Algebra

***EYNTKA* Series**

Nathanael Chwojko-Srawley

October 28, 2026

Contents

Contents **3**

Preliminary Chapter **i**

0.1 Sets i

0.1.1 Propositions and Predicates vi

0.1.2 Induction xii

0.1.3 *Pigeon-hole Principle xii

0.1.4 Relations and Equivalence Relations xii

0.1.5 Functions xv

0.1.6 Adding Structures to Sets xxv

0.1.7 *Cardinality xxvi

0.2 Number Theory xxvii

0.2.1 GCD and Euclidean Algoritm xxvii

0.2.2 Modular Arithmetic xxxi

0.2.3 Counting Problems xxxv

0.3 Graphs xxxvii

0.4 Categories xxxviii

0.4.1 Important Concepts xxxix

0.5 Matrices xliii

I Groups **1**

1 Introduction to Groups **7**
1.1 Basic Properties and Definitions . . . 7
1.1.1 Consequences of Group Axioms . . . 15
1.2 Examples of Groups . . . 22
1.2.1 Integers Modulo n and Cyclic Groups . . . 22
1.2.2 Symmetric Groups . . . 27
1.2.3 Dihedral Groups . . . 35
1.2.4 Quaternion Group . . . 39
1.2.5⋆ Matrix Groups . . . 41
1.3 Generators and Relations . . . 43
1.4 Homomorphisms and Isomorphisms . . . 46
1.4.1 Homomorphisms . . . 47
1.4.2 Isomorphisms . . . 56
1.5 Symmetry and Transformations: A Prelude to Group Actions . . . 64
1.6 Cayley Graphs . . . 67

2 Sub Groups and Generating Groups **71**
2.1 Basic Definition and Properties . . . 71
2.2 Examples of Subgroups . . . 73
2.2.1 Kernel and Image . . . 73
2.2.2 Center, Centralizers, and Normalizers . . . 75
2.3 Subgroups Generated by Subsets . . . 80
2.3.1 Cyclic Groups and Cyclic subgroups . . . 80
2.3.2 Generating Subgroups . . . 87
2.3.3 Free Groups . . . 91
2.3.4 Free Abelian Group . . . 101
2.3.5 *Free-Forgetful Adjoint . . . 101
2.4 Subgroup Lattices . . . 102
2.5 *Universal Property of the Kernel . . . 106

3 Homomorphisms and Quotient Groups **109**
3.1 Quotient Groups . . . 110
3.2 Presentations . . . 122
3.3 Application to Finite Groups . . . 125
3.4 Internal Direct Product . . . 129

3.5 Isomorphism Theorems . . . 131
3.6 Extensions . . . 139
3.7 Classifying all Finite Groups: Hölder Program . . . 142

4 Group Actions 149
4.1 Definitions and First Examples . . . 150
4.2 Orbits, Stabilizers, and the Kernel . . . 156
4.3 The Orbit-Stabilizer Theorem . . . 163
4.4 Types of Actions . . . 168
4.5 Action by Left Multiplication . . . 173
4.6 Action by Conjugation and the Class Equation . . . 178
4.7 Automorphisms and Inner Automorphisms . . . 184
4.7.1 Characteristic Subgroups . . . 188
4.8 Sylow's Theorems . . . 189
4.9 Applications of Sylow's Theorems . . . 195
4.9.1 Simplicity of A_5 . . . 198
4.10 Summary . . . 201
4.11⋆Group Actions in Advanced Mathematics . . . 204
4.11.1 Representation Theory . . . 204
4.11.2 Algebraic Topology . . . 205
4.11.3 Category Theory . . . 205

5 Building Groups: Direct and Semi-Direct Products 207
5.1 Classical Definitions And Properties . . . 207
5.1.1 Fundamental theorem of Finitely Generated Abelian Groups . . . 209
5.2 Recognizing Direct Products . . . 211
5.2.1 A word on Perfect Groups . . . 215
5.3 Semi-Direct Products . . . 215
5.4 A Categorical approach of the Product . . . 224
5.4.1 The dual of the Product . . . 227
5.4.2 Universal Property of Semi-Direct Products . . . 231

6 Further Topics in Group Theory 233
6.1 Generalization of Abelian Groups . . . 233
6.1.1 Solvable Groups . . . 235
6.1.2 Nilpotent Groups . . . 239
6.1.3 Polycyclic Groups . . . 245

6.2 Non-finitely generated abelian groups . . . 246
6.3 Linear Groups . . . 246

7 Generalization of Groups 247
7.1 Monoid . . . 247
7.2 Groupoid . . . 251

8 Category of Group 253
8.1 Basic properties of Morphisms . . . 259
8.2 Commutative diagrams . . . 263
8.3 Summary . . . 264

II Rings 265

9 Introduction To Rings 269
9.1 Basic Properties and Definitions . . . 270
9.1.1 Category of Ring . . . 284
9.1.2 Summary . . . 287
9.2 Examples of Rings . . . 289
9.2.1 Polynomial Rings . . . 289
9.2.2⋆ Formal Power Series . . . 294
9.2.3 Matrix Rings . . . 299
9.2.4 Group Rings . . . 300
9.3 Ring Homomorphisms and Quotient Rings . . . 301
9.4 Properties and Further Structures of Ideals . . . 313
9.4.1 Operations and Generation on Ideals . . . 313
9.4.2 Ideals and Units . . . 320
9.4.3 Maximal Ideals . . . 322
9.4.4 Prime Ideals . . . 324
9.5 Ring of Fractions: Localization . . . 327
9.5.1 The Real Numbers Are Not Algebraic over Q . . . 332
9.6 Chinese Remainder Theorem . . . 333
9.7⋆ Monoidal Objects . . . 337

10 Exploring Integral Domains: Factorization and Valuation 339
10.1 Factorization . . . 341
10.1.1 Example of Atomic Domains: Noetherian Domains . . . 347

10.1.2 Unique Factorization Domains . . . 351
10.1.3 Important UFD: Principle Ideal Domains . . . 357
10.2 Euclidean Domains . . . 361
10.3 Application: Sums of Primes and Gaussian Integers . . . 371

11 Exploring Polynomial Rings **379**
11.1 Polynomial Rings over Fields . . . 380
11.2 Polynomial Rings over UFD's . . . 383
11.3 Irreducibility of Polynomials . . . 386

III Modules **397**

12 Introduction to Modules **401**
12.1 Basic Definitions and Examples . . . 402
12.1.1 Vector-spaces . . . 407
12.1.2 Algebras . . . 409
12.1.3 Abelian Groups as Modules . . . 414
12.2 Homomorphism and Quotients of Modules . . . 415
12.2.1 Extensions and Exactness . . . 422
12.3 Generation of Modules . . . 424
12.3.1 Direct Sum of Modules . . . 425
12.3.2 Free Modules . . . 433
12.3.3 Presentations and Resolutions . . . 442
12.3.4 Finitely Generated Modules and Noetherian Modules . . . 445
12.3.5 Direct Sums and Homomorphisms . . . 448

13 Modules over Fields: Vector Spaces and Linear Algebra I **451**
13.1 Vector Spaces and their Properties . . . 452
13.1.1 Quotient Spaces and Subspaces . . . 460
13.2 Linear Transformations and Matrix Representation . . . 466
13.2.1 Change of Basis . . . 471
13.2.2 Similarity . . . 474
13.2.3 Gaussian Elimination: Finding a Nice Basis . . . 476
13.2.4 Geometric Result: Systems of Linear Equations . . . 484
13.2.5 Use Case: Reading Presentations . . . 490
13.3 Dual Spaces and Forms . . . 490

13.3.1 Dual Spaces . . . 491
13.3.2 Prelude to Adjoints of Vector Space . . . 500
13.3.3 Functor of Points for Vector Spaces . . . 501
13.3.4 Multilinear Forms . . . 503
13.4 Linear Operators Invariants: Trace and Determinant . . . 507
13.5 Eigenvectors and Characteristic Polynomial . . . 516
13.6 Geometry and Inner Product . . . 525

14 Modules Over PIDs: Linear Algebra II **527**
14.1 Over PID, Submodule of Free Module is Free . . . 529
14.2 Application: Linear Algebra revisited . . . 543
14.3 Rational and Jordan Canonical Form . . . 548
14.3.1 Converting a square matrix to Rational Canonical Form . . . 554
14.4 Jordan Canonical Form . . . 558
14.4.1 Changing From one Canonical Form to Another . . . 564
14.4.2 Computation: Convert to JCF . . . 564
14.5 The Jordan-Chevalley Decomposition . . . 564

15 Tensor Products Of Modules: Linear Algebra III **573**
15.1 The Tensor Product of Modules . . . 573
15.2 Properties of the Tensor Product . . . 582
15.3 Extension of Scalars . . . 597
15.4 Application: The Kronecker Product . . . 602
15.5 Summary . . . 609

16 Multilinear Algebra **613**
16.1 Multilinear, Symmetric and Alternating Maps . . . 613
16.2 Graded Rings and Graded Modules . . . 619
16.3 The Tensor, Symmetric and Exterior Algebras . . . 625
16.4 Bases, Ranks and the Determinant . . . 631
16.5⋆The Koszul Complex . . . 637
16.6 Summary . . . 642

17⋆Projective, Injective and Flat Modules **645**
17.1 Exact Sequences, Splitting, and the Extension Problem . . . 645
17.1.1 Maps Between Short Exact Sequences . . . 648
17.1.2 Split Sequences . . . 652

17.2 Projective Modules . . . 656
17.3 Injective Modules . . . 665
17.3.1 Embedding a Module in an Injective . . . 672
17.3.2 Injective Hulls . . . 674
17.4⋆Divisible Groups . . . 677
17.5 Flat Modules . . . 683
17.6 Ext and Tor . . . 688
17.6.1 Complexes and Their Homology . . . 689
17.6.2 The Construction . . . 689
17.6.3 What They Repair . . . 692
17.6.4 The Extension Problem, Answered . . . 693
17.7 Summary . . . 695

18⋆Morita Theory **699**
18.1 Generators and Progenerators . . . 699
18.2 Morita's Theorem . . . 703
18.3 Morita Invariants and the Basic Algebra . . . 709

IV Fields **715**

19 Field Theory **719**
19.1 Properties of Fields . . . 719
19.2 Field Extensions . . . 726
19.2.1 Isomorphism of Fields Extensions . . . 740
19.3 Algebraic Extensions . . . 745
19.4 Historical Detour: Straightedge and Compass Construction . . . 755
19.5 Closures of Fields . . . 758
19.5.1 Algebraic Closure . . . 758
19.5.2 Splitting Field and Normal Extensions . . . 764
19.6 Separable Extensions . . . 772
19.6.1 Separability and Embeddings . . . 778
19.6.2 Separability and Simple Extensions . . . 782
19.6.3 Important Functional: Resultant and Discriminant . . . 786
19.7 Application: Cyclotomic Extensions and Finite Fields . . . 795
19.7.1 Cyclotomic Polynomials and Fields . . . 795
19.7.2 Finite Fields . . . 802

20 Galois Theory **809**
20.1 Galois Extension and Galois Group . . . 815
20.1.1 Galois Correspondence . . . 822
20.1.2 Composite Fields . . . 835
20.1.3 A bit of Character Theory and Kummer Theory . . . 839
20.2 Application of Galois Theory . . . 844
20.2.1 Fundamental Theorem of Algebra . . . 844
20.2.2 Construction of Regular n-gon . . . 847
20.2.3 Symmetric Functions . . . 847
20.2.4 Solvability By Radicals . . . 851
20.3 Galois Groups of Polynomials . . . 855
20.4 Kummer Theory and Artin-Schreier Extensions . . . 858

21 ⋆More Structures on Fields **869**
21.1 Ordered and Real Fields . . . 870
21.1.1 The Fields That Carry a Geometry . . . 880
21.2 Absolute Values on General Fields . . . 881
21.2.1 Ostrowski Theorem . . . 888
21.3 Derivation on Field . . . 888

22 ⋆Bilinear, Quadratic and Alternating Forms over a Field **897**
22.1 Quadratic Forms and Symmetric Bilinear Forms . . . 897
22.2 Diagonalization and Orthogonal Bases . . . 903
22.3 Alternating Forms, the Linear Darboux Theorem, and Lagrangians . . . 906
22.4 Isotropy, the Hyperbolic Plane, and Witt Decomposition . . . 915
22.5 Witt Cancellation and Witt's Extension Theorem . . . 924
22.6 The Witt Group . . . 935
22.7 The Clifford Algebra . . . 945

V Commutative Algebra **955**

23 Noetherian Rings, Hilbert's Basis Theorem, and Localization **959**
23.1 Noetherian Rings and Modules . . . 959
23.2 Hilbert Basis Theorem . . . 962
23.3 Gröbner Bases . . . 966
23.4 Localization . . . 969

23.4.1 Localization of Rings . . . 970
23.4.2 Localization of Modules . . . 976
23.4.3 Local Properties . . . 979
23.4.4 Local Rings . . . 983
23.4.5 Nakayama's Lemma . . . 985

24 Primary Decomposition and Associated Primes 993
24.1 Primary Ideals . . . 993
24.2 Primary Decomposition . . . 996
24.3 Associated Primes . . . 996
24.4 The Lasker-Noether Theorem . . . 997
24.5 Support and the Isolated Components . . . 999
24.6 Localization and Primary Decomposition . . . 1001

25 Completion 1003
25.1 Constructing Completions . . . 1004
25.2 Filtrations . . . 1012
25.3 More on Graded Algebras . . . 1013
25.4 Artin-Rees Lemma . . . 1015
25.5 Associated Graded Rings: Noetherian Closed under Completion . . . 1020
25.6 The Cohen Structure Theorem . . . 1024
25.7 Weierstrass Preparation and Division . . . 1025

26 Ring Extension and Integral Extension 1027
26.1 Ring and Integral Extensions . . . 1027
26.2 Extension and Contraction of Ideals . . . 1035
26.3 Integral Extensions and Prime Ideals . . . 1038

27 Valuation Ring and Local Rings 1043
27.1 Valuations . . . 1043
27.2 Discrete Valuation Ring . . . 1046

28 Artinian Rings 1055
28.1 Artinian Rings and Modules . . . 1055

29 Dimension Theory 1063
29.1 Noether Normalization . . . 1063
29.2 Krull Dimension . . . 1064

29.3 The Hilbert-Samuel Function . . . 1064
29.4 The Dimension Theorem . . . 1066
29.5 Systems of Parameters and Krull's Principal Ideal Theorem . . . 1067
29.6 Dimension and Transcendence Degree . . . 1068
29.7 Catenary Rings and the Height Formula . . . 1069
29.8 Regular Local Rings . . . 1072
29.9 Regular Local Rings Are Factorial . . . 1076
29.10Normal Domains in Codimension One . . . 1080

30 Flatness and Faithfully-Flat Descent **1083**
30.1 Flat Modules . . . 1083
30.2 Faithfully Flat Modules and Algebras . . . 1084
30.3 Faithfully-Flat Descent . . . 1085
30.4 The Local Criterion for Flatness . . . 1086
30.5 Fitting Ideals . . . 1086
30.6 Generic Flatness . . . 1092

VI Affine Varieties **1093**

31 Algebraic Sets and the Zariski Topology **1097**
31.1 Affine Space and Regular Functions . . . 1097
31.2 Algebraic Sets and Vanishing Ideals . . . 1100
31.3 The Zariski Topology . . . 1111
31.4 Regular Maps and Continuity . . . 1115

32 The Algebra-Geometry Dictionary **1121**
32.1 Coordinate Rings . . . 1121
32.2 Radical Ideals . . . 1127
32.3 Irreducibility and the Decomposition Theorem . . . 1129
32.4 Hilbert's Nullstellensatz . . . 1132
32.5 The Dictionary . . . 1137

33 Rational Maps and Birational Classification **1141**
33.1 Rational Functions and the Function Field . . . 1141
33.2 Domains of Definition and Local Rings . . . 1143
33.3 Rational and Birational Maps . . . 1146
33.4 Classification up to Birational Equivalence . . . 1152

VII Local Properties 1157

34 Dimension **1161**

34.1 What Dimension Should Mean . . . 1161
34.2 Krull Dimension and Transcendence Degree . . . 1163
34.3 Codimension, Curves, and Surfaces . . . 1165
34.4 Hypersurface Sections and Codimension One . . . 1167

35 Smooth Points and Regular Local Rings **1171**

35.1 The Tangent Space Bound . . . 1171
35.2 The Jacobian Criterion and Regular Local Rings . . . 1172
35.3 The Singular Locus . . . 1174
35.4 Homological Characterization: Serre's Theorem . . . 1175
35.5 Regular Local Rings in Dimension One . . . 1176

36 Tangent Cones and Completions **1179**

36.1 The Tangent Cone and Multiplicity . . . 1179
36.2 Completion and Local Parameters . . . 1183
36.3 Formal Branches . . . 1185
36.4 Local Factoriality and Weil Divisors . . . 1187

37 Normal Varieties and Normalization **1191**

37.1 Integrally Closed Domains and Normal Varieties . . . 1191
37.2 The Normalization of an Affine Variety . . . 1193
37.3 Curves, Function Fields, and Discrete Valuation Rings . . . 1195
37.4 Normality and the Serre Conditions . . . 1197
37.5 Weil Divisors and the Class Group . . . 1199

VIII Projective Varieties 1203

38 Projective Space and Homogeneous Ideals **1207**

38.1 Points at Infinity . . . 1207
38.2 Projective Space and Homogeneous Polynomials . . . 1210
38.3 The Affine Cone and Homogenization . . . 1215
38.4 The Projective Nullstellensatz and Irrelevant Ideals . . . 1223
38.5 The Hilbert Function of a Projective Variety . . . 1224

39 Quasi-Projective Varieties and Regular Maps **1229**
39.1 The Affine Cover of Projective Space . . . 1229
39.2 Projective Closure . . . 1232
39.3 Quasi-Projective Varieties . . . 1237
39.4 Regular Maps . . . 1239
39.5 Rational Functions on Quasi-Projective Varieties . . . 1243

40 Completeness and Finite Maps **1245**
40.1 Products and the Segre Embedding . . . 1245
40.2 Completeness of Projective Varieties . . . 1249
40.3 Finite Maps . . . 1253
40.4 Noether Normalization, Geometrically . . . 1256
40.5 Dimension of Fibres . . . 1258
40.6 The Dimension of an Intersection . . . 1260

41 Projective Embeddings and Constructible Sets **1263**
41.1 The Veronese Embedding . . . 1263
41.2 Grassmannians and the Plücker Embedding . . . 1266
41.3 Constructible Sets and Chevalley's Theorem . . . 1267
41.4 Application: Lines on a Cubic Surface . . . 1269
41.5 Degree, Linear Sections, and Bézout in $\mathbb{P}^n$ . . . 1272
41.6 Cones, Projections, and Secant Varieties . . . 1274

IX Curves **1279**

42 Intersection Multiplicity **1283**
42.1 Plane Curves, Multiplicity, and Tangent Lines . . . 1283
42.2 Local Rings of Plane Curves . . . 1287
42.3 The Intersection Number . . . 1291
42.4 Computing Intersection Numbers . . . 1296

43 Bézout's Theorem and Max Noether's Theorem **1299**
43.1 Bézout's Theorem . . . 1299
43.2 Consequences and Bounds on Multiplicity . . . 1302
43.3 Max Noether's Fundamental Theorem . . . 1305
43.4 Application: Pascal's and Pappus's Theorems . . . 1308
43.5 The Dual Curve and Plücker's Formulas . . . 1310

44 Divisors on Curves **1313**
44.1 Divisors and Their Degree . . . 1313
44.2 Principal Divisors and Linear Equivalence . . . 1315
44.3 The Picard Group . . . 1318
44.4 The Genus of a Plane Curve . . . 1319

45 The Group Law on Cubic Curves **1323**
45.1 The Chord-Tangent Construction . . . 1323
45.2 The Group Law via the Picard Group . . . 1327
45.3 Independence of the Base Point . . . 1328

46 Differential Forms and the Canonical Class **1331**
46.1 Differential Forms on a Variety . . . 1331
46.2 The Canonical Class . . . 1333

47 Blowing Up and Resolution of Curve Singularities **1337**
47.1 The Blow-Up of the Plane at a Point . . . 1337
47.2 Blowing Up a Variety Along a Subvariety . . . 1339
47.3 Resolving Plane Curve Singularities . . . 1340
47.4 Multiplicity, Genus, and the Effect of Blowing Up . . . 1343
47.5 Cubic Surfaces and the Twenty-Seven Lines . . . 1345

48 Riemann-Roch for Plane Curves **1349**
48.1 The Space of Functions with Prescribed Poles . . . 1350
48.2 Riemann's Theorem . . . 1351
48.3 The Canonical Divisor and Riemann-Roch . . . 1352
48.4 Application: Curves of Low Genus . . . 1354

49 What Next? **1357**

50 Relating Algebra to Number Theory **1361**
50.1 Ring of Integers . . . 1363
50.1.1 Functionals: Field Trace and Field Norms . . . 1368
50.1.2 Functionals: Discriminant . . . 1375
50.1.3 Abelian Group Structure . . . 1383
50.1.4 Lattice Structure: Geometry of Number Rings . . . 1396
50.2 Ring Structure and Dedekind Domains . . . 1410
50.2.1 Fractional Ideals in Rings . . . 1415

50.2.2 Prime Decomposition in Dedekind Domain . . . 1419
50.2.3 Class Group of Ring of Integer . . . 1426
50.2.4 Dirichlet's Unit Theorem . . . 1434
50.3 Extension of Dedekind Domains and Number Fields . . . 1441
50.3.1 Ideal Correspondence in Extension . . . 1444
50.4 Prime Factorization in Extension . . . 1453
50.4.1 Example: Eisenstein Polynomials . . . 1466
50.4.2 Primes in Galois Extensions . . . 1471
50.4.3 Detecting Ramification . . . 1488
50.4.4 Frobenius Automorphism . . . 1501
50.4.5 Example: Cyclotomic Fields . . . 1502
50.4.6 Application: Quadratic Extensions and Quadratic Reciprocity . . . 1506
50.5 Application: Kronecker Weber Theorem . . . 1512
50.6 *Modules Over Dedekind Domains . . . 1519
50.7 *Geometric Idea: 1-Dimensional Schemes . . . 1521
50.7.1 Localization of Dedekind Domains . . . 1521
50.7.2 Orders: Curves with Singularities . . . 1521
50.8 *Profinite Groups . . . 1523
50.8.1 Profinite Groups . . . 1524
50.8.2 Infinite Galois Theory . . . 1528

X Representation Theory 1533

51 Semisimple Rings and Modules 1537
51.1 Decomposing Modules . . . 1538
51.2 Artin-Wederburn . . . 1547
51.3 Central Simple Algebras . . . 1560
51.3.1 Brauer Group . . . 1566
51.4 Build up to Quaternion Algebras . . . 1568

52 The Jacobson Radical and Non-Semisimple Algebras 1571
52.1 The Jacobson Radical . . . 1572
52.2 Indecomposable Modules and Krull-Schmidt . . . 1580
52.3 Idempotents, Projective Covers, and the Regular Representation . . . 1588

53 Representation of Finite Groups 1599

53.1 Representations of Finite Groups . . . 1599
53.2 Character Theory . . . 1614
53.2.1 More Character Tables . . . 1632
53.2.2 Burnside's Theorem . . . 1635
53.3 Induced Representation . . . 1638
53.4 *Application to Harmonic Analysis . . . 1645
53.4.1 Generalization to Locally Compact Abelian Groups . . . 1655
53.4.2 The Algebraic-Geometric Meaning of the Dual Group . . . 1657
53.5⋆Modular Representations and the Failure of Semisimplicity . . . 1659

54 Quiver Representations and Path Algebras 1667
54.1 Quivers and Their Decomposition . . . 1668
54.1.1 Quiver Representation and Varieties . . . 1670
54.1.2 Decomposing Quivers . . . 1676
54.1.3 The Tits Form and Its Roots . . . 1677
54.1.4 Gabriel's Theorem . . . 1692
54.1.5 Path Algebra of Quivers . . . 1704
54.2 Bound Quiver Algebras . . . 1712

XI Homological Algebra 1723

55 Abelian Categories 1731
55.1 Definitions and Properties . . . 1731
55.2 Localization of Categories . . . 1739
55.2.1 Serre Subcategories and the Quotient . . . 1743

56 Complexes and (co)Homology 1747
56.1 Basic Definition and Properties . . . 1748
56.1.1 Homology and Cohomology . . . 1753
56.1.2 Snake Lemma . . . 1759
56.1.3 Chain Homotopies and Homotopic Categories . . . 1766
56.2 Projective and Injective Resolutions . . . 1777
56.2.1 Resolutions . . . 1784
56.2.2 Derived Category with Enough Projectives . . . 1787
56.3 Derived Functors: Ext and Tor . . . 1790
56.3.1 Derived Functor . . . 1791

56.3.2 Long Exact Sequences of Derived Functors . . . 1793
56.4 δ-Functors and Grothendieck's Effaceability Criterion . . . 1809
56.5 Double Complexes . . . 1818
56.5.1 Applications to Computations of Ext and Tor . . . 1828

57 The Derived Category **1831**
57.1 Triangulated Categories . . . 1831
57.2 The Derived Category as a Triangulated Category . . . 1840
57.2.1 Stable Module Theory . . . 1849
57.3 Adapted Classes and Total Derived Functors . . . 1850
57.4 RHom and the Derived Tensor Product . . . 1856

58 Applications of (co)Homology **1873**
58.1 Group Cohomology . . . 1874
58.2 Homological Dimension . . . 1889
58.2.1 Projective and Global Dimension . . . 1890
58.2.2 Dimension of Local Rings . . . 1895
58.2.3 Beyond Regularity: The Hierarchy of Singularities . . . 1900
58.2.4 Cohen-Macaulay Rings . . . 1904
58.3 Serre's Criterion for Normality . . . 1907
58.4 The Local Criterion for Flatness . . . 1908
58.5 The Limit of a Tower and Its First Derived Functor . . . 1911

59 Unbounded Derived Categories and t-Structures **1919**
59.1 Grothendieck Abelian Categories and K-Injective Resolutions . . . 1920
59.2 K-Flat Complexes and the Unbounded Tensor-Hom Adjunction . . . 1935
59.3 Truncation in the Derived Category . . . 1950
59.4 t-Structures and Their Hearts . . . 1959

60 Spectral Sequences **1975**
60.1 Exact Couples and Derived Couples . . . 1975
60.2 The Spectral Sequence of a Filtered Complex . . . 1984
60.3 The Two Spectral Sequences of a Double Complex . . . 1998
60.4 Hypercohomology . . . 2002
60.5 The Grothendieck Spectral Sequence . . . 2011
60.6 Filtered Complexes and the Filtered Derived Category . . . 2015

XII Category Theory 2025

61 Categories, Functors, and Natural Transformations 2029

61.1 Categories, Morphisms, and Size . . . 2030
61.2 Isomorphisms, Monomorphisms, and Epimorphisms . . . 2035
61.3 Duality and Opposite Categories . . . 2041
61.4 Functors . . . 2046
61.5 Natural Transformations . . . 2050

62 The Yoneda Lemma and Representability 2059

62.1 Representable Functors . . . 2059
62.2 The Yoneda Lemma . . . 2063
62.3 The Yoneda Embedding . . . 2067
62.4 Applications . . . 2070

63 Universal Properties, Limits, and Colimits 2075

63.1 Universal Properties and Universal Arrows . . . 2075
63.2 Limits . . . 2079
63.3 Colimits . . . 2084
63.4 Computing (Co)limits . . . 2089

64 Adjunctions 2097

64.1 Adjoint Functors . . . 2097
64.2 Examples of Adjunctions . . . 2103
64.3 Units, Counits, and Preservation . . . 2107
64.4 Adjoint Functor Theorems . . . 2111

65 Monads and their Algebras 2117

65.1 Monads from Adjunctions . . . 2117
65.2 Algebras for a Monad . . . 2121
65.3 The Kleisli Category . . . 2126
65.4 Monadicity . . . 2131

66 Kan Extensions 2135

66.1 Left and Right Kan Extensions . . . 2135
66.2 The Pointwise Formula . . . 2138
66.3 All Concepts are Kan Extensions . . . 2143
66.4 Ends, Coends, and Density . . . 2145

67 Monoidal Categories **2151**
67.1 Monoidal Categories and Coherence . . . 2151
67.2 Braided and Symmetric Monoidal Categories . . . 2156
67.3 Closed Monoidal Categories . . . 2159
67.4 Monoids, Comonoids, and Duality . . . 2163

68 Enriched and 2-Categories **2169**
68.1 Enriched Categories . . . 2169
68.2 Enriched Functors and Naturality . . . 2172
68.3 Enriched Functor Categories and Weighted Limits . . . 2176
68.4 Strict 2-Categories . . . 2182
68.5 Toward Weak and Higher Categories . . . 2188

XIII Appendix **2193**

A Axiom of Choice **2197**
A.1 Build-up . . . 2198
A.2 Axiom of Choice Equivalences . . . 2201
A.3 Zorn's Lemma . . . 2206
A.4 The Schröder-Bernstein Theorem . . . 2207

B Sub-Group of a Free Group is Free **2209**
B.1 Using Cosets . . . 2209
B.2 Using Tree's . . . 2213

C Basic Topology and Topological Groups **2215**
C.1 Definition and Properties . . . 2215
C.2 Construction Topologies . . . 2223
C.3 Compactness and Connectedness . . . 2225
C.4 Topological Groups . . . 2226
C.5 Completion in Topology . . . 2231

D Lattice Theory **2237**
D.1 Lattice Theory . . . 2237

E Model Theory **2257**
E.1 Löwenheim-Skolem Theorem . . . 2257

XIV Glossary, Index, Bibliography **2259**

Index **2266**

0.0.1 Reading the numbering A star marks *bonus material*: a chapter, section or subsection that belongs in the book but that nothing later depends on. Skipping it costs nothing downstream. The star sits on the number, as in §2.7⋆; in divisions written before this convention it sits at the front of the title instead, as in **Uniform Spaces*. The two mean the same thing.

The title of the book says it all: the intention is that you will find "everything you need to know about undergraduate algebra" in these many pages. I chose the word "everything" purposefully knowing it is a contentious word, especially in the range of material that is considered at the undergraduate level. In some universities, only the first few chapters of this book are considered part of the undergraduate curriculum, while at others the entirety of the books content and more is available in the undergraduate program. Thus, parameters had to be set in choosing the material of this book while trying to remain true in using the word "everything" – they are the following:

1. By the end of the book, or any part of the book (ex. part on Groups, Rings, Modules, etc.), the reader should have had a deep enough understanding and intuition so as to be able to tackle graduate level mathematics. The reader should be comfortable with picking up almost any graduate level book in algebra, including topics like algebraic number theory, algebraic geometry, representation theory, lie theory, classical or geometric group theory, ring theory, homological algebra, and so forth.

2. By the end of the book, the reader should be comfortable to think in any (or at least most) major algebraic studies, to be able to more than just recite definitions and systematically follow proofs but to have a connection with the definition and the way of thinking that allowed the mathematician to come up with the proofs and ideas, which will hopefully encourage the reader to start thinking like a mathematician. The goal is that the reader has a deep pool of examples, mental structures, and intuitions that they can draw on to come up with their own ideas.

3. By the end of the book, the reader should get a sense of how interconnected mathematics is. There is over a thousand cross-references in the book interconnecting all parts of it together, and a mathematical language will be introduced early on that will allow the reader to study the connection between objects.

4. By the end of this book (or any section), the reader should be comfortable solving problems (or problems from that section). To achieve this, many exercises are added throughout the end of sections in the book. Doing as many as necessary to get comfortable with the material is very important; reading a math book and not doing the exercises is like reading a cook book without cooking – you will not get to taste the result. It is common to have a fake sense of understanding or a lack of intuition if exercises are skipped (I say this out of personal experience and that of many of the colleagues I have worked with).

Thus, in order to achieve these goals, the book is on the larger side of textbooks, and covers most of "core algebra" of undergraduate curriculums as well as most "optional" courses in algebra many undergraduate curriculum's offer. To insure the book stays within the scope of undergraduate knowledge, only material that I have personally covered or have learned about during my undergraduate years are included. Since algebra is my favourite topic, I have taken as many optional algebra courses and read as many books as possible on the subject, and so I wish to think that I have covered enough of a broad range of topics in great enough depth to use my personal experience to be a benchmark for the quantity of material[1]. There is also the question of what should be assumed to be the starting point. The solution I have done is the same as many authors solutions: have a preliminary chapter that assumes only an elementary level of knowledge of mathematics (for this book, knowledge of arithmetic's and factorization) and cover all necessary prerequisite material that will be used in the book. The preliminary chapter in this book is more extensive than most preliminary chapter to

[1]This also means that I chose to start considering some material as beyond the scope of undergraduate algebra, such as scheme theory and class field theory (dissuasion of omitted material at the end of this section)

insure the reader has no "knowledge gaps". In any case, I hope that the reader will find this textbook a useful accompaniment throughout their undergraduate studies in algebra.

Properties of the Book

The book covers a great multitude of topics and structures (there are at least 21 different structures in this book, including groups, rings, modules, sets, graphs, and so forth), which not only overlap in many important ways but also constantly interconnect, describe, and influence each other. Part of the goal of this book is to show how interconnected mathematics and algebra is, and so to accomplish this goal a light-version of category theory is introduced early on and gradually built upon throughout the book. It is the opinion of this author that shying away from all category theory (as some textbooks I have read have done) delays many interesting and important connections between so many parts of algebra, and gets rid of the opportunity to foreshadow some amazing results[2]. Naturally, the full generality of category theory is not needed. Similarly to how set theory is not introduced in terms of the Zermelo-Frenkel axioms but as naïve set theory, so too is category theory introduced in a simplified version, giving a sufficient amount of language and tools to study how mathematical objects interconnect while not overloading on the generalities and technicalities. Some key tools and vocabulary that will be introduced early on is that of universal properties and functors. Throughout the book, there are hundreds of instances of universal properties and functors being used, showing how pervasive of a tool they are in algebra and mathematics as a whole. Gaining an intuition by seeing these concepts naturally appear gradually but early is useful to gain deeper insights.

Each part and chapter of the book will start off with some motivation for the material. To accommodate many different learning styles, many forms of motivation are given, from historical context, to practical application, to important consequences, to how the material is connected to other areas of mathematics. The idea is to have the reader already start making connections while reading the main material. This is an approach that contrasts with Bourbaki which aims to present material minimally and coarsely, omitting any of the authors intuitions or insights with the goal of creating a standard for mathematics. This book is not intended to be an encyclopedia for senior mathematicians to double-check their notation understanding of some concepts, but to be a fun and interesting yet deep and insightful pedagogical tool to encourage the reader to build up their understanding and make as many connections as possible while challenging the readers ways of thinking by actively engaging in the interpretation of the material. Though the intuitions of this author will be present, it is my hope that the book will be written in such a way that the reader will develop their own intuition, solidifying in their own way what the material of this book has to offer.

The end of each chapter will contain a summary section. This summary serves both as a chance for readers to insure they have memorized the core ideas of the chapter, as well as a litmus test for readers coming from other EYTNKA books that reference a chapters in this book.

This book is an algebra textbook, and so avoids covering material outside of algebra. However, since mathematics is a very interconnected discipline, it is sometimes impossible to avoid talking about other domains of mathematics. As an example of the interconnectedness of mathematics, many definitions will have examples that lie in different domains of mathematics. Thus, it will not be uncommon that examples of definitions will be given that are not strictly algebraic, however there will always be an algebraic example accompanying a non-algebraic example, since the book should

[2]For example, Cayley's theorem, the existence of a homomorphism from any ring R to $\mathrm{End}_{\mathbf{Grp}}(R)$, or representation theory in general are all naturally connected via Yonneda's lemma. Another example would be the plethora of adjoints

have no prerequisites besides what is covered in the preliminary chapter. It will be necessary to cover some non-algebra material at the preliminary stage and late stage of the book. For the preliminary stage, it will be necessary to cover some basics of [naïve] set theory, number theory, graph theory, and logic. Elementary concepts not needed for algebra (such as supremum, limits, completeness of $\mathbb{R}$) are not covered, and concepts that play a tangential role (such as cardinality) will be left as optional. In the later stages of the books (starting near the end of part IV on page 1523), topology and geometry will start getting a more prominent role. Since these topics are so far into the book, it is perhaps not too wrong to think that the reader has a great interest in mathematics as a whole and has already covered some basics of topology, or perhaps even differential geometry. Looking through the curriculum of many universities, it seems that differential geometry is usually covered quite late, while topology is either taught as part of a 2nd or 3rd year analysis or as a separate course. Thus, the book will not rely on geometric thinking, however it will start to casually incorporate topological thinking and results to relevant theorems (which will be relatively few), starting in part V. A review of topology is given in appendix C. Finally, some intuition on the notion of the real numbers $\mathbb{R}$ and the Pythagorean theorem shall start appearing at chapter 13 for very few results.

A convention that is prominent in this book is that square brackets around words indicate that the word can be used to eliminate ambiguity. For example, we will define functions in the preliminary chapter. But in other domain of mathematics, the term function is used differently (ex. the definition of *function* in differential geometry would be defined as *real-valued function* in the preliminary chapter). Thus I will put a word in square parenthesis to show that the word can be added to the term to eliminate ambiguity. For example, though we will always say *function* throughout this book, where it might be ambiguous in general mathematical contexts and in the definition it will be written as *[set] function*.

Another convention will be that sections that have a starred in front of their title are consider as "optional". This is material that does not fit in the appendix, which is material that fills in more advanced gaps for the curious reader (ex. properties of the Axiom of Choice, or topological interpretations of some results), while at the same time not being central to the main narratives of the chapter. They were included as side-quests for the interested readers, but the reader who is not interested can comfortably skip the section without worry of it being referenced later in the book. The exception to this referencing rule is the starred sections in the preliminary chapter; these shall only be referenced for a hand-full of proofs in the book.

The book shall also try to mix classical and modern motivation for the study of each given field. For example, Galois groups have a classical motivation in understanding the symmetries of roots of equation, while they also have a modern motivation in containing the structural information of primes or of being the right analogue of the fundamental group. The classical motivation shall often be the doorway that makes it easy to start having an interest in a certain theory, while the modern motivation explains why this theory persists in being interesting into present mathematical research. More modern motivations for the theories that will be presented shall become more prevalent in latter parts of the book and left as boxes for more advanced readers in the earlier parts of the book.

(mention how a lot of the footnotes are are for a 2nd reading).

Finally, as the reader goes through the book, they will gain skills and intuitions for solving many problems. Many of these skills will come from reading through all the proofs of the results, as well as the reader doing the exercises. Eventually, many of the results boxed as propositions, lemmas, and corollaries will stop being proved in detail and have part or all of it left as exercises (starting around 300 pages into the book). This pattern shall become more prominent as the reader progresses through the book and gains "mathematical maturity". This pattern reflects the changing pedagogical

need of the reader as they progress through the book; it shall become more fruitful for the reader to prove results on their own rather than having the detail laid out. In fact, at that stage of the book the reader may even find that it is easier to prove the results themselves, or feel it is cumbersome to read through a proof they can do themselves[3].

Exercises There are very few exercises in this textbook as compared a proper textbook. This will be remedied in the 1st edition.

Conventions

If any of the notation is unclear, the preliminary chapter will cover it in more detail.

- Notation $x = a, b$ is shorthand for $x \in \{a, b\}$. If S is a clearly enumerable set (ex. $S = \{1, 2, 3, 4, 5, 6, 7\}$, then we shall sometimes write $x = 1, .., 7$ to mean $x \in S$.
- (convention on fields notation (k vs K vs $\mathbb{F}$)

The numbering of definitions, lemmas, propositions, theorems, corollaries, examples, and box environments all share the same counter; the goal is to make it quicker to navigate to relevant results when flipping through the pages.

What is [Abstract] Algebra?[4]

Algebra as a field of study originated in the study of numbers and equations that can be formed through the elementary arithmetic operations: addition, subtraction, multiplication, and division ($+, -, \times, \text{div}$). As mathematics has evolved, it was found that there exist many instances where we can find new forms of arithmetic on objects that are different from numbers with new operations. A simple example can be given by a square with corners distinctly labeled. We can rotate the square by $\pi/2$ radians (90 degrees). Doing four $\pi/2$ rotations shall result in the square with its original orientation. If we think of the symbol e as representing the original square in its original orientation, r the square rotated by $\pi/2$ radians, r^2 the square rotated by $2\pi/2$ radians, r^3 the square rotated by $3\pi/2$ radians, and r^4 the square rotate by $4\pi/2$ radians, we can imagine that $r^4 = e$. As a mathematician, we may consider this equation as a property of the "arithmetics of rotation" of a square. A similar example would be the hands of a clock: a clockhand rotates by $\pi/6$ radians every hour, and after 12 hours shall come back to its original position (as an equation, $r^{12} = e$), giving a form of "clock arithmetics". As mathematicians studied new systems, a huge quantity of new "arithmetics" where found. A list of some of the first new arithmetics systems that were found are:

1. The set of matrices can be added and multiplied
2. The set of networks (or direct graphs) can be combined to form larger graphs (in this case, the operation is the direct product)

[3] I, the author of this book, have had this experience the more mathematics I studied
[4] From a non-historical perspective

3. Functions can be composed (In this case, the operation is composition)
4. Sets can be unioned and intersected (in this case, the operation here is set-union and set-intersection)
5. vectors can be added and multiplied by a scalar (in this case, the operations are vector addition and scalar multiplication)
6. n-gons can be rotated by multiple of $2\pi/n$ radians to get back a square that is indistinguishable from the original square (in this case, the operation is rotation by $2\pi/n$)
7. Two paths $\alpha, \beta \subseteq \mathbb{R}^2$ whose endpoints match can be concatenated (in this case, the operation is path-concatenation)

This is a short list of thousands of new "arithmetics" that were found in a huge multitude of fields (from physics, to engineering, to linguistics, to geometry, and much more), many of which share commonalities in their properties, their "algebra". A new unified way of studying these systems had to put in place in order to systematically study these systems and better understand the rules manipulating these objects, the *algebra* of these systems.

The solution was to *abstract* a list of properties these systems share and study these properties. The abstraction was called an *algebraic structure*. Any algebraic structure consists of:

- a set of *objects* and
- a set of *operations* (i.e. functions) which must follow
- a collection of *axioms* (assumed rules they must follow)

All the examples that were given above are algebraic structures, for they may all be represented as a set along with one or multiple operations. Many of the operations in the above examples follow different axioms. Mathematicians have classified and given names to different types of algebraic objects depending on which set of axioms they follow. For example, the integers (with addition and multiplication) is an example of an algebraic structure called a *commutative ring*, while n-gons (with rotation by $2\pi/n$ radians) are an example of an algebraic structure called a *group*.

Abstract Algebra is the study of *family* or *types*[5] algebraic structures. As a consequence, in abstract algebra, we do not study a particular operation or "arithmetic system" such as the numbers with addition, rotations of a square, or any other given in the examples, but study operations that follow certain rules called *axioms*. This is the core idea behind abstract algebra: a new type algebraic structure is defined by either abstracting desirable properties from a collection of algebraic objects or creating axioms which are deemed representative of the studied structures. The advantage of this abstraction is we can study the property of the operations directly without any "noise" that may come from other properties of objects, giving us insights on all systems which can be represented an algebraic structure of a certain type. In this book, there shall be over 20 types algebraic structures that shall be studied, each at varying degrees of depth depending on their importance. Some of these elementary structures are, in the order presented in the book:

groups, group-actions, rings, fields, modules,
vector-spaces, [associative] algebras, chain complexes

[5]This is similar to the term types from *type theory* which holds a more precise meaning that the current casual use of the word type. The words "family" and "type" where both used here to accommodate type theory and set theory

Some other important objects that appear less often are (in no particular order):

monoids, groupoids, Lie algebras, inner product spaces, lattices, rngs, algebraic sets

Algebraic Equations

Given an algebraic structure, we may define *algebraic equations*: we have a collection of symbols called *variables* (three such common symbols in high school are x, y, z) which have restrictions placed on them. A prototypical example of such equations on numbers are *linear equations*: equations of the form $ax + b = 0$ for numbers a, b and variable x.

In abstract algebra, the operations no longer need to be addition and multiplication, and the objects no longer need to be numbers. If you know some calculus, then the following is an example of a more advanced equation[6]:

- *Differential Equations*: These are equations whose solutions are functions. The operations are addition of functions represented by $+$, multiplying by a number, and differentiating (we can treat differentiation as an operation that takes in one function and returns another). An example of a differential equation is:

  $$6f'' + 5cf' - f = 0$$

  where f is an at least twice differentiable function

More generally, an algebraic equation p is some composition of operations with elements of a set and variables. Often, we shall want to know if there exists an α (or multiple $\alpha_1, \alpha_2, ..., \alpha_n$) and β such that $p(\alpha) = \beta$ (or $p(\alpha_1, ..., \alpha_n) = \beta$). When looking for solutions, the set of objects of our algebraic structure matter. For example, if we restrict ourselves to working with the positive numbers, the equation $x + 5 = 0$ has no solutions, and if we allow for negative numbers then $x = -5$ is the solution. If we restrict ourselves to working with the whole numbers, then the equation $2x + 3 = 0$ has no solutions, and if we allow for rational numbers then $x = -3/2$ is the solution. As we see with the example with differential equations, the objects we are working with need not be numbers. Indeed, as long as we define the operation $+$ correctly in more general contexts, the solution to an equation $ax + b = 0$ need not be a number (it may be a function, a matrix, a network, or a shape)!

Though looking for solutions to equations may seem like a core goal of algebra, it turns out that equations themselves present many fascinating properties that are often much more valuable to study than looking for solutions to equations. In abstract algebra, we consider equations as holding "semantic information", often holding information about a "property" of an algebraic structure. For example, the equation $r^4 = e$ from earlier is an example of an algebraic equation that shows that rotating 4 times by $\pi/2$ radians gives us back the original square. The reader may start to imagine how this equation characterizes a square more than a pentagon or a triangle, and indeed this notion of an equation "representing" some core information become central to algebra[7]. Often, we shall be able to distinguish two particular instances of an algebraic structure by what equations the elements satisfy. More generally, algebraic equations may be hiding much more information (a famous example being the study of elliptic curves in algebraic number theory), and many mathematicians will invest a great deal of time uncovering these properties.

[6] The set of differential functions along with differentiation forms an algebraic structure known as a *lie algebra*

[7] To foreshadow, the construction of free-objects shall make this rigorous, and the Nullstellensatz shall be the bridge in thinking of equations as holding semantic information and interpreting them as functions

Goal of Abstract Algebra?

So what does an algebraist aim to achieve? In short:

1. *Solving and understanding equations*: Given an equation or system of equations, an algebraist wants to find solutions to the equation(s) (or determine that no solution exists). An algebraist will look for these solutions by "algebraic" means (for example, calculus or tools from ODE/PDE theory would be considered non-algebraic[8]). When the objects of study are not numbers, finding solutions may get quite complicated. As mentioned above, it shall also be the case that mathematicians look for intrinsic properties of algebraic equations themselves. How to think of this "information" which algebraic equations provide will be elucidated throughout the textbook.

2. *Finding properties of Algebraic Structures*: There is an incredible amount of different families of algebraic structures, each with varying properties. As can be surmised by the table of contents, a lot of energy will be dedicated to understanding the properties of algebraic structures. Some intriguing questions that shall be answered are:

   (a) When can the notion of "factorization" be defined, and when is it unique?

   (b) Given some algebraic structure, are there simple objects that can be used to construct all other objects (for example, there will be algebraic structures which will have the notion of "prime" like prime numbers)

   (c) when are objects "finite", "almost finite", or "infinite"?

   (d) Is the notion of "dimension" well-defined?

   (e) Can we define some reasonable notion of "size"?

   (f) Are some objects good at representing a problem in such a way that it elucidates some new property?

   these may seem like rather abstract questions, however this is a consequence of studying the abstraction of objects, which often implies that some "core" property of the object reveals itself in the abstraction

3. *Clasifying Algebraic Structures*: In the best case scenario, all possible types of algebraic objects of a given family can be found. For example, it is one of the great accomplishments of the 20th century is finding the building blocks of an algebraic structure known as *finite groups* (requiring over 10000 pages to write down the proof)[9]. More generally, algebraist tend to look for building blocks of algebraic structures and means of creating more complicated algebraic structures given the building blocks.

4. *Developping Algebraic Techniques*: Many algebraic structures allow "shift of paradigms" that reduce a seemingly very difficult problem into a simple solved problem. For example, many shapes (circles, tori, Möbus bands, klein bottles) can be distinguished by associating an algebraic structure to them which then allow mathematicians to find properties of these shapes given properties of the algebraic structures.

[8] The boundary of what is an "algebraic" method to solve equations becomes more murky in advanced algebraic topics, for example in the representation of Lie Algebras or Scheme Theory. This shall not be a problem for this textbook in over 99% of cases

[9] this shall be explored further in section 3.7

The general angle of attack in solving a problem "algebraically" is:

- to find a way of inducing an algebraic structure given the object the mathematician is working on. This is very commonly done in geometry where associating different algebraic structure to a shape give different properties of the shape, depending on the properties of the algebraic structure[10].
- to find some key properties, call them axioms, then study the consequences of these axioms. This shall be done repeatedly in this textbook, and most major algebraic structures have come about through this process[11]
- to break down your problem in pieces that we *know how to put it back together* through the use of several *functions*. The more mathematics that you encounter, the more often you shall see this strategy. For example, in Measure Theory we take advantage of the vector-space structure in the process of measuring diagonal planes in $\mathbb{R}^n$, and in Fourier analysis it is key that solutions to linear PDE's are closed under function-addition to form more complicated solutions. It is important to emphasize that we know how to put it back together using *functions* or else we would have something more akin to *topology*.

Advice for Beginners

For those experiencing abstract mathematics for the first time, perhaps with a background in calculus or some computational linear algebra, the first encounter with this sort of mathematical thinking may seem a bit obtuse. This section shall give some pointers to ease into abstraction.

As a first-time learner, it is tempting to try and memorize the definitions, lemmas, and theorems to be able to apply them on a test, similar to how a successful strategy for at least passing most calculus tests is to memorize the rules of differentiation and integration. This only works in minimal ways for abstract algebra, and mathematics more generally. In order to achieve mastery over mathematics, the reader should really form their own intuitive understanding of the topics, an internal world that naturally holds together all the concepts which the reader should know like the back of their hand. The reader should try to internalize a reason for why the definitions exist, for why the theorems and lemmas need to be proved in the first place, and how one would come up with the questions the theorems and lemmas are asking.

At the very beginning of the readers mathematical journey, this is only partly feasible. In my personal experience, it was very much akin to being a new-born who needs help understanding the language and the basics of how to "walk". However, at your own pace, you shall start "seeing" why a certain definition was chosen, shall start asking questions to yourself that on the next page will be a theorem the author (i.e. me) already answered, and shall start feeling that the concepts you have learned are "basic concepts" that anybody would know. To start picking up these skills, there are certain steps the reader should take:

1. Do as many exercises as the reader needs until they feel they understand the concepts. Some more advanced mathematics courses even go so far as to not present any theorems/lemmas and

[10] See a book in *algebraic topology* for more details

[11] Groups were an abstraction from bijective function, commutative rings from integers and modular arithmetic's, fields from solving polynomials, Dedekind Domain from rings of integers, and so forth

make the students deduce these results[12].

2. Before looking at the proof of any result, try to see if you can prove it yourself. For some results, this may be very challenging, however in these cases the reader shall find that even taking a moment to think of how to tackle the question creates enormous benefit in understanding the concept, even if the reader is totally off (which I must confess I myself have been multiple times). Doing this shall also give the added benefit of giving the reader more confidence in trying to attempt problems, and being able to prove a result before a proof is presented will certainly make the reader deeply feel like they understand what is going on. It may even be that you come up with a better proof that the one presented in the book! Even if the reader was completely off, having experienced exactly what *not* to think is itself insightful (though admittedly could be frustrating); it is inevitable that the reader shall not have the right idea for a concept in their mind, and the sooner the reader catches their misconception by being wrong, the better.

3. Try to tie together various concepts you have learned. This increases the number of ways you can recall and use your concepts, and greatly enriches ones appreciation of the topics. This book goes to great lengths to give some intriguing connections, however it is very fruitful to any reader to start seeking out these connections.

Once the readers masters these tools and ways of thinking, by the end of the book the material will truly feel elementary and introductory.

Omitted Material

No textbook can comprehensively cover all possible material as there are too many branching subjects with their own preliminaries. The following material was omitted for various reasons such as having relatively narrow application for a first-time algebraist, needing a whole other book to explore its basic properties and motivations, needing knowledge of fields outside of algebra to properly study their properties, and sometimes simply because the material (as of writing this book and the last few decades) has not had a strong branch of research within mathematics. Material falling under one of these categories include:

1. Schemes. They are the starting point of modern algebraic geometry, but the topics depth requires its own book to study (see [13]) for the continuation in algebraic geometry.

2. One of the culminating results of number theory in the 20th century is the proof of *Artin Reciprocity* which, *very* loosely speaking, connects the properties of primes to properties of some polynomials (more specifically, there is a connection between class groups of field extensions with galois groups of field extensions). A lot of modern algebraic research centers on generalizations of this result (ex. *Langland's Program*), however the amount of extra material required to cover would be too much and would require some use of complex and real analysis to cover properly.

3. Commutative algebra is a vast field that holds many very interesting and important results, more than any introductory textbook can cover. This textbook shall cover enough to introduce number theory and (classical) algebraic geometry, and prepare the reader for some further studies in these fields. See [74] or [96] for in-depth coverage.

[12] I have once jokingly seen an exercise in Lang's *Algebra* which was to pick up any textbook in algebra, and prove every result from beginning to end independently

4. Lie Algebras get a cursory overview due to their importance in representation theory, but a deeper study is greatly benefited when paired with Lie Groups.

5. Invariant Theory is an area of mathematics that has been greatly studied and has grown further in disciplines such as complexity theory[13], however we shall not have the time to cover the material in any level of depth.

6. The classification of finite groups is a project considered "complete" and so only a limited amount of effort is put in covering the mathematics behind it, enough to understand the magnitude of the project and the important principles leading to how the program was pushed forward.

7. Representation theory is a huge disciplines which shall only get enough coverage to elucidate the most important results (ex. Artin-Wedderburn) and its applications to many fields (finite groups, quivers and lie algebras, number theory).

8. An introduction to Category theory is covered in part XII, however it stops short of covering higher-order category theory (a tool useful in modern algebraic topology and algebraic geometry).

9. Cohomology theory is covered to the point where the core results are on full display and some "immediate" application is evident, but will not go into detail about many of the broader applications and theory (ex. Motivic Cohomology will be left for a textbook in algebraic geometry)

Some advanced algebraic material was chosen to be included due to its relevance in other textbooks in the EYTNKA series such as spectral sequences, quiver theory, infinite galois theory, and Hilbert polynomials.

Acknowledgments

This book started off as my personal notes for my first course in algebra, and then evolved as my algebra notes in general. I found it helpful to write the notes in a textbook format, as being able to explain why something is true proved to greatly increase my own understanding of the topic. Since the book was written while I was learning the topics, a lot of inspiration was drawn form multiple textbooks and followed their outlines closely. As the book expanded, it started to get its own character, however as of writing this acknowledgment there is still a lot of the book that is heavily influenced by other textbooks. It is thus in good conscience that I would like to give credit to these inspirations:

1. *Abstract Algebra* by Dummit and Foote [48] was the first textbook in algebra I used. A lot of the core material covered in this textbook stem from the material covered in this textbook. This textbook is an excellent introduction to the field of algebra with the abundance of details and examples, as well as some detailed proofs. The textbook is especially useful for its coverage of foundational material such as Groups and Rings. Some of the more computational aspects of the book (ex. Calculating Gröbner basis, finding RCF) is inspired by this textbook.

[13]The P vs. NP conjecture can be reformulated in the language of invariance theory

2. *Chapter 0* by Paolo Aluffi's [3] has been a huge influence on this textbook. I agree with the author that categorical thinking should not be shied away from and should be introduced as soon as possible, though as this textbook aims to have a more undergraduate starting point a lot of the categorical results are introduced more slowly in this textbook. A lot of the later material this book is also more strongly inspired by Chapter 0 (especially the chapters on Field/Galois Theory and Homological Algebra).

3. Richard E. Borcherds' youtube videos were often my key source for finding intuitions: https://www.youtube.com/@richarde.borcherds7998. His clarity and ability to communicate the core idea of a concept so succinctly has greatly helped my entire mathematical journey[14].

4. *Commutative Algebra* by Michael Atiyah [7] has had a strong influence on the commutative algebra part of the book. A large part of what was considered to be core results came from his book. A section that I was wavering on adding was the one on Hilbert polynomials as these do not show up again in the EYNTKA series until Hilbert Schemes and cohomology of schemes are introduced in [13], however I ultimately decided to keep the section on Hilbert Polynomials as there is no other natural place to introduce them in the EYNTKA series.

5. *Number Fields* by Marcus [73] and *Algebraic Number Theory* by Neukirch [83] were foundational to the chapter on number theory. Marcus's textbook offered a very detailed overview of the theory when only focusing on number fields, while Neukrich offered the abstraction I was looking for to ground these ideas in my mental framework.

6. *Algebraic Curves* by Fulton [102] *Basic Algebraic Geometry* by Shafarevich [91] were strong inspiration for the chapter on algebraic geometry. The initial sections more strongly draw inspiration form Dummit and Foote who go over the core algebraic-geometric concepts in great detail, while Shafarevich and Fulton covered the missing sections that would be necessary background for scheme theory and class field theory.

7. Milne's notes were often consulted for their lucidity and breath of subject. The section on Kummer Theory was heavily inspired by Milne's *Field and Galois Theory*, [65]

8. *Algebra* be Serge Lang [70] has often been consulted for some the more advanced material of this book, such as the section on infinite galois extensions, as well as ordered fields and derivations on fields.

[14] After struggling with a concept, I would often watch Richard Borcherds explanation and comment to my colleges that "As always, Richard Borcherds knocks it out of the park"

Preliminary Chapter

If naïve set theory is new to you, this section is going to go through a lot of terminology. The reader may want to skip to certain sections depending on their background:

1. Sets: sets, power-sets, unions and intersections. Logical quantifiers, basic propositions, vacuous truth. Induction. Relations, equivalence Relations, partial and total orders.
2. Functions: injective/surjective/bijective functions and their relation to equivalence relations. Image and restriction, composition of functions, associativity of composition, Cardinality
3. Number theory: GCD and LCM, divisibility, prime factorization, coprime numbers, the euclidean algorithm, Bézout's Identity, Modular Arithmetics, Fermat's Little Theorem
4. Graphs: basic properties
5. Category Theory: intuition, universal property, functors.

You can look over this section if you want a refresher, or skip to section 0.1.4 to start from equivalence relations, in particular if the reader is unaware of the relation between equivalence relations and functions, then this section will be important.

There are also a few starred sections that are not necessary for most of the book, and are added as they show up for a few proofs.

0.1 Sets

As in any field of study, we need to establish a common language for everyone in the field to communicate their ideas. The accepted language of mathematics today was invented by Georg Cantor in the 19th century and is called *set theory*. Before Cantor, there's wasn't one universal set of symbols and concepts mathematicians agreed upon to talk about basic concepts, with different

groups of mathematician inventing their own symbology to talk about their ideas. Nowadays, every field of mathematics grounds their work in set theory [15] – algebra is no exception.

We'll be learning a small part of set theory which concerns itself with using the tools of set theory for talking about concepts. These tools are under the label of *naïve set theory*. We will be using these tools and question little why we are using these particular tools. The reason for the term "naïve" set theory is due to history: there were a couple of important paradoxes which showed some inconsistencies in set theory [16]. From the existence of these paradoxes, a generation of mathematician's tried to free set theory from these problems [17]. Their research became known as set theory, and the previous understanding of set theory came to be known as *naïve set theory*. Naïve set theory wasn't dismissed, instead mathematicians who were interested in making a solid foundation for mathematics tried figuring out exactly how we should be using naïve set theory without contradiction, while the rest of mathematicians used naïve set theory. When we use naïve set theory, we're essentially using the results of [the new] set theory without worrying about the details. It's like taking advantage of a building without knowing the architectural details of why a support was put here, or a door was needed there. We will be taking full advantage of this pre-built building for us. Some footnotes will be added for those who want to peek at the questions that lead mathematicians of the early 20th century to investigate the details of set theory. For those with a deeper interest in the foundations of mathematics, a class on logic is recommended, or the reader can checkout EYTNKA logic [35] for the logic book in the EYNTKA series.

As a consequence of using naïve set theory, we'll be defining certain concepts by relying on some [very] basic intuition. For example, we will assume the idea that we can conceptualize a collection of objects (for example, imagine a bunch of trees, or a bunch of numbers), or know the basics of numbers (ex. you know how to think of the symbols $1, 2, 3, ...$ as number, and you can add/subtract/multiply/divide). Definition's after the preliminary chapter will build on the definition's presented here, and so it's not a prerequisite for chapters after the preliminary chapter to rely heavily on intuition.

Basic Definitions: Sets

In mathematics, we work with collection of things, and with "mathematical sentences" about a collection of things, where a mathematical sentence must be either be true or false. We will start by learning how to describe the collection of things, and then move on to learning about mathematical sentences. We will make a distinction between a collection of things and the things inside the collection. We call a collection of things a *set*, and the things inside a set are *elements*. Another definition of a set is provided by the founder of set theory Georg Cantor

> *A set is a Many that allows itself to be thought of as a One*

In other words, we can think of any arbitrary collection of objects put together as a new single entity. The one restriction we give to sets is that all the elements in a set must be different, in other words,

[15] There is a movement to replace foundation of mathematics with *type theory* – for those interested see ref:HERE

[16] Famously, Russel's paradox showed a logical problem in how we can define sets. We'll actually cover Russel's Paradox in ref:HERE (Perhaps add it to the end of set theory section?) if you're curious to check it out after reading this section

[17] one major result of this research was the axiomatization of set theory (i.e. the development of the fundamental rules) by Zermelo and Frankel, their set of axioms (i.e. fundamental rules) being called ZF in honour of them. There are a couple of axioms that can be added or removed from ZF, but ZF generally forms the core of modern mathematics. If you keep doing mathematics, you will hear statements like "This statement is true in ZF"

we must have each element to be distinct. The reason for this is that set theory can be thought of pulling from universe of all possible objects of which there are no copies of objects[18].

When we write a set, we put curly braces ("{" and "}") around a collection of things (or really, symbols which could represent things [19]) which are separated by a comma.

Example 0.1.1: Example of sets

1. To write a set with the numbers $1, 2$ and 3, we write $\{1, 2, 3\}$. The numbers 1, 2, and 3 are the elements of $\{1, 2, 3\}$. Note that $\{1, 1, 2, 3\}$ would not be considered a set since the 1's repeat. The convention when a set has repeated elements is to have them "squished" into one element to create a set with only distinct elements. This would mean that we would consider the set $\{1, 1\}$ to be $\{1\}$ where we squished the two 1's into a single element. This convention also holds if the set has other elements too:

   $$\{1, 1, 2, 3\} = \{1, 2, 3\}$$

   If we add an element to a set that's already there, we will also do this "squishing" [a]

2. As mentioned, sets contain can anything. The set

   $$\{\text{ice-cream}, \text{cheesecake}, \text{chocolate}\}$$

   is a set that represents 3 desserts.

3. The set $\{1\}$ is a set with the element 1. We would not say that 1 and $\{1\}$ are the same thing, since $\{1\}$ is "a set containing the number one as its element" and 1 as "the number one". Using mathematical notation, $1 \neq \{1\}$

4. $\{\}$ is also a set, called the empty set. It pops up often enough that we have a special symbol for this set: $\emptyset$

5. Sets can contain sets, so $\{1, \{☺, \mathfrak{T}\}, \text{bat}\}$ is a set that contains the element 1, the element $\{☺, \mathfrak{T}\}$ (which is also a set), and the element bat.

6. Sets need not have an order, so for example

   $$\{\text{ice-cream}, \text{cheesecake}, \text{chocolate}\} = \{\text{cheesecake}, \text{ice-cream}, \text{chocolate}\}$$

   This also means that a set with the words for days of the week is the same if we re-arrange the days.

[a] Formally, (explain what's actually happening here in terms of ZFC?)

Sometimes, we care about the order of elements. If that is the case, we will surround them in parenthesis, "(and)", and call these *tuples*, or if there are n elements then n-tuples where n represents the number of elements. For example: $(1, 2, 3)$ is a 3-tuple, and $(1, 2, 3) \neq (3, 2, 1)$ even

[18] Going deeper than this, asking questions like what are the possible things a set can contain, what are all possible sets, can there be sets that contain itself, all venture into set theory proper

[19] Some might be dubious on whether the symbols can represent "anything". For example, is it okay to say that x represents a statement that is both true and false? Is that "a thing". This type of question of what is a "well-defined" thing is subject to deeper explorations of set theory

though $\{1,2,3\} = \{3,2,1\}$ [20]. 2-tuples are sometimes called a *pair*. If it is clear from context, it is a common convention to drop the number in front of the word tuple, i.e., if the writer consistently uses 2-tuples they might choose to just call them tuples.

Elements

As mentioned earlier, If something is inside a set, we call that an *element* or *object* of the set. We usually (but not necessarily) denote elements with lower-case letters (ex. a, b)[21]. To write "a in A" in mathematical notation, we use the symbol $\in$. For example:

$$a \in A$$

is read as "a in A" (or "a is in A" to sound more grammatically correct). If we want to say that "a not in A", we add a slash across our symbol ($/$):

$$a \notin A$$

For example, $1 \in \{1,2,3\}$, but $4 \notin \{1,2,3\}$. If we have the empty set $\emptyset$ (i.e. $\{\}$), then it is always the case that nothing is inside it, i.e., $a \notin \emptyset$ for any a. Sets can also contain other sets, so $\{1\} \in \{\{1\}, 2, \{\text{cheesecake}, 6\}\}$. Note that $1 \notin \{\{1\}, 2, \{\text{cheesecake}, 6\}\}$ since the set $\{\{1\}, 2, \{\text{cheesecake}, 6\}\}$ doesn't contain "the element 1" but the "the set that contains the element 1".

0.1.2 Concept Check Is

$$\{1,2,3\} \in \{0, \{\{1,2,3\}\}, 4\}$$

Equality

The concept of equality was already used earlier based on our intuition. We will expand a bit further on how to think of equality in set theory, and we will distinguish two symbols for equality:

$$A = \{1,2,3\}$$
$$A := \{1,2,3\}$$

Starting with the first line, the symbol $=$ means *logically equal*. Being "logically equal" (which we will always abbreviate to saying equal[22]) means the two sets have the same elements (for example

[20] In set theory, every mathematical object is represented as a set. This is no exception in n-tuples. A 2-tuple (a, b) would be $\{a, \{a, b\}\}$. A similar pattern follows for n-tuples

[21] Here's another "beyond the scope of naive set theory" question: What are the possible elements that may exist? Question of this varieties lead to logicians like Butrard Russel to come up with *Russel's Paradox*. This paradox will actually be covered in the book near the end (see ref:HERE). It's written in such a way that you can skip to take a look at it if you're curious

[22] This is another big set-theoretic question: what does it really mean for something to be equal? Bertrand Russel and Alfred Whitehead in their book *Principia Mathematica* famously took 379 pages before they defined equality. In modern set theory, two sets are equal if they contain the same elements

$\{1,2\} = \{2,1\}$). If we want to say that the two are not equal (i.e. the symbols represent different things [23]), we do the same convention as with $\in$ and put a slash across the symbol: $\{1\} \neq \{1,2\}$.

Notice we were comparing sets, while "=" has been done between numbers:

$$\frac{1}{2} = \frac{2}{4} \qquad \text{and} \qquad \frac{1}{2} \neq \frac{1}{3} \tag{1}$$

In proper set theory, every object is actually a set. Thus, even comparing $\frac{1}{2}$ and $\frac{2}{4}$ will be a comparison with sets. We will construct $\mathbb{Q}$ and show how it's elements are sets in section 9.5. For this entire book, we will freely use the common intuition of equality between elements like done in the above equations (equation 1), and for equality between predicates (covered in section 0.1.1).

Example 0.1.3: Examples Of Equality

1. if we want to say two sets have the same elements, that they are each representing the same collection of objects, we write $A = B$
2. $\{1,2,3\} \neq \{2,3,4\}$. Even though both sets have the elements 2 and 3, they each contain a number the other doesn't have, and so they are not equal
3. Similarly, $\{1,2\} \neq \{1,2,3\}$ since $3 \notin \{1,2\}$

The symbol := means the same thing as =, that is, := is also logically equal. The difference between := and = is that := is used to emphasize that the symbol on the left of := will now be used to represent the thing on the right of :=. This is most often used in definitions to make sure the reader understands that symbol will consistently be used to represent the same thing many times. Because of this, the symbol := is read as "define" – the statement $A := \{1,2,3\}$ can be read that "Define A to be the set $\{1,2,3\}$".

Set-Builder Notation

Many times, we want to have a set of elements that satisfy only certain properties. For example, from the set of all deserts, I only want the ones that contain ice-cream, or from the set of all numbers I want only the prime numbers, or from the set of all months, I want the months that end in "ber". The way we'll capture this idea with sets is by using *set builder-notation* to build a new set given an old one. If S is a set and P is some sentence describing a property (ex. being an even number, or being a prime number, or representing "this desert has ice-cream"), then we'd write

$$A = \{s \in S \mid P\}$$
or
$$A = \{s \in S \ : \ P\}$$

[23] This is another question beyond naïve set theory: Since all we're using are symbols that represent objects, where do the objects come from? One answer to this is some universal set with every possible thing as an element of it, but thinking about what exactly does it mean for a set to contain everything leads to interesting nuances (one of the problems of a set that contains everything is once again Russel's Paradox)

and is read "s in S such that [s satisfies the property P]". In the next section, we shall be more precise about what type of sentence can be used:

Example 0.1.4: Set Builder Notation

1. If

$$M = \{\text{Janurary, February, March, April, May, June,}$$
$$\text{July, August, September, October, November, December}\}$$

and $D = \{m \in M \mid \text{m ends in "ber"}\}$, then

$$D = \{\text{September, October, November, December}\}$$

2. If $W = \{\text{hello, bonjour, cześć}\}$, and $V = \{w \in W \mid w \text{ is in polish}\}$, then

$$V = \{\text{cześć}\}$$

3. if $\mathbb{N} = \{0, 1, 2, 3, \cdots\}$ and $P = \{n \in \mathbb{N} \mid n \text{ is a prime number}\}$ then

$$P = \{2, 3, 5, 7, 11, \cdots\}$$

Note that $P' = \{n \in \mathbb{N} \mid \text{the only numbers that divide } n \text{ are 1 and } n\}$ is the exact same set (i.e. $P = P'$). Different properties can produce the same sets.

4. if $\mathbb{N} = \{0, 1, 2, 3, \cdots\}$ represents the set of all non-negative numbers with no decimal places, the set

$$A = \{x \in \mathbb{N} \mid x = 2y,\ y \in \mathbb{N}\}$$

would represent all even numbers [a], and can be read "x in the natural numbers such that x can be twice any natural number"

[a] This notation has it's limitations if you dig deeper in it. You can create some very interesting paradoxes (Russel's paradox being one of them). We will not construct such contradictory cases in the book

0.1.1 Propositions and Predicates

We will now explore how to formulate questions and mathematical statements using mathematical language. Again, a full exploration would be covered in a textbook in logic.

Intuitively, there is some understanding of the meaning of a sentence[24] . If I say "I think blue is pretty" then in your mind some information got passed on. If we make a sentence that has a truth value associated to it (the sentence can either be true or false) [25] , like "The number 2 is prime", then we call such a sentence a *proposition*. If we have a sentence that takes in a variable that will make it depend on its truth value, for example "The number x is a prime number", then this will be called a *predicate*. Propositions and predicates are at the heart of mathematical communication. We

[24] The nature of how we derive meaning from sentences is an interesting logical and philosophical debate that goes beyond the scope of this book. See Russel, Wittgenstein, _____, for more details

[25] Development in a field called *topoi theory* are trying to generalize our notion of proposition beyond true and false, an interesting developing field to look into

have already encountered predicates before when we used set-builder notations: the restriction *has to be a predicate*. For convenience, we assign a symbol to a proposition. For example, we can have $P =$ "2 is a prime number". Then P would be true. However, $Q =$ "2 is not a prime number" is a false. For predicates, we shall usually assign a symbol and a variables, for example:

$$R(x) = \text{“}x \text{ is a prime number”’}$$

where x may be any natural number, then this predicate truth-value (that is, whether it is true or false) depends on the value the variables x will take.

Example 0.1.5: Predicates

1. let $P(x) =$"x is a month of the year". Then

$$P(\text{September}) = \text{true} \qquad P(\text{Wednesday}) = \text{false} \qquad P(\text{Laughing}) = \text{false}$$

2. The variable x can also reused in other propositions. For example we can have $P(x) =$"x is a dog" and $Q(x) =$"x is an animal".
3. Propositions can be composed, for example consider $R(x) =$"$P(x)$, then $Q(x)$" where $P(x), Q(x)$ are the propositions from the above. When is this proposition true?
4. Proposition can also take in multiple variables, for example

$$P(x, y) = (x < y)$$

Predicates of the form

$$\text{if } P(x) \text{ then } Q(x)$$

are some of the most common, allowing for relations being made between different concepts. The symbol used to symbolize an "if, then" relation is $\Rightarrow$, so

$$\text{If } P(x) \text{ then } (Q) \qquad \text{becomes} \qquad P(x) \Rightarrow Q(x)$$

Which is usually read "$P(x)$ implies $Q(x)$". A common mistake is to assume that if $P(x) \Rightarrow Q(x)$, then $Q(x) \Rightarrow P(x)$. This need not be the case. For example, define the following two predicates

$$A(x) = (x|2) \Rightarrow (x|4) \qquad A'(x) = (x|4) \Rightarrow (x|2)$$

When is predicate $A(x)$ true? When is $A'(x)$ true? If it *is* true that $P(x) \Rightarrow Q(x)$ always implies $Q(x) \Rightarrow P(x)$ we use the symbol $P(x) \Leftrightarrow Q(x)$ and read $\Leftrightarrow$ as "if and only if" (sometimes abbreviated to iff).

Vacuous Truth

Let's say we had two proposition $P(x, y) = x \Rightarrow y$, and let's say that x was false, while y is true. What is the truth value of $P(x, y)$? For example, let's say that

$$x = \text{I'm walking in the rain}$$
$$y = \text{I am wet}$$

Then if you are *not* walking in the rain, but *are* wet, then what should be the value of $P(x, y)$? Perhaps more interesting is the following example:

1. Let's say there are no cell-phones in a room. Then is the statement "all phone are turned off" true?
2. A famous such example is the following: is the statement "The king of France is not wearing pants" true or false if France does not have a king?

There are many solutions to this problem. The mathematically accepted solution to this problem is something called *vacuous truth*, which gives the following resolution:

$$(\text{False} \Rightarrow \text{True}) \text{ is True, and } (\text{False} \Rightarrow \text{False}) \text{ is } \textit{also} \text{ True}$$

The idea being that any "nonsense" statement is always "true" in the most trivial way. This interpretation of truth is not a unique one, but it is one that is very convenient as shall be seen by the reader.

Logical Quantifiers

We will now explore how to create more complicated properties by adding to our tool-belt 6 "words" from which we can construct mathematical sentences:

Definition 0.1.6: Quantifiers And Connectives

We define the following 3 quantifiers to be used in propositions:

1. $\forall$: the for-all quantifier.
2. $\exists$: the *existence* quantifier
3. $\exists!$ the *unique existence quantifier*

and the following 4 connectives to be used for propositions

1. $\vee$: disjunction (or) connective. If P, Q are propositions, then $P \vee Q$ mean that if one of or both of P or Q is true, then the new poposition $P \vee Q$ is true.
2. $\wedge$: conjunction (and) connective. If P, Q are propositions, then $P \wedge Q$ mean that if both P and Q are true, then the new proposition $P \wedge Q$ is true. If one of them are false, then $P \wedge Q$ is false.
3. $\Rightarrow$: implication connective: $P \Rightarrow Q$ is false if P is true and Q is false. In other words, if P is true, then P implies Q means Q is true.
4. $\neg$ negation (not) connective. If P is a proposition, then if P is true then $\neg P$ is false, and similarly if P is false then $\neg P$ is true.

The keen reader may ask if there are any other quantifiers or connectives, and indeed there can be many more. However, it is in fact sufficient to define these connectives/quantifiers to completely

describe any [first-order] mathematical sentence[26]. Using these symbols, can the reader translate some of the propositions earlier in the book using these symbols?

Recall that we have defined the symbol $\in$ earlier to specify an element belongs to a set. This is a special symbol which is neither a quantifier nor a connective. It is considered a special symbol that is part of the language of set theory.

The order of quantifiers is important. For example:

$$\forall x \in \mathbb{Z},\ \exists y \in \mathbb{Z},\ x < y$$

means that for every x, there exists a y that is greater than it, which is certainly true when working with numbers. However:

$$\exists x \in \mathbb{Z},\ \forall y \in \mathbb{Z},\ x < y$$

means that there exists an x that is smaller than all y, which is certainly not possible since we can always find a smaller number.

With these, we can define certain operations we can perform on sets:

Definition 0.1.7: Set Operations

1. Define a subset to be:
$$A \subseteq B \Leftrightarrow (x \in A \Rightarrow x \in B)$$
Sometimes the symbol $A \subset B$ is also used. Since it is possible that $A \subset B$ and $A = B$ (you can check this by the definition), the symbol $\subseteq$ will predominantly be used to emphasize this relation. If we want to make it clear that $A \neq B$, we write $A \subsetneq B$.

   For any set S, we always have $\emptyset \subseteq S$ and $S \subseteq S$. With this notation, we also have that $A \subseteq B$ and $B \subseteq A \Rightarrow A = B$

2. Define the intersection of two sets to be:
$$A \cap B := \{x \mid x \in A \text{ and } x \in B\}$$

3. Define the union of two sets to be:
$$A \cup B := \{x \mid x \in A \text{ or } x \in B\}$$
if $A \cap B = \emptyset$, we say that A and B are *disjoint*

4. Define difference between sets to be:
$$A \setminus B := \{x \mid x \in A \text{ and } x \notin B\}$$
sometimes also written as $A - B$. If $T \subseteq S$, then we say that $S \setminus T$ is the *compliment* of T, usually written T^c.

Another very important definition

[26] This would be explored in a course on logic

Definition 0.1.8: Product Of Sets

Let A and B be sets. Then

$$A \times B = \{(a, b) \mid a \in A,\ b \in B\}$$

is the set of all 2-tuples (called just tuples for short). This construction can be extended indefinitely:

$$X_1 \times X_2 \times \cdots = \{(x_1, x_2, ...) \mid x_1 \in X_1,\ x_2 \in X_2,\ ...\}$$

This notation is also abbreviated as:

$$\prod_i X_i$$

For example:

Example 0.1.9: Product Of Sets

$$\{1, 2\} \times \{a, b\} = \{(1, a), (2, a), (1, b), (2, b)\}$$

and

$$\{a, b\} \times \{1, 2\} = \{(a, 1), (b, 1), (a, 2), (b, 2)\}$$

Exercise 0.1.1

1. Let $\{E_n\}_{n=1}^{\infty}$ be a collection of sets indexed by the natural numbers. Define

$$\limsup\{E_n\}_{n=1}^{\infty} = \bigcap_{k=1}^{\infty} \bigcup_{n=k}^{\infty} E_n \qquad \liminf\{E_n\}_{n=1}^{\infty} = \bigcup_{k=1}^{\infty} \bigcap_{n=k}^{\infty} E_n$$

show that

$$\limsup\{E_n\}_{n=1}^{\infty} = \{x \mid x \in E_n \text{ for infinitely many } n\}$$
$$\liminf\{E_n\}_{n=1}^{\infty} = \{x \mid x \in E_n \text{ for all but finitely many } n\}$$

2. (De Morgan's laws) Let X be a set and let $\{A_i\}_{i \in I}$ be a collection of subsets of X. Show that

$$X \setminus \bigcup_{i \in I} A_i = \bigcap_{i \in I} (X \setminus A_i) \qquad X \setminus \bigcap_{i \in I} A_i = \bigcup_{i \in I} (X \setminus A_i)$$

Naming the Numbers and Common Sets

With the basics of set down, we can introduce some of the most common sets and their notation

Definition 0.1.10: Common Sets

1. As we've already seen, if a set has no elements, the symbol $\emptyset$ represents the empty-set
2. If a set has a single element, we call that set a *singleton*. For example, $\{1\}$ and $\{\pi\}$ are singletons.
3. If X is a set, $P(X)$ is the set of all subsets of X[a]. In set builder notation, it can be denoted $P(X) = \{S \mid S \subseteq X\}$. For example, if $X = \{a, b, c\}$, then

$$P(X) = \{\emptyset, \{a\}, \{b\}, \{c\}, \{a, b\}, \{a, c\}, \{b, c\}, \{a, b, c\}\}$$

[a] The existence of this set is an axiom in ZFC

Definition 0.1.11: Sets Representing Numbers

1. $\mathbb{N} := \{0, 1, 2, 3, \cdots\}$ is the set of all *natural numbers* (some call it the *counting numbers* or *whole numbers*). Natural numbers are all positive numbers which do not have any decimal places. Sometimes, people define $\mathbb{N}$ to not have 0. We will always have $\mathbb{N}$ contain the number 0 (for reasons which will be clear much later in the book [a]). If we want only the [strictly] positive number [b], we will write $\mathbb{N}_{>0}$.
2. $\mathbb{Z} := \{\cdots -3, -2, -1, 0, 1, 2, 3, \cdots\}$ is the set of all *integers*. Integers are the natural numbers along with their negative counter-part. Sometimes, the natural numbers are called the non-negative integers.
3. $\mathbb{Q} := \left\{ \frac{p}{q} \;\middle|\; p, q \in \mathbb{Z},\ q \neq 0 \right\}$ is the set of all *rational numbers*. For example, $\frac{1}{2} \in \mathbb{Q}$. The symbol $\mathbb{Q}$ is used since numbers of the form $\frac{p}{q}$ are called ***q**uotients*. Notice also that this is one of the instances where we use the convention that if there is a repeated element, we "squish" to a single element. If we did not take this convention, this set wouldn't be defined, since there would be many repeated numbers (for example $\frac{1}{2} = \frac{2}{4} = \frac{4}{8}$ and so forth)
4. $\mathbb{R}$ represents any number with any decimal expansion (ex. $\pi, e, 1, \frac{1}{3}$), i.e., all the numbers on the number line. If you've learned about Complex numbers or Quaternions in high school, these numbers are not real numbers, and will be defined and studied later in this book. The set $\mathbb{R}$ is called the *real numbers*. We can abuse notation (meaning use the notation in a way bends the rules a little) and write $\mathbb{R}$ as

$$\mathbb{R} := \{\cdots D_3 D_2 D_1 . d_1 d_2 d_3 \cdots \mid D_i, d_i \in \mathbb{Z}\}$$

where $\cdots D_3 D_2 D_1 . d_1 d_2 d_3 \cdots$ represents some arbitrary string of numbers put together where there can only be finitely many D_i's, but there can be infinitely many d_i's. In other word, the number

$$0.123123123123\cdots$$

where 123 continues on forever on the right is in the set $\mathbb{R}$, but

$$\cdots 123123123$$

where 123 continues on forever on the left is not in the set $\mathbb{R}$.

[a] See section 7.1

[b] There is no complete agreement on whether 0 is positive or negative: 0 is either both positive and negative or neither positive nor negative. It usually comes down to the purposes of the context. If we allow 0 to be a positive number, we sometimes say that all numbers larger than 0 are *strictly positive*

Some find it intuitive to think about $\mathbb{R}$ has having "no gaps", which means we cannot perfectly split $\mathbb{R}$ into two using the less than and greater than operator ($<$ and $>$) without missing a number. For an example of a split, we can split $\mathbb{N}$ into $\mathbb{N}_{\frac{5}{2}^+} = \left\{x \in \mathbb{N} \;\middle|\; x > \frac{5}{2}\right\}$ and $\mathbb{N}_{\frac{5}{2}^-} = \left\{x \in \mathbb{N} \;\middle|\; x < \frac{5}{2}\right\}$, and we have successfully split $\mathbb{N}$ into two without missing a number (i.e. every natural number is either in $\mathbb{N}_{\frac{5}{2}^+}$ or $\mathbb{N}_{\frac{5}{2}^-}$). If we chose to split around 5, then neither the set $\mathbb{N}_{5^+}$ nor the set $\mathbb{N}_{5^-}$ would contain 5, meaning it does not split $\mathbb{N}$. For the Real numbers, there does not exist a perfect split. You might ask if $\mathbb{Q}$ has this same property, but we will prove that we can in fact always split it: We will show $\mathbb{Q}_{\sqrt{2}^+} = \left\{x \in \mathbb{Q} \;\middle|\; x > \sqrt{2}\right\}$ and $\mathbb{Q}_{\sqrt{2}^-} = \left\{x \in \mathbb{Q} \;\middle|\; x < \sqrt{2}\right\}$ splits $\mathbb{Q}$ (see ref:HERE).

The fact that $\mathbb{R}$ cannot be split into two using $>$ and $<$ is actually at the heart of many formal definitions of $\mathbb{R}$ which is covered in an Analysis I class. In this book, we will not need to think of $\mathbb{R}$ in this fashion, and so we'll stick with just using intuition for now. [27]

https://math.stackexchange.com/questions/2834876/convergence-of-geometric-series-with-r1

0.1.2 Induction

Here. The whole $(p(x) \Rightarrow p(x+1)) \Rightarrow$ here this as the formal definition? + some intuition?

0.1.3 *Pigeon-hole Principle

(Comes up in algeraic number theory, so should add it here)

0.1.4 Relations and Equivalence Relations

What does it mean two things to be equal? There are actually many ways, depending on what you want to be "equal". For example,

1. we may say that two people have the same birthday, even if they are not born in the same year.
2. more examples her

In this section, we shall explore how to capture this more general notion of equality.

Relations

We start of with the more general notion of *relation*. Many times when working with sets, some subsets can be thought of as having certain properties for example, we can split the set $\mathbb{Z}$ into even

[27] Google *Dedikend Cut construction* or *Completion of Rational Numbers* if you're curious to see a formal definition of $\mathbb{R}$

and odd numbers, or we have some numbers being bigger than others, or that some numbers are multiples of another. The following is this idea is formalized:

Definition 0.1.12: [Binary] Relation

Let X be a set. Then any collection of pairs (x, y), $x, y \in X$ is called a [binary] *relation*. If $(a, b) \in R$, we will say that x *is related to* y. If $(a, b) \in R$, we will write aRb.

More generally, we can increase the number of times we take the product (i.e. $n > 2$) (ex. $X \times X \times \cdots X$). This would be called an *n-relation*.

We shall almost always think of relations

Example 0.1.13: Relations

1. Take $\mathbb{Z}$ and define the set $< \subseteq \mathbb{Z} \times \mathbb{Z}$ to be

   $$(x, y) \in < \text{ if and only if } x \text{ is strictly less than } y$$

   Then $(3, 4) \in <$, $(3, 3) \notin <$, and $(4, 3) \notin <$. If $(a, b) \in <$, we would usually write:

   $$a < b$$

   and if $(a, b) \notin <$, we would write

   $$a \not< b$$

   A similar relation is the $\leq$ relation, where we also allow for two numbers to be equal

2. Take $\mathbb{Z}$ and define the set R_{div} to be:

   $$(x, y) \in R_{\text{div}} \text{ if and only if } x \text{ divides } y$$

   Then $(2, 4) \in R_{\text{div}}$. What other elements are in this set? This set is usually denoted $|$ so that if a divides b then:

   $$a|b$$

3. for a non-mathematical example, if we let X be the set of all humans, then we may define a relation "is the ancestor of". Another similar but different relation is "is the parent of" where two humans are related is one is the parent of another.

A common relation to put on objects give a sense ordering:

Definition 0.1.14: Order

Let R be a relation on X. Then R is a *partial order* if it is:

1. **reflexive**: For all $x \in X$, xRx (x always relates to itself)
2. **antisymmetric**: if xRy and yRx, then $x = y$[a]
3. **Transitive**: if xRy and yRz, then xRz.

Furthermore, a partial order is a *total order* (or simply an *order*) if it is furthermore:

4. **Connected**: For each $x, y \in X$, either xRy or yRx

[a] a relation is symmetric if xRy then yRx. Hence, antisymmetry means no elements can be symmetric with another elements besides itself

The canonical total order is $\leq$ on numbers, and the canonical partial order is $\subseteq$ on sets.

Example 0.1.15: Orders

1. Let $\mathbb{N}^2 = \mathbb{N} \times \mathbb{N}$. Give some examples on $\mathbb{N}^2$ of different ordering.
2. Let D be the set of words in a dictionary dictionary. Then D can be lexicographically ordered
3. All numbers introduced so far have an order defined: $(\mathbb{N}, \leq), (\mathbb{Z}, \leq), (\mathbb{Q}, \leq), (\mathbb{R}, \leq)$.

Equivalence Relations

The most common type of relation that we shall see is the equivalence relation which generalizes the notion of equality:

Definition 0.1.16: Equivalence Relation

Let S be a set and $x, y, z \in S$ be elements of S. An *equivalence relation* on a set S is relation $\sim$ satisfying

1. **(reflexive)** $x \sim x$ (i.e. every element must be related to itself)
2. **(symmetric)** if $x \sim y$ then $y \sim x$
3. **(Transitive)** if $x \sim y$ and $y \sim z$ then $x \sim z$

Example 0.1.17: Equivalence Relations

1. Equality ($=$) is the prototypical example of an equivalence relation. For example, If we have $a, b, c \in S$ with $aRb \Leftrightarrow a = b$, then
   (a) $a = a$
   (b) $a = b \Rightarrow b = a$

(c) If $a = b$ and $b = c$, then $a = c$.

In a ways, an equivalence relation is a generalization of equality.

2. Let X be any non-empty set. Then we may make all elements equivalent to each other. Similarly, we may make all elements only equivalent to themselves.
3. Let P be the set of all people. Check that "has the same birthday" is an equivalence relation
4. Two equivalence relations from high school that the reader may have encountered is with triangles. Check that being *similar to* and being *congruent to* are equivalence relations.
5. Define $\sim$ on $\mathbb{Z}$ to be $a \sim b$ if and only if $|a| = |b|$. Then $\sim$ is an equivalence relation.
6. Is $\leq$ an equivalence relation?
7. Let R be the empty relationship on any non-empty set. Is R an equivalence relation?

Given an equivalence relation $\sim$ on S, the *equivalence class* of $x \in S$ is $[x] = \{y \in S \mid y \sim x\}$, and S splits into these classes:

$$S/\sim = \{[x] \mid x \in S\}$$

For example, if $S = \{1, 2, 3, 4, 5, 6, 7, 8, 9\}$, and:

$$1 \sim 2 \qquad 3 \sim 4 \sim 5 \sim 6 \qquad 7 \sim 8 \sim 9$$

Then:

$$S/\sim = \{\{1, 2\}, \{3, 4, 5, 6\}, \{7, 8, 9\}\}$$

Two classes are either equal or disjoint, and their union is S. Conversely, breaking S into nonempty disjoint sets whose union is S defines an equivalence relation, under which two elements are equivalent when they lie in the same set. The exercises in exercise set 0.1.2 below ask for both proofs. Such a splitting is called a partition:

Definition 0.1.18: Partition

Let S be a set. A *partition* of S is a collection $\{S_i\}_{i \in I}$ of nonempty subsets of S such that

1. $S_i \cap S_j = \emptyset$ whenever $i \neq j$
2. $\bigcup_{i \in I} S_i = S$

The sets S_i are the *parts* of the partition.

0.1.5 Functions

In mathematics, it is very desirable to relate one set to another set, or said differently how two sets may "interact". For example, to each positive natural number one may associate the number of its

prime factors, counted with multiplicity:

$$\begin{aligned} 1 &\mapsto 0 \\ 2 &\mapsto 1 \\ 3 &\mapsto 1 \\ 4 &\mapsto 2 \\ 5 &\mapsto 1 \\ 6 &\mapsto 2 \\ &\vdots \\ 16 &\mapsto 4 \\ &\vdots \end{aligned}$$

Another more abstract relation we may ask for is given a set of names, say

$$\{\text{Alfred}, \text{Socrates}, \text{Buddha}, \text{Oscar Petesron}\}$$

the function returns a set containing some information about that person:

$$\begin{aligned} \text{Alfred} &\mapsto \{\text{Batman's Butler}, \text{Friend of Bruce}\} \\ \text{Socrates} &\mapsto \{\text{Philosopher}, \text{lived in Athens}, \text{Never wrote his work down}\} \\ \text{Buddha} &\mapsto \{\text{Real name Siddhartha Gautama}, \text{Starter of a Religion}, \text{Born in Lumbini}\} \\ \text{Oscar Peterson} &\mapsto \{\text{Greatest Jazz Pianist}, \text{Canadian}, \text{“Maharaja of the keyboard”}, \text{Lived to 82}\} \end{aligned}$$

As a final example, we may imagine a every location of a map of the world being represented as an element in a set. Then we may relate a point on the map to the temperature at that location. Generalizing this pattern, given some set X, we may want to assign it an element from another set Y.

Definition 0.1.19: [set] Functions

Let X and Y be sets. Then a *function* is a subset $\Gamma(f) \subseteq \{(x,y) \mid x \in X,\ y \in Y\}$ such that

1. **Total** or **Serial** (left-total): For every $x \in X$, there exists an element $(x,y) \in \Gamma(f)$
2. **Functional** (right-unique): Every $x \in X$ is associated with one and only one $y \in Y$, that is, it cannot be that $(x,y),(x,y') \in \Gamma$, for $y \neq y'$ where $y, y' \in Y$

This is usually written as:

$$f : X \to Y \qquad f(x) = y \qquad \text{or} \qquad X \xrightarrow{f} Y$$

where f is called the *function* and $\Gamma(f)$ is called the graph of the function and is defined to be:

$$\Gamma(f) = \{(x,y) \mid x \in X,\ y \in Y,\ f(x) = y\}$$

If $f : X \to Y$, X is called the *domain* and Y is called the *codomain*. The collection of all functions from two sets X, Y is denoted:

$$\mathrm{Hom}_{\mathbf{Set}}(X,Y) \qquad \text{or} \qquad Y^X \quad (a)$$

[a] Notice this is a set operation. This particular notation shall be elaborated on with more category theory in section ref:HERE

Function are also sometime called maps or mappings. Sometimes, we want to define a function, but don't need to reference to it again (in computer science, this is called an *anonymous function*). In this case, we may use the following notation:

$$x \mapsto y$$

instead of $f(x) = y$. If $X = Y$ so that $f : X \to X$, then we may think of f as a relation which has the property of being functional and total. If more than one function with the same domain and codomain is defined (say f, g with domain X and codomain Y), then the declaration is often shorthanded to $f, g : X \to Y$.

Example 0.1.20: Functions

1. The first three examples given are examples of functions, since every element in the domain get's mapped to a unique element in the codomain.
2. Some other perhaps more familiar functions to the reader are
   (a) $x \mapsto e^x$, i.e. $f : \mathbb{R} \to \mathbb{R},\ f(x) = e^x$
   (b) $\log : \mathbb{R}_{>0} \to \mathbb{R},\ x \mapsto \log(x)$
   (c) $p(x) : \mathbb{R} \to \mathbb{R},\ p(x) = ax^2 + bx + c$, for $a, b, c \in \mathbb{R}$
3. Let X be an arbitrary non-empty set. Then there always exists at least one function from X to X, namely:
   $$\mathrm{id}_X : X \to X \qquad \mathrm{id}_X(x) = x$$
   that is, id_X maps every element to itself.

Definition 0.1.21: Image and Restriction of Function

1. Let $S \subseteq X$ and $f : X \to Y$. Then:

$$f(S) := \{f(x) \mid x \in S\}$$

this is called the *image* of S. If $S = X$, then $f(X)$ is called the *image* or *range* of the function f, and is commonly denoted $\text{im}(f)$.

2. Let $S \subseteq X$. Then $f|_S$ is a function $f|_S : S \to Y$ such that

$$f|_S(x) = f(x)$$

that is, $f|_S$ is the *restriciton* of f by S.

As a function is just some "syntactic sugar" to more easily represent the set Γ_f, two functions f, g are equal if $\Gamma_f = \Gamma_g$. In terms of function notation this means that f, g are equal if for all elements x in the domain:

$$f(x) = g(x)$$

An advantage of the left-total and right-unique property is that it is easy to compose functions together, that is it is easy to chain together the output of one function to be the input of the next:

Proposition 0.1.22: Composition of Functions

Let $f : X \to Y$, $g : Y \to Z$, $h : Z \to W$ be function. Define $(g \circ f)$ to be $(g \circ f)(x) = g(f(x))$. Then $(g \circ f)$ is a function and is called g *compose* f. The process is called *function composition*.

***Proof*:**
The rule $(g \circ f)(x) = g(f(x))$ describes the subset $\Gamma = \{(x, g(f(x))) \mid x \in X\}$ of $X \times Z$, and we check the two conditions of definition 0.1.19. It is left-total: for $x \in X$, $f(x) \in Y$ exists because f is left-total, and then $g(f(x)) \in Z$ exists because g is left-total, so $(x, g(f(x))) \in \Gamma$. It is right-unique: by the right-uniqueness of f there is only one $y \in Y$ with $(x, y) \in \Gamma(f)$, namely $f(x)$, and by the right-uniqueness of g there is only one $z \in Z$ with $(f(x), z) \in \Gamma(g)$, namely $g(f(x))$, so x is related by Γ to the single element $g(f(x))$. Hence $g \circ f \colon X \to Z$ is a function, as claimed.

Example 0.1.23: Function Composition

1. Let $f : \mathbb{R} \to \mathbb{R}$, $f(x) = x^2$ and $g : \mathbb{R} \to \mathbb{R}^2$ be $g(x) = (x, 0)$. Then:

$$(g \circ f)(x) = (x^2, 0)$$

A function may also be composed with itself, given the domain and codomain match:

$$(f \circ f)(x) = x^4$$

2. Let $f : X \to Y$ be any function, id_X, id_Y the identity functions defined in example 0.1.20. Then:

$$f \circ \text{id}_X = f \qquad \text{id}_Y \circ f = f$$


This chaining together is in a way "state-independent": given three functions f, g, h, the function $(g \circ f)$ following by composing with h is equal to if we first just do f, then follow by taking the combined state $(h \circ g)$[28]:

Proposition 0.1.24: Associativity of Functions


Let $f : X \to Y$, $g : Y \to Z$, $h : Z \to W$ be function. Then:

$$h \circ (g \circ f) = (h \circ g) \circ f$$


Pictorially, function composition may be represented by the following diagrams:




or



or



and associativity may be drawn as:




***Proof*:**
By proposition 0.1.22, $g \circ f \colon X \to Z$ and $h \circ g \colon Y \to W$ are functions, and hence so are $h \circ (g \circ f)$ and $(h \circ g) \circ f$, both from X to W. Two functions with the same domain and codomain are equal when they agree at every element of the domain. For $x \in X$, the definition of composition gives


$$\big(h \circ (g \circ f)\big)(x) = h\big((g \circ f)(x)\big) = h\big(g(f(x))\big) = (h \circ g)\big(f(x)\big) = \big((h \circ g) \circ f\big)(x)$$

so $h \circ (g \circ f) = (h \circ g) \circ f$, as claimed.

These diagrams have the following special property: start on one of sets in the diagram (say A) and travel down the arrows to reach another set (say to D in the last diagram). Now start again at A and travel down to D via a different path in the diagram. Then notice that the compositions of functions agree with each other in the two paths. For example, take the following path:



and



Then the 1st red line is the composition $(h \circ g) \circ f$ and the 2nd red line is the composition $h \circ (g \circ f)$. Then by associativity, these two functions are equal

$$(h \circ g) \circ f = h \circ (g \circ f)$$

[28] can you think of an example where this is not the case in your everyday life? This would greatly help in understanding associativity

a diagram which satisfies this property for all paths is called a *commutative diagram*. These shall show up everywhere in this book, and mathematics more generally. They shall be further explored in section 0.4.

Injective, Surjective, and Bijective

There are two special types of functions that deserve to be pointed out: *injective* functions and *surjeciton* functions. These shall each represent some partial "reverse" of a function. Starting off with injectivity:

Definition 0.1.25: Injective

Let $f : X \to Y$ be a function. Then f is called *injective*, an *injection*, or *one-to-one* if the following condition holds: for all $a, b \in X$

$$f(a) = f(b) \;\Rightarrow\; a = b$$

To emphasize a function is injective, a hooked right arrow ($\hookrightarrow$) may be used like so:

$$f : X \hookrightarrow Y \qquad X \overset{f}{\hookrightarrow} Y \qquad X \hookrightarrow Y$$

Intuitively, being injective means we can embed the domain X directly into Y. As a consequence of this, we can always "recover" X in the following way

Proposition 0.1.26: Injective And Left Inverse

let f be an injective function. Then there exists a function $\ell f(X) \to X$ such that

$$\ell \circ f = \mathrm{id}$$

that is $(\ell \circ f)(x) = \mathrm{id}(x) = x$ is the identity function.

***Proof*:**
Define $\ell : Y \to X$, $\ell(y) = \ell(f(x)) = x$. Since f is injective, this is a well-defined function (if it were not injective, then $\ell(f(x))$ would be ambiguous). Then by definition $(\ell \circ f)(x) = \ell(f(x)) = x$, as we sought to show.

Notice that the inverse function ℓ inverted the function *after* applying f. What if there is some function $r : Y \to X$ such that f reverses it? The following shows when this is the case:

Definition 0.1.27: Surjective

Let $f : X \to Y$ be a function. Then f is *surjective*, a *surjection*, or *onto* if for all $y \in Y$, there exists an x such that $f(x) = y$, i.e. $f(X) = Y$. To emphasize a function is surjective, a double-headed right arrow ($\twoheadrightarrow$) may be used like so:

$$f : X \twoheadrightarrow Y \qquad X \overset{f}{\twoheadrightarrow} Y \qquad X \twoheadrightarrow Y$$

Intuitively, being surjective means that Y is "represented" by the elements of X, i.e., every element y has one or many elements of x associated to it, which is why another word for a function to be surjective is that it is "onto". As a consequence of this, we can pullback any element $y \in Y$ to some representative $x \in X$ such that $f(x) = y$. We can capture this intuition in the following way:

Proposition 0.1.28: Surjective And Right Inverse

Let $f : X \to Y$ be a surjective function. Then there exists a (and in fact more generally many) $r : Y \to X$ such that

$$f \circ r = \mathrm{id}_Y$$

that is, $(f \circ r)(y) = y$ for every $y \in Y$.

***Proof*:**
Define $r : Y \to X$ by mapping each $y \in Y$ to some element $x \in X$ such that $f(x) = y$ (such an element exists since f is surjective). Then by definition for any $y \in Y$, $(f \circ r)(y) = f(r(y)) = f(x) = y$ as we sought to show.

Another perhaps more intuitive way of seeing how surjections make every y "represented" by X is by seeing that every surjection defines an equivalence relation:

Proposition 0.1.29: Surjective And Equivalence Class

Let $f : X \to Y$ be a surjective function. Then the relation $\sim_f$ on X defined by

$$a \sim_f b \qquad \Leftrightarrow \qquad f(a) = f(b)$$

is an equivalence relation. For $y \in Y$, the set $\{x \in X \mid f(x) = y\}$ is called the *fiber* over y. The equivalence classes of $\sim_f$ are exactly the fibers, and every fiber is nonempty.

***Proof*:**

1. For each $a \in X$, $f(a) = f(a)$ by right-uniqueness, hence $a \sim_f a$
2. If $a \sim_f b$ for $a, b \in X$, then $f(a) = f(b)$. By symmetry of the equivalence relation $=$, $f(b) = f(a)$, and so $b \sim_f a$
3. If $a \sim_f b$ and $b \sim_f c$, then $f(a) = f(b)$ and $f(b) = f(c)$, so $f(a) = f(c)$ by transitivity of $=$, and $a \sim_f c$

The class of x is $\{x' \in X \mid f(x') = f(x)\}$, the fiber over $f(x)$. Since f is surjective, every $y \in Y$ is $f(x)$ for some x, so the fiber over y is the class of x, and it contains x.

The surjectivity is used only for the last claim: for any function f, the relation $\sim_f$ is an equivalence relation on X, and a point of Y outside the image of f has an empty fiber. If f is injective, then each equivalence class has size 1. Many functions that are present in mathematics are both injective

and surjective, for example:

$$f : \{1, 2, 3\} \to \{a, b, c\}, \qquad f(n) = \begin{cases} a & n = 1 \\ b & n = 2 \\ c & n = 3 \end{cases} \tag{2}$$

Such functions are given a name:

Definition 0.1.30: Bijective

Let $f : X \to Y$ be a function. Then f is said to be *bijective* or *isomorphic in* **Set** if f is injective and surjective. If X and Y are bijective, then we may write:

$$X \cong_{\mathbf{Set}} Y \qquad X \cong Y \qquad X \xrightarrow{\sim} Y$$

The intuition of bijective functions can combine the intuition behind injective and surjective functions, however they may equivalently be seen as formally defining a notion of "size". As seen in equation 2, two sets that are bijective have the same size. The issue becomes more subtle when the domain/codomain are infinite:

Example 0.1.31: Size Of Infinite Sets

Define $2\mathbb{N} = \{2n \mid n \in \mathbb{N}\}$ and $f : \mathbb{N} \to 2\mathbb{N}$ by:

$$f(n) = 2n$$

Show that f is bijective.

This gives rise to the following definition:

Definition 0.1.32: Cardinality

Let X, Y be sets. Then X is said to have the same *cardinality* as Y if there exists a bijective function $f : X \to Y$. If X, Y have the same cardinality, they are said to have the same size.

Another important property of bijective functions is that they give rise to a *unique* inverse:

Proposition 0.1.33: Bijectivity And Unique Inverse

Let $f : X \to Y$ be a bijective function. Then there exists a unique function g such that

$$g \circ f = \mathrm{id}_X \qquad f \circ g = \mathrm{id}_Y$$

where $\mathrm{id}_X : X \to X$ and $\mathrm{id}_Y : Y \to Y$ are the identity maps on the respective sets. Often, the subscript on the identity maps are dropped and the following abuse of notation is carried out:

$$g \circ f = f \circ g = \mathrm{id}$$

The function g is often denoted f^{-1}

***Proof*:**
Since f is surjective, there exists an inverse function $g : Y \to X$ such that $f \circ g = \mathrm{id}_Y$. Since f is injective, there can only be one such function (there is only element in the fiber above each $y \in Y$). Furthermore, $\mathrm{im}(f) = Y$, hence g satisfies the condition $g \circ f = \mathrm{id}_X$, as we sought to show.

0.1.34 Remark: inverse notation abuse The symbol f^{-1} may represent one of two things depending on the context. Given $f : X \to Y$:

1. if f is bijective, f^{-1} represents the unique inverse function
2. $f^{-1} : P(Y) \to P(X)$ is the function

$$f^{-1}(T) = \{x \in X \mid f(x) \in T\}$$

the images of f^{-1} are called the *pre-images* of f. This notation is particularly prevalent in topology where this the pre-image function takes center stage through continuous functions, however it will also have many applications in algebra.

Given any function $f : X \to Y$, there are certain natural functions that we may define that allows us to decompose f as a composition of injective and surjective functions with an intermediary bijective function

Proposition 0.1.35: Function Decomposition

Let $f : X \to Y$ be a function. Then there exists functions such that

$$X \twoheadrightarrow X/\sim_f \xrightarrow{\sim} \mathrm{im}(f) \hookrightarrow Y \qquad (X \to Y \text{ via } f)$$

where the 1st function is surjective, the 2nd bijective, and the 3rd injective

***Proof*:**
Define $\pi_f : X \to X/\sim_f$ by

$$\pi_f(x) = [x]_f$$

that is, π_f maps x to it's equivalence class. Next, define $F : X/\sim_f \to \mathrm{im}(f)$ by

$$F([x]) = y$$

where $y \in Y$ is chosen so that $f(x) = y$. Finally, define $\iota : \mathrm{im}(f) \to Y$ by

$$\iota(y) = y$$

that is, ι maps y to itself (since $\mathrm{im}(f) \subseteq Y$). The reader should verify that these maps have the desired properties.

This proposition gives an intriguing relation between equivalence relations and functions, namely any function may be "represented" as an equivalence relation, and equivalently any equivalence relation my be "represented" by a function.

Using functions, we may define the notion of a multiset:

Definition 0.1.36: Multiset

Let X be a set. Then a *multiset* given by elements of X is a function:

$$m : X \to \mathbb{N}$$

which assigns each element $x \in X$ a multiplicity.

Example 0.1.37: Multiset

Let $X = \{a, b, c\}$ and:

$$m(a) = 3 \qquad m(b) = 1 \qquad m(c) = 0$$

Then m defines a multiset. Commonly, this set is written as:

$$\{a, a, a, b\}$$

As practice, define another multiset n and show how to define the notion of inclusion, union, intersection, and so forth.

As a closing remark, it is a common convention in the study of Analysis (one of the major studies of mathematics) that if we have a function $f : X \to Y$, we might abuse notation and use a subset of X as the actual domain. For example, $f : \mathbb{R} \to \mathbb{R}$, $f(x) = \frac{1}{x}$ is not a function as we've defined the concept, since $f(0) = \frac{1}{0}$ is not defined [29]. If we were to re-write this to be a function, we'd write $f : \mathbb{R} - \{0\} \to \mathbb{R}$. However, it is often implied in analysis that we will restrict the domain to the points for which f is defined.

Exercise 0.1.2

1. Let $f : X \to Y$ and take $A \subseteq X$, $B \subseteq Y$. Show that $f(A) \subseteq B \Leftrightarrow A \subseteq f^{-1}(B)$
2. Let $f : X \to Y$ and $A, B \subseteq X$. Then is it true that $f(A \cup B) = f(A) \cup f(B)$? What about $f(A \cap B) = f(A) \cap f(B)$? What if there were more unions or intersections?
3. Let $f : X \to Y$, and define $f^{-1} : P(Y) \to P(X), f^{-1}(T) = \{x \in X \mid f(x) \in T\}$. Is $f^{-1}(A \cup B) = f^{-1}(A) \cup f^{-1}(B)$ for $A, B \subseteq Y$? What about $f^{-1}(A \cap B) = f^{-1}(A) \cap f^{-1}(B)$? What if there were more unions or intersections?
4. Let $\sim$ be an equivalence relation on a set S, and for $x \in S$ let $[x] = \{y \in S \mid y \sim x\}$. Show that the classes $[x]$ are nonempty, that two classes are either equal or disjoint, and that their union is S. Conversely, show that every collection of nonempty, pairwise disjoint subsets of S with union S is the collection of classes of an equivalence relation on S.
5. With $\sim$ and $[x]$ as in the previous question, let $S/\sim$ be the set of classes. Show that the *natural projection* $\pi : S \to S/\sim$, $\pi(x) = [x]$, is a surjective function, and that $\pi(x) = \pi(y)$

[29] This would be covered rigorously in a calculus or analysis class

exactly when $x \sim y$.

6. (formalities behind natural numbers). Let $s_0 = \{\}$ be the empty set and $s_{n+1} = \{s_n\}$, so that

$$S = \{\{\},\ \{\{\}\},\ \{\{\{\}\}\}, ...\} = \{s_0, s_1, s_2, \dots\}$$

is the set of the n-nested empty sets. Show that $s_m \neq s_n$ for $m \neq n$, so that $n \mapsto s_n$ is a bijection from $\mathbb{N}$ to S. Define $+ : S \times S \to S$ by $+(s_n, s_m) = s_{n+m}$ and $* : S \times S \to S$ by $*(s_n, s_m) = s_{nm}$ (for $n, m \geq 1$, the n-nested empty set with its nesting repeated m times). Show that $+$ and $*$ are commutative and associative, with identities s_0 and s_1, and that $*$ distributes over $+$, so that these create the usual natural numbers.

0.1.6 Adding Structures to Sets

So far, we have been extensively working with sets and functions. Sets by themselves have no notion of size, order, arithmetic operations, geometry, among others possible properties. Many interesting subjects in mathematics deal with these additional concepts. For this reason, mathematicians often "augment", so to speak, sets to have some extra structure:

Example 0.1.38: Extra Structure

1. (Order Structure). A set $(A, \leq)$ with an order $\leq$ is called an *ordered set*. Depending on the type of order given (ex. partial oder, total order, well order etc.), the set would be called the appropraited order (ex. paritally ordere set, totally ordered set, well ordered set, etc.)

2. (Algebraic structure) The set $\mathbb{Z}$ on its own is only numbers (and so is $\mathbb{N}, \mathbb{Q}, \mathbb{R}$). If we add a function $+ : \mathbb{Z} \times \mathbb{Z} \to \mathbb{Z}$, where $+$ acts exactly like the familiar addition we have learnt earlier in life, then $(\mathbb{Z}, +)$ now also has addition! We can add more functions to sets, for example $(\mathbb{Z}, +, \cdot)$ where $\cdot : \mathbb{Z} \times \mathbb{Z} \to \mathbb{Z}$ is the usual multiplication. If we augment a set with function(s), we call this an *algebraic structure*. This whole book will be dedicated to the study of algebraic structures.

3. (Topological Structures). Another common augmentation of a set is something called a topology. Given a set A, a set $\mathcal{T}_A$ is a set of subsets of A that follows three rules:

   (a) $\emptyset \in \mathcal{T}_A$ and $A \in \mathcal{T}_A$

   (b) if $\{U_i\}_{i \in I} \subseteq \mathcal{T}_A$ is some arbitrary subset of $\mathcal{T}_A$ indexed by I, then $\bigcup_{i \in I} U_i \in \mathcal{T}_A$ (i.e. an arbitrary union of sets in $\mathcal{T}_A$ is in $\mathcal{T}_A$)

   (c) if $U_1, U_2, ..., U_n \in \mathcal{T}_A$ is a finite subset of $\mathcal{T}_A$, then $\bigcap_i U_i \in \mathcal{T}_A$ (i.e. a finite intersections of sets in $\mathcal{T}_A$ is in $\mathcal{T}_A$)

   Then $(A, \mathcal{T}_A)$ is called a *topology* or sometimes a *space*. If a set is augmented with a sets of sets that follow these rules, it's called a *topological structure*. Topology is the natural space in which much of Real and Complex Analysis, as well as [non-classical] geometry takes place. It is the "coarsest" structure we add to sets to give sets some notion of locality.

4. (Measure Structures). Similar to a topological structure, a measure structure is one where

   (a) $\emptyset \in \mathcal{T}_A$ and $A \in \mathcal{T}_A$

(b) if $U_1, U_2, ..., U_n, ... \in \mathcal{T}_A$, then $\bigcup_i U_i \in \mathcal{T}_A$ (i.e. an countable union of sets in $\mathcal{T}_A$ is in $\mathcal{T}_A$)

(c) if $U_1, U_2, ..., U_n, ... \in \mathcal{T}_A$, then $\bigcap_i U_i \in \mathcal{T}_A$ (i.e. a countable intersections of sets in $\mathcal{T}_A$ is in $\mathcal{T}_A$)

This structure is central to generalizing the notion of "size" for general sets and is the basis for defining the integral[a].

5. (Differential structure) If you have done calculus, then you are familiar with the notion of being differentiable. There is a field of study in which we can call "sets" differentiable. Given a set S, there is a collection of functions called an *atlas* (say, $\mathcal{A}$ represents this collection) which gives a set S a "differentiable structure", and is usually denoted $(S, \mathcal{A})$. The details of what the atlas $\mathcal{A}$ contains is left for a course in differential geometry or diffeology.

6. *(Affine Scheme structure) This will be a very important structure on commutative ring that will dominate the readers who will study algebraic geometry. Any commutative ring will induce a natural topological space. A topological space represents some idea of locality on a set; a local piece is called an *open set*. A *sheaf* represents having data on each open set in a topological space in such a way that we can use local data to glue together global data (think of solving a problem by breaking it down into smaller problems and knowing you can glue it back together).

7. *(Model) In section 0.1.1, we have shown how to make logical statements given sets. The full study how sets (usually augmented with other structures) may have statements which are true or provable is the domain of *model theory*. Usually, a set M along with some collection of functions and relations is augmented in such a way to be able to study the properties of logical statements. This would be covered in a class on first order logic or model theory more generally.

[a] In particular, the Lebesgue integral

This textbook is dedicated to the study of algebraic structures. It will sometimes be the case that we encounter ordered structures [30], and only near the end of the book do we encounter topological structures (p. 1108) where it is assumed the reader has taken a course covering point-set topology[31]. The reason for the eventual mixing of structure is because different domains of mathematics start motivating each other in further exploration. For example, many geometers and algebraists found parallels between their fields, and hence algebraic geometry was born. Similarly, it was found that algebra can be used to solve topological problems, and hence algebraic topology was founded.

0.1.7 *Cardinality

(Here in there in he book, cardinality will come up. For ex, in proof that an injective map from $X \to X$ where X is finite is surjective, or when we figure out the algebraic numbers are countable, and other results later in the book)

(classical diagonalization proof?)

(as exercise, do $\{0,1\}^{\mathbb{N}}$ is bijective to $[0,1]$ by thinking of binary representation?)

[30] see section 2.4

[31] Differentiable structure's will be mentioned to motivate the concept of schemes which are based off of manifolds

0.2 Number Theory

Numbers are at the heart of mathematics and algebra. In this section, the basic properties of numbers will be explored. Some history of these concepts will be given as well to give a sense of why we call these special sets numbers.

Numbers started with our intuitive ability to understand discrete quantities (ex. 5 rocks, 2 people). In the past, it was contentious whether 0 was a number (the idea being that numbers are supposed to represent a real quantity), however it is now accepted that 0 represents the notion of "nothingness", "emptyness", or "inaction". Ratios of numbers (e.x 3/4) became important when it was important to be precise on what part of a whole object we want (ex. half the money). Negative numbers became important when considering other peoples debts (you owe 2 sheep, you "have" -2 sheep). In the times of at least the Greeks, it was discovered that there are certain numbers that are irrational (ex. $\sqrt{2}$ cannot be written as $\frac{a}{b}$, where a, b are natural numbers); the square root of any prime number shown to be irrational. The square-root of negative numbers remained undefined for awhile until NAME discovered that they are useful in finding roots of polynomials of degree 3, and it wans't till Euler that square-roots of negative numbers got the symbol $i := \sqrt{-1}$. It wasn't till later that it was understood there were many more irrational numbers than rational numbers; the collection of all rational and irrational numbers form the real numbers. The collection of all numbers $a + bi$, $a, b \in \mathbb{R}$ is known as the *complex numbers*. For reasons that shall be explored later in the book[32], any further addition to the number system beyond the complex numbers start to loose properties of numbers (ex. $ab \neq ba$ or $(ab)c \neq a(bc)$), and so we usually consider the following sets as "numbers" :

$$\mathbb{N} \subseteq \mathbb{Z} \subseteq \mathbb{Q} \subseteq \mathbb{R} \subseteq \mathbb{C}$$

We shall heavily explore the properties of all of these number systems, with the notable exception of $\mathbb{R}$. This is because the real numbers are in many ways the beginning of the exploration of "taming infinities" and start moving beyond algebra. In fact, we shall even show in section E.1 that it is impossible to construct $\mathbb{R}$ in an algebraic way.

0.2.1 GCD and Euclidean Algoritm

Definition 0.2.1: Divisibility

Let a, b be numbers. Then we say that a *divides* b, or b is *divisible by* a if there exists a number k such that

$$ak = b$$

Note that divisibility depends on the set of numbers you are working, In $\mathbb{N}$, 3 is not divisible by 5, however in $\mathbb{Q}$, 3 is divisible by 5, namely let $k = 3/5$.

Example 0.2.2: Divisibility Practice

1. Show that if $x \big| n_1$ and $x \big| n_2$, then $x \big| an_1 + bn_2$ for any $a, b \in \mathbb{Z}$.
2. Show that if $a \big| b$ and $b \big| c$ then $a \big| c$

[32] ref:HERE for details

From now on in this section, we shall limit ourselves to divisibility in $\mathbb{Z}$[33].

One special result about integers is that every number has a prime factorizaiton:

Proposition 0.2.3: Prime Factorization Of Natural Numbers

Let $n \geq 2$ be an integer. Then there exist distinct prime numbers $p_1, p_2, ..., p_k$ and positive integers $n_1, n_2, ..., n_k$ such that

$$n = p_1^{n_1} p_2^{n_2} \cdots p_k^{n_k}$$

***Proof*:**

By strong induction on n. If n is prime, then $n = n^1$. Otherwise $n = ab$ with $1 < a, b < n$, and a and b are products of primes by the induction hypothesis, hence so is n. Collecting equal primes gives the form above.

The factorization is unique up to the order of the factors (corollary 0.2.12), which needs Bézout's identity.

Every integer n with $|n| \geq 2$ is ± 1 times such a product, unique up to order and sign (corollary 0.2.12). The sign costs little: $-1 \cdot -1 = 1$, and 1 and -1 are the only integers with a multiplicative inverse in $\mathbb{Z}$.

Definition 0.2.4: Greatest Common Divisor

Let $a, b \in \mathbb{Z}$ be to non-zero integers. Then the *greatest common divisor* between these to numbers is the greatest number n such that n divides a and n divides b.
The common notation for this fact is that:

$$n|a \qquad n|b$$

Similarly, we have the dual concept:

Definition 0.2.5: Least Common Multiple

Let $a, b \in \mathbb{Z}$ be non-zero integers. Then the *least common multiple* is the smallest positive integer m such that

$$a|m \qquad b|m$$

Example 0.2.6: Greatest Common Divisor

1. $\gcd(10, 5) = 5$
2. $\gcd(100, 90) = 10$
3. $\gcd(45, 49) = 1$
4. If p, q are distinct prime numbers, then $\gcd(p, q) = 1$

[33] In chapter 10, we shall re-define divisibility in a more general context

It is natural that two prime numbers have 1 as their greatest common divisor for they have no factor in common. However, it is not necessary for numbers to be prime for their gcd to be 1. We give a name to numbers with no common factors:

Definition 0.2.7: Coprime Numbers

Let $a, b \in \mathbb{N}_{>0}$. Then if $\gcd(a, b) = 1$, a and b are said to be *coprime*.

We may find the greatest common multiple by finding the prime factorization, however this is in general very inefficient on large numbers. These values can be found in an algorithmic manner relying on the fact that numbers have a notion of size[34]

Theorem 0.2.8: Euclidean Algorithm

Given two natural numbers a, b we can find their greatest common divisor by the following technic:

1. Let $a > b$. Put them into the equation $a = bk_1 + r_1$, where k is the amount of times b fits into a, and r_1 is the remainder.
2. Once you find these values, all but k shift over to the left, and you repeat the process to find r_2:

$$\begin{aligned} b &= r_1 k_2 + r_2 \\ r_1 &= r_2 k_3 + r_3 \\ r_2 &= r_3 k_4 + r_4 \end{aligned}$$

3. The algorithm continues until $r_n = 0$ (which it will reach since a, b where finite). The final non-zero remainder r_{n-1} is the greatest common divisor.

***Proof*:**
If $a = bk + r$, then an integer divides both a and b exactly when it divides both b and $r = a - bk$, so $\gcd(a, b) = \gcd(b, r)$ when $r \neq 0$. The remainders satisfy $b > r_1 > r_2 > \cdots \geq 0$, so some r_n is 0. With $r_{-1} = a$ and $r_0 = b$, the step $r_{i-2} = r_{i-1}k_i + r_i$ gives $\gcd(r_{i-2}, r_{i-1}) = \gcd(r_{i-1}, r_i)$ whenever $r_i \neq 0$, so $\gcd(a, b) = \gcd(r_{-1}, r_0) = \cdots = \gcd(r_{n-2}, r_{n-1}) = r_{n-1}$, the last equality because r_{n-1} divides $r_{n-2} = r_{n-1}k_n$.

As an example:

[34] We shall see in chapter 10 that not all systems in which we can define a GCD will allow for a euclidean algorithm

Example 0.2.9: Euclidean Algorithm
Let $a = 20$, $b = 13$. Then:

$$\begin{aligned} 20 &= 1 \cdot 13 + 7 \\ 13 &= 1 \cdot 7 + 6 \\ 7 &= 1 \cdot 6 + 1 \\ 6 &= 6 \cdot 1 + 0 \end{aligned}$$

so $\gcd(20, 13) = 1$, the last nonzero remainder.

Using the euclidean algorithms, we may always find the solution to the following interesting linear equation:

Theorem 0.2.10: Extended Euclidean Algorithm (Bézout's Identity)

Let $a, b \in \mathbb{Z}$ be nonzero. Then there exist integers $x, y \in \mathbb{Z}$ such that

$$ax + by = \gcd(a, b)$$

***Proof*:**
Among the positive integers of the form $ax + by$ with $x, y \in \mathbb{Z}$, such as $a \cdot a + b \cdot b$, let $d = ax_0 + by_0$ be the least. Dividing with remainder, $a = qd + r$ with $q = \lfloor a/d \rfloor$ and $0 \leq r < d$, and $r = a(1 - qx_0) + b(-qy_0)$ has the same form, so $r = 0$ by the minimality of d, and $d|a$. Likewise $d|b$. Every common divisor n of a and b divides $ax_0 + by_0 = d$, so $n \leq d$, and $d = \gcd(a, b)$.

Example 0.2.11: Bézout's Identity
Recall that $\gcd(20, 13) = 1$ (example 0.2.9). Reading the steps of the Euclidean algorithm backwards expresses 1 in the form $20x + 13y$. The third step gives $1 = 7 - 6$. The second gives $6 = 13 - 7$, so $1 = 7 - (13 - 7) = 2 \cdot 7 - 13$. The first gives $7 = 20 - 13$, so $1 = 2(20 - 13) - 13 = 2 \cdot 20 - 3 \cdot 13$, and $40 - 39 = 1$.

Try doing the same with 220 and 38.

Bézout's Identity has the following neat interpretation: primes are fundamentally a multiplicative decomposition of numbers: any n is equal to $p_1^{n_1} \cdots p_k^{n_k}$ for appropriate primes p_i and powers n_i. However, they do have an additive relation between them, the Bézout identity. If we have two primes, we can (up to appropriate constants) add them to get to the multiplicative identity 1. In this way, we have a property of primes given via addition.

Corollary 0.2.12: Uniqueness Of Prime Factorization

Let p be a prime and a, b positive integers. If $p|ab$, then $p|a$ or $p|b$. Consequently, the factorization of proposition 0.2.3 is unique up to the order of the factors.

***Proof*:**
Suppose $p \nmid a$. The only positive divisors of p are 1 and p, so $\gcd(a, p) = 1$, and theorem 0.2.10 gives $ax + py = 1$. Then $b = abx + pby$, and p divides both terms, so $p|b$. By induction on the number of factors, a prime dividing a product of primes equals one of them. If $p_1^{n_1} \cdots p_k^{n_k} = q_1^{m_1} \cdots q_l^{m_l}$, then p_1 divides the right side, so $p_1 = q_j$ for some j. Cancelling it and inducting on $n_1 + \cdots + n_k$ shows that the two factorizations agree up to order.

Exercise 0.2.1

1. Let $p, q, r \in \mathbb{N}$ be prime numbers greater than 3. Show that 3 divides $p^2 + q^2 + r^2$

0.2.2 Modular Arithmetic

When counting the hours on a clock-face, we start with 12 o-clock, then add an hour to make it 1 o-clock, then another hour to make it 2 o-clock, until we circle back to 12 o-clock again, at which point we start counting again to 1 o-clock. For the rest of this section, we will say that 12 o-clock is 0 o-clock for reasons that would be explained soon. Notice how the arithmetic of the clock differs from the usual number system where for each $x \in \mathbb{N}$, there exists an n such that $n > x$. Hours on a clock could add to be zero, for example:

$$7 + 5 = 0$$

In this section, we rigorously define this notion

Definition 0.2.13: Modular Arithmetic

Let $n \in \mathbb{N}_{>0}$. Define the equivalent relation on $\mathbb{Z}$:

$$a \sim_n b \quad \Leftrightarrow \quad a - b = kn \text{ for some } k \in \mathbb{Z}$$

The collection of these equivalences classes is denoted $\mathbb{Z}/n\mathbb{Z}$[a] and is called the *integers modulo n*. The number n is called the *modulus* and if $a \sim_n b$, we say that *a is congruent to b* modulo n. If $a \sim_n b$, then it is denoted

$$a \equiv b \bmod n \qquad \text{or} \qquad a \equiv_n b$$

The equivalence classes may be denoted as:

$$[a],\ [a]_n,\ \overline{a},\ \overline{a}_n$$

where the n is dropped if the context permits it.

[a] This notation shall be elucidated on in chapter 3

Intuitively, this equivalence relation says that the difference of two numbers is a multiple of n. When $n = 12$, then this is the usual clock arithmetic. When n is any other number, the reader may imagine a clock-face with n digits.

Naturally, it has to be proven that $\sim_n$ is indeed an equivalence relation:

Proposition 0.2.14: Modular Arithmetic Is Well-defined

Let $\sim_n$ be defined as in definition 0.2.13. Then $\sim_n$ is indeed an equivalence relation

***Proof*:**
Let $x, y, z \in \mathbb{Z}$ and let $n \in \mathbb{N}_{>0}$ be any positive natural number.

1. $x \equiv x \bmod n$ since $x - x = 0 = 0 \cdot n$
2. If $x \equiv y \bmod n$ then there exists a k st $x - y = kn$. Then $y - x = -kn = (-k)n$. Then by definition $y \equiv x \bmod n$
3. If $x \equiv y \bmod n$ and $y \equiv z \bmod n$, then $x - y = kn$ and $y - z = \ell n$ for some $k, \ell \in \mathbb{Z}$. Adding these two equations, we get:

$$x - z = x - y + y - z = (k + \ell)n$$

and so $x \equiv z \bmod n$

Since all the conditions of an equivalence relation is satisfied, $\sim_n$ is indeed an equivalence relation, as we sought to show.

Example 0.2.15: Practice With Congruences
Verify the following:

1. $35 \equiv 11 \bmod 12$
2. $2 \equiv -3 \bmod 5$
3. If $a \equiv b \bmod n$, then $a + t \equiv b + t \bmod n$ for any $t \in \mathbb{Z}$
4. If $a \equiv b \bmod n$, then $a^t \equiv b^t \bmod n$ for any $t \in \mathbb{N}$

Proposition 0.2.16: Properties Of Modular Arithmetic

Let $n \in \mathbb{N}_{>0}$ and $a_1 \equiv a_2 \bmod n$, $b_1 \equiv b_2 \bmod n$. Then:

1. $a_1 + b_1 \equiv a_2 + b_2 \bmod n$
2. $a_1 - b_1 \equiv a_2 - b_2 \bmod n$
3. $a_1 b_1 \equiv a_2 b_2 \bmod n$

Furthermore, the following addition and multiplication of classes depend only on the classes $\overline{a_1}$ and $\overline{b_1}$, and not on the representatives a_1 and b_1:

1. $a_1 + b_1 \bmod n = a_1 \bmod n + b_1 \bmod n$ (in different notation, $\overline{a_1 + b_1} = \overline{a_1} + \overline{b_1}$)
2. $a_1 b_1 \bmod n = (a_1 \bmod n)(b_1 \bmod n)$ (in different notation, $\overline{a_1 b_1} = \overline{a_1}\,\overline{b_1}$)

***Proof*:**
By definition 0.2.13, $a_1 - a_2 = kn$ and $b_1 - b_2 = ln$ for some $k, l \in \mathbb{Z}$.

1. $(a_1 + b_1) - (a_2 + b_2) = (a_1 - a_2) + (b_1 - b_2) = (k + l)n$, so $a_1 + b_1 \equiv a_2 + b_2 \bmod n$.
2. $(a_1 - b_1) - (a_2 - b_2) = (a_1 - a_2) - (b_1 - b_2) = (k - l)n$, so $a_1 - b_1 \equiv a_2 - b_2 \bmod n$.
3. $a_1b_1 - a_2b_2 = (a_1 - a_2)b_1 + a_2(b_1 - b_2) = (kb_1 + la_2)n$, so $a_1b_1 \equiv a_2b_2 \bmod n$.

For the second list, recall that $\sim_n$ is an equivalence relation (proposition 0.2.14), so $\overline{a_1} = \overline{a_2}$ exactly when $a_1 \equiv a_2 \bmod n$.

1. If $\overline{a_1} = \overline{a_2}$ and $\overline{b_1} = \overline{b_2}$, then $\overline{a_1 + b_1} = \overline{a_2 + b_2}$ by (1) of the first list. So the class $\overline{a_1 + b_1}$ depends only on $\overline{a_1}$ and $\overline{b_1}$, and the sum $\overline{a_1} + \overline{b_1} = \overline{a_1 + b_1}$ is well defined.
2. If $\overline{a_1} = \overline{a_2}$ and $\overline{b_1} = \overline{b_2}$, then $\overline{a_1b_1} = \overline{a_2b_2}$ by (3) of the first list, so the product $\overline{a_1}\,\overline{b_1} = \overline{a_1b_1}$ is well defined, completing the proof.

Proposition 0.2.17: Cancellation Properties Of Modular Arithmetic

Let $n \in \mathbb{N}_{>0}$ and $a, b \in \mathbb{Z}$. Then:

1. if $a + k \equiv b + k \bmod n$ for some integer $k \in \mathbb{Z}$, then $a \equiv b \bmod n$
2. if $ka \equiv kb \bmod n$ for some nonzero $k \in \mathbb{Z}$ coprime with n ($\gcd(k, n) = 1$), then $a \equiv b \bmod n$
3. if $ka \equiv kb \bmod kn$ for some $k \in \mathbb{N}_{>0}$, then $a \equiv b \bmod n$

***Proof*:**

1. Since $(a + k) - (b + k) = a - b$, the hypothesis says $a - b = ln$ for some $l \in \mathbb{Z}$, that is, $a \equiv b \bmod n$.
2. By hypothesis $k(a - b) = ka - kb = ln$ for some $l \in \mathbb{Z}$. By theorem 0.2.10, $kx + ny = 1$ for some $x, y \in \mathbb{Z}$. Then
$$a - b = (a - b)(kx + ny) = x \cdot k(a - b) + ny(a - b) = n\big(xl + y(a - b)\big)$$
so $a \equiv b \bmod n$.
3. By hypothesis $ka - kb = lkn$ for some $l \in \mathbb{Z}$, so $k(a - b - ln) = 0$. As $k \neq 0$ and a product of nonzero integers is nonzero, $a - b = ln$, that is, $a \equiv b \bmod n$, completing the proof.

Important Results

The following are important properties of the integers modulo n:

Theorem 0.2.18: Fermat's Little Theorem

Let p be prime and $a \in \mathbb{N}_{>0}$ such that $p \nmid a$. Then

$$a^p \equiv a \bmod p$$

***Proof*:**
It suffices to show that

$$a^{p-1} \equiv 1 \bmod p$$

For, if the above holds, then multiplying both sides by a gives the desired result (proposition 0.2.16(3)).

Start by listing the first $p-1$ positive multiples of a:

$$a, 2a, 3a, ..., (p-1)a \tag{3}$$

None of them is divisible by p: for $1 \leq r \leq p-1$, $p \nmid r$ and $p \nmid a$, so $p \nmid ra$ by corollary 0.2.12. Next, no two of them are equal $\bmod p$. For the sake of contradiction, suppose that $ra \equiv sa \bmod p$ for some $1 \leq r, s \leq p-1$ where $r \neq s$. Since p is prime and $p \nmid a$, the only positive common divisor of a and p is 1, so $\gcd(a,p) = 1$, and hence by proposition 0.2.17(2):

$$r \equiv s \bmod p$$

Since $1 \leq r, s \leq p-1$, this implies $r = s$, contradicting $r \neq s$. Hence the $p-1$ terms of list (3) are congruent (modulo p) to $p-1$ distinct numbers among $1, ..., p-1$, that is, to each of these numbers exactly once.

Now, multiply the terms in list (3). Then by proposition 0.2.16(3), applied one factor at a time:

$$(1a)(2a)\cdots((p-1)a) \equiv (1)(2)\cdots(p-1) \bmod p$$

which, after collecting the factors a, is:

$$a^{p-1}(p-1)! \equiv (p-1)! \bmod p$$

Since p is prime, each number $1 \leq k \leq p-1$ is coprime to p, and hence cancelling the factors $1, 2, \ldots, p-1$ of $(p-1)!$ one at a time by proposition 0.2.17(2) gives:

$$a^{p-1} \equiv 1 \bmod p$$

and multiplying both sides by a gives $a^p \equiv a \bmod p$, as we sought to show.

The reader may ask if this can be generalized in some some way to modulo n. The key would be to generlize the step in which each number $1 \leq k \leq p-1$ is coprime with n, and indeed if $\varphi(n)$ represents the number of integers $1 \leq k \leq n$ that are coprime with n, then for every integer a coprime with n the identity can be generalized to:

$$a^{\varphi(n)} \equiv 1 \bmod n$$

This proof is best in the context of group theory, and so shall be left alone till then, however the persistent reader has all they need to attempt to directly prove this result.

Exercise 0.2.2

1. Let $a \equiv b \bmod n$. If $k \mid a, b$, is it the case that $(a/k) \equiv (b/k) \bmod n$?

0.2.3 Counting Problems

For $n \in \mathbb{N}$, the *factorial* of n is $n! = 1 \cdot 2 \cdots n$, with $0! = 1$, so that $(n+1)! = (n+1) \cdot n!$.

Definition 0.2.19: Binomial Coefficient

For $n, k \in \mathbb{N}$ with $k \leq n$, the *binomial coefficient* "n choose k" is

$$\binom{n}{k} = \frac{n!}{k!\,(n-k)!}$$

For example, $\binom{n}{0} = \binom{n}{n} = 1$ and $\binom{4}{2} = \frac{24}{2 \cdot 2} = 6$.

Proposition 0.2.20: Pascal's Rule

For $n, k \in \mathbb{N}$ with $1 \leq k \leq n$,

$$\binom{n+1}{k} = \binom{n}{k-1} + \binom{n}{k}$$

***Proof*:**
Using $k! = k \cdot (k-1)!$ and $(n-k+1)! = (n-k+1) \cdot (n-k)!$, both fractions can be written over the denominator $k!\,(n-k+1)!$:

$$\binom{n}{k-1} + \binom{n}{k} = \frac{n!\,k}{k!\,(n-k+1)!} + \frac{n!\,(n-k+1)}{k!\,(n-k+1)!} = \frac{n!\,(n+1)}{k!\,(n+1-k)!} = \binom{n+1}{k}$$

as claimed.

Proposition 0.2.21: Counting Subsets

Let X be a set with n elements and let $0 \leq k \leq n$. Then X has exactly $\binom{n}{k}$ subsets with k elements. In particular, $\binom{n}{k}$ is a natural number.

***Proof*:**
By induction on n. For $n = 0$, the only subset of $X = \emptyset$ is $\emptyset$, and $\binom{0}{0} = 1$. Suppose the claim holds for sets with n elements, and let X have $n+1$ elements. For $k = 0$ and $k = n+1$ there is exactly one subset, $\emptyset$ or X, and $\binom{n+1}{0} = \binom{n+1}{n+1} = 1$. For $1 \leq k \leq n$, fix $x \in X$ and put $X' = X \setminus \{x\}$, a set with n elements. A subset of X with k elements either omits x, and is then a subset of X' with k elements, or contains x, and is then $T \cup \{x\}$ for exactly one subset T of X' with $k-1$ elements. By the induction hypothesis there are $\binom{n}{k} + \binom{n}{k-1}$ such subsets, which is $\binom{n+1}{k}$ by proposition 0.2.20, completing the induction.

Theorem 0.2.22: The Binomial Theorem

Let x, y be complex numbers and $n \in \mathbb{N}$. Then

$$(x+y)^n = \sum_{k=0}^{n} \binom{n}{k} x^k y^{n-k}$$

***Proof*:**
By induction on n. For $n = 0$ both sides are 1. Suppose the formula holds for n. Multiplying it by $x + y$ and shifting the index of the first sum by one,

$$\begin{aligned}(x+y)^{n+1} &= \sum_{k=0}^{n} \binom{n}{k} x^{k+1} y^{n-k} + \sum_{k=0}^{n} \binom{n}{k} x^k y^{n+1-k} \\ &= \sum_{k=1}^{n+1} \binom{n}{k-1} x^k y^{n+1-k} + \sum_{k=0}^{n} \binom{n}{k} x^k y^{n+1-k}\end{aligned}$$

For $1 \leq k \leq n$ the coefficient of $x^k y^{n+1-k}$ is $\binom{n}{k-1} + \binom{n}{k} = \binom{n+1}{k}$ by proposition 0.2.20, and the remaining terms are y^{n+1} and x^{n+1}, with coefficients $\binom{n}{0} = 1 = \binom{n+1}{0}$ and $\binom{n}{n} = 1 = \binom{n+1}{n+1}$. This is the formula for $n + 1$, completing the induction.

0.3 Graphs

Graphs record which pairs of objects are linked. The group theory that follows does not need them, and this section can be read when graphs first appear there.

Definition 0.3.1: Graph

A *graph* $\mathfrak{G} = (V, E)$ consists of a set V, whose elements are the *vertices*, and a set E of two-element subsets of V, whose elements are the *edges*. Two vertices v and w are *adjacent* if $\{v, w\} \in E$. If E is instead a set of ordered pairs (v, w) of vertices with $v \neq w$, then $\mathfrak{G}$ is a *directed graph*.

For example, the vertices $1, 2, 3, 4$ with the edges $\{1, 2\}$, $\{2, 3\}$, $\{3, 4\}$, $\{4, 1\}$ form a square, and with all six two-element subsets of $\{1, 2, 3, 4\}$ as edges they form the complete graph on four vertices.

Definition 0.3.2: Graph Isomorphism

Let $\mathfrak{G} = (V_{\mathfrak{G}}, E_{\mathfrak{G}})$ and $\mathfrak{H} = (V_{\mathfrak{H}}, E_{\mathfrak{H}})$ be two graphs. A bijection $f : V_{\mathfrak{G}} \to V_{\mathfrak{H}}$ is called a *graph isomorphism* if for all $v, w \in V_{\mathfrak{G}}$

$$\{v, w\} \in E_{\mathfrak{G}} \;\Leftrightarrow\; \{f(v), f(w)\} \in E_{\mathfrak{H}}$$

that is, f preserves adjacency in both directions. If a graph isomorphism exists, then $\mathfrak{G}$ and $\mathfrak{H}$ are *isomorphic*, written $\mathfrak{G} \cong \mathfrak{H}$.

The bijection is part of the definition: two vertices with no edges and one vertex with no edges satisfy the displayed condition under the constant map, and they are not isomorphic.

0.4 Categories

In the last couple of section, we have been focusing on understanding mathematical objects, in particular, we tried constructing different types of objects (like sets and functions, numbers, graphs, and sets with binary relations) and tried showing some properties of these objects. In this section, we will focus less on the mathematical object, and more on the *relation* between mathematical objects that preserve some of the same "structure". The nouns "structure" and "relation" will be given more precise meaning through the use of *categories*.

Categories have a reputation to be difficult to understand – a reputation I (the author of this book) feel comes from an overly abstract introduction at too early a stage in the pedagogical journey. The hardest part about categories is a shift in perspective in how to think about mathematical objects, and having the sample space to intuit why this shift brings great value. Thus, before getting into the theory of category theory, let's first give an analogy to get a more intuitive understanding in what we are trying to achieve:

> Let's take any Language (ex. English). We can study any given word to get some properties of it (for example, its grammatical properties, syntactic correctness, its phonetic properties in a dialect, and so forth). These give information about words, however what we usually care about is not the properties of a word, but how words *relate* to other words. The meaning behind a sentence doesn't come just from the individual words, but from how the words "come together": This is called semantics [35]. As an example of semantics, we can even see that the meaning of words is defined in relation to other words in a sentence; for example the word *cold* usually means the absence of heat, but in the sentence "those people are giving him a cold stare", I am not referencing to the temperature of their gaze, but some lack of friendliness in their feelings towards him.
>
> If we look at language through the lens of the relation between words, we can get some insights on how language is used. An excellent example of this is translation. Let's say we're trying to translate from English to Sanskrit (or really any two languages). Both English and Sanskrit are languages, and so they have words (i.e. the objects) and rules (i.e. the relation between objects). Don't worry for a moment about exceptions to rule in particular languages (If it helps the reader, pretend they don't exist for the sake of the analogy), the main idea is that English and Sanskrit (and all languages) have words and rules that govern their use. When we compare English to Sanskrit, what we will do is see how the relations of the words in English (ex. conjugations, articles, etc.) link to those in Sanskrit (ex. declension, compounds, etc.). In a sense, we don't care about what the particular words of the respective language are. What we care is to find the word form one language that will create the same relations in the other language.
>
> For example, If I say "dog" in English, then the sentences "The dog barked", "I took the dog for a walk", or "Many dogs like to chase cats" all make sense, while "I dog the took for a walk" is not a sentence that makes sense, since the position of the word "dog" and "take" are wrong given the grammatical rules in the English languages. In Sanskrit, the grammatical rules are different: If we directly translate the sentence "I dog the took for a walk" to Sanskrit, the sentence will actually make sense! That is because the rules of Sanskrit are different than English. In fact, it is a little more subtle than this: There is no "a" (like "a walk") or "the" in Sanskrit – if you're translating from English to Sanskrit,

[35] Semantics is the study of the meaning that sentences (or any discourse) carries

> we can't replace "a" with a Sanskrit word (since non exist). Instead, we will make sure that the words we choose in Sanskrit when translating the English sentences will have the appropriate *relations* in order to capture the meaning

The entire point of this analogy is to show that it is useful to understand objects not how they "intrinsically" are, but how they "in relation" to other objects [36]. The analogy showed that an advantage of this approach comes from a better understanding of how to translate sentences. Similarly, thinking about mathematical objects by how they relate to one another will let us be able to compare object by seeing if one mathematical object has the same type of relations with other objects.

In fact, we have already done this before: when we worked with ordered structures (ex. $(\mathbb{N}, \leq)$), we studied objects by how they related to other objects. We can even make definitions based on how objects relate. For example, in $(\mathbb{N}, \leq)$, define the *smallest* to be the object x such that for every other element $y \in \mathbb{N}$, $x \leq y$. Then 0 is the smallest object. Hover, in $(\mathbb{Z}, \leq)$ no object is the smallest object, because for any $x \in \mathbb{Z}$, there exists $x - 1 \in \mathbb{Z}$ such that $x - 1 \leq x$.

In the following section, we will try to more rigorously define a way to talk about the relation between objects

0.4.1 Important Concepts

This section is very much a cursory glance of the elementary concepts of category theory for the sake of exposure rather than for internalizing the definitions and working through problems. Let's start by giving a high-level idea of that a category is. This definition should hold both information about objects and the relation between objects:

Definition 0.4.1: Pre-Definition Of Category

A Category $\mathbf{C}$ is a collection[a] of objects and relations between objects:

1. We denote the collection of objects of $\mathbf{C}$ by $\text{Obj}(b)$.
2. For any to objects $A, B \in \text{Obj}(\mathbf{C})$, $\text{Hom}_{\mathbf{C}}(A, B)$ denotes the collection of relation between objects, which we call *morphisms*. In particular, if $f \in \text{Hom}_{\mathbf{C}}(A, B)$, then f is called a morphism. Morphism are *directional*, meaning that if $f \in \text{Hom}_{\mathbf{C}}(A, B)$, it is *not* the case that $f \in \text{Hom}_{\mathbf{C}}(B, A)$ (unless $A = B$)

   If $f \in \text{Hom}_{\mathbf{C}}(A, B)$, we shall write $f : A \to B$ to emphasize the directionality.
3. If $f \in \text{Hom}_{\mathbf{C}}(A, B)$, and $g \in \text{Hom}_{\mathbf{C}}(B, C)$, then there must exist a morphism $h \in \text{Hom}_{\mathbf{C}}(A, C)$ that we associate g and f; we'll write $h = gf$, $h = g \cdot f$, or $h = g \circ f$, and call h the *composite morphism* of f and g.

[a] the word *collection* is used instead of *set* for a technical reason. More on that after this definition

The fact that we said *collection* instead of *set* is because of a quirk of logic. In particular, once we properly define what a category is, we will show that sets and functions between sets will form a category. Then $\text{Obj}(\mathbf{Set})$ will have to be *a set of all sets*, but it can be proven that no such set exists! This is called *Russel's Paradox*, and is addressed in chapter **??**. The morphisms in $\text{Hom}_{\mathbf{C}}(A, B)$ cannot be chosen arbitrary, they shall have to satisfy the following properties:

[36] The philosophy behind this idea is called *structuralism*

1. (identity morphism) For each $A \in \text{Obj}(\mathbf{C})$, there must at least exists morph $1_A \in \text{Hom}_{\mathbf{C}}(A, A)$ such that for any $f \in \text{Hom}_{\mathbf{C}}(A, X)$ and $g \in \text{Hom}_{\mathbf{C}}(X, A)$ (for any $X \in \text{Obj}(\mathbf{C})$, we have:
$$f\text{id}_X = f \qquad \text{and} \qquad \text{id}_X g = g$$
2. (associativity) For $f \in \text{Hom}_{\mathbf{C}}(A, B)$, $g \in \text{Hom}_{\mathbf{C}}(B, C)$ and $h \in \text{Hom}_{\mathbf{C}}(C, D)$,then if $\alpha = gf$ and $\beta = hg$, then:
$$h\alpha = \beta f \qquad \text{i.e.} \qquad h(gf) = (hg)f$$

The motivation behind these rules will come in chapter 8.

Example 0.4.2: Category of Set

The prototypical examples of a category is **Set** with object as sets and morphisms as functions, namely for any two sets $X, Y \in \text{Obj}(\mathbf{Set})$, $\text{Hom}_{\mathbf{Set}}(X, Y)$ is the collection of all functions from X to Y. For any $X \in \text{Obj}(\mathbf{Set})$, the identity function is the identity morphism, and section 0.1.5 showed functions are associative.

We shall cover more examples when there is more material to cover in chapter 8 and more advanced examples in part XII.

Let us now go over some important concepts that shall come up continuously throughout the entire textbook.

Definition 0.4.3: Isomorphism

Let $\mathbf{C}$ be a category (the reader can keep in mind **Set**). Then we shall say that $X, Y \in \text{Obj}(\mathbf{C})$ are *isomorphic* if there exists morphisms $f \in \text{Hom}_{\mathbf{C}}(X, Y)$ and $g \in \text{Hom}_{\mathbf{C}}(Y, X)$ such that $fg = \text{id}_X$ and $gf = \text{id}_Y$. We shall sometimes abuse notation and simply write $fg = gf = \text{id}$. If X, Y are isomorphic, we shall write:
$$X \cong_{\mathbf{C}} Y$$

Example 0.4.4: Isomorphisms in Set

Let $\mathbf{C} = \mathbf{Set}$. Show that X, Y are isomorphic if and only if $|X| = |Y|$. This shows that the relations in the relations in the category **Set** "capture" or "remember" cardinality information of sets. If we had different morphisms, we can have different types of information.

Recall that what we care about in category theory are the relations between objects and not necessarily the objects themselves. As a consequence, results proven in **Set** shall be true for all sets of the same cardinality. More generally, we shall see that results proven in category for an object X shall be true *up to isomorphism*, that is if they are true for X and $X \cong_{\mathbf{C}} Y$, then they are true for Y.

The reader may think to themselves that cardinality information is not much to preserve, for example we may have two sets of the same cardinality that satisfy different distinct predicates. This is because **Set** is a very simple category and each morphism holds little information[a]. We shall often extend the objects and morphism of **Set** to hold more information.


[a]The knowledgeable category theorist may complain that by Yoneda's lemma, any locally small category can embed into **Set** and so the category is far from being simple. The aforementioned simplicity is from the basic description and isomorphisms classes rather than the complicated subcategories we may produce

The next important idea is that of *commutative diagram*. These can be thought of as defining sets of rules:


Definition 0.4.5: Commutative Diagram

Let $\mathbf{C}$ be a category. Then a *commutative diagram* is a graph where each node is an object $X \in \text{Obj}(\mathbf{C})$ and each edge is a morphism (with appropriate domain and codomain) where for each closed loop in the graph (disregarding orientation), the composite morphisms must agree.

To elucidate the last condition, consider:



This forms a closed path, and hence composition must agree, and so $gf = h$. Another common example is:



Then:


$$gf = ih$$

As we care about the relations between objects, commutative diagrams will be the building for most categorical theorems. A lot of results shall come down to saying "the following diagram commutes". Let us apply this to the first concept of category theory: *universal properties*. A universal property shall often be a property that captures the *essence* of a predicate in such a way that we can ask whether an object in different categories have or don't have the property. This is part of where the word *universal* comes from; these shall represent properties that can be described *universally between categories*. The full generality of universal properties is something we shall delay for chapter 8. For now, let us give an important example of the *universal property of quotients*. We shall show what they exist **Set**, and in each part of the book we shall see how the majority of categories we work with shall have objects satisfying this universal property.

The name suggests some notion of "dividing". This is certainly strongly related to dividing in the traditional numerical sense, however the connection to dividing would be too large of a build up for the expository nature of this section, and so it will have to be relegated to chapter 10. Instead, the reader should think of *equivalence relations* of a way of dividing up a set. The universal property of quotients in **Set** shall show that there is an object that represents the equivalence relation:

Theorem 0.4.6: Universal Property Of Quotient Sets

Let A be a set and $\sim$ be an equivalence relation on A. Let $f : A \to Z$ be any set function such that $a \sim b \Rightarrow f(a) = f(b)$. Then there exists a unique map φ from $A/\sim$ to Z such that the following diagram commutes



***Proof*:**
Let's say $f : A \to Z$ respected where $a \sim b \Rightarrow f(a) = f(b)$. we want to ask if there exists a unique map such that

$$f = F \circ \pi$$

that is

$$f(x) = F(\pi(x))$$

Consider the map $F : (A/\sim) \to Z$, $F([x]) = f(x)$. This map is well-defined since if $[x] = [y]$, then $x \sim y$ so $f(x) = f(y)$.

Furthermore, this map is unique. If $F, F' : (A/\sim) \twoheadrightarrow Z$ were two well-defined maps, then it must be that $F(\pi(x)) = f(x) = F'(\pi(x))$ making $F = F'$, showing uniqueness, completing the proof.

Essentially, given an equivalence relation $\sim$ on a set A it can be "represented" by the object $A/\sim \in \text{Obj}(\mathbf{Set})$ which captures the right amount of information such that any other object that tries to captures it is always linked to $A/\sim$. In other words, $A/\sim$ is in a sense always in an object that tries to represent the equivalence classes of A.

This will conclude our quick exposition of category theory. In chapter 8, we shall properly introduce the theory of category theory at the "elementary level". In part XII, we shall properly cover category theory in its full generality and introduce the important major results that students ought to carry throughout their mathematical career.

0.5 Matrices

This section can be comfortably skipped until chapter 13.2. It will also be referenced in section 1.2.5⋆ for examples of groups, but it is skippable without any loss (since it's just one out of over a dozen example of groups that will be presented).

In this book, we will work with many structures. Some of them will be very different from one another, while others share striking similarities. Many of these more similar mathematical structures will be able to be "represented" by matrices. We will define more rigorously for something to be "representable" by matrices later – for now we want to gain some basic appreciation and understanding of how to use matrices.

(History going back to China, this is the early motivator for matrices compared to the "new" one of being a useful classification theorem. Define a matrix. Show it's used to solve systems of linear equations. Explain Gaussian elimination)

(Later, Gauss developed a way to multiply matrices. The intuition shall come in chapter 13)

Part I

Groups

The concept of a group is the culmination of multiple branches of mathematics converging on a unifying object that appears in many domains. One of the first mathematical settings in which the ideas leading to the modern notion of a group appeared was the study of polynomials and their solutions. A young[37] mathematician by the name of Évariste Galois contributed a decisive insight to the question of whether the roots of a polynomial could always be expressed by a formula analogous to the quadratic equation using the coefficients, elementary arithmetic operations of $+, \times, -, \div$, and radicals (i.e. $\sqrt[n]{-}$). This is the problem of *solvability of degree n-polynomials*[38]. The degree 3 (cubic) and degree 4 (quartic) cases had been solved in the affirmative roughly 300 years earlier[39]. Abel proved that there is no formula by radicals for the general degree 5 (quintic) polynomial. Galois developed a criterion that determines whether a particular polynomial is solvable by radicals. In particular, there are quintic polynomials $ax^5 + bx^4 + cx^3 + dx^2 + ex + f$ with rational coefficients whose roots cannot be expressed in terms of their coefficients using $+, \times, -, \div$ and radicals. We shall prove this in section 20.2.4.

Around the same time, mathematicians started to discover that there are "more geometries" than just the usual flat geometry of Euclidean space. It was shown that one of Euclid's foundational axioms, the 5th postulate (or parallel postulate), could be replaced by alternative assumptions without producing a contradiction, assuming the consistency of the other axioms. Near the beginning of these developments, a mathematician by the name of Felix Klein saw that the notion of a group is intimately connected with understanding these new geometries, and so he developed the *Erlangen Program*, whose goal was to describe geometries in terms of the transformation groups that preserve their relevant properties[40]. Around the same time, a Norwegian mathematician named Sophus Lie (pronounced "Lee") developed the theory of *Lie groups* which combines group structures and smooth shapes (smooth manifolds) in hopes of extending the techniques of Galois's theory to the study of differential equations [41]. Overall, groups became a major tool in geometry.

While all of this was happening, group-like structures were already appearing in *number theory*. While Gauss was studying binary quadratic forms (expression of the form $ax^2 + bxy + cy^2$), he found that suitable classes of forms with the same "discriminant"[42] can be combined by a rule now called *Gauss composition*: under this rule, the classes form a finite abelian group called the *form class group*. This is a classical example of a *class group*[43]. In another area of number theory, Dirichlet proved that every arithmetic progression $a, a+m, a+2m, \ldots$, where a and m have no common factor greater than 1, contains infinitely many primes. His proof used characters: group homomorphisms on the invertible remainders modulo m that turn multiplication of remainders into multiplication of complex numbers. We shall cover these results (in modern algebraic language) in chapter 50 and [16, Dirichlet's Theorem on Primes in Arithmetic Progressions].

[37] Évariste Galois was shot in a duel on 30 May 1832 and died the following day. The familiar story that he wrote down Galois Theory the night before the duel is an exaggeration: much of his mathematical work predated it.

[38] Here "solvability" means "solvability by radicals": whether the roots can be expressed using arithmetic operations and radicals. It does not mean whether roots exist at all. In modern terms, over a field of characteristic zero, a polynomial is solvable by radicals precisely when its Galois group is a solvable group.

[39] See this link for the cubic formula and this link for the quartic.

[40] The Erlangen Program was later generalized in *Cartan geometry*, which uses Cartan connections on principal bundles to describe geometries beyond the original program's framework. The broader idea of understanding geometry through symmetries also became important in physics; Noether's theorem, for example, relates continuous symmetries of physical systems to conservation laws.

[41] This material belongs in a course on Lie groups, see *Lie Groups* [97].

[42] see definition 19.6.27

[43] More precisely, for a fundamental discriminant D, the form class group is isomorphic to the narrow ideal class group of the quadratic field $\mathbb{Q}(\sqrt{D})$, see [15, Ideal Class Group]. When $D < 0$, the narrow and ordinary ideal class groups agree.

In these early days, different branches of mathematics were developing group-like ideas in slightly different ways. The modern abstract definition emerged gradually through the work of mathematicians such as Camille Jordan, Arthur Cayley, and Walther von Dyck[44]. The formalization of the definition of a group became a huge stepping stone, allowing many disciplines to recognize its usefulness in their domains. Today, groups are a major, if not central, object in almost every branch of mathematics, and they have also been extensively used in physics, chemistry, cryptography, computer science, and many more fields. A central reason groups are fundamental in so many fields is that they can encode the *symmetries* of a system, a notion that comes up naturally a little bit everywhere.

A modern mathematician would now consider groups to be a rather universal and "natural" object. However, groups came late in the development of mathematics, partly due to the mathematical groundwork that needed to happen and partly due to their abstract nature, which can make them seem unnatural to a first-time viewer. A consequence of this is that teaching groups introduces a new level of abstraction that many students have not experienced. The difficulties are further compounded by the fact that visualizations of many groups are scarce or impractical[45]. This, however, is not a bad thing: a whole new way of learning and "experiencing" mathematical objects is the reward for internalizing groups and all the further objects built from them.

In this Part, we shall cover in detail all the fundamental concepts of groups. Most of these concepts shall be instrumental in the rest of the textbook, and the reader shall find that this part of the book is the nexus for most of the algebraic tools that we shall cover in the rest of the book.

For Graduate Student The interpretation of a group representing symmetry is in fact very natural: all groups can be represented as a category with one objects whose morphisms are isomorphisms. In particular, any group G is associated to the category BG. From this perspective, it is not that it is *an* interpretation, but *the* interpretation.

The symmetry is "realized" via a functor to another category. For example, a group action on a set X is equivalent to a covariant functor $BG \to \mathbf{Set}$ that sends the single object of BG to X. A representation is a functor $BG \to \mathbf{Vect}_k$ that sends the single object to a vector space. More generally, a G-action on an object $c \in \mathbf{C}$ is a functor $BG \to \mathbf{C}$ that sends the single object to c[a].

[a] Covariant functors correspond to left group actions, and contravariant functors correspond to right group actions.

There is another way that I (the author of this book) sees groups. They feel like naturally "second-order" objects, in the loose sense that they often encode transformations or invariants associated with an object we first want to study. If we are trying to study some object (numbers, shapes, graphs, etc.), we will want to understand some property of the object. This property can be local (like functions defined on a neighborhood) or global (e.x., homotopy classes of loops based at a point, or symmetries of the whole object). These questions often lead us to consider transformations or equivalences of the object. Groups arise naturally when those transformations are invertible and compose: the automorphisms of an object are its invertible structure-preserving maps to itself, and they form a group under composition[46]. Thus, groups are one way of capturing information about

[44] See [66, 11, 49] for these original works.

[45] We shall see that there are ways of representing any group as a group of symmetries, but sometimes the visual picture is less helpful; for example, some groups are most naturally studied through their actions on very high-dimensional spaces (i.e. 100'000+ dimensional).

[46] In an ordinary category, an automorphism is an isomorphism from an object to itself. In higher categories, analogous notions of equivalence can involve invertibility up to higher morphisms.

an object. There can be other kinds of information about an object (e.g., curvature or twisting) that use additional structures and are not captured by a group alone. Hence, groups are just a part of the puzzle of looking for information about an object.

1

Introduction to Groups

In this chapter, you will cover the basic properties of groups. In the process, we will prove statements that the reader perhaps thought were axiomatic. For example, if $ab = ac$, does that mean $b = c$? We will classify two very important sub-categories: groups with the axiom of *commutativity* ($ab = ba$), and those without it. These two categories of groups will set the narrative for how we study groups, meaning this one axiom plays an incredibly central role in the study of groups! We will cover many examples of groups to get a taste on what groups are, and define the groups which will be referenced indefinitely throughout the rest of the book. We will then cover how to compare two groups, and define the notion of equality between two groups. We will then see how we can use groups to "represent" a system of objects. For example, we will use a group to represent all possible ways of rotating an object.

1.1 Basic Properties and Definitions

As mentioned in [43], algebraic structures are sets along with a function (or functions) which must follow certain rules. The most common type of function used for an algebraic structure is called a *binary operation*:

Definition 1.1.1: Binary Operation

1. A *binary operation* $*$ on a set G is a function $* : G \times G \to G$. For any $a, b \in G$, we shall write $a * b$ or $*(a, b)$. Often the notation is abbreviated to ab.
2. A binary operation $*$ on a set G is *associative* if for every $a, b, c \in G$ we have $a * (b * c) = (a * b) * c$
3. If $*$ is a binary operation on a set G we say elements a and b *commute* if $a * b = b * a$. We say $*$ (or G) is *commutative* if for every $a, b \in G$, $a * b = b * a$

The star of the show in group theory is the binary operation. This function is the key mathematical structure added to a set which we study in group theory. Different group structures on the same set are different binary operations.

Example 1.1.2: Binary Operations

1. Arithmetic operations are a good source of binary operations. As we have discussed in the preliminary chapter, $+$ and $\times$ are functions that take in two numbers as input, and output one number. If you want to practice proving something is a function, you can try showing that $+ : \mathbb{Z} \times \mathbb{Z} \to \mathbb{Z}$ is a function (and since the domain is the cartesian product of two copies of the codomain, it's a binary operation). Similarly, you can do the same with $- : \mathbb{Z} \times \mathbb{Z} \to \mathbb{Z}$.
2. Is $-$ a binary operation with $\mathbb{N}$ (i.e. is $- : \mathbb{N} \times \mathbb{N} \to \mathbb{N}$ a binary operation)? What about $\times$ and $\div$? Which of these binary operations are associative? Are they commutative? What if you switch $\mathbb{N}$ with $\mathbb{Z}$, $\mathbb{Q}$, or $\mathbb{R}$?
3. When working with sets, it is common to take the union or intersection of sets. These are binary operations. If A is a set and $P(A)$ is its powerset, then $\cup : P(A) \times P(A) \to P(A)$ is a binary operation. Similarly for $\cap$
4. The greatest common divisor and the least common multiple of two nonzero integers (definition 0.2.4, definition 0.2.5) are again nonzero integers, so gcd and lcm are binary operations on $\mathbb{Z} \setminus \{0\}$. Is either of them a binary operation on $\mathbb{N}$?
5. If you have taken some multi-variable calculus, then the cross product $\times : \mathbb{R}^3 \times \mathbb{R}^3 \to \mathbb{R}^3$ is an example of a binary operation.
6. Take $E : \mathbb{N} \times \mathbb{N} \to \mathbb{N}$ to be $E(x, y) = x^y$. Check that $E(x, E(y, z))$ is not necessarily equal to $E(E(x, y), z)$ (that is $x^{(y^z)}$ is not necessarily equal to $(x^y)^z$). Hence, exponentiation is a non-assotiative operation.
7. Given two functions f and g over the same domain and codomain ($f : X \to X$ and $g : X \to X$), their composition. Thus composition of functions with the same domain and codomain forms a binary operation.

With these intuitions, we can move on to defining a group:

Definition 1.1.3: Group

A *group* is an ordered pair $(G, *)$, where G is a set and $*$ is a binary operation on G satisfying the following axioms:

1. associativity: $(a * b) * c = a * (b * c)$
2. there exists an element e in G, called the *identity* of G, such that for every $a \in G$, we have $e * a = a$
3. For each $a \in G$ there is an element $b \in G$ called an *inverse* of a, such that $ab = ba = e$. We denote this element b by a^{-1}, so that we can equivalently write $a^{-1} * a = e$

The group $(G, *)$ is called *abelian* (or commutative) if $a * b = b * a$ for every $a, b \in G$.

If $(G, *)$ is a group, we say that G is a group under $*$.

1.1.4 Note Some authors like to make it explicit that it's closed under the operation, meaning if $a, b \in G$, then $a * b \in G$. However, that is implied in the definition of binary operation (i.e. a function), since the codomain of $*$ is G.

Example 1.1.5: First Encounter With Groups

In the following examples, when we are working with numbers, think of them only as a set, and define the operations $+$, $\times$ or others in the way they were intuitively defined when learning arithmetic's.

1. $(\mathbb{Z}, +)$, $(\mathbb{Q}, +)$, $(\mathbb{R}, +)$ are groups. We would say, for example, that $\mathbb{Z}$ is a group under $+$. For each of these examples, we would have the identity to be $e = 0$, and for each element a, $a^{-1} = -a$. Note that technically, the $+$ in each group is not the same $+$, because the domains and co-domains are different. Note that $\mathbb{N}$ is *not* a group under $+$, since not every element has an inverse: There does not exist an $a \in \mathbb{N}$ such that $2 + a = 0$ (i.e. $-2 \notin \mathbb{N}$). [a]
2. $\mathbb{Z}, \mathbb{Q}, \mathbb{R}$ and $\mathbb{C}$ under $\times$ are *not* groups. $\mathbb{Q} - \{0\}$, $\mathbb{R} - \{0\}$ $\mathbb{C} - \{0\}$, $\mathbb{Q}_{>0}$, $\mathbb{R}_{>0}$ *are* groups under $\times$, with $e = 1$, and $a^{-1} = \frac{1}{a}$. Why is that? Take a moment to think about why removing the zero will make those sets groups. Is $\mathbb{Z} - \{0\}$ a group under $\times$? Is $(\mathbb{Z} - \{0\})$ a group under $+$?
3. For any $n \in \mathbb{N}$, $\mathbb{Z}/n\mathbb{Z}$ is a group under modulo $+$ $(\mathbb{Z}/n\mathbb{Z}, +)$. Can you show that 0 is the identity? Can you show that every number has an inverse? Note that $((\mathbb{Z}/n\mathbb{Z}), \times)$ under $\times$ is *not* a group in general! $(\mathbb{Z}/n\mathbb{Z} \setminus \{0\}, \times)$ *is* a group when n is prime. You can pick some non-prime n and try it (ex. $n = 4$). The general proof that $(\mathbb{Z}/n\mathbb{Z} \setminus \{0\}, \times)$ is a group when n is prime will come later (after we introduce theorem 2.3.11)
4. If $(A, \bullet_A)$ and $(B, \bullet_B)$ are groups, we can form a group on their cartesian product $A \times B$ called the *direct product group*, whose elements are those in the Cartesian product

$$A \times B = \{(a, b) | a \in A, b \in B\}$$

and the binary operations is defined point wise:

$$(a, b) * (c, d) = (a \bullet_A c, b \bullet_B d)$$

We can denote this group and its binary operation $(A \times B, (\bullet_A, \bullet_B))$. A common example of a direct product of group is $(\mathbb{R} \times \mathbb{R}, (+, +))$, with the usual notation of vector-addition in $\mathbb{R}^2$. We will dedicate a lot of energy understanding the details of the Cartesian product of groups in chapter 5.

5. Define $+_2 : \mathbb{Z} \times \mathbb{Z} \to \mathbb{Z}$ $x +_2 y = 2 + x + y$. The operation $+_2$ is associative, since

$$(x +_2 y) +_2 z = (2 + x + y) +_2 z = (2 + x + y) + 2 + z = 2 + x + (2 + y + z) = x +_2 (y +_2 z)$$

Furthermore, $e = -2$, since

$$x +_2 -2 = x + 2 - 2 = x$$

and $x^{-1} = -x - 4$ since

$$x^{-1} +_2 x = -x - 4 + 2 + x = -2$$

showing that $(\mathbb{Z}, +_2)$ is indeed a group. Notice that $(\mathbb{Z}, +_2)$ and $(\mathbb{Z}, +)$ are different (for example, their identity is different)[b]. When introducing multiplication to integers, we shall want $+$ and $\cdot$ to behave well together. The usual $+(x, y) = x + y$ will insure this[c].

6. $G = (\mathrm{Mat}_n(\mathbb{R}), \cdot)$ is almost forms a group. A binary operation exists, identity exists, and associativity holds. However, there are non-invertible matrices, meaning that $\forall M \in G$, it's not necessarily the case that $\exists N \in G$ such that $NM = \mathrm{I}$. We will explore this in section 1.2.5⋆

7. Take $\{e\}$ to be the set with a single element, and define the binary operation $\cdot$ to be the only possible function:

$$e \cdot e = e$$

that is, the binary operation that treats e like an identity. Then $(\{e\}, \cdot)$ is a group! This group is called the *trivial group*.

8. Take a set A and its powerset $P(A)$. Is $(P(A), \cup)$ a group? What about $(P(A), \cap)$? answer: [d]

9. Take $(\mathbb{Z}, -)$, where $-$ is the operation of subtraction. Then $(\mathbb{Z}, -)$ is not a group! Can you see which axiom fails?

10. Here is a more complex example which fails for the same reason as the previous one. Take $(\mathbb{R}^3, \times)$ where $\times$ represents the cross product:

$$\begin{pmatrix} a_1 \\ a_2 \\ a_3 \end{pmatrix} \times \begin{pmatrix} b_1 \\ b_2 \\ b_3 \end{pmatrix} = \begin{pmatrix} a_2 b_3 - a_3 b_2 \\ a_1 b_3 - a_3 b_1 \\ a_1 b_2 - a_2 b_1 \end{pmatrix}$$

or, if you have taken a physics or linear algebra class, you might have seen it defined as

$$a \times b = \det \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ a_1 & a_2 & a_3 \\ b_1 & b_2 & b_3 \end{vmatrix}$$

where we represent the three components of the vector as $\mathbf{i}$, $\mathbf{j}$, $\mathbf{k}$, and we use the determinant to shorten notation. Then $(\mathbb{R}^3, \times)$ is *not* a group! The cross product is not associative! Take

$$\begin{pmatrix} 1 \\ 2 \\ 3 \end{pmatrix}, \begin{pmatrix} 2 \\ 3 \\ 4 \end{pmatrix}, \begin{pmatrix} 3 \\ 4 \\ 5 \end{pmatrix}$$

Then

$$\begin{pmatrix}1\\2\\3\end{pmatrix}\times\begin{pmatrix}2\\3\\4\end{pmatrix}=\begin{pmatrix}-1\\2\\-1\end{pmatrix}\qquad\begin{pmatrix}-1\\2\\-1\end{pmatrix}\times\begin{pmatrix}3\\4\\5\end{pmatrix}=\begin{pmatrix}14\\2\\-10\end{pmatrix}$$

and

$$\begin{pmatrix}2\\3\\4\end{pmatrix}\times\begin{pmatrix}3\\4\\5\end{pmatrix}=\begin{pmatrix}-1\\2\\-1\end{pmatrix}\qquad\begin{pmatrix}1\\2\\3\end{pmatrix}\times\begin{pmatrix}-1\\2\\-1\end{pmatrix}=\begin{pmatrix}-8\\-2\\4\end{pmatrix}$$

meaning $(\mathbb{R}^3,\times)$ is *not* associative, meaning it's not a group. The cross product is a different kind of operation, a *Lie bracket*, which makes $\mathbb{R}^3$ a Lie algebra.

11. If you know some properties of complex numbers, then $G=\{z\in\mathbb{C}|z^n=1 \text{ for some } n\in\mathbb{Z}^+\}$ is a group! Visually, this group looks like points on the unit circle in the complex plane. The main idea here is since $z^n=1$, then elements in G will be of the form $e^{\frac{2\pi i}{n}\cdot k}$ for $1\le k\le n$. If you are comfortable with multiplying complex numbers and trust me that all the elements of G are of this form, then you can check that this is a group.

    More generally, $G=\{z\in\mathbb{C}\mid \|z\|=1\}$ is a group with multiplication (i.e. the unit circle in the complex plane). You can verify that $1\in G$ and for any $z,w\in G$, $\|zw\|=\|z\|\,\|w\|=1\cdot 1=1$. Multiplication on G is associative because multiplication on $\mathbb{C}$ is. Each $z\in G$ has the inverse $z^{-1}=\bar{z}$, since $z\bar{z}=\|z\|^2=1$, and $\bar{z}\in G$ because $\|\bar{z}\|=\|z\|=1$.

12. If you know some complex arithmetic's, show that $G=\{z\in\mathbb{C}\mid 0.1<|z|<10\}$ with the usual multiplication structure of $\mathbb{C}$ satisfies associativity, having an identity, and having an inverse, but is *not* a group.

13. Let A be any set. Consider the collection of every bijective function from A to itself:

    $$G=\{f:A\to A\mid f \text{ is bijective}\}$$

    Then with the binary operation of composition, $(G,\circ)$ is a group. What is the identity, and why do inverses always exist? The collection of bijective functions is a very common group that shows up in many different ways in different areas of mathematics and so has lots of notations:

    $$\mathrm{Bij}(A)\qquad \mathrm{Sym}(A)\qquad \mathrm{Aut}_{\mathbf{Set}}(A)$$

Part of the motivation behind learning group theory is in the abundance of areas groups show up in mathematics. The more domains of mathematics you learn, the more types of groups you will encounter. For example, field theory (Part IV) has *Galois groups* at its heart, Differential Geometry have *lie groups* that allow for a large classification of and construction of "manifolds" (a generalization of the notion of Euclidean space), Algebraic Geometry (see *Classical Algebraic Geometry* [42]) use *algebraic groups* to represent more complicated objects in more familiar terms, Analysis uses *topological groups* (for example, Amenable and Locally Compact groups) in the study of Fourier Analysis and Functional Analysis, Algebraic topology has the *fundamental group* and *homology group* at its heart, and combinatorics uses *geometric group theory* (for example, the *Kleinian group* or *hyperbolic groups* shows up frequently).

Groups can also be thought of as one of the "basic" structures that many other structures will build on or act on. Of the algebraic structures that will be explored in this book, rings, fields, vector-spaces, modules, and (lie and associative) algebras are all also groups.

Overall, it is worth remembering that groups are a very common mathematical object that show up a little bit everywhere.

[a] $\mathbb{N}$ is a weaker structure called a monoid which does not require inverses. More on them in section 7.1
[b] I'm careful in saying they are different instead of saying they have *different group structures*. There is a subtly here on how we define two group structures being the same or different. This is addressed in section 1.4
[c] we shall desire distributivity, or for the expert that $\mathbb{Z}$ is representable in its endomorphism ring
[d] the answer is no! Like $\mathbb{N}$, these are example of monoids

In general, when we write a group, the group operation will be clear from context, so instead of writing $(G, *)$, we will write G. We will take on this convention form here on out unless it's ambiguous. We will also assume the standard binary operation of addition for

$$\mathbb{Z}, \mathbb{Q}, \mathbb{R}, \mathbb{C}, \mathbb{Z}/n\mathbb{Z}$$

unless stated otherwise (ex, if you see $\mathbb{Z}$, assume it is $(\mathbb{Z}, +)$). If we want the multiplicative structure of these numbers, we will add a $\times$ in the superscript and implicitly omit the zero:

$$\mathbb{Z}^\times, \mathbb{Q}^\times, \mathbb{R}^\times, \mathbb{C}^\times (\mathbb{Z}/n\mathbb{Z})^\times$$

These sets are $(\mathbb{Z} - \{0\}, \times)$ [1], $(\mathbb{Q} - \{0\}, \times)$, $(\mathbb{R} - \{0\}, \times)$, and so forth. The sets $\mathbb{R}^+$ and $\mathbb{Q}^+$ shall represent the collection of positive real numbers and positive rational number with the usual multiplication. Furthermore, since we are always working with binary operations, the word "binary" is often omitted for convenience.

1.1.6 Note In many of the previous examples, there is some more structure usually associated with those symbols. For example, in $\mathbb{N}$, $\mathbb{Z}$, $\mathbb{Q}$ and $\mathbb{R}$, there is a notion of some numbers being bigger than others, that is, $1 < 2$, or $n < n + 1$. These are *not* part of the definition of a group, and so cannot be used when proving general statements about groups! It will be very common that you work with groups with *more* structure than their group structure, so be quite careful that the examples you hold when doing exercises *only* represent the structure you want to work with at that moment

You might have noticed that some of the underlying sets of the above groups are subsets of each other: $\mathbb{Z} \subseteq \mathbb{Q} \subseteq \mathbb{R} \subseteq \mathbb{C}$. Does this imply that there is a relation between their group structure? For example does the usual addition in $\mathbb{Z}$ works as in $\mathbb{Q}$ with usual addition? If you think about this particular example, you will see that the answer is yes. But being a subset doesn't always means you will have the same (if any) group structure: $\mathbb{N} \subseteq \mathbb{Z}$, but $\mathbb{N}$ is not even a group! On the other hand, if we take $2\mathbb{Z} \subseteq \mathbb{Z}$, and give $2\mathbb{Z}$ the same operation as $\mathbb{Z}$ (that is $(2\mathbb{Z}, +)$ is our group), then $(2\mathbb{Z}, +)$ acts exactly the same way as $\mathbb{Z}$, with just fewer elements. So, we will give a name to subsets which inherit group properties of their parent group:

Definition 1.1.7: Subgroup

Let G be a group and $H \subseteq G$. Then H is a subgroup of G if it is still a group under the same operation as G. We denote the subgroup by $H \leqslant G$ [a]

[a] In some textbooks, the symbol for subgroup is $H \preceq G$

[1] Note that $\mathbb{Z}^\times$ is not a group under $\times$ as we have pointed out earlier. However, the binary operations $\times$ is still defined on this set

You might have flinched to it saying "the same operation", since it was explicitly mentioned in the definition that for a group G, the operation is $G \times G \to G$, so H cannot have the same operation since the domain and co-domain are different. This is a common convention in algebra for structures which are similar: if we restrict the operation to only the elements of H, then $(H, *|_H)$ should be a group. In particular, if $* : G \times G \to G$ is the binary operation on G, then we say we *restrict* the binary operation to H if we can define $*|_H : H \times H \to H$, where for any two elements $h_1, h_2 \in H$ $*|_H (h_1, h_2) = *(h_1, h_2)$. If $(H, *|_H)$ is a group, we say it's a subgroup of $(G, *)$. In this way, we say that H has "the same" binary operation as G.

Example 1.1.8: Subgroups

1. Take $2\mathbb{Z} \subseteq \mathbb{Z}$, the set of all even integers. The identity is there: $0 \in 2\mathbb{Z}$. If you add two even integers, you get an even integer $(2x + 2y = 2(x + y))$ [a]. Furthermore, if $2x \in 2\mathbb{Z}$, then there exists $-2x \in 2\mathbb{Z}$ such that $2x - 2x = 0$, meaning every element has an inverse. Finally, associativity is implied by associativity in $\mathbb{Z}$: for any $2x, 2y, 2z \in 2\mathbb{Z}$, we have that $2x, 2y, 2z \in \mathbb{Z}$, so $2x + (2y + 2z) = (2x + 2y) + 2z$. Thus $2\mathbb{Z} \leqslant \mathbb{Z}$
2. Right before the previous definition, it was mentioned that $\mathbb{Z} \subseteq \mathbb{Q}$ is an example of a subgroup (i.e. $\mathbb{Z} \leqslant \mathbb{Q}$). This is an exercise worth doing to get comfortable with the concept. Mix an match with other types of numbers to get more practice.
3. Let $\mathbb{Z}^\times \subseteq \mathbb{Q}^\times$ (i.e. $Z - \{0\} \subseteq \mathbb{Q} - \{0\}$). Is $\mathbb{Z}^\times$ a subgroup?
4. Let $H \leqslant G$ and $K \leqslant H$. Is $K \leqslant G$?
5. Here is an exercise in understanding the nuance of binary operations: Is $\mathbb{Z}/5\mathbb{Z} \leqslant \mathbb{Z}$? answer: [b]

[a] Note here how I *did* use extra properties that are not necessarily part of a group (I factored the two out). This is fine, since we are working with a *particular* example, this would not be a proof we can do on general groups

[b] It is no, since the binary operation does not "act" the same way $(3 + 3 = 1)$ in $\mathbb{Z}/5\mathbb{Z}$ but $3 + 3 = 6$ in $\mathbb{Z}$

Groups are missing one key property that numbers usually have: commutativity. Though we already talked about them in the definition of a group, I will add it here to emphasize their importance:

Definition 1.1.9: Abelian Group

Given a group G, if $ab = ba$ for all $a, b \in G$, we call G a *commutative* or *abelian* group

Example 1.1.10: Abelian Groups

$\mathbb{Z}, \mathbb{Q}, \mathbb{R}, \mathbb{C}, \mathbb{Z}/n\mathbb{Z}$ are all Abelian Groups [a]. So are $\mathbb{Q}^\times, \mathbb{R}^\times, \mathbb{C}^\times$. In fact, all examples in the example 1.1.5 were abelian groups with the exception of the bijections on a set with at least three elements. An important non-commutative group will be the Dihedral group (definition 1.2.28)

[a] This is an example where the binary operation is implied. The binary operations shown in example 1.1.5 are the standard binary operations for these sets

As mentioned earlier, being abelian/commutative is insanely powerful. Of all the properties the reader will cover in basic group theory, a lot of them will be properties a group being "almost" or "kind of" abelian. In this text, we will come across many definitions and sections that are centered

around how close they are to being abelian [2]

The reason we relate a lot of conditions to commutativity is because Abelian Groups behave in much more predictable ways as compared to general groups, as shall be developed. The power of commutativity permeates a lot of algebraic structures. Because of this, we often split up domains in mathematics in "commutative" and "not-commutative". As an example of this split, some mathematicians like to reference the set of Abelian groups as **Ab** and the set of all groups as **Group** to show how different a general group versus a general abelian group is [3]. There are entire areas of mathematics where the problem has been solved in the "abelian case", while the "nonabelian case" is an active area of research[4].

For the visual reader, the following is a helpful tool to understand the group operation:

Definition 1.1.11: Cayley Table (Multiplication Table)

Let G be a finite group (that is, a group on a finite set). Label the elements of G as $\{g_1, g_2, ..., g_n\}$, where g_1 represents the identity.

Then *Cayley table* or *multiplication table* of G is the $n \times n$ matrix whose i, j entry is the group element $g_i g_j$.

I personally prefer the term Cayley table since not all binary operations are called "multiplication". It can be confusing to do a multiplication table for $(G, +)$

Example 1.1.12: Cayley Table

Take $G = \mathbb{Z}/4\mathbb{Z}$. Then the Cayley tables for addition and multiplication are:

$+$	0	1	2	3
0	0	1	2	3
1	1	2	3	4
2	2	3	4	0
3	3	4	0	1

$\times$	0	1	2	3
0	0	0	0	0
1	0	1	2	3
2	0	2	0	2
3	0	3	2	1

This can be done for any finite group, and sometimes gives valuable insights instantly. For example, notice that in the Cayley table for multiplication, for row 0, 1, and 3, they contain every element of $\mathbb{Z}/4\mathbb{Z}$, yet the row for 2 does not. Notice further that both tables are symmetrical, that is, position ij is equal to position ji.

In general, it can be quite cumbersome to write out an entire Cayley table, especially when the order the group will be higher than 4, if not infinite. So throughout Part I, we develop algebraic tools to deduce information about groups.

[2] for reference, see definition 3.1.9, definition 2.2.4, and sections 5.3 and 6.1

[3] There are some technicalities here in saying it's the *set* of all groups, due to Russel's paradox. We should instead say the *class* of all groups. This is addressed in section 61.1.

[4] There are a huge number of such examples, but to point out one relevant to algebra: class field theory completely classifies abelian extension of fields, while the nonabelian counterpart is a very deeply researched problem and is a special case of the *Langland's Program*. Another example that creates a split between the commutative and non-commutative case is within the study of algebraic geometry where the structures are built out of commutative rings, while the non commutative case would require more machinery from analysis.

1.1.1 Consequences of Group Axioms

With the definition of groups down, we can deduce a lot of direct consequences from the axioms. One thing common with mathematical constructs is an abundance of propositions. These are vital to be able to prove by oneself, and once comfortable should be treated as knowledge as important as the definition of a group. I would even go so far as to say that not knowing the properties of groups means you do not really know what a group is. For example, do you really know what a frying pan is/can do if you have not cooked with it before? Do you know the in's an out of what utensils can you use to not damage it, or what type of food will stick to it or not? You will only know once you have practiced using it.

I would strongly suggest that the reader attempts proving *all* of these propositions before looking at the proof, especially if this is the first time the reader has seen algebraic structures! It is crucial moving forward that these properties are second nature, since everything we build form here on out will constantly be relying on these properties.

The first thing to point out is that if we have $a * e = a$, we can deduce $e * a = a$.

Proposition 1.1.13: one-sided identity implies two-sided identity

Let G be a group and e an identity. If $a * e = a$ then $e * a = a$ (or vice-versa)

***Proof*:**
The identity axiom gives $e * a = a$ for every $a \in G$, so it suffices to prove that $a * e = a$ also holds for every $a \in G$. From the axioms,

$$\begin{aligned} a * e &= a * (a^{-1} * a) && \text{inverse definition (axiom 3)} \\ &= (a * a^{-1}) * a && \text{associativity (axiom 1)} \\ &= e * a && \text{inverse definition (axiom 3)} \\ &= a && \text{left identity (axiom 2)} \end{aligned}$$

as we sought to show.

Some author's put $a * e = e * a = a$ as a definition. This is a matter of preference: since it's a direct consequence of the axioms, it can be put as one of the fundamental rules a group has to follow without worry of constraining the definition. Some authors disagree with this, and would rather keep the definition of group in fuller generality. This preference for generality is a balancing act: the more general you go, the more "complicated" the concept gets. However, if done right, you gain a more "nuanced" perspective with generality. In this book, the more general idea was taken, since some proofs already covered earlier fail for more subtle reasons. For example, $(\mathbb{Z}, -)$ fails to be a group because of associativity, however if we put $a * e = e * a = a$ in the definition, we can also say it fails because $-a = 0 - a \neq a - 0 = a$ (for $a \neq 0$). However, as we have seen in the above proof, this fact *relies on associativity*, and therefore is hiding the fact that $(\mathbb{Z}, -)$ is still failing to be a group because of associativity.

Corollary 1.1.14: one-sided Inverse Implies two-sided Inverse

Let a, a^{-1} be elements of the group G and let e be the identity of G. Then $a * a^{-1} = e$ if and only if $a^{-1} * a = e$

***Proof*:**
Let's say $b = a^{-1}$ so that $a * b = e$. Then $b = b * e = b * a * b$. Multiplying both sies by b^{-1}, we get

$$\begin{aligned} e &= b * b^{-1} \\ &= (b * a * b) * b^{-1} \\ &= b * a * (b * b^{-1}) \\ &= b * a \\ &= a^{-1} * a && b = a^{-1} \end{aligned}$$

as we sought to show.

Proposition 1.1.15: Basic properties of Group elements

1. The identity of G is unique. Furthermore, if for some $x \in G$, $f * x = x$, then is equal to the identity
2. For each $a, \in G$, a^{-1} is uniquely determined
3. $(a^{-1})^{-1} = a$, for all $a \in G$
4. $(a * b)^{-1} = (b^{-1}) * (a^{-1})$.
5. generalized associative law (induction on associativity).

***Proof*:**
Again, I highly encourage you to attempt all of these before looking at these answers!!

1. Let $e \in G$ be the identity, that is, for all $x \in g$ $e * x = x$. Let's say there is another element $f \in G$ that is also the identity. Then

   $$\begin{aligned} e &= e * f && \text{definition of identity} \\ &= f && \text{definition of identity} \end{aligned}$$

   therefore, $e = f$, showing that e is unique.

   Furthermore, if there was an f such that for only *some* $x \in G$, $f * x = x$, then

   $$\begin{aligned} (f * x) * x^{-1} &= (x * x^{-1}) = e \\ \Leftrightarrow f * (x * x^{-1}) &= e \\ \Leftrightarrow f &= e \end{aligned}$$

thus, there cannot be a "partial" identity.

2. Let $a \in G$, and suppose $b, c \in G$ are both inverses of a, that is, $a * b = b * a = e$ and $a * c = c * a = e$. Then

$$\begin{aligned} b &= b * e && \text{proposition 1.1.13} \\ &= b * (a * c) && c \text{ is an inverse of } a \\ &= (b * a) * c && \text{associativity} \\ &= e * c && b \text{ is an inverse of } a \\ &= c && \text{definition of identity} \end{aligned}$$

   Thus $b = c$. Any two inverses of a are equal, so a^{-1} is uniquely determined.

3. Let $a \in G$. By the definition of the inverse, $a^{-1} * a = e$ and $a * a^{-1} = e$. These two equations state exactly that a is an inverse of a^{-1}. By part 2, the inverse of a^{-1} is unique, so $(a^{-1})^{-1} = a$.

4. Let $a, b \in G$. Then

$$\begin{aligned} (a * b) * ((b^{-1}) * (a^{-1})) &= ((a * b) * b^{-1}) * a^{-1} && \text{associativity} \\ &= (a * (b * b^{-1})) * a^{-1} && \text{associativity} \\ &= (a * e) * a^{-1} && \text{inverse definition} \\ &= a * a^{-1} && \text{proposition 1.1.13} \\ &= e && \text{inverse definition} \end{aligned}$$

   By corollary 1.1.14, we also have $((b^{-1}) * (a^{-1})) * (a * b) = e$. Thus $(b^{-1}) * (a^{-1})$ is an inverse of $a * b$. By part 2, it is the only one, so $(a * b)^{-1} = (b^{-1}) * (a^{-1})$.

5. The precise claim is that for any $n \geq 1$ and any $a_1, a_2, \ldots, a_n \in G$, all ways of inserting parentheses into the product $a_1 * a_2 * \cdots * a_n$ (keeping the order of the factors) produce the same element of G. Call a product *left-normed* if it is bracketed as $(\cdots((a_1 * a_2) * a_3)\cdots) * a_n$. We prove, by strong induction on n, that every bracketing of $a_1 * a_2 * \cdots * a_n$ equals the left-normed product of $a_1, \ldots, a_n$. For $n = 1$ and $n = 2$ there is only one bracketing, so there is nothing to prove.

   Now let $n \geq 3$, and consider any bracketing P of $a_1 * \cdots * a_n$. The outermost multiplication of P splits it as $P = Q * R$, where Q is a bracketing of $a_1 * \cdots * a_k$ and R is a bracketing of $a_{k+1} * \cdots * a_n$, for some $1 \leq k \leq n - 1$. If $k = n - 1$, then $R = a_n$, and the induction hypothesis (applied to the $n - 1$ factors of Q) says Q equals the left-normed product of $a_1, \ldots, a_{n-1}$. Hence $P = Q * a_n$ is the left-normed product of $a_1, \ldots, a_n$. If $k < n - 1$, then R has at least two factors, so by the induction hypothesis R equals the left-normed product of $a_{k+1}, \ldots, a_n$, which by its bracketing has the form $S * a_n$, where S is the left-normed product of $a_{k+1}, \ldots, a_{n-1}$. By the associativity axiom,

$$P = Q * (S * a_n) = (Q * S) * a_n$$

   Now $Q * S$ is a bracketing of the $n - 1$ factors $a_1 * \cdots * a_{n-1}$, so by the induction hypothesis it equals the left-normed product of $a_1, \ldots, a_{n-1}$. Thus $P = (Q * S) * a_n$ is the left-normed product of $a_1, \ldots, a_n$, completing the induction. Any two bracketings of $a_1 * a_2 * \cdots * a_n$ therefore both equal the left-normed product of $a_1, \ldots, a_n$, and hence equal each other.

With these in mind, here's some standard notation to simplify writing: One usually write the operation $*$ as $\cdot$ to represent an abstract binary operation, unless otherwise specified. If clear from context, we write $a \cdot b$ as ab. We usually also denote the identity e as 1. We will also implement the following short hand: [5]

$$\underbrace{xxxxxx\cdots x}_{n \text{ times}} = x^n, \qquad \underbrace{x^{-1}x^{-1}\cdots x^{-1}}_{n \text{ times}} = x^{-n}, \qquad x^0 = 1$$

Do not forget that last one is the identity of G. If we are using a group where specific notation is already defined (like with the $+$ operation), we can use it's specific convention. So $a+a+\cdots+a = na$, $-a+-a+\cdots+-a = -na$, and $0a = 0$ [6]. Furthermore, $a+(-a)$ is sometimes shorthanded to $a-a$.

The next result we will cover let's us generalize our intuition of pre-abstract algebra. When learning algebra for the first time, you have probably encountered equations of the form:

$$3x = 5$$

and where asked to solve for x. The way you would do this is by dividing both sides by 3 to get the equation:

$$x = \frac{5}{3}$$

This might seem like the obvious thing to do in any situation. However, you cannot always cancel out a number on one side and get a unique result! Take a moment to review your proof of uniqueness of identity and uniqueness of the inverse, and consider this thought experiment:

1.1.16 Thought Experiment Let's take a set for which every element does *not* have an inverse. Recall (or prove) that $\mathbb{Z}/6\mathbb{Z}$ is not a group under multiplication. In particular, $[2]$ has no multiplicative inverse. Since $[2][2] = [0]$, then:

$$[4] = [2][2] = [2][5] = [10] = [4]$$

However, $[2] \neq [5]$. In other words, I could not "cancel" out the $[2]$ on the left side, i.e. for the equation $[2]x = [4]$ we get $x = [2]$ or $x = [5]$.

This cancelling out of a number on the left [or right] side is something you probably took for granted, but it's the consequence of the fact that every number in a group must have a unique inverse! This fact is proven in the next proposition:

Proposition 1.1.17: Cancellation Property: Unique solution to monomials

Let G be a group and let $a, b \in G$. The equation $ax = b$ and $ya = b$ have unique solutions for $x, y \in G$. In particular, the left and right cancellation properties hold in G:

1. If $au = av$ then $u = v$
2. If $ub = vb$ then $u = v$

[5] $x^0 = 1$ since $x^0 = x^{1-1} = x^1x^{-1} = xx^{-1} = 1$

[6] If you have covered rings, this might look familiar to the first property in proposition 9.1.9. It is quite similar in that this shorthand secretly is a ring-action on the group (but not a $\mathbb{Z}$-module since G is not necessarily abelian). This means that the intuition behind the notation is similar to the proof in proposition 9.1.9: $0a = (1-1)a = a - a = 0$

Sometimes, this proposition is called the *Cancellation Law*

***Proof*:**
Simply use uniqueness of inverse. The point of this theorem is that if $ab = e$, for any element $a \in G$ and some element $b \in G$, then $b = a^{-1}$.

This proposition is very powerful, it means we can bring in our elementary algebra knowledge. In this sense, groups are the structure on which we generalize the idea of doing elementary algebra on. They are limited in that they only allow one operation: you probably have worked with equation with both addition and multiplication (ex. $3x^2 - 5 = 0$). We will work with such equations with 2 binary operations once we study *rings* (see Part II)

With these properties, I will take a moment to explain the power of associativity and commutativity. In all type of numbers systems we saw $(\mathbb{N}, \mathbb{Z}, \mathbb{Q}, \mathbb{R})$, for any two numbers a and b:

$$aaabbbbaaabaaaabbbbbaa$$

is unambiguous. and so, we can write

$$a^3b^3a^3ba^4b^5a^2$$

Which is really powerful. If you did not have associativity, then $aaabbbbaaabaaaabbbbbaa$ would be ambiguous, since it's possible that

$$(aaabbbbaaabaaaabbbbba)a \neq a(aabbbbaaabaaaabbbbbaa)$$

So every pair of elements would have to be bracketed since

$$abc$$

would be ambiguous [7] since it's possible that

$$(ab)c \neq a(bc)$$

and so you would be forced to have an expression like

$$((((aa)b)((bb)(ba)))(((((aa)(ba))a))((a(a(bb)))((b(bb))a))))a$$

with no simpler way of representing the expression, quite a monstrosity. There are more than $2^{22} = 4'194'304$ ways of bracketing this!! The idea is that associativity means that given a sequence of operations that must be performed in a certain order:

$$a_1 * a_2 * a_3 * \cdots * a_n$$

We are allowed to "break up" the problem into smaller problems that can be grouped and operated and then recombined in the right order. For example if we must perform 4 actions in order:

$$a_1 * a_2 * a_3 * a_4$$

Then associativity means that we could have considered $a_3 * a_4 = b_2$ as a new combined actions and $a_1 * a_2 = b_1$ also as a combined action:

$$b_1 * b_2$$

[7] like $\mathbb{R}^3$ with the cross product

Or we could have taken $a_1 * a_2 = b_1$ and then combine it with the action of a_3, $b_1 * a_3 = b_3$ and then with a_4 and get the same result:

$$a_1 * a_2 * a_3 * a_4 = b_1 * b_2 = b_3 * a_4$$

This can also be thought of as "pre-combining" the steps before performing the result in the same order, which if the operation is associative would give you the same result.

Example 1.1.18: Associativity and The Lack of It

1. An example of real world phenomena where this is not applicable rock-paper-scissors. Let's says the (commutative) binary operation takes in two choices and gives the winner (and if the two input are the same return the input). Then:

   $$(\text{rock} * \text{paper}) * \text{scissors} = \text{paper} * \text{rock} = \text{paper} \neq \text{rock} * \text{scissors} = \text{rock} * (\text{paper} * \text{scissors})$$

2. *Divide and Conquer (Parallel Computing)*: Associativity is key in parallel computing. If a sequence of operations is associative, we do not have to wait for a single processor to calculate from left to right:

   $$((((a_1 * a_2) * a_3) * a_4) \dots)$$

   Instead, we can dispatch the problem locally to different processors:

   (a) Processor 1 solves $a_1 * a_2$ locally.

   (b) Processor 2 solves $a_3 * a_4$ locally.

   They then combine their local results[a]. Such "reduction" operations must be associative precisely so they can be solved locally on separate servers and combined later without changing the final outcome.

3. Exponentiation is *not* associative: $(a^b)^c$ is not in general equal to $(a)^{b^c}$.

4. The averaging operation is not associative

5. Convince your self that cooking instruction are usually not associative.

[a] Frameworks like Google's MapReduce rely entirely on this

Since functions are associative, most algebraic structures in mathematics will be associative, however there are entire domain of study which concentrates on a non-associative structure [8] or drop the condition of associativity[9]. Structures without associativity are outside the scope of this book[10]. As a consequence of associativity, we can unambiguously write:

$$x^{a+b} = x^{b+a}$$


since the order of multiplication does not effect the final result. We can also visualize associativity through the use of directed graphs. If we take abc, then we can visualize which tuple of elements we

[8] the most famous of is called Lie Algebra, with something called the Jacobi Identity replacing associativity. Another is the logical implications: $(a \to b) \to c$ does not always give the same truth value as $a \to (b \to c)$


[9] Three such examples are *loops*, *Quasigroups*, and *magmas*

[10] Nonassociative algebras are treated in [88], and quasigroups and loops in [94].

choose to multiply first:



this is more clear if we have 4 elements, any way we choose to bracket our elements leads to the same result:



Note that adding commutativity makes this even more powerful, since

$$aba = aab = a^2b$$

and so we can group all like terms together, and write

$$aaabbbbaaabaaaabbbbbaa \qquad \text{as} \qquad aaaaaaaaaaaabbbbbbbbbb$$

and collapse it to:

$$a^{12}b^{10}$$

That is, the only information we need is the number of times we multiply by a and b, with no regard to the order we multiply them! This added axiom is so powerful that it will turn out that it will constrain the number of possible (finite and finitely generated) groups, which are relatively few[11] (see section 5.1.1)

Exercise 1.1.1

1. Let $G = \mathbb{Q}$, and the binary operation be average : $\mathbb{Q} \times \mathbb{Q} \to \mathbb{Q}$, where average$(x, y) = \frac{x+y}{2}$. Is $(G, \text{average})$ a group? What if $G = \mathbb{Z}/4\mathbb{Z}$?
2. Can a group structure be put on $\emptyset$ (i.e., can there exist a function $* : \emptyset \times \emptyset \to \emptyset$ such that $(\emptyset, *)$ is a group?)

[11] Finitely generated groups are defined in section 2.3, and the result is theorem 5.1.6. As of writing this book, the project of classifying all abelian groups is still a very unsolved problem

3. (If you know some complex analysis) In example 1.1.5(11), it was stated that

$$G = \{z \in \mathbb{C} \mid |z| = 1\}$$

is a group. Prove that G is indeed a group.

4. Let $\text{Bij}(X)$ be the set of all bijections from X to X. Prove that $\text{Bij}(X)$ is a group. In section 1.2.2, we will relabel this as $\text{Sym}(X)$.

5. Show that if G is abelian, then $(ab)^{-1} = a^{-1}b^{-1}$ for all $a, b \in G$.

1.2 Examples of Groups

Now that we covered the basics, it is important to build up a family of common groups to get familiar with the how to recognize groups, and to feel very comfortable manipulating groups. We already showed how many previous mathematical structures were already groups (the canonical examples being $\mathbb{Z}, \mathbb{Q}, \mathbb{R}, \mathbb{C}$). We will now define new groups to show further what is possible with the definition of the group, and to build-up a repertoire of more elaborate examples.

1.2.1 Integers Modulo n and Cyclic Groups

Recall in section 0.2.2 that $\mathbb{Z}/n\mathbb{Z}$ is a collection of equivalences classes satisfying $a \sim_n b$ if and only if there exists a $k \in \mathbb{Z}$ st $a - b = kn$. Given that $\mathbb{Z}$ is a group and the results proposition 0.2.16, it is reasonable to think that it may form a group:

Proposition 1.2.1: Modular Arithmetic Groups

Let $\mathbb{Z}/n\mathbb{Z}$ be the integesr modulo n. Then $\mathbb{Z}/n\mathbb{Z}$ forms a group under modular addition:

$$(a \bmod n) +_n (b \bmod n) = (a + b) \bmod n$$

with the binary operation denoted as $+_n$, or if the context permits simply as $+$

In almost all cases, the notion $+$ shall be used, for it will be clear from context that the elements will be part of a certain set of modular integers.

***Proof*:**

(Well-defined) By proposition 0.2.16(1), the operation is well-defined

(Idenitty) For any n, there is always $\overline{0}_n \in \mathbb{Z}/n\mathbb{Z}$ for $n - n = 0$. Then for any $\overline{a}_n \in \mathbb{Z}/n\mathbb{Z}$:

$$\overline{0}_n + \overline{a})n = \overline{0 + a}_n$$

Then notice that

$$a - (0 + a) = 0 = kn \qquad (\text{with } k = 0)$$

Thus, $\overline{0 + a}_n = \overline{a}_n$, and so $\overline{0}_n$ is the identity for any $n \in \mathbb{N}_{>0}$

(Inverse) For any $\overline{a}_n \in \mathbb{Z}/n\mathbb{Z}$, pick $\overline{-a}_n$ (i.e., the equivalence class that can be represented by $-a$). Then:

$$(a + -a) - 0 = 0$$

implying that $\overline{a}_n = \overline{-a}_n = \overline{a + (-a)}_n = \overline{0}_n$, showing that $\overline{a}_n$ is indeed the inverse. Usually, a representative between $0 \leq t \leq n-1$ so that $\overline{-a}_n = \overline{t}_n$.

(Associaivity) let $\overline{a}_n, \overline{b}_n, \overline{b}_n \in \mathbb{Z}/n\mathbb{Z}$. We want to show that

$$(\overline{a}_n + \overline{b}_n) + \overline{c}_n = \overline{a}_n + (\overline{b}_n + \overline{c}_n)$$

expanding the definition of the binary operation, we get:

$$\overline{(a+b)+c}_n = \overline{a+(b+c)}_n$$

In particular, we want to verify that:

$$[(a+b)+c] - [a+(b+c)] = kn$$

which by the associativity of the integers, we get that their difference is 0, which implies both sides are equal, completing the proof.

Definition 1.2.2: Integers Modulo n

The set $\mathbb{Z}/n\mathbb{Z}$ forms a group under modulo addition called *integers modulo n*.

Hence, for each $n \in \mathbb{N}_{>0}$, there is a group with with n elements. It has yet to be explored whether the modulo multiplication is a viable binary operation, namely if:

$$(a \bmod n) \cdot (b \bmod n) = (ab) \bmod n \tag{1.1}$$

can form a binary operation. Some more care must be put in:

Example 1.2.3: Not Always Group

Take $n = 4$. The reader should verify that $\overline{1}_4$ is the identity given the binary operation defined in equation (1.1), and by proposition 1.1.15(1) it is unique. However, notice that $\overline{2}_4$ has *no* multiplicative inverse:

$$\overline{0 \cdot 2}_4 = \overline{0}_4 \qquad \overline{1 \cdot 2}_4 = \overline{2}_4 \qquad \overline{2 \cdot 2}_4 = \overline{0}_4 \qquad \overline{3 \cdot 2}_4 = \overline{2}_4$$

Hence, $(\mathbb{Z}/n\mathbb{Z}, \cdot_4)$ is *not* a group. However, if we pick $n = 3$, notice that this forms a group!

The reader may have observed that 3 is a prime and may wonder if is the key difference. This is in fact close: the important part is to choose all elements that are *coprime* with n:

Definition 1.2.4: Euler Totient

Define $\varphi\colon \mathbb{N}_{>0} \to \mathbb{N}$ by

$$\varphi(n) := \#\left\{k \in \mathbb{N} \mid 1 \leq k \leq n \text{ and } \gcd(n,k) = 1\right\}$$

that is, $\varphi(n)$ counts the integers between 1 and n that are coprime to n.

For example, $\varphi(1) = 1$, $\varphi(4) = 2$ (counting 1 and 3), and $\varphi(p) = p - 1$ for a prime p, since the only positive divisors of p are 1 and p. The notation φ is often re-used and so should not be considered a "universal" symbol for the Euler Totient.

Definition 1.2.5: Integer Modulo n With Multiplication

Let $n \in \mathbb{N}_{>0}$ and let $\mathbb{Z}/n\mathbb{Z}$ be the integers modulo n. Take $(\mathbb{Z}/n\mathbb{Z})^\times \subseteq \mathbb{Z}/n\mathbb{Z}$ defined to be

$$(\mathbb{Z}/n\mathbb{Z})^\times = \left\{\bar{t}_n \in \mathbb{Z}/n\mathbb{Z} \;\middle|\; 1 \leq t \leq n \text{ and } \gcd(t,n) = 1\right\}$$

Define the binary operation to be:

$$(a \bmod n) \cdot (b \bmod n) = (ab) \bmod n \tag{1.2}$$

Then $(\mathbb{Z}/n\mathbb{Z})^\times$ is an abelian group with identity $\overline{1}_n$ and with $\varphi(n)$ elements. A class $\overline{a}_n$ lies in $(\mathbb{Z}/n\mathbb{Z})^\times$ exactly when $ax + ny = 1$ for some $x, y \in \mathbb{Z}$, and for $a \neq 0$ this holds exactly when $\gcd(a,n) = 1$.

***Proof*:**
Every integer a can be written as $a = qn + r$ with $q \in \mathbb{Z}$ and $1 \leq r \leq n$, by dividing with remainder and replacing a remainder 0 by n. Two distinct integers r, r' in $\{1, \ldots, n\}$ are not congruent modulo n, since $0 < |r - r'| < n$. So each class has exactly one representative in $\{1, \ldots, n\}$, and $(\mathbb{Z}/n\mathbb{Z})^\times$ has $\varphi(n)$ elements by definition 1.2.4.

Let $a = qn + r$ with $1 \leq r \leq n$. If $\gcd(r,n) = 1$, Bézout's identity (theorem 0.2.10) gives $rx + ny = 1$ for some $x, y \in \mathbb{Z}$, and then $ax + n(y - qx) = 1$. Conversely, if $ax + ny = 1$, then $rx + n(y + qx) = 1$, and a positive common divisor of r and n divides 1, so $\gcd(r,n) = 1$. This proves the criterion for membership. For $a \neq 0$ the same two arguments, applied to a in place of r, show that $ax + ny = 1$ for some x, y exactly when $\gcd(a,n) = 1$.

The product of classes is well defined by proposition 0.2.16(3). It is associative and commutative, since $\overline{a}_n(\overline{b}_n\overline{c}_n) = \overline{a(bc)}_n = \overline{(ab)c}_n = (\overline{a}_n\overline{b}_n)\overline{c}_n$ and $\overline{ab}_n = \overline{ba}_n$. If $ax + ny = 1$ and $bx' + ny' = 1$, then multiplying the two equations gives

$$ab(xx') + n(axy' + bx'y + nyy') = 1$$

so $\overline{ab}_n \in (\mathbb{Z}/n\mathbb{Z})^\times$, and the operation restricts to $(\mathbb{Z}/n\mathbb{Z})^\times$. The class $\overline{1}_n$ lies in $(\mathbb{Z}/n\mathbb{Z})^\times$, as $1 \cdot 1 + n \cdot 0 = 1$, and it is an identity, since $\overline{1}_n\overline{a}_n = \overline{a}_n$. Finally, if $ax + ny = 1$, then the same equation read as $xa + ny = 1$ shows $\overline{x}_n \in (\mathbb{Z}/n\mathbb{Z})^\times$, and $\overline{a}_n\overline{x}_n = \overline{ax}_n = \overline{1 - ny}_n = \overline{1}_n$. So $(\mathbb{Z}/n\mathbb{Z})^\times$ is an abelian group with identity $\overline{1}_n$, as claimed.

Cyclic Subgroups

Each group G will have something similar to the integers modulo n, which is worth exploring:

Proposition 1.2.6: Creating a Cyclic Subgroup

Let G be a group and take any $x \in G$. Let $\langle x \rangle = \{x^a | a \in \mathbb{Z}\}$. Then $\langle x \rangle$ is a subgroup of G

***Proof*:**
I would recommend you do this as an exercise!

Let $\langle x \rangle = \{x^a | a \in \mathbb{Z}\}$. We will run through the group-axioms:

1. (associativity) Associativity come's from associativity in G. Let $r, s, t \in \langle x \rangle$, and consider
$$(r + s) + t$$
then since $r, s, t \in G$, and G is associative, we get that
$$(r + s) + t = r + (s + t)$$
and since $r, s, t \in \langle x \rangle$ were arbitrary 3 elements, this holds for any elements of $\langle x \rangle$, completing the proof
2. (identity) We need to show that in $\langle x \rangle$, there exists an element e such that $ex^a = x^a$. Since $0 \in \mathbb{Z}$, $x^0 = e \in \langle x \rangle$. And since for any element $y \in x$, $ey = y$, and every x^a is an element of G, $ex^a = x^a e = x^a$
3. (inverse). Let $y \in \langle x \rangle$ be an element of $\langle x \rangle$. Then by definition, for some $a \in \mathbb{Z}$, $y = x^a$. Then since $-a \in \mathbb{Z}$, $x^{-a} \in \langle x \rangle$, and as we have seen earlier:
$$x^a x^{-a} = x^{a-a} = x^0 = e$$
showing that x^a has an inverse for every a.

Thus, $\langle x \rangle$ is a group. Notice that the binary operation is identical to that of G restricted to $\langle x \rangle$, making $\langle x \rangle$ a subgroup of G, completing the proof.

Given any element $x \in G$, we can form a subgroup $\langle x \rangle \leqslant G$. The reason for it being called a cyclic subgroup comes when we consider a finite group G [12]

Example 1.2.7: Why is $\langle x \rangle$ called Cyclic?
Let G be a finite group (i.e. $|G| = n$ for some $n \in \mathbb{N}$), take $x \in G$ and consider $\langle x \rangle \leqslant G$.

1. Show that $\langle x \rangle$ is finite, that is, there is some $k \in \mathbb{N}$ such that $|\langle x \rangle| = k$
2. Show that for any x^{-a}, where $a \in \mathbb{N}$, there exists some number $b \in \mathbb{N}$ such that
$$x^{-a} = x^b$$

[12] More generally, subgroup $\langle x \rangle \leqslant G$ where $|\langle x \rangle|$ is finite

Conclude that $\langle x \rangle$ can be generated by raising number *only* to the power of positive number, i.e.

$$\{x^a \mid a \in \mathbb{Z}\} = \{x^a \mid a \in \mathbb{N}\}$$

3. show that if $|\langle x \rangle| = k$, then $x^k = e$. Use this fact to show that for any $x^a \in \langle x \rangle$, $a \leq k$.

With these facts, we can visualize a finite cyclic subgroup $\langle x \rangle$ using a graph. Let's say 1 is the identity. If we multiply 1 by x $(1 \cdot x)$, we get x. We can represent this visually with

$$1 \xrightarrow{\cdot x} x$$


if we multiply x by x, we get

$$1 \xrightarrow{\cdot x} x \xrightarrow{\cdot x} x^2$$


continuing in this fashion, we will make long "chain":

$$1 \xrightarrow{\cdot x} x \xrightarrow{\cdot x} x^2 \xrightarrow{\cdot x} x^3 \xrightarrow{\cdot x} \cdots$$

until we reach 1, at which point we can circle back to it in the graph:



which more conveniently can be written as



producing us a cycle!

Since every element can form a cyclic group, and their structure is characterized by the cardinality of $\langle x \rangle$, we will give a special name to this cardinality:

Definition 1.2.8: Order of an element

For a group G and $x \in G$, define the *order of* x to be the smallest positive integer n such that $x^n = 1$, and denote this integer by $|x|$. In this use, x is said to be of order n. If no positive power of x is the identity, the order of x is defined to be infinity and x is said to be of infinite order
Equivalently, we can also say $|x| = |\langle x \rangle|$, that is, the order of x is the order of the group generated by x

Another word for element with finite order is *torsion elements*. Elements that are not torsion elements

(i.e. with infinite order) are called *torsion-free elements*.

Example 1.2.9: Order of Elements

1. Every element of $\mathbb{Z}, \mathbb{Q}, \mathbb{R}, \mathbb{C}$ under $+$ has infinite except 0. Is the same true for $\mathbb{R}^\times$ (i.e. $\mathbb{R} - \{0\}$ (answer: [a]) Note the identity always has order 1.
2. Can you find the order of the elements in $\mathbb{Z}/p\mathbb{Z}$ for prime p? What if p is not prime? What are the order of the elements of $\mathbb{Z}/60\mathbb{Z}$?

[a] no, take $-1 \in \mathbb{R}^\times$

1.2.10 Note The order of an element depends on *both* the set and the binary operation: -1 has infinite order in $(\mathbb{Z}, +)$ and order 2 in $(\mathbb{R}^\times, \cdot)$ (example 1.2.9).
Also, the word *order* is sometimes used to mean the cardinality of the group.

Every finitely generated abelian group is a direct product of finitely many copies of $\mathbb{Z}$ and of groups $\mathbb{Z}/n\mathbb{Z}$ (theorem 5.1.6).

1.2.2 Symmetric Groups

Let X be any set. As covered in the preliminary chapter, a bijective function $f : X \to X$ always has a (two-sided) inverse function[13], say f^{-1}. Furthermore, function composition is associative, and since the domain and codomain match, the composition of two bijective functions $f, g : X \to X$ gives another bijective function $g \circ f : X \to X$ (as the reader ought to check if they are not convinced). The final property to check for the collection of bijective functions on a set X to form a group is whether there exists a bijective function $\mathrm{id}_X : X \to X$ such that for all bijective functions $f : X \to X$, $\mathrm{id}_X \circ f = f \circ \mathrm{id}_X = f$. The reader should take a moment to think what this function

1.2.11 Moment Taking a moment

The reader may have noticed that this function arises naturally by taking $f \circ f^{-1}$, namely it's the function defined to be $s \mapsto s$. Thus, given any set X, there is a natural group structure on the collection of bijections on X. This set is given a name:

Definition 1.2.12: Symmetric Group

Let X be any set. Then then:

$$S_X := \{f : X \to X \mid f \text{ is a bijection}\}$$

is called the *symmetric group* or *permutation group* of X [with respect to composition $\circ$]. If the cardinality of X is finite, say $|X| = n$, then we denote S_X by S_n.

Other common notations for the symmetric group are:

$$\mathrm{Bij}(A) \qquad \mathrm{Sym}(A) \qquad \mathrm{Aut}_{\mathbf{Set}}(A)$$

[13] This in fact characterizes bijective functions

If X is finite, then the bijections S_n are determined only by the place to which elements map to and not by any property of the elements, making the bijections only dependent on the number of elements and hence the S_n notation being unambiguous. For this reason, it is often assumed that the set over which the bijections are being taken is given by[14]:

$$\{1, 2, ..., n\}$$

A mention on notation is in order: for $f, g \in S_X$, the product fg in S_X is the composite $f \circ g$, so

$$(fg)(x) = f(g(x))$$

A product of permutations is therefore read from right to left: the rightmost factor acts first. This follows the convention for composing functions, which is older than the notation for group operations.

Symmetric groups are rather large. The number of bijections between finite sets grows:

$$|S_n| = n!$$

And hence even for $|X| = 100$, $|S_{100}| \gg 10^{100}$. For $n \in \{1, 2\}$, the bijections are rather simple, namely:

$$f_1 : \{1\} \to \{1\},\ f_1(1) = 1 \qquad g_1 : \{1, 2\} \to \{1, 2\},\ g_1 = \mathrm{id}_{\{1,2\}} \quad g_2(1) = 2\ g_2(2) = 1$$

For larger sets, it may get difficult to track the information a bijection holds. For example, if σ is a bijection on a set with 9 elements:

$$\{1, 2, 3, 4, 5, 6, 7, 8, 9\}$$

then we after the σ permutes, we might get

$$(\sigma(1), \sigma(2), \sigma(3)\sigma(4), \sigma(5), \sigma(6), \sigma(7), \sigma(8), \sigma(9)) = (2, 4, 1, 3, 7, 9, 8, 5, 6)$$

It is cumbersome to write-out the permutation by saying what each value of $\sigma \in S_n$ maps to. Instead, there is the following *matrix notation* as a shorthand:

$$\begin{pmatrix} 1 & 2 & 3 & 4 & 5 & 6 & 7 & 8 & 9 \\ 2 & 4 & 1 & 3 & 7 & 9 & 8 & 5 & 6 \end{pmatrix} \tag{1.3}$$

Representing f_1, g_1, g_2 in matrix notation, we would get:

$$\begin{pmatrix} 1 \\ 1 \end{pmatrix} \qquad \begin{pmatrix} 1 & 2 \\ 1 & 2 \end{pmatrix} \qquad \begin{pmatrix} 1 & 2 \\ 2 & 1 \end{pmatrix}$$

This is better notation, however we can do even better taking advantage of the fact that a bijection is one-to-one and onto. This implies that every element is only associated with one element and each element must be represented. This allows for the following "cycle" notation. Take equation (1.3), and notice that 1 maps to 2, which maps to 4, which maps to 3, which maps to 1:

$$1 \mapsto 2 \mapsto 4 \mapsto 3 \mapsto 1$$

Furthermore, 5 maps to 7, which maps to 8, which maps to 5:

$$5 \mapsto 8 \mapsto 7 \mapsto 5$$

[14]This set is also sometimes called the *indexing set* and represents labeling each element of some set of size n

Finally, 6 maps to 9, and 9 maps to 6:

$$6 \mapsto 9 \mapsto 6$$

This behavior can be represented via the following *cycle notation*:

$$(1\ 2\ 4\ 3)(5\ 8\ 7)(6\ 9)$$

Each "chain" in the above is called a *cycle*, and the combination of each is called the *cycle representaiton* If a cycle contains n elements, it is called an n-cycle. In the above example, there were not any elements that map to itself. If the element 10 is added to the set and we extend σ to $\overline{\sigma}$so that $\overline{\sigma}(10) = 10$, then we would write $(1\ 2\ 4\ 3)(5\ 8\ 7)(6\ 9)(10)$. By convention, any element that maps to itself is dropped in cycle notation, and hence $\overline{\sigma}$ would in cycle notation also be represented as:

$$(1\ 2\ 4\ 3)(5\ 8\ 7)(6\ 9)$$

Hence, there is an inherent ambiguity in cycle notation on the size of the domain/codomain, since any elements that map to themselves is not taken into accost, however it is usually the element that map to a non-trivial element that are of interest and hence this ambiguity does not effect the theory. Note that:

$$(1\,2\,3) = (3\,1\,2) = (2\,3\,1)$$

Since they all do the same permutation, you are just starting at different positions when converting to the cycle notation.

Example 1.2.13: Cycle Representation

1. Let τ be a bijective function on a set $\{1, 2, 3, 4, 5\}$ such that:

   $$(\tau(1), \tau(2), \tau(3), \tau(4), \tau(5)) = (5, 4, 3, 2, 1)$$

   What is the cycle notation for τ?

2. Cycles can be used to define permutations. Let $X = \{1, 2, 3, 4\}$. Find the bijection τ of X represented by the cycle representation:

   $$(1\ 2\ 3)(2\ 3\ 4)$$

   Notice that the two cycles overlap. To find τ, first find where 1 maps to under the right cycle, and then where the resulting element maps under the left cycle. In function notation, if f is the left cycle and g is the right cycle, then $\tau(1) = f(g(1))$. Proceed with this for all 4 elements. Remember that if an element is not in a cycle, then it is considered to map to itself.

3. Is it true that the functions represented by $(1\,2)(3\,4)$ and $(3\,4)(1\,2)$ are equal, that is:

   $$(1\ 2)(3\ 4) = (3\ 4)(1\ 2)$$

   More generally, do disjoint cycles commute?

To ensure the reader has the right calculation, here is an example of the product of two cycles as reference:

$$(1\ 4\ 5\ 2)(4\ 1\ 3) = (1\ 3\ 5\ 2)$$

Proposition 1.2.14: Disjoint Cycle Decomposition

Let $\sigma \in S_n$. For distinct $a_1, \ldots, a_m \in \{1, \ldots, n\}$ with $m \geq 2$, write $(a_1\ a_2\ \cdots\ a_m)$ for the m-cycle that sends a_i to a_{i+1} for $1 \leq i < m$, sends a_m to a_1, and fixes every other element. Its *support* is $\{a_1, \ldots, a_m\}$. Then σ is a product of cycles whose supports are pairwise disjoint, the empty product being id, and the set of cycles in such a product is determined by σ.

***Proof*:**

Step 1: the orbits of σ. Let $a \in \{1, \ldots, n\}$. The $n+1$ elements $a, \sigma(a), \ldots, \sigma^n(a)$ of an n-element set are not all distinct, so $\sigma^i(a) = \sigma^j(a)$ for some $0 \leq i < j \leq n$, and applying σ^{-i} gives $\sigma^{j-i}(a) = a$. Let m_a be the least positive integer with $\sigma^{m_a}(a) = a$, and put $O_a = \{a, \sigma(a), \ldots, \sigma^{m_a-1}(a)\}$. These m_a elements are distinct, since $\sigma^i(a) = \sigma^j(a)$ with $0 \leq i < j < m_a$ would give $\sigma^{j-i}(a) = a$ with $0 < j - i < m_a$. Because $\sigma^{m_a}(a) = a$, the set O_a contains $\sigma^k(a)$ for every $k \in \mathbb{Z}$, and $\sigma(O_a) = O_a$. If $b \in O_a$, say $b = \sigma^k(a)$, then $O_b \subseteq O_a$ and $a = \sigma^{-k}(b) \in O_b$, so $O_b = O_a$. Hence any two of the sets O_a are equal or disjoint, and together they cover $\{1, \ldots, n\}$. When $m_a \geq 2$, the cycle $c_a = (a\ \sigma(a)\ \cdots\ \sigma^{m_a-1}(a))$ has support O_a, agrees with σ on O_a and fixes every element outside O_a, so $c_b = c_a$ whenever $O_b = O_a$.

Step 2: existence. Let $O_1, \ldots, O_r$ be the distinct sets O_a with at least two elements, and $c_1, \ldots, c_r$ the corresponding cycles. We claim that $\sigma = c_1 c_2 \cdots c_r$. Let $x \in \{1, \ldots, n\}$. If x lies in no O_t, then $O_x = \{x\}$, so $\sigma(x) = x$, and every c_t fixes x. If $x \in O_t$, then every factor c_u with $u \neq t$ fixes both x and $\sigma(x) \in O_t$, since its support is disjoint from O_t, so the product sends x to $c_t(x) = \sigma(x)$.

Step 3: uniqueness. Let $\sigma = d_1 \cdots d_s$ with $d_1, \ldots, d_s$ cycles of pairwise disjoint supports $D_1, \ldots, D_s$. For $x \in D_t$, the argument of Step 2 gives $\sigma(x) = d_t(x) \in D_t$, so $\sigma^k(x) = d_t^k(x)$ for every $k \geq 0$. Writing $d_t = (b_1\ \cdots\ b_m)$, the iterates of d_t carry each b_i through all of $b_1, \ldots, b_m$, so $O_x = D_t$. Then d_t agrees with σ on O_x and fixes everything else, that is, d_t is the cycle attached to O_x in Step 1. An element outside all the D_t is fixed by σ, so its set O_x has one element. Hence the supports $D_1, \ldots, D_s$ are exactly the sets O_a with at least two elements, and $\{d_1, \ldots, d_s\} = \{c_1, \ldots, c_r\}$, completing the proof.

Definition 1.2.15: Cycle Type

Let $\sigma \in S_n$, and write σ as a product of cycles with pairwise disjoint supports (proposition 1.2.14). The *cycle type* of σ is the list of the lengths of these cycles, in increasing order. It is well defined because the cycles are determined by σ.

Example 1.2.16: Cycle-Type

$(1\,2\,4\,3)(5\,7\,8)(6\,9)$ is equivalent to $(6\,9)(5\,7\,8)(1\,2\,4\,3)$ which we can label as a $(2, 3, 4)$-cycle type. If you have a $(1\,2)(3\,4)$ permutation, then it's a $(2, 2)$-cycle type.

A cycle of particular importance are 2-cycles.

Definition 1.2.17: Transposition

2-cycles are usually referred to as ***transpositions***

Using transpositions, any n-cycle can be decomposed into the product of transpositions. For example, take:

$$(1\,2\,4\,3)$$

Then the reader should verify that:

$$(1\,3)(1\,4)(1\,2) = (1\,2\,4\,3)$$

So, the cycle broke up into 3 transpositions. In fact, an n-cycle is a product of $n-1$ transpositions, and of no fewer.

Theorem 1.2.18: n-Cycle Breakdown To Exactly $n-1$ Transpositions

Let σ be an n-cycle in a symmetric group S_N, where $N \geq n$. Then σ can be broken down to the composition of exactly $n-1$ transpositions, and it is not a composition of fewer than $n-1$ transpositions

***Proof*:**
Write $\sigma = (a_1\ a_2\ \cdots\ a_n)$. A decomposition into $n-1$ transpositions is namely:

$$(a_1\ a_2\ \cdots\ a_n) = (a_1\ a_n)(a_1\ a_{n-1})\cdots(a_1\ a_2)$$

To verify this, recall that in a product of cycles the rightmost cycle is applied first. Fix a_i with $2 \leq i \leq n-1$. The factors $(a_1\ a_2), \ldots, (a_1\ a_{i-1})$ fix a_i, the factor $(a_1\ a_i)$ sends a_i to a_1, the factor $(a_1\ a_{i+1})$ sends a_1 to a_{i+1}, and the remaining factors fix a_{i+1}. Hence the product sends a_i to a_{i+1}. Similarly, a_1 is sent to a_2 by the first factor and then fixed by all later factors, and a_n is fixed by every factor except the last, which sends it to a_1. Any other letter appears in no factor and is fixed. The two sides therefore agree, so σ is a product of $n-1$ transpositions.

It remains to show that no decomposition uses fewer. Suppose $\sigma = \tau_k \cdots \tau_1$ with each τ_j a transposition. Form the graph Γ whose vertices are the letters $a_1, \ldots, a_n$ together with every letter appearing in some τ_j, and which has one edge $\{x, y\}$ for each factor $\tau_j = (x\ y)$. We claim that for every vertex x, the letter $\sigma(x)$ lies in the connected component of x. We induct on k. For $k = 0$ the product is the identity and the claim is trivial. If $\sigma = \tau_k \sigma'$ with $\sigma' = \tau_{k-1} \cdots \tau_1$, then $\sigma'(x)$ lies in the component of x by induction, and τ_k either fixes $\sigma'(x)$ or moves it along an edge of Γ, proving the claim. Since σ sends $a_1 \mapsto a_2 \mapsto \cdots \mapsto a_n$, the claim puts all of $a_1, \ldots, a_n$ in a single component. If Γ has m vertices, then with no edges it has m components, and adding an edge decreases the number of components by at most one, so Γ has at least $m-k$ components. On the other hand, since the n distinct letters $a_1, \ldots, a_n$ share one component, Γ has at most $m-n+1$ components. Hence $m-k \leq m-n+1$, that is $k \geq n-1$, as we sought to show.

Corollary 1.2.19: Permutations Are Products Of Transpositions

Every $\sigma \in S_n$ is a product of transpositions, the empty product being id.

***Proof*:**
By proposition 1.2.14, $\sigma = c_1 \cdots c_r$ with each c_t a cycle of some length $m_t \geq 2$. By theorem 1.2.18, each c_t is a product of $m_t - 1$ transpositions. Writing each c_t in this way expresses σ as a product of $(m_1 - 1) + \cdots + (m_r - 1)$ transpositions, as claimed.

The number of transpositions in such a product is not determined by the permutation, since (1 2)(1 2) and the empty product both equal id, but its parity is (theorem 1.2.20(4)).

Theorem 1.2.20: The Sign Of A Permutation

For $\sigma \in S_n$ define the rational number

$$\operatorname{sgn}(\sigma) = \prod_{1 \leq i < j \leq n} \frac{\sigma(j) - \sigma(i)}{j - i}$$

the empty product being 1. Then:

1. $\operatorname{sgn}(\sigma) \in \{1, -1\}$ for every $\sigma \in S_n$
2. $\operatorname{sgn}(\sigma\tau) = \operatorname{sgn}(\sigma)\operatorname{sgn}(\tau)$ for all $\sigma, \tau \in S_n$, and $\operatorname{sgn}(\mathrm{id}) = 1$
3. $\operatorname{sgn}(\tau) = -1$ for every transposition $\tau \in S_n$
4. if $\sigma = \tau_1 \cdots \tau_k$ with transpositions $\tau_1, \ldots, \tau_k$, then $\operatorname{sgn}(\sigma) = (-1)^k$. In particular, any two expressions of σ as a product of transpositions have numbers of factors of the same parity.

***Proof*:**
Let P be the set of two-element subsets of $\{1, \ldots, n\}$. A permutation σ sends each $e = \{a, b\} \in P$ to $\sigma(e) = \{\sigma(a), \sigma(b)\} \in P$, and $e \mapsto \sigma(e)$ is a bijection of P, with inverse $e \mapsto \sigma^{-1}(e)$. For $e = \{a, b\} \in P$ put

$$q_\sigma(e) = \frac{\sigma(b) - \sigma(a)}{b - a}$$

which does not change when a and b are exchanged, so it depends only on e. Each pair $i < j$ gives exactly one $e = \{i, j\} \in P$, so $\operatorname{sgn}(\sigma) = \prod_{e \in P} q_\sigma(e)$.

1. For $e = \{a, b\} \in P$ let $d(e) = |b - a|$, a positive integer, so that $|q_\sigma(e)| = d(\sigma(e))/d(e)$. Reindexing by the bijection $e \mapsto \sigma(e)$ gives $\prod_{e \in P} d(\sigma(e)) = \prod_{e \in P} d(e)$. Hence $|\operatorname{sgn}(\sigma)| = 1$, so $\operatorname{sgn}(\sigma) = \pm 1$.
2. For $e = \{a, b\} \in P$ we have $\tau(a) \neq \tau(b)$, and

$$q_{\sigma\tau}(e) = \frac{\sigma(\tau(b)) - \sigma(\tau(a))}{\tau(b) - \tau(a)} \cdot \frac{\tau(b) - \tau(a)}{b - a} = q_\sigma(\tau(e))\, q_\tau(e)$$

   Taking the product over $e \in P$ and reindexing the first factors by the bijection $e \mapsto \tau(e)$ gives $\operatorname{sgn}(\sigma\tau) = \operatorname{sgn}(\sigma)\operatorname{sgn}(\tau)$. Every factor of $\operatorname{sgn}(\mathrm{id})$ equals 1.
3. Let $\tau = (a\ b)$ with $a < b$. For $e = \{i, j\}$ with $i < j$, the factor $q_\tau(e) = (\tau(j) - \tau(i))/(j - i)$ is negative exactly when $\tau(j) < \tau(i)$. Since τ fixes every $k \neq a, b$, this happens for $e = \{a, b\}$,

and for $e = \{a, k\}$ and $e = \{k, b\}$ with $a < k < b$, because $\tau(a) = b > k = \tau(k)$ and $\tau(k) = k > a = \tau(b)$. It happens for no other e: a pair $\{a, k\}$ or $\{b, k\}$ with $k < a$ or $k > b$ keeps its order, since $\tau(a)$ and $\tau(b)$ lie in $\{a, b\}$, and a pair avoiding a and b is fixed. So exactly $1 + 2(b - a - 1)$ factors are negative, an odd number, and $\operatorname{sgn}(\tau) < 0$. By (1), $\operatorname{sgn}(\tau) = -1$.

4. By (2) and (3) and induction on k, $\operatorname{sgn}(\tau_1 \cdots \tau_k) = \operatorname{sgn}(\tau_1) \cdots \operatorname{sgn}(\tau_k) = (-1)^k$, the case $k = 0$ being $\operatorname{sgn}(\mathrm{id}) = 1$. If also $\sigma = \tau'_1 \cdots \tau'_l$ with transpositions τ'_i, then $(-1)^k = \operatorname{sgn}(\sigma) = (-1)^l$, so k and l have the same parity, completing the proof.

Definition 1.2.21: Parity Of Cycle

Let $\sigma \in S_n$. The *parity* of σ is the parity of the number of factors in any expression of σ as a product of transpositions. Such expressions exist by corollary 1.2.19, and their numbers of factors all have the same parity by theorem 1.2.20(4), so σ has even parity exactly when $\operatorname{sgn}(\sigma) = 1$. A permutation of even parity is called an *even permutation*, and one of odd parity an *odd permutation*.

For example, an m-cycle is a product of $m - 1$ transpositions (theorem 1.2.18), so it is odd when m is even and even when m is odd.

Parity might seem like a weird thing to care about, but it will in fact come in very useful. So useful in fact, that there's a special name for groups based around parity:

Definition 1.2.22: Alternating Group

Let S_n be the permutation group permuting n elements. Then $A_n \subseteq S_n$ is the set of even permutations, that is, $A_n = \{\sigma \in S_n \mid \operatorname{sgn}(\sigma) = 1\}$. By theorem 1.2.20(2), $\mathrm{id} \in A_n$, a product of two even permutations is even, and the inverse of an even permutation σ is even, since $\operatorname{sgn}(\sigma^{-1}) \operatorname{sgn}(\sigma) = \operatorname{sgn}(\mathrm{id}) = 1$. Thus

$$A_n \leqslant S_n$$

Why this group is interesting requires more algebraic tools, so we will leave at defining it for now and get back to it to show it's use.

At the origins of group theory, in the study of polynomial equations, the groups studied were groups of permutations, that is, subgroups of symmetric groups. Cayley proposed abstract axioms for groups in the middle of the nineteenth century, with little impact at the time, and in 1882 Weber gave an axiomatic definition of a finite group [55, Section 27.2]. Later in this book, it shall be shown that every group is isomorphic to a subgroup of a symmetric group (see theorem 4.5.3).

Example 1.2.23: Interesting Exercises on Commutativity

We earlier mentioned how being commutative is a nice property, and that groups which are commutative are quite nice. It was also mentioned that S_n is in a sense the most general group that possible. So, in a sense, if we can establish properties of S_n for particular orders, that can be quite insightful.

Here's one such property worth proving. If we take S_n, $n \geq 3$, then S_n is *not* commutative To prove this, try composing a n-cycles and a 2-cycle which are not disjoint form the left and right and see what you get

Properties of Symmetric Groups

Proposition 1.2.24: Order of element is p iff composition of disjoint p-cycles

Let p be a prime. Then an element of S_n has order p if and only if its cycle decomposition is a product of (commuting) p-cycles.

***Proof*:**

First, if c is an m-cycle $(a_1\ a_2\ \cdots\ a_m)$, then an induction on j shows that $c^j(a_i) = a_{i+j}$, reading subscripts modulo m. In particular $c^m = \mathrm{id}$ while $c^j(a_1) = a_{1+j} \neq a_1$ for $0 < j < m$, so $|c| = m$. Second, if c and d are disjoint cycles, then $cd = dc$. Indeed, injectivity shows each cycle maps the set of letters it moves into itself, so on a letter moved by c both products act as c, on a letter moved by d both act as d, and both fix every other letter.

Now write σ in its cycle representation $\sigma = c_1c_2\cdots c_r$, a product of disjoint cycles with c_t an m_t-cycle and $m_t \geq 2$ (proposition 1.2.14). Since the c_t commute, $\sigma^k = c_1^k c_2^k \cdots c_r^k$ for every k. The permutations $c_1^k, \ldots, c_r^k$ move pairwise disjoint sets of letters, and on every letter that c_t moves the product agrees with c_t^k. Hence $\sigma^k = \mathrm{id}$ if and only if each $c_t^k = \mathrm{id}$, which by the first fact happens if and only if $m_t \big| k$ for every t. Therefore $\sigma^k = \mathrm{id}$ if and only if $\mathrm{lcm}(m_1, \ldots, m_r) \big| k$, that is, $|\sigma| = \mathrm{lcm}(m_1, \ldots, m_r)$.

If the cycle representation of σ consists of p-cycles, then $m_1 = \cdots = m_r = p$, so $|\sigma| = \mathrm{lcm}(p, \ldots, p) = p$. Conversely, if $|\sigma| = p$, then each m_t divides $\mathrm{lcm}(m_1, \ldots, m_r) = p$. Since p is prime and each $m_t \geq 2$, every m_t equals p, so the cycle representation of σ is a product of (commuting) p-cycles.

Note that if p is not prime, the "if and only if" is not necessarily true.

Example 1.2.25: Counter-Examples

1. Take
$$s = (1\,2)(3\,4\,5\,6) = s_1 s_2$$
Then $(s_1 s_2)^4 = 1$, but $|s_1| = 2$.

2. Take $(1\,2)(3\,4\,5) \in S_5$. Then
$$\begin{aligned}(1\,2)(3\,4\,5)^2 &= (3\,5\,4)\\ (1\,2)(3\,4\,5)^3 &= (1\,2)\\ (1\,2)(3\,4\,5)^4 &= (3\,4\,5)\\ (1\,2)(3\,4\,5)^5 &= (1\,2)(3\,5\,4)\\ (1\,2)(3\,4\,5)^6 &= id\end{aligned}$$
but $6 > 5$. Thus, we found a cycle of order 6 in S_5. The trick was to find two disjoint cycles such that the $\mathrm{lcm}(\sigma, \tau) > n$.

Proposition 1.2.26: σ is p-cycle for prime p then σ^k is p-cycle

Let p be a prime and let $\sigma \in S_n$ be a p-cycle. Then σ^k is a p-cycle for every $1 \leq k \leq p-1$.

***Proof*:**
Write $\sigma = (a_0\ a_1\ \cdots\ a_{p-1})$ and read subscripts modulo p. Then $\sigma(a_i) = a_{i+1}$, so induction on k gives $\sigma^k(a_i) = a_{i+k}$, and σ^k fixes every element outside $\{a_0, \ldots, a_{p-1}\}$. Let $1 \leq k \leq p-1$. The elements $a_0, a_k, a_{2k}, \ldots, a_{(p-1)k}$ are distinct: if $a_{ik} = a_{jk}$ with $0 \leq i < j \leq p-1$, then p divides $(j-i)k$, which is impossible because the prime p divides neither $j-i$ nor k, both lying between 1 and $p-1$. So these are all of $a_0, \ldots, a_{p-1}$, and σ^k sends each of them to the next one in the list and $a_{(p-1)k}$ to $a_{pk} = a_0$. Hence $\sigma^k = (a_0\ a_k\ a_{2k}\ \cdots\ a_{(p-1)k})$ is a p-cycle, as claimed.

The proposition fails for cycles of composite length. For the 4-cycle $\sigma = (1\,2\,3\,4)$,

$$\sigma^2 = (1\,3)(2\,4) \qquad \sigma^3 = (1\,4\,3\,2)$$

so σ^3 is again a 4-cycle, while σ^2 is a product of two disjoint 2-cycles. The shape of σ^2 also follows from proposition 1.2.24: $\sigma^2 \neq \mathrm{id}$ and $(\sigma^2)^2 = \sigma^4 = \mathrm{id}$, so σ^2 has order 2 and is a product of disjoint 2-cycles. In general, whenever a power of a cycle has prime order p, proposition 1.2.24 shows that this power is a product of disjoint p-cycles.

Proposition 1.2.27: Conjugation preserves permutation-type

Let $\sigma \in S_n$ and let $\tau = (a_1\ a_2\ \cdots\ a_k)$ be a k-cycle. Then

$$\sigma\tau\sigma^{-1} = (\sigma(a_1)\ \sigma(a_2)\ \cdots\ \sigma(a_k))$$

that is, $\sigma\tau\sigma^{-1}$ is obtained by applying σ to every entry of τ. Consequently, π and $\sigma\pi\sigma^{-1}$ have the same cycle type (definition 1.2.15) for every $\pi \in S_n$.

***Proof*:**
For $1 \leq i \leq k$, $\sigma\tau\sigma^{-1}(\sigma(a_i)) = \sigma(\tau(a_i)) = \sigma(a_{i+1})$, reading a_{k+1} as a_1. If $y \notin \{\sigma(a_1), \ldots, \sigma(a_k)\}$, then $\sigma^{-1}(y) \notin \{a_1, \ldots, a_k\}$ is fixed by τ, so $\sigma\tau\sigma^{-1}(y) = y$. These are the values of the cycle $(\sigma(a_1)\ \cdots\ \sigma(a_k))$, which proves the displayed formula. Now write $\pi = c_1 \cdots c_r$ with cycles c_t of pairwise disjoint supports (proposition 1.2.14). Since the inner factors $\sigma^{-1}\sigma$ cancel,

$$\sigma\pi\sigma^{-1} = (\sigma c_1 \sigma^{-1})(\sigma c_2 \sigma^{-1}) \cdots (\sigma c_r \sigma^{-1})$$

By the formula, $\sigma c_t \sigma^{-1}$ is a cycle of the same length as c_t whose support is the image under σ of the support of c_t. These supports are pairwise disjoint because σ is injective, so by the uniqueness in proposition 1.2.14 the cycle type of $\sigma\pi\sigma^{-1}$ is that of π, as claimed.


1.2.3 Dihedral Groups

In classical geometry, an n-gon for $n \in \mathbb{N}$ is a 2D shape with all sides of the same length. For example, a triangle is a 3-gon, a square is a 4-gon, a pentagon is a 5-gon, and so forth, while a rectangle and a


circle are not n-gons. Each of these shapes can be rotated or reflected in such a way that we get back the same shape: these are called the *rigid-motion symmetries* or just *symmetries* of the n-gon. The term *rigid motion* comes from analysis/linear-algebra where a function $f : X \to X$ is called a *rigid motion* if the distance between each point remains the same after the application of the function. Notationally, this would be represented as:

$$\|f(x) - f(y)\| = \|x - y\|$$


where the $\| - \| : X \to \mathbb{R}_{>0}$ is a special kind of function called the *norm* which defines size and distance information on a space[15]. We shall not use rigid motions explicitly, however we shall insure that when transforming n-gons, their they shall never stretch (ex. a square shall not become a rectangle). We shall further place the restriction that the rigid motions of the n-gons have to map to themselves, this is another way of saying that it is a *symmetry*. For example, if we choose a square (a 4-gon):



and rotated it a quarter turn to the right (90 degrees to the right or $\pi/2$ radians to the right), then we'd get back a square



if we were to rotate it an eighth of a turn, we would not get the exact shape back:



Let's label quarter turns to the right r (for **r**otate). Compounding rotations, the resulting square get's rotated by π, $3\pi/2$, and 2π radians. Each of these can be labeled r^2, r^3, and r^4 respectively. Another symmetry of the square would be reflections, namely there is a vertical, horizontal, and two diagonal reflections: $\sigma_h, \sigma_v, \sigma_{d1}, \sigma_{d_2}$. These are not all the symmetries of a square (for example, we transpose the left-edge with the right edge), however it is the only symmetries that are also *rigid motions* (the reader who is already comfortable with norms form linear algebra is free to prove this fact).

More formally, we may represent any n-gon with n-points, with the restrictions that any symmetry (i.e. bijection) f applied to these n-points must further follow the restrictions that the n-gon these

[15] Norms are introduced formally in *Linear Algebra* [31].

points represent must transform as a rigid-motion (all points must remain equi-distant). This special subset of S_n with this added restriciton is called the *dihedral group*:

Definition 1.2.28: Dihedral Groups

Let S_n be the symmetric group on n elements and take the subset $D_n \subseteq S_n$ for which the permutations further follow the restriction of rigid-motions (so that these points represent an n-gon).Then D_n is called the *dihedral group*.

In order for the set D_n to be a group, one ought to prove this is indeed the csae

***Proof*:**

1. Identity comes from the identity function $\mathrm{id}_n \in D_n$ since it is certainly a rigid motion.
2. The inverse come from the fact that if σ is a rigid motion, it's inverse is as well
3. The set is associative since its a collection of functions
4. The composition of two rigid motions is a rigid motion, and hence the binary operation is well-defined

Proposition 1.2.29: Properties of D_n

Let $G = D_n$. Let r represent rotation by $2\pi/n$, and s represent a reflection about some fixed axis. Then:

1. $1, r, \ldots, r^{n-1}$ are all distinct and $r^n = 1$, so $|r| = n$
2. $|s| = 2$
3. $s \neq r^i$ for any i
4. $sr^i \neq sr^j$ for all $0 \leq i, j \leq n-1$ with $i \neq j$, so

$$D_n = \left\{1, r, r^2, \cdots, r^{n-1}, s, sr, sr^2, \cdots, sr^{n-1}\right\}$$

   i.e. each element can be written uniquely in the form $s^k r^i$ for some $k = 0$ or 1, and $i = 0, \cdots, n-1$

5. $rs = sr^{-1}$. In particular this shows D_n is not abelian!
6. $r^i s = sr^{-i}$ (use induction)

***Proof*:**
Label the vertices of the n-gon $1, 2, \ldots, n$ counterclockwise, and read all labels modulo n, so that vertex $n+1$ means vertex 1. Recall that a product of symmetries applies the rightmost factor first.

In a regular n-gon, the distance between two distinct vertices depends only on how many edges apart they lie along the polygon, and it is smallest exactly when they are adjacent. An element

$g \in D_n$ preserves all distances between vertices, so g sends adjacent vertices to adjacent vertices, that is, $g(k+1) = g(k)+1$ or $g(k+1) = g(k)-1$ for every k. Moreover the sign is the same for every k: if $g(k+1) = g(k)+1$ and $g(k+2) = g(k+1)-1$ for some k, then $g(k+2) = g(k)$, contradicting injectivity (here we use $n \geq 3$). Hence every $g \in D_n$ has the form

$$g(k) = a + \epsilon k \pmod{n} \qquad a \in \{1, \ldots, n\},\ \epsilon \in \{+1, -1\}$$

and there are at most $2n$ such maps. For $n \geq 3$ no map has both forms, since $a + k = a' - k$ for all k would force $n \mid 2$. The sign ϵ of g is therefore well-defined. Composing two such maps gives $g(h(k)) = (a_g + \epsilon_g a_h) + \epsilon_g \epsilon_h k$, so the sign of gh is $\epsilon_g \epsilon_h$.

The rotation r sends each vertex to the next one counterclockwise, so $r(k) = k+1$ and more generally $r^i(k) = k+i$, of sign $+1$. The reflection s produces a mirror image, so it reverses the counterclockwise order of the vertices. Its sign is therefore -1, and by the affine form above, $s(k) = c - k$ for some fixed c.

1. $r^i(n) = i$, so $1, r, \ldots, r^{n-1}$ act differently on the vertex n and are pairwise distinct, while $r^n(k) = k + n = k$, so $r^n = 1$. Hence $|r| = n$.
2. $s^2(k) = c - (c - k) = k$, so $s^2 = 1$, and $s \neq 1$ since s has sign -1 while the identity has sign $+1$. Hence $|s| = 2$.
3. s has sign -1 and every r^i has sign $+1$, so $s \neq r^i$ for any i.
4. If $sr^i = sr^j$, then multiplying by s^{-1} on the left gives $r^i = r^j$, so $i = j$ by (1). Also $sr^i \neq r^j$ for all i, j, since sr^i has sign -1 and r^j has sign $+1$. Hence the $2n$ listed elements are pairwise distinct. Conversely, take any $g \in D_n$, say $g(k) = a + \epsilon k$. If $\epsilon = +1$, then $g = r^a$. If $\epsilon = -1$, then $(sr^{c-a})(k) = s(k + c - a) = a - k = g(k)$, so $g = sr^{c-a}$. Hence the list exhausts D_n, and each element is uniquely of the form $s^k r^i$ with $k = 0$ or 1 and $i = 0, \ldots, n-1$.
5. $(rs)(k) = r(c - k) = c - k + 1$ and $(sr^{-1})(k) = s(k-1) = c - k + 1$, so $rs = sr^{-1}$. Since $n \geq 3$, $r^{-1} \neq r$ by (1), so $rs = sr^{-1} \neq sr$ by the uniqueness in (4), and D_n is not abelian.
6. We induct on i, the case $i = 1$ being (5). If $r^i s = sr^{-i}$, then

$$r^{i+1}s = r(r^i s) = r(sr^{-i}) = (rs)r^{-i} = (sr^{-1})r^{-i} = sr^{-(i+1)}$$

completing the induction.

In particular, we know now any element in D_n can be written as $s^k r^i$, with $k = 0 \vee 1$ and $0 \leq i \leq n-1$. For example, if $n = 12$:

$$(sr^9)(sr^6) = sr^9 sr^6 = sr^9 r^{-6} s = sr^3 s = s^2 r^{-3} = r^{-3} = r^9$$

This group will come up very often since it's a particularly simple.

Proposition 1.2.30: Order of Dihedral Group

Let D_n be a dihedral group. Then:

$$|D_n| = 2n$$

***Proof*:**
By proposition 1.2.29(4), the $2n$ elements $1, r, \ldots, r^{n-1}, s, sr, \ldots, sr^{n-1}$ are pairwise distinct and every element of D_n appears in this list. Hence $|D_n| = 2n$.

Some authors like to put the order of the Dihedral group in the subscript, that is they write D_{2n}. This convention is rather confusing given the original intuition behind Dihedral groups, and so the D_n notation is used instead for the clarity it brings.

1.2.4 Quaternion Group

The Quaternion (or Hamiltonian) group is a group with 2 fundamental interpretation:

1. The Quaternions are a generalization of the complex numbers. We can think of the fact that $i^2 = -1$ to be the key property which distinguishes the complex numbers from other number systems. If we take $C = \{-1, 1, i, -i\} \subseteq \mathbb{C}$, then

   $$\langle C | i^2 = -1 \rangle$$

   will form the group which represents the rotation of $\pi/2$ in the cartesian plane. William Hamilton around the 1840s started a project to try an make 3D numbers $(1, i, j)$, the same way $\mathbb{C}$ can be thought of as 2D $(1, i)$. He could not manage to make them 3D, but realized the key generalization is making them "4D" $(1, i, j, k)$. The story goes that Hamilton had this flash of inspiration near a bridge in 1843 and wrote down the idea under that very bridge. Today, there is a plaque commemorating the moment of inspiration.

2. It got discovered later that Quaternions efficiently capture the idea of rotating a 3D object in 3D space. At the beginning of vector calculus, some mathematician considered using quaternion instead of vectors as the pedagogical tool used to introduce the concept of 3D rotation, but pedagogical history went with the vector notation. In quantum mechanics, the Pauli spin matrices of 1927, multiplied by $-i$, satisfy the quaternion relations, so quaternions also describe *spin*, a fundamental property of sub-atomic particles.

Let $Q_8 = \{1, -1, i, -i, j, -j, k, -k\}$, with the multiplication given by the following rules. The element 1 is the identity. The element -1 commutes with every element and satisfies $(-1)^2 = 1$, and for $a \in \{1, i, j, k\}$ the product $(-1)a$ is written $-a$. Finally,

$$i^2 = j^2 = k^2 = -1 \qquad ij = k \qquad ji = -k \qquad jk = i \qquad kj = -i \qquad ki = j \qquad ik = -j$$

These rules determine every product, for instance $(-i)j = (-1)(ij) = -k$, and fig. 1.1 lists them all. Hamilton summarized them as $i^2 = j^2 = k^2 = ijk = -1$. The multiplication is associative: sending ± 1 to $\pm I$ and

$$i \mapsto \begin{pmatrix} i & 0 \\ 0 & -i \end{pmatrix} \qquad j \mapsto \begin{pmatrix} 0 & 1 \\ -1 & 0 \end{pmatrix} \qquad k \mapsto \begin{pmatrix} 0 & i \\ i & 0 \end{pmatrix}$$

(and $-a$ to the negative of the image of a) identifies Q_8 with eight complex 2×2 matrices satisfying the same rules, and matrix multiplication is associative.

This group is interesting, for it is the second non-abelian group of order 8 in this book, D_4 being the other. Both come from geometry, D_4 from the symmetries of a square and Q_8 from Hamilton's quaternions, but they have different multiplication tables:

Example 1.2.31: Comparing D_4 and Q_8

Element	1	-1	i	$-i$	j	$-j$	k	$-k$
1	1	-1	i	$-i$	j	$-j$	k	$-k$
-1	-1	1	$-i$	i	$-j$	j	$-k$	k
i	i	$-i$	-1	1	k	$-k$	$-j$	j
$-i$	$-i$	i	1	-1	$-k$	k	j	$-j$
j	j	$-j$	$-k$	k	-1	1	i	$-i$
$-j$	$-j$	j	k	$-k$	1	-1	$-i$	i
k	k	$-k$	j	$-j$	$-i$	i	-1	1
$-k$	$-k$	k	$-j$	j	i	$-i$	1	-1

Figure 1.1: Q_8 Multiplication Table

While D_4 has

Element	e	a	a^2	a^3	x	ax	a^2x	a^3x
e	e	a	a^2	a^3	x	ax	a^2x	a^3x
a	a	a^2	a^3	e	ax	a^2x	a^3x	x
a^2	a^2	a^3	e	a	a^2x	a^3x	x	ax
a^3	a^3	e	a	a^2	a^3x	x	ax	a^2x
x	x	a^3x	a^2x	ax	e	a^3	a^2	a
ax	ax	x	a^3x	a^2x	a	e	a^3	a^2
a^2x	a^2x	ax	x	a^3x	a^2	a	e	a^3
a^3x	a^3x	a^2x	ax	x	a^3	a^2	a	e

Figure 1.2: D_4 Multiplication Table

which the reader will notice is different

We will be able to show that two groups are not the same once we introduce the concept of isomorphisms (section 1.4).

Exercise 1.2.1

1. Show that there exists 4 homomorphisms $\varphi : Q_8 \to \mathbb{R}^\times$

1.2.5⋆ Matrix Groups

⋆ *Optional. This subsection is an aside; nothing later in the book depends on it.*

This section assumes either some linear algebra knowledge or that you have internalized some of section 0.5 (however, some of these collection of objects goes beyond that section). All prerequisite knowledge assumed in this section shall be covered in great detail in chapter 13 and section 13.2. For the inner-product background behind the orthogonal and unitary groups, see *Linear Algebra* [31]. Let's first recall the notation we use to describe the collection of matrices:

Definition 1.2.32: Matrix Group Under Addition

Let G be an abelian group. Then The set $M_{n\times m}(\mathbb{F})$ forms a group under element-wise operation of G, namely:

$$A * B \equiv (a_{ij} * b_{ij})_{ij}$$

If the reader is familiar with linear algebra, they may notice this group is not that interesting: it is equivalent to the group G^{nm}[16]. Sticking to $G = k$ is a field (notice that all fields are Abelian groups under addition), the more interesting binary operation that can be performed on matrices is matrix multiplication, since it combines elements in much more interesting ways. As you might recall, matrix multiplication requires dimensions to line up properly, so for associative to hold, we will have the dimensions be the same. Furthermore, the identity must be I, the matrix with 1's on the diagonal, and zero's everywhere else. If there are matrices that multiply and *do not* get to I, then they cannot be in the group. Hence, the subset of invertible matrices from $M_n(k)$ must be selected in order to make a group, which the reader may recall from linear algebra implies we are taking the set for which all matrices have a non-zero determinant

Definition 1.2.33: General Linear Group

Let F be a field. Then

$$GL_n(F) = \{A \mid A \text{ is an } n \times n \text{ matrix with entries from } F \text{ and } \det(A) \neq 0\}$$

We will also name 3 special subgroups of GL_n since it comes up often enough. Check that these are indeed groups:

Definition 1.2.34: Special Linear Group

$$SL_n(F) = \{A \mid A \text{ is an } n \times n \text{ matrix with entries from } F \text{ and } \det(A) = 1\}$$

If $F \in \{\mathbb{R}, \mathbb{C}\}$, then geometrically these can be thought of as the volume and orientation preserving functions.

Definition 1.2.35: Orthogonal Group

$$O_n(F) = \left\{A \;\middle|\; A \text{ is an } n \times n \text{ matrix with entries from } F \text{ and } A^tA = AA^t = I\right\}$$

[16]We can show this once we get to isomorphisms (definition 1.4.12)

In this group, the transformations are *distance-preserving*, which as an exercise the reader can check that for $O_2(\mathbb{R})$, all transformations are rotations and reflections across lines passing through the origin[17]. Limiting to orthogonal matrices with determinant 1 gives us the set of all rotations:

Definition 1.2.36: Special Orthogonal Group

$$SO_n(F) = \{A \in O_n(F) \mid \det(A) = 1\}$$

If the underlying field is clear, we sometimes write $SO(n)$.

For a finite field F with q elements, the group $GL_n(F)$ has $(q^n - 1)(q^n - q) \cdots (q^n - q^{n-1})$ elements (proposition 13.2.20). The count uses the linear algebra of chapter 13.

Exercise 1.2.2

1. for $n > 1$, $\mathbb{Z}/n\mathbb{Z}$ is not a group under multiplication (hint: think of identity)
2. prove that every element in a finite group has finite order
3. if $x \in G$, G a group, and $|x| = n$, then $x^{-1} = x^{n-1}$.
4. $x \in G$, G a group. Then $|x| = |x^{-1}|$. (hint: $(x^{-1})^n = (x^n)^{-1}$ for every $n \in \mathbb{N}$, and the case of infinite order follows from the finite one)
5. $x, g \in G$, G a group. Then $|x| = |g^{-1}xg|$. Deduce that $|ab| = |ba|$ for all $a, b \in G$. (hint: simply assign an order to x, and expand $g^{-1}xg$. things will cancel out nicely. For the second part, start with ab, and multiply like so $babb^{-1}$. By what you have shown, this has the same order).
6. $x \in G$, $|x| = n < \infty$. If $n = st$ for some positive integers s and t, prove that $|x^s| = t$. (hint: how many times do you need to multiply x^s to get to 1)
7. if $x^2 = 1$ for all $x \in G$ then G is abelian.
8. if x is an element of the group G, then $H = \{x^n | n \in \mathbb{Z}\}$ is a subgroup (cf. show for all $h, k \in H$, $hk \in H$, $h^{-1} \in H$) of G (called the *cyclic subgroup* of G generated by x)
9. $A \times B$ is abelian if and only if A and B is abelian
10. Let $A \times B$ be the *direct product* group formed by the cartesian product of the group A, B as shown in example 1.1.5. Show that $(a, 1)$ and $(1, b)$ commute. Deduce that the order of (a, b) is the least common multiple of $|a|$ and $|b|$.
11. any finite group G of even order contains an element of order 2. (hint: let $t(G)$ be the set $\left\{g \in G | g \neq g^{-1}\right\}$. Show that $t(G)$ has even number of elements and every non-identity element of $G - t(G)$ has order 2).
12. Challenging exercise. Let A be a set containing numbers. Define the following

$$\mathcal{A} = \bigoplus_{i=1}^{\infty} A$$

[17] Higher dimensional analogues of "rotation" and "reflection" come from taking this interpretation in lower dimensions and claiming it generalizes to higher dimensions

to be the set of infinitely long tuples in which *all but finitely many* entries are zero. For example, if $A = \{1, 2, 3\}$, then

$$(0, 0, 1, 0, 2, 0, 0, 0, 0, 1, 3, 3, 2, 0, ...)$$

where the ... means there are zeros going on forever. Then this tuples is in $\mathcal{A}$. On the other hand

$$(1, 1, 1, 1, 1, ...)$$

where the ... means the ones are going on forever is not in $\mathcal{A}$.

If G is a group, let

$$\mathcal{G} = \bigoplus_{i=1}^{\infty} G$$

be the set of tuples in which all but finitely many entries are the identity e, and define the operation on $\mathcal{G}$ to be pointwise:

$$(a_1, a_2, a_3, ...) \cdot (b_1, b_2, b_3, ...) = (a_1 b_1, a_2 b_2, a_3 b_3, ...)$$

Show that $\mathcal{G}$ along with this operation is a group.

13. Let p be a prime number. Show that $(\mathbb{Z}/p\mathbb{Z})$ is a cyclic group.

14. Let $n = 8$. What is $(\mathbb{Z}/8\mathbb{Z})^\times$? What if $n = 9$. Conclude that in general, $(\mathbb{Z}/n\mathbb{Z})^\times$ is not necessarily cyclic, but it can be.

15. Show that the rotation groups of the regular tetrahedron, cube and dodecahedron are isomorphic to A_4, S_4 and A_5 respectively, and that a platonic solid and its dual have the same rotation group. Conclude that the five platonic solids give three finite subgroups of $SO(3)$, up to conjugacy, that are neither cyclic nor dihedral.

16. The *Heisenberg group* over a field F is the set of upper triangular 3×3 matrices over F with every diagonal entry equal to 1. Show that it is a subgroup of $GL_3(F)$ and that it is not abelian.

17. (If you know the dot product) Recall that if v, w are vectors then the dot product can be represented as $v \cdot w = v^T w$ where v^T is the transpose. Show that matrices in $O_n(\mathbb{R})$ preserve the dot product (namely $Av \cdot Aw = v \cdot w$).

1.3 Generators and Relations

(When dealing with numbers, they can represent anything, for example 5 apples, 5 cars, 5 textbooks, and so forth. However, when we defined the dihedral group. it was specifically linked to the rotation and reflections of n-gons. In this section, we will show a way to abstract away this dependency on a concrete object to define a group).

Notice that D_n can be written with r and s (reflections and rotations). Similarly, $\langle x \rangle \leqslant G$ is an element from which we can find every other element of $\langle x \rangle$. In a sense, they *generated* the group. This notion will be treated rigorously with free groups later (section 2.3.3), but intuitively this idea makes sense. For now, here how we will define them

Definition 1.3.1: Generators

A subset S of elements of a group G with the property that every element of G can be written as a (finite) product of elements of S and their inverses is called the set of *generators* of G. If $x \subseteq G$ generates x, then we write $\langle x \rangle$. Similarly, if $x, y \in G$ are needed to generate G, we write $\langle x, y \rangle$. More generally, if $A \subseteq G$ generates G we write $\langle A \rangle$.

Example 1.3.2: Generators

1. An easy example would be 1 for $\mathbb{Z}$, since every $x \in \mathbb{Z}$ could be written as adding 1 or it's inverse. So $\mathbb{Z} = \langle 1 \rangle$.
2. By property (4) for D_n, $S = \{r, s\}$ is a set of generators of D_n, so $D_n = \langle r, s \rangle$.

Later, we will see for finite groups that we do not need the inverse operation to generate finite groups. For any set of generators, we have a set of relationships that they satisfy[18]. For D_n, they are

$$r^n = 1, \qquad s^2 = 1, \qquad rs = sr^{-1}$$

Why are these the relations? Because any additional relation between elements of D_n may be derived from these three (example 3.2.4 proves this once presentations are defined formally). Note that there can be more than one set of relations for a group (we will see later that D_n has another set of relations that can be used).

Definition 1.3.3: Presentation of a group

if some group G is generated by a subset S and there is some collection of relations, say $R_1, \cdots, R_m$, which are all equations with elements from $S \cup \{1\}$, such that any relation among the elements of S an be deduced from these, we shall call these generators and relations a *presentation* of G, and write

$$G = \langle S | R_1, \cdots, R_m \rangle$$

Example 1.3.4: Presentation

1. Show that the presentation:

   $$\langle r, s | r^n = 1, s^2 = 1, rs = sr^{-1} \rangle$$

   represents the Dihedral group D_n
2. Let A be any set. Show that

   $$\langle A | ab = 1, \forall a, b \in A \rangle$$

   is group. In particular, show that from any set, we can define the trivial group. Sections 1.2.2 and 2.3.3 give two other, non-trivial, ways of creating groups from arbitrary sets.

[18] With only one exception. When a set of generators has no relationships, we call the group generated by that set a *free group*

1.3.5 Prelude to Word Problem The relations of a presentation can be arbitrary equations, so it may be hard to decide when two elements of the group are equal, or to find the order of the group. For example,

$$\langle x, y \big| x^2 = y^2 = (xy)^2 = 1 \rangle$$

is a presentation of a group of order 4, while the similar-looking presentation

$$\langle x, y \big| x^3 = y^3 = (xy)^3 = 1 \rangle$$

defines an infinite group (example 3.2.5).

It might be tempting to only work with presentations, or to try and come up with every possible group working with generators. A considerable amount of time has been poured into this problem, and absolutely incredibly, it turns out that you can come up with presentations which are *insoluble*:

Example 1.3.6: Insoluble Presentation
The group representation by this monstrous presentation:

$$\begin{array}{lll}
\langle\ a,b,c,d,e,p,q,r,t,k & | & \\
p^{10}a = ap, & pacqr = rpcaq, & ra = ar, \\
p^{10}b = bp, & p^2adq^2r = rp^2daq^2, & rb = br, \\
p^{10}c = cp, & p^3bcq^3r = rp^3cbq^3, & rc = cr, \\
p^{10}d = dp, & p^4bdq^4r = rp^4dbq^4, & rd = dr, \\
p^{10}e = ep, & p^5ceq^5r = rp^5ecaq^5, & re = er, \\
aq^{10} = qa, & p^6deq^6r = rp^6edbq^6, & pt = tp, \\
bq^{10} = qb, & p^7cdcq^7r = rp^7cdceq^7, & qt = tq, \\
cq^{10} = qc, & p^8ca^3q^8r = rp^8a^3q^8, & \\
dq^{10} = qd, & p^9da^3q^9r = rp^9a^3q^9, & \\
eq^{10} = qe, & a^{-3}ta^3k = ka^{-3}ta^3 & \rangle
\end{array}$$

Figure 1.3: Group for which we cannot write out what the elements are

has elements which we *cannot* write out!

The details of this is are well beyond this course, but it's existence is still interesting to know about

https://en.wikipedia.org/wiki/Word_problem_for_groups

Proposition 1.3.7: Generators For Symmetric Group

$$S_n = \langle (i, i+1) \mid 1 \leq i \leq n \rangle$$

***Proof*:**
This proof relies on this key observation:

$$(a\,b)(a\,c)(a\,b)^{-1} = (a\,b)(a\,c)(a\,b) = (b\,c)$$

that is, we shifted a to b (so in a sense if $\sigma = (a\,b)$ and $\tau = (a\,c)$, $\sigma\tau\sigma^{-1} = (\sigma(a), \sigma(b))$).

With that in mind, we will proceed by *induction*. If $n = 2$, then S_2 is generated by this set, so assume it generate S_{n-1} and consider S_n. Take some cycle with n in it:

$$(a_1\, a_2 \ldots a_k\, n)$$

which we have shown earlier can be decomposed as

$$(a_1\, a_2)(a_1\, a_3)\cdots(a_1\, a_k)$$

All the $(a_1\, a_j)$ are in G by the induction hypothesis (they are not in because of the generating set because we do not know if $(a_1\, a_j) = (i\, i+1)$). What's left to show is whether $(a_1\, n)$ is in G. To do this, we use the conjugation fact we brought up earlier:

$$(a_1\, n) = (a_1\, n-1)(n-1\, n)(a_1\, n-1)$$

which since $(n-1\, n) \in S$, and the other two terms are in G by induction hypothesis, it means that $(a_1\, n) \in G$. And Since any cycle can be broken down into the aforementioned form (where if we have a cycle, we can move k to the back, since its the same cycle that represents it), any cycle can be broken down in this fashion, and thus, we completed the proof

As a bonus, if you want to represent such a group:

$$\langle \sigma_i | \sigma_i^2 = 1\,, \sigma_i\sigma j = \sigma_j\sigma i \text{ for } |i-j| > 1\,, (\sigma_i, \sigma_{i+1})^3 = 1 \rangle$$

Though this is not necessary to know, but it can be good to know if you want to show something to be isomorphic to the symmetric group (since if something is isomorphic, it has the same relations).

https://en.wikipedia.org/wiki/Symmetric_group#Generators_and_relations.

There is a way to prove these once we introduce either quotient groups or conjugacy classes (in the group-action section). Thus, we will not prove these here for the nicest way to prove them is once we have those extra tools.

Exercise 1.3.1

1. exercise 7, 16, simply to know how to solve a concrete problem.
2. exercise ,17,18.
3. Do 10 to see that you can find all symmetries
4. Take $(1, i)$ for $2 \leq i \leq n$, that is, the set where you fix one element, then the 2nd position is all other elements.
5. This one is probably the most useful theoretically. You can generate a symmetric group given only 2 cycles!! Take any n-cycles from S_n, and a 2-cycle of adjacent elements in the n-cycle!

1.4 Homomorphisms and Isomorphisms

When comparing D_4 and Q_8 in example 1.2.31, we resolved at looking at the Cayley tables to distinguish the two. However, this becomes very tedious to do for larger groups, and downright

impossible for infinite groups. In this section, we will make precise the notion of comparing groups.

What does it mean to compare groups? If we were comparing tuples, $(a, b) \neq (b, a)$, since the order matters. On the other hand, if we are comparing sets, then $\{a, b\} = \{b, a\}$ since the order does not matter, as long as the elements are the same. For groups, the star of the show is the binary operation. If two groups G and H shared *exactly* the same binary operation, they'd be identical in terms of the binary operation. We often encounter groups with different elements, but the binary operation acts identically in both groups.

Example 1.4.1: "Identical" groups

Let $G = \{0, 1, 2\}$ and $H = \{a, b, c\}$, and define $(G, +_G)$ and $(H, +_H)$ with binary operation's which have Cayley tables:

$+_G$	0	1	2
0	0	1	2
1	1	2	0
2	2	0	1

and

$+_H$	a	b	c
a	a	b	c
b	b	c	a
c	c	a	b

Then notice we can replace 0 with a, 1 with b, and 2 with c, and the two tables would be identical. In other words, the operation $+_H$ acts exactly the same as $+_G$.

It is sometimes restrictive that the two binary operations act *exactly* the same. sometimes that are similar, but the two groups share a different structure. The take-away is that when working with homomorphisms and isomorphissm, what we care about is the binary operation between two groups behave similarly.

1.4.1 Homomorphisms

Definition 1.4.2: Homomorphism

Let $(G, \bullet_G)$, and $(H, \bullet_H)$ be groups. A map $\psi : G \to H$ such that for all $x, y \in G$,

$$\psi(x \bullet_G y) = \psi(x) \bullet_H \psi(y)$$

is called a *homomorphism*

Remember that the left side is the domains operation, and the right side is the co-domains operation. A good way of remembering the rule of a homomorphism is that the resulting image $\varphi(G) = \{\varphi(g) \mid g \in G\}$ is also a group (this is proved in proposition 1.4.4). Another way remembering the rule of a homomorphism is that if there is a homomorphism, then in some way the binary operation must be *preserved*. It is not necessarily perfectly preserved: it's possible that only some of it is preserved. The following examples of homomorphisms may help in gaining an intuition

Example 1.4.3: Homomorphisms

1. Take the integers with the usual addition. Let e represent even integers; o represent odd integers. Then we know that adding even with even is even, even with odd is odd, odd with even is odd, and odd with odd is even:

$$e+e=e,\ o+o=e,\ o+e=e+o=o$$

On the other hand, if we take 1 and -1 and find all possible outcomes of multiplication, we get

$$1\cdot 1=1,\quad (-1)\cdot(-1)=1,\quad 1\cdot(-1)=(-1)\cdot 1=-1$$

Notice how 1 can represent even integers, and -1 represent odd. In this way, multiplication on -1 and 1 "captures" the idea of adding even and odd numbers.

Let's formalize this idea by making an explicit homomorphism. First, $\{-1,1\}$ is a group under usual multiplication $\cdot$. The element 1 is the identity since $1\cdot 1=1$, $-1\cdot 1=-1$. Furthermore -1 it's own inverse ($-1\cdot -1=1$). For associativity, most cases are essentially immediate to check, with the following case being the non-trivial case:

$$(-1\cdot -1)\cdot -1=1\cdot -1=-1\cdot 1=-1\cdot(-1\cdot -1)$$

Any case with 1 in the question be more easily checked since $a\cdot 1=1\cdot a=1$, making the cases of $1\cdot -1\cdot -1$, $-1\cdot 1\cdot -1$, $1\cdot 1\cdot -1$, and so forth easy to check. Thus, $\{-1,1\}$ is a group.

Next, let $\psi:\mathbb{Z}\to\{-1,1\}$ be a function such that

$$\psi(x)=\begin{cases}1 & x \text{ is even}\\ -1 & x \text{ is odd}\end{cases}$$

Then if e represents an arbitrary even number and o an arbitrary odd number:

$$\psi(e+e)=\psi(e)=1=1\cdot 1=\psi(e)\cdot\psi(e)$$
$$\psi(o+o)=\psi(o)=1=(-1)\cdot(-1)=\psi(o)\cdot\psi(o)$$
$$\psi(o+e)=\psi(e+o)=\psi(o)=-1=-1\cdot 1=1\cdot -1=\psi(e)\cdot\psi(o)=\psi(o)\cdot\psi(e)$$

Showing that ψ is indeed a homomorphism.

Generalizing the previous result, notice that our group $\{-1,1\}$ is homomorphic to $\mathbb{Z}/2\mathbb{Z}$ (remember that by default, if we say $\mathbb{Z}/2\mathbb{Z}$ is a group, we mean $(\mathbb{Z}/2\mathbb{Z},+)$ with modulo 2 addition). In particular

$$f:\{-1,1\}\to\mathbb{Z}/2\mathbb{Z}\qquad f(1)=0,\ f(-1)=1$$

Then one should verify that that f is indeed a homomorphism. It is further a bijection, meaning that every element of the group $\mathbb{Z}/2\mathbb{Z}$ represents exactly one element from $\{-1,1\}$, showing we can inter-change the two.

Now, take $\varphi : \mathbb{Z} \to \mathbb{Z}/n\mathbb{Z}$, $\varphi(x) = [x]$. Then φ is a homomorphism. Indeed:

$$\begin{aligned} \varphi(x+y) &= [x+y] \\ &= [x] + [y] && \text{property of } \mathbb{Z}/n\mathbb{Z} \\ &= \varphi(x) + \varphi(y) \end{aligned}$$

If $n = 2$, then this will be exactly the homomorphism we defined earlier.

2. If you have done any calculus or analysis, you might have seen before that:

$$\frac{d}{dx}(f+g) = \frac{d}{dx}(f) + \frac{d}{dx}(g) \qquad \int f + g\,dx = \int f, dx + \int g\,dx$$

so $\frac{d}{dx}$ and $\int$ both satisfy this condition! Are they homomorphisms? In fact, they are, with the group being all differentiable functions for the 1st one, and all integrable functions for the second one. These groups require more build-up within Calculus or Analysis, and so we will not cover these operation in more detail.[a].

3. For those with knowledge of the exponential function e^z (which we will write as exp), then there is a natural way of relating the addition and multiplication operation of $\mathbb{C}$ and $\mathbb{C}^\times$ (as well as $\mathbb{R}$ and $\mathbb{R}^\times$). The map $\exp : \mathbb{C} \to \mathbb{C}^\times$ is surjective group homomorphism. Restricting the domain and co-domain, we also get an injective (but not surjective) map $\exp : \mathbb{R} \to \mathbb{R}^\times$.

4. Verify that there is no bijective homomorphism from D_4 to Q_8. At the moment, this may be a tedious task, it will become easier to show later with some more properties of bijective homomorphisms.

5. Let $G_1 \times G_2$ be the direct product of two groups G_1 and G_2 as defined in example 1.1.5(4). The map $\pi_1 : G_1 \times G_2 \to G_1$ and $\pi_2 : G_1 \times G_2 \to G_2$ defined by

$$\pi_1((g_1, g_2)) = g_1 \qquad \pi_2((g_1, g_2)) = g_2$$

are homomorphisms.

6. Let G, H be any group. Then $\varphi : G \to H$ defined by $\varphi(g) = e_H$ where e_H is the identity of H is a homomorphism. This is called the *trivial homomorphism*.

7. (If you know about $\mathbb{C}$) Show that the subset $\{1, i, -1, -i\} \subseteq \mathbb{C}$ is a subgroup of $\mathbb{C}$ and that there is a bijective group homomorphism $\varphi : \mathbb{Z}/4\mathbb{Z} \to \{1, i, -1, -i\}$.

[a] However, $\frac{d}{dx}(fg)$ is not necessarily equal to $\left(\frac{d}{dx}(f)\right)\left(\frac{d}{dx}(g)\right)$ and $\int fg\,dx$ is not necessarily equal to $\left(\int f\,dx\right)\left(\int g\,dx\right)$. The first is studied in a course on Lie Groups and Lie Algebras, while the other is studied in a course in Measure Theory, in particular L^p spaces and Hölder's inequality

We will often simplify notation since lots of information is usually deduced from context. We will drop the binary operation and simply write $\varphi(ab) = \varphi(a)\varphi(b)$, given that it's clear that when we write ab the binary operation happens in the domain, and that when we werite $\varphi(a)\varphi(b)$ the binary operation happens in the codomain.

One more interpretation of a homomorphism that is a little more abstract but is enlightening in it's own way is that a homomorphism f is a function that "commutes" with the binary operation: If $*$ represent any binary operation (of any group, not just one group), then f is a homomorphism if and

only if

$$f \circ * = * \circ f$$

Concretely, if we let $*$ for a group G be represented as $*_G$ and $*$ for a group H be represented as $*_H$, then

$$f \circ *_G = *_H \circ (f, f)$$

or, if written in terms of elements and with the standard notation for binary operation:

$$f(x *_G y) = f(x) *_H f(y)$$

. This idea can be captured in a diagram like so:

$$\begin{array}{ccc} G \times G & \xrightarrow{\varphi \times \varphi} & H \times H \\ {\scriptstyle *_G(a,b)}\downarrow & & \downarrow{\scriptstyle *_H(\varphi(a),\varphi(b))} \\ G & \xrightarrow[\varphi(ab)]{} & H \end{array}$$

which can be read as "start at $G \times G$, then either go down then right, or go right then down, and both paths should give the same result", i.e. $\varphi(ab) = \varphi(a)\varphi(b)$.

Now that homomorphisms are defined, you might ask yourself "given two groups G, and H, how do I know there is a homomorphism between them?" There is always a trivial answer to this, the homomorphism sending everything to the identity always exist [19]. This is called the *trivial homomorphism* (you should check that it's indeed a homomorphism):

$$\varphi : G \to \{e\} \qquad \varphi(g) = e$$

So the better question would be "How can I find the non-trivial homeomorphisms between these two groups?" This in some cases can be a very difficult question. If we just look at them as set-functions from G to H, then if there are n objects in one category and m in the other, there are minimum n^m possible functions! That's a ton to check. We can deduce properties of homomorphisms which will let us diminish that number:

Proposition 1.4.4: Properties of Homomorphisms

Let G, H be groups and φ be a homomorphism. Then:

1. $\varphi(1_G) = 1_H$
2. $\varphi(g^{-1}) = \varphi(g)^{-1}$
3. $\varphi(g^n) = \varphi(g)^n$
4. the *kernel* $\ker \varphi = \{g \in G \mid \varphi(g) = 1_H\}$ is a subgroup of G (named again in definition 2.2.1)
5. the *image* $\mathrm{Im}(\varphi) = \varphi(G) = \{\varphi(g) \mid g \in G\}$ is a subgroup of H.
6. if $\psi : H \to K$ is also a homomorphism, then $\psi \circ \varphi : G \to K$ is a homomorphism, i.e., the composition of homomorphisms is a homomorphism.

[19] Elaborated in proposition 1.4.5

***Proof*:**

1. $\varphi(1_G) = \varphi(1_G 1_G) = \varphi(1_G)\varphi(1_G)$, so $\varphi(1_G) = \varphi(1_G)\varphi(1_G)$. Then by proposition 1.1.17
$$\varphi(1_G)\varphi(1_G)^{-1} = \varphi(1_G)\varphi(1_G)\varphi(1_G)^{-1}$$
the left hand side becomes 1_H, and the right hand side becomes $\varphi(1_G)1_H = \varphi(1_G)$, giving us
$$\varphi(1_G) = 1_H$$
2. By (1), $\varphi(g)\varphi(g^{-1}) = \varphi(gg^{-1}) = \varphi(1_G) = 1_H$. Multiplying on the left by $\varphi(g)^{-1}$ gives $\varphi(g^{-1}) = \varphi(g)^{-1}$.
3. For $n \geq 0$ we induct on n. The case $n = 0$ is (1), and $\varphi(g^{n+1}) = \varphi(g^n g) = \varphi(g^n)\varphi(g) = \varphi(g)^n\varphi(g) = \varphi(g)^{n+1}$. For $n < 0$, g^n is the inverse of g^{-n}, so (2) and the case $-n > 0$ give $\varphi(g^n) = \varphi(g^{-n})^{-1} = (\varphi(g)^{-n})^{-1} = \varphi(g)^n$.
4. $1_G \in \ker\varphi$ by (1). If $x, y \in \ker\varphi$, then $\varphi(xy) = \varphi(x)\varphi(y) = 1_H$ and $\varphi(x^{-1}) = \varphi(x)^{-1} = 1_H$ by (2). So $\ker\varphi$ contains 1_G and is closed under products and inverses, and associativity holds because it holds in G. Hence $\ker\varphi$ is a subgroup of G (definition 1.1.7).
5. $1_H = \varphi(1_G) \in \varphi(G)$ by (1). For $x, y \in G$, both $\varphi(x)\varphi(y) = \varphi(xy)$ and $\varphi(x)^{-1} = \varphi(x^{-1})$ (by (2)) lie in $\varphi(G)$, and associativity holds because it holds in H. Hence $\varphi(G)$ is a subgroup of H (definition 1.1.7).
6. For $x, y \in G$, $(\psi \circ \varphi)(xy) = \psi(\varphi(x)\varphi(y)) = \psi(\varphi(x))\psi(\varphi(y)) = (\psi \circ \varphi)(x)(\psi \circ \varphi)(y)$.

These propositions can even help us deduce whether [non-trivial] homomorphisms exist. For example, is there a non-trivial homomorphism from $\mathbb{Z}/2\mathbb{Z}$ to $\mathbb{Z}$? Let's say $\varphi : \mathbb{Z}/2\mathbb{Z} \to \mathbb{Z}$ were such a map. By the above proposition we have $\varphi(0) = 0$. Let's say $\varphi(1) = n$. Then
$$0 = \varphi(0) = \varphi(1 + 1) = \varphi(1) + \varphi(1) = n + n$$
giving us $0 = n + n$, which re-arranging is $-n = n$. The only integer equal to its negative is 0, hence $n = 0$. This shows that there is no non-trivial map from $\mathbb{Z}/2\mathbb{Z}$ to $\mathbb{Z}$.

The particular structure of the group that is being preserved depends on the operation and the cardinality of the domain and co-domain. In general, to get an idea of what part of the group is being preserved, you will have to check by doing a couple of example.

Important examples

I will go over some homomorphisms to build a deeper understanding of the concept

The first one is deceptively boring: take $\varphi : G \to \{e\}$ such that $\varphi(g) = e$. The function φ is a homomorphism, since for any $g, h \in G$
$$\varphi(g \cdot h) = e = e \cdot e = \varphi(g) \cdot \varphi(h)$$

This seemingly boring homomorphism has a very important property: for *any* group G, there *always* exists a *unique* homomorphism from G to $\{e\}$. This is also true for homomorphisms with $\{e\}$ as the domain! This fact is important enough to make a proposition:

Proposition 1.4.5: Homomorphism To/From Trivial Group

Let G be any group and I represent the trivial group. Then there always exists a unique homomorphism

$$\varphi : G \to I \qquad \psi : I \to G$$

to and from I

***Proof*:**
Let e_G be the identity of G and e_I the only element of I.

Homomorphisms $G \to I$. The constant map $\varphi(g) = e_I$ is a homomorphism by the computation above. Every function $G \to I$ takes the value e_I at each $g \in G$, so φ is the only function from G to I, and in particular the only homomorphism.

Homomorphisms $I \to G$. Define $\psi(e_I) = e_G$. Then $\psi(e_I e_I) = \psi(e_I) = e_G = e_G e_G = \psi(e_I)\psi(e_I)$, so ψ is a homomorphism. If $\psi' \colon I \to G$ is any homomorphism, then $\psi'(e_I) = e_G$ by proposition 1.4.4(1). A function on I is determined by its value at e_I, so $\psi' = \psi$, completing the proof.

So why is this property important? What can we do with it? In this case with groups, it is not used often [20]. what's more important is the concept that there *always* exists a homomorphism from any group, and that it is a *unique* homomorphism. These properties for the right homomorphisms will come back big-time when we study *quotient groups* (chapter 3): For *every* homomorphism there *always* exists a *unique* group (called the quotient group) which will "represent" the homomorphism.

Thus, we will give a name to groups with this property:

Definition 1.4.6: Initial And Final Groups


Let G be a group.

1. If for every group H there exists a unique homomorphism $\varphi : G \to H$, then we say that G is an *initial group* (or *initial object*)
2. If for every group H there exists a unique homomorphism $\varphi : H \to G$, then we say that G is a *final group* (or *final object*)
3. A final group is also called a *terminal group* (or *terminal object*), and a group that is both initial and final is called a *zero object*

The reason for this vocabulary is clearer if you think of a graph where the edges are homomorphisms

[20] It is used in the context of Category theory, where $\{e\}$ is both the initial and final group in the category of **Group**, making it an intuitive first step towards introducing universal properties. More on this in chapter 8

and the nodes are groups:



(1.4)

You can see how there is only one homomorphism from G to any other group, and M has only one homomorphism from every other group. Thus, G is initial, and M is final, that is, terminal.

1.4.7 Note An object *can* be both initial and final. The trivial group is one such example

For now, we do not have the tools to properly analyze this result. We will gain those in chapter 2, and revisit this idea in chapter 3.

Redefining Subgroup

Moving back towards things we can prove, I will present an important way of using homomorphisms to *define* subgroups, using the fact that subgroups as a similar structure to the original groups, and homomorphisms preserve some structure of a group. It might already be somewhat intuitive that if $H \leqslant G$, then H is pretty similar to G, especially that it must have the same group operation. With homomorphisms, we can formalize this idea:

Proposition 1.4.8: Defining Sub Group With Homomorphism

Let $(G, \cdot)$ and $(H, \bullet)$ be two groups, and $H \subseteq G$. Then H is a subgroup if and only if there exists a inclusion map $i : H \to G$ which is also a homomorphism

***Proof*:**
We will show that this definition is equivalent to definition 1.1.7, that is, that $(H, \cdot)$ is a group. Let $i : H \to G$ be an homomorphism which is also an inclusion map. All of these will come from proposition 1.4.4.

1. $(e_G = e_H)$ We need to how that H has the same identity. This comes for free with proposition 1.4.4
2. (inverse) We need to show that for any $a \in (H, \cdot)$, then there is a $b \in (H, \cdot)$ such that $ab = ba = e_G$. Since $i(a^{-1}) = a^{-1}$, then a^{-1} is a candidate. Indeed, since

$$i(e_H) = i(aa^{-1}) = i(a)i(a^{-1}) = i(a)i(a)^{-1} = aa^{-1} = e_G$$

   then a^{-1} will indeed be our desired inverse
3. (associativity) Similarly to how we have down the other two, but the proof is a little more tedious to carry out. One can do this to try proving associativity at least once in their career.

This is probably one of my favourite proposition using homomorphisms: really showing how homomorphism captures the idea that an algebraic structure is preserved by defining subgroups with an inclusion map that is also a homomorphism.

Collection of Homomorphisms

Next, we will address a little more complicated object. We might ask ourselves in what other way can we use homomorphisms to study groups? If a homomorphism preserves group structure, what possible homomorphisms can we have between a group and itself? What would that give us? Let's first label the set of all such homomorphisms:

Definition 1.4.9: Set of Endomorphisms

1. Given a group G, an endomorphism is a homomorphism from an object to itself: $\varphi : G \to G$.
2. Let $\text{End}(G) := \{\varphi : G \to G \mid \forall a, b \in G,\ \varphi(ab) = \varphi(a)\varphi(b)\}$ represent the set of all endomorphisms on G

The parity map $\psi\colon \mathbb{Z} \to \{-1, 1\}$ of example 1.4.3 is not an element of $\text{End}(\mathbb{Z})$. Its codomain is a different group, and read as a map $\mathbb{Z} \to \mathbb{Z}$ it sends 0 to 1, so it does not preserve addition (proposition 1.4.4(1)). The doubling map $x \mapsto 2x$ is an element of $\text{End}(\mathbb{Z})$, and its image is the set $2\mathbb{Z}$ of even integers, which is also the set of integers that ψ sends to 1. Being the image of a homomorphism, $2\mathbb{Z}$ is a *subgroup* of $\mathbb{Z}$ (proposition 1.4.4(5)).

If we can figure out some structure on $\text{End}(G)$, we can start getting a good idea on what are all sub-structures in G. More excitingly, if $\text{End}(G)$ can be proven to be a group (with composition, $\circ$, as the operation), then we can use all the technics of group theory to study it. However, this turns out not to be the case. The problem comes when trying to prove the existence of an inverse, which does not necessarily exist (try proving it's a group!).

So you might ask if there is still a way to make $\text{End}(G)$ into a group. Perhaps with a nice operation, we can define a [non-trivial] group structure? The one that is usually first attempted is defining addition *pointwise*, that is

$$f, g \in \text{End}(G) \qquad f + g \equiv (f + g)(x) = f(x) + g(x)$$

Where $\equiv$ means we are showing how the ne function "$f + g$" is defined by how it processes every element. With the operation defined, to check that $f + g$ is in $\text{End}(G)$, we need to check if it's a homomorphism, that is

$$(f + g)(x + y) = (f + g)(x) + (f + g)(y)$$

and going through the computation:

$$\begin{aligned}(f + g)(x + y) &= f(x + y) + g(x + y)\\ &= f(x) + f(y) + g(x) + g(y)\end{aligned}$$

and here is were we get stuck, since G is not necessarily commutative.

However, if G is commutative, then $f(y)$ and $g(x)$ commute and the computation continues:

$$\begin{aligned} &= f(x) + f(y) + g(x) + g(y) \\ &= f(x) + g(x) + f(y) + g(y) \\ &= (f+g)(x) + (f+g)(y) \end{aligned}$$

showing that $(f+g)$ is indeed a homomorphism!! Thus, $f+g$ is a well-defined operation. From here, you can check the axioms of a group to check that $\mathrm{End}(G)$ is indeed a group. It's even an abelian group! This is an example of how being commutativity changes how a group effects.

1.4.10 Remark In fact, more is true. If the domain of the functions are arbitrary sets, then $\mathrm{Hom}(A, G)$ is *still* an abliean group! This fact will be very useful to us much further don the line, in Parts II and III, and in *Core Representation Theory* [22].

Dihedral Groups As Groups Of Rotations

The dihedral group D_n of definition 1.2.28 consists of symmetries of a regular n-gon in the plane, and it is also isomorphic to a subgroup of rotations-reflections of 3-dimensional space. A reflection of the polygon is realized in space by turning the polygon over, a rotation by π about an axis in its plane. Let $n \geq 3$ and $\theta = 2\pi/n$, and let

$$R = \begin{pmatrix} \cos\theta & -\sin\theta & 0 \\ \sin\theta & \cos\theta & 0 \\ 0 & 0 & 1 \end{pmatrix} \qquad S = \begin{pmatrix} 1 & 0 & 0 \\ 0 & -1 & 0 \\ 0 & 0 & -1 \end{pmatrix}$$

be the rotation by θ about the z-axis and the rotation by π about the x-axis. Both satisfy $M^tM = MM^t = I$, by $\cos^2\theta + \sin^2\theta = 1$, and both have determinant 1, so they lie in $SO_3(\mathbb{R})$ (definition 1.2.36).

Proposition 1.4.11: D_n Embeds In $SO_3(\mathbb{R})$

Let $n \geq 3$, and let $r, s \in D_n$ be as in proposition 1.2.29. Then $\rho(s^k r^i) = S^k R^i$, for $k \in \{0, 1\}$ and $0 \leq i \leq n-1$, defines an injective homomorphism $\rho\colon D_n \to SO_3(\mathbb{R})$.

***Proof*:**
By the angle addition formulas, R^i is the rotation by $i\theta$ about the z-axis, so $R^n = I$ and $R^i \neq I$ for $0 < i < n$. Also $S^2 = I$, and multiplying out gives $SRS = R^{-1}$, hence $SR^iS = (SRS)^i = R^{-i}$ and $R^iS = SR^{-i}$ for every integer i. By proposition 1.2.29(4), ρ is defined on all of D_n. Since $s^2 = 1$, $r^n = 1$, $S^2 = I$ and $R^n = I$, the formula $\rho(s^a r^b) = S^a R^b$ holds for all integers a and b.

Homomorphism. Let $g = s^k r^i$ and $h = s^l r^j$ with $l \in \{0, 1\}$. By proposition 1.2.29(6), $r^i s^l = s^l r^{(-1)^l i}$, so $gh = s^{k+l} r^{(-1)^l i + j}$. In the same way, $R^iS = SR^{-i}$ gives

$$\rho(g)\rho(h) = S^k R^i S^l R^j = S^{k+l} R^{(-1)^l i + j} = \rho(gh)$$

Injectivity. Every R^i fixes the vector $e_3 = (0, 0, 1)^t$, while $SR^ie_3 = Se_3 = -e_3$, so no R^i equals

any SR^j. If $R^i = R^j$ or $SR^i = SR^j$ with $0 \leq i \leq j \leq n-1$, then $R^{j-i} = I$, so $i = j$. Hence the $2n$ matrices $S^k R^i$ are distinct, and ρ is injective, as claimed.

1.4.2 Isomorphisms

While homomorphisms preserve some algebraic structure, isomorphisms preserve the *entire* algebraic structure. An isomorphism can be thought of as the generalization of the concept of equality: If two groups are isomorphic, they are identical (as groups). They will only differ in the symbols which are used in representing them. The idea of an isomorphism extends far beyond group theory. Here's a fun linguistic example: if I say

one, two, three, four, five

or

un, deux, trois, quatre, cinq

Then both are capturing the idea of $1, 2, 3, 4, 5$, except in one I'm writing it in English, and in the other in French. Those two sentences ostensibly capture the same [numerical] ideas, but with different symbols

When trying to capture this idea in groups, we have to consider what it means for two group to be identical. First, the two groups would need to be of the same size, if not we cannot say they are the same. Therefore, the homomorphism must also be bijective. Next, all the relation between the two groups need to be the same. The parity map of example 1.4.3 preserves the operation but is not injective, since it sends every even integer to 1.

Definition 1.4.12: Isomorphism

The map $\psi : G \to H$ is called an *isomorphism* and G and H are said to be *isomorphic* or of the same *isomorphism* type, written $G \cong H$ if

1. ψ is a homomorphism
2. ψ is a bijection

1.4.13 Note Definition 1.4.12 defines an isomorphism as a bijective homomorphism. In a more categorical framework one would instead ask for a homomorphism $\varphi\colon H \to G$ with $\varphi \circ \psi = \mathrm{id}_G$ and $\psi \circ \varphi = \mathrm{id}_H$. For groups the two definitions agree. Such a φ is an inverse function of ψ, so ψ is a bijection. Conversely, if ψ is a bijective homomorphism, then its inverse function ψ^{-1} is a homomorphism, since $\psi(\psi^{-1}(x)\psi^{-1}(y)) = xy$ for $x, y \in H$, that is, $\psi^{-1}(xy) = \psi^{-1}(x)\psi^{-1}(y)$.[a]

[a] The analogous statement fails in topology, where a continuous bijection need not have a continuous inverse: the identity map from a two-point set with the discrete topology to the same set with the indiscrete topology is continuous, and its inverse is not.

When two groups are isomorphic, it means they only differ by the symbols we choose to use, they are in practice identical. The trivial isomorphism is the identity map $\mathrm{id} : G \to G$. We can also form an

equivalence class of isomorphic groups: take $\mathcal{G}$ to the set of groups and let the equivalence relation be isomorphisms.

Example 1.4.14: Isomorphism Examples

Let V_4 (*Vierergruppe*, meaning 4-group, sometimes called Klein 4-group), is the group that represents the symmetries of a [non-square] rectangle. You can define it as

$$V_4 = \langle a, b | a^2 = b^2 = (ab)^2 = e \rangle$$

Show that:

$$V_4 \cong \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z}$$

Here $\mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z}$ carries the componentwise operation of the direct product in example 1.1.5.

A less obvious example of a group isomorphism is $\psi : \mathbb{R} \to \mathbb{R}^+$, $\exp(x) = e^x$. e^x is invertible, and thus bijective, and $e^{x+y} = e^x e^y$, preserving group structure.

Proposition 1.4.15: Properties Of Isomorphisms

Let $f\colon G \to H$ and $g\colon H \to K$ be homomorphisms.

1. If f is an isomorphism, then its inverse function $f^{-1}\colon H \to G$ is an isomorphism.
2. If f and g are isomorphisms, then $g \circ f$ is an isomorphism.
3. If $g \circ f$ and f are isomorphisms, then g is an isomorphism.
4. If $g \circ f$ and g are isomorphisms, then f is an isomorphism.

***Proof*:**

1. The inverse function f^{-1} is a bijection. For $x, y \in H$,
$$f(f^{-1}(x)f^{-1}(y)) = f(f^{-1}(x))f(f^{-1}(y)) = xy$$
and applying f^{-1} gives $f^{-1}(x)f^{-1}(y) = f^{-1}(xy)$. So f^{-1} is a homomorphism.
2. The composite $g \circ f$ is a homomorphism by proposition 1.4.4(6), and a composite of bijections is a bijection.
3. By (1), f^{-1} is an isomorphism, so $g = (g \circ f) \circ f^{-1}$ is an isomorphism by (2).
4. By (1), g^{-1} is an isomorphism, so $f = g^{-1} \circ (g \circ f)$ is an isomorphism by (2), completing the proof.

An interesting exercise to show is if A and B are sets of the same cardinality, and S_A and S_B are two symmetric groups, then $S_A \cong S_B$. A bijection $f\colon A \to B$ relabels the elements, and $\sigma \mapsto f \circ \sigma \circ f^{-1}$ is the isomorphism.

Going back for a moment to when we tried to define a group $(\mathrm{End}(G), \circ)$, the fatal flaw was that not all homomorphisms have inverses. However, isomorphisms can be reversed: if $\varphi : G \to H$ is an isomorphism, then its inverse function $\varphi^{-1}\colon H \to G$ is an isomorphism (proposition 1.4.15), with

$\varphi^{-1} \circ \varphi = \mathrm{id}_G$ and $\varphi \circ \varphi^{-1} = \mathrm{id}_H$. In particular, if $\varphi : G \to G$ is an isomorphism, then φ^{-1} is an inverse of φ for composition, and the isomorphisms from G to itself form a group.

Definition 1.4.16: Automorphism

1. if $\varphi : G \to G$ is an isomorphism from a group to itself, then φ is called an ***automorphism***
2. Let $\mathrm{Aut}(G) := \{\varphi : G \to G \mid \varphi \text{ is an automorphism}\}$ be the collection of all automorphisms of G

Proposition 1.4.17: $\mathrm{Aut}(G)$ is a Group

Let G be a group and $\mathrm{Aut}(G)$ be the collection of automorphisms. Then $(\mathrm{Aut}(G), \circ)$ forms a group

***Proof*:**
First, $\circ$ is a binary operation on $\mathrm{Aut}(G)$. If $\varphi, \psi \in \mathrm{Aut}(G)$, then $\varphi \circ \psi$ is a homomorphism by proposition 1.4.4(6), and it is a bijection because a composite of bijections is a bijection. So $\varphi \circ \psi \in \mathrm{Aut}(G)$ (definition 1.4.16), and the axioms of definition 1.1.3 hold:

1. (associativity) For $\varphi, \psi, \chi \in \mathrm{Aut}(G)$ and $x \in G$, both $((\varphi \circ \psi) \circ \chi)(x)$ and $(\varphi \circ (\psi \circ \chi))(x)$ equal $\varphi(\psi(\chi(x)))$, so $(\varphi \circ \psi) \circ \chi = \varphi \circ (\psi \circ \chi)$.
2. (identity) The identity map id_G is a bijective homomorphism, so $\mathrm{id}_G \in \mathrm{Aut}(G)$, and $\mathrm{id}_G \circ \varphi = \varphi \circ \mathrm{id}_G = \varphi$ for every $\varphi \in \mathrm{Aut}(G)$.
3. (inverses) Let $\varphi \in \mathrm{Aut}(G)$ and let $\varphi^{-1} \colon G \to G$ be its inverse function, which is a bijection. For $x, y \in G$ put $a = \varphi^{-1}(x)$ and $b = \varphi^{-1}(y)$. Then $\varphi(ab) = \varphi(a)\varphi(b) = xy$, so
$$\varphi^{-1}(xy) = ab = \varphi^{-1}(x)\varphi^{-1}(y)$$
and φ^{-1} is a homomorphism. Hence $\varphi^{-1} \in \mathrm{Aut}(G)$, and $\varphi \circ \varphi^{-1} = \varphi^{-1} \circ \varphi = \mathrm{id}_G$.

So $(\mathrm{Aut}(G), \circ)$ is a group, as claimed.

Example 1.4.18: Automorphisms
Simplest example are identity maps. Other examples come form Linear Algebra with bijective linear functions (since $\varphi(a)\varphi(b) = \varphi(ab)$ for a linear function, it *is* an example)

1.4.19 Foreshadowing The concept of automorphisms will not be limited to groups. Many algebraic and non-algebraic structures will have the concept of automorphism defined. Most excitingly, the set of automorphisms for *any* of these objects *always* forms a group! The automorphism groups of field extensions, for example, are the subject of Galois theory (chapter 20).

Exercise 1.4.1

1. In example 1.1.5(5) we showed that $(\mathbb{Z}, +)$ and $(\mathbb{Z}, +_2)$ have different identities and inverses. Show that they are in fact isomorphic. This means that they are not a good example of two different groups on the same set since algebraically, they are identical.
2. Show that $D_4 \ncong \mathbb{Z}/8\mathbb{Z}$. With this knowledge, conclude that we can define two different groups on the set of 8 elements, giving a proper example of two different groups structure on the same underlying set.
3. (Challenging) Try to come up with two different structure on the underlying set of $\mathbb{Z}$ (Hint: recall the structure of $\bigoplus_i^\infty (\mathbb{Z}/2\mathbb{Z})$ and show there is a bijection between $\mathbb{Z}$ and this set, so that you can define a group structure on $\mathbb{Z}$ relative to this bijection. Is this group isomorphic to $\mathbb{Z}$?)

In the following section, we will explore classifying all possible groups on n elements where n has small order (larger orders of n will come when we have more tools)

First Use of Isomorphisms

In mathematics, there's a whole set of theorems that we use to show that classes of mathematical objects, like groups, are isomorphic to each other or not. Such theorems are called *classification theorems*. As a simple example, we can classify all non-abelian groups of order 6, in particular:

1.4.20

any non-abelian group of order 6 is isomorphic to S_3

Holding the theorem to be true for now, we can conclude that $D_3 \cong S_3$, and $GL_2(\mathbb{F}_2) \cong S_3$ without needing to find an explicit map. Not all groups of order 6 are isomorphic to S_3, since $\mathbb{Z}/6\mathbb{Z}$ is abelian and S_3 is not. However, all abelian groups of order 6 are isomorphic to $\mathbb{Z}/6\mathbb{Z}$! Thus, any group of order 6 is isomorphic to either S_3 or $\mathbb{Z}/6\mathbb{Z}$. This classification is the case $p = 2$, $q = 3$ of theorem 4.9.1 (example 4.9.2).

In general, it is difficult, sometime unfeasible, to find an explicit isomorphism mapping. Here are some necessary, but not sufficient, conditions for isomorphisms:

Proposition 1.4.21: Isomorphism Conditions

Let $\psi : G \to H$ be an isomorphism. Then:

1. $|G| = |H|$
2. G is abelian if and only if H is abelian
3. for all $x \in G$, $|x| = |\psi(x)|$

***Proof*:**
By definition 1.4.12, ψ is a bijective homomorphism.

1. The bijection $\psi \colon G \to H$ shows that G and H have the same cardinality, so $|G| = |H|$.

2. Suppose G is abelian and let $h, h' \in H$. Since ψ is surjective, $h = \psi(x)$ and $h' = \psi(y)$ for some $x, y \in G$, and then

$$hh' = \psi(x)\psi(y) = \psi(xy) = \psi(yx) = \psi(y)\psi(x) = h'h$$

so H is abelian. Conversely, suppose H is abelian and let $x, y \in G$. Then $\psi(xy) = \psi(x)\psi(y) = \psi(y)\psi(x) = \psi(yx)$, and since ψ is injective, $xy = yx$. So G is abelian.

3. Let $x \in G$ and $n \in \mathbb{Z}$. By proposition 1.4.4(1) and (3), $\psi(1_G) = 1_H$ and $\psi(x^n) = \psi(x)^n$. Since ψ is injective, $x^n = 1_G$ holds exactly when $\psi(x^n) = \psi(1_G)$, that is exactly when $\psi(x)^n = 1_H$. So the positive integers n with $x^n = 1_G$ are the positive integers n with $\psi(x)^n = 1_H$. If there are none, then x and $\psi(x)$ both have infinite order, and otherwise the smallest such n is both $|x|$ and $|\psi(x)|$ (definition 1.2.8). Hence $|x| = |\psi(x)|$, completing the proof.

Example 1.4.22

This proposition shows that S_3 and $\mathbb{Z}/6\mathbb{Z}$ are not isomorphic, because one is abelian and the other is not. Additionally, $(\mathbb{R} - \{0\}, \times)$ and $(\mathbb{R}, +)$ are not isomorphic, because $-1 \in \mathbb{R}^\times$ has order 2, and no element in $(\mathbb{R}, +)$ has order 2

A homomorphism out of a group given by a presentation is determined by where the generators go, and any choice of images that satisfies the relations gives one. Free groups make this precise (theorem 3.2.3).

Example 1.4.23

1. Take D_n and it's presentation $\langle r, s | r^n = s^2 = 1, sr = r^{-1}s \rangle$. Now take $n = mk$, $k \geq 3$ and consider d_{2k}. Then

$$\psi : d_n \to d_{2k} \qquad \text{by} \qquad \psi(r) = r_1, \text{ and } \psi(s) = s_1$$

is a homomorphism. In other words, the operation between Dihedral groups which are "multiples" are the same (think of a triangle and hexagon. two hexagon rotations is 2 triangle rotation, angle wise).

2. $D_3 = S_3$: $D_3 \subseteq S_3$ (definition 1.2.28), D_3 has order 6 (proposition 1.2.30), and so does S_3.

Proposition 1.4.24: Isomorphism properties

Let $\psi\colon G \to H$ be a homomorphism and $\Psi\colon G \to H$ an isomorphism.

1. $\psi(1_G) = 1_H$
2. $\psi(x^n) = \psi(x)^n$ for all $x \in G$ and $n \in \mathbb{Z}$
3. $|\Psi(x)| = |x|$ for all $x \in G$, so G and H have the same number of elements of order n for each $n \in \mathbb{Z}^+$. If $G \neq 1$, the statement $|\psi(x)| = |x|$ fails for the trivial homomorphism $G \to \{1\}$, which sends every element to 1.
4. G is abelian if and only if H is abelian
5. If S generates G (definition 1.3.1) and $\psi'\colon G \to H$ is a homomorphism with $\psi'(s) = \psi(s)$ for every $s \in S$, then $\psi' = \psi$. That is, a homomorphism is determined by its values on a set of generators.

***Proof*:**

1. This is proposition 1.4.4(1).
2. This is proposition 1.4.4(3).
3. By proposition 1.4.21(3), $|\Psi(x)| = |x|$ for every $x \in G$. So Ψ maps the set of elements of G of order n injectively into the set of elements of H of order n, and onto it, since an element $y \in H$ of order n is $\Psi(x)$ for some $x \in G$, and then $|x| = |y| = n$. Hence the two sets have the same number of elements. If $G \neq 1$, choose $x \neq 1_G$. The trivial homomorphism sends x to 1, which has order 1, while $|x| \neq 1$.
4. This is proposition 1.4.21(2).
5. Let $g \in G$. By definition 1.3.1, $g = s_1^{\epsilon_1} \cdots s_m^{\epsilon_m}$ for some $s_i \in S$ and $\epsilon_i \in \{1, -1\}$, where $m = 0$ gives $g = 1_G$. Since ψ and ψ' are homomorphisms, (2) gives

$$\psi'(g) = \psi'(s_1)^{\epsilon_1} \cdots \psi'(s_m)^{\epsilon_m} = \psi(s_1)^{\epsilon_1} \cdots \psi(s_m)^{\epsilon_m} = \psi(g)$$

so $\psi' = \psi$, completing the proof.

The last point of proposition 1.4.24 is used repeatedly to construct homomorphisms and isomorphisms, for instance between groups and subgroups of S_n once group actions are available.

Example 1.4.25

Prove that the subgroup of $SL_2(\mathbb{F}_3)$ generated by $A = \begin{pmatrix} 0 & -1 \\ 1 & 0 \end{pmatrix}$ and $B = \begin{pmatrix} 1 & 1 \\ 1 & -1 \end{pmatrix}$ is isomorphic to the quaternion group Q_8 of section 1.2.4.

***Proof*:**
Entries are read modulo 3. Both matrices have determinant 1, so they lie in $SL_2(\mathbb{F}_3)$. Direct computation gives

$$A^2 = B^2 = -I \qquad AB = \begin{pmatrix} -1 & 1 \\ 1 & 1 \end{pmatrix} \qquad BA = \begin{pmatrix} 1 & -1 \\ -1 & -1 \end{pmatrix} = -AB$$

Since $-I$ commutes with every matrix, these give $(AB)^2 = A(BA)B = -A^2B^2 = -I$, $A(AB) = A^2B = -B$, $(AB)A = A(BA) = -A^2B = B$, $B(AB) = (BA)B = -AB^2 = A$ and $(AB)B = AB^2 = -A$. With A, B, AB and $-I$ in the roles of i, j, k and -1, these are exactly the relations of section 1.2.4: $i^2 = j^2 = k^2 = -1$, $ij = k$, $ji = -k$, $ik = -j$, $ki = j$, $jk = i$ and $kj = -i$.

Define $\varphi\colon Q_8 \to SL_2(\mathbb{F}_3)$ by $\varphi(\pm 1) = \pm I$, $\varphi(\pm i) = \pm A$, $\varphi(\pm j) = \pm B$ and $\varphi(\pm k) = \pm AB$. Every element of Q_8 is εu with $\varepsilon \in \{1, -1\}$ and $u \in \{1, i, j, k\}$, and $\varphi(\varepsilon u) = \varepsilon\varphi(u)$. In Q_8 (section 1.2.4) the element -1 commutes with everything and $(-1)^2 = 1$, so $(\varepsilon u)(\varepsilon' u') = \varepsilon\varepsilon'(uu')$, and the relations give $uu' = \delta w$ with $\delta \in \{1, -1\}$ and $w \in \{1, i, j, k\}$. The previous paragraph shows that $\varphi(u)\varphi(u') = \delta\varphi(w)$ for the same δ and w, which is immediate when u or u' is 1. As $-I$ is central,

$$\varphi(\varepsilon u)\varphi(\varepsilon' u') = \varepsilon\varepsilon'\varphi(u)\varphi(u') = \varepsilon\varepsilon'\delta\varphi(w) = \varphi((\varepsilon u)(\varepsilon' u'))$$

so φ is a homomorphism. The top rows of $I, -I, A, -A, B, -B, AB, -AB$ are $(1, 0)$, $(2, 0)$, $(0, 2)$, $(0, 1)$, $(1, 1)$, $(2, 2)$, $(2, 1)$ and $(1, 2)$, which are distinct, so φ is injective.

Let H be the subgroup generated by A and B, the set of finite products of A, B and their inverses (definition 1.3.1). The image of φ is a subgroup of $SL_2(\mathbb{F}_3)$ (proposition 1.4.4(5)) containing A and B, so it contains H. Conversely, every element of the image is a product of copies of A and B, since $-I = A^2$ and $I = A^4$. So φ is a bijective homomorphism from Q_8 onto H, and $H \cong Q_8$, as claimed.

Prove that an isomorphism $\varphi\colon S_n \to S_n$ preserves parity: for every $\sigma \in S_n$, the permutations σ and $\varphi(\sigma)$ are both even or both odd (definition 1.2.21). A homomorphism need not preserve parity, since for $n \geq 2$ the trivial homomorphism $S_n \to S_n$ sends the odd permutation (1 2) to the even permutation id.

***Proof*:**
If $n = 1$, then $S_1 = \{\text{id}\}$ and there is nothing to prove, so let $n \geq 2$. By definition 1.2.21, it suffices to show that $\text{sgn}(\varphi(\sigma)) = \text{sgn}(\sigma)$ for every $\sigma \in S_n$.

The images under φ of all transpositions have one common sign. Indeed, for $g \in S_n$ and a transposition $(a\ b)$, proposition 1.2.27 gives $g(a\ b)g^{-1} = (g(a)\ g(b))$. Given two transpositions $(a\ b)$ and $(c\ d)$, choose $g \in S_n$ with $g(a) = c$ and $g(b) = d$, which is possible because $a \neq b$ and $c \neq d$. Then $(c\ d) = g(a\ b)g^{-1}$, so

$$\varphi((c\ d)) = \varphi(g)\varphi((a\ b))\varphi(g)^{-1}$$

and theorem 1.2.20(2) gives $\text{sgn}(\varphi((c\ d))) = \text{sgn}(\varphi((a\ b)))$, because the signs are the commuting numbers ± 1.

If this common sign were 1, then every $\varphi(\sigma)$ would have sign 1, since σ is a product of transpositions (corollary 1.2.19) and $\varphi(\sigma)$ is the product of their images. This is impossible, because φ is surjective and $\text{sgn}((1\ 2)) = -1$ (theorem 1.2.20(3)). Hence $\text{sgn}(\varphi(\tau)) = -1$ for every transposition τ. Writing $\sigma = \tau_1 \cdots \tau_k$ with transpositions τ_i, theorem 1.2.20 gives $\text{sgn}(\varphi(\sigma)) = \text{sgn}(\varphi(\tau_1)) \cdots \text{sgn}(\varphi(\tau_k)) = (-1)^k = \text{sgn}(\sigma)$, as claimed.

Exercise 1.4.2

1. Find all non-trivial homomorphisms between D_4 and Q_8
2. Let G be an arbitrary group.
    1. Prove that there always exists a homomorphism from $\mathbb{Z}$ to G
    2. Why does this not contradict the fact that I is the only initial group?
3. (If you know some complex analysis) Let S^1 be the circle in the complex plane. show that $f : \mathbb{R} \to S^1$, $f(x) = e^{2\pi ix}$ is a homomorphism.
4. Is there a non-trivial homomorphism from $\mathbb{Z}/n\mathbb{Z}$ to $\mathbb{Z}$?
5. Let $\varphi : G \to H$ be a homomorphism. Show that $\varphi(a + b + c) = \varphi(a) + \varphi(b) + \varphi(c)$. More generally, if $g_1, g_2, ..., g_n \in G$, then $\varphi(g_1 + g_2 + \cdots + g_n) = \varphi(g_1) + \varphi(g_2) + \cdots + \varphi(g_n)$. [hint: recall associativity and induction]
6. Does there exist a surjective homomorphism $\varphi : G \to H$ where G is abelian and H is not?
7. Let S where $|S| = 3$ be a set and let $\text{Sym}(S)$ all bijections on S (i.e. the symmetric group). Show that there exists a homomorphism $\sigma : D_3 \to \text{Sym}(S)$. (it is in fact an isomorphism) (This is a particular example of a *group action*, the subject of chapter 4.)
8. Define the map $\varphi_g : G \to G$, $\varphi(x) = gx$. Is this map in general a homomorphism? If not in general, in a particular case?
9. Define the map $\psi_g : G \to G$, $\psi(x) = gxg^{-1}$. Is this map in general a homomorphism? If not in general, in a particular case?

10. Let $\varphi : G \to H$ be a homomorphism and $\ker(\varphi) = \{e_G\}$. Prove that φ is injective.
11. Show that there exist an injective homomorphism $\varphi_n : D_n \hookrightarrow O_2(\mathbb{R})$.


1.5 Symmetry and Transformations: A Prelude to Group Actions

We have so far studied groups as abstract algebraic objects, defined by axioms and explored through subgroups, homomorphisms . But groups did not arise historically from axioms. They arose from *symmetry*. Évariste Galois studied permutations of roots of polynomials. Arthur Cayley studied transformations of space. In every early appearance of what we now call a "group," the central idea was the same: a collection of *reversible transformations* of some object, where transformations can be composed and undone.

In this section, we pause the axiomatic development to revisit this original intuition. The goal is simple: to see that groups *act on things*, and that this perspective is the natural way to think about them. We will make all of this precise in Chapter 4. For now, we build intuition.


The Symmetries of a Square

Recall from Section 1.2.3 that the dihedral group D_4 consists of the 8 symmetries of a square: four rotations and four reflections. Let us label the corners $1, 2, 3, 4$:




Each symmetry of the square *moves the corners around*. A $90°$ clockwise rotation r sends each corner to the next one clockwise:

$$1 \longmapsto 2, \quad 2 \longmapsto 3, \quad 3 \longmapsto 4, \quad 4 \longmapsto 1.$$



Similarly, the reflection s across the vertical axis swaps the left and right columns:

$$1 \longmapsto 2, \quad 2 \longmapsto 1, \quad 3 \longmapsto 4, \quad 4 \longmapsto 3.$$




Each element of D_4 determines a specific way of rearranging the four corners, that is, a *bijection* from $\{1, 2, 3, 4\}$ to itself. We can compose these rearrangements: rotating by r twice gives the same result as rotating by r^2. In other words, the group D_4 is *acting* on the set $\{1, 2, 3, 4\}$.

Two observations are worth highlighting. First, every symmetry is *reversible*: if r rotates the square clockwise, then r^{-1} rotates it back. This is why we need a *group* (with inverses) rather than just a monoid. Second, the identity element $e \in D_4$ does nothing to the corners. It is the "trivial symmetry" that leaves everything in place.

Beyond the Square: Symmetry is Everywhere

The group D_4 does not only describe the symmetries of a geometric square. Consider the *cycle graph* C_4 on four vertices:



A *graph automorphism* is a bijection on the vertex set that preserves adjacency. One can verify that the automorphism group $\mathrm{Aut}(C_4)$ is precisely D_4: the same rotations and reflections that preserve the square also preserve which vertices are joined by an edge. The group D_4 captures an abstract *pattern of symmetry* that manifests in both geometry (the square) and combinatorics (the cycle graph). This is the key insight: a single group can describe the symmetries of *many different objects*.

Here are several more instances of this phenomenon, drawn from across mathematics. In each case, a group "acts" on a set by rearranging its elements in a structured, reversible way.

1. **Linear transformations.** The general linear group $GL_n(\mathbb{R})$ acts on $\mathbb{R}^n$: each invertible matrix A transforms a vector $\vec{x}$ to $A\vec{x}$. Composing two transformations corresponds to multiplying the matrices, and the identity matrix leaves every vector fixed. Rotations, reflections, scalings, and shears of n-dimensional space are *all* captured by this single action.

2. **Permutations.** The symmetric group S_n acts on $\{1, 2, \ldots, n\}$ by evaluation: each permutation σ sends i to $\sigma(i)$. This is, in a sense, the "most general" action: every rearrangement of n objects corresponds to some element of S_n. As we will see in Chapter 4, *every* group action can be viewed through the lens of permutations.

3. **The Rubik's Cube.** A standard 3×3 Rubik's Cube has six faces, each consisting of nine colored squares. The center square of each face is fixed (it defines the face's color), leaving $6 \times 8 = 48$ movable *facelets*. Each legal move (a quarter-turn or half-turn of a single face)

permutes these 48 facelets, and the set of all finite sequences of legal moves forms a group $\mathcal{R} \leq S_{48}$. This group is enormous:

$$|\mathcal{R}| \;=\; 43{,}252{,}003{,}274{,}489{,}856{,}000 \;\approx\; 4.3 \times 10^{19},$$

yet it is a *tiny* fraction of $|S_{48}| = 48! \approx 1.2 \times 10^{61}$. Not every conceivable rearrangement of the facelets can be reached by legal moves. The structure of the group $\mathcal{R}$ (its subgroups, generators, and quotients) is precisely what determines which configurations are reachable from a solved cube and which are not.

4. **Translations of polynomials.** Consider the set of all real polynomials. The additive group $(\mathbb{R}, +)$ acts on this set by *translation*: given $t \in \mathbb{R}$ and a polynomial f, define

$$(t \cdot f)(x) \;=\; f(x + t).$$

Translating by t and then by s is the same as translating by $t + s$, and translating by 0 changes nothing. This simple action connects algebra to analysis: Taylor's theorem, for instance, describes exactly how a polynomial changes under translation.

In every example above, three things are true:

1. Each element of the group "does something" to every element of the set: it rearranges, transforms, or moves things around.
2. The **identity element does nothing**: it leaves every element of the set exactly where it was.
3. The group operation is **compatible with composition**: performing one element's transformation followed by another's is the same as performing the transformation of their product.

These three observations are the soul of what we will call a *group action*. Chapter 4 makes them precise as a single homomorphism from the group into a symmetric group, and develops the theory around it. But the underlying philosophy is already clear:

> *A group is not just an abstract set with a binary operation.*
> *It is a collection of symmetries that act.*

Groups Acting on Themselves: A First Glimpse

The examples above involve a group acting on an "external" object: a square, a vector space, a set of facelets. But some of the best applications of group actions come from letting a group act *on its own elements*. There are two natural ways to do this. Given a group G and elements $g, a \in G$:

- Left multiplication: define $g \cdot a = ga$. Each element g "shuffles" the elements of G by multiplying on the left. This will lead us to *Cayley's Theorem*, which asserts that every group is isomorphic to a group of permutations.
- Conjugation: define $g \cdot a = gag^{-1}$. This action detects the internal structure of G: which elements "behave similarly" under the group operation, and how the center $Z(G)$ relates to the rest of the group. It will lead us to the *Class Equation* and, ultimately, to the celebrated *Sylow Theorems*, which describe how a finite group decomposes relative to its prime factors.

Both of these self-actions will be central to Chapter 4. The remarkable fact is that by studying how G transforms *itself*, we can deduce deep structural information about G that is invisible from the axioms alone.

1.6 Cayley Graphs

We have seen that each element g of a group can be thought of as a transformation: it "moves" every element a to ga. If we focus on a set of generators $\{s_1, s_2, \ldots, s_k\}$, then each generator defines a specific *step* that can be taken from any group element. Starting from the identity e and repeatedly taking these steps, we trace out the entire group.

This is precisely the idea behind a *Cayley graph* (Definition 1.6.1): we place a vertex at each element of G and draw a directed edge from a to $s_i a$ for each generator s_i. The resulting picture is a vivid record of the group's structure, and it is nothing other than a *visual record of the left-multiplication action* restricted to the generators. As we explore Cayley graphs, keep this action-based perspective in mind, it is the thread that connects the algebra of groups to the geometry of their visual representations:

Definition 1.6.1: Cayley Graph

Let G be a group and let S be a generating set of G. The *Cayley Graph* $\Gamma = \Gamma(G, S)$ is a colored directed graph constructed as follows:

1. Each element $g \in G$ is assigned a *vertex*: the vertex set $V(\Gamma)$ of Γ bijectivity corresponds with G
2. Each generator $s \in S$ is assigned a colour c_s
3. For any $g \in G$ and $s \in S$, the vertices corresponding to the elements g and gs are joined by a direct edges of colour c_s. Thus, the edge set $E(\Gamma)$ consists of pairs of the form (g, gs), with $s \in S$ providing the colour

some popular, but not necessary, conventions are: [21]

1. The set S is finite
2. $S = S^{-1} = \left\{s^{-1} \middle| s \in S\right\}$
3. $e \notin S$ (i.e., the identity is not in S)

Example 1.6.2: Cayley Graphs


1. Let $G = \mathbb{Z} = \langle 1 \rangle$. Then we can say that $S \cup S = \{1, -1\}$. This gives us the graph:

$$\cdots \quad -3 \longleftarrow -2 \longleftarrow -1 \longleftarrow 0 \longrightarrow 1 \longrightarrow 2 \longrightarrow 3 \quad \cdots$$


   Take a moment to try and see what the Cayley graph of $\mathbb{Z} \times \mathbb{Z}$ would be (the answer is given in a later example)

[21] These conventions are usually followed in *geometric group theory*

2. Let $G = S_3 = \langle a, b | a^2 = b^3 = 1, ab = b^2 a \rangle$. Then if b is represented by red edges and a is represented by green vertices, we get:




3. Let $G = \mathbb{Z}/4\mathbb{Z}$. Then the Cayley graph is:




4. Let $G = \mathbb{Z} \times \mathbb{Z}$. Then the Cayley graph is:

$$
\begin{array}{ccccccccc}
 & & & \vdots & & & & & \\
 & & (-2,2) & \longleftarrow & (-1,2) & \longleftarrow & (0,2) & \longrightarrow & (1,2) & \longrightarrow & (2,2) & & \\
 & & \uparrow & & \uparrow & & \uparrow & & \uparrow & & \uparrow & & \\
 & & (-2,1) & \longleftarrow & (-1,1) & \longleftarrow & (0,1) & \longrightarrow & (1,1) & \longrightarrow & (2,1) & & \\
 & & \uparrow & & \uparrow & & \uparrow & & \uparrow & & \uparrow & & \\
\cdots & & (-2,0) & \longleftarrow & (-1,0) & \longleftarrow & (0,0) & \longrightarrow & (1,0) & \longrightarrow & (2,0) & & \cdots \\
 & & \downarrow & & \downarrow & & \downarrow & & \downarrow & & \downarrow & & \\
 & (-2,-1) & \longleftarrow & (-1,-1) & \longleftarrow & (0,-1) & \longrightarrow & (1,-1) & \longrightarrow & (2,-1) & & & \\
 & \downarrow & & \downarrow & & \downarrow & & \downarrow & & \downarrow & & & \\
 & (-2,-2) & \longleftarrow & (-1,-2) & \longleftarrow & (0,-2) & \longrightarrow & (1,-2) & \longrightarrow & (2,-2) & & & \\
 & & & \vdots & & & & & & & & &
\end{array}
$$

5. Let $G = \mathbb{Z} \times \mathbb{Z}/2\mathbb{Z}$ and $S = \{(1,0), (0,1)\}$, with red edges for $(1,0)$ and green edges for $(0,1)$. Then the Cayley graph is:



6. Let $G = D_\infty = \langle r, s \mid s^2 = 1,\ rs = sr^{-1} \rangle$ (i.e this is D_n but with no $r^n = 1$ relation) and let $S = \{r, s\}$, with red edges for r and green edges for s. Every element is r^n or $r^n s$ for some $n \in \mathbb{Z}$, and $sr = r^{-1}s$, so $r^n \cdot r = r^{n+1}$ while $r^n s \cdot r = r^{n-1}s$. Then the Cayley graph is:



Just by looking at the graphs, you might be able to see some interesting patterns. For example, by taking the direct product, we found it produces parallel graphs. We see in S_3 and $\mathbb{Z}/n\mathbb{Z}$ that arrow point *to* the identity represent the *order* of the element. Different Cayley graphs can also give different insights: the Cayley graph of $\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z}$ above consists of two parallel lines with every node connected to the one above it. The Cayley graph of D_∞ has the same shape, except that the red edges of the top line point the other way, a "twist" introduced to it[22].

In most of this textbook, Cayley graphs will not play a prominent role. They come back here and there to give a visual way of looking at new concepts introduced[23]. However, they are the foundation for an area of group theory called *geometric group theory*. For the study of geometric group theory, some knowledge of analysis is needed (ex. metrics). For those interested in such explorations, [72] is an introduction.

[22] Chapter 5 constructs D_∞ from $\mathbb{Z}$ and $\mathbb{Z}/2\mathbb{Z}$ as the semidirect product $\mathbb{Z} \rtimes \mathbb{Z}/2\mathbb{Z}$.
[23] For example, they will come back when working with free groups and semi-direct products

2

Sub Groups and Generating Groups

Now that we have studied some fundamental aspects of group theory and important examples, let's dive deeper in the mechanics used in analyzing and finding groups. The first way we will be studying group is by trying to take smaller groups from the larger group and seeing if we can find information through the pieces of the group.

We will start by trying to find subgroups that exist for *any* group G. These subgroups are sometimes called *natural subgroups*, since they always exist for a group, as though the axioms of the group "naturally" let these subgroups exist. We will then move on to constructing groups given some subset of a group, and show how the basic operations of $\cup$ and $\cap$ interact with groups. Finishing off our exploration of generating groups, we will define the concept of "most general group". It will turn out that the free groups can be thought of as the groups that "generate" all other possible groups. We will end this chapter by exploring a new way of visualizing the subgroups of finite groups through the use of a graph (in particular a lattice) that will become useful when trying to find how to construct larger groups.

2.1 Basic Definition and Properties

First, a reminder of what it means to take a smaller group from the same group:

Definition 2.1.1: Subgroup

Let G be a group with operation $*$. The subset H of G is a *subgroup* of G if H is a nonempty, closed under the restricted operation $*|_H$, that is, it is closed under products and inverse. We shall write $H \leqslant G$.

Recall that the binary operation $*|_H$ on H is a restriction of the binary operation $*$ on G. In particular, if $* : G \times G \to G$ is the binary operation on G, then we say we *restrict* the binary operation to H if we can define $*|_H : H \times H \to H$, where for any two elements $h_1, h_2 \in H$ $*|_H (h_1, h_2) = *(h_1, h_2)$. If $(H, *|_H)$ is a group, we say it's a subgroup of $(G, *)$. In this way, we say that H has "the same" binary operation as H. We will abuse notation and denote the binary operation of the subgroup $H \leqslant G$ as the same operation as the group G, that is, we will write $(G, \cdot)$ and $(H, \cdot)$ instead of $(G, \cdot)$ and $(H, \cdot|_H)$. If we have $H \leqslant G$ and $H \subsetneq G$, then we will denote this as $H < G$

Example 2.1.2: Sub Groups

1. If $1 \in G$ and $H = \{1\}$, $H \leqslant G$. H is called the *trivial subgroup*. Similarly, $G \leqslant G$ always.
2. $\mathbb{Z} \leqslant \mathbb{Q} \leqslant \mathbb{R}$ with the operation of addition.
3. $\mathbb{Z}^+ \not\leqslant \mathbb{Z}$ under addition. Can you prove it?
4. Take the set of all symmetries ($\{1, \sigma\} \subseteq D_4$) and all rotations ($\{1, r, r^2, r^3\} \subseteq D_4$). These are both subgroups.

The subgroup H inherits a lot of properties we have proven in section 1.1.1. For example, for any equation of elements in H, it is also an equation of elements in G, and so will have the same solution(s) or lack thereof. Furthermore, the identity will remain the same, since every group must have a unique identity, and similarly for inverses.

For computational purposes, here is a useful proposition that warps up the conditions of a subgroup to be able to more quickly identify whether a subset is or is not a subgroup:

Proposition 2.1.3: The Subgroup Criterion

A subset H of G is a subgroup if and only if

1. $H \neq \emptyset$
2. for all $x, y \in H$, $xy^{-1} \in H$

Furthermore, if H is finite, then it suffices to check that H is non-empty and closed under its operation.

***Proof*:**
Let $H \subseteq G$

($\Rightarrow$) Let $H \leqslant G$. Then $1 \in H$, so $H \neq \emptyset$. Take $x, y \in H$. If $y \in H$, then $y^{-1} \in H$. Since H is closed under its operation, then $xy^{-1} \in H$

($\Leftarrow$) Let $H \subseteq G$ and consider $(H, \cdot|_H)$.

(a) **(associativity)** Associativity comes for free since the binary operation on H is the same, so if $x, y, z \in H$, then $x(yz) = (xy)z$

(b) **(identity)** Since $H \neq \emptyset$, there must exist some $x \in H$. Then by the 2nd condition, $xx^{-1} = 1 \in H$, so $1 \in H$.

(c) **(inverse)** Let $x \in H$. Since $1 \in H$ then $1x^{-1} = x^{-1} \in H$.

(d) **(well-defined)** Let's make sure that if $x, y \in H$ then $xy \in H$ (making sure that the binary operation is still a function). By what we have just shown, $y^{-1} \in H$. Thus $x(y^{-1})^{-1} = xy \in H$ (where $(x^{-1})^{-1} = x$ was proved in proposition 1.1.15). Thus, $\cdot|_H$ is indeed a function

Thus, $H \leqslant G$

Now, let H be a finite group. Then for any $x \in H$, there can only be finitely many distinct elements $x_1, x_2, ..., x_n, ...$, meaning for some $a, b \in \mathbb{N}$, $x^a = x^b$ with $a < b$. This means that $x^{b-a} = 1$, and so for any $x \in H$, x has finite order. Thus, we get that $x^{-1} = x^{n-1}$, where $x^n = 1$. Thus, we automatically get H is a subgroup if H is closed under its binary operation

Exercise 2.1.1

1. Prove or disprove that the following are subgroups: $\mathbb{Q}^\times \leqslant \mathbb{R}$, $D_3 \leqslant D_4$
2. Let $H, K \leqslant G$. Is $H \cup K$ always a group? Prove or give a counter-example. If not, then identify what condition(s) is needed for $H \cup K$ to be a group.
3. Prove that G cannot have a subgroup H with $|H| = n - 1$, where $n = |G| > 2$.
4. Let $K \leqslant H$ and $H \leqslant G$. Prove that $K \leqslant G$

2.2 Examples of Subgroups

In this section, we will explore "natural" subgroups as well as subgroups that arise given any homomorphism

2.2.1 Kernel and Image

Given any homomorphism $\varphi : G \to H$, are there subsets that can be created using φ which will be subgroups of either G or H? Naturally, the image of a homomorphism is a subgroup of H ($\varphi(G) \subseteq H$), essentially by definition. We might ask ourselves if there exists some subgroup of G that we can construct using φ?

commented old text here:

For the first subgroup, consider the following set

$$\ker(\varphi) \subseteq G \qquad \ker(\varphi) = \{g \in G \mid \varphi(g) = 1\}$$

then $\ker(\varphi) \leqslant G$

Proof. We will use the subgroup criterion. Take $a, b \in \ker(\varphi)$. Then using properties of homomorphisms:

$$1 = \varphi(ab^{-1}) = \varphi(a)\varphi(b^{-1}) = \varphi(a)\varphi(b)^{-1}$$

and since $\varphi(a) = \varphi(b) = 1$, we get

$$\varphi(a)\varphi(b)^{-1} = 11^{-1} = 11 = 1$$

so $ab^{-1} \in \ker\varphi$

□

the set $\ker(\varphi)$ will thus be given a name:

Definition 2.2.1: Kernel

Let $\varphi : G \to H$ be a homomorphism. Then the set

$$\ker(\varphi) = \{g \in G \mid \varphi(g) = 1\}$$

is the *kernel* of φ

2.2.2 Question to Ponder Let's say $\varphi : G \to H$ and $\psi : G \to H$ are two homomorphisms with the same domain and codomain. If $\ker(\varphi) = \ker(\psi)$, does that imply $\varphi = \psi$?

As we have discussed earlier, $\varphi(G)$ is a group:

$$\varphi(G) \subseteq H, \quad \varphi(G) = \{h \in H \mid \varphi(g) = h \text{ for some } g \in G\}$$

For completeness of this section, we put the proof here:

Definition 2.2.3: Image

Let $\varphi : G \to H$ be a homomorphism. Then the set

$$\varphi(G) = \{h \in H \mid \varphi(g) = h \text{ for some } g \in G\}$$

or

$$\text{im}(\varphi) = \{h \in H \mid \varphi(g) = h \text{ for some } g \in G\}$$

is the *image* of G with φ.

Proof. We will use the subgroup criterion as well as proposition 1.4.4. Since $\varphi(e_G) = e_H$, we have that $\varphi(G)$ is non-empty.

Next, take $a, b \in \varphi(G)$, meaning there exists an $x, y \in G$ such that $\varphi(x) = a$ and $\varphi(y) = b$. Since $\varphi(y^{-1}) = \varphi(y)^{-1}$, we have

$$ab^{-1} = \varphi(x)\varphi(y)^{-1} = \varphi(xy^{-1}) \in \varphi(G)$$

thus, $ab^{-1} \in \varphi(G)$, meaning $\varphi(G)$ passes the subgroup criterion, as we sought to show □

Given that $\varphi(G) \subseteq H$, $\varphi(G)$ has structure of H. However, since $\varphi(G)$ also has some of it's structural information based on G, it would not be surprising if we can somehow characterize $\varphi(G)$ through G. The first isomorphism theorem of chapter 3 does this: $\varphi(G)$ is isomorphic to a quotient of G.

2.2.2 Center, Centralizers, and Normalizers

Given any group G, does there exist [non-trivial][1] subsets $H \subseteq G$ which will *always* be subgroups (i.e. $H \leqslant G$), regardless of the operation? Not all subsets will form subgroups. For example, take the set

$$T(G) = \{x \in G \mid x^n = 1, \text{ for some } n \in \mathbb{N}_{>0}\}$$

this set is called the *torsion subset* (i.e. the set of all element of finite order). If $T(G) \leqslant G$, then it must pass the subgroup criterion for all possible groups G. However, take

$$G = \langle x, y \mid x^2 = y^2 = 1 \rangle$$

both $x, y \in T(G)$. However, $xy^{-1} = xy \notin T(G)$ (note that $y^2 = 1 \Rightarrow y = y^{-1}$): the element $(xy)^n = xyxyxyxy\cdots$ will never equal 1, since there are no relations that permit the appropriate cancellation to occur. In particular, note that there is no relation for G which makes $xy = yx$ which would allow the values to commute and cancel. This is rather difficult to prove at this stage in the book. So $T(G)$ need not be a subgroup of G. If G is abelian, then $T(G)$ *is* a subgroup (exercise 2.2.1 (7)).

The question arises then if there are properties for which a subset will *always* be a subgroup for any group G regardless of the operation on G. These types of natural subgroups are in general quite hard to find, however they do exist. The rest of this section will be exploring examples of such subsets.

The first one we will explore is a great example of the power of commutativity: Let

$$Z(G) \subseteq G, \; Z(G) = \{g \in G \mid gx = xg \text{ for all } x \in G\}$$

then $Z(G) \leqslant G$

Proof. We will use the subgroup criterion. For this whole proof, let x be an arbitrary element of G. First note that $1x = x1 = x$, and so $1 \in Z(G)$. Next, take any $a, b \in Z(G)$. Since $bx = xb$, multiplying on the left and right by b^{-1} on both sides of the equation:

$$b^{-1}bxb^{-1} = b^{-1}xbb^{-1} \quad \Rightarrow \quad xb^{-1} = b^{-1}x$$

and since equality is symmetric, $b^{-1}x = xb^{-1}$, meaning $b^{-1} \in Z(G)$. Finally, we have

$$ab^{-1}x = axb^{-1} = xab^{-1}$$

meaning $ab^{-1} \in Z(G)$, proving it's a subgroup by the subgroup criterion □

This subgroup is special enough to be given a name:

[1] the trivial subset being just the identity $\{e_G\}$, which is always the simplest subgroup which has essentially no "interesting" structure, and hence trivial

Definition 2.2.4: Center

Let G be an arbitrary group. Define

$$Z(G) := \{g \in G | gx = xg \text{ for all } x \in G\}$$

to be the set of elements commuting with all the elements of G. This subset is called the *center* of G.

2.2.5 trivia The letter Z is because the German word for center is *Zentrum*.

Example 2.2.6: Center of Groups

The provided examples should be verified by the reader as practice

1. If G is abelian, then $Z(G) = G$. Thus $Z(\mathbb{Z}) = \mathbb{Z}$, $Z(\mathbb{R}) = \mathbb{R}$, and so forth
2. $Z(D_4) = \left\{1, r^2\right\}$
3. $Z(Q_8) = \{1, -1\}$

The Center of other subgroups we have encountered in section 1.2 will be left as exercises.

This should start giving you an idea of the power of commutativity. In fact, it is even more powerful than we need it to be. The notion of the center can be weakened a bit and still remain a group. Take $A \subseteq G$ (notice that A is just a subset). Then define

$$C_G(A) \subseteq G,\ C_G(A) = \left\{g \in G \mid gag^{-1} = a \text{ for all } a \in A\right\}$$

Note that $gag^{-1} = a$ is equivalent to $ga = ag$. The change in equation is due to a further generalization we will shortly make. Before we get to that, we must first show that $C_G(A)$ is indeed a group

Proof. We will use the subgroup criterion. First, since for any $a \in A$, $1a = a1 = a$, $1 \in C_G(A)$

Next, take $x, y \in C_G(A)$. Since $y \in C_G(A)$, $yay^{-1} = a$ for all $a \in A$. Multiplying on the left by y^{-1} and right by y, we get $a = y^{-1}ay = (y^{-1})a(y^{-1})^{-1}$, showing that $y^{-1} \in C_G(A)$. Finally, to show $xy^{-1}a(xy^{-1})^{-1} = xy^{-1}ayx^{-1} = a$, we use associativity and the fact that $x, y, y^{-1} \in C_G(A)$:

$$\begin{aligned} xy^{-1}axy^{-1} &= xay^{-1}yyx^{-1} \\ &= xax^{-1} \\ &= a \end{aligned}$$

and so $xy^{-1} \in C_G(A)$, showing that $C_G(A) \leqslant G$ by the subgroup criterion □

Since it's a subgroup that will always exist, it is special enough to be given a name:

Definition 2.2.7: Centralizer

Let G be an arbitrary group, and $A \subseteq G$[a]. Define

$$C_G(A) := \{g \in G | gag^{-1} = a \text{ for all } a \in A\}$$

This subset of G is called the *centralizer* of A in G. Since $gag^{-1} = a$ if and only if $ga = ag$, $C_G(A)$ is the set of elements of G which commute with every element of A.
If A is a subgroup of G and $C_G(A) = G$, then A is called a *central subgroup*

[a]Notice A is a *subset*, not necessarily a subgroup

If we take, $A = G$ then $C_G(G) = Z(G)$. Equivalently, notice that:

$$\bigcap_{g \in G} C_G(g) = Z(G)$$

since an element lies in either side exactly when it commutes with every element of G.

If $A \leqslant G$ and $C_G(A) = G$, then every element of A commutes with every element of G, so $A \leqslant Z(G)$. This is the reason for the name *central* subgroup.

Example 2.2.8: Centralizer of Groups

Let $A = \{1, r, r^2, r^3\} \subseteq D_4$ and $B = \{1, i\} \subseteq Q_8$

1. $C_{D_4}(A) = A$. Notice how this set is larger than $Z(D_4)$, since $r^3 \in C_{D_4}(A)$ but $r^3 \notin Z(D_4)$
2. $C_{Q_8}(B) = \{1, -1, i, -i\}$. Similar to the previous example, notice that $C_{Q_8}(B)$ is larger than $Z(Q_8)$.

We can generalize this result even further: so far, we have written $ga = ag$ for all $g \in G$. we can re-write this as $g\{a\} = \{a\}g$, where we define $g\{a\} = \{gx \mid x \in \{a\}\}$ and $\{a\}g = \{xg \mid x \in \{a\}\}$ This might seem to be making the situation overly-complex, however the great advantage of this approach is we can now general to taking a general set A

$$gA = Ag \qquad gA = \{ga \mid a \in A\} \;\; Ag = \{ag \mid a \in G\}$$

What this difference does is that it weakens the condition for an element to "directly" commute ($ga = ag$) to "indirectly" commuting, or more precisely commuting with respect to the set A: for every $a \in A$, there exists an $a' \in A$ such that $ga = a'g$. It will not always be the case that if $A \subseteq G$, then $gA = Ag$

Example 2.2.9: Counter-Example and Example

Let $A = \{r, \sigma\} \subseteq D_4$. Take $g = r$. Then:

$$rA = \{r^2, r\sigma\} \qquad Ar = \{r^2, \sigma r\} = \{r^2, r^3\sigma\}$$

notice that $rA \neq Ar$

However, if $A = \{1, r, r^2, r^3\}$ then for any $g \in D_4$, $gA = Ag$. As an example, let $g = \sigma$. Then

$$\sigma A = \{\sigma, \sigma r, \sigma r^2, \sigma r^3\} \qquad A\sigma = \{\sigma, r\sigma, r^2\sigma, r^3\sigma\} = \{\sigma, \sigma r, \sigma r^2, \sigma r^3\}$$

verifying other values of D_4 by hand shows that $gA = Ag$ for all $g \in D_4$

Therefore, we can define the following set of elements that satisfy $gA = Ag$:

$$N_G(A) \subseteq G,\ N_G(A) = \left\{g \in G \mid gAg^{-1} = A\right\}$$

Again, $N_G(A)$ is a subgroup of G. The proof is almost identical to the proof for $C_G(A)$ (change a for A in the proof). We therefore give a name to this special subgroup:

Definition 2.2.10: Normalizer

Take $gAg^{-1} = \left\{gag^{-1} | a \in A\right\}$. Define the *normalizer* of A in G to be the set

$$N_G(A) := \left\{g \in G | gAg^{-1} = A\right\}$$

If A is a group and $N_G(A) = G$ (that is, $gAg^{-1} = A$ for all $g \in G$) we call A a *normal subgroup* of G

If $g \in C_G(A)$, then $gag^{-1} = a$ for every $a \in A$, so $gAg^{-1} = A$ and $g \in N_G(A)$. Hence $C_G(A) \subseteq N_G(A)$, and since both are subgroups of G, $C_G(A) \leqslant N_G(A)$.

Example 2.2.11: Normalizer of Groups

Let $A = \{1, r, r^2, r^3\} \subseteq D_4$ and $B = \{1, i\} \subseteq Q_8$

1. $N_{D_4}(A) = D_4$. Notice how $Z(D_4) \subseteq C_{D_4}(A) \subseteq N_{D_4}(A)$, that is

   $$\{1, r^2\} \subseteq \{1, r, r^2, r^3\} \subseteq D_4$$

   Since A is also a subgroup of D_4, A is also an example of a normal subgroup of D_4

2. $N_{Q_8}(B) = \{1, -1, i, -i\}$ First, $1 \in N_{Q_8}(B)$. To show that $i \in N_{Q_8}(B)$, notice that

   $$iB = \{i, -1\} = Bi$$

   so $i \in N_{Q_8}(B)$. Similarly, for -1 and $-i$. For $j, k \in Q_8$, the relations $ij = k$, $ji = -k$, $ik = -j$ and $ki = j$ (see section 1.2.4) give

   $$jB = \{j, -k\} \neq \{j, k\} = Bj \qquad kB = \{k, j\} \neq \{k, -j\} = Bk$$

   meaning $j, k \notin N_{Q_8}(B)$. Similarly for $-j, -k$. Thus $N_{Q_8}(B) = \{1, -1, i, -i\}$. Notice that $C_{Q_8}(B) = N_{Q_8}(B)$ (example 2.2.8), so the normalizer need not be bigger than the centralizer

3. If $D = \{1, (1\ 2)\} \subseteq S_3$, what is $N_{S_3}(D)$? What about $C_{S_3}(D)$?

The notion of the normalizer is not simply generalization for the sake of generalization, it in fact comes up as a very important property: the kernel of a homomorphism has is always normal!

Proposition 2.2.12: Kernels Are Normal Subgroups

Let $\varphi : G \to H$ be a homomorphism, and take $\ker(\varphi) \leqslant G$. Then $\ker(\varphi)$ is a normal subgroup, that is

$$N_G(\ker(\varphi)) = G$$

In other words, for any $g \in G$, $g(\ker(\varphi)) = (\ker(\varphi))g$

***Proof*:**

Let $\varphi : G \to H$, and for notational convenience, let $K = \ker(\varphi)$.

Take any $g \in G$, and $k \in K$, that is, $k \in G$ such that $\varphi(k) = e_H$. We want to show that $gK = Kg$, or equivalently $gKg^{-1} = K$, for all $g \in G$. Take $gkg^{-1} \in gKg^{-1}$. Then

$$\varphi(gkg^{-1}) = \varphi(g)\varphi(k)\varphi(g^{-1}) = \varphi(g)1\varphi(g^{-1}) = \varphi(g)\varphi(g^{-1}) = \varphi(gg^{-1}) = e_H$$

thus, $gkg^{-1} \in K$, so for some k', $k' = gkg^{-1}$. Since this is true for arbitrary $k \in K$, we get $gKg^{-1} = K$, as we sought to show

The fact that kernels are normal subgroups will become very important in chapter 3 This brings us to the end of our generalizations. This section will be closed with a quick remark about normal subgroups. We did not prove much about them here. However, they are at the heart of chapter 3. For now, you can keep them in the back of your mind.

Exercise 2.2.1

1. $C_G(Z(G)) = G$ and deduce that $N_G(Z(G)) = G$
2. If $A, B \subseteq G$, and $A \subseteq B$, then $C_G(B) \leqslant C_G(A)$
3. For each of S_3, D_4 and Q_8, compute the centralizer of each element and find the center of the group.

   These next 3 subgroups from the next 3 questions will come back when we study group actions (and the conjugacy action, section 4.6)
4. Find the centre of $GL_3(\mathbb{C})$
5. Find the centralizer of $\begin{pmatrix} 1 & 0 & 0 \\ 0 & 2 & 0 \\ 0 & 0 & 3 \end{pmatrix}$ in $GL(3, \mathbb{C})$
6. Find the centralizer of $\begin{pmatrix} 1 & 0 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 & 0 \\ 0 & 0 & 1 & 0 & 0 \\ 0 & 0 & 0 & -1 & 0 \\ 0 & 0 & 0 & 0 & -1 \end{pmatrix}$ in $SL(5, \mathbb{C})$, the 5×5 complex matrices having determinant equal to 1
7. Let G be an abelian group and let $T(G) = \{x \in G \mid x^n = 1 \text{ for some } n \in \mathbb{N}_{>0}\}$. Show that $T(G) \leqslant G$. It is called the *torsion subgroup* of G.

8. Show that $C_G(S) \leqslant N_G(S)$ by showing $C_G(S)$ is the kernel of the homomorphsims $N_G(S) \to \text{Sym}(S)$ by $g \mapsto (x \mapsto gxg^{-1})$ (i.e. $T(g)(x) = T_g(x) = gxg^{-1}$)
9. For any group G, and any subset $A \subseteq G$, is it true that $Z(G) \leqslant C_G(A)$?

2.3 Subgroups Generated by Subsets

All groups have an underlying set. We can thus ask ourselves many questions about groups related to it's underlying set. For example, If we have two subgroups $H, K \leqslant G$, is $H \cap K$ or $H \cup K$ also a subgroup? What if we extend to finite or infinite intersection or union? On another hand, we can ask ourselves if there exists subsets $A \subseteq G$ that can in some way generate G using the binary operation. If generating all of G is too strong of a condition, can A always generate a subgroup of G? These are the types of questions that will be asked in this section.

Note that the technics in this section are very common throughout algebra (and many other areas of mathematics). Asking whether a subset of the underlying of an algebraic object "generates" the entire object (or part of the object) will occupy our time in many of the following chapters of this book (especially chapter 13).

2.3.1 Cyclic Groups and Cyclic subgroups

We will start our exploration subsets $A \subseteq G$ which are singletons: $|A| = 1$. The first question we will ask ourselves is if there is a subgroup $H \leqslant G$ which contains A. The answer to this is always yes: $G \leqslant G$ is a subgroup and by definition $A \subseteq G$. Though this is a valid answer, this is a very boring answer (in mathematical lingo, we'd say it is the trivial case). Thus, we look for a more interesting question: what is the *smallest* subgroup of G that contains A[2]. If $H \leqslant G$ is the smallest subgroup containing A, H is called a *cyclic subgroup*. If the entire group G is the smallest subgroup containing A, then G is called a *cyclic group*. To find the cyclic subgroup or groups given a subset $\{a\} = A$, a similar strategy will be used from when the order of an element (definition 1.2.8) was discussed. Cyclic groups they pop-up quite often due to their simplicity.

Definition 2.3.1: Cyclic groups

Let G be a group. The group G is *cyclic* if G can be generated by a single element, i.e., there is some element $x \in G$ such that $G = \{x^n | n \in \mathbb{Z}\}$ (where the operation is usually denoted as multiplication)

Sometimes, the notation C_n used to represent arbitrary cyclic groups of order n (with multiplication notations)

We say G is generated by x (or x generated G), and write $G = \langle x \rangle$. It was proven in proposition 1.2.6 that $\langle x \rangle$ is indeed a group. The existence of a C_n for every n is because there exists the cyclic group $\mathbb{Z}/n\mathbb{Z}$ for every n (or $\langle r_n \rangle$ for $r \in D_n$). Later in this section, we will show that $\mathbb{Z}/n\mathbb{Z}$ is the *only* cyclic group of order n up to isomorphism, meaning we will be able to conclude that $C_n \cong \mathbb{Z}/n\mathbb{Z} \cong \langle r_n \rangle$. Since C_n usually has multiplication notation, for this section we will use 1 to represent the identity.

[2]The notion of "smallest" is clear if $|G|$ is finite, but trickier if $|G|$ is infinite: $2\mathbb{Z} \subsetneq \mathbb{Z}$ although $|2\mathbb{Z}| = |\mathbb{Z}|$. Section 2.3.2 makes the notion precise.

2.3.2 Note The fact that $\langle x \rangle$ is the smallest subgroup containing x forced by construction: if there was a subgroup $H \leqslant G$ such that $H \subsetneq \langle x \rangle$, then there would be number n such that $x^n \in \langle x \rangle$ but $x^n \notin H$. Do you see how this contradicts that H is a subgroup?

Example 2.3.3

1. As mentioned earlier, the usual candidate for this example if $\mathbb{Z}/n\mathbb{Z}$, that is, addition modular n, which can be generated by $\overline{1}$. So $\langle \overline{1} \rangle = \mathbb{Z}/n\mathbb{Z}$. Notice there is some ambiguity here: How can you know if $\overline{1}$ represents the of order $5, 10, 324$? In general, you cannot. It is up using the context to determine the order. If the context requires clarity, a subscript will be added: $\langle \overline{1}_n \rangle = \mathbb{Z}/n\mathbb{Z}$ or $\langle [1]_n \rangle = \mathbb{Z}/n\mathbb{Z}$
2. D_n is *not* cyclic. Try finding a single element in D_n which generates all of D_n
3. Is Q_8 cyclic? What about $\mathbb{Z}$? What about $\mathbb{Z} \times \mathbb{Z}$?

Proposition 2.3.4: $|C_n| = |x|$

If $C_n = \langle x \rangle$, then $|C_n| = |x|$ (where if one side of this equality is infinite so is the other).

***Proof*:**
The idea is to show that that if $|x| < \infty$, then if two elements differ in exponent and are smaller than the group, $a \neq b < n$, then $x^a \neq x^b$, which can be shown by contradiction. For the case where the exponent is greater than or equal to n, $t \geq n$, x^t, such an elements can always equal to an element of order less than n. In particular, if $t \geq n$, then $x^t = x^{t-kn}$ for appropriate k for which $0 \leq t - kn < n$. Thus, in the $t \geq n$ case, the proof comes down to the first case that was proved.

For the $|x| = \infty$ case, assume $x^a = x^b$, $a \neq b$, and proceed by contradiction (i.e. $x^{b-a} = 1$).

2.3.5 Note This does not imply that for *any* $x \in C_n$, $|x| = |C_n|$. For example, $\mathbb{Z}/6\mathbb{Z}$ is cyclic since $\mathbb{Z}/6\mathbb{Z} = \langle \overline{1} \rangle$. However, $|\overline{2}| = 3$, meaning $\overline{2}$ cannot generate $\mathbb{Z}/6\mathbb{Z}$. On the other hand, $\overline{1}$ is not the only element of order 6 in $\mathbb{Z}/6\mathbb{Z}$, can you think of a second? Is there more than two?

Corollary 2.3.6: Cyclic $\Rightarrow$ Abelian

If G is cyclic, then G is abelian

***Proof*:**
Let G be a cyclic group. Take some $g \in G$ that generates it. Take some $a, b \in G$ so $g^n = a$ and $g^m = b$ then

$$ab = g^n g^m = g^{n+m} = g^{m+n} = g^m g^n = ba$$

thus, G is also abelian.

You might not be satisfied with this proof: why in the exponent can we commute n and m? The answer comes the associativity of groups. Since

$$a(aa) = (aa)a$$

it makes no difference to write

$$a^{1+2} \qquad a^{2+1}$$

or more generally $a^{n+m} = a^{m+n}$ due to proposition 1.1.15(5).

Since every element in a cyclic is determined by the exponent, having some information about what power of the generator leads to the identity can give us some information on smaller powers of the generator that also lead to the identity.

Proposition 2.3.7: Powers of an Element

Let G be a group, $x \in G$ and let $m, n \in \mathbb{Z}$ be nonzero. If $x^n = 1$ and $x^m = 1$, then $x^d = 1$, where $d = \gcd(m, n)$. In particular, if $x^m = 1$ for some nonzero $m \in \mathbb{Z}$, then $|x|$ is finite and $|x| \big| m$.

***Proof*:**
By Bézout's identity (theorem 0.2.10) there are integers u, v with $um + vn = d$, so

$$x^d = x^{um+vn} = (x^m)^u (x^n)^v = 1$$

For the second statement, $x^m = 1$ with $m \neq 0$ gives $x^{|m|} = 1$ (if $m < 0$, then $x^{-m} = (x^m)^{-1} = 1$), so x has finite order $k = |x|$. Divide: $m = ck + r$ with $c, r \in \mathbb{Z}$ and $0 \leq r < k$. Then $x^r = x^m (x^k)^{-c} = 1$, and the minimality of k forces $r = 0$, that is, $k \big| m$, as we sought to show.

Corollary 2.3.8

Let G be a group (not necessarily cyclic), let $x \in G$, and let $a \in \mathbb{Z} - \{0\}$.

1. if $|x| = \infty$, then $|x^a| = \infty$
2. if $|x| = n < \infty$, then $|x^a| = \frac{n}{\gcd(n,a)}$. If $a > 0$ divides n, then $|x^a| = \frac{n}{a}$.

***Proof*:**

1. If $|x^a| < \infty$, then there would exist an n such that $(x^a)^n = x^{an} = 1$. (if an is negative, take $-an$). But then x would have finite order, a contradiction
2. Let $d = \gcd(n, a)$, and write $n = dn'$ and $a = da'$, so that $\gcd(n', a') = 1$. For $k \in \mathbb{Z}$, proposition 2.3.7 and its converse ($n \big| m$ implies $x^m = 1$) give

   $$(x^a)^k = 1 \iff n \big| ak \iff n' \big| a'k \iff n' \big| k$$

   the last step because n' and a' are coprime (theorem 0.2.10 gives $un' + va' = 1$, so $n' \big| a'k$ implies $n' \big| un'k + va'k = k$). The smallest positive such k is n', so $|x^a| = n' = n/\gcd(n, a)$. If $a > 0$ divides n, then $\gcd(n, a) = a$, giving $|x^a| = n/a$, completing the proof.

With this idea in mind, let's do what we did before and try to see if we can classify cyclic groups.

For cyclic groups, there's in fact an incredibly simple isomorphism which will be introduced showing that if two cyclic groups have the cardinality (same order), they are in fact isomorphic, and thus can be treated as interchangeable! This means that when dealing with future theorems about cyclic groups, once we found it applies to a cyclic group of a certain order, we know it applies to any cyclic group of the same order! This also means there are only countably many finite cyclic groups, each with a predictable structure.

Theorem 2.3.9: Isomorphism between same-order Cyclic Groups

Any two cyclic groups of the same order are isomorphic. More specifically,

1. if $n \in \mathbb{Z}^+$ and $\langle x \rangle$ and $\langle y \rangle$ are both cyclic groups of order n, then the map

$$\psi : \langle x \rangle \to \langle y \rangle \qquad x^k \mapsto y^k$$

   is well defined and is an isomorphism

2. if $\langle x \rangle$ is an infinite cyclic group, the map

$$\psi : \mathbb{Z} \to \langle x \rangle \qquad k \mapsto x^k$$

   is well defined and is an isomorphism

***Proof*:**

1. By proposition 2.3.4, $|x| = |y| = n$. By proposition 2.3.7, $x^m = 1$ with $m \neq 0$ implies $n \mid m$, and conversely $n \mid m$ gives $x^m = (x^n)^{m/n} = 1$. For $m = 0$ both hold. So $x^m = 1$ exactly when $n \mid m$, and the same holds for y. For $a, b \in \mathbb{Z}$, multiplying by x^{-b} and y^{-b} gives

$$x^a = x^b \iff x^{a-b} = 1 \iff n \mid a - b \iff y^{a-b} = 1 \iff y^a = y^b$$

   The implications from left to right show that ψ is well defined, and those from right to left show that it is injective. It is a homomorphism, since $\psi(x^a x^b) = \psi(x^{a+b}) = y^{a+b} = y^a y^b = \psi(x^a)\psi(x^b)$, and it is surjective, since every element of $\langle y \rangle$ is some $y^k = \psi(x^k)$. Hence ψ is an isomorphism.

2. The map ψ is a homomorphism, since $x^{a+b} = x^a x^b$, and it is surjective, since every element of $\langle x \rangle$ is a power of x. If $\psi(a) = \psi(b)$ with $a > b$, then $x^{a-b} = 1$ with $a - b > 0$, so x has finite order and $\langle x \rangle$ is finite by proposition 2.3.4, a contradiction. Hence ψ is injective, and so an isomorphism.

Two infinite cyclic groups are both isomorphic to $\mathbb{Z}$ by (2), hence to each other, and two finite cyclic groups of the same order are isomorphic by (1), completing the proof.

This let's us properly conclude what was stated at the beginning of this section: if G is s cyclic group of order n (ex. $\mathbb{Z}/n\mathbb{Z}$ or $\langle r \rangle$, $r \in D_n$) then

$$\mathbb{Z}/n\mathbb{Z} \cong \langle r \rangle$$

Hence, instead of referencing a specific cyclic group, it is sometimes useful to just write C_n (some authors like Z_n) to represent some arbitrary cyclic group of order n, and use $\mathbb{Z}$ for an infinite cyclic group (instead of C_∞ or Z_∞)

Now that we classified all cyclic groups, we can ask ourselves the question of which elements generate one of these groups. this next proposition leads us to the answer

Now that we know how many cyclic sub-groups there are, and how these groups can be generated, we can explore what kind of sub-groups we get from cyclic groups. Quite naturally, every subgroup of a cyclic sub group is cyclic. It will turn out that if you have a cyclic group of infinite order, it has an infinite number of cyclic subgroups, and if its of finite order, lets say n, then every sub groups is of an order that divides n. That is , if $H \leqslant G$, G is cyclic, $|H| = a$, then $a|n$.

Proposition 2.3.10: x relation to cyclic group H

Let $H = \langle x \rangle$.

1. Assume $|x| = \infty$. Then $H = \langle x^a \rangle$ if and only if $a = \pm 1$.
2. Assume $|x| = n < \infty$. Then $H = \langle x^a \rangle$ if and only if $(a, n) = 1$. In particular, the number of generators of H is $\psi(n)$, where ψ is Euler's totient function. (which gives the number of relatively prime numbers to it).

Proof. 1. Suppose $a = \pm 1$. Then $\langle x^a \rangle$ contains x^a and its inverse x^{-a}, hence contains x, hence contains every power of x, so $\langle x^a \rangle = H$.

Conversely, suppose $H = \langle x^a \rangle$. Since $x \in H$, there is a $k \in \mathbb{Z}$ with $x = (x^a)^k = x^{ak}$, and therefore

$$x^{ak-1} = 1$$

Because $|x| = \infty$, the only power of x equal to 1 is x^0, so $ak = 1$. As a and k are integers, this forces $a = \pm 1$.

2. Write $n = |x|$. By proposition 2.3.4 applied to $H = \langle x \rangle$ and to $\langle x^a \rangle$,

$$|H| = |x| = n \qquad |\langle x^a \rangle| = |x^a|$$

and by corollary 2.3.8(2), $|x^a| = n/\gcd(n, a)$. Now $\langle x^a \rangle \leqslant H$, and both are finite, so $H = \langle x^a \rangle$ if and only if the two have the same order, that is if and only if

$$\frac{n}{\gcd(n, a)} = n$$

which happens if and only if $\gcd(a, n) = 1$.

For the count, every element of H is a power of x, and $x^k = x^{k'}$ whenever $k \equiv k' \bmod n$, so $H = \{x^0, x^1, \ldots, x^{n-1}\}$. These n elements exhaust a group of order n and are therefore distinct. By the previous paragraph the generators of H among them are exactly the x^a with $\gcd(a, n) = 1$, so the number of generators is the number of $a \in \{1, 2, \ldots, n\}$ with $\gcd(a, n) = 1$, which is $\psi(n)$.

□

Finally, we will put together all our knowledge into one theorem for easy reference:

Theorem 2.3.11: elements that generate cyclic subgroup

Let $H = \langle x \rangle$ be a cyclic group

1. Every subgroup of H is cyclic. More precisely, if $K \leqslant H$, then either $K = \{1\}$ or $K = \langle x^d \rangle$, where d is the smallest positive integer such that $x^d \in K$
2. If $|H| = \infty$, then for any distinct non negative integers a, b, $\langle x^a \rangle \neq \langle x^b \rangle$. Furthermore, for every integer m, $\langle x^m \rangle = \langle x^{|m|} \rangle$, where $|m|$ denotes the absolute value of m, so that the nontrivial subgroups of h correspond bijectivity with the integers $1, 2, 3, ...$
3. If $|H| = n < \infty$, then for each positive integer a dividing n, there is a unique subgroup of H of order a. This subgroup is the cyclic group $\langle x^d \rangle$, where $d = \frac{n}{a}$. Furthermore, for every integer m, $\langle x^m \rangle = \langle x^{gcd(n,m)} \rangle$, so that the subgroups of H correspond bijectivity with the positive divisors of n.

***Proof*:**
This proof involves a lot of counting.

1. Let $K \leqslant H$. If $K = \{1\}$, then $K = \langle 1 \rangle$ is cyclic. So assume $K \neq \{1\}$. Every element of K lies in $H = \langle x \rangle$, and so has the form x^a for some $a \in \mathbb{Z}$ (definition 2.3.1). Pick an element $x^a \in K$ with $x^a \neq 1$. Then $a \neq 0$, since $x^0 = 1$. Since K is a subgroup, $(x^a)^{-1} = x^{-a} \in K$ as well. One of a and $-a$ is positive, so the set

   $$S = \{b \in \mathbb{Z} | b > 0 \text{ and } x^b \in K\}$$

   is non-empty. By the well-ordering of the positive integers, the set S has a least element d. By construction, d is the smallest positive integer such that $x^d \in K$. We claim that $K = \langle x^d \rangle$.

   For the inclusion $\langle x^d \rangle \subseteq K$: we have $x^d \in K$, and K is closed under products and inverses, so $(x^d)^k \in K$ for every $k \in \mathbb{Z}$.

   For the inclusion $K \subseteq \langle x^d \rangle$: let $x^t \in K$ be arbitrary, with $t \in \mathbb{Z}$. Write $t = qd + r$ with $q, r \in \mathbb{Z}$ and $0 \leq r < d$. Such q and r exist. Indeed, some integers of the form $t - qd$ (for $q \in \mathbb{Z}$) are non-negative: taking $q = -|t|$ gives $t - qd = t + |t|d \geq t + |t| \geq 0$, since $d \geq 1$. By the well-ordering of the non-negative integers we may let $r = t - qd$ be the least non-negative integer of this form. If $r \geq d$, then $r - d = t - (q + 1)d$ would be a smaller non-negative integer of the same form, so $0 \leq r < d$. Now

   $$x^r = x^{t-qd} = x^t (x^d)^{-q} \in K$$

   since $x^t \in K$ and $x^d \in K$, and K is a subgroup. By the minimality of d, the exponent r cannot satisfy $0 < r < d$, so $r = 0$. Thus $x^t = (x^d)^q \in \langle x^d \rangle$. The two inclusions together give $K = \langle x^d \rangle$, so K is cyclic.

2. Assume $|H| = \infty$. Since $H = \langle x \rangle$, proposition 2.3.4 gives $|x| = \infty$. All powers of x are distinct: if $x^s = x^t$ with $s > t$, then $x^{s-t} = x^s (x^t)^{-1} = 1$ with $s - t > 0$, so a positive power of x would equal the identity, contradicting $|x| = \infty$ (definition 1.2.8).

Now let a and b be distinct non-negative integers, and without loss of generality say $a > b \geq 0$. Suppose toward a contradiction that $\langle x^a \rangle = \langle x^b \rangle$. If $b = 0$, then $\langle x^b \rangle = \langle 1 \rangle = \{1\}$, while $x^a \neq x^0 = 1$ because the powers of x are distinct and $a > 0$. Then $x^a \in \langle x^a \rangle$ but $x^a \notin \langle x^b \rangle$, a contradiction. If $b > 0$, then $x^b \in \langle x^a \rangle$ gives $x^b = (x^a)^k = x^{ak}$ for some $k \in \mathbb{Z}$, and since the powers of x are distinct, $b = ak$. Likewise $x^a \in \langle x^b \rangle$ gives $a = b\ell$ for some $\ell \in \mathbb{Z}$. Then $a = ak\ell$, and since $a \neq 0$ we get $k\ell = 1$, so either $k = \ell = 1$ or $k = \ell = -1$. Since a and b are both positive, $b = ak$ forces $k = 1$, hence $a = b$. This contradicts $a \neq b$. Thus $\langle x^a \rangle \neq \langle x^b \rangle$.

For the second claim, let $m \in \mathbb{Z}$. If $m \geq 0$, then $|m| = m$ and there is nothing to prove. If $m < 0$, then $x^{|m|} = x^{-m} = (x^m)^{-1} \in \langle x^m \rangle$, so every power of $x^{|m|}$ lies in $\langle x^m \rangle$, that is, $\langle x^{|m|} \rangle \subseteq \langle x^m \rangle$. In the same way, $x^m = (x^{|m|})^{-1} \in \langle x^{|m|} \rangle$ gives $\langle x^m \rangle \subseteq \langle x^{|m|} \rangle$. Hence $\langle x^m \rangle = \langle x^{|m|} \rangle$.

Finally, consider the map $d \mapsto \langle x^d \rangle$ from the positive integers to the nontrivial subgroups of H. For $d \geq 1$ the subgroup $\langle x^d \rangle$ is nontrivial, since $x^d \neq 1$. The map is surjective by part 1, and it is injective because distinct positive integers $d \neq d'$ give $\langle x^d \rangle \neq \langle x^{d'} \rangle$, by the first claim of this part: distinct non-negative exponents yield distinct subgroups. Thus the nontrivial subgroups of H correspond bijectively with the integers $1, 2, 3, \ldots$

3. Assume $|H| = n < \infty$. Since $H = \langle x \rangle$, proposition 2.3.4 gives $|x| = n$. In particular, $x^n = 1$.

   We first prove that for every integer m, $\langle x^m \rangle = \langle x^{\gcd(n,m)} \rangle$. If $m = 0$, then $\gcd(n, m) = n$, and $\langle x^0 \rangle = \{1\} = \langle x^n \rangle$ since $x^n = 1$. So let $m \neq 0$ and write $g = \gcd(n, m)$. Since g divides m, we have $x^m = (x^g)^{m/g} \in \langle x^g \rangle$, and hence $\langle x^m \rangle \subseteq \langle x^g \rangle$. For the reverse inclusion, corollary 2.3.8 together with proposition 2.3.4 gives

   $$|\langle x^m \rangle| = |x^m| = \frac{n}{\gcd(n, m)} = \frac{n}{g}, \qquad |\langle x^g \rangle| = |x^g| = \frac{n}{\gcd(n, g)} = \frac{n}{g}$$

   where $\gcd(n, g) = g$ because g divides n. Thus $\langle x^m \rangle$ is a subset of the finite set $\langle x^g \rangle$ and has the same cardinality, so $\langle x^m \rangle = \langle x^g \rangle$.

   Existence: let a be a positive divisor of n, and let $d = \frac{n}{a}$. Then d divides n, so by corollary 2.3.8 together with proposition 2.3.4,

   $$|\langle x^d \rangle| = |x^d| = \frac{n}{d} = a$$

   Thus $\langle x^d \rangle$ is a subgroup of H of order a.

   Uniqueness: let $K \leqslant H$ with $|K| = a$. If $a = 1$, then K contains only the identity, so $K = \{1\} = \langle x^n \rangle = \langle x^d \rangle$, since in this case $d = n$. If $a > 1$, then $K \neq \{1\}$, so by part 1, $K = \langle x^k \rangle$, where k is the smallest positive integer such that $x^k \in K$. By corollary 2.3.8 and proposition 2.3.4 again,

   $$a = |K| = |x^k| = \frac{n}{\gcd(n, k)}$$

   so $\gcd(n, k) = \frac{n}{a} = d$. Applying the equality $\langle x^m \rangle = \langle x^{\gcd(n,m)} \rangle$ with $m = k$ gives $K = \langle x^{\gcd(n,k)} \rangle = \langle x^d \rangle$. Thus every subgroup of H of order a equals $\langle x^d \rangle$.

   Finally, every subgroup K of H has order dividing n: this holds for $K = \{1\}$, and otherwise $K = \langle x^k \rangle$ as above has order $\frac{n}{\gcd(n,k)}$, which divides n because $\gcd(n, k)$ divides n. The

map sending a positive divisor a of n to the unique subgroup of H of order a is therefore surjective onto the subgroups of H, and it is injective because subgroups of distinct orders are distinct. Thus the subgroups of H correspond bijectively with the positive divisors of n.

Also, once you have Lagrange's Theorem (theorem 3.3.1), this proof will become much easier.

Note that the finite group examples of theorem 2.3.11 will eventually easily generalize to perhaps the most use theorem of the course: Lagrange Theorem (theorem 3.3.1), which sates that the order of any subgroup divides the order of a group ($H \leqslant G \Rightarrow |H|||G|$).

An abelian subgroup H of G, even one of prime order, need not be contained in the center $Z(G)$:

Example 2.3.12: : $H \notin Z(G)$

Take D_4. Note that $\langle\sigma\rangle \leqslant D_4$ and $|\langle\sigma\rangle| = 2$, and so it's cyclic and abelian. However. $r\sigma = \sigma r^3$ meaning that $\sigma \notin Z(D_4)$. However, it is in the centralizer $C_{D_4}(\sigma) = \{g \in G | g\sigma = \sigma g\}$ for $\sigma\sigma = e = \sigma\sigma$, which can also be "obvious" since $\langle\sigma\rangle$ is abelian, and so it would be in the centralizer.

The intuition behind this is that for something to be in the center, it must commute with *all* of G. It is possible to take a subgroup that only commutes (as we have seen with the idea of the centralizer). This is why the intersection under definition 2.2.4 is true: it must commute with everything.

2.3.13 Note You cannot take $\langle x\rangle \leqslant G$ and do $G - \langle x\rangle$. G is not necessarily a group. Take D_4, and take $K = \langle\sigma\rangle$. Then consider $H = D_4 - K$. Then $r^3 \cdot r\sigma = \sigma$, showing that H is not closed under multiplication. Thus, subtraction of groups is not well-defined. However, it will turn out that under the right circumstances, *dividing* and *multiplying* groups will be well-defined! This will be the subject of the next chapter (chapter 3)

interesting exercise

1. number 9
2. number 13
3. number 16
4. Knowing Cyclic groups, we can look at another great example of a homomorphism: $\psi : \mathbb{Z} \to Z_n$, where $Z_n = \langle x\rangle$,
$$\psi(a) = x^a$$
Prove that it's a homomorphism, then figure out what elements of $\mathbb{Z}$ map to an element of Z_n.
5. the product of two cyclic subgroups is not necessarily cyclic!

2.3.2 Generating Subgroups

We now turn our attention to generating groups or subgroups using more than 1 element. When studying cyclic groups, we asked whether given an element $x \in G$, does there exists a smallest group $H \leqslant G$ such that $x \in H$. It was shown that taking the closure of x by taking all powers of x resulted

in such a group, namely $H = \langle x \rangle$. Phrased differently, the subgroup $\langle x \rangle$ is the smallest subgroup of G that contains the set $\{x\}$. What it means to be the *smallest* is if $L \leqslant G$ is another subgroup where and $x \in L$, then $\langle x \rangle \subseteq L$. We now replace the singleton $\{x\}$ with some arbitrary subset $A \subseteq G$.

As mentioned in the beginning of this chapter, generating subgroups from a subset of a group is not unique to Group Theory. In the following chapters studying other algebraic structures (ex. Ideals, rings, modules, vector-spaces, algebras, fields, etc.), the theme of trying to find minimal sub-object $S \leqslant X$ (subgroup, subspace, subfield, subring, etc.) that contain a subset $A \subseteq X$ from the original object (so that $A \subseteq S \leqslant X$) will repeat itself, and so will the general method for finding the minimal subobject. To find a minimal subobject there are two possible general approach:

1. (Generation Method) If $A \subseteq X$ is a subset of the object, take all possible subobjects containing A and intersect them. In the case of groups, if $A \subseteq G$, then take all possible subgroup $H_A \leqslant G$ containing A (so $A \subseteq H_A \leqslant G$ and intersect them all.
2. (Closure Method) The above approach can be thought as the "global approach". Another way of finding the minimal subobject is instead by the "element approach" (or "local approach"): If A is a subset of the object, then let $\overline{A}$ be the set of all possible combinations of elements of A using the binary operation of G. In the case of groups, of $A \subseteq G$, then $\overline{A}$ will be all the possible combination of elements of A with the binary operation of G.

The main result of this section is that these two methods will coincide and form the same subgroup. In proceeding chapters covering subobjects (subrings, ideals, subspaces, etc.), some details will be omitted due to them being covered in this section, so it is advised that this section be well understood.

We start with the first method. We need show that the intersection of subgroups still forms a group:

Proposition 2.3.14: intersection of Groups

Let G be a group and let $\mathcal{H}$ be any collection of subgroups of G. Then

$$\bigcap_{H \in \mathcal{H}} H$$

Is a subgroup of G.

***Proof*:**
Let $K = \bigcap_{H \in \mathcal{H}} H$. First, $e \in H$ for all $H \in \mathcal{H}$, so $e \in K$. Next, take $a, b \in K$. Since $b \in K$, b is in every subgroup H in $\mathcal{H}$. Thus, b^{-1} is in every subgroup H in $\mathcal{H}$, and so $b^{-1} \in K$. Similarly, ab^{-1} would be in every subgroup H in $\mathcal{H}$ (since each subgroup passes the subgroup test), so $ab^{-1} \in K$. Thus, by the subgroup test, K is a subgroup of G

Therefore, the following is well-defined:

Definition 2.3.15: Minimal Subgroup via Generation

let G be a group and $A \subseteq G$. Then

$$\langle A \rangle = \bigcap_{\substack{H \leqslant G \\ A \subseteq H}} H$$

is called the *closure of* A, or the subgroup *generated by* A. If A is a finite set $\{a_1, a_2, ..., a_n\}$, we can write $\langle a_1, a_2, ..., a_n \rangle$. Furthermore, $\langle A, B \rangle := \langle A \cup B \rangle$ for the union of two sets.

We have already been using this notation when $A = \{x\}$ is a singleton, in particular cyclic subgroups are the closure of singletons. Note that $\langle A \rangle$ always exists, since at minimum $A \subseteq G$ (and naturally $G \leqslant G$), so G is part of the sets in be intersection. This is important to point out as there exists sets where $\langle A \rangle = G$:

Definition 2.3.16: Generating Set and Generators

Let $A \subseteq G$. Then if $\langle A \rangle = G$, then A is called a *generating set* for G, and the elements of A are called *generators*.

If $A = \emptyset$, then A is containing in every group, including the trivial group $\{e_G\}$. As the intersection $\{e_G\}$ with any group is $\{e_G\}$, we see that $\langle \emptyset \rangle = \{e_G\}$.

Proposition 2.3.17: Minimal Subgroup using Generation

Let $A \subseteq G$. Then $\langle A \rangle \leqslant G$ is the unique smallest subgroup containing A.

***Proof*:**
If $H' \leqslant G$ and $A \subseteq H'$, then by definition H' is one of the subgroup that were intersected in the aforementioned definition, since $\langle A \rangle$ is equal to this intersection, $\langle A \rangle \subseteq H'$, so $\langle A \rangle$ is minimal.

Next, $\langle A \rangle$ is the unique smallest subgroup containing A (similarly to how $\langle x \rangle$ is unique in the sense that all cyclic subgroups of the same order are isomorphic to it). If there exists another group K' that was also the smallest subgroup containing A, then K' would be in the intersection above, so $\langle A \rangle \subseteq K'$. But since K' is supposed to be the smallest subgroup containing A, it is also the case that $K' \subseteq \langle A \rangle$. Therefore $\langle A \rangle = K'$, showing uniqueness as well, completing the proof.

The limit with this approach is that all the possible subgroups containing A must be found, and that is not always feasible. There is not a general method to find elements of $\langle A \rangle$ (except, naturally, that $e_G \in \langle A \rangle$). The 2nd approach will give a better insight into this problem by changing perspective away from the high-level and starting with the elements of A and trying to "generate" a subgroup containing A. To that end, define the set

$$\overline{A} := \{a_1^{\sigma_1} a_2^{\sigma_2} \cdots a_n^{\sigma_n} \mid n \geq 1 \text{ and } a_i \in A,\ \sigma_i = \pm 1, 1 \leq i \leq n\}$$

where if $A = \emptyset$ then $\overline{A} = \{e_G\}$. The set $\overline{A}$ contains all possible finite products (using the binary operation of G) of the elements from A. Note that the a_i's need not be distinct, for example a^2

for $a \in A$ would be written a^1a^1. It is also easy to verify that this set is indeed a subgroup of G using the subgroup criterion (consider that n can vary in any possible length, see exercise 2.3.1 (1)). The interesting question is whether this set is also the smallest minimal subgroup containing A, and indeed it is:

Proposition 2.3.18

Let G be a group and $A \subseteq G$ be a subset of G. Then

$$\langle A \rangle = \overline{A}$$

***Proof*:**
If $A = \emptyset$, then $\overline{A} = \{e_G\}$, and $\langle \emptyset \rangle = \{e_G\}$ as computed before proposition 2.3.17. So let $A \neq \emptyset$.

First, $\overline{A}$ is a subgroup of G containing A. It is nonempty, and for $x = a_1^{\sigma_1} \cdots a_n^{\sigma_n}$ and $y = b_1^{\rho_1} \cdots b_m^{\rho_m}$ in $\overline{A}$, the inverse of y is $b_m^{-\rho_m} \cdots b_1^{-\rho_1}$, so

$$xy^{-1} = a_1^{\sigma_1} \cdots a_n^{\sigma_n} b_m^{-\rho_m} \cdots b_1^{-\rho_1}$$

is again a product of elements of A and their inverses, that is, $xy^{-1} \in \overline{A}$. So $\overline{A} \leqslant G$ by proposition 2.1.3. It contains every $a \in A$, as the product a^1 with $n = 1$. Hence $\langle A \rangle \subseteq \overline{A}$ by proposition 2.3.17.

Conversely, let H be a subgroup of G with $A \subseteq H$. Then H contains every $a \in A$ and its inverse, and it is closed under products, so induction on n shows that H contains every product $a_1^{\sigma_1} \cdots a_n^{\sigma_n}$ with $a_i \in A$ and $\sigma_i = \pm 1$. So $\overline{A} \subseteq H$ for every such H, and $\overline{A} \subseteq \langle A \rangle$ by definition 2.3.15. Hence $\langle A \rangle = \overline{A}$, as we sought to show.

From now on, the notation $\langle A \rangle$ will be used to represent the subgroup generated by A.

We can ask some basic question about $\langle A \rangle$ given A and G. If G is abelian, then the order the elements are written in does not matter, and so if $A = \{a_1, ..., a_k\}$, every element can be written as:

$$a_1^{n_1} a_2^{n_2} \cdots a_k^{n_k}$$

This is not the case if G is not abelian. Consider for example:

$$G = \langle a, b \mid a^2 = b^2 = 1 \rangle \tag{2.1}$$

Notably, $ab \neq ba$. Next, if each $a_i \in A$ has finite order, then if G is abelian we have that G is finite. This is because:

$$(ab)^n = a^n = b^n$$

See exercise 2.3.1 (2). This is not necessarily the case if G is non-abelian. Consider again the group in equation (2.1) where $|a| = 2$ and $|b| = 2$. Then we see that:

$$abababa....$$

If G is not abelian, then as mentioned in box 1.3.5 and example 1.3.6, it is exceedingly difficult to determine the structure of G.

We may also ask if there is any "optimal" set of generators for a group, that is a "best" subset $A \subseteq G$ st $\langle A\rangle = G$. Generally, there can be many sets that generate a group: for example $\langle r, \sigma\rangle = \langle r\sigma, \sigma\rangle = D_n$, or $\langle 2, 3\rangle = \langle 7, 5\rangle = \mathbb{Z}/10\mathbb{Z}$. Notice that no proper subset of $\{2, 3\}$ generates $\mathbb{Z}/10\mathbb{Z}$, however there do exist smaller subsets of $\mathbb{Z}/10\mathbb{Z}$ that generate $\mathbb{Z}/10\mathbb{Z}$ (namely, $\{1\}$). Thus, the cardinality of the minimal generating subset cannot be determined by simply finding a minimal generating subset: it would have to be $\min\{|A| \mid A \subseteq G,\ \langle A\rangle = G\}$[3].

Notice also that in the case of D_4 with generators $a = \sigma$ and $b = r\sigma$ have order 2, while D_4 has order 8. Using this show how it is not always the case that all elements of D_4 will be written of the form $a^\alpha b^\beta$ $(\alpha, \beta \in \mathbb{Z})$ like in the abelian case, in particular show that aba cannot be written as $a^\alpha b^\beta$ for any $\alpha, \beta \in \mathbb{Z}$.

2.3.19 Food for Thought If G is finitely generated, is every subgroup of G finitely generated? In other words, if

$$G = \langle S|R\rangle$$

where S is a set of elements and R is the relation on those elements, then can you find a subgroup $H \leqslant G$ such that you need an infinite number of elements to generate H? There is an answer to this question which will be given as exercise 2.3.2 (1), but it can be useful to contemplate this question now as an exercise in the types of questions a mathematicians might ask themselves. You can further ask if $\varphi : G \to H$ is a homomorphsims, and G is finitely generated, is $\varphi(G)$ finitely generated?

Exercise 2.3.1

1. Show that $\overline{A}$ is indeed a subgroup
2. Let G be abelian and $A \subseteq G$ a finite set containing only elements of finite order. Show that $\langle A\rangle$ is finite.
3. Show that every finitely generated subgroup of $\mathbb{Q}$ is cyclic
4. Let (Presentation for V_4. This group is called the Klein 4-group, or *Viergruppe*. Prove that $V_4 \cong \mathbb{Z}_2 \times \mathbb{Z}_2$, showing that a group has a non-unique representation.
5. If $H, K \leqslant G$, is $H \cup K$ a group? If $H \cup K$ is a subgroup in some case, what relation would there be between H and K (does on include the other?)
6. Let $G = k[x, 1/x]$ be the group of polynomials under multiplication.

2.3.3 Free Groups

So far, when we were generating groups from sets, we either took a subset of G (and so took the relation between elements of G), or we defined the set given a presentation. For example, We can make a group from $\{a, b\}$ by defining [4]

$$\langle a, b|a^n = 1, b^2 = 1, ab = b^{-1}a\rangle$$

[3] If G is infinite, it might be that we require the stronger notion of an Infimum: $\inf\{|A| \mid A \subseteq G,\ \langle A\rangle = G\}$
[4] This is D_n

what happens if we get rid of one or two of these relations? What if we get rid of all three, and make a group "free" of relations besides the ones needed to form a group? We explore this question in this section.

Since this group has no restrictions, it can be thought of as the "most general" group on that number of elements. In fact, something more subtle is going on here: since $\{a, b\}$ (or any set A to that matter) is essentially an arbitrary set, we are asking if from *any* arbitrary set, is there a way of defining a group using as little "extra group structure" as possible, or put another way, as free from relations as possible. If we can define such a group given $\{a, b\}$, is there a way of "defining" another group generated by two elements using this more "free group" by adding relations to the "free group"?


The answers to this question lies in exploring how to make a *function* (or to be pedantic a *set-function*) from any set A to a group G

$$f : A \to G$$


be "lifted" to a *group-homomorphism*

$$\varphi : F(A) \to G$$

where $F(A)$ will be our "free group" on A (the notation $F(A)$ is suggestive that this group will indeed be called a free group). The word "lifted" here means that if we restrict $F(A)$ to A, then $\varphi|_A = f$. This can be visualized with the following diagram (called a commutative diagram):



Thus, we turn a set function into a group-homomorphism while still keeping the structure of the set-function. More generally, if $f_1 \colon A \to G_1$ and $f_2 \colon A \to G_2$ are functions and $\varphi \colon G_1 \to G_2$ is a homomorphism with $f_2 = \varphi \circ f_1$, then φ is called a lift of f_2 through f_1. Equivalently, φ is such a lift if the following diagram commutes:




Why are lifts the key concept? It is because not all set-function can be lifted to group homomorphism:


Example 2.3.20: Lifts and non-Lifts

1. Let $A = \{a\}$, $G_1 = \mathbb{Z}/5\mathbb{Z}$, and $G_2 = \mathbb{R}$. Define
   (a) $f_1 : A \to G_1$, $f_1(a) = 0$
   (b) $f_2 : A \to G_2$, $f_2(a) = 4$

   Does A lift to G_1, that is:



that is, does there exist a homorphism $\varphi : \mathbb{Z}/5\mathbb{Z} \to \mathbb{R}$ such that $f_2 = \varphi \circ f_1$ If we can find a homomorphism φ such that



then a lift exists. Suppose there were such a φ. Then

$$4 = f_2(a) = (\varphi \circ f_1)(a) = \varphi(0) = 0$$

since a homomorphism sends 0 to 0 (proposition 1.4.4(1)). But $4 \neq 0$ in $\mathbb{R}$, so no such homomorphism exists, and f_2 has no lift through f_1.

2. Now swap the roles of 0 and 4: let $f_1(a) = 4$ in $\mathbb{Z}/5\mathbb{Z}$ and $f_2(a) = 0$ in $\mathbb{R}$. Every homomorphism $\varphi\colon \mathbb{Z}/5\mathbb{Z} \to \mathbb{R}$ is zero, because $5\varphi(x) = \varphi(5x) = \varphi(0) = 0$ in $\mathbb{R}$ for every $x \in \mathbb{Z}/5\mathbb{Z}$ (proposition 1.4.4(3)), so $\varphi(x) = 0$. The zero homomorphism satisfies $\varphi(f_1(a)) = 0 = f_2(a)$, so it is a lift of f_2 through f_1, and it is the only one.

3. Let $f_1'(a) = 1$ in $\mathbb{Z}/5\mathbb{Z}$ and $f_2'(a) = 1$ in $\mathbb{R}$. A lift φ would satisfy $\varphi(1) = 1$, but every homomorphism $\mathbb{Z}/5\mathbb{Z} \to \mathbb{R}$ is zero by the previous item. So f_2' has no lift through f_1'.

4. Let $G_1 = G_2 = \mathbb{Z}/5\mathbb{Z}$ and let $A = \{a\}$. Let

   (a) $f_1 : A \to \mathbb{Z}/5\mathbb{Z},\ f_1(a) = 1$

   (b) $f_2 : A \to \mathbb{Z}/5\mathbb{Z},\ f_2(a) = 2$

   A lift φ of f_2 through f_1 satisfies $\varphi(1) = 2$, hence $\varphi(x) = x\varphi(1) = 2x$ for every x (proposition 1.4.4(3)). Conversely, $x \mapsto 2x$ is a homomorphism of $\mathbb{Z}/5\mathbb{Z}$, since $2(x + y) = 2x + 2y$. So there is exactly one lift. If instead $f_1(a) = f_2(a) = 0$, then every homomorphism $\varphi\colon \mathbb{Z}/5\mathbb{Z} \to \mathbb{Z}/5\mathbb{Z}$ is a lift, since $\varphi(0) = 0$, and the five homomorphisms $x \mapsto mx$ with $0 \leq m \leq 4$ are distinct, because they send 1 to different elements. So there can be several lifts.

Which group $F(A)$, together with a function $i\colon A \to F(A)$, admits a lift through i of every function from A to every group? The trivial group does not, as soon as A has two elements $a \neq b$. If $j\colon A \to \{e\}$ and $f\colon A \to G$ takes distinct values $f(a) \neq f(b)$, then a lift φ of f through j would give $f(a) = \varphi(j(a)) = \varphi(e) = \varphi(j(b)) = f(b)$. The function j imposes the relation $j(a) = j(b)$, and every lift must respect it. So $F(A)$ should satisfy no relations among the elements $i(a)$ beyond those that the group axioms force.

The High-level Idea

The construction below recurs throughout the book in different settings, as the *free objects*[5] and, more generally, as *universal properties*[6]. The *universal property of free groups* is the first universal

[5] *Free monoids*, such as the monoid of strings over an alphabet, appear in section 7.1, and *free modules* in section 12.3.2.

[6] For instance theorem 3.1.15, theorem 5.4.3 (products), theorem 5.4.10 (coproducts), theorem 9.2.4, theorem 9.5.4, theorem 15.3.4 and theorem 15.1.12.

property in this book after that of the trivial group (proposition 1.4.5).

Let's say A is an arbitrary set. Our goal is to construct a group, which we will label $F(A)$, from which every other group which contains A can be derived. First, we will be "relating" A to any group G. Let's take all set-functions:

$$f : A \to G$$


Where A is a set that maps into the group G [7]. Let's label this function along with its co-domain G as (f, G). Choosing all possible f and G will make all possible functions from A to every possible group, essentially telling us all ways A relates to any group G. The fact that there is no restriction on the functions from A to G is a way of saying there is *no* group structure on A which limits the types of maps we can form. Remember that when we lift the map $f : A \to G$ to $\varphi : F(A) \to G$, we need that $\varphi|_A = f$, so the fact that the map can be arbitrary means that $F(A)$ must accommodate for any function from A to G. As we have shown in example 2.3.20, not all groups can accommodate this. Let's label the set of all possible (f, G) as $\mathcal{F}^A$:

$$\mathcal{F}^A = \{(f, G) | f : A \to G\}$$

Next, we want to be able to relate the groups in the co-domain. We want to define $F(A)$ to be able to lift from a set-function to a group-homomorphsims. What we will do is define the following relation between any two pairs (f_1, G_1), (f_2, G_2): a *morphism*

$$(f_1, G_1) \xrightarrow{\varphi} (f_2, G_2)$$

is a homomorphism φ: $G_1 \to G_2$ such that the following diagram commutes:



that is, where $f_2 = \varphi \circ f_1$. You can think of the morphism φ as a homomorphism that is restricted by f_1 and f_2. In fact, every example in example 2.3.20 can be re-written to be morphisms from $\mathcal{F}^A$. Take a moment to go back and translate the previous notation to the new one, and think about what $\mathcal{F}^A$ with its objects and morphisms represent. We have essentially taken any group homomorphism between any two groups $G_1 \xrightarrow{\varphi} G_2$ and also made a relation between A and these groups. In fact, as reader's who have read section 0.4 and chapter 8 might have guessed, we have defined a category

[7] It might be more intuition for every f to be *injective*, since this way we'd get that every G contains the set A. We can indeed do this, and we will get the same result. For reasons that will be elaborated later in this section, the more general approach is desirable to be able to repeat this trick later in the textbook

Proposition 2.3.21: $\mathcal{F}^A$ is a category


The set $\mathcal{F}^A$ along with the morphisms form a category (we can write $\mathfrak{F}^A S$ as a shorthand to represent $\mathcal{F}^A$ and it's morphisms). In particular:

1. For every $(f, G) \in \mathfrak{F}^A$, there exists an identity morphism $1_{(f,G)} : (f, G) \to (f, G)$
2. If $\varphi, \psi \in \mathfrak{F}^A$ are morphisms

$$\varphi : (f_1, G_1) \to (f_2, G_2) \qquad \psi : (f_2, G_2) \to (f_3, G_3)$$


then $\psi \circ \varphi$ is a morphism.

***Proof*:**
First, composition of morphisms will be a morphism in $\mathcal{F}$. If $\varphi, \psi \in \mathcal{F}$ are composable morphisms (i.e. the codomain of φ matches the domain of ψ) then



that is, the morphism $\psi \circ \varphi \in \mathcal{F}^A$ with domain (f, G) and codomain (f'', K) exists

Next, we will check each object $(f, G) \in \mathcal{F}^A$ has an identity morphism. Take an arbitrary $(f, G) \in \mathcal{F}^A$, so that $A \xrightarrow{f} G$. Then the homomorphism $\mathrm{id}_G : G \to G$, $\mathrm{id}_G(x) = x$ satisfies




If we take any $\varphi \in \mathcal{F}^A$ where $\varphi : (f, G) \to (f', H)$, then $\mathrm{id}_H \varphi = \varphi \mathrm{id}_G = \varphi$, showing that identities exist.

The fact that any compossible triple is associative comes from function composition.

With the category $\mathfrak{F}^A$ finally defined, we can ask the following question

Does $\mathfrak{F}^A$ have an initial object[8]?

That is, does there exists (f^*, G^*) such that for any object $(f, G) \in \mathfrak{F}^A$, there exists a unique morphism φ^* such that



[8] see definition 1.4.6

Notice that this is the same lifting question we have asked about a theoretical "free group" $F(A)$ near the beginning of this section, but re-phrased! You might ask if such a group even exists? If such a group does exist, then have found a group which let's us relate it to any other group. We will call such a group (if it exists) a *free group*. Essentially, $F(A)$ must be able to relate to any other group, making it the "most general" group. But what is $F(A)$? In the following section, we will construct such a group that will indeed be the initial object of $\mathfrak{F}^A$.

Constructions of $F(A)$

When $A = \{a\}$ the answer is $\mathbb{Z}$, with $j\colon \{a\} \to \mathbb{Z}$ given by $j(a) = 1$. Let (f, G) be an element of $\mathfrak{F}^A$ and put $g = f(a)$. A homomorphism $\varphi\colon \mathbb{Z} \to G$ with $\varphi \circ j = f$ satisfies $\varphi(1) = \varphi(j(a)) = g$. Since $n \in \mathbb{Z}$ is the n-th power of 1 in the additive group $\mathbb{Z}$, proposition 1.4.4(3) forces

$$\varphi(n) = \varphi(1)^n = g^n$$

so there is at most one such φ. Conversely, $n \mapsto g^n$ is a homomorphism because $g^{m+n} = g^m g^n$, and it sends $j(a) = 1$ to $g = f(a)$. So φ exists and is unique.

When $A = \emptyset$ the answer is the trivial group $\{0\}$, which is the initial object of groups (proposition 1.4.5).

For a general set A, the group $F(A)$ is built from formal products of elements of A and of formal inverses of those elements, in which the only cancellation allowed is that of a symbol standing next to its own inverse.

Let A be a set. Choose a set A^{-1} disjoint from A together with a bijection $A \to A^{-1}$, written $a \mapsto a^{-1}$. At this stage a^{-1} is only the name of a new symbol, not an inverse in any group. The elements of $A \sqcup A^{-1}$ are called *letters*. The *formal inverse* of a letter x is the letter x^{-1}, where $x^{-1} = a^{-1}$ if $x = a \in A$ and $x^{-1} = a$ if $x = a^{-1} \in A^{-1}$. Then $(x^{-1})^{-1} = x$ for every letter x, and $x^{-1} \neq x$ because A and A^{-1} are disjoint.

Definition 2.3.22: Word

Let A be a set. A *word* on A is a finite sequence $(x_1, x_2, \ldots, x_n)$ of letters $x_i \in A \sqcup A^{-1}$, written $x_1 x_2 \cdots x_n$. The integer $n \geq 0$ is the *length* of the word, and the word of length 0 is the *empty word*, written 1. The set of all words on A is denoted $W(A)$. The *concatenation* of $w = x_1 \cdots x_n$ and $w' = y_1 \cdots y_m$ is the word $ww' = x_1 \cdots x_n y_1 \cdots y_m$ of length $n + m$.

Concatenation is associative, since $(ww')w''$ and $w(w'w'')$ are the same sequence of letters, and $1w = w1 = w$ for every word w. Concatenation does not make $W(A)$ a group: the length of ww' is the sum of the lengths of w and w', so no nonempty word has an inverse. Inverses appear once adjacent pairs xx^{-1} are allowed to cancel.

Definition 2.3.23: Reduced Word

Let A be a set.

1. If $w = uxx^{-1}v$ for words u, v and a letter x, then passing from w to uv is called an *elementary reduction*, written $w \to uv$. The notation $w \to^* w'$ means that w' is obtained from w by a finite sequence of zero or more elementary reductions.
2. A word is *reduced* if no elementary reduction applies to it, that is, if no two adjacent letters of it are formal inverses of each other. The set of reduced words on A is denoted $F(A)$.

An elementary reduction lowers the length of a word by 2. Every word of length 0 or 1 is reduced.

Example 2.3.24: Reducing a Word

Let $A = \{a, b\}$ and $w = ab^{-1}baa^{-1}b$. The word w contains two adjacent pairs of formal inverses, $b^{-1}b$ and aa^{-1}. Deleting $b^{-1}b$ first gives $aaa^{-1}b$, and deleting aa^{-1} from that gives ab. Deleting aa^{-1} first gives $ab^{-1}bb$, and deleting $b^{-1}b$ from that gives ab again. The word ab is reduced, since $b \neq a^{-1}$, so both orders of cancellation end at the same reduced word. Lemma 2.3.25 shows that the reduced word at the end never depends on the order.

Lemma 2.3.25: Reduced Word Lemma

Let A be a set. For every word $w \in W(A)$ there is exactly one reduced word $\mathrm{red}(w)$ with $w \to^* \mathrm{red}(w)$. In particular, $\mathrm{red}(w) = w$ when w is reduced.

***Proof*:**

Step 1: existence. Let n be the length of w. Apply elementary reductions to w for as long as one applies. Each lowers the length by 2, so the process stops after at most $n/2$ steps, and it stops exactly at a reduced word r, with $w \to^* r$.

Step 2: two elementary reductions of one word. Let $w = x_1 \cdots x_n$, and suppose $w \to w_1$ and $w \to w_2$ delete the adjacent pairs in positions $\{i, i+1\}$ and $\{j, j+1\}$ respectively. Exchanging the names w_1 and w_2 if necessary, we may assume $i \leq j$. If $i = j$, then $w_1 = w_2$. If $j = i + 1$, then $x_{i+1} = x_i^{-1}$ and $x_{i+2} = x_{i+1}^{-1} = x_i$, so deleting $x_i x_{i+1}$ and deleting $x_{i+1}x_{i+2}$ both leave $x_1 \cdots x_{i-1}x_i x_{i+3} \cdots x_n$, and again $w_1 = w_2$. If $j \geq i + 2$, the two pairs do not overlap, and deleting both of them, in either order, gives one word w_3 with $w_1 \to w_3$ and $w_2 \to w_3$. So either $w_1 = w_2$, or some word w_3 satisfies $w_1 \to w_3$ and $w_2 \to w_3$.

Step 3: uniqueness. We show by strong induction on the length n of w that $w \to^* r$ and $w \to^* r'$ with r and r' reduced imply $r = r'$. If w is reduced, then no elementary reduction applies to it, so both sequences of reductions are empty and $r = w = r'$. Otherwise both sequences are nonempty, since w itself is not reduced, and they begin $w \to w_1 \to^* r$ and $w \to w_2 \to^* r'$ with w_1 and w_2 of length $n - 2$. If $w_1 = w_2$, the induction hypothesis for w_1 gives $r = r'$. Otherwise Step 2 gives w_3 with $w_1 \to w_3$ and $w_2 \to w_3$, and Step 1 gives a reduced word r'' with $w_3 \to^* r''$. Then $w_1 \to^* r$ and $w_1 \to^* r''$, so $r = r''$ by the induction hypothesis for w_1, and in the same way $w_2 \to^* r'$ and $w_2 \to^* r''$ give $r' = r''$. Hence $r = r'$.

Steps 1 and 3 give exactly one reduced word $\mathrm{red}(w)$ with $w \to^* \mathrm{red}(w)$. When w is reduced, $w \to^* w$ by the empty sequence, so $\mathrm{red}(w) = w$, completing the proof.

Proposition 2.3.26: Word Group

Let A be a set. The set $F(A)$ of reduced words on A is a group under the operation

$$w \cdot w' = \mathrm{red}(ww')$$

with the empty word as identity. Regard each letter as a reduced word of length 1. Then for every $a \in A$ the letters a and a^{-1} are inverse to each other in $F(A)$, and every reduced word $x_1 x_2 \cdots x_n$ equals the product $x_1 \cdot x_2 \cdots x_n$ in $F(A)$. In particular, every element of $F(A)$ is a product of elements of A and their inverses.

***Proof*:**
By lemma 2.3.25, $\mathrm{red}(ww')$ is a reduced word, so the operation is a binary operation on $F(A)$. Moreover, if $u \to^* u'$ and $v \to^* v'$, then

$$\mathrm{red}(uv) = \mathrm{red}(u'v')$$

Indeed, an elementary reduction inside u or inside v is also an elementary reduction of the concatenation, so $uv \to^* u'v \to^* u'v' \to^* \mathrm{red}(u'v')$. Thus $\mathrm{red}(u'v')$ is a reduced word obtained from uv by elementary reductions, and it equals $\mathrm{red}(uv)$ by the uniqueness in lemma 2.3.25. The axioms of definition 1.1.3 follow:

1. (associativity) Let $u, v, w \in F(A)$. Since $uv \to^* \mathrm{red}(uv)$ and $vw \to^* \mathrm{red}(vw)$, the displayed equality gives

$$(u \cdot v) \cdot w = \mathrm{red}(\mathrm{red}(uv)w) = \mathrm{red}(uvw) = \mathrm{red}(u\,\mathrm{red}(vw)) = u \cdot (v \cdot w)$$

2. (identity) For $w \in F(A)$, $1 \cdot w = \mathrm{red}(w) = w$ and $w \cdot 1 = \mathrm{red}(w) = w$, because w is reduced.

3. (inverses) Let $w = x_1 \cdots x_n \in F(A)$ and $\bar{w} = x_n^{-1} \cdots x_1^{-1}$. Two adjacent letters $x_{k+1}^{-1} x_k^{-1}$ of $\bar{w}$ are formal inverses exactly when $x_{k+1} = x_k^{-1}$, that is, exactly when $x_k x_{k+1}$ is a pair of formal inverses in w. Since w is reduced, this never happens, so $\bar{w} \in F(A)$. In $w\bar{w} = x_1 \cdots x_n x_n^{-1} \cdots x_1^{-1}$, deleting the middle pair n times leaves the empty word, so $w \cdot \bar{w} = \mathrm{red}(w\bar{w}) = 1$. The word obtained from $\bar{w}$ in the same way is w, so the same computation gives $\bar{w} \cdot w = 1$.

So $F(A)$ is a group. For $a \in A$, the case $n = 1$ of (3) says that $a \cdot a^{-1} = a^{-1} \cdot a = 1$. Finally, induction on n shows that a reduced word $x_1 \cdots x_n$ equals the product $x_1 \cdot x_2 \cdots x_n$. For $n = 0$ both sides are the identity. For $n \geq 1$, the word $x_1 \cdots x_{n-1}$ is reduced, being part of a reduced word, and

$$(x_1 \cdots x_{n-1}) \cdot x_n = \mathrm{red}(x_1 \cdots x_n) = x_1 \cdots x_n$$

so the induction hypothesis for $x_1 \cdots x_{n-1}$ completes the proof.

Theorem 2.3.27: Universal Property Of Free Groups

Let A be a set, let $F(A)$ be the group of proposition 2.3.26, and let $i\colon A \to F(A)$ send $a \in A$ to the one-letter word a. For every group G and every function $f\colon A \to G$ there is a unique homomorphism $\varphi\colon F(A) \to G$ such that $f = \varphi \circ i$, that is, such that the following diagram commutes:

$$\begin{array}{ccc} F(A) & \xrightarrow{\varphi} & G \\ {\scriptstyle i}\uparrow & \nearrow_{f} & \\ A & & \end{array}$$

Equivalently, $(i, F(A))$ is an initial object of $\mathfrak{F}^A$: for every object (f, G) of $\mathfrak{F}^A$ there is exactly one morphism $(i, F(A)) \to (f, G)$. The group $F(A)$ is called the *free group* on A.

***Proof*:**

Let G be a group and $f\colon A \to G$ a function. Extend f to the letters by $\hat{f}(a) = f(a)$ and $\hat{f}(a^{-1}) = f(a)^{-1}$ for $a \in A$. Then $\hat{f}(x^{-1}) = \hat{f}(x)^{-1}$ for every letter x: for $x = a$ this is the definition, and for $x = a^{-1}$ it reads $f(a) = (f(a)^{-1})^{-1}$. Define $\Phi\colon W(A) \to G$ by $\Phi(1) = 1_G$ and

$$\Phi(x_1 x_2 \cdots x_n) = \hat{f}(x_1)\hat{f}(x_2)\cdots\hat{f}(x_n)$$

Step 1: Φ respects concatenation and reduction. For words w and w', the definition gives $\Phi(ww') = \Phi(w)\Phi(w')$. If $w = uxx^{-1}v$ and $w \to uv$ is the corresponding elementary reduction, then

$$\Phi(w) = \Phi(u)\hat{f}(x)\hat{f}(x)^{-1}\Phi(v) = \Phi(u)\Phi(v) = \Phi(uv)$$

So Φ is constant along any sequence of elementary reductions, and $\Phi(w) = \Phi(\mathrm{red}(w))$ for every word w (lemma 2.3.25).

Step 2: existence. Let $\varphi\colon F(A) \to G$ be the restriction of Φ to the reduced words. For $w, w' \in F(A)$, Step 1 gives

$$\varphi(w \cdot w') = \Phi(\mathrm{red}(ww')) = \Phi(ww') = \Phi(w)\Phi(w') = \varphi(w)\varphi(w')$$

so φ is a homomorphism. Also $\varphi(i(a)) = \hat{f}(a) = f(a)$ for every $a \in A$, that is, $f = \varphi \circ i$.

Step 3: uniqueness. Let $\varphi'\colon F(A) \to G$ be a homomorphism with $f = \varphi' \circ i$. Then $\varphi'(a) = f(a)$ for $a \in A$. The letter a^{-1} is the inverse of a in $F(A)$ (proposition 2.3.26), so proposition 1.4.4(2) gives $\varphi'(a^{-1}) = f(a)^{-1}$. Hence $\varphi'(x) = \hat{f}(x)$ for every letter x. Every reduced word $w = x_1 \cdots x_n$ is the product $x_1 \cdot x_2 \cdots x_n$ in $F(A)$ (proposition 2.3.26), so

$$\varphi'(w) = \varphi'(x_1)\cdots\varphi'(x_n) = \hat{f}(x_1)\cdots\hat{f}(x_n) = \varphi(w)$$

and $\varphi' = \varphi$.

Finally, a morphism $(i, F(A)) \to (f, G)$ in $\mathfrak{F}^A$ is by definition a homomorphism $\varphi\colon F(A) \to G$ with $f = \varphi \circ i$. Steps 2 and 3 therefore say that there is exactly one such morphism, so $(i, F(A))$ is an initial object of $\mathfrak{F}^A$, as we sought to show.

Corollary 2.3.28: Free Group Is Unique

Let A and B be sets such that $|A| = |B|$. Then

$$F(A) \cong F(B)$$

***Proof*:**
Since $|A| = |B|$, there is a bijection $\beta\colon A \to B$. Let $i_A\colon A \to F(A)$ and $i_B\colon B \to F(B)$ be the maps of theorem 2.3.27. Applying theorem 2.3.27 to the function $i_B \circ \beta\colon A \to F(B)$ gives a homomorphism $\varphi\colon F(A) \to F(B)$ with $\varphi \circ i_A = i_B \circ \beta$. Applying it to $i_A \circ \beta^{-1}\colon B \to F(A)$ gives a homomorphism $\psi\colon F(B) \to F(A)$ with $\psi \circ i_B = i_A \circ \beta^{-1}$. The composite $\psi \circ \varphi\colon F(A) \to F(A)$ is a homomorphism (proposition 1.4.4(6)), and

$$\psi \circ \varphi \circ i_A = \psi \circ i_B \circ \beta = i_A \circ \beta^{-1} \circ \beta = i_A$$

The identity homomorphism of $F(A)$ also satisfies $\mathrm{id}_{F(A)} \circ i_A = i_A$. The uniqueness in theorem 2.3.27, applied to the function $i_A\colon A \to F(A)$, therefore gives $\psi \circ \varphi = \mathrm{id}_{F(A)}$. Exchanging the roles of A and B gives $\varphi \circ \psi = \mathrm{id}_{F(B)}$ in the same way. So φ is a bijective homomorphism, and $F(A) \cong F(B)$ (definition 1.4.12), as claimed.

Since free groups on sets of the same cardinality are isomorphic, we usually write F_n to denote the free group with n generators.

Definition 2.3.29: Freely Generated

Let G be a group and $S \subseteq G$. We say that S *freely generates* G, or that G is *free on* S, if the inclusion of S in G has the universal property of theorem 2.3.27: for every group H and every function $f\colon S \to H$ there is a unique homomorphism $\varphi\colon G \to H$ with $\varphi(s) = f(s)$ for every $s \in S$. By theorem 2.3.27, $F(S)$ is free on its one-letter words, identified with the elements of S.

Example 2.3.30: Free Groups

1. Let $A = \{a\}$. By theorem 2.3.27, the function $f\colon A \to \mathbb{Z}$ with $f(a) = 1$ extends to a homomorphism $\varphi\colon F(A) \to \mathbb{Z}$ with $\varphi(a) = 1$. A reduced word on A has no two adjacent letters aa^{-1} or $a^{-1}a$, so all of its letters are equal: it is the empty word, the letter a repeated $m \geq 1$ times, or the letter a^{-1} repeated $m \geq 1$ times. By proposition 2.3.26, the word a repeated m times is the power a^m in $F(A)$, so φ sends it to $m\varphi(a) = m$ (proposition 1.4.4(3)). In the same way the word a^{-1} repeated m times goes to $-m$, and the empty word goes to 0. So φ is a bijective homomorphism, and

$$F(A) \cong \mathbb{Z}$$

2. The free group on 2 elements, $F(\{x, y\})$, can be pictured through part of its Cayley graph (definition 1.6.1) with respect to $\{x, y\}$:




Figure 2.1: Cayley Graph of F_2

The graph is infinite, and the edges are drawn shorter at each step away from the identity so that the picture fits on the page. [a]

[a] If you have done any algebraic topology, this is the fundamental group of the figure 8!

2.3.4 Free Abelian Group

We can repeat this same construction, except limit our attention to abelian groups. In particular, given a set A an any map $f : A \to G$ to an abelian group, we want to lift it to an abelian group $F^{ab}(A)$ in the domain of the homomorphism $\varphi : F^{ab}(A) \to G$.

The construction is identical if we impose a commutativity condition on $F(A)$, that is, for any $a, b \in F^{ab}(A)$, $ab = ba$. If you were uncomfortable with the proof of the universal property of free group, it is worth going over it again, then go over it a 2nd time but with only abliean groups and $F^{ab}(A)$ in mind.

What we will be focusing on this section is finding a nicer group that is isomorphic to $F^{ab}(A)$.

In theorem 2.3.27 the universal map $i\colon A \to F(A)$ is an inclusion. A universal map need not be injective: the bilinear map $M \times N \to M \otimes_R N$ of chapter 15 sends $(m, 0)$ and $(0, n)$ to 0 for all $m \in M$ and $n \in N$.

2.3.5 *Free-Forgetful Adjoint

Is this the right place to ask this question? It's asking whether we have really defined the "right" idea of general group. The way we make this idea rigorous is by asking if we have a functor F : **Group** $\to$ **Set**, that forgets the structure, is there a functor G : **Set** $\to$ **Group** that "regains" some structure? It cannot regain all of it because sets do not have enough information for that, but is there a way in which we can make sure that our free construction is the "mirror-image" of

forgetting the structure?

Build up to this: If $L(_) : \mathbf{Group} \to \mathbf{Set}$ takes a group G and returns the underlying set: $\mathcal{L}((G,\cdot)) = G$, and $\mathcal{F}(_) : \mathbf{Set} \to \mathbf{Group}$ takes a set and returns a group: $\mathcal{F}(S) = ((F(S), \cdot_{F(S)})$, then

$$\mathrm{Hom}_{\mathbf{Set}}(S, \mathcal{L}(G)) \cong_{\mathbf{Set}} \mathrm{Hom}_{\mathbf{Group}}(\mathcal{F}(S), G)$$

where we there is $\cong_{\mathbf{Set}}$ in the middle because Hom_{Set} does not have a group structure. If it did, we would ask it to preserve that too.

Exercise 2.3.2

1. Let $G = \langle a, b\rangle$ be the free (non-abelian) group generated on two elements. Show that $H = \langle a^n b a^{-n} \mid n \in \mathbb{Z}\rangle$ is an infinitely generated subgroup
2. (harder) Let $G + \mathrm{SL}_2(\mathbb{Z})$. Show it contains a subgroup isomorphic to the free subgroup with two elements.

2.4 Subgroup Lattices

In this section, we will show how to use graphs in order to visually see the subgroup structure of a group.

Before introducing a rigorous definition, let's first do an example: Let's do the subgroup lattice of Q_8. We must first know all the subgroups of Q_8. With some computation, the subgroups that are found are

$$1,\ \langle -1\rangle,\ \langle i\rangle,\ \langle j\rangle,\ \langle k\rangle,\ Q_8$$

where $1 = \{e\}$. By the definition of Q_8, any other set of generators will fall into these groups. For example, $\langle i, j\rangle = Q_8$, since it contains $k = ij$ and hence all eight elements (similarly for i, k and j, k). To construct the lattice, start by imagining Q_8 on the "top" and the identity group on the "bottom"‘

$$Q_8$$

$$1$$

then, apply the first rule of doing the lattice:

1. draw a line if one group is a subgroup of another group.


Since $1 \leqslant Q_8$, then

$$\begin{array}{c} Q_8 \\ | \\ 1 \end{array}$$

Next, pick one of the groups, let's say it's $\langle -1\rangle$. Now apply the second rule of drawing a lattice:

2. if $H \subsetneq K \subsetneq G$, then remove the line from H to G (if one is already drawn) and add a line from H to K, and K to G. In other words, only draw a line between subgroups $A \subsetneq B$ if and only if there is no group H such that $A \subsetneq H \subsetneq B$.


Since $1 \leqslant \langle -1 \rangle \leqslant Q_8$, our diagram will now look like this:



similarly, we can add $\langle i \rangle$ like so:



Next, notice that $\langle i \rangle \not\leqslant \langle j \rangle$, and $\langle j \rangle \not\leqslant \langle i \rangle$, however both $\langle i \rangle$ and $\langle j \rangle$ have $\langle -1 \rangle$ as a subgroup and are both subgroups of Q_8. The same situation occurs for $\langle k \rangle$. Thus, the updated lattice will be:



since we have exhausted our list of possible subgroups, we have finished the subgroup lattice of Q_8.

More generally, the orientation does not matter (we could've had 1 on top and Q_8 on bottom, or going from left to right). What matter's is we know how to translate a line into an appropriate subgroup (i.e. If 1 is on top and Q_8 is on bottom, then a line now becomes a supergroup inclusion $H \geqslant G$). Note also that the particular shape the lattice took does not really matter, a pretty diamond-like shape was chosen to make the lattice more readable.

If G is infinite, the lines of such a diagram need not record which subgroups contain which. In $G = \mathbb{Q}$, every nonzero subgroup H contains a subgroup strictly between 0 and H: if $0 \neq x \in H$, then $\langle 2x \rangle$ is nonzero and does not contain x. So no subgroup of $\mathbb{Q}$ is joined to 0 by a line. Thus, we usually work with finite groups.


With this build-up, we can formally define a subgroup lattice:

Definition 2.4.1: Group Lattice

Let G be a finite group and $\mathcal{G}$ be the collection of subgroups of G. Then $\Gamma = (\mathcal{G}, E_{\leqslant})$ is the graph where there is an edge between $A, B \in \mathcal{G}$ if and only if $A \subsetneq B$ and there is no subgroup K with $A \subsetneq K \subsetneq B$. When Γ is visualized, we put G on top and the identity group 1 on bottom.


Example 2.4.2: Group Lattices

1. Let $G = \mathbb{Z}/n\mathbb{Z}$. By theorem 2.3.11(3), the subgroups of G correspond to the positive divisors of n. For $n = 2, 4, 8$ the lattices are:




   Note that $\mathbb{Z}/2\mathbb{Z} = \langle 1 \rangle$, or $\mathbb{Z}/4\mathbb{Z} = \langle 1 \rangle = \langle 3 \rangle$, or that $\mathbb{Z}/8\mathbb{Z} = \langle 1 \rangle = \langle 3 \rangle = \langle 5 \rangle = \langle 7 \rangle$

2. More generally, if $G = \mathbb{Z}/p^n\mathbb{Z}$, then




3. If $G = \mathbb{Z}/n\mathbb{Z}$ where n is a non-prime power, we can get some interesting diagram. For

example:



4. Let $G = V_4$, the Klein 4-group of example 1.4.14, and put $c = ab$. Then



This lattice differs from that of Q_8 above, where $\langle -1 \rangle$ lies below all three of $\langle i \rangle$, $\langle j \rangle$ and $\langle k \rangle$. Isomorphic groups have the same lattice, but the converse fails: $\mathbb{Z}/2\mathbb{Z}$ and $\mathbb{Z}/3\mathbb{Z}$ both have the lattice consisting of 0 below the whole group, and they are not isomorphic.

Theorem 2.4.3: Subgroup And Sublattices

Let G be a finite group and $H \leqslant G$. Then the lattice of H is the sublattice of G of groups contained in H: its vertices are the subgroups of G contained in H, and two of them are joined by an edge in the lattice of H exactly when they are joined by an edge in the lattice of G.

***Proof*:**
Since G is finite, so is H, and both lattices are defined (definition 2.4.1). The inclusion $H \to G$ is a homomorphism by proposition 1.4.8, so by proposition 1.4.4(1) and (2) the identity of H is the identity of G, and the inverse in H of each $y \in H$ is its inverse in G.

Step 1: the vertices. Let $K \subseteq H$. The conditions of proposition 2.1.3, that $K \neq \emptyset$ and $xy^{-1} \in K$ for all $x, y \in K$, mean the same thing whether y^{-1} and the product are computed in H or in G. So K is a subgroup of H exactly when it is a subgroup of G. Hence the vertices of the lattice of H are the subgroups of G contained in H.

Step 2: the edges. Let $K \subsetneq L$ be subgroups of H. A subgroup M of G with $K \subsetneq M \subsetneq L$ is contained in H, so it is a subgroup of H by Step 1. Conversely, every subgroup of H is a subgroup of G. So the subgroups lying strictly between K and L are the same in H as in G. By the definition of the edges in definition 2.4.1, K and L are joined in the lattice of H exactly when they are joined in the lattice of G, as we sought to show.

Example 2.4.4: Sublattices Of Subgroups

1. Let $H = \langle i \rangle = \{1, -1, i, -i\} \leqslant Q_8$. Of the subgroups 1, $\langle -1 \rangle$, $\langle i \rangle$, $\langle j \rangle$, $\langle k \rangle$ and Q_8 found at the start of this section, those contained in H are 1, $\langle -1 \rangle$ and $\langle i \rangle$, since $j, k \notin H$. In the lattice of Q_8, the edges among these three join 1 to $\langle -1 \rangle$ and $\langle -1 \rangle$ to $\langle i \rangle$. By theorem 2.4.3, the lattice of $\langle i \rangle$ is the chain $1 \leqslant \langle -1 \rangle \leqslant \langle i \rangle$, which has the shape of the lattice of $\mathbb{Z}/4\mathbb{Z}$ in example 2.4.2.
2. Let $H = \langle 2 \rangle \leqslant \mathbb{Z}/20\mathbb{Z}$, a subgroup of order 10. In the lattice of $\mathbb{Z}/20\mathbb{Z}$ drawn in example 2.4.2, the subgroups contained in $\langle 2 \rangle$ are $\langle 2 \rangle$, $\langle 4 \rangle$, $\langle 10 \rangle$ and 0, while $\langle 5 \rangle$ is not, since $5 \notin \langle 2 \rangle$. The edges among these four join $\langle 2 \rangle$ to $\langle 4 \rangle$ and to $\langle 10 \rangle$, and each of these to 0. By theorem 2.4.3, the lattice of $\langle 2 \rangle$ is a square with $\langle 2 \rangle$ at the top and 0 at the bottom.

If $\varphi\colon G \to H$ is a homomorphism of finite groups, then $\varphi(G) \leqslant H$ (proposition 1.4.4(5)), so by theorem 2.4.3 the lattice of $\varphi(G)$ is the part of the lattice of H below $\varphi(G)$. How it relates to the lattice of G is answered by the fourth isomorphism theorem (theorem 3.5.7).

2.4.5 Foreshadowing The answer is "dual" to theorem 2.4.3: the lattice of $\varphi(G)$ has the same shape as the part of the lattice of G above the kernel $\ker(\varphi)$, that is, the lattice of subgroups of G *containing* $\ker(\varphi)$ (chapter 3).

Exercise 2.4.1

1. Draw the subgroup lattices of $\mathbb{Z}/12\mathbb{Z}$ and of S_3.


2.5 *Universal Property of the Kernel

No later result in this book depends on this section. The kernel of a homomorphism is characterized by a universal property, and that property describes kernels well beyond groups: kernels and cokernels of module homomorphisms (definition 12.2.12) form the exact sequences of chapter 17⋆, and the cohomology of a complex, a kernel modulo an image (chapter 56), is what the derived category is built to preserve (chapter 57).


In the following seciton, $0 : G \to H$ will represent the homomorphism $\varphi(G) = e_H [= 0]$. This is indeed a homomorphism (as we have seen in proposition 1.4.5).

Theorem 2.5.1: Universal Property Of The Kernel


Let $\varphi : G \to H$ be a homomorphism. Then the inclusion map $i : \ker(\varphi) \hookrightarrow G$ is the final object in the category of group homomorphisms $\alpha : K \to G$ such that $\varphi \circ \alpha$ is the trivial map. In other words, every group homomorphism $\alpha : K \to G$ such that $\varphi \circ \alpha$ is trivial factors through i:



Let $\mathcal{C}_\varphi$ be the category whose objects are the pairs (K, α) of a group K and a homomorphism $\alpha : K \to G$ such that the following diagram commutes:



If (K, α) and (J, β) are two objects in this category, define the morphism $\gamma : (K, \alpha) \to (J, \beta)$ to be a homomorphism from K to J such that



commutes.

***Proof*:**
Let $\alpha : K \to G$ such that $\varphi \circ \alpha = 0$, that is

$$\varphi(\alpha(K)) = 0$$

then $\alpha(K) \subseteq \ker(\varphi)$. The inclusion i is itself an object, as $\varphi \circ i$ is trivial. A homomorphism $\alpha' \colon K \to \ker(\varphi)$ with

$$\alpha = i \circ \alpha'$$

must send each k to $\alpha(k)$, so α' is α with its codomain restricted to $\ker(\varphi)$. That map is a homomorphism, which gives existence, and it is the only candidate, which gives uniqueness.

The dual statement, the universal property of the cokernel, needs quotient groups and is theorem 3.2.8.

3

Homomorphisms and Quotient Groups

In this chapter, we take a closer look at homomorphisms and how they relate different groups. We start our exploration by getting a better understanding of the image of a homomorphism. For example, if $\varphi : G \to H$ is a homomorphism, then we saw that $\varphi(G)$ is a group (re-prove this if it is not clear). Since φ is a function, then as we saw in [43] we can define $(G/\sim_\varphi)$ which is bijective to $\varphi(G)$ (in particular, $x \sim_\varphi y \Leftrightarrow \varphi(x) = \varphi(y)$), In particular, using equivalence classes:

$$[g] \mapsto \varphi(g)$$

The collection $(G/\sim_\varphi)$ is called the *fibers* of φ[1]. Since there is a bijection between $\varphi(G)$ and $(G/\sim_\varphi)$, and $\varphi(G)$ is a group, can we define a group structure on $(G/\sim_\varphi)$? Furthermore, is there some "minimal" and "unique" group structure that we can put on $(G/\sim_\varphi)$ so that there is a cannonical identification between $\varphi(G)$ and $(G/\sim_\varphi)$? Those comfortable with the category theory presented so far will recognize this as asking for the universal properties of quotient objects in the category **Grp**. Due to this universal property, the name of the group structure on $(G/\sim_\varphi)$ satisfying the universal property will be the *quotient group*. The exploration of this question is at the center of the first section of this chapter. Due to the axioms of groups, it will turn out that there is a lot of "regularity" in the collection of fibers which allow for an easy representation of $(G/\sim_\varphi)$.

After finishing the first part, we will have developed the appropriate tools to get back to what we started in section 1.3 and define these notions more formally, i.e., how do we impose relations on groups.

For the rest of the chapter, we will use our new theory to give us some very powerful results. We will see that when working with finite groups, the order of the group will give us a lot of information about it's subgroup structure, we will use our understanding of quotient groups to learn how to


[1] Given $\varphi : G \to H$ and an element $h \in H$, the fiber of h is all elements that map to h by φ

build some new types of groups, and we will learn 4 isomorphism theorems which give us lots of information on group structure.

We will end this chapter by introducing one of the most fundamental classification theorem in finite group theory: *Jordan Hölder's Program*. In the last few section, we will show how there are groups that can be considered the "building blocks" of any other finite groups, and show how we can put these groups together to form other groups.

3.1 Quotient Groups

Let $\varphi : G \to H$ be a homomorphism. We start by exploring the structure of $\varphi(G)$. Since $\varphi(G)$ is a set, we know by proposition 0.1.28 in the preliminary chapter that there is a bijection between $G/\sim_\varphi$ and $\varphi(G)$ such that for any function $\varphi : G \to H$ where $a \sim b \Leftrightarrow \varphi(a) = \varphi(b)$, we have



We now try to see if there is an equivalent universal property for quotients in **Grp**. To that end, we would then want $G \xrightarrow{\pi} G/\sim$ to be a homomorphism, that is

$$\pi(a \cdot b) = \pi(a) \bullet \pi(b)$$

or, written in terms of equivalence relations,

$$[a \cdot b] = [a] \bullet [b]$$

We would need to have that $\bullet$ is independent of representation. That is, if we have $x, y \in [a]$, then we want

$$x \sim y \Leftrightarrow xb \sim yb \tag{3.1}$$

since we would also want that

$$[b \cdot a] = [b] \bullet [a]$$

we must have that

$$x \sim y \Leftrightarrow bx \sim by \tag{3.2}$$

These are necessary condition in order for $(G/\sim, \bullet)$ to be a group, since if once of these condition's fail, then we will not have a group. For examle, if $x \sim y \not\Rightarrow xb \sim yb$, then $[x][b] \neq [xb]$.

These are necessary conditions, since if $G/\sim$ was a group, then these must hold. We can ask if they are sufficient conditions, that is, condition's such that if they are followed, then $(G/\sim, \bullet)$ must be a group. These two condition's are also sufficient, meaning defining a group structure on $G/\sim$ is equivalent to the equivalence relation respecting these two properties:

Theorem 3.1.1: $(G/\sim,\cdot)$ is the quotient object of Grp

Let G be a group and $G/\sim$ be the set of equivalence relations given $\sim$. Then $G/\sim$ is a group under $\cdot$ if and only if

$$\forall g \in G,\ (x \sim y \Leftrightarrow gx \sim gy \text{ and } xg \sim yg)$$

Furthermore, If $\varphi : G \to H$ is another homomorphism such that $g \sim g' \Rightarrow \varphi(g) = \varphi(g')$, then there exists a homomorphism φ such that the following diagram commutes:

$$\begin{array}{ccc} G/\sim & \xrightarrow{\varphi} & H \\ {\scriptstyle\pi}\uparrow & \nearrow_{\varphi} & \\ G & & \end{array}$$

We say that $\sim$ is *compatible* with the group-structure on G

***Proof*:**
The proof of the $\Rightarrow$ direction we have just showed above the theorem, so we will show that these two equivalence relations are sufficient conditions for to define $(G/\sim,\cdot)$.

First, note that the operation $\cdot : G/\sim \times G/\sim \to G/\sim$ $[a]\cdot[b] = [ab]$ is well-defined, since if we take any other two representative $a' \in [a]$ and $b' \in [b]$, then since

$$b \sim b' \Leftrightarrow ab \sim ab' \text{ and } a'b \sim a'b'$$

and

$$a \sim a' \Leftrightarrow ab \sim a'b \text{ and } ab' \sim a'b'$$

Thus, putting pieces together using transitivity, we get

$$ab \sim ab' \sim a'b' \text{ or } ab \sim a'b \sim a'b'$$

both showing that $ab \sim a'b'$, meaning $\cdot$ is well-defined. Next, we need to show that $(G/\sim,\cdot)$ is indeed a group

1. Let $[a],[b],[c] \in G/\sim$. Then

$$\begin{aligned} ([a][b])[c] &= ([ab])[c] \\ &= [(ab)][c] \\ &= [(ab)c] \\ &= [a(bc)] \\ &= \vdots \\ &= [a]([b][c]) \end{aligned}$$

2. I claim that $[e_G] \in G/\sim$ is the identity. For any $[g] \in G/\sim$,

$$[g][e_G] = [ge_G] = [g] = [e_G g] = [e_G][g]$$

as we sought to show

3. Finally, for any $[g] \in G/\sim$, I claim that $[g]^{-1} = [g^{-1}]$. Indeed:

$$[g][g^{-1}] = [gg^{-1}] = [e_G]$$

showing that $[g^{-1}]$ is indeed the inverse of G

Thus, $(G/\sim, \bullet)$ is indeed a group.

Finally, we must show that G is universal with respect to homomorphisms $\varphi : G \to G'$ such that $g \sim g' \Rightarrow \varphi(g) = \varphi(g')$. Note that we already have that such a function exists, since φ is also a set function, so we already have that there exists a unique set-funciton $\varphi : G/\sim \to G'$ such that $\varphi([g]) = \varphi(g)$. Thus, we only need to check that φ is a homomorphism. We get this pretty much be definition:

$$\varphi([a][b]) = \varphi([ab]) = \varphi(ab) = \varphi(a)\varphi(b) = \varphi([a])\varphi([b])$$

showing that φ is indeed a homomorphism, and must be unique since there is only one possible set function (and hence homomorphism) that satisfies this property (there are no more functions to check).

Since $\bullet$ is the unique structure on $G/\sim$ that respects the universal property, we will drop it without risk of confusion, and write

$$[a][b] = [ab]$$

Definition 3.1.2: Quotient Group Via Congruence Relation

Let G be a group and $\varphi : G \to H$ a group homomorphism giving the induced equivalence relation $\sim_\varphi$. Then the group $G/\sim_\varphi$ from theorem 3.1.1 is called a *quotient group* and the equivalence relation $\sim_\varphi$ is called a *congrunce relation.*

By theorem 3.1.1, the equivalence relations whose quotient is a group are exactly those respecting both (3.2) and (3.1). Property (3.2) alone already forces the class of e_G to be a subgroup whose left cosets are the other classes:

Proposition 3.1.3: Equivalence Classes Using property (3.2)

Let $G/\sim$ be a quotient set given $\sim$ with proprety (3.2). Then

1. The equivalence class $K \in G/\sim$ where $e_G \in K$ is a subgroup of G ($K \leqslant G$)
2. Given any other equivalence calss $[g] \in G/\sim$, for any $a, b \in [g]$

$$a \sim b \iff a^{-1}b \in K \iff aK = bK$$

where the $aK = \{ak \mid k \in K\}$ and $bK = \{bk \mid k \in K\}$

***Proof*:**

1. Let $a, b \in K$, so that $e_G \sim a$ and $e_G \sim b$. Left multiplication by a^{-1} (property (3.2)) turns these into $a^{-1} \sim e_G$ and $a^{-1} \sim a^{-1}b$, so $a^{-1}b \sim e_G$ by symmetry and transitivity, that is,

$a^{-1}b \in K$. Taking $b = e_G$ gives $a^{-1} \in K$, and applying this to a^{-1} and b gives $ab \in K$. Since $e_G \in K$, K is a subgroup of G. With (3.1) in place of (3.2), right multiplication gives $ba^{-1} \in K$ instead.

2. Let $[g]$ be an equivalence class and $a, b \in [g]$ so that $a \sim b$.

   Since $\sim$ respects (3.2) $a^{-1}b \sim e_G$, implying $a^{-1}b \in K$. Next, take any element $x \in a^{-1}bK$. Then $x = a^{-1}bk$. Next, since $a^{-1}b \in K$ and $k \in K$, $x \in K$. Thus, $a^{-1}bK \subseteq K$. This implies that $bK \subseteq aK$, since if $x \in bK$, then $x = bk$, and so $x = a(a^{-1}bk)$, and since $a^{-1}b \in K$ and $k \in k$, we get $x = ak'$ for some $k' = a^{-1}bk \in K$, an so $x \in aK$. Using symmetry of $\sim$, we will get that $aK \subseteq bK$, implying $aK = bK$. Thus, we showed that

   $$a \sim b \Rightarrow a^{-1}b \in K \Rightarrow aK = bK$$

   Note that if we were using property (3.1), then we would get $Ka = Kb$, since we would be multiplying on the right.

   To make this chain of implication go full circle, assume $aK = bK$. Then $a = ae_G \in bK$, so $a = bk$ for some $k \in K$, and $b^{-1}a = k \in K$, that is, $e_G \sim b^{-1}a$. Left multiplication by b (property (3.2)) gives $b \sim a$. So $aK = bK \Rightarrow a \sim b$, completing the loop of implication, thus showing that

   $$a \sim b \Leftrightarrow a^{-1}b \in K \Leftrightarrow aK = bK$$

   as we sought to show

This shows that for any equivalence relation satisfying (3.2) (respectively (3.1)), the equivalence classes are the sets aK (respectively Ka), where a is a representative of the class and K is the class containing e_G. So the subgroup K determines every equivalence class of $G/\sim$.

Corollary 3.1.4: Quotient Set Size

Let G be a group, let $\sim$ be an equivalence relation on G satisfying (3.2) (respectively (3.1)), and let K be the class of e_G. Then every class has as many elements as K:

$$|aK| = |K| \qquad \text{(respectively } |Ka| = |K|\text{)} \qquad \forall a \in G$$

***Proof*:**
For $a \in G$, the map $K \to aK$ given by $k \mapsto ak$ is a bijection, with inverse $x \mapsto a^{-1}x$. Hence $|aK| = |K|$ for every $a \in G$. For the classes Ka the map $k \mapsto ka$ gives $|Ka| = |K|$ in the same way, completing the proof.

Since these cosets represent our equivalence relations, we will give a special name to these quotient sets:

Definition 3.1.5: Cosets

Let $H \leqslant G$. Then for every $g \in G$, we can define

$$gH = \{gh | h \in H\}$$

we call this a [left]-***coset***. We can also define the ***right***-coset:

$$Hg = \{hg | h \in H\}$$

If additive notation is used for G ($(G, +)$), it is common to denote the coset as

$$g + H \qquad H + g$$

The set of left-cosets is represented as G/H, an the set of right-cosets is represented as $G \setminus H$.

Does every subgroup arise as the class of e_G of an equivalence relation satisfying (3.2)? In other words, is there a converse to proposition 3.1.3(1), which states that if $\sim$ respects property (3.2) (or (3.1)), then the equivalence class containing e_G is a subgroup? The answer is yes:

Proposition 3.1.6: Subgroups And Equivalence Classes

Let $H \leqslant G$ be a subgroup of G. Define the equivalence relation

$$a \sim_L b \Leftrightarrow a^{-1}b \in H$$

then $\sim_L$ respects property (3.2)

***Proof*:**
Let's first show that $\sim_L$ is indeed an equivalence relation

1. If $a \sim a$, then $a^{-1}a = e \in H$, which is the case since H is a group
2. Let $a \sim b$. Then $a^{-1}b \in H$, implying $(a^{-1}b)^{-1} = b^{-1}a \in H$, implying $b \sim a$
3. Let $a \sim b$ and $b \sim c$. Then $a^{-1}b, b^{-1}c \in H$. Then $a^{-1}bb^{-1}c = a^{-1}c \in H$, implying $a \sim c$.

Thus, $\sim_L$ is indeed an equivalence relation.
To show it satisfies property (3.2), notice that for any $g \in G$

$$a \sim b \to a^{-1}b \in Ha^{-1}(g^{-1}g)b \in H \Rightarrow (ga)^{-1}gb \in H \Rightarrow ga \sim_L gb$$

showing that $\sim_L$ satisfies property (3.2)

This proposition shows that any subgroup of H will define an equivalence relation $\sim_L$ respecting property (3.2), and thus by proposition 3.1.3(2) partition G (even better, equally partition G due to corollary 3.1.4). Similarly, we can show that the relatoin $a \sim_R b \Leftrightarrow ab^{-1} \in H$ gives an equivalence relation which satisfies property (3.1). Note that since H partitioned G, only $eH = H$ is a subgroup of G since only it contains the identity.

Combining propositions 3.1.3 and 3.1.6 we get the following one to one correspondence:

$$\{H|H \leqslant G\} \leftrightarrow \left\{ \begin{array}{c} \text{equivalence relations } \sim_L \\ \text{on } G \text{ satisfying} \\ \text{property (3.2)} \end{array} \right\}$$

Similarly:

$$\{H|H \leqslant G\} \leftrightarrow \left\{ \begin{array}{c} \text{equivalence relations } \sim_R \\ \text{on } G \text{ satisfying} \\ \text{property (3.1)} \end{array} \right\}$$

This shows that the subgroups of G give us all possible such equivalence relations, that is all one-sided congruence relations. Because of this, we can without ambiguity write G/H to represent $G/\sim$ with an equivalence relation $\sim$ satisfying property (3.2), and similarly for $G \setminus H$.

Is the partition G/H into left cosets always the same as the partition $G \setminus H$ into right cosets, and does $\sim_L$ also satisfy property (3.1)? The answer to both is no:

3.1.7 counter-example Take $G = D_3$. Then $H = \langle\sigma\rangle$ is a subgroup, and has left cosets $eH(=H), rH, r^2H$. giving us

$$\{e, \sigma\}, \{r, r\sigma\}, \{r^2, r^2\sigma\}$$

and the right-cosets are

$$\{e, \sigma\}, \{r, \sigma r\}, \{r^2, \sigma r^2\}$$

using the fact that $r\sigma = \sigma r^2$ and $r^2\sigma = \sigma r$, we can re-write the right cosets as

$$\{e, \sigma\}, \{r, r^2\sigma\}, \{r^2, r\sigma\}$$

showing that they partition G differently than the left cosets!
This means that $\sim_L$ defined by H does not respect property (3.1). If it did, then

$$r \sim_L r\sigma \Rightarrow r(r\sigma)^{-1} = r\sigma r^2 = rr\sigma \in H$$

however, $r^2\sigma \notin H$, showing that it does not satify the propety

Remember that we showed in theorem 3.1.1 that *both* the properties need to be satisfied in order for G/H to be a group. Since every $\sim$ with these properties corresponds to a subgroup H, it will come down to a special subgroup H which has both properties. The property is the normality of definition 2.2.10.

Proposition 3.1.8: When H Induces Both $\sim_L$ And $\sim_R$

Let $H \leqslant G$, and let $a \sim_L b \Leftrightarrow a^{-1}b \in H$ and $a \sim_R b \Leftrightarrow ab^{-1} \in H$. The relations $\sim_L$ and $\sim_R$ induce the same cosets corresponding to H, that is, they have the same equivalence classes, if and only if H is normal in the sense of definition 2.2.10, that is, $gHg^{-1} = H$ for every $g \in G$. Both conditions are equivalent to $gH = Hg$ for every $g \in G$.

***Proof*:**
For $a \in G$, the $\sim_L$-class of a is $\left\{b \in G \;\middle|\; a^{-1}b \in H\right\} = aH$. Since $ab^{-1} = h$ holds exactly when $b = h^{-1}a$, and $h \mapsto h^{-1}$ is a bijection of H onto itself, the $\sim_R$-class of a is $\left\{b \in G \;\middle|\; ab^{-1} \in H\right\} = Ha$.

If $\sim_L$ and $\sim_R$ have the same classes, then for each $g \in G$ the sets gH and Hg are classes of one partition of G, and both contain g, so $gH = Hg$. Conversely, if $gH = Hg$ for every $g \in G$, then every element of G has the same class under $\sim_L$ as under $\sim_R$, so the two relations have the same classes.

If $gH = Hg$, then $gHg^{-1} = (Hg)g^{-1} = H$. Conversely, if $gHg^{-1} = H$, then $gH = (gHg^{-1})g = Hg$. So $gH = Hg$ for every $g \in G$ exactly when $gHg^{-1} = H$ for every $g \in G$, completing the proof.

Definition 3.1.9: Normal Subgroup

Let $H \leqslant G$ such that $aH = Ha$ for every $a \in G$. Then H is a normal subgroup, written $H \trianglelefteq G$

We have already encountered normal subgroups before

Example 3.1.10: Normal Subgroups

1. for any group G, $Z(G) \leqslant G$. Take any $y \in G$ and $x \in Z(G)$. Then by definition of $Z(G)$, $yx = xy \in Z(G)y$, so $yZ(G) \subseteq Z(G)y$, and in the same way $Z(G)y \subseteq yZ(G)$, showing that $Z(G)$ is normal
2. for any homomorphism $\varphi\colon G \to H$, the kernel $\ker(\varphi)$ is normal in G (proposition 2.2.12)

Proposition 3.1.11: properties of normal sub-groups

Let N be a subgroup of a group G. Then the following are equivalent:

1. $N \trianglelefteq G$ (definition 3.1.9)
2. $N_G(N) = G$
3. $gN = Ng$ for all $g \in G$
4. the rule $(aN)(bN) = (ab)N$, which is the operation $\cdot$ of theorem 3.1.1 for the relation $\sim_L$ whose classes are the left cosets, is well defined on the set G/N of left cosets of N (definition 3.1.5), that is, $aN = a'N$ and $bN = b'N$ imply $(ab)N = (a'b')N$, and it makes G/N a group
5. $gNg^{-1} \subseteq N$ for all $g \in G$

***Proof*:**
For $m \in N$ we have $mN = N$, since $mN \subseteq N$ by closure and $N = m(m^{-1}N) \subseteq mN$.

(1) $\Leftrightarrow$ (3) This is definition 3.1.9.

(3) $\Rightarrow$ (5) Let $g \in G$ and $n \in N$. Then $gn \in gN = Ng$, so $gn = n'g$ for some $n' \in N$, and $gng^{-1} = n' \in N$.

(5) $\Rightarrow$ (2) Let $g \in G$. By (5), $gNg^{-1} \subseteq N$, and by (5) for g^{-1}, $g^{-1}Ng \subseteq N$. Hence $N = g(g^{-1}Ng)g^{-1} \subseteq gNg^{-1}$, so $gNg^{-1} = N$ and $g \in N_G(N)$ (definition 2.2.10). So $N_G(N) = G$.

(2) $\Rightarrow$ (3) Let $g \in G$. By (2), $g \in N_G(N)$, so $gNg^{-1} = N$ and $gN = (gNg^{-1})g = Ng$.

(5) $\Rightarrow$ (4) Suppose $aN = a'N$ and $bN = b'N$. Since $a' \in a'N = aN$ and $b' \in b'N = bN$, we may write $a' = an_1$ and $b' = bn_2$ with $n_1, n_2 \in N$. Then

$$a'b' = an_1bn_2 = ab(b^{-1}n_1b)n_2$$

and $m = (b^{-1}n_1b)n_2 \in N$, because $b^{-1}n_1b \in N$ by (5) for $g = b^{-1}$. So $(a'b')N = (ab)mN = (ab)N$, and the operation is well defined. It is associative, since $((aN)(bN))(cN) = ((ab)c)N = (a(bc))N = (aN)((bN)(cN))$. The coset $eN = N$ is an identity, since $(eN)(aN) = aN = (aN)(eN)$, and $a^{-1}N$ is an inverse of aN, since $(aN)(a^{-1}N) = eN = (a^{-1}N)(aN)$. So G/N is a group.

(4) $\Rightarrow$ (5) Let $g \in G$ and $n \in N$. Then $nN = N = eN$, so computing $(nN)(g^{-1}N)$ with the representatives n, g^{-1} and with e, g^{-1} gives $(ng^{-1})N = g^{-1}N$ by well-definedness. Hence $ng^{-1} \in g^{-1}N$, so $ng^{-1} = g^{-1}n'$ for some $n' \in N$, and $gng^{-1} = n' \in N$.

Together with (1) $\Leftrightarrow$ (3), the cycle (3) $\Rightarrow$ (5) $\Rightarrow$ (2) $\Rightarrow$ (3) and the equivalence (4) $\Leftrightarrow$ (5) show that all five conditions are equivalent, as claimed.

Corollary 3.1.12: Subgroups Of Abelian Groups Are Normal

If G is abelian and $H \leqslant G$, then $H \trianglelefteq G$.

***Proof*:**
Let $g \in G$. Since $gh = hg$ for every $h \in H$, $gH = \{gh \mid h \in H\} = \{hg \mid h \in H\} = Hg$. Hence $H \trianglelefteq G$ by definition 3.1.9, as claimed.

Proposition 3.1.8 is very important. The equivalence relatoin $\sim$ corresponding to H has both property (3.2) and (3.1) by proposition 3.1.6 and so by theorem 3.1.1 G/H is a group!

Definition 3.1.13: Quotient Group

Let $H \trianglelefteq G$ be a normal subgroup of G. The *quotient group* G/H, sometimes written G mod H (and read G modulo H or G mod H for short) is the group $(G/\sim, \cdot)$ where $\sim$ is defined in proposition 3.1.6, and $\cdot$ is defined by

$$aHbH := (ab)H$$

An easy way to remember that this operation is defined when is H is normal is by remembering $a(Hb)H = abHH = abH$. For notation, we can write $aH = \bar{a} = [a]$ for a representative a and $G/H = \bar{G}$. The projection $\pi\colon G \to G/\sim$ then reads

$$\pi\colon G \to G/H \qquad \pi(g) = gH$$

and it is a homomorphism, since $\pi(ab) = (ab)H = aH\,bH = \pi(a)\pi(b)$ by the definition of the product in G/H.

Since π is a homomorphism, it's kernel is a subgroup:

$$\ker(\pi) = \{g \in G \mid \pi(g) = eH\}$$

and since $eH = H$, this means that $\ker(\pi) = H$. Since H can be any normal subgroup, this means that H is always the kernel of some map

$$\text{Normal} \Rightarrow \text{Kernel}$$

Is the converse true, that is, the kernel is always normal? If so, that would be really powerful, since the kernel would then always be a normal subgroup of G, and so any homomorphism $\varphi : G \to H$ would induce a quotient group G/K, where $K = \ker(\varphi)$. Kernels are always normal subgroups!

Proposition 3.1.14: Kernel Then Normal

Let $\varphi : G \to H$ be a homomorphism and let $K = \ker(\varphi)$. Then $K \trianglelefteq G$

***Proof*:**
Let K be the kernel of $\varphi : G \to H$, and take any $g \in g$. then

$$\varphi(gkg^{-1}) = \varphi(g)\varphi(k)\varphi(g^{-1}) = \varphi(g)\varphi(k)\varphi(g)^{-1} = \varphi(g)\varphi(g)^{-1} = e_H$$

and so $gkg^{-1} \in K$, showing that $gK = Kg$, meaning $K \trianglelefteq G$

This means that given any homomorphism $\varphi : G \to H$, we can *always* define an equivalence relation on G given the kernel of φ since $\ker(\varphi)$ is normal!


Since any normal subgroup will be the kernel of some homomorphism, and the kernel of any homomorphism will be normal, we get that the two are essentially synonymous in group theory:

$$\text{Normal} \Leftrightarrow \text{Kernel}$$

With quotient groups available, the universal property of quotients (theorem 3.1.1) takes a form stated with a normal subgroup. If a normal subgroup N lies in the kernel of a homomorphism $\varphi\colon G \to H$, then elements of the same coset of N have the same image under φ, so φ factors through G/N:

Theorem 3.1.15: The First Isomorphism Theorem

Let $\varphi : G \to H$ be a homomorphism and let $K = \ker(\varphi)$. If $N \trianglelefteq G$ where $N \subseteq \ker(\varphi)$, then there exists a unique *homomorphism* $\Phi : G/N \to H$ such that the following diagram commutes:



where $\varphi = \Phi \circ \pi$, and π is the natural projection

***Proof*:**
Let $\sim$ be the relation $a \sim b \Leftrightarrow a^{-1}b \in N$ of proposition 3.1.6. The class of a consists of the elements $b \in G$ with $a^{-1}b \in N$, which form the coset aN, and G/N is the group $(G/\sim, \bullet)$ (definition 3.1.13). Let $a, b \in G$ with $a \sim b$. Then $a^{-1}b \in N \subseteq \ker(\varphi)$, so by proposition 1.4.4(2)

$$\varphi(a)^{-1}\varphi(b) = \varphi(a^{-1}b) = e_H$$

that is, $\varphi(a) = \varphi(b)$. By theorem 3.1.1, there is a homomorphism $\Phi\colon G/N \to H$ with $\Phi(aN) = \varphi(a)$ for every $a \in G$, that is, $\varphi = \Phi \circ \pi$. If $\Psi\colon G/N \to H$ is a homomorphism with $\varphi = \Psi \circ \pi$ as well, then $\Psi(aN) = \varphi(a) = \Phi(aN)$ for every $a \in G$, and every element of G/N is a coset aN, so $\Psi = \Phi$, as claimed.

What theorem 3.1.15 (the universal property of quotient groups) shows is that all the information a homomorphism φ gives us can be captured via the quotient group G/K.

Corollary 3.1.16: Canonical Decomposition For Groups

Let $\varphi : G \to H$ be any group homomorphism. Then it may be decomposed into

$$G \xrightarrow[\pi]{} G/\ker(\varphi) \xrightarrow[\Phi]{\cong} \operatorname{im}(G) \xhookrightarrow[\iota]{} H \qquad (\varphi : G \to H)$$

where Φ is an isomorphism

***Proof*:**
Write $K = \ker(\varphi)$. By proposition 3.1.14, K is normal, so G/K is a group (definition 3.1.13), and the natural projection $\pi\colon G \to G/K$, $a \mapsto aK$, is a homomorphism, since $\pi(ab) = (ab)K = aK\,bK$. The image $\operatorname{im}(G) = \varphi(G)$ is a subgroup of H (proposition 1.4.4(5)), so the inclusion ι is a homomorphism. By theorem 3.1.15 with $N = K$, there is a homomorphism $\Phi_0\colon G/K \to H$ with $\varphi = \Phi_0 \circ \pi$, that is, $\Phi_0(aK) = \varphi(a)$ for every $a \in G$. Its values lie in $\varphi(G)$, so it restricts to a homomorphism $\Phi\colon G/K \to \varphi(G)$ with $\varphi = \iota \circ \Phi \circ \pi$.

The map Φ is surjective, since every element of $\varphi(G)$ is some $\varphi(a) = \Phi(aK)$. It is injective: if $\Phi(aK) = \Phi(bK)$, then $\varphi(a) = \varphi(b)$, so $\varphi(a^{-1}b) = \varphi(a)^{-1}\varphi(b) = e_H$ by proposition 1.4.4(2), that is, $a^{-1}b \in K$, and $aK = bK$ since the coset aK is the class of a for the relation $a \sim b \Leftrightarrow a^{-1}b \in K$ of proposition 3.1.6. So Φ is a bijective homomorphism, that is, an isomorphism (definition 1.4.12), completing the proof.

Corollary 3.1.17: Surjective Homomorphisms

Let $\varphi : G \to H$ be a surjective homomorphism, and let $K = \ker(\varphi)$. Then

$$G/K \cong H$$

***Proof*:**
For $G/K \cong H$, notice that $H = \operatorname{im}(G)$ in corollary 3.1.16.

This last corollary is very useful and one you will use constantly in both theoretical and practical context. It is saying that if we want to know the structure of G/K, if we can find a surjective homomorphism from G to H with kernel K, then $G/K \cong H$, i.e., H will represent the structure!

A surjective homomorphism $\varphi\colon G \to H$ with kernel K, as in corollary 3.1.17, can be recorded as a chain of homomorphisms

$$1 \xrightarrow{\iota_1} K \xhookrightarrow{\iota_K} G \xrightarrow{\varphi} H \xrightarrow{\pi} 1$$

where 1 is the trivial group, ι_1 and ι_K are the inclusion homomorphisms, and π is the projection of H onto the trivial group.

This representation is called a *short exact sequence*. We will return to short exact sequences soon to flesh out many intersting results when precieving which groups can be put in the 3 non-trivial positions, that is

$$1 \xrightarrow{\iota_1} A \hookrightarrow B \twoheadrightarrow C \xrightarrow{\pi} 1$$

Exercise 3.1.1

Throughout these exercises, let $\varphi : G \to H$ be a homomorphism between the two groups G and H, and $K = \ker(\varphi)$

1. Show that $\varphi^{-1}(Q)$ (the pre-image of Q) is a group. If Q was a normal subgroup, $Q \trianglelefteq H$, show that $\varphi^{-1}(Q)$ is also normal. Is it true that if $H \trianglelefteq G$ then $\varphi(H) \trianglelefteq \varphi(G)$?
2. Let $h \in H$. We call $\varphi^{-1}(h)$ a *fiber* of φ over h. Let $F_h = \varphi^{-1}(H)$. Show that
   1. For any $u \in F_h$, $F_h = uK$
   2. For any $u \in F_h$, $F_h = Ku$
3. Let $aKbK = \{akbk' \mid a, b \in G, k, k' \in K\}$ be a set, and $K \trianglelefteq G$. Show that
   $$aKbK = abK$$
   where $abK = \{abk \mid a, b \in G, k \in K\}$ [hint: for $aKbK \subseteq abK$, recall that $aK = Ka$ since K is normal. For $aKbK \supseteq abK$, note that $1 \in K$ so $1 \cdot a \in Ka$. Take advantage of normality to complete the proof]
4. Let $R \leqslant G$. Show that the cosets of G/R are all of equal size.
5. Show that if $aB = 1B$, then $a \in B$
6. Let $H, K \trianglelefteq G$. Show that $H \cap K \trianglelefteq G$
7. Generalizing the previous result, If $\{H_i\}_{i \in I}$ is some collection of normal subroups of G show that $\cap_{i \in I} H_i \trianglelefteq G$
8. Let G be finitely generated and let $N \trianglelefteq G$ be finitely generated. Prove that G/N is finitely generated.
9. For any group G, show that $Z(G) \trianglelefteq G$
10. Let n be a positive integer. Show that $n\mathbb{Q} = \mathbb{Q}$, where $n\mathbb{Q} = \{nq \mid q \in \mathbb{Q}\}$ and nq is the sum of n copies of q in the additive group $\mathbb{Q}$. (Groups with this property for every n are called *divisible* groups. More on them in section 17.3.)
11. Let $G \cong H$, $N \trianglelefteq G$ and $K \trianglelefteq H$. If $N \cong K$ is it true that $G/N \cong H/K$? Prove or show a counter example. hint: [2]
12. (Useful in Lie Groups) Let $GL_n(\mathbb{R})$ be the set of invertible $n \times n$ matrices over $\mathbb{R}$ (more generally, if you know linear algebra, over a field $\mathbb{F}$ with characteristic $\neq 2$ or 3 if $n = 2$). What are the normal subgroups of $GL_n(\mathbb{R})$?
13. We have shown that if we have a map $f : G \to H$ and $N \trianglelefteq H$, we can define a map $\overline{f} : G \to H/N$. Is the converse true? That is, if we have a map $f : G \to H/N$, do we have a map $F : G \to H$ such that $f = \pi \circ F$? [Hint: Consider maps with domains and codomains of $\mathbb{Z}$ and $\mathbb{Z}/n\mathbb{Z}$, $n > 1$]
14. Show that every subgroup of Q_8 is normal. Hence, every subgroup being normal does not imply the group is abelian[3]

[2] Consider $G = H = N = \mathbb{Z}$ and $K = 2\mathbb{Z}$.

[3] On the other hand, Q_8 is special: Every non-abelian group for which all subgroups are normal is of the form

3.2 Presentations

We have seen in section 2.3.3 that if we have any set map from a set S to a group G, $f : S \to G$, then it can be extended it to a homomorphism from the group $F(S)$ to G: $\varphi : F(S) \to G$, $\varphi|_S = f$. We have also seen that if we have a surjective homomorphism $G \to H$, then $G/N \cong H$ (where N is the kenrel of the homomorphism). We can combine these results: Converting to $(G, *)$ notation for groups for a moment, given an identity map $\mathrm{id} : G \to (G, *)$, which is a prefectly valid surjective set function from the set G to the underlying $\varphi : (F(G), *_F) \to (G, *)$. By the first isomorphism theorem, if N is the kernel, then $(F(G)/N, (*_F)_\varphi) \cong (G, *)$. Thus, $\varphi : F(G) \to (G, *)$. By the first isomorphism theorem, if N is the kernel, then $F(G)/N \cong (G, *)$. Thus, every group is the quotient of a free group! We now go back to our usual convention of groups being written as G where we drop the binary operation, where we will consider it clear from context when a map is a set map and when it is a homomorphism.

Let's generalize this result a bit: Let's say $S \subseteq G$ such that $\langle S \rangle = G$, and consider $f : S \to G$. Then by the universal property of free groups, we have that $\varphi : F(S) \to G$ is a group homomorphism. Since $\langle S \rangle = G$, and all possible words are in $F(S)$, then by construction of $F(S)$ and φ, the map φ is a surjective group homomorphism. Thus, for the appropriate kernel N, $F(S)/N \cong G$.

Since $F(S)$ is free from relations, but G has relations, φ somehow imposed relations onto $F(S)$. This means that N captured the idea of the relations imposed on $F(S)$ to make $F(S)/N \cong G$. As observed in section 2.3, any relations of a group can be written as

$$r_1 = r_2 = \cdots = r_k = 1$$

If we let $r_i = \prod_{i \in I_{r_i}} s_i$ to be some arbitrary finite[4] product of elements of S and it's inverses. Then if If we let $r_i = \prod_{i \in I_{r_i}} s_i$ to be some arbitrary product of elements of S and it's inverses. Then if we let $R = \{r_1, r_2, ..., r_k\}$, we can write $G = \langle S | r_1 = r_2 = \cdots = r_k = 1 \rangle$ as

$$G = \langle S | R \rangle$$

for short hand. Since $F(S)/N \cong G$, it must be that $R \subseteq N$. We might be tempted to say $\langle R \rangle \subseteq N$, however the closure *need not be normal*, while N must be a normal subset. Instead, we will define the noraml closure:

Definition 3.2.1: Normal Closure

Let $S \subseteq G$ be a subset of a group G. Then define the intersection of all normal subgroups of G containing S

$$\langle S \rangle^{\trianglelefteq} = \bigcap_{\substack{N_i \trianglelefteq G \\ S \subseteq N_i}} N_i$$

to be *normal closure of* S.

$\langle S \rangle^{\trianglelefteq}$ is indeed a normal subgroup: it is an intersection of subgroups, hence a subgroup (proposition 2.3.14), and for $g \in G$, $g \left(\bigcap_i N_i\right) g^{-1} \subseteq \bigcap_i g N_i g^{-1} = \bigcap_i N_i$. Since $r_1 = r_2 = \cdots = r_k = 1$ in G, then $[r_1] = [r_2] = \cdots = [r_k] = [1] \in F(S)/N$, and so $r_1, r_2 ... r_k \in N$. We thus have that $\langle R \rangle^{\trianglelefteq} \subseteq N$.

$G \cong Q_8 \times B \times D$ where B is something called an elementary abelian 2-group and D is called a torsion abelian group whose elements are of odd order. A group where all subgroups are normal is called a Dedekind group, and a non-abelian Dedekind group is called a Hamiltonian group.

[4] Infinite products would require more care to be well-defined, see EYNTKA real analysis I

Next, let's say we have some $x \in N$. Then that means then $[x] = [1]$, so for some $n' \in N$, $xn' = 1$. But then, xn' must be some combinations of elements $r_1, r_2, \cdots, r_k$, since by the presentation of G, those are the elements that can equal to 1. Thus $N \subseteq \langle R \rangle^{\trianglelefteq}$. Therefore $N = \langle R \rangle^{\trianglelefteq}$

From this, we can formally define a presentation

Definition 3.2.2: Presentation

Let G be any group. Then a *presentation* of G is a pair of sets (S, R) where $\langle R \rangle^{\trianglelefteq}$ is the kernel of the homomorphism $F(S) \to G$. The elements of S are called the *generators* of G, and the elements of R are called the *relations* of G:

$$\langle S|R \rangle := F(S)/\langle R \rangle^{\trianglelefteq}$$

We say G is finitely generated if given a presentation (S, R), $|S|$ is finite. We say G is *finitely presented* if both $|S|$ and $|R|$ are finite.

Notice how this statement is like the dual equivalent of Cayley's theorem (theorem 4.5.3): In Cayley's theorem, every group is the subgroup of a symmetric group. Here, every group is the quotient of a free group.

Theorem 3.2.3: Homomorphisms From A Presentation (von Dyck)

Let $G = \langle S \big| R \rangle$, let H be a group and $f\colon S \to H$ a function, and let $\varphi\colon F(S) \to H$ be the homomorphism extending f (theorem 2.3.27). If $\varphi(r) = 1$ for every $r \in R$, there is a unique homomorphism $\overline{\varphi}\colon G \to H$ sending the class of each $s \in S$ to $f(s)$. It is surjective when $f(S)$ generates H.

***Proof*:**
$\ker(\varphi)$ is a normal subgroup of $F(S)$ (proposition 3.1.14) containing R, so it contains $\langle R \rangle^{\trianglelefteq}$ (definition 3.2.1). With $\pi\colon F(S) \to G$ the projection, theorem 3.1.15 gives a homomorphism $\overline{\varphi}\colon G \to H$ with $\overline{\varphi} \circ \pi = \varphi$, so $\overline{\varphi}$ sends the class of s to $f(s)$. Every element of G is a product of classes of elements of S and their inverses, since every element of $F(S)$ is such a product and π is surjective, so a homomorphism on G is determined by these values, which gives uniqueness. The image of $\overline{\varphi}$ is a subgroup containing $f(S)$, so it is H when $f(S)$ generates H.

Example 3.2.4

1. $\langle A|\emptyset \rangle$ is the presentation of the free group $F(A)$
2. The dihedral group D_n ($n \geq 3$) of definition 1.2.28 has the presentation $G = \langle r, s \big| r^n, s^2, rsrs \rangle$. Let $\rho \in D_n$ be the rotation by $2\pi/n$ and σ a reflection. By proposition 1.2.29, $\rho^n = \sigma^2 = 1$ and $\rho\sigma = \sigma\rho^{-1}$, which is $\rho\sigma\rho\sigma = 1$, and every element of D_n is $\sigma^k\rho^i$, so ρ and σ generate D_n, which has order $2n$ (proposition 1.2.30). So theorem 3.2.3 gives a surjective homomorphism $G \to D_n$ with $r \mapsto \rho$, $s \mapsto \sigma$. In G, $rs = sr^{-1}$, so $sr^k = r^{-k}s$ for every k, and every element of G can be written as $r^i s^j$ with $0 \leq i < n$ and $0 \leq j < 2$. So $|G| \leq 2n = |D_n|$, and the surjection is an isomorphism.

Example 3.2.5: A Presentation Of An Infinite Group

The group $G = \langle x, y | x^3, y^3, (xy)^3 \rangle$ is infinite.

***Proof*:**

Let $\omega = e^{2\pi i/3} \in \mathbb{C}$. Then $\omega^3 = 1$ and $\omega \neq 1$, and $t^3 - 1 = (t-1)(t^2+t+1)$ gives $1+\omega+\omega^2 = 0$. Define $a, b \colon \mathbb{C} \to \mathbb{C}$ by $a(z) = \omega z$ and $b(z) = \omega z + 1$. They are bijections, with inverses $z \mapsto \omega^2 z$ and $z \mapsto \omega^2(z-1)$, so they lie in the symmetric group $\mathrm{Sym}(\mathbb{C})$ (definition 1.2.12). For $z \in \mathbb{C}$,

$$a^3(z) = \omega^3 z = z \qquad b^3(z) = \omega^3 z + \omega^2 + \omega + 1 = z \qquad (ab)(z) = \omega^2 z + \omega$$

and applying ab three times gives $(ab)^3(z) = \omega^6 z + \omega^5 + \omega^3 + \omega = z + \omega^2 + 1 + \omega = z$. So $a^3 = b^3 = (ab)^3 = \mathrm{id}$, and theorem 3.2.3 gives a homomorphism $\overline{\varphi} \colon G \to \mathrm{Sym}(\mathbb{C})$ with $x \mapsto a$ and $y \mapsto b$. Its image contains ba^{-1}, and $ba^{-1}(z) = b(\omega^2 z) = z + 1$. The powers $(ba^{-1})^m$ with $m \geq 1$ are the translations $z \mapsto z + m$, which are pairwise distinct, so the image of $\overline{\varphi}$ is infinite. Since $\overline{\varphi}$ maps G onto its image, G is infinite, as claimed.

3.2.6 Note Let $N \trianglelefteq G$. Since N is already normal, $\langle N \rangle^{\trianglelefteq} = N$. However, it is rather difficult to determine whether $S \subseteq N$ is a smallest set that satisfies $\langle S \rangle^{\trianglelefteq} = N$.

Corollary 3.2.7: Finitely Generated Groups

Let G be a group. Then G is finitely generated if and only if G is isomorphic to the quotient group of a finitely generated free group.

***Proof*:**

Let $G \cong F/N$, where F is a free group generated by finitely many elements $t_1, \ldots, t_n$, and let $\pi \colon F \to F/N$ be the canonical projection. Every element of F is a product of the t_i and their inverses, and π is a surjective homomorphism, so every element of F/N is a product of the $\pi(t_i)$ and their inverses. Hence F/N, and so G, is finitely generated.

On the other hand, let G is finitely generated, say $S \subseteq G$ such that $\langle S \rangle = G$ and $|S| = n$. Then there exists an inclusion map $S \hookrightarrow G$. By the universal property of free groups, this extends to a map $\varphi : F(S) \twoheadrightarrow G$. This map is surjective since S is a generating set for G. Then by the 1st isomorphism theorem, $F(S)/\ker(\varphi) \cong G$, fulfilling our requirement.

This book does not develop presentations $F(S)/N \cong G$ further. They are the starting point of *geometric group theory*, which studies a finitely generated group through the geometry of its Cayley graphs. For an introduction see [72], and for a more comprehensive treatment [47].

Theorem 3.2.8: Universal Property Of The Cokernel

Let $\varphi\colon G \to H$ be a homomorphism, let $N = \langle \varphi(G) \rangle^{\trianglelefteq}$ be the normal closure of its image (definition 3.2.1), and let $\pi\colon H \to H/N$ be the projection. Then $\pi \circ \varphi$ is trivial, and every homomorphism $\beta\colon H \to K$ with $\beta \circ \varphi$ trivial factors uniquely as $\beta = \beta' \circ \pi$. The group H/N is the *cokernel* of φ.

***Proof*:**
$\pi \circ \varphi$ is trivial because $\varphi(G) \subseteq N$. If $\beta \circ \varphi$ is trivial, then $\varphi(G) \subseteq \ker(\beta)$, a normal subgroup of H (proposition 3.1.14), so $N \subseteq \ker(\beta)$, and theorem 3.1.15 gives a unique β' with $\beta = \beta' \circ \pi$.

When H is abelian, every subgroup is normal, so $N = \varphi(G)$ and the cokernel is $H/\varphi(G)$. The image need not be normal: for the inclusion of $\langle (1\,2) \rangle$ in S_3, N contains every conjugate of $(1\,2)$, hence every transposition, so $N = S_3$ and the cokernel is trivial.

3.3 Application to Finite Groups

As mentioned earlier, thinking about cosets in themselves is also very useful. In fact, a theorem which you will you to death in this course relies on cosets. With the fact that cosets partition your group, you can deduce this strikingly important result:

Theorem 3.3.1: Lagrange Theorem

If G is a finite group and H is a subgroup of G, then the order of H divides the order of G (i.e., $|H| \big| |G|$), and the number of left cosets of H in G equals $\frac{|G|}{|H|}$

***Proof*:**
Let $H \leqslant G$. By proposition 3.1.6, $a \sim_L b \Leftrightarrow a^{-1}b \in H$ is an equivalence relation on G satisfying (3.2), and the class of a is $\left\{ b \in G \;\middle|\; a^{-1}b \in H \right\} = aH$. The left cosets therefore partition G, and each has $|H|$ elements by corollary 3.1.4. If there are m left cosets, then $|G| = m|H|$, so $|H|$ divides $|G|$ and $m = |G|/|H|$, as we sought to show.

Lagrange's theorem determines every group of prime order up to isomorphism.

Corollary 3.3.2: if G has order p, then it is cyclic

If G is a group of prime order p, then G is cyclic, hence $G \cong Z_p$.

***Proof*:**
Since $|G| = p > 1$, choose $x \in G$ with $x \neq e$. The order of the subgroup $\langle x \rangle$ divides p by theorem 3.3.1, and it is greater than 1 since $\langle x \rangle$ contains e and x. As p is prime, $|\langle x \rangle| = p = |G|$, so $\langle x \rangle = G$ and G is cyclic. By corollary 2.3.6, it is abelian, and since Z_p is cyclic of order p, generated by 1, theorem 2.3.9(1) gives $G \cong Z_p$, completing the proof.

Example 3.3.3
Try going back to theorem 2.3.11 and proving it using Lagrange's Theorem. You will find it much easier, almost trivial even.

As the examples show, Lagrange is incredibly powerful as it let's us relate the order of a group and it's subgroup, which is a fact used extensively.

Definition 3.3.4: Index

If G is a group (possibly infinite) and $H \leq G$, the number of left cosets of H in G is called the index of H in G and is denoted by $|G : H|$.

With this notation, we can re-write Lagrange's Theorem as

$$|G| = |H||G : H|$$

Corollary 3.3.5: x to the order of G

If G is a finite group and $x \in G$, then the order of x divides the order of G. In particular $x^{|G|} = 1$ for all $x \in G$.

Corollary 3.3.6: index of H is 2 $\Rightarrow$ H is normal

If $H \leqslant G$ and the index of H is 2, then H is normal

***Proof*:**
Let $x \in G \setminus H$. The left cosets of H partition G (proposition 3.1.6), and $x \in xH$ while $x \notin H = eH$, so the two left cosets are H and xH, and $xH = G \setminus H$. If $hx \in H$ for some $h \in H$, then $x = h^{-1}(hx) \in H$, a contradiction, so $Hx \subseteq G \setminus H = xH$. Since $x^{-1} \notin H$, the same argument gives $Hx^{-1} \subseteq x^{-1}H$, and replacing every element of these two sets by its inverse gives $xH \subseteq Hx$. Hence $xH = Hx$ for every $x \notin H$, and $hH = H = Hh$ for every $h \in H$. So $gH = Hg$ for every $g \in G$, and $H \trianglelefteq G$ by proposition 3.1.11(3), as claimed.

3.3.7 Why this does not necessarily work when the index is greater than 2 Take $G = D_3$, the triangle group, and $H = \{e, \sigma\}$, a subgroup of index 3. Since $\sigma r = r^{-1}\sigma$, the product $r\sigma$ equals $\sigma r^{-1} = \sigma r^2$, so

$$rH = \{r, \sigma r^2\} \qquad Hr = \{r, \sigma r\}$$

and $\sigma r^2 \neq \sigma r$. So $rH \neq Hr$, and H is not normal.

Because of the power of Lagrange, one might ask themselves if the converse is true: if a number divides the order of a group $n||G|$, does that mean there is a subgroup $H \leqslant G$ such that $|H| = n$? The answer is no:

Example 3.3.8: A_4 Has No Subgroup Of Order 6

The alternating group A_4 has order 12, and it has no subgroup of order 6, although $6\big|12$.

Step 1: the elements of A_4. By proposition 1.2.14, every $\sigma \in S_4$ other than id is a product of cycles whose supports are pairwise disjoint subsets of $\{1,2,3,4\}$ with at least two elements each. So σ is a transposition, a 3-cycle, a 4-cycle, or a product of two disjoint transpositions. By theorem 1.2.18, a 3-cycle is a product of two transpositions and a 4-cycle is a product of three, so by theorem 1.2.20(4) the transpositions and the 4-cycles are odd, while the 3-cycles and the products of two disjoint transpositions are even. Hence A_4 (definition 1.2.22) consists of id, the three permutations

$$(1\,2)(3\,4) \qquad (1\,3)(2\,4) \qquad (1\,4)(2\,3)$$

and the eight 3-cycles, two on each of the four 3-element subsets of $\{1,2,3,4\}$. So $|A_4| = 1+3+8 = 12$.

Step 2: squares lie in a subgroup of order 6. Suppose $H \leqslant A_4$ with $|H| = 6$. The left cosets of H are the classes of the equivalence relation of proposition 3.1.6, so they partition A_4, and by theorem 3.3.1 there are $12/6 = 2$ of them. Every $g \in A_4$ satisfies $g^2 \in H$. This holds if $g \in H$. If $g \notin H$, then $g \in gH$ and $g \notin H = eH$, so the two cosets are H and gH, and $A_4 = H \cup gH$. If moreover $g^2 \notin H$, then $g^2 \in gH$, say $g^2 = gh$ with $h \in H$, and cancelling g (proposition 1.1.17) gives $g = h \in H$, a contradiction.

Step 3: the contradiction. Let c be a 3-cycle. Then c has order 3 by proposition 1.2.24, so $c = c^4 = (c^2)^2$, and Step 2 applied to $g = c^2 \in A_4$ gives $c \in H$. So H contains id and the eight 3-cycles, and $|H| \geq 9 > 6$, a contradiction. Therefore A_4 has no subgroup of order 6.

Are there at least partial converses that are true? There are two famous theorems giving the best converse: *Cauchy's Theorem* and *Sylow's Theorem*:

1. (Cauchy) If G is finite, and $p\big||G|$, then there exists a subgroup $H \leqslant G$ of order p
2. (Sylow) If G is finite and $p^k\Big||G|$, that is p maximally divides $|G|$ ($|G| = p^k m$ for some m where $p \nmid m$), then there exists a subgroup $H \leqslant G$ such that $|H| = p^k$.
3. (Sylow Corollary) If $p^j\big||G|$ for some $j \geq 0$, then there exists a subgroup $H \leqslant G$ such that $|H| = p^j$ (see exercise 4.8.1 (1)).

These theorems rely on prime-number properties to give us a partial converse. Sylow's theorem goes a step further in telling us how many groups of a particular order we can find (so more than there exists one). By the way we will present Sylow's theorem, it will require group-actions, the topic of section 4.8. Cauchy's theorem technically does not need it (see [10]).

For finite abelian groups, the full converse of Lagrange's theorem holds:

Corollary 3.3.9: Cauchy's Theorem For Abelian Groups

If G is a finite abelian group, and n divides $|G|$, then there is a subgroup of G of order n. When $n = p$ is prime, G has an element of order p

***Proof*:**
Step 1: the prime case. We show the sharper statement that a finite abelian group G whose order is divisible by a prime p contains an *element* of order p. The subgroup it generates then has order p by proposition 2.3.4, which is the case $n = p$ of the corollary.

The argument is by induction on $|G|$, so assume the statement holds for every abelian group of order strictly smaller than $|G|$. Since $p \big| |G|$ we have $|G| > 1$, so pick $x \in G$ with $x \neq 1$.

First suppose p divides $|x|$, say $|x| = pm$. By corollary 2.3.8(2),

$$|x^m| = \frac{pm}{\gcd(pm, m)} = \frac{pm}{m} = p$$

and x^m is the element we wanted.

Now suppose p does not divide $|x|$. Put $N = \langle x \rangle$, which is normal in G because G is abelian, so the quotient G/N is defined, and it is again abelian. By theorem 3.3.1,

$$|G/N| = \frac{|G|}{|N|}$$

and $|N| = |x| > 1$ by proposition 2.3.4, so $|G/N| < |G|$. Since p divides $|G| = |N| \cdot |G/N|$ and p is prime and does not divide $|N|$, it must divide $|G/N|$. The induction hypothesis applied to G/N produces $y \in G$ whose coset yN has order p in G/N. Then

$$(yN)^{|y|} = y^{|y|}N = N$$

so by proposition 2.3.7 the order p of yN divides $|y|$. Therefore y falls under the previous case, which produces an element of order p and completes the induction.

Step 2: arbitrary divisors. The argument is by induction on $|G|$, so assume the corollary holds for every abelian group of order strictly smaller than $|G|$. Let $d \big| |G|$. If $d = 1$ then the trivial subgroup serves, so assume $d > 1$ and pick a prime p dividing d.

Since $p \big| d$ and $d \big| |G|$, Step 1 gives a subgroup $P \leqslant G$ with $|P| = p$, and P is normal because G is abelian, so G/P is a group with

$$|G/P| = \frac{|G|}{p} < |G|$$

Now d/p is an integer dividing $|G|/p = |G/P|$, and G/P is abelian, so the induction hypothesis produces a subgroup $\overline{H} \leqslant G/P$ with $|\overline{H}| = d/p$. This $\overline{H}$ pulls back along the projection $\pi \colon G \to G/P$: the preimage $H = \pi^{-1}(\overline{H})$ is a subgroup of G by proposition 2.1.3, since $\pi(1) = P \in \overline{H}$ and $\pi(xy^{-1}) = \pi(x)\pi(y)^{-1}$. An element $g \in G$ lies in H exactly when its coset gP lies in $\overline{H}$, so H is the union of the d/p cosets that are elements of $\overline{H}$. These cosets are pairwise disjoint (proposition 3.1.6) and each has $|P| = p$ elements (corollary 3.1.4), so

$$|H| = \frac{d}{p} \cdot p = d$$

and H has the required order, as claimed.

For finite abelian groups the order forces a subgroup of every order dividing it (corollary 3.3.9),

which fails for A_4 (example 3.3.8). This is a first instance of the structure theory that classifies every finitely generated abelian group in chapter 5. The exponentially more difficult task of the non-abelian case is is why much of finite group theory concerns the non-abelian case.

Be mindful that Lagrange's theorem gives you information about *finite* groups. In general, arithmetics on infinite groups will not be defined in a meaningful way for us. In fact, we can get quite some weird results, like subgroups being isomorphic to their parent group!

Example 3.3.10: Subgroups Of $\mathbb{Z}$
Take the group $\mathbb{Z}$, and any subgroup $n\mathbb{Z} \leqslant \mathbb{Z}$ for $n \in \mathbb{N}_+$. Show that

$$n\mathbb{Z} \cong \mathbb{Z}$$

that is, every (non-trivial) subgroup of $\mathbb{Z}$ is isomorphic to $\mathbb{Z}$!

3.4 Internal Direct Product

Though it might seem inconspicuous at first, the introduction of a normal subgroup will let us be able to define the multiplication of subgroups that from subgroups in themselves!! The idea behind this idea is to decompose a group into smaller subgroups, giving an insight on its structure. Chapter 5 develops this decomposition further.

Definition 3.4.1: HK (Internal Direct Product)

Let H, K be subgroups of a group and define

$$HK = \{hk | h \in H, k \in K\}$$

3.4.2 Note This is *not* necessarily a group! Take $\langle(123)\rangle = H \leqslant S_4$ and $\langle(3\,4)\rangle = K \leqslant S_4$. Then

$$HK = \{\mathrm{id}, (123), (132), (123)(34), (132)(34), (34)\}$$

and $(132)(34) = (3421)$, but $(3421)^2 \notin HK$, meaning HK is not closed!

Proposition 3.4.3: cardinality of HK

Let H, K be finite subgroups of a group. Then

$$|HK| = \frac{|H||K|}{|H \cap K|}$$

***Proof*:**
The set HK is the union of the left cosets hK with $h \in H$, and each of them has $|K|$ elements (corollary 3.1.4). For a subgroup C and elements x, y of the ambient group, $xC = yC$ exactly when $y^{-1}x \in C$: if $xC = yC$, then $x = xe \in yC$, so $y^{-1}x \in C$, and if $y^{-1}x = m \in C$, then $xC = y(mC) = yC$, since $mC = C$. Two cosets h_1K and h_2K are equal or disjoint, because a

common element $h_1k_1 = h_2k_2$ gives $h_2^{-1}h_1 = k_2k_1^{-1} \in K$. For $h_1, h_2 \in H$ the element $h_2^{-1}h_1$ lies in H, so

$$h_1K = h_2K \Leftrightarrow h_2^{-1}h_1 \in K \Leftrightarrow h_2^{-1}h_1 \in H \cap K \Leftrightarrow h_1(H \cap K) = h_2(H \cap K)$$

Hence the number of distinct cosets hK with $h \in H$ is the number of left cosets of $H \cap K$ in H, which is $|H|/|H \cap K|$ by theorem 3.3.1. These cosets are pairwise disjoint, so

$$|HK| = \frac{|H|}{|H \cap K|}|K| = \frac{|H||K|}{|H \cap K|}$$

as we sought to show.

Proposition 3.4.4: When is HK a group

If H and K are subgroups of a group, HK is a subgroup if and only if $HK = KH$

***Proof*:**
Let $H, K \leqslant G$.

($\Rightarrow$) Let $HK \leqslant G$. If $x \in HK$, then $x^{-1} \in HK$, say $x^{-1} = hk$, and $x = k^{-1}h^{-1} \in KH$. So $HK \subseteq KH$. If $kh \in KH$, then $(kh)^{-1} = h^{-1}k^{-1} \in HK$, and since HK is a subgroup, $kh \in HK$. So $KH \subseteq HK$, and $HK = KH$.

($\Leftarrow$) Let $HK = KH$. Then $HK \neq \emptyset$. For $h_1k_1, h_2k_2 \in HK$,

$$(h_1k_1)(h_2k_2)^{-1} = h_1(k_1k_2^{-1}h_2^{-1})$$

and $k_1k_2^{-1}h_2^{-1} \in KH = HK$, say it equals $h'k'$. So $(h_1k_1)(h_2k_2)^{-1} = (h_1h')k' \in HK$, and $HK \leqslant G$ by proposition 2.1.3.

Corollary 3.4.5: Condition on K when Internal Direct Product is Present

If H and K are subgroups of G and $H \leq N_G(K)$, then HK is a subgroup of G. Symmetrically, $HK \leqslant G$ when $K \leq N_G(H)$, in particular when $H \trianglelefteq G$. Furthermore, if H and K are normal subgroups, then $HK \trianglelefteq G$.

***Proof*:**
Suppose $H \leqslant N_G(K)$. For $h \in H$ and $k \in K$, both hkh^{-1} and $h^{-1}kh$ lie in K, because h and h^{-1} lie in $N_G(K)$. Hence $hk = (hkh^{-1})h \in KH$ and $kh = h(h^{-1}kh) \in HK$, so $HK = KH$, and $HK \leqslant G$ by proposition 3.4.4.

If $K \leqslant N_G(H)$, the previous paragraph, with the roles of H and K exchanged, gives $KH = HK$ and $HK \leqslant G$. This applies when $H \trianglelefteq G$, since then $N_G(H) = G$ (proposition 3.1.11).

Finally, let H and K be normal in G. Then $HK \leqslant G$ by the previous paragraph. For $g \in G$, $h \in H$ and $k \in K$, we have $g(hk)g^{-1} = (ghg^{-1})(gkg^{-1})$ with $ghg^{-1} \in H$ and $gkg^{-1} \in K$

(proposition 3.1.11). So $gHKg^{-1} \subseteq HK$ for every $g \in G$, and $HK \trianglelefteq G$ by proposition 3.1.11, completing the proof.

Defining when HK is a group is intersting, but it would be even more useful if we can figure out the structure of HK. For example, Can we say that $HK \cong H \times K$? The answer is not always! In fact, we will find a way of exactly figuring out the structure of HK in chapter 5 once we have learned the appropriate tools in chapter 4

3.4.6 Foreshadowing Thinking about HK like in corollary 3.4.5 will become the defining feature when we discuss *semi-direct* products in chapter 5.

Since we have now defined how we can take the "product" of two groups, we can ask the following intersting question: If $\mathcal{N}$ is some subset of normal subgroup G that is "closed" under multiplication, does it form a group? The reader should fiddle around with this before the answer is given. The same question will be asked in the next part of the book where we will have the equivalent of normal subgroup for rings (an algebraic structure with 2 binary operations). It with the "normal" objects of rings. The answer for groups shall be presented in chapter 7. with the "normal" objects of rings. In the case for groups, such a collection will not form a group.

Thus, we will set internal direct products aside, with only an exception made for the next section, until we have accumulated more tools to discuss them again.

3.5 Isomorphism Theorems

We know turn back to how quotient groups are inseparably related to homomorphisms. Mathematicians who were studying homomorphisms wanted to understand the relation between groups given certain properties, for then we can gain new perspective into problems being solved. For example, if we have a group $HK \leqslant G$, and $K \trianglelefteq G$, can we always determine what HK/K is? Is there *always* an answer to this question, no matter what group HK we pick? Another question is what if we "recusively" take quotients: If $H \trianglelefteq K \trianglelefteq G$, what is $(G/H)/(K/H)$? Is there a simplification that will make this more understandable? Yet another such question is how much can we deduce of the subgroups of G/N (i.e. the lattice of G/N) given what we know about G?

In this section, we will show these results:

1. We will sum up the results of of theorem 3.1.15, but give it the name that is more commonly used
2. We will look at equivalent ways of looking at internal direct products, since they pop up a lot (especially chapter 5)
3. An easier way of thinking of quotient groups whose quotient is a quotient group.
4. the subgroup lattice of G and the subgroup lattice of G/N

We first recall theorem 3.1.15, but given it its classical name:

Theorem 3.5.1: First Isomorphism Theorem

If $\Phi : G \to H$ is a homomorphism of groups, then $\ker(\Phi) \trianglelefteq G$ and $G/\ker\Phi \cong \Phi(G)$.
Similarly, if $N \trianglelefteq G$ and $N \subseteq \ker(\Phi)$, there exists a unique *homomorphism* $\varphi : G/N \to H$ such that the following diagram commutes:

$$\begin{array}{ccc} G & \xrightarrow{\pi} & G/N \\ & \searrow^{\Phi} & \downarrow{\scriptstyle \varphi} \\ & & H \end{array}$$

where $\Phi = \varphi \circ \pi$, and π is the natural projection

The second half of the theorem is the universal property of the quotient group: every homomorphism $\Phi\colon G \to H$ whose kernel contains N factors uniquely through the natural projection $\pi\colon G \to G/N$[5], as $\Phi = \varphi \circ \pi$. Questions about Φ therefore become questions about the group G/N.

Also, remember that if we take $\Phi(G) \leqslant H$, and $N = \ker(\Phi)$ so that

$$\begin{array}{ccc} G & \xrightarrow{\pi} & G/\ker(\Phi) \\ & \searrow^{\Phi} & \downarrow{\scriptstyle \varphi} \\ & & \Phi(G) \end{array}$$

then

$$G/\ker(\Phi) \cong \Phi(G)$$

Example 3.5.2

1. we can get some information about S_n for $n \geq 2$. The set $\{1, -1\}$ is a group under multiplication, and by theorem 1.2.20(2) the sign $\operatorname{sgn}\colon S_n \to \{1, -1\}$ is a homomorphism, which sends σ to 1 if σ is even and to -1 if σ is odd (definition 1.2.21). It is surjective, since $\operatorname{sgn}((1\ 2)) = -1$, and its kernel is the alternating group A_n (definition 1.2.22). By corollary 3.1.17, we then know that

   $$S_n/A_n \cong \{\pm 1\}$$

   and so, using Lagrange, we get that

   $$2 = |S_n/A_n| = \frac{|S_n|}{|A_n|} \qquad \Rightarrow \qquad |A_n| = \frac{1}{2}|S_n|$$

2. Let's say we have two groups G, H with $\varphi : G \to H$ being a surjective homomorphism. Then we know that

   $$G/\ker(\varphi) \cong H$$

   in other words, if we have a surjective homomorphism, we can always view the structure of H through the perspective of the quotient group $G/\ker(\varphi)$!

[5] Here *natural* means that defining π requires no choices. The word also has a technical meaning, the one of definition 18.2.1.

Corollary 3.5.3: properties as consequence

Let $\varphi : G \to H$ be a group homomorphism

1. φ is injective if and only if $\ker \varphi = 1$
2. $|G : \ker \varphi| = |\varphi(G)|$ [a]


[a] If you have taken linear algebra, this is the Rank-Nullity theorem equivalent for Group Theory

The second Isomorphism theorem let's us view the quotients of internal direct products (definition 3.4.1) form a different angle.

Theorem 3.5.4: The Second or Diamond Isomorphism Theorem

Let G be a group, let A and B be subgroups of G and assume $A \leq N_G(B)$. Then AB is a subgroup of G, $B \trianglelefteq AB$, $A \cap B \trianglelefteq A$, and $AB/B \cong A/A \cap B$.

The name diamond comes form this diagram where the arrow represent subgroups, and a red arrow represents norma subgroup:



and

$$\frac{AB}{B} \cong \frac{A}{A \cap B}$$

For finite A and B, comparing orders on the two sides of $AB/B \cong A/(A \cap B)$ gives $|AB| = |A||B|/|A \cap B|$, recovering proposition 3.4.3 in the case $A \leqslant N_G(B)$.

***Proof*:**

Since $A \leqslant N_G(B)$, $aBa^{-1} = B$ for every $a \in A$. So for $a \in A$ and $b \in B$,

$$ab = (aba^{-1})a \in BA \qquad ba = a(a^{-1}ba) \in AB$$

using $a^{-1} \in A$ in the second. Hence $AB = BA$, and $AB \leqslant G$ by proposition 3.4.4.

For $a \in A$ and $b \in B$, $(ab)B(ab)^{-1} = a(bBb^{-1})a^{-1} = aBa^{-1} = B$, since $bBb^{-1} = B$ for $b \in B$.

So $(ab)B = B(ab)$, and $B \trianglelefteq AB$ (definition 3.1.9).

The quotient AB/B is therefore a group (definition 3.1.13). Define $\varphi\colon A \to AB/B$ by $\varphi(a) = aB$. It is a homomorphism, since $\varphi(aa') = aa'B = (aB)(a'B)$ by the definition of the operation on AB/B. It is surjective: an element of AB/B has the form abB with $a \in A$ and $b \in B$, and $abB = aB = \varphi(a)$ because $bB = B$. Its kernel is $\{a \in A \mid aB = B\}$. If $aB = B$, then $a = ae \in B$. Conversely, if $a \in B$, then $aB \subseteq B$ and $B = a(a^{-1}B) \subseteq aB$, so $aB = B$. Hence $\ker\varphi = A \cap B$, which is normal in A by proposition 3.1.14, and corollary 3.1.17 gives

$$\frac{A}{A \cap B} \cong \frac{AB}{B}$$

as we sought to show.

One way to remember this theorme is through the following mnemonic:

> If we have $\frac{AB}{B}$, then add a $A \cap _$ to the top and bottom, giving us
>
> $$\frac{A \cap AB}{A \cap B} = \frac{A}{A \cap B}$$

Another way to think about the 2nd isomorphism theorem is to consider the case where $A \cap B = \{e\}$. Then this theorem shows that $AB/B \cong A$, and if also $B \leqslant N_G(A)$, that $AB/A \cong B$:

$$\frac{AB}{B} \cong A \qquad \frac{AB}{A} \cong B$$

Heuristically, we can think in this situation that we are "cancelling out" the B's. However, be mindful to take this as a heuristic: this is *not* what is happening!

The third Isomorphism theorem lets quickly simplify quotient groups quotiented *by* a quotient group:

Theorem 3.5.5: The Third Isomorphism Theorem

Let G be a group and let H and K be normal subgroups of G with $H \leq K$. Then $K/H \trianglelefteq G/H$ and

$$(G/H)/(K/H) \cong G/K$$

If we denote the quotient by H with a bar, this can be written

$$\bar{G}/\bar{K} \cong G/K$$

***Proof*:**
Since $K \trianglelefteq G$, $K/H \trianglelefteq G/H$. To show this, first note that K/H is indeed a subgroup of G/H. For any $[x], [y] \in K/H$, $[x][y]^{-1} = [xy^{-1}] \in K/H$ since $xy^{-1} \in K$. Furthermore, for any $[g] \in G/H$, and any coset $[k] \in K/H$, $[g][k] = [k'][g]$, $k' \in K$ (i.e. $[g](K/H) = (K/H)[g]$), since both K and H are normal. Thus $K/H \trianglelefteq G/H$.

Now, define the map

$$\varphi : G/H \to G/K \qquad gH \mapsto gK$$

This map is well-defined: if $g_1H = g_2H$, then $g_2^{-1}g_1 \in H \subseteq K$, so $g_1K = g_2K$.

Now, notice this map is a homomorphism and surjective. It is a homomorphism since

$$\varphi(g_1Hg_2H) \overset{!}{=} \varphi(g_1g_2H) = g_1g_2K \overset{!}{=} g_1Kg_2K = \varphi(g_1H)\varphi(g_2H)$$

where the $\overset{!}{=}$ equalities are the definition of the operations on G/H and G/K (definition 3.1.13). For surjectivity, since $H \leqslant K$, then for any gK, we know there is at least the coset gH that maps to it (there might be more, since $H \leqslant K$). Hence, by corollary 3.1.17

$$(G/H)/\ker(\varphi) \cong G/K$$

to find $\ker(\varphi)$, we put together the information we have so far:

$$\begin{aligned}\ker(\varphi) &= \{gH \in G/H \mid \varphi(gH) = K\} \\ &= \{gH \in G/H \mid gK = K\} \\ &= \{gH \in G/H \mid g \in K\} \\ &= K/H\end{aligned}$$

Thus, replacing $\ker(\varphi)$ with K/H we get

$$(G/H)/(K/H) \cong G/K$$

as we sought to show

An easy heuristic to remember $(G/H)/(K/H) \cong G/K$ is to think about how to simply fraction's of fractions, that is, the "flip and cancel" trick

$$\frac{\frac{1}{2}}{\frac{4}{2}} = \frac{1}{2}\frac{2}{4} = \frac{1}{4}$$

Note however that this is *not* what is happening here. It is just a useful heuristic to remember the 3rd Isomorphism Theorem. Note too that for the simplification to occur, you need that H is in the denominator of both quotients, you cannot have a different value.

Example 3.5.6: Quotients Of Cyclic Groups

Let n and m be positive integers with $n|m$, say $m = nk$. Then $m\mathbb{Z} \subseteq n\mathbb{Z}$, since $mx = n(kx)$, and both are normal in the abelian group $\mathbb{Z}$ (corollary 3.1.12). By theorem 3.5.5,

$$(\mathbb{Z}/m\mathbb{Z})/(n\mathbb{Z}/m\mathbb{Z}) \cong \mathbb{Z}/n\mathbb{Z}$$

For instance, the quotient of $\mathbb{Z}/6\mathbb{Z}$ by its subgroup $\{0, 2, 4\} = 2\mathbb{Z}/6\mathbb{Z}$ has order 2.

Finally, we will relate the subgroup structure (the lattice) of G/N with G. It will be precisely a sublattice of G that contains N! This means that going to G/N will preserve subgroup relations:

Theorem 3.5.7: The Fourth or Lattice Isomorphism Theorem (Correspondence Theorem)

Let G be a group and let N be a normal subgroup of G. Then $H \mapsto \bar{H} = H/N$ is a bijection from the set of subgroups H of G which contain N onto the set of subgroups of $\bar{G} = G/N$.

$$\{H | H \leqslant G,\ H \text{ contains } N\} \leftrightarrow \left\{\overline{H} \leqslant \overline{G}\right\}$$

In particular, every subgroup of $\bar{G}$ is of the form H/N for some subgroup H of G containing N (namely, its pre-image in G under the natural projection homomorphism from G to G/N).

***Proof*:**

Let $\pi\colon G \to \overline{G}$, $\pi(g) = gN$, be the natural projection. It is a surjective homomorphism, since $\pi(ab) = (ab)N = (aN)(bN)$ by the definition of the operation on G/N (definition 3.1.13), and its kernel is N, because $gN = N$ exactly when $g \in N$.

Step 1: the map is defined. Let H be a subgroup of G containing N. Then $H/N = \{hN \mid h \in H\} = \pi(H)$, which is a subgroup of $\overline{G}$ by proposition 1.4.4(5) applied to the restriction of π to H. Moreover $\pi^{-1}(\pi(H)) = H$: if $\pi(g) = \pi(h)$ with $h \in H$, then $gN = hN$, so $g = ge \in hN \subseteq H$, because $N \subseteq H$.

Step 2: injectivity. If H and K are subgroups of G containing N with $H/N = K/N$, then Step 1 gives $H = \pi^{-1}(\pi(H)) = \pi^{-1}(\pi(K)) = K$.

Step 3: surjectivity. Let $\overline{H} \leqslant \overline{G}$ and $P = \pi^{-1}(\overline{H})$. Then $e \in P$, and for $x, y \in P$, $\pi(xy^{-1}) = \pi(x)\pi(y)^{-1} \in \overline{H}$, so $P \leqslant G$ by proposition 2.1.3. It contains N, since $\pi(n) = N$ is the identity of $\overline{G}$ for $n \in N$. Since π is surjective, every element of $\overline{H}$ is $\pi(g)$ for some $g \in G$, and such a g lies in P, so $P/N = \pi(P) = \overline{H}$. Hence the map is a bijection, and the preimage of $\overline{H}$ is the subgroup of G containing N that maps to it, as we sought to show.

This fact has many very nice consequences:

Corollary 3.5.8: Equivalent way of looking at 4th Isomorphism Theorem

Let $N \trianglelefteq G$, let $\pi\colon G \to \overline{G} = G/N$ be the natural projection, and for a subgroup X of G containing N write $\overline{X} = X/N = \pi(X)$. Let A and B be subgroups of G containing N. Then:

1. $A \leqslant B$ if and only if $\overline{A} \leqslant \overline{B}$
2. if $A \leqslant B$ then $|B : A| = |\overline{B} : \overline{A}|$
3. $\overline{\langle A, B\rangle} = \langle \overline{A}, \overline{B}\rangle$
4. $\overline{A \cap B} = \overline{A} \cap \overline{B}$
5. $A \trianglelefteq G$ if and only if $\overline{A} \trianglelefteq \overline{G}$

***Proof*:**
The projection $\pi(g) = gN$ is a surjective homomorphism, since $\pi(ab) = (ab)N = (aN)(bN) = \pi(a)\pi(b)$ by the definition of the operation on G/N (definition 3.1.13). For a subgroup X of G containing N, the set $\overline{X}$ is a subgroup of $\overline{G}$ by proposition 1.4.4(5) applied to the restriction of π to X. Moreover

$$\pi^{-1}(\overline{X}) = X$$

Indeed, $X \subseteq \pi^{-1}(\pi(X))$, and if $\pi(g) \in \overline{X}$, then $gN = xN$ for some $x \in X$, so $g = ge \in gN = xN \subseteq X$ because $N \subseteq X$. We also use that for a subgroup C of any group and elements x, y of that group, $xC = yC$ exactly when $x^{-1}y \in C$: if $xC = yC$, then $y \in yC = xC$, so $x^{-1}y \in C$, and if $x^{-1}y = m \in C$, then $yC = x(mC) = xC$, since $mC = C$.

1. If $A \subseteq B$, then $\overline{A} = \pi(A) \subseteq \pi(B) = \overline{B}$. If $\overline{A} \subseteq \overline{B}$, then $A = \pi^{-1}(\overline{A}) \subseteq \pi^{-1}(\overline{B}) = B$.

2. Let $A \leqslant B$. For $b, b' \in B$,

$$bA = b'A \Leftrightarrow b^{-1}b' \in A \Leftrightarrow \pi(b^{-1}b') \in \overline{A} \Leftrightarrow \pi(b)^{-1}\pi(b') \in \overline{A} \Leftrightarrow \pi(b)\overline{A} = \pi(b')\overline{A}$$

   where the second equivalence holds because $A = \pi^{-1}(\overline{A})$. So $bA \mapsto \pi(b)\overline{A}$ is a well-defined injective map from the left cosets of A in B to the left cosets of $\overline{A}$ in $\overline{B}$. It is surjective, since every element of $\overline{B}$ is $\pi(b)$ for some $b \in B$. Both indices count left cosets, so $|B : A| = |\overline{B} : \overline{A}|$.

3. The subgroup $\langle A, B\rangle = \langle A \cup B\rangle$ contains N (definition 2.3.15). Its image $\overline{\langle A, B\rangle}$ is a subgroup of $\overline{G}$ containing $\overline{A} \cup \overline{B}$, so it contains $\langle \overline{A}, \overline{B}\rangle$ by proposition 2.3.17. Conversely, $P = \pi^{-1}(\langle \overline{A}, \overline{B}\rangle)$ is a subgroup of G by proposition 2.1.3, since $e \in P$ and $\pi(xy^{-1}) = \pi(x)\pi(y)^{-1} \in \langle \overline{A}, \overline{B}\rangle$ for $x, y \in P$. It contains A and B, so $\langle A, B\rangle \subseteq P$ by proposition 2.3.17, and $\overline{\langle A, B\rangle} = \pi(\langle A, B\rangle) \subseteq \pi(P) \subseteq \langle \overline{A}, \overline{B}\rangle$.

4. The subgroup $A \cap B$ contains N (proposition 2.3.14), and $\pi(A \cap B) \subseteq \pi(A) \cap \pi(B)$. Conversely, let $y \in \overline{A} \cap \overline{B}$ and write $y = \pi(g)$ with $g \in G$. Then $g \in \pi^{-1}(\overline{A}) = A$ and $g \in \pi^{-1}(\overline{B}) = B$, so $y = \pi(g) \in \pi(A \cap B)$. Hence $\overline{A \cap B} = \overline{A} \cap \overline{B}$.

5. Every element of $\overline{G}$ is $\pi(g)$ with $g \in G$, and every element of $\overline{A}$ is $\pi(a)$ with $a \in A$. Suppose $A \trianglelefteq G$, and let $g \in G$ and $a \in A$. Then $gag^{-1} \in A$ by proposition 3.1.11, so $\pi(g)\pi(a)\pi(g)^{-1} = \pi(gag^{-1}) \in \overline{A}$. Hence $\overline{A} \trianglelefteq \overline{G}$ by the equivalence of (5) and (1) in proposition 3.1.11. Conversely, suppose $\overline{A} \trianglelefteq \overline{G}$. For $g \in G$ and $a \in A$, $\pi(gag^{-1}) = \pi(g)\pi(a)\pi(g)^{-1} \in \overline{A}$ by proposition 3.1.11, so $gag^{-1} \in \pi^{-1}(\overline{A}) = A$. Hence $A \trianglelefteq G$ by proposition 3.1.11, completing the proof.

Another way of looking at the first part of the Correspondence Theorem is in the following slight generalization: Let G be a group and N a normal subgroup so that G/N is well-defined. If $\mathcal{G}$ contains all subgroups of G, for any $H \in \mathcal{G}$, the map $\pi : H \to G/N$, $\pi(h) = hN$ is well-defined. So, H maps to a subgroup of G/N. If $\mathcal{N}$ represents all subgroups of G/N, then there is a surjective map


$$\mathcal{G} \twoheadrightarrow \mathcal{N}$$

and if we take $\mathcal{G}|_N$ to be all subgroups that contain N, then there is a bijection between $\mathcal{G}|_N$ and $\mathcal{N}$:


$$\mathcal{G}|_N \leftrightarrow \mathcal{N}$$

Example 3.5.9: Using Correspondence Theorem

1. Let $G = Q_8$, and take $\langle -1 \rangle \trianglelefteq Q_8$. Then in the following lattice, the double lines represent the sublattice of Q_8 which is an isomorphic copy of the lattice of $Q_8/\langle -1 \rangle$



2. Let $G = D_4$ and let $\langle r^2 \rangle \trianglelefteq D_4$. Then with the same definitions as the last example, we get:



Notice that several subgroup of G (for example $\langle s \rangle$) become elements in a larger subgroup (in this case $\langle s, r^2 \rangle$). Thus, every subgroup of $\overline{G}$ might have multiple subgroups of G that map to it, but a unique subgroup which contains N.

A good example how the map of subgroup of G to G/N is surjective is by the following example: Notice that $Q_8/\langle -1 \rangle \cong D_4/\langle r^2 \rangle \cong \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z}$, and $\langle -1 \rangle \cong \langle r^2 \rangle$, but $Q_8 \ncong D_4$. We will explore this idea in more depth in the next section.

Exercise 3.5.1

1. (The *Butterfly Lemma*, Zassenhaus.) Let G be a group with subgroups $A' \trianglelefteq A$ and $B' \trianglelefteq B$. Show that $A'(A \cap B)$ is a subgroup of A, that $D = (A' \cap B)(A \cap B')$ is a normal subgroup of $A \cap B$, and that $A'(A \cap B')$ is a normal subgroup of $A'(A \cap B)$.

2. In the setting of exercise 3.5.1 (1), show that $a'x \mapsto xD$ ($a' \in A'$, $x \in A \cap B$) is a well-defined surjective homomorphism $A'(A \cap B) \to (A \cap B)/D$ with kernel $A'(A \cap B')$. Conclude that

$$\frac{A'(A \cap B)}{A'(A \cap B')} \cong \frac{A \cap B}{(A' \cap B)(A \cap B')} \cong \frac{B'(A \cap B)}{B'(A' \cap B)}$$

3. A *refinement* of a subnormal series (definition 3.7.3) is a subnormal series containing all of its terms. Use exercise 3.5.1 (2) to show that any two subnormal series of a group have refinements whose factors agree up to order and isomorphism (Schreier), and deduce part (2) of theorem 3.7.9.

3.6 Extensions

Recall (or revisit) that if $H \leqslant G$ (and G is finite), then the subgroup lattice of H is the sublattice of G of all groups *contained* in H (theorem 2.4.3), so *a fortiori* if $K \trianglelefteq G$ is a normal subgroup then the subgroup lattice of K is the sublattice of G of all subgroups contained in K. Even hen G is infinite, the set of subgroup of K is the set o subgroup of G which are contained in K. The Correspondence Theorem has shown us that the "dual" is true for quotient groups (except it orks for *all* groups, not just finite): If $K \trianglelefteq G$, then the subgroup lattice of G/K is the sublattice of G of all groups *containing* K. In this way, K and G/K together capture the subgroup structure of a group! In this section, we will explore how we can find a group structure given *only* the information from K and G/K.

More succintely, Given $K \trianglelefteq G$, the group K and G/K contain the subgroup structure of G. However, K and G/K do not capture the full structure of a group: in the process of quotienting, G/K losses some information:

Example 3.6.1: Subgroup And Quotient Group Limits

Take $G = D_4$ and $K = \{1, r, r^2, r^3\} \cong C_4$. Then $D_4/K \cong C_2$. Label this K'. Then given just K and K', one cannot guarantee that $K' = D_4/K$, other groups can take the place of D_4. For example:

$$H = C_4 \times C_2 \qquad \varphi : C_4 \times C_2 \to C_2,\ \varphi((a,b)) = ((0,b))$$

Here, H is another group here the kernel is C_4 and the quotient is C_2.

It must be noted though that there is still information within cosets: for any $x \in G$, then $[x] = xK \in G/K$, so for any $y \in xK$, $y = xk$ for appropriate $k \in K$ (proposition 3.1.3). This means for every coset, there is some information about how the elements relate. An easy example of this can be seen if $K = Z(G)$.

Example 3.6.2: Relation Within Cosets

Take $G/Z(G)$, which is a group since $Z(G) \trianglelefteq G$ (example 3.1.10). Take any $[x] \in G/Z(G)$, and any $a, b \in [x]$. Then $a = xz_a$ and $b = xz_b$, so $ab = xz_axz_b = xz_bxz_a = ba$ (since $z_a, z_b \in Z(G)$). Thus, within any coset of $G/Z(G)$, the elements commute! This is not nesesarily the case if the elements are *not* within the same coset (ex. $G = D_7$).

However, as we saw in example 3.6.1, there can be more than one group (say G') we can construct from K and K' (where $G'/K = K'$). We will call groups which can be built in this fashion *extension*:

Definition 3.6.3: Extension

Let A and B be groups. If $G/A \cong B$, then we say G *is an extension of* A *by* B.

The idea behind this name is that we want to be able to restrict G to A (i.e. A must be able to map

injectively and homomorphically into G; $A \hookrightarrow G$), similarly to how we can restrict functions (the dual of restricting functions is also called *extending* functions, where the extended function must be exactly the same as the orginal funciton when restricting).

As we saw at the beginning of this section, quotient groups are the perfect candidate for extension of groups since every group can be decomposed into a [normal] subgroup and quotient group.

Since all normal subgroups are also kernels, we can re-write what it means to be an extension in terms of homomorphisms. In the following definition, let I represent the trivial group.

Definition 3.6.4: Short Exact Sequence

Let A, B, C be group. If there exists an injective homomorphism f and a surjective homomorphism g such that

$$I \xrightarrow{\iota} A \xrightarrow{f} B \xrightarrow{g} C \xrightarrow{\pi} I$$

where $\text{im}(f) = \ker(g)$, ι is the trivial injective $(0 \mapsto 0)$ map and π is the total projective map $(c \mapsto 0)$, then we say that B *is an extension of* A *by* C.

Notice that $\text{im}(\iota) = \ker(f)$ since f is injective, $\text{im}(g) = \ker(\pi)$ since g is surjective, and $\text{im}(f) = \ker(g)$ by definition. A sequence in which the image of each map is the kernel of the next is called *exact*[6], whether it is short or a longer chain $X_1 \xrightarrow{f_1} X_2 \xrightarrow{f_2} X_3 \xrightarrow{f_3} X_4 \xrightarrow{f_4} \cdots$ (chapter 17⋆ returns to these). The exact sequence in definition 3.6.4 is the shortest non-trivial sequence with the trivial group at the beginning and end, and so it is called a short exact sequence.

For our purposes, exactness gives $C \cong B/f(A)$ with $f(A) \cong A$, so B is an extension of A by C.

Example 3.6.5: Short Exact Sequences

In the following examples, let 1 represent the trivial group

1. If $\varphi : G \to H$ is a homomorphism and $K = \ker(\varphi)$, we always have

   $$1 \to K \hookrightarrow G \xrightarrow{\varphi} \varphi(G) \to 1$$

   is a short exact sequence. If φ is surjective, then

   $$1 \to K \hookrightarrow G \xrightarrow{\varphi} H \to 1$$

   In this way, every surjective homomorphism represents an extension G of K by H.

2. Let A and B be two arbitrary groups. Then

   $$1 \to A \hookrightarrow A \times B \xrightarrow{(a,b)\mapsto(0,b)} B \to 1$$

   is a short exact sequence. In this way, any group can be extended by any other group to the extensions $A \times B$. This is sometimes called the *trivial extension* [a]

[6] A differential form is called *exact* when it lies in the image of the exterior derivative d, and for $k \geq 1$ the sequence of maps d between spaces of differential forms is exact in the present sense at the k-forms precisely when every closed k-form, one in the kernel of d, is exact. De Rham cohomology [79, De Rham Cohomology] measures the failure of this.

3. Take $A = B = 2$. Then
$$1 \to C_2 \xrightarrow{f} C_4 \xrightarrow{g} C_2 \to 1$$
where $f(x) = 2x$ and $g(0)$ and $g(2)$ both map to 0, while $g(1)$ and $g(3)$ map to 1. It is easy to verify that f and g are indeed homomorphism and that the above sequence is exact.

4. Similarly to the last example, Let $A = C_2$ and $B = C_8$ and $C = C_4$. Can you find the appropriate maps such that
$$1 \to C_2 \to C_8 \to C_4 \to 1$$
is a short exact sequence? Is the following
$$1 \to C_2 \to D_4 \to C_4 \to 1$$
also a short exact sequence with the appropriate maps?

[a] In fact, once we cover homological algebra in chapter 17⋆, the idea of this being the trivial extension will become rigorous

An extension of an X group by an X group is X. When is this statement true when X is:

1. cyclic
2. abelian
3. finite
4. finitely generated
5. Noetherian

It is in general difficult to tell when when given a short exact sequence if the sequence splits. In section 17.2, we will classify which *abelian groups* in a short exact sequence of abelian groups split[7] (abelian groups which always split in a short exact sequence of abelian groups be called *projective groups*). For general groups, the best tool we have is trying to identify when C acts on B.

A normal subgroup H of G gives the short exact sequence
$$1 \to H \to G \to G/H \to 1$$
and every element of G lies in a coset zH for a representative z chosen in each coset. It is natural to ask whether G can be thought of as "$(G/H) \cdot H$". This works when the representatives can be chosen to form a subgroup of G: the extension then splits, and G is a semi-direct product, the subject of chapter 5.

Exercise 3.6.1

1. Let $0 \to \mathbb{Z} \to B \to A \to 0$ be an extension, where B is an abelian group and A is free. Show that B splits. (The converse, that an abelian group A over which every such extension splits is free, is known as Whitehead's problem, and it can be neither proved nor disproved from the ZFC axioms.)

[7] It will turn out that all abelian groups are $\mathbb{Z}$-modules, and so this will be a consequence of classifying when modules split with the space case of when the module is over $\mathbb{Z}$

2. Let $1 \to A \xrightarrow{f} G \xrightarrow{g} B \to 1$ be a short exact sequence of groups with B finite. Show that $f(A)$ is a normal subgroup of G of index $|B|$.

3.7 Classifying all Finite Groups: Hölder Program

With the isomorphism theorems under our belt, we are ready to tackle one of the central questions posed by group-theorists: How can we classify all groups? This sections start by building up the mental models used in order to comprehend the way classification efforts.

We can approach the problem of classification in many different ways. We briefly mentioned the idea trying to construct arbitrary presentation's of groups to try and create groups, but we have mentioned that this can create "insoluble presentation", meaning presentaion in which we cannot represent every element. In general, it is very hard to find groups in that manner. Perhaps instead we can start with the groups we knwo and see if there is a way to "decompose" them. The first thing you might try is decomposing the group into cyclic sub-groups. This is certainly possible (take an element, generate a group from it, remove those elements from your origianl group, continue doing this till you have exhausted the group [8]). But how would you then put them back together? For example, we know that $\langle r \rangle, \langle s \rangle \leqslant D_4$. With what we have learnt, is there a way to represent D_4 using these? In fact, we have just seen that we can but them back together using short exact sequences! The group D_4 is an extension of C_2 by C_4.

However, we must be more careful using extensions when we are trying to classify groups. Are cyclic subgroups really the way to go? In fact, this is not the case: there exists cyclic groups which are an extension of smaller groups. We would want to be able to have some fixed subgroups we can use as our "building puzzles" which are not extensions of any other groups. In this section we will define these "smalles puzzle pieces" or "atoms of groups". Try taking a moment to see if you can come up with a more suitable definition of "smallest puzzle piece" for groups and have an idea of an example of a group following your definition.

Every finite simple group (definition 3.7.1) appears in the list of theorem 3.7.11, the classification of finite simple groups, whose proof occupied group theorists for the better part of the 20th century. For abelian groups the classification is much simpler: theorem 5.1.6 describes every finitely generated abelian group.

Defining our Terms

First, we will have to define what would be our "puzzle piece". Since we are using extensions, we know there is a non-trivial homomorphism from a group G to another group H if G has a non-trivial normal subgroup. If G has *only* trivial subgroups, the structure of G is not "composed" of other possible structure but is as "simple" as possible. This motivates the folloing definition.

Definition 3.7.1: Simple Groups

A (finite or infinite) group G is called *simple* if $|G| > 1$ and the only normal subgroups of G are 1 and G.

[8] This works well in groups of *countable* size. One has to be more careful for groups of *uncountable* size, where the axiom of choice is involved (see appendix A for details on the axiom of choice).

These groups are called "simple" because there are no more group-structures within them [9]. To undersatnd what "no more group-structures within them" means, recall the 4th isomorphism theorem. If N is a noraml subgroup, then ther is a direct correspondence between the subgroups of G/N and the subgroups of G containing N. If there is no $N \trianglelefteq G$ besides $\{1\}$ and G, then the lattice of G cannot be split into G/N and G. So in a sense, that lattice is as small as it gets.

Example 3.7.2: Simple Groups

By Lagrange's theorem, a group of prime order p has no subgroups other than 1 and itself, so groups of prime order are simple. If G is abelian and simple, then every subgroup is normal, so $G = \langle x \rangle$ for any $x \neq e$ and G is cyclic. It is not infinite, since $\mathbb{Z}$ has the proper nontrivial subgroup $2\mathbb{Z}$. So $G \cong \mathbb{Z}/n\mathbb{Z}$, which has a subgroup of order d for every $d \big| n$ (theorem 2.3.11), forcing n to be prime.

There are also non-abelian simple groups, both infinite and finite. The alternating group A_5, of order 60, is simple by theorem 4.9.6.

Looking at simple groups a little more abstractly for a moment, they play an analogous role to primes in arithmetic's of $\mathbb{N}$ as in they cannot be "factored" into smaller [meaningful] pieces[10] (i.e. N and G/N). There is even a "unique factorization theorem" based on this idea. First, we will define what is meant by "factorize" a group

Definition 3.7.3: Subnormal Series

Let G be a group. Then

$$G = G_1 \geqslant G_2 \geqslant G_3 \geqslant \cdots \geqslant G_n = \{1\}$$

is called a *series* (or *tower*) for the group G. If every $G_i \trianglelefteq G$, then G the series is called a *normal series*. If $G_i \trianglelefteq G_{i-1}$ for every $1 \leq i \leq n$, then we call the series a *subnormal series*:

$$G = G_1 \trianglerighteq G_2 \trianglerighteq \cdots \trianglerighteq G_n = \{1\}$$

Sometimes, [normal/subnomral] series are written in the ascending, rather than descending order:

$$\{1\} = G_0 \leqslant G_1 \leqslant \cdots \leqslant G_n = G$$

I chose to write them in descending order since down the line we will be comparing some types of series to other types, and if everything is written in descending order, then we'd have a scendario were we start writing $G_{n-i} \trianglelefteq B_i$ ineated of $G_i \trianglelefteq B_i$, which I feel will make the simple relations a little more notationaly cumbersome than it needs to be.

You might ask whether this a subnormal series would imply a noraml series, that is, that $N_i \trianglelefteq G$? However, that does not need to be the case:

[9] The term simple is one that comes up often enough in matheamtics. It has a sligthly more nuanced meaning than just the simplest object (ex. the trivial group is not a simple group, it's "too simple to be simple". See this nlab article on simple objects

[10] meaningful here meaning there is a notion of combining groups using short exact sequence, unlike general groups cannot be

Example 3.7.4: Normality *not* transitive
Here's an example of how normality is *not* transitive. Let $G = D_4$. Let $H \trianglelefteq G$ such that $H = \langle r\sigma, \sigma r\rangle$. Next, take $K \trianglelefteq H$ such that $K = \langle r\sigma\rangle$. Note that

$$K \trianglelefteq H \trianglelefteq G$$

but $K \not\trianglelefteq G$

thus a subnormal series need not be a noraml series. However, a normal series is a subnormal series: if $N_{i+1} \trianglelefteq G$, then $gN_{i+1}g^{-1} = N_{i+1}$ for every $g \in G$. If we restrict to every $n \in N_i$, then since $N_i \subseteq G$, it is already the cse that $nN_{i+1}n^{-1} = N_{i+1}$. Thus $N_{i+1} \trianglelefteq N_i$. Thus:

$$\text{normal series} \Rightarrow \text{subnormal series} \qquad \text{subnormal series} \not\Rightarrow \text{normal series}$$

Thus, subnormal series can be thought of as the decomposition of a group.

Example 3.7.5: Refining A Subnormal Series
In $G = \mathbb{Z}/8\mathbb{Z}$ every subgroup is normal (corollary 3.1.12), so

$$\mathbb{Z}/8\mathbb{Z} \trianglerighteq \langle 4\rangle \trianglerighteq 0 \qquad \text{and} \qquad \mathbb{Z}/8\mathbb{Z} \trianglerighteq \langle 2\rangle \trianglerighteq \langle 4\rangle \trianglerighteq 0$$

are subnormal series, and the second is obtained from the first by inserting the term $\langle 2\rangle$. The subgroups $\langle 2\rangle$ and $\langle 4\rangle$ have orders 4 and 2, so the terms of the second series have orders $8, 4, 2, 1$. No term can be inserted into the second series: a subgroup M strictly between two consecutive terms would have order divisible by the order of the smaller term and dividing the order of the larger one (theorem 3.3.1), and different from both, which is impossible when the two orders differ by a factor of 2.

In the second series of example 3.7.5 every factor has order 2, hence is simple (example 3.7.2). A series all of whose factors are simple has a name:

Definition 3.7.6: Composition Series

In a group G, a sequence of groups

$$1 = N_0 \leqslant N_1 \leqslant N_2 \leqslant \cdots \leqslant N_{k-1} \leqslant N_k = G$$

is called a *composition series* if $N_i \trianglelefteq N_{i+1}$ and N_{i+1}/N_i is a simple group, for all $0 \leq i \leq k-1$. If the above sequence is a composition series, the quotient group N_{i+1}/N_i are called the *composition factors* of G.

Every finite group $G \neq 1$ has a composition series, as part (1) of theorem 3.7.9 below shows.

Example 3.7.7: Some Composition Series
Take $\mathbb{Z}_p \times \mathbb{Z}_q$. Then

$$\{e\} \trianglelefteq \mathbb{Z}_p \times \{e\} \trianglelefteq \mathbb{Z}_p \times \mathbb{Z}_q$$
$$\{e\} \trianglelefteq \{e\} \times \mathbb{Z}_q \trianglelefteq \mathbb{Z}_p \times \mathbb{Z}_q$$

The quotient of any two will produce simple groups

Take Q_8 Then

$$\{e\} \trianglelefteq \langle -1\rangle \trianglelefteq \langle i\rangle \trianglelefteq Q_8$$
$$\{e\} \trianglelefteq \langle -1\rangle \trianglelefteq \langle j\rangle \trianglelefteq Q_8$$
$$\{e\} \trianglelefteq \langle -1\rangle \trianglelefteq \langle k\rangle \trianglelefteq Q_8$$

Where I figured out the composition series with the help of the lattice of subgroups to trace possible paths and figuring out whether they are normal or not. The quotient so any of these factors will be isomorphic to $\mathbb{Z}_2$, which is simple, and thus there are composition series.

another example is:

$$1 \trianglelefteq \langle s\rangle \trianglelefteq \langle s, r^2\rangle \trianglelefteq D_4 \qquad \text{and} \qquad 1 \trianglelefteq \langle r^2\rangle \trianglelefteq \langle r\rangle \trianglelefteq G$$

Not every infinite group has a composition series.

Example 3.7.8: The Integers Have No Composition Series

Suppose $0 = N_0 \trianglelefteq N_1 \trianglelefteq \cdots \trianglelefteq N_k = \mathbb{Z}$ were a composition series. Then $k \geq 1$ and $N_1 \cong N_1/N_0$ is a nonzero simple group. By theorem 2.3.11, $N_1 = m\mathbb{Z}$ for some $m \geq 1$. But $2m\mathbb{Z}$ is a subgroup of $m\mathbb{Z}$ different from 0 and from $m\mathbb{Z}$, since $m \notin 2m\mathbb{Z}$, and it is normal because $\mathbb{Z}$ is abelian. So $m\mathbb{Z}$ is not simple, a contradiction.

A subnormal series

$$G = G_0 \trianglerighteq G_1 \trianglerighteq G_2 \trianglerighteq \cdots \trianglerighteq G_n = \{1\}$$

breaks into short exact sequences:

$$1 \longrightarrow G_{n-1} \longrightarrow G_{n-2} \longrightarrow G_{n-2}/G_{n-1} \longrightarrow 1$$
$$1 \longrightarrow G_i \longrightarrow G_{i-1} \longrightarrow G_{i-1}/G_i \longrightarrow 1 \quad 1 \longrightarrow G_1 \longrightarrow G_0 \longrightarrow G_0/G_1 \longrightarrow 1$$

so G is built from the quotients $G_0/G_1, G_1/G_2, \ldots, G_{n-1}/G_n = G_{n-1}$ by successive extensions. For a composition series these quotients are simple groups.

One might ask about if a composition series is supposed to be unique factorization, what about there being 3 composition series for Q_8, and what about the re-arranging we have done of $\mathbb{Z}_p \times Z_q$? The *quotients* of each N_{i+1}/N_i will be unique *up to rearrangement*! That is the content of the next theorem:

Theorem 3.7.9: Jordan-Hölder's Theorem

Let G be a finite group with $G \neq 1$. Then

1. G has a composition series
2. The composition factors in a composition series are unique, namely, if $1 = N_0 \leqslant N_1 \leqslant \cdots \leqslant N_r = G$, and $1 = M_0 \leqslant M_1 \leqslant \cdots \leqslant M_s = G$, are two composition series of G, then $r = s$ and there is some permutation π of $\{1, 2, ..., r\}$ such that

$$M_{\pi(i)}/M_{\pi(i)-1} \cong N_i/N_{i-1} \qquad 1 \leq i \leq r$$

***Proof*:**
In a composition series each factor N_i/N_{i-1} is simple, hence nontrivial (definition 3.7.1), so $N_{i-1} \subsetneq N_i$ and the orders $|N_0| < |N_1| < \cdots < |N_r|$ strictly increase.

Step 1: if $N \trianglelefteq G$ and G/N is simple, the only normal subgroups of G containing N are N and G. Let $L \trianglelefteq G$ with $N \subseteq L$. By corollary 3.5.8(5), $L/N \trianglelefteq G/N$, so L/N is N/N or G/N. In the first case $L/N \subseteq N/N$, so $L \subseteq N$ by corollary 3.5.8(1), and $L = N$. In the second case $G/N \subseteq L/N$, so $G \subseteq L$ in the same way, and $L = G$.

Step 2: if N has the largest order among the normal subgroups of G different from G, then G/N is simple. First, $|G/N| > 1$ because $N \neq G$. Let $\overline{M} \trianglelefteq G/N$. By theorem 3.5.7, $\overline{M} = M/N$ for a subgroup M of G containing N, and $M \trianglelefteq G$ by corollary 3.5.8(5). If $M \neq G$, then $|M| \leq |N|$ by the choice of N, and $N \subseteq M$ gives $M = N$, so $\overline{M} = N/N$ is trivial. Otherwise $\overline{M} = G/N$. So G/N is simple.

Step 3: part (1). We use strong induction on $|G|$. Since $G \neq 1$, the trivial subgroup is a normal subgroup different from G, so among the finitely many normal subgroups different from G there is one, N, of largest order, and G/N is simple by Step 2. If $N = 1$, then $1 = N_0 \leqslant N_1 = G$ is a composition series. If $N \neq 1$, then $|N| < |G|$, and the induction hypothesis gives a composition series $1 = N_0 \leqslant \cdots \leqslant N_k = N$ of N. Since $N \trianglelefteq G$ and G/N is simple, putting $N_{k+1} = G$ gives a composition series of G.

Step 4: lists of factors. Call two finite lists of groups $(X_1, \ldots, X_r)$ and $(Y_1, \ldots, Y_s)$ *equivalent* if $r = s$ and there is a permutation π of $\{1, \ldots, r\}$ with $Y_{\pi(i)} \cong X_i$ for $1 \leq i \leq r$. This relation is reflexive, symmetric and transitive: use the identity permutation, the inverse permutation with the inverse isomorphisms, and the composite of two permutations with the composite isomorphisms. Reordering a list, or replacing an entry by an isomorphic group, gives an equivalent list. If X is equivalent to Y and X' to Y', then the list X followed by X' is equivalent to the list Y followed by Y', by using the two permutations side by side. The *list of factors* of a composition series $1 = N_0 \leqslant \cdots \leqslant N_r = G$ is $(N_1/N_0, \ldots, N_r/N_{r-1})$, and part (2) says exactly that any two composition series of G have equivalent lists of factors.

Step 5: part (2). We use strong induction on $|G|$. Let $1 = N_0 \leqslant \cdots \leqslant N_r = G$ and $1 = M_0 \leqslant \cdots \leqslant M_s = G$ be composition series. As $G \neq 1$, $r \geq 1$ and $s \geq 1$. Put $N = N_{r-1}$ and $M = M_{s-1}$. Then $N \trianglelefteq G$ and $M \trianglelefteq G$, the groups G/N and G/M are simple, and in particular $N \neq G$ and $M \neq G$.

Suppose first that $N = M$. If $N = 1$, then $N_{r-1} = N_0$ and $M_{s-1} = M_0$, so $r = s = 1$ because the orders increase strictly, and both lists of factors are $(G/1)$. If $N \neq 1$, then $1 = N_0 \leqslant \cdots \leqslant N_{r-1} = N$ and $1 = M_0 \leqslant \cdots \leqslant M_{s-1} = N$ are composition series of N, and $|N| < |G|$. By the induction hypothesis, $r - 1 = s - 1$ and their lists of factors are equivalent. Appending the common factor G/N to both shows that the two lists of factors of G are equivalent.

Suppose now that $N \neq M$. Since N and M are normal, $N_G(N) = N_G(M) = G$ (proposition 3.1.11), so theorem 3.5.4 applies with $A = M$ and $B = N$, and with $A = N$ and

$B = M$. For $m \in M$ and $n \in N$, $mn = (mnm^{-1})m \in NM$ and $nm = m(m^{-1}nm) \in MN$, so $MN = NM$, a subgroup of G by theorem 3.5.4. It is normal in G by proposition 3.1.11, since $g(mn)g^{-1} = (gmg^{-1})(gng^{-1}) \in MN$ for $g \in G$. By Step 1 applied to N, either $MN = N$ or $MN = G$. If $MN = N$, then $M \subseteq N$, and Step 1 applied to M gives $N = M$ or $N = G$, both of which are excluded. Hence $MN = G$. Put $D = M \cap N$. By theorem 3.5.4, $D \trianglelefteq M$, $D \trianglelefteq N$ and

$$G/N = MN/N \cong M/D \qquad G/M = NM/M \cong N/D$$

A group isomorphic to a simple group is simple, since an isomorphism carries the normal subgroups of one group bijectively onto those of the other. So M/D and N/D are simple, and in particular $M \neq 1$ and $N \neq 1$.

If $D \neq 1$, part (1) gives a composition series $1 = D_0 \leqslant \cdots \leqslant D_t = D$ of D, and if $D = 1$ put $t = 0$ and $D_0 = D$. Let $\Delta = (D_1/D_0, \ldots, D_t/D_{t-1})$, the empty list when $t = 0$. Then $1 = D_0 \leqslant \cdots \leqslant D_t \leqslant N$ is a composition series of N whose list of factors is Δ followed by N/D, and $1 = D_0 \leqslant \cdots \leqslant D_t \leqslant M$ is a composition series of M whose list of factors is Δ followed by M/D. Since $|N| < |G|$, the induction hypothesis for N gives $r - 1 = t + 1$ and shows that $(N_1/N_0, \ldots, N_{r-1}/N_{r-2})$ is equivalent to Δ followed by N/D. In the same way $s - 1 = t + 1$, and $(M_1/M_0, \ldots, M_{s-1}/M_{s-2})$ is equivalent to Δ followed by M/D. Hence $r = s$. Appending the last factors and using $N/D \cong G/M$ and $M/D \cong G/N$, the list of factors of the first series of G is equivalent to Δ followed by $G/M, G/N$, and that of the second series is equivalent to Δ followed by $G/N, G/M$. These two lists differ only in the order of their last two entries, so the two lists of factors of G are equivalent, as we sought to show.

3.7.10 Historical Note: The Hölder Program By theorem 3.7.9, a finite group $G \neq 1$ determines a list of finite simple groups, its composition factors, and G is assembled from them by successive extensions (definition 3.6.3). This splits the classification of finite groups into two problems, known together as the *Hölder program*:

1. classify all finite simple groups
2. determine all ways of assembling finite groups from given composition factors, that is, given groups K and Q, find all groups G with a normal subgroup isomorphic to K whose quotient is isomorphic to Q (the extension problem of section 3.6)

The first problem was solved by the classification of finite simple groups, stated below as theorem 3.7.11, whose proof was completed by the early 2000s. The second problem remains open in general.

Theorem 3.7.11: Types of Finite Groups

There is a list consisting of 18 (infinite) families of simple groups and 26 (or 27 [a]) simple groups not belonging to these families (the *sporadic* simple groups) such that every finite simple group is isomorphic to one of the groups in this list

[a] some include Tits group

The proof of theorem 3.7.11 is spread over hundreds of journal articles totalling tens of thousands

of pages, and it relies on character theory, modular representation theory and the local analysis of finite groups, which this book does not develop. An outline of the whole proof, with the groups of characteristic 2 type treated in detail, is the monograph of Aschbacher, Lyons, Smith and Solomon, *The Classification of Finite Simple Groups: Groups of Characteristic 2 Type* [6].

***Proof Key ideas*:**
By the theorem of Feit and Thompson [50], a nonabelian finite simple group has even order, so it has an element of order 2 by theorem 4.8.7. Brauer and Fowler [9] showed that the order of a finite simple group is bounded in terms of the order of the centralizer of any of its elements of order 2, which suggests identifying simple groups through these centralizers. The bulk of the proof analyses the normalizers of nontrivial p-subgroups, the *local subgroups*. The groups whose elementary abelian 2-subgroups are all small, mostly groups of Lie type of small rank over fields of odd characteristic, are treated separately. The others divide into two kinds: those of *characteristic* 2 *type*, whose local subgroups for the prime 2 resemble those of groups of Lie type over fields of characteristic 2, and those of *component type*, in which the centralizer of some element of order 2 involves a smaller nonabelian simple group, to which induction applies. In each case the local data are shown to match those of a group on the list, and the sporadic groups are the configurations that match no infinite family. The last case, that of the quasithin groups, was settled by Aschbacher and Smith [4, 5] in 2004, completing the classification.

Example 3.7.12
Here are a couple such family of groups:

1. $\{Z_p | p \text{ is prime } \}$
2. the groups $SL_n(\mathbb{F})/Z(SL_n(\mathbb{F}))$ with $n \geq 2$ and $\mathbb{F}$ a finite field, with two exceptions. The groups $SL_2(\mathbb{F}_2)/Z(SL_2(\mathbb{F}_2))$ and $SL_2(\mathbb{F}_3)/Z(SL_2(\mathbb{F}_3))$ have orders 6 and 12, are isomorphic to S_3 and A_4, and are not simple. Every other group in the family is simple, by a theorem of Jordan and Dickson [86, 3.2.9 and p. 78].
3. A_n, $n \geq 5$.

The groups $SL_n(\mathbb{F})/Z(SL_n(\mathbb{F}))$ are the first examples of the *groups of Lie type*, and the remaining families are further groups of Lie type [86, Section 3.2].

Exercise 3.7.1

1. Let $H \trianglelefteq G$ with $H \neq G$. Call H a *maximal normal subgroup* if the only normal subgroups K of G with $H \subseteq K$ are H and G. Show that H is a maximal normal subgroup if and only if G/H is a simple group.

4

Group Actions

In Section 1.5, we saw that groups arise naturally as *symmetries*. The dihedral group captures the symmetries of a polygon, the symmetric group captures rearrangement of a finite set, the general linear group captures invertible linear transformation of a vector space, and so forth. Historically, groups *were* symmetry groups before they were axiomatized. The abstract axioms we introduced in Section 1.1 are a *distillation* of what all these concrete symmetry groups have in common.

In this chapter, we reverse the process. Having built the abstract theory we now reconnect it to its roots by developing the theory of *group actions*: the study of how a group can act on a set (or on itself). We will show:

1. The Orbit-Stabilizer Theorem (section 4.3). If a group G acts on a set X, then X decomposes into orbits, and the size of each orbit is controlled by a subgroup of G (the stabilizer). This is, in spirit, a generalization of Lagrange's Theorem (theorem 3.3.1). We shall see that if the action is *transitive*, then X can be represented as cosets of G, leading the way to motivate why it is natural to study actions of a group on itself

2. Cayley's Theorem (section 4.5). Every group is isomorphic to a subgroup of a symmetric group. In other words, every abstract group *is* a group of permutations.

3. The Class Equation (section 4.6). By letting a group act on itself by conjugation, we obtain an arithmetic identity that splits $|G|$ into contributions from the center $Z(G)$ (definition 2.2.4) and the non-central conjugacy classes. This will immediately imply that every p-group has a nontrivial center.

4. The Sylow Theorems (section 4.8). For any prime p dividing $|G|$, Sylow's three theorems guarantee the *existence* of subgroups of maximal p-power order, prove they are all *conjugate* (hence isomorphic), and tightly constrain their *number*. These theorems are among the most powerful tools in finite group theory.

Along the way, we will see several important *types* of actions (faithful, transitive, free, and regular) and see how each captures a different facet of the relationship between a group and the object it acts on.

A recurring theme will be that the most important applications of group actions come not from letting a group act on some external set, but from letting a group act *on itself* or on its own substructure (elements, subsets, cosets). When a group acts on itself by left multiplication, we get Cayley's Theorem. When it acts on its cosets, we get structural information about normal subgroups. When it acts on itself by conjugation, we get the Class Equation. When it acts on the set of its own Sylow subgroups, we get the Sylow counting theorem. Each of these is an instance of the same machine. What changes is the *choice of action*, and each choice reveals different information.

4.0.1 Applied Aside: Klein's Erlangen Programme In 1872, Felix Klein presented a new vision of geometry at the University of Erlangen. Rather than defining geometries axiomatically (as Euclid had done), Klein proposed that a *geometry* is a set X together with a group G acting on it, and that the "geometric properties" of X are precisely those invariant under the action of G.

Under this lens, different choices of group yield different geometries:

Group G	**Set** X	**Geometry**
Euclidean isometries	$\mathbb{R}^2$	Euclidean geometry
Affine transformations	$\mathbb{R}^2$	Affine geometry
Projective transformations	$\mathbb{RP}^2$	Projective geometry

Euclidean geometry studies properties like distance and angle (invariant under rigid motions); affine geometry studies parallelism (invariant under the larger group of affine maps); projective geometry studies incidence (invariant under the still larger projective group). More symmetry means fewer invariants, hence a "coarser" geometry.

Klein's Programme was one of the first explicit formulations of the idea that *group actions define structure*. It remains a guiding principle: in differential geometry, in topology, and throughout modern mathematics, the question "what is the symmetry group, and how does it act?" is often the first one asked.

4.1 Definitions and First Examples

In Section 1.5, we observed informally that a group can "act" on a set by rearranging its elements. Our goal now is to make this precise. We will give two equivalent formulations of the definition (one emphasizing the homomorphism, the other emphasizing axioms on the action map) and prove that they are interchangeable.

The Homomorphism Definition

Let us return to the motivating example from the prelude. The dihedral group D_n (definition 1.2.28) acts on the set of vertices $\{1, 2, \ldots, n\}$ of a regular n-gon. Each element $g \in D_n$ determines a bijection of the vertex set: a rotation cyclically permutes the labels, a reflection swaps them. Different elements yield different (or sometimes the same) bijections, and, crucially, performing one symmetry followed by another corresponds to composing the associated bijections.

In other words, there is a map ρ that assigns to each group element $g \in D_n$ a permutation $\rho(g) \in \mathrm{Sym}(\{1, \ldots, n\})$, and this map *respects the group structure*: $\rho(gh) = \rho(g) \circ \rho(h)$. That is, ρ is a homomorphism (definition 1.4.2). This observation is the definition.

Definition 4.1.1: Group Action

Let G be a group and let X be a set. A *group action* of G on X is a group homomorphism

$$\rho \colon G \to \mathrm{Sym}(X),$$

where $\mathrm{Sym}(X)$ is the symmetric group on X (definition 1.2.12), i.e. the group of all bijections $X \to X$ under composition.
We write $G \curvearrowright X$ (read "G *acts on* X") to indicate that such a homomorphism has been specified. The set X, together with the action ρ, is called a ***G-set***.

Let us unpack what this definition gives us concretely.

- For each $g \in G$, the image $\rho(g)$ is an element of $\mathrm{Sym}(X)$, that is, a *bijection* from X to X. We can *evaluate* this bijection at any point $x \in X$ to obtain an element $\rho(g)(x) \in X$. One should read "$\rho(g)(x)$" as: *"the result of applying the permutation $\rho(g)$ to the element x."*
- Since ρ is a homomorphism, it respects composition: $\rho(gh) = \rho(g) \circ \rho(h)$ for all $g, h \in G$.
- Since ρ is a homomorphism, it sends the identity to the identity (proposition 1.4.4): $\rho(e) = \mathrm{id}_X$, the identity permutation.

It is convenient to introduce a shorthand that suppresses the homomorphism ρ:

$$g \cdot x \;:=\; \rho(g)(x) \qquad \text{for all } g \in G,\ x \in X.$$

In this notation, the two properties above translate into:

1. Compatibility: $(gh) \cdot x \;=\; g \cdot (h \cdot x)$ for all $g, h \in G$ and $x \in X$.
2. Identity: $e \cdot x \;=\; x$ for all $x \in X$.

These are not new axioms: they are automatic consequences of ρ being a homomorphism. The natural question is: are they *sufficient*? That is, if we have a rule "$g \cdot x$" satisfying just these two properties, does it necessarily come from a homomorphism to $\mathrm{Sym}(X)$? The answer is yes.

The Axiomatic Characterization

Many textbooks take the following as the *definition* of a group action, and then derive the homomorphism as a consequence. Since we have gone the other direction, we state it as a theorem establishing the equivalence.

Theorem 4.1.2: Equivalence of Definitions

Let G be a group and X a nonempty set. There is a bijective correspondence between:

(a) group homomorphisms $\rho\colon G \to \mathrm{Sym}(X)$, and

(b) functions $\cdot\colon G \times X \to X$, written $(g,x) \mapsto g \cdot x$, satisfying

(A1) $(gh)\cdot x = g\cdot(h\cdot x)$ for all $g,h \in G$ and $x \in X$, and

(A2) $e \cdot x = x$ for all $x \in X$.

The correspondence is given by $g \cdot x = \rho(g)(x)$.

***Proof*:**

(a)⇒(b). Given a homomorphism $\rho\colon G \to \mathrm{Sym}(X)$, define $g \cdot x := \rho(g)(x)$. We check the two axioms.

For (A1): since ρ is a homomorphism, $\rho(gh) = \rho(g) \circ \rho(h)$, so

$$(gh)\cdot x \;=\; \rho(gh)(x) \;=\; \big(\rho(g)\circ\rho(h)\big)(x) \;=\; \rho(g)\big(\rho(h)(x)\big) \;=\; g\cdot(h\cdot x).$$

For (A2): since ρ sends identities to identities (proposition 1.4.4), $\rho(e) = \mathrm{id}_X$, so

$$e\cdot x \;=\; \rho(e)(x) \;=\; \mathrm{id}_X(x) \;=\; x.$$

(b)⇒(a). Given a function $\cdot\colon G \times X \to X$ satisfying (A1) and (A2), we must construct a homomorphism $\rho\colon G \to \mathrm{Sym}(X)$. For each $g \in G$, define the function

$$\sigma_g\colon X \to X, \qquad \sigma_g(x) = g\cdot x.$$

We must show two things: that each σ_g is a bijection (hence an element of $\mathrm{Sym}(X)$), and that the map $g \mapsto \sigma_g$ is a group homomorphism.

Step 1: Each σ_g is a bijection. We claim that $\sigma_{g^{-1}}$ is a two-sided inverse for σ_g. For any $x \in X$:

$$(\sigma_g \circ \sigma_{g^{-1}})(x) = \sigma_g(g^{-1}\cdot x) = g\cdot(g^{-1}\cdot x) \overset{\text{(A1)}}{=} (gg^{-1})\cdot x = e\cdot x \overset{\text{(A2)}}{=} x,$$

so $\sigma_g \circ \sigma_{g^{-1}} = \mathrm{id}_X$. An identical computation gives $\sigma_{g^{-1}} \circ \sigma_g = \mathrm{id}_X$. Thus σ_g is a bijection, and $\sigma_g \in \mathrm{Sym}(X)$.

Step 2: $g \mapsto \sigma_g$ is a homomorphism. Define $\rho\colon G \to \mathrm{Sym}(X)$ by $\rho(g) = \sigma_g$. For any $g,h \in G$ and $x \in X$:

$$\rho(gh)(x) = \sigma_{gh}(x) = (gh)\cdot x \overset{\text{(A1)}}{=} g\cdot(h\cdot x) = \sigma_g(\sigma_h(x)) = (\sigma_g\circ\sigma_h)(x) = \big(\rho(g)\circ\rho(h)\big)(x).$$

Since this holds for every $x \in X$, we have $\rho(gh) = \rho(g)\circ\rho(h)$, so ρ is a homomorphism.

Finally, these two constructions are inverse to each other: starting from ρ, forming $g\cdot x = \rho(g)(x)$, and then recovering the homomorphism $g \mapsto \sigma_g$ gives back $\sigma_g = \rho(g)$; conversely, starting from $\cdot$, forming $\rho(g) = \sigma_g$, and then recovering the action gives $\rho(g)(x) = \sigma_g(x) = g\cdot x$. Thus the correspondence is bijective.

4.1.3 Remark: Currying The equivalence above is an instance of a general phenomenon in mathematics (and computer science) called *currying*. A function of two variables $\cdot\colon G \times X \to X$ can be equivalently viewed as a function of one variable $\rho\colon G \to X^X$ that returns a *function* $X \to X$. The group action axioms are exactly the conditions ensuring that ρ lands in $\mathrm{Sym}(X) \subseteq X^X$ and is a homomorphism. This point of view (recasting a "two-variable" structure as a "one-variable" homomorphism) will reappear when we study modules and representations.

Thanks to theorem 4.1.2, we may define group actions using whichever formulation is most convenient. In practice:

- To define an action on a concrete set, it is usually easiest to write down a rule $g \cdot x =$ (some formula) and verify axioms (A1) and (A2).
- To reason abstractly about actions (e.g. to apply the isomorphism theorems), it is usually more powerful to work with the homomorphism $\rho\colon G \to \mathrm{Sym}(X)$.

We give a name to this homomorphism when it arises from an action:

Definition 4.1.4: Permutation Representation

If $G \curvearrowright X$ is a group action, the associated homomorphism $\rho\colon G \to \mathrm{Sym}(X)$ is called the *permutation representation* of the action. We say the action *affords* or *induces* the permutation representation ρ.

Since ρ is a homomorphism, all the tools we developed for homomorphisms apply: its kernel $\ker(\rho)$ is a normal subgroup of G (proposition 2.2.12), its image $\rho(G)$ is a subgroup of $\mathrm{Sym}(X)$ (proposition 1.4.8), and the First Isomorphism Theorem (theorem 3.1.15) gives $G/\ker(\rho) \cong \rho(G) \leq \mathrm{Sym}(X)$. We will exploit these facts heavily starting in Section 4.2.

We close this subsection by recording why we chose the homomorphism formulation as our leading definition. This is a matter of taste, but the reasoning is forward-looking:

- A group action is a homomorphism $G \to \mathrm{Sym}(X)$.
- A linear representation (definition 53.1.1) will be a homomorphism $G \to GL(V)$.
- A module (Part III) will be defined via a ring homomorphism $R \to \mathrm{End}(M)$.

Example 4.1.5: Fundamental Group Actions

1. *The tautological action of S_n.* Let $G = S_n$ and $X = \{1, 2, \ldots, n\}$. Define
$$\sigma \cdot i \;=\; \sigma(i).$$
The permutation representation is the identity map $\rho = \mathrm{id}\colon S_n \to \mathrm{Sym}(\{1, \ldots, n\}) = S_n$, which is trivially a homomorphism. This is the most elementary group action: each permutation simply *does what it says*.
2. *Dihedral symmetries of a regular n-gon.* Let $G = D_n$ (definition 1.2.28) and let $X = \{1, 2, \ldots, n\}$ represent the vertices of a regular n-gon, labeled clockwise. The rotation r

acts by $r \cdot i = i + 1 \pmod{n}$, and the reflection s acts by $s \cdot i = n + 1 - i \pmod{n}$ (with an appropriate labeling convention). The permutation representation $\rho\colon D_n \to S_n$ is an injective homomorphism, embedding D_n as a subgroup of S_n.

3. *Matrix groups acting on vectors.* Let $G = GL_n(\mathbb{R})$ (definition 1.2.33) and $X = \mathbb{R}^n$. Define

$$A \cdot \vec{x} \;=\; A\vec{x} \qquad \text{(matrix-vector multiplication)}.$$

Axiom (A1) is the associativity of matrix multiplication: $(AB)\vec{x} = A(B\vec{x})$. Axiom (A2) is the identity matrix property: $I_n\vec{x} = \vec{x}$. Thus this defines a group action.

This action is the foundation of linear algebra: every invertible linear transformation $\mathbb{R}^n \to \mathbb{R}^n$ is encoded by an element of $GL_n(\mathbb{R})$, and composition of transformations corresponds to matrix multiplication.

4. *Two actions of $\mathbb{R}^\times$ on $\mathbb{R}^2$.* Let $G = (\mathbb{R}^\times, \cdot)$, the multiplicative group of nonzero reals, and $X = \mathbb{R}^2$. Here are two *different* actions of the same group on the same set:

$$\textbf{Scaling:}\quad r \cdot \begin{pmatrix} x \\ y \end{pmatrix} = \begin{pmatrix} rx \\ ry \end{pmatrix}, \qquad\qquad \textbf{Hyperbolic:}\quad r \cdot \begin{pmatrix} x \\ y \end{pmatrix} = \begin{pmatrix} rx \\ r^{-1}y \end{pmatrix}.$$

Both satisfy (A1) and (A2). For the hyperbolic action, $1 \cdot (x, y) = (x, y)$ and $(rs) \cdot (x, y) = (rsx, (rs)^{-1}y) = (r(sx), r^{-1}(s^{-1}y)) = r \cdot (s \cdot (x, y))$, where $(rs)^{-1} = r^{-1}s^{-1}$ uses that $\mathbb{R}^\times$ is commutative, and the scaling action is checked in the same way. The scaling action dilates every vector uniformly, while the hyperbolic action stretches the x-axis and compresses the y-axis (or vice versa), preserving the hyperbolas $\{xy = c\}$.

This example makes an important point: *a group action is not determined by the group and the set alone.* One must specify the rule.

5. *Left multiplication.* Let G be any group, and let $X = G$ (the underlying set of the group itself). Define

$$g \cdot a \;=\; ga \qquad \text{(group multiplication)}.$$

Axiom (A1) is exactly the associativity of the group operation: $(gh) \cdot a = (gh)a = g(ha) = g \cdot (h \cdot a)$. Axiom (A2) is the identity property: $e \cdot a = ea = a$.

Note that for a given g, the map $a \mapsto ga$ is *not* a group homomorphism (unless $g = e$). It is only a bijection $G \to G$. This action is our first example of a group acting on *itself*, and it will lead to Cayley's Theorem in Section 4.5.

6. *Conjugation.* Let G be any group, and again let $X = G$. Define

$$g \cdot a \;=\; gag^{-1}.$$

Let us verify the axioms. For (A1):

$$(gh) \cdot a = (gh)\, a\, (gh)^{-1} = g\, h\, a\, h^{-1} g^{-1} = g \cdot (hah^{-1}) = g \cdot (h \cdot a).$$

For (A2): $e \cdot a = eae^{-1} = a$.

Unlike left multiplication, conjugation "preserves" much of the group's internal structure: it fixes the identity, sends subgroups to (isomorphic) subgroups, and preserves the order of elements. This action will lead to the Class Equation in Section 4.6.

7. *Rotations of a tetrahedron.* Let $G = A_4$ (definition 1.2.22), the alternating group on four symbols, and let $X = \{1, 2, 3, 4\}$ represent the vertices of a regular tetrahedron. The 12 elements of A_4 correspond to the 12 rotational symmetries of the tetrahedron:

   - e: the identity (no rotation).
   - 8 rotations by 120° and 240° about axes through a vertex and the center of the opposite face, e.g. $(1\,2\,3)$ and $(1\,3\,2)$ fix vertex 4.
   - 3 rotations by 180° about axes connecting the midpoints of opposite edges, e.g. $(1\,2)(3\,4)$ swaps the two pairs.

   The action is $\sigma \cdot i = \sigma(i)$, i.e. the restriction of the tautological action of S_4 to A_4.

8. *Translation of polynomials.* Let $G = (\mathbb{R}, +)$ and let $X = \mathbb{R}[x]$, the set of all polynomials with real coefficients. Define

$$t \cdot f \;=\; f_t, \qquad \text{where } f_t(x) = f(x + t).$$

   For (A1): $\big((s + t) \cdot f\big)(x) = f(x + s + t)$ and $\big(s \cdot (t \cdot f)\big)(x) = (t \cdot f)(x + s) = f(x + s + t)$.
   For (A2): $(0 \cdot f)(x) = f(x + 0) = f(x)$.

   This action connects algebra to analysis: Taylor's theorem describes how the coefficients of f_t depend on the coefficients of f and the shift t.

4.1.6 Applied Aside: Symmetry in Chemistry and Crystallography The symmetry group of a molecule (the collection of all rotations and reflections that map the molecule to itself) is called its *point group*. These point groups are finite subgroups of the orthogonal group $O(3)$ (definition 1.2.35). Remarkably, there are only 32 distinct crystallographic point groups compatible with the periodic structure of a crystal lattice.
Group actions enter directly: a point group acts on the set of atoms in a molecule, and the *orbits* of this action (a concept we formalize in Section 4.2) determine which atoms are "chemically equivalent." In spectroscopy, *selection rules*, which govern which transitions between energy levels are allowed, are derived from the representation theory of these point groups. In crystallography, the 32 point groups combine with translational symmetries to yield the *230 space groups*, which classify all possible crystal structures in three dimensions.

A Word on Left and Right Actions

What we have defined above is, more precisely, a *left* group action: the group element appears on the *left* in the expression "$g \cdot x$." There is an equally valid notion of a right action.

Definition 4.1.7: Right Group Action

A *right action* of a group G on a set X is a function $X \times G \to X$, written $(x, g) \mapsto x \cdot g$, satisfying:

(R1) $(x \cdot g) \cdot h = x \cdot (gh)$ for all $g, h \in G$ and $x \in X$, and

(R2) $x \cdot e = x$ for all $x \in X$.

Equivalently, a right action is a group homomorphism $\rho\colon G^{\mathrm{op}} \to \mathrm{Sym}(X)$, where G^{op} is the *opposite group*[a] of G.

[a]The opposite group G^{op} has the same underlying set as G but with the multiplication reversed: $a \cdot_{\mathrm{op}} b = ba$.

Observe the key difference in (R1): the parentheses associate to the *left* $((x \cdot g) \cdot h)$, and the group product is gh in its original order. Compare with the left-action axiom (A1), where the parentheses associate to the *right* $(g \cdot (h \cdot x))$.

Left and right actions are completely interchangeable in the following sense:

Proposition 4.1.8: Converting Between Left and Right Actions

If $\cdot_L\colon G \times X \to X$ is a left action, then

$$x \cdot_R g \;:=\; g^{-1} \cdot_L x$$

defines a right action. Conversely, if $\cdot_R$ is a right action, then $g \cdot_L x := x \cdot_R g^{-1}$ defines a left action.

***Proof*:**
We verify (R1). For any $g, h \in G$ and $x \in X$:

$$\begin{aligned}(x \cdot_R g) \cdot_R h = h^{-1} \cdot_L (x \cdot_R g) = h^{-1} \cdot_L (g^{-1} \cdot_L x) \\ = (h^{-1}g^{-1}) \cdot_L x = (gh)^{-1} \cdot_L x = x \cdot_R (gh).\end{aligned}$$

For (R2): $x \cdot_R e = e^{-1} \cdot_L x = e \cdot_L x = x$. The converse is analogous.

Because of this correspondence, there is no essential loss of generality in working with one type exclusively.

4.1.9 Convention For the remainder of this book, "group action" means *left* group action unless explicitly stated otherwise.

4.2 Orbits, Stabilizers, and the Kernel

Given a group action $G \curvearrowright X$, two fundamental questions arise:

1. From the perspective of X: Given a point $x \in X$, where can x be "moved to" by the elements of G?
2. From the perspective of G: Given a point $x \in X$, which elements of G "leave x in place"?

The answers to these questions, *orbits* and *stabilizers*, are two of the most important concepts in the theory of group actions. As we will see, they are intimately related, and much of the power of group actions comes from playing them off against each other.

Orbits

Consider the special orthogonal group $SO(3)$ (definition 1.2.36) acting on the unit sphere $S^2 = \{(x, y, z) \in \mathbb{R}^3 : x^2 + y^2 + z^2 = 1\}$ by matrix multiplication. If we start at the north pole $N = (0, 0, 1)$ and apply every rotation in $SO(3)$, we reach *every* point on the sphere: $SO(3) \cdot N = S^2$. Now restrict to the subgroup $SO(2) \leq SO(3)$ of rotations about the z-axis. From the north pole, $SO(2)$ goes nowhere: $SO(2) \cdot N = \{N\}$. But from a point P at latitude θ, $SO(2)$ traces out the entire latitude circle through P. The latitude circles, together with the two poles, form a family of non-overlapping subsets that cover the sphere.

This is the geometric prototype of a general phenomenon: under any group action, the set X decomposes into non-overlapping "layers" of points that can be reached from one another.

Definition 4.2.1: Orbit

Let $G \curvearrowright X$. For any $x \in X$, the *orbit* of x under the action of G is the set

$$G \cdot x \;=\; \{g \cdot x \,|\, g \in G\}.$$

In words, $G \cdot x$ is the set of all points in X that x can be "sent to" by some element of G.

The notation $\mathrm{Orb}_G(x)$ or $\mathcal{O}_x$ is also shows up in the literature. We will use $G \cdot x$ throughout.


Example 4.2.2: Orbits Under a Cyclic Group

Let $G = \langle(1\ 2\ 3)\rangle = \{e, (1\ 2\ 3), (1\ 3\ 2)\} \cong \mathbb{Z}/3\mathbb{Z}$, viewed as a subgroup of S_5, and let $X = \{1, 2, 3, 4, 5\}$ with the tautological action $\sigma \cdot i = \sigma(i)$. Then:

$$\begin{aligned} G \cdot 1 &= \{e(1),\ (1\ 2\ 3)(1),\ (1\ 3\ 2)(1)\} = \{1,\ 2,\ 3\}, \\ G \cdot 4 &= \{e(4),\ (1\ 2\ 3)(4),\ (1\ 3\ 2)(4)\} = \{4\}, \\ G \cdot 5 &= \{5\}. \end{aligned}$$

Note that $G \cdot 1 = G \cdot 2 = G \cdot 3$ (the three points can all reach each other), and the set X decomposes as the disjoint union

$$X \;=\; \{1, 2, 3\} \sqcup \{4\} \sqcup \{5\}.$$



The decomposition into orbits holds for any group action.

Proposition 4.2.3: Orbits Partition the Set

Let $G \curvearrowright X$. Define a relation $\sim$ on X by

$$x \sim y \quad \iff \quad y = g \cdot x \text{ for some } g \in G.$$

Then $\sim$ is an equivalence relation on X, and the equivalence class of x is precisely the orbit $G \cdot x$. Consequently, the orbits of the action partition X:

$$X = \bigsqcup_{i \in I} G \cdot x_i,$$

where $\{x_i\}_{i \in I}$ is any set of orbit representatives (one element chosen from each orbit).

***Proof*:**
We verify the three properties of an equivalence relation.

- *Reflexive:* $x = e \cdot x$, so $x \sim x$. (Uses axiom (A2).)
- *Symmetric:* If $x \sim y$, then $y = g \cdot x$ for some $g \in G$. Applying g^{-1}:

  $$g^{-1} \cdot y = g^{-1} \cdot (g \cdot x) \overset{(A1)}{=} (g^{-1}g) \cdot x \overset{(A2)}{=} e \cdot x = x,$$

  so $x = g^{-1} \cdot y$, which gives $y \sim x$. (Uses the existence of inverses in G.)
- *Transitive:* If $x \sim y$ and $y \sim z$, then $y = g \cdot x$ and $z = h \cdot y$ for some $g, h \in G$. Then

  $$z = h \cdot y = h \cdot (g \cdot x) \overset{(A1)}{=} (hg) \cdot x,$$

  so $x \sim z$. (Uses closure of the group operation.)

The equivalence class of x is $[x] = \{y \in X : y \sim x\} = \{g \cdot x : g \in G\} = G \cdot x$. Since equivalence classes partition a set, the orbits partition X.

The margin annotations in the proof are worth reflecting on: *reflexivity* uses the identity axiom, *symmetry* uses the existence of inverses, and *transitivity* uses closure. In other words, the group axioms are precisely what is needed to make the orbit relation an equivalence relation. A monoid action (where inverses may not exist) would give reflexivity and transitivity but *not* symmetry, and the orbits would generally fail to partition the set.

We introduce notation for the *set of orbits*:

Definition 4.2.4: Set of Orbits

If $G \curvearrowright X$, the set of all orbits is denoted

$$X/G \;=\; \{G \cdot x : x \in X\}.$$

This is called the *orbit space* (or *set of orbits*) of the action.

Counting orbits will become a central theme once we prove Burnside's Lemma (section 4.3).

Stabilizers and Fixed Points

We now turn to the second question: which group elements "do nothing" to a given point?

Definition 4.2.5: Stabilizer

Let $G \curvearrowright X$ and let $x \in X$. The *stabilizer* (or *isotropy subgroup*) of x in G is

$$G_x \;=\; \{g \in G \,|\, g \cdot x = x\}.$$

The notation $\mathrm{Stab}_G(x)$ is also standard. We use the subscript notation G_x for brevity.

Proposition 4.2.6: The Stabilizer is a Subgroup

For any $x \in X$, the stabilizer G_x is a subgroup of G.

***Proof*:**
We apply the subgroup criterion (proposition 2.1.3).

- *Non-empty:* $e \cdot x = x$ by axiom (A2), so $e \in G_x$.
- *Closed under products and inverses:* Let $g, h \in G_x$. Then

$$(gh^{-1}) \cdot x \overset{(A1)}{=} g \cdot (h^{-1} \cdot x).$$

  Since $h \in G_x$, we have $h \cdot x = x$, and so $h^{-1} \cdot x = h^{-1} \cdot (h \cdot x) = (h^{-1}h) \cdot x = e \cdot x = x$. Therefore $(gh^{-1}) \cdot x = g \cdot x = x$, giving $gh^{-1} \in G_x$.

The fact that G_x is a *subgroup* (not just a subset) is crucial: it means we can bring the full weight of our subgroup theory to bear. In particular, G_x has an index in G given by Lagrange's Theorem (theorem 3.3.1), and this index is precisely the size of the orbit $G \cdot x$ (theorem 4.3.1).

Example 4.2.7: Computing Stabilizers

Consider $G = D_4$ acting on the vertices $X = \{1, 2, 3, 4\}$ of a square, with the labeling from Section 1.5. We compute the stabilizer of vertex 1. An element $g \in D_4$ stabilizes 1 if and only if g maps vertex 1 to itself. Among the 8 elements of D_4:

- The identity e fixes 1.

- The rotations r, r^2, r^3 all move vertex 1.
- Among the four reflections, exactly one fixes vertex 1: the reflection sr^3 across the diagonal through vertex 1 (depending on the labeling convention).

Thus $G_1 = \{e, sr^3\} \cong \mathbb{Z}/2\mathbb{Z}$, a subgroup of order 2. Note that $|G_1| = 2$ and $|G{\cdot}1| = |\{1, 2, 3, 4\}| = 4$, so $|G_1| \cdot |G \cdot 1| = 2 \cdot 4 = 8 = |D_4|$. This is the orbit-stabilizer theorem, proved below.

There is a dual notion to the stabilizer that will be useful later:

Definition 4.2.8: Fixed-Point Sets

Let $G \curvearrowright X$.

1. For a single element $g \in G$, the *fixed-point set* of g is
$$X^g = \{x \in X \,|\, g \cdot x = x\}.$$
2. The *fixed-point set* of the entire group G is
$$X^G = \{x \in X \,|\, g \cdot x = x \text{ for all } g \in G\} = \bigcap_{g \in G} X^g.$$

Observe the duality: the stabilizer G_x is a subset of G (the group elements that fix a *given point*), while the fixed-point set X^g is a subset of X (the points fixed by a *given group element*). Both notions have the same underlying condition, "$g \cdot x = x$," but viewed from opposite sides:

	Lives in...	**Defined by fixing...**
Stabilizer G_x	G	the point $x \in X$
Fixed-point set X^g	X	the element $g \in G$

4.2.9 A Mnemonic for Orbits and Stabilizers Here is a useful way to keep the two concepts straight. Both G_x (stabilizer) and $G \cdot x$ (orbit) have an element of X in their notation:

- If G_x is *large* (many elements of G fix x), then $G \cdot x$ is *small* (the point x is not moved very far).
- If G_x is *small* (few elements of G fix x), then $G \cdot x$ is *large* (the point x is moved to many different places).

In the extreme: if $G_x = G$ (everything fixes x), then $G \cdot x = \{x\}$ (a singleton orbit). Conversely, if $G_x = \{e\}$ (only the identity fixes x), then the orbit is as large as possible. This inverse relationship will be made precise by the Orbit-Stabilizer Theorem in Section 4.3.

We close this subsection with two remarks connecting stabilizers to concepts from Chapter 2 that will be developed fully later in this chapter.

1. Left multiplication (item 5 of example 4.1.5). When G acts on itself by $g \cdot a = ga$, the stabilizer

of any $a \in G$ is

$$G_a = \{g \in G : ga = a\} = \{e\}.$$

Every stabilizer is trivial: no element other than the identity can "fix" a point under left multiplication.

2. Conjugation (item 6 of example 4.1.5). When G acts on itself by $g \cdot a = gag^{-1}$, the stabilizer of a is

$$G_a = \{g \in G : gag^{-1} = a\} = \{g \in G : ga = ag\} = C_G(a),$$

the centralizer of a (definition 2.2.7). Thus the orbit-stabilizer framework gives us a direct link between orbits (conjugacy classes) and centralizers. We will exploit this connection in Section 4.6.

The Kernel of an Action

The stabilizer G_x captures which group elements fix a *single* point. We now ask: which group elements fix *every* point?

Definition 4.2.10: Kernel of a Group Action

Let $G \curvearrowright X$ with permutation representation $\rho\colon G \to \mathrm{Sym}(X)$. The *kernel* of the action is

$$\ker(G \curvearrowright X) \;=\; \{g \in G \,|\, g \cdot x = x \text{ for all } x \in X\} \;=\; \bigcap_{x \in X} G_x.$$

An element in the kernel "acts trivially": it is a group element that induces the identity permutation on X. This means $\rho(g) = \mathrm{id}_X$, and so the kernel of the *action* is exactly the kernel of the *homomorphism* ρ:

$$\ker(G \curvearrowright X) \;=\; \ker(\rho).$$

Proposition 4.2.11: The Kernel is a Normal Subgroup

$$\ker(G \curvearrowright X) \trianglelefteq G$$

***Proof*:**
Since $\rho\colon G \to \mathrm{Sym}(X)$ is a group homomorphism, its kernel $\ker(\rho)$ is a normal subgroup of G by proposition 2.2.12.

The kernel measures how much "information about G" is lost by the action. If the kernel is large, many group elements are "wasted" as they all induce the same (trivial) permutation. If the kernel is trivial, then distinct group elements always induce distinct permutations. As the kernel is normal, we can always "eliminate" the wasteful elements by taking $G/\ker(\rho)$. This motivates:

Definition 4.2.12: Faithful Action

A group action $G \curvearrowright X$ is called *faithful* (or *effective*) if its kernel is trivial:

$$\ker(G \curvearrowright X) = \{e\}.$$

Equivalently, the action is faithful if and only if the permutation representation $\rho\colon G \to \mathrm{Sym}(X)$ is *injective*.

In a faithful action, distinct group elements always produce distinct permutations of X: if $g \neq h$, then there exists some $x \in X$ with $g \cdot x \neq h \cdot x$. The group G is thus "faithfully represented" as a group of permutations of X.

Example 4.2.13: A Non-Faithful Action

Let $G = \mathbb{Z}/4\mathbb{Z} = \{\bar{0}, \bar{1}, \bar{2}, \bar{3}\}$ and $X = \{1, 2\}$. Define an action by $\bar{n} \cdot i = \tau^n(i)$, where $\tau = (1\ 2) \in S_2$. Then:

$$\bar{0} \cdot i = i, \quad \bar{1} \cdot i = \tau(i), \quad \bar{2} \cdot i = \tau^2(i) = i, \quad \bar{3} \cdot i = \tau^3(i) = \tau(i).$$

The elements $\bar{0}$ and $\bar{2}$ both act as the identity on X, so

$$\ker(\rho) \;=\; \{\bar{0}, \bar{2}\} \;\cong\; \mathbb{Z}/2\mathbb{Z}.$$

The action is *not* faithful. By the First Isomorphism Theorem (theorem 3.1.15),

$$G/\ker(\rho) \;\cong\; \rho(G) \;\leq\; \mathrm{Sym}(X) \;=\; S_2,$$

so $(\mathbb{Z}/4\mathbb{Z})/(\mathbb{Z}/2\mathbb{Z}) \cong \mathbb{Z}/2\mathbb{Z}$ embeds into S_2, consistent with the fact that the *effective* part of the action is just "swap or do not swap."

The example above illustrates a general principle: even if an action is not faithful, we can always *make* it faithful by passing to the quotient.

Proposition 4.2.14: Quotient by the Kernel Acts Faithfully

Let $G \curvearrowright X$ with kernel $K = \ker(\rho)$. Then the quotient group G/K acts faithfully on X via

$$(gK) \cdot x \;=\; g \cdot x.$$

***Proof*:**

We first check well-definedness: if $gK = hK$, then $h^{-1}g \in K$, so $(h^{-1}g) \cdot x = x$ for all x, whence $g \cdot x = h \cdot x$ for all x. Thus the action of gK does not depend on the choice of representative.

The axioms (A1) and (A2) are inherited directly from the action of G. Finally, if gK is in the kernel of this new action, then $g \cdot x = x$ for all $x \in X$, so $g \in K$, meaning $gK = eK$. The kernel of the G/K-action is trivial, so the action is faithful.

In the language of the permutation representation: ρ factors through the quotient as

$$G \;\twoheadrightarrow\; G/K \;\xhookrightarrow{\bar{\rho}}\; \mathrm{Sym}(X),$$

where $\bar{\rho}$ is injective. This is simply the First Isomorphism Theorem (theorem 3.1.15) applied to ρ.

We summarize the key objects introduced in this section for quick reference.

Object	**Notation**	**Lives in**	**Definition**
Orbit of x	$G \cdot x$	subsets of X	$\{g \cdot x : g \in G\}$
Stabilizer of x	G_x	subgroups of G	$\{g \in G : g \cdot x = x\}$
Fixed-point set of g	X^g	subsets of X	$\{x \in X : g \cdot x = x\}$
Kernel of the action	$\ker(\rho)$	normal subgroups of G	$\bigcap_{x \in X} G_x$

4.3 The Orbit-Stabilizer Theorem

In the previous section, we observed an inverse relationship between orbits and stabilizers: the larger the stabilizer, the smaller the orbit, and vice versa. We also noticed, in the D_4 example (example 4.2.7), that $|G_1| \cdot |G \cdot 1| = |D_4|$. The Orbit-Stabilizer Theorem makes this relationship precise, and reveals it to be a direct consequence of Lagrange's Theorem.

Theorem 4.3.1: The Orbit-Stabilizer Theorem

Let G be a group acting on a set X, and let $x \in X$. There is a bijection

$$G/G_x \longleftrightarrow G \cdot x, \qquad gG_x \longmapsto g \cdot x,$$

between the set of left cosets of the stabilizer G_x in G and the orbit of x. In particular,

$$|G \cdot x| \;=\; [G : G_x].$$

If G is finite, this gives $|G \cdot x| = |G| \,/\, |G_x|$, or equivalently,

$$|G| \;=\; |G \cdot x| \cdot |G_x|.$$

***Proof*:**
Define the map

$$\varphi \colon G/G_x \to G \cdot x, \qquad \varphi(gG_x) = g \cdot x.$$

We verify that φ is a well-defined bijection.

Well-defined. Suppose $gG_x = hG_x$. Then $h^{-1}g \in G_x$, so $(h^{-1}g) \cdot x = x$. By axiom (A1):

$$g \cdot x = h \cdot \big((h^{-1}g) \cdot x\big) = h \cdot x.$$

Thus $\varphi(gG_x) = \varphi(hG_x)$, and the map does not depend on the choice of coset representative.

Injective. Suppose $\varphi(gG_x) = \varphi(hG_x)$, i.e. $g \cdot x = h \cdot x$. Then

$$(h^{-1}g) \cdot x = h^{-1} \cdot (g \cdot x) = h^{-1} \cdot (h \cdot x) = (h^{-1}h) \cdot x = e \cdot x = x,$$

so $h^{-1}g \in G_x$, hence $gG_x = hG_x$.

Surjective. Every element of $G \cdot x$ has the form $g \cdot x$ for some $g \in G$, and $g \cdot x = \varphi(gG_x)$.

Since φ is a bijection, $|G \cdot x| = |G/G_x| = [G : G_x]$. When G is finite, Lagrange's Theorem (theorem 3.3.1) gives $[G : G_x] = |G|/|G_x|$.

4.3.2 Remark The formula $|G| = |G \cdot x| \cdot |G_x|$ has exactly the same shape as Lagrange's Theorem: $|G| = [G : H] \cdot |H|$. It *is* Lagrange's Theorem, applied to the subgroup $H = G_x$. The content of the Orbit-Stabilizer Theorem is the bijection φ that identifies the abstract index $[G : G_x]$ with the concrete, countable object $G \cdot x$.

When X is finite, we can combine the Orbit-Stabilizer Theorem with the fact that orbits partition X (proposition 4.2.3) to obtain a useful counting formula.

Corollary 4.3.3: The Orbit-Counting Formula

Let G be a finite group acting on a finite set X, and let $x_1, \ldots, x_k$ be representatives from the distinct orbits. Then

$$|X| \;=\; \sum_{i=1}^{k} |G \cdot x_i| \;=\; \sum_{i=1}^{k} [G : G_{x_i}].$$

***Proof*:**

Since the orbits partition X (proposition 4.2.3), we have $|X| = \sum_{i=1}^{k} |G \cdot x_i|$. Replacing each $|G \cdot x_i|$ by $[G : G_{x_i}]$ via theorem 4.3.1 yields the result.

This formula will be the key ingredient in the Class Equation (Section 4.6), where we apply it to the conjugation action and split the sum according to whether orbit representatives lie in the center.

Example 4.3.4: Orbits of Polynomials Under S_4

Let $R = \mathbb{Z}[x_1, x_2, x_3, x_4]$, the ring of polynomials in four variables with integer coefficients, and let S_4 act on R by permuting the indices:

$$\sigma \cdot p(x_1, x_2, x_3, x_4) \;=\; p(x_{\sigma(1)}, x_{\sigma(2)}, x_{\sigma(3)}, x_{\sigma(4)}).$$

We compute the orbit of $f = x_1 + x_2$ under this action.

Rather than applying all 24 elements of S_4 to f, we first identify the stabilizer. A permutation σ fixes $x_1 + x_2$ if and only if the set $\{\sigma(1), \sigma(2)\} = \{1, 2\}$ (since addition is commutative, the order within the pair does not matter). This means σ must permute $\{1, 2\}$ among themselves and $\{3, 4\}$ among themselves. The stabilizer is therefore

$$(S_4)_f \;=\; \langle (1\ 2),\ (3\ 4) \rangle \;\cong\; \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z},$$

a copy of the Klein four-group, with $|(S_4)_f| = 4$. By the Orbit-Stabilizer Theorem,

$$|S_4 \cdot f| = \frac{|S_4|}{|(S_4)_f|} = \frac{24}{4} = 6.$$

We can now enumerate the orbit with confidence that we are looking for exactly 6 polynomials. Choosing one representative from each coset of $(S_4)_f$ yields:

$$S_4 \cdot (x_1 + x_2) = \{x_1 + x_2,\ x_1 + x_3,\ x_1 + x_4,\ x_2 + x_3,\ x_2 + x_4,\ x_3 + x_4\}.$$

The Orbit-Stabilizer Theorem saved us from checking all 24 permutations: knowing the stabilizer immediately told us the orbit size, and we only needed to find 6 distinct images.

Example 4.3.5: S_n Acting on $\{1, \ldots, n\}$

Consider S_{10} acting on $\{1, \ldots, 10\}$ by $\sigma \cdot i = \sigma(i)$. For any $i, j \in \{1, \ldots, 10\}$, there exists a permutation sending i to j (for instance, the transposition $(i\ j)$), so the action has a single orbit: $S_{10} \cdot i = \{1, \ldots, 10\}$ for every i.

The stabilizer of, say, 1 consists of all permutations that fix 1:

$$(S_{10})_1 = \{\sigma \in S_{10} : \sigma(1) = 1\} \cong S_9.$$

The Orbit-Stabilizer Theorem confirms: $|S_{10} \cdot 1| = |S_{10}|/|(S_{10})_1| = 10!/9! = 10$.

Example 4.3.6: D_4 Acting on Vertices, Revisited

The group D_4 acts on $X = \{1, 2, 3, 4\}$ (the vertices of a square). Since any vertex can be sent to any other by a suitable rotation, the action has a single orbit of size 4. From example 4.2.7, the stabilizer of vertex 1 has order 2. The Orbit-Stabilizer Theorem gives $|G \cdot 1| = 8/2 = 4$, as expected.

Now consider D_4 acting on the set of two diagonals, $\mathcal{D} = \{d_1, d_2\}$, where $d_1 = \{1, 3\}$ and $d_2 = \{2, 4\}$. A rotation by 90° swaps the two diagonals, while a rotation by 180° preserves both. Here $|G \cdot d_1| = 2$ and $|G_{d_1}| = 8/2 = 4$. The stabilizer G_{d_1} consists of the symmetries that preserve the diagonal d_1 as a set: $G_{d_1} = \{e,\ r^2,\ sr,\ sr^3\}$, a copy of the Klein four-group.

Burnside's Lemma

The Orbit-Stabilizer Theorem gives the size of each individual orbit. But in many applications, particularly in combinatorics, what we really want to know is the *number* of orbits. The following classical result answers this question.

Theorem 4.3.7: Burnside's Lemma

Let G be a finite group acting on a finite set X. Then the number of orbits is

$$|X/G| \ = \ \frac{1}{|G|} \sum_{g \in G} |X^g|,$$

where $X^g = \{x \in X : g \cdot x = x\}$ is the fixed-point set of g (definition 4.2.8).

In words: the number of distinct orbits equals the average number of fixed points, averaged over all group elements.

4.3.8 Historical Note Despite its name, this result was known to Cauchy (1845) and proved in full generality by Frobenius (1887). Burnside included it in his influential 1897 textbook, citing Frobenius, and subsequent authors attributed it to Burnside. For this reason, some authors call it the *Cauchy-Frobenius Lemma*. This book will follow the (ahistorical but widespread) convention of calling it Burnside's Lemma.

***Proof*:**
The proof is a double-counting argument. Consider the set of pairs

$$\mathcal{S} \;=\; \{(g,x) \in G \times X \big| g \cdot x = x\}.$$

We count $|\mathcal{S}|$ in two ways.

Counting by group elements (summing over $g \in G$). For each $g \in G$, the number of $x \in X$ with $g \cdot x = x$ is $|X^g|$. Therefore

$$|\mathcal{S}| = \sum_{g \in G} |X^g|. \tag{4.1}$$

Counting by set elements (summing over $x \in X$). For each $x \in X$, the number of $g \in G$ with $g \cdot x = x$ is $|G_x|$. Therefore

$$|\mathcal{S}| = \sum_{x \in X} |G_x|. \tag{4.2}$$

We now simplify (4.2) by grouping the sum according to orbits. Let $\mathcal{O}_1, \ldots, \mathcal{O}_k$ be the distinct orbits. For any x in an orbit $\mathcal{O}_i$, the Orbit-Stabilizer Theorem (theorem 4.3.1) gives $|G_x| = |G|/|\mathcal{O}_i|$. Summing over the $|\mathcal{O}_i|$ elements of the orbit:

$$\sum_{x \in \mathcal{O}_i} |G_x| \;=\; |\mathcal{O}_i| \cdot \frac{|G|}{|\mathcal{O}_i|} \;=\; |G|.$$

Each orbit contributes exactly $|G|$ to the sum, and there are $k = |X/G|$ orbits, so

$$\sum_{x \in X} |G_x| \;=\; |X/G| \cdot |G|.$$

Equating (4.1) and (4.2):

$$\sum_{g \in G} |X^g| \;=\; |X/G| \cdot |G|,$$

and dividing by $|G|$ yields the result.

The double-counting technique at the heart of this proof is worth internalizing: whenever a condition involves both a group element and a set element (here, "g fixes x"), counting the pairs from both sides often yields a clean identity.

Let us see Burnside's Lemma in action.

Example 4.3.9: Counting Colorings of a Square

How many distinct ways can we color the vertices of a square using 2 colors (say, black and white), if two colorings are considered "the same" when one can be obtained from the other by a symmetry of the square?

Let X be the set of all 2-colorings of 4 labeled vertices, so $|X| = 2^4 = 16$. The symmetry group $G = D_4$ acts on X by permuting the vertices (and hence the colors assigned to them). The distinct colorings "up to symmetry" are precisely the orbits, so we seek $|X/G|$.

We compute $|X^g|$ for each $g \in D_4$. Using the vertex labeling 1 (top-left), 2 (top-right), 3 (bottom-right), 4 (bottom-left), the eight elements act as the following permutations:


g	Permutation	Cycle structure	$\lvert X^g \rvert$
e	()	four fixed points	$2^4 = 16$
r	(1 2 3 4)	one 4-cycle	$2^1 = 2$
r^2	(1 3)(2 4)	two 2-cycles	$2^2 = 4$
r^3	(1 4 3 2)	one 4-cycle	$2^1 = 2$
s	(1 2)(3 4)	two 2-cycles	$2^2 = 4$
sr	(2 4)	one 2-cycle, two fixed	$2^3 = 8$
sr^2	(1 4)(2 3)	two 2-cycles	$2^2 = 4$
sr^3	(1 3)	one 2-cycle, two fixed	$2^3 = 8$

The rule for each row: a coloring is fixed by g if and only if all vertices within each cycle of g receive the same color. So $|X^g| = 2^{(\text{number of cycles of } g)}$, counting fixed points as 1-cycles.

Burnside's Lemma gives:

$$|X/G| \;=\; \frac{1}{8}(16 + 2 + 4 + 2 + 4 + 8 + 4 + 8) \;=\; \frac{48}{8} \;=\; 6.$$

The six distinct colorings are:



4.3.10 Applied Aside: Counting Molecular Structures The same technique applies in chemistry. Consider a benzene ring C_6H_6, where each hydrogen atom can be replaced by a substituent (say, chlorine). How many distinct chlorinated benzene derivatives exist? The symmetry group of the hexagonal ring is D_6, acting on the six positions. Burnside's Lemma (or its refinement, Pólya's Enumeration Theorem) answers this question systematically. For instance, with two possible substituents (H or Cl) at each of 6 positions, there are

$$\frac{1}{12}(2^6 + \cdots) = 13$$

distinct molecules, a count that matches experimental chemistry. This interplay between symmetry and enumeration is foundational in chemical graph theory.

4.4 Types of Actions

Some actions allow different group elements to "look the same" on X. Others ensure that every group element acts distinctly. Some actions can move any point to any other. Others split X into multiple unreachable regions. In this section, we introduce a taxonomy of four properties that classify the most important qualitative features of an action: faithful, transitive, free, and regular.

Faithful Actions

We have already defined this notion in definition 4.2.12: an action $G \curvearrowright X$ is *faithful* if $\ker(\rho) = \{e\}$, i.e. if the only element that fixes every point of X is the identity. Equivalently, the permutation representation $\rho\colon G \to \mathrm{Sym}(X)$ is injective, so G embeds into $\mathrm{Sym}(X)$.

Faithfulness is a *global* condition: it says nothing about any individual stabilizer G_x, only about their intersection $\bigcap_{x\in X} G_x$. Individual stabilizers may well be nontrivial.

Example 4.4.1: Faithful Actions

1. The tautological action of S_n on $\{1, \ldots, n\}$ is faithful: any nontrivial permutation must move at least one element.
2. The action of D_n on the vertices of a regular n-gon is faithful for $n \geq 3$: distinct symmetries of the polygon induce distinct permutations of the vertices. Note, however, that stabilizers are nontrivial: the stabilizer of a vertex is the order-2 subgroup generated by the reflection fixing that vertex.
3. The conjugation action of G on itself (item 6 of example 4.1.5) has kernel

   $$\ker(\rho) = \{g \in G : gag^{-1} = a \text{ for all } a \in G\} = Z(G),$$

   the center of G (definition 2.2.4). This action is faithful if and only if $Z(G) = \{e\}$, i.e. if and only if G has trivial center.

As we saw in proposition 4.2.14, any action can be made faithful by passing to the quotient $G/\ker(\rho)$. In this sense, the "faithful part" of an action is always available. The kernel measures the redundancy.

Transitive Actions

Definition 4.4.2: Transitive Action

A group action $G \curvearrowright X$ is called *transitive* if it has exactly one orbit, i.e. $G \cdot x = X$ for every $x \in X$. Equivalently, for any $x, y \in X$, there exists some $g \in G$ such that $g \cdot x = y$.

In a transitive action, every point can be reached from every other point. No point is "isolated" from the rest.

Example 4.4.3: Transitive and Non-Transitive Actions

1. The action of S_n on $\{1, \ldots, n\}$ is transitive: for any i, j, the transposition $(i\ j)$ sends i to j.
2. The action of D_4 on the four vertices of a square is transitive: r cyclically permutes all four vertices.
3. The action of D_4 on the set X of unordered distinct pairs $\{i, j\}$ of the 4 vertices that permutes like the above action is not transitive: show there are 2 orbits.
4. The action of $\langle(1\ 2\ 3)\rangle$ on $\{1, 2, 3, 4, 5\}$ from example 4.2.2 is *not* transitive: it has three orbits.
5. The conjugation action of G on itself is transitive if and only if every pair of elements is conjugate. For finite groups, this can only happen when $|G| = 1$ (since the identity is conjugate only to itself, so if $|G| > 1$, the singleton $\{e\}$ is always an orbit separate from any non-identity element).

Transitive actions enjoy a useful structural property: the stabilizers of any two points are conjugate subgroups.

Proposition 4.4.4: Stabilizers of Points in the Same Orbit

Let $G \curvearrowright X$. If $y = g \cdot x$ for some $g \in G$, then

$$G_y = g\, G_x\, g^{-1}.$$

In particular, if the action is transitive, then the stabilizers of any two points in X are conjugate subgroups of G.

***Proof*:**
Let $G_x = \{g \in G \mid g \cdot x = x\}$ and $y = g \cdot x$. Then act both sides by g^{-1} so that $g^{-1} \cdot y = g^{-1} \cdot (g \cdot x) = (g^{-1}g) \cdot x = x$. Now, for any $h \in G_x$ (constantly using group-action associativity):

$$ghg^{-1} \cdot y = gh \cdot x = g \cdot x = y$$

showing $gG_xg^{-1} \subseteq G_y$, equivalently that $G_x \subseteq g^{-1}G_yg$. Working the argument in reverse, for any $k \in G_y$, we get:

$$g^{-1}kg \cdot x = g^{-1} \cdot (k \cdot y) = g^{-1} \cdot y = x$$

showing $g^{-1}G_yg \subseteq G_x$, equivalently $G_y \subseteq gG_xg^{-1}$. Both containments give $G_y = gG_xg^{-1}$.

This proposition has an important consequence: in a transitive action, knowing the stabilizer of *any single point* determines (up to conjugacy) the stabilizer of every point.

Even more is true. A transitive action is completely determined, up to a natural notion of equivalence, by the stabilizer of any chosen point. To make this precise, we need a brief definition.

Definition 4.4.5: Isomorphism of G-sets

Let $G \curvearrowright X$ and $G \curvearrowright Y$ be two actions of the same group. A bijection $\varphi\colon X \to Y$ is an *isomorphism of G-sets* (or a *G-equivariant* bijection) if

$$\varphi(g \cdot x) = g \cdot \varphi(x) \qquad \text{for all } g \in G,\ x \in X.$$

If such a bijection exists, we write $X \cong_G Y$ and say the two G-sets are *isomorphic*.

In other words, φ is a relabeling of X as Y that is compatible with the group action: it does not matter whether we act first and then relabel, or relabel first and then act.

Theorem 4.4.6: Structure Theorem for Transitive Actions

Let $G \curvearrowright X$ be a transitive action, and fix any point $x_0 \in X$. Then the bijection

$$\varphi\colon G/G_{x_0} \xrightarrow{\sim} X, \qquad gG_{x_0} \mapsto g \cdot x_0,$$

from the Orbit-Stabilizer Theorem (theorem 4.3.1) is an isomorphism of G-sets, where G acts on G/G_{x_0} by left multiplication: $h \cdot (gG_{x_0}) = (hg)G_{x_0}$.

In particular, every transitive G-set is isomorphic to G/H for some subgroup $H \leq G$.

***Proof*:**
We already know from theorem 4.3.1 that φ is a well-defined bijection (using transitivity so that $G \cdot x_0 = X$). It remains to verify equivariance. For any $h \in G$ and any coset gG_{x_0}:

$$\varphi(h \cdot gG_{x_0}) = \varphi((hg)G_{x_0}) = (hg) \cdot x_0 = h \cdot (g \cdot x_0) = h \cdot \varphi(gG_{x_0}).$$

Thus φ respects the action, and the two G-sets are isomorphic.

This theorem is one of the most clarifying results in the theory: it says that, up to relabeling, *every* transitive action is a coset action. We will study coset actions in detail in Section 4.5. If the action is furthermore faithful, then as there is one coset $G_x = \{e\}$ and:

$$G \cong_G (X, \rho)$$

where ρ represents the faithful transitive action.

4.4.7 Geometric Interpretation In differential geometry, is is very common to have group actions on a manifold or a bundle on the manifold. The action can always be made faithful as explained above, and often the action is transitive on fibers. Hence, each fiber of a bundle has the "structure" of a group in the sense of the above G-set isomorphism. This motivates shifting our perspective from an action on a set to an action on a group, as in many important cases we can study what happens to geometric objects by studying the left-multiplication or conjugation actin on G!
Note that a fiber bundle where each fiber is G-set isomorphic to a group G is called a G-torsor, or a Principal homogeneous space.

Free Actions

Faithful actions require the *intersection* of all stabilizers to be trivial. Free actions require something much stronger: every *individual* stabilizer must be trivial.

Definition 4.4.8: Free Action

A group action $G \curvearrowright X$ is called *free* if

$$G_x = \{e\} \qquad \text{for every } x \in X.$$

Equivalently, if $g \cdot x = x$ for some $x \in X$, then $g = e$.

There is a useful reformulation: an action is free if and only if distinct group elements never produce the same result at any point.

Proposition 4.4.9: Characterization of Free Actions

An action $G \curvearrowright X$ is free if and only if for all $g, h \in G$ and all $x \in X$,

$$g \cdot x = h \cdot x \quad \Longrightarrow \quad g = h.$$

***Proof*:**
If $g \cdot x = h \cdot x$, then $(h^{-1}g) \cdot x = x$, so $h^{-1}g \in G_x$. If the action is free, $G_x = \{e\}$, so $h^{-1}g = e$, giving $g = h$. Conversely, if the implication holds for all g, h, x, then taking $h = e$: $g \cdot x = x$ implies $g = e$, so every stabilizer is trivial.

Example 4.4.10: Free Actions

1. The left-multiplication action $G \curvearrowright G$ (item 5 of example 4.1.5) is free: if $ga = a$, then $g = e$ by cancellation (proposition 1.1.17). This holds for any group G.
2. The action of $(\mathbb{Z}, +)$ on $\mathbb{R}$ by $n \cdot x = x + n$ is free: if $x + n = x$, then $n = 0$.
3. The action of D_4 on the vertices of a square is *not* free: the stabilizer of each vertex has order 2.

4. The action of $\mathbb{Z}/2\mathbb{Z} = \{e, \sigma\}$ on $\{1, 2, 3, 4\}$ via $\sigma = (1\ 2)(3\ 4)$ is free: σ has no fixed points. It is not transitive, however (the orbits are $\{1, 2\}$ and $\{3, 4\}$).

Free actions interact cleanly with the Orbit-Stabilizer Theorem.

Corollary 4.4.11: Orbit Sizes in Free Actions

If G is a finite group acting freely on X, then every orbit has size $|G|$. In particular, $|G|$ divides $|X|$.

***Proof*:**
For every $x \in X$, $|G_x| = 1$, so $|G \cdot x| = |G|/|G_x| = |G|$ by theorem 4.3.1. Since the orbits partition X (proposition 4.2.3), $|X|$ is a sum of copies of $|G|$.

Note that every free action is faithful: if $G_x = \{e\}$ for all x, then $\ker(\rho) = \bigcap_x G_x = \{e\}$. The converse is false, as the example of D_4 on the vertices of a square shows (faithful, but not free).

Regular Actions

The strongest condition arises when we ask for an action that is simultaneously free and transitive.

Definition 4.4.12: Regular Action

A group action $G \curvearrowright X$ is called *regular* if it is both free and transitive.

Regular actions have a particularly elegant characterization.

Proposition 4.4.13: Characterization of Regular Actions

An action $G \curvearrowright X$ is regular if and only if for every pair $x, y \in X$, there exists a *unique* $g \in G$ such that $g \cdot x = y$.

***Proof*:**
Transitivity says "at least one such g exists." Freeness says "at most one such g exists" (by proposition 4.4.9: if $g \cdot x = y = h \cdot x$, then $g = h$). Together, they give exactly one.

Conversely, if for every x, y there exists a unique g with $g \cdot x = y$, then existence gives transitivity, and uniqueness gives freeness.

Example 4.4.14: Regular Actions

1. The left-multiplication action $G \curvearrowright G$ is regular: it is free (example 4.4.10) and transitive (given $a, b \in G$, the element $g = ba^{-1}$ satisfies $g \cdot a = ba^{-1}a = b$). This is the *canonical* regular action.
2. The action of $(\mathbb{Z}, +)$ on $\mathbb{R}$ by translation ($n \cdot x = x + n$) is free but not transitive ($\frac{1}{2}$ is not in the orbit of 0), hence not regular.

3. The action of D_4 on the four vertices of a square is transitive but not free, hence not regular.

By the Orbit-Stabilizer Theorem, a regular action of a finite group G on a set X satisfies $|X| = |G \cdot x| = |G|$ for every x: the set and the group have the same cardinality. In fact, the Structure Theorem for Transitive Actions (theorem 4.4.6) shows precisely what every regular action looks like:

Corollary 4.4.15: Regular Actions are Left Multiplication

If G acts regularly on X, then $X \cong_G G$ as G-sets. That is, up to isomorphism, the left-multiplication action of G on itself is the *only* regular G-action.

***Proof*:**
By theorem 4.4.6, any transitive G-set is isomorphic to G/G_{x_0} for some $x_0 \in X$. Since the action is also free, $G_{x_0} = \{e\}$, so $X \cong_G G/\{e\} = G$.

4.5 Action by Left Multiplication

An action of G on a set X (definition 4.1.1) needs two pieces of data besides G, the set X and the homomorphism $G \to \mathrm{Sym}(X)$. Every group carries both without further choices: its underlying set, and the actions defined by its own operation, such as left multiplication and conjugation. By theorem 4.4.6, every transitive action is isomorphic to the action of G by left multiplication on a set of cosets G/H, so actions built from G itself already describe all transitive G-sets. For an action of G on itself, the orbits are subsets of G and the stabilizers are subgroups of G, so the Orbit-Stabilizer Theorem (theorem 4.3.1) applied to it gives statements about G alone.

The simplest self-action is left multiplication: each group element shuffles the entire group by multiplying on the left.

Let G be a group and let $X = G$ (the underlying set). The action is

$$g \cdot a = ga \qquad \text{for all } g, a \in G.$$

We verified in item 5 of example 4.1.5 that this is a valid group action. We can now classify it using the taxonomy of Section 4.4:

Proposition 4.5.1: Left Multiplication is a Regular Action

The left-multiplication action $G \curvearrowright G$ is regular (free and transitive).

***Proof*:**
The action is free: if $g \cdot a = a$, then $ga = a$, so $g = e$ by cancellation (proposition 1.1.17). The action is transitive: given any $a, b \in G$, taking $g = ba^{-1}$ gives $g \cdot a = ba^{-1}a = b$.

Since the action is faithful (every free action is), the permutation representation $\rho\colon G \to \mathrm{Sym}(G)$ is injective. Let us see what ρ looks like concretely.

Example 4.5.2: Permutation Representation of the Klein Four-Group

Let $G = \{e, a, b, c\}$ be the Klein four-group, with multiplication defined by $a^2 = b^2 = c^2 = e$ and $ab = c$, $ac = b$, $bc = a$. Label $e \leftrightarrow 1$, $a \leftrightarrow 2$, $b \leftrightarrow 3$, $c \leftrightarrow 4$. For each $g \in G$, we compute the permutation $\sigma_g(i) = j$ where $g \cdot g_i = g_j$:

g	$g \cdot e$	$g \cdot a$	$g \cdot b$	$g \cdot c$	σ_g
e	e	a	b	c	$()$
a	a	e	c	b	$(1\ 2)(3\ 4)$
b	b	c	e	a	$(1\ 3)(2\ 4)$
c	c	b	a	e	$(1\ 4)(2\ 3)$

The image $\rho(G) = \{(), (1\ 2)(3\ 4), (1\ 3)(2\ 4), (1\ 4)(2\ 3)\}$ is a subgroup of S_4 isomorphic to the Klein four-group. One can verify directly that $g \mapsto \sigma_g$ is a homomorphism, and injectivity is visible from the table: distinct rows give distinct permutations.

The example above embeds a group of order 4 into S_4. The same construction works for any group.

Theorem 4.5.3: Cayley's Theorem

Every group is isomorphic to a subgroup of a symmetric group. More precisely, if G is a group, then the permutation representation $\rho\colon G \to \mathrm{Sym}(G)$ of the left-multiplication action is an injective homomorphism. If $|G| = n$, then G is isomorphic to a subgroup of S_n.

***Proof*:**

The left-multiplication action $G \curvearrowright G$ is free (proposition 4.5.1), hence faithful (definition 4.2.12). Thus the permutation representation $\rho\colon G \to \mathrm{Sym}(G)$ has trivial kernel, so ρ is injective. By the First Isomorphism Theorem (theorem 3.1.15), $G \cong \rho(G) \leq \mathrm{Sym}(G)$.

If $|G| = n$, we may label the elements of G as $\{g_1, \ldots, g_n\}$ and identify $\mathrm{Sym}(G) \cong S_n$, so G embeds into S_n.

Cayley's Theorem shows that the abstract axioms (closure, associativity, identity, inverses) do not create anything genuinely "new" beyond permutation groups. Every group, no matter how abstractly defined, *is* a group of symmetries: a subgroup of a symmetric group. The Erlangen Programme's vision (see the aside in box 4.0.1) is vindicated: groups and symmetries are one and the same.

4.5.4 Historical Note When group theory began in the early 19th century, a "group" simply *meant* a group of permutations. Cayley was among the first to propose the abstract axiomatic definition. His 1854 theorem then showed that the abstraction lost nothing: the original permutation-based intuition remains fully applicable to every abstract group.

That said, the embedding $G \hookrightarrow S_n$ is rarely practical. The symmetric group S_n has order $n!$, which is vastly larger than n for even modest values: if $|G| = 100$, then $|S_{100}| = 100! \approx 9.3 \times 10^{157}$. Working inside S_n is typically no easier than working directly with G. The theorem's value is *conceptual*: it guarantees that any general statement proved about subgroups of symmetric groups automatically applies to all groups.

The following example illustrates a subtler limitation: Cayley's bound $n = |G|$ is sometimes optimal (you genuinely cannot embed the group into any smaller symmetric group).

Example 4.5.5: The Minimum Faithful Degree of Q_8

The quaternion group $Q_8 = \{\pm 1, \pm i, \pm j, \pm k\}$ has order 8, so Cayley's Theorem gives $Q_8 \hookrightarrow S_8$. We claim that Q_8 cannot act faithfully on any set X with $|X| \leq 7$.

Suppose $Q_8 \curvearrowright X$ with $|X| \leq 7$. For any $x \in X$, the Orbit-Stabilizer Theorem (theorem 4.3.1) gives

$$|G_x| = \frac{|Q_8|}{|Q_8 \cdot x|} = \frac{8}{|Q_8 \cdot x|} \geq \frac{8}{7} > 1,$$

so $G_x \neq \{e\}$ for every x. Now, a particular property of Q_8 is that every nontrivial subgroup contains -1 (one can verify this by inspecting the subgroup lattice of Q_8, cf. example 1.2.31). Since G_x is a nontrivial subgroup for every x, we have $-1 \in G_x$ for every x. Therefore $-1 \in \bigcap_{x \in X} G_x = \ker(\rho)$, and the action is not faithful.

Thus, the Cayley embedding into S_8 is the smallest symmetric group that can faithfully contain Q_8.

Action on the Coset Space

Left multiplication acts on the full group G. We now generalize by letting G act on the set of left cosets of a subgroup.

Let $H \leq G$, and let $G/H = \{gH : g \in G\}$ denote the set of left cosets (this is a set, not necessarily a group, since H need not be normal). Define

$$g \cdot (aH) = (ga)H \qquad \text{for all } g \in G,\ aH \in G/H.$$

This is well-defined: if $aH = bH$, then $b^{-1}a \in H$, so $(gb)^{-1}(ga) = b^{-1}a \in H$, giving $(ga)H = (gb)H$. The two axioms are immediate: $(gh) \cdot aH = (gh)aH = g \cdot (haH)$ and $e \cdot aH = aH$.

Note that when $H = \{e\}$, the cosets of H are simply the elements of G, and this action reduces to left multiplication. In this sense, the coset action *generalizes* the construction of the previous subsection.

The following theorem extracts the structural information that the coset action provides.

Theorem 4.5.6: Properties of the Coset Action

Let $H \leq G$, and let G act on G/H by left multiplication. Let $\pi_H \colon G \to \mathrm{Sym}(G/H)$ be the associated permutation representation. Then:

1. The action is transitive.
2. The stabilizer of the coset eH is H:
$$G_{eH} = H.$$
3. The kernel of the action is the largest normal subgroup of G contained in H:
$$\ker(\pi_H) = \bigcap_{g \in G} gHg^{-1}.$$

***Proof*:**

1. Given any two cosets $aH, bH \in G/H$, take $g = ba^{-1}$. Then $g \cdot aH = (ba^{-1})aH = bH$. Since a and b were arbitrary, the action is transitive.
2. The stabilizer of eH is $\{g \in G : g \cdot eH = eH\} = \{g \in G : gH = H\}$. Now $gH = H$ if and only if $g \in H$ (recall that $gH = H \Leftrightarrow g \in H$). Thus $G_{eH} = H$.
3. The kernel is $\ker(\pi_H) = \bigcap_{aH \in G/H} G_{aH}$. The stabilizer of an arbitrary coset aH is:

$$\begin{aligned} G_{aH} &= \{g \in G : g \cdot aH = aH\} = \{g \in G : gaH = aH\} \\ &= \{g \in G : a^{-1}ga \in H\} = \{g \in G : g \in aHa^{-1}\} = aHa^{-1}. \end{aligned}$$

   Therefore

$$\ker(\pi_H) = \bigcap_{a \in G} aHa^{-1}.$$

   It remains to show this is the *largest* normal subgroup of G contained in H. Since $\ker(\pi_H) \leq G_{eH} = H$ (part 2), the kernel is contained in H. It is normal in G since it is the kernel of a homomorphism (proposition 2.2.12).

   Conversely, let $N \trianglelefteq G$ with $N \leq H$. For any $a \in G$: $N = aNa^{-1} \leq aHa^{-1}$ (since $N \leq H$ implies $aNa^{-1} \leq aHa^{-1}$). Thus $N \leq \bigcap_{a \in G} aHa^{-1} = \ker(\pi_H)$, confirming maximality.

Example 4.5.7: D_4 Acting on Cosets of $\langle s \rangle$

Let $G = D_4$ and $H = \langle s \rangle = \{e, s\}$. The index $[D_4 : H] = 8/2 = 4$, so there are four left cosets:

$$C_1 = \{e,\ s\}, \quad C_2 = \{r,\ sr^3\}, \quad C_3 = \{r^2,\ sr^2\}, \quad C_4 = \{r^3,\ sr\}.$$

The coset action gives a homomorphism $\pi_H \colon D_4 \to S_4$. To find the image, we compute where r and s send each coset:

$$\begin{aligned} r\colon\ & C_1 \mapsto C_2,\ C_2 \mapsto C_3,\ C_3 \mapsto C_4,\ C_4 \mapsto C_1 && \Longrightarrow \quad \sigma_r = (1\ 2\ 3\ 4), \\ s\colon\ & C_1 \mapsto C_1,\ C_2 \mapsto C_4,\ C_3 \mapsto C_3,\ C_4 \mapsto C_2 && \Longrightarrow \quad \sigma_s = (2\ 4). \end{aligned}$$

The image $\pi_H(D_4) = \langle (1\ 2\ 3\ 4), (2\ 4) \rangle$ is a subgroup of S_4 isomorphic to D_4. In particular, $\ker(\pi_H) = \{e\}$, so the action is faithful: D_4 embeds into S_4. This is smaller than the Cayley embedding into S_8, and it recovers the natural representation of D_4 as the symmetry group of a square.

Theorem 4.5.6 predicted this: the kernel is $\bigcap_{g \in G} g\langle s \rangle g^{-1}$. Since the only conjugates of $\langle s \rangle$ are $\{e, s\}$ and $\{e, sr^2\}$, their intersection is $\{e\}$.

Example 4.5.8: Recovering the Index-2 Theorem

If $[G : H] = 2$, the coset action gives a homomorphism $\pi_H \colon G \to S_2 \cong \mathbb{Z}/2\mathbb{Z}$. Since $|S_2| = 2$, the kernel has index at most 2 in G. But $\ker(\pi_H) \leq H$ and $[G : H] = 2$, so $\ker(\pi_H) = H$. Since kernels are normal, $H \trianglelefteq G$.

We have thus re-derived corollary 3.3.6 as a special case of the coset action.

Subgroups of Smallest Prime Index

The observation in the previous example generalizes beyond index 2. The key insight is that if $[G : H] = p$ for a small prime p, then the coset action maps G into S_p, and S_p is "small enough" to force the kernel to be large.

Theorem 4.5.9: Subgroups of Smallest Prime Index are Normal

Let G be a finite group and let p be the smallest prime dividing $|G|$. If $H \leq G$ with $[G : H] = p$, then $H \trianglelefteq G$.

***Proof*:**
The coset action gives a homomorphism $\pi_H \colon G \to \mathrm{Sym}(G/H) \cong S_p$. Let $K = \ker(\pi_H)$. By theorem 4.5.6, $K \trianglelefteq G$ and $K \leq H$. We will show $K = H$.

By the First Isomorphism Theorem (theorem 3.1.15), $G/K \cong \pi_H(G) \leq S_p$, so $|G/K|$ divides $|S_p| = p!$. Since $K \leq H$, the index decomposes as

$$[G : K] = [G : H] \cdot [H : K] = p \cdot [H : K].$$

Therefore $p \cdot [H : K]$ divides $p!$, which gives $[H : K]$ divides $(p-1)!$.

On the other hand, $[H : K]$ divides $|H|$ by Lagrange's Theorem (theorem 3.3.1), and $|H|$ divides $|G|$, so every prime factor of $[H : K]$ is also a prime factor of $|G|$. Since p is the *smallest* prime dividing $|G|$, every prime factor of $[H : K]$ is at least p.

But every prime factor of $(p-1)!$ is strictly less than p. The only positive integer all of whose prime factors are simultaneously $\geq p$ and $< p$ is 1. Therefore $[H : K] = 1$, so $K = H$, and $H = \ker(\pi_H) \trianglelefteq G$.

Example 4.5.10: Applications of the Index-p Theorem

1. If $|G| = 2m$ with m odd, the smallest prime dividing $|G|$ is 2. Any subgroup of index 2 is normal. This recovers corollary 3.3.6.
2. Let $|G| = 2 \cdot 3 \cdot 5 = 30$. The smallest prime dividing $|G|$ is 2. If G has a subgroup of index 2 (i.e. order 15), it is automatically normal. Any subgroup of index 3 need not be normal, since 3 is not the smallest prime dividing 30.
3. Let $|G| = 3 \cdot 7 = 21$. The smallest prime is 3. If G has a subgroup of index 3 (i.e. order 7), it is normal.
4. Let $|G| = 5 \cdot 11 \cdot 13 = 715$. The smallest prime is 5. A subgroup of index 5 (order 143), should one exist, is normal.

4.5.11 Remark A group of order n need not have a subgroup of every possible index. For instance, A_4 has order 12 and the smallest prime dividing 12 is 2, but A_4 has no subgroup of order 6 (cf. the counterexample to the converse of Lagrange's Theorem, example 3.3.8). The theorem says that *if* a subgroup of index p exists, it must be normal. It does not guarantee existence. The question of existence will be addressed by the Sylow Theorems in Section 4.8.

We pause to take stock. Starting from the simple idea of a group multiplying its own elements, we have obtained:

- Cayley's Theorem: every group embeds into a symmetric group.
- The coset action: a versatile tool that converts subgroup information ($H \leq G$) into homomorphism information ($G \to S_p$).
- The index-p theorem: a powerful normality criterion that requires nothing more than knowing $[G : H]$ and the prime factorization of $|G|$.

4.6 Action by Conjugation and the Class Equation

In Section 4.5, a group acted on itself by left multiplication, and the payoff was Cayley's Theorem: every group is a group of permutations. We now let a group act on itself by *conjugation*, and the payoff will be of a completely different character: arithmetic information about the internal structure of the group, encoded in an identity called the *Class Equation*.

Conjugation on Elements

Let G be a group and let $X = G$. The *conjugation action* is defined by

$$g \cdot a \;=\; gag^{-1} \qquad \text{for all } g, a \in G.$$

We verified in item 6 of example 4.1.5 that this is a valid group action. Let us now identify its orbits and stabilizers.

Definition 4.6.1: Conjugacy Class

Two elements $a, b \in G$ are *conjugate* in G if $b = gag^{-1}$ for some $g \in G$, i.e. if they lie in the same orbit of the conjugation action. The orbit

$$\mathrm{cl}(a) \;=\; G \cdot a \;=\; \{gag^{-1} : g \in G\}$$

is called the *conjugacy class* of a.

Since orbits partition the set (proposition 4.2.3), conjugacy classes partition G: every element belongs to exactly one conjugacy class.

The stabilizer of the conjugation action has a familiar name:

$$G_a = \{g \in G : gag^{-1} = a\} = \{g \in G : ga = ag\} = C_G(a),$$

the centralizer of a in G (definition 2.2.7). The Orbit-Stabilizer Theorem (theorem 4.3.1) therefore gives:

$$|\operatorname{cl}(a)| \;=\; [G : C_G(a)]. \tag{4.3}$$

An element a has a singleton conjugacy class, $\operatorname{cl}(a) = \{a\}$, if and only if $gag^{-1} = a$ for all $g \in G$, i.e. if and only if a commutes with every element of G. This is precisely the condition $a \in Z(G)$ (definition 2.2.4). Thus:

The singleton conjugacy classes are exactly the elements of the center.

Example 4.6.2: Conjugacy Classes of Small Groups

1. If G is abelian, then $gag^{-1} = a$ for all g, a, so every conjugacy class is a singleton: $\operatorname{cl}(a) = \{a\}$ for all a. The conjugation action is trivial.
2. Let $G = Q_8 = \{\pm 1, \pm i, \pm j, \pm k\}$. The center is $Z(Q_8) = \{1, -1\}$ (example 1.2.31). The non-central elements form three conjugacy classes:

   $$\operatorname{cl}(i) = \{i, -i\}, \qquad \operatorname{cl}(j) = \{j, -j\}, \qquad \operatorname{cl}(k) = \{k, -k\}.$$

   To verify: $jij^{-1} = ji(-j) = ji \cdot j^{-1}$. Using $ji = -k$ and $(-k)(-j) = kj = -i$, so $jij^{-1} = -i$. Each conjugacy class has size $[Q_8 : C_{Q_8}(i)] = 8/4 = 2$, since $C_{Q_8}(i) = \langle i \rangle$ has order 4.
3. Let $G = D_4$. The center is $Z(D_4) = \{e, r^2\}$. The non-central conjugacy classes are:

   $$\operatorname{cl}(r) = \{r, r^3\}, \qquad \operatorname{cl}(s) = \{s, sr^2\}, \qquad \operatorname{cl}(sr) = \{sr, sr^3\}.$$

   Each has size 2, consistent with $[D_4 : C_{D_4}(r)] = 8/4 = 2$, etc.

The Class Equation

We now translate the orbit decomposition of the conjugation action into an arithmetic identity.

Theorem 4.6.3: The Class Equation

Let G be a finite group, and let $g_1, \ldots, g_r$ be representatives of the distinct conjugacy classes of G that are *not* contained in $Z(G)$. Then

$$|G| \;=\; |Z(G)| \;+\; \sum_{i=1}^{r} [G : C_G(g_i)].$$

Each term $[G : C_G(g_i)]$ in the sum is strictly greater than 1 and divides $|G|$.

***Proof*:**
The conjugacy classes partition G, so $|G| = \sum |\operatorname{cl}(a)|$ as a ranges over a set of orbit representatives. We split this sum into two parts:

- Elements $a \in Z(G)$ have $|\operatorname{cl}(a)| = 1$. There are $|Z(G)|$ such elements.
- Elements $a \notin Z(G)$ have $|\operatorname{cl}(a)| = [G : C_G(a)] > 1$ (since $C_G(a) \neq G$ when $a \notin Z(G)$). Let $g_1, \ldots, g_r$ be representatives of these non-central classes.

Combining:

$$|G| = \sum_{a \in Z(G)} 1 + \sum_{i=1}^{r} |\operatorname{cl}(g_i)| = |Z(G)| + \sum_{i=1}^{r} [G : C_G(g_i)].$$

Each $[G : C_G(g_i)]$ divides $|G|$ by Lagrange's Theorem (theorem 3.3.1), and is > 1 since $g_i \notin Z(G)$.

Example 4.6.4: The Class Equation in Practice

1. For $G = Q_8$: $|Z(Q_8)| = 2$ and the three non-central classes each have size 2, giving $8 = 2 + 2 + 2 + 2$.
2. For $G = D_4$: $|Z(D_4)| = 2$ and the three non-central classes each have size 2, giving $8 = 2 + 2 + 2 + 2$.
3. For $G = S_3$: $Z(S_3) = \{e\}$, and the conjugacy classes are $\{e\}$, $\{(1\ 2), (1\ 3), (2\ 3)\}$, $\{(1\ 2\ 3), (1\ 3\ 2)\}$, giving $6 = 1 + 3 + 2$.
4. If G is abelian, the Class Equation reads $|G| = |G|$, which is vacuously true but uninformative. The Class Equation is a tool for *non-abelian* groups.

p-Groups Have Nontrivial Center

The Class Equation becomes especially powerful when $|G|$ is a prime power. The following theorem is the first result that students typically cannot prove *without* group actions.

Theorem 4.6.5: p-Groups Have Nontrivial Center

Let p be a prime and let G be a group of order p^α for some $\alpha \geq 1$. Then $Z(G) \neq \{e\}$. More precisely, p divides $|Z(G)|$.

***Proof*:**
The Class Equation gives

$$p^\alpha = |Z(G)| + \sum_{i=1}^{r} [G : C_G(g_i)].$$

For each i, the centralizer $C_G(g_i)$ is a proper subgroup of G (since $g_i \notin Z(G)$), so $[G : C_G(g_i)] > 1$. Since $C_G(g_i) \leq G$ and $|G| = p^\alpha$, Lagrange's Theorem gives $|C_G(g_i)| = p^{\beta_i}$ for some $\beta_i < \alpha$. Therefore $[G : C_G(g_i)] = p^{\alpha - \beta_i}$, which is divisible by p.

The left-hand side p^α is divisible by p, and every term in the sum is divisible by p. Therefore $|Z(G)|$ is divisible by p, so $|Z(G)| \geq p > 1$.

The argument is clean and short, but notice how much machinery is involved beneath the surface: the conjugation action, the Orbit-Stabilizer Theorem (to get $|\operatorname{cl}(g_i)| = [G : C_G(g_i)]$), Lagrange's Theorem (to deduce $p \big| [G : C_G(g_i)]$), and the orbit partition (to write the Class Equation). This is a vivid demonstration of the power of group actions as a *proof technique*.

Corollary 4.6.6: Groups of Order p^2 Are Abelian

If $|G| = p^2$ for some prime p, then G is abelian. More precisely, $G \cong \mathbb{Z}/p^2\mathbb{Z}$ or $G \cong \mathbb{Z}/p\mathbb{Z} \times \mathbb{Z}/p\mathbb{Z}$.

***Proof*:**

By theorem 4.6.5, $p \big| |Z(G)|$. Since $Z(G) \leq G$ and $|G| = p^2$, Lagrange gives $|Z(G)| \in \{p, p^2\}$.

If $|Z(G)| = p^2$, then $Z(G) = G$ and G is abelian.

If $|Z(G)| = p$, then $|G/Z(G)| = p^2/p = p$, so $G/Z(G)$ has prime order and is therefore cyclic (corollary 3.3.2). We claim this forces G to be abelian, contradicting $Z(G) \neq G$.

Indeed, let $G/Z(G) = \langle gZ(G) \rangle$. Then every element of G can be written as $g^k z$ for some $k \in \mathbb{Z}$ and $z \in Z(G)$. For any two elements $g^{k_1} z_1$ and $g^{k_2} z_2$:

$$(g^{k_1} z_1)(g^{k_2} z_2) = g^{k_1} g^{k_2} z_1 z_2 = g^{k_2} g^{k_1} z_2 z_1 = (g^{k_2} z_2)(g^{k_1} z_1),$$

where we used that powers of g commute with each other, that $z_1, z_2 \in Z(G)$ commute with everything, and that $Z(G)$ is abelian. Thus G is abelian, a contradiction.

Therefore $|Z(G)| = p^2$, and G is abelian of order p^2. By the classification of finite abelian groups (or by direct argument using corollary 3.3.2), the only abelian groups of order p^2 are $\mathbb{Z}/p^2\mathbb{Z}$ and $\mathbb{Z}/p\mathbb{Z} \times \mathbb{Z}/p\mathbb{Z}$.

4.6.7 Remark The key step ("if $G/Z(G)$ is cyclic, then G is abelian") is worth remembering in its own right. More generally, if $G/Z(G)$ is cyclic, the same argument shows every pair of elements commutes, so G is abelian and $Z(G) = G$. This means $G/Z(G)$ is trivial, a stronger conclusion than cyclic. In other words: $G/Z(G)$ *can never be a nontrivial cyclic group.*

Conjugation on Subsets and Subgroups

So far, conjugation has acted on *elements* of G. There is a natural extension to *subsets*: let $\mathcal{P}(G)$ denote the power set of G, and define

$$g \cdot S \;=\; gSg^{-1} \;=\; \{gsg^{-1} : s \in S\} \qquad \text{for } g \in G,\ S \subseteq G.$$

This defines a group action $G \curvearrowright \mathcal{P}(G)$. (Verification of the axioms is identical to the element case.)

Definition 4.6.8: Conjugate Subsets

Two subsets $S, T \subseteq G$ are *conjugate* in G if $T = gSg^{-1}$ for some $g \in G$.

When we restrict attention to the set of all *subgroups* of G, conjugation sends subgroups to (isomorphic) subgroups, so this restriction is also a valid action.

The stabilizer and orbit of a subset S under this action connect to familiar concepts:

- The *stabilizer* of S is
$$G_S = \{g \in G : gSg^{-1} = S\} = N_G(S),$$
the normalizer of S in G (definition 2.2.10).
- The *orbit* $G \cdot S = \{gSg^{-1} : g \in G\}$ is the set of all conjugates of S.

The Orbit-Stabilizer Theorem immediately yields:

Corollary 4.6.9: Number of Conjugates

The number of distinct conjugates of a subset $S \subseteq G$ is $[G : N_G(S)]$. In particular, S is the only member of its conjugacy class if and only if $N_G(S) = G$, i.e. if and only if $S \trianglelefteq G$ (when S is a subgroup) or S is a union of conjugacy classes (when S is an arbitrary subset).

This corollary will be indispensable in the proof of Sylow's Theorems (Section 4.8), where we count the number of conjugates of a Sylow p-subgroup.

Example 4.6.10: Conjugates of a Subgroup

Let $G = S_4$ and $H = \langle(1\ 2)\rangle = \{e, (1\ 2)\}$. The normalizer $N_{S_4}(H)$ consists of all $\sigma \in S_4$ with $\sigma H \sigma^{-1} = H$, i.e. $\sigma(1\ 2)\sigma^{-1} \in \{e, (1\ 2)\}$. Since conjugation preserves cycle type (proposition 1.2.27), $\sigma(1\ 2)\sigma^{-1}$ is always a transposition. It equals $(1\ 2)$ precisely when σ fixes the set $\{1, 2\}$, so

$$N_{S_4}(H) = \{\sigma \in S_4 : \{\sigma(1), \sigma(2)\} = \{1, 2\}\} = \{e,\ (1\ 2),\ (3\ 4),\ (1\ 2)(3\ 4)\}.$$

Therefore H has $[S_4 : N_{S_4}(H)] = 24/4 = 6$ conjugates. These are the six subgroups $\langle(i\ j)\rangle$ for $1 \leq i < j \leq 4$, one for each transposition.

Conjugacy in S_n and Cycle Types

Since S_n plays a distinguished role throughout this chapter, we take a moment to characterize its conjugacy classes completely. The answer is as clean as one could hope: conjugacy in S_n is determined entirely by cycle type.

Theorem 4.6.11: Conjugacy Classes in S_n

Two permutations in S_n are conjugate if and only if they have the same cycle type (definition 1.2.15).

***Proof*:**

One direction was established in proposition 1.2.27: if $\tau = \sigma\pi\sigma^{-1}$, then τ has the same cycle type as π, because conjugation by σ sends the cycle $(a_1\ a_2\ \cdots\ a_k)$ to $(\sigma(a_1)\ \sigma(a_2)\ \cdots\ \sigma(a_k))$, preserving the cycle length.

For the converse, suppose π and τ have the same cycle type. Write them in disjoint cycle notation (including 1-cycles for fixed points):

$$\pi = (a_1\ \cdots\ a_{k_1})(b_1\ \cdots\ b_{k_2})\cdots(z_1\ \cdots\ z_{k_m}),$$
$$\tau = (c_1\ \cdots\ c_{k_1})(d_1\ \cdots\ d_{k_2})\cdots(w_1\ \cdots\ w_{k_m}),$$

where the cycle lengths $k_1, k_2, \ldots, k_m$ are the same in both (this is what "same cycle type" means). Define $\sigma \in S_n$ by

$$\sigma(a_i) = c_i, \quad \sigma(b_j) = d_j, \quad \ldots, \quad \sigma(z_l) = w_l$$

for all indices. Since both decompositions account for every element of $\{1, \ldots, n\}$ exactly once, σ is a well-defined bijection. Then

$$\sigma\pi\sigma^{-1} = (\sigma(a_1)\ \cdots\ \sigma(a_{k_1}))(\sigma(b_1)\ \cdots\ \sigma(b_{k_2}))\cdots = (c_1\ \cdots\ c_{k_1})(d_1\ \cdots\ d_{k_2})\cdots = \tau.$$

So π and τ are conjugate.

Example 4.6.12: Conjugacy Classes of S_4

The partitions of 4 are $4 = 4 = 3+1 = 2+2 = 2+1+1 = 1+1+1+1$, giving five cycle types and hence five conjugacy classes:

Cycle type	*Example*	*Description*	*Class size*	$\lvert C_{S_4}(\cdot)\rvert$
(1^4)	e	identity	1	24
$(2, 1^2)$	(1 2)	transpositions	6	4
(2^2)	(1 2)(3 4)	double transpositions	3	8
$(3, 1)$	(1 2 3)	3-cycles	8	3
(4)	(1 2 3 4)	4-cycles	6	4

The class sizes sum to $1+6+3+8+6 = 24 = |S_4|$. The centralizer sizes in the last column satisfy $|\operatorname{cl}(\pi)| \cdot |C_{S_4}(\pi)| = 24$ by (4.3).

Since $Z(S_4) = \{e\}$ (for $n \geq 3$, the center of S_n is trivial), the Class Equation reads:

$$24 = 1 + 6 + 3 + 8 + 6.$$

More generally, there is a formula for the size of each conjugacy class in S_n. If a permutation has cycle type $(1^{a_1}\, 2^{a_2}\, \cdots\, n^{a_n})$ (meaning a_k cycles of length k, with $\sum k\, a_k = n$), then the size of its centralizer is

$$|C_{S_n}(\pi)| \;=\; \prod_{k=1}^{n} k^{a_k} \cdot a_k! \tag{4.4}$$

and the conjugacy class has size $n!/|C_{S_n}(\pi)|$. (The factor k^{a_k} accounts for rotations within each k-cycle, and $a_k!$ accounts for permuting cycles of the same length.) We leave the verification as an exercise.

4.7 Automorphisms and Inner Automorphisms

In Section 4.6, the conjugation action $g \cdot a = gag^{-1}$ gave us the Class Equation by viewing each g as a *permutation* of the underlying set of G. But conjugation does more than permute elements: it preserves the group operation. That is, the map $a \mapsto gag^{-1}$ is not just a bijection $G \to G$ but an *automorphism*. Upgrading the permutation representation from $\mathrm{Sym}(G)$ to $\mathrm{Aut}(G)$ will yield one of the most important structural results in the chapter.

Fix an element $g \in G$ and consider the map

$$\varphi_g \colon G \to G, \qquad \varphi_g(x) = gxg^{-1}.$$

Proposition 4.7.1: Conjugation by g is an Automorphism

For each $g \in G$, the map φ_g is an automorphism of G.

***Proof*:**
We verify that φ_g is a bijective homomorphism.

Homomorphism. For any $x, y \in G$:

$$\varphi_g(xy) = g(xy)g^{-1} = (gxg^{-1})(gyg^{-1}) = \varphi_g(x)\,\varphi_g(y).$$

Bijection. The map $\varphi_{g^{-1}}$ is a two-sided inverse:

$$(\varphi_g \circ \varphi_{g^{-1}})(x) = g(g^{-1}xg)g^{-1} = x = g^{-1}(gxg^{-1})g = (\varphi_{g^{-1}} \circ \varphi_g)(x).$$

Thus $\varphi_g \in \mathrm{Aut}(G)$ (definition 1.4.16).

Since each φ_g is an automorphism, we can ask whether the assignment $g \mapsto \varphi_g$ is compatible with the group structure.

Proposition 4.7.2: The Conjugation Map is a Homomorphism

The map

$$\Phi \colon G \to \mathrm{Aut}(G), \qquad \Phi(g) = \varphi_g,$$

is a group homomorphism, with $\ker(\Phi) = Z(G)$.

***Proof*:**
For any $g, h \in G$ and $x \in G$:

$$\Phi(gh)(x) = \varphi_{gh}(x) = (gh)x(gh)^{-1} = g(hxh^{-1})g^{-1} = \varphi_g(\varphi_h(x)) = (\varphi_g \circ \varphi_h)(x).$$

Since this holds for all x, we have $\Phi(gh) = \Phi(g) \circ \Phi(h)$, so Φ is a homomorphism.

The kernel consists of those g for which φ_g is the identity automorphism:

$$\ker(\Phi) = \{g \in G : gxg^{-1} = x \text{ for all } x \in G\} = \{g \in G : gx = xg \text{ for all } x \in G\} = Z(G).$$

Let us pause to compare this with the conjugation action from Section 4.6. There, we had a homomorphism $\rho\colon G \to \mathrm{Sym}(G)$ (the permutation representation of the conjugation action). Now we have a homomorphism $\Phi\colon G \to \mathrm{Aut}(G)$. Since $\mathrm{Aut}(G) \leq \mathrm{Sym}(G)$ (proposition 1.4.17), these are compatible: Φ is simply ρ with its codomain refined from $\mathrm{Sym}(G)$ to $\mathrm{Aut}(G)$. The kernel is the same in both cases, i.e. $Z(G)$, but the refined codomain gives us access to the richer structure of $\mathrm{Aut}(G)$.

Definition 4.7.3: Inner Automorphism

The image of the conjugation homomorphism $\Phi\colon G \to \mathrm{Aut}(G)$ is called the group of *inner automorphisms* of G:

$$\mathrm{Inn}(G) \;=\; \Phi(G) \;=\; \{\varphi_g : g \in G\} \;\leq\; \mathrm{Aut}(G).$$

An automorphism that is *not* inner is called an *outer automorphism*.

Since Φ is a homomorphism with kernel $Z(G)$ and image $\mathrm{Inn}(G)$, the First Isomorphism Theorem (theorem 3.1.15) immediately yields:

Theorem 4.7.4: $G/Z(G) \cong \mathrm{Inn}(G)$

For any group G,

$$G/Z(G) \;\cong\; \mathrm{Inn}(G).$$

***Proof*:**
Apply the First Isomorphism Theorem to $\Phi\colon G \to \mathrm{Aut}(G)$:

$$G/\ker(\Phi) \;\cong\; \Phi(G), \qquad \text{i.e.,} \qquad G/Z(G) \;\cong\; \mathrm{Inn}(G).$$

Short as it is, this theorem encodes a great deal of structural information. It says that the "non-abelian part" of G, measured by the quotient $G/Z(G)$, is faithfully captured by the inner automorphisms. The larger the center, the fewer inner automorphisms there are, and vice versa.

Example 4.7.5: Inner Automorphisms of Familiar Groups

1. If G is abelian, then $Z(G) = G$, so $\mathrm{Inn}(G) \cong G/G = \{e\}$. Every automorphism of G is outer.
2. For $G = S_3$: $Z(S_3) = \{e\}$, so $\mathrm{Inn}(S_3) \cong S_3/\{e\} \cong S_3$. Since $|\mathrm{Aut}(S_3)| = 6 = |S_3|$ (one can verify that every automorphism of S_3 is inner), we have $\mathrm{Inn}(S_3) = \mathrm{Aut}(S_3)$.
3. For $G = D_4$: $Z(D_4) = \{e, r^2\}$, so $\mathrm{Inn}(D_4) \cong D_4/\{e, r^2\}$, a group of order 4. Since $D_4/\{e, r^2\}$ is non-cyclic (it is generated by two elements of order 2), $\mathrm{Inn}(D_4)$ is isomorphic to the Klein four-group. In fact, $|\mathrm{Aut}(D_4)| = 8$, so $[\mathrm{Aut}(D_4) : \mathrm{Inn}(D_4)] = 2$: there are automorphisms of D_4 that cannot be realized by conjugation.

The construction above has a natural generalization. Instead of conjugating G by itself, we can conjugate any subgroup H by elements that normalize it.

Theorem 4.7.6: The N/C Theorem

Let $H \leq G$. The map

$$\Psi\colon N_G(H) \to \mathrm{Aut}(H), \qquad \Psi(g)(h) = ghg^{-1},$$

is a well-defined homomorphism with $\ker(\Psi) = C_G(H)$. Consequently,

$$N_G(H) \,/\, C_G(H) \;\hookrightarrow\; \mathrm{Aut}(H).$$

In particular, $N_G(H)/C_G(H)$ is isomorphic to a subgroup of $\mathrm{Aut}(H)$.

***Proof*:**
The map $\Psi(g) = \varphi_g|_H$ (conjugation by g, restricted to H) is well-defined because $g \in N_G(H)$ means $gHg^{-1} = H$ (definition 2.2.10), so φ_g sends H to H. That $\varphi_g|_H$ is an automorphism of H follows from proposition 4.7.1 by restriction.

The verification that Ψ is a homomorphism is identical to the proof of proposition 4.7.2. The kernel is

$$\ker(\Psi) = \{g \in N_G(H) : ghg^{-1} = h \text{ for all } h \in H\} = C_G(H) \cap N_G(H) = C_G(H),$$

where the last equality uses $C_G(H) \leq N_G(H)$ (if g commutes with every element of H, then certainly $gHg^{-1} = H$). The embedding follows from the First Isomorphism Theorem (theorem 3.1.15).

When $H \trianglelefteq G$, we have $N_G(H) = G$, so the theorem gives $G/C_G(H) \hookrightarrow \mathrm{Aut}(H)$. When $H = G$ (which is always normal in itself), we recover $G/Z(G) \cong \mathrm{Inn}(G)$ as a special case.

4.7.7 Foreshadowing: Semi-Direct Products The N/C Theorem has an important special case. Suppose $H \trianglelefteq G$ and $K \leq G$. Then $K \leq N_G(H) = G$, so restricting Ψ to K gives a homomorphism

$$\psi\colon K \to \mathrm{Aut}(H), \qquad k \mapsto (h \mapsto khk^{-1}).$$

This homomorphism ψ encodes how K "twists" H by conjugation, and it will be the key ingredient in the definition of the *semi-direct product* (chapter 5). Knowing H, K, and ψ is enough to reconstruct the group G (under suitable conditions).

To define the quotient $\mathrm{Aut}(G)/\mathrm{Inn}(G)$, we first verify that $\mathrm{Inn}(G)$ is normal in $\mathrm{Aut}(G)$.

Proposition 4.7.8: $\mathrm{Inn}(G) \trianglelefteq \mathrm{Aut}(G)$

For any group G, $\mathrm{Inn}(G)$ is a normal subgroup of $\mathrm{Aut}(G)$.

***Proof*:**
Let $\sigma \in \mathrm{Aut}(G)$ and $\varphi_g \in \mathrm{Inn}(G)$. For any $x \in G$:

$$(\sigma \circ \varphi_g \circ \sigma^{-1})(x) = \sigma\big(g \cdot \sigma^{-1}(x) \cdot g^{-1}\big) = \sigma(g) \cdot x \cdot \sigma(g)^{-1} = \varphi_{\sigma(g)}(x).$$

Thus $\sigma \circ \varphi_g \circ \sigma^{-1} = \varphi_{\sigma(g)} \in \mathrm{Inn}(G)$, and $\mathrm{Inn}(G) \trianglelefteq \mathrm{Aut}(G)$.

Definition 4.7.9: Outer Automorphism Group

The *outer automorphism group* of G is the quotient

$$\mathrm{Out}(G) \;=\; \mathrm{Aut}(G) \,/\, \mathrm{Inn}(G).$$

The outer automorphism group measures how much of $\mathrm{Aut}(G)$ is *not* explained by conjugation. A group with $\mathrm{Out}(G) = \{e\}$ is called *complete* (when it also has trivial center). In such a group, every automorphism is inner.

Example 4.7.10: Outer Automorphisms

1. If G is abelian, then $\mathrm{Inn}(G) = \{e\}$, so $\mathrm{Out}(G) \cong \mathrm{Aut}(G)$. All automorphisms are outer.
2. $\mathrm{Out}(S_n) = \{e\}$ for $n \neq 6$: every automorphism of S_n is inner. The case $n = 6$ is exceptional: $|\mathrm{Out}(S_6)| = 2$, giving S_6 a unique outer automorphism (up to composition with inner ones).
3. $\mathrm{Out}(D_4) \cong \mathbb{Z}/2\mathbb{Z}$: there is one nontrivial coset of $\mathrm{Inn}(D_4)$ in $\mathrm{Aut}(D_4)$.

4.7.11 Foreshadowing: Matrix Groups Have Outer Automorphisms As $\mathrm{Aut}(S_n) = \mathrm{Inn}(S_n)$, and $S_n \hookrightarrow M_n(F)$ by permuting the columns (or rows), it is tempting to guess that this must imply enough rigidity so that the group of matrices has only inner automorphisms, i.e. conjugation. As it turns out, this is not the case! On $G = GL_n(F)$ for a field F (definition 1.2.33), both

$$\tau(A) = (A^T)^{-1}$$

and, for $F = \mathbb{C}$,

$$\kappa(A) = \overline{A} \text{ (conjugate every entry)}$$

are automorphisms (check that each respects products and has an inverse). Neither is inner: the key is that conjugation preserves the determinant, since $\det(BAB^{-1}) = \det A$. But for $A = \mathrm{diag}(2, 1, \ldots, 1) \in GL_n(\mathbb{R})$ we get $\det \tau(A) = \frac{1}{2} \neq 2$, and for $A = \mathrm{diag}(i, 1, \ldots, 1) \in GL_n(\mathbb{C})$ we get $\det \kappa(A) = -i \neq i$. So $\mathrm{Out}(GL_n(\mathbb{R}))$ and $\mathrm{Out}(GL_n(\mathbb{C}))$ are nontrivial.

However, these are essentially the only sources. Schreier and van der Waerden [89] proved that for $n \geq 3$, every automorphism of the quotient of $SL_n(F)$ by its scalar matrices comes from conjugation by an invertible matrix, an automorphism of the field F applied to the entries, and possibly τ. Why exactly these appear is explained in *Geometric Representation Theory* [41].

For later use, the following short exact sequence that encodes the relationship between the center, the group, and its inner automorphisms is written out explicitly:

$$1 \longrightarrow Z(G) \hookrightarrow G \xrightarrow{\Phi} \mathrm{Inn}(G) \longrightarrow 1 \tag{4.5}$$

In particular, $Z(G)$ measures how far G is from being faithfully represented by its inner automorphisms. $\mathrm{Inn}(G)$ captures the "non-central" part of G. The center is precisely the part that acts trivially by conjugation.

4.7.1 Characteristic Subgroups

Normal subgroups are defined by invariance under *inner* automorphisms: H is normal in G if $\varphi_g(H) = H$ for every $\varphi_g \in \mathrm{Inn}(G)$. A natural strengthening is to require invariance under *all* automorphisms.

Definition 4.7.12: Characteristic Subgroup

A subgroup $H \leq G$ is *characteristic* in G, written $H \operatorname{char} G$, if

$$\sigma(H) = H \qquad \text{for every } \sigma \in \mathrm{Aut}(G).$$

Proposition 4.7.13: Properties of Characteristic Subgroups

1. If $H \operatorname{char} G$, then $H \trianglelefteq G$.
2. If H is the unique subgroup of G of a given order, then $H \operatorname{char} G$.
3. If $H \operatorname{char} K$ and $K \trianglelefteq G$, then $H \trianglelefteq G$.

***Proof*:**

1. Since $\mathrm{Inn}(G) \leq \mathrm{Aut}(G)$, invariance under all automorphisms implies invariance under inner automorphisms: $gHg^{-1} = \varphi_g(H) = H$ for all $g \in G$.
2. Let $\sigma \in \mathrm{Aut}(G)$. Since σ is an isomorphism, $\sigma(H)$ is a subgroup of G with $|\sigma(H)| = |H|$. By uniqueness, $\sigma(H) = H$.
3. Let $g \in G$. Since $K \trianglelefteq G$, the inner automorphism φ_g restricts to an automorphism $\varphi_g|_K \in \mathrm{Aut}(K)$ (because $gKg^{-1} = K$). Since $H \operatorname{char} K$, this automorphism preserves H:

   $$gHg^{-1} = \varphi_g(H) = (\varphi_g|_K)(H) = H.$$

   Since this holds for every $g \in G$, $H \trianglelefteq G$.

Item 3 is the principal reason characteristic subgroups are useful. Recall that normality is *not* transitive: $H \trianglelefteq K$ and $K \trianglelefteq G$ does *not* imply $H \trianglelefteq G$ in general (example 3.7.4). Characteristic subgroups provide a partial remedy: if the inner link is characteristic (rather than only normal), transitivity is restored.

Example 4.7.14: Characteristic Subgroups

1. The center $Z(G)$ is characteristic in G: if $\sigma \in \mathrm{Aut}(G)$ and $z \in Z(G)$, then for any $x \in G$,

   $$\sigma(z)\,x = \sigma(z)\,\sigma(\sigma^{-1}(x)) = \sigma(z \cdot \sigma^{-1}(x)) = \sigma(\sigma^{-1}(x) \cdot z) = x\,\sigma(z),$$

   so $\sigma(z) \in Z(G)$. Thus $\sigma(Z(G)) \subseteq Z(G)$, and applying the same argument to σ^{-1} gives equality.
2. The commutator subgroup $G' = \langle xyx^{-1}y^{-1} : x, y \in G \rangle$ is characteristic in G: any automorphism σ sends commutators to commutators ($\sigma(xyx^{-1}y^{-1}) = \sigma(x)\sigma(y)\sigma(x)^{-1}\sigma(y)^{-1}$), so

$\sigma(G') = G'$.

3. Every Sylow p-subgroup of a group G is normal if and only if it is the *unique* Sylow p-subgroup. By item 2 of proposition 4.7.13, such a subgroup is automatically characteristic. We will use this in Section 4.8.

4.7.15 Remark: Normality vs. Characteristic The logical chain is:

$$\text{characteristic} \implies \text{normal} \implies \text{subgroup},$$

and neither implication reverses. A normal subgroup that is not characteristic: consider $G = \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z}$ and $H = \{(0,0),(1,0)\}$. Then $H \trianglelefteq G$ (since G is abelian), but the automorphism swapping the two coordinates sends H to $\{(0,0),(0,1)\} \neq H$. So H is normal but not characteristic.

We summarize the automorphism-related groups and their relationships in a single diagram:

$$\begin{array}{ccccccccc} 1 & \longrightarrow & Z(G) & \hookrightarrow & G & \xrightarrow{\Phi} & \mathrm{Inn}(G) & \hookrightarrow & \mathrm{Aut}(G) & \twoheadrightarrow & \mathrm{Out}(G) & \longrightarrow & 1 \\ & & & & & & \mathrel{\rotatebox{90}{$\vartriangle$}} & & & & & & \\ & & & & & & \mathrm{Aut}(G) & & & & & & \end{array}$$

The top row is exact: $Z(G)$ is the kernel of Φ, $\mathrm{Inn}(G)$ is its image (hence the kernel of the projection to $\mathrm{Out}(G)$), and $\mathrm{Out}(G)$ is the cokernel. This picture captures the hierarchy at a glance: $Z(G)$ measures commutativity, $\mathrm{Inn}(G)$ measures conjugation, and $\mathrm{Out}(G)$ measures the "exotic" automorphisms that conjugation cannot produce.

4.8 Sylow's Theorems

Lagrange's Theorem (theorem 3.3.1) shows that if $H \leq G$, then $|H|$ divides $|G|$. The converse is false in general: A_4 has order 12 but no subgroup of order 6 (example 3.3.8). Sylow's Theorems provide the best *partial converse*: for every prime power p^α dividing $|G|$, a subgroup of order p^α not only exists but is essentially unique up to conjugation, and the number of such subgroups is tightly constrained. These are among the most powerful and frequently used results in finite group theory, and their proofs are an applications of everything we have built in this chapter: the Orbit-Stabilizer Theorem, the Class Equation, and the coset action.

Definition 4.8.1: p-Group

Let p be a prime. A group P is called a *p-group* if $|P| = p^k$ for some $k \geq 0$. A subgroup $H \leq G$ that is a p-group is called a *p-subgroup* of G.

Definition 4.8.2: Sylow p-Subgroup

Let G be a finite group and write $|G| = p^\alpha m$ where $\alpha \geq 0$ and $p \nmid m$ (so p^α is the largest power of p dividing $|G|$). A subgroup $P \leq G$ of order p^α is called a *Sylow p-subgroup* of G. We write $\mathrm{Syl}_p(G)$ for the set of all Sylow p-subgroups of G, and $n_p = n_p(G) = |\mathrm{Syl}_p(G)|$ for their number.

Example 4.8.3: Sylow Subgroups of Small Groups

1. $|S_3| = 6 = 2 \cdot 3$. Sylow 2-subgroups have order 2: these are $\langle(1\ 2)\rangle$, $\langle(1\ 3)\rangle$, $\langle(2\ 3)\rangle$. Sylow 3-subgroups have order 3: only $\langle(1\ 2\ 3)\rangle$. So $n_2 = 3$ and $n_3 = 1$.
2. $|A_4| = 12 = 2^2 \cdot 3$. Sylow 2-subgroups have order 4. Sylow 3-subgroups have order 3.
3. If $|G| = p^\alpha$ (a p-group), then G itself is its only Sylow p-subgroup, so $n_p = 1$.
4. $|\mathbb{Z}/n\mathbb{Z}| = n$. For each prime p dividing n, the unique subgroup of order p^α (where $p^\alpha \| n$) is the unique Sylow p-subgroup. (Here uniqueness follows from the fact that $\mathbb{Z}/n\mathbb{Z}$ has exactly one subgroup of each order dividing n.)

Before proving Sylow's Theorems, we isolate a lemma that will be used repeatedly. It says that when a p-group acts on a finite set, the number of fixed points is congruent to the total size of the set modulo p.

Lemma 4.8.4: Fixed-Point Congruence for p-Group Actions

Let P be a finite p-group acting on a finite set X. Then

$$|X| \equiv |X^P| \pmod{p},$$

where $X^P = \{x \in X : g \cdot x = x \text{ for all } g \in P\}$ is the set of fixed points (definition 4.2.8).

***Proof*:**
The orbits of P on X partition X. By the Orbit-Stabilizer Theorem (theorem 4.3.1), each orbit has size $[P : P_x] = |P|/|P_x|$, which divides $|P| = p^k$, so every orbit size is a power of p. An orbit has size 1 (i.e. p^0) if and only if it is a fixed point. Every other orbit has size p^j with $j \geq 1$, hence divisible by p. Therefore

$$|X| = |X^P| + \sum_{\substack{\text{non-fixed} \\ \text{orbits}}} p^{j_i} \equiv |X^P| \pmod{p}.$$

This lemma is the mechanism behind many counting arguments in p-group theory. For instance, theorem 4.6.5 (p-groups have nontrivial center) is a special case: applying the lemma to the conjugation action $G \curvearrowright G$ with $P = G$ gives $|G| \equiv |Z(G)| \pmod{p}$, so $p \big| |Z(G)|$. This lemma also gives an immediate proof of Cauchy's theorem corollary 3.3.9 worth pointing out:

Corollary 4.8.5: Cauchy Theorem using Fixed Point Theorem

Let G be a finite abelian group and p a prime dividing $|G|$. Then there exists a subgroup $P \leqslant G$ of order p.

***Proof*:**
Take the set

$$X = \{(g_1, ..., g_p) \in G^p \mid g_1 g_2 \cdots g_p = 1\}$$

This set has order $|G|^{p-1}$, for after choosing the elements $g_1, ...g_{p-1}$, the choice of g_p is forced:

$$g_p = (g_1 \cdots g_{p-1})^{-1}$$

Next, the shift action $\sigma : X \to X$ given by $\sigma(g_1, g_2, ..., g_p) = (g_2, g_3, ..., g_p, g_1)$ is well defined, since if $a = g_1$ and $b = g_2 \cdots g_p$ then $ab = 1$ and $b^{-1} = a$ meaning $ba = 1$ corollary 1.1.14. Then as $\sigma^k = \mathrm{id}$, this defines a $\mathbb{Z}/p\mathbb{Z}$-action on X. As $|\mathbb{Z}/p\mathbb{Z}| = p$, by lemma 4.8.4:

$$\left|X^{(\mathbb{Z}/p\mathbb{Z})}\right| \equiv |X| \equiv |G|^{p-1} \equiv 0 \bmod p$$

Hence $p \big| |X^{(\mathbb{Z}/p\mathbb{Z})}|$ implying there is a non-trivial element g such that $g^p = 1$, showing g has order p, and hence $\langle p \rangle \leqslant G$, completing the proof.10425

Theorem 4.8.6: Sylow's Theorems

Let G be a finite group with $|G| = p^\alpha m$, where p is prime and $p \nmid m$.

1. *(Existence.)* G has a Sylow p-subgroup, i.e. a subgroup of order p^α.
2. *(Conjugacy.)* Any two Sylow p-subgroups of G are conjugate. More generally, if P is a Sylow p-subgroup and Q is any p-subgroup of G, then $Q \leq gPg^{-1}$ for some $g \in G$.
3. *(Counting.)* The number n_p of Sylow p-subgroups satisfies:
   (a) $n_p = [G : N_G(P)]$ for any $P \in \mathrm{Syl}_p(G)$,
   (b) n_p divides m,
   (c) $n_p \equiv 1 \pmod p$.

We prove each part in turn.

***Proof of Sylow I*:**
We proceed by strong induction on $|G|$. If $|G| = 1$ (so $\alpha = 0$), the trivial subgroup has order $p^0 = 1$ and there is nothing to prove. Suppose $|G| > 1$ and that the result holds for all groups of order less than $|G|$. Write $|G| = p^\alpha m$ with $\alpha \geq 1$ and $p \nmid m$.

Consider the Class Equation (theorem 4.6.3):

$$|G| = |Z(G)| + \sum_{i=1}^{r} [G : C_G(g_i)].$$

Case 1: $p \big| |Z(G)|$. Since $Z(G)$ is abelian, Cauchy's Theorem for abelian groups (corollary 3.3.9) gives an element $z \in Z(G)$ of order p. Let $N = \langle z \rangle$. Since $N \leq Z(G)$, we have $N \trianglelefteq G$, and $|G/N| = p^{\alpha-1}m < |G|$.

By the induction hypothesis, G/N has a subgroup $\overline{P}$ of order $p^{\alpha-1}$. By the Correspondence Theorem (theorem 3.5.7), there exists $P \leq G$ with $N \leq P$ and $P/N = \overline{P}$. Then

$$|P| = |P/N| \cdot |N| = p^{\alpha-1} \cdot p = p^{\alpha}.$$

Case 2: $p \nmid |Z(G)|$. Since $p \big| |G|$ and the Class Equation gives $|Z(G)| = |G| - \sum [G : C_G(g_i)]$, if p divided every term $[G : C_G(g_i)]$, then p would divide $|Z(G)|$, a contradiction. So there exists some g_j with

$$p \nmid [G : C_G(g_j)].$$

Since $|G| = |C_G(g_j)| \cdot [G : C_G(g_j)]$ and $p^{\alpha} \big| |G|$ while $p \nmid [G : C_G(g_j)]$, we conclude $p^{\alpha} \big| |C_G(g_j)|$. But $g_j \notin Z(G)$, so $C_G(g_j) \neq G$ and $|C_G(g_j)| < |G|$.

By the induction hypothesis, $C_G(g_j)$ has a subgroup P of order p^{α}. Since $P \leq C_G(g_j) \leq G$ and $|P| = p^{\alpha}$, P is a Sylow p-subgroup of G. □

***Proof of Sylow II*:**
Let $P \in \mathrm{Syl}_p(G)$ and let Q be any p-subgroup of G. Consider the set of left cosets G/P, and let Q act on G/P by left multiplication: $q \cdot gP = (qg)P$.

Since $|G/P| = [G : P] = m$ and $p \nmid m$, the Fixed-Point Congruence (lemma 4.8.4) gives

$$m = |G/P| \equiv |(G/P)^Q| \pmod{p}.$$

Since $p \nmid m$, we have $(G/P)^Q \neq \varnothing$: there is at least one fixed point.

A coset gP is fixed by all $q \in Q$ if and only if $qgP = gP$ for all $q \in Q$, i.e. $g^{-1}qg \in P$ for all $q \in Q$, i.e. $g^{-1}Qg \leq P$, i.e. $Q \leq gPg^{-1}$.

So there exists $g \in G$ with $Q \leq gPg^{-1}$. If Q is itself a Sylow p-subgroup, then $|Q| = p^{\alpha} = |gPg^{-1}|$, and the inclusion forces $Q = gPg^{-1}$: all Sylow p-subgroups are conjugate. □

***Proof of Sylow III*:**
Let $\mathcal{S} = \mathrm{Syl}_p(G)$ and $n_p = |\mathcal{S}|$.

Part (a): $n_p = [G : N_G(P)]$. The group G acts on $\mathcal{S}$ by conjugation: $g \cdot P_i = gP_ig^{-1}$. By Sylow II, this action is transitive (any two Sylow p-subgroups lie in the same orbit). The stabilizer of P under this action is

$$G_P = \{g \in G : gPg^{-1} = P\} = N_G(P).$$

By the Orbit-Stabilizer Theorem (theorem 4.3.1), $n_p = |\mathcal{S}| = [G : N_G(P)]$.

Part (b): $n_p \big| m$. Since $P \leq N_G(P) \leq G$, the index decomposes as

$$[G : P] = [G : N_G(P)] \cdot [N_G(P) : P].$$

Thus $n_p = [G : N_G(P)]$ divides $[G : P] = m$.

Part (c): $n_p \equiv 1 \pmod{p}$. Fix $P_1 \in \mathcal{S}$ and let P_1 act on $\mathcal{S}$ by conjugation. By the Fixed-Point Congruence (lemma 4.8.4),

$$n_p \equiv |\mathcal{S}^{P_1}| \pmod{p},$$

where $\mathcal{S}^{P_1}$ is the set of Sylow p-subgroups fixed by every element of P_1.

We claim $\mathcal{S}^{P_1} = \{P_1\}$. Suppose $P_j \in \mathcal{S}^{P_1}$, so $P_1 \leq N_G(P_j)$. Since $P_j \trianglelefteq N_G(P_j)$ and $P_1 \leq N_G(P_j)$, the product P_1P_j is a subgroup of $N_G(P_j)$ (proposition 3.4.4). Its order is

$$|P_1P_j| = \frac{|P_1| \cdot |P_j|}{|P_1 \cap P_j|} = \frac{p^\alpha \cdot p^\alpha}{|P_1 \cap P_j|} = \frac{p^{2\alpha}}{|P_1 \cap P_j|},$$

which is a power of p (since $P_1 \cap P_j$ is a p-group). So P_1P_j is a p-subgroup of G containing P_1. Since P_1 is a *maximal* p-subgroup (it has order p^α), we must have $P_1P_j = P_1$, which gives $P_j \leq P_1$. Since $|P_j| = |P_1| = p^\alpha$, it follows that $P_j = P_1$.

Thus $|\mathcal{S}^{P_1}| = 1$, and $n_p \equiv 1 \pmod{p}$. □

With Sylow's Theorems in hand, we can immediately prove the full version of Cauchy's Theorem for arbitrary finite groups, completing the proof that was deferred in section 3.3:

Theorem 4.8.7: Cauchy's Theorem

If G is a finite group and p is a prime dividing $|G|$, then G has an element of order p.

***Proof*:**
Write $|G| = p^\alpha m$ with $\alpha \geq 1$ and $p \nmid m$. By Sylow I, G has a Sylow p-subgroup P of order p^α. Let $x \in P$ with $x \neq e$. Then $|\langle x \rangle|$ divides $|P| = p^\alpha$ (theorem 3.3.1), so $|x| = p^\beta$ for some $1 \leq \beta \leq \alpha$. The element $y = x^{p^{\beta-1}}$ satisfies

$$|y| = \frac{|x|}{(|x|,\, p^{\beta-1})} = \frac{p^\beta}{p^{\beta-1}} = p,$$

where we used theorem 2.3.11. Since $y \in P \leq G$, G has an element of order p.

Note the logical structure: the abelian case of Cauchy's Theorem (corollary 3.3.9) was used *in the proof of Sylow I*, and the full Cauchy's Theorem is now derived *from* Sylow I. There is no circular reasoning.

Example 4.8.8
Let $G \neq 1$ be a finite abelian group whose only normal subgroups are 1 and G. Then $G \cong Z_p$ for a prime p.

***Proof*:**
Since $|G| > 1$, some prime p divides $|G|$, and theorem 4.8.7 gives an element $x \in G$ of order p. The subgroup $\langle x \rangle$ has order p (proposition 2.3.4) and is normal by corollary 3.1.12, so $\langle x \rangle = G$. Thus G is cyclic of order p, and $G \cong Z_p$ by theorem 2.3.9, as claimed.

Consequences

The following corollary collects the most frequently used structural consequences.

Corollary 4.8.9: Characterizations of a Unique Sylow Subgroup

Let $P \in \mathrm{Syl}_p(G)$. The following are equivalent:

1. $n_p = 1$ (i.e. P is the unique Sylow p-subgroup of G).
2. $P \trianglelefteq G$.
3. $P \operatorname{char} G$.

***Proof*:**
Item 1 $\Rightarrow$ item 3: If P is the unique subgroup of G of order p^α, then P is characteristic by item 2 of proposition 4.7.13.

Item 3 $\Rightarrow$ item 2: Characteristic implies normal (item 1 of proposition 4.7.13).

Item 2 $\Rightarrow$ item 1: If $P \trianglelefteq G$ and Q is any other Sylow p-subgroup, then by Sylow II, $Q = gPg^{-1}$ for some $g \in G$. Since P is normal, $gPg^{-1} = P$, so $Q = P$. Thus $n_p = 1$.

In particular, to show that a Sylow subgroup is normal, it suffices to show $n_p = 1$. The congruence and divisibility conditions from Sylow III often force this conclusion.

Example 4.8.10: Using Sylow's Theorems

1. Let $|G| = 15 = 3 \cdot 5$. Then $n_3 \mid 5$ and $n_3 \equiv 1 \pmod 3$, giving $n_3 \in \{1\}$. Similarly, $n_5 \mid 3$ and $n_5 \equiv 1 \pmod 5$, giving $n_5 \in \{1\}$. Both Sylow subgroups are normal and unique, each cyclic of prime order.
2. Let $|G| = 12 = 2^2 \cdot 3$. Then $n_3 \mid 4$ and $n_3 \equiv 1 \pmod 3$, giving $n_3 \in \{1, 4\}$. Also, $n_2 \mid 3$ and $n_2 \equiv 1 \pmod 2$, giving $n_2 \in \{1, 3\}$. Both possibilities genuinely occur: for A_4, $n_3 = 4$ and $n_2 = 1$; for $\mathbb{Z}/12\mathbb{Z}$, $n_3 = 1$ and $n_2 = 1$.
3. Let $|G| = 99 = 9 \cdot 11$. Then $n_{11} \mid 9$ and $n_{11} \equiv 1 \pmod{11}$. The divisors of 9 are $1, 3, 9$, and only $1 \equiv 1 \pmod{11}$. So $n_{11} = 1$ and the Sylow 11-subgroup is normal.

4.8.11 A Strategy for Sylow Problems Many problems in finite group theory reduce to the following systematic procedure:

1. Write $|G| = p^\alpha m$ with $p \nmid m$ for each prime p dividing $|G|$.
2. For each p, list the candidates for n_p: they must simultaneously divide m and be congruent to $1 \pmod{p}$.
3. Use the candidates to deduce structural information: if $n_p = 1$, the Sylow p-subgroup is normal; if $n_p > 1$, count the elements of order p^k across all Sylow subgroups and check for contradictions.

We will apply this strategy systematically in Section 4.9.

4.8.12 Applied Aside: Noether's Theorem in Physics While Sylow's Theorems concern finite groups, the underlying philosophy (that symmetries constrain structure) extends far beyond algebra. In 1918, Emmy Noether proved that every continuous symmetry of a physical system corresponds to a conserved quantity:

Symmetry (group action)	*Conservation law*
Time translation	Energy
Spatial translation	Momentum
Rotational symmetry	Angular momentum

Noether's Theorem uses *Lie groups* (continuous groups acting smoothly on manifolds), but the conceptual root is identical to everything in this chapter: a group acts on a space, and the structure of the action (its orbits, its stabilizers, its kernel) reveals deep invariants. The conservation laws of physics are, in a precise sense, consequences of group actions.

Exercise 4.8.1

1. Let p be prime, P a p-group, and $N \trianglelefteq G$.
   a) Prove that if $N \neq \{e\}$, then $N \cap Z(P) \neq \{e\}$
   b) Prove that for all $i \geq 0$ where $p^i \big| |N|$, then N contains a subgroup of order p^i that is normal in P. Show these groups can form a central series.
   c) Let G be any finite group. Show that for any integer $i \geq 0$, if $p^i \big| G$, then there exists a subgroup $H \leqslant G$ where $|H| = p^i$. By example 3.3.8, this is the strongest converse to Lagrange's Theorem (theorem 3.3.1).

4.9 Applications of Sylow's Theorems

We now put the Sylow machinery to work. The goal is to demonstrate, through a sequence of increasingly sophisticated examples, how the existence, conjugacy, and counting theorems combine to

constrain, and sometimes completely determine, the structure of a finite group from its order alone.

Groups of Order pq

Let $p < q$ be distinct primes and let $|G| = pq$. This is the simplest case beyond prime and prime-squared orders, and Sylow's Theorems give a nearly complete classification.

Theorem 4.9.1: Classification of Groups of Order pq

Let $p < q$ be primes and $|G| = pq$.

1. G has a unique (hence normal) Sylow q-subgroup.
2. If $p \nmid (q-1)$, then G is cyclic: $G \cong \mathbb{Z}/pq\mathbb{Z}$.
3. If $p \mid (q-1)$ and G is not cyclic, then G is non-abelian and $n_p = q$. For $p = 2$ there is, up to isomorphism, exactly one non-abelian group of order $2q$, the dihedral group D_q (definition 1.2.28).

***Proof*:**

1. By Sylow III, $n_q \mid p$ and $n_q \equiv 1 \pmod{q}$. The divisors of p are 1 and p. Since $p < q$, we have $p \not\equiv 1 \pmod{q}$ (as $1 < p < q$). Therefore $n_q = 1$, and the unique Sylow q-subgroup Q is normal in G (corollary 4.8.9).

2. By Sylow III, $n_p \mid q$ and $n_p \equiv 1 \pmod{p}$. Since q is prime, $n_p \in \{1, q\}$. If $n_p = q$, then $q \equiv 1 \pmod{p}$, i.e. $p \mid (q-1)$. Contrapositively, if $p \nmid (q-1)$, then $n_p = 1$, and the Sylow p-subgroup P is also normal.

   Now $P \cong \mathbb{Z}/p\mathbb{Z}$ and $Q \cong \mathbb{Z}/q\mathbb{Z}$ (both have prime order, hence are cyclic by corollary 3.3.2). Since $P \cap Q$ is a subgroup of both P and Q, its order divides $\gcd(p, q) = 1$, so $P \cap Q = \{e\}$. By proposition 3.4.3, $|PQ| = |P||Q|/|P \cap Q| = pq = |G|$, so $PQ = G$.

   We claim G is abelian. For any $x \in P$ and $y \in Q$, the commutator $xyx^{-1}y^{-1}$ lies in Q (since $Q \trianglelefteq G$ gives $xyx^{-1} \in Q$, so $xyx^{-1}y^{-1} \in Q$) and also in P (since $P \trianglelefteq G$ gives $yx^{-1}y^{-1} \in P$, so $xyx^{-1}y^{-1} \in P$). Thus $xyx^{-1}y^{-1} \in P \cap Q = \{e\}$, giving $xy = yx$.

   Since every element of $G = PQ$ is a product of an element of P and an element of Q, and these all commute, G is abelian. Let x generate P and y generate Q. Then $|xy| = \operatorname{lcm}(p, q) = pq$ (since $\gcd(p, q) = 1$), so $G = \langle xy \rangle \cong \mathbb{Z}/pq\mathbb{Z}$.

3. Suppose $p \mid (q-1)$. If G is abelian, then P and Q are both normal, and the argument of (2) shows $G \cong \mathbb{Z}/pq\mathbb{Z}$. So if G is not cyclic, it is non-abelian, the same argument shows that P is not normal, and $n_p = q$ by the count in (2). For $p = 2$ a non-abelian group of order $2q$ exists, the dihedral group D_q, of order $2q$ (proposition 1.2.30) and non-abelian (proposition 1.2.29(5)), with $D_3 = S_3$ for $q = 3$.

   For $p = 2$ the non-abelian group is unique up to isomorphism. Let G be non-abelian of order $2q$, let $Q = \langle y \rangle$ be its normal Sylow q-subgroup from (1), and let $x \in G$ have order 2 (theorem 4.8.7). Then $xyx^{-1} \in Q$, say $xyx^{-1} = y^s$, and

$$y = x^2yx^{-2} = xy^sx^{-1} = y^{s^2}$$

so q divides $s^2 - 1 = (s-1)(s+1)$, and since q is prime it divides $s-1$ or $s+1$. If $q \mid s-1$, then x commutes with y, and $G = \langle x, y\rangle$ (its order is divisible by 2 and by q) would be abelian. Hence $xyx^{-1} = y^{-1}$, and $xy^i = y^{-i}x$ for every i. Since $\langle x\rangle \cap Q = 1$, the $2q$ elements $y^i x^j$ with $0 \le i < q$ and $0 \le j < 2$ are distinct, so they are all of G, and

$$(y^i x^j)(y^k x^l) = y^{i+(-1)^j k} x^{j+l}$$

determines every product. Two non-abelian groups of order $2q$ therefore have the same multiplication in these coordinates, and $y^i x^j \mapsto y'^i x'^j$ is an isomorphism between them.

For odd p with $p \mid q-1$ the same classification holds: a non-abelian group of order pq exists (corollary 5.3.5, using semi-direct products) and is unique up to isomorphism (corollary 11.3.16, using the cyclicity of $(\mathbb{Z}/q\mathbb{Z})^\times$).

Example 4.9.2: Concrete Cases

1. $|G| = 15 = 3 \cdot 5$. Here $p = 3, q = 5$, and $3 \nmid 4$. So $G \cong \mathbb{Z}/15\mathbb{Z}$: there is only one group of order 15.
2. $|G| = 35 = 5 \cdot 7$. Here $p = 5, q = 7$, and $5 \nmid 6$. So $G \cong \mathbb{Z}/35\mathbb{Z}$.
3. $|G| = 6 = 2 \cdot 3$. Here $p = 2, q = 3$, and $2 \mid 2$. There are two groups: $\mathbb{Z}/6\mathbb{Z}$ and the non-abelian group S_3.
4. $|G| = 21 = 3 \cdot 7$. Here $p = 3, q = 7$, and $3 \mid 6$. There are two groups: $\mathbb{Z}/21\mathbb{Z}$ and a non-abelian group of order 21 (corollaries 5.3.5 and 11.3.16).

Groups of Order p^2q: A Worked Example

We illustrate the general strategy for $|G| = p^2q$ ($p \neq q$ primes) through the concrete case $|G| = 12 = 2^2 \cdot 3$.

Example 4.9.3: Sylow Analysis of Groups of Order 12

Let $|G| = 12$. The Sylow constraints give:

$$n_3 \mid 4 \text{ and } n_3 \equiv 1 \pmod 3 \implies n_3 \in \{1, 4\},$$
$$n_2 \mid 3 \text{ and } n_2 \equiv 1 \pmod 2 \implies n_2 \in \{1, 3\}.$$

Case $n_3 = 4$. There are 4 Sylow 3-subgroups, each cyclic of order 3 with 2 non-identity elements. Since distinct Sylow 3-subgroups intersect trivially (their intersection has order dividing 3 and is a proper subgroup of each, so it is $\{e\}$), there are $4 \times 2 = 8$ elements of order 3. The remaining $12 - 8 = 4$ elements (including e) must form the unique Sylow 2-subgroup. Thus $n_2 = 1$ and the Sylow 2-subgroup P is normal.

Since P has order 4, $P \cong \mathbb{Z}/4\mathbb{Z}$ or $P \cong V_4 \cong \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z}$ (corollary 4.6.6). The group A_4 is an example of this case, with $P \cong V_4$ and $n_3 = 4$.

Case $n_3 = 1$. The unique Sylow 3-subgroup $Q \cong \mathbb{Z}/3\mathbb{Z}$ is normal. The Sylow 2-subgroup P (order 4) acts on Q by conjugation, giving a homomorphism $P \to \mathrm{Aut}(Q) \cong \mathbb{Z}/2\mathbb{Z}$ (by theorem 4.7.6).

The structure of G depends on this homomorphism: different choices yield the cyclic group $\mathbb{Z}/12\mathbb{Z}$, the dihedral group D_6, and the dicyclic group Dic_3 (among others, depending on whether $P \cong V_4$ or $P \cong \mathbb{Z}/4\mathbb{Z}$).

The key technique on display is *element counting*: when n_p is large, the Sylow p-subgroups account for many elements, leaving fewer elements for Sylow subgroups at other primes. This often forces $n_q = 1$ at a different prime, yielding a normal subgroup.

The same strategy applies to any order p^2q. In general:

1. Compute the Sylow constraints for n_p and n_q.
2. If both $n_p = 1$ and $n_q = 1$ are forced, both Sylow subgroups are normal, and G is a semi-direct product (or direct product) of a p-group and a q-group.
3. If $n_q > 1$ is possible, use element counting to check whether $n_p = 1$ is forced. If so, the normal Sylow p-subgroup provides structural leverage.
4. The full classification typically requires the semi-direct product machinery of chapter 5.

4.9.1 Simplicity of A_5

The alternating group A_5 is simple. Through Galois theory, this is the group-theoretic reason that the general quintic equation cannot be solved by radicals.

Lemma 4.9.4: Splitting Of Conjugacy Classes In A_n

Let $n \geq 2$, let $\sigma \in A_n$, and let K be the conjugacy class of σ in S_n.

1. If $C_{S_n}(\sigma)$ contains an odd permutation, then K is the conjugacy class of σ in A_n.
2. If every element of $C_{S_n}(\sigma)$ is even, then K is the union of two conjugacy classes of A_n, each of size $|K|/2$, namely the classes of σ and of $\tau\sigma\tau^{-1}$ for any odd $\tau \in S_n$.

***Proof*:**
Write $C = C_{S_n}(\sigma)$, and write $\mathrm{cl}_{A_n}(\sigma)$ for the conjugacy class of σ in A_n. By theorem 1.2.20(2), $\mathrm{sgn}(\pi^{-1}) = \mathrm{sgn}(\pi)^{-1}$, so $\mathrm{sgn}(\pi\rho\pi^{-1}) = \mathrm{sgn}(\rho)$ for all $\pi, \rho \in S_n$. In particular $K \subseteq A_n$ and $\mathrm{cl}_{A_n}(\sigma) \subseteq K$. The centralizer of σ in A_n is $C \cap A_n$, and $|A_n| = n!/2$ by example 3.5.2(1). By (4.3), applied in S_n and in A_n, and theorem 3.3.1,

$$|K| = \frac{n!}{|C|} \qquad |\,\mathrm{cl}_{A_n}(\sigma)| = \frac{n!}{2\,|C \cap A_n|}$$

1. Let $\tau \in C$ be odd. If $x \in C$, then $\tau x \in C$, since $\tau x\sigma = \tau\sigma x = \sigma\tau x$, and $\mathrm{sgn}(\tau x) = -\mathrm{sgn}(x)$. So $x \mapsto \tau x$ maps the even elements of C to the odd ones, and $y \mapsto \tau^{-1}y$ maps the odd ones back, because τ^{-1} also commutes with σ. Hence exactly half of the elements of C are even, $|C \cap A_n| = |C|/2$, and $|\,\mathrm{cl}_{A_n}(\sigma)| = n!/|C| = |K|$. Since $\mathrm{cl}_{A_n}(\sigma) \subseteq K$ and both sets are finite, $\mathrm{cl}_{A_n}(\sigma) = K$.
2. Now $C \cap A_n = C$, so $|\,\mathrm{cl}_{A_n}(\sigma)| = |K|/2$. Let $\tau \in S_n$ be odd, for instance $\tau = (1\ 2)$, and put $\sigma' = \tau\sigma\tau^{-1} \in K$. An element $x \in S_n$ commutes with σ' exactly when $\tau^{-1}x\tau$ commutes

with σ, so $C_{S_n}(\sigma') = \tau C \tau^{-1}$, whose elements are even. The same count, applied to σ', whose conjugacy class in S_n is also K, gives $|\operatorname{cl}_{A_n}(\sigma')| = |K|/2$. If $\sigma' = \alpha\sigma\alpha^{-1}$ with $\alpha \in A_n$, then $\tau\sigma\tau^{-1} = \alpha\sigma\alpha^{-1}$, so $\alpha^{-1}\tau \in C$, which is impossible because $\operatorname{sgn}(\alpha^{-1}\tau) = -1$. So the classes of σ and σ' in A_n are distinct, hence disjoint, since conjugacy classes partition A_n. Both lie in K, and together they have $|K|/2 + |K|/2 = |K|$ elements, so their union is K, as claimed.

Lemma 4.9.5: Conjugacy Classes of A_5

The group A_5 has five conjugacy classes, with sizes 1, 12, 12, 15, 20.

***Proof*:**
By theorem 1.2.18 and theorem 1.2.20(4), a permutation whose disjoint cycles have lengths $m_1, \ldots, m_r$ has sign $(-1)^{(m_1-1)+\cdots+(m_r-1)}$. Of the seven cycle types in S_5, the four even ones are:

Cycle type	*Example*	*Count in A_5*
(1^5)	e	1
$(3, 1^2)$	(1 2 3)	$\binom{5}{3} \cdot 2 = 20$
$(2^2, 1)$	(1 2)(3 4)	$\frac{1}{2}\binom{5}{2}\binom{3}{2} = 15$
(5)	(1 2 3 4 5)	$5!/5 = 24$

Total: $1 + 20 + 15 + 24 = 60 = |A_5|$.

In S_5, permutations of the same cycle type form a single conjugacy class (theorem 4.6.11), and lemma 4.9.4 decides whether such a class is one class of A_5 or two.

- 3-*cycles:* $C_{S_5}((1\ 2\ 3))$ contains the odd permutation (4 5), which is disjoint from (1 2 3). One A_5-class of size 20.
- $(2^2, 1)$-*type:* $C_{S_5}((1\ 2)(3\ 4))$ contains the odd permutation (1 2). One A_5-class of size 15.
- 5-*cycles:* let $\sigma = (1\ 2\ 3\ 4\ 5)$. Its class in S_5 consists of the 24 five-cycles, so $|C_{S_5}(\sigma)| = 120/24 = 5$ by (4.3). The subgroup $\langle\sigma\rangle$ has order 5 (proposition 1.2.24) and commutes with σ, so $C_{S_5}(\sigma) = \langle\sigma\rangle$, whose elements are powers of the even permutation σ and hence even. The class splits into two A_5-classes of size $24/2 = 12$, represented by σ and by $(4\ 5)\sigma(4\ 5)^{-1} = (1\ 2\ 3\ 5\ 4)$ (proposition 1.2.27).

The five class sizes are therefore $1, 12, 12, 15, 20$, as claimed.

Theorem 4.9.6: A_5 is Simple

The alternating group A_5 has no nontrivial proper normal subgroups.

***Proof*:**
Suppose $N \trianglelefteq A_5$ with $N \neq \{e\}$. Since N is normal, it is a union of conjugacy classes and must include $\{e\}$. The class sizes are $1, 12, 12, 15, 20$. Since $|N|$ divides $|A_5| = 60$ (theorem 3.3.1), we check all possible unions:

Sum including 1	*Divides* 60*?*
$1 + 12 = 13$	No
$1 + 15 = 16$	No
$1 + 20 = 21$	No
$1 + 12 + 12 = 25$	No
$1 + 12 + 15 = 28$	No
$1 + 12 + 20 = 33$	No
$1 + 15 + 20 = 36$	No
$1 + 12 + 12 + 15 = 40$	No
$1 + 12 + 12 + 20 = 45$	No
$1 + 12 + 15 + 20 = 48$	No
$1 + 12 + 12 + 15 + 20 = 60$	Yes (all of A_5)

No proper nontrivial union of conjugacy classes (including $\{e\}$) has order dividing 60. Therefore $N = \{e\}$ or $N = A_5$, and A_5 is simple.

4.9.7 Remark: The Quintic and Simplicity The simplicity of A_5 is the key obstruction in Galois's proof that there is no formula (using radicals) for the roots of a general polynomial of degree ≥ 5. The rough idea: the "solvability" of a polynomial equation by radicals corresponds to a property of its Galois group called *solvability* (which we will define in Section 6.1.1), and A_5 is the smallest non-solvable group. The chain of normal subgroups required by solvability cannot exist in a simple group with more than one element. Since A_5 arises as the Galois group of certain quintic polynomials, those polynomials are not solvable by radicals.

Exercise 4.9.1

1. Let $|G| = pqr$ where $p < q < r$ are distinct primes. Show that G has a normal Sylow subgroup for at least one of the primes p, q, r.

   Hint: Apply Sylow III to all three primes. If $n_r > 1$ and $n_q > 1$, count the elements of orders r and q (they contribute $(n_r)(r-1) + (n_q)(q-1)$ non-identity elements from distinct cyclic subgroups). Show that if all three $n_p, n_q, n_r > 1$, the total exceeds pqr.

2. Let $|G| = 30 = 2 \cdot 3 \cdot 5$.

   1. Show that $n_5 \in \{1, 6\}$ and $n_3 \in \{1, 10\}$.
   2. Using exercise 4.9.1 (1), conclude that G has a normal Sylow 5-subgroup or a normal Sylow 3-subgroup (or both).
   3. Deduce that G has a normal subgroup of order 15.

Hint: If $Q \trianglelefteq G$ is a Sylow 5-subgroup, consider G/Q and use the classification of groups of order 6 (theorem 4.9.1). If the Sylow 3-subgroup R is also normal, argue using $|QR| = 15$.

3. Let $|G| = 36 = 2^2 \cdot 3^2$.

   1. Show that $n_3 \in \{1, 4\}$.
   2. If $n_3 = 4$, show that the action of G on $\mathrm{Syl}_3(G)$ by conjugation gives a homomorphism $\pi\colon G \to S_4$. Conclude that $\ker(\pi)$ is a nontrivial normal subgroup of G.
      Hint: $|G| = 36 > 24 = |S_4|$, so π cannot be injective.

   Deduce that every group of order 36 has a nontrivial proper normal subgroup (and hence is not simple).

4. Show that the only simple group of order 60 is A_5 (up to isomorphism).

   Hint: Let G be simple of order 60. Show $n_5 = 6$, giving $[G : N_G(P)] = 6$ for $P \in \mathrm{Syl}_5(G)$. The action of G on the 6 cosets of $N_G(P)$ gives an injective homomorphism $G \hookrightarrow S_6$. Argue that the image lies in A_6, and identify it with A_5.

5. Let p be an odd prime. Show that every Sylow p-subgroup of D_n is cyclic and normal.

   Hint: The cyclic subgroup $\langle r \rangle \trianglelefteq D_n$ has index 2.

4.10 Summary

This chapter developed the theory of group actions from first principles and applied it to obtain structural results about finite groups. We collect the main threads here for reference.

The Core Framework

A *group action* of G on a set X is a homomorphism $\rho\colon G \to \mathrm{Sym}(X)$ (definition 4.1.1), equivalently a map $G \times X \to X$ satisfying the compatibility and identity axioms (theorem 4.1.2). Every action decomposes X into *orbits* (definition 4.2.1), and the size of each orbit is governed by the *stabilizer* via the Orbit-Stabilizer Theorem (theorem 4.3.1):

$$|G \cdot x| = [G : G_x].$$

The number of orbits can be computed by Burnside's Lemma (theorem 4.3.7): $|X/G| = \frac{1}{|G|} \sum_{g \in G} |X^g|$.

Types of Actions

Type	*Defining condition*	*Consequence*
Faithful	$\ker(\rho) = \{e\}$	$G \hookrightarrow \mathrm{Sym}(X)$
Transitive	One orbit: $G \cdot x = X$	$X \cong_G G/G_{x_0}$ for any x_0
Free	All stabilizers trivial: $G_x = \{e\}$	Every orbit has size $\lvert G\rvert$
Regular	Free + Transitive	$X \cong_G G$ (left multiplication)

The Key Self-Actions

The most powerful applications came from letting G act on itself or on structures derived from itself. The following table summarizes the three principal self-actions and their consequences.

Action	*Set X*	*Orbit of x*	*Stabilizer G_x*	*Kernel*	*Key result*
Left mult. $g \cdot a = ga$	G	G (one orbit)	$\{e\}$	$\{e\}$	Cayley's Thm
Conjugation $g \cdot a = gag^{-1}$	G	$\mathrm{cl}(a)$	$C_G(a)$	$Z(G)$	Class Equation
Coset action $g \cdot aH = gaH$	G/H	G/H (one orbit)	H (at eH)	$\bigcap_g gHg^{-1}$	Index-p Thm

Two further actions played essential roles:

- *Conjugation on subgroups* ($g \cdot S = gSg^{-1}$): the stabilizer is the normalizer $N_G(S)$, and the number of conjugates of S is $[G : N_G(S)]$ (corollary 4.6.9).
- *Conjugation on Sylow subgroups*: transitivity (Sylow II) gives $n_p = [G : N_G(P)]$, and the Fixed-Point Congruence (lemma 4.8.4) gives $n_p \equiv 1 \pmod{p}$.

The Major Theorems

1. *Orbit-Stabilizer Theorem* (theorem 4.3.1): $|G \cdot x| = [G : G_x]$.
2. *Burnside's Lemma* (theorem 4.3.7): $|X/G| = \frac{1}{|G|} \sum_g |X^g|$.
3. *Cayley's Theorem* (theorem 4.5.3): Every group embeds into a symmetric group.
4. *The Class Equation* (theorem 4.6.3): $|G| = |Z(G)| + \sum [G : C_G(g_i)]$.
5. *p-Groups have nontrivial center* (theorem 4.6.5).
6. $G/Z(G) \cong \mathrm{Inn}(G)$ (theorem 4.7.4).
7. *The N/C Theorem* (theorem 4.7.6): $N_G(H)/C_G(H) \hookrightarrow \mathrm{Aut}(H)$.
8. *Sylow's Theorems* (theorem 4.8.6): Existence, conjugacy, and counting of Sylow p-subgroups.
9. *Cauchy's Theorem* (theorem 4.8.7): If $p \big| |G|$, then G has an element of order p.

Looking Ahead

The idea that a group *acts* on something, and that the structure of the action reveals the structure of the group, is not a technique that ends with this chapter. In the chapters ahead, group actions will reappear in new forms:

- In the study of *semi-direct products* (chapter 5), the N/C Theorem and the conjugation action will be the key ingredients for constructing new groups from old ones.
- In *Galois theory*, a Galois group acts on the roots of a polynomial and on intermediate field extensions. The Fundamental Theorem of Galois Theory is, at its core, a correspondence between subgroups (stabilizers) and orbits (field extensions).
- In *module theory* (Part III), the group action framework generalizes to rings acting on abelian groups. The single condition "ρ is a homomorphism" will become the defining property of a module.

The unifying philosophy of this chapter bears repeating one last time:

> *Groups are not static objects. They are agents of symmetry, and the way to understand them is to watch how they act: on sets, on themselves, and on each other.*

4.11⋆ Group Actions in Advanced Mathematics

⋆ *Optional. This section is an aside; nothing later in the book depends on it.*

This section is addressed to the mathematically curious reader who wishes to see where the ideas of this chapter lead. No proofs are given, and nothing here is prerequisite for the rest of the book.

The theory of group actions developed in this chapter (homomorphisms to symmetric groups, orbits, stabilizers, counting) is the finite, discrete case of a theme that pervades nearly every branch of modern mathematics. In each new setting, the pattern is the same: a group acts on a structured object, and the interplay between the action and the structure produces deep theorems. We sketch three such settings.

4.11.1 Representation Theory

In this chapter, a group action was a homomorphism $\rho\colon G \to \mathrm{Sym}(X)$, where X was only a *set*. What happens if we upgrade X to a *vector space*?

A *(linear) representation* of a group G is a homomorphism

$$\rho\colon G \to GL(V),$$

where V is a vector space over a field $\mathbb{F}$ and $GL(V)$ is the group of invertible linear maps $V \to V$. Each group element acts on V not as a bijection alone, but as an *invertible linear transformation*: it respects addition and scalar multiplication.

Every group action $G \curvearrowright X$ on a finite set gives rise to a representation in a canonical way. Let $V = \mathbb{F}^X$ be the vector space with basis $\{e_x : x \in X\}$, one basis vector per element of X. Then G acts on V by permuting the basis: $g \cdot e_x = e_{g\cdot x}$. This is the *permutation representation* in the linear sense, and it converts our set-theoretic theory into linear algebra.

The power of representation theory lies in the tools of linear algebra that become available: eigenvalues, traces, direct-sum decompositions. The *character* of a representation is the function $\chi\colon G \to \mathbb{F}$ defined by $\chi(g) = \mathrm{tr}(\rho(g))$. Characters satisfy remarkable orthogonality relations, and for finite groups over $\mathbb{C}$, the irreducible characters form a basis for the space of class functions (functions constant on conjugacy classes). The number of irreducible representations equals the number of conjugacy classes, a striking connection to the Class Equation of Section 4.6.

Two landmark results illustrate the depth of the theory:

- *Maschke's Theorem (theorem 53.1.9):* If $\mathrm{char}(\mathbb{F}) \nmid |G|$, then every representation decomposes as a direct sum of irreducible representations. This is the analogue of diagonalizability for group actions.
- *Burnside's p^aq^b Theorem (theorem 53.2.24):* Every group of order p^aq^b (two prime factors) is solvable. Remarkably, the only known proof for over a century used *representation theory*, not pure group theory: a vivid demonstration that "linearizing" group actions can unlock results inaccessible by other means. (A purely group-theoretic proof was found by Thompson and others only much later.)

4.11.2 Algebraic Topology

Group actions enter topology through the theory of *covering spaces*.

Let X be a topological space and $\widetilde{X} \to X$ a covering map. The *deck transformations* (or covering transformations) are the homeomorphisms $\varphi\colon \widetilde{X} \to \widetilde{X}$ that commute with the projection to X. These form a group $\mathrm{Deck}(\widetilde{X}/X)$ that acts on $\widetilde{X}$ by homeomorphisms. When the covering is *normal* (or *regular*, note the terminology!), the deck group acts *freely and transitively* on each fiber. This is precisely a regular action in the sense of definition 4.4.12, and the base space is recovered as the orbit space:

$$X \;\cong\; \widetilde{X} \,/\, \mathrm{Deck}(\widetilde{X}/X).$$

The fundamental group $\pi_1(X, x_0)$ acts on the fiber $p^{-1}(x_0)$ by *monodromy*: lifting a loop in X to a path in $\widetilde{X}$ and tracking where the endpoint lands. This action encodes the topology of the covering:

- The *orbits* of the monodromy action correspond to the connected components of $\widetilde{X}$ (if the covering is connected, there is one orbit: the action is transitive).
- The *stabilizer* of a point in the fiber corresponds to the image of $\pi_1(\widetilde{X})$ in $\pi_1(X)$, the "surviving" loops.
- The *orbit-stabilizer correspondence* becomes the classical bijection between connected coverings of X (up to isomorphism) and conjugacy classes of subgroups of $\pi_1(X)$, a topological analogue of the Structure Theorem for Transitive Actions (theorem 4.4.6).

More broadly, whenever a group G acts on a topological space X, one can study *equivariant topology*: homology and cohomology theories that respect the action. The *equivariant cohomology* $H^*_G(X)$ combines the topology of X with the algebra of G, and its computation often reduces to understanding the fixed points and stabilizers of the action, exactly the tools developed in this chapter.

4.11.3 Category Theory

Category theory provides the most general and conceptually clean framework for understanding group actions.

A group G can be viewed as a category $\mathbf{B}G$ with a single object $*$ and one morphism $* \to *$ for each element of G, with composition given by the group operation. (The invertibility of morphisms makes $\mathbf{B}G$ a *groupoid*, a category in which every morphism is an isomorphism.)

From this viewpoint:

Algebraic concept	*Categorical translation*	*Target category*
Group action on a set	Functor $\mathbf{B}G \to \mathbf{Set}$	Sets and functions
Linear representation	Functor $\mathbf{B}G \to \mathbf{Vect}_{\mathbb{F}}$	Vector spaces
Module over a group ring	Functor $\mathbf{B}G \to \mathbf{Ab}$	Abelian groups
Topological G-space	Functor $\mathbf{B}G \to \mathbf{Top}$	Topological spaces

In each row, the pattern from definition 4.1.1 is visible: a group action is a homomorphism into the automorphism group of some object. The categorical perspective replaces "automorphism group" with "endomorphism monoid" and "homomorphism" with "functor," but the essential idea is identical.

The collection of all G-sets itself forms a category, denoted G-**Set**, whose morphisms are the G-equivariant maps (definition 4.4.5). The Structure Theorem for Transitive Actions (theorem 4.4.6) becomes the statement that every transitive G-set is isomorphic to a coset space G/H in this category. Burnside's Lemma can be reinterpreted as a statement about the *colimit* of the functor $\mathbf{B}G \to \mathbf{Set}$.

Perhaps most strikingly, the passage from group actions to module theory, the subject of much of Part III, is simply the passage from functors into **Set** to functors into **Ab**. The group ring $\mathbb{Z}[G]$ arises as the *free abelian group* on the morphisms of $\mathbf{B}G$, and a $\mathbb{Z}[G]$-module is exactly a functor $\mathbf{B}G \to \mathbf{Ab}$. In this way, the entire theory of modules over group rings (and by extension, much of representation theory) is a natural continuation of the ideas introduced in this chapter.

A group action is a functor from a one-object groupoid.
Change the target category, and the whole of algebra unfolds.

5

Building Groups: Direct and Semi-Direct Products

A group G with a normal subgroup H and $G/H \cong K$ is an extension of H by K (definition 3.6.3), and a composition series (section 3.7) assembles every finite group from simple groups by repeated extensions. The groups H and K alone do not determine G: both D_4 and $C_4 \times C_2$ are extensions of C_4 by C_2 (example 3.6.1). This chapter studies two constructions that produce an extension from given data. The *direct product* $H \times K$ is built from H and K alone, and the *semi-direct product* $H \rtimes K$ from H, K and an action of K on H by automorphisms. Inside a group G, the direct product appears when $G = HK$ for normal subgroups H and K with $H \cap K = 1$, and the semi-direct product when only H is required to be normal. Every extension of H by K is isomorphic to a subgroup of a single group built from H and K, the complete wreath product, by a theorem of Kaloujnine and Krasner [86, Exercises 11.1, no. 12]. This book does not develop wreath products.

5.1 Classical Definitions And Properties

You might recall example 1.1.5(4), we showed we can create a group-structure given two groups. We revisit this definition here in generality:

Definition 5.1.1: Direct Product

The *direct product* of $G_1 \times G_2 \times \cdots$ of groups $G_1, ..., G_n, ...$ with the operations $*_1, ..., *_n, ...$ respectively is the set of sequences $(g_1, ..., g_n, ...)$ (or n-tuples if the number of groups is finite) where $g_9 \in G_i$ with the operation defined componentwise:

$$(g_1, ..., g_n, ...) * (h_1, ..., h_n, ...) = (g_1 *_1 h_1, ..., g_n *_n h_n, ...)$$

Sometimes, the direct product is called the *external direct product* to differentiate it from the *internal direct product* (see definition 3.4.1)

Example 5.1.2

1. Think of $\mathbb{R}^2 = \mathbb{R} \times \mathbb{R}$ with component-wise addition: $(\mathbb{R} \times \mathbb{R}, (+, +))$ or $(\mathbb{R}^2, (+, +))$.
2. The groups can also be arbitrary. Let $G_1 = \mathbb{Z}$, $G_2 = S_3$ and $G_3 = GL_2(\mathbb{R})$. Then $G_1 \times G_2 \times G_3$ with the operation defined component wise is indeed a group

For the direct product, there are a few general properties you can prove as an exercise:

Proposition 5.1.3: properties of Direct Products

Let every G_i be a group.

1. $|\prod_i G_i| = \prod_i |G_i|$
2. For each fixed i, the set of elements of G which have the identity of G_j in the jth position for all $j \neq i$ and arbitrary elements of G_i in position i is a subgroup of G isomorphic to G_i:
$$G_i \cong (1_{g_1}, ..., g_i, 1_{g_{i+1}}, ...)$$
3. For each fixed i, define $\pi_i : G \to G_i$ by
$$\pi_i((g_1, ..., g_n)) = g_i$$
then π_i is a surjective homomorphsim with
$$\begin{aligned}\ker(\pi_i) &= \{(g_1, ..., g_{i-1}, 1, g_{i+1}, ..., g_n) | g_j \in G_j \text{ for all } j \neq i\} \\ &\cong G_1 \times \cdots \times G_{i-1} \times G_{i+1} \times \cdots \times G_n\end{aligned}$$
4. Under the identifications in part (2), if $x \in G_i$ and $y \in G_j$ for some $i \neq j$, then $xy = yx$

***Proof*:**
Throughout, write $G = \prod_i G_i$, whose elements are the tuples $(g_1, ..., g_n, ...)$ with $g_i \in G_i$ and whose operation is componentwise. Note that G is a group: the tuple $(1_{G_1}, ..., 1_{G_n}, ...)$ is a two-sided identity, the componentwise inverse $(g_1^{-1}, ..., g_n^{-1}, ...)$ is a two-sided inverse, and associativity holds in each component.

1. As a set, G is the Cartesian product of the underlying sets of the G_i: an element of G is

exactly a choice of one element of G_i for each i. Hence $|\prod_i G_i| = \prod_i |G_i|$.

2. Fix i and let $H_i \subseteq G$ be the described set. Define $\iota_i : G_i \to G$ by letting $\iota_i(g)$ be the tuple with g in position i and 1_{G_j} in every position $j \neq i$. Since the operation of G is componentwise and $1_{G_j}1_{G_j} = 1_{G_j}$, we get $\iota_i(g)\iota_i(h) = \iota_i(gh)$, so ι_i is a homomorphism. Its image is exactly H_i, which is therefore closed under products and, since $\iota_i(g)^{-1} = \iota_i(g^{-1})$, under inverses. As H_i also contains the identity, $H_i \leqslant G$. Finally, ι_i is injective, for if $\iota_i(g) = \iota_i(h)$ then comparing position i gives $g = h$. Hence ι_i restricts to an isomorphism $G_i \cong H_i$.

3. For tuples $g = (g_1, ..., g_n, ...)$ and $h = (h_1, ..., h_n, ...)$, the componentwise operation gives $\pi_i(gh) = g_ih_i = \pi_i(g)\pi_i(h)$, so π_i is a homomorphism. It is surjective since $\pi_i(\iota_i(g)) = g$ for every $g \in G_i$. A tuple lies in $\ker(\pi_i)$ if and only if its ith position is 1_{G_i}, which is exactly the displayed set. The map sending such a tuple to the tuple obtained by deleting position i is a bijection onto $G_1 \times \cdots \times G_{i-1} \times G_{i+1} \times \cdots$, and it is a homomorphism since both operations are componentwise. Hence $\ker(\pi_i) \cong G_1 \times \cdots \times G_{i-1} \times G_{i+1} \times \cdots$.

4. Identify x with $\iota_i(x)$ and y with $\iota_j(y)$, where $i \neq j$. In the product $\iota_i(x)\iota_j(y)$, position i is $x \cdot 1_{G_i} = x$, position j is $1_{G_j} \cdot y = y$, and every other position is the identity. The product $\iota_j(y)\iota_i(x)$ has position i equal to $1_{G_i} \cdot x = x$, position j equal to $y \cdot 1_{G_j} = y$, and every other position the identity. The two products agree, so $xy = yx$.

In the last part of proposition 5.1.3, elements of different factors commute. The factors do not interact under the componentwise operation, and this forces the commutation.

Exercise 5.1.1

1. Does there exist a nontrivial group G such that $G \times G \cong G$? hint: [1]
2. Let G be a finitely generated abelian group. Show that every subgroup is also a finitely generated abelian group.
3. If $H \leqslant G_1 \times G_2$, are there always subgroups $H_1 \leqslant G_1$ and $H_2 \leqslant G_2$ such that $H \cong H_1 \times H_2$? Prove it or give a counter-example.

In definition 5.1.1, the factors need not be the same. When they are, G^n denotes the direct product of n copies of G, for instance $G^4 = G \times G \times G \times G$. An element $(g_0, \ldots, g_{n-1})$ of G^n is the same data as the function $f\colon \{0, \ldots, n-1\} \to G$ with $f(i) = g_i$, and the componentwise product of two tuples corresponds to the pointwise product $(ff')(i) = f(i)f'(i)$ of the functions. So G^n is isomorphic to the group of functions $\{0, \ldots, n-1\} \to G$ under pointwise multiplication. The same description works for any set B and any group A: the functions $B \to A$ form a group A^B under pointwise multiplication, the direct product of copies of A indexed by B. For example, $(\mathbb{Z}/2\mathbb{Z})^{\mathbb{R}}$ is the group of all functions $\mathbb{R} \to \mathbb{Z}/2\mathbb{Z}$.

5.1.1 Fundamental theorem of Finitely Generated Abelian Groups

This theorem is stated, but not proved till till much later (chapter 14, theorem 14.1.9). The main idea that is trying to be presented here is the power of of being abelian: If we have an abelian, it is *such* a nice group that we can classify them all with isormophism to $\mathbb{Z}$ and $\mathbb{Z}_{p^\alpha}$ for appropriate power-prime.

[1] Think about $G = \prod_{n=1}^{\infty} \mathbb{Z}$

It will also help in our indeavour to classify groups. With this representation, it becomes much much easier. Here are two terms we introduce now to present the theorem:

Definition 5.1.4: Finitely Generated Group

A group G is *finitely generated* if $\langle A \rangle = G$ for some finite subset $A \subseteq G$.

Definition 5.1.5: Free Abelian Group

$\mathbb{Z}^r = \mathbb{Z} \times \cdots \times \mathbb{Z}$. $\mathbb{Z}^r$ is called the *free abelian group of rank r*.

Theorem 5.1.6: Fundamental Theorem of Finitely Generated Abelean Groups

Let G be a finitely generated abelian group. Then:

$$G \cong \mathbb{Z}^r \times \mathbb{Z}_{n_1} \times \cdots \mathbb{Z}_{n_s}$$

for some integers $r, n_1, ..., n_s$ with the following conditions:

1. $r \geq 0$ and $n_j \geq 2$ for all j, and
2. $n_{i+1} | n_i$ for $1 \leq i \leq s-1$

Furthermore, r and $n_1, \ldots, n_s$ are uniquely determined by G.

***Proof*:**
Existence is corollary 14.1.18, the case $R = \mathbb{Z}$ of theorem 14.1.9, and uniqueness is the case $R = \mathbb{Z}$ of theorem 14.1.16.

The rest of this section gives the vocabulary for describing abelian groups.

Notice also that it's for *finitely generated abelian groups*. What about infinitely generated abelian groups? We can simplify for a moment and ask about countably generated abelian groups. We have solved this for p-groups, but we have yet to solve it in the general case:

https://math.stackexchange.com/questions/3927834/classification-of-countably-infinite-abelian-groups

Definition 5.1.7: free rank and invariant factors

r is called the *free rank* or *betti number*, while $n_1, ..., n_s$ are called the *invariant factors*. The whole expression is called the *invariant factor decomposition of G*.

Exercise 5.1.2

1. Let $A \subseteq B$ be two finitely generated free abelian groups, each of rank n. Show that B/A has rank 0.
2. Let $G = (\mathbb{Z}/n\mathbb{Z})^\times$. Decompose G into a product of cyclic groups with additive notation.

5.2 Recognizing Direct Products

Let's say we have a (not necessarily abelian) group G. Can G be decomposed into the direct product of two smaller groups? This question is what we will be exploring in this section.

The 4th identity of proposition 5.1.3 gives us a very valuable insight on how to think of direct products. If we have two groups G_1 and G_2, we showed that creating a set of 2-tulpes with component-wise operation creates a new group. With the fact that components commute ($xy = yx$, if $x \in G_1$, $y \in G_2$), we can also define the direct product in terms of the following:

$$G_1 \times G_2 = \langle x, y | xy = yx, x \in G_1, y \in G_2 \rangle$$

where the operation is done when everything is "moved to the appropriate place"

Example 5.2.1: presentation example
Let $G_1 = S_3$ and $G_2 = \mathbb{Z}_5$. Take $x = (1\ 2)4$ and $y = 4(2\ 3)2$. Then

$$xy = (1\ 2)44(2\ 3)2 = (1\ 2)(2\ 3)442 = (1\ 2\ 3)2$$

You might ask yourself what's the point of this 2nd perspective? The idea is that we can now ask ourselves when can a group be decomposed into smaller groups. In other words, if we had a group G, can we split it into two parts G_1, G_2 such that $G \cong G_1 \times G_2$?

Thus, we will explore exactly how far a two subgroups (or more generally subsets) of a group are from being commutative, and then use that information to find out when we can decompose groups.

We start with defining a way to capture *how commutative* a groups/subgroups/elements are:

Definition 5.2.2: Commutator and Commutator Group

Let G be a group, let $x, y \in G$, and let A, B be nonemtpy subset of G


1. Define $[x, y] = x^{-1}y^{-1}xy$. $[x, y]$ is called the *commutator* of x and y
2. Define $[A, B] = \langle [a, b] \big| a \in A,\ b \in B \rangle$, the group geenrated by the commutators of elements from A and B
3. Define $G' = \langle [x, y] | x, y \in G \rangle$ to be the subgroup of G generated by commutators of all element sfrom G. G' is called the *commutator subgroup* of G

Notice that if x and y commute, then $[x, y] = 1$. If all the element of G commute, then $G' = \{1\}$. Thus, the commutator captures an idea of how much the elements of G commute

Proposition 5.2.3: Commutator Subgroup Properties

Let G be a group, $x, y \in G$, and $H \leqslant G$. Then

1. $xy = yx[x, y]$
2. $H \trianglelefteq G$ if and only if $[H, G] \leqslant H$
3. for every automorphism σ of G, $\sigma([x, y]) = [\sigma(x), \sigma(y)]$ and $\sigma(G') = G'$. Hence G' char G, so $G' \trianglelefteq G$, and G/G' is abelian
4. G/G' is the largest abelian quotient of G. That is, if $H \trianglelefteq G$ and G/H is abelian, then $G' \leqslant H$. Conversely, if $G' \leqslant H$, then $H \trianglelefteq G$ and G/H is abelian
5. (Universal Abelian Quotient) let $\pi \colon G \to G/G'$ be the natural projection. If $\varphi \colon G \to A$ is a homomorphism into an abelian group A, then $G' \leqslant \ker(\varphi)$, and there is a unique homomorphism $\overline{\varphi} \colon G/G' \to A$ with $\varphi = \overline{\varphi} \circ \pi$, that is, the following diagram commutes:



***Proof*:**

1. $yx[x, y] = yxx^{-1}y^{-1}xy = xy$.
2. For $h \in H$ and $g \in G$,
$$g^{-1}hg = h[h, g]$$
since $h[h, g] = hh^{-1}g^{-1}hg$. Suppose $H \trianglelefteq G$. Then $g^{-1}hg \in H$ by proposition 3.1.11(5), applied to g^{-1}, so $[h, g] = h^{-1}(g^{-1}hg) \in H$. Thus the subgroup H contains every generator of $[H, G]$, and $[H, G] \leqslant H$ by proposition 2.3.17. Conversely, suppose $[H, G] \leqslant H$. Then $g^{-1}hg = h[h, g] \in H$ for all $h \in H$ and $g \in G$. Replacing g by g^{-1} gives $gHg^{-1} \subseteq H$ for every $g \in G$, so $H \trianglelefteq G$ by proposition 3.1.11.
3. Let $\sigma \in \mathrm{Aut}(G)$. By proposition 1.4.4(2),
$$\sigma([x, y]) = \sigma(x)^{-1}\sigma(y)^{-1}\sigma(x)\sigma(y) = [\sigma(x), \sigma(y)]$$
so σ sends every commutator to a commutator. The set $P = \{g \in G \mid \sigma(g) \in G'\}$ is a subgroup of G by proposition 2.1.3: it contains 1, since $\sigma(1) = 1$, and if $g, h \in P$, then $\sigma(gh^{-1}) = \sigma(g)\sigma(h)^{-1} \in G'$. It contains every commutator, so $G' \subseteq P$ by proposition 2.3.17, that is, $\sigma(G') \subseteq G'$. The inverse σ^{-1} is also an automorphism of G, so the same argument gives $\sigma^{-1}(G') \subseteq G'$, and applying σ gives $G' \subseteq \sigma(G')$. Hence $\sigma(G') = G'$ for every $\sigma \in \mathrm{Aut}(G)$, so G' char G (definition 4.7.12) and $G' \trianglelefteq G$ by proposition 4.7.13(1). Finally, for $x, y \in G$, (1) and $[x, y] \in G'$ give
$$(xG')(yG') = xyG' = yx[x, y]G' = yxG' = (yG')(xG')$$
so G/G' is abelian.

4. Suppose $H \trianglelefteq G$ and G/H is abelian, and let $x, y \in G$. Then $xyH = (xH)(yH) = (yH)(xH) = yxH$, so $xy \in yxH$, say $xy = yxh$ with $h \in H$. Then $h = (yx)^{-1}xy = x^{-1}y^{-1}xy = [x, y]$, so H contains every commutator, and $G' \leqslant H$ by proposition 2.3.17. Conversely, suppose $G' \leqslant H$. Every generator $[h, g]$ of $[H, G]$ is a commutator, so $[H, G] \leqslant G' \leqslant H$ by proposition 2.3.17, and $H \trianglelefteq G$ by (2). For $x, y \in G$, the commutator $[x, y]$ lies in H, so $[x, y]H = H$, and by (1)

$$(xH)(yH) = xyH = yx[x, y]H = yxH = (yH)(xH)$$

Thus G/H is abelian.

The converse also follows from the isomorphism theorems. By (3), G/G' is abelian, so $H/G' \trianglelefteq G/G'$ (corollary 3.1.12), and $H \trianglelefteq G$ by corollary 3.5.8(5). By theorem 3.5.5,

$$G/H \cong (G/G')/(H/G')$$

and a quotient Q/N of an abelian group Q is abelian, since $(aN)(bN) = abN = baN = (bN)(aN)$.

5. Let $\varphi\colon G \to A$ be a homomorphism into an abelian group A. For $x, y \in G$, proposition 1.4.4(2) and the commutativity of A give

$$\varphi([x, y]) = \varphi(x)^{-1}\varphi(y)^{-1}\varphi(x)\varphi(y) = 1$$

so the subgroup $\ker(\varphi)$ (proposition 1.4.4(4)) contains every commutator, and $G' \leqslant \ker(\varphi)$ by proposition 2.3.17. Since $G' \trianglelefteq G$ by (3), theorem 3.1.15 with $N = G'$ gives a unique homomorphism $\overline{\varphi}\colon G/G' \to A$ with $\varphi = \overline{\varphi} \circ \pi$, namely $\overline{\varphi}(gG') = \varphi(g)$, which completes the proof.

Example 5.2.4

If G is abelian, then for any $x, y \in G$, $[x, y] = x^{-1}y^{-1}xy = x^{-1}xy^{-1}y = 1$, and so $G' = 1$, and $G/G' \cong G$.

With this, we can answer now give criterion to recognize direct products. First, a lemma:

Lemma 5.2.5: Representation's of HK

Let H and K be subgroups of a group G. The number of distinct ways of writing each element of the set HK in the form hk, for some $h \in H$ and $k \in K$ is $|H \cap K|$. In particular, if $H \cap K = 1$, then each element of HK can be written uniquely as a product of hk, for some $h \in H$ and $k \in K$.

***Proof*:**

Let $x \in HK$, say $x = hk$ with $h \in H$ and $k \in K$, and let $R_x = \{(h', k') \in H \times K \mid h'k' = x\}$ be the set of ways of writing x. Define $\theta\colon H \cap K \to R_x$ by $\theta(t) = (ht, t^{-1}k)$. It takes values in R_x, since $ht \in H$, $t^{-1}k \in K$ and $(ht)(t^{-1}k) = hk = x$. It is injective, since $ht = ht'$ forces $t = t'$. It is surjective: if $h'k' = x = hk$, then $t = h^{-1}h' = kk'^{-1}$ lies in $H \cap K$, and $\theta(t) = (h', (kk'^{-1})^{-1}k) = (h', k')$. So $|R_x| = |H \cap K|$ for every $x \in HK$, and when $H \cap K = 1$

each element of HK has exactly one expression hk, as claimed.

Theorem 5.2.6: Recognition Theorem For Direct Products

Let G be a group, and let H, K be subgroups such that

1. H and K are normal in G, and
2. $H \cap K = \{1\}$

Then HK is a subgroup of G, and $\mu\colon H \times K \to HK$, $\mu(h,k) = hk$, is an isomorphism, so

$$HK \cong H \times K$$

Conversely, if HK is a subgroup of G and μ is an isomorphism, then $H \cap K = \{1\}$ and both H and K are normal subgroups of HK.

***Proof*:**
Suppose first that H and K are normal in G and $H \cap K = 1$. For $h \in H$ and $k \in K$, the element $hkh^{-1}k^{-1}$ equals $(hkh^{-1})k^{-1}$, which lies in K because $K \trianglelefteq G$, and it equals $h(kh^{-1}k^{-1})$, which lies in H because $H \trianglelefteq G$ (proposition 3.1.11). So it lies in $H \cap K = 1$, and $hk = kh$. The set HK is a subgroup of G by corollary 3.4.5. For $(h,k), (h',k') \in H \times K$,

$$\mu((h,k)(h',k')) = hh'kk' = hkh'k' = \mu(h,k)\mu(h',k')$$

because k commutes with h', so μ is a homomorphism. It is surjective by the definition of HK, and injective by lemma 5.2.5, since $H \cap K = 1$. Hence μ is an isomorphism.

Conversely, suppose that HK is a subgroup and μ is an isomorphism. If $t \in H \cap K$, then $\mu(t, t^{-1}) = 1 = \mu(1,1)$, so $t = 1$ by injectivity, and $H \cap K = 1$. For $h \in H$ and $k \in K$,

$$hk = \mu((1,k)(h,1)) = \mu(1,k)\mu(h,1) = kh$$

Now let $x = h'k' \in HK$ and $h \in H$. Then $xhx^{-1} = h'k'hk'^{-1}h'^{-1} = h'hh'^{-1} \in H$, since k' commutes with h. So $xHx^{-1} \subseteq H$ for every $x \in HK$, and in the same way $xKx^{-1} \subseteq K$. By proposition 3.1.11, applied in the group HK, both H and K are normal in HK, completing the proof.

In particular, if H and K are normal subgroups of G with $H \cap K = 1$ and $HK = G$, then $G \cong H \times K$. The converse cannot conclude normality in G when $HK \neq G$: for $G = S_3$, $H = \langle (1\ 2) \rangle$ and $K = 1$, the map μ is an isomorphism, while H is not normal in S_3, since $(1\ 3)(1\ 2)(1\ 3)^{-1} = (2\ 3)$ (proposition 1.2.27).

The propety that $H \cap K = 1$ has a name:

Definition 5.2.7: Complement

Let H be a subgroup of G. A subgroup K of G is called a *complement* for H in G if $G = HK$ and $H \cap K = 1$.

Thus, we can rephrase the previous theorem: if a normal subgroup H of G has a complement K that is also normal, then $G \cong H \times K$.

Another way of thinking about this theorem is that the *internal direct product* HK (definition 3.4.1) of two subgroups H and K of G agrees with their *external direct product* $H \times K$ (definition 5.1.1) when the two conditions in theorem 5.2.6 hold. If $H \cap K \neq \{1\}$, or one of them is not normal in HK, then the map μ is not an isomorphism. In the next section, we will explore a generalization of the direct product, the *semi-direct product*, which describes HK when H is normal and $H \cap K = 1$ (theorem 5.3.7).

Note that if G is abelian, finitely generated or not, and $H, K \leqslant G$ satisfy $H \cap K = 1$, then $HK \cong H \times K$, since every subgroup of an abelian group is normal (corollary 3.1.12). This is another example of the niceties of being commutative.

5.2.1 A word on Perfect Groups

We saw that if a group G is abelian, then $G' = \{1\}$. What if we had the complete opposite: if $G = G'$? Such a group has a name:

Definition 5.2.8: Perfect Group

Let G be a group and G' be the commutator subgroup. If $G = G'$, then G is called a *perfect group*

Example 5.2.9: Perfect Groups

The alternating group A_5 is perfect. Its commutator subgroup A_5' is normal in A_5 by proposition 5.2.3(3), so $A_5' = 1$ or $A_5' = A_5$ by theorem 4.9.6. If $A_5' = 1$, then $x^{-1}y^{-1}xy = 1$, that is, $xy = yx$, for all $x, y \in A_5$. But the 3-cycles $(1\,2\,3)$ and $(3\,4\,5)$ are products of two transpositions (theorem 1.2.18), so they lie in A_5, and

$$(1\,2\,3)(3\,4\,5) = (1\,2\,3\,4\,5) \neq (1\,2\,4\,5\,3) = (3\,4\,5)(1\,2\,3)$$

Hence $A_5' = A_5$.

Perfect groups are linked to solvable groups, which section 6.1.1 defines through the repeated commutator subgroups $G' \supseteq (G')' \supseteq \cdots$. For a perfect group every term of this sequence equals G, so a perfect group $G \neq 1$ is not solvable.

5.3 Semi-Direct Products

As we mentioned earlier, not all groups can be broken down into [non-trivial] direct products:

Example 5.3.1: $G \ncong H \times K$

Let $G = D_3 = \langle \sigma, r | \sigma^2 = r^3 = 1,\ \sigma r = r^{-1}\sigma \rangle$, whose six elements $\sigma^k r^i$ with $k \in \{0, 1\}$ and $0 \leq i \leq 2$ are distinct (proposition 1.2.29(4)). The subgroup $\langle \sigma \rangle = \{1, \sigma\}$ has order 2, and $\langle r \rangle$ has order 3. Since $\langle r \rangle$ has index 2, $\langle r \rangle \trianglelefteq D_3$ (corollary 3.3.6). So $\langle r \rangle \langle \sigma \rangle$ is a subgroup (corollary 3.4.5), and since $\langle r \rangle \cap \langle \sigma \rangle = 1$, its order dividing both 2 and 3 (theorem 3.3.1), proposition 3.4.3 gives

it 6 elements, so $\langle r\rangle\langle\sigma\rangle = D_3$. However, $\langle\sigma\rangle$ is not normal in D_3: from $\sigma r = r^{-1}\sigma$ and $\sigma^2 = 1$ we get $r\sigma = \sigma r^{-1}$, so $r\sigma r^{-1} = \sigma r^{-2} = \sigma r$, which is not in $\{1, \sigma\}$. By theorem 5.2.6, the map $\langle\sigma\rangle \times \langle r\rangle \to D_3$, $(a, b) \mapsto ab$, is therefore not an isomorphism. In fact no isomorphism exists:

$$D_3 \ncong \langle\sigma\rangle \times \langle r\rangle$$

because $\langle\sigma\rangle \times \langle r\rangle$ is abelian, both factors being cyclic (corollary 2.3.6) and the operation componentwise, while D_3 is not abelian (proposition 1.2.29(5)), and isomorphic groups are both abelian or both not (proposition 1.4.21(2)).

Since, $\langle\sigma\rangle \cong \mathbb{Z}/2\mathbb{Z}$ and $\langle r\rangle \cong \mathbb{Z}/3\mathbb{Z}$, we can swtich over to that notation. Then we can say that

$$D_3 \ncong \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/3\mathbb{Z}$$

The question might arise on whether there is a suitable generalization of the direct product to classify the above group. More generally, is there a way to capture the structure of HK, where H and K are *arbitrary* groups (i.e. not subgroups of a larger group G). That question is explored in this section. Note that if G was abelian then automatically, $K \trianglelefteq G$, since every subgroup of an abelian group is normal. Thus, this distinction becomes interesting only when G is non-abelian.

The way we will do this is by trying to fix the fact that elements of the group H and K will no longer always commute with each other. Note that we always have that $HK = KH$ (proposition 3.4.4), but that did not imply $hk = kh$. In the dihedral example, we had $rs = sr^{-1}$. If we were to try to write this as a product, we'd get

$$(r, 1)(1, s) = (1, s)(r^{-1}, 1)$$

Another example would be S_3. The group S_3 is another group of order 6 with subgroups of order 2 and 3, for example: (1 2) and (1 2 3)). Since $|S_3| = 6$, we again have $|(1\ 2\ 3)| \trianglelefteq S_3$ and $\langle(1\ 2\ 3)\rangle\langle(1\ 2)\rangle \cong S_3$. However, one can easily check that $(1\ 2) \ntrianglelefteq S_3$ (try taking $g = (1\ 2\ 3)$ and see if $g\langle(1\ 2)\rangle g^{-1} = \langle(1\ 2)\rangle$). We again get that $ab \neq ba$, and instead, they commute in a different manner. let $a = (1\ 2)$ and $b = (1\ 2\ 3)$. Then you can verify that:

$$ab = b^2a$$

meaning when a and b comute, b becomes b^2. Thus, we can write

$$S_3 = \langle a, b | a^2 = b^3 = 1,\ ab = b^2a\rangle$$

If were to try to write this as a product, we'd get that

$$(a, 1)(1, b) = (1, b^2)(a, 1)$$

So the question is "Is there a more general way to capture how elements in a group commute"?

As a way to motivate the coming definition, Let's start by having a larger group G, and recall that to define HK as a group, we need $H \trianglelefteq G$ and $K \leqslant G$.

Since HK is a group, we already have that $(h_1k_1)(h_2k_2) = h_3k_3$ for some $h_3k_3 \in HK$ (similarly to how in a direct product, $(a_1, b_1)(a_2b_2) = (a_1a_2, b_1b_2) = (a_3, b_3)$). More precicely, we take $h_1k_1, h_2k_2 \in HK$, we can re-write $h_1k_1h_2k_2$ as $h_3k_3 \in HK$. We showed this in proposition 3.4.4.

Doing it again here, notice exactly how we get to write $h_1k_1h_2k_2$ as h_3k_3:

$$\begin{aligned}(h_1k_1)(h_2k_2) &= h_1k_1h_2(k_1^{-1}k_1)k_2\\ &= h_1(k_1h_2k_1^{-1})k_1k_2\\ &= (h_1(k_1h_2k_1^{-1}))k_1k_2\\ &= h_3k_3\end{aligned}$$

where $h_3 = h_1(k_1h_2k_1^{-1})$ (since $H \trianglelefteq G$, $gh_1g^{-1} \in H$) and $k_3 = k_1k_3$.

To get to this construction, we heavily relied on *starting* with the group G and all the properties of the subgroups H, and K (ex. $H \cap K = \{e\}$, $H \trianglelefteq G$). Relying so heavily on a bigger group G does not help in our generalization of the direct product: when defining an arbitrary direct product $G_1 \times G_2$, we did not rely on some bigger group G from which G_1 and G_2 were normal subgroups. Thus, we have to figure out a way to do this construction by only relying on information on H and K.

To do this, we must be able to describe the operation between $(h_1k_1) \cdot (h_2k_2)$ without using the normality of $H \trianglelefteq G$. It is easy for the k elements since $k_3 = k_1k_2$, so the question about about defining $k_1h_2k_1^{-1}$.

We have in fact already encountered a solution to this problem. Since H is normal in G, the group K *acts* on H by conjugation:

$$k \cdot h = khk^{-1} \qquad \text{for } h \in H, k \in K$$

Since H is normal, $khk^{-1} = h' \in H$, meaning if we know how every k acts on every h, we can drop the necessity for a larger group G. In fact, all this information *can* be captured with a group-action:

$$\varphi : K \to \text{Aut}(H)$$

meaning we now only rely on the product of K, H, and the homomorphism φ which captures how H and K interact. Importantly for defining a group with this, $\text{Aut}(H) = \text{Aut}_{\mathbf{Grp}}(H)$, not $\text{Aut}_{\mathbf{Set}}(H)$, and so

$$\varphi(x)(ab) = \varphi(x)(a)\varphi(x)(b)$$

Thus, we have eliminated the need for a larger group G!

With this idea, we can define a our new product:

Definition 5.3.2: Semi-Direct Product

Let H and K be groups and let φ be a homomorphism form K into $\text{Aut}(H)$. Let $\cdot$ denote the (left) action of K on H determined by φ. Let G be the set of ordered pairs (h, k) with $h \in H$ and $k \in K$ and define the following multiplication on G:

$$(h_1, k_1)(h_2, k_2) = (h_1k_1 \cdot h_2, k_1k_2)$$

we usually denote $G = H \rtimes_\varphi K$, or $H \rtimes K$ if the context permits it

Notice how we are not using a bigger group, but a lot of intuition can be derived from thinking about H and K as subgroups of a larger group, showing how subgroups still play an important role in the analysis and conception of semi-direct products, but it is certainly not necessary as we will point out in the examples.

The $\rtimes$ notation is to remember that H is the normal subgruop of $H \rtimes K$ (as we will prove soon). It might be evident that in most cases $H \rtimes K \ncong K \rtimes H$, since we'd be defining different actions. More on this when we show some examples.

Another way of remembering which group is acting on which is with a pop-culture reference (curtosy of one of my professors): if you are aware of what a "Kamehameha" is from dragon ball, then the symbol "$\rtimes$" can be thought of as Goku's hand preforming the Kamehameha.



If you are unaware of the cultural reference, here's a youtube video I found (or you can google it):

https://www.youtube.com/watch?v=_ct3ccrU4AI

As silly as it may be, this turned out to be the most efficient way for me to remember which groups acts on which.

Before we get too hasty, we should prove that this is indeed a group and that all the properties stated earlier hold:

Proposition 5.3.3: Properties Of Semi-Direct Product

1. This multiplication makes G into a group of order $|G| = |H||K|$
2. The sets $\{(h,1)|h \in H\}$ and $\{(1,k)|k \in K\}$ are subgroups of G and the maps $h \mapsto (h,1)$ and $k \mapsto (1,k)$ for $k \in K$ are isomorphisms of these subgroups with the groups H and K respectively:
$$H \cong \{(h,1)|h \in H\} \qquad K \cong \{(1,k)|k \in K\}$$
3. $H \trianglelefteq G$
4. $H \cap K = \{e\}$
5. for all $h \in H$ and $k \in K$, $khk^{-1} = k \cdot h = \varphi(k)(h)$

***Proof*:**

1. To show $H \rtimes K$ is a group, we need to show it obeys the axioms of a group

(a) **associativity**. Let $(a,x),(b,y),(c,z) \in H \rtimes K$. Then

$$\begin{aligned}((a,x)(b,y))(c,z) &= (a\ x\cdot b, xy)(c,z)\\ &= (a\ x\cdot b\ (xy)\cdot c, xyz)\\ &= (a\ x\cdot b\ x\cdot(y\cdot c), xyz)\\ &= (a\ \varphi(x)(b)\ \varphi(x)(y\cdot c), xyz)\\ &= (a\ \varphi(x)(b\ y\cdot c), xyz)\\ &= (a\ x\cdot(b\ y\cdot c), xyz)\\ &= (a,x)(by\cdot c, yz)\\ &= (a,x)((b,y)(c,z))\end{aligned}$$

where I switched over to homomorphism notation to show that since $\varphi(x)$ is a homomorphism (note that $\varphi(x)$ is an automorphism of H), then $\varphi(x)(st) = \varphi(x)(s)\varphi(x)(t)$.

(b) **Identity**: I claim that $(1,1)$ is an identity. In particular, for any $(x,y) \in H \rtimes K$

$$(1,1)(x,y) = (1\ 1\cdot x, 1y) = (x,y) = (x,y)(1,1)$$

(c) **Inverse**: I claim that for any $(h,k) \in H \rtimes K$, $(h,k)^{-1} = (k^{-1}\cdot h^{-1}, k^{-1})$ is an inverse. Indeed:

$$\begin{aligned}(h,k)(k^{-1}\cdot h^{-1}, k^{-1}) &= (hk\cdot(k^{-1}\cdot h^{-1}), kk^{-1})\\ &= (h(kk^{-1})\cdot h^{-1}, 1)\\ &= (h\ 1\cdot h^{-1}, 1) = (hh^{-1}, 1)\\ &= (1,1)\end{aligned}$$

and similarly for $(h,k)^{-1}(h,k)$.

Thus, $H \rtimes K$ is a group.

2. Let $\hat{H} = \{(h,1) | h \in H\}$ and $\hat{K} = \{(1,k) | k \in K\}$. Since $\varphi\colon K \to \mathrm{Aut}(H)$ is a homomorphism, $\varphi(1) = \mathrm{id}_H$, so $1\cdot b = b$ for $b \in H$. Since each $\varphi(k)$ is a homomorphism, $k\cdot 1 = \varphi(k)(1) = 1$ for $k \in K$ (proposition 1.4.4). Hence, for $a,b \in H$ and $a',b' \in K$,

$$(a,1)(b,1) = (a\ 1\cdot b, 1) = (ab,1) \qquad (1,a')(1,b') = (1\ a'\cdot 1, a'b') = (1,a'b')$$

so $h \mapsto (h,1)$ and $k \mapsto (1,k)$ are injective homomorphisms $H \to G$ and $K \to G$. Their images $\hat{H}$ and $\hat{K}$ are subgroups of G by proposition 1.4.4, isomorphic to H and K.

3. Identify h with $(h,1)$ and k with $(1,k)$. By (2), $(1,k)^{-1} = (1,k^{-1})$, and

$$\begin{aligned}khk^{-1} &= (1,k)(h,1)(1,k^{-1})\\ &= (k\cdot h, k)(1,k^{-1})\\ &= (k\cdot h\ k\cdot 1, kk^{-1})\\ &= (k\cdot h, 1)\end{aligned}$$

which lies in $\hat{H}$. So $(1,k)\hat{H}(1,k)^{-1} \subseteq \hat{H}$, and the same computation with k^{-1} gives $(1,k)^{-1}\hat{H}(1,k) \subseteq \hat{H}$, hence equality. So every element of $\hat{K}$ normalizes $\hat{H}$, and so does every element of $\hat{H}$. Every element of G is $(h,k) = (h,1)(1,k)$, and $N_G(\hat{H})$ is a subgroup of G, so $N_G(\hat{H}) = G$ and $\hat{H} \trianglelefteq G$.

4. If $(h,1)=(1,k)$, then $h=1$ and $k=1$, so $\hat{H}\cap\hat{K}=\{(1,1)\}$.
5. This is the computation in (3): $khk^{-1}=(k\cdot h,1)$, which is identified with $k\cdot h=\varphi(k)(h)$.

Point (5) is where the semi-direct product departs from the direct product. In the coming example, play close attention to exactly how the action commute elements.

Remember that the semi-direct products are a generalization of direct products. Exactly how is what this next theorem identifies:

Proposition 5.3.4: When The Semi-Direct Product is a Direct Product

Let H and K be groups and let $\varphi: K\to \mathrm{Aut}(H)$ be a homomorphism. Then the following are equivalent:

1. The identity (set) map between $H\rtimes K$ and $H\times K$ is a group homomorphism hence an isomrophism
2. φ is the trivial homomorphism form K into $\mathrm{Aut}(H)$
3. $K\trianglelefteq H\rtimes K$

***Proof*:**
Write $G=H\rtimes K$ and identify H and K with the subgroups $\{(h,1)\}$ and $\{(1,k)\}$ of G as in proposition 5.3.3(2).

$(1\Rightarrow 2)$: By definition 5.3.2 the product in $H\rtimes K$ is

$$(h_1,k_1)(h_2,k_2)=(h_1\ k_1\cdot h_2,\ k_1k_2)$$

while the product in $H\times K$ is (h_1h_2,k_1k_2). If the identity set map is a homomorphism, these two agree for all choices, and comparing first coordinates gives $k_1\cdot h_2=h_2$ for every $h_2\in H$ and every $k_1\in K$. That says $\varphi(k_1)=\mathrm{id}_H$ for every $k_1\in K$, which is (2).

$(2\Rightarrow 3)$: If φ is trivial then $k\cdot h=h$ for all $h\in H$ and $k\in K$, so proposition 5.3.3(5) gives $khk^{-1}=h$, that is $hk=kh$. Hence every $h\in H$ normalizes K, and every element of K normalizes K, so $N_G(K)$ contains both H and K. Every element of G is of the form $(h,k)=(h,1)(1,k)$, so $G=HK$ and therefore $N_G(K)=G$, which says $K\trianglelefteq G$.

$(3\Rightarrow 1)$: Assume $K\trianglelefteq G$ and take $h\in H$, $k\in K$. Since K is normal, $hkh^{-1}\in K$, so

$$hkh^{-1}k^{-1}=(hkh^{-1})k^{-1}\in K$$

and since H is normal by proposition 5.3.3(3), $kh^{-1}k^{-1}\in H$, so the same element $hkh^{-1}k^{-1}=h(kh^{-1}k^{-1})$ lies in H. By proposition 5.3.3(4), $H\cap K=1$, so $hkh^{-1}k^{-1}=1$ and $hk=kh$. Feeding this back into proposition 5.3.3(5) gives $k\cdot h=khk^{-1}=h$, so the product in $H\rtimes K$ reads

$$(h_1,k_1)(h_2,k_2)=(h_1h_2,k_1k_2)$$

which is the product in $H\times K$. The identity set map is therefore a homomorphism, and being a bijection it is an isomorphism, which is (1).

Corollary 5.3.5: A Non-Abelian Group Of Order pq

Let $p < q$ be primes with $p|q-1$. Then there is a non-abelian group of order pq.

***Proof*:**
The nonzero classes modulo q form a group $(\mathbb{Z}/q\mathbb{Z})^\times$ of order $q-1$ under multiplication, since each is invertible by Bézout (theorem 0.2.10). As $p|q-1$, it contains an element s of order p (theorem 4.8.7). Multiplication by s is an automorphism of the additive group $\mathbb{Z}/q\mathbb{Z}$, and $\varphi\colon \mathbb{Z}/p\mathbb{Z} \to \mathrm{Aut}(\mathbb{Z}/q\mathbb{Z})$, $k \mapsto (h \mapsto s^k h)$, is a well-defined homomorphism because $s^p = 1$. By proposition 5.3.3, $G = \mathbb{Z}/q\mathbb{Z} \rtimes_\varphi \mathbb{Z}/p\mathbb{Z}$ has order pq, and for the classes $h = \overline{1}$ of $\mathbb{Z}/q\mathbb{Z}$ and $k = \overline{1}$ of $\mathbb{Z}/p\mathbb{Z}$, $khk^{-1} = \varphi(k)(h) = s \neq h$. So G is non-abelian.

Example 5.3.6: Semi-Direct Products

1. Let H be any abelian group (even of infinite order) and let $K = \langle x \rangle \cong Z_2$. be the group of order 2. Define $\varphi : K \to \mathrm{Aut}(H)$ by mapping x to the automorphism of inversion on H, so that the associated action is $x \cdot h = h^{-1}$, or, written in homomorphism form:

$$\varphi(x)(h) = h^{-1} \qquad \varphi(e)(h) = h$$

Note that this is an automorphism, for

$$f_x : H \to H, \qquad f_x(h) = h^{-1} \qquad f_x(xy) = (xy)^{-1} = x^{-1}y^{-1} = f_x(x)f_x(y)$$

since H is abelian, the map is it's own inverse (making it bijective).

Thus, we can define $H \rtimes_\varphi K$. To distinguish between the group-action and the group operation, I will ues the $+$ symbol to represent the operation for both groups. To get comfortable with this, let's do a computation:

$$(a_1, x)(a_2, x) = (a_1 + x \cdot a_2, x + x) = (a_1 a_2^{-1}, 0)$$

$$\begin{aligned} xhx^{-1} &= (0, x)(h, 0)(0, x^{-1}) \\ &= (0 + x \cdot h, 0 + x)(0, x^{-1}) = (-h, x)(0, x) \\ &= (-h + x \cdot 0, x + x) \\ &= (-h - h, 0) \\ &= (-h, 0) \\ &= h^{-1} \end{aligned}$$

Thus, we have:

$$xhx^{-1} = h^{-1} \Rightarrow xh = h^{-1}x$$

in the special case where $H = Z_n$, then $\mathbb{Z}/n\mathbb{Z} \rtimes \mathbb{Z}/2\mathbb{Z} \cong D_n$!!! if $H = \mathbb{Z}$, then we'd say $G = D_\infty$.

2. Let $H = \mathbb{R}^2$ and $K = SO(2)$.

3. Since simple groups have no normal subgroups, simple groups cannot be decomposed into semi-direct products, showing further how they are like "prime numbers" for groups.

With the idea of the semi-direct product in mind and a couple of examples, we end this section by given sufficient and necessary conditions to recognize semi-direct products:

Theorem 5.3.7: Recognition Theorem For Semi-Direct Products

Suppose G is a group with subgrosup H and K such that

1. $H \trianglelefteq G$
2. $H \cap K = 1$

Let $\varphi : K \to \text{Aut}(H)$ be the homomorphism define dby mapping $k \in K$ to the automrophis mof left conjugation by k on H. Then

$$HK \cong H \rtimes K$$

In particualr, if $G = HK$, with H and K satisfying the aforementioend conditions, then

$$G \cong H \rtimes K$$

Put another way, a group is a semi-derict product if there exists a complement for some proper normal subgroup of G.

***Proof*:**
First, φ is well defined and is a homomorphism. For $k \in K$ the map $c_k : h \mapsto khk^{-1}$ sends H into H because $H \trianglelefteq G$, it is a homomorphism of H, and $c_{k^{-1}}$ is a two-sided inverse for it, so $c_k \in \text{Aut}(H)$. For $k_1, k_2 \in K$ and $h \in H$,

$$c_{k_1k_2}(h) = (k_1k_2)h(k_1k_2)^{-1} = k_1(k_2hk_2^{-1})k_1^{-1} = (c_{k_1} \circ c_{k_2})(h)$$

so $\varphi : k \mapsto c_k$ is a homomorphism $K \to \text{Aut}(H)$.

Next, HK is a subgroup of G. Since $H \trianglelefteq G$ we have $hk = k(k^{-1}hk) \in KH$ and $kh = (khk^{-1})k \in HK$ for all $h \in H$ and $k \in K$, so $HK = KH$, and $HK \leqslant G$ by proposition 3.4.4.

Each element of HK is hk for exactly one pair (h, k): if $h_1k_1 = h_2k_2$ then $h_2^{-1}h_1 = k_2k_1^{-1}$ lies in $H \cap K = 1$, so $h_1 = h_2$ and $k_1 = k_2$. Hence

$$\Psi : HK \to H \rtimes K \qquad hk \mapsto (h, k)$$

is a well defined bijection. It remains to see that it is a homomorphism. Using $k_1h_2k_1^{-1} = \varphi(k_1)(h_2) = k_1 \cdot h_2$,

$$(h_1k_1)(h_2k_2) = h_1(k_1h_2k_1^{-1})k_1k_2 = (h_1\ k_1 \cdot h_2)(k_1k_2)$$

and the right hand side is already in the form (element of H)(element of K), so

$$\Psi\left((h_1k_1)(h_2k_2)\right) = (h_1\ k_1 \cdot h_2,\ k_1k_2) = (h_1, k_1)(h_2, k_2) = \Psi(h_1k_1)\Psi(h_2k_2)$$

by definition 5.3.2. Therefore $HK \cong H \rtimes K$, and when $G = HK$ this reads $G \cong H \rtimes K$.

A semi-direct product $G = H \rtimes_\varphi K$ is an extension of H by K. By definition 5.3.2, the map $G \to K$

sending (h, k) to k is a surjective homomorphism, and its kernel is the subgroup $\{(h, 1) \mid h \in H\}$, which is isomorphic to H (proposition 5.3.3(2)). So $G/H \cong K$ by corollary 3.1.17. Moreover, the homomorphism $K \to G$ sending k to $(1, k)$ composed with this map is the identity of K. Extensions with such a homomorphism are called split, and every split extension is a semi-direct product (proposition 5.3.9).

Definition 5.3.8: Split Sequence

A short exact sequence $1 \to A \xrightarrow{f} B \xrightarrow{g} C \to 1$ (definition 3.6.4) *splits* if there is a homomorphism $\psi\colon C \to B$ with $g \circ \psi = \mathrm{id}_C$, that is, if the following diagram commutes:

$$\begin{array}{ccccccccc} 1 & \longrightarrow & A & \xrightarrow{f} & B & \xrightarrow{g} & C & \longrightarrow & 1 \\ & & & & & \nwarrow^{\psi} & \uparrow{\scriptstyle \mathrm{id}_C} & & \\ & & & & & & C & & \end{array}$$

Proposition 5.3.9: Split Extensions Are Semi-Direct Products

Let $1 \to A \xrightarrow{f} B \xrightarrow{g} C \to 1$ be a short exact sequence that splits by $\psi\colon C \to B$. Then $N = f(A)$ is a normal subgroup of B isomorphic to A, the subgroup $Q = \psi(C)$ is isomorphic to C, $N \cap Q = 1$ and $B = NQ$. Hence $B \cong N \rtimes Q$, with Q acting on N by conjugation.

***Proof*:**
By exactness $N = \ker(g)$, which is normal in B (proposition 3.1.14), and f is an injective homomorphism onto N, so $N \cong A$. If $\psi(c) = \psi(c')$, then $c = g(\psi(c)) = g(\psi(c')) = c'$, so ψ is an injective homomorphism onto Q, and $Q \cong C$. If $\psi(c) \in N$, then $c = g(\psi(c)) = 1$, so $N \cap Q = 1$. For $b \in B$ put $q = \psi(g(b)) \in Q$. Then $g(bq^{-1}) = g(b)g(\psi(g(b)))^{-1} = g(b)g(b)^{-1} = 1$, so $bq^{-1} \in N$ and $b = (bq^{-1})q \in NQ$. Hence $B = NQ$, and theorem 5.3.7 gives $B \cong N \rtimes Q$, as claimed.

When the action of Q on N is trivial, the multiplication of definition 5.3.2 is componentwise and $N \rtimes Q$ is the direct product $N \times Q$. For modules, split sequences return in section 17.1. Not every short exact sequence splits:

Example 5.3.10: Counter-Example
Write $C_2 = \mathbb{Z}/2\mathbb{Z}$ and $C_4 = \mathbb{Z}/4\mathbb{Z}$ additively, and let $f\colon C_2 \to C_4$ send 1 to 2 and $g\colon C_4 \to C_2$ send x to its residue modulo 2. Then

$$1 \longrightarrow C_2 \xrightarrow{f} C_4 \xrightarrow{g} C_2 \longrightarrow 1$$

is exact, since f is injective, g is surjective and $\mathrm{im}(f) = \{0, 2\} = \ker(g)$. It does not split: a homomorphism $\psi\colon C_2 \to C_4$ sends 1 to an element x with $x + x = \psi(1 + 1) = \psi(0) = 0$, so $x \in \{0, 2\}$ and $g(\psi(1)) = 0 \neq 1$. A semi-direct product of two groups of order 2 contains the two subgroups $\{(h, 1)\}$ and $\{(1, k)\}$ of order 2, which meet trivially (proposition 5.3.3(2) and (4)), while 2 is the only element of order 2 in C_4. So C_4 is not such a semi-direct product.

5.4 A Categorical approach of the Product


The idea of being able to take the "product" of two objects is not unique to sets and groups. As we continue to explore more and more algebraic structures, we will keep asking ourselves a similar question: Does algebraic structure X have the flexibility/restriction to define products? [2] What we will be doing then is finding a property which we can use to define what a product is in different algebraic settings.

Let's pick two arbitrary groups A and B. We defined product in the classical definition as the new group $(A \times B, (\cdot_A, \cdot_B))$. Let's denote this new group C. The key idea is that C is a group that contains groups A and B, and you can "recover" A and B from C. The way we can recover these two groups from C is simply by projcting to them:

$$\pi_A : C \to A,\ (a,b) \mapsto a \qquad \pi_B : C \to B,\ (a,b) \mapsto b$$


It should be checked that π_A and π_B are both surjective homomorphisms. Notice that $\pi_A(C) \cong A$ and $\pi_A(C) \cong B$. In this way, we have "recovered" A and B from C. Furthermore, C contains no more information than information about A and B. So essentially, if there exists a group C that most efficienly stores A and B, in particular if there are two functions (in our case π_A, π_B) which let's us recover A and B, then we can say C is the product of A and B. let's write this group and these two functions (C, π_A, π_B)

But is C the most efficient group for storing information about the group A and B? We can answ3re this by relating C to any other group, as is common in category theory. Let's say we have a group $G \in \text{Obj}(Grp)$ were we have a homomorphism $G \xrightarrow{f_A} A$ and $G \xrightarrow{f_B} B$ (so some structe of G is in A and B). Then does there exist a homomorphism $f : G \to C$ which can compose with π_A and π_B and produce f_1 and f_2? In other words: (Rushed)



In a sense, it's saying that whatever structure G has of A and B, C must have it too, since we can pass through C wihtout loosing that structure.


We can now formalize this idea with categories. The objects of $C_{A,B}$ are



and such an object can be represented as (X, f_A, f_B), where X is a group and $f_A \colon X \to A$ and $f_B \colon X \to B$ are homomorphisms. If (X, f_A, f_B) and (Y, g_A, g_B) are objects, then a morphism

[2] As usual with category theory, the question of whether the product exists goes beyond algebra: Topological spaces, uniform spaces, graphs, ordered sets, and other domains of mathematics will also have products!

$f : (X, f_A, f_B) \to (Y, g_A, g_B)$ is a homomorphism $f\colon X \to Y$ such that the following diagram commutes, that is, $g_A \circ f = f_A$ and $g_B \circ f = f_B$:



Example 5.4.1: Morphisms In $C_{A,B}$

Let $A = B = \mathbb{Z}$, and consider the objects $(\mathbb{Z}, \mathrm{id}_\mathbb{Z}, \mathrm{id}_\mathbb{Z})$ and $(\mathbb{Z} \times \mathbb{Z}, \pi_1, \pi_2)$, where π_1 and π_2 are the projections, which are homomorphisms (proposition 5.1.3(3)). The diagonal homomorphism $f\colon \mathbb{Z} \to \mathbb{Z} \times \mathbb{Z}$, $f(n) = (n, n)$, is a morphism from the first object to the second, since $\pi_1 \circ f = \mathrm{id}_\mathbb{Z}$ and $\pi_2 \circ f = \mathrm{id}_\mathbb{Z}$. The homomorphism $f'(n) = (n, 0)$ is not, since $\pi_2(f'(1)) = 0 \neq 1$.

Proposition 5.4.2: $C_{A,B}$ Forms A Category

Let $C_{A,B}$ be defined as above. Then $C_{A,B}$ forms a category

***Proof*:**

The requirements of a category hold, as in the proof of proposition 2.3.21:

1. (composition) Let $f\colon (X, f_A, f_B) \to (Y, g_A, g_B)$ and $g\colon (Y, g_A, g_B) \to (Z, h_A, h_B)$ be morphisms. The composite $g \circ f\colon X \to Z$ is a homomorphism by proposition 1.4.4(6), and

$$h_A \circ (g \circ f) = (h_A \circ g) \circ f = g_A \circ f = f_A$$

   and in the same way $h_B \circ (g \circ f) = f_B$. So $g \circ f$ is a morphism $(X, f_A, f_B) \to (Z, h_A, h_B)$.

2. (identities) For an object (X, f_A, f_B), the identity homomorphism id_X satisfies $f_A \circ \mathrm{id}_X = f_A$ and $f_B \circ \mathrm{id}_X = f_B$, so it is a morphism from (X, f_A, f_B) to itself. For morphisms f out of (X, f_A, f_B) and f' into it, $f \circ \mathrm{id}_X = f$ and $\mathrm{id}_X \circ f' = f'$.

3. (associativity) Composition of morphisms is composition of functions, and for composable morphisms f, g, k both $(k \circ (g \circ f))(x)$ and $((k \circ g) \circ f)(x)$ equal $k(g(f(x)))$.

So $C_{A,B}$ is a category, as claimed.

We can ask whether $C_{A,B}$ has *final* objects, that is, an object $(G, f_A, f_B) \in C_{A,B}$ where for any $(H, g_A, g_B) \in C_{A,B}$, $\mathrm{Hom}((H, g_A, g_B), (G, f_A, f_B))$ is a singleton. In fact, (C, π_A, π_B) is such an object. In other words, we will show that (C, π_A, π_B) must be the only group with this property since the axioms of groups and homomorphisms forces it to be.

Theorem 5.4.3: Universal Property Of The Product For Groups

Let A and B be groups. Then $A \times B$ is a group, and $\pi_A \colon A \times B \to A$ and $\pi_B \colon A \times B \to B$ are homomorphisms. For every group H and all homomorphisms $f_A \colon H \to A$ and $f_B \colon H \to B$, there exists a unique homomorphism $f \colon H \to A \times B$ such that $f_A = \pi_A \circ f$ and $f_B = \pi_B \circ f$. The homomorphism f is denoted $f_A \times f_B$.

***Proof*:**
The set $A \times B$ with the componentwise operation is a group, and π_A and π_B are homomorphisms (proposition 5.1.3). Next, let $(A \times B, \pi_A, \pi_B)$ be as above and let $(H, f_A, f_B) \in C_{A,B}$. Define

$$f : H \to A \times B \qquad f(h) = (f_A(h), f_B(h))$$

This f is a homomorphism because f_A and f_B are and the operation on $A \times B$ is componentwise. Also $(\pi_A \circ f)(h) = \pi_A(f_A(h), f_B(h)) = f_A(h)$, and similarly for f_B, showing that the diagram indeed comutes, and so f is indeed a morphism in $C_{A,B}$.

To show that f is unique, let's assume there is another morphism f'. Then

$$f_A(h) = (\pi_A \circ f')(h) = \pi_A(f'(h)) = \pi_A(f'(h)_A, f'(h)_B) = f'(h)_A$$

where $f'(h)_A$ and $f'(h)_B$ represent the components of $f'(h)$. Similarly, $f'(h)_B = f_B(h)$. Therefore, $f'(h) = (f_A(h), f_B(h))$. However, that is exactly what f does:


$$f(h) = (f_A(h), f_B(h)) = f'(h)$$

thus $f = f'$, showing uniqueness. Thus (C, π_A, π_B) is the final object of $C_{A,B}$. In other words, $A \times B$ respects the universal property of the product in Group.

We can further generalize this for an arbitrary direct product, that is if $(G_i)_{i \in I}$ is a family of groups, then their direct product $G = \prod_{i \in I} G_i$ along with $\pi_i : G \to G_i$ for every $i \in I$ will be a final object in $C_{(G_i)_{i \in I}}$.

Theorem 5.4.4: Universal Property For Arbitrary Direct Product Of Groups

Let $(G_i)_{i \in I}$ be a family of groups, let $G = \prod_{i \in I} G_i$ be their direct product, whose elements are the families $(g_i)_{i \in I}$ with $g_i \in G_i$ and whose operation is componentwise, and let $\pi_i \colon G \to G_i$ be the projections $\pi_i((g_j)_{j \in I}) = g_i$. For every group H, and every I-indexed family of homomorphisms $f_i : H \to G_i$, there exists a unique homomorphism $f \colon H \to G$ such that the following diagrams commute for every $i \in I$:



***Proof*:**
As in the proof of proposition 5.1.3, G is a group: the family $(1_{G_i})_{i\in I}$ is an identity, the family $(g_i^{-1})_{i\in I}$ is an inverse of $(g_i)_{i\in I}$, and associativity holds in each component. Each π_i is a homomorphism, since $\pi_i((g_j)_j(h_j)_j) = g_ih_i = \pi_i((g_j)_j)\pi_i((h_j)_j)$.

Define $f\colon H \to G$ by $f(h) = (f_i(h))_{i\in I}$. Since each f_i is a homomorphism and the operation of G is componentwise, $f(hh') = (f_i(h)f_i(h'))_{i\in I} = f(h)f(h')$, so f is a homomorphism. Also $\pi_i(f(h)) = f_i(h)$ for all $h \in H$, that is, $\pi_i \circ f = f_i$ for every $i \in I$.


Let $f'\colon H \to G$ be a homomorphism with $\pi_i \circ f' = f_i$ for every $i \in I$. For $h \in H$, the ith component of $f'(h)$ is $\pi_i(f'(h)) = f_i(h)$, which is the ith component of $f(h)$. So $f'(h) = f(h)$ for every h, and $f' = f$, completing the proof.

Exercise 5.4.1

1. Given that you have seen the universal property of products for groups, what do you think it would be for sets? What would be the generalization for an aribtary category? (For a hint, see the preliminary chapter or section 5.4)
2. let $1 \to A \to B \to C \to 1$ be an exact sequence. Show there exists an action $\rho : C \to \mathrm{Out}(A)$

5.4.1 The dual of the Product

What happens if you flip the arrows? Instead of looking at $C \xrightarrow{\pi_A} A$ and $C \xrightarrow{\pi_B} B$, we look at $A \xrightarrow{i'_A} C$ and $B \xrightarrow{i'_A} C$, and for all groups G, if we have $A \to G$ and $B \to G$, then there exists a homomorphism $f : C \to G$ such that the following diagram commutes



Does $(A \times B, i_A, i_B)$ where $i_A(a) = (a, 1)$ and $i_B(b) = (1, b)$ work? Let's break down the restrictions of this commutative diagram to check. By the above commutative diagram, we need that $f'_A(a) = F(i_A(a)) = F((a, 1))$ and that $f'_B(b) = F(i_B(b)) = F((1, b))$. So we have


$$F((a, 1))F((1, b)) = f'_A(a)f'_B(b)$$

Since F must be a homomorphism, then:


$$F((a, 1))F((1, b)) = F((a, 1)(1, b)) = F((a, b)) = F((1, b)(a, 1)) = F((1, b))F((a, 1))$$

that is $f'_A(a)f'_B(b) = f'_B(b)f'_A(a)$, that is, the image of A and B must always commute. However, we can see that there will exist a group G and homomorphisms f'_A f'_B where $f'_A(a)f'_B(b) \neq f'_B(b)f'_A(a)$:

Example 5.4.5: Counter-example
Let $A = \mathbb{Z}_2$ and $B = D_3$ so that we get



Let $G = D_3$, $f'_A : \mathbb{Z}_2 \to D_3$, $f'_A(x) = \sigma^x$, $f'_B : D_3 \to D_3$, $f'_B(x) = x$ (i.e. f'_B is the identity map). Then is it true that there exists a homomorphism F such that:



By definition $F((a,1)) = F(i_A(a)) = f'_A(a) = \sigma^a$ and $F((1,b)) = F(i_B(b)) = f'_B(b) = b$, so

$$F((a,b)) = \sigma^a b$$

and by what we just saw, we must also have that $F((a,b)) = b\sigma^a$ for every $a \in A$ and $b \in B$. However

$$F((1,2)) = \sigma r^2 \neq r^2 \sigma$$

showing that F is *not* a well-defined homomorphism!

Restricting to abelian groups removes this problem. When G is abelian, $F((a,b)) = f'_A(a)f'_B(b)$ is a homomorphism, since $F((a,b)(a',b')) = f'_A(a)f'_A(a')f'_B(b)f'_B(b') = f'_A(a)f'_B(b)f'_A(a')f'_B(b')$, and by the computation above it is the only homomorphism with $F \circ i_A = f'_A$ and $F \circ i_B = f'_B$. So $(A \times B, i_A, i_B)$ is the initial object in the category whose objects are triples (G, f_A, f_B) with G abelian and whose morphisms are the commutative diagrams above.

The problem here came from the extra structure of $A \times B$: by proposition 5.1.3(4), the copies of A and B inside $A \times B$ commute with each other, $(a,1)(1,b) = (1,b)(a,1)$.

So does there exist a group and maps will be the initial object in this category? The answer to this question is yes! It is a group we have not yet encountered. The main idea here is that this group is supposted to be the most generic way of having A and B (so as little relations btween A and B) so that the homomorphism from this group to any G does not preserve these properties. We have encountered a similar situation like this before when defining the *free group* (see section 2.3.3). Something analogous is defined called the *free product*.

Definition 5.4.6: Free Product

Let H and K be groups with presentations (S_H, R_H) and (S_K, R_K) (definition 3.2.2), where the generating sets S_H and S_K are disjoint. Then

$$H * K = \langle S_H \cup S_K | R_H \cup R_K \rangle$$

Example 5.4.7: Free Products

The free product $\mathbb{Z}/2\mathbb{Z} * \mathbb{Z}/2\mathbb{Z} = \langle x, y \big| x^2 = y^2 = 1 \rangle$ is the group of section 2.2.2 whose elements of finite order do not form a subgroup: x and y have order 2, but xy does not have finite order.

Exercise 5.4.2

1. Show that $(H * K, i_H, i_K)$ respects the universal property of the co-product in **Grp**.

Infinite abelian case

It should be mentioend again that if we restrict to **Ab**, then the universal property of the coproduct is fulfilled by $H \times K$, which differs from $H * K$ unless H or K is trivial. Is this also true in the infinite case: given abelian groups $G_1, G_2, \dots$, does $\prod_i G_i$ respect the universal property of the coproduct? The answer is no!

Example 5.4.8: The Product Is Not A Coproduct In Ab

Let $G = \prod_{i=1}^{\infty} \mathbb{Z}$, and let $\iota_i \colon \mathbb{Z} \to G$ send x to the sequence with x in position i and 0 elsewhere. Let $D \subseteq G$ be the set of sequences with only finitely many nonzero entries. It is a subgroup: it contains 0, and a difference of two such sequences is nonzero only where one of them is. Since G is abelian, $D \trianglelefteq G$ (corollary 3.1.12), and the quotient $H = G/D$ is an abelian group, with the projection $\pi \colon G \to H$ a homomorphism (definition 3.1.13). Take $f_i = 0 \colon \mathbb{Z} \to H$ for every i. Both the zero homomorphism $G \to H$ and π satisfy $F \circ \iota_i = 0 = f_i$ for every i, because $\iota_i(\mathbb{Z}) \subseteq D$. They are different: the sequence $(1, 1, 1, \dots)$ has infinitely many nonzero entries, so it does not lie in D, and $\pi((1, 1, 1, \dots)) \neq 0$. So the homomorphism F with $F \circ \iota_i = f_i$ for all i is not unique, and G with the maps ι_i does not have the universal property of the coproduct in **Ab**.

In the subgroup D of this example every element is a finite sum of elements $\iota_i(x_i)$, so a homomorphism out of D is determined by its composites with the ι_i. This is what makes D the coproduct, as theorem 5.4.10 below shows for any family.

A group still exists which can fix our scenario and respect the universal property for coproducts in the infinite case:

Definition 5.4.9: Direct Sum Of Groups

Let $\{A_i\}_{i\in I}$ be a family of groups. Then the *direct sum*

$$A = \bigoplus_{i\in I} A_i$$

is a subset of $\prod_{i\in I} A_i$ consisting of all elements $(x_i)_{i\in I}$ with $x_i \in A_i$ such that $x_i = 0$ for all but finitely many indices i (cofinitely many indices).

It is a subgroup of $\prod_{i\in I} A_i$: it contains the identity, and if (x_i) and (y_i) have $x_i = 0$ outside a finite set S and $y_i = 0$ outside a finite set T, then $(x_i - y_i)$ has $x_i - y_i = 0$ outside $S \cup T$. Note that in the finite case, $\bigoplus_{i=1}^n G_i = \prod_{i=1}^n G_i$. It only differs once we reach the infinite case

Theorem 5.4.10: Universal Property Of Coproducts In Ab

Let $(G_i)_{i\in I}$ be a family of abelian groups, written additively, let $G = \bigoplus_{i\in I} G_i$ (definition 5.4.9), and for $j \in I$ let $\iota_j \colon G_j \to G$ send z to the family with z in position j and 0 in every other position. Then G respects the universal property of the coproduct in **Ab**: for every abelian group H and every family of homomorphisms $f_i \colon G_i \to H$, there is a unique homomorphism $F \colon G \to H$ with $F \circ \iota_i = f_i$ for every $i \in I$.

***Proof*:**
By the remark after definition 5.4.9, G is a subgroup of $\prod_{i\in I} G_i$, so it is a group under the componentwise operation, and it is abelian since each G_i is. Each ι_j lands in G and is a homomorphism, since the operation is componentwise.

Step 1: definition of F. The *support* $\{i \in I \mid x_i \neq 0\}$ of $x = (x_i)_{i\in I} \in G$ is finite. For a finite set $S \subseteq I$ containing the support of x, put

$$F_S(x) = \sum_{i\in S} f_i(x_i)$$

a finite sum in the abelian group H, whose value does not depend on the order of its terms. It does not depend on S either. If $S \subseteq S'$, the extra terms $f_i(x_i)$ with $i \in S' \setminus S$ have $x_i = 0$, so they vanish because $f_i(0) = 0$ (proposition 1.4.4(1)). Any two admissible sets are contained in their union, so all the $F_S(x)$ agree, and we put $F(x) = F_S(x)$.

Step 2: F is the required homomorphism. Let $x, y \in G$, and let S be the union of their supports, which also contains the support of $x + y$. Since each f_i is a homomorphism and H is abelian,

$$F(x+y) = \sum_{i\in S} f_i(x_i + y_i) = \sum_{i\in S} f_i(x_i) + \sum_{i\in S} f_i(y_i) = F(x) + F(y)$$

For $j \in I$ and $z \in G_j$, the support of $\iota_j(z)$ is contained in $\{j\}$, so $F(\iota_j(z)) = f_j(z)$, that is, $F \circ \iota_j = f_j$.

Step 3: uniqueness. Let $x \in G$ have support contained in the finite set S. Then $x = \sum_{i\in S} \iota_i(x_i)$,

since both sides have ith component x_i for $i \in S$ and 0 for $i \notin S$. If $F' \colon G \to H$ is a homomorphism with $F' \circ \iota_i = f_i$ for every i, then

$$F'(x) = \sum_{i \in S} F'(\iota_i(x_i)) = \sum_{i \in S} f_i(x_i) = F(x)$$

so $F' = F$, as we sought to show.

5.4.2 Universal Property of Semi-Direct Products

Every element (h, k) of $H \rtimes_\varphi K$ is the product $(h, 1)(1, k)$, so a homomorphism out of $H \rtimes_\varphi K$ is determined by its values on the two factors.

Proposition 5.4.11: Universal Property Of The Semi-Direct Product

Let H and K be groups, let $\varphi \colon K \to \mathrm{Aut}(H)$ be a homomorphism, let $G = H \rtimes_\varphi K$ (definition 5.3.2), and let $\iota_H(h) = (h, 1)$ and $\iota_K(k) = (1, k)$. Let L be a group.

1. If $F \colon G \to L$ is a homomorphism, then $f = F \circ \iota_H$ and $g = F \circ \iota_K$ are homomorphisms with
$$g(k)f(h)g(k)^{-1} = f(\varphi(k)(h)) \qquad \text{for all } h \in H,\ k \in K$$
2. Conversely, if $f \colon H \to L$ and $g \colon K \to L$ are homomorphisms satisfying this condition, then there is a unique homomorphism $F \colon G \to L$ with $F \circ \iota_H = f$ and $F \circ \iota_K = g$, namely $F(h, k) = f(h)g(k)$.

***Proof*:**
The maps ι_H and ι_K are homomorphisms by proposition 5.3.3(2). Every automorphism of H fixes 1 (proposition 1.4.4(1)), so the multiplication of definition 5.3.2 gives, for $h \in H$ and $k \in K$,

$$(h, 1)(1, k) = (h, k) \qquad (1, k)(h, 1) = (\varphi(k)(h), k) = (\varphi(k)(h), 1)(1, k)$$

1. The maps f and g are composites of homomorphisms, hence homomorphisms (proposition 1.4.4(6)). Applying F to the second identity gives $g(k)f(h) = f(\varphi(k)(h))g(k)$, which is the condition.
2. If F is such a homomorphism, the first identity gives $F(h, k) = F(h, 1)F(1, k) = f(h)g(k)$, which proves uniqueness. For existence, put $F(h, k) = f(h)g(k)$. Then $F(h, 1) = f(h)$ and $F(1, k) = g(k)$, and for $(h_1, k_1), (h_2, k_2) \in G$ the condition gives
$$F((h_1, k_1)(h_2, k_2)) = f(h_1)f(\varphi(k_1)(h_2))g(k_1)g(k_2) = f(h_1)g(k_1)f(h_2)g(k_2)$$
which is $F(h_1, k_1)F(h_2, k_2)$. So F is a homomorphism, as claimed.

When φ is trivial, G is the direct product $H \times K$, and the condition says that every $f(h)$ commutes with every $g(k)$. So the homomorphisms out of $H \times K$ correspond to the pairs of homomorphisms out of H and K whose images commute elementwise. This is a property of maps out of $H \times K$, while theorem 5.4.3 describes maps into it.

A group can be a semi-direct product in several ways. In D_6, with the rotation r and reflection s of proposition 1.2.29, the rotations $\langle r \rangle \cong C_6$ have index 2, hence form a normal subgroup (corollary 3.3.6), with complement $\langle s \rangle$, so $D_6 \cong C_6 \rtimes C_2$ (theorem 5.3.7). Also, r^2 has order 3 and $sr^2s^{-1} = r^{-2}$ (proposition 1.2.29), so $\langle r^2, s \rangle = \{1, r^2, r^4, s, sr^2, sr^4\}$ is a copy of D_3 of index 2, hence normal. The center $\langle r^3 \rangle \cong C_2$ is normal, the two meet trivially, and $6 \cdot 2 = 12$, so $D_6 \cong D_3 \times C_2$ (theorem 5.2.6), a semi-direct product with trivial action. In general, $G \cong H \rtimes K$ exactly when H is a normal subgroup with a complement K (theorem 5.3.7 and proposition 5.3.3).

Exercise 5.4.3

1. Show that $\mathrm{GL}_n(F) \cong \mathrm{SL}_n(F) \rtimes F^\times$ for every field F and every $n \geq 1$.

6

Further Topics in Group Theory

Two subgroups measure how far a group is from being abelian: the commutator subgroup, which is trivial exactly when the group is abelian, and the center, which is the whole group exactly when the group is abelian. Iterating the commutator subgroup leads to metabelian and solvable groups, iterating the center leads to nilpotent groups, and subnormal series with cyclic factors lead to polycyclic groups.

6.1 Generalization of Abelian Groups

So far we saw that

$$\text{cyclic} \Rightarrow \text{Abelian}$$

We found a way to find how close agroup is to being abelian using commutator groups. If $G' = \{1\}$, then G is abelian. Otherwise, G is not abelian. We will develop further generalization's from this concept.

Definition 6.1.1: Metabelian Group

Let G be a group. If $G'' = (G')' = \{1\}$, we say that G is a *metabelian* group

Proposition 6.1.2: Properties Of Metabelian Groups

Let G be a metabelian group. Then

1. any subgroup is metabelian
2. If $\varphi : G \to H$ is a homomorphism, then $\varphi(G)$ is metabelian

***Proof*:**

1. Let $H \leqslant G$. Every commutator of elements of H is a commutator of elements of G, so it lies in G', and $H' \leqslant G'$ by proposition 2.3.17. Applying this to the subgroup H' of the group G' gives $H'' \leqslant G'' = \{1\}$, so H is metabelian.
2. Let $\varphi : G \to H$ be a homomorphism and G a metabelian group, and consider $\varphi(G) \leqslant H$. We will show that homomorphisms preserve commutator subgroups to show that $\varphi(G)$ is metabelian. In particular, if $N \leqslant G$, then $\varphi(N') = \varphi(N)'$. Indeed, $\varphi([x, y]) = [\varphi(x), \varphi(y)]$ for $x, y \in N$, so the commutators of elements of $\varphi(N)$ are exactly the images of the commutators of elements of N. The image $\varphi(N')$ is a subgroup (proposition 1.4.4(5)) containing all of them, so $\varphi(N)' \leqslant \varphi(N')$ by proposition 2.3.17. The preimage $\varphi^{-1}(\varphi(N)')$ is a subgroup of G by proposition 2.1.3, since $\varphi(xy^{-1}) = \varphi(x)\varphi(y)^{-1}$, and it contains every commutator of elements of N, so it contains N', which gives $\varphi(N') \leqslant \varphi(N)'$. Thus

$$\varphi(G)'' = \varphi(G')' = \varphi(G'') = \varphi(\{1\}) = \{1\}$$

and so $\varphi(G)$ is also metabelian.

Example 6.1.3: Metabelian Groups

1. Any abelian group is always metabelian
2. if A and B are abelian groups, and $A \rtimes B$ is well-defined, then $A \rtimes B$ is metabelian.

Proposition 6.1.4: Extension of Abelian Groups

A group G is metabelian if and only if it has an abelian normal subgroup A with G/A abelian, that is, if and only if G is an extension of an abelian group by an abelian group:

$$1 \longrightarrow A \longrightarrow G \longrightarrow M \longrightarrow 1$$

with A and M abelian.

***Proof*:**
Let $A \trianglelefteq G$ be abelian with G/A abelian. By proposition 5.2.3(4), $G' \subseteq A$, so G' is abelian and $G'' = 1$. Conversely, let $G'' = 1$, so that G' is abelian. It is normal: for $g \in G$ and $h \in G'$, $ghg^{-1} = (ghg^{-1}h^{-1})h \in G'$. By proposition 5.2.3(4), G/G' is abelian, so $A = G'$ works, completing the proof.

6.1.1 Solvable Groups

Metabelian groups are a simple example of a group called a *solvable* group. Instead of looking at the 2nd commutator subgroup being trivial, we can ask if the nth commutator subgroup will be trivial:

Definition 6.1.5: nth Commutator Group

Let G be a group. Put $G_{(0)} = G$, and for $n \geq 1$ let

$$G_{(n)} = [G_{(n-1)}, G_{(n-1)}] = (G_{(n-1)})'$$

the subgroup generated by the commutators $[a, b]$ with $a, b \in G_{(n-1)}$ (definition 5.2.2). It is called the nth commutator group, and $G_{(1)} = G'$.

Definition 6.1.6: Solvable Groups

A group G is *solvable* if there is a subnormal series with commutator subgroup:

$$G = G_{(0)} \trianglerighteq G_{(1)} \trianglerighteq G_{(2)} \trianglerighteq \cdots \trianglerighteq G_{(n)} = \{1\}$$

such a subnormal series is called the *derived series*. If $G_{(n)} = 1$, we say G has *solvable length* n.

Example 6.1.7: Solvable Groups

1. Every abelian group is solvable, since $1 \trianglelefteq G$ is a normal series.
2. Any metabelian group is solvable, with the series is called the *derived series of* G.

$$1 = G'' \trianglelefteq G' \trianglelefteq G$$

Since G/G' is abelian, and $G'/G'' \cong G'$ which is abelian.

There are equivalent definitions of solvability that are worth keeping in mind to have a variety of intuitions.

Lemma 6.1.8: characteristic of nth commutator

Let G be a group. Then $G_{(i+1)}$ char $G_{(i)}$ for any $i \in \mathbb{N}$. Consequently, $G_{(i+1)} \trianglelefteq G_{(i)}$.

***Proof*:**
By definition 6.1.5, $G_{(i+1)}$ is the commutator subgroup of the group $G_{(i)}$, so proposition 5.2.3(3), applied to the group $G_{(i)}$, gives $G_{(i+1)}$ char $G_{(i)}$, and $G_{(i+1)} \trianglelefteq G_{(i)}$ by proposition 4.7.13(1).

Normality can also be proved directly. Every commutator of elements of $G_{(i)}$ lies in $G_{(i)}$, so $G_{(i+1)} \leqslant G_{(i)}$ by proposition 2.3.17. Let $g \in G_{(i)}$ and $h \in G_{(i+1)}$. Then $h \in G_{(i)}$, so

$ghg^{-1}h^{-1} = [g^{-1}, h^{-1}]$ is a commutator of elements of $G_{(i)}$ and lies in $G_{(i+1)}$, and hence

$$ghg^{-1} = (ghg^{-1}h^{-1})h \in G_{(i+1)}$$

Thus $gG_{(i+1)}g^{-1} \subseteq G_{(i+1)}$ for every $g \in G_{(i)}$, and $G_{(i+1)} \trianglelefteq G_{(i)}$ by proposition 3.1.11(5), as claimed.

Theorem 6.1.9: Equivalent Definitions Of Solvable group

Let G be a group. The following are equivalent

1. G is solvable
2. There exists a subnormal series

$$G = A_0 \trianglerighteq A_1 \trianglerighteq A_2 \trianglerighteq \cdots \trianglerighteq A_n = \{1\}$$

such that A_i/A_{i+1} is abelian for $0 \leq i < n$. Such a subnormal series is called a *subnormal series with abelian factors.*

***Proof*:**
For a group A and a normal subgroup M of A, the quotient A/M is abelian if and only if $A' \leqslant M$. Indeed, for $x, y \in A$ the cosets xM and yM commute exactly when $(yx)^{-1}xy = [x, y] \in M$, and M contains every commutator of elements of A exactly when it contains the subgroup A' that they generate (proposition 2.3.17).

(1) $\Rightarrow$ (2) Let $G_{(n)} = 1$. By lemma 6.1.8, $G = G_{(0)} \trianglerighteq G_{(1)} \trianglerighteq \cdots \trianglerighteq G_{(n)} = 1$ is a subnormal series. Each factor $G_{(i)}/G_{(i+1)}$ is abelian by the first paragraph, applied to $A = G_{(i)}$ and $M = G_{(i+1)} = A'$.

(2) $\Rightarrow$ (1) Let (A_i) be a subnormal series with abelian factors. We show $G_{(i)} \leqslant A_i$ by induction on i. For $i = 0$ both are G. If $G_{(i)} \leqslant A_i$, then every commutator of elements of $G_{(i)}$ is a commutator of elements of A_i, so $G_{(i+1)} \leqslant (A_i)'$ by proposition 2.3.17. The first paragraph, applied to $A = A_i$ and $M = A_{i+1}$, gives $(A_i)' \leqslant A_{i+1}$, since A_i/A_{i+1} is abelian. So $G_{(i+1)} \leqslant A_{i+1}$. Hence $G_{(n)} \leqslant A_n = 1$, and G is solvable, as claimed.

The use of the 2nd definition is to show that finding any solvable series for a group is enough to show a group is solvable. The advantage of the 1st definition is that it is the most refined solvable series of a group, since the commutator subgroup is smallest subgroup which makes the quotients A_i/A_{i+1} abelian.

Proposition 6.1.10: Properties Of Solvable Groups

Let G be solvable. Then

1. subgroups of solvable groups are solvable
2. if $\varphi : G \to H$ is a homomorphism, then $\varphi(G)$ is solvable
3. if M is a group with a normal subgroup N such that N and M/N are solvable, that is, if M is an extension of a solvable group by a solvable group, then M is solvable.

***Proof*:**
Let $G_{(n)} = 1$.

1. Let $H \leqslant G$. We show $H_{(i)} \leqslant G_{(i)}$ by induction on i. For $i = 0$ this is $H \leqslant G$. If $H_{(i)} \leqslant G_{(i)}$, then every commutator of elements of $H_{(i)}$ is a commutator of elements of $G_{(i)}$, so $H_{(i+1)} \leqslant G_{(i+1)}$ by proposition 2.3.17. Hence $H_{(n)} \leqslant G_{(n)} = 1$, and H is solvable.
2. First, $\psi(A') = \psi(A)'$ for every homomorphism ψ and every subgroup A of its domain. Indeed, $\psi([x, y]) = [\psi(x), \psi(y)]$, so the commutators of elements of $\psi(A)$ are the images of the commutators of elements of A. The image $\psi(A')$ is a subgroup (proposition 1.4.4(5)) containing all of them, so $\psi(A)' \leqslant \psi(A')$ by proposition 2.3.17. The preimage of $\psi(A)'$ is a subgroup by proposition 2.1.3, since $\psi(xy^{-1}) = \psi(x)\psi(y)^{-1}$, and it contains every commutator of elements of A, so it contains A', which gives $\psi(A') \leqslant \psi(A)'$. Induction on i now gives $\varphi(G_{(i)}) = \varphi(G)_{(i)}$, so $\varphi(G)_{(n)} = \varphi(1) = 1$, and $\varphi(G)$ is solvable.
3. Let $N \trianglelefteq M$ with $N_{(l)} = 1$ and $(M/N)_{(k)} = 1$, and let $\pi\colon M \to M/N$ be the projection, a surjective homomorphism with kernel N (definition 3.1.13). By the first sentence of (2), induction on i gives $\pi(M_{(i)}) = (M/N)_{(i)}$, so $\pi(M_{(k)}) = 1$ and $M_{(k)} \leqslant N$. Induction on j from definition 6.1.5 gives $(M_{(k)})_{(j)} = M_{(k+j)}$. The argument of (1), applied to the subgroup $M_{(k)}$ of N, gives $M_{(k+l)} = (M_{(k)})_{(l)} \leqslant N_{(l)} = 1$. So M is solvable, completing the proof.

Corollary 6.1.11: Finite P-Groups

Let G be a finite p-group. Then G is solvable.

***Proof*:**
We use strong induction on $|G|$. If $|G| = 1$, then $G_{(0)} = G = 1$. Let $|G| > 1$. By theorem 4.6.5, $Z(G) \neq 1$, and $Z(G)$ is normal in G (example 3.1.10). The quotient $G/Z(G)$ is a p-group of order $|G|/|Z(G)| < |G|$ (theorem 3.3.1), so it is solvable by the induction hypothesis. The group $Z(G)$ is abelian, so all its commutators equal 1, $Z(G)' = 1$, and $Z(G)$ is solvable. By proposition 6.1.10(3), G is solvable, as claimed.

One more theorem gives a sufficient condition for solvability:

Theorem 6.1.12: Feit-Thompson's Theorem

Let G be a finite group of odd order. Then G is solvable.

The proof of theorem 6.1.12 occupies a journal article of 255 pages and combines the local analysis of finite groups with character theory, which this book does not develop. It is due to W. Feit and J. G. Thompson, *Solvability of groups of odd order* [50].

***Proof Key ideas*:**
A counterexample of smallest order is a nonabelian simple group G of odd order in which every proper subgroup is solvable. Indeed, every proper subgroup has smaller odd order, and a proper nontrivial normal subgroup N would make N and G/N solvable, hence G solvable by proposition 6.1.10(3). Abelian groups are solvable, so G is nonabelian. The proof determines the possible structure of the maximal subgroups of such a G by local analysis, the study of the normalizers of nontrivial p-subgroups, and combines this with character theory to show that no such G exists, completing the outline.

Consequently, a finite group that is not solvable has even order, so it has an element of order 2 by theorem 4.8.7.

Theorem 6.1.13: Solvability Condition

A finite group G is solvable if and only if for every divisor n of $|G|$ such that $\left(n, \frac{|G|}{n}\right) = 1$, G has a subgroup of order n.

Both directions of theorem 6.1.13, which is due to P. Hall, need tools this book does not develop. That a solvable group has these subgroups rests on the Schur-Zassenhaus theorem, which gives a complement to a normal subgroup whose order is coprime to its index. The converse rests on Burnside's theorem that groups of order $p^a q^b$, for primes p and q, are solvable, and the standard proof of Burnside's theorem uses character theory. Both directions are proved in Robinson, *A Course in the Theory of Groups* [86, Theorems 9.1.7 and 9.1.8]. Robinson's Theorem 9.1.8 and [48, Section 19.2, Theorem 8] both prove the converse in a stronger form, which assumes only the subgroups whose index is the order of a Sylow subgroup.

***Proof Key ideas*:**
Suppose G is solvable and $(n, |G|/n) = 1$, and argue by induction on $|G|$. A minimal normal subgroup M of a solvable group is a p-group for some prime p, say of order p^k. If p divides n, then p^k divides n, and induction gives a subgroup of G/M of order n/p^k, whose preimage in G has order n. If p does not divide n, induction gives a subgroup K/M of G/M of order n, and the Schur-Zassenhaus theorem gives a complement to M in K, which is a subgroup of order n.

Conversely, suppose G has all these subgroups, in particular, for every prime p, a subgroup whose index is the largest power of p dividing $|G|$. These subgroups pass to normal subgroups and to quotients, so a counterexample of smallest order is simple. If at most two primes divide $|G|$, Burnside's theorem shows that G is solvable. Otherwise, the intersection of these subgroups for all but two of the primes has order divisible by only two primes, so it is solvable by Burnside's theorem, and a minimal normal subgroup of it produces a proper nontrivial normal subgroup of

G, contradicting simplicity and completing the outline.

6.1.2 Nilpotent Groups

We have defined solvable groups using nth commutator groups to give a notion of generalization from being commutative. What if we used the center instead? Since $Z(G) \trianglelefteq G$, the quotient $G/Z(G)$ is a group, and the elements of G whose cosets lie in its center form a subgroup of G containing $Z(G)$. Repeating this gives the *upper central series*: $Z^0(G) = 1$, and $Z^{i+1}(G)$ is the set of $g \in G$ whose coset $gZ^i(G)$ lies in $Z(G/Z^i(G))$. Since $gZ^i(G)$ commutes with $xZ^i(G)$ exactly when $[g,x] = g^{-1}x^{-1}gx \in Z^i(G)$ (definition 5.2.2),

$$Z^{i+1}(G) = \left\{ g \in G \;\middle|\; [g,x] \in Z^i(G) \text{ for all } x \in G \right\}$$

So $Z^1(G) = Z(G)$ and $Z^i(G) \subseteq Z^{i+1}(G)$. By induction each $Z^i(G)$ is a normal subgroup of G, being the preimage P of the normal subgroup $Z(G/Z^{i-1}(G))$ (example 3.1.10) under the canonical projection $\pi\colon G \to G/Z^{i-1}(G)$: for $g \in G$ and $p \in P$, $\pi(gpg^{-1}) = \pi(g)\pi(p)\pi(g)^{-1}$ lies in that normal subgroup, so $gpg^{-1} \in P$. So the next quotient is defined. A group whose upper central series reaches G is called *nilpotent*:

Definition 6.1.14: Nilpotent Groups

Let G be a group. If $Z^m(G) = G$ for some $m \in \mathbb{N}$, then G is said to be nilpotent. The smallest such m is called the *(nilpotency) class of* G.

Example 6.1.15: Nilpotent Groups

1. If G is abelian, then $Z(G) = G$, meaning all abelian groups are nilpotent
2. A metabelian group need not be nilpotent. In S_3, every commutator $\sigma^{-1}\tau^{-1}\sigma\tau$ is an even permutation, since by theorem 1.2.20(2) its sign is $\operatorname{sgn}(\sigma)^{-1}\operatorname{sgn}(\tau)^{-1}\operatorname{sgn}(\sigma)\operatorname{sgn}(\tau) = 1$ (definition 1.2.21). So $S_3' \subseteq A_3$, which has order 3 and is abelian (corollary 3.3.2), and $S_3'' = 1$, so S_3 is metabelian. But $Z(S_3) = 1$, since each transposition fails to commute with the other two transpositions and each 3-cycle fails to commute with (1 2). So $Z^i(S_3) = 1$ for every i, and S_3 is not nilpotent.
3. Every finite p-group G is nilpotent. If $Z^i(G) \neq G$, then $G/Z^i(G)$ is a nontrivial p-group, so its center $Z^{i+1}(G)/Z^i(G)$ is nontrivial by theorem 4.6.5, and $Z^i(G) \neq Z^{i+1}(G)$. The orders $|Z^i(G)|$ therefore increase strictly until $Z^i(G) = G$, which happens after at most a steps if $|G| = p^a$.
4. This is not so much an example as future motivation: Nilpotent groups make an appearance in the classification of Lie Groups.

Proposition 6.1.16: Equivalent Definition

Let G be a group, and define its *lower central series* by $G_0 = G$ and $G_i = [G, G_{i-1}]$ for $i \geq 1$, the subgroup generated by the commutators $[g, h]$ with $g \in G$ and $h \in G_{i-1}$ (definition 5.2.2). The following are equivalent:

1. G is nilpotent (its upper central series reaches G)
2. The lower central series reaches the trivial group, that is, for some n
$$G = G_0 \trianglerighteq G_1 \trianglerighteq G_2 \trianglerighteq \cdots \trianglerighteq G_n = \{1\}$$
3. There exists a *central series*, that is, a chain of subgroups
$$G = A_0 \geqslant A_1 \geqslant \cdots \geqslant A_n = \{1\}$$
with $[G, A_i] \leqslant A_{i+1}$ for $0 \leq i < n$, or equivalently, with every A_i normal in G and $A_i/A_{i+1} \leqslant Z(G/A_{i+1})$ for $0 \leq i < n$

***Proof*:**

First, by the description of $Z^{i+1}(G)$ before definition 6.1.14, an element y lies in $Z^{i+1}(G)$ exactly when $[y, x] \in Z^i(G)$ for all $x \in G$, and since $[x, y] = [y, x]^{-1}$ and $Z^i(G)$ is a subgroup, exactly when $[x, y] \in Z^i(G)$ for all $x \in G$. Second, a subgroup containing a set contains the subgroup that the set generates (proposition 2.3.17). Third, each G_i is normal in G and $G_{i+1} \leqslant G_i$, which we prove by induction on i. For $i = 0$, $G_0 = G \trianglelefteq G$. Suppose $G_i \trianglelefteq G$ and let $x \in G$. Conjugation by x is an automorphism of G (proposition 4.7.1), so $x[g, h]x^{-1} = [xgx^{-1}, xhx^{-1}]$ by proposition 5.2.3(3), and $xhx^{-1} \in G_i$ when $h \in G_i$. So the preimage of G_{i+1} under conjugation by x, which is a subgroup by proposition 2.1.3 because conjugation is a homomorphism, contains every generator of G_{i+1}, hence contains G_{i+1} by the second fact. Thus $xG_{i+1}x^{-1} \subseteq G_{i+1}$ for every $x \in G$, and $G_{i+1} \trianglelefteq G$ by proposition 3.1.11. Each generator $[g, h] = (g^{-1}h^{-1}g)h$ with $h \in G_i$ lies in G_i because $G_i \trianglelefteq G$, so $G_{i+1} \leqslant G_i$, and then $G_{i+1} \trianglelefteq G_i$.

(1) ⇒ (2) Let $Z^m(G) = G$. We show $G_i \leqslant Z^{m-i}(G)$ for $0 \leq i \leq m$ by induction on i. For $i = 0$ both sides are G. If $G_i \leqslant Z^{m-i}(G)$ with $i < m$, then each generator $[g, h]$ of G_{i+1} has $h \in Z^{m-i}(G)$, so $[g, h] \in Z^{m-i-1}(G)$ by the first fact, and $G_{i+1} \leqslant Z^{m-i-1}(G)$ by the second. For $i = m$ this gives $G_m \leqslant Z^0(G) = 1$, so (2) holds with $n = m$.

(2) ⇒ (3) If $G_n = 1$, then $A_i = G_i$ is a central series, since $G_{i+1} \leqslant G_i$ by the third fact and $[G, G_i] = G_{i+1}$.

(3) ⇒ (1) Let (A_i) be a central series. We show $A_{n-j} \leqslant Z^j(G)$ for $0 \leq j \leq n$ by induction on j. For $j = 0$, $A_n = 1 = Z^0(G)$. If $A_{n-j} \leqslant Z^j(G)$ with $j < n$, let $y \in A_{n-j-1}$. For every $x \in G$, $[x, y] \in [G, A_{n-j-1}] \leqslant A_{n-j} \leqslant Z^j(G)$, so $y \in Z^{j+1}(G)$ by the first fact. Hence $A_{n-j-1} \leqslant Z^{j+1}(G)$. For $j = n$ this gives $G = A_0 \leqslant Z^n(G)$, so G is nilpotent.

It remains to see that the two descriptions of a central series in (3) agree. Suppose $[G, A_i] \leqslant A_{i+1}$ for $0 \leq i < n$. For $g \in G$ and $h \in A_i$ with $i < n$, $ghg^{-1} = h[h, g^{-1}]$ and $[h, g^{-1}] = [g^{-1}, h]^{-1} \in [G, A_i] \leqslant A_{i+1} \leqslant A_i$, so $ghg^{-1} \in A_i$. Hence every A_i is normal in G by proposition 3.1.11, the

last one being trivial. Now let $A_{i+1} \trianglelefteq G$. The cosets gA_{i+1} and hA_{i+1} commute exactly when $(hg)^{-1}gh = [g,h] \in A_{i+1}$, so $A_i/A_{i+1} \leqslant Z(G/A_{i+1})$ holds exactly when $[g,h] \in A_{i+1}$ for all $g \in G$ and $h \in A_i$. By the second fact this is the condition $[G, A_i] \leqslant A_{i+1}$, completing the proof.

With the lower central series, we can gain an intuition on why the group is called nilpotent. Let G be any group and $g \in G$ be any element. Define the *adjoint action*

$$\mathrm{ad}_g : G \to G \qquad \mathrm{ad}_g(x) = [g,x]$$

If G is nilpotent of class c, then $(\mathrm{ad}_g)^c(x) = e$ for all $g, x \in G$. Indeed, by the description of $Z^{i+1}(G)$ before definition 6.1.14, $[g,y] = [y,g]^{-1}$ lies in $Z^i(G)$ whenever $y \in Z^{i+1}(G)$, so ad_g maps $Z^{i+1}(G)$ into $Z^i(G)$. Starting from $x \in G = Z^c(G)$ and applying ad_g c times therefore lands in $Z^0(G) = 1$. In this sense each ad_g is nilpotent. A group in which every pair g, x satisfies $(\mathrm{ad}_g)^n(x) = e$ for some n, where n may depend on g and x, is called an *Engel group*. Every nilpotent group of class c is an Engel group, with the single exponent $n = c$ for all pairs, but an Engel group need not be nilpotent.

Example 6.1.17: An Engel Group That Is Not Nilpotent

For $k \geq 2$ let $P_k = D_{2^k}$, the dihedral group of the regular 2^k-gon, with the rotation r_k of order 2^k and a reflection s_k (proposition 1.2.29). Let G be the set of sequences $(y_k)_{k\geq 2}$ with $y_k \in P_k$ and $y_k = 1$ for all but finitely many k. The argument after definition 5.4.9, written multiplicatively, shows that G is a subgroup of the direct product $\prod_{k\geq 2} P_k$, so its operation and its commutators are computed componentwise.

1. G is an Engel group. Let $g, x \in G$, and choose $K \geq 2$ with $g_k = x_k = 1$ for every $k > K$. The elements of G equal to 1 in every position $k > K$ form a subgroup G_K containing g and x. An element of G_K is determined by its entries in positions $2, \ldots, K$, so by proposition 1.2.30

$$|G_K| = \prod_{k=2}^{K} |P_k| = \prod_{k=2}^{K} 2^{k+1}$$

   Thus G_K is a finite 2-group, hence nilpotent of some class c (example 6.1.15), and the computation above, carried out inside G_K, gives $(\mathrm{ad}_g)^c(x) = e$.

2. G is not nilpotent. In P_k, proposition 1.2.29 gives $s_k^{-1} = s_k$ and $r_k^i s_k = s_k r_k^{-i}$, so $s_k r_k^i s_k = r_k^{-i}$ for every $i \geq 0$, hence for every integer i since $r_k^{2^k} = 1$. Therefore $\mathrm{ad}_{s_k}(r_k^j) = s_k r_k^{-j} s_k r_k^j = r_k^{2j}$, and by induction on m, $(\mathrm{ad}_{s_k})^m(r_k) = r_k^{2^m}$ for every $m \geq 0$. Suppose G were nilpotent of class c, and choose $k \geq 2$ with $k > c$. Let g and x be the elements of G with s_k, respectively r_k, in position k and 1 in every other position. The entry of $(\mathrm{ad}_g)^c(x)$ in position k is $r_k^{2^c}$, which is not 1, because $0 < 2^c < 2^k$ and r_k has order 2^k. This contradicts $(\mathrm{ad}_g)^c(x) = e$, so G is not nilpotent.

Proposition 6.1.18: Nilpotent Then Solvable

Let G be a nilpotent group. Then G is solvable

***Proof*:**
Let $G_0 = G, G_1, G_2, \dots$ be the lower central series of G (proposition 6.1.16), and let $G_{(0)} = G$ and $G_{(i+1)} = (G_{(i)})'$ be the derived series (definition 6.1.5), so that $G_{(i+1)}$ is generated by the commutators $[a, b]$ with $a, b \in G_{(i)}$ (definition 5.2.2). We show $G_{(i)} \leqslant G_i$ by induction on i. For $i = 0$ both are G. If $G_{(i)} \leqslant G_i$, then every generator $[a, b]$ of $G_{(i+1)}$ has $a \in G$ and $b \in G_{(i)} \subseteq G_i$, so it is one of the generators of $G_{i+1} = [G, G_i]$, and $G_{(i+1)} \leqslant G_{i+1}$ by proposition 2.3.17. Since G is nilpotent, $G_n = 1$ for some n by proposition 6.1.16. Then $G_{(n)} = 1$, so G is solvable (definition 6.1.6), as claimed.

Note that the converse is not true

Example 6.1.19: Solvable, but not Nilpotent
Let

$$G = \left\{ \begin{pmatrix} a & b \\ 0 & c \end{pmatrix} \;\middle|\; a, b, c \in \mathbb{R},\ ac \neq 0 \right\} \subseteq GL_2(\mathbb{R})$$

The product and the inverse of elements of G are

$$\begin{pmatrix} a & b \\ 0 & c \end{pmatrix} \begin{pmatrix} a' & b' \\ 0 & c' \end{pmatrix} = \begin{pmatrix} aa' & ab' + bc' \\ 0 & cc' \end{pmatrix} \qquad \begin{pmatrix} a & b \\ 0 & c \end{pmatrix}^{-1} = \begin{pmatrix} a^{-1} & -b(ac)^{-1} \\ 0 & c^{-1} \end{pmatrix}$$

so $I \in G$ and $xy^{-1} \in G$ for all $x, y \in G$, and $G \leqslant GL_2(\mathbb{R})$ by proposition 2.1.3.

The diagonal map. By the product formula, the map $\delta \colon G \to \mathbb{R}^\times \times \mathbb{R}^\times$ sending the matrix above to (a, c) is a homomorphism into an abelian group. It is surjective, since it sends the diagonal matrix with diagonal entries a, c to (a, c), and its kernel is

$$H = \left\{ \begin{pmatrix} 1 & b \\ 0 & 1 \end{pmatrix} \;\middle|\; b \in \mathbb{R} \right\}$$

So $H \trianglelefteq G$ (proposition 3.1.14) and $G/H \cong \mathbb{R}^\times \times \mathbb{R}^\times$ (corollary 3.1.17). By the product formula, $b \mapsto \begin{pmatrix} 1 & b \\ 0 & 1 \end{pmatrix}$ is an isomorphism from $(\mathbb{R}, +)$ onto H, so H is abelian. By proposition 5.2.3(5), $G' \leqslant \ker(\delta) = H$.

The center. Let $g = \begin{pmatrix} a & b \\ 0 & c \end{pmatrix} \in Z(G)$. By the product formula,

$$g \begin{pmatrix} 1 & 1 \\ 0 & 1 \end{pmatrix} = \begin{pmatrix} a & a + b \\ 0 & c \end{pmatrix} \qquad \begin{pmatrix} 1 & 1 \\ 0 & 1 \end{pmatrix} g = \begin{pmatrix} a & b + c \\ 0 & c \end{pmatrix}$$

so $a = c$. In the same way, g times the diagonal matrix d with diagonal entries $1, 2$ has upper right entry $2b$, while dg has upper right entry b, so $b = 0$. Conversely, the scalar matrices aI with $a \neq 0$ commute with every matrix. Hence

$$Z(G) = \{aI \mid a \in \mathbb{R},\ a \neq 0\}$$

G is not nilpotent. The only scalar matrix in H is I, so $Z(G) \cap H = \{I\}$. Let $g \in Z^2(G)$. For every $x \in G$, the commutator $[g, x]$ lies in $Z(G)$ by the description of $Z^2(G)$ before definition 6.1.14, and in $G' \leqslant H$, so $[g, x] = I$ and $gx = xg$. Hence $Z^2(G) = Z(G)$. If $Z^i(G) = Z(G)$ for some $i \geq 1$, then $Z^{i+1}(G)$ is the set of $g \in G$ with $[g, x] \in Z(G)$ for all $x \in G$, which is $Z^2(G) = Z(G)$. By

induction, $Z^i(G) = Z(G)$ for every $i \geq 1$. Since $\begin{pmatrix} 1 & 1 \\ 0 & 1 \end{pmatrix}$ is not scalar, $Z(G) \neq G$, so no $Z^m(G)$ equals G, and G is not nilpotent (definition 6.1.14).

G is solvable. The subgroup G' lies in the abelian group H, so it is abelian, and $G'' = (G')' = \{I\}$ by example 5.2.4. So the derived series $G \trianglerighteq G' \trianglerighteq G'' = \{I\}$ reaches the identity, and G is solvable (definition 6.1.6).

Another example is S_3, which is solvable but not nilpotent by example 6.1.15(2) and example 6.1.7(2). The subgroup A_3 has order 3 by example 3.5.2(1), so it has index 2 and is normal (corollary 3.3.6), and it meets $\langle(1\ 2)\rangle$ trivially because $(1\ 2)$ is odd. By lemma 5.2.5, $A_3\langle(1\ 2)\rangle$ has $3 \cdot 2 = 6$ elements, so it is S_3, and $S_3 \cong A_3 \rtimes \langle(1\ 2)\rangle$ by theorem 5.3.7. Both factors have prime order, so they are abelian (corollary 3.3.2) and hence nilpotent (example 6.1.15(1)). So a semi-direct product of nilpotent groups need not be nilpotent. More generally, an extension of a nilpotent group by a nilpotent group need not be nilpotent.

Thus, we have the following chain of implications

$$\text{cyclic} \Rightarrow \text{abelian} \Rightarrow \text{nilpotent} \Rightarrow \text{solvable}$$

by corollary 2.3.6, example 6.1.15(1) and proposition 6.1.18. None of the last three properties makes a group finitely generated (definition 5.1.4). For instance $\mathbb{Q}$ is abelian but not finitely generated: if $q_1, \ldots, q_m \in \mathbb{Q}$ have a common denominator $d \geq 1$, then the subgroup $\{x/d \mid x \in \mathbb{Z}\}$ contains each q_i, hence contains $\langle q_1, \ldots, q_m\rangle$ (proposition 2.3.17), but it does not contain $1/(2d)$.

So nilpotent groups do not interact well with extensions. However, the fac that their slightly stronger than extensions, but more general then abelian groups, brings us some useful properties:

Proposition 6.1.20: Properties Of Nilpotent Groups

Let G be a nilpotent group. Then

1. If H is a proper subgroup of G, then H is a proper normal subgroup of $N_G(H)$. We call this property the *normalizer property*, and we sometimes say that the "normalizer grows"
2. If G is finite, every Sylow subgroup of G is normal
3. If G is finite, G is the direct product of its Sylow subgroups
4. If G is finite and d divides the order of G, then G has a normal subgroup of order d

In fact, a finite group with property (4) is nilpotent, giving us another definition of nilpotency for finite groups.

***Proof*:**

1. Let H be a proper subgroup of G. By the definition of the normalizer, $H \trianglelefteq N_G(H)$, so it remains to find an element of $N_G(H)$ outside H. Let $Z^m(G) = G$. Since $Z^0(G) = 1 \subseteq H$ and $Z^m(G) \not\subseteq H$, there is a largest $i < m$ with $Z^i(G) \subseteq H$. Choose $x \in Z^{i+1}(G)$ with $x \notin H$. For $h \in H$, $xhx^{-1}h^{-1} = [x^{-1}, h^{-1}]$ lies in $Z^i(G) \subseteq H$ because $x^{-1} \in Z^{i+1}(G)$,

so $xhx^{-1} \in H$. Thus $xHx^{-1} \subseteq H$. The same argument with x^{-1} in place of x gives $x^{-1}Hx \subseteq H$, and so $xHx^{-1} = H$. Hence $x \in N_G(H)$ and $x \notin H$.

2. Let G be finite, let P be a Sylow p-subgroup of G (definition 4.8.2), and let $N = N_G(P)$. Then $|P|$ is the largest power of p dividing $|G|$, and $|P|$ divides $|N|$, which divides $|G|$ (theorem 3.3.1), so P is also a Sylow p-subgroup of N. Every element of N normalizes P, so $P \trianglelefteq N$, and corollary 4.8.9, applied to the group N, gives P char N. In the same way $N \trianglelefteq N_G(N)$, so proposition 4.7.13(3) gives $P \trianglelefteq N_G(N)$, that is, $N_G(N) \subseteq N_G(P) = N$. So $N_G(N) = N$. If $N \neq G$, part (1) would make N a proper subgroup of $N_G(N)$, which is false. Hence $N_G(P) = G$, and $P \trianglelefteq G$ by proposition 3.1.11.

3. Let G be finite with $|G| = p_1^{a_1} \cdots p_k^{a_k}$ for distinct primes p_i and $a_i \geq 1$, and let P_i be a Sylow p_i-subgroup (theorem 4.8.6), which is normal by (2). For $i \neq j$, $P_i \cap P_j = 1$, since its order divides both $p_i^{a_i}$ and $p_j^{a_j}$ (theorem 3.3.1). For $x \in P_i$ and $y \in P_j$ with $i \neq j$, the element $xyx^{-1}y^{-1}$ lies in P_j, being $(xyx^{-1})y^{-1}$, and in P_i, being $x(yx^{-1}y^{-1})$, so it equals 1 and $xy = yx$. Define

$$\mu\colon P_1 \times \cdots \times P_k \to G \qquad \mu(x_1, \ldots, x_k) = x_1 x_2 \cdots x_k$$

Moving each y_i to the right past the elements x_j with $j > i$ gives

$$\mu((x_1, \ldots, x_k)(y_1, \ldots, y_k)) = x_1 y_1 \cdots x_k y_k = x_1 \cdots x_k \, y_1 \cdots y_k$$

so μ is a homomorphism. Its image is a subgroup of G (proposition 1.4.4(5)) containing every P_i, so its order is divisible by every $p_i^{a_i}$ (theorem 3.3.1), hence by $|G|$, and μ is surjective. Since $|P_1 \times \cdots \times P_k| = |G|$ (proposition 5.1.3(1)), the surjection μ is a bijection, so $G \cong P_1 \times \cdots \times P_k$.

4. Let G be finite, with P_i and μ as in (3), and let $d = p_1^{b_1} \cdots p_k^{b_k}$ divide $|G|$, where $0 \leq b_i \leq a_i$. First, a group P of order p^a, for a prime p, has a normal subgroup of order p^b for each $0 \leq b \leq a$. We induct on a. For $b = 0$ take 1, which settles $a = 0$. Let $1 \leq b \leq a$. By theorem 4.6.5, p divides $|Z(P)|$, so $Z(P)$ has an element z of order p by theorem 4.8.7. The subgroup $Z = \langle z \rangle$ has order p and is normal in P, because $gz^l g^{-1} = z^l$ for $g \in P$. By the induction hypothesis, P/Z, of order p^{a-1} (theorem 3.3.1), has a normal subgroup of order p^{b-1}. By theorem 3.5.7 it is M/Z for a subgroup M of P containing Z. Then $M \trianglelefteq P$ by corollary 3.5.8(5), and $|M| = |M/Z||Z| = p^b$ by theorem 3.3.1.

   Now choose $N_i \trianglelefteq P_i$ with $|N_i| = p_i^{b_i}$, and put $N = \mu(N_1 \times \cdots \times N_k)$, a subgroup of G (proposition 1.4.4(5)). Since μ is injective, $|N| = |N_1| \cdots |N_k| = d$. The subgroup $N_1 \times \cdots \times N_k$ is normal in $P_1 \times \cdots \times P_k$, because conjugation is computed componentwise and each $N_i \trianglelefteq P_i$. Since μ is surjective, every $g \in G$ is $\mu(u)$ for some u, and for $v \in N_1 \times \cdots \times N_k$, $g\mu(v)g^{-1} = \mu(uvu^{-1}) \in N$. So $N \trianglelefteq G$ by proposition 3.1.11.

Finally, let G be a finite group with property (4), and factor $|G|$ as in (3). For each i, property (4) gives a normal subgroup P_i of order $p_i^{a_i}$, which is a Sylow p_i-subgroup. The argument of (3) used only that the P_i are normal of these orders, so it gives an isomorphism $\mu\colon P_1 \times \cdots \times P_k \to G$. Each P_i is nilpotent (example 6.1.15), so by proposition 6.1.16 it has a central series, and repeating its last term 1 we may take all of them of one length n, say $P_i = A_{i,0} \geqslant \cdots \geqslant A_{i,n} = 1$ with $[P_i, A_{i,j}] \leqslant A_{i,j+1}$. Put $B_j = \mu(A_{1,j} \times \cdots \times A_{k,j})$, a subgroup of G. Then $B_0 = G$, $B_n = 1$ and $B_{j+1} \leqslant B_j$. For $g = \mu(u)$ and $b = \mu(v)$ with $v \in A_{1,j} \times \cdots \times A_{k,j}$, the commutator

$[g, b] = \mu([u, v])$ lies in B_{j+1}, because the components $[u_i, v_i]$ of $[u, v]$ lie in $A_{i,j+1}$. Hence $[G, B_j] \leqslant B_{j+1}$ by proposition 2.3.17, so (B_j) is a central series of G, and G is nilpotent by proposition 6.1.16, completing the proof.

Exercise 6.1.1

1. Prove that any nilpotent group of class 3 or lower is metabelian
2. Show that if $\mathrm{Aut}(G)$ is abelian, then G is nilpotent of class at most 2

6.1.3 Polycyclic Groups

We have extended a abelian group using *central extensions* and *abelian extensions*. In this section, we will once again be extending an abelian group, but this time we will ask what happens if we extend a cyclic group in such a way that G_i/G_{i+1} is cyclic?

Definition 6.1.21: Polycyclic Group

Let G be a group. Then if

$$G = G_0 \trianglerighteq G_1 \trianglerighteq \cdots \trianglerighteq G_n = \{1\}$$

st G_i/G_{i+1} is cyclic, Then G is said to be polycyclic. The series G admits is called a *subnormal series with cyclic factors*. If $G_n = \{1\}$, then we say that G is polycyclic with length n.
If $n = 2$, then we say that G is a *metacyclic group*.

Example 6.1.22: polycyclic groups
By theorem 5.1.6, every finitely generated abelian group is polycyclic: the group $\mathbb{Z}^r \times \mathbb{Z}_{n_1} \times \cdots \times \mathbb{Z}_{n_s}$ has the series of its partial products, whose factors are cyclic.

Proposition 6.1.23: Polycyclic Then Finitely Generated

Let G be a polycyclic group. Then G is finitely generated.

***Proof*:**
Let G be polycyclic, so that

$$G = G_0 \trianglerighteq G_1 \trianglerighteq \cdots \trianglerighteq G_n = \{1\}$$

is the subnormal series with cyclic factors. For $0 \leq i < n$ choose $g_i \in G_i$ whose coset $g_i G_{i+1}$ generates the cyclic group G_i/G_{i+1}. We show $G_i = \langle g_i, \ldots, g_{n-1} \rangle$ by downward induction on i, the case $i = n$ being $G_n = 1 = \langle \emptyset \rangle$. Suppose $G_{i+1} = \langle g_{i+1}, \ldots, g_{n-1} \rangle$ with $i < n$. Every generator $g_i, \ldots, g_{n-1}$ lies in G_i, so $\langle g_i, \ldots, g_{n-1} \rangle \subseteq G_i$ (proposition 2.3.17). Conversely, for $x \in G_i$ we have $xG_{i+1} = (g_i G_{i+1})^\alpha = g_i^\alpha G_{i+1}$ for some $\alpha \in \mathbb{Z}$, so $x = g_i^\alpha y$ with $y \in G_{i+1} = \langle g_{i+1}, \ldots, g_{n-1} \rangle$, and $x \in \langle g_i, \ldots, g_{n-1} \rangle$. For $i = 0$ this gives $G = \langle g_0, \ldots, g_{n-1} \rangle$, showing that G is finitely generated.

Note that the converse is false:

Example 6.1.24: Finitely Generated, But Not Polycyclic
Let $G = A_5$, which is a simple non-cyclic group. Since it simple, it's subnormal series is only

$$A_5 \trianglerighteq \{1\}$$

and so, it cannot be polycyclic.

For finitely generated groups the implications combine as follows:

$$\text{cyclic} \Rightarrow \text{abelian} \Rightarrow \text{polycyclic} \Rightarrow \text{solvable}$$

Here a finitely generated abelian group is polycyclic by example 6.1.22, and a polycyclic group is solvable by theorem 6.1.9, because cyclic groups are abelian. Every polycyclic group is finitely generated (proposition 6.1.23). A finitely generated nilpotent group is polycyclic as well: it satisfies the maximal condition on subgroups [86, 5.2.17], a tool this book does not develop, and refining its lower central series gives a central series with cyclic factors [86, 5.2.18].

6.2 Non-finitely generated abelian groups

The additive group $\mathbb{Q}$ is abelian and not finitely generated, as the paragraph after example 6.1.19 shows. Nor is $\mathbb{Q}$ isomorphic to a direct sum of cyclic groups (definition 5.4.9). Any two nonzero elements a/b and c/d of $\mathbb{Q}$ have the nonzero common multiple $ac = (bc)(a/b) = (ad)(c/d)$, whereas two nonzero elements of a direct sum that are supported in different positions have no nonzero common multiple. So such a direct sum would have only one nonzero summand, and $\mathbb{Q}$ would be cyclic.

Prüfer theorems give two conditions under which an abelian group, written additively, is a direct sum of cyclic groups, without the assumption that it is finitely generated. An abelian group G has *bounded order* if there is an integer $n \geq 1$ with $nx = 0$ for every $x \in G$, and every abelian group of bounded order is a direct sum of cyclic groups. For a prime p, let G be an abelian group in which every element has order a power of p. An element $x \in G$ has *infinite height* if for every $k \geq 1$ there is $y \in G$ with $p^k y = x$, and if G is countable and has no nonzero elements of infinite height, then G is a direct sum of cyclic groups. Prüfer proved both statements for countable groups. Both are proved with pure subgroups and heights [67, Theorems 6 and 11], which this book does not develop. The first holds for every abelian group of bounded order, while the second fails for some uncountable groups [67, p. 74].

6.3 Linear Groups

A *linear group* is a subgroup of $GL_n(F)$ (definition 1.2.33) for a field F and an integer $n \geq 1$. The groups $SL_n(F)$, $O_n(F)$ and $SO_n(F)$ of definitions 1.2.34 to 1.2.36 are linear groups, and so is the group of invertible upper triangular matrices of example 6.1.19. Lie theory studies linear groups over $\mathbb{R}$ and $\mathbb{C}$ through their Lie algebras, and invariant theory studies the polynomial functions on F^n that a linear group leaves unchanged.

7

Generalization of Groups

In this chapter, I will cover common algebraic objects which are generalizations of groups.

7.1 Monoid

Having a unique inverse is one of the more powerful axioms you can add to an algebraic structure. Recall how the uniqueness of a linear solution is bassed off of the fact that the invere exists and is unique (proposition 1.1.17). This property is also called the *cancellation property*. There are many mathematical structures which do not have this ($\mathbb{N}$ would be a group if inverses existed). For this reason, the study of this structure is also of interest to many

Definition 7.1.1: Monoid

A *Monoid* is an ordered pair $(M, *)$ where M is a set and $*$ is a binary operation on M satisfying the following axioms

1. associativity: $(a * b) * c = a * (b * c)$
2. there exists an element e in G, called the *identity* of G such that for every $a \in G$, we have $a * e = e * a = a$ [a]

The Monoid $(M, *)$ is called *abelian* (or commutative) if $a * b = b * a$ for every $a, b \in M$

[a] it can in fact be proven that if $a * e = a$ then $e * a = a$ (or vice-versa); an indispensable exercise worth doing

Example 7.1.2
Naturally, all groups are monoids. I will give non-group example of monoids:

1. The natural numbers $\mathbb{N}$
2. Given a set A and it's powerset $P(A)$ (set of all substs), then $(P(A, \cup))$ is a monoid with $\emptyset$ as the identity.
3. Given a set A and it's powerset $P(A)$, then $(P(A), \cap)$ is a monoid with A as the identity.
4. The set $\{0, 1\}$ with any boolean operation ($\Rightarrow$, NOR, AND, etc.) is a monoid. More commonly, the set is relabled as $\{\text{False}, \text{True}\}$
5. The set of strings, given an alphabet is a free monoid.
6. Given a set A, the set of all functions $f : A \to A$ is a monoid! This is incredibly powerful, since we can now put an algebraic structure on sets themselves!! Any set has a default algebraic structure! Further wil be true soon: When we study rings, rings will be an abelian group, along with a second operation which will be a monoid!!

   If A is an abelian group, the homomorphisms $A \to A$ even form a ring, with pointwise addition and composition as multiplication.
7. The normal subgroups of a group G form a monoid under the product of subgroups, the product of N and M being the set NM of all products nm with $n \in N$ and $m \in M$, and the identity being $\{e\}$.

Recall that $\text{Aut}(G)$ is a group, but $\text{End}(G)$ was not since not every element has an inverse (section 1.4)? This then makes $\text{End}(G)$ a monoid

Proposition 7.1.3: $\text{End}(G)$ Is a Monoid

Let G be a group. Then $\text{End}(G)$ is a monoid under composition, with identity id_G.

***Proof*:**
A composite of homomorphisms $G \to G$ is a homomorphism (proposition 1.4.4(6)), so composition is a binary operation on $\text{End}(G)$. It is associative, since $((f \circ g) \circ h)(x) = f(g(h(x))) = (f \circ (g \circ h))(x)$ for all $x \in G$. The identity map id_G is a homomorphism, and $f \circ \text{id}_G = \text{id}_G \circ f = f$ for every $f \in \text{End}(G)$, completing the proof.

Example 7.1.4
For $G = D_3$, the monoid $\text{End}(G)$ is not a group: the trivial homomorphism $x \mapsto e$ has no inverse, since $f \circ (x \mapsto e)$ is the trivial homomorphism for every $f \in \text{End}(G)$, and never id_G.

There is a lot of intereting theory for monoids which I will simply sum up for now to get to the main reason I wanted to bring them up

1. Recall that I said that groups have the cancellation property because of the unique inverse of every element. It is possible that there are monoids with this property that are not groups.

Such monoids are called monoids *with the cancellation property*. The natural numbers is an example of such a monoid. Monoids with the cancellation property can be extended to form groups (called the Grothendieck construction). If the monoid is finite, then it implies that it's a group

2. The automorphisms of a group form a group, and its endomorphisms only a monoid. Dropping the condition of being a homomorphism, the functions $f\colon S \to S$ on any set S form a monoid under composition, with identity id_S.

3. The same way we defined group-actions with groups, we can define monoid-actions with the same axioms. These pop-up in computer-science in the study of automata.

4. In functional programming, monads is a central tool in programming. Monads are monoids! The objects on which they are monoids is a more complicated subject, and will be left for the appendix on category theory [1]

5. free-monoids play a pivitol role in modeling the behavior of machines (ex. Turing machines).

Though all these reaon are good reasons to look into monoids, I bring them up for their use in Category Theory. More particularly, we can define a monoid to be a category with a single element!

The Grothendieck construction named in (1) above is worth carrying out in full, because it is the mechanism by which a number of later invariants are built. Whenever a class of objects carries a notion of direct sum, its isomorphism classes form an abelian monoid, and the invariant one wants is the group this construction produces: the Grothendieck group of vector bundles, of finitely generated projective modules, and of a C^*-algebra are each defined this way. The construction is stated for an arbitrary abelian monoid, since cancellation is exactly what it does *not* need.

Definition 7.1.5: Grothendieck Completion

Let $(M, +)$ be an abelian monoid. Define a relation on $M \times M$ by

$$(m, n) \sim (m', n') \quad \text{if and only if} \quad m + n' + p = m' + n + p \ \text{ for some } p \in M$$

The *Grothendieck completion* of M is the quotient $M^{-1}M = (M \times M)/\sim$ with addition induced coordinatewise, together with the monoid homomorphism

$$\iota\colon M \to M^{-1}M, \qquad m \mapsto [(m, 0)]$$

The class of (m, n) is written $[m] - [n]$, which the group structure below justifies.

The auxiliary p in the relation is what makes $\sim$ transitive without assuming cancellation, and it is exactly the obstruction measured in part (3) below.

[1] For those who are impatient or know some Category theory, a monoid on a category of functors which are derived given by a particular adjoint

Proposition 7.1.6: Properties of the Grothendieck Completion

Let M be an abelian monoid. Then:

1. $M^{-1}M$ is an abelian group, and every element of it has the form $[m]-[n]$ for some $m,n\in M$.
2. $\iota(m)=\iota(n)$ if and only if $m+p=n+p$ for some $p\in M$.
3. ι is injective if and only if M has the cancellation property.
4. For every abelian group A, composition with ι is a bijection
$$\mathrm{Hom}_{\mathbf{Grp}}(M^{-1}M,A)\xrightarrow{\sim}\mathrm{Hom}_{\mathbf{Mon}}(M,A)$$
natural in M and A. That is, $M\mapsto M^{-1}M$ is left adjoint to the forgetful functor from abelian groups to abelian monoids.

***Proof*:**
Step 1: $\sim$ is an equivalence relation. Reflexivity and symmetry are immediate. For transitivity, suppose $m+n'+p=m'+n+p$ and $m'+n''+q=m''+n'+q$. Adding the two equations gives
$$m+n''+(n'+m'+p+q)=m''+n+(n'+m'+p+q)$$
so $(m,n)\sim(m'',n'')$ with the witness $r=n'+m'+p+q$. Note that no cancellation was used, which is the point of carrying p at all.

Step 2: the group structure. Coordinatewise addition respects $\sim$, since adding a fixed pair to both sides of the defining equation preserves it. Associativity and commutativity are inherited from M, the class $[(0,0)]$ is an identity, and $[(n,m)]$ is inverse to $[(m,n)]$ because $(m+n,\ n+m)\sim(0,0)$ with $p=0$. So $M^{-1}M$ is an abelian group, and $[(m,n)]=\iota(m)-\iota(n)$, which is (1).

Step 3: parts (2) and (3). By definition $\iota(m)=\iota(n)$ means $(m,0)\sim(n,0)$, that is $m+p=n+p$ for some p, which is (2). Then ι is injective exactly when $m+p=n+p$ forces $m=n$, which is the cancellation property, giving (3).

Step 4: the universal property. Let $f\colon M\to A$ be a monoid homomorphism into an abelian group. If $(m,n)\sim(m',n')$, say $m+n'+p=m'+n+p$, then applying f and cancelling in A, which is legitimate because A is a group, gives $f(m)-f(n)=f(m')-f(n')$. So
$$\tilde{f}([m]-[n]):=f(m)-f(n)$$
is well defined, and it is a homomorphism because addition in $M^{-1}M$ is coordinatewise. It satisfies $\tilde{f}\circ\iota=f$. For uniqueness, any homomorphism g with $g\circ\iota=f$ is determined on the elements $\iota(m)$, and these generate $M^{-1}M$ by (1), so $g=\tilde{f}$. Naturality in M and A is immediate from the formula, completing the proof.

Example 7.1.7: Grothendieck Completions

1. $\mathbb{N}$ under addition is cancellative, so ι is injective, and $\mathbb{N}^{-1}\mathbb{N}=\mathbb{Z}$. This is the motivating case named at the start of the section.

2. Let $M = \{0, 1\}$ with $1 + 1 = 1$. Cancellation fails, since $1 + 1 = 0 + 1$ while $1 \neq 0$, and indeed $M^{-1}M = 0$: taking $p = 1$ shows $(1, 0) \sim (0, 0)$, so $\iota(1) = 0$.

3. More generally, if M has an absorbing element ω, meaning $\omega + m = \omega$ for every m, then $M^{-1}M = 0$: for any m, taking $p = \omega$ gives $m + \omega = 0 + \omega$. This is why the construction is applied to *finitely generated* objects rather than arbitrary ones, an infinite direct sum being absorbing.

Exercise 7.1.1

1. In the following exercises, we will test your understanding of the idea of defining quotient objects by building up to defining a quotient monoid
   a) Recall the difference between an equivalence relation and a congruence relation. What condition do we need in order that $[x][y] = [xy]$ in a monoid?

7.2 Groupoid

Recall how at the very begining under definition 1.1.3, I remarked how some authors prefer to say groups are not closed under multiplication? Some authors introduce this convention to be able to later drop this axiom in order to define the more general notion of *groupoid*. A groupoid is a group which is not closed under the binary operation! [2]

Definition 7.2.1: Groupoid

A groupoid is a set G with a unary operation $^{-1} : G \to G$ and a patial function $* : G \times G \rightharpoonup G$ where the following axioms hold:

1. Where $a * b$ and $b * c$ are defined, $(a * b) * c = a * (b * c)$. Conversaly, if $(a * b) * c$ and $a * (b * c)$ is defined, then so are both $a * b$ and $b * c$ and $(a * b) * c = a * (b * c)$
2. $a^{-1} * a$ and $a * a^{-1}$ are always well-defined
3. if $a * b$ is defined, then $a * b * b^{-1} = a$ and $a^{-1} * a * b = b$

[2] Technically, this means it's not a binary operation, because binary operations are functions, which need to be closed, but the spirit of the sentence is correct

8

Category of Group

Throughout the book, we will be introducing more and more algebraic structures of varying levels of similarity and differences[1]. It would be very convenient to be able to have a way to compare these algebraic structures. In this section, we elaborate more on the concept of *Categories* which were introduced in section 0.4. When we introduce new algebraic structures, we will show how the algebraic structure also forms a *category*, and by doing so we will open up the ability to compare and contrast all sorts of properties. For example, we saw in example 1.1.5 that if G and H are groups we can define $G \times H$ to be a group under point-wise operations. Will the same type of construction be possible for algebraic structures in coming chapters? For rings? Group-actions? Fields? Vector-space? Will all of these objects have a notion similar to subgroup? Will they all have a notion of homomorphism/isomorphism, or a similar notion to group action? The answer will be yes to some and no to others! In order for these structure to have or not have a property, say for example the ability to do a "direct product", there must be a way of saying "the direct product of groups follows the same principle as the direct product of rings/group-actions/fields/vector spaces/etc." This will be accomplished with the language of category theory.

As mentioned in section 0.4, the core concept of categories is that we want to be able to have a structure that holds *objects* (ex. groups), and a particular way to *relate* these objects (ex. homomorphisms). See the analogy in the aforementioned section for an analogous point of reference. Different categories can have the same objects but different relations, or the same relations but different objects, or different objects and relations. Commonly, a relation between two objects will be a way to change from one object to another while preserving some of the original structure of the object. These types of relations are called *structure preserving* relations. As an example of relations between objects that preserve some structure, take homomorphism, which relates two groups if there is some common group-structure. The fact that homomorphisms preserve (some or all of) the structure can also be

[1] In this book, there will be 15 algebraic objects that can be considered "key objects" to algebra, while we also work with 6 others non-algebraic objects throughout the book (ex. sets, graphs, ordered sets, etc.)

found in the etymology of the word: the word *homomorphism* come from *homo-* meaning "same" [2] and *morphism* meaning shape. Since homomorphsims preserve (some or all) group structure, they in a sense change a shape from one group to another while keeping some of the "sameness" between the two. Many different mathematical objects have a relation between them that preserve some of it's structure (topologies with topology-preserving functions, graphs and graph-preserving functions, or ordered sets with order-preserving functions to name few), which is why when categories were first introduced, the word *morphism* came to be the name used to describe relations between objects (i.e. if A and B are related in a category, there is a morphism from A to B). The word morphism is a generalization of the word homomorphism to capture the idea of relation's between objects.

I was purposefully being vague in the start by saying that a category has a "particular way to relate objects" instead of just jumping to saying that morphisms preserve some of the structure of the objects. At the beginning of category theory in the 1940s, the types of relations morphisms represented were relations that preserved (some or all of) the structure of the objects. As time went on, more mathematical objects were shown to form categories using morphisms that did not preserve structure in a way we saw with homomorphisms, and the idea that some of the structure is preserved can be a stretch. A partially ordered set $(S, \leq)$ is a category whose objects are the elements of S, with a single morphism $x \to y$ when $x \leq y$ and none otherwise, and these morphisms are not maps between sets at all. This is good to know early on to not get the wrong idea of categories, however in the undergraduate level, 99% of the time morphism in categories will be about preserving some/all the structure of a particular object.

With this very high-level idea, let's give some concrete examples before introducing the definition of a category. If we take all the groups and all the possible homomorphism between groups; that will in fact from the category of groups, sometimes denoted **Grp** or **Group**. Another example would be the collection of all sets and all function between sets. That will form the category of sets, sometimes denoted **Set**. We will soon bring in the definition of a category to prove that it will follow the axioms of a category, for now we will build up some terminology for describing these collections.

Definition 8.0.1: Category Of Grp and Set

1. Let **Grp** represent the collection of all groups and homomorphism between Groups and **Set** the collection of all sets and functions between sets.
2. Let Obj(**Grp**) represent all the objects in the category of **Grp**. Similarly for Obj(**Set**).
3. For any $G, H \in \text{Obj}(\mathbf{Grp})$, Let $\text{Hom}_{\mathbf{Grp}}(G, H)$ represent all homomorphisms from G to H. Similarly, if $A, B \in \text{Obj}(\mathbf{Set})$, let $\text{Hom}_{\mathbf{Set}}(A, B)$ represent all function form A to B.

In many ways, properties of these collections was the starting point for the first category theorists definition of a category, so it is worth taking a closer look at the properties. To not clutter the analysis, we will stick with **Grp** to build-up to the definition of a category.

When we relate two group using homomorphsims, we always have a domain and a co-domain:

$$\varphi : G \to H$$

This means that relations are *directional*: a homomorphism from G to H is different from a homomorphism from H to G. In some structure, direction of the relation does not matter (for

[2] Other words with homo- would be homeostasis (same state), homochromatic (same colour), or homogeneous (same kind/nature, or uniform structure). It's antonym would be hetero- (heterostatis, heterochromatic, heterogenous)

example, in equivalence relations, $x \sim y$ if and only if $y \sim x$). In categories, we pay careful attention at the direction of the arrow, and so when generalizing, a morphism from an object A to B is not the same from a morphism from an object B to A.

When we work with homomorphism, we showed in proposition 1.4.4 that the composition of two homomorphisms is a homomorphism. Particularly, if have a homomorphism from G to H, and a homomorphism from H to K, then there will always exist a homomorphism from G to K:

$$G \xrightarrow{f} H \xrightarrow{g} K \qquad G \xrightarrow[g\circ f]{} K$$

So, if there is a way to get from G to K through homomorphism, there must be a way to "get there directly" too. Morphisms will have the same property.

Finally, notice that for every group there always exists a "trivial" homomorphism:

$$1_G : G \to G \qquad 1_G(g) = g$$

that is, the homomorphism takes G to itself. In a sense, what is being said here is that every object trivially relates to itself. Another way of thinking that 1_G is trivial is that when composed with other homomorphisms (with appropriate domain or co-domain), it does not change them. If:

$$\alpha : G \to H,\ \beta : F \to G$$

were homomorphsims, then

$$\alpha \circ 1_G = \alpha \qquad 1_G \circ \beta = \beta$$

We want this same property to exist for categories: That every object in a category has a *trivial morphism* which can compose with morphisms (with appropriate domain or co-domain) and not affect it

You might have noticed that all of these properties are about the morphisms of a category. This is a common philosophy in category theory: What's important is not the objects, but the how an objects relates to other object! It is arguable that the more mathematics you will encounter, the more it will be clear that it is the way objects can relate to object objects that i the defining feature of many objects. In fact, many algebraic objects that we will see will be defined by how they relate to other objects.

With this, we will finally define a category:

Definition 8.0.2: Category

A ***category*** C consists of[a]

1. A collection of *objects*, denoted $\text{Obj}(C)$
2. A collection of *morphisms*, denoted $\text{Mor}C$

where

- Each morphism has a specified ***domain*** and ***codomain*** object. Sometimes, this is written as $f : X \to Y$, where f is the morphism with domain X and codomain Y [b]. For any $A, B \in \text{Obj}(C)$, $\text{Hom}_C(A, B)$ denotes all morphisms form A to B.
- Each object has an ***identity morphism*** $1_X : X \to X$
- For each pair of morphisms f, g with the codomain of f equal to the domain of g (ex. $f \in \text{Hom}C(A, B)$, $g \in \text{Hom}_C(B, C)$), there exists a specified ***composite morphism*** gf (or $g \cdot f$)[c] whose domain is equal to the domain of f and whose codomain is equal to the codomain of g, i.e.

$$f : X \to Y \qquad g : Y \to Z \qquad \Rightarrow \qquad gf : X \to Z$$

such that

1. For any $f : X \to Y$, the composites $1_Y f$ and $f 1_X$ are both equal to f (i.e. unital with the identity homomorphism)
2. For any composable triple of morphisms f, g, h, the composites $h(gf)$ and $(hg)f$ are equal (i.e. associative), and so we can write hgf unambiguously.

[a] The word *collection* being used instead of *set* was purposeful. We will get to this
[b] Note that f **need not be a function**! Namely, the morphism need not have a unique codomain
[c] the notation is purposefully not $\circ$ so as to not draw too much of an analogy of gf with the process of composing functions to demonstrate that in some cases gf is *not* function composition

Example 8.0.3: Examples of Categories

1. It was mentioned that groups along with homomorphisms from a category. Indeed, by proposition 1.4.4 the composition of two homomorphsims is a homomorphism, so $gf = g \circ f$. Homomorphsims are associative since function composition is associative (proposition 0.1.22), and for any $G \in \text{Obj}(Grp)$, the map $\text{id} :\to G$, $\text{id}(g) = g$ is the identity morphisms since for any $f : F \to G$ and $h : G \to H$, $f \circ \text{id} = f$ and $\text{id} \circ h = h$.
2. If we take all groups, and restrict to taking only the isomorphisms, we will again have a category. Check that all the axioms are still satisfied. A category in which every morphism is an isomorphism is called a *groupoid* (section 7.2 describes the same notion as a set with a partially defined operation). A groupoid with a single object x is a group, namely the morphisms $x \to x$ under composition.
3. If we take all abelian groups and use homomorphsims, this will again be a category. This category is significant enough to deserve it's own notation: this category will denoted **Ab**.

4. If we take all sets and all functions between sets, we will get the category of **Set**.

   Notice that every morphism in **Grp** can be thought of as a morphism in **Set** if we "forget" the group structure of the domain and co-domain, and the homomorphism condition of the morphism of **Grp**. In This way, the category of **Grp** and the category of **Set** are related if we "forget" some of the additional structure of **Grp**. Is it possible to have the reverse? That is, starting with **Set**, is it possible to somehow "upgrade" it to **Grp**? Is there more than one way of doing this? Is there a "natural" way of doing it, that is, is there a way of performing this upgrade in such a way that it follows from the properties of groups and sets without needing to add any more conditions? These questions will be further explored in section 2.3.3. generally.

5. If we take the collection partially ordered sets, that the collection of $(S, \leq)$ where $S \in \text{Obj}(Set)$ and $\leq$ is a possible partial order on S, then we can define a notion similar to homomorphisms that preserve (some or all of) the structure of the order, i.e. we can define a $f : (S, \leq_S) \to (R, \leq_R)$ where f is the appropriate morphism. Can you think of what this morphism should be?

6. Graphs and graph isomorphisms (section 0.3) also form a category. A *graph homomorphism* is a map on vertices sending adjacent vertices to adjacent vertices, and a colouring of a graph with k colours is the same as a homomorphism to the complete graph K_k (see [61]).

Before continuing with the language of category, we will add one more example of a category which is a little more abstract than the previous categories but one we will constantly use. Namely, we can take categories themselves to be objects and define a notion of morphism between categories! This category will be denoted **Cat**. Since morphisms relate objects, the morphisms in the category of **Cat** allows us to find commonalities between different categories! We have in fact already described a category morphism in example 8.0.3(4): If we take **Grp**, we can forget the group structure of every group and the homomorphism property of every homomorphsims and we will end up with **Set**. In effect, we did $(G, *) \to G$ and mapped the homomorphism f where $f : (G, *_G) \to (H, *_H)$ to the function f $f : G \to H$ where the function f is identical to the homomorphsims f except it no longer requires the homomorphism property (in fact, it is impossible for it to have the homomorphism property since sets do not have a binary operation). We will call category morphisms *Functors* (as a generalization of the word function)

Definition 8.0.4: [Covariant] Functor

Let C, D be two categories. Then a *Functor* F will consist of:

1. a function between $\text{Obj}(C)$ and $\text{Obj}(D)$. If $a \in C$ is an object, then $F(a) \in D$ denotes the object in D.
2. a function between Mor$C$ and Mor$D$. If $f \in C$ is a morphism in C, then $F(f)$ denotes the morphism in D.

such that

1. F must preserves the domain and codomain of each morphism: $f : A \to B$ must map to $F(f) : F(A) \to F(B)$
2. F must map identities to identities: $F(\text{id}_f) = \text{id}_{F(f)}$
3. F must preserve composition: $F(g \cdot_C f) = F(g) \cdot_D F(f)$.

Example 8.0.5: Functor

1. For any category C, there is always a trivial functor sending objects to themselves and functions to themselves
2. The relation above between **Group** and **Set** is indeed a functor: $F : \textbf{Group} \to \textbf{Set}$ Such a functor is called a *forgetful functor* since it forgets some of the structure of the category. In the coming chapters, many of the objects are augmentation of sets. All of these categories will have a forgetful functor $F : \textbf{C} \to \textbf{Set}$.

Some authors prefer to be more specific about the second condition and define it instead as the following: for any two object $a, b \in \text{Obj}(C)$ there exists a function $\text{Hom}_C(a, b) \to \text{Hom}_D F(a), F(b)$. We will see many more examples of functors throughout this book. For now, it is left as an optional exercise to prove that categories and functors together form a category[3].

So far, all the categories we have dealt were all in some fundamental sense based on sets: each object was either a set with an augmentation (ex. $(G, *)$ or $(S, \leq)$) or a collection of sets following certain restrictions (ex. graphs). Because of this, every object in every category so far has the notion of having "elements". However, there is nothing in the definition of an object in a category that restricts objects to needing elements:

Example 8.0.6: Non-Set Category

Let $\mathbb{N}$ be the set of all natural numbers and $\leq$ be the usual order. Then we define a category C whose objects are the numbers of $\mathbb{N}$ and whose morphism is $\leq$, that is for every $x \in \mathbb{N}$, $\leq$ is the morphism that relates x to numbers greater than or equal to number y, which we will label $x \leq y$. Notice that $\leq$ is not a function, since x is not "mapped" to a single element but to every element greater than it. Furthermore, $\leq$ is the only morphism in in this category. Composition will return $\leq$ (since it's the only morphism) and we see that if $x \leq y$ and $y \leq z$ then their composition results

[3]There is a technicality about the fact we are taking "the category of all categories" in the sense that this is self-referential creating a contradiction usually called Russel's Paradox. There is a definition of *small category* which circumnavigates this problem which was not introduced so as to no overload new terminology


in $x \leq z$.

This is indeed a category: $\leq$ has a domain and co-domain (if you like you can picture $\leq: x \to y$ as long as it is kept in mind that $\leq$ is not a function). For any $x \in \mathbb{N}$, x has an identity morphism, namely the only morphism $\leq$, (you can picture $\leq \cdot \leq = \leq$).

More generally, any set S with some partial order forms a category. For example, if X is a set, then $(P(X), \subseteq)$ is a category whose objects are all subsets of X and the morphism is the partial order induced by $\subseteq$ (i.e. $U \subseteq V$ then $U \to V$).

(Another would be to simply draw diagrams!!)

The set $\mathbb{N}$ was an arbitrary choice in the previous construction: we could have chosen $\mathbb{R}$ or $\{0\}$ or an arbitrary set with an arbitrary ordering. We can visualize the category in the example by imagining a directed graph where every edge represents the morphism between the domain and codomain:



Such a directed graph is called a *commutative diagram*. The full reason behind the name is a little abstract without the proper build-up[4], however we can still understand the etymology given the following illustrative example: imagine we start at the number 1, and every horizontal arrow represents multiplying on the right by x, and every vertical arrow represents multiplying on the right by y, and we form a square like so:

$$\begin{array}{ccc} 1 & \xrightarrow{\cdot x} & x \\ \downarrow{\scriptstyle \cdot y} & & \downarrow{\scriptstyle \cdot y} \\ y & \xrightarrow{\cdot x} & yx = xy \end{array}$$

Similarly, we could have started with $G \times G$ in the top left, let the right arrow be the swap operation $(x, y) \mapsto (y, x)$, the bottom arrow being the identity $(x, y) \mapsto (x, y)$, and then both arrow to the bottom right being the group multiplication arrows.

This square shape is so common that the any directed graph represented morphisms came to be called a commutative diagram. In section 8.2, we shall further explore the use of commutative diagram to understand properties of categories.

8.1 Basic properties of Morphisms

I clearly do not have enough knowledge to write this yet:

https://en.wikipedia.org/wiki/Monomorphism.

Read this and come back.

When we studied function, we started by classifying injective and surjective functions due to their simplicity and universality. It would be nice if there are some nice equivalent, or at least similar, notions of injectivity and subjectivity for morphisms in general categories. Since objects need not

[4]We will often care about morphisms between categories commuting in some "natural" way. This will lead to the study of natural transformation from which the name commutative diagram will takes it's name

have elements, the definition has to take this generality into account. Fortunately, there is already a property of injective and surjective functions that was characterized in terms of functions in proposition 0.1.26 and proposition 0.1.28: it was shown that all injective functions have a left inverse and all surjective functions have a right-inverse. These notions can be generalized in the following way:

Definition 8.1.1: Monomorphism

Let $f : A \to B$ be a morphism. Then if for any morphism $\alpha : Z \to A$, $\beta : Z \to A$, if

$$f \circ \alpha = f \circ \beta \Rightarrow \alpha = \beta$$

then we call f a monomorphism

Intuitively, monomorphisms should take you to a "unique place" similarly to how injective functions have a single element to represent them.

Proposition 8.1.2: In Set, monomorphism if and only if Injective

Let $f : A \to B$ be a set function. Then f is injective if and only if it is a monomorphism

***Proof*:**

($\Rightarrow$) Let's say f is injective, and that $f \circ \alpha = f \circ \beta$. We want to show that $\alpha = \beta$. By proposition 0.1.26, there exists a left-inverse f^{-1}. Now, notice that

$$\begin{aligned} (f^{-1} \circ f) \circ \alpha &= f^{-1} \circ (f \circ \alpha) && \text{associativity of composition} \\ &= f^{-1} \circ (f \circ \beta) && \text{by assumption} \\ &= (f^{-1} \circ f) \circ \beta && \text{associativity of composition} \end{aligned}$$

meaning we get $\mathrm{id}_A \circ \alpha = \mathrm{id}_A \circ \beta$, and so

$$\alpha = \beta$$

as we sought to show

($\Leftarrow$) Let's say f is a monomorphism so that $f \circ \alpha = f \circ \beta$ implies $\alpha = \beta$. Let's say f was not injective, that is, for some $a, b \in A$, $f(a) = f(b)$ but $a \neq b$. Choose $B' = f(B)$ to be the domain of α and β where α and β both agree where to send elements with the exception of α sending $f(a)$ to a and β sending $f(a)$ to b. Then

$$f \circ \alpha = f \circ \beta$$

but $\alpha \neq \beta$ a contradiction. Since those elements were arbitrary, it must be the case that,

$$f(a) = f(b) \Rightarrow a = b$$

showing injectivity.

One can also prove this directly by letting $Z = \{p\}$ (i.e., a singleton) and using the monomorphism property to conclude that

$$f(a) = f(b) \Rightarrow a = b$$

Similarly, we can define an epimorphism:

Definition 8.1.3: Epimorphism

Let $f : A \to B$ be a morphism.

If for any function $\alpha : B \to Z$, $\beta : B \to Z$, if

$$\alpha \circ f = \beta \circ f \Rightarrow \alpha = \beta$$

then we call f a epimorphism

Proposition 8.1.4: In Set, epimorphism if and only if Surjective

Let $f : A \to B$ be a set function. Then f is surjective if and only if it is a epimorphism

***Proof*:**

($\Rightarrow$) Let f be surjective, and let $\alpha, \beta : B \to Z$ satisfy $\alpha \circ f = \beta \circ f$. Take any $b \in B$. By surjectivity, there exists $a \in A$ with $f(a) = b$, and so

$$\alpha(b) = \alpha(f(a)) = \beta(f(a)) = \beta(b)$$

Since b was arbitrary, $\alpha = \beta$, showing f is an epimorphism.

($\Leftarrow$) Let f be an epimorphism, and suppose toward a contradiction that f is not surjective, that is, there exists $b_0 \in B$ with $b_0 \notin f(A)$. Let $Z = \{0, 1\}$ and define $\alpha, \beta : B \to Z$ by $\alpha(b) = 0$ for every b, while $\beta(b) = 0$ for $b \in f(A)$ and $\beta(b) = 1$ otherwise. For every $a \in A$ we have $f(a) \in f(A)$, so $\alpha(f(a)) = 0 = \beta(f(a))$, that is, $\alpha \circ f = \beta \circ f$. Since f is an epimorphism, $\alpha = \beta$. But $\alpha(b_0) = 0$ while $\beta(b_0) = 1$, a contradiction. Hence f is surjective.

We have mentioned earlier that in category theory, we define objects based on how they relate to other objects. We have in fact done this before, when subgroups were characterized through homomorphisms (proposition 1.4.8).

Definition 8.1.5: Subobject

Let C be a category and $X \in C$ be an object in this category. We say $Y \in C$ is a *suboject* of X is there exists a monomorphism

$$Y \to X$$

To demonstrate what I mean, Let's take an arbitrary set X, and an arbitrary set Y. When can I say that Y is a subset of X, or vice versa? You probably guessed it: if one can be part of included in another, one is a subset of the other. Written in terms of functions: if there exists an inclusion map $i : Y \to X$, then Y is a subset of X ($Y \subseteq X$). We then can define a set being a subset as follows:

If there exists an inclusion map $i : X \to Y$, then X is a subset of Y ($X \subseteq Y$).

If both inclusion maps exist, then there is two injections, and so by the Schröder-Bernstein theorem

(see appendix A), there exists a bijection between X and Y ($|X| = |Y|$). In this way, we can *define* a set to be a *subset* of another set if there exists an inclusion map from Y *to* the bigger set. If we weaken our need for i to be an inclusion map, to i being an injective map, we can start comparing sets with different elements [5]

We can apply this now to groups. By proposition 1.4.8, a subset $H \subseteq G$ which is a group is a subgroup exactly when the inclusion map $H \to G$ is a homomorphism.

Since the same technique is used in defining both concepts, we can say each are similar concepts or types of "objects". Thus, we can say what we have here is applied the more general idea of *sub-object* to both situations.

For sets, injections in both directions give a bijection (Schröder-Bernstein). For groups, injective homomorphisms in both directions give an isomorphism when the groups are finite (proposition 8.1.9), and can fail for infinite groups.

Example 8.1.6: sub-objects

1. **subobjects in Grp**: Recall in proposition 1.4.8 where we showed that if $(H, \bullet)$ is a group and $H \subseteq G$, then H is a subgroup if and only if the inclusion map $i : H \to G$ is a homomorphism. This proposition was the proof that **Grp** had subojects!
2. **subobjects in Set**: by proposition 8.1.2, a monomorphism $Y \to X$ in **Set** is an injective map, which is a bijection from Y onto its image, a subset of X. So the subobjects of X are the sets in bijection with subsets of X.

Definition 8.1.7: Isomorphism In C

Let C be a category, and $f\colon X \to Y$ be a morphism. Then f is said to be an *isomorphism* if there is a morphism $g\colon Y \to X$ with $gf = 1_X$ and $fg = 1_Y$.

Example 8.1.8: Isomorphisms in Different Categories

1. In **Grp**, the isomorphisms are the bijective homomorphisms of definition 1.4.12: the inverse function of a bijective homomorphism ψ is a homomorphism, since $\psi(\psi^{-1}(a)\psi^{-1}(b)) = ab$.
2. In **Set**, the isomorphisms are the bijections, whose inverse functions are again morphisms.
3. In the category of partially ordered sets and order-preserving maps, a bijective morphism need not be an isomorphism. The identity map from $\{a, b\}$ with no relation between a and b to $\{a, b\}$ ordered by $a \leq b$ preserves order, but its inverse does not, as $a \leq b$ holds in the target and fails in the source.

Proposition 8.1.9: Mutual Injections Between Finite Groups

Let G, H be finite groups. If there exist injective homomorphisms $G \to H$ and $H \to G$, then $G \cong H$.

[5] It does not matter what the elements of a set are. What matters is that there *are* arbitrary distinct elements in a set. So being an inclusion or injective is "equivalent" in a broader sense.

***Proof*:**
The injections give $|G| \leq |H| \leq |G|$, so an injective homomorphism $G \to H$ is an injective map between finite sets of the same size. It is therefore bijective, and an isomorphism (definition 1.4.12).

For infinite groups this fails. Let B be the group of sequences $(x_n)_{n\in\mathbb{N}}$ in $\mathbb{Z}/4\mathbb{Z}$ with finitely many nonzero terms, under termwise addition, and let $A = \mathbb{Z}/2\mathbb{Z} \times B$. Then $b \mapsto (0, b)$ is an injective homomorphism $B \to A$, and $(x, (x_n)_n) \mapsto (\iota(x), x_0, x_1, \dots)$ is an injective homomorphism $A \to B$, where $\iota\colon \mathbb{Z}/2\mathbb{Z} \to \mathbb{Z}/4\mathbb{Z}$ sends 1 to 2. But every element of order 2 in B has all its terms in $\{0, 2\}$, so it is twice an element of B, while $(1, 0) \in A$ has order 2 and is not twice any element of A. So $A \ncong B$.

The great advantage of defining subgroup/subset in this way is that we can now define what it means to be a sub-object in many other areas of mathematics! We can even ask whether it is *possible* to define the notion of sub-object. There are some areas in mathematics where the concept of an injective map cannot be defined!![6]

For an object X of a category C, the isomorphisms $X \to X$ (definition 8.1.7) form a group $\mathrm{Aut}_C(X)$ under composition. Composition is associative and 1_X is an identity. If f and f' are isomorphisms with inverses g and g', then $(f \circ f') \circ (g' \circ g) = 1_X = (g' \circ g) \circ (f \circ f')$, so $f \circ f'$ is an isomorphism, and the inverse g of f is an isomorphism with inverse f. For $C = \mathbf{Set}$ the isomorphisms are the bijections (example 8.1.8), and $\mathrm{Aut}_{\mathbf{Set}}(X) = \mathrm{Sym}(X)$. The groups $\mathrm{Aut}_C(X)$ come back when studying *group actions*.

8.2 Commutative diagrams

As mentioned countless times, categories try to capture the idea of relations between objects. Very often, this is done by forcing some relation between morphisms. We have already seen an example of this in the category of **Set** and **Grp** by saying the composition of two functions (or homomorphisms) is again a function (or homomorphism). We represented this by the diagram:

$$X \xrightarrow{f} Y \xrightarrow{g} Z, \quad X \xrightarrow{h} Z$$

where we usually denote h as $g \circ f$. We can form all sorts of relations between objects and enforce the fact that compositions of functions must lead to other arrows. We call this a commutative diagram

Forgetting composition and identities, and keeping only the objects and the arrows, turns a category into a directed graph that may have several arrows between two vertices, called a *quiver*.

Definition 8.2.1: Commutative Diagram

A *diagram* in a category C is a directed graph whose vertices are labelled by objects of C and whose arrows are labelled by morphisms of C between the corresponding objects. The diagram *commutes* if any two directed paths of positive length with the same starting vertex and the same ending vertex give the same morphism when their arrows are composed.

[6] The category of posets $(P, \leq)$ is an example.

Example 8.2.2: Homomorphisms As Commutative Squares
Let G and H be groups, and write $m_G\colon G\times G\to G$ and $m_H\colon H\times H\to H$ for their multiplications. For a function $\varphi\colon G\to H$, let $\varphi\times\varphi\colon G\times G\to H\times H$ send (a,b) to $(\varphi(a),\varphi(b))$. In the category of sets, the square

$$\begin{array}{ccc} G\times G & \xrightarrow{\varphi\times\varphi} & H\times H \\ {\scriptstyle m_G}\downarrow & & \downarrow{\scriptstyle m_H} \\ G & \xrightarrow{\varphi} & H \end{array}$$

commutes exactly when $\varphi(m_G(a,b))=m_H(\varphi(a),\varphi(b))$ for all $a,b\in G$, that is, when $\varphi(ab)=\varphi(a)\varphi(b)$. So φ is a homomorphism exactly when this square commutes.

8.3 Summary

A category (definition 8.0.2) gives objects, morphisms between them, and a composition law; a functor (definition 8.0.4) is the corresponding map between categories; and a commutative diagram (definition 8.2.1) is the notation in which an equality between composites is asserted. Against that backdrop, each notion below replaces a statement about *elements* by a statement about *morphisms*. What permits the replacement in each case is that the two agree in **Set**, where the element-level notion is the familiar one.

Notion in ***Set***	*Categorical form*	*Agreement in* ***Set***
Injective function	Monomorphism (definition 8.1.1)	proposition 8.1.2
Surjective function	Epimorphism (definition 8.1.3)	proposition 8.1.4
Subset $Y\subseteq X$	Subobject (definition 8.1.5)	inherited, the definition being via a monomorphism Y -

The pattern is the one every later categorical definition in this book follows: a property phrased by quantifying over elements is re-phrased by quantifying over morphisms into or out of the object, and the re-phrasing is checked against **Set** before being adopted elsewhere.

Part II

Rings

Now that we have the essentials covered groups, we can move on to structures which have 2 binary operations on the set. These structures are called *rings* [7] As with commutative groups, commutative rings will be very different from rings, so much so that one can think of ring theory as really being 2 seperate domains put under one label: commutative rings and non-commutative rings. However, similarly to how all groups share some common structure (a notion of homomorphism, isomorphism theorem, direct product, free group, group-action, etc.), so do rings, and so we will be building on the foundation of ring theory.

We may wonder how to interpret adding a second binary operation to an abelian group? Does this restrict our structure? Does this limit what we can prove? Does it give more tools to work with when proving? The way I like to perceive adding this second operation is that there are more properties that we have at our disposal to work with. The "type" of new property we add also determines what properties we work with (for example, as is briefly addressed in appendix C.4, we can add a topological structure to groups which gives us different tools we can use to study groups). In the case of adding a new binary operations, we gain more "algebraic" tools to work with. For example, we have an understanding of how the prime numbers of $\mathbb{N}$ interact when we add them[8] or when we multiply them, but we have little knowledge of the interaction of prime numbers between these two binary operations. Furthermore, for any abelian group, we can always add at least one new binary operation that satisfies the axioms of a ring[9] (which we will present near the end of section 9.1.1). In that way, all groups can be made into rings, and we can study them as rings.

For the 1st operation, we will always use additive notation. For example, if we are taking the internal direct product of two groups in this notation, we will write $H + K$, since we will reserve the multiplicative notation for the 2nd binary operation.

[7] The term *ring* was probably a contraction of David Hilbert's term *Zahlring*, literally translated as *number ring*. The word ring was probably coined because of the cyclic nature of the numbers Hilbert was working with. More details on this discussion can be found here: https://math.stackexchange.com/questions/61497/why-are-rings-called-rings

[8] All be it to a very limited degree

[9] Similarly to how all abelian groups are topological groups with the discrete topology

9

Introduction To Rings

With Groups extensively covered, what's "basic" has now changed. We need not so extensively elaborate intuitions for homomorphisms, quotients, products, or actions. Instead, we will show how these concept grow when considering *rings*. Fundamentally, a ring is a set with two operators (hence, is a triple $(R, +, \cdot)$ where $+$ and $\cdot$ satisfy certain axioms[1]).

As with groups homomorphisms, "ring homomorphisms" will play a central role in the study of rings. There will be an equivalent to "normal groups" which we will extensively study: the equivalent for rings is called *ideals*. Manipulating and combining ideals is at the core of ring theory. After exploring ideals, we will take a moment to look at a way to embedd any ring R into a larger ring that permits the notion of "division" (as we will see, unlike groups, not all elements of a ring will have an inverse with the second operation). Through this construction, we will show how to take $\mathbb{Z}$ and create $\mathbb{Q}$.

[1] One source of the axioms: the endomorphisms of an abelian group, under pointwise addition and composition, satisfy all of them (section 9.1.1).

9.1 Basic Properties and Definitions

Definition 9.1.1: Ring

A *ring* R is a set together with two binary operations $+$ and $\cdot$ (called addition and multiplication), $(R, +, \cdot)$ satisfying the following axioms:

1. $(R, +)$ is an *abelian* group, where the identity is denoted by 0
2. **(Mult. Associativity)** $(a \cdot b) \cdot c = a \cdot (b \cdot c)$ for all $a, b, c \in R$
3. **(Mult. Identity)** There exists an $e. \in R$ such that for every $r \in R$, $e. \cdot r = r \cdot e. = r$. The element $e.$ is usually labeled 1.
   - Sometimes, we use *rng* to denote a ring without multiplicative identity.
4. **(Distributivity)** For all $a, b, c \in R$

   $$a \cdot (b + c) = (a \cdot b) + (a \cdot c) \qquad \text{and} \qquad (a + b) \cdot c = (a \cdot c) + (b \cdot c)$$

   The two equations separately are called left and right distributively respectively.

If $a \cdot b = b \cdot a$ for all $a, b \in R$, we call the ring a *commutative ring*.

We will usually write $a \cdot b$ as ab for convenience. The convention that the multiplicative identity is 1 and additive identity is 0 is essentially universal, and so it is safe enough to have it as part of the definition of a ring.

9.1.2 Ring always has identity? Some author's do not include 1 in the definition of a ring (we called rings without a (multiplicative) identity *rng*). In this case, a ring with a multiplicative identity is usually called a unital ring. Any *rng* R can be extended to a ring by taking $\mathbb{Z} \oplus R$ with identity $(1, 0)$ (What is the multiplication here that makes $\mathbb{Z} \oplus R$ into a ring?)[a]. The most common place in mathematics where mathematicians usually do not want rings to have identities is in analysis. For those inclined towards examples see [80]. In Algebra, it is now pretty rare to find a textbook that define a ring without a multiplicative identity, however some classical textbooks have done so (for example [48] and [60])

[a] If R is an algebra over a commutative ring k, the same construction with k in place of $\mathbb{Z}$ adjoins an identity and keeps the k-algebra structure.

Just like associativity was a powerful axiom, so is distributivity for linking the $+$ operation and the $\times$ operation. If you have any arbitrary expression:

$$(a + b)(c + d + e(f + g(i + j)kl(m + n)op))q$$

It can be simplified to the sum of monomials:

$$ac + bc + ad + bd + aefq + befq + aegiklmopq + begiklmopq + aegjklmopq$$
$$+begjklmopq + aegiklnopq + begiklnopq + aegjklnopq + begjklnopqq$$

There are non-distributive algebraic structures. However, the study of non-distributive structures seems to be much scarser than that of non-associative structures or structures without inverse. [2]. Distribuitivity seems to be how most structure link the two operations. At the minimum it usually would be distributive on only one side [3].

9.1.3 Note R being an abelian group is unavoidable given the distributive property

$$a+b+a+b=(1+1)(a+b)=a+a+b+b \Rightarrow a+b=b+a$$

Another way to think about G being abelian is that we want to concentrate on the *ring* operation now, so if we can make the group-operation very-well behaved (as we have shown commutativity does in chapter 5), it will not obtrude our study of the ring operation. This is a common technic.

Example 9.1.4: Ring Examples

1. Taking any abelian group G, and define $a \cdot b = 0$. This is the *trivial ring*. If If $G = \{0\}$, then we call this the *zero ring*. In fact, all $ab = 0$ for all $a, b \in R$ if and only if R is the zero ring:

   Proof. If R is the zero ring, then we already have that $0 \cdot 0 = 0$. Thus, we must prove the converse

   Let's say $\forall a, b \in R$, $ab = 0$. Then $1 \cdot 1 = 0$, meaning $1 = 0$

   Then, notice that

   $$\begin{aligned} &\Leftrightarrow\ 0 \cdot a = (0+0) \cdot a = 0 \cdot a + 0 \cdot a \\ &\Leftrightarrow\ 0 \cdot a = 0 \cdot a + 0 \cdot a \\ \Leftrightarrow\ 0 \cdot a - 0 \cdot a &= 0 \cdot a + 0 \cdot a - 0 \cdot a \qquad \text{additive inverse} \\ &\Leftrightarrow 0 = 0 \cdot a \end{aligned}$$

   Thus, we have $0 = 0 \cdot a = 1 \cdot a = a$ for all a, and so all element equal 0, showing it's a zero ring. □

   In fact, this proof has a very powerful corollary: if $1 = 0$, then we have the zero ring! This property usually breaks many parts of many proofs, so we usually say that $1 \neq 0$ in most theorems and propositions. In some textbooks, this is even part of the axioms of a ring

2. The integers $\mathbb{Z}$ is the canonical example of a ring. When ring theory started, a lot of study was with trying to characterize properties of integers. Note that $ab = ba$, making $\mathbb{Z}$ a *commutative ring*.

3. $\mathbb{Z}/n\mathbb{Z}$ is a [commutative] ring with identity

4. $\mathbb{R}, \mathbb{Q}, \mathbb{C}$ are all [commutative] rings with identity. Naturally, $\mathbb{N}$ is not [a]

5. If R and S are rings, then $R \times S$ is also a ring with operation component wise. [b]. What is the identity of $R \times S$?

[2] I found this paper: generalized De Morgan algebra
[3] Something called a *Quasifields* is an example

6. If you have taken Linear Algebra, then all fields are an example of [commutative] rings

7. Recall the group Q_8 (see section 1.2.4). Using it, we will define the set $\mathbb{H} = \{a + bi + cj + dk \mid a, b, c, d \in \mathbb{R}\}$ where the elements bi, cj, an dk are distinct elements of $\mathbb{H}$, and are not another element in $\mathbb{R}$ or Q_8 (think of a, b, c, d as coefficients). Then we can make $\mathbb{H}$ into a ring by defining addition to be ponitwise:

$$(a + bi + cj + dk) + (a' + b'i + c'j + d'k) = (a + a') + (b + b')i + (c + c')j + (d + d')k$$

and multiplication through repeated use of the distributive property, which distributes to:

$$\begin{aligned}(a + bi + cj + dk)(a' + b'i + c'j + d'k) = &(aa' - bb' - cc' - dd') \\ &+ (ab' + ba' + cd' - dc')i \\ &+ (ac' - bd' + ca' + db')j \\ &+ (ad' + bc' - cb' + da')k\end{aligned}$$

Then $\mathbb{H}$ is called the ring of *quaternions*. It is a non-commutative ring containing the complex numbers $\mathbb{C} = \{a + bi \mid a, b \in \mathbb{R}\}$, and in fact infinitely many copies of $\mathbb{C}$: each $u = bi+cj+dk$ with $b^2 + c^2 + d^2 = 1$ satisfies $u^2 = -1$, so $\{a + a'u \mid a, a' \in \mathbb{R}\}$ is a subring isomorphic to $\mathbb{C}$.

8. If X is a set and A is a ring, then the collection of all function $f : X \to A$ are a ring with function addition and multiplication being done point-wise: $(f + g)(x) = f(x) + g(x)$, $(fg)(x) = f(x)g(x)$. All ring structure on this function space comes from A. A concrete example of this is if $X = [0, 1]$, $A = \mathbb{R}$, and f is continuous $f : [0, 1] \to \mathbb{R}$. These types of rings show up a lot in analysis with the collection of function from a space X (a topological space, or measurable space, a manifold, etc.) to $\mathbb{R}$ or $\mathbb{C}$ giving many properties of the domain of the functions.

9. The set $2\mathbb{Z}$ is not a ring since it does not have an identity. It is thus a *rng*.

10. From section 1.2.5⋆, we saw that $(M_n(G), \cdot)$ is not necessarily a group since inverses were not not always defined. However, this is not a requirements for ring multiplication! It is very tedious and a bit hard at this stage to check that associativity and distributivity hold (there will be a simple proof of this in corollary 13.2.7), but they are verifiable and show that $(M_n(R), +, \cdot)$ is a ring. Note that $M_n(R)$ is not commutative. For example

$$\begin{pmatrix} 1 & 0 \\ 1 & 0 \end{pmatrix} \cdot \begin{pmatrix} 1 & 1 \\ 0 & 0 \end{pmatrix} \neq \begin{pmatrix} 1 & 1 \\ 0 & 0 \end{pmatrix} \begin{pmatrix} 1 & 0 \\ 1 & 0 \end{pmatrix}$$

Matrix rings will be explored in more detail soon, and will have a whole chapter (in particular chapter 53) dedicated to the study of when matrix rings "act" on finite groups (in a similar way groups acted on sets in group-actions).

11. Recall when I asked if $P(X)$ is a group under $\cup$? Here is another similar question with rings. Take $P(X)$ again, and define addition and multiplication as

$$A + B = (A - B) \cup (B - A) \qquad A \cdot B = A \cap B$$

prove that it's a [commutative ring]. Another thing you can show is that for any $Y \in P(X)$, $Y^2 = Y$. If a ring has this property, it is said to be a *boolean ring*. [c]

12. Let G be any abelian group. Then $(\text{End}_{\mathbf{Grp}}(G), +, \circ)$ is a ring. In this way, any ring is formed from an abelian group. [d]

[a] $\mathbb{N}$ is a semi-ring with $+$ and $\cdot$

[b] Though this might feel "trivially true", the fact that taking the direct product of two rings will produce the same algebraic structure, in this case a ring, is not always true! See example 9.1.27 for a counter-example

[c] This ring comes up in *measure theory*, where the set of measurable sets can be made into a boolean ring

[d] The general term for taking [abelian] objects (ex. abelian groups) from an category C and working with $\text{End}(X)$ as the new object and morphisms that also preserve $\circ$ is **Ab**-enriched category given the abelian category C

When working with rings, we will assume the usual ring structure for $\mathbb{Z}, \mathbb{Q}, \mathbb{R}$ and $\mathbb{Z}/n\mathbb{Z}$, and use the same notation if it's clear in context. The notation $\mathbb{Z}^\times, \mathbb{Q}^\times, ...$ will soon be repurposed for another use later in this section.

Note that every ring is naturally an abelian group as well as a monoid (see section 7.1). When working with homomorphisms for rings, both structure need to be preserved in some way for the image of a funciton to be a ring. There is in fact one more sneaky criterion that needs to be added in order for a the image of a function be be a ring, and hence a *ring homomorphism*:

Definition 9.1.5: Ring Homomorphism

Let R and S be rings. Then:

1. A *ring homomorphism* is a map $\varphi\colon R \to S$ satisfying, for all $a, b \in R$,
   (a) $\varphi(a+b) = \varphi(a) + \varphi(b)$
   (b) $\varphi(a \cdot b) = \varphi(a) \cdot \varphi(b)$
   (c) $\varphi(1_R) = 1_S$
2. If $\varphi\colon R \to S$ is a ring homomorphism, and there exists a ring homomorphism $\psi\colon S \to R$ with $\psi \circ \varphi = \text{id}_R$ and $\varphi \circ \psi = \text{id}_S$, then φ is a ring isomorphism

Note that just like for group homomorphisms, a ring homomorphism φ is a ring isomorphism exactly when it is bijective. A ring isomorphism has the inverse map ψ, so it is bijective. Conversely, if φ is bijective, its inverse map ψ satisfies $\varphi(\psi(x)\psi(y)) = \varphi(\psi(x))\varphi(\psi(y)) = xy$, so $\psi(xy) = \psi(x)\psi(y)$ by injectivity of φ, and in the same way $\psi(x+y) = \psi(x) + \psi(y)$ and $\psi(1_S) = 1_R$.

Note that the reason we add the condition that $\varphi(1_R) = 1_S$ is so that the image $\varphi(R)$ is a subring of S. If a ring is not defined to have a multiplicative identity (as is done for *rngs*), then the condition $\varphi(1_R) = 1_S$ is not necessary. Furthermore, where $\psi(e_G) = e_H$ is a provable property given that ψ is a group-homomorphism and e_G, e_H are the respective identities of the domain and codomain, the same is not true for rings: the first 2 conditions of a ring homomorphism can hold while $\varphi(1_R) \neq 1_S$. The map $\mathbb{Z} \to \mathbb{Z} \times \mathbb{Z}$, $n \mapsto (n, 0)$, preserves sums and products, and its image $\mathbb{Z} \times \{0\}$ is a ring with identity $(1, 0)$, but it is not a subring of $\mathbb{Z} \times \mathbb{Z}$, whose identity is $(1, 1)$.

Many times, mathematical objects will have multiples different structures defined on them, but we sometimes want to only work with some of them[4]. Thus, a group homomorphism between rings will only preserve group structure, while a ring homomorphism preserves both. Section 9.3 relates the structure of $\varphi(R) \subseteq S$ to that of R, as was done with quotient groups.

[4] An example with full of different structures is $\mathbb{R}$ which can come with a group, ring, and order and structure, but also structures that we have not covered, some of which are non-algebraic (ex. completeness (see uniformly continuous functions and uniform spaces), or topological)

From definition 9.1.5, we can define a sub-ring:

Definition 9.1.6: Sub-Ring

Let R be a ring and $S \subseteq R$ a subset. Then S is a *subring* of R if it is a ring under the operations of R and $1_R \in S$, that is, if the inclusion map $i : S \to R$ is a ring homomorphism[a].

[a] See proposition 1.4.8

Corollary 9.1.7: sub-ring condition

A subset S of a ring R is a subring if and only if S is an additive subgroup of R that is closed under multiplication and contains 1_R.

***Proof*:**
If S is a subring, it is a ring under the operations of R, so it is an additive subgroup closed under multiplication, and $1_R = i(1_S) = 1_S \in S$ because the inclusion i is a ring homomorphism. Conversely, such an S is an abelian group under $+$, multiplication restricts to an associative operation on S that distributes over $+$ because it does on R, and $1_R \in S$ is an identity for it. So S is a ring, and the inclusion preserves sums, products and 1, completing the proof.

Notice that there is no special symbol for a subring like there as for subgroup. This will be a recurring pattern as we continue to explore algebra: there is no special symbol for "subobjects". We will always say "Let S be a subring of R" or "Let $S \subseteq R$ be a subring of R".

One subring is available in every ring and measures how far the multiplication is from being commutative. It is the ring-theoretic analogue of definition 2.2.4, and unlike the group case it is a subring rather than merely a subgroup.

Definition 9.1.8: [Ring] Center

Let R be a ring. The *center* of R is

$$Z(R) := \{c \in R \mid cx = xc \text{ for all } x \in R\}$$

the set of elements commuting with every element of R. A ring is commutative exactly when $Z(R) = R$.

That $Z(R)$ is a subring is immediate from corollary 9.1.7: it contains 0 and 1, it is closed under subtraction since $(c - c')x = cx - c'x = xc - xc' = x(c - c')$, and it is closed under multiplication since $(cc')x = c(c'x) = c(xc') = (cx)c' = x(cc')$. It is commutative, being a set of pairwise commuting elements, so the center of any ring is a commutative ring.

Proposition 9.1.9: Properties of Rings

Let R be a ring. Then:

1. $0a = a0 = 0$ for all $a \in R$
2. $(-a)b = a(-b) = -(ab)$ for all $a, b \in R$ (recall $-a$ is the additive inverse)
3. $(-a)(-b) = ab$ for all $a, b \in R$
4. The multiplicative identity is unique and $-a = (-1)a$.
5. Generalized Distribuitivity: for all $a, b_1, \ldots, b_n \in R$

$$a(b_1 + \cdots + b_n) = ab_1 + \cdots + ab_n \qquad (b_1 + \cdots + b_n)a = b_1a + \cdots + b_na$$

and hence $(a_1 + \cdots + a_m)(b_1 + \cdots + b_n) = \sum_{i=1}^{m} \sum_{j=1}^{n} a_i b_j$ for all $a_i, b_j \in R$.

***Proof*:**
All of these proofs take advantage of the abelian structure of R and distributivity. Sums of several terms need no brackets by the generalized associative law in the group $(R, +)$ (proposition 1.1.15(5)).

1. Using the fact that 0 is an additive identity and distribuitivity, we get:

$$0 \cdot a = (0 + 0)a = 0 \cdot a + 0 \cdot a$$

Since $0 \cdot a \in R$, there exists an additive inverse, thus

$$0 \cdot a - 0 \cdot a = 0 \cdot a + 0 \cdot a - 0 \cdot a$$

implying $0 = 0 \cdot a$. In the same way $a \cdot 0 = a(0 + 0) = a \cdot 0 + a \cdot 0$, and adding $-(a \cdot 0)$ to both sides gives $0 = a \cdot 0$.

2. By distributivity and (1), $ab + (-a)b = (a + (-a))b = 0b = 0$, so $(-a)b$ is an additive inverse of ab, and inverses in the group $(R, +)$ are unique (proposition 1.1.15(2)), so $(-a)b = -(ab)$. Likewise $ab + a(-b) = a(b + (-b)) = a0 = 0$ gives $a(-b) = -(ab)$.

3. By (2), applied first to a and $-b$ and then to a and b, $(-a)(-b) = -(a(-b)) = -(-(ab))$, and $-(-(ab)) = ab$ by proposition 1.1.15(3).

4. If e and e' are both multiplicative identities, then $e = ee' = e'$. By (2), $(-1)a = -(1a) = -a$.

5. By induction on n, the case $n = 1$ being trivial. If the first identity holds for n, then distributivity gives

$$a(b_1 + \cdots + b_{n+1}) = a(b_1 + \cdots + b_n) + ab_{n+1} = ab_1 + \cdots + ab_n + ab_{n+1}$$

and the second identity follows in the same way from right distributivity. For the last claim, the second identity with $a = b_1 + \cdots + b_n$ gives $(a_1 + \cdots + a_m)a = a_1a + \cdots + a_ma$, and the first identity expands each a_ia into $a_ib_1 + \cdots + a_ib_n$, completing the proof.

In particular, $(-1)^2 = (-1)(-1) = 1 \cdot 1 = 1$ by proposition 9.1.9(3).

Consequences of no Multiplicative Inverse

Now that we know what is needed to be a ring, let's put names to common rings with properties added on. For each of these properties, I would recommend to go back and see which rings we covered have these properties. If you want to verify your intuition, you can check the glossary (see Part XIV).

The first thing is that the multipication operation is missing one of the axioms of a group: elements need not have a multiplicative inverse. If every element has a multiplicative inverse, we will give a name to such a ring:

Definition 9.1.10: Division Ring

A ring R with identity 1, where $1 \neq 0$ is called a *division ring* (or a *skew field*) if every non-zero element $a \in R$ has a multiplicative inverse, $b \in R$ such that $ab = 1$.

The inverse b of a nonzero a in a division ring also satisfies $ba = 1$. Here $b \neq 0$, since $a0 = 0 \neq 1$ (proposition 9.1.9(1)), so $bc = 1$ for some $c \in R$, and then $a = a(bc) = (ab)c = c$, that is, $ba = bc = 1$.

If furthermore, multipication is commutative, the resulting ring is a commutative division ring, whcih is called *field*:

Definition 9.1.11: Field

Let F be a divison ring. If F is also *commutative*, then F is called a *field*.

Sometimes, the symbol k (from German Körper) or $\mathbb{F}$ will be used for a field. The field is the "smallest" mathematical structure in which we can perform all the standard arithmetic operations $+, -, \times, \div$ in the usual way. If R is a field, then it is as though there is two compatible abelian group structures (both are associatve, have an identity, have an inverese, both commute), the two operations being linked through distributivity. In particular, it's like $(R, +)$ and $(R - \{0\}, \cdot)$ are combined through distributivity. . If R is a field, we can call the sub-rings of R a sub-field. For example, $\mathbb{Q}$ is a subfield of $\mathbb{R}$.

Example 9.1.12: Subfields Of $\mathbb{R}$ Contain $\mathbb{Q}$

Every subfield K of $\mathbb{R}$ contains $\mathbb{Q}$. The identity 1_K of K satisfies $1_K 1_K = 1_K \neq 0$, and multiplying by its inverse in $\mathbb{R}$ gives $1_K = 1$. As K is closed under addition and additive inverses, it contains $n = 1 + \cdots + 1$ and $-n$ for every $n \in \mathbb{N}$, so $\mathbb{Z} \subseteq K$. As K is closed under multiplication and inverses of nonzero elements, it contains mn^{-1} for all $m, n \in \mathbb{Z}$ with $n \neq 0$, so $\mathbb{Q} \subseteq K$.

Zero divisors and Units

If a ring is not a division ring, then the cancellation property does not necessarily hold (see proposition 1.1.17). In groups, we constantly take advantage of the fact that $ab = ac \Rightarrow b = c$. This proof relied on the [unique] inverse of elements. However, there are rings in which this does not happen

Example 9.1.13

Let $R = \mathbb{Z}/6\mathbb{Z}$ with the usual addition and multiplication. First, show that it's a ring.

Then, notice that [2] times any number in $\mathbb{Z}/6\mathbb{Z}$ is not [1] (i.e. there does not exist $[a]$ such that $[2][a] = [1]$):

$$[2][1] = [2]\,, [2][2] = [4]\,, [2][3] = [0]\,, [2][4] = [2]\,, [2][5] = [4]$$

Furthermore, there exists an element ([3]) such that [2] times it gives the additive identity: $[2][3] = [0]$

So it breaks down! You might wonder if for any $a \in R$ if there exists an element b such that $ab = 0$ or $ab = 1$, but that need not be the case:

Example 9.1.14: No Multiplicative Inverses

In $\mathbb{Z}$ with the usual addition and multiplication, take any $a \in \mathbb{Z}$, $a \notin \{0, 1\}$. Then there does not exist an element b such that $ab = 1$, which is shown by $\mathbb{Z}$ not having multiplicative inverse, but also $ab = 0$ cannot happen in $\mathbb{Z}$ for any $b \in \mathbb{Z}$

Thus, one cannot imply the other in general

You might further wonder if for any $a \in R$ that only $ab = 0$ happens or only $av = 1$ happens, that is, if there exists an element $b \in R$ such that $ab = 0$, then there does *not* exist an element $v \in R$ such that $av = 1$ (or vice versa). However, this again is not the case! What if $ab = 0$, or $ab = 1$, does that means $ba = 0$ or $ba = 1$? Also no (in the non-commutative case)!

Example 9.1.15

1. Take S to be the set of all infinite sequences. This set, under component-wise addition, is a group. Then take $\text{End}(S)$, making function composition multiplication. Then this is a ring with identity.

2. Prove that

$$P(a_1, a_2, ..., a_n, ...) = (a_1, 0, ..., 0, ...) \tag{9.1}$$
$$L(a_1, a_2, ..., a_n, ...) = (a_2, a_3, ..., a_{n-1}, ...) \tag{9.2}$$
$$R(a_1, a_2, ..., a_n, ...) = (0, a_1, ..., a_{n+1}, ...) \tag{9.3}$$
$$0(a_1, a_2, ..., a_n, ...) = (0, 0, ..., 0, ...) \tag{9.4}$$
$$1(a_1, a_2, ..., a_n, ...) = (a_1, a_2, ..., a_n, ...) \tag{9.5}$$
$$\tag{9.6}$$

   are all elements in $\text{End}(S)$ $(L, R, P, 0, 1 \in \text{End}(S))$

3. Show that $LP = 0$, but $LR = 1$. Then, show that $PL \neq 0$ (so $LP = 0$, but $PL \neq 0$)

4. You just showed that $LR = 1$. Show that $RL \neq 1$.

Since it's not commutative, it's not imediately clear that since we found an example where $ab = 0$ but $ac = 1$, then we can find the same but multiplying from the left side. However, we can construct exactly such an example from the previous example:

1. Define $\text{End}(S)^{op}$ to be the object where function composition is reversed:

$$f \cdot g = g \circ f$$

show that $\text{End}(S)^{op}$ is still a ring. Convince yourself that all the previous elements $(1) - (5)$ are in $\text{End}(S)^{op}$.

2. Show that $PL = 0$, but $RL = 1$. Then, show that $PL \neq 0$ (so $LP = 0$, but $PL \neq 0$)

So, we cannot carry over our intuition of the cancellation property into general rings! However, thanks to associatvity, there is *one* relation we can prove: if $ab = 0$, then there does not exist a c such that $ca = 1$. That is, if there exists an element b such that $ab = 0$, then there does not exist a c such that $ca = 1$:

Proposition 9.1.16: Partial Result for ab and ca

Let $a \in R$ such that there exists an element $b \in R$ such that $ab = 0$ (or $ba = 0$). Then there does not exist an element c such that $ca = 1$ (or $ac = 1$), that is:

$$\begin{matrix} ab = 0 \\ ca \neq 1 \end{matrix} \quad \text{and} \quad \begin{matrix} ab = 1 \\ ca \neq 0 \end{matrix}$$

***Proof*:**
Take $a \in R$ as in the proposition. Let's say there exists a $b \in R$, $b \neq 0$, such that $ab = 0$. Let's say there is a c such that $ca = 1$, $c \neq 0$. Then:

$$b = 1b = (ca)b = c(ab) = c(0) = 0$$

a contradiction since $b \neq 0$

Let's say there exists a $b \in R$, $b \neq 0$, such that $ba = 1$. Let's say there is a c such that $ac = 0$, $c \neq 0$.

$$c = 1c = (ba)c = b(ac) = b \cdot 0 = 0$$

a contradiction since $c \neq 0$

Note that as a consequence of this theorem, if an element a has a left-sided inverse l and ar right-sided inverse r, then $l = r$, since:

$$l = l1 = l(ar) = (la)r = 1r = r$$

Since multiplicative inverses can either multiply to 1, to 0 or to neither, we will take a moment to name elements that can multiply into 1, 0, or neither:

Definition 9.1.17: Zero Divisors and Units

Let R be a ring.

1. Let $a \in R$ be a nonzero element. Then a is called a *left* (resp. *right*) *zero divisor* if there is a nonzero element $b \in R$ such that ab (resp. ba) equals to 0. If $ab = ba = 0$, then a is called a *two-sided zero divisor*, or simply a *zero-divisor*
2. Assume $1 \neq 0$. An element u of R is called a left (resp. right) *unit* in R if there is some v in R such that vu (resp. uv) equals to 1. If $uv = vu = 1$. , then u is called a *two-sided unit*, or simply *unit* for short

If R is commutative, then there is no distinction between left and right zero-divisors/units.

The term zero-divisors comes from the following observation: if $ab = n$ in a commutative ring for simplicity, then we may say that $a|n$ and $b|n$ (i.e. a, b divide n). Then if $ab = 0$, then "$a\big|0$" and "$b\big|0$", so a, b divide 0 (they are *zero-divisors*). This notion of divisibility shall further be explored in chapter 10. Note that if u is a unit of R so that there is some v such that $uv = vu = 1$, then v is unique (think of the same proof for groups). The same is not the case for zero-divisors (try playing around in $\mathbb{Z}/10\mathbb{Z}$). Since any unit must be a two-sided inverse, we can define the following:

Proposition 9.1.18: Group of Units

Let R be a commutative ring, and let $R^\times$ denote the set of all units of R. Then $R^\times$ is a group under $\cdot$, and is called the *group of units of* R

***Proof*:**
Associativity comes from associativity of multiplication, multiplicative identity comes from the fact that 1 is a unit, and inverses come from the definition of units.

It only remains to show that $\cdot$ is indeed a well-defined operation. Does it map units of R to units of R. Take $a, b \in R^\times$. Since both are units, then there exists a u and v st $au = ua = bv = vb = 1$. Then I claim that vu is the element such that $(vu)(ab) = 1$. Indeed:

$$(vu)(ab) = v(ua)b = v \cdot 1 \cdot b = v \cdot b = 1$$

Thus $ab \in R^\times$, showing it is indeed well-defined as we sought to show

Sometimes, the group of units of R is denoted $U(R)$, R^*, or $E(R)$ (from German *Einheit*, meaning "oneness") Notice how this let's us characterize division rings and fields in a new way: if every non-zero element of a ring (resp. commutative ring) is a unit, the ring is then a division ring (resp. field). Note too that it is not always obvious when a ring can be characterized as a field in this way:

Example 9.1.19: Every Element is a Unit

Let D be a not-a-perfect square rational number [a] Then take $\mathbb{Q}(\sqrt{(D)}) \subseteq \mathbb{C}$,

$$\mathbb{Q}(\sqrt{(D)}) := \left\{ a + b\sqrt{(D)} \;\middle|\; a, b \in \mathbb{Q} \right\}$$

Note that if $D > 0$, then $\mathbb{Q}(\sqrt{D}) \subseteq \mathbb{R}$. This set is indeed a ring since

$$\forall x, y \in \mathbb{Q}(\sqrt{5}) \qquad a + b\sqrt{D} - c - d\sqrt{D} = (a - c) + (b - d)\sqrt{D}$$
$$\forall x, y \in \mathbb{Q}(\sqrt{5}) \qquad (a + b\sqrt{D})(c + d\sqrt{D}) = (ac + bdD) + (ad + bc)\sqrt{D}$$

showing it's indeed a [commutative] ring.Note that D being not-a-square implies every element can be written uniquely. If it were a square, say 9, then

$$2\sqrt{9} = 6$$

meaning two elements were written the same way! Because of this, if a, b are non-zero, then $a^2 - b^2D$ is non-zero. For example, if $D = 4$, then

$$4^2 - 2^2 4 = 16 - 16 = 0$$

but Since D is not-a-square,

$$a^2 - b^2D = 0 \Rightarrow a^2 = b^2D \Rightarrow \frac{a^2}{b^2} = D \Rightarrow \frac{a}{b} = \sqrt{D}$$

which since D is not-a-square, it's square-root is not a rational number [b], hence a contradiction. Thus, $a^2 - b^2D$ is non-zero if a, b are non-zero. The point of this is to notice that

$$(a + b\sqrt{D})(a - b\sqrt{D}) = a^2 - b^2D$$

then $a + b\sqrt{D}$, $a - b\sqrt{D}$ must both be non-zero! Thus, we can define

$$\frac{a - b\sqrt{D}}{a^2 - b^2D}$$

to be the inverse of $a + b\sqrt{D}$! This shows that every non-zero element of $\mathbb{Q}(\sqrt{D})$ is a unit, and hence it's a field!

[a] perfect square number: $x \in X$ such that $\sqrt{x} \in X$
[b] A similar proof to that of $\sqrt{2}$ is not rational!

This also means that since every element in a field has a multiplicative inverse, a field has *no* zero-divisors.

As we saw, if x is *not* a zero divisor, this does not imply that x *is* a unit, and vice-versa, as we have seen with the integers. However, in the finite case, this *does* hold

Proposition 9.1.20: In finite ring, not zero divisor ⇒ unit

If R is a finite ring, and $x \in R$ is *not* a zero-divisor, then x is a unit

***Proof*:**
The key idea of finiteness is that we can take advantage of forcing injective maps being surjective. Withought loss of generality, when there are zero divisors, we take the left zero divisors. The proof for right zero-divisors works identically by switching the order of the elements.

Let's say $x \in R$ is not a left zero divisor so that for no element $y \in R$ there is $xy = 0$. If $x = 1$, we are done, so let's say $x \neq 1$. Define the map $y \mapsto xy$. [a]. Since for no y there is $xy = 0$, then this map is injective. Since R is finite and the map is from R to R, then this map is also surjective. Thus, there exists a y' such that $xy' = 1$. It remains to show that $y'x = 1$.

The element x can either be a right zero-divisor or it can not be. If it is not a right-zero divisor, then the map the map $y \mapsto yx$ would be injective, and hence surjective, and we can find an element y'' such that $y''x = 1$. So, let's say x was a right zero-divisor. If it was a right zero-divisor, then there would exist a $z \in R$ such that $zx = 0$, and x would be a right, but not a left zero-divisor. However, there exists a y' such that $xy' = 1$, which is a contradiction by proposition 9.1.16. Therefore, in the finite case, if x is a right zero-divisor, it would also have to be a left zero-divisor

Therefore, x is not a zero-divisor, so we can again define the map $y \mapsto yx$ which is also injective, and so there exists a y'' such that $y''x = 1$. Finally, notice that:

$$y' = 1 \cdot y' = (y''x) \cdot y' = y'' \cdot 1 = y''$$

showing that $y' = y''$ and so $xy' = y'x = 1$, fulfilling the condition for x being a unit, as we sought to show.

[a] Tangentially, note that this function is not in general a ring homomorphism. Can you see why?

No Zero-Divisors: Integral Domains

Numbers as they are generally known do not have zero divisors (ex. $\mathbb{N}, \mathbb{Z}, \mathbb{Q}, \mathbb{R}, \mathbb{C}$). A large part of the study of rings is the study of number theory, and so defining rings which do not have zero divisors is important for ease of communication:

Definition 9.1.21: Integral Domain

A commutative ring with identity $1 \neq 0$ is called *integral domain* if it has a no zero divisors

Example 9.1.22: Integral Domains

1. $\mathbb{Z}$ is the canonical example, even the name-sake
2. $\mathbb{Q}$ and $\mathbb{R}$ are integral domains. Note that every (nonzero) elements are also units
3. $(\mathrm{GL}_n(\mathbb{F}), +, \cdot))$ is an integral domain
4. $M_n(F), +, \cdot)$ is not an integral domain, since

$$\begin{pmatrix} 1 & 0 \\ 0 & 0 \end{pmatrix} \cdot \begin{pmatrix} 0 & 0 \\ 0 & 1 \end{pmatrix} = \begin{pmatrix} 0 & 0 \\ 0 & 0 \end{pmatrix}$$

5. Let $F = \mathrm{Hom}_{\mathbf{Set}}(X, R)$ be a collection of functions where $|X| > 2$ $R \neq \{0\}$. As noted in example 9.1.4 this is a ring. This ring is not an integral domain. Let $a, b \in X$, $a \neq b$, and $x \in R$, $x \neq 0$. Then define a function where $f(a) = 0, f(b) = x$, and the rest of the elements of f map to zero, and define $g(a) = x, g(b) = 0$, and the rest of the elements of g map to

zero. Note that f and g are not the zero function since they are not identically zero, but $fg = 0$. Importantly

$$fg(a) = f(a)g(a) = 0x = 0 \qquad fg(b) = f(b)g(b) = x0 = 0$$

The set of functions from a set X to a ring R is rarely an integral domain when $|X| > 0$ and $R \neq \{0\}$, since it would have to be the case that $fg = 0$ implies that either f is zero everywhere or g is zero everywhere. However, they do exist (an important example in complex analysis is the ring of power-series, or more generally the ring of analytic functions).

Sometimes the term *domain* used for the same type of ring without the commutative property:

Definition 9.1.23: Domain

A ring in which there are no zero-divisors is called a domain

The nicest property of integral domains is that the cancellation law holds!

Proposition 9.1.24: Cancellation Law for Integral Domains

Assume a, b, c are elements of any ring with a not a zero divisor. If $ab = ac$, then either $a = 0$ or $b = c$.

***Proof*:**

$$\begin{aligned} & ab = ac \\ \Leftrightarrow\ & a(b-c) = 0 \\ \Leftrightarrow\ & a = 0 \text{ or } b - c = 0 \\ \Leftrightarrow\ & a = 0 \text{ or } b = c \end{aligned}$$

With this property of integral domains, proposition 9.1.20 can be expanded upon:

Corollary 9.1.25: Finite Integral Domain is a Field

If R is a finite integral domain, then R is a field

Just like in proposition 9.1.20, the trick in this proof is a neat use of function to capture the idea of how an element acts on every other element in an object, not unlike how we can think when working with group actions:

***Proof*:**
Let R be a finite integral domain. and let a be a nonzero element of R. By the cancellation law the map $x \mapsto ax$ is an injective function. To see this, let's say it was not injective so $ax = ay$ but $x \neq y$. Then

$$ax - ay = 0 \quad \Rightarrow \quad a(x - y) = 0$$

Since a is non-zero and there are no zero divisors, it must be that $x - y = 0$, so $x = y$.

Now, since the map is injective, its image has $|R|$ elements, so it is surjective[a]. In particular, there is some $b \in R$ such that $ab = 1$. Since R is commutative, also $ba = 1$, so a is a unit in R.

Since a was arbitrary nonzero element, R is a field.

[a] For infinite sets an injective map from a set to itself need not be surjective, as $n \mapsto 2n$ on $\mathbb{Z}$ shows.

9.1.26 Note If commutativity is dropped and every nonzero element is required to be a unit, giving a division ring, the conclusion survives: every finite division ring is commutative, hence a field. This is Wedderburn's little theorem, proved in theorem 19.7.20 from the class equation and cyclotomic polynomials.

Though integral domains are nice, they loose a every important property: If R is an integral domain, then $R \times R$ is *not* an ingeral domain

Example 9.1.27: product of integrals domains is not an integral domain
Let R be an arbitrary integral domain. Then take $R \times R$, with addition and multiplication done point-wise. Then

$$(1,0) \cdot (0,1) = (0,0)$$

meaning there are zero-divisors, and so $R \times R$ is not a integral domain A particular consequence of this is that the direct product of fields is not a field (since fields are integral domains) More generally, integral domains do not satisfy the universal property of products.

A summary of all these properties is in section 9.1.2.

Exercise 9.1.1

1. An element $e \in R$ is called *idempotent* if $e^2 = e$. Does there exist a ring R that has exactly 3 idempotent elements? Find one or show it's not possible.
2. We will prove that every finite integral domain is a ring using the pigeonhole principle
   a) Show... click here for this proof
3. Let $\mathbb{C}$ be the set of expressions $a+bi$ with $a, b \in \mathbb{R}$, with $(a+bi)+(c+di) = (a+c)+(b+d)i$ and $(a+bi)(c+di) = (ac-bd)+(ad+bc)i$, the product obtained by expanding and using $i^2 = -1$. Prove that $\mathbb{C}$ is a ring. (Example 19.2.7 realizes $\mathbb{C}$ as the quotient ring $\mathbb{R}[x]/(x^2+1)$.)
4. Let' say $s \neq 1$ and $s^2 = s$. This propety is called idempotence. Show that the only idempotent element in an integral domain is 0 and 1
5. Let R be a ring with $1 \neq 0$. Is $\varphi : R \to R$, $\varphi(r) = 0$ a ring-homomorphism? If so, prove it, and if not, would it be a rng-homomorphism (i.e. would the image be a rng)?
6. Show that the only idempotent elemnt in a field' is 0 or 1 (there exists a proof using properties of a field but not properties of integral domain)
7. A field is said to be characteristic n if there exists a number n st $\underbrace{1+1+1\cdots+1}_{n \text{ times}} = 0$. If no such number exists, we say that the field has characteristic 0. Give an example (or examples) of fields with characteristic 0, 2, and 5.
8. Let $u \in R$ be a unit and $R \to S$ a ring homomorphism. Then $\varphi(u)$ is a unit. Is the same true

for zero-divisors? What about non-zero-divisors?

9. Show that if $\mathbb{F}$ is a field of characteristic 0, then $\mathbb{Q} \subseteq \mathbb{F}$.

10. (For those who know some Analysis and want examples of *rngs*) In the process of defining the Fourier series, it is necessary to define the convolution product between two continuous functions (on compact support, or more generally L^2)

11. (ibid last comment) Let X be a locally compact Hausdorff space (every $x \in X$ has a neighbourhood contained in a compact set) that is not compact. Let $C_0(X)$ be the set of continuous complex functions $f : X \to \mathbb{C}$ that vanish at infinity (for every $\epsilon > 0$, there exists a compact $K \subseteq X$ such that $|f(x)| < \epsilon$ for all $x \in X - K$). Then $(C_0(X), +, \cdot)$ with function addition and multiplicatoin is a rng, but not a ring (namely, the function $1(x)$ does not vanish at infinity). This rng is used quite often in analysis: it comes up in Fourier analysis, in defining Radon Measures, and in the study of C^*-algebras to name a few examples (see [51] and *C*-Algebras and K-Theory* [17]).

    Loosely speaking, rngs correspond to locally compact spaces, while rings correspond to compact spaces. For analysts, working over compact spaces is much too restrictive ($\mathbb{R}^n$ is not compact), while locally compact spaces are much more natural to work with ($\mathbb{R}^n$ is locally compact). Furthermore, recall we have mentioned we can turn a rng into a ring by doing $\mathbb{Z} \oplus R$ to some rng R. If we were interested in keeping nice analytical properties, for a $\mathbb{C}$-algebra R we would instead take $\mathbb{C} \oplus R$ (for instance $\mathbb{C} \oplus C_0(X)$). This corresponds to the one-point compactification of X: $C(X \cup \{\infty\}) \cong \mathbb{C} \oplus C_0(X)$.

12. Show that $(F, +, \cdot)$ be a ring. Show that $(F, +, \cdot)$ is a field if and only if $(F, +)$ is an abelian group and the set $F^\times$ is equal to $F - \{0\}$.

13. Let R be a ring and R^{op} denote the ring where the underlying set and addition operation is the same, and the multiplication is defined as $x * y = yx$ where yx happens in R. Show that $\text{id} : R \to R^{\text{op}}$ is not necessarily a ring isomorphism (it is sometimes called an *anti-isomorphism*). When is it a ring isomorphism? Show that for a commutative ring k, transposition $A \mapsto A^T$ is a ring isomorphism $M_n(k) \to M_n(k)^{\text{op}}$.

14. show that if $x^n = 0$, then $(x - 1)$ is an invertible element. An element where $x^n = 0$ is called a *nilpotent element*.

15. recall that $(x + y)^n = \sum_{k=1}^{n} \binom{n}{k} x^n y^{n-k}$. Show that the binomial formula holds if and only if $xy = yx$.

16. I the set of all left (resp. right) invertible elements a group? How that $Z(R)$ is a subring of R.

17. let G be a cyclic group of order n. For each $k \in \mathbb{Z}$, define $f : G \to G$, $f_k(g) = kg$. The n the map $k \mapsto f_k$ defines a ring isomorphism $\mathbb{Z}/n\mathbb{Z} \cong_{\mathbf{Ring}} \text{End}_{\mathbf{Ring}}(G)$ and a group isomorphism $(\mathbb{Z}/n\mathbb{Z})^* \cong_{\mathbf{Grp}} \text{Aut}_{\mathbf{Grp}}(G)$

9.1.1 Category of Ring

We now approach rings a 2nd time, but this time, we will take a more birds-eye view of the category or rings. We will see if this category has some properties different than the category of groups, and whether there is a general way of extending groups to form rings.

Proposition 9.1.28: Category of Ring

The collection of Rings along with ring homomorphisms form a category. This category will be denoted **Ring**.

***Proof*:**
If $\varphi\colon R \to S$ and $\psi\colon S \to T$ are ring homomorphisms, then $\psi \circ \varphi$ preserves sums and products because each map does, and $(\psi \circ \varphi)(1_R) = \psi(1_S) = 1_T$. Composition of functions is associative, and the identity map of a ring is a ring homomorphism that is an identity for composition, completing the proof.

Since **Ring** is a category, it will be verified what are the initial/final objects, and whether there are product, sub-, and quotient objects, and whether quotient objects can be classified through kernels. We can further ask about the relation between **Group** and **Ring**, and ask whether there is an analogous concept of ring-actions. In this section we will drop the subscript and write $\mathrm{Hom}(R, S)$ or $\mathrm{End}(R)$ instead of $\mathrm{Hom}_{\mathbf{Ring}}(R, S)$ or $\mathrm{End}_{\mathbf{Ring}}(R)$

The fact that sub-objects and product objects exist in rings (that is, subrings and product rings) has already been explored in definition 9.1.6 and example 9.1.4(5), though not in categorical terms. We will mention some more about product of rings and the consequences of integral domains not having products as an interesting example of category with no products. Quotient objects will be revisited in more detail in section 9.3.

Rings and $\mathbb{Z}$

The first thing to check is whether **Ring** has initial and final objects. In definition 1.4.6, we introduced the concept of initial and final group. We found there to not really be an intersting initial and final group: only the identity group. The same is true for the final object of rings. However, the zero ring cannot be the initial: if R is the zero ring and $\varphi\colon R \to S$ is a homomorphism, then $1_S = \varphi(1_R) = \varphi(0_R) = 0_S$, so S is the zero ring. There is still an initial object in the category or rings: we have our first example of a non-trivial initial object!

Proposition 9.1.29: $\mathbb{Z}$ is an Initial Ring

The ring $\mathbb{Z}$ is an intial ring

***Proof*:**
Let R be any ring (with identity) and let $\varphi : \mathbb{Z} \to R$ such that

$$\varphi(z) = 1 + 1 + 1 \ (z \text{ times}) \ = z \cdot 1$$

this is a ring homomorphism. For

$$\varphi(a{+}b) = (a{+}b){\cdot}1 = a{\cdot}1{+}b{\cdot}1 = \varphi(a){+}\varphi(b) \qquad \varphi(ab) = (ab){\cdot}1 = a(b{\cdot}1) = (a{\cdot}1)(b{\cdot}1) = \varphi(a)\varphi(b)$$

Furthermore, if $\varphi' : \mathbb{Z} \to R$ was another ring homomorphism, then by proposition 9.1.9

$$\varphi'(1) = 1\,, \varphi'(2) = 1 + 1\,, \cdots$$

that is, by the fact that the identity *must* be distributed in this fashion, we are forced that

$$\varphi = \varphi'$$

making it unique

If rings are not required to have a multiplicative identity, then $\mathbb{Z}$ is no longer initial: the identity map $\mathbb{Z} \to \mathbb{Z}$ and the zero map $\mathbb{Z} \to \mathbb{Z}$ both preserve sums and products. The initial object of that category is the zero ring.

So how can we use this result? The way I think about it is something "integer-like" in every ring [with identity]. It might not be commutative, it might not be injective (the codomain might even be finite), or it might be uncountably big (like $\mathbb{R}$ or $M_n(\mathbb{C})$) but there is still something integer like. For this reason, asking questions like "what properties of the integers do rings have" is a very sensible question! In fact, that will be essentially what we do in chapter 10!

For example, if we take $x \in \mathbb{Z}$, then $x = p_1 p_2 \cdots p_n$, that is x has a *unique prime factorization*. In the next chapter, we will study rings which have this similar property (they will be called *unique factorization domains*). Similarly, to find the $gcd(a, b)$, we can use the euclidean algorithm which algorithmically shows how much the set of divisors of the two numbers intersect. This is very handy since we can in very few steps find the common divisors of two numbers of extremely large numbers. Rings in which the notion of the euclidean algorithm is well-dfined will be called *euclidean domains*. Finally, a little more difficult but important concept, any number can be decomposed into *unique* prime numbers in $\mathbb{Z}$. We will find the equivalent of "numbers" in rings to be "ideals" (the original name was "ideal numbers" of rings). If every ideal can be generated by a single element $x \in R$, the ideal is called a *principal ideal*. Thus, a ring which is has "numbers" (ideals) which are generated by one element (just like a number just needs itself to describe, well, itself) will be called a *principal ideal domain*.

Thus, in the folloing chapters, some basic theory will extensively be used. Take a moment to review section 0.2 for a refresher on some basic tools of number theory.

Rings and $\mathrm{End}(G)$

You might ask how should we choose which of the axioms are "nice" axioms to add to our structure. One way of doing so is by thinking about the multiplication action being permutations of the elements, not unlike ho the group operation can be thought of as the permutation of elements (i.e. any group $(G, +)$ is a subgroup of $\mathrm{Sym}(G)$) [6]

We saw in definition 1.4.9 that if G is an abelian group that $\mathrm{End}(G)$ is an agelian group under pointwise addition. Notice that there is already a 2nd operation, since function can compose:

$$(\mathrm{End}(G), +, \circ)$$

Then, it can be checked that composition here will make this into a ring (as shown in example 9.1.4)

Conversely, every ring $(R, +, \cdot)$ embeds in $\mathrm{End}((R, +))$: the map $r \mapsto (x \mapsto rx)$ is an injective ring homomorphism, injective because r is recovered as the image of 1. This is the ring analogue of Cayley's theorem (theorem 4.5.3). Cayley's theorem is the Yoneda lemma (theorem 62.2.1) for the one-object category of a group G. Applied to the monoid $(R, \cdot)$, the Yoneda lemma gives the multiplicative half of this embedding, and distributivity places its image in $\mathrm{End}((R, +))$.

[6] Research **Ab**-enriched categories for information about this process


:exercse

Let $\mathrm{Aut}_{\mathbf{Ab}}(R)$ be the set of group-automorphisms on R. Show that $U(R) \cong_{\mathbf{Ab}} \mathrm{Aut}_{\mathbf{Ab}}(R)$

let R be a commutative ring. Show that $\lambda : R \to \mathrm{End}_{\mathbf{Ab}}(R)$ by $r \mapsto (y \mapsto ry)$ is indeed a ring homomorphism. If R is not commutative, show that it's almost abelian.

Products of Rings

Rings have products: Given any to rings A and B, there exists a ring $A \times B$ along ring homomorphisms $\pi_A : A \times B \to A$ and $\pi_B : A \times B \to B$ such that for any C here $f_A : C \to A$ and $f_B : C \to B$, there exists a unique $f! : C \to A \times B$ such that the folloing diagram commutes:




In this way, products in **Ring** are like products in **Grp**. A similar situation occurs for coproducts.

However, as mentioned earlier, if we retirct to *integral domains* and take the category whose objects are integral domains (this is indeed still a category as can be verified), they are no longer products, as demonstrated in example 9.1.27!

Since since all fields are integral domains, this means that products are not defined for fields! As a consequence of this, we cannot repeat the same trick as in chapter 5 in creating larger groups using products. Thus, extensions of fields (similar to how they were defined for groups in section 3.6) will have to be used to study the creation of larger fields. To study field extensions, we must first study ring homomorphisms more extensively. The particular way in which ring homomorphissm will be used in constructing larger fields requires more build-up, and so the study of fields is relegated to Part IV.

9.1.2 Summary

Keeping track of these properties and their relation to everything can be a bit to take in. It might help to have a visual too:



The *rng* can have more arrows extending from it to commutative ring, domain, and integral domain, but the diagram would be cumbersome, so I opted to make it a dashed line from *rng* to *ring*, since, it is not needed to "upgrade" those rings until we get to division ring and fields. I added a (+1) where we really need the multiplicative identity to define the next concept.

Notice that if a commutative ring only has units, it is then a commutative division ring, and hence a field. The line as not drawn so as to not clutter the diagram.

look at comment:

The following categorical results are also noted:

1. $\mathbb{Z}$ is the initial object of rings
2. All rings are subrings of $\mathrm{End}((R, +))$
3. Products exist for rings, but not for integral domains (and so not for fields).

Exercise 9.1.2

1. Since $\mathbb{Z}$ is initial, for any ring R and natural homomorphism $\mathbb{Z} \to \mathbb{R}$, $\mathrm{im}(\mathbb{Z})$ exists is a subring. Show that $\mathrm{im}(\mathbb{Z})$ is the *smallest* subring of any ring. Show further that $\mathrm{im}(\mathbb{Z})$ is either $\mathbb{Z}_n$ for any $n > 0$ or $\mathbb{Z}$. If $|\mathrm{im}(\mathbb{Z})| < \infty$, then we say the ring R has *characteristic* n, and if $\mathrm{im}(\mathbb{Z}) \cong \mathbb{Z}$ then R has *characteristic 0*.
2. Let R be a ring and define R^{op} to be the ring with the same underlying set and addition operation, and multiplication defined by $x * y = yx$, where yx happens in R. Show that R^{op} is a ring, and that $(_)^{\mathrm{op}} : \mathbf{Ring} \to \mathbf{Ring}$ is a functor (where do ring homomorphisms map to?). Is it covariant or contravariant?
3. Let $a, b \in R$ such that $ab = ba$. Show that ab is invertible if and only if a and b are invertible. Generlize your result to show that if $ab \neq ba$, then if ab invertible, then a is left-invertible, and b is right-invertible.
4. Show that $\mathrm{End}_{\mathbf{Ab}}(\mathbb{Z}) \cong_{\mathbf{Ring}} \mathbb{Z}$.

9.2 Examples of Rings

The following are rings that will show up time and time again, and being aquainted with them is very useful. Many of these rings will be the starting point to a new field of study in mathematics. For example, Polynomial rings are pivotal in commutative algebra (*Commutative Algebra* [20]), and when the polynomial ring takes on coefficients from a field (i.e. a polynomial ring over a field), then they form the foundation for field theory (see Part IV). Matrix rings are a common the "representation objects", the same way $\text{Sym}(X)$ was an object that can be used to "represent" groups (see chapter 51). Group rings can be thought of as the dual of the group of unity of rings, and also appear frequently in representation theory (see chapter 53) and group cohomology (see section 58.1).

There is also an optional section on formal power series covering the elementary operations that can be performed on formal power series. These results are important for a class in complex analysis, however the formal power series ring will come up as examples for certain concepts introduced later in the book as well. These examples of formal power series will not be critical in understanding any material, and so they can be comfortably skipped.

9.2.1 Polynomial Rings

Polynomial Rings are one of the first examples we will give of a [commutative] extension of a ring. Let R be a commutative ring [7]. What we will be doing is extending R by an arbitrary unkown element x. In a sense, what we are doing is saying x is now an element of R, an then we figure out how to define this new structure (which we label $R[x]$) so that it's also a ring. Since $x \in R[x]$, then $x \cdot x \in R[x]$. Since we know nothing of x, we can only say that $x \cdot x = x^2$ is another element. We can continue this process inductively getting us every x^k for all $k \in \mathbb{N}$. For any other element r: $r \cdot x = rx$ where rx is a new element of $R[x]$. A similar reasoning to creating new elements applies to adding: $r + x$ is a new element. However, it need not be the case that an element has an inverse, so we do not define an x^{-1} such that $xx^{-1} = 1$[8]. All of these properties together give us the following definition:

[7] In the exercises, there are questions concerning the study of non-commutative R forming a polynomial ring and why it is often preferred for R to be commutative

[8] polynomial rings where the indeterminate x has an inverse are called the *ring of fractions of R[x].* see section 9.5

Definition 9.2.1: Polynomial Ring

Let R be a ring and x be an indeterminante. Then the sum

$$a_n x^n + a_{n-1}x^{n-1} + \cdots + a_1 x + a_0$$

with $n \geq 0$ and each $a_i \in R$ is called a *polynomial* in x with coefficients a_i in R. The set of all such polynomials is called the ring of *polynomial in the variable x with coefficients in R* (or *polynomial ring* if context permits) and will be denoted $R[x]$. Addition is defined as

$$(a_n x^n + \cdots + a_1 x + a_0) + (b_n x^n + \cdots + b_1 x + b_0) = (a_n + b_n)x^n + \cdots (a_1 + b_1)x + (a_0 + b_0)$$

where a_n or b_n may be zero in order for addition of polynomials of different degrees to be defined. Multiplication is perfomed by defining $(a_i x^i)(b_j x^j) = a_i b_i x^{i+j}$ and then extending to all polynomials by the distributive law. This is called the *convolution product*
The following are pertinent definitions with regards to polynomials.

1. If $a_n \neq 0$, then the polynomial is said to be of *degree* n, and $a_n x^n$ is called the *leading coefficient* (where the leading coefficeint of the zero polynomial is taken to be 0).
2. The polynomial is *monic* if $a_n = 1$.

For reference, here is the general formula for polynomial multiplication (i.e. the convolution product)

$$\left(\sum_{i=0}^{\deg(p)} p_i x^i\right) \cdot \left(\sum_{i=0}^{\deg(q)} q_j x^j\right) = \sum_{k=0}^{\deg(p)+\deg(q)} \sum_{l=0}^{k} p_l q_{k-l} x^k$$

9.2.2 Remark If you have done Fourier Analysis (or intend to in the future), then the convolution of two continuous (more generally measurable) functions follow's the exact same properties as polynomial multiplication. In fact, polynomial multiplication would be a discrete convolution.

Note that R is always a subring of $R[x]$, which we can see through the natural inclusion map[9] $R \hookrightarrow R[x]$ of $r \mapsto r$.

Usually, when we manipulate polynomials we treat them as functions. It must be stressed that we are *not* treating the elements of $R[x]$ as functions. The study of the elements of $R[x]$ as functions will be done in *Classical Algebraic Geometry* [42], which will establish the largest connection between algebra and geometry in the 20th century.

If $R = F$ is a field, then every coefficient is a unit, meaning we can divide each coefficient a polynomial to make it *monic*, that is,

$$a_n x^n + a_{n-1}x^{n-1} + \cdots + a_1 x + a_0 \overset{1/a_n}{\mapsto} x^n + a'_{n-1}x^{n-1} + \cdots + a'_1 x + a'_0$$

where $a'_i = \frac{a_i}{a_n}$. We shall see that often-times many results *up to multiplication by unit* (meaning if the result holds on p, it will hold on cp, where c is a unit). For this reason, it is worth keeping the term *monic* in mind.

[9] Natural in the sense that defining it requires nothing besides R and $R[x]$. The technical meaning of the word is the one of definition 18.2.1.

We can extend the definition of a polynomial ring to a polynomial ring over several variables by simply making $R[x]$ a polynomial ring over y, that is

$$R[x,y] = (R[x])[y] = R([y])[x] = R[y,x]$$

Continuing inductively, we can define a ring over a finite number of variable this way:

$$R[x_1, x_2, ..., x_{n+1}] = (R[x_1, x_2, ..., x_n])[x_{n+1}]$$

This process can be extended "indefinitely"[10] to define $R[x_1, x_2, ..., x_n, ...]$, in which every polynomial (i.e. elements of $R[x_1, x_2, ...,]$) has finitely many terms, and each term can have multiples of any of variables of $R[x_1, x_2, ..., x_n, ...]$, for example:

$$x_{30}^2 x_7^{23523} x_2 - r x_{100} x^{39} \in R[x_1, x_2, ...]$$

Multiplication in $R[x_1, x_2, ...]$ is the same as the multiplication in polynomial rings over finitely many variables, where we know the value for any term be expanding out the multiplication far enough to group like-terms. If $x_1^{d_1} x_2^{d_2} \cdots x_k^{d_k}$ is a term, then the *total degree* of the term is

$$d = d_1 + d_2 + \cdots + d_k$$

and the tuple $(d_1, d_2, ..., d_k)$ is the multi-degree of the term.

Properties of Polynomial Rings

To motivate the next theorem, let's say we have two polynomials of degree 1, $ax + b, cx + d \in R[x]$. We can ask what is the degree of $(ax + b)(cx + d) = acx^2 = (ad + bc)x + bd$. We might expect the degree to be 2. However, it is possible that a and c are zero-divisors: take $4x + 1, 4x + 1 \in (\mathbb{Z}/8\mathbb{Z})[x]$. In fact, in the example just stated, $4x + 1$ is in fact a unit in $(\mathbb{Z}/8\mathbb{Z})[x]$! If R is an integral domain, then some of its structure will be simpler:

Proposition 9.2.3: Degree Of Polynomials

Let R be an integral domain and let $p(x), q(x)$ be nonzero elements of $R[x]$. Then

1. degree $p(x)q(x)$ = degree $p(x)$ + degree $q(x)$
2. the units of $R[x]$ are the units of R
3. $R[x]$ is an integral domain

***Proof*:**
Write $p(x) = \sum_{i=0}^{n} a_i x^i$ and $q(x) = \sum_{j=0}^{m} b_j x^j$ with $a_n \neq 0$ and $b_m \neq 0$, so that $\deg p(x) = n$ and $\deg q(x) = m$, and put $a_i = 0$ for $i > n$ and $b_j = 0$ for $j > m$. By the formula for the

[10] For those uncomfortable with how the fact that the above process of defining a polynomial ring will always only produce polynomial rings with finitely many variables, the ring $R[x_1, x_2, ...]$ is the union of the chain $R[x_1] \subseteq R[x_1, x_2] \subseteq \cdots$, a *colimit* (definition 63.3.1)

product of polynomials, the coefficient of x^k in $p(x)q(x)$ is

$$c_k = \sum_{l=0}^{k} a_l b_{k-l}$$

1. Let $k \geq n+m$. A term $a_l b_{k-l}$ of c_k with $l > n$ vanishes because $a_l = 0$. A term with $l \leq n$ has $k - l \geq k - n \geq m$, with equality only when $k = n+m$ and $l = n$, so it vanishes because $b_{k-l} = 0$, except the term $a_n b_m$ when $k = n+m$. Hence $c_k = 0$ for $k > n+m$ and $c_{n+m} = a_n b_m$, which is nonzero because R has no zero divisors. Therefore $\deg p(x)q(x) = n+m$.

2. A unit u of R is a unit of $R[x]$, with the same inverse, since R is a subring of $R[x]$. Conversely, let $u \in R[x]$ and $v \in R[x]$ satisfy $uv = 1$. Neither is 0, since $0 \cdot v = 0 \neq 1$, so (1) gives $\deg u + \deg v = \deg 1 = 0$. Hence $\deg u = \deg v = 0$, so u and v are constants, that is, elements of R with $uv = 1$, and u is a unit of R.

3. The ring $R[x]$ is commutative: reindexing by $l \mapsto k - l$ and using that R is commutative turns c_k into $\sum_{l=0}^{k} b_l a_{k-l}$, the coefficient of x^k in $q(x)p(x)$. Its identity 1 is nonzero because $1 \neq 0$ in R. If $p(x)$ and $q(x)$ are nonzero, then by (1) the coefficient $c_{n+m} = a_n b_m$ of $p(x)q(x)$ is nonzero, so $p(x)q(x) \neq 0$. So $R[x]$ has no zero divisors and is an integral domain (definition 9.1.21), as we sought to show.

A ring homomorphism out of $R[x]$ is determined by its restriction to R and its value at x, and every such pair of data occurs:

Theorem 9.2.4: Universal Property of Polynomial Rings

Let R and S be commutative rings and let

$$\varphi : R \to S$$

be any ring homomorphism and let $s \in S$ be any element of S. Then there is a unique ring homomorphism

$$\psi : R[x] \to S$$

such that $\psi(x) = s$ and which makes the following diagram commute, where ι is the inclusion

$$\begin{array}{ccc} R & \xrightarrow{\varphi} & S \\ \downarrow{\scriptstyle \iota} & \nearrow{\scriptstyle \psi} & \\ R[x] & & \end{array}$$

A nuance that must be mentioned is that polynomial rings may be over different rings. We thus may thus ask how a ring S is generated with respect to a ring R. As demonstrated earlier, $\mathbb{Z}$ is the initial object of **Ring**, and so in the arbitrary case $f : X \to S$ for some set X, we shall have a polynomial ring on the elements X over $\mathbb{Z}$. For those who are categorically inclined, try figuring out what is the category involved behind the scenes (this is similar to the construction for free groups in section 2.3.3)

***Proof*:**
Every $p \in R[x]$ is $p = \sum_{i\geq 0} a_i x^i$ for unique coefficients $a_i \in R$, all but finitely many zero.

Existence. Define

$$\psi\left(\sum_{i\geq 0} a_i x^i\right) = \sum_{i\geq 0} \varphi(a_i) s^i$$

Then $\psi(a) = \varphi(a)$ for $a \in R$, so $\psi \circ \iota = \varphi$, and $\psi(x) = s$ and $\psi(1) = \varphi(1) = 1$. Coefficients of a sum are the sums of the coefficients and φ is additive, so ψ is additive. Let $q = \sum_{j\geq 0} b_j x^j$. The coefficient of x^k in pq is $\sum_{l=0}^{k} a_l b_{k-l}$, so

$$\psi(pq) = \sum_{k\geq 0} \sum_{l=0}^{k} \varphi(a_l)\varphi(b_{k-l}) s^k$$

On the other hand, generalized distributivity (proposition 9.1.9(5)) and the commutativity of S give

$$\psi(p)\psi(q) = \sum_{i,j\geq 0} \varphi(a_i)\varphi(b_j) s^{i+j}$$

and grouping the terms with $i + j = k$ turns this into the expression for $\psi(pq)$. So ψ is a ring homomorphism.

Uniqueness. If $\psi' \colon R[x] \to S$ is a ring homomorphism with $\psi' \circ \iota = \varphi$ and $\psi'(x) = s$, then, as ψ' preserves sums and products,

$$\psi'\left(\sum_{i\geq 0} a_i x^i\right) = \sum_{i\geq 0} \psi'(a_i)\psi'(x)^i = \sum_{i\geq 0} \varphi(a_i) s^i$$

so $\psi' = \psi$, completing the proof.

A particular case of this is when $\varphi : R \to R$ is an identity map. In this case, we may link the notion of a [formal] polynomial to a polynomial function:

Definition 9.2.5: Evalutation Map

Let R be a ring and let $\alpha \in R$. The natural ring homomorphism

$$\varphi : R[x] \to R$$

which acts as the identity on R and which sends x to α is called the *evaluation at* α and is often denoted ev_α.
We say that α is a *zero* (or root) of $f(x)$ if $f(x)$ is in the kernel of ev_α.

The evaluation map can come in quite handy in many proofs that will be seen later (for instance in example 9.4.28, once prime ideals are available).

When working with functions, they are determined by the value at each point of evaluation. It must

be stressed that in general, a polynomial is *not* determined by it's evaluation

Example 9.2.6: Polynomial Not Determined By Evaluation
[Polynomial Not Determined By EvaluationPolynomial Not Determined By Evaluation] Take $x^2 - x \in (\mathbb{Z}/2\mathbb{Z})[x]$. Does the evaluation of this polynomial uniquely determine $x^2 - x$?

9.2.2⋆ Formal Power Series

⋆ *Optional. This subsection is an aside; nothing later in the book depends on it.*

Any polynomial is a finite linear combination of the terms x^n. If we allow for infinitely many terms, we call such an object a *formal power series*, and write it like so:

$$f(x) = \sum_{i=0}^{\infty} a_i x^i \qquad a_i \in R$$

The reader may ask what does it mean to take an infinite linear combination, as we have defined the $+$ notation to only take in two inputs, and if we recurse over the inputs we may have a finite linear combination. These are valid concerns which will be addressed in *Commutative Algebra* [20] (completion). For now, we may consider $f(x)$ in the above equation as being an infinite tuple[11]

$$(a_0, a_1, a_2, \dots) \in \prod_{i=0}^{\infty} R$$

however we should take this identification as simply insuring that $f(x)$ is well-defined. We shall not write $f(x)$ in the notation of tuples and from now on shall assume we can take infinite sums. The collection of all formal power series are certainly closed under termwise addition. We must make sure multiplication is still well-defined. For multipilcation to be well-defined, each coefficient must be well-defined. Fortunately, this is the case. If $p(x)$ and $q(x)$ where

$$\begin{aligned} p(x)q(x) &= \left(\sum_{i=0}^{\infty} a_i x^i\right)\left(\sum_{j=0}^{\infty} b_j x^j\right) \\ &= a_0b_0 + (a_0b_1 + a_1b_0)x + (a_0b_2 + a_1b_1 + a_2b_0)x^2 + \cdots \\ &= \sum_{n=0}^{\infty}\left(\sum_{i=0}^{n} a_i b_{n-i}\right)x^n \end{aligned}$$

Each coefficient $\sum_{i=0}^{n} a_i b_{n-i}$ is a finite sum, so the product is well defined, and the sequence of these coefficients is called the *convolution* of the sequences (a_i) and (b_j). The ring axioms hold. Addition is termwise, so $(R[[x]], +)$ is an abelian group. The coefficient of x^n in both $(pq)r$ and $p(qr)$, where $r(x) = \sum_k c_k x^k$, is the finite sum of the products $a_i b_j c_k$ over all $i + j + k = n$, so multiplication is associative. The coefficients of $p(q + r)$ are $\sum_{i=0}^{n} a_i(b_{n-i} + c_{n-i})$, the sums of those of pq and pr, and similarly on the other side, so multiplication distributes over addition. The constant series 1 is an identity. Thus $R[[x]]$ is a ring:

[11] this may push the concern in asking how $\prod_{i=0}^{\infty}$ is defined. For those with this concern, they may skip to chapter 25 or they may take for granted that we may always make a countable number of choices and remember the order

Definition 9.2.7: Formal Power Series

The collection of all infinite R-linear combinations of $\{1, x, x^2, ...\}$ forms a ring known as the ring of *formal power series* over R, and is denoted $R[[x]]$

The term "formal" comes from how we often associate to an object $f \in R[[x]]$ the evaluation function. If we had a function with a domain and codomain for which $r \mapsto \sum_{i=0}^{\infty} a_i r^i$, we would call this function a *power series*. However, for such a function to be defined, we require the ability to unambiguously define summing infinitely many elements of a ring. Such considerations require the introduction of a topology on our ring, something we shall not cover. We shall remark that it is very commmon in compex analysis to work with power series and choose $R \in \{\mathbb{R}, \mathbb{C}\}$ with the usual euclidean topology, leading to many very important results about complex-differentiable functions. There is one value we may unambiguously define without the need for any convergence considerations:

$$f(0) := a_0$$

Proposition 9.2.8: Formal Power Series Integral Domain

Let R be an integral domain. Then the ring $R[[x]]$ of formal power series over R is an integral domain

***Proof*:**
Write $f = \sum_{i\geq 0} a_i x^i$ and $g = \sum_{j\geq 0} b_j x^j$ for elements of $R[[x]]$. By the product formula above, the coefficient of x^n in fg is $\sum_{i=0}^{n} a_i b_{n-i}$. Reindexing by $i \mapsto n - i$ and using that R is commutative turns this into $\sum_{i=0}^{n} b_i a_{n-i}$, the coefficient of x^n in gf, so $R[[x]]$ is commutative. Its identity is the constant series 1, which is nonzero because $1 \neq 0$ in R.

Now let f and g be nonzero, let m be the least index with $a_m \neq 0$ and let k be the least index with $b_k \neq 0$. The coefficient of x^{m+k} in fg is

$$\sum_{i=0}^{m+k} a_i b_{m+k-i} = a_m b_k$$

because $a_i = 0$ for $i < m$, and for $i > m$ the index $m + k - i$ is less than k, so that $b_{m+k-i} = 0$. Since R is an integral domain, $a_m b_k \neq 0$, hence $fg \neq 0$. So $R[[x]]$ is a commutative ring with $1 \neq 0$ and no zero divisors, that is, an integral domain (definition 9.1.21), as we sought to show.

Given that $R[[x]]$ is the extension of $R[x]$, it may see intriguing to think that these two rings share very similar properties. However, the "infinitude" of $R[[x]]$ will make the ring act rather differently. The following may be the most striking change when extending to infinite polynomials:

Lemma 9.2.9: Existence of More Units

Let $R[[x]]$ be the formal power series over a ring R. Then $(1 - x)$ has an inverse in $R[[x]]$

***Proof*:**
Notice that

$$(1-x)(1+x+x^2+\cdots+x^n+\cdots)=1$$

and hence by definition that means that $1-x$ has an inverse, namely $\sum_{n=0}^{\infty} x^n$.

By convention, we denote inverses using quotient notation, and hence we would write:

$$\frac{1}{1-x} := \sum_{n=0}^{\infty} x^n$$

For those who have taken calculus, they may be familiar with an "analysis" version of this proof relying on absolute convergence. The above shows that this result is purely algebraic. In fact, we can fully classify all units in a formal power series

Proposition 9.2.10: Units In Formal Power Series

Let $f \in k[[x]]$. Then f is a unit (i.e. f has an inverse) if and only if $a_0 \neq 0$

***Proof*:**
The condition is certainly necessary since if

$$g(x)=\sum_n b_n x^n \qquad f(x)g(x)=1$$

then we must have $a_0 b_0 = 1$, so $a_0 \neq 0$. If conversely we have $a_0 \neq 0$, we shall show that the formal power series $(a_0)^{-1}f(x) = f_1(x)$ has an inverse $g_1(x)$, and hence $(a_0)^{-1}g_1(x)$ is the inverse of $f(x)$. Decompose $f_1(x)$ into:

$$f_1(x) = 1 - u(x)$$

then substitute $u(x)$ for y in the proof of lemma 9.2.9 to get that $1-u(x)$ has an inverse. But then we may conclude that $f(x)$ has an inverse, thus completing the proof.

Another question we may ask is the following: Given two polynomials $f(x), g(x)$, we may take $f(g(x))$, (replace x with $g(x)$). Can the same be done for power series? The following shows when this is possible:

Definition 9.2.11: Formal Derivative

Let $f \in k[[x]]$ be a formal power series. Then if $f(x) = \sum_{k=0}^{\infty} a_k x^k$, the formal derivative of f is the value

$$\frac{d}{dx}(f) = \sum_{k=0}^{\infty} k a_k x^{k-1}$$

we usually denote the derivative of $f(x)$ as $f'(x)$, and for higher derivatives we write $f^{(n)}(x)$ to represent taking recursively the derivative of f n times.

We may use the formal derivative recursively to find the coefficients of f. Namely, $f(0) = a_0$, $f'(0) = a_1$, ..., $f^{(n)}(0) = a_n$, and so forth.

Let f, g be power series. We may wonder when $g(f(z))$ is well-defined:

Proposition 9.2.12: Composing Power Series

Let f, g be formal power series. Then $g(f(z))$ is well-defined if $b_0 = 0$.

***Proof*:**
When composing power series, we get:

$$a_0 + a_1(b_1 z + b_2 z^2 + \cdots) + a_2(b_1 z = b_2 z^2 + \cdots)^2 + \cdots$$

where each coefficient is an infinite sum, and so we must ask for their convergence conditions. One thing we can do to guarantee this is by setting $b_0 = 0$, which will guarantee that all the coefficients are finite sums and hence well-defined.

We often denote the composition as $g \circ f$.

Proposition 9.2.13: Associativity Of Composition

Let $f, g, h \in k[[x]]$ be power series with $f(0) = 0$ and $g(0) = 0$. Then

$$(h \circ g) \circ f = h \circ (g \circ f)$$

***Proof*:**
The composites $h \circ g$ and $g \circ f$ are defined by proposition 9.2.12, since $g(0) = 0$ and $f(0) = 0$. Writing $g = \sum_{n \geq 0} b_n x^n$, the constant term of $g \circ f = \sum_{n \geq 0} b_n f^n$ is $b_0 = g(0) = 0$, because f has no constant term, so $h \circ (g \circ f)$ is defined as well, and $(h \circ g) \circ f$ is defined because $f(0) = 0$.

Fix $v \in k[[x]]$ with $v(0) = 0$ and consider substitution of v. For any $u_1, u_2 \in k[[x]]$,

$$(u_1 + u_2) \circ v = u_1 \circ v + u_2 \circ v \qquad (u_1 u_2) \circ v = (u_1 \circ v)(u_2 \circ v)$$

because each coefficient of each side is the same finite polynomial expression in the coefficients of u_1, u_2 and v. Taking $u_1 = u_2 = \cdots = u$ and inducting on n, the second identity gives

$$u^n \circ v = (u \circ v)^n$$

for every $n \geq 0$.

Now write $h = \sum_{n \geq 0} c_n x^n$, so that $h \circ g = \sum_{n \geq 0} c_n g^n$ by definition of composition. Substituting f,

$$(h \circ g) \circ f = \sum_{n \geq 0} c_n \, (g^n \circ f) = \sum_{n \geq 0} c_n (g \circ f)^n = h \circ (g \circ f)$$

where the middle equality is the displayed identity with $u = g$ and $v = f$, and the last is again the definition of composition, applied to h and $g \circ f$.

The first equality above interchanges substitution with an infinite sum. Since $g(0) = 0$ the series g^n has no terms of degree below n, and likewise for $(g \circ f)^n$ since $(g \circ f)(0) = 0$. So for each fixed p only the indices $n \leq p$ contribute to the coefficient of x^p on either side, and the interchange is an identity between two finite sums.

Define $I(x) = x$. Notice that for any $f \in k[[x]]$, $I \circ f = f \circ I = f$.

Proposition 9.2.14: Composition Has Inverse

Let $f \in k[[x]]$ and $I(x) = x$. Then a right inverse exists, $f \circ g$ if and only if $f(0) = 0$ and $f'(0) \neq 0$ (i.e. $a_1 \neq 0$). For g to also be a left-inverse, we require $g(0) = 0$, in which case

$$f \circ g = g \circ f = I$$

9.2.15 remark (If you know some calculus) Notice how the condition $f'(0) \neq 0$ bears resemblence to the inverse function theorem

***Proof*:**
We want to a g such that $f(g(z)) = z$. We want:

$$a_0 + a_1(b_1 z + b_2 z^2 + \cdots) + a_2(b_1 z = b_2 z^2 + \cdots)^2 = z$$

expanding and using the method of undetermined coefficients expanding the first two terms we get:

$$a_0 = 0 \qquad a_1 b_1 = 1$$

This shows us that $a_0 = 0$ and $a_1 = f'(0) \neq 0$ are necessary conditions. To show they are sufficient conditions, we can see that we may deduce all other coefficeints given these conditions.For example, we may deduce the coefficient of z^n as $a_0 + a_1 g(z) + \cdots + a_n g(z)^n$, so

$$a_1 b_n + P_n(a_2, ..., a_n, b_1, ..., b_{n-1}) = 0$$

Thus, we would start by doing $b_1 = 1/a_1$, and $b_2, b_3, ...$ are defined recursively (this resulting polynomials is called *Bells polynomial*). With our construction, we have that g satisfies $b_0 = 0$ and $b_1 \neq 0$. Thus, we can do the same thing to g, that is $g(f_1(w)) = w$. These inverses are equal:

$$f_1 = \mathrm{id} \circ f_1 = (f \circ g) \circ f_1 = f \circ (g \circ f_1) = f \circ \mathrm{id} = f$$

where we assumed the associativity of composition, something that can be checked. Finally, for the radius of convergence, we shall delay such considerations for now, noting that when we show that holomorphic functions are analytic we can use the inverse function theorem to estimate the values.

Example 9.2.16: Formal Power Series
Some classical examples of power series include:

1. $\exp(x) = e^x = \sum_{k=0}^{\infty} \frac{x^k}{k!}$
2. $\cos(x) =$
3. $\sin(x) =$
4. $\log(x) =$

9.2.3 Matrix Rings

As was briefly mentioned in the preliminary chapter (section 0.5), many structures can be "represented as matrices", that is, instead of studying all these structure as separate algebraic objects, they all follow the same rules as matrix rings.

Definition 9.2.17: Matrix Ring

Let R be a ring. Then $M_n(R)$ is the collection of all $n \times n$ matrices with coefficients in R. Addition is defined term-wise and multiplication is defined via matrix-multiplication as given in section 0.5. A matrix may be represented by:

$$(a_{ij})_{ij} \in M_n(R)$$

where a_{ij} represents the value at position ij of the matrix. The identity of $M_n(R)$ is denoted I_n.

In the above notation, matrix multiplication AB of two matrices can be represented as

$$(c)_{ij} = \left(\sum_{k=1}^{n} a_{ik} b_{kj} \right)_{ij}$$

Note that $M_1(R) \cong R$, and $M_2(R)$ is *not* commutative, and always has zero divisors, for:

$$\begin{pmatrix} 0 & 1 \\ 0 & 0 \end{pmatrix} = \begin{pmatrix} 1 & 0 \\ 0 & 0 \end{pmatrix} \cdot \begin{pmatrix} 0 & 1 \\ 0 & 0 \end{pmatrix} \neq \begin{pmatrix} 0 & 1 \\ 0 & 0 \end{pmatrix} \cdot \begin{pmatrix} 1 & 0 \\ 0 & 0 \end{pmatrix} = \begin{pmatrix} 0 & 0 \\ 0 & 0 \end{pmatrix}$$

R can be embedded into R by taking by taking mapping it to the diagonal:

$$a \mapsto (a)_{ii}$$

where the matrix $(a)_{ii}$ has zero in all other entries. It should be check that the subring of diagonal entries with all the same value is a subring, sometimes denoted $\iota(R) \subseteq M_n(R)$ to emphasize that $\iota(R)$ is an embedding, or RI_n. It should be check that $I_n = \iota(1)$. If R is commutative, then:

$$Z(M_n(R)) = RI_n$$

that is, the center of the matrix ring is the diagonals with the same coefficients. Slightly more generally, the subset of diagonal matrices also form a subring., espec Diagonal matrices are rather common, and so they are often denoted

$$\text{diag}(a_1, a_2, ..., a_n) = (a_i)_{ii}$$

Using the diagonal embedding, we can define a functor $M_n(-) : \mathbf{Ring} \to \mathbf{Ring}$ mapping R to the diagonal and φ to $M_n(\varphi)$ that maps $(a_{ij})_{ij} \mapsto (\varphi(a_{ij}))_{ij}$ (the reader should feel free to check this is indeed a functor). Thus, there is the following diagram:

$$\begin{array}{ccc} R & \xrightarrow{\varphi} & S \\ \downarrow & & \downarrow \\ M_n(R) & \xrightarrow[M_n(\varphi)]{} & M_n(S) \end{array}$$

Thus, if $S \subseteq R$, then $M_n(S) \subseteq M_n(R)$.

Matrix rings shall appear in many context, notably in the case when $R = k$ is a field in the theory of vector-spaces and when R is a division ring in representation theory.

9.2.4 Group Rings

We have seen how to take a set and turn it into a group in many ways (ex. trivial group $T(X)$, permutation group S_X, free group $F(X)$). Of these methods the free-group construction gave us a way to lift a set map to a group map. If you have read section 2.3.5, **Set** and **Grp** form a free-forgetful adjoint, which tells us that than the "lifting" of set functions to group homomorphisms happened in a "natural way". We can repeat this process with groups and rings, forming a "free ring" with respect to groups. This "free ring" will not be free with respect to *sets*, and so will differ from free groups[12]. However, after going through free rings with respect to groups, the reader might start seeing why both constructions are called *free*.

Definition 9.2.18: Group Ring

Let R be a commutative ring and let G be any group, where $g_0 = e$ is the identity, with the operation written multiplicity. Then define the *group ring* $R[G]$ (or RG) of G with respect to R to be the set of all formal sums:

$$\sum_{g_i \in G} a_i g_i$$

where only finitely many a_i are non-zero where addition is done point wise and the product is defined per monomial as $(ag_i)(bg_j) = (ab)g_k$ where ab is performed in R and $g_i g_j = g_k$, and then extended this is extended to multiplication of the formal sums using convolution.

Since $g_0 = e$, we often write $a_0 g_0 = a_0$. In this way, we can identify $R \subseteq R[G]$, and R in as a subring of $R[G]$ has it's original ring operations. Similarly, taking $a_{ij} = \delta_{ij}$[13] where

$$\delta_{ij} = \begin{cases} 0 & i \neq j \\ 1 & i = j \end{cases}$$

we can identify $G \subseteq R[G]$, and G as a subgroup of $R[G]$ has it's original group operation. Even better, $G \leqslant R[G]^\times$. It is an easy exercise to check that $R[G]$ is indeed a ring, and that $R[G]$ is commutative if and only if G is commutative. Another simple exercise to check is that R (identified as a subring of $R[G]$) is in the center of $R[G]$ ($R \subseteq Z(G)$), and that $1 \in R$ (identified as a subring of $R[G]$) is the identity of $R[G]$

The reader may see that group rings are indeed the free objects with respect to the forgetful functor **Ring** $\to$ **Grp** by repeating the construction given for free groups: Take the collection of set maps $f : G \to R$ where only finitely many $f(g)$ are nonzero (such maps are said to have *finite support*[14]). Then two elements are added pointwise, $h \mapsto f(h) + g(h)$, and multiplication has the following clever interpretation:

$$h \mapsto \sum_{ab=h} f(a)g(b) = \sum_{a \in G} f(a)g(a^{-1}h)$$

[12] We will cover free rings later

[13] this is called the Kronecker delta

[14] For those who know some calculus/analysis, this is similar to how many smooth functions are defined on compact support

Notice this sum is indeed finite since f, g have finite support.

Example 9.2.19: Group Rings

1. Let $R = \mathbb{Z}$ and $G = D_4$. Then, for example $3r^2 - s, rs + 9 \in \mathbb{Z}[D_4]$.
2. If G is any finite subgroup, and $S \subseteq R$ is a subring, then $S[G] \subseteq R[G]$ is a subring.
3. (If you know about the quaternions $\mathbb{H}$), then $\mathbb{R}[Q_8] \neq \mathbb{H}$, even though they both contain Q_8. Can you see why?
4. Let $R = \mathbb{Q}$ and $G = S_3$. Let $a = 3(2\ 3) - 4(1\ 2\ 3)$ and $b = 1/2(1\ 2) + 5(3\ 2\ 1)$. Compute:

$$a + b \qquad ab$$

Note that if G has an element of finite order, then the group ring always has zero divisors: let $g \in G$ such that $m = |g| > 1$. Then

$$(1 - g)(1 + ... + g^{m-1}) = 1 - g^m = 1 - 1 = 0$$

Exercise 9.2.1

1. Is $R[x]$ isomorphic to $\oplus_{i=1}^{\infty} R$? Is $R[[x]]$ isomorphic to $\prod_{i=1}^{\infty} R$?)
2. Let $f|g$. Does this imply $\deg(f)\big|\deg(g)$?
3. Let R be a **non**-commmutative ring. Define the appropriate ring so that for any set function $f : A \to S$, there is a unique map $\iota : A \to R$ to the ring $F : R \to S$ such that the diagram commutes. That is, define the free object in the general case so that it is left-adjoint to the forgetful functor **Ring** $\to$ **Set**.
4. Take the full sub-category **Poly-Ring** $\subseteq$ **Ring**. What is the inital object of **Poly-Ring**?
5. Let $p(x) \in R[x]$ be a polynomial such that for all $r \in R$,

$$p(r) = a_n r^n + \cdots + a_1 r + a_0 \neq 0$$

   Show that there is an extension $S \supseteq R$ such that there exists $s \in S$ where $p(s) = 0$. In particular, there exists an S such that there exists a natural inclusion $\iota : R \hookrightarrow S$, $p(x)$ naturally includes in S and some element $s \in S$ is a root to $p(x)$:

$$p(s) = a_n s^n + \cdots + a_1 s + a_0 = 0$$

6. Show that $R[\mathbb{N}] \cong R[x]$. Show that $R[\mathbb{Z}] \cong R[x, x^{-1}]$
7. Is $\mathbb{Z}[x, x^{-1}] \cong \mathbb{Z}[[x]]$

9.3 Ring Homomorphisms and Quotient Rings

In this section, we explore the structure of the quotient objects of rings, that is, if $\varphi : R \to S$ is a ring-homomorphism, we aim to describe the structure of $\varphi(R) \subseteq S$ given structure for R. We first

recall the definition of ring homomorphisms from the first section:

Definition 9.3.1: Ring Homomorphism Remainder

Let R and S be rings. Then:

1. *ring homomorphism* is a map $\psi : R \to S$ satisfying
   (a) $\varphi(a+b) = \varphi(a) + \varphi(b)$
   (b) $\varphi(a \cdot b) = \varphi(a) \cdot \varphi(b)$
   (c) $\varphi(1_R) = 1_S$
2. The *kernel* of the ring homomorphism φ, denoted $\ker(\varphi)$ is the set of elements of R that map to 0 in S
3. A ring homomorphism with an inverse that is a ring homomorphism is a *ring isomorphism.*

If the context is clear, "homomorphism" will be used instead of "ring homomorphism". Also, if A, B are rings, then $A \cong B$ will always be interpreted as an isomorphism between the two rings.

Example 9.3.2

1. $\pi : Z \to \mathbb{Z}/2\mathbb{Z}$, here $\pi(x) = [x]$ is the natural projection map, is a ring homomorphism
2. $\varphi_n : \mathbb{Z} \to \mathbb{Z}$, $\varphi_n(x) = nx$ is *not* a ring-homomorphism.
3. $\varphi : \mathbb{Q}[x] \to \mathbb{Q}$, $\varphi(p(x)) = p(0)$ is a ring homomorphism, here $\ker\varphi = \{a_n x^n + \cdots + a_1 x\}$. Notice that every elements in the kernel has an x. We can also think of this as $p(x) \cdot x$ for any $p(x) \in \mathbb{Q}[x]$. This way of looking at it will become the main way we look at the kernel of a ring homomorphism shortly.
4. As shown earlier, if $S \subseteq R$ has a ring-structure, then if the inclusion map $i : S \to \mathbb{R}$ is a [ring] homomoprhism, then S is a subring.
5. The inclusion map $\mathbb{Z} \hookrightarrow \mathbb{Q}$ is a ring homomorphism. Is there a non-trivial homomorphim from $\mathbb{Q}$ to $\mathbb{Z}$?
6. Embedd $k[x] \hookrightarrow k[[x]]$ by mapping $k[x]$ to be all formal power series with only finitely many nonzero elements. Then by proposition 9.2.10, any polynomial $p(x) \in k[x]$ such that $p(0) \neq 0$ under the evaluation map is invertible in $k[[x]]$. Hence, there is a power series that can be identified by $1/p(x)$. Thus, we may define polynomial quotients in $k[[x]]$
$$\frac{p(x)}{q(x)} \qquad q(0) \neq 0$$
7. Is the derivative map $\frac{d}{dx} : k[[x]] \to k[[x]]$ defined by
$$\frac{d}{dx}\left(\sum_{k=0}^{\infty} a_k x^k\right) = \sum_{k=0}^{\infty} k a_k x^{k-1}$$
   a ring homomorphism? what is $\frac{d}{dx}(fg)$?

8. Let k be a field and $T = \sum_{n\geq 0} b_n y^n \in k[[y]]$ with $b_0 = 0$. For $f = \sum_{n\geq 0} a_n x^n \in k[[x]]$, define $f \circ T = \sum_{n\geq 0} a_n T^n$, where each coefficient is a finite sum because T^n has no terms of degree below n. Show that $f \mapsto f \circ T$ is a ring homomorphism $k[[x]] \to k[[y]]$. What goes wrong if $b_0 \neq 0$?

Just as the study of group-homomorphisms is equivalent to finding a normal subgroup H and studying G/H, so too will there be a link between ring-homomorphisms and a special subset I of R for which R/I represents the homomorphism. Just like for group-homomorphisms, the set I is based on the kernel of the ring-homomorphism, and R/I will be isomorphic to the image of φ:

Proposition 9.3.3: Image and Kernel of Ring Homomorphism

Let R, S be rings and $\psi : R \to S$ be a homomorphism.

1. The image of ψ is a sub-ring of S
2. the kernel of ψ is, in general, *not* a subring of R. Rather, the kernel $I = \ker(\psi)$ retains the abelian structure of R (i.e. $a - b \in I$ for all $a, b \in I$), and is closed under multiplication (left/right multiplication)[a] from elements of R (for all $r \in R$ and $i \in I$, $ri \in \ker(\psi)$ and $ir \in \ker(\psi)$).

[a] note that it was specified that it was both left and right multiplication because the multiplication is not necessarily commutative, while addition is

As an example of a kernel, take $\varphi : \mathbb{Z}[x] \to \mathbb{Z}[x]$, $p(x) \mapsto p(0)$. Then $\ker(\varphi) = x\mathbb{Z}[x]$, which is not a ring as $1 \notin x\mathbb{Z}[x]$. Kernels are the more general object *rng*. Note that if we define a ring to not have an identity, then the kernel would indeed be a sub-ring of R. Some authors define rings to not have an identity for this very reason. However, as a consequence, almost every theorem will have to be prefaced with "let R be a ring with identity", meaning the study of ring theory will ultimately be the study of a special case of rings with identity, which begs the question whether broadening the definition to not have an identity is worth the trade-off. However one sees it, it is simply a mathematical reality that kernels are different objects than rings (as the proposition suggests), and this author belives it is better to treat them as such[15]. Kernels will soon be defined as *ideals* (definition 9.3.6) since they have different properties from rings.

***Proof*:**
The map ψ is a homomorphism of the additive groups, so $\psi(a-b) = \psi(a) - \psi(b)$ for all $a, b \in R$ (proposition 1.4.4(2)).

1. The image $\psi(R)$ is an additive subgroup of S (proposition 1.4.4(5)). It is closed under multiplication, since $\psi(a)\psi(b) = \psi(ab)$, and it contains $1_S = \psi(1_R)$. By corollary 9.1.7, $\psi(R)$ is a subring of S.
2. Let $I = \ker \psi$ and take $a, b \in I$. Then

$$\psi(a - b) = \psi(a) - \psi(b) = 0 \Rightarrow a - b \in I$$

showing that I is closed under subtraction, and in particular is an additive subgroup of R.

Now take $r \in R$. We want to show that for any $i \in I$, $ri, ir \in I$. The key to this proof is

[15] The fact that the kernel is not a ring means that the category of **Ring** does not have kernel objects

proposition 9.1.9(1). Then

$$\psi(ri) = \psi(r)\psi(i) = \psi(r) \cdot 0 = 0 \Rightarrow ri \in I$$

and similarly

$$\psi(ir) = \psi(i)\psi(r) = 0 \cdot \psi(r) = 0 \Rightarrow ir \in I$$

Thus, I is closed under left-right multiplication of R, completing the proof.

9.3.4 Remark As a consequence of kernels not being subrings, the concept of extensions as discussed in section 3.6 do not apply so simply to rings! A group extension relied on the fact that both N and G/N were groups. Since ideals are not rings, the same concept does not apply for rings! There is an analogous concept of a "ring extension"[a], which generalize the notion of an extension by just requiring a ring extension S of R to be that there exists an injective ring homomorphism $\varphi : R \to S$ (similarly to how if $N \trianglelefteq G$ then we always have that $N \hookrightarrow G$). This notion of ring extension will be central to us in chapter 26 [b], but the "block-building" story that happened for groups does not play out in the same way for rings. However, any ring R is naturally an R-module (Part III), and modules have extensions defined on them [c]. Thus, we may study the extensions of rings in a group-theoretic way in the context of module theory.

[a] not to be confused with ring extensions that extend a ring by an abelian group as described in Nagata Masayoshi's book *Local Rings* (see Wikipedia article)

[b] It will be the fundamental way we look at varieties and number fields

[c] The category of R-module is closed under kernels

This does not mean that we cannot define $R/\ker(\varphi)$. In fact, $R/\ker(\varphi)$ will be a well-defined ring, as we explore now. Note that since R is an abelian group, and φ is also always a group-homomorphism, $\ker\varphi$ is always be a normal group. If we label $I = \ker(\varphi)$ then R/I already has a group structure, that is:

$$(r + I) + (s + I) = (r + s) + I$$

is well defined. The question becomes if we can also add a multiplicative structure to the quotient group, that is:

$$(r + I) \cdot (s + I) = (rs) + I \qquad \text{(in equivalence class notation: } [x \cdot y] = [x] \cdot [y])$$

With I the kernel of a ring homomorphism, the multiplication is well-defined. For $i, k \in I$ and $r, s \in R$:

$$\varphi((r+i)(s+k)) = \varphi(r+i)\varphi(s+k) = (\varphi(r)+\varphi(i))(\varphi(s)+\varphi(k)) = \varphi(r)\varphi(s)+0+0+0 = \varphi(r)\varphi(s)$$

where we used both the additive and multiplicative linearity condition. Labelling $[x] = x + I$, we call $(R/I, +_\sim, \cdot_\sim)$ with $+_\sim$ and $\cdot_\sim$ being defined through φ the *quotient ring* [16]. Thus, I being the kernel of a ring is a sufficient condition to make R/I into a ring. Is it a necessary condition? That is, can there be weaker structures that still preserves the multiplicative structure as shown above? For example, can I simply be a normal subgroup and always preserve the multiplicative structure? The answer is no:

[16] as before we will delay defining the quotient object till we find the sufficient conditions on I independent of a ring homomorphism

Example 9.3.5: : Quotient group without preserving multiplicative property
Take $\mathbb{Q}/\mathbb{Z}$ as a quotient group. Since $\mathbb{Q}$ is abelian, $\mathbb{Q}/\mathbb{Z}$ is a well-defined quotient group. Suppose the rule $(r+\mathbb{Z})(s+\mathbb{Z}) = rs+\mathbb{Z}$ were a well-defined multiplication. Since $1+\mathbb{Z} = 0+\mathbb{Z}$, every $s \in \mathbb{Q}$ would satisfy

$$s+\mathbb{Z} = (1+\mathbb{Z})(s+\mathbb{Z}) = (0+\mathbb{Z})(s+\mathbb{Z}) = 0+\mathbb{Z}$$

using $0 \cdot s = 0$ (proposition 9.1.9(1)). But $\frac{1}{2}+\mathbb{Z} \neq 0+\mathbb{Z}$, since $\frac{1}{2} \notin \mathbb{Z}$. So the multiplication of $\mathbb{Q}$ does not pass to the quotient group $\mathbb{Q}/\mathbb{Z}$.

So we must figure out what properties I requires for closure of multiplication. Let's say that I is a normal subgroup, and let's work with the cosets R/I. Let's say that multiplication of cosets is well defined. That would imply that

$$[r+i][s+j] = [rs] \qquad i,j \in I$$

that is, multiplication is independent of representation. If $r = s = 0$, then that means that

$$(i+I)(j+I) \in I \Rightarrow ij \in I$$

meaning that I is closed under multiplication. Next, what if $s = 0$ and r is arbitrary. Then that would lead to $[r][0] = [r0] = [0]$ by proposition 9.1.9(1), which, written in terms of cosets with $j \in I$ representing the class $[0] = I$, will be:

$$\begin{aligned} &(r+I)\cdot(j+I) = I \\ \Rightarrow &rj+I = I \\ \Rightarrow &rj \in I \end{aligned}$$

and since r is any arbitrary element $r \in R$, then I must be closed under left multiplication of any element of R. Similarly if $r = 0$, meaning $js \in I$.

Conversely, let's say I is closed under multiplication from the left and right-side: $\forall i \in I$, $ri \in I$, $ir \in I$ $\forall r \in R$. Then

$$\begin{aligned} \big((r+i)+I\big)\cdot\big((s+j)+I\big) &= (r+i)(s+j)+I \\ &= (rs+rj+is+ij)+I \\ &= (rs+I)+(rj+I)+(is+I)+(ij+I) \end{aligned}$$

and since I is closed under multiplication, $ij \in I$, and since I is closed under left and right multiplication by any element of R, $rj, is \in I$, meaning we are left with:

$$= (rs)+I$$

meaning we are once again representative independent. Thus, we showed that left and right R-closure of I is a necessary *and* sufficient condition for the cosets defined by I to have a 2nd operation.

As with cosets, the equivalence classes induced by ring homomorphisms are given a special name:

Definition 9.3.6: Ideals

Let R be a ring, and let I be a subset of R, and let $r \in R$. Then:

1. $rI = \{ra | a \in I\}$, and $Ir = \{ar | a \in I\}$
2. a subset I of R is a *left ideal* if I is an additive subgroup of R that is closed under *left* multiplication by elements from R ($rI \subseteq I$ for all $r \in R$)
3. Similarly, I is a *right* ideal if I is an additive subgroup of R that is closed under *right* multiplication by elements from R ($Ir \subseteq I$ for all $r \in R$)
4. A subset I that is *both* a left and right ideal is called an *ideal* (or, for added emphasis, a *two-sided* ideal) of R


Example 9.3.7

1. Take $m \in \mathbb{Z}$. Then $m\mathbb{Z} \subseteq \mathbb{Z}$ is an ideal. Similarly for $\mathbb{Z}m$.
2. Take $m \neq 0$ and $m\mathbb{Z} \subseteq \mathbb{R}$. Then $m\mathbb{Z}$ is not an ideal (since $\frac{1}{2m} \cdot m = \frac{1}{2} \notin m\mathbb{Z}$).
3. In $\mathbb{Z}_4 \times \mathbb{Z}_4$, $\langle (1,1) \rangle$ is a sub-ring, but not an ideal
4. Take any product of two rings $R \times S$. Then $R \times 0 \subseteq R \times S$ is an ideal, since for any $(a, 0) \in R \times 0$, $(R \times S) \cdot (a, 0) \subseteq R \times 0$. It is a ring with identity $(1, 0)$, but it is not a subring of $R \times S$ when $S \neq 0$, as it does not contain $(1, 1)$. No proper ideal contains 1, since an ideal containing 1 contains $r \cdot 1 = r$ for every r.

9.3.8 Trivia Why is it called an ideal? In number theory, people tried finding more information about polynomials like

$$x^2 - d = 0 \Rightarrow x = \sqrt{d}$$

And we would construct the field $\mathbb{Q}(\sqrt{d}) = \left\{a + b\sqrt{d} | a, b \in \mathbb{Q}\right\}$ which was called $\mathbb{Q}$ with $\sqrt{d}$ adjoint. This ring (in fact field) has a sub-ring $\mathbb{Z}[\sqrt{d}]$ and Q, making the diagram:



So, with this construction, we have the question of developping the concept of prime number in $\mathbb{Z}$ to it in $\mathbb{Z}[\sqrt{d}]$. If you try to take the same idea (a element that has no divisors in the ring except the element and ± 1). But it turns that if you try to define an element of that, elements do not necessarily have a unique factorization!
Example
This is so fundamental that this was dropped as a good definition as prime element in $\mathbb{Z}[\sqrt{d}]$. Insead, the proper generalization of this concept will turn out to be ideals in $\mathbb{Z}$ which will be called *prime ideals*, and then look at their natural extension into $\mathbb{Z}[\sqrt{d}]$. The word "ideal" here comes from how these elements would be the *ideal numbers*. The word number will eventaully get dropped, leaving us with ideal.

9.3.9 Computational Shortcut To prove that I is an ideal, we must show that I is non-empty, that it is closed under subtraction (so that it is an additive subgroup, normal since $(R, +)$ is abelian), and that $rI \subseteq I$ and $Ir \subseteq I$ for all $r \in R$. Since R has a 1, you can replace "closed under subtraction" by "closed under addition", since $(-1)a = -a$ (proposition 9.1.9(4)) will cover the negative case

Another reason to treat ideals differently than rings is the following:

> Another way of how ideals are different form rings is that being a ideal is "ring-dependent". For example $(x) = \mathbb{R}[x]x$ is an ideal of $\mathbb{R}[x]$, but not an ideal of $\mathbb{C}[x]$, since $i \cdot x = ix \notin \mathbb{R}[x]x$. This points again to how ideals are different.

This discussion is summarized in the following proposition:

Definition 9.3.10: Quotient Ring

When I is an ideal of R. The ring R/I with the natural multiplicative operation is called the *quotient ring* of R by I.

Proposition 9.3.11: Quotient groups and Ring Homomorphism

Let R be a ring and let I be an ideal of R. Then the (additive) quotient group R/I is a ring under the binary operation:

$$(r+I)+(s+I)=(r+s)+I \qquad \text{and} \qquad (r+I)\cdot(s+I)=(r\cdot s)+I$$

for all $r, s \in R$. Conversely, if I is any additive subgroup of R such that the above operations are well defined, then I is an ideal of R.

***Proof*:**
The additive group $(R,+)$ is abelian, so I is a normal subgroup and R/I is an abelian group under the stated addition, which is well defined. If $r+I=r'+I$ and $s+I=s'+I$, write $r'=r+i$ and $s'=s+j$ with $i,j\in I$. Then

$$r's'=rs+(rj+is+ij)$$

and $rj, is, ij \in I$ because I is an ideal, so $r's'+I=rs+I$ and the multiplication is well defined. The associative and distributive laws hold in R/I because they hold for representatives in R, for instance $\big((r+I)(s+I)\big)(t+I)=(rs)t+I=r(st)+I=(r+I)\big((s+I)(t+I)\big)$, and $1+I$ is an identity. So R/I is a ring.

Conversely, let I be an additive subgroup for which the multiplication is well defined, and let $r\in R$ and $i\in I$. Since $i+I=0+I$, well definedness and proposition 9.1.9(1) give

$$ri+I=(r+I)(i+I)=(r+I)(0+I)=0+I \qquad ir+I=(i+I)(r+I)=(0+I)(r+I)=0+I$$

so $ri, ir\in I$, and I is an ideal of R, as claimed.

Just like for groups, we can ask if every ideal is the kernel of a ring homomorphism, essentially asking for the 1st isomorphism theorem for rings (i.e. the universal property of quotient rings). This turns out to be the case:

Theorem 9.3.12: The first isomorphism theorem for Rings

1. If $\varphi : R\to S$ is a homomorphism of rings, then the kernel of φ is an ideal of R, the image of φ is a subring of S and $R/\ker(\varphi)$ is isomorphic as a ring to $\varphi(R)$, by the isomorphism $r+\ker(\varphi)\mapsto\varphi(r)$.
2. If I is any ideal of R, then the map

   $$R\to R/I \qquad \text{defined by} \qquad r\mapsto r+I$$

   is a surjective ring homomorphism with kernel I (this homomorphism is called the *natural projection* of R onto R/I). Thus every ideal is the kernel of a ring homomorphism and vice versa.

***Proof*:**

1. Let $K = \ker(\varphi)$. By proposition 9.3.3(2), K is an additive subgroup of R closed under left and right multiplication by elements of R, that is, an ideal (definition 9.3.6), and by proposition 9.3.3(1), $\varphi(R)$ is a subring of S. So R/K is a ring (proposition 9.3.11). The additive group of R is abelian, so K is a normal subgroup of it contained in the kernel of φ, and theorem 3.1.15 applied to the additive groups gives a homomorphism of additive groups $\Phi\colon R/K \to S$ with $\Phi(r+K) = \varphi(r)$. It is multiplicative, since

$$\Phi\big((r+K)(s+K)\big) = \Phi(rs+K) = \varphi(rs) = \varphi(r)\varphi(s) = \Phi(r+K)\Phi(s+K)$$

   and $\Phi(1+K) = \varphi(1) = 1$, so Φ is a ring homomorphism. Its image is $\varphi(R)$. It is injective: if $\Phi(r+K) = \varphi(r) = 0$, then $r \in K$ and $r + K = 0 + K$. So Φ is a bijective ring homomorphism from R/K onto $\varphi(R)$, hence a ring isomorphism by the remark following definition 9.1.5.

2. Let $\pi(r) = r + I$. By the definition of the operations of R/I (proposition 9.3.11), $\pi(r+s) = \pi(r) + \pi(s)$, $\pi(rs) = \pi(r)\pi(s)$ and $\pi(1) = 1 + I$, so π is a ring homomorphism, and it is surjective because every element of R/I is a coset $r + I$. Its kernel is $\{r \in R \mid r + I = 0 + I\} = I$. So every ideal is the kernel of a ring homomorphism, and by (1) every kernel of a ring homomorphism is an ideal, completing the proof.

As with groups, the bar notation $\overline{r}$ or r mod I notation is used to represent the equivalence class $[r]$.

Example 9.3.13

1. R and $\{0\}$ are ideals. An ideal is proper if $I \neq R$. The set with only zero is called the *trivial* ideal.

2. $n\mathbb{Z}$ is an ideal of $\mathbb{Z}$.

3. Take $R = \mathbb{Z}[x]$, and let I be the subset whose polynomials are of degree at least 2. Note that I is closed under addition and multiplication, and thus an ideal. The cosets consist of the elements with the same 0th and 1st term, so

$$\overline{1 + 2x + x^2} = \overline{1 + 2x - 5x^3} = \overline{1 + 2x + x^6 + 87x^{1231}}$$

   Note that $\overline{x}\,\overline{x} = \overline{x^2} = \overline{0}$, thus R/I has a zero divisor, even though $\mathbb{Z}[x]$ does not .

4. We saw $\mathbb{Q}[x]/(x)$. Let's try another polynomial: $\mathbb{Q}[x]/(x^2-2)$. Since we can divide polynomials, we can divide any polynomial by $x^2 - 2$. We can in fact keep dividing it till we get a polynomial of lesser degree. We then get that

$$\mathbb{Q}[x]/(x^2-2) = \{ax + b | a, b \in \mathbb{Q}\}$$

   Note that $x^2 - 2$, so $x^2 - 2 = 0 \Rightarrow x = \pm\sqrt{2}$. So, since $[x^2 - 2] = [0]$, this will make

$$\mathbb{Q}[x]/(x^2-2) \cong \mathbb{Q}(\sqrt{2}) = \left\{x + y\sqrt{2} | x, y \in \mathbb{Q}\right\}$$

   Or, more specifically, if we take the ring-homomorphism $\varphi : \mathbb{Q}[x] \to \mathbb{Q}(\sqrt{2})$, $p(x) \mapsto p(\sqrt{2})$, then This is a isomorphism.

5. If we take $k[x,y]$, then $k[x,y]/(x) \cong k[y]$
6. Let $G = \langle g \rangle$ be a cyclic group and k be any field. Define:

$$\varphi : k[G] \to k[x] \qquad \varphi(ag^k) = ax^k \qquad \forall a \in k$$

Show that:

$$k[G] \cong \frac{k[x]}{x^n - 1}$$

Example 9.3.14
Let's say you want to figure out all integer solutions to

$$x^2 + y^2 = 3z^2$$

Suppose such integers exist. Observe first that we may assume x, y and z have no factors in common, since otherwise we could divide through this equation by the square of this common factor and obtain another set of integer solutions smaller than the initial ones. This equation simply states a relation between these elements in the ring $\mathbb{Z}$. As such, the same relation must also hold in any quotient ring as well. In particular, this relation must hold in $\mathbb{Z}/n\mathbb{Z}$ for any integer n. The choice $n = 4$ is particularly efficacious, for the following reason: the squares mod 4 are just 0^2, 1^2, 2^2, 3^2, i.e., 0, 1 (mod 4). Reading the above equation mod 4 (that is, considering this equation in the quotient ring $\mathbb{Z}/4\mathbb{Z}$), we must have

$$\begin{Bmatrix} 0 \\ 1 \end{Bmatrix} + \begin{Bmatrix} 0 \\ 1 \end{Bmatrix} = + \begin{Bmatrix} 0 \\ 3 \end{Bmatrix} \qquad (\text{mod} 4)$$

where the $\begin{Bmatrix} 0 \\ 1 \end{Bmatrix}$ indicate that either a 0 or a 1 may be taken. The only possibility is if they are all even, but we assumed they were not, thus there is no solution.

Note that this technique has limitation. The following equation has solution integers modulo any n, but no integer solutions (which is hard to prove).

$$3x^3 + 4x^3 + 5z^3 = 0$$

Eventually, we will be using a similar technique to factor polynomial.

There is also the 2nd, 3rd, and 4th isomorphisms theorems. Each of these are quite easy to show: We already know they are true because R is an *additive group* (or *correspondence of groups*, in the case of the Fourth Isomorphism theorem). It only needs to be show that the group isomorphism is also a multiplicative map, and thus a ring-isomorphism.

Beforehand, we had $H, K \leqslant G$ and defined HK. Since we are now writing the group operation additively, we will convert our notation to saying $H + K$. If I, J are subrings of R, then since they are both normal (even abelian) subgroups, then $I + J$ is well-defined.

Theorem 9.3.15: 2nd, 3rd, 4th Isomorphism Theorem for Rings

Let R be a ring.

(2) Let A be a subring and B be an ideal of R. Then $A+B$ is a subring of R, B is an ideal of $A+B$, $A \cap B$ is an ideal of A, and $\frac{A+B}{B} \cong \frac{A}{A \cap B}$

(3) Let I, J be ideals of R with $I \subseteq J$. Then J/I is an ideal of R/I and $(R/I)/(J/I) \cong R/J$

(4) Let I be an ideal of R. The correspondence $A \leftrightarrow A/I$ is an inclusion preserving bijection between the set of subrings A of R that contain I and the set of subrings of R/I, and it restricts to an inclusion preserving bijection $J \leftrightarrow J/I$ between the set of ideals J of R that contain I and the set of ideals of R/I. In both cases the inverse sends a subset of R/I to its preimage under the natural projection $R \to R/I$.

***Proof*:**
In (3) and (4), $\pi\colon R \to R/I$ is the natural projection $r \mapsto r+I$, a surjective ring homomorphism with kernel I (theorem 9.3.12(2)), and for a subset $X \subseteq R$ we write $X/I = \{x+I \mid x \in X\} = \pi(X)$.

(2) The set $A+B$ contains $0 = 0+0$ and $1 = 1+0$, and it is an additive subgroup of R, since $(a+b)-(a'+b') = (a-a')+(b-b')$ for $a, a' \in A$ and $b, b' \in B$. It is closed under multiplication, since

$$(a+b)(a'+b') = aa' + (ab' + ba' + bb')$$

where $aa' \in A$ and the bracket lies in B because B is an ideal of R. By corollary 9.1.7, $A+B$ is a subring. It contains B, and B absorbs multiplication by every element of R, so B is an ideal of $A+B$, and $(A+B)/B$ is a ring by proposition 9.3.11. Define

$$\varphi\colon A \to \frac{A+B}{B} \qquad \varphi(a) = a+B$$

For $a, a' \in A$, $\varphi(a+a') = (a+B)+(a'+B)$ and $\varphi(aa') = (a+B)(a'+B)$ by the definition of the operations on the quotient ring, and $\varphi(1) = 1+B$, so φ is a ring homomorphism. It is surjective, since $(a+b)+B = a+B = \varphi(a)$ for $a \in A$ and $b \in B$. Its kernel is $\{a \in A \mid a+B = B\} = A \cap B$. By theorem 9.3.12(1) applied to φ, $A \cap B$ is an ideal of A and $A/(A \cap B) \cong \varphi(A) = (A+B)/B$.

(3) The set $J/I = \pi(J)$ is an additive subgroup of R/I, being the image of the additive group J under the restriction of π to J (proposition 1.4.4(5)). For $r \in R$ and $j \in J$, $(r+I)(j+I) = rj+I$ and $(j+I)(r+I) = jr+I$ lie in J/I because $rj, jr \in J$, so J/I is an ideal of R/I. Define

$$\psi\colon R/I \to R/J \qquad r+I \mapsto r+J$$

If $r+I = r'+I$, then $r-r' \in I \subseteq J$, so $r+J = r'+J$, and ψ is well defined. It sends sums to sums, products to products and $1+I$ to $1+J$, by the definition of the operations on the two quotient rings, and it is surjective. Its kernel is $\{r+I \mid r \in J\} = J/I$, because $r+J = J$ exactly when $r \in J$. By theorem 9.3.12(1), $(R/I)/(J/I) \cong R/J$.

(4) The additive group of R is abelian, so I is a normal subgroup of it. By theorem 3.5.7 applied to the additive groups, $X \mapsto X/I$ is a bijection from the additive subgroups X of R containing I onto the additive subgroups of R/I, and it preserves inclusions in both directions by corollary 3.5.8(1). Its inverse is $Y \mapsto \pi^{-1}(Y)$, because $\pi^{-1}(Y)$ is an additive subgroup containing I with $\pi(\pi^{-1}(Y)) = Y$, as π is surjective. It therefore suffices to show that this bijection matches subrings with subrings and ideals with ideals. Let A be an additive subgroup of R containing I. Then $\pi^{-1}(A/I) = A$: every $a \in A$ has $\pi(a) = a + I \in A/I$, and conversely, if $\pi(r) = a + I$ with $a \in A$, then $r - a \in I \subseteq A$, so $r \in A$.

If A is a subring, then A/I contains $1 + I$ and is closed under multiplication, since $(a + I)(a' + I) = aa' + I$, so A/I is a subring of R/I by corollary 9.1.7. Conversely, if A/I is a subring, then $\pi(1) = 1 + I \in A/I$ gives $1 \in \pi^{-1}(A/I) = A$, and for $a, a' \in A$, $\pi(aa') = \pi(a)\pi(a') \in A/I$ gives $aa' \in A$. So A is a subring.

If A is an ideal of R, then A/I is an ideal of R/I by the argument of (3). Conversely, if A/I is an ideal of R/I, then for $r \in R$ and $a \in A$ the elements $\pi(ra) = \pi(r)\pi(a)$ and $\pi(ar) = \pi(a)\pi(r)$ lie in A/I, so $ra, ar \in \pi^{-1}(A/I) = A$, and A is an ideal of R. This completes the proof.

9.3.16 Remark We can define a *simple ring* to be a nonzero ring whose only two-sided ideals are 0 and R[a], which mirrors the definition of simple groups. The simple commutative rings are exactly the fields[b]. For a field k, the matrix ring $M_n(k)$ is a simple ring that is not commutative for $n \geq 2$: if a two-sided ideal I contains $A \neq 0$ with $a_{ij} \neq 0$, then I contains $a_{ij}^{-1} E_{pi} A E_{jq} = E_{pq}$ for all p, q, where E_{pq} is the matrix with 1 in position (p, q) and 0 elsewhere, so I contains $\sum_p E_{pp} = 1$ and $I = M_n(k)$.

[a] the reason for sticking to two-sided ideals is because we can quotient R by two-sided ideals to get a quotient ring, but we cannot quotient by 1-sided ideals and get a quotient ring

[b] This fails for *rngs*: $\mathbb{Z}/p\mathbb{Z}$ with the zero multiplication has no ideals other than 0 and itself, and it is not a field.

Exercise 9.3.1

1. Let R, S be rings and consider the product ring $R \times S$. What are the ideals of $R \times S$?
2. Let I be an ideal of the ring R and let $(I) = I[x]$ denote the ideal of $R[x]$ generated by I (the set of polynomials with coefficient I). Then

   $$R[x]/(I) \cong (R/I)[x]$$

   In particular, if I is a prime ideal of R then (I) is a prime ideal of $R[x]$. Conclude that $\mathbb{Z}[x]/(n\mathbb{Z}[x]) \cong (\mathbb{Z}/n\mathbb{Z})[x]$
3. Show that the set of upper-triangular matrices is a subring.

9.4 Properties and Further Structures of Ideals

Since the kernel of ring homomorphisms are ideals, they form the core of much of ring theory. Recall how when working with groups, they can be thought of as $F(A)/N$ for an appropriate normal set N which represents the *relations* on the generators A. Ideals will play a role of similar importance: Ideals will represent the relations. There will be an analogous notion of free ring, however the study of generation of free rings shall be delayed to Part III since the two constructions are identical.

This is not to say that thinking of ideals as adding relations is un-useful! For example, since $\mathbb{Z}$ is initial in rings, it is of great interest to see how what relations ideals of $\mathbb{Z}$ can give us, what properties do they have, and how they translate with ring homomorphisms. (We will focus a lot on this in number theory).

The set generated by a subset $A \subseteq R$ under addition, negation and multiplication need not be a subring, since it need not contain 1. In $\mathbb{Z}$, the set generated by $\{2\}$ is $(2) = 2\mathbb{Z}$. In $\mathbb{Z}[x]$, the set generated by $\{1 + x\}$ is $\{p(1 + x) \mid p \in \mathbb{Z}[y],\ p(0) = 0\} = (1 + x)\,\mathbb{Z}[1 + x] = (1 + x)$, since $\mathbb{Z}[1 + x] = \mathbb{Z}[x]$, and it does not contain 1, because $(1 + x)g(x)$ has degree at least 1 for every nonzero g. Both sets are rngs and not rings. Since every rng embeds in a ring (box 9.1.2), this book works with rings.

9.4.1 Operations and Generation on Ideals

The first thing we might think of is way of extending how to manipulates ideals through binary operations (in essense, we find different ways of combining what relations we impose on a ring). We give a list of common operations of ideals

Definition 9.4.1: Operations on Ideals

Let R be a ring and $I, J \subseteq R$ be (left, right, or two-sided) ideals. Then:

1. $I \cap J$ is the intersection of two ideals. More generally,

$$\bigcap_{i \in \mathcal{I}} I_i$$

is the intersection of ideals I_i indexed by $\mathcal{I}$.

2. Define the *sum* of I and J by $I + J = \{a + b | a \in I, b \in J\}$. More generally,

$$\sum_{i \in \mathcal{I}} I_i = \left\{ \sum_{i \in N} a_i \;\middle|\; N \subseteq \mathcal{I},\ |N| \in \mathbb{N},\ a_i \in I_i \right\}$$

is the sums of ideals I_i indexed by $\mathcal{I}$.

3. Define the *product* of I and J, denoted IJ, to be the set of all finite sums of elements of he form ab wit $a \in I$ and $b \in J$.

$$\left\{ \sum_{i=1}^{n} a_i b_i \middle| a_i \in I,\ b_i \in J \right\}$$

Note that we must take finite sums since the ideal must be closed under addition. More generally:

$$\prod_{i \in \mathcal{I}} I_i = \left\{ \sum_{i=1}^{m} a_{i_1} \cdots a_{i_n} \;\middle|\; a_{i_1}, ..., a_{i_n} \in \mathcal{I}, n, m \in \mathbb{N} \right\}$$

4. For any $n \geq 1$, define the nth power of I, denoted I^n to be the set consisting of all finite sums of elements of the form $a_1 a_2 \cdots a_n$ with $a_i \in I$ for all $i>$ Equivalently, I^n is defined inductively by defining $I^1 = I$, and $I^n = II^{n-1}$ for $n = 2, 3, ...$ By convention $I^0 = R$.

5. Let R be commutative. Define the *ideal quotient* $(I : J)$ to be:

$$(I : J) := \{x \in R \mid xI \subseteq J\}$$

6. Let R be commutative. Define the *radical* of I to be

$$\sqrt{I} := \{r \in R \mid r^n \in I \text{ for some } n \geq 1\}$$

An ideal satisfying $I = \sqrt{I}$ is called a *radical ideal*.

Note that if I, J are *both* ideals, then $I + J$ is an ideal (this set is closed under sums and $r(a + b) = ra + rb \in I + J$). It should be emphasized that the set IJ is the *finite sum* of elements of the form ab. This condition is required so that IJ is closed under addition, which is necessary for IJ to be an ideal. Just like groups and rings, the union of two ideals is not an ideal (for example, $2\mathbb{Z} \cup 3\mathbb{Z}$ does not contain 5, however $2 \in 2\mathbb{Z}$, $3 \in 3\mathbb{Z}$). Can you show that the quotient ideal $(I : J)$ is indeed an

ideal? In some very lose way, if $a \in (x)$, then that means that x is a "factor" of a in the sense that $a = rx$ for some $r \in R$)

Example 9.4.2

1. Let $I = 6\mathbb{Z}$ and $J = 10\mathbb{Z}$. Then $I + J$ is the ideal of all integers of the form $6x + 10y$ for $x, y \in \mathbb{Z}$. Since 6 an 10 are divisible by 2, meaning that $6x + 10y = 2(3x + 5y)$, so that $2\mathbb{Z} \supseteq 6\mathbb{Z} + 10\mathbb{Z}$. Conversely, we see that $2 = 6(2) + 10(-1)$, so $2x = 6(2x) + 10(-x)$, meaning that every element of $2\mathbb{Z}$ can be written of the form $6\mathbb{Z} + 10\mathbb{Z}$, so $2\mathbb{Z} \subseteq 6\mathbb{Z} + 10\mathbb{Z}$. Thus $2\mathbb{Z} = 6\mathbb{Z} = 10\mathbb{Z}$. We can generalize this to $n\mathbb{Z} + m\mathbb{Z} = d\mathbb{Z}$ where $d = (m, n)$, in the next section. Similarly, it is worth checking that $6\mathbb{Z}10\mathbb{Z} = 60\mathbb{Z}$.
2. Take $I \subseteq \mathbb{Z}[x]$ to be the ideal whose constant term is even. Then (2) and (x) are in subsets of I. Thus, $4 = 2 \cdot 2$ and $x^2 = x \cdot x$ are in I^2, as is their sum $x^2 + 4$. However, $x^2 + 4$ cannot be written as a product $p(x)q(x)$ of two elements of I.
3. the ideal $((0) : I)$ known as
4. Let $(2), (6) \subseteq \mathbb{Z}$. Then $((2) : (6)) = (3)$, showing how the quotient ideal generlizes some notion of division. *annihilator of* I and consists of all elements of R such that $rx = 0$ for all $x \in I$. Usually, for any ideal $I = (r)$ generated by a single element, we write $(r : I)$ instead of $((r) : I)$. Using this, can you deduce what $(0 : R)$ is equal to?

The radical needs a word of its own, since unlike the other five operations it is not built from sums and products of elements already in the ideals, and that it is an ideal at all is a small argument rather than an observation.

Proposition 9.4.3: The Radical Is an Ideal

Let R be a commutative ring and $I \subseteq R$ an ideal. Then $\sqrt{I}$ is an ideal of R containing I, and $\sqrt{\sqrt{I}} = \sqrt{I}$.

***Proof*:**

Every $r \in I$ satisfies $r^1 \in I$, so $I \subseteq \sqrt{I}$. In particular $0 \in \sqrt{I}$.

For closure under the ring action, let $r \in \sqrt{I}$ with $r^n \in I$ and let $a \in R$. Since R is commutative, $(ar)^n = a^n r^n$, which lies in I because I absorbs multiplication, so $ar \in \sqrt{I}$.

For closure under addition, let $r^n \in I$ and $s^m \in I$. By the binomial theorem, valid in any commutative ring,

$$(r+s)^{n+m-1} = \sum_{i=0}^{n+m-1} \binom{n+m-1}{i} r^i s^{n+m-1-i}$$

Consider a single term. If $i \geq n$ then $r^i = r^n r^{i-n} \in I$. And if $i \leq n-1$ then $n+m-1-i \geq m$, so $s^{n+m-1-i} \in I$ by the same argument. Either way the term lies in I, and I is closed under addition, so $(r+s)^{n+m-1} \in I$ and $r + s \in \sqrt{I}$. Together with the previous paragraph this makes $\sqrt{I}$ an ideal.

Finally, if $r \in \sqrt{\sqrt{I}}$ then $r^n \in \sqrt{I}$ for some n, so $(r^n)^m = r^{nm} \in I$ for some m, giving $r \in \sqrt{I}$. The reverse inclusion is the first paragraph applied to $\sqrt{I}$, completing the proof.

We can also ask oursevles about the generation of ideals:

Definition 9.4.4: Generating Ideals

1. (A) is the smallest ideal containing A. Then
$$(A) = \cap_{A \subseteq I} I$$
where I is an ideal containing A.
2. RA is he set of all finite sums of elements of the form ra between R and A.
$$\{r_1 a_1 + \cdots + r_k a_k | r_i \in R, a_i \in A\}$$
Similarly for AR and RAR.
3. An ideal generated by a single element is a *principal ideal*.
4. an ideal generated by a finite set is called a *finitely generated ideal*.

If R is commutative, then $RA = AR = RAR = (A)$.

9.4.5 Moment To Ponder You might ask yourself, with addition and multiplication defined on the ideals, does the set of ideals form a ring? Try it out! Is this a way to study ideals? More on studying the ideal structure of a ring when studying Modules in Part III

In the following chapter's, ideals generate by a singleton (a) will be of keen interest. As a prelude, notice that if $b \in (a)$, then $b = ra$ for some $r \in R$. Phrased differently, a divides b. Also, $b \in (a)$ if and only if $(b) \subseteq (a)$. In other words, being an element inside the ideal gives some idea of "divisibility" or "factorization".

Example 9.4.6

1. (0) and R are both principal ideals, since (0) is generated by 0, and $R = (1)$ (since we assumed R has an identity).
2. Every ideal of $\mathbb{Z}$ is a principal ideal

Proof. We will show that $(m) + (n) = gcd(m, n)$

($\Rightarrow$) Let $x \in (m) + (n)$. Let's show that $x \in (m, n)$. Since $x \in (m) + (n)$, then:
$$x = ma + nb \qquad a, b \in \mathbb{Z}$$
letting $p = (m, n)$, we see that
$$ma + nb = (m'a + n'b)p = cp \in (m, n)$$
where m', n' are the remainders, and $c = m'a + n'b$, showing that $cp \in (m, n)$

($\Leftarrow$) Let $p = gcd(m, n)$. Without loss of generality, let's say $m > n$. We will take advantage of the euclidean algorithm. First, start with:

$$m = a_1 n - r_1$$

where r_1 is the remaidner by dividng m by n and a is the number of times n can be divided into m. This is the extended euclidean algorithm. We can work our way down till we get

$$r_k = a_{k+1} p - 0$$

where $p = gcd(m, n)$. Then, we can use Bézout's identity from the results to get that:

$$p = k_1 m - k_2 n$$

with appropriate k_1, k_2. This then implies that

$$cp = ck_1 m - ck_2 n$$

for any $c \in \mathbb{Z}$, and so cp can be written of the form $am + bn$, meaning $cp \in (m) + (n)$, as we sought to show.

We can use this to show that *any* (A) is a principle ideal in $\mathbb{Z}$. Since $\mathbb{Z}$ is commutative, we can think of $(A) = RA$. Then we can do the same greatest common denominator trick to get down to our desied number such that $d\mathbb{Z}$ is equal to $\mathbb{Z}A$. We can use this to show that every ideal of $\mathbb{Z}$ are principal ideals. Since $\mathbb{Z}$ is also an integral domain, meaning it's also a domain, we will end up calling $\mathbb{Z}$ a *principal ideal domain.*

However, it's not always true that if (a, b) can be reduced to (c) that a ring is a principal ideal domain. There is a sub-class of rings called *Bézout Domains* for which every pair of number can be reduced to a principal ideal, but the ring itself is *not* a principal ideal domain. More on that in chapter 10. □

3. Let $R = \mathbb{Z}[x]$. Then $(2, x)$ is *not* a principal ideal. Let

$$(2, x) = \{2p(x) + xq(x) | p(x), q(x) \in \mathbb{Z}[x]\}$$

that is, all polynomials with *even* constants (and hence, a proper ideals, since it does not containt 1). Let's say for some $a(x) \in \mathbb{Z}[x].(2, x) = (a(x))$. Since $2 \in (a(x))$, there must be some $p(x)$ such that $2 = p(x)a(x)$. By proposition 9.2.3, we know that degree $p(x)a(x) =$ degree $p(x)+$ degree$a(x)$, and since degree(2) is 0, then $a(x)$ and $p(x)$ must *both* be constant polynomials. Since 2 is a prime number, the only possibilities are $p(x), a(x) \in \{\pm 1, \pm 2\}$. If $a(x) = \pm 1$, then $1 \in (a(x))$, and so by proposition 9.4.10, $(a(x)) = \mathbb{Z}[x]$. But that's a contradiction to $(2, x)$ being proper. Thus, it must be that $a(x) = \pm 2$. But then, $x \in (\pm 2)$, and so $x = p(x)(\pm 2)$. But this is impossible. We'd need $\frac{1}{2}x$ to be $p(x)$, but $\frac{1}{2} \notin \mathbb{Z}$. Thus, $(2, x)$ is *not* a principal ideal. Thus $\mathbb{Z}[x]$ is *not* a principal ideal domain.

I like to thinke of elements of (p, q) for some $R[x]$ as elements in which every term has p or q as a factor. This is because when taking $\alpha p + \beta q$ for $\alpha, \beta \in R[x]$, you can have α or β be 0, meaning you just need elements which have p or q as a factor.

4. If we take $\mathbb{Q}[x]$ instead of $\mathbb{Z}[x]$, then this would be solved since $(2) = \mathbb{Q}[x]$ since $\frac{1}{2}2 = 1$, maning (2) has a unit, meaning $(2, x)$ has a unit. In fact, $\mathbb{Q}[x]$ will become a principal ideal domain because of this! Try playing around with the following ideals to see they are indeed principal

- $(2, x)$
- $(x, x^2 + 1)$
- $(p(x), q(x))$ for $p, q \in \mathbb{Q}[x]$.

5. Take $R = k[x]$ and take $I = \{p(x) \in k[x] | p(q) = 0\}$ for some arbitrarry $q \in \mathbb{F}$. One can check that it is an ideal. More interestingly though, we know from high-school math that if $p(x) = 0$, then we can factor out $p(x) = (x - q)r(x)$ for any polynomial $r(x) \in \mathbb{F}[x]$. This will thus make $I = ((x - q))$, making these ideals principal ideals! However, if $I = \{p(x) \in \mathbb{F}[x] | p(a) = p(b) = 0, a \neq b\}$ for two arbitrary $a, b \in F$, $a \neq b$, then I is *not* a principal ideal.

As the intuition for ideals suggest, they are a sort of generalization of properties of $\mathbb{Z}$. For example, if $a \in R$ and (a) is an ideal, then $R/(a)$ is well-defined. Now, take $\overline{b} \in R/(a)$ and generate $(\overline{b})$. Then it should be verified that

$$(R/(a)/(\overline{b}) = R/(a, b)$$

Furthermore, notice that in $\mathbb{Z}$, the ideal (a, b) is equal to the ideal $(\gcd(a, b))$. For this reason, ideals capture some more general sense of divisibility for rings! Exploring the notion of divisibility further will be the goal of chapter 10.

Since ideals are so important, it is often the case that studying rings with simpler ideal structure are of much interest. Two particular cases are especially important due to the abundance of finiteness:

Definition 9.4.7: Noetherian rings

Let R be a commutative ring. Then if every ideal[a] $I \subseteq R$ is finitely generated, then R is called a *Noetherian ring.*

[a] Be sure not to mistake ideal for ring, for finitely generated rings have not been defined

Noetherian rings are particularly nice in that they are finite locally and globally. If we just require that the ring is finitely generated, it may be that a subring is non-finitely generated. Conversely. We shall have lots of experience with Noetherian rings later, for now it is useful to know these rings since since being Noetherian is stable under taking the quotient, and is also stable under the "converse" of taking the quotient (if you have covered section 3.6, the Noetherian condition is stable under extensions). For the next proposition, note that a finitely generated ideal is defined identically to a finitely generated ring (that it is generated by finitely many elements):

Proposition 9.4.8: Noetherian Rings Under Quotients And Extensions

Let R be a commutative ring and I an ideal of R.

1. If R is Noetherian, then R/I is Noetherian.
2. Conversely, if R/I is Noetherian and every ideal of R contained in I is finitely generated, then R is Noetherian.

***Proof*:**
Let $\pi\colon R \to R/I$ be the natural projection, a surjective ring homomorphism with kernel I (theorem 9.3.12(2)). The ring R/I is commutative because R is, and in a commutative ring the ideal generated by $a_1, \dots, a_k$ is $\{r_1a_1 + \cdots + r_ka_k \mid r_1, \dots, r_k \in R\}$ (definition 9.4.4).

1. Let $\overline{J}$ be an ideal of R/I and $J = \pi^{-1}(\overline{J})$. Then J is an ideal of R: it is an additive subgroup, being the preimage of one under the additive homomorphism π, and $\pi(rx) = \pi(r)\pi(x) \in \overline{J}$ for $r \in R$ and $x \in J$. As R is Noetherian, J is generated by some $a_1, \dots, a_k \in J$. Every element of $\overline{J}$ is $\pi(x)$ for some $x \in J$, since π is surjective, and writing $x = r_1a_1 + \cdots + r_ka_k$ gives $\pi(x) = \pi(r_1)\pi(a_1) + \cdots + \pi(r_k)\pi(a_k)$. So $\overline{J}$ is contained in the ideal generated by $\pi(a_1), \dots, \pi(a_k)$, and it contains that ideal because it is an ideal containing each $\pi(a_i)$. Hence every ideal of R/I is finitely generated, and R/I is Noetherian.

2. Let J be an ideal of R. Its image $\pi(J)$ is an ideal of R/I: it is an additive subgroup, and $\pi(r)\pi(x) = \pi(rx) \in \pi(J)$ for $r \in R$ and $x \in J$, where every element of R/I has the form $\pi(r)$. As R/I is Noetherian, $\pi(J)$ is generated by finitely many of its elements, which we write as $\pi(a_1), \dots, \pi(a_k)$ with $a_1, \dots, a_k \in J$. The intersection $J \cap I$ is an ideal of R, being an additive subgroup that absorbs multiplication by R, and it is contained in I, so by hypothesis it is generated by some $b_1, \dots, b_l$. We claim that J is generated by $a_1, \dots, a_k, b_1, \dots, b_l$. These elements lie in J, so the ideal they generate is contained in J. Conversely, let $x \in J$. Then $\pi(x) \in \pi(J)$, so $\pi(x) = \pi(r_1)\pi(a_1) + \cdots + \pi(r_k)\pi(a_k)$ for some $r_i \in R$, and $y = x - (r_1a_1 + \cdots + r_ka_k)$ lies in $\ker \pi = I$. It also lies in J, since x and the a_i do. So $y \in J \cap I$, that is, $y = s_1b_1 + \cdots + s_lb_l$ for some $s_j \in R$, and

$$x = r_1a_1 + \cdots + r_ka_k + s_1b_1 + \cdots + s_lb_l$$

Hence every ideal of R is finitely generated, and R is Noetherian, as we sought to show.

One of the simplest Noetherian rings are those for which every ideal is not only finitely generated, but also principal. If the ideal is furthermore an integral domain (to avoid pathologies from zero-divisors) then it is a principal ideal domain:

Definition 9.4.9: Principal Ideal Domain

Let R be an integral domain. Then if every ideal $I \subseteq R$ is a principal ideal, then R is called a *Principal Ideal Domain*.

As a simple example, $\mathbb{Z}$ is a PID (can you see why?). It should be noted that *every* ideal is principal, even those that may seem infinitely-generated. In fact, there are domain in which only finitely-generated ideals are principle (such rings are called *Bézout* rings).

Another way of looking at principal ideal domains is that they are "locally free". Here, locality is taken to mean that any proper submodule is free. Since R is an integral domain, it is torsion free, and since R is principle, if $I \subseteq R$ is a submodule (i.e. ideal), then

$$I = (a) \qquad a \in R$$

This fact shall make PID's very powerful, and in fact the idea that PID's have "local freeness" shall be further explore in chapter 17⋆[17].

[17] A projective module over a PID is in fact a free module

Principal Ideal Domains (PIDs) will have the property of having "prime elements" well-defined and lend itself useful in many classification theorems (for example, study of Jordan Canonical Forms in chapter 14 will heavily rely on this type of ring).

Exercise 9.4.1

1. $(I \cap J)(I + J) = IJ$

9.4.2 Ideals and Units

As briefly mentioned, some ideals seem to be related to a notion of divisibility. This intuition more clear with the following theorem:

Proposition 9.4.10: units in Ideals and ideals in fields

Let R be a ring.

1. A left or right ideal I of R satisfies $I = R$ if and only if I contains a unit
2. Let R be nonzero. Then R is a division ring if and only if its only left- and right-sided ideals are 0 and itself. If R is commutative, then the only ideals of R are 0 and itself if and only if R is a field.

***Proof*:**

1. one inclusion is easy. The key part to the other inclusion is that I must be closed under multiplication from all elements of R. If $I = R$ then I contains the unit 1. If I contains a unit u, then given its inverse $v \in R$ and any element $r \in R$

$$r = r \cdot 1 = r(vu) = (rv)u \qquad r = 1 \cdot r = (uv)r = u(vr)$$

and the first expression lies in I when I is a left ideal, the second when I is a right ideal. So $I = R$.

2. If R is a division ring, then every nonzero element is a unit, so every nonzero left or right ideal contains a unit and equals R by (1). Conversely, suppose the only left and right-sided ideals are R and 0, and let $u \in R$ be nonzero. The set $Ru = \{ru \mid r \in R\}$ is a left ideal containing $u = 1u$, so $Ru = R$ and $1 = vu$ for some $v \in R$. Likewise uR is a right ideal containing u, so $1 = uw$ for some $w \in R$. Then $v = v(uw) = (vu)w = w$, so u is a unit. Since this holds for every nonzero element and $1 \neq 0$, R is a division ring. If R is also commutative, then Ru is an ideal, and the same argument shows that a nonzero commutative ring whose only ideals are 0 and itself is a commutative division ring, and thus a field. Conversely, a field is a division ring, so by the first part its only left ideals, and in particular its only ideals, are 0 and itself, completing the proof.

9.4.11 Note As a consequence, if $1 \in I$, then $I = R$, since 1 is a unit!! This means that in a proper ideal, $1 \notin I$, and so, they cannot be sub-rings with identity $1 \neq 0$.

It should be pointed out it was necessary to have the condition that both let and right-sided ieals are trivial, instead of just picking one or saying that only two-sided ideals are trivial.

Example 9.4.12: Two-Sided Ideals Trivial, but non-trivial left/right-sided ideals

Let k be a field and $M_2(k)$ the matrix ring over k. Then $M_2(k)$ has non-trivial left and right-sided ideals (think of columns and rows of $M_2(k)$): the matrices whose second column is zero form a left ideal, since multiplying on the left keeps a zero column zero, and the matrices whose second row is zero form a right ideal, and both are nonzero and proper. However, $M_2(k)$ has *no* two-sided non-trivial ideals (box 9.3.16).

Now, $M_2(k)$ is not a division ring: the element

$$\begin{pmatrix} 1 & 1 \\ 1 & 1 \end{pmatrix}$$

does not have an inverse, since

$$\begin{pmatrix} 1 & 1 \\ 1 & 1 \end{pmatrix} \begin{pmatrix} 1 & -1 \\ -1 & 1 \end{pmatrix} = 0$$

and an invertible A with $AB = 0$ forces $B = A^{-1}AB = 0$.

Since any two-sided ideal is a left and right ideal, then division ring's naturally have no non-trivial two-sided ideals.

Corollary 9.4.13: Division Ring and Ring-Homomorphism

If R is a division ring, then any non-zero ring-homomorphism $\varphi : R \to S$ to any other ring must be injective.

***Proof*:**

Let φ be a ring-homomrophism. The kernel of φ is a two-sided ideal of R, but R is a divison ring, meaning the only ideals of R are 0 and R. Since φ is non-trivial, $\ker \varphi \neq R$, and so $\ker \varphi = 0$, making φ injective.

This might make one think that studying division rings, or more particularly fields, in terms of homomorphisms is less useful. However, we will *still* use ring-homomorphisms on fields, since mapping a field injectively into another field will turn out to be quite useful: we can study how fields *embedd* into one another (this will be called a *field extensions*, which will be defined in Part IV, and an *integral extension* for more general commutative rings, which will be defined in definition 26.1.3).

If a ring does only have 0 and R as two-sided ideals, we have the analogous concept to simple groups

Definition 9.4.14: Simple Rings

Let R be a nonzero ring. Then R is said to be *simple* if its only two-sided ideals are the 0 ideal and itself.

One might think that from here, there will be a similar story as in group theory: A lot of time and effort spent on classifying all rings (and finite rings) given this idea of a simple ring. It turns out though that the classification of finite rings are in fact much much easier: Every finite simple ring is

isomorphic to the ring $M_n(\mathbb{F}_q)$ over a finite field of order q (i.e., intimately related to matrix rings)! In fact, the study of simple rings is the setting of representation theory! Simple rings are covered in chapter 51.

9.4.3 Maximal Ideals

Many times, we might want if an ideals is *as large as possible* in a ring. That is, if I is an ideal, then there does not exist another J such that $I \subseteq J$ unless $J = R$

Definition 9.4.15: Maximal ideal

An ideal M in an arbitrary ring S is called a *maximal ideal* if $M \neq S$ and the only ideals containing M are M and S.

Example 9.4.16: Ring with maximal ideal

Take $\mathbb{Z}$ and $6\mathbb{Z}$. Since $6 = 2(x)$, $6\mathbb{Z} \subseteq 2\mathbb{Z}$. However, since 2 is a prime, we cannot repeat this same trick twice. Thus, $2\mathbb{Z}$ is a maximal ideal. In general, $p\mathbb{Z}$ for prime p is a maximal ideal

All rings have a maximal ring with the exception of a ring with the trivial ring structure:

Example 9.4.17: Ring without maximal ideal

Take any group with a non-maximal group (ex $\mathbb{Q}$) and take the trivial ring structure ($ab = 0$).

The only restriction on a ring that requires it to have a maximal ideal is that $1 \neq 0$. The way we will prove this will require a form of "super-induction". The use of this proof technique requires the axiom of choice. For those who want to have an idea of Zorn's lemma, see appendix A.3, and for those who want to see how it links to the axiom of choice, see appendix A.

Proposition 9.4.18: Ring with $1 \neq 0$ have Maximal ideals

Let R be a non-trivial ring and $I \subsetneq R$ be a proper ideal. Then I is contained in a maximal ideal

***Proof*:**

Since $I \subsetneq R$, $1 \neq 0$), and $1 \notin I$ (or else $I = R$), a maximal ideal can exist. To show that it is the case, we will us Zorn's Lemma (theorem A.2.3). Let $\mathcal{I}$ be the collection of all proper ideals of R containing I, and let it be ordered by inclusion. Then $(\mathcal{I}, \subseteq)$ is a partial order. If e take any chain $\mathcal{C} \subseteq \mathcal{S}$, then

$$J = \bigcup_{A \in \mathcal{C}} A$$

is the ideal which is the upper-bound for $\mathcal{C}$. For this to be the case, J must be an ideal.

1. J is non-empty, since any ideal must contain 0, thus $0 \in J$
2. Take $a, b \in J$ and consider $a - b$. Then for some $A, B \in \mathcal{C}$, $a \in A$ and $b \in B$. Since $\mathcal{C}$ is a chain, $A \subseteq B$ or $B \subseteq A$. Witout loss of generality, let's assume $A \subseteq B$ and say $a, b \in B$ (if

e pick $B \subseteq A$ do $a, b \in A$). Then since B is an ideal, $a - b \in B$, so $a - b \in J$, showing that J is closed under subtraction

3. Take $a \in J$ and consider $r \cdot a$ and $a \cdot r$. Then since $a \in J$, a is in some ideal, let's say $a \in A$. Then $r \cdot a \in A$ and $a \cdot r \in A$, so $r \cdot a, a \cdot r \in J$, showing it's closed uner left and right multiplication

Thus, J is an ideal. It is further a proper ideal. If it ere not, then $1 \in J$, meaning for some ideal A, $1 \in A$. But then $A = R$, showing it is *not* a proper ideal, a contradiction to the definition of J. Thus, J must also be a proper ideal.

Therefore, by Zorn's Lemma, $\mathcal{I}$ must have a maximal element M, that is, if there is an element M' such that $M \subseteq M'$, then it must be that $M' \subseteq M$, so $M = M'$, which fulfills the definition of a maximal ideal, as e sought to show.

Note that we took the union of ideals within the proof. In general, if $I, J \subseteq R$, then $I \cup J$ is not an ideal (consider $2\mathbb{Z} \cup 3\mathbb{Z}$). The reason it worked for this proof is because the ideals are in a chain:

$$I_1 \subseteq I_2 \subseteq \cdots \subseteq I_n \subseteq \cdots$$

It should be pointed out that it is possible to have an infinitely long chain of the form $(x_1) \subsetneq (x_1, x_2) \subsetneq \cdots$ of which the union is not a maximal ideal, hence being maximal is a different condition that such a chain terminating in finite itterations, or even countably-infinite many iterations. This is part of the importance of using Zorn's lemma in the proof.

Since Zorn's Lemma was used, there is no way to computationally figure out what the maximal ideal is by just using this proposition. If a ring is also commutative, we can more easily characterize it with the structure of their quotient ring

Proposition 9.4.19: Maximal Ideals in Commutative Rings

Let R be a commutative ring with $1 \neq 0$. The ideal M is a maximal ideal if and only if the quotient R/M is a field

***Proof*:**
This follow's from the Correspondence Theorem (theorem 9.3.15(4)) and proposition 9.4.10. Both conditions force $M \neq R$: a maximal ideal is proper (definition 9.4.15), and a field is nonzero, while R/M is the zero ring exactly when $1 \in M$, that is, exactly when $M = R$ (proposition 9.4.10(1)). So let $M \neq R$. Then R/M is a nonzero ring, and it is commutative because R is. By theorem 9.3.15(4), applied with $I = M$, the map $J \mapsto J/M$ is an inclusion preserving bijection from the ideals J of R that contain M onto the ideals of R/M, and it sends M to the zero ideal and R to R/M. Hence the only ideals of R containing M are M and R if and only if the only ideals of R/M are (0) and R/M. The first condition says that M is maximal, and by proposition 9.4.10(2), applied to the nonzero commutative ring R/M, the second says that R/M is a field. Thus, M is a maximal ideal if and only if R/M is a field, as we sought to show.

The use of the Correspondence theorem in proposition 9.4.19 can be visualized with such a diagram:

$$\begin{array}{cc} R & R/M \\ | & | \\ M & 0 \end{array}$$

Notice that if R was not commutative, then left ideals are not necessarily right ideals, and so the theorem does not apply: if we pick any one-sided ideal (say a left-ideal), and perform proposition 9.4.18 to show the existence of a maximal left-ideal (and hence, we have a non-empty collection of maximal left-ideals), it is not guarnateed that the set of maximal left-ideals will contain any proper right-ideals[18]. A different approach must be taken to study R/I when R is not commutative and I is a maximal left/right ideal, which will lead to many fruitful results in *Core Representation Theory* [22]. This case will require some more module theory, and so will be left alone for now.

In the commutative case, this let's us study properties of R by studying the field R/M for all maximal ideal M. If R has a single maximal ideal (say $\mathfrak{m}$) then $R/\mathfrak{m}$ is called the *residue field*. An example of a local ring would be $\mathbb{Z}/4\mathbb{Z}$, with single maximal ideal $\{\overline{0}, \overline{2}\}$. Such are called local rings for a reason. They show up intensively in commutative algebra, and will be central in chapter 35.

This last characterization of maximal ideals through quotienting for commutative rings will come to be very useful in the construction of some fields. For example this will be used to construct all finite fields by taking quotient of the ring $\mathbb{Z}[x]$ by maximal ideals. In a more specific case, we will be construction the "extension" of a field k by first defining a polynomial ring $k[x]$, and quotienting it by a maximal ideal $M \subseteq k[x]$. This will be the foundation of *field Theory*, and will be covered in Part IV

Example 9.4.20

1. We have hand-waved a bit before how $p\mathbb{Z}$ is a maximal field. Since $\mathbb{Z}$ is commutative, we can now rigorously state this by noticing that $\mathbb{Z}/p\mathbb{Z}$ is a field
2. The ideal $(2, x)$ is a *maximal* in $\mathbb{Z}[x]$, since $\mathbb{Z}[x]/(2, x) \cong \mathbb{Z}/2\mathbb{Z}$, and $\mathbb{Z}/2\mathbb{Z}$ is a field
3. Let $R = \mathcal{F}([0, 1], \mathbb{R})$ be the ring of all functions from $[0, 1]$ to $\mathbb{R}$, and let M_a be the kernel of evaluation at a ($M_a = \{f \in R | f(a) = 0\}$). Show that M_a is maximal.

Note that a ring can have multiple maximal ideals. For example, $\mathbb{Z} \times \mathbb{Z}$ is a ring, and $I = ((1, 0), (0, 2))$ is an ideal generated by $(1, 0)$ and $(0, 2)$. Then $(\mathbb{Z} \times \mathbb{Z})/I \cong \mathbb{Z}/2\mathbb{Z}$, meaning I is a maximal ideal. Similarly, $J = ((2, 0), (0, 1))$ is an ideal and $(\mathbb{Z} \times \mathbb{Z})/J \cong \mathbb{Z}/2\mathbb{Z}$. Thus, both I and J are maximal. The quotients by two maximal ideals need not be isomorphic: in $\mathbb{Z}$ the ideals (3) and (5) are maximal, and $\mathbb{Z}/3\mathbb{Z} \ncong \mathbb{Z}/5\mathbb{Z}$ since they have different orders.

9.4.4 Prime Ideals

The first definition given of prime numbers is that a number is prime if and only if it's only divisors are 1 and itself, that is the only numbers such that $a|p$ are 1 and p. This definition works well for integers, but does it generalize well when we try to define divisibility over more general rings. This is due to a sneaky "global" assumption when working with primes, namely that an element is prime if *any* factorization that may include the prime element *has* to include the element as a factor. The following example should illustrate how this is not necessarily the case:

[18] Indeed, we can modify example 9.4.12 to see that $M_2(k)/(0)$ is not a field, and hence a counter-example

Example 9.4.21: The Need For Globalness

[The Need For Globalness] Take $R = \mathbb{Z}[2i]$. Then $4 = (-2i)(-2i)$, and $-2i$ can no longer be factor[a]. However, we also have $4 = 2 \cdot 2$, and 2 can no longer factor (which in this case can be verified by taking a few cases). Thus, even though 2 was a factor of 4, we may split 4 differently, showing that there are "local" factorizations.

[a] up to multiplying by a unit, but factorizaiton is only defined up to unt, think $2 \cdot 3 = (-2) \cdot (-3)$

This subtly becomes very important, and shall be explored in depth in chapter 10.

To capture this idea, consider a prime number p. Then p is a prime number and if p divides ab, $a, b \in \mathbb{Z}$, then p divides a or p divides b. For example, if $3|15$, then either $3|3$ or $3|15$. If p was not a prime number, this is not the case: $8|16[= 4 \cdot 4]$, but $8 \nmid 4$ and $8 \nmid 4$. The prime ideals for the integers are the sets that contain all the multiples of a given prime number

Definition 9.4.22: Prime Ideal

Assume R is commutative. An ideal P is called a ***prime ideal*** if $P \neq R$ and whenver the product ab of two element $a, b \in R$ is an element of P, then at least one of the a an b is an element of P.

Since R is commutative, another way of saying the condition is that if A, B where ideals and $AB \subseteq P$, then $A \subseteq P$ or $B \subseteq P$. The non-commutative case does not generalize well, however we discuss a remedy for this case in chapter 50[19].

Example 9.4.23: Prime Ideals

The origins of the idea come from generalizing the notion of primes in $\mathbb{Z}$, so we will do the same. The prime numbers p generate the prime-ideals (p).

Let's say $ab \in (p)$, meaning $ab = rp$ for some $r \in \mathbb{Z}$ (note that $\mathbb{R}$ is commutative so $(p) = Rp$). Since $ab = rp$ that impleis that $p|ab$ (p divides ab): If you think about what it means for a number x to divide y ($x|y$), then that means there exists another number a such that $ax = y$. For example $3|6$, so $2\dot{3} = 6$.

Now, since $p|ab$, then $p|a$ or $p|b$. If $p \nmid a$ and $p \nmid b$, then ab would not have it as a prime number under their factorization, but then $p \nmid ab$, a contradiction. So, $p|a$ or $p|b$. But that would mean $r_a p = a$ or $r_b p = b$ for appropriate r_a or r_b. But then, $a \in (p)$ or $b \in (p)$.

Here's a concrete exmpale. Take $3\mathbb{Z}$, an ideal of $\mathbb{Z}$. (can think of $\varphi : \mathbb{Z} \to \mathbb{Z}/3\mathbb{Z}$, $\varphi(x) = [x]$ to convince yourself it's an ideal). Now let's say $ab \in 3\mathbb{Z}$. That means that $3|ab$, meaning either $3|a$ or $3|b$. In either case, that would imply $a \in 3\mathbb{Z}$ or $b \in 3\mathbb{Z}$, showing that $3\mathbb{Z}$ is a prime ideal. On the other hand, if we have $6\mathbb{Z}$, Then $2 \cdot 3 \in 6\mathbb{Z}$, but $2 \notin 6\mathbb{Z}$ and $3 \notin 6\mathbb{Z}$, meaning $6\mathbb{Z}$ is *not* a prime ideal.

Note that this is an *inclusvie* or, not exlusive. If $p = 2$, and $a = b = 2$, then $2|4$, and both $2|2$ and $2|2$.

Another way I like to think about is is that we already know that if $a \in I$ and $b \in I$, then $ab \in I$. However, it's not clear the converse is true $ab \in I$, $a \in I$ and $b \in I$. This condition is a little too strong: Since $1 \cdot x \in I$ then $1 \in I$, meaning $I = R$. So what if we loosen the condition a bit , and say $ab \in I$ then $a \in I$ *or* $b \in I$. In other words, we can to a limited degree work backwards from *any*

[19] namely, the ideal group is abelian for certain non-abelian

combination of elements $ab \in I$ to find one of them keeps needing to be in I. For example, if $abc \in I$ (say we braketed $(ab)c$) then either $ab \in I$ or $c \in I$. Since $ab \in I$, then either $a \in I$ or $b \in I$. This idea will come back in section 10.1, when we factor elements in an integral domain, and will be the key idea to a couple of proofs[20].

This interpretation shows that a prime element is irreducible (both notions are defined in definition 10.1.5). Let R be an integral domain, $p \in R$ a prime element, and $p = rr'$. Then $p \mid rr'$, so $p \mid r$ or $p \mid r'$. If $r = ps$, then $p = psr'$, and cancelling $p \neq 0$ gives $sr' = 1$, so r' is a unit. Divisibility both ways does not force equality: it only makes r and p associates (definition 10.1.2), as $1 \mid 2$ and $2 \mid 1$ in $\mathbb{R}$ while $1 \neq 2$. If $p \mid r'$ instead, the same argument makes r a unit. Proposition 10.1.7 records this.

Another thought: Take (x) and consider $ab \in (x)$. Then $ab = cx$ for appropriate $c \in R$. Then we no get the question $cx \in (x)$ too. This though is "obvious" since $x \in (x)$. But ab is not obvious. So the "representation" of the value that both ab and cx represents is important: it's a question about hether the constituent components of a represetnation is in there (a or b or c or x)

Here are some more example of prime ideals:

Example 9.4.24: Further Examples of Prime Ideals

1. Take $C([0,1])$, that is, all continuous function to/from $[0,1]$. Let $I \subseteq C([0,1])$ be all polynomials with roots at $\frac{1}{2}$ and $\frac{1}{3}$ ($f(\frac{1}{2}) = f(\frac{1}{3}) = 0$). Is I an ideal? Is it a prime ideal? Hint [a].

2. As an exercise to show that you can no longer "go backards", prove that if R is a commutative ring and P is a prime ideal of R, then R/P is an integral domain. (Hint [b]).

[a] Think about two polynomials with single roots such that when multiplied, you get an element of I
[b] Assume R/P has a zero-divisor

This last example is important enough to be referenced many times, and so we make it a proposition:

Proposition 9.4.25: Prime Ideals And Integral Domains

Assume R is commmutative. Then the ideal P is a prime ideal in R if and only if the quotient ring R/P is an integral domain

***Proof*:**
The quotient ring R/P (proposition 9.3.11) is commutative, since $(a+P)(b+P) = ab+P = ba+P = (b+P)(a+P)$, and its identity is $1+P$. First, $1+P \neq 0+P$ exactly when $1 \notin P$, that is, exactly when $P \neq R$ (proposition 9.4.10(1)). Second, the product $(a+P)(b+P) = ab+P$ is the zero class P exactly when $ab \in P$, and $a+P = P$ exactly when $a \in P$, so R/P has no zero divisors exactly when $ab \in P$ implies $a \in P$ or $b \in P$. Hence R/P is an integral domain (definition 9.1.21) exactly when P is a prime ideal (definition 9.4.22), as claimed.

Corollary 9.4.26: Maximal Ideal Then Prime Ideal

Assume R is commutative. Then every maximal ideal of R is a prime ideal

[20] for example, proposition 10.1.32 and theorem 10.1.30

***Proof*:**
If M is a maximal idea, then by proposition 9.4.19 R/M is a field. A field is an integral domain, so the corollary folllows from proposition 9.4.25

Example 9.4.27

1. The principal ideals generated by (p) where p is prime are both prime and maximal. Not all prime ideals are maximal: (0) is a prime ideal, but not maximal.
2. The ideal (x) is a prime ideal in $\mathbb{Z}[x]$ since $\mathbb{Z}[x]/(x) \cong \mathbb{Z}$, but not maximal since $\mathbb{Z}$ is not a field. Or, you can diretly see that $(x) \subseteq (2, x)$, meaning that (x) is not maximal.

Example 9.4.28: Evaluation At Zero
The ideal (y) of $\mathbb{Q}[x, y] = (\mathbb{Q}[x])[y]$ is a prime ideal. Write each $p \in \mathbb{Q}[x, y]$ as $p = \sum_{j \geq 0} p_j y^j$ with $p_j \in \mathbb{Q}[x]$. By theorem 9.2.4, applied to the identity of $\mathbb{Q}[x]$ and the element $0 \in \mathbb{Q}[x]$, there is a ring homomorphism $\varphi\colon \mathbb{Q}[x, y] \to \mathbb{Q}[x]$ that is the identity on $\mathbb{Q}[x]$ and sends y to 0, namely $\varphi(p) = p_0$, the evaluation at $y = 0$. It is surjective, since $\varphi(f) = f$ for $f \in \mathbb{Q}[x]$. Its kernel consists of the p with $p_0 = 0$, which are exactly the multiples $p = y \sum_{j \geq 1} p_j y^{j-1}$ of y, so $\ker \varphi = (y)$. By theorem 9.3.12(1), $\mathbb{Q}[x, y]/(y) \cong \mathbb{Q}[x]$, which is an integral domain by proposition 9.2.3(3), and so (y) is a prime ideal by proposition 9.4.25.

Exercise 9.4.2

1. Let R, S be rings and $R \times S$ be the product ring. What are the prime ideals of $R \times S$(answer: $R \times P$ and $Q \times S$ for primes P and Q. In general, only one component can be the ideal)
2. Let $a, b \subseteq R$ be ideals. Show that $(a + b)(a \cap b) \subseteq ab$ and $ab \subseteq a \cap b$. Show that if $(a, b) = (1)$, then $a \cap b = ab$.
3. exercise on quotient ideals $(a : b)$
4. Let $f : R \to S$ be a ring homomorphism and $p \subseteq S$ a prime ideal. Show that $f^{-1}(p)$ is a prime ideal. If $m \subseteq S$ is maximal, is $f^{-1}(m)$ maximal? (Consider $R = \mathbb{Z}$ and $S = \mathbb{Q}$)
5. Perhaps, if possible at this stage how if if $a_1, a_2, ..., a_n$ are ideals and $\cap_i a_i$ is contained in the prime ideal p, then p contains one of the a_i, and if $p = \cap_i a_i$, then $p = a_i$ for on of them (shows how prime genelize numbers, so to speak).
6. Notice that we have defined what I^k is. Let's say we started with an ideal J. Is there a rasonable way of defining $\sqrt{J}$? Define $\sqrt{J} = \{a \in R \mid \exists n \in \mathbb{N}_{>0},\ a^n \in J\}$. Show that $\sqrt{J}$ is an ideal.

9.5 Ring of Fractions: Localization

In this section, we will take a moment to discuss how we can take any ring with no zero divisors, and extend the ring to one in which every element has a multiplicative inverse! More generally, given any non zero-divisor element $d \in R$ (where R will have to be commutative), we can construct a ring

R_d which will where $d^{-1} \in R_d$. This concept was applied in the field of *algebraic geometry* for the purposes of looking at a ring "locally". What this means and how to think about this consruction "geometrically" will be discussed much later in section 23.4. In this section, the full generality of this construction is not particularly useful. What's more interesting at the moment is that this gives us a way to add units to our ring!

We will start with a practical example by using $\mathbb{Z}$ to construct $\mathbb{Q}$! Taking $\mathbb{Z}$, we can make an equivalence class

$$(a, b) \sim (c, d) \Leftrightarrow ad = bc$$

where $b, c \neq 0$. Then $[(a, b)]$ represents a fraction $\frac{a}{b}$, with the point of the equivalence relation is to make all fractions with similar divisors be the same:

$$\frac{1}{2} = \frac{2}{4} = \frac{3}{6} = \cdots$$

I will stick with fraction notation for these equivalence relationships. We can see that we can define

$$\frac{a}{b} + \frac{c}{d} = \frac{ad + bc}{bd} \qquad \text{and} \qquad \frac{a}{b} \cdot \frac{c}{d} = \frac{ac}{bd}$$

It should be checked that these operations are independent of representative. With this construction, we can identity $\mathbb{Z}$ with $\left\{\frac{a}{1} | a \in \mathbb{Z}\right\}$ [21], showing how $\mathbb{Z}$ is a sub-ring of $\mathbb{Q}$.

With that intuition, we can ask about general commutative rings R. The problem comes when we allow $d = 0$ or be a zero divisor. Say $d \neq 0$ $bd = 0$. Then:

$$d = \frac{d}{1} = \frac{bd}{b} = \frac{0}{b} = 0$$

We will avoid this by taking a set $R^\times$ which represents all the units of R

Theorem 9.5.1: Ring of Fractions

Let R be a commutative ring R (not necessarily with identity). Let D be any nonempty subset of R that does not contain 0, does not contain any zero-divisors and is closed under multiplication (i.e. $ab \in D$, for every $a, b \in D$)[a]. Then there is a commutative ring Q with 1 such that Q contains R as as a subring and every element of D is a unit in Q. The ring Q has the following additional properties

1. Every element of Q is of the form rd^{-1} for some $r \in R$ nd $d \in D$. In particualr if $D = R - \{0\}$ then Q is a field
2. (uniqueness of Q) The ring Q is the "smallest" ring containing R in which al elements of D become units. That is, if S is any commutative ring with identity and let $\varphi : R \to S$ be any injective ring homomorphism such that $\varphi(d)$ is a unit in S for every $d \in D$. Then there is an injective homomorphism $\Phi : Q \to S$ such that $\Phi|_R = \varphi$. In other words, any ring containing an isomorphic copy of R in which which all the elements of D become units must also contain an isomrophic copy of Q.

[a] such a set is called a *semi-group*

[21] meaning construct a isomorphism

***Proof*:**
We will start like we started with $\mathbb{Z}$. Let $F = \{(r,d)|r \in R, d \in D\}$ (d in the 2nd component because we do not want zero-divisors in the bottom, and we need the denominator to be closed to define multiplication). Then, we define the equivalence relation

$$(r,d) \sim (s,e) \text{ if and only if } re = sd$$

It is easy to show that $\sim$ is an equivalence relation [a]

We commonly denote (r,d) by $\frac{r}{d}$. Now, let

$$Q = \big\{[(a,b)]\big|a \in R, d \in D\big\}$$

be the set of equivalence relations. Note that $\frac{r}{d} = \frac{re}{de}$ for any $e \in D$, as we would expect.

We can define addition and multiplication as

$$\begin{aligned} [(a,b)] + [(c,d)] = [(ad+bc,bd)] \qquad &\Rightarrow \qquad \frac{a}{b} + \frac{c}{d} = \frac{ad+bc}{bd} \\ [(a,b)] \cdot [(c,d)] = [(ac,bd)] \qquad &\Rightarrow \qquad \frac{a}{b} \cdot \frac{c}{d} = \frac{ac}{bd} \end{aligned}$$

Then the following properties need to be checked. I will show that addition is well-defined, and the rest is not hard to show that it follows:

1. The operations are well-defined (not dependent on representatives)

   Proof. We will show addition is well-defined. Let

   $$\frac{a}{b} = \frac{a'}{b'} \ (ab' = a'd) \qquad \frac{c}{d} = \frac{c'}{d'} \ (c'd = cd')$$

   then

   $$\frac{ad+bc}{bd} = \frac{a'd' + b'c'}{b'd'}$$

   which equivalently means:

   $$\begin{aligned} (ad+bc)(b'd') &= adb'd' + bcb'd' && \text{distributivity in } R \\ &= ab'dd' + cd'bb' && \text{commutativity in } R \\ &= ab'dd' + cd'bb' && ab' = a'b,\ cd' = c'd \\ &= (a'd' + b'c')(bd) \end{aligned}$$

   thus, the two are equivalent. A similar procedure works for multiplication □

2. Q is an abliean group under addition, where the aditive identity is $\frac{0}{d}$ for any $d \in D$ and the additive inverse of $\frac{a}{d}$ is $\frac{-a}{d}$
3. Multiplication is associative, distributive, commutative,
4. Q has an identity $\frac{d}{d}$ for any $d \in D$

Next, we show that R can indeed be embedded into Q. Let

$$i : R \to Q \qquad r \mapsto \frac{rd}{d}$$

Since $\frac{rd}{d} = \frac{re}{e}$, this function is independent of choice of d. Since d is closed under multiplication:

$$i(rs) = \frac{rsd}{d} = \frac{rs}{1} = \frac{r}{1}\frac{s}{1} = \frac{rd}{d}\frac{sd}{d} = i(r)i(s)$$

finally, for injectivity of the inclusion, notice that

$$i(r) = 0 \Leftrightarrow \frac{rd}{d} = \frac{0}{d} \Leftrightarrow rd^2 = 0 \Leftrightarrow r = 0$$

meaning the kernel is trivial, and i is injective.

Next, we show that every element $q \in Q$ can be written as rd^{-1}. Since $d = \frac{d}{1}$, then $d^{-1} = \frac{1}{d}$ since $\frac{d}{1}\frac{1}{d} = \frac{1}{1}$. Then by definition of an element in Q, we define an elemnent as $\frac{r}{d} \in Q$, and so we have that $q = rd^{-1}$.

Note that if $D = R - \{0\}$, then every element has a multiplicative inverse, and so that makes Q into a field.

Finally, we must show this extension is unique. To do this, let's say $\varphi : R \to S$ is an injective ring-homomorphism such that $\varphi(d)$ is a unit in S. In this way, S acts as "another" extension of R (since we shows that R can be imbedded into Q). Since $q = rd^{-1}$ for every $q \in Q$, extend φ to Φ by defininging

$$\Phi(rd^{-1}) = \varphi(s)\varphi(d)^{-1}$$

for all $r, d \in R$. Note that $\varphi(d)^{-1}$ is defined since $\varphi(d)$ is a unit in S. This map is well-defined. If we have $rd^{-1} = re^{-1}$, then multiplying around we get $re = rs$, so by the property of ring homomrphisms $\varphi(r)\varphi(e) = \varphi(s)\varphi(d)$ and so

$$\Phi(rd^{-1}) = \varphi(r)\varphi(d)^{-1} = \varphi(s)\varphi(e)^{-1} = \Phi(se^{-1})$$

showing it is indeed well-defined. Checking Φ is a ring homomorphism is strait forward using commutativity of Q.

Last step is to show Φ is injective. There is a sneaky trick you can do to pull this off. Let's say $rd^{-1} \in \ker(\Phi)$. Then that means that $r \in \ker(\varphi)$ since we'd need $\Phi(rd^{-1}) = \varphi(r)\varphi(d)^{-1} = 0$ and $\varphi(d)^{-1}$ cannot be zero since d is a unit. However, $\ker(\varphi)$ is trivial, so $r = 0$, but then $rd^{-1} = 0d^{-1} = 0$, meaning Φ is also injective! Thus, we forced the S to have Q embedded inside of it, meaning *any* extension of R to S would inevitably have Q. This makes Q the smallest extension of R and the unique extension of R.

[a] Reflexivity and symmetry come immediately. For transitivity, combining the two equations appropriately and realise you can factor by $d \in D$, which is not zero or a zero-divisor, which will force the equation you want to be zero, forcing the equivalence for transitivity

We will give Q a name:

Definition 9.5.2: Ring Of Fraction

Let R be a commutative ring, D be the appropriate subset and Q be the extension as in the above theorem. Then

1. The ring Q is called the *ring of fractions* of D with respect to R and is dneoted $D^{-1}R$
2. If R is an integral domain an $D = R - \{0\}$, Q is called the *field of fractions* or *quotient field* of R.

we often want all units of a ring R. We denote all units as $\mathbb{R}^\times$.

Here are some examples of ring of fractions

Example 9.5.3

1. the trivial example would a a field $\mathbb{F}$, which would be it's own field of fractions.
2. the construction we have done at the beginning is a special case of our construction. So, if we take $R = \mathbb{Z}$, and take $D = \mathbb{Z} - \{0\}$, then $D^{-1}\mathbb{Z} = \mathbb{Q}$
3. Let $R = \mathbb{Z}$ and take $D = \{1\}$. Then the quotient ring would be $\mathbb{Z}$ again!
4. $R = \mathbb{Z}$, and take $D = \left\{19, 19^2, ...\right\}$. This is a valid D, since it does not contain 0, does not contain zero divisors, and is closed under multiplicationso what is $D^{-1}\mathbb{Z}$?
5. The ring $2\mathbb{Z}$ is alsmot an integral domain. It doens't have an identity. However, $(R^\times)^{-1}(2\mathbb{Z}) = \mathbb{Q}$ as well! If you think about it, being able to divide will give us the identity, as well as $\frac{1}{2}$, which will produce the rest
6. $Z[p]$ should be elaborated on
7. $\mathbb{F}[x]$ becomes $\mathbb{F}(x)$, that is, elements of the form $\frac{p(x)}{q(x)}$ where $q(x)$ is not the zero-polynomial (Since $\mathbb{F}[x]$ is an integral domain, it's the only value we would need to worry about). Notice the square-brakets became parenthesis. In this way, we might see the motivation to write $\mathbb{Q}(\sqrt{D})$, since we are allowed to divide those values as well! The difference here being that $x, x^2, x^3, ..., x^n, ...$ are all distinct elements, non of them being an element of their original field. However, this same chain doens't appear for $Q(\sqrt{D})$: $\sqrt{D}, \sqrt{D}^2 = D$. This is because $\sqrt{D}$ is not an arbitrary indeterminate value, giving us this relation, similar to what we saw with group-rings.
8. Take $\mathbb{Z}[i]$ and $D = R^\times = R - \{0\}$. Then the ring of fractions is $\mathbb{Q}[i]$! Notice it's not something like $\mathbb{Z}(i)$. This comes down to how multiplication is defined in this ring, which is much more akin to multiplying complex numbers.
9. what is the field of fractions of $\mathbb{Q}[\sqrt{2}]$?
10. What if we have $R = \mathbb{Z}/4\mathbb{Z}$ and $D = \{1, 3\}$?

Theorem 9.5.4: Universal Property Of Field Of Fractions

If $h : R \to F$ is an injective homomorphism from R into a field F, then there exists a unique ring homomorphism $g : Q \to F$ which extends h

***Proof*:**
Use the uniqueness of the extension to show that $\Phi(Q)$ will be in any sub-field.

With the relation $(r, d) \sim (s, e)$ if and only if $u(re - sd) = 0$ for some $u \in D$, the construction of $D^{-1}R$ extends to multiplicative sets D that contain zero-divisors, and $D^{-1}R$ is universal among ring homomorphisms $R \to S$ sending D into $S^\times$. The map $R \to D^{-1}R$ need not be injective, since $r/1 = 0$ whenever $dr = 0$ for some $d \in D$. This is localization, developed in section 23.4.

(Another perspective would be that we are giving a solution to all equations of the form $bx - a = 0$, for $a, b \in R$. Thus, for $R = \mathbb{Z}$, we are doing:

$$\frac{\mathbb{Z}[x_{1/2}, x_{1/3}, ..., x_{1/p}, ...]}{(2x_{1/2} - 1, 3x_{1/3} - 1, ...,)} =: \mathbb{Q}$$

Though this way of looking at it seems more complicated, it fits better with the idea that we are adding relations to $\mathbb{Z}$. In particular, it shows that we are adding all *linear* relations (i.e. solutions) to $\mathbb{Z}$. We will in later section's show how we add non-linear solution.

Note that we construct $\mathbb{Z}$ from $\mathbb{N}$ by adding all monomial-linear polynomials. We then construct $\mathbb{Q}$ by taking all linear equations. We shall further explore in *Commutative Algebra* [20] how to think of non-monic polynomials with non-unit leading coefficients.)

9.5.5 Foreshadowing By taking the "infinite" version of polynomials, we managed to make all the non-zero-divisors become units. In this section, another way of producing using by formally inverting them. These two processes shall seem very different, however they are related, and the connection will be made in chapter 25.

9.5.1 $\mathbb{R}$ Is Not Algebraic over $\mathbb{Q}$

The Grothendieck completion turns the monoid $\mathbb{N}$ into the group $\mathbb{Z}$ (example 7.1.7), the field of fractions turns $\mathbb{Z}$ into $\mathbb{Q}$, and adjoining a root of $x^2 + 1$ turns $\mathbb{R}$ into $\mathbb{C}$ (example 19.2.7). The step from $\mathbb{Q}$ to $\mathbb{R}$ is of a different kind. Adjoining to $\mathbb{Q}$ roots of polynomials, even of all of them, gives only algebraic numbers, and the real algebraic numbers $\overline{\mathbb{Q}}^{\mathbb{R}}$ (section 21.1) form a countable field, since there are countably many polynomials over $\mathbb{Q}$ and each has finitely many roots. As $\mathbb{R}$ is uncountable, it is not reached this way. Its standard constructions, by Dedekind cuts or by Cauchy sequences, use the order or the absolute value of $\mathbb{Q}$ ([23, The Real Numbers]).

Exercise 9.5.1

1. Show that $\mathbb{Q}(\sqrt{2}) = \left\{a + b\sqrt{2} \mid a, b \in \mathbb{Q}\right\}$ is a subfield of $\mathbb{R}$ and that it is the field of fractions of its proper subring $\mathbb{Z}[\sqrt{2}] = \left\{a + b\sqrt{2} \mid a, b \in \mathbb{Z}\right\}$.

9.6 Chinese Remainder Theorem

Let's say we have a ring R and a collection of ideals $I_1, I_2, ..., I_k$. Then given

$$a_1 \bmod I_1, \cdots, a_k \bmod I_k$$

does there exist a $a \in R$ such that

$$a \equiv a_1 \bmod I_1, \cdots, a \equiv a_k \bmod I_k$$

Think about it for a moment before looking at the answer

9.6.1 Taking a moment aking a moment to think about the answer.

The answer depends on the choice of I_i. The reader should have tried this with $R = \mathbb{Z}$ and noticed it is not always possible, for example if $R = \mathbb{Z}$, $a \equiv 1 \bmod 2$, $a \equiv 2 \bmod 4$ does not have a solution.

The Chinese Remainder Theorem (CRT) is a way of finding an to this question. It's name sake most likely comes from a book *Sun Tzu Suan Ching*. It is said that it was originally developed either for accounting purposes or for dividing troops.

Before we get into the actual theorem, we will first explore a direct application of Chinese Remainder Theorem:

Example 9.6.2: Concrete Use
simple form

$$\text{if } gcd(m, n) = 1 \text{ and } 0 \leq a < m, 0 \leq b < n$$

then

$$\exists!\ k,\ 0 \leq k < mn \text{ such that } k \equiv a \bmod m, k \equiv b \bmod n$$

Let's say: $m = 6$, $n = 5$, $a = 4$, $b = 2$. Then $k = 22$.

Proof. We have

$$k \equiv 4 \bmod 6,\ k \equiv 2 \bmod 5$$

so using the classical method, we first find

$$6 \cdot 5 = 30$$

from this, we find $30/6 = 5$ and $30/5 = 6$ to be the values such that and kno that we get the solution by solving the equivalent problem of:

$$k \equiv 5 \cdot 1 \bmod 30,\ k \equiv 6 \cdot 1 \bmod 30$$

meaning the solution is $(4 \cdot 5 \cdot 5) + (2 \cdot 6 \cdot 6) =$ □

When generalizing this result, we can no longer ask for numbers to be co-prime. The equivalent concept in rings are co-maximal ideals [22]

[22] why not co-prime ideals? We will show how prime and maximal ideals will match in special rings in section 50.2, here we would usually apply such a result. However, we stay general since we can prove it in more general contexts

Definition 9.6.3: Comaximal Ideals and Elements

The ideals A and B of the ring R are *comaximal* if $A + B = (1)$. When R is commutative, two elements $a, b \in R$ are *comaximal* (also called *strictly coprime*) if the ideals (a) and (b) are comaximal, that is, if $(a, b) = (1)$. Equivalently, there exist $x, y \in R$ with $xa + yb = 1$.

The model case is $\mathbb{Z}$. If $a, b \in \mathbb{Z}$ share no prime factor, the Extended Euclidean Algorithm (theorem 0.2.10) provides $x, y \in \mathbb{Z}$ with $xa+yb = 1$, so $1 \in (a)+(b)$ and $(a)+(b) = \mathbb{Z}$ by proposition 9.4.10. For integers, "coprime" and "comaximal" are therefore the same condition. In a general commutative ring they separate, and the Chinese Remainder Theorem needs the stronger of the two.

9.6.4 Convention: Coprime Versus Strictly Coprime Call a, b in a commutative ring R *coprime* if their only common divisors are units. Comaximal elements are coprime: if $d|a$, $d|b$ and $xa + yb = 1$, then $d|1$. The converse fails (example 9.6.5), so the ideas need distinct terminology. Two nomenclatures are common:

- Atiyah and Macdonald call ideals with $A + B = (1)$ *coprime* (or comaximal), so for them the ideal-theoretic is the basic idea.
- Milne, in his treatment of Hensel's lemma for étale cohomology, keeps *coprime* for the "no common factor" notion over a field and writes *strictly coprime* for $(f, g) = (1)$ over a ring.

Thus ,we say *comaximal*, which has only one meaning.

Example 9.6.5: Coprime But Not Comaximal

In $\mathbb{Z}[x]$, the elements 2 and x are coprime. If $d|2$, then by proposition 9.2.3 d is a constant, so $d \in \{\pm 1, \pm 2\}$, and $\pm 2 \nmid x$. Hence only the units ± 1 divide both. They are not comaximal, since $(2, x)$ is the proper ideal of polynomials with even constant term (example 9.4.6).

The Chinese Remainder map $\mathbb{Z}[x] \to \mathbb{Z}[x]/(2) \times \mathbb{Z}[x]/(x)$ is therefore not surjective. A preimage $f(x)$ of $(1, 0)$ would satisfy $f(x) \in 1 + (2)$ and $f(x) \in (x)$, so its constant term $f(0)$ would be both odd and 0. The kernel $(2) \cap (x) = (2x)$ is still the product of the two ideals. The conclusion of lemma 9.6.9 can hold without its hypothesis, but surjectivity cannot.

The most useful test for comaximality in a polynomial ring involves a linear factor.

Proposition 9.6.6: Comaximality With A Linear Polynomial

Let B be a commutative ring, $a \in B$ and $f(x) \in B[x]$. Then

1. $(f(x), x - a) = (f(a), x - a)$ as ideals of $B[x]$
2. $f(x)$ and $x - a$ are comaximal if and only if $f(a) \in B^\times$
3. if B is an integral domain, $f(x)$ and $x - a$ are coprime if and only if $f(a) \neq 0$

***Proof*:**
For (1), each $k \geq 1$ gives $x^k - a^k = (x-a)(x^{k-1} + ax^{k-2} + \cdots + a^{k-1})$. Writing $f(x) = \sum_k c_k x^k$, we get

$$f(x) - f(a) = \sum_k c_k(x^k - a^k) = (x-a)\, q(x)$$

for some $q(x) \in B[x]$. Hence $f(a) = f(x) - (x-a)q(x) \in (f(x), x-a)$ and $f(x) = f(a) + (x-a)q(x) \in (f(a), x-a)$, so the two ideals coincide.

For (2), if $f(a) \in B^\times$ then $1 \in (f(a), x-a) = (f(x), x-a)$. Conversely, suppose $1 = u(x)f(x) + v(x)(x-a)$. Applying the evaluation homomorphism ev_a (definition 9.2.5), which fixes B, gives $1 = u(a)f(a)$, so $f(a) \in B^\times$.

For (3), degrees add in $B[x]$ (proposition 9.2.3). So a unit of $B[x]$ has degree 0, and $x-a$ is not a unit. If $f(a) = 0$, the identity from (1) reads $f(x) = (x-a)q(x)$, and $x-a$ is a common non-unit divisor. Conversely, let d be a common non-unit divisor and write $x - a = d\,e$, so $\deg d + \deg e = 1$. If $\deg d = 0$, then $d = c$ is a constant, and comparing leading coefficients in $x - a = c\,e$ shows $c \in B^\times$, contradicting that d is not a unit. So $\deg e = 0$, $e = c$ is a constant, the same comparison gives $c \in B^\times$, and $d = c^{-1}(x-a)$. Then $x - a \big| f(x)$, and applying ev_a gives $f(a) = 0$.

Example 9.6.7: Nonzero Is Not Enough
Take $B = \mathbb{Z}$, $f(x) = x$ and $a = 2$. Then $f(2) = 2 \neq 0$, so x and $x-2$ are coprime by proposition 9.6.6(3). But $2 \notin \mathbb{Z}^\times$, so they are not comaximal. Indeed $(x, x-2) = (2, x-2) = (2, x)$, the ideal of example 9.6.5. Over $\mathbb{Q}$, the same polynomials are comaximal, since $1 = \frac{1}{2}x - \frac{1}{2}(x-2)$. Over a field every nonzero element is a unit, so parts (2) and (3) give the same condition.

9.6.8 Foreshadowing: Hensel's Lemma The two notions meet in Hensel's lemma for a local ring A with maximal ideal $\mathfrak{m}$ and residue field $k = A/\mathfrak{m}$. Its hypothesis is a factorization $\bar{f} = g_0 h_0$ with g_0, h_0 coprime in $k[x]$, the field notion. Its conclusion is a lift $f = gh$ in $A[x]$ with g, h comaximal, the ring notion. The bridge is that for g monic, g and h are comaximal in $A[x]$ exactly when $\bar{g}$ and $\bar{h}$ are coprime in $k[x]$. Its proof applies Nakayama's lemma to the finite A-module $A[x]/(g,h)$, and it belongs with the commutative algebra of local rings.

Lemma 9.6.9: Characterizing Products of Coprime Ideals

Let $I_1, I_2, ..., I_n$ be pairwise comaximal ideals. Then:

$$\bigcap_{i=1}^{n} I_i = \prod_{i=1}^{n} I_i$$

***Proof*:**
We shall do induction so consider first when $n = 2$ so that $I, J \subseteq R$ such that $I + J = (1)$. It is always the case that $IJ \subseteq I \cap J$ so we have to show that $I \cap J \subseteq IJ$ when $I + J = (1)$. Given $I + J = (1)$, there exists $a \in I$, $b \in J$, such that $a + b = 1$. Now, if $r \in I \cap J$, then

$$r = r \cdot 1 = r(a+b) = ra + rb \in IJ$$

Since $r \in J$ and $a \in I$, $ra \in IJ$, an similarly $rb \in IJ$ since $r \in I$ and $b \in J$.

Then the inductive step follows immediately.

Lemma 9.6.10: Recursive Comaximal Of Products

Let $I_1, I_2, ..., I_n \subseteq R$ be ideals such that $I_i + I_n = (1)$ for all $i \in \{1, ..., n-1\}$. Then $(I \cdots I_{n-1}) + I_n = (1)$

***Proof*:**
By assumption, there exists $a_i \in I_k$ and $1 - a_k \in I_i$ such that

$$(1 - a_1) \cdots (1 - a_{n-1}) \in I_1 \cdots I_{n-1}$$

And

$$1 - (1 - a_1) \cdots (1 - a_{n-1}) \in I_n$$

since it is a comination of the elements $a_1, a_2, ..., a_{n-1} \in I_n$

Theorem 9.6.11: Chinese Remainder Theorem

Let $A_1, A_2, ..., A_k$ be ideals in R. The map

$$R \to R/A_1 \times \cdots \times R/A_k \qquad \text{defined by} \qquad r \mapsto (r + A_1, \cdots, r + A_k)$$

is a ring homomorphism with kernel $A_1 \cap A_2 \cap \cdots \cap A_k$. If for each $i, j \in \{1, 2, ..., k\}$ with $i \neq j$ the ideals A_i and A_j are comaximal, then this map is surjective and $A_1 \cap \cdots \cap A_k = A_1 A_2 \cdots A_k$, so

$$R/(A_1 A_2 \cdots A_k) = R/(A_1 \cap A_2 \cap \cdots \cap A_k) \cong R/A_1 \times R/A_2 \times \cdots \times R/A_k$$

***Proof*:**
Take

$$R \to \bigoplus_{i=1}^{n} R/A_i \qquad a \mapsto (a \bmod A_1, ..., a \bmod A_n)$$

Then this is easily checked to be a ring homomorphism with kernel $A = \bigcap_i A_i$. Assuming now the ideals are comaximal, we shall show surjectivity. We shall do a proof by induction. If $n = 1$ where done, so let for let's say

$$R/(A_1 \cdots A_{n-1}) \cong R/A_1 \times \cdots \times R/A_{n-1}$$

Then by lemma 9.6.10, $(A_1 \cdots A_{n-1}) + A_n = (1)$, and hence this is reduced to two ideals. By comaximality there exists $a_1 \in A_1$, $a_2 \in A_2 \cdots A_{n-1}$ such that $1 = a_1 + a_2$. Then writting

$$x = x_2 a_1 + x_1 a_2$$

we get that $x \equiv x_1 \bmod A_1$ and $x \equiv x_2 \bmod A_2 \cdots A_n$. But then $x \mapsto (x_1 \bmod A_1, x_2 \bmod A_2 A_3 \cdots A_{n-1})$, completing the proof.

A useful consequence to remember is that if there are elements $r_i \in R$ where $r_i \bmod A_i$, then there exists an element a

$$a \equiv r_i \bmod A_i$$

The ability to solve such a system mod A_i is sometimes called the *Weak Approximation Theorem.*

Corollary 9.6.12: Chinese Remainder Theorem For Integers

Let $R = \mathbb{Z}$ $a_1, a_2, ..., a_n \in \mathbb{Z}$ be elements such that $\gcd(a_i, a_j) = 1$ for all $i \neq j$. Then if $a = a_1 \cdots a_n$, The function

$$\varphi : \mathbb{Z}/a\mathbb{Z} \to \mathbb{Z}/a_1\mathbb{Z} \times \cdots \times \mathbb{Z}/a_k\mathbb{Z}$$

given in the natural way is an isomorphism

***Proof*:**
This is an immediate consequene of the chinese remainder theorem since $\gcd(a, b) = 1$ if and only if $(a, b) = (a) + (b) = 1$

Exercise 9.6.1

1. Show that if $P + Q = R$, then for any $n, m > 0$, $P^n + Q^m = R$. Conclude the CRT can be generalized to ideals of the form $A_1^{n_1}, ..., A_k^{n_k}$.

9.7⋆ Monoidal Objects

⋆ *Optional. This section is an aside; nothing later in the book depends on it.*

Maybe have this here to be able to introduce R-algebras as the monoidal objects in the R-**Mod** Category?

10

Exploring Integral Domains: Factorization and Valuation

This chapter will assume basic number theory knowledge from the preliminary chapter (section 0.2).

Integral domains are a huge overarching category of rings, being in a meaningful way the generalization of integers. That they have no zero-divisors makes it possible to partially invert elements (by proposition 9.1.24). There are many different consequences of this result especially in the right specializations, for example divisibility, size, and even the euclidean algorithm shall all be definable on the appropriate integral domains[1]. These topics all interact greatly with each other and there is no linear way of addressing these ideas. However, books are inherently written with a total ordering and we must learn content in some order, and hence this chapter has been written with the idea of exploration the notion of divisibility (which the reader can think of the best that can be done to check invertibility if an element is not a unit). As this exploration naturally progresses, all other pertinent notions about integral domains shall become natural questions and will be answered.

The following diagram sums up the results of this chapter:

[1]There is also a more geometric interpretation, which is that integral domains will correspond to "irreducible" geometric objects (think of how $R \times S$ is no longer integral. This idea is explored in section 32.3




Figure 10.1: Image form Alufi's textbook

At the end of this chapter, we shall explore how these abstract notions were in fact developed to solve number-theoretic problems. We shall see our first example of finding the solution to a Diophantine equation, namely

$$x^2 + y^2 = p$$

In other words, which primes can be written as sums of two squares. As equations are the fundamental way in which we determine the properties of objects, this will be the first glimpse into the properties of prime numbers. This exploration is greatly generalized in section 50.4.6.

10.0.1 Note Some results in this chapter apply beyond integral domains. It will be made extra-clear when that is.

Goal

In fields, every element has an inverse. This is not so for general rings, as we have seen when studying units and zero-divisors. If not every element is a unit, there is a new idea that is introduced when learning some basic number theory: *factorization*. In this way, we can "decompose" an element into some basic building blocks. This idea of factorizing is one the reader is already familiar with: any number $x \in \mathbb{Z}$ can be factored, even uniquely, into prime numbers:

$$x = up_1^{k_1} p_2^{k_2} \cdots p_n^{k_n}$$

where $u \in \{1, -1\}$ and each p_i is a prime. Is there a generelizable notion of being factorizable in more general rings? Is this idea related to prime ideals? Some types of rings do admit an idea of factorization, or even some stronger conditions (like the euclidean algorithm being well-defined, or the factorization being unique), while other rings have a weaker condition (like the factorization not being unique or even existing). The first major focus of this chapter are these ideas.

The overarching idea in factorization is centered around the idea of divisibility like we have seen in $\mathbb{Z}$. For example:

$$2|8 \qquad 32|17728 \qquad \text{but} \qquad 3 \nmid 8 \qquad 5 \nmid 7$$

When an element is divisible, let's say $2|8$, then there exists some $x \in \mathbb{Z}$ such that $2x = 8$, that is, 8 got subdivided into other elements. In this way, factorization can be thought of as a "partial division" or "partial inverse" condition. This idea will be at the heart of our following exploration.

The result will give 3 new classes of rings and develop on 2 previously mentioned classes or rings which are very often studied.

1. *Atomic Domains* (or Domains with Factorization) are will be rings in which element can be factored into elements that can no longer be factored (they will be called irreducible elements), though not necessarily uniquely
2. *Noetherian domains* are similar to Unique Factorization domain as in every element can be factorzied, but it need not be unique. The reader may recall these as rings in which every ideal may be finitely generated.
3. *Unique Factorization Domains* (UFDs) will allow for every element to have a unique factorization, and let's us define the notion of there being a greatest common divisor between elements.
4. *Principal Ideal Domains* (PIDs) will be stronger than PIDs in that they allow for unique factorization and will have a more rigid structure. The reader may recall these as rings in which every ideal may be generated by a single element.
5. *Euclidean Domains* will have the property of the euclidean division algorithm applying to them to quickly find the greatest common divisor. These will allow for algorithmic decomposition of elements into prime elements.

Since factorization is heavily inspired by the properties of $\mathbb{Z}$, all rings in this chapter will be *integral domains* unless specified otherwise.

10.1 Factorization

We will first define more rigorously the notion of elements being factorizable

Definition 10.1.1: Divisibility

Let R be a commutative ring and $a, b \in R$ be elements of R. Then we say that a *divides* b (or b *is divisible by* a) if there exists an element c such that

$$ca = b$$

Equivalently, $ca = b$ if and only if $b \in (a)$. Notationally, we write $a|b$ to mean "a divides b".

If R is not commutative, one can define left and right divisibility separately, but this book does not treat the non-commutative case. When a divides b, one also says that b is a *multiple* of a. This terminology is used much less often.

The equivalent condition with ideals is a very insightful way of understanding divisibility. Here are the four equivalent conditions of divisibility for ease of reference:

1. $b|a$ if and only if

2. $a = bb'$ if and only if
3. $a \in (b)$ if and only if
4. $(a) \subseteq (b)$

It is unfortunate that the notation $b|a$ stuck, since you will have to swap at some point the order of the a and the b given that it's read "b divides a" and not "a is divided by b". It's a matter of getting used to.

The notation for divisibility using ideals is particularly insightful here. Notice that if $u \in R$ is a unit, then for any element $r \in R$ $(r) = (ur)$. Both inclusion are easy and should be proven before continuing to read. Because of this property, it is immediate that $a\big|b$ if and only if $a\big|ub$, that is, if an element is divided (or not divided) by another, then multiplying it by a unit let's it remain divisible (or not divisible) by the other element. This is in fact something the reader is already is familiar with. Notice that $6 = -1 \cdot -6$. Then $2\big|6$, and $2\big|-6$, but also $5 \nmid 6$ and $5 \nmid -6$. Thus, when we think of divisibility, it is important to think of a number being divisible "up to a unit":

Definition 10.1.2: Associative

Let R be a commutative ring and let $a, b \in R$ be two elements. Then we say that a and b are *associates* if the ideals generated by a and b are equal, that is:

$$(a) = (b)$$

It is important to check that this is equivalent to saying that a and b are associates if $a\big|b$ and $b\big|a$, showing how this links to divisibility. Notice that in the previous definition, R was not an integral domain, but just a commutative ring, which allows zero-divisors. This in fact breaks the intuition of associativity we just showed:

Example 10.1.3: associativity in non-integral domains

Let $R = \mathbb{Z}/6\mathbb{Z}$. Then $(\overline{2}) = (\overline{4})$, since

$$(\overline{2}) = \{\overline{2}, \overline{4}, \overline{0}\} = \{\overline{4}, \overline{2}, \overline{0}\} = (4)$$

Furthermore, $\overline{4} = \overline{2} \cdot \overline{2}$ but $\overline{2}$ is *not* a unit.

For this reason, restricting to integral domains let's us keep this "up to a unit" intuition for for divisibility using ideals:

Proposition 10.1.4: Associativity in Integral Domains

Let R be an integral domain. Then a and b are associates if and only if $a = ub$ for some unit $u \in R$

***Proof*:**

Let $(a) = (b)$, so that for some $r, s \in R$, $ra = b$ and $a = sb$. If $a = 0$, then $b = ra = 0$ and $a = 1 \cdot b$. Otherwise

$$sra = sb = a$$

and cancelling a (proposition 9.1.24) gives $sr = 1$, so s is a unit and $a = sb$.

Conversely, if $a = ub$ for a unit $u \in R$, then $(a) \subseteq (b)$ since $u \cdot b = a$, and $(b) \subseteq (a)$ since $u^{-1} \cdot a = b$.

The conclusion of proposition 10.1.4 can still hold in a ring with zero divisors. In example 10.1.3, the units of $\mathbb{Z}/6\mathbb{Z}$ are $\overline{1}$ and $\overline{5}$. The principal ideals of $\mathbb{Z}/6\mathbb{Z}$ are $(\overline{0}) = \{\overline{0}\}$, $(\overline{3}) = \{\overline{0}, \overline{3}\}$, $(\overline{2}) = (\overline{4}) = \{\overline{0}, \overline{2}, \overline{4}\}$ and $(\overline{1}) = (\overline{5}) = \mathbb{Z}/6\mathbb{Z}$, so the only distinct associates are $\overline{1}, \overline{5}$ and $\overline{2}, \overline{4}$, and $\overline{5} = \overline{5} \cdot \overline{1}$ and $\overline{4} = \overline{5} \cdot \overline{2}$ differ from their partners by the unit $\overline{5}$. Most work on divisibility in rings takes place in integral domains, where the cancellation property holds, and this book restricts to integral domains as well.

With a notion of divisibility up to unit established, we can start thinking of what are the building blocks, the "fundamental elements", into which we will factorize an element:

Definition 10.1.5: Irreducible and Prime Elements

Let R be an intergral domain

1. Let $r \in R$ be a nonzero element that is not a unit. Then r is called *irreducible* in R if whenever $r = ab$, at least one of a or b must be a unit in R. Otherwise, r is said to be *reducible*.

2. The nonzero element $p \in R$ is called *prime* in R if the ideal (p) generated by p is a prime ideal. In other words, a nonzero element p is a prime if it is not a unit and whenver $p|ab$ for any $a, b \in R$ then either $p|a$ or $p|b$.

Example 10.1.6: Irreducible and Prime elements

Let $R = \mathbb{Z}$, and take $6 \in \mathbb{Z}$. Then we can see that $2 \cdot 3 = 6$. Since 2 and 3 are both not units, that means that 6 is a reducible element in $\mathbb{Z}$. On the other hand, 2 and 3 are not reducible elements. If there existed a a, b such that $2 = ab$, then by our knowledge that 2 is a prime number (or by some elementary number theory argument), the only number that divide it are 1 and 2, so it must be that either

$$1 \cdot 2 = 2 \quad \text{or} \quad -1 \cdot -2 = 2$$

In both cases, a is a unit, and so 2 is irreducible (similarly for 3). Furthermore, 2 and -2 are associates, since $2 = -1 \cdot -2$, i.e., the differ by a unit. in $\mathbb{Z}$, every n are associates to it's negative $-n$.

As pointed out in example 9.4.23, 2 is also a prime element since (2) is a prime ideal. In fact, in the previous exercise, we used the fact that 2 is a prime integer (which corresponds to the prime ideals of $\mathbb{Z}$) in order to show it's irreducible. Though 2 is both an irreducible and a prime element in $\mathbb{Z}$, it need not be the case in general integral domains that an element is both!

As an example, take $\mathbb{F}[x]$ to be the polynomials over a field, and take $F_{0x} \subseteq \mathbb{F}[x]$ to be all the polynomials such that the coefficient of x is zero. As an example of elements in F_{0x}:

$$ax^3 + b \in F_{0x} \qquad cx^3 + dx \notin F_{0x} \qquad \forall a, b, c, d \in \mathbb{F}$$

It is easy to check that F_{0x} is an integral domain (as you should check), and so we can try to find irreducible and prime elements. Take x^6. It has two factorizations: $x^6 = x^2x^2x^2$ and $x^6 = x^3x^3$. The elements x^2 and x^3 are irreducible, but not prime.

To show x^2 and x^3 are irreducible, let's say

$$x^2 = p(x)q(x)$$

then since we are working with polynomials over an integral domain, by proposition 9.2.3:

$$\deg(x^2) = \deg(p(x)) + \deg(q(x))$$

meaning $2 = \deg(p(x)) + \deg(q(x))$. Since both $p(x)$ and $q(x)$ cannot be one (since $ax \notin F_{0x}$, for all $a \in \mathbb{F}$) then one of them has to be of degree zero, but since x^2 is monic this implies it must be 1, meaning it's a unit, meaning x^2 is irreducible. Similarly for x^3. Notice that this means that x^6 had two decompositions into irreducible factors, meaning the decomposition was not unique.

Now, take (x^2), i.e. the ideal generated by x^2. Notice that $(x^3)(x^3) \in (x^2)$ because $x^4 \cdot x^2 \in (x^2)$. However, $x^3 \notin (x^2)$. If it were, then there would exist a polynomal $p(x)$ such that $p(x)x^2 = x^3$. By the degree formula, $p(x)$ would have to be of degree 1. However, no degree 1 polynomial exists in F_{0x}. Therefore, (x^2) is not prime! This harkens back to prime ideals (definition 9.4.22), where being prime in some way means we can work backwards. This "working backwards" let's us guarantee we decompose our number into unique elements, as we will soon see.

Though not all irreducible elements are prime, the converse is true, that is, being "globally divisible"‘ is a strong enough condition that it guarantee's irreducibility:

Proposition 10.1.7: Prime Then Irreducible In Integral Domain

Let R be an integral domain. Then prime elements in R are always irreducible

***Proof*:**
Supose $(p) \subseteq R$ is a nonzero prime ideal, and that $p = ab$. Since (p) is a prime ideal, then either $a \in (p)$ or $b \in (p)$. If $b \in (p)$. Then $b = rp$ for some $r \in R$, and if $a \in (p)$ then $a = pr$ for some $r \in R$. Without loss of generality, let's say $a \in (p)$. Then

$$p = ab = prb$$

and since R is an integral domain, the cancellation property holds (proposition 9.1.24), and we get

$$1 = rb$$

implying r, b are units, and so b is a unit. The same argument applies if we chose b. Thus, p is irreducible.

Thus, being prime is stronger than being an irreducible. The natural question to ask now is whether all elements in an integral domain can be decomposed into irreducible or prime factors (if it is factored into prime factors, then automatically it is factored into irreducible factors). It might already be clear that some Integral domains we have explored have this property (ex. $\mathbb{Z}$, and if you are familiar with some manipulation of polynomials, then $\mathbb{F}[x]$). This is however not the case for all integral domains:

Example 10.1.8: Domain with no Factorization

1. Let $R = \mathbb{Z} + x\mathbb{Q}[x]$ be the polynomials with rational coefficients and integer constant term. It is closed under addition, negation and multiplication and contains 1, so it is a subring of $\mathbb{Q}[x]$ (corollary 9.1.7), hence an integral domain. Its units are ± 1: if $fg = 1$, then f and g have degree 0, so they are integers. The element x has no factorization into irreducibles. In

a product $x = f_1 f_2 \cdots f_k$ of elements of R, degrees add, so exactly one factor has degree 1 and the others are nonzero integers. The factor of degree 1 is $a + qx$ with $a \in \mathbb{Z}$ and $q \in \mathbb{Q}$, and comparing constant terms gives $a = 0$. But $qx = 2 \cdot \frac{q}{2}x$, where neither 2 nor $\frac{q}{2}x$ is a unit, so qx is not irreducible.

2. Let $\overline{\mathbb{Z}} \subseteq \mathbb{C}$ be the set of *algebraic integers*: the $r \in \mathbb{C}$ with

$$a_0 + a_1 r + a_2 r^2 + \cdots + r^n = 0$$

for some $a_0, \ldots, a_{n-1} \in \mathbb{Z}$, that is, the roots of monic polynomials with integer coefficients. It is studied at length in chapter 50. That $\overline{\mathbb{Z}}$ is closed under addition and multiplication is a theorem about integral extensions, corollary 26.1.6, and it is not proved here. Granting it, $\overline{\mathbb{Z}}$ is a subring of $\mathbb{C}$, hence an integral domain. It is not a field: $2 \in \overline{\mathbb{Z}}$, but $1/2 \notin \overline{\mathbb{Z}}$, since multiplying $(1/2)^n + a_{n-1}(1/2)^{n-1} + \cdots + a_0 = 0$ by 2^n gives $1 = -2(a_{n-1} + 2a_{n-2} + \cdots + 2^{n-1}a_0)$, which is impossible.

It has no irreducible elements at all. Let $r \in \overline{\mathbb{Z}}$ be nonzero and not a unit, and let $\sqrt{r} \in \mathbb{C}$ be a square root of r (write $r = \rho e^{i\theta}$ and take $\sqrt{\rho}\, e^{i\theta/2}$). If $f(r) = 0$ with f monic in $\mathbb{Z}[x]$, then $f(y^2)$ is monic and vanishes at $y = \sqrt{r}$, so $\sqrt{r} \in \overline{\mathbb{Z}}$. It is not a unit, since $1/\sqrt{r} \in \overline{\mathbb{Z}}$ would give $1/r = (1/\sqrt{r})^2 \in \overline{\mathbb{Z}}$. So $r = \sqrt{r} \cdot \sqrt{r}$ is a product of two non-units and is not irreducible. In particular 2 has no factorization into irreducibles.

For this reason, we must define a special subclass of integral domains which do admit a factorization into irreducibles for every element:

Definition 10.1.9: Atomic Domains

Let R be an integral domain. Then R is an *atomic domain* (or *domain with factorization*) if for every non-unit nonzero element $r \in R$, there exists irreducible elements $q_1, q_2, ..., q_n$ such that

$$r = q_1 q_2 \cdots q_n$$

that is, every element has a *factorization* (or *decomposition*) into irreducible

The name atomic is due to every element being decomposable into element that can no longer be subdivided, similar to atoms, where the word atom comes from the Greek *atomos* meaning "not cuttable". Note that the q_i's need not be distinct (for example, we will show that $\mathbb{Z}$ is an atomic domain, and that $4 = 2 \cdot 2$). Usually, we are more interested in domains where the factorization into irreducible elements is unique:

Definition 10.1.10: Unique Factorization Domain (UFD)

Let R be an integral domain. Then R is a *Unique Factorization Domain* (commonly abbreviated to UFD) if for every non-unit nonzero element $r \in R$, there exists irreducible elements $q_1, q_2, ..., q_n$ and a unit u such that

$$r = uq_1q_2 \cdots q_n$$

and if there is another set of irreducible element $q_1', q_2', ..., q_m'$ and a unit u' such that $r = u'q_1'q_2' \cdots q_m'$, then $n = m$, and after some reshuffling the factors agree up to units (i.e. they are associates), that is, for a permutation σ of $\{1, \ldots, n\}$ and units $u_1, \ldots, u_n \in R$

$$q'_{\sigma(i)} = u_i q_i \qquad \text{for } 1 \leq i \leq n$$

The following corollary is stated for the sake of reference:

Corollary 10.1.11: Unique Factorization Domain ⇒ Atomic Domain

Let R be a Unique Factorization Domain. Then R is an Atomic domain

***Proof*:**
By definition, every element in a Unique Factorization Domain has a factorization into irreducibles, and so is an Atomic Domain

Note that "unique" means unique up to unit, as we pointed out earlier. The factorization in both definitions could have had the unit dropped and just have been written $r = q_1, q_2, ..., q_n$ since it is a the result is an associate to $u^{-1}r$, and so it is harmless to drop the unit. However, I chose to keep the unit in the definition since it may lead to certain unfortunate mistakes when factoring concrete elements.

Example 10.1.12: Unique Factorization Domains

1. Every field is trivially a Unique Factorization Domain, since every nonzero element is a unit, so there are no elements for which the two properties must be verified. In some textbooks, fields are purposefully omitted as Unique Factorization Domains to omit mentioning them as exceptions in proofs. They are still considered Unique Factorization Domains in this book since they fit well in the diagram presented at the beginning of this chapter. However, in a sense, this means that in a field there is no "unique factorization", or at least it's vacuously true that all elements can be uniquely factorized since no nonzero elements are non-units.

2. As we saw in example 11.2.5, $F_{0x} \subseteq \mathbb{F}[x]$ which has x coefficient of 0 is not a Unique Factorization Domain. We saw that x^2 and x^3 are irreducible. If we take x^6, then has two factorizations: $x^6 = x^2x^2x^2$ and $x^6 = x^3x^3$, and hence the factorization is not unique.

3. The ring $\mathbb{Z}[2i]$ is *not* a Unique Factorization Domain. $4 = 2 \cdot 2 = ((-2i) \cdot 2i)$. The elements 2 and $2i$ are irreducible, but not associates, since $2 = 2 \cdot i$, but $i \notin \mathbb{Z}[2i]$. They are furthermore not prime, since $\mathbb{Z}[2i]/(2i) \cong \mathbb{Z}/4\mathbb{Z}$ which is not an integral domain (see proposition 9.4.25)

4. In the ring $\mathbb{Z}[i]$, 2 and $2i$ *are* associates. We have $i \in \mathbb{Z}[i]$, and $i \cdot i^3 = 1$ showing that i is a

unit, and hence 2 and $2i$ are indeed associated. $\mathbb{Z}[i]$ is also a Unique Factorization Domain (section 10.3).

5. If R is a UFD, then $R[x]$ is a UFD (chapter 11). Note how this contrasts with PID's ($\mathbb{Z}$ is a PID but $\mathbb{Z}[x]$ is not, see example 9.4.6(3)).

All of these are examples of Unique Factorization Domains. Atomic Domains which are not Unique Factorization Domains are rather difficult to find. Fortunately, there is an easy criterion that allows us to find (a subset of) common atomic domains

10.1.1 Example of Atomic Domains: Noetherian Domains

The goal of this section is to show that Noetherian domains are atomic domains, and that there exists noetherian domains which are not Unique Factorization Domain's. Let's first remember the definition of a Noetherian Domain, or more generally a Noetherian ring:

Definition 10.1.13: Noetherian Rings

Let R be ring. Then if every ideal $I \subseteq R$ is finitely generated, then R is called a *Noetherian Ring*. If R is an integral domain, we call R a *Noetherian Domain*

Most results that will be presented apply to Noetherian rings in general, and so we will work with Noetherian rings. The first thing to show is how to relate Noetherian rings to the idea of factorization. Emmy Noether introduced the following condition in 1921 [84], and it characterizes Noetherian rings:

Proposition 10.1.14: Ascending Chain Condition

Let R be a commutative ring. The following are equivalent:

1. R is a Noetherian ring
2. for every chain of ascending ideals of R

$$I_1 \subseteq I_2 \subseteq \cdots \subseteq I_n \subseteq \cdots$$

there exists an number m such that for all $n > m$, $I_n = I_{n+1} = \cdots$

3. Every nonempty family of ideals of R partially ordered by inclusion has a maximal element

For a noncommutative ring the same proof shows that every left ideal is finitely generated exactly when the left ideals satisfy (2) and (3), and likewise on the right. The left and right conditions can differ.

***Proof*:**

(1) $\Rightarrow$ (2) Let R be a Noetherian ring. If $I_1 = R$ we are done, so assume I_1 is a proper ideal of R, and consider any ascending chain of left ideals

$$I_1 \subseteq I_2 \subseteq I_3 \subseteq \cdots \subseteq I_n \subseteq \cdots$$

Take

$$I = \bigcup_{i=1}^{\infty} I_i$$

which is an ideal for a similar reasoning as presented in the proof that every proper ideal is contained in a maximal ideal (see proposition 9.4.19). Since R is a Noetherian domain and $I \subseteq R$, then I is finitely generated. Let's say $I = (a_1, a_2, ..., a_n)$. Then these generators must each be in some ideal I_m, meaning that for all $n > m$, $I_{n+1} = I_{n+2} = \cdots$, showing that R respects the ascending chain condition

(2) $\Rightarrow$ (3) Let R respect the ascending chain condition on it's left ideals, and let $\mathcal{F}$ be a family of left-ideals of R. Pick some random $I_1 \in \mathcal{F}$. If I_1 is maximal in $\mathcal{F}$, then we'd be done, so let's say I_1 is not maximal in $\mathcal{F}$. Then there exists an I_2 such that $I_1 \subset I_2$. If I_2 is maximal in $\mathcal{F}$, then we are done. If not, then we can continue this process. If every element we pick is not maximal, we can create an infinitely long chain[a]

$$I_1 \subsetneq I_2 \subsetneq I_3 \cdots \subsetneq I_n \subsetneq \cdots$$

However, that contradicts the ascending chain condition, meaning for some n, the chain must stabilize. Thus, $\mathcal{F}$ must have a maximal element

(3) $\Rightarrow$ (1) Let $I \subseteq R$ be a left-ideal. Take $\mathcal{I}$ to be the set of all finitely-generated left-ideals contained in I. The set $\mathcal{I}$ is nonempty since $\{0\} \in \mathcal{I}$. It is thus a family of left-ideals of R and so by the 3rd condition, $\mathcal{I}$ admits a maximal,/Then if say I' [b]. If $I \neq I'$, then there exists an element $x \in I$ such that $x \notin I'$. But then $(I' \cup x)$ is a finitely generated left-ideal larger than I', contradicting the maximality of I'. Hence, $I = I'$, showing that I is finitely generated.

[a] technically, to create this infinitely long chain, we used the axiom of choice

[b] Note that Zorn's lemma cannot be used here since it is not known whether every chain will have an upper bound in this set, their union potentially no longer being finitely generated

10.1.15 Remark This proof will become a special case of the equivalent proof for modules in section 12.3.4.

For our purposes, this let's us think of Noetherian domains in terms of the ascending chain condition. You probably already see how this might start related to Factorization domains: If every element in the ring is finitely generated, it must be decomposable into a finite number of factors. This is essentially true:

Proposition 10.1.16: A.C.C. and Factorization

Let R be an integral domain, and let r be a nonzero nonunit element of R. Then if every ascending chain of *principal ideals*

$$(r) \subseteq (r_1) \subseteq (r_2) \subseteq \cdots \subseteq (r_n) \subseteq$$

stabilizes (there exists an m such that for all $l > m$, $(r_l) = (r_{l+1}) = \cdots$), then r can be factored into irreducible elements. In particular, if R respects the A.C.C. on principal ideals, then R is an atomic domain.

Re-writing these ideal using the divisibility notation, it may be more evident: if $r_1|r$, $r_2|r_1$, and so on eventually stabalizes, then r can be factored into irreducible elements.

***Proof*:**
Let's prove this using the contrapositive ($\neg B \Rightarrow \neg A$), so that we will show if r does not factor into irreducible then there exists an ascending chain of principal ideals that does not stabalize.

Since r is not irreducible, then there exists two nonunit non zero element r_1, s_2 suc that $r = r_1 s_2$. Since r does not have a factorization, either r_1 or s_1 are reducible. Without loss of generality, let's say r_1 is reducible. Then $(r) \subseteq (r_1)$ since $s_2 \cdot r_1 = r$, and $r_1 = r_2 s_2$. The same being applied to r_1, we get $(r) \subseteq (r_1) \subseteq (r_2)$. Continuing on indefinitely, we get

$$(r) \subseteq (r_1) \subseteq (r_2) \subseteq \cdots \subseteq (r_n) \subseteq \cdots$$

which never stabilizes since r does not factor, as we sought to show.

Notice how similar this is to Noetherian rings: in a Noetherian ring the ascending chain condition holds for all ideals (proposition 10.1.14), so in particular for its *principal ideals*.

Corollary 10.1.17: Noetherian Domain ⇒ Atomic Domain

Let R be a Noetherian Domain. Then it is an Atomic Domain

***Proof*:**
By proposition 10.1.14, R respects the ascending chain condition on its ideals. Since any element $r \in R$ forms a principal ideal, any ascending chain of principal ideals must stabalize. Thus, by proposition 10.1.16 r must have a factorization. Since r was arbitrary, every element has a factorization, and so R is an Atomic Domain as we sought to show

An atomic domain need not satisfy the ascending chain condition on principal ideals. P. M. Cohn asserted that it does [44], and Grams [54] constructed an atomic domain in which it fails. Proposition 10.1.16 still links a finiteness condition on ideals to a factorization condition.

A counter-example to the converse of corollary 10.1.17 is simplest to verify after Hilbert's Basis Theorem in chapter 23. For the reader who wants to know the counter-example, they can either skip to Hilbert's basis theorem in *Commutative Algebra* theorem 23.2.1 (you have everything you need to know to understand it now), or take on faith that "if R is a Noetherian Domain then $R[x_1, x_2, ..., x_n]$ is a Noetherian Domain". The following is a counter-example:

Example 10.1.18: Atomic Domain $\not\Rightarrow$ Noetherian Domain

Let $R = \mathbb{Z}[x_1, x_2, ..., x_n, ...]$ be a polynomial ring over an infinite number of variables (see section 9.2). Notice that $\mathbb{Z}$ is a Noetherian Domain: As we have shown, $\mathbb{Z}$ a Principal Ideal Domain (example 9.4.6, and so any ideal of $\mathbb{Z}$ is generated by one element, and so it is Noetherian. By Hilbert's Basis Theorem, $\mathbb{Z}[x_1, x_2, ..., x_n]$ is a Noetherian Domain as well.

Now, any polynomial $f \in R$ has finitely many terms by definition, and so is also an element of the subring $\mathbb{Z}[x_{\sigma(1)}, x_{\sigma(2)}, ..., x_{\sigma(n)}]$ where $\sigma(i)$ is some appropriate permutation function so that the terms of f are in the aforementioned subring. But then it is an element of a Noetherian Domain, which means it could be factored by proposition 10.1.16. Since $\mathbb{Z}[x_{\sigma(1)}, x_{\sigma(2)}, ..., x_{\sigma(n)}] \hookrightarrow R$, the same factorization happens in R, and since f was arbitrary, R is an Atomic Domain

However, R is not a Noetherian Domain. The ideal $(x_1, x_2, ..., x_n, ...)$ of all of the terms of R is not finitely generated (it does not respect the ascending chain condition).

This means that in the image presented in the beginning of the chapter, the strict inclusion of Noetherian Domains in Atomic Domains is justified. Similarly, Being an Atomic Domain does not mean the factorization is unique

Example 10.1.19: Atomic Domain $\not\Rightarrow$ Unique Factorization Domain

Take the ring F_{0x} from example 10.1.6. Take any element $f \in F_{0x}$, and form a ascending chain of principal ideals. For the sake of contradiction, let's say the chain never stabilizes: $(f) \subsetneq (f_1) \subseteq (f_2) \subsetneq \cdots \subseteq (f_n) \subsetneq \cdots$. Then since $(f_i) \subsetneq (f_j)$, and every degree zero element is a unit (recall that $F_{0x} \subseteq \mathbb{F}[x]$ for a field $\mathbb{F}$) then the degree of f_j must be *less* than that of f_i. This means we have a decreasing chain:

$$\deg(f) > \deg(f_1) > \deg(f_2) > \cdots > \deg(f_n) > \cdots$$

Notice importantly that this chain *must* terminate since there are no polynomials of degree 0. Since f was arbitrary, every element has a factorization and so it is an Atomic Domain.

However, as we have shown in example 10.1.6, $x^6 = x^2x^2x^2 = x^3x^3$ are two factorizations of x^6 where x^2 and x^3 are not associates, showing it is not a Unique Factorization Domain.

Notice the ring F_{0x} is not a Noetherian Domain in the previous example. Using Hilbert's Basis Theorem, we can also find a Noetherian Domain which is not a UFD:

Example 10.1.20: Noetherian Domain $\not\Rightarrow$ Unique Factorization Domain

Let

$$R = \frac{\mathbb{C}[x, y, z, w]}{(xw - yz)}$$

be the polynomial ring over 4 variables quotiented by the ideal $(xw - yz)$ [a]. By Hilbert's Basis Theorem, $\mathbb{C}[x, y, z, w]$ is a Noetherian ring. By proposition 9.4.8, $\frac{\mathbb{C}[x,y,z,w]}{(xw-yz)} = R$ is a noetherian ring. It is also an integral domain, since $(xw - yz)$ is a prime ideal. Indeed $\mathbb{C}[x, y, z, w]$ is a Unique Factorization Domain (theorem 11.2.3), and $xw - yz$ is irreducible: as a polynomial in w over $\mathbb{C}[x, y, z]$ it has degree 1, so any factorization has a factor of w-degree 0, which divides both coefficients x and yz and is therefore a unit. Irreducible elements of a Unique Factorization Domain are prime (proposition 10.1.29). It is therefore a Noetherian Domain (and hence an Atomic Domain).

However, it is not a Unique Factorization Domain. The element x, y, z, w are all irreducible, and not associates. Since $xw - yz = 0$, we have $r = xw = yz$ has two distinct factorization, showing that R is not a Unique Factorization Domain.

[a] In chapter 31, we will see this ring be called the *quadratic cone in* $\mathbb{A}^4$

The converse is not true either: being a Unique Factorization Domain does not imply it is a Noetherian Domain. In fact, the ring $\mathbb{Z}[x_1, x_2, ..., x_n, ...]$ from example 10.1.18 is also a Unique Factorization Domain that is not a Noetherian Domain. A polynomial involves only finitely many variables, say $x_1, \dots, x_n$, and so does every factor of it, since the degrees in each other variable add up to 0. So its factorizations in $\mathbb{Z}[x_1, x_2, \dots]$ are exactly its factorizations in $\mathbb{Z}[x_1, \dots, x_n]$, where the units are also ± 1, and $\mathbb{Z}[x_1, \dots, x_n]$ is a Unique Factorization Domain by theorem 11.2.3 applied n times, starting from the Unique Factorization Domain $\mathbb{Z}$ (corollary 10.1.34).

Thus, we have shown (or claimed) that

$$\begin{array}{rcl@{\qquad}rcl} \text{Noetherian Domain} & \Rightarrow & \text{Atomic Domain} & \text{Atomic Domain} & \not\Rightarrow & \text{Noetherian Domain} \\ \text{UFD} & \Rightarrow & \text{Atomic Domain} & \text{Atomic Domain} & \not\Rightarrow & \text{UFD} \\ \text{UFD} & \not\Rightarrow & \text{Noetherian Domain} & \text{Noetherian Domain} & \not\Rightarrow & \text{UFD} \end{array}$$

This completes some of the layers in the diagram presented at the beginning of this chapter.

Exercise 10.1.1

1. Let R be a commutative ring generated as a ring by finitely many elements $r_1, \dots, r_n$, that is, every element of R is a polynomial expression with integer coefficients in $r_1, \dots, r_n$. Must R be Noetherian?
2. Show that $\mathbb{C}[x, y, z, w]/(xw - yz)$ is an integral domain.
3. Let R be a commutative ring in which every prime ideal is finitely generated. Show that R is Noetherian. (Hint: otherwise, Zorn's lemma gives an ideal I maximal among the ideals of R that are not finitely generated. If $ab \in I$ with $a, b \notin I$, consider the ideals $I + (a)$ and $\{r \in R \mid ra \in I\}$.)

10.1.2 Unique Factorization Domains

We know continue exploring Atomic Domains in which the factorization of each element is unique (up to unit). As a reminder, here is the definition of a UFD:

Definition 10.1.21: Unique Factorization Domain (UFD)

Let R be an integral domain. Then R is a *Unique Factorization Domain* (commonly abbreviated to UFD) if for every non-unit nonzero element $r \in R$, there exists irreducible elements $q_1, q_2, ..., q_n$ such that

$$r = q_1 q_2 \cdots q_n$$

and if there is another set of irreducible element $q_1', q_2', ..., q_m'$ such that $r = q_1' q_2' \cdots q_m'$, then $n = m$, and after some reshuffling the factors agree up to units (i.e. they are associates), that is, for a permutation σ of $\{1, \ldots, n\}$ and units $u_1, \ldots, u_n \in R$

$$q'_{\sigma(i)} = u_i q_i \qquad \text{for } 1 \leq i \leq n$$

Perhaps the most intuitive way of thinking about elements in Unique Factorization Domains is by linking to every nonzero element of the UFD a multiset (a set that allow's multiplicity) of irreducible factors, in which associate irreducible elements are identified. Units are associated to the empty multiset. The multiplication structure can also be thought of as forming a free abelian monoid structure with all prime elements as generators.

Lemma 10.1.22: Irreducible and Multisets

Let R be a Unique Factorization Domain. For a nonzero $r \in R$, write $r = uq_1 q_2 \cdots q_n$ with u a unit and the q_i irreducible ($n = 0$ when r is a unit), and let the *multiset of irreducible elements* of r be the multiset $M(r)$ of the classes of $q_1, \ldots, q_n$ under the relation of being associates. Then $M(r)$ depends only on r, and for nonzero elements $a, b, c \in R$

1. $(a) \subseteq (b)$ if and only if the multiset of irreducible elements of b is contained in the multiset of irreducible elements of a
2. a and b are associates if and only if their corresponding multisets are equal
3. if $a = bc$, then the corresponding multiset of a is the sum of the multisets of b and c, in which multiplicities add

***Proof*:**

A multiset M is contained in a multiset M' when every class occurs in M at most as often as in M'. An associate vq of an irreducible element q is irreducible: it is nonzero, since v and q are nonzero in an integral domain, and not a unit, since otherwise $q = v^{-1}(vq)$ would be a unit, and if $vq = xy$, then $q = (v^{-1}x)y$, so $v^{-1}x$ or y is a unit, and then x or y is a unit.

$M(r)$ depends only on r. An expression $r = uq_1 \cdots q_n$ exists: with $u = r$ and $n = 0$ if r is a unit, and with $u = 1$ by definition 10.1.21 otherwise. If r is a unit, then it has no such expression with $n \geq 1$, for then $q_1(uq_2 \cdots q_n r^{-1}) = 1$ would make q_1 a unit, while irreducible elements are not units (definition 10.1.5). So $M(r)$ is empty for every unit r. If r is not a unit and $r = uq_1 \cdots q_n = u'q_1' \cdots q_m'$, then $n, m \geq 1$, and $r = (uq_1)q_2 \cdots q_n = (u'q_1')q_2' \cdots q_m'$ are two factorizations into irreducible elements, so definition 10.1.21 gives $n = m$ and a matching of the factors in which matched factors are associates. As uq_1 is an associate of q_1 and $u'q_1'$ one of q_1', the two expressions give the same multiset of classes.

1. By definition 10.1.1, $(a) \subseteq (b)$ exactly when $a = bc$ for some $c \in R$, and then $c \neq 0$ because $a \neq 0$. If $a = bc$, then $M(b) \subseteq M(b) + M(c) = M(a)$ by (3), whose proof below does not use (1). Conversely, suppose $M(b) \subseteq M(a)$, and write $a = uq_1 \cdots q_n$ and $b = vp_1 \cdots p_m$ as in the statement. Every class occurs in $M(b)$ at most as often as in $M(a)$, so after renumbering the q_i we have $m \leq n$ and q_i an associate of p_i for $i \leq m$, say $q_i = w_i p_i$ with w_i a unit (proposition 10.1.4). Then

$$a = uw_1 \cdots w_m \, p_1 \cdots p_m \, q_{m+1} \cdots q_n = b \cdot \left(v^{-1} uw_1 \cdots w_m \, q_{m+1} \cdots q_n\right)$$

   so $a \in (b)$, that is, $(a) \subseteq (b)$.

2. By definition 10.1.2, a and b are associates exactly when $(a) \subseteq (b)$ and $(b) \subseteq (a)$, which by (1) holds exactly when $M(b) \subseteq M(a)$ and $M(a) \subseteq M(b)$, that is, when $M(a) = M(b)$.

3. If $b = uq_1 \cdots q_n$ and $c = vq'_1 \cdots q'_m$, then $a = bc = (uv)q_1 \cdots q_n q'_1 \cdots q'_m$ with uv a unit, so $M(a) = M(b) + M(c)$, completing the proof.

This lemma essentially shows that working with elements of a Unique Factorization Domain comes down to working with their corresponding multiset, making the analysis of their structure more often than not being more set theoretical or number theoretical. As an example of this, Unique Factorization Domains make it very easy to define the concept of *greatest common divisor*.

Greatest Common Divisor

The set of sets of multi-sets thus has a natural lattice paralleled on rings given by the divisibility. In fact, meet and joins are well-defined[2]:

Definition 10.1.23: Greatest Common Divisors In Commutative Rings

Let R be a commutative ring and let $a, b \in R$ with $b \neq 0$. Then the *greatest common divisor* of a and b is a nonzero element d such that

1. $d|a$ and $d|b$,
2. if $d'|a$ and $d'|b$ then $d'|d$

A greatest common divisor of a and b will be denoted $\gcd(a, b)$.

Notice that in the definition, R was a commutative ring, since divisibility was defined for commutative rings in general. It should be noted that the gcd of two elements is unique *up to associativity*. it is helpful to put the definition of gCD in ideal-interpretation of divisibility:

Definition 10.1.24: GCD Using Principal Ideals

Let R be a commutative ring and $a, b \in R$, not both zero. An element $d \in R$ is a gcd of a and b if (d) is the smallest principal ideal containing $(a) + (b)$.

In a Principal Ideal Domain, $(a) + (b)$ is itself principal, so $(\gcd(a, b)) = (a) + (b)$.

[2]See appendix D.1.

Since $(d) \supseteq (a) + (b)$ exactly when d divides both a and b, this matches the previous definition of gcd. The ideal $(a) + (b)$ need not be principal: in $\mathbb{Z}[x]$, $\gcd(2, x) = 1$, but $(2) + (x) \neq (1)$, since every element of $(2) + (x)$ has an even constant term. There do exist rings for which the gcd between two elements do not exist (in example 10.1.6, take the ring F_{0x} from the second part of the example. A divisor of x^m in F_{0x} is a nonzero constant times x^k with $x^{m-k} \in F_{0x}$, that is $m - k \neq 1$. So the common divisors of x^5 and x^6 are, up to units, 1, x^2 and x^3, and x^2 does not divide x^3 because $x \notin F_{0x}$, while x^3 does not divide x^2 by degree. Hence $\gcd(x^5, x^6)$ does not exist). For Unique Factorization Domains, every element has a gcd:

Proposition 10.1.25: GCD in Unique Factorization Domain

let R be a Unique Factorization Domain. Then for any $a, b \in R$ with $b \neq 0$, $\gcd(a, b)$ exists. Furthermore, if $a \neq 0$ and

$$a = up_1^{n_1} p_2^{n_2} \cdots p_k^{n_k} \qquad b = vp_1^{m_1} p_2^{m_2} \cdots p_k^{m_k}$$

is the factorization of a and b, that is, every p_i is irreducible, u and v are units, p_i and p_j are not associates for $i \neq j$, and some n_i's or m_i's can be zero. Then the gcd (up to a unit) is:

$$\gcd(a, b) = p_1^{\min(n_1, m_1)} p_2^{\min(n_2, m_2)} \cdots p_k^{\min(n_k, m_k)}$$

***Proof*:**
If $a = 0$, then b is a gcd of a and b (definition 10.1.23): it divides $0 = 0 \cdot b$ and b, and every common divisor of 0 and b divides b. So let $a \neq 0$, and let $d = p_1^{\min(n_1, m_1)} p_2^{\min(n_2, m_2)} \cdots p_k^{\min(n_k, m_k)}$. Since $\min(n_i, m_i) \leq n_i$ and $\min(n_i, m_i) \leq m_i$ for each i, $d \mid a$ and $d \mid b$. Write $M(-)$ for the multisets of lemma 10.1.22. As the p_i are pairwise non-associate, $M(a)$ contains the class of p_i exactly n_i times, $M(b)$ contains it exactly m_i times, and $M(d)$ contains it exactly $\min(n_i, m_i)$ times, with no other classes. If there is some c that also divides a and b ($c \mid a$ and $c \mid b$), then $c \neq 0$ since $a \neq 0$, and $(a) \subseteq (c)$ and $(b) \subseteq (c)$. By lemma 10.1.22(1), $M(c)$ is contained in both $M(a)$ and $M(b)$, so every class occurs in $M(c)$ at most $\min(n_i, m_i)$ times if it is the class of p_i, and not at all otherwise. Hence $M(c) \subseteq M(d)$, so $(d) \subseteq (c)$ by lemma 10.1.22(1), that is, $c \mid d$. So d is a gcd of a and b, as we sought to show.

10.1.26 Relation Between Lattice's and UFDs It should be noted that there are integral domains which are not Unique Factorization Domain's but do have the concept of gcd defined for every element. The class of all integral domains which have the concept of gcd defined for every element is broader than Unique Factorization Domain's and are not always Noetherian, and so such domains need their own name and are called *gcd domains*. In a sense, gcd domains are a generalization of Unique Factorization Domains: A gcd domain is Unique Factorization Domain if and only if the gcd domain satisfies the ascending chain condition on principal ideals (similarly to how Atomic domains do). However, a gcd domain is not always an Atomic domain, and hence fits a bit awkwardly in our current hierarchy. In essence, this is because gcd domains hold information on information between elements, while atomic domains hold element-wise information.
For future purposes, gcd domains do fit into an important hierarchy of domains: *normal domains* shall be introduced in *Commutative Algebra* definition 26.1.3, and all gcd domains are normal domains:

$$\text{normal domains} \supseteq \text{gcd domains} \supseteq \text{UFD's}$$

The definition of GCD's using ideals suggests that the GCD, when it exists, ought to be unique in general, and indeed it is:

Proposition 10.1.27: Uniqueness Of Greatest Common Divisor (In Integral Domain)

Let R be an integral domain. If (d) and (d') are both greatest common divisors of then $(d) = (d')$.

***Proof*:**
If d and d' are greatest common divisors, then they must each divide each other (condition 2 of definition 10.1.23), and so we will get $(d') \subseteq (d)$ and $(d') \supseteq (d)$, meaning $(d') = (d)$,

Just like for the integers, we may also define the dual of the GCD, the least common multiple. In the following, the LCM will be defined in terms of principle ideals, the similar definition should be translated into elements:

Definition 10.1.28: Least Common Multiple (lCM)

Let R be a commutative ring and $(a), (b) \subseteq R$. Then the *least common muliple* is the ideal I such that $I \subseteq (a)$ and $I \subseteq (b)$ and is the largest such ideal. Namely

$$\text{lcm}((a), (b)) = (a) \cap (b)$$

Properties of UFD's

As we have shown in examples 10.1.6 and 10.1.20 being an irreducible element in an integral domain does not imply that the element is a prime element. This was because prime elements are "stronger" than irreducible in that they not only have to be able to be divisible, but they have to be "globally divisible" for any factorization. However, since factorization is unique in a Unique Factorization

Domain, it should come as no surpise that there is no distinction between prime elements and irreducible elements:

Proposition 10.1.29: Prime If And Only If Irreducible In UFD

Let R be a Unique Factorization Domain. Then a nonzero element is a prime if and only if it is irreducible

***Proof*:**
The fact that prime elements are irreducible was proven in proposition 10.1.7, so we will show the converse. Let a be an irreducible element. Then a is nonzero and not a unit. Now, assume $bc \in (a)$ so that $d \cdot a = bc$. If $b = 0$ or $c = 0$, then that element lies in (a). Otherwise $bc \neq 0$ and $(bc) \subseteq (a)$, so, with $M(-)$ the multisets of lemma 10.1.22, parts (1) and (3) of that lemma give

$$M(a) \subseteq M(bc) = M(b) + M(c)$$

As $a = 1 \cdot a$ with a irreducible, $M(a)$ consists of the class of a alone. That class therefore occurs in $M(b)$ or in $M(c)$, that is, $M(a) \subseteq M(b)$ or $M(a) \subseteq M(c)$, and lemma 10.1.22(1) gives $(b) \subseteq (a)$ or $(c) \subseteq (a)$. In any case, at least one of b or c are in (a), showing that a is prime (definition 10.1.5), as we sought to show.

Thus, if we see every irreducible element being prime as representing "global" irreducibility (or divisibility), then if we further assume the A.C.C. on principle ideals, we see that this ought to fully characterize UFDs. The following theorem demonstrate exactly this:

Theorem 10.1.30: Unique Factorization Domain Equivalence

Let R be an integral domain. Then R is a Unique Factorization Domain if and only if

1. The ascending chain condition for principal ideal holds in R
2. Every irreducible element is a prime element

***Proof*:**

($\Rightarrow$) Let R be a Unique Factorization Domain. Then by proposition 10.1.29 every irreducible element is a prime element, and by corollary 10.1.11 R is an atomic domain, and so by proposition 10.1.16 R respects the ascending chain condition (this can also be proven directly using the corresponding multisets to elements)

($\Leftarrow$) Let R satisfy the A.C.C. for principal ideals and let every irreducible be prime. By proposition 10.1.16, R is an Atomic domain. It remains to show that R factors uniquely. To show this, let n be a nonunit and

$$n = p_1 p_2 \cdots p_n = q_1 q_2 \cdots q_m$$

be two factorizations of n into irreducibles. Then since $q_2 q_3 \cdots q_n \cdot q_1 = p_1 p_2 \cdots p_n$, we have $p_1 p_2 \cdots p_n \in (q_1)$. Since q_1 is irreducible, by the 2nd condition it is a prime, and so for some i, $p_i \in (q_1)$. Without loss of generality, we can say $p_1 \in (q_1)$ by just rearranging and relabelling the factors. Since

$p_1 \in (q_1)$, then $u_1 \cdot q_1 = p_1$. Since p_1 is irreducible and q_1 is not a unit, necessarily u_1 is a unit. Then, we can re-write the equation as

$$u_1 q_1 p_2 \cdots p_n = q_1 q_2 \cdots q_m$$

Cancelling out q_1 from each side and replacing p_2 by $u_1 p_2$ produces us

$$p_2 p_3 \cdots p_n = q_2 q_3 \cdots q_m$$

from here, we can continue this process for the rest of the p_i's, where we will end up with

$$u_1 u_2 \cdots u_n q_1 q_2 \cdots q_m = q_1 q_2 \cdots q_m$$

leting $u = u_1 u_2 \cdots u_n$, we get $u q_1 q_2 \cdot q_n = q_1 q_2 \cdots q_n$. Note that $n = m$ since if not then at some point the remaininng part of the left hand side will be equal to 1, a contradiction to n not being a unit. Thus, the two factorization are equal up to associates, as we sought to show.

Notice how the uniqueness of the factorization allowed us to make the A.C.C. for principal ideals a defining feature of Unique Factorization Domains, in contrast to ho the A.C.C. for principal ideals was insufficient to define Atomic Domains.

This theorem is also very useful in easily remembering how Unique Factorization Domain's and Noetherian Domains are different: If we start with a domain with the A.C.C. for principal ideals (i.e. the types of Atomic domains we ill work with) strengthen the A.C.C. condition to work on all ideals, we get a Noetherian domain. Conversely, if we are working with a Noetherian domain and we loosen the A.C.C. condition to principal ideals but add that all irreducible are primes, then we get a Unique Factorization Domain.

10.1.3 Important UFD: Principle Ideal Domains

Principal Ideal Domains are stronger than Noetherian Domains in the sense that every ideal is generated by a single element (rather than finitely many element for Noetherian Domains). They are therefore immediately Atomic Domains by proposition 10.1.16. By theorem 10.1.30, if a Principal Ideal Domain also has that every irreducible element is prime, then it is automatically a Unique Factorization Domain. Are irreducible elements prime in a Principal Ideal Domain? The answer is yes. Hence PIDs form a subclass of UFDs. Take a moment to think about why irreducible elements are prime in PIDs before proceeding to the next proposition (hint: can you prove prime ideals *must* be maximal ideals in a PID?). From this proof, there will now be a new set of examples for Unique Factorization Domains similarly to how all Noetherian domains are an easy set of examples for Atomic domains

10.1.31 Taking a moment

As the hint suggests, we first prove the following important intermediary result:

Proposition 10.1.32: In PID, Prime Ideal iff Maximal Ideal

Let R be a Principal Ideal Domain and take a nonzero ideal $(r) \subseteq R$. Then (r) is a prime ideal if and only if it is a maximal ideal.

Intuitively, since

***Proof*:**
Let R be a Principal Ideal Domain. If an ideal of R is maximal, by corollary 9.4.26 that ideal is prime. Thus we will prove the converse.

Let $(p) \subseteq R$ be a prime ideal, and assume that $I \supseteq (p)$ is an ideal that contains (p). We must show that $I = (p)$ or $I = R$. Since R is a Principal Ideal Domain, there exists an $m \in R$ such that $(m) = I$. Since $(m) \supseteq (p)$, $p \in (m)$, and so $p = rm$. Since p is a prime element, then either $r \in (p)$ or $m \in (p)$. If $m \in (p)$, then $(m) = (p)$, fulfilling the $I = (p)$ case. If $r \in (p)$ then $r = sp = ps$ and so

$$p = rm = psm$$

And by the cancellation property of integral domains, $1 = sm$, and so $1 \in (m)$ implying that $(m) = R$, fulfilling the $I = R$ condition. That means that (p) fulfills the conditions of being a maximal ideal, as we sought to show.

The main idea is that any ideal requries only 1 element to repersent it, which as it will turn out will be key to why elements will factor uniquely.

Proposition 10.1.33: Prime If And Only If Irreducible In PID

Let R be a Principal Ideal Domain. Then a nonzero element is a prime if and only if it is irreducible. Along with the fact that Principal Ideal Domain are Noetherian Domains (and hence respecting the A.C.C. on principal ideals) we have

$$\text{PID} \Rightarrow \text{UFD}$$

***Proof*:**
Since a Principal Ideal Domain is an integral domain, we have just shown in proposition 10.1.7 that prime elements are irreducible, so it remains to prove the converse.

Let's say p is an irreducible element of R. To show it's prime, we must how (p) is a prime ideal. Since we are working in a Principal Ideal Domain, by proposition 10.1.32, it's equivalent to show that (p) is a maximal ideal. So, for the sake of contradiction, let's assume (p) is not maximal, and so there exists a strictly larger ideal that is the maximal ideal containing (p) $(p) \subsetneq (m) \neq R$ for appropriate $m \in R$. Then

$$p = am$$

for some $a \in R$. Since p is irreducible, then either a or m is a unit in R. If M is a unit, then $m^{-1}m = 1 \in (m)$ implying $(m) = (1) = R$, but then it's not a maximal ideal, since maximal ideals are proper ideals. Conversely, if a is a unit, then by proposition p and m are associates, meaning $(p) = (m)$. But since (m) was maximal, that makes (p) maximal. Thus, (p), by proposition 10.1.32, (p) is a prime ideal.

Therefore, since all Principal Ideal Domain are Noetherian Domains and Noetherian respect

the A.C.C. on principal ideals, by theorem 10.1.30, all Principal Ideal Domain are Unique Factorization Domains, as we sought to show.

There is also a very simple proof I like I found in Eisenbud: (Eisenbud) We know that if R is a Unique Factorization Domain, then it respects the A.C.C. on principal ideals. Use that to find a maximal ideal, which must be generated by one element since it's a Principal Ideal Domain, but then it must be that for one of the elements in the chain, it plateau's, and so it fulfills the ascending chain condition, and so it is a Unique Factorization Domain.

Corollary 10.1.34: $\mathbb{Z}$ is a UFD (Fundamental Theorem of Arithmetics)

The integers ($\mathbb{Z}$) as a ring are a Unique Factorization Domain.

***Proof*:**
$\mathbb{Z}$ is a Principal Ideal Domain: the zero ideal is (0), and a nonzero ideal $I \subseteq \mathbb{Z}$ contains a least positive element n, and for $a \in I$, dividing gives $a = qn + r$ with $0 \leq r < n$ and $r = a - qn \in I$, so $r = 0$ and $I = (n)$. By proposition 10.1.33, every Principal Ideal Domain is a Unique Factorization Domain, completing the proof.

The converse of this theorem is not true, that is if an integral domain is a Unique Factorization Domain, this does not imply that it is a PID, justifying the strict inclusion of the image at the very beginning. Recall from example 9.4.6 that the ideal $(2, x)$ from the ring $\mathbb{Z}[x]$ is not a principal ideal. However, the ring $\mathbb{Z}[x]$ is a Unique Factorization Domain. This is rather difficult to show directly: if we have any any polynomial $p(x) \in \mathbb{Z}[x]$, how can we guarantee it factors and that it's unique up to units, that is that $\mathbb{Z}[x]$ respects the ascending chian conditions on principal ideals and that all irreducibles are primes? On page 385, we shall show this result.

Proposition 10.1.35: Sufficient Condition for Greatest Common Divisor

If a and b are nonzero elements in the commutative ring R such that the ideal gnerated by a and b is a principal ideal (d), then d is a greatest common divisor of a and b

***Proof*:**
The ideal generated by a and b in the commutative ring R is $(a, b) = \{ra + sb \mid r, s \in R\}$, and by hypothesis $(a, b) = (d)$.

Since $a \in (a, b) = (d)$, there is an $r \in R$ with $a = rd$, that is $d \big| a$, and the same argument gives $d \big| b$. Also $d \neq 0$, since otherwise $(d) = 0$ would force $a = 0$.

Now suppose $d' \big| a$ and $d' \big| b$, say $a = d'u$ and $b = d'v$. Since $d \in (d) = (a, b)$, we may write $d = xa + yb$ for some $x, y \in R$, and then

$$d = xd'u + yd'v = d'(xu + yv)$$

so $d' \big| d$. Both requirements of definition 10.1.23 hold, so d is a greatest common divisor of a and b.

Corollary 10.1.36: Coprime Equals Comaximal In A PID

Let R be a principal ideal domain and $a, b \in R$ nonzero. Then 1 is a greatest common divisor of a and b if and only if a and b are comaximal (definition 9.6.3).

***Proof*:**
Write $(a, b) = (d)$. By proposition 10.1.35, d is a greatest common divisor of a and b, and by proposition 10.1.27 every greatest common divisor generates (d). So 1 is a greatest common divisor exactly when $(d) = (1)$, that is, when $(a, b) = (1)$.

Being a unique factorization domain is not enough: $\mathbb{Z}[x]$ is one (theorem 11.2.3, proved later), yet $\gcd(2, x) = 1$ while $(2, x) \neq (1)$ (example 9.6.5).

10.1.37 Warning: Two Meanings of (a, b) Some texts write (a, b) both for $\gcd(a, b)$ and for the ideal generated by a and b. In a PID the clash is harmless by corollary 10.1.36. In $\mathbb{Z}[x]$ it is not: "$(2, x) = 1$" is true for the gcd and false for the ideal. We reserve (a, b) for the ideal.

This proposition explains the (a, b) notation for the gcd of a and b.

Note that an integral domain in which every ieal generated by 2 elements (a, b) is a principal ideal is called a *Bézout Domain* (more generally, if every *finitely generated* ideal is principal, then we have a Bézout Domain. For Principal Ideal Domains, every ideal is principal). Note that it's not a *necessary* condition.

For future reference, we also prove the following[3]:

Proposition 10.1.38: UFD And Maximal, Then PID

Let R be a Unique Factorization Domain in which every nonzero prime ideal is maximal. Then R is a Principal Ideal Domain

***Proof*:**
Step 1: every prime ideal is principal. Let P be a prime ideal of R. If $P = (0)$, it is principal. Otherwise choose $0 \neq r \in P$. It is not a unit, since otherwise $1 = r^{-1}r \in P$ and $P = R$, while a prime ideal is proper (definition 9.4.22). By definition 10.1.21, $r = q_1 q_2 \cdots q_n$ with $n \geq 1$ and each q_i irreducible. As P is prime and $q_1(q_2 \cdots q_n) \in P$, either $q_1 \in P$ or $q_2 \cdots q_n \in P$, and repeating the argument with the shorter product gives $q_i \in P$ for some i. By proposition 10.1.29, q_i is a prime element, so (q_i) is a nonzero prime ideal (definition 10.1.5), hence maximal by hypothesis. Since $(q_i) \subseteq P \neq R$, maximality gives $P = (q_i)$.

Step 2: a maximal non-principal ideal. Let N be the set of ideals of R that are not principal, partially ordered by inclusion, and suppose for a contradiction that $N \neq \emptyset$. Every chain in N has an upper bound in N. For the empty chain, any member of N is one. For a nonempty chain $\mathcal{C}$, the union $U = \bigcup_{A \in \mathcal{C}} A$ is an ideal: two elements $x, y \in U$ lie in a common member of the chain, which contains $x - y$, and rx lies in the member containing x for every $r \in R$. If

[3]This will be useful in number theory

$U = (x)$ were principal, then $x \in A$ for some $A \in \mathcal{C}$, so $(x) \subseteq A \subseteq U = (x)$ and $A = (x)$ would be principal, which is impossible. So $U \in N$, and it contains every member of $\mathcal{C}$. By Zorn's lemma (theorem A.2.3), N has a maximal element $\mathfrak{n}$.

Step 3: the contradiction. The ideal $\mathfrak{n}$ is proper, since $R = (1)$ is principal, and it is not prime by Step 1. So there are $a, b \in R$ with $ab \in \mathfrak{n}$, $a \notin \mathfrak{n}$ and $b \notin \mathfrak{n}$. The ideal $\mathfrak{n} + (a)$ strictly contains $\mathfrak{n}$, so it does not lie in N by the maximality of $\mathfrak{n}$, that is, $\mathfrak{n} + (a) = (u)$ for some $u \in R$. Let

$$J = \{r \in R \mid ru \in \mathfrak{n}\}$$

This is an ideal of R: it contains 0, and for $r, r' \in J$ and $s \in R$, $(r - r')u = ru - r'u \in \mathfrak{n}$ and $(sr)u = s(ru) \in \mathfrak{n}$. It contains $\mathfrak{n}$, because $\mathfrak{n}$ is an ideal. It contains b: writing $u = x + ta$ with $x \in \mathfrak{n}$ and $t \in R$, we get $bu = bx + t(ab) \in \mathfrak{n}$. Since $b \notin \mathfrak{n}$, the ideal J strictly contains $\mathfrak{n}$, so $J \notin N$ and $J = (v)$ for some $v \in R$.

We claim $\mathfrak{n} = (uv)$. Since $v \in J$, $uv \in \mathfrak{n}$, so $(uv) \subseteq \mathfrak{n}$. Conversely, let $x \in \mathfrak{n}$. Then $x \in \mathfrak{n} + (a) = (u)$, so $x = ru$ for some $r \in R$, and $ru = x \in \mathfrak{n}$ gives $r \in J = (v)$, say $r = sv$. Hence $x = suv \in (uv)$. So $\mathfrak{n} = (uv)$ is principal, contradicting $\mathfrak{n} \in N$. Therefore $N = \emptyset$, every ideal of R is principal, and R, being an integral domain, is a Principal Ideal Domain (definition 9.4.9), completing the proof.

Exercise 10.1.2

1. Let $R[x]$ be a Principal Ideal Domain. Then R is a UFD. Conclude that if R is not a field, then $R[x]$ is not a Principal Ideal Domain!

   Since $\mathbb{Z}$ is not a field, then $\mathbb{Z}[x]$ is not a Principal Ideal Domain! In example 9.4.6(3) it was manually shown that $(2, x)$ is not a principal ideal in $\mathbb{Z}[x]$. This theorem makes it easier to prove.

   The converse is true too: if F is a field, $F[x]$ is a Principal Ideal Domain, and in fact a Euclidean Domain (section 11.1).

2. (Challenging) Let R be an integral domain. Then if every prime ideal is principle, R is a PID (In this way, UFDs are almost PIDs, however not all ideals are principle)

3. (If you know Complex Analysis) Show that the ring of entire functions is a gcd domain. Show that the ring of real analytic functions is a Bézout domain.

10.2 Euclidean Domains

So far, we have been exploring divisibility in terms of being able to directly factor elements. However, it is in general difficult to establish when an element is divisible by another (try it out yourself with relatively large elements of some of the more complicated UFDs that were presented). If an element is not divisible by another element is there some way to measure to what "degree" an element is not divisible by another? Can we quantify the lack of divisibility given by the gcd.

In the integers, there is the *euclidean algorithm* that gives the answer. The existence of an algorithm to find the GCD cannot be under-estimated: If given two integers with over a thousand digits, it will

be impossible to find the greatest common divisor in a reasonable amount of time, that is, before the heat death of the universe (until a faster way of factorizing is found). The problem is about our initial choice for divisors. If I say R is a Unique Factorization Domain and $x \in R$, then how would you start finding it's prime factorization? If you have some a and b such that $ab = x$, How do you start decomposing them? Even for the integers, it is in general very difficult to find prime factors of an element x[5].

For the integers, Euclid in approximately the year 300BC discovered that there is a simple algorithm for finding the GCD that quantifies exactly how divisible two numbers are. The key observation is that if $a, b \in \mathbb{Z}$, where $a < b$ (notice the user of the total order, $<$, of $\mathbb{Z}$) then we may write

$$b = ka + r$$

where $r < a$. If $a|b$, then $r = 0$. If $a \nmid b$, then r is the "torsion" or "remainder" that is left-over. In terms of the GCD, if $a|b$, then $\gcd(a, b) = a$, and if $a \nmid b$, then $\gcd(a, b) < a$ and in the "worst case scenario" $\gcd(a, b) = 1$. The problem when generalizing this to general rings is that we require a notion of "size", namely it was crucial to use the fact that $a < b$ and it is imperative that $r < a$ to have a reasonable notion of such a factorization. In this section, we shall endavour to find a function, say $v : R \to \mathbb{N}_{\geq 0}$ that will allow us to assign a natural number to each ring element so that we may recapture this notion from the integers.

Definition 10.2.1: [Ring] Valuation

Any function $v : R \to \mathbb{Z}$ with $v(0) = 0$ is called a *valuation* on the ring R. If $v(a) > 0$ for $a \neq 0$, then v is said to be a *positive valuation*.

10.2.2 Note The notion of valuation shall be defined later in these notes on fields as *real [Archimedean] valuation* or *absolute value* (definition 21.2.1) and generalized to *G-valuation* (definition 27.1.1)[a]. The notion of a G-valuation is a generalization of the absolute value, however it is often presented with the axiom that $v(0) = \infty$. Valuations can just as well be defined with $v(0) = 0$, and hence the use of the term "valuation" here is justified.

[a] More specifically non-Archimedean valuations shall be generalized to G-valuations

10.2.3 Note There are at least two common uses of the word "valuation" in contemporary abstract algebra: an *absolute-valuation* or more commonly an *absolute value* and a *G-valuation* (definition 27.1.1). These two concepts are non-compatible[a], notably G-valuations have axiom dictating that $v(0) = \infty$ while absolute values has an axiom dictating that $v(0) = 0$. The above use of the term valuation is closer to an *absolute value*.

[a] Though an absolute value may induce a G-valuation, this is shown when the concepts are introduced

If you know some analysis, you may wonder if the valuation is related to the one introduced on $\mathbb{R}$ or $\mathbb{C}$ (or normed vector spaces more generally). These concepts are indeed related, and we shall even see more explicit connection in chapter 21$\star$.

[5] RSA encryption is based off of the fact that prime factorization is a every difficult task if you do not know a priori what primes you are working with

Returning to the issue at hand, we shall require a valuation N to be defined on an integral domain R that satisfies the following property:

Definition 10.2.4: Euclidean Valuation and Euclidean Domain

Let R be an integral domain and $N : R \to \mathbb{N}_{\geq 0}$ a valuation. Then v is a *euclidean valuation* on R if for any two elements a, b of R with $b \neq 0$ there exists elements q, r in R such that

$$a = qb + r \qquad \text{with } r = 0 \text{ or } N(r) < N(b)$$

The element q is called the *quotient* and the element r the *remainder* of the division
if a euclidean valuation can be defined on a ring, then the ring is said to be a *Euclidean Domain* (or posses a *division algorithm*)

The main thing we can do in euclidean domains is run the division algorithm to keep "dividing" our numbers

$$\begin{aligned} a &= q_0 b + r_0 \\ b &= q_1 r_0 + r_1 \\ r_0 &= 2_0 r_1 + r_2 \\ &\vdots \\ r_{n-1} &= q_{n+1} r_n \end{aligned}$$

Such a sequence will terminate since $N(b) > N(r_0) > \cdots > N(r_n)$, and it will eventually hit 0.

Example 10.2.5: Euclidean Domains

1. Every field with the euclidean valuation is a euclidean domain! In fact, any valuation will work!

   Proof. Let $x \in \mathbb{F}$ be an element of a field. Then since every element in a field has a unit, then
   $$x = xb + 0$$
   where $b = x^{-1}$.

   □

   Thus, a commutative division ring is a field, and hence a Euclidean domain.

2. In general, every unit will trivially satisfy this condition, since if $u \in R$ is a unit, then
   $$u = uu^{-1} + 0$$
   and so terminates instantly. So in a sense, Euclidean domains say that if we have elements that are *not* units, how many properties of divisible things can we put on them?

   Note importantly that euclidean domains must be domains (meaning no zero-divisors)! So oddities with multiplying not increasing the "size" of elements will not happen.

3. Ring of fractions in general are not euclidean domains, since they might have zero-divisors. So even though rings of fractions can be thought of as a way of enlarging a ring to make it's elements more divisible, it cannot do so if it has zero-divisors.

4. The integers $\mathbb{Z}$ are a euclidean domain with $N(a) = |a|$. The division algorithm is your usual euclidean algorithm. If you take $a, b \in \mathbb{Z}$, and $a < b$ then $b = aq + r$. We see that $N(r) = |r| < |b| = N(b)$. This will always be the case with $b \neq 0$! Thus, it is a Euclidean Domain.

5. If $\mathbb{F}$ is a field, then $\mathbb{F}[x]$ is also a Euclidean domain with $N(p(x)) = deg(p(x))$. The division algorithm is your usual polynomial division. The reason is simple for valuation: polynomial division *must* produce a remainder r with degree *less* than b, by definition! This makes $\mathbb{F}[x]$ into a Euclidean Domain, as section 11.1 proves in full.

6. Let
$$\mathbb{Z}[i] = \{a + bi | a, b \in \mathbb{Z}\}$$
And let
$$N(a + bi) = (a + bi)(a - bi) = a^2 + b^2$$
which is the usual valuation on $\mathbb{C}$. Intuitively, this is because we have subrings $\mathbb{Z}[i] \subseteq \mathbb{C}$. These are called the *Gaussian Integers*. We will show that Gaussian integers ($\mathbb{Z}[i]$) is a Euclidean Domain.

   Consider $a, b \in \mathbb{Z}[i]$. We need to show that
$$a = kb + r \qquad N(r) < N(b)$$
for appropriate k, r. Since $\mathbb{Z}[i] \subseteq \mathbb{Q}(i)$, take
$$\frac{a}{b} = \frac{ac + bd}{c^2 + d^2} + \left(\frac{bc - ad}{c^2 + d^2}\right) = r + si$$
this gives us an idea of how close a is to b by having by looking at their fraction. Let p be the closest (or one of the 2 closest) integers to r and q be the closest (or one of the 2 closest) integers to s so that $|r - p|, |s - q| \leq \frac{1}{2}$. Then we will show that
$$a = (p + qi)b + r$$
Whatis r? Notice that $t = (r - p) + (s - q)i$, so that $r = tb$, giving us $r = a - (p + qi)b$, showing that $r \in \mathbb{Z}[i]$. With this, we can calcualte the valuations quite easily! Notice that $N(t) = (r - p)^2 + (s - q)^2$ would at most
$$N(t) \leq \frac{1}{4} + \frac{1}{4} = \frac{1}{2}$$
and so, since $N(\alpha\beta) = \alpha\beta\,\overline{\alpha\beta} = (\alpha\overline{\alpha})(\beta\overline{\beta}) = N(\alpha)N(\beta)$ for all $\alpha, \beta \in \mathbb{C}$, and $N(b) > 0$ for $b \neq 0$,
$$N(r) = N(tb) = N(t)N(b) \leq \frac{1}{2}N(b) < N(b)$$
showing that $\mathbb{Z}[i]$ is indeed a Euclidean Domain.

7. Another class of Euclidean domains come from polynomial rings over fields. The proof is a little more elaborate and so we shall leave it till page 380.

Notice how central defining a valuation is to showing a ring is a euclidean domain. This algorithm *almost* produces a divisibility condition, making Euclidean domains "close" to fields. However, they are not fields, since $\mathbb{Z}$ is a euclidean domain. So instead of every element having an inverse, for every pair of elements (a, b), we can find a number(s) c such that we have a notion of $c|a$ and $c|b$. If every pair of numbers has this condition, we have a Euclidean domain!

We have not seen many examples of Euclidean domains. The following is a class of rings that shall provide a testing ground for finding more Euclidean domains and will come up a lot in chapter 50:

Example 10.2.6: Rings of Integers of Quadratic Extenions

Let D be a squarefree integer (it's prime-factorization has exactly one factor for each prime that appears in it, so $10 = 2 \cdot 5$ is square free, but $18 = 2^2 \cdot 3$ is not). Then we can define $\mathbb{Z}[\sqrt{D}] = \left\{a + b\sqrt{D} | a, b \in \mathbb{Z}\right\}$, which is a ring, even a subring, of the quadratic field $\mathbb{Q}(\sqrt{D})$ (that we defined in the first examples). If we take $D \equiv 1 \bmod 4$, then consider the slighty larger subset

$$\mathbb{Z}\left[\frac{1+\sqrt{D}}{2}\right] = \left\{a + b\frac{1+\sqrt{D}}{2} | a, b \in \mathbb{Z}\right\}$$

is also a subring. With this, define

$$\mathcal{O} = \mathcal{O}_{\mathbb{Q}(\sqrt{(D)})} = \mathbb{Z}[\omega] = \{a + b\omega | a, b \in \mathbb{Z}\}$$

where

$$\omega = \begin{cases} \sqrt{D} & \text{If } D \equiv 2, 3 \bmod 4 \\ \frac{1+\sqrt{D}}{2} & \text{If } D \equiv 1 \bmod 4 \end{cases}$$

called the *ring of integers* in the quadratic field $\mathbb{Q}(\sqrt{D})$. The idea being that the elements of $\mathcal{O}$ of the field $\mathbb{Q}(\sqrt{D})$ have many properties analogous to those of the subring of integers $\mathbb{Z}$ in the field of rational numbers. Or, if we have a "field extension", which in a diagram we can think of as:

$$\begin{array}{ccc} \mathbb{F} & \supseteq & O_{\mathbb{F}} \\ \uparrow & & \uparrow \\ \mathbb{Q} & \supseteq & \mathbb{Z} \end{array}$$

where the arrows represent inclusions, then we want $\mathbb{F}$ to share properties that $\mathbb{Z}$ has Given an extension field $\mathbb{F}$ for $\mathbb{Q}$, we identity rings of integers $O_{\mathbb{F}}$ a subrging of F analogous to $\mathbb{Z} \subset \mathbb{Q}$

Note also that $\mathbb{Z}[\omega] = \mathcal{O}_{\sqrt{(D)}}$ is an integral domain, and that it's field of fraction is $\mathbb{Q}(\sqrt{D})$, giving us another way of thinking of ho $\mathbb{Z}[\omega]$ is sort of the "natural" integral domain to choose.

In the special case where $= -1$, we get $\mathbb{Z}[i]$, called the *Gausian integers*, used to study powers of numbers in the complex plane.

The reason for defining this is because we can define the concept of a *field norm*. Let $N : \mathbb{Q}(\sqrt{D}) \to Q$ by

$$N(a + b\sqrt{D}) = (a + b\sqrt{D})(a - b\sqrt{D}) = a^2 - Db^2 \in \mathbb{Q}$$

which is non-zero if $a + b\sqrt{D} \neq 0$. This gives an idea of "size" in the field $\mathbb{Q}(\sqrt{D})$. For instance, when $D = -1$, then the valuation of $a + bi$ is $a^2 + b^2$ (as we know it from Complex Analysis!),

which is the square of the length of this complex number considered as a vector in the compelx plane.

We can see that N is multiplicative, that is, $N(\alpha\beta) = N(\alpha)N(\beta)$ for all $\alpha, \beta \in \mathbb{Q}(\sqrt{D})$ given by

$$N(a+b\omega) = (a+b\omega)(a-b\overline{\omega}) = \begin{cases} a^2 - b^2 D & \text{if } D \cong 2,3 \bmod 4 \\ a^2 + ab + \frac{1-\sqrt{D}}{2} & \text{if } D \cong 1 \bmod 4 \end{cases}$$

where

$$\overline{\omega} = \begin{cases} -\sqrt{D} & \text{if } D \equiv 2,3 \bmod 4 \\ \frac{1-\sqrt{D}}{2} & \text{if } D \equiv 1 \bmod 4 \end{cases}$$

It follows that $N(\alpha) \in \mathbb{Z}$, meaning we can relate properties of $\mathbb{Z}$ to the field norm!

For example, we can use this norm to charactetrize the units of $\mathbb{Z}[\omega]$. If $N(\alpha) = \pm 1$, then $(a+b\omega)^{-1} = (a+b\overline{\omega})$, which is an element of $\mathbb{Z}[\omega]$, and so α is a unit. Suppose, conversely, that α is a unit in $\mathbb{Z}[\omega]$, so $\exists \beta$ such that $\alpha\beta = 1$. Then since N is multiplicative,

$$N(\alpha)N(\beta)N(\alpha\beta) = N(1) = \pm 1$$

and since $N(\alpha)$, $N(\beta)$ must be integers, they must be ± 1, and so

$$\text{the element } \alpha \text{ is a unit in } \mathcal{O} \text{ if and only if } N(\alpha) = \pm 1$$

Thus, the field norm also gives us an easy way to find the units of a given ring of integers.

We will be using the field norm to how for certain values of D, $\mathbb{Z}[\sqrt{D}]$ will be a Euclidean Domain, and not for others (ex. we have already shown that $\mathbb{Z}[\sqrt{-1}] = \mathbb{Z}[i]$ is a Euclidean Domain).

Euclidean domain ⇒ PID

As mentioned earlier, Euclidean Domains will be useful to factorizing elements in UFDs in which they are defined. Not all UFDs may have a valuation satisfying the euclidean algorithm, namely since being able to define such a va implies a good deal of structure on the ring. One important consequence of the existence of such a norm is that every Eucildean domain is a PID

Proposition 10.2.7: Euclidean Domain ⇒ Pid

Given a Euclidean domain R, then every ideal of R is a principal ideal, meaning R is also a PID. In particular, if I is an ideal, then $I = (d)$, where d is any nonzero element of I of minimum norm

***Proof*:**
If I is the zero ideal, then we are done, so let $I \neq (0)$. This means that we can choose an element $d \in I$ such that $N(d)$ is a minimum element. This exists since $\{N(a) | a \in I,\ a \neq 0\}$ has a minimum element by the well-ordering of the non-negative integers. We now show that $(d) = I$

($\subseteq$) it's clear that $(d) \subseteq I$ by the definition of ideals

($\supset$) Let $a \in I$ be any element of our ideal. Then since R is a euclidean domain, we can write a as :

$$a = qd + r$$

where $r = 0$ or $N(r) < N(d)$. Since $r = a - qd$, and $a, qd \in I$, then $r \in I$. But then, it's impossible that $N(r) < N(d)$ since $N(d)$ is already the minimal norm!! Thus $r = 0$, implying $a = qd$. But then $a = qd \in (d)$, as we sought to show

As usual, the contra-positive should be kept in mind: R is *not* an Euclidean Domain if it is *not* a PID.

Example 10.2.8: Implications

1. Since $\mathbb{Z}$ is a Euclidean domain, it is A Principal Ideal Domain. Note that we did not show that PID $\Rightarrow$ Euclidean domain, we will present a counter-example soon, so this was only a hint in the right direction
2. $\mathbb{Z}[x]$ is *not* a PID since $(2, x)$ is a non-principal ideal, and so not a euclidean domain.
3. $\mathbb{Q}[x]$ is a PID, and can be shown to be the euclidean domain with $N(p(x)) = \deg(p(x))$
4. $\mathbb{Z}[\sqrt{5}]$ is not a PID, and so not a Euclidean Domain

You might wonder if *all* PID's are euclidean domains. That need not be the case. To prove this, we will first prove a another way of finding Euclidean domains:

Definition 10.2.9: Side Divisor

Let $\overline{R} = R^\times \cup \{0\}$ be the collection of units of R together with 0. An element $u \in R - \overline{R}$ is called a *universal side divisor* if for evry $x \in R$ there is some $z \in \overline{R}$ such that u divides $x - z$ in R, i.e., there is a type of "division algorithm" for u: every x may be written as $x = qu + z$ where z is either zero or a unit.

The existence of universal side divisors is weakening of the Euclidean condition, since we are saying that for any element $x \in R$, we can "divide" it by u and have a remainder of a unit z. These conditions are not as general as the conditions for the euclidean algorihtm (where z does not need to be constrained to be $N(z) = 1$). With this, we prove the following equivalent condition:

Proposition 10.2.10: Euclidean Domain Implies Universal Side Divisors

Let R be an integral domain that is not a field. If R is a euclidean domain, then there are universal side divisors in R

***Proof*:**
Suppose R is Euclidean with respect to some norm N and let u be an element $R - \overline{R}$ (which is non-empty since F is not a field), of minimal norm. For any $x \in R$ write $x = qu + r$ where r is etiher 0 or $N(r) < N(u)$. In either case the minimality of u implies $r \in \overline{R}$. Hence u is a univerasl side divisor in R

With this, we can find

Example 10.2.11: : PID but not euclidean domain

Let $\alpha = \frac{1+\sqrt{-19}}{2}$, and take the following ring of integers.

$$R = \mathcal{O}_{\mathbb{Q}(\sqrt{-19})} = \mathbb{Z}[\alpha] = \{a + b\alpha \mid a, b \in \mathbb{Z}\}$$

Since $\alpha^2 = \alpha - 5$, a product $(a + b\alpha)(c + d\alpha) = (ac - 5bd) + (ad + bc + bd)\alpha$ is again of this form, so R is a subring of $\mathbb{C}$ (corollary 9.1.7) and an integral domain. The complex conjugate of $a + b\alpha$ is $a + b\overline{\alpha}$, and $\alpha + \overline{\alpha} = 1$, $\alpha\overline{\alpha} = 5$, so the field norm is

$$N(a + b\alpha) = (a + b\alpha)(a + b\overline{\alpha}) = a^2 + ab + 5b^2$$

Being the restriction of $z \mapsto z\overline{z} = |z|^2$, it is multiplicative, and it takes values in $\mathbb{N}$. This ring is a PID, a fact shown in example 10.2.15. However, it is not a Euclidean domain, for there does not exist a universal side divisor.

Note that if $b \neq 0$, then

$$a^2 + ab + 5b^2 = \left(a + \frac{b}{2}\right)^2 + \frac{19b^2}{4} \geq \frac{19}{4}$$

so $N(a + b\alpha) \geq 5$, while $N(a) = a^2$. Hence the norm never takes the values 2 and 3, the value 1 is taken exactly at ± 1, and the value 4 exactly at ± 2. A unit u has $N(u)N(u^{-1}) = N(1) = 1$, so $N(u) = 1$, and $\overline{R} = \{0, \pm 1\}$ are the units of R together with 0. In particular R is not a field. If $2 = \beta\gamma$, then $4 = N(\beta)N(\gamma)$, so one of β, γ has norm 1 and is ± 1: the divisors of 2 are ± 1 and ± 2. If $3 = \beta\gamma$, then $9 = N(\beta)N(\gamma)$, and since 3 is not a value of N, again one factor is ± 1: the divisors of 3 are ± 1 and ± 3.

Now suppose $u \in R$ is a universal side divisor (definition 10.2.9). Taking $x = 2$, u divides one of $2 - 0$, $2 - 1$ and $2 + 1$, and it does not divide 1, since it is not a unit. So u is a nonunit divisor of 2 or of 3, that is, $u \in \{\pm 2, \pm 3\}$. Taking $x = \alpha$, u divides one of α, $\alpha - 1$ and $\alpha + 1$, whose norms are 5, 5 and 7. But a multiple $w = qu$ of ± 2 has $N(w) = 4N(q)$ divisible by 4, and a multiple of ± 3 has norm divisible by 9, while neither 4 nor 9 divides 5 or 7. So R has no universal side divisor, and by proposition 10.2.10 it is not a Euclidean domain.

It is tempting to think that PIDs are close to being Euclidean domains as they share a notion of gcd and lcm, unique factorization. The following measure the degree of seperation of a Principal Ideal Domain being a Euclidean Domain:

Definition 10.2.12: Dedikend-Hasse Valuation

Define N to be the *Dedekind-Hasse valuation* if N is a positive norm and for every nonzero $a, b \in R$ either a is an element of the ideal (b) or there is a nonzero elemtn of the ideal (a, b) of norm strictly smaller than the norm of b (i.e., either b divides a in R or their exists $s, t \in R$ such that $0 < N(sa - tb) < N(b)$

Note that R is Euclidean with respect to a positive norm N if it is always possible to satisfy the Dedekind-Hasse norm with $s = 1$, so this is indeed a weakening of our condition for Euclidean Domains.

Proposition 10.2.13: Principal Ideal Domain If And Only If Dedekind-Hasse Norm

Let R be an integral domain.

1. If R has a Dedekind-Hasse valuation, then R is a Principal Ideal Domain.
2. If R is a Principal Ideal Domain, let $n(a)$ be the number of irreducible factors of a nonzero $a \in R$, counted with multiplicity. Then $N(0) = 0$ and $N(a) = 2^{n(a)}$ for $a \neq 0$ define a Dedekind-Hasse valuation on R, and $N(ab) = N(a)N(b)$ for all $a, b \in R$.

In particular, R is a Principal Ideal Domain if and only if it has a Dedekind-Hasse valuation.

***Proof*:**

1. Suppose N is a Dedekind-Hasse valuation on R and let $I \subseteq R$ be an ideal. If $I = 0$ then $I = (0)$, so assume $I \neq 0$ and choose a nonzero $b \in I$ with $N(b)$ minimal, which is possible because N takes positive integer values on nonzero elements and $\mathbb{N}$ is well ordered. Since I is an ideal, $(b) \subseteq I$. For the reverse inclusion take a nonzero $a \in I$. By definition 10.2.12, either $a \in (b)$, or there are $s, t \in R$ with

$$0 < N(sa - tb) < N(b)$$

The second alternative cannot occur: $sa - tb$ lies in I, and $N(sa - tb) > 0$ forces $sa - tb \neq 0$ since $N(0) = 0$, so $sa - tb$ would be a nonzero element of I of norm smaller than $N(b)$, against the choice of b. Hence $a \in (b)$, so $I = (b)$. Every ideal of R is principal, and R is an integral domain by hypothesis, so R is a Principal Ideal Domain.

2. Suppose R is a Principal Ideal Domain. By proposition 10.1.33, R is a Unique Factorization Domain, so every nonzero $a \in R$ may be written $a = up_1p_2 \cdots p_n$ with u a unit, the p_i irreducible, and $n \geq 0$ (the case $n = 0$ being a a unit). By definition 10.1.21 the integer n depends only on a, so

$$N(0) = 0 \qquad N(a) = 2^n \quad \text{for } a \neq 0$$

is well defined, and it is a positive valuation in the sense of definition 10.2.1, since $N(a) \geq 1$ for $a \neq 0$. Counting irreducible factors on both sides of a product shows

$$N(ab) = N(a)N(b)$$

for all $a, b \in R$. In particular a nonzero x is a unit if and only if $N(x) = 1$, and $N(x) \geq 2$ for a nonzero nonunit.

It remains to check the Dedekind-Hasse condition for nonzero $a, b \in R$. The ideal (a, b) is principal, say $(a, b) = (r)$, and $r \neq 0$ because $a \in (r)$ is nonzero. Assume $a \notin (b)$. Since $b \in (r)$ we may write $b = xr$. Here x is not a unit, for otherwise $(b) = (r) \ni a$. So $N(x) \geq 2$ and

$$N(b) = N(x)N(r) \geq 2N(r) > N(r)$$

Finally $r \in (a, b)$ means $r = sa - tb$ for suitable $s, t \in R$, and $0 < N(r) < N(b)$. Thus N is a Dedekind-Hasse valuation on R, completing the proof.

Corollary 10.2.14: Multiplicative Dedekind-Hasse Norm

Let R be a Principal Ideal Domain. Then R has a multiplicative Dedekind-Hasse norm.

***Proof*:**
The valuation N of proposition 10.2.13(2) is a Dedekind-Hasse valuation on R with $N(ab) = N(a)N(b)$ for all $a, b \in R$, completing the proof.

Example 10.2.15: : $\mathbb{Z}[\frac{1+\sqrt{-19}}{2}]$ is a PID

Let $R = \mathbb{Z}[\alpha]$ with $\alpha = \frac{1+\sqrt{-19}}{2}$ and norm $N(a + b\alpha) = a^2 + ab + 5b^2$, as in example 10.2.11. The norm N is a Dedekind-Hasse valuation (definition 10.2.12), so R is a Principal Ideal Domain by proposition 10.2.13(1), and by example 10.2.11 it is a Principal Ideal Domain that is not a Euclidean Domain. The norm takes positive integer values on nonzero elements and $N(0) = 0$, so it remains to check the condition on nonzero $u, v \in R$ with $u \notin (v)$.

Step 1: elements of R and of $K = \{p + q\sqrt{-19} \mid p, q \in \mathbb{Q}\}$. As $a + b\alpha = \frac{(2a+b)+b\sqrt{-19}}{2}$, the ring R consists of the numbers $\frac{m+n\sqrt{-19}}{2}$ with $m, n \in \mathbb{Z}$ of the same parity. In particular $R \subseteq K$, and R contains $\mathbb{Z}[\sqrt{-19}]$. The formula $N(p + q\sqrt{-19}) = p^2 + 19q^2 = |p + q\sqrt{-19}|^2$ extends N to a multiplicative function on K. Every $\gamma \in K$ can be written $\gamma = \frac{a+b\sqrt{-19}}{c}$ with $a, b, c \in \mathbb{Z}$ and $c \geq 1$, and choosing c minimal, a, b and c have no common divisor $d > 1$, since dividing by it would give a smaller denominator.

Step 2: reduction. Let $u, v \in R$ be nonzero with $u \notin (v)$, and put $\gamma = \frac{u}{v} = \frac{u\overline{v}}{N(v)}$. The conjugate $\overline{v}$ lies in R, since $\overline{a + b\alpha} = (a + b) - b\alpha$, so $\gamma \in K$, and $\gamma \notin R$, since $u = \gamma v$ and $u \notin (v)$. Suppose $s, t \in R$ satisfy $0 < N(s\gamma - t) < 1$. Then $su - tv = v(s\gamma - t)$ has

$$0 < N(su - tv) = N(v)N(s\gamma - t) < N(v)$$

which is the Dedekind-Hasse condition. So it suffices to find such s, t for every $\gamma = \frac{a+b\sqrt{-19}}{c} \in K \setminus R$ written as in Step 1. Then $c \neq 1$, since $a + b\sqrt{-19} \in R$.

Step 3: the case $c \geq 5$. The set $I = \{ax + by + cz \mid x, y, z \in \mathbb{Z}\}$ is an additive subgroup of $\mathbb{Z}$ containing $c > 0$. Let d be its least positive element. Dividing an element $e \in I$ by d gives $e = q_1 d + r_1$ with $0 \leq r_1 < d$ and $r_1 = e - q_1 d \in I$, so $r_1 = 0$ and $d \mid e$. In particular d divides a, b and c, so $d = 1$, and $ax + by + cz = 1$ for some $x, y, z \in \mathbb{Z}$. Divide $ay - 19bx$ by c with a remainder of least absolute value, $ay - 19bx = cq + r$ with $q, r \in \mathbb{Z}$ and $|r| \leq c/2$, and put $s = y + x\sqrt{-19}$ and $t = q - z\sqrt{-19}$, both in $\mathbb{Z}[\sqrt{-19}] \subseteq R$. Then

$$s\gamma - t = \frac{(ay - 19bx) + (ax + by)\sqrt{-19}}{c} - q + z\sqrt{-19} = \frac{r + (ax + by + cz)\sqrt{-19}}{c} = \frac{r + \sqrt{-19}}{c}$$

so $N(s\gamma - t) = \frac{r^2+19}{c^2} > 0$. For $c = 5$ the integer r satisfies $|r| \leq 2$, and $N(s\gamma - t) \leq \frac{23}{25} < 1$. For $c \geq 6$, $r^2 \leq \frac{c^2}{4}$ and $19 \leq \frac{19c^2}{36}$, so $N(s\gamma - t) \leq \frac{1}{4} + \frac{19}{36} = \frac{7}{9} < 1$.

Step 4: the cases $c = 2, 3, 4$. Squares of integers are 0 or 1 modulo 3, with 0 exactly for multiples of 3, and the square of an odd integer $2k + 1$ is $4k(k + 1) + 1 \equiv 1 \bmod 8$.

- $c = 2$: a and b are not both even, and not both odd, since $\gamma \notin R$ (Step 1). So $a - 1$ and b have the same parity, $t = \frac{(a-1)+b\sqrt{-19}}{2}$ lies in R, and $s = 1$ gives $s\gamma - t = \frac{1}{2}$, of norm $\frac{1}{4}$.

- $c = 3$: a and b are not both multiples of 3, so $a^2 + 19b^2 \equiv a^2 + b^2 \bmod 3$ is not divisible by 3. Write $a^2 + 19b^2 = 3q + r$ with $r \in \{1, 2\}$, and put $s = a - b\sqrt{-19}$ and $t = q$. Then $s\gamma = \frac{a^2+19b^2}{3}$, so $s\gamma - t = \frac{r}{3}$, of norm $\frac{r^2}{9} \leq \frac{4}{9}$.
- $c = 4$: a and b are not both even. If exactly one of them is odd, then $a^2 + 19b^2 = 4q + r$ with $r \in \{1, 3\}$, and $s = a - b\sqrt{-19}$, $t = q$ give $s\gamma - t = \frac{r}{4}$, of norm at most $\frac{9}{16}$. If both are odd, then $a^2 + 19b^2 \equiv 1 + 19 \equiv 4 \bmod 8$, say $a^2 + 19b^2 = 8q + 4$, and $s = \frac{a-b\sqrt{-19}}{2} \in R$, $t = q$ give $s\gamma = \frac{a^2+19b^2}{8} = q + \frac{1}{2}$, so $s\gamma - t = \frac{1}{2}$, of norm $\frac{1}{4}$.

In every case $0 < N(s\gamma - t) < 1$, so N is a Dedekind-Hasse valuation and R is a Principal Ideal Domain.


10.3 Application: Sums of Primes and Gaussian Integers

Let us use the theory we have developed to get our first result about prime numbers, namely let us classify all prime numbers that can be written as the sum of two squares $p = x^2 + y^2$. [6]

Recall that the Gaussian integers are of the form:

$$\mathbb{Z}[i] \subseteq \mathbb{C}$$


which can be thought of as the smallest ring containing $\mathbb{Z}$ and i. The Gaussian integers have a pretty geometric picture as a lattice:



The Gaussian Integers $\mathbb{Z}[i]$

[6] A prime p is never the square of an integer, but it may be congruent to a square modulo another prime q, in which case p is called a *quadratic residue* modulo q. For distinct odd primes p and q, the law of *quadratic reciprocity* relates whether p is a square modulo q to whether q is a square modulo p (section 50.4.6). This section needs a single such residue: the proof of theorem 10.3.3 reduces the question to whether -1 is a square modulo p.

This gives us a geometric picture of this ring! For example, we may visualize principal ideals in this grid, for example the ideal $(2+i)$ is the point:



The Gaussian Integers $\mathbb{Z}[i]$ with $(2+i)$ highlighted

Recall how we introduced the field-norm on on quadratic integers, where $\mathbb{Z}[i] = \mathbb{Z}[\sqrt{-1}]$ is an example of quadratic integers. With the above visuals, it is more clear to see that the field norm has similar geometric information to the norm presented in real or complex analysis, namely:

$$N(a+bi) = (a+bi)(a-bi) = a^2 + b^2 = \|a+bi\|^2$$

Using the fact that the codomain of the field norm is $\mathbb{N}_{\geq 0}$, we can see that the norm is in fact a euclidean valuation

Lemma 10.3.1: Gaussian Integers Are Euclidean Domain

Let $R = \mathbb{Z}[i]$ and N be the field norm. Then N is a Euclidean valuation. Furthermore, N is multiplicative so that for every $z, w \in \mathbb{Z}[i]$,

$$N(zw) = N(z)N(w)$$

***Proof*:**
For $\alpha \in \mathbb{C}$ put $N(\alpha) = \alpha\overline{\alpha} = |\alpha|^2$, which extends the norm of $\mathbb{Z}[i]$ since $(a+bi)(a-bi) = a^2+b^2$. Complex conjugation satisfies $\overline{\alpha\beta} = \overline{\alpha}\,\overline{\beta}$, so for all $\alpha, \beta \in \mathbb{C}$

$$N(\alpha\beta) = \alpha\beta\,\overline{\alpha}\,\overline{\beta} = (\alpha\overline{\alpha})(\beta\overline{\beta}) = N(\alpha)N(\beta)$$

and the case $\alpha, \beta \in \mathbb{Z}[i]$ is the multiplicativity claim.

The ring $\mathbb{Z}[i]$ is an integral domain, being a subring of the field $\mathbb{C}$, and N takes values in $\mathbb{N}_{\geq 0}$ with $N(0) = 0$, so it is a valuation as required in definition 10.2.4. Let $z, w \in \mathbb{Z}[i]$ with $w \neq 0$, so that $N(w) > 0$. Write $z\overline{w} = m + ni$ with $m, n \in \mathbb{Z}$. In $\mathbb{C}$,

$$\frac{z}{w} = \frac{z\overline{w}}{w\overline{w}} = \frac{m}{N(w)} + \frac{n}{N(w)}\,i = x + yi$$

with $x, y \in \mathbb{Q}$. Choose integers s and t nearest to x and y, so that $|x-s| \leq \frac{1}{2}$ and $|y-t| \leq \frac{1}{2}$, and put $q = s + ti \in \mathbb{Z}[i]$ and $r = z - qw \in \mathbb{Z}[i]$. Then $z = qw + r$, and in $\mathbb{C}$

$$r = w\left(\frac{z}{w} - q\right) = w\big((x-s) + (y-t)i\big)$$

so that, by multiplicativity,

$$N(r) = N(w)\left((x-s)^2 + (y-t)^2\right) \leq N(w)\left(\frac{1}{4} + \frac{1}{4}\right) = \frac{N(w)}{2} < N(w)$$

Hence $r = 0$ or $N(r) < N(w)$, and N is a Euclidean valuation on $\mathbb{Z}[i]$ (definition 10.2.4), completing the proof.

What could be more insightful is to understand using the lattice picture the significant of the field norm on $\mathbb{Z}[i]$ (this was demonstrated in Aluffi's textbook see [3]). Take $z, w \in \mathbb{Z}[i]$ with $w \neq 0$ nd consider the lattice given by (w). Then either z lies on a point in this lattice, in which case $z = qw$ for appropriate q, or z is inside a "box" of the lattice. Pick some points qw that is a vertex of the box containing z, and set $r = z - qw$ so that $z = qw + r$. By visual inspection, we see that the length of r is ells than that of r, namely:

$$N(r) < N(w)$$

This trick shall not work for all quadratic fields, as we shall demonstrates after finishing elaborating on Gaussian integers.

If u is a unit, then $N(u)N(u^{-1}) = N(1) = 1$ with both factors non-negative integers, so $N(u) = 1$, and conversely $N(u) = u\overline{u} = 1$ exhibits $\overline{u}$ as an inverse of u. As $a^2 + b^2 = 1$ forces $(a, b) = (\pm 1, 0)$ or $(0, \pm 1)$, the units are exactly $1, -1, i, -i$. We can use the norm to also detect irreducible elements. To see this, let' say $p \in \mathbb{Z}$ is a prime. Then since $\mathbb{Z}$ is an integral domain, p is irreducible, and so $p = ab$ if and only if a or b is a unit. Let's now take $\pi \in \mathcal{O}$ such that $p = N(\pi)$. If $\pi = \alpha \cdot \beta$, then:

$$p = N(\pi) = N(\alpha)N(\beta)$$

meaning either $N(\alpha)$ or $N(\beta)$ is a unit, meaning it's value is ± 1. Thus, we have that

$$\text{If } N(\alpha) \text{ is } \pm p \text{ for a prime } p \in \mathbb{Z}, \text{ then } \alpha \text{ is irreducible (even prime) in } \mathbb{Z}[i]$$

The converse is not necessarily true: we can have a prime in $\mathbb{Z}[i]$ but it's norm is not p. Fortunately, this is a feature of primes in $\mathbb{Z}[i]$ and demonstrates a deeper insight on the structure of primes in $\mathbb{Z}[i]$:

Lemma 10.3.2: Gaussian Integers Norm of Primes

Let $\pi \in \mathbb{Z}[i]$ be a prime element. Then

$$N(\pi) \in \{p, p^2\}$$

for appropriate prime $p \in \mathbb{Z}$, which can be chosen so that π divides p in $\mathbb{Z}[i]$.

Fermat's theorem of sum of square (theorem 10.3.3) shall show that both p and p^2 show up as norms of primes.

***Proof*:**
Let $\pi \in \mathbb{Z}[i]$ be a prime element, that is, (π) is a prime ideal in $\mathbb{Z}[i]$. As π is not a unit, $N(\pi) \neq 1$, so the integer $N(\pi) = \pi\overline{\pi} \geq 2$ is a product of prime numbers (corollary 10.1.34). The prime element π divides this product, so by induction on the number of factors it divides one of them, say p.

Now, take $(p) \subseteq \mathbb{Z}[i]$. Then $(p) \subseteq (\pi)$ so that $p = x\pi$ for some $x \in \mathbb{Z}[i]$ (which may be a unit, as p may be an associate of π). Then $N(p) = p^2$, and since the norm is multiplicative, $p^2 = N(x)N(\pi)$ and

$$N(\pi)\big|N(p) = p\overline{p} = pp = p^2$$

so $N(\pi) \in \{1, p, p^2\}$, and $N(\pi) \neq 1$ gives $N(\pi) \in \{p, p^2\}$, completing the proof.

Irreducible does not imply prime. In $\mathbb{Z}[\sqrt{-5}]$, with norm $N(a + b\sqrt{-5}) = a^2 + 5b^2$, the element $1 + \sqrt{-5}$ has norm 6. It is irreducible, since a proper factor would have norm 2 or 3, and $a^2 + 5b^2$ takes neither value. It is not prime: it divides $2 \cdot 3 = (1 + \sqrt{-5})(1 - \sqrt{-5})$ but neither 2 nor 3, as 6 divides neither $N(2) = 4$ nor $N(3) = 9$. The argument above applies to a *prime* element π of any quadratic ring $\mathbb{Z}[\sqrt{d}]$ with norm $N(a + b\sqrt{d}) = a^2 - db^2$: π divides $N(\pi) = \pi\overline{\pi}$, hence some prime p of $\mathbb{Z}$, and so $N(\pi) = \pm p$ or $\pm p^2$. For irreducible elements that are not prime it can fail, as $N(1 + \sqrt{-5}) = 6$ shows. Under the right framework, this connection can be made more precise, which will be part of the aim of chapter 50.


Let us find some examples of primes with norms p and p^2. Let's take $\alpha = a + bi \in \mathbb{Z}[i]$ to be prime. Then $N(\alpha) = \alpha\overline{\alpha} = a^2 + b^2 \in \{p, p^2\}$. If p is reducible in $\mathbb{Z}[i]$,then

$$p = \pi\pi' \qquad \Rightarrow \qquad N(p) = N(\pi)N(\pi') = p^2$$

Thus, p will factor in $\mathbb{Z}[i]$ into two irreducibles if and only if $p = a^2 + b^2$, that is, p is the sum of two integers squares. If p is not the sum of two integer squares, it will remain irreducible. Take or example $3 \in \mathbb{Z}[i]$. Then $N(3) = 9$, and if 3 factored we would need an element $a + bi$ such that $N(a+bi) = a^2+b^2 = 3$ for natural numbers $a, b \in \mathbb{N}$. However, it can be quickly verified that no such numbers exist, and so 3 is prime in $\mathbb{Z}[i]$. For another example, take 2. Then as $2 = 1^2 + 1^2$, 2 factors in $\mathbb{Z}[i]$! In particular, $2 = (1 + i)(1 - i) = -i(1 + i)^2$ (note that $N(-i) = 1$ and so these two are associates). This will be the only case were conjugate irreducibles $a + bi$ and $a - bi$ can be associate. Let us next consider 5, so we need to see if there is an element $a + bi$ such that $N(a + bi) = 5$, and indeed:

$$N(2 + 1 \cdot i) = 2^2 + (1)^2 = 5$$

from which we find $5 = (2+i)(2-i)$. This factorization picture can be seen more clearly when viewing this elements via their ideals in the lattice. In the case of 3, there is no possible further refinement that can be done to the lattice, while for 5 we may further refine the lattice (without it being the entire lattice):



Let us now find a condition that shall let us immediately tell if a prime can splits in $\mathbb{Z}[i]$. First, any number in $\mathbb{Z}$ is congruent to $0, 1, 2, 3 \bmod (4)$. Therefore, the square of any number is congruent to either 0 or 1. The possible sums of square are thus $0, 1, 2 \bmod 4$. If the sum is $0, 2 \bmod 4$, then it is even, so a prime $p = a^2 + b^2$ of this kind is $p = 2$. Thus an odd prime (so $p > 2$) in $\mathbb{Z}$ that is the sum

of two squares must be congruent to 1 mod 4 (ex. 5). Therefore, if $p \equiv 3 \bmod 4$ in $\mathbb{Z}$, then p is *not* the sum of squares, and remains irreducible (and thus prime) in $\mathbb{Z}[i]$.

Theorem 10.3.3: Fermat's Theorem on Sums Of Squares

The prime p is the sum of two integer squares, $p = a^2 + b^2$, $a, b \in \mathbb{Z}$ if and only if $p = 2$ or $p \equiv 1 \bmod 4$. Except for interchanging a and b or changing the sign of a and b, the representation of p as a sum of two squares is unique.

Furthermore, up to multiplication by the units $\pm 1, \pm i$, the prime elements in the Gaussian integers $\mathbb{Z}[i]$ are as follows:

1. $1 + i$ (which has norm 2)
2. the primes $p \in \mathbb{Z}$ with $p \equiv 3 \bmod 4$ (which have norm p^2)
3. $(a+bi)$, $(a-bi)$, the two non-associate irreducible factors of $p = a^2+b^2 = (a+bi)(a-bi)$ for the primes $p \in \mathbb{Z}$ with $p \equiv 1 \bmod 4$ (both of which have norm p).

In other words, each prime $p \equiv 1 \bmod 4$ can be written as the sum of two squares:

$$p = a^2 + b^2$$

***Proof*:**

The ring $\mathbb{Z}[i]$ is a Euclidean domain (lemma 10.3.1), hence a Principal Ideal Domain (proposition 10.2.7), in which irreducible and prime elements coincide (proposition 10.1.33). Its units are the elements of norm 1, since $uv = 1$ gives $N(u)N(v) = 1$ in $\mathbb{N}$ and $N(u) = u\overline{u} = 1$ exhibits an inverse of u, and the solutions of $a^2 + b^2 = 1$ give the units $\pm 1, \pm i$. An element π whose norm is a prime number q is irreducible: it is not a unit, and if $\pi = \alpha\beta$, then $q = N(\alpha)N(\beta)$, so α or β has norm 1 and is a unit.

Step 1: a prime $p = a^2 + b^2$ is 2 or $\equiv 1 \bmod 4$. The squares $(2k)^2 = 4k^2$ and $(2k+1)^2 = 4k(k+1)+1$ are 0 or 1 modulo 4, so $a^2 + b^2$ is 0, 1 or 2 modulo 4. An odd sum is therefore 1 modulo 4, and an even prime is 2. Conversely $2 = 1^2 + 1^2$.

Step 2: if $p \equiv 1 \bmod 4$, then p divides $n^2 + 1$ for some $n \in \mathbb{Z}$. Write $p = 4k + 1$. The group $(\mathbb{Z}/p\mathbb{Z})^\times$ of definition 1.2.5 consists of the classes of $1, 2, \ldots, p-1$, all coprime to the prime p. A class $\overline{x}$ with $1 \leq x \leq p-1$ equals its own inverse exactly when p divides $x^2 - 1 = (x-1)(x+1)$. This happens for $x = 1$ and $x = p-1$, and for no $2 \leq x \leq p-2$, since then $x-1$ and $x+1$ lie between 1 and $p-1$, so p divides neither, nor their product (corollary 0.2.12). The classes $\overline{1}$ and $\overline{p-1} = \overline{-1}$ are distinct as $p > 2$, and the remaining classes fall into pairs $\{\overline{x}, \overline{x}^{-1}\}$ of distinct classes with product $\overline{1}$. As $(\mathbb{Z}/p\mathbb{Z})^\times$ is abelian, the product of all its elements is therefore $\overline{1} \cdot \overline{-1} = \overline{-1}$, that is, $(p-1)! \equiv -1 \bmod p$. Since $p - j \equiv -j \bmod p$,

$$(p-1)! = \prod_{j=1}^{2k} j \cdot \prod_{j=1}^{2k} (p-j) \equiv (-1)^{2k} \big((2k)!\big)^2 = \big((2k)!\big)^2 \bmod p$$

So $n = (2k)!$ satisfies $n^2 \equiv -1 \bmod p$, that is, $p \big| n^2 + 1$.

Step 3: if $p \equiv 1 \bmod 4$, then p is a sum of two squares. With n from Step 2, p divides $n^2 + 1 = (n + i)(n - i)$ in $\mathbb{Z}[i]$, but it divides neither factor, since $\frac{n}{p} \pm \frac{1}{p}i \notin \mathbb{Z}[i]$. So p is not prime, hence not irreducible, in $\mathbb{Z}[i]$. It is nonzero and not a unit, as $N(p) = p^2$, so $p = \alpha\beta$ with α, β not units. Then $p^2 = N(\alpha)N(\beta)$ with $N(\alpha), N(\beta) \neq 1$, so $N(\alpha) = p$, and writing $\alpha = a + bi$ gives $p = a^2 + b^2$. With Step 1, this proves the first claim.

Step 4: uniqueness. Let $p = a^2 + b^2 = c^2 + d^2$. The element $\pi = a + bi$ has norm p, so it is irreducible and hence prime. It divides $p = (c + di)(c - di)$, so it divides $c + di$ or $c - di$, say $c + \epsilon di = \pi\gamma$ with $\epsilon = \pm 1$. Comparing norms, $p = pN(\gamma)$, so γ is a unit, and $c + \epsilon di$ is one of $\pm(a + bi)$ and $\pm i(a + bi) = \pm(-b + ai)$. Hence (c, d) is obtained from (a, b) by interchanging the two entries and changing signs.

Step 5: the prime elements of $\mathbb{Z}[i]$. The elements listed are prime. The norm of $1 + i$ is 2, and the elements $a \pm bi$ in (3) have norm p, so they are irreducible, hence prime. If $p \equiv 3 \bmod 4$ and $p = \alpha\beta$ with α, β not units, then $N(\alpha) = p$ as in Step 3, and p would be a sum of two squares, against Step 1. So p is irreducible, hence prime. In (3), the associates of $a + bi$ are $\pm(a + bi)$ and $\pm(-b + ai)$, and $a - bi$ equals one of them only if $b = 0$, $a = 0$ or $a = \pm b$, which would make the odd prime $p = a^2 + b^2$ a square or twice a square. So $a + bi$ and $a - bi$ are not associates.

Conversely, let π be a prime element. By lemma 10.3.2, $N(\pi) \in \{p, p^2\}$ for a prime p with $\pi | p$. If $N(\pi) = p$, then $\pi = a + bi$ with $a^2 + b^2 = p$, so $p = 2$ or $p \equiv 1 \bmod 4$ by Step 1. For $p = 2$, π is one of $\pm 1 \pm i$, the associates $1 + i$, $i(1 + i)$, $-(1 + i)$ and $-i(1 + i)$ of $1 + i$. For $p \equiv 1 \bmod 4$, $\pi = a + bi$ is one of the elements in (3). If $N(\pi) = p^2$, write $p = \pi\gamma$. Then $N(\gamma) = 1$, so π is an associate of p, and p is prime in $\mathbb{Z}[i]$. Then p is not a sum of two squares, for $p = (a + bi)(a - bi)$ would be a product of two elements of norm p, which are not units. So $p \neq 2$ and $p \not\equiv 1 \bmod 4$ by Step 3, that is, $p \equiv 3 \bmod 4$, completing the proof.

Lemma 10.3.4: Writing p as $n^2 + 1$

The prime number $p \in \mathbb{Z}$ divides an integer of the form $n^2 + 1$ if and only if p is either 2 or is an odd prime congruent to 1 mod 4.

***Proof*:**

The prime 2 divides $1^2 + 1$. If $p \equiv 1 \bmod 4$, then $p = a^2 + b^2$ by theorem 10.3.3. Here a and b are nonzero, since a prime is not a square, so $0 < b^2 < p$ and $p \nmid b$. Hence $\gcd(b, p) = 1$, and the class of b lies in the group $(\mathbb{Z}/p\mathbb{Z})^\times$ (definition 1.2.5). Choose b' with $bb' \equiv 1 \bmod p$ and put $n = ab'$. Then

$$n^2 + 1 \equiv a^2b'^2 + b^2b'^2 = b'^2p \equiv 0 \bmod p$$

so $p | n^2 + 1$.

Conversely, let p be an odd prime dividing $n^2 + 1$. In $\mathbb{Z}[i]$, p divides $n^2 + 1 = (n + i)(n - i)$ but neither factor, since $\frac{n}{p} \pm \frac{1}{p}i \notin \mathbb{Z}[i]$, so p is not a prime element of $\mathbb{Z}[i]$. By theorem 10.3.3(2), the primes congruent to 3 modulo 4 are prime elements of $\mathbb{Z}[i]$, so $p \not\equiv 3 \bmod 4$, and the odd prime p is congruent to 1 modulo 4, as we sought to show.

Though this condition is equivalent to Fermat's Theorem on Sums of Squares, it is not as informative: $5|3^2+1=10$, however $3+i$ and $3-i$ are *not* prime (for example, $3+i=(1+i)(2-i)$). There is however something very interesting that was demonstrated in this entire section: we have answered a purely number theoretic question about which primes can be expressible as sums of squares (a fact that should at first not be so obvious) by taking advantage of a lot of simple theoretical properties built-up about factorization and of the group $(\mathbb{Z}/p\mathbb{Z})^\times$!

10.3.5 Foreshadowing Fermat's Theorem of sums of two squares will be generalized to the factorization of any polynomial over any finite extension of a ring (theorem 50.4.7), though the strategy of writing a prime p as some polynomial expression is in general more difficult.

Exercise 10.3.1

1. Find all integer solutions of $y^2=x^3-1$ by factoring y^2+1 in $\mathbb{Z}[i]$.

11

Exploring Polynomial Rings

When first studying algebra, we often looked to find solutions to linear and quadratic equations:

$$ax + b = 0 \qquad ax^2 + bx + c = 0$$

This naturally generalizes to polynomial of higher degree. In pre-abstract algebra, solutions to such equations where usually limited to $\mathbb{R}$, probably $\mathbb{C}$. We have now developed the abstraction to consider the value (or root) of such a polynomial for an arbitrary ring R, that is for an arbitrary polynomial in $R[x]$, does there exist an element $r \in R$ such that

$$p(r) = 0$$

As is the usual strategy in algebra, we generalize a problem into an algebraic object, in this case the polynomial ring $R[x]$, and look for interesting properties of the objects and tools we can use to manipulate the object. Such polynomials rings are paramount to study. To give an idea of their importance:

1. they arbitrarily approximate continuous functions on compact neighborhoods
2. all complex differentiable function can be locally be represented as infinite polynomials (i.e. they are analytic)
3. All relations in rings are represented by polynomial (similarly to how all relations in a group is represented by a monomial)

The last point shows that polynomial rings are used to "locally" represent rings, namely through the universal property of [commutative] universal rings (see theorem 9.2.4). It may thus seem natural to consider studying polynomials rings themselves to see what properties we may deduce from them.

One necessary limitation of the exploration of polynomial rings in chapter is that we shall not look at finding solutions to polynomials, we shall rather look at the structure of polynomial rings. The

reason for this is that it is in fact a much more difficult task to find solutions requiring more build-up that starts venturing into the domain of algebraic geometry. The beginnings of this effort shall be presented in chapter 31.

It must be noted that we shall further develop on polynomial rings in *Commutative Algebra* [20]. This exploration is left to that book since it is not necessary to cover some results until much later.

Note that this chapter shall use some exercises from exercise set 9.3.1, most importantly:

Proposition 11.0.1: Ideals of Polynomial Ring wrt. R

Let $I \subseteq R$ be an ideal. Then:

$$(R[x])/(IR[x]) \cong (R/I)[x]$$

***Proof*:**
Let $\pi\colon R[x] \to (R/I)[x]$ reduce every coefficient modulo I, $\sum_i a_i x^i \mapsto \sum_i (a_i + I)x^i$. It preserves sums, and products because the coefficients of a product, $\sum_j a_j b_{i-j}$, are sums of products of coefficients and $R \to R/I$ is a ring homomorphism. It sends 1 to 1 and is surjective. Its kernel is the set of polynomials with every coefficient in I, which is $IR[x]$: every element $\sum a \cdot f$ ($a \in I$, $f \in R[x]$) of $IR[x]$ has its coefficients in I, and $\sum_i a_i x^i$ with every $a_i \in I$ is the sum of the elements $a_i \cdot x^i$ of $IR[x]$. Theorem 9.3.12 gives the isomorphism.

11.1 Polynomial Rings over Fields

We will now explore polynomial rings with coefficients from a field $\mathbb{F}$. The first question we may ask if what type of ring is $\mathbb{F}[x]$? It's not a field, since we already saw that x is not invertible (meaning it's also not a division ring). The next strongest ring we know is Euclidean domains. If $\mathbb{F}[x]$ is a euclidean domain, there must be a norm we define, which we will use $N(p(x)) = \deg(p(x))$ (the usual polynomial norm). Then $\mathbb{F}[x]$ is indeed a Euclidean Domain:

Theorem 11.1.1: Field Then $\mathbb{F}[x]$ Is Euclidean Domain

Let $\mathbb{F}$ be a field. The $\mathbb{F}[x]$ is a Euclidean Domain. In particular, if $a(x)$ and $b(x)$ are two polynomials in $\mathbb{F}[x]$ with $b(x)$ nonzero, then there are *unique* $q(x)$ and $r(x)$ such that

$$a(x) = q(x)b(x) + r(x_0) \qquad \text{with} \qquad r(x) = 0 \text{ or } \deg(r(x)) < \deg(b(x))$$

***Proof*:**
First, the edge cases:

If $a(x)$ is the zero polynomial, then let $q(x) = r(x) = 0$. So let $a(x)$ be a nonzero polynomial. Let $b(x)$ be an arbitrary other polynomial. If $\deg(a(x)) < \deg(b(x))$, then let $q(x) = 0$ and $r(x) = a(x)$.

Now, take the nonzero polynomial $a(x)$ such that $\deg(a(x)) > \deg(b(x))$. We will do a proof by induction on the degree of $a(x)$ ($n = \deg(a(x))$).

For visualization, we can denote $a(x)$ and $b(x)$ as:

$$a(x) = a_n x^n + a_{n-1}x^{n-1} + \cdots + a_0 \qquad b(x) = b_m x^m + b_{m-1}x^{m-1} + \cdots + b_0$$

We want to apply the induction hypothesis. Let $a'(x) = a(x) - \frac{a_n}{b_m}x^{n-m}b(x)$, which purposely defined to eliminate the monomial of degree n from $a(x)$. Then by the induciton hypothesis:

$$a'(x) = q'(x)b(x) + r(x) \qquad r(x) = 0 \text{ or } \deg(r(x)) < \deg(p(x))$$

Then, we "reverse" the step of taking $a'(x)$ by doing $q(x) = q'(x) + \frac{a_n}{b_n}x^{n-m}$, which will give us

$$a(x) = q(x)b(x) + r(x) \qquad r(x) = 0 \text{ or } \deg(r(x)) < \deg(p(x))$$

showing we can factor two polynomials.

It remains to show that this factorization is unique. Suppose $q(x), r(x)$, and $q_0(x)$, $r_0(x)$ are both polynomials that satisfy the euclidean condition. Then

$$a(x) - q(x)b(x) \qquad a(x) - q_0(x)b(x)$$

are both of degree less than m. The difference between these two polynomials then:

$$b(x)(q(x) - q_0(x))$$

is also less than m. But the degree of product of polynomials over an integral domain is the sum of their degree ($m > \deg(b(x)(q(x) - q_0(x))) = \deg(b(x) + \deg(q(x) - q_0(x))$. So, $q(x) - q_0(x) = 0$, implying $q(x) = q_0(x)$. This then implies $r(x) = r_0(x)$, completing the proof of uniqueness

Corollary 11.1.2: Field Then $\mathbb{F}[x]$ PID And UFD

Let $\mathbb{F}$ be a field. The $\mathbb{F}[x]$ is a Principal Ideal domain, and a Euclidean Domain

***Proof*:**
By the previous theorem (theorem 11.1.1), we know $\mathbb{F}[x]$ is a euclidean domain. By proposition 10.2.7, it is a Principal Ideal Domain, and since PID's are UFD's, it is also a Unique Factorization Domain

Example 11.1.3

1. $\mathbb{Q}[x]$ is a Principal Ideal Domain since $\mathbb{Q}$ is a field.
2. $\mathbb{Q}[x, y]$ is not a Principal Ideal Domain, since $\mathbb{Q}[x]$ is not a field (using the contra-positive).

One final consequence of $\mathbb{F}[x]$ being a Principal Ideal Domain:

Corollary 11.1.4: Kernel Of Evaluation Map

Let $\mathbb{F}$ be a field and let α be an element of $\mathbb{F}$. Then the kernel of ev_α is the ideal $(x - \alpha)$

***Proof*:**
Let $I = \ker(\text{ev}_\alpha)$. By definition of ev_α, $x - \alpha \in I$. Now, since $\mathbb{F}$ is a field, $\mathbb{F}[x]$ is a Euclidean Domain, and thus a Principal Ideal Domain, so I is a principal ideal. Let's say $I = (p)$ for some $p \in \mathbb{F}[x]$. Then by definition, $x - \alpha = up$, meaning $p|x - \alpha$. Note that p cannot have degree higher than 2, since then $x - \alpha \notin I$. So, if p has degree one, then the two elements are associates, meaning $I = (p) = (up) = (x - \alpha)$. If p has degree 0, then it must be a constant. However, p has a root at α, so if p were a constant, it would have to be 0. But then $x - \alpha \notin (0)$, a contradiction. Therefore $(x - \alpha) = \ker(\text{ev}_\alpha)$.

Here is also a fun result I want to put down:

Example 11.1.5: generalization of Famous infinite primes proof
Let F be a finite field. Then there are infinitely many prime elements in $F[x]$

Proof. Let's assume there is a finite amount. Then $p_1, ..., p_n$ is our list of irreducible polynomials. Note that $\deg(p_i) \geq 1$ for each polynomial. Then take $P = p_1 p_1 \cdots p_n + 1$. Then $\deg(P) \geq 1$, and so P is not a unit or 0. Therefore, P must be divisible by some p_i, meaning $p_i|P$, which implies $qp_i = P$, or equivalently $P \in (p_i)$. Next, by closure of ideals, $-p_1 p_2 \cdots p_n \in (p_i)$. Then, by closure under addition:

$$P - p_1 p_2 \cdots p_n = p_1 p_2 \cdots p_n + 1 - p_1 p_2 \cdots p_n = 1 \in (p_i)$$

meaning $up_i = 1$ for appropriate $u \in F[x]$, implying p_i is a unit! However, prime elements are *not* units. Since p_i was arbitrary, *no* p_i can divide P. But then, P will have non of the factor's in it's factorization, a contradiction to deg > 0 and the p_i's being the only irreducibles! Therefore, P must be a new prime number!

Therefore, there is an infinite number of prime numbers. □

We finish off with an application of the Chinese remainder theorem with the new fact that $k[x]$ is a Euclidean domain, and hence a UFD:

Proposition 11.1.6: Chinese Remainder On Polynomials

Let $g(x)$ be a nonconstant monic element of $k[x]$ and let

$$g(x) = f_1(x)^{n_1} f_2(x)^{n_2} \cdots f_k(x)^{n_k}$$

be its factorization into irreducibles, where the $f_i(x)$ are distinct. Then we have the following isomorphism of rings:

$$k[x]/(g(x)) \cong k[x]/(f_1(x)^{n_1}) \times k[x]/(f_2(x)^{n_2}) \times \cdots \times k[x]/(f_k(x)^{n_k})$$

***Proof*:**
This follows from the Chinese Remainder Theorem (theorem 9.6.11) and corollary 10.1.36, but we will re-state it here. Since $(f_i(x)^{n_i})$ and $(f_i(x)^{n_i})$ are comaximal if $f_i(x)$ and $f_j(x)$ are distinct (they are relatively prime in the Euclidean Domain $k[x]$, hence $gcd(f_i^{n_i}, f_j^{n_j}) = 1$, and so $p(x)f_i(x)^{n_i} + q(x)f_j(x)^{n_j} = 1$, so $1 \in (f_i^{n_i}) + (f_j^{n_j})$ implying $(f_i^{n_i}) + (f_j^{n_j}) = k[x]$ by proposition 9.4.10).

Exercise 11.1.1

1. Let $R[x]$ be a Principal Ideal Domain. Show that $R[x]$ is a Euclidean Domain.

11.2 Polynomial Rings over UFD's

We have seen R is an integral domain then $R[x]$ is an integral domain. We have also seen that if R is an integral domain, than we can embed R into a field of fraction F (see section 9.5). This means that $R[x] \subseteq F[x]$. Furthermore, since F is a field, then $F[x]$ is a euclidean domain. With this, we can do lots of our computation in $F[x]$ instead of $R[x]$, at the expense of allowing fractional coefficients. The question then arises if we can use information from $F[x]$ to gain information about $R[x]$!

For example, take a polynomial $p(x) \in R[x]$. Since $p(x) \in k[x]$, and $k[x]$ is a Unique Factorization Domain, then $p(x)$ factors in $k[x]$ into irreducibles. We can then ask if $p(x)$ will factor in $R[x]$. The answer is no in general, since $R[x]$ is not always a Unique Factorization Domain, since that would imply R is a Unique Factorization Domain since the coefficients of $R[x]$ must also factor uniquely. However, if R were a unique factorization domain, then this will imply that $R[x]$ is a Unique Factorization Domain! Hence, factoring in $k[x]$ gives information on how we factor in $R[x]$. The way we will prove this is first by uniquely factoring in $k[x]$, then "clear denominators" to obtain unique factorization in $R[x]$!

The first thing to do is make precise the notion of comparing factorization of a polynomial in $k[x]$ and a factorization in $R[x]$

Proposition 11.2.1: Gauss's Lemma

Let R be a Unique Factorization Domain with field of fraction K and let $p(x) \in R[x]$. If $p(x)$ is reducible in $K[x]$ then $p(x)$ is reducible in $R[x]$. More precisely, if $p(x) = A(x)B(x)$ for some non constant polynomials $A(x), B(x) \in K[x]$, then there are nonzero elements $r, s \in F$ such that $rA(x) = a(x)$ and $sB(x) = b(x)$, such that $a(x), b(x) \in R[x]$ and $p(x) = a(x)b(x)$ is a factorization in $R[x]$

A concrete case that can be kept in mind is with the polynomials $p(x), q(x) \in \mathbb{Q}[x]$, then $rp(x), sq(x) \in \mathbb{Z}[x]$ for appropriates $r, s \in \mathbb{Q}$. Note that it is possible that $q(x) \in \mathbb{Q}$, i.e. $q(x)$ is a constant polynomial[1].

***Proof*:**
Let's say $p(x) \in k[x]$ and is reducible $p(x) = A(x)B(x)$. Then the coefficients of $p(x)$ are quotients from R. Since R is a Unique Factorization Domain, let's take d a number common betewen all denominators for all the coefficients of $A(x)B(x)$, so that we can obtain

$$dp(x) = a'(x)b'(x)$$

where $a'(x), b'(x)$ are now in $R[x]$ since we multiplied away the denominators with d! If d is a unit, then

$$a(x) = d^{-1}a'(x) \qquad b(x) = b'(x)$$

[1] In textbooks where the contra-positive of this statement is used, it is often specified that $p(x)$ is *primitive*, meaning for all principal prime $\mathfrak{p} \subseteq R$, $p(x) \notin \mathfrak{p}R[x]$. In the UFD case, this amounts to the gcd of the coefficients being 1

which completes the proof, so let's assume d is not a unit. Since $d \in R$, and R is a Unique Factorization Domain, then there is a unique factorization into irreducibles:

$$d = p_1 \cdots p_n$$

Since p_1 is an irreducible element, and R is a Unique Factorization Domain, then $(p_1) = p_1 R[x]$ (since $R[x]$ is commutative $(a) = aR$) is prime (exercise), and so $R[x]/p_1 R[x]$ is an integral domain (proposition 9.4.25) and $R[x]/p_1 R[x] \cong (R/p_1 R)[x]$ (exercise).

Now, reducing $dp(x) = a'(x)b'(x)$ modulo p_1, we get

$$\overline{0} = \overline{a'(x)} \cdot \overline{b'(x)}$$

Since $(R/p_1 R)[x]$ is an integral domain, then either $\overline{a'(x)}$ or $\overline{b'(x)}$ is zero, say $\overline{a'(x)} = 0$. This would imply $p_1 | a'(x)$, and so every coefficient of $a'(x)$ is divisible by p_1, meaning $\frac{1}{p_1} a'(x)$ also has coefficients from R! So, we can divide both sides by p_1 (that is d by p_1 and either $a'(x)$ or $b'(x)$ by p_1). But then, the factor d on the left hand side has one fewer irreducible element! We can continue this procedure till we cancel out all of the factors, leaving us with $p(x) = a(x)b(x)$, with $a(x), b(x) \in R[x]$, $a(x)$ and $b(x)$ being F-mutiples of $A(x)$ and $B(x)$!

Note that $A(x)$ and $B(x)$ are not necessarily R-multiples, nor are they necessarily unique. For example, $x^2 \in Q[x]$ is reducible, and so reducible in $\mathbb{Z}[x]$. One factorization would be $A(x) = 2x$ and $B(x) = \frac{1}{2}x$. However, $\frac{1}{2} \notin \mathbb{Z}$: no integer multiple gives us a factorization of $A(x)$ and $B(x)$. What the theorem will tell us is that $\frac{1}{2}A(x) \in \mathbb{Z}[x]$, and $2B(x) \in \mathbb{Z}[x]$.

Since k is a field, the elements of R becomes units in $k[x]$ (the units in $k[x]$ being the non-zero constants). For example, $7x$ factors in $\mathbb{Z}[x]$ and produces two irreducible 7 and x, so $7x$ is *not* irreducible in $\mathbb{Z}[x]$. However, in $\mathbb{Q}[x]$, $7x$ is a unit 7 times an irreducible, so $7x$ *is* irreducible in $\mathbb{Q}[x]$. However, this is the *only* difference between the irreducible elements in $R[x]$ and $k[x]$

Corollary 11.2.2: Irreducibility In $R[x]$ And $k[x]$

Let R be a UFD, let $k = K(R)$ be its field of fractions, and let $p(x) \in R[x]$. Suppose the greatest common divisor of the coefficients of $p(x)$ is 1. Then $p(x)$ is irreducible in $R[x]$ if and only if it is irreducible in $K[x]$. In particular, if $p(x)$ is a monic polynomial that is irreducible in $R[x]$, then $p(x)$ is irreducible in $K[x]$.

***Proof*:**
We will proceed by the contrapositive: $p(x)$ is reducible in $R[x]$ if and only if $p(x)$ is reducible $K[x]$. The ($\Leftarrow$) direction is Gauss's Lemma, so let's go ($\Rightarrow$). Let's say $p(x)$ is reducible in $R[x]$ and the greatest comon divisor of the coefficients is 1. That means that when we reduce $p(x) = a(x)b(x)$, neither $a(x)$ or $b(x)$ can be constants! Note that polynomials which are not constants in $K[x]$ are not units, meaning $p(x) = a(x)b(x)$ is also a factorization in $K[x]$, completing the proof!

This theorem is already incredibly powerful, it means that the task of finding the irreducible elements of $R[x]$ reduces to finding the irreducible elements of $k[x]$ (which we know is a euclidean domain) up to a multiple of R. We shall later find more techniques for finding solutions to polynomials over fields, which by our above results immediately give us a way to translate these results for integral

domains whose field of fraction is the given polynomial ring over a field.

Yet another result is the following which shows that extending a ring to form a polynomial ring preserves UFD!

Theorem 11.2.3: R UFD If And Only If $R[x]$ UFD

R is a Unique Factorization Domain if and only if $R[x]$ is a Unique Factorization Domain

***Proof*:**
If $R[x]$ is a Unique Factorization Domain, then the constants of $R[x]$ must uniquely factor, meaning R is a Unique Factorization Domain.

So let's suppose R is a Unique Factorization Domain, and take $p(x) \in R[x]$. If $p(x)$ is a constant, then it's uniquely factorizable, so let's say $\deg(p(x)) > 0$. Let d be the g.c.d. of the coefficients of $p(x)$, so that $p(x) = dp'(x)$, meaning the g.c.d. of the coefficients of $p'(x)$ is 1. Note that this factorization is unique up to a unit multiple of d (i.e. up to a unit in R by proposition 9.2.3), and since d can be factored uniquely in R (and these are also irreducibles in $R[x]$ too), it suffices now to prove that $p'(x)$ can be uniquely factored into irreducibles in $R[x]$.

Let k be the field of fractions of R. Then since $k[x]$ is a Unique Factorization Domain (theorem 11.1.1), $p(x)$ can be factored uniquely into irreducibles in $k[x]$. By Gauss's Lemma, such a factorization implies a factorization in $R[x]$ whose factors are F-multiples of the factors in $k[x]$. Since the g.c.d. of $p'(x)$ is 1, the g.c.d. of the coefficients of each of these factors in $R[x]$ must be 1. By corollary 11.2.2, each of these factors are irreducible in $R[x]$! Hence $p(x)$ can be written as the product of irreducibles in $R[x]$.

The uniqueness of the factorization of $p(x)$ follows from the uniqueness in $k[x]$. Suppose

$$p'(x) = q_1(x)q_2(x)\cdots q_n(x) = q_1'(x)q_2'(x)\cdots q_m'(x)$$

Since the g.c.d. of the coefficients of $p'(x)$ is 1, so to it is for both factorizations. By corollary 11.2.2, each $q_i(x)$ and $q_j'(x)$ is an irreducible in $k[x]$. By uniqueness of factorization on $k[x]$, $n = m$, and the up to rearrangement, the two factorizations are the same up to associates, that is $q_i(x) = uq_i'(x)$ for a unit $u \in k[x]$. It remains to show they are associates in $R[x]$. By proposition 9.2.3, the untis of $k[x]$ are the units of F, so

$$q_i(x) = \frac{a}{b}q_i'(x)$$

for $a, b \in R$. Thus, $bq_i(x) = aq_i'(x)$. Thinking about it another way, the g.c.d. of the coefficients of the polynomial on the left hand side is b, and a on the right hand side respectively. Since in a Unique Factorization Domain, the coefficients of a nonzero polynomial is unique up to units ($a = ub$ for a unit in R), then $q_i(x) = uq_i'(x)$, and so $q_i(x)$ and $q_i'(x)$ are associates in R as well, completing the proof!

Corollary 11.2.4: Polynomial Rings in Several Variables over a UFD are UFDs

If R is a Unique Factorization Domain, then a polynomial ring in an arbitrary number of variables with coefficients in R is also a UFD

***Proof*:**
For the finitely many case, apply induction on theorem 11.2.3, since $R[x,y] = R[x][y]$, and $R[x]$ is a Unique Factorization Domain. The general case follwos fromthe definition of a polynomial ring in an arbitrar ynumber of variables as the union of polynomial rings in finitely many variables.

Example 11.2.5

1. $\mathbb{Z}[x], \mathbb{Z}[x,y]$, and so on are Unique Factorization Domains. The ring $\mathbb{Z}[x]$ now gives a good example of a Unique Factorization Domain that is *not* a Principal Ideal Domain!
2. Similarly, $\mathbb{Q}[x]$, $\mathbb{Q}[x,y]$, and so forth are Unique Factorization Domains.

Finally, we will ask if we can weaken the condition's and still get the same result. What if R was just an integral domain? Can we follow a similar construction? Generalizing in a different direction, if R is a Unique Factorization Domain, does that imply that $R[[x]]$ is a Unique Factorization Domain? The answer to both is in general no

Example 11.2.6: Counter-Example

1. Let $R = \mathbb{Z}[2i]$, and let $p(x) = x^2 + 1$. Then the field of fractions of R is $F = \mathbb{Q}[2i]$. The polynomial $p(x)$ factors uniquely into a product of two linear facrors in $k[x] : x^2 = (x-i)(x+1)$. so in particular $p(x)$ *is* reducible in $\mathbb{Q}[2i]$. However, Neither of these factors lies in $R[x]$ (because $i \notin R$) so $p(x)$ is *irreducible* in $R[x]$. In particualr, by corollary 11.2.2, $\mathbb{Z}[2i]$ is *not* a Unique Factorization Domain! If it were, then it should've been reducible!
2. It is a rather technical project to show that if R is a UFD, then $R[[x]]$ need not be a UFD. The somewhat canonical counter-example is

$$R = \frac{k[x,y,z]}{(x^2 + y^3 + z^7)}$$

See [87] for an in-depth explanation[a].

[a] this paper does require some algebraic knowledge introduced in *Commutative Algebra* [20]

Exercise 11.2.1

1. Let $x^5 - x + 1 \in \mathbb{Q}[x]$. Is this polynomial irreducible? (Hint: use Gauss's Lemma)
2. Recall that if R Is a UFD, it is not necessarily the case that $R[[x]$. Show that $\mathbb{R}[[x]]$ is a UFD

11.3 Irreducibility of Polynomials

Now that we have shown R, $R[x]$, $R[x,y]$ and so forth are Unique Factorization Domains if and only if R is a Unique Factorization Domain and that irreducibility over $R[x]$ is symmetrically reflected to irreducibility over $k[x]$, we now raise the question about finding irreducible elements in such a ring (i.e. the prime elements, the "building blocks"). A polynomial $p(x)$ is reducible if we can find

two polynomials of smaller degree such that $p(x) = a(x)b(x)$. A polynomial is irreducible if no such polynomials exist. In general this is difficult, which is why we look for nicer irreducibility criteria.

Throughout these proofs, we shall be taking advantage of the fact that the field of fractions is a UFD, hence the polynomial ring over the field is a UFD. We shall not even require the ring that we are using to construct the field of fraction to be a UFD, simply an integral domain. To demonstrate, consider the following key fact:

Proposition 11.3.1: Finding Linear Factors

Let R be an integral domain, $p(x) \in R[x]$ and $r \in R$. Then $p(r) = 0$ if and only if $x - r$ divides $p(x)$ in $R[x]$.

***Proof*:**
If $p(x) = (x - r)q(x)$ with $q(x) \in R[x]$, then $p(r) = (r - r)q(r) = 0$. Conversely, let $p(x) = \sum_{k=0}^{n} a_k x^k$ with $p(r) = 0$. For $k \geq 1$, $x^k - r^k = (x - r)\sum_{j=0}^{k-1} x^j r^{k-1-j}$, so

$$p(x) = p(x) - p(r) = \sum_{k=1}^{n} a_k(x^k - r^k)$$

is divisible by $x - r$ in $R[x]$, completing the proof.

Corollary 11.3.2: Maximum Number Of Roots

[Maximum Number Of Roots] Let R be an integral domain and $p(x) \in R[x]$ of degree n. Then $p(x)$ has *at most* n roots.

***Proof*:**
Let $k = K(R)$ be the field of fraction of R. Then the number of roots of $p(x) \in [R]x$ is certainly less than or equal to the number of roots in $p(x) \in k[x]$. Now, *a fortiori* k is a UFD, hence by theorem 11.2.3 $k[x]$ is a UFD, and so each root corresponds to an (irreducible) factor of degree 1. But then, f can have at most n factors of degree 1 by unique factorization, completing the proof.

Note that this statement can fail if R is not an integral domain!

Example 11.3.3: Polynomial With More Roots And Its Degree

[Polynomial With More Roots And Its Degree] Let $x^2 + x \in (\mathbb{Z}/6\mathbb{Z})[x]$. Show that this polynomial of degree 2 has the 4 roots 0, 2, 3 and 5.

However, using proposition 11.3.1, we may show that polynomials over infinite integral domains are determined by their roots!

Corollary 11.3.4: Polynomials Detremiend By Evaluation

[Polynomials Detremiend By Evaluation] Let R be an infinite integral domain and $f, g \in R[x]$. Then $f = g$ if and only if

$$r \mapsto f(r) \qquad \text{and} \qquad r \mapsto g(r)$$

agree for all $r \in R$

***Proof*:**
Two functions agree if every $r \in R$ is a root of $f - g<$ but a nonzero polynomial over R cannot have infinitely many roots by corollary 11.3.2, hence they must be equal as we sought to show.

Continuing from this, we may ask about the irreducibility of degree 2 and 3 polynomials, which is an immediate consequence of the above results:

Proposition 11.3.5: Degree 2 Or 3 Polynomials

A polynomial of degree two or three over a field F is reducible if and only if it has a root in F.

***Proof*:**
Let $f \in F[x]$ have degree 2 or 3. If $f = gh$ with g, h not units, then g and h have positive degree, since the units of $F[x]$ are the nonzero constants, and $\deg g + \deg h = \deg f \leq 3$. So one factor has degree 1, say $g = ax + b$ with $a \neq 0$, and $-b/a$ is a root of f. Conversely, if c is a root of f, then $f = (x - c)h$ by proposition 11.3.1, with $\deg h = \deg f - 1 \geq 1$, so f is reducible, completing the proof.

The reason for this is that if we have a degree higher than 4, then we can reduce to two irreducible polynomials of degree 2, like $(x^2 + 1)(x^2 + 1)$ in $\mathbb{Q}[x]$. For higher degree polynomials, we may have more solutions depending on what type of field we are working over. For example, we shall introduce in section 19.5.1 the existence of field for which only linear polynomials are irreducible ($\mathbb{C}$ being a canonical example of such a field). Yet another example is that any polynomial of degree ≥ 3 over $\mathbb{R}$ is reducible[2]. For more general rings, it is in general much more difficult to determine if a polynomial is reducible. There are however some tricks that help in arbitrary situations, especially if R is a UFD (for then we may use the gcd)

This next proposition let's us limit the number of "rational" solutions of a polynomial over a UFD.

Proposition 11.3.6: Rational Roots Test

Let R be a UFD and $k = K(R)$. Let $p(x) = a_n x^n + a_{n-1} x^{n-1} + \cdot + a_1 x + a_0$ be a polynomial of degree n with coefficients in the UFD R. If $r/s \in k$ with $gcd(r, s) = 1$, and r/s is a root of $p(x)$ ($p(r/s) = 0$), then r divides the constant term and s divides the leading coefficient of $p(x)$: $r \big| a_0$ and $s \big| a_n$. In particular, if $p(x)$ is a monic polynomial with integer coefficients and $p(d) \neq 0$ for all integers d dividing the constant term of $p(x)$, then $p(x)$ has no roots in $k[x]$.

[2]This is exercise ref:HeRE (closure of fields, 3rd exercise). An astute student would be able to work out this exercise

***Proof*:**
Let's say $p(r/s) = 0$. Then

$$p(r/s) = 0 = a_n(r/s)^n + a_{n-1}(r/s)^{n-1} + \cdots + a_1(r/s) + a_0$$

multiplying all by s^n, we get:

$$0 = a_n r^n + a_{n-1} r^{n-1} s + \cdots + a_1 r s^{n-1} + a_0 s^n$$

so

$$a_n r^n = s(-a_{n-1} r^{n-1} - \cdots - a_1 r s^{n-1} - a_0 s^{n-1})$$

thus, $s \big| a_n r^n$. $gcd(r, s) = 1$, then it must be that $s | a_n$. Doing the same trick for a_0:

$$a_0 s^n = r(-a_n r^{n-1} - a_{n-1} r^{n-2} - \cdots - a_1 s^{n-1})$$

then $r | a_0$.

If $a_n = 1$, then we'd have $s|1$, so $r/s = r/1 = r$. This means we only need to check the values r which divide a_0. If every value that divdse a_0 is not a root of $p(x)$, then $p(x)$ has no roots.

This gives us a really easy way of testing irreducibility of low-degree polynomials:

Example 11.3.7: Irreducibility Of Low-Degree Polynomials

1. The polynomial $p(x) = x^3 - 3x - 1$ is irreducible in $\mathbb{Z}[x]$. Since the polynomial is monic, by corollary 11.2.2, it is irreducible in $\mathbb{Z}[x]$ if it is irreducible in $\mathbb{Q}[x]$. By the rational number test, we are given the candidates ± 1. Plugging both of them in, we get no roots of $\mathbb{Q}[x]$, and so by proposition 11.3.5, this polynomial is irreducible, and so is irreducible in $\mathbb{Z}[x]$.
2. For any prime p, $x^2 - p$ and $x^3 - p$ are irreducible in $\mathbb{Q}[x]$. We have ± 1 and $\pm p$ as candidates. Both of them are not roots, and therefore, these polynomials are not reducible!
3. The polynomial $x^2 + 1$ is *reducible* in $(\mathbb{Z}/2\mathbb{Z})[x]$, namely $(1)^2 + 1 = 1 + 1 = 0$. It's factors are $(x + 1)(x + 1) = x^2 + 1$.
4. The polynomial $x^2 + x + 1$ is *irreducible* in $(\mathbb{Z}/2\mathbb{Z})[x]$, since there are no roots.
5. Similarly for $x^3 + x + 1$ in $(\mathbb{Z}/2\mathbb{Z})[x]$

All the polynomials in the aforementioned examples are all of degree less than or equal to 3. This is because when factoring polynomials of degree greater than or equal to 4, it's possible that we get 2nd degree polynomials as irreducible factors (like $(x^2 + 1)(x^2 + 1)$ in $\mathbb{Q}[x]$, which has no factors).

We use another trick for these type of polynomials: We can use proposition 11.0.1 ($R[x]/I[x] \cong (R/I)[x]$) to generalize the rational root test:

Proposition 11.3.8: Reduction Test

Let I be a proper ideal in the integral domain R and let $p(x)$ be a non-constant *monic* polynomial in $R[x]$. If the image of $p(x)$ in $(R/I)[x]$ cannot be factored in $(R/I)[x]$ into two polynomials of smaller degree, then $p(x)$ is irreducible in $R[x]$.

***Proof*:**
Suppose $p(x)$ is reducible in $R[x]$, so $p(x) = a(x)b(x)$ with neither factor a unit. Since R is an integral domain, $\deg a + \deg b = \deg p$, and the leading coefficients of $a(x)$ and $b(x)$ multiply to 1, so both are units of R. A factor of degree 0 would then be a unit, so both factors have positive degree, and hence degree smaller than $\deg p$. Multiplying $a(x)$ by the inverse u^{-1} of its leading coefficient u, and $b(x)$ by u, makes both factors monic without changing their product.

Reducing every coefficient modulo I is a ring homomorphism $R[x] \to (R/I)[x]$, the map behind proposition 11.0.1. It sends $p(x) = a(x)b(x)$ to a product of two monic polynomials of the same degrees as $a(x)$ and $b(x)$, since $1 \neq 0$ in R/I for the proper ideal I. So the image of $p(x)$ factors in $(R/I)[x]$ into two polynomials of smaller degree, contradicting the hypothesis.

The power here comes from the fact that R/I might have much simpler structure for factoring (ex. $\mathbb{Z}$ vs $\mathbb{Z}/n\mathbb{Z}$!) For example, in exercise set 11.2.1, we may prove that $x^5 - x + 1$ using this trick rather quickly! So, If we reduce a polynomial into $(R/I)[x]$, and show it cannot be factored, then it is irreducible in $R[x]$ as well! However, the converse (if $p(x)$ is irreducible in $R[x]$, then $p(x)$ is irreducible in every $(R/I)[x]$) is not true.

Example 11.3.9: Limitation of reduction method

Take $x^4 + 1 \in \mathbb{Z}[x]$. This polynomial is irreducible in $\mathbb{Z}[x]$, (hint: recall that $\sqrt{2}$ is irrational), but is reducible for every prime. Verify this by considering cases of

$$p \equiv 1, 3, 5, 7 \bmod 8$$

since the case of $p = 2$ can quickly be manually verified.

So, if you get that a polynomial is reducible in $(R/I)[x]$, that unfortunately does not tell you it's reducible in $R[x]$.

A special case of proposition 11.3.8 that is quite useful is called Eisenstein's Criterion (or Eisenstein-Schönenmann Criterion, since Schönenmann discovered it first)

Proposition 11.3.10: Eisenstein's Criterion

Let P be a prime ideal of the commutative ring R and let $f(x) = x^n + a_{n-1}x^{n-1} + \cdots + a_1x + a_0$ be a polynomial in $R[x]$ (where $n \geq 1$). Suppose $a_{n-1}, ..., a_0 \in P$, but $a_0 \notin P^2$. Then $p(x)$ is irreducible.

***Proof*:**
Let's take $p(x)$ like in the proposition. For the sake of contradiction, let's say $p(x)$ is reducible: $p(x) = a(x)b(x)$, where $a(x)$ and $b(x)$ are non-constant.Then by proposition 11.3.8 (the

contrapositive of it), it is reducible in $(R/P)[x]$. Since every non-leading coefficient is in P:

$$\overline{p(x)} = \overline{x^n} = \overline{a(x)} \cdot \overline{b(x)}$$

Since P is prime, R/I is an integral domain, and so the constant terms of $a(x)$ and $b(x)$ must be in P, or else we will get $\overline{x} \cdot \overline{y} = \overline{0}$. But then, multiplying those terms means $a_0 \in P^2$, a contradiction!

For the purposes of this book, the following is the most immediate use of Eisenstein's Criterion:

Corollary 11.3.11: Eisenstein's Criterion For $\mathbb{Z}[x]$

Let p be a prime in $\mathbb{Z}$ and let $f(x) = x^n + a_{n-1}x^{n-1} + \cdots a_1 x + a_0$. If every a_i is divisible by p, but a_0 is not divisible by p^2, then $f(x)$ is irreducible in both $\mathbb{Z}[x]$ and $\mathbb{Q}[x]$.

***Proof*:**
This is proposition 11.3.10 and using corollary 11.2.2.

Here are some examples using Eisenstein's criterion, and some more tricks when finding irreducible polynomials:

Example 11.3.12: Irreducibility Tricks

1. When solving polynomials of degree 3 or less, it'd suggest to always start with checking roots: it's the simpliest criterion.
2. The polymoial $x^4 + 10x + 5$ in $\mathbb{Z}[x]$ is irreducible, if we take $p = 5$. Since $5|10$, $5|5$, but $5^2 \nmid 5$, then Eisntein's criterion holds.
3. For any integer a such that $p|a$ but $p^2 \nmid a$, then $x^n - a$ is irreducible in $\mathbb{Z}[x]$. If $a = p$ a prime, then $x^n - p$ is irreducible for all positive integers n, so for $n \geq 2$, the nth root of p are not rational numbers (i.e. has no roots in $\mathbb{Q}[x]$)
4. We cannot apply the same tricks we did before to the polynomial x^4+1 in $\mathbb{Z}[x]$, since nothing divides prime, and any proper ideal will not contain 1. Instead, we will use a trick called *substitution*.

   Consider the polynomial $f(x+1) = (x+1)^4 + 1 = x^4 + 4x^3 + 6x^2 + 4x + 2$. On this polynimal, Eisntein's criterion works, since all non-leading coefficients are divisible by 2, and $2^2 \nmid a_0$. From this, it follows that $f(x)$ is irreducible, since any factorization of $f(x)$ will be a factorization for $f(x+1)$ (replace x by $x+1$ in the factorization!) Remember this trick for polynomials which seem at first glance to not get an application of Eisntein's criterion.
5. (cyclotomic polynomials) Perhaps the most famous application of Eisenstein's criterion is on polynomials of the following form:

   $$1 + x + x^2 + \cdots + x^{p-1} \in \mathbb{Z}[x]$$

   Eisenstein's criterion cannot be directly applied, however as before we can do the $x \mapsto x+1$ trick to get

   $$p(x+1) = 1 + (x+1) + \cdots + (x+1)^{p-1} = x^{p-1} + \binom{p}{p-1}x^{p-2} + \cdots + \binom{p}{2}x + \binom{p}{1}$$

where $\binom{p}{1} = p$.It suffices to show that $p \Big| \binom{p}{k}$ for $1 \leq k \leq p-1$ to conclude the result.

6. Notice that in the proof, we reduced to $(R/P)[x]$. If $R = \mathbb{F}$ was a field, then the only ideals are 0 and $\mathbb{F}$, meaning $(\mathbb{F}/P)[x] \cong 0[x] \cong 0$. Therefore, Einsteins criterion does not work will with such polynomials.

   For example, is $x^4 + 1$ reducible in $\mathbb{F}_5[x]$ ($\mathbb{F}_5$ is the field with 5 elements, and is isomorphic to $\mathbb{Z}/5\mathbb{Z}$)? Over $\mathbb{Q}$ it is irreducible, since substituting $x + 1$ gives $x^4 + 4x^3 + 6x^2 + 4x + 2$, which satisfies Eisenstein's criterion at 2 (corollary 11.3.11). It also has no roots, as can be verified by plugging in $0, ..., 4$.

   We cannot use einstein's criteron, but since the degree is 4, we know if a factorization did exist, they would have to be of degree 2, that is

   $$x^4 + 1 = (x^2 + ax + b)(x^2 + cx + d) = x^4 + (a + c)x^3 + (b + ac + d)x^2 + (ad + bc)x + bd$$

   note that the coefficients of x^2 are one since the coeficient of x^4 is one. We can then deduce that

   $$a + c = 0, b + ac + d = 0, ad + bc = 0, bd = 1$$

   Manipulating a bit, we can get the following information:

   $$\begin{aligned} c &= -a \\ b + a(-a) + d &= 0 \\ ad + b(-a) &= 0 \\ a^2 &= b + d \\ ad &= ab \end{aligned}$$

   If $a \neq 0$, then $ad = ab$ gives $b = d$, so $b^2 = 1$ and $a^2 = 2b = \pm 2$. But the squares in $\mathbb{F}_5$ are $0, 1, 4$, so this is impossible. If $a = 0$, then $b = -d$ and $bd = 1$ give $b^2 = -1 = 4$, so $b = 2$ and $d = 3$ (or the reverse), and $c = 0$. This gives

   $$p(x) = x^4 + 1 = (x^2 + 2)(x^2 + 3)$$

   Thus, $p(x)$ is reducible in $\mathbb{F}_5[x]$.

Over finite fields, irreducibility can also be decided by an algorithm that factors polynomials, for example Berlekamp's algorithm.

Finally, we give a few important results that shall be very handy tools. The first tells us that polynomial division is insensitive to extending the field: for $f(x), g(x) \in F[x]$, the quotient and remainder, and with them the question of whether $g(x)$ divides $f(x)$, come out the same in $F[x]$ and in $E[x]$ for any extension E of F:

Proposition 11.3.13: Invariant Under Field Extensions

Let $F \subseteq E$ be an extension of fields and let $f(x), g(x) \in F[x]$ with $g(x)$ nonzero. Then the quotient and remainder of $f(x)$ upon division by $g(x)$ are the same whether computed in $F[x]$ or in $E[x]$. In particular, $g(x) \big| f(x)$ in $F[x]$ if and only if $g(x) \big| f(x)$ in $E[x]$.

***Proof*:**
By theorem 11.1.1 applied in $F[x]$, write

$$f(x) = q(x)g(x) + r(x) \qquad \text{with} \qquad r(x) = 0 \text{ or } \deg(r(x)) < \deg(g(x))$$

where $q(x), r(x) \in F[x]$. Since $F[x] \subseteq E[x]$, this same equation holds in $E[x]$, and the condition on $r(x)$ is unchanged. By the uniqueness part of theorem 11.1.1 applied in $E[x]$, the pair $(q(x), r(x))$ is therefore also the quotient and remainder of $f(x)$ by $g(x)$ in $E[x]$, proving the first claim.

For the second claim, note that $g(x)\big|f(x)$ in $F[x]$ if and only if $r(x) = 0$. Indeed, if $r(x) = 0$ then $f(x) = q(x)g(x)$, and conversely if $f(x) = h(x)g(x)$ with $h(x) \in F[x]$, then $f(x) = h(x)g(x) + 0$ is a division with remainder 0, so $r(x) = 0$ by uniqueness. The same equivalence holds in $E[x]$, and by the first claim the remainder is the same polynomial $r(x)$ in both rings. Hence $g(x)\big|f(x)$ in $F[x]$ if and only if $r(x) = 0$ if and only if $g(x)\big|f(x)$ in $E[x]$.

This next one is of particular interest for the structure of the multiplicative group of a field!

Theorem 11.3.14: Subgroup of Multiplicative Group is Cyclic

A finite subgroup of the multiplicative group of a field is cyclic. In particular, if F is a finite field, then the multiplicative group $F^\times$ of nonzero elements of F is a cyclic group.

***Proof*:**
We will use the fundamental theorem for finitely generated abliean groups!

Let $A \subseteq F^\times$ be a finite subgroup. It is abelian, so by theorem 5.1.6 (with $r = 0$, as A is finite):

$$A \cong \mathbb{Z}/n_1\mathbb{Z} \times \mathbb{Z}/n_2\mathbb{Z} \times \cdots \times \mathbb{Z}/n_k\mathbb{Z}$$

where $n_k\big|n_{k-1}, n_{k-1}|n_{k-2}, ..., n_2\big|n_1$. Since n_k divides the order of each of the cyclic groups in the direct product, it follows that each direct factor contains n_k elements g with $g^{n_k} = 1$: in $\langle x\rangle$ of order m with $n_k\big|m$, $(x^j)^{n_k} = 1$ exactly when $m\big|jn_k$, that is when $\frac{m}{n_k}\big|j$, which holds for n_k values of j modulo m (proposition 2.3.7). If k were greater than 1, there would therefore be a total of more than n_k such elements. But then there would be more than n_k roots of the polynomial $x^{n_k} - 1$ in the field F, contradicting corollary 11.3.2. Hence $k \leq 1$, and the group is cyclic.

Corollary 11.3.15: $(\mathbb{Z}/p\mathbb{Z})^\times$ is cyclic

Let p be a prime. The multiplicative group $(\mathbb{Z}/p\mathbb{Z})^\times$ of nonzero residue classes mod p is cyclic

***Proof*:**
Since $\mathbb{Z}/p\mathbb{Z}$ is a field, apply theorem 11.3.14

Corollary 11.3.16: Non-Abelian Groups Of Order pq Are Unique

Let $p < q$ be primes with $p \mid q-1$. Any two non-abelian groups of order pq are isomorphic.

***Proof*:**
Let G be non-abelian of order pq. Its Sylow q-subgroup $Q = \langle y \rangle$ is normal (theorem 4.9.1(1)), and some $x \in G$ has order p (theorem 4.8.7). Then $xyx^{-1} = y^s$ for an integer s, so $x^j y^k x^{-j} = y^{s^j k}$ for all $j \geq 0$ and k, and $y = x^p y x^{-p} = y^{s^p}$, so $s^p \equiv 1 \pmod{q}$. If $s \equiv 1$, then x and y commute, and $\langle x, y \rangle$, whose order is divisible by p and by q, is all of G and abelian, so the class of s has order p in $(\mathbb{Z}/q\mathbb{Z})^\times$. That group is cyclic (corollary 11.3.15), so it has exactly one subgroup of order p (theorem 2.3.11). Since $\langle x \rangle \cap Q = 1$, the pq elements $y^i x^j$ with $0 \leq i < q$ and $0 \leq j < p$ are distinct and form G, and

$$(y^i x^j)(y^k x^l) = y^{i+s^j k} x^{j+l}$$

Let G' be another such group, with y', x' and s'. Both s and s' generate the unique subgroup of order p of $(\mathbb{Z}/q\mathbb{Z})^\times$, so $s \equiv s'^t$ for some t with $p \nmid t$. Replacing x' by x'^t, which also has order p, replaces s' by s'^t, so the two multiplication rules coincide, and $y^i x^j \mapsto y'^i x'^j$ is an isomorphism $G \to G'$.

Corollary 11.3.17: Isomorphisms Of Multiplicative Groups

Let $n \geq 2$ be an integer with factorization $n = p_1^{\alpha_1} p_2^{\alpha_2} \cdots p_r^{\alpha_r}$ in $\mathbb{Z}$, where $p_1, ..., p_r$ are distinct primes. Then we have the following isomorphisms of (multiplicative) groups:

1. $(\mathbb{Z}/n\mathbb{Z})^\times \cong (\mathbb{Z}/p_1^{\alpha_1}\mathbb{Z})^\times \times (\mathbb{Z}/p_2^{\alpha_2}\mathbb{Z})^\times \times \cdots \times (\mathbb{Z}/p_r^{\alpha_r}\mathbb{Z})^\times$
2. $(\mathbb{Z}/2^\alpha\mathbb{Z})^\times$ is the direct product of a cyclic group of order 2 and a cyclic group of order $2^{\alpha-2}$, for all $\alpha \geq 2$
3. $(\mathbb{Z}/p^\alpha\mathbb{Z})^\times$ is a cyclic group of order $p^{\alpha-1}(p-1)$ for all odd primes p and $\alpha \geq 1$

***Proof*:**
For (1), the ideals $(p_i^{\alpha_i})$ are pairwise comaximal, as $\gcd(p_i^{\alpha_i}, p_j^{\alpha_j}) = 1$ for $i \neq j$, so theorem 9.6.11 gives a ring isomorphism $\mathbb{Z}/n\mathbb{Z} \cong \prod_i \mathbb{Z}/p_i^{\alpha_i}\mathbb{Z}$. A ring isomorphism restricts to an isomorphism of unit groups, and the units of a product of rings are the tuples of units.

For (2) and (3), let p be a prime, $k \geq 1$, with $k \geq 2$ if $p = 2$, and let $u \in \mathbb{Z}$. Then

$$(1 + p^k u)^p = 1 + p^{k+1} u + \sum_{j=2}^{p} \binom{p}{j} p^{jk} u^j \equiv 1 + p^{k+1} u \pmod{p^{k+2}}$$

since for $2 \leq j < p$ the prime p divides $\binom{p}{j}$ and $jk + 1 \geq k + 2$, and $pk \geq k + 2$ (for $p = 2$ this is where $k \geq 2$ is used). Applying this with $k + i$ in place of k gives, by induction on $i \geq 0$,

$$(1 + p^k)^{p^i} = 1 + p^{k+i} u_i \qquad \text{with } u_i \equiv 1 \pmod{p}$$

So if $\alpha > k$, the class of $1 + p^k$ in $(\mathbb{Z}/p^\alpha\mathbb{Z})^\times$ satisfies $(1 + p^k)^{p^{\alpha-k}} = 1$ and $(1 + p^k)^{p^{\alpha-k-1}} \neq 1$, and has order exactly $p^{\alpha-k}$.

For (3), let p be odd. The group $(\mathbb{Z}/p^\alpha\mathbb{Z})^\times$ has $p^\alpha - p^{\alpha-1} = p^{\alpha-1}(p-1)$ elements, the classes prime to p. Reduction modulo p is a surjective homomorphism onto $(\mathbb{Z}/p\mathbb{Z})^\times$, which is cyclic of order $p-1$ (corollary 11.3.15). If g maps to a generator, its order is a multiple $(p-1)t$ of $p-1$, and g^t has order $p-1$. The element $1+p$ has order $p^{\alpha-1}$ (the case $k=1$ above, or trivially if $\alpha = 1$). The orders are coprime and the group is abelian, so $g^t(1+p)$ has order $p^{\alpha-1}(p-1)$ and generates the group.

For (2), $(\mathbb{Z}/4\mathbb{Z})^\times = \{1,3\}$ is cyclic of order 2, which is the case $\alpha = 2$. Let $\alpha \geq 3$. The group has $2^{\alpha-1}$ elements, and $5 = 1+2^2$ has order $2^{\alpha-2}$ (the case $p=2$, $k=2$ above). Every power of 5 is 1 modulo 4, while -1 is not, so $\langle -1\rangle \cap \langle 5\rangle = \{1\}$. Both subgroups are normal, the group being abelian, and $|\langle -1\rangle||\langle 5\rangle| = 2^{\alpha-1}$, so the group is the direct product $\langle -1\rangle \times \langle 5\rangle$ (theorem 5.2.6).

This description of $(\mathbb{Z}/n\mathbb{Z})^\times$ is used in the proof of the Kronecker-Weber theorem (theorem 50.5.4).

Exercise 11.3.1

1. Show that there are irreducible polynomial in $\mathbb{Z}[x]$ and $\mathbb{Q}[x]$ for every degree.
2. Let $f(x)$ be an irreducible monic polynomial of $\mathbb{Z}[x]$. Show that $f(x)$ mod p has a root for infinitely many primes. The opposite is true too when $\deg f \geq 2$: there are infinitely many primes for which $f(x)$ mod p does *not* have a root, though that direction lies deeper, through the Chebotarev density theorem[3]
3. Show that $t^2+t+1 \in \mathbb{F}_2[t]$ is irreducible. Use this to show that $\mathbb{F}_2[t]/(t^2+t+1)$ is a field with 4 elements.

[3] see [77]

Part III

Modules

When we explored groups, we saw that the kernel of groups were groups (in particular a special subset of a group called the normal subgroup), and if we have an abelian group, every abelian group is the kernel of some group.

The story for rings is more complicated. As we mentioned at the beginning of the part on rings, some authors include an identity in the definition, others do not. If we include an identity, then the kernel of ring homomorphisms are not rings. Even if we take exclude identities as part of the definition, notice that practically none of the ideals we have encountered are among the rings previously mentioned, essentially because almost every ring we have mentioned has an identity, but if an ideal has an identity, it is the entire ring. The cokernels is also not as well-behaved (recall that $i : \mathbb{Z} \hookrightarrow \mathbb{Q}$ is an epimorphism). In this way, the kernel of rings and rings are very different objects, and so a lot goes into studying ideals as though they are a seperate object in ring theory. In particular, we do not focus a lot of attention of constructing rings based on other rings (similar to how we constructed polyabelian or poly-cyclic groups). Overall, the category of **Ring** and **Rng** are not the best behaved categories.

The concept of Modules can be thought of as a fix to this. Modules are more similar to abliean groups than they are to rings, for example if you have any sub-module, then the quotient will always be well-defined. Furthermore, all Rings can be thought as a module, making the study of module subsumes the study of rings. As we shall see,

We shall see that an R-module M will be an abelian group M with an ring action by R. The reason M is an abelian group and not just a set like in group actions is because it is a generalization of vector-spaces, not an addition to group actions. What I mean by this is that you have to think of the reasoning from the point of view that vector-spaces came first, and then there were many instances where the field acting on the group was too restrictive, which lead to module.

Over the 19th and 20th century, many mathematical objects were studied that all turn out to be modules. To those who want the punchline, I will point out a few right now:

1. All abelian groups are $\mathbb{Z}$-modules
2. All linear transformations are $F[x]$-modules
3. All rings are modules (If R is a ring, then it is an R-module over itself)
4. All ideals are modules (if $I \subseteq R$ is an ideal, it is an R-module)
5. All vector-spaces over k are k-modules
6. All vector-bundles are projective modules

12

Introduction to Modules

A lot of the algebraic structures we have covered so far share a similar story: we ask how maps between them can be studied (leading us to explore sub-objects and quotient-objects), and we ask how to generate them. Modules will have the same story at the beginning. When we will be building up modules, they will more closely resemble groups and rings. In groups, simple groups and free groups played a bigger role than they did in ring theory, and free modules return in section 12.3.2.

12.1 Basic Definitions and Examples

Definition 12.1.1: [left]-Module

Let R be a ring (more generally a rng). A *left R-module* or a *left module over R* is a set M together with

1. a binary operation $+$ on M under which M is an **abelian group**, and
2. an action of R on M (that is, a map $R \times M \to M$) denoted by rm, for all $r \in R$ and for all $m \in M$ which satisfies
   (a) $(r+s)m = rm + sm$, for all $r, s \in R$, $m \in M$
   (b) $(rs)m = r(sm)$, for all $r, s \in R$, $m \in M$
   (c) $r(m+n) = rm + rn$ for all $r \in R$, $m, n \in M$

   If the rng R is a ring (i.e. has a 1), we impose the additional axiom

   (d) $1m = m$, for all $m \in M$

   And we sometimes call such a module a *unital* R-module.

Right modules are defined similarly. If the R ring is commutative, and M is an left $R-$*module*, we can turn it into a right $R-$*module* by defining $rm = mr$. To distinguish when different rings may be acting on an abelian group M, the symbol $\curvearrowright$ (read *acts on*) may be used to show that a ring R is acting on M: $R \curvearrowright M$

Unless stated otherwise, the term "module" will reference "left-module" Note that for a module M, we usually denote what ring it is over (or what ring acts upon it) by saying it is an *[ring symbol here]-module* (ex. R-module, $F[x]$-module, $[M_{m\times n}(\mathbb{F})]$-module). We might also say R acts on M where R is the ring and M is the abelian group. We will always be working *rings* actions, however as noted in the definition, we can also work with *rng* actions. Note too that we will often say that "R acts on the module M" to mean that we define a ring-action of R on the abelian group M.

When working over rings, the distributivity condition forces M to be abelian: let $r = s = 1$:

$$(1+1)\cdot(m+n) = (1+1)\cdot m + (1+1)\cdot n = 1\cdot m + 1\cdot m + 1\cdot n + 1\cdot n = m+m+n+n$$

$$(1+1)\cdot(m+n) = 1\cdot(m+n) + 1\cdot(m+n) = 1\cdot m + 1\cdot n + 1\cdot m + 1\cdot n = m+n+m+n$$

which implies $m+n = n+m$ for all $m, n \in M$. Notice how this when working with group actions, the group acting on the set did not effect any strucutre of set, namely since the set has no additional structure. Be mindeful that when referring to a module, we will usually call M the module. For example we might say "Let $\mathbb{Z}$ act on $\mathbb{Q}$ by $r \cdot a = ra$. Then $\mathbb{Q}$ has the following properties". Here $\mathbb{Q}$ is being regarded as a module, namely a $\mathbb{Z}$-module, not just as an abelian group or a ring.

If R is commutative then we defined a two-sided action $r \cdot m = m \cdot r$. If R is not commutative, then defining this property will have problems with $2(b)$: Let R be non-commutative, let $r \cdot m = m \cdot r$, and take $r, s \in R$ such that $rs \neq sr$ and $rs \cdot m \neq sr \cdot m$ (an example of such a module will be presented in the example 12.1.7). Then:

$$(rs)m = m(rs) = (mr)s = (rm)s = sr(m) = (sr)m$$

however, $sr \cdot m \neq rs \cdot m$ so this statement is not necessarily always true. Note how it may be possible that even though $rs \neq sr$ that $rs \cdot m = sr \cdot m$, for example, the trivial module structure $r \cdot m = m$ for any $r \in R$ will produce this result, however, as example 12.1.7 shows, every module induces a *faithful* module (the word faithful being defined equivalently to the group-action case[1]), and so making a distinction between left and right modules is very important over non-commutative rings.

We now have many operators to keep track of: the group operation of M, the two rings operations of R, and the ring action of R on M. When working with modules, we often focus on the ring-action, and use group and rings structures that were previously covered.

One might ask themselves if modules and group-rings might be similar concept, boths somehow being a ring "acting" on a group. If this suspicions crossed your mind, it is good idea to check how these two structure's differ (for example, if $|G| > 1$, recall a group-ring always has zero-divisors. Find an example in the list of examples bellow that does not have this property).

Since a module is an action on an abelian group, it would make sense if there is an equivalent to a permutation representation for module's as there is for group-actions. Recall that any group action can be seen as a group-homomorphism:

$$\rho : G \to \mathrm{Sym}(S)$$

The exact same idea works for defining an R-module as an action. In order to do so, we need an a notion of an R-module homomorphism that preserves some of the structure. Before looking at the definition bellow, see if you can come up with the definition of an R-module homomorphism.

Definition 12.1.2: R-module homomorphism

Let R be a ring and let M and N be R-module A map $\varphi : M \to N$ is an *R-module homomorphism* if it respects the R-module structure of M and N, i.e.

1. $\varphi(x + y) = \varphi(x) + \varphi(y)$ for all $x, y \in M$
2. $\varphi(r \cdot x) = r\varphi(x)$, for all $r \in R$, $m \in M$

Since M and N are both abelian groups, R-module homomorphisms are sometimes called *R-linear group homomorphisms*, where the map is R-linear since the ring actions passes through the homomorphism. Notice that both M and N both have the same ring acing on them: it is imperative that an R-module homomorphism be betewen R-modules.

Returning to the discussion on treating R-modules as an action, it is a good exercise to check ones understanding of the axioms of modules that the "axiomatic representation" of an R-module is equivalent to defining an R-module as a ring-homomorphism

$$\rho : R \to \mathrm{End}_{\mathbf{Ab}}(M)$$

where $\mathrm{End}_{\mathrm{Ab}}(M)$ is the collection of all group-homomorphisms from M to itself. Notice that $\mathrm{End}(M)$ is an [abelian] group because M is an abelian group, while the ring operation of composition, $\circ$, automatically satisfies the condition to make $\mathrm{End}_{\mathbf{Ab}}(M)$ a ring, which should be checked (for example, $\mathrm{id} : M \to M$ is an element of $\mathrm{End}_{\mathbf{Ab}}(M)$, hence it has a multiplicative identity). It will sometimes be useful to define an R-module as a ring homomorphism $\rho\colon R \to \mathrm{End}_{\mathbf{Ab}}(M)$. For instance, *restricting scalars* (definition 15.3.1) along a ring homomorphism $f\colon S \to R$ is the composition $\rho \circ f\colon S \to \mathrm{End}_{\mathbf{Ab}}(M)$.

[1] That is, if $r \cdot m = s \cdot m$ for every $m \in M$, then $r = s$.

As with rings and and with groups, we can define a category: given a ring R, the collection of R-modules and the collection of R-module homomorphisms forms a category:

Definition 12.1.3: R-Mod

The collection of all R-modules and R-module homomorphisms forms a category, which we will denote R-**Mod** or $\mathbf{Mod}_R$.

This category has some of the nice properties that the other categories that were extensively worked in so far have:

Definition 12.1.4: Classical definition of Submodule

Let R be a ring and let M be an R-module. An R-submodule of M is a subgroup N of M which is closed under the action of ring elements, i.e., $rn \in N$, for $r \in R$, $n \in N$

Definition 12.1.5: Categorical Definition of Submodule

Let $N \subseteq M$. Then if there exists a R-module inclusion map $\varphi : N \to M$ that is also an R-module homomorphism, then N is a submodule of M

Proposition 12.1.6: The sub-module Criterion

Let R be a ring and let M be a R-module. A subset of N of M is a submodule of M if and only if

1. $N \neq \emptyset$, and
2. $x + ry \in N$ for all $r \in R$, and for all $x, y \in N$

***Proof*:**
Easy to prove both ways (recall that M is an abelian group, and for the other way, simply set the values of r and x to some appropriate values)

Example 12.1.7: Modules

1. Let R be any ring. Then $M = R$ is a left R-module with the ring multiplication as the ring action: $r \cdot s = rs$. Take a moment to think about what are the submodules of R? The answer will be revieled in the next sentence. the sub-modules of M are the left-ideals of R! This is because ideals of R are closed under multiplication of R, and the axioms of modules require closure under "scalar multiplication" by the ring elements. Is R/I for any (two-sided) ideal of R also an R-module? Take a moment to think about it. The answer is that R/I is indeed an R-module! We will soon show that the kernel of module-homomorphisms will be submodules, showing that the axioms of a module "fix" the category of **Ring** by being closed under kernels!

   From now on, if we say that R is a [left/right] R-module over itself, it will be taken that the R-action on R is [left/right] multiplication by R, with a bias towards *left* R-modules if R is

non-commutative and which side of the action was not specified. We will also sometimes say "let R have the natural R-module structure" to mean the one induced by the ring operation of R.

2. Let R be a ring with 1 and let $n \in \mathbb{Z}^+$. Then since R is a group, we can define the direct product:
$$R^n = \{(a_1, ..., a_n) | a_i \in R, \text{ for all } i\}$$
We can turn R^n to an R-module by defining addition in R^n component wise, and the action being componentwise:
$$r(a_1, ..., a_n) = (ra_1, ..., ra_n)$$
Such a module R^n is called a *free module* [a]. More on these in section 12.3.2. If $R = \mathbb{R}$, then we have the usual algebraic structure of $\mathbb{R}^n$ common in analysis and linear algebra.

3. If M is an R-module, and S is a sub-ring of R, then M is automatically an S-module (i.e. the set M is also a module under the ring action with S). Since if the module axioms hold for R, i.e. the ring being closed under the ring action and the rules holding, then it will still hold for a sub-ring. In this way $\mathbb{R}$ is an $\mathbb{R}$-module, a $\mathbb{Q}$-module, and a $\mathbb{Z}$-module with the ring action being defined by regular multiplication. Notice though that the $\mathbb{R}$-submodules, $\mathbb{Q}$-submodules, and $\mathbb{Z}$-submodules differ, showing that having a different ring act on $\mathbb{R}$ greatly changes its module structure.

4. Let M be an R-module. If $I \subseteq R$ is a two-sided ideal, is it always true that M is an R/I-module? Under what condition's is it an R/I-module? The following is an exploration of when this is the case: Let I be a 2-sided ideal of R such that $am = 0$ for all $a \in I$ and $m \in M$, that is, $I \subseteq \text{Ann}_R(M)$ (definition 12.3.21), the largest such ideal. Then we say that M is *annihilated* by I. In this situation, we can make M into an (R/I)-module by defining an action of the quotient ring R/I on M as follows: for each $m \in M$, and $(r + I) \in R/I$, let
$$(r + I)m = rm$$
This is well defined since for any $a \in I$, $(r + a)m = rm + am = rm$. Check that the axioms of a module still hold. When $I = \text{Ann}_R(M)$, M is a *faithful* R/I-module: if $(r + I)m = 0$ for all $m \in M$, then $r \in \text{Ann}_R(M) = I$.

   If, conversely, if $I = \text{Ann}_R(M)$, and we have defined an R/I-action on a module M, can we define an R-action on M? More generally, given two rings R and S acting on M, when can we say that the module structure they induce on M is "comparable"‘ in some way? One way two types of modules can be equivalent is if they are something called "Morita equivalence", which is settled in chapter 18$\star$ [b])

5. What is and is not a well defined R-module is not always intuitive. Take for example the group ring $R = \mathbb{Z}[G]$ where $G = \{1, \sigma\}$ is a group of order 2. For the abelian group, take the module $M = \mathbb{Z}e_1 + \mathbb{Z}e_2$, where e_1, e_2 are generators for $\mathbb{R}^2$ (for example, $(1, 0)$ and $(0, 1)$ generate $\mathbb{R}^2$ as an abelian group), and the product $\mathbb{Z}e_i = \{ze_i | z \in \mathbb{Z}\}$.

   Define the action as:
$$\sigma(e_1) = e_1 + 2e_2 \qquad \sigma(e_2) = -e_2$$
Then M is a $\mathbb{Z}[G]$-module! The big one to check is $r_1(r_2m) = (r_1r_2)m$. The other conditions follow more easily. This is an example of how the limit on what can be defined as a module is not easy, since an example like this one exists, checking when a module is defined can be quite useful.

6. Let R be any ring and let $F(A,R)$ be the set of all [set]-functions from A to R:

$$f \in F(A,R) \Rightarrow f : A \to R$$

Then define the action by R to be

$$r \cdot f = rf \qquad r \cdot f(a) := rf(a) \qquad \forall a \in A$$

since $f(a) \in R$ Band $r \in R$. Define the group operation to be the new function $f+g$ where

$$(f+g)(a) := f(a) + g(a) \qquad \forall a \in A$$

Note that these functions are *not* R-module homomorphisms, since the set A has no structure! This R-module is is often dentoed as R^A (to symbolise all functions from A to R)[c].

Very often in Analysis and Algebraic Geometry, the set A will be all continuous functions on a topological space X, denoted $C(X)$, and the ring R would be the real or complex numbers $\mathbb{R}$ or $\mathbb{C}$. The study of these spaces is done commonly in functional analysis and classical algebraic geometry, usually requiring some analysis knowledge. In this textbook, these types of R-module will come back when discussing free-modules in theorem 12.3.11.

7. Let X be any set and $P(X)$ the powerset. Sending $A \subseteq X$ to its indicator function $\chi_A \colon X \to \mathbb{Z}/2\mathbb{Z}$, with $\chi_A(x) = \overline{1}$ for $x \in A$ and $\chi_A(x) = \overline{0}$ otherwise, is a bijection from $P(X)$ onto the module $(\mathbb{Z}/2\mathbb{Z})^X$ of the previous item, since a subset is recovered as the set of points where its indicator function is $\overline{1}$. Transporting the module structure along this bijection makes $P(X)$ a $\mathbb{Z}/2\mathbb{Z}$-module, in which $A+B$ is the symmetric difference $(A \setminus B) \cup (B \setminus A)$, since $\chi_A + \chi_B$ takes the value $\overline{1}$ exactly at the points lying in exactly one of A and B.

[a] not dissimilar to free-groups we studied in section 2.3.3

[b] For the categorically inclined, R-mod and S-mod are Morita equivalent if they are equivalent as categories. Are R-mod and R/I-mod equivalent?

[c] The notation matches exponentiation of numbers: for finite A and R there are $|R|^{|A|}$ functions $A \to R$.

When we worked with group-actions, we can take any group G and make it act on any set S. This is not the case with modules (i.e. given some fixed ring R and abelian group M, there does not always exist a ring-homomorphism $\varphi : R \to \mathrm{End}_{\mathbf{Ab}}(M)$):

Example 12.1.8: Impossible Module

Consider $M = \mathbb{Z}$ and $R = \mathbb{Q}$. Is there always a $\mathbb{Q}$ action over $\mathbb{Z}$? If it was, then:

$$\frac{1}{2} \cdot 1 = z$$

must be an element of $\mathbb{Z}$ ($z \in \mathbb{Z}$). Then:

$$z + z = \frac{1}{2} \cdot 1 + \frac{1}{2} \cdot 1 = (\frac{1}{2} + \frac{1}{2}) \cdot 1 = 1 \cdot 1 = 1$$

as a direct consequence of the module axioms. However, this implies

$$z + z = 1$$

which is not possible for any $z \in \mathbb{Z}$, and thus a contradiction! This is also an example where you can have a $\mathbb{Z} \subseteq \mathbb{Q}$ and a defined $\mathbb{Z}$-module, but there is no extension of M to a $\mathbb{Q}$-module for

which the previous module structure is embedded within it (opposite to how if we had a $\mathbb{Q}$-module, it would automatically be a $\mathbb{Z}$-module)[a]

[a]There is in fact still a notion of extending a module along a ring map, however the original module need not embed in the result. See section 15.3, and corollary 15.3.8 for exactly when it does


12.1.1 Vector-spaces

If the ring is a field, we give a special name to such a module:

Definition 12.1.9: Vector Space

Let M be an R-module. If $R = k$ is a field, then we call M a *vector-space* over k. An arbitrary field is often denoted by k or $\mathbb{F}$.

Due to historical reasons $\mathbb{F}$-modules homomorphisms are called *linear transformations*. The motivation for this will be seen in chapter 13, but the gist is that when $\mathbb{F} = \mathbb{R}$, the geometric intuition of the images and kernels of linear transformations will all be hyper-planes in the domain and codomain. A simple example would be $f : \mathbb{R} \to \mathbb{R} \times \mathbb{R}$ with $f(x) = (x, x)$. The resulting hyper-plane (simply called a line since it's 1 dimensional), looks like so:



If you are comfortable with linear algebra, then you are probably familiar of how simple the structure of vector-spaces are (if not, you may skip this remark: all that will be discussed here is covered in chapter 13). Essentially, a vector space V over k can be completely determined by it's dimension. For modules over a general ring R, this is sometimes far from the case: sometimes R will not even embed itself in V! However, there are ways in which we can systematically loosen the conditions on the ring k acting on V and get similar, but weaker, results. Thus, if it is intuitive to think of modules as generlizations of vector-spaces, which historically is how many mathematicians thought

of modules, then these chapters on module theory can be thought of as what happens if the action on a vector-space no longer forces to give a basis.

Example 12.1.10: Vector Spaces

1. The most common example is when $R = \mathbb{R}$ and $M = R^n = \mathbb{R}^n$. This vector-space is commonly reffered to as *euclidean space* due to the classical geometrical properties that can be defined on it(ex. a notion of distance, length, angle, translation and rotation)
2. If I is a maximal ideal in a commutative ring, and $IM = 0$, then M is a vector space over R/I (since R/I is a field)
3. Take $\mathbb{F}[x]$ to be a polynomial ring over a field $\mathbb{F}$, an let $f(x)$ be any polynomial of degree $n \geq 1$. Then $V = \mathbb{F}[x]/(f(x))$ is another polynomial ring. Let $\mathbb{F}$ act on V by $a \cdot \overline{f} = \overline{af}$. This will be a vector-space. If $\mathbb{F}$ is a finite field of order p, then we can show that V has p^n.
4. (If you know some calculus). Consider $\mathbb{R}[x]$. Then it is a vector-space over $\mathbb{R}$ ($\mathbb{R}[x]$ is an abelian group, and the action is simply the multiplication in $\mathbb{R}[x]$, since $\mathbb{R} \subseteq \mathbb{R}[x]$). Recall that the derivative has the following two properties:
$$\frac{d}{dx}(p(x) + q(x)) = \frac{d}{dx}p(x) + \frac{d}{dx}q(x)$$
$$\frac{d}{dx}(cf(x)) = c\left(\frac{d}{dx}f(x)\right)$$
This shows that the derivative is in fact a linear transformation (i.e. $\mathbb{R}$-module homomorphism) from $\mathbb{R}[x]$ to itself![a]
5. If R is a nonzero ring where the only two-sided ideals are (0) and R, then R is called a *simple ring* (similarly to how simple groups are groups whose only normal subgroups are $\{e\}$ and the entire group). Then $Z(R)$ (the center of the ring) *has* to be a field (can you show this?). If $k = Z(R)$, then any simple ring is a vector-space over its center.

[a]For those who know some Linear algebra and Fourier Analysis, the "diagonalization" of the derivative is the Fourier transform of a function! For details, see the Gelfand Transformation of unbounded operators

If $R = \mathbb{F}$ is a field, we give a special name to sub-modules:

Definition 12.1.11: Subspace

If $W \subseteq V$ is a submodule of a vector space, then we call it a *subspace*

12.1.12 Remark (If you know linear algebra) When determining where a linear transformation maps, it is sufficient to know where the basis maps to. General R-modules need not have a basis well-defined on them. However, *cyclic* modules will always have a basis, since $M = R \cdot x$ for some $x \in M$. Thus, R is always a cyclic R-module over itself since $R \cdot 1 = R$. General R-modules need not have a basis, and so R as an R-module a particularly nice module.
As a consequence of this, for any R-module homomorphism: $\varphi : R \to N$, it suffices to know where $\varphi(1)$ maps to. In general, it is much harder to determine a map $\varphi : M \to N$ given where only certain elements are mapped to.

Exercise 12.1.1

1. Let $\langle m \rangle = M$ be an R-module generated by a single element (i.e. if $x \in M$, $x = a_i m$ for some $a_i \in R$)[2]. Show that $\text{Ann}_R(M)$ (definition 12.3.21) is a two-sided ideal of R.
2. Let M be as in the previous question, with R commutative. Show that $R/\text{Ann}_R(M) \cong M$ as R-modules, so that ideals can be studied through the cyclic modules R/I.
3. (practice with categories). Let A be a set and $F(A)$ be the group freely generated by A (definition 2.3.29).
    1. Prove that the collection of all vector-spaces along with linear transformations form a category. Label it k-**Vect**.
    2. Show that $F(A)$ can have a vector-space structure over k put on it such that $F : \textbf{Set} \to k\textbf{-Vect}$ is a functor. (Hint: See the functor defined in section 2.3.5)
4. What is the initial object of Mod_R (if any)?

12.1.2 Algebras

Recall that if S is a ring, then it is always an abelian group, and there is always a unique homomorphism $\mathbb{Z} \to S$. Using this homomorphism, we can define a $\mathbb{Z}$-action given by $z \cdot s = \varphi(z)s$, and so every ring is automatically a $\mathbb{Z}$-module. More generally, any ring map $R \to S$ where R is commutative produces an R-module structure on the ring S that is compatible with the multiplication of S. To encapsulate this extra structure, we shall define a new term known as an *R-algebra* that represents a ring that also has a ring action on it.

The definition is simple if constrained to commutative rings, but there are many important cases where we must work with a non-commutative codomain (particularly in *Core Representation Theory* [22]), and so the above intuition must be made more precise. Given any ring homomorphism $\varphi : R \to S$, we can always define an R-module structure on S by defining

$$r \cdot s = \varphi(r)s$$

that is, the action is multiplication in S. The axioms of an R-module is immediate given the axioms of a ring and that φ is a homomorphism. Since we can multiply, we run into situations like the following: If $s_1 = r_1 \cdot x$ and $s_2 = r_2 \cdot y$, then:

$$s_1 s_2 = (r_1 \cdot x)(r_2 \cdot y)$$

[2] Module generation is the subject of section 12.3.

Such an element is not necessarily equal to $(r_1r_2)\cdot xy$ (similarly to how with rings, if the underlying set is not abelian, distributivity would not hold). This would be desirable, as in we would want $\varphi : R \to S$ to be a ring homomorphism that was also compatible with the R-module structure in the following way:

$$(r_1 \cdot x)(r_2 \cdot y) = (r_1r_2) \cdot xy$$

As a commutative diagram:

$$\begin{array}{ccc} (R \times S) \times (R \times S) & \xrightarrow{a \times a} & S \times S \\ \downarrow{\scriptstyle \ell} & & \downarrow{\scriptstyle m} \\ R \times S & \xrightarrow[a]{} & S \end{array}$$

where the left map is

$$\ell\big((r_1, x), (r_2, y)\big) = (r_1r_2,\ xy), \qquad \ell = (\mu_R \times m) \circ \sigma,$$

with σ the shuffle $\big((r_1, x), (r_2, y)\big) \mapsto \big((r_1, r_2), (x, y)\big)$.

Getting back to the homomorphism $\varphi : R \to S$ and the R-module structure on S, if we further require that R be *commutative* and that $\varphi(R) \subseteq Z(S)$ (the multiplicative center), then the left and right R-module structure will coincide (i.e. left and right multiplication produce the same module structure), and the ring operation of S will be compatible with that of R, that is

$$(r_1r_2) \cdot (s_1s_2) = \varphi(r_1r_2)(s_1s_2) = \varphi(r_1)\varphi(r_2)(s_1s_2) = \varphi(r_1)s_1\varphi(r_2)s_2 = (r_1 \cdot s_1)(r_2 \cdot s_2)$$

Boxing these properties we define an algebra:

Definition 12.1.13: R-algebra

Let S be a ring, R a commutative ring. Then S is called an (associative) R-algebra if S is also an R-module satisfying:

$$r \cdot (xy) = (r \cdot x)y = x(r \cdot y)$$

Equivalently, S is an R-algebra if there exists ring homomorphism $\varphi : R \to S$ where $\varphi(R) \subseteq Z(S)$. Furthermore:

1. If S is a division ring, then the R-algebra S is called a *division algebra*
2. If S is commutative, then the R-algebras S is called a *commutative algebra*

Note that S has has a natural R-module structure by forgetting the multiplication so that the action

$$r \cdot a[= a \cdot r] = \varphi(r)a$$

is the R-module structure. Unless otherwise stated, this will be the assumed R-module structure of an R-algebra S.

Algebra homomorphisms are defined similarly to how they have been defined before (can you figure it out without looking at the following definition?)

Definition 12.1.14: R-Algebra Homomorphism and Isomorphism

If A and B are R-algebra, then $\varphi : R \to S$ is an R-algebra homomorphism if φ is a ring-homomorphism and

$$r \cdot \varphi(x) = \varphi(r \cdot x)$$

If there exists an inverse function φ that is also an R-algebra homomorphism, then A and B are *algebra isomorphic*, or just *isomorphic* to each other, and we write $A \cong B$ if the context permits.

With this definition, the collection of R-algebra's along with R-algebra homomorphism forms the category R-**Alg**.

12.1.15 For the Categorically Inclined: Monoidal Object in R-module

Another way of saying that an R-algebra adds the notion of multiplication to an R-module in a "consistent" way is by noticing that R-algebra are the monoidal objects in the category of R-mod. Since all rings are $\mathbb{Z}$-modules, the discussion in section 9.7⋆ shows that rings are the monoidal objects in $\mathbb{Z}$-Mod (Hence, the category $\mathbb{Z}$-Alg is the category **Ring**).

$$\begin{array}{ccc}
(R \otimes S) \otimes (R \otimes S) & \xrightarrow{a \otimes a} & S \otimes S \\
\cong \downarrow {\scriptstyle 1_R \otimes \tau_{S,R} \otimes 1_S} & & \\
(R \otimes R) \otimes (S \otimes S) & & \downarrow {\scriptstyle m} \\
\mu_R \otimes m \downarrow & & \\
R \otimes S & \xrightarrow[a]{} & S
\end{array}$$

The word "associative" was put in parenthesis in the definition of an algebra since there is a notion of an algebra that is not associative: some author's say the object in definition 12.1.13 is an *associative algebra*, and define algebras more generally as follows: Take an R-module M, and equip it with a binary operation such that the binary operation is left and right distributive (for all $a, b, c \in M$, $a \cdot (b + c) = a \cdot b + a \cdot c$, an $(b + c) \cdot a = b \cdot a + c \cdot a$), and that it is compatible with scalars (for all $a, b \in R$ and $x, y \in M$, $(ab) \cdot (xy) = (a \cdot x)(b \cdot y)$), then M is called an R-algebra. If the binary operation is associative and an identity exists, then it would be a ring operation it will be called an associative algebra.

There is a good reason adding the prefix "associative" in the greater context of mathematics: a large domain of study in mathematics is the study of *lie groups* and *lie algebras*, which focus on understanding the structure of smooth manifolds and representations of algebraic groups. Notably, Lie algebras are *not associative*, satisfying instead a relation called the *Jacobi identity*. However, since they are non-associative, they are not *rings*. They are thus quite different objects from R-algebras as we have defined them, and so do not encompass our current discussion. Their study takes up many books (among them *Lie Groups* [97] and [63]) which the reader with a good background in linear algebra has the algebraic background to understand[3].

From now on, when we say algebra or R-algebra, we will mean an associative algebra as defined in

[3]Though a good basis in differential geometry would go a long way for intuition

definition 12.1.13.

If $R = k$ is a field, then using the terminology of vector-spaces, a k-algebra would be defining a way of multiplying vectors. It is non-trivial to always define a multiplication structure on an R-module (I suggest you try it on $\mathbb{R}^n$!). Even harder is to ask whether there is a "natural" way of creating a multiplication structure, or more broadly to make an R-module M big enough so that we can define an R-algebra in a "natural" way[4]. We will in fact define such a notion in section 16.3.

Example 12.1.16: R-Algebras

1. If R has positive characteristic p ($\#(\text{im}\mathbb{Z}) = p < \infty$), then it is more natural to define a $\mathbb{Z}/p\mathbb{Z}$-algebra, namely since as a $\mathbb{Z}$-algebra the kernel of the map $\mathbb{Z} \to R$ would be $p\mathbb{Z}$, and hence by the 1st isomorphism theorem it homomorphism commutes with $\mathbb{Z}/p\mathbb{Z} \to R$.

2. If S is commutative, then any subring of $R \subseteq S$ will define R-algebra on S (take $\iota : R \hookrightarrow S$). If S is not commutative, any subring of the center will define an R-algebra.

3. Let $R[x_1, x_2, ..., x_n]$ be the polynomial ring over several variables. Then it is an R-algebra through $r \cdot p(x) = rp(x)$.

4. Let $k[G]$ be a group ring over the field k. Then $k[G]$ is naturally a k-algebra.

5. If D is a divisor ring, then $Z(D)$ is always a *field*. If $k = Z(D)$, then any division ring D has a k-algebra structure on it, which also implies it is a vector-space over k.

6. Let $R = k^n$ for some field k. Then R is a k-algebra, with multiplication done point-wise.

7. Let $R = M_n(k)$ over a field k. Then R is a k-algebra. More generally, If A is a k-algebra, then $M_n(A)$ is a k-algebra.

   Compare this example to the previous one, which we will label $S = k^{n^2}$. As vector-spaces over k, $R \cong_k S$. However, as k-algebras, $R \ncong_{k\textbf{-Alg}} S$, since the multiplication structure is different between the two (one has nilpotent elements, the other does not).

8. If A, B are k-algebra, so is $A \times B$. By the previous part, that implies

   $$M_n(A) \times M_n(B)$$

   is also a k-algebra.

9. At the heart of real analysis is the $\mathbb{R}$-algebra $\mathbb{R}$, and at the heart of complex analysis is the $\mathbb{C}$-algebra $\mathbb{C}$. Note that $\mathbb{C}$ is also a $\mathbb{R}$-algebra.

10. Let $R = \mathbb{R}^2$. Then we know that $\mathbb{R}^2$ has point-wise multiplication, but we can also define the following:

    $$(a, b) \cdot (c, d) = (ac - bd, ad + bc)$$

    the multiplication of complex numbers $a + bi$ and $c + di$ written in coordinates, then this also forms an $\mathbb{R}$-algebra. In fact, this is $\mathbb{R}$-algebra isomorphic to $\mathbb{C}$ (over $\mathbb{R}$), by $(a, b) \mapsto a + bi$!

[4] natural meaning it satisfies the appropriate universal property

11. One might ask themselves how many $\mathbb{R}$-algebra's exist (i.e. classify all $\mathbb{R}$-algebras). A little more generally, one might ask how many finite-dimensional associatvive divison algebras there are, that is, algebra on which you can has division and asociativity, and the notion of finite-dimension is well-defined. Only $\mathbb{R}$, $\mathbb{C}$, and $\mathbb{H}$ exist, with dimension 1, 2, and 4! This is called *Frobenius' Theorem*. In this way, the real, compelx, and quaternions are kind of special. [a]

There are a large number of areas that algebras appear in, to name a notable few:

1. commutative algebras in algebraic geometry
2. Banach-Algebra's in real analysis
3. C^*-algebra or $*$-algebras more generally in functional analysis
4. Lie algebras in Lie theory, which are not algebras in the present sense, as their multiplication need not be associative. The cross product on $\mathbb{R}^3$ is an example: $(e_1 \times e_1) \times e_2 = 0$, while $e_1 \times (e_1 \times e_2) = e_1 \times e_3 = -e_2$. Every algebra A becomes a Lie algebra with the product $ab - ba$, see *Lie Groups* [97].

[a] https://math.stackexchange.com/questions/368456/frobenius-from-hurwitzs-theorem

Theorem 12.1.17: Universal Property of Free R-algebras

$R[A]$ is a free commutative R-algebra over a [finite set] A

Notice how this is similar to the universal property of commutative polynomial rings. In fact, that is a special case of this theorem by taking $R = \mathbb{Z}$

***Proof*:**
Let S be any commutative R-algebra and $\alpha : A \to S$ be any set-function. Since S is an commutative R-algebra, it is accompanied by a function $f : R \to S$ defining its multiplication.

Since $A = \{a_1, a_2, ..., a_n\}$ is finite, $R[A] = R[x_1, x_2, ..., x_n]$. Similarly to how the universal property of polynomial rings was proven (theorem 9.2.4), we will extend $f : R \to S$ to $f_1 : R[x_1] \to S$ by mapping $f_1(x_1) = \alpha(a_1)$ and extending linearly. f_1 is still an R-algebra homomorphism since $f_1(n_0 + n_1 x + n_2 x^2 + \cdots + n_k x^k) = f(n_0) + f(n_1)\alpha(a_1) + f(n_2)\alpha(a_1)^2 + \cdots + f(n_k)\alpha(a_1)^k$, and Similarly for multiplying two polynomials (using the binomial theorem and both the additive and multiplicative linearity of f_1). We can again extend f_1 to f_2 by defining $f_2(a_2) = \alpha(a_2)$ so that $f_2 : (R[x_1])[x_2] \to S$ (usually written as $f_2 : R[x_1, x_2] \to S$) is an R-algebra homomorphism. Continuing inductively will get us an R-algebra homomorphism $F : R[x_1, x_2, ..., x_n] \to S$. Thus, picking $\iota : A \to R[x_1, x_2, ..., x_n]$ will show that $\alpha : A \to S$ lifts uniquely to $F : R[A] \to S$, as we sought to show.

As a consequence of this, all R-algebras are quotient of polynomial rings!! That is, if S is a finitely generearted S algebra

$$R[x_1, x_2, ..., x_n] \twoheadrightarrow S$$

12.1.3 Abelian Groups as Modules

Some entire domains of study are done on particular modules. We have already studied a particular collection modules extensively! The most immediate example is that all rings are R-modules over themselves with the action defined by:

$$r \cdot x = rx$$

Then submodules are precisely the ideals of R, and so the study of all R-modules includes the study of the ring R.

In this section, we show another important classes of R-modules: let $R = \mathbb{Z}$, and let $M = A$ be *any* abelian group (finite or infinite), and write the operation of A as $+$. Make A into a $\mathbb{Z}$-module by defining the ring action as :

$$na = \begin{cases} a + a + \cdots + a \ (n \text{ times}) & \text{if } n > 0 \\ 0 & \text{if } n = 0 \\ -a - a - \cdots - a \ (n \text{ times}) & \text{if } n < 0 \end{cases}$$

Then M is a $\mathbb{Z}$-module. In fact, this ring action is the only possible ring action on M (i.e. abelian groups):

Proposition 12.1.18: Abelian Group iff $\mathbb{Z}$-module

Every abelian group is a $\mathbb{Z}$-module, and every $\mathbb{Z}$-module is an abelian group

***Proof*:**
for $\Rightarrow$, we can always define the previous ring-action and so it's always a $\mathbb{Z}$-module

For $\Leftarrow$, it is simply a consequence of the existence of 1 and the distributivity property, i.e., the ring action $\mathbb{Z}$ performs on abelian groups is "stuck" since we must play out the consequence of the axioms.

By definition

$$n \cdot 1 = n$$

and therefore

$$n \cdot 2 = n \cdot (1 + 1) = n \cdot 1 + n \cdot 1 = n + n$$


and continuity inductively

$$n \cdot k = n \cdot (1 + \cdots + 1) = n + \cdots + n$$

k times. This result is exactly the ring action we defined earlier. And so, forced by the axioms of groups and modules, it must be that every $\mathbb{Z}$ action on an abelian foms this particular $\mathbb{Z}$-module.

This proposition has a very intersting consequence: for every R-module, $R \neq \mathbb{Z}$, then it always has at least one other module structure, namely the natural $\mathbb{Z}$-module structure! An intuitive way to remember this fact is that numbers as we have learnt them earlier in our life usually have a $\mathbb{Z}$-module structure ($\mathbb{Z}$, $\mathbb{Q}$, $\mathbb{R}$, $\mathbb{C}$). The natural numbers form an abelian monoid that is not a group, so this intuition does not apply to $\mathbb{N}$.

This example can also make us think of the class of all abelian groups as a subclass of modules. Abelian groups are also a subclass of groups. However, not every group is a module (and vice versa). The following diagram I'm about to draw should not be taken as a commutative diagram, but as an "analogy":



So in a sense, we are "switching gears" when studying modules. We are taking a different approach to the study of algebraic structures as compared to studying groups.

Exercise 12.1.2

1. Recall that for any $\alpha \in R$ for a ring R, $f_\alpha : R[x] \to R$ mapping $p(x) \mapsto p(a)$ is a ring-homomorphism. Is it an R-module homomorphism?

12.2 Homomorphism and Quotients of Modules

In this section we explore R-module homomorphisms and how the image of R-module homomorphisms can be represented by a particular quotient of the domain (as we have seen with groups and rings). As R-module homomorphsism are explored, they should be constrasted to rings in that they will have many nicer properties. They are in fact comparable to abelian groups. Every subgroup of an abelian group is normal, and so too every submodule of a R-module will be "normal".

R-Module Homomorphisms

Definition 12.2.1: R-module homomorphism Terminology

Let R be a ring, M and N be R-module, and $\varphi : M \to N$ be a function. Then:

1. φ is called an *R-module homomorphism* if:
   (a) $\varphi(x+y) = \varphi(x) + \varphi(y)$ for all $x, y \in M$
   (b) $\varphi(r \cdot x) = r\varphi(x)$, for all $r \in R$, $m \in M$

   If furthermore there exists a φ^{-1} such that $\varphi \circ \varphi^{-1} = \varphi^{-1} \circ \varphi = \text{id}$ and φ^{-1} is an R-module homomorphism, then φ is called an *R-module isomorphism* and we write $M \cong_{R\textbf{-Mod}} N$, or $M \cong N$ if it is unambiguous

   If $R = k$ is a field, then k-module homomorphisms are called *linear maps*, *linear functions*, or *linear transfomration*, and k-module isomorphisms are called *linear isomorphisms* (due to historical precedence)

2. Denote
   (a) $\ker(\varphi) = \{m \in M \mid \varphi(m) = 0\}$
   (b) $\text{im}(\varphi) = \varphi(M) = \{n \in N | \varphi(m) = n\}$

3. Define $\text{Hom}_R(M, N)$ be the set of all R-module homomorphisms from M into N, $\text{End}_R(M)$ the set of all R-module homomorphism from M to itself, and $\text{Aut}_R(M)$ the set of all all R-module isomorphisms from M to itself. A function $\varphi \in \text{End}_R(M)$ is called an *R-module enormophism*, and a function $\varphi \in \text{Aut}_R(M)$ is called an *R-module automorphism*.

Notice how it's key that the two structures be R-modules. If M is an R-module and N is an S-module, then $\varphi : M \to N$ is not an R-module or S-module homomrophsim unless either R has a compatible S-module structure of N has a compatible R-module structure that is preserved under φ (this is similar to how G-equivariant functions are betwen two G-sets)

Many of the properties demonstrated of group and ring homomorphisms apply for R-modules

Lemma 12.2.2: R-Module Homomorphism Equivalence

Let $\varphi : M \to N$ be a function. Then φ is an R-module homomorphism if and only if for every $r \in R$ and $x, y \in M$,

$$\varphi(x + ry) = \varphi(x) + r\varphi(y)$$

***Proof*:**
First suppose φ is an R-module homomorphism. Then for every $r \in R$ and $x, y \in M$,

$$\varphi(x + ry) = \varphi(x) + \varphi(ry) = \varphi(x) + r\varphi(y)$$

using additivity and then compatibility with the ring action.

Conversely, suppose $\varphi(x+ry) = \varphi(x) + r\varphi(y)$ for every $r \in R$ and $x, y \in M$. Taking $r = 1$ and using the unital axiom in N gives

$$\varphi(x+y) = \varphi(x) + 1 \cdot \varphi(y) = \varphi(x) + \varphi(y)$$

so φ is additive. In particular $\varphi(0) = \varphi(0+0) = \varphi(0) + \varphi(0)$, and cancelling in the abelian group N gives $\varphi(0) = 0$. Taking $x = 0$ in the hypothesis now gives

$$\varphi(ry) = \varphi(0+ry) = \varphi(0) + r\varphi(y) = r\varphi(y)$$

so φ is compatible with the ring action, and φ is an R-module homomorphism.

Lemma 12.2.3: R-Module Isomorphism Equivalence

Let $\varphi : M \to N$ be an R-module homomorphism. Then φ is an R-module isomorphism if and only if φ is an R-module homomorphism and bijective

***Proof*:**
An isomorphism has an inverse function, so it is bijective. Conversely, let φ be a bijective R-module homomorphism with inverse function ψ. For $x, y \in N$ and $r \in R$,

$$\psi(x+y) = \psi(\varphi(\psi(x)) + \varphi(\psi(y))) = \psi(\varphi(\psi(x) + \psi(y))) = \psi(x) + \psi(y)$$

and $\psi(rx) = \psi(r\varphi(\psi(x))) = \psi(\varphi(r\psi(x))) = r\psi(x)$. So ψ is an R-module homomorphism and φ is an isomorphism, completing the proof.

Lemma 12.2.4: Composition Of R-Module Homomorphism/Isomorphism

Let M, N, L be R-modules. If $\varphi \in \mathrm{Hom}_R(L, M)$ and $\psi \in \mathrm{Hom}_R(M, N)$ then $\psi \circ \varphi \in \mathrm{Hom}_R(L, N)$

***Proof*:**
For every $r \in R$ and $x, y \in L$,

$$(\psi \circ \varphi)(x + ry) = \psi\big(\varphi(x) + r\varphi(y)\big) = \psi(\varphi(x)) + r\psi(\varphi(y)) = (\psi \circ \varphi)(x) + r(\psi \circ \varphi)(y)$$

where the first equality applies lemma 12.2.2 to φ and the second applies it to ψ. By lemma 12.2.2 again, $\psi \circ \varphi$ is an R-module homomorphism, that is, $\psi \circ \varphi \in \mathrm{Hom}_R(L, N)$.

Lemma 12.2.5: R-module Automorphism Group

Let $\mathrm{Aut}_R(M)$ be the set of R-module automorphisms on M. Then $(\mathrm{Aut}_R(M), \circ)$ forms a group under composition.

***Proof*:**
For closure, let $\varphi, \psi \in \mathrm{Aut}_R(M)$. By lemma 12.2.4, $\psi \circ \varphi$ is an R-module homomorphism, and by the same lemma so is $\varphi^{-1} \circ \psi^{-1}$. Since

$$(\psi \circ \varphi) \circ (\varphi^{-1} \circ \psi^{-1}) = \mathrm{id} = (\varphi^{-1} \circ \psi^{-1}) \circ (\psi \circ \varphi)$$

the homomorphism $\psi \circ \varphi$ has a two-sided inverse which is itself an R-module homomorphism, so $\psi \circ \varphi \in \mathrm{Aut}_R(M)$ by definition 12.2.1.

Associativity holds because composition of functions is associative.

For the identity, $\mathrm{id}_M(x+ry) = x+ry = \mathrm{id}_M(x)+r\mathrm{id}_M(y)$, so id_M is an R-module homomorphism by lemma 12.2.2, and it is its own two-sided inverse, so $\mathrm{id}_M \in \mathrm{Aut}_R(M)$. Moreover $\mathrm{id}_M \circ \varphi = \varphi \circ \mathrm{id}_M = \varphi$ for every φ.

Finally, for inverses, let $\varphi \in \mathrm{Aut}_R(M)$. By definition 12.2.1, φ^{-1} is an R-module homomorphism, and φ is a two-sided inverse of φ^{-1} which is an R-module homomorphism, so $\varphi^{-1} \in \mathrm{Aut}_R(M)$, and $\varphi \circ \varphi^{-1} = \varphi^{-1} \circ \varphi = \mathrm{id}_M$.

Example 12.2.6: Module Homomorphisms

1. if a ring is an R-module over itself with the natural ring action, then R-module homomorphisms need not be ring homomorphisms (even from R to itself), and ring homomorphisms need not be R-module homomorphisms. For example, $\mathbb{Z}$ act on itself in the natural way, and let $\varphi(x) = 2x$. φ is not a ring homomorphism [a], but φ is an R-module homomorphism. For the example going the other way, $F[x]$ act on itself in the natural way, and let $\varphi : f(x) \mapsto f(x^2)$. Then φ is not an $F[x]$-module homomorphism [b], but it is a ring homomorphism.

2. Let R be a ring and $M = R^n$ be an R-module with the natural ring action. Then the projective map is naturally an R-module homomorphism.

3. If we take $\mathbb{R}$ to be an $\mathbb{R}$ module over $\mathbb{R}$, then $\mathbb{R}$ has no non-trivial submodules (since $\mathbb{R}$ is a field, it's only ideals are 1 and itself). We call such a module a simple or an irreducible module. Thus, the quotient structure of $\mathbb{R}$ as an $\mathbb{R}$-module is trivial. However, if we consider $\mathbb{R}$ as a $\mathbb{Q}$-module (which we can). Then $\mathbb{Q}$ is a submodule of $\mathbb{R}$ (since $\mathbb{Q}$ is closed under the ring action of $\mathbb{Q}$)! $\mathbb{R}$ as a $\mathbb{Q}$-module will be an infinite-dimensional vector-space [c]. Therefore, it becomes meaningful in this situation to look at $\mathbb{R}/\mathbb{Q}$ under the $\mathbb{Q}$ action!!

4. It should be done as an exercise that if $\varphi : M \to N$ is an R-module homomorphism, then the image and kernel are both R-modules.

[a] $\varphi(xy) = 2xy \neq 2x2y = \varphi(x)\varphi(y)$
[b] $x^2 = \varphi(x) = \varphi(x \cdot 1) = x\varphi(1) = x$, a contradiction
[c] In fact, it will even be *uncountably* infinite-dimensional

Recall in remark HomGrpIfAbRmk that $(\mathrm{Hom}_{\mathbf{Set}}(A, G), +)$ (where $+$ is defined pointwise: $f+g(x) = f(x) + g(x)$) can be given a group structure if G is abelian, and is not a group if G was not abelian (i.e. it not important what the domain was for the structure of the hom-set). Since every R-module is always over an abelian group, $\mathrm{Hom}_R(M, N)$ is *always* an abelian group. In the following proposition we further the structure of $\mathrm{Hom}_R(M, N)$

Proposition 12.2.7: Properties of $\mathrm{Hom}_R(M,N)$

Let M, N and L be R-module. Then

1. $(\mathrm{Hom}_R(M,N),+)$ is an abelian group with $+$ being defined pointwise:

$$(\varphi+\psi)(m)=\varphi(m)+\psi(m) \qquad \forall \varphi,\psi\in \mathrm{Hom}_R(M,N),\ \forall m\in M$$

   In particular $\varphi+\psi\in\mathrm{Hom}_R(M,N)$

2. If R is a commutative ring, then for $r\in R$ define $r\varphi$ by

$$(r\varphi)(m)=r(\varphi(m)) \qquad \text{for all } m\in M$$

   Then $r\varphi\in\mathrm{Hom}_R(M,N)$, and with this action $\mathrm{Hom}_R(M,N)$ is an R-module.

3. With addition defined as above, $(\mathrm{End}_R(M),+,\circ)$ is a ring. When R is commutative, $\mathrm{End}_R(M)$ is an R-algebra.

***Proof*:**
The first statement was proven above remark HomGrpIfAbRmk.

For an R-action to be defined on $\mathrm{Hom}_R(M,N)$ we would need the following to be equal:

$$(rs\varphi)(m)=rs\cdot\varphi(m)$$
$$(r(s\varphi))(m)=r\cdot(s\varphi)(m)=sr\cdot\varphi(m)$$

showing R must be commutative. The other axioms follow quickly

Finally, $(\mathrm{End}_R(M),+,\circ)$ follows the ring axioms. If R is commutative then for ring homomorphism $f:R\to\mathrm{End}_R(M)$, since f is commutative, $f(R)$ is always abelian, and hence $f(R)\subseteq Z(\mathrm{End}_R(M))$, and so $\mathrm{End}_R(M)$ is always an R-algebra, completing the proof.

Note that $(\mathrm{Aut}_R(M),+)$ is *not* a group structure, since the identity *does not exist* (the zero homomorphism is not an automorphism)![5]

Like with groups and rings, we want to know what conditions are needed on a sub-module so that:

$$(x+N)+(y+N)=(x+y)+N \qquad r(x+N)=(rx)+N$$

are both well defined. Since Modules are already abelian groups, than M/N is already well-defined as an abelian group! What's left is to see what condition's are needed so that a submodule N can be used to define an R-module structure on the abelian group M/N. Like abelian groups, every sub-module is "normal"!

[5] semi-groups are groups without an identity. Thus, $(\mathrm{Aut}_R(M)+)$ is a natural example of a semi-group(!), with a compatible group structure with $\circ$

Proposition 12.2.8: sub-modules are "normal" sub-modules

Let R be a ring and let M be an R-module and let N be a submodule of M. The (additive, abeliean) quotient group M/N can be made into an R-module by definin an action of elements of R by

$$r(x+N) = (rx) + N, \qquad \text{for all } r \in R,\ x+N \in M/N$$

The natural projection $\pi : M \to M/N$ defined by $\pi(x) = x+N$ is an R-module homomorphism with kernel N.

***Proof*:**
First, M/N is already an abelian quotient group. We want the ring action to be well defined, that is

$$x + N = y + N$$

which equivalently means that $x - y \in N$. Since N is a submodule, $r(x-y) \in N$, thus

$$rx + N = ry + N$$

therefore, the R-action on M naturally induces an action on M/N. The rest of the module axioms can now e easily verified.

Next, we must show the implication goes the other way, that is, if the elements of the quotient groups are formed by the cosets $x+N$, then N is the kernel of some R-module homomorphis (i.e. the natural projection). The natural projection map π described above is already the natural projection of the abelian group M into the abelian group M/N. It only remains to show that it is a R-module homomorphism:

$$\begin{aligned} \pi(rm) &= rm + N \\ &= r(m+N) && \text{(by definition of the action of } R \text{ on } M/N) \\ &= r\pi(m) \end{aligned}$$

Thus, the natural projection an R-module homomorphism, completing the proof.

As with groups and rings, R-modules also have the isomorphism theorems. Since R-modules are already abelian groups, half the proof is already done. What is left to check would be if the action still preserved under the isomorphisms. To define the 2nd isomorphism theorem, we define what it means to take sum of two modules:

Definition 12.2.9: Sum Of Modules

Let A, B be submodules of an R-module M. Then the *sum* of A and B is the set

$$A + B = \{a + b | a \in A, b \in B\}$$

As before, $A + B$ is the smallest module containing A and B (as you sould check)

Theorem 12.2.10: Isomorphism Theorems For Modules

1. Let M, N be R-modules and let $\varphi : M \to N$ be an R-module homomorphism. Then $\ker(\varphi)$ is a submodule of M and
$$M/\ker(\varphi) \cong \varphi(M)$$
2. Let A, B be submodules of the R-module M. Then
$$\frac{A+B}{B} \cong \frac{A}{A \cap B}$$
3. Let M be an R-module, and let A and B be submodules of M, with $A \subseteq B$. Then
$$(M/A)/(B/A) \cong M/B$$
4. Let N be a submodule of the R-module M. There is a bijection beetween the submodules of M which contain N and the submodules of M/N. The correspondence is give nby $A \leftrightarrow A/n$, an for all $A \supseteq N$. The correspondence commutes with the processes of taking sums and intersection (i.e., is a lattice isomorphism between the lattice of submodules of M/N an dthe lattice of submodules of M which contain N

***Proof*:**
Quotients of R-modules by submodules are R-modules by proposition 12.2.8, and a bijective R-module homomorphism is an isomorphism by lemma 12.2.3.

1. The kernel is a subgroup of M, and it is closed under the action, since $\varphi(rm) = r\varphi(m) = 0$ for $m \in \ker(\varphi)$. Likewise $\varphi(M)$ is a submodule of N, as $r\varphi(m) = \varphi(rm)$. The map $\Phi\colon M/\ker(\varphi) \to \varphi(M)$, $m + \ker(\varphi) \mapsto \varphi(m)$, is well defined and injective, since $\varphi(m) = \varphi(m')$ exactly when $m - m' \in \ker(\varphi)$, and it is surjective. It is R-linear, since $\Phi((m + \ker(\varphi)) + (m' + \ker(\varphi))) = \varphi(m + m') = \varphi(m) + \varphi(m')$ and $\Phi(r(m + \ker(\varphi))) = \varphi(rm) = r\varphi(m)$. So Φ is an isomorphism.
2. The sum $A+B$ is a submodule of M containing B, since $(a+b)+(a'+b') = (a+a')+(b+b')$ and $r(a+b) = ra+rb$. The map $A \to (A+B)/B$, $a \mapsto a+B$, is R-linear, and it is surjective, since $(a + b) + B = a + B$. Its kernel is $A \cap B$, so (1) gives $A/(A \cap B) \cong (A + B)/B$.
3. The subset $B/A = \{b + A \mid b \in B\}$ of M/A is a submodule, since $r(b + A) = rb + A$. The map $M/A \to M/B$, $m + A \mapsto m + B$, is well defined because $A \subseteq B$, and it is R-linear and surjective, with kernel B/A. So (1) gives $(M/A)/(B/A) \cong M/B$.
4. Let $\pi\colon M \to M/N$ be the natural projection, which is R-linear (proposition 12.2.8). Applied to the additive groups, theorem 3.5.7 shows that $A \mapsto A/N = \pi(A)$ is a bijection from the subgroups of M containing N onto the subgroups of M/N, with inverse $\overline{A} \mapsto \pi^{-1}(\overline{A})$. The image of a submodule under the R-linear map π is a submodule, and so is the preimage of a submodule, so the bijection restricts to a bijection between the submodules of M containing N and the submodules of M/N. Both directions preserve inclusions. The sum of two submodules is the smallest submodule containing both, since by (2) it is a submodule and

every submodule containing both contains each sum of an element of one and an element of the other, and the intersection is the largest submodule contained in both. Write β for the bijection and let $A, B \supseteq N$ be submodules. As $A, B \subseteq A+B$, also $\beta(A), \beta(B) \subseteq \beta(A+B)$, so $\beta(A)+\beta(B) \subseteq \beta(A+B)$. Conversely $\beta^{-1}(\beta(A)+\beta(B))$ is a submodule containing A and B, so it contains $A+B$, and applying β gives $\beta(A+B) \subseteq \beta(A)+\beta(B)$. For intersections, $A \cap B \subseteq A, B$ gives $\beta(A \cap B) \subseteq \beta(A) \cap \beta(B)$, and $\beta^{-1}(\beta(A) \cap \beta(B))$ is a submodule contained in A and in B, so it lies in $A \cap B$, and applying β gives $\beta(A) \cap \beta(B) \subseteq \beta(A \cap B)$, completing the proof.

12.2.1 Extensions and Exactness

We conclude this section with a quick word on extensions and where they will show up. Similarly to groups (and rings), we may wonder under what conditions is a module M an extension of two modules A and B, that is $M \cong B/A$, or in terms of a short exact sequence:

$$0 \to A \to M \to B \to 0$$

Section 3.7 showed that mathematicians managed to find the building blocks of finite group extensions, known as simple groups, and classify all finite simple groups, and section 5.4 showed that semi-direct products can be represented by split exact sequences. The classification of simple modules depends on the ring that's acting, R, and is much simpler since the underlying group is abelian. Similar to groups, there exist classification project for R-modules for some particular rings R, at least four of which will be covered in this book[6].

We also endeavour to study R-modules in which the extension property works nicely. This is further explored in chapter 51. Since all modules are abelian groups, the semi-direct product is simply the direct product. However, split exact sequences are still an important concept since it gives us a way of recognizing direct products using homomorphisms. A particularly interesting collection of modules are those for which every short exact sequence is a split exact sequence, or phrased differently that every short exact sequence splits. This endeavour is taken up in chapter 17$\star$, and explored in full length in *Homological Algebra* [29].

The vocabulary for a sequence of R-module homomorphisms that represent extensions is quite important, and so we define the term here for future use:

Definition 12.2.11: Exact Chain Complex

Let $M_0, M_1, M_2, ..., M_n, ...$ is a collection of R-modules $d_i : M_i \to M_{i-1}$ be a collection of R-module homomorphisms where

$$\cdots \xleftarrow{d_0} M_0 \xleftarrow{d_1} M_1 \xleftarrow{d_2} \cdots \xleftarrow{d_n} M_n \xleftarrow{d_{n+1}} \cdots$$

and $\ker(d_i) = \text{im}(d_{i-1})$. Then the tuple $(M_i, d_i)_{i=-\infty}^{\infty}$ is called an *exact chain complex*, *exact chain*, or *exact sequence*. Often, we abbreviate and write $(M_\bullet, d_\bullet)$. If the arrows are pointing the opposite direction and $\ker(d_i) = \text{im}(d_{i+1})$ then the resulting tuple $(M_i, d_i)_{i=-\infty}^{\infty}$ is called an *exact cochain*. If the chain has only finite length, (i.e. only finitely many of the modules are non-zero), then the resulting exact (co)chain is called a *finite exact (co)chain*.

[6] When R is a Field, a Principal Ideal Domain, a Dedekind Domain, and Semi-Simple

A single homomorphism already sits inside such a chain, once one more module is named.

Definition 12.2.12: Cokernel

Let $\varphi\colon M \to N$ be a homomorphism of R-modules. The *cokernel* of φ is the quotient module

$$\operatorname{coker}(\varphi) := N/\operatorname{im}(\varphi)$$

The kernel measures how far φ is from being injective and the cokernel how far it is from being surjective: φ is injective exactly when $\ker(\varphi) = 0$, and surjective exactly when $\operatorname{coker}(\varphi) = 0$. Both statements are packaged in the one exact sequence

$$0 \to \ker(\varphi) \xhookrightarrow{\iota} M \xrightarrow{\varphi} N \xrightarrow{\pi} \operatorname{coker}(\varphi) \to 0$$

which is exact at $\ker(\varphi)$ because ι is injective, at M because $\ker(\varphi)$ is by definition $\operatorname{im}(\iota)$ and is what φ kills, at N because $\ker(\pi) = \operatorname{im}(\varphi)$ is exactly what the quotient divides out, and at $\operatorname{coker}(\varphi)$ because π is surjective.

Example 12.2.13: Kernels And Cokernels

1. Let $n \geq 2$ and let $\varphi\colon \mathbb{Z} \to \mathbb{Z}$ be multiplication by n, a homomorphism of $\mathbb{Z}$-modules. As $nx = 0$ forces $x = 0$ in $\mathbb{Z}$, $\ker(\varphi) = 0$, and $\operatorname{im}(\varphi) = n\mathbb{Z}$, so the sequence reads

   $$0 \to 0 \to \mathbb{Z} \xrightarrow{\cdot n} \mathbb{Z} \to \mathbb{Z}/n\mathbb{Z} \to 0$$

   The map φ is injective and, as $\mathbb{Z}/n\mathbb{Z} \neq 0$, not surjective, although its source and target are the same module.

2. Let $\varphi\colon \mathbb{Z}^2 \to \mathbb{Z}^2$ be $\varphi(x, y) = (x + y, 2x + 2y)$, the map given by the matrix with rows $(1, 1)$ and $(2, 2)$. Then $\varphi(x, y) = 0$ exactly when $y = -x$, so $\ker(\varphi) = \{(t, -t) \mid t \in \mathbb{Z}\} \cong \mathbb{Z}$, and $\operatorname{im}(\varphi) = \{(s, 2s) \mid s \in \mathbb{Z}\}$. The homomorphism $\psi\colon \mathbb{Z}^2 \to \mathbb{Z}$, $\psi(a, b) = b - 2a$, is surjective, since $\psi(0, b) = b$, and its kernel is $\{(a, 2a) \mid a \in \mathbb{Z}\} = \operatorname{im}(\varphi)$, so $\operatorname{coker}(\varphi) \cong \mathbb{Z}$ by theorem 12.2.10(1). The sequence becomes

   $$0 \to \mathbb{Z} \xrightarrow{t \mapsto (t,-t)} \mathbb{Z}^2 \xrightarrow{\varphi} \mathbb{Z}^2 \xrightarrow{\psi} \mathbb{Z} \to 0$$

   and φ is neither injective nor surjective, with kernel and cokernel both isomorphic to $\mathbb{Z}$.

3. Let R be a ring and let $\pi\colon R^2 \to R$ be the projection $\pi(a, b) = a$. It is surjective, so $\operatorname{coker}(\pi) = 0$, and $\ker(\pi) = \{(0, b) \mid b \in R\} \cong R$. The sequence becomes

   $$0 \to R \xrightarrow{b \mapsto (0,b)} R^2 \xrightarrow{\pi} R \to 0 \to 0$$

   For the inclusion $\iota\colon R \to R^2$, $a \mapsto (a, 0)$, the roles are exchanged: $\ker(\iota) = 0$, and $(a, b) \mapsto b$ is a surjective homomorphism $R^2 \to R$ with kernel $\operatorname{im}(\iota)$, so $\operatorname{coker}(\iota) \cong R$ by theorem 12.2.10(1).

A presentation $R^n \xrightarrow{\varphi} R^m \xrightarrow{\pi} M \to 0$ of a module M (definition 12.3.26) gives $M \cong \operatorname{coker}(\varphi)$, since π is surjective with kernel $\operatorname{im}(\varphi)$ (theorem 12.2.10(1)). So modules given by generators and relations are cokernels, and this is why the sequence recurs in chapter 13 and chapter 14. Section 13.2.5 computes such cokernels from a matrix. For a linear map φ between vector spaces of the same finite

dimension, the Rank-Nullity Theorem (corollary 13.1.18) gives $\ker(\varphi) = 0$ exactly when $\operatorname{coker}(\varphi) = 0$ (corollary 13.1.20), and the first example above shows that this fails over $\mathbb{Z}$. Over a PID, every finitely generated module is the cokernel of an injective map of free modules (corollary 14.1.8) whose matrix is diagonal in suitable bases (corollary 14.1.7), and the cokernel of a diagonal matrix with diagonal entries $a_1, \ldots, a_m$ is the direct sum of the cyclic modules $R/(a_i)$ and a free module, which is the form in theorem 14.1.9. Further on, proposition 17.1.10 joins the kernels and cokernels of the three maps of a homomorphism of short exact sequences into one exact sequence, and proposition 17.6.7 computes Ext and Tor of $\mathbb{Z}/n\mathbb{Z}$ against an abelian group A as the kernel $A[n]$ and the cokernel A/nA of multiplication by n on A.

Exercise 12.2.1

1. Let M be an R-module. Prove that $\operatorname{Hom}_R(R, M) \cong M$
2. Let R^{op} be the opposite ring of R (exercise 9.1.1 (13)), and let $\operatorname{End}_R(R)$ be all R-module homomorphisms from R to itself. Considering $(\operatorname{End}_R(R), +, \circ)$ as a ring show that $R^{\text{op}} \cong_{\mathbf{Ring}} \operatorname{End}_R(R)$ [Hint ; think of Yoneda's lemma]

12.3 Generation of Modules

We now extend the notion of generating algebraic structures to subsets of a module. We will start by generalizing the results of section 2.3.2: we take a subset of an R-module, and permit all possible combinations and R-actions of those elements to form an R-module, or equivaelntly we take the intersection of all R-submodules containing the elements of the set.

Then, as with groups and rings, the easiest way of creating a larger module from smaller ones is to take the direct sum or direct product. Due to their simplicity, it is worth taking the time to find out under what condition's can a module be decomposed into direct products or sums (just like for groups in section 5.2). We then take the approaching of trying to define the "most free" module we can put on an arbitrary set, similar to what we have done in section 2.3.4, that is we are looking to find the universal property of free-modules. As compared to groups, we will spend more time looking at minimal generating sets. Recall that for groups, it is possible that minimal generating sets can differ in cardinatliy. With modules, we will ask if there are modules where there exists a subset $A \subseteq M$ such that A generates M and if any other subset B generated A, then $|A| \leq |B|$. It will turn out that some modules have this property, some will be close, and other will not have this property at all.

After having tackled the question of generating modules "freely" and how to recognize free modules, we will then turn our attention to finitely generated modules, and modules where all submodules are finitely generated. Similalrly to how we can classify all finitely generated abelian groups, finitely generated and Noetherian modules have more "regularly", or equivalently have less "pathological" properties.

A new approach to studying structure's of objects we will take is considering the collection of homomorphisms on modules. As we saw in proposition 12.2.7, $\operatorname{Hom}_R(M, N)$ is always an abelian group, and if R is commutative it is always R-module. Thus, the "symmetries" of an R-module are themselves and R-module, meaning we would like to explore what properties M or N can have given the properties of $\operatorname{Hom}_R(M, N)$ have as an R-module, or even better that $\operatorname{End}_R(M)$ has as an R-algebra. This exploration is very fruitful, and will be of key importance in the theory

of representation (of finite groups, lie algebras, etc.). In fact, if this intrigues the reader, after reading chapter 13 and chapter 14, the reader can skip to chapter 51 (only requiring knowledge from section 19.5 for the last 2 propositions of that chapter). A particular example of the above is when $N = R$ so that we consider $\text{Hom}_R(M, R)$. This module is called the *dual module* of M, and will be very important in the study of M, even outside the field of algebra[7].

How does the generation of modules compare to the generation of groups and rings? With general groups, we saw that it was very difficult to show what the elements in an arbitrarily generated group look like (it is considered one of the hardest problems in mathematics, known as the *word problem for groups*). However, if G is abelian and finitely generated, then every element can be written in a very simple form due to the fundamental theorem of finitely generated abelian groups (theorem 5.1.6) With rings, we had that the objects that we quotient by (ideals) were no longer rings, and so took the time to study generation of ideals, but we have not studied any structure theorems on rings.

With modules, the story of the exploration of module structures is much closer to that of abelian groups, namely because every module *is* an abelian group. One major advantage of studying module is that many of the previous structure's we have studied can be represented as modules: since all abelian groups are $\mathbb{Z}$-modules, the study of the structure of abelian group is subsumed in the study of the structure of modules (we prove the Fundamental Theorem of Finitely Generated Abelian Groups in greater generality in chapter 14), and since all rings are module over themselves, the study of the structure of modules is also the study of the structure of rings! Due to the fact that all module are abelian groups, we can always collect "like terms":

$$r_1a_1 + r_2a_2 + s_1a_1 = (r_1 + s_1)a_1 + a_2$$

due to this, the order of the generating elements does not affect their sum! It becomes meaningful to ask if the ring acting on a module somehow determines some (or even all!) of the structure of the module. This question is a very meaningful question, and the answer will vary depending on what type of ring is acting on the module: chapters 13 and 14 and chapter 53 will each focus modules over particular types of rings and show how the answer to this question changes depending on what type of ring is acting on the module.

12.3.1 Direct Sum of Modules

We first update the terminology from the generation of groups and rings for the generation of modules:

[7] dual modules are central to Functional analysis and Harmonic Analysis

Definition 12.3.1: Generating Modules

Let M be an left R-module and let $(N_i)_{i\in I}$ be the submodules of M where I is an indexing set.

1. The *sum* of $(N_i)_{i\in I}$ is the smallest submodule of M containing each N_i, and is the set of all finite sums of elements from N_i:

$$\sum_i N_i := \{a_1 + \cdots + a_k | a_i \in N_i \text{ for all } i\}$$

If I is finite with $|I| = k$, then it is usually written as

$$N_1 + \cdots + N_k$$

2. For any subset $A \subseteq M$, then RA is the set:

$$RA = \left\{r_1a_1 + \cdots + r_ma_m | r_1, ..., r_m \in R, a_1, ..., a_m \in A, m \in \mathbb{Z}^+\right\}$$

(where by convention $RA = \{0\}$ if $A = \emptyset$) is the smallest [left] submodule of M generated by the elements of A, an is called the *[left] submodule generated by A*. If A is finite the set $\{a_1, a_2, ..., a_n\}$ we shall write

$$Ra_1 + \cdots Ra_n$$

If N is a submodule of M (possibly $N = M$) and $N = RA$, for some subset, then A is called the *set of generators* or *generating set for* N, and we say N is generated by A and is sometimes written as $\langle A\rangle = N$.

3. A submodule N of M (possibly $N = M$) is *finitely generated* if there is some finite subset A of M such that $N = RA$.

4. A submodule N of M (possibly $N = M$) is *cyclic* if there exists an element $a \in M$ such that $N = Ra$, that is, if N is generated by one element

$$N = Ra = \{ra|\ r \in R\}$$

and is sometimes written as $\langle a\rangle = N$.

It is an easy starter exercise to show that the structures in definition 12.3.1 are indeed modules. If R is a *rng*, then it is not necessarily the case that $A \subseteq RA$.

Example 12.3.2: Example

1. Let $R = \mathbb{Z}$ and let M be any $\mathbb{Z}$-module. Take any $a \in M$. Then $\mathbb{Z}a$ is a cyclic sub-module. It is in fact a cyclic subgroup! More generally, A generates M as a $\mathbb{Z}$-module if and only if A generates M as an [abelian] group. That is, generating M through A as a group (using $+$ and $-$ in groups) will produce as many elements as generating M through A as a module (which also allows $\mathbb{Z}$-actions). Thus, the definition of a finitely generated $\mathbb{Z}$-module is identical to the definition of a finitely generated group (definition 5.1.4).

2. Let R be a ring and let $M = R$ be the [left] R-module of R acting on itself. Then R is finitely generated as a module, even if R is infinitely generated as a ring! Even better: it is cyclic, since $R \cdot 1 = R$. Thus, in terms of generation, R is the "simplest" R-module.

3. If R is an R-module over itslef, then $I \subseteq R$ is a finitely generated R-module if and only if it is a finitely generated *left-ideal*. If R was a right-module, then I would be a finitely generated *right-ideal*, and if R was commutative, I would be a finitely generated *two-sided ideal*.

4. Let M be a finitely generated R-module. Then it is not the case that every submodule of M is finitely generated! Take $P[x_1, x_2, ...] = P[X]$ (i.e. the polynomial ring over countably many coefficients) which is a $P[X]$-module over itself. Then $P[X]$ is cyclic as a $P[X]$-module, and hence finitely generaed, however $(x_2, x_4, x_6, ...) \subseteq P[X]$ is a $P[X]$-submodule of $P[X]$ (being a left-ideal), however, it is an *infinitely generated* left-ideal. Finitely generated modules in which all submodules are finitely generated will be called *Noetherian*.

5. Let R^k be an R-module with the action being pointwise multiplication. Then R^k is finitely generaed by
$$e_i = (\underbrace{0, ..., 0}_{i-1 \text{ times}}, 1, \underbrace{0, ..., 0}_{k-i \text{ times}})$$
hence, for any $(r_1, r_2, ..., r_k) \in R^k$,
$$(r_1, ..., r_k) = \sum_i r_i e_i$$

6. Here is a neat way of writing down M if $A = M/B$. Then $M \cong A' + B$, since any element in M is some element of A (namely A' is a set of coset representative when taking $b = 0$), and an element of B:
$$\frac{M}{B} = \frac{A' + B}{B} \cong A$$
Note that is in general smmimply a *subset* of M, we can define the operation on A' by taking:
$$a_1 + a_2 = a_3 \qquad a_3 \text{ is the appropriate representative from } [a_1 + a_2] \text{ that belongs in } A'$$
In this way, $A' \not\subseteq M$ for as an R-module since the binary operation is different. Note too that $M = A' + B$ does not imply that $M \cong A \oplus B$. For example, consider $A = \mathbb{Z}/6\mathbb{Z}$ with $M = \mathbb{Z}$, and $B = 6\mathbb{Z}$. Letting $A' = \{0, 1, 2, 3, 4, 5\}$, we get that as sets:
$$M = A' + B = \{0, 1, 2, 3, 4, 5\} + 6\mathbb{Z} = \mathbb{Z}$$
for example, $10 = 4 + 6$, and $101 = 5 + 96$. However, giving A' the group structure of $\mathbb{Z}/6\mathbb{Z}$:
$$\mathbb{Z} \ncong_R (\mathbb{Z}/6\mathbb{Z}) + 6\mathbb{Z}$$
For the right hand side has torsion elements, while the left does not. For the $+$ to be upgraded to a $\oplus$, the operation of the quotient must in some natural way be compatible with the operation in M, that is A must in not only be the quotient M/B, but must also be considered as $A \subseteq M$. This is explore in chapter 17$\star$.

Naturally, we would want to find when direct sums of modules behave like direct products, or more specifically external direct sums

Definition 12.3.3: Direct Product and Sum of Modules

Let $(M_i)_{i\in I}$ be a collection of R-modules where I is an indexing set. Then the collection of tuples $(m_i)_{i\in I}$ where $m_i \in M_i$ with addition and action of R defined componentwise is called the *direct product* of $(M_i)_{i\in I}$, denoted

$$\prod_{i\in I} M_i$$

If I is finite where $|I| = n$, then it is usually denoted:

$$M_1 \times \cdots \times M_k$$

If we take the subset of $\prod_{i\in I} M_i$ where only finitely many of the terms are nonzero, then this this set is called the *external direct sum*, and is written as:

$$\bigoplus_{i\in I} M_i$$

If I is finite where $|I| = n$, then it is usually denoted:

$$M_1 \oplus M_2 \oplus \cdots \oplus M_n$$

If I is infinite and $R \neq 0$, then $\bigoplus_{i\in I} M_i \subsetneq \prod_{i\in I} M_i$.

12.3.4 Remark It might be tempting to say that:

$$M \cong N_1 \oplus N_2 \quad \Leftrightarrow \quad M = N_1 + N_2$$

however that is not the case: Take $\mathbb{Z}$ as a $\mathbb{Z}$-module over itself, $N_1 = 2\mathbb{Z}$ an $N_2 = (0)$. Then $2\mathbb{Z} + 0 = 2\mathbb{Z}$, and:

$$\mathbb{Z} \cong 2\mathbb{Z} \qquad \text{but} \qquad \mathbb{Z} \neq 2\mathbb{Z}$$

which we can see since, $1 \notin 2\mathbb{Z}$

If $M \cong A \times B$ for some modules M, A, and B, then for any $m \in M$, there exist unique pair of elements $a \in A, b \in B$ such that $m \mapsto (a, 0) + (0, b)$. Thus, any generating set (or more specifically minimal generating set) of M breaks down to a question of a generating set (or minimal generating gset) of A and B. The key here is that any element $m \in M$ can be uniquely represented by elements a and b (namely since these two modules are isomorphic).

Let's say conversely that we want to find submodules $A, B \subseteq M$ for which $M = A + B$. If a module M is finitely generated, by Zorn's lemma there must exist a minimal nonnegative integer d such that M is generated by d elements (and no less)[8]. If M was not finitely generated, this need not be the case. If M can be generated by d elements, it need not be the case that there is a unique set of generating elements, nor the case that the R-linear combination of these elements be unique:

[8] Note that minimal does not mean smallest! There can be multiple different $d \in \mathbb{N}$ that satisfy this property, see the discussion in section 2.3

Example 12.3.5: Non-Unique Sets And R-Linear Combinations

It will turn out that we almost never get a unique minimal generating set [a]. Take for example R over itself. Let $u \in R$ be a unit of R. Since u is a unit, let $v \in R$ such that $uv = 1$. Then $R \cdot 1 = R \cdot (vu) = (Rv)u = R \cdot u$ (since $u \in R$, $uv = 1 \in Rv$, and from that we can show that $(Rv)u = Ru$).

[a] If you have already taken a course in linear algebra, this is equivalent to saying that there is no unique basis

Though unique minimal generated sets are rare to come accorss, uniqe R-linear combinations are much more common. For example, taking R over itself so that $\{1\}$ generated R as an R-module. Then every R-linear combination is unique, that is

$$r \cdot 1 = s \cdot 1 \Leftrightarrow r = s$$

We can see this by taking the homomorphism $\varphi : R \to M$, $r \mapsto r \cdot 1$ and look at the kernel. This property is very desirable, since it will allow us to show that M can split into a direct sum of submodules. If the R-linear combinations are unique, then we need only concern ourselves with any minimal generating set when considering the structure of such a module!

For the rest of the chapter, we identify equivalent properties to saying R-linear combinations are unique, and identify modules which have this property.

Proposition 12.3.6: Equivalent Conditions for Linear Combinations

Let $N_1, ..., N_k$ be (not necessarily distinct) submodules of R-module M. Then the following are equivelent

1. the map $\pi : \bigoplus_{i \in I} N_i \to \sum_i N_i$ defined by

$$(n_i)_{i \in I} \mapsto \sum_i n_i$$

   is an R-module isomorphim. If $|I| < k$ is finite, we write:

$$N_1 + N_2 + \cdots + N_k \cong N_1 \times N_2 \times \cdots \times N_k$$

2. $N_j \cap (N_1 + N_2 + \cdots + N_{j-1} + N_{j+1} + \cdots + N_k) = 0$ for all $j \in \{1, 2, ..., k\}$
3. Every $x \in N_1 + N_2 + \cdots + N_k$ can be written *uniquely* in the form $a_1 + a_2 + \cdots + a_k$ with $a_i \in N_i$

***Proof*:**

For (1) implies (2). let's assume that the intersection is not empty. Then there exists some a_j such that

$$a_j = a_1 + a_2 + \cdots + a_{j-1} + a_{j+1} + \cdots + a_k$$

However, this implies that

$$\pi(0, ..., a_j, ..., 0) = \pi(a_1, a_2, ..., a_{j-1}, a_{j+1}, ..., a_k)$$

but

$$(0, ..., a_j, ..., 0) \neq (a_1, a_2, ..., a_{j-1}, a_{j+1}, ..., a_k)$$

contradiction injectivy, since π is an isomorphism

For (2) implies (3). Let's say there are two linear combinations

$$a_1 + a_2 + \cdots + a_k = b_1 + b_2 + \cdots + b_k$$

then we can isolate any jth components:

$$b_j - a_j = (b_1 - a_1) + \cdots + (b_{j-1} - a_{j-1}) + (b_{j+1} - a_{j+1}) + \cdots + (b_k - a_k)$$

which implies by our previous proposition

$$b_j - a_j \in N_j \cap (N_1 + N_2 + \cdots + N_{j-1} + N_{j+1} + \cdots + N_k) = 0$$

thus, $b_j - a_j = 0$ and so $b_j = a_j$ for every j, showing that the linear combination is unique!

For (3) implies (1), Notice that the function is surjective construction: for any element $a_1 + a_2 + \cdots + a_k$, the element $(a_1, a_2, ..., a_k)$ would map to it. What (2) does is show injectivity, since if two sums are the same, then the direct product of elements must also be the same!. This map is also easily checked to be an R-module homomorphism. For example

$$\begin{aligned} \pi(r \cdot (a_1, a_2, ..., a_k) &= \pi(ra_1, ra_2, ..., ra_k) && (12.1)\\ &= ra_1 + ra_2 + \cdots + ra_k && (12.2)\\ &= r \cdot (a_1 + a_2 + \cdots + a_k) && (12.3)\\ &= r\pi(a_1, a_2, ..., a_k) && (12.4) \end{aligned}$$

where line 3 comes from induction on $r \cdot (m + n) = r \cdot m + r \cdot n$, and linearity comes easily too.

This show's us how we may split up a module into "direct products" which satisfy the universal property of direct products. We now introduce a notion that is slightly stronger than the external direct product and of sums of modules:

Definition 12.3.7: Internal Direct Sum

Let $(N_i)_{i \in I}$ be a collection of submodules of M modules respecting one of the 3 condition's in proposition 12.3.6. If:

$$\sum_i N_i = M$$

then we will replace the summation symbol $\sum_i$ with $\bigoplus_i$. If the indexing set is finite, then:

$$N_1 + \cdots + N_k = N_1 \oplus \cdots \oplus N_k$$

Thus, we are *overloading* the notation of $\oplus$ to represent the fact that the sum $\sum_i N_i$ is isomorphic to $\oplus_i N_i$ *and* that $\sum_i N_i = M$

We have already shown in remark where M is an R-module that is isomorphic to a direct sum of submodules $(N_i)_{i \in I}$ but $\sum_i N_i \neq M$, namely by taking $\mathbb{Z}$ as a $\mathbb{Z}$-module and $N_1 = 2\mathbb{Z}$, $N_2 = (0)$. Then:

$$\mathbb{Z} \cong 2\mathbb{Z} \oplus (0) \qquad \mathbb{Z} \neq 2\mathbb{Z} \oplus (0)$$

In chapter 17$\star$ and chapter 51, we will further explore how to find when a module M can be

decomposed into direct products.

One case is settled immediately, and is used often enough to record. When the *ring* is a product, every module over it splits, and the splitting is forced by the two idempotents $(1,0)$ and $(0,1)$. The upshot is that module theory over $R \times S$ is nothing more than module theory over R and over S carried out side by side.

Proposition 12.3.8: Modules over a Product Ring

Let R and S be rings and put $e = (1,0)$ and $f = (0,1)$ in $R \times S$, so that e and f are central idempotents with $e + f = 1$ and $ef = 0$. Then every $(R \times S)$-module M decomposes as an internal direct sum

$$M = eM \oplus fM$$

where eM is an R-module and fM is an S-module. The assignments $M \mapsto (eM, fM)$ and $(M_1, M_2) \mapsto M_1 \oplus M_2$ are mutually inverse, and give an equivalence of categories

$$(R \times S)\textbf{-Mod} \;\simeq\; R\textbf{-Mod} \times S\textbf{-Mod}$$

Under it, a module is finitely generated, or projective, exactly when both of its components are. Freeness is *not* componentwise: $M_1 \oplus M_2$ is free over $R \times S$ if and only if M_1 and M_2 are free of the *same* rank, since a free $(R \times S)$-module is $(R \times S)^n \cong R^n \oplus S^n$.

***Proof*:**

Step 1: the decomposition. For $m \in M$ we have $m = 1 \cdot m = (e + f)m = em + fm$, so $M = eM + fM$. If $x \in eM \cap fM$, write $x = em' = fm''$. Then $x = ex = e(fm'') = (ef)m'' = 0$, using that e is idempotent and $ef = 0$. So the sum is direct.

Step 2: the components are modules over the factors. The subgroup eM is stable under $R \times S$, and f acts on it as $fe = 0$, so the action factors through $(R \times S)/(0 \times S) \cong R$, making eM an R-module. Symmetrically fM is an S-module.

Step 3: the two constructions are inverse. Given R-module M_1 and S-module M_2, let $R \times S$ act on $M_1 \oplus M_2$ componentwise. Then $e(M_1 \oplus M_2) = M_1$ and $f(M_1 \oplus M_2) = M_2$, recovering the pair. Conversely Step 1 rebuilds M from (eM, fM). Both assignments send a homomorphism to its restrictions, and a map commutes with the action of e and f exactly when it preserves the two summands, so the correspondence is functorial in both directions and is an equivalence.

Step 4: the listed properties. Finite generation and projectivity are checked componentwise because the equivalence carries $R \times S$ to the pair (R, S) and direct sums to direct sums. A generating set for M projects to generating sets of eM and fM and conversely, giving finite generation. And M is a summand of a free $(R \times S)$-module exactly when each component is a summand of a free module over its factor, giving projectivity.


Freeness is the exception, and the equivalence is what shows why. A free $(R \times S)$-module of rank n corresponds to the pair (R^n, S^n), so M is free exactly when its two components are free *of a common rank*. For $R = S = k$ a field, $M = k \oplus k^2$ has both components free, of ranks 1 and 2, and is projective. But it is not free, since that would force $1 = 2$. This completes the proof.

To conclude, we re-phrase the above results in the language of universal properties. The properties of $M \oplus N$ can be described in terms of maps $\varphi : L \to M \oplus N$ where this map is uniquely determined


by the maps $\varphi_M : L \to M$ and $\varphi_N : L \to N$, that is:

Proposition 12.3.9: Universal Property of Products, Modules

Let M, N be two R-modules and let $\pi_M \colon M \oplus N \to M$ and $\pi_N \colon M \oplus N \to N$ be the projections $(m, n) \mapsto m$ and $(m, n) \mapsto n$. Then $M \oplus N$ as constructed above satisfies the universal property of products: for any R-module L, if $\varphi_M \colon L \to M$ and $\varphi_N \colon L \to N$ are two R-module homomorphisms, then there exists a unique R-module homomorphism $\varphi \colon L \to M \oplus N$ such that the following diagram commutes:



More generally, if $(M_i)_{i \in I}$ is a collection of R-modules, then for any R-module L and collection of R-module homomorphisms $\varphi_i \colon L \to M_i$, there exists a unique R-module homomorphism $\varphi \colon L \to \prod_{i \in I} M_i$ such that all of the following diagrams commute, where π_{M_i} is the projection onto the ith component:



When I is finite, $\prod_{i \in I} M_i = \bigoplus_{i \in I} M_i$.

***Proof*:**

When I is finite, every tuple $(m_i)_{i \in I}$ has finitely many nonzero entries, so $\prod_{i \in I} M_i = \bigoplus_{i \in I} M_i$ (definition 12.3.3), and the statement for $M \oplus N$ is the case $I = \{1, 2\}$, $M_1 = M$, $M_2 = N$ of the general one. So let $(M_i)_{i \in I}$, L and the φ_i be as in the general statement. Each projection $\pi_{M_i} \colon \prod_j M_j \to M_i$, $(m_j)_j \mapsto m_i$, is an R-module homomorphism, since addition and the action of R on the product are defined componentwise.

Existence. Define $\varphi(\ell) = (\varphi_i(\ell))_{i \in I}$ for $\ell \in L$. For $\ell, \ell' \in L$ and $r \in R$,

$$\varphi(\ell + \ell') = (\varphi_i(\ell) + \varphi_i(\ell'))_{i \in I} = \varphi(\ell) + \varphi(\ell') \qquad \varphi(r\ell) = (r\varphi_i(\ell))_{i \in I} = r\varphi(\ell)$$

because each φ_i is R-linear and the operations on $\prod_i M_i$ are componentwise. So φ is an R-module homomorphism, and $\pi_{M_i}(\varphi(\ell)) = \varphi_i(\ell)$ for every i and ℓ, that is, $\pi_{M_i} \circ \varphi = \varphi_i$.

Uniqueness. Let $\psi \colon L \to \prod_i M_i$ be an R-module homomorphism with $\pi_{M_i} \circ \psi = \varphi_i$ for every i. For $\ell \in L$, the ith component of $\psi(\ell)$ is $\pi_{M_i}(\psi(\ell)) = \varphi_i(\ell)$, which is also the ith component of $\varphi(\ell)$. A tuple is determined by its components, so $\psi(\ell) = \varphi(\ell)$ for every ℓ, and $\psi = \varphi$, as claimed.

For infinite I the product cannot be replaced by the direct sum. Take $R = L = \mathbb{Z}$, $M_i = \mathbb{Z}$ and $\varphi_i = \mathrm{id}$ for $i \in \mathbb{N}$. If some homomorphism $\psi\colon \mathbb{Z} \to \bigoplus_{i\in\mathbb{N}} \mathbb{Z}$ satisfied $\pi_{M_i} \circ \psi = \mathrm{id}$ for every i, then its composite with the inclusion $\bigoplus_{i\in\mathbb{N}} \mathbb{Z} \subseteq \prod_{i\in\mathbb{N}} \mathbb{Z}$ would satisfy the same equations, so by uniqueness $\psi(1) = (1, 1, 1, \dots)$, which has infinitely many nonzero entries and does not lie in $\bigoplus_{i\in\mathbb{N}} \mathbb{Z}$.

12.3.2 Free Modules

Given a ring R and a an arbitrary abelian group A, we can always define the trivial module via the action $r \cdot a = 0$: let's label this module $T(A)$ and call it the trivial R-module. Just like trivial groups, trivial modules offer little in structure[9]. It would be desirable if we can find a better struture on A, in particular if A represents the generating set of some R-module M, then we would like to define a "free R-module" $F(A)$ (or more particularly $F^R(A)$ to remember the ring R) which represents an R-module with no relationship, and then find a R-submodule $N \subseteq F(A)$ such that $F(A)/N \cong M$ (i.e. the submodule N woule represent adding relationships to $F(A)$). This mirrors the development of the free group from sections 2.3.3 and 3.2.

Let's say we were to define a R-module $F^R(A)$ on the generating set A of M with only the bare minimum relations to make it into an R-module ($1 \cdot m = m$, $(rs) \cdot m = r \cdot (s \cdot m)$, and so forth). Then similarly to free groups, we would want that for any element of $x \in F^R(A)$, which is some linear combination:

$$x = \sum_{a\in B\subseteq A} r_a \cdot a \quad \text{for some subset } B \subseteq A$$

to be equal to 0 if and only if $r_a = 0$ for all a. This is similar to free groups, where any relation between generating elements can be move to the left hand side and the right hand side equals to the identity element. By proposition 12.3.6, this means that $F^R(A) = R^{|A|}$ is our desired free R-module. To see why, suppose some $r_a \neq 0$. Then that means we have added some relation into $F^R(A)$, that is the function $\varphi : R^{|A|} \to F^R(A)$ would have a non-trivial kernel, going against the idea that $F^R(A)$ is a free-module.

If $F^R(A)$ is a free module on A, just like for free groups, any set-function from A to any R-module N, $f : A \to N$, should lift to an R-module homomorphism $F : F^R(A) \to N$, i.e. there is a map $\iota : A \hookrightarrow F^R(A)$ that injects A into $F^R(A)$ and $f = F \circ \iota$. In particular, given any arbitrary map $f : A \to N$, no matter where f maps A, whether f is injective or not, we can find a map F such that $F|_A = f$, so F must map any element of the set A exactly as how f would map it, hence F is an extension of f that has the restriction of being an R-module homomorphism. Furthermore, N is any R-module, meaning any $f : A \to N$ can be lifted to $F : F^R(A) \to N$ (see how this is not the case for an arbitrary domain M, or check out section 2.3.3 for the parallel problem in group theory). A consequence of this result is that we can determine how $F^R(A)$ maps to an R-module N simply by determining where A maps to, that is we have the universal property of free modules.

[9]When dealing with groups, we also defined $\mathrm{Sym}(A)$. As a thought exercise, can you see why we cannot parallel the same idea with module? Hint: Think of $\mathbb{Z} \hookrightarrow \mathbb{Q}$

12.3.10 On Recovering A We would have to already know of the set A in order to do the above strategy. The notation $F^R(A)$ makes it seem obvious that we know about the set A, namely since we will soon construct $F^R(A)$ with respect to A, but it is not so obvious that if we are given a module M that we say is a free R-module, can we find a subset A such that $F^R(A) \cong_R M$. In fact, depending on the ring R acting on M, it will sometimes be possible to "recover" A, while other times it will be impossible[a]. Chapter 13 takes this up for vector spaces.

[a] It will be possible to say there exists such a set using the axiom of choice, but it will be impossible to give a description of the elements

We now prove that $F^R(A) = R^{|A|}$ does indeed respect the universal property of free R-modules.

Theorem 12.3.11: Universal Property of Free Modules

For any set A, there exists a free R-module $F^R(A)$ on the set A where $F^R(A)$ satisfies the following *universal property*: If M is any R-module and $\varphi : A \to M$ is any map of sets, then there is a unique R-module homomorphism $\psi : F(A) \to M$ such that $\psi|_A = \varphi$, that is, the following diagram commutes

$$\begin{array}{ccc} S & \xhookrightarrow{\text{incl.}} & F(S) \\ & \searrow^{\varphi} & \downarrow{\scriptstyle \psi} \\ & & M \end{array}$$

When A is a finite set $\{a_1, a_2, ..., a_n\}$, $F^R(A) = Ra_1 \oplus \cdots + \oplus RA_n \cong R^n$, and if A has any cardinality, then:

$$F^R(A) = \bigoplus_{a \in A} R_a$$

where A is treated as an indexing set.

***Proof*:**
if $A = \emptyset$, then let $F(A) = \{0\}$. Then this trivially satisfies:

$$\begin{array}{ccc} \emptyset & \xhookrightarrow{\text{incl.}} & \{0\} \\ & \searrow^{\varphi} & \downarrow{\scriptstyle \Phi} \\ & & M \end{array}$$

since $\emptyset$ is included in any set, φ is the vacuous map, and $\Phi(0) = 0$ makes Φ into an R-module homomorphism which restircted to $\emptyset$ is itself again.

So let $A \neq \emptyset$. What we will do is construct funtions with the domain as a set and the co-domain as the ring R. These functions will be the mechanism by which set A is given an R-module structure! Let $F^R(A)$ be the collection of all set functions $f : A \to R$ such that $f(a) = 0$ for all but finitely many $a \in A$:

$$F^R(A) = \{f \in \text{Hom}_{\mathbf{Set}}(A, R) \mid f(a) \neq 0 \text{ for only finitely many } a \in A\}$$

Make $F^R(A)$ into an R-module by defining pointwise addition and pointwise multiplication for

the action:

$$(f+a)(a) = f(a) + g(a)$$
$$(rf)(a) = r(f(a))$$

for all $a \in A$, $r \in R$, $f, g \in F^R(A)$. Notice how $F^R(A)$ is isomorphic to $R^{|A|}$, meaning this construction matches definition 12.3.12.

Let $\iota : A \to F^R(A)$ vis $a \mapsto f_a$, where f_a is the function which is 1 at a and zero everywhere else. We can thus identify a set $A \leftrightarrow A' \subseteq F^R(A)$ as the subset containing all of f_a. Notice that since any f has only finitely many non-zero elements, we can write any $f \in F^R(A)$ as

$$f = r_1 f_{a_1} + r_2 f_{a_2} + \cdots + r_n f_{a_n}$$

which by our identification of A' with A, represents:

$$r_1 a_1 + r_2 a_2 + \cdots + r_n a_n$$

where f takes on the value of r_i at a_i and is zero at all other elements of A. Even better, by construction, every element of $F^R(A)$ has a *unique* expression as such a formal sum, since by construction, non of the a_i have any relation to each other, there cannot be a way of cancelling them out!

To establish the universal property, of $F^R(A)$, Let's say we have a function $\varphi : A \to M$, where M is an R-module. We need to show this function raises to an R-module homomorphism $\Phi : F^R(A) \to M$. Let Φ be defined by

$$\sum_{i=1}^{n} r_i a_i \mapsto \sum_{i=1}^{n} r_i \varphi(a_i)$$

by the uniqueness fo the expression of the elements of $F^R(A)$ as linear combinations of a_i, we see that Φ is indeed a well dfiend R-module homomrophsim!! Indeed, two elements of $F^R(A)$ can be written over a common finite list $a_1, \ldots, a_n$ of distinct elements of A, allowing zero coefficients, and then

$$\Phi\left(\sum_i r_i a_i + \sum_i s_i a_i\right) = \sum_i (r_i + s_i)\varphi(a_i) = \Phi\left(\sum_i r_i a_i\right) + \Phi\left(\sum_i s_i a_i\right)$$
$$\Phi\left(r \sum_i r_i a_i\right) = \sum_i r r_i \varphi(a_i) = r\Phi\left(\sum_i r_i a_i\right)$$

By definition, the restriction of $\Phi|_A$ is φ. For uniqueness of $F^R(A)$, since $F^R(A)$ is generated by A, once we know the values of an R-module homomorphism on A, tis value on every element of $F^R(A)$ are uniquely determined (by force of construction), so Φ is the unique extension of Φ to all of $F^R(A)$.

If A is finite ($\{a_1, a_2 ..., a_n\}$), proposition 12.3.6

$$F^R(A) = Ra_1 \oplus Ra_2 \oplus \cdots \oplus Ra_n$$

Since $R \cong Ra_i$ (under $r \mapsto ra_i$) by proposition 12.3.6 again, the direct sum is isomorphic to R^n.

Definition 12.3.12: Free Module

An R-module F is said to be *free* on the subset A of F if for every nonzero element x of F, there exists a unique nonzero elements $r_1, ..., r_n$ of R and unique $a_1, ..., a_n$ in A such that $x = r_1a_1 + \cdots r_na_n$, for some $n \in \mathbb{Z}^+$, which by proposition 12.3.6 implies that:

$$F = \bigoplus_{i \in I} R$$

If R is a commutative ring, the cardinality of A is called the *free rank* of F, or just *rank* if unambiguous.

Note that A need not be finite, but the linear combinations of elements of A need to be finite (notice that we say $a_1, ..., a_n \in A$, and not $a_1, ..., a_n, ... \in A$). From now on, we will write R^n to mean the free R-module $R \oplus R \oplus \cdots \oplus R$. So $(\mathbb{Z}/2\mathbb{Z})^3$ is a free $(\mathbb{Z}/2\mathbb{Z})$-module. R^1 is a free R-module of rank 1 (to be distinguished from R which we will treat as a ring). If the superscript is infinite, say $N = |\mathbb{N}|$ or $N = |\mathbb{R}|$, then R^N is considered an infinite direct sum, not a direct product (unlike the R^A of example 12.1.7, which denotes all functions $A \to R$). The direct product $\prod_{n \in \mathbb{N}} \mathbb{Z}$, by contrast, is not a free $\mathbb{Z}$-module (the Baer-Specker theorem, [52]). Furthermore, the notion of rank is not necessarily well-defined if R is not commutative. We shall explore more of this in chapter 13.

Example 12.3.13: Free Modules

1. Let R be any ring with identity. Then R over itself is a free-module! The element 1 will always generated all of R since 1 is a unit (and so $ab \neq 0$ for any $b \neq 0$) and $r \cdot 1 = r$, and so it's a linearly independent generating set!

2. The "freeness" is dependent on the ring you choose, as well as the module (i.e., the abelian group). So $\mathbb{Z}/n\mathbb{Z}$ over itself is free (by the logic provided above), but not over $\mathbb{Z}$ (which we already know is a well-defined module), since

   $$n \cdot 3 = 0$$

   In general, one criterion for freeness is that $r \cdot a \neq 0$ for any r. This criterion is called being *torsion-free*, and if $r \cdot a = 0$, then r is said to be a *torsion element* of the R-module M. However, a module being torsion free does not imply the module is free.

3. Since $\mathbb{Z}/n\mathbb{Z}$ overt $\mathbb{Z}$ is not a free-module, it does not have a basis. If we try to choose $A \subseteq \mathbb{Z}/n\mathbb{Z}$ to be a basis, it will always have torsion elements. $\mathbb{Z}/n\mathbb{Z}$ over $\mathbb{Z}$ is also an example of a module *without* any linearly independent sets!

4. Let $\mathbb{C}[x, y]$ act on itself. Then $\mathbb{C}[x, y]$ is a free module. As stated in example 12.1.7, ideals of modules over themselves are sub-modules. Take $(x, y) \subseteq \mathbb{C}[x, y]$. Any two distinct nonzero $f, g \in (x, y)$ satisfy $g \cdot f - f \cdot g = 0$, so a basis of (x, y) has one element h, and $(x, y) = (h)$. Then h divides x and y, so h is a nonzero constant, but every element of (x, y) has zero constant term. So (x, y) is *not* free. However, (x, y) is certainly torsion-free, since $\mathbb{C}[x, y]$ is an integral domain.

   Thus, freeness is not preserved by taking sub-modules

5. Let $\mathbb{Z}$ act on itself. Then $\mathbb{Z}/n\mathbb{Z}$ is a quotient $\mathbb{Z}$-module as we have seen in section 12.2. However, as we have seen in the 2nd example, $\mathbb{Z}/n\mathbb{Z}$ over $\mathbb{Z}$ is not free.

Thus, freeness is not preserved when taking quotient modules.

6. Let's say $S = \{1, 2, 3\}$, and $M = \mathbb{R}^3$ (over $\mathbb{R}$). Take any $f : S \to M$. For our concrete example, let's say:

$$f(1) = (\varphi, \sqrt{2}, 4) \qquad f(2) = (0, 0, 0) \qquad f(3) = (0, 5753, 9)$$

I chose particularly random values to show that f is indeed any set function map. Now if you consider $F^R(S)$ (over $\mathbb{R}$), we'd have some uncountable set of elements, which most importantly are all distinct! It's that last part that let's us say that

$$\psi : F^R(S) \to \mathbb{R}^3$$

will be the unique homomorphism where $\psi|_S = f$. Consider

$$\psi(x) = \psi(\sum_{i=1}^{3} r_i s_i) = \sum_{i=1}^{3} r_i \varphi(s_i)$$

This function is indeed well defined since every x is *unique* in it's represetnation from S, since if it was not, and we consider

$$x = y(\sum_{i=1}^{3} r_i s_i = \sum_{i=1}^{3} r_i' s_i)$$

then it is not true in general that

$$\psi(x) = \psi(y)$$

what let's use insure that this will always be true is precicely the linear independence, or free property, of the module!

Finally, this is indeed a [unique] homomorphism. it is easy to check that

$$\psi(x + ry) = \psi(x) + r\psi(y)$$

and the uniqueness will come from free modules elements having no relation to each other (if they did, you might be able to have a second homomrophism).

7. You can have a module with linearly independent sets, but that always fail to generate the module, meaning it is not a free module. For example, $\prod_{n\in\mathbb{N}} \mathbb{Z}$ has infinite linearly independent subsets, but it is not a free $\mathbb{Z}$-module ([52]).

8. Take $\mathbb{C} \times \mathbb{C}$ over itself. This is free module (its basis is $(1, 1)$). Then $\mathbb{C} \times \{0\}$ is a submodule, but not a free module: every element $(a, 0)$ satisfies $(0, 1) \cdot (a, 0) = (0, 0)$ with $(0, 1) \neq 0$, so no nonempty subset of $\mathbb{C} \times \{0\}$ is linearly independent, and the nonzero module $\mathbb{C} \times \{0\}$ has no basis.

9. Let R be a Principal Ideal Domain acting over itself. Then any submodule N of R is an ideal, and since it is principal, $N = (a)$ for some $a \in R$. If $a = 0$, then $N = 0$ is free on the empty set. If $a \neq 0$, then $r \mapsto ra$ is an isomorphism $R \to N$, injective because R is an integral domain, so N is free of rank 1. Thus every submodule of R is free.

10. $\mathbb{R}$ has a basis as a $\mathbb{Q}$-vector space (theorem 13.1.8), and the basis is uncountable, since the $\mathbb{Q}$-span of a countable set is countable while $\mathbb{R}$ is not! Note that even though the basis is uncountable, any element $x \in \mathbb{R}$ will still be a $\mathbb{Q}$-linear combination of *finitely many* basis elements.

11. On the other hand $\mathbb{Q}$ over $\mathbb{Z}$ is *not* a free module (i.e. $\mathbb{Q}$ is not a free abelian group). To see this, notice that for any $\frac{a}{b}, \frac{c}{d} \in \mathbb{Q}$, there exists $m, n \in \mathbb{Z}$ (namely $m = bc,\ n = -da$) such that $(bc)\frac{a}{b} + (-da)\frac{c}{d} = 0$, and hence any two elements are linearly dependent, meaning if $\mathbb{Q}$ was a free $\mathbb{Z}$-module, it would have to be cyclic. As we have seen in section 2.3.4, the only free cyclic $\mathbb{Z}$-module is $\mathbb{Z}$. Can you see why $\mathbb{Z} \not\cong_{\mathbb{Z}} \mathbb{Q}$?

Take note of the fact that whether a module is free or not is highly dependent on what ring is acting on it. In $\mathbb{Z}$-**Mod**, $\mathbb{Z}/n\mathbb{Z}$ is certainly not a free (it is not a free group). However, we have just seen that $\mathbb{Z}/n\mathbb{Z}$ is a free-module over itself! The intuition here behind being "free" comes down to the ring-action being "free".

Corollary 12.3.14: Consequences Of Universal Property

1. If F_1 and F_2 are free modules on the same set A, there is a unique isomorphism between F_1 and F_2 which is the identity map on A

2. if F is any free R-module on a free-generating set A, then $F \cong F^R(A)$. In particular, F enjoys the same universal property with respect to A as $F^R(A)$ does in theorem 12.3.11.

***Proof*:**

Any module F which is free on a subset A satisfies the universal property of theorem 12.3.11: for every R-module M and every set map $\varphi : A \to M$ there is a unique R-module homomorphism $\psi : F \to M$ with $\psi|_A = \varphi$.

For uniqueness, note that by definition 12.3.12 every nonzero $x \in F$ can be written as $x = r_1a_1 + \cdots + r_na_n$ with $r_i \in R$ and $a_i \in A$, so any homomorphism ψ restricting to φ must satisfy $\psi(x) = r_1\varphi(a_1) + \cdots + r_n\varphi(a_n)$, and $\psi(0) = 0$. Hence ψ is determined by φ.

For existence, we first observe that representations over a common finite subset are unique even when zero coefficients are allowed: if $\sum_{a\in B} r_a a = \sum_{a\in B} s_a a$ for a finite $B \subseteq A$, then dropping the terms with zero coefficient on each side yields two expressions of the same element with nonzero coefficients, which coincide by the uniqueness in definition 12.3.12 (for the zero element, the expression with all coefficients zero is the only one, since an expression with a nonzero coefficient would violate uniqueness for that element). Hence $r_a = s_a$ for all $a \in B$. We may therefore define $\psi\left(\sum_{a\in B} r_a a\right) := \sum_{a\in B} r_a\varphi(a)$, which is well-defined by the observation. Given $x = \sum_{a\in B} r_a a$ and $y = \sum_{a\in B'} s_a a$, we may enlarge both representations by zero coefficients to the common finite set $B \cup B'$, and then

$$\psi(x+y) = \sum_a (r_a + s_a)\varphi(a) = \psi(x) + \psi(y) \qquad \psi(rx) = \sum_a (rr_a)\varphi(a) = r\psi(x)$$

so ψ is an R-module homomorphism, and $\psi(a) = \varphi(a)$ for $a \in A$ by construction. This proves the claim, and with it the second sentence of part (2).

1. By definition 12.3.12, $A \subseteq F_1$ and $A \subseteq F_2$. Applying the universal property of F_1 to the inclusion $A \hookrightarrow F_2$ gives a homomorphism $\psi_1 : F_1 \to F_2$ restricting to the identity on A,

and symmetrically we get $\psi_2 : F_2 \to F_1$ restricting to the identity on A. The composite $\psi_2 \circ \psi_1 : F_1 \to F_1$ restricts to the identity on A, as does id_{F_1}, so by the uniqueness in the universal property of F_1 we get $\psi_2 \circ \psi_1 = \mathrm{id}_{F_1}$. Similarly $\psi_1 \circ \psi_2 = \mathrm{id}_{F_2}$. Hence ψ_1 is an isomorphism which is the identity on A, and it is the only one: any homomorphism restricting to the identity on A equals ψ_1 by the same uniqueness.

2. Let $\iota : A \to F^R(A)$ be the inclusion of A into $F^R(A)$ from theorem 12.3.11. By the universal property of F applied to ι, there is a homomorphism $\psi : F \to F^R(A)$ with $\psi|_A = \iota$, and by the universal property of $F^R(A)$ applied to the inclusion $A \hookrightarrow F$, there is a homomorphism $\chi : F^R(A) \to F$ with $\chi \circ \iota$ the inclusion. Then $\chi \circ \psi : F \to F$ restricts to the identity on A, so $\chi \circ \psi = \mathrm{id}_F$ by the uniqueness in the universal property of F, and $\psi \circ \chi$ and $\mathrm{id}_{F^R(A)}$ both restrict to ι on A, so $\psi \circ \chi = \mathrm{id}_{F^R(A)}$ by the uniqueness in theorem 12.3.11. Hence $F \cong F^R(A)$.

12.3.15 Foreshadowing Though a free R-module has no relations, it is not the case that any submodule has no relation, that is the submodule of a free module *need not be free*! In other words, though it may at first seem counter-intuitive, the process of taking a submodule can add relations: $\mathbb{C} \times \{0\}$ is a submodule of the free module $\mathbb{C} \times \mathbb{C}$ and is not free (example 12.3.13). This contrasts to how the subgroup of a free group is always free (see appendix B). There are certain rings for which the R-submodule are always free, while there are other rings where submodules are far from being free (ex. some submodules will be torsion modules, which will be far away from being free). We will explore these concepts further in chapters 13 and 17⋆.

Measuring degree of Freeness

As we have seen, not all modules are free modules. However, we may still like to find collection of elements that are linearly independent (i.e. that are "free" of relations). We explore these notions here.

Definition 12.3.16: [Free] Rank

For any ring R, the *rank* of an R-module M is the maximum number of R-linearly independent elements of M, that is if M has rank n, there exists elements $y_1, y_2, ..., y_n$ such that

$$r_1 y_1 + r_1 y_2 + \cdots + r_n y_n = 0 \quad \Leftrightarrow \quad r_1 = r_2 = \cdots = r_n = 0$$

If for all $n \in \mathbb{N}$, there exists a R-linearly independent set, then M is said to be of infinite rank.

Due to the importance of the notion of rank for modules in geometry, the rank is also sometimes called the *Betti Number*[10]. The rank of a module is similar to the size of the generating set of a module, and it will in fact match exactly the idea of rank for modules over fields, but this is not necessarily the case for modules over weaker rings:

[10]The kth Betti number loosely refers to the number of k-dimensional holes ona a topological surface

Example 12.3.17: Different Rank and Size of Generators

Let $R = \mathbb{Z}[x]$ and let $M = (2, x)$ be an R-module. If we take $2 \in M$, then since R is an R an integral domain and M is an ideal of R, there does not exist a r such that

$$ra = 0$$

thus, $\{2\}$ is a linearly independent set from M, meaning it's at least rank 1. What if we two elements? Let's take $a, b \in M$. Since $a, b \in R$, in particular $-a \in R$

$$ba - ab = 0$$

meaning 2 elements will never be linearly independent. This will naturally generalize to n elements, so M is of rank 1.

However, M is generated by 2 elements, showing that the rank and the number of generators does not match.

Sometimes, authors define the minimal set of generators to be the rank of the matrix, and rank as was defined above would be called the *free rank*. Since the size of the generating sets rarely comes up outside the context of free generating sets, this book decided to stick with "rank" to mean the maximal number of linearly independent elements.

Not that it is yet to be established if there is a unique maximal rank (just like in a tree, there may be many maximal heights). For modules over integral domains, the maximal height will alwaays be unique, and under appropriate finiteness conditions it shall also be unique, however there are counter-examples over more general rings. This shall be further explore in chapter 13.

Using the notion of rank, we can see how a module might fail to be free. In the "worst case scenario", we can single out elements fail to be linearly independent:

Definition 12.3.18: Torsion Element

Let M be an R-module and $m \in M$. Then m is called a *torsion element* if m is linearly *de*pendent, in particular there exists a nonzero $r \in R$ such that

$$r \cdot m = 0$$

The collection of all torsion elements of M is denoted $\mathrm{Tor}_R(M)$ or $\mathrm{Tor}(M)$ is the context is clear. An element that is not torsion is called *torsion-free*.

Elements that are torsion-free can be thought of as being "locally" free. Being is a property of modules, while being torsion-free is a property of elements. If every element has this property, then we give a name to such a module:

Definition 12.3.19: Torsion-Free Modules

Let M be an R-module. Then if $\mathrm{Tor}_R(M) = \{0\}$, then M is said to be *torsion-free* or to be a *torsion-free module*.

Being torsion free is an interesting example of the fact that it is not always enough that every element have a property for the global module to have the property. In this case, even if every element itself is free, this does not imply the module itself is free

Example 12.3.20: Torsion-free, But Not Free Module

Take $\mathbb{C}[x, y]$ over itself. Then since it's an integral domain, it is torsion free and each submodule is torsion free. However, (x, y) is not free.

Looking instead at the ring action instead of the module element, we can also find all elements of the ring that fail to be linearly dependent with *all* module elements:

Definition 12.3.21: Annihilator

Let M be an R-module. Then the set

$$\text{Ann}_R(M) = \{r \in R \mid r \cdot m = 0 \ \forall m \in M\}$$

is called the *annihilator* of M.

Recall that this set appeared in example 12.1.7(4), in the discussion of modules where the annihilator is trivial. Such a module is given a name:

Definition 12.3.22: Faithful Module

Let M be an R-module. Then if $\text{Ann}_R(M) = \{0\}$, M is said to be a *faithful R-module*, or that the ring R is acting faithfully on M

If R does not act faithfuully on M, when we may always induce a faithful action along the lines of example 12.1.7(4). The same cannot be said about non-torsion modules, instead we may ask if a module M can be split into a torsion-free part and a torsion part. Being trosion free is much more flexible than being free:

Proposition 12.3.23: Extensions And Submodules Of Torsion-Free Modules

Let M be an R-module. Then:

1. If M is torison-free, then any submodule is torsion free
2. the direct sum of torsion free modules is torsion-tree
3. if M is an extension of torsion-free modules, that is $0 \to A \to M \to B \to 0$ is a short exact sequence with A and B being torsion-free, then M is torsion-free.
4. If R is an integral domain M is free, then M is torsion-free (i.e. free modules over integral domains are torsion-free)

***Proof*:**

1. This is immediate after realising $\text{Tor}_R(N) \subseteq \text{Tor}_R(M)$
2. this is also almost immediate givn a similar type of reasoning as in part (1)
3. If $m \in M$, where $r \cdot m = 0$, then $r \cdot \overline{m} = \overline{0}$, but since $r \in\in \text{Tor}_R(B) = \{0\}$ $r = 0$, and so $\text{Tor}_R(M) = 0$.

4. Since the direct of free modules is free, and the integral domain R as a module over itself is torsion free, M is torsion-free.

In chapter 14, we shall further explore the decomposition of the torsion and torsion-free part of a module over nicer enough rings so that the decomposition is possible.

If N is not a torsion module, then $\text{Ann}(N) = 0$. It is possible that N is a torsion module, but $\text{Ann}(N) = 0$:

Example 12.3.24: Torsion Module With No Annihilators
Take

$$Z = \bigoplus_k \mathbb{Z}/2^k\mathbb{Z}$$

then Z is a $\mathbb{Z}$-torsion module, since for every $z \in \mathbb{Z}$, we can take 2^k, where we pick k relative to the largest nonzero component. However,

$$\text{Ann}(Z) = 0$$

Since if $r \in \mathbb{Z}$ was an annihilator, then $r \cdot z = 0$ for every z, but z can take any value of $\mathbb{N}$, leading us to a contradiction

If the module is finitely generated the annihilator will always be non-empty, since if we annihilate the generators, we annihilate the entire module.

Exercise 12.3.1

1. Let M be an R-module, and define $\text{Ann}_R(M) = \{r \in R \mid r \cdot m = 0,\ \forall m \in M\}$.
    1. Show that $\text{Ann}_R(M)$ is a two-sided ideal
    2. If $\text{Ann}_R(M) = 0$, then M is said to be a faithful module. Show that all free modules are faithful, but there are faithful non-free modules
2. Let R be a commutative ring and an R-module over itself. Then show that an ideal $I \subseteq R$ is a free R-module if and only if it is principal and generated by a nonzero divisor.
3. Show that $\mathbb{Z}^{\mathbb{N}}$ (a direct product of countably many $\mathbb{Z}$ is *not* a free abelian group

12.3.3 Presentations and Resolutions

We claimed that all R-modules are a quotient of a free R-module, just how all groups are quotient of free groups. We will demonstrate this here, and then explore a bit furter how we can think of relations and presentations of modules:

Proposition 12.3.25: Constructing Modules using Free Modules

Any R-module M is the quotient of a free module $F^R(A)$ for appropriate set A:

$$F^R(A)/K \cong_R M$$

***Proof*:**
Let M be an R-module and $\mathcal{F} = F^R(M)$. Define the map:

$$\varphi : \mathcal{F} \to M \qquad (r_i m_i)_{i \in M} \mapsto \sum_{i \in M} r_i m_i$$

where any element on the left hand side is a tulpe indexed by M where all but finitely many of the terms are nonzero, and hence the right hand side is well-defined. This map is evidentely surjective (since the tulpe of m in the first element maps to m), and so if K is the kernel of this map, by the first isomrophism theorem:

$$F^R(M)/K \cong_R M$$

as we sought to show.

Hence, the kernel of a free module plays the role of codifying all the relations in a module. When working with groups, we encoded these relations writting a group as either, for example:

$$\langle x, y \ : \ xy - yx = 0 \rangle \qquad \text{or} \qquad \frac{F(x,y)}{xy - yx}$$

The former notation is easier to read before quotients are introduced. Since the kernel is the central object defining the relations, it enters the definition of a presentation of a module:

Definition 12.3.26: Presentation Of Module

Let M be an R-module. Then a *presentation* of M is a an exact sequence:

$$R^n \to R^m \to M \to 0$$

If m and n are finite (i.e. if $m, n \in \mathbb{N}$), then M is said to be *finitely presented*, or a *finitely presented module*.

Note that m and n need not be natural numbers, and that the map $R^n \to R^m$ in a presentation need not be injective, so a presentation is in general *not* a short exact sequence

$$0 \to R^n \to R^m \to M \to 0 \tag{12.5}$$

For instance, the map $\mathbb{Z}[x]^2 \to \mathbb{Z}[x]$ given by $(f, g) \mapsto 2f + xg$ is the first map of a presentation of $\mathbb{Z}[x]/(2, x)$, and its kernel contains $(x, -2) \neq 0$. Over a PID a presentation of the form (12.5) always exists: the kernel of a surjection $R^m \to M$ is a submodule of a free module, hence free, as theorem 14.1.6 proves. Conversely, if R is an integral domain and the kernel of every surjection from a finitely generated free R-module is free, then R is a PID (proposition 12.3.29). The observations below assume these results.

It is informative to the reader to see how presentations of modules compares to presentations of groups. Note that $\mathbb{Z}$ is a Principal Ideal Domain, and so for any finitely generated abelian group (i.e. any finitely generated $\mathbb{Z}$-module), we have the exact sequence:

$$0 \to \mathbb{Z}^n \to \mathbb{Z}^m \to G \to 0$$

Furthermore, any subgroup of a free group is free (see appendix B), and so more generally for any group G and appropriate sets A and B:

$$0 \to F(A) \to F(B) \xrightarrow{\varphi} G \to 0$$

where $F(A) = \ker(\varphi)$. Over some other rings some modules admit no chain like (12.5) (examples are in *Homological Algebra* [29]), and this distinguishes groups from modules. In fact, there are even modules for which there is no finite length chain of free modules. If we interpret equation (12.5) as saying that the relations on a module is free, then if we extend the length by 1:

$$0 \to R^n \to R^m \to R^p \to M \to 0$$

can interpret the extra homomorphism as the relations of the relations, where the "relations of the relations" are free. Some modules do not have a finite length chain of this sort!! We give a name to such a chain

Definition 12.3.27: Free Resolution

Let R be a ring and M an R-module. A *free resolution* of M is an *exact* chain complex (definition 12.2.11)

$$\cdots \to F_2 \to F_1 \to F_0 \to M \to 0$$

in which every F_i is a free R-module. The resolution has *finite length* k if $F_i = 0$ for every $i > k$, so that it reads

$$0 \to F_k \to F_{k-1} \to \cdots \to F_1 \to F_0 \to M \to 0$$

and M is then said to have a *finite length free resolution* of length k.

Exactness is what makes the resolution say something about M: at F_0 it says that the relations among the chosen generators are exactly the image of F_1, at F_1 that the relations among *those* relations are the image of F_2, and so on.

By definition, all free modules have a finite length free resolution of length zero since

$$0 \to R^{n_0} \to M \to 0$$

i.e. $R^{n_0} \cong M$. By the universal property of free modules, any R-module M has a free resolution (can you see why). The resolution is called a *free* resolution since we are using free-modules. If we use a different type of module, we will get a different type of resolution[11].

Example 12.3.28: Free Resolution

Let G be a finitely generated abelian group. Then by the fundamental theorem for such groups (theorem 5.1.6),

$$G \cong \mathbb{Z}^n \oplus \mathbb{Z}/n_1 Z \oplus \mathbb{Z}/n_2\mathbb{Z} \oplus \cdots \oplus \mathbb{Z}/n_k\mathbb{Z}$$

As pointed out, all free-modules have a resolution of length 0, namely

$$0 \to \mathbb{Z}^n \to \mathbb{Z}^n \to 0$$

[11] Projective, injective and flat modules are introduced in chapter 17⋆, and the corresponding resolutions in *Homological Algebra* [29].

On the other hand, any cyclic torsion group has a resolution of length 1:

$$0 \to \mathbb{Z} \xrightarrow{\cdot n} \mathbb{Z} \xrightarrow{\pi} \mathbb{Z}/n\mathbb{Z} \to 0$$

These results can be combined to show that G always has a resolution of length 1. Modules whose free resolutions all have length at least 2 will be given in *Homological Algebra* [29].

Proposition 12.3.29: Free Resolutions Of Length 1, Then PID

Let R be an integral domain such that for every finitely generated R-module M and every surjective homomorphism $R^n \to M$, the kernel is a free R-module, so that

$$0 \to R^m \to R^n \to M \to 0$$

is exact for some m. Then R is a PID.

***Proof*:**
Let $I \subseteq R$ be an ideal. The projection $R \to R/I$ is surjective with kernel I, so I is free. Two elements $a \neq b$ of R are linearly dependent over R: if both are nonzero, $b \cdot a + (-a) \cdot b = 0$ is a nontrivial relation, and a set containing 0 is dependent. So a basis of I has at most one element, and $I = 0 = (0)$ or $I = Ra = (a)$. Since I was arbitrary, every ideal of R is principal, making R a PID, as we sought to show.

12.3.4 Finitely Generated Modules and Noetherian Modules

As with many structures in mathematics, the "infinite" case (in our case infinitely generated objects) have different behavior than the finite case and require some different tools to analyze (possibly some analysis to use the notion of limits). We thus study the case where modules are finitely generated or all submodules are finitely generated.

Let R be a ring and let M be a left R-module. We first define what types of modules are *finitely generated*, and some consequences of being finitely generated,

Definition 12.3.30: Finitely Generated R-Module

Let M be an R-module. Then M is said to be finitely generated if there exists an $n \in \mathbb{N}_{>0}$ such that $M \cong_R R^n/K$ for some R-module K, that is there exists a map φ where

$$R^n \xrightarrow{\varphi} M \to 0$$

is exact so that $\ker(\varphi) = K$ and $R^n/K \cong_R M$.

Though we have defined finitely generated modules, we usually require the stronger condition that all submodules of a finitely generated R-module to be finitely generated (which is not true for every finitely generated modules)

Example 12.3.31: Finitely Generated But A Non-finitely Generated Submodule
Take $R = k[x_1, x_2, ..., x_n, ...]$ be the ring with infinitely many indeterminates over a field. Then R is cyclic over itself, generated by 1, but the R-submodule, i.e. ideal, $(x_1, x_2, ..., x_n, ...) \subseteq R$ is not finitely generated as an R-module.

The main inhibitor to this is We will phrase this condition a little differently and show it's equivalent to the previous statement:

Definition 12.3.32: Noetherian R-Module and Ring

Let M be a left R-module Then:

1. M is said to be *Noetherian R-module* or to satisfy the *ascending chain condition on submodules* (or A.C.C. On submodules), that is there are no infinite increasing chains of submodules, i.e., whenever
$$M_1 \subseteq M_2 \subseteq M_3 \subseteq \cdots$$
is an increasing chain of submodules of M, then there is a positive integer m such that for all $k \geq m$, $M_k = M_m$ (so the chain becomes stationary at stage m: $M_m = M_{m+1} = M_{m+2} = \cdots$)
2. The ring R is said to be Neotherian if it is Neotherian as a left-module over itself, i.e., if there are no infinite increasing chains of left-ideals in R.

One can have an analogous definition of A.C.C. for right and two-sided ideals in (possibly noncommutative) ring R. For noncommutative rings, left and right A.C.C. need not agree. In the ring of matrices $\begin{pmatrix} a & b \\ 0 & c \end{pmatrix}$ with $a \in \mathbb{Z}$ and $b, c \in \mathbb{Q}$, the matrices with $a = c = 0$ and $b \in \frac{1}{2^n}\mathbb{Z}$ form a left ideal for each n, and these left ideals increase strictly, so the ring is not left Noetherian. It is right Noetherian ([69]).

Theorem 12.3.33: Equivalent Conditions To Noetherian

Let R be a ring and let M be a left R-module. Then the following are equivalent

1. M is a Noetherian R-module
2. Every nonempty set of submodules of M contains a maximal element under inclusion
3. Every submodule of M (including M) is finitely generated

***Proof*:**
(1) $\Rightarrow$ (2). Let S be any collection of submodules. Let's pick some sub-module $M_1 \in S$. If S is maximal, then we are done. If not, then M_1 is not maximal, meaning there exists an M_2 such that $M_1 \subseteq M_2$. If M_2 is maximal, we are done. If not, pick M_3 in a similar fashion. Keep picking sub-modules M_i. If none of them are maximal, then by the axiom of choice, we can pick an infinitely long chain of submodules
$$M_1 \subseteq M_2 \subseteq \cdots \subseteq M_k \subseteq \cdots$$
which is a contradiction to the statement that M is Noetherian.

For (2) $\Rightarrow$ (3), Let M be a module. Pick $x \in M$. If $\langle x_1 \rangle = M$, then M is finitely generated. If $\langle x_1 \rangle = N_1 \subsetneq M$, then pick another element $x_2 \in M - N_1$. If $\langle x_1, x_2 \rangle = M$, we are done. If $\langle x_1, x_2 \rangle = N_2 \subsetneq M$, then pick another element $x_3 \in M - N_2$. Either this stabalizes, or we can craete an infinite chain:

$$N_1 \subseteq N_2 \subseteq \cdots \subseteq N_k \cdots$$

This is a collection of submomdules of M, and so by the 2nd condition there must exist a maximal module, say N. Since every module in this chain is finitely generated, N mut be finitely generated, and since it's maximal adding one more element to N, $N + x$ and taking it's closure, $\overline{N + x} = N'$ must make the new larger module N' equal to M. Hence, M is finitely genearted.

For (3) $\Rightarrow$ (1), Take any ascending chain of modules

$$N_1 \subsetneq N_2 \subsetneq \cdots \subsetneq N_k \subsetneq \cdots$$

then $N = \bigcup_{i=1}^{\infty} N_i$ is a module, and by assumption it is finitely generated, say by $\{x_1, x_2, ..., x_n\}$. By definition of N, for each x_i, there exists a j such that $x_i \in N_j$. Since N is the union of the modules N_j, it must be that at some finite distance into the chain, a module contains all the generators. But that means the chain stabalizes.

Note that if M is a Noetherian R-module, then R need not be Noetherian. If R is noetherian, then M is a Noetherian R-module? (Use the fact that the direct sum and quotient of a noetherian ring is noetherian, an the uni prop of free modules).[12]. In proposition 9.4.18, it was shown that rings where $1 \neq 0$ have maximal ideals. Since all rings are modules over themsleves, it might seem that all rings are Noetherian modules due to the second conditions. However, this is certainly not the case, consider $R[x_1, x_2, ..., x_n, ...]$ over itself and the chain $(x_1) \subsetneq (x_1, x_2,) \subsetneq \cdots$. The subtly lies in the fact that the maximal element must lie in the collection of submodules, while the maximal element in the previous example is the union of all the submodules.

Many textbooks introduce Noetherian modules as modules where each submodule is finitely generated. The reason the A.C.C. was chosen for this textbook was for it's greater applicability in many other fields. Notions of being "Noetherian" are pervasive in mathematics, but not all structure are "Noetherian" by having every substructure be finitely generated (sometimes, the notion of substructure is not even well-defined)[13]. The A.C.C. allows us to still consider those structures.

Since Principal Ideal Domain are *a fortiori* Noetherian rings, finitely generated modules over PID's are are also Noetherian, and all the results we discussed earlier apply to such modules (including PID's over themsleves).

Finite Generation vs. Finite Type

Being finitely generated as an R-module and finitely generated as an R-algebra are very differnet:

Example 12.3.34: Finite Generation: Module vs. Algebra
Take $R = k[x]$ as an k-algebra and consider the natural k-module structure. Then it is an *infinitely generated* k-module generated (for example by $\{1, x, x^2, x^3, ...\}$ however it is a *finitely generated* k-algebra generated by $\{1, x\}$.

[12]This mirrors a more general theme in which a property of the underlying ring "becomes" the property of all modules over that ring. Can you see how we can (in a sense) call a field a "free ring"?

[13]See Noetherian topologies for an interesting example

Mo generally, contrast an finitely generated R-module M to a finitely generated R-algebra M:

$$R^{\oplus A} \twoheadrightarrow M \quad R[A] \twoheadrightarrow M$$

Definition 12.3.35: Finite Type

Let A be an R-algebra. Then A is of *finite type* (over R) if A is finitely generated as an R-algebra.

Often, instead of finite type the terms "finitely generated as an R-algebra" or even "finitely generated R'algebra" are often used interchangeably.

Exercise 12.3.2

1. Is a subring of a Noetherian ring Noetherian?
2. (If you know some complex analysis) In this exercise, we try to show how the Noetherian property is not stable by taking subrings and show demonstrate a correspondence between being Noetherian and how the zero of functions are in some way "well-behaved". Consider the following chain of subrings:

$$\begin{gathered}\mathbb{R}[x] \\ \subseteq \\ \text{Analytic functions on } \mathbb{R} \\ \subseteq \\ \text{Analytic functions on } [0,1] \\ \subseteq \\ \text{Analytic functions on } (0,1) \\ \subseteq \\ \text{Analytic functions at } 0 \\ \subseteq \\ \text{Smooth functions near } 0 \\ \subseteq \\ \text{Former Power series}\end{gathered}$$

   which of these rings are Noetherian, and which are not?
3. Show that a finitely generated R-module over a Noetherian ring R is itself Noetherian
4. Let M be an R-module over an integral domain R. Then if M is of rank n, any submodule $N \subseteq M$ can be of rank at most $n \leq m$ (hint: take the ring of fractions).

12.3.5 Direct Sums and Homomorphisms

For the first time in this book, we will pay closer attention to hom-sets. The structure of hom-sets of modules will allo us to determine many important properties of modules.

Proposition 12.3.36: Direct Sums And Homomorphisms

Let $(M_i)_{i\in I}$ and $(N_j)_{j\in J}$ be a collection of modules with I and J indexing sets. Then:

$$\mathrm{Hom}_R\left(\bigoplus_{i\in I} M_i, N\right) = \prod_{i\in I} \mathrm{Hom}_R(M_i, N)$$

and

$$\mathrm{Hom}_R\left(M, \prod_{j\in J} N_j\right) = \prod_{j\in J} \mathrm{Hom}_R(M, N_j)$$

***Proof*:**
let $\varphi : \oplus_{i\in I} M_i \to N$. Then for any $(\alpha_i)_{i\in I} \in \oplus_{i\in I} M_i$, there are only finitely many non-zero entries. For ease of visualization, lkets represent the element $(\alpha_i)_{i\in I}$ as

$$(\alpha_1, \alpha_2, ..., \alpha_n, 0, ...)$$

This represetnation can be confusing on two terms: we have implicitly chosen an "order" of the elements and re-labelled the indices of the finite eleents accordingly, and it makes the set I look like it is *countable*, which is not necessarily the case. These two remarks should be kept in mind while working with this represetnation of the element.

Since there are n elements, write each of them as:

$$\alpha_i = \underbrace{0 + \cdots + 0}_{i-1 \text{ times}} + \alpha_i + \underbrace{0 + \cdots + 0}_{n-i \text{ times}}$$

Now, the finiteness condition was key here so that we may use linearity inductively, so that for any $\varphi \in \mathrm{Hom}_R\left(\bigoplus_{i\in I} M_i, N\right)$

$$\varphi((\alpha_i)_{i\in I}) = \varphi(\alpha_1) + \cdots + \varphi(\alpha_n)$$

Now, it is immediate that each function on the right hand side is naturally isomorphic to a function $\varphi_i \mathrm{Hom}_R(M_i, N)$. Labelling eahc of thes functions a φ_i, we get:

$$\varphi \to (\varphi_i)_{i\in I}$$

which is an isomorphism.

The direct product case is done almost identically, except we do not need to worry about finite additivity, since for any

$$\varphi(\alpha) = (\beta_i)_{i\in I}$$

we can define:

$$\varphi_i(\alpha) = \beta_i$$

which will give us the desired isomorphism, completing the proof.

As a consequence of this, we can simplify:

$$\mathrm{Hom}_R\left(\bigoplus_i M_i, \bigoplus_j N_j\right) \cong \prod_{i,j} \mathrm{Hom}_R(M_i, N_j)$$

If you are comfortable with linear algebra, then in the case where both direct sums have only finitely many components (also known as *summands*), then if φ_{ji} represent's the component function taking in the ith component in the domain and is in the jth component of the domain, then: the there is an isomrophism mapping $\varphi \mapsto (\varphi_{ij})$ where the maps is defined as:

$$\varphi \begin{pmatrix} s_1 \\ s_2 \\ \vdots \\ s_n \end{pmatrix} = \begin{pmatrix} \varphi_{11} & \varphi_{12} & \cdots & \varphi_{1n} \\ \varphi_{21} & \varphi_{22} & \cdots & \varphi_{2n} \\ \vdots & \vdots & \ddots & \cdots \\ \varphi_{n1} & \varphi_{n2} & \cdots & \varphi_{nn} \end{pmatrix} \begin{pmatrix} s_1 \\ s_2 \\ \vdots \\ s_n \end{pmatrix}$$

Showing that there is a natural relation between $\mathrm{Hom}_R(\oplus_i^m M_i, \oplus_j^n N_j)$ and matrix rings, especially if $M_i = N_j$. More on that in chapter 51.

Notice how important linearity is to split up the homomorphsim in direct products in the *domain*. To make sure that no misconceptions are being formed, here is a counter-example when a function is not linear:

Example 12.3.37: Hom's And Products Not Commuting in Domain

Let R be a nonzero commutative ring and $f\colon R \times R \to R$, $f(x,y) = xy$. Then $f(x,0) = 0$ and $f(0,y) = 0$ for all $x, y \in R$, while $f(1,1) = 1$. So $f(x,y) \neq f(x,0) + f(0,y)$ for $x = y = 1$, and f is not determined by its restrictions to the two factors, while an R-linear $\varphi\colon A \oplus B \to N$ satisfies $\varphi(a,b) = \varphi(a,0) + \varphi(0,b)$.

On the other hand, every function $f\colon M \to A \oplus B$, linear or not, is determined by its two components $\pi_A \circ f$ and $\pi_B \circ f$, since $f(m) = (\pi_A(f(m)), \pi_B(f(m)))$. For R-linear f, the components are the homomorphisms of the universal property of the product (proposition 12.3.9).

Exercise 12.3.3

1. Show that if M is an R-module, then $\mathrm{Hom}_R(R, M) \cong M$
2. Let M and N be R-modules, let ι_j and π_i be the inclusions and projections of the summands of $M \oplus M$ and of $N \oplus N$, and for $\varphi \in \mathrm{Hom}_R(M \oplus M, N \oplus N)$ put $\varphi_{ij} = \pi_i \circ \varphi \circ \iota_j \in \mathrm{Hom}_R(M, N)$, $i, j \in \{1, 2\}$. Show that $\varphi \mapsto (\varphi_{ij})$ is a bijection from $\mathrm{Hom}_R(M \oplus M, N \oplus N)$ onto the 2×2 arrays of elements of $\mathrm{Hom}_R(M, N)$, and that for $N = M$ it is a ring isomorphism from $\mathrm{End}_R(M \oplus M)$ onto the ring of 2×2 matrices with entries in $\mathrm{End}_R(M)$, multiplied by the usual formula with composition in place of multiplication of entries.
3. Let $\varphi : A \to B$ be an R-module isomorphism. Show that $\Phi : \mathrm{End}_R(A) \to \mathrm{End}_R(B)$ where $\Phi(f) = \varphi \circ f \circ \varphi^{-1}$ is a ring isomorphism, and if R is commutative an R-algebra isomrophism.
4. show that if $I \subsetneq R$ is a proper ideal, $I \cong S$ as an R-module isomorphism $\varphi(e) = 1$ a,d $e^2 = e$, then φ is in fact a ring-isomrophism, so I has the ring structure of S (though it cannot have the ring structure of R, since it cannot contain a unit).

13

Modules over Fields: Vector Spaces and Linear Algebra I

This chapter focuses on the study of modules where the ring are fields (i.e. [unital] commutative division ring). We will use the letter k (from German Körper) or the symbol $\mathbb{F}$ to represent an arbitrary field. As we have mentioned in definition 12.1.9, a module over a field is called a vector-space due to the historical precedence of the terminology which is now widely accepted in and beyond mathematics (for example, the term vector-space is used in physics, biology, and chemistry). This precedence of modules over fields comes from the fact that historically, fields were studied before general rings. Many problems in physics in the 19th century turned out to requires vector-spaces (ex. solutions to ODEs formed vector spaces, many important spaces of functions formed vector-spaces, the Cartesian plane formed a vector space), leading to precedence in nomenclature for modules over fields. Mathematically, giving another name to modules over fields is not unreasonable: as we will see, having a field act on a module is so restrictive (or powerful) that we will only need to keep track of two pieces of information to fully understand the structure and the classification of vector-spaces: the underlying field k, and a new number called the *dimension* of the vector-space[1]. No algebraic structure we have encountered requires so little data to be able to classify them (for example, the classification of finite simple groups required tens of thousands of pages over almost a century, while the classification of vector-space is regularly taught in a 1st or 2nd year undergraduate class).

Due to the simplicity of vector-space structures, vector space homomorphisms (k-module homomorphisms) will be completely classified. (A further word on this before talking a bit about dual theory and geometry)

As a consequence of the historical precedence of vector-spaces, a separate vernacular was developed for modules over fields that is now considered standard:

[1]This holds in infinite dimension too, where the dimension is a cardinal: any two bases of a vector space have the same cardinality [3, Proposition VI.1.9]. This book proves it for spaces with a finite basis (corollary 13.1.13).

Terminology over any Ring	Terminology over Fields
M is an R-module	M is a vector space over R
m is an element of M	m is a vector in M
N is a submodule of M	N is a subspace of M
M/N is a quotient module	M/N is a quotient space
M is a free module of rank n	M is a vector space of dimension n
M is a nonzero cyclic module	M is a 1-dimensional vector space
$\varphi : M \to N$ is an R-module homomorphism	$\varphi : M \to N$ is a (R) linear transformation
M and N are isomorphic as R-modules	M and N are isomorphic vector spaces
the subset A of M generates M	The subset A of M spans M
$M = RA$	each element of M is a linear combination of elements of A, i.e., $M = \text{Span}(A)$

13.1 Vector Spaces and their Properties

Vector spaces are famous for having a very simple structure: Given a vectorspace V over k, then V is isomorphic to k^N for appropriate N. In a linear algebra class, we say that every vector space has a basis. This N will be called the *dimension* of the vector-space. In many linear algebra classes, the attention is limited to $N \in \mathbb{N}$. However, this section will allow N to be of any cardinality (ex. $|\mathbb{N}|$ or $|\mathbb{R}|$). This is to show some of the power of vector-spaces: the (algebraic) structure does not get more complicated when dealing with infinite dimensions[2]

Before these results are shown, for those who gain an intuition via examples, here are a couple more example's of vector-spaces

Example 13.1.1: Vector Spaces
We already gave 4 examples in example 12.1.10. We give a few more here

1. We can generlize k^n as follows: notice that we can define k^n as

$$k^n = \{f \mid f : \{1, ..., n\} \to \mathbb{R}\}$$

   where addition is defined pointwise, and since k is commutative we can define a natural k-action on k^n (can you see it?). Any function $f \in k^n$ will tell us what value we should have in the component i. For example, if $f(1) = \pi$, $f(2) = 3$, an $f(3) = \sqrt{10}$, then this function is equivalent to:

$$(\pi, 3, \sqrt{10})$$

   Thus, We can consider:

$$k^{\mathbb{N}} = \{f \mid f : \mathbb{N} \to \mathbb{R}\}$$

   To be the $\mathbb{N}$-dimensional vector-space, or $k^{\mathbb{R}} = \{\mathbb{R} \mid f : \mathbb{R} \to \mathbb{R}\}$ to be the $\mathbb{R}$-dimensional vector space

2. Generalizing the above example, let k be a field, X a set, and $V = \text{Hom}_{\mathbf{Set}}(X, k)$ (another common notation is k^X). Then we can make V into a vector-space via point-wise operation

[2] On the other hand, the set-theoretical and analytic structure (if there is a topology present) gets more complicated, and arguably non-trivial, in infinite dimensions. For example, in infinite dimensions, surjective does not imply injective (similar to the proof for infinite sets), and there will exist linear transformations that are not continuous (for the appropriate topology).

in the codomain: for any $f, g \in V$, $c \in k$, $f + g$ is defined to be:

$$(f + g)(x) = f(x) + g(x) \qquad \forall x \in X$$

while fg and cf is defined as:

$$(fg)(x) = f(x)g(x) \qquad (cf)(x) = cf(x) \qquad \forall x \in X$$

These definitions are possible since the image of any function in V lands in a field, where all the above operations are well-defined. If we take the collection of lienar transformation from V to k (where V is a vector space), then we often denote that as V^*. Note that since k is also a ring, we can also define $(fg)(x) = f(x)g(x)$, making $\mathrm{Hom}_{\mathbf{Set}}(X, k)$ into a k-algebra.

Often, the set X is given its own properties (a popular example are X is a locally compact Hausdorff space, or X is a smooth manifold). Then we often try to deduce more information about X given the structure of hom-set $\mathrm{Hom}_{\mathbf{Set}}(X, k)$.

3. Let $R = k[x]$ for some field x. Then $k[x]$ is a k vector-space with action $c \cdot p(x) = cp(x)$. More generally, if $R = k[x_1, x_2, ..., x_n, ...]$ is some polynomial ring over several variables, then R is a k vector-space with $c \cdot p(x_1, x_2, ..., x_n, ...) = cp(x_1, x_2, ..., x_n, ...)$.

4. Let $k = \mathbb{C}$ an $V = \mathbb{C}^n$. Then $\mathbb{C}^n$ is a complex vector space with the action:

$$z \cdot (z_1, ..., z_n) = (zz_1, ..., zz_n)$$

There is a second natural action, known as the *conjugate action*:

$$z \cdot (z_1, ..., z_n) = (\overline{z}z_1, ..., \overline{z}z_n)$$

More generally, if V is a vector-space over $\mathbb{C}$ (also known as a complex vector space), then $\overline{V}$ denote the same space with the element being conjugated before the action is applied.

5. (If you know some ODE's) Given a linear ordinary differential equation, the set of all solutions form's a vector-space. Take for example $\varphi : C^\infty(\mathbb{R}) \to C^\infty(\mathbb{R})$ where:

$$f \mapsto f'' + f$$

Consider the subspace V where

$$V := \{f \in C^\infty(\mathbb{R}) \mid f'' + f \equiv 0\}$$

Then using elementary ODE theory, we find that:

$$V = \mathrm{span}_{\mathbb{R}}(\{e^t, e^{-t}\})$$

The fact that all solutions to the ODE $f'' + f = 0$ is a linear combination of these two solutions is a remarkable property of *linear* ODE's. This simple property of linearity can be taken very far: in the world of PDE's (Parital Differential Equations), if you have something called a *linear PDE*, which means that if you have two solutions, then add them and/or scale the terms, the result is another solution. The power we get from this is that we can then see if this is generalizable to taking *limits* of some very simple solutions to the PDE. As a common example, let's say the solution is of the form $\cos(\alpha x)$ or $\sin(\beta x)$ for any α, β. Then under the right conditions[a], the collection of these (after being closed under addition) is *dense* in $L^2(S^1)$, meaning we can use limits to construct *any* $L^2(S^1)$ function and find another solution to our PDE. A common place this particular example is used is *Fourier Analysis*[b]

6. (If you know Differential Geometry) Let M be a smooth n-manifold and consider the collection of all $\varphi : C^\infty(M) \to \mathbb{R}$. Then the collection of all *derivations at* p[c] for some point $p \in M$, denoted $\text{der}_p(M) \subseteq \text{Hom}_{\mathbf{Smooth}}(C^\infty(M), \mathbb{R})$ forms a vector-space of dimension n, and is a common definition of the *tangent space* of the manifold M at the point p[d]

[a] See a textbook covering Fourier Analysis, ex. Pugh or Folland
[b] See [85]
[c] linear function where $\varphi(fg) = \varphi(f)g + f\varphi(g)$
[d] See [79, Tangent Vector as Derivation, Dimension of the Tangent Space]

Now, we shall develop a more sophisitaced notion of generating set:

Definition 13.1.2: Linear Independence And Basis

Let M be an R-module.

1. A subset $S \subseteq M$ is said to be *linearly indepenent*, or a set of *linearly independent elements*, if for any equation

$$a_1 m_1 + a_2 m_2 + ... + a_n m_n = 0$$

with $a_1, a_2, ..., a_n \in R$ and $m_1, m_2, ..., m_n \in S$, then $a_1 = a_2 = \cdots = a_n = 0$. If this is not the case, the elements are called *linearly dependent*. In other words, if $I = \{m_1, m_2, ..., m_n\} \subseteq M$, so that $\iota : I \to M$ is injective, then:

$$\begin{array}{ccc} F^R(I) & \xrightarrow{\varphi} & M \\ {\scriptstyle j}\uparrow & \nearrow_{\iota} & \\ I & & \end{array} \tag{13.1}$$

commutes[a] and φ is injective. Note that I can be an arbitrary indexing set, that is for every $i \in I$, $m_i \in M$ corresponds to it, and then we would have an injection $\iota : I \to M$ which lifts to $\varphi : F^R(I) \to M$. If $R = k$, then the elements are called *linearly independent vectors*.

2. A *basis* for M is an *set* $\{a_1, a_2, ..., a_n\}$ of elements that is linearly independent and which generate sM (i.e. span M).

3. An *ordered basis* for M is an *ordered set* (a tuple) $(a_a, a_2, ..., a_n)$ of linearly independent elements which generates M (i.e. span M).

[a] The diagram commuting is the universal property of free modules

The point of an *ordered basis* is so that $A \subseteq M$ gives a *unique* isomorphism:

$$\varphi : F^R(A) \cong M$$

i.e. The φ in equation (13.1) is both injective and surjective. In particular, two ordered bases will be considered different even if one is a rearrangement of the other (hence why it's ordered).

13.1.3 Convention In this section, all bases shall implicitly be ordered basis. The convention shall be dropped when working with tensor products of vector spaces.

Note that the φ from the commutative diagram in equation (13.1) has as domain all *finite* combinations of elements of $\{m_i\}_{i\in I}$, so that when writing:

$$\sum_{i\in I} r_i m_i$$

only finitely many r_i are nonzero. If φ is injective, then $\sum_{i\in I} r_i m_i = 0$ if and only if $r_i = 0$ for all $i \in I$. Sometimes to emphasize the fact that it's ordered, a basis is called an *ordered basis*. In terms of indexing sets, the ordered elements are generalized to elements having different indexes. Notice how being linearly independent is different from proposition 12.3.6(3), where if $x \in \oplus_{i\in I} N_i$ implies there exists unique elements $v_i \in N_i$ such that $x = \sum_i v_i$. We are adding another requirement on $\bigoplus_i v_i$, namely that the function φ in the above definition is injective.

A module M having a basis is in fact a very restricting condition:

Lemma 13.1.4: Basis iff Free

Let M be an R-module. Then M is free if and only if it admits a basis, in paritcular $B \subseteq M$ is a basis if and only if the natural homomorphism $R^{\oplus B} \to M$ is an isomorphism

***Proof*:**
This is immedaite from the definition: if $B \subseteq M$ is linearly independent and generates M, then $\varphi : R^{\oplus B} \to M$ is injective and surjective, and if $\varphi : R^{\oplus B} \to M$ is an isomorphism, then $\varphi(B)$ is a subset of M which generates it and is linearly independent.

Example 13.1.5: Linearly Dependent and Independent Sets

1. Let $M = \mathbb{Z}/n\mathbb{Z}$ be a $\mathbb{Z}$-module. Then:

   $$n \cdot [1]_n = 0$$

   but naturally $n \neq 0$. More generally, if R is a ring with a zero divisor, and $(z) \subseteq R$ is the sub-module generated by the zero-divor (z), then if $zz' = 0$, $z' \cdot z = 0$,showing that the singleton z is linearly dependent.

2. Let $R = \mathbb{C}[x, y]$ be a module over itself. This ring has no zero divisors, hence the above does not apply. However, that there are still linearly dependent elements, for example:

   $$y \cdot x + (-x) \cdot y = xy - xy = 0$$

   showing that x, y are *not* linearly independnet over $\mathbb{C}[x, y]$. However, if we consider $\mathbb{C}[x, y]$ over $\mathbb{C}$, then $\{x, y\}$ *are* linearly independent, since $\mathbb{C}[x, y]$ is the free $\mathbb{C}$-algebra. Hence:

   $$F^{\mathbb{C}}(\{x, y\}) = \mathbb{C}^2 \to \mathbb{C}[x, y]$$

   is an injective function. However, $\{x, y\}$ is not a basis since the above homomorphsim is not surjective, since nothing maps to xy. Is there any finite that will create a surjective map?

3. If R is any ring (which includes rings with torsion elements), then $(1) = R$, and $r \cdot 1 = r1$ if and only if $r = 0$. Hence,
$$R \mapsto R$$
is an injective homomorphism (even surjective, making it a basis). This shows that the choice of subset of the module effects whether the set if linearly independent or a basis.

   Though R has a basis when over itself, show that $\mathbb{Z}/2\mathbb{Z} \oplus \mathbb{Z}/4\mathbb{Z}$ over $\mathbb{Z}$ does *not* have a basis, or even a linearly independent set.

As we saw in the above example, some modules have linearly independent sets, some do not, and others have a basis. By a simple applications of Zorn's lemma and some manipulation of definition, we can show that every module has a maximally linearly independent set:

Lemma 13.1.6: Maximally Linearly Independent Set

Let M be an R-module and let $S \subseteq M$ be a lienarly independnet set. Then there exsits a maximal linearly independent subset of M containing S.

***Proof*:**
This is an application of Zorn's lemma: Let $\mathcal{L}$ be the collection of linearly independent subset of M containing S ordered by inclusion. Since $S \in \mathcal{L}$, $\mathcal{L} \neq \emptyset$. If we take any chain $\mathcal{C} \subseteq \mathcal{L}$, and take $C = \cup\mathcal{C}$, then C is linearly independent, since it it were linearly dependent, then only finitely many linear element would be used in the equation, but then they all belong to some $C_i \in \mathcal{C}$, which by assumption is linearly independnet. Hence, by Zorn's lemma $\mathcal{L}$ contains a maximally linearly independent set containing S.

13.1.7 Trivia The Axiom of Choice and the above lemma are in fact equivalent, hence it is impossible to prove the above statement without using Zorn's lemma.

If S is a maximally linearly independent set containing $\emptyset$, we shall simply say that S is maximally linearly independent. Note that being maximally linearly independent does not guarantee a unique size or that it generates the entire module, for example $\{2\} \subseteq \mathbb{Z}$ is maximally linearly independent but does not generate $\mathbb{Z}$. In the special case where $R = k$ is a field so that we have a vector-space V, then a maximally linearly independent set is indeed a basis!

Theorem 13.1.8: Vector Space has Basis

Let V be a vector space over k and let B be a maixmally lienarly independnet set. Then B is a basis of V, hence V is a free k-module. Furthermore, if S is a liearly independent set, then S is contained in a basis B.

***Proof*:**
We need to show that B generates V. Let $v \in V$, $v \notin B$. Then by maximality of B, $B \cup \{v\}$ is linearly dependent, hence there exists $v_1, v_2, ..., v_n$ and $c_0, c_1, ..., c_n$ such that
$$c_0 v + c_1 v_1 + \cdots + c_n v_n = 0$$
with not all $c_i = 0$. Note that $c_0 \neq 0$ or else we would get $c_1 v_1 + \cdots + c_n v_n = 0$ with not all

$c_i \neq 0$, contradicting linearly independence of elements in B. Since k is a field, c_0 is a unit, hence:

$$v = (-c_0^{-1}c_1)v_1 + \cdots + (-c_0^{-1}c_n)v_n$$

But then, $v \in \text{span}(B)$, showing that B generated V. By lemma 13.1.4, V is a free k-module.

Furthermore, if S is lienarly independent, then S is contained in a maximally linearly independent set, say B. But by our above reasoning B is a basis, hence S is contained in a basis, as we sought to show.

Hence, every vector-space is free. Before continuing our exploration of bases, a quick comment must be made: we can define the dual notion, where a *minimally spanning set* is a spanning set no proper subset of which spans V, and the same statement holds in the reverse direction, namely:

Proposition 13.1.9: Vector space, Minimally Spanning then Basis

Let V be a k-vector space and let B be a minimally spanning set. Then B is a basis for V, making V a free k-module. Furthermore, if S is any spanning set, then S contains a minimal spanning set B.

***Proof*:**
For the first claim, suppose toward a contradiction that the minimally spanning set B is linearly dependent, so there exist distinct $v_1, ..., v_n \in B$ and scalars $c_1, ..., c_n \in k$, not all zero, with

$$c_1v_1 + c_2v_2 + \cdots + c_nv_n = 0$$

Reordering, we may take $c_1 \neq 0$. Since k is a field, c_1 is a unit, and so

$$v_1 = (-c_1^{-1}c_2)v_2 + \cdots + (-c_1^{-1}c_n)v_n \in \text{span}(B \setminus \{v_1\})$$

Now take any $v \in V$. Since B spans, v is a linear combination of elements of B. Replacing every occurrence of v_1 in that combination by the displayed expression yields a linear combination of elements of $B \setminus \{v_1\}$, so $\text{span}(B \setminus \{v_1\}) = V$, contradicting minimality of B. Hence B is linearly independent and spanning, that is, a basis, and by lemma 13.1.4, V is a free k-module.

For the second claim, order the linearly independent subsets of S by inclusion. The union of a chain of linearly independent sets is again linearly independent, since a linear dependence involves only finitely many elements, which all lie in a single member of the chain. By Zorn's lemma, there is a maximal linearly independent subset $B \subseteq S$. We claim B spans V. Take any $s \in S$. If $s \in B$, then $s \in \text{span}(B)$. Otherwise, $B \cup \{s\}$ is linearly dependent by maximality, so there is a dependence $c_0s + c_1v_1 + \cdots + c_nv_n = 0$ with $v_i \in B$ and not all coefficients zero, and $c_0 \neq 0$ since B itself is linearly independent. As c_0 is a unit, $s \in \text{span}(B)$. Hence $S \subseteq \text{span}(B)$, and since every $v \in V$ is a linear combination of elements of S, each of which is a linear combination of elements of B, we get $\text{span}(B) = V$. Finally, B is minimally spanning: if $\text{span}(B \setminus \{b\}) = V$ for some $b \in B$, then $b = c_1v_1 + \cdots + c_nv_n$ with $v_i \in B \setminus \{b\}$, and $b - c_1v_1 - \cdots - c_nv_n = 0$ is a linear dependence in B, contradicting the linear independence of B. Hence $B \subseteq S$ is a minimal spanning set.

Corollary 13.1.10: Subspaces Of Vector-Spaces Are Free

Let V be a vector-space and $W \subseteq V$ be a subspace. Then W is free

***Proof*:**
Let $W \subseteq V$ be a subspace. Since W is a k-module, by theorem 13.1.8, it is free.

Note that this is not true for arbitrary free-modules: there exists submodule of free modules which are *not* free[3]. In fact, since any ring R is a module over itself, then it is easy to find counter-examples. For instance, the ideal (x, y) of $k[x, y]$ is not free: two elements f, g are never linearly independent, since $g \cdot f - f \cdot g = 0$, so a basis would have one element, and (x, y) is not principal, since a generator would divide both x and y and so be a nonzero constant, while every element of (x, y) has constant term 0. Another simpler example is as follows

Example 13.1.11: Non Free Submodule
Take $\mathbb{Z}_6$ over itself, and consider the ideal (2). Show that it is not free[a].

[a]Hint: it's torsion

In later chapters, we shall see that submodules of free modules over slightly more general rings, namely PIDs, will still be free[4], however this generlization is limited in scope and does not further generlize over more general rings, as we shall discuss later.

The key in theorem 13.1.8 is that every element in a field is a unit. Commutativity was not important. Thus, this same proof can work for division rings more generally[5]. Over a general ring, minimal generating sets can have different sizes: $\{1\}$ and $\{2, 3\}$ both generate $\mathbb{Z}$ as a $\mathbb{Z}$-module, and no proper subset of either does. We thus ask the question of when do we get bases with different cardinalites, or if there are conditions for which different basis always have the same cardinality. For vector-spaces, every basis *always* has the same cardinality! The following theorem is the key result for the proof:

Theorem 13.1.12: Replacement Theorem

Let $A = (a_1, a_2, \ldots, a_n)$ be a basis of V and let $b_1, b_2, ..., b_m$ be linearly independent vectors in V. Then $m \leq n$, and after renumbering the a_i, for each $k \in \{0, 1, ..., m\}$ the family $(b_1, b_2, ..., b_k, a_{k+1}, a_{k+2}, ..., a_n)$ is a basis of V. In other words, the elements $b_1, b_2, ..., b_m$ can be used to successively replace elements of the basis A, and the result is still a basis.

***Proof*:**
We proceed by induction on k. For $k = 0$ the family is A. Let $0 \leq k < m$, and suppose that $(b_1, \ldots, b_k, a_{k+1}, \ldots, a_n)$ is a basis of V. It spans V, so

$$b_{k+1} = \beta_1 b_1 + \cdots + \beta_k b_k + \alpha_{k+1} a_{k+1} + \cdots + \alpha_n a_n \tag{13.2}$$

for some scalars. Not all the α_i are zero, since otherwise $b_{k+1} - \beta_1 b_1 - \cdots - \beta_k b_k = 0$ would contradict the linear independence of $b_1, \ldots, b_{k+1}$. In particular $k < n$, and after renumbering

[3]Though it is true for free groups, see appendix B
[4]see theorem 14.1.6
[5]And will be used in chapter 51

$a_{k+1}, \ldots, a_n$ we may assume $\alpha_{k+1} \neq 0$. Then

$$a_{k+1} = \alpha_{k+1}^{-1} \left(b_{k+1} - \beta_1 b_1 - \cdots - \beta_k b_k - \alpha_{k+2} a_{k+2} - \cdots - \alpha_n a_n \right)$$

lies in the span of $b_1, \ldots, b_{k+1}, a_{k+2}, \ldots, a_n$, so this family spans every element of the old basis, hence V. It is linearly independent: suppose

$$\gamma_1 b_1 + \cdots + \gamma_{k+1} b_{k+1} + \delta_{k+2} a_{k+2} + \cdots + \delta_n a_n = 0$$

Substituting equation (13.2) for b_{k+1} gives a relation in the old basis, in which the coefficient of a_{k+1} is $\gamma_{k+1}\alpha_{k+1}$, the coefficient of b_i is $\gamma_i + \gamma_{k+1}\beta_i$ for $i \leq k$, and the coefficient of a_i is $\delta_i + \gamma_{k+1}\alpha_i$ for $i \geq k+2$. All of them vanish. As $\alpha_{k+1} \neq 0$, $\gamma_{k+1} = 0$, and then every γ_i and every δ_i is 0. So $(b_1, \ldots, b_{k+1}, a_{k+2}, \ldots, a_n)$ is a basis of V. Since $k < n$ for every $k < m$, also $m \leq n$, completing the proof.

The proof uses only that nonzero scalars are invertible, so it applies verbatim to modules over a division ring, with the scalars acting on the left. The Replacement Theorem relates the sizes of linearly independent sets and spanning sets:

Corollary 13.1.13: Steinitz exchange lemma

1. Suppose V has a finite basis with n elements. Any set of linearly independent vectors has at most n elements. Any spanning set has at least n elements
2. If V has some finite basis then any two bases of V have the same cardinality

***Proof*:**

1. Let A be a basis with n elements. A linearly independent set S has at most n elements: otherwise it contains $n+1$ linearly independent vectors, which theorem 13.1.12 forbids. A spanning set S contains a basis B (proposition 13.1.9), which has at most n elements by the previous sentence, so B is finite. Applying theorem 13.1.12 to the basis B and the linearly independent vectors of A gives $n \leq |B| \leq |S|$.
2. Every basis of V is linearly independent and spanning, so by (1) it has exactly n elements, where n is the size of the given finite basis, completing the proof.

A finitely generated vector space has a finite basis, contained in any finite spanning set (proposition 13.1.9), and by corollary 13.1.13(2) all of its bases have the same number of elements, so the following is well defined:

Definition 13.1.14: Dimension

Let V be a vector space over F. Then the cardinality of the basis is called the *dimension* of V, and is denoted $\dim_F(V)$ or $\dim(V)$ if context permits. If V is not finitely generated, then we say that V is infinite dimensional, and we write $\dim V = \infty$.

As we saw in example 13.1.5, a singleton set with a single element which has torsion is always linearly dependent. In an integral domain, we have some more power:

Corollary 13.1.15: Module Linearity

Let R be an integral domain and let M be a free R-module of rank $n < \infty$. Then any $n+1$ elements of M are R-linearly dependent, i.e., for any $y_1, y_2, ..., y_{n+1} \in M$, there are elements $r_1, r_2 ..., r_{n+1} \in R$ not all nonzero such that

$$r_1 y_1 + r_2 y_2 + \cdots + r_{n+1} y_{n+1} = 0$$

***Proof*:**
There is a trick similar to Gauss's lemma. We can embed R in its quotient field (since R is an integral domain, this is indeed an embedding), say k is its quotient field. Since M is a free module,

$$M \cong \underbrace{R \oplus R \oplus \cdots R \oplus R}_{n \text{ times}}$$

and so

$$M \subseteq \underbrace{k \oplus k \oplus \cdots \oplus k}_{n \text{ times}}$$

Since the latter is an n dimensional vector space over F, so any $n+1$ dimensional elements of M are F-linearly dependent. By clearing the denominators of the scalars (ex. multiplying through by the product of all the denominaotrs), we get an R-linear dependence realtion among $n+1$ elements of M.

An important consequence of the existence of a basis is that linear transformation $f : V \to W$ can be defined by first determining where a basis of V maps to, and then extending linearly (that is, if $v = \sum_{\beta_i \in \mathcal{B}} b_i \beta_{\in} W$, then $f(v) = f\left(\sum_{\beta_i \in \mathcal{B}} b_i \beta_i\right) = \sum_{\beta_i \in \mathcal{B}} b_i f(\beta_i)$). Note however that the choice basis is important, we shall get back to this in section 13.2, and that vector spaces may have many different bases (of the same cardinality by the replacement theorem):

Example 13.1.16: Different Basis
As we have defined in example 12.3.2 the set

$$e_i = (\underbrace{0, ..., 0}_{i-1 \text{ times}}, 1, \underbrace{0, ..., 0}_{k-i \text{ times}}) \qquad 1 \leq i \leq n$$

is a basis for $\mathbb{Q}^n$. There are countably many different basis for $\mathbb{Q}^n$. Can you think of a few? If you know about inner product spaces, can you think of an orthonormal [hamel][a] basis?

[a] The term orthonormal basis is usually reserved for *countable* linear combination for *Hilbert space*. Since the linear combination is not finite, it requires some analysis to define. This would be covered in a text on *Functional Analysis*. If you know about Hilbert spaces, then taking $\mathbb{C}[x]$ as the closure of $\mathbb{C}[x]$, is there an orthonormal basis for it?

13.1.1 Quotient Spaces and Subspaces

Now that we have established the struture of a vector-space, we can some questions about subspaces the structure of quotient spaces, with particular interest in finite vector-spaces to be able to take advantage of counting arguments. We already saw that subspace of vector spaces are free k-module.

Proposition 13.1.17: Dimension Of Quotient Space

Let V be a finite dimensional vector space over k and let $W \subseteq V$ be a subspace. Then:

1. W and the quotient space V/W are finite dimensional, and
$$\dim V = \dim W + \dim V/W$$
2. $\dim W \leq \dim V$, with equality only if $W = V$
3. if $V_1, \ldots, V_r$ are finite dimensional vector spaces over k, then $V_1 \times \cdots \times V_r$ is finite dimensional and $\dim(V_1 \times \cdots \times V_r) = \dim V_1 + \cdots + \dim V_r$

***Proof*:**
Let $n = \dim V$. The quotient module V/W is a vector space over k, and we write $\overline{v} = v + W$ for the class of $v \in V$.

1. The subspace W has a basis B (theorem 13.1.8). It is a linearly independent subset of V, so it has at most n elements (corollary 13.1.13(1)), say $B = (w_1, \ldots, w_m)$. So W is finite dimensional, and $\dim W = m$ by corollary 13.1.13(2). By theorem 13.1.8, B is contained in a basis of V, which has n elements by corollary 13.1.13(2), so this basis can be written $(w_1, \ldots, w_m, u_1, \ldots, u_{n-m})$. The classes $\overline{u}_1, \ldots, \overline{u}_{n-m}$ span V/W: every $v \in V$ is $\sum_i a_i w_i + \sum_j b_j u_j$ for some scalars, and $\overline{w}_i = 0$ since $w_i \in W$, so $\overline{v} = \sum_j b_j \overline{u}_j$. They are linearly independent: if $\sum_j b_j \overline{u}_j = 0$, then $\sum_j b_j u_j \in W$, say $\sum_j b_j u_j = \sum_i a_i w_i$, and the relation $\sum_i a_i w_i - \sum_j b_j u_j = 0$ in the basis of V forces every $b_j = 0$. So V/W has a basis with $n - m$ elements, and
$$\dim V/W = n - m = \dim V - \dim W$$
2. By (1), $\dim W = m \leq n$. If $m = n$, the basis of V chosen in the proof of (1) is $(w_1, \ldots, w_n)$, whose elements lie in W, so $V = \operatorname{span}(w_1, \ldots, w_n) \subseteq W$ and $W = V$.
3. For each i let $\iota_i \colon V_i \to V_1 \times \cdots \times V_r$ send v to the tuple with v in position i and 0 elsewhere, and choose a basis B_i of V_i, which has $\dim V_i$ elements. The vectors $\iota_i(b)$, for $1 \leq i \leq r$ and $b \in B_i$, span the product, since $(v_1, \ldots, v_r) = \sum_i \iota_i(v_i)$ and each v_i is a linear combination of elements of B_i. They are linearly independent: if $\sum_i \sum_{b \in B_i} c_{i,b}\, \iota_i(b) = 0$, then the ith component gives $\sum_{b \in B_i} c_{i,b} b = 0$ in V_i, so every $c_{i,b} = 0$. Hence they form a basis of the product with $\dim V_1 + \cdots + \dim V_r$ elements, completing the proof.

Naturally, since we are working with quotients, we have an associated linear transformation The following is the "homomorphism-equivalent" of the previous proposition:

Corollary 13.1.18: Rank-Nullity Theorem

Let $\varphi : V \to W$ be a linear transformation of vector spaces over k with $\dim(V) < \infty$. Then $\ker \varphi$ is a subspace of V, $\varphi(V)$ is a finite dimensional subspace of W, and
$$\dim_k(V) = \dim_k(\ker(\varphi)) + \dim_k(\varphi(V))$$

***Proof*:**
By theorem 12.2.10(1), applied to the k-module homomorphism φ, the kernel $\ker\varphi$ is a subspace of V and there is an isomorphism $\psi\colon V/\ker\varphi \to \varphi(V)$. The image is a subspace of W, since it contains $0=\varphi(0)$ and $\varphi(v)+c\varphi(v')=\varphi(v+cv')$ for $v,v'\in V$ and $c\in k$. By proposition 13.1.17(1), $\ker\varphi$ and $V/\ker\varphi$ are finite dimensional and

$$\dim V = \dim\ker\varphi + \dim V/\ker\varphi$$

Let $(\overline{v}_1,\dots,\overline{v}_r)$ be a basis of $V/\ker\varphi$. The family $(\psi(\overline{v}_1),\dots,\psi(\overline{v}_r))$ spans $\varphi(V)$, since ψ is linear and surjective. It is linearly independent, since $\sum_i c_i\psi(\overline{v}_i)=\psi(\sum_i c_i\overline{v}_i)=0$ forces $\sum_i c_i\overline{v}_i=0$ by injectivity of ψ, hence every $c_i=0$. So $\varphi(V)$ is finite dimensional with $\dim\varphi(V)=r=\dim V/\ker\varphi$, and $\dim V=\dim\ker\varphi+\dim\varphi(V)$, completing the proof.

Since the dimensions are of the subspaces are invariant to basis, we can give a name to the dimension of the image and null space of a linear transformation

Definition 13.1.19: Rank And Nullity

If $\varphi: V\to W$ is a linear transformation of vector spaces over k, $\ker(\varphi)$ is called the *null space* of φ ,and the dimension of $\ker(\varphi)$ is called the *nullity* of φ. The dimension of $\varphi(V)$ is called the *rank* of φ. If $\ker(\varphi)=0$, the transformatoin is said to be *nonsingular*.

The reasoning behind the name *nonsingular* is due to the fact that very often in (differentil) geometry, we associated to shapes a vector-space at each point (such an object is called a *vector bundle*) and if the curve "drops rank" this would correspond to a particular function having $\dim_k(\ker(\varphi))>0$[6]. For example, the curve $x^3=y^2$ "drops rank" at $(0,0)$.

Corollary 13.1.20: Properties of [finite dim.] Linear Transformations

Let $\varphi: V\to W$ be a linear transformation of vector spaces of the same finite dimension n. Then the following are equivalent

1. φ is an isomorphism
2. φ is injective, i.e., $\ker(\varphi)=0$
3. φ is surjective, i.e. $\varphi(V)=W$
4. φ sends some basis $(v_1,\dots,v_n)$ of V to a basis $(\varphi(v_1),\dots,\varphi(v_n))$ of W
5. φ sends every basis of V to a basis of W

Notice that this proof is saying that if $f: V\to W$ is a k-homomorphism where $\dim_k(V)=\dim_k(W)=n$, then given f is injective, it is surejctive. This fails to be the case even for maps between free moduels over PIDs, for example $f:\mathbb{Z}\to\mathbb{Z}$ mapping $z\mapsto 2z$ is an injective $\mathbb{Z}$-module homomorphism between free $\mathbb{Z}$-modules, but is certainly not surjective! This also fails for infinite dimensional vectors spaces as will be demonsarted by a counter-example after the proof. Hence, the fact that it's sufficient to check injectivity shows how linear maps between finite vector-spaces are akin to maps between

[6] In particular, if T_pf is the tangent map at p, then T_pf would drop rank

finite sets[7].

***Proof*:**
The map φ is injective exactly when $\ker(\varphi) = 0$, since $\varphi(v) = \varphi(v')$ means $v - v' \in \ker(\varphi)$. By corollary 13.1.18, $n = \dim \ker(\varphi) + \dim \varphi(V)$.

(1)⇒(5) Let $(v_1, \dots, v_n)$ be a basis of V. Every $w \in W$ is $\varphi(v)$ for some $v = \sum_i c_i v_i$, so $w = \sum_i c_i \varphi(v_i)$, and $(\varphi(v_1), \dots, \varphi(v_n))$ spans W. If $\sum_i c_i \varphi(v_i) = 0$, then $\varphi(\sum_i c_i v_i) = 0$, so $\sum_i c_i v_i = 0$ by injectivity and every $c_i = 0$. Hence $(\varphi(v_1), \dots, \varphi(v_n))$ is a basis of W.

(5)⇒(4) The space V has a basis with n elements, since $\dim V = n$.

(4)⇒(3) If $(\varphi(v_1), \dots, \varphi(v_n))$ is a basis of W, then every $w \in W$ is $\sum_i c_i \varphi(v_i) = \varphi(\sum_i c_i v_i)$.

(3)⇒(2) If $\varphi(V) = W$, then $\dim \ker(\varphi) = n - n = 0$. As $\{0\} \subseteq \ker(\varphi)$ also has dimension 0, proposition 13.1.17(2) gives $\ker(\varphi) = \{0\}$.

(2)⇒(1) If $\ker(\varphi) = 0$, then $\dim \varphi(V) = n = \dim W$, so $\varphi(V) = W$ by proposition 13.1.17(2). Thus φ is a bijective linear map, an isomorphism by lemma 12.2.3, completing the proof.

Note that finiteness of dimension is important in the previous corrollaries: these need not hold in infinite dimension

Example 13.1.21: Infinite Dimensinoal Linear Transformations
Take $V = \ell^2$, the set of all infinite sequences of real numbers satisfying the property:

$$\left(\sum_{i \in \mathbb{N}}^{\infty} |x_i|^2 \right)^{1/2} < \infty$$

Then define $f : V \to V$ via:

$$(x_1, x_2, ..., x_n, ...) \mapsto (x_1, \frac{x_2}{2}, ..., \frac{x_n}{n})$$

Then this function is injective, but not surjective. Even more is true. Here V and f belong to some of the nicest infinite dimensional spaces and functions (V is a Hilbert space and f is a bounded self-adjoint linear operator), and hence this property is not easily rectified.

We now take a look at subspaces. We have already established that all subspaces of a vector-spaces are free. Another importnant property is that every subspace always has a *compliment*, that is if $W \subseteq V$, then there exists a $U \subseteq V$ such that $U \cap W = \{0\}$ and $W + U = V$. This is certainly *not* true for general R-modules. In the $\mathbb{Z}$-module $M = \mathbb{Z}/4\mathbb{Z}$, take $W = \{0, 2\}$. A subgroup U with $W + U = M$ contains an element u with $1 = u + w$ for some $w \in W$, so $u \in \{1, 3\}$, and u generates M. Then $U = M$ and $U \cap W = W \neq \{0\}$, so W has no complement.[8] However, we may always find such a compliment for subspaces of vector-spaces, given the space is finite dimensional:

[7] In fact, this parallels is runs more deeply than it may at first seem, see a text on K-theory for some interesting elaboration on this notion

[8] In **Grp**, the corresponding question is which short exact sequences split. See section 17.2 for a generalized notion of splitting and proposition 5.3.9 for groups.

Proposition 13.1.22: Existence Of Compliment

Let V be a finite dimensional vector space and $W \subseteq V$ be a subspace. Then there exists a subspace $U \subseteq V$ such that

1. $W \cap U = \{0\}$
2. $W + U = V$

If these two conditions are satisfied, we will write $V = W \oplus U$ and call V the direct sum of W and U (as in definition 12.3.3).

***Proof*:**
Let $n = \dim V$. By proposition 13.1.17(1), W has a finite basis $(w_1, \dots, w_m)$. By theorem 13.1.8 it is contained in a basis of V, which has n elements (corollary 13.1.13(2)), so this basis can be written $(w_1, \dots, w_m, u_1, \dots, u_{n-m})$. Let $U = \operatorname{span}(u_1, \dots, u_{n-m})$.

1. If $v \in W \cap U$, then $v = \sum_i a_i w_i = \sum_j b_j u_j$ for some scalars, and the relation $\sum_i a_i w_i - \sum_j b_j u_j = 0$ in the basis of V forces all coefficients to vanish, so $v = 0$.
2. Every $v \in V$ is $\sum_i a_i w_i + \sum_j b_j u_j$ for some scalars, with $\sum_i a_i w_i \in W$ and $\sum_j b_j u_j \in U$, so $W + U = V$, completing the proof.

Finite dimension only keeps the bases finite: by theorem 13.1.8, a basis of W extends to a basis of V in any dimension, and the same argument produces a complement of W in every vector space V.

Corollary 13.1.23: Finite Generation of Subspace

Let $W \subseteq V$ be a subspace of a finite dimensional vector space. Then W is finitely generated

***Proof*:**
By proposition 13.1.17(1), W is finite dimensional, so it has a finite basis, and a basis generates W (definition 13.1.2), completing the proof.

If $V = W \oplus U$, every $v \in V$ is $w + u$ for unique $w \in W$ and $u \in U$: if $w + u = w' + u'$, then $w - w' = u' - u \in W \cap U = \{0\}$. So $\pi_W(w + u) = w$ defines a map $\pi_W : V \to V$, which is linear, with image W and kernel U. Such maps are important enough to be given a name:

Definition 13.1.24: Projection Map

Let $\pi : V \to V$ be a linear transformation $U \subseteq V$. Given $V = U \oplus W$, then the *projection map* (with respect to U) is the map $\pi_U : V \to V$ such that $\pi(v) = \pi(u + w) = u$.

Notice $\pi \circ \pi = \pi$, that is, applying the map twice gives back the same result: $\pi(\pi(v)) = \pi(v)$. This in fact characterizes such a map:

Proposition 13.1.25: Characterizing Projection Maps

Let π be linear operator over a [not necessarily finite dimensional] vector space such that $\pi \circ \pi = \pi$. Then π is a projection map.

***Proof*:**
Let $U = \text{im}(\pi)$ and $W = \text{im}(I - \pi)$. Then for any $v \in V$:

$$\pi(v) + v - \pi(v) = v$$

hence $U + W = V$. If $x \in U \cap W$. Since $x \in \text{im}(\pi)$, $x = \pi(y)$ for some $y \in V$, and so:

$$\pi(x) = \pi(\pi(y)) = \pi(y) = x$$

hence, $\pi(x) = x$. Then:

$$\begin{aligned} x &= \pi(x) && x \in U \\ &= (I - \pi)(x) && x \in W \\ &= \pi((I - \pi)(x)) && (I - \pi)(x) = x \in U \\ &= \pi(x - \pi(x)) \\ &= \pi(x - x) && \pi(x) = x \\ &= \pi(0) \\ &= 0 \end{aligned}$$

Hence $x = 0$, and so $U \cap W = \{0\}$. With the above, we get that

$$V = U \oplus W = \ker(\pi) \oplus \text{im}(\pi)$$

as we sought to show.

Notice how the above proof did not rely on any structure of V (notably, it was not important that V had a basis). Thus, if $\varphi : M \to M$ is any R-module homomorphism such that $\varphi \circ \varphi = \varphi$, then

$$M = \ker(\varphi) \oplus \text{im}(\varphi)$$

For this reason, it is much more common to define projection maps as maps that satisfy the property of $\varphi^2 = \varphi$ (i.e., they are *idempotent*).

Exercise 13.1.1

1. Let $a \in \mathbb{R}$ and let $\mathbb{R}_n[x]$ be the $\mathbb{R}$-vector space of real polynomials of degree at most n, together with 0. Show that $1, (x-a), (x-a)^2, \ldots, (x-a)^n$ is a basis of $\mathbb{R}_n[x]$.
2. Let R be a commutative ring that is *not* a field. Show that not all R-modules are free, i.e. find a counter-example [Hint: Look back at the examples given in section 12.1]
3. (More challenging) Let R be any ring (not necessarily commutative). Show that if any left (or right) R-module is free, then R is a divison ring.

4. Show that $(x, y) \subseteq \mathbb{C}[x, y]$ is not a free $\mathbb{C}[x, y]$-submodule.
5. Show that any uncountable set of $\mathbb{C}[x]$ is linearly dependent.
6. Let $R = k[x_1, ..., x_n]$ and $I = (x_1, ..., x_n)$, and let $m \geq 0$. Show that the ideal I^m is the k-subspace of R spanned by the monomials $x_1^{r_1} \cdots x_n^{r_n}$ of total degree $r_1 + \cdots + r_n \geq m$, and that the classes of the monomials of total degree exactly m form a k-basis of the quotient I^m / I^{m+1}.

13.2 Linear Transformations and Matrix Representation

As mentioned at the beginning of the chapter, k-module homomorphisms are called linear transformation in the theory of vector-spaces. In this section, we will show how every linear transformation between finite dimensional vector-spaces can be represented as a matrix. Since all vector-spaces are free with an invariant basis number, when defining a linear transformation we only need to be concerned with where the basis get's mapped to. If $\varphi : V \to W$, where V and W are finite dimensional vector-spaces over k, and $\varphi \in \mathrm{Hom}_k(V, W)$. Let $\beta_V = \{v_1, v_2, ..., v_n\}$ and $\beta_W = \{w_1, w_2, ..., w_m\}$ be (ordered) bases for V and W respectively. Then we are only concerned where the v_i's map to, that is, what $\varphi(v_j) = w_j$ is. Since they map into the vector-space W, $w_j = \sum_{i=1}^{m} b_{ij} w_i$, $b_{ij} \in k$,

$$\varphi(v_j) = \sum_{i=1}^{m} b_{ij} w_i$$

Let $M_{\beta_V}^{\beta_W}(\varphi)$ be the $m \times n$ matrix whose ij entry is b_{ij} (i.e. the coefficients of w_i given v_j). This matrix is given a name:

Definition 13.2.1: Matrix Representation

Let $\varphi : V \to W$ be a linear transformation between two finite dimensional vector spaces with dimension n and M and basis β_V and β_W respecitvely. Then the *matrix representation* $M_{\beta_V}^{\beta_W}$ of φ (also written as $M_{\beta_V}^{\beta_W}(\varphi)$) is

$$\begin{pmatrix} a_{11} & a_{12} & \cdots & a_{1n} \\ a_{21} & a_{22} & \cdots & a_{2n} \\ \vdots & \vdots & \ddots & \vdots \\ a_{m1} & a_{m2} & \cdots & a_{mn} \end{pmatrix}$$

where each entry ij is the coefficient of the ith basis element of β_W in the linear combination of where the element v_j maps.
If a matrix A is a matrix representation of a linear transformation φ, we say that A *represents* φ *with respect to the basis* β_V, β_W. Similarly, φ would be the linear transformation represented by A with respect to the bases β_V, β_W.

With the matrix representation of φ, we can re-write $\varphi(v) = w$ as

$$\begin{pmatrix} c_{11} & c_{12} & \cdots & c_{1n} \\ c_{21} & c_{22} & \cdots & c_{2n} \\ \vdots & \vdots & \ddots & \vdots \\ c_{m1} & c_{m2} & \cdots & c_{mn} \end{pmatrix} \begin{pmatrix} a_1 \\ a_2 \\ \vdots \\ a_n \end{pmatrix} = \begin{pmatrix} b_1 \\ b_2 \\ \vdots \\ b_m \end{pmatrix} \tag{13.3}$$

where $v = \sum_{i=1}^{n} a_i v_i$ and $\varphi(v) = \sum_{i=1}^{m} b_i w_i$. Sometimes, the following notation is used as a shorthand for (13.3): $[\varphi(v)]_{\beta_W} = M_{\beta_V}^{\beta_W} [v]_{\beta_V}$.

Example 13.2.2: Matrix Representation

1. Let $V = \mathbb{R}^3$, $W = \mathbb{R}^2$, and take $\beta_V = \{(1,0,0),(0,1,0),(0,0,1)\}$ and $\beta_W = \{(1,0),(0,1)\}$ (i.e., the standard basis for $\mathbb{R}^3$ and $\mathbb{R}^2$). Let

   $$\varphi(x,y,z) = (4x + 2z, x - y + 5z)$$

   Then $\varphi(1,0,0) = (4,1)$, $\varphi(0,1,0) = (0,-1)$, and $\varphi(0,0,1) = (2,5)$. Thus, the matrix representation of φ with respect to β_V and β_W is

   $$\begin{pmatrix} 4 & 0 & 2 \\ 1 & -1 & 5 \end{pmatrix}$$

Theorem 13.2.3: Matrix Representation Correspondence

Let V and W be a finite dimensional vector space over F with dimension n and m, as well as basis β_V and β_W respectively. Then the map $\Psi : \text{Hom}_F(V,W) \to M_{mn}(F)$, where $\varphi \mapsto M_{\beta_V}^{\beta_W}(\varphi)$ is a [vector-space] isomorphism.

Note that the operation on $\text{Hom}_F(V,W)$ if point-wise function addition and $M_{mn}(F)$ is matrix addition.

***Proof*:**

To show Ψ is F-linear, it comes down to the fact that every $\varphi \in \text{Hom}_F(V,W)$ is F-linear. Since every column of $M_{\beta_V}^{\beta_W}$ represents $\varphi(v_i)$, and $(\varphi + \psi)(v) = \varphi(v) + \psi(v)$, then we get that the map Ψ is also F-linear.

The map Ψ is surjective, since given a matrix $A \in M_{mn}(F)$, the map φ that maps to it can be defined by reversing the process that was done in equation (13.3). This map is injective since if $A = B$, then $A = M_{\beta_V}^{\beta_W}(\varphi) = M_{\beta_V}^{\beta_W}(\psi) = B$. Since a basis uniquely defines a linear transformation and both representations are with respect to the same bases, it must be that $\varphi = \psi$, proving injectivity.

Thus, Ψ is an isomorphism, as we sought to show.

13.2.4 Note Different choices of bases produces different isomorphisms. There is no "natural choice" in the same way that there is no natural choice for a basis for a vector-space

Corollary 13.2.5: Dimension Of $\mathrm{Hom}_F(V,W)$

The dimension of $\mathrm{Hom}_F(V,W)$ is $\dim(V)\cdot\dim(W)$

***Proof*:**
Since $\mathrm{Hom}_F(V,W)$ is isomorphic to $M_{mn}(F)$, and $\dim(M_{mn}(F)) = mn$, then $\dim(\mathrm{Hom}_F(V,W)) = mn = \dim(V)\cdot\dim(W)$

We have shown that function addition is compatible with matrix addition. When it comes to function composition, the story becomes a little trickier, since we need the co-domain of one function to line-up with the domain of the next. Thus, to that end, let U, V, W be finite dimensional vector-spaces with dimension k, n, m and bases $\beta_U = \{u_1, u_2, ..., u_k\}$, $\beta_V = \{v_1, v_2, ..., v_n\}$, and $\beta_W = \{w_1, w_2, ..., w_m\}$ respectively. Let $\varphi : U \to V$ and $\psi : V \to W$ be two linear transformations. Their composition $\psi \circ \varphi$ is a linear fransformation from U to W, and so there exists a representation $M_{\beta_U}^{\beta_W}(\psi \circ \varphi)$ given by

$$(\psi \circ \varphi)(u_j) = \sum_{i=1}^{m} c_{ij} w_i \qquad c_{ij} \in F$$

Since φ and ψ are linear transfomation, they too have a matrix representation:

$$\varphi(u_j) = \sum_{p=1}^{n} a_{pj} v_p \qquad \psi(v_p) = \sum_{i=1}^{m} b_{ip} w_i$$

from this, we can find c_{ij} in terms of the coefficients a_{pj} and b_{ip}:

$$\begin{aligned}
(\psi \circ \varphi)(u_j) &= \psi\left(\sum_{p=1}^{n} a_{pj} v_p\right) \\
&= \sum_{p=1}^{n} a_{pj} \psi(v_p) \\
&= \sum_{p=1}^{n} a_{pj} \sum_{i=1}^{m} b_{ip} w_i \\
&= \sum_{p=1}^{n} \sum_{i=1}^{m} a_{pj} b_{ip} w_i \\
&= \sum_{i=1}^{m} \sum_{p=1}^{n} a_{pj} b_{ip} w_i
\end{aligned}$$

Thus, if we let $c_{ij} = \sum_{p=1}^{n} a_{pj} b_{ip}$, we get

$$= \sum_{i=1}^{m} c_{ij} w_i$$

Take a moment to look over this and think about how this would be represented as multiplying the matrix $M_{\beta_U}^{\beta} V(\varphi)$ and $M_{\beta_V}^{\beta_W}(\psi)$. In fact, the coefficents of $M_{\beta_U}^{\beta_W}(\psi \circ \varphi)$ are exactly what you get by multiplying the other two matrices! This is summed up in the following theorem:

Theorem 13.2.6: Matrix Representation And Composition

Let U, V, W be finite dimensional vector-spaces with bases β_U, β_V, β_W, of size k, m, n respectively. Let $\varphi : U \to V$ and $\psi : V \to W$ be two linear transformations. Then

$$M_{\beta_U}^{\beta_W}(\psi \circ \varphi) = M_{\beta_V}^{\beta_W}(\psi) M_{\beta_U}^{\beta_V}(\varphi)$$

Another way of seeing this theorem is by saying the following diagram commutes:

$$\begin{array}{ccc} M_{mp}(F) \times M_{mp}(F) & \longrightarrow & M_{mn}(F) \\ \downarrow & & \downarrow \\ \mathrm{Hom}_F(F^p, F^m) \times \mathrm{Hom}_F(R^p, R^m) & \longrightarrow & \mathrm{Hom}_F(F^n, F^m) \end{array}$$

Corollary 13.2.7: Matrix Multiplication Properties

Let $M_{mn}(F)$ be the set of $m \times n$ matrices over F. Then given appropriate matrices, matrix multiplication is associative and distributive

Note how this is different from the associativity and distributivity of $GL_n(F)$. Namely, all the matrices of $GL_n(F)$ are square matrices. We have not yet proven that non-square matrices are associative and distributive, particularly because they do not always line up properly, and their result can pass from one set of matrices to another (for example $A \in M_{ab}(F)$, $B \in M_{bc}(F)$, $AB \in M_{ac}(F)$)

***Proof*:**
Distributivity follows by the same technique as associativity, which is proved here. Let A, B, C be matrices such that $(AB)C$ and $A(BC)$ are defined. By theorem 13.2.6, (AB) represents $S \circ T$ for appropriate linear transformations S, T. Multiplying on the right side by C, $(AB)C$, the resulting matrix represents $(S \circ T) \circ R$ for appropriate R. Similarly, $A(BC)$ is represented by $S \circ (T \circ R)$. Since the composition of functions is associative,

$$\Psi((AB)C) = (S \circ T) \circ R = S \circ (T \circ R) = \Psi(A(BC))$$

and since Ψ is injective, $(AB)C = A(BC)$.

Corollary 13.2.8: Matrix Representation Isomorphisms

1. If β is a basis of the n-dimensional vector space V, the map $\varphi \mapsto M_\beta^\beta(\varphi)$ is a ring isomorphism and a vector-space isomorphism of $\mathrm{Hom}_F(V, V)$ (i.e. $\mathrm{End}(V)$) onto $M_n(F)$:

$$\mathrm{End}(V) \cong_{\mathbf{Ring}} M_n(F) \qquad \mathrm{End}(V) \cong_{F\text{-}\mathbf{Vect}} M_n(F)$$

2. If we restrict to automorphisms, then $\mathrm{Aut}(V) \cong GL_n(F)$ as groups[a]. In particular

$$\mathrm{Aut}_{\mathbf{Vect}}(V) \cong_{\mathbf{Grp}} GL_n(F)$$

[a] $\mathrm{Aut}(V)$ is not a ring

***Proof*:**
In both cases, we have already shown that it is isomorphic as F-vector-spaces, so we will show they are isomorphic as rings

(1) Using corollary 13.2.7, we see that $M_n(F)$ is a ring (since multiplying two $n \times n$ matrices get's us an $n \times n$ matrix). We have shown this map is bijective in theorem 13.2.3. Theorem 13.2.6 shows that this map also preserves the ring structure of $\text{End}(V)$, showing that the map is a ring-isomorphism.

(2) The units of $\text{End}(V)$ are the automorphisms of V, and the units of $M_n(F)$ form $GL_n(F)$. A ring isomorphism maps units bijectively onto units, since it preserves products and the identity, and so does its inverse. So the isomorphism of (1) restricts to a bijection $\text{Aut}(V) \to GL_n(F)$ that preserves products, a group isomorphism.

Finally, we convert the powerful result of corollary 13.1.20 into for matrices, in particular we showed that if f is injective between two finite dimensional vector space of the same dimension, then it is surjective. This result is important enough that the matrix representation of such an f should be given a name

Definition 13.2.9: Nonsingular Matrix

An $m \times n$ matrix A is called *nonsingular* if $Ax = 0$ with $x \in F^n$ implies $x = 0$

The paragraph after definition 13.1.19 explains the name.

Proposition 13.2.10: Nonsingular Square Matrix

Let A be an $n \times n$ matrix. Then A is invertible if and only if A is nonsingular

***Proof*:**
If A is invertible and $Ax = 0$, then $x = A^{-1}(Ax) = A^{-1}0 = 0$, so A is nonsingular.

Conversely, let A be nonsingular. Then A represents some linear transformation $\varphi : V \to V$ for some finite dimensional vector-space V with respect to basis β and γ for the domain and codomain. Since $\varphi(x) = 0$ if and only if $x = 0$, then φ is injective, and so by corollary 13.1.20, φ is an isomorphism. Thus, there exists a linear transfomration φ^{-1} such that $\varphi^{-1} \circ \varphi = \text{id}$. By using theorem 13.2.3, let B be the representation of φ^{-1} with respect to γ and β. Using theorem 13.2.6 we have

$$AB = M_\beta^\gamma(\varphi)M_\gamma^\beta(\varphi^{-1}) = M_\gamma^\gamma(\varphi \circ \varphi^{-1}) = M_\gamma^\gamma(I) = I$$

thus $AB = I$. similarly $BA = I$. Thus, $B = A^{-1}$, as we sought to show.

Exercise 13.2.1

1. We know that in general, if R is a ring and $x \in R$ is not a unit, that does not imply that x is a zero-divisor (ex. take the integers). Show that for the matrix ring $M_n(k)$, if $A \in M_n(k)$ is not a unit, then A is a zero-divisor.

2. Show that a polynomial of degree at most n over a subfield of $\mathbb{C}$ is uniquely determined by its values at $n+1$ distinct points (You may freely use the fact that a polynomial of degree n can be broken down into a product of n linear terms).

3. (If you know some complex arithmetics) Let $f : \mathbb{C} \to \mathbb{C}$ be a $\mathbb{C}$-linear function. Recall that $\mathbb{C}$ is a 2 dimensional $\mathbb{R}$-vector space, and so f may be represented as a real matrix. Show that if $f(z) = \alpha z = (a + bi)z$, then the matrix representation of f in the basis $(1, i)$ will be of the form:
$$[f] = \begin{pmatrix} a & -b \\ b & a \end{pmatrix}$$

13.2.1 Change of Basis

While representing vectors in a vector space in terms of coordinates simplifies their representation, and linear transformations and their compositions can be seen as matrices and matrix multiplication, we are *always* dependent on a choice of basis (i.e. a choice of isomorphism $\varphi : k^n \to V$). As pointed out earlier, there is no "canonical" choice for a basis: there are many choices of bases which will produce isomorphic vector spaces[9]. Thus, in this section we will explore how to change from one basis to another to be able to compare representations. We will be working with vector-spaces, but we will only be using properties of free-modules meaning the theory is true for free-modules in general.

Let V be an F-vector space of dimension n. Let β_A and β_B be two basis for V, meaning we have the two isomorphissm
$$F^{\oplus \beta_A} \xrightarrow{\varphi} V \qquad F^{\oplus \beta_B} \xrightarrow{\psi} V$$

Then we will get the following isomorphism:
$$F^{\oplus \beta_A} \xrightarrow{\psi^{-1} \circ \varphi} F^{\oplus \beta_B}$$

Then by theorem 13.2.3, there is a matrix $N_{\beta_A}^{\beta_B}$ that corresponds to $(\psi^{-1} \circ \varphi)$. In particular, the jth column of $N_{\beta_A}^{\beta_B}$ is the image of the jth element of A viewed as a column vector in $f^{\oplus \beta_B}$.
If $\beta_A = (a_1, a_2, ..., a_n)$ and $\beta_B = (b_1, b_2, ..., b_n)$ then
$$(\psi^{-1} \circ \varphi)(a_j) = \sum_{i=1}^{n} n_{ij} b_i$$

We give this matrix a name:

Definition 13.2.11: Change Of Basis

Let V be a F-vector space of dimension n, and let β_A and β_B be two bases corresponding to the isomorphisms φ and ψ. Then the *change of basis matrix* is the matrix representation of $(\psi^{-1} \circ \varphi)$.
We can represent this matrix as $N_{\beta_A}^{\beta_B}$ or $N_{\beta_A}^{\beta_B}(V)$

[9] There are ways to make it "canonical" by augmenting the vector-space to have further structure which may naturally induce a basis (for example, an inner product). For such examples, see *Linear Algebra* [31].

Corollary 13.2.12: Properties Of Change Of Basis

Let β_A, β_B and β_C be bases of an n-dimensional vector space V. Then

1. $N_{\beta_A}^{\beta_B}$ is invertible and $(N_{\beta_A}^{\beta_B})^{-1} = N_{\beta_B}^{\beta_A}$
2. $N_{\beta_B}^{\beta_C} N_{\beta_A}^{\beta_B} = N_{\beta_A}^{\beta_C}$

***Proof*:**
For a basis β of V let $\varphi_\beta \colon F^n \to V$ be the isomorphism sending the jth standard basis vector e_j to the jth element of β. By definition 13.2.11, N_β^γ is the matrix of $\varphi_\gamma^{-1} \circ \varphi_\beta \colon F^n \to F^n$ with respect to the standard basis $e = (e_1, \ldots, e_n)$ in domain and codomain, and the matrix of the identity map in this basis is I_n, since $\mathrm{id}(e_j) = e_j$ (definition 13.2.1).

1. By theorem 13.2.6,

$$N_{\beta_A}^{\beta_B} N_{\beta_B}^{\beta_A} = M_e^e\left((\varphi_{\beta_B}^{-1} \circ \varphi_{\beta_A}) \circ (\varphi_{\beta_A}^{-1} \circ \varphi_{\beta_B})\right) = M_e^e(\mathrm{id}) = I_n$$

$$N_{\beta_B}^{\beta_A} N_{\beta_A}^{\beta_B} = M_e^e\left((\varphi_{\beta_A}^{-1} \circ \varphi_{\beta_B}) \circ (\varphi_{\beta_B}^{-1} \circ \varphi_{\beta_A})\right) = M_e^e(\mathrm{id}) = I_n$$


   Hence $N_{\beta_A}^{\beta_B}$ is invertible with inverse $N_{\beta_B}^{\beta_A}$.

2. By theorem 13.2.6,

$$N_{\beta_B}^{\beta_C} N_{\beta_A}^{\beta_B} = M_e^e\left((\varphi_{\beta_C}^{-1} \circ \varphi_{\beta_B}) \circ (\varphi_{\beta_B}^{-1} \circ \varphi_{\beta_A})\right) = M_e^e(\varphi_{\beta_C}^{-1} \circ \varphi_{\beta_A}) = N_{\beta_A}^{\beta_C}$$

   as claimed.

With the change of basis for a vector space taken care of, we know check how to perform a change of basis for a matrix representation of a linear transformation. The idea behind this comes down to the following visual:



Let N_A^B be the matrix representation of $\varphi_2^{-1} \circ \varphi_1$ and M_C^D be the matrix representation of $\psi_2^{-1} \circ \psi_1$. If we choose the basis β_A for V and β_C for W, then we have:

$$\varphi_2^{-1} \circ \alpha \circ \varphi_1 : F^{\oplus\beta_A} \to F^{\oplus\beta_C} \tag{13.4}$$

Let P be the matrix representation of $\varphi_2^{-1} \circ \alpha \circ \varphi_1$. If we choose the basis β_B for V and β_D for W, then we have:

$$\psi_2^{-1} \circ \alpha \circ \psi_1 : F^{\oplus\beta_B} \to F^{\oplus\beta_D} \tag{13.5}$$

now with some manipulation, we can transform equation (13.5) into equation (13.4) like so

$$\psi_2^{-1} \circ \alpha \circ \psi_1 = (\mu_{\beta_C}^{\beta_D} \circ \varphi_2^{-1}) \circ \alpha \circ (\varphi_1 \circ (\nu_{\beta_A}^{\beta_B})^{-1}) = \mu_{\beta_C}^{\beta_D} \circ (\varphi_2^{-1} \circ \alpha \circ \varphi_1) \circ (\nu_{\beta_A}^{\beta_B})^{-1}$$

And using the matrix correspondence, this is equivalent to

$$M_{\beta_C}^{\beta_D} P (N_{\beta_A}^{\beta_B})^{-1} = M_{\beta_C}^{\beta_D} P N_{\beta_B}^{\beta_A} = Q$$

This should be able to be read quite intuitively: $N_{\beta_B}^{\beta_A}$ converts our vector represented by a linear combination of vectors in β_B into linear combination of vectors in β_A, then P transforms the result and outputs it as a linear combination of vectors in β_C, and finally $M_{\beta_C}^{\beta_D}$ converst the result into a linear representation of vectors in β_D. W

We sum up these results into a proposition:

Proposition 13.2.13: Change Of Basis For Linear Transformation

Let $\varphi : V \to W$ be a linear transformation from two finite dimensional vector spaces, and let P be the matrix representation of φ with respect to bassi β_A and β_C for V and W respectively. Then the matrix representing linear transformation φ with respect to basis β_B and β_D is

$$M_{\beta_C}^{\beta_D} P N_{\beta_B}^{\beta_A}$$

with the notation given above.

More generally, if M and N are any invertible matrix, they represent a change of basis, so MPN would be a change of basis (given the appropriate dimensions).

Definition 13.2.14: Equivalence

Let R be a commutative ring and $P, Q \in M_{m,n}(R)$ be $m \times n$ matrices over R. Then P and Q are *equivalent* if there exist invertible matrices $M \in M_m(R)$ and $N \in M_n(R)$ such that

$$Q = MPN$$

Read through bases, this says that P and Q represent the same homomorphism between free R-modules of ranks n and m, with respect to two choices of bases of the domain and of the codomain.

Products of matrices over a commutative ring R are associative, $(AB)C = A(BC)$, since by distributivity and associativity in R the (i,j) entry of both sides is $\sum_{k,l} a_{ik} b_{kl} c_{lj}$. With this, equivalence of matrices is an equivalence relation on $M_{m,n}(R)$. It is reflexive, since $P = I_m P I_n$. It is symmetric, since $Q = MPN$ gives $P = M^{-1} Q N^{-1}$. It is transitive, since $Q = MPN$ and $S = M'QN'$ give $S = (M'M)P(NN')$, where $M'M$ and NN' are invertible with inverses $M^{-1}M'^{-1}$ and $N'^{-1}N^{-1}$.

For the reading through bases, let φ: $R^n \to R^m$ be $x \mapsto Px$, so that P is the matrix of φ in the standard bases, and let M and N be invertible. The columns $\beta_j = Ne_j$ of N form a basis of R^n: they span, since $x = N(N^{-1}x) = \sum_j (N^{-1}x)_j \beta_j$, and they are linearly independent, since $\sum_j c_j \beta_j = Nc = 0$ forces $c = N^{-1}Nc = 0$. Applied to the invertible matrix M^{-1}, the same two

computations show that its columns $\gamma_i = M^{-1}e_i$ form a basis of R^m, and

$$\varphi(\beta_j) = PNe_j = M^{-1}(MPN)e_j = \sum_{i=1}^{m}(MPN)_{ij}\gamma_i$$

so MPN is the matrix of φ with respect to the bases (β_j) and (γ_i). Conversely, let Q be the matrix of φ with respect to bases (β_j) of R^n and (γ_i) of R^m, and let N and C be the matrices whose columns are the β_j and the γ_i. Comparing $\varphi(\beta_j) = PNe_j$ with $\varphi(\beta_j) = \sum_i Q_{ij}\gamma_i = CQe_j$ gives $PN = CQ$. A matrix $B \in M_r(R)$ whose columns $b_1, \dots, b_r$ form a basis of R^r is invertible: writing $e_k = \sum_i b'_{ik}b_i$ defines $B' = (b'_{ik})$ with $BB' = I_r$, so $B(B'B - I_r) = 0$, and $B'B = I_r$ because the columns of B are linearly independent. Applied to N and to C, this shows that both are invertible, and $Q = C^{-1}PN$ is equivalent to P. Thus there is an entire equivalence class of matrices representing a linear transformation, where any representative of the equivalence class equates to a choice of basis for the domain and codomain. This brings up an interesting question: is there a particular representative (i.e. choices of bases for P, Q) that will make it "easier" to see what the linear transformation is doing? This is a very interesting question, and in the next section shall be explored to great success, in particular, all linear transformation can be represented in "reduced form" and which can be algorithmically found.

13.2.2 Similarity

Before proceeding, there is one more important concept that must be covered, namely the special case where $V = W$ is the same vector-space:

$$\mathrm{Hom}_R(V, V) = \mathrm{End}_R(V)$$

that is, we shall look at linear transformations from V to itself. Such endomorphisms are in fact extremely common. They can be thought of as representing the "change in state" of a system. As the reader may surmise, this means they have applications all other the physical science, however they shall amply show up in pure mathematics. In fact, chapter 14 is essentially the theoretical build-up for studying such functions.

In this subsection R is a commutative ring, and the main case is a field $R = k$.

We shall simply start by asserting that the vector-space V in $\mathrm{Hom}_R(V, V)$ shall be considered to be the exact same space, not two isomorphic copies of these spaces as generally is considered. In this situation, an element $\alpha \in \mathrm{Hom}_R(V, V) = \mathrm{End}_R(V)$ is usually called a *linear operator* to emphasize the fact that the domain and codomain are "identical". With this in mind, there are new questions that could be asked, such as if there exists $v \in V$ such that $\alpha(v) = \lambda v$ for some $\lambda \in R$, or if a subspace $W \subseteq V$ maps into itself.

Another important consequence of identifying the domain and codomain is that when choosing a basis, the *same* basis must be chosen for both of them (as α is considered to be mapping V to itself). This means that there is a more specific notion of equivalence as only one matrix is chosen:

Definition 13.2.15: Similarity

Let R be a commutative ring. Two matrices $A, B \in M_n(R)$ are *similar*, written $A \sim B$, if $B = PAP^{-1}$ for some $P \in \mathrm{GL}_n(R)$. Two endomorphisms α, β of an R-module M are *similar*, written $\alpha \sim \beta$, if $\beta = \varphi \circ \alpha \circ \varphi^{-1}$ for some automorphism φ of M.

The two notions match through matrix representations, and both are equivalence relations:

Lemma 13.2.16: Similarity Of Matrices And Operators

Let R be a commutative ring and let M be a free R-module with a basis $\beta = (b_1, \ldots, b_n)$. For $\alpha \in \mathrm{End}_R(M)$ let $[\alpha]_\beta \in M_n(R)$ be its matrix, defined by $\alpha(b_j) = \sum_i ([\alpha]_\beta)_{ij} b_i$.

1. Similarity is an equivalence relation on $M_n(R)$ and on $\mathrm{End}_R(M)$.
2. $[\alpha \circ \alpha']_\beta = [\alpha]_\beta [\alpha']_\beta$ for $\alpha, \alpha' \in \mathrm{End}_R(M)$, and $[\mathrm{id}_M]_\beta = I_n$. In particular, if α is an automorphism, then $[\alpha]_\beta$ is invertible with inverse $[\alpha^{-1}]_\beta$.
3. For $\alpha, \alpha' \in \mathrm{End}_R(M)$, $\alpha \sim \alpha'$ if and only if $[\alpha]_\beta \sim [\alpha']_\beta$.
4. If γ is another basis of M with n elements, then $[\alpha]_\gamma \sim [\alpha]_\beta$. Conversely, every matrix similar to $[\alpha]_\beta$ is $[\alpha]_\gamma$ for some basis γ of M with n elements.

***Proof*:**
Matrix multiplication over R is associative (see the discussion after definition 13.2.14), and an endomorphism of M is determined by its values on the basis β, hence by its matrix, while every matrix is the matrix of some endomorphism (corollary 12.3.14).

1. For matrices, $A = I_n A I_n^{-1}$. If $B = PAP^{-1}$, then $A = P^{-1}B(P^{-1})^{-1}$. If $B = PAP^{-1}$ and $C = QBQ^{-1}$, then $C = (QP)A(QP)^{-1}$, where $(QP)^{-1} = P^{-1}Q^{-1}$. The same three computations, with composition in place of multiplication and automorphisms in place of invertible matrices, prove the claim for endomorphisms.
2. Write $A = [\alpha]_\beta$ and $A' = [\alpha']_\beta$. Since R is commutative,
$$(\alpha \circ \alpha')(b_j) = \alpha\Big(\sum_l a'_{lj} b_l\Big) = \sum_l a'_{lj} \sum_i a_{il} b_i = \sum_i (AA')_{ij} b_i$$
and $\mathrm{id}_M(b_j) = b_j$ gives $[\mathrm{id}_M]_\beta = I_n$. If α is an automorphism, then $[\alpha]_\beta [\alpha^{-1}]_\beta = [\alpha \circ \alpha^{-1}]_\beta = I_n$, and in the same way $[\alpha^{-1}]_\beta [\alpha]_\beta = I_n$.
3. If $\alpha' = \varphi \circ \alpha \circ \varphi^{-1}$, then $[\alpha']_\beta = [\varphi]_\beta [\alpha]_\beta [\varphi]_\beta^{-1}$ by (2). Conversely, let $[\alpha']_\beta = P[\alpha]_\beta P^{-1}$ with P invertible, and let φ and ψ be the endomorphisms with $[\varphi]_\beta = P$ and $[\psi]_\beta = P^{-1}$. By (2), $[\varphi \circ \psi]_\beta = [\psi \circ \varphi]_\beta = I_n = [\mathrm{id}_M]_\beta$, so $\varphi \circ \psi = \psi \circ \varphi = \mathrm{id}_M$, and φ is an automorphism with inverse ψ. Then $[\varphi \circ \alpha \circ \varphi^{-1}]_\beta = P[\alpha]_\beta P^{-1} = [\alpha']_\beta$, so $\alpha' = \varphi \circ \alpha \circ \varphi^{-1}$.
4. Let $\gamma = (c_1, \ldots, c_n)$, write $c_j = \sum_i n_{ij} b_i$ and $b_j = \sum_i n'_{ij} c_i$, and let $N = (n_{ij})$ and $N' = (n'_{ij})$. Then $b_j = \sum_i n'_{ij} \sum_l n_{li} b_l = \sum_l (NN')_{lj} b_l$, so $NN' = I_n$ by the uniqueness of coordinates in the basis β, and in the same way $N'N = I_n$. With $A = [\alpha]_\beta$ and $B = [\alpha]_\gamma$,
$$\alpha(c_j) = \sum_l n_{lj} \alpha(b_l) = \sum_i (AN)_{ij} b_i \qquad \alpha(c_j) = \sum_k b_{kj} c_k = \sum_i (NB)_{ij} b_i$$
so $AN = NB$ and $B = N^{-1}AN$, which is similar to A. Conversely, let $B = PAP^{-1}$ with P invertible, put $N = P^{-1} = (n_{ij})$ and $c_j = \sum_i n_{ij} b_i$. The c_j span M, since $\sum_i p_{ij} c_i = \sum_l (NP)_{lj} b_l = b_j$, and they are linearly independent, since $\sum_j x_j c_j = \sum_l (Nx)_l b_l = 0$ forces $Nx = 0$ and then $x = PNx = 0$. So $\gamma = (c_1, \ldots, c_n)$ is a basis, and the computation above gives $[\alpha]_\gamma = N^{-1}AN = PAP^{-1} = B$, completing the proof.

In the language of group theory, $\mathrm{GL}_n(R)$ acts on $M_n(R)$ by conjugation[10], and $A \sim B$ if and only if A and B lie in the same orbit of this action.

Just like for equivalence, we may ask for when two matrices are similar, or if there is a nice representation in the orbit. This question is a bit trickier because the domain and codomain have are the same, and so there is less flexibility in choosing representatives. Chapter 14 finds a basis giving a nice representation of α.

13.2.3 Gaussian Elimination: Finding a Nice Basis

Let $\varphi : V \to W$ be a linear transformation, and P be some matrix representation given by choosing a basis for V and W. Then P belongs to some equivalence class representing all possible representatives of φ. If we multiply P on the left or right by an invertible matrix, then by by proposition 13.2.13, P remains in the same equivalence class. It would thus be nice if given P, we may simplify P as much as possible to get an "nice" looking represetnative for φ. To do this, we will find nice sets of invertible matrices that do "elementary" operations to a marix which will allow the matrix P to be put in as simple a form as possible. In particular, we will find invertible matrice that will allow us to perfom the following "elementary" operations:

1. switching two rows (resp. columns) or P. For example, let's say we want to switch the 1st and 2nd row of a matrix. This can be done by multiplying on the left (resp. right) by:

$$\begin{pmatrix} 0 & 1 & 0 \\ 1 & 0 & 0 \\ 0 & 0 & 1 \end{pmatrix}$$

   and the identity on the right (resp. left). In particular, we swapped the rows of the above matrix.

2. multiply all elements in a row (resp. column) of P by a unit of R by multiplying on the left (resp. right) by a matrix of the form:

$$\begin{pmatrix} u & 0 & 0 \\ 0 & 1 & 0 \\ 0 & 0 & 1 \end{pmatrix}$$

   This particular matrix will scale the first row (resp. column) by a factor of u when multiplying on the left (resp. right).

3. add a multiple of one row (resp. column) to another row (resp. column) of P. For example, to add a multiple of the second row to the first, we would multiply on the left by:

$$\begin{pmatrix} 1 & 3 & 0 \\ 0 & 1 & 0 \\ 0 & 0 & 1 \end{pmatrix}$$

   This particular matrix will add 3 copies of the 2nd row to the 1st row when multiplying on the left, and 3 copies of the 1st column to the 2nd column when multiplying on the right.

[10] Recall that conjugation is *the* natural group-action

Over any commutative ring R, these matrices are invertible, and multiplying by one of them on the left acts on rows while multiplying on the right acts on columns:

Proposition 13.2.17: Equivalence And Elementary Matrices

Let R be a commutative ring and $P, Q \in M_{m,n}(R)$. The *elementary row operations* are interchanging two rows, multiplying a row by a unit of R, and adding r times one row to a different row, for some $r \in R$. The *elementary column operations* are defined in the same way with columns. For $1 \leq k, l \leq m$ let $E_{kl} \in M_m(R)$ be the matrix with 1 in position (k, l) and 0 elsewhere, and for $k \neq l$, a unit u and $r \in R$ put

$$S_{kl} = I_m - E_{kk} - E_{ll} + E_{kl} + E_{lk} \qquad D_k(u) = I_m + (u-1)E_{kk} \qquad T_{kl}(r) = I_m + rE_{kl}$$

The matrices of the same names in $M_n(R)$ are defined in the same way with n in place of m.

1. For $X \in M_{m,n}(R)$, the matrices $S_{kl}X$, $D_k(u)X$ and $T_{kl}(r)X$ are X with rows k and l interchanged, with row k multiplied by u, and with r times row l added to row k. The matrices XS_{kl}, $XD_k(u)$ and $XT_{kl}(r)$ are X with columns k and l interchanged, with column k multiplied by u, and with r times column k added to column l.
2. These matrices are invertible:

$$S_{kl}S_{kl} = I \qquad D_k(u)D_k(u^{-1}) = D_k(u^{-1})D_k(u) = I$$

$$T_{kl}(r)T_{kl}(-r) = T_{kl}(-r)T_{kl}(r) = I$$

3. If Q is obtained from P by a finite sequence of elementary row and column operations, then P and Q are equivalent (definition 13.2.14).

***Proof*:**

1. For $X \in M_{m,n}(R)$, the kth row of $E_{kl}X$ is the lth row of X, and its other rows are 0. So $S_{kl}X = X - E_{kk}X - E_{ll}X + E_{kl}X + E_{lk}X$ is X with rows k and l first replaced by 0 and then by the rows l and k of X, $D_k(u)X = X + (u-1)E_{kk}X$ is X with row k replaced by u times itself, and $T_{kl}(r)X = X + rE_{kl}X$ is X with r times row l added to row k. For the matrices $E_{kl} \in M_n(R)$, the lth column of XE_{kl} is the kth column of X and its other columns are 0, and the same expansions show that XS_{kl}, $XD_k(u)$ and $XT_{kl}(r)$ are X with columns k and l interchanged, with column k multiplied by u, and with r times column k added to column l.
2. By (1), $S_{kl}S_{kl}$ is S_{kl} with rows k and l interchanged, which is the identity matrix, and $D_k(u)D_k(u^{-1})$ is $D_k(u^{-1})$ with row k multiplied by u, which is the identity matrix, and in the same way $D_k(u^{-1})D_k(u) = I$. Since $E_{kl}E_{kl} = 0$ for $k \neq l$, $T_{kl}(r)T_{kl}(-r) = I - r^2E_{kl}E_{kl} = I$, and in the same way $T_{kl}(-r)T_{kl}(r) = I$.
3. By (1) and (2), every elementary row operation is left multiplication by an invertible matrix in $M_m(R)$, and every elementary column operation is right multiplication by an invertible matrix in $M_n(R)$. If Q is obtained from P by a finite sequence of these operations, associativity of matrix multiplication (see the discussion after definition 13.2.14) lets the left factors and the right factors be collected separately, so $Q = E_s \cdots E_1 P F_1 \cdots F_t$ with

invertible $E_i \in M_m(R)$ and $F_j \in M_n(R)$. The products $M = E_s \cdots E_1$ and $N = F_1 \cdots F_t$ are invertible, with inverses $E_1^{-1} \cdots E_s^{-1}$ and $F_t^{-1} \cdots F_1^{-1}$, and $Q = MPN$. Hence P and Q are equivalent, as claimed.

Due to these matrices being the transition matrices between two equivalent matrices, we give matrices that perform elementary operations a name:

Definition 13.2.18: Elementary Matrices

The matrices S_{kl}, $D_k(u)$ and $T_{kl}(r)$ of proposition 13.2.17 are called *elementary matrices*. By proposition 13.2.17(1), multiplying a matrix by an elementary matrix on the left performs an elementary row operation, and on the right an elementary column operation. By proposition 13.2.17(2), the inverse of an elementary matrix is again an elementary matrix: $S_{kl}^{-1} = S_{kl}$, $D_k(u)^{-1} = D_k(u^{-1})$ and $T_{kl}(r)^{-1} = T_{kl}(-r)$.

Notice that proposition 13.2.17(3) is not an "if and only if", only an "if". This is because it is possible that P and Q are equivalent, but the invertible matrices that "connects" the two are not the product of elementary matrices. If R has certain extra properties, then it will be the case that all invertible matrices can be written as a product of elementary matrices, as explored below. The invertible matrices are given a name

Definition 13.2.19: General Linear Matrices

Let R be a ring and $M_n(R)$ the set of all matrices of of dimension n over R. Then:

$$\mathrm{GL}_n(R) := (M_n(R))^\times$$

that is, $\mathrm{GL}_n(R)$ is the set of all units of $M_n(R)$, i.e. the set of all invertible matrices of dimension n over R.

The word "dimension" is used to indicate the number of rows and columns (which are both equal in this case, and hence why a single number is named). The term "general" is used since there other set of invertible matrices commonly studied, usually given a different prefix ("special", "orthogonal", "orthonormal", "unitary", and so forth). This set of invertible matrices is called "general" since it ill encompass *all* of these other sets of invertible matrices. For who may have come across these terms before, notice that this set was already mentioned in definition 1.2.33. One thing that as difficult to prove directly with matrices but easy to prove now is that $(\mathrm{GL}_n(R), \cdot)$ is associative: every invertible matrix represents a function, and function composition is associative, and hence $\cdot$ is an associative operation.

Proposition 13.2.20: Order of GL_n Over A Finite Field

Let F be a finite field with q elements and let $n \geq 1$. Then

$$|\mathrm{GL}_n(F)| = \prod_{i=0}^{n-1} (q^n - q^i) = (q^n - 1)(q^n - q)(q^n - q^2) \cdots (q^n - q^{n-1})$$

***Proof*:**
Call a sequence $(v_1, \dots, v_m)$ of vectors in F^n *independent* if $c_1v_1+\cdots+c_mv_m = 0$ with $c_1, \dots, c_m \in F$ forces $c_1 = \cdots = c_m = 0$. Let A be an $n \times n$ matrix over F with columns $a_1, \dots, a_n \in F^n$. For $x \in F^n$ we have $Ax = x_1a_1 + \cdots + x_na_n$, so A is nonsingular (definition 13.2.9) exactly when $(a_1, \dots, a_n)$ is independent. By proposition 13.2.10, A is invertible exactly when it is nonsingular, so $|\mathrm{GL}_n(F)|$ is the number of independent sequences $(a_1, \dots, a_n)$ in F^n.

Let $0 \le i \le n-1$, let $(a_1, \dots, a_i)$ be independent, and let $W = \{c_1a_1 + \cdots + c_ia_i \mid c_1, \dots, c_i \in F\}$. The map $F^i \to W$ sending $(c_1, \dots, c_i)$ to $c_1a_1 + \cdots + c_ia_i$ is surjective by definition and injective by independence, so $|W| = q^i$. The sequence $(a_1, \dots, a_{i+1})$ is independent exactly when $a_{i+1} \notin W$. Indeed, if $a_{i+1} = c_1a_1 + \cdots + c_ia_i$, then $c_1a_1 + \cdots + c_ia_i - a_{i+1} = 0$ is a relation with a nonzero coefficient. Conversely, if $a_{i+1} \notin W$ and $c_1a_1 + \cdots + c_{i+1}a_{i+1} = 0$, then $c_{i+1} = 0$, since otherwise $a_{i+1} = -c_{i+1}^{-1}(c_1a_1 + \cdots + c_ia_i) \in W$, and then $c_1 = \cdots = c_i = 0$ by the independence of $(a_1, \dots, a_i)$. So each independent sequence of length i extends in exactly $q^n - q^i$ ways, and multiplying over $i = 0, 1, \dots, n-1$ gives the formula, as claimed.

As mentioned, there can be matrices in $\mathrm{GL}_n(R)$ which are not a product of elementary matrices, that is, $\mathrm{GL}_n(R)$ need not be generated by elementary matrices. However, if $R = k$ is a field, then this is in fact the case, and the "if" in proposition 13.2.17(3) becomes an "iff"

Proposition 13.2.21: General Linear Group Of Field

Let k be a field and $A \in \mathrm{GL}_n(k)$. Then there are elementary matrices $E_1, \dots, E_s \in M_n(k)$ with

$$E_s \cdots E_1 A = I_n$$

so $A = E_1^{-1} \cdots E_s^{-1}$ is a product of elementary matrices, and $\mathrm{GL}_n(k)$ is generated by the elementary matrices. Consequently, two matrices $P, Q \in M_{m,n}(k)$ are equivalent if and only if Q is obtained from P by a finite sequence of elementary row and column operations.

***Proof*:**
Step 1: row reduction. We show by induction on j, for $0 \le j \le n$, that there is a product F_j of elementary matrices such that the first j columns of F_jA are the standard basis vectors $e_1, \dots, e_j$ of k^n. For $j = 0$ take $F_0 = I_n = D_1(1)$. Let $1 \le j \le n$ and $B = F_{j-1}A$, with columns $b_1, \dots, b_n$, so that $b_i = e_i$ for $i < j$. The matrix B is invertible, as a product of invertible matrices (proposition 13.2.17(2)), hence nonsingular (proposition 13.2.10). Some entry B_{ij} with $i \ge j$ is nonzero: otherwise $b_j = \sum_{i<j} B_{ij}e_i = \sum_{i<j} B_{ij}b_i$, and the vector $x = e_j - \sum_{i<j} B_{ij}e_i$, whose jth entry is 1, satisfies $Bx = b_j - \sum_{i<j} B_{ij}b_i = 0$. Choose such an i. In the first $j-1$ columns, every row of index at least j has zero entries, since those columns are $e_1, \dots, e_{j-1}$. Interchange rows i and j if $i \ne j$, then multiply row j by the inverse of its jth entry, and then, for each $l \ne j$, add $-c_l$ times row j to row l, where c_l is the current (l, j) entry. The jth column becomes e_j, and the first $j-1$ columns do not change, since in those columns the rows i and j have zero entries. By proposition 13.2.17(1) these operations are left multiplications by elementary matrices, and F_j is their product times F_{j-1}. For $j = n$, the columns of F_nA are $e_1, \dots, e_n$, that is, $F_nA = I_n$, and we write $F_n = E_s \cdots E_1$.

Step 2: generation. Since $E_s \cdots E_1A = I_n$ and A is invertible, $E_s \cdots E_1 = (E_s \cdots E_1A)A^{-1} = A^{-1}$, so $A = (E_s \cdots E_1)^{-1} = E_1^{-1} \cdots E_s^{-1}$. Each E_i^{-1} is an elementary matrix (definition 13.2.18),

so A is a product of elementary matrices. Conversely, every elementary matrix lies in $\mathrm{GL}_n(k)$ by proposition 13.2.17(2), so the subgroup of $\mathrm{GL}_n(k)$ generated by the elementary matrices is $\mathrm{GL}_n(k)$.

Step 3: equivalence. If Q is obtained from P by elementary operations, then P and Q are equivalent by proposition 13.2.17(3). Conversely, let $Q = MPN$ with $M \in \mathrm{GL}_m(k)$ and $N \in \mathrm{GL}_n(k)$. By Step 2, $M = M_1 \cdots M_a$ and $N = N_1 \cdots N_b$ with elementary matrices M_i and N_j, so $Q = M_1(\cdots(M_a(PN_1)\cdots)\cdots)N_b$ by associativity of matrix multiplication, and by proposition 13.2.17(1) each multiplication by an elementary matrix performs an elementary row or column operation, completing the proof.

Step 1 also computes inverses:

Corollary 13.2.22: Finding Inverse Of Matrix

Let k be a field and $A \in \mathrm{GL}_n(k)$. If a finite sequence of elementary row operations transforms A into I_n, then the same operations, applied to I_n, produce A^{-1}. Equivalently, if elementary row operations transform the $n \times 2n$ matrix $(A|I_n)$ into a matrix of the form $(I_n|B)$, then $B = A^{-1}$. Such a sequence of operations exists by proposition 13.2.21.

***Proof*:**
By proposition 13.2.17(1), the row operations are left multiplications by elementary matrices $E_1, \ldots, E_s$, applied in this order. If they transform A into I_n, then $E_s \cdots E_1 A = I_n$, so $E_s \cdots E_1 = (E_s \cdots E_1 A)A^{-1} = A^{-1}$, and the same operations applied to I_n give $E_s \cdots E_1 I_n = A^{-1}$. For the second statement, the jth column of EX is E times the jth column of X, for all $E \in M_n(k)$ and $X \in M_{n,2n}(k)$, so $E(A|I_n) = (EA|E)$. If the operations, with product $E = E_s \cdots E_1$, transform $(A|I_n)$ into $(I_n|B)$, then $EA = I_n$ and $E = B$, so $B = A^{-1}$ by the first part, completing the proof.

Reducing a matrix by elementary row operations, as in Step 1 of the proof of proposition 13.2.21, is called *Gaussian Elimination.*[11]

Over a field, every matrix is equivalent to a matrix of a simple shape, and the shape is determined by a single number:

[11] Though Gauss has most likely invented the above method when working with matrices, it has been known under slightly different symbols and theory at least as far back as Han China

Corollary 13.2.23: Equivalence Of Matrices

Let K be a field, let $P \in M_{m,n}(K)$, and let k be the dimension of the subspace $P(K^n) = \{Px \mid x \in K^n\}$ of K^m. For $0 \leq l \leq \min(m,n)$ write

$$B_l = \left(\begin{array}{c|c} I_l & 0 \\ \hline 0 & 0 \end{array}\right) \in M_{m,n}(K)$$

where each 0 is a zero matrix of the appropriate size, so that B_0 is the zero matrix. Then:

1. $0 \leq k \leq \min(m,n)$, and P is equivalent to B_k
2. P is equivalent to B_l only for $l = k$, and two matrices $P, Q \in M_{m,n}(K)$ are equivalent if and only if $\dim P(K^n) = \dim Q(K^n)$
3. $P(K^n)$ is the subspace of K^m spanned by the columns of P, and the subspace of K^n spanned by the rows of P, written as columns, also has dimension k

***Proof*:**
Let $\varphi\colon K^n \to K^m$ be the linear map $x \mapsto Px$, whose matrix with respect to the standard bases is P, since $\varphi(e_j) = Pe_j = \sum_i P_{ij} e_i$.

1. By corollary 13.1.18, $n = \dim \ker \varphi + k$, so $k \leq n$, and $k \leq m$ by proposition 13.1.17(2), since $\varphi(K^n) \subseteq K^m$. The kernel has a basis $(u_{k+1}, \ldots, u_n)$ (proposition 13.1.17(1)), which is contained in a basis of K^n with n elements (theorem 13.1.8, corollary 13.1.13(2)), and we write this basis as $(u_1, \ldots, u_n)$. The vectors $\varphi(u_1), \ldots, \varphi(u_k)$ span $\varphi(K^n)$, since $\varphi(u_j) = 0$ for $j > k$. They are linearly independent: if $\sum_{i \leq k} c_i \varphi(u_i) = 0$, then $\sum_{i \leq k} c_i u_i \in \ker \varphi$ is a combination of $u_{k+1}, \ldots, u_n$, and the independence of $(u_1, \ldots, u_n)$ forces every $c_i = 0$. Extend $(\varphi(u_1), \ldots, \varphi(u_k))$ to a basis $(w_1, \ldots, w_m)$ of K^m with $w_i = \varphi(u_i)$ for $i \leq k$ (theorem 13.1.8, corollary 13.1.13(2)). Then $\varphi(u_j) = w_j$ for $j \leq k$ and $\varphi(u_j) = 0$ for $j > k$, so the matrix of φ with respect to the bases (u_j) and (w_i) is B_k. By proposition 13.2.13, $B_k = MPN$ for change of basis matrices M and N, which are invertible by corollary 13.2.12(1). Hence P is equivalent to B_k.

2. Let $Q = MPN$ with $M \in \mathrm{GL}_m(K)$ and $N \in \mathrm{GL}_n(K)$. Then $N(K^n) = K^n$, since $x = N(N^{-1}x)$, so $Q(K^n) = M(P(K^n))$. The linear map $\rho\colon P(K^n) \to K^m$, $y \mapsto My$, is injective, since $My = 0$ forces $y = M^{-1}My = 0$, and its image is $Q(K^n)$. By corollary 13.1.18, $\dim P(K^n) = 0 + \dim Q(K^n)$. So equivalent matrices give subspaces of the same dimension. As $B_l(K^n) = \mathrm{span}(e_1, \ldots, e_l)$ has dimension l, P can be equivalent to B_l only for $l = k$. If $\dim P(K^n) = \dim Q(K^n) = k$, then by (1) $B_k = MPN = M'QN'$ for invertible M, N, M', N', so $Q = (M'^{-1}M)P(NN'^{-1})$ is equivalent to P.

3. For $x \in K^n$, $Px = x_1 p_1 + \cdots + x_n p_n$, where p_j is the jth column of P, so $P(K^n)$ is the span of the columns. The rows of P, written as columns, are the columns of the transpose P^t. By (1), $P = M^{-1}B_k N^{-1}$ with M and N invertible. Over the commutative field K, $(XY)^t = Y^t X^t$, both having (a,b) entry $\sum_c x_{bc} y_{ca}$, so $P^t = (N^{-1})^t B_k^t (M^{-1})^t$, where $(N^{-1})^t$ is invertible with inverse N^t, since $N^t(N^{-1})^t = (N^{-1}N)^t = I$ and $(N^{-1})^t N^t = (NN^{-1})^t = I$, and likewise for $(M^{-1})^t$. So $P^t \in M_{n,m}(K)$ is equivalent to B_k^t, the matrix of the same shape in $M_{n,m}(K)$, whose image $\mathrm{span}(e_1, \ldots, e_k) \subseteq K^n$ has dimension k. By

(2) applied to P^t, the span of the columns of P^t has dimension k, completing the proof.

So there are exactly $\min(m,n)+1$ equivalence classes of $m \times n$ matrices over a field, one for each k with $0 \leq k \leq \min(m,n)$. This also shows that if we look at a linear transformation in the right way (i.e. pick the right basis), a linear transformation *always* looks like a projection eliminating certain dimensions followed by an embedding of the rest of the space into the codomain! See proposition 13.1.22 to see how this intuition and the existence of complements of subspaces work together.

Some authors define the *row rank* and the *column rank* of a matrix as the dimensions of the spaces spanned by its rows and by its columns, and show that the two are the same number, which is corollary 13.2.23(3):

Definition 13.2.24: [matrix] Rank

Let A be an $m \times n$ matrix over a field. Then the *row rank* is the dimension of the space spanned by its rows, and the *column rank* is the dimension of the space spanned by its columns. By corollary 13.2.23(3), the row rank and the column rank are equal, and the single number is called the *rank* of the matrix. If the rank is $\min(m,n)$, the matrix is said to be of *full rank*.

The map $x \mapsto Ax$ represented by an $m \times n$ matrix A of rank r has image of dimension r by corollary 13.2.23(3), so it is surjective when $r = m$ (proposition 13.1.17(2)) and injective when $r = n$, its kernel then having dimension $n - r = 0$ (corollary 13.1.18).

To finish off this section, we can ask if the same logic can be done for the notion of similarity. Unfortunately, similarity is more complicated: since only one matrix is being picked (i.e. only one basis is being picked) the rows and column operations must be done "simultaneously". Not all hope is lost: using properties of PID's will show us how to find a good matrix representation for similar matrices in the next chapter.

Gaussian Elimination over Euclidean Domain

From the rings we explored earlier, the euclidean domain is a good start, and indeed with some cleverness a matrix over a euclidean domain can be reduced, though not intirely to an identity matrix in a sub-matrix of the original.

To demonstrate the idea, let R be a euclidean domain with valuation ν, and take any 2×2 matrix:

$$\begin{pmatrix} a & b \\ c & d \end{pmatrix}$$

then use elementary matrices to put the element with the lowest valuation at position $(1,1)$. Then use the euclidean algorithm to find:

$$b = aq + r$$

where either $r = 0$ or $\nu(r) < \nu(a)$. Then do the appropriate elementary operation to get:

$$\begin{pmatrix} a & r \\ c & d - aq \end{pmatrix}$$

if $r = 0$, then we have eliminated one of the components. If $r \neq 0$, then repeat the same process, moving the term with the lowest valuation to the $(1,1)$ position using elementary matrices. Since

each term has a finite valuation, it must be that eventually $r = 0$. With minor modifications, the same thing can be done in the $(2, 1)$ position, getting us:

$$\begin{pmatrix} a' & 0 \\ 0 & d' \end{pmatrix}$$

Next, notice that we may find an a', d' such that $a' \big| d'$. For if not, we may consider:

$$\begin{pmatrix} a' & d' \\ 0 & d' \end{pmatrix}$$

and repeat the process until we get to the same state, and keep repeating until either $d' = 0$ or $a' \big| d'$. Thus, we produce a 2×2 matrix where the diagonal divides each other.

From this, it is not too hard to see that this is easily generelizable to an $n \times n$ matrix:

Theorem 13.2.25: Smith Normal Form

Let R be a euclidean domain and $P \in M_{m,n}(R)$. Then P is equivalent to a matrix of the form

$$\left(\begin{array}{ccc|c} [ccc|c]d_1 & \cdots & 0 & 0 \\ \vdots & \ddots & 0 & 0 \\ 0 & \cdots & d_k & 0 \\ \hline 0 & \cdots & 0 & 0 \end{array}\right)$$

where

$$d_1 \big| \cdots \big| d_k$$

The resulting matrix is called the *smith normal form*.

***Proof*:**

Throughout, all matrices produced from P by elementary row and column operations are equivalent to P by proposition 13.2.17(3). We prove the theorem itself by induction on $\min(m, n)$. If $P = 0$, then P is already of the stated form with $k = 0$, so assume P is nonzero.

The following clearing claim holds for every nonzero P, with no induction: P is equivalent to a block matrix whose $(1, 1)$ entry is some nonzero d_1, whose remaining first row and first column are zero, and whose lower right block P' (possibly empty) has every entry divisible by d_1.

Consider the set of valuations $\nu(a)$ of all nonzero entries a of all matrices equivalent to P. This is a nonempty set of non-negative integers, so by well-ordering it has a least element. Choose a matrix Q equivalent to P having a nonzero entry a with $\nu(a)$ least. Swapping rows and columns, we may assume a is in position $(1, 1)$.

We claim a divides every entry b of the first row of Q. Say b is in position $(1, j)$ with $j \geq 2$, and divide: $b = qa + r$ with $r = 0$ or $\nu(r) < \nu(a)$. Subtracting q times the first column from the jth column produces a matrix equivalent to P with r in position $(1, j)$. If $r \neq 0$, then $\nu(r) < \nu(a)$ contradicts the minimality of $\nu(a)$. Hence $r = 0$ and $a \big| b$. The same argument with rows in place of columns shows a divides every entry of the first column.

Consequently, subtracting the appropriate multiple of the first column from each other column clears the rest of the first row, and then subtracting the appropriate multiple of the (new) first

row from each other row clears the rest of the first column. We arrive at an equivalent matrix with $(1,1)$ entry a, zeros elsewhere in the first row and column, and some lower right block P'.

Next, a divides every entry c of P'. Say c is in position (i,j) with $i,j \geq 2$. Adding the ith row to the first row leaves the $(1,1)$ entry equal to a (the ith row has first entry 0) and places c in position $(1,j)$. Dividing $c = qa + r$ and subtracting q times the first column from the jth column as before, minimality of $\nu(a)$ forces $r = 0$, so $a \big| c$. This proves the clearing claim with $d_1 = a$.

In the base case $\min(m,n) = 1$ of the induction, the block P' is empty, so the clearing claim already puts P in the stated form with $k = 1$. For the inductive step, apply the clearing claim to P. If P' is zero, the matrix is in the stated form with $k = 1$. Otherwise, the induction hypothesis, that is, the theorem for the smaller matrix P', provides a sequence of elementary operations on P' bringing it to the form $\operatorname{diag}(d_2, \ldots, d_k)$ bordered by zeros, with $d_2 \big| \cdots \big| d_k$. These operations involve only the last $m-1$ rows and last $n-1$ columns, so they do not disturb the first row and column, and applying them yields a matrix of the stated shape, equivalent to P.

It remains to verify $d_1 \big| d_2$. Each elementary operation replaces every entry of a matrix by an R-linear combination of its previous entries, so by induction along the sequence of operations, every entry of the reduced form of P' is an R-linear combination of entries of P'. Since d_1 divides every entry of P', it divides every such combination, and in particular $d_1 \big| d_2$. Hence $d_1 \big| d_2 \big| \cdots \big| d_k$, completing the proof.

Using smith normal forms, we may prove that $\mathrm{GL}_n(R)$ is generated by elementary matrices for a Euclidean domain R. This fails for some Principal Ideal Domains: for the ring of integers $\mathbb{Z}[\frac{1+\sqrt{-19}}{2}]$ of $\mathbb{Q}(\sqrt{-19})$, which is a Principal Ideal Domain but not Euclidean, GL_2 is not generated by elementary matrices [45]. On the other hand, we can put any matrix in $\mathrm{GL}_n(R)$ into smith normal form using the gcd and some non-elementary matrix operations. This shall be further explored in chapter 14.

13.2.4 Geometric Result: Systems of Linear Equations

Vector spaces and linear maps have part of their origins in geometry, where the term *linear* originates. The rigorous interpretation of a concept being "geometrical" is something that would be explored in a class on [differential] geometry, and so for the uses of this book geometrical shall mean "locally or globally looks like the solutions to equations":

$$\begin{aligned} f_1(\vec{x}) &= a_1 \\ f_2(\vec{x}) &= a_2 \\ &\vdots \\ f_n(\vec{x}) &= a_n \end{aligned}$$

Often, the constant is moved to the left modifying the equations to be:

$$\begin{aligned} f_1(\vec{x}) - a_1 &= 0 \\ f_2(\vec{x}) - a_2 &= 0 \\ &\vdots \\ f_n(\vec{x}) - a_n &= 0 \end{aligned}$$

This understanding of geometrical is in fact very potent, for example the reader may have already encountered many geometrical objects that are defined in this way, for example:




Figure 13.1: solution to $x^2 + y^2 - n^2 = 0$

For the particular explorations of this section, we shall show that vector spaces can be interpreted as the of solutions to *linear equations*:

Definition 13.2.26: Linear Equation and System of Linear Equations

Let V be a k-vector space of dimension n and $k[x_1, x_2, ..., x_n]$ be a polynomial ring over the field k with n variables. Then a *linear equation* is a polynomial, possibly over several variables, where the degree of each variable is at most 1:

$$a_1x_1 + a_2x_2 + \cdots + a_nx_n$$

A collection of linear equations is called a *system of linear equations*.

Given a (system of) linear equation(s), we can define *linear functions*: if $\sum_i a_ix_i$ is a linear equation then we can define:

$$L_1 : k^n \to k \qquad L(x_1, x_2, ..., x_n) = a_1x_1 + a_2x_2 + \cdots a_nx_n$$

and similarly a system of linear functions is a collection of linear functions $L_1, ..., L_m$. Since these functions are linear, they can be represented by a matrix, namely given the standard basis:

$$A = [L_1] = \begin{pmatrix} a_1 & a_2 & \cdots & a_n \end{pmatrix}$$

so that if $\vec{x}$ is an $n \times 1$ matrix with with x_i coefficients, then plugging in a value from k^n is represented as matrix multiplication by

$$A\vec{x} = \begin{pmatrix} a_1 & a_2 & \cdots & a_n \end{pmatrix} \begin{pmatrix} x_1 \\ x_2 \\ \vdots \\ x_n \end{pmatrix} = a_1x_1 + a_2x_2 + \cdots + a_nx_n$$

Equivalently, any system of linear equation can be combined to form a linear equation:

$$L : k^n \to k^m \qquad L = \begin{bmatrix} L_1 \\ L_2 \\ \vdots \\ L_m \end{bmatrix} \tag{13.6}$$

Let's now say we want to find the solution to the system:

$$\begin{aligned} a_{11}x_1 + a_{12}x_2 + \cdots a_{1n}x_n &= b_1 \\ a_{21}x_1 + a_{22}x_2 + \cdots a_{2n}x_n &= b_2 \\ &\vdots \\ a_{m1}x_1 + a_{m2}x_2 + \cdots a_{mn}x_n &= b_m \end{aligned}$$

Then if $\vec{b} = (b_{k1})$, then what we are solving for is:

$$A\vec{x} = \vec{b}$$

If A is invertible and $n = m$, then the answer is simple:

$$\vec{x} = A^{-1}\vec{b}$$

where A^{-1} is found using corollary 13.2.22. In general, corollary 13.2.23 gives invertible matrices $M \in \mathrm{GL}_m(k)$ and $N \in \mathrm{GL}_n(k)$ with $MAN = B_r$, where r is the rank of A. Writing $\vec{x} = N\vec{y}$ and $\vec{c} = M\vec{b}$, the system $A\vec{x} = \vec{b}$ is equivalent to $(MAN)\vec{y} = \vec{c}$, since M and N are invertible, that is, to the system

$$y_1 = c_1 \qquad \cdots \qquad y_r = c_r \qquad 0 = c_{r+1} \qquad \cdots \qquad 0 = c_m$$

So $A\vec{x} = \vec{b}$ has a solution if and only if $c_{r+1} = \cdots = c_m = 0$, and then its solutions are the vectors $N\vec{y}$ with $y_i = c_i$ for $i \leq r$ and $y_{r+1}, \ldots, y_n$ arbitrary. Over a Euclidean domain R such as $\mathbb{Z}$, theorem 13.2.25 gives invertible matrices M and N over R with MAN diagonal with entries $d_1 \big| \cdots \big| d_r$ followed by zeros, and the same substitution turns the system into $d_iy_i = c_i$ for $i \leq r$ and $0 = c_i$ for $i > r$, which has a solution $\vec{y} \in R^n$ if and only if $d_i \big| c_i$ for $i \leq r$ and $c_i = 0$ for $i > r$.

Where this links to geometry is when considering the space of solution to systems of linear equations. First, notice that without loss of generality the linear equations may equal to 0, for this would simply translate the resulting set of solutions in the vector-space, hence it suffices to consider:

$$\begin{aligned} a_{11}x_1 + a_{12}x_2 + \cdots a_{1n}x_n &= 0 \\ a_{21}x_1 + a_{22}x_2 + \cdots a_{2n}x_n &= 0 \\ &\vdots \\ a_{m1}x_1 + a_{m2}x_2 + \cdots a_{mn}x_n &= 0 \end{aligned}$$

That is, it suffices to consider the kernel of a system of linear equations, equivalently the kernel of L as defined in equation (13.6).

Now, to endeavor exploring the shape of the kernel of linear functions, let's start with $k = \mathbb{R}$, $L : \mathbb{R}^3 \to \mathbb{R}$, and always use the standard basis. It is easy to visualize $\mathbb{R}, \mathbb{R}^2, \mathbb{R}^3$, and higher dimensional analogues can be fathomed. Naturally, if $L(x) = 0$, then $\ker = \mathbb{R}^3$. It is more interesting if L is non-trivial, which for linear functions implies L is surjective. Then by the Rank-Nullity Theorem $\dim \ker = 3 - 1 = 2$, i.e. it is a plane. A plane that is one-dimension less than the ambient space (in this case $\mathbb{R}^3$) is called a *hyper-plane*. Since it is a subspace, it must contain 0 and hence passes through the origin. Since the plane is two dimension, it is spanned by two vectors. Using Gaussian elimination, we can deduce it is spanned by two vectors:

$$\left\{ \begin{pmatrix} a_1 \\ a_2 \\ a_3 \end{pmatrix}, \begin{pmatrix} b_1 \\ b_2 \\ b_3 \end{pmatrix} \right\}$$

Example 13.2.27: Finding A Hyperplane

Take $L(x, y, z) = 3x + 2y - 3z$, which is surjective since $L(c/3, 0, 0) = c$ for every $c \in \mathbb{R}$. By the Rank-Nullity Theorem (corollary 13.1.18) its kernel has dimension $3 - 1 = 2$. The vectors $(2, -3, 0)$ and $(1, 0, 1)$ lie in the kernel, since $3 \cdot 2 + 2 \cdot (-3) = 0$ and $3 - 3 = 0$, and they are linearly independent, since neither is a multiple of the other. So they form a basis of the kernel, since a linearly independent set lies in a basis (theorem 13.1.8) and every basis of the kernel has 2 elements (corollary 13.1.13(2)). The kernel when embedded in $\mathbb{R}^3$ looks like so:




Figure 13.2: $3x + 2y - 3z = 0$

Notice that since the image is one dimensional, the hyper-plane is defined by only one equation, however it is a two dimensional object. More generally, for a surjective linear function $L : \mathbb{R}^n \to \mathbb{R}$, the hyperplane shall be $(n-1)$ dimensional and be defined by a single equation.

Next, let's consider the case where $L : \mathbb{R}^3 \to \mathbb{R}^2$, that is there are two linear equations $L_1 : \mathbb{R}^3 \to \mathbb{R}$ and $L_2 : \mathbb{R}^3 \to \mathbb{R}$. Let's again assume that L is surjective, or full-rank, for if L was one dimension less it would be equivalent to the case of $L : \mathbb{R}^3 \to \mathbb{R}$. Then by the Rank-Nullity theorem we have that $\ker L = 3 - 2 = 1$. Intuitively, this is because there are more restrictions for $L(x) = 0$, namely both L_1 and L_2 must equal 0. Geometrically, this can be thought of as the *intersection* of the kernel of L_1 and the kernel of L_2. Since L is full rank, the intersection is not parallel (the geometric word for this is that the intersection is *transversal*). More generally, $L : \mathbb{R}^n \to \mathbb{R}^2$ would have $\dim \ker L = n - 2$, and would be defined by two linear equations.

Extended the pattern further, given a full-rank linear function $L : \mathbb{R}^n \to \mathbb{R}^m$, the resulting plane given by the kernel would be $n - m$ dimensional and would represent the intersection of m hyper-plane of dimension $n - 1$, each new hyper-plane restricting the dimension of the kernel. The orientation of the kernel is completely dependent on the linear map in question. Nothing in these results required to work specifically with $k = \mathbb{R}$, it was simply convenient for visual purposes. These results can be summarized into the following:

Theorem 13.2.28: Classification Of Planes

Let V be a k-vector-space of dimension n and let $0 \leq m \leq n$, where $k^0 = \{0\}$.

1. If $L\colon V \to k^m$ is a surjective (that is, full-rank) linear map, then $\ker L$ is a subspace of V of dimension $n - m$
2. Every subspace W of V of dimension $n - m$ is $\ker L$ for some surjective linear map $L\colon V \to k^m$
3. Two surjective linear maps $L, L'\colon V \to k^m$ have the same kernel if and only if $L' = g \circ L$ for some linear automorphism g of k^m

Thus the sub-spaces of V of dimension $n-m$ correspond to the full-rank linear maps $V \to k^m$, taken up to composition with automorphisms of k^m. When $V = k^n$, every subspace is the set of solutions of a system of linear equations $a_{i1}x_1 + \cdots + a_{in}x_n = 0$, $1 \leq i \leq m$.

***Proof*:**

1. By the Rank-Nullity Theorem (corollary 13.1.18), $\ker L$ is a subspace of V and $\dim \ker L = \dim V - \dim L(V) = n - m$, since $L(V) = k^m$ has dimension m.
2. The subspace W has a basis $w_1, \ldots, w_{n-m}$ (theorem 13.1.8), with $n - m$ elements since $\dim W = n - m$. This linearly independent set is contained in a basis B of V (theorem 13.1.8), which has n elements by corollary 13.1.13(2). So we may write $B = \{w_1, \ldots, w_{n-m}, u_1, \ldots, u_m\}$. Let $L\colon V \to k^m$ be the linear map with $L(w_i) = 0$ for all i and $L(u_j) = e_j$, the jth standard basis vector of k^m (corollary 12.3.14). For $v = \sum_i c_i w_i + \sum_j d_j u_j$,
$$L(v) = d_1 e_1 + \cdots + d_m e_m = (d_1, \ldots, d_m)$$
so L is surjective, and $L(v) = 0$ exactly when every $d_j = 0$, that is, when $v \in W$, the coefficients of v with respect to B being unique. Hence $\ker L = W$.
3. If $L' = g \circ L$ with g an automorphism, then $L'(v) = 0$ exactly when $L(v) = 0$, since g is injective, so $\ker L' = \ker L$. Conversely, suppose $\ker L = \ker L' = W$, and define $g\colon k^m \to k^m$ by $g(L(v)) = L'(v)$. Every element of k^m has the form $L(v)$, as L is surjective, and g is well defined: if $L(v) = L(v')$, then $v - v' \in W = \ker L'$, so $L'(v) = L'(v')$. It is linear, since $g(L(v) + cL(v')) = g(L(v + cv')) = L'(v + cv') = L'(v) + cL'(v')$ for $c \in k$. It is surjective, because L' is, and injective, because $g(L(v)) = 0$ means $v \in \ker L' = \ker L$, that is, $L(v) = 0$. By lemma 12.2.3, g is a linear automorphism of k^m, and $L' = g \circ L$ by construction.

Finally, let $V = k^n$ and write $L = (L_1, \ldots, L_m)$ with components $L_i\colon k^n \to k$. For $x = \sum_j x_j e_j$ and $a_{ij} = L_i(e_j)$, linearity gives $L_i(x) = a_{i1}x_1 + \cdots + a_{in}x_n$, so $\ker L$ is the set of solutions of the system $a_{i1}x_1 + \cdots + a_{in}x_n = 0$, $1 \leq i \leq m$. By (2), every subspace of k^n has this form, completing the proof.

Given that L is surjective, notice that as m increases in size, the dimension of the kernel decreases in

size. In a sense it is the "co-dimension" of the domain. This observation is not lost on mathematicians, and the notion of codimension is quite important in geometry: the dimension of an object represents the degree of freedom an object may have within a space (ex. a hyper-plane is $n-1$ dimensional) while the codimension represents the degree of restriction an object may have within a space (ex. a hyper-plane is 1 codimensional).

13.2.5 Use Case: Reading Presentations

Recall from section 12.3.3 that a presentation of a [finitely generated] R-module can be represented as an exact sequence:

$$R^n \to R^m \to M \to 0$$

Using the above results, we can more easily read the presentation. Let $\varphi : R^n \to R^m$. Then by exactness, we have that $M \cong \text{coker}(\varphi)$. Hence, if we find the image of φ, we found the relations of M, and and if R is a field of euclidean domain, this is task is simplified using Gaussian elimination:

Example 13.2.29: Finding A Presentation
Let $R = \mathbb{Z}$ and let φ be represented by the matrix:

$$\begin{pmatrix} 1 & 3 \\ 2 & 3 \\ 5 & 9 \end{pmatrix}$$

which means that $\varphi : \mathbb{Z}^2 \to \mathbb{Z}^3$ and this matrix determines an abelian group G (since finitely generated abelian groups have free resolutions of length at most 1 as mentioned in section 12.3.3). To find G, let us first simplify the above matrix. The reader should check that the matrix reduces to:

$$\begin{pmatrix} 1 & 0 \\ 0 & 3 \\ 0 & 0 \end{pmatrix}$$

Hence, G is isomorphic to the cokernel of $\varphi : \mathbb{Z}^2 \to \mathbb{Z}^3$ that maps $(1,0)$ to $(1,0,0)$ and $(0,1)$ to $(0,3,0)$. In particular, since the image is $\mathbb{Z} \oplus 3\mathbb{Z} \oplus 0$, we get

$$G \cong \text{coker}\varphi \cong \frac{\mathbb{Z} \oplus \mathbb{Z} \oplus \mathbb{Z}}{\mathbb{Z} \oplus 3\mathbb{Z} \oplus 0} \cong (\mathbb{Z}/3\mathbb{Z}) \oplus \mathbb{Z}$$

Showing how a matrix can uniquely represent an abelian group! In the next chapter, we shall show how a matrix can more generally represent a finitely generated module over a PID.

13.2.30 Remark Notice that we may eliminate first row and column if the leading term is 1 (or more generally a unit) since in the quotient the summand shall be completely quotiented.

13.3 Dual Spaces and Forms

Let's say you are studying some mathematical object, say the set of linear transformations. We may want to find numerical properties. For example of linear transformations, we can quantify the size of

a matrix, or give some numerical value to similarity, or the dimension of the image. We can define a function from $L(V)$ to a field, say $\mathbb{R}$, that shall give us this quantification. The collection of all these functions are called the *functionals* on $L(V)$. Depending on what type of property we want want the invariances that are being sought after, we will have different types of functionals. For example, when working in analysis, we shall often want our functional to be continuous or perhaps bounded in some way [12]. In Algebra, we shall want our functionals to be homomorphisms, and depending on what other property we want we shall add more properties to our functionals (ex. it shall be important in section 31.1 that the functional preserves solutions to a special set of polynomial equations).

The set of functionals on a vector space V can be thought of as containing all possible quantifiable "information" about a space (with the limits of the information provided by the properties of the functionals). Most of the time, the space of functionals is larger than the original space[13]. In some special cases, the spaces of all functionals is isomorphic to the space over which we are taking the functionals (as we shall see, all linear functionals on a finite dimensional vector space V is isomorphic to V). In this special case, we can think of our space being characterized by the property the functionals represent! This realization was the origin of *dual theory*, which we shall start exploring in this section. Dual theory is normally explored in earnest in Real and Functional analysis, however it shall show up in some important ways in section 32.1, and certain key functionals shall give a lot of information on linear transformations, namely the trace and the determinant.

13.3.1 Dual Spaces

In mathematics, there is frequently two "opposing" or "dual" ways of describing objects: Let's say X is our object of study

1. internally: Using properties internal to your object to describe that object. Often, maps *to* the object will give us internal information ($f : A \to X$ for some appropriate object A). This can may also be thought of as local information
2. externally: Using some exterior property (ex. be it by putting it an ambient space, or a sapce in which the object X "resonates" or "interacts" with[14]). Ofen, maps *from* the object will give us external information ($f : X \to A$ for osme appropriate object A). This can also often be thought as global information

As an example of this, when we were working with group theory, we found two way of looking at all possible groups:

1. Using quotients of free groups, we managed to make normal subgroups of free groups represent relations between elements. In the process of doing this, we defined a surjective homomorphism:
$$\varphi : F(A) \to G$$
2. Using Cayley's theorem, we manage to embed any group into a subgroup of S_A. In the process of doing this, we defined an invective map
$$\psi : G \to S_A$$

[12] See Lebesgue Spaces in [80] for more details

[13] This is a guiding principle behind many generalizations in Mathematics, Distribution Theory being the prototypical example

[14] If you know Fourier Analysis, think of phase space

Notice how the first one defined us what's happening between elements in a sort of "local" way, while in the 2nd example we defined it by using properties of the larger group S_A and how elements of G embed into S_A. Another example of this principle can be seen with the universal property of products and coproducts of groups. In a sense, the universal property of products only requires the product group to have groups A and B "locally" in the most efficient way, leading to the direct product of A and B, while the corpoduct group require it to have A and B "globally" in the most efficient way, leading to the free product of A and B.

Often when studying an object X, we will study if from these two perspectives: from maps going *into* X and maps going *out of* X. One remarkable phenomena that occurs often in mathematics is that there is often a [contravariant] *dual object* in which the maps *into* and *out of* X are naturally associated to maps *out of* and *into* a dual object X^*. Note the reversal in the directions of the maps! It is often very fruitful to look at objects from the perspective of both X and X^* to gain more information.

To demonstrate a simple but powerful example of "dualness" in mathematics (or the pervasiveness of dualness), we require knowledge of fields outisde of algebra. Usually, I (the author of this book) would decide to leave out any such example to insure no prerequisites are required to learn the material. However, I have decided to break this rule here for those who know a bit of topology since it is an example so powerful that it changed my view of duality, and requires elementary topology knowledge. The following example is *not* necessary for understanding any material of this book and can be considered motivation for dual spaces and dual theory in general for those who know some topology (if you need a refresher on topology, see appendix C). In this example, we will take a moment and venture outisde of algebra and into the realm of analysis and and geometry to give an interesting example.We will give a common phenomena in which "algebraic" object have "geometric" objects as their dual. In particular, unlike the duality of a group in its represetnation in terms of the quotient of a free group or an embedding into S_G, both of which are algebraic ways of looking at groups, we will show that dual objects are sometimes found in other fields of mathematics, allowing us to connect these two fields of mathematics proof-strategies and techniques!

> First, define a *Boolean Algebra* to be a $\mathbb{F}_2$-algebra (where $\mathbb{F}_2 = \mathbb{Z}/2\mathbb{Z}$). Since $\mathbb{F}_2$ is a field, a Boolean Algebra B is module-isomorphic to $\mathbb{F}_2^n$ for some cardinality n. For $0, 1$ in a Boolean algebra B:
>
> $$0+0=0 \quad 0+1=1+0=0 \quad 1+1=0 \qquad 0\cdot 0=0\cdot 1=1\cdot 0=0 \quad 1\cdot 1=0$$
>
> We usually also define the additional operation of $\neg$:
>
> $$\neg(x) = 1 - x$$
>
> If you have done some computer science or logic, then you might notice that 1 and 0 can represent the values of *true* and *false* respectively, while $+$ and $\cdot$ represent XOR and AND respectively (hence the name Boolean to this algebra). This algebra underlines most of the logic behind computer science, making us want to find properties of boolean algebras. One way we may study these properties is by looking for maps going *into* a boolean algebra B. Dually, by a result known as *Stone Duality*, we can instead study all the maps *out of* a totally disconnected[15] Hausdorff spaces B^*! Thus, the "dual" of Boolean Algebra is all continuous maps from B^* to $\mathbb{R}$! More generally, locally compact[16]

[15] A topological space in which the only connected sets are singletons

[16] a topological space in which for any point x, there exists a compact neighbourhood

topological spaces (which we can consider as a geometric object) are the dual of a type of algebra known as a C^*-algebras[17] (which we consider as algebraic objects): this is known as *Gelfand Duality*[18]. The study of these objects that are related to each other by "duality" is called *Dual Theory*.

Coming back to algebra and the study of vector-spaces, we will see the very beginnings of Dual Theory by studying the simplest case of dual objects, *dual vector-spaces*. The way we will define the dual of a vector-space will be through "external" means. When we defined vector spaces using a basis, that is a "local" property. In a sense, we showed that the map $f : F(A) \to V$ can define a vector space where A is a basis. What we will now do is the *dual* equivalent: we will define a vector space by mapping V into a different space.

The question arrises as to what space might we might we map to? When working with groups, it was not immediately obvious that S_A would be the right group to map. Fortunately for us, there is an "obvious" space to map to: for any vector-sapce over k, we are always given two algebraic objects, namely the abelian group V and the field k. Since k is always a vector-sapce over itself,we can consider linear maps $f : V \to k$! The collection of all such maps is called the *dual space* of V.

Definition 13.3.1: Dual Space

Let V be a vector space over k. Then $V^* = \mathrm{Hom}_k(V, k)$ is the space of all linear transformations from V to f, and is called the *dual space* of V.

By proposition 12.2.7, $\mathrm{Hom}_k(V, k)$ is a vector-space over k (if you are not convinced, it is recommended to reprove this before continuing). The notation $V^\vee$ is also often used to define the dual space and will be used interchangibly. Elements inside the dual space V^* are sometimes called *covectors*, paralleling to how elements inside a vector space V is called *vectors*. In physics and analysis, there is seomtimes a different convention for how to write the evalutation of if $f \in V^*$ at $x \in V$: instead of writing $f(x)$, to mean "evaluate f at the point x", it is sometimes written $\langle f, x\rangle$.

Elements of V^* are given a name:

Definition 13.3.2: Linear Functionals

Let V^* be the dual space of V. Then $f \in V^*$ is called a *linear functional* or *linear form*.

Example 13.3.3: Linear Functional and Dual Spaces

1. (If you know some calculus) Perhaps the most famous linear functional is $\int_a^b ___ dx : L^1(\mathbb{R}) \to \mathbb{R}$, where $L^1(\mathbb{R})$ will denote the set of all (either Riemann or Lebesgue)[a] integrable functions $f : \mathbb{R} \to \mathbb{R}$ where $\int_{\mathbb{R}} |f| dx < \infty$ (so that the integral is well-defined). Note that $L^1(\mathbb{R})$ is a vector-space with addition and scalar multiplication defined pointwise since the codomain is

[17] A Banach Algebra over $\mathbb{C}$ with a map known as an involution satisfying the properties of an adjoins

[18] This duality requires a good deal more topology and analysis than is part of the scope of this book. However, in section 31.3, we will see the Zariski Duality which studies a geometric-algebraic duality without the need for much analysis or topology

$\mathbb{R}$:

$$f + g \Leftrightarrow (f+g)(a) = f(a) + (g)$$
$$c \cdot f \Leftrightarrow (c \cdot f)(a) = cf$$

Now, $\int_a^b ___ dx$ takes in a function $f : \mathbb{R} \to \mathbb{R}$, an gives th number $\int_a^b f dx \in \mathbb{R}$. By basic properties of integarls, we know that:

$$\int_a^b (f+g)dx = \int_a^b f dx + \int_a^b g dx$$
$$\int_a^b cf dx = c\int_a^b f dx \qquad \forall a \in \mathbb{R}$$

and hence $\int_a^b ___ dx$ is indeed a linear functional! Hence $\int_a^b ___ dx \in L^1(\mathbb{R})^*$, for any $a, b \in \mathbb{R}$[b] The study of these functionals is part of functional analysis (*Functional Analysis* [80]).

2. Let $C([a,b])$ be the collection of all continuous maps from $[a,b]$ to $\mathbb{R}$, $f : [a,b] \to \mathbb{R}$, with addition and scalar multiplication defined pointwise. Then define: $\mathrm{ev}_x : C([a,b]) \to \mathbb{R}$ to be

$$f \mapsto f(x)$$

Then it can be shown that ev_x is a linear transformation, called the *evaluation map*, and is thus a linear functional. More generally, as long as the codomain is a field $\mathbb{R}$, then the evaluation map is a linear functional.

3. A more advanced case of the above example occurs if we consider the set $C^1(\mathbb{R})$ of all differentiable functions[c] forms a vector-space with point-wise addition and scalar multiplicaiton. The operator $D_a : C^1(\mathbb{R}) \to \mathbb{R}$ takes in a differentiable function f and gives back $Df(a)$ (which in first year calculus is more commonly denoted $f'(a)$).

4. (If you know geometry or analysis) The following examples are not examples of dual spaces as we have defined them, but the generlization of them. In this generlization, the dual space we have defined would be called a *linear* dual space, or the dual space of in the category of $\mathbf{Vect}_k$. More generally, if X is an object in a category, then given a *dualizing* object D (often it is $\mathbb{R}$, $\mathbb{C}$, $\mathbb{C}^\times$, $\mathbb{Z}/n\mathbb{Z}$, or $\mathbb{R}/\mathbb{Z}$ depending on the context), then $\mathrm{Hom}_C(X, D)$ is the dual space. In the following example, let D be either $\mathbb{R}$ or $\mathbb{C}$. Let's say X is either a vector-space over $\mathbb{R}$ or $\mathbb{C}$ (you should have function spaces in mind) or a manifold over $\mathbb{R}$ or $\mathbb{C}$. Then $C_0(X)$, $C^k(X)$, $L^p(X)$, an so forth are all subspace of the dual space X^* in the appropriate category.

Another place in which [ring] funcitonals shall become of paramount importance is in section 31.1 and section 32.5, where a duality is set up between algebraic and geometric objects.

[a] For the sake of this example, it does not matter, though L^1 usually denote *Lebesuge* measurable functions where $\int |f| < \infty$

[b] (if you know some analysis) Every *bounded* linear functional on $L^1(\mathbb{R})$ has the form $f \mapsto \int fg$ for a unique $g \in L^\infty(\mathbb{R})$ [80, Description Of Dual Of Lp]. The algebraic dual $L^1(\mathbb{R})^*$ used here also contains unbounded functionals.

[c] in particular, continuously differentiable functions. This distinction is of no importance for this example

In the above examples, all the vector-spaces are infinite dimensional. The vector-space being infinite dimensional will in fact greatly complicate the structure of dual spaces[19]. In general, more structure is added to a vector-space (ex. a norm) to have better "control" of infinite dimensional vector-spaces. Such discussion is left to a course on functional analysis[20]. We will mainly focus on the theory of finite dimensional vector spaces, since the results of this theory is in it of itself quite fruitful and provides a good basis for its study of dual spaces more generally.

Given a basis for V, it straight-forward to find a basis for $V^\vee$:

Definition 13.3.4: Dual Basis

Let $\beta = \{v_1, v_2, ..., v_n\}$ be a basis for the finite dimensional vector-space V. Then define $v_i^* \in V^*$ to be

$$v_i^*(v_j) = \begin{cases} 1 & \text{if } i = j \\ 0 & \text{if } i \neq j \end{cases}$$

for $1 \leq i, j \leq n$. Let β^* be the set of dual-basis elements

Since β^* has the word basis in it's name, you might guess that it is ineed a basis for the dual space:

Proposition 13.3.5: Dual Basis

Let β^* be defined as in definition 13.3.4. Then β^* is a basis for V^*

***Proof*:**

Note first that each v_i^* is well-defined: V is free on the basis β, so by corollary 12.3.14 a linear map out of V may be prescribed arbitrarily on β.

We show $\beta^* = \{v_1^*, \dots, v_n^*\}$ spans V^*. Let $f \in V^*$ and set $g := \sum_{i=1}^n f(v_i)\, v_i^*$. For each basis vector v_j,

$$g(v_j) = \sum_{i=1}^{n} f(v_i)\, v_i^*(v_j) = f(v_j)$$

since $v_i^*(v_j)$ is 1 when $i = j$ and 0 otherwise. Hence for any $v = \sum_j c_j v_j \in V$, linearity gives $g(v) = \sum_j c_j g(v_j) = \sum_j c_j f(v_j) = f(v)$, so $f = g \in \operatorname{span}(\beta^*)$.

For linear independence, suppose $\sum_{i=1}^n c_i v_i^* = 0$ in V^*. Evaluating at v_j gives

$$0 = \sum_{i=1}^{n} c_i v_i^*(v_j) = c_j$$

for every j, so all coefficients vanish. Hence β^* is linearly independent and spans V^*, that is, a basis.

As a consequence, V^* has the same dimension as V

[19] This is one of the analytic properties that was discussed in the footnote in page 452

[20] See *Functional Analysis* [80] and [51].

Proposition 13.3.6: Reflectivity Of Finite Dimensional Vector Spaces

Let V be a finite dimensional vector space. Then $V \cong V^*$.

***Proof*:**
By proposition 13.3.5, since V and V^* are of the same dimension, $V \cong V^*$.

An intuitive way of viewing the reflectively product to reference the intuition presented in the introduction of this section mentioning how functional represent *information*. Each linear function provides some information about a vector-space (prototypical examples would be the projection functions $\pi_{\beta,i} : V \to k$ picking a component of a vector given a choice of basis β). The type of information provided is restricted by the properties of the functions on V, in this case the co-domain is always k, and the functional is always linear. In finite dimension, these functions can be completely characterized by elements in V by the existence of the above isomorphism. The choice of the isomorphism is still an important factor to consider, since there is not natural basis or extra information that allows for favoring one isomorphism over another.

Since the structure of V isomorphic to V^*, it would be interesting if each map $f : V \to W$ can be associated to an appropriate "dual" function f^* where composition is respected, hopefully giving the existence of the functor $(-)^*$ from Vect_k to itself. To start, there is a notion of a dual function:

Definition 13.3.7: Dual map (Transpose)

Let $f : V \to W$ be a linear transformation. Then the *transpose* of f, denoted f^*, is defined as:

$$f^* : W^* \to V^* \qquad f^*(\varphi) = \varphi \circ f$$

A basis of a finite-dimensional V gives an isomorphism $V \cong V^*$ sending each basis vector to its dual functional, and changing the basis can change it: on $V = \mathbb{Q}$ the bases $\{1\}$ and $\{2\}$ give $v \mapsto (w \mapsto vw)$ and $v \mapsto (w \mapsto vw/4)$. So none of them is canonical. The transpose involves no choice. Note that the transpose of a function insures that maps that used to "out of" the space V will now "go into" the space V^* (and similarly for maps that go into V). Thus, this definition matches with our goal for V^* to be the dual of V, and furthermore is independent of any choice of basis. The name transpose comes from the matrix representation of f^*

Proposition 13.3.8: Matrix Representation Of Dual Map

Let $f : V \to W$ be a linear transformation and $A = (a_{ij})$ be the matrix representation of f given some basis β and γ for V and W respectively. Then if $f^* : W^* \to V^*$ is the dual map of f, where W^* and V^* have as basis γ^* and β^*, then the matrix representation A^* of f^* is:

$$A^* = [f^*]_{\gamma^*}^{\beta^*} = (a_{ji}) = A^t$$

Intuitively, in the matrix representation, each entry a_{ij} transposed with entry a_{ji}. For this reason, the map f^* is sometimes called the *transpose* of f.

***Proof*:**
Write $\beta = \{v_1, \ldots, v_n\}$ and $\gamma = \{w_1, \ldots, w_m\}$. By definition 13.2.1, the entries of A are determined by

$$f(v_i) = \sum_{k=1}^{m} a_{ki}\, w_k$$

Fix j and consider the functional $f^*(w_j^*) = w_j^* \circ f \in V^*$. Evaluating on each basis vector v_i gives

$$f^*(w_j^*)(v_i) = w_j^*(f(v_i)) = w_j^*\left(\sum_{k=1}^{m} a_{ki}\, w_k\right) = a_{ji}$$

since $w_j^*(w_k)$ is 1 when $k = j$ and 0 otherwise. The functional $\sum_{i=1}^{n} a_{ji}\, v_i^*$ takes the same value a_{ji} on each v_i, and two linear maps agreeing on the basis β agree on all of V by linearity. Hence

$$f^*(w_j^*) = \sum_{i=1}^{n} a_{ji}\, v_i^*$$

By definition 13.2.1 applied to f^* with domain basis γ^* and codomain basis β^*, the (i, j) entry of $[f^*]_{\gamma^*}^{\beta^*}$ is the coefficient of v_i^* in $f^*(w_j^*)$, which is a_{ji}. Hence $A^* = (a_{ji}) = A^t$.

As a corollary, if A is a nonsingular map $f : V \to W$, then the matrix representation for the map $(f^{-1})^* : V^* \to W^*$ is $(A^{-1})^t$.

Similarly to how the kernel of a linear transformation f provides the needed information to deduce the structure of the image of f, we get the dual equivalent for f^*, given an appropriate "dual" for the kernel:

Definition 13.3.9: Annihilator Of Dual Map

$U \subseteq V$ be a subspace of V. Then the *annihilator* of U is:

$$U^o := \{f \in V^* \mid f(U) = 0\}$$

Note that $V^0 = \{0\}$ and $\{0\}^0 = V$. Another common notation is $U^\perp$, which is pronounced "U perp", which shows how U^0 is related to the orthogonal complement of U. That relation needs an inner product, and is carried out in *Linear Algebra* [31].

Lemma 13.3.10: Properties Of Annihilator

Let $U \subseteq V$ be a subspace. Then:

1. $U^0 \subseteq V^*$ is a subspace
2. if $\dim(V) < \infty$, then $\dim(V) = \dim(U) + \dim(U^0)$

***Proof*:**

1. The zero functional vanishes on U, so $0 \in U^0$ and U^0 is nonempty. If $f, g \in U^0$ and $c \in k$, then for every $u \in U$,

$$(f + cg)(u) = f(u) + cg(u) = 0 + c \cdot 0 = 0$$

so $f + cg \in U^0$. Hence U^0 is closed under addition and scalar multiplication, and is a subspace of V^*.

2. Let $n = \dim(V)$ and consider the restriction map

$$\rho : V^* \to U^* \qquad \rho(f) = f|_U$$

which is linear since restriction commutes with addition and scalar multiplication of functionals. Its kernel is exactly the set of functionals vanishing on U, that is, $\ker(\rho) = U^0$.

We claim ρ is surjective. First, U is finite dimensional: a basis $u_1, \dots, u_k$ of U exists by theorem 13.1.8, and it is a linearly independent subset of V, so $k \leq n$ by corollary 13.1.13. By theorem 13.1.8 again, the linearly independent set $\{u_1, \dots, u_k\}$ is contained in a basis B of V. Given $g \in U^*$, define $f : V \to k$ on the basis B by $f(u_i) = g(u_i)$ for $1 \leq i \leq k$ and $f(b) = 0$ for the remaining $b \in B$, extended linearly, which is possible by corollary 12.3.14. Then $f|_U$ and g are linear maps agreeing on the basis $u_1, \dots, u_k$ of U, so $\rho(f) = g$, proving surjectivity. Hence the image of ρ is U^*.

By proposition 13.3.5, $\dim(V^*) = n$ and $\dim(U^*) = \dim(U)$. Applying the Rank-Nullity theorem (corollary 13.1.18) to ρ gives

$$\dim(V) = \dim(V^*) = \dim(\ker(\rho)) + \dim(\text{im}(\rho)) = \dim(U^0) + \dim(U)$$

as we sought to show.

Proposition 13.3.11: Properties Of Dual Maps

Let V and W be (not necessarily finite dimensional) vector space over k, $f \in \text{Hom}_k(V, W)$ so that $f^* \in \text{Hom}_k(W^*, V^*)$ is its dual map. Then:

1. $\ker(f^*) = (\text{im}(f))^0$ (implying f^* injective if and only if f surjective)
2. $\text{im}(f^*) \subseteq (\ker(f))^0$ is a subspace
3. If $\dim(V), \dim(W) < \infty$, then $\text{im}(f^*) = (\ker(f))^0$ (implying f^* surjective if and only if f injective)

***Proof*:**
Let X be a vector space over k, let $U \subseteq X$ be a subspace, and choose a basis B_U of U (theorem 13.1.8).

Fact (a): every $h \in U^*$ extends to X. Extend B_U to a basis B of X (theorem 13.1.8), and let $\tilde{h} \colon X \to k$ be the linear map with $\tilde{h}(b) = h(b)$ for $b \in B_U$ and $\tilde{h}(b) = 0$ for $b \in B \setminus B_U$

(corollary 12.3.14). Then $\tilde{h}|_U$ and h are linear maps agreeing on the basis B_U of U, so $\tilde{h}|_U = h$.

Fact (b): if $x \in X \setminus U$, then some $\lambda \in U^0$ has $\lambda(x) = 1$. The set $B_U \cup \{x\}$ is linearly independent: in a relation $cx + \sum_b c_b b = 0$ with $b \in B_U$, the coefficient c is 0, since otherwise $x = -c^{-1} \sum_b c_b b \in U$, and then every c_b is 0. Extend $B_U \cup \{x\}$ to a basis B of X, and let λ be the linear map with $\lambda(x) = 1$ and $\lambda(b) = 0$ for the other $b \in B$. Then λ vanishes on the basis B_U of U, so $\lambda \in U^0$.

1. For $\psi \in W^*$, $f^*(\psi) = \psi \circ f$ is the zero functional exactly when $\psi(f(v)) = 0$ for every $v \in V$, that is, when ψ vanishes on $\mathrm{im}(f)$. So $\ker(f^*) = (\mathrm{im}(f))^0$. If f is surjective, then $\ker(f^*) = W^0 = \{0\}$ and f^* is injective. If f is not surjective, Fact (b) with $X = W$, $U = \mathrm{im}(f)$ and some $x \in W \setminus \mathrm{im}(f)$ gives a nonzero element of $(\mathrm{im}(f))^0 = \ker(f^*)$, and f^* is not injective.
2. The image of f^* is a subspace of V^*, since $f^*(\psi)+cf^*(\psi') = f^*(\psi+c\psi')$ for $\psi, \psi' \in W^*$ and $c \in k$. For $\psi \in W^*$ and $v \in \ker(f)$, $f^*(\psi)(v) = \psi(f(v)) = \psi(0) = 0$, so $f^*(\psi) \in (\ker(f))^0$.
3. By (2) it suffices to show $(\ker(f))^0 \subseteq \mathrm{im}(f^*)$. Let $\lambda \in (\ker(f))^0$ and define $h\colon \mathrm{im}(f) \to k$ by $h(f(v)) = \lambda(v)$. It is well defined: if $f(v) = f(v')$, then $v - v' \in \ker(f)$, so $\lambda(v) - \lambda(v') = \lambda(v - v') = 0$. It is linear, since $h(f(v) + cf(v')) = h(f(v + cv')) = \lambda(v + cv') = h(f(v)) + ch(f(v'))$. By Fact (a) with $X = W$ and $U = \mathrm{im}(f)$, h extends to some $\psi \in W^*$, and then $f^*(\psi)(v) = \psi(f(v)) = h(f(v)) = \lambda(v)$ for every $v \in V$, so $\lambda = f^*(\psi)$. Hence $\mathrm{im}(f^*) = (\ker(f))^0$. If f is injective, this is $\{0\}^0 = V^*$, and f^* is surjective. If f is not injective, choose $0 \neq v \in \ker(f)$. Fact (b) with $X = V$, $U = \{0\}$ and $x = v$ gives $\mu \in V^*$ with $\mu(v) = 1$, so $\mu \notin (\ker(f))^0 = \mathrm{im}(f^*)$, and f^* is not surjective, completing the proof.

The first point in proposition 13.3.11 is particularly useful in that in infinite dimensions, f being injective *does not* imply f is surjective. In the right situation, checking the injectivity of a linear transformation is *much* easier than checking surjectivity, and so checking the injectivity of f^* is often advantageous.

The next topic we will cover might at first seem abstract, however it is an important demonstration of the concept of *naturality*. Since we have taken $\mathrm{Hom}_k(V, k)$ and have shown it is a vector-space, we can take the dual of it again:

Definition 13.3.12: Double Dual

Let V be a vector-space and V^* it's dual. Then the *double-dual* of V is the dual of V^*, denoted V^{**}

The double dual has the property of being *naturally isomorphic* to V. To explain the idea of a natural isomorphism, we will show how V is *not* naturally isomorphic to V^*:

Example 13.3.13: Double Dual Motivation

Let V be a finite-dimensional vector space over k and $V^* = \mathrm{Hom}(V, \mathbb{F})$. If $\beta = \{e_1, ..., e_n\}$ is a basis for V, and $\beta^* = \{e_1^*, ..., e_n^*\}$ is the dual basis for V^* where:

$$e_j^*(e_i) = \begin{cases} 1 & i = j \\ 0 & i \neq j \end{cases}$$

Then the maps $e_i \mapsto e_i^*$ are bijective and linear, meaning V and V^* are isomorphic ($V \cong V^*$).

We can further consider $V^{**} = \text{Hom}(\text{Hom}(V, \mathbb{F}), \mathbb{F})$ being the set of all linear maps mapping all elements form $\text{Hom}(V, \mathbb{F})$ to $\mathbb{F}$. We can in similar fashion make an isomorphism $V^* \cong V^{**}$ letting us conclude that $V \cong V^{**}$.

This whole construction started with a choice of basis form V, which need not be unique, and so it's not a "property" of V. However, we can still define an isomorphism between V and V^{**} *without* any reference to a basis. For any $v \in V$, we can define a map

$$(f \mapsto f(v)) : V^* \to \mathbb{F} \qquad (f \mapsto f(v))(g) = g(v)$$

that is, every functional $g \in V^*$ evaluates the value and gets us $g(v)$. This map is sometimes called the evaluation function. Let's switch up the notation for simplicity:

$$ev_v : V^* \to \mathbb{F} \qquad ev_v(g) = g(v)$$

where ev_v stands for evaluate at v. Now, the map $ev \colon V \to \text{Hom}(V^*, \mathbb{F})$, $v \mapsto ev_v$, is an *isomorphism*. For linearity, let $k \in \mathbb{F}$ and $v, w \in V$:

$$ev(k \cdot v) = ev(kv) = ev_{kv} = k \cdot ev_v = kev(v)$$

$$ev(v + w) = ev_{v+w} = ev_v + ev_w = ev(v) + ev(w)$$

where kv represents the vector we get when applying the ring action on v. Note that we essentially used the linearity of the object we are mapping to in order to prove linearity. The map ev is injective: if $ev_v = 0$ and $v = \sum_i c_i e_i$, then $c_j = e_j^*(v) = ev_v(e_j^*) = 0$ for every j, so $v = 0$. By proposition 13.3.5, applied to V and then to V^*, $\dim V^{**} = \dim V^* = \dim V$, so the injective linear map ev is bijective (corollary 13.1.20).

Thus, we defined this isomorphism with *no* reference to a basis on V. We cannot do the same trick for $V \to V^*$, since if we try to do $v \mapsto f(v)$, it is ambiguous which f is meant.

The intuition behind the double-dual having a natural isomorphism is that there is more information to work with. The reader should ponder on what extra information has been provided.

13.3.2 Prelude to Adjoints of Vector Space

Now that we have the basic structure of (finite dimensional) dual spaces, we may return to the discussion of defining V internally or externally. Let's say that you have been given $\text{Hom}_k(V, k)$, but not the structure of V. Is the information in $\text{Hom}_k(V, k)$ sufficient to recover the structure of V? The answer is almost: the following proposition shows how much information we can recover:

Proposition 13.3.14: Recovering V From Its Dual

Let V be some vector-space and V^* its dual.

1. If $v, w \in V$ satisfy $f(v) = f(w)$ for all $f \in V^*$, then
$$v = w$$
that is, the linear map $\mathrm{ev}\colon V \to V^{**}$, $v \mapsto \mathrm{ev}_v$ of example 13.3.13 is injective
2. If V is finite dimensional, then $\mathrm{ev}\colon V \to V^{**}$ is an isomorphism

***Proof*:**

1. Let $u = v - w$ and suppose $u \neq 0$. The set $\{u\}$ is linearly independent, since $cu = 0$ with $c \neq 0$ would give $u = c^{-1}cu = 0$. Extend it to a basis B of V (theorem 13.1.8) and let $f\colon V \to k$ be the linear map with $f(u) = 1$ and $f(b) = 0$ for $b \in B \setminus \{u\}$ (corollary 12.3.14). Then $f(v) - f(w) = f(u) = 1 \neq 0$, contradicting the hypothesis. Hence $u = 0$, that is, $v = w$. Since $\mathrm{ev}_v = \mathrm{ev}_w$ means exactly that $f(v) = f(w)$ for every $f \in V^*$, this is the injectivity of ev.
2. The map ev is linear: for $v, w \in V$, $c \in k$ and $f \in V^*$, $\mathrm{ev}_{v+cw}(f) = f(v) + cf(w) = (\mathrm{ev}_v + c\mathrm{ev}_w)(f)$. It is injective by (1). Applying proposition 13.3.5 to V and then to V^* gives $\dim V^{**} = \dim V^* = \dim V < \infty$, so ev is an injective linear map between vector spaces of the same finite dimension, hence an isomorphism (corollary 13.1.20), completing the proof.

13.3.3 Functor of Points for Vector Spaces

Another way to bring in the intuition from the introduction is to take the dual of a functional $V \to k$, namely to think of elements of V as functions $k \to V$. Every linear transformation $g\colon k \to V$ is of the form
$$t \mapsto tx$$
with $x = g(1)$, since $g(t) = g(t \cdot 1) = tg(1)$, and for every $x \in V$ this formula defines a linear map. Represent these transformations as $g_x : k \to V$. Taking the dual of g_x we get:

$$\begin{aligned} g_x^*(\varphi) &= \varphi \circ g_x \\ &\equiv \varphi(g_x(t)) && \forall t \in k \\ &= \varphi(tx) && \forall t \in k \\ &= t\varphi(x) && \forall t \in k \\ &\equiv g_{\varphi(x)} \end{aligned}$$

Hence g_x^* maps φ to $g_{\varphi(x)} : k \to k$ where $t \mapsto t\varphi(x)$. With the identification between elements of V and the linear transformations $k \to V$, we may interpret this as a functional $V^* \to k$ where:
$$\varphi \mapsto \varphi(x)$$

Given $V \cong V^*$, then if β is the basis defining the isomorphism, each $\varphi \in V^*$ is associated to a vector $v \in V$, namely the vector for which:

$$\begin{pmatrix} \beta_1 \\ \beta_2 \\ \vdots \end{pmatrix} \mapsto \sum_i v_i \beta_i$$

where $\sum_i$ is a finite sum. Then the linear functional $V \to k$ is defined by:

$$\begin{pmatrix} v_1 \\ v_2 \\ \vdots \end{pmatrix} \mapsto \sum_i v_i x_i$$

where again $\sum_i$ is a finite sum since only finitely many v_i (and x_i) are nonzero Let's label this functional f_x. The element $x \in V$ may be interpreted, functionally, as $t \to tx$ or $v \to \sum_i v_i x_i$. Geometrically, the first function can loosely be thought of as defining a magnitude and direction. This is *not* a correct interpretation in infinite dimensions in general, since a magnitude requires a norm and a bare vector space carries none, however it is valid in finite dimension[21]. The second function can is the "dual" notion, where instead of focusing on x, the focus is on how x manipulates every other element. The reader may want to ponder how this relates to the "internal" and "external" way of describing object mentioned at the beginning of section 13.3. The first description, $x \mapsto (\varphi \mapsto \varphi(x))$, is the evaluation map $\mathrm{ev}\colon V \to V^{**}$, which is injective and involves no choice (proposition 13.3.14(1)). The second, $x \mapsto f_x$, is an injective linear map $V \to V^*$, since $f_x(\beta_j) = x_j$ vanishes for every j only when $x = 0$, but it depends on the basis β.

As mentioned, it is not always the case that $V \cong V^*$. This immediately falls apart if V is infinite dimensional. To demonstrate this, let us consider the duality presented above where each $x \in V$ is associated with the functional f_x. The key is that given any basis β for V, $[x]_\beta$ has only finitely many components. Hence, the following valid function $F \in V^*$ is not associated to any f_x:

$$[v]_\beta \to \sum_i v_i$$

where the sum is finite since v when represented as an infinite tuple must only have finitely many nonzero components. The functional F is associated to the sequence $(1, 1, ..., 1, ...)$, namely the sequence where 1 is in each position. No f_x can be associated to F since by construction f_x, when represented as an infinite tuple, must have all but finitely position zero. This immediately shows that V^* is much larger, and hence contains much more information than the elements of V can represent. In fact, V^* contains even more interesting functionals. Consider:

$$(v_1, v_2, ..., v_n, ...) \mapsto (0, v_1, ..., v_{n-1}, ...)$$

Notationally, this may be represented as $f(\beta_i) = \beta_{i+1}$ given a basis β for V. This is called he *right shift operator*. This linear transformation can only be defined since there are infinite dimensions, hence each component may shift over by 1.

There are in fact so many linear functionals on infinite dimensional vector spaces that the study of such spaces is almost always accompanied with additional structure to bring some more regularity to the elements. The core problem stems from the extra flexibility working with infinitely many dimensions entails. Hence, some form of "finiteness" is usually imposed via the introduction of a *norm*,

[21] This interpretation holds true in Hilbert Spaces

for instance one induced by an *inner product*. The transpose makes $(-)^*$ a contravariant functor, since $(g \circ f)^* = f^* \circ g^*$, and it involves no basis. For a finite-dimensional real inner product space V, $v \mapsto \langle -, v\rangle$ is an isomorphism $V \cong V^*$ that depends on no basis. For a linear map $L\colon V \to W$ between finite-dimensional real inner product spaces, transporting L^* through these isomorphisms gives a linear map $L^\dagger\colon W \to V$, the *adjoint* of L, whose matrix in orthonormal bases is $[L]^t$. The exploration of these notions is very fruitful even in finite dimensions, and it is carried out in *Linear Algebra* [31].

Exercise 13.3.1

1. Let V be finite dimensional and $U \subseteq V$ a subspace. Show that $U^{00} \cong U$. If $\widehat{(___)}$ is the natural embedding of V into V^{**}, show that $\hat{U} = U^{00}$.
2. Let V be a finite dimensional vector space and $U_1, U_2 \subseteq V$ subspaces. Show that:
    1. $(U_1 + U_2)^0 = U_1^0 \cap U_2^0$
    2. $(U_1 \cap U_2)^0 = U_1^0 + U_2^0$
    3. if $W \subseteq V$ is a subspace, then $(V/W)^* \cong W^0$
3. Show that $(-)^*$ is a contravariant functor from the category of vector spaces over k to itself, that is, $(g \circ f)^* = f^* \circ g^*$ for linear maps $f\colon U \to V$ and $g\colon V \to W$, and $(\mathrm{id}_V)^* = \mathrm{id}_{V^*}$.

13.3.4 Multilinear Forms

Studying linear functionals allow us to give some scalar value to vectors. However, this is sometimes not enough: it is very common in mathematics that one of the two scenarios occur (we will see examples of these in this and coming section[22])

1. We want to study many functional on spaces simultaneously (ex. both V and V^*)
2. We require many copies of the same space to have enough "data" to define the desired functional

In this section, we elaborate on the theory allowing us to do just that, give some examples elaborating the above intuitions, and in the coming section we will see how these are of great use in defining some invariants for linear transformations and bringing in geometry into vector-spaces:

[22]There are also many examples in differential geometry, such as covariant/contravariant/mixed tensor fields on a manifold

Definition 13.3.15: Bilinear and Multilinear Maps

Let V and W be vector spaces over k. Then a map $\varphi : V \times W \to k$ is called *bilinear* if

1. for any $v \in V$, the map $\varphi(v, \cdot) : W \to k$ mapping $w \mapsto \varphi(v, w)$ is linear
2. for any $w \in W$, the map $\varphi(\cdot, w) : V \to k$ mapping $v \mapsto \varphi(v, w)$ is linear.

More generally, if $V_1, V_2, ..., V_n$ are vector-space sover k, then $\varphi : V_1 \times V_2 \times \cdots \times V_n \to k$ is *multilinear* (or n-linear if the number of variables is known) if for all i, $1 \leq i \leq n$, given fixed $v_1, v_2, ..., v_{i-1}, v_{i+1}, ..., v_n$, the map

$$\varphi(v_1, v_2, ..., v_{i-1}, \cdot, v_{i+1}..., v_n)$$

is linear. Two important types of multilinear maps are:

- (Symmetric) for any $v_i, v_j \in V$:

$$\varphi(v_1, ..., v_i, ..., v_j, ..., v_n) = \varphi(v_1, ..., v_j, ..., v_i, ..., v_n)$$

- (Alternating) for any $v_i, v_j \in V$:

$$\varphi(v_1, ..., v_i, ..., v_j, ..., v_n) = -\varphi(v_1, ..., v_j, ..., v_i, ..., v_n)$$

13.3.16 WARNING Since we are now dealing with multilinear maps, these are *no longer morphisms in the category of* Vect_k! Hence, multilinear maps are a different object of study. In chapter 15, we will show how we can study multilinear maps via linear algebra.

Example 13.3.17: Bilinear and Multilinear Maps

1. Let $\varphi : V \times V^* \to k$ be defined by $(v, f) \mapsto f(v)$. Then φ is bilinear
2. Let $V = \mathbb{R}^n$ be a vector-space over $\mathbb{R}$ and take $\varphi : \mathbb{R}^n \times \mathbb{R}^n \to \mathbb{R}$ to be defined as:

$$\varphi\left(\begin{pmatrix} x_1 \\ x_2 \\ \vdots \\ x_n \end{pmatrix}, \begin{pmatrix} y_1 \\ y_2 \\ \vdots \\ y_n \end{pmatrix}\right) = \sum_{i=1}^{n} x_i y_i$$

   Then φ is bilinear, and is called the *dot product* or *scalar product* of two vectors $x, y \in \mathbb{R}^n$
3. Let $\mathbb{R}$ be a vector-space over itself, and take $V : \mathbb{R} \times \mathbb{R} \times \cdots \times \mathbb{R} \to \mathbb{R}$. Then the map that multiplies all the elements:

$$V(x_1, x_2, ..., x_n) = x_1 x_2 \cdots x_n$$

   is a n-linear. As a paticualr example, consider $\varphi : \mathbb{R} \times \mathbb{R} \times \mathbb{R} \to \mathbb{R}$, and imagine any 3-tulpe (x_1, x_2, x_3) represents the length, width, and height of a shape. Then $V(x_1, x_2, x_3) = x_1 x_2 x_3$ will give the volume of a rectangular prism (or a cube if $x_1 = x_2 = x_3$). The fact that

multiplication produces a natural multi-linear map means that multilienar maps show up a lot in geometry. it is for this reason that multilinear maps are sometimes called *volume forms*. We will see more of these in section 16.3.

4. (If you know some calculus) Let $V = C([0,1], \mathbb{R})$ be the set of all continuous functions from $[0,1]$ to $\mathbb{R}$. Then define $\varphi : V \times V \to \mathbb{R}$ to be:

$$\varphi(f,g) = \int_0^1 f(t)g(t)\,dt$$

Then φ is bilinear. This is the infinite dimensional equivalent of the dot product.

In the rest of this section, we will focus on Bilinear forms: the results can easily be generlized using induction to Mutilinear forms. The first thing worth trying to find is wether there is still a reasonable notion of matrix representaiton of bilinear forms, since they are no longer linear maps. The following definition and lemma give us jut that:

Definition 13.3.18: Bilinear Form Matrix Representation

Let V and W be finite dimensional vector spaces over k of dimension n and m and with basis β, γ respectively. Let $\varphi : V \times W \to k$ a bilinear form. Then define the *matrix representation* of φ to be:

$$[\varphi]_{\beta,\gamma} := (\varphi(\beta_i, \gamma_j))_{\substack{1 \le i \le n \\ 1 \le j \le m}}$$

Lemma 13.3.19: Bilinear Form Matrix Representation

Let V and W be finite dimensional vector spaces over k of dimension n and m and with basis β, γ respectively. Let $\varphi : V \times W \to k$ a bilinear form. Then

$$\varphi(v,w) = [v]_\beta^t [\varphi]_{\beta,\gamma} [w]_\gamma$$

***Proof*:**
Write $v = \sum_{i=1}^n a_i \beta_i$ and $w = \sum_{j=1}^m b_j \gamma_j$, so that $[v]_\beta$ has entries a_i and $[w]_\gamma$ has entries b_j. Bilinearity of φ expands each argument separately:

$$\varphi(v,w) = \varphi\Big(\sum_i a_i\beta_i,\ \sum_j b_j\gamma_j\Big) = \sum_{i=1}^n \sum_{j=1}^m a_i b_j\, \varphi(\beta_i, \gamma_j)$$

On the other side, the (i,j) entry of $[\varphi]_{\beta,\gamma}$ is $\varphi(\beta_i, \gamma_j)$, so the matrix product is $[v]_\beta^t [\varphi]_{\beta,\gamma} [w]_\gamma = \sum_i \sum_j a_i\, \varphi(\beta_i, \gamma_j)\, b_j$. The two sums agree term by term.

Definition 13.3.20: Orthogonal

Let $\varphi : V \times V \to k$ be a bilinear form and $S \subseteq V$ a *subset*. Then the set:

$$S^{\perp} := \{y \in V \mid \varphi(x, y) = 0 \text{ for every } x \in S\}$$

is called the *orthogonal complement* of S. If $\varphi(x, y) = 0$, then x is *perpendicular* to y, written $x \perp y$. If $x \perp y$ for all $y \in S$, then $x \perp S$.

The orthogonal complement is always a subspace, whatever the subset S was.

Lemma 13.3.21: The Orthogonal Complement Is a Subspace

Let $\varphi\colon V \times V \to k$ be a bilinear form and $S \subseteq V$ any subset. Then $S^{\perp}$ is a subspace of V, and $S^{\perp} = (\operatorname{span} S)^{\perp}$.

***Proof*:**

Linearity of φ in its second argument gives $\varphi(x, 0) = 0$ for every x, so $0 \in S^{\perp}$. If $y, y' \in S^{\perp}$ and $a \in k$, then for every $x \in S$

$$\varphi(x, y + ay') = \varphi(x, y) + a\,\varphi(x, y') = 0 + a \cdot 0 = 0$$

so $y + ay' \in S^{\perp}$, and $S^{\perp}$ is a subspace.

For the second claim, $S \subseteq \operatorname{span} S$ forces $(\operatorname{span} S)^{\perp} \subseteq S^{\perp}$. Conversely let $y \in S^{\perp}$ and let $x = \sum_{i=1}^{m} a_i x_i$ with $x_i \in S$. Linearity in the first argument gives $\varphi(x, y) = \sum_i a_i \varphi(x_i, y) = 0$, so $y \in (\operatorname{span} S)^{\perp}$, as we sought to show.

Taking S to be all of V produces the subspace on which the form carries no information at all, and the form deserves a name according to whether that subspace is trivial.

Definition 13.3.22: The Radical and Nondegeneracy

Let $\varphi\colon V \times V \to k$ be a bilinear form. The *radical* of φ is the subspace

$$\operatorname{rad}(\varphi) := V^{\perp} = \{y \in V \mid \varphi(x, y) = 0 \text{ for every } x \in V\}$$

The form φ is *nondegenerate* if $\operatorname{rad}(\varphi) = 0$, and *degenerate* otherwise.

For a symmetric form the radical is the same computed on either side, so no ambiguity arises from having used the second argument. The radical is detected by the matrix of the form in any single basis, which is the form in which nondegeneracy is checked in practice.

Lemma 13.3.23: Nondegeneracy and the Matrix of the Form

Let V be finite dimensional with basis β, let $\varphi\colon V \times V \to k$ be a bilinear form, and let $A = [\varphi]_{\beta,\beta}$ be its matrix (definition 13.3.18). Then

$$\operatorname{rad}(\varphi) = \left\{ y \in V \;\middle|\; A^t[y]_\beta = 0 \right\}$$

and consequently φ is nondegenerate if and only if A is invertible. The criterion does not depend on which basis β was chosen, since the left-hand side does not.

***Proof*:**
By lemma 13.3.19, $\varphi(x,y) = [x]_\beta^t A[y]_\beta$ for all $x, y \in V$. Fix y. Then $y \in \operatorname{rad}(\varphi)$ means $[x]_\beta^t A[y]_\beta = 0$ for every $x \in V$, and as x ranges over V the coordinate vector $[x]_\beta$ ranges over all of k^n. A vector $u \in k^n$ satisfies $w^t u = 0$ for every $w \in k^n$ if and only if $u = 0$, so the condition is $A[y]_\beta = 0$. Transposing the defining relation gives the displayed form. Hence $\operatorname{rad}(\varphi) = 0$ if and only if A has trivial kernel, which for a square matrix is invertibility.

The final sentence needs no comparison of bases: $\operatorname{rad}(\varphi)$ was defined without reference to any basis, so if A is invertible for one choice of β the radical is zero, and then the same equivalence run backwards makes the matrix invertible for every other choice, completing the proof.

Exercise 13.3.2

1. Let $f\colon V \times W \to k$ be a bilinear form on a pair of spaces, and write $W^\perp := \{v \in V \mid f(v,w) = 0 \text{ for all } w \in W\}$ and $V^\perp := \{w \in W \mid f(v,w) = 0 \text{ for all } v \in V\}$ for its two kernels. Show that f descends to a well-defined bilinear form $\bar{f}\colon V/W^\perp \times W/V^\perp \to k$, and that $\bar{f}$ is non-degenerate in each variable.

13.4 Linear Operators Invariants: Trace and Determinant

In this section, we will go over to common functionals on $M_n(k)$ (equivalently, $\operatorname{End}_k(V)$ for an n-dimensional vector-space) that give more insight on linear transformations. A good chunk of the following theory works well over more general rings, and so we will sometimes work over a general commutative ring R.

The first functional on $M_n(k)$ we will define is called the *trace*, and it takes the same value on similar matrices (that is, on matrices related by a change of basis):

Definition 13.4.1: Trace

Let R be a commutative ring and $M_n(R)$ the collection of all $n \times n$ matrices over R. Then $\operatorname{tr} : M_n(R) \to R$ is the map:

$$\operatorname{tr}(A) = \sum_{i=1}^{n} a_{ii}$$

The trace is studied for the following very useful properties:

Proposition 13.4.2: Properties of Trace

Let R be a commutative ring and $A, B \in M_n(R)$. Then:

1. $\text{tr}(A) = \text{tr}(A^t)$
2. $\text{tr}(AB) = \text{tr}(BA)$

***Proof*:**
Write $A = (a_{ij})$ and $B = (b_{ij})$.

1. The (i,i) entry of $A^t = (a_{ji})$ is a_{ii}, so $\text{tr}(A^t) = \sum_{i=1}^n a_{ii} = \text{tr}(A)$.
2. The (i,i) entry of AB is $\sum_{l=1}^n a_{il}b_{li}$ and the (l,l) entry of BA is $\sum_{i=1}^n b_{li}a_{il}$, so

$$\text{tr}(AB) = \sum_{i=1}^n \sum_{l=1}^n a_{il}b_{li} \qquad \text{tr}(BA) = \sum_{l=1}^n \sum_{i=1}^n b_{li}a_{il}$$

Since R is commutative, $a_{il}b_{li} = b_{li}a_{il}$ for all i and l, and the two finite double sums have the same terms. Hence $\text{tr}(AB) = \text{tr}(BA)$, as claimed.

As a consequence, if A and B are similar so that there exists a P such that $A = PBP^{-1}$, then:

$$\text{tr}(A) = \text{tr}(PBP^{-1}) = \text{tr}(P(BP^{-1})) = \text{tr}((BP^{-1})P) = \text{tr}(B(P^{-1}P)) = \text{tr}(B)$$

Hence the trace is invariant under change of basis, making it a good tool to study linear maps without needing to pick a basis. Let V be a finite dimensional vector space over k and $f\colon V \to V$ a linear map. If β and γ are bases of V, then the matrices $[f]_\beta^\beta$ and $[f]_\gamma^\gamma$ of f with respect to β and to γ are similar by lemma 13.2.16(4), so they have the same trace, and the following definition does not depend on the basis:

Definition 13.4.3: Trace Of Linear Map

Let V be a finite dimensional vector space and $f : V \to V$ a linear map, and let β be a basis of V. Then define $\text{tr}(f)$ to be

$$\text{tr}(f) := \text{tr}([f]_\beta^\beta)$$

the trace of the matrix of f with respect to β in both the domain and the codomain.

Corollary 13.4.4: Trace Of Dual

Let V be a finite dimensional vector space, $f : V \to V$ a linear map and $f^* : V^* \to V^*$ its dual map. Then:

$$\text{tr}(f) = \text{tr}(f^*)$$

***Proof*:**
Let β be a basis of V, let β^* be the dual basis of V^* (proposition 13.3.5), and let $A = [f]_\beta^\beta$, so that $\text{tr}(f) = \text{tr}(A)$ by definition 13.4.3. By proposition 13.3.8, applied with $W = V$ and $\gamma = \beta$, the

matrix of f^* with respect to β^* in both the domain and the codomain is A^t. So $\operatorname{tr}(f^*) = \operatorname{tr}(A^t)$ by definition 13.4.3, computed in the basis β^*, and $\operatorname{tr}(A^t) = \operatorname{tr}(A)$ by proposition 13.4.2(1). Hence $\operatorname{tr}(f^*) = \operatorname{tr}(f)$, completing the proof.

The next map is a very common multilinear form that will be used extensively: this form will also be independnet of basis, but with the extra information giving a very clear geometric picture of how a linear transformation effects a 1-cube in $\mathbb{R}^n$:

Definition 13.4.5: Determinant

Let R be a commutative ring and $A = (a_{ij}) \in M_n(R)$ a square matrix. then the *determinant* of A is a map $\det : M_n(R) \to R$:

$$\det(A) := \sum_{\sigma \in S_n} (-1)^\sigma \prod_{i=1}^{n} a_{i\sigma(i)} \in R$$

Proposition 13.4.6: Properties Of The Determinant

Let R be a commutative ring and $A \in M_n(R)$. Then:

1. $\det(I_n) = 1$.
2. $\det(A) = \det(A^t)$, here $(a_{ij})^t = (a_{ji})$.
3. (multilinearity) det is R-linear in each column separately: if the j-th column of A is $cu + c'u'$ for $c, c' \in R$ and column vectors u, u', and if A_u, $A_{u'}$ denote the matrices agreeing with A outside column j and having u, respectively u', in column j, then

   $$\det(A) = c \det(A_u) + c' \det(A_{u'})$$

   By (2) the same holds for rows.
4. (alternating) If two columns of A are equal then $\det(A) = 0$. The same holds for rows. Combined with (3), if one column is a scalar multiple of another then $\det(A) = 0$.
5. (permuting rows) If A_τ denotes the matrix whose i-th row is the $\tau(i)$-th row of A, for $\tau \in S_n$, then $\det(A_\tau) = (-1)^\tau \det(A)$.

***Proof*:**
All five are read off the defining sum.

1. For $A = I_n$ the product $\prod_i \delta_{i\sigma(i)}$ vanishes unless $\sigma(i) = i$ for every i, so only $\sigma = \mathrm{id}$ contributes, and it contributes 1.
2. By definition $\det(A^t) = \sum_\sigma (-1)^\sigma \prod_i a_{\sigma(i)i}$. Re-indexing the product by $j = \sigma(i)$ gives $\prod_i a_{\sigma(i)i} = \prod_j a_{j\sigma^{-1}(j)}$, and $(-1)^\sigma = (-1)^{\sigma^{-1}}$ since a permutation and its inverse have the same parity. As σ runs over S_n so does σ^{-1}, so the two sums agree term for term.
3. In the term indexed by σ, exactly one factor is drawn from column j, namely $a_{\sigma^{-1}(j)\,j}$.

Each term is therefore R-linear in column j with the other columns held fixed, and a sum of such terms is too.

4. Suppose columns $j \neq k$ of A are equal, and let $\tau = (j\ k)$. Since $a_{ij} = a_{ik}$ for all i, one has $a_{i\,\tau(m)} = a_{im}$ for every i and m, and hence

$$\prod_i a_{i\,\tau\sigma(i)} = \prod_i a_{i\sigma(i)}$$

while $(-1)^{\tau\sigma} = -(-1)^{\sigma}$. The assignment $\sigma \mapsto \tau\sigma$ is an involution of S_n without fixed points, so it partitions S_n into pairs whose two terms are negatives of one another. The sum is therefore 0. Note that this argument cancels terms exactly and so does not require 2 to be invertible in R. The statement for rows follows by (2), and the statement for proportional columns by pulling the scalar out with (3).

5. By definition $\det(A_\tau) = \sum_\sigma (-1)^\sigma \prod_i a_{\tau(i)\sigma(i)}$. Substituting $j = \tau(i)$ turns the product into $\prod_j a_{j\,\sigma\tau^{-1}(j)}$. Writing $\rho = \sigma\tau^{-1}$, so that $(-1)^\sigma = (-1)^\rho(-1)^\tau$, and letting ρ run over S_n as σ does,

$$\det(A_\tau) = (-1)^\tau \sum_{\rho \in S_n} (-1)^\rho \prod_j a_{j\rho(j)} = (-1)^\tau \det(A)$$

completing the proof.

The determinant is multiplicative, and this holds for all square matrices over a commutative ring, not only invertible ones. The proof is a direct expansion of the defining sum, with proposition 13.4.6(4) killing every term that is not indexed by a permutation.

Proposition 13.4.7: Multiplicativity of the Determinant

Let R be a commutative ring and let $A, B \in M_n(R)$. Then

$$\det(AB) = \det(A)\det(B)$$

***Proof*:**
Write $A = (a_{ij})$ and $B = (b_{ij})$, so that $(AB)_{ij} = \sum_k a_{ik}b_{kj}$. Expanding the defining sum,

$$\det(AB) = \sum_{\sigma \in S_n} (-1)^\sigma \prod_{i=1}^{n} \left(\sum_{k=1}^{n} a_{ik} b_{k\sigma(i)} \right)$$

Expanding the product over i amounts to choosing an index k for each i, that is, a function $f\colon \{1,\dots,n\} \to \{1,\dots,n\}$, so

$$\det(AB) = \sum_f \left(\prod_{i=1}^{n} a_{if(i)} \right) \left(\sum_{\sigma \in S_n} (-1)^\sigma \prod_{i=1}^{n} b_{f(i)\sigma(i)} \right)$$

the sum being over all n^n such functions. For fixed f, let B_f be the matrix whose i-th row is the $f(i)$-th row of B, so that $(B_f)_{ij} = b_{f(i)j}$. The inner sum is exactly $\det(B_f)$.

If f is not injective, say $f(i) = f(i')$ with $i \neq i'$, then B_f has two equal rows and $\det(B_f) = 0$ by proposition 13.4.6(4). Only the injective f survive, and an injective self-map of a finite set is a

permutation, so the sum runs over $f = \tau \in S_n$. For such an f, B_τ is B with its rows permuted by τ, so $\det(B_\tau) = (-1)^\tau \det(B)$ by proposition 13.4.6(5). Therefore

$$\det(AB) = \sum_{\tau \in S_n} \left(\prod_{i=1}^{n} a_{i\tau(i)} \right) (-1)^\tau \det(B) = \left(\sum_{\tau \in S_n} (-1)^\tau \prod_{i=1}^{n} a_{i\tau(i)} \right) \det(B) = \det(A) \det(B)$$

as we sought to show.

A block diagonal matrix has the determinant one would hope for. This is the computation that makes determinants of matrices assembled out of smaller ones tractable.

Proposition 13.4.8: Determinant of a Block Diagonal Matrix

Let R be a commutative ring and let $M \in M_n(R)$ be block diagonal with square diagonal blocks $B_1, \ldots, B_m$, so that $M_{uv} = 0$ whenever u and v lie in different blocks. Then

$$\det(M) = \prod_{t=1}^{m} \det(B_t)$$

***Proof*:**

Index the rows and columns of M by pairs (t, u), where t names the block and u the position inside it, so that $M_{(t,u),(t',u')}$ is $(B_t)_{uu'}$ when $t = t'$ and 0 otherwise. A permutation σ of the index set contributes a nonzero term to the defining sum only if σ maps each block into itself, since otherwise some factor $M_{(t,u),\sigma(t,u)}$ has $t' \neq t$ and vanishes. Such a σ is precisely a tuple $(\sigma_1, \ldots, \sigma_m)$ of permutations of the individual blocks, acting as $\sigma(t, u) = (t, \sigma_t(u))$.

These block permutations move disjoint sets of indices, so σ is the product of the commuting permutations they determine and $(-1)^\sigma = \prod_t (-1)^{\sigma_t}$, the sign being a homomorphism. Hence

$$\det(M) = \sum_{(\sigma_1, \ldots, \sigma_m)} \prod_{t=1}^{m} (-1)^{\sigma_t} \prod_{u} (B_t)_{u\sigma_t(u)} = \prod_{t=1}^{m} \left(\sum_{\sigma_t} (-1)^{\sigma_t} \prod_{u} (B_t)_{u\sigma_t(u)} \right) = \prod_{t=1}^{m} \det(B_t)$$

the middle step being the distributive law, since the tuples range independently over the factors, completing the proof.

Determinants detect nonsingular matrices. For a linear map $f\colon \mathbb{R}^2 \to \mathbb{R}^2$, $|\det f|$ is the area of the image of the unit square, a parallelogram, and when $\det f \neq 0$ its sign records whether f preserves orientation. The image of the square is flattened to a segment or a point exactly when f is not invertible, that is, when $\det f = 0$ (see also *Linear Algebra* [31]).

Proposition 13.4.9: Elementary Matrices And Determinant

Let R be a commutative ring, let $A \in M_n(R)$, and let A' be the matrix obtained from A by the row operation named in each item. Then

1. (switching two rows) $\det(A') = -\det(A)$
2. (adding r times one row to a different row, $r \in R$) $\det(A') = \det(A)$
3. (multiplying one row by $c \in R$, for instance by a unit) $\det(A') = c\det(A)$

The same three formulas hold for the corresponding column operations.

***Proof*:**
By proposition 13.4.6(3) and (2), det is R-linear in each row when the other rows are held fixed.

1. If A' is A with rows $k \neq l$ interchanged, then the ith row of A' is the $\tau(i)$th row of A for the transposition $\tau = (k\ l)$. By proposition 13.4.6(5), $\det(A') = (-1)^\tau \det(A) = -\det(A)$, since a transposition has sign -1 (theorem 1.2.20(3)).
2. Let A' be A with its kth row ρ_k replaced by $\rho_k + r\rho_l$, where $l \neq k$ and ρ_l is the lth row. Linearity in row k gives $\det(A') = \det(A) + r\det(A'')$, where A'' is A with ρ_k replaced by ρ_l. The matrix A'' has two equal rows, so $\det(A'') = 0$ by proposition 13.4.6(4), and $\det(A') = \det(A)$.
3. If A' is A with its kth row multiplied by c, linearity in row k gives $\det(A') = c\det(A)$.

If A' is obtained from A by a column operation, then $(A')^t$ is obtained from A^t by the corresponding row operation, and det is unchanged by transposition (proposition 13.4.6(2)), so the three formulas hold for column operations as well, completing the proof.

Over any commutative ring, the inverse of an invertible matrix A is $\det(A)^{-1}$ times a matrix whose entries are determinants of matrices built from A (proposition 13.4.12).

Definition 13.4.10: Adjugate Matrix

Let R be a commutative ring and $A \in M_n(R)$, and let $e_1, \ldots, e_n$ be the standard basis of R^n. For a column vector $u \in R^n$ and $1 \leq j \leq n$, write $A_j(u)$ for the matrix obtained from A by replacing its jth column with u. The *cofactors* of A are $c_{ij}(A) = \det(A_j(e_i))$ for $1 \leq i, j \leq n$, and the *adjugate* of A is the matrix $\operatorname{adj}(A) \in M_n(R)$ whose (j, i) entry is $c_{ij}(A)$.

Proposition 13.4.11: The Adjugate Identity

Let R be a commutative ring and $A \in M_n(R)$. Then

1. (expansion along a column) $\det(A_j(u)) = \sum_{i=1}^n u_i c_{ij}(A)$ for every $u \in R^n$ and $1 \leq j \leq n$
2. $\operatorname{adj}(A)A = A\operatorname{adj}(A) = \det(A)I_n$

***Proof*:**

1. Since $u = \sum_i u_i e_i$ and det is R-linear in the jth column (proposition 13.4.6(3)),

$$\det(A_j(u)) = \sum_{i=1}^{n} u_i \det(A_j(e_i)) = \sum_{i=1}^{n} u_i c_{ij}(A)$$

2. *Step 1:* $\operatorname{adj}(A)A = \det(A) I_n$. Let a_l be the lth column of A. By (1), the (j,l) entry of $\operatorname{adj}(A)A$ is

$$\sum_{i=1}^{n} c_{ij}(A) a_{il} = \det(A_j(a_l))$$

For $l = j$ this is $\det(A_j(a_j)) = \det(A)$. For $l \neq j$ the matrix $A_j(a_l)$ has its jth and lth columns both equal to a_l, so the entry is 0 (proposition 13.4.6(4)).

Step 2: a cofactor computed by rows. Fix i and j, and let X be A with its jth row replaced by the row vector e_i^t. We claim $\det(X) = \det(A_i(e_j))$. Let Z be the matrix that agrees with A outside row j and column i, has jth row e_i^t and has ith column e_j (the two prescriptions agree at position (j,i), where both give 1). The ith column of X is $e_j + \sum_{k \neq j} a_{ki} e_k$, so linearity in column i (proposition 13.4.6(3)) gives $\det(X) = \det(X_i(e_j)) + \sum_{k \neq j} a_{ki} \det(X_i(e_k))$. Here $X_i(e_j) = Z$, and for $k \neq j$ the jth row of $X_i(e_k)$ is zero, so $\det(X_i(e_k)) = 0$ by linearity in that row. Hence $\det(X) = \det(Z)$. Next, the jth row of $Y = A_i(e_j)$ is $e_i^t + \sum_{l \neq i} a_{jl} e_l^t$, so linearity in row j gives $\det(Y) = \det(Y') + \sum_{l \neq i} a_{jl} \det(Y_l)$, where Y' and Y_l are Y with its jth row replaced by e_i^t and by e_l^t. Here $Y' = Z$, and for $l \neq i$ the ith column of Y_l is zero, so $\det(Y_l) = 0$ by linearity in that column. Hence $\det(Y) = \det(Z)$, which proves the claim.

Step 3: $\operatorname{adj}(A^t) = \operatorname{adj}(A)^t$. The transpose of $(A^t)_j(e_i)$ is the matrix X of Step 2, so by proposition 13.4.6(2) and Step 2, the (j,i) entry of $\operatorname{adj}(A^t)$ is

$$c_{ij}(A^t) = \det(X) = \det(A_i(e_j)) = c_{ji}(A)$$

which is the (i,j) entry of $\operatorname{adj}(A)$, that is, the (j,i) entry of $\operatorname{adj}(A)^t$.

Step 4: $A \operatorname{adj}(A) = \det(A) I_n$. Step 1 for A^t gives $\operatorname{adj}(A^t)A^t = \det(A^t) I_n = \det(A) I_n$. Over the commutative ring R, $(XY)^t = Y^t X^t$, since both have (a,b) entry $\sum_c x_{bc} y_{ca}$. Transposing and using Step 3 gives $A \operatorname{adj}(A) = \det(A) I_n$, completing the proof.

Proposition 13.4.12: Invertibility And Determinants

Let R be a commutative ring. Then:

1. $A \in M_n(R)$ is invertible if and only if $\det(A)$ is a unit in R, and in that case $A^{-1} = \det(A)^{-1}\operatorname{adj}(A)$
2. the determinant is a homomorphism $\det : \mathrm{GL}_n(R) \to R^\times$, that is, for any $A, B \in \mathrm{GL}_n(R)$:
$$\det(A \cdot B) = \det(A) \cdot \det(B)$$

***Proof*:**

1. If A is invertible, then $\det(A)\det(A^{-1}) = \det(AA^{-1}) = \det(I_n) = 1$ by proposition 13.4.7 and proposition 13.4.6(1), so $\det(A)$ is a unit. Conversely, let $\det(A)$ be a unit and $B = \det(A)^{-1}\operatorname{adj}(A)$. By proposition 13.4.11(2), $AB = \det(A)^{-1}A\operatorname{adj}(A) = I_n$ and $BA = \det(A)^{-1}\operatorname{adj}(A)A = I_n$, so A is invertible with $A^{-1} = B$.
2. By (1), $\det(A)$ is a unit for every $A \in \mathrm{GL}_n(R)$, so det maps $\mathrm{GL}_n(R)$ into $R^\times$, and $\det(AB) = \det(A)\det(B)$ for all $A, B \in M_n(R)$ by proposition 13.4.7, completing the proof.

Over an integral domain, a vanishing determinant is the same as a nonzero solution of $Ax = 0$:

Proposition 13.4.13: Determinant And Kernel Over An Integral Domain

Let R be an integral domain and $A \in M_n(R)$. Then $\det(A) = 0$ if and only if $Ax = 0$ for some nonzero $x \in R^n$.

***Proof*:**

Suppose $Ax = 0$ with $x \neq 0$, and choose i with $x_i \neq 0$. By proposition 13.4.11(2), $\det(A)x = \operatorname{adj}(A)Ax = 0$, so $\det(A)x_i = 0$, and $\det(A) = 0$ as R is an integral domain.

Conversely, suppose $\det(A) = 0$, and let K be the field of fractions of R (definition 9.5.2), so that $A \in M_n(K)$ with the same determinant. As 0 is not a unit of K, the matrix A is not invertible in $M_n(K)$ (proposition 13.4.12(1)), so it is not nonsingular (proposition 13.2.10): $Ay = 0$ for some nonzero $y \in K^n$. Write $y_i = r_i/s_i$ with $r_i, s_i \in R$ and $s_i \neq 0$, and let $s = s_1 \cdots s_n \neq 0$. Then $x = sy$ lies in R^n, it is nonzero since $sy_i \neq 0$ whenever $y_i \neq 0$, and $Ax = sAy = 0$, completing the proof.

We will finish off this section with an application of determinants to solve systems of linear equations. This will become particularly useful for a few proofs in the book[23].

[23]The adjugate identity (proposition 13.4.11), which is the form of Cramer's rule that holds without assuming that $\det(A)$ is a unit, is the form used in *Commutative Algebra* proposition 26.1.4.

Proposition 13.4.14: Cramer's Rule

Let R be a commutative ring, let $A \in M_n(R)$ with $\det(A)$ a unit of R, and let $b \in R^n$. For $1 \leq j \leq n$ let $A^{(j)}$ be the matrix obtained by replacing the jth column of A by the column vector b. Then the system $Ax = b$ has exactly one solution $x \in R^n$, given by

$$x_j = \det(A)^{-1} \det(A^{(j)}) \qquad 1 \leq j \leq n$$

***Proof*:**

By proposition 13.4.12(1), A is invertible with $A^{-1} = \det(A)^{-1} \operatorname{adj}(A)$. If $Ax = b$, then $x = A^{-1}Ax = A^{-1}b$, and $x = A^{-1}b$ is a solution, since $A(A^{-1}b) = b$. So the system has exactly one solution, $x = \det(A)^{-1} \operatorname{adj}(A)b$. Its jth entry is

$$x_j = \det(A)^{-1} \sum_{i=1}^{n} c_{ij}(A) b_i = \det(A)^{-1} \det(A_j(b)) = \det(A)^{-1} \det(A^{(j)})$$

by proposition 13.4.11(1), since $A^{(j)} = A_j(b)$, as we sought to show.

A determinant also measures the size of the parallelepiped spanned by n vectors of $\mathbb{R}^n$:

Definition 13.4.15: Volume

Let $e = (e_1, e_2, \ldots, e_n)$ be the standard basis of $\mathbb{R}^n$. For vectors $v_1, \ldots, v_n \in \mathbb{R}^n$ write $v_j = \sum_{i=1}^{n} a_{ij} e_i$ and let $A = (a_{ij}) \in M_n(\mathbb{R})$, the matrix whose jth column is v_j. Then the *volume* of $v = (v_1, \ldots, v_n)$ is

$$\operatorname{vol}(v) = |\det(A)|$$

The absolute value around $\det(A)$ is to eliminate orientation information. Geometrically, when $v_1, v_2, ..., v_n$ are linearly independent, $\operatorname{vol}(v)$ is the volume of the parallelepiped

$$P = \left\{ \sum_{i=1}^{n} c_i v_i \;\middle|\; 0 \leq c_i < 1 \right\}$$

spanned by them, and the intuitive notion of volume of P agrees with this definition. The case $v = e$ gives $A = I_n$, so the standard basis e has volume $\det(I_n) = 1$ (proposition 13.4.6(1)). The volume depends on the family and not only on its members: for $n = 2$ the family $v = (e_1, e_1)$ has volume 0, since its matrix A has two equal columns (proposition 13.4.6(4)). Since $\det(A^t) = \det(A)$ (proposition 13.4.6(2)), the volume is also the absolute value of the determinant of the matrix whose rows are the v_j.

Exercise 13.4.1

1. Let $A \in M_n(k)$, $k \subseteq \mathbb{C}$. Show that $\det(\overline{A}) = \overline{\det(A)}$ where we define $\overline{A}$ component-wise to be $(\overline{A})_{ij} = \overline{a_{ij}}$ with $\overline{a_{ij}}$ being the complex conjugate ($\overline{x + iy} = x - iy$)
2. Let R be a commutative ring and $A \in M_n(R)$, and for $1 \leq i, j \leq n$ let $A^{(ij)} \in M_{n-1}(R)$ be the matrix obtained from A by deleting row i and column j. Show that the cofactors

of definition 13.4.10 are $c_{ij}(A) = (-1)^{i+j}\det(A^{(ij)})$, and deduce the expansion $\det(A) = \sum_{i=1}^{n}(-1)^{i+j}a_{ij}\det(A^{(ij)})$ along the jth column.

3. (If you know multi-variable calculus) Treating $M_n(\mathbb{R})$ as $\mathbb{R}^{n^2}$, show that the derivative of the determinant map $\det : M_n(\mathbb{R}) \to \mathbb{R}$ at the identity I is the trace tr: $(\det)'(I) = \text{tr}$. This gives a surprisingly interesting link between the two concepts, and is important in the beginning of the study of *Lie Algebras* of many matrix groups such as $\text{GL}_n(k)$, $\text{SL}_n(k)$, $O_n(k)$, and so forth, where $k \in \{\mathbb{R}, \mathbb{C}\}$.

4. More generally, show that $\det : M_n(\mathbb{R}) \to \mathbb{R}$ has a derivative at any point A, namely: $(D_A \det)(X) = \text{tr}(\text{adj}(A)X)$, with $\text{adj}(A)$ as in definition 13.4.10.

5. Let R be an integral domain with field of fractions K, and let $A \in M_n(R)$. Show that A is invertible in $M_n(K)$ if and only if $\det(A) \neq 0$, and find a matrix $A \in M_2(\mathbb{Z})$ with $\det(A) \neq 0$ that is not invertible in $M_2(\mathbb{Z})$.

13.5 Eigenvectors and Characteristic Polynomial

After having found the trace and determinant, the reader may wonder if there are more invariant functionals on $\text{End}_k(V)$ for an n-dimensional vector space. As it turns out, these are both special cases of a collection of n invariant given by the coefficients of the following polynomial:

Definition 13.5.1: Characteristic Polynomial

Let R be a commutative ring and $A \in M_n(R)$. The *characteristic polynomial* of A is

$$P_A(t) := \det(tI_n - A) \in R[t]$$

the determinant (definition 13.4.5) of the matrix $tI_n - A$, whose entries lie in the commutative ring $R[t]$ of R-polynomials with indeterminate t. If M is a free R-module with a basis of n elements and $\alpha \in \text{End}_R(M)$, the *characteristic polynomial* of α is $P_\alpha(t) := P_A(t)$, where A is the matrix of α with respect to a basis of M with n elements.

The origins of this seemingly complicated looking polynomial comes from its link to eigenvectors and eigenvalues (namely scalars and vector of a linear operator that satisfy $\alpha(v) = \lambda v$ for appropriate $\lambda \in R$ and $v \neq 0$) which shall be explored soon. Some important properties are established first:

Proposition 13.5.2: Properties Of The Characteristic Polynomial

Let R be a commutative ring, let $n \geq 1$ and $A \in M_n(R)$, and write $P_A(t) = \sum_{i \geq 0} c_i t^i$. Then:

1. $P_A(t)$ is monic of degree n
2. the coefficient of t^{n-1} is $c_{n-1} = -\mathrm{tr}(A)$
3. the constant term is $c_0 = (-1)^n \det(A)$
4. if $B = PAP^{-1}$ for some $P \in \mathrm{GL}_n(R)$, then $P_B = P_A$. In particular, the characteristic polynomial of an endomorphism α of a free R-module with a basis of n elements does not depend on the basis used to compute it, and similar endomorphisms have the same characteristic polynomial.

***Proof*:**
Write $X = tI_n - A \in M_n(R[t])$, so that $X_{ij} = t\delta_{ij} - a_{ij}$ and, by definition 13.4.5,

$$P_A(t) = \sum_{\sigma \in S_n} (-1)^\sigma \prod_{i=1}^{n} X_{i\sigma(i)}$$

1. The term of $\sigma = \mathrm{id}$ is $\prod_{i=1}^{n}(t - a_{ii})$. A permutation $\sigma \neq \mathrm{id}$ moves at least two indices: if $\sigma(i) \neq i$, then $\sigma(\sigma(i)) \neq \sigma(i)$ since σ is injective, so $\sigma(i)$ is moved as well. For a moved index i the factor $X_{i\sigma(i)} = -a_{i\sigma(i)}$ is a constant, and every factor has degree at most 1 in t, so the term of $\sigma \neq \mathrm{id}$ has degree at most $n-2$. Expanding $\prod_i (t - a_{ii})$ gives t^n plus terms of degree less than n, so P_A is monic of degree n.

2. By the proof of (1), only the term of $\sigma = \mathrm{id}$ contributes to the coefficient of t^{n-1}. By induction on n, $\prod_{i=1}^{n}(t - a_{ii}) = t^n - (a_{11} + \cdots + a_{nn})t^{n-1} + h$ with $h = 0$ or $\deg h < n-1$: the case $n = 1$ is $t - a_{11}$, and multiplying $t^{n-1} - st^{n-2} + h'$, where $h' = 0$ or $\deg h' < n-2$, by $t - a_{nn}$ gives $t^n - (s + a_{nn})t^{n-1}$ plus terms of degree less than $n-1$. Hence $c_{n-1} = -\sum_i a_{ii} = -\mathrm{tr}(A)$.

3. The evaluation $R[t] \to R$, $t \mapsto 0$, is a ring homomorphism (theorem 9.2.4), and it sends P_A to its constant term c_0. The defining sum of $\det(X)$ is built from the entries of X by sums and products, so applying the evaluation entrywise gives

$$c_0 = \det(-A) = \sum_{\sigma \in S_n} (-1)^\sigma \prod_{i=1}^{n} (-a_{i\sigma(i)}) = (-1)^n \det(A)$$

4. Let $B = PAP^{-1}$. In $M_n(R[t])$ the scalar matrix tI_n commutes with P, so $tI_n - B = P(tI_n - A)P^{-1}$. By proposition 13.4.7, over the commutative ring $R[t]$, and proposition 13.4.6(1),

$$P_B = \det(P) P_A \det(P^{-1}) = P_A \det(PP^{-1}) = P_A \det(I_n) = P_A$$

   If A and B are the matrices of an endomorphism α with respect to two bases with n elements, then A and B are similar by lemma 13.2.16(4), so $P_A = P_B$. If $\alpha' \sim \alpha$, then their matrices with respect to one basis are similar by lemma 13.2.16(3), so $P_{\alpha'} = P_\alpha$, completing the proof.

For an endomorphism α of a free R-module with a basis of $n \geq 1$ elements, parts (2), (3) and (4) show that the trace and the determinant of the matrix of α do not depend on the basis. They are called the *trace* $\mathrm{tr}(\alpha)$ and the *determinant* $\det(\alpha)$ of α, the trace agreeing with definition 13.4.3 for vector spaces. Hence, the characteristic polynomial is of the form:

$$t^n - (\mathrm{tr}\alpha)t^{n-1} + \cdots + (-1)^n(\det \alpha)$$

The trace and the determinant are special among these coefficients: they coincide when $n = 1$, over a field the determinant is zero exactly when α is not surjective (proposition 13.4.12(1), corollary 13.1.20), and the trace is zero if $\alpha = \beta\gamma - \gamma\beta$ is a commutator, since $\mathrm{tr}(\beta\gamma) = \mathrm{tr}(\gamma\beta)$ (proposition 13.4.2). Furthermore, note that all coefficients are invariant under similarity, meaning that if the trace or determinant between two linear operators differ, they are *not* similar! Unfortunately, the converse does not hold:

Example 13.5.3: Similar Matrices

Let:

$$A = \begin{pmatrix} 2 & 0 \\ 0 & 2 \end{pmatrix} \qquad B = \begin{pmatrix} 2 & 1 \\ 0 & 2 \end{pmatrix}$$

These each have the characteristic polynomial $(t-2)^2 = t^2 - 4t + 4$. However, they are not similar: $A = 2I$, and conjugating A by any invertible matrix P gives $P^{-1}(2I)P = 2I$, and hence never B.

As mentioned earlier, the characteristic polynomial naturally arises when studying eigenvector and values. Let us start by formally defining these terms:

Definition 13.5.4: Eigenvalue and Spectrum

Let M be a free R-module over a commutative ring R and let $\alpha \in \mathrm{End}_R(M)$ be a linear operator on M. Then a scalar $\lambda \in R$ is called an *eigenvalue* of α if there exists a nonzero $v \in M$ such that

$$\alpha(v) = \lambda v$$

The collection of all eigenvalues is called the *spectrum* of α.

The existence of eigenvalues of an operator α means that in some subspace $N \subseteq M$ the transformation $\alpha|_N$ is simply scaling. Over $\mathbb{C}$[24], a suitable choice of basis splits the behavior of a linear operator into two kinds: it can only scale or *shear*. In example 13.5.3, matrix B scaled the first basis vector and sheared the second basis vector. Scaling is the easier of the two behaviours as the algebraic invariant for detecting scaling is the characteristic polynomial, while detecting and characterizing shearing requires more complicated invariants: shearing shall be explored in section 14.3.

Eigenvalues are extremely important, having a wide range of applications in quantum mechanics (the term *spectrum of an atom* comes from finding the spectrum of an endomorphism) functional analysis (K-theory has its origin in the spectrum of infinite linear operators), differential equations (in finding a basis to the solutions of an ODE and in defining the Fourier Transform), to number theory and Field theory (as we shall see later in the book), and so much more! Due to the prominence of eigenvalues, some may claim that the study of endomorphisms of vector-spaces is one of the fundamental concepts of mathematics or the sciences. In *Algebraic Geometry* [13] it is shown that

[24] so that there is no "algebraic obstruction", an intuition that shall be covered in great detail in chapter 19

any commutative ring has a spectrum associated to (though by the definition of a spectrum of a ring, the connection shall not be obvious[25]).

The eigenvalues are invariant under similarity. Let α, β be similar using ρ ($\alpha = \rho \circ \beta \circ \rho^{-1}$) and let $\beta(v) = \lambda v$ with $v \neq 0$. Then $\alpha \circ \rho = \rho \circ \beta$ and

$$\alpha(\rho(v)) = (\rho \circ \beta \circ \rho^{-1})(\rho(v)) = \rho \circ \beta(v) = \rho(\lambda v) = \lambda \rho(v)$$

with $\rho(v) \neq 0$, since ρ is injective and $v \neq 0$. So every eigenvalue of β is an eigenvalue of α, and the converse follows by exchanging the roles, as $\beta = \rho^{-1} \circ \alpha \circ \rho$.

Now, as promised, the following shows why the characteristic polynomial is a natural concept based on its invariance in similarity:

Proposition 13.5.5: Eigenvalues And Characteristic Polynomial

Let R be an integral domain, let M be a free R-module with a basis of n elements, and let $P_\alpha(t)$ be the characteristic polynomial of the linear operator $\alpha \in \text{End}_R(M)$. Then $\lambda \in R$ is an eigenvalue if and only if λ is a root of $P_\alpha(t)$. In other words, the set of roots of $P_\alpha(t)$ in R is exactly the spectrum of α.

***Proof*:**
Let A be the matrix of α with respect to a basis β of M with n elements, and let $\lambda \in R$. A vector $v \in M$ with coordinate vector $x \in R^n$ satisfies $\alpha(v) = \lambda v$ exactly when $(\lambda I_n - A)x = 0$, and $v \neq 0$ exactly when $x \neq 0$. So λ is an eigenvalue if and only if $(\lambda I_n - A)x = 0$ for some nonzero $x \in R^n$, that is, by proposition 13.4.13, if and only if $\det(\lambda I_n - A) = 0$. The evaluation $R[t] \to R$, $t \mapsto \lambda$, is a ring homomorphism (theorem 9.2.4), and applying it entrywise to the defining sum of $\det(tI_n - A)$ gives $P_\alpha(\lambda) = \det(\lambda I_n - A)$. Hence λ is an eigenvalue if and only if $P_\alpha(\lambda) = 0$, as we sought to show.

Example 13.5.6: Eigenvalues And Characteristic Polynomials

1. If α is not injective, then 0 is an eigenvalue, otherwise 0 is not an eigenvalue.
2. Take
$$\begin{pmatrix} 0 & -1 \\ 1 & 0 \end{pmatrix}$$
This matrix has a characteristic polynomial of $t^2 + 1$. If $R = \mathbb{R}$, then this characteristic polynomial has *no* roots. Similarly, the linear operator this matrix represents has no eigenvalues. Geometrically, this matrix can be seen as rotating $\mathbb{R}^2$ by $\pi/2$ degrees, which is why it has no eigenvalues over $\mathbb{R}$. If $R = \mathbb{C}$, then the polynomial has two roots, namely $i, -i$. The reader should verify that these are eigenvalues of a linear operator represented by this matrix. Intuitively, multiplying by i can be thought of as representing rotation by $\pi/2$ degree's which is why it is an eigenvalue.

[25]The curious reader may checkout EYNKTA functional analysis where this connection is fully fleshed out, as the connection is fundamentally a functional analysis result and would be too far out of the scope of an algebra textbook to be covered

3. Take
$$\begin{pmatrix} 0 & 2 \\ 1 & 0 \end{pmatrix}$$
This matrix has a characteristic polynomial of $t^2 - 2$. If $R = \mathbb{R}$, then this polynomial has roots $\pm\sqrt{2}$, while if $R = \mathbb{Q}$, this polynomial has no roots, which equivalently implies that there is no eigenvalues when $R = \mathbb{Q}$. Geometrically, this transformation can be seen as reflecting the plane across a line passing through the origin with an irrational slope. Since the slope is irrational, there is no nonzero irrational scalar to a vector, and hence cannot be a rational eigenvalue.

Geometrically, eigenvectors correspond to the linear operator scaling in the appropriate direction. In the simplest case, an n-dimensional linear operator α can be represented in a basis for which $[\alpha]$ just scales appropriately in each direction. We take a moment to explore these type of matrices.

Since roots have the notion of multiplicity (the number of roots sharing the same value), it is natural to contemplate the multiplicity of eigenvalues and see what information this gives us:

Definition 13.5.7: Algebraic Multiplicity

Let λ be an eigenvalue of a linear operator α over a finitely generated free module. Then the *algebraic multiplicity* is its multiplicity as a root of $P_\alpha(t)$.

Example 13.5.8: Algebraic Multiplicity
Let M be a finitely generated free module over an integral domain R.

1. the identity operator I on M has a single eigenvalue, namely 1, which has algebraic multiplicity equal to the rank of M.
2. for $M = R^2$ and the operator with matrix $A = \begin{pmatrix} 1 & 1 \\ 0 & 2 \end{pmatrix}$, $P_A(t) = (t-1)(t-2)$, so the eigenvalues 1 and 2 each have algebraic multiplicity 1.

Notice that the sum of the algebraic multiplicities is bounded by the rank of the free module M (resp. the dimension of the vector-space V). If R is *algebraically closed* (meaning every polynomial of degree n over R has exactly n roots[26]), then the sum of the algebraic multiplicities of the eigenvalues always equals the rank of M. The prototypical algebraically closed field is $\mathbb{C}$, the complex numbers.

The definition has been careful to call the multiplicity "algebraic". There is another notion of multiplicity which corresponds to the geometric behavior of multiplicity, namely there is a special subspace that is linked to each eigenvalue:

[26] See definition 19.5.1 and the lemma under it for more details

Definition 13.5.9: Eigenspace And Eigenvector

Let λ be an eigenvalue associated to the linear operator α over a finitely generated free R-module M. Then the sub-module

$$E_\lambda = \ker(\lambda I - \alpha)$$

is called the *eigenspace* associated to λ, and the elements of E_λ are called *eigenvectors* and represent the elements of M such that

$$\alpha(v) = \lambda v$$

Technically, it is more correct to call these spaces "eigen-modules" rather than eigenspace, however the study of eigen-modules over vector-spaces greatly precedes the generalization to eigen-modules over R-modules, giving us our current vocabulary.

Definition 13.5.10: Geometric Multiplicity

Let E_λ be an eigenspace corresponding to an eigenvalue λ. Then the rank of E_λ is the *geometric multiplicity* of λ.

The eigenspace is mapped into itself by α: if $\alpha(v) = \lambda v$, then $\alpha(\alpha(v)) = \lambda\alpha(v)$, so $\alpha(E_\lambda) \subseteq E_\lambda$ (we shall later call submodules mapped into themselves by an operator α α-stable). The geometric multiplicity is invariant under similarity: if $\alpha = \rho \circ \beta \circ \rho^{-1}$ with ρ an automorphism, the computation above shows that ρ maps the eigenspace of β for λ into the eigenspace of α for λ, and ρ^{-1} maps it back in the same way. So the two eigenspaces are isomorphic, and an isomorphism carries linearly independent elements to linearly independent elements, so they have the same rank (definition 12.3.16).

Example 13.5.11: Geometric And Algebraic Multiplicity

Take

$$\begin{pmatrix} 1 & 1 \\ 0 & 1 \end{pmatrix}$$

Then the characteristic polynomial is $(t-1)^2$, and hence 1 is an eigenvalue with algebraic multiplicity 2. To find it's geometric multiplicity, by considering

$$\begin{pmatrix} 1 & 1 \\ 0 & 1 \end{pmatrix} \begin{pmatrix} v_1 \\ v_2 \end{pmatrix} = \begin{pmatrix} v_1 + v_2 \\ v_2 \end{pmatrix}$$

we see that the right hand side is equal to $1v$ if and only if $v_2 = 0$, hence the eigenspace is

$$\text{span} \begin{pmatrix} 1 \\ 0 \end{pmatrix}$$

which is 1 dimensional, hence the geometric multiplicity is 1.

A result that should stand out to the reader given the above example is the following

Proposition 13.5.12: Algebraic And Geometric Multiplicity

Let R be an integral domain and let λ be an eigenvalue associated to the linear operator α over a finitely generated free R-module M. Then the geometric multiplicity is always less than or equal to the algebraic multiplicity

***Proof*:**

Let n be the rank of M. Fix a basis of M, identifying M with R^n, and let $A \in M_n(R)$ represent α, so that $P_\alpha(t) = \det(tI - A) \in R[t]$. Let K be the field of fractions of R (definition 9.5.2), so $R \subseteq K$ and $R^n \subseteq K^n$, and let α_K be the linear operator on K^n given by the same matrix A.

Let g be the geometric multiplicity of λ and choose g elements $v_1, \dots, v_g$ of E_λ which are linearly independent over R, as the rank provides. They are also linearly independent over K: if $\sum_i c_i v_i = 0$ with $c_i \in K$ not all zero, multiplying through by the product of the denominators of the c_i (nonzero, as R is a domain) gives a dependence with coefficients in R, not all zero, a contradiction. Since each v_i lies in $\ker(\lambda I - A)$ computed over K, we conclude

$$d := \dim_K \ker(\lambda I - \alpha_K) \geq g$$

Next we show $(t-\lambda)^d$ divides $P_\alpha(t)$ in $K[t]$. By theorem 13.1.8, choose a basis $w_1, \dots, w_d$ of $\ker(\lambda I - \alpha_K)$ and extend it, again by theorem 13.1.8, to a basis $w_1, \dots, w_n$ of K^n. In this basis, $\alpha_K(w_j) = \lambda w_j$ for $j \leq d$, so the representing matrix has the block form

$$A' = \begin{pmatrix} \lambda I_d & B \\ 0 & C \end{pmatrix}$$

for some blocks B and C. Since A and A' represent the same operator α_K, we have $\det(tI - A') = P_\alpha(t)$ by proposition 13.5.2(4). Now consider

$$tI - A' = \begin{pmatrix} (t-\lambda) I_d & -B \\ 0 & tI_{n-d} - C \end{pmatrix}$$

as a matrix over the commutative ring $K[t]$. In the defining sum of definition 13.4.5, a permutation σ contributes a nonzero term only if every one of the last $n-d$ indices is sent to one of the last $n-d$ indices, since the entries in those rows and the first d columns vanish. Being a bijection, such a σ then permutes the first d indices and the last $n-d$ indices separately, and every factor of its term comes from the two diagonal blocks. The nonzero terms therefore coincide with those of the block diagonal matrix obtained by replacing $-B$ with 0, and proposition 13.4.8 gives

$$P_\alpha(t) = \det\big((t-\lambda) I_d\big) \det(tI_{n-d} - C) = (t-\lambda)^d \det(tI_{n-d} - C)$$

in $K[t]$. In particular $(t-\lambda)^g$ divides $P_\alpha(t)$ in $K[t]$.

Finally, we transfer the divisibility to $R[t]$. The polynomial $h(t) = (t-\lambda)^g$ is monic with coefficients in R. Dividing P_α by h within $R[t]$ is possible with quotient and remainder in $R[t]$: at each step one subtracts the leading term of the current remainder times a power of t times h, and since h is monic no denominators appear. This produces $P_\alpha = q_0 h + r_0$ with $q_0, r_0 \in R[t]$ and $r_0 = 0$ or $\deg r_0 < \deg h$. Read in $K[t]$, this must coincide with the division of P_α by h in $K[t]$ by the uniqueness in theorem 11.1.1, and the latter has remainder 0 since $h \big| P_\alpha$ in $K[t]$. Hence $r_0 = 0$ and $P_\alpha(t) = (t-\lambda)^g\, q_0(t)$ with $q_0 \in R[t]$. The multiplicity of λ as a root of $P_\alpha(t)$ is therefore at least g, that is, the geometric multiplicity is less than or equal to the algebraic multiplicity.

One of the main results comes in the algebraic multiplicities add up to the rank of the free module and when the algebraic multiplicity matches the geometric multiplicity. Then there exists a basis P making α a bunch of scalars, namely:

Theorem 13.5.13: Diagonalizable

Let α be a linear operator on an n-dimensional vector space V over a field k. Then if the algebraic multiplicities of the eigenvalues sum to n and the algebraic multiplicities of each eigenvalue equal to their respective geometric multiplicities, then for any representation A of α there exists an invertible matrix $P \in \mathrm{GL}_n(k)$ such that:

$$A = P \begin{pmatrix} \lambda_1 & 0 & \cdots & 0 \\ 0 & \lambda_2 & \cdots & 0 \\ \vdots & \vdots & \ddots & \vdots \\ 0 & 0 & \cdots & \lambda_n \end{pmatrix} P^{-1}$$

where $\lambda_1, \lambda_2, ..., \lambda_n$ are the eigenvalues of α counted with algebraic multiplicity, and α (resp. A) is said to be *diagonalizable*. Moreover, such a P exists if and only if there exists a basis for V consisting of eigenvectors.

***Proof*:**
Eigenvectors belonging to distinct eigenvalues are independent in the following sense: if $\mu_1, \ldots, \mu_r$ are distinct eigenvalues and $u_i \in E_{\mu_i}$ satisfy $u_1 + \cdots + u_r = 0$, then every $u_i = 0$. We induct on r, the case $r = 1$ being trivial. Applying the operator $\alpha - \mu_r I$ to the relation kills u_r and gives

$$(\mu_1 - \mu_r)u_1 + \cdots + (\mu_{r-1} - \mu_r)u_{r-1} = 0$$

where $(\mu_i - \mu_r)u_i \in E_{\mu_i}$. By the induction hypothesis, $(\mu_i - \mu_r)u_i = 0$ for each $i < r$, and since $\mu_i \neq \mu_r$ and k is a field, $u_i = 0$ for $i < r$. The relation then forces $u_r = 0$ as well.

Now let $\mu_1, \ldots, \mu_r$ be the distinct eigenvalues of α, with algebraic multiplicities $m_1, \ldots, m_r$ equal to the respective geometric multiplicities, and $m_1 + \cdots + m_r = n$. Choose a basis B_i of each eigenspace E_{μ_i}, so $|B_i| = m_i$, and let $B = B_1 \cup \cdots \cup B_r$, a set of n vectors. We claim B is linearly independent. In a linear dependence among the elements of B, group the terms by eigenspace: the dependence reads $u_1 + \cdots + u_r = 0$ with $u_i \in E_{\mu_i}$ the part of the combination using B_i. By the previous paragraph each $u_i = 0$, and then all coefficients vanish since each B_i is linearly independent. By theorem 13.1.8, B is contained in a basis of V, and by corollary 13.1.13 every basis of V has n elements, so B is itself a basis of V.

Order $B = \{b_1, \ldots, b_n\}$ and let λ_j denote the eigenvalue with $\alpha(b_j) = \lambda_j b_j$. The representation of α in the basis B is then the diagonal matrix D with entries $\lambda_1, \ldots, \lambda_n$, the eigenvalues counted with algebraic multiplicity. If A represents α with respect to a basis β, then A and D represent the same operator in two bases, so by proposition 13.2.13 there is an invertible change of basis matrix $P \in \mathrm{GL}_n(k)$ with $A = PDP^{-1}$.

For the final claim, one direction is the argument above: a basis of eigenvectors produces the diagonal representation D and the matrix P. Conversely, suppose $A = PDP^{-1}$ with D diagonal with entries $d_1, \ldots, d_n$, where A represents α with respect to a basis $v_1, \ldots, v_n$. Define $b_j := \sum_i P_{ij} v_i$, so that the coordinate vector of b_j is $[b_j] = Pe_j$. Since P is invertible, $b_1, \ldots, b_n$

form a basis of V. Moreover

$$[\alpha(b_j)] = A[b_j] = APe_j = PDe_j = d_jPe_j = d_j[b_j]$$

so $\alpha(b_j) = d_jb_j$, and $b_1, \ldots, b_n$ is a basis of V consisting of eigenvectors.

Definition 13.5.14: Diagonalizable

Let α be a linear operator over a finitely generated free R-module M. Then if α admits a representation whose only nonzero entries lie on the diagonal, α is said to be *diagonalizable*. Similarly, a matrix that is similar to a diagonal matrix is said to be *diagonalizable*.

If α is diagonalizable, then M can be expressed in the following useful decomposition:

Theorem 13.5.15: Spectral Decomposition

Let M be a finitely generated free module over an integral domain R and let $\alpha : M \to M$ be diagonalizable. Then M admits the following decomposition into direct sums

$$M \cong \bigoplus_{\text{eigenvalue } \lambda} E_\lambda$$

***Proof*:**
By definition 13.5.14, α admits a diagonal representation: there is a basis $e_1, \ldots, e_n$ of M and scalars $d_1, \ldots, d_n \in R$ with $\alpha(e_i) = d_ie_i$. Each d_i is an eigenvalue of α, witnessed by the nonzero vector e_i.

Conversely, every eigenvalue λ of α is one of the d_i. Indeed, let $\alpha(v) = \lambda v$ with $v \neq 0$ and write $v = \sum_i v_ie_i$. Comparing coefficients of e_i in $\alpha(v) = \lambda v$ gives $d_iv_i = \lambda v_i$, that is, $(d_i - \lambda)v_i = 0$ for every i. Some v_i is nonzero, and since R is a domain, $\lambda = d_i$ for that i.

For an eigenvalue λ, the eigenspace is exactly the span of the basis eigenvectors carrying λ:

$$E_\lambda = \bigoplus_{i\,:\,d_i=\lambda} Re_i$$

The right hand side is contained in E_λ, since each generator e_i with $d_i = \lambda$ satisfies $\alpha(e_i) = \lambda e_i$ and E_λ is a submodule. Conversely, if $v = \sum_i v_ie_i \in E_\lambda$, then as above $(d_i - \lambda)v_i = 0$ for every i, so $v_i = 0$ whenever $d_i \neq \lambda$ (again since R is a domain), and v lies in the right hand side.

Finally, partition the index set $\{1, \ldots, n\}$ by the value of d_i. Since $e_1, \ldots, e_n$ is a basis, every element of M is uniquely an R-linear combination of the e_i, so grouping the terms by eigenvalue expresses every element of M uniquely as a sum of components in the submodules $\bigoplus_{d_i=\lambda} Re_i = E_\lambda$. By proposition 12.3.6, this exhibits

$$M \cong \bigoplus_{\text{eigenvalue } \lambda} E_\lambda$$

as we sought to show.

For future reference, let's give a name to the above decomposition:

Definition 13.5.16: Spectral Decomposition

Let $\alpha : M \to M$ be diagonalizable. Then the decomposition in the above theorem is called the *spectral decomposition* of M.

Given the spectral decomposition of M, α can simply be thought of as scaling each eigenspace E_λ by the eigenvalue, making the "action" of α on the space M completely transparent!

If the algebraic multiplicity does not sum to the rank of M or the geometric multiplicity does not match the algebraic multiplicity, then the matrix is *not* diagonalizable. If the algebraic multiplicity does not sum to the rank of M, then if we are working over field[27] we can take something called the *algebraic closure* of the field, which as the name implies means it is *algebraically closed*. To rigorously go over the algebraic closure of a field is too much work at this stage, and so will just be taken for granted when it is brought up, the curious reader may checkout section 19.5.1. With the reader's current knowledge, most of the section can be parsed.

If the geometric multiplicity does not match the algebraic multiplicity, then it is a harder to find a form. However, in the next chapter, we shall see that there exists a representation that is *almost* diagonalizable: it shall be diagonalizable with possibly a 1 in the super-diagonal (the position right above the diagonal). In fact, *all* square matrices will be able to have this almost diagonal form! This shall be the aforementioned *shearing* behaviour that is the only other behaviour besides scaling that a matrix shall represent when choosing an appropriate basis.

13.6 Geometry and Inner Product

A vector space over an arbitrary field carries no notion of length and no notion of angle, and none can be manufactured from the field axioms alone. Producing one takes two things a general field does not have: an ordering, so that a quantity can be called nonnegative, and a conjugation, so that $\langle v, v\rangle$ can be forced to be real. The real and complex numbers give both, and over them the whole geometric apparatus follows, namely inner products and the Cauchy-Schwarz inequality, orthonormal bases and the Gram-Schmidt process, orthogonal complements and projections, the Riesz representation of a linear functional, adjoints, and the spectral theorem for normal and self-adjoint operators.

That development belongs to a book about $\mathbb{R}$ and $\mathbb{C}$ rather than to one about modules over a general ring, and it is carried out in *Linear Algebra* [31]. Nothing later in this book depends on it.

[27] more generally, over integral domains, since the ring of fractions of an integral domains is a field

14

Modules Over PIDs: Linear Algebra II

Modules over fields have some of the simplest possible structures. Because they are always free, they admit a trivial short exact sequence:

$$0 \to R^n \to M \to 0$$

In the language of free resolutions (definition 12.3.27), every module over a field admits a free resolution of length 0 (recall indexing starts at 0). It is natural to want to study modules that admit a free resolution of length 1. Specifically, if R is a ring and M is a finitely generated module with a surjection

$$R^n \to M \to 0$$

we ask when the kernel is also free, meaning there exists an R^m such that

$$0 \to R^m \to R^n \to M \to 0$$

is exact. As was foreshadowed in section 12.3.3, all finitely generated modules over PIDs admit free resolutions of length 1, and hence they shall be the focus of this chapter. Having a free resolution of length 0 (i.e., being free) implied the existence of a basis, and even over PIDs, matrix representations of linear transformations admitted Smith Normal Forms. A free resolution of length 1 offers slightly less rigid structural results. However, it remains incredibly powerful, introducing us to *Jordan Canonical Forms* and *Rational Canonical Forms* and expands the number of modules for which we have a structure theorem. These forms give a new way of representing linear transformations and invariants of similarity (section 14.3).

The reader may naturally ask if it is interesting to further push the length of the free resolution and explore modules that admit a free resolution of length 2, 3, or n. While finitely generated

modules over a polynomial ring in finitely many variables over a field always have finite projective dimension (Hilbert's Syzygy Theorem, theorem 58.2.6), most interesting examples of such modules become a good deal more complex and require a build-up in algebraic geometry and homological algebra. For the interested reader, these lengths are intimately linked to the *Krull dimension* of a commutative ring[1]. The essential concepts for understanding this link will be covered later (specifically, chapter 34 and section 58.2), and further reading can be done in *Homological Algebra* [29, Auslander-Buchsbaum-Serre Theorem].

Goal

The goal of this section is to show finitely generated modules over PID's have the following structure:

$$M \cong R^k \oplus R/(a_1) \oplus \cdots \oplus R/(a_m)$$

We will define the terms a_m and how to find k soon. Essentially, M shall be split into a part which is "as linearly dependent as possible", and the rest of M will be the elements which cannot be linearly independent (over R). These "rest of elements" of M can be identified with the simplest quotient rings of R, in particular a cyclic module.

Since PID's are UFD's, we will be able to find a 2nd representation given appropriate prime elements:

$$M \cong R^k \oplus R/(p_1) \oplus \cdots \oplus R/(p_n)$$

where p_i will turn out to represent prime elements of R (and the k will be the same).

A consequence of this would be the proof of the Fundamental Theorem of finitely Generated abelian groups (theorem 5.1.6). Since $\mathbb{Z}$ is a finitely generated Principal Ideal Domain, if M is a $\mathbb{Z}$-module (and so an abelian group), it will be a consequence of the following theoretical build-up that

$$M \cong \mathbb{Z}^k \oplus \mathbb{Z}/n_1\mathbb{Z} \oplus \cdots \oplus \mathbb{Z}/n_k\mathbb{Z}$$

Another consequence will be the ability to classify all linear maps from a vector-space to itself (up to similarity). This means that the structure of $M_n(k)$ and $\mathrm{GL}_n(k)$ will be eminently understandable, having huge consequence in representation theory (*Core Representation Theory* [22]) and many areas beyond algebra (Differential Geometry, K-theory, Optimization, ODEs, and so forth). In particular, if V is a vector space over $\mathbb{F}$ and T is a linear transformation, then (section 14.2 gives the details) V becomes an $F[x]$-module on which x acts by T:

$$p(x) \cdot v = (a_n x^n + a_{n-1}x^{n-1} + \cdots + a_1 x + a_0) \cdot v = a_n T^n(v) + \cdots + a_1 T(v) + a_0 v$$

then we can use the fact that $F[x]$ is a Principal Ideal Domain to decompose T into a nicer representation. Since every linear transformation can be represented as a matrix, then we can also decompose matrices in this fashion (which will be called Rational Canonical form and Jordan Canonical Form).

Note that finiteness is an important condition. The $\mathbb{Z}$-module $\mathbb{Q}$ is torsion-free but not free: two elements of $\mathbb{Q}$ are linearly dependent over $\mathbb{Z}$ (example 12.3.13), so a basis would consist of a single $q \neq 0$, while $q/2 \notin \mathbb{Z}q$. So torsion-free modules over a PID need not be free when they are not finitely generated.

[1]The link is not perfect. Often some additional conditions must be placed on the ring, such as R needing to be a regular local ring or Cohen-Macaulay

14.1 Over PID, Submodule of Free Module is Free

Theorem 13.1.12 used the fact that a field k was composed of only units (and 0) to show dimension of a vector-space was well-defined. Not all free R-modules have this property. Fortunately, this will not be an issue for PID's as the following much more general result shows:

Lemma 14.1.1: Invariant Basis Well-defined Over Commutative Ring

Let R be a nonzero commutative ring and let $n, m \in \mathbb{N}$. If $R^n \cong R^m$ as R-modules, then $n = m$

This result can be proven for arbitrary cardinalities, which is left as an exercise. In particular a vector space over a field has a well-defined dimension, finite or not.

***Proof*:**
As R is nonzero, the zero ideal is proper, so it lies in a maximal ideal $\mathfrak{m}$ (proposition 9.4.18), and $k = R/\mathfrak{m}$ is a field (proposition 9.4.19). For $t \in \mathbb{N}$ let $\mathfrak{m}R^t$ be the submodule of tuples with all entries in $\mathfrak{m}$. The map $R^t \to k^t$, $(r_1, \dots, r_t) \mapsto (r_1 + \mathfrak{m}, \dots, r_t + \mathfrak{m})$, is surjective with kernel $\mathfrak{m}R^t$, so $R^t/\mathfrak{m}R^t \cong k^t$ (theorem 12.2.10(1)), and this is an isomorphism of k-vector spaces for the action $(r + \mathfrak{m})(v + \mathfrak{m}R^t) = rv + \mathfrak{m}R^t$. Let $\varphi\colon R^n \to R^m$ be an isomorphism. A tuple with entries in $\mathfrak{m}$ is $\sum_i c_i e_i$ with every $c_i \in \mathfrak{m}$, and φ maps it to $\sum_i c_i \varphi(e_i)$, whose entries lie in the ideal $\mathfrak{m}$. The same holds for φ^{-1}, so $\varphi(\mathfrak{m}R^n) = \mathfrak{m}R^m$, and $v + \mathfrak{m}R^n \mapsto \varphi(v) + \mathfrak{m}R^m$ is a bijective k-linear map. Then:

$$(R/\mathfrak{m})^n \cong (R/\mathfrak{m})^m$$

as vector spaces, and an isomorphism carries the standard basis of k^n to a basis of k^m with n elements, so $n = m$ by corollary 13.1.13(2), completing the proof.

Definition 14.1.2: Invariant Basis Number

Let R be a ring. Then R has the *invariant basis number property* (IBN property) if $R^n \cong R^m$ if and only if $n = m$.

A free R-module where R has the IBN property has the notion of *rank* well-defined.

If R is not commutative, this need not be the case:

Example 14.1.3: Ring Without IBN Property
Let $V = k^{\oplus \mathbb{N}}$ and $R = \mathrm{End}_k(V)$. Prove that:

$$R \cong R^4$$

Thus, there is no ambiguity for the notion of rank when working with free-modules over commutative rings.

Recall that a sub-module of a free module need not be free. For example, if we take $\mathbb{C}[x, y]$ over itself, then it is free with rank 1, but the sub-module (ideal) (x, y) is not free. If it were of rank 1[2],

[2]Why cannot the rank be ≥ 1? hint: use field of fractions

then (x, y) would be generated by a single element, but it has been shown earlier this is not possible. However, if R is a PID, then just like for modules over fields, submodules of free modules over a PID are free. For free modules, this was because every module over a field is free, however there do exist modules over PID's that are not free (consider any torsion abelian group). To prove this result, we shall show that if F is a free module over a PID and $M \subseteq F$, we can iteratively split off a cyclic direct summand $\langle y \rangle$ from $M \subseteq F$, which shall result in separating the free part from the torsion part. Furthermore, y can be chosen in such a way that it is a scalar multiple of a basis element of F: $y = ax$ for appropriate $a \in R$. Think of submodules of $\mathbb{Z}^n$ as a canonical example of this behavior:

Lemma 14.1.4: Splitting Modules Over PID

Let R be a PID, F a finitely generated free module over R, and $M \subseteq F$ be a nonzero submodule. Then there exist a nonzero element $a \in R$, elements $x \in F$, $y \in M$, submodules $F' \subseteq F$ and $M' \subseteq M$, and a homomorphism $\alpha \colon F \to R$ such that

1. $y = ax$
2. $M' = F' \cap M$
3. $F = \langle x \rangle \oplus F'$, $M = \langle y \rangle \oplus M'$
4. $\alpha(x) = 1$, $\ker(\alpha) = F'$, and $\alpha(M) = (a)$ is maximal among the ideals $\varphi(M)$ with $\varphi \in \mathrm{Hom}_R(F, R)$, that is, if $(a) \subseteq \varphi(M)$ for such a φ, then $\varphi(M) = (a)$

***Proof*:**
Since $F \cong R^n$, it is perhaps tempting to think that our factor may be one of the components of R^n, however this implicitly chooses a particular representation (i.e. a basis for the isomorphism $\cong$). Since we do not know that M is free yet, we cannot know how to pick a basis representation of F that matches well with a basis representation of M, we cannot pick a basis β for F in such a way that the free submodule M is a projection. In that case, the splitting in the lemma would be obtained by choosing a component, or in terms of functions using the projection map:

$$\pi(r_1, r_2, ..., r_n) = r_1$$

Instead, we consider all homomorphisms $\varphi \colon F \to R$ at once and choose one for which $\varphi(M)$ is maximal.

Thus, define the following collection of ideals

$$\mathscr{F} = \{\varphi(M) \mid \varphi \in \mathrm{Hom}_R(F, R)\} = \{\varphi(M) \mid \varphi \in F^*\}$$

Each $\varphi(M)$ is a submodule of the R-module R, that is, an ideal. Every ideal of R is principal, hence finitely generated, so theorem 12.3.33, (3) $\Rightarrow$ (2), applied to the R-module R, gives a maximal element of the nonempty set $\mathscr{F}$, of the form $\alpha(M)$ for some $\alpha \colon F \to R$. Fix an isomorphism $F \cong R^n$ and let $\pi_k \colon F \to R$ send an element to its kth coordinate. A nonzero element of M has a nonzero coordinate, so $\pi_k(M) \neq 0$ for some k. If $\alpha(M) = 0$, then $\alpha(M) \subseteq \pi_k(M)$, and maximality gives $\alpha(M) = \pi_k(M) \neq 0$, which is impossible. So $\alpha(M) \neq 0$. Since R is a PID, $\alpha(M) = (a)$ for some nonzero $a \in R$. Thus, there exists a $y \in M$ such that $\alpha(y) = a$.

We shall see that this y and a are the desired values. To find the desired x, we shall show that a

divides $\varphi(y)$ for all $\varphi \in F^*$. To see this, fix $\varphi \in F^*$ and let $b \in R$ be a generator of the ideal

$$(b) = (a, \varphi(y))$$

Then there exists $r, s \in R$ such that

$$b = ra + s\varphi(y)$$

Using this, define the homomorphism $\psi := r\alpha + s\varphi$. Then $\psi(y) = ra + s\varphi(y) = b$, so $\alpha(M) = (a) \subseteq (b) \subseteq \psi(M)$, and by maximality $\psi(M) = \alpha(M)$. But then $b \in (a)$, and

$$(a) = (b) = (a, \varphi(y))$$

namely, $\varphi(y) \in (a)$, hence a divides $\varphi(y)$. Now, with the isomorphism $F \cong R^n$ fixed above, we may write:

$$y = (s_1, s_2, ..., s_n)$$

so that $\pi_i(y) = s_i$. Since $\pi_i \in F^*$, a divides s_i for each s_i, namely there exists $r_1, ..., r_n$ such that $s_i = ar_i$. Letting x be the element associated to the element

$$(r_1, ..., r_n)$$

in the isomorphism, we get that

$$y = ax$$

giving the desired x.

Let's now show that x, y have the desired properties. First, notice that

$$a = \alpha(y) = \alpha(ax) = a\alpha(x)$$

Since R is an integral domain and $a \neq 0$, $\alpha(x) = 1$. Next, let $F' = \ker(\alpha)$ and $M' = F' \cap M$. Notice that for every $z \in F$,

$$z = \alpha(z)x + (z - \alpha(z)x)$$

which by linearity:

$$\alpha(z - \alpha(z)x) = \alpha(z) - \alpha(z)\alpha(x) = \alpha(z) - \alpha(z) = 0$$

Thus,

$$z - \alpha(z)x \in \ker \alpha$$

implying that $F = \langle x \rangle + F'$. Next, take $rx \in \langle x \rangle \cap F'$. Then $\alpha(rx) = 0$, and by linearity $r\alpha(x) = 0$, but $\alpha(x) = 1$ so $r = 0$, and so $\langle x \rangle \cap F' = 0$, which by definition implies:

$$F = \langle x \rangle \oplus F'$$

Giving part of the 3rd claim. Finally, if $z \in M$, then $a \big| \alpha(z)$, and indeed

$$\alpha(z) \in \alpha(M) = (a)$$

Writing $\alpha(z) = ca$, we get $\alpha(z)x = cax = cy$. Splitting z as we have done before, notice that:

$$z - \alpha(z)x = z - cy \in M \cap F' = M'$$

so $z = cy + (z - cy)$ and $M = \langle y \rangle + M'$. As $\langle y \rangle \subseteq \langle x \rangle$ and $M' \subseteq F'$, also $\langle y \rangle \cap M' \subseteq \langle x \rangle \cap F' = 0$, and so we get:

$$M = \langle y \rangle \oplus M'$$

This proves the third claim, and the fourth holds by the choice of α, a and F', completing the proof.

With this, we may prove one of the main results:

Theorem 14.1.5: Submodule Of Free Module Over PID

Let R be a PID, let F be a free R-module of finite rank n, and let $M \subseteq F$. Then M is free, of rank at most n

***Proof*:**
If $M = 0$, we are done, so let $M \neq 0$. By lemma 14.1.4 there exists a $y_1 \in M$ and a $M^1 \subseteq M$ such that

$$M = \langle y_1 \rangle \oplus M^1$$

If $M^1 = 0$, we are done. Otherwise, since $M^1 \subseteq F$, we may keep applying lemma 14.1.4 producing a y_2 and M^2, and so on. After j steps, $M = \langle y_1 \rangle \oplus \cdots \oplus \langle y_j \rangle \oplus M^j$, and each y_i is nonzero, since $\alpha(y_i) = a\alpha(x) = a \neq 0$ for the elements a, x and the homomorphism α of lemma 14.1.4 at step i. The family $(y_1, \ldots, y_j)$ is linearly independent: if $\sum_i r_i y_i = 0$, then every $r_i y_i = 0$ by the uniqueness in proposition 12.3.6(3), and $r_i = 0$, since the free module F over the integral domain R is torsion-free (proposition 12.3.23(4)). This forces $j \leq n$. Indeed, let K be the field of fractions of R (definition 9.5.2) and view $F \cong R^n$ inside K^n. A relation $\sum_i c_i y_i = 0$ with $c_i \in K$, multiplied by a common denominator $d \neq 0$ of the c_i, becomes a relation with coefficients $dc_i \in R$, so every $dc_i = 0$ and every $c_i = 0$. So $y_1, \ldots, y_j$ are linearly independent in the K-vector space K^n, which has a basis with n elements, and $j \leq n$ by corollary 13.1.13(1). Hence the process terminates, leaving us with a $M^m = 0$ for some $m \leq n$, at which point:

$$M = \langle y_1 \rangle \oplus \langle y_2 \rangle \oplus \cdots \oplus \langle y_m \rangle$$

and $(y_1, \ldots, y_m)$ is a basis of M, as we sought to show.

The finite rank hypothesis is not needed for the conclusion, only for this proof: what makes the argument stop is that a linearly independent subset of F cannot have more than n elements. Removing the hypothesis costs exactly one thing, namely a well-ordering in place of the counter m, and the following proof is the same argument with that substitution made. It is worth reading the finite case first, because the well-ordering conceals how simple the mechanism is: peel off one basis vector, split what the submodule contributes in that coordinate, and recurse.

Theorem 14.1.6: Submodule Of Free Module Over PID, General Case

Let R be a PID, let F be a free R-module of any rank, and let $M \subseteq F$ be a submodule. Then M is free

***Proof*:**
Let $(e_\lambda)_{\lambda \in \Lambda}$ be a basis of F and well-order Λ, which is possible by theorem A.2.4. For each λ write

$$F_{<\lambda} = \bigoplus_{\mu<\lambda} Re_\mu, \qquad F_{\leq\lambda} = \bigoplus_{\mu\leq\lambda} Re_\mu,$$

and set $M_{<\lambda} = M \cap F_{<\lambda}$ and $M_{\leq\lambda} = M \cap F_{\leq\lambda}$.

Step 1: one coordinate at a time. Every $x \in F_{\leq\lambda}$ has a unique expression $x = y + re_\lambda$ with

$y \in F_{<\lambda}$ and $r \in R$, so

$$\pi_\lambda \colon F_{\leq\lambda} \to R, \qquad \pi_\lambda(y + re_\lambda) = r$$

is a well defined R-module homomorphism with $\ker(\pi_\lambda) = F_{<\lambda}$. Its image on $M_{\leq\lambda}$ is a submodule of R, that is an ideal, and R is a principal ideal domain, so

$$\pi_\lambda(M_{\leq\lambda}) = (a_\lambda) \qquad \text{for some } a_\lambda \in R$$

Let $\Lambda' = \{\lambda \in \Lambda \mid a_\lambda \neq 0\}$, and for $\lambda \in \Lambda'$ choose $x_\lambda \in M_{\leq\lambda}$ with $\pi_\lambda(x_\lambda) = a_\lambda$.

Step 2: the splitting at λ. If $a_\lambda = 0$ then $M_{\leq\lambda} \subseteq \ker(\pi_\lambda)$, so $M_{\leq\lambda} = M_{<\lambda}$. If $a_\lambda \neq 0$ then

$$M_{\leq\lambda} = M_{<\lambda} \oplus Rx_\lambda$$

For the sum: given $m \in M_{\leq\lambda}$, write $\pi_\lambda(m) = ra_\lambda$. Then $\pi_\lambda(m - rx_\lambda) = 0$, so $m - rx_\lambda \in M \cap F_{<\lambda} = M_{<\lambda}$. For directness: if $rx_\lambda \in M_{<\lambda}$ then $0 = \pi_\lambda(rx_\lambda) = ra_\lambda$, and R is a domain with $a_\lambda \neq 0$, so $r = 0$. The same computation shows $Rx_\lambda \cong R$ is free of rank one.

Step 3: the x_λ span M. Put $N = \sum_{\lambda\in\Lambda'} Rx_\lambda \subseteq M$ and suppose $N \neq M$. Every element of F has finite support, so every $m \in M$ lies in $M_{\leq\lambda}$ for λ the largest index in its support. Hence the set

$$S = \{\lambda \in \Lambda \mid M_{\leq\lambda} \not\subseteq N\}$$

is nonempty, and being a subset of a well-ordered set it has a least element λ_0. Choose $m \in M_{\leq\lambda_0}$ with $m \notin N$. By Step 2, $m = m' + rx_{\lambda_0}$ with $m' \in M_{<\lambda_0}$, where $r = 0$ in the case $a_{\lambda_0} = 0$. Now m' has finite support contained in $\{\mu \mid \mu < \lambda_0\}$, so $m' \in M_{\leq\mu}$ for some $\mu < \lambda_0$, and $M_{\leq\mu} \subseteq N$ by minimality of λ_0. Then $m = m' + rx_{\lambda_0} \in N$, a contradiction. So $N = M$.

Step 4: the x_λ are independent. Suppose $r_1x_{\lambda_1} + \cdots + r_nx_{\lambda_n} = 0$ with $\lambda_1 < \cdots < \lambda_n$ in Λ'. Each x_{λ_i} with $i < n$ lies in $F_{\leq\lambda_i} \subseteq F_{<\lambda_n} = \ker(\pi_{\lambda_n})$, so applying π_{λ_n} leaves $0 = \pi_{\lambda_n}(r_nx_{\lambda_n}) = r_na_{\lambda_n}$, whence $r_n = 0$. Repeating with λ_{n-1}, and so on down, gives $r_i = 0$ for every i.

So $(x_\lambda)_{\lambda\in\Lambda'}$ is a basis of M, and M is free.

For finitely generated F, the maximality in lemma 14.1.4(4) gives a more precise result, the analogue over a PID of the Smith normal form (theorem 13.2.25):

Corollary 14.1.7: Basis For Submodules Of Free Modules

Let R be a PID, F a finitely-generated free R-module, and $M \subseteq F$ a submodule. Then there exists a basis $(x_1, x_2, ..., x_n)$ for F and nonzero elements $a_1, a_2, ..., a_m \in R$ with $m \leq n$ such that

$$(a_1x_1, ..., a_mx_m)$$

is a basis for M. Furthermore, $a_1|a_2|\cdots|a_m$

***Proof*:**

The rank n of F is well defined by lemma 14.1.1, and we argue by induction on n. If $M = 0$, then any basis $(x_1, \ldots, x_n)$ of F works, with $m = 0$. This covers $n = 0$, where $F = 0$. So let $n \geq 1$, assume the statement for free modules of rank $n - 1$, and let $M \neq 0$.

Step 1: splitting off one basis vector. Lemma 14.1.4 gives a nonzero $a_1 \in R$, elements $x_1 \in F$ and $a_1x_1 \in M$, submodules $F' \subseteq F$ and $M' = F' \cap M$, and a homomorphism $\alpha \colon F \to R$ such

that $F = \langle x_1 \rangle \oplus F'$, $M = \langle a_1 x_1 \rangle \oplus M'$, $\alpha(x_1) = 1$, $\ker(\alpha) = F'$, and $\alpha(M) = (a_1)$ is maximal among the ideals $\varphi(M)$, $\varphi \in \mathrm{Hom}_R(F, R)$.

Step 2: F' is free of rank $n-1$. By theorem 14.1.5, the submodule F' of F is free with a basis of some $k \leq n$ elements, so $F' \cong R^k$. The map $R \to \langle x_1 \rangle$, $r \mapsto r x_1$, is surjective, and injective since $r x_1 = 0$ gives $r = \alpha(r x_1) = 0$. As $\langle x_1 \rangle \cap F' = 0$, proposition 12.3.6 identifies F with $\langle x_1 \rangle \times F'$, so

$$R^n \cong F \cong R \times R^k \cong R^{k+1}$$

and $k = n - 1$ by lemma 14.1.1.

Step 3: the two bases. By the induction hypothesis, applied to the submodule M' of F', there are a basis $(x_2, \ldots, x_n)$ of F' and nonzero $a_2, \ldots, a_m \in R$, with $m - 1 \leq n - 1$ and $a_2 \big| a_3 \big| \cdots \big| a_m$, such that $(a_2 x_2, \ldots, a_m x_m)$ is a basis of M'. Then $(x_1, \ldots, x_n)$ is a basis of F. It spans, since $F = \langle x_1 \rangle + F'$. If $\sum_i r_i x_i = 0$, then $r_1 x_1 = -\sum_{i \geq 2} r_i x_i$ lies in $\langle x_1 \rangle \cap F' = 0$, so $r_1 = \alpha(r_1 x_1) = 0$, and then $r_2 = \cdots = r_n = 0$ by the independence of $(x_2, \ldots, x_n)$. Likewise $(a_1 x_1, \ldots, a_m x_m)$ spans $M = \langle a_1 x_1 \rangle + M'$, and if $\sum_i r_i a_i x_i = 0$, then $r_1 a_1 x_1 \in \langle x_1 \rangle \cap F' = 0$, as $M' \subseteq F'$, so $r_1 a_1 = \alpha(r_1 a_1 x_1) = 0$ and $r_1 = 0$, because $a_1 \neq 0$ and R is an integral domain. The independence of $(a_2 x_2, \ldots, a_m x_m)$ then gives $r_2 = \cdots = r_m = 0$. So $(a_1 x_1, \ldots, a_m x_m)$ is a basis of M, and $m \leq n$.

Step 4: $a_1 \big| a_2$. If $m = 1$ there is nothing left to prove, so let $m \geq 2$. Every element of F is $\sum_i r_i x_i$ with unique coefficients $r_i \in R$, so $\varphi\left(\sum_i r_i x_i\right) = r_1 + r_2$ is a well defined homomorphism $\varphi \colon F \to R$. Then $a_1 = \varphi(a_1 x_1) \in \varphi(M)$, so $(a_1) \subseteq \varphi(M)$, and the maximality of $\alpha(M) = (a_1)$ forces $\varphi(M) = (a_1)$. Hence $a_2 = \varphi(a_2 x_2) \in (a_1)$, that is, $a_1 \big| a_2$. With $a_2 \big| \cdots \big| a_m$ this gives $a_1 \big| a_2 \big| \cdots \big| a_m$, completing the proof.

Corollary 14.1.8: If PID, Then Free Resolutions Of Length 1

Let R be a PID. Then for every finitely generated R-module M and every surjective homomorphism:

$$R^{m_0} \xrightarrow{\pi_0} M \to 0$$

there exists a free R-module R^{m_1} and a homomorphism $\pi_1 : R^{m_1} \to R^{m_0}$ such that the sequence

$$0 \to R^{m_1} \xrightarrow{\pi_1} R^{m_0} \xrightarrow{\pi_0} M \to 0$$

is exact. Along with proposition 12.3.29, an integral domain R is a PID if and only if, for every finitely generated R-module M, the kernel of every surjection $R^n \to M$ is free.

***Proof*:**
Since R^{m_0} is an R-module over a PID, $\ker(\pi_0)$ is is free by theorem 14.1.5, and since R^{m_0} is finitely generated, $\ker(\pi_0) \cong R^{m_1}$ for some $m_1 \in \mathbb{N}$. Hence choose the natural embedding $\pi_1 : \ker(\pi_0) \hookrightarrow R^{m_0}$ giving the desired exact sequence, completing the proof.

Since every finitely generated module over a PID has a free resolution of length 1, it is characterized by a matrix (up to equivalence), namely if

$$0 \to R^m \xrightarrow{\varphi} R^n \xrightarrow{\pi_0} M \to 0$$

Then $M = \mathrm{coker}(\varphi)$, and by exactness we know that φ injects into R^n (or, if the reader rather not

use exactness, φ injects since $R^m = \ker(\pi_0)$). Then by corollary 14.1.7, applied to the submodule $\ker(\pi_0)$ of R^n, there exist a basis $(x_1, x_2, ..., x_n)$ of R^n and nonzero elements $a_1, ..., a_m \in R$ where $a_1 \big| a_2 \big| \cdots \big| a_m$ and $(a_1x_1, a_2x_2, ..., a_mx_m)$ forms a basis for $\ker(\pi_0) \cong R^m$, the number of these elements being m by lemma 14.1.1. Hence, in the basis $(\varphi^{-1}(a_1x_1), \ldots, \varphi^{-1}(a_mx_m))$ of R^m and the basis $(x_1, \ldots, x_n)$ of R^n, M is presented by the matrix:

$$\begin{pmatrix} a_1 & \cdots & 0 \\ \vdots & \ddots & \vdots \\ 0 & \cdots & a_m \\ 0 & \cdots & 0 \\ \vdots & \ddots & \vdots \\ 0 & \cdots & 0 \end{pmatrix}$$

By box 13.2.30, any row/column which contains an a_i that is a unit may be removed. As $a_1 \big| a_2 \big| \cdots \big| a_m$, the a_i that are units come first, and removing them and renumbering leaves non-units $a_1, a_2, ..., a_m$, with $n - m$ unchanged. Then:

$$M \cong R/(a_1) \oplus \cdots \oplus R/(a_m) \oplus R^{n-m}$$

Notice what just happened: a finitely generated module over a PID is isomorphic to a rather simple structure, that is such modules lend themselves to a classification theorem! The following theorem summarizes this result and proves a couple more important facts:

Theorem 14.1.9: Invariant Factor Form of Modules over PID's

Let R be a Principal Ideal Domain and let M be a finitely generated R-module. Then:

1. M is isomorphic to a direct sum of finitely many cyclic modules. More precisely,

   $$M \cong_R R^r \oplus R/(a_1) \oplus R/(a_2) \oplus \cdots \oplus R/(a_m)$$

   for some integer $r \geq 0$ and nonzero element $a_1, a_2, ..., a_m$ of R which are not units in R and which satisfy the divisibility relations

   $$a_1 \mid a_2 \mid \cdots \mid a_m$$

2. M is torsion-free if and only if M is free

3. In the decomposition of (1)

   $$\mathrm{Tor}(M) \cong_R R/(a_1) \oplus R/(a_2) \oplus \cdots \oplus R/(a_m)$$

   in particular M is a torsion module if and only if $r = 0$, and in this case, if $M \neq 0$, the annihilator of M is the ideal (a_m).

Theorem 14.1.16 proves the uniqueness of this decomposition up to isomorphism, allowing us to say it is *the* direct sum of finitely many cyclic modules.

***Proof*:**

1. This is the above analysis, stated more succinctly. Let $x_1, x_2, ..., x_n$ be a generating set of M of minimal cardinality, which exists as M is finitely generated. Then given R^n with basis $b_1, b_2, ..., b_n$:
$$\pi : R^n \to M \qquad \pi(b_i) = x_i$$
is a surjective R-module homomorphism. By corollary 14.1.7, applied to the submodule $\ker(\pi)$ of R^n, there are a basis $y_1, y_2, ..., y_n$ for R^n and nonzero $a_1 \big| a_2 \big| \cdots \big| a_m$ in R, $m \leq n$, such that $a_1 y_1, a_2 y_2, ..., a_m y_m$ is a basis for $\ker(\pi)$. Then:
$$M \cong R^n / \ker(\pi) = (y_1 R \oplus y_2 R \oplus \cdots \oplus y_n R)/(a_1 y_1 R \oplus a_2 y_2 R \oplus \cdots \oplus a_m y_m R)$$
The homomorphism $\sum_i r_i y_i \mapsto (r_{m+1}, \ldots, r_n, r_1 + (a_1), \ldots, r_m + (a_m))$ is well defined, the coefficients r_i being unique, and surjective. Its kernel consists of the $\sum_i r_i y_i$ with $a_i \big| r_i$ for $i \leq m$ and $r_i = 0$ for $i > m$, that is, $a_1 y_1 R \oplus \cdots \oplus a_m y_m R$, so by theorem 12.2.10(1) this quotient is isomorphic to:
$$R^{n-m} \oplus R/(a_1) \oplus R/(a_2) \oplus \cdots \oplus R/(a_m)$$
No a_i is a unit. Otherwise a_1, which divides a_i, is a unit, so $y_1 = a_1^{-1}(a_1 y_1) \in \ker(\pi)$, and $M = \pi(R^n)$ is generated by the $n-1$ elements $\pi(y_2), \ldots, \pi(y_n)$, contradicting the minimality of n. This proves (1), with $r = n - m$.

2. If M is free, it is torsion-free by proposition 12.3.23(4), as R is an integral domain. Conversely, if $m \geq 1$, the class of 1 in the summand $R/(a_1)$ is nonzero, as a_1 is not a unit, and it is killed by $a_1 \neq 0$, so M has a nonzero torsion element. So if M is torsion-free, then $m = 0$ and $M \cong R^r$, and the image of a basis of R^r under such an isomorphism is a basis of M, so M is free.

3. Write $T = R/(a_1) \oplus \cdots \oplus R/(a_m)$. Every element of T is killed by $a_m \neq 0$, since $a_i \big| a_m$ for every i. If a nonzero $s \in R$ kills $(f, t) \in R^r \oplus T$, then $sf = 0$ in R^r forces $f = 0$, as R is an integral domain. So the torsion elements of $R^r \oplus T$ form $0 \oplus T$. An isomorphism maps torsion elements onto torsion elements, since $sz = 0$ exactly when $s\Phi(z) = 0$ for an isomorphism Φ, so $\mathrm{Tor}_R(M) \cong_R T$. If $r \geq 1$, the element $((1, 0, \ldots, 0), 0)$ of $R^r \oplus T$ is not torsion, so M is a torsion module exactly when $r = 0$. Let $r = 0$ and $M \neq 0$, so that $m \geq 1$. Isomorphic modules have the same annihilator, so $\mathrm{Ann}_R(M) = \mathrm{Ann}_R(T)$. An element $c \in (a_m)$ lies in every (a_i), so it kills every summand $R/(a_i)$. Conversely, if c kills T, then it kills the class of 1 in $R/(a_m)$, so $c \in (a_m)$. Hence $\mathrm{Ann}_R(M) = (a_m)$, completing the proof.

In order to prove the uniqueness of this decomposition, we shall show how we can systematically "embed" parts of M into a vector-space and take advantage of the invariant basis number (IBN) of finitely dimensional isomorphic vector spaces, that is if two vector-spaces are isomorphic they are the same dimension.

First, since R is a PID the annihilator of M is a principal ideal. We start by finding the annihilator of M when it is a torsion module:

Lemma 14.1.10: Annihilator of Module Over PID

Let M be a finitely generated torsion module over a PID R with decomposition:

$$R/(a_1) \oplus \cdots R/(a_m)$$

with $a_1 \big| \cdots \big| a_m$. Then $\text{Ann}_R(M) = (a_m)$.

***Proof*:**
$0 \neq r \in \text{Ann}_R(M)$ so that

$$0 = r \cdot (1, ..., 1) = (r, ..., r)$$

which by the given decomposition implies:

$$r \equiv 0 \bmod (a_m) \qquad \Leftrightarrow \qquad r \in (a_m)$$

Hence, $\text{Ann}_R(M) \subseteq (a_m)$. Conversely, if $r \in (a_m)$ and $y \in M$, decomposing y so that

$$y = (y_1, ..., y_m) \qquad y_i \in R/(a_i)$$

since $r \in (a_m) \subseteq (a_i)$, we see that for each a_i:

$$ry_i = 0$$

hence $ry = 0$, and so $r \in \text{Ann}_R(M)$, as we sought to show.

Next, since R is a UFD, $a_m = up_1^{k_1} p_2^{k_2} \cdots p_r^{k_r}$ with u a unit and $p_1, \ldots, p_r$ pairwise non-associate primes. For $i \neq j$, $(p_i^{k_i}) + (p_j^{k_j}) = (d)$ for some d, since R is a PID, and d divides both $p_i^{k_i}$ and $p_j^{k_j}$. As p_i and p_j are non-associate primes, d is a unit, so

$$(p_i^{k_i}) + (p_j^{k_j}) = (1)$$

Hence, by the Chinese Remainder Theorem (theorem 9.6.11): $R/(a_m) \cong R/(p_1^{k_1}) \oplus \cdots \oplus R/(p_r^{k_r})$ Doing this to every a_i gives the following decomposition:

Definition 14.1.11: Elementary Divisor Form Of Modules Over PID's

Let M be a finitely generated module over a PID R. An isomorphism

$$M \cong R^r \oplus R/(p_1^{k_1}) \oplus \cdots \oplus R/(p_s^{k_s})$$

with $p_1, \ldots, p_s$ primes of R (not necessarily distinct) and $k_i \geq 1$, as obtained above, is called a[a] elementary divisor form of M, and the prime powers $p_1^{k_1}, \ldots, p_s^{k_s}$ are called the *elementary divisors* of M.

[a] we cannot yet say "the"

Given M is torsion, since M can be decomposed into modules of the form $R/(p_k^{k_i})$, we may group together these modules to form a decomposition:

$$M \cong N_1 \oplus \cdots \oplus N_s$$

where the elements of N_i are annihilated by a power of a distinct prime p_i.

Theorem 14.1.12: Primary Decomposition Theorem

Let R be a PID and let M be a nonzero torsion R-module (not necessarily finitely generated) whose annihilator is $\mathrm{Ann}_R(M) = (a)$ with $a \neq 0$. Suppose the factorization of a into prime powers in R is

$$a = up_1^{\alpha_1} p_2^{\alpha_2} \cdots p_n^{\alpha_n}$$

with u a unit, $p_1, \ldots, p_n$ pairwise non-associate primes and every $\alpha_i \geq 1$, and let $N_i = \{x \in M | p_i^{\alpha_i} x = 0\}$, $1 \leq i \leq n$. Then N_i is a submodule of M with annihilator $(p_i^{\alpha_i})$ and is the submodule of M of all elements annihilated by some power of p_i. Thus, we get

$$M = N_1 \oplus N_2 \oplus \cdots \oplus N_n$$

If M is finitely generated, then each N_i is the direct sum of finitely many cyclic modules whose annihilators are generated by divisors of $p_i^{\alpha_i}$

***Proof*:**

The ring R is a Unique Factorization Domain (proposition 10.1.33), and its primes are its irreducible elements. If $b, c \in R$ are nonzero and have no common prime factor, then $(b)+(c) = (1)$: since R is a PID, $(b) + (c) = (d)$ for some d, which divides b and c, so $d \neq 0$ has no prime factor and is a unit. The same argument applies to any finite list of nonzero elements with no prime factor common to all of them. Write $q_i = \prod_{j \neq i} p_j^{\alpha_j}$, so that $a = up_i^{\alpha_i} q_i$. A prime dividing a power of p_i is an associate of p_i, and a prime dividing q_i is an associate of some p_j with $j \neq i$, so for every $k \geq 0$ the elements p_i^k and q_i have no common prime factor.

Step 1: N_i is a submodule, made of the elements annihilated by a power of p_i. As R is commutative, $x \mapsto p_i^{\alpha_i} x$ is an R-module homomorphism $M \to M$, and N_i is its kernel, a submodule by theorem 12.2.10(1). If $p_i^k x = 0$ for some $k \geq 0$, write $1 = sp_i^k + tq_i$ with $s, t \in R$. Then

$$p_i^{\alpha_i} x = sp_i^{\alpha_i}(p_i^k x) + tu^{-1}(ax) = 0$$

so $x \in N_i$, and conversely every element of N_i is annihilated by the power $p_i^{\alpha_i}$.

Step 2: $M = N_1 + \cdots + N_n$. No prime divides all of $q_1, \ldots, q_n$: such a prime would be an associate of some p_j, and p_j does not divide q_j. So $1 = s_1 q_1 + \cdots + s_n q_n$ for some $s_i \in R$. For $x \in M$, $x = \sum_i s_i q_i x$, and $p_i^{\alpha_i}(s_i q_i x) = s_i u^{-1}(ax) = 0$, so $s_i q_i x \in N_i$.

Step 3: the sum is direct. Let $y_1 + \cdots + y_n = 0$ with $y_i \in N_i$, and fix j. For $i \neq j$, $p_i^{\alpha_i}$ divides q_j, so $q_j y_i = 0$, and multiplying the relation by q_j gives $q_j y_j = 0$. Writing $1 = sq_j + tp_j^{\alpha_j}$ gives $y_j = sq_j y_j + tp_j^{\alpha_j} y_j = 0$. So every element of $N_1 + \cdots + N_n$ is uniquely a sum of elements of the N_i, and $M = N_1 \oplus \cdots \oplus N_n$ by proposition 12.3.6.

Step 4: the annihilator of N_i. As $p_i^{\alpha_i} \in \mathrm{Ann}_R(N_i)$ and R is a PID, $\mathrm{Ann}_R(N_i) = (d_i)$ with d_i dividing $p_i^{\alpha_i}$, so d_i is an associate of $p_i^{\beta_i}$ for some $0 \leq \beta_i \leq \alpha_i$. The element $c = p_i^{\beta_i} q_i$ annihilates every N_j: for $j \neq i$ because $p_j^{\alpha_j}$ divides q_i, and for $j = i$ because $p_i^{\beta_i}$ annihilates N_i. By Step 2, c annihilates M, so $c \in (a)$, that is, $up_i^{\alpha_i} q_i$ divides $p_i^{\beta_i} q_i$. Cancelling $q_i \neq 0$ in the integral domain R, $p_i^{\alpha_i}$ divides $p_i^{\beta_i}$, and $\beta_i < \alpha_i$ would make the nonunit $p_i^{\alpha_i - \beta_i}$ divide 1. So $\beta_i = \alpha_i$ and $\mathrm{Ann}_R(N_i) = (p_i^{\alpha_i})$.

Step 5: the finitely generated case. By Step 3, $\sum_j y_j \mapsto y_i$ is a well defined surjective R-module homomorphism $M \to N_i$, so N_i is generated by the images of finitely many generators of M. By theorem 14.1.9(1), $N_i \cong R^r \oplus R/(c_1) \oplus \cdots \oplus R/(c_l)$ with $c_1 \big| \cdots \big| c_l$ nonzero nonunits. As N_i is torsion, and nonzero since its annihilator $(p_i^{\alpha_i})$ is not R, $r = 0$ and $\mathrm{Ann}_R(N_i) = (c_l)$ by theorem 14.1.9(3), so $(c_l) = (p_i^{\alpha_i})$ by Step 4, and every c_k divides $p_i^{\alpha_i}$. Each $R/(c_k)$ is cyclic, generated by the class of 1, with annihilator (c_k). The images of these summands under the isomorphism are finitely many cyclic submodules with annihilators (c_k), and N_i is their direct sum, completing the proof.

We give a name to the N_i modules

Definition 14.1.13: p_i-Primary Components

The submodules N_i in the previous theorem are called *p_i-primary components* of M.

With this, we come to the key result:

Lemma 14.1.14: Embedding Module over PID into Vector Space

Let R be a PID, let p be a prime in R, and let F denote the field $R/(p)$. For an R-module M and $j \geq 0$, the set $p^j M = \left\{ p^j x \;\middle|\; x \in M \right\}$ is a submodule of M, and $p^j M/p^{j+1}M$, in particular M/pM, is an F-vector space with $(r + (p)) \cdot \overline{x} = \overline{rx}$. Then, with isomorphisms of F-vector spaces:

1. if $M = R^t$, then $M/pM \cong F^t$
2. if $M = R/(a)$ where a is a nonzero element of R, then
$$M/pM \cong \begin{cases} F & \text{if } p \text{ divides } a \text{ in } R \\ 0 & \text{if } p \text{ does not divide } a \text{ in } R \end{cases}$$
3. if $M = R/(a_1) \oplus R/(a_2) \oplus \cdots \oplus R/(a_k)$ where each a_i is divisible by p, then $M/pM \cong F^k$
4. if $M = R/(p^e)$ with $e \geq 1$, then for $j \geq 1$, $p^{j-1}M/p^j M \cong F$ when $j \leq e$ and $p^{j-1}M/p^j M = 0$ when $j > e$
5. if $M = M_1 \oplus \cdots \oplus M_k$, then $p^{j-1}M/p^j M \cong \bigoplus_l p^{j-1}M_l/p^j M_l$ for every $j \geq 1$, and an isomorphism of R-modules $\varphi\colon M \to M'$ induces isomorphisms $p^{j-1}M/p^j M \to p^{j-1}M'/p^j M'$ for every $j \geq 1$

***Proof*:**
As R is commutative, $p^j M$ is closed under addition and under multiplication by R, since $r(p^j x) = p^j(rx)$. The element p maps $p^j M$ into $p^{j+1}M$, so it acts as zero on $p^j M/p^{j+1}M$, and the action of $r + (p)$ is well defined. An R-linear map between two such quotients is F-linear, so each R-module isomorphism below is an isomorphism of F-vector spaces. Write $\overline{x}$ for classes.

1. The map $R^t \to F^t$, $(r_1, \ldots, r_t) \mapsto (r_1 + (p), \ldots, r_t + (p))$, is R-linear and surjective, with kernel pR^t. By theorem 12.2.10(1), $M/pM \cong F^t$.

2. The image of the ideal (p) under the projection $R \to R/(a)$ is $pM = ((p)+(a))/(a)$, so theorem 12.2.10(3), applied to the submodules $(a) \subseteq (p)+(a)$ of R, gives $M/pM \cong R/((p)+(a))$. As R is a PID, $(p)+(a) = (d)$ for some d dividing p, and p is irreducible (proposition 10.1.7), so d is a unit or an associate of p. If p divides a, then $(a) \subseteq (p)$, so $(d) = (p)$ and $M/pM \cong R/(p) = F$. If p does not divide a, then d, which divides a, is not an associate of p, so d is a unit, $(d) = R$ and $M/pM = 0$.

3. By (5) with $j = 1$ and by (2), $M/pM \cong \bigoplus_l (R/(a_l))/p(R/(a_l)) \cong F^k$.

4. For $i \geq 0$, $p^i M$ is the image of the ideal (p^i) in $R/(p^e)$, that is, $(p^i)+(p^e) = (p^{\min(i,e)})$ modulo (p^e). So theorem 12.2.10(3), applied to the module $(p^{\min(j-1,e)})$ and its submodules $(p^e) \subseteq (p^{\min(j,e)})$, gives $p^{j-1}M/p^jM \cong (p^{\min(j-1,e)})/(p^{\min(j,e)})$. If $j > e$, both exponents are e and this is 0. If $j \leq e$, it is $(p^{j-1})/(p^j)$, and $r \mapsto rp^{j-1} + (p^j)$ is a surjective R-linear map $R \to (p^{j-1})/(p^j)$ with kernel (p): p^j divides rp^{j-1} exactly when p divides r, by cancellation of p^{j-1} in the integral domain R (proposition 9.1.24). By theorem 12.2.10(1), $p^{j-1}M/p^jM \cong R/(p) = F$.

5. Multiplication by p^i acts componentwise, so $p^iM = \bigoplus_l p^iM_l$ for every $i \geq 0$. The map $p^{j-1}M \to \bigoplus_l p^{j-1}M_l/p^jM_l$, $(y_1, \ldots, y_k) \mapsto (\overline{y_1}, \ldots, \overline{y_k})$, is surjective and R-linear with kernel $\bigoplus_l p^jM_l = p^jM$, which gives the first isomorphism by theorem 12.2.10(1). An isomorphism φ satisfies $\varphi(p^iM) = p^i\varphi(M) = p^iM'$, so $y \mapsto \overline{\varphi(y)}$ is a surjective R-linear map $p^{j-1}M \to p^{j-1}M'/p^jM'$, with kernel $p^{j-1}M \cap \varphi^{-1}(p^jM') = p^jM$, and theorem 12.2.10(1) gives the induced isomorphism, completing the proof.

The invariant factors determine the elementary divisors, and conversely:

Lemma 14.1.15: Invariant Factors And Prime Powers

Let R be a PID and let $a_1 \big| a_2 \big| \cdots \big| a_m$ be nonzero nonunits of R. Let $p_1, \ldots, p_s$ be pairwise non-associate primes such that every prime factor of a_m is an associate of some p_j, and write $a_k = u_k p_1^{e_{k1}} \cdots p_s^{e_{ks}}$ with u_k a unit and $e_{kj} \geq 0$ (proposition 10.1.33). Then:

1. $R/(a_k) \cong \bigoplus_{j\,:\,e_{kj} \geq 1} R/(p_j^{e_{kj}})$ as R-modules, for each k

2. $e_{1j} \leq e_{2j} \leq \cdots \leq e_{mj}$ for each j, and m is the largest of the numbers $\#\{k \mid e_{kj} \geq 1\}$, $1 \leq j \leq s$

3. if $b_1 \big| \cdots \big| b_l$ are nonzero nonunits with $b_k = v_k p_1^{f_{k1}} \cdots p_s^{f_{ks}}$, v_k a unit, such that for each j the positive exponents among $e_{1j}, \ldots, e_{mj}$ and among $f_{1j}, \ldots, f_{lj}$ are the same up to order, then $l = m$ and b_k is an associate of a_k for every k

***Proof*:**
The ring R is a Unique Factorization Domain, whose primes are its irreducible elements (proposition 10.1.33, proposition 10.1.7), so the factorizations exist and the exponent of p_j in a product is the sum of its exponents in the factors.

1. Fix k. For $j \neq j'$, the ideals $(p_j^{e_{kj}})$ and $(p_{j'}^{e_{kj'}})$ are comaximal: their sum is (d) for some d dividing both generators, and a prime factor of d would be an associate of p_j and of $p_{j'}$, so d is a unit. The product of these ideals over the j with $e_{kj} \geq 1$ is (a_k), so the Chinese

Remainder Theorem (theorem 9.6.11) gives the isomorphism, induced by $r \mapsto (r + (p_j^{e_{kj}}))_j$ and hence R-linear.

2. Writing $a_{k+1} = ca_k$, the exponent of p_j in a_{k+1} is e_{kj} plus its exponent in c, so $e_{kj} \leq e_{k+1,j}$. Each number $\#\{k \mid e_{kj} \geq 1\}$ is at most m. As a_1 is not a unit, $e_{1j} \geq 1$ for some j, and then $e_{kj} \geq 1$ for every k, so this j gives the number m.

3. By (2), applied to the a_k and to the b_k, both m and l are the largest number of positive exponents of a single p_j, so $l = m$. For each j, the sequences $e_{1j} \leq \cdots \leq e_{mj}$ and $f_{1j} \leq \cdots \leq f_{mj}$ have the same length and the same positive entries, so both consist of zeros followed by these entries in increasing order, and $e_{kj} = f_{kj}$ for all k. Hence $b_k = v_k u_k^{-1} a_k$, completing the proof.

Theorem 14.1.16: Fundamental Theorem of Uniqueness of Factors

Let R be a Principal Ideal Domain. Then two finitely generated R-modules M_1 and M_2 are isomorphic if and only if they have the same rank, that is, the same exponent r of the free part in theorem 14.1.9(1), and the same list of invariant factors up to units, and if and only if they have the same rank and the same elementary divisors (definition 14.1.11) up to associates and order. In particular, the rank, the invariant factors and the elementary divisors of M do not depend on the decomposition used to compute them.

***Proof*:**

If the ranks agree and the invariant factors agree up to units (resp. the elementary divisors agree up to associates and order), then the two direct sums are isomorphic summand by summand, since $R/(c) = R/(c')$ when c and c' are associates (proposition 10.1.4), so $M_1 \cong M_2$. Conversely, let $\varphi\colon M_1 \to M_2$ be an isomorphism, and fix decompositions $M_i \cong R^{r_i} \oplus T_i$, where T_i is the direct sum of the cyclic summands $R/(c)$, $c \neq 0$, of the invariant factor form or of an elementary divisor form.

Step 1: the rank. The torsion elements (definition 12.3.18) of $N = R^r \oplus T$, with T a finite direct sum of modules $R/(c)$ with $c \neq 0$, are the elements of $0 \oplus T$: an element of T is killed by the product of the c's, which is nonzero as R is an integral domain, and if a nonzero s kills (f, t), then $sf = 0$ in R^r forces $f = 0$. So the projection onto R^r induces $N/\mathrm{Tor}_R(N) \cong R^r$ (theorem 12.2.10(1)). An isomorphism maps torsion elements to torsion elements, since $sx = 0$ exactly when $s\varphi(x) = 0$, so φ restricts to an isomorphism $\mathrm{Tor}_R(M_1) \to \mathrm{Tor}_R(M_2)$ and induces $R^{r_1} \cong M_1/\mathrm{Tor}_R(M_1) \cong M_2/\mathrm{Tor}_R(M_2) \cong R^{r_2}$. If R is a field, this is an isomorphism of vector spaces, which maps a basis to a basis, so $r_1 = r_2$ by corollary 13.1.13(2). Otherwise R has a nonzero nonunit, which has a prime factor p, and lemma 14.1.14(5) and (1) give an isomorphism of F-vector spaces $F^{r_1} \cong F^{r_2}$, $F = R/(p)$, so again $r_1 = r_2$.

Step 2: the elementary divisors at a prime p. By Step 1, $T_1 \cong \mathrm{Tor}_R(M_1) \cong \mathrm{Tor}_R(M_2) \cong T_2$. Write T_i through an elementary divisor form, $T_i \cong \bigoplus_l R/(q_{i,l})$ with prime powers $q_{i,l}$, given directly or obtained from the invariant factor form by lemma 14.1.15(1). Fix a prime p and put $T[p^\infty] = \{x \in T \mid p^k x = 0 \text{ for some } k \geq 0\}$, a submodule of T. An isomorphism $T \to T'$ maps $T[p^\infty]$ onto $T'[p^\infty]$. On a summand $R/(q)$ with q a power of an associate of p, say $(q) = (p^e)$, the element p^e acts as 0. On a summand $R/(q)$ with q a power of a prime p' not associate to p, $p^k x = 0$ forces $x = 0$. Indeed $(p^k) + (q) = (d)$ with d dividing p^k and q, and a prime factor of d would be an associate of p and of p', so d is a unit, $1 = sp^k + tq$ for some $s, t \in R$, and

$x = sp^k x + tqx = 0$. As p^k acts componentwise, $T_i[p^\infty]$ corresponds to the sum of the summands $R/(q_{i,l})$ with $(q_{i,l}) = (p^e)$ for some $e \geq 1$. So the modules $P_i = \bigoplus_{l\,:\,(q_{i,l})=(p^{e_{i,l}})} R/(p^{e_{i,l}})$ satisfy $P_1 \cong P_2$.

Step 3: counting. For $P = \bigoplus_{l=1}^{n} R/(p^{e_l})$ with every $e_l \geq 1$ and for $j \geq 1$, lemma 14.1.14(5) and (4) give

$$\dim_F \left(p^{j-1}P/p^j P\right) = \#\{l \mid e_l \geq j\}$$

and by lemma 14.1.14(5) these numbers are the same for isomorphic modules, the dimension of a vector space being well defined (corollary 13.1.13(2)). The number of l with $e_l = j$ is $\#\{l \mid e_l \geq j\} - \#\{l \mid e_l \geq j+1\}$, so P_1 and P_2 have the same exponents $e_{i,l}$ up to order. As p was arbitrary, the elementary divisors of M_1 and M_2 agree up to associates and order.

Step 4: the invariant factors. Let $a_1 \big| \cdots \big| a_m$ and $b_1 \big| \cdots \big| b_l$ be invariant factors of M_1 and of M_2, and choose pairwise non-associate primes $p_1, \ldots, p_s$ such that every prime factor of a_m or of b_l is an associate of some p_j. By lemma 14.1.15(1), the decompositions give elementary divisor forms whose elementary divisors are the $p_j^{e_{kj}}$ and the $p_j^{f_{kj}}$ with positive exponents, in the notation of lemma 14.1.15. By Step 3, for each j the positive exponents of p_j agree up to order, so lemma 14.1.15(3) gives $l = m$ and b_k associate to a_k for every k, completing the proof.

Finally, we can now refer to *the* invariant factor form and *the* elementary divisor form of a finitely generated R-module M for R a PID.

Corollary 14.1.17: Computation Shortcut For Invariant Factors

Let R be a Principal Ideal Domain and let M be a finitely generated R-module, with invariant factors $a_1 \big| \cdots \big| a_m$ (theorem 14.1.9). Then, up to units:

1. The elementary divisors of M are the prime power factors of the invariant factors of M: if $a_k = u_k \prod_j p_j^{e_{kj}}$ with u_k a unit and $p_1, \ldots, p_s$ pairwise non-associate primes, then the elementary divisors are the $p_j^{e_{kj}}$ with $e_{kj} \geq 1$, one for each pair (k, j).
2. The largest invariant factor of M is the product of the largest of the distinct prime powers among the elementary divisors of M, the next largest invariant factor is the product of the largest of the distinct prime powers among the remaining elementary divisors of M, and so on

***Proof*:**
Write $M \cong R^r \oplus R/(a_1) \oplus \cdots \oplus R/(a_m)$ as in theorem 14.1.9(1).

1. Combining the isomorphisms of lemma 14.1.15(1) for $k = 1, \ldots, m$ gives an elementary divisor form of M (definition 14.1.11) whose elementary divisors are the $p_j^{e_{kj}}$ with $e_{kj} \geq 1$. By theorem 14.1.16, the elementary divisors of M do not depend on the decomposition, which proves (1).
2. By lemma 14.1.15(2), $e_{1j} \leq e_{2j} \leq \cdots \leq e_{mj}$ for each j. So the largest power of p_j among the elementary divisors is $p_j^{e_{mj}}$ when $e_{mj} \geq 1$, and the product of these largest powers is $\prod_j p_j^{e_{mj}}$, which is a_m up to the unit u_m. Removing one copy of each $p_j^{e_{mj}}$ leaves the elementary divisors $p_j^{e_{kj}}$ with $k \leq m-1$, which by (1) are those of the module $R/(a_1) \oplus \cdots \oplus R/(a_{m-1})$, with invariant factors $a_1 \big| \cdots \big| a_{m-1}$. Induction on m gives the

remaining invariant factors in decreasing order, and the invariant factors are unique up to units by theorem 14.1.16, completing the proof.

Corollary 14.1.18: The Fundamental Theorem of f.g. Abelian Groups

Let G be a finitely generated abelian group. Then:

$$G \cong \mathbb{Z}^r \times \mathbb{Z}_{n_1} \times \cdots \mathbb{Z}_{n_s}$$

for some integers $r, n_1, ..., n_s$ with the following conditions:

1. $r \geq 0$ and $n_j \geq 2$ for all j, and
2. $n_{i+1} | n_i$ for $1 \leq i \leq s-1$

***Proof*:**
Take $R = \mathbb{Z}$ in theorem 14.1.9. Note that the invariant factors are listed in reverse order in Chapter 5 for ease of computation.

Summary

Any finitely generated module over a PID is fully characterised by its rank $r \in \mathbb{N}$ and a chain of proper nonzero ideals $(a_1), ..., (a_m)$ such that

$$(a_1) \supseteq (a_2) \supseteq \cdots \supseteq (a_m)$$

If M is torsion, (a_m) is the annihilator of M. For a torsion module, the invariant factors also combine into a single ideal, which records their product:

Definition 14.1.19: Characteristic Ideal

Let M be a finitely generated torsion module over a PID, with invariant factors $a_1 | \cdots | a_m$. Then the ideal

$$(a_1 a_2 \cdots a_m)$$

is known as the *characteristic ideal* of M.

The characteristic ideal does not depend on the choice of invariant factors, since these are unique up to units (theorem 14.1.16). It no longer determines M: $\mathbb{Z}/2\mathbb{Z} \oplus \mathbb{Z}/2\mathbb{Z}$ and $\mathbb{Z}/4\mathbb{Z}$ both have characteristic ideal (4). The name "characteristic ideal" is given due to its link to the characteristic polynomial explored in section 13.5, made precise in section 14.3.

14.2 Application: Linear Algebra revisited

With the classification established, it can be put to good use in better understanding linear operators between vector spaces. Recall in section 13.2.2 that it was mentioned that chapter 14 is essentially the theoretical build-up for studying linear operators. We now make good on this promise. In this

section, we define a $k[x]$-module structure on vector-spaces given by a linear operator α, and we shall define a new invariant similar to the characteristic polynomial known as the *minimal polynomial*.

To define this new module, we will have to juggle lot of components. Let k be a field, let x be an indeterminate and let R be the polynomial ring $k[x]$. Let V be an k-module (i.e. a vector space over k). Notice that we are using the same field for V and for $k[x]$. Finally, let α be a linear operator on V, that is a linear operator from V to V where we consider the domain and codomain to be the same object. We shall extend the k-module V (i.e. a vector-space) into an $k[x]$-module using α. To accomplish this, we will take advantage of nice properties of linear operators. First, define

$$\alpha^0 = I \qquad \alpha^n = \alpha \circ \alpha \circ \cdots \circ \alpha \qquad (n \text{ times})$$
$$a_n\alpha^n + a_{n-1}\alpha^{n-1} + \cdots + a_1\alpha + a_0 \in \mathrm{End}_k(V)$$

where I is the identity map from V to V and $\circ$ is function composition (which is well-defined since α maps to V). We will now define the ring action of $k[x]$. Let $p(x) \in k[x]$ be a polynomial. Then define an action of the ring element $p(x)$ on the module element b by:

$$\begin{aligned} p(x) \cdot v &= (a_n\alpha^n + \cdots + a_1\alpha + a_0)(v) \\ &= a_n\alpha^n(v) + \cdots + a_1\alpha(v) + a_0 v \end{aligned}$$

That is, $p(x)$ acts by substituting the linear operator α for x in $p(x)$ and applying the resulting linear operator to v. These rules satisfy the module axioms that make V into an $k[x]$-module. For $p = \sum_i a_i x^i$ and $q = \sum_j b_j x^j$, $(p+q)(\alpha) = p(\alpha) + q(\alpha)$ by definition, and since each α^i is linear and $\alpha^i \circ \alpha^j = \alpha^{i+j}$,

$$p(\alpha) \circ q(\alpha) = \sum_{i,j} a_i b_j \, \alpha^{i+j} = (pq)(\alpha)$$

So $(p+q)\cdot v = p\cdot v + q\cdot v$, $p\cdot(v+w) = p\cdot v + p\cdot w$ as $p(\alpha)$ is linear, $(pq)\cdot v = p\cdot(q\cdot v)$, and $1\cdot v = v$. The same computation applies to an endomorphism of a module over any commutative ring R, giving an $R[x]$-module. Note that k is a subring of $k[x]$, and this new module with constant polynomials acting on it is simply the structure of the vector space. Thus the definition of $k[x]$-module *extends* the action of k to an action of the larger ring $k[x]$.

The key is that $k[x]$ is a PID when k is a field (recall theorem 11.1.1 and its corollaries), and V is a finitely generated $k[x]$-module, generated by any finite k-basis, so theorem 14.1.9 gives:

$$V \cong_{k[x]} (k[x])^n \oplus (k[x]/(f_1)) \oplus \cdots \oplus (k[x]/(f_m))$$

Since V is finite k-dimensional, the action $k[x] \curvearrowright V$ must have rank 0, since if it had rank $n \geq 1$, then the invariant factor $(k[x])^n$ would be nonzero, and it is k-isomorphic to:

$$k[x] \cong k \oplus k \oplus \cdots \oplus k \oplus \cdots$$

which would make V infinite k-dimensional. Thus,

$$V \cong_{k[x]} (k[x]/(f_1)) \oplus \cdots \oplus (k[x]/(f_m))$$

Since the action of $k[x]$ is completely dependent on α, the above proposition may be interpreted as there being a special basis for V that will make the action of α on V rather transparent!

Example 14.2.1: Actions of this Module

1. If $\alpha = 0$, that is, the function maps every element to the identity in V (recall that V is an [abelian] group). Then
$$p(x)v = a_n \cdot 0 + \cdots + a_1 \cdot 0 + a_0 v = a_0 v$$
Thus, with such a linear operator, the $k[x]$-module structure is just like the k-module structure.

2. Another simple example is $\alpha = I$, that is, the identity. Thus
$$p(x)v = a_n v + \cdots + a_0 v = (a_n + \cdots + a_0)v$$
Or simply the sum of coefficient of $p(x)$ act on v

3. Here's a more specific example. Take V to be the affine n-space k^n and let α be the "shift operator"
$$\alpha(x_1, ..., x_n) = (x_2, x_3, ..., x_n, 0)$$
Since V is a vector-space, let e_i be a choice of basis vectors. Then applying this linear operator to only the basis, we get:
$$\alpha^k(e_i) = \begin{cases} e_{i-k} & \text{if } i > k \\ 0 & \text{if } i \leq k \end{cases}$$
So that if $m < n$
$$(a_m x^m + a_{m-1}x^{m-1} + \cdots + a_0)e_n = (0, 0, ..., 0, a_m, a_{m-1}, ..., a_0)$$

4. under what condition is $W \subseteq V$ a $k[x]$-submodule of V with the $k[x]$-action? Since $k[x]$ extends the actions of k, it is necessary that W be a subspace. By the subspace criterion we have that it is necessary that $\alpha(W) \subseteq W$. Not all subspaces satisfy this conditions, if they do they are called α-stable subspaces.

Now, notice that we may take the annihilator of the $k[x]$-module V, that is all elements $p(x) \in k[x]$ such that $p(x) \cdot v = 0$ for all $v \in V$, that is, $p(\alpha) = 0$. Since $k[x]$ is a PID, the annihilator is a principal ideal. It is nonzero: for a field K and $A \in M_n(K)$, the $n^2 + 1$ matrices $I_n, A, \ldots, A^{n^2}$ lie in the vector space $M_n(K)$, which has the basis of the n^2 matrices with a single entry 1 and all other entries 0, so they are linearly dependent (corollary 13.1.13(1)), and a nontrivial relation $\sum_i c_i A^i = 0$ gives a nonzero polynomial $\sum_i c_i x^i$ vanishing at A. The polynomials $f \in K[x]$ with $f(A) = 0$ form an ideal, since $(gf)(A) = g(A)f(A)$ by the computation above with A in place of α, so this ideal is (m) for a nonzero m. Two generators are associates (proposition 10.1.4), so they differ by a unit of $K[x]$, that is, a nonzero constant (proposition 9.2.3(2)), and exactly one generator is monic. This ideal shall be important in contexts where R need not be a field, and hence it is defined more generally:

Definition 14.2.2: Annihilator Ideal and Minimal Polynomial

Let R be an integral domain with field of fractions K, let M be a free R-module with a basis of n elements, and let $\alpha \in \mathrm{End}_R(M)$, with matrix $A \in M_n(R)$ in such a basis. Then the ideal

$$\mathfrak{M}_\alpha = \mathrm{Ann}_{R[x]}(M) = \{f \in R[x] \mid f(\alpha) = 0\}$$

of the $R[x]$-module M on which x acts as α is called the *annihilator ideal* of α. The monic generator m_α of the ideal $\{f \in K[x] \mid f(A) = 0\}$ of $K[x]$ is called the *minimal polynomial* of α. When $R = k$ is a field, $\mathfrak{M}_\alpha = (m_\alpha)$.

The minimal polynomial does not depend on the basis: the matrices of α in two bases are similar (lemma 13.2.16(4)), and $f(PAP^{-1}) = Pf(A)P^{-1}$ for every polynomial f, since $(PAP^{-1})^i = PA^iP^{-1}$. When $R = k$, a polynomial f satisfies $f(\alpha) = 0$ exactly when $f(A) = 0$, since the matrix of $f(\alpha)$ is $f(A)$, by lemma 13.2.16(2) and the linearity of $\alpha \mapsto [\alpha]_\beta$, and an endomorphism is zero exactly when its matrix is.

Recall that $k[x]$ is a PID if and only if k is a field, hence it is natural to work in the setting of $R = k$ is a field to use the above module structure and the classification theorem. The term "minimal polynomial" is because it is the smallest polynomial (with respect to divisibility) that solves the equation $f(\alpha) = 0$. The reader may ask if the characteristic polynomial shares the same property, that is if

$$P_\alpha(\alpha) = 0$$

This is the *Cayley-Hamilton Theorem*, proposition 14.3.10 (the reader may try to use definition 14.1.19 to find a connection between these two polynomials and hence a proof of the above equation). The annihilator ideal shares the same nice invariance properties as the characteristic polynomial:

Lemma 14.2.3: Annihilator Ideal And Similarity

Let α be similar to β. Then $\mathfrak{M}_\alpha = \mathfrak{M}_\beta$

***Proof*:**
Let $\rho \in \mathrm{GL}_R(M)$ such that $\beta = \rho \circ \alpha \circ \rho^{-1}$. Then since when composing conjugates:

$$\beta^k = \rho \circ \alpha^k \circ \rho^{-1}$$

we get that for any $f(x) \in R[x]$,

$$f(\beta) = \rho \circ f(\alpha) \circ \rho^{-1}$$

Hence, $f(\alpha) = 0$ if and only if $f(\beta) = 0$, as we sought to show.

The converse is not necessarily, the case: if $\mathfrak{M}_\alpha = \mathfrak{M}_\beta$, it does not imply that $\alpha \sim \beta$:

Example 14.2.4: Same Annihilators, Not Similar
Over a field k, let A and B be the diagonal matrices with diagonal entries $1, 1, 2$ and $1, 2, 2$, where $2 = 1 + 1 \neq 1$. For $f \in k[x]$, $f(A)$ and $f(B)$ are diagonal with entries $f(1), f(1), f(2)$ and $f(1), f(2), f(2)$, so each vanishes exactly when $f(1) = f(2) = 0$. By proposition 11.3.1, $f(1) = 0$

means $f = (x-1)g$, and then $f(2) = g(2) = 0$ means $x - 2$ divides g. So A and B have the same annihilator ideal, generated by $(x-1)(x-2)$. They are not similar, since their characteristic polynomials $(t-1)^2(t-2)$ and $(t-1)(t-2)^2$ differ (proposition 13.5.2(4)).

On the other hand, annihilators can separate matrices with the same characteristic polynomial, as for the matrices of example 13.5.3: $x - 1$ generates the annihilator of the identity matrix, while it does not annihilate

$$A = \begin{pmatrix} 1 & 1 \\ 0 & 1 \end{pmatrix}$$

since $A - I \neq 0$.

Coming back to the $k[x]$-module on V, we may use it to finally have a converse to establishing two linear operators are similar:

Lemma 14.2.5: Similarity And New Module Structure

Let R be a commutative ring and α, β linear operators on a free R-module M. Then the corresponding $R[x]$-module structures on M are isomorphic if and only if $\alpha \sim \beta$

***Proof*:**
Let M_α, M_β be the corresponding $R[x]$-modules given by α, β respectively. Assume $\alpha \sim \beta$ so that there exists an automorphism ρ of M such that

$$\beta = \rho \circ \alpha \circ \rho^{-1} \Rightarrow \beta \circ \rho = \rho \circ \alpha$$

By induction on i, $\rho \circ \alpha^i = \beta^i \circ \rho$, since $\rho \circ \alpha^{i+1} = \beta^i \circ \rho \circ \alpha = \beta^{i+1} \circ \rho$. As ρ is R-linear, for $f = \sum_i c_i x^i \in R[x]$,

$$\rho(f \cdot v) = \sum_i c_i \rho(\alpha^i(v)) = \sum_i c_i \beta^i(\rho(v)) = f \cdot \rho(v)$$

So $\rho \colon M_\alpha \to M_\beta$ is a bijective $R[x]$-module homomorphism, an isomorphism by lemma 12.2.3, and $M_\alpha \cong_{R[x]} M_\beta$.

Conversely, let $\rho \colon M_\alpha \to M_\beta$ be an isomorphism of $R[x]$-modules. The constants $R \subseteq R[x]$ act on M_α and M_β as on M, so ρ is a bijective R-linear map, an automorphism of M (lemma 12.2.3), and $\rho(\alpha(v)) = \rho(x \cdot v) = x \cdot \rho(v) = \beta(\rho(v))$ for every $v \in M$. So $\beta = \rho \circ \alpha \circ \rho^{-1}$, as we sought to show.

Corollary 14.2.6: Similarity And Isomorphism Classes

Let R be a commutative ring and M a free R-module. Then $\alpha \mapsto M_\alpha$ induces a one-to-one correspondence between the similarity classes of R-linear operators on M and the isomorphism classes of $R[x]$-module structures on M extending its R-module structure.

***Proof*:**
An $R[x]$-module structure on M extending its R-module structure determines $\alpha(v) = x \cdot v$, which is R-linear since $x \cdot (rv) = (xr) \cdot v = (rx) \cdot v = r(x \cdot v)$, and the module axioms give

$(\sum_i c_i x^i) \cdot v = \sum_i c_i \alpha^i(v)$, so the structure is M_α. Distinct operators give distinct structures, since α is recovered as the action of x. By lemma 14.2.5, $\alpha \sim \beta$ if and only if $M_\alpha \cong M_\beta$, so $\alpha \mapsto M_\alpha$ induces the stated bijection, completing the proof.

Exercise 14.2.1

1. Show that the $k[x]$-module on V can be constructed using the universal property of polynomials

14.3 Rational and Jordan Canonical Form

From now on, $R = F$ is a field and V is an n dimensional vector-space over F. We shall use the above results to find a nice representation of a linear operator α on V (also written T), namely a matrix representation for the action of x on the $F[x]$-module V.

By section 14.2, the $F[x]$-module V decomposes as

$$V \cong F[x]/(a_1(x)) \oplus F[x]/(a_2(x)) \oplus \cdots \oplus F[x]/(a_m(x))$$

where $a_1(x), a_2(x), ..., a_m(x)$ are nonzero nonunits of $F[x]$ with the divisibility condition

$$a_1(x) | a_2(x) | \cdots | a_m(x)$$

The units of $F[x]$ are the nonzero constants (proposition 9.2.3(2)), so each a_i has degree at least 1, and replacing a_i by its monic associate does not change the ideal (a_i), so every a_i may be taken monic. Two decompositions of this kind give isomorphic modules, so by theorem 14.1.16 their lists of polynomials agree up to units, and two monic polynomials that differ by a unit are equal. So the monic polynomials $a_1, \ldots, a_m$ are determined by α, and they are called the *invariant factors* of α. The minimal polynomial is the last of them:

Proposition 14.3.1: Finding Minimal Polynomial

Let α be a linear operator on a finite dimensional vector space V over a field F, with invariant factors $a_1 \big| \cdots \big| a_m$. Then the minimal polynomial m_α of α is the largest invariant factor a_m, and all the invariant factors of α divide m_α.

***Proof*:**
By definition 14.2.2, (m_α) is the annihilator of the $F[x]$-module V. Isomorphic modules have the same annihilator, since an isomorphism Φ satisfies $f \cdot \Phi(c) = \Phi(f \cdot c)$, so (m_α) is the annihilator of $F[x]/(a_1) \oplus \cdots \oplus F[x]/(a_m)$, which is (a_m) by lemma 14.1.10. So m_α and a_m generate the same ideal and are associates (proposition 10.1.4), that is, they differ by a nonzero constant (proposition 9.2.3(2)), which is 1 since both are monic. Hence $m_\alpha = a_m$, and every a_i divides a_m, completing the proof.

Be mindful that since everything divides m_α, $a_i(x) \big| m_\alpha(x)$, then $(m_\alpha(x)) \subseteq (a_i(x))$, so it is the *smallest* ideal of all the invariant factors. Be careful then when thinking of the word "minimal", for it is the *biggest* polynomial relative to all the invariant factors. It is smallest when it comes to being the *smallest* polynomial which can annihilate V over $F[x]$ (i.e $m_\alpha(\alpha) = 0$). An invariant factor annihilates V only if it equals a_m.

Each summand $F[x]/(a)$, for a monic $a(x) = x^k + b_{k-1}x^{k-1} + \cdots + b_1 x + b_0$, has the F-basis $1, \overline{x}, \ldots, \overline{x}^{k-1}$, where $\overline{x} = x \bmod (a(x))$, and multiplication by x, which is how α acts, sends each basis element to the next one and $\overline{x}^{k-1}$ to $\overline{x}^k = -b_0 - b_1\overline{x} - \cdots - b_{k-1}\overline{x}^{k-1}$. Its matrix in this basis is therefore

$$\begin{pmatrix} 0 & 0 & \cdots & \cdots & \cdots & -b_0 \\ 1 & 0 & \cdots & \cdots & \cdots & -b_1 \\ 0 & 1 & \cdots & \cdots & \cdots & -b_2 \\ 0 & 0 & \ddots & & & \vdots \\ \vdots & \vdots & & \ddots & & \vdots \\ 0 & 0 & \cdots & \cdots & 1 & -b_{k-1} \end{pmatrix}$$

This matrix has a name:

Definition 14.3.2: Companion Matrix

Let $a(x) = x^k + b_{k-1}x^{k-1} + \cdots + b_1 x + b_0$ be any monic polynomial in $F[x]$. The *companion matrix* of $a(x)$ is the $k \times k$ matrix with 1's down the first subdiagonal, $-b_0, -b_1, .., -b_{k-1}$ down the last column and zeros elsewhere. The companion matrix of $a(x)$ will be denoted $C_{a(x)}$

Lemma 14.3.3: Cyclic Modules And Companion Matrices

Let F be a field, let $a = x^d + b_{d-1}x^{d-1} + \cdots + b_1 x + b_0 \in F[x]$ be monic of degree $d \geq 1$, let $C = F[x]/(a)$, and write $\overline{f}$ for the class of $f \in F[x]$. Then:

1. the classes $\overline{1}, \overline{x}, \ldots, \overline{x}^{d-1}$ form an F-basis of C, and the matrix of multiplication by x on C in this basis is the companion matrix C_a
2. the annihilator of the $F[x]$-module C is (a)
3. $\det(xI_d - C_a) = a$, that is, the characteristic polynomial of C_a is a

***Proof*:**

1. The classes span C: dividing $f \in F[x]$ by a (theorem 11.1.1) gives $f = sa + r$ with $r = 0$ or $\deg r < d$, so $\overline{f} = \overline{r}$ is an F-linear combination of them. They are linearly independent: if $\sum_{l<d} c_l \overline{x}^l = 0$, then a divides $g = \sum_{l<d} c_l x^l$, and a nonzero multiple of a has degree at least d (proposition 9.2.3(1)), so $g = 0$. Multiplication by x sends $\overline{x}^l$ to $\overline{x}^{l+1}$ for $l < d-1$, and $\overline{x}^{d-1}$ to $\overline{x}^d = -b_0\overline{1} - b_1\overline{x} - \cdots - b_{d-1}\overline{x}^{d-1}$, because $\overline{a} = 0$. So its matrix in this basis is the companion matrix C_a (definition 14.3.2).
2. The polynomial a kills every class, and $f \cdot \overline{1} = \overline{f} = 0$ forces $f \in (a)$.
3. Let $N = xI_d - C_a \in M_d(F[x])$. If $d = 1$, then $N = (x + b_0) = a$. Let $d \geq 2$. The nonzero entries of N are $N_{ll} = x$ for $l < d$, $N_{dd} = x + b_{d-1}$, $N_{l+1,l} = -1$ for $l < d$, and $N_{ld} = b_{l-1}$ for $l < d$. For $l = 2, \ldots, d$ add x^{l-1} times row l to row 1. This does not change the determinant (proposition 13.4.9(2), over the commutative ring $F[x]$), and the new first row is $\sum_{l=1}^{d} x^{l-1}$(row l of N). Its entry in column $c < d$ is $x^{c-1}N_{cc} + x^c N_{c+1,c} = x^c - x^c = 0$,

and its entry in column d is

$$\sum_{l=1}^{d-1} x^{l-1} b_{l-1} + x^{d-1}(x + b_{d-1}) = a$$

Moving the first row to the bottom by $d-1$ interchanges of adjacent rows multiplies the determinant by $(-1)^{d-1}$ (proposition 13.4.9(1)). The resulting matrix T consists of rows $2, \ldots, d$ of N followed by $(0, \ldots, 0, a)$, so $T_{lc} = 0$ whenever $l > c$, and its diagonal entries are $-1, \ldots, -1, a$. In the defining sum of $\det(T)$, a permutation $\sigma \neq \mathrm{id}$ has some l with $\sigma(l) < l$, since otherwise $\sigma(d) = d$, then $\sigma(d-1) = d-1$, and so on down to $\sigma = \mathrm{id}$. Its term contains the factor $T_{l\sigma(l)} = 0$. Hence $\det(T) = \prod_l T_{ll} = (-1)^{d-1} a$, and $\det(N) = (-1)^{d-1} \det(T) = a$, completing the proof.

Example 14.3.4: Sanity Check

Let $q(x) = x^4 + x^3 + 5x^2 - 2x + 3 \in \mathbb{Q}[x]$. Its companion matrix is

$$C = \begin{pmatrix} 0 & 0 & 0 & -3 \\ 1 & 0 & 0 & 2 \\ 0 & 1 & 0 & -5 \\ 0 & 0 & 1 & -1 \end{pmatrix}$$

so $Ce_1 = e_2$, $Ce_2 = e_3$, $Ce_3 = e_4$ and $Ce_4 = -3e_1 + 2e_2 - 5e_3 - e_4$. Hence

$$q(C)e_1 = C^4 e_1 + C^3 e_1 + 5C^2 e_1 - 2Ce_1 + 3e_1 = (-3e_1 + 2e_2 - 5e_3 - e_4) + e_4 + 5e_3 - 2e_2 + 3e_1 = 0$$

For $j = 2, 3, 4$ also $q(C)e_j = q(C)C^{j-1}e_1 = C^{j-1}q(C)e_1 = 0$. So $q(C) = 0$, matching lemma 14.3.3(2). This does not yet determine the other invariant factors of an operator, or its minimal polynomial, but it confirms that matrices of this type behave as expected.

The same process applies to each cyclic summand $F[x]/(a_i(x))$, and the bases of the summands together give a basis of V in which α has as matrix the *direct sum* of the companion matrices:

$$\begin{pmatrix} C_{a_1(x)} & & & \\ & C_{a_2(x)} & & \\ & & \ddots & \\ & & & C_{a_m(x)} \end{pmatrix}$$

This matrix is determined by the invariant factors of the $F[x]$-module V, which are unique by theorem 14.1.16. Thus, we can give this matrix a name:

Definition 14.3.5: Rational Cannonical Form

1. A matrix is said to be in *rational canonical form* if it is the direct sum of companion matrices for monic polynomials $a_1(x), a_2(x)..., a_m(x)$ of degree at least one with $a_1(x)|a_2(x)|\cdots|a_m(x)$. The polynomial $a_i(x)$ are called the *invariant factors* of the matrix. Such a matrix is also said to be a *block diagonal* matrix with blocks the companion matrices for $a_i(x)$
2. A *rational canonical form* for a linear transformation T is a matrix representing T which is in rational canonical form

Theorem 14.3.6: Rational Canonical Form

Let V be a finite dimensional vector sapce over the field F and let T be a linear transformation of V, with invariant factors $a_1\big|\cdots\big|a_m$.

1. There is a basis for V with respect to which the matrix T is in rational canonical form, i.e., is a block diagonal matrix whose diagonal blocks are the companion matrices for the invariant factors $a_1(x), a_2(x), ..., a_m(x)$ of T
2. If the matrix of T with respect to some basis is in rational canonical form, with invariant factors $b_1(x)\big|\cdots\big|b_l(x)$, then $l = m$ and $b_i = a_i$ for every i. So T has exactly one rational canonical form, called *the* rational canonical form of T

***Proof*:**

1. Fix an isomorphism of $F[x]$-modules $\Phi\colon F[x]/(a_1)\oplus\cdots\oplus F[x]/(a_m)\to V$. As $F\subseteq F[x]$, Φ is a bijective F-linear map, and $T(\Phi(c)) = x\cdot\Phi(c) = \Phi(x\cdot c)$ for every c, since x acts on V as T. By lemma 14.3.3(1), each summand $F[x]/(a_i)$ has an F-basis in which multiplication by x has matrix C_{a_i}. These bases together form an F-basis of the direct sum, since each element of the direct sum is uniquely the sum of its components, and each component is uniquely a combination of the basis of its summand. Their images under Φ form an F-basis β of V (corollary 13.1.20(5), the two spaces having the same dimension by corollary 13.1.18). Multiplication by x maps each summand into itself, and $T\circ\Phi$ is Φ composed with multiplication by x, so the matrix of T in the basis β is block diagonal with diagonal blocks $C_{a_1},\dots,C_{a_m}$.
2. Let the matrix of T in the basis γ be block diagonal with diagonal blocks $C_{b_1},\dots,C_{b_l}$, let $e_j = \deg b_j \geq 1$, and split γ into consecutive pieces $\gamma_j = (w_{j,0},\dots,w_{j,e_j-1})$ of sizes e_j, with D_j the span of γ_j. Writing $b_j = x^{e_j} + \sum_{s<e_j} c_{j,s}x^s$, the block C_{b_j} says that $T(w_{j,s}) = w_{j,s+1}$ for $s < e_j - 1$ and $T(w_{j,e_j-1}) = -\sum_{s<e_j} c_{j,s}w_{j,s}$. So $w_{j,s} = T^s(w_{j,0})$, the subspace D_j is T-stable, hence an $F[x]$-submodule of V, and $b_j\cdot w_{j,0} = T(w_{j,e_j-1}) + \sum_{s<e_j} c_{j,s}w_{j,s} = 0$. The $F[x]$-module homomorphism $F[x]\to D_j$, $f\mapsto f\cdot w_{j,0}$, is surjective, since its image is a submodule containing every $w_{j,s} = x^s\cdot w_{j,0}$, and its kernel contains (b_j). So $f+(b_j)\mapsto f\cdot w_{j,0}$ is a well defined surjective $F[x]$-module homomorphism $F[x]/(b_j)\to D_j$. Both spaces have dimension e_j over F (lemma 14.3.3(1)), so it is bijective by corollary 13.1.20, an isomorphism of $F[x]$-modules (lemma 12.2.3). As γ is a basis, $(d_1,\dots,d_l)\mapsto d_1+\cdots+d_l$ is a bijective $F[x]$-module homomorphism $D_1\oplus\cdots\oplus D_l\to V$. Hence $V\cong F[x]/(b_1)\oplus\cdots\oplus F[x]/(b_l)$,

and the b_j are nonzero nonunits with $b_1 \mid \cdots \mid b_l$. By theorem 14.1.16, comparing with $V \cong F[x]/(a_1) \oplus \cdots \oplus F[x]/(a_m)$, we get $l = m$ and b_i equal to a_i up to a unit, and $b_i = a_i$ as both are monic, completing the proof.

The rational canonical form of a matrix $A \in M_n(F)$ is that of the linear operator $x \mapsto Ax$ on F^n, and its invariant factors are those of this operator. Similarity is detected by the rational canonical form:

Corollary 14.3.7: RCF And Similarity

Let $\alpha, \beta : V \to V$ be two linear operators on a finite dimensional vector space V over a field F. Then $\alpha \sim \beta$ if and only if they have the same RCF, that is, the same invariant factors. Likewise, two matrices $A, B \in M_n(F)$ are similar if and only if they have the same RCF.

***Proof*:**
By lemma 14.2.5, $\alpha \sim \beta$ if and only if the $F[x]$-modules V_α and V_β, on which x acts as α and as β, are isomorphic. If they are isomorphic, then the decompositions of V_α and V_β into cyclic modules give isomorphic modules, so their invariant factors agree by theorem 14.1.16, both lists being monic. Conversely, if α and β have the same invariant factors $a_1, \ldots, a_m$, then $V_\alpha \cong F[x]/(a_1) \oplus \cdots \oplus F[x]/(a_m) \cong V_\beta$. By theorem 14.3.6, the RCF of an operator is the block diagonal matrix of the companion matrices of its invariant factors, and it determines them, so having the same RCF means having the same invariant factors.

For matrices, let L_A and L_B be the operators $x \mapsto Ax$ and $x \mapsto Bx$ on F^n, whose matrices in the standard basis are A and B. By lemma 13.2.16(3), $A \sim B$ if and only if $L_A \sim L_B$, which by the first part holds if and only if L_A and L_B, that is, A and B, have the same RCF, completing the proof.

The name *rational* reflects that the rational canonical form is computed using only the field operations of F, with no need to find roots of polynomials. In particular it does not change when F is enlarged:

Corollary 14.3.8: RCF Over Extended Fields

Let A and B be two $n \times n$ matrices over a field F and suppose F is a subfield of the field K ($F \subseteq K$, or sometimes written K/F) Then

1. The RCF of A is the same whether it is computed over K or over F. The minimal and characteristic polynomials and the invariant factors of A are the same whether A is considered as a matrix over F or as a matrix over K.
2. The matrices A and B are similar over K if and only if they are similar over F, i.e., there exists an invertible $n \times n$ matrix P with entries from K such that $B = P^{-1}AP$ if and only if there exists an (in general different) invertible $n \times n$ matrix Q with entries from F such that $B = Q^{-1}AQ$

***Proof*:**

1. By theorem 14.3.6(1) and lemma 13.2.16(4), applied to the operator $x \mapsto Ax$ on F^n, there is $P \in \mathrm{GL}_n(F)$ such that $M = P^{-1}AP$ is the rational canonical form of A over F. As $P \in \mathrm{GL}_n(K)$, the matrix M is similar to A over K, so by lemma 13.2.16(4) it is the matrix of the operator $x \mapsto Ax$ on K^n with respect to some basis, and by theorem 14.3.6(2) over K, it is the rational canonical form of A over K. Its diagonal blocks give the invariant factors, so these agree, and so does the minimal polynomial, the largest invariant factor (proposition 14.3.1). The characteristic polynomial $\det(xI_n - A)$ is the same over F and over K, being computed from the entries of $xI_n - A$ in $F[x] \subseteq K[x]$.
2. If $B = Q^{-1}AQ$ with $Q \in \mathrm{GL}_n(F)$, then $Q \in \mathrm{GL}_n(K)$. Conversely, if A and B are similar over K, they have the same rational canonical form over K (corollary 14.3.7), which by (1) is their rational canonical form over F, so they are similar over F by corollary 14.3.7, completing the proof.

The characteristic polynomial is now read off the invariant factors:

Lemma 14.3.9: Characteristic Polynomial For Block Matrix

1. Let R be a commutative ring. If M is the block diagonal matrix
$$M = \begin{pmatrix} A_1 & 0 & \cdots & 0 \\ 0 & A_2 & \cdots & 0 \\ \vdots & \vdots & \ddots & \vdots \\ 0 & 0 & \cdots & A_k \end{pmatrix}$$
given by the direct sum of square matrices $A_1, A_2, ..., A_k$ over R, then the characteristic polynomial of M is the product of the characteristic polynomials of $A_1, A_2, ..., A_k$
2. Let α be a linear operator on a finite dimensional vector space over a field F, with invariant factors $a_1, \ldots, a_m$. The characteristic polynomial is the product of the invariant factors:
$$P_\alpha(x) = a_1(x)a_2(x)\cdots a_m(x)$$

***Proof*:**

1. The matrix $xI - M$ is block diagonal over the commutative ring $R[x]$, with diagonal blocks $xI - A_1, \ldots, xI - A_k$, so proposition 13.4.8 gives $\det(xI - M) = \prod_i \det(xI - A_i)$.
2. By theorem 14.3.6(1), α has a matrix M that is block diagonal with diagonal blocks $C_{a_1}, \ldots, C_{a_m}$, and $P_\alpha = P_M$ (proposition 13.5.2(4)). By (1) and lemma 14.3.3(3), $P_M = \prod_i \det(xI - C_{a_i}) = a_1 a_2 \cdots a_m$, completing the proof.

Over any commutative ring, a matrix is a root of its characteristic polynomial:

Proposition 14.3.10: Cayley-Hamilton Theorem

Let R be a commutative ring and A an $n \times n$ matrix over R, with characteristic polynomial $P_A(t) = \sum_{i=0}^{n} c_i t^i$. Then

$$P_A(A) = \sum_{i=0}^{n} c_i A^i = 0$$

Consequently $P_\alpha(\alpha) = 0$ for every endomorphism α of a free R-module with a basis of n elements. If $R = F$ is a field, then the minimal polynomial of A divides the characteristic polynomial of A.

***Proof*:**

A matrix with entries in $R[t]$ is uniquely a finite sum $\sum_i X_i t^i$ with $X_i \in M_n(R)$, taking for X_i the matrix of coefficients of t^i in the entries. Choose $N \geq n$ such that every entry of the adjugate $\operatorname{adj}(tI_n - A) \in M_n(R[t])$ (definition 13.4.10) has degree at most N, and write $\operatorname{adj}(tI_n - A) = \sum_{i=0}^{N} B_i t^i$ with $B_i \in M_n(R)$. Put $B_{-1} = B_{N+1} = 0$ and $c_i = 0$ for $n < i \leq N+1$. By proposition 13.4.11(2), over the commutative ring $R[t]$,

$$\operatorname{adj}(tI_n - A)(tI_n - A) = \det(tI_n - A)I_n = P_A(t)I_n$$

The (j,l) entry of the left side is $\sum_m (\sum_i B_i t^i)_{jm}(t\delta_{ml} - a_{ml}) = \sum_i t^{i+1}(B_i)_{jl} - \sum_i t^i (B_i A)_{jl}$, so comparing the coefficient matrices of t^i for $0 \leq i \leq N+1$ gives

$$B_{i-1} - B_i A = c_i I_n$$

Multiplying the ith equation on the right by A^i and adding over i, the left side telescopes:

$$\sum_{i=0}^{N+1} c_i A^i = \sum_{i=0}^{N+1} \left(B_{i-1}A^i - B_i A^{i+1}\right) = \sum_{i=1}^{N+1} B_{i-1}A^i - \sum_{i=0}^{N} B_i A^{i+1} = 0$$

As $c_i = 0$ for $i > n$, this is $P_A(A) = 0$. If A is the matrix of α in a basis β, then the matrix of $P_\alpha(\alpha) = \sum_i c_i \alpha^i$ is $\sum_i c_i A^i = P_A(A) = 0$, by lemma 13.2.16(2) and the linearity of $\alpha \mapsto [\alpha]_\beta$, so $P_\alpha(\alpha) = 0$. If $R = F$ is a field, then P_A lies in the ideal of polynomials vanishing at A, whose monic generator is the minimal polynomial (definition 14.2.2), so the minimal polynomial divides P_A, completing the proof.

Over a field, the rational canonical form gives a second proof of the last statement: the minimal polynomial a_m (proposition 14.3.1) divides the product $a_1 a_2 \cdots a_m$ of the invariant factors, which is the characteristic polynomial (lemma 14.3.9(2)).

In field theory the minimal polynomial of an algebraic element α (definition 19.2.19) is the minimal polynomial of the linear map $\mu_\alpha \colon F(\alpha) \to F(\alpha)$, $v \mapsto \alpha v$: for $f \in F[x]$, $f(\mu_\alpha) = \mu_{f(\alpha)}$, which is zero exactly when $f(\alpha) = 0$.

14.3.1 Converting a square matrix to Rational Canonical Form

Let A be an $n \times n$ matix with entries from a field F

1. First, reduce $xI - A$ to its Smith Normal Form (theorem 13.2.25, which applies since $F[x]$ is a Euclidean domain) by elementary row and column operations, keeping track of the row operations for step (2).

   Let $d_1, d_2, ..., d_m$ be the degrees ofthe monic nonconstant polynomials $a_1(x), ..., a_m(x)$ that are in the respective diagonals

2. Let P' be the $n \times n$ identity matrix. For each row operation of (1), in order, change P' as follows: if rows i and j are interchanged, interchange columns i and j of P'. If $p(x)$ times row j is added to row i, subtract $p(A)$ times column i of P' from column j. If row i is multiplied by a unit u, divide column i of P' by u.

3. Once you have diagonalize $xI - A$ to the Smith Normal Form, the first $n - m$ columns of the matrix P' should be 0, and the remaining m columns of P' are nonzero. For each $i = 1, 2, ...m$, multiply the ith nonzero column of P' successively by $A^0 = I, A^1, A^2, ..., A^{d_i - 1}$, where d_i is the integer in (1) aboce and use the resulting column vectors (in this order) as the next d_i column of an $n \times n$ matrix $P>$ Then $P^{-1}AP$ is in rational canonical form (whose diagonal blocks are the companion matrices for the polynomials $a_1(x), ..., a_m(x)$ in (1))

Example 14.3.11: Finding Rational Canonical Form

1. Let the following 3×3 matrices be over $\mathbb{Q}$:

$$A = \begin{pmatrix} 2 & -2 & 14 \\ 0 & 3 & -7 \\ 0 & 0 & 2 \end{pmatrix} \quad B = \begin{pmatrix} 0 & -4 & 85 \\ 1 & 4 & -30 \\ 0 & 0 & 3 \end{pmatrix} \quad C = \begin{pmatrix} 2 & 2 & 1 \\ 0 & 2 & -1 \\ 0 & 0 & 3 \end{pmatrix}$$

   We can see that each matrix has the same characteirstic polynomial

$$c_A(x) = c_B(x) = c_C(x) = (x-2)^2(x-3)$$

   Since the minimal and characteristic polynomial have the same roots, the only possibilities for the minimal polynomials are $(x-2)(x-3)$ or $(x-2)^2(x-3)$. Since there are only two options, we it will either be one minimal polynomial or the other. Thus, with some computation, we see that $(A - 2I)(A - 3I) = 0$, $(B - 2I)(B - 3I) \neq 0$ (the $1,1$-entry is nonzero) and $(C - 2I)(C - 3I) \neq 0$ (the $1,2$-entry is nonzero). Thus, we get

$$m_A(x) = (x-2)(x-3), \qquad m_B(x) = m_C(x) = (x-2)^2(x-3)$$

   since other invariant factors would need to divide $m_B(c)/m_C(x)$, there must be no other invariatn facors for B and C. Since the invariant factors for A divide the minimal polynomial and have as a product the characteristic polynomial, we see that A has for invariant factors the polynomials, $x - 2, (x-2)(x-3) = x^2 - 5x + 6$. For 2×2 and 3×3 matrices the characteristic and minimal polynomials determine all the invariant factors: the invariant factors other than $m(x)$ divide $m(x)$ and have product $c(x)/m(x)$, of degree at most 2, and if that degree is 2 then $m(x)$ has degree 1 and every invariant factor equals $m(x)$.

   Thus, we can conclude that B and C are similar, and both are not simialr to A. The rational canonical forms are(note $(x-2)^2(x-3) = x^3 - 7x^2 + 16x - 12$)

$$\begin{pmatrix} 2 & 0 & 0 \\ 0 & 0 & -6 \\ 0 & 1 & 5 \end{pmatrix} \quad \begin{pmatrix} 0 & 0 & 12 \\ 1 & 0 & -16 \\ 0 & 1 & 7 \end{pmatrix} \quad \begin{pmatrix} 0 & 0 & 12 \\ 1 & 0 & -16 \\ 0 & 1 & 7 \end{pmatrix}$$

2. In example (1), we managed to conclude the rational canonical form from the minimal polynomials, which we can always do for 3×3 matries and lower. However, that is not the case for matries of higher degree. Before doing such an example, let's practice by going the long way on matrix A from example (1).

   (a) We first start by reducint $xI - A$ in $\mathbb{Q}[x]$

   $$xI - A = \begin{pmatrix} x-2 & 2 & -14 \\ 0 & x-3 & 7 \\ 0 & 0 & x-2 \end{pmatrix}$$

   which we can do by the operations $R_1 + R_2 \mapsto R_1$, $C_1 - C_2 \mapsto C_1$, $-R_1$, $R_2 + (x-3)R_1 \mapsto R_2$, $C_2 + (x-1)C_1 \mapsto C_2$, $C_3 - 7C_1 \mapsto C_3$, $-C_2$, $R_2 - 7R_3 \mapsto R_2$, and finally $R_2 \leftrightarrow R_3$ together with $C_2 \leftrightarrow C_3$, where $R_i + aR_j \mapsto R_i$ adds a times the jth row to the ith row, $-R_i$ multiplies the ith row by -1, $R_i \leftrightarrow R_j$ interchanges two rows, and C denotes the same operations on columns [48, Section 12.2]. After the first six operations the matrix is

   $$\begin{pmatrix} 1 & 0 & 0 \\ 0 & -x^2 + 5x - 6 & 7(x-2) \\ 0 & 0 & x-2 \end{pmatrix}$$

   so, our final result is

   $$\begin{pmatrix} 1 & 0 & 0 \\ 0 & x-2 & 0 \\ 0 & 0 & x^2 - 5x + 6 \end{pmatrix}$$

   This gives us the invariant factors of $x - 2$ and $x^2 - 5x + 6 = (x-2)(x-3)$ for this matrix. Now, let V be a 3 dimensional vector space over $\mathbb{Q}$ with standard basis e_1, e_2, e_3 and let T be the corresponding linear operator (which defines the action of x on V):

   $$\begin{aligned} xe_1 &= T(e_1) = 2e_1 \\ xe_2 &= T(e_2) = -2e_1 + 3e_2 \\ xe_3 &= T(e_3) = 14e_1 - 7e_2 + 2e_3 \end{aligned}$$

   taking the row operations from earlier, $R_1 + R_2 \mapsto R_1$, $-R_1$, $R_2 + (x-3)R_1 \mapsto R_2$, $R_2 - 7R_3 \mapsto R_2$ and $R_2 \leftrightarrow R_3$, and applying them to this basis by the rules of [48, Section 12.2]: interchanging rows i and j interchanges the ith and jth generators, adding $p(x)$ times row j to row i subtracts $p(x)$ times the ith generator from the jth generator, and multiplying row i by a unit u divides the ith generator by u. This gives

   $$\begin{aligned} [e_1, e_2, e_3] &\to [e_1, e_2 - e_1, e_3] \to [-e_1, e_2 - e_1, e_3] \to [-e_1 - (x-3)(e_2 - e_1), e_2 - e_1, e_3] \\ &\to [-e_1 - (x-3)(e_2 - e_1), e_2 - e_1, e_3 + 7(e_2 - e_1)] \end{aligned}$$

   with a final result of

   $$[-e_1 - (x-3)(e_2 - e_1), e_3 + 7(e_2 - e_1), e_2 - e_1]$$

   and applying the formulas for T from earlier, we will get

   $$[0, -7e_1 + 7e_2 + e_3, -e_1 + e_2]$$

which correspond to the elements 1, $x-2$, and x^2-5x+6 we found earlier. Since the first invariant factor has degree 0, we can ignore it. So, we have $f_1 = -7e_1 + 7e_2 + e_3$, and $f_2 = -e_1 + e_2$. These are the $\mathbb{Q}[x]$-module generators for the two cyclic factors of V in its invariant factor decomposition as $\mathbb{Q}[x]$-modules. For the corresponding $\mathbb{Q}$-vector space bases for theset two factros, since $x-2$ has degree 1, and x^2-5x+6 has degree 2, we get f_1, f_2, xf_2 as a basis, where $xf_2 = T(f_2) = -4e_1 + 3e_2$, giving us

$$P = \begin{pmatrix} -7 & -1 & -4 \\ 7 & 1 & 3 \\ 1 & 0 & 0 \end{pmatrix}$$

which we can use to find P^{-1} and get

$$P^{-1}AP = \begin{pmatrix} 2 & 0 & 0 \\ 0 & 0 & -6 \\ 0 & 1 & 5 \end{pmatrix}$$

which is the same result we had in (1).

(b) We can also convert strait into Rational cannonical form. Given the operation for the diagonalization of A, we use them on the identity matrix, by the rules of section 14.3.1:

$$I_3 \xrightarrow{C_2 - C_1 \mapsto C_2} \begin{pmatrix} 1 & -1 & 0 \\ 0 & 1 & 0 \\ 0 & 0 & 1 \end{pmatrix} \xrightarrow{-C_1} \begin{pmatrix} -1 & -1 & 0 \\ 0 & 1 & 0 \\ 0 & 0 & 1 \end{pmatrix} \xrightarrow{C_1 - (A-3I)C_2 \mapsto C_1} \begin{pmatrix} 0 & -1 & 0 \\ 0 & 1 & 0 \\ 0 & 0 & 1 \end{pmatrix}$$
$$\xrightarrow{C_3 + 7C_2 \mapsto C_3} \begin{pmatrix} 0 & -1 & -7 \\ 0 & 1 & 7 \\ 0 & 0 & 1 \end{pmatrix} \xrightarrow{C_2 \leftrightarrow C_3} \begin{pmatrix} 0 & -7 & -1 \\ 0 & 7 & 1 \\ 0 & 1 & 0 \end{pmatrix} = P'$$

Here $d_1 = 1$ and $d_2 = 2$, corresponding to the second and third columns of P', and the columns of P are:

$$\begin{pmatrix} -7 \\ 7 \\ 1 \end{pmatrix} \quad \text{and} \quad \begin{pmatrix} -1 \\ 1 \\ 0 \end{pmatrix} A \begin{pmatrix} -1 \\ 1 \\ 0 \end{pmatrix} = \begin{pmatrix} -4 \\ 3 \\ 0 \end{pmatrix}$$

which gives the same P as before.

Exercise 14.3.1

1. Show that every square matrix $A \in M_n(k)$ is similar to its transpose A^t. (Hint: by theorem 14.3.6 and corollary 14.3.7 it suffices to treat a companion matrix $C = C_a$ of degree d. Show that $e_d, C^t e_d, \ldots, (C^t)^{d-1} e_d$ is a basis of k^d, and deduce that the rational canonical form of C^t is C_a.)

14.4 Jordan Canonical Form

The RCF was found by taking using the invariant factors. Let us now find a form based on the elementary divisors when the characteristic polynomial factors completely. If the characteristic polynomial does not factor completely, then the field can be enlarged so that every polynomial factors completely (as mentioned in section 13.5 the avid reader may checkout section 19.5.1 for more details on algebraic closure). As we have outlined earlier, the similarity of two linear transformations is independent of the base field, and hence this pursuit does lead to a useful matrix form for deducing similarity.

Given a $\alpha \in \text{End}_k(V)<$ we may obtain the elementary divisor decomposition of the correspondign $k[x]$-module to be:

$$V \cong \bigoplus_{i,j} \frac{k[x]}{(p_i(x)^{r_{ij}})}$$

Then the characteristic polynomial $P_\alpha(x)$ is equal to the product

$$\prod_{i,j} p_i(x)^{r_{ij}}$$

(lemma 14.4.1(1) below). This gives us the following results:

Lemma 14.4.1: Elementary Divisors And Characteristic Polynomial

Let α be a linear operator on a finite dimensional vector space V over a field k, and let

$$V \cong \bigoplus_{i=1}^{s} \bigoplus_{j=1}^{t_i} \frac{k[x]}{(p_i(x)^{r_{ij}})}$$

be an elementary divisor form of the $k[x]$-module V (definition 14.1.11), where $p_1, \ldots, p_s$ are distinct monic irreducible polynomials, $t_i \geq 1$ and $r_{ij} \geq 1$. Then:

1. $P_\alpha(x) = \prod_{i,j} p_i(x)^{r_{ij}}$
2. the minimal polynomial is $m_\alpha(x) = \prod_{i=1}^{s} p_i(x)^{\max_j\{r_{ij}\}}$
3. if the characteristic polynomial factors completely, as

$$P_\alpha(x) = \prod_{i=1}^{s'} (x - \lambda_i)^{m_i}$$

where $\lambda_1, \ldots, \lambda_{s'}$ are the distinct eigenvalues and $m_i \geq 1$ are the algebraic multiplicities, then after renumbering $s' = s$ and

$$p_i(x) = x - \lambda_i \qquad m_i = \sum_j r_{ij}$$

so that the minimal polynomial is

$$m_\alpha(x) = \prod_{i=1}^{s} (x - \lambda_i)^{\max_j\{r_{ij}\}}$$

***Proof*:**

Write $q_{ij} = p_i^{r_{ij}}$ and fix a $k[x]$-module isomorphism $\Phi\colon \bigoplus_{i,j} k[x]/(q_{ij}) \to V$. As $k \subseteq k[x]$, Φ is a bijective k-linear map, and $\alpha(\Phi(c)) = x \cdot \Phi(c) = \Phi(x \cdot c)$ for every c, since x acts on V as α.

1. The bases of lemma 14.3.3(1) of the summands $k[x]/(q_{ij})$ together form a k-basis of the direct sum, and their images under Φ form a k-basis β of V. Multiplication by x maps each summand into itself, and $\alpha \circ \Phi$ is Φ composed with multiplication by x, so by lemma 14.3.3(1) the matrix A of α in the basis β is block diagonal with diagonal blocks $C_{q_{ij}}$. Then $xI - A$ is block diagonal with blocks $xI - C_{q_{ij}}$, and by proposition 13.4.8, applied over $k[x]$, and lemma 14.3.3(3),

$$P_\alpha(x) = \det(xI - A) = \prod_{i,j} \det(xI - C_{q_{ij}}) = \prod_{i,j} p_i(x)^{r_{ij}}$$

The characteristic polynomial does not depend on the basis used to compute it (proposition 13.5.2(4)).

2. By definition 14.2.2, m_α is the monic generator of the annihilator of the $k[x]$-module V. Isomorphic modules have the same annihilator, since an isomorphism Φ of $k[x]$-modules

satisfies $f \cdot \Phi(v) = \Phi(f \cdot v)$. An element of $k[x]$ annihilates a direct sum exactly when it annihilates every summand, since it acts componentwise. So by lemma 14.3.3(2)

$$\mathrm{Ann}_{k[x]}(V) = \bigcap_{i,j}(p_i^{r_{ij}}) = \bigcap_{i=1}^{s}(p_i^{e_i}) \qquad e_i = \max_j\{r_{ij}\}$$

since for fixed i the ideals $(p_i^{r_{ij}})$ are nested and the smallest is $(p_i^{e_i})$. Let $g = \prod_{i=1}^{s} p_i^{e_i}$. Each $p_i^{e_i}$ divides g, so (g) lies in the intersection. Conversely, let $p_i^{e_i}$ divide f for every i. Each p_i is prime in the principal ideal domain $k[x]$ (corollary 11.1.2, proposition 10.1.33), and p_l does not divide p_i for $i \neq l$: otherwise $p_i = up_l$ with u a unit, that is a nonzero constant, and $u = 1$ as both are monic, contradicting $p_i \neq p_l$. If a prime p does not divide a and p^e divides ab, then p^e divides b: for $e \geq 1$, p divides b, say $b = pb'$, and cancelling p in the integral domain $k[x]$ shows p^{e-1} divides ab', so induction on e applies. Now suppose $g_{l-1} = \prod_{i<l} p_i^{e_i}$ divides f, say $f = g_{l-1}h$. As p_l is prime and divides no p_i with $i < l$, it does not divide g_{l-1}, so $p_l^{e_l}$ divides h and g_l divides f. By induction on l, starting from $g_0 = 1$, $g = g_s$ divides f. Hence $\mathrm{Ann}_{k[x]}(V) = (g)$, and since g is monic, $m_\alpha = g$.

3. Each $x - \lambda_l$ is monic of degree 1, hence irreducible and prime in $k[x]$. By (1), $x - \lambda_l$ divides $\prod_{i,j} p_i^{r_{ij}}$, so it divides some p_i, and as in (2) this forces $p_i = x - \lambda_l$. Conversely, each p_i divides $P_\alpha = \prod_l (x - \lambda_l)^{m_l}$, so it divides some $x - \lambda_l$, and then $p_i = x - \lambda_l$, both being monic of degree 1. The p_i are distinct and so are the $x - \lambda_l$, so this matches them bijectively, and after renumbering $s' = s$ and $p_i = x - \lambda_i$. Fix i and put $R_i = \sum_j r_{ij}$. By (1) and by hypothesis, $P_\alpha = (x - \lambda_i)^{R_i} a = (x - \lambda_i)^{m_i} b$, where a and b are products of factors $x - \lambda_l$ with $l \neq i$, so $x - \lambda_i$ divides neither a nor b, as it would then divide some $x - \lambda_l$ with $\lambda_l \neq \lambda_i$. If $R_i < m_i$, cancelling $(x - \lambda_i)^{R_i}$ in the integral domain $k[x]$ gives $a = (x - \lambda_i)^{m_i - R_i} b$, so $x - \lambda_i$ divides a, which is impossible. If $m_i < R_i$, cancelling $(x - \lambda_i)^{m_i}$ gives $(x - \lambda_i)^{R_i - m_i} a = b$, so $x - \lambda_i$ divides b, which is impossible. Hence $m_i = R_i = \sum_j r_{ij}$, and the formula for m_α is (2) with $p_i = x - \lambda_i$, completing the proof.

With this, let's start finding the matrix representation of α. Just like before, let's tart with the cyclic factor, $F[x]/((x - \lambda)^k)$. We will purposefully be choosing our basis so that our representation is particularly simple:

$$(\overline{x} - \lambda)^{k-1}, (\overline{x} - \lambda)^{k-2}, ..., (\overline{x} - \lambda), (\overline{x} - \lambda^)0 = 1$$

this is indeed a basis, since expanding out, simplifying, we get these elements to be a linear combination of $\overline{x}^{k-1}, \overline{x}^{k-2}, ..., \overline{x}, 1$, meaning they do form a basis. Then, we can associate the linear operator T to x, and get

$$\begin{cases} (x - \lambda)^{r-1} \mapsto x(x - \lambda)^{r-1} = \lambda(x - \lambda)^{r-1} + (x - \lambda)^r = \lambda(x - \lambda)^{r-1} \\ (x - \lambda)^{r-2} \mapsto x(x - \lambda)^{r-2} = (x - \lambda)^{r-1} + \lambda(x - \lambda)^{r-1} \\ \vdots \\ 1 \mapsto x = (x - \lambda) + \lambda \end{cases}$$

which in matrix form is be represented as:

$$\begin{pmatrix} \lambda & 1 & & & \\ & \lambda & 1 & & \\ & & \ddots & \ddots & \\ & & & \lambda & 1 \\ & & & & \lambda \end{pmatrix}$$

where the blank spots are all zero. We give a name to this matrix

Definition 14.4.2: Jordan Block

The $k \times k$ matrix with λ along the main diagonal and 1 along the first superdiagonal depicted avoce is called the $k \times k$ *elementary Jordan matrix with eigenvalue* λ, or the *Jordan block of size* k *with eigenvalue* λ

As before, we may combine all of these to get a full representation of α:

Definition 14.4.3: Jordan canonical Form (JCF)

Let α be a linear operator on a finitely dimensional vector space V. Then it's *Jordan Canonical Form* (JCF) is the combination of all the Jordan blocks:

$$\begin{pmatrix} [c|c|c]J_{\lambda_1,(r_{1,j})} & & \\ & \ddots & \\ & & J_{\lambda_s,(r_{s,j})} \end{pmatrix}$$

where $(x - \lambda_i)^{r_{ij}}$ are the elementary divisors of α.

14.4.4 An ambiguity in Uniqueness While the RCF is is completely unique up to isomorphism, since there is no unique way of arranging the eigenvalues, there is no unique way of arranging the Jordan blocks (unlike the invariant blocks which are arranged by the divisibility of the invariant factors)

So far the Jordan canonical form has only been described. What has not yet been said is when an operator *has* one: unlike the rational canonical form, which exists over any field, the Jordan form requires the relevant polynomials to factor into linear pieces. The elementary divisor decomposition of chapter 14 settles the question, and the proof also explains where the superdiagonal 1s come from.

Theorem 14.4.5: Existence of the Jordan Canonical Form

Let k be a field, let V be a finite dimensional k-vector space and let α be a linear operator on V whose minimal polynomial factors into linear factors over k (which holds for every α when k is algebraically closed). Then there is a basis of V in which the matrix of α is in Jordan canonical form, and the multiset of Jordan blocks appearing is uniquely determined by α. Equivalently, a matrix $A \in M_n(k)$ whose minimal polynomial splits over k is similar to a matrix in Jordan canonical form, unique up to the order of its blocks.

***Proof*:**
Regard V as a $k[x]$-module with x acting as α. It is finitely generated, being finite dimensional over k, and it is torsion, since the minimal polynomial $m(x)$ annihilates it. As $k[x]$ is a principal ideal domain, definition 14.1.11 gives a decomposition

$$V \cong \bigoplus_{i=1}^{s} k[x]/\big(p_i(x)^{r_i}\big)$$

with each p_i irreducible, and the multiset of the $p_i^{r_i}$ is uniquely determined by V. There is no free part because V is torsion.

Step 1: the p_i are linear. The polynomial $m(x)$ annihilates V, hence annihilates each summand $k[x]/(p_i^{r_i})$, and therefore $p_i^{r_i}$ divides $m(x)$. By hypothesis $m(x)$ is a product of linear factors, and $k[x]$ is a unique factorization domain, so every irreducible factor of m is linear. Hence each p_i is linear, say $p_i = x - \lambda_i$.

Step 2: each summand is a Jordan block. Fix a summand $W = k[x]/\big((x-\lambda)^r\big)$ and, for $1 \le j \le r$, let $e_j \in W$ be the class of $(x-\lambda)^{r-j}$. These r elements form a k-basis of W, since $1, (x-\lambda), \dots, (x-\lambda)^{r-1}$ is a k-basis of $k[x]/\big((x-\lambda)^r\big)$: the polynomials $(x-\lambda)^d$ for $0 \le d < r$ have distinct degrees $0, 1, \dots, r-1$, so they are a basis of the space of polynomials of degree less than r, which maps isomorphically onto the quotient. Writing $x = \lambda + (x-\lambda)$ and setting $e_0 := 0$, which is consistent because $(x-\lambda)^r = 0$ in W,

$$\alpha(e_j) = x \cdot (x-\lambda)^{r-j} = \lambda(x-\lambda)^{r-j} + (x-\lambda)^{r-j+1} = \lambda e_j + e_{j-1}$$

So the matrix of $\alpha|_W$ in the ordered basis $(e_1, \dots, e_r)$ has λ in every diagonal entry and 1 in every entry of the first superdiagonal, which is the Jordan block $J_{\lambda,r}$ of definition 14.4.2.

Step 3: assembly. Concatenating the bases of the summands gives a basis of V in which the matrix of α is block diagonal with the blocks of Step 2, which is the Jordan canonical form of definition 14.4.3. Uniqueness of the multiset of blocks is the uniqueness of the elementary divisors, since the block $J_{\lambda,r}$ corresponds to the elementary divisor $(x-\lambda)^r$, as we sought to show.

Only the order of the blocks is undetermined, which is the ambiguity recorded in box 14.4.4.

An interesting proeprty the JCF gives us is that it distinguishes algebraic and geometric multiplicity of eigenvalues:

Proposition 14.4.6: Geometric An Algebraic Multiplicity Of Eigenvalues Using JCF

Let α be a linear operator on a finitely dimensional vector space V. Then the geometric multiplicity of an eigenvalue λ of α equals the number of Jordan blocks corresponding to λ in the Jordan canonical form of α, and the algebraic multiplicity equals the number of times the eigenvalue shows up in the Jordan canonical form.

***Proof*:**
The fact that the algebraic multiplicity of the eigenvalue corresponds to the number or times it shows up in the JCF is immediate, hence let's show the number of Jordan blocks equasl the geometric multiplicity. Let:

$$J =: \begin{pmatrix} \lambda & 1 & \cdots & 0 & 0 \\ 0 & \lambda & \cdots & 0 & 0 \\ \vdots & \vdots & \ddots & \vdots & \vdots \\ 0 & 0 & \cdots & \lambda & 1 \\ 0 & 0 & \cdots & 0 & \lambda \end{pmatrix}$$

be a Jordan block and $v = \begin{pmatrix} v_1 \\ \vdots \\ v_r \end{pmatrix}$ be an eigenvector corresponding to λ. Then:

$$\lambda \begin{pmatrix} v_1 \\ v_2 \\ \vdots \\ v_r \end{pmatrix} = J \begin{pmatrix} v_1 \\ v_2 \\ \vdots \\ v_r \end{pmatrix} = \begin{pmatrix} \lambda v_1 + v_2 \\ \lambda v_2 + v_3 \\ \vdots \\ \lambda v_r \end{pmatrix}$$

which solving gives us:

$$v_2 = \cdots = v_r = 0$$

Hence, the eigenspace of λ is generated by:

$$v = \begin{pmatrix} 1 \\ 0 \\ \vdots \\ 0 \end{pmatrix}$$

completing the proof.

Corollary 14.4.7: Diagonalizability And Minimal Polynomial

Assume the characteristic polynomial of $\alpha \in \mathrm{End}_k(V)$ factors completely over k. Then α is diagonalizable iff the minimal polynomial of α has no multiple roots

***Proof*:**
Throughout, write m_α for the minimal polynomial and P_α for the characteristic polynomial. By the Cayley-Hamilton theorem (proposition 14.3.10), $P_\alpha(\alpha) = 0$, so P_α lies in the annihilator ideal (m_α) of definition 14.2.2, that is, $m_\alpha | P_\alpha$. The ring $k[x]$ is a Euclidean domain (theorem 11.1.1), hence a PID (proposition 10.2.7), hence a UFD (proposition 10.1.33). Since P_α factors completely into linear factors, unique factorization shows every irreducible factor of its divisor m_α is linear as well, so m_α also factors completely over k.

($\Rightarrow$) Suppose α is diagonalizable, with a diagonal representation D with diagonal entries $d_1, \ldots, d_n$, and let $\mu_1, \ldots, \mu_s$ be the distinct values among them. Set $f(x) := \prod_{i=1}^{s}(x - \mu_i)$. Fixing the basis giving D, the matrix representation is additive and multiplicative (theorem 13.2.6), so the

matrix representing $f(\alpha)$ is $f(D)$, which is diagonal with entries $f(d_1), \ldots, f(d_n)$, all zero since each d_j is one of the μ_i. Hence $f(\alpha) = 0$, so $f \in (m_\alpha)$, that is, $m_\alpha | f$. If m_α had a multiple root λ, then $(x-\lambda)^2$ would divide f, which is false since the μ_i are distinct. Hence m_α has no multiple roots.

($\Leftarrow$) Suppose m_α has no multiple roots. As shown above, m_α factors into linear factors over k, so theorem 14.4.5 applies: α has a Jordan canonical form. By lemma 14.4.1,

$$m_\alpha(x) = \prod_{i=1}^{s} (x - \lambda_i)^{\max_j\{r_{ij}\}}$$

where the $(x-\lambda_i)^{r_{ij}}$ are the elementary divisors, whose exponents r_{ij} are the sizes of the Jordan blocks. Since m_α has no multiple roots, $\max_j\{r_{ij}\} = 1$ for every i, so every $r_{ij} = 1$ and every Jordan block has size 1. The Jordan canonical form of α is therefore a diagonal matrix, so α admits a diagonal representation and is diagonalizable (definition 13.5.14).

Naturally, the diagonalizability of a matrix also depends on the base field, for example the rotation by $\pi/2$ degrees for $\mathbb{R}^2$ is not diagonalizable, while it is diagonalizable over $\mathbb{C}$

14.4.1 Changing From one Canonical Form to Another

The elementary divisors are the prime power factors of the invariant factors. Conversely, the largest invariant factor is the product of the largest power of each $(x-\lambda)$ among the elementary divisors, the next largest is the product of the largest remaining powers, and so on, with 1 once a root's powers run out. The two canonical forms of a matrix whose characteristic polynomial splits therefore determine each other [48, Section 12.3].

14.4.2 Computation: Convert to JCF

Let A be an $n \times n$ matrix over a field F over which the characteristic polynomial of A splits.

1. Carry out steps (1) and (2) of section 14.3.1, obtaining the invariant factors $a_1(x), \ldots, a_m(x)$ and the nonzero columns $f_1, \ldots, f_m$ of P'.
2. For each i, factor $a_i(x) = (x-\lambda_1)^{e_1} \cdots (x-\lambda_s)^{e_s}$ with $\lambda_1, \ldots, \lambda_s$ distinct, and for each j let $g_{ij} = \prod_{l \neq j} (A - \lambda_l I)^{e_l} f_i$.
3. For each such $g = g_{ij}$, with $\lambda = \lambda_j$ and $e = e_j$, use the column vectors $(A-\lambda I)^{e-1}g, \ldots, (A-\lambda I)g, g$ (in this order) as the next e columns of an $n \times n$ matrix P.

Then $P^{-1}AP$ is in Jordan canonical form, with one Jordan block of size e_j and eigenvalue λ_j for each factor $(x-\lambda_j)^{e_j}$ of each $a_i(x)$, in the order used in step (3) [48, Section 12.3].

14.5 The Jordan-Chevalley Decomposition

A matrix in Jordan canonical form is the sum of two pieces of very different character: its diagonal, which scales, and its superdiagonal of 1s, which shears. These are the two behaviours promised in

chapter 13, and the two pieces even commute, since within each Jordan block the diagonal piece is the scalar matrix λI. What theorem 14.4.5 does not tell us is whether this splitting belongs to the operator or to the basis: perform the same surgery on the matrix of α in some other basis, and the two pieces need not commute and need not agree with the pieces the Jordan basis produces. The goal of this section is to show that the splitting is intrinsic. Every operator whose characteristic polynomial factors completely is the sum of a diagonalizable operator and a nilpotent operator that commute, the pair is unique, and both are polynomial expressions in the operator itself with zero constant term. The polynomial clause is the strongest part of the statement: anything that commutes with α commutes with both pieces, and any subspace that α preserves both pieces preserve. First, names for the two behaviours.

Definition 14.5.1: Semisimple and Nilpotent Operators

Let V be a finite dimensional vector space over a field k and let $\alpha \in \mathrm{End}_k(V)$. Then α is said to be *semisimple* if it is diagonalizable in the sense of definition 13.5.14[a], and α is said to be *nilpotent* if $\alpha^m = 0$ for some $m \geq 1$. The smallest such m is called the *index* of the nilpotent operator α.

[a] over a field where polynomials need not factor completely, the right definition is instead that the minimal polynomial of α is a product of distinct irreducible factors, and corollary 14.4.7 shows the two definitions agree whenever the characteristic polynomial factors completely. Everything in this section happens in that setting, so no distinction arises.

Two lemmas about diagonalizable operators are needed, and both are useful well beyond this section. The first says that diagonalizability survives restriction.

Lemma 14.5.2: Restriction of a Diagonalizable Operator

Let $\alpha \in \mathrm{End}_k(V)$ be diagonalizable with distinct eigenvalues $\mu_1, ..., \mu_r$, and let $W \subseteq V$ be an α-stable subspace (example 14.2.1). Then

$$W = (W \cap E_{\mu_1}) \oplus \cdots \oplus (W \cap E_{\mu_r})$$

and the restriction $\alpha|_W$ is diagonalizable.

***Proof*:**
By theorem 13.5.15, $V = E_{\mu_1} \oplus \cdots \oplus E_{\mu_r}$, hence any $w \in W$ decomposes as $w = w_1 + \cdots + w_r$ with $w_j \in E_{\mu_j}$, and the content of the lemma is that each w_j lies in W. Fix j and consider the polynomial

$$\pi_j(t) = \prod_{l \neq j} \frac{t - \mu_l}{\mu_j - \mu_l} \in k[t]$$

whose denominators are nonzero because the μ_l are distinct. For $v \in E_{\mu_l}$ we have $\alpha v = \mu_l v$, so every polynomial in α acts on E_{μ_l} as its value at μ_l, and π_j takes the value 0 at each μ_l with $l \neq j$ and the value 1 at μ_j. Therefore

$$\pi_j(\alpha)w = \sum_{l=1}^{r} \pi_j(\mu_l) w_l = w_j$$

Since W is α-stable, it is stable under every power of α and under linear combinations of those

powers, so $\pi_j(\alpha)W \subseteq W$ and $w_j \in W$. This proves that W is the sum of the subspaces $W \cap E_{\mu_j}$, and the sum is direct because the E_{μ_j} are independent. Concatenating bases of the $W \cap E_{\mu_j}$ now gives a basis of W consisting of eigenvectors of $\alpha|_W$, which is therefore diagonalizable by theorem 13.5.13, as we sought to show.

The second lemma removes the one ambiguity a diagonalizable operator carries, namely *which* basis diagonalizes it: commuting operators can be made to share one.

Lemma 14.5.3: Simultaneous Diagonalization

Let V be a finite dimensional vector space over a field k and let $\mathcal{F} \subseteq \mathrm{End}_k(V)$ be any family of diagonalizable operators that commute pairwise. Then there is a single basis of V consisting of common eigenvectors of every member of $\mathcal{F}$, so that every member of $\mathcal{F}$ is diagonal in one shared basis. Such a family is called *simultaneously diagonalizable*.

***Proof*:**
We induct on $\dim V$. If every member of $\mathcal{F}$ is a scalar multiple of the identity, then any basis of V diagonalizes all of $\mathcal{F}$ at once, and this in particular settles $\dim V \leq 1$. Otherwise, fix some $\alpha \in \mathcal{F}$ that is not a scalar. By theorem 13.5.15,

$$V = E_{\mu_1} \oplus \cdots \oplus E_{\mu_r}$$

where $\mu_1, ..., \mu_r$ are the distinct eigenvalues of α. Here $r \geq 2$: if α had a single eigenvalue μ, a diagonalizing basis would represent α by the matrix μI, making $\alpha = \mu\mathrm{id}$ a scalar. Consequently each eigenspace satisfies $0 < \dim E_{\mu_j} < \dim V$.

Every $\beta \in \mathcal{F}$ preserves every E_{μ_j}: for $v \in E_{\mu_j}$,

$$\alpha(\beta v) = \beta(\alpha v) = \mu_j(\beta v)$$

so $\beta v \in E_{\mu_j}$. By lemma 14.5.2 each restriction $\beta|_{E_{\mu_j}}$ is diagonalizable, and for fixed j the restrictions commute pairwise because the members of $\mathcal{F}$ do. The inductive hypothesis applied to E_{μ_j} produces a basis of E_{μ_j} of common eigenvectors of all the restrictions. Concatenating these bases over $j = 1, ..., r$ gives a basis of V, and each of its vectors is a common eigenvector of every member of $\mathcal{F}$, completing the proof.

Lemma 14.5.4: Sums and Products of Commuting Semisimple or Nilpotent Operators

Let V be a finite dimensional vector space over a field k and let $a, b \in \mathrm{End}_k(V)$ commute.

1. If a and b are semisimple, then $a + b$, $a - b$ and ab are semisimple
2. If a and b are nilpotent, then $a + b$, $a - b$ and ab are nilpotent

***Proof*:**
(1). By lemma 14.5.3 applied to the family $\{a, b\}$, there is a basis in which both a and b are diagonal, and sums, differences and products of diagonal matrices are diagonal.

(2). Say $a^u = 0$ and $b^v = 0$. Since $ab = ba$, the binomial theorem applies and

$$(a \pm b)^{u+v-1} = \sum_{i=0}^{u+v-1} \binom{u+v-1}{i} (\pm 1)^{u+v-1-i}\, a^i b^{u+v-1-i}$$

In each term either $i \geq u$ or $u + v - 1 - i \geq v$, so every term vanishes and $a \pm b$ is nilpotent. Finally, $(ab)^u = a^u b^u = 0$, using commutativity again, completing the proof.

The remaining input is a decomposition of V into pieces on which α is a scalar plus a nilpotent, and it has already been proven in this chapter under another name. When α is not diagonalizable, the eigenspaces of theorem 13.5.15 are too small to fill out V, and the correct enlargement is to relax "killed by $\alpha - \lambda\mathrm{id}$" to "killed by a power of $\alpha - \lambda\mathrm{id}$".

Definition 14.5.5: Generalized Eigenspace

Let V be a finite dimensional vector space over a field k, let $\alpha \in \mathrm{End}_k(V)$ and let $\lambda \in k$. Then the subspace

$$V_\lambda = \left\{ v \in V \middle| (\alpha - \lambda\mathrm{id})^m v = 0 \text{ for some } m \geq 1 \right\}$$

is called the *generalized eigenspace* of α at λ, and its nonzero elements are called *generalized eigenvectors*.

The eigenspace of definition 13.5.9 is the $m = 1$ part of V_λ, and $V_\lambda \neq 0$ exactly when λ is an eigenvalue: if $(\alpha - \lambda\mathrm{id})^m v = 0$ with $v \neq 0$ and m minimal, then $(\alpha - \lambda\mathrm{id})^{m-1} v$ is an eigenvector for λ. The generalized eigenspaces are exactly the primary components of theorem 14.1.12 for the $k[x]$-module structure that α places on V, so the machinery of this chapter already decomposes V into them.

Corollary 14.5.6: Generalized Eigenspace Decomposition

Let V be a nonzero finite dimensional vector space over a field k and let $\alpha \in \mathrm{End}_k(V)$ have characteristic polynomial

$$P_\alpha(x) = \prod_{i=1}^{r} (x - \lambda_i)^{m_i}$$

factoring completely over k, with $\lambda_1, ..., \lambda_r$ distinct. Then

$$V = V_{\lambda_1} \oplus \cdots \oplus V_{\lambda_r} \qquad \text{where} \qquad V_{\lambda_i} = \ker(\alpha - \lambda_i\mathrm{id})^{m_i}$$

and the restriction of $\alpha - \lambda_i\mathrm{id}$ to V_{λ_i} is nilpotent.

***Proof*:**
Regard V as a $k[x]$-module with x acting as α, as in the proof of theorem 14.4.5. It is a nonzero torsion module, and its annihilator is generated by the minimal polynomial $m_\alpha(x)$

(definition 14.2.2), which by lemma 14.4.1 factors as

$$m_\alpha(x) = \prod_{i=1}^{r} (x - \lambda_i)^{\nu_i}$$

where $\nu_i = \max_j r_{ij}$ and $m_i = \sum_j r_{ij}$ in terms of the elementary divisor exponents, so that $1 \leq \nu_i \leq m_i$ for every i. Theorem 14.1.12 applied to this factorization yields

$$V = N_1 \oplus \cdots \oplus N_r$$

where N_i is the kernel of $(\alpha - \lambda_i \mathrm{id})^{\nu_i}$ and equally the set of all elements killed by *some* power of $\alpha - \lambda_i \mathrm{id}$, which is the definition of V_{λ_i}. The sandwich

$$\ker(\alpha - \lambda_i \mathrm{id})^{\nu_i} \subseteq \ker(\alpha - \lambda_i \mathrm{id})^{m_i} \subseteq V_{\lambda_i} = \ker(\alpha - \lambda_i \mathrm{id})^{\nu_i}$$

obtained from $\nu_i \leq m_i$ forces all three subspaces to coincide, and the middle description is the one in the statement. Finally, $(\alpha - \lambda_i \mathrm{id})^{\nu_i}$ vanishes on V_{λ_i} by construction, so the restriction of $\alpha - \lambda_i \mathrm{id}$ to V_{λ_i} is nilpotent, as we sought to show.

Everything is now assembled.

Theorem 14.5.7: Jordan-Chevalley Decomposition

Let V be a nonzero finite dimensional vector space over a field k and let $\alpha \in \mathrm{End}_k(V)$ be an operator whose characteristic polynomial factors into linear factors over k, which holds for every α when k is algebraically closed, with no restriction on the characteristic of k. Then:

1. there exist $s, n \in \mathrm{End}_k(V)$ with

$$\alpha = s + n \qquad sn = ns$$

   where s is semisimple and n is nilpotent

2. there are polynomials $p(t), q(t) \in k[t]$ with zero constant term such that $s = p(\alpha)$ and $n = q(\alpha)$. In particular, s and n commute with every operator that commutes with α, and every α-stable subspace of V is s-stable and n-stable

3. the pair (s, n) is unique: if $\alpha = s' + n'$ with s' semisimple, n' nilpotent and $s'n' = n's'$, then $s' = s$ and $n' = n$

The expression $\alpha = s + n$ is called the *Jordan-Chevalley decomposition* (or *additive Jordan decomposition*) of α, and s and n are called the *semisimple part* and the *nilpotent part* of α.

***Proof*:**
We first build the polynomial p, then verify that $s = p(\alpha)$ and $n = \alpha - s$ have every property claimed, and prove uniqueness last. Throughout, write

$$P_\alpha(x) = \prod_{i=1}^{r} (x - \lambda_i)^{m_i}$$

with $\lambda_1, ..., \lambda_r$ the distinct eigenvalues of α.

Step 1: constructing p by interpolation. We seek a polynomial $p(t) \in k[t]$ satisfying the congruences

$$p(t) \equiv \lambda_i \bmod (t-\lambda_i)^{m_i} \qquad 1 \leq i \leq r$$

together with $p(0) = 0$, which is the congruence $p(t) \equiv 0 \bmod (t)$. For $i \neq j$ the ideals $\left((t-\lambda_i)^{m_i}\right)$ and $\left((t-\lambda_j)^{m_j}\right)$ of $k[t]$ are comaximal: $t-\lambda_i$ and $t-\lambda_j$ are non-associate primes of $k[t]$, so $\gcd\left((t-\lambda_i)^{m_i}, (t-\lambda_j)^{m_j}\right) = 1$, and a Bézout identity in the Euclidean domain $k[t]$ places 1 in the sum of the two ideals, exactly as in the proof of proposition 11.1.6. The congruence at 0 needs care, and there are two cases according to whether 0 is an eigenvalue.

If no λ_i is 0, then $t = t-0$ is a monic linear polynomial distinct from every $t-\lambda_i$, so by the same argument the ideal (t) is comaximal with each $\left((t-\lambda_i)^{m_i}\right)$. The map of the Chinese Remainder Theorem (theorem 9.6.11) is then surjective onto the product of the $r+1$ quotients, and choosing the preimage of the tuple $(\lambda_1, ..., \lambda_r, 0)$ produces a $p(t)$ satisfying all $r+1$ congruences at once. The last congruence says that t divides $p(t)$, which is exactly the vanishing of the constant term.

If instead $\lambda_{i_0} = 0$ for some necessarily unique i_0, the congruence at 0 cannot be imposed as a separate condition, and does not need to be: the ideals (t) and $\left(t^{m_{i_0}}\right)$ are not comaximal, so theorem 9.6.11 does not apply to the enlarged list of $r+1$ ideals, but the i_0-th congruence already reads

$$p(t) \equiv \lambda_{i_0} = 0 \bmod \left(t^{m_{i_0}}\right)$$

Hence we impose only the original r congruences, whose moduli are pairwise comaximal as shown above, and theorem 9.6.11 again provides a solution $p(t)$. Since $m_{i_0} \geq 1$, divisibility by $t^{m_{i_0}}$ implies divisibility by t, and the constant term of p vanishes in this case too, this time as a consequence of the eigenvalue congruence at $\lambda_{i_0} = 0$ rather than as an extra condition.

In both cases the result is a polynomial $p(t)$ with $p(0) = 0$ such that $(t-\lambda_i)^{m_i}$ divides $p(t) - \lambda_i$ for every i. Set

$$s = p(\alpha) \qquad q(t) = t - p(t) \qquad n = q(\alpha) = \alpha - s$$

and note that $q(0) = 0 - p(0) = 0$ as well.

Step 2: s is semisimple and n is nilpotent. By corollary 14.5.6, $V = V_{\lambda_1} \oplus \cdots \oplus V_{\lambda_r}$ with $V_{\lambda_i} = \ker(\alpha - \lambda_i \mathrm{id})^{m_i}$. Fix i and write $p(t) - \lambda_i = h_i(t)\,(t-\lambda_i)^{m_i}$. Evaluating at α and applying to $v \in V_{\lambda_i}$,

$$(s - \lambda_i \mathrm{id})v = h_i(\alpha)(\alpha - \lambda_i \mathrm{id})^{m_i} v = 0$$

so s acts on V_{λ_i} as the scalar λ_i. A basis of V adapted to the direct sum decomposition therefore consists of eigenvectors of s, and s is semisimple. On V_{λ_i} the operator $n = \alpha - s$ acts as $\alpha - \lambda_i \mathrm{id}$, whose m_i-th power kills V_{λ_i}. Setting $m = \max_i m_i$, the power n^m kills every summand and hence all of V, so n is nilpotent.

This proves clauses (1) and (2): s and n are polynomials in α with zero constant term by Step 1, so each is a linear combination of *positive* powers of α. Such operators commute with α, with each other, and with every operator commuting with α, and they carry any α-stable subspace into itself.

Step 3: uniqueness. Let $\alpha = s' + n'$ with s' semisimple, n' nilpotent and $s'n' = n's'$. Then s' commutes with $s' + n' = \alpha$, and so does n'. An operator commuting with α commutes with every power of α and hence with every polynomial in α, so s' and n' commute with s and with n. Rearranging $s + n = s' + n'$ gives

$$s - s' = n' - n$$

and all four operators commute pairwise. By lemma 14.5.4, the left side is semisimple and the right side is nilpotent, so the operator $\delta = s - s' = n' - n$ is both. Being nilpotent, δ has no eigenvalue besides 0: if $\delta v = \mu v$ with $v \neq 0$ and $\delta^m = 0$, then $0 = \delta^m v = \mu^m v$ forces $\mu = 0$. Being semisimple, δ is represented by a diagonal matrix in some basis, and the diagonal entries of a diagonal matrix are eigenvalues, hence all 0. So $\delta = 0$, that is $s' = s$ and $n' = n$, as we sought to show.

In a Jordan basis the decomposition becomes visible: Step 2 makes s act as λ_i on each generalized eigenspace, which is precisely the diagonal of the Jordan canonical form of theorem 14.4.5, and $n = \alpha - s$ is what remains, the superdiagonal of 1s. Uniqueness then says that the recipe "keep the diagonal of the JCF" computes the semisimple part correctly, while the first example below shows that the same recipe applied in any other basis computes nothing of the sort.

Example 14.5.8: Computing a Jordan-Chevalley Decomposition

1. Take $k = \mathbb{Q}$ and
$$A = \begin{pmatrix} 1 & 1 \\ 0 & 2 \end{pmatrix} \qquad \text{so that} \qquad P_A(t) = (t-1)(t-2)$$
Splitting off the diagonal gives a diagonal piece D and a nilpotent piece N with
$$DN = \begin{pmatrix} 1 & 0 \\ 0 & 2 \end{pmatrix}\begin{pmatrix} 0 & 1 \\ 0 & 0 \end{pmatrix} = \begin{pmatrix} 0 & 1 \\ 0 & 0 \end{pmatrix} \neq \begin{pmatrix} 0 & 2 \\ 0 & 0 \end{pmatrix} = ND$$
so $A = D + N$ is *not* the Jordan-Chevalley decomposition of A. Indeed, the minimal polynomial of A has no multiple roots, so A is already diagonalizable by corollary 14.4.7 and its decomposition is $s = A$ and $n = 0$. The recipe of the proof agrees: 0 is not an eigenvalue, and the congruences
$$p \equiv 1 \bmod (t-1) \qquad p \equiv 2 \bmod (t-2) \qquad p \equiv 0 \bmod (t)$$
are solved by $p(t) = t$, so $s = p(A) = A$.

2. Now take
$$B = \begin{pmatrix} 1 & 1 & 0 \\ 0 & 1 & 0 \\ 0 & 0 & 2 \end{pmatrix} \qquad \text{so that} \qquad P_B(t) = (t-1)^2(t-2)$$
Again 0 is not an eigenvalue, so the proof imposes the congruences
$$p \equiv 1 \bmod (t-1)^2 \qquad p \equiv 2 \bmod (t-2) \qquad p \equiv 0 \bmod (t)$$
The moduli multiply to the degree 4 polynomial $t(t-1)^2(t-2)$, so there is a unique solution of degree at most 3, namely
$$p(t) = t^3 - 3t^2 + 3t$$
All three congruences can be checked directly: $p(t)$ has no constant term, $p(t) - 1 = (t-1)^3$, and $p(2) = 8 - 12 + 6 = 2$. To compute $s = p(B)$, note that on the upper 2×2 Jordan block J the identity $p(t) = (t-1)^3 + 1$ gives $p(J) = (J-I)^3 + I = I$, since $(J-I)^2 = 0$, while on the lower block $p(2) = 2$. Hence
$$s = \begin{pmatrix} 1 & 0 & 0 \\ 0 & 1 & 0 \\ 0 & 0 & 2 \end{pmatrix} \qquad n = B - s = \begin{pmatrix} 0 & 1 & 0 \\ 0 & 0 & 0 \\ 0 & 0 & 0 \end{pmatrix}$$
and a direct multiplication confirms $sn = ns$, both products being equal to n.

One clause of the theorem deserves a closing word. Interpolation without the congruence at 0 would already produce commuting semisimple and nilpotent parts, so the zero constant term looks like a free refinement, and Step 1 of the proof shows that it costs nothing. It is nevertheless the clause that transfers the strongest properties of α to s and n. A polynomial in α with constant term $c \neq 0$ acts as $c\mathrm{id}$ plus a combination of positive powers of α, and the summand $c\mathrm{id}$ carries any nonzero subspace onto itself, never into a smaller one. With the constant term gone that obstruction disappears: whenever $W' \subseteq W$ are subspaces with $\alpha(W) \subseteq W'$, every positive power of α also carries W into W', hence so do s and n. The semisimple and nilpotent parts therefore satisfy every containment of the form $\alpha(W) \subseteq W'$ that α satisfies, of which stability is the special case $W' = W$. This stronger inheritance is invisible at the level of a single matrix, and it becomes essential the moment operators are constrained to lie in a subspace of $\mathrm{End}_k(V)$ that does not contain the identity.

15

Tensor Products Of Modules: Linear Algebra III

The results of chapter 13 and chapter 14 describe modules and the linear maps between them, and several of the objects those chapters produced are not linear maps. The determinant of section 13.4 takes n column vectors and is linear in each one separately, not in all of them together. An inner product (section 13.6) takes two vectors and is linear in each. The consequence is that such maps are not morphisms in Vect_k, so no theorem about morphisms applies to them. Multiplication in a ring is the same phenomenon at its most basic. The map $R \times R \to R$ sending (a, b) to ab is additive in each variable when the other is held fixed, and it is not additive in the pair: the product $(a + a')(b + b')$ is $ab + ab' + a'b + a'b'$, not $ab + a'b'$.

This chapter removes the obstruction by changing the domain rather than the map in a natural way. From two modules M and N over a ring R it constructs a single module $M \otimes_R N$, together with a bilinear map $M \times N \to M \otimes_R N$ through which every bilinear map out of $M \times N$ factors, uniquely, as a homomorphism out of $M \otimes_R N$. A question about bilinear maps on $M \times N$ then becomes a question about homomorphisms on $M \otimes_R N$, where the machinery of the previous two chapters applies. Iterating the construction on a single module produces the tensor algebra $\mathcal{T}(M)$ and its two quotients, the symmetric algebra $\mathcal{S}(M)$ and the exterior algebra $\bigwedge(M)$. The determinant reappears in section 16.4 as the map an endomorphism induces on the top exterior power.

15.1 The Tensor Product of Modules

Suppose for a moment that the module $M \otimes_R N$ has been built, along with a map $\iota\colon M \times N \to M \otimes_R N$ whose value at (m, n) is written $m \otimes n$. Asking that ι be additive in each variable forces

$$(m_1 + m_2) \otimes n = m_1 \otimes n + m_2 \otimes n, \qquad m \otimes (n_1 + n_2) = m \otimes n_1 + m \otimes n_2$$

giving relations any construction must impose. The condition governing scalars needs more care. Take R commutative first, with M, N and the target L all R-modules. A map $\varphi\colon M \times N \to L$ that is R-linear in each variable satisfies

$$\varphi(rm, n) = r\varphi(m, n) = \varphi(m, rn)$$

so a scalar may be moved from one argument to the other. Over a non-commutative ring that same conditin is nearly vacuous. Suppose M, N and L are left R-modules and φ is R-linear in each variable. Evaluating $\varphi(rm, sn)$ two ways, once by extracting s from the second argument and once by extracting r from the first, gives

$$(sr)\varphi(m, n) = s\varphi(rm, n) = \varphi(rm, sn) = r\varphi(m, sn) = (rs)\varphi(m, n)$$

so that $(rs - sr)\varphi(m, n) = 0$ for every $m \in M$ and $n \in N$. Any such φ is annihilated by every commutator in R, and over a ring with few central elements this leaves almost nothing.

The repair is to weaken the condition in two places. The target drops from an R-module to an abelian group, so that "pulling out a scalar" is no longer available and cannot be contradicted. And the two modules are taken on opposite sides, M a right R-module and N a left one, so that the surviving requirement $\varphi(mr, n) = \varphi(m, rn)$ moves a scalar across the comma without ever moving it outside. This is the condition the construction can enforce.

Definition 15.1.1: R-Balanced Map

Let R be a ring, let M be a right R-module, let N be a left R-module, and let L be an abelian group written additively. A map $\varphi\colon M \times N \to L$ is *R-balanced*, or *middle linear over R*, if for all $m, m_1, m_2 \in M$, all $n, n_1, n_2 \in N$ and all $r \in R$,

$$\begin{aligned} \varphi(m_1 + m_2, n) &= \varphi(m_1, n) + \varphi(m_2, n) \\ \varphi(m, n_1 + n_2) &= \varphi(m, n_1) + \varphi(m, n_2) \\ \varphi(mr, n) &= \varphi(m, rn) \end{aligned}$$

The third axiom is the only one that mentions R at all, and it is weaker than linearity in either variable, since it never asserts what happens to a scalar that is pulled out of the map, namely as L has no module structure.

Example 15.1.2: R-Balanced Maps

1. Let R be commutative and let M, N, L be R-modules, with $mr := rm$ making M a right R-module. Every map that is R-linear in each variable is R-balanced: $\varphi(mr, n) = \varphi(rm, n) = r\varphi(m, n) = \varphi(m, rn)$. So over a commutative ring the balanced condition is implied by, and strictly weaker than, bilinearity.

2. For any ring R and any right R-module M, the action map $M \times R \to M$ sending (m, r) to mr is R-balanced, where R is viewed as a left module over itself. Additivity in each variable is a module axiom, and the third axiom is associativity of the action: $(ms)r = m(sr)$.

3. Take $R = \mathbb{Z}$. Every $\mathbb{Z}$-module is an abelian group and every abelian group is a $\mathbb{Z}$-module (section 12.1), so a $\mathbb{Z}$-balanced map is exactly a map additive in each variable: the third axiom, $\varphi(mk, n) = \varphi(m, kn)$ for $k \in \mathbb{Z}$, already follows from the first two. Balanced maps over $\mathbb{Z}$ therefore impose no condition beyond biadditivity.

4. The determinant of a 2×2 matrix, read as a map $F^2 \times F^2 \to F$ sending the pair of columns $\big((a,b),(c,d)\big)$ to $ad - bc$, is F-bilinear (section 13.4) and hence F-balanced. It is one of the maps this chapter exists to bring inside linear algebra.

The construction now writes down the freest object carrying such a map. Start with a group in which the pairs (m, n) satisfy nothing whatsoever, then impose the three axioms of definition 15.1.1 by hand. Write $F^{\mathbb{Z}}(A)$ for the free $\mathbb{Z}$-module on a set A (theorem 12.3.11), that is, the free abelian group with basis A.

Applied to the underlying *set* of $M \times N$, this group is enormous. If $R = \mathbb{R}$, $M = \mathbb{R}^2$ and $N = \mathbb{R}^3$, the basis of $F^{\mathbb{Z}}(M \times N)$ is the whole of $\mathbb{R}^2 \times \mathbb{R}^3$, so distinct pairs (m, n) and (m', n') are independent generators even when m and m' differ by a scalar. Nothing that holds in M or in N survives into $F^{\mathbb{Z}}(M \times N)$. Every relation the tensor product satisfies has to be put in by quotienting.

Definition 15.1.3: Tensor Product

Let R be a ring, let M be a right R-module and let N be a left R-module. Let $K \subseteq F^{\mathbb{Z}}(M \times N)$ be the subgroup generated by all elements of the three forms

$$\begin{aligned} &(m_1 + m_2,\ n) - (m_1, n) - (m_2, n) \\ &(m,\ n_1 + n_2) - (m, n_1) - (m, n_2) \\ &(mr,\ n) - (m, rn) \end{aligned}$$

taken over all $m, m_1, m_2 \in M$, all $n, n_1, n_2 \in N$ and all $r \in R$. The *tensor product of M and N over R* is the quotient group

$$M \otimes_R N := F^{\mathbb{Z}}(M \times N)/K$$

The coset of the basis element (m, n) is written $m \otimes n$ and is called a *simple tensor*. The subscript R is dropped when the ring is clear from context.

Killing K is exactly what makes the three defining identities hold in the quotient, so that for all $m, m_i \in M$, $n, n_i \in N$ and $r \in R$,

$$\begin{gathered} (m_1 + m_2) \otimes n = m_1 \otimes n + m_2 \otimes n \qquad m \otimes (n_1 + n_2) = m \otimes n_1 + m \otimes n_2 \\ mr \otimes n = m \otimes rn \end{gathered} \tag{15.1}$$

These three are the only relations available. Anything else true in $M \otimes_R N$ has to be derived from them, and the next lemma is the derivation used most often.

Lemma 15.1.4: Simple Tensors Generate

Let M be a right R-module and N a left R-module. Then

1. $0 \otimes n = 0$ and $m \otimes 0 = 0$ for all $m \in M$, $n \in N$;
2. every element of $M \otimes_R N$ is a finite sum $\sum_{i=1}^{k} m_i \otimes n_i$ of simple tensors;
3. two group homomorphisms $M \otimes_R N \to L$ that agree on every simple tensor are equal.

***Proof*:**

1. By the first identity in (15.1) applied to $m_1 = m_2 = 0$, one has $0 \otimes n = (0+0) \otimes n = 0 \otimes n + 0 \otimes n$, and subtracting $0 \otimes n$ from both sides in the group $M \otimes_R N$ gives $0 \otimes n = 0$. The argument for $m \otimes 0$ is the same using the second identity.

2. The group $F^{\mathbb{Z}}(M \times N)$ is generated by its basis, so every element of it is a finite sum $\sum_i k_i(m_i, n_i)$ with $k_i \in \mathbb{Z}$, and the quotient map is surjective, so every element of $M \otimes_R N$ is a finite sum $\sum_i k_i(m_i \otimes n_i)$. It therefore suffices to see that an integer multiple of a simple tensor is again a simple tensor. For $k \geq 0$ induction on k using the first identity in (15.1) gives $k(m \otimes n) = (km) \otimes n$, the base case $k = 0$ being part (1). For $k < 0$ it suffices to treat $k = -1$, and

$$(-m) \otimes n + m \otimes n = (-m + m) \otimes n = 0 \otimes n = 0$$

gives $(-m) \otimes n = -(m \otimes n)$, so $k(m \otimes n) = (km) \otimes n$ for every $k \in \mathbb{Z}$.

3. Let ψ, ψ' be two such homomorphisms. The set on which two group homomorphisms agree is a subgroup of the domain, and by (2) the simple tensors generate $M \otimes_R N$, so that subgroup is everything, completing the proof.

Part (2) says that every element of the tensor product is a finite sum of simple tensors. It does not say that every element *is* a simple tensor, and that distinction is the most common source of error in computations with tensor products. Box 15.1.6 exhibits an element that is not simple.

The definition of $M \otimes_R N$ was engineered to make ι balanced and to impose nothing further. The following theorem is the statement that it succeeded, and it is the only property of the tensor product used from here on: every later result in this chapter is proved from it rather than from the quotient construction.

Theorem 15.1.5: Universal Property of the Tensor Product

Let R be a ring, let M be a right R-module and let N be a left R-module. The map

$$\iota \colon M \times N \to M \otimes_R N, \qquad \iota(m, n) = m \otimes n$$

is R-balanced, and it is universal among such maps: for every abelian group L and every R-balanced map $\varphi \colon M \times N \to L$ there is a unique group homomorphism $\psi \colon M \otimes_R N \to L$ with $\varphi = \psi \circ \iota$, that is, making

$$\begin{array}{ccc} M \otimes_R N & \xrightarrow{\ \psi\ } & L \\ {\scriptstyle \iota}\uparrow & \nearrow_{\varphi} & \\ M \times N & & \end{array}$$

commute.

***Proof*:**
That ι is R-balanced is precisely the three identities (15.1), which hold because the corresponding elements of $F^{\mathbb{Z}}(M \times N)$ were placed in K.

Existence. Regard $M \times N$ as a set and φ as a map of sets into the abelian group L, which is a $\mathbb{Z}$-module. By the universal property of free modules (theorem 12.3.11, applied with $R = \mathbb{Z}$) there is a group homomorphism $\tilde{\varphi}\colon F^{\mathbb{Z}}(M \times N) \to L$ with $\tilde{\varphi}\big((m,n)\big) = \varphi(m,n)$ on each basis element. Evaluating $\tilde{\varphi}$ on the three families of generators of K gives

$$\begin{aligned}\tilde{\varphi}\big((m_1+m_2,n)-(m_1,n)-(m_2,n)\big) &= \varphi(m_1+m_2,n)-\varphi(m_1,n)-\varphi(m_2,n) = 0\\ \tilde{\varphi}\big((m,n_1+n_2)-(m,n_1)-(m,n_2)\big) &= \varphi(m,n_1+n_2)-\varphi(m,n_1)-\varphi(m,n_2) = 0\\ \tilde{\varphi}\big((mr,n)-(m,rn)\big) &= \varphi(mr,n)-\varphi(m,rn) = 0\end{aligned}$$

each vanishing by the corresponding axiom of definition 15.1.1. A subgroup is generated by any set whose elements it contains together with their sums and inverses, and $\ker\tilde{\varphi}$ is a subgroup containing all three families, so $K \subseteq \ker\tilde{\varphi}$. Since $F^{\mathbb{Z}}(M \times N)$ is abelian, K is normal in it, so theorem 3.1.15 applies and yields a unique map $\psi\colon F^{\mathbb{Z}}(M \times N)/K \to L$ with $\tilde{\varphi} = \psi \circ \pi$, where π is the quotient map. It is a group homomorphism, since for $x, y \in F^{\mathbb{Z}}(M \times N)$,

$$\psi\big(\pi(x)+\pi(y)\big) = \psi\big(\pi(x+y)\big) = \tilde{\varphi}(x+y) = \tilde{\varphi}(x)+\tilde{\varphi}(y) = \psi(\pi(x))+\psi(\pi(y))$$

and π is surjective. Reading the identity $\tilde{\varphi} = \psi \circ \pi$ on the basis element (m,n) gives $\psi(m \otimes n) = \varphi(m,n)$, which is $\varphi = \psi \circ \iota$.

Uniqueness. A homomorphism ψ' with $\varphi = \psi' \circ \iota$ satisfies $\psi'(m \otimes n) = \varphi(m,n) = \psi(m \otimes n)$ for every simple tensor, so $\psi' = \psi$ by lemma 15.1.4, completing the proof.

The theorem is what converts the tensor product from a construction into a tool. To produce a homomorphism out of $M \otimes_R N$ one never returns to cosets of a free group: one writes down a balanced map on $M \times N$, checks three identities, and reads off the homomorphism. To prove two homomorphisms out of $M \otimes_R N$ equal, one checks them on simple tensors. Both moves are used repeatedly below, starting immediately.

15.1.6 Warning: Not Every Tensor Is Simple Let F be a field, let $V = F^2$ with standard basis e_1, e_2, and consider

$$t = e_1 \otimes e_1 + e_2 \otimes e_2 \in V \otimes_F V$$

Then t is not a simple tensor. Suppose $t = v \otimes w$. For linear functionals $f, g \in V^*$ (section 13.3) the map $V \times V \to F$ sending (x,y) to $f(x)g(y)$ is F-bilinear, hence F-balanced, so by theorem 15.1.5 below it induces a homomorphism $\theta_{f,g}\colon V \otimes_F V \to F$ with $\theta_{f,g}(x \otimes y) = f(x)g(y)$. Evaluating on both expressions for t,

$$f(v)g(w) = \theta_{f,g}(t) = f(e_1)g(e_1) + f(e_2)g(e_2)$$

Taking (f,g) to be (e_1^*, e_1^*), then (e_2^*, e_2^*), then (e_1^*, e_2^*) gives in turn $v_1w_1 = 1$, $v_2w_2 = 1$ and $v_1w_2 = 0$, where $v = v_1e_1 + v_2e_2$ and $w = w_1e_1 + w_2e_2$. The first two force v_1 and w_2 to be nonzero, contradicting the third.

A consequence worth recording is that the pair $(M \otimes_R N, \iota)$ is pinned down by the theorem, so the arbitrary choices in definition 15.1.3 leave no trace.

Corollary 15.1.7: Uniqueness of the Tensor Product

Let T be an abelian group and $j\colon M \times N \to T$ an R-balanced map with the property that for every abelian group L and every R-balanced $\varphi\colon M \times N \to L$ there is a unique homomorphism $\psi\colon T \to L$ with $\varphi = \psi \circ j$. Then there is a unique isomorphism $\theta\colon M \otimes_R N \to T$ with $\theta \circ \iota = j$.

***Proof*:**
Applying theorem 15.1.5 to the balanced map j gives a homomorphism $\theta\colon M \otimes_R N \to T$ with $\theta \circ \iota = j$, and applying the hypothesis on T to the balanced map ι gives $\eta\colon T \to M \otimes_R N$ with $\eta \circ j = \iota$. Then $\eta \circ \theta$ is an endomorphism of $M \otimes_R N$ satisfying $(\eta \circ \theta) \circ \iota = \iota$, and so is the identity. By the uniqueness clause of theorem 15.1.5 applied to $\varphi = \iota$, the two agree. Symmetrically $\theta \circ \eta = \mathrm{id}_T$, using the uniqueness clause assumed for T. Hence θ is an isomorphism, and it is the unique one satisfying $\theta \circ \iota = j$ by that same uniqueness clause, as we sought to show.

So far $M \otimes_R N$ is only an abelian group, and definition 15.1.1 was designed to make that unavoidable: nothing in the data of a right module M and a left module N produces an R-action on the tensor product. A module structure has to come from somewhere else, and the smallest extra hypothesis that gives one is a second, compatible action on one of the factors.

Definition 15.1.8: (S, R)-Bimodule

Let R and S be rings. An abelian group M is an (S, R)-*bimodule* if it is a left S-module, a right R-module, and the two actions commute:

$$s(mr) = (sm)r \qquad \text{for all } s \in S,\ r \in R,\ m \in M$$

Example 15.1.9: Bimodules

1. Any ring R is an (R, R)-bimodule over itself, with both actions given by ring multiplication. The compatibility axiom is associativity, $s(mr) = (sm)r$.
2. Let $f\colon R \to S$ be a ring homomorphism. Then S is an (S, R)-bimodule: the left S-action is multiplication in S, and the right R-action is $s \cdot r := sf(r)$. Compatibility reads $s'(sf(r)) = (s's)f(r)$, which is associativity in S. This is the structure that makes extension of scalars along f possible, and it is taken up in section 15.3.
3. As a special case of (2), let $I \subseteq R$ be a two-sided ideal and $f\colon R \to R/I$ the quotient map. Then R/I is an $(R/I, R)$-bimodule.
4. Let R be commutative and M an R-module. Setting $mr := rm$ makes M an (R, R)-bimodule, since the compatibility axiom $s(mr) = (sm)r$ reads $(sr)m = (rs)m$. This is called the *standard* bimodule structure on M, and it is the structure meant whenever a module over a commutative ring is treated as a bimodule without further comment.

Proposition 15.1.10: Module Structure on the Tensor Product

Let M be an (S, R)-bimodule and let N be a left R-module. Then $M \otimes_R N$ is a left S-module under the action determined by

$$s \cdot (m \otimes n) = (sm) \otimes n$$

on simple tensors.

***Proof*:**
Fix $s \in S$ and consider $\lambda_s \colon M \times N \to M \otimes_R N$ defined by $\lambda_s(m, n) = (sm) \otimes n$. It is R-balanced. Additivity in the first variable holds because $s(m_1 + m_2) = sm_1 + sm_2$ and $\otimes$ is additive in its first argument. Additivity in the second is immediate. For the third axiom, the bimodule condition gives $s(mr) = (sm)r$, so

$$\lambda_s(mr, n) = \big(s(mr)\big) \otimes n = \big((sm)r\big) \otimes n = (sm) \otimes rn = \lambda_s(m, rn)$$

the middle equality being the third relation of (15.1). By theorem 15.1.5 there is therefore a unique group endomorphism Λ_s of $M \otimes_R N$ with $\Lambda_s(m \otimes n) = (sm) \otimes n$. Define $s \cdot x := \Lambda_s(x)$ for $x \in M \otimes_R N$. This is additive in x because Λ_s is a homomorphism.

The remaining module axioms are equalities between group homomorphisms $M \otimes_R N \to M \otimes_R N$, so by lemma 15.1.4 each may be checked on simple tensors alone. On $m \otimes n$,

$$\begin{aligned}
\Lambda_{s+s'}(m \otimes n) &= \big((s + s')m\big) \otimes n = (sm + s'm) \otimes n \\
&= (sm) \otimes n + (s'm) \otimes n = (\Lambda_s + \Lambda_{s'})(m \otimes n) \\
\Lambda_{ss'}(m \otimes n) &= \big((ss')m\big) \otimes n = \big(s(s'm)\big) \otimes n \\
&= \Lambda_s\big((s'm) \otimes n\big) = (\Lambda_s \circ \Lambda_{s'})(m \otimes n) \\
\Lambda_1(m \otimes n) &= (1m) \otimes n = m \otimes n
\end{aligned}$$

using in each case only a left S-module axiom for M. Hence $\Lambda_{s+s'} = \Lambda_s + \Lambda_{s'}$, $\Lambda_{ss'} = \Lambda_s \circ \Lambda_{s'}$ and $\Lambda_1 = \mathrm{id}$, which are exactly the axioms making $M \otimes_R N$ a left S-module, completing the proof.

The proof is a template for everything that follows: a map is defined on simple tensors, shown balanced, promoted to a homomorphism by theorem 15.1.5, and its properties are then checked on simple tensors by lemma 15.1.4. No later argument in this chapter returns to the free group.

Specializing to a commutative ring recovers the situation the chapter opened with, in which both factors and the target are modules over the same ring and the universal property is stated for bilinear maps. That case needs the module-theoretic form of bilinearity, which definition 13.3.15 gave only for vector spaces with target the base field.

Definition 15.1.11: R-Bilinear Map

Let R be a commutative ring and let M, N and L be R-modules. A map $\varphi \colon M \times N \to L$ is *R-bilinear* if for each fixed $n \in N$ the map $\varphi(-, n) \colon M \to L$ is an R-module homomorphism, and for each fixed $m \in M$ the map $\varphi(m, -) \colon N \to L$ is an R-module homomorphism.

Theorem 15.1.12: Universal Property Of Tensor Product (Over Commutative Rings)

Let R be a commutative ring and let M, N be R-modules, each carrying its standard bimodule structure. Then $M \otimes_R N$ is an R-module, the map $\iota\colon M \times N \to M \otimes_R N$ is R-bilinear, and for every R-module L and every R-bilinear map $\varphi\colon M \times N \to L$ there is a unique R-module homomorphism $\psi\colon M \otimes_R N \to L$ with $\varphi = \psi \circ \iota$.

***Proof*:**
The R-module structure is proposition 15.1.10 applied with $S = R$, using the standard bimodule structure on M from example 15.1.9(4). Explicitly, $r(m \otimes n) = (rm) \otimes n$. That ι is R-bilinear now follows from (15.1) together with this action: it is additive in each variable, $r(m \otimes n) = (rm) \otimes n$ by definition of the action, and $r(m \otimes n) = (mr) \otimes n = m \otimes rn$ by the third relation.

Let φ be R-bilinear. By example 15.1.2(1) it is R-balanced, so theorem 15.1.5 gives a unique group homomorphism ψ with $\varphi = \psi \circ \iota$. It remains to see that ψ is R-linear. Fix $r \in R$. The two maps $x \mapsto \psi(rx)$ and $x \mapsto r\psi(x)$ are group homomorphisms $M \otimes_R N \to L$, and on a simple tensor

$$\psi\big(r(m \otimes n)\big) = \psi\big((rm) \otimes n\big) = \varphi(rm, n) = r\varphi(m, n) = r\psi(m \otimes n)$$

so they agree on all simple tensors and hence are equal by lemma 15.1.4. Thus ψ is R-linear. Uniqueness is inherited: an R-module homomorphism satisfying $\varphi = \psi \circ \iota$ is in particular a group homomorphism satisfying it, and there is only one of those, as we sought to show.

Two computations show what the construction does to familiar modules, and they point in opposite directions. The first says that tensoring against the ring itself changes nothing; the second says that tensoring two nonzero modules can annihilate both.

Example 15.1.13: Tensoring Against the Ring
Let R be a ring and N a left R-module. Then $R \otimes_R N \cong N$ as left R-modules, where R carries its (R, R)-bimodule structure from example 15.1.9(1).

The action map $\mu\colon R \times N \to N$ with $\mu(r, n) = rn$ is R-balanced: additivity in each variable is a module axiom, and $\mu(rs, n) = (rs)n = r(sn) = \mu(r, sn)$. By theorem 15.1.5 it induces a group homomorphism $\bar{\mu}\colon R \otimes_R N \to N$ with $\bar{\mu}(r \otimes n) = rn$. In the other direction let $\nu\colon N \to R \otimes_R N$ be $\nu(n) = 1 \otimes n$, which is additive. Then $\bar{\mu}(\nu(n)) = \bar{\mu}(1 \otimes n) = n$, so $\bar{\mu} \circ \nu = \mathrm{id}_N$. For the other composite, on a simple tensor

$$\nu\big(\bar{\mu}(r \otimes n)\big) = \nu(rn) = 1 \otimes rn = 1 \cdot r \otimes n = r \otimes n$$

the third equality being the third relation of (15.1) read backwards. So $\nu \circ \bar{\mu}$ agrees with the identity on simple tensors and is the identity by lemma 15.1.4. Finally $\bar{\mu}$ is R-linear, since $\bar{\mu}\big(s(r \otimes n)\big) = \bar{\mu}\big((sr) \otimes n\big) = (sr)n = s(rn) = s\,\bar{\mu}(r \otimes n)$ on simple tensors.

Example 15.1.14: Tensor Products of Cyclic Groups

1. $\mathbb{Z}/2\mathbb{Z} \otimes_{\mathbb{Z}} \mathbb{Z}/3\mathbb{Z} = 0$. Since $3 \equiv 1 \pmod 2$, one has $\bar{a} = 3\bar{a}$ in $\mathbb{Z}/2\mathbb{Z}$ for every a, and therefore

$$\bar{a} \otimes \bar{b} = (3\bar{a}) \otimes \bar{b} = \bar{a} \otimes (3\bar{b}) = 0$$

using $3\bar{b} = \bar{0}$ in $\mathbb{Z}/3\mathbb{Z}$. So every simple tensor vanishes, and by lemma 15.1.4(2) the whole group is zero.

2. $\mathbb{Z}/2\mathbb{Z} \otimes_{\mathbb{Z}} \mathbb{Z}/2\mathbb{Z} \cong \mathbb{Z}/2\mathbb{Z}$. The same manipulation is unavailable here, and in fact $\bar{1} \otimes \bar{1} \neq 0$. To see it, the multiplication map $\mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z} \to \mathbb{Z}/2\mathbb{Z}$ sending $(\bar{a}, \bar{b})$ to $\overline{ab}$ is $\mathbb{Z}$-balanced, so it induces Φ with $\Phi(\bar{1} \otimes \bar{1}) = \bar{1} \neq 0$. A homomorphism sends 0 to 0, so $\bar{1} \otimes \bar{1} \neq 0$. Conversely every simple tensor is $\bar{a} \otimes \bar{b}$ with $a, b \in \{0, 1\}$, hence is 0 or $\bar{1} \otimes \bar{1}$, so by lemma 15.1.4(2) the group $\mathbb{Z}/2\mathbb{Z} \otimes_{\mathbb{Z}} \mathbb{Z}/2\mathbb{Z}$ is cyclic, generated by $t = \bar{1} \otimes \bar{1}$. That generator satisfies $2t = (2\bar{1}) \otimes \bar{1} = \bar{0} \otimes \bar{1} = 0$, so it has order dividing 2, and it is nonzero, so its order is exactly 2. Hence $\mathbb{Z}/2\mathbb{Z} \otimes_{\mathbb{Z}} \mathbb{Z}/2\mathbb{Z} \cong \mathbb{Z}/2\mathbb{Z}$, with Φ the isomorphism.

The contrast between the two computations is the first real content of the construction. Both $\mathbb{Z}/2\mathbb{Z}$ and $\mathbb{Z}/3\mathbb{Z}$ are nonzero, and their tensor product is not. So $\otimes_R$ is not a construction that remembers its inputs. The mechanism is visible in the computation: the relation $mr \otimes n = m \otimes rn$ lets a scalar be moved from a factor where it acts invertibly to one where it acts as zero. Section 15.3 turns this from an obstruction into a tool, and the systematic account of which sequences of modules survive tensoring is the subject of section 17.5.

Example 15.1.15: Tensors as Multilinear Maps

Outside algebra, and particularly in physics and in analysis, the word "tensor" usually names a multilinear map rather than an element of a tensor product. In that convention a k-tensor on a vector space V over F *is* a multilinear map $T\colon V^k \to F$, and the tensor product of a k-tensor T and an ℓ-tensor S is defined directly by the formula

$$(T \otimes S)(x_1, \ldots, x_k, y_1, \ldots, y_\ell) = T(x_1, \ldots, x_k) \cdot S(y_1, \ldots, y_\ell)$$

which is again multilinear, now in $k + \ell$ arguments.

The two usages agree when V is finite dimensional. A multilinear map $V^k \to F$ is the same thing as a linear functional on $V^{\otimes k}$, which is the universal property of theorem 15.2.11 below, and for finite-dimensional V the space of such functionals is identified with $(V^*)^{\otimes k}$ by the basis computation of corollary 15.2.6. Under that identification the displayed formula is the image of $T \otimes S$ in the sense of definition 15.1.3. The reason for the analyst's convention is that a multilinear map has a domain and a target, so conditions like continuity, differentiability, or being C^r can be imposed on it. An element of an abstract quotient group cannot carry such conditions until it is realized as a function. This is the form in which tensors appear in *Calculus on Manifolds* [18].

Exercise 15.1.1

1. Let R be a ring and M a right R-module, with R carrying its (R, R)-bimodule structure. Show that $M \otimes_R R \cong M$, and identify the isomorphism on simple tensors.

2. Let $m, n \geq 1$ and let $d = \gcd(m, n)$. Show that

$$\mathbb{Z}/m\mathbb{Z} \otimes_{\mathbb{Z}} \mathbb{Z}/n\mathbb{Z} \cong \mathbb{Z}/d\mathbb{Z}$$

(Suggestion: since $\mathbb{Z}$ is a principal ideal domain, $(d) = (m) + (n)$ by definition 10.1.24, so $d = um + vn$ for some $u, v \in \mathbb{Z}$. Use this to show first that d annihilates the left-hand side.)

3. Let R be a ring, M a right R-module and N a left R-module, and suppose there is an $r \in R$

with $Mr = 0$ and $rN = N$. Show that $M \otimes_R N = 0$. Deduce that $\mathbb{Q} \otimes_{\mathbb{Z}} A = 0$ for every finite abelian group A, and that $\mathbb{Q}/\mathbb{Z} \otimes_{\mathbb{Z}} \mathbb{Q}/\mathbb{Z} = 0$.

4. Let R be commutative, let M be generated as an R-module by a set X and let N be generated by a set Y. Show that $M \otimes_R N$ is generated as an R-module by the simple tensors $x \otimes y$ with $x \in X$ and $y \in Y$. Give an example showing that these need not be independent.

5. Let M be a right R-module, N a left R-module and L an abelian group. Show that $\varphi \mapsto \psi$ is a bijection from the set of R-balanced maps $M \times N \to L$ onto $\mathrm{Hom}_{\mathbb{Z}}(M \otimes_R N, L)$, and that it commutes with composition by a homomorphism $L \to L'$.

6. Let R be commutative, let A, B, M be R-modules and let $f\colon A \to M$ and $g\colon B \to M$ be R-linear. Show that $(a, b) \mapsto f(a) + g(b)$ is an R-module homomorphism $A \oplus B \to M$, and exhibit f and g for which it is not R-bilinear. Conclude that $A \oplus B$ and $A \otimes_R B$ solve different universal problems.

15.2 Properties of the Tensor Product

With one exception, named where it occurs, no proof below returns to the free abelian group of section 15.1. Everything is derived from theorem 15.1.5 and lemma 15.1.4, by the two moves those results give: to produce a map out of a tensor product, write down a balanced map and invoke the universal property; to prove two maps out of a tensor product equal, check them on simple tensors. What follows records how $\otimes_R$ interacts with each construction the previous chapters gave, in the order in which the proofs depend on one another: homomorphisms, direct sums, free modules, and then the two structural isomorphisms, commutativity and associativity, that make an unbracketed $M_1 \otimes \cdots \otimes M_n$ meaningful. The section closes with the ring structure carried by a tensor product of algebras.

Proposition 15.1.10 produced a left module structure from a second action on the left-hand factor. A second action on the right-hand factor does the mirror-image job, and the two are independent, so both can be imposed at once. The right action is what theorem 15.2.8 needs, since there the middle factor of a triple product is acted on from both sides.

Proposition 15.2.1: Two-Sided Module Structure on a Tensor Product

Let R, S, T be rings, let M be an (S, R)-bimodule and let N be an (R, T)-bimodule. Then $M \otimes_R N$ is an (S, T)-bimodule, with actions determined on simple tensors by

$$s \cdot (m \otimes n) = (sm) \otimes n \qquad \text{and} \qquad (m \otimes n) \cdot t = m \otimes (nt)$$

***Proof*:**

The left S-module structure is proposition 15.1.10, which uses only that M is an (S, R)-bimodule and N a left R-module.

For the right T-action, fix $t \in T$ and consider $\rho_t\colon M \times N \to M \otimes_R N$ given by $\rho_t(m, n) = m \otimes (nt)$. It is R-balanced: additivity in m is additivity of $\otimes$ in its first argument; additivity in n follows because $n \mapsto nt$ is additive and $\otimes$ is additive in its second argument; and for the third axiom

the (R,T)-bimodule condition on N gives $r(nt) = (rn)t$, so

$$\rho_t(mr, n) = (mr) \otimes (nt) = m \otimes r(nt) = m \otimes (rn)t = \rho_t(m, rn)$$

the middle equality being the third relation of (15.1). By theorem 15.1.5 there is a unique group endomorphism P_t of $M \otimes_R N$ with $P_t(m \otimes n) = m \otimes nt$. Set $x \cdot t := P_t(x)$, which is additive in x because P_t is a homomorphism.

The remaining right-module axioms are equalities of group homomorphisms, so by lemma 15.1.4(3) each may be checked on simple tensors:

$$\begin{aligned} P_{t+t'}(m \otimes n) &= m \otimes n(t+t') = m \otimes (nt + nt') = m \otimes nt + m \otimes nt' = (P_t + P_{t'})(m \otimes n) \\ P_{tt'}(m \otimes n) &= m \otimes n(tt') = m \otimes (nt)t' = P_{t'}(m \otimes nt) = (P_{t'} \circ P_t)(m \otimes n) \\ P_1(m \otimes n) &= m \otimes n1 = m \otimes n \end{aligned}$$

The second line gives $x(tt') = (xt)t'$, which is the associativity axiom for a *right* action, the order of composition being reversed exactly as it should be. Finally the two actions commute: $x \mapsto s(xt)$ and $x \mapsto (sx)t$ are group homomorphisms, and on a simple tensor both give $(sm)\otimes(nt)$, so they agree by lemma 15.1.4(3), completing the proof.

Homomorphisms of the two factors induce a homomorphism of the tensor product, and the assignment respects composition. This is what makes $\otimes_R$ usable inside diagrams rather than only on individual modules.

Theorem 15.2.2: The Tensor Product of Two Homomorphisms

Let $\varphi\colon M \to M'$ be a homomorphism of right R-modules and let $\psi\colon N \to N'$ be a homomorphism of left R-modules.

1. There is a unique group homomorphism $\varphi \otimes \psi\colon M \otimes_R N \to M' \otimes_R N'$ with
$$(\varphi \otimes \psi)(m \otimes n) = \varphi(m) \otimes \psi(n)$$
for all $m \in M$ and $n \in N$.
2. If M and M' are (S,R)-bimodules and φ is also a homomorphism of left S-modules, then $\varphi \otimes \psi$ is a homomorphism of left S-modules. In particular, if R is commutative and all four modules carry their standard structures, then $\varphi \otimes \psi$ is R-linear.
3. $\mathrm{id}_M \otimes \mathrm{id}_N = \mathrm{id}_{M \otimes_R N}$, and if $\lambda\colon M' \to M''$ and $\mu\colon N' \to N''$ are further homomorphisms of right and left R-modules respectively, then
$$(\lambda \otimes \mu) \circ (\varphi \otimes \psi) = (\lambda \circ \varphi) \otimes (\mu \circ \psi)$$

***Proof*:**

1. The map $M \times N \to M' \otimes_R N'$ sending (m,n) to $\varphi(m) \otimes \psi(n)$ is R-balanced. Additivity in each variable follows from additivity of φ and ψ together with additivity of $\otimes$ in each argument. For the third axiom, φ is a homomorphism of right R-modules and ψ of left

R-modules, so

$$\varphi(mr)\otimes\psi(n) = \big(\varphi(m)r\big)\otimes\psi(n) = \varphi(m)\otimes r\psi(n) = \varphi(m)\otimes\psi(rn)$$

the middle equality being the third relation of (15.1) in $M'\otimes_R N'$. Theorem 15.1.5 now gives the homomorphism, and its uniqueness.

2. Both $x\mapsto(\varphi\otimes\psi)(sx)$ and $x\mapsto s(\varphi\otimes\psi)(x)$ are group homomorphisms $M\otimes_R N\to M'\otimes_R N'$, so by lemma 15.1.4(3) it suffices to compare them on a simple tensor, where

$$(\varphi\otimes\psi)\big(s(m\otimes n)\big) = (\varphi\otimes\psi)\big((sm)\otimes n\big) = \varphi(sm)\otimes\psi(n) = \big(s\varphi(m)\big)\otimes\psi(n) = s\big(\varphi(m)\otimes\psi(n)\big)$$

using S-linearity of φ in the third step and proposition 15.1.10 in the fourth. When R is commutative and the structures are standard, an R-module homomorphism is S-linear for $S = R$, so the statement applies with $S = R$.

3. All three claims are equalities of group homomorphisms out of $M\otimes_R N$, so lemma 15.1.4(3) reduces each to a check on simple tensors. There $(\mathrm{id}\otimes\mathrm{id})(m\otimes n) = m\otimes n$, and

$$(\lambda\otimes\mu)\big((\varphi\otimes\psi)(m\otimes n)\big) = (\lambda\otimes\mu)\big(\varphi(m)\otimes\psi(n)\big) = \lambda(\varphi(m))\otimes\mu(\psi(n))$$

which is the value of $(\lambda\circ\varphi)\otimes(\mu\circ\psi)$ on $m\otimes n$, completing the proof.

Parts (1) and (3) say precisely that fixing a left R-module N makes $-\otimes_R N$ a functor from right R-modules to abelian groups, and symmetrically for $M\otimes_R -$. The question of how this functor treats exact sequences is left open here and settled in section 17.5. The computation $\mathbb{Z}/2\mathbb{Z}\otimes_{\mathbb{Z}}\mathbb{Z}/3\mathbb{Z} = 0$ of example 15.1.14 is already a warning that it does not treat them well.

The next two results compute a tensor product one summand at a time.

Theorem 15.2.3: Tensor Products of Direct Sums

Let M, M' be right R-modules and let N, N' be left R-modules. There are unique group isomorphisms

$$(M\oplus M')\otimes_R N \cong (M\otimes_R N)\oplus(M'\otimes_R N)$$
$$M\otimes_R (N\oplus N') \cong (M\otimes_R N)\oplus(M\otimes_R N')$$

determined on simple tensors by $(m,m')\otimes n\mapsto(m\otimes n, m'\otimes n)$ and $m\otimes(n,n')\mapsto(m\otimes n, m\otimes n')$ respectively. If M and M' are (S,R)-bimodules, the first is an isomorphism of left S-modules; if R is commutative and all modules carry their standard structures, both are isomorphisms of R-modules.

***Proof*:**
Consider $\alpha\colon (M\oplus M')\times N\to(M\otimes_R N)\oplus(M'\otimes_R N)$ given by $\alpha\big((m,m'),n\big) = (m\otimes n, m'\otimes n)$. It is R-balanced, each axiom holding in both coordinates at once. For the third,

$$\alpha\big((m,m')r,n\big) = \big(mr\otimes n,\ m'r\otimes n\big) = \big(m\otimes rn,\ m'\otimes rn\big) = \alpha\big((m,m'),rn\big)$$

since the action on $M\oplus M'$ is componentwise. By theorem 15.1.5 there is a group homomorphism $\bar\alpha$ on $(M\oplus M')\otimes_R N$ with the stated values.

For the inverse, the maps $\beta_1 \colon M \times N \to (M \oplus M') \otimes_R N$ with $\beta_1(m,n) = (m,0) \otimes n$ and $\beta_2 \colon M' \times N \to (M \oplus M') \otimes_R N$ with $\beta_2(m',n) = (0,m') \otimes n$ are R-balanced, because $m \mapsto (m,0)$ and $m' \mapsto (0,m')$ are homomorphisms of right R-modules. So they induce group homomorphisms $\bar{\beta}_1$ and $\bar{\beta}_2$. Define

$$\beta \colon (M \otimes_R N) \oplus (M' \otimes_R N) \to (M \oplus M') \otimes_R N, \qquad \beta(x,y) = \bar{\beta}_1(x) + \bar{\beta}_2(y)$$

which is a group homomorphism.

On a simple tensor,

$$\beta\big(\bar{\alpha}((m,m') \otimes n)\big) = (m,0) \otimes n + (0,m') \otimes n = \big((m,0) + (0,m')\big) \otimes n = (m,m') \otimes n$$

so $\beta \circ \bar{\alpha} = \mathrm{id}$ by lemma 15.1.4(3). In the other direction, lemma 15.1.4(2) applied in each summand shows that $(M \otimes_R N) \oplus (M' \otimes_R N)$ is generated as a group by the elements $(x,0)$ and $(0,y)$ with x and y simple tensors, so it is enough to evaluate $\bar{\alpha} \circ \beta$ on those. On $(m \otimes n, 0)$,

$$\bar{\alpha}\big(\bar{\beta}_1(m \otimes n)\big) = \bar{\alpha}\big((m,0) \otimes n\big) = (m \otimes n,\, 0 \otimes n) = (m \otimes n,\, 0)$$

by lemma 15.1.4(1), and the computation on $(0, m' \otimes n)$ is the same. Hence $\bar{\alpha} \circ \beta = \mathrm{id}$ and $\bar{\alpha}$ is an isomorphism.

When M, M' are (S,R)-bimodules, so is $M \oplus M'$, and S-linearity of $\bar{\alpha}$ is again an equality of group homomorphisms checked on simple tensors, where both sides give $\big((sm) \otimes n, (sm') \otimes n\big)$. Uniqueness in all cases is lemma 15.1.4(3).

The second isomorphism is the mirror image of the first: interchange the two factors throughout, replacing each appeal to additivity in the first argument of $\otimes$ by additivity in the second, and proposition 15.1.10 by proposition 15.2.1. No new step enters, completing the proof.

Theorem 15.2.4: Arbitrary Direct Sums Commute with Tensor Products

Let $\{M_i\}_{i \in I}$ be a family of right R-modules and let N be a left R-module. Then there is a unique group isomorphism

$$\left(\bigoplus_{i \in I} M_i\right) \otimes_R N \cong \bigoplus_{i \in I} (M_i \otimes_R N)$$

sending $(m_i)_i \otimes n$ to $(m_i \otimes n)_i$. If each M_i is an (S,R)-bimodule it is an isomorphism of left S-modules, and if R is commutative it is an isomorphism of R-modules.

***Proof*:**

Write $M = \bigoplus_{i \in I} M_i$, whose elements are the families $(m_i)_i$ with $m_i = 0$ for all but finitely many i. The assignment $\alpha\big((m_i)_i, n\big) = (m_i \otimes n)_i$ lands in the direct sum rather than the product, since $m_i = 0$ forces $m_i \otimes n = 0$ by lemma 15.1.4(1), so all but finitely many entries vanish. It is R-balanced for the same componentwise reason as in theorem 15.2.3, and so induces $\bar{\alpha}$ on $M \otimes_R N$.

Let $\kappa_j \colon M_j \to M$ be the inclusion of the j-th summand, a homomorphism of right R-modules. Each $\beta_j \colon M_j \times N \to M \otimes_R N$ given by $\beta_j(m,n) = \kappa_j(m) \otimes n$ is therefore R-balanced, inducing

$\bar{\beta}_j$. Define

$$\beta\colon \bigoplus_{i\in I}(M_i \otimes_R N) \to M \otimes_R N, \qquad \beta\big((x_i)_i\big) = \sum_{i\in I} \bar{\beta}_i(x_i)$$

a finite sum because $(x_i)_i$ has finite support, and a group homomorphism because each $\bar{\beta}_i$ is. On a simple tensor, writing $(m_i)_i = \sum_i \kappa_i(m_i)$ as the finite sum it is,

$$\beta\big(\bar{\alpha}((m_i)_i \otimes n)\big) = \sum_i \kappa_i(m_i) \otimes n = \left(\sum_i \kappa_i(m_i)\right) \otimes n = (m_i)_i \otimes n$$

using additivity of $\otimes$ in its first argument, so $\beta \circ \bar{\alpha} = \mathrm{id}$. Conversely $\bigoplus_i (M_i \otimes_R N)$ is generated as a group by the elements $\kappa'_j(x)$ with x a simple tensor of $M_j \otimes_R N$, where κ'_j is the inclusion of the j-th summand, and

$$\bar{\alpha}\big(\beta(\kappa'_j(m \otimes n))\big) = \bar{\alpha}\big(\kappa_j(m) \otimes n\big) = \kappa'_j(m \otimes n)$$

since every entry of $\kappa_j(m)$ other than the j-th is zero and therefore contributes $0 \otimes n = 0$. Hence $\bar{\alpha} \circ \beta = \mathrm{id}$. The bimodule claims and uniqueness are as in theorem 15.2.3, completing the proof.

Theorem 15.2.4 decomposes a direct sum in the *left* argument, and theorem 15.2.3 handles two summands on either side. The remaining case, an arbitrary direct sum in the right argument, is what a free presentation of a module needs, so it is recorded separately.

Corollary 15.2.5: Arbitrary Direct Sums in the Right Argument

Let M be a right R-module and $\{N_i\}_{i\in I}$ a family of left R-modules. Then there is a unique group isomorphism

$$M \otimes_R \left(\bigoplus_{i\in I} N_i\right) \cong \bigoplus_{i\in I}(M \otimes_R N_i)$$

sending $m \otimes (n_i)_i$ to $(m \otimes n_i)_i$. If M is an (S, R)-bimodule it is an isomorphism of left S-modules.

***Proof*:**

Write $N = \bigoplus_{i\in I} N_i$. The assignment $\alpha\big(m, (n_i)_i\big) = (m \otimes n_i)_i$ lands in the direct sum rather than the product, since $n_i = 0$ for all but finitely many i and $m \otimes 0 = 0$ by lemma 15.1.4(1). It is additive in each variable componentwise, and R-balanced because

$$\alpha\big(mr, (n_i)_i\big) = (mr \otimes n_i)_i = (m \otimes rn_i)_i = \alpha\big(m, r \cdot (n_i)_i\big)$$

so it induces $\bar{\alpha}\colon M \otimes_R N \to \bigoplus_i (M \otimes_R N_i)$.

For the inverse, let $\kappa_j\colon N_j \to N$ be the inclusion of the j-th summand, a map of left R-modules. Each $\beta_j\colon M \times N_j \to M \otimes_R N$ given by $\beta_j(m, n) = m \otimes \kappa_j(n)$ is R-balanced, hence induces $\bar{\beta}_j$ on $M \otimes_R N_j$, and these assemble into a map β on the direct sum.

The composites are the identity on simple tensors, which suffices by lemma 15.1.4. Writing $(n_i)_i = \sum_{j\in F} \kappa_j(n_j)$ over the finite set F of nonzero entries,

$$\beta\big(\bar{\alpha}(m \otimes (n_i)_i)\big) = \sum_{j\in F} m \otimes \kappa_j(n_j) = m \otimes \sum_{j\in F} \kappa_j(n_j) = m \otimes (n_i)_i$$

and conversely $\bar{\alpha}\big(\beta(\kappa'_j(m \otimes n))\big) = \bar{\alpha}\big(m \otimes \kappa_j(n)\big) = \kappa'_j(m \otimes n)$, every entry of $\kappa_j(n)$ other than the j-th being zero and so contributing $m \otimes 0 = 0$. The S-linearity claim holds because the left S-action on both sides is $s \cdot (m \otimes n) = (sm) \otimes n$ by proposition 15.2.1, which $\bar{\alpha}$ respects, completing the proof.

Applying theorem 15.2.4 to a free module, where every summand is a copy of the ring, computes the tensor product of two free modules completely. This is the result that makes tensor products calculable in linear algebra: it says that a basis of M and a basis of N determine a basis of $M \otimes_R N$, indexed by pairs.

Corollary 15.2.6: Tensor Products of Free Modules

Let R be a commutative ring, let M be a free R-module with basis $\{m_i\}_{i \in I}$ and let N be a free R-module with basis $\{n_j\}_{j \in J}$. Then $M \otimes_R N$ is a free R-module with basis

$$\{m_i \otimes n_j\}_{(i,j) \in I \times J}$$

In particular $R^s \otimes_R R^t \cong R^{st}$, and if V, W are finite-dimensional vector spaces over a field F then

$$\dim_F(V \otimes_F W) = \dim_F(V) \cdot \dim_F(W)$$

***Proof*:**
Since $\{m_i\}$ is a basis, $M = \bigoplus_{i \in I} Rm_i$ with each $Rm_i \cong R$ as an R-module, the isomorphism carrying m_i to 1 (theorem 12.3.11). Applying theorem 15.2.4, and then example 15.1.13 to each summand after transporting it along $Rm_i \cong R$ by theorem 15.2.2, gives R-module isomorphisms

$$M \otimes_R N \cong \bigoplus_{i \in I} \big(Rm_i \otimes_R N\big) \cong \bigoplus_{i \in I} N$$

under which $m_i \otimes n$ corresponds to the family whose i-th entry is n and whose other entries are 0. Writing $N = \bigoplus_{j \in J} Rn_j \cong \bigoplus_{j \in J} R$ in the same way and substituting,

$$M \otimes_R N \cong \bigoplus_{i \in I} \bigoplus_{j \in J} R \cong \bigoplus_{(i,j) \in I \times J} R$$

and following $m_i \otimes n_j$ through the three isomorphisms shows that it corresponds to the element of $\bigoplus_{I \times J} R$ with 1 in position (i, j) and 0 elsewhere. Those elements form the standard basis of $\bigoplus_{I \times J} R$, and an isomorphism of R-modules carries a basis to a basis, so $\{m_i \otimes n_j\}$ is a basis of $M \otimes_R N$.

The two special cases follow by counting: $I \times J$ has st elements when $|I| = s$ and $|J| = t$, and the dimension of a vector space is the cardinality of any basis, as we sought to show.

This closes the identification promised in example 15.1.15: for finite-dimensional V, a basis of V^* and one of W^* produce a basis of $V^* \otimes_F W^*$, matching the basis of the space of bilinear forms on $V \times W$ under the correspondence of theorem 15.1.12.

Two structural isomorphisms remain. Both are needed before an expression such as $M_1 \otimes M_2 \otimes M_3$ can be written without brackets.

Proposition 15.2.7: Commutativity of the Tensor Product

Let R be a commutative ring and let M, N be R-modules with their standard structures. Then there is a unique R-module isomorphism

$$\tau\colon M \otimes_R N \to N \otimes_R M, \qquad \tau(m \otimes n) = n \otimes m$$

***Proof*:**
The map $M \times N \to N \otimes_R M$ sending (m, n) to $n \otimes m$ is R-bilinear: it is additive in each variable, and for $r \in R$,

$$n \otimes (rm) = (nr) \otimes m = r(n \otimes m)$$

using the third relation of (15.1) and the description of the action in theorem 15.1.12, with the same computation in the other variable. So theorem 15.1.12 gives a unique R-module homomorphism τ with $\tau(m \otimes n) = n \otimes m$. The same construction with the roles of M and N exchanged gives $\tau'\colon N \otimes_R M \to M \otimes_R N$ with $\tau'(n \otimes m) = m \otimes n$, and both composites fix every simple tensor, so both are the identity by lemma 15.1.4(3), as we sought to show.

Theorem 15.2.8: Associativity of the Tensor Product

Let M be a right R-module, let N be an (R, T)-bimodule and let L be a left T-module. Then there is a unique isomorphism of abelian groups

$$(M \otimes_R N) \otimes_T L \cong M \otimes_R (N \otimes_T L)$$

carrying $(m \otimes n) \otimes l$ to $m \otimes (n \otimes l)$. If M is an (S, R)-bimodule it is an isomorphism of left S-modules; if $R = T$ is commutative and all three modules carry their standard structures, it is an isomorphism of R-modules.

***Proof*:**
By proposition 15.2.1, $M \otimes_R N$ is a right T-module with $(m \otimes n)t = m \otimes (nt)$, and $N \otimes_T L$ is a left R-module with $r(n \otimes l) = (rn) \otimes l$. Both tensor products in the statement are therefore defined.

Step 1: a homomorphism for each l. Fix $l \in L$. The map $M \times N \to M \otimes_R (N \otimes_T L)$ sending (m, n) to $m \otimes (n \otimes l)$ is R-balanced. It is additive in m; it is additive in n because $n \mapsto n \otimes l$ is additive and $\otimes$ is additive in its second argument; and

$$(mr) \otimes (n \otimes l) = m \otimes r(n \otimes l) = m \otimes \big((rn) \otimes l\big)$$

which is the third axiom. By theorem 15.1.5 there is a unique group homomorphism $\theta_l\colon M \otimes_R N \to M \otimes_R (N \otimes_T L)$ with $\theta_l(m \otimes n) = m \otimes (n \otimes l)$.

Step 2: assembling over l. The map $(M \otimes_R N) \times L \to M \otimes_R (N \otimes_T L)$ sending (x, l) to $\theta_l(x)$ is T-balanced. It is additive in x because θ_l is a homomorphism. For additivity in l, both $\theta_{l+l'}$ and $\theta_l + \theta_{l'}$ are group homomorphisms out of $M \otimes_R N$, and on a simple tensor both give $m \otimes (n \otimes l) + m \otimes (n \otimes l')$, so they are equal by lemma 15.1.4(3). For the third axiom, $x \mapsto \theta_l(xt)$ and $x \mapsto \theta_{tl}(x)$ are group homomorphisms, and on a simple tensor

$$\theta_l\big((m \otimes n)t\big) = \theta_l(m \otimes nt) = m \otimes \big((nt) \otimes l\big) = m \otimes \big(n \otimes (tl)\big) = \theta_{tl}(m \otimes n)$$

the third equality being the third relation of (15.1) inside $N \otimes_T L$. So theorem 15.1.5 gives a group homomorphism Θ on $(M \otimes_R N) \otimes_T L$ with $\Theta\big((m \otimes n) \otimes l\big) = m \otimes (n \otimes l)$.

Step 3: the inverse. The same two steps run with the outer factors exchanged. Fixing $m \in M$, the map $N \times L \to (M \otimes_R N) \otimes_T L$ sending (n, l) to $(m \otimes n) \otimes l$ is T-balanced, giving $\eta_m \colon N \otimes_T L \to (M \otimes_R N) \otimes_T L$ with $\eta_m(n \otimes l) = (m \otimes n) \otimes l$; and $(m, y) \mapsto \eta_m(y)$ is then R-balanced by the same three checks. This yields a group homomorphism Ξ on $M \otimes_R (N \otimes_T L)$ with $\Xi\big(m \otimes (n \otimes l)\big) = (m \otimes n) \otimes l$.

Step 4: the composites. By lemma 15.1.4(2) every element of $(M \otimes_R N) \otimes_T L$ is a finite sum of terms $x \otimes l$ with $x \in M \otimes_R N$, and each such x is itself a finite sum of simple tensors, so by additivity of $\otimes$ in its first argument every element is a finite sum of terms $(m \otimes n) \otimes l$. Since $\Xi \circ \Theta$ is a group homomorphism fixing each such term, it is the identity. The same argument on the other side gives $\Theta \circ \Xi = \mathrm{id}$.

The S-linearity of Θ, when M is an (S, R)-bimodule, is once more an equality of group homomorphisms verified on the generating terms $(m \otimes n) \otimes l$, where both sides give $(sm) \otimes (n \otimes l)$. And uniqueness holds because a homomorphism is determined by its values on those terms, completing the proof.

15.2.9 Foreshadowing: Monoidal Structure on R-Mod For a commutative ring R, the three isomorphisms

$$(M \otimes_R N) \otimes_R L \cong M \otimes_R (N \otimes_R L), \qquad R \otimes_R M \cong M, \qquad M \otimes_R N \cong N \otimes_R M$$

of theorem 15.2.8, example 15.1.13 and proposition 15.2.7 are not three unrelated facts. They are the associator, the unit isomorphism and the braiding of a structure called a *symmetric monoidal category*, carried by R-Mod with $\otimes_R$ as its product and R as its unit. In that language the R-algebras of definition 12.1.13 are exactly the monoid objects of R-Mod, and the compatibility conditions the three isomorphisms satisfy with one another are the subject of a coherence theorem. The structure is developed in *Category Theory* [19]. Nothing in this chapter depends on it.

Associativity justifies the notation $M_1 \otimes_R \cdots \otimes_R M_n$: define it to mean the left-bracketed product $(\cdots (M_1 \otimes_R M_2) \otimes_R \cdots) \otimes_R M_n$, and write $m_1 \otimes \cdots \otimes m_n$ for the corresponding element. Repeated application of theorem 15.2.8 produces an isomorphism from any other bracketing onto this one matching the corresponding simple tensors, which is what makes the bracket-free notation harmless. With that in place the universal property extends from two factors to n.

Definition 15.2.10: Multilinear Maps

Let R be a commutative ring and let $M_1, \ldots, M_n$ and L be R-modules with their standard structures. A map $\varphi \colon M_1 \times \cdots \times M_n \to L$ is *R-multilinear*, or *n-linear*, if for each index i and each choice of fixed elements $m_k \in M_k$ for $k \neq i$, the map

$$M_i \to L, \qquad m \mapsto \varphi(m_1, \ldots, m_{i-1}, m, m_{i+1}, \ldots, m_n)$$

is an R-module homomorphism. For $n = 2$ and $n = 3$ one says *bilinear* and *trilinear* rather than 2-linear and 3-linear.

This is definition 13.3.15 with the target allowed to be any R-module rather than the base field, and with any number of arguments. For $n = 2$ it is definition 15.1.11.

Theorem 15.2.11: Universal Property for Multilinear Maps

Let R be a commutative ring and let $M_1, \dots, M_n$ and L be R-modules. For every R-multilinear map $\varphi\colon M_1 \times \cdots \times M_n \to L$ there is a unique R-module homomorphism

$$\psi\colon M_1 \otimes_R \cdots \otimes_R M_n \to L, \qquad \psi(m_1 \otimes \cdots \otimes m_n) = \varphi(m_1, \dots, m_n)$$

***Proof*:**

Induction on n. The case $n = 1$ is the identity and $n = 2$ is theorem 15.1.12, so suppose $n \geq 3$ and the statement holds for $n - 1$. Write $P = M_1 \otimes_R \cdots \otimes_R M_{n-1}$, so that by definition of the left-bracketed product the n-fold tensor product is $P \otimes_R M_n$.

First note that P is generated as an R-module by the simple tensors $m_1 \otimes \cdots \otimes m_{n-1}$: this holds for $n - 1 = 1$ trivially, and the inductive step is lemma 15.1.4(2) applied to $P' \otimes_R M_{n-1}$ together with additivity of $\otimes$ in its first argument.

Fix $m_n \in M_n$. The map $(m_1, \dots, m_{n-1}) \mapsto \varphi(m_1, \dots, m_n)$ is $(n-1)$-linear, since fixing all but one of its arguments fixes all but one argument of φ. By the inductive hypothesis there is a unique R-module homomorphism $\psi_{m_n}\colon P \to L$ with $\psi_{m_n}(m_1 \otimes \cdots \otimes m_{n-1}) = \varphi(m_1, \dots, m_n)$.

The map $P \times M_n \to L$ sending (x, m_n) to $\psi_{m_n}(x)$ is R-bilinear. Linearity in x holds because ψ_{m_n} is an R-module homomorphism. For linearity in m_n, the maps $\psi_{m_n + m_n'}$ and $\psi_{m_n} + \psi_{m_n'}$ are R-module homomorphisms out of P agreeing on every $m_1 \otimes \cdots \otimes m_{n-1}$, by linearity of φ in its last argument, and those generate P. So the two are equal. The same argument gives $\psi_{rm_n} = r\psi_{m_n}$.

Theorem 15.1.12 therefore gives a unique R-module homomorphism ψ on $P \otimes_R M_n$ with $\psi(x \otimes m_n) = \psi_{m_n}(x)$, and evaluating at $x = m_1 \otimes \cdots \otimes m_{n-1}$ gives the stated formula. Uniqueness follows because the simple tensors $m_1 \otimes \cdots \otimes m_n$ generate $M_1 \otimes_R \cdots \otimes_R M_n$, by the generation statement above and lemma 15.1.4(2), completing the proof.

One fact about $\otimes_R$ cannot be obtained from the universal property, because it is a statement about how an equation in $M \otimes_R N$ arises rather than about maps out of it. Lemma 15.1.4(2) says every element is a finite sum of simple tensors. The lemma below says that when such a sum vanishes, the vanishing already occurs inside a finitely generated piece of M. Its proof is the one place in this section that returns to the construction in definition 15.1.3.

Lemma 15.2.12: Vanishing Is Witnessed Finitely

Let R be a ring, M a right R-module and N a left R-module, and suppose

$$\sum_{i=1}^{k} m_i \otimes n_i = 0 \qquad \text{in } M \otimes_R N$$

Then there is a *finitely generated* submodule $M_0 \subseteq M$ containing $m_1, \dots, m_k$ such that already

$$\sum_{i=1}^{k} m_i \otimes n_i = 0 \qquad \text{in } M_0 \otimes_R N$$

The same holds with the roles of M and N exchanged.

***Proof*:**

By definition 15.1.3 the group $M \otimes_R N$ is $F^{\mathbb{Z}}(M \times N)/K$, so the hypothesis says that the element $\sum_i (m_i, n_i)$ of $F^{\mathbb{Z}}(M \times N)$ lies in K. Since K is generated by the three displayed forms, there are finitely many generators $g_1, \dots, g_t$ of K and integers $c_1, \dots, c_t$ with

$$\sum_{i=1}^{k} (m_i, n_i) = \sum_{j=1}^{t} c_j \, g_j$$

Each g_j mentions only finitely many elements of M: a generator of the first form mentions m, m' and $m + m'$, one of the second mentions a single m, and one of the third mentions mr and m. Let $S \subseteq M$ be the finite set consisting of $m_1, \dots, m_k$ together with every element of M mentioned by some g_j, and let M_0 be the submodule of M generated by S. It is finitely generated and contains each m_i.

Now form $F^{\mathbb{Z}}(M_0 \times N)$ and the subgroup K_0 generated by the three forms of definition 15.1.3 taken over M_0, N and R, so that $M_0 \otimes_R N = F^{\mathbb{Z}}(M_0 \times N)/K_0$. Every g_j lies in $F^{\mathbb{Z}}(M_0 \times N)$, since all of its M-coordinates belong to $S \subseteq M_0$; and g_j is a generator of K_0, because M_0 is a submodule and so is closed under the addition and the R-action that the three forms use. Hence the displayed identity holds in $F^{\mathbb{Z}}(M_0 \times N)$ and exhibits $\sum_i (m_i, n_i)$ as an element of K_0, which is to say $\sum_i m_i \otimes n_i = 0$ in $M_0 \otimes_R N$.

The statement with M and N exchanged is the same argument applied to the second coordinate.

The lemma does not say that $M_0 \otimes_R N \to M \otimes_R N$ is injective, and in general it is not. What it says is that a *relation* that holds downstairs already holds upstairs, which is what makes it possible to reduce a question about an arbitrary module to the finitely generated case. Theorem 17.5.7 is the use it was recorded for.

A tensor product of quotients of a commutative ring is again a quotient, and the ideal one quotients by is the sum. This is the computation behind most small examples.

Proposition 15.2.13: Tensor Product of Quotient Rings

Let R be a commutative ring and let I, J be ideals of R. Then there is an R-module isomorphism

$$R/I \otimes_R R/J \cong R/(I+J), \qquad \overline{a} \otimes \overline{b} \mapsto \overline{ab}$$

***Proof*:**

The map $R/I \times R/J \to R/(I+J)$ sending $(\overline{a}, \overline{b})$ to $\overline{ab}$ is well defined: if $a - a' \in I$ and $b - b' \in J$ then

$$ab - a'b' = (a-a')b + a'(b-b') \in I + J$$

It is R-bilinear, so theorem 15.1.12 induces an R-module homomorphism Φ with $\Phi(\overline{a} \otimes \overline{b}) = \overline{ab}$.

In the other direction set $\Psi(\overline{r}) = \overline{r} \otimes \overline{1}$. Throughout, a bar in the left-hand factor denotes a class in R/I and a bar in the right-hand factor a class in R/J. To see that Ψ is well defined, let $r - r' \in I + J$ and write $r - r' = a + b$ with $a \in I$ and $b \in J$, so that

$$\overline{r - r'} \otimes \overline{1} = \overline{a} \otimes \overline{1} + \overline{b} \otimes \overline{1}$$

The first term vanishes because $\overline{a} = \overline{0}$ already in R/I. For the second, moving the scalar b across by the third relation of (15.1),

$$\overline{b} \otimes \overline{1} = (b \cdot \overline{1}) \otimes \overline{1} = \overline{1} \otimes (b \cdot \overline{1}) = \overline{1} \otimes \overline{b} = 0$$

since $\overline{b} = \overline{0}$ in R/J. So Ψ is well defined, and it is R-linear.

The composite $\Phi \circ \Psi$ sends $\overline{r}$ to $\overline{r}$. For the other composite,

$$\Psi\big(\Phi(\overline{a} \otimes \overline{b})\big) = \overline{ab} \otimes \overline{1} = (\overline{a} \cdot b) \otimes \overline{1} = \overline{a} \otimes b\overline{1} = \overline{a} \otimes \overline{b}$$

so $\Psi \circ \Phi$ fixes every simple tensor and is the identity by lemma 15.1.4(3), as we sought to show.

Taking $R = \mathbb{Z}$, $I = (m)$ and $J = (n)$ recovers $\mathbb{Z}/m\mathbb{Z} \otimes_{\mathbb{Z}} \mathbb{Z}/n\mathbb{Z} \cong \mathbb{Z}/\gcd(m,n)\mathbb{Z}$, since $(m) + (n) = (\gcd(m,n))$ by definition 10.1.24. That is the second exercise of section 15.1, and both computations of example 15.1.14 are the cases $(m,n) = (2,3)$ and $(m,n) = (2,2)$.

When the two factors are R-algebras rather than bare modules, their multiplications combine into one on the tensor product. This is the construction that will produce the tensor algebra in section 16.3, and it is the source of the coproduct description that closes this section.

Theorem 15.2.14: Tensor Product of R-Algebras

Let R be a commutative ring and let A and B be R-algebras (definition 12.1.13). Then there is a unique R-bilinear multiplication on $A \otimes_R B$ satisfying

$$(a \otimes b)(a' \otimes b') = (aa') \otimes (bb')$$

and it makes $A \otimes_R B$ into an R-algebra with identity $1_A \otimes 1_B$. If A and B are both commutative, so is $A \otimes_R B$.

***Proof*:**
Step 1: the multiplication exists. The map $A \times B \times A \times B \to A \otimes_R B$ sending (a, b, a', b') to $(aa') \otimes (bb')$ is R-multilinear: in each of its four arguments the other three are fixed, and the resulting map is a composite of multiplication in A or in B, which is R-linear in each variable by definition 12.1.13, with $\otimes$, which is R-linear in each argument by theorem 15.1.12. By theorem 15.2.11 it induces an R-module homomorphism

$$\mu' \colon A \otimes_R B \otimes_R A \otimes_R B \to A \otimes_R B, \qquad \mu'(a \otimes b \otimes a' \otimes b') = (aa') \otimes (bb')$$

By theorem 15.2.8 there is an isomorphism $(A \otimes_R B) \otimes_R (A \otimes_R B) \cong A \otimes_R B \otimes_R A \otimes_R B$ matching $(a \otimes b) \otimes (a' \otimes b')$ with $a \otimes b \otimes a' \otimes b'$. Composing it with μ' gives an R-module homomorphism μ on $(A \otimes_R B) \otimes_R (A \otimes_R B)$ with $\mu\big((a \otimes b) \otimes (a' \otimes b')\big) = (aa') \otimes (bb')$. Setting $xy := \mu(x \otimes y)$ defines a map $(A \otimes_R B) \times (A \otimes_R B) \to A \otimes_R B$ which is R-bilinear, being the composite of the R-bilinear ι with the R-linear μ, and which satisfies the displayed formula on simple tensors. It is the unique such: two R-bilinear maps agreeing on pairs of simple tensors induce, by theorem 15.1.12, two homomorphisms on $(A \otimes_R B) \otimes_R (A \otimes_R B)$ agreeing on the simple tensors $(a \otimes b) \otimes (a' \otimes b')$, which generate it, so they coincide.

Step 2: the ring axioms. Distributivity is additivity of the multiplication in each variable, which is part of bilinearity. For associativity, both $(x, y, z) \mapsto (xy)z$ and $(x, y, z) \mapsto x(yz)$ are R-trilinear, being built from bilinear maps, so by theorem 15.2.11 each corresponds to a homomorphism on the triple tensor product, and the two agree if and only if they agree on triples of simple tensors. There

$$\big((a\otimes b)(a'\otimes b')\big)(a''\otimes b'') = \big((aa')a''\big)\otimes\big((bb')b''\big) = \big(a(a'a'')\big)\otimes\big(b(b'b'')\big) = (a\otimes b)\big((a'\otimes b')(a''\otimes b'')\big)$$

by associativity in A and in B. For the identity, $x \mapsto (1_A \otimes 1_B)x$ and the identity map are both additive and agree on simple tensors, so they are equal by lemma 15.1.4(3), and likewise on the other side.

Step 3: the R-algebra structure. The R-module structure is the one $A \otimes_R B$ already carries, and the compatibility $r(xy) = (rx)y = x(ry)$ required by definition 12.1.13 is R-bilinearity of the multiplication. Finally, if A and B are commutative then $(x, y) \mapsto xy$ and $(x, y) \mapsto yx$ are R-bilinear and agree on pairs of simple tensors, since $(aa') \otimes (bb') = (a'a) \otimes (b'b)$, so they are equal by the uniqueness argument of Step 1, completing the proof.

Example 15.2.15: Tensoring Two Copies of $\mathbb{C}$ over $\mathbb{R}$
The base ring matters, and comparing $\mathbb{C} \otimes_{\mathbb{C}} \mathbb{C}$ with $\mathbb{C} \otimes_{\mathbb{R}} \mathbb{C}$ shows how much. The first is $\mathbb{C}$ itself by example 15.1.13. The second has $\mathbb{R}$-dimension 4 by corollary 15.2.6, since $\mathbb{C}$ is free of rank 2 over $\mathbb{R}$, and it is not even a domain:

$$\mathbb{C} \otimes_{\mathbb{R}} \mathbb{C} \cong \mathbb{C} \times \mathbb{C}$$

as $\mathbb{R}$-algebras. To see this, define $\Phi \colon \mathbb{C} \otimes_{\mathbb{R}} \mathbb{C} \to \mathbb{C} \times \mathbb{C}$ on simple tensors by

$$\Phi(z \otimes w) = (zw,\ z\overline{w})$$

This is well defined because $(z, w) \mapsto (zw, z\overline{w})$ is $\mathbb{R}$-bilinear, complex conjugation being $\mathbb{R}$-linear, so theorem 15.1.12 applies. It is a ring homomorphism: on simple tensors

$$\Phi\big((z\otimes w)(z'\otimes w')\big) = \Phi(zz'\otimes ww') = \big(zz'ww',\ zz'\overline{ww'}\big) = (zw\cdot z'w',\ z\overline{w}\cdot z'\overline{w'}) = \Phi(z\otimes w)\Phi(z'\otimes w')$$

and both $(x,y) \mapsto \Phi(xy)$ and $(x,y) \mapsto \Phi(x)\Phi(y)$ are $\mathbb{R}$-bilinear, so agreeing on simple tensors makes them equal. Also $\Phi(1 \otimes 1) = (1,1)$.

For surjectivity, compute Φ on three elements:

$$\Phi(1 \otimes 1) = (1,1), \qquad \Phi(i \otimes 1) = (i,i), \qquad \Phi(i \otimes i) = (i \cdot i,\ i\bar{i}) = (-1,1)$$

The image of Φ is both an $\mathbb{R}$-subspace and a subring. It contains $(1,1) - (-1,1) = (2,0)$ and $(1,1) + (-1,1) = (0,2)$, hence $(1,0)$ and $(0,1)$. And being closed under multiplication it then contains $(1,0)(i,i) = (i,0)$ and $(0,1)(i,i) = (0,i)$. Those four elements form an $\mathbb{R}$-basis of $\mathbb{C} \times \mathbb{C}$, so Φ is surjective. Both sides have $\mathbb{R}$-dimension 4, and a surjective linear map between vector spaces of equal finite dimension is an isomorphism.

So a tensor product of two fields over a common subfield need not be a field, and need not even be an integral domain: $\mathbb{C} \times \mathbb{C}$ has the zero divisors $(1,0)$ and $(0,1)$.

The last result of this section reads the tensor product of algebras backwards, as the answer to a universal problem rather than as a construction. Recall that in R-Mod the direct sum $M \oplus N$ is simultaneously the product and the coproduct of M and N. This is a feature of *finite* families only, since for an infinite index set the product $\prod_i M_i$ and the coproduct $\bigoplus_i M_i$ differ, the latter consisting of the finitely supported families. In commutative R-algebras the two come apart even for two factors. The product is the direct product $A \times B$ with componentwise operations, and the coproduct is the tensor product.

Lemma 15.2.16: Generation of $A \otimes_R B$ as an Algebra

Let R be a commutative ring and A, B be R-algebras. Then $A \otimes_R B$ is generated as an R-algebra by the set $\{a \otimes 1 \mid a \in A\} \cup \{1 \otimes b \mid b \in B\}$.


***Proof*:**
By theorem 15.2.14, $(a \otimes 1)(1 \otimes b) = (a \cdot 1) \otimes (1 \cdot b) = a \otimes b$, so every simple tensor is a product of two elements of the stated set. By lemma 15.1.4(2) every element of $A \otimes_R B$ is a finite sum of simple tensors, completing the proof.

Theorem 15.2.17: Universal Property of the Coproduct in R-Alg

Let R be a commutative ring and let A and B be commutative R-algebras, with structure maps $i_A\colon R \to A$ and $i_B\colon R \to B$. Then the maps

$$\iota_A\colon A \to A \otimes_R B, \quad a \mapsto a \otimes 1 \qquad \text{and} \qquad \iota_B\colon B \to A \otimes_R B, \quad b \mapsto 1 \otimes b$$

are R-algebra homomorphisms, and $(A \otimes_R B, \iota_A, \iota_B)$ is the coproduct of A and B in the category of commutative R-algebras: for every commutative R-algebra Z and every pair of R-algebra homomorphisms $f\colon A \to Z$ and $g\colon B \to Z$ there is a unique R-algebra homomorphism $h\colon A \otimes_R B \to Z$ with $h \circ \iota_A = f$ and $h \circ \iota_B = g$:



***Proof*:**
That ι_A is an R-algebra homomorphism is immediate from theorem 15.2.14: it is additive and R-linear because $\otimes$ is R-linear in its first argument, multiplicative because $(a\otimes 1)(a'\otimes 1) = (aa')\otimes 1$, and unital because $\iota_A(1_A) = 1_A \otimes 1_B$. The same holds for ι_B.

Existence. Define $\Phi\colon A \times B \to Z$ by $\Phi(a,b) = f(a)g(b)$. It is R-bilinear: it is additive in each variable because f and g are additive and multiplication in Z distributes, and for $r \in R$,

$$\Phi(ra,b) = f(ra)g(b) = \big(rf(a)\big)g(b) = r\big(f(a)g(b)\big) \qquad \Phi(a,rb) = f(a)\big(rg(b)\big) = r\big(f(a)g(b)\big)$$

using R-linearity of f and of g and the compatibility $r(xy) = (rx)y = x(ry)$ of definition 12.1.13 in Z. By theorem 15.1.12 there is a unique R-module homomorphism $h\colon A \otimes_R B \to Z$ with $h(a \otimes b) = f(a)g(b)$.

The map h is multiplicative. Both $(x,y) \mapsto h(xy)$ and $(x,y) \mapsto h(x)h(y)$ are R-bilinear, and on a pair of simple tensors

$$\begin{aligned} h\big((a \otimes b)(a' \otimes b')\big) &= h(aa' \otimes bb') = f(aa')g(bb') \\ &= f(a)f(a')g(b)g(b') = f(a)g(b)f(a')g(b') \\ &= h(a \otimes b)\, h(a' \otimes b') \end{aligned}$$

the fourth equality using that Z is commutative. Two R-bilinear maps agreeing on pairs of simple tensors are equal, by the argument in Step 1 of theorem 15.2.14, so h is multiplicative. It is unital, since $h(1_A \otimes 1_B) = f(1)g(1) = 1$, and therefore an R-algebra homomorphism. Finally $h(\iota_A(a)) = h(a \otimes 1) = f(a)g(1) = f(a)$ and likewise $h \circ \iota_B = g$, so the diagram commutes.

Uniqueness. Suppose h' is an R-algebra homomorphism with $h' \circ \iota_A = f$ and $h' \circ \iota_B = g$. Then h and h' agree on every $a \otimes 1$ and every $1 \otimes b$. By lemma 15.2.16 those elements generate $A \otimes_R B$ as an R-algebra, and two R-algebra homomorphisms agreeing on a generating set are equal, since the set on which they agree is a subalgebra. Hence $h' = h$, completing the proof.

Every commutative ring is an algebra over $\mathbb{Z}$ in exactly one way, which turns the theorem into a statement about rings with no base ring chosen in advance.

Corollary 15.2.18: Universal Property of the Coproduct in CRing

Let A and B be commutative rings. Then $A \otimes_{\mathbb{Z}} B$, with $\iota_A(a) = a \otimes 1$ and $\iota_B(b) = 1 \otimes b$, is the coproduct of A and B in the category **CRing** of commutative rings.

***Proof*:**
By proposition 9.1.29 there is exactly one ring homomorphism $\mathbb{Z} \to A$ for every ring A, so every commutative ring carries exactly one $\mathbb{Z}$-algebra structure, and its image lies in the centre because A is commutative. Moreover every ring homomorphism $\varphi\colon A \to B$ of commutative rings is automatically a $\mathbb{Z}$-algebra homomorphism: the two ring homomorphisms $\varphi \circ i_A$ and i_B from $\mathbb{Z}$ to B coincide by that same uniqueness. Hence the category of commutative $\mathbb{Z}$-algebras and **CRing** have the same objects and the same morphisms, and theorem 15.2.17 applied with $R = \mathbb{Z}$ gives the claim, completing the proof.

The product $A \times B$ is formed with no reference to a base ring, while the coproduct is formed over one, and in **CRing** the base is forced to be the initial object $\mathbb{Z}$. Over a general base R, the object $A \otimes_R B$ solves the coproduct problem for R-algebras, which is the same as a pushout of $A \leftarrow R \to B$ in commutative rings. Reversing every arrow turns a pushout of rings into a pullback of spaces, and this is the computation that makes $\otimes_R$ the algebraic form of the fibre product of affine schemes in *EYNTKA Algebraic Geometry* [13].

Exercise 15.2.1

1. Show that $\varphi \otimes \mathrm{id}$ need not be injective when φ is. (Take $\varphi\colon \mathbb{Z} \to \mathbb{Z}$ to be multiplication by 2 and tensor with $\mathbb{Z}/2\mathbb{Z}$ over $\mathbb{Z}$.) Conclude that the functor of theorem 15.2.2 does not preserve injections.

2. Let R be commutative, let M be an R-module and let I be an ideal of R. Show that $M \otimes_R R/I \cong M/IM$, and recover proposition 15.2.13 as the case $M = R/J$.

3. Show that every element of $\mathbb{Q} \otimes_{\mathbb{Z}} \mathbb{Q}$ is a simple tensor, and deduce that $\mathbb{Q} \otimes_{\mathbb{Z}} \mathbb{Q} \cong \mathbb{Q}$. (Note that example 15.1.13 does not apply: the left factor is $\mathbb{Q}$, not the base ring $\mathbb{Z}$.)

4. Let R be commutative and A an R-algebra. Show that the isomorphism $A \otimes_R R \cong A$ of example 15.1.13 is an isomorphism of R-algebras.

5. Using the isomorphism of example 15.2.15, find the two nontrivial idempotents of $\mathbb{C} \otimes_{\mathbb{R}} \mathbb{C}$ explicitly as combinations of simple tensors, and verify directly that each squares to itself.

6. Let R be commutative and let M, N be finitely generated R-modules, generated by s and t elements respectively. Show that $M \otimes_R N$ is generated by st elements. Show also that the bound is attained but not always sharp, by computing a case where $M \otimes_R N$ needs fewer.

7. Let F be a field and let V, W be finite-dimensional F-vector spaces. Show that

$$V^* \otimes_F W \to \mathrm{Hom}_F(V, W), \qquad f \otimes w \mapsto \big(v \mapsto f(v)w\big)$$

is an isomorphism of F-vector spaces, and identify where finite-dimensionality is used.

8. Combine theorem 15.2.8 and proposition 15.2.7 into an isomorphism $(A \otimes_R B) \otimes_R (A \otimes_R B) \cong (A \otimes_R A) \otimes_R (B \otimes_R B)$ carrying $(a \otimes b) \otimes (a' \otimes b')$ to $(a \otimes a') \otimes (b \otimes b')$. Use it, together with the maps $A \otimes_R A \to A$ and $B \otimes_R B \to B$ induced by multiplication, to give a second construction of the multiplication of theorem 15.2.14.

15.3 Extension of Scalars

The previous two sections held the ring fixed and varied the modules. This one does the opposite. Given a ring homomorphism $f\colon R \to S$, there are two ways to move a module between the two rings, and they are not symmetric: passing from S to R needs nothing, while passing from R to S requires a construction. That construction is the tensor product, applied to the bimodule of example 15.1.9(2), and everything in this section is a consequence of theorem 15.1.5 rather than a new construction.

The cheap direction first.

Definition 15.3.1: Restriction of Scalars

Let $f\colon R \to S$ be a ring homomorphism and let L be a left S-module. The *restriction of scalars* of L along f is the left R-module L_R with the same underlying abelian group and action

$$r \cdot l := f(r)\, l$$

An S-module homomorphism is in particular an R-module homomorphism $L_R \to L'_R$, so restriction of scalars sends S-modules to R-modules and S-linear maps to R-linear maps.

The module axioms hold because f is a ring homomorphism, exactly as in the construction of an R-algebra from a ring map (section 12.1.2). Nothing is created and nothing is destroyed, only forgotten. The other direction cannot work this way. An R-module N carries no S-action to forget, and there is in general no way to define one on the same underlying set: if $R = \mathbb{Z}$, $S = \mathbb{Q}$ and $N = \mathbb{Z}/2\mathbb{Z}$, then any $\mathbb{Q}$-action on N would make multiplication by 2 invertible on a group killed by 2. A new module has to be built, and the tensor product builds it.

Definition 15.3.2: Extension of Scalars

Let $f\colon R \to S$ be a ring homomorphism and let N be a left R-module. Regard S as an (S, R)-bimodule as in example 15.1.9(2), with left action given by multiplication in S and right action $s \cdot r := sf(r)$. The *extension of scalars* of N along f is the left S-module

$$S \otimes_R N$$

whose S-action, given by proposition 15.1.10, is determined on simple tensors by $s' \cdot (s \otimes n) = (s's) \otimes n$.

No verification is owed here: the module structure was proved once in proposition 15.1.10 and the only input is the bimodule structure on S, which is example 15.1.9(2). The relation that does the work is the third one in (15.1), which now reads

$$sf(r) \otimes n = s \otimes rn$$

so a scalar of R may be moved out of the module and into S, where it becomes invertible whenever $f(r)$ is.

Example 15.3.3: Extension of Scalars of a Free Module
Let $f\colon R \to S$ be a ring homomorphism. Then

$$S \otimes_R R^n \cong S^n$$

as left S-modules, and more generally $S \otimes_R R^{(I)} \cong S^{(I)}$ for a free module on any index set I. Indeed $R^{(I)} = \bigoplus_{i\in I} R$, so theorem 15.2.4 applied on the right-hand factor gives

$$S \otimes_R \bigoplus_{i\in I} R \cong \bigoplus_{i\in I} (S \otimes_R R) \cong \bigoplus_{i\in I} S$$

the second isomorphism being example 15.1.13 in each summand. Following a basis element e_i through, $1 \otimes e_i$ corresponds to the i-th standard generator of $S^{(I)}$. So extension of scalars carries a free R-module of rank n to a free S-module of the same rank: a basis survives, and only the ring it is a basis over changes.

Free modules therefore lose nothing. In general something is lost, and the map that measures the loss is the following.

The assignment $\iota\colon N \to S \otimes_R N$ with $\iota(n) = 1 \otimes n$ is additive, and it is R-linear when $S \otimes_R N$ is regarded as an R-module by restriction:


$$\iota(rn) = 1 \otimes rn = 1 \cdot f(r) \otimes n = f(r)\big(1 \otimes n\big) = r \cdot \iota(n)$$

using the third relation and then the definition of the S-action. It need not be injective. For $R = \mathbb{Z}$, $S = \mathbb{Q}$ and N any finite abelian group, $\mathbb{Q} \otimes_{\mathbb{Z}} N = 0$ by the third exercise of section 15.1, so ι is the zero map on a nonzero module.

The next theorem says that although N may not sit inside $S \otimes_R N$, every R-linear map from N into an S-module factors through it, uniquely and S-linearly. It is the defining property of extension of scalars and the reason the construction is the right one.

Theorem 15.3.4: Universal Property of Extension of Scalars

Let $f\colon R \to S$ be a ring homomorphism, let N be a left R-module and let $\iota\colon N \to S \otimes_R N$ be the R-module homomorphism $\iota(n) = 1 \otimes n$. Then for every left S-module L and every R-module homomorphism $\varphi\colon N \to L_R$ there is a unique S-module homomorphism $\psi\colon S \otimes_R N \to L$ with $\varphi = \psi \circ \iota$, that is, making



commute.

***Proof*:**
Existence. The map $S \times N \to L$ sending (s, n) to $s\varphi(n)$ is R-balanced. Additivity in s holds because the S-action on L distributes, and additivity in n because φ is additive. For the third axiom, the right R-action on S is $s \cdot r = sf(r)$ and the R-action on L_R is $r \cdot l = f(r)l$, so

$$(s \cdot r)\varphi(n) = \big(sf(r)\big)\varphi(n) = s\big(f(r)\varphi(n)\big) = s\big(r \cdot \varphi(n)\big) = s\,\varphi(rn)$$

the last equality because φ is R-linear. By theorem 15.1.5 there is a unique group homomorphism $\psi\colon S \otimes_R N \to L$ with $\psi(s \otimes n) = s\varphi(n)$.

It is S-linear. Fix $s' \in S$. The maps $x \mapsto \psi(s'x)$ and $x \mapsto s'\psi(x)$ are group homomorphisms, and on a simple tensor

$$\psi\big(s'(s \otimes n)\big) = \psi\big((s's) \otimes n\big) = (s's)\varphi(n) = s'\big(s\varphi(n)\big) = s'\psi(s \otimes n)$$

so they agree by lemma 15.1.4(3). Finally $\psi(\iota(n)) = \psi(1 \otimes n) = 1 \cdot \varphi(n) = \varphi(n)$, so $\varphi = \psi \circ \iota$.

Uniqueness. As an S-module, $S \otimes_R N$ is generated by the image of ι, since $s \otimes n = s(1 \otimes n) = s\,\iota(n)$ and every element is a finite sum of simple tensors by lemma 15.1.4(2). An S-module homomorphism is determined by its values on a generating set, and any ψ' with $\varphi = \psi' \circ \iota$ agrees with ψ on $\iota(N)$, so $\psi' = \psi$, completing the proof.

Restated without diagrams, the theorem says that R-linear maps out of N into an S-module are the same thing as S-linear maps out of $S \otimes_R N$. That is an adjunction, and it is worth naming as one, because it is the form in which the construction is used downstream.

Corollary 15.3.5: Extension of Scalars Is Left Adjoint to Restriction

Let $f\colon R \to S$ be a ring homomorphism. For every left R-module N and every left S-module L the map

$$\operatorname{Hom}_S\big(S \otimes_R N,\, L\big) \to \operatorname{Hom}_R\big(N,\, L_R\big), \qquad \psi \mapsto \psi \circ \iota$$

is an isomorphism of abelian groups. A pair of functors related this way is called an *adjunction*, and this one is expressed by saying that $S \otimes_R -$, from left R-modules to left S-modules, is *left adjoint* to restriction of scalars. The general theory is section 64.1. Only the displayed bijection is used below.

***Proof*:**
The map is additive, since $(\psi + \psi') \circ \iota = \psi \circ \iota + \psi' \circ \iota$, and it lands in $\operatorname{Hom}_R(N, L_R)$ because ι is R-linear and ψ is S-linear, hence R-linear after restriction. It is surjective by the existence half of theorem 15.3.4 and injective by the uniqueness half: if $\psi \circ \iota = \psi' \circ \iota$ then both are maps induced by the same φ, so they coincide, as we sought to show.

Two computations show what the construction does. The first is the standard way a real vector space is turned into a complex one.

Example 15.3.6: Complexification
Take $R = \mathbb{R}$, $S = \mathbb{C}$ and f the inclusion. For a real vector space V the *complexification* is the complex vector space

$$V_{\mathbb{C}} := \mathbb{C} \otimes_{\mathbb{R}} V$$

Every element of $V_{\mathbb{C}}$ has the form $1 \otimes v + i \otimes w$ for unique $v, w \in V$. A simple tensor already does, since for $z = x+iy$ with $x, y \in \mathbb{R}$ the third relation of (15.1) gives $z \otimes v = x \otimes v + iy \otimes v = 1 \otimes xv + i \otimes yv$. And a sum of two such collapses to one by additivity of $\otimes$ in its second argument. If V has $\mathbb{R}$-basis $e_1, \ldots, e_n$ then $V_{\mathbb{C}}$ has $\mathbb{C}$-basis $1 \otimes e_1, \ldots, 1 \otimes e_n$ by example 15.3.3, so

$$\dim_{\mathbb{C}}(V_{\mathbb{C}}) = \dim_{\mathbb{R}}(V)$$

A linear map $\varphi \colon V \to W$ extends to $\mathrm{id}_{\mathbb{C}} \otimes \varphi \colon V_{\mathbb{C}} \to W_{\mathbb{C}}$ by theorem 15.2.2, and on the bases above it has the same matrix as φ. The entries are simply now read as complex numbers. This is what permits the standard move of computing eigenvalues of a real matrix over $\mathbb{C}$.

One warning. Complexifying a space that is already complex does not return it. Reading $\mathbb{C}$ itself as a real vector space and complexifying gives $\mathbb{C} \otimes_{\mathbb{R}} \mathbb{C} \cong \mathbb{C} \times \mathbb{C}$ by example 15.2.15, which has $\mathbb{C}$-dimension 2, not 1. The construction depends on the ring the tensor product is taken over, not only on the two spaces.

Example 15.3.7: Induced Representations

Let K be a field, let G be a finite group and let $H \leq G$ be a subgroup. The group rings $K[H]$ and $K[G]$ of definition 9.2.18 are related by the inclusion $K[H] \hookrightarrow K[G]$, so extension of scalars along it carries $K[H]$-modules to $K[G]$-modules. Since a $K[G]$-module is the same data as a representation of G over K, this manufactures a representation of G from one of H.

The dimension is forced. Choosing coset representatives $g_1, \ldots, g_k$ for G/H, where $k = [G : H]$, gives $K[G] = \bigoplus_{i=1}^{k} g_i K[H]$ as a right $K[H]$-module, so $K[G]$ is free of rank k over $K[H]$. If V is a representation of H of dimension d, then theorem 15.2.4 gives

$$K[G] \otimes_{K[H]} V \cong \bigoplus_{i=1}^{k} \left(g_i K[H] \otimes_{K[H]} V \right) \cong V^{\oplus k}$$

as K-vector spaces, so the induced representation has dimension kd. Concretely, $\mathbb{Z}/3\mathbb{Z}$ sits inside S_3 with index 2, so a 10-dimensional representation of $\mathbb{Z}/3\mathbb{Z}$ induces a 20-dimensional representation of S_3.

The construction is the *induced representation*, and its theory, including Frobenius reciprocity, which is corollary 15.3.5 read in this setting, is developed in *Core Representation Theory* [22].

Returning to the map ι, the universal property settles exactly when it is injective, and the answer identifies what part of N can survive into any S-module at all.

Corollary 15.3.8: When the Unit Is Injective

Let $f \colon R \to S$ be a ring homomorphism, let N be a left R-module and let $\iota \colon N \to S \otimes_R N$ be as above. Then every R-module homomorphism from N into (the restriction of) a left S-module vanishes on $\ker \iota$. Consequently N embeds as an R-submodule of some left S-module if and only if ι is injective, in which case $N \cong \iota(N) \subseteq S \otimes_R N$.

***Proof*:**
Let L be a left S-module and $\theta\colon N \to L_R$ an R-module homomorphism. By theorem 15.3.4 there is an S-module homomorphism ψ with $\theta = \psi \circ \iota$, so θ kills $\ker \iota$.

If ι is injective it is itself such an embedding, with image $\iota(N)$. If conversely some $\theta\colon N \to L_R$ is injective, then $\ker \iota \subseteq \ker \theta = 0$ by the previous paragraph, so ι is injective, completing the proof.

For a finite abelian group N and $\mathbb{Z} \hookrightarrow \mathbb{Q}$ this recovers a fact already known: ι is the zero map, so no nonzero element of N survives into any $\mathbb{Q}$-vector space, which is another way of saying that a torsion element cannot live in a space where every nonzero integer acts invertibly.

The adjunction of corollary 15.3.5 is one instance of a general relationship between $\otimes$ and Hom. Stating it here rather than alongside its applications keeps every property of the tensor product in one place. It is used in section 17.5 to compare tensoring with the Hom functors, and in *Homological Algebra* [29] to produce derived functors.

Theorem 15.3.9: Hom-Tensor Adjunction

Let R and S be rings, let A be a right R-module, let B be an (R,S)-bimodule and let C be a right S-module. Give $\mathrm{Hom}_S(B,C)$ the right R-action $(g \cdot r)(b) := g(rb)$. Then there is an isomorphism of abelian groups

$$\mathrm{Hom}_S\big(A \otimes_R B,\, C\big) \cong \mathrm{Hom}_R\big(A,\, \mathrm{Hom}_S(B,C)\big)$$

sending φ to the map $a \mapsto \big(b \mapsto \varphi(a \otimes b)\big)$.

***Proof*:**
First, the objects are what the statement claims. Every right R-module is a $(\mathbb{Z},R)$-bimodule, so proposition 15.2.1, applied with $\mathbb{Z}$ in the role of the left-hand ring and S in the role of the right-hand one, makes $A \otimes_R B$ a right S-module with $(a \otimes b)s = a \otimes (bs)$. The stated action on $\mathrm{Hom}_S(B,C)$ is a right action, since $\big((g \cdot r) \cdot r'\big)(b) = (g \cdot r)(r'b) = g(rr'b) = \big(g \cdot (rr')\big)(b)$.

The forward map. Given $\varphi \in \mathrm{Hom}_S(A \otimes_R B, C)$, define $\Lambda(\varphi)(a)(b) = \varphi(a \otimes b)$. For fixed a the map $\Lambda(\varphi)(a)$ is S-linear: it is additive because $\otimes$ is additive in its second argument, and

$$\Lambda(\varphi)(a)(bs) = \varphi\big(a \otimes bs\big) = \varphi\big((a \otimes b)s\big) = \varphi(a \otimes b)\, s = \Lambda(\varphi)(a)(b)\, s$$

using S-linearity of φ. The map $\Lambda(\varphi)$ is R-linear: it is additive because $\otimes$ is additive in its first argument, and

$$\Lambda(\varphi)(ar)(b) = \varphi(ar \otimes b) = \varphi(a \otimes rb) = \Lambda(\varphi)(a)(rb) = \big(\Lambda(\varphi)(a) \cdot r\big)(b)$$

the second equality being the third relation of (15.1). Finally Λ is additive in φ, directly from the definition.

The backward map. Given $\Psi \in \mathrm{Hom}_R(A, \mathrm{Hom}_S(B,C))$, the map $A \times B \to C$ sending (a,b) to $\Psi(a)(b)$ is R-balanced: it is additive in a because Ψ is additive, additive in b because each $\Psi(a)$ is, and

$$\Psi(ar)(b) = \big(\Psi(a) \cdot r\big)(b) = \Psi(a)(rb)$$

which is the third axiom. By theorem 15.1.5 there is a unique group homomorphism $\Gamma(\Psi)\colon A \otimes_R B \to C$ with $\Gamma(\Psi)(a \otimes b) = \Psi(a)(b)$, and it is S-linear because $x \mapsto \Gamma(\Psi)(xs)$ and $x \mapsto \Gamma(\Psi)(x)s$

are group homomorphisms agreeing on simple tensors, where both give $\Psi(a)(bs)$. Again Γ is additive.

The two are mutually inverse. For $\Psi \in \mathrm{Hom}_R(A, \mathrm{Hom}_S(B, C))$ and all $a \in A$, $b \in B$,

$$\Lambda\big(\Gamma(\Psi)\big)(a)(b) = \Gamma(\Psi)(a \otimes b) = \Psi(a)(b)$$

so $\Lambda(\Gamma(\Psi))(a) = \Psi(a)$ for every a, giving $\Lambda \circ \Gamma = \mathrm{id}$. In the other direction, $\Gamma(\Lambda(\varphi))$ and φ are group homomorphisms out of $A \otimes_R B$ agreeing on every simple tensor, since $\Gamma(\Lambda(\varphi))(a \otimes b) = \Lambda(\varphi)(a)(b) = \varphi(a \otimes b)$, so they are equal by lemma 15.1.4(3). Hence Λ is an isomorphism of abelian groups, completing the proof.

Taking $B = S$, viewed as an (R, S)-bimodule along $f\colon R \to S$, and using $\mathrm{Hom}_S(S, C) \cong C_R$ recovers corollary 15.3.5 in its right-handed form: extension of scalars is the case of the Hom-tensor adjunction in which the bimodule is the ring itself.

Exercise 15.3.1

1. Let $f\colon R \to S$ be a ring homomorphism and let $I \subseteq R$ be an ideal. Show that $S \otimes_R R/I \cong S/f(I)S$ as S-modules, where $f(I)S$ is the ideal of S generated by $f(I)$.
2. Let A be a finitely generated abelian group, so that $A \cong \mathbb{Z}^r \oplus T$ with T finite by chapter 14. Show that $\mathbb{Q} \otimes_{\mathbb{Z}} A \cong \mathbb{Q}^r$ as $\mathbb{Q}$-vector spaces, so that extension of scalars along $\mathbb{Z} \hookrightarrow \mathbb{Q}$ destroys exactly the torsion and $r = \dim_{\mathbb{Q}}(\mathbb{Q} \otimes_{\mathbb{Z}} A)$.
3. Let $R \subseteq S$ be an inclusion of rings and suppose S is free as a right R-module with a basis containing 1. Show that $\iota\colon N \to S \otimes_R N$ is injective for every left R-module N. Where does the argument fail for $\mathbb{Z} \subseteq \mathbb{Q}$?
4. Viewing S as an (R, S)-bimodule along $f\colon R \to S$, show that $\mathrm{Hom}_R(S, L)$ is a left S-module for every left R-module L, and that

   $$\mathrm{Hom}_R\big(M_R,\, L\big) \cong \mathrm{Hom}_S\big(M,\, \mathrm{Hom}_R(S, L)\big)$$

   for every left S-module M. (So restriction of scalars has a right adjoint as well as a left one. This is *coextension of scalars*.)
5. Let V be a real vector space. Show that $V_{\mathbb{C}} \cong V \oplus V$ as real vector spaces, and describe the complex structure that this decomposition carries in terms of the two summands.
6. Let $f\colon R \to S$ and $g\colon S \to T$ be ring homomorphisms. Show that extension of scalars along $g \circ f$ agrees with extension along f followed by extension along g, that is $T \otimes_S (S \otimes_R N) \cong T \otimes_R N$ naturally in N.
7. Show that theorem 15.3.9 is natural in C: for an S-module homomorphism $h\colon C \to C'$, the two ways of passing from $\mathrm{Hom}_S(A \otimes_R B, C)$ to $\mathrm{Hom}_R(A, \mathrm{Hom}_S(B, C'))$ agree.

15.4 Application: The Kronecker Product

Chapter 13 and chapter 14 computed with matrices: a linear map became an array once bases were chosen, and questions about the map became questions about the array. Nothing in this chapter has

yet been written down that way. The apparatus for doing so is already in place: corollary 15.2.6 says that bases of V and W determine a basis of $V \otimes_R W$, and theorem 15.2.2 says that maps of the factors determine a map of the tensor product. Putting the two together produces a matrix, and it has a name.

Definition 15.4.1: Kronecker Product

Let R be a commutative ring, let $A = (a_{ij}) \in M_{m\times n}(R)$ and let $B \in M_{p\times q}(R)$. The *Kronecker product* $A \otimes B \in M_{mp\times nq}(R)$ is the block matrix

$$A \otimes B := \begin{pmatrix} a_{11}B & a_{12}B & \cdots & a_{1n}B \\ a_{21}B & a_{22}B & \cdots & a_{2n}B \\ \vdots & \vdots & \ddots & \vdots \\ a_{m1}B & a_{m2}B & \cdots & a_{mn}B \end{pmatrix}$$

Equivalently, indexing rows by pairs (i,k) with $1 \le i \le m$, $1 \le k \le p$ and columns by pairs (j,l) with $1 \le j \le n$, $1 \le l \le q$, both ordered lexicographically,

$$(A \otimes B)_{(i,k),(j,l)} = a_{ij}b_{kl}$$

The lexicographic indexing is part of the definition rather than a convenience: a different ordering of the pairs produces a matrix conjugate to this one by a permutation, which is the content of proposition 15.4.3(4) below. Every statement in this section is made with respect to that ordering.

Proposition 15.4.2: The Kronecker Product Represents the Tensor Product of Maps

Let R be a commutative ring and let V, V', W, W' be free R-modules with ordered bases $(e_1,\dots,e_n)$, $(e'_1,\dots,e'_m)$, $(f_1,\dots,f_q)$ and $(f'_1,\dots,f'_p)$ respectively. Let $\varphi\colon V \to V'$ be represented by A and $\psi\colon W \to W'$ by B. Give $V \otimes_R W$ the basis $(e_j \otimes f_l)$ and $V' \otimes_R W'$ the basis $(e'_i \otimes f'_k)$ of corollary 15.2.6, each ordered lexicographically. Then $\varphi \otimes \psi$ is represented by $A \otimes B$.

***Proof*:**
By theorem 15.2.2 and the bilinearity of $\otimes$,

$$(\varphi\otimes\psi)(e_j \otimes f_l) = \varphi(e_j)\otimes\psi(f_l) = \left(\sum_{i=1}^{m} a_{ij}e'_i\right) \otimes \left(\sum_{k=1}^{p} b_{kl}f'_k\right) = \sum_{i=1}^{m}\sum_{k=1}^{p} a_{ij}b_{kl}\,(e'_i \otimes f'_k)$$

By definition 13.2.1 the entry of the representing matrix in row (i,k) and column (j,l) is the coefficient of $e'_i \otimes f'_k$ in the image of $e_j \otimes f_l$, which the display gives as $a_{ij}b_{kl}$. That is the entry prescribed by definition 15.4.1, completing the proof.

Every property of the Kronecker product below is therefore a property of $\otimes$ read in coordinates, and the two viewpoints are used interchangeably from here on.

Proposition 15.4.3: Arithmetic of the Kronecker Product

Let R be a commutative ring.

1. (mixed product rule) $(A\otimes B)(C\otimes D)=(AC)\otimes(BD)$ whenever AC and BD are defined.
2. $I_m\otimes I_p=I_{mp}$.
3. If $A\in M_m(R)$ and $B\in M_p(R)$ are invertible then so is $A\otimes B$, with $(A\otimes B)^{-1}=A^{-1}\otimes B^{-1}$.
4. There is a permutation matrix $P\in M_{mp}(R)$, depending only on m and p, with
$$P(A\otimes B)P^{-1}=B\otimes A$$
for all $A\in M_m(R)$ and $B\in M_p(R)$.

***Proof*:**

1. Both sides are indexed by pairs, and summing over the intermediate index pair (r,s),
$$\begin{aligned}\big((A\otimes B)(C\otimes D)\big)_{(i,k),(j,l)}&=\sum_r\sum_s a_{ir}b_{ks}\,c_{rj}d_{sl}\\&=\left(\sum_r a_{ir}c_{rj}\right)\left(\sum_s b_{ks}d_{sl}\right)=(AC)_{ij}(BD)_{kl}\end{aligned}$$
the middle step using commutativity of R to separate the two sums. The right-hand side is the $(i,k),(j,l)$ entry of $(AC)\otimes(BD)$.
2. $(I_m\otimes I_p)_{(i,k),(j,l)}=\delta_{ij}\delta_{kl}$, which is 1 if $(i,k)=(j,l)$ and 0 otherwise.
3. By (1) and (2), $(A\otimes B)(A^{-1}\otimes B^{-1})=(AA^{-1})\otimes(BB^{-1})=I_m\otimes I_p=I_{mp}$, and the same on the other side.
4. Both $\{(i,k)\}$ and $\{(k,i)\}$ index sets of size mp, so the slot-exchanging bijection $\pi(i,k)=(k,i)$ between them has a permutation matrix P, determined by $Pe_{(i,k)}=e_{(k,i)}$ on standard basis vectors. For any M this gives $\big(PMP^{-1}\big)e_{\pi(y)}=PMe_y=\sum_x M_{xy}e_{\pi(x)}$, that is $\big(PMP^{-1}\big)_{\pi(x),\pi(y)}=M_{x,y}$. Applying this with $M=A\otimes B$,
$$\big(P(A\otimes B)P^{-1}\big)_{(k,i),(l,j)}=(A\otimes B)_{(i,k),(j,l)}=a_{ij}b_{kl}=b_{kl}a_{ij}=(B\otimes A)_{(k,i),(l,j)}$$
again using commutativity, completing the proof.

Part (4) is proposition 15.2.7 in coordinates: the isomorphism $V\otimes W\cong W\otimes V$ becomes, once bases are fixed on both sides, conjugation by the permutation that exchanges the two index slots. The matrix P is the reason the ordering convention in definition 15.4.1 is harmless.

The trace and the determinant of a Kronecker product are determined by those of the factors. Both formulas hold over an arbitrary commutative ring.

Theorem 15.4.4: Trace and Determinant of a Kronecker Product

Let R be a commutative ring, $A \in M_m(R)$ and $B \in M_p(R)$. Then

$$\operatorname{tr}(A \otimes B) = \operatorname{tr}(A)\operatorname{tr}(B) \qquad \text{and} \qquad \det(A \otimes B) = \big(\det A\big)^p \big(\det B\big)^m$$

***Proof*:**

Trace. The diagonal entries of $A \otimes B$ are those indexed by $(i,k) = (j,l)$, that is by $i = j$ and $k = l$, and there the entry is $a_{ii}b_{kk}$. Hence

$$\operatorname{tr}(A \otimes B) = \sum_{i=1}^{m}\sum_{k=1}^{p} a_{ii}b_{kk} = \left(\sum_{i=1}^{m} a_{ii}\right)\left(\sum_{k=1}^{p} b_{kk}\right) = \operatorname{tr}(A)\operatorname{tr}(B)$$

Determinant. By the mixed product rule and proposition 15.4.3(2),

$$A \otimes B = (AI_m) \otimes (I_pB) = (A \otimes I_p)(I_m \otimes B)$$

so $\det(A \otimes B) = \det(A \otimes I_p)\det(I_m \otimes B)$ by proposition 13.4.7. The second factor is immediate: $I_m \otimes B$ is block diagonal with m diagonal blocks, each equal to B, so $\det(I_m \otimes B) = (\det B)^m$ by proposition 13.4.8.

For the first factor, proposition 15.4.3(4) gives a permutation matrix P with $P(A \otimes I_p)P^{-1} = I_p \otimes A$. Determinants are unchanged by conjugation, since proposition 13.4.7 gives $\det(P)\det(P^{-1}) = \det(PP^{-1}) = \det(I) = 1$ and hence $\det(PMP^{-1}) = \det(M)$. Now $I_p \otimes A$ is block diagonal with p diagonal blocks each equal to A, so

$$\det(A \otimes I_p) = \det(I_p \otimes A) = (\det A)^p$$

by proposition 13.4.8 again. Multiplying the two factors gives the claim, as we sought to show.

Note the asymmetry of the exponents: each determinant is raised to the size of the *other* factor. A quick check is $A = B = I$, where both sides are 1, and a sharper one is $m = p = 2$ with $\det A = \det B = 2$, giving $\det(A \otimes B) = 16$ rather than 4.

Rank behaves as simply, though here a field is needed: the argument passes through a complement, and over a general commutative ring a submodule need not be a direct summand.

Proposition 15.4.5: Rank of a Kronecker Product

Let F be a field, $A \in M_{m\times n}(F)$ and $B \in M_{p\times q}(F)$. Then

$$\operatorname{rank}(A \otimes B) = \operatorname{rank}(A) \cdot \operatorname{rank}(B)$$

***Proof*:**

Let $\varphi\colon V \to V'$ and $\psi\colon W \to W'$ be the linear maps represented by A and B, so that $A \otimes B$ represents $\varphi \otimes \psi$ by proposition 15.4.2, and rank is the dimension of the image (definition 13.1.19).

Choose complements $V' = \operatorname{im}\varphi \oplus U$ and $W' = \operatorname{im}\psi \oplus U'$, which exist because F is a field.

Applying theorem 15.2.3 in each variable,

$$V' \otimes_F W' \cong \big(\mathrm{im}\varphi \otimes \mathrm{im}\psi\big) \oplus \big(\mathrm{im}\varphi \otimes U'\big) \oplus \big(U \otimes \mathrm{im}\psi\big) \oplus \big(U \otimes U'\big)$$

and under this decomposition the natural map $\mathrm{im}\varphi \otimes_F \mathrm{im}\psi \to V' \otimes_F W'$ is the inclusion of the first summand, hence injective.

The image of $\varphi \otimes \psi$ is exactly that summand. It is contained in it: every element of $V \otimes_F W$ is a finite sum of simple tensors by lemma 15.1.4(2), and $(\varphi \otimes \psi)(v \otimes w) = \varphi(v) \otimes \psi(w)$ lies in $\mathrm{im}\varphi \otimes \mathrm{im}\psi$. It contains it, because those same elements $\varphi(v) \otimes \psi(w)$ span $\mathrm{im}\varphi \otimes \mathrm{im}\psi$, again by lemma 15.1.4(2) applied there. Therefore

$$\mathrm{rank}(\varphi \otimes \psi) = \dim_F \big(\mathrm{im}\varphi \otimes_F \mathrm{im}\psi\big) = \dim_F(\mathrm{im}\varphi) \cdot \dim_F(\mathrm{im}\psi) = \mathrm{rank}(\varphi)\mathrm{rank}(\psi)$$

the middle equality being corollary 15.2.6, as we sought to show.

Eigenvalues multiply as well. One half of the statement needs nothing at all.

Proposition 15.4.6: Eigenvectors of a Kronecker Product

Let F be a field, $A \in M_m(F)$, $B \in M_p(F)$, and suppose $Av = \lambda v$ and $Bw = \mu w$ with $v \neq 0$ and $w \neq 0$. Then $v \otimes w \neq 0$ and

$$(A \otimes B)(v \otimes w) = \lambda\mu\,(v \otimes w)$$

so $\lambda\mu$ is an eigenvalue of $A \otimes B$.

***Proof*:**
Reading $A \otimes B$ as $\varphi \otimes \psi$ by proposition 15.4.2 and applying theorem 15.2.2,

$$(\varphi \otimes \psi)(v \otimes w) = \varphi(v) \otimes \psi(w) = (\lambda v) \otimes (\mu w) = \lambda\mu\,(v \otimes w)$$

using bilinearity to extract both scalars. For $v \otimes w \neq 0$, extend v to a basis of F^m and w to a basis of F^p. Then $v \otimes w$ is one of the basis elements of $F^m \otimes_F F^p$ furnished by corollary 15.2.6, and a basis element is nonzero, completing the proof.

That accounts for the products of eigenvalues that come from actual eigenvectors. The full spectrum, counted with multiplicity, needs a triangular form, and theorem 14.4.5 gives one exactly when the minimal polynomials split.

Theorem 15.4.7: Spectrum of a Kronecker Product

Let F be a field and let $A \in M_m(F)$ and $B \in M_p(F)$ have minimal polynomials that split into linear factors over F, which holds for all A and B when F is algebraically closed. List the eigenvalues of A as $\lambda_1, \dots, \lambda_m$ and those of B as $\mu_1, \dots, \mu_p$, each repeated according to its algebraic multiplicity. Then the characteristic polynomial of $A \otimes B$ is

$$\prod_{i=1}^{m} \prod_{k=1}^{p} (x - \lambda_i \mu_k)$$

so the eigenvalues of $A \otimes B$, with algebraic multiplicity, are the mp products $\lambda_i \mu_k$.

***Proof*:**

Two general facts are used repeatedly, so both are recorded first.

The determinant of an upper triangular matrix is the product of its diagonal entries. In the defining sum a term $\prod_i t_{i\sigma(i)}$ is nonzero only if $i \leq \sigma(i)$ for every i, and since $\sum_i \big(\sigma(i) - i\big) = 0$ this forces $\sigma(i) = i$ for all i. Only the identity term survives. Consequently an upper triangular T has characteristic polynomial $\prod_i (x - t_{ii})$, since $xI - T$ is again upper triangular.

Similar matrices have the same characteristic polynomial, because $\det\big(xI - PMP^{-1}\big) = \det\big(P(xI - M)P^{-1}\big) = \det(xI - M)$ by proposition 13.4.7, applied over the commutative ring $F[x]$.

Now by theorem 14.4.5 there are invertible P and Q with $A = PJ_AP^{-1}$ and $B = QJ_BQ^{-1}$, where J_A and J_B are in Jordan canonical form and hence upper triangular. Combining the two facts, the characteristic polynomial of A is $\prod_i (x - (J_A)_{ii})$, so the diagonal entries of J_A are exactly the eigenvalues $\lambda_1, \dots, \lambda_m$ of A listed with algebraic multiplicity, and likewise for J_B and the μ_k.

By the mixed product rule and proposition 15.4.3(3),

$$A \otimes B = \big(PJ_AP^{-1}\big) \otimes \big(QJ_BQ^{-1}\big) = (P \otimes Q)\,(J_A \otimes J_B)\,(P \otimes Q)^{-1}$$

so $A \otimes B$ is similar to $J_A \otimes J_B$ and the two have the same characteristic polynomial.

The matrix $J_A \otimes J_B$ is upper triangular for the lexicographic ordering. Its $(i,k),(j,l)$ entry is $(J_A)_{ij}(J_B)_{kl}$, which vanishes unless $i \leq j$ and $k \leq l$. And if (i,k) comes strictly after (j,l) lexicographically then either $i > j$, or $i = j$ and $k > l$, and in both cases one of the two factors is 0. Its diagonal entries are $(J_A)_{ii}(J_B)_{kk} = \lambda_i \mu_k$.

So $J_A \otimes J_B$ is upper triangular with diagonal entries $\lambda_i \mu_k$, and by the first recorded fact its characteristic polynomial is $\prod_{i,k}(x - \lambda_i \mu_k)$, as we sought to show.

Example 15.4.8: Computing with the Kronecker Product

Take $R = \mathbb{Q}$ and

$$A = \begin{pmatrix} 1 & 2 \\ 3 & 4 \end{pmatrix}, \qquad B = \begin{pmatrix} 0 & 1 \\ -1 & 0 \end{pmatrix}$$

so that $\det A = -2$, $\mathrm{tr}A = 5$, $\det B = 1$ and $\mathrm{tr}B = 0$. Assembling the blocks $a_{ij}B$,

$$A \otimes B = \begin{pmatrix} 0 & 1 & 0 & 2 \\ -1 & 0 & -2 & 0 \\ 0 & 3 & 0 & 4 \\ -3 & 0 & -4 & 0 \end{pmatrix}$$

Its diagonal entries are all 0, so its trace is $0 = 5 \cdot 0 = \mathrm{tr}(A)\mathrm{tr}(B)$, as theorem 15.4.4 requires. That theorem also predicts

$$\det(A \otimes B) = (\det A)^2(\det B)^2 = (-2)^2 \cdot 1^2 = 4$$

Both A and B are invertible, so both have rank 2, and proposition 15.4.5 predicts $\mathrm{rank}(A \otimes B) = 4$, consistent with the nonzero determinant.

Replacing A by the rank one matrix

$$A' = \begin{pmatrix} 1 & 1 \\ 1 & 1 \end{pmatrix}$$

gives $\mathrm{rank}(A' \otimes B) = 1 \cdot 2 = 2$, so $A' \otimes B$ is a 4×4 matrix of rank 2. Correspondingly $\det(A' \otimes B) = (\det A')^2(\det B)^2 = 0$. Note that the rank drops to 2 rather than to 3: a Kronecker product cannot have rank 3 at all, since by proposition 15.4.5 its rank is a product of two integers each at most 2.

One identification remains, and it explains a phenomenon recorded without explanation in section 15.1. For finite-dimensional spaces the tensor product of a dual space with another space is the space of linear maps between them.

Theorem 15.4.9: $V^* \otimes W$ and Linear Maps

Let F be a field and let V, W be finite-dimensional F-vector spaces. Then

$$\Theta\colon V^* \otimes_F W \to \mathrm{Hom}_F(V, W), \qquad \Theta(f \otimes w)(v) = f(v)\, w$$

is an isomorphism of F-vector spaces. Under Θ:

1. the simple tensors correspond exactly to the homomorphisms of rank at most one;
2. the least number of simple tensors whose sum is a given $t \in V^* \otimes_F W$ equals $\mathrm{rank}\Theta(t)$.

***Proof*:**

The map $(f, w) \mapsto \big(v \mapsto f(v)w\big)$ is F-bilinear, so theorem 15.1.12 gives the F-linear map Θ.

Let $(e_1, \ldots, e_n)$ be a basis of V with dual basis $(e_1^*, \ldots, e_n^*)$ (section 13.3) and $(w_1, \ldots, w_p)$ a basis of W. By corollary 15.2.6 the np elements $e_i^* \otimes w_k$ form a basis of $V^* \otimes_F W$. Their images are the maps $e_j \mapsto \delta_{ij}w_k$, whose matrices with respect to the two bases are the np elementary matrices having a single 1 in position (k, i). Those form a basis of $\mathrm{Hom}_F(V, W)$. An F-linear map carrying a basis onto a basis is an isomorphism, so Θ is one.

(1). The image of $\Theta(f \otimes w)$ is contained in Fw, so its rank is at most one. Conversely, let θ have rank at most one. If $\theta = 0$ it is $\Theta(0 \otimes 0)$. Otherwise $\mathrm{im}\theta = Fw$ for some $w \neq 0$, and writing $\theta(v) = f(v)w$ defines a map $f\colon V \to F$ which is linear because θ is and w is a basis of its image.

Then $\theta = \Theta(f \otimes w)$.

(2). If $t = \sum_{j=1}^{r} f_j \otimes w_j$ then $\Theta(t) = \sum_j \Theta(f_j \otimes w_j)$ is a sum of r maps of rank at most one. The image of a sum is contained in the sum of the images, and $\dim(X+Y) \le \dim X + \dim Y$, so $\operatorname{rank}\Theta(t) \le r$. Conversely let $\operatorname{rank}\Theta(t) = r$ and choose a basis $u_1, \dots, u_r$ of $\operatorname{im}\Theta(t)$. Every v has $\Theta(t)(v) = \sum_{j=1}^{r} g_j(v) u_j$ for unique scalars $g_j(v)$, and each $g_j \colon V \to F$ so defined is linear because $\Theta(t)$ is and the u_j are independent. Then $\Theta\big(\sum_j g_j \otimes u_j\big) = \Theta(t)$, and Θ is injective, so $t = \sum_{j=1}^{r} g_j \otimes u_j$ is a sum of r simple tensors, completing the proof.

Part (2) settles the question left open in box 15.1.6. Taking $W = V$ of dimension n, the element $\sum_{i=1}^{n} e_i^* \otimes e_i$ corresponds under Θ to the identity map, which has rank n. So it needs exactly n simple tensors and is not itself simple once $n \ge 2$. The witness exhibited there, $e_1 \otimes e_1 + e_2 \otimes e_2$, is this element for $n = 2$ under the identification of V with V^* by the dual basis, and the ad hoc argument given there is replaced by a count of rank.

Exercise 15.4.1

1. Show that $A \otimes B$ and $B \otimes A$ are always similar, and give explicit 2×2 matrices A and B for which they are not equal.
2. Show that $(A \otimes B)^k = A^k \otimes B^k$ for every $k \ge 1$, and deduce that if $A^r = 0$ then $(A \otimes B)^r = 0$ for every B. Conclude that a Kronecker product with a nilpotent factor is nilpotent, with index at most that of the factor.
3. Deduce from the mixed product rule that $A \mapsto A \otimes I_p$ is an injective ring homomorphism $M_m(R) \to M_{mp}(R)$, and that its image commutes elementwise with the image of $B \mapsto I_m \otimes B$.
4. Identify the step in the proof of proposition 15.4.5 that requires a field. Then show it genuinely fails over $\mathbb{Z}$: with $\varphi \colon \mathbb{Z} \to \mathbb{Z}$ multiplication by 2 and ψ the identity on $\mathbb{Z}/2\mathbb{Z}$, show that the natural map $\operatorname{im}\varphi \otimes_{\mathbb{Z}} \mathbb{Z}/2\mathbb{Z} \to \mathbb{Z} \otimes_{\mathbb{Z}} \mathbb{Z}/2\mathbb{Z}$ is not injective.
5. Let V and W be arbitrary vector spaces over F, not assumed finite dimensional. Show that Θ of theorem 15.4.9 is still injective and that its image is exactly the set of homomorphisms of finite rank. Deduce that Θ is an isomorphism if and only if V or W is finite dimensional.
6. Show that under the isomorphism $V^* \otimes_F V \cong \operatorname{End}_F(V)$ of theorem 15.4.9, the trace of definition 13.4.3 corresponds to the evaluation map determined by $f \otimes v \mapsto f(v)$. (This is the basis-free description of the trace.)

15.5 Summary

Everything in this chapter rests on one universal property: bilinear maps out of $M \times N$ are homomorphisms out of a single module $M \otimes_R N$. The tables below state what follows from it, each entry pointing at the result that establishes it.

Representing objects and adjunctions

Each class of map has a representing object, and in every case it is a tensor product. The representing object is determined up to unique isomorphism by its property (corollary 15.1.7), so the particular

construction used in definition 15.1.3 is not part of the data.

Maps	On	Represented by	Reference
R-balanced, into an abelian group	$M \times N$	$M \otimes_R N$	theorem 15.1.5
R-bilinear, into an R-module	$M \times N$	$M \otimes_R N$	theorem 15.1.12
R-multilinear	$M_1 \times \cdots \times M_n$	$M_1 \otimes_R \cdots \otimes_R M_n$	theorem 15.2.11
R-linear, into an S-module	N	$S \otimes_R N$	theorem 15.3.4
Pairs of R-algebra maps	A, B	$A \otimes_R B$	theorem 15.2.17

The second and third rows require R commutative and the standard structures of example 15.1.9(4). The fifth requires A and B commutative. Two facts are used constantly with these: simple tensors generate, so a homomorphism out of a tensor product is determined by its values on them (lemma 15.1.4), and not every element is itself simple (box 15.1.6).

Two of these are adjunctions.

Left adjoint	Right adjoint	Reference
$S \otimes_R -$	restriction of scalars along $R \to S$	corollary 15.3.5
$- \otimes_R B$	$\mathrm{Hom}_S(B, -)$	theorem 15.3.9

The first is the case $B = S$ of the second.

Module structure

The tensor product of a right module and a left module is only an abelian group. Any further structure comes from a second action on one of the factors.

Hypothesis	Structure on $M \otimes_R N$	Reference
M right R-, N left R-module	abelian group only	definition 15.1.3
M an (S, R)-bimodule	left S-module	proposition 15.1.10
M an (S, R)-, N an (R, T)-bimodule	(S, T)-bimodule	proposition 15.2.1
R commutative, standard structures	R-module	theorem 15.1.12
A, B R-algebras	R-algebra	theorem 15.2.14

What is preserved, and what is not

Statement	Reference
$R \otimes_R N \cong N$	example 15.1.13
$(\bigoplus_i M_i) \otimes_R N \cong \bigoplus_i (M_i \otimes_R N)$	theorem 15.2.4
Free $\otimes$ free is free, on the basis $\{m_i \otimes n_j\}$	corollary 15.2.6
$M \otimes_R N \cong N \otimes_R M$	proposition 15.2.7
$(M \otimes_R N) \otimes_T L \cong M \otimes_R (N \otimes_T L)$	theorem 15.2.8
$(\lambda \otimes \mu) \circ (\varphi \otimes \psi) = (\lambda \circ \varphi) \otimes (\mu \circ \psi)$	theorem 15.2.2
$\mathrm{rank}(A \otimes B) = \mathrm{rank}(A)\mathrm{rank}(B)$ over a field	proposition 15.4.5

The first, fourth and fifth rows are the unit, commutativity and associativity constraints of a symmetric monoidal structure on R-Mod (box 15.2.9).

Fails	**Witness**	**Reference**
Being nonzero	$\mathbb{Z}/2\mathbb{Z} \otimes_{\mathbb{Z}} \mathbb{Z}/3\mathbb{Z} = 0$	example 15.1.14
Injectivity of a map	multiplication by 2 against $\mathbb{Z}/2\mathbb{Z}$	section 17.5
Containing the original module	ι has a kernel	corollary 15.3.8
Being an integral domain	$\mathbb{C} \otimes_{\mathbb{R}} \mathbb{C} \cong \mathbb{C} \times \mathbb{C}$	example 15.2.15

The second row is the one with consequences beyond this chapter: which modules D make $D \otimes_R -$ preserve injections is the definition of flatness, taken up in section 17.5.

In coordinates

Once bases are fixed, corollary 15.2.6 turns each of the constructions above into a matrix identity.

Object	**Coordinate form**	**Reference**
$\varphi \otimes \psi$	the Kronecker product $(a_{ij}B)$	proposition 15.4.2
$\operatorname{tr}(A \otimes B)$	$\operatorname{tr}(A)\operatorname{tr}(B)$	theorem 15.4.4
$\det(A \otimes B)$	$(\det A)^p (\det B)^m$	theorem 15.4.4
Eigenvalues of $A \otimes B$	the products $\lambda_i \mu_k$	theorem 15.4.7
$\operatorname{Hom}_F(V, W)$	$V^* \otimes_F W$	theorem 15.4.9

Computations worth reusing

Identity	**Reference**
$\mathbb{Z}/m\mathbb{Z} \otimes_{\mathbb{Z}} \mathbb{Z}/n\mathbb{Z} \cong \mathbb{Z}/\gcd(m,n)\mathbb{Z}$	proposition 15.2.13
$R/I \otimes_R R/J \cong R/(I+J)$	proposition 15.2.13
$S \otimes_R R^n \cong S^n$	example 15.3.3
$V_{\mathbb{C}} = \mathbb{C} \otimes_{\mathbb{R}} V$, with $\dim_{\mathbb{C}} V_{\mathbb{C}} = \dim_{\mathbb{R}} V$	example 15.3.6
$A \otimes_{\mathbb{Z}} B$ is the coproduct in **CRing**	corollary 15.2.18

16

Multilinear Algebra

Chapter 15 represented the bilinear maps on a product of two modules. Fixing a single module M and allowing more arguments produces further classes of map on M^k: the k-multilinear maps, those left unchanged by permuting the arguments, and those that vanish whenever two arguments coincide. Each class has its own representing object, and the three objects are quotients of one another.

Summing over k turns each family of representing objects into a ring. The tensor algebra $\mathcal{T}(M)$, the symmetric algebra $\mathcal{S}(M)$ and the exterior algebra $\bigwedge(M)$ are graded by the number of arguments, and each carries a universal property of its own, now for homomorphisms into an algebra rather than into a module. The determinant returns at the end as the map an endomorphism induces on the top exterior power, recovering section 13.4 from a universal property rather than from the defining sum.

16.1 Multilinear, Symmetric and Alternating Maps

The k-multilinear maps on M already have a representing object. Definition 15.2.10 defined the class and theorem 15.2.11 produced the module through which every such map factors: an R-linear map out of the k-fold tensor product of M with itself is the same thing as a k-multilinear map on M^k.

Two subclasses of these maps occur constantly, and both are cut out by requiring the map to be insensitive to something. A symmetric map does not see the order of its arguments. An alternating map vanishes on a repetition among them. Each subclass is again represented by a module, and in each case that module is a quotient of the k-fold tensor product by exactly the elements the subclass is required to kill. That is the pattern of this section, applied three times.

Definition 16.1.1: Tensor Powers

Let R be a commutative ring and M an R-module. For $k \geq 1$ the *k-th tensor power* of M is

$$\mathcal{T}^k(M) := \underbrace{M \otimes_R M \otimes_R \cdots \otimes_R M}_{k \text{ factors}}$$

bracketed to the left as in section 15.2, with $\mathcal{T}^0(M) := R$ and $\mathcal{T}^1(M) = M$. Its elements are called *k-tensors*.

In this notation theorem 15.2.11 reads: the map $M^k \to \mathcal{T}^k(M)$ sending $(m_1, \ldots, m_k)$ to $m_1 \otimes \cdots \otimes m_k$ is k-multilinear, and every k-multilinear map on M^k factors through it uniquely by an R-module homomorphism. Nothing further is needed about $\mathcal{T}^k(M)$ here. The two quotients are what this section constructs.

Definition 16.1.2: Symmetric Multilinear Maps

Let R be a commutative ring and let M, N be R-modules. A k-multilinear map $\varphi\colon M^k \to N$ is *symmetric* if

$$\varphi\big(m_{\sigma(1)}, \ldots, m_{\sigma(k)}\big) = \varphi(m_1, \ldots, m_k)$$

for every $\sigma \in S_k$ and all $m_1, \ldots, m_k \in M$.

Definition 16.1.3: Alternating Multilinear Maps

With R, M, N as above, a k-multilinear map $\varphi\colon M^k \to N$ is *alternating* if

$$\varphi(m_1, \ldots, m_k) = 0 \qquad \text{whenever } m_i = m_j \text{ for some } i \neq j$$

The determinant of definition 13.4.5, read as a function of the n columns of a matrix, is the standard example of an alternating n-multilinear map $(R^n)^n \to R$: it is multilinear in the columns and vanishes when two of them agree, which is proposition 13.4.6(3) and (4). A symmetric bilinear form, such as an inner product (section 13.6), is the standard example of a symmetric map.

Alternating maps are often introduced by a sign rule rather than by the vanishing condition. The two agree except in characteristic 2, and the direction that always holds is worth isolating, since it is what makes the exterior power computable.

Lemma 16.1.4: Equivalence Of Alternating Map

Let R be a commutative ring and let $\varphi\colon M^k \to N$ be k-multilinear.

1. If φ is alternating then for every $\sigma \in S_k$,

$$\varphi\big(m_{\sigma(1)}, \ldots, m_{\sigma(k)}\big) = (-1)^{\sigma}\, \varphi(m_1, \ldots, m_k)$$

2. If 2 is a unit in R, the converse holds: a k-multilinear map satisfying the displayed sign rule is alternating.

***Proof*:**
(1). For $\sigma \in S_k$ write $\varphi^\sigma(m_1, \dots, m_k) := \varphi(m_{\sigma(1)}, \dots, m_{\sigma(k)})$. Substituting shows $(\varphi^\sigma)^\tau = \varphi^{\tau\sigma}$, so if the identity $\varphi^\sigma = (-1)^\sigma \varphi$ holds for two permutations it holds for their product:

$$\varphi^{\tau\sigma} = (\varphi^\sigma)^\tau = \big((-1)^\sigma \varphi\big)^\tau = (-1)^\sigma \varphi^\tau = (-1)^\sigma (-1)^\tau \varphi = (-1)^{\tau\sigma} \varphi$$

Since the transpositions generate S_k, it therefore suffices to treat a transposition $\tau = (a\ b)$ with $a < b$.

Fix all arguments except those in positions a and b, and let $f(x, y)$ denote the value of φ with x in position a and y in position b. Then f is bilinear, and $f(x, x) = 0$ for every x because φ is alternating. Expanding,

$$0 = f(x + y,\, x + y) = f(x, x) + f(x, y) + f(y, x) + f(y, y) = f(x, y) + f(y, x)$$

so $f(y, x) = -f(x, y)$, which is exactly the claim for τ.

(2). Suppose the sign rule holds and $m_i = m_j$ with $i \neq j$. Applying the rule to the transposition $\tau = (i\ j)$, the left-hand side is φ evaluated at the same arguments, since interchanging two equal entries changes nothing, while the right-hand side is $-\varphi(m_1, \dots, m_k)$. Hence $2\,\varphi(m_1, \dots, m_k) = 0$, and multiplying by the inverse of 2 gives $\varphi(m_1, \dots, m_k) = 0$, completing the proof.

The hypothesis in (2) cannot be dropped. Over $R = \mathbb{Z}/2\mathbb{Z}$ every sign $(-1)^\sigma$ equals 1, so the sign rule says only that the map is symmetric. And the multiplication map $\varphi\colon \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z} \to \mathbb{Z}/2\mathbb{Z}$ with $\varphi(x, y) = xy$ is symmetric and bilinear but has $\varphi(\overline{1}, \overline{1}) = \overline{1} \neq \overline{0}$, so it is not alternating. In characteristic 2 the vanishing condition of definition 16.1.3 is strictly stronger, and it is the one the exterior power is built from.

Each subclass is now represented, by quotienting $\mathcal{T}^k(M)$ by the elements a map in the subclass is obliged to kill.

Definition 16.1.5: Symmetric Powers

Let $C^k(M) \subseteq \mathcal{T}^k(M)$ be the submodule generated by all elements

$$m_1 \otimes \cdots \otimes m_k - m_{\sigma(1)} \otimes \cdots \otimes m_{\sigma(k)} \qquad \sigma \in S_k,\ m_i \in M$$

The *k-th symmetric power* of M is $\mathcal{S}^k(M) := \mathcal{T}^k(M)/C^k(M)$, and the image of $m_1 \otimes \cdots \otimes m_k$ is written $m_1 m_2 \cdots m_k$. Since $C^0(M) = C^1(M) = 0$, one has $\mathcal{S}^0(M) = R$ and $\mathcal{S}^1(M) = M$.

Theorem 16.1.6: Universal Property of the Symmetric Power

Let R be a commutative ring and M an R-module. The map

$$\varsigma\colon M^k \to \mathcal{S}^k(M), \qquad \varsigma(m_1, \dots, m_k) = m_1 m_2 \cdots m_k$$

is symmetric and k-multilinear, and it is universal among such maps: for every R-module N and every symmetric k-multilinear $\varphi\colon M^k \to N$ there is a unique R-module homomorphism $\overline{\varphi}\colon \mathcal{S}^k(M) \to N$ with $\varphi = \overline{\varphi} \circ \varsigma$.

***Proof*:**
The map ς is the composite of the universal k-multilinear map of theorem 15.2.11 with the quotient map $\pi\colon \mathcal{T}^k(M) \to \mathcal{S}^k(M)$, hence k-multilinear. It is symmetric because the difference $m_1 \otimes \cdots \otimes m_k - m_{\sigma(1)} \otimes \cdots \otimes m_{\sigma(k)}$ lies in $C^k(M)$ by construction and so maps to 0.

Let φ be symmetric and k-multilinear. By theorem 15.2.11 there is a unique R-module homomorphism $\psi\colon \mathcal{T}^k(M) \to N$ with $\psi(m_1 \otimes \cdots \otimes m_k) = \varphi(m_1, \ldots, m_k)$. On a generator of $C^k(M)$,

$$\psi\big(m_1 \otimes \cdots \otimes m_k - m_{\sigma(1)} \otimes \cdots \otimes m_{\sigma(k)}\big) = \varphi(m_1, \ldots, m_k) - \varphi(m_{\sigma(1)}, \ldots, m_{\sigma(k)}) = 0$$

precisely because φ is symmetric. A homomorphism vanishing on a generating set vanishes on the submodule it generates, so $C^k(M) \subseteq \ker\psi$ and ψ factors through the quotient, giving $\overline{\varphi}$ with $\overline{\varphi} \circ \varsigma = \varphi$.

For uniqueness, the products $m_1 \cdots m_k$ generate $\mathcal{S}^k(M)$, being the images of the simple tensors, which generate $\mathcal{T}^k(M)$. Two homomorphisms agreeing on a generating set are equal, as we sought to show.

Definition 16.1.7: Exterior Powers

Let $A^k(M) \subseteq \mathcal{T}^k(M)$ be the submodule generated by all simple tensors

$$m_1 \otimes \cdots \otimes m_k \qquad \text{with } m_i = m_j \text{ for some } i \neq j$$

The *k-th exterior power* of M is $\bigwedge^k(M) := \mathcal{T}^k(M)/A^k(M)$, and the image of $m_1 \otimes \cdots \otimes m_k$ is written $m_1 \wedge \cdots \wedge m_k$, the operation being called the *wedge* or *exterior product*. Since $A^0(M) = A^1(M) = 0$, one has $\bigwedge^0(M) = R$ and $\bigwedge^1(M) = M$.

Theorem 16.1.8: Universal Property of the Exterior Power

Let R be a commutative ring and M an R-module. The map

$$\alpha\colon M^k \to \bigwedge^k(M), \qquad \alpha(m_1, \ldots, m_k) = m_1 \wedge \cdots \wedge m_k$$

is alternating and k-multilinear, and it is universal among such maps: for every R-module N and every alternating k-multilinear $\varphi\colon M^k \to N$ there is a unique R-module homomorphism $\overline{\varphi}\colon \bigwedge^k(M) \to N$ with $\varphi = \overline{\varphi} \circ \alpha$.

***Proof*:**
As before α is k-multilinear, being the composite of the universal k-multilinear map with the quotient map, and it is alternating because a simple tensor with a repeated entry lies in $A^k(M)$ by construction.

Given an alternating k-multilinear φ, let $\psi\colon \mathcal{T}^k(M) \to N$ be the homomorphism given by theorem 15.2.11. Each generator of $A^k(M)$ is a simple tensor $m_1 \otimes \cdots \otimes m_k$ with $m_i = m_j$ for some $i \neq j$, and ψ sends it to $\varphi(m_1, \ldots, m_k)$, which is 0 because φ is alternating. So $A^k(M) \subseteq \ker\psi$ and ψ factors through $\bigwedge^k(M)$. Uniqueness holds because the elements $m_1 \wedge \cdots \wedge m_k$ generate

$\bigwedge^k(M)$, completing the proof.

The sign rule now transfers from maps to elements.

Proposition 16.1.9: Anticommutativity of the Wedge Product

Let M be an R-module. In $\bigwedge^k(M)$,

$$m_1 \wedge \cdots \wedge m_k = 0 \quad \text{whenever } m_i = m_j \text{ for some } i \neq j$$
$$m_{\sigma(1)} \wedge \cdots \wedge m_{\sigma(k)} = (-1)^\sigma \, m_1 \wedge \cdots \wedge m_k$$

for every $\sigma \in S_k$. In particular $m \wedge m' = -\, m' \wedge m$ for all $m, m' \in M$.

***Proof*:**
The first identity is the statement that the generators of $A^k(M)$ die in the quotient. The second is lemma 16.1.4(1) applied to the alternating map α of theorem 16.1.8, whose values are precisely the elements $m_1 \wedge \cdots \wedge m_k$. Taking $k = 2$ and σ the transposition gives the last claim, completing the proof.

Both $\mathcal{S}^k(M)$ and $\bigwedge^k(M)$ have been built as quotients of $\mathcal{T}^k(M)$. They can also be found inside it, as submodules, provided $k!$ is invertible. The comparison rests on an action of the symmetric group.

Proposition 16.1.10: The Symmetric Group Acts on Tensor Powers

Let M be an R-module and $k \geq 1$. For each $\sigma \in S_k$ there is a unique R-module homomorphism $\sigma \cdot (-)$ of $\mathcal{T}^k(M)$ with

$$\sigma \cdot (m_1 \otimes \cdots \otimes m_k) = m_{\sigma^{-1}(1)} \otimes \cdots \otimes m_{\sigma^{-1}(k)}$$

and these assemble into a left action of S_k on $\mathcal{T}^k(M)$ by R-module automorphisms.

***Proof*:**
For fixed σ the assignment $(m_1, \ldots, m_k) \mapsto m_{\sigma^{-1}(1)} \otimes \cdots \otimes m_{\sigma^{-1}(k)}$ is k-multilinear, since each argument appears in exactly one slot of the output, so theorem 15.2.11 gives the homomorphism and its uniqueness.

For the action law, evaluate on a simple tensor. The i-th slot of $\tau \cdot (m_1 \otimes \cdots \otimes m_k)$ holds $m_{\tau^{-1}(i)}$, so the i-th slot of $\sigma \cdot \big(\tau \cdot (m_1 \otimes \cdots \otimes m_k)\big)$ holds $m_{\tau^{-1}(\sigma^{-1}(i))} = m_{(\sigma\tau)^{-1}(i)}$, which is the i-th slot of $(\sigma\tau) \cdot (m_1 \otimes \cdots \otimes m_k)$. Two homomorphisms agreeing on the simple tensors are equal, so $\sigma \cdot (\tau \cdot z) = (\sigma\tau) \cdot z$ for all z. The identity permutation acts as the identity, so each σ acts invertibly, completing the proof.

The inverse in the formula is what makes the assignment a left action rather than a right one. Without it the composition law would come out reversed.

Definition 16.1.11: Symmetric and Alternating Tensors

Let M be an R-module and $k \geq 1$. A tensor $z \in \mathcal{T}^k(M)$ is

1. a *symmetric k-tensor* if $\sigma \cdot z = z$ for every $\sigma \in S_k$;
2. an *alternating k-tensor* if $\sigma \cdot z = (-1)^\sigma z$ for every $\sigma \in S_k$.

These form submodules of $\mathcal{T}^k(M)$, written $\mathcal{T}^k_{\mathrm{sym}}(M)$ and $\mathcal{T}^k_{\mathrm{alt}}(M)$, each being an intersection of kernels of R-module homomorphisms.
The *symmetrization* and *antisymmetrization* operators on $\mathcal{T}^k(M)$ are

$$\mathrm{Sym}(z) := \sum_{\sigma \in S_k} \sigma \cdot z \qquad \text{and} \qquad \mathrm{Alt}(z) := \sum_{\sigma \in S_k} (-1)^\sigma \, \sigma \cdot z$$

Proposition 16.1.12: Symmetric and Alternating Tensors When $k!$ Is Invertible

Let M be an R-module, $k \geq 1$, and suppose $k!$ is a unit in R. Then $\frac{1}{k!}\,\mathrm{Sym}$ and $\frac{1}{k!}\,\mathrm{Alt}$ are idempotent endomorphisms of $\mathcal{T}^k(M)$ with images $\mathcal{T}^k_{\mathrm{sym}}(M)$ and $\mathcal{T}^k_{\mathrm{alt}}(M)$, and they induce isomorphisms of R-modules

$$\mathcal{S}^k(M) \xrightarrow{\sim} \mathcal{T}^k_{\mathrm{sym}}(M) \qquad \text{and} \qquad \bigwedge^k(M) \xrightarrow{\sim} \mathcal{T}^k_{\mathrm{alt}}(M)$$

In particular $\mathcal{T}^k(M) = \mathcal{T}^k_{\mathrm{sym}}(M) \oplus \ker \mathrm{Sym}$, and likewise for the alternating part.

***Proof*:**
The symmetric case. Reindexing the sum shows $\tau \cdot \mathrm{Sym}(z) = \mathrm{Sym}(z)$ for every τ, since $\sigma \mapsto \tau\sigma$ permutes S_k. So Sym lands in $\mathcal{T}^k_{\mathrm{sym}}(M)$. If z is already symmetric then every term of the sum equals z, so $\mathrm{Sym}(z) = k!\, z$ and $\frac{1}{k!}\,\mathrm{Sym}$ restricts to the identity there. Hence $\frac{1}{k!}\,\mathrm{Sym}$ is idempotent with image exactly $\mathcal{T}^k_{\mathrm{sym}}(M)$, and an idempotent endomorphism splits its domain as image plus kernel.

Writing $\rho = \sigma^{-1}$, the generator $m_1 \otimes \cdots \otimes m_k - m_{\sigma(1)} \otimes \cdots \otimes m_{\sigma(k)}$ of $C^k(M)$ is $z - \rho \cdot z$ for the simple tensor z, and $\mathrm{Sym}(z - \rho \cdot z) = \mathrm{Sym}(z) - \mathrm{Sym}(z) = 0$ by the reindexing above. So $\frac{1}{k!}\,\mathrm{Sym}$ kills $C^k(M)$ and induces $\Theta\colon \mathcal{S}^k(M) \to \mathcal{T}^k_{\mathrm{sym}}(M)$.

Its inverse is the composite $\mathcal{T}^k_{\mathrm{sym}}(M) \hookrightarrow \mathcal{T}^k(M) \xrightarrow{\pi} \mathcal{S}^k(M)$. Indeed, for a simple tensor z one has $\pi(\sigma \cdot z) = \pi(z)$, since $z - \sigma \cdot z \in C^k(M)$, so

$$\pi\left(\tfrac{1}{k!}\,\mathrm{Sym}(z)\right) = \tfrac{1}{k!} \sum_{\sigma \in S_k} \pi(\sigma \cdot z) = \pi(z)$$

and both sides are homomorphisms, so this holds for all z. That is one composite. In the other order, $\frac{1}{k!}\,\mathrm{Sym}$ is the identity on $\mathcal{T}^k_{\mathrm{sym}}(M)$, which is the second. So Θ is an isomorphism.

The alternating case. The same reindexing gives $\tau \cdot \mathrm{Alt}(z) = (-1)^\tau \,\mathrm{Alt}(z)$, so Alt lands in $\mathcal{T}^k_{\mathrm{alt}}(M)$. And if z is alternating then $(-1)^\sigma \sigma \cdot z = (-1)^\sigma (-1)^\sigma z = z$ for every σ, so $\mathrm{Alt}(z) = k!\, z$. Idempotence and the splitting follow as before.

That Alt kills $A^k(M)$ needs the pairing argument. Let $z = m_1 \otimes \cdots \otimes m_k$ have $m_a = m_b$ with

$a \neq b$ and set $\tau = (a\ b)$. Then $\tau \cdot z = z$, because the two interchanged entries are equal. Pairing each σ with $\sigma\tau$ gives $(\sigma\tau)\cdot z = \sigma\cdot(\tau\cdot z) = \sigma\cdot z$ while $(-1)^{\sigma\tau} = -(-1)^{\sigma}$, so the two terms cancel and $\operatorname{Alt}(z) = 0$. Hence $\frac{1}{k!}\operatorname{Alt}$ induces a map on $\bigwedge^k(M)$.

For the inverse, let $\pi_A \colon \mathcal{T}^k(M) \to \bigwedge^k(M)$ be the quotient map. By proposition 16.1.9, $\pi_A(\sigma\cdot z) = (-1)^{\sigma}\pi_A(z)$ on simple tensors, so

$$\pi_A\left(\tfrac{1}{k!}\operatorname{Alt}(z)\right) = \tfrac{1}{k!}\sum_{\sigma\in S_k}(-1)^{\sigma}(-1)^{\sigma}\pi_A(z) = \pi_A(z)$$

using $(-1)^{\sigma}(-1)^{\sigma} = 1$. And $\frac{1}{k!}\operatorname{Alt}$ is the identity on $\mathcal{T}^k_{\mathrm{alt}}(M)$. So the two maps are mutually inverse, as we sought to show.

Defining an invariant element by averaging over a finite group, which is what $\frac{1}{k!}\operatorname{Sym}$ does, is a technique that recurs whenever the order of the group is invertible in the ring. It is the mechanism behind Maschke's theorem (theorem 53.1.9), where averaging over a finite group produces an invariant complement to a subrepresentation. When $k!$ is not invertible the comparison genuinely fails, and the exercises give a witness.

Exercise 16.1.1

1. Show that $C^k(M)$ is already generated by the elements $z - \tau\cdot z$ with z a simple tensor and τ a transposition, so that symmetry of a multilinear map need only be checked on transpositions.
2. Let R have characteristic 2. Show that a k-multilinear map satisfies the sign rule of lemma 16.1.4 if and only if it is symmetric, and exhibit a symmetric trilinear map over $\mathbb{Z}/2\mathbb{Z}$ that is not alternating.
3. Show that if M is generated by fewer than k elements then $\bigwedge^k(M) = 0$.
4. Let $\varphi\colon M \to N$ be a surjection of R-modules. Show that the induced maps $\mathcal{S}^k(M) \to \mathcal{S}^k(N)$ and $\bigwedge^k(M) \to \bigwedge^k(N)$ are surjective. (Use theorem 15.2.2 on $\mathcal{T}^k$ first, then check that generators map to generators.)
5. Take $R = \mathbb{Z}$ and $M = \mathbb{Z}/2\mathbb{Z}$. Compute $\mathcal{T}^2(M)$, $\mathcal{S}^2(M)$ and $\bigwedge^2(M)$.
6. Show that $\operatorname{Alt}\circ\operatorname{Sym} = 0$ on $\mathcal{T}^k(M)$ for every $k \geq 2$, over any commutative ring.
7. Continuing the previous exercise with $R = \mathbb{Z}$ and $M = \mathbb{Z}/2\mathbb{Z}$, where $2!$ is not a unit, compute $\mathcal{T}^2_{\mathrm{alt}}(M)$ and compare it with $\bigwedge^2(M)$. Conclude that the invertibility hypothesis in proposition 16.1.12 cannot be dropped: the two modules are not merely joined by a different isomorphism, they are not isomorphic at all.

16.2 Graded Rings and Graded Modules

The tensor powers of definition 16.1.1 come with a bookkeeping device that has so far gone unused. Associativity (theorem 15.2.8) identifies $\mathcal{T}^k(M)\otimes_R\mathcal{T}^l(M)$ with $\mathcal{T}^{k+l}(M)$, so a k-tensor times an l-tensor is a $(k+l)$-tensor: the index adds. A ring carrying an index of this kind is called graded, and the three algebras of section 16.3 are all built by taking a graded ring apart and putting it back

together modulo relations that respect the index. Grading is therefore developed first, in its own right.

Definition 16.2.1: Graded Ring

A ring S is a *graded ring* if it comes with a decomposition

$$S = \bigoplus_{k \geq 0} S_k$$

of its underlying additive group into subgroups such that

$$S_k S_l \subseteq S_{k+l} \qquad \text{for all } k, l \geq 0$$

An element of S_k is *homogeneous of degree* k, and S_k is the *homogeneous component of* S *of degree* k. Every $s \in S$ has a unique expression $s = \sum_k s_k$ with $s_k \in S_k$ and all but finitely many s_k zero. The s_k are the *homogeneous components* of s.

The base ring plays no role in the definition, and the letter S is used for the graded ring throughout to keep it distinct from a ring R that may be acting. Note also that S_k is only required to be an additive subgroup: the multiplicative structure is carried entirely by the containments $S_k S_l \subseteq S_{k+l}$. What those containments force is the following.

Proposition 16.2.2: The Degree-Zero Part

Let $S = \bigoplus_{k \geq 0} S_k$ be a graded ring. Then

1. $1 \in S_0$, and S_0 is a subring of S;
2. each S_k is an S_0-module, and S is an S_0-algebra when S_0 lies in the centre of S;
3. $S_+ := \bigoplus_{k>0} S_k$ is a two-sided ideal of S, and $S/S_+ \cong S_0$ as rings.

***Proof*:**

1. Write $1 = \sum_k e_k$ with $e_k \in S_k$. For $x \in S_l$ the product $x \cdot 1 = \sum_k x e_k$ has $x e_k \in S_{l+k}$, so comparing homogeneous components of degree l on both sides of $x = x \cdot 1$ gives $x = x e_0$. Additivity extends this from homogeneous x to all of S, and the same argument on the other side gives $e_0 x = x$. So e_0 is a two-sided identity, and an identity is unique, so $1 = e_0 \in S_0$. Now $S_0 S_0 \subseteq S_0$ makes S_0 closed under multiplication, it is an additive subgroup by construction, and it contains 1. So it is a subring.

2. $S_0 S_k \subseteq S_k$ and $S_k S_0 \subseteq S_k$, so each S_k is a module over the subring S_0 on either side, and S is their direct sum. The algebra statement is definition 12.1.13, whose hypothesis is exactly that the image of S_0 is central.

3. S_+ is an additive subgroup, and for $x \in S_l$ and $y \in S_k$ with $k > 0$ one has $xy \in S_{k+l}$ with $k + l > 0$. Additivity extends this to all of S, on both sides, so S_+ is a two-sided ideal. The projection $S \to S_0$ sending s to its degree-zero component is additive, sends 1 to 1 by (1), and is multiplicative because the degree-zero component of a product st is $s_0 t_0$, every

other contribution $s_k t_l$ with $k+l=0$ and $k,l \geq 0$ being absent. Its kernel is exactly S_+, completing the proof.

Note that $S_i \subseteq S_j$ is not to be expected for $i < j$: the components are summands, not a filtration. In $R[x]$ graded by degree, $S_1 = Rx$ and $S_2 = Rx^2$ are disjoint apart from 0.

Definition 16.2.3: Graded Modules, Ideals and Homomorphisms

Let $S = \bigoplus_{k\geq 0} S_k$ and $T = \bigoplus_{k\geq 0} T_k$ be graded rings.

1. A left S-module M is *graded* if it comes with a decomposition $M = \bigoplus_{k\geq 0} M_k$ into additive subgroups with $S_k M_l \subseteq M_{k+l}$ for all k, l. Elements of M_k are *homogeneous of degree* k.
2. An ideal $I \subseteq S$ is a *graded ideal*, or a *homogeneous ideal*, if
$$I = \bigoplus_{k\geq 0} (I \cap S_k)$$
Writing $I_k := I \cap S_k$, a graded ideal is in particular a graded S-module.
3. A ring homomorphism $\varphi\colon S \to T$ is *graded* if $\varphi(S_k) \subseteq T_k$ for every k.

Example 16.2.4: Graded Rings

1. Any ring S is graded with $S_0 = S$ and $S_k = 0$ for $k > 0$. This is the *trivial* grading, and it shows the definition imposes nothing by itself.
2. For any ring R, the polynomial ring $R[x]$ is graded by degree:
$$R[x] = \bigoplus_{k\geq 0} Rx^k$$
the degree-k component being the free R-module on the single monomial x^k, and $Rx^k \cdot Rx^l \subseteq Rx^{k+l}$. It is worth being precise about what the components are, since the powers $(x)^k$ of the ideal (x) are *not* a grading: they are nested, $(x) \supseteq (x)^2 \supseteq \cdots$, so their sum is not direct.
3. More generally $R[x_1, \ldots, x_n]$ is graded with k-th component the free R-module on the monomials $x_1^{a_1} \cdots x_n^{a_n}$ with $a_1 + \cdots + a_n = k$. These are the *homogeneous polynomials* of degree k. Here $S_0 = R$, and S_+ is the ideal $(x_1, \ldots, x_n)$ of polynomials with zero constant term.
4. Let R be commutative and $I \subseteq R$ an ideal. The *Rees algebra* of R with respect to I is
$$\mathrm{Rees}_R(I) := \bigoplus_{k\geq 0} I^k = R \oplus I \oplus I^2 \oplus \cdots$$
with multiplication induced by that of R. It is graded because $I^k I^l = I^{k+l}$, so in particular $I^k I^l \subseteq I^{k+l}$. The summands are indexed copies of the ideals I^k, kept formally separate. The sum inside R would not be direct, for the same reason as in (2).[a]

[a] Rees algebras are the algebraic form of a blow-up in algebraic geometry, and are taken up alongside the Artin-Rees lemma in *Commutative Algebra* theorem 25.4.1.

Quotienting by a graded ideal is exactly the operation that keeps the grading.

Proposition 16.2.5: Quotient of a Graded Ring by a Graded Ideal

Let $S = \bigoplus_k S_k$ be a graded ring and $I \subseteq S$ a graded ideal, and write $I_k = I \cap S_k$. Then S/I is a graded ring with

$$(S/I)_k \cong S_k/I_k$$

and the quotient map $S \to S/I$ is a graded ring homomorphism.

***Proof*:**
Let $\pi\colon S \to S/I$ be the quotient map and let $(S/I)_k := \pi(S_k)$, an additive subgroup. These generate S/I additively, since π is surjective and the S_k generate S. Their sum is direct: if $\sum_k \pi(s_k) = 0$ with $s_k \in S_k$ and almost all zero, then $\sum_k s_k \in I$, so every $s_k \in I$ by definition 16.2.3(2), whence $\pi(s_k) = 0$ for each k. The containment $(S/I)_k(S/I)_l \subseteq (S/I)_{k+l}$ follows by applying π to $S_kS_l \subseteq S_{k+l}$. So $S/I = \bigoplus_k (S/I)_k$ is a graded ring, and $\pi(S_k) = (S/I)_k$ says exactly that π is graded.

For the displayed isomorphism, the restriction $\pi|_{S_k}\colon S_k \to (S/I)_k$ is a surjective homomorphism of additive groups with kernel $S_k \cap I = I_k$, so $S_k/I_k \cong (S/I)_k$ by theorem 3.1.15, completing the proof.

The same bookkeeping applies to a graded homomorphism, whose kernel and image decompose degree by degree.

Proposition 16.2.6: Kernel and Image of a Graded Homomorphism

Let $\varphi\colon S \to T$ be a graded ring homomorphism and write $\varphi_k := \varphi|_{S_k}\colon S_k \to T_k$. Then

$$\ker\varphi = \bigoplus_{k\geq 0} \ker\varphi_k \qquad \text{and} \qquad \varphi(S) = \bigoplus_{k\geq 0} \varphi(S_k)$$

so $\ker\varphi$ is a graded ideal of S and $\varphi(S)$ is a graded subring of T.

***Proof*:**
If $s \in \ker\varphi$ has homogeneous components s_k, then $\sum_k \varphi(s_k) = 0$ with $\varphi(s_k) \in T_k$, so each $\varphi(s_k) = 0$ by uniqueness of the decomposition in T. Hence $s \in \bigoplus_k \ker\varphi_k$. The reverse inclusion is clear, and the displayed equality shows $\ker\varphi$ is graded.

For the image, $\varphi(S) = \sum_k \varphi(S_k)$ because φ is additive and the S_k span S, and the sum is direct because $\varphi(S_k) \subseteq T_k$ and the T_k are independent. Closure under multiplication is $\varphi(S_k)\varphi(S_l) \subseteq \varphi(S_{k+l})$, which holds because φ is multiplicative, completing the proof.

Those two results give the last of several equivalent ways to recognize a graded ideal.

Proposition 16.2.7: Characterizing Graded Ideals

Let $S = \bigoplus_k S_k$ be a graded ring and $I \subseteq S$ an ideal. The following are equivalent.

1. I is a graded ideal.
2. For every $s \in I$, each homogeneous component of s lies in I.
3. I is generated by homogeneous elements.
4. I is the kernel of a graded ring homomorphism out of S.

***Proof*:**

(1) ⇒ (2). If $I = \bigoplus_k (I \cap S_k)$ then every $s \in I$ is a finite sum $\sum_k t_k$ with $t_k \in I \cap S_k$. That expression is also the decomposition of s into homogeneous components, which is unique, so each component $s_k = t_k$ lies in I.

(2) ⇒ (3). By (2) the set H of homogeneous elements of I is contained in I, and every $s \in I$ is the sum of its homogeneous components, all of which lie in H. So H generates I.

(3) ⇒ (1). Let I be generated by homogeneous elements h_α, say $h_\alpha \in S_{d_\alpha}$. An element $s \in I$ is a finite sum $s = \sum_\alpha a_\alpha h_\alpha$ with $a_\alpha \in S$. Decomposing each $a_\alpha = \sum_j a_{\alpha,j}$ into homogeneous components,

$$s = \sum_\alpha \sum_j a_{\alpha,j} h_\alpha$$

and each $a_{\alpha,j} h_\alpha$ is homogeneous of degree $j + d_\alpha$ and lies in I. Collecting the terms of each fixed degree therefore exhibits the homogeneous components of s as elements of I, so $s \in \bigoplus_k (I \cap S_k)$. The reverse inclusion is automatic, giving (1).

(1) ⇒ (4). By proposition 16.2.5 below, S/I is a graded ring and the quotient map is a graded homomorphism. Its kernel is I.

(4) ⇒ (2). Let $\varphi\colon S \to T$ be graded with kernel I, and let $s \in I$ have homogeneous components s_k. Then $0 = \varphi(s) = \sum_k \varphi(s_k)$ with $\varphi(s_k) \in T_k$, and the decomposition of 0 into homogeneous components of T is unique, so every $\varphi(s_k) = 0$ and every $s_k \in I$, completing the proof.

For prime ideals the grading cuts the work down: only homogeneous elements need to be tested.

Corollary 16.2.8: Prime Graded Ideals

Let S be a graded commutative ring and $I \subseteq S$ a graded ideal with $I \neq S$. Then I is prime if and only if for all *homogeneous* $f, g \in S$ with $fg \in I$, either $f \in I$ or $g \in I$.

***Proof*:**

If I is prime the condition holds, since it is a special case of the definition.

Conversely, suppose the condition holds and let $f, g \in S$ with $fg \in I$ but $f \notin I$ and $g \notin I$. By proposition 16.2.7(2) some homogeneous component of f lies outside I, and only finitely many components are nonzero, so there is a largest index a with $f_a \notin I$. Choose b likewise for g.

Consider the homogeneous component of fg in degree $a+b$, namely $\sum_{i+j=a+b} f_i g_j$. In any term

with $i > a$ one has $f_i \in I$ by maximality of a, so $f_i g_j \in I$. And in any term with $i < a$ one has $j = a + b - i > b$, so $g_j \in I$ and again $f_i g_j \in I$. Every term except $f_a g_b$ therefore lies in I. Since $fg \in I$ and I is graded, the whole degree-$(a+b)$ component lies in I by proposition 16.2.7(2), and subtracting the other terms gives $f_a g_b \in I$. As f_a and g_b are homogeneous, the hypothesis forces $f_a \in I$ or $g_b \in I$, contradicting the choice of a and b. So I is prime, completing the proof.

Finally, the operations on ideals of definition 9.4.1 preserve gradedness.

Proposition 16.2.9: Arithmetic of Homogeneous Ideals

Let S be a graded commutative ring and let $I, J \subseteq S$ be graded ideals. Then each of

$$I + J, \qquad IJ, \qquad I \cap J, \qquad \sqrt{I}$$

is a graded ideal.

***Proof*:**
Throughout, proposition 16.2.7 is used to switch between the definition and the two convenient criteria.

$I + J$ and IJ. By criterion (3) each of I and J has a generating set of homogeneous elements, say H_I and H_J. Then $H_I \cup H_J$ generates $I + J$ and consists of homogeneous elements, and the products $\{hh' | h \in H_I,\ h' \in H_J\}$ generate IJ and are homogeneous, since $S_k S_l \subseteq S_{k+l}$. Criterion (3) applies to both.

$I \cap J$. Let $s \in I \cap J$. Each homogeneous component of s lies in I by criterion (2) applied to I, and in J by the same criterion applied to J, hence in $I \cap J$. Criterion (2) gives the claim.

$\sqrt{I}$. That $\sqrt{I}$ is an ideal is proposition 9.4.3. For criterion (2), let $s \in \sqrt{I}$ and argue by induction on the number of nonzero homogeneous components of s. If that number is 0 there is nothing to prove. Otherwise let d be the largest degree with $s_d \neq 0$, and choose n with $s^n \in I$. The homogeneous component of s^n in the top degree nd is s_d^n, because every other product of n components has total degree strictly less than nd. Since $s^n \in I$ and I is graded, criterion (2) gives $s_d^n \in I$, so $s_d \in \sqrt{I}$. Then $s - s_d \in \sqrt{I}$, as $\sqrt{I}$ is an ideal, and it has one fewer nonzero homogeneous component, so the inductive hypothesis puts all of its components in $\sqrt{I}$. Those together with s_d are the components of s, completing the proof.

Exercise 16.2.1

1. Show that a graded ring S has $S_0 \neq 0$ unless $S = 0$, and give an example of a graded ring in which $S_1 = 0$ but $S_2 \neq 0$.
2. Show that an ideal of $R[x_1, \ldots, x_n]$ is graded if and only if it is generated by homogeneous polynomials, and use this to show that $(1 + x) \subseteq \mathbb{Z}[x]$ is not graded.
3. Show that $(y - x^2) \subseteq k[x, y]$ is not a graded ideal for the standard grading, while $(y,\ y - x^2)$ is. (For the second, identify the ideal.)
4. Let S be a graded ring. Show that S_+ is the unique largest graded ideal I with $I \cap S_0 = 0$, and that S is generated as an S_0-algebra by any set of homogeneous elements whose images generate S_+/S_+^2 as an S_0-module.

5. Show that a graded ideal I is radical if and only if $s_d^n \in I$ implies $s_d \in I$ for every homogeneous s_d and every $n \geq 1$.

6. Show that $I = (x^2 - y^2) \subseteq k[x, y]$ is a graded ideal that is not prime, and exhibit homogeneous $f, g \notin I$ with $fg \in I$. (By corollary 16.2.8 such a homogeneous witness must exist whenever a graded ideal fails to be prime.)

16.3 The Tensor, Symmetric and Exterior Algebras

Section 16.1 produced one module for each degree k. Adding them up produces a ring. The multiplication is concatenation of tensors, which raises the degree by exactly the amount it should, so the result is a graded ring in the sense of definition 16.2.1. And the sum acquires a universal property that the individual degrees do not have, one about homomorphisms into an algebra rather than into a module. The symmetric and exterior algebras are then quotients of it, and the last thing to check is that quotienting the whole and quotienting degree by degree agree.

Definition 16.3.1: Tensor Algebra

Let R be a commutative ring and M an R-module. The *tensor algebra* of M is the R-module

$$\mathcal{T}(M) := \bigoplus_{k \geq 0} \mathcal{T}^k(M) = R \oplus M \oplus \mathcal{T}^2(M) \oplus \cdots$$

equipped with the multiplication determined on homogeneous elements by the composite

$$\mathcal{T}^k(M) \times \mathcal{T}^l(M) \xrightarrow{\iota} \mathcal{T}^k(M) \otimes_R \mathcal{T}^l(M) \xrightarrow{\sim} \mathcal{T}^{k+l}(M)$$

where the second map is the associativity isomorphism of theorem 15.2.8 when $k, l \geq 1$, and is example 15.1.13 when $k = 0$ or $l = 0$, and extended to all of $\mathcal{T}(M)$ by additivity in each variable.

On simple tensors the multiplication is concatenation,

$$(m_1 \otimes \cdots \otimes m_i)(m'_1 \otimes \cdots \otimes m'_j) = m_1 \otimes \cdots \otimes m_i \otimes m'_1 \otimes \cdots \otimes m'_j$$

which is what makes it computable. Note that this is not the multiplication of theorem 15.2.14, which was $(a \otimes b)(a' \otimes b') = aa' \otimes bb'$ and required both factors to be algebras already. Here M is only a module, and the product of two elements of M lands not in M but one degree higher.

Theorem 16.3.2: $\mathcal{T}(M)$ is an R-algebra

Let R be a commutative ring and M an R-module.

1. $\mathcal{T}(M)$ is an associative R-algebra with identity $1 \in R = \mathcal{T}^0(M)$, and it is graded, with $\mathcal{T}^k(M)\mathcal{T}^l(M) \subseteq \mathcal{T}^{k+l}(M)$. It contains M as the homogeneous component of degree 1.
2. (universal property) For every R-algebra A and every R-module homomorphism $\varphi\colon M \to A$ there is a unique R-algebra homomorphism $\Phi\colon \mathcal{T}(M) \to A$ with $\Phi|_M = \varphi$:

$$\begin{array}{ccc} \mathcal{T}(M) & \xrightarrow{\Phi} & A \\ {\scriptstyle\iota}\uparrow & \nearrow_{\varphi} & \\ M & & \end{array}$$

***Proof*:**

1. The multiplication is R-bilinear on each pair of homogeneous components, being a composite of the R-bilinear ι with an R-module isomorphism, and it is extended biadditively, so it distributes over addition and commutes with the R-action. That is the compatibility definition 12.1.13 asks for. The containment $\mathcal{T}^k(M)\mathcal{T}^l(M) \subseteq \mathcal{T}^{k+l}(M)$ holds by construction, which is the grading.

   For associativity, both $(x, y, z) \mapsto (xy)z$ and $(x, y, z) \mapsto x(yz)$ are R-trilinear, so by theorem 15.2.11 each is determined by its values on triples of simple tensors, where both are the concatenation

   $$m_1 \otimes \cdots \otimes m_i \otimes m_1' \otimes \cdots \otimes m_j' \otimes m_1'' \otimes \cdots \otimes m_h''$$

   since concatenation of finite sequences is associative. For the identity, $1 \in R = \mathcal{T}^0(M)$ acts on $\mathcal{T}^k(M)$ through the isomorphism $R \otimes_R \mathcal{T}^k(M) \cong \mathcal{T}^k(M)$ of example 15.1.13, which is the identity map. Finally $\mathcal{T}^1(M) = M$ by definition 16.1.1.

2. Fix A and φ. For each $k \geq 1$ the map

   $$M^k \to A, \qquad (m_1, \ldots, m_k) \mapsto \varphi(m_1)\varphi(m_2)\cdots\varphi(m_k)$$

   is k-multilinear: φ is R-linear and multiplication in A is R-linear in each variable by definition 12.1.13. So theorem 15.2.11 gives a unique R-module homomorphism $\Phi_k\colon \mathcal{T}^k(M) \to A$ with $\Phi_k(m_1 \otimes \cdots \otimes m_k) = \varphi(m_1)\cdots\varphi(m_k)$. Let $\Phi_0\colon R \to A$ be the structure map of the R-algebra A, and let $\Phi := \sum_k \Phi_k$ on the direct sum, which is a well-defined R-module homomorphism because every element has only finitely many nonzero components.

   Φ is multiplicative: both $(x, y) \mapsto \Phi(xy)$ and $(x, y) \mapsto \Phi(x)\Phi(y)$ are R-bilinear, and on a pair of simple tensors both give $\varphi(m_1)\cdots\varphi(m_i)\varphi(m_1')\cdots\varphi(m_j')$, so they agree by theorem 15.1.12. It sends 1 to 1 because Φ_0 does. Restricted to $\mathcal{T}^1(M) = M$ it is φ.

   For uniqueness, $\mathcal{T}(M)$ is generated as an R-algebra by M: the simple tensors $m_1 \otimes \cdots \otimes m_k$ are products of elements of M, and they generate $\mathcal{T}^k(M)$ as an R-module by lemma 15.1.4. An R-algebra homomorphism is determined by its values on an algebra generating set, so any Φ' agreeing with φ on M equals Φ, completing the proof.

Part (2) says that $\mathcal{T}(-)$ converts modules into algebras in the freest possible way: prescribing an algebra homomorphism out of $\mathcal{T}(M)$ needs no more than prescribing a module homomorphism out of M. In categorical language $\mathcal{T}(-)$ is left adjoint to the functor forgetting the multiplication of an R-algebra, which is the same shape of statement as corollary 15.3.5. The general theory is section 64.1.

The two quotients of interest are cut out by degree-two relations. Before taking them, one compatibility has to be settled, since section 16.1 defined $\mathcal{S}^k(M)$ and $\bigwedge^k(M)$ by quotienting $\mathcal{T}^k(M)$ by a *submodule*, while the algebras are obtained by quotienting $\mathcal{T}(M)$ by an *ideal*. The two operations agree, but that is a statement to prove rather than to observe.

Lemma 16.3.3: The Defining Ideals Are Graded, Degree by Degree

Let R be a commutative ring and M an R-module. Let $\mathcal{C}(M) \subseteq \mathcal{T}(M)$ be the two-sided ideal generated by all $m \otimes m' - m' \otimes m$ with $m, m' \in M$, and let $\mathcal{A}(M) \subseteq \mathcal{T}(M)$ be the two-sided ideal generated by all $m \otimes m$ with $m \in M$. Then both are graded ideals, and for every $k \geq 0$

$$\mathcal{C}(M) \cap \mathcal{T}^k(M) = C^k(M), \qquad \mathcal{A}(M) \cap \mathcal{T}^k(M) = A^k(M)$$

where $C^k(M)$ and $A^k(M)$ are the submodules of definition 16.1.5 and definition 16.1.7.

***Proof*:**
Both ideals are generated by homogeneous elements of degree 2, so both are graded by proposition 16.2.7(3), and it remains to identify the degree-k parts. Write $\mathcal{C}(M)_k$ for $\mathcal{C}(M) \cap \mathcal{T}^k(M)$.

The symmetric case, $C^k(M) \subseteq \mathcal{C}(M)_k$. By definition $C^k(M)$ is generated by the differences $z - \sigma \cdot z$ for simple tensors z and $\sigma \in S_k$. Since adjacent transpositions generate S_k, and

$$z - (\tau_1 \cdots \tau_r) \cdot z = \sum_{j=1}^{r} \Big((\tau_{j+1} \cdots \tau_r) \cdot z - (\tau_j \tau_{j+1} \cdots \tau_r) \cdot z \Big)$$

telescopes with each summand of the form $w - \tau \cdot w$ for a simple tensor w and an adjacent transposition τ, it suffices to treat $\tau = (i\ i+1)$. There

$$z - \tau \cdot z = (m_1 \otimes \cdots \otimes m_{i-1}) \big(m_i \otimes m_{i+1} - m_{i+1} \otimes m_i \big) (m_{i+2} \otimes \cdots \otimes m_k)$$

a product in $\mathcal{T}(M)$ of an element of $\mathcal{T}^{i-1}(M)$, a generator of $\mathcal{C}(M)$, and an element of $\mathcal{T}^{k-i-1}(M)$, hence an element of $\mathcal{C}(M)$. And it is homogeneous of degree k.

The symmetric case, $\mathcal{C}(M)_k \subseteq C^k(M)$. An element of $\mathcal{C}(M)$ is a finite sum of products $x\,(m \otimes m' - m' \otimes m)\,y$ with $x, y \in \mathcal{T}(M)$. Expanding x and y into homogeneous components and then into simple tensors, and keeping only the terms of total degree k, every such term is of the form $w - \tau \cdot w$ for a simple tensor $w \in \mathcal{T}^k(M)$ and an adjacent transposition τ, by the display above read backwards. Each lies in $C^k(M)$, and $C^k(M)$ is a submodule, so the sum does too.

The alternating case. The inclusion $\mathcal{A}(M)_k \supseteq A^k(M)$ needs slightly more, since a generator of $A^k(M)$ is a simple tensor whose repeated entries need not be adjacent. Note first that for $u, v \in M$,

$$u \otimes v + v \otimes u = (u+v) \otimes (u+v) - u \otimes u - v \otimes v \in \mathcal{A}(M)$$

so interchanging two adjacent factors of a simple tensor changes it by an element of $\mathcal{A}(M)$, up to sign. Given $z = m_1 \otimes \cdots \otimes m_k$ with $m_a = m_b$ and $a < b$, repeatedly interchanging adjacent factors moves m_b into position $a+1$, so that $z \equiv \pm z'$ modulo $\mathcal{A}(M)$, where z' is a simple tensor with two equal adjacent entries. Then z' factors as a product of an element of $\mathcal{T}^{a-1}(M)$, the generator $m_a \otimes m_a$, and an element of $\mathcal{T}^{k-a-1}(M)$, so $z' \in \mathcal{A}(M)$ and hence $z \in \mathcal{A}(M)$. Being homogeneous of degree k, it lies in $\mathcal{A}(M)_k$.

The reverse inclusion $\mathcal{A}(M)_k \subseteq A^k(M)$ follows as in the symmetric case: the degree-k part of a product $x\,(m \otimes m)\,y$ expands into simple tensors each having two equal adjacent entries, and those are generators of $A^k(M)$, completing the proof.

Corollary 16.3.4: The Quotients Are Graded

With the notation above, $\mathcal{T}(M)/\mathcal{C}(M)$ and $\mathcal{T}(M)/\mathcal{A}(M)$ are graded rings, and their homogeneous components of degree k are $\mathcal{S}^k(M)$ and $\bigwedge^k(M)$ respectively.

***Proof*:**
By lemma 16.3.3 both ideals are graded, so proposition 16.2.5 applies and gives graded quotients with degree-k component $\mathcal{T}^k(M)/(\mathcal{C}(M) \cap \mathcal{T}^k(M))$, which is $\mathcal{T}^k(M)/C^k(M) = \mathcal{S}^k(M)$ by the same lemma and definition 16.1.5. The alternating case is identical, completing the proof.

Definition 16.3.5: Symmetric Algebra

The *symmetric algebra* of an R-module M is the quotient R-algebra

$$\mathcal{S}(M) := \mathcal{T}(M)/\mathcal{C}(M)$$

where $\mathcal{C}(M)$ is the two-sided ideal generated by the elements $m \otimes m' - m' \otimes m$ for $m, m' \in M$. By corollary 16.3.4 it is graded with $\mathcal{S}(M)_k = \mathcal{S}^k(M)$, and the product of the images of $m_1, \ldots, m_k$ is written $m_1 m_2 \cdots m_k$.

Theorem 16.3.6: The Symmetric Algebra Is the Free Commutative Algebra

Let R be a commutative ring and M an R-module. Then $\mathcal{S}(M)$ is a commutative R-algebra, and for every *commutative* R-algebra A and every R-module homomorphism $\varphi\colon M \to A$ there is a unique R-algebra homomorphism $\Phi\colon \mathcal{S}(M) \to A$ restricting to φ on $M = \mathcal{S}^1(M)$.

***Proof*:**
The algebra $\mathcal{S}(M)$ is generated by the image of M, since $\mathcal{T}(M)$ is generated by M and the quotient map is surjective. The images of any two elements of M commute, because $m \otimes m' - m' \otimes m \in \mathcal{C}(M)$. An associative algebra generated by a set of pairwise commuting elements is commutative: the set of elements commuting with everything in the generating set is a subalgebra, so it is the whole algebra, and then the same argument applied a second time gives commutativity outright. So $\mathcal{S}(M)$ is commutative.

Let A be commutative and $\varphi\colon M \to A$ an R-module homomorphism. By theorem 16.3.2 there

is a unique R-algebra homomorphism $\Psi\colon \mathcal{T}(M) \to A$ with $\Psi|_M = \varphi$. On a generator of $\mathcal{C}(M)$,

$$\Psi(m \otimes m' - m' \otimes m) = \varphi(m)\varphi(m') - \varphi(m')\varphi(m) = 0$$

because A is commutative. An algebra homomorphism vanishing on a set of generators of a two-sided ideal vanishes on the ideal, so $\mathcal{C}(M) \subseteq \ker \Psi$ and Ψ factors through $\mathcal{S}(M)$, giving Φ. Uniqueness holds because $\mathcal{S}(M)$ is generated as an R-algebra by the image of M, as we sought to show.

Definition 16.3.7: Exterior Algebra

The *exterior algebra* of an R-module M is the quotient R-algebra

$$\bigwedge(M) := \mathcal{T}(M)/\mathcal{A}(M)$$

where $\mathcal{A}(M)$ is the two-sided ideal generated by the elements $m \otimes m$ for $m \in M$. By corollary 16.3.4 it is graded with $\bigwedge(M)_k = \bigwedge^k(M)$, and the image of $m_1 \otimes \cdots \otimes m_k$ is written $m_1 \wedge \cdots \wedge m_k$.

Proposition 16.3.8: The Exterior Algebra Is the Free Algebra on Squares Zero

Let R be a commutative ring and M an R-module. For every R-algebra A and every R-module homomorphism $\varphi\colon M \to A$ satisfying $\varphi(m)^2 = 0$ for all $m \in M$, there is a unique R-algebra homomorphism $\Phi\colon \bigwedge(M) \to A$ restricting to φ on $M = \bigwedge^1(M)$.

***Proof*:**
As in theorem 16.3.6, theorem 16.3.2 gives $\Psi\colon \mathcal{T}(M) \to A$ with $\Psi|_M = \varphi$, and $\Psi(m \otimes m) = \varphi(m)^2 = 0$ kills every generator of $\mathcal{A}(M)$, hence the ideal. The induced Φ is unique because $\bigwedge(M)$ is generated as an R-algebra by the image of M, completing the proof.

The wedge product is not commutative, and it is not anticommutative either. The sign depends on the degrees. Proposition 16.1.9 gave the rule for elements of degree 1, and the general rule follows from it.

Proposition 16.3.9: Graded Commutativity of the Exterior Algebra

Let $a \in \bigwedge^p(M)$ and $b \in \bigwedge^q(M)$. Then

$$a \wedge b = (-1)^{pq}\, b \wedge a$$

In particular elements of odd degree anticommute and elements of even degree are central among homogeneous elements; the identity $ab = -ba$ fails as soon as one of the two degrees is even.

***Proof*:**
Both $(a,b) \mapsto a \wedge b$ and $(a,b) \mapsto (-1)^{pq} b \wedge a$ are R-bilinear on $\bigwedge^p(M) \times \bigwedge^q(M)$, so by theorem 15.1.12 it suffices to compare them on pairs of products of degree-one elements, which generate each factor. Take $a = m_1 \wedge \cdots \wedge m_p$ and $b = m'_1 \wedge \cdots \wedge m'_q$. Moving m'_1 leftwards past each of $m_1, \ldots, m_p$ in turn costs a factor of -1 each time by proposition 16.1.9, so p sign changes. Doing this for each of the q elements of b in turn gives $(-1)^{pq}$ in total and rearranges $a \wedge b$ into $b \wedge a$. Hence $a \wedge b = (-1)^{pq} b \wedge a$.

For the last sentence, take $p = q = 1$ to get $m \wedge m' = -m' \wedge m$, and $p = 2$, $q = 1$ to get $a \wedge m = m \wedge a$, which is not $-m \wedge a$ unless $2a \wedge m = 0$, completing the proof.

Example 16.3.10: Tensor Algebras

1. Let $R = \mathbb{Z}$ and $M = \mathbb{Q}/\mathbb{Z}$. Then $(\mathbb{Q}/\mathbb{Z}) \otimes_{\mathbb{Z}} (\mathbb{Q}/\mathbb{Z}) = 0$ by the third exercise of section 15.1, so $\mathcal{T}^k(M) = 0$ for every $k \geq 2$ and

$$\mathcal{T}(\mathbb{Q}/\mathbb{Z}) = \mathbb{Z} \oplus \mathbb{Q}/\mathbb{Z}$$

   Addition is componentwise, and the multiplication is

$$(r, \overline{p})(s, \overline{q}) = (rs,\ r\overline{q} + s\overline{p})$$

   since the product of two degree-one elements lands in $\mathcal{T}^2 = 0$. This is the *square-zero extension* of $\mathbb{Z}$ by $\mathbb{Q}/\mathbb{Z}$: the degree-one part is an ideal whose square vanishes.

2. Let $R = \mathbb{Z}$ and $M = \mathbb{Z}/n\mathbb{Z}$. Then $(\mathbb{Z}/n\mathbb{Z}) \otimes_{\mathbb{Z}} (\mathbb{Z}/n\mathbb{Z}) \cong \mathbb{Z}/n\mathbb{Z}$ by proposition 15.2.13, and inductively $\mathcal{T}^k(M) \cong \mathbb{Z}/n\mathbb{Z}$ for every $k \geq 1$, so

$$\mathcal{T}(\mathbb{Z}/n\mathbb{Z}) = \mathbb{Z} \oplus (\mathbb{Z}/n\mathbb{Z}) \oplus (\mathbb{Z}/n\mathbb{Z}) \oplus \cdots \cong \mathbb{Z}[x]/(nx)$$

   the isomorphism sending the degree-k generator to x^k. The relation $nx = 0$ records that the degree-one part is killed by n, and every higher degree inherits it.

3. Take $M = \mathbb{Q}$ as a module over itself. Then $\mathcal{T}^k(\mathbb{Q}) \cong \mathbb{Q}$ for every k by example 15.1.13, so $\mathcal{T}(\mathbb{Q}) \cong \mathbb{Q}[x]$ as graded $\mathbb{Q}$-algebras. Here the tensor algebra happens to be commutative, because M has rank one. For a module of rank at least two it never is, as section 16.4 will show.

Exercise 16.3.1

1. Show that $\mathcal{T}(M)$ is commutative if and only if $\mathcal{S}(M) = \mathcal{T}(M)$, and that this happens if and only if $m \otimes m' = m' \otimes m$ for all $m, m' \in M$.
2. Show that $\mathcal{S}(M)$ satisfies the universal property of theorem 16.3.6 with respect to R-algebra homomorphisms into non-commutative algebras as well, provided the image of M is required to consist of pairwise commuting elements.
3. Let $I \subseteq \mathcal{T}(M)$ be the two-sided ideal generated by $\mathcal{T}^{\geq d}(M) := \bigoplus_{k \geq d} \mathcal{T}^k(M)$ for some $d \geq 1$. Show that $I = \mathcal{T}^{\geq d}(M)$, that it is graded, and identify the quotient $\mathcal{T}(M)/I$ as an R-module.

4. Show that $\bigwedge(M)$ is commutative when $2 = 0$ in R, and give an example over $\mathbb{Z}$ where it is not. (For the example, use the determinant to produce an alternating bilinear map on $\mathbb{Z}^2$ and deduce that $e_1 \wedge e_2$ has infinite order.)

5. Let $\varphi\colon M \to N$ be an R-module homomorphism. Show that it induces graded R-algebra homomorphisms $\mathcal{T}(\varphi)$, $\mathcal{S}(\varphi)$ and $\bigwedge(\varphi)$ between the corresponding algebras, and that each is surjective when φ is.

6. Show that $\mathcal{S}(M \oplus N) \cong \mathcal{S}(M) \otimes_R \mathcal{S}(N)$ as R-algebras, using theorem 16.3.6 together with theorem 15.2.17, which identifies the right-hand side as the coproduct of commutative R-algebras.

16.4 Bases, Ranks and the Determinant

Nothing so far has required M to be free. When it is, all three graded algebras become computable: a basis of M determines a basis of each homogeneous component, and the ranks are the three counts one would guess from thinking of the components as words, unordered words, and sets. The exterior case then delivers the determinant, which reappears not as the defining sum of definition 13.4.5 but as the action of an endomorphism on a rank-one module.

Theorem 16.4.1: Bases of the Tensor Powers

Let R be a commutative ring and let M be a free R-module with basis $\{e_i\}_{i \in I}$. Then $\mathcal{T}^k(M)$ is free with basis

$$\left\{ e_{i_1} \otimes e_{i_2} \otimes \cdots \otimes e_{i_k} \;\middle|\; (i_1, \ldots, i_k) \in I^k \right\}$$

indexed by all k-tuples. If I is finite of size n, then $\mathcal{T}^k(M)$ is free of rank n^k.

***Proof*:**
Induction on k. For $k = 0$ and $k = 1$ the claim is $\mathcal{T}^0(M) = R$ and $\mathcal{T}^1(M) = M$. For the inductive step, $\mathcal{T}^k(M) = \mathcal{T}^{k-1}(M) \otimes_R M$ by definition 16.1.1, and $\mathcal{T}^{k-1}(M)$ is free on the $(k-1)$-tuples by hypothesis, so corollary 15.2.6 makes $\mathcal{T}^k(M)$ free on the products of a basis element of each factor, which are exactly the k-tuples. The rank count is $|I^k| = n^k$, completing the proof.

In particular $\mathcal{T}(M)$ is the free associative R-algebra on the set $\{e_i\}$: its elements are the R-linear combinations of words in the e_i, multiplied by concatenation. For $|I| \geq 2$ it is not commutative, since $e_1 \otimes e_2$ and $e_2 \otimes e_1$ are distinct basis elements, which settles the question raised in example 16.3.10(3).

The symmetric algebra is the polynomial ring, and it is quickest to identify the whole algebra at once and read off the components afterwards.

Theorem 16.4.2: The Symmetric Algebra of a Free Module

Let R be a commutative ring and M free with basis $e_1, \dots, e_n$. Then there is an isomorphism of graded R-algebras

$$\mathcal{S}(M) \;\cong\; R[x_1, \dots, x_n]$$

carrying e_i to x_i. Consequently $\mathcal{S}^k(M)$ is free with basis the monomials

$$e_{i_1} e_{i_2} \cdots e_{i_k}, \qquad 1 \le i_1 \le i_2 \le \cdots \le i_k \le n$$

and has rank $\binom{n+k-1}{k}$.

***Proof*:**
The polynomial ring is a commutative R-algebra, so the R-module homomorphism $M \to R[x_1, \dots, x_n]$ sending e_i to x_i induces, by theorem 16.3.6, an R-algebra homomorphism

$$\Phi \colon \mathcal{S}(M) \longrightarrow R[x_1, \dots, x_n], \qquad \Phi(e_i) = x_i$$

Conversely the universal property of polynomial rings (theorem 9.2.4) gives an R-algebra homomorphism $\Psi \colon R[x_1, \dots, x_n] \to \mathcal{S}(M)$ with $\Psi(x_i) = e_i$, since $\mathcal{S}(M)$ is commutative by theorem 16.3.6.

Each composite is an R-algebra endomorphism fixing a set of algebra generators, hence the identity: $\mathcal{S}(M)$ is generated by the image of M, and $R[x_1, \dots, x_n]$ by the x_i. So Φ is an isomorphism. It is graded because it sends the degree-one generators e_i to the degree-one generators x_i and both algebras are generated in degree one, so it carries a product of k generators to a product of k generators.

Restricting to degree k, $\mathcal{S}^k(M) = \mathcal{S}(M)_k$ by corollary 16.3.4, and the degree-k component of $R[x_1, \dots, x_n]$ is free on the monomials of total degree k (example 16.2.4(3)). Their preimages are the products $e_{i_1} \cdots e_{i_k}$ with indices weakly increasing, one for each monomial. Counting monomials of degree k in n variables is the standard problem of distributing k identical items into n labelled boxes, whose answer is $\binom{n+k-1}{k}$, completing the proof.

The exterior powers need a separate argument, because there is no ambient ring to compare against. Spanning is immediate. Independence is produced by exhibiting, for each proposed basis element, an alternating map that detects it. Those maps are minors, and the fact that a determinant is alternating is proposition 13.4.6. There is no circularity: det is the sum of definition 13.4.5, defined without any reference to exterior algebra, and it is only in theorem 16.4.7 below that the two are identified.

Theorem 16.4.3: Bases of the Exterior Powers

Let R be a commutative ring and M free with basis $e_1, \dots, e_n$. Then $\bigwedge^k(M)$ is free with basis

$$\{\, e_{i_1} \wedge e_{i_2} \wedge \cdots \wedge e_{i_k} \mid 1 \le i_1 < i_2 < \cdots < i_k \le n \,\}$$

so it has rank $\binom{n}{k}$. In particular $\bigwedge^k(M) = 0$ for $k > n$, and $\bigwedge^n(M)$ is free of rank one on $e_1 \wedge \cdots \wedge e_n$. The whole exterior algebra $\bigwedge(M)$ is then free of rank 2^n.

***Proof*:**

Spanning. By theorem 16.4.1 the tensors $e_{i_1} \otimes \cdots \otimes e_{i_k}$ span $\mathcal{T}^k(M)$, so their images span $\bigwedge^k(M)$. If two indices coincide the image is 0 by proposition 16.1.9. Otherwise the same proposition rearranges the factors into strictly increasing order up to a sign. So the displayed set spans.

Independence. Fix a strictly increasing $I = (i_1 < \cdots < i_k)$ and define

$$\varphi_I \colon M^k \to R, \qquad \varphi_I(v_1, \ldots, v_k) = \det\Big(\big(v_j\big)_{i_a}\Big)_{1 \le a,j \le k}$$

the determinant of the $k \times k$ matrix whose (a, j) entry is the i_a-th coordinate of v_j in the basis $e_1, \ldots, e_n$. Each coordinate is R-linear in v_j, and the determinant is R-linear in each column by proposition 13.4.6(3), so φ_I is k-multilinear. And if $v_j = v_{j'}$ for $j \neq j'$ then the matrix has two equal columns, so φ_I vanishes by proposition 13.4.6(4). Thus φ_I is alternating, and theorem 16.1.8 induces $\overline{\varphi_I} \colon \bigwedge^k(M) \to R$.

Evaluate $\overline{\varphi_I}$ on a proposed basis element $e_J = e_{j_1} \wedge \cdots \wedge e_{j_k}$ with J strictly increasing. The matrix in question has (a, b) entry δ_{i_a, j_b}. If $I = J$ it is the identity matrix and the determinant is 1 by proposition 13.4.6(1). If $I \neq J$ then, both being strictly increasing k-tuples, some i_a lies outside J, and then row a is zero, so the determinant is 0. Hence $\overline{\varphi_I}(e_J) = \delta_{IJ}$.

Now suppose $\sum_J c_J e_J = 0$ is a relation among the proposed basis elements, with $c_J \in R$. Applying $\overline{\varphi_I}$ gives $c_I = 0$ for every I. So the set is independent, and with spanning it is a basis.

Counts. The strictly increasing k-tuples from $\{1, \ldots, n\}$ are the k-element subsets, of which there are $\binom{n}{k}$. For $k > n$ there are none, so $\bigwedge^k(M) = 0$, and for $k = n$ there is exactly one. Summing over k gives $\sum_{k=0}^{n} \binom{n}{k} = 2^n$, completing the proof.

Example 16.4.4: Exterior Algebras of Small Vector Spaces
Let F be a field and V an F-vector space.

1. If $\dim V = 1$ with basis v, then theorem 16.4.3 gives $\bigwedge^0(V) = F$, $\bigwedge^1(V) = V$, and $\bigwedge^i(V) = 0$ for every $i \geq 2$, since there are no strictly increasing i-tuples from a one-element set. So

$$\bigwedge(V) = F \oplus V$$

   with every product of two elements of V equal to zero.

2. Now let $\dim V = 2$ with basis v, v'. The only strictly increasing pairs give $\bigwedge^2(V) = F\,(v \wedge v')$, and $\bigwedge^i(V) = 0$ for $i \geq 3$. Computing a general product of two vectors,

$$\begin{aligned}(av + bv') \wedge (cv + dv') &= ac\,(v \wedge v) + ad\,(v \wedge v') + bc\,(v' \wedge v) + bd\,(v' \wedge v') \\ &= (ad - bc)\, v \wedge v'\end{aligned}$$

   using $v \wedge v = v' \wedge v' = 0$ and $v' \wedge v = -v \wedge v'$. The coefficient is the determinant of the matrix with those columns, which is theorem 16.4.7 in the case $n = 2$.

3. If $\dim V = 3$ with basis $\mathbf{e}_1, \mathbf{e}_2, \mathbf{e}_3$, then $\bigwedge^2(V)$ has rank $\binom{3}{2} = 3$, the same as V itself, and

$$v \wedge w = (v_1 w_2 - v_2 w_1)(\mathbf{e}_1 \wedge \mathbf{e}_2) + (v_2 w_3 - v_3 w_2)(\mathbf{e}_2 \wedge \mathbf{e}_3) + (v_1 w_3 - v_3 w_1)(\mathbf{e}_1 \wedge \mathbf{e}_3)$$

Identifying the basis of $\bigwedge^2(V)$ with that of V turns $\wedge$ into the cross product of vector calculus. The coincidence is exactly $\binom{3}{2} = 3$ and happens in no other dimension, which is why the cross product is a three-dimensional phenomenon.

4. Let $R = \mathbb{Z}[x, y]$ and $I = (x, y)$, both regarded as R-modules. The inclusion $\varphi\colon I \hookrightarrow R$ induces $\bigwedge^2(\varphi)\colon \bigwedge^2(I) \to \bigwedge^2(R)$. Now R is free of rank one, so $\bigwedge^2(R) = 0$ by theorem 16.4.3, while $x \wedge y \neq 0$ in $\bigwedge^2(I)$. For the latter, every $f \in I$ has zero constant term, so its coefficients f_x and f_y of x and y are well defined. The map $(f, g) \mapsto f_x g_y - f_y g_x$ into $R/I = \mathbb{Z}$ is R-bilinear, because multiplying f by $h \in R$ scales both coefficients by $h(0, 0)$, and it is alternating. So theorem 16.1.8 induces $\bigwedge^2(I) \to \mathbb{Z}$ sending $x \wedge y$ to 1. Hence $\bigwedge^2(\varphi)$ is not injective even though φ is: the exterior power of an injection need not be an injection, which is the same failure of exactness recorded for $\otimes$ in section 15.5.

Exterior powers turn direct sums into a graded tensor product, in the same way symmetric powers turn them into an ordinary one. The formula below is what makes the exterior algebra computable on a module built from simpler pieces, and it is the tool behind the fact that a stably free module of rank one is free.

Theorem 16.4.5: Exterior Powers of a Direct Sum

Let R be a commutative ring and M, N two R-modules. Then for every $k \geq 0$ there is an isomorphism of R-modules

$$\bigwedge^k(M \oplus N) \;\cong\; \bigoplus_{i+j=k} \bigwedge^i(M) \otimes_R \bigwedge^j(N)$$

natural in M and N, carrying $\alpha \otimes \beta$ to $\alpha \wedge \beta$ when $\bigwedge M$ and $\bigwedge N$ are identified with their images in $\bigwedge(M \oplus N)$ under the maps induced by the inclusions of M and N into $M \oplus N$.

***Proof*:**

Step 1: a twisted product on the tensor product. Put $T = \bigwedge(M) \otimes_R \bigwedge(N)$, graded by total degree, so that T_k is the right-hand side. Define a multiplication on homogeneous elements by

$$(\alpha \otimes \beta) \cdot (\alpha' \otimes \beta') = (-1)^{\deg \beta \, \deg \alpha'} \, (\alpha \wedge \alpha') \otimes (\beta \wedge \beta')$$

and extend bilinearly. This is well defined, both wedge products being bilinear, and it is associative: comparing the two bracketings of a triple product, each produces $(\alpha \wedge \alpha' \wedge \alpha'') \otimes (\beta \wedge \beta' \wedge \beta'')$ with sign exponent $\deg\beta(\deg\alpha' + \deg\alpha'') + \deg\beta' \deg\alpha''$. The element $1 \otimes 1$ is a unit, so T is an R-algebra.

Step 2: a map out of $\bigwedge(M \oplus N)$. Consider the R-module map $\varphi\colon M \oplus N \to T$ sending (m, n) to $m \otimes 1 + 1 \otimes n$, landing in degree one. Then

$$\varphi(m, n)^2 = (m \wedge m) \otimes 1 + m \otimes n + (-1)^{1 \cdot 1} m \otimes n + 1 \otimes (n \wedge n) = 0$$

the two middle terms coming from $(m \otimes 1)(1 \otimes n)$ and $(1 \otimes n)(m \otimes 1)$ with signs $(-1)^0$ and $(-1)^1$, and the outer terms vanishing since $v \wedge v = 0$. So proposition 16.3.8 gives a unique R-algebra map $\Phi\colon \bigwedge(M \oplus N) \to T$ restricting to φ.

Step 3: a map back. The inclusions $M \hookrightarrow M \oplus N$ and $N \hookrightarrow M \oplus N$ induce algebra maps $\iota_M\colon \bigwedge M \to \bigwedge(M \oplus N)$ and ι_N, again by proposition 16.3.8, since the composites $M \to \bigwedge(M \oplus N)$

and $N \to \bigwedge(M \oplus N)$ square to zero. The assignment $(\alpha, \beta) \mapsto \iota_M(\alpha) \wedge \iota_N(\beta)$ is R-bilinear, hence induces $\Psi \colon T \to \bigwedge(M \oplus N)$ on the tensor product, and Ψ respects the twisted multiplication: moving $\iota_N(\beta)$ past $\iota_M(\alpha')$ costs exactly $(-1)^{\deg \beta \deg \alpha'}$ by proposition 16.3.9.

Step 4: the two composites are the identity. Both $\Psi \circ \Phi$ and $\Phi \circ \Psi$ are algebra maps, and on degree-one elements they are the identity: $\Psi(\Phi(m,n)) = \Psi(m \otimes 1) + \Psi(1 \otimes n) = m + n = (m,n)$, and similarly in the other direction. Since $\bigwedge(M \oplus N)$ is generated as an algebra by its degree-one part, the uniqueness clause of proposition 16.3.8 makes $\Psi \circ \Phi$ the identity. And T is generated by the elements $m \otimes 1$ and $1 \otimes n$, which gives the other. Both maps preserve total degree, so restricting to degree k gives the displayed isomorphism, as we sought to show.

Step 5: naturality. Let $u \colon M \to M'$ and $v \colon N \to N'$ be R-module maps, not necessarily isomorphisms. Naturality asserts that the square

$$\begin{array}{ccc} \bigoplus_{i+j=k} \bigwedge^i(M) \otimes_R \bigwedge^j(N) & \longrightarrow & \bigwedge^k(M \oplus N) \\ \downarrow & & \downarrow \\ \bigoplus_{i+j=k} \bigwedge^i(M') \otimes_R \bigwedge^j(N') & \longrightarrow & \bigwedge^k(M' \oplus N') \end{array}$$

commutes, the horizontal maps being $\alpha \otimes \beta \mapsto \alpha \wedge \beta$ and the vertical ones $\bigoplus_{i+j=k} \bigwedge^i(u) \otimes \bigwedge^j(v)$ and $\bigwedge^k(u \oplus v)$. Both composites are R-linear, so it is enough to check them on elements $\alpha \otimes \beta$ with $\alpha = m_1 \wedge \cdots \wedge m_i$ and $\beta = n_1 \wedge \cdots \wedge n_j$ decomposable, since these generate the left-hand module. Going right then down sends $\alpha \otimes \beta$ to $\bigwedge^k(u \oplus v)\big(m_1 \wedge \cdots \wedge m_i \wedge n_1 \wedge \cdots \wedge n_j\big) = u(m_1) \wedge \cdots \wedge u(m_i) \wedge v(n_1) \wedge \cdots \wedge v(n_j)$, and going down then right sends it to $\big(u(m_1) \wedge \cdots \wedge u(m_i)\big) \wedge \big(v(n_1) \wedge \cdots \wedge v(n_j)\big)$, which is the same element. So the square commutes.

Corollary 16.4.6: A Stably Free Module of Rank One Is Free

Let R be a commutative ring and P a finitely generated projective R-module with $P_{\mathfrak{p}} \cong R_{\mathfrak{p}}$ for every prime $\mathfrak{p}$. If $P \oplus R^n \cong R^{n+1}$ for some $n \geq 0$, then $P \cong R$.

***Proof*:**

First, $\bigwedge^i(P) = 0$ for $i \geq 2$. Exterior powers are quotients of tensor powers, so they commute with localization. Hence $\big(\bigwedge^i P\big)_{\mathfrak{p}} \cong \bigwedge^i(P_{\mathfrak{p}}) \cong \bigwedge^i(R_{\mathfrak{p}})$, which vanishes for $i \geq 2$ by theorem 16.4.3. A module vanishing at every prime is zero.

Now apply theorem 16.4.5 with $M = P$ and $N = R^n$ in degree $n+1$. The summand indexed by (i,j) vanishes unless $i \leq 1$ and $j \leq n$, the latter by theorem 16.4.3. Since $i + j = n + 1$, the only survivor is $(i,j) = (1,n)$. Hence

$$R \cong \bigwedge^{n+1}(R^{n+1}) \cong \bigwedge^{n+1}(P \oplus R^n) \cong \bigwedge^1(P) \otimes_R \bigwedge^n(R^n) \cong P$$

using theorem 16.4.3 for the two free top powers, as we sought to show.

The top exterior power of a free module of rank n is free of rank one, so an endomorphism of M acts on it by multiplication by a scalar. That scalar is the determinant, and this is the basis-free description of it.

Theorem 16.4.7: The Determinant as the Top Exterior Power

Let R be a commutative ring, let M be free of rank n, and let $\varphi\colon M \to M$ be an R-module homomorphism with matrix A with respect to some basis. Then

$$\bigwedge^n(\varphi)\colon \bigwedge^n(M) \to \bigwedge^n(M)$$

is multiplication by $\det(A)$. Consequently $\det(A)$ does not depend on the chosen basis, and for endomorphisms φ, ψ of M,

$$\det(\varphi \circ \psi) = \det(\varphi)\det(\psi)$$

***Proof*:**
Let $e_1, \dots, e_n$ be the basis and $A = (a_{ij})$, so $\varphi(e_j) = \sum_i a_{ij} e_i$. By theorem 16.4.3 the module $\bigwedge^n(M)$ is free of rank one on $\omega := e_1 \wedge \cdots \wedge e_n$, so it suffices to compute $\bigwedge^n(\varphi)(\omega) = \varphi(e_1) \wedge \cdots \wedge \varphi(e_n)$.

Expanding each factor and using multilinearity of the wedge,

$$\varphi(e_1) \wedge \cdots \wedge \varphi(e_n) = \sum_f \left(\prod_{j=1}^{n} a_{f(j)\,j} \right) e_{f(1)} \wedge \cdots \wedge e_{f(n)}$$

the sum running over all functions $f\colon \{1, \dots, n\} \to \{1, \dots, n\}$. If f is not injective then two factors coincide and the wedge vanishes by proposition 16.1.9. An injective self-map of a finite set is a permutation, so only $f = \sigma \in S_n$ contributes, and there $e_{\sigma(1)} \wedge \cdots \wedge e_{\sigma(n)} = (-1)^\sigma \omega$ by the same proposition. Therefore

$$\bigwedge^n(\varphi)(\omega) = \left(\sum_{\sigma \in S_n} (-1)^\sigma \prod_{j=1}^{n} a_{\sigma(j)\,j} \right) \omega = \det(A^t)\,\omega = \det(A)\,\omega$$

the last step by proposition 13.4.6(2). Since $\bigwedge^n(\varphi)$ is defined from φ alone, with no basis involved, the scalar it multiplies by is an invariant of φ. So any two bases give matrices with the same determinant.

Finally $\bigwedge^n$ is functorial by theorem 15.2.2, so $\bigwedge^n(\varphi \circ \psi) = \bigwedge^n(\varphi) \circ \bigwedge^n(\psi)$, and composing two multiplications by scalars multiplies the scalars, completing the proof.

The multiplicativity just obtained is proposition 13.4.7 again, now with a reason attached rather than a computation: determinants multiply because $\bigwedge^n$ is a functor into rank-one modules, and endomorphisms of a rank-one free module compose by multiplying their scalars. The Leibniz sum of definition 13.4.5 is what the scalar looks like once a basis is fixed.

Corollary 16.4.8: Invertibility and the Top Exterior Power

Let M be free of rank n over a commutative ring R and φ an endomorphism of M. Then φ is an isomorphism if and only if $\det(\varphi)$ is a unit of R.

***Proof*:**
If φ is an isomorphism with inverse ψ, then $\det(\varphi)\det(\psi) = \det(\mathrm{id}_M) = 1$ by theorem 16.4.7 and proposition 13.4.6(1), so $\det(\varphi)$ is a unit. The converse is proposition 13.4.12(1) applied to the matrix of φ, completing the proof.

Exercise 16.4.1

1. Let M be free of rank n and let $v_1, \dots, v_k \in M$ be linearly dependent. Show that $v_1 \wedge \cdots \wedge v_k = 0$ in $\bigwedge^k(M)$.
2. Let F be a field with $-1 \neq 1$ and V a finite-dimensional F-vector space. Show that $V \otimes_F V \cong \mathcal{S}^2(V) \oplus \bigwedge^2(V)$, and check the dimensions against theorem 16.4.2 and theorem 16.4.3.
3. Verify that $\mathcal{T}^k$, $\mathcal{S}^k$ and $\bigwedge^k$ of a free module of rank n have ranks n^k, $\binom{n+k-1}{k}$ and $\binom{n}{k}$, and show that for $k = 2$ the last two add up to the first. Then show the analogous identity fails for $k = 3$ by computing all three ranks at $n = 2$.
4. Let M be free of rank n and φ an endomorphism. Show that $\bigwedge^k(\varphi)$ acts on the basis of theorem 16.4.3 by the $k \times k$ minors of the matrix of φ, and deduce that φ has rank less than k if and only if $\bigwedge^k(\varphi) = 0$ when R is a field.
5. Let M be free of finite rank n. Show that $\bigwedge(M)$ is finitely generated as an R-module, of rank 2^n, while $\mathcal{S}(M)$ is not finitely generated as an R-module unless $M = 0$.
6. Show that theorem 16.4.3 needs freeness. Take $R = \mathbb{Z}$ and $M = \mathbb{Z}/2\mathbb{Z} \oplus \mathbb{Z}/2\mathbb{Z}$, compute $\mathcal{T}^2(M)$ using theorem 15.2.3, identify the submodule $A^2(M)$, and conclude that $\bigwedge^2(M) \cong \mathbb{Z}/2\mathbb{Z}$. Compare with what $\binom{2}{2} = 1$ would predict for a free module of rank 2.

16.5⋆ The Koszul Complex

⋆ *Optional. This section is an aside; nothing later in the book depends on it.*

The exterior powers of a free module assemble into a complex, and when the ring elements defining it are well enough behaved that complex is exact. The result is the standard source of free resolutions in commutative algebra, and it is the first place where the exterior algebra does work that has nothing to do with volume or orientation.

Nothing later in this book uses it. It is here because the books that do use it are downstream: *Commutative Algebra* [20] and *Homological Algebra* [29] both build on the complex constructed below, and this is the last point in the prerequisite chain at which the exterior powers are available and the statement can be made.

Two definitions are needed, and neither has appeared so far.

Definition 16.5.1: Regular Sequence

Let R be a commutative ring. A sequence $a_1, \dots, a_n \in R$ is a *regular sequence* if

1. a_1 is not a zero divisor in R, and for each $i \geq 2$ the image of a_i is not a zero divisor in $R/(a_1, \dots, a_{i-1})$;
2. $(a_1, \dots, a_n) \neq R$.

An ideal generated by a regular sequence is called a *regular ideal*.

Condition (1) is the one that does the work, and it says the a_i impose genuinely new conditions one after another: each is a non-zero-divisor on the quotient by the previous ones. In $R = k[x_1, \dots, x_n]$ the variables themselves form a regular sequence, since $k[x_1, \dots, x_n]/(x_1, \dots, x_{i-1}) \cong k[x_i, \dots, x_n]$ is a domain in which $x_i \neq 0$. Note that an initial segment $a_1, \dots, a_m$ of a regular sequence is again one, directly from the definition. This is what makes induction on n available below.

The object the complex will produce is a free resolution in the sense of definition 12.3.27: an exact chain complex $\cdots \to F_1 \to F_0 \to M \to 0$ with every F_i free. Every module admits one, since a module is a quotient of a free module and the kernel is again a module. The content of a particular resolution is that it is short, explicit, or both. Over a principal ideal domain chapter 14 produced very short ones, because a submodule of a free module over a PID is free, so the process stops after one step. Over a general ring the process need not stop, and the Koszul complex is an explicit finite resolution available whenever the defining elements form a regular sequence.

The differential is contraction against a linear functional, and it exists for the same reason everything in this chapter exists: it is an alternating map, so theorem 16.1.8 builds it.

Proposition 16.5.2: Contraction Against a Functional

Let R be a commutative ring, F an R-module and $\lambda \in \mathrm{Hom}_R(F, R)$. For each $r \geq 1$ there is a unique R-module homomorphism

$$d_r \colon \bigwedge^{r}(F) \longrightarrow \bigwedge^{r-1}(F)$$

with

$$d_r(v_1 \wedge \cdots \wedge v_r) = \sum_{j=1}^{r} (-1)^{j-1} \lambda(v_j)\, v_1 \wedge \cdots \wedge \widehat{v_j} \wedge \cdots \wedge v_r$$

where $\widehat{v_j}$ means that the factor is omitted. Setting $d_0 = 0$, these satisfy the graded Leibniz rule

$$d(u \wedge w) = d(u) \wedge w + (-1)^p\, u \wedge d(w) \qquad \text{for } u \in \bigwedge^{p}(F)$$

***Proof*:**

Existence. The right-hand side, read as a function of $(v_1, \dots, v_r)$, is r-multilinear: each v_j appears once in each term, linearly, since λ is linear and $\wedge$ is multilinear.

It is alternating. Suppose $v_a = v_b =: v$ with $a < b$. Any term with $j \notin \{a, b\}$ still contains both

v_a and v_b among its factors, so it vanishes by proposition 16.1.9. The two remaining terms are

$$(-1)^{a-1}\lambda(v)\,W_a \qquad \text{and} \qquad (-1)^{b-1}\lambda(v)\,W_b$$

where W_a omits the factor in position a and W_b the one in position b. In W_a the surviving copy of v sits in position $b-1$, and in W_b it sits in position a. Moving it from one to the other is $b-1-a$ interchanges of adjacent factors, so $W_b = (-1)^{b-1-a}W_a$ by proposition 16.1.9. The sum of the two terms is therefore

$$\big((-1)^{a-1} + (-1)^{b-1}(-1)^{b-1-a}\big)\lambda(v)W_a = \big((-1)^{a-1} + (-1)^{a}\big)\lambda(v)W_a = 0$$

So the map is alternating, and theorem 16.1.8 gives d_r and its uniqueness.

Leibniz rule. Both sides are R-bilinear in (u, w), so it suffices to check them on products of degree-one elements, which generate each factor. For $u = v_1 \wedge \cdots \wedge v_p$ and $w = v_{p+1} \wedge \cdots \wedge v_{p+q}$, the defining formula for $d(u \wedge w)$ has $p+q$ terms. The first p of them are exactly the terms of $d(u) \wedge w$. The last q are the terms of $u \wedge d(w)$, except that in $d(u \wedge w)$ the term omitting v_{p+j} carries the sign $(-1)^{p+j-1}$ while in $u \wedge d(w)$ it carries $(-1)^{j-1}$. The two differ by $(-1)^p$, which is the stated factor, completing the proof.

Definition 16.5.3: Koszul Complex

Let R be a commutative ring and $a_1, \dots, a_n \in R$. Let $F = R^n$ with basis $e_1, \dots, e_n$ and let $\lambda\colon F \to R$ be the R-module homomorphism with $\lambda(e_i) = a_i$. The *Koszul complex* $K_\bullet(a_1, \dots, a_n)$ is

$$0 \longrightarrow \bigwedge^{n}(F) \xrightarrow{d_n} \bigwedge^{n-1}(F) \xrightarrow{d_{n-1}} \cdots \xrightarrow{d_2} \bigwedge^{1}(F) \xrightarrow{d_1} \bigwedge^{0}(F) = R$$

with d_r the contraction of proposition 16.5.2. On basis elements,

$$d_r\big(e_{i_1} \wedge \cdots \wedge e_{i_r}\big) = \sum_{j=1}^{r} (-1)^{j-1} a_{i_j}\; e_{i_1} \wedge \cdots \wedge \widehat{e_{i_j}} \wedge \cdots \wedge e_{i_r}$$

Proposition 16.5.4: The Koszul Complex Is a Complex

With the notation above, $d_{r-1} \circ d_r = 0$ for every $r \geq 1$, so $\operatorname{im}(d_r) \subseteq \ker(d_{r-1})$.

***Proof*:**
Both composites are R-linear, so it suffices to evaluate on a basis element $e_I = e_{i_1} \wedge \cdots \wedge e_{i_r}$ with $i_1 < \cdots < i_r$. Applying d_r and then d_{r-1} produces a sum of terms indexed by ordered pairs of distinct positions (j, k), the term being $\pm\, a_{i_j} a_{i_k}$ times the wedge with both factors omitted. Fix $j < k$ and collect the two terms that omit those two positions.

Removing position j first contributes the sign $(-1)^{j-1}$. In the shortened wedge the factor originally at position k now sits at position $k-1$, so removing it contributes $(-1)^{k-2}$, for a total of $(-1)^{j+k-3} = (-1)^{j+k-1}$. Removing position k first contributes $(-1)^{k-1}$, and the factor at position j is unmoved, so removing it contributes $(-1)^{j-1}$, for a total of $(-1)^{j+k-2} = (-1)^{j+k}$.

The two signs are opposite and the coefficients $a_{i_j}a_{i_k}$ agree because R is commutative, so the two terms cancel. Every term cancels in such a pair, completing the proof.

Exactness is where the hypothesis on the a_i enters, and it is the reason regular sequences were defined.

Theorem 16.5.5: Exactness of the Koszul Complex

Let R be a commutative ring and let $a_1, \dots, a_n$ be a regular sequence, with $I = (a_1, \dots, a_n)$. Then $\ker(d_r) = \operatorname{im}(d_{r+1})$ for every $r \geq 1$, and $R/\operatorname{im}(d_1) = R/I$. Consequently

$$0 \longrightarrow \bigwedge^{n}(F) \longrightarrow \cdots \longrightarrow \bigwedge^{1}(F) \longrightarrow R \longrightarrow R/I \longrightarrow 0$$

is a finite free resolution of R/I, of length n.

***Proof*:**
The statement about $R/\operatorname{im}(d_1)$ holds for any a_i: $d_1 = \lambda$ has image $\lambda(F) = (a_1, \dots, a_n) = I$. Freeness of each term is theorem 16.4.3. So only exactness at $r \geq 1$ is at issue, and it is proved by induction on n.

Base case $n = 1$. The complex is $0 \to R \xrightarrow{a_1} R$, and exactness at degree 1 says that multiplication by a_1 is injective, which is the statement that a_1 is not a zero divisor.

Inductive step. Let $n \geq 2$, let $F' \subseteq F$ be free on $e_1, \dots, e_{n-1}$ and let $K'_\bullet$ be the Koszul complex of $a_1, \dots, a_{n-1}$ on F', with differentials d'. An initial segment of a regular sequence is regular, so the inductive hypothesis applies to K'.

By theorem 16.4.3 every basis element of $\bigwedge^r(F)$ either involves e_n or does not, which gives

$$\bigwedge^{r}(F) = \bigwedge^{r}(F') \;\oplus\; \Big(\bigwedge^{r-1}(F') \wedge e_n\Big)$$

so every element is uniquely $x + y \wedge e_n$ with $x \in \bigwedge^r(F')$ and $y \in \bigwedge^{r-1}(F')$. The Leibniz rule of proposition 16.5.2, together with $d(e_n) = a_n$, computes the differential in these coordinates:

$$d_r\big(x + y \wedge e_n\big) = \Big(d'_r(x) + (-1)^{r-1} a_n\, y\Big) + \Big(d'_{r-1}(y)\Big) \wedge e_n \tag{16.1}$$

Suppose now $r \geq 1$ and $d_r(x + y \wedge e_n) = 0$. Comparing the two summands,

$$d'_{r-1}(y) = 0 \qquad \text{and} \qquad d'_r(x) + (-1)^{r-1} a_n y = 0$$

Producing v with $d'_r(v) = y$. If $r \geq 2$ then $r - 1 \geq 1$, so the inductive hypothesis gives exactness of K' at degree $r-1$ and $y = d'_r(v)$ for some $v \in \bigwedge^r(F')$. If $r = 1$ then $y \in \bigwedge^0(F') = R$ and the first equation is vacuous, so a different argument is needed. There the second equation reads $\lambda'(x) + a_n y = 0$ with $\lambda' = d'_1$, so $a_n y \in (a_1, \dots, a_{n-1})$. Because $a_1, \dots, a_n$ is a regular sequence, a_n is not a zero divisor on $R/(a_1, \dots, a_{n-1})$, so $y \in (a_1, \dots, a_{n-1})$. Writing $y = \sum_{i<n} c_i a_i$ and setting $v = \sum_{i<n} c_i e_i \in \bigwedge^1(F')$ gives $d'_1(v) = y$.

Producing u. From $d'_r(x) = -(-1)^{r-1} a_n y = (-1)^r a_n\, d'_r(v)$ one gets

$$d'_r\big(x - (-1)^r a_n v\big) = 0$$

and $r \geq 1$, so the inductive hypothesis gives $x - (-1)^r a_n v = d'_{r+1}(u)$ for some $u \in \bigwedge^{r+1}(F')$.

Conclusion. Apply (16.1) in degree $r+1$ to $u + v \wedge e_n$:

$$d_{r+1}\big(u + v \wedge e_n\big) = \Big(d'_{r+1}(u) + (-1)^r a_n v\Big) + d'_r(v) \wedge e_n = x + y \wedge e_n$$

So every cycle in degree r is a boundary, which is exactness, completing the proof.

Example 16.5.6: The Koszul Complex of the Variables

Take $R = k[x_1, \dots, x_n]$ over a field k and the regular sequence $x_1, \dots, x_n$, so that $I = (x_1, \dots, x_n)$ and $R/I \cong k$. The theorem produces a free resolution of k by free R-modules of ranks $\binom{n}{k}$, of total length n:

$$0 \to R \to R^n \to R^{\binom{n}{2}} \to \cdots \to R^n \to R \to k \to 0$$

For $n = 1$ this is $0 \to k[x] \xrightarrow{x} k[x] \to k \to 0$, which is the observation that x is not a zero divisor. For $n = 2$ it is

$$0 \to R \xrightarrow{\binom{-x_2}{x_1}} R^2 \xrightarrow{(x_1 \;\; x_2)} R \to k \to 0$$

and exactness in the middle says precisely that a pair (f, g) with $fx_1 + gx_2 = 0$ is a multiple of $(-x_2, x_1)$: the only relations among x_1 and x_2 are the obvious ones. Regularity is exactly what makes that true, and it fails for a non-regular sequence, as the exercises show.

The construction is the algebraic origin of several later ones. In *Homological Algebra* [29] the Koszul complex resolves the residue field in the proof of the Hilbert syzygy theorem, in *Commutative Algebra* [20] its homology measures how far a sequence is from being regular, and the same complex reappears in intersection theory, where the exactness above expresses that n hypersurfaces meeting in the expected dimension impose independent conditions.

Exercise 16.5.1

1. Show that x, y is a regular sequence in $k[x, y]$, and that x, x is not. Write out the Koszul complex for x, x and exhibit an element of $\ker(d_1)$ that is not in $\operatorname{im}(d_2)$, so that theorem 16.5.5 genuinely needs its hypothesis.

2. Show that a permutation of a regular sequence need not be regular, using $a_1 = x$, $a_2 = y(1-x)$, $a_3 = z(1-x)$ in $k[x, y, z]$. (Check that a_1, a_2, a_3 is regular but a_2, a_3, a_1 is not.)

3. Show that $d_n \colon \bigwedge^n(F) \to \bigwedge^{n-1}(F)$ is injective for a regular sequence, and identify $\bigwedge^n(F)$ and the image of d_n explicitly when $n = 2$.

4. Show that the Koszul complex of $a_1, \dots, a_n$ is, up to isomorphism, the tensor product over R of the n two-term complexes $0 \to R \xrightarrow{a_i} R \to 0$, in the sense that its degree-r term is the direct sum of the products of r of the left-hand copies with $n - r$ of the right-hand ones. (Only the module structure is asked for, not the differential.)

5. Write out the Koszul complex of x, y, z in $k[x, y, z]$ explicitly, giving the matrices of d_3, d_2 and d_1 with respect to the bases of theorem 16.4.3, and verify $d_2 d_3 = 0$ and $d_1 d_2 = 0$ by direct computation.

16.6 Summary

One module M, four classes of map on its powers, and four objects representing them. The tables below state what was established, each entry pointing at the result that establishes it.

The representing objects

Each class of multilinear map on M^k is represented by a module, and each representing object is a quotient of the tensor power by exactly what the class is required to kill.

Maps on M^k	Represented by	Universal property	Rank
k-multilinear	$\mathcal{T}^k(M)$	theorem 15.2.11	n^k
symmetric k-multilinear	$\mathcal{S}^k(M)$	theorem 16.1.6	$\binom{n+k-1}{k}$
alternating k-multilinear	$\bigwedge^k(M)$	theorem 16.1.8	$\binom{n}{k}$

The ranks are for M free of rank n, and are theorem 16.4.1, theorem 16.4.2 and theorem 16.4.3 respectively. In particular $\bigwedge^k(M) = 0$ once $k > n$, and $\bigwedge^n(M)$ is free of rank one, which is what makes the determinant a scalar.

The graded algebras

Summing the powers over k turns each family into a ring, graded in the sense of definition 16.2.1, and each acquires a universal property about homomorphisms into an algebra.

Algebra	Construction	Universal for maps into	Reference
$\mathcal{T}(M)$	$\bigoplus_k \mathcal{T}^k(M)$	any R-algebra	theorem 16.3.2
$\mathcal{S}(M)$	$\mathcal{T}(M)/\mathcal{C}(M)$	commutative R-algebras	theorem 16.3.6
$\bigwedge(M)$	$\mathcal{T}(M)/\mathcal{A}(M)$	algebras where $\varphi(m)^2 = 0$	proposition 16.3.8

That the two routes to $\mathcal{S}^k(M)$ and $\bigwedge^k(M)$ agree, one quotienting $\mathcal{T}^k(M)$ by a submodule and the other quotienting $\mathcal{T}(M)$ by an ideal, is lemma 16.3.3 and corollary 16.3.4. For M free of rank n the three algebras are the free associative algebra on n generators, the polynomial ring $R[x_1, \ldots, x_n]$ (theorem 16.4.2), and a free module of rank 2^n (theorem 16.4.3).

Graded rings

Statement	Reference
$1 \in S_0$; S_0 is a subring; S_+ is an ideal with $S/S_+ \cong S_0$	proposition 16.2.2
Graded $\Leftrightarrow$ components in I $\Leftrightarrow$ homogeneous generators $\Leftrightarrow$ a graded kernel	proposition 16.2.7
S/I is graded, with $(S/I)_k \cong S_k/I_k$	proposition 16.2.5
$\ker\varphi$ and $\mathrm{im}\varphi$ decompose degree by degree	proposition 16.2.6
Primality is testable on homogeneous elements	corollary 16.2.8
$I + J$, IJ, $I \cap J$ and $\sqrt{I}$ are graded	proposition 16.2.9

Signs

The exterior algebra is governed by signs, and three separate statements are involved, which are easy to conflate.

Statement	Reference
Alternating $\Rightarrow$ the sign rule; the converse needs 2 invertible	lemma 16.1.4
$m_{\sigma(1)} \wedge \cdots \wedge m_{\sigma(k)} = (-1)^{\sigma} m_1 \wedge \cdots \wedge m_k$	proposition 16.1.9
$a \wedge b = (-1)^{pq} b \wedge a$ for $a \in \bigwedge^p$, $b \in \bigwedge^q$	proposition 16.3.9
$\mathcal{S}^k(M)$ and $\bigwedge^k(M)$ sit inside $\mathcal{T}^k(M)$ when $k!$ is invertible	proposition 16.1.12

In characteristic 2 the first row is strict: a symmetric bilinear form satisfies the sign rule vacuously without being alternating, so the vanishing condition of definition 16.1.3 is the one the exterior power is built from.

The determinant, and what fails

Statement	Reference
$\bigwedge^n(\varphi)$ is multiplication by $\det(\varphi)$	theorem 16.4.7
det is independent of the basis, and multiplicative	same
φ is an isomorphism $\Leftrightarrow$ $\det(\varphi)$ is a unit	corollary 16.4.8
$\bigwedge^k$ does not preserve injections	example 16.4.4(4)
$\bigwedge^k(M)$ need not be free when M is not	theorem 16.4.3

The second row is the conceptual reading of multiplicativity: determinants multiply because $\bigwedge^n$ is a functor landing in rank-one modules, where composition is multiplication of scalars. The elementary proof from the defining sum is proposition 13.4.7.

The exterior powers of a free module also assemble into a complex, which resolves $R/(a_1, \ldots, a_n)$ whenever the a_i are regular. That construction is section 16.5$\star$, marked as skippable for a reader of this book, and is the form in which *Commutative Algebra* [20] and *Homological Algebra* [29] take up the exterior algebra.

17⋆

Projective, Injective and Flat Modules

⋆ *Optional. This chapter is an aside; nothing later in the book depends on it.*

Given two R-modules A and C, which modules M fit into a short exact sequence

$$0 \to A \to M \to C \to 0\ ?$$

This is the *extension problem*. Section 3.6 asked it for groups and left it open, and theorem 3.7.9 is exactly the reason it matters: the Jordan-Hölder theorem pins down the composition factors of a finite group without saying how they are assembled. For modules there is always at least one answer, $M = A \oplus C$, and for $A = \mathbb{Z}$ and $C = \mathbb{Z}/n\mathbb{Z}$ there are exactly two.

Exactness itself is the tool. A short exact sequence records how M is assembled from A and C, and the three constructions already available ($\mathrm{Hom}_R(D, -)$, $\mathrm{Hom}_R(-, D)$ and $- \otimes_R D$) each turn such a sequence into one that is exact everywhere except at a single spot. Whether the failure at that spot vanishes depends on the module D, and the modules for which it does are the projective, injective and flat modules of the title. What measures the failure when it does not vanish is a module $\mathrm{Ext}^1_R(C, A)$, whose elements turn out to be in bijection with the answers to the question above.

17.1 Exact Sequences, Splitting, and the Extension Problem

Definition 12.2.11 already said what it means for a chain of R-module homomorphisms to be exact: the image of each map is the kernel of the next. Two degenerate cases fix how short an exact sequence can be before it stops carrying information.

Proposition 17.1.1: Injective and Surjective Maps in Exact Sequences

Let A, B and C be R-modules.

1. The sequence $0 \to A \xrightarrow{\psi} B$ is exact at A if and only if ψ is injective.
2. The sequence $B \xrightarrow{\varphi} C \to 0$ is exact at C if and only if φ is surjective.

***Proof*:**

1. The only homomorphism $\alpha\colon 0 \to A$ sends $0 \mapsto 0$, so $\operatorname{im}(\alpha) = 0$. Exactness at A says $\operatorname{im}(\alpha) = \ker(\psi)$, which is therefore the assertion $\ker(\psi) = 0$, and a homomorphism is injective exactly when its kernel is trivial.
2. The only homomorphism $\beta\colon C \to 0$ sends every c to 0, so $\ker(\beta) = C$. Exactness at C says $\operatorname{im}(\varphi) = \ker(\beta) = C$, which is the assertion that φ is surjective.

Consequently $0 \to A \xrightarrow{f} B \to 0$ is exact precisely when f is both injective and surjective, so A and B are isomorphic and nothing has been learned. The first length that carries information is one longer.

Definition 17.1.2: Short Exact Sequence

A *short exact sequence* of R-modules is an exact sequence

$$0 \to A \xrightarrow{\psi} B \xrightarrow{\varphi} C \to 0$$

In this situation B is called an *extension of C by A*.

Unwinding proposition 17.1.1, the displayed sequence is short exact if and only if ψ is injective, φ is surjective and $\operatorname{im}(\psi) = \ker(\varphi)$. The first isomorphism theorem (theorem 12.2.10) then gives $C \cong B/\psi(A)$, while ψ identifies A with the submodule $\psi(A)$. An extension of C by A is therefore a module B containing a copy of A whose quotient by that copy is C, packaged in a form that names the two maps along with the three modules.

17.1.3 The Two Extension Conventions Definition 3.6.3 called G an extension of A by B when $G/A \cong B$, which is the order used in classical group theory and is the reverse of the order fixed above. The convention attached to short exact sequences is the one used for the rest of this chapter: the module being extended is the quotient C, and the module extending it is the submodule A. Both orders are current in the literature, and the safe reading is always the sequence itself.

Example 17.1.4: Short Exact Sequences

1. For any A and C the sequence
$$0 \to A \xrightarrow{\iota} A \oplus C \xrightarrow{\pi} C \to 0, \qquad \iota(a) = (a, 0), \quad \pi(a, c) = c$$
is short exact, since ι is injective, π is surjective, and $\operatorname{im}(\iota) = A \oplus 0 = \ker(\pi)$. Every pair of

modules therefore admits at least one extension.

2. Any homomorphism $\varphi\colon B \to C$ yields

$$0 \to \ker(\varphi) \hookrightarrow B \xrightarrow{\varphi} \operatorname{im}(\varphi) \to 0$$

and when φ is surjective the right-hand term is C itself.

3. Let M be an R-module and S a generating set for M. The homomorphism $\varphi\colon F(S) \to M$ extending the inclusion of S (theorem 12.3.11) is surjective, so with $K = \ker(\varphi)$,

$$0 \to K \hookrightarrow F(S) \xrightarrow{\varphi} M \to 0$$

is short exact. Every module is thus a quotient of a free module, and $F(S)$ is an extension of M by the module K of relations holding among the chosen generators.

Exactness is not confined to modules, nor to length three.

Example 17.1.5: The Centre and the Outer Automorphisms

Section 4.7.1 described the centre $Z(G)$ of a group and its outer automorphism group $\operatorname{Out}(G)$ as opposite ends of one construction, and exactness states this precisely. Let $\sigma\colon G \to \operatorname{Aut}(G)$ send g to conjugation by g, so that $\operatorname{im}(\sigma) = \operatorname{Inn}(G)$ (definition 4.7.3) and $\ker(\sigma) = Z(G)$, and let ρ be the quotient map by $\operatorname{Inn}(G)$, which is normal in $\operatorname{Aut}(G)$ by proposition 4.7.8. Then

$$1 \longrightarrow Z(G) \hookrightarrow G \xrightarrow{\sigma} \operatorname{Aut}(G) \xrightarrow{\rho} \operatorname{Out}(G) \longrightarrow 1$$

is exact: at $Z(G)$ because the inclusion is injective, at G because $\ker(\sigma) = Z(G)$, at $\operatorname{Aut}(G)$ because $\ker(\rho) = \operatorname{Inn}(G) = \operatorname{im}(\sigma)$, and at $\operatorname{Out}(G)$ because ρ is surjective. Cutting the sequence in the middle recovers theorem 4.7.4, the isomorphism $G/Z(G) \cong \operatorname{Inn}(G)$.

Example 17.1.4(1) makes $A \oplus C$ available for every pair. It is not always the only answer.

Example 17.1.6: Two Extensions of $\mathbb{Z}/n\mathbb{Z}$ by $\mathbb{Z}$

Fix $n \geq 2$. Two short exact sequences of $\mathbb{Z}$-modules with the same outer terms are

$$0 \to \mathbb{Z} \xrightarrow{\iota} \mathbb{Z} \oplus \mathbb{Z}/n\mathbb{Z} \xrightarrow{\pi} \mathbb{Z}/n\mathbb{Z} \to 0 \qquad \text{and} \qquad 0 \to \mathbb{Z} \xrightarrow{\cdot n} \mathbb{Z} \xrightarrow{p} \mathbb{Z}/n\mathbb{Z} \to 0$$

where $\iota(z) = (z, \overline{0})$ and $\pi(z, \overline{a}) = \overline{a}$, while $\cdot n$ is multiplication by n and p is reduction modulo n. The first is short exact by example 17.1.4(1). The second is short exact because multiplication by n is injective on $\mathbb{Z}$, reduction is surjective, and $\operatorname{im}(\cdot n) = n\mathbb{Z} = \ker(p)$.

The two middle terms are not isomorphic, since $\mathbb{Z} \oplus \mathbb{Z}/n\mathbb{Z}$ has an element of order n and $\mathbb{Z}$ has no element of finite order other than 0. So $\mathbb{Z}/n\mathbb{Z}$ has at least two genuinely different extensions by $\mathbb{Z}$.

The same phenomenon occurs among finite modules. Both

$$0 \to \mathbb{Z}/2\mathbb{Z} \xrightarrow{\overline{a} \mapsto \overline{2a}} \mathbb{Z}/4\mathbb{Z} \xrightarrow{\bmod 2} \mathbb{Z}/2\mathbb{Z} \to 0$$

$$0 \to \mathbb{Z}/2\mathbb{Z} \xrightarrow{\iota} \mathbb{Z}/2\mathbb{Z} \oplus \mathbb{Z}/2\mathbb{Z} \xrightarrow{\pi} \mathbb{Z}/2\mathbb{Z} \to 0$$

are short exact (for the first, the injection has image $\{\overline{0}, \overline{2}\}$, which is exactly the kernel of reduction modulo 2), and $\mathbb{Z}/4\mathbb{Z} \ncong \mathbb{Z}/2\mathbb{Z} \oplus \mathbb{Z}/2\mathbb{Z}$.

17.1.1 Maps Between Short Exact Sequences

Two extensions of the same pair can differ, and there is more than one reasonable sense in which two of them are the same.

Definition 17.1.7: Homomorphism and Equivalence of Short Exact Sequences

Let

$$0 \to A \xrightarrow{\psi} B \xrightarrow{\varphi} C \to 0 \qquad \text{and} \qquad 0 \to A' \xrightarrow{\psi'} B' \xrightarrow{\varphi'} C' \to 0$$

be short exact sequences of R-modules.

1. A *homomorphism of short exact sequences* from the first to the second is a triple (α, β, γ) of R-module homomorphisms making

$$\begin{array}{ccccccccc} 0 & \longrightarrow & A & \xrightarrow{\psi} & B & \xrightarrow{\varphi} & C & \longrightarrow & 0 \\ & & \downarrow{\scriptstyle \alpha} & & \downarrow{\scriptstyle \beta} & & \downarrow{\scriptstyle \gamma} & & \\ 0 & \longrightarrow & A' & \xrightarrow[\psi']{} & B' & \xrightarrow[\varphi']{} & C' & \longrightarrow & 0 \end{array}$$

   commute, that is $\beta \circ \psi = \psi' \circ \alpha$ and $\gamma \circ \varphi = \varphi' \circ \beta$.

2. The homomorphism is an *isomorphism of short exact sequences* if α, β and γ are all isomorphisms, and the extensions B and B' are then called *isomorphic*.

3. The two sequences are *equivalent* if $A = A'$ and $C = C'$ and there is an isomorphism as in (2) with $\alpha = \mathrm{id}_A$ and $\gamma = \mathrm{id}_C$. The extensions B and B' are then called *equivalent* extensions.

Equivalence is strictly stronger than isomorphism, and the gap between them is what the classification in section 17.6 counts. An isomorphism is free to rebuild the outer terms by any automorphisms it likes. An equivalence holds the outer terms fixed and asks only that the middles be matched compatibly. Two extensions of one fixed pair can accordingly be isomorphic as diagrams while remaining inequivalent as extensions.

Example 17.1.8: Homomorphisms, Isomorphisms and Equivalences

1. Let $n \mid m$ with $n, m > 1$ and put $k = m/n$. Take the second sequence of example 17.1.6 on top and, beneath it, the sequence built from $\ell(\overline{a}) = \overline{na}$ and reduction modulo n:

$$\begin{array}{ccccccccc} 0 & \longrightarrow & \mathbb{Z} & \xrightarrow{\cdot n} & \mathbb{Z} & \xrightarrow{p} & \mathbb{Z}/n\mathbb{Z} & \longrightarrow & 0 \\ & & \downarrow{\scriptstyle \alpha} & & \downarrow{\scriptstyle \beta} & & \downarrow{\scriptstyle \mathrm{id}} & & \\ 0 & \longrightarrow & \mathbb{Z}/k\mathbb{Z} & \xrightarrow[\ell]{} & \mathbb{Z}/m\mathbb{Z} & \xrightarrow[p']{} & \mathbb{Z}/n\mathbb{Z} & \longrightarrow & 0 \end{array}$$

   with α and β the reductions modulo k and modulo m. The bottom row is short exact: ℓ is well defined because $a \equiv a' \pmod{k}$ gives $na \equiv na' \pmod{m}$, injective because $na \equiv 0$

$(\text{mod } m = nk)$ gives $a \equiv 0 \pmod{k}$, and $\text{im}(\ell) = n\mathbb{Z}/m\mathbb{Z} = \ker(p')$. Both squares commute, since $\ell(\alpha(a)) = \overline{na} = \beta(na)$ and $p'(\beta(z)) = \overline{z} = \text{id}(p(z))$.

2. Let p be a prime and, for each $c \in \{1, \dots, p-1\}$, let

$$\mathcal{E}_c\colon \qquad 0 \to \mathbb{Z}/p\mathbb{Z} \xrightarrow{\psi} \mathbb{Z}/p^2\mathbb{Z} \xrightarrow{\varphi_c} \mathbb{Z}/p\mathbb{Z} \to 0, \qquad \psi(\overline{x}) = \overline{px}, \quad \varphi_c(\overline{y}) = \overline{cy}$$

   Each is short exact: ψ is well defined and injective because $px \equiv 0 \pmod{p^2}$ forces $x \equiv 0 \pmod{p}$; φ_c is surjective because c is invertible modulo p; and $\text{im}(\psi) = p\mathbb{Z}/p^2\mathbb{Z} = \ker(\varphi_c)$.

   Any two of them are isomorphic. Taking $\alpha = \text{id}$, $\beta = \text{id}$ and γ multiplication by $c'c^{-1}$ makes both squares of definition 17.1.7 commute, and γ is an automorphism of $\mathbb{Z}/p\mathbb{Z}$ because $c'c^{-1}$ is a unit modulo p.

   No two of them are equivalent. Every endomorphism β of $\mathbb{Z}/p^2\mathbb{Z}$ is multiplication by some t, so $\beta \circ \psi = \psi$ forces $tp \equiv p \pmod{p^2}$, that is $t \equiv 1 \pmod{p}$. Then $\varphi_{c'} \circ \beta$ is multiplication by $c't \equiv c' \pmod{p}$, and requiring it to equal φ_c forces $c' \equiv c \pmod{p}$.

   So $\mathcal{E}_1, \dots, \mathcal{E}_{p-1}$ are $p-1$ pairwise inequivalent extensions of $\mathbb{Z}/p\mathbb{Z}$ by $\mathbb{Z}/p\mathbb{Z}$, all isomorphic to one another, and none of them is $\mathbb{Z}/p\mathbb{Z} \oplus \mathbb{Z}/p\mathbb{Z}$.

3. The two extensions of $\mathbb{Z}/n\mathbb{Z}$ by $\mathbb{Z}$ in example 17.1.6 are not even isomorphic, since an isomorphism of short exact sequences carries B to B' isomorphically and the two middle terms are not isomorphic.

A homomorphism of short exact sequences constrains its own three components: the two outer maps already determine a great deal about the middle one.

Proposition 17.1.9: Short Five Lemma

Let (α, β, γ) be a homomorphism of short exact sequences, in the notation of definition 17.1.7. Then

1. if α and γ are injective, so is β;
2. if α and γ are surjective, so is β;
3. if α and γ are isomorphisms, so is β, and the two sequences are isomorphic.

***Proof*:**
This is the first diagram chase in the book and is written out element by element. A chase is an algorithm with three moves: push an element along an available arrow, use commutativity of a square to identify the two routes around it, and use exactness of a row to move *backwards* along an arrow once the element is known to lie in that arrow's image. The bookkeeping is done by redrawing the relevant square with elements in place of modules, and $\mapsto$ in place of $\to$.

Step 1: β is injective. Let $b \in B$ with $\beta(b) = 0$. The goal is $b = 0$. Chase b around the right-hand

square:

$$\begin{array}{ccc} b & \xmapsto{\varphi} & \varphi(b) \\ {\scriptstyle\beta}\downarrow & & \downarrow{\scriptstyle\gamma} \\ 0 & \xmapsto[\varphi']{} & 0 \end{array}$$

Down then right gives $\varphi'(\beta(b)) = \varphi'(0) = 0$, and right then down gives $\gamma(\varphi(b))$. The square commutes, so $\gamma(\varphi(b)) = 0$. And γ is injective, so $\varphi(b) = 0$, that is $b \in \ker(\varphi)$.

Exactness is what makes the next move available. The top row is exact at B, so $\ker(\varphi) = \operatorname{im}(\psi)$, and there is an $a \in A$ with $\psi(a) = b$. Knowing only that φ kills b, the chase has produced a preimage in A, which is where the hypothesis on α can be used. Now chase a around the left-hand square:

$$\begin{array}{ccc} a & \xmapsto{\psi} & b \\ {\scriptstyle\alpha}\downarrow & & \downarrow{\scriptstyle\beta} \\ \alpha(a) & \xmapsto[\psi']{} & 0 \end{array}$$

Commutativity gives $\psi'(\alpha(a)) = \beta(\psi(a)) = \beta(b) = 0$. The map ψ' is injective by proposition 17.1.1 applied to the bottom row, so $\alpha(a) = 0$, and α is injective by hypothesis, so $a = 0$. Therefore $b = \psi(a) = \psi(0) = 0$.

Step 2: β is surjective. Let $b' \in B'$. The goal is to produce a preimage under β. Both surjectivity hypotheses give a pullback. Since γ is surjective there is a $c \in C$ with $\gamma(c) = \varphi'(b')$, and since φ is surjective by proposition 17.1.1 there is a $b \in B$ with $\varphi(b) = c$. Chasing b gives

$$\begin{array}{ccc} b & \xmapsto{\varphi} & c \\ {\scriptstyle\beta}\downarrow & & \downarrow{\scriptstyle\gamma} \\ \beta(b) & \xmapsto[\varphi']{} & \varphi'(b') \end{array}$$

where the bottom right entry is computed by commutativity:

$$\varphi'(\beta(b)) = \gamma(\varphi(b)) = \gamma(c) = \varphi'(b')$$

Hence $\varphi'(b' - \beta(b)) = 0$, so $b' - \beta(b) \in \ker(\varphi') = \operatorname{im}(\psi')$ by exactness of the bottom row, and $b' - \beta(b) = \psi'(a')$ for some $a' \in A'$. Since α is surjective, $a' = \alpha(a)$ for some $a \in A$, and the left square gives

$$b' - \beta(b) = \psi'(\alpha(a)) = \beta(\psi(a))$$

Therefore $b' = \beta(b) + \beta(\psi(a)) = \beta\big(b + \psi(a)\big)$, so b' lies in the image of β.

Step 3. If α and γ are isomorphisms then Steps 1 and 2 both apply, so β is injective and surjective, hence an isomorphism, and (α, β, γ) is an isomorphism of short exact sequences by definition 17.1.7(2).

Neither chase used the R-action, only the underlying additive groups, and the single subtraction in Step 2 can be written multiplicatively as $b'\beta(b)^{-1}$. The proposition and its proof therefore hold verbatim for short exact sequences of groups, abelian or not.

The next result relates two short exact sequences by splicing their kernels and cokernels into one long exact sequence. Its proof runs the same three moves, and from here on a chase states which move it is making rather than tracking every element.


Proposition 17.1.10: Mini Snake Lemma

Let (α, β, γ) be a homomorphism of short exact sequences, in the notation of definition 17.1.7. Then there is an exact sequence of R-modules

$$0 \to \ker(\alpha) \xrightarrow{\overline{\psi}} \ker(\beta) \xrightarrow{\overline{\varphi}} \ker(\gamma) \xrightarrow{d} \operatorname{coker}(\alpha) \xrightarrow{\overline{\psi}'} \operatorname{coker}(\beta) \xrightarrow{\overline{\varphi}'} \operatorname{coker}(\gamma) \to 0$$

in which $\overline{\psi}$ and $\overline{\varphi}$ are the restrictions of ψ and φ, the maps $\overline{\psi}'$ and $\overline{\varphi}'$ are induced by ψ' and φ' on cokernels, and d is the *connecting homomorphism* constructed in the proof.

***Proof*:**
The whole statement is read off the following diagram, in which the two middle rows are the given ones and the outer rows are the sequence being constructed. The connecting homomorphism d is the one arrow not drawn: it runs from the top right corner $\ker(\gamma)$ to the bottom left corner $\operatorname{coker}(\alpha)$, and the route taken to build it (down the right column, left along the bottom row, then up the left column) is the snake the lemma is named for.



Step 1: the four induced maps exist. If $a \in \ker(\alpha)$ then $\beta(\psi(a)) = \psi'(\alpha(a)) = 0$, so ψ carries $\ker(\alpha)$ into $\ker(\beta)$. The same computation with the right square carries $\ker(\beta)$ into $\ker(\gamma)$. Dually $\psi'(\operatorname{im}(\alpha)) \subseteq \operatorname{im}(\beta)$, because $\psi'(\alpha(a)) = \beta(\psi(a))$, so ψ' descends to $\overline{\psi}' : \operatorname{coker}(\alpha) \to \operatorname{coker}(\beta)$. The same computation gives $\overline{\varphi}'$.

Step 2: construction of d. Let $c \in \ker(\gamma)$. Pull back along φ, which is surjective, to get $b \in B$ with $\varphi(b) = c$. Commutativity of the right square gives $\varphi'(\beta(b)) = \gamma(\varphi(b)) = \gamma(c) = 0$, so $\beta(b) \in \ker(\varphi') = \operatorname{im}(\psi')$ by exactness of the bottom row. Since ψ' is injective there is a *unique* $a' \in A'$ with $\psi'(a') = \beta(b)$. Define

$$d(c) := a' + \operatorname{im}(\alpha) \in \operatorname{coker}(\alpha)$$

The three steps just taken, namely pulling back along φ, crossing by β and pulling back along ψ', are the three segments of the route described above.

Step 3: d is a well defined homomorphism. The only choice made was the lift b. If $\varphi(b_1) = c$ as well then $b_1 - b \in \ker(\varphi) = \operatorname{im}(\psi)$, say $b_1 - b = \psi(a)$, so

$$\psi'(a_1') - \psi'(a') = \beta(b_1) - \beta(b) = \beta(\psi(a)) = \psi'(\alpha(a))$$

and injectivity of ψ' gives $a_1' - a' = \alpha(a) \in \operatorname{im}(\alpha)$. The two answers agree in $\operatorname{coker}(\alpha)$. Additivity and R-linearity follow because a lift of $c_1 + rc_2$ may be taken to be $b_1 + rb_2$, and ψ' and β are homomorphisms.

Step 4: exactness, at each of the six interior spots.

At $\ker(\alpha)$. The map $\overline{\psi}$ is a restriction of the injective ψ, so it is injective.

At $\ker(\beta)$. Since $\varphi \circ \psi = 0$ the composite $\overline{\varphi} \circ \overline{\psi}$ is zero, giving $\operatorname{im}(\overline{\psi}) \subseteq \ker(\overline{\varphi})$. Conversely let $b \in \ker(\beta)$ with $\varphi(b) = 0$. Exactness of the top row gives $b = \psi(a)$, and $\psi'(\alpha(a)) = \beta(\psi(a)) = \beta(b) = 0$, so $\alpha(a) = 0$ by injectivity of ψ'. Thus $a \in \ker(\alpha)$ and $b = \overline{\psi}(a)$.

At $\ker(\gamma)$. If $c = \overline{\varphi}(b)$ with $b \in \ker(\beta)$, then b is an admissible lift of c in Step 2 and $\beta(b) = 0 = \psi'(0)$, so $d(c) = 0 + \operatorname{im}(\alpha) = 0$. Conversely suppose $d(c) = 0$, so the element a' of Step 2 is $\alpha(a)$ for some $a \in A$. Then $\beta(b) = \psi'(\alpha(a)) = \beta(\psi(a))$, so $b - \psi(a) \in \ker(\beta)$, while $\varphi(b - \psi(a)) = \varphi(b) = c$. Hence $c = \overline{\varphi}(b - \psi(a))$.

At $\operatorname{coker}(\alpha)$. With c, b and a' as in Step 2,

$$\overline{\psi}'(d(c)) = \psi'(a') + \operatorname{im}(\beta) = \beta(b) + \operatorname{im}(\beta) = 0$$

so $\operatorname{im}(d) \subseteq \ker(\overline{\psi}')$. Conversely let $a' + \operatorname{im}(\alpha)$ lie in $\ker(\overline{\psi}')$, meaning $\psi'(a') = \beta(b)$ for some $b \in B$. Then $\gamma(\varphi(b)) = \varphi'(\beta(b)) = \varphi'(\psi'(a')) = 0$, so $c := \varphi(b)$ lies in $\ker(\gamma)$, and b is a lift of c exhibiting $d(c) = a' + \operatorname{im}(\alpha)$.

At $\operatorname{coker}(\beta)$. Since $\varphi' \circ \psi' = 0$ the composite $\overline{\varphi}' \circ \overline{\psi}'$ is zero. Conversely let $b' + \operatorname{im}(\beta)$ lie in $\ker(\overline{\varphi}')$, so $\varphi'(b') = \gamma(c)$ for some $c \in C$, and write $c = \varphi(b)$ using surjectivity of φ. Then $\varphi'(b' - \beta(b)) = \gamma(c) - \gamma(\varphi(b)) = 0$, so $b' - \beta(b) = \psi'(a')$ for some a', and $b' + \operatorname{im}(\beta) = \overline{\psi}'(a' + \operatorname{im}(\alpha))$.

At $\operatorname{coker}(\gamma)$. The map $\overline{\varphi}'$ is induced by the surjective φ', so it is surjective.

The name records that this is the three-module case. The general snake lemma replaces each of the three modules in a row by a whole chain complex and each kernel and cokernel by homology, and the six-term sequence above becomes a long exact sequence continuing in both directions. That version is [29, Snake Lemma]. The connecting homomorphism is what turns a short exact sequence into a longer one, and section 17.6 uses it to build the long exact sequences of Ext.

17.1.2 Split Sequences

Among all extensions of C by A, the direct sum $A \oplus C$ carries no information beyond its two ends. Example 17.1.6 showed that other extensions exist, so the ones that reduce to the direct sum deserve a name.

Definition 17.1.11: Split Short Exact Sequence

A short exact sequence $0 \to A \xrightarrow{\psi} B \xrightarrow{\varphi} C \to 0$ of R-modules *splits* if $\psi(A)$ has a complement in B, that is if there is a submodule $C' \subseteq B$ with

$$B = \psi(A) \oplus C'$$

The extension B is then called a *split extension* of C by A.

The complement is automatically a copy of C, so the definition need not require it. If $B = \psi(A) \oplus C'$, then φ restricted to C' is injective because $C' \cap \ker(\varphi) = C' \cap \psi(A) = 0$, and surjective because $\varphi(B) = \varphi(\psi(A)) + \varphi(C') = \varphi(C')$. Hence $B \cong \psi(A) \oplus C \cong A \oplus C$.

Definition 17.1.12: Section and Retraction

Let $0 \to A \xrightarrow{\psi} B \xrightarrow{\varphi} C \to 0$ be a short exact sequence of R-modules.

1. A *section* of φ is an R-module homomorphism $\mu\colon C \to B$ with $\varphi \circ \mu = \mathrm{id}_C$. It is also called a *splitting homomorphism* for the sequence.
2. A *retraction* of ψ is an R-module homomorphism $\lambda\colon B \to A$ with $\lambda \circ \psi = \mathrm{id}_A$.

Proposition 17.1.13: Splitting Criteria

For a short exact sequence $0 \to A \xrightarrow{\psi} B \xrightarrow{\varphi} C \to 0$ of R-modules the following are equivalent.

1. The sequence splits.
2. φ has a section $\mu\colon C \to B$.
3. ψ has a retraction $\lambda\colon B \to A$.

***Proof*:**
(1) $\Rightarrow$ (2). Let $B = \psi(A) \oplus C'$. As noted above φ restricts to an isomorphism $\varphi|_{C'} : C' \to C$, so its inverse followed by the inclusion $C' \subseteq B$ is a homomorphism $\mu\colon C \to B$, and $\varphi(\mu(c)) = c$ for every $c \in C$.

(2) $\Rightarrow$ (1). Let μ be a section and put $C' := \mu(C)$, a submodule of B. For any $b \in B$,

$$b = \big(b - \mu(\varphi(b))\big) + \mu(\varphi(b))$$

and $\varphi(b - \mu(\varphi(b))) = \varphi(b) - \varphi(b) = 0$, so the first summand lies in $\ker(\varphi) = \psi(A)$ while the second lies in C'. The sum is direct: if $\mu(c) \in \psi(A) = \ker(\varphi)$ then $0 = \varphi(\mu(c)) = c$, so $\mu(c) = 0$. Hence $B = \psi(A) \oplus C'$.

(1) $\Rightarrow$ (3). Let $B = \psi(A) \oplus C'$ and let $\pi_{\psi(A)}$ be the projection onto the first summand. The map ψ is an isomorphism onto $\psi(A)$ by proposition 17.1.1, so $\lambda := \psi^{-1} \circ \pi_{\psi(A)}$ is defined, and $\lambda(\psi(a)) = \psi^{-1}(\psi(a)) = a$.

(3) $\Rightarrow$ (1). Let λ be a retraction and put $C' := \ker(\lambda)$. For any $b \in B$,

$$b = \psi(\lambda(b)) + \big(b - \psi(\lambda(b))\big)$$

where the first summand lies in $\psi(A)$ and the second lies in C', since $\lambda(b-\psi(\lambda(b))) = \lambda(b)-\lambda(b) = 0$. The sum is direct: if $b = \psi(a)$ and $\lambda(b) = 0$ then $a = \lambda(\psi(a)) = \lambda(b) = 0$, so $b = 0$. Hence $B = \psi(A) \oplus C'$.

Example 17.1.14: Split and Non-split Sequences

1. The sequence $0 \to A \xrightarrow{\iota} A \oplus C \xrightarrow{\pi} C \to 0$ splits, with section $\mu(c) = (0, c)$.
2. Of the two sequences in example 17.1.6, the first splits and the second does not. A section of the second would be a nonzero homomorphism $\mathbb{Z}/n\mathbb{Z} \to \mathbb{Z}$, and the image z of $\overline{1}$ would satisfy $nz = 0$, forcing $z = 0$ and hence the whole map to be zero.
3. The sequence $0 \to \mathbb{Z}/2\mathbb{Z} \to \mathbb{Z}/4\mathbb{Z} \to \mathbb{Z}/2\mathbb{Z} \to 0$ does not split, since a splitting would give $\mathbb{Z}/4\mathbb{Z} \cong \mathbb{Z}/2\mathbb{Z} \oplus \mathbb{Z}/2\mathbb{Z}$, and only the left-hand side has an element of order 4.
4. Over $R = k[x]$ the sequence

   $$0 \to (x) \hookrightarrow k[x] \to k[x]/(x) \to 0$$

   does not split. A section would embed $k[x]/(x)$ as a nonzero submodule of $k[x]$ annihilated by x, and $k[x]$ is an integral domain, so no nonzero element is annihilated by x.

Splitting is a property of the sequence alone, and it is carried along by any isomorphism of sequences. Equivalence is not needed.

Proposition 17.1.15: Splitting Is an Isomorphism Invariant

Let (α, β, γ) be an isomorphism of short exact sequences, in the notation of definition 17.1.7. Then the top sequence splits if and only if the bottom one does.

***Proof*:**
Suppose the top sequence splits and let $\mu\colon C \to B$ be a section of φ, which exists by proposition 17.1.13. Set

$$\mu' := \beta \circ \mu \circ \gamma^{-1}\colon C' \to B'$$

a homomorphism because γ^{-1} is one. Commutativity of the right square reads $\varphi' \circ \beta = \gamma \circ \varphi$, so

$$\varphi' \circ \mu' = \varphi' \circ \beta \circ \mu \circ \gamma^{-1} = \gamma \circ \varphi \circ \mu \circ \gamma^{-1} = \gamma \circ \gamma^{-1} = \mathrm{id}_{C'}$$

Hence μ' is a section of φ' and the bottom sequence splits, again by proposition 17.1.13.

For the converse, note that $(\alpha^{-1}, \beta^{-1}, \gamma^{-1})$ is an isomorphism of short exact sequences from the bottom one to the top one: composing $\beta \circ \psi = \psi' \circ \alpha$ with β^{-1} on the left and α^{-1} on the right gives $\psi \circ \alpha^{-1} = \beta^{-1} \circ \psi'$, and the right square is handled the same way. Applying the first paragraph to it gives the converse.

The vocabulary is now sufficient to state the question this chapter opened with. Given R-modules A and C, write $\mathcal{E}(C, A)$ for the set of equivalence classes of extensions of C by A, in the sense of definition 17.1.7(3). This set is never empty, and all split extensions lie in a single class: if μ is a section of φ, then $B = \psi(A) \oplus \mu(C)$ by the proof of proposition 17.1.13, so $\beta(a, c) := \psi(a) + \mu(c)$ is an isomorphism $A \oplus C \to B$, both ψ and μ being injective. It satisfies $\beta(\iota(a)) = \psi(a)$ and $\varphi(\beta(a, c)) = c = \pi(a, c)$, so $(\mathrm{id}_A, \beta, \mathrm{id}_C)$ is an equivalence with the direct-sum sequence. By example 17.1.8(2) the set can have more than one element.

The *extension problem* for modules asks for $\mathcal{E}(C, A)$. Section 17.6 answers it by constructing a module $\mathrm{Ext}^1_R(C, A)$ together with a bijection $\mathrm{Ext}^1_R(C, A) \leftrightarrow \mathcal{E}(C, A)$ carrying 0 to the class of the split extension.

Exercise 17.1.1

1. For each of the following short exact sequences of $\mathbb{Z}$-modules, decide whether it splits. Exhibit a section when one exists, and prove that none exists otherwise.

   1. $0 \to \mathbb{Z} \xrightarrow{\cdot 3} \mathbb{Z} \to \mathbb{Z}/3\mathbb{Z} \to 0$
   2. $0 \to \mathbb{Z}/2\mathbb{Z} \to \mathbb{Z}/2\mathbb{Z} \oplus \mathbb{Z}/3\mathbb{Z} \to \mathbb{Z}/3\mathbb{Z} \to 0$, with the evident injection and projection
   3. $0 \to \mathbb{Z}/3\mathbb{Z} \to \mathbb{Z}/9\mathbb{Z} \to \mathbb{Z}/3\mathbb{Z} \to 0$, with $\overline{a} \mapsto \overline{3a}$ and reduction modulo 3
   4. $0 \to \mathbb{Z}/2\mathbb{Z} \to \mathbb{Z}/6\mathbb{Z} \to \mathbb{Z}/3\mathbb{Z} \to 0$, with $\overline{a} \mapsto \overline{3a}$ and reduction modulo 3

2. Let p be a prime. Show that every extension of $\mathbb{Z}/p\mathbb{Z}$ by $\mathbb{Z}/p\mathbb{Z}$ has a middle term of order p^2, hence isomorphic to $\mathbb{Z}/p^2\mathbb{Z}$ or to $\mathbb{Z}/p\mathbb{Z} \oplus \mathbb{Z}/p\mathbb{Z}$ by theorem 5.1.6, and that in the second case the sequence splits. In the first case, show the sequence is equivalent to one of the $\mathcal{E}_c$ of example 17.1.8(2). You may use that $\mathbb{Z}/p^2\mathbb{Z}$ has a unique subgroup of order p. Conclude that $\mathcal{E}(\mathbb{Z}/p\mathbb{Z}, \mathbb{Z}/p\mathbb{Z})$ has exactly p elements.

3. Let $m, n \geq 1$. Take both rows of definition 17.1.7 to be $0 \to \mathbb{Z} \xrightarrow{\cdot m} \mathbb{Z} \to \mathbb{Z}/m\mathbb{Z} \to 0$ and take α, β and γ all to be multiplication by n. Verify that this is a homomorphism of short exact sequences, identify all six terms of the sequence of proposition 17.1.10 in terms of $g = \gcd(m, n)$, and compute the connecting homomorphism d explicitly. Then specialise to $m = 4$ and $n = 6$.

4. Let (α, β, γ) be a homomorphism of short exact sequences.

   1. Show that if β is injective then so is α.
   2. Show that if β is surjective then so is γ.
   3. Give an example in which β is an isomorphism while α is not surjective and γ is not injective. *Hint*: one of the two rows may end in the zero module.

5. Show that a short exact sequence $0 \to A \to B \xrightarrow{\varphi} C \to 0$ of R-modules splits whenever C is a free module. *Hint*: choose a basis of C, lift each basis element along φ, and use theorem 12.3.11.

6. Show that if $0 \to A \xrightarrow{\psi} B \xrightarrow{\varphi} C \to 0$ splits then for every R-module D there are isomorphisms of abelian groups
$$\mathrm{Hom}_R(D, B) \cong \mathrm{Hom}_R(D, A) \oplus \mathrm{Hom}_R(D, C)$$
$$\mathrm{Hom}_R(B, D) \cong \mathrm{Hom}_R(A, D) \oplus \mathrm{Hom}_R(C, D)$$

Hint: use the section and the retraction given by proposition 17.1.13.

7. *(The five lemma.)* Consider a commutative diagram of R-modules

$$\begin{array}{ccccccccc} A_1 & \longrightarrow & A_2 & \longrightarrow & A_3 & \longrightarrow & A_4 & \longrightarrow & A_5 \\ \downarrow{\scriptstyle f_1} & & \downarrow{\scriptstyle f_2} & & \downarrow{\scriptstyle f_3} & & \downarrow{\scriptstyle f_4} & & \downarrow{\scriptstyle f_5} \\ B_1 & \longrightarrow & B_2 & \longrightarrow & B_3 & \longrightarrow & B_4 & \longrightarrow & B_5 \end{array}$$

with exact rows. Prove that if f_2 and f_4 are isomorphisms, f_1 is surjective and f_5 is injective, then f_3 is an isomorphism. *Hint*: run the two chases of proposition 17.1.9 one column further in each direction.

17.2 Projective Modules

Example 17.1.14 produced short exact sequences that do not split, so the extension problem has content. The instrument for measuring the failure is already available: fix an R-module D, apply $\mathrm{Hom}_R(D,-)$ to a short exact sequence, and see how much of the sequence survives.

Throughout, ψ_* denotes the map induced on $\mathrm{Hom}_R(D,-)$ by a homomorphism ψ, reserving the primes of definition 17.1.7 for the second row of a diagram.

Proposition 17.2.1: Left Exactness of $\mathrm{Hom}_R(D,-)$

Let D be an R-module.

1. For every R-module homomorphism $\psi\colon L \to M$, the assignment

$$\psi_*\colon \mathrm{Hom}_R(D,L) \to \mathrm{Hom}_R(D,M), \qquad f \mapsto \psi \circ f$$

is a homomorphism of abelian groups.

2. If $0 \to L \xrightarrow{\psi} M \xrightarrow{\varphi} N \to 0$ is a short exact sequence of R-modules, then

$$0 \to \mathrm{Hom}_R(D,L) \xrightarrow{\psi_*} \mathrm{Hom}_R(D,M) \xrightarrow{\varphi_*} \mathrm{Hom}_R(D,N)$$

is exact, for every D. In this situation one says that $\mathrm{Hom}_R(D,-)$ is *left exact*.

Note what part (2) does *not* claim: that φ_* is surjective, so that the sequence may be closed off with a $\to 0$ on the right. That claim is false in general, and the whole section grows out of the failure.

***Proof*:**

(1) For $f, g \in \mathrm{Hom}_R(D,L)$ and $d \in D$,

$$\big(\psi \circ (f+g)\big)(d) = \psi\big(f(d)+g(d)\big) = \psi(f(d)) + \psi(g(d)) = \big(\psi\circ f + \psi \circ g\big)(d)$$

using that ψ is a homomorphism, so $\psi_*(f+g) = \psi_*(f) + \psi_*(g)$.

(2) *Exactness at* $\mathrm{Hom}_R(D,L)$, which by proposition 17.1.1 is the injectivity of ψ_*. Suppose $\psi \circ f = 0$. Then $\psi(f(d)) = 0$ for every $d \in D$, so $f(d) \in \ker(\psi) = 0$ because ψ is injective, and $f = 0$.

Exactness at $\mathrm{Hom}_R(D, M)$, that is $\mathrm{im}(\psi_*) = \ker(\varphi_*)$.

($\subseteq$) For $f \in \mathrm{Hom}_R(D, L)$ we have $\varphi_*(\psi_*(f)) = \varphi \circ \psi \circ f$, and $\varphi \circ \psi = 0$ because $\mathrm{im}(\psi) = \ker(\varphi)$. So $\varphi_*(\psi_*(f)) = 0$.

($\supseteq$) Let $F \in \ker(\varphi_*)$, so $\varphi \circ F = 0$. For each $d \in D$ we have $\varphi(F(d)) = 0$, hence $F(d) \in \ker(\varphi) = \mathrm{im}(\psi)$, so there is an $l \in L$ with $\psi(l) = F(d)$. And l is unique because ψ is injective. Define $F' \colon D \to L$ by letting $F'(d)$ be that unique l, so that $\psi \circ F' = F$ by construction.

It remains to check that F' is a homomorphism, which is the only step here with content. For $d, e \in D$ and $r \in R$,

$$\psi\big(F'(d) + rF'(e)\big) = \psi(F'(d)) + r\psi(F'(e)) = F(d) + rF(e) = F(d + re) = \psi\big(F'(d + re)\big)$$

and ψ is injective, so $F'(d + re) = F'(d) + rF'(e)$. Hence $F' \in \mathrm{Hom}_R(D, L)$ and $F = \psi_*(F') \in \mathrm{im}(\psi_*)$.

Now the failure, computed before anything is named after it. The sequence at hand is the non-split extension of example 17.1.6 with $n = 2$.

Example 17.2.2: $\mathrm{Hom}_R(D, -)$ **Need Not Be Right Exact**
Take $R = \mathbb{Z}$, the short exact sequence


$$0 \to \mathbb{Z} \xrightarrow{\cdot 2} \mathbb{Z} \xrightarrow{\pi} \mathbb{Z}/2\mathbb{Z} \to 0$$

and $D = \mathbb{Z}/2\mathbb{Z}$. Then $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}/2\mathbb{Z}, \mathbb{Z}) = 0$: a homomorphism h sends $\overline{1}$ to some $z \in \mathbb{Z}$ with $2z = h(\overline{2}) = h(\overline{0}) = 0$, so $z = 0$. On the other hand $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}/2\mathbb{Z}, \mathbb{Z}/2\mathbb{Z}) \cong \mathbb{Z}/2\mathbb{Z}$, since such a homomorphism is determined by the image of $\overline{1}$ and both choices are legitimate. So applying $\mathrm{Hom}_{\mathbb{Z}}(D, -)$ gives

$$0 \to 0 \xrightarrow{(\cdot 2)_*} 0 \xrightarrow{\pi_*} \mathbb{Z}/2\mathbb{Z}$$

which is exact, as proposition 17.2.1 promised, and which cannot be extended by $\to 0$ on the right, since π_* is the zero map into a nonzero group.

The obstruction has a name in the language of diagrams. The element of $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}/2\mathbb{Z}, \mathbb{Z}/2\mathbb{Z})$ that is not hit is $\mathrm{id}_{\mathbb{Z}/2\mathbb{Z}}$, and saying it is not hit is saying that the dashed arrow below does not exist:



Indeed the only homomorphism $g \colon \mathbb{Z}/2\mathbb{Z} \to \mathbb{Z}$ is the zero map, and $\pi \circ 0 = 0 \neq \mathrm{id}_{\mathbb{Z}/2\mathbb{Z}}$.

A homomorphism out of D that fails to lift is exactly what stops $\mathrm{Hom}_R(D, -)$ from being exact. The modules for which this never happens are the subject of this section.

Definition 17.2.3: Projective Module

An R-module P is *projective* if the functor $\mathrm{Hom}_R(P, -)$ is exact, that is if for every short exact sequence $0 \to L \to M \to N \to 0$ of R-modules the sequence

$$0 \to \mathrm{Hom}_R(P, L) \to \mathrm{Hom}_R(P, M) \to \mathrm{Hom}_R(P, N) \to 0$$


is again short exact.

By proposition 17.2.1 everything in that sequence is automatic except surjectivity on the right, so the definition asks for one thing only: that every homomorphism out of P lift along every surjection. The theorem below makes that precise and adds two further descriptions, one about splitting and one about free modules.

Theorem 17.2.4: Equivalencies for Projective Modules

Let P be an R-module. The following are equivalent.

1. P is projective.
2. *(Lifting.)* For all R-modules M and N, if $\varphi\colon M \to N$ is surjective, then every $f \in \mathrm{Hom}_R(P, N)$ has a lift $g \in \mathrm{Hom}_R(P, M)$ with $\varphi \circ g = f$:



3. *(Splitting.)* Every short exact sequence $0 \to L \to M \to P \to 0$ of R-modules splits.
4. *(Summand.)* P is isomorphic to a direct summand of a free R-module.

***Proof*:**

(1) $\Rightarrow$ (2). Let $\varphi\colon M \to N$ be surjective and put $L = \ker(\varphi)$, so that $0 \to L \to M \xrightarrow{\varphi} N \to 0$ is short exact by example 17.1.4(2). Condition (1) makes $\varphi_*\colon \mathrm{Hom}_R(P, M) \to \mathrm{Hom}_R(P, N)$ surjective, so a given f equals $\varphi_*(g) = \varphi \circ g$ for some g.

(2) $\Rightarrow$ (1). Proposition 17.2.1 gives exactness at the first two spots of the sequence in definition 17.2.3, and (2) applied to the surjection φ says precisely that φ_* is surjective.

(2) $\Rightarrow$ (3). Let $0 \to L \xrightarrow{\psi} M \xrightarrow{\varphi} P \to 0$ be short exact. Then φ is surjective, so applying (2) to $f = \mathrm{id}_P$ produces $\mu \in \mathrm{Hom}_R(P, M)$ with $\varphi \circ \mu = \mathrm{id}_P$. That is a section of φ, so the sequence splits by proposition 17.1.13.

(3) $\Rightarrow$ (4). By example 17.1.4(3), applied with $S = P$ as a generating set, there is a short exact sequence

$$0 \to K \hookrightarrow F \xrightarrow{\pi} P \to 0$$

with F free. By (3) it splits, so $F = K \oplus C'$ for some submodule C', and $\pi|_{C'} : C' \to P$ is an isomorphism by the remark following definition 17.1.11. Hence P is isomorphic to the direct

summand C' of F.

(4) $\Rightarrow$ (2). Suppose $F = P' \oplus K$ with F free and $P' \cong P$. Replacing P by P', we may assume P itself is a summand, and write $\iota\colon P \to F$ for the inclusion and $\rho\colon F \to P$ for the projection, so $\rho \circ \iota = \mathrm{id}_P$.

Let $\varphi\colon M \to N$ be surjective and $f \in \mathrm{Hom}_R(P, N)$. Let $(e_s)_{s\in S}$ be a basis of F. For each s the element $f(\rho(e_s))$ lies in N, so by surjectivity of φ we may choose $m_s \in M$ with $\varphi(m_s) = f(\rho(e_s))$. By theorem 12.3.11 there is a unique homomorphism $G\colon F \to M$ with $G(e_s) = m_s$ for every s, and then $\varphi \circ G$ and $f \circ \rho$ are homomorphisms $F \to N$ agreeing on a basis, hence equal.

Now set $g := G \circ \iota\colon P \to M$. It is a homomorphism, and

$$\varphi \circ g = \varphi \circ G \circ \iota = f \circ \rho \circ \iota = f \circ \mathrm{id}_P = f$$

which is the required lift.

17.2.5 Summand, Not Sum Condition (4) says direct **summand** of a free module, which is weaker than being a free module. A direct summand of M is any submodule admitting a complement, so if $M = A \oplus B \oplus C$ then

$$A,\ B,\ C,\ A \oplus B,\ A \oplus C,\ B \oplus C,\ A \oplus B \oplus C$$

are all direct summands of M, and only the last is M itself. Reading (4) as "direct sum" would collapse the notion of projective onto the notion of free, and the two are genuinely different, as the two examples below show.

Corollary 17.2.6: Free Modules Are Projective

Every free R-module is projective.

***Proof*:**
A free module F is a direct summand of itself, with complement 0, so theorem 17.2.4(4) applies.

The converse fails, and it fails for a reason worth seeing twice. Both witnesses come from splitting a ring into a direct sum of ideals. The summands are then projective by construction and too small to be free.

Example 17.2.7: Projective But Not Free

1. Let $R = \mathbb{Z}/6\mathbb{Z}$. The Chinese remainder theorem gives a ring isomorphism $R \cong \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/3\mathbb{Z}$, which is in particular an isomorphism of R-modules, so the ideal $P = \overline{3}R = \{\overline{0}, \overline{3}\}$ is a direct summand of R, with complement $\overline{4}R = \{\overline{0}, \overline{4}, \overline{2}\}$. Since R is free of rank one over itself, P is projective by theorem 17.2.4(4).

   It is not free. A free R-module of finite rank k has 6^k elements and P has 2, while a free module of infinite rank is infinite. And $2 \neq 6^k$ for every $k \geq 0$.

2. Let F be a field, $n \geq 2$, and $R = M_n(F)$ the ring of $n \times n$ matrices. Let $C = F^n$ be the module of column vectors, a left R-module by matrix multiplication. Writing E_{jj} for the

matrix with a 1 in position (j, j) and zeros elsewhere,

$$R = \bigoplus_{j=1}^{n} RE_{jj}$$

since RE_{jj} consists of the matrices supported in column j and every matrix is the sum of its columns. Each RE_{jj} is isomorphic to C as a left R-module, by reading off column j. So C is a direct summand of the free module R and is projective.

It is not free. Counting dimensions over F, a free R-module of finite rank k has F-dimension kn^2, and one of infinite rank is infinite dimensional. Meanwhile $\dim_F C = n$, which is finite, and $n = kn^2$ has no solution $k \in \mathbb{Z}_{\geq 0}$ once $n \geq 2$.

Condition (4) is structural but awkward to verify, since it requires producing a free module and a complement. The following reformulation is the working criterion, because it asks only for elements of A and homomorphisms out of A, both of which can be exhibited.

Proposition 17.2.8: Dual Basis Lemma

An R-module A is projective if and only if there exist a family $(a_i)_{i\in I}$ of elements of A and a family $(f_i)_{i\in I}$ of homomorphisms $f_i \in \mathrm{Hom}_R(A, R)$ such that, for every $a \in A$,

1. $f_i(a) = 0$ for all but finitely many $i \in I$, and
2. $a = \sum_{i\in I} f_i(a)\, a_i$.

Such a pair of families is called a *dual basis* for A. It may be taken finite exactly when A is finitely generated.

***Proof*:**

($\Rightarrow$) Let A be projective. By example 17.1.4(3) there is a free module F with basis $(e_i)_{i\in I}$ and a surjection $\pi\colon F \to A$, and by theorem 17.2.4(3) the sequence $0 \to \ker(\pi) \to F \xrightarrow{\pi} A \to 0$ splits, so proposition 17.1.13 gives $\sigma\colon A \to F$ with $\pi \circ \sigma = \mathrm{id}_A$.

Put $a_i := \pi(e_i)$, and let $f_i(a)$ be the i-th coordinate of $\sigma(a)$ in the basis (e_i), so that $\sigma(a) = \sum_i f_i(a)e_i$. Each f_i is a homomorphism $A \to R$, being σ followed by a coordinate function, and (1) holds because an element of F has only finitely many nonzero coordinates. Applying π,

$$a = \pi(\sigma(a)) = \pi\Big(\sum_i f_i(a)e_i\Big) = \sum_i f_i(a)\pi(e_i) = \sum_i f_i(a)a_i$$

which is (2).

($\Leftarrow$) Given the two families, let F be free on a basis $(e_i)_{i\in I}$ and define $\pi\colon F \to A$ by $\pi(e_i) = a_i$, using theorem 12.3.11. Define $\sigma\colon A \to F$ by $\sigma(a) = \sum_i f_i(a)e_i$, which is a well defined element of F by (1) and is a homomorphism because each f_i is. Then (2) says exactly that $\pi(\sigma(a)) = a$, so $\pi \circ \sigma = \mathrm{id}_A$. In particular π is surjective, and σ is a section of π, so $0 \to \ker(\pi) \to F \xrightarrow{\pi} A \to 0$ splits by proposition 17.1.13 and A is a direct summand of F by definition 17.1.11. Theorem 17.2.4(4) makes A projective.

For the last sentence: if the families are finite then (2) exhibits $a_1, \ldots, a_n$ as generators of A. Conversely if A is generated by n elements, take $F = R^n$ in the forward direction, so that I is

finite.

Chapter 15 produced an isomorphism $V^* \otimes_F W \cong \mathrm{Hom}_F(V, W)$ for finite dimensional vector spaces (theorem 15.4.9). Over a general commutative ring the same map exists, and the dual basis says exactly when it is an isomorphism.

Corollary 17.2.9: Evaluation and Finitely Generated Projectives

Let R be a commutative ring, A an R-module, and $A^* := \mathrm{Hom}_R(A, R)$. Let

$$\theta\colon A^* \otimes_R A \to \mathrm{End}_R(A), \qquad \theta(f \otimes b)(a) = f(a)b$$

Then A is finitely generated and projective if and only if θ is an isomorphism, and in fact if and only if θ is surjective.

***Proof*:**

The map θ exists because $(f, b) \mapsto \big(a \mapsto f(a)b\big)$ is R-bilinear, so theorem 15.1.12 produces it.

Suppose first that θ is surjective. Then $\mathrm{id}_A = \theta(t)$ for some $t \in A^* \otimes_R A$, and every element of a tensor product is a finite sum of simple tensors, say $t = \sum_{i=1}^{n} f_i \otimes a_i$. Unwinding, $a = \mathrm{id}_A(a) = \sum_{i=1}^{n} f_i(a)a_i$ for every $a \in A$. That is a finite dual basis, so A is finitely generated and projective by proposition 17.2.8.

Conversely let A be finitely generated and projective, with a finite dual basis $(a_i, f_i)_{i=1}^{n}$ from proposition 17.2.8. Two observations do the work. The first is that

$$g = \sum_{i=1}^{n} g(a_i)\, f_i \qquad \text{for every } g \in A^*$$

since evaluating the right-hand side at a gives $\sum_i g(a_i)f_i(a) = g\big(\sum_i f_i(a)a_i\big) = g(a)$, using R-linearity of g.

Surjectivity. Given $\alpha \in \mathrm{End}_R(A)$, put $t = \sum_i f_i \otimes \alpha(a_i)$. Then for every a,

$$\theta(t)(a) = \sum_i f_i(a)\, \alpha(a_i) = \alpha\Big(\sum_i f_i(a)a_i\Big) = \alpha(a)$$

so $\theta(t) = \alpha$.

Injectivity. Let $t = \sum_{j=1}^{m} g_j \otimes b_j$ satisfy $\theta(t) = 0$. Expanding each g_j by the displayed identity and collecting,

$$t = \sum_j \Big(\sum_i g_j(a_i) f_i\Big) \otimes b_j = \sum_i f_i \otimes \Big(\sum_j g_j(a_i) b_j\Big) = \sum_i f_i \otimes \theta(t)(a_i) = 0$$

where the middle step moves the scalars $g_j(a_i) \in R$ across the tensor sign, which is legitimate because the tensor product is over R.

Example 17.2.10: Projective Modules
Throughout, proposition 12.3.36 is what lets Hom_R be computed one summand at a time.

1. If F is a field then every F-module is free (theorem 13.1.8), so every vector space is projective.

2. Any ring R is free of rank one over itself and hence projective. Directly: $\mathrm{Hom}_R(R, M) \cong M$ by $h \mapsto h(1)$, so applying $\mathrm{Hom}_R(R, -)$ to a short exact sequence returns that sequence, which is exact.

3. No nonzero finite abelian group is a projective $\mathbb{Z}$-module. A projective is a direct summand of a free module by theorem 17.2.4(4), hence a submodule of one; a free $\mathbb{Z}$-module has no nonzero element of finite order; and every nonzero element of a nonzero finite group has finite order.

   For $\mathbb{Z}/n\mathbb{Z}$ with $n \geq 2$ the same conclusion is visible in the functor. Applying $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}/n\mathbb{Z}, -)$ to $0 \to \mathbb{Z} \xrightarrow{\cdot n} \mathbb{Z} \xrightarrow{\pi} \mathbb{Z}/n\mathbb{Z} \to 0$ gives

   $$0 \to 0 \to 0 \to \mathbb{Z}/n\mathbb{Z}$$

   since $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}/n\mathbb{Z}, \mathbb{Z}) = 0$ by the argument of example 17.2.2 and $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}/n\mathbb{Z}, \mathbb{Z}/n\mathbb{Z}) \cong \mathbb{Z}/n\mathbb{Z}$. The last map is not surjective.

4. $\mathbb{Q}/\mathbb{Z}$ is not a projective $\mathbb{Z}$-module, being a nonzero torsion module and so not a submodule of a free one. Correspondingly

   $$0 \to \mathbb{Z} \hookrightarrow \mathbb{Q} \to \mathbb{Q}/\mathbb{Z} \to 0$$

   does not split: a section would exhibit $\mathbb{Q}/\mathbb{Z}$ as a submodule of $\mathbb{Q}$, and $\mathbb{Q}$ has no nonzero element of finite order while $\mathbb{Q}/\mathbb{Z}$ is nonzero and torsion.

5. $\mathbb{Q}$ is not a projective $\mathbb{Z}$-module either, and the reason is different: it is torsion-free, so the argument above does not apply. Instead, *every* homomorphism $h\colon \mathbb{Q} \to \mathbb{Z}$ is zero. For if $h(x) \neq 0$ for some x, then for every $n \geq 1$

   $$h(x) = h\Big(n \cdot \frac{x}{n}\Big) = n\, h\Big(\frac{x}{n}\Big)$$

   so n divides $h(x)$ for every $n \geq 1$, forcing $h(x) = 0$.

   Consequently every homomorphism from $\mathbb{Q}$ into a free $\mathbb{Z}$-module $F = \bigoplus_{i \in I} \mathbb{Z}$ is zero, since composing with each coordinate projection gives a homomorphism $\mathbb{Q} \to \mathbb{Z}$. So $\mathbb{Q}$ is not isomorphic to a submodule of a free $\mathbb{Z}$-module, in particular not to a direct summand of one, and theorem 17.2.4(4) fails.

6. Let $0 \to L \xrightarrow{\psi} M \xrightarrow{\varphi} N \to 0$ be short exact with N projective, and write $X^* = \mathrm{Hom}_R(X, R)$. Then

   $$0 \to N^* \xrightarrow{\varphi^*} M^* \xrightarrow{\psi^*} L^* \to 0$$

   is short exact, where $\varphi^*(h) = h \circ \varphi$ and $\psi^*(g) = g \circ \psi$.

   What makes this work is *not* that the modules are projective as arguments of $\mathrm{Hom}_R(-, R)$. Projectivity of L, M and N says nothing directly about a contravariant Hom. It is that N projective forces the sequence to split (theorem 17.2.4(3)), and a split sequence is

preserved by any additive functor. Explicitly, let μ be a section of φ and λ a retraction of ψ (proposition 17.1.13). Then λ^* is a section of ψ^*, since $\psi^*(\lambda^*(g)) = g \circ \lambda \circ \psi = g$, so ψ^* is surjective. And μ^* is a retraction of φ^*, since $\mu^*(\varphi^*(h)) = h \circ \varphi \circ \mu = h$, so φ^* is injective. Exactness in the middle holds because $\psi^*\varphi^*(h) = h \circ \varphi \circ \psi = 0$, and conversely a $g \in M^*$ with $g \circ \psi = 0$ kills $\psi(L) = \ker(\varphi)$ and so factors through $M/\ker(\varphi) \cong N$ by theorem 12.2.10.

7. If P_1 and P_2 are projective then so is $P_1 \oplus P_2$: writing $F_1 = P_1 \oplus K_1$ and $F_2 = P_2 \oplus K_2$ with F_i free, the module $F_1 \oplus F_2$ is free and contains $P_1 \oplus P_2$ as a direct summand with complement $K_1 \oplus K_2$.

Over one class of rings the gap between projective and free closes entirely.

Proposition 17.2.11: Projective Modules Over a PID

Let R be a principal ideal domain. Then every projective R-module is free. Together with corollary 17.2.6, projective and free coincide over a PID.

***Proof*:**
Let P be projective. By theorem 17.2.4(4) there is a free R-module F and a submodule $P' \subseteq F$ with $P \cong P'$, namely a direct summand. By theorem 14.1.6 the submodule P' is free, and hence so is P.

No finiteness hypothesis is needed, which is exactly what theorem 14.1.6 was proved for. The finite rank case (theorem 14.1.5) would give the statement only for finitely generated P. Example 17.2.7 shows that some hypothesis on R is unavoidable, since $\mathbb{Z}/6\mathbb{Z}$ and $M_n(F)$ are not domains. A second class where the two notions agree is the local rings, where every finitely generated projective module is free. That result belongs with the theory of local rings and is proved in *Commutative Algebra*.[1]

Two different presentations of the same module by projectives differ by no more than a free summand. This is the result that makes an invariant computed from a projective resolution independent of the resolution chosen, and section 17.6 depends on it.

Proposition 17.2.12: Schanuel's Lemma

Let M be an R-module and let

$$0 \to K_1 \hookrightarrow P_1 \xrightarrow{\pi_1} M \to 0 \qquad \text{and} \qquad 0 \to K_2 \hookrightarrow P_2 \xrightarrow{\pi_2} M \to 0$$

be short exact sequences with P_1 and P_2 projective. Then

$$K_1 \oplus P_2 \cong K_2 \oplus P_1$$

***Proof*:**
Let

$$X = \{(p_1, p_2) \in P_1 \oplus P_2 \mid \pi_1(p_1) = \pi_2(p_2)\}$$

which is a submodule of $P_1 \oplus P_2$, being the kernel of the homomorphism $(p_1, p_2) \mapsto \pi_1(p_1) - \pi_2(p_2)$.

[1] theorem 23.4.30.

Let q_1 and q_2 be the two coordinate projections restricted to X.

q_2 is surjective with kernel K_1. Given $p_2 \in P_2$, surjectivity of π_1 produces $p_1 \in P_1$ with $\pi_1(p_1) = \pi_2(p_2)$, and then $(p_1, p_2) \in X$ maps to p_2. Its kernel consists of the pairs of the form $(p_1, 0)$ that lie in X, and $(p_1, 0) \in X$ says $\pi_1(p_1) = \pi_2(0) = 0$, so the kernel is $K_1 \oplus 0$, which is isomorphic to K_1.

So $0 \to K_1 \to X \xrightarrow{q_2} P_2 \to 0$ is short exact, and P_2 is projective, so it splits by theorem 17.2.4(3), giving $X \cong K_1 \oplus P_2$ by the remark following definition 17.1.11. Exchanging the roles of the two sequences, the same argument applied to q_1 gives $X \cong K_2 \oplus P_1$.

Exercise 17.2.1

1. For each pair, decide whether the module is projective over the indicated ring, and justify the answer.

    1. $\mathbb{Z}/3\mathbb{Z}$ over $\mathbb{Z}/6\mathbb{Z}$
    2. $\mathbb{Z}/2\mathbb{Z}$ over $\mathbb{Z}/4\mathbb{Z}$
    3. $2\mathbb{Z}$ over $\mathbb{Z}$
    4. $\mathbb{Z}[x]/(x)$ over $\mathbb{Z}[x]$
    5. $\mathbb{Z}/2\mathbb{Z} \oplus \mathbb{Z}/3\mathbb{Z}$ over $\mathbb{Z}/6\mathbb{Z}$

2. Let $R = \mathbb{Z}/6\mathbb{Z}$ and $P = \overline{3}R$, the projective module of example 17.2.7(1). Exhibit a dual basis for P consisting of a single pair (a_1, f_1), and verify both conditions of proposition 17.2.8 directly. Then do the same for the complement $\overline{4}R$.

3. Show that the evaluation map θ of corollary 17.2.9 fails to be surjective in each of the following cases, and identify which hypothesis fails.

    1. $R = \mathbb{Z}$ and $A = \mathbb{Q}$
    2. $R = \mathbb{Z}$ and $A = \bigoplus_{k=1}^{\infty} \mathbb{Z}$

4. Take $R = \mathbb{Z}$, $P = \mathbb{Z}$, $M = \mathbb{Z}$, $N = \mathbb{Z}/6\mathbb{Z}$ with φ the reduction map, and $f\colon \mathbb{Z} \to \mathbb{Z}/6\mathbb{Z}$ the homomorphism with $f(1) = \overline{5}$. Determine every lift g of f along φ, and show that the set of lifts is a coset of $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}, 6\mathbb{Z})$ inside $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}, \mathbb{Z})$.

5. Let $(P_i)_{i \in I}$ be a family of R-modules. Show that $\bigoplus_{i \in I} P_i$ is projective if and only if every P_i is projective. *Hint*: for one direction, a direct summand of a direct summand is a direct summand.

6. Let $0 \to L \to M \to N \to 0$ be a short exact sequence of R-modules.

    1. Show that if L and N are projective then so is M.
    2. Give an example with M projective and L not projective. *Hint*: a ring of the form $\mathbb{Z}/p^2\mathbb{Z}$ has a non-projective ideal.

7. Call an R-module M *finitely presented* if there is an exact sequence $R^s \xrightarrow{\alpha} R^t \to M \to 0$ for some $s, t \in \mathbb{N}$. Use proposition 17.2.12 to show that if M is finitely presented then *every* surjection $\varphi\colon R^r \to M$ from a finitely generated free module has finitely generated kernel. Deduce that for a finitely generated M the converse holds too, so that finite presentation

may be tested on any one such surjection. *Hint*: the kernel of $R^t \to M$ is $\mathrm{im}(\alpha)$, and a direct summand of a finitely generated module is finitely generated.

17.3 Injective Modules

Section 17.2 fixed a module D and asked what $\mathrm{Hom}_R(D,-)$ does to a short exact sequence. The other slot of Hom_R asks the same question with the arrows reversed: fix D and apply $\mathrm{Hom}_R(-,D)$, which turns a homomorphism $M \to N$ into a homomorphism $\mathrm{Hom}_R(N,D) \to \mathrm{Hom}_R(M,D)$ by composition. A short exact sequence $0 \to L \xrightarrow{\psi} M \xrightarrow{\varphi} N \to 0$ therefore produces

$$0 \longrightarrow \mathrm{Hom}_R(N,D) \xrightarrow{\varphi^*} \mathrm{Hom}_R(M,D) \xrightarrow{\psi^*} \mathrm{Hom}_R(L,D) \longrightarrow 0$$

with the outer terms of the original sequence exchanged. The superscript stars record that the assignment reverses arrows, in contrast to the lower stars of section 17.2.

Proposition 17.3.1: Left Exactness of $\mathrm{Hom}_R(-,D)$

Let D be an R-module.

1. For every R-module homomorphism $\varphi\colon M \to N$, the assignment
$$\varphi^*\colon \mathrm{Hom}_R(N,D) \to \mathrm{Hom}_R(M,D), \qquad f \mapsto f \circ \varphi$$
is a homomorphism of abelian groups.

2. If $0 \to L \xrightarrow{\psi} M \xrightarrow{\varphi} N \to 0$ is a short exact sequence of R-modules, then
$$0 \to \mathrm{Hom}_R(N,D) \xrightarrow{\varphi^*} \mathrm{Hom}_R(M,D) \xrightarrow{\psi^*} \mathrm{Hom}_R(L,D)$$
is exact, for every D. In this situation one says that $\mathrm{Hom}_R(-,D)$ is *left exact*, the word being applied to the sequence $0 \to \mathrm{Hom}_R(N,D) \to \mathrm{Hom}_R(M,D) \to \mathrm{Hom}_R(L,D)$ obtained after the reversal.

As with proposition 17.2.1, part (2) does not claim that the last map is surjective. The two propositions fail at opposite ends of the original sequence: $\mathrm{Hom}_R(D,-)$ can miss homomorphisms into the *right* hand term N, and $\mathrm{Hom}_R(-,D)$ can miss homomorphisms out of the *left* hand term L.

***Proof*:**
(1) For $f, g \in \mathrm{Hom}_R(N,D)$ and $m \in M$,

$$\big((f+g)\circ\varphi\big)(m) = f(\varphi(m)) + g(\varphi(m)) = \big(f\circ\varphi + g\circ\varphi\big)(m)$$

so $\varphi^*(f+g) = \varphi^*(f) + \varphi^*(g)$.

(2) *Exactness at* $\mathrm{Hom}_R(N,D)$, which is the injectivity of φ^*. Suppose $f \circ \varphi = 0$. Every $n \in N$ is $\varphi(m)$ for some m, since φ is surjective, so $f(n) = f(\varphi(m)) = 0$ and $f = 0$.

Exactness at $\mathrm{Hom}_R(M,D)$, that is $\mathrm{im}(\varphi^*) = \ker(\psi^*)$.

($\subseteq$) For $f \in \mathrm{Hom}_R(N,D)$, $\psi^*(\varphi^*(f)) = f \circ \varphi \circ \psi = 0$, since $\varphi \circ \psi = 0$ by $\mathrm{im}(\psi) = \ker(\varphi)$.

($\supseteq$) Let $g \in \mathrm{Hom}_R(M, D)$ with $g \circ \psi = 0$, so g vanishes on $\mathrm{im}(\psi) = \ker(\varphi)$. Let $\pi\colon M \to M/\ker(\varphi)$ be the quotient map. By theorem 12.2.10 the map g factors as $g = \overline{g} \circ \pi$ for a unique $\overline{g}\colon M/\ker(\varphi) \to D$, and φ induces an isomorphism $\overline{\varphi}\colon M/\ker(\varphi) \to N$ with $\overline{\varphi} \circ \pi = \varphi$. Put $f := \overline{g} \circ \overline{\varphi}^{-1} \in \mathrm{Hom}_R(N, D)$. Then

$$\varphi^*(f) = f \circ \varphi = \overline{g} \circ \overline{\varphi}^{-1} \circ \overline{\varphi} \circ \pi = \overline{g} \circ \pi = g$$

so $g \in \mathrm{im}(\varphi^*)$.

The failure at the other end is visible in the same sequence that example 17.2.2 used, with the roles of the two slots exchanged.

Example 17.3.2: $\mathrm{Hom}_R(-, D)$ Need Not Be Right Exact
Take $R = \mathbb{Z}$, the short exact sequence

$$0 \to \mathbb{Z} \xrightarrow{\cdot 2} \mathbb{Z} \xrightarrow{\pi} \mathbb{Z}/2\mathbb{Z} \to 0$$

and $D = \mathbb{Z}/2\mathbb{Z}$. A homomorphism out of $\mathbb{Z}$ is determined by the image of 1, so $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}, \mathbb{Z}/2\mathbb{Z}) \cong \mathbb{Z}/2\mathbb{Z}$, and likewise $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}/2\mathbb{Z}, \mathbb{Z}/2\mathbb{Z}) \cong \mathbb{Z}/2\mathbb{Z}$. Applying $\mathrm{Hom}_{\mathbb{Z}}(-, D)$ gives


$$0 \to \mathbb{Z}/2\mathbb{Z} \xrightarrow{\pi^*} \mathbb{Z}/2\mathbb{Z} \xrightarrow{(\cdot 2)^*} \mathbb{Z}/2\mathbb{Z}$$

Here $\pi^*(\mathrm{id}_{\mathbb{Z}/2\mathbb{Z}}) = \pi \neq 0$, so π^* is injective and therefore, both groups having two elements, bijective. And $(\cdot 2)^*$ is the zero map: for $g \in \mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}, \mathbb{Z}/2\mathbb{Z})$ and $x \in \mathbb{Z}$,

$$\big(g \circ (\cdot 2)\big)(x) = g(2x) = 2\,g(x) = 0$$

because every element of $\mathbb{Z}/2\mathbb{Z}$ is killed by 2. The displayed sequence is thus exact, as proposition 17.3.1 promised, and it cannot be closed off with a $\to 0$ on the right, since $(\cdot 2)^*$ has image 0 inside a group of order two.

In the language of diagrams, the homomorphism not in the image of $(\cdot 2)^*$ is π itself, and saying it is not in the image says that π does not *extend* along the injection $\cdot 2$:



Any such F would satisfy $F(2x) = 2F(x) = 0$ while $\pi(x) \neq 0$ for odd x.

The contrast with section 17.2 is worth naming precisely, because the two words are easy to swap. A projective module is one out of which every homomorphism *lifts* along a surjection. An injective module is one into which every homomorphism *extends* along an injection.

Definition 17.3.3: Injective Module

An R-module Q is *injective* if the functor $\mathrm{Hom}_R(-, Q)$ is exact, that is if for every short exact sequence $0 \to L \to M \to N \to 0$ of R-modules the sequence


$$0 \to \mathrm{Hom}_R(N, Q) \to \mathrm{Hom}_R(M, Q) \to \mathrm{Hom}_R(L, Q) \to 0$$

is again short exact.

Theorem 17.3.4: Injective Modules Equivalences

Let Q be an R-module. The following are equivalent.

1. Q is injective.
2. *(Extension.)* For all R-modules L and M, if $\psi\colon L \to M$ is injective, then every $f \in \mathrm{Hom}_R(L, Q)$ has an extension $F \in \mathrm{Hom}_R(M, Q)$ with $F \circ \psi = f$:



3. *(Splitting.)* Every short exact sequence $0 \to Q \to M \to N \to 0$ of R-modules splits. Equivalently, whenever Q is a submodule of an R-module M, it is a direct summand of M.

***Proof*:**

(1) $\Rightarrow$ (2). Let $\psi\colon L \to M$ be injective and put $N = M/\psi(L)$, so that $0 \to L \xrightarrow{\psi} M \to N \to 0$ is short exact by proposition 17.1.1 and theorem 12.2.10. Condition (1) makes $\psi^*\colon \mathrm{Hom}_R(M, Q) \to \mathrm{Hom}_R(L, Q)$ surjective, so a given f is $\psi^*(F) = F \circ \psi$ for some F.

(2) $\Rightarrow$ (1). Proposition 17.3.1 gives exactness at the first two spots of the sequence in definition 17.3.3, and (2) applied to the injection ψ says precisely that ψ^* is surjective.

(2) $\Rightarrow$ (3). Let $0 \to Q \xrightarrow{\psi} M \xrightarrow{\varphi} N \to 0$ be short exact, so ψ is injective. Applying (2) to $f = \mathrm{id}_Q$ gives $\lambda \in \mathrm{Hom}_R(M, Q)$ with $\lambda \circ \psi = \mathrm{id}_Q$, a retraction of ψ, so the sequence splits by proposition 17.1.13.

(3) $\Rightarrow$ (2). Let $\psi\colon L \to M$ be injective and $f \in \mathrm{Hom}_R(L, Q)$. The construction that follows glues Q and M along L. Let

$$W = \big\{ \big(f(l),\, -\psi(l)\big) \;\big|\; l \in L \big\} \subseteq Q \oplus M$$

which is a submodule, being the image of the homomorphism $l \mapsto (f(l), -\psi(l))$, and set $X = (Q \oplus M)/W$. Write $\iota\colon Q \to X$ for $q \mapsto \overline{(q, 0)}$ and $j\colon M \to X$ for $m \mapsto \overline{(0, m)}$, both homomorphisms.

The map ι is injective: if $(q, 0) \in W$ then $q = f(l)$ and $\psi(l) = 0$ for some l, and ψ is injective, so $l = 0$ and $q = 0$. Thus $\iota(Q)$ is a submodule of X isomorphic to Q, and by (3) it is a direct

summand, say $X = \iota(Q) \oplus C$. Let $\rho\colon X \to Q$ be the projection onto the first summand followed by ι^{-1}, so that $\rho \circ \iota = \mathrm{id}_Q$.

Put $F := \rho \circ j\colon M \to Q$. For $l \in L$ the element $(f(l), -\psi(l))$ lies in W, so $\overline{(0, \psi(l))} = \overline{(f(l), 0)}$ in X, that is $j(\psi(l)) = \iota(f(l))$. Hence

$$F(\psi(l)) = \rho\big(j(\psi(l))\big) = \rho\big(\iota(f(l))\big) = f(l)$$

so $F \circ \psi = f$.

The name records condition (2): the property concerns extending along injections, exactly as *projective* records lifting along surjections. Condition (3) is the concrete reading: an injective module cannot be enlarged without splitting off, so it is as far from the inside of a bigger module as a submodule can be.

For projective modules theorem 17.2.4 offered a fourth description, as a direct summand of a free module, which reduces every question to free modules. Nothing that simple is available here, and the classification of injective modules over a general ring is genuinely harder. What replaces it is a test that only has to be run on the ideals of R.

Theorem 17.3.5: Baer's Criterion

Let R be a ring and Q an R-module.

1. Q is injective if and only if, for every left ideal I of R, every R-module homomorphism $g\colon I \to Q$ extends to an R-module homomorphism $G\colon R \to Q$.
2. Suppose R is a principal ideal domain. Then Q is injective if and only if $rQ = Q$ for every *nonzero* $r \in R$.

The hypothesis $r \neq 0$ in (2) cannot be dropped: $0 \cdot Q = 0$, so without it the condition would fail for every nonzero module.

***Proof*:**
(1) ($\Rightarrow$) The inclusion $I \hookrightarrow R$ is injective, so theorem 17.3.4(2) extends any $g\colon I \to Q$ to $G\colon R \to Q$.

($\Leftarrow$) Assume the extension property for ideals. It suffices to verify theorem 17.3.4(2), so let $\psi\colon L \to M$ be injective and $f \in \mathrm{Hom}_R(L, Q)$. Replacing L by $\psi(L)$ and f by $f \circ (\psi|^{\psi(L)})^{-1}$, we may assume L is a submodule of M and ψ the inclusion.

Step 1: a poset of partial extensions. Let

$$\mathcal{L} = \{(L', f') \mid L \subseteq L' \subseteq M,\ f' \in \mathrm{Hom}_R(L', Q),\ f'|_L = f\}$$

ordered by $(L', f') \leq (L'', f'')$ when $L' \subseteq L''$ and $f''|_{L'} = f'$. This is a partial order, and $\mathcal{L}$ is nonempty because $(L, f) \in \mathcal{L}$.

Step 2: chains have upper bounds. Let $\{(L_i, f_i)\}_{i \in \mathcal{I}}$ be a chain. The union $\mathfrak{L} = \bigcup_i L_i$ is a submodule of M, since any two of its elements lie in a common L_i by totality of the chain. Define $\mathfrak{f}\colon \mathfrak{L} \to Q$ by $\mathfrak{f}(x) = f_i(x)$ for any i with $x \in L_i$. This is unambiguous because the chain is compatible, and it is a homomorphism because any two elements lie in a common L_i. Then $(\mathfrak{L}, \mathfrak{f}) \in \mathcal{L}$ bounds the chain.

Step 3: a maximal element. By Zorn's lemma (theorem A.2.3) there is a maximal $(M', F) \in \mathcal{L}$.

Step 4: $M' = M$. Suppose not, and choose $m \in M$ with $m \notin M'$. Set

$$I = \{r \in R \mid rm \in M'\}$$

which is a left ideal of R: it contains 0; it is closed under addition because M' is; and if $r \in I$ and $s \in R$ then $(sr)m = s(rm) \in M'$. Define $g\colon I \to Q$ by $g(r) = F(rm)$, which is a homomorphism since F is and since $r \mapsto rm$ is. By hypothesis g extends to $G\colon R \to Q$.

Now let $M'' = M' + Rm$, a submodule of M strictly containing M', and define

$$F'\colon M'' \to Q, \qquad F'(m' + rm) = F(m') + G(r)$$

This is well defined. If $m'_1 + r_1 m = m'_2 + r_2 m$ then $(r_1 - r_2)m = m'_2 - m'_1 \in M'$, so $r_1 - r_2 \in I$ and therefore

$$G(r_1) - G(r_2) = G(r_1 - r_2) = g(r_1 - r_2) = F\big((r_1 - r_2)m\big) = F(m'_2) - F(m'_1)$$

which rearranges to $F(m'_1) + G(r_1) = F(m'_2) + G(r_2)$. That F' is a homomorphism is immediate from the formula, and taking $r = 0$ gives $F'|_{M'} = F$, so in particular $F'|_L = f$ and $(M'', F') \in \mathcal{L}$.

Since $m \in M''$ and $m \notin M'$, the pair (M'', F') is strictly larger than (M', F), contradicting maximality. Hence $M' = M$ and F is the required extension.

(2) ($\Rightarrow$) Let $x \in Q$ and $r \in R$ with $r \neq 0$. Define $g\colon (r) \to Q$ by $g(sr) = sx$. This is well defined because R is an integral domain: if $sr = s'r$ with $r \neq 0$ then $s = s'$. It is a homomorphism, and by part (1) it extends to $G\colon R \to Q$. Then

$$x = g(r) = G(r) = r\,G(1)$$

so $x \in rQ$. As x was arbitrary, $rQ = Q$. Only the domain hypothesis was used here, not that ideals are principal, so this direction holds over any integral domain.

($\Leftarrow$) Assume $rQ = Q$ for every nonzero r, and verify the criterion of part (1). Let I be an ideal of R and $g\colon I \to Q$ a homomorphism. Since R is a principal ideal domain, $I = (r)$ for some r. If $r = 0$ then $I = 0$ and $G = 0$ extends g. If $r \neq 0$, then $g(r) \in Q = rQ$, so there is a $y \in Q$ with $ry = g(r)$. Define $G\colon R \to Q$ by $G(s) = sy$, a homomorphism. For any element sr of I,

$$G(sr) = sry = s\,g(r) = g(sr)$$

so $G|_I = g$. By part (1), Q is injective.

Corollary 17.3.6: Quotients of Injectives Over a PID

Let R be a principal ideal domain, Q an injective R-module and $N \subseteq Q$ a submodule. Then Q/N is injective.

***Proof*:**
For $r \neq 0$ we have $rQ = Q$ by theorem 17.3.5(2), hence

$$r(Q/N) = (rQ + N)/N = (Q + N)/N = Q/N$$

and theorem 17.3.5(2) applies again in the other direction.

The condition appearing in theorem 17.3.5(2) is worth a name of its own, both because it is the only practical test for injectivity over $\mathbb{Z}$ and because it is the source of every concrete injective module in this chapter.

Definition 17.3.7: Divisible Group

Let R be an integral domain. An R-module M is *divisible* if $rM = M$ for every nonzero $r \in R$; equivalently, if for every $x \in M$ and every nonzero $r \in R$ there is a $y \in M$ with $ry = x$.
For $R = \mathbb{Z}$ this says that an abelian group G is divisible when every $x \in G$ is n times some element of G, for every $n \geq 1$. Such a G is called a *divisible group*.

In this language, theorem 17.3.5(2) reads: over a principal ideal domain, injective and divisible are the same condition. Over an integral domain that is not principal only half survives, namely that injective modules are divisible. The reverse implication used principality when it wrote $I = (r)$, and it genuinely fails in general.

Example 17.3.8: Divisible Groups

1. $\mathbb{Q}$ is divisible: given $\frac{a}{b} \in \mathbb{Q}$ and $n \geq 1$, the rational $\frac{a}{nb}$ satisfies $n \cdot \frac{a}{nb} = \frac{a}{b}$. So $\mathbb{Q}$ is an injective $\mathbb{Z}$-module. More generally the field of fractions of any integral domain R is a divisible R-module.

2. Any quotient of a divisible module is divisible, since $r(M/N) = (rM + N)/N = M/N$. In particular $\mathbb{Q}/\mathbb{Z}$ is divisible, hence an injective $\mathbb{Z}$-module. Note that $\mathbb{Q}/\mathbb{Z}$ is a torsion group, so divisibility does not force torsion-freeness. And in a torsion group the element y with $ry = x$ is not unique.

3. Fix a prime p and let

$$\mathbb{Z}_{p^\infty} = \{[x] \in \mathbb{Q}/\mathbb{Z} \mid p^n[x] = 0 \text{ for some } n \geq 0\} = \left\{ \left[\tfrac{a}{p^n}\right] \in \mathbb{Q}/\mathbb{Z} \;\middle|\; a \in \mathbb{Z},\ n \geq 0 \right\}$$

   the p-primary part of $\mathbb{Q}/\mathbb{Z}$, called the *Prüfer p-group*[a]. The two descriptions agree: $p^n\left[\frac{a}{p^n}\right] = [a] = 0$ gives one inclusion, and if $p^n[x] = 0$ with $[x] = \left[\frac{c}{d}\right]$ in lowest terms then $d \mid p^n$, so $[x]$ has the displayed form. It is a subgroup, being the set of elements killed by some power of p.
   It is divisible. Let $[x] = \left[\frac{a}{p^n}\right]$ and let $m \geq 1$, and write $m = p^k u$ with u coprime to p. Since u is invertible modulo p^{n+k}, choose v with $uv \equiv 1 \pmod{p^{n+k}}$, say $uv = 1 + p^{n+k}w$, and set $y = \left[\frac{av}{p^{n+k}}\right] \in \mathbb{Z}_{p^\infty}$. Then

$$my = \left[\frac{p^k uav}{p^{n+k}}\right] = \left[\frac{a(1+p^{n+k}w)}{p^n}\right] = \left[\frac{a}{p^n} + ap^k w\right] = [x]$$

   since $ap^k w \in \mathbb{Z}$. So $\mathbb{Z}_{p^\infty}$ is an injective $\mathbb{Z}$-module.

4. A direct product $\prod_i M_i$ of divisible modules is divisible, since the required y may be chosen coordinatewise, and so is a direct sum. Conversely if $M \oplus N$ is divisible then so are M and N: given $x \in M$ and $r \neq 0$, some (y, z) has $r(y, z) = (x, 0)$, and then $ry = x$.

5. No nonzero finite abelian group is divisible: if $|G| = m$ then $mg = 0$ for every g, so $mG = 0 \neq G$. Combined with theorem 5.1.6, no nonzero finitely generated abelian group is divisible, since a free summand $\mathbb{Z}$ is not divisible either.

[a] It is also $\varinjlim \mathbb{Z}/p^k\mathbb{Z}$ along the inclusions.

Before collecting examples of injective modules, one closure property is needed, and it is the one that fails to be symmetric with the projective case.

Proposition 17.3.9: Summands and Products of Injectives

Let R be a ring.

1. A direct summand of an injective R-module is injective.
2. A direct product $\prod_{i\in I} Q_i$ of R-modules is injective if and only if every Q_i is injective. In particular a finite direct sum of injective modules is injective.

***Proof*:**
(1) Let $Q = E \oplus C$ with Q injective, and let $\iota\colon E \to Q$ and $\rho\colon Q \to E$ be the inclusion and projection, so $\rho \circ \iota = \mathrm{id}_E$. Given an injection $\psi\colon L \to M$ and $f \in \mathrm{Hom}_R(L, E)$, the map $\iota \circ f$ extends to some $H \in \mathrm{Hom}_R(M, Q)$ by theorem 17.3.4(2). Then $F := \rho \circ H$ satisfies $F \circ \psi = \rho \circ \iota \circ f = f$, so theorem 17.3.4(2) holds for E.

(2) ($\Leftarrow$) Let every Q_i be injective, let $\psi\colon L \to M$ be injective and let $f \in \mathrm{Hom}_R(L, \prod_i Q_i)$. Each component $\pi_i \circ f$ extends to $F_i \in \mathrm{Hom}_R(M, Q_i)$, and $F := (F_i)_i$ satisfies $\pi_i \circ F \circ \psi = \pi_i \circ f$ for every i, hence $F \circ \psi = f$.

($\Rightarrow$) Each Q_j is a direct summand of $\prod_i Q_i$, with complement $\prod_{i\neq j} Q_i$, so part (1) applies.

Example 17.3.10: Injective Modules

1. $\mathbb{Z}$ is not an injective $\mathbb{Z}$-module: it is not divisible, since $2y = 1$ has no solution in $\mathbb{Z}$. Equivalently, the sequence $0 \to \mathbb{Z} \xrightarrow{\cdot 2} \mathbb{Z} \to \mathbb{Z}/2\mathbb{Z} \to 0$ does not split (example 17.1.14(2)), so theorem 17.3.4(3) fails. Since $\mathbb{Z}$ is free, free does not imply injective, in contrast with corollary 17.2.6.
2. $\mathbb{Q}$, $\mathbb{Q}/\mathbb{Z}$ and $\mathbb{Z}_{p^\infty}$ are injective $\mathbb{Z}$-modules, by example 17.3.8 and theorem 17.3.5(2). So is $\mathbb{Q} \oplus \mathbb{Q}/\mathbb{Z}$, by proposition 17.3.9(2).
3. No nonzero finitely generated $\mathbb{Z}$-module is injective, by example 17.3.8(5).
4. If $R = F$ is a field then every F-module is injective. Indeed every F-module is free (theorem 13.1.8), and any short exact sequence of F-modules $0 \to Q \to M \to N \to 0$ has N free, hence projective, hence the sequence splits by theorem 17.2.4(3). Theorem 17.3.4(3) follows. Over a field, projective, free and injective all coincide.
5. $\mathbb{Z}/2\mathbb{Z}$ is not an injective $\mathbb{Z}/4\mathbb{Z}$-module. It occurs as the ideal $(\overline{2}) \subseteq \mathbb{Z}/4\mathbb{Z}$, and $\mathbb{Z}/4\mathbb{Z}$ is indecomposable as a module over itself, since its only proper nonzero submodule is $(\overline{2})$ and a complement would have to be a second one. So $(\overline{2})$ is not a direct summand and

theorem 17.3.4(3) fails. Compare exercise set 17.2.1, question 1: the same module is not projective either.

17.3.1 Embedding a Module in an Injective

Example 17.1.4(3) says every module is a quotient of a free, hence of a projective, module. The dual statement is that every module is a submodule of an injective one. It is true, but it is not formal: there is no dual of a free module to hand, and the proof goes through $\mathbb{Z}$ and back.

Lemma 17.3.11: $\mathbb{Z}$-module Submodules of Injective Modules

Every $\mathbb{Z}$-module is a submodule of an injective $\mathbb{Z}$-module.

***Proof*:**
Let M be a $\mathbb{Z}$-module and A a set of generators, so that theorem 12.3.11 gives a surjection $\pi\colon \bigoplus_{a\in A}\mathbb{Z}\to M$ from the free $\mathbb{Z}$-module on A. Writing $K=\ker(\pi)$, theorem 12.2.10 gives $M\cong\bigoplus_{a\in A}\mathbb{Z}/K$.

Now $\bigoplus_{a\in A}\mathbb{Z}$ sits inside $V:=\bigoplus_{a\in A}\mathbb{Q}$, the direct sum of copies of $\mathbb{Q}$ indexed by A, which is divisible by example 17.3.8(1) and (4), hence injective. Since $K\subseteq\bigoplus_{a\in A}\mathbb{Z}\subseteq V$, the quotient V/K is defined, and it is divisible by example 17.3.8(2), hence injective. Finally

$$M\cong\bigoplus_{a\in A}\mathbb{Z}/K\subseteq V/K$$

exhibits M as a submodule of an injective $\mathbb{Z}$-module.

Passing from $\mathbb{Z}$ to an arbitrary ring is done by a change of rings, and the mechanism is the adjunction of theorem 15.3.9. The proof below writes the correspondence out explicitly rather than invoking naturality.

Lemma 17.3.12: Inducing Injective R-modules

Let $f\colon S\to R$ be a homomorphism of commutative rings and let Q be an injective S-module. Regard R as an S-module through f, and give

$$\mathrm{Hom}_S(R,Q)$$

the R-module structure $(r\cdot h)(x):=h(xr)$. Then $\mathrm{Hom}_S(R,Q)$ is an injective R-module.

***Proof*:**
Write $f_*(N)$ for an R-module N regarded as an S-module through f, so that $s\cdot n=f(s)n$.

Step 1: the correspondence. For an R-module N define

$$\alpha\mapsto\widetilde{\alpha},\quad \widetilde{\alpha}(n)=\alpha(n)(1)\qquad\text{and}\qquad \beta\mapsto\widehat{\beta},\quad \widehat{\beta}(n)(r)=\beta(rn)$$

between $\mathrm{Hom}_R\big(N,\mathrm{Hom}_S(R,Q)\big)$ and $\mathrm{Hom}_S\big(f_*(N),Q\big)$. These are the two directions of theorem 15.3.9 applied with N in the role of A, the ring R in the role of the bimodule B and Q in

the role of C, using $N \otimes_R R \cong N$. The verifications are short enough to give directly.

That $\widetilde{\alpha}$ is S-linear: $\alpha(n) \in \mathrm{Hom}_S(R, Q)$ is S-linear on R, whose S-action is $s \cdot x = f(s)x$, so $\alpha(n)(f(s)) = s\,\alpha(n)(1)$. Combining with R-linearity of α,

$$\widetilde{\alpha}(s \cdot n) = \alpha(f(s)n)(1) = \big(f(s) \cdot \alpha(n)\big)(1) = \alpha(n)(f(s)) = s\,\widetilde{\alpha}(n)$$

That $\widehat{\beta}(n)$ is S-linear: $\widehat{\beta}(n)(s \cdot r) = \beta(f(s)rn) = \beta(s \cdot (rn)) = s\,\widehat{\beta}(n)(r)$. That $\widehat{\beta}$ is R-linear: $\widehat{\beta}(r'n)(r) = \beta(rr'n) = \widehat{\beta}(n)(rr') = \big(r' \cdot \widehat{\beta}(n)\big)(r)$.

The two assignments are mutually inverse:

$$\widehat{\widetilde{\alpha}}(n)(r) = \widetilde{\alpha}(rn) = \alpha(rn)(1) = \big(r \cdot \alpha(n)\big)(1) = \alpha(n)(r), \qquad \widetilde{\widehat{\beta}}(n) = \widehat{\beta}(n)(1) = \beta(n)$$

and both are visibly compatible with restriction along a submodule inclusion $L \subseteq N$, in the sense that $\widetilde{\alpha|_L} = \widetilde{\alpha}|_L$.

Step 2: the extension property. Verify theorem 17.3.4(2) for $\mathrm{Hom}_S(R, Q)$. Let $L \subseteq M$ be R-modules and $\alpha \in \mathrm{Hom}_R(L, \mathrm{Hom}_S(R, Q))$. Then $\widetilde{\alpha} \in \mathrm{Hom}_S(f_*(L), Q)$, and $f_*(L) \subseteq f_*(M)$ is still an inclusion of S-modules, since restriction of scalars changes only the action. As Q is an injective S-module, theorem 17.3.4(2) gives $\beta \in \mathrm{Hom}_S(f_*(M), Q)$ with $\beta|_L = \widetilde{\alpha}$.

Put $A := \widehat{\beta} \in \mathrm{Hom}_R(M, \mathrm{Hom}_S(R, Q))$. Then

$$A|_L = \widehat{\beta|_L} = \widehat{\widetilde{\alpha}} = \alpha$$

so A extends α, and $\mathrm{Hom}_S(R, Q)$ is injective.

Corollary 17.3.13: Inducing Injectives Using Divisible Groups

Let R be a commutative ring and D a divisible abelian group. Then $\mathrm{Hom}_{\mathbb{Z}}(R, D)$ is an injective R-module.

***Proof*:**
The group D is an injective $\mathbb{Z}$-module by theorem 17.3.5(2), and there is a unique ring homomorphism $\mathbb{Z} \to R$, so lemma 17.3.12 applies with $S = \mathbb{Z}$.

Lemma 17.3.14: R-module Submodules of Injective Modules

Let R be a commutative ring and M an R-module. Then M is a submodule of an injective R-module.

***Proof*:**
By lemma 17.3.11 there is an injective $\mathbb{Z}$-module D with $M \subseteq D$ as $\mathbb{Z}$-modules. By theorem 17.3.5(2) the group D is divisible. Now compose three injections of R-modules:

$$M \xrightarrow{\sim} \mathrm{Hom}_R(R, M) \hookrightarrow \mathrm{Hom}_{\mathbb{Z}}(R, M) \hookrightarrow \mathrm{Hom}_{\mathbb{Z}}(R, D)$$

The first sends m to the map $x \mapsto xm$, and is an isomorphism of R-modules for the action $(r \cdot h)(x) = h(xr)$, its inverse being $h \mapsto h(1)$. The second is the inclusion of the R-linear maps

among the additive ones, which respects that action. The third is composition with $M \subseteq D$, injective because a map into M is zero exactly when it is zero into D. By corollary 17.3.13 the target $\mathrm{Hom}_{\mathbb{Z}}(R, D)$ is an injective R-module.

Definition 17.3.15: Injective Resolution

Let R be a ring and M an R-module. An *injective resolution* of M is an exact chain complex (definition 12.2.11)

$$0 \longrightarrow M \longrightarrow Q^0 \longrightarrow Q^1 \longrightarrow Q^2 \longrightarrow \cdots$$

in which every Q^i is injective. It has *finite length* k if $Q^i = 0$ for every $i > k$.

Corollary 17.3.16: Existence of Injective Resolutions

Every module over a commutative ring admits an injective resolution.

***Proof*:**
Embed M in an injective Q^0 by lemma 17.3.14, embed the quotient Q^0/M in an injective Q^1, embed $Q^1/(Q^0/M)$ in an injective Q^2, and continue. The composites $Q^i \to Q^i/(\text{previous image}) \hookrightarrow Q^{i+1}$ have image the kernel of the next map by construction, which is exactness.

17.3.2 Injective Hulls

Every module embeds in an injective one, but lemma 17.3.14 produces a wasteful embedding: nothing stops Q from being far larger than M. Asking for the smallest such Q turns out to have a clean answer, and the condition that pins it down is that M should meet every nonzero piece of Q.

Definition 17.3.17: Essential Extension

Let $M \subseteq E$ be R-modules. Then M is *essential* in E, and E is an *essential extension* of M, if

$$N \cap M \neq 0 \qquad \text{for every nonzero submodule } N \subseteq E$$

Equivalently, for every $x \in E$ with $x \neq 0$ there is an $r \in R$ with $rx \in M$ and $rx \neq 0$.

The two formulations agree because Rx is a nonzero submodule whenever $x \neq 0$, and any nonzero N contains such an Rx.

Lemma 17.3.18: Essential Extensions Compose

Let $M \subseteq E \subseteq F$ be R-modules with M essential in E and E essential in F. Then M is essential in F.

***Proof*:**
Let $N \subseteq F$ be a nonzero submodule. Then $N \cap E \neq 0$ because E is essential in F, and $N \cap E$ is a nonzero submodule of E, so $(N \cap E) \cap M \neq 0$ because M is essential in E. That intersection is contained in $N \cap M$.

Theorem 17.3.19: Universal Property of Injective Hulls

Let R be a commutative ring and M an R-module.

1. There is an injective R-module E containing M as an essential submodule. Such an E is called an *injective hull*, or *injective envelope*, of M, and is written $E(M)$.
2. If E and E' are both injective hulls of M, there is an isomorphism $E \to E'$ restricting to the identity on M.
3. If $M \subseteq Q$ with Q injective, there is an injective homomorphism $E(M) \to Q$ restricting to the identity on M, and its image is a direct summand of Q. So $E(M)$ is the smallest injective module containing M.

***Proof*:**

(1) By lemma 17.3.14 choose an injective Q with $M \subseteq Q$.

Step 1: a maximal essential extension inside Q. Let

$$\Sigma = \{E \mid M \subseteq E \subseteq Q \text{ and } M \text{ is essential in } E\}$$

partially ordered by inclusion. It contains M, so it is nonempty. A chain $\{E_i\}$ in Σ has upper bound $\bigcup_i E_i$, which is a submodule of Q containing M, and M is essential in it: a nonzero x in the union lies in some E_i, and $Rx \cap M \neq 0$ there. By Zorn's lemma (theorem A.2.3) there is a maximal $E \in \Sigma$.

Step 2: a maximal complement. Let $\mathcal{C}$ be the set of submodules $C \subseteq Q$ with $C \cap E = 0$, ordered by inclusion. It contains 0, and a chain's union again meets E trivially, so Zorn's lemma gives a maximal $C \in \mathcal{C}$.

Step 3: E is essential in Q/C. First, $E \cap C = 0$, so E maps injectively into Q/C. Let X/C be a nonzero submodule of Q/C, so $C \subsetneq X \subseteq Q$. By maximality of C we have $X \cap E \neq 0$. Choose $0 \neq e \in X \cap E$. Then $e \notin C$, since $E \cap C = 0$, so the class $e + C$ is a nonzero element of X/C lying in the image of E.

Step 4: E is a direct summand of Q. The sum $E + C$ is direct, so there is a projection $p\colon E \oplus C \to E \subseteq Q$. Since $E \oplus C$ is a submodule of Q and Q is injective, theorem 17.3.4(2) extends p to a homomorphism $g\colon Q \to Q$ with $g|_E = \mathrm{id}_E$ and $g(C) = 0$.

Then $\ker(g) \cap E = 0$, because g is the identity on E, and $C \subseteq \ker(g)$. So maximality of C forces $C = \ker(g)$. Hence g induces an isomorphism $Q/C \to \mathrm{im}(g)$, carrying the image of E onto E itself. By Step 3, E is essential in $\mathrm{im}(g)$, and M is essential in E, so M is essential in $\mathrm{im}(g)$ by lemma 17.3.18. Thus $\mathrm{im}(g) \in \Sigma$ and $E \subseteq \mathrm{im}(g)$, and maximality of E gives $E = \mathrm{im}(g)$.

Now $g\colon Q \to Q$ has image E and restricts to the identity on E, so $g \circ g = g$. An idempotent endomorphism splits its domain: every q is $g(q) + (q - g(q))$ with the first term in $\mathrm{im}(g)$ and the second in $\ker(g)$, and an element of $\mathrm{im}(g) \cap \ker(g)$ is $g(y)$ with $0 = g(g(y)) = g(y)$. Therefore $Q = \mathrm{im}(g) \oplus \ker(g) = E \oplus C$.

Step 5. By proposition 17.3.9(1) the summand E of the injective module Q is injective, and M is essential in E by construction.

(2) Let E and E' be injective hulls of M. Since E' is injective and $M \subseteq E$, theorem 17.3.4(2) extends the inclusion $M \hookrightarrow E'$ to a homomorphism $h\colon E \to E'$. Then $\ker(h) \cap M = 0$, because

h is injective on M, and M is essential in E, so $\ker(h) = 0$ and h is injective.

The image $h(E) \cong E$ is injective, so $h(E)$ is a direct summand of E' by theorem 17.3.4(3), say $E' = h(E) \oplus X$. Since $M = h(M) \subseteq h(E)$, the submodule X meets M trivially, and M is essential in E', so $X = 0$. Hence h is an isomorphism, and it is the identity on M by construction.

(3) Let $M \subseteq Q$ with Q injective. Extending the inclusion $M \hookrightarrow Q$ along $M \subseteq E(M)$ gives $h\colon E(M) \to Q$ with $h|_M$ the inclusion. As in (2), $\ker(h) \cap M = 0$ and M essential in $E(M)$ force h to be injective, and $h(E(M)) \cong E(M)$ is injective, hence a direct summand of Q by theorem 17.3.4(3).

Combining (1) and (3): every injective module containing M contains a copy of $E(M)$ over M, and $E(M)$ is injective, so $E(M)$ is a smallest one. Exercise set 17.3.1 below computes $E(\mathbb{Z}) = \mathbb{Q}$ and $E(\mathbb{Z}/p\mathbb{Z}) = \mathbb{Z}_{p^\infty}$.

One consequence of injectivity is worth recording before leaving the section, because it is what makes duality work for abelian groups at all. Section 13.3 defined the dual of a vector space as $V^* = \mathrm{Hom}_k(V, k)$ and found $V \cong V^{**}$ naturally in finite dimensions. Over $\mathbb{Z}$ the same recipe collapses: $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}/n\mathbb{Z}, \mathbb{Z}) = 0$ for every $n \geq 2$, by the argument of example 17.2.2, so dualizing against $\mathbb{Z}$ destroys every torsion group. Replacing $\mathbb{Z}$ by the injective module $\mathbb{Q}/\mathbb{Z}$ repairs it, since a homomorphism $\mathbb{Z}/n\mathbb{Z} \to \mathbb{Q}/\mathbb{Z}$ sends $\overline{1}$ to an element killed by n, and those form the cyclic group $\frac{1}{n}\mathbb{Z}/\mathbb{Z}$, so

$$\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}/n\mathbb{Z},\, \mathbb{Q}/\mathbb{Z}) \cong \mathbb{Z}/n\mathbb{Z}$$

The module $\mathbb{Q}/\mathbb{Z}$ is the *dualizing module* for abelian groups. Injectivity is exactly what makes this work: it is what keeps $\mathrm{Hom}_{\mathbb{Z}}(-, \mathbb{Q}/\mathbb{Z})$ exact, so that the dual of a submodule is a quotient of the dual. The isomorphism displayed above is not natural, there being no canonical generator of a cyclic group, but the double dual is. The systematic development, in which these homomorphisms become characters, is section 53.2.

Exercise 17.3.1

1. For each pair, decide whether the module is injective over the indicated ring, and justify the answer.
    1. $\mathbb{Q}$ over $\mathbb{Z}$
    2. $\mathbb{Z}/6\mathbb{Z}$ over $\mathbb{Z}/6\mathbb{Z}$
    3. $\mathbb{Z}/2\mathbb{Z}$ over $\mathbb{Z}/4\mathbb{Z}$
    4. $\mathbb{Q}/\mathbb{Z}$ over $\mathbb{Z}$
    5. $F[x]$ over $F[x]$, for a field F
2. Let $g\colon 6\mathbb{Z} \to \mathbb{Q}/\mathbb{Z}$ be the homomorphism of $\mathbb{Z}$-modules determined by $g(6) = \left[\frac{1}{4}\right]$. Find every extension $G\colon \mathbb{Z} \to \mathbb{Q}/\mathbb{Z}$ of g, and say how many there are. Then explain why theorem 17.3.5 guarantees at least one without any computation.
3. Essential extensions.
    1. Show that $\mathbb{Z}$ is essential in $\mathbb{Q}$ as a $\mathbb{Z}$-module.
    2. Show that $\mathbb{Z}/p\mathbb{Z}$ is essential in $\mathbb{Z}/p^2\mathbb{Z}$.
    3. Show that $\mathbb{Z} \oplus 0$ is *not* essential in $\mathbb{Z} \oplus \mathbb{Z}/2\mathbb{Z}$.

4. Deduce from (a) that $E(\mathbb{Z}) \cong \mathbb{Q}$.

4. Show that every nonzero subgroup of $\mathbb{Z}_{p^\infty}$ contains an element of order p, and deduce that $\mathbb{Z}/p\mathbb{Z}$ is essential in $\mathbb{Z}_{p^\infty}$. Conclude that $E(\mathbb{Z}/p\mathbb{Z}) \cong \mathbb{Z}_{p^\infty}$ as $\mathbb{Z}$-modules. *Hint*: the subgroups of $\mathbb{Z}_{p^\infty}$ are totally ordered by inclusion.

5. Let $0 \to L \to M \to N \to 0$ be a short exact sequence of R-modules.

   1. Show that if L is injective the sequence splits, so $M \cong L \oplus N$.
   2. Show that if L and N are injective then so is M.
   3. Give an example with M injective and N not injective. *Hint*: take $R = \mathbb{Z}/4\mathbb{Z}$, and use example 17.3.10(5). Why does no such example exist over $\mathbb{Z}$?

6. *(The dual of Schanuel's lemma.)* Let

$$0 \to M \to Q_1 \to C_1 \to 0 \qquad \text{and} \qquad 0 \to M \to Q_2 \to C_2 \to 0$$

   be short exact sequences of R-modules with Q_1 and Q_2 injective. Prove that $C_1 \oplus Q_2 \cong C_2 \oplus Q_1$. *Hint*: run the proof of proposition 17.2.12 backwards, replacing the submodule of $P_1 \oplus P_2$ by the quotient of $Q_1 \oplus Q_2$ by the copy of M embedded as $m \mapsto (\iota_1(m), -\iota_2(m))$.

7. Compute injective resolutions.

   1. Show that $0 \to \mathbb{Z} \to \mathbb{Q} \to \mathbb{Q}/\mathbb{Z} \to 0$ is an injective resolution of $\mathbb{Z}$ as a $\mathbb{Z}$-module, of length 1.
   2. Show that multiplication by p on $\mathbb{Z}_{p^\infty}$ is surjective with kernel the subgroup of order p, and deduce that $0 \to \mathbb{Z}/p\mathbb{Z} \to \mathbb{Z}_{p^\infty} \xrightarrow{\cdot p} \mathbb{Z}_{p^\infty} \to 0$ is an injective resolution of $\mathbb{Z}/p\mathbb{Z}$, again of length 1.
   3. Conclude that every $\mathbb{Z}$-module has an injective resolution of length at most 1. *Hint*: corollary 17.3.6.

17.4⋆ Divisible Groups

⋆ *Optional. This section is an aside; nothing later in the book depends on it.*

Example 17.3.8 exhibited $\mathbb{Q}$, $\mathbb{Q}/\mathbb{Z}$ and the Prüfer groups $\mathbb{Z}_{p^\infty}$ as divisible, and theorem 17.3.5(2) made each of them an injective $\mathbb{Z}$-module. This section proves that the list is complete: every divisible group is a direct sum of copies of those, in essentially one way. Since divisible and injective coincide over $\mathbb{Z}$, that is a full classification of the injective $\mathbb{Z}$-modules.

Everything here is about abelian groups, so *group* means *abelian group* throughout, written additively, and $\mathrm{Tor}(G)$ denotes the torsion subgroup of definition 12.3.18.

A subgroup of a divisible group need not be divisible: $\mathbb{Z} \subseteq \mathbb{Q}$ is the standard example. It is therefore not obvious that a group has a largest divisible subgroup, and the first thing to establish is that it does.

Definition 17.4.1: Divisible Subgroup

Let G be an abelian group. Write dG for the subgroup of G generated by all the divisible subgroups of G, that is, the set of finite sums $x_1 + \cdots + x_k$ with each x_i lying in some divisible subgroup. If $dG = 0$, the group G is called *reduced*.

Lemma 17.4.2: dG Is the Largest Divisible Subgroup

Let G be an abelian group. Then dG is divisible, and every divisible subgroup of G is contained in dG.

***Proof*:**
Let $x \in dG$ and $n \geq 1$. Write $x = x_1 + \cdots + x_k$ with $x_i \in D_i$ for divisible subgroups $D_i \subseteq G$. Each D_i is divisible, so there is a $y_i \in D_i$ with $ny_i = x_i$. Then $y := y_1 + \cdots + y_k$ lies in dG and

$$ny = ny_1 + \cdots + ny_k = x_1 + \cdots + x_k = x$$

so $n\,dG = dG$. The second claim holds by construction, since every divisible subgroup is one of the D_i available in the generating set.

Lemma 17.4.3: Splitting Off the Divisible Part

Let G be an abelian group. Then there is a subgroup $H \subseteq G$ with

$$G = dG \oplus H$$

and every such H is reduced, and isomorphic to G/dG.

***Proof*:**
By lemma 17.4.2 the subgroup dG is divisible, hence an injective $\mathbb{Z}$-module by theorem 17.3.5(2), so the short exact sequence

$$0 \to dG \hookrightarrow G \to G/dG \to 0$$

splits by theorem 17.3.4(3). This gives $G = dG \oplus H$ for some subgroup H, with $H \cong G/dG$ by the remark following definition 17.1.11.

Such an H is reduced. The subgroup dH is a divisible subgroup of H, hence a divisible subgroup of G, so $dH \subseteq dG$ by lemma 17.4.2. Also $dH \subseteq H$. Therefore $dH \subseteq dG \cap H = 0$.

So every abelian group is a divisible group plus a reduced one, and the two halves do not interact. Classifying the divisible groups is thus a genuine piece of the classification of abelian groups, and it is the piece that has a clean answer. The route splits G once more, into its torsion part and the rest.

Lemma 17.4.4: The Torsion Subgroup of a Divisible Group

Let G be a divisible abelian group. Then $\mathrm{Tor}(G)$ is divisible, and

$$G \cong \mathrm{Tor}(G) \oplus G/\mathrm{Tor}(G)$$

***Proof*:**
Let $x \in \mathrm{Tor}(G)$ and $n \geq 1$. Since G is divisible there is a $y \in G$ with $ny = x$. Since x is a torsion element there is an $m \geq 1$ with $mx = 0$, and then

$$(mn)y = m(ny) = mx = 0$$

so y is a torsion element and $y \in \mathrm{Tor}(G)$. Hence $n\mathrm{Tor}(G) = \mathrm{Tor}(G)$ for every $n \geq 1$, and $\mathrm{Tor}(G)$ is divisible.

Being divisible, $\mathrm{Tor}(G)$ is an injective $\mathbb{Z}$-module by theorem 17.3.5(2), so the short exact sequence $0 \to \mathrm{Tor}(G) \to G \to G/\mathrm{Tor}(G) \to 0$ splits by theorem 17.3.4(3), and the complement is isomorphic to $G/\mathrm{Tor}(G)$.

The two factors are now treated separately. The quotient turns out to carry a structure it had no right to expect.

Lemma 17.4.5: Structure of $G/\mathrm{Tor}(G)$

Let G be a divisible abelian group. Then $G/\mathrm{Tor}(G)$ carries a unique structure of $\mathbb{Q}$-vector space compatible with its addition, and consequently

$$G/\mathrm{Tor}(G) \cong \bigoplus_{i \in I} \mathbb{Q}$$

for some index set I.

***Proof*:**
Write $A = G/\mathrm{Tor}(G)$.

Step 1: A is torsion-free. This holds for every abelian group G. If $n\overline{x} = \overline{0}$ with $n \geq 1$, then $nx \in \mathrm{Tor}(G)$, so $m(nx) = 0$ for some $m \geq 1$. Then $(mn)x = 0$ with $mn \geq 1$, so $x \in \mathrm{Tor}(G)$ and $\overline{x} = \overline{0}$.

Step 2: A is divisible, being a quotient of the divisible group G (example 17.3.8(2)).

Step 3: division is unambiguous. If $ny = ny'$ with $n \geq 1$ then $n(y - y') = 0$, and A is torsion-free by Step 1, so $y = y'$. Combined with Step 2: for every $x \in A$ and $n \geq 1$ there is exactly one $y \in A$ with $ny = x$.

Step 4: the action. For $\frac{a}{b} \in \mathbb{Q}$ written with $b \geq 1$, and $x \in A$, define $\frac{a}{b} \cdot x$ to be the unique $y \in A$ with $by = ax$, which exists and is unique by Step 3.

This does not depend on the representative. If $\frac{a}{b} = \frac{a'}{b'}$ with $b, b' \geq 1$, so $ab' = a'b$, let y and y' be the elements produced by the two fractions. Then

$$bb'y = b'(by) = b'ax = a'bx = b(b'y') = bb'y'$$

and $bb' \geq 1$, so $y = y'$ by Step 3.

Step 5: the axioms. Write $y = \frac{a}{b}x$, $u = \frac{c}{d}x$ and $y_i = \frac{a}{b}x_i$, so $by = ax$, $du = cx$ and $by_i = ax_i$.

- Additivity in x: $b(y_1 + y_2) = ax_1 + ax_2 = a(x_1 + x_2)$, so $\frac{a}{b}(x_1 + x_2) = y_1 + y_2$.
- Additivity in the scalar: $bd(y + u) = d(by) + b(du) = dax + bcx = (ad + bc)x$, so $\frac{a}{b}x + \frac{c}{d}x = \frac{ad+bc}{bd}x$.
- Associativity: let $v = \frac{a}{b}u$, so $bv = au$. Then $bd\,v = d(bv) = dau = a(du) = acx$, so $\frac{a}{b}\left(\frac{c}{d}x\right) = \frac{ac}{bd}x$.
- Unit: $1 \cdot x$ is the unique y with $y = x$.

So A is a $\mathbb{Q}$-vector space, and the structure is unique because Step 3 leaves no choice about what $\frac{a}{b} \cdot x$ can be.

Step 6. By theorem 13.1.8 the vector space A has a basis, indexed by some set I, so $A \cong \bigoplus_{i \in I} \mathbb{Q}$.

The torsion factor is where the Prüfer groups appear, and the argument has three stages: break the torsion into primary pieces, check each piece is still divisible, and identify a divisible p-group.

Lemma 17.4.6: Structure of $\mathrm{Tor}(G)$

Let G be a divisible abelian group. Then

$$\mathrm{Tor}(G) \cong \bigoplus_{p \text{ prime}} \bigoplus_{i \in I_p} \mathbb{Z}_{p^\infty}$$

for index sets I_p.

***Proof*:**

Write $T = \mathrm{Tor}(G)$, which is divisible by lemma 17.4.4. For a prime p let

$$T_p = \left\{ x \in T \;\middle|\; p^k x = 0 \text{ for some } k \geq 0 \right\}$$

the *p-primary component*, a subgroup of T since $p^k x = p^l y = 0$ gives $p^{k+l}(x - y) = 0$.

Step 1: $T = \bigoplus_p T_p$. This holds for any torsion group. For the sum, let $x \in T$ have order $n = p_1^{n_1} \cdots p_k^{n_k}$ with the p_i distinct primes and $n_i \geq 1$, and set $q_i = n/p_i^{n_i}$. No prime divides every q_i, since p_j does not divide q_j, so $\gcd(q_1, \ldots, q_k) = 1$ and there are integers h_i with

$$h_1 q_1 + h_2 q_2 + \cdots + h_k q_k = 1 \tag{17.1}$$

Put $x_i = h_i q_i x$. Then $p_i^{n_i} x_i = h_i n x = 0$, so $x_i \in T_{p_i}$, and multiplying (17.1) by x gives $x = x_1 + \cdots + x_k$.

For directness, suppose $x \in T_p \cap \sum_{q \neq p} T_q$. Then $p^k x = 0$ for some k, so the order of x is a power of p. On the other hand $x = y_1 + \cdots + y_r$ with $y_j \in T_{q_j}$ for primes $q_j \neq p$, and each y_j has order a power of q_j, so the order of x divides a product of powers of primes different from p. A number that is both a power of p and coprime to p is 1, so $x = 0$.

Step 2: each T_p is divisible. Let $x \in T_p$ and $n \geq 1$. Since T is divisible there is a $y \in T$ with $ny = x$. Decompose $y = \sum_q y_q$ by Step 1. Then $x = ny = \sum_q n y_q$ with $n y_q \in T_q$, and x lies in

T_p, so uniqueness of the decomposition forces $ny_q = 0$ for $q \neq p$ and $ny_p = x$. As $y_p \in T_p$, this shows $nT_p = T_p$.

Step 3: a nonzero divisible p-group contains a copy of $\mathbb{Z}_{p^\infty}$. Let D be a nonzero divisible group in which every element has order a power of p, and pick $g \neq 0$, of order p^k with $k \geq 1$. Then $x_1 := p^{k-1}g$ has order exactly p. Using divisibility choose x_2 with $px_2 = x_1$, then x_3 with $px_3 = x_2$, and so on.

Each x_r has order exactly p^r: repeatedly applying $px_{i+1} = x_i$ gives $p^{r-1}x_r = x_1 \neq 0$ and $p^r x_r = px_1 = 0$. Also $x_r = px_{r+1} \in \langle x_{r+1}\rangle$, so the cyclic groups $\langle x_1\rangle \subseteq \langle x_2\rangle \subseteq \cdots$ form a chain, and $Z := \bigcup_r \langle x_r\rangle$ is a subgroup of D.

Define $\theta\colon Z \to \mathbb{Z}_{p^\infty}$ by $\theta(ax_r) = \left[\frac{a}{p^r}\right]$. It is well defined: if $ax_r = bx_s$ with $r \leq s$, then $x_r = p^{s-r}x_s$, so $(ap^{s-r} - b)x_s = 0$, so p^s divides $ap^{s-r} - b$, and therefore $\left[\frac{a}{p^r}\right] = \left[\frac{ap^{s-r}}{p^s}\right] = \left[\frac{b}{p^s}\right]$. It is a homomorphism by the same computation, surjective because every element of $\mathbb{Z}_{p^\infty}$ has the form $\left[\frac{a}{p^r}\right]$ (example 17.3.8(3)), and injective because $\theta(ax_r) = 0$ says $p^r \mid a$, which says $ax_r = 0$. So $Z \cong \mathbb{Z}_{p^\infty}$.

Step 4: a divisible p-group is a direct sum of copies of $\mathbb{Z}_{p^\infty}$. Let D be such a group and let $\mathcal{T}$ be the set of families of subgroups of D, each member of each family isomorphic to $\mathbb{Z}_{p^\infty}$, whose sum inside D is direct. Order $\mathcal{T}$ by inclusion of families. It contains the empty family. A chain has the union of its families as an upper bound, which is again in $\mathcal{T}$ because directness is a condition on finitely many members at a time, and any finitely many members of the union already lie in one family of the chain. By Zorn's lemma (theorem A.2.3) there is a maximal family $\{Z_j\}_{j\in J}$. Put $H = \bigoplus_{j\in J} Z_j \subseteq D$.

The group H is divisible, being a direct sum of divisible groups (example 17.3.8(4)), hence injective, so $D = H \oplus K$ for some K by theorem 17.3.4(3). The complement K is divisible: given $x \in K$ and $n \geq 1$, divisibility of D gives $d = h + k$ with $nd = x$, and comparing components in $H \oplus K$ gives $nh = 0$ and $nk = x$. Every element of K has order a power of p, so if $K \neq 0$ then Step 3 gives a subgroup $Z \subseteq K$ isomorphic to $\mathbb{Z}_{p^\infty}$. Since $H \cap K = 0$, the family $\{Z_j\}_{j\in J} \cup \{Z\}$ is again in $\mathcal{T}$ and strictly larger, contradicting maximality. So $K = 0$ and $D = H$.

Applying Steps 2 and 4 to each T_p and assembling with Step 1 gives the statement.

Theorem 17.4.7: Classification of Divisible Groups

Let G be a divisible abelian group. Then there are index sets I and I_p, one for each prime p, with

$$G \cong \left(\bigoplus_{p \text{ prime}} \bigoplus_{i\in I_p} \mathbb{Z}_{p^\infty} \right) \oplus \bigoplus_{i\in I} \mathbb{Q}$$

The cardinalities of these index sets are determined by G, namely

$$|I| = \dim_{\mathbb{Q}}\big(G/\mathrm{Tor}(G)\big) \qquad \text{and} \qquad |I_p| = \dim_{\mathbb{F}_p} G[p], \quad \text{where } G[p] = \{g \in G \mid pg = 0\}$$

Since divisible and injective agree over $\mathbb{Z}$ (theorem 17.3.5(2)), this classifies the injective $\mathbb{Z}$-modules.

***Proof*:**
Existence. By lemma 17.4.4, $G \cong \mathrm{Tor}(G) \oplus G/\mathrm{Tor}(G)$. Lemma 17.4.6 identifies the first summand and lemma 17.4.5 the second.

The invariants. Suppose $G \cong \left(\bigoplus_{p \text{ prime}} \bigoplus_{i \in I_p} \mathbb{Z}_{p^\infty}\right) \oplus \bigoplus_{i \in I} \mathbb{Q}$. Each $\mathbb{Z}_{p^\infty}$ is a torsion group and each copy of $\mathbb{Q}$ is torsion-free, so the torsion subgroup of the right-hand side is exactly the first bracket, and

$$G/\mathrm{Tor}(G) \cong \bigoplus_{i \in I} \mathbb{Q}$$

which is a $\mathbb{Q}$-vector space with a basis indexed by I. Since G determines $\mathrm{Tor}(G)$ and hence $G/\mathrm{Tor}(G)$ up to isomorphism, and the cardinality of a basis is an invariant of a vector space (lemma 14.1.1 and the remark following it), $|I|$ is determined by G.

For the primary invariants, note that $G[p]$ is killed by p and so is a vector space over $\mathbb{F}_p$, and that forming $G[p]$ commutes with direct sums, an element of a direct sum being killed by p exactly when each of its components is. Now

$$\mathbb{Q}[p] = 0, \qquad \mathbb{Z}_{q^\infty}[p] = 0 \text{ for } q \neq p, \qquad \mathbb{Z}_{p^\infty}[p] = \left\{ \left[\frac{a}{p}\right] \;\middle|\; a \in \mathbb{Z} \right\} \cong \mathbb{Z}/p\mathbb{Z}$$

The first holds because $\mathbb{Q}$ is torsion-free; the second because every element of $\mathbb{Z}_{q^\infty}$ has order a power of q, and no nonzero such order is divisible by p; the third because $p\left[\frac{a}{p^n}\right] = 0$ forces $p^{n-1} \big| a$, so the element is $\left[\frac{b}{p}\right]$ for some b. Therefore

$$G[p] \cong \bigoplus_{i \in I_p} \mathbb{Z}/p\mathbb{Z}$$

an $\mathbb{F}_p$-vector space with a basis indexed by I_p. As G determines $G[p]$, the cardinality $|I_p|$ is determined by G.

Exercise 17.4.1

1. Compute dG, the largest divisible subgroup, for each of the following.
    1. $G = \mathbb{Z}$
    2. $G = \mathbb{Q}$
    3. $G = \mathbb{Q} \oplus \mathbb{Z}$
    4. $G = \mathbb{Z}/6\mathbb{Z}$
    5. $G = \mathbb{Q}/\mathbb{Z}$
2. Decide which of the following are divisible, and justify each answer.
    1. $\mathbb{R}$ under addition
    2. $\mathbb{R}/\mathbb{Z}$ under addition
    3. $\mathbb{C}^\times$ under multiplication
    4. $\mathbb{Z}[1/p]$ under addition, for a prime p

5. $\mathbb{Q}^\times$ under multiplication

3. For each of the following divisible groups, compute the invariants $|I|$ and $|I_p|$ of theorem 17.4.7.
   1. $\mathbb{Q}/\mathbb{Z}$
   2. $\mathbb{Q} \oplus \mathbb{Q}/\mathbb{Z}$
   3. $\mathbb{Z}_{p^\infty} \oplus \mathbb{Z}_{p^\infty}$
   4. $\mathbb{R}$ under addition. *Hint*: compare cardinalities.

4. Show that $\mathbb{Z}_{p^\infty} \cong \mathbb{Z}[1/p]/\mathbb{Z}$, and that the proper subgroups of $\mathbb{Z}_{p^\infty}$ are exactly the finite cyclic groups $\langle \left[\frac{1}{p^n}\right] \rangle \cong \mathbb{Z}/p^n\mathbb{Z}$ for $n \geq 0$, totally ordered by inclusion. Deduce that $\mathbb{Z}_{p^\infty}$ has no maximal subgroup.

5. Show that every homomorphism $f\colon G \to H$ of abelian groups satisfies $f(dG) \subseteq dH$, and that $G \mapsto dG$ is therefore a functor $\mathbf{Ab} \to \mathbf{Ab}$. *Hint*: the image of a divisible group is divisible.

6. Show that a nonzero divisible group has no maximal subgroup. *Hint*: if M were maximal, G/M would be a simple abelian group, hence $\mathbb{Z}/p\mathbb{Z}$ for some prime p. But G/M is divisible. Deduce that no nonzero divisible group is finitely generated, recovering example 17.3.8(5).

17.5 Flat Modules

The third functor available on a short exact sequence is the tensor product. Fix a right R-module D and apply $D \otimes_R -$, which theorem 15.2.2 turns into a covariant functor from left R-modules to abelian groups, landing in left S-modules when D is an (S, R)-bimodule. Everything below is stated for $D \otimes_R -$. The functor $- \otimes_R D$ on right modules behaves identically, with left and right exchanged throughout.

This functor fails at the opposite end from the two in section 17.2 and section 17.3. Both Hom functors are left exact and can lose surjectivity. Tensoring is *right* exact and can lose injectivity. The reason is the Hom-tensor adjunction of theorem 15.3.9: $D \otimes_R -$ is a left adjoint, and left adjoints preserve the constructions that sit at the right-hand end of a sequence.

Theorem 17.5.1: $D \otimes_R -$ Is Right Exact

Let D be a right R-module and let

$$0 \to L \xrightarrow{\psi} M \xrightarrow{\varphi} N \to 0$$

be a short exact sequence of left R-modules. Then

$$D \otimes_R L \xrightarrow{1\otimes\psi} D \otimes_R M \xrightarrow{1\otimes\varphi} D \otimes_R N \to 0$$

is an exact sequence of abelian groups, and of left S-modules when D is an (S, R)-bimodule. The map $1 \otimes \psi$ need not be injective.

***Proof*:**
Surjectivity of $1 \otimes \varphi$. By lemma 15.1.4(2) every element of $D \otimes_R N$ is a finite sum $\sum_i d_i \otimes n_i$. Each n_i is $\varphi(m_i)$ for some m_i, since φ is surjective, so the element is the image of $\sum_i d_i \otimes m_i$.

$\operatorname{im}(1 \otimes \psi) \subseteq \ker(1 \otimes \varphi)$. By theorem 15.2.2 the composite $(1 \otimes \varphi) \circ (1 \otimes \psi)$ is $1 \otimes (\varphi \circ \psi)$, and $\varphi \circ \psi = 0$ because $\operatorname{im}(\psi) = \ker(\varphi)$.

$\ker(1 \otimes \varphi) \subseteq \operatorname{im}(1 \otimes \psi)$. Write $I = \operatorname{im}(1 \otimes \psi)$. By the previous paragraph $1 \otimes \varphi$ kills I, so it factors as

$$\overline{\varphi} \colon (D \otimes_R M)/I \to D \otimes_R N, \qquad \overline{\varphi}\big(\overline{d \otimes m}\big) = d \otimes \varphi(m)$$

by theorem 12.2.10. It suffices to produce an inverse, for then $\overline{\varphi}$ is injective, which says exactly that $\ker(1 \otimes \varphi) = I$.

Define $\beta \colon D \times N \to (D \otimes_R M)/I$ by $\beta(d, n) = \overline{d \otimes m}$ for any m with $\varphi(m) = n$. This does not depend on the choice: if $\varphi(m) = \varphi(m')$ then $m - m' \in \ker(\varphi) = \operatorname{im}(\psi)$, say $m - m' = \psi(l)$, and then

$$d \otimes m - d \otimes m' = d \otimes \psi(l) = (1 \otimes \psi)(d \otimes l) \in I$$

The map β is R-balanced in the sense of definition 15.1.1: it is additive in d because $\otimes$ is; it is additive in n because a lift of $n + n'$ may be taken to be $m + m'$; and $\beta(dr, n) = \overline{dr \otimes m} = \overline{d \otimes rm} = \beta(d, rn)$, since rm is a lift of rn and by the third relation of (15.1).

By theorem 15.1.5 there is a homomorphism $\overline{\beta} \colon D \otimes_R N \to (D \otimes_R M)/I$ with $\overline{\beta}(d \otimes n) = \overline{d \otimes m}$. Both composites fix every simple tensor, hence are the identity by lemma 15.1.4(3), so $\overline{\varphi}$ is an isomorphism.

Now the failure at the left, computed before anything is named after it, on the same sequence that example 17.2.2 and example 17.3.2 used.

Example 17.5.2: $D \otimes_R -$ Need Not Be Left Exact

1. Take $R = \mathbb{Z}$, the short exact sequence $0 \to \mathbb{Z} \xrightarrow{\cdot 2} \mathbb{Z} \xrightarrow{\pi} \mathbb{Z}/2\mathbb{Z} \to 0$, and $D = \mathbb{Z}/2\mathbb{Z}$. Since $A \otimes_{\mathbb{Z}} \mathbb{Z} \cong A$ for every A, and $\mathbb{Z}/2\mathbb{Z} \otimes_{\mathbb{Z}} \mathbb{Z}/2\mathbb{Z} \cong \mathbb{Z}/2\mathbb{Z}$ by proposition 15.2.13, applying $D \otimes_{\mathbb{Z}} -$ gives

   $$\mathbb{Z}/2\mathbb{Z} \xrightarrow{1 \otimes (\cdot 2)} \mathbb{Z}/2\mathbb{Z} \xrightarrow{1 \otimes \pi} \mathbb{Z}/2\mathbb{Z} \to 0$$

   The first map is zero: for $\overline{a} \in \mathbb{Z}/2\mathbb{Z}$ and $x \in \mathbb{Z}$,

   $$\overline{a} \otimes 2x = \overline{a} \cdot 2 \otimes x = \overline{0} \otimes x = 0$$

   So the sequence is exact where theorem 17.5.1 promises and fails to be exact at the left, the first map being zero on a group of order two.

2. The sharpest version replaces the middle term. The inclusion $\mathbb{Z} \hookrightarrow \mathbb{Q}$ is injective, but $\mathbb{Z}/2\mathbb{Z} \otimes_{\mathbb{Z}} \mathbb{Q} = 0$, since

   $$\overline{a} \otimes q = \overline{a} \otimes 2 \cdot \tfrac{q}{2} = \overline{a} \cdot 2 \otimes \tfrac{q}{2} = 0$$

   for every q. So $1 \otimes \iota$ maps $\mathbb{Z}/2\mathbb{Z} \otimes_{\mathbb{Z}} \mathbb{Z} \cong \mathbb{Z}/2\mathbb{Z}$ to the zero group, and injectivity fails as badly as it can.

Proposition 17.5.3: Conditions for $A \otimes_R -$ to Be Exact

Let A be a right R-module. The following are equivalent.

1. For every short exact sequence $0 \to L \xrightarrow{\psi} M \xrightarrow{\varphi} N \to 0$ of left R-modules, the sequence
$$0 \to A \otimes_R L \xrightarrow{1\otimes\psi} A \otimes_R M \xrightarrow{1\otimes\varphi} A \otimes_R N \to 0$$
is short exact.
2. For every injective homomorphism $\psi\colon L \to M$ of left R-modules, the map $1 \otimes \psi\colon A \otimes_R L \to A \otimes_R M$ is injective.

***Proof*:**

(1) $\Rightarrow$ (2). Given ψ injective, put $N = M/\psi(L)$, so that $0 \to L \xrightarrow{\psi} M \to N \to 0$ is short exact by proposition 17.1.1 and theorem 12.2.10. Condition (1) makes $1 \otimes \psi$ injective.

(2) $\Rightarrow$ (1). Theorem 17.5.1 gives exactness at $A \otimes_R M$ and at $A \otimes_R N$, and (2) gives injectivity of $1 \otimes \psi$, which is exactness at $A \otimes_R L$ by proposition 17.1.1.

Definition 17.5.4: Flat Module

A right R-module A is *flat* if it satisfies the equivalent conditions of proposition 17.5.3, that is if the functor $A \otimes_R -$ is exact. A left R-module is *flat* when the corresponding statement holds for $- \otimes_R A$.

The side matters only because $\otimes_R$ does. Over a commutative ring the two notions coincide, by proposition 15.2.7, and the qualification can be dropped.

Corollary 17.5.5: Projective Modules Are Flat

Every free R-module is flat, and more generally every projective R-module is flat.

***Proof*:**

First, R itself is flat: the map $R \otimes_R L \to L$ sending $r \otimes l$ to rl is an isomorphism with inverse $l \mapsto 1 \otimes l$, and under it $1 \otimes \psi$ becomes ψ, so $1 \otimes \psi$ is injective whenever ψ is.

Next let $F = \bigoplus_{i\in I} R$ be free. By theorem 15.2.4 there are isomorphisms $F \otimes_R L \cong \bigoplus_{i\in I}(R \otimes_R L) \cong \bigoplus_{i\in I} L$, and similarly for M, carrying $1 \otimes \psi$ to the map $\bigoplus_i \psi$ acting coordinatewise. A direct sum of injective maps is injective, so F is flat.

Finally let P be projective. By theorem 17.2.4(4) there is a free module F and a module K with $F \cong P \oplus K$. By theorem 15.2.3,
$$F \otimes_R L \cong (P \otimes_R L) \oplus (K \otimes_R L)$$
compatibly with M in place of L, and under these identifications $1_F \otimes \psi$ is $(1_P \otimes \psi) \oplus (1_K \otimes \psi)$. A direct sum of maps is injective only if each summand is, so injectivity of $1_F \otimes \psi$ forces injectivity of $1_P \otimes \psi$.

So free implies projective implies flat, and both implications are strict: example 17.2.7 exhibits projective modules that are not free, and example 17.5.8 exhibits a flat $\mathbb{Z}$-module that is not projective. Over a principal ideal domain there is a criterion for flatness as concrete as Baer's is for injectivity.

Proposition 17.5.6: Flat Implies Torsion-Free

Let R be an integral domain and A a flat R-module. Then A is torsion-free.

***Proof*:**
Let $r \in R$ be nonzero. Multiplication by r is an injective R-module homomorphism $R \to R$, since R is a domain, so flatness makes $1 \otimes (\cdot r) \colon A \otimes_R R \to A \otimes_R R$ injective. The map $A \otimes_R R \to A$ sending $a \otimes r$ to ar is an isomorphism, with inverse $a \mapsto a \otimes 1$, and it carries $1 \otimes (\cdot r)$ to multiplication by r on A. Hence $ra = 0$ forces $a = 0$, and A has no nonzero torsion element.

Theorem 17.5.7: Flat Equals Torsion-Free Over a PID

Let R be a principal ideal domain and A an R-module. Then A is flat if and only if A is torsion-free.

***Proof*:**
One direction is proposition 17.5.6, which needs only that R is a domain.

For the converse let A be torsion-free, let $\psi \colon L \to M$ be an injective homomorphism, and let $\xi \in A \otimes_R L$ satisfy $(1 \otimes \psi)(\xi) = 0$. Write $\xi = \sum_{i=1}^{k} a_i \otimes l_i$ using lemma 15.1.4(2), so that

$$\sum_{i=1}^{k} a_i \otimes \psi(l_i) = 0 \qquad \text{in } A \otimes_R M$$

Step 1: pass to a finitely generated piece. By lemma 15.2.12 there is a finitely generated submodule $A_0 \subseteq A$ containing $a_1, \dots, a_k$ with

$$\sum_{i=1}^{k} a_i \otimes \psi(l_i) = 0 \qquad \text{in } A_0 \otimes_R M$$

Step 2: A_0 is flat. A submodule of a torsion-free module is torsion-free, so A_0 is a finitely generated torsion-free module over a principal ideal domain, hence free by theorem 14.1.9(2), hence flat by corollary 17.5.5.

Step 3: conclude. The map $1_{A_0} \otimes \psi \colon A_0 \otimes_R L \to A_0 \otimes_R M$ is therefore injective, and Step 1 says it kills the element $\sum_i a_i \otimes l_i$ of $A_0 \otimes_R L$. So that element is zero in $A_0 \otimes_R L$, and its image under the map $A_0 \otimes_R L \to A \otimes_R L$ induced by the inclusion is ξ. Hence $\xi = 0$, and $1 \otimes \psi$ is injective.

Example 17.5.8: Flat Modules

Throughout, $R = \mathbb{Z}$ unless stated otherwise, so theorem 17.5.7 applies and flat means torsion-free.

1. $\mathbb{Z}$ is flat, being free. For $n \geq 2$ the module $\mathbb{Z}/n\mathbb{Z}$ is not flat, having $\overline{1}$ as a torsion element. Example 17.5.2(1) is that failure for $n = 2$, seen directly.
2. $\mathbb{Q}$ is a flat $\mathbb{Z}$-module, being torsion-free. It is *not* projective, by example 17.2.10(5). So the implication projective $\Rightarrow$ flat is strict, and flatness is genuinely weaker than the other two conditions of this chapter.
3. $\mathbb{Q}/\mathbb{Z}$ is an injective $\mathbb{Z}$-module (example 17.3.10(2)) but is not flat, being a nonzero torsion group. So injective does not imply flat.
4. $\mathbb{Q} \oplus \mathbb{Z}$ is torsion-free, hence flat. It is not projective: a direct summand of a projective module is projective, being a summand of a summand of a free module, and $\mathbb{Q}$ is not projective. It is not injective either, since a direct summand of an injective module is injective by proposition 17.3.9(1) and $\mathbb{Z}$ is not injective (example 17.3.10(1)).
5. A direct sum $\bigoplus_i A_i$ is flat if and only if every A_i is, by the computation in the proof of corollary 17.5.5 applied to theorem 15.2.4.
6. Over a field every module is free (theorem 13.1.8), hence flat. Over a field, free, projective, injective and flat all coincide.
7. Let R be a principal ideal domain and $D \subseteq R \setminus \{0\}$ a multiplicatively closed set containing 1. The ring of fractions $D^{-1}R$ of section 9.5 sits inside the field of fractions of R, which is torsion-free as an R-module, so $D^{-1}R$ is a torsion-free and therefore flat R-module. That localization is flat holds over any commutative ring, and is taken up in *Commutative Algebra*.[a]

[a] proposition 23.4.9 and proposition 23.4.10.

Corollary 17.5.9: Tensor Products of Projective Modules

Let R be a commutative ring and let P and Q be projective R-modules. Then $P \otimes_R Q$ is projective.

***Proof*:**

Choose P' and Q' with $P \oplus P' = F$ and $Q \oplus Q' = G$ free, using theorem 17.2.4(4). Then $F \otimes_R G$ is free by corollary 15.2.6, and theorem 15.2.3 expands it as

$$F \otimes_R G \cong (P \otimes_R Q) \oplus (P \otimes_R Q') \oplus (P' \otimes_R Q) \oplus (P' \otimes_R Q')$$

So $P \otimes_R Q$ is a direct summand of a free module and theorem 17.2.4(4) applies.

A ring homomorphism $R \to S$ making S flat as an R-module is called a *flat extension*, and the condition is what allows a construction performed over R to be transported to S without losing exactness. Example 17.5.8(7) is the first example. Flat extensions, the local criterion that detects flatness one prime at a time, and the geometric reading of flatness as a family of fibres varying continuously all belong with commutative algebra and are developed in *Commutative Algebra* [20].

Exercise 17.5.1

1. Decide whether each module is flat over the indicated ring, and justify.
   1. $\mathbb{Z}/6\mathbb{Z}$ over $\mathbb{Z}$
   2. $\mathbb{Q}$ over $\mathbb{Z}$
   3. $\mathbb{Z}[1/2]$ over $\mathbb{Z}$
   4. $\mathbb{Z}/2\mathbb{Z}$ over $\mathbb{Z}/6\mathbb{Z}$
   5. $k[x]/(x)$ over $k[x]$, for a field k
2. Let $m, n \geq 1$ and $d = \gcd(m, n)$. Using $\mathbb{Z}/m\mathbb{Z} \otimes_{\mathbb{Z}} \mathbb{Z}/n\mathbb{Z} \cong \mathbb{Z}/d\mathbb{Z}$ (proposition 15.2.13), show directly that $\mathbb{Z}/2\mathbb{Z}$ is not a flat $\mathbb{Z}$-module, by tensoring the injection $\mathbb{Z}/2\mathbb{Z} \to \mathbb{Z}/4\mathbb{Z}$, $\overline{a} \mapsto \overline{2a}$, with $\mathbb{Z}/2\mathbb{Z}$ and computing both sides.
3. Show that a direct sum $\bigoplus_{i \in I} A_i$ of right R-modules is flat if and only if every A_i is flat.
4. Let R be a principal ideal domain.
   1. Show that every submodule of a flat R-module is flat.
   2. Show that a quotient of a flat R-module need not be flat, by exhibiting a surjection from a flat $\mathbb{Z}$-module onto a non-flat one.
5. Let R be a commutative ring and let A and B be flat R-modules. Show that $A \otimes_R B$ is flat. *Hint*: theorem 15.2.8 identifies $(A \otimes_R B) \otimes_R L$ with $A \otimes_R (B \otimes_R L)$.
6. Show that every element of $M \otimes_R N$ lies in the image of $M_0 \otimes_R N_0 \to M \otimes_R N$ for some finitely generated submodules $M_0 \subseteq M$ and $N_0 \subseteq N$. *Hint*: lemma 15.1.4(2). Explain why this is weaker than lemma 15.2.12, and why the weaker statement would not suffice in the proof of theorem 17.5.7.
7. Assemble the three strictness witnesses of this chapter into one picture. Exhibit $\mathbb{Z}$-modules, or modules over a ring of your choice, showing that each of the implications

   $$\text{free} \Rightarrow \text{projective} \Rightarrow \text{flat}$$

   is strict, and that neither implication holds between injective and flat in either direction.

17.6 Ext and Tor

Section 17.1 asked for $\mathcal{E}(C, A)$, the set of equivalence classes of extensions of C by A, and everything since has been about the three functors that a short exact sequence can be pushed through. Each is exact at one end and can fail at the other. Writing $0 \to A \to B \to C \to 0$ for a short exact sequence and D for a fixed module, proposition 17.2.1, proposition 17.3.1 and theorem 17.5.1 say

$$0 \to \mathrm{Hom}_R(D, A) \to \mathrm{Hom}_R(D, B) \to \mathrm{Hom}_R(D, C)$$
$$0 \to \mathrm{Hom}_R(C, D) \to \mathrm{Hom}_R(B, D) \to \mathrm{Hom}_R(A, D)$$
$$A \otimes_R D \to B \otimes_R D \to C \otimes_R D \to 0$$

and in each case the missing end is missing for a reason: something is there, and it is not zero. This section names it. The construction is given in full and the computations below are unconditional, but three of the theorems are stated without proof, because their proofs need machinery that this book does not build. Where that happens it is said explicitly, and the reason is given.

17.6.1 Complexes and Their Homology

Definition 12.2.11 defined an *exact* chain complex. What is needed here is the same object without the exactness, together with a measure of how far from exact it is.

Definition 17.6.1: Chain Complex and Homology

A *chain complex* of R-modules is a family $(M_i)_{i\in\mathbb{Z}}$ together with homomorphisms $d_i\colon M_i \to M_{i-1}$ satisfying $d_i \circ d_{i+1} = 0$ for every i, equivalently $\operatorname{im}(d_{i+1}) \subseteq \ker(d_i)$. Its *$i$-th homology* is the quotient module

$$H_i(M_\bullet) := \ker(d_i)/\operatorname{im}(d_{i+1})$$

A *cochain complex* is the same data with the arrows reversed, $d^i\colon M^i \to M^{i+1}$ and $d^{i+1}\circ d^i = 0$, and its *i-th cohomology* is $H^i(M^\bullet) := \ker(d^i)/\operatorname{im}(d^{i-1})$.

So a complex is exact at M_i exactly when $H_i(M_\bullet) = 0$, and the homology records the failure one degree at a time. This is the whole of the apparatus needed below. The theory of complexes proper is *Homological Algebra* [29].

17.6.2 The Construction

Fix an R-module M and choose a projective resolution of it, which exists by example 17.1.4(3) and corollary 17.2.6: an exact complex

$$\cdots \to P_2 \xrightarrow{d_2} P_1 \xrightarrow{d_1} P_0 \xrightarrow{\varepsilon} M \to 0$$

with every P_i projective. Deleting M leaves the complex $P_\bullet$, which is no longer exact at P_0. Its homology there is M itself. Now apply one of the three functors to $P_\bullet$ and take homology.

Definition 17.6.2: Tor

Let R be a ring, M a right R-module with a chosen projective resolution $P_\bullet$, and N a left R-module. The complex $P_\bullet \otimes_R N$ has differentials $d_i \otimes 1$ and satisfies $(d_i \otimes 1)(d_{i+1} \otimes 1) = (d_i d_{i+1}) \otimes 1 = 0$ by theorem 15.2.2, so it is a chain complex. Define

$$\operatorname{Tor}_i^R(M,N) := H_i\big(P_\bullet \otimes_R N\big) = \ker(d_i \otimes 1)/\operatorname{im}(d_{i+1} \otimes 1)$$

Definition 17.6.3: Ext

With M, $P_\bullet$ as above and N any R-module, the family $\operatorname{Hom}_R(P_i, N)$ with the maps d_{i+1}^* is a cochain complex, since $d_{i+1}^* d_i^* = (d_i d_{i+1})^* = 0$. Define

$$\operatorname{Ext}_R^i(M,N) := H^i\big(\operatorname{Hom}_R(P_\bullet, N)\big) = \ker(d_{i+1}^*)/\operatorname{im}(d_i^*)$$

17.6.4 Two Meanings of Tor The symbol Tor now carries two jobs. Definition 12.3.18 wrote $\mathrm{Tor}_R(M)$, or $\mathrm{Tor}(M)$, for the torsion submodule of M, and definition 17.6.2 writes $\mathrm{Tor}_i^R(M,N)$ for the module just constructed. The subscript decides: an *integer* index means the functor of this section, a *ring* means the torsion submodule, and the functor always takes two arguments. The collision is standard in the literature, and proposition 17.6.7 shows that $\mathrm{Tor}_1^{\mathbb{Z}}(\mathbb{Z}/n\mathbb{Z}, A)$ is the subgroup of A killed by n, so the derived functor really is measuring torsion.

The definitions depend on a choice, and nothing so far says the answer does not. It does not, and that is the first of the three deferred theorems.

Theorem 17.6.5: The Derived Functors Are Well Defined

Let R be a ring and M, N be R-modules.

1. $\mathrm{Tor}_i^R(M,N)$ and $\mathrm{Ext}^i_R(M,N)$ do not depend on the choice of projective resolution of M, up to isomorphism.
2. For Tor, a resolution by flat modules (definition 17.5.4) may be used in place of a projective one, with the same result.
3. $\mathrm{Tor}_i^R(M,N)$ may equally be computed from a projective resolution of the second argument N, and $\mathrm{Ext}^i_R(M,N)$ from an *injective* resolution (definition 17.3.15) of N, in both cases giving the same module.

The proofs are omitted here, and the reason is a genuine gap rather than an economy: all three rest on the comparison theorem, which lifts a map of modules to a map of resolutions uniquely up to chain homotopy, and on the fact that chain homotopic maps induce the same map on homology. Neither statement is available in this book, both being about complexes rather than modules, and they are proved in *Homological Algebra* [29, Unique Projection Resolution, Chain-Homotopy and Cohomology]. Proposition 17.2.12 is the degree-one instance of the comparison theorem: two projective presentations of the same module differ by a free summand, which is why the degree-one answer cannot depend on the presentation.

Every computation below fixes one explicit resolution, so each is a complete calculation on its own terms. Theorem 17.6.5 is what upgrades it from a statement about that resolution to a statement about M.

Proposition 17.6.6: Degree Zero

Let M and N be R-modules. Then

$$\mathrm{Tor}_0^R(M,N) \cong M \otimes_R N \qquad \text{and} \qquad \mathrm{Ext}^0_R(M,N) \cong \mathrm{Hom}_R(M,N)$$

***Proof*:**

Let $P_\bullet \to M$ be a projective resolution. Exactness at P_0 says $P_1 \xrightarrow{d_1} P_0 \xrightarrow{\varepsilon} M \to 0$ is exact.

For Tor, apply $- \otimes_R N$. By theorem 17.5.1 the sequence $P_1 \otimes N \to P_0 \otimes N \to M \otimes N \to 0$ is exact, so $\varepsilon \otimes 1$ identifies $(P_0 \otimes N)/\mathrm{im}(d_1 \otimes 1)$ with $M \otimes_R N$. Since $d_0 = 0$ in the deleted

complex, $\ker(d_0 \otimes 1) = P_0 \otimes N$ and the left-hand side is exactly $\operatorname{Tor}_0^R(M,N)$.

For Ext, apply $\operatorname{Hom}_R(-,N)$. By proposition 17.3.1 the sequence $0 \to \operatorname{Hom}_R(M,N) \xrightarrow{\varepsilon^*} \operatorname{Hom}_R(P_0,N) \xrightarrow{d_1^*} \operatorname{Hom}_R(P_1,N)$ is exact, so ε^* is an isomorphism onto $\ker(d_1^*)$. Since $d_0^* = 0$, that kernel is exactly $\operatorname{Ext}_R^0(M,N)$.

Proposition 17.6.7: Ext and Tor of a Cyclic Group

Let $n \geq 1$ and let A be an abelian group. Write $A[n] = \{a \in A \mid na = 0\}$. Then, as abelian groups,

$$\operatorname{Ext}^i_{\mathbb{Z}}(\mathbb{Z}/n\mathbb{Z}, A) \cong \begin{cases} A[n] & i = 0 \\ A/nA & i = 1 \\ 0 & i \geq 2 \end{cases} \qquad \operatorname{Tor}_i^{\mathbb{Z}}(\mathbb{Z}/n\mathbb{Z}, A) \cong \begin{cases} A/nA & i = 0 \\ A[n] & i = 1 \\ 0 & i \geq 2 \end{cases}$$

***Proof*:**

The sequence $0 \to \mathbb{Z} \xrightarrow{\cdot n} \mathbb{Z} \xrightarrow{\pi} \mathbb{Z}/n\mathbb{Z} \to 0$ of example 17.1.6 is a projective resolution of $\mathbb{Z}/n\mathbb{Z}$, since $\mathbb{Z}$ is free: take $P_0 = P_1 = \mathbb{Z}$, $d_1 = \cdot n$, and $P_i = 0$ for $i \geq 2$. The deleted complex is

$$0 \to \mathbb{Z} \xrightarrow{\cdot n} \mathbb{Z} \to 0$$

concentrated in degrees 1 and 0.

Every homomorphism $\mathbb{Z} \to A$ is determined by the image of 1, so $\operatorname{Hom}_{\mathbb{Z}}(\mathbb{Z}, A) \cong A$ by $h \mapsto h(1)$, and under this identification $d_1^* = (\cdot n)^*$ is multiplication by n on A, since $(h \circ (\cdot n))(1) = h(n) = n\,h(1)$. Likewise $\mathbb{Z} \otimes_{\mathbb{Z}} A \cong A$ by $x \otimes a \mapsto xa$, and $d_1 \otimes 1$ becomes multiplication by n. Both functors therefore turn the deleted complex into

$$0 \to A \xrightarrow{\cdot n} A \to 0$$

with A in degrees 1 and 0 for Tor, and in degrees 0 and 1 for Ext, the arrows of a cochain complex running the other way.

Reading off homology: the kernel of multiplication by n is $A[n]$ and its cokernel is A/nA, and every other module in the complex is zero. For Tor this gives $\operatorname{Tor}_1 = \ker(\cdot n) = A[n]$ and $\operatorname{Tor}_0 = A/nA$. For Ext it gives $\operatorname{Ext}^0 = \ker(\cdot n) = A[n]$ and $\operatorname{Ext}^1 = A/nA$. All higher terms vanish because $P_i = 0$ for $i \geq 2$.

The two degree-zero answers agree with proposition 17.6.6: $\operatorname{Hom}_{\mathbb{Z}}(\mathbb{Z}/n\mathbb{Z}, A)$ is the set of elements of A killed by n, and $\mathbb{Z}/n\mathbb{Z} \otimes_{\mathbb{Z}} A \cong A/nA$ by proposition 15.2.13. Specialising the degree-one answers,

$$\operatorname{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/m\mathbb{Z},\, \mathbb{Z}/n\mathbb{Z}) \cong \mathbb{Z}/\gcd(m,n)\mathbb{Z}, \qquad \operatorname{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/n\mathbb{Z},\, \mathbb{Z}) \cong \mathbb{Z}/n\mathbb{Z}, \qquad \operatorname{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/n\mathbb{Z},\, \mathbb{Q}) = 0$$

the last because $\mathbb{Q} = n\mathbb{Q}$.

Corollary 17.6.8: Vanishing

Let $i \geq 1$.

1. If P is projective then $\operatorname{Ext}^i_R(P, N) = 0$ and $\operatorname{Tor}^R_i(P, N) = 0$ for every N.
2. If F is flat then $\operatorname{Tor}^R_i(M, F) = 0$ for every M.

***Proof*:**
(1) A projective module is its own projective resolution: take $P_0 = P$, $\varepsilon = \mathrm{id}_P$ and $P_i = 0$ for $i \geq 1$, which is exact. The deleted complex has a single nonzero term in degree 0, so every functor applied to it has vanishing homology in degrees $i \geq 1$.

(2) Let $P_\bullet \to M$ be a projective resolution, so the complex $\cdots \to P_1 \to P_0 \to M \to 0$ is exact. Since F is flat, applying $- \otimes_R F$ preserves that exactness, by proposition 17.5.3 applied at each spot. So $P_\bullet \otimes_R F$ is exact except in degree 0, which is to say $\operatorname{Tor}^R_i(M, F) = 0$ for $i \geq 1$.

Part (2) is the sense in which flatness is the condition that makes Tor disappear, just as projectivity kills Ext in the first argument. The dual statement, that $\operatorname{Ext}^i_R(M, Q) = 0$ for Q injective, needs theorem 17.6.5(3): compute Ext from an injective resolution of Q, which may be taken to be Q itself.

17.6.3 What They Repair

Theorem 17.6.9: Long Exact Sequences

Let $0 \to A \to B \to C \to 0$ be a short exact sequence of R-modules and let D be an R-module. Then there are homomorphisms δ_i, δ'_i and ∂_i, called *connecting homomorphisms*, making the following sequences exact.

$$0 \to \operatorname{Hom}_R(D, A) \to \operatorname{Hom}_R(D, B) \to \operatorname{Hom}_R(D, C) \xrightarrow{\delta_0} \operatorname{Ext}^1_R(D, A) \to \cdots$$
$$\cdots \to \operatorname{Ext}^i_R(D, A) \to \operatorname{Ext}^i_R(D, B) \to \operatorname{Ext}^i_R(D, C) \xrightarrow{\delta_i} \operatorname{Ext}^{i+1}_R(D, A) \to \cdots$$

$$0 \to \operatorname{Hom}_R(C, D) \to \operatorname{Hom}_R(B, D) \to \operatorname{Hom}_R(A, D) \xrightarrow{\delta'_0} \operatorname{Ext}^1_R(C, D) \to \cdots$$
$$\cdots \to \operatorname{Ext}^i_R(C, D) \to \operatorname{Ext}^i_R(B, D) \to \operatorname{Ext}^i_R(A, D) \xrightarrow{\delta'_i} \operatorname{Ext}^{i+1}_R(C, D) \to \cdots$$

$$\cdots \to \operatorname{Tor}^R_i(C, D) \xrightarrow{\partial_i} \operatorname{Tor}^R_{i-1}(A, D) \to \operatorname{Tor}^R_{i-1}(B, D) \to \operatorname{Tor}^R_{i-1}(C, D) \to \cdots$$
$$\cdots \to A \otimes_R D \to B \otimes_R D \to C \otimes_R D \to 0$$

These are the sequences the section exists to produce: each short exact sequence, which the three functors truncate, is restored to an exact sequence by the derived functors, running off to infinity in the direction the functor was failing. The proofs are again omitted, and again for a reason that can be named: the connecting homomorphisms are built by the snake lemma applied to a short exact sequence of *complexes* rather than of modules, which is the general form of proposition 17.1.10, and that is developed in *Homological Algebra* [29, Snake Lemma].

Notice how the first sequence recovers a fact already proved. If D is projective then $\operatorname{Ext}^1_R(D, A) = 0$ by

corollary 17.6.8, so the first sequence reads $0 \to \mathrm{Hom}_R(D,A) \to \mathrm{Hom}_R(D,B) \to \mathrm{Hom}_R(D,C) \to 0$, which is definition 17.2.3. In the same way $\mathrm{Tor}_1^R(C,D) = 0$ for D flat turns the third into the short exact sequence of proposition 17.5.3(1). The derived functors do not replace the three module classes. They say what happens when a module is not in them.

17.6.4 The Extension Problem, Answered

Section 17.1 defined $\mathcal{E}(C,A)$ and showed it has at least one element, the class of the split extension, and sometimes more.

Theorem 17.6.10: Ext^1 Classifies Extensions

Let R be a ring and let A and C be R-modules. Then there is a bijection

$$\mathrm{Ext}^1_R(C,A) \longleftrightarrow \mathcal{E}(C,A)$$

between the underlying set of $\mathrm{Ext}^1_R(C,A)$ and the set of equivalence classes of extensions of C by A, under which 0 corresponds to the class of the split extension $A \oplus C$. The addition of $\mathrm{Ext}^1_R(C,A)$ transports to an operation on $\mathcal{E}(C,A)$, the *Baer sum*, making it an abelian group.

This is the theorem the chapter opened with, and it is the last of the three whose proof is omitted. Half of the construction is short, and it uses the following description of Ext^1, which also isolates why the theorem is plausible.

Proposition 17.6.11: Ext^1 as a Cokernel

Let $0 \to K \hookrightarrow P_0 \xrightarrow{\varepsilon} M \to 0$ be exact with P_0 projective, and let N be any R-module. Then

$$\mathrm{Ext}^1_R(M,N) \cong \mathrm{coker}\Big(\mathrm{Hom}_R(P_0,N) \xrightarrow{\text{restrict}} \mathrm{Hom}_R(K,N)\Big)$$

***Proof*:**
Extend the presentation to a projective resolution by choosing a projective P_1 with a surjection $d\colon P_1 \twoheadrightarrow K$ and setting $d_1 = \iota \circ d$, where $\iota\colon K \to P_0$ is the inclusion, and continuing with a resolution of $\ker(d)$.

Since d is surjective, $d^*\colon \mathrm{Hom}_R(K,N) \to \mathrm{Hom}_R(P_1,N)$ is injective by proposition 17.3.1, and its image is $\ker(d_2^*)$: the sequence $P_2 \to P_1 \xrightarrow{d} K \to 0$ is exact, so applying the same proposition identifies $\mathrm{Hom}_R(K,N)$ with the kernel of $\mathrm{Hom}_R(P_1,N) \to \mathrm{Hom}_R(P_2,N)$. Under this identification $\mathrm{im}(d_1^*)$ becomes the image of the restriction map $\mathrm{Hom}_R(P_0,N) \to \mathrm{Hom}_R(K,N)$, because $d_1 = \iota \circ d$ gives $d_1^* = d^* \circ \iota^*$. Hence

$$\mathrm{Ext}^1_R(M,N) = \ker(d_2^*)/\mathrm{im}(d_1^*) \cong \mathrm{Hom}_R(K,N)/\mathrm{im}(\iota^*)$$

which is the stated cokernel.

Now the construction. An extension $0 \to A \to B \xrightarrow{\beta} C \to 0$ together with a projective presentation $0 \to K \to P \xrightarrow{\varepsilon} C \to 0$ produce, by projectivity of P applied to the surjection β, a map $P \to B$ over

C. It carries K into A, and the class of the resulting $K \to A$ in the cokernel of proposition 17.6.11 is the invariant attached to the extension. What is genuinely work is that the assignment is well defined, bijective and additive, and that is deferred to *Homological Algebra* [29], which owes the full correspondence.

The theorem closes the loop with example 17.1.8(2), where the extensions of $\mathbb{Z}/p\mathbb{Z}$ by $\mathbb{Z}/p\mathbb{Z}$ were counted by hand. Proposition 17.6.7 gives

$$\operatorname{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/p\mathbb{Z},\,\mathbb{Z}/p\mathbb{Z}) \cong (\mathbb{Z}/p\mathbb{Z})\big/p(\mathbb{Z}/p\mathbb{Z}) \cong \mathbb{Z}/p\mathbb{Z}$$

which has p elements, matching the $p-1$ pairwise inequivalent nonsplit extensions found there together with the split one. Likewise $\operatorname{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/n\mathbb{Z},\mathbb{Z}) \cong \mathbb{Z}/n\mathbb{Z}$ says there are exactly n equivalence classes of extensions of $\mathbb{Z}/n\mathbb{Z}$ by $\mathbb{Z}$, while example 17.1.6 exhibited only two non-isomorphic middle terms. There is no conflict: equivalence is finer than isomorphism, exactly as definition 17.1.7 warned, and Ext^1 counts the finer relation.

Finally, $\operatorname{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/n\mathbb{Z},\mathbb{Q}) = 0$ says every extension of $\mathbb{Z}/n\mathbb{Z}$ by $\mathbb{Q}$ splits, which is theorem 17.3.4(3) for the injective module $\mathbb{Q}$. And $\operatorname{Tor}^{\mathbb{Z}}_1(\mathbb{Z}/n\mathbb{Z},A) = A[n]$ says the failure of $-\otimes\mathbb{Z}/n\mathbb{Z}$ to preserve an injection is measured by the n-torsion, which is theorem 17.5.7 read one module at a time.

Exercise 17.6.1

1. Using proposition 17.6.7, compute each of the following.
   1. $\operatorname{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/4\mathbb{Z},\mathbb{Z}/6\mathbb{Z})$ and $\operatorname{Tor}^{\mathbb{Z}}_1(\mathbb{Z}/4\mathbb{Z},\mathbb{Z}/6\mathbb{Z})$
   2. $\operatorname{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/n\mathbb{Z},\mathbb{Q}/\mathbb{Z})$ and $\operatorname{Tor}^{\mathbb{Z}}_1(\mathbb{Z}/n\mathbb{Z},\mathbb{Q}/\mathbb{Z})$
   3. $\operatorname{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/n\mathbb{Z},\mathbb{Z}_{p^\infty})$, for a prime p

2. Use theorem 17.6.10 and proposition 17.6.7 to say how many equivalence classes of extensions of $\mathbb{Z}/4\mathbb{Z}$ by $\mathbb{Z}$ there are. Then show that the possible middle terms are $\mathbb{Z}\oplus\mathbb{Z}/4\mathbb{Z}$, $\mathbb{Z}$ and $\mathbb{Z}\oplus\mathbb{Z}/2\mathbb{Z}$, so that strictly fewer isomorphism types occur than there are classes. *Hint*: the extension attached to k has middle term $(\mathbb{Z}\oplus\mathbb{Z})/\langle(4,-k)\rangle$.

3. Show directly from definition 17.6.3 that $\operatorname{Ext}^i_R(M,N) = 0$ for all $i \geq 1$ whenever M admits a projective resolution of length 0, and that $\operatorname{Ext}^i_R(M,N) = 0$ for all $i \geq 2$ whenever M admits one of length 1. Deduce that $\operatorname{Ext}^i_{\mathbb{Z}}(M,N) = 0$ for every $i \geq 2$ and every pair of abelian groups M, N. *Hint*: theorem 14.1.6.

4. Let R be a principal ideal domain. Show that $\operatorname{Tor}^R_1(M,N) = 0$ whenever either argument is torsion-free, and give an example over $R = \mathbb{Z}$ where $\operatorname{Tor}^{\mathbb{Z}}_1(M,N) \neq 0$.

5. Verify the first long exact sequence of theorem 17.6.9 by hand in one case: take $0 \to \mathbb{Z} \xrightarrow{\cdot 2} \mathbb{Z} \to \mathbb{Z}/2\mathbb{Z} \to 0$ and $D = \mathbb{Z}/2\mathbb{Z}$, compute every term using proposition 17.6.7, and check that the sequence you obtain is exact. Identify the connecting map δ_0.

6. Show that $\operatorname{Ext}^1_R(M,N) = 0$ for every N if and only if M is projective. *Hint*: one direction is corollary 17.6.8. For the other, take a projective presentation $0 \to K \to P \to M \to 0$ and use the description of Ext^1 as $\operatorname{coker}\big(\operatorname{Hom}_R(P,N) \to \operatorname{Hom}_R(K,N)\big)$ with $N = K$.

7. Explain why $\operatorname{Tor}_R(M)$ and $\operatorname{Tor}^R_1(M,N)$ are not the same kind of object, and compute both for $M = \mathbb{Z}/6\mathbb{Z}$ over $R = \mathbb{Z}$, taking $N = \mathbb{Z}/4\mathbb{Z}$ in the second.

17.7 Summary

One short exact sequence, three functors that truncate it, three classes of module that stop the truncation, and two families of modules that measure it when it happens. The tables below state what was established, each entry pointing at the result that establishes it.

Short exact sequences

Statement	**Reference**
$0 \to A \to B$ exact $\Leftrightarrow$ injective; $B \to C \to 0$ exact $\Leftrightarrow$ surjective	proposition 17.1.1
Short five lemma: α, γ injective (surjective) $\Rightarrow \beta$ is	proposition 17.1.9
Mini snake lemma: kernels and cokernels splice into one exact sequence	proposition 17.1.10
Splits $\Leftrightarrow$ a section exists $\Leftrightarrow$ a retraction exists	proposition 17.1.13
Splitting is carried along by any isomorphism of sequences	proposition 17.1.15
Equivalence of extensions is strictly finer than isomorphism	example 17.1.8(2)

The last row is what makes the extension problem a counting problem rather than a classification of middle terms, and it is what theorem 17.6.10 counts.

The three functors against exactness

Each functor below is exact at one end of a short exact sequence and can fail at the other. Naming the modules for which it does not fail is what the chapter is for. The first and third are covariant and the second contravariant.

Functor	**Always**	**Exact when**	**Reference**
$\mathrm{Hom}_R(D, -)$	left exact	D projective	proposition 17.2.1, definition 17.2.3
$\mathrm{Hom}_R(-, D)$	left exact	D injective	proposition 17.3.1, definition 17.3.3
$D \otimes_R -$	right exact	D flat	theorem 17.5.1, definition 17.5.4

For the contravariant row, *left exact* refers to the sequence after the outer terms have been exchanged, which is how proposition 17.3.1 states it. The two Hom functors can lose surjectivity. Tensoring can lose injectivity. The failures are at opposite ends because $D \otimes_R -$ is a left adjoint and $\mathrm{Hom}_R(D, -)$ its right adjoint (theorem 15.3.9).

The three classes

Class	Equivalent descriptions	Reference
Projective P	maps out of P lift along surjections; every $0 \to L \to M \to P \to 0$ splits	theorem 17.2.4
	P is a direct summand of a free module; P has a dual basis	proposition 17.2.8
Injective Q	maps into Q extend along injections; every $0 \to Q \to M \to N \to 0$ splits	theorem 17.3.4
	every $g\colon I \to Q$ on a left ideal extends to R	theorem 17.3.5
Flat A	$1 \otimes \psi$ is injective for every injective ψ	proposition 17.5.3

Projective modules have a structural description and injective modules do not, which is why Baer's criterion exists: it replaces a quantifier over all modules by one over the ideals of R.

How the classes relate, and where the implications are strict

Statement	Witness	Reference
free $\Rightarrow$ projective $\Rightarrow$ flat	(always)	corollary 17.2.6, corollary 17.5.5
projective $\not\Rightarrow$ free	$\mathbb{Z}/2\mathbb{Z}$ over $\mathbb{Z}/6\mathbb{Z}$; F^n over $M_n(F)$	example 17.2.7
flat $\not\Rightarrow$ projective	$\mathbb{Q}$ over $\mathbb{Z}$	example 17.5.8(2)
injective $\not\Rightarrow$ flat	$\mathbb{Q}/\mathbb{Z}$ over $\mathbb{Z}$	example 17.5.8(3)
flat $\not\Rightarrow$ injective	$\mathbb{Z}$ over $\mathbb{Z}$	example 17.3.10(1)
free $\not\Rightarrow$ injective	$\mathbb{Z}$ over $\mathbb{Z}$	example 17.3.10(1)
Projective, injective and flat pass to direct summands	(always)	proposition 17.3.9

Over particular rings the classes collapse.

Ring	Collapse	Reference
A field	free = projective = injective = flat	example 17.3.10(4)
A PID	projective = free	proposition 17.2.11
A PID	injective = divisible	theorem 17.3.5(2)
A PID	flat = torsion-free	theorem 17.5.7
An integral domain	injective $\Rightarrow$ divisible, and not conversely	theorem 17.3.5(2)

Resolutions and hulls

Every module is a quotient of a projective one and a submodule of an injective one, so both kinds of resolution exist. The injective side needed real work, having no dual of a free module to hand.

Statement	**Reference**
Every module is a quotient of a free module	example 17.1.4(3)
Every module is a submodule of an injective module	lemma 17.3.14
Injective resolutions exist	corollary 17.3.16
Every module has an injective hull, unique over the module	theorem 17.3.19
Two projective presentations differ by a free summand	proposition 17.2.12
Divisible groups: $\bigoplus_p \bigoplus_{I_p} \mathbb{Z}_{p^\infty} \oplus \bigoplus_I \mathbb{Q}$, invariants determined	theorem 17.4.7

The last row is the classification of injective $\mathbb{Z}$-modules, since divisible and injective agree over $\mathbb{Z}$. It is the one starred division of the chapter, and nothing outside it depends on it.

Ext, Tor, and the answer

Statement	**Reference**
$\operatorname{Tor}_i^R(M,N) = H_i(P_\bullet \otimes_R N)$ and	definition 17.6.2,
$\operatorname{Ext}^i_R(M,N) = H^i(\operatorname{Hom}_R(P_\bullet, N))$	definition 17.6.3
$\operatorname{Tor}_0 = M \otimes_R N$ and $\operatorname{Ext}^0 = \operatorname{Hom}_R(M,N)$	proposition 17.6.6
$\operatorname{Ext}^i_{\mathbb{Z}}(\mathbb{Z}/n\mathbb{Z}, A) = A[n],\ A/nA,\ 0$ and	proposition 17.6.7
$\operatorname{Tor}^{\mathbb{Z}}_i(\mathbb{Z}/n\mathbb{Z}, A) = A/nA,\ A[n],\ 0$	
$\operatorname{Ext}^i(P,N) = 0$ for P projective; $\operatorname{Tor}_i(M,F) = 0$ for F flat	corollary 17.6.8
Independent of the resolution; flat resolutions suffice for Tor	theorem 17.6.5
Long exact sequences in each variable	theorem 17.6.9
$\operatorname{Ext}^1_R(C,A) \leftrightarrow \mathcal{E}(C,A)$, with 0 the split class	theorem 17.6.10

The last row answers the question the chapter opened with, and the row above it is what turns the answer into a computation: $\operatorname{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/p\mathbb{Z}, \mathbb{Z}/p\mathbb{Z}) \cong \mathbb{Z}/p\mathbb{Z}$ has p elements, which is the count example 17.1.8(2) arrived at by hand.

Three of those statements are proved elsewhere. Theorem 17.6.5 and theorem 17.6.9 need the comparison theorem and chain homotopies, and theorem 17.6.10 needs the full construction of the correspondence. The first two are [29, Unique Projection Resolution, Chain-Homotopy and Cohomology], and the third is deferred there with the correspondence. That book takes up the three module classes of this chapter in the setting of an abelian category and takes the derived functors as its subject.

18⋆

Morita Theory

⋆ *Optional. This chapter is an aside; nothing later in the book depends on it.*

The rings R and $M_n(R)$ agree in almost nothing. One may be commutative. The other is not, once $n \geq 2$. Their unit groups are unrelated, and so are their underlying additive groups. Yet every statement about left R-modules translates into a statement about left $M_n(R)$-modules and back again, because the two module categories are equivalent. Chapter 12 met this phenomenon, named it *Morita equivalence*, and deferred it. This chapter settles it.

The result is Morita's theorem: every equivalence R-**Mod** $\to$ S-**Mod** is given by tensoring with a bimodule, and the bimodules that occur are exactly those that are finitely generated, projective, and large enough to reach every module. Most of what the proof needs is already available. Chapter 15 constructed the tensor product of bimodules and proved the Hom-tensor adjunction (theorem 15.3.9). Chapter 17⋆ gave projective modules and the dual basis lemma (proposition 17.2.8). One notion is new, and section 18.1 isolates it before section 18.2 proves the theorem and section 18.3 works out what an equivalence preserves and what it destroys.

Nothing in Part IV uses this chapter, which is why it is marked optional. Its payoff is further out: Morita equivalence is the reduction that makes the representation theory of finite-dimensional algebras tractable, in *Core Representation Theory* [22], and the invariance that makes K_0 computable, in *Algebraic K-Theory* [14].

18.1 Generators and Progenerators

An equivalence of categories carries an object to one with the same categorical description, so the first question is which description singles out R among left R-modules. Three properties do, and each is phrased purely in terms of maps: R is projective (definition 17.2.3), it is finitely generated, and every left R-module is a quotient of a direct sum of copies of R. The first two have names already.

The third does not.

Definition 18.1.1: Generator

Let R be a ring. A left R-module P is a *generator* of R-**Mod** if for every left R-module M there is an index set I and a surjection

$$P^{(I)} := \bigoplus_{i \in I} P \twoheadrightarrow M$$

The module R is a generator: any M is the image of the map $R^{(M)} \to M$ sending the basis element indexed by m to m. So definition 18.1.1 asks of P exactly what makes that argument work for R.

Checking the definition directly means quantifying over every module and every index set, which is unworkable. The next definition gathers the images of all maps $P \to R$ into a single subset of R, and theorem 18.1.4 shows that this one subset already decides the question.

Definition 18.1.2: Trace Ideal

Let P be a left R-module. The *trace ideal* of P is

$$\mathrm{Tr}(P) := \sum_{f \in \mathrm{Hom}_R(P,R)} f(P) \subseteq R$$

the additive subgroup of R generated by the elements $f(p)$ for $f \in \mathrm{Hom}_R(P, R)$ and $p \in P$.

Lemma 18.1.3: The Trace Ideal Is Two-Sided

For every left R-module P, the set $\mathrm{Tr}(P)$ is a two-sided ideal of R.

***Proof*:**
It is an additive subgroup by construction, so only the two multiplications need checking, and since $\mathrm{Tr}(P)$ is generated additively by the elements $f(p)$ it is enough to check them on such an element.

For left multiplication, let $r \in R$. Then $r\,f(p) = f(rp)$ because f is R-linear, and $rp \in P$, so $r\,f(p) \in f(P) \subseteq \mathrm{Tr}(P)$.

For right multiplication, fix $a \in R$ and define $g\colon P \to R$ by $g(x) = f(x)a$. This g is additive, and for $r \in R$ and $x \in P$,

$$g(rx) = f(rx)a = \big(r f(x)\big)a = r\big(f(x)a\big) = r\,g(x)$$

so $g \in \mathrm{Hom}_R(P, R)$. Hence $f(p)a = g(p) \in \mathrm{Tr}(P)$, completing the proof.

Theorem 18.1.4: Characterizations of a Generator

Let P be a left R-module. The following are equivalent.

1. P is a generator of R-**Mod**.
2. $\mathrm{Tr}(P) = R$.
3. R is isomorphic to a direct summand of P^n for some finite $n \geq 1$.
4. The functor $\mathrm{Hom}_R(P, -)\colon R\text{-}\mathbf{Mod} \to \mathbf{Ab}$ is faithful.

***Proof*:**

(1) $\Rightarrow$ (2). Apply definition 18.1.1 to $M = R$, giving a surjection $\pi\colon P^{(I)} \to R$. Write $\iota_i\colon P \to P^{(I)}$ for the inclusion of the i-th summand and set $f_i := \pi \circ \iota_i \in \mathrm{Hom}_R(P, R)$. Since π is surjective there is $x \in P^{(I)}$ with $\pi(x) = 1$, and an element of a direct sum has only finitely many nonzero coordinates, so $x = \sum_{i \in F} \iota_i(p_i)$ for a finite $F \subseteq I$ and elements $p_i \in P$. Then

$$1 = \pi(x) = \sum_{i \in F} f_i(p_i) \in \mathrm{Tr}(P)$$

By lemma 18.1.3 the set $\mathrm{Tr}(P)$ is an ideal, and an ideal containing 1 is the whole ring, so $\mathrm{Tr}(P) = R$.

(2) $\Rightarrow$ (3). By (2) there are $f_1, \ldots, f_n \in \mathrm{Hom}_R(P, R)$ and $p_1, \ldots, p_n \in P$ with $\sum_{i=1}^n f_i(p_i) = 1$. Define

$$\varphi\colon P^n \to R, \quad \varphi(x_1, \ldots, x_n) = \sum_{i=1}^n f_i(x_i), \qquad \sigma\colon R \to P^n, \quad \sigma(r) = (rp_1, \ldots, rp_n)$$

Both are R-linear: φ because each f_i is, and σ because the action on P^n is coordinatewise. For every $r \in R$,

$$\varphi(\sigma(r)) = \sum_{i=1}^n f_i(rp_i) = r \sum_{i=1}^n f_i(p_i) = r$$

so σ is a section of φ. In particular φ is surjective, and proposition 17.1.13 applied to $0 \to \ker(\varphi) \to P^n \xrightarrow{\varphi} R \to 0$ shows that this sequence splits, so $P^n \cong \sigma(R) \oplus \ker(\varphi)$ with $\sigma(R) \cong R$.

(3) $\Rightarrow$ (4). Let $f\colon M \to N$ be a nonzero map of left R-modules. The claim is that $f_* = \mathrm{Hom}_R(P, f)$ is nonzero. Choose $m \in M$ with $f(m) \neq 0$ and let $g\colon R \to M$ be the R-linear map $g(r) = rm$, so $f(g(1)) = f(m) \neq 0$ and hence $f \circ g \neq 0$. By (3) there are R-linear maps $\iota\colon R \to P^n$ and $\rho\colon P^n \to R$ with $\rho \circ \iota = \mathrm{id}_R$. Then

$$(f \circ g \circ \rho) \circ \iota = f \circ g \circ (\rho \circ \iota) = f \circ g \neq 0$$

so $f \circ g \circ \rho\colon P^n \to N$ is nonzero. A map out of a finite direct sum vanishes if and only if its restriction to every summand vanishes, so there is a coordinate inclusion $\kappa_j\colon P \to P^n$ with $f \circ (g \circ \rho \circ \kappa_j) \neq 0$. Setting $h := g \circ \rho \circ \kappa_j \in \mathrm{Hom}_R(P, M)$ gives $f_*(h) \neq 0$.

(4) $\Rightarrow$ (1). Let M be a left R-module and put

$$T := \sum_{h \in \mathrm{Hom}_R(P, M)} h(P) \subseteq M$$

a submodule of M, being a sum of the submodules $h(P)$. Let $q\colon M \to M/T$ be the quotient map. Every $h \in \mathrm{Hom}_R(P, M)$ has $h(P) \subseteq T$, so $q \circ h = 0$. That is, q_* is the zero map on $\mathrm{Hom}_R(P, M)$. Since $\mathrm{Hom}_R(P, -)$ is faithful and q_* agrees with the map induced by the zero homomorphism, it follows that $q = 0$, hence $M/T = 0$ and $T = M$. The map

$$P^{(\mathrm{Hom}_R(P,M))} \to M$$

whose restriction to the summand indexed by h is h therefore has image $T = M$, so it is surjective. As M was arbitrary, P is a generator, completing the proof.

Condition (2) is the one to check in practice, since it trades a quantifier over all modules for a computation inside R. Condition (3) is the form section 18.2 uses: it presents R as a retract of a finite power of P, which is what allows an argument about R to be transported to P. Condition (4) is the categorical reading, that P is a generator exactly when no nonzero map between modules is invisible to P.

Definition 18.1.5: Progenerator

A left R-module P is a *progenerator* if it is finitely generated, projective, and a generator of R-**Mod**.

These are the three properties of R listed at the start of the section, so R is a progenerator. Theorem 18.2.8 will show that the progenerators are precisely the modules that can take its place.

Example 18.1.6: Progenerators and Two Near Misses

1. For any ring R and any $n \geq 1$, the module R^n is a progenerator. It is free, hence projective by corollary 17.2.6, and finitely generated. The coordinate projection $R^n \to R$ is surjective, so $\mathrm{Tr}(R^n) = R$.

2. *Finitely generated and projective, but not a generator.* Let $R = \mathbb{Z}/6\mathbb{Z}$ and $e = \overline{3}$, which satisfies $e^2 = \overline{9} = \overline{3} = e$. Then $R = Re \oplus R(1 - e)$, so $P := Re = \{\overline{0}, \overline{3}\}$ is a direct summand of R, hence projective by theorem 17.2.4(4), and it is generated by one element. Every $f \in \mathrm{Hom}_R(P, R)$ satisfies
$$f(e) = f(e \cdot e) = e\, f(e) \in eR$$
and R is commutative here, so $f(P) = f(Re) = Rf(e) \subseteq Re$, giving $\mathrm{Tr}(P) = Re \neq R$. By theorem 18.1.4 the module P is not a generator. Concretely, every element of a direct sum of copies of P is annihilated by $\overline{2}$, while $\overline{1} \in R$ is not, so no such sum surjects onto R.

3. *A generator that is not projective.* Let $R = \mathbb{Z}$ and $P = \mathbb{Z} \oplus \mathbb{Z}/2\mathbb{Z}$. The projection onto the first coordinate lies in $\mathrm{Hom}_{\mathbb{Z}}(P, \mathbb{Z})$ and has image $\mathbb{Z}$, so $\mathrm{Tr}(P) = \mathbb{Z}$ and P is a generator by theorem 18.1.4. It is not projective: over the principal ideal domain $\mathbb{Z}$ projective and free coincide (proposition 17.2.11), and P has the nonzero torsion element $(0, \overline{1})$, so it is not free.

The two near misses show that neither condition in definition 18.1.5 implies the other, so both are genuine requirements on the bimodule that Morita's theorem produces.

Exercise 18.1.1

1. Let P be a left R-module and $n \geq 1$. Show that $\operatorname{Tr}(P^n) = \operatorname{Tr}(P)$, and deduce that P is a generator if and only if P^n is.
2. Show that every nonzero free left R-module is a generator of R-**Mod**, and that any module with a nonzero free direct summand is a generator.
3. Let $R = \mathbb{Z}/6\mathbb{Z}$. Decide, for each of the R-modules $\mathbb{Z}/2\mathbb{Z}$, $\mathbb{Z}/3\mathbb{Z}$, $\mathbb{Z}/6\mathbb{Z}$ and $\mathbb{Z}/2\mathbb{Z} \oplus \mathbb{Z}/3\mathbb{Z}$, whether it is a progenerator, justifying each answer using theorem 18.1.4.
4. Let P be a projective left R-module. Using the dual basis lemma (proposition 17.2.8), show that $\operatorname{Tr}(P)$ is idempotent, that is $\operatorname{Tr}(P)\operatorname{Tr}(P) = \operatorname{Tr}(P)$.
5. Let P be a generator of R-**Mod**. Show that $\operatorname{Hom}_R(P, M) = 0$ implies $M = 0$. Then show that this consequence does not characterize generators, by exhibiting a ring R and a non-generator P for which it still holds.

18.2 Morita's Theorem

The statement to be proved compares two module categories, so it needs the vocabulary for comparing categories. Functors are available (definition 8.0.4). The maps between functors are not, and the notion of two categories being "the same" rests on them.

Definition 18.2.1: Natural Transformation and Natural Isomorphism

Let $F, G \colon \mathcal{C} \to \mathcal{D}$ be functors. A *natural transformation* $\eta \colon F \Rightarrow G$ assigns to each object C of $\mathcal{C}$ a morphism $\eta_C \colon F(C) \to G(C)$ of $\mathcal{D}$ such that for every morphism $f \colon C \to C'$ of $\mathcal{C}$ the square

$$\begin{array}{ccc} F(C) & \xrightarrow{\eta_C} & G(C) \\ {\scriptstyle F(f)}\downarrow & & \downarrow{\scriptstyle G(f)} \\ F(C') & \xrightarrow[\eta_{C'}]{} & G(C') \end{array}$$

commutes. It is a *natural isomorphism*, written $F \cong G$, if every η_C is an isomorphism.

Definition 18.2.2: Equivalence of Categories

An *equivalence* between categories $\mathcal{C}$ and $\mathcal{D}$ is a pair of functors $F \colon \mathcal{C} \to \mathcal{D}$ and $G \colon \mathcal{D} \to \mathcal{C}$ together with natural isomorphisms $GF \cong \mathrm{id}_{\mathcal{C}}$ and $FG \cong \mathrm{id}_{\mathcal{D}}$. The functor G is a *quasi-inverse* of F, and $\mathcal{C}$ and $\mathcal{D}$ are *equivalent*.

An equivalence is bijective on morphism sets: F induces a bijection $\operatorname{Hom}_{\mathcal{C}}(C, C') \to \operatorname{Hom}_{\mathcal{D}}(FC, FC')$, with inverse obtained by applying G and conjugating by the natural isomorphism $GF \cong \mathrm{id}$. Every property of an object stated purely in terms of morphisms therefore transfers across an equivalence, which is what makes theorem 18.1.4(4) the useful characterization of a generator.

Definition 18.2.3: Morita Equivalence

Rings R and S are *Morita equivalent* if R-**Mod** and S-**Mod** are equivalent categories.

Now fix a left R-module P. Two rings act on it: R on the left, and its own endomorphism ring. Writing endomorphisms on the right makes the second action a right action, and that is the convention the whole section uses.

Proposition 18.2.4: The Bimodules Attached to a Module

Let P be a left R-module and set $S := \mathrm{End}_R(P)^{\mathrm{op}}$ and $Q := \mathrm{Hom}_R(P, R)$.

1. P is an (R, S)-bimodule under $p \cdot s := s(p)$.
2. Q is an (S, R)-bimodule under $(s \cdot q)(p) := q(s(p))$ and $(q \cdot r)(p) := q(p)r$.

***Proof*:**

1. Multiplication in S is $s_1 s_2 = s_2 \circ s_1$, so $p \cdot (s_1 s_2) = (s_2 \circ s_1)(p) = s_2(s_1(p)) = (p \cdot s_1) \cdot s_2$, and $p \cdot \mathrm{id}_P = p$. The action is additive in each variable because endomorphisms are additive. Compatibility with the left action is R-linearity of s:

$$(rp) \cdot s = s(rp) = r\, s(p) = r(p \cdot s)$$

2. First, $s \cdot q$ and $q \cdot r$ lie in Q: the map $p \mapsto q(s(p))$ is a composite of R-linear maps, and $(q \cdot r)(ap) = q(ap)r = a\, q(p)\, r = a\, (q \cdot r)(p)$. The left action is an action because

$$\big((s_1 s_2) \cdot q\big)(p) = q\big((s_1 s_2)(p)\big) = q\big(s_2(s_1(p))\big) = (s_2 \cdot q)(s_1(p)) = \big(s_1 \cdot (s_2 \cdot q)\big)(p)$$

using $(s_1 s_2)(p) = s_2(s_1(p))$ from the opposite multiplication. The right action is one because $(q \cdot (r_1 r_2))(p) = q(p) r_1 r_2 = ((q \cdot r_1) \cdot r_2)(p)$. They commute:

$$\big((s \cdot q) \cdot r\big)(p) = (s \cdot q)(p)\, r = q(s(p))\, r = (q \cdot r)(s(p)) = \big(s \cdot (q \cdot r)\big)(p)$$

completing the proof.

With P an (R, S)-bimodule and Q an (S, R)-bimodule, the two tensor products $P \otimes_S Q$ and $Q \otimes_R P$ are an (R, R)-bimodule and an (S, S)-bimodule respectively (proposition 15.2.1). Each carries an evaluation map to the ring on the corresponding side, and the entire theorem is the assertion that both are isomorphisms.

Proposition 18.2.5: The Morita Maps

With P, S and Q as in proposition 18.2.4, there are well-defined maps

$$\mu\colon P \otimes_S Q \to R, \quad \mu(p \otimes q) = q(p), \qquad \tau\colon Q \otimes_R P \to S, \quad \tau(q \otimes p) = \big[x \mapsto q(x)p\big]$$

the first a homomorphism of (R,R)-bimodules and the second of (S,S)-bimodules, and they satisfy the *associativity identities*

$$\mu(p \otimes q)\, p' = p \cdot \tau(q \otimes p'), \qquad q \cdot \mu(p \otimes q') = \tau(q \otimes p) \cdot q'$$

for all $p, p' \in P$ and $q, q' \in Q$.

***Proof*:**
Well-definedness. The assignment $(p,q) \mapsto q(p)$ is additive in each variable and satisfies $\mu(p{\cdot}s, q) = q(s(p)) = (s \cdot q)(p) = \mu(p, s \cdot q)$, so it is S-balanced and induces μ on $P \otimes_S Q$. For τ, the map $x \mapsto q(x)p$ is R-linear since $q(ax)p = a\, q(x)p$, so it is an element of S. The assignment is additive in each variable and

$$\tau(q \cdot r, p)(x) = (q \cdot r)(x)p = q(x)rp = \tau(q, rp)(x)$$

so it is R-balanced and induces τ.

Bimodule linearity. For μ: $\mu(rp \otimes q) = q(rp) = r\, q(p)$ and $\mu(p \otimes q \cdot r) = (q \cdot r)(p) = q(p)r$. For τ, recall $s_1 s_2 = s_2 \circ s_1$ in S. On the left,

$$\tau(s \cdot q \otimes p)(x) = (s \cdot q)(x)\, p = q(s(x))\, p = \big(\tau(q \otimes p) \circ s\big)(x) = \big(s\, \tau(q \otimes p)\big)(x)$$

and on the right, using R-linearity of s,

$$\tau(q \otimes p \cdot s)(x) = q(x)\, s(p) = s\big(q(x)p\big) = \big(s \circ \tau(q \otimes p)\big)(x) = \big(\tau(q \otimes p)\, s\big)(x)$$

The identities. For the first, $\mu(p \otimes q)p' = q(p)p'$, while $\tau(q \otimes p')$ is the endomorphism $x \mapsto q(x)p'$, so $p \cdot \tau(q \otimes p') = \tau(q \otimes p')(p) = q(p)p'$. For the second, evaluate both sides at $x \in P$:

$$\big(q \cdot \mu(p \otimes q')\big)(x) = q(x)\, q'(p), \qquad \big(\tau(q \otimes p) \cdot q'\big)(x) = q'\big(\tau(q \otimes p)(x)\big) = q'\big(q(x)p\big) = q(x)\, q'(p)$$

as we sought to show.

The two maps measure exactly the two conditions of definition 18.1.5, one each.

Lemma 18.2.6: What the Morita Maps Detect

With notation as above:

1. $\mathrm{im}\mu = \mathrm{Tr}(P)$, so μ is surjective if and only if P is a generator.
2. τ is surjective if and only if P is finitely generated and projective.

***Proof*:**

1. The image of μ is the additive subgroup generated by the elements $q(p)$ for $q \in \mathrm{Hom}_R(P, R)$ and $p \in P$, which is definition 18.1.2 verbatim. The equivalence with being a generator is theorem 18.1.4, (1) $\Leftrightarrow$ (2), since a subgroup of R equals R exactly when the map onto it is surjective.

2. ($\Rightarrow$) If τ is surjective, then $\mathrm{id}_P = \tau(t)$ for some $t \in Q \otimes_R P$, and every element of a tensor product is a finite sum of simple tensors, say $t = \sum_{i=1}^{n} q_i \otimes p_i$. Evaluating at $x \in P$,

$$x = \mathrm{id}_P(x) = \sum_{i=1}^{n} q_i(x)\, p_i$$

which is a finite dual basis, so P is finitely generated and projective by proposition 17.2.8.

($\Leftarrow$) If P is finitely generated and projective, proposition 17.2.8 gives a finite dual basis $(p_i, q_i)_{i=1}^{n}$, and the displayed identity says $\tau\big(\sum_i q_i \otimes p_i\big) = \mathrm{id}_P$. The image of τ is a two-sided ideal of S, being the image of an (S, S)-bimodule map, and an ideal containing the identity is the whole ring, completing the proof.

Surjectivity of the two maps is therefore exactly the progenerator hypothesis. What is not yet clear is injectivity, and the next lemma is the reason the theorem needs no separate argument for it: each map is forced to be injective by its own surjectivity, through the associativity identities that tie it to the other.

Lemma 18.2.7: Surjective Forces Bijective

If μ is surjective then μ is injective. If τ is surjective then τ is injective.

***Proof*:**
Suppose μ is surjective and let $t = \sum_{i=1}^{m} p_i \otimes q_i$ lie in $\ker \mu$, so that $\sum_i q_i(p_i) = 0$. Surjectivity gives elements $a_j \in P$ and $b_j \in Q$ with $1 = \sum_{j=1}^{k} \mu(a_j \otimes b_j)$. Then

$$t = \sum_i \Big(\sum_j \mu(a_j \otimes b_j)\Big) p_i \otimes q_i = \sum_{i,j} \big(\mu(a_j \otimes b_j)\, p_i\big) \otimes q_i = \sum_{i,j} \big(a_j \cdot \tau(b_j \otimes p_i)\big) \otimes q_i$$

using the first associativity identity of proposition 18.2.5. Moving the element of S across the tensor and applying the second identity,

$$t = \sum_{i,j} a_j \otimes \big(\tau(b_j \otimes p_i) \cdot q_i\big) = \sum_{i,j} a_j \otimes \big(b_j \cdot \mu(p_i \otimes q_i)\big) = \sum_j a_j \otimes \Big(b_j \cdot \sum_i \mu(p_i \otimes q_i)\Big)$$

and the inner sum is $\mu(t) = 0$, so $t = 0$. The argument for τ is the same with the roles of the two identities and of (P, R) and (Q, S) interchanged, completing the proof.

Theorem 18.2.8: Morita's Theorem

Let P be a progenerator in R-**Mod**, and set $S = \mathrm{End}_R(P)^{\mathrm{op}}$ and $Q = \mathrm{Hom}_R(P, R)$. Then

$$\mu \colon P \otimes_S Q \xrightarrow{\sim} R, \qquad \tau \colon Q \otimes_R P \xrightarrow{\sim} S$$

are isomorphisms of bimodules, and the functors

$$Q \otimes_R - \colon R\text{-}\mathbf{Mod} \to S\text{-}\mathbf{Mod}, \qquad P \otimes_S - \colon S\text{-}\mathbf{Mod} \to R\text{-}\mathbf{Mod}$$

are mutually quasi-inverse equivalences. In particular R and S are Morita equivalent.

***Proof*:**
Since P is a generator, μ is surjective by lemma 18.2.6(1). Since P is finitely generated and projective, τ is surjective by lemma 18.2.6(2). Both are then injective by lemma 18.2.7, hence bijective, and they are bimodule maps by proposition 18.2.5.

For the functors, let N be a left S-module. Associativity of the tensor product (theorem 15.2.8) and the isomorphism just established give

$$Q \otimes_R \left(P \otimes_S N\right) \cong \left(Q \otimes_R P\right) \otimes_S N \cong S \otimes_S N \cong N$$

and symmetrically, for a left R-module M,

$$P \otimes_S \left(Q \otimes_R M\right) \cong \left(P \otimes_S Q\right) \otimes_R M \cong R \otimes_R M \cong M$$

Each isomorphism in these chains is natural in the module argument, since theorem 15.2.8 is natural and the remaining two steps are the unit isomorphisms of the tensor product. The two chains are therefore natural isomorphisms $(Q \otimes_R -) \circ (P \otimes_S -) \cong \mathrm{id}$ and $(P \otimes_S -) \circ (Q \otimes_R -) \cong \mathrm{id}$, which is definition 18.2.2, completing the proof.

The theorem manufactures an equivalence from every progenerator. The converse says that this is the only source: an equivalence cannot arise any other way, and the progenerator producing it is recovered as the image of the ring.

Theorem 18.2.9: Every Equivalence Is Tensoring with a Progenerator

Let $F \colon R$-**Mod** $\to S$-**Mod** be an equivalence with quasi-inverse G. Put $Q := F(R)$ and $P := G(S)$. Then Q carries a right R-action making it an (S, R)-bimodule, P carries a right S-action making it an (R, S)-bimodule,

$$P \otimes_S Q \cong R \ \text{ as } (R,R)\text{-bimodules}, \qquad Q \otimes_R P \cong S \ \text{ as } (S,S)\text{-bimodules}$$

and $F \cong Q \otimes_R -$. Moreover P is a progenerator in R-**Mod**.

***Proof*:**
Step 1: the right action on Q. For $r \in R$ let $\rho_r \colon R \to R$ be $x \mapsto xr$, which is left R-linear. Since $\rho_{r_1 r_2} = \rho_{r_2} \circ \rho_{r_1}$ and F is a functor, $F(\rho_{r_1 r_2}) = F(\rho_{r_2}) \circ F(\rho_{r_1})$. Setting $q \cdot r := F(\rho_r)(q)$ therefore defines a right R-action on Q, and it commutes with the left S-action because each

$F(\rho_r)$ is a map of S-modules. The same construction gives the right S-action on P.

Step 2: F preserves direct sums and cokernels. An equivalence is bijective on morphism sets, as recorded after definition 18.2.2, and it is essentially surjective, every object of S-**Mod** being isomorphic to $F(G(N))$. A cocone is a direct sum, or a cokernel, exactly when a certain map of morphism sets is bijective for every test object. Bijectivity on morphism sets transports the condition forward and essential surjectivity gives every test object on the far side. So F carries direct sums to direct sums and cokernels to cokernels.

Step 3: $F \cong Q \otimes_R -$. For a left R-module M and $m \in M$ let $\lambda_m \colon R \to M$ be $r \mapsto rm$. The assignment $(q, m) \mapsto F(\lambda_m)(q)$ is additive in each variable and R-balanced, since $\lambda_{rm} = \lambda_m \circ \rho_r$ gives $F(\lambda_{rm})(q) = F(\lambda_m)(q \cdot r)$. It therefore induces $\theta_M \colon Q \otimes_R M \to F(M)$, and θ is natural in M because $f \circ \lambda_m = \lambda_{f(m)}$ for any $f \colon M \to M'$.

At $M = R$ the map θ_R is the isomorphism $Q \otimes_R R \cong Q = F(R)$, since $\lambda_r = \rho_r$. Both $Q \otimes_R -$ and F preserve direct sums, the first by corollary 15.2.5 and the second by Step 2, so $\theta_{R^{(I)}}$ is an isomorphism for every index set I. Now take any M and a free presentation $R^{(J)} \to R^{(I)} \to M \to 0$, which exists because every module is a quotient of a free one and the kernel of that quotient is again such a quotient. Both functors are right exact, again by theorem 17.5.1 and Step 2, so the rows of

$$\begin{array}{ccccccc} Q \otimes_R R^{(J)} & \longrightarrow & Q \otimes_R R^{(I)} & \longrightarrow & Q \otimes_R M & \longrightarrow & 0 \\ \downarrow{\scriptstyle \theta_{R^{(J)}}} & & \downarrow{\scriptstyle \theta_{R^{(I)}}} & & \downarrow{\scriptstyle \theta_M} & & \\ F(R^{(J)}) & \longrightarrow & F(R^{(I)}) & \longrightarrow & F(M) & \longrightarrow & 0 \end{array}$$

are exact and the square commutes by naturality. The two left vertical maps are isomorphisms, and a cokernel is determined up to unique isomorphism by the map it is taken of, so θ_M is an isomorphism.

Step 4: the bimodule isomorphisms. By Step 3 applied to F and to G, the composite $GF \cong P \otimes_S (Q \otimes_R -) \cong (P \otimes_S Q) \otimes_R -$ using theorem 15.2.8. Since $GF \cong \mathrm{id}$, evaluating at R gives $(P \otimes_S Q) \otimes_R R \cong R$, that is $P \otimes_S Q \cong R$. The isomorphism is one of (R, R)-bimodules because the natural isomorphism $GF \cong \mathrm{id}$ commutes with the maps ρ_r, whose images generate the right action. Symmetrically $Q \otimes_R P \cong S$.

Step 5: P is a progenerator. From $P \otimes_S Q \cong R$: the tensor product is generated as an abelian group by simple tensors, so the map $\bigoplus_{q \in Q} P \to P \otimes_S Q$ sending the summand indexed by q to $p \mapsto p \otimes q$ is surjective, exhibiting R as a quotient of a direct sum of copies of P. Hence P is a generator. From $Q \otimes_R P \cong S$: the element of $Q \otimes_R P$ corresponding to 1_S is a *finite* sum $\sum_{i=1}^{n} q_i \otimes p_i$, and unwinding the isomorphism as in lemma 18.2.6(2) yields $x = \sum_i q_i(x) p_i$ for all $x \in P$, a finite dual basis. So P is finitely generated and projective by proposition 17.2.8, completing the proof.

Taken together the two theorems say that Morita equivalence is not an exotic relation to be checked category by category: R and S are Morita equivalent precisely when $S \cong \mathrm{End}_R(P)^{\mathrm{op}}$ for some progenerator P over R. The next example is the case that motivated the whole discussion.

Example 18.2.10: A Ring and Its Matrix Rings

Let R be any ring and $n \geq 1$, and take $P = R^n$, the module of columns. By example 18.1.6(1) it is a progenerator. Its endomorphism ring is computed one summand at a time: an R-linear map $R \to R$ is right multiplication by its value at 1, so $\mathrm{End}_R(R) \cong R^{\mathrm{op}}$, and therefore

$$\mathrm{End}_R(R^n) \cong M_n\big(\mathrm{End}_R(R)\big) \cong M_n(R^{\mathrm{op}}) \cong M_n(R)^{\mathrm{op}}$$

the last isomorphism being transposition, which reverses the order of multiplication. Hence

$$S = \mathrm{End}_R(R^n)^{\mathrm{op}} \cong M_n(R)$$

and theorem 18.2.8 gives an equivalence R-**Mod** $\simeq M_n(R)$-**Mod**. Unwinding it, $Q = \mathrm{Hom}_R(R^n, R) \cong R^n$ as rows, the equivalence R-**Mod** $\to M_n(R)$-**Mod** sends M to the column space M^n with $M_n(R)$ acting by matrix multiplication, and its quasi-inverse sends N to eN where $e = E_{11}$ is the idempotent matrix with a single 1 in the top-left entry.

Nothing about R is recovered by $M_n(R)$ beyond its module category: for $n \geq 2$ the ring $M_n(R)$ is never commutative, so a commutative R is Morita equivalent to noncommutative rings. Section 18.3 makes precise which properties survive.

Exercise 18.2.1

1. Let P be a progenerator over R and $S = \mathrm{End}_R(P)^{\mathrm{op}}$. Show that $\mathrm{Hom}_R(P, -)$ and $Q \otimes_R -$ are naturally isomorphic as functors R-**Mod** $\to S$-**Mod**, where $Q = \mathrm{Hom}_R(P, R)$.
2. Show that Morita equivalence is an equivalence relation on rings.
3. Show that if R and S are Morita equivalent, then so are $M_n(R)$ and $M_n(S)$ for every $n \geq 1$.
4. Show that a commutative ring R and the matrix ring $M_n(R)$ have isomorphic centres for every $n \geq 1$, and explain why example 18.2.10 does not contradict this.
5. Let D be a division ring. Show that every progenerator over D is isomorphic to D^n for some $n \geq 1$, and deduce that the rings Morita equivalent to D are exactly the matrix rings $M_n(D)$.
6. Give an example of two rings that are Morita equivalent but not isomorphic, and an example of two rings that are not Morita equivalent even though both are commutative and have the same cardinality.
7. Let P be a progenerator over R. Show that P is also a progenerator when regarded as a right S-module, where $S = \mathrm{End}_R(P)^{\mathrm{op}}$.

18.3 Morita Invariants and the Basic Algebra

Example 18.2.10 showed that R and $M_n(R)$ have the same module category while differing in nearly every element-level respect. A property of a ring that transfers across every Morita equivalence is called a *Morita invariant*, and the question this section answers is which properties those are. The test is uniform: a property is a Morita invariant when it can be stated in terms of the module category alone, and it fails to be one as soon as a single equivalence moves it.

Commutativity is the basic failure. For $n \geq 2$ the ring $M_n(R)$ is noncommutative whatever R is, so no property implying commutativity survives. What does survive is the part of the multiplication that is visible categorically, and theorem 18.3.2 identifies it exactly: the center.

Proposition 18.3.1: The Center as Endomorphisms of the Identity

Let R be a ring. Sending $c \in Z(R)$ to the family of maps $\eta^c_M \colon M \to M$, $\eta^c_M(m) = cm$, is a ring isomorphism from $Z(R)$ (definition 9.1.8) to the ring of natural transformations $\mathrm{id}_{R\text{-}\mathbf{Mod}} \Rightarrow \mathrm{id}_{R\text{-}\mathbf{Mod}}$, under pointwise addition and composition.

***Proof*:**

The map is well defined. For $c \in Z(R)$ each η^c_M is R-linear, since $\eta^c_M(rm) = c(rm) = (cr)m = (rc)m = r(cm) = r\,\eta^c_M(m)$, which is exactly where centrality is used. It is natural: for $f \colon M \to N$ and $m \in M$,

$$f\big(\eta^c_M(m)\big) = f(cm) = c\,f(m) = \eta^c_N\big(f(m)\big)$$

Injectivity. If $\eta^c = \eta^{c'}$ then in particular $c = \eta^c_R(1) = \eta^{c'}_R(1) = c'$.

Surjectivity. Let η be a natural transformation of the identity and put $c := \eta_R(1)$. For $r \in R$, R-linearity of η_R gives $\eta_R(r) = \eta_R(r \cdot 1) = r\,\eta_R(1) = rc$. Naturality applied to the right multiplication $\rho_r \colon R \to R$, $x \mapsto xr$, which is a map of left R-modules, gives $\eta_R(xr) = \eta_R(x)r$. At $x = 1$ this reads $\eta_R(r) = cr$. Comparing the two expressions, $rc = cr$ for every $r \in R$, so $c \in Z(R)$.

It remains to see that $\eta = \eta^c$ on every module, not only on R. For $m \in M$ let $\lambda_m \colon R \to M$ be $r \mapsto rm$. Naturality gives

$$\eta_M(m) = \eta_M\big(\lambda_m(1)\big) = \lambda_m\big(\eta_R(1)\big) = \lambda_m(c) = cm = \eta^c_M(m)$$

Ring structure. Addition is pointwise on both sides. For multiplication, $\eta^c_M\big(\eta^{c'}_M(m)\big) = c(c'm) = (cc')m = \eta^{cc'}_M(m)$, so composition corresponds to multiplication in $Z(R)$, and $\eta^1 = \mathrm{id}$, completing the proof.

The right-hand side of proposition 18.3.1 mentions only the category R-**Mod**, never the ring R. That is the whole content of the next theorem.

Theorem 18.3.2: The Center Is a Morita Invariant

If R and S are Morita equivalent, then $Z(R) \cong Z(S)$ as rings.

***Proof*:**

Let $F \colon R\text{-}\mathbf{Mod} \to S\text{-}\mathbf{Mod}$ be an equivalence with quasi-inverse G, and let $\alpha \colon GF \cong \mathrm{id}$ and $\beta \colon FG \cong \mathrm{id}$ be the natural isomorphisms of definition 18.2.2. Given a natural transformation η of $\mathrm{id}_{R\text{-}\mathbf{Mod}}$, define

$$\Phi(\eta)_N := \beta_N \circ F\big(\eta_{G(N)}\big) \circ \beta_N^{-1} \colon N \to N \qquad (N \in S\text{-}\mathbf{Mod})$$

Each component is a composite of S-linear maps. It is natural in N: for $g \colon N \to N'$, naturality of β gives $g \circ \beta_N = \beta_{N'} \circ FG(g)$, and naturality of η at $G(g)$ gives $\eta_{G(N')} \circ G(g) = G(g) \circ \eta_{G(N)}$,

so applying F and conjugating,

$$g \circ \Phi(\eta)_N = \beta_{N'} \circ F\big(G(g) \circ \eta_{G(N)}\big) \circ \beta_N^{-1} = \beta_{N'} \circ F\big(\eta_{G(N')} \circ G(g)\big) \circ \beta_N^{-1} = \Phi(\eta)_{N'} \circ g$$

So Φ carries natural transformations of $\mathrm{id}_{R\text{-}\mathbf{Mod}}$ to natural transformations of $\mathrm{id}_{S\text{-}\mathbf{Mod}}$. It preserves addition because F is additive on morphism sets and conjugation is additive, and it preserves composition because the conjugating isomorphisms cancel in the middle:

$$\Phi(\eta)_N \circ \Phi(\eta')_N = \beta_N \circ F\big(\eta_{G(N)}\big) \circ F\big(\eta'_{G(N)}\big) \circ \beta_N^{-1} = \beta_N \circ F\big(\eta_{G(N)} \circ \eta'_{G(N)}\big) \circ \beta_N^{-1}$$

The same construction applied to G gives Ψ in the opposite direction, and $\Psi\Phi = \mathrm{id}$ follows from α being a natural isomorphism by the same cancellation. Hence Φ is a ring isomorphism, and proposition 18.3.1 on each side identifies its source and target with $Z(R)$ and $Z(S)$, completing the proof.

Two consequences follow at once, and together they say that Morita equivalence is a coarser relation than isomorphism on noncommutative rings while collapsing to isomorphism on commutative ones.

Corollary 18.3.3: Commutative Rings Are Morita Rigid

Let R and S be commutative rings. Then R and S are Morita equivalent if and only if $R \cong S$.

***Proof*:**
If $R \cong S$ then the isomorphism induces an equivalence of module categories by restriction of scalars along it. Conversely, if R and S are Morita equivalent then $Z(R) \cong Z(S)$ by theorem 18.3.2, and commutativity gives $Z(R) = R$ and $Z(S) = S$ by definition 9.1.8, so $R \cong S$, as we sought to show.

Example 18.3.4: Morita Equivalence Is Coarser than Isomorphism

Take R any ring and $n \geq 2$. Then R and $M_n(R)$ are Morita equivalent by example 18.2.10 but not isomorphic whenever R is commutative, since $M_n(R)$ is not commutative: the matrix units E_{11} and E_{12} satisfy $E_{11}E_{12} = E_{12}$ while $E_{12}E_{11} = 0$. Consistently with theorem 18.3.2, the center is preserved: $Z(M_n(R))$ consists of the scalar matrices cI with $c \in Z(R)$, so $Z(M_n(R)) \cong Z(R)$.

By corollary 18.3.3 no two non-isomorphic commutative rings are Morita equivalent, so every instance of the phenomenon involves a noncommutative ring.

The remaining business of the section is the construction that produces those equivalences in practice. Example 18.1.6(2) showed that Re is projective and finitely generated for an idempotent e, and computed its trace ideal in a special case. The general computation is what decides when Re is a progenerator.

Definition 18.3.5: Full Idempotent

An idempotent $e \in R$, so $e^2 = e$, is *full* if $ReR = R$, that is if the two-sided ideal generated by e is the whole ring.

Theorem 18.3.6: The Corner Ring of a Full Idempotent

Let $e \in R$ be an idempotent. Then

1. Re is a finitely generated projective left R-module with $\mathrm{Tr}(Re) = ReR$, so Re is a progenerator if and only if e is full;
2. $\mathrm{End}_R(Re)^{\mathrm{op}} \cong eRe$, the *corner ring* of e.

Consequently, if e is full then R and eRe are Morita equivalent.

***Proof*:**

1. Since $e^2 = e$, the element $1 - e$ is also idempotent and $R = Re \oplus R(1-e)$: every r decomposes as $r = re + r(1-e)$, and if x lies in the intersection, written both as $x = re$ and as $x = r'(1-e)$, then multiplying on the right by e gives $x = re \cdot e = xe = r'(1-e)e = 0$, the last step because $(1-e)e = e - e^2 = 0$. So Re is a direct summand of R, hence projective by theorem 17.2.4(4), and it is generated by the single element e.

   For the trace ideal, take $f \in \mathrm{Hom}_R(Re, R)$. Then $f(e) = f(e \cdot e) = e\, f(e)$, so $f(e) \in eR$, and since every element of Re has the form re,

   $$f(Re) = f(Re \cdot e) = R\, f(e) \subseteq ReR$$

   Conversely, for each $a \in R$ the map $f_a \colon Re \to R$ given by $f_a(x) = xa$ is left R-linear with image Rea. Summing over $a \in R$ gives $\mathrm{Tr}(Re) \supseteq \sum_a Rea = ReR$. Hence $\mathrm{Tr}(Re) = ReR$, and theorem 18.1.4 makes Re a generator exactly when $ReR = R$. Combined with the previous paragraph, Re is a progenerator exactly when e is full.

2. A map $\varphi \in \mathrm{End}_R(Re)$ is determined by $\varphi(e)$, since $\varphi(re) = r\varphi(e)$, and $\varphi(e) = \varphi(e \cdot e) = e\, \varphi(e)$ shows $\varphi(e) \in eRe$ (it already lies in Re). Conversely each $x \in eRe$ gives $\varphi_x(re) = rex = rx$, which is left R-linear and lands in Re because $x = ex'e \in Re$. The two assignments are mutually inverse and additive.

   For the multiplication, let $\varphi(e) = ebe$ and $\psi(e) = eae$. Then

   $$(\varphi \circ \psi)(e) = \varphi(eae) = \varphi\big((ea) \cdot e\big) = (ea)\, \varphi(e) = ea\, ebe = (eae)(ebe) = \psi(e)\, \varphi(e)$$

   using $e^2 = e$ in the last-but-one step. So $\varphi \mapsto \varphi(e)$ reverses multiplication, giving $\mathrm{End}_R(Re) \cong (eRe)^{\mathrm{op}}$ and therefore $\mathrm{End}_R(Re)^{\mathrm{op}} \cong eRe$.

For the final claim, if e is full then Re is a progenerator by (1), so theorem 18.2.8 applied to $P = Re$ gives an equivalence between R-**Mod** and $\mathrm{End}_R(Re)^{\mathrm{op}}$-**Mod** $= eRe$-**Mod** by (2), completing the proof.

Theorem 18.3.6 is the form in which Morita theory is used downstream. Passing from R to eRe for a full idempotent shrinks the ring while keeping the module category, and choosing e well makes the smaller ring markedly more tractable. The matrix case is the choice $e = E_{11}$ in $R = M_n(A)$, where $eRe \cong A$ recovers example 18.2.10. In the representation theory of finite-dimensional algebras the same construction selects one idempotent from each isomorphism class of indecomposable projectives

and produces the *basic algebra*, over which every algebra's representation theory can be read. That development, which needs the semisimple structure theory this book does not carry, is in *Core Representation Theory* [22].

Example 18.3.7: The Corner Ring of a Non-Full Idempotent

Fullness is not automatic. Let $R = \mathbb{Z}/6\mathbb{Z}$ and $e = \overline{3}$, as in example 18.1.6(2). Then $ReR = Re = \{\overline{0}, \overline{3}\}$, which is not R, so e is not full. The corner ring is $eRe = \{\overline{0}, \overline{3}\} \cong \mathbb{Z}/2\mathbb{Z}$, and $\mathbb{Z}/6\mathbb{Z}$ is not Morita equivalent to $\mathbb{Z}/2\mathbb{Z}$: both are commutative and not isomorphic, so corollary 18.3.3 rules it out. The construction still produces a ring, but without fullness it produces the wrong one.

One invariant is worth recording separately, because it is the reason *Algebraic K-Theory* [14] cares about this section at all.

Corollary 18.3.8: Finitely Generated Projectives Correspond

Let $F\colon R\text{-}\mathbf{Mod} \to S\text{-}\mathbf{Mod}$ be an equivalence. Then F restricts to a bijection between the isomorphism classes of finitely generated projective R-modules and those of finitely generated projective S-modules, and this bijection preserves direct sums.

***Proof*:**

Projectivity is preserved: M is projective exactly when $\mathrm{Hom}_R(M, -)$ carries surjections to surjections (definition 17.2.3), F is bijective on morphism sets, and F carries surjections to surjections because a map is surjective exactly when its cokernel vanishes and F preserves cokernels by theorem 18.2.9, Step 2.

Being finitely generated is preserved because $F \cong Q \otimes_R -$ with $Q \otimes_R R \cong Q$ (theorem 18.2.9), so F carries R^n to Q^n and a summand of R^n to a summand of Q^n. That Q^n is itself finitely generated over S is theorem 18.2.9 applied with the roles of F and G exchanged, which makes $Q = F(R)$ a progenerator in $S\text{-}\mathbf{Mod}$. The same argument then runs backwards through G. Direct sums are preserved by Step 2 of the same proof, and the quasi-inverse G gives the inverse bijection on isomorphism classes, completing the proof.

Since K_0 of a ring is built from the isomorphism classes of finitely generated projectives under direct sum, corollary 18.3.8 says that K_0 cannot distinguish Morita equivalent rings. That statement, and the group it is about, belong to *Algebraic K-Theory* [14].

Exercise 18.3.1

1. Show that the center of $M_n(R)$ consists of the scalar matrices rI with $r \in Z(R)$, and deduce $Z(M_n(R)) \cong Z(R)$ directly, without using theorem 18.3.2.
2. Decide which of the following are Morita invariants, with proof or counterexample: being a division ring; being commutative; being an integral domain (definition 9.1.21); having exactly two two-sided ideals.
3. Show that if R is commutative then an idempotent $e \in R$ is full if and only if $e = 1$, and give a noncommutative ring with a full idempotent $e \neq 1$.
4. Let $R = M_2(\mathbb{Z})$ and $e = E_{11}$. Verify directly that e is full, identify Re and eRe explicitly, and describe the equivalence $R\text{-}\mathbf{Mod} \simeq \mathbb{Z}\text{-}\mathbf{Mod}$ it produces.

5. Show that if e and f are idempotents of R with $Re \cong Rf$ as R-modules, then $eRe \cong fRf$ as rings.

6. Let R be a ring in which $1 = e_1 + \cdots + e_n$ for orthogonal idempotents e_i, meaning $e_i e_j = 0$ for $i \neq j$. Show that $R \cong \bigoplus_i Re_i$ as left R-modules, and that e_1 is full whenever $Re_1 \cong Re_i$ for every i.

Part IV

Fields

When studying classical algebra, a lot of time and energy is dedicated to solving equations. Famously, for any equation of the form $ax^2 + bx + c = 0$ has solution

$$x = \frac{-b - \sqrt{b^2 - 4ac}}{2a}$$

which was known since at least the time of ancient Egypt (though not in the current algebraic form[1])After a long gap, Niccolò Tartaglia discovers the general equation for the cubic equation in terms by using an "imaginary" number i as a trick to solve the problem of $\sqrt{-n}$ coming up (it will take some more time before i is considered a number and not simply a tool to solve equations). Using this equation, a solution for quartic equation with respect to x was also found. The mission was on in finding a solution to the quintic equation. However, over 200 years, no such equation was found. Abel and Galois have in fact proved that only using $+, -, \times, \div$ and $\sqrt{_}$, it is *impossible* to isolate x!

This is the origin of the study of field theory and Galois theory, and will be the driving motivation in this part of the book, however the study of fields have in modern times moves past this and are now used as a primary tool in the study of algebraic number theory. In chapter 50, we will use the language of field theory as the language of algebraic number theory.

[1] It was a geometric proof involving fitting squares of different sizes together

19

Field Theory

A reminder that a field F is a unital commutative division ring (definition 9.1.11). Another way of thinking of a field is that it's a set with two binary operations both acting like abelian groups. Yet another way of seeing them is that $F^\times = F - \{0\}$ is an abelian group. In this chapter, we will be mostly thinking about fields as unital commutative division rings, in particular, we are going to develop how the trivial ideal structure of fields (proposition 9.4.10) lets us uniquely define some extensions of a field. We will denote $\mathbb{F}_p := \mathbb{Z}/p\mathbb{Z}$ and usually use the letters k and K to refer to fields.

Furthermore, the complex numbers $\mathbb{C}$ will be referenced for it's nice algebraic properties (ex. $i^2 = 1$ or $z = a + bi$ for any $z \in \mathbb{C}$). If the reader is unfamiliar with these notion, there are many resources online explaining these concepts[1].

19.1 Properties of Fields

First, all fields are rings, and so we can form the category **Fld** with fields as objects and ring homomorphisms as morphisms. We will use the term field homomorphsisms sometimes since the objects of study are fields with the knowledge that they are just ring homomorphisms. In general, the term ring homomorphism will be reserved for when rings will be brought into the discussion as will sometimes happen. Since the objects are fields, it is important to remember that all homomorphisms must be *injective* (see corollary 9.4.13)

[1] A famous book explaining these notions is *Althor's Complex Analysis*, in which the first chapter explores complex numbers

Proposition 19.1.1: Field Homomorphisms

Let $\varphi : k \to K$ be a ring homomorphism of fields. Then φ is injective, and its image $\varphi(k)$ is a subfield of K isomorphic to k. In particular φ is never identically 0.

***Proof*:**
Since $\varphi(1) = 1 \neq 0$ (definition 9.1.5), φ is a nonzero ring homomorphism out of the division ring k, so it is injective by corollary 9.4.13. Its image $\varphi(k)$ is a subring of K (proposition 9.3.3(1)), commutative as K is, with $1 \neq 0$, and every nonzero element of $\varphi(k)$ is $\varphi(a)$ for some $a \neq 0$, with inverse $\varphi(a^{-1}) \in \varphi(k)$, since $\varphi(a)\varphi(a^{-1}) = \varphi(1) = 1$. So $\varphi(k)$ is a subfield of K, and $\varphi\colon k \to \varphi(k)$ is a bijective ring homomorphism, hence an isomorphism by the remark following definition 9.1.5, completing the proof.

Thus, If a homomorphism between fields $\varphi : k \to K$ exists, $\varphi(k) \cong k$. In this way, K can be thought of as extending k:

Definition 19.1.2: Field Extension

Let k and K be fields. If there exists a homomorphism $\varphi : k \to K$ (which as we have shown must be injective), then we say that K *extends* k, or K is a *field extension* of k. We will denote this by $k \subseteq K$, K/k, or

$$\begin{array}{c} F \\ | \\ K \end{array}$$

the field from which we are extending is sometimes called the *base field* or *ground field*.

Note that since fielsd are commutative, field extension $\varphi : k \to F$ makes F a k-algebra.

Example 19.1.3: Field Extensions

1. For any field F, F/F is trivially a field extension, since the identity map is a field homomorphism.
2. Perhaps the most famous field extension is that of $\mathbb{C}/\mathbb{R}$, since $\mathbb{R}$ is directly embedded into $\mathbb{C}$. A perhaps easy mistake to make when first learning about field extensions is that $\mathbb{R}^2/\mathbb{R}$ is not a field extension since $\mathbb{R}^2$ is simply not a field. On the other hand, $\mathbb{C}/\mathbb{Q}$ is also a field extension, since the natural inclusion map $\iota : \mathbb{Q} \to \mathbb{C}$ is a field homomorphism. Similarly, $\mathbb{R}/\mathbb{Q}$ is a field extension.
3. In example 9.1.19, we saw that $\mathbb{Q}(\sqrt{D})$ is a field where D is not a perfect square (i.e. there does not an element $d \in \mathbb{Q}$ s.t. $d^2 \in \mathbb{Q}$). For a concrete examples, let's say $D = 2$. Then $\mathbb{Q}(\sqrt{2})/\mathbb{Q}$ is a field extension. If $D = -1$, then we usually write $\sqrt{-1}$ as i, and we get that $\mathbb{Q}(i)/\mathbb{Q}$ is a field extension. We also have that $\mathbb{C}/\mathbb{Q}(i)$ is a field extension, with the map $\iota : \mathbb{Q}(i) \to \mathbb{C}$ given by mapping $a + bi \mapsto a + bi$. Notice that the map $a + bi \mapsto a - bi$ is also a valid field homomorphism, showing that there need not be a unique map.

   We will soon find a way to define $\mathbb{Q}(\sqrt{D})$ without needing to reference set-builder notation.

4. Let k be a field and $k(x) = \text{Frac}(k[x])$ be the field of fractions of $k[x]$. Then $k(x)/k$ is a field extension.

The notation K/k may be read as "K over k". It does *not* represent the quotient K by k. This can be consider an overload of notation, but since the kernel of a ring homomorphism between fields must *always* be trivial, it is safe to see that K/k would not represent a quotient of the field K by k.

Another thing we can observe is that every field homomorphism $\varphi : F \to K$ can be extended into a ring homomorphism $f^\varphi : F[x] \to K[x]$ through

$$\sum_i a_i x^i \mapsto \sum_i \varphi(a_i) x^i$$

the fact that this is a ring homomorphisms comes straight from the properties of φ. Thus, we can consider this process to be a functor $f\text{—} : \mathbf{Fld} \to \mathbf{Ring}$.

If F/k is any field extension, then we can naturally make F into a *vector-space over* k by making k act on F by multiplication (since $k \subseteq F$, this action is well-defined). Since every field has a prime subfield, every field is at least a vector-space over it's prime-subfield. The dimension of the vector-space is given a name:

Definition 19.1.4: Degree

The *degree* (or *relative degree* or *index*) of a field of extension F/k, denoted $[F : k]$, is the dimension of F as a vector-space over k (i.e. $[F : k] = \dim_k(F)$). The extension is said to be *finite* if $[F : k]$ is finite and is said to be *infinite* otherwise.

Definition 19.1.5: Finite Extension

Let F/k be a field extension. Then F/k is called a *finite extension* if $[F : k]$ is finite, and an *infinite extension* otherwise.

In example 19.1.3, $\mathbb{C}/\mathbb{R}$ is an extension of degree 2, the basis of $\mathbb{C}$ over $\mathbb{R}$ consiss of $\{1, i\}$, and hence a finite extension. The extension $k(x)/k$ is an extension if infinite degree: If it were finite, then any rational function can be written as a sum of a finite number of polynomials up to a constant $c \in k$, but then this collection must have a highest degree term, say n. Then any polynomial of degree $n + 1$ cannot be written as a linear combination of the basis, a contradiction. Hence, it is an infinite extension. Note too that as was demonstrated in theorem 13.1.8, every vector-space has a basis, and so any element $x \in F$ can be represented as a finite linear combination:

$$a_1\beta_1 + a_2\beta_2 + \cdots + a_n\beta_n \qquad a_i \in k,\ \beta_i \in \mathcal{B}$$

We will soon show how to find such a basis.

Since F/k can also be represented as a vector-space over k, we might ask if any field homomorphism/isomorphism can is also a linear transformation. The answer is yes, if we are a bit careful. Let's say that F/k and L/k are two fields extending k, and $\varphi : F \to L$ is a field homomorphism/isomorphism. We will look for a condition under which φ is also a k-vector space homomorphism. Additivity holds because φ is a ring homomorphism. For homogeneity of the scalar, we see that for any $r \in k$ and $m \in F$:

$$\varphi(rm) = \varphi(r)\varphi(m) \overset{!}{=} r\varphi(m)$$

where $\overset{!}{=}$ is the condition we need so that φ is a k-vector space homomorphism. In particular, this conditions say's that for any element $r \in k$, $\varphi(r) = r$. This is stronger than saying φ maps k to itself (i.e. $\varphi(k) = k$), rather it is saying that φ is the *identity* on k. Since such field homomorphisms/isomorphsisms are also vector-space homomorphisms, they are given a name:

Definition 19.1.6: Fixed Homomorphisms

Let F/k and L/k be two field extensions of k and $\varphi : F \to L$ be a field homomorphism (resp. isomorphism). Then if φ is the identity on k, φ is said to be a *k-homomorphsm* (resp. *k-isomorphism*). If there exists a k-isomorphisms $A \to B$, then we will say that A is k-isomorphic to B and write $A \cong_k B$.

Note that a fixed homomorhism is in fact a k-algebra homomorphism: if L/k, then there is a natural k-module structure on L given by multiplication.

As was shown in section 13.2, a linear transformation is determined by where it maps it's basis to. Hence, if we have a k-homomorphism, then can deduce where the element map (or resp. construct a k-homomrophism) by finding where the basis maps to (resp. by only choosing where the basis maps to). Even better, this linear transformation respects the multiplicative structure of F (that is $\varphi(ab) = \varphi(a)\varphi(b)$), that if a basis β can be generated multiplicatively and additively from a set S, $\langle S \rangle = \beta$, then a k-homomorphism is only determined by where it sends S. Even better, this makes any k-homomorphism a k-algebra homomrophism, and a field F that extends k (F/k) is a k-algebra.

One more word of warning is in order: Let's say we find two field extensions A/k, B/k such that $A \cong_k B$. Then this implies that $\dim_k A = \dim_k B$, however it does not imply $A = B$. This might seem obvious, however it is an mistake that is easy to make after working with field extensions for awhile (this nuance will be particularly important in theorem 19.5.13).

In most of this and the next chapter, we will focus on finite extensions. Some results for extensions of infinite degree will arise as a natural generalization of the results of finite extensions, however finiteness is used in some key proofs to construct bijections (most importantly, in proposition 20.1.12). Infinite Galois extensions are treated in theorem 50.8.8.

Characteristic

The following is is perhaps the simplest invariant of a field k (that is, if $\varphi : k \to K$ is a homomorphism, the property we are about to discuss is preserved). Every field has a multiplicative identity $1 \in k$. Since k is a field, it is also a ring, and hence there exists a unique ring homomorphism from $\mathbb{Z}$ to k mapping 1 to 1 (see proposition 9.1.29):

$$\mathbb{Z} \to k,\ n \mapsto \begin{cases} \underbrace{1+1\cdots+1}_{n \text{ times}} & n > 0 \\ -(\underbrace{1+1\cdots+1}_{n \text{ times}}) & n < 0 \\ 0 & n = 0 \end{cases}$$

We will use multiplication notation $n \cdot 1$ as a shorthand [2]. The image $\text{im}(\mathbb{Z})$ of this homomorphism is the smallest subring of k, since every subring contains 1 and hence every $n \cdot 1$.

[2] Note that we can also have defined it as a $\mathbb{Z}$-module on k

Definition 19.1.7: Characteristic

The *characteristic* of a field F, dentoed $ch(F)$, is the order of $\text{im}(\mathbb{Z})$. If $|\text{im}(\mathbb{Z})| < \infty$, we say that F has a *finite characteristic*, and characteristic 0 otherwise. In other words, it is defined as the smallest positive integer n such that $n \cdot 1 = 0$ if such a n exists, and is defined to be 0 otherwise

If n exists, then n needs to be prime. If it were not, then

$$n = n \cdot 1 = (a \cdot 1)(b \cdot 1) = 0$$

meaning either $a \cdot 1$ or $b \cdot 1$ must be zero-divisors, a contradiction since a field has no zero-divisors! Notice that we only need to have an integral domain for the previous proposition, and that the characteristic of the integral on an integral domain will be the same as its field of fractions. For a prime p, $\mathbb{Z}/p\mathbb{Z}$ is a field: if $p \nmid a$, then $\gcd(a, p) = 1$ and Bézout (theorem 0.2.10) gives $ua + vp = 1$, so u is inverse to a modulo p. However, $\mathbb{Z}$ is not a field. Using theorem 9.5.1, we know the smallest field containing $\mathbb{Z}$ would be $\mathbb{Q}$! In both cases, the field this map injects to must be the *smallest* field that contains 1 (which can also be thought of as the field *generated* by 1 in k)

Definition 19.1.8: Prime Subfield

The *prime subfield* of a field k is the subfield k generated by the multiplicative identity 1_F of k. It is (isomorphic to) either $\mathbb{Q}$ (if $\text{ch}(k) = 0$) or k_p (if $\text{ch}(k) = p$).

19.1.9 Note A shorthand of writing the characteristic of a field is the following: if $p \cdot 1 = 0$, then it is sometimes written $p = 0$ to mean a field with characteristic p.

Notice that for a field k of characteristic n ($n \geq 0$), $k/\mathbb{F}_p$ (resp. $k/\mathbb{Q}$) is always a field extension, since we can always map $\mathbb{F}_p$ or $\mathbb{Q}$ to k through the identity map.

Note that for fields of characteristic 0, field homomorphism are automatically a vector-space homomorphism over $\mathbb{Q}$: linearity holds automatically, and for any scalar $c \in \mathbb{Q}$:

$$\varphi(cx) = \varphi(c)\varphi(x) \overset{!}{=} c\varphi(x)$$

where $\overset{!}{=}$ comes from how a field homomorphism must map $\mathbb{Q}$ to itself.

The claim at the beginning of this section should now be checked, namely that if $\text{ch}(k) = n$, $n \geq 0$, and $\varphi : k \to K$ is a homomorphism, then $\text{ch}(K) = n$: φ is injective and $\varphi(m \cdot 1) = m \cdot 1$, so $m \cdot 1 = 0$ in k exactly when $m \cdot 1 = 0$ in K. Since charactersitic is preserved, we can take the subcategory of $\mathbf{Fld}_0$ or $\mathbf{Fld}_p$ where we restric to fields of characteristic p or 0. We will not really do this, however it is inisghtful that doing so will now make these categories have initial objects, namely the respective prime subfield (can you prove this? Can you see why $\mathbf{Fld}$ has no initial objects?). More generally, since homomorphisms can only be injective, we can take $\mathbf{Fld}_k$ to be the category ring homomorphisms as morphisms and all fields that extend k as objects! In most of the following studies, we will fix a field k and study extensions from it, and so field theory can be thought of as studying particular $\mathbf{Fld}_k$ categories

Torsion in Fields

By theorem 11.3.14, every finite subgroup of $F^\times$ is cyclic. Not every element of $F^\times$ has finite order: in $\mathbb{R}$, no positive power 2^n equals 1.

Definition 19.1.10: Root of Unity

Let F be a field and $r \in F$. If there exists an $n \in \mathbb{N}$ such that $r^n = 1$, then we call r an *nth root of unity*.

Example 19.1.11

In $\mathbb{C}$, all elements of the form $e^{\frac{2\pi ik}{n}}$ for $0 \leq k \leq n-1$ are nth roots of unity. In fact, they are all the roots of unity of $\mathbb{C}$. The real numbers $\mathbb{R}$ have only 2 roots of unity of degree 1 and 2 respectively: ± 1.

Notice that not all $e^{\frac{2\pi ik}{n}}$ are generators for the cyclic subgroup they belong to. The generators of these cyclic subgroups are given a name:

Definition 19.1.12: Primitive Root Of Unity

Let F be a field. Then a *primitive nth root of unity* is a generator of the cyclic multiplicative subgroup of all nth roots of unity.

We will return to the study of the roots of unity later. They will be the "building blocks" for [finitely generated] abelian groups in field theory (and Representation theory)[3]

Exercise 19.1.1

1. Let $\zeta_8 = \frac{\sqrt{2}}{2}(1+i) \in \mathbb{C}$. Show that ζ_8 is a primitive 8th root of unity, that $\zeta_8^2 = i$, and that $\zeta_8 + \zeta_8^7 = \sqrt{2}$.
2. (Analysis Problem) Show that the roots of unity are dense in $S^1 = \{z \in \mathbb{C} \mid |z| = 1\}$.

Generating Fields

Let's say $k \subseteq F$ is a subfield of F, and take some subset $A \subseteq F$. We can construct a field using k and A in the same way as we have done all the way back in section 2.3.2: Take all subfield of F containing k and A, and intersect them. Similarly to section 2.3.2, this is equivalent to "closing" the field k with A by taking all possible combinations. There is always at least exists the field K with this which contains this property. Since the intersection of fields is a field (this should be done as an exercise), then we can intersect all fields with this property to get the smallest such subfield.

[3] Remember by the fundamental theory of finitely generated abelian groups that any finitely generated abelian group is the direct product of a free part $\mathbb{Z}^r$ and a torsion part? Notice how the roots of unity can represent any cyclic subgroup?

Definition 19.1.13: Field Generated By Elements Over F

Let F/k be a field extension and S be a set of elements of F. Then the smallest subfield of F containing both k and the elements of S is denoted $k(S)$ and is called *the field generated by S over k*. If S is finite so that $S = \{\alpha_1, \alpha_2, ..., \alpha_n\}$, we usually denote $k(S)$ by $k(\alpha_1, \alpha_2, ..., \alpha_n)$ and call it the field *generated by $\alpha, \alpha_2, ..., \alpha_n$ over k*.

If we have a field extension F/k, and F can be generated by a single element, then we call that a simple extension:

Definition 19.1.14: Simple Extension

Let F/k be a field extension. Then if there exists an element $\alpha \in F$ such that $F = k(\alpha)$, we say that F is a *simple extension*, and call α the *primitive element* of the extension. The field $k(\alpha)$ is sometimes called "k adjoin α".

Be mindful to not confuse the terms "finite generation over k", "finite type k-algebra" [4], or "finite degree over k" (for example, $k(t)/k$ is a simple extension, but certainly not finite as was discussed under the definition of degree).

A similar definition works if we broaden to rings: instead of taking the intersection of all fields containing α and F, we take all rings containing α and F. It is easy to generlize the proof that the intersection of fields is a field to rings. We will usually denote this smallest ring $F[S]$, and if $S = \{\alpha_1, \alpha_2, ..., \alpha_n\}$ is finite, then $F[S] = F[\alpha_1, \alpha_2, ..., \alpha_n]$.

Proposition 19.1.15: Characterizing $F(S)$ and $F[S]$

Let K/F be a field extensions, $S \subseteq K$, and consider both $F(S)$ and $F[S]$. Then:

1. $F[S]$ can be characterized as the set of all finite linear combinations with coefficients in K of finite products of powers of elements of S, that is, polynomials with variables taken from S
2. $F(S)$ can be characterized as the set of all $ab^{-1} \in K$ with $a, b \in F[S]$ with $b \neq 0$. Furthermore, $F(S) \cong \text{Frac}(F[S])$

Note that in the "polynomials" mentioned above, the varaibles S are *not* indeterminates, since they might have relations in K (for example, it might be that for some $s \in S$, $s^2 + 1 = 0$)

***Proof*:**
These proofs are similar to those of section 2.3.2 with appropriate modifications for the added operation of multiplication and inversing.

To close off this section, we introduce a generalization to notion of the smallest field K/k generated by some elements to the smallest field generated with all the elements of another field:

[4] There is a deep connection between those two concepts, which we will explore in *Classical Algebraic Geometry* [42]. As foreshadowing, try seeing if you can think of a finitely generated field extension F/k that is not a finite-type k-algebra (or vice-versa). The answer to this question is given by Zariski's Lemma

Definition 19.1.16: Composite Field

Let K_1 and K_2 be two subfield of K. Then the *composite field* of K_1 and K_2, denoted K_1K_2, is the smallest subfield of K containing both K_1 and K_2. Similarly, the composite of any collection of subfields of K is the smallest subfield containign all the subfields.

Note that like in section 2.3.2, we can describe K_1K_2 as the intersection of all subfields contianing K_1 and K_2 (or any number of subfields).

Example 19.1.17: Composite Fields

The composite field $\mathbb{Q}(\sqrt{2})\mathbb{Q}(\sqrt[3]{2})$ is $\mathbb{Q}(\sqrt[6]{2})$, since thie field contains both these fields, and conversely any field containing both $\sqrt{2}$ and $\sqrt[3]{2}$ contains their quotient, namely $\sqrt[6]{2}$

Exercise 19.1.2

1. Sometimes, we want to consider field extensions without an underlying field. Let E, F be two fields of the same characteristic, say p. Show that $E \otimes_{\mathbb{F}_p} F$ (resp. $E \otimes_{\mathbb{Q}} F$) as a $\mathbb{F}_p$ (resp. $\mathbb{Q}$)-algebra is a field if and only if $[EF : \mathbb{F}_p] = [E : \mathbb{F}_p][F : \mathbb{F}_p]$ (resp. $[EF : \mathbb{Q}] = [E : \mathbb{Q}][F : \mathbb{Q}]$)

19.2 Field Extensions

We now continue our exploration of field extensions. As we saw in proposition 19.1.15, any field K/F such that $K = F(S)$ is the field of fractions of all "polynomials" with variables S and coefficients F. In particular, these polynomials have "solutions" or "roots" characterizing their relations. Similarly to how generators in a group where characterized by a monomial, (for example, D_4 is characterized with the generators a, b satisfying the monomails $ab^{-1}ab = 1$ and $a^2 = b^4 = 1$), generators in fields are characterized by polynomial relationships (for example, $\mathbb{C}/\mathbb{R}$ is characterized by being generated by $\mathbb{R}$ and i where $i^2 = -1$). Just like how any relation of elements within a group can be shifted so all the elements are on the left hand side (ex. writing $a^{-1}bab = 1$ instead of $ab = b^{-1}a$), we can do the same with polynomial relationships (ex. $i^2 + 1 = 0$). In proposition 19.2.24, we will show why it only matters to characterize polynomials, and not rational polynomials (i.e. elements of $p(S)/q(S)$)

As we have seen in chapter 11, every polynomial $p(x) \in F[x]$ can be broken down into irreducible polynomials. We will start finding an easy way of extending any field k which will give us a large class of field and field extensions to work with using irreducible polynomials (recall that $x^2 + 1$ has no solutions in $\mathbb{R}$, but does in $\mathbb{C}$, so is there an extension from $\mathbb{R}$ to $\mathbb{C}$?). We will find that the method used to construct fields will almost create "universal fields" (the same way free groups are sort of the universal groups since any group is the quotient of a free group). This endevaour to create a universal property will be very close in obtaining a universal property for fields, however it will fail in one important way. Due to that failure, it will be important carry around some more information to take into account the lake of universality. In fact, the lack of universal property may be seen less as a failure and more as a peek into the further structure that underly field extensions. Figuring all of this out is the goal of this section

Field Extensions using Polynomial

If we take our field to be $\mathbb{R}$, then $x^2+1=0$ does not have a solution in $\mathbb{R}$. The question then is whether there is a larger field K for which $x^2+1=0$ *has* a solution. More generally, given any irreducible polynomial $p(x) \in k[x]$, does there exists a field K such that K contains a root of $p(x)$[5]?. The answer is yes, and we have all the tools already to answer it. Take a moment and try to find the larger field K which satisfies this.

19.2.1 Taking a moment

Theorem 19.2.2: Kronecker's Theorem

Let k be a field and let $p(x) \in k[x]$ be an irreducible polynomial. Then there exists a field K containing an isomorphic copy of k in which $p(x)$ has a root. Identifying k with this isomorphic copy through i shows that there exists an extension of k in which $p(x)$ has a root. Furthermore, if L/k is a field extension in which $p(x)$ has a root, then there exists a k-homomorphism $j : K \to L$ such that

$$\begin{array}{ccc} K & \xrightarrow{j} & L \\ {\scriptstyle \iota}\uparrow & \nearrow_{i} & \\ k & & \end{array}$$

commutes. Due to this, the field K produced in the following construction is sometimes called the *Kronecker field for* $p(x)$ *over* k.

If in the Kronecker construction we use a *reducible* polynomials, then the resulting object is no longer a field (it contains zero-divisors), but remains to be a k-algebra.

***Proof*:**
Consider

$$K = k[x]/(p(x))$$

Since $k[x]$ is a Principal Ideal Domain (corollary 11.1.2) and since $p(x)$ is irreducible (so prime by proposition 10.1.33), $p(x)$ is maximal (proposition 10.1.32). Then $k[x]/(p(x))$ is a field by proposition 9.4.19. Restricting the canonical projection $\pi : k[x] \to K$ to k gives a homomorphism $\pi|_k : k \to K$, which is injective by proposition 19.1.1, so $\pi(k) \cong k$ is an isomorphic copy of k contained in K. We identify k with its isomorphic image in K and view k as a *subfield* of K. If $\overline{x} = \pi(x)$ denotes the image of x in the quotient K, then

$$\begin{aligned} p(\overline{x}) &= \overline{p(x)} && \text{since } \pi \text{ is a homomorphism} \\ &= p(x) \bmod (p(x)) && \text{in } k[x]/(p(x)) \\ &= 0 \end{aligned}$$

so that K contains a root of the polynomial $p(x)$. Thus, K is an extension of k in which the polynomial $p(x)$ has a root.

[5] We can assume that $p(x)$ is irreducible in $F[x]$, since if any factors of $p(x)$ has a root, then so does $p(x)$

For the second assertion, suppose $p(x)$ has a root α in L. Then the evaluation map $\text{ev}_\alpha : k[x] \to L$ (which we have proved is a ring-homomorphism in theorem 9.2.4), $g(x) \mapsto g(\alpha)$ must map $p(x)$ to 0. Hence, $p(x) \in \ker(\text{ev}_\alpha)$ meaning $(p(x)) \subseteq \ker(\text{ev}_\alpha)$, and by maximality of $(p(x))$ $(p(x)) = \ker(\text{ev}_\alpha)$. Since ideals correspond one-to-one with homomorphisms, we have a homomorphism:

$$j : \frac{k[x]}{(p(x))} \to L$$

and since $\frac{k[x]}{(p(x)} \cong K$, we have:

$$j : K \to L$$

Furthermore, for any $r \in k$, $j(r) = r$. Thus j commutes in the aforementioned diagram, completing the proof.

From now on, when we say *irreducible polynomial*, we will specifically mean *non-linear irreducible polynomials*, since linear irreducible polynomials produce trivial field extensions (i.e. k being extended to sovle for $x - \alpha \in k[x]$ is just k) unless stated otherwise.

The field extension to the Kronecker field K/k is *almost* universal with respect to finding roots to the polynomial $p(x)$. If it were universal, then if there was another field extension F/k such that F has a root of the irreducible polynomial $p(x) \in k[x]$, there would exist a *unique* homomorphism $j : F \to K$ such that the diagarm commutes. However, the homomorphism j need not be unique.

Example 19.2.3: Lack Of Uniqueness

Take $K = \mathbb{Q}[x]/(x^2 - 2)$ and $\mathbb{R}$. Then the polynomial $x^2 - 2$ has a root in $\mathbb{R}$, hence we know there exists a homomorphism:

$$K = \mathbb{Q}[x]/(x^2 - 2) \hookrightarrow \mathbb{R}$$

However, there exists two homomorphisms mapping K to $\mathbb{R}$. Since K extends $\mathbb{Q}$, any homomorphism can be represented by where the roots map: we can map $1 \mapsto 1$ and $\overline{x} \mapsto \sqrt{2}$, or map $1 \mapsto 1$ and $\overline{x} \mapsto -\sqrt{2}$. Both of these are valid homomorphisms, and so adjoints are not universal with respect to roots.

The universality can be recovered if we keep track of which root we want to map to (ex. $\sqrt{2}$), however we would have to make sure that there is only 1 homomorphism given some root (how do we know in more general cases that there cannot be 2 homomorphisms mapping $\overline{x}$ to the same root?). This concern is solved soon in theorem 19.2.27.

Since the aforementioned diagram commutes, notice that for any $r \in k$:

$$r \overset{!}{=} i(r) = j(\iota(r)) = j(r)$$

where ι is the natural inclusion into K, and the image of i is identified with the domain, justifying the $\overset{!}{=}$. Thus, j must *always* fix the base field, i.e. j is a k-homomorphism/isomorphism.

You might be concerned about *which* root of an irreducible polynomial does $\overline{x}$ represent in the previous theorem. For example, $x^2 - 2$ is irreducible over $\mathbb{Q}$, with $\pm\sqrt{2}$. So which root should we pick to represent $\overline{x}$? In fact, we can pick $\overline{x}$ to be represented *any* root of this polynomial: the field extending to contain $\sqrt{2}$ or $-\sqrt{2}$ will be isomorphic. More generally, if $p(x)$ is any irreducible polynomial, then $k[x]/(p(x))$ can be representing *any* choice of the possible roots of $p(x)$[6] and extending k to contain

[6]What it means to "choose" a root here is a bit ambiguous, since we have yet to say there exists a field that makes

that root. We can choose a particular root of $p(x)$, say α (which we define by saying α satisfies some polynomial equation), and isomorphically identify $K \xrightarrow{\sim} k(\alpha)$ (which we will show in more detail in theorem 19.2.8).

Note that to find the root of a polynomial, we required that polynomial to be irreducible. This technique will not obtain us a root of $(x^2-2)(x^3-2) = x^5 - 2x^3 - 2x^2 + 4$, namely because $(x^5 - 2x^3 - 2x^2 + 4)$ is not even a prime ideal (the resulting quotient contains zero-divisors). Section 19.5.2 constructs, for a given polynomial, an extension containing all of its roots, by adjoining roots of irreducible factors one at a time.

Note that we have not shown a way to "find" the root. For example, if we were looking at irreducible polynomial over $\mathbb{R}$ and we pick a root $\alpha \in \mathbb{C}$ that satisfies the polynomial equation, we do not have a computational way of finding it:

Example 19.2.4: Existence, but not construction

Let's say say F is a field extension $F/\mathbb{Q}$. Consider the irreducible polynomial $x^3 - 3x - 1$. over $\mathbb{Q}$ (it has no rationals roots by proposition 11.3.5). Thus, $F = \mathbb{Q}[x]/(x^3 - 3x - 1)$ is a field which has a root! The fact that all the roots of $x^3 - 3x - 1$ are real (and hence being able to identify F with a subfield of $\mathbb{R}$) can be considerd as taken for granted for now. We will have the tools to show that by the end of section 20.1.1. Visually, if we plot $x^3 - 3x - 1$, notice that all the roots are real, and hence $\mathbb{Q}$ can only by roots of $x^3 - 3x - 1$ which are real.

Let's say α is the root, so $\alpha \in \mathbb{R}$. We might hope that we can find which α in $\mathbb{R}$ satisfies the polynomial given that we know α is a root, however there is no *algebraic* way of finding this root! Using Newton-Raphsons approximation method, we can find that it is a real number $x \approx 1.97938...$. Finding these roots is a sub-branch of numerical analysis known as *root-finding algorithms*

For most common roots, we have already developped a symbol to represent them, namely $\sqrt[n]{m}$ is the root of $x^n - m$. More generally, if we extend $\mathbb{Q}[x]/(x^n - m)$ to solve another polynomial of a similar form, say $x^k - l$:

$$\frac{(\mathbb{Q}[x]/(x^n - m))[y]}{(y^k - l)}$$

we can "nest" as many square roots as we want. Since adding and multiplying is closed in a field, any extension of such polynomials produce elements of the form:

$$\sqrt[3]{\frac{3 + \sqrt[9]{40}}{\sqrt[8]{\sqrt{2}\sqrt{10}}}}$$

However, most more complicated polynomials are not given a special symbol, a notable exception being the golden ratio φ which is the root of $x^2 - x - 1$[7]. In section 20.2.4, we will further explore extensions which only add radical elements.

With the extension of a field through an irreducible polynomial constructed, it would be advantageous to be able to easily work with it's elements. Since K is a subfield of k, we can describe K as a k-vector-space!

$p(x)$ factor into linear terms. Such a field is constructed in section 19.5.1

[7]Though, this is not much of an exception since $\varphi = \frac{1+\sqrt{5}}{2}$

Theorem 19.2.5: Basis For Kronecker Field

Let $p(x) \in F[x]$ be an irreducible polynomial of degree n over the field F and let K be the field $F[x]/(p(x))$. Let $\theta = x \bmod (p(x)) \in K$. Then the elements

$$1, \theta, \theta^2, ..., \theta^{n-1}$$

are a basis for K as a vector space over F, so the degree of the extension is n, i.e., $[K : F] = n$. Thus

$$K = \left\{a_0 + a_1\theta + a_2\theta^2 + \cdots + a_{n-1}\theta^{n-1} | a_0, a_1, ..., a_{n-1} \in F\right\}$$

consists of all polynomials of degree $< n$ in θ. In particular, all field extensions of this form have finite degree.

***Proof*:**
Take $K = F[x]/(p(x))$, and consider $a(x) \in F[x]$ to be any polynomial. Then, by the Euclidean algorithm, we get that

$$a(x) = q(x)p(x) + r(x) \qquad q(x), r(x) \in F[x] \text{ with } \deg(r(x)) < n$$

then in K, we get that $[a(x)] = [r(x) + q(x)p(x)] = [r(x)]$, so any polynomial can be represented by it's residue polynomial, which will always be of degree $< n$. Thus, $1, \theta, \theta^2, ..., \theta^{n-1}$ (the image of $1, x, x^2, ..., x^{n-1}$) span the quotient. It remains to show they are linearly independent to conclude they are a basis.

If they were not, then for some $b_i \in F$ (not all 0)

$$b_0 + b_1\theta + \cdots + b_{n-1}\theta^{n-1} = 0$$

that is

$$b_0 + b_1x + \cdots + b_{n-1}x^{n-1} \equiv 0 \bmod (p(x))$$

meaning $p(x) | b_0 + b_1x + \cdots + b_{n-1}x^{n-1}$. However, that's a contradiction, since the degree of $p(x)$ is higher than the polynomial on the right hand side (which is at most $n - 1$)! Thus, these must be linearly independent. Since they also span, they fulfill the condition of a basis.

Since a basis is generated as a k-algebra by θ, any k-homomorphism $\varphi : k(\theta) \to F$ is determined by where it maps θ, making the map particularly easy to determine if we determine where θ maps to (the criterion for which we do in corollary 19.2.29).

As a reminder of arithmetics in $F[x]/(p(x))$:

Corollary 19.2.6: Shortcut On Arithmetics In K

Let K be as in theorem 19.2.2, and let $a(\theta), b(\theta) \in K$ be two polynomials of degree $< N$ in θ. Then addition in K is defined simply bu usual polynomial addition and multiplicatin in K is defined by

$$a(\theta)b(\theta) = r(\theta)$$

where $f(x)$ is the remainder (of degree $< n$) obtaiend after dividing the polynomial $a(x)b(x)$ by $p(x)$ in $F[x]$

***Proof*:**
An exercice in quotient ring of polynomials. Addition multiplication is done as in any quotient ring:

1. addition is usual addition of polynomials, since it does not change the degree
2. For multiplication, one can multiply the terms, then find a representative in the coset with degree $< n$

Note that what is described in corollary 19.2.6 works in any quotient field, including over polynomials which are *not* irreducible. However, the result is not a field, not even an integral domain [8].

Example 19.2.7: Field Extension Through Irreducible Polynomials

1. Let $F = \mathbb{R}$ and $p(x) = x^2 + 1$. Then we know that $x^2 + 1$ does not have a root in $\mathbb{R}$. Thus, consider:
$$K = \mathbb{R}[x]/(x^2 + 1)$$
is an extension field (of degree 2) that contains a root to this polynomial. Let $\theta = \overline{x}$. By theorem 19.2.5, $K/\mathbb{R}$ has degree 2 and any element $t \in K$ can be written as:
$$t = a + b\theta \qquad a, b \in \mathbb{R}$$
If you are comfortable with the arithmetics of $\mathbb{C}$, show that:
$$\mathbb{R}[x]/(x^2 + 1) \cong \mathbb{C}$$
2. Let $F = \mathbb{Q}$ and $p(x) = x^2 + 1$. Then by substitution with Eisntein's Criteron, $x^2 + 1$ is irreducible, hence $K = \mathbb{Q}[x]/(x^2 + 1)$ is a field extension of $\mathbb{Q}$. Since the base field is now $\mathbb{Q}$, any element $t \in K$ is of the form:
$$t = a + b\theta \qquad a, b \in \mathbb{Q}$$
3. Let $F = \mathbb{Q}$ and $p(x) = x^2 - 2$. Then $x^2 - 2$ is irreducible by Eisenstein's, so $F = \mathbb{Q}[x]/(x^2 - 2)$ is a field extension of $\mathbb{Q}$. Letting $K = \mathbb{Q}[x](x^2 + 1)$, show that:
$$F \ncong K$$
that is, extending by different roots of different irreducible polynomial produces distinct fields.

[8] Recall that if $p(x) = a(x)b(x)$, $a(x)$, $b(x)$ not being units, then in $F[x]/(p(x))$, $\overline{a(x)}, \overline{b(x)}$ are both nonzero, but $\overline{a(x)} \cdot \overline{b(x)} = \overline{0}$, meaning $F[x]/(p(x))$ has zero-divisors

4. Let $F = \mathbb{F}_2$ (the finite field with 2 elements) and $p(x) = x^2 + x + 1$. Then $p(x)$ is irreducible since $0^2 + 0 + 1 = 1^1 + 1 + 1 = 1$. Hence, $K = \mathbb{F}_2[x]/(x^2 + x + 1)$ is irreducible of degree 2. Can you make the multiplication table for this field?

Classifying Simple and Transcendental Extensions

Let's now turn our attention to classifying field extensions, given $k \subseteq K$ where we consider k the base field. If $A \subseteq K$, then we already have a notion of field extensions: $k \subseteq k(A)$. We will focus on the special cae where $A = \{\alpha\}$, that is, simple extension with $\alpha \in K$. As an example of this, imagine taking $\mathbb{R} \subseteq \mathbb{C}$, $\alpha = i$, and considering $\mathbb{R}(i)$. Then it is a known fact that $i^2 + 1 = 0$. We might ask if in general, given some $\alpha \in K$, can we find a polynomial that sovles it? In this way, we can characterize the field $k(\alpha)$ without needing to resort to taking the intersection of all subfields of K containing F and α. The answer is in fact, half the time. All simple extensions can be characterized by either being isomorphic to the rational functions over the base field or in terms of a quotient of a polynomial ring, giving us an easy classification of simple extensions:

Theorem 19.2.8: Classifying Simple Extensions

Let K/k be a field, $\alpha \in K$, and $k(\alpha)$. Consider $\text{ev}_\alpha : k[x] \to k(\alpha)$ mapping $f(x) \mapsto f(\alpha)$. Then if ev_α is injective, $k(\alpha)$ is an infinite extension and $k(\alpha) \cong k(x)$, and if ev_α is not injective, then there exists a polynomial $p(x)$ such that $k[x]/(p(x)) \cong k(\alpha)$. Furthermore, $p(x)$ is the polynomial of *minimal degree* that has α as a root.

Note that in this theorem, we are saying that *any* field over K extending k in which $p(x)$ contains a root in K and is irreducible in k contains a subfield isomorphic to the extension of k as we constructed in theorem 19.2.2 and that this field is (up to isomorphism) the smallest extension of k containing such a root.

***Proof*:**
Take the natural homomorphism

$$\text{ev}_\alpha : F[x] \to F(\alpha)(\subseteq K) \qquad a(x) \mapsto a(\alpha)$$

which maps the polynomial $a(x)$ to the polynomial evaluated at α. Note that $\text{ev}_\alpha(F[x])$ is an integral domain, since $F(\alpha)$ is integral domain.

If ev_α is injective, then $F[x]$ can be identified with an subring of $F(\alpha)$ that is an integral domain. By the universal property of field of fraction (theorem 9.5.4), ev_α uniquely extends to a homomorphism

$$\varphi : F(x) \to F(\alpha)$$

Since $\varphi(F(x))$ is a field containing F and α, $\varphi(F(x)) \supseteq F(\alpha)$, and since φ is a function $\varphi(F(x)) \subseteq F(\alpha)$, hence $\varphi(F(x)) = F(\alpha)$. To find the degree $[F(\alpha) : F]$, notice that $1[= \alpha^0], \alpha, \alpha^2, ...$ are all linearly independent over F in $F(\alpha)$ (since $1[x^0], x, x^2, ...$ are all linearly independent all linearly indepndent over F in $F(x)$), hence any basis must at least contain countably many linearly independent elements, and hence the degree must be infinite.

On the other hand, if ev_α is not injective, then $\ker(\text{ev}_\alpha) \neq 0$. The image $\text{ev}_\alpha(F[x])$ is an integral domain, so $\ker(\text{ev}_\alpha)$ is a nonzero prime ideal, hence a maximal ideal since $F[x]$ is a principal ideal domain. The quotient by it is then a field isomorphic to $\text{ev}_\alpha(F[x])$, which is therefore

a subfield of $F(\alpha)$ containing F and α, forcing $\text{ev}_\alpha(F[x]) = F(\alpha)$ and ev_α to be surjective, and since $F[x]$ is a euclidean domain (and hence a PID), any polynomial of minimal degree in $\ker(\text{ev}_\alpha)$ can represent the ideal, that is $(m_{\alpha,k}(x)) = \ker(\text{ev}_\alpha)$ for some minimal degree polynomial $m_{\alpha,k}(x) \in \ker(\text{ev}_\alpha)$. In fact, this minimal polynomial must be unique up to unit: if there where two minimal polynomials where $(m_{\alpha,k}) = (m'_{\alpha,k})$, then they must be equal up to unit, i.e. up to a factor in $k^\times$. Hence, we have that

$$\frac{k[x]}{(m_{\alpha,k}(x))} \cong F(\alpha)$$

By theorem 19.2.5, $[F(\alpha) : F] = \deg m_{\alpha,k}(x)$, and so the extension is finite, completing the proof.

This theorem motivates the following vocabulary:

Definition 19.2.9: Algebraic and Transcendental Elements

Let F be a field and let K be an extension of F. Then:

1. The element $\alpha \in K$ is said to be *algebraic* over F if α is a root of some nonzero polynomial $f(x) \in F[x]$.
2. If α is not algebraic over F (i.e., is not the root of any nonzero polynomial with coefficeints in F) then α is said to be *transcendental over* F.

Dealing with more general transcendental extensions is a straight-forward generlization of the previous thoerem. It naturally generlizes for $k(\alpha_1, ..., \alpha_n) \subseteq K$ where each α_i is transcendental. We first define the following term for the corollary:

Definition 19.2.10: Algebraically Independent

Let R be a k-algebra. Then $\alpha_1, ..., \alpha_n \in R$ are *algebraically independent* over k if the k-algebra homomorphism ev_k (i.e., the evaluation map) which fixes k:

$$\text{ev}_k : k[x_1, ..., x_n] \to R \qquad \text{ev}_k(x_i) = \alpha_i$$

is injective. The set is called *algebraically dependent* otherwise.

The definition is stated for a finite list, and that is the only case a polynomial relation can see: a relation involves finitely many indeterminates however large the set. So the notion extends to arbitrary subsets without any new content.

Definition 19.2.11: Algebraically Independent Set

Let K/k be a field extension. A subset $S \subseteq K$ is *algebraically independent* over k if every finite list of distinct elements of S is algebraically independent over k in the sense of definition 19.2.10. The empty set is algebraically independent.

The analogy with linear algebra now runs further than it first appears. An algebraically independent set behaves like a linearly independent one, a set over which K is algebraic behaves like a spanning

one, and the two notions meet in an object that deserves the name basis.

Definition 19.2.12: Transcendence Basis

Let K/k be a field extension. A subset $B \subseteq K$ is a *transcendence basis* of K over k if B is algebraically independent over k and K is an algebraic extension of $k(B)$.

Existence follows the same route as for vector-space bases: take a maximal independent set. Maximality is exactly what forces the algebraicity.

Theorem 19.2.13: Existence of a Transcendence Basis

Let K/k be a field extension and let $S \subseteq K$ be a subset with K algebraic over $k(S)$. Let $A \subseteq S$ be algebraically independent over k. Then there is a transcendence basis B of K/k with $A \subseteq B \subseteq S$. In particular, taking $S = K$ and $A = \emptyset$, every field extension has a transcendence basis.

***Proof*:**
Order by inclusion the collection of algebraically independent subsets of S containing A. It is nonempty, containing A. A chain in this collection has its union as an upper bound, and that union is algebraically independent because a dependence relation involves finitely many elements and would therefore already lie in some member of the chain. By Zorn's lemma there is a maximal such subset B.

It remains to see that K is algebraic over $k(B)$. Let $s \in S$. If $s \in B$ this is clear, and otherwise $B \cup \{s\}$ is a subset of S containing A that strictly contains B, so by maximality it is algebraically dependent: some finite list of distinct elements of $B \cup \{s\}$ satisfies a nontrivial polynomial relation over k. That list must involve s, since B is independent, so collecting the relation as a polynomial in s with coefficients in $k[B]$ gives a nonzero polynomial over $k(B)$ killing s. Hence s is algebraic over $k(B)$.

So every element of S is algebraic over $k(B)$, whence $k(S)$ is algebraic over $k(B)$, and K is algebraic over $k(S)$ by hypothesis. Algebraicity is transitive in towers, so K is algebraic over $k(B)$ and B is a transcendence basis, as we sought to show.

The substance is that the size of a transcendence basis does not depend on the basis chosen. As in linear algebra, this rests on an exchange argument comparing an independent set against a set over which everything is algebraic.

Lemma 19.2.14: Independent Sets Are No Larger Than Algebraic Generating Sets

Let K/k be a field extension, let $S = \{s_1, \ldots, s_n\} \subseteq K$ be finite with K algebraic over $k(S)$, and let $A \subseteq K$ be algebraically independent over k. Then A is finite with $|A| \leq n$.

***Proof*:**
It suffices to show that no $n+1$ distinct elements of A can be algebraically independent. Suppose $a_1, \dots, a_{n+1} \in A$ are distinct. The argument replaces the s_j by the a_i one at a time, and the claim to be maintained after r steps is that, after renumbering the s_j, the field K is algebraic over $k(a_1, \dots, a_r, s_{r+1}, \dots, s_n)$.

Step 1: the base case and the replacement. For $r = 0$ the claim is the hypothesis. Suppose it holds for some $r < n+1$, so K is algebraic over $F_r = k(a_1, \dots, a_r, s_{r+1}, \dots, s_n)$. Then a_{r+1} is algebraic over F_r, so there is a nonzero polynomial relation

$$f\big(a_{r+1};\, a_1, \dots, a_r,\, s_{r+1}, \dots, s_n\big) = 0$$

with f a nonzero polynomial over k in which the first slot occurs. The relation must involve at least one s_j with $j > r$: otherwise it exhibits a nontrivial algebraic relation among $a_1, \dots, a_{r+1}$ over k, contradicting the independence of A. Renumber so that s_{r+1} occurs. Reading the relation as a nonzero polynomial in s_{r+1} over $k(a_1, \dots, a_{r+1}, s_{r+2}, \dots, s_n)$ shows s_{r+1} is algebraic over that field, so F_r is algebraic over $F_{r+1} = k(a_1, \dots, a_{r+1}, s_{r+2}, \dots, s_n)$, and by transitivity K is too. This advances the claim to $r+1$.

Step 2: the contradiction. Running the replacement n times gives that K is algebraic over $k(a_1, \dots, a_n)$. Then a_{n+1} is algebraic over $k(a_1, \dots, a_n)$, which is a nontrivial algebraic relation among distinct elements of A, contradicting independence. Hence A has at most n elements, completing the proof.

Theorem 19.2.15: Transcendence Degree Is Well-Defined

Let K/k be a field extension admitting a finite transcendence basis. Then every transcendence basis of K/k is finite, and any two have the same number of elements.

***Proof*:**
Let B be a finite transcendence basis, of size n, and let B' be any transcendence basis. Since K is algebraic over $k(B)$ and B' is algebraically independent, lemma 19.2.14 gives that B' is finite with $|B'| \le n$. Exchanging the roles of B and B', which is legitimate because B' is now known to be finite and K is algebraic over $k(B')$, gives $n \le |B'|$. Hence $|B'| = n$, as we sought to show.

Definition 19.2.16: Transcendence Degree

Let K/k be a field extension admitting a finite transcendence basis. The *transcendence degree* $\operatorname{trdeg}_k K$ is the common number of elements of its transcendence bases. An extension is algebraic exactly when $\operatorname{trdeg}_k K = 0$, and $\operatorname{trdeg}_k k(x_1, \dots, x_n) = n$ for indeterminates x_i.

Transcendence degree adds along towers, which is what makes it usable as a notion of dimension. The proof is the statement that a transcendence basis of the top over the middle, together with one of the middle over the bottom, is a transcendence basis of the top over the bottom.

Proposition 19.2.17: Transcendence Degree Is Additive in Towers

Let $k \subseteq K \subseteq L$ be fields with L/k admitting a finite transcendence basis. Then

$$\text{trdeg}_k L = \text{trdeg}_k K + \text{trdeg}_K L$$

***Proof*:**
Let B be a transcendence basis of K/k and C a transcendence basis of L/K. Both are finite by lemma 19.2.14, since L is algebraic over $k(B \cup C)$ once the two are combined. The sets B and C are disjoint, an element of C being transcendental over $K \supseteq k(B)$.

Algebraicity. L is algebraic over $K(C)$, and K is algebraic over $k(B)$, so $K(C)$ is algebraic over $k(B)(C) = k(B \cup C)$. By transitivity L is algebraic over $k(B \cup C)$.

Independence. Suppose a nontrivial polynomial relation over k holds among distinct elements of $B \cup C$. Collect it as a polynomial in the elements of C with coefficients in $k[B] \subseteq K$. Those coefficients are not all zero, since the relation is nontrivial and B is algebraically independent over k. So the relation is a nontrivial algebraic relation among elements of C over K, contradicting the independence of C over K.

So $B \cup C$ is a transcendence basis of L/k, and counting gives $\text{trdeg}_k L = |B| + |C| = \text{trdeg}_k K + \text{trdeg}_K L$, completing the proof.

Corollary 19.2.18: Classifying Finitely Generated Transcendental Extensions

Let K/k be a field extensions such that $K = k(\alpha_1, ..., \alpha_n)$ where each element is trancsendental. Then if $k(x_1, ..., x_n)$ is the field of rational functions over the indeterminates x_i[a], then, the set $\alpha_1, ..., \alpha_n$ is algebraically independent, and:

$$k(x_1, ..., x_n) \cong_k k(\alpha_1, ..., \alpha_n)$$

[a] sometimes called *formal variables*

The case for arbitrarily many transcendental elements is the same proof with more book-keeping on notation.

***Proof*:**
This is an immediate generalization of theorem 19.2.8

This shows that in terms of fields, algebraically independent sets do not offer much to our analysis of classification. They act more like a basis with essentially no relation, a resemblance made precise in definition 19.2.12 below. This is not to say that they do not offer any use in Galois theory, where we will correspond group for transcendental extensions, but in terms of field theory their structure is very simple. Thus, we will take more time stuyding algebraically dependent sets, especially since we can use theorem 19.2.2 to study study irreducible polynomials that aquire a root.

Going back to the minimal polynomial that we found in the proof,

Definition 19.2.19: Minimal Polynomial

Let K/k be a field extension and $\alpha \in K$ such that the map ev_α of theorem 19.2.8 is not injective. The *minimal polynomial* $m_{\alpha,k}(x)$ of α over k is the monic polynomial of least degree in $k[x]$ having α as a root.

It exists by theorem 19.2.8, after dividing by the leading coefficient, and it is unique: two monic polynomials of the least degree d with root α differ by a polynomial of degree less than d with root α, which is therefore 0. Every $f \in k[x]$ with $f(\alpha) = 0$ is divisible by $m_{\alpha,k}$: dividing gives $f = qm_{\alpha,k} + r$ with $r = 0$ or $\deg r < \deg m_{\alpha,k}$ (theorem 11.1.1), and $r(\alpha) = 0$ forces $r = 0$ by the minimality of $\deg m_{\alpha,k}$. So $m_{\alpha,k}$ generates $\ker(\mathrm{ev}_\alpha)$.

Proposition 19.2.20: Minimal Polynomial Over A Larger Field

If L/F is an extension of fields and α is algebraic over both F and L, then $m_{\alpha,L}(x)$ divides $m_{\alpha,F}(x)$ in $L[x]$.

***Proof*:**
The polynomial $m_{\alpha,F}$ lies in $F[x] \subseteq L[x]$ and has α as a root. Dividing in $L[x]$ (theorem 11.1.1) gives $m_{\alpha,F} = qm_{\alpha,L} + r$ with $q, r \in L[x]$ and $r = 0$ or $\deg r < \deg m_{\alpha,L}$. Evaluating at α gives $r(\alpha) = 0$, so $r = 0$ by the minimality of $\deg m_{\alpha,L}$ (definition 19.2.19), and $m_{\alpha,L}$ divides $m_{\alpha,F}$ in $L[x]$, completing the proof.

The minimal polynomial will always be irreducible: If it was reducible, then $m_{\alpha,k}(x) = g(x)h(x)$ would produce a polynomial where either $g(\alpha) = 0$ or $h(\alpha) = 0$, contradicting the minimality of $m_{\alpha,k}(x)$. The minimal polynomial can be found from a characteristic polynomial:

Proposition 19.2.21: Finding Minimal Polynomial

Let F/k be a finite field extension of degree n, let $\alpha \in F$, and let $L_\alpha \colon F \to F$ be multiplication by α, $y \mapsto \alpha y$. Then L_α is k-linear, its characteristic polynomial $P_{L_\alpha} \in k[x]$ is monic of degree n with $P_{L_\alpha}(\alpha) = 0$, and the minimal polynomial $m_{\alpha,k}$ divides P_{L_α}.

***Proof*:**
The map L_α is k-linear, since $\alpha(y+y') = \alpha y + \alpha y'$ and $\alpha(cy) = c(\alpha y)$ for $c \in k$, by distributivity and commutativity in F. By proposition 13.5.2(1), computed in a k-basis of F with n elements, P_{L_α} is monic of degree n, and $P_{L_\alpha}(L_\alpha) = 0$ by proposition 14.3.10. For $\beta, \gamma \in F$ and $c \in k$, $L_{\beta\gamma} = L_\beta \circ L_\gamma$, $L_{\beta+\gamma} = L_\beta + L_\gamma$ and $L_c = c\,\mathrm{id}_F$, so $f(L_\alpha) = L_{f(\alpha)}$ for every $f \in k[x]$. Hence $L_{P_{L_\alpha}(\alpha)} = 0$, and $P_{L_\alpha}(\alpha) = L_{P_{L_\alpha}(\alpha)}(1) = 0$. In particular ev_α is not injective, and $m_{\alpha,k}$ divides P_{L_α} by the divisibility property following definition 19.2.19, completing the proof.

Gröbner bases give another way to compute minimal polynomials (section 23.3).

Example 19.2.22: Minimal Polynomials

1. The minimal polynomial for $\sqrt{2}$ over $\mathbb{Q}$ is $x^2 - 2$ and $\sqrt{2}$ is of degree 2 over $\mathbb{Q}$: $[\mathbb{Q}(\sqrt{2}), \mathbb{Q}] = 2$

2. The minimal polynomial for $\sqrt[3]{2}$ over $\mathbb{Q}$ is x^3-2 and $\sqrt[3]{2}$ is of degree 3 over $\mathbb{Q}$: $[\mathbb{Q}(\sqrt[3]{2}),\mathbb{Q}]=3$
3. similarly, for any $n>1$, the polynomial x^n-2 is irreducible (by Eisenstein's Criterion).
4. The minimal polynomial and the degree of an element α are dependent on the base field! For example, if $F=\mathbb{R}$, then the element $\sqrt[n]{2}$ has degree 1, with minimal polynomial
$$m_{\sqrt[n]{2},\mathbb{R}}(x)=x-\sqrt[n]{2}$$
5. the minimal polynomial for the golden ratio φ is x^2-x-1.
6. In general, most algebraic elements do not have a special symbol representing them, and so we would have to say that some $\alpha\in K$ has minimal polynomial (say) x^5-x-1

As a result of theorem 19.2.8, it also makes sense to ask the context of the existence of an irreducible polynomial what is the degree of an α over F: given $p(x)$ is the polynomial for which α is a root, then it's the degree of $\dim_F F[x]/(p(x))=\dim_F F(\alpha)$. We may write $\deg\alpha$ (or $\deg_F\alpha$) for the degree of α (over F). If $\deg\alpha=1$, then $\alpha\in F$.

Combining the classification of finite simple extensions with corollary 19.2.6, we get to easily represent $F(\alpha)$

Corollary 19.2.23: Representing $F(\alpha)$

Suppose in theorem 19.2.8 that $p(x)$ is of degree n. Then
$$F(\alpha)=\left\{a_0+a_1\alpha+a_2\alpha^2+\cdots+a_{n-1}\alpha^{n-1}|a_0,a_1,...,a_{n-1}\in F\right\}\subseteq K$$

Proposition 19.2.24: Finite Simple Extensions Elements

Let $k(\alpha)/k$ be a finite simple extension. Then:
$$k[\alpha]=k(\alpha)$$

***Proof*:**
The inclusion $k[\alpha]\subseteq k(\alpha)$ holds since $k[\alpha]$ is the smallest subring containing k and α, while $k(\alpha)$ is a field, in particular a ring, containing both.

For the reverse inclusion, consider the evaluation map $\mathrm{ev}_\alpha: k[x]\to k(\alpha)$ of theorem 19.2.8. If ev_α were injective, that theorem would make $k(\alpha)$ an infinite extension of k, contradicting finiteness. Hence ev_α is not injective, and α has a minimal polynomial $p(x)$ over k, say of degree n. By corollary 19.2.23, every element of $k(\alpha)$ has the form
$$a_0+a_1\alpha+a_2\alpha^2+\cdots+a_{n-1}\alpha^{n-1}\qquad a_i\in k$$
which is a polynomial expression in α with coefficients in k, hence lies in $k[\alpha]$ by proposition 19.1.15(1). Therefore $k(\alpha)\subseteq k[\alpha]$, and the two are equal.

This justifies why we only need to care about polynomials, and not rational polynomials.

Example 19.2.25: Simple Extension

1. In $\mathbb{Q}(\sqrt{2})$, $\dim_{\mathbb{Q}} \mathbb{Q}(\sqrt{2}) = 2$, and we can write $\mathbb{Q}(\sqrt{2}) = \left\{a + b\sqrt{2} \mid a, b \in \mathbb{Q}\right\}$. We could also have chosen the other root of $x^2 - 2$, namely $-\sqrt{2}$. However, these two fields are isomrophic: $\mathbb{Q}(\sqrt{2}) \cong \mathbb{Q}(-\sqrt{2})$, showing they are algebraically indistinguishable.
2. In $\mathbb{Q}(\sqrt[3]{2})$, $\dim_{\mathbb{Q}} \mathbb{Q}(\sqrt[3]{2}) = 3$, and we can write $\mathbb{Q}(\sqrt[3]{2}) = \left\{a + b\sqrt[3]{2} + c(\sqrt[3]{2})^2 \mid a, b, c \in \mathbb{Q}\right\}$.
3. Over $\mathbb{R}$, $x^3 - 2$ has no more solutions than the last example. However, over $\mathbb{C}$, there are two more solutions:
$$\zeta_2 = \sqrt[3]{2}\left(\frac{-1 + i\sqrt{3}}{2}\right) \qquad \zeta_3 = \sqrt[3]{2}\left(\frac{-1 - i\sqrt{3}}{2}\right)$$
Thus, $\mathbb{Q}(\zeta_2)$ and $\mathbb{Q}(\zeta_3)$ are field extensions.

Thus, we have fully classified all simple extensions of a field and dealt with transcendental extensions. In following sections, we will show how to classify fields generated by finitely many elements (ex. $k(\alpha, \beta)$) and infinitely many elements. Before continuing into that endeavour, isomorphisms between fields should be given some more attention to be more cear on how to classify fields.

The fields in example 19.2.25 need not be isomorphic (as fields) if the roots solve different polynomials, meaning different irreducible polynomials will produce different extensions:

Example 19.2.26: $\mathbb{Q}(\sqrt{2}) \ncong \mathbb{Q}(\sqrt{5})$

Take $\mathbb{Q}(\sqrt{2})$ and $\mathbb{Q}(\sqrt{5})$. Let's say φ is an isomorphism. Then we know that
$$\varphi(1) = 1$$
since 1 is the only element of order 1 in both fields. Then:
$$\varphi(\sqrt{2}) = a + b\sqrt{5}$$
for some non-zero value in the codomain. Then
$$\varphi(2) = a^2 + 2ab\sqrt{5} + 5b^2$$
but we also know that
$$\varphi(1) = 1 \qquad \varphi(2) = \varphi(1 + 1) = \varphi(1) + \varphi(1) = 1 + 1 = 2$$
so
$$2 = a^2 + 2ab\sqrt{5} + 5b^2 \qquad a, b \in \mathbb{Q}$$
If $a = b = 0$, $2 = 0$, a contradiction. If $a, b \neq 0$, then:
$$\frac{2 - a^2 - 5b^2}{2ab} = \sqrt{5}$$
implying that $\sqrt{5}$ is a rational number, a contradiction. If $a = 0, b \neq 0$, then:
$$\frac{\sqrt{2}}{\sqrt{5}} = b$$
but b is a rational number, a contraidction. If $a \neq 0, b = 0$, then:
$$\sqrt{2} = a$$
but a is a rational number, a contradiction. Thus, these two fields cannot be isomorphic.

However, notice that the extension of to $\mathbb{Q}(\sqrt{2})$ and $\mathbb{Q}(-\sqrt{2})$ were isomorphic, and so was all the extensions of $\mathbb{Q}$ by roots of x^3-2:

$$\mathbb{Q}(\sqrt[3]{2}) \cong \mathbb{Q}\left(\sqrt[3]{2}\left(\frac{-1+i\sqrt{3}}{2}\right)\right) \cong \mathbb{Q}\left(\sqrt[3]{2}\left(\frac{-1-i\sqrt{3}}{2}\right)\right)$$

even though those 3 fields are not equal. In particular, that means that non of these fields contain *all* of the roots of x^3-2. One of the large motifs in the following study of extensions is to find extensions in which for any irreducible (or more generally any polynomial) will contain *all* of the roots.

19.2.1 Isomorphism of Fields Extensions

As we have seen in theorem 19.2.2, If we know that an irreducible polynomial $p(x) \in k[x]$ has a root in a field F. Then there exists a [not necessarily unique] isomorphism φ such that the following diagram commutes:

$$\begin{array}{ccc} k[x]/(p(x)) & \xrightarrow{\varphi} & F \\ {\scriptstyle\iota}\uparrow & \nearrow_{\iota} & \\ k & & \end{array}$$

The fact that φ is not unique gives raise to several interesting results. As we have shown in example 19.2.3, $\mathbb{Q}(\sqrt{2})$ has two homomorphisms into $\mathbb{R}$. In fact, since $-\sqrt{2} \in \mathbb{Q}(\sqrt{2})$, we have that:

$$\begin{array}{ccc} \mathbb{Q}(\sqrt{2}) & \xrightarrow{\varphi} & \mathbb{Q}(-\sqrt{2}) \\ {\scriptstyle\iota}\uparrow & \nearrow_{\iota} & \\ \mathbb{Q} & & \end{array}$$

If we extend the bottom to be the identity map form k to k, then we get a square:

$$\begin{array}{ccc} \mathbb{Q}(\sqrt{2}) & \xrightarrow{\sim} & \mathbb{Q}(-\sqrt{2}) \\ \uparrow & & \uparrow \\ \mathbb{Q} & \xrightarrow{\text{id}} & \mathbb{Q} \end{array}$$

Showing the fields with the two roots of x^2-2 are isomorphic. In fact,$-\sqrt{2} \in \mathbb{Q}(\sqrt{2})$, and so this is in fact a field automorphism (though in general it does not have to be, like $\mathbb{Q}(\sqrt[3]{2})$ and $\mathbb{Q}(\sqrt[3]{2}\zeta_3)$). We have claimed earlier than two fields that have two different roots of the same irreducible polynomial adjoined to them are algebraically indistinguishable. This shows it in the case for x^2-2 over $\mathbb{Q}$, and the following theorem shows the generlizatoin of this result. Note how by keeping track of the root we have in fact recovered a sense of uniqueness:

Theorem 19.2.27: Extending Isomorphisms to Adjoint Fields

Let $k_1 \subseteq F_1 = k_1(\alpha_1)$, $k_2 \subseteq F_2 = k_2(\alpha_2)$ be simple extensions and let $\varphi : k_1 \to k_2$ be an isomorphism of fields. Let $p(x) \in k_1[x]$ be an irreducible polynomial and let $p'(x) \in k_2[x]$ be the irredcibble polynomial obtained by applying the map φ to the coefficients of $p(x)$. Let α_1 be a root of $p(x)$ (in some extension of k_1) and let α_2 be a root of $p'(x)$ (in some extension k_2). Then there is an isomorphism:

$$\sigma : k_1(\alpha_1) \to k_2(\alpha_2) \qquad \alpha_1 \mapsto \alpha_2$$

mapping α_1 to α_2 and extending φ, .i.e., such that σ restricted to F is the isomorphism φ.

In other words, if we have

$$\begin{array}{ccc} k_1(\alpha) & & k_2(\beta) \\ \uparrow & & \uparrow \\ k_1 & \xrightarrow{\sim} & k_2 \end{array}$$

and $\iota(m_{\alpha,k_1})(x)) = m_{\beta,k_2}(x)$ (i.e. it maps the coefficients of the first minimal polynomial to the second one), then we can *uniquely* extend ι to an isomorphism j between the two adjoint fields:

$$\begin{array}{ccc} k_1(\alpha) & \overset{\sim}{\dashrightarrow} & k_2(\beta) \\ \uparrow & & \uparrow \\ k_1 & \xrightarrow{\sim} & k_2 \end{array}$$

such that $j(\alpha) = \beta$. Note that j being an extension of ι means the elements of k_1 are fixed in j.

***Proof*:**
Let $\varphi : k_1 \to k_2$ be an isomorphism of fields. The map φ induces a ring isomorphism:

$$f^\varphi : k_1[x] \to k_2[x]$$

defined by applying φ to the coefficeints of a polynomial in $k_1[x]$. Let $p(x) \in k_1[x]$ be an irreducible polynomial, and let $p'(x) \in k_2[x]$ be the polynomial obtained by applying the map φ to the coefficients of $p(x)$, i.e., the image of $p(x)$ under f^φ. The isomorphism f^φ maps the maximal ideal $(p(x))$ to the ideal $(p'(x))$, so the ideal is also maximal, which shows that $p'(x)$ is also irreducible in $k_2[x]$.

Taking the quotinet by these ideals of the map, we get the following isomorphism of fields

$$k_1[x]/(p(x)) \to k_2[x]/(p'(x))$$

By theorem 19.2.8, the left side is isomorphic to $k_1(\alpha_1)$, and the right side to $k_2(\alpha_2)$, so composing these maps will produce a map for σ! It should also be clear now that the restriction of this isomorphism to k_1 is φ.

This isomorphism will come back big time when we address galois theory. It is sometimes represented in as in the following diagram:

$$\begin{array}{lcc} \sigma: & k_1(\alpha_1) & \xrightarrow{\cong} k_2(\alpha_2) \\ & \big| & \big| \\ \varphi: & k_1 & \xrightarrow{\cong} k_2 \end{array}$$

If we let $\mathrm{id}: k \to k$ be our k-isomorphism, and $m_{\alpha,k}(x)$ be our minimal polynomial with roots α, β, then $\varphi: k(\alpha) \xrightarrow{\sim} k(\beta)$ is also an isomorphism, showing that the roots of a minimal polynomials are algebraically indistinguishable. Furthermore, we can upgrade Kronecker's Theorem so that it gives us a universaly property: instead of L being a field that has a root of $p(x)$, upgrade that to $\alpha \in L$ being a root of $p(x)$. Then there exists a *unique* homomorphism mapping $\overline{x}$ to α (with uniqueness established by the above theorem).

Through this theorem, we get another important insight. If we have a non-trivial finite field extension $k(\alpha)/k$ which has roots of a minimal polynomial $m_{k,\alpha}(x)$, then if any other roots of $m_{k,\alpha}(x)$ are in $k(\alpha)$, there is a k-automorphisms of $k(\alpha)$ (can you see why a k-automorphism is determined by where it sends the roots?). This means we can find elements of the group $\mathrm{Aut}_k(k(\alpha))$ (where the subscript means we fix k), and hence the structure of $k(\alpha)$ [9]. More conretely, $k(\alpha)/k$ represents adding a new element α to the field k which satisfies an algebraic relation $m_{\alpha,k}(\alpha)$ (a polynomial). Finding information about the new field $k(\alpha)$ by looking at the k-automorphisms is essentially studying the properties of the polynomial $m_{\alpha,k}(x)$.

Even better, we will show that this characterizes *all* k-automorphisms, giving us a complete description of these symmetries. These symmetries are at the heart of studying fields in Galois theory. When Galois originally formulated his theory, he looked different ways to permute the roots and noticed that there are often limitation to the permutations of the roots since the roots may be related to each other[10]. For example if α is a root of $x^3 - x - 1$, then the other two roots are:

$$\frac{1}{1-\alpha} \qquad 1 + \frac{1}{\alpha}$$

Similarly, if ζ is a root of $x^n - 1$, then the other roots of $x^n - 1$ are $\zeta^2, \zeta^3, ..., \zeta^{n-1}, 1$. Thus, we take some time to define our terms more precisely, and elaborate further what the automorphisms look like:

Definition 19.2.28: Automorphism and fixed Element

Let K be a field and $\mathrm{Aut}(K)$ be the collection of automorphisms (isomorphisms from k to itself). Then:

1. An auotmorphism $\sigma \in \mathrm{Aut}(K)$ is said to *fix* an element $\alpha \in K$ if $\sigma\alpha = \alpha$. If F is a subset of K, then an automorphism σ is said to *fix* F if it fixes all the elements of F

$$\sigma a = a \qquad \forall a \in F$$

2. If F/k be an extension of fields, then $\mathrm{Aut}(F/k)$ or $\mathrm{Aut}_k(F)$ is the collection of all automorphsism of F which fix k.

[9] Recall that we already used the automorphism group to deduce information about groups, for example $\mathrm{Out}(G) \cong_{\mathbf{Grp}} \mathrm{Aut}(G)$ if and only if G is abelian

[10] Later we shall see that the roots are almost never related to each other, that is most Galois groups are S_n, but it is a good insight to notice that the roots of small polynomials are often related

the previous theorem gives us the following link between $\text{Aut}_k(F)$ and F given that F is finite and simple:

Corollary 19.2.29: Order of Fixed Automorphism Group

Let F/k be a simple finite extension (so $F = k(\alpha)$ for some $\alpha \in F$), and let $m_{k,\alpha}(x) \in k[x]$ be the minimal polynomial of α. Then $|\text{Aut}_k(F)|$ is equal to the number of *distinct* roots of $m_{k,\alpha}(x)$ in F. In particular,

$$|\text{Aut}_k(F)| \leq [k(\alpha) : k] \qquad |\text{Aut}_k(F)| = [k(\alpha) : k]_d$$

where $[k(\alpha) : k]_d$ represents the number of *distinct* roots $k(\alpha)$ contains of the minimal polynomial $m_{k,\alpha})(x)$. Equality holds if and only if $m_{k,\alpha}(x)$ factors over F as a product of *distinct linear* polynomials

This result will be called the *fixed root criterion* when we cover Galois theory.

***Proof*:**
Let $\sigma \in \text{Aut}_k(F)$ be an automorphism fixing k (so for any $t \in k$, $\sigma(t) = t$). Then since every element $t \in F = k(\alpha)$ can be written as a polynomial $t = f(\alpha) \in k[\alpha]$ (recall that $k(\alpha)$ is finite, and so has a basis of the form $\alpha, \alpha^2, ..., \alpha^n$ for some appropriat n), and σ fixes k, all the elements are determined by where α maps to, that is $\sigma(\alpha)$. Then since σ is an automorphism (hence ring homomorphism), given

$$x^n + a_{n-1}x^{n-1} + \cdots + a_1 x + a_0$$

is the minimal polynomial with coefficients from k so that

$$\alpha^n + a_{n-1}\alpha^{n-1} + \cdots + a_1\alpha + a_0 = 0$$

then, applying any automorphism σ to this polynomial will get us

$$\sigma(\alpha^n + a_{n-1}\alpha^{n-1} + \cdots + a_1\alpha + a_0) = \sigma(0)$$
$$\sigma(\alpha)^n + a_{n-1}\sigma(\alpha)^{n-1} + \cdots + a_1\sigma(\alpha) + \sigma(a_0) = 0 \qquad \sigma \text{ fixes } a_i \text{ for each } i$$

since $a_i \in k$ for each i, showing that $\sigma(\alpha)$ is also a root of the minimal polynomial, i.e. σ must map α to some other root of $m_{k,\alpha}$.

As α is the generator, all roots are determined by where ‘ maps to, hence there can be at most $\deg(m_{k,\alpha}(x))$ automorphisms.

Conversely, for any root β of $p(x)$ in $k(\alpha)$, $\beta \in k(\alpha)$, we can take the isomorphism $\text{id} : k \to k$, which by theorem 19.2.27, there exists a unique lift to a root $k(\alpha) \to k(\beta)$ that fixes k. Since $k(\alpha) \cong k(\beta)$, then we can use this isomorphism to define an automorphism from $k(\alpha)$ to $k(\alpha)$, showing us that $\text{Aut}_k(F)$ must have at least as many elements as there are roots of the minimal polynomial in F. If F contains all the roots of $p(x)$ and each root of $p(x)$ is distinct, then $|\text{Aut}_k(F)| = [F : k]$, completing the proof.

Interpreting the above example as a group actions on the set of roots R_F of $m_{\alpha,k}(x)$ in F, $\text{Aut}_k(F) \curvearrowright R_F$, we have that $\text{Aut}_k(F)$ acts *faithfully and transitively* on the set of roots of $p(x)$ in F (the


group $\mathrm{Aut}_k(F)$ can be identified with some transitive subgroup of the symmetric group acting on the roots of $p(x)$ in F). This correlation hints at the connection beween fields and groups at the heart of the galois theory, since any collection of automorphisms will always form a group[11]. The main impediment to directly translating this result of more general [finite] field extensions[12] is that the minimal polynomial might not factor into *linear* and *distinct* terms over the simple extension $k(\alpha)/k$[13]. For example, in $\mathbb{Q}(\sqrt[3]{2})$, the polynomial $x^3 - 1$ does not fully factor. The next two sections will encompass finding field extensions in which these conditions are met. In particular, we shall take some time to find fields in which:

1. All polynomials factor (splitting fields)
2. If $f(x) \in k[x]$ is irreducible, then in F/k, either $f(x)$ factors completely or $f(x)$ remains irreducible (normal extensions)
3. Given a polynomial $f(x)$, F/k factors completely (Splitting field)
4. If $f(x)$ is irreducible in k, then in F/k, $f(x)$ factors into linear terms of degree 1 (Separable extensions)

As a final word on relating isomorphisms and extensions, note that if $\dim_k A = \dim_k B$, this does not imply $[B : A] = 1$ or that $A \cong_k B$:

Example 19.2.30: Nuance On Dimension

Let $A = \mathbb{Q}(\sqrt{3})$ and $B = \mathbb{Q}(\zeta_3\sqrt{3})$. Then the two are of the same dimension, both extend $\mathbb{Q}$ and $A \cong_k B$, but $[B : A]$ is not even well defined. To visualize:



Exercise 19.2.1

1. Let $\mathrm{ch}(k) = n$, $n \geq 0$, and $\varphi : k \to K$ be a homomorphism. Then $\mathrm{ch}(K) = n$.
2. Show that the intersection of any collection of subfields of a field is a field. Is the same true for the union? What if the fields where given a partial order through inclusion?
3. Let $N \subseteq M_{2\times 2}(\mathbb{R})$ be a subset where
$$N = \left\{ \begin{pmatrix} a & b \\ -b & a \end{pmatrix} \;\middle|\; a, b \in \mathbb{R} \right\}$$
Then $N \cong \mathbb{C}$.
4. Let E/k and F/k be field extensions inside a common field. Show that if E/k is finite, then so is EF/F. Show that if E/k and F/k are finite, so is EF/k.

[11] If you are not convinced, now is good time to check this
[12] Infinite Galois extensions need a topology on the Galois group (theorem 50.8.8).
[13] It is possible that a irreducible polynomial factors linearly, but the factors are not distinct, see section 19.6

5. Suppose that $f(x) \in k[x]$ where $f(x)$ factors into $f(x) = p_1(x)p_2(x)\cdots p_n(x)$ where $p_i(x) \neq p_j(x)$. Show that $k[x]/(f(x))$ is a product of fields (Hint: Chinese Remainder Theorem). If one of the terms had multiplicity greater than 1, would the result still be a product of fields?
6. (If you know Calculus) The $\mathbb{R}$-algebra $\mathbb{R}[x]/(x^2)$ is sometimes the *dual numbers*. Let any element of this degree 2 extension of $\mathbb{R}$ be written in the form $a + b\epsilon$. If $p'(x)$ is the derivtive of $p(x)$, show that $p(a + b\epsilon) = P(a) + bP'(a)\epsilon$, that is, the derivitve "automatically" shows up.
7. Let m, n be square free and $n \neq m$. Show that $\mathbb{Q}(\sqrt{n}) \ncong_{\mathbb{Q}} (\sqrt{m})$.
8. Let ζ_n be a root of unity where n is odd. Show that $\mathbb{Q}(\zeta_n) \cong_{\mathbb{Q}} \mathbb{Q}(\zeta_{2n})$

19.3 Algebraic Extensions

We will now focus some attention on the algebraic elements of an extension. We first give name to elements for which all elements are algebraic or non-algebraic:

Definition 19.3.1: Algebraic and Transcendental Extensions

Let F be a field and let K be an extension of F. Then:

1. The element $\alpha \in K$ is said to be *algebraic* over F if α is a root of some nonzero polynomial $f(x) \in F[x]$.
2. If α is not algebraic over F (i.e., is not the root of any nonzero polynomial with coefficeints in F) then α is said to be *transcendental over* F.
3. The extension K/F is said to be *algebraic* or an *algebraic extension* if every element of K is algebraic over F.
4. The extension K/F is said to be *transcendental* or a *transcendental extension* if every element of K not in F is transcendental over F.

Note that if an element α is algebraic over a field F, then it is algebraic over *any* extension field L of F (if $f(x)$ having α as a root has coefficients in F, then it also has coefficients in L). Note too that the polynomial for which α must be a root need not be irreducible, however it is an immediate consequence that if α is the root of a polynomial $p(x) = (a_1(x))^{n_1}\cdots(a_k(x))^{n_k}$, it is a root for some irreducible polynomial $a_i(x)$.

Example 19.3.2: Algebraic extensions

1. Take $\mathbb{Q}(\sqrt{2})/\mathbb{Q}$. Then every element in $\mathbb{Q}(\sqrt{2})$ is a solution to a polynomial over $\mathbb{Q}$, thus $\mathbb{Q}(\sqrt{2})/\mathbb{Q}$ is algebraic: any element $a + b\sqrt{2}$ is the root of $\left(\frac{x-a}{b}\right)^2 - 2$. If you take $\mathbb{Q}(\sqrt{2})$ as a vector-space over $\mathbb{Q}$, then we see that 1 and $\sqrt{2}$ generate $\mathbb{Q}(\sqrt{2})$. Note that $\sqrt{2}$ is not in $\mathbb{Q}$, but but $\sqrt{2}$ is algebraic over $\mathbb{Q}$).

   More generally, is it true that any finite simple extension $F(\alpha)$ of F is an algebraic extension? Is every element of $F(\alpha)$ the root of a polynomial with coefficients in F?

2. $\mathbb{C}$ as an $\mathbb{R}$-vector space is generated by 1 and i. Both of these are root to polynomials over $\mathbb{R}$, in particular $x-1$ and x^2+1. It is a famous result that any $c \in \mathbb{C}$ is a solution of a polynomial over $\mathbb{R}$ (i.e., with coefficients from $\mathbb{R}$). Thus, $\mathbb{C}/\mathbb{R}$ is algebraic.

   The degree of $[\mathbb{C} : \mathbb{R}] = 2$

3. Consider $\mathbb{C}$ again. For any $\alpha \in \mathbb{C}$, is there a polynomial $p(x) \in \mathbb{C}[x]$ for which $p(\alpha) = 0$? In a sense, we are asking if $\mathbb{C}$ is algebraic over itself. [a]

4. For a moment, take for granted that there is no polynomial in $\mathbb{Q}$ such that π is a root (this is Lindemann's theorem, which this book does not prove). Then π is *transcendental* over $\mathbb{Q}$, and so $\mathbb{R}/\mathbb{Q}$ is *not* an algebraic extension.

   Here is an idea to ponder: What is $[\mathbb{R} : \mathbb{Q}]$? The answer will be given in example 19.3.15

[a] The answer is yes! We call a field such that every element of it has a root over itself *algebraically closed*

In these examples, the algebraic extensions all had a finite degree. Is it possible to have an algebraic extension with infinite degree? If K is algebaric over F, then every element of K is a roof a polynomial over F? What about the converse: If K/F is finite, is K algebraic over F? (take a moment to ponder here)

Proposition 19.3.3: degree of Algebraic Extension

The element α is algebraic over F if and only if the simple extension $F(\alpha)/F$ is finite. More precisely, if α is an element of an extension of degree n over F, then α satisfies a polynomial of degree at most n over F and if α satisfies a polynomial of degree n over F, then the degree of $F(\alpha)$ over F is at most n.

***Proof*:**
If α is algebraic over F (so for some $p(x) \in F[x]$, $p(\alpha) = 0$), then the degree of the extension $F(\alpha)/F$ is the degree of the minimal polynomial, making it an extension of finite degree at most n.

Conversely, let α be an element of degree n over F (ex. $[F(\alpha) : F] = n$). Then by theorem 19.2.5, we know that $n+1$ elements will be linearly dependent:

$$c_0 + c_1\alpha + c_2\alpha^2 + \cdots + c_n\alpha^n = 0$$

with $c_0, c_2, ..., c_n \in F$ which are not all 0. Thus, α must be the root of some non-zero polynomial with coefficients from F (of degree $\leq n$), showing α is algebraic over F.

Corollary 19.3.4: Finite Extension Then Algebraic Extension

If the extension K/F is finite, then it is algebaric

***Proof*:**
let K/F be finite and take any $\alpha \in K$. Consider the simple extension $F(\alpha)$. Consider K as an F-vector space, then since the extension is finite, $\dim_F K = n$. Now, $F(\alpha) \subseteq K$ would be a

subspace of K ($F(\alpha)$ also being an F-vector sapce), so

$$\dim_F F(\alpha) \leq \dim_F K \qquad \text{or} \qquad [F(\alpha) : F] \leq [K : F]$$

showing the extension is finite, and so by proposition 19.3.3, α is algebraic over F. since α was an artibrary element of K, this means that K is algebaric over F, as we sought to show.

Though not important to us in this chapter, we also have the following characterisation of an algegraic extension more useful in algebraic number theory:

Corollary 19.3.5: Algebraic Extension and Algebras

K/F is algebraic if and only if every sub F-algebra is a field

***Proof*:**
Suppose first that K/F is algebraic, and let $A \subseteq K$ be a sub F-algebra, that is, a subring of K containing F. Let $a \in A$ be nonzero. Since a is algebraic over F, there is a polynomial

$$p(x) = c_n x^n + c_{n-1} x^{n-1} + \cdots + c_1 x + c_0 \in F[x]$$

of minimal degree with $p(a) = 0$. We claim $c_0 \neq 0$: otherwise $p(x) = x\, q(x)$ for some $q \in F[x]$ of smaller degree, and $a\, q(a) = 0$ with $a \neq 0$ in the field K forces $q(a) = 0$, contradicting minimality. Rearranging $p(a) = 0$ gives

$$a \cdot \left(-c_0^{-1}\left(c_n a^{n-1} + c_{n-1} a^{n-2} + \cdots + c_1\right)\right) = 1$$

The element in parentheses is a polynomial expression in a with coefficients in F, hence lies in the ring A. Therefore a is invertible in A, and A is a field.

Conversely, suppose every sub F-algebra of K is a field, and let $\alpha \in K$. The subring $F[\alpha]$ is a sub F-algebra of K, hence a field by hypothesis. If α were transcendental over F, the evaluation map $\mathrm{ev}_\alpha : F[x] \to K$ would be injective, since no nonzero polynomial has α as a root, and its image is $F[\alpha]$. Then $F[x] \cong F[\alpha]$ would be a field. But $F[x]$ is not a field: for any $f \in F[x]$, the degree formula over the integral domain F gives $\deg(x\, f) = 1 + \deg(f) \geq 1$, so $x\, f \neq 1$ and x has no inverse. This contradiction shows α is algebraic over F. Since α was arbitrary, K/F is algebraic.

Note that the converse of corollary 19.3.4 is not true: If K is algebraic over F, this does not mean that K/F has finite degree

Example 19.3.6: Algebraic and infinite degree
We require corollary 19.3.14 which is introduced in a couple of pages, but we can still state the case with the added assumption here to get the idea:

Take $\mathbb{C}/\mathbb{Q}$, and take the set $\overline{\mathbb{Q}}$ to be the set of all algebraic elements over $\mathbb{Q}$. Then by the aforementioned corollary, this is a subfield of $\mathbb{C}$. Since $\sqrt[n]{2}$ is algebraic over $\mathbb{Q}$ (root of the polynomial $x^n - 2$), we have

$$[\mathbb{Q}(\sqrt[n]{2}) : \mathbb{Q}] = n$$

for every n. Since $\mathbb{Q}(\sqrt[n]{2}) \subseteq \overline{\mathbb{Q}}$, it follows that $\overline{\mathbb{Q}}$ is an algebraic extension of infinite degree.

However, a weaker version of this direction does have a converse, and we will build up to it now. Let's first show that the finite extension of a finite extension remains a finite extension (if you like, the composition of finite extensions is a finite extension)

Theorem 19.3.7: Multiplicity of Finite Extensions (Tower Law)

Let $k \subseteq E \subseteq F$ be fields. Then

$$[F : k] = [F : E][E : k]$$

that is, extension degree multiply each other, where if one side of the equation is infinite, so is the other.

***Proof*:**

The infinite case is clear, so we will deal with the finite case. First, if F is finite dimensional over k, then the subspace E is also finite dimensional. Furthermore, any linear combination of elements of F over the field k naturally is a linear combination over the larger field E. Thus, if $[F : k]$ is finite, so is $[F : E]$ and $[E : k]$.

Conversely, suppose $[F : E]$ and $[E : k]$ are both finite. Let $(e_1, e_2, ..., e_m)$ be a basis for E over k and $(f_1, f_2, ..., f_n)$ be a basis for F over E. I claim that

$$(e_1f_1, e_1f_2, ..., e_1f_n, e_2f_1, ..., e_mf_n)$$

is a basis for F over k.

Let $g \in F$. Then for appropriate $d_i \in E$,

$$g = \sum_j d_j f_j$$

Next, for each d_j, for appropriate $c_{ij} \in k$, we have

$$d_j = \sum_i c_{ij} e_i$$

Thus, we have:

$$g = \sum_i \sum_j c_{ij} e_i f_j$$

Therefore, the products e_if_j span F, showing that F must at most be finite dimensional.

To show they form a basis, assume

$$\sum_{i,j} \lambda_{ij} e_i f_j = 0$$

Then:

$$\sum_j \left(\sum_i \lambda_{ij} e_i \right) f_j = 0$$

which, since the the elemnts f_j are linearly independent over E, we have that $\sum_i \lambda_{ij} e_i = 0$. But then, the elements e_i are linearly indepenent over e_i,and so each $\lambda_{ij} = 0$, showing that the original linear combination is also linearly independent, as we sought to show.

Notice how this corollary mirrors Lagranges theorem with respect to the order of groups. This parallel will capture our attention in the next chapter. The following corollary deepends this connection:

Corollary 19.3.8: Degree Extension Divisibility

Suppose L/F is a finite extension and let K be any subfield of L contianing F, $F \subseteq K \subseteq L$. Then $[K : F]$ divides $[L : F]$

***Proof*:**
Since

$$[L : F] = [L : K][K : F]$$

this result holds.

This result gives us a similar power that Lagrange's theorem gives us

Example 19.3.9: Use Of Tower Law

1. We can quickly rule out that $\sqrt{2} \notin \mathbb{Q}(\sqrt[n]{2})$ if n is odd. To see this, if $\sqrt{2} \in \mathbb{Q}(\sqrt[n]{2})$, then $\mathbb{Q}(\sqrt{2}) \subseteq \mathbb{Q}(\sqrt[n]{2})$. Then by what we have just shown:

   $$[\mathbb{Q}(\sqrt[n]{2}) : \mathbb{Q}] = [\mathbb{Q}(\sqrt[n]{2}) : \mathbb{Q}(\sqrt{2})][\mathbb{Q}(\sqrt{2}) : \mathbb{Q}]$$

   However, that would imply that an even number divides an odd number, a contradiction.

2. More generally, we can conclude the following: If K/k is an extension of odd degree and $\alpha \in K$, then α can be written as a polynomial in α^2, that is $\alpha = p(\alpha^2) = \sum_i k_i(\alpha^2)^i$ for $k_i \in k$.

   To see this, we first notice that through simple set theory we must have

   $$k \subseteq k(\alpha^2) \subseteq k(\alpha)$$

   and that $k(\alpha)/k(\alpha^2)$. To find the degree d of this extension, notice that over $k(\alpha^2)$, we get that $x^2 - \alpha^2 \in k(\alpha^2)[x]$, so $d \leq 2$. On the other hand, d must divide $[k(\alpha) : k]$ which is odd, forcing us to have $d = 1$. Thus $k(\alpha^2) = k(\alpha)$, and so $\alpha \in k(\alpha^2)$.

3. Let K/k be an extension with $[K : k]$ prime. Then there is *no* field E with $k \subsetneq E \subsetneq K$, since $[E : k]$ would divide the prime $[K : k]$. This is similar to how all finite groups of prime order are simple.

4. Take $\mathbb{Q} \subseteq \mathbb{R}$ and consider $\mathbb{Q}[x]/(x^3 - 3x - 1) \cong \mathbb{Q}(\alpha)$ as in example 19.2.4. Since $[\mathbb{Q}(\sqrt{2}) : \mathbb{Q}] = 2$, and $[\mathbb{Q}(\alpha) : \mathbb{Q}] = 3$, and $2 \nmid 3$, then $\mathbb{Q}(\sqrt{2}) \not\subseteq \mathbb{Q}(\alpha)$, so $\sqrt{2} \notin \mathbb{Q}(\alpha)$! It is much more difficult to directly show $\sqrt{2}$ cannot be written as a $\mathbb{Q}$-linear combination of $1, \alpha, \alpha^2$.

Continuing to strive towards a partial converse, we define the following generlization of a simple extension. The key feature about finitely generated fields is that they can be decomposed into simple extensions:

Lemma 19.3.10: Recursive Definition Of Extension Field

$F(\alpha,\beta) = (F(\alpha))(\beta)$, i.e., the field generated over F by α and β is the field generated by β over the field $F(\alpha)$ generated by α.

***Proof*:**
This proof takes complete advantage that by definition, field extensions are the *smallest* field containing F and α (or α and β)

The field $F(\alpha,\beta)$ is the smallest field to contain F,α,β, so $F(\alpha,\beta) \subseteq (F(\alpha))(\beta)$. Conversely, $F((\alpha))(\beta)$ is the smallest field to contain $F(\alpha)$ and β. Since $F(\alpha) \subseteq F(\alpha,\beta)$ and $\beta \in F(\alpha,\beta)$, $(F(\alpha))(\beta) \subseteq F(\alpha,\beta)$, implying

$$F(\alpha,\beta) = (F(\alpha))(\beta)$$

With this, we can break down any finitely generated:

$$K = F(\alpha_1,\alpha_2,...,\alpha_k) = (F(\alpha_1,\alpha_2,...,\alpha_{k-1}))(\alpha_k) = ((\cdots F(\alpha_1))(\alpha_2))\cdots(\alpha_n)$$

Thus, we get the following chain of extensions:

$$F = F_0 \subseteq F_1 \subseteq F_2 \subseteq \cdots \subseteq F_k = K$$

where

$$F_{i+1} = F_i(\alpha_{i+1}) \qquad i = 0,1,...,k-1$$

Importantly, this reduces everything down to lots of simple extensions! Now, suppose that the elements $\alpha_1,\alpha_2,...,\alpha_k$ are algebraic over F of degrees $n_1,n_2,...,n_k$

$$[F(\alpha_1):F] = n_1,\ [F(\alpha_2):F] = n_2 \cdots [F(\alpha_k):F] = n_k$$

By proposition 19.2.20, we can replace F with F_i. Then these can all be characterized in terms of simple extensions, meaning we can use proposition 19.3.3. The relative extension degree $[F_{i+1}:F_i]$ is equal to the degree of the minimal polynomoial of α_{i+1} over F_i, which is at most n_{i+1} (and is equal to n_{i+1} if and only if the minimal polynomial of α_{i+1} over F remains irreducible over F_i). So, by the Tower Law:

$$[K:F] = [F_k:F_{k-1}][F_{k-1}:F_{k-2}]\cdots[F_1:F_0] \leq [F(\alpha_1):F][F(\alpha_2):F]\cdots[F(\alpha_k):F] \tag{19.1}$$

And so $[K:F]$ must be a *finite* extension of degree less than or equal to $n_1n_2\cdots n_k$! We sum up this entire discussion of finite degrees in the following theorem:

Theorem 19.3.11: Degree of Algebraic Extension

The extension K/F is finite if and only if K is generaed by a finite number of algebraic elements over F. More precisely, a field generated over F by a finite number of algebraic elements of degrees $n_1,n_2,...,n_k$ is algegraic of degree $\leq n_1,n_2,...,n_k$

Before, we hade

$$\alpha \text{ algebraic over } F \Leftrightarrow F(\alpha)/F \text{ finite}$$

and when we try to generlize, we loose one side of the implication

$$K \text{ algebraic over } F \Leftarrow K/F \text{ finite}$$

with the counter example 19.3.6 for $\Rightarrow$.

We now restricted the hypothesis to give us the if and only if again:

$$K \text{ generated by finite number of algebraic elements over } F \Leftrightarrow K/F \text{ finite}$$

***Proof*:**
Let the extension K/F be finite, so $a_1, a_2, ..., a_n$ forms a basis for K over F. Then since $F(a_i) \subseteq K$ as a F-vector-space, $[F(a_i) : F] \leq [K : F]$, meaning it has finite degree, and so by proposition 19.3.3, a_i is algebraic. Since a_i was arbitrary, this means that every a_i is algebraic. Thus K is generated by a finite number of algebraic elements over F.

For the converse, let's say K is generated by a finite number of algebraic elements over F. Let

$$\alpha_1, \alpha_2, ..., \alpha_n$$

all be algebraic over F and generate K. Since they generated K, $K = F(\alpha_1, \alpha_2, ..., \alpha_n)$. Then by what we have seen in equation (19.1), we have that K/F is finite.

Using what we have found, it is easier to compute the degree of non-simple extensions:

Example 19.3.12: Computing Degree of non-simple Extension

1. The extension $\mathbb{Q}(\sqrt[6]{2}, \sqrt{2})$ is $\mathbb{Q}(\sqrt[6]{2})$ since $\sqrt{2} \in \mathbb{Q}(\sqrt[6]{2})$. Another way of showing this is that the degree d of $\sqrt{2}$ over $\mathbb{Q}(\sqrt[6]{2})$ is 1. Thus, even though the degree of $\sqrt{2}$ is 2 and the degree of $\sqrt[6]{2}$ is 6, the degre of $\mathbb{Q}(\sqrt[6]{2}, \sqrt{2})$ is 6, not 12.

2. Consider $\mathbb{Q}(\sqrt{2}, \sqrt{3})$. We will proceed to find the degree of this extensions over $\mathbb{Q}$. Since $\sqrt{3}$ is of degree 2 over $\mathbb{Q}$, then the degree of the extension $\mathbb{Q}(\sqrt{2}, \sqrt{3})/\mathbb{Q}(\sqrt{2})$ is at most 2 ($\sqrt{3}$ can at most add another dimension), and *is* 2 if and only if $x^2 - 3$ is irreducible over $\mathbb{Q}(\sqrt{2})$. To see if it is, let's suppose it is reducible. Since $x^2 - 3$ is of degree 2, by proposition 11.3.5, it is irreducible if and only if it has a root, that is, if $\sqrt{3} \in \mathbb{Q}(\sqrt{2})$.

   If $\sqrt{3} \in \mathbb{Q}(\sqrt{2})$, $\sqrt{3} = a + b\sqrt{2}$. From here, it's a lot of manipulation (squaring both sides and checking cases). It will turn out that every possibility will make either $\sqrt{2}$, $\sqrt{3}$ or $\sqrt{6}$ rational, a contradiction.

   Thus, $\deg_{\mathbb{Q}(\sqrt{2})} \mathbb{Q}(\sqrt{2}, \sqrt{3}) = 2$, so

   $$\deg_{\mathbb{Q}} \mathbb{Q}(\sqrt{2}, \sqrt{3}) = 4$$

   and we can find the basis for it by "closing" the set $1, \sqrt{2}, \sqrt{3}$ to produce $1, \sqrt{2}, \sqrt{3}, \sqrt{6}$, giving us

   $$\mathbb{Q}(\sqrt{2}, \sqrt{3}) = \left\{ a + b\sqrt{2} + c\sqrt{3} + d\sqrt{6} | a, b, c, d \in \mathbb{Q} \right\}$$

Corollary 19.3.13: Algebraic Elements are Closed

Suppose α and β are algebraic over F. Then $\alpha \pm \beta$, $\alpha\beta$, α/β (for $\beta \neq 0$, are all algebraic (since α/β is algebraic $1/\alpha$ is also algebraic)

***Proof*:**
All these elements are part of $F(\alpha, \beta)$, which is finite over F by theorem 19.3.11, and so are algebraic by corollary 19.3.4 (in particular, $F(\alpha + \beta)$ is a simple extension, and since $\alpha + \beta \in F(\alpha, \beta)$(and $F \subseteq F(\alpha, \beta)$), we have that $F(\alpha + \beta) \subseteq F(\alpha, \beta)$ by definition, so it is a finite extension, so by corollary 19.3.4 every element will be a root of a polynomial over F).

Corollary 19.3.14: Algebraic Elements Form a Field

Let L/k be an arbitrary extension. Then the collection of elements of k that are algebraic over F form a subfield K of F.

***Proof*:**
By corollary 19.3.13, we get that the collection is closed under $+$ and $\times$. From here, it is easy to verify any extra axiom we want.

Example 19.3.15: Algebraic Closure

1. Consider the extension $\mathbb{C}/\mathbb{Q}$, and let $\overline{\mathbb{Q}}$ represent the subfield of $\mathbb{C}$ containing all elements that are algebraic over $\mathbb{Q}$. Then $\sqrt[n]{2} \in \overline{\mathbb{Q}}$ for all $n \in \mathbb{N}$ (taking the positive roots), so $[\overline{\mathbb{Q}} : \mathbb{Q}] \geq n$ for every $n > 1$. Thus, $\overline{\mathbb{Q}}$ is an *infinite* algebraic extension of $\mathbb{Q}$, called the field of *algebraic numbers*. We have now proved what we have assumed in example 19.3.6.

2. Take $\mathbb{R}$ and the subfield $\overline{\mathbb{Q}}$ consisting of all algebraic elements over $\mathbb{Q}$, and consider $\mathbb{R} \cap \overline{\mathbb{Q}}$. This set is countable: $\mathbb{Q}$ is countable, and $\mathbb{Q}[x]$ consists of the countable union of polynomials of degree n ($S_0 \cup S_1 \cup \cdots$ where S_n contains all polynomials of degree n), so $\mathbb{Q}[x]$ is countable. $\overline{\mathbb{Q}}$ must have a cardinality at least less than $\mathbb{Q}[x]$, and so is also countable.

   Since $\mathbb{R}$ is uncountable, we see that there must be elements in $\mathbb{R}$ which are *not* algebraic (i.e. transcendental) over $\mathbb{Q}$. In fact, the vast majority of elements are transcendental. The subfield $\overline{\mathbb{Q}} \cap \mathbb{R}$ is a *proper* subfield of $\mathbb{R}$.

   Though the majority of elements[a] are transcendental, it is extremely difficult to show that an element *is* transcendental. For example, it was proved that $\pi = 3.1415926...$ was transcendental in 1880, and $e = 2.171828...$ is transcendental in 1870. Proving these are transcendental is very involved. Even combining these elements is tricky to prove: e^π was proven to be transcendental in 1934, however as of writing this book, it is unknown whether π^e is transcendental. In fact, it is also not known whether $\pi + e$ or πe are transcendental.

   We have only a small list of numbers which we *know* to be transcendental, even though the vast majority of them are transcendental [b]. Known transcendental numbers include e^a for a nonzero algebraic number a, a^b where a is algebraic $\neq 0, 1$ and b is algebraic and irrational (ex. $2^{\sqrt{2}}$), and $\sin(a)$ for a nonzero algebraic number a.

[a] In terms of probability, 100% of the elements

[b] If you have taken some statistics/measure theory, then if $\mathbb{A}$ are the algebraic numbers over $\mathbb{Q}$, $\int \chi_{\mathbb{A}} = 0$, i.e., the chances of picking an algebraic number from the set of real number is 0!

We can extend the results of theorem 19.3.11 a bit further to algebraic extensions (finite or infinite)

Theorem 19.3.16: Composing Algebraic extensions

Let $k \subseteq E \subseteq F$ be field extensions. Then F/k is algebraic if and only if F/E and E/k are algebraic.

***Proof*:**
If F/k is algebraic, then *a fortiori* F/E is algebraic (If $\alpha \in F$ are all roots of some polynomial $k[x]$ and $k \subseteq E$, then they are certainly roots in $E[x]$). Since $E \subseteq F$, *a priori* E/k.

For the other way, assume E/k and F/E are algebraic, and consider $\alpha \in F$. Since F/E is algebraic, there exists a $p(x) \in E[x]$ such that

$$p(\alpha) = \alpha^n + e_{n-1}\alpha^{n-1} + \cdots + e_1\alpha + e_0 = 0$$

We thus have that α is algebraic over the subfield $k(e_0, ..., e_{n-1}) \subseteq E$. Hence, by theorem 19.3.11

$$k(e_1, ..., e_{n-1}) \subseteq k(e_1, ..., e_{n-1}, \alpha)$$

is a finite extension. Furthermore, by theorem 19.3.11 again, we have that

$$k \subseteq k(e_1, ..., e_{n-1})$$

is also a finite extension, since each e_i is in E, so is algebraic over k by assumption that E/k is algebaric. Hence, by the Tower Law,

$$k \subseteq k(e_1, ..., e_n, \alpha)$$

is a finite extension as well, and hence α is algebraic over k. Since α was arbitrary, F is algebraic over k, as we sought to show.

To close off this section, we show how our previous discussion applies to composite fields:

Proposition 19.3.17: Degree Of Composite Field

Let K_1 and K_2 be two finite extensions of a field F contained in K. Then

$$[K_1K_2 : F] \leq [K_1 : F][K_2 : F]$$

with equality if and only if an F-basis for one of the fields remains linearly independent over the other field. If $\alpha_1, \alpha_2, ..., \alpha_n$ and $\beta_1, \beta_2, ..., \beta_m$ are bases for K_1 and K_2 over F respectively, then the elements $\alpha_i\beta_j$ for $i = 1, 2, ..., n$ and $j = 1, 2, ..., m$ span K_1K_2 over F

***Proof*:**
Let $n = [K_1 : F]$, $m = [K_2 : F]$, and let $S \subseteq K$ be the F-span of the nm elements $\alpha_i\beta_j$.

The set S is closed under multiplication: $(\alpha_i\beta_j)(\alpha_k\beta_l) = (\alpha_i\alpha_k)(\beta_j\beta_l)$, where $\alpha_i\alpha_k \in K_1$ is an F-combination of the α's and $\beta_j\beta_l \in K_2$ is an F-combination of the β's, so expanding exhibits the product as an F-combination of the $\alpha_i\beta_j$. The general case follows by bilinearity of multiplication. Moreover $K_1 \subseteq S$: given $x \in K_1$, write $x = \sum_i a_i\alpha_i$ with $a_i \in F$ and $1 = \sum_j c_j\beta_j$ with $c_j \in F$ (as $1 \in K_2$), so that $x = x \cdot 1 = \sum_{i,j} a_i c_j\, \alpha_i\beta_j \in S$. Symmetrically $K_2 \subseteq S$, and in particular $1 \in S$. Hence S is a subring of K containing F, and a finite dimensional F-vector space of dimension at most nm.

The ring S is in fact a field. Let $s \in S$ be nonzero and consider the F-linear map $S \to S$, $y \mapsto sy$. It is injective since K is a field, hence by corollary 13.1.20 it is surjective, so $sy = 1$ for some $y \in S$ and s is invertible in S. Since each $\alpha_i\beta_j \in K_1K_2$ we have $S \subseteq K_1K_2$, while S is a subfield of K containing K_1 and K_2, so the minimality in definition 19.1.16 gives $K_1K_2 \subseteq S$. Hence $S = K_1K_2$, the elements $\alpha_i\beta_j$ span K_1K_2 over F, and


$$[K_1K_2 : F] \leq nm = [K_1 : F][K_2 : F]$$

For the equality criterion, note that every element of $K_1K_2 = S$ can be written $\sum_{i,j} c_{ij}\alpha_i\beta_j = \sum_i \left(\sum_j c_{ij}\beta_j\right)\alpha_i$ with $\sum_j c_{ij}\beta_j \in K_2$, so $\alpha_1, \ldots, \alpha_n$ span K_1K_2 as a K_2-vector space and $[K_1K_2 : K_2] \leq n$. If the α_i are linearly independent over K_2, then $[K_1K_2 : K_2] = n$. If they are dependent over K_2, then, K_2 being a field, some α_i lies in the K_2-span of the others, so $n - 1$ elements span and $[K_1K_2 : K_2] \leq n - 1$. By the Tower Law (theorem 19.3.7),

$$[K_1K_2 : F] = [K_1K_2 : K_2][K_2 : F] = m\,[K_1K_2 : K_2]$$

which equals nm if and only if $[K_1K_2 : K_2] = n$, that is, if and only if the F-basis $\alpha_1, \ldots, \alpha_n$ of K_1 remains linearly independent over K_2. Exchanging the roles of K_1 and K_2 gives the same criterion with the β_j over K_1, proving the statement.

summing up the result in a diagram:



Corollary 19.3.18: Degree of Composite Field and Equality

Suppose that $[K_1 : F] = n$, $[K_2 : F] = m$ in proposition 19.3.17, where n and m are relatively prime $(n, m) = 1$. Then $[K_1K_2 : F] = [K_1 : F][K_2 : F] = nm$

***Proof*:**
In general, the extension is divisible by n and m since K_1 and K_2 are subfields of K_1K_2 (so divisible by its least common multiple). Since $(m, n) = 1$, then $[K_1K_2 : F]$ is divisible by nm. Since by proposition 19.3.17, $[K_1K_2 : F] \leq nm$, we get $[K_1K_2 : F] = nm$

Exercise 19.3.1

1. Let F be a field with $\text{ch}(F) \neq 2$ and let K/F be an extension of degree 2. Show that $K = F(\beta)$ for some $\beta \in K$ with $\beta^2 = D \in F$, where D is not a square in F.
2. Let E/k and F/k be field extensions inside a common field. Show that if E/k is algebraic, then so is EF/F. Show that if E/k and F/k are algebraic, so is EF/k.

19.4 Historical Detour: Straightedge and Compass Construction

For millennia in mathematical history, mathematicians as far back as ancient greeks tried to construct shapes or compute numbers through geometric means by using a straight edge and compass. For example, using a straight edge and compass, there is a way to compute sums, products, quotient (which would have been known as ratios to the ancient greeks), and square-roots. Geometry, mathematicians have figured out how to double the area of the square, take exactly half the angle, and navigate using the stars [14]. These all conformed with the rules of Euclid's geometry, and so straight-edge and compass constructions seemed like a powerful algorithm for geoemtry and arithmetics. However, a few problems were open since at least since the times of the ancient greeks around 400 BC, namely:

1. Given a square, using a straight-edge and compass, can we find a circle with the same area
2. Given a cube, using a straight-edge and compass, can we find another cube that's double it's volume
3. Given an angle, using a straight-edge and compass, can we triscect the angle (i.e. split the angle into 3 equa angles)

These problems do not have much use practically. However the simpliciy in their statement, the ubiquity of using rulers and compasses in many fields of engeneering, navigation, and so on, as well as the belief that the foundation of the world's geometry is inherently euclidean (in particular, that geometric reality followed euclidean rules and were provable using euclid's simple axioms), made these problems the central attention of a huge plethora of mathematicians for over 2 millennia.

With the new tools of field theory, we can characterize the types of numbers a straight-edge and compass can give us:

1. using a straight-dge construction, the 4 basic operations $(+, -, \times, \div)$ can be derivd. Thus, it will form a field.

[14] and an additional instrument to measure the angle between the person and the horizon, and the north star

2. the compass constructions allows the performance of square-roots. Translating this into the cartesian plane, it will be the intersction of a straight-line and a circle, which will sometimes gives polynomials which will have solutions *not* inside the base field, and so we would use an algebraic extension. Such polynomials will always be of degree 2. Hence, if we keep trying to extend these fields, we will always get multiples of 2 as the degree of the extension

From this comes the theorem that feels so mind-blowing that I can state after literal millenia of people trying to solve this problem:

Theorem 19.4.1: Straightedge And Compass Imposibilities

The 3 classical greek straight-edge and compass problems:

1. **Doubling the Cube** Using only straight edge and compasss, construct a cube with precisely twice hte volume of a given cube
2. **Triscecting an Angle** Given a straightedge and compass, triseced any given angle θ
3. **Squaring the circle** Given a straightedge and compass, construct a square whose area is precisely the area of a given circle.

are all answered in the negative

***Proof*:**
Set up coordinates so that the two points given at the start are $(0,0)$ and $(1,0)$. A construction step draws the line through two points already constructed, or the circle centred at a point already constructed whose radius is the distance between two points already constructed. The new points are the points of intersection of these lines and circles. Call $\alpha \in \mathbb{R}$ *constructible* when it is a coordinate of a point reachable by finitely many such steps.

Step 1: one step at a time, the coordinates move up by degree at most 2. Let $F \subseteq \mathbb{R}$ be a subfield containing the coordinates of every point constructed so far. The line through two such points has an equation $ax + by = c$ with $a, b, c \in F$, and the circle centred at such a point through such a point has an equation $x^2 + y^2 + dx + ey + f = 0$ with $d, e, f \in F$, since the square of the radius is a sum of squares of differences of coordinates. There are three ways a new point can appear.

1. Two distinct lines meet, distinctness being what makes the intersection a single point. Solving the two linear equations gives coordinates already in F.
2. A line meets a circle. Solving the linear equation for one coordinate and substituting it into the quadratic leaves a quadratic equation over F for the other coordinate. Adjoining a root of it gives an extension of F of degree 1 or 2, and the first coordinate is an F-linear expression in the second.
3. Two distinct circles meet, distinctness again being what makes the intersection finite. Subtracting one equation from the other cancels $x^2 + y^2$ and leaves a linear equation over F, satisfied by both points of intersection. So the intersection of the two circles is the intersection of one of them with that line, and the previous case applies.

Step 2: a constructible number has degree a power of 2 *over* $\mathbb{Q}$. Running Step 1 along a construction of α produces a tower

$$\mathbb{Q} = F_0 \subseteq F_1 \subseteq \cdots \subseteq F_m \subseteq \mathbb{R}$$

with $[F_{i+1} : F_i] \leq 2$ for every i and $\alpha \in F_m$. By the Tower Law (theorem 19.3.7) applied repeatedly, $[F_m : \mathbb{Q}] = 2^k$ for some $k \geq 0$. Applying the Tower Law once more to $\mathbb{Q} \subseteq \mathbb{Q}(\alpha) \subseteq F_m$ shows $[\mathbb{Q}(\alpha) : \mathbb{Q}]$ divides 2^k, so

$$[\mathbb{Q}(\alpha) : \mathbb{Q}] = 2^j \quad \text{for some } j \geq 0$$

Step 3: (1) doubling the cube. Starting from a cube of side 1, a cube of twice the volume has side $\sqrt[3]{2}$, so the problem asks for $\sqrt[3]{2}$ to be constructible. The polynomial $x^3 - 2$ is irreducible over $\mathbb{Q}$ by Eisenstein's criterion at the prime 2 (corollary 11.3.11), so it is the minimal polynomial of $\sqrt[3]{2}$ and theorem 19.2.8 gives $\mathbb{Q}(\sqrt[3]{2}) \cong \mathbb{Q}[x]/(x^3 - 2)$, whence

$$[\mathbb{Q}(\sqrt[3]{2}) : \mathbb{Q}] = 3$$

which is not a power of 2. By Step 2 the number $\sqrt[3]{2}$ is not constructible.

Step 4: (2) trisecting an angle. An angle θ is constructible from a given one exactly when $\cos\theta$ is a constructible number: the point at distance 1 from the origin at angle θ is $(\cos\theta, \sin\theta)$, and dropping the perpendicular to the horizontal axis produces the point $(\cos\theta, 0)$, while conversely erecting the perpendicular at $(\cos\theta, 0)$ and cutting the unit circle with it recovers the angle. The claim is that no single construction trisects every angle, so it is enough to exhibit one angle it fails on.

Take $\theta = 60$ degrees, itself constructible since $\cos\theta = 1/2$. Write $\beta = \cos 20$ degrees. The triple angle identity $\cos\theta = 4\cos^3(\theta/3) - 3\cos(\theta/3)$ gives

$$4\beta^3 - 3\beta = \frac{1}{2} \qquad \text{that is} \qquad 8\beta^3 - 6\beta - 1 = 0$$

Setting $\alpha = 2\beta$ turns this into $\alpha^3 - 3\alpha - 1 = 0$. The cubic $x^3 - 3x - 1$ is monic with constant term -1, so by the rational roots test (proposition 11.3.6) its only possible rational roots are ± 1, and neither is a root, since $1 - 3 - 1 = -3$ and $-1 + 3 - 1 = 1$. A cubic over a field with no root in that field is irreducible by proposition 11.3.5, so $x^3 - 3x - 1$ is the minimal polynomial of α and $[\mathbb{Q}(\alpha) : \mathbb{Q}] = 3$ by theorem 19.2.8. Since $\alpha = 2\beta$ we have $\mathbb{Q}(\alpha) = \mathbb{Q}(\beta)$, so $[\mathbb{Q}(\beta) : \mathbb{Q}] = 3$ is not a power of 2 and $\beta = \cos 20$ degrees is not constructible. Hence the angle of 60 degrees cannot be trisected.

Step 5: (3) squaring the circle. A square with the area of the circle of radius 1 has side $\sqrt{\pi}$, so the problem asks for $\sqrt{\pi}$ to be constructible. If it were, then $\pi = (\sqrt{\pi})^2$ would lie in the field F_m of Step 2, so $[\mathbb{Q}(\pi) : \mathbb{Q}]$ would divide $[F_m : \mathbb{Q}]$ and in particular be finite.

What remains is the transcendence of π, which this book does not prove. That π is transcendental over $\mathbb{Q}$ is Lindemann's theorem. Its proof is analytic and belongs to a treatment of transcendence. Granting it, π is a root of no nonzero rational polynomial, so $[\mathbb{Q}(\pi) : \mathbb{Q}]$ is infinite by proposition 19.3.3, and in particular is not a power of 2. The circle therefore cannot be squared.

19.5 Closures of Fields

Through theorem 19.2.2, we saw that if we have a irreducible polynomial $f(x) \in k[x]$, we can find a larget field which gives $f(x)$ a root: $f(x) = f'(x)(x-\alpha)$. However, we have only established result for 1 polynomial, and for only 1 root. It would be nice if the set of all roots of every polynomials formed a field, and even better if that field existed for any field k and was unique (up to isomorphism). In such a field, every polynomial would *fully factor* or *split* into linear terms. Through corollary 19.3.14, we found that given K/k the set of algebraic elements $\alpha \in K$ over k forms a field, namely the set of elements from the larger field K which are algebraic over k. In example 19.3.15(1), we where implicitely using the fact that every polynomial over $\mathbb{C}$ reduces to linear terms, allowing us to say that $\overline{\mathbb{Q}}$ to be algebraically closed. It would be much better if the definition would be independent of any larger field, that is, find a field $\overline{k}$ such that the only irreducible polynomials in $\overline{k}[x]$ are of degree 1. Furthermore, if $\overline{k}$ existed for every field and was unique, we can call it *the* algebraic closure of k. This is the first thing proven in this section. Then, we take a closer look at fields for which only some subset $S \subseteq k[x]$ have polynomials that split. These fields will be at the heart of Galois theory, for as we saw in corollary 19.2.29, the group of k-automorphism $\mathrm{Aut}_k(F)$ depends on the number of roots of a polynomial in F. Thus, we take some time constructing such a field.

19.5.1 Algebraic Closure

We start off this section by reminding the reader what an algebraically closed field is:

Definition 19.5.1: Algebraically Closed

Let K be a field. Then K is called algebraically closed if every polynomial in $K[x]$ factors into a product of linear terms.

There are many equivalent ways of defining algebraic closure:

Lemma 19.5.2: Algebraic Closure Equivalences

Let K be a field. then the following are equivalent:

1. K is algebraically closed
2. every maximal ideal in $K[x]$ is of the form $(x-c)$ for some $c \in K$
3. There does not exist nontrivial algebraic extensions of K
4. If L/K is some field extension, and $\alpha \in L$ is algebraic over K, then $\alpha \in K$

***Proof*:**
We prove (1) $\Rightarrow$ (2) $\Rightarrow$ (3) $\Rightarrow$ (4) $\Rightarrow$ (1).

(1) $\Rightarrow$ (2): Let $M \subseteq K[x]$ be a maximal ideal. Since $K[x]$ is a Euclidean domain (theorem 11.1.1) and hence a PID (proposition 10.2.7), $M = (f)$ for some $f \in K[x]$. The polynomial f is nonconstant: a nonzero constant is a unit, giving $M = K[x]$, and $f = 0$ gives $M = (0) \subsetneq (x) \subsetneq K[x]$, in both cases contradicting maximality. By (1), f factors into linear factors, so

$f = (x-c)g$ for some $c \in K$ and $g \in K[x]$. Then $(f) \subseteq (x-c) \subsetneq K[x]$, the last containment being proper since the degree one polynomial $x - c$ is not a unit. Maximality of $M = (f)$ forces $M = (x - c)$.

(2) $\Rightarrow$ (3): Let L/K be an algebraic extension and take any $\alpha \in L$. Since α is algebraic, the evaluation map $\text{ev}_\alpha : K[x] \to K(\alpha)$ is not injective, and theorem 19.2.8 gives $K[x]/(m) \cong K(\alpha)$ where $m = m_{\alpha,K}$ is the minimal polynomial of α (definition 19.2.19). As $K(\alpha)$ is a field, proposition 9.4.19 shows (m) is a maximal ideal, so by (2), $(m) = (x - c)$ for some $c \in K$. Two generators of the same principal ideal in a domain divide one another, so comparing degrees, $m = u(x - c)$ for some unit $u \in K^\times$. Since $m(\alpha) = 0$, we get $u(\alpha - c) = 0$ and hence $\alpha = c \in K$. As α was arbitrary, $L = K$, so there is no nontrivial algebraic extension of K.

(3) $\Rightarrow$ (4): Let L/K be a field extension and $\alpha \in L$ algebraic over K. By theorem 19.2.8 and corollary 19.2.23, $K(\alpha)$ is a finite extension of K, hence algebraic by corollary 19.3.4. By (3), $K(\alpha) = K$, so $\alpha \in K$.

(4) $\Rightarrow$ (1): Let $f \in K[x]$ be nonconstant. We show by induction on $\deg f$ that f factors into linear factors. Since $K[x]$ is a UFD (proposition 10.1.33), f has an irreducible factor p. By Kronecker's theorem (theorem 19.2.2), there is an extension L/K in which p has a root α. Then α is algebraic over K, being a root of p, so $\alpha \in K$ by (4). Dividing f by $x - \alpha$ using theorem 11.1.1 gives $f = (x - \alpha)q + r$ with r constant, and evaluating at α gives $r = f(\alpha) = 0$ since $p(\alpha) = 0$ and $p \mid f$. Hence $f = (x - \alpha)q$ with $\deg q = \deg f - 1$. If q is constant, we are done. Otherwise the induction hypothesis factors q into linear factors, and with it f. Hence K is algebraically closed.

These show that being an algebraically closed field K means that there are no more algebraic extensions L/K, besides trivial ones. Given some field k, there can be many field extensions that are algebraically closed. For example, $\overline{\mathbb{Q}}/\mathbb{Q}$, $\mathbb{C}/\mathbb{Q}$, and $\mathbb{C}(t)/\mathbb{Q}$ are all field extensions of $\mathbb{Q}$ to algebraically closed fields. However, the first extensions seems in some way more simple or "minimal" than the other in that it is defined through only algebraic elements (recall from example 19.3.15(1) that all the elements of $\overline{\mathbb{Q}}$ are algebraic over $\mathbb{Q}$), while $\mathbb{C}$ contains transcendental elements (we have mentioend in example 19.3.15(2) how π and e are not algebraic).

Definition 19.5.3: Algebraic Closure

Let k be any field. Then an *algebraic closure* of k is a field $\overline{k}$ where $\overline{k}/k$ is an *algebaric extension* and $\overline{k}$ is algebraically closed.

Soon, the statement can be re-written with "the algebraic closure" and "the field" instead of "an algebraic closure" and "a field". The field $\overline{k}$ will be the smallest field in which every nonconstant polynomial $p(x) \in k[x]$ will split into linear factors, and since $\overline{k}$ is algebraically closed, the subfield of $\overline{k}$ that contains all the roots of all non-constant polynomials in $k[x]$ is $\overline{k}$ itself. To show the existence of such a field, we first prove that there exists a field extension where every polynomial in $k[x]$ has *at least* one root, and then recursively apply the theorem to get a long chain of field extensions, each containing at least one more root to every polynomial.

Lemma 19.5.4: Adding One Root

Let k be a field. Then there exists a field extension K of k such that every non-constant polynomial of $k[x]$ admits at least 1 root in K.

The following proof is credited to Emil Artin

***Proof*:**
Let $\mathcal{F}$ be a set that is in bijection with all non-constant monic polynomials $F \subseteq k[x]$: $\mathcal{F} = \{t_f\}_{f \in F}$, and let $k[\mathcal{F}]$ be a polynomial ring with indeterminates $t_f \in \mathcal{F}$. Let $I \subseteq k[\mathcal{F}]$ be the set of all polynomials generated by all $f(t_f)$ (that is, the polynomial f that takes in the indeterminate t_f that it is in bijective correspondence).

I claim that I is a proper ideal of $k[\mathcal{F}]$. Indeed, if it were not, then we would have:

$$1 = \sum_i^n a_i f(t_{f_i})$$

with $a_i \in k[\mathcal{F}]$. The identity cannot be possible, for that would lead to imply $1 = 0$. Let's take $k \subseteq F$ where each polynomial $f_1(x), ..., f_n(x)$ has a root $\alpha_1, ..., \alpha_n$ (apply theorem 19.2.2 n times). Then viewing the previous identity to be in $F[\mathcal{F}]$ we get:

$$1 = \sum_i^n a_i f(t_{f_i}) = \sum_i^n a_i f(\alpha_i) = \sum_i^n a_i \cdot 0 = 0$$

a contradiction.

Now, since I is proper, it is contained in a maximal ideal m (proposition 9.4.18). Thus, we have the field extension:

$$k \subseteq K := \frac{k[\mathcal{F}]}{m}$$

By construction every non-constant monic (and so every nonconstant) polynomial $f(x) \in k[x]$ must have a root in K, namely $\overline{t_f}$

Note that we had to use Zorn's lemma to find the maximal ideal m. Very commonly, a statement using Zorn's lemma is equivalent to it (ex. instead of using Zorn's lemma to prove the existence of a maximal ideal, we can use the existence of a maximal ideal to prove Zorn's lemma). We might ask if the existence if the previous result is also equivalent to Zorn's lemma, however this is not the case (it is due to the *compactness theorem of first order logic*, which is known to be weaker than the axiom of choice)

We can now find a field $K_1 \supseteq k$ in which every nonconstant polynomial in $k[x]$ has at least 1 root. We can continue this process by applying lemma 19.5.4 to K_1, which gives a field $K_2 \supseteq K_1$ in which every nonconstant polynomial of $K_1[x]$ has at least 1 root. Continuing this process, we get a chain:

$$k = K_0 \subseteq K_1 \subseteq K_2 \subseteq \cdots$$

in which every nonconstant polynomial of $K_i[x]$ has a root in K_{i+1}. Now, take $L = \bigcup_i K_i$[15]. L can easily be turned into a field through the operation of $a + b$ and $a \cdot b$ where we choose K_i in which $a, b \in K_i$.

[15]This is an example of a *direct limit*

Lemma 19.5.5: Union Of The Root-Adjoining Chain Is Algebraically Closed

Let $k = K_0 \subseteq K_1 \subseteq K_2 \subseteq \cdots$ be a chain of fields in which every nonconstant polynomial of $K_i[x]$ has a root in K_{i+1}, for instance the chain constructed above, and let $L = \bigcup_i K_i$. Then L is algebraically closed.

***Proof*:**
We show by induction on $n \geq 1$ that every polynomial $f \in L[x]$ of degree n is a product of a nonzero constant and n linear factors $x - \alpha$ with $\alpha \in L$. The polynomial f has finitely many coefficients, each lying in some K_j, and the K_j form a chain, so all of them lie in a single K_i, that is, $f \in K_i[x]$. As f is nonconstant, it has a root $\alpha \in K_{i+1} \subseteq L$. Dividing f by $x - \alpha$ in $K_{i+1}[x]$ (theorem 11.1.1) gives $f = (x - \alpha)g + r$ with r constant, and evaluating at α gives $r = f(\alpha) = 0$. So $f = (x - \alpha)g$ with $g \in L[x]$ of degree $n - 1$ (proposition 9.2.3(1)). If $n = 1$, then g is a nonzero constant and $f = g \cdot (x - \alpha)$ has the required form. If $n \geq 2$, the induction hypothesis writes g as a nonzero constant times $n - 1$ linear factors, and with the factor $x - \alpha$ this gives the required form for f. Hence every polynomial in $L[x]$ factors into linear terms, and L is algebraically closed (definition 19.5.1), completing the proof.

Thus, for any field k, there exists an algebreaically closed field L such that L/k. Note that L need not be algebraic closure, since L/k need not be an algebraic extension. However, with an algebraically closed field, we can very simply construct an algebraic closure of k:

Theorem 19.5.6: Existence Of Algebraic Closure

Let k be a field and L/k be a field extension where L is algebraically closed. Then

$$\overline{k} := \{\alpha \in L \mid \alpha \text{ is algebraic over } k\ \}$$

is an algebraic closure of k

Note how this mimicked $\overline{\mathbb{Q}}$ in example 19.3.15(2) assuming $\mathbb{C}$ is algebraically closed.

***Proof*:**
First, by corollary 19.3.14, $\overline{k}$ is a field, and *a prior* $\overline{k}$ is an algebraic extension of k. To show that k is algeraically closed, let α be algebraic over $\overline{k}$. Then

$$k \subseteq \overline{k} \subseteq \overline{k}(a)$$

is a composition of albegraic extensions, hence $\overline{k}(a)$ is algebraic (theorem 19.3.16), thus α is algebraic over k. But then by definition of $\overline{k}$, $\alpha \in \overline{k}$. Thus, by lemma 19.5.2$\overline{k}$ is algebraically closed, completing the proof

Next, we strive for uniqueness. As we establisehd in theorem 19.2.2, being a field extension is not a universal property, and so the best we an strive for is the existence of a homomorphism, though not necesarrily a unique one. We first establish a lemma:

Lemma 19.5.7: Embedding Into Algebraic Extension

Let L/k be any field extension where L is algebraically closed over k. Let F/k be an algebraic extensions. Then there exists a [not necessarily unique] homomorphism $i : F \to L$ fixing k.

Note that *a-priori*, L need not have any relation to F (ex. we do not know if F is a subset of L, they might only intersect on k).

***Proof*:**

This is a Zorn's lemma argument similar to Baer's Criterion (theorem 17.3.5). Let S be the set of homomorphisms of the form

$$i_K : K \to L$$

The set S is nonempty since $i_k : k \to L \in S$. Define a patial orer on S $i_K \preceq i_{K'}$ if $K \subseteq K' \subseteq L$ and $i_{K'}|_K = i_K$. To apply Zorn's lemma, we need to show that every chain has an upper bound. Let $C \subseteq S$ be a chain, and let K_C be the union of all the domains of elements $i_K \in C$. Then K_C is a field, being the union of a chain of fields (any two elements of K_C lie in a common K), and for every $\alpha \in K_C$ define $i_{K_C}(\alpha)$ to be $i_K(\alpha)$ for appropriate K where $\alpha \in K$. Then i_{K_C} is well-defined: if $\alpha \in K \subseteq K'$ with $i_K, i_{K'} \in C$, then $i_{K'}|_K = i_K$, so the value does not depend on the choice of K, and so we have a homomorphism $i_{K_C} : K_C \to L$ where $i_K \preceq i_{K_C}$ for all $i_K \in C$, showing that i_{K_C} is indeed an upper bound for C. Thus, by Zorn's lemma, Z has an upper bound $i_G : G \to L$ where $k \subseteq G \subseteq L$.

I claim that $G = F$, which will prove the statement. For the sake of contradiction, let's assume this is not the case, so that there exists an element $\alpha \in F \setminus G$. Consider $G(\alpha)/G$. Since $\alpha \in F$ is algebraic over k, α is algebraic over G, and since $\alpha \notin G$, it is the root of an irreducible polynomial $g(x) \in G[x]$. Let $H = i_G(G)$. Then as discussed in the first pages of section 19.2 i_G induces a ring homomorphism

$$f^{i_G} : G[x] \to H[x]$$

Let $h(x) = f^{i_G}(g(x))$. Then $h(x)$ is irreducible over H, and since L is algebraically closed, it must have a root $\beta \in L$.

We are now setup in a situation to apply theorem 19.2.27: we have an isomorphism $i_G : G \to H$ and two simples extensions $G(\alpha), H(\beta)$ with α and β being roots of $g(x)$ and $h(x)$ respectively (with $h(x) = i_G(g(x))$). Thus, i_G lifts to an isomorphism:

$$i_{G(\alpha)} G(\alpha) \to H(\beta) \subseteq L$$


which sends α to β. Then $i_G \preceq i_{G(\alpha)}$, contradicting the maximality of i_G.

Thus, it must be that $G = F$, and so $i_F : F \to L$ is a field homomorphism, as we sought to show.

The fact that the isomorphism is not unique will become important in representing algebraic closures. We first finish off by showing that the algebraic closure is indeed unique up to isomorphism (given a fixed field k)

Theorem 19.5.8: Uniqueness Of Algebraic Closure

Let $k \subseteq \overline{k_1}$ and $k \subseteq \overline{k_2}$ be two algebraic closures of k. Then $\overline{k_1} \cong \overline{k_2}$ where the isomorphism extends the identity on k, or equivalently k_1 is isomorphic to k_2 as extensions. In terms of a commutative diagram, in the following



there always exists an isomorphism from k_1 to k_2

the second condition for the isomorphism is so that the two fields represent the algebraic closure over the common field k. Sometimes, such a isomorphism (resp. homomorphism) is called a k-isomorphism (resp. k-homomorphism)


***Proof*:**
Since $\overline{k_1}/k$ is algebraic and $\overline{k_2}$ is algebraically closed over k, by lemma 19.5.7, there exists a homomorphism $i : \overline{k_1} \to \overline{k_2}$. This homomorphism is injective, being a field homomorphism, and surjective since otherwise, $\overline{k_1} \subseteq \overline{k_2}$ would be a non-trivial algebraic extension, contradicting lemma 19.5.2 since $\overline{k_1}$ is algebraically closed. Thus, i must be an isomorphism as we sought to show.

The fact that the isomorphism is not necessarily unique has some important consequences: There is no "cannonical" way of representing the algebraic closure. At first, it might seem harmless that the isomorphism is not unique, as long as the two field are isomorphic. However, this means there is no real cannonical "choice" when it comes to representing algebraic closures.

Take for example $\overline{\mathbb{R}}$, which we know to be $\mathbb{C}$. We can write $\overline{\mathbb{R}}$ as $\mathbb{R}[i]$, which for many mathematicians is "the" algebraic closure of $\mathbb{R}$. However, if we go over to an electrical engineer, we will see that they have also constructed an algebraic closure for $\mathbb{R}$ to represent electrical charge and circuits where they use the letter j (since i is already used for something else), and write it as $\mathbb{R}[j]$. We might think it to be harmless to make the isomorphism $1 \mapsto 1$ and $i \mapsto j$, however the electrical engineers have decided that electrical charge should be represented by a -1. Does this means we should instead have

$$1 \mapsto 1 \qquad i \mapsto -j?$$

Mathematically, there is no good reason to pick one representation over another. In other words, if one person constructs a splitting field L for k and another person constructs a algebraic closure L' for k, then we know that we get:



however, there is no "natural" way to associate an element of L to an element of L'. This often means that we should keep track of the construction of the splitting field we have done, since if we do not we might not be able to communicate to other mathematicians who have done a different

construction (how can you compare your work if you cannot correspond the results you have come up with with the other mathematicians).

The idea there there is no natural choice of isomorphism can be made more rigorous if we ask it in the language of category theory. If we map every field to it's algebraic closure $k \to \overline{k}$, does this define a functor? In order for it to define a functor, we would need that every map $k \to l$ of field defines a map of algebraic closures

$$\begin{array}{ccc} k & \longrightarrow & \overline{k} \\ \downarrow & & \vdots \\ l & \longrightarrow & \overline{l} \end{array}$$

However, it is not clear what map should be chosoen here[16].

19.5.2 Splitting Field and Normal Extensions

Having established that every field has an algebraic closure, meaning we can unambiguously refer to roots of polynomials, we now return to analyzing algebraic extensions. We start off by zoom in on fields that only split some subset of polynomials $S \subseteq k[x]$. In the following sections, we will be working over the case where S is finite. Since S is finite, say $S = \{f_1(x), ..., f_n(x)\}$, then having each $f_i(x)$ split is equivalent to having $f_1(x)f_2(x)\cdots f_n(x)$, thus, we usually have $S = \{f(x)\}$ be one polynomial

Definition 19.5.9: Splitting Field

Let k be a field and $f(x) \in k[x]$ be a polynomial where $\deg(f(x)) = d$. Then a *splitting field* for $f(x)$ over k is a minimal extension F/k such that

$$f(x) = c\prod_{i}^{d}(x - \alpha_i)$$

i.e. $f(x)$ splits completely in $F[x]$, and $f(x)$ does not factor in any proper subfield of F.

Furthermore, by minimality, $F = k(\alpha_1, ..., \alpha_n)$ (i.e. F is generated by the roots of $f(x)$ in F)

The fact that a splitting field exists is immediate from the fact that $\overline{k}$ exists, namely if $f(x)$ is a polynomial, then $F \subseteq \overline{k}$ generated by the roots of $f(x)$ in $\overline{k}$. Furthermore, the splitting field is in fact unique (up to isomorphism), justifying replacing any "a splitting field" in the definition to "the splitting field"

[16] perhaps you can force through a construction using the axiom of choice, but it is certainly not a natural choice

Theorem 19.5.10: Uniqueness Of Splitting Field

Let k be a field and let $f(x) \in k[x]$. Then the splitting field F for $f(x)$ over k is unique up to isomorphism, and $[F : k] \leq (\deg(f))!$ (i.e. the factorial of the degree of f). Furthermore, if $i : k \to k'$ is an isomorphism, $f(x) \in k[x]$ and $g(x) = i(f(x))$, then i extends to an isomorphism from the splitting field of $g(x)$ over k' to the splitting field of $f(x)$ over k:

$$\begin{array}{ccc} F & \overset{\sim}{\dashrightarrow} & F' \\ \uparrow & & \uparrow \\ k & \xrightarrow{\sim} & k' \end{array}$$

***Proof*:**
We will first construct a splitting field explicitly with $[F : k] \leq (\deg(f))!$, and then use that field to show uniqueness. For existence, this is an application of induction on the degree of the polynomial. Degree 1 is trivial, covering the base-case, so let's say the splitting field was constructed for all fields and all polynomials of degree $\deg(f) - 1$. Let $f(x)$ be some polynomial that is not yet fully factored into linear terms. Let $q(x)$ be some irreducible non-linear factor over k. Then

$$k \subseteq F' := \frac{k[x]}{(q(x))}$$

is an extension of degree $\deg q \leq \deg f$ in which $q(x)$ has a root (and so $f(x)$ has a root), say α, and so $q(x) = q'(x)(x - \alpha)$. Then we can define the polynomial $h(x) = f(x)/(x - \alpha) \in F'[x]$ of degree $\deg(f) - 1$. Thus, by the induction hypothesis, there exists a splitting field F for $h(x)$ over F' and

$$[F : F'] \leq (\deg(f) - 1)!$$

Since the factors of $f(x)$ over F are $(x - \alpha)$ and the factors of $h(x)$, it follows that F is a splitting field for $f(x)$, and

$$[F : k] = [F : F'][F' : k] \leq (\deg(f) - 1)!(\deg(f)) = (\deg(f))!$$

To prove that an isomorphism $i : k \to k'$ extends to isomorphisms of splitting fields as stated, let F be the splitting field for $f(x)$, and consider $k \to k' \subseteq \overline{k'}$. Since the extension $k \subseteq F$ is algebraic, by lemma 19.5.7 there exists a k-homomorphism $i : F \to \overline{k'}$. Since F is generated over k by the roots of $f(x)$ in F, we have

$$i(F) = k'(\alpha_1, ..., \alpha_d) \subseteq \overline{k'}$$

where the α_i's are the roots of $g(x) = i(f(x))$ in $\overline{k'}$. Therefore, $L := i(F)$ is independent of the given isomorphism i and the splitting field F. Applying this to i and to the identity $k' \to k'$ completes the proof (since both F and G are isomorphic to L)

Example 19.5.11: Splitting Fields

1. The splitting field of $x^2 - 2$ over $\mathbb{Q}$ is $\mathbb{Q}(\sqrt{2})$, since the two roots are $\pm\sqrt{2}$ and $-\sqrt{2} \in \mathbb{Q}(\sqrt{2})$. The splitting field of $(x - 2)^n$ is also $\mathbb{Q}(\sqrt{2})$ for all $n \in \mathbb{N}_{>0}$, since we only need to add the

root $\sqrt{2}$ (resp. $-\sqrt{2}$) for this polynomial to split.

2. Splitting field for $(x^2-2)(x^2-3)$ over $\mathbb{Q}$ is $\mathbb{Q}(\sqrt{2},\sqrt{3})$. Note that $\mathbb{Q}(\sqrt{2},\sqrt{3})$ is equal to the composite field $\mathbb{Q}(\sqrt{2})\mathbb{Q}(\sqrt{3})$, i.e. $\mathbb{Q}(\sqrt{2})\mathbb{Q}(\sqrt{3}) = \mathbb{Q}(\sqrt{2},\sqrt{3})$.

3. More generally, If $f(x)$ is a polynomial over k such that

$$f(x) = \prod g_i(x)$$

where each $g_i(x)$ is irreduible over k, then the splitting field of $f(x)$ is the composite field of the splitting fields for each $g_i(x)$ since each splitting field is the smallest field containing all the roots of g_i, and the composite field is the smallest field containing all the splitting fields.

4. splitting field of x^3-2 over $\mathbb{Q}$ is not $\mathbb{Q}(\sqrt[3]{2})$, since we are missing two roots, namely:

$$\sqrt[3]{2}\left(\frac{-1+i\sqrt{3}}{2}\right) \qquad \sqrt[3]{2}\left(\frac{-1-i\sqrt{3}}{2}\right)$$


Thus, the splitting field is $\mathbb{Q}(\sqrt[3]{2}, i\sqrt{3}) = \mathbb{Q}(\sqrt[3]{2}, \sqrt{-3})$.

5. The splitting field of x^2+1 over $\mathbb{Q}$ is $\mathbb{Q}(i)$, and the splitting field of the same polynomial x^2+1 over $\mathbb{R}$ is $\mathbb{C}$, showing that the splitting field is dependent on the base field.

6. Let F be the splitting field of x^8-1 over $\mathbb{Q}$. With some knowledge of complex analysis, we see that all the roots are 8th root of unit, that is,

$$\zeta = e^{\frac{2\pi i}{8}}$$

is a generator for the roots (i.e. the primite elements), and so $F = \mathbb{Q}(\zeta)$. Visually, these roots look like so:



In fact, ζ is also the root of x^4+1 (since $\zeta^4 = -1$), and so is the root of the smaller irreducible polynomial x^4+1 over $\mathbb{Q}$. There is no smaller minimal polynomial for which ζ is a root (since smaller powers of ζ is not in $\mathbb{R}$) and so:

$$[\mathbb{Q}(\zeta) : \mathbb{Q}] = 4$$

showing that the degree of the splitting field is much less than $8! = 40'320$. To better undersatnd this field, notice that $\zeta^2 = i$, so $\sqrt{2} = \zeta + \zeta^7$. Thus:

$$\mathbb{Q}(i, \sqrt{2}) \subseteq \mathbb{Q}(\zeta)$$

Conversely, $\zeta = \frac{\sqrt{2}}{2}(1+i) \in \mathbb{Q}(i, \sqrt{2})$, showing that:

$$\mathbb{Q}(i, \sqrt{2}) \supseteq \mathbb{Q}(\zeta)$$

showing that they are in fact equal.

As an exercise, show that $\mathrm{Aut}_{\mathbb{Q}}(\mathbb{Q}(i, \sqrt{2})) = \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z}$

7. Let $p(x) = x^4 - 1$. this polynomial in fact factors over $\mathbb{Q}$:

$$x^4 - 1 = (x-1)(x+1)(x^2+1)$$

and so the splitting field of $x^4 - 1$ is the splitting field of $x^2 + 1$, which is $\mathbb{Q}(i)$

8. Let $p(x) = x^4 + 2$. This polynomial is irreducible by Eisenstein. Given $\zeta = e^{\frac{2\pi i}{8}}$, then the roots of $p(x)$ are:

$$\sqrt[4]{2}\zeta, \ \sqrt[4]{2}\zeta^3, \ \sqrt[4]{2}\zeta^5, \ \sqrt[4]{2}\zeta^7$$

and so the splitting field is $K = \mathbb{Q}(\sqrt[4]{2}\zeta, \ \sqrt[4]{2}\zeta^3, \ \sqrt[4]{2}\zeta^5, \ \sqrt[4]{2}\zeta^7)$. We can simply the adjoint elements with the following observations:

$$K \subseteq \mathbb{Q}(\zeta, \sqrt[4]{2}) \subseteq \mathbb{Q}(i, \sqrt{2}, \sqrt[4]{2}) = \mathbb{Q}(i, \sqrt[4]{2})$$

so $K \subseteq \mathbb{Q}(i, \sqrt[4]{2})$. For the $\supseteq$ direaction, notice that:

$$\sqrt{2} = \frac{(\sqrt[4]{2}\zeta)^3}{\sqrt[4]{2}\zeta^3} \in K \qquad i = \frac{(\sqrt[4]{2}\zeta)^2}{\sqrt{2}} \in K$$

So $\zeta = \frac{\sqrt{2}}{2}(1+i) \in K$ and $\sqrt[4]{2} = \frac{\sqrt[4]{2}\zeta}{\zeta} \in K$, showing that $K \supseteq \mathbb{Q}(i, \sqrt[4]{2})$. With a little bit of computation, we see that:

$$[\mathbb{Q}(i, \sqrt[4]{2}) : \mathbb{Q}] = 8$$

Overall, small variation in polynomials can create quite large differences in splitting fields (as we have seen with $x^4 + 2$, $x^4 + 1$, $x^4 - 1$). This shows how precise the tools of field theory are in the study of polynomials.

Given a polynomial $f(x)$ over k, we can find a field F in which $f(x)$ factor completely over F. In fact, we have also gained a slightly stronger result for free: if $g(x)$ is irreducible in k has a root in F, then it in fact *also* splits. The idea is that the automorphism group acts transitively on all the roots of an irreducible polynomials (recall the discussion under corollary 19.2.29). If all the roots are inside the field, then the automorphism group will shuffle around all the roots within the field. Hence, if we are given that a single root is inside a field, and that the image of each automorphism in the automorphism group is inside the field, we would have that all the roots are within the field. As the action of the automorphism group $\mathrm{Aut}_k(F) \curvearrowright R_F$ is a evaluation action $\sigma \cdot \alpha = \sigma(\alpha)$ (often called the *galois conjugate* or just *conjugate)*, another way of saying it is that the field is closed under conjugation of the automorphism group. To understand this phenomenon better, we give a name to

fields with this property:

Definition 19.5.12: Normal Extension

Let F/k be an algebraic field extension. Then F/k is called a *normal extension* if for every *irreducible* polynomial $f(x) \in k[x]$, $f(x)$ has a root if and only if $f(x)$ splits as a product of linear factors over F

A normal extension is *not necessarily* the algebraic closure since not necessarily all irreducible polynomials have a root, however the irreducible polynomials over the base field become the polynomials that split completely in the normal extension, constant polynomials, and irreducible polynomials that have no roots in the normal extension (or, they can be thought of as polynomials that have yet to have a root added to the extension).

The name normal is given to this type of extension is due to the fact that most of the nice properties of automorphism groups we have discussed in corollary 19.2.29 apply to normal extensions[17]

Theorem 19.5.13: Finite Normal Extension Equivalences

Let F/k be a field extension. Then the following are equivalent:

1. F is finite and normal
2. F is the splitting field of some polynomial $f(x) \in k[x]$
3. F is finite over k, and every k-homomorphism $\varphi\colon F \to \overline{F}$ satisfies $\varphi(F) = F$

***Proof*:**

For $2 \Rightarrow 3$, let F be the splitting field of some polynomial $f(x) \in k[x]$. It is generated over k by the finitely many roots of $f(x)$, each algebraic, so F is finite over k (theorem 19.3.7). Let $\varphi\colon F \to \overline{F}$ be a k-homomorphism. If α is a root of $f(x)$, then $m_{\alpha,k}(x) \big| f(x)$, and by corollary 19.2.29, $\varphi(\alpha)$ is another root of $m_{\alpha,k}$, and hence of $f(x)$. Since F is a splitting field, it contains all the roots of $f(x)$, and so $\varphi(\alpha) \in F$. Since F is generated by the roots of $f(x)$, $\varphi(F) \subseteq F$. Then φ is an injective k-linear map of the finite-dimensional k-vector space F into itself, hence surjective, so $\varphi(F) = F$.

For $3 \Rightarrow 1$, let $p(x) \in k[x]$ be irreducible with a root $\alpha \in F$, and let $\beta \in \overline{F}$ be a root of $p(x)$. By theorem 19.2.27, there is a k-isomorphism $\sigma\colon k(\alpha) \to k(\beta)$ with $\sigma(\alpha) = \beta$. Regard $\overline{F}$ as an extension of $k(\alpha)$ through σ. As $F/k(\alpha)$ is finite, hence algebraic, lemma 19.5.7 gives a homomorphism $\varphi\colon F \to \overline{F}$ extending σ. It is a k-homomorphism, so $\varphi(F) = F$ and $\beta = \varphi(\alpha) \in F$. Hence $p(x)$ has all its roots in F and splits over F, so F/k is finite and normal.


Next, we show $1 \Rightarrow 2$. Assume F is finite and normal. Since it's finite, $F = k(\alpha_1, \alpha_2, ..., \alpha_n)$, where each α_i is algebraic over k. Next, let $m_i(x)$ be the minimal polynomial of α_i. Since F is normal, and each m_i has at least one root (namely α_i), $m_i(\alpha)$ splits. Then $f(x) = m_1(x) \cdots m_n(x)$ is a polynomial that splits over F. But then, F is the smallest field in which $f(x)$ splits (since $F = k(\alpha_1, ..., \alpha_n)$), and so F is the splitting field for $f(x)$.

Finally, we show $2 \Rightarrow 1$: assume F is the splitting field for some polynomial $f(x) \in k[x]$, and

[17] In fact, normal subgroups got their name from normal extensions! The connection will be made in the chapter 20 when discussing Galois Theory in theorem 20.1.23

assume that $p(x) \in k[x]$ is an irreducible polynomial over k such that F contains a root α for $p(x)$. If $p(x)$ has degree less than or equal to 2, we are done, so let's say $\deg p(x) \geq 3$. Since $F \subseteq \overline{k}$, let $\beta \in \overline{k}$ be a different root of $p(x)$. We want to show that $\beta \in F$. This will show that F is normal, and by theorem 19.5.10, F must be finite.

Since $\mathrm{id} : k \to k$ is a field homomorphism, by theorem 19.2.27, there is an isomorphism $i : k(\alpha) \to k(\beta)$ sending $\alpha \mapsto \beta$. Note that $F(\beta) \subseteq \overline{k}$. Visually, we can imagine all of this in the commutative diagram:



Note that we cannot draw the identity map from $\overline{k}$ to $\overline{k}$, since ι maps $\alpha \mapsto \beta$. Now, notice that F is the *splitting field* $f(x)$ over $k(\alpha)$. Indeed, F contains all the roots of $p(x)$ and is generated over k (and hence $k(\alpha)$) by the roots of $p(x)$. Similarly, $F(\beta)$ is the splitting field for $f(x)$ over $k(\beta)$. Then by the uniqueness of the splitting field (theorem 19.5.10), ι extends to an isomorphism $\iota' : F \to F(\beta)$. Now, since ι restricts to the identity on k, ι' is an isomorphism of k-vector spaces, in particular $\dim_k F = \dim_k F(\beta)$ (since splitting fields are always finite extensions). In particular, we get to take advantage of facts about liner algebra, in particular that if the dimensions of two vector-spaces are the same, then any injective linear transformation is in fact an isomrophism.


Now, we also have the natural inclusion map $\iota : F \to F(\beta)$ which is both a k-homomorphism and a k-vector spaces. Since F and $F(\beta)$ are k-vector spaces of the same [finite!] dimension, i must *also* be an isomorphism, i.e.

$$[F(\beta) : F] = 1$$


Thus, $\beta \in F$, completing the proof.

An algebraic extension F/k, not necessarily finite, is normal if and only if every k-homomorphism $\varphi\colon F \to \overline{F}$ satisfies $\varphi(F) = F$. The proofs of $3 \Rightarrow 1$ and of $\varphi(F) \subseteq F$ in $2 \Rightarrow 3$ carry over, applied to one irreducible polynomial at a time, and $\varphi(F) \supseteq F$ holds because φ permutes the finitely many roots in F of each such polynomial.

19.5.14 Remark Notice how condition (3) of theorem 19.5.13 allows us to refer to "the" embedding of a Normal extension F/k into $\overline{k}$, since $\varphi(F) = F$ for any F. Recall that $\mathbb{Q}(\sqrt[3]{2})/\mathbb{Q}$ is not normal, and that we have shown that $\mathbb{Q}(\sqrt[3]{2})$ is isomorphic to 3 subfields of $\overline{\mathbb{Q}}$ which do not all overlap:



However, if the extensoin is normal, then there is a notion of "the" embedding since they all overlap:



In this way, having a [algebraic][a] normal extension F/k can be thought of as being more "precise" than a non-normal extension, since any other isomorphic copy of F is just an automorphism of F.

[a] This is to ensure that $F \subseteq \overline{k}$. The algebraic elements of F is also what we care about when we look at k-homomorphisms $F \to \overline{k}$

Example 19.5.15: Consequences
Let's say $p(x)$ is an irreducible polynomial over $\mathbb{Q}$ with a complex root that may be expressed as a polynomial in i and $\sqrt[4]{2}$ over $\mathbb{Q}$. Then *all* roots of $p(x)$ may be expressed as a polynomial in i and $\sqrt[4]{2}$. As we have shown in example 19.5.11, $\mathbb{Q}(\sqrt[4]{2}, i)$ is a splitting field over $\mathbb{Q}$, and hence a normal extension.

Unlike algebraic and finite extensions, normal extensions are more finicky when it comes to composing normal extensions:

Proposition 19.5.16: Tower Law On Normal Extensions

If $L/K/k$ and L/k is normal, then L/K is normal

***Proof*:**
Let $f(x) \in K[x]$ be irreducible with a root $\alpha \in L$. Then $f(x) = m_{\alpha,K}(x)$ is the minimal polynomial over K. Note that

$$m_{\alpha,K}(x) | m_{\alpha,k}(x)$$

And since $m_{\alpha,k}(x)$ splits over L (since L/k is normal), $m_{\alpha,K}$ splits over L, as we sought to show.

Note that this result has little wiggle room:

Example 19.5.17: Low Tolerance for Normal Extension
Consider $L/K/k$ where:

$$\begin{array}{c} \mathbb{Q}(\sqrt[3]{2}, \zeta_3) \\ | \\ \mathbb{Q}(\sqrt[3]{2}) \\ | \\ \mathbb{Q} \end{array}$$

where σ_3 is one of the two other roots of $x^3 - 2$. Then while L/k is normal, K/k is *not* normal here (we have yet to add enough roots). Furthermore, if L/K and K/k is normal, this does not imply that L/k is normal. For example:

$$\begin{array}{c} \mathbb{Q}(\sqrt[4]{2}) \\ | \\ \mathbb{Q}(\sqrt{2}) \\ | \\ \mathbb{Q} \end{array}$$

To see this, notice that each extension is of degree 2, and hence is normal (exercise). However, $\mathbb{Q}(\sqrt[4]{2})/\mathbb{Q}$ is not normal, since 2 of the roots of $x^4 - 2$ are complex, while $\mathbb{Q}(\sqrt[4]{2})$ is contained in the reals, and hence cannot have all the roots.

Notice how this behavior is mimicked by normal subgroups.

Definition 19.5.18: Normal Closure

Let K/k be an algebraic extenion. Then the *normal closure* of K given k is an algebraic extension N/K such that

1. N/k is normal
2. If $N \supseteq N' \supseteq k$, and N'/k is normal, then $N = N'$

Proposition 19.5.19: Existence Of Normal Closure

Let K/k be a finite extension. Then there exists a unique normal closure N up to isomorphism fixing k.

Note the finiteness condition given. It is true for algebraic ones too, but we did not yet prove that

***Proof*:**
Since K is finite, let $K = k(\alpha_1, \alpha_2, ..., \alpha_n)$ where each $\alpha_i \in K$ is algebraic over k. Let

$$f(x) = \prod m_{\alpha_i,k}(x) \in k[x]$$

and let N be the splitting field of $f(x)$ over K. Then $[N : K] < \infty$. But then, N is the splitting field of $f(x)$ over k as $K = k(\alpha_1, \alpha_2, ..., \alpha_n)$. But this implies N/k is normal.

Finally, let's say $k \subseteq N' \subseteq N$ and N'/k is normal. Then by normality, N' has to split each $m_{\alpha_i,k}(x)$, and so splits $f(x)$, and so N/k *is* a normal closure.

Exercise 19.5.1

1. A splitting field of $f \in k[x]$ of degree n has degree at most $n!$ over k (theorem 19.5.10). Show that the splitting field of $x^3 - 2$ over $\mathbb{Q}$ has degree $6 = 3!$.
2. Let E/k and F/k be algebraic extensions inside a common field. Show that if E/k is normal, then so is EF/F. Show that if E/k and F/k are normal, so is EF/k.
3. Let L/K be an algebraic field extension, and $\varphi_K : K \to \overline{F}$ be a homomorphism to an algebraically closed field. Then φ_K extends to a homomorphism $\varphi_L : L \to \overline{F}$ (use Zorn's lemma and a proof similar to lemma 19.5.7 with Zorn being applied to (E, φ_E) where E/K is a subextension of L/K and $\varphi_E : E \to \overline{F}$ extends φ_K)

19.6 Separable Extensions

We have now shown that there exists a field K over F such that a polynomial $f(x)$ splits (or a field $\overline{F}$ such that all polynomials in $F[x]$ split). A pattern has been occuring which you might have not noticed: every time we split an irreducible polynomial completely into linear factors, each factor was *unique*, that is, we had that the multiplicity of every linear term was 1. Does that need to be the case for any polynomial over any field? The answer is no:

Example 19.6.1: Higher Multiplicity

Let p be a prime number, and take the field $\mathbb{F}_p(t)$. Consider the polynomial:

$$p(x) = x^p - t \in \mathbb{F}_p(t)[x]$$

Then $p(x)$ is irreducible: by Eisenstein's criterion, it is irreducible in $\mathbb{F}_p[t][x]$ (since (t) is prime in $\mathbb{F}_p[t]$), and hence it is prime in $\mathbb{F}_p(t)[x]$ by corollary 11.2.2. Let u be a root of $p(x)$ in the extension $L/\mathbb{F}_p(t)$ (L can be the algebraic closure, or the splitting field). Then notice that:

$$x^p - t = (x - u)^p$$

Simply expand the right hand side of the equation. Thus, u has multiplicity p, i.e., the minimal polynomial over $\mathbb{F}_p(t)$ for $u \in L$ vanishes p times at u[a].

[a] $p(x)$ must be the irreducible polynomial, since if the degree was smaller then $p(x)$ would be reducible

Thus, in general, a polynomial $f(x) \in k[x]$ can factorize over a splitting field as:

$$f(x) = (x - \alpha_1)^{n_1}(x - \alpha_2)^{n_2} \cdots (x - \alpha_k)^{n_k}$$

where $\alpha_1, \alpha_2, ..., \alpha_k$ are distinct elements in the splitting fields, and $n_1, n_2, ..., n_k$ is the multiplicity of every root. However, this seems to be a rare occurence given the fields we have worked with. In fact, most field we will work with do not have this property. It will also become important in Galois theory that a polynomial would have to to linear polynomials with multiplicity 1[18]. For those who are curious, see what hapens to the automorphism group $\mathrm{Aut}_k(F)$ of the splitting field F if $(x - \alpha)^n$ is the linear factorization of $f(x)$ over k. Hence, we give a name to polynomials that factor with multiplicity 1:

Definition 19.6.2: Separable Polynomial

A polynomial over k is called *separable* if it factors into linear terms with multiplicity 1 in it's splitting field. Equivalently, it has no multiple roots (i.e., all its' roots are distinct). A polynomial which is not separable is called *inseparable*.

My intuition behind the name is that the roots cannot be completely "separated" from each other if the polynomial is *inseparable*. In Algebraic Geometry, polynomials that have roots with multiplicity higher than 1 (say multiplicity m) shall correspond to a collection of points that shall all be arbitrarily close to each other while not being equal, ostensibly being "inseparable"[19]. Naturally, the choice of splitting field does not affect whether a polynomial is separable since all splitting fields for a polynomial are isomorphic, and isomorphisms preserves roots (theorem 19.2.27). Even better, we can use *any* field in which the chosen polynomial $f(x)$ splits into linear factors (since there will be a homomorphism from the splitting field F to the field K in which $f(x)$ splits). For our purposes, that means that it is just as good to work over the algebraic closure $\overline{k}$.

[18] (the correspondence Galois group is trivial otherwise)

[19] See the plane with two origins for an example of such a geometric object

Definition 19.6.3: Separable Extension

Let F/k be a field extension and $\alpha \in F$. Then:

1. The element α is called *seprable* if α is algebraic and the minimal polynomial corresponding to α is seperable. Otherwise, the element α is called *inseparable*
2. F/K is called a *separable extension* if every element $\alpha \in F$ is separable, and an *inseparable extension* otherwise.

19.6.4 Remark Note that it is not immediately obvious that if α is separable over k that $k(\alpha)/k$ is a separable extension (what if $1+\alpha$ is inseparable?). We will answer this question after we develop more tools to work with separable elements.

Using the fact that separability is independent of the field in which it splits, we can use a clever trick in finding whether a polynomial is separable using a tool usually defined in calculus:

Definition 19.6.5: Derivative

Given a polynomial $f(x) \in k[x]$ where

$$f(x) = a_n x^n + a_{n-1}x^{n-1} + \cdots + a_1 x + a_0$$

then its *derivative* or *formal derivative* is the image of the function $D_x : k[x] \to k[x]$ where:

$$D_x f(x) = n a_n x^{n-1} + (n-1)a_{n-1}x^{n-2} + \cdots + 2a_2 x + a_1$$

or more succinctly

$$D_x\left(\sum_i^n a_i x^i\right) = \sum_i^n i a_i x^{i-1} \tag{19.2}$$

Notice that this derivative acts exactly like the derivative seen in a regular calculus course [20]. In a calculus course, we derive this formula using a limit construction. However, if we just think about the derivative (restricted to polynomials) as a function, then we get a purely algebraic definition of the derivative. In fact, the derivative (and even its generalization with he external operator on differential forms) can be studied purely algebraically; see [13] a deeper exploration of these ideas[21].

Note that the i in equation (19.2) is well-defined since we always have the unique homomorphism $\iota : \mathbb{Z} \to k[x]$ since $\mathbb{Z}$ is initial in **Ring**, and so i is the element associated with $\iota(i)$. The *linearity* and *Leibniz property* of the derivative can both be proven with just this definition:

$$D_x(f(x)+g(x)) = D_x f(x) = D_x g(x)$$
$$D_x(f(x)g(x)) = (D_x f(x))g(x) + f(x)(D_x g(x))$$

We will often abbreviate notation and write $f'(x) := D_x f(x)$ when it is not ambiguous.

[20] A good resources to learn this would be Spivak's Analysis

[21] For example, algebraic differential forms shall be useful to determine the separability of algebraic maps, which is the generalization of the idea that an extension is separable if each element has a nonzero derivative

Proposition 19.6.6: Separable Polynomial Test

A polynomial $f(x)$ has multiple roots α if and only if α is also a root of $D_x f(x)$, i.e., $f(x)$ and $D_x f(x)$ are both divisible by the minimal polynomial for α. In particular, $f(x)$ is separable if and only if it is relatively prime to its derivative

$$(f(x), f'(x)) = 1$$

Noet how $f(x)$ is *not necessarily irreducible*. This means that the derivative test is incredibly powerful, telling us that if $(f(x), f'(x)) = 1$, then any irreducible factor of $f(x)$ but all be distinct and have distinct roots.

***Proof*:**
First, let's say $f(x)$ is inseparable so that it has multiple roots in a splitting field F:

$$f(x) = (x - \alpha)^n g(x)$$

where $n \geq 2$ and $g(x) \in F[x]$. Then:

$$f'(x) = n(x - \alpha)^{n-1} g(x) + (x - \alpha)^n g'(x)$$

showing that $\gcd(f(x), f'(x)) \neq 1$ in $F[x]$. By corollary 11.2.2 to Gauss's Lemma, $\gcd(f(x), f'(x)) \neq 1$ in $k[x]$

Conversely, Assume that $f(x)$ and $f'(x)$ share a root (say $\alpha \in \overline{k}$), so that $\gcd(f(x), f'(x)) \neq 1$ in $k[x]$. Since $f(x)$ has a root, we can write it as:

$$f(x) = (x - \alpha)h(x)$$

for $h(x) \in k[x]$ (or $\overline{k}[x]$?). Then the derivative is:

$$f'(x) = h(x) + (x - \alpha)h'(x)$$

Since $f(x)$ and $f'(x)$ share a root, it must be that $(x - \alpha) \big| h(x)$. But then:

$$(x - \alpha)^2 \big| f(x)$$

showing that $f(x)$ has multiple roots, hence inseparable, as we sought to show.

Using this theorem, we can see that $p(x) = x^p - t$ is inseparable since $p'(x) = px^{p-1} = 0$ (since the characteristic of $\mathbb{F}_p(t)$ is p). Thus, $\gcd(x^p - t, 0) = x^p - t \neq 1$. In fact, this captures a bigger result:

Proposition 19.6.7: Separability and irreducible polynomial

Let k be a field and $f(x) \in k[x]$ be an *inseparable and irreducible* polynomial. Then

$$f'(x) = 0$$

***Proof*:**
Since $f(x)$ is inseparable, by proposition 19.6.6, $f(x)$ and $f'(x)$ share a common irreducible factor $q(x)$, that is $f(x) = q(x)g(x)$ for non-constant $g(x) \in k[x]$. However, f is irreducible, and so $q(x)$ must be an associate of $f(x)$ (and hence be of equal degree). However, that implies that it has degree higher than $f'(x)$ if $f'(x) \neq 0$. Since $q(x) \big| f'(x)$, the only possibility left is that $f'(x) = 0$, as we sought to show.

Corollary 19.6.8: Separability Over Characteristic 0

let k be a field of characteristic 0 and $f(x) \in k[x]$ an irreducible polynomial. Then $f(x)$ is seperable.

***Proof*:**
Since f is irreducible, it must have degree at least 2, and so $f'(x) \neq 0$, showing it is separable by proposition 19.6.7

Thus, every algebraic extension of a characteristic 0 field is a separable extension, and fields in which an irreducible polynomial is inseperable must have characteristic p. Even better, given an inseperable polynomial:

$$f(x) = \sum_{i}^{n} a_i x^i$$

since $f'(x) = 0$:

$$f'(x) = \sum_{i}^{n} i a_i x^{i-1} = 0$$

thus, $ia_i = 0$ for all i, so ia_i is a multiple of p. If i itself is a multiple of p, then certainly $ia_i = 0$, and so it must be that $a_i = 0$ for all indicies that are *not* multiples of p. Therefore, we have reduced inseparable polynomials to polynomials of the form:

$$f(x) = a_0 + a_p x^p + a_{2p} + x^{2p} + \cdots + a_{np} x^{np} = \sum_{k=1}^{n} a_k (x^p)^k$$

Thus, an inseparable polynomial $f(x)$ can be thought of as a polynomial in x^p, $f(x) = g(x^p)$. Using this, we can define the following homomorphism which will be useful to characterize fields which have inseparable polynomials:

Definition 19.6.9: Frobenius Homomorphism

Let k be a field such that $p = \mathrm{ch}(k) > 0$. Then the *Frobenius homomorphism* is a map $k \to k$ defined by

$$x \mapsto x^p$$

It should be verified that this map is indeed a field homomorphism. the Frobenius must be injective, being a homomorphism between fields, however it need not be surjective. Using this homomorphism, we will find all fields in which being separable is identical to being algebraic:

Definition 19.6.10: Perfect Field

Let k be a field. Then k is called a *perfect field* if all irreducible polynomials in $k[x]$ are seperable, that is, every algebraic extension is a separable extension.

Proposition 19.6.11: Frobenius Homomorphism And Separability

Let k be a field. Then k is perfect if and only if either:

1. if $\text{ch}(k) = 0$
2. if $\text{ch}(k) > 0$ and the Frobenius homomorphism is surjective.

***Proof*:**
If $\text{ch}(k) = 0$, then by corollary 19.6.8, any irreducible polynomial is already seperable, so let's say $\text{ch}(k) = p$ for some prime p.

($\Leftarrow$) By our discussion from earlier, we know an inseparable irreducible polynomial must be of the form:

$$f(x) = \sum_{i=1}^{n} a_i (x^p)^i$$

Now, since the Frobenius homomorphism is surjective, for everry a_i, there exists a b_i such that $b_i \mapsto a_i$, that is $(b_i)^p = a_i$. Thus, using the fact that this map is indeed a ring homomorphism, we get:

$$f(x) = \sum_{i=1}^{n} b_i^p (x^p)^i = \sum_{i=1}^{n} (b_i x^i)^p = \left(\sum_{i=1}^{n} b_i x^i \right)^p = g(x)^p$$

where $g(x) = \sum_{i=1}^{n} b_i x^i$. But then $f(x)$ has become reducible! This contradicts our assumption of the irreducibility of $f(x)$, showing us that no such polynomial can exist.

($\Rightarrow$) Take the contra-positive, that $\text{ch}(k) \neq 0$ (say $\text{ch}(k) = p$) and that the Frobenius homomorphism is not surjective. Let's say that φ is the Frobenius homomorphism and that $t \in k \setminus \varphi(k)$. I claim that $x^p - t$ does not split into linear factors. Indeed, emulating what we have done in example 19.6.1, we get $x^p - t$ is irreducible, and that $(x - u)^p = x^p - t$

Here is another one: Suppose that T has characteristic $p > 0$, and that $x \mapsto x^p$ is not an automorphism. Since a ring homomorphism from a field into itself is injective or zero, then $x \mapsto x^p$ is not surjective.

Let $a \in T$ be such that $a \neq b^p$ for every $b \in T$. Let $f(x) = x^p - a$. We prove that f is irreducible and inseparable. If α is a root of $x^p - a$, then $x^p - a = (x - a)^p$, so α is a multiple root of f (with multiplicity p), hence f is inseparable. Now, let $g(x)$ be an irreducible factor of $f(x)$. Note that $\alpha \notin T$, otherwise $a = \alpha^p$, contrary to the assumption. Then $g(x) = (x - \alpha)^k$ for some $1 < k \leq p$. Using the binomial theorem, we have

$$g(x) = (x - \alpha)^k = x^k - k\alpha x^{-1} + \cdots + (-\alpha)^k$$

Therefore, $k\alpha \in T$. Since $\alpha \notin T$, then $k = p$, so $g = f$. Hence, f is irreducible.

Corollary 19.6.12: Finite Fields Are Perfect

let k be a finite field. Then k is perfect

***Proof*:**
Since a finite field must have a $\text{ch}(k) = p > 0$, the Frobenius homomorphism is well-defined. Furthermore, Since k is a field, the homomorphism is injective. But an injective map between two finite sets is surjective, hence the Frobenius homomorphism is surjective, and so by proposition 19.6.11 k is perfect.

Thus, we have shown that over most fields we have worked with so far, they are separable. Inseparable extensions do not behave so well (as we will see, their galois group is [almost] trivial, and hence we get little information about them through galois theory), and so more focus is given in understanding the more common subclass of seperable extensions of a field.

19.6.1 Separability and Embeddings

It should be noted that there *are* separable extensions even if a field is not perfect. For example $x^6 - tx^3 + t \in \mathbb{F}_3(t)[x]$ is irreducible over $\mathbb{F}_3(t)$ and factors into unique linear terms in the splitting field, however the field is not perfect since $x^6 - x^3 + 1$ is irreducible and inseparable. Therefore, we need a better way of finding separable polynomial without relying on nice properties of the ground field. This will be part of the goal of this section.

To characterize separable extensions without relying on k being perfect, we will take advantage that a k-homomorphism is determined by where it maps the roots of minimal polynomials of elements of F. In this way, we get an idea of how many distinct roots a minmial polynomial contains. Recall that we have been able to characterize normal fields through k-homomorphisms: if $\sigma : F \to \overline{k}$ is a k-homomorphism and F/k is normal, then $\sigma(F) = F$, which, as noted in box 19.5.14, shows that for normal extensions we can characterize all k-homomorphisms as in fact being k-automorphisms (in the sense that all isomorphic copies of F are just symmetries of F). In general, separable extensions need not be normal, and hence they might have multiple embeddings into $\overline{k}$. However, understanding all possible k-homomorphisms still gives us a lot of information about our field as was just pointed out. Studying these embeddings will give us some more information about separable extensions, and will allow us to answer the question of whether an extension $k(\alpha)/k$ is separable if α is separable over k, and to see that any algebraic extension can further be broken down into a separable extension followed by a "purely inseparable" extension: F_{sep}/k and F/F_{sep}.

Definition 19.6.13: Separable Degree

Let F/k be a field extension. Then the number of k-homomorphism $F \to \overline{k}$ called the *separable degree* and is denoted

$$[F : k]_s = \text{Hom}_k(F, \overline{k}) = \text{Emb}_k(F)$$

where $\text{Emb}_k(F)$ is shortand for all possible k-embeddings of F into the algebraic closure of F [a]

[a] Note that for any two algebraic closures $\overline{k}_1, \overline{k}_2$, $\text{Hom}(F, \overline{k}_1) \cong \text{Hom}(F, \overline{k}_2)$, making the definition independent of particular algebraic closure, and hence the notation $\text{Emb}_k(F)$ unambiguous

For the curious reader who would want to see the connection between separability and the separable degree and wants a hint before looking at the solution, they may want to think about what happens to the root, since the following theorem is a generalization of theorem 19.2.27.

19.6.14 moment to ponder

Proposition 19.6.15: Separable Degree of Simple Extensions

Let $k \subseteq k(\alpha)$ be a simple algebraic extension. Then $[k(\alpha) : k]_s$ is equal to the number of distincts roots in $\overline{k}$ of the minimal polynomial of α. In particular,

$$[k(\alpha) : k]_s \leq [k(\alpha) : k]$$

with equality if and only if α is separable over k

Notice how this proposition gives us a way to check the separability of the element α without any appeal to k (i.e., without knowing whether k is perfect or not). In fact more is true: $[k(\alpha) : k]_s \mid [k(\alpha) : k]$. The proof of this fact is a bit more laborious than just showing the inequality since it requires the notion of *separable closure*, which is simply the intersection of all fields that are separable, and so we will leave it as an exercise.

***Proof*:**
This proof will be very similar to that of corollary 19.2.29. Consider the collection of k-homomorpihism $\{\iota_r : k(\alpha) \to \overline{k}\}$. By corollary 19.2.29, we can associate each of these homomorphisms with where a root r of the minimal polynomial $m_{\alpha,k}(x)$ maps to, i.e. $\iota_r(\alpha) = r$. We will start by showing that this correspondence is bijective:

$$\{\iota_r : k(\alpha) \to \overline{k}\} \leftrightarrow \{r\}$$

Injectivity comes easily since ι_r fixes k, and so it is completely determined by where α maps to, which necessarily is a root of the minimal polynomial for α. To show surjectivity, consider $\beta \in \overline{k}$ which is some root of the minimal polynomial $m_{\alpha,k}(x)$. Then by lemma 19.5.7, $k(\beta) \subseteq \overline{k}$ exists, and by theorem 19.2.27, there exists a unique isomorphism $k(\alpha) \xrightarrow{\sim} k(\beta)$. Hence, combining with $k(\beta) \subseteq \overline{k}$, we get an extension $k(\alpha) \subseteq \overline{k}$ that maps α to the root β, showing surjectivity.

Thus, we have establisehd a bijection between the roots of the minimal polynomial and the number of embeddings of a simple algebraic extension. Since the degree of α is the degree of the minimal polynomial, which is less than or equal to the number of roots the minimal polynomial contains, we have that:

$$[k(\alpha) : k]_s \leq [k(\alpha) : k]$$

If furthermore $k(\alpha)$ is separable, then the number of roots is the degree of the polynomial, and hence:

$$[k(\alpha) : k]_s = [k(\alpha) : k]$$

completing the proof.

Corollary 19.6.16: Tower Law For Finite Separable Extensions

Furthermore, if $F/E/k$ is a sequence of algebraic extensions, $[F:k]_s$ is finite if and only if $[F:E]_s$ and $[E:k]_s$ is finite, and furthermore:

$$[F:k]_s = [F:E]_s[E:k]_s$$

***Proof*:**
We will show that if $[E:k]_s$ or $[F:E]_s$ are infinite, so must $[F:k]_s$, and then show that if they are both finite, so must $[F:k]_s$ be. Let $\varphi : E \to \overline{k}$ be a k-homomorphism. Then since F/E exists and is algebraic over E (and hence k), by lemma 19.5.7, there exists an exension of φ to $\Phi : F \to \overline{k}$ fixing E (i.e. $\Phi|_E = \varphi$). Furthermore, an extension F into $\overline{E} = \overline{k}$ fixing E extends *a fortiori* the identity on k. Thus, if either $[E:k]_s$ or $[F:E]_s$ is infinite, so must $[F:k]_s$ be.

Conversely if $[F:E]_s$ and $[E:k]_s$ is finite, we will show $[F:k]_s$ is finite and the multiplicity formula holds. This is almost immediate: for any embedding $F \to \overline{k}$ that extends k, we can can first find all extensions from k to E fixing k, of which there are $[E:k]_s$ possible ways of doing so, and then and then extend any chosen embedding from F to $\overline{E} = \overline{k}$ ($F \to \overline{E}$) fixing E in $[F:E]_s$ different ways, giving us a total of $[F:E]_s[E:k]_s$ total possible extensions, completing the proof.

Proposition 19.6.17: Finite Separable Extension Equivalence

Let F/k be a finite extension. Then $[F:k]_s \leq [F:k]$, and the following are equivalent:

1. $F = k(\alpha_1, ..., \alpha_n)$ where each α_i, is separable over k
2. F/k is a separable extension
3. $[F:k]_s = [F:k]$

***Proof*:**
We will first generlize proposition 19.6.15 for finite extensions to show that $[F:k]_s \leq [F:k]$. Since F/k is finite, F is finitely generated over k, so let $F = k(\alpha_1, ..., \alpha_n)$. Using proposition 19.6.15, corollary 19.6.16, and theorem 19.3.7:

$$\begin{aligned}[F:k]_s &= [k(\alpha_1, ..., \alpha_{n-1})(\alpha_n) : k(\alpha_1, ..., \alpha_{n-1})]_s \cdots [k(\alpha_1) : k]_s \\ &\leq [k(\alpha_1, ..., \alpha_{n-1})(\alpha_n) : k(\alpha_1, ..., \alpha_{n-1})] \cdots [k(\alpha_1) : k] \\ &= [F:k]\end{aligned}$$

showing the inequality

($1 \Rightarrow 3$) Since each α_i is separable over k, it is separable over $k(\alpha_1, ..., \alpha_{i-1})$ (the minimal polynomial of α_i over the intermediate field divides the minimal polynomial over the ground field), and so the inequalites in the previous argument are in fact all equalities by corollary 19.6.16

($3 \Rightarrow 2$) Let $[F:k]_s = [F:k]$, take $\alpha \in F$, and consider $k \subseteq k(\alpha) \subseteq F$. Since F is a finite extension, by corollary 19.6.16,

$$[F:k(\alpha)]_s[k(\alpha):k]_s = [F:k]_s = [F:k] = [F:k(\alpha)][k(\alpha):k]$$

Thus, we have two numbers, say a, b such that $a \leq A$, $b \leq B$ and $ab = AB$. This forces $a = A$ and $b = B$, and so we can cancel $[F:k(\alpha)]_s$ and $[F:k(\alpha)]$ on both sides to get:

$$[k(\alpha):k]_s = [k(\alpha):k]$$

which, by proposition 19.6.15 shows that α is separable. Since $\alpha \in F$ was arbitrary, this shows that all elements of F are separable, and hence F/k is a separable extension.

($2 \Rightarrow 1$) Since F/k is separable and F is finite, $F = k(\alpha_1, ..., \alpha_n)$, and each α_i must be separable by definition.

We can finally answer the question posed in remark ref:RemarkSeparableEx: if α is separable over k, then so is $1 + \alpha$, α^2, and any other combination of α, since $k(\alpha)/k$ is separable.

Proposition 19.6.18: Tower Law For Separable Extensions

Let $F/E/k$ be a sequence of algebraic extensions. Then F/k is separable if and only if F/E and E/k is separable.

***Proof*:**
Suppose first that F/k is separable. Then E/k is separable, since every element of E lies in F. And for $\alpha \in F$ the minimal polynomial $m_{\alpha,E}$ divides $m_{\alpha,k}$ in $E[x]$, because $m_{\alpha,k}$ lies in $E[x]$ and has α as a root. A divisor of a polynomial with no repeated roots has none either, so $m_{\alpha,E}$ is separable and F/E is a separable extension.

Conversely, let F/E and E/k both be separable and take $\alpha \in F$. The point is to replace E, which may be enormous, by the finite piece of it that the minimal polynomial of α sees. Write

$$m_{\alpha,E}(x) = x^n + c_{n-1}x^{n-1} + \cdots + c_0 \qquad c_j \in E$$

and put $K = k(c_0, ..., c_{n-1})$. Each c_j lies in E and so is separable over k, whence K/k is a finite separable extension by proposition 19.6.17.

Now $m_{\alpha,E}$ has all its coefficients in K, so α is algebraic over K and $m_{\alpha,K}$ divides $m_{\alpha,E}$ in $K[x]$. The latter is separable because F/E is, so $m_{\alpha,K}$ is separable and $K(\alpha)/K$ is a finite separable extension. Multiplying separable degrees along $K(\alpha)/K/k$ with corollary 19.6.16, and ordinary degrees with theorem 19.3.7,

$$[K(\alpha):k]_s = [K(\alpha):K]_s\,[K:k]_s = [K(\alpha):K]\,[K:k] = [K(\alpha):k]$$

using proposition 19.6.17 on each of the two factors. That same proposition, read backwards, makes $K(\alpha)/k$ separable, so α is separable over k. As $\alpha \in F$ was arbitrary, F/k is separable, as we sought to show.

Note that along with the fact that an extension is normal (implying the minimal polynomial splits), we get a bijection between the roots of the minimal polynomial and the automorphisms fixing the base field. For this reason, this will be one of the definitions (out of many equivalent definitions) of a galois extension.

Exercise 19.6.1

1. Let $K/\mathbb{Q}$ be a finite extension. Show that there exists an injective ring homomorphism $K \hookrightarrow \mathbb{R}^{r_1} \oplus \mathbb{C}^{r_2}$ for appropriate r_1, r_2. This is called the *Archimedean embedding* and the codomain is called the *Minkowski space*. Both are taken up in [15, Archimedean Embedding].

19.6.2 Separability and Simple Extensions

Finally, we show that all finite-degree separable fields (of infinite cardinality) are in fact simple. This means that when we were working with the finite extension F/k, we can always find an α where $F = k(\alpha)$. We will show the case for fields of finite cardinality in the next section.

Proposition 19.6.19: Algebraic And Simple Extensions

Let F/k be an algebraic extension. Then F is simple if and only if the number of distinct intermediate fields $k \subseteq E \subseteq F$ is finite

***Proof*:**

Let F/k be simple, so that $F = k(\alpha)$. Since F is algebraic, let $m_{\alpha,k}(x)$ be the minimal polynomial over k. Embed $k(\alpha)$ into an algebraic closure $\overline{k}$. If E is an intermediary field $k \subseteq E \subseteq F$, then $k(\alpha) = F = E(\alpha)$ is also a simple algebraic extension. Denote $m_{E,\alpha}(x)$ to be the minimal polynomial for $E(\alpha)$ over E. Since $m_{k,\alpha}(x) \in E[x]$ for all E and $m_{k,\alpha}(\alpha) = 0$, we know that each $m_{E,\alpha}(x)$ is a factor of $m_{k,\alpha}(x)$.

I claim that E is determined by $m_{E,\alpha}(x)$. Since $m_{k,\alpha}(x)$ has finitely many factors in $\overline{k}$, this will prove there are only finitely many intermediate fields, completing one direction of the proof.

Proceeding with proving the claim, I will show that E is generated (over k) by the coefficients of $m_{E,\alpha}(x)$. To see this, let E' be the set generated by k and the coefficients of $m_{E,\alpha}(x)$. Then $m_{E,\alpha}(x) \in E'[x]$, and since $m_{E,\alpha}(x)$ is irreducible in E, it is irreducible in E', and in fact minimal. Note too that $E'(\alpha) = k(\alpha) = E(\alpha)$, so $[k(\alpha) : E'] = \deg(m_{E,\alpha}(x)) = [k(\alpha) : E]$

Now, we have $E' \subseteq E \subseteq k(\alpha)$, therefore by the tower law:

$$\deg(m_{E,\alpha}(x)) = [k(\alpha) : E'] = [k(\alpha) : E][E : E'] = \deg(m_{E,\alpha}(x))[E : E']$$

Thus, it must be that $[E : E'] = 1$, hence $E = E'$, showing that E is indeed completely determined by $m_{E,\alpha}(x)$, hence there can only be finiely many intermediate fields.

Conversely, let's assume there are finitely many intermediate field $k \subseteq E \subseteq F$. Then it must be that the extension F/k is finite, or else we could construct an infinite sequene of sub-extensions $k \subseteq k(\alpha_1) \subseteq k(\alpha_1, \alpha_2) \subseteq \cdots F$. Thus, F/k is algebraic. We will deal with the case of F being a finite field in corollary 19.7.15. Thus, for now, assume k is a field of infinite cardinality. We have to show that every $F = k(\alpha_1, ..., \alpha_n)$ is in fact simple.

Arguing induictively, it suffices to show that $k(\alpha, \beta)$ is simple. For every $c \in k$, we have:

$$k \subseteq k(c\alpha + \beta) \subseteq k(\alpha, \beta)$$

Since there are only finitely many intermediate fields, it must be that for some two $c, c' \in k$, $c \neq c$:

$$k(c\alpha + \beta) = k(c'\alpha + \beta)$$

But then:

$$\alpha = \frac{(c'\alpha + \beta) - (c\alpha + \beta)}{c' - c} \in k(c\alpha + \beta)$$
$$\beta = (c\alpha + \beta) - c\alpha \in k(c\alpha + \beta)$$

Thus, $k(\alpha, \beta) \subseteq k(c\alpha + \beta)$. Since $k(c\alpha + \beta) \subseteq k(\alpha, \beta)$, we have an equality, showing that it is indeed simple, completing the proof.

Theorem 19.6.20: Primitive Element Theorem

Let F/k be a finite separable extension. Then F is also a *simple* extension.

***Proof*:**

Arguing inductively, we may take $F = k(\alpha, \beta)$ with α and β separable over k (and hence algebraic). As before, the finite case will be dealt with in corollary 19.7.15.

Let I be the number of k-homomorphisms $\iota : F \to \overline{k}$ (so $|I| = [F : k]_s$). Choose two $\iota, \iota' \in I$ where $\iota \neq \iota$. If x is an indeterminate, then the polynomials

$$\iota(\alpha)x + \iota(\beta) \quad \iota'(\alpha)x + \iota'(\beta)$$

are different (or else $\iota'(\alpha) = \iota(\alpha)$ and $\iota'(\beta) = \iota(\beta)$ so ι, ι' would act in the same way on the whole of $k(\alpha, \beta)$ forcing $\iota = \iota'$)

Therefore, define:

$$f(x) = \prod_{\iota \neq \iota'} ((\iota(\alpha)x + \iota(\beta)) - (\iota'(\alpha)x + \iota'(\beta))) \in \overline{k}[x]$$

The polynomial $f(x)$ cannot be identically 0 since k is infinite. Thus, take $c \in k$ such that $f(c) \neq 0$. So, a distinct map $\iota \in I$ will map $\gamma = c\alpha + \beta$ to distinct elements $\iota(\alpha)c + \iota(\beta)$ (recall $\iota(c) = c$). Since $|I| = [F : k]_s$, and each $\iota(\gamma)$ is a root of the minimal polynomial of γ over k, we have:

$$[F : k]_s \leq [k(\gamma) : k] \leq [F : k]$$

By assumption, the extension is separable, so we have equalities above:

$$[F : k]_s = [k(\gamma) : k] = [F : k]$$

Thus:

$$F = k(\gamma)$$

as we sought to show.

Using this, we can extend corollary 19.2.29 from simple to finite extensions:

Corollary 19.6.21: Order of $\mathrm{Aut}_k(F)$ Of Finite Extension

Let F/k be a finite seprable extension. Then:

$$|\mathrm{Aut}_k(F)| \leq [F:k]$$

with equlaity if and only if F/k is a finite separable normal extension.

***Proof*:**
By theorem 19.6.20, if K is finite and separable, it is simple, and so the inequality immediately holds by corollary 19.2.29. Equality holds if the minimal polynomial splits, which it does over it's splitting field, which is a normal extension by theorem 19.5.13. Conversely, if K/F is normal, then $f(x)$ splits completly in F and has distinct roots since α is separable over k, establishing equalitly once again, completing the proof.

Note that the separability condition is necessary:

Example 19.6.22: Nonseparable Nonsimple Extension
Let $F = \mathbb{F}_p(u,v)$ be the field with two indeterminate variables over $\mathbb{F}_p$, and subfield $k = \mathbb{F}_p(s,t)$ such that $s = u^p$ and $t = v^p$. Then F/k is an algebraic extension. The minimal polynomial of u over k is $x^p - s$, and the minimal polynomial of v over $k(u)$ is $y^p - t$. Thus:

$$[F:k] = p^2$$

Arguing like before, As c ranges in k, we get the intermediate fields:

$$k \subseteq k(cu+v) \subseteq F$$

If any two chocies c, c' get give the same intermediate field, then we can deduce $k(u,v) = k(cu+v)$ as we have argued earlier. This would then give us:

$$[k(cu+v):k] = p^2$$

However, the minimal polynomial of $cu+v$ has degree p:

$$(cu+v)^p = c^p + st \in k(s,t) = k$$

Thus, since $k = \mathbb{F}_p(s,t)$ is infinite, there are infinitely many intermediate fields, and it follows that F is *not* a simple extension of k by proposition 19.6.19

As a final result, we state the following that shall be handy for chapter 33:

Theorem 19.6.23: Lüroth's Theorem

Let k be a field, let t be transcendental over k, and let E be a field with $k \subsetneq E \subseteq k(t)$. Then there exists $u \in E$ such that

$$E = k(u)$$

***Proof*:**
Since t is transcendental, $k[t]$ is a polynomial ring and every element of $k(t)$ is a quotient of two elements of $k[t]$ (theorem 19.2.8). For a polynomial G in two variables t and X we view $k[t][X] = k[t, X] = k[X][t]$ and write $\deg_t G$ and $\deg_X G$ for its degrees in t and in X.

Step 1: the minimal polynomial of t over E. Choose $u_0 \in E \setminus k$ and write $u_0 = a_0(t)/b_0(t)$ with $a_0, b_0 \in k[t]$ and $b_0 \neq 0$. The polynomial $a_0(X) - u_0 b_0(X) \in E[X]$ has t as a root, and it is nonzero: otherwise its coefficients give $a_{0,l} = u_0 b_{0,l}$ for every l, and an l with $b_{0,l} \neq 0$ gives $u_0 = a_{0,l}/b_{0,l} \in k$. So t is algebraic over E. Since $E \supseteq k$, the field $E(t)$ is $k(t)$. Let $f(X) = X^n + c_{n-1}X^{n-1} + \cdots + c_0 \in E[X]$ be the monic minimal polynomial of t over E. Then $n = [k(t) : E]$, and f divides every polynomial of $E[X]$ having t as a root, since it generates the kernel of evaluation at t (theorem 19.2.8, theorem 19.2.5).

Step 2: a coefficient u of f. Some c_j is not in k, since otherwise f would be a nonzero polynomial over k with the root t. Fix such a j and put $u = c_j \in E$. Write $u = a(t)/b(t)$ with $a, b \in k[t]$, $b \neq 0$ and $\deg b$ as small as possible. Then a and b have no common nonconstant factor, since cancelling one would lower $\deg b$, so in the principal ideal domain $k[t]$ (corollary 11.1.2) the ideal $(a) + (b)$ is (1), that is, $1 = \mu a + \nu b$ for some $\mu, \nu \in k[t]$ (definition 10.1.24). Moreover $a \neq \lambda b$ for every $\lambda \in k$, since otherwise $u = \lambda \in k$. Write $a = \sum_l a_l t^l$ and $b = \sum_l b_l t^l$, and let $m = \max(\deg a, \deg b)$. The polynomial

$$P(X) = a(X) - ub(X) \in k(u)[X]$$

has t as a root, and its coefficient of X^m is $a_m - ub_m \neq 0$: if $b_m \neq 0$, then $a_m - ub_m = 0$ would give $u = a_m/b_m \in k$, and if $b_m = 0$, then $a_m \neq 0$. So P has degree m, and $[k(t) : k(u)] \leq m$ (proposition 19.3.3), as $k(u)(t) = k(t)$. Since $k(u) \subseteq E$, the tower law (theorem 19.3.7) gives

$$[k(t) : k(u)] = [k(t) : E][E : k(u)] = n[E : k(u)]$$

Step 3: clearing denominators. Multiplying f by a common denominator of its coefficients gives elements of the form ef with $e \in k(t)^\times$ lying in $k[t][X]$. Among them choose $F = ef$ whose coefficient of X^n, which is e, has the least degree. Then $e \in k[t]$, and the coefficients $F_0, \ldots, F_n \in k[t]$ of F have no common nonconstant factor π, since $(e/\pi)f$ would have a coefficient of X^n of smaller degree. The coefficient of X^j is $F_j = eu = ea/b$, so $bF_j = ea$ and $e = \mu ea + \nu eb = b(\mu F_j + \nu e)$. Hence b divides e, $\deg F_n = \deg e \geq \deg b$, and $\deg F_j = \deg e - \deg b + \deg a \geq \deg a$, using $a \neq 0$ (proposition 9.2.3(1)). Therefore $\deg_t F \geq m$.

Step 4: F divides $Q = a(X)b(t) - a(t)b(X)$ in $k[t][X]$. We have $Q = b(t)P(X)$. As $P \in k(u)[X] \subseteq E[X]$ has the root t, f divides P in $E[X]$, so $Q = FH$ for some $H \in k(t)[X]$. Write $H = H_0/c$ with $H_0 \in k[t][X]$ and $0 \neq c \in k[t]$ of least possible degree, and suppose that c is not a nonzero constant. Let π be an irreducible factor of c in $k[t]$. Then (π) is a maximal ideal (proposition 10.1.33, proposition 10.1.32), so $\kappa = k[t]/(\pi)$ is a field (proposition 9.4.19), and reducing coefficients modulo π is a ring homomorphism $k[t][X] \to \kappa[X]$ (theorem 9.2.4). Reducing $cQ = FH_0$ gives $0 = \overline{F}\,\overline{H_0}$ in $\kappa[X]$, an integral domain (proposition 9.2.3(3)). As π does not divide every coefficient of F, $\overline{F} \neq 0$, so $\overline{H_0} = 0$, that is, π divides every coefficient of H_0, and $H = (H_0/\pi)/(c/\pi)$ contradicts the minimality of $\deg c$. So c is a nonzero constant and $H \in k[t][X]$.

Step 5: H is a nonzero constant. The coefficient of X^m in Q is $a_m b(t) - a(t)b_m$, which is nonzero: if $b_m \neq 0$ its vanishing would give $a = (a_m/b_m)b$, which is excluded, and if $b_m = 0$ then $a_m \neq 0$ and it equals $a_m b(t) \neq 0$. So $Q \neq 0$. As a polynomial in t over the integral domain $k[X]$,

$$Q = \sum_l \left(a(X)b_l - a_l b(X)\right) t^l$$

has $\deg_t Q \leq m$, and $\deg_t Q = \deg_t F + \deg_t H$ (proposition 9.2.3(1)). With $\deg_t F \geq m$ this forces $\deg_t H = 0$, that is, $H \in k[X]$. Suppose $\deg H \geq 1$ and let h be an irreducible factor of H in $k[X]$. Then h divides $Q = FH$ in $k[X][t]$, and comparing coefficients of t^l shows that h divides $a(X)b_l - a_l b(X)$ for every l. Let $\kappa' = k[X]/(h)$, a field for the same reason as κ in Step 4, and let θ be the class of X, so that $g(\theta) = 0$ exactly when h divides g. Then $a(\theta)b_l = a_l b(\theta)$ for every l. If $b(\theta) \neq 0$, then $a_l = \lambda b_l$ for every l with $\lambda = a(\theta)/b(\theta)$, and an l with $b_l \neq 0$ shows $\lambda = a_l/b_l \in k$, so $a = \lambda b$, which is excluded. If $b(\theta) = 0$, then $a(\theta)b_l = 0$ for every l, so $a(\theta) = 0$, and h divides both a and b, contradicting $(a) + (b) = (1)$. Hence H is a nonzero constant.

Step 6: conclusion. By Step 5, F is a nonzero constant multiple of Q, so $n = \deg_X F = \deg_X Q$. The coefficient of X^l in Q is $a_l b(t) - a(t)b_l$, which vanishes for $l > m$ and not for $l = m$, so $\deg_X Q = m$. Hence $n = m$, and Step 2 gives $n[E : k(u)] = [k(t) : k(u)] \leq m = n$. So $[E : k(u)] = 1$, that is, $E = k(u)$, as we sought to show.

Exercise 19.6.2

1. Let E/k and F/k be field extensions inside a common field. Show that if E/k is separable, then so is EF/F. Show that if E/k and F/k are separable, so is EF/k.
2. Let F/k is simple so that $F = k(\alpha)$. then if L is the splitting field for a [not necessarily separable] minimal polynomial $m_{\alpha,k}(x)$, $L = \prod_{\sigma \in \mathrm{Emb}_k(F)} \sigma(F)$. If F is normal, then $L = F$, and if F separable, we have an idea of the number of σ exists, namely the degree of $k(\alpha)$ over k)

19.6.3 Important Functional: Resultant and Discriminant

One very useful functional on $R[x]$ that allows us to detect when a polynomial has a root even R need not contain the roots is the following:

Theorem 19.6.24: Resultant

Let R be an integral domain and $f(x), g(x) \in R[x]$ be two polynomials:

$$f(x) = a_n x^n + a_{n-1}x^{n-1} + \cdots + a_1 x + a_0$$
$$g(x) = b_m x^m + b_{m-1}x^{m-1} + \cdots + b_1 x + b_0$$

where $a_n, b_m \neq 0$ so that their degree is the highest order term. Then f and g have a common root if and only if:

$$\text{Res}(f,g) := \det \begin{pmatrix} a_n & 0 & \cdots & 0 & b_m & 0 & \cdots & 0 \\ a_{n-1} & a_n & \cdots & 0 & b_{m-1} & b_m & \cdots & 0 \\ a_{n-2} & a_{n-1} & \cdots & 0 & b_{m-2} & b_{m-1} & \ddots & 0 \\ \vdots & \vdots & \ddots & a_n & \vdots & \vdots & \ddots & b_m \\ a_0 & a_1 & \cdots & \vdots & b_0 & b_1 & \cdots & \vdots \\ 0 & a_0 & \ddots & \vdots & 0 & b_0 & \ddots & \vdots \\ \vdots & \vdots & \ddots & a_{n-1} & \vdots & \vdots & \ddots & b_1 \\ 0 & 0 & \cdots & a_0 & 0 & 0 & \cdots & b_0 \end{pmatrix} = 0$$

is zero.

***Proof*:**

Let $f, g \in R[x]$ be (not necessarily monic) polynomials with degree n and m respectively. If either $f = 0$ or $g = 0$, there is nothing to prove, so assume both are nonzero. Let $\mathcal{P}_n$, $\mathcal{P}_m$ be the free R-modules of polynomial up to degree strictly less than n and strictly less than m respectively. Then $\mathcal{P}_n, \mathcal{P}_m$ have dimension (rank)[a] n, m, so $\mathcal{P}_n \times \mathcal{P}_m$ has dimension $n + m$. Define:

$$\varphi : \mathcal{P}_m \times \mathcal{P}_n \to \mathcal{P}_{n+m} \qquad \varphi(p,q) = fp + gq$$

As R is an integral domain, $\deg(fp + gq) = n + m$, otherwise it may be of a smaller degree and we may get unwanted zero-polynomials. The function φ is linear as:

$$\begin{aligned} \varphi((p_1,q_1) + (p_2,q_2)) &= \varphi(p_1 + q_2, q_1 + q_2) \\ &= f(p_1 + p_2) + g(q_1 + q_2) \\ &= fp_1 + fp_2 + gq_1 + gq_2 \\ &= (fp_1 + gq_1) + (fp_2 + gq_2) \\ &= \varphi(p_1,q_1) + \varphi(p_2,q_2) \end{aligned}$$

Hence, this transformation has a matrix representation. Choosing the (ordered) basis $(x^{n-1}, x^{n-2}, ..., x, 1)$ for $\mathcal{P}_n$ and the (ordered) basis $(y^{m-1}, y^{m-2}, ..., y, 1)$ for $\mathcal{P}_m$, we get the matrix representation:

$$\begin{pmatrix} a_n & 0 & \cdots & 0 & b_m & 0 & \cdots & 0 \\ a_{n-1} & a_n & \cdots & 0 & b_{m-1} & b_m & \cdots & 0 \\ a_{n-2} & a_{n-1} & \cdots & 0 & b_{m-2} & b_{m-1} & \ddots & 0 \\ \vdots & \vdots & \ddots & a_n & \vdots & \vdots & \ddots & b_m \\ a_0 & a_1 & \cdots & \vdots & b_0 & b_1 & \cdots & \vdots \\ 0 & a_0 & \ddots & \vdots & 0 & b_0 & \ddots & \vdots \\ \vdots & \vdots & \ddots & a_{n-1} & \vdots & \vdots & \ddots & b_1 \\ 0 & 0 & \cdots & a_0 & 0 & 0 & \cdots & b_0 \end{pmatrix}$$

Note that $f \notin \mathcal{P}_n$ and $g \notin \mathcal{P}_m$ or else there would always exist $\varphi(-g, f) = -fg + fg = 0$, which would ruin the following argument using the determinant. Let M represent this matrix.

If f, g share a common $\alpha \in \overline{K}$ where $K = \text{Frac}(R)$, then there exists an $h \in \overline{K}[x]$ such that $h(x)f_0(x) = f(x)$ and $h(x)g_0(x) = g(x)$ for appropriate factors $f_0, g_0 \in \overline{K}[x]$. Then $\varphi(-g_0, f_0) = 0$ with $(-g_0, f_0) \neq 0$, so $\det(M) = 0$ by proposition 13.4.13, applied over the integral domain $\overline{K}$.

Conversely, suppose $\det(M) = 0$. By proposition 13.4.13 there exist p_0, q_0, not both zero, such that

$$fp_0 + gq_0 = 0 \qquad \Rightarrow \qquad fp_0 = -gq_0 \tag{19.3}$$

We will use this to show that f, g are not relatively prime. Suppose $(f, g) = 1$ so that there exists s, t such that $ft + sg = 1$. Then $ftp_0 + sgp_0 = p_0$. Substituting $fp_0 = -gq_0$ from equation (19.3) we get:

$$gq_0p_0 + sgp_0 = g(q_0p_0 + sp_0) = p_0$$

As R is an integral domain, $g | p_0$ so $p_0 = gh$. Similarly, $q_0 = fr$.

Both of these cause a contradiction. For example, considering $p_0 = gh$, then:

$$m > \deg(p_0) = \deg(gh) = \deg(g) + \deg(h) = m + \epsilon$$

where $\epsilon \in \mathbb{N}$. Thus (f, g) is *not* relatively prime. Then if $K = \text{Frac}(R)$ we have that $\overline{K}[x]$ is a PID and it must be that there exists a unit $h \in \overline{K}[x]$

$$(h) = (f, g)$$

showing f, g have a common root.

[a] Note that as this is over finite dimensions and over commutative rings, the rank is invariant and hence there is no issue when we use the specific rank later in the proof

Definition 19.6.25: Resultant

The determinant in theorem 19.6.24 $\text{Res}(f, g)$ is called the *resultant*. If the base-ring is not clear, we often denote it as $\text{Res}_R(f, g)$ for the desired ring R, and if the indeterminate element is not clear we may denote it as $\text{Res}_x(f, g)$.

The form above is useful as it can be defined over an integral domain R and is better suited for computational purposes as no field extensions are required. The following is often useful when strictly

working over algebraically closed fields:

Proposition 19.6.26: Characterizing Resultant using Algebraically Closed Fields

Let $f, g \in R[x]$ be (not necessarily monic) polynomials over an integral domain R, of degrees n and m with leading coefficients a_n and b_m respectively, and let $\overline{K}$ be the algebraic closure of $K = \mathrm{Frac}(R)$. Then if $\alpha_1, ..., \alpha_n$ are the roots of f and $\beta_1, ..., \beta_m$ the roots of g respectively (listed with multiplicity):

$$\mathrm{Res}(f, g) = a_n^m b_m^n \prod_{i,j} (\alpha_i - \beta_j)$$

***Proof*:**

Over $\overline{K}$ we may write

$$f = a_n \prod_{i=1}^{n} (x - \alpha_i) \qquad g = b_m \prod_{j=1}^{m} (x - \beta_j)$$

The Sylvester matrix of theorem 19.6.24 has entries in $R \subseteq \overline{K}$ and its determinant is the same computed over either ring, so we work over $\overline{K}$ throughout. Note also that $\overline{K}$ is infinite: a finite field $\{c_1, \dots, c_q\}$ is never algebraically closed, since the polynomial $\prod_u (x - c_u) + 1$ has no root in it.

Step 0: a Vandermonde determinant. For scalars $\gamma_1, \dots, \gamma_N$ let $W(\gamma_1, \dots, \gamma_N)$ be the $N \times N$ matrix with entry γ_u^{N-c} in row u and column c, so the columns list decreasing powers $N - 1, \dots, 1, 0$. We claim

$$\det W(\gamma_1, \dots, \gamma_N) = \prod_{u<v} (\gamma_u - \gamma_v)$$

We induct on N, the case $N = 1$ being the empty product 1. For $c = 1, 2, \dots, N-1$ in this order, subtract γ_N times column $c+1$ from column c. By multilinearity and the alternating property (proposition 13.4.6(3), (4)) this does not change the determinant, and when column c is modified, column $c+1$ still holds its original entries. The new entry in row u and column $c \le N-1$ is $\gamma_u^{N-c} - \gamma_N \gamma_u^{N-c-1} = \gamma_u^{N-c-1}(\gamma_u - \gamma_N)$, while column N keeps the entries 1. In particular row N becomes $(0, \dots, 0, 1)$, so in the defining sum (definition 13.4.5) only permutations fixing N contribute, and these are exactly the permutations of $\{1, \dots, N-1\}$ with unchanged sign. Hence the determinant equals that of the top left $(N-1) \times (N-1)$ block, whose row u carries the common factor $(\gamma_u - \gamma_N)$. Factoring it out of each row (proposition 13.4.6(2), (3)) leaves $W(\gamma_1, \dots, \gamma_{N-1})$, and the induction hypothesis gives the claim. In particular, splitting the pairs $u < v$ into pairs of α's, pairs of β's, and mixed pairs,

$$\det W(\alpha_1, \dots, \alpha_n, \beta_1, \dots, \beta_m) = \det W(\alpha_1, \dots, \alpha_n) \det W(\beta_1, \dots, \beta_m) \prod_{i,j} (\alpha_i - \beta_j)$$

Step 1: the identity when $\alpha_1, \dots, \alpha_n, \beta_1, \dots, \beta_m$ are pairwise distinct. Let $\mathcal{P}_d$ denote the polynomials of degree strictly less than d over $\overline{K}$, with the descending monomial bases, and consider the linear maps

$$\Phi : \mathcal{P}_m \times \mathcal{P}_n \to \mathcal{P}_{n+m} \quad \Phi(p, q) = fp + gq \qquad E : \mathcal{P}_{n+m} \to \overline{K}^{n+m} \quad E(h) = (h(\alpha_1), \dots, h(\alpha_n), h(\beta_1), \dots, h(\beta_m))$$

Inspecting the columns of the matrix in theorem 19.6.24, its c-th column for $c \le m$ lists the coefficients of $x^{m-c} f$, and its $(m+c)$-th column for $c \le n$ the coefficients of $x^{n-c} g$, with

respect to the descending powers $x^{n+m-1}, \dots, x, 1$. Hence the Sylvester matrix is the matrix M of Φ, and $\det(M) = \operatorname{Res}(f, g)$. The matrix of E with respect to the descending basis is $W_{\alpha\beta} := W(\alpha_1, \dots, \alpha_n, \beta_1, \dots, \beta_m)$, whose determinant is nonzero by Step 0 since the scalars are pairwise distinct. By theorem 13.2.6 and proposition 13.4.7,

$$\det[E \circ \Phi] = \det(W_{\alpha\beta} M) = \det(W_{\alpha\beta}) \operatorname{Res}(f, g)$$

On the other hand, the matrix of $E \circ \Phi$ can be computed directly: its c-th column for $c \leq m$ is the evaluation vector of $x^{m-c} f$, which vanishes at every α_i and takes the value $\beta_j^{m-c} f(\beta_j)$ at β_j, and its $(m+c)$-th column is the evaluation vector of $x^{n-c} g$, taking the value $\alpha_i^{n-c} g(\alpha_i)$ at α_i and vanishing at every β_j. Hence

$$[E \circ \Phi] = \begin{pmatrix} 0 & G \\ F & 0 \end{pmatrix} \qquad G_{ic} = g(\alpha_i) \alpha_i^{n-c} \qquad F_{jc} = f(\beta_j) \beta_j^{m-c}$$

with G of size $n \times n$ and F of size $m \times m$. Moving the last n columns to the front is a permutation of the columns realized by nm transpositions, which multiplies the determinant by $(-1)^{nm}$ (proposition 13.4.6(2), (5)) and produces the block diagonal matrix with blocks G and F. Hence by proposition 13.4.8 and factoring $g(\alpha_i)$ out of the i-th row of G and $f(\beta_j)$ out of the j-th row of F,

$$\det[E \circ \Phi] = (-1)^{nm} \det(G) \det(F) = (-1)^{nm} \prod_i g(\alpha_i) \prod_j f(\beta_j) \det W(\alpha_1, \dots, \alpha_n) \det W(\beta_1, \dots, \beta_m)$$

Comparing the two computations of $\det[E \circ \Phi]$, cancelling the nonzero factor $\det(W_{\alpha\beta})$ using the factorization from Step 0, we get

$$\operatorname{Res}(f, g) = (-1)^{nm} \frac{\prod_i g(\alpha_i) \prod_j f(\beta_j)}{\prod_{i,j} (\alpha_i - \beta_j)}$$

Substituting $\prod_i g(\alpha_i) = b_m^n \prod_{i,j} (\alpha_i - \beta_j)$ and $\prod_j f(\beta_j) = a_n^m \prod_{i,j} (\beta_j - \alpha_i) = (-1)^{nm} a_n^m \prod_{i,j} (\alpha_i - \beta_j)$ gives

$$\operatorname{Res}(f, g) = a_n^m b_m^n \prod_{i,j} (\alpha_i - \beta_j)$$

Step 2: the general case. Fix a_n and b_m and let $t_1, \dots, t_n, s_1, \dots, s_m$ be indeterminates. Set $f_t = a_n \prod_i (x - t_i)$ and $g_s = b_m \prod_j (x - s_j)$. Each coefficient of f_t and g_s is a polynomial in the t's and s's, every entry of the Sylvester matrix of (f_t, g_s) is such a coefficient or 0, and the determinant is a polynomial in the entries. Hence both

$$D_1 := \operatorname{Res}(f_t, g_s) \qquad D_2 := a_n^m b_m^n \prod_{i,j} (t_i - s_j)$$

lie in the polynomial ring $\overline{K}[t_1, \dots, t_n, s_1, \dots, s_m]$, and by Step 1 they take the same value at every point of $\overline{K}^{n+m}$ with pairwise distinct coordinates. Let E_0 be the product of the differences of all pairs of the $n+m$ variables. Then the polynomial $(D_1 - D_2) E_0$ vanishes at *every* point of $\overline{K}^{n+m}$: where the coordinates are distinct $D_1 - D_2$ vanishes, and elsewhere E_0 does.

A polynomial over $\overline{K}$ in N variables vanishing at every point of $\overline{K}^N$ is the zero polynomial. We induct on N: for $N = 1$ this is corollary 11.3.4 applied against the zero polynomial, using that

$\overline{K}$ is infinite. For $N > 1$, write the polynomial as $\sum_d h_d(x_1, \ldots, x_{N-1})x_N^d$. Fixing any values of the first $N-1$ variables and applying the case $N = 1$ shows each h_d vanishes at every point of $\overline{K}^{N-1}$, so each $h_d = 0$ by induction.

Hence $(D_1 - D_2)E_0 = 0$ in $\overline{K}[t, s]$, which is an integral domain by iterating proposition 9.2.3(3). Since E_0 is a product of nonzero polynomials, $E_0 \neq 0$, and therefore $D_1 = D_2$. Evaluating at $t_i = \alpha_i$ and $s_j = \beta_j$ gives the claimed identity.

One of the more important application is to find whether a polynomial has a multiple root:

Definition 19.6.27: Discriminant

Let $f \in R[x]$ be a polynomial over an integral domain. Then:

$$\Delta(f) = \operatorname{disc}(f) = \frac{(-1)^{n(n-1)/2}}{a_n}\operatorname{Res}(f, f')$$

If f is monic,

$$\Delta(f) = \operatorname{disc}(f) = (-1)^{n(n-1)/2}\operatorname{Res}(f, f')$$

Proposition 19.6.28: Discriminant As A Product

Let $f \in R[x]$ be a polynomial of degree n with leading coefficient a_n over an integral domain, $K = \operatorname{Frac}(R)$, and assume $na_n \neq 0$ in R. Let L/K be the splitting field of f. Then if $\alpha_1, ..., \alpha_n$ are the roots of f (with multiplicity),

$$\Delta(f) = a_n^{2n-2} \prod_{1 \leq i < j \leq n} (\alpha_i - \alpha_j)^2$$

In particular, $\Delta(f) = \prod_{1 \leq i < j \leq n}(\alpha_i - \alpha_j)^2$ when f is monic.

***Proof*:**

Over $L \subseteq \overline{K}$ write $f = a_n \prod_{i=1}^n (x - \alpha_i)$. The hypothesis $na_n \neq 0$ says the derivative $f' = na_n x^{n-1} + \cdots + a_1$ has degree $m := n - 1$ and leading coefficient $b_m = na_n \neq 0$, so proposition 19.6.26 applies to the pair (f, f'): if $\beta_1, \ldots, \beta_{n-1}$ are the roots of f', so that $f' = na_n \prod_j (x - \beta_j)$, then

$$\operatorname{Res}(f, f') = a_n^{n-1}(na_n)^n \prod_{i,j}(\alpha_i - \beta_j) = a_n^{n-1} \prod_{i=1}^{n} \left(na_n \prod_{j=1}^{n-1} (\alpha_i - \beta_j) \right) = a_n^{n-1} \prod_{i=1}^{n} f'(\alpha_i)$$

Writing $f = (x - \alpha_i)h_i$ with $h_i = a_n \prod_{j \neq i}(x - \alpha_j)$, the Leibniz property of the formal derivative gives $f' = h_i + (x - \alpha_i)h_i'$, and evaluating at α_i:

$$f'(\alpha_i) = h_i(\alpha_i) = a_n \prod_{j \neq i}(\alpha_i - \alpha_j)$$

Multiplying over i and pairing the factors $(\alpha_i - \alpha_j)$ and $(\alpha_j - \alpha_i) = -(\alpha_i - \alpha_j)$ for each of the

$n(n-1)/2$ pairs $i<j$:

$$\prod_{i=1}^{n} f'(\alpha_i) = a_n^n \prod_{i\neq j}(\alpha_i-\alpha_j) = a_n^n(-1)^{n(n-1)/2}\prod_{i<j}(\alpha_i-\alpha_j)^2$$

Hence

$$\operatorname{Res}(f,f') = a_n^{2n-1}(-1)^{n(n-1)/2}\prod_{i<j}(\alpha_i-\alpha_j)^2$$

and by definition 19.6.27,

$$\Delta(f) = \frac{(-1)^{n(n-1)/2}}{a_n}\operatorname{Res}(f,f') = (-1)^{n(n-1)}a_n^{2n-2}\prod_{i<j}(\alpha_i-\alpha_j)^2 = a_n^{2n-2}\prod_{1\leq i<j\leq n}(\alpha_i-\alpha_j)^2$$

since $(-1)^{n(n-1)} = 1$, the exponent being even. The monic case is the special case $a_n = 1$.

As is immediate after proposition 19.6.6:

Proposition 19.6.29: Vanishing Discriminant Gives a Multiple Root

Let $f \in \mathbb{R}[x]$ be a polynomial. Then if $\Delta(f) = 0$, f has a multiple root in the splitting field.

***Proof*:**
immediate.

here)

Separability has a numerical measure that is often more useful than the definition. A finite extension F/k makes F a finite-dimensional k-vector space, so every element of F acts on it by multiplication and has a trace in the sense of definition 13.4.3. That assignment is a k-linear form on F, and the symmetric bilinear form it induces detects separability exactly.

Definition 19.6.30: Trace of a Finite Field Extension

Let F/k be a finite field extension and let $x \in F$. Multiplication by x is a k-linear endomorphism $m_x \colon F \to F$, and the *trace* of x is

$$\operatorname{tr}_{F/k}(x) \;:=\; \operatorname{tr}(m_x) \in k$$

the trace of that endomorphism in the sense of definition 13.4.3. The *trace form* of F/k is the symmetric k-bilinear form

$$\langle x, y\rangle \;:=\; \operatorname{tr}_{F/k}(xy)$$

Proposition 19.6.31: The Trace Form of a Separable Extension Is Nondegenerate

Let F/k be a finite separable field extension. Then the trace form of F/k is nondegenerate: if $x \in F$ satisfies $\operatorname{tr}_{F/k}(xy) = 0$ for all $y \in F$, then $x = 0$. Equivalently, for any k-basis $e_1, \dots, e_n$ of F there is a dual basis $e_1^*, \dots, e_n^*$ with $\operatorname{tr}_{F/k}(e_i e_j^*) = \delta_{ij}$.

***Proof*:**
Step 1: reduce to a computation in one element. By theorem 19.6.20 the extension is simple, say $F = k(\alpha)$ with α of degree n over k and minimal polynomial m. Then $1, \alpha, \dots, \alpha^{n-1}$ is a k-basis of F, and it suffices to show that the Gram matrix $M = \big(\mathrm{tr}_{F/k}(\alpha^{i+j})\big)_{0 \le i,j \le n-1}$ of the trace form in that basis is invertible: by lemma 13.3.23 a bilinear form on a finite-dimensional space is nondegenerate (definition 13.3.22) exactly when its matrix in a basis is invertible, and the criterion is independent of which basis is used.

Step 2: traces are power sums of the roots. In the basis $1, \alpha, \dots, \alpha^{n-1}$ the matrix of m_α is the companion matrix of m, so the characteristic polynomial of m_α is m itself. Let $\alpha_1, \dots, \alpha_n$ be the roots of m in a splitting field. They are distinct because F/k is separable, so m is a separable polynomial (definition 19.6.3, proposition 19.6.7). The eigenvalues of the companion matrix are exactly the α_r, so those of m_α^j are the α_r^j, and therefore

$$\mathrm{tr}_{F/k}(\alpha^j) \;=\; \mathrm{tr}\big(m_\alpha^j\big) \;=\; \sum_{r=1}^{n} \alpha_r^j$$

for every $j \ge 0$.

Step 3: a Vandermonde determinant. Let $V = (\alpha_r^i)_{0 \le i \le n-1,\ 1 \le r \le n}$ be the Vandermonde matrix of the roots. By Step 2,

$$M_{ij} \;=\; \sum_{r=1}^{n} \alpha_r^i \alpha_r^j \;=\; \big(VV^{\mathsf{T}}\big)_{ij}$$

so $M = VV^{\mathsf{T}}$ and $\det M = (\det V)^2 = \prod_{r<s}(\alpha_r - \alpha_s)^2$. The roots are distinct, so this is nonzero and M is invertible. The dual basis is then obtained by inverting M, completing the proof.

The dual basis is what makes the trace form a finiteness tool: an element whose products with a fixed basis all have trace in a subring is pinned inside the free module spanned by the dual basis. That is the mechanism behind the finiteness of integral closure in *Commutative Algebra*,[22] and behind the finiteness of the ring of integers of a number field in *Algebraic Number Theory* [15].

For a transcendental extension K/k, a transcendence basis B makes K algebraic over $k(B)$ but says nothing about separability, and in characteristic p the two can come apart. Over a perfect field they can always be reconciled. Combined with the computation of $\Omega_{K/k}$ in section 21.3, this gives $\dim_K \Omega_{K/k} = \mathrm{trdeg} K/k$ for every finitely generated extension K of a perfect field k, and *Algebraic Geometry* uses that equality to show that the nonsingular points of a variety over an algebraically closed field form a nonempty open set.[23]

Definition 19.6.32: Separating Transcendence Basis

Let K/k be a field extension. A transcendence basis B of K/k is *separating* if K is a separable algebraic extension of $k(B)$. The extension K/k is *separably generated* if it admits one.

[22] theorem 26.1.11.
[23] [13, Nonsingular Points are Open and Dense].

Theorem 19.6.33: Perfect Base Fields Give Separating Transcendence Bases

Let k be a perfect field and let $K = k(a_1, \ldots, a_n)$ be a finitely generated field extension. Then some subset of $\{a_1, \ldots, a_n\}$ is a separating transcendence basis of K over k. In particular every finitely generated extension of a perfect field is separably generated.

***Proof*:**
If $\mathrm{char} k = 0$ every algebraic extension is separable (corollary 19.6.8), so any transcendence basis extracted from the generators by theorem 19.2.13 is separating. Assume $\mathrm{char} k = p > 0$ and induct on n, the case $n = 0$ being trivial.

Step 1: dispose of the independent case. If $a_1, \ldots, a_n$ are algebraically independent over k they form a transcendence basis and $K = k(a_1, \ldots, a_n)$ is separable over itself, so the basis is separating. Otherwise there is a nonzero $f \in k[X_1, \ldots, X_n]$ with $f(a_1, \ldots, a_n) = 0$, and we may take f irreducible, replacing it by an irreducible factor that still vanishes.

Step 2: perfectness forces a nonzero partial derivative. Suppose every X_i occurred in f only through p-th powers, so that $f = \sum_\alpha c_\alpha X^{p\alpha}$. Since k is perfect, every c_α is a p-th power, say $c_\alpha = d_\alpha^p$, and then

$$f = \sum_\alpha d_\alpha^p X^{p\alpha} = \Big(\sum_\alpha d_\alpha X^\alpha\Big)^p$$

using that raising to the p-th power is a ring homomorphism in characteristic p (proposition 19.6.11). That contradicts irreducibility of f. So some variable occurs in f outside a p-th power, which is to say $\partial f/\partial X_i \neq 0$ for some i. Fix such an i.

Step 3: the i-th generator is separable over the others. Put $F = k(a_1, \ldots, \widehat{a_i}, \ldots, a_n)$, the subfield generated by the remaining generators. Viewing f as a polynomial in X_i with coefficients in $k[X_1, \ldots, \widehat{X_i}, \ldots, X_n]$, it is nonconstant in X_i (otherwise $\partial f/\partial X_i = 0$) and irreducible, so up to a unit it is the minimal polynomial of a_i over F. Its derivative in X_i is nonzero and of smaller degree, hence not divisible by the minimal polynomial, so the minimal polynomial has no repeated root by proposition 19.6.6. Thus a_i is separable algebraic over F, and $K = F(a_i)$ is a finite separable extension of F.

Step 4: induct. The field F is generated over k by $n-1$ elements, so by induction some subset B of $\{a_1, \ldots, \widehat{a_i}, \ldots, a_n\}$ is a separating transcendence basis of F/k. Then K is algebraic over F, which is algebraic over $k(B)$, so K is algebraic over $k(B)$ and B is a transcendence basis of K/k. Separability passes up the tower $k(B) \subseteq F \subseteq K$ by proposition 19.6.18, both steps being separable, so $K/k(B)$ is separable and B is separating, completing the proof.

Over an imperfect field the theorem fails. Let k have characteristic p, let $t \in k$ not be a p-th power, let x be transcendental over k, and let $K = k(x, u)$ with $u^p = t$, so that $\mathrm{trdeg} K/k = 1$. The element t is not a p-th power in $k(x)$ either (compare leading coefficients in $tg^p = f^p$), so u has minimal polynomial $U^p - t$ over $k(x)$, and the differential of that polynomial is $pU^{p-1}\,dU - dt = 0$, because $p = 0$ in K and $t \in k$. So the relation $u^p = t$ imposes nothing on $\Omega_{K/k}$, in which dx and du are linearly independent, and $\dim_K \Omega_{K/k} = 2 > \mathrm{trdeg} K/k$. By the computation of $\Omega_{K/k}$ in section 21.3,

the extension K/k is not separably generated.

Exercise 19.6.3

1. Show that if f, g are polynomials of degree n, m respectively then
$$(x^{m-1}f(x)) \wedge (x^{m-2}f(x)) \wedge \cdots \wedge f(x) \wedge (x^{n-1}g(x) \wedge \cdots \wedge g(x) = \mathrm{Res}(f,g)x^{n+m-1} \wedge x^{n+m-2} \wedge \cdots \wedge 1$$

2. Let $f, g \in R[x]$ have nonzero leading coefficients. Show that $\mathrm{Res}(f,g) = 0$ iff f, g have a common factor of positive degree in $\mathrm{Frac}(R)[x]$.
3. Show that $\mathrm{Res}(f(x+a), g(x+a)) = \mathrm{Res}(f(x), g(x))$ for $a \in R$.
4. Show that $\Delta(fg) = \Delta(f)\Delta(g)\mathrm{Res}(f,g)^2$.
5. Let $f(x) = ax^2 + bx + c$. Show that $\Delta(f) = b^2 - 4ac$.

19.7 Application: Cyclotomic Extensions and Finite Fields

In this section, we use the tools given to us to gain some important examples of field extensions and analyse the corresponding $\mathrm{Aut}_k(F)$, and generalize theorem 19.6.20 to show finite separable extensions of finite fields are in fact simple.

We start by using the tools that were developed to study the important class of polynomials of the form $x^n - 1$. Such extensions will be called *Cyclotomic extensions*. These polynomials represent the "torsion units" and shall show up everywhere when considering solutions to equations as they often add the necessary "symmetry" to find all the solutions to an algebraic equation. They are also important for the continuation of Field Theory to Kummer Theory, which is the study of the case where $\mathrm{Aut}_k(F)$ is an abelian group, and they form an important first step towards Fermat's Last theorem through their application to solutions of Elliptic curves[24].

After having classified Cyclotomic extensions, we shall finish the section with the study of extensions of finite fields. As it turns out, all finite extensions will be splitting fields of polynomials of the form $x(x^{p^d} - 1)$, meaning they will have a very simple structure and automorphism group.

19.7.1 Cyclotomic Polynomials and Fields

We start off with some reminders:

[24] if $\mathrm{ch}(F) \notin 2, 3$, then an elliptic curve is a polynomial of the form $y^2 = x^3 + ax + b$, $a, b \in F$. A more technical definition is given when $\mathrm{ch}(F) \in \{2, 3\}$ that would be presented in a course on elliptic curves

Definition 19.7.1: Roots Of Unity Reminder

We will denote $\zeta_n = e^{\frac{2\pi i}{n}}$, and the cyclic subgroup they generated to be μ_n. Note that:

$$\zeta_n^n = e^{2\pi i} = 1$$

If $\langle \zeta_n^k \rangle = \mu_n$, then this element is called a *primitive root of unity.*


The element ζ_n is always a root of $x^n - 1$, and each ζ_n^k, $1 \leq k \leq n$ where $\gcd(n, k) = 1$ consist of the rest of the roots of $x^n - 1$, for

$$(\zeta_n^k)^n = 1$$

and if $\gcd(n, k) = \ell$, then:

$$(\zeta_n^k)^\ell = 1$$

It is an easy mistake to think that $\zeta_2 = i$, however $\zeta_2 = -1$ and $\zeta_4 = i$. These elements always form a group under multiplication, which we labeled μ_n. This group always lies on the unit circle, for example:



If you know about the euler representation of complex numbers:

$$re^{i\theta} = r(\cos(\theta) + i\sin(\theta))$$

Then $e^{\frac{2\pi i}{n}} = \zeta_n = \cos(2\pi/n) + i\sin(2\pi/n)$. Other identities we get are:

1. $\zeta_3 = \frac{-1+i\sqrt{3}}{2}$
2. $\zeta_5 = \frac{\sqrt{5}-1}{4} + \frac{\sqrt{10+2\sqrt{5}}}{4}i$
3. $\zeta_6 = \frac{1+i\sqrt{3}}{2}$ (to not be confused with ζ_3)

4. $\zeta_8 = \frac{\sqrt{2}}{2} + i\frac{\sqrt{2}}{2}$

These can be deduced using the results from section 19.4. In paticular Gauss proved that primitive nth roots of unity ζ_n can be constructed using the square-roots, additions, subtraction, multiplication, and division of rational numbers, which we saw implies that n is a power of two, or in our case we would require that n is the product of two discint *fermat primes*.

Every root of unity of a root of $x^n - 1$ for some n, however this polynomial is not irreducible, namely $x^n - 1 = (x-1)p(x)$. The polynomial $p(x)$ will turn out to be irreducible, and hence is given a name:

Definition 19.7.2: Cyclotomic Polynomials

Let:

$$\Phi_n(x) = \prod_{\zeta \text{ primitive } n\text{th root of } 1} (x - \zeta) = \prod_{\substack{1 \leq m \leq n \\ \gcd(m,n)=1}} (x - \zeta_n^m)$$

Then the resulting polynomial is called the *nth cyclotomic polynomial*

As we have seen in the section on number theory (section 0.2), there are $\varphi(n)$ primitive roots of 1, where φ is Euler's totient function. The term cyclotomic comes from the greek *cyclo* (circle) and *tomos* (divide), owing to how the roots of unity divide the circle into regular sections. Though not obvious, this polynomial has rational coefficients and is irreducible over $\mathbb{Q}$ (which we will show).

Example 19.7.3: Cyclotomic Polynomials

In the case of $n = p$ is a prime, it is simple to see it's irreducible. Every non-identity element of μ_p is a generator, i.e. every pth root of 1 is primitive except 1. In fact, 1 is a root of $x^p - 1$ ($1^p - 1 = 0$), and so we get:

$$\Phi_p(x) = \frac{x^p - 1}{x - 1} = x^{p-1} + x^{p-2} + \cdots + x + 1$$

which is irreducible over $\mathbb{Q}$ using Eisenstein's trick along with shifting (noting that p divides $\binom{n}{k}$). Furthermore, $\mu_p = C_p = \mathbb{Z}/p\mathbb{Z}$.

Aside: for those who know Taylor series and the exponential function, notice how close $\Phi_p(x)$ resembles the pariatal sum for the taylor expansion of e^x:

$$1 + x + \frac{x^2}{2} + \frac{x^3}{3!} + \cdots + \frac{x^p}{p!}$$

the main difference being the coefficient of the partial taylor expansion of e^x being $1/n!$. This reflects on the "rotation" nature of e^x, as well as it's link to roots of unity. However, note that e^x has no roots (even when expended to $\mathbb{C}$, since $e^z \cdot e^{-z} = 1$). Hence, though the partial expansion may have root, even roots that resemble the roots of unity, taylor expansion, the "infinite polynomial representation" need not have roots!

For ease of reference, we record what happens when n is not prime:

Lemma 19.7.4: Cyclotomic Polynomial divisor Representation

For all $n > 0$,

$$x^n - 1 = \prod_{1 \leq d \mid n} \Phi_d(x)$$

***Proof*:**
For all ζ_n^k, $0 \leq k \leq n-1$, $(\zeta_n^k) - 1 = 0$. Hence, $x^n - 1$ splits into products

$$x^n - 1 = \prod_{k}^{n} (x - \zeta_k)$$

If $n = dk$ then $1 = \zeta_n^n = (\zeta_n^d)^k$, hence every dth root of unity is an nth root of unity. In particular, every primitive dth root of unity is an nth root of unity. Conversely, if $\zeta_n^d \in \mu_n$, then ζ_n^d forms cyclic subgroup, say μ_d where d is a divisor of n. But then ζ_n^d is a primitive dth root of unity for some divisor d. This establishes:

$$x^n - 1 = \prod_{1 \leq d \mid n} \left(\prod_{\substack{\zeta \text{ primitive} \\ d\text{th root of } 1}} (x - \zeta) \right) = \prod_{1 \leq d \mid n} \Phi_d(x)$$

as we sought to show.

Corollary 19.7.5: Integer Coefficients

The cyclotomic polynomials $\Phi_n(x)$ have integer coefficients

***Proof*:**
This is a proof by [strong] induction. The case of $\Phi_1(x) = x - 1$ is immediate, so assume that for $m < n$, Φ_m is a monic polynomial with integer coefficients. Then:

$$f(x) = \prod_{\substack{1 \leq d \mid n \\ d < n}} \Phi_d(x)$$

is a monic polynomial with degree $< n$. Since $f(x), x^n - 1 \in \mathbb{Z}[x]$ are two monic polynomials with integer ceofficients, we may use the euclidean algorithm to find $q(x), r(x) \in \mathbb{Z}[x]$, $\deg(r(x)) < \deg(f(x))$ or $r(x) = 0$ where

$$x^n - 1 = f(x)q(x) + r(x)$$

Then by lemma 19.7.4 we have

$$x^n - 1 = f(x)\Phi_n(x)$$

Hence, we get

$$f(x)(q(x) - \Phi_n(x)) = r(x)$$

But that implies $\deg(r(x)) > \deg(f(x))$, a contradiction. Thus $r(x) = 0$, giving us $f(x)q(x) = f(x)\Phi_n(x)$, which implies $\Phi_n(x) = q(x) \in \mathbb{Z}[x]$, as we sought to show.

Example 19.7.6: Cyclotomic Polynomial

1. Let $p(x) = x^4 - 1 = \Phi_1(x)\Phi_2(x)\Phi_4(x)$. Then:
$$\Phi_4(x) = \frac{x^4 - 1}{x^2 - 1} = x^2 + 1$$
2. Let $p(x) = x^6 - 1 = \Phi_1(x)\Phi_2(x)\Phi_3(x)\Phi_6(x)$. Then:
$$\Phi_6(x) = \frac{x^6 - 1}{(x^2 - 1)(x^2 + x + 1)} = x^2 - x + 1$$
3. Let $p(x) = x^{12} - 1 = \Phi_1(x)\Phi_2(x)\Phi_3(x)\Phi_4(x)\Phi_6(x)\Phi_{12}(x)$. Then:
$$\Phi_{12}(x) = \frac{x^{12} - 1}{(x^6 - 1)(x^2 + 1)} = x^4 - x^2 + 1$$

It might seem that all the coefficients are 0 or ± 1. However, the first counter-example to this problem is when $n = 105$, and in general the coefficients can be as large as we might want

Proposition 19.7.7: Irreducibility Of Cyclotomic Polynomials

For all $n \in \mathbb{N}_{>0}$, $\Phi_n(x) \in \mathbb{Z}[x]$ is irreducible over $\mathbb{Q}$

Note that since $\Phi_n(x)$ is monic, by Gauss's lemma, irreducibility in $\mathbb{Q}[x]$ is equivalen to ireducibility in $\mathbb{Z}[x]$.

***Proof*:**
Suppose Φ_n were reducible over $\mathbb{Q}$, say $\Phi_n = AB$ with $A, B \in \mathbb{Q}[x]$ nonconstant. By Gauss's Lemma (proposition 11.2.1) we may replace A and B by rational multiples $f, g \in \mathbb{Z}[x]$ with $\Phi_n = fg$. Comparing leading coefficients, the product of the leading coefficients of f and g is 1, so both are ± 1, and changing the sign of both if necessary we may take f and g monic. Shrinking f to one of its monic irreducible factors in $\mathbb{Z}[x]$ and absorbing the rest into g, we may assume in addition that f is irreducible, and it is then irreducible in $\mathbb{Q}[x]$ by corollary 11.2.2.

A root of f and a prime moving it onto g. By definition 19.7.2 the roots of Φ_n are the primitive nth roots of unity, each occurring once, and each is a root of f or of g. Fix a root ζ of f. Every primitive nth root of unity is then a power ζ^m with $\gcd(m, n) = 1$, so choose a root of g and write it as ζ^m with $1 \le m \le n$ and $\gcd(m, n) = 1$. Factor $m = p_1 p_2 \cdots p_r$ into primes, none of which divides n. Along the chain
$$\zeta, \quad \zeta^{p_1}, \quad \zeta^{p_1 p_2}, \quad \ldots, \quad \zeta^{p_1 p_2 \cdots p_r} = \zeta^m$$
every entry is again a primitive nth root of unity, hence a root of f or of g. The first entry is a root of f and the last is a root of g, so for some i the element $\xi = \zeta^{p_1 \cdots p_{i-1}}$ is a root of f while ξ^p is not, where $p = p_i$. Then ξ^p is a root of g, and p does not divide n.

Reduction modulo p. Since f is monic and irreducible in $\mathbb{Q}[x]$ with $f(\xi) = 0$, it is the minimal

polynomial of ξ over $\mathbb{Q}$. From $g(\xi^p) = 0$ we get that ξ is a root of $g(x^p)$, so f divides $g(x^p)$ in $\mathbb{Q}[x]$. Dividing $g(x^p)$ by the monic f inside $\mathbb{Z}[x]$ produces an integer quotient and remainder, and these agree with the quotient and remainder over $\mathbb{Q}$, so the remainder is 0 and

$$g(x^p) = f(x)h(x) \qquad h \in \mathbb{Z}[x]$$

Reduce coefficients modulo p and write $\overline{u}$ for the image of $u \in \mathbb{Z}[x]$ in $\mathbb{F}_p[x]$. The map $u \mapsto u^p$ on $\mathbb{F}_p[x]$ is a ring homomorphism, since $p = 0$ in $\mathbb{F}_p[x]$ and p divides $\binom{p}{i}$ for $0 < i < p$, and it fixes every $c \in \mathbb{F}_p$, since $\mathbb{F}_p^\times$ has order $p-1$ and theorem 3.3.1 gives $c^{p-1} = 1$ for $c \neq 0$. Applying it to $\overline{g}$ therefore gives $\overline{g}(x)^p = \overline{g}(x^p)$, so

$$\overline{g}(x)^p = \overline{f}(x)\overline{h}(x)$$

Both f and g are monic, so $\overline{f}$ and $\overline{g}$ are nonconstant. Let $q \in \mathbb{F}_p[x]$ be an irreducible factor of $\overline{f}$. Then q divides $\overline{g}^p$, and q is prime in the Unique Factorization Domain $\mathbb{F}_p[x]$, so q divides $\overline{g}$. Hence

$$q^2 \big| \overline{f}\ \overline{g} = \overline{\Phi_n}$$

The contradiction. By lemma 19.7.4, Φ_n divides $x^n - 1$ in $\mathbb{Z}[x]$, so q^2 divides $x^n - 1$ in $\mathbb{F}_p[x]$. Write $x^n - 1 = q^2 s$ and differentiate:

$$nx^{n-1} = 2qq's + q^2 s' = q\left(2q's + qs'\right)$$

so q divides nx^{n-1}. Since p does not divide n, the element n is a unit of $\mathbb{F}_p$, so q divides x^{n-1}, and since x is irreducible and $\mathbb{F}_p[x]$ is a Unique Factorization Domain, q is an associate of x. But x does not divide $x^n - 1$, whose constant term is -1. This contradiction shows Φ_n is irreducible over $\mathbb{Q}$.

Definition 19.7.8: Cyclotomic Field

The splitting field $\mathbb{Q}(\zeta_n)$ for the polynomial $x^n - 1$ over $\mathbb{Q}$ is the nth *cyclotomic field*

Proposition 19.7.9: Cyclotomic Field Automorphism

Let $n \geq 1$ and let φ be the Euler totient (definition 1.2.4). Then:

1. $[\mathbb{Q}(\zeta_n) : \mathbb{Q}] = \varphi(n)$
2. for $m \in \mathbb{Z}$, there is an automorphism $\sigma \in \mathrm{Aut}_{\mathbb{Q}}(\mathbb{Q}(\zeta_n))$ with $\sigma(\zeta_n) = \zeta_n^m$ if and only if $\gcd(m, n) = 1$, and it is then unique, denoted σ_m
3. the map
$$j \colon (\mathbb{Z}/n\mathbb{Z})^\times \to \mathrm{Aut}_{\mathbb{Q}}(\mathbb{Q}(\zeta_n)) \qquad [m]_n \mapsto \sigma_m$$
is an isomorphism of groups, where $(\mathbb{Z}/n\mathbb{Z})^\times$ is the group of definition 1.2.5, whose elements are the classes $[m]_n$ of the integers m with $\gcd(m, n) = 1$

In particular,
$$\mathrm{Aut}_{\mathbb{Q}}(\mathbb{Q}(\zeta_n)) \cong (\mathbb{Z}/n\mathbb{Z})^\times$$

***Proof*:**

The number $\zeta_n = e^{2\pi i/n}$ has multiplicative order n, since $e^{2\pi ix} = \cos(2\pi x) + i\sin(2\pi x)$ equals 1 exactly when x is an integer. So $\zeta_n^a = 1$ exactly when $n \mid a$, and $\mu_n = \langle \zeta_n \rangle$ is cyclic of order n (definition 19.7.1). If $m \equiv r \bmod n$, then $\zeta_n^m = \zeta_n^r$, and $\gcd(m, n) = \gcd(r, n)$, since a common divisor of n and one of m, r divides the other.

1. The polynomial Φ_n is monic with integer coefficients (corollary 19.7.5), it is irreducible over $\mathbb{Q}$ (proposition 19.7.7), and $\zeta_n = \zeta_n^1$ is one of its roots (definition 19.7.2). By theorem 19.2.8, $\mathbb{Q}(\zeta_n) \cong \mathbb{Q}[x]/(p)$, where p is a nonconstant polynomial generating the kernel of evaluation at ζ_n. As Φ_n lies in that kernel, p divides Φ_n, and the irreducibility of Φ_n makes the quotient a nonzero constant. So $[\mathbb{Q}(\zeta_n) : \mathbb{Q}] = \deg p = \deg \Phi_n$ (theorem 19.2.5), and $\deg \Phi_n = \varphi(n)$, since Φ_n is the product of the $\varphi(n)$ linear factors $x - \zeta_n^m$ with $1 \leq m \leq n$ and $\gcd(m, n) = 1$.
2. Uniqueness: every element of $\mathbb{Q}(\zeta_n)$ is a polynomial in ζ_n with rational coefficients (corollary 19.2.23), and a $\mathbb{Q}$-automorphism preserves sums and products and fixes $\mathbb{Q}$, so it is determined by its value at ζ_n.

   Suppose $\gcd(m, n) = 1$, and let $1 \leq r \leq n$ with $r \equiv m \bmod n$. Then $\zeta_n^m = \zeta_n^r$ with $\gcd(r, n) = 1$ is a root of Φ_n. By theorem 19.2.27, applied to the identity of $\mathbb{Q}$, the irreducible polynomial Φ_n and its roots ζ_n and ζ_n^m, there is an isomorphism $\sigma \colon \mathbb{Q}(\zeta_n) \to \mathbb{Q}(\zeta_n^m)$ fixing $\mathbb{Q}$ with $\sigma(\zeta_n) = \zeta_n^m$. As ζ_n^m generates the cyclic group μ_n of order n (theorem 2.3.11(3), using $\gcd(m, n) = 1$), ζ_n is a power of ζ_n^m, so $\mathbb{Q}(\zeta_n^m) = \mathbb{Q}(\zeta_n)$ and $\sigma \in \mathrm{Aut}_{\mathbb{Q}}(\mathbb{Q}(\zeta_n))$.

   Conversely, let $\sigma \in \mathrm{Aut}_{\mathbb{Q}}(\mathbb{Q}(\zeta_n))$ satisfy $\sigma(\zeta_n) = \zeta_n^m$. Since σ fixes the rational coefficients of Φ_n, $\Phi_n(\zeta_n^m) = \sigma(\Phi_n(\zeta_n)) = 0$. The roots of Φ_n are the ζ_n^r with $1 \leq r \leq n$ and $\gcd(r, n) = 1$, so $\zeta_n^m = \zeta_n^r$ for such an r. Then $n \mid m - r$, and $\gcd(m, n) = \gcd(r, n) = 1$.
3. If $[m]_n = [m']_n$ with $\gcd(m, n) = 1$, then $\gcd(m', n) = 1$ and $\zeta_n^{m'} = \zeta_n^m$, so $\sigma_{m'} = \sigma_m$ by uniqueness, and j is well defined. For classes $[m]_n$ and $[m']_n$ in $(\mathbb{Z}/n\mathbb{Z})^\times$, the automorphism

$\sigma_m \circ \sigma_{m'}$ sends ζ_n to $\sigma_m(\zeta_n)^{m'} = \zeta_n^{mm'}$, so $\gcd(mm', n) = 1$ by (2), and $\sigma_m \circ \sigma_{m'} = \sigma_{mm'}$ by uniqueness. So $j([m]_n[m']_n) = j([m]_n) \circ j([m']_n)$, and j is a homomorphism from the group $(\mathbb{Z}/n\mathbb{Z})^\times$ (definition 1.2.5) to $\mathrm{Aut}_{\mathbb{Q}}(\mathbb{Q}(\zeta_n))$. The map j is injective: if $\sigma_m = \mathrm{id}$, then $\zeta_n^m = \zeta_n$, so $n|m-1$ and $[m]_n = [1]_n$. It is surjective: by (2), every $\sigma \in \mathrm{Aut}_{\mathbb{Q}}(\mathbb{Q}(\zeta_n))$ sends ζ_n to some ζ_n^r with $\gcd(r, n) = 1$, and then $\sigma = \sigma_r = j([r]_n)$ by uniqueness. Hence j is a bijective homomorphism of groups, that is, an isomorphism. In particular $|\mathrm{Aut}_{\mathbb{Q}}(\mathbb{Q}(\zeta_n))| = \varphi(n) = [\mathbb{Q}(\zeta_n) : \mathbb{Q}]$, since $(\mathbb{Z}/n\mathbb{Z})^\times$ has $\varphi(n)$ elements (definition 1.2.5), completing the proof.

19.7.2 Finite Fields

Let F be a finite field of characteristic p. Then as we remarked under definition 19.1.8,

$$F/\mathbb{F}_p$$

where $\mathbb{F}_p = \mathbb{Z}/p\mathbb{Z}$. Since F is finite, let $d = [F : \mathbb{F}_p]$. Since F is a d-dimensional vector-space over $\mathbb{F}_p$, $F \cong_{\mathbf{Vect}} \mathbb{F}_p^d$, hence the order of $|F|$ is a power of p: $|F| = p^d$.

With everything we have learned, we can now classify all finite fields. Interestingly, we get essentially the best possible result we might ask for when classifying objects: for every order p^d, we get a unique field up to isomorphism:

Theorem 19.7.10: Classifying Finite Fields

Let $q = p^d$ be a power of the prime number p. Then the polynomial $x^q - x$ is separable over $\mathbb{F}_p$, and the splitting field of the polynomial $x^q - x$ over $\mathbb{F}_p$ is a field with exactly q elements. Conversely, let F be a field with exactly q elements. Then F is a splitting field for $x^q - x$ over $\mathbb{F}_p$

Hence, all finite extension of finite fields is abelian, and even better cyclic.

***Proof*:**
Let F be the splitting field of $x^q - x$ over $\mathbb{F}_p$. Then necessarily F is finite, and hence it's perfect by corollary 19.6.12, and hence it's a separable extension, meaning F contains q distinct roots of $x^q - x$. We need to show that every element of F is a root (i.e. $|F| = q$). Let R be the set of roots of $x^q - x$ from F. Then I claim that R is a field. Since F is the smallest field containing all the roots, it follows that $R = F$.

We simply need to show it's a subring, and since all nonzero elements are units, it is a field. For any $a, b \in R$, since $a^q - a = 0$, $b^q - b = 0$, then $a^q = a$ and $b^q = b$. Then using the binomial theorem and the characteristic of F, we get:

$$(a-b)^q = a^q + (-1)^q b^q = a - b$$

where $(-1)^q = -1$ if p is odd, and $(-1)^q = 1 = -1$ if $p = 2$. Furthermore, if $b \neq 0$, then:

$$(ab^{-1})^q = a^q (b^q)^{-1} = ab^{-1}$$

showing that R is closed under both operations, hence it is a subfield, hence $R = F$

On the other hand, let F be a field with q elements. Then $|F^\times| = q - 1$, and so by Lagrange

Theorem, for any $0 \neq a \in F^\times$, $|a| \big| q-1$ Thus:

$$a \neq 0 \Rightarrow a^{q-1} = 1 \Rightarrow a^q - a = 0$$

showing that a *must* be a root of $x^q - x$. Furthermore, $0^q - 0 = 0$, showing that $x^q - x$ has q roots in F (i.e. all elements of F). But then, F is the splitting field of $x^q - x$ by the previous logic, as we sought to show.

Corollary 19.7.11: Unique Finite Field For Every Order

For every $q = p^d$, p a prime and $d \in \mathbb{N}_{>0}$, there exists a unique field of order q

***Proof*:**
this follows from theorem 19.7.10 and the uniqueness of the splitting field (theorem 19.5.10)

Definition 19.7.12: Galois Field

Let F be a field of order $q = p^d$. Then F is called the *Galois Field* of order q, and we usually denote it as $\mathbb{F}_q$ or $\mathbb{F}_{p^d}$.

Example 19.7.13: Galois Fields

The polynomial x^4+1 is reducible over *any* field $\mathbb{F}_p$, and hence over any finite field F of characteristic p, which contains $\mathbb{F}_p$ as its prime subfield. When $p = 2$, the binomial coefficients 4, 6 and 4 are even, so $(x+1)^4 = x^4 + 4x^3 + 6x^2 + 4x + 1 = x^4 + 1$ in $\mathbb{F}_2[x]$.

Let p be odd. Every odd integer $2k+1$ satisfies $(2k+1)^2 - 1 = 4k(k+1)$, and $k(k+1)$ is even, so 8 divides $p^2 - 1$. Write $p^2 - 1 = 8s$. In $\mathbb{F}_p[x]$,

$$x^8 - 1 = (x^4 - 1)(x^4 + 1) \qquad x^{p^2-1} - 1 = (x^8)^s - 1 = (x^8 - 1)\sum_{l=0}^{s-1} x^{8l} \qquad x^{p^2} - x = x(x^{p^2-1} - 1)$$

so $x^4 + 1$ divides $x^8 - 1$, which divides $x^{p^2-1} - 1$, which divides $x^{p^2} - x$. Let E be the splitting field of $x^{p^2} - x$ over $\mathbb{F}_p$. It has p^2 elements (theorem 19.7.10), so $[E : \mathbb{F}_p] = 2$, and $x^{p^2} - x$ is a product of linear factors $x - e$ in $E[x]$. A monic irreducible factor q of $x^4 + 1$ in $E[x]$ is prime in the principal ideal domain $E[x]$ (corollary 11.1.2, proposition 10.1.33) and divides the product of these linear factors, so it divides one of them and $q = x - \alpha$ for some $\alpha \in E$. Thus α is a root of $x^4 + 1$ in E, and

$$\mathbb{F}_p \subseteq \mathbb{F}_p(\alpha) \subseteq E$$

so $[\mathbb{F}_p(\alpha) : \mathbb{F}_p]$ divides $[E : \mathbb{F}_p] = 2$ (corollary 19.3.8). The minimal polynomial of α over $\mathbb{F}_p$ therefore has degree 1 or 2 (theorem 19.2.8, theorem 19.2.5), and it divides x^4+1, since it generates the kernel of evaluation at α. Hence $x^4 + 1$ is a product of two nonconstant polynomials in $\mathbb{F}_p[x]$, so it is reducible over $\mathbb{F}_p$, and the same factorization shows that it is reducible over every field containing $\mathbb{F}_p$.

Corollary 19.7.14: Finite Field Extensions

Let p be a prime and let $d \leq e$ be positive integers. Then there is an extension $\mathbb{F}_{p^d} \subseteq \mathbb{F}_{p^e}$ if and only if $d|e$. If $d|e$, then there is exactly one such extension, in the sense that $\mathbb{F}_{p^e}$ contains a unique copy of $\mathbb{F}_{p^d}$.

Furthermore, all extensions $\mathbb{F}_{p^d} \subseteq \mathbb{F}_{p^e}$ are simple

***Proof*:**

If $\mathbb{F}_{p^d} \subseteq \mathbb{F}_{p^e}$, then $\mathbb{F}_{p^e}$ is a vector space of some dimension r over $\mathbb{F}_{p^d}$, so $p^e = (p^d)^r$ and $d|e$.

Conversely, let $e = dr$. Then $p^e - 1 = (p^d - 1)\sum_{j=0}^{r-1} p^{dj}$, so $p^e - 1 = (p^d - 1)s$ for some integer s, and

$$x^{p^e} - x = x(x^{p^e-1} - 1) = x(x^{p^d-1} - 1)\sum_{j=0}^{s-1} x^{(p^d-1)j} = (x^{p^d} - x)\sum_{j=0}^{s-1} x^{(p^d-1)j}$$

Every $a \in \mathbb{F}_{p^e}^\times$ has $a^{p^e-1} = 1$ (theorem 3.3.1), so the p^e elements of $\mathbb{F}_{p^e}$ are p^e distinct roots of $x^{p^e} - x$, which therefore splits over $\mathbb{F}_{p^e}$ with distinct roots. By unique factorization in $\mathbb{F}_{p^e}[x]$, so does its divisor $x^{p^d} - x$, and its set K of roots has p^d elements. Since $a \mapsto a^{p^d}$ is a ring homomorphism (a power of the Frobenius homomorphism $a \mapsto a^p$ of definition 19.6.9, which preserves sums because $p = 0$ in $\mathbb{F}_{p^e}$ and p divides $\binom{p}{i}$ for $0 < i < p$), K is closed under sums and products, and it contains 0, 1 and the inverse of each of its nonzero elements, so K is a subfield with p^d elements, a copy of $\mathbb{F}_{p^d}$ (corollary 19.7.11). A subfield L with p^d elements satisfies $a^{p^d} = a$ for all $a \in L$, again by theorem 3.3.1, so $L \subseteq K$, and $L = K$ as both have p^d elements.

Finally, the multiplicative group of $\mathbb{F}_{p^e}$ is cyclic (theorem 11.3.14), generated by some α. Every nonzero element of $\mathbb{F}_{p^e}$ is a power of α, so $\mathbb{F}_{p^e} = \mathbb{F}_{p^d}(\alpha)$ and the extension is simple.

Corollary 19.7.15: Separable Finite Extensions Of Finite Fields

Let k be a finite field and F/k a finite separable extension. Then F is a simple extension.

***Proof*:**

Most of the proof of this was already done by proposition 19.6.19. If k is a finite field, then so is F, and the extensions are automatically simple by corollary 19.7.14.

Using these results, we can be more gain a lot of information about polynomials over finite fields:

Corollary 19.7.16: Finite Fields And Irreducible Polynomials

Let F be a finite field. Then for all integers $n \geq 1$, there exists irreducible polynomials of degree n in $F[x]$

***Proof*:**
Let $n \geq 1$ and $F = \mathbb{F}_{p^d}$. Then

$$\mathbb{F}_{p^d} \subseteq \mathbb{F}_{p^{dn}}$$

is a finite simple extension, say $\mathbb{F}_{p^{dn}} = \mathbb{F}_{p^d}(\alpha)$. Then sine

$$[\mathbb{F}_{p^{dn}} : \mathbb{F}_{p^d}] = n$$

and α has a minimal polynomial over $\mathbb{F}_{p^d} = F$, we see that we can find an irreducible polynomial of degree n in $F[x]$.

Note how this proof does not necessarily generalize for infinite fields, since we do not have so much control over the degree of the extension (worth pondering over).

Corollary 19.7.17: Factorizing $x^{q^n} - x$

Let $F = \mathbb{F}_q$ be a finite field and $n \geq 1$. Then $x^{q^n} - x$ is the product of all the monic irreducible polynomials in $F[x]$ whose degree divides n.

***Proof*:**
Let p be the characteristic of F, so q is a power of p, and let $N = x^{q^n} - x$. It is separable (theorem 19.7.10, as q^n is a power of p), so it is the product of its distinct monic irreducible factors in $F[x]$. Let $f \in F[x]$ be monic irreducible of degree d, and α a root of f in some extension of F (theorem 19.2.2). Then $F(\alpha) \cong F[x]/(f)$ has q^d elements (theorem 19.2.8), so $\alpha^{q^d} = \alpha$ (theorem 3.3.1 in $F(\alpha)^\times$ when $\alpha \neq 0$, and trivially when $\alpha = 0$). If $d|n$, iterating gives $\alpha^{q^n} = \alpha$, so f, the minimal polynomial of α, divides N. Conversely, suppose f divides N, and let L be a splitting field of N over $F(\alpha)$. As in the proof of corollary 19.7.14, the roots of N in L form a subfield K with q^n elements, since $a \mapsto a^{q^n}$ is a ring homomorphism. K contains α and F, whose elements satisfy $a^q = a$. So $F \subseteq F(\alpha) \subseteq K$ with $[K : F] = n$ and $[F(\alpha) : F] = d$, and $d|n$ (theorem 19.3.7).

Example 19.7.18: Factorizing Polynomials over Finite Fields
Over $\mathbb{F}_2$, multiplying out gives

$$x^2 - x = x(x+1) \qquad x^4 - x = x(x+1)(x^2+x+1) \qquad x^8 - x = x(x+1)(x^3+x+1)(x^3+x^2+1)$$

The quadratic and the two cubics have no root in $\mathbb{F}_2$, so they are irreducible (proposition 11.3.5). By corollary 19.7.17, $x^4 - x$ is the product of all monic irreducibles of degree 1 or 2, and $x^8 - x$ of all those of degree 1 or 3. So $x^2 + x + 1$ is the only irreducible quadratic over $\mathbb{F}_2$, and $x^3 + x + 1$ and $x^3 + x^2 + 1$ are the only irreducible cubics.

Another result that finiteness brings is that the structure of $\mathrm{Aut}_{\mathbb{F}_p}(\mathbb{F}_{p^d})$ is very simple. We already know that any finite field is perfect, hence all algebraic extensions are separable, and so

$$|\mathrm{Aut}_{\mathbb{F}_p}(\mathbb{F}_{p^d})| = d$$

However, we can say even more about the structure of the group

Proposition 19.7.19: Structure of Aut Of Finite Fields

Let $\mathbb{F}_{p^d}/\mathbb{F}_p$ be a field extension of degree d. Then $\mathrm{Aut}_{\mathbb{F}_p}(\mathbb{F}_{p^d})$ is cyclic, and generated by the Frobenius isomorphism.

***Proof*:**
Let $\varphi\colon \mathbb{F}_{p^d} \to \mathbb{F}_{p^d}$ be the Frobenius homomorphism $x \mapsto x^p$, a ring homomorphism because $p = 0$ in $\mathbb{F}_{p^d}$ and p divides $\binom{p}{i}$ for $0 < i < p$. It is injective, as a field homomorphism, hence surjective, as $\mathbb{F}_{p^d}$ is finite. It fixes $\mathbb{F}_p$: $0^p = 0$, and every $x \in \mathbb{F}_p^\times$ has $x^{p-1} = 1$ (theorem 3.3.1), so $x^p = x$. So $\varphi \in \mathrm{Aut}_{\mathbb{F}_p}(\mathbb{F}_{p^d})$, a group with at most d elements (corollary 19.2.29, as $\mathbb{F}_{p^d} = \mathbb{F}_p(\alpha)$ for a generator α of its multiplicative group, theorem 11.3.14). If $\varphi^e = \mathrm{id}$ with $e \geq 1$, then every element of $\mathbb{F}_{p^d}$ is a root of $x^{p^e} - x$, so $p^d \leq p^e$ (corollary 11.3.2) and $e \geq d$. Hence φ has order d, so it generates $\mathrm{Aut}_{\mathbb{F}_p}(\mathbb{F}_{p^d})$, which is therefore cyclic of order d.

This result is rather interesting: it means that given $(\mathbb{Z}/m\mathbb{Z})^*$ we have a natural relation p mod m associated to the Frobenius morphism $x \mapsto x^p$. This relation to prime being modded and the Frobenius homomorphism shall go far in algebraic number theory ([15]) and will fully be realized in class field theory (see [77]).

Every finite extension $\mathbb{F}_{q^r}/\mathbb{F}_q$ of a finite field has a cyclic automorphism group: $\mathrm{Aut}_{\mathbb{F}_q}(\mathbb{F}_{q^r})$ is a subgroup of $\mathrm{Aut}_{\mathbb{F}_p}(\mathbb{F}_{q^r})$, which is cyclic by proposition 19.7.19, and subgroups of cyclic groups are cyclic (theorem 2.3.11). Over $\mathbb{Q}$ this fails, but every finite *abelian* extension of $\mathbb{Q}$ lies in a cyclotomic field $\mathbb{Q}(\zeta_n)$. This is the Kronecker-Weber theorem, proved in theorem 50.5.4 and also a consequence of class field theory (*Class Field Theory* [77]).

Theorem 19.7.20: Wedderburn's Little Theorem

Every finite division ring is a field.

***Proof*:**
Let D be a finite division ring (definition 9.1.10), and let

$$Z = \{z \in D : zx = xz \text{ for all } x \in D\}$$

be its center. We show that $Z = D$.

Step 1: Z is a field, and $|D| = q^n$, where $q = |Z|$ and $n = \dim_Z D$. The set Z contains 0 and 1 and is closed under sums, negatives and products. If $0 \neq z \in Z$, then for every $x \in D$

$$z^{-1}x = z^{-1}(xz)z^{-1} = z^{-1}(zx)z^{-1} = xz^{-1}$$

so $z^{-1} \in Z$. Hence Z is a commutative division ring, that is, a field, and $q = |Z| \geq 2$. Multiplication on the left makes D a vector space over Z, of finite dimension n because D is finite. A basis $v_1, \ldots, v_n$ (theorem 13.1.8) writes every element of D uniquely as $c_1v_1 + \cdots + c_nv_n$ with $c_i \in Z$, so $|D| = q^n$. The same count gives $|V| = q^{\dim_Z V}$ for every Z-subspace V of D.

Step 2: centralizers. For $x \in D$ put $C(x) = \{y \in D : xy = yx\}$. It contains Z and is closed under sums and products, so it is a Z-subspace of D, and $|C(x)| = q^{d(x)}$ with $d(x) = \dim_Z C(x)$ by Step 1. If $0 \neq y \in C(x)$, then $y^{-1}x = y^{-1}(xy)y^{-1} = y^{-1}(yx)y^{-1} = xy^{-1}$, so $y^{-1} \in C(x)$. Hence, for $x \neq 0$, the centralizer of x in the group $D^\times$ (definition 2.2.7) is $C(x) \setminus \{0\}$, of order

$q^{d(x)}-1$, and by theorem 3.3.1 the number $q^{d(x)}-1$ divides $|D^\times| = q^n - 1$. This forces $d(x)\big|n$. Write $n = a\,d(x) + r$ with $0 \le r < d(x)$, where $a \ge 1$ since $d(x) \le n$. Then

$$q^n - 1 = q^r\big(q^{a\,d(x)} - 1\big) + \big(q^r - 1\big)$$

and $q^{d(x)}-1$ divides $q^{a\,d(x)} - 1 = \big(q^{d(x)} - 1\big)\big(q^{(a-1)d(x)} + \cdots + q^{d(x)} + 1\big)$, so it divides $q^r - 1$. Since $0 \le q^r - 1 < q^{d(x)} - 1$, this gives $q^r = 1$, so $r = 0$.

Step 3: the class equation. The center of the group $D^\times$ is $Z \setminus \{0\}$, since an element of $D^\times$ commuting with every element of $D^\times$ also commutes with 0. Let $x_1, \ldots, x_k$ represent the conjugacy classes of $D^\times$ not contained in its center, and put $d_i = d(x_i)$. Each x_i lies outside Z, so $C(x_i) \ne D$ and $d_i < n$, and $d_i\big|n$ by Step 2. Theorem 4.6.3 gives

$$q^n - 1 = (q-1) + \sum_{i=1}^{k} \frac{q^n - 1}{q^{d_i} - 1}$$

Step 4: a cyclotomic divisibility. Suppose $n > 1$, and write t for the polynomial variable. By lemma 19.7.4,

$$t^n - 1 = \Phi_n(t) \prod_{\substack{1 \le e \big| n \\ e < n}} \Phi_e(t)$$

and every factor has integer coefficients by corollary 19.7.5. Substituting $t = q$ shows that the integer $\Phi_n(q)$ divides $q^n - 1$. Let d be a divisor of n with $d < n$. By lemma 19.7.4 again, $t^d - 1$ is the product of the $\Phi_e(t)$ over the divisors e of d, and these are divisors of n different from n. Hence

$$t^n - 1 = (t^d - 1)\,\Phi_n(t)\,g(t) \qquad g(t) = \prod_{\substack{e \big| n,\ e \nmid d \\ e < n}} \Phi_e(t) \in \mathbb{Z}[t]$$

and so $(q^n-1)/(q^d-1) = \Phi_n(q)\,g(q)$ is an integer multiple of $\Phi_n(q)$. Applying this to each d_i, the class equation of Step 3 shows that $\Phi_n(q)$ divides $q-1$. As $q - 1 \ge 1$, this gives $|\Phi_n(q)| \le q - 1$.

Step 5: the size of $\Phi_n(q)$. By definition 19.7.2, $|\Phi_n(q)|$ is the product of the numbers $|q - \zeta|$ over the primitive nth roots of unity $\zeta \in \mathbb{C}$, of which there is at least one. As $n > 1$, each such ζ satisfies $\zeta \ne 1$ and $|\zeta| = 1$, so $\operatorname{Re}\zeta < 1$ and

$$|q - \zeta|^2 = q^2 - 2q\operatorname{Re}\zeta + 1 > q^2 - 2q + 1 = (q-1)^2$$

Each factor therefore exceeds $q - 1$. With $m \ge 1$ factors, the product exceeds $(q-1)^m$, which is at least $q - 1$ because $q - 1 \ge 1$. This contradicts Step 4, so $n = 1$. Then $D = Z$ is commutative, and D is a field.

Exercise 19.7.1

1. Let $f(x) \in \mathbb{F}_p[x]$ be irreducible of degree n. Show that the field $\mathbb{F}_p[x]/(f(x))$ is a splitting field of $f(x)$ over $\mathbb{F}_p$, and that it is isomorphic to the splitting field of $x^{p^n} - x$ over $\mathbb{F}_p$.
2. Let $k = \mathbb{F}_p$. Show that $f(x^p) = f(x)^p$ for every $f(x) \in k[x]$.

20

Galois Theory

For eons, mathematicians looked for relations between coefficients and roots of a polynomial. The answer is "trivial" for linear polynomials, given:

$$ax + b = 0 \qquad \text{with solution } \alpha, \text{ then} \quad \alpha = -ba^{-1}$$

For a quadratic $x^2 + bx + c$ with roots α and β, then $\alpha + \beta = -b$ and $\alpha\beta = c$[1], and each individual root is given by the quadratic formula:

$$r = \frac{-b \pm \sqrt{b^2 - 4ac}}{2a}$$

More generally, a lot of focus was put into finding the roots of polynomials given their coefficients[2], eventually finding the cubic and quartic equation relating the coefficients to roots of cubic and quartic polynomials respectively. However, the effort to generalize to higher degree polynomials brought limited results, in particular even for the next degree (the quintic) it was unclear how its roots can written in terms of it's coefficients and the arithmetic operations of $+, -, \times, \div$ and $\sqrt{-}$. It was not until the turn of the 18th century when serious progress has been made on this front. The key insight was to treat the coefficients of a polynomials as determining a dynamical system (that is, the dynamic of how the roots of a polynomial change as we move around the coefficients). In chapter 19, the right context to consider is the algebraic closure of a field; for pedagogical purposes we stick to $\overline{\mathbb{Q}}$ or $\mathbb{C}$ namely since this is the theories starting point and generalizations to $\mathbb{F}_{q^n}$ and other fields/rings is the natural progression.

To demonstrate these dynamics, consider $x^2 + x - 1 = 0$. This equation (by using the quadratic

[1] See section 20.2.3 for much more detail about these relations

[2] This is a little anachronistic, for when the quadratic formula was first discovered in Babylonia and more succinctly by Brahmagupta, the "modern" notion of polynomial and variables where not used, but rather it was shown by relating areas of circles and rectangles

equations) has solutions:

$$x_1 = \frac{-1+\sqrt{5}}{2} x_2 = \frac{-1-\sqrt{5}}{2}$$

If the b and c coefficients are swapped to get $x^2 - x + 1 = 0$, then the solutions are:

$$x_1 = \frac{1+i\sqrt{3}}{2} x_2 = \frac{1-i\sqrt{3}}{2}$$

In other words if (a, b, c) represents the coefficients, then the permutation action $(2\ 3) \in S_3$ does not leave the roots invariant, that is this is *not* invariant to coefficient permutation. Note these dynamics are "discrete", but they are the shadow of a continuous one. Let $\mathcal{P}_n$ denote the space of monic degree-n complex polynomials with distinct roots, that is, $\mathbb{C}^n$ with the discriminant locus removed. Sending a polynomial to its unordered set of roots exhibits the space of *ordered* root tuples as an n-sheeted covering of $\mathcal{P}_n$, so a *loop* of coefficients returns the root set to itself while permuting the individual roots. This is a homomorphism

$$\pi_1(\mathcal{P}_n) \longrightarrow S_n$$

and the permutation above is one of its values: the discrete action is what a continuous loop leaves behind. The group $\pi_1(\mathcal{P}_n)$ is the braid group B_n, and for a generic polynomial the image of this map is all of S_n, the same S_n that will shortly appear as a Galois group. That a fundamental group turns up here is not an accident; see box 20.0.1.

Now, given a general $ax^2 + bx + c = 0$, factoring as $(x - \alpha)(x - \beta)$, then by commutativity:

$$(x - \alpha)(x - \beta) = (x - \beta)(x - \alpha)$$

In other words, applying an S_2 action on the roots leaves the coefficients invariant[3] [4].

The first immediate introduction of dynamics into polynomials is by applying group-actions to the roots. The realization that links roots to coefficients is that, given we can completely split a polynomial:

$$x^n + \cdots + \alpha_1 x + \alpha_0 = (x - a_1)(x - a_2) \cdots (x - a_n)$$

each coefficient of the original polynomial can be represented as a *symmetric function* (see section 20.2.3).

$$\begin{aligned}
\alpha_{n-1} &= -(a_1 + a_2 + \cdots + a_n) \\
\alpha_{n-2} &= a_1 a_2 + a_1 a_3 + \cdots + a_1 a_n + a_2 a_3 + \cdots a_{n-1} a_n \\
&\cdots \\
\alpha_0 &= (-1)^n a_1 a_2 \cdots a_n
\end{aligned}$$

the signs alternating, exactly as in the quadratic case above where $\alpha + \beta = -b$ and $\alpha\beta = c$. These form a natural relationship between the roots and the coefficients. It was noticed that these equations are invariant under permutation action of S_n; if $A = \{A_0, ..., A_{n-1}\}$ represent the above n equations and the action is given by $(r\ s) \cdot a_r = a_s$, then $\sigma \cdot A_i = A_i$ for each A_i and σ, hence the action $S_n \curvearrowright A$ is the trivial action. Thus, there is always a natural group-action.

[3] Concretely, take $x^2 - c$, whose roots are $\pm\sqrt{c}$. As c travels once around the circle $c = re^{i\theta}$, with θ running from 0 to 2π, the roots $\pm\sqrt{r}e^{i\theta/2}$ trade places: a single loop of the coefficient around the discriminant realises the transposition in S_2

[4] As a consequence, there is no continuous function that can take in coefficients and return roots

As any roots of polynomial induce such equations and induce this trivial action, these do not give enough information about polynomials. It shall be shown that roots of a generic polynomial satisfy no further equation, and in these cases there is nothing more that can be done to understand a polynomial via a group-action on its roots. However, there are polynomials whose roots shall have *more* relations the roots satisfy, limiting what group can act on them (i.e. a subgroup of S_n will act trivially, but S_n will not). This chapter shall make rigorous this realization and translate it into the modern language of field theory.

This realization almost managed to show the general quintic is unsolvable:

> "The quintic was almost proven to have no general solutions by radicals by Paolo Ruffini in 1799, whose key insight was to use permutation groups, not just a single permutation. His solution contained a gap, which Cauchy considered minor, though this was not patched until the work of the Norwegian mathematician Niels Henrik Abel, who published a proof in 1824, thus establishing the Abel-Ruffini theorem."[5]

This theory was established with the aim to show there is an unsolvable quintic, but not how to find whether a given quintic is solvable. This is where the work of Évariste Galois comes in. He noticed that the key insight was to work with all possible relationships of the roots of the polynomial, assuming all the roots exist.

Modern uses of Galois Theory

Galois groups are central in both algebraic geometry and number theory, where they serve different purposes in each domain. The galois group of a polynomial:

1. establishes the algebraic relations between the roots and creates a "covering space" that has some similar properties to the covering spaces seen in algebraic topology (see box 20.0.1),
2. establishes the invariance necessary to find a solution over a lower field, in particular if L/K is a field extension and a root of an $L[x]$ polynomial has a root in K, then the root is invariant under the $\mathrm{Gal}_K(L)$-action.

From action on roots to field theory

Take the polynomial:

$$x^4 - 2 = 0$$

which is irreducible over $\mathbb{Q}$ by Eisenstein's criterion (proposition 11.3.10). Adjoining $\sqrt[4]{2}$, $\mathbb{Q}(\sqrt[4]{2})$, the polynomial splits to:

$$(x - \sqrt[4]{2})(x + \sqrt[4]{2})(x^2 + \sqrt{2})$$

Adjoining $\sqrt[4]{2}i$, the polynomial splits completely:

$$(x - \sqrt[4]{2})(x + \sqrt[4]{2})(x - \sqrt[4]{2}i)(x + \sqrt[4]{2}i) \tag{20.1}$$

Already, there is some interesting phenomena at play, for example, another way of getting this splitting is by adjoining $\sqrt[4]{2}$ and then adjoining i (or adjoining i then $\sqrt[4]{2}$). In fact, by just adjoining

[5] taken from Wikipedia for Galois Theory

$\sqrt[4]{2}+i$, we immediately get this splitting. Indeed, certainly $\mathbb{Q}(\sqrt[4]{2}+i) \subseteq \mathbb{Q}(\sqrt[4]{2}, i)$. Conversely, to show $i \in \mathbb{Q}(\sqrt[4]{2}+i)$, letting $a = \sqrt[4]{2}+i$, then:

$$\begin{aligned} a - i &= \sqrt[4]{2} \\ \Leftrightarrow\ (a-i)^4 &= 2 \\ \Leftrightarrow\ (a-i)^4 &= 2 \\ \Leftrightarrow\ a^4 - 4a^3 i - 6a^2 + 4ai + 1 &= 2 \\ \Leftrightarrow\ i(4a - 4a^3) &= 1 - a^4 + 6a^2 \\ \Leftrightarrow\ i &= \frac{1 - a^4 + 6a^2}{4a - 4a^3} \end{aligned}$$

showing that $i \in \mathbb{Q}(\sqrt[4]{2}+i)$, and so $a - i = \sqrt[4]{2} \in \mathbb{Q}(\sqrt[4]{2}+i)$. More generally for any finite separable extension $K/\mathbb{Q}$, such an element always exists and is constructible by the primitive element theorem (theorem 19.6.20).

Let us understand the equations the roots form given by symmetric functions. As $x^4 - 2 = x^4 + 0x^3 + 0x^2 + 0x - 2$, the only meaningful relation obtained by multiplying out the roots in (20.1) is:

$$(\sqrt[4]{2})(-\sqrt[4]{2})(\sqrt[4]{2}i)(-\sqrt[4]{2}i) = -2 \qquad \text{equiv.} \qquad (\sqrt[4]{2})(-\sqrt[4]{2})(\sqrt[4]{2}i)(-\sqrt[4]{2}i) + 2 = 0$$

This equation is invariant under the action of S_4, namely if

$$(a_1, a_2, a_3, a_4) = (\sqrt[4]{2}, \sqrt[4]{2}i, -\sqrt[4]{2}, -\sqrt[4]{2}i)$$

represent the 4 roots, and $A_0 = (\sqrt[4]{2})(-\sqrt[4]{2})(\sqrt[4]{2}i)(-\sqrt[4]{2}i) + 2 = 0$, then:

$$\sigma \cdot A_0 = A_0 \qquad \forall \sigma \in S_4$$

However, there are more equations that can be formed with these roots (using the operations of a field). With the labelling above, the first and third roots are negatives of one another, as are the second and fourth:

$$\begin{aligned} A_1 :\ a_1 + a_3 &= \sqrt[4]{2} + (-\sqrt[4]{2}) = 0 \\ A_2 :\ a_2 + a_4 &= \sqrt[4]{2}i + (-\sqrt[4]{2}i) = 0 \end{aligned}$$

These equations are *not* invariant under the permutation action of S_4:

$$(1\ 2) \cdot A_1 \neq A_1 \qquad \text{(concretely: } (1\ 2) \cdot (a_1 + a_3) = a_2 + a_3 = \sqrt[4]{2}i - \sqrt[4]{2} \neq 0)$$

A subgroup of S_4 must be chosen, namely notice that $D_4 \cong \langle (1\ 2\ 3\ 4), (1\ 3) \rangle \subseteq S_4$[6] keeps them invariant. It does not fix each one separately: the four-cycle carries A_1 to A_2 and back. What it preserves is the *pairing* $\{\{1,3\},\{2,4\}\}$ of the roots into negative pairs, and so the pair of equations as a set:

$$D_4 \cdot A_0 = A_0 \qquad D_4 \cdot \{A_1, A_2\} = \{A_1, A_2\}$$

Indeed D_4 is precisely the stabiliser of that pairing inside S_4, and it has order $8 = [\mathbb{Q}(\sqrt[4]{2}, i) : \mathbb{Q}]$, the first hint that this is the right subgroup. Are there any other equations that we can be considered

[6]The reader may recall exercise set 1.3.1 asks to show S_n is generated by a two cycle and an n-cycle; it was important the 2-cycle was an *adjacent* cycle

which would further restrict the choice of invariant permutation action? To answer this, the above is re-framed in the language of field extensions.

Let us say f is a polynomial over $\mathbb{Q}$ and that α is a root of f. Then the algebraic extension $\mathbb{Q}(\alpha)/\mathbb{Q}$ contains *all* possible polynomial equations that can be generated with elements from $\mathbb{Q}$ and α (recall $\mathbb{Q}(\alpha) = \mathbb{Q}[\alpha]$, see proposition 19.2.24). If any of these polynomials happen to be another root of f, that is $p(\alpha) = \beta$ where $f(\beta) = 0$ and $p(x) \in \mathbb{Q}[x]$, then $\mathbb{Q}(\alpha)/\mathbb{Q}$ contains this relationship between the roots. Let's say one of these relationships is represented as :

$$P(x) = p(x) - \beta \text{ so that } P(\alpha) = p(\alpha) - \beta = 0$$

Then a $\mathbb{Q}$-automorphism (in this case nothing more than a field automorphism) would have to preserve this relationship (it must map roots to roots). Hence, the set of $\mathbb{Q}$-automorphism captures the relationships between α and all possible roots that are $\mathbb{Q}$-polynomials of α. If $K/\mathbb{Q}$ is the splitting field of f, then the $\mathbb{Q}$-automorphisms of K would be restricted to automorphism that must satisfy all possible relationships between roots. Given $K/\mathbb{Q}$ is a splitting field for f, as any $\mathbb{Q}$-automorphisms σ is determined by where the roots map to, it is associated to a permutation in S_n. If there were no relationships (you need to add n roots to split f), then the automorphism group would be isomorphic to S_n. If there is any other type of group, that means there are some relationships between the roots (just like the example of $\mathbb{Q}(\sqrt[4]{2} + i)/\mathbb{Q}$).

The automorphism group of the splitting field above is called the *galois group* and it is the aim of this chapter define the galois group for any field extension L/K, to be able to find some galois groups, to find how frequent certain galois groups are, to show the correspondence between field extension and galois groups, and answer some long-pending mathematical questions such as the solvability of [general] quintic using the newly developed theory.

Another way of thinking about galois group is they are a rough classification tool for field extensions: if two field extensions have different Galois groups they cannot be the same extensions. It is similar in roughness to the fundamental group $\pi_1(X)$ as is often encountered in algebraic topology. To see this roughness in classification, as the splitting field $\mathbb{Q}(\sqrt[4]{2}, i)$ of $x^4 - 2$ is equal to $\mathbb{Q}(\sqrt[4]{2} + i)$, and the minimal polynomial of $\sqrt[4]{2} + i$ is:

$$x^8 + 4x^6 + 2x^4 + 28x^2 + 1$$

then they share the same restrictions on their roots as they have the same galois group, but they certainly also have many differences (for example, these two polynomials have different discriminants, see definition 19.6.27).

20.0.1 Galois Group as Fundamental Group

(Assuming strong familiarity with algebraic geometry and algebraic topology) Under the right framework in algebraic geometry, galois groups can be interpreted as *étale fundamental group* for $\operatorname{Spec} K$,

$$\pi_1^{\text{ét}}(\operatorname{Spec}(K)) \cong \operatorname{Gal}_K(\overline{K})$$

The name *fundamental group* is well-deserved for if X is a connected $\mathbb{C}$-scheme of finite type (i.e. "essentially" a connected variety) and $X(\mathbb{C})$ is its analytification, then:

$$\pi_1^{\text{ét}}(X) \cong \widehat{\pi_1^{\text{top}}(X(\mathbb{C}))}$$

where $\pi_1^{\text{top}}(-)$ is the usual fundamental group and $\widehat{(-)}$ is the profinite completion with respect to its finite-index normal subgroups. See [13] for the details.

20.1 Galois Extension and Galois Group

First, let's the recall the definition of an automorphism and define a new term:

Definition 20.1.1: Automorphism and fixed Element

1. An isomorphism σ of F with itself is called an *automorphism* of F. The collection of automorphisms of F is denoted $\mathrm{Aut}(F)$. If $\alpha \in F$, we write $\sigma\alpha$ for $\sigma(\alpha)$
2. An auotmorphism $\sigma \in \mathrm{Aut}(F)$ is said to *fix* an element $\alpha \in F$ if $\sigma\alpha = \alpha$. If k is a subset of F, then an automorphism σ is said to *fix* F if it fixes all the elements of F

$$\sigma a = a \qquad \forall a \in k$$

3. Let F/k be an extension of fields. Then $\mathrm{Aut}(F)$ is the collection of automorphissm of F, and $\mathrm{Aut}_k(F)$ is collection of automorphsism of F which fix F.

Example 20.1.2: Automorphism and Fixed F

The identity map id is always an automorphism.

Furthermore, the prime field of any field K is always fixed. If P is the prime-field of F, then for any $\sigma \in \mathrm{Aut}(K)$, $\sigma(1) = 1$, since $\sigma(0) = 0$. Thus, $\sigma(a) = a$ for every $a \in P$. This means that $\mathbb{Q}$ and $\mathbb{F}_p$ have only trivial automorphisms

$$\mathrm{Aut}(\mathbb{Q}) = \{\mathrm{id}\}, \mathrm{Aut}(\mathbb{F}_p) = \{\mathrm{id}\}$$

and if P is a prime field of F, then

$$\mathrm{Aut}_P(F) = \mathrm{Aut}(F)$$

Next, we recall a very useful criterion for finding automorphisms of algebraic extensions K/F

Proposition 20.1.3: Fixed Roots Criterion

Let F/k be a field extension and let $\alpha \in F$ be algebraic over k. Then for any $\sigma \in \mathrm{Aut}(F/k)$, $\sigma\alpha$ is a root of the minimal polynomial for α over k, i.e., $\mathrm{Aut}(F/k)$ permutes the roots of irreducible polynomials. Equivalently, any polynomial whith coefficeints in k having α as a root also has $\sigma\alpha$ as a root.
Furthermore, $\mathrm{Aut}_k(k(\alpha))$ acts *transitively* on the set of roots of $m_{k,\alpha}(x)$ (i.e. if β_1, β_2 are roots of $m_{k,\alpha}(x)$, then there exists a $\sigma \in \mathrm{Aut}_k(k(\alpha))$ such that $\sigma\beta_1 = \beta_2$)

***Proof*:**

Let

$$x^n + a_{n-1}x^{n-1} + \cdots + a_1x + a_0$$

be the minimal polynomial with coefficients from F so that

$$\alpha^n + a_{n-1}\alpha^{n-1} + \cdots + a_1\alpha + a_0 = 0$$

then, applying any automorphism σ to this polynomial will get us

$$\sigma(\alpha^n + a_{n-1}\alpha^{n-1} + \cdots + a_1\alpha + a_0) = \sigma(0)$$
$$\sigma(\alpha)^n + a_{n-1}\sigma(\alpha)^{n-1} + \cdots + a_1\sigma(\alpha) + \sigma(a_0) = 0 \qquad \sigma \text{ fixes } a_i \text{ for each } i$$

since $a_i \in F$ for each i, showing that $\sigma(\alpha)$ is also a root of the minimal polynomial

Transitivty is left as an exercise (recall the appropriate theorem)

Example 20.1.4: Automorphism Groups

1. Take $K = \mathbb{Q}(\sqrt{2})$. Then $\text{Aut}(\mathbb{Q}(\sqrt{2})) = \text{Aut}(\mathbb{Q}(\sqrt{2})/\mathbb{Q})$. If $\sigma \in \text{Aut}(\mathbb{Q}(\sqrt{2}))$, then by the fixed root criterion, it must be that

   $$\sigma(\sqrt{2}) = \pm\sqrt{2}$$

   and since σ must fix everything else in place, this means that we get

   $$\sigma(a + b\sqrt{2}) = a \pm b\sqrt{2}$$

   in other words, we have determined were every other element must map to! Thus, we have the maps

   $$\sqrt{2} \mapsto \sqrt{2} \qquad \sqrt{2} \mapsto \sqrt{-2}$$

   If we let the first map be represetned by 1 and the second by σ, then we get

   $$\text{Aut}(\mathbb{Q}(\sqrt{2})) = \{1, \sigma\} = C_2$$

   that is, $\text{Aut}(\mathbb{Q}(\sqrt{2}))$ is a cyclic group of order 2.

2. Let $K = \mathbb{Q}(\sqrt[3]{2})$. By theorem 19.2.5, every element of $\mathbb{Q}$ can be written as

   $$a + b\sqrt[3]{2} + c(\sqrt[3]{2})^2$$

   If we consider any $\sigma \in \text{Aut}(\mathbb{Q}(\sqrt[3]{2}))$, then we get

   $$a + b\sigma(\sqrt[3]{2}) + c\sigma(\sqrt[3]{2}) \qquad a, b, c \in \mathbb{Q}$$

   and since $\mathbb{Q}(\sqrt[3]{2})$ has non of it's other roots (recall example 19.3.12). Then that means that the only automorphism is the identity, meaning

   $$\text{Aut}(\mathbb{Q}(\sqrt[3]{2})) = \{1\}$$

3. Now let $K = \mathbb{Q}(\sqrt[3]{2}, \sqrt{-3})$, be the splitting field of $x^3 - 2$ in example 19.5.11, which unlike the previous example will insure we have interesting automorphisms since K contains all the roots of $x^3 - 2$. Let's label these roots $\sqrt[3]{2}, \omega, \omega^2$. Then:

   $$[\mathbb{Q}(\sqrt[3]{2}, \sqrt{-3}) : \mathbb{Q}] = [\mathbb{Q}(\sqrt[3]{2}, \sqrt{-3}) : \mathbb{Q}(\sqrt[3]{2})] : [\mathbb{Q}(\sqrt[3]{2}) : \mathbb{Q}] = 2 \cdot 3 = 6$$

   We know that $\mathbb{Q}(\sqrt[3]{2})$ contains one root of $x^3 - 2$ over $\mathbb{Q}$ ($\sqrt[3]{2} \in \mathbb{Q}(\sqrt[3]{2})$), and that $\mathbb{Q}(\sqrt[3]{2}, \omega)$ also contains the other two roots over $\mathbb{Q}$, and in particular over $\mathbb{Q}(\sqrt[3]{2})$ ($\omega, \omega^2 \in \mathbb{Q}(\sqrt[3]{2}, \omega)$.

Next, Since the degree of K is 6, we know it has a basis consisting of 6 elements, namely:

$$1,\ \sqrt[3]{2},\ \sqrt[3]{4},\ \omega,\ \omega\sqrt[3]{2},\ \omega\sqrt[3]{4}$$

Since any $\mathbb{Q}$-automorphism of K is a $\mathbb{Q}$-linear automorphism on K, it suffices to characterise these automorphisms by where by map these basis elements. By the fixed roots criterion, a $\mathbb{Q}$-automorphism σ on K can map $\sqrt[3]{2}$ to:

$$\sqrt[3]{2},\ \omega\sqrt[3]{2},\ \omega^2\sqrt[3]{2}$$

and map ω to:

$$\omega,\ \omega^2$$

Using this information, we can carry through computations to see that $\mathrm{Aut}_{\mathbb{Q}}(K)$ is S_3.

4. More on computing automorphisms groups here: here

Lemma 20.1.5: Field Automorphism Is Functorial

Let $\mathcal{N}_k$ be the category whose objects are the finite normal extensions of k and whose morphisms are the k-homomorphisms. Then $\mathrm{Aut}_k(-)$, sending F to $\mathrm{Aut}_k(F)$ and a morphism $\iota\colon F \to L$ to $\mathrm{Aut}_k(L) \to \mathrm{Aut}_k(F)$, $\varphi \mapsto \iota^{-1} \circ \varphi \circ \iota$, is a contravariant functor $\mathcal{N}_k \to \mathbf{Grp}$.

***Proof*:**
The field homomorphism ι is injective, and $\iota(F)$ is finite and normal over k, being k-isomorphic to F. For $\varphi \in \mathrm{Aut}_k(L)$, φ restricts to a k-homomorphism from $\iota(F)$ into $\overline{L}$, an algebraic closure of $\iota(F)$, so $\varphi(\iota(F)) = \iota(F)$ (theorem 19.5.13) and $\iota^{-1} \circ \varphi \circ \iota \in \mathrm{Aut}_k(F)$. Conjugating by ι preserves composition and identities, so each map is a group homomorphism, and for a second morphism $\kappa\colon L \to M$ and $\psi \in \mathrm{Aut}_k(M)$,

$$(\kappa \circ \iota)^{-1} \circ \psi \circ (\kappa \circ \iota) = \iota^{-1} \circ (\kappa^{-1} \circ \psi \circ \kappa) \circ \iota$$

which is contravariance.

Normality is needed: in $\mathbb{Q}(\sqrt[3]{2}, \omega)$, $\omega = e^{2\pi i/3}$, some $\mathbb{Q}$-automorphism sends $\sqrt[3]{2}$ to $\omega\sqrt[3]{2} \notin \mathbb{Q}(\sqrt[3]{2})$, so it does not restrict to $\mathbb{Q}(\sqrt[3]{2})$. For groups, restriction along an injective homomorphism can fail to exist: for $f\colon \mathbb{Z}/2\mathbb{Z} \to S_3$ with image $\langle (1\,2) \rangle$, conjugation by $(1\,3)$ is an automorphism of S_3 that moves $f(\mathbb{Z}/2\mathbb{Z})$.

Beyond functoriality, $\mathrm{Aut}_k(-)$ preserves more structure, namely the latice of groups and interemetiate fields is [contravariantly] preserved. The following propositions builds up to this result. Since $\mathrm{Aut}_k(F)$ has a relatively easy to find structure, any connections between the structure of $\mathrm{Aut}_k(F)$ (which is a finite group if $[F : k] < \infty$) and F/k would allow us to use the full power of group theory (and better still finite group theory) to analise field extensions. We endevaour to deepen this connection in this chapter. One of the most important connection is that intermediate fields $k \subseteq E \subseteq F$ correspond to subgroups of $\mathrm{Aut}(F/k)$! This is called the *Galois correspondence*, and is what we will be building up for the rest of this section. We start by showing how subgroups of $\mathrm{Aut}_k(F)$ correspond to an intermediate field $k \subseteq E \subseteq F$, and conversely intermediate extension $k \subseteq E \subseteq F$ correspond a subgroup fo $\mathrm{Aut}_k(F)$

Proposition 20.1.6: Fixing F with automorphisms

Let $H \leqslant \mathrm{Aut}_k(F)$ be a subgroup of automorphisms of F (or $H \subseteq \mathrm{Aut}_k(F)$ more generally). Then the collection F^H of elements of F fixed by all the elements of H is a subfield of F extending k, $k \subseteq F^H \subseteq F$. Conversely, Let E be an intermediate field $k \subseteq E \subseteq F$. Then $\mathrm{Aut}_E(F) \leqslant \mathrm{Aut}_k(F)$.

***Proof*:**
Let F^H be the collection of fixed elements by element $h \in H$. Then by definition, every element of k is fixed by H, so F^H is nonempty and $k \subseteq F^H$. Next, for any $a, b \in F^H$

$$h(a \pm b) = h(a) \pm h(b) = a \pm b \qquad h(ab) = h(a)h(b) = ab \qquad h(a^{-1}) = h(a)^{-1} = a^{-1}$$

that is, F^H is closed under the operations of F, and so $F^H \subseteq F$, showing that $k \subseteq F^H \subseteq F$.

For the other direction, let $\mathrm{Aut}_E(F)$ be the set of automorphisms that fix E. This subset is nonempty since $\mathrm{id}_F \in \mathrm{Aut}_E(F)$. If $\sigma \in \mathrm{Aut}_E(F)$, then $\sigma^{-1} \in \mathrm{Aut}_E(F)$: applying σ^{-1} to $\sigma(e) = e$ gives $\sigma^{-1}(e) = e$ for every $e \in E$. Finally, for any $\sigma, \tau \in \mathrm{Aut}_E(F)$, given $e \in E$,

$$\sigma \circ \tau^{-1}(e_1) = \sigma(\tau^{-1}(e)) = \sigma(e) = e$$

showing that $\sigma \circ \tau^{-1} \in \mathrm{Aut}_E(F)$, an so $\mathrm{Aut}_E(F) \leqslant \mathrm{Aut}_k(F)$, completing the proof.

Definition 20.1.7: Fixed Field

Let $H \subseteq \mathrm{Aut}_k(F)$. Then the subfield of F fixed by all the elements of H is called the *fixed field* of H, and is denoted F^H.

Example 20.1.8: Fixed Field

1. The fixed field of $\mathrm{Aut}_{\mathbb{Q}}(\mathbb{Q}(\sqrt{2}))$ is $\mathbb{Q}$. As we have seen in example 20.1.4.
2. The fixed field of $\mathrm{Aut}_{\mathbb{Q}}(\mathbb{Q}(\sqrt[3]{2}))$ is $\mathbb{Q}(\sqrt[3]{2})$, since $\mathrm{Aut}_{\mathbb{Q}}(\sqrt[3]{2}) = \{\mathrm{id}\}$. If we add the other roots of $x^3 - 2$, then the fixed field of $\mathrm{Aut}_{\mathbb{Q}}(\mathbb{Q}(\sqrt[3]{2}, \omega))$ is $\mathbb{Q}$.

Using this vocabulary, we can make the following correspondence betweeen F/k and its intermediate fields with $\mathrm{Aut}_k(F)$ and it's subgroups:

Proposition 20.1.9: Galois Correspondence

Let $k \subseteq F$ be a fields extension. Then there exists a correspondence:

$$\left\{\begin{matrix}\text{Intermediate fields } E \\ k \subseteq E \subseteq F\end{matrix}\right\} \underset{F^H}{\overset{\text{Aut}_E(F)}{\rightleftarrows}} \left\{\begin{matrix}\text{subgroups } H \\ H \subseteq \text{Aut}_k(F)\end{matrix}\right\}$$

sending an intermediate field E to the subgroup $\text{Aut}_E(F)$, and a subgroup H of $\text{Aut}_k(F)$ to the fixed field F^H. Furthermore, we have the following properies:

1. The correspondence is inclusion reversing, that is:
   - if $k \subseteq E_1 \subseteq E_2 \subseteq F$ are two subfield of F extending k , then $\text{Aut}_{E_2}(F) \leqslant \text{Aut}_{E_1}(F)$
   - if $H_1 \leqslant H_2 \leqslant \text{Aut}_k(F)$ are two subgroups of automorphsism with associated fixed fields F^{H_1} and F^{H_2} respectively, then $F^{H_2} \subseteq F^{H_1}$.
2. For all subgroups $H \leqslant \text{Aut}_k(F)$ and intermediate fields $k \subseteq E \subseteq F$
   - $E \subseteq F^{\text{Aut}_E(F)}$
   - $H \subseteq \text{Aut}_{F^H}(F)$
3. If E_1E_2 is the smallest subfield of F containing the two intermediate the E_1 and E_2, and $\langle G_1, G_2\rangle$ denotes the smallest subgroup of $\text{Aut}_k(F)$ containing G_1 and G_2, then:

$$\begin{aligned}\text{Aut}_{E_1E_2}(F) &= \text{Aut}_{E_1}(F) \cap \text{Aut}_{E_2}(F) \\ F^{\langle G_1,G_2\rangle} &= F^{G_1} \cap F^{G_2}\end{aligned}$$

***Proof*:**
The Galois correspondence is an immediate consequence of proposition 20.1.6.

For the inclusion-reversal, consider the extension, $k \subseteq E_1 \subseteq E_2 \subseteq F$. Then $\text{Aut}_{E_2}(F)$ *a fortiori* fixes all the elements of E_1, since $E_1 \subseteq E_2$, and so can only be *smaller* as the number of elements in Aut_{E_2} depend on the number of roots that can be premuted (as shown in the root permutation Criterion). A similar argument can be made for $H_1 \leqslant H_2 \leqslant \text{Aut}_k(F)$.

For the subsets, Take the intermediate field E, $k \subseteq E \subseteq F$. Then $F^{\text{Aut}_E(F)}$ is the set of elements That are fixed by the automorphisms that fix E. Then it is immediate that $E \subseteq F^{\text{Aut}_E(F)}$. Similarly for $H \subseteq \text{Aut}_{F^H}(F)$.

For the minimality statements, If E_1E_2 is the smallest of F containing both E_1 and E_2, then the $\subseteq$ inclusion is immediate (since $\text{Aut}_{E_1}(F) \cap \text{Aut}_{E_2}(F)$ contains only elements that fix E_1 and E_2), while the $\supseteq$ comes from the fact that $\text{Aut}_{E_1}(F)$ and $\text{Aut}_{E_2}(F)$ are in themselves the minimal subgroups of $\text{Aut}_k(F)$ that fix all elements of E_1 and E_2. A similar argument can be made for the second assertion.

It is natural to ask whether the galois correspondence is bijective. Before showing when it is, we will show that it is possible that it is not:

Example 20.1.10: non-bijective Galois Correspondence

Consider $Q(\sqrt[3]{2})/\mathbb{Q}$. Then we know that $[\mathbb{Q}(\sqrt{3})/\mathbb{Q}] = 3$, which is prime, and so the only intermediate fields are $\mathbb{Q}$ and $\mathbb{Q}(\sqrt[3]{2})$. For $\text{Aut}_{\mathbb{Q}}(\mathbb{Q}(\sqrt[3]{2}))$, recall that $\mathbb{Q}(\sqrt[3]{2}) \subseteq \mathbb{R}$, and that $\sqrt[3]{2}$ is the only root of the minimal polynomial within $\mathbb{R}$. Thus, since automorphisms of fields permute roots, $\text{Aut}_{\mathbb{Q}}(\mathbb{Q}(\sqrt[3]{2}))$ can only have one element:

$$\text{Aut}_{\mathbb{Q}}(\mathbb{Q}(\sqrt[3]{2})) = \{e\}$$

Hence, we have:

$$\{\mathbb{Q}, \mathbb{Q}(\sqrt[3]{2})\} \rightleftarrows \{\,\{e\}\,\} = \{\text{Aut}_{\mathbb{Q}}(\mathbb{Q}(\sqrt[3]{2}))\}$$

showing that the function from intermediate fields to subgroups of the automorphism group is not injective with respect to intermediate fields in general[a] (for every intermediate field, we may map it to the same subgroup of $\text{Aut}_k(F)$). In this case, $\mathbb{Q} \subseteq F^{\text{Aut}_{\mathbb{Q}}(\mathbb{Q}(\sqrt[3]{2}))}$ and $\mathbb{Q}(\sqrt[3]{2}) \subseteq F^{\text{Aut}_{\mathbb{Q}}(\mathbb{Q}(\sqrt[3]{2}))}$

[a] Or similarly, the correspondence is not surjective with respect to subgroups of $\text{Aut}_k(F)$

This examples shows that it possible that $E \subsetneq F^{\text{Aut}_E(F)}$. Fortunately, in the finite case, we always have that for any $H \leqslant \text{Aut}_k(F)$, there exists an intermediate field (namely F^H) such that $H = \text{Aut}_{F^H}(F)$ (and hence, the correspondence is at least always surjective with respect to intermediate fields). To prove this result we need the following lemma which shows that the field F^H is essentially as nice as a field as we want. The high-level idea is that automorphisms in $H = \text{Aut}_E(F)$ fix E, and F^H is *defined* to be the field that is fixed by H:

Lemma 20.1.11: Properties Of Fixed Field

Let F/k be a finite extension, and let $H \leqslant \text{Aut}_k(F)$. Then F/F^H is normal and separable. It is furthermore finite and simple.

Note that we are not given that F^H or k is a perfect field, and so separability is a powerful result. Similarly, we do not know beforehand that F is a normal extension of k, yet F is a normal extension of F/F^H. Note too that we can take $H = \{e\}$ so that $F/F^{\{e\}}$ has all the aforementioned properies. As we have seen in the previous example, it is not necessarily the case that $F^{\{e\}} = k$. (in the previous example, we had $F^{\{e\}} = \mathbb{Q}(\sqrt[3]{2})$)

***Proof*:**

First, F/F^H is finite since F/k is finite, so by the tower law:

$$[F : k] = [F : F^H][F^H : k]$$

Next, to show F/F^H is a separable extension, we will show any $\alpha \in F$ is separable over F^H. To do so, we use the following clever trick: Let $\alpha \in F$ be any element of F (possibly an element of F^H). We will construct the minimal polynomial of α, and show that it is separable. Take $\sigma \in H$. Since F is finite over k, α is the root of some minimal polynomial, $m_{\alpha,k}(x)$. By the fixed roots criterion, $h\alpha$ must be a root of the minimal polynomial $m_{\alpha,k}(x)$ of α over k (which might also imply $h\alpha = \alpha$ if no other root are in F). Since $m_{\alpha,k}(x)$ has only finitely many roots, the H-orbit of α (i.e. all possibles distinct images of α under all possible $\sigma \in H$) consists of finitely many elements $\alpha_1, ..., \alpha_n$. Now, the group H acts on the H-orbit by premuting its elements.

Therefore, every element of H keeps the polynomial:

$$q_\alpha(x) = (x-\alpha_1)(x-\alpha_2)\cdots(x-\alpha_n)$$

fixed (where $\alpha_1 = \alpha$). In other words, the coefficients of $q_\alpha(x)$ *must* be in the fixed field F^H: $q_\alpha(x) \in F^H[x]$! Next, we show that $q_\alpha(x) = m_{\alpha,F^H}(x)$, which will show that the minimal polynomial corresponding to α is separable, showing α is separable. To see this, let $g(x)$ be any other polynomial having α as a root. Then:

$$g(\alpha) = b_m\alpha^m + \cdots + b_1\alpha + b_0 = 0$$

and by definition, any $\sigma \in H$ will map α to another root α_i, so:

$$g(\alpha_i) = b_m\alpha_i^m + \cdots + b_1\alpha_i + b_0 = 0$$

meaning $g(x)$ is divisible by $x-\alpha_i$ for every i, and hence $q_\alpha(x)\big|g(x)$. Since the minimal polynomial of α over F^H also has α as a root, we have that $q_\alpha(x)\big|m_{\alpha,f^H}(x)$, and as we have shown before $m_{\alpha,F^H}(x)\big|q_\alpha(x)$. Thus, $q_\alpha(x) = m_{\alpha,F^H}(x)$ up to a constant. Thus, α is separable and since α was arbitrary, F/F^H is a separable extension (Note that it's possible that $\alpha \in F^H$, in which case $q_\alpha(x) = x-\alpha$, which is certainly the minimal polynomial of α over F^H and is separable).

Next, since F/F^H is finite and separable, then by theorem 19.6.20, it simple. Let's say $F = F^H(\beta)$, so $F^H(\beta)/F^H$ is simple. Let $q_\beta(x)$ be define as we have done above (note that $q_\beta(x) = m_{\beta,F^H}(x)$ and that it is not possible that $q_\beta(x) = x-\beta$ unless $F = F^H$)

Finally, since $q_\beta(x) \in F^H[x]$ splits in F, and F is generated over F^H (namely, F is generated by F and β), F is the splitting field of $q_\alpha(x)$ over F^H, and so $F^H \subseteq F$ is a normal extension by theorem 19.5.13, completing the proof (notice again how finiteness was important for this part of the proof)

(checkout other proofs of this that do not require using the fact it's a simple extension, since the primitive roots theorem is sometimes proven using Galois Theory)

This proposition provides us with a couple more results: The polynomial $q_\alpha(x)$ (say of degree n) can be expanded to:

$$q_\alpha(x) = x^n - s_1x^{n-1} + s_2x^{n-1} - \cdots + (-1)^{n-1}s_{n-1}x + (-1)^n s_n$$

where each s_i are functions $s_i(\alpha_1, ..., \alpha_n)$ and represent:

$$s_1(\alpha_1, ..., \alpha_n) = \alpha_1 + \alpha_2 + \cdots + \alpha_n = \sum_i \alpha_i$$

$$s_2(\alpha_1, ..., \alpha_n) = \sum_{i<j} \alpha_i\alpha_j$$

$$s_3(\alpha_1, ..., \alpha_n) = \sum_{i<j<k} \alpha_i\alpha_j\alpha_k$$

$$\vdots$$

$$s_n(\alpha_1, ..., \alpha_n) = \alpha_1\alpha_2\cdots\alpha_n$$

Since $q_\alpha(x) \in F^H$, then each of these coefficients are in F^H. Furthermore, $\deg(q_\alpha(x)) \leq |H|$

Proposition 20.1.12: $H = \mathrm{Aut}_{F^H}(F)$

Let F/k be a *finite* extension, and let H be a subgroup of $\mathrm{Aut}_k(F)$. Then $|H| = [F : F^H]$ and

$$H = \mathrm{Aut}_{F^H}(F)$$

In particular, the Galois correspondence is surejctive for a finite field (for any subgroup $H \leqslant \mathrm{Aut}_k(F)$, there exists an intermediate field (namely F^H) such that $H = \mathrm{Aut}_{F^H}(F)$)

Intuitively, we want to show that $\mathrm{Aut}_{F^H}(F)$ *only* fixes F^H, and so $H = \mathrm{Aut}_{F^H}(F)$.

***Proof*:**
Let $H \leqslant \mathrm{Aut}_k(F)$. By proposition 20.1.9, we have that $H \leqslant \mathrm{Aut}_{F^H}(F)$, so $|H| \leq |\mathrm{Aut}_{F^H}(F)|$. Since $\mathrm{Aut}_{F^H}(F)$ is finite, verifying that $\geq$ holds will complete the proof.

To see this, recall that we have shown in lemma 20.1.11 that $F = F^H(\alpha)$ for some $\alpha \in F$. Thus, by corollary 19.2.29, $|\mathrm{Aut}_{F^H}(F)|$ equals the number of distinct roots of $m_{\alpha,F^H}(\alpha)$. Though we do not know the minimal polynomial $m_{\alpha,F^H}(x)$, we do know that α is a root of the polynomial $q_\alpha(x)$ defined in lemma 20.1.11. By construction, the number of roots of $q_\alpha(x)$ must be less than or equal $|H|$, giving us:

$$|\mathrm{Aut}_{F^H}(F)| \leq |H|$$

And since $|\mathrm{Aut}_{F^H}(F)| \geq |H|$, we get $|\mathrm{Aut}_{F^H}(F)| = |H|$ and since $H \subseteq \mathrm{Aut}_{F^H}(F)$, then $H = \mathrm{Aut}_{F^H}(F)$, giving the desired equality.

Finally, to show that $[F : F^H] = H$, since F/F^H is finite, separable, and normal, by corollary 19.6.21, $[F : F^H] = |\mathrm{Aut}_{F^H}(F)|$, completing the proof.

A particular consequence of this is that $\mathrm{Aut}_{F^{\mathrm{Aut}_E(F)}}(F) = \mathrm{Aut}_E(F)$, since the intermediate field that maps to $\mathrm{Aut}_{F^{\mathrm{Aut}_E(F)}}(F)$ is $F^{\mathrm{Aut}_E(F)}$, and so the group that it maps to is $\mathrm{Aut}_E(F)$.

Note that F/k being a *finite* extension was necesary for the proof. The Galois correspondence is in fact not necessarily surjective in the infinite case. This correspondence can be recovered given a suitable topology known as the *Krull topology* on $\mathrm{Aut}_k(F)$, which is used to limit the galois correspondence to *closed* subgroups of the automorphism group, which will regain surjectivity (theorem 50.8.8).

20.1.1 Galois Correspondence

We finally have reached a point where we can define a Galois extension. the following theorem is sometime also called the *Galois Extension Equivalences*, but it will be called by it's more famous name:

Theorem 20.1.13: Fundamental Theorem of Galois Theory I

Let F/k be a finite field extension. Then the following are equivalent:

1. F is the splitting field of a separable polynomial $f(x) \in k[x]$ over k
2. F/k is separable and normal
3. $|\text{Aut}_k(F)| = [F : k]$
4. $k = F^{\text{Aut}_k(F)}$ is the fixed field of $\text{Aut}_k(F)$
5. F/k is separable, and if K/F is an algebraic extension and $\sigma \in \text{Aut}_k(K)$, then $\sigma(F) = F$
6. The Galois correspondence for F/k is a bijection

***Proof*:**
Many of these have already been shown to be equivalent. We have shown:

- $1 \Leftrightarrow 2$ in theorem 19.5.13
- $2 \Leftrightarrow 3$ in corollary 19.6.21
- $3 \Leftrightarrow 4$ follows from proposition 20.1.12, since $[F : F^{\text{Aut}_k(F)}] = |\text{Aut}_k(F)|$, and since $k \subseteq F^{\text{Aut}_k(F)}$, we have that

$$k = F^{\text{Aut}_k(F)} \text{ if and only if } |\text{Aut}_k(F)| = [F : k]$$

- $2 \Leftrightarrow 5$ follows from the 3rd equivalence of theorem 19.5.13 along with the fact that finite separable extensions are simple (theorem 19.6.20)

Thus, we will show $6 \Rightarrow 4$ and $1 \Rightarrow 6$, which will complete the chain of implications.

Starting with $6 \Rightarrow 4$, assume the galois correspondence is bijective, and consider $E = F^{\text{Aut}_k(F)}$. By proposition 20.1.12, $\text{Aut}_{F^{\text{Aut}_k(F)}}(F) = \text{Aut}_k(F)$, and so E and $F^{\text{Aut}_k(F)}$ map to the same subgroup: $\text{Aut}_k(F) = \text{Aut}_E(F)$. Since the correlation is bijective, it must be that $k = E$, implying 4.

Next, we will show $1 \Rightarrow 6$. Since F/k is a finite extension, by proposition 20.1.12, we already know the Galois correspondence is surjective (i.e., has a right-inverse), so it suffice to show it's injective, or equivalently that it has a left-inverse. To that end, we need to show that every intermediate field E equals the fixed field of the corresponding subgroup $\text{Aut}_E(F)$, that is $E = F^{\text{Aut}_E(F)}$. So, pick some E such that $k \subseteq E \subseteq F$. Since F is the splitting field for some separable polynomial $f(x) \in k[x] \subseteq E[x]$, we see that F is the splitting field of the separable polynomial $f(x)$ over E (i.e., condition (1) holds for F/E too). Since $1 \Leftrightarrow 4$, then $E = F^{\text{Aut}_E}(F)$, thus $1 \Rightarrow 6$ completing the proof.

It can be helpful to have the following visual to keep track of where intermediate fields are with

respect to their galois group:

$$\begin{aligned} \mathrm{Aut}_E(F) &= G \\ E &= F^G \end{aligned}$$

Definition 20.1.14: Galois Extension

Let F/k be a finite extension. Then F is called *Galois* or F/k is called a *Galois extension* if it satisfies any of the conditions in theorem 20.1.13.

Note that we have limited the definition to *finite galois extensions*, due to the requirement to bring in more tools to study the infinite equivalence. Nothing is lost in doing so, since infinite galois extensions will naturally generalize and improve upon the results we will present. From now on, we will take galois extension to mean finite galois extension.

Corollary 20.1.15: Galois Extension Of Char 0

Let F/k be an extension of characteristic 0. Then F is galois over k if and only if F is finite and normal over k

Note that the finite condition was only added since we are focusing on finite Galois extensions.

***Proof*:**
If F is galois then it is *a priori* normal. Conversely, if F is finite and normal, then by corollary 19.6.8, any algebraic extension of F is separable, and hence by theorem 20.1.13, it is Galois.

Definition 20.1.16: Galois Group

Let F/k be a Galois extension. Then the corresponding automrophsim group $\mathrm{Aut}_k(F)$ is called the *galois group* of the extension. We will denote it by $\mathrm{Gal}_k(F)$ or $\mathrm{Gal}(F/k)$

The symbol $\mathrm{Gal}_k(F)$ is simply to emphasize we are working over a Galois extension, and does not reflect any additional structrue or data given to $\mathrm{Aut}_k(F)$.

Definition 20.1.17: Galois Group Of A Polynomial

Let $f(x)$ be a separable polynomial over $k[x]$. Then the *galois group* $\mathrm{Gal}_k(f(x))$ is the galois group of the splitting field of $f(x)$).

Definition 20.1.18: Abelian and Cyclic Extensions

Let F/k be a galois extension. Then F is called a *cyclic* (resp. *abelian*) extension if it's corresponding Galois group is cyclic (resp. abelian)
More generally, if the Galois group G has some property (ex. nilpotent, solvable, free), then the respetive extension is said to have that same property (ex. nilpotent extension, solvable extension, free extension)

Note that any vocabulary already used (like simple extension) will be prioritized over the group theory vocabulary (a simple extension is not related to simple group)

The equivalent conditions for Galois extensions gives us many details on results we have encountered earlier:

20.1.19 Remark

1. For any $H \leqslant \mathrm{Aut}_k(F)$, F/F^H is a Galois extension, and every intermediate field $k \subseteq E \subseteq F$ appears as a fixed field for a unique $H \leqslant \mathrm{Aut}_k(F)$ (If F/k is not Galois, this is not the case, like for $\mathbb{Q}(\sqrt[3]{2})/\mathbb{Q}$). This also means that by the 4th condition of Galois extension equivlences:
$$F^H = F^{\mathrm{Aut}_{F^H}(F)}$$
and since every intermediate field appears as a fixed field, we get that:
$$E = F^{\mathrm{Aut}_E(F)}$$

2. Let F/k be any finite extension. Then $|\mathrm{Aut}_k(F)|$ divides $[F:k]$. Taking any $G = \mathrm{Aut}_k(F)$, then
$$[F:k] = [F:F^G][F^G:k] \overset{!}{=} |\mathrm{Aut}_{F^{\mathrm{Aut}_k(F)}}(F)|[F^G:k] = |\mathrm{Aut}_k(F)|[F^G:k]$$
where $\overset{!}{=}$ comes from theorem 20.1.13(3). If F/k is Galois, then $F^G = k$, meaninig $|\mathrm{Aut}_k(F)|[F^G:k] = |\mathrm{Aut}_k(F)|[k:k] = |\mathrm{Aut}_k(F)|$.

3. Let F/k be a Galois extension. Then $|\mathrm{Aut}_k(F)|$ divides $|\mathrm{Aut}_{F^H}(F)|$. Taking any $H \leqslant \mathrm{Aut}_k(F)$ and $G = \mathrm{Aut}_k(F)$, then
$$|\mathrm{Aut}_k(F)| = [F:k] = [F:F^H][F^H:k] = |\mathrm{Aut}_{F^H}(F)|[F^H:k]$$
Switching up the notation, this means that $|G| = |H|[F^H:k]$, meaning $[F^H:k]$ is the index of H in G: $[F^H:k] = [G:H]$. The fact that it equals to the index means that it corresponds bijectively with the cosets $g\mathrm{Aut}_k(F^H)$ where $g \in \mathrm{Aut}_k(F)$, however it is yet to be shown how these two sets can correspond, only that they are the same size. Theorem 20.1.23 says when this set of cosets forms a group.

4. It may be really difficult to figure out if we have found all intermediate fields of an infinite in general, namely since in general, there are infinitely many possible choices. However, it is relatively easy to find the subgroups of a finite group! Hence, using finite group theory allows us to bring in the powerful tools having that finiteness brings (including Sylow's theorems).

5. Note how the 5th condition is almost the condition for an extension being normal, where just also assumed that the extension is separable. Note that the 5th condition still works if the extension is not separable. This can motivate the idea that we can somhow make separability a superfluous condition given some appropriate generalization, and indeed we can. If we replace Galois Group with an appropriate *algebraic group*, then we can recover the bijective correspondence[a]

6. Given the base field is perfect, for any extension F/k, we can always extend it to its normal closure $N/F/k$, which is normal over k, and so is Galois. Hence, many field theory problems over $\mathbb{Q}$ can be translated "wlog" to Galois theory

[a] algebraic groups are schemes (with with a group structure), for which one of the motivations for their invention was to distinguish roots higher multiplicities at a point

If $E = F^H$, the last observation can be seen visually as:

$$\begin{array}{ccc} F & & \\ | & \} & |H|=[F:E] \\ E & & \\ | & \} & |G:H|=[E:k] \\ k & & \end{array}$$

Example 20.1.20: Galois Groups

1. Let $K = \mathbb{Q}(\sqrt{2})/\mathbb{Q}$. Then since $[K : \mathbb{Q}] = 2.$ and $|\text{Aut}(K/\mathbb{Q})| = 2$ (as we have seen in example 20.1.4), then K is galois with galois group

   $$\text{Gal}(\mathbb{Q}(\sqrt{2})/\mathbb{Q}) = \{1, \sigma\} \cong \mathbb{Z}/2\mathbb{Z}$$

   With the identity automorphism and

   $$a + b\sqrt{2} \mapsto a - b\sqrt{2}$$

2. More generally, let K be any quadratic extension of F $(K = F(\sqrt{D}))$. If $\text{ch}(K) \neq 2$, then K is Galois.

3. The extension $\mathbb{Q}(\sqrt[3]{2})/\mathbb{Q}$ is *not* Galois, since $|\text{Aut}(\sqrt[3]{2})| = 1 < 3 = [\mathbb{Q}(\sqrt[3]{2}) : \mathbb{Q}]$. Notice that $\mathbb{Q} \subseteq \mathbb{Q}(\sqrt[3]{2})$ is not a fixed field, since the only fixed field is $\mathbb{Q}(\sqrt[3]{2})$.

4. Let $K = \mathbb{Q}(\sqrt{2}, \sqrt{3})$ be an extension of $\mathbb{Q}$. Then since K is the splitting field of $(x^2-2)(x^2-3)$, it Galois. To determine its Galois group, we know from example 19.3.12 that $[K : \mathbb{Q}] = 4$, giving us the amount of automorphisms to look for. Since $\sqrt{2} \notin \mathbb{Q}(\sqrt{3})$, by the fixed roots criterion, we see that any automorphism $\sigma \in \text{Aut}_{\mathbb{Q}}(K)$ must map $\sqrt{2}$ to $\pm\sqrt{2}$, and since $\sqrt{3} \notin \mathbb{Q}(\sqrt{2})$, we see that any automorphism $\tau \in \text{Aut}_{\mathbb{Q}}(K)$ must map $\sqrt{3}$ map $\pm\sqrt{3}$.

   Going through defining a σ and a τ by permuting $\sqrt{2}$ and $\sqrt{3}$ we see that:

   $$\text{Gal}(K/\mathbb{Q}) = \{1, \sigma, \tau, \sigma\tau\} \cong V_4 \cong \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z}$$

   Next, we can use proposition 20.1.9 to find the associated fixed field given the subgroups of

$\mathrm{Gal}(K/\mathbb{Q})$. Using some arithmetic, we see that:

$$\begin{array}{cc} \{1\} & \mathbb{Q}(\sqrt{2},\sqrt{3}) \\ \{1,\sigma\} & \mathbb{Q}(\sqrt{3}) \\ \{1,\sigma\tau\} & \mathbb{Q}(\sqrt{6}) \\ \{1,\tau\} & \mathbb{Q}(\sqrt{2}) \\ \{1,\sigma,\tau,\sigma\tau\} & \mathbb{Q} \end{array}$$

which exhausts all possible intermediate fields of $\mathbb{Q}(\sqrt{2},\sqrt{3})/\mathbb{Q}$

5. Take the splitting field of x^4-2 (say we choose adjoints $\mathbb{Q}(i,\sqrt[4]{2})$). Since $\mathrm{ch}(\mathbb{Q})=0$, the polynomial must be separable, and hence $\mathbb{Q}(i,\sqrt[4]{2})$ must be Galois. Then we know that:

$$[\mathbb{Q}(i,\sqrt[4]{2}):\mathbb{Q}] = [\mathbb{Q}(i,\sqrt[4]{2}):\mathbb{Q}(\sqrt[4]{2})][\mathbb{Q}(\sqrt[4]{2}):\mathbb{Q}] = 4\cdot 2 = 8$$

Telling us the Galois group has 8 elements. Since $i^n\sqrt[4]{2}$ are the 4 roots of x^4-2, we see that

$$\mathrm{Gal}_{\mathbb{Q}}(\mathbb{Q}(i,\sqrt[4]{2})) \leqslant S_4$$

Since $|\mathrm{Gal}_{\mathbb{Q}}(\mathbb{Q}(i,\sqrt[4]{2}))| = 2\cdot 4$, $\mathrm{Gal}_{\mathbb{Q}}(\mathbb{Q}(i,\sqrt[4]{2}))$ has a Sylow 2-subgroup of S_4. By Sylow's 2nd theorem (theorem 4.8.6) this group then *must* be D_4.

This makes finding the automorphisms quite easily. Notice that the automorphism σ:

$$\begin{cases} \sqrt[4]{2} \longrightarrow i\sqrt[4]{2} \\ i \longrightarrow i \end{cases}$$

is cyclic of order 4, and the automorphism τ:

$$\begin{cases} \sqrt[4]{2} \longrightarrow \sqrt[4]{2} \\ i \longrightarrow -i \end{cases}$$

is cyclic of order 2, and that:

$$\sigma\tau = \tau^{-1}\sigma$$

Which gives us that $\mathrm{Gal}_{\mathbb{Q}}(\mathbb{Q}(i,\sqrt[4]{2})) \cong D_4$! We correspond the subgroups with the intermediate fields in example 20.1.22.

6. As we have seen with cyclotomic fields, by proposition 19.7.9,
$$\mathrm{Aut}_{\mathbb{Q}}(\mathbb{Q}(\zeta_n)) \cong (\mathbb{Z}/n\mathbb{Z})^\times$$
giving us a Galois group for every $n \in \mathbb{N}_{>0}$.

7. By theorem 19.7.10, all finite field are Galois, since they are the splitting field over the separable polynomial $x^{p^d} - x$. As we have seen in proposition 19.7.19, the galois group is cyclic of order d:
$$\mathrm{Aut}_{\mathbb{F}_p}(\mathbb{F}_{p^d}) \cong \mathbb{Z}/d\mathbb{Z}$$
and is generated by the frobenius k-automorphism $x \mapsto x^p$

8. The extension $\mathbb{F}_2(x^{1/2})/\mathbb{F}_2(x)$, with $x^{1/2}$ a root of $y^2 - x$, is normal but not separable, and so it is not Galois (theorem 20.1.13(2)). In characteristic 2, $y^2 - x = (y - x^{1/2})^2$, so $\mathbb{F}_2(x^{1/2})$ is a splitting field of $y^2 - x$ over $\mathbb{F}_2(x)$, hence normal (theorem 19.5.13). The polynomial $y^2 - x$ has no root in $\mathbb{F}_2(x)$, since $(g/h)^2 = x$ with $g, h \in \mathbb{F}_2[x]$ would give $2\deg g = 1 + 2\deg h$, so it is irreducible (proposition 11.3.5), the minimal polynomial of $x^{1/2}$, with the repeated root $x^{1/2}$.

The correspondence by theorem 20.1.13 is in fact even stronger: we can correspond the intermediate lattice to the subgroup lattice. The first extension of the theorem is to give the correspondence between the lattices of subgroups of the galois group and of the field extensions. To show two lattices coresond, we need to show that if A_1 and A_2 are two objects, then A_1A_2 (i.e. the smallest object containing both A_1 and A_2) corresponding to B_1B_2, or if the relation is contravariant, A_1A_2 corresponds to $B_1 \cap B_1$. This is what we show with subgroups and intermediate fields:


Theorem 20.1.21: Fundamental Theorem Of Galois Theory II

Let F/k be a Galois extension. Then the Galois correspondence is an inclusion-reversing isomorphism between the lattice of intermediate subfield of F/k with the lattice of subgroups of $\mathrm{Aut}_k(F)$.


In particular, If E_1, E_2 are intermediate fields and G_1, G_2 are the correspondong subgroups of $\mathrm{Aut}_k(F)$, then $E_1 \cap E_2$ coresponds to $\langle G_1, G_2\rangle$ and E_1E_2 corresponds to $G_1 \cap G_2$

***Proof*:**
From theorem 20.1.13, we get the bijection between the intermediate fields and the subgroups of $\mathrm{Gal}_k(F)$, and from the 3rd property of the Galois Correspondence (proposition 20.1.9), we get that:
$$\mathrm{Aut}_{E_1E_2}(F) = G_1 \cap G_2 \qquad F^{\langle G_1, G_2\rangle} = E_1 \cap E_2$$
completing the proof.

We usually write the lattice of fields with k on the bottom and F on top, while the lattice of groups usualy has $\{e\}$ on top and $\mathrm{Aut}_k(F)$ on bottom to more easily associate the two lattices:




Some authors mark the Galois group though their own edges:




Example 20.1.22: Lattice Correspondence

1. As we have shown in example 20.1.20(3), where we corresponded the subgroups of $\mathrm{Gal}_{\mathbb{Q}}(\mathbb{Q}(\sqrt{2},\sqrt{3}))$ with the intermediate fields $\mathbb{Q} \subseteq E \subseteq \mathbb{Q}(\sqrt{2},\sqrt{3})$, we found that $\mathrm{Gal}_{\mathbb{Q}}(\mathbb{Q}(\sqrt{2},\sqrt{3})) \cong \mathbb{Z}_2 \times \mathbb{Z}_2$ and intermediate fields for each subgroup. We can make this result more precise. If the subgroup lattice is:




then the corresponding intermediate field lattice is:




We can futhermore deduce that there are *no* further intermediate extensions $k \subseteq E \subseteq F$.

2. As we have shown in example 20.1.20(4), $x^4 - 2$ has splitting field $\mathbb{Q}(i, \sqrt[4]{2})$ with Galois


group $\text{Gal}_{\mathbb{Q}}(\mathbb{Q}(i, \sqrt[4]{2})) = D_4$. Then:




with corresponding intermediate field lattice:



3. Take $\mathbb{F}_{64}/\mathbb{F}_2$, which is a degree 6 extension with Galois group $\text{Aut}_{\mathbb{F}_2}(\mathbb{F}_{64}) \cong \mathbb{Z}/6\mathbb{Z}$. the subgroup lattice is:



which corresponds to:



The next result comes from recalling that if $k \subseteq E \subseteq F$ is a series of field extensions where F/k is normal, this does not imply E/k is normal (as we have discussed in proposition 19.5.16 and example 19.5.17). Intuitively, this can be thought of as E having some but not all the required roots so that F is normal (ex. $\mathbb{Q} \subseteq \mathbb{Q}(\sqrt[3]{2}) \subseteq \mathbb{Q}(\sqrt[3]{2}, \varphi)$). However, it is sometimes the case that the intermediate fields are normal (ex. $Q \subseteq \mathbb{Q}(\sqrt{2}) \subseteq \mathbb{Q}(\sqrt{2}, \sqrt{3})$). We may ask when more generally is an extension E/k also normal, or more generally Galois? The following theorem answers that question:

Theorem 20.1.23: Fundamental Theorem Of Galois Theory III

Let F/k be a galois extension, and let E be an intermediate field. Then E/k is Galois if and only if $\mathrm{Aut}_E(F)$ is *normal* in $\mathrm{Aut}_k(F)$. If this is the case, then

$$\mathrm{Aut}_k(E) = \mathrm{Aut}_k(F)/\mathrm{Aut}_E(F)$$

Hence, *normal* subgroups arise from *normal* extensions. In fact, the term "normal" originate in field theory, and the term normal subgroup was coined after it's field theory counterpart.

The proof essentially comes down to a couple of key observations about the cosets of $\mathrm{Aut}_k(F)/\mathrm{Aut}_E(F)$ and how we can surmise information about them through group actions! We have already observed in box 20.1.19 that E/k has the same cardinality as $\{g\mathrm{Aut}_E(F) \mid g \in \mathrm{Aut}_k(F)\}$. We will make this correspondence more precise.

By theorem 19.5.13, a finite extension E/k is normal if and only if $\iota(E) = E$ for every k-homomorphism $\iota \colon E \to \overline{k}$.

Let F/K be a Galois extension. Identify $F \subseteq \overline{k}$ within some algebraic closure of $\overline{k}$. Let $k \subseteq E \subseteq F$ be some intermediate field, and consider:

$$I = \left\{ \iota : E \to \overline{k} \;\middle|\; \iota \text{ is a } k\text{-homomorphism} \right\} = \mathrm{Hom}_k(E, \overline{k})$$

We can equivalently see E/k as an arbitrary extension of k where for some $\iota \in I$, $\iota(E) \subseteq F$.

Claim 1: for all $\iota \in I$, $\iota(E) \subseteq F$

Proof. Let ι be a $\iota \in I$ such that $\iota(E) \subseteq F$. Since E is separable (since $\iota(E) \subseteq F$ and F is separable) and finite, is is simple by theorem 19.6.20, Thus $E = k(\alpha)$ for some $\alpha \in \overline{k}$ and α is the root some minimal polynomial over k, $m_{\alpha,k}(x)$. Since $\iota(\alpha)$ determines ι, looking at where it maps is all that

matters. Since $\iota(\alpha)$ is *some* root of the minimum polynomial $m_{\alpha,k}(x)$, and F is normal, F contains *all* roots of the minimal polynomial. But then, for any ι, $\iota(E) \subseteq F$, as we sought to show. □

Notice that

Claim 2: $\mathrm{Aut}_k(F)$ acts on I: for $g \in \mathrm{Aut}_k(F)$ and $\iota \in I$, $g \circ \iota \in I$

Proof. Since $\iota(E) \subseteq F$, and $g : F \to F$, we can intermret ι as $\iota : E \to F$ and compose the functions □

claim 3: $\mathrm{Aut}_k(F)$ is transitive on I (i.e. on $\mathrm{Hom}_k(E, \overline{k})$)

Proof. We need to show that for any $\iota_1, \iota_2 \in I$, $g \circ \iota_1 = \iota_2$. This follows from uniqueness of the splitting field. Since $\iota_1(E)$ and $\iota_2(E)$ each contain k and are each contained in F, and F is a splitting field over k for some polynomial, say $f(x)$ (since F is Galois, it follows from theorem 20.1.13). Hence, *a fortiori*, F must be the splitting field of $f(x)$ over $\iota_1(E)$ and over $\iota_2(E)$. Note that:

$$\iota_2 \circ \iota_1^{-1} : \iota_1(E) \to \iota_2(E)$$

is an k-isomorphism, and hence by the uniqueness of the splitting field, this isomorphism is extended to a k-isomorphism:

$$g : F \to F$$

By construction, $g|_{\iota_1(E)} = \iota_2 \circ \iota_1^{-1}$, or equivalently:

$$g \circ \iota_1 = \iota_2$$

as we sought to show. □

Thus, the galois group $\mathrm{Gal}_k(F)$ acts transitively on $\hom_k(E, \overline{k})$.

Let $\iota_0 \in I$ be the inclusion of E in $\overline{k}$. Its stabilizer in $\mathrm{Aut}_k(F)$ is $\mathrm{Aut}_E(F)$, the subgroup of elements that restrict to the identity on E. Thus, by the Orbit-Stabilizer Theorem, we can deduce the following result:

Let $G = \mathrm{Aut}_k(F)$. Then consdering I as a G-set, I is isomorphic to the set of left-cosets of $\mathrm{Aut}_E(F)$ in $\mathrm{Aut}_k(F)$

20.1.24 key Isomorphism

$$\hom_k(E, \overline{k}) \quad \cong_G \quad \{g\mathrm{Aut}_E(F) \mid g \in \mathrm{Aut}_k(F)\}$$

***Proof*:**
of theorem 20.1.23

Let $G = \mathrm{Aut}_k(F)$ and $I = \left\{\iota : E \to \overline{k} \;\middle|\; \iota \text{ is a } k\text{-homomorphism}\right\}$. Then I is a G-set (Claim 2), transitive by Claim 3. Let $\iota_0 \in I$ be the inclusion $E \subseteq F \subseteq \overline{k}$. The stabilizer of $\iota \in I$ is $\mathrm{Aut}_{\iota(E)}(F)$, since $g \circ \iota = \iota$ exactly when g fixes $\iota(E)$ pointwise. For $g \in G$, $h \circ g \circ \iota = g \circ \iota$ if and only if $(g^{-1}hg) \circ \iota = \iota$, so the stabilizer of $g \circ \iota$ is $g\mathrm{Aut}_{\iota(E)}(F)g^{-1}$. By Claim 3 every $\iota \in I$ equals $g \circ \iota_0$ for some $g \in G$, hence

$$\mathrm{Aut}_{\iota(E)}(F) = g\mathrm{Aut}_E(F)g^{-1}$$

Thus, if $\mathrm{Aut}_E(F)$ is normal, $\mathrm{Aut}_{\iota(E)}(F) = \mathrm{Aut}_E(F)$ for every $\iota \in I$, and the bijectivity of the Galois correspondence for F/k (theorem 20.1.13, item 6) gives $\iota(E) = E$. As E/k is finite and $\overline{k}$ is an algebraic closure of E, E/k is normal by $3 \Rightarrow 1$ of theorem 19.5.13, and it is separable because F/k is, so E/k is Galois (theorem 20.1.13).

Conversely, if E/k is galois, then $\iota(E) = E$ for all ι ($1 \Rightarrow 3$ of theorem 19.5.13, as E/k is finite and normal). Define the homomorphism ρ which takes $g \in \mathrm{Aut}_k(F)$ and restricts it to $E[= \iota(E)]$:

$$\rho : \mathrm{Aut}_k(F) \to \mathrm{Aut}_k(E)$$

This homomorphism is surjective (since the G-action acts transitively on I), and $\ker(\rho)$ is all automorphism that restrict to the identity on E, that is, $\mathrm{Aut}_E(F)$. But then, we know that the kernel of a group homomorphism is normal, and by the 1st isomorphism theorem for groups:

$$\mathrm{Aut}_k(F)/\mathrm{Aut}_E(F) \cong \mathrm{Aut}_k(E)$$

completing the proof.

The correspondence turns the action of $\mathrm{Aut}_k(F)$ on intermediate fields into conjugation of subgroups: if E corresponds to $H = \mathrm{Aut}_E(F)$, then for any $\sigma \in \mathrm{Aut}_k(F)$, $\sigma(E)$ corresponds to $\mathrm{Aut}_{\sigma(E)}(F) = \sigma H \sigma^{-1}$, since $\tau \in \mathrm{Aut}_k(F)$ fixes $\sigma(E)$ pointwise exactly when $\sigma^{-1}\tau\sigma$ fixes E pointwise.

Corollary 20.1.25: Isomorphism Of Categories

Let E/k be a Galois extension. Let $\mathbf{Fld}_k^E$ be the collection of fields F such that $k \subseteq F \subseteq E$ whose morphisms are k-homomorphisms and $\mathcal{O}_G$ where $G = \mathrm{Aut}_k(E)$ be the category whose objects are left G-sets G/H for every $H \leqslant G$ and the morphisms are G-equivariant maps $G/H \to G/K$. Then as categories, $\mathcal{O}_G^{\mathrm{op}} \cong \mathbf{Fld}_k^E$

***Proof*:**
Write $G = \mathrm{Aut}_k(E)$ throughout.

The morphisms of $\mathcal{O}_G$. A G-equivariant map $\psi : G/H \to G/K$ is determined by $\psi(H)$, since $\psi(gH) = g\psi(H)$. Writing $\psi(H) = \gamma K$, the recipe $gH \mapsto g\gamma K$ is well defined exactly when $h\gamma K = \gamma K$ for every $h \in H$, that is exactly when

$$\gamma^{-1} H \gamma \subseteq K$$

and two elements γ, γ' subject to this give the same map if and only if $\gamma K = \gamma' K$. So the morphisms $G/H \to G/K$ are exactly the maps $\psi_\gamma : gH \mapsto g\gamma K$ with $\gamma^{-1}H\gamma \subseteq K$, indexed by the coset γK. Composing, $\psi_\delta(\psi_\gamma(gH)) = \psi_\delta(g\gamma K) = g\gamma\delta L$, so

$$\psi_\delta \circ \psi_\gamma = \psi_{\gamma\delta}$$

and ψ_1 is the identity.

The functor. Send the object G/H to the fixed field E^H, and send the morphism $\psi_\gamma : G/H \to G/K$ to the map

$$\Phi(\psi_\gamma) : E^K \to E^H \qquad x \mapsto \gamma x$$

This lands where claimed: for $x \in E^K$ and $h \in H$ we have $\gamma^{-1}h\gamma \in K$, so $h(\gamma x) = \gamma(\gamma^{-1}h\gamma)x = \gamma x$, and γx is fixed by H. It does not depend on the representative: if $\gamma' = \gamma\kappa$ with $\kappa \in K$ then $\gamma' x = \gamma\kappa x = \gamma x$ for $x \in E^K$. It is a k-homomorphism because γ is. Finally $\Phi(\psi_{\gamma\delta})$ is $x \mapsto \gamma\delta x$, which is $\Phi(\psi_\gamma) \circ \Phi(\psi_\delta)$, and $\Phi(\psi_1) = \mathrm{id}$. So Φ is a functor $\mathcal{O}_G^{\mathrm{op}} \to \mathbf{Fld}_k^E$.

Bijective on objects. Since E/k is Galois, the Galois correspondence is a bijection by theorem 20.1.13(6), with $H \mapsto E^H$ and $F \mapsto \mathrm{Aut}_F(E)$ mutually inverse between the subgroups of G and the intermediate fields of E/k. The objects of $\mathcal{O}_G$ are indexed by the subgroups $H \leqslant G$, so Φ is a bijection on objects.

Bijective on morphisms. For injectivity, suppose ψ_γ and $\psi_{\gamma'}$ are morphisms $G/H \to G/K$ with $\gamma x = \gamma' x$ for all $x \in E^K$. Then $\gamma'^{-1}\gamma$ fixes E^K pointwise, so $\gamma'^{-1}\gamma \in \mathrm{Aut}_{E^K}(E)$, which is K by proposition 20.1.12. Hence $\gamma K = \gamma' K$ and the two morphisms coincide.

For surjectivity, let $\sigma : E^K \to E^H$ be a k-homomorphism. By theorem 20.1.13(1), E is the splitting field over k of a separable $f(x) \in k[x]$. The roots of f generate E over k, hence over any intermediate field, so E is also the splitting field of f over E^K and over $\sigma(E^K)$. The coefficients of f lie in k and σ fixes k, so $\sigma(f) = f$, and theorem 19.5.10 extends the isomorphism $\sigma : E^K \to \sigma(E^K)$ to an isomorphism $\gamma : E \to E$ fixing k, that is to an element $\gamma \in G$. For $x \in E^K$ and $h \in H$ we get $h\gamma x = h\sigma x = \sigma x = \gamma x$, since $\sigma x \in E^H$, so $\gamma^{-1}h\gamma$ fixes E^K pointwise and therefore lies in $\mathrm{Aut}_{E^K}(E) = K$. Thus $\gamma^{-1}H\gamma \subseteq K$, the map $\psi_\gamma : G/H \to G/K$ is a morphism of $\mathcal{O}_G$, and $\Phi(\psi_\gamma) = \sigma$.

A functor that is bijective on objects and bijective on each set of morphisms is an isomorphism of categories, so $\mathcal{O}_G^{\mathrm{op}} \cong \mathbf{Fld}_k^E$.

Example 20.1.26: Application To Lattices

In the lattices of example 20.1.22(2), for $F = \mathbb{Q}(i, \sqrt[4]{2})$, the intermediate fields $\mathbb{Q}(\sqrt[4]{4}) = \mathbb{Q}(\sqrt{2})$, $\mathbb{Q}(i)$, $\mathbb{Q}(\sqrt[4]{4}i) = \mathbb{Q}(i\sqrt{2})$ and $\mathbb{Q}(i, \sqrt[4]{4}) = \mathbb{Q}(i, \sqrt{2})$ are the splitting fields over $\mathbb{Q}$ of the separable polynomials x^2-2, x^2+1, x^2+2 and $(x^2-2)(x^2+1)$, so they are Galois over $\mathbb{Q}$ (theorem 20.1.13(1)). By theorem 20.1.23, the corresponding subgroups $\langle a^2, b\rangle$, $\langle a\rangle$, $\langle a^2, ab\rangle$ and $\langle a^2\rangle$ are normal in D_4. The polynomial $x^4 - 2$ is irreducible over $\mathbb{Q}$ (corollary 11.3.11, with $p = 2$), and the field $\mathbb{Q}(\sqrt[4]{2}) \subseteq \mathbb{R}$ contains its root $\sqrt[4]{2}$ but not its root $i\sqrt[4]{2}$, which is not real. So $\mathbb{Q}(\sqrt[4]{2})/\mathbb{Q}$ is not normal (definition 19.5.12), hence not Galois, and by theorem 20.1.23 the corresponding subgroup $\langle b\rangle$ is not normal in D_4.

20.1.27 Foreshadowing Can give the connection between Galois group/extensions to Algebraic geometry with regular covers and deck transformations

Exercise 20.1.1

1. Let $L = \mathbb{Q}(\zeta_p)$ where p is an odd prime. Show there exists a subfield $K \subseteq L$ such that $K = \mathbb{Q}(\sqrt{p'})$ where
$$p' = \begin{cases} p & p \equiv 1 \bmod 4 \\ -p & p \equiv 2, 3 \bmod 4 \end{cases}$$

2. Let $K/\mathbb{Q}$ be an odd Galois Extension, Show that L must be totally real.

20.1.2 Composite Fields


We now take what we proved earlier and do two things with it: we extend the results for composite fields and we classify all cyclic Galois Extensions (given an appropriate restriction on the base field). Earlier exercises (exercises 19.6.2 (1) to 19.5.1 (2) and 19.2.1 (4)) ask to show that:

> If E/k and F/k are field extensions inside a common field (algebraic ones, for normality), and E/k is (finite/algebraic/normal/separable resp.), then EF/F is (finite/algebraic/normal/separable resp). If E/k and F/k are (finite/algebraic/normal/separable resp.) then EF/k is (finite/algebraic/normal/separable resp.)

Since [finite] Galois extensions are finite, normal, and separable, we see immediately that if E/k is Galois, then EF/F is Galois, and if E/k and F/k are Galois, so is EF/k. The natural question to ask is what's the galois group of a composite field and of EF/F:

Proposition 20.1.28: Galois Composite Fields I

Suppose E/k is Galois and F/k is any field extension. Then EF/F is Galois, and $\mathrm{Aut}_F(EF) \cong \mathrm{Aut}_{E\cap F}(E)$. Visually, we see that:



The reader should ponder why does F/k need to be finite for this theorem?

***Proof*:**
Using the Galois extension equivalences, we can quickly prove that EF/k is Galois, namely since E/k is Galois, it is the splitting field of a separable polynomial $p(x) \in k[x] \in F[x]$. The roots of $p(x)$ generate E over k ,and so they generate EF over F, i.e., EF is the splitting field of $p(x)$ over F, thus EF/F is a Galois Extension

To show that $\mathrm{Aut}_F(EF) \cong \mathrm{Aut}_{E\cap F}(E)$, we will first show we can embedd $\mathrm{Aut}_F(EF)$ into $\mathrm{Aut}_k(E)$, and then find that the subgroup of $\mathrm{Aut}_k(E)$ associated to this embedding is $\mathrm{Aut}_{E\cap F}(E)$. For the embedding, consider first any F-automorphism $\sigma : EF \to EF$ (and hence k-automorphism). Then we can restrict σ to E, giving us $\sigma : E \to \sigma(E)$. Since E is Galois, $\sigma(E) = E$. Thus, any element of $\mathrm{Aut}_F(EF)$ get's mapped to an element of $\mathrm{Aut}_k(E)$, that is, we have a natural group homomorphism:

$$\rho : \mathrm{Aut}_F(EF) \to \mathrm{Aut}_k(E)$$

This homomorphism is injective: If the only element that maps to the identity is the identity,

then we are done. Indeed, if $\sigma \in \mathrm{Aut}_k(E)$ is the identity on E, since any element $\mathrm{Aut}_F(EF)$ is the identity on F, the coresponding σ in $\mathrm{Aut}_F(EF)$ must be the identity on EF, showing injectivity.

Thus, $\mathrm{Aut}_F(EF)$ embeds into $\mathrm{Aut}_k(E)$, and so it is associated with some $H \leqslant \mathrm{Aut}_k(E)$. By proposition 20.1.12, $H = \mathrm{Aut}_{E^H}(E)$. It suffices to show that $E^H = E \cap F$. For the $\supseteq$ direction, since every $\sigma \in \mathrm{Aut}_F(EF)$ fixes F, the restriction $\rho(\sigma)$ fixes $E \cap F$, hence $E^H \supseteq E \cap F$. For the $\subseteq$ direction, take $\alpha \in E^H$. Then $\alpha \in E$. By definition, $F(\alpha)$ is in the fixed field of $\mathrm{Aut}_F(EF)$, which is F sinc F is Galois over EF/F (1st Galois Theorem, theorem 20.1.13(4)). Thus, $\alpha \in F$, and so $E^H \subseteq E \cap F$. Therefore, $H = E \cap F$, and:

$$\mathrm{Aut}_F(EF) \cong \mathrm{Aut}_{E\cap F}(E)$$

as we sought to show

Example 20.1.29: Composite Fields Determining Abelian Extensions

1. As we have seen in section 19.7.1, if ζ_n is the nth root of unity, $\mathbb{Q}(\zeta_n)$ is the splitting field of $x^n - 1$ over $\mathbb{Q}$, and hence is Galois since $\mathrm{ch}(\mathbb{Q}) = 0$. By proposition 19.7.9, $\mathrm{Aut}_{\mathbb{Q}}(\mathbb{Q}(\zeta_n)) \cong (\mathbb{Z}/n\mathbb{Z})^\times$.

   Now, let k be any field of characteristic 0. Then the splitting field K/k for $x^n - 1$ is the composite of k and $\mathbb{Q}(\zeta)$, namely $K = k(\zeta)$. Since $\mathbb{Q}(\zeta)/\mathbb{Q}$ is Galois and $k/\mathbb{Q}$ is a field extension, by proposition 20.1.28, we get that:

   $$\mathrm{Aut}_k(k(\zeta)) \cong \mathrm{Aut}_{\mathbb{Q}(\zeta)\cap k}(\mathbb{Q}(\zeta)) \leqslant \mathrm{Aut}_{\mathbb{Q}}(\mathbb{Q}(\zeta)) \cong (\mathbb{Z}/n\mathbb{Z})^\times$$

   showing that $\mathrm{Aut}_k(k(\zeta))$ is some subgroup of $(\mathbb{Z}/n\mathbb{Z})^\times$. in particular, *any* such extension *must* be abelian.

   The fact that every extension of the form $k(\zeta)$ is abelian is quite powerful. In fact, they are relatively easy to classify. The study of Galois extensions that are abelian(which also must contain n distinct roots of unity for some $n \in \mathbb{N}$) is called *Kummer Theory*. We touch a bit of Kummer theory in the following, since we need it for showing no quintic is unsolvable, and will later show that all finite abelian group show up as a field extension of $\mathbb{Q}$ in section 20.4.

2. Generalizing the results from the exercises, we know that if E/k and F/k are Galois, so is EF/k. Can you find a way to link $\mathrm{Gal}_k(EF)$ with $\mathrm{Gal}_k(E)$ and $\mathrm{Gal}_k(F)$? (Hint: Consider $\mathrm{Gal}_k(EF) \to \mathrm{Gal}_k(E) \times \mathrm{Gal}_k(F)$, $\sigma \mapsto (\sigma|_E, \sigma|_F)$)

Corollary 20.1.30: Order of Galois Composite

Let E/k be a galois extension and F/k be any finite extension. Then:

$$[EF : k] = \frac{[E : k][F : k]}{[E \cap F : k]}$$

***Proof*:**
By proposition 20.1.28, EF/F is Galois and $\mathrm{Aut}_F(EF) \cong \mathrm{Aut}_{E\cap F}(E)$. Moreover, $E/(E\cap F)$ is Galois: since E/k is Galois, E is the splitting field over k of some separable polynomial $f(x) \in k[x]$ by theorem 20.1.13(1), and the roots of f generate E over k, hence over the intermediate field $E\cap F$, so E is also the splitting field of the separable polynomial f over $E\cap F$. Applying theorem 20.1.13(3) to the two Galois extensions EF/F and $E/(E\cap F)$:

$$[EF:F] = |\mathrm{Aut}_F(EF)| = |\mathrm{Aut}_{E\cap F}(E)| = [E : E\cap F]$$

By the Tower Law (theorem 19.3.7) applied to $k \subseteq E\cap F \subseteq E$, we get $[E : E\cap F] = [E : k]/[E\cap F : k]$, and applied to $k \subseteq F \subseteq EF$:

$$[EF:k] = [EF:F][F:k] = [E:E\cap F][F:k] = \frac{[E:k][F:k]}{[E\cap F:k]}$$

as we sought to show.

Note that this formula does not hold in general if niether of the extensions is Galois.

Example 20.1.31: Failure of Formula with no Galois Extension
Let $k = \mathbb{Q}$, $E = \mathbb{Q}(\sqrt[3]{2})$, and $F = \mathbb{Q}(\zeta_3\sqrt[3]{2})$), since $EF = \mathbb{Q}(\zeta_3\sqrt[3]{2}), \sqrt{3}$ (with minimal polynomial $x^3 - 2$, and hence degree 6 extension) and:

$$6 = [\mathbb{Q}(\zeta_3\sqrt[3]{2})] \neq \frac{[\mathbb{Q}(\sqrt[3]{2}):\mathbb{Q}][\mathbb{Q}(\zeta_3\sqrt[3]{2}):\mathbb{Q}]}{[\mathbb{Q}:\mathbb{Q}]} = 9$$

Using this, we may answer the arguably more intesesting questions of the composite and intersection of fields being galois over the same base field:

Proposition 20.1.32: Galois Composite Fields II

Let $E/k, F/k$ be galois extensions of k. Then:

1. $E\cap F$ is galois over k
2. EF is galois over k. It's galois group is isomorphic to:
$$G = \{(\sigma,\tau) \mid \sigma|_{E\cap F} = \tau|_{E\cap F}\} \leqslant \mathrm{Gal}_k(E) \times \mathrm{Gal}_k(F)$$
3. If $E\cap F = k$, then:
$$\mathrm{Gal}_k(EF) \cong \mathrm{Gal}_k(E) \times \mathrm{Gal}_k(F)$$

***Proof*:**

1. Let $p(x) \in k[x]$ be irreducible and have a root $\alpha \in E\cap F$. Since $\alpha \in E$ and E/k is normal by theorem 20.1.13(2), p splits into linear factors over E, so all roots of p lie in E. The same argument in F puts all roots of p in F, hence all of them lie in $E\cap F$ and p splits over $E\cap F$. By definition 19.5.12, $E\cap F$ is normal over k. It is finite over k, being an intermediate field of the finite extension E/k, and it is separable over k, since each of its

elements lies in E and E/k is separable. By theorem 20.1.13(2), $E \cap F$ is Galois over k.

2. By theorem 20.1.13(1), E is the splitting field over k of a separable $f(x) \in k[x]$ and F is the splitting field over k of a separable $g(x) \in k[x]$. Let $h(x)$ be the product of the distinct monic irreducible factors of fg in $k[x]$. Each such factor divides f or g and so has distinct roots, and distinct monic irreducibles share no root, so h is separable. The roots of h are the roots of f together with those of g, and these generate EF over k, so EF is the splitting field of h over k and EF/k is Galois by theorem 20.1.13(1).

   Since E/k and F/k are Galois, theorem 20.1.13(5) gives $\sigma(E) = E$ and $\sigma(F) = F$ for every $\sigma \in \mathrm{Gal}_k(EF)$, so restriction defines a map

$$\rho : \mathrm{Gal}_k(EF) \to \mathrm{Gal}_k(E) \times \mathrm{Gal}_k(F) \qquad \sigma \mapsto (\sigma|_E , \sigma|_F)$$

   which is a group homomorphism. It is injective: an element of the kernel is the identity on E and on F, hence on the field EF they generate. Its image lies in G, because restricting $\sigma|_E$ and $\sigma|_F$ further to $E \cap F$ gives $\sigma|_{E\cap F}$ both times.

   It remains to count. By part (1), $E \cap F$ is Galois over k, so theorem 20.1.23 applied to $k \subseteq E \cap F \subseteq F$ gives $\mathrm{Gal}_k(F)/\mathrm{Gal}_{E\cap F}(F) \cong \mathrm{Gal}_k(E \cap F)$ through restriction. Hence restriction $\mathrm{Gal}_k(F) \to \mathrm{Gal}_k(E \cap F)$ is surjective with fibres the cosets of $\mathrm{Gal}_{E\cap F}(F)$, so for each $\sigma \in \mathrm{Gal}_k(E)$ the number of $\tau \in \mathrm{Gal}_k(F)$ with $\tau|_{E\cap F} = \sigma|_{E\cap F}$ is $|\mathrm{Gal}_{E\cap F}(F)|$. Therefore

$$|G| = |\mathrm{Gal}_k(E)| \cdot |\mathrm{Gal}_{E\cap F}(F)| = [E : k] \cdot [F : E \cap F] = \frac{[E : k][F : k]}{[E \cap F : k]}$$

   using theorem 20.1.13(3) on the Galois extensions E/k and $F/(E \cap F)$ and the Tower Law (theorem 19.3.7) on $k \subseteq E \cap F \subseteq F$. Here $F/(E \cap F)$ is Galois because F is the splitting field of the separable g over k, hence also over the intermediate field $E \cap F$. On the other side corollary 20.1.30 gives

$$|\mathrm{Gal}_k(EF)| = [EF : k] = \frac{[E : k][F : k]}{[E \cap F : k]}$$

   So ρ is an injection between finite sets of the same size and therefore carries $\mathrm{Gal}_k(EF)$ isomorphically onto G.

3. If $E \cap F = k$ then every element of $\mathrm{Gal}_k(E)$ and of $\mathrm{Gal}_k(F)$ restricts to the identity on $E \cap F$, so the condition cutting out G holds for every pair and G is all of $\mathrm{Gal}_k(E) \times \mathrm{Gal}_k(F)$. Part (2) then reads $\mathrm{Gal}_k(EF) \cong \mathrm{Gal}_k(E) \times \mathrm{Gal}_k(F)$.

Corollary 20.1.33: Galois Closure

Let F/k be a finite separable extension. Then there exists a minimal finite galois extension E/k such that $E/F/k$.

***Proof*:**
Simply take the composite of the splitting fields of the minimal polynomials for the basis of F over k (which is separable since F/k is separable), nad intersect all the galois extensions of k containing F.

Definition 20.1.34: Galois Closure

Let F/K be a finite separable extension. Then the smallest extension $E/F/k$ such that E/k is galois is called the *galois closure* of F over k.

Exercise 20.1.2

1. Show there exists fields E, F such that $[EF : F] \neq [F : E \cap F]$

20.1.3 A bit of Character Theory and Kummer Theory

Let F/K be a galois extension. Then each $\sigma \in \mathrm{Gal}_K(F)$ is also a K-linear isomorphism $F \to F$ of n-dimensional K-vector spaces. Thus, does σ have eigenvalues? Can it be diagonalized? How does each $\sigma \in \mathrm{Gal}_K(F)$ relate to each other? To start:

Lemma 20.1.35: Eigenvalues Are Roots of Unity

Let F/K be a galois extension and $\sigma \in \mathrm{Gal}_K(F)$. Then if σ has an eigenvalue λ, then λ is a root of unity

***Proof*:**
Let σ be as in the statement and assume $\sigma(\alpha) = \lambda\alpha$ where $\lambda \in K$. Then as $\mathrm{Gal}_K(F)$ is a finite group, the exists an n such that $\sigma^n = \mathrm{id}$. Thus:

$$\alpha = \mathrm{id}(\alpha) = \sigma^n(\alpha) = \lambda^n\alpha$$

Then $\lambda^n = 1$, hence λ is a root of unity.

Thus, σ is diagonalizable if K contains enough roots of unity. Such an extension is called a *Kummer extension* (see definition 20.4.2, the definition is delayed due to the need to consider the behaviour over different characteristic which is covered in section 20.4).

Next, we would like to know how each automorphism relates to each other. We shall use a concept from Character theory to frame the discussion:

Definition 20.1.36: Group Character

Let G be a group and L a field. Then a *[linear] character* (denoted χ) is a homomorphism from G to the multiplicative group of L:

$$\chi : G \to L^\times$$

Example 20.1.37: Group Character

For our purposes, any field homomorphism $\sigma : F \to K$ induces a character $\chi_\sigma : F^\times \to K^\times$ (since σ maps the multiplicative group of F into the multiplicative group of K). Note that χ_σ captures essentially all the mapping information of σ, since χ only omits mapping 0 from F to 0 from K, but we can simply deduce that. Thus, if we are working with χ_σ, we are showing that we do not want to remember that the additive structure is preserved.

Definition 20.1.38: Character Linearly Independent

The characters $\chi_1, ..., \chi_n$ of G are *linearly independent* over L if they are linearly independent as functions on G, i.e. for any $a_i \in L$

$$a_1\chi_1 + a_2\chi_2 + \cdots + a_n\chi_n = 0 \quad \text{if and only if} \quad a_i = 0, 1 \leq i \leq n$$

Note that the expression on the left hand side of the above equality is a function on G, and hence it means that the characters are linearly independent if, whenever

$$a_1\chi_1(g) + a_2\chi_2(g) + \cdots + a_n\chi_n(g) = 0 \qquad \text{for all } g \in G$$

then $a_i = 0$ for $1 \leq i \leq n$.

Theorem 20.1.39: Artin's Lemma

Let $\chi_1, ..., \chi_n$ be distinct characters of G with values in L. Then they are linearly independent over L

***Proof*:**

Suppose that the characters are linearly dependent, that is, there exist coefficients $a_1, ..., a_n \in L$, not all zero, with

$$a_1\chi_1 + a_2\chi_2 + \cdots + a_n\chi_n = 0$$

Among all such relations, choose one with the least number $m \geq 1$ of nonzero coefficients. The characters are distinct for any ordering, so we may renumber them so that this relation has $a_i \neq 0$ for $i \leq m$ and $a_i = 0$ for $i > m$. Thus, for any $g \in G$:

$$a_1\chi_1(g) + a_2\chi_2(g) + \cdots + a_m\chi_m(g) = 0 \tag{20.2}$$

Here $m \geq 2$: if $m = 1$, then $a_1\chi_1(g) = 0$ with $\chi_1(g) \in L^\times$, so $a_1 = 0$, which is not the case. Let g_0 be an element of G such that $\chi_1(g_0) \neq \chi_m(g_0)$ (which exists since $\chi_1 \neq \chi_m$). Since equation (20.2) holds for every element of G, we have that:

$$a_1\chi_1(g_0g) + a_2\chi_2(g_0g) + \cdots + a_m\chi_m(g_0g) = 0 \tag{20.3}$$

i.e., as each χ_i is a homomorphism,

$$a_1\chi_1(g_0)\chi_1(g) + a_2\chi_2(g_0)\chi_2(g) + \cdots + a_m\chi_m(g_0)\chi_m(g) = 0 \tag{20.4}$$

Now, multiplying equation (20.2) by $\chi_m(g_0)$ and subtracting equation (20.4), we get:

$$[\chi_m(g_0) - \chi_1(g_0)]a_1\chi_1(g) + \cdots + [\chi_m(g_0) - \chi_{m-1}(g_0)]a_{m-1}\chi_{m-1}(g) = 0$$

which holds for all $g \in G$. This is a relation among $\chi_1, \ldots, \chi_n$ with at most $m - 1$ nonzero coefficients, and its first coefficient $[\chi_m(g_0) - \chi_1(g_0)]a_1$ is nonzero, contradicting the minimality of m. Hence the characters are linearly independent, completing the proof.

Corollary 20.1.40: linear independence of Automorphisms (Dedekind's Lemma)

Let $\sigma_1, \sigma_2, ..., \sigma_n$ be distinct embeddings of K into L. Then they are linearly independent over L as functions on K. In particular, distinct automorphism of a field K are linearly independent over K as functions on K.

***Proof*:**

Each σ_i is an injective ring homomorphism (proposition 19.1.1), so it maps $K^\times$ into $L^\times$, and its restriction $\chi_i \colon K^\times \to L^\times$ is a homomorphism of multiplicative groups, that is, a character of $G = K^\times$ with values in L (definition 20.1.36). The characters $\chi_1, \ldots, \chi_n$ are distinct: if $\chi_i = \chi_j$, then σ_i and σ_j agree on $K^\times$, and also at 0, so $\sigma_i = \sigma_j$ and $i = j$. Now let $a_1, \ldots, a_n \in L$ with $a_1\sigma_1(y) + \cdots + a_n\sigma_n(y) = 0$ for every $y \in K$. Restricting to $y \in K^\times$ gives $a_1\chi_1 + \cdots + a_n\chi_n = 0$, so every $a_i = 0$ by theorem 20.1.39. The case of automorphisms is the case $L = K$, completing the proof.

Independence of automorphisms determines the structure of a Galois extension as a module over its Galois group. A finite Galois extension L/k with group G is a k-vector space of dimension $|G|$ carrying a G-action, so it is a $k[G]$-module of the right size to be free of rank one, and the normal basis theorem says that it is. Equivalently, L has a k-basis permuted simply transitively by G, in contrast with the bases $1, \alpha, \ldots, \alpha^{n-1}$ coming from a primitive element, on which G acts in no controlled way.

Theorem 20.1.41: Normal Basis Theorem

Let L/k be a finite Galois extension with group G, and put $n = [L : k] = |G|$. There exists $x \in L$ whose G-orbit $\{\sigma(x) \mid \sigma \in G\}$ is a k-basis of L. Such a basis is called a *normal basis*, and its existence says exactly that

$$L \cong k[G]$$

as $k[G]$-modules, so that L is free of rank one over the group ring.

***Proof*:**

Write $G = \{\sigma_1, \ldots, \sigma_n\}$ with $\sigma_1 = 1$. The two statements are equivalent: a k-basis of the form $\{\sigma(x) \mid \sigma \in G\}$ is precisely a $k[G]$-basis of L consisting of the single element x.

The criterion used throughout is this. For $x \in L$ the orbit $\{\sigma(x) \mid \sigma \in G\}$ is a k-basis if and only if

$$\det\left(\sigma_i^{-1}\sigma_j(x)\right)_{i,j} \neq 0$$

Indeed, suppose the determinant is non-zero and $\sum_j c_j\sigma_j(x) = 0$ with $c_j \in k$. Applying σ_i^{-1} and using that the c_j lie in k, hence are fixed, gives $\sum_j c_j\sigma_i^{-1}\sigma_j(x) = 0$ for every i. So the matrix annihilates the vector (c_j) and therefore $c = 0$. As there are n elements in the orbit and $\dim_k L = n$, independence is enough. The converse also holds, though it is not needed below: writing $v_j = \sigma_j(x)$ and $\tau_i = \sigma_i^{-1}$, which runs over G, the matrix is $(\tau_i(v_j))$, and if $v = wa$ for a k-basis w and $a \in \mathrm{GL}_n(k)$ then $\det(\tau_i(v_j)) = \det(\tau_i(w_l))\det(a)$, non-zero because $\det(\tau_i(w_l)) \neq 0$ by corollary 20.1.40. It is not the matrix of a k-linear map: for $x \in k^\times$ every entry equals x and the determinant vanishes for $n \geq 2$, so independence of automorphisms is doing the work here too.

Case 1: k infinite. Fix a k-basis $w_1, \dots, w_n$ of L and consider

$$g(X_1, \dots, X_n) = \det\left(\sum_l X_l\, \sigma_i^{-1}\sigma_j(w_l)\right)_{i,j} \in L[X_1, \dots, X_n]$$

This polynomial is not zero. By corollary 20.1.40 the automorphisms in G are linearly independent over L. Hence the $n \times n$ matrix $\big(\sigma(w_l)\big)_{\sigma,l}$ is invertible over L: an L-linear relation among its rows gives $\sum_\sigma a_\sigma \sigma$ vanishing on the k-basis w, hence, that map being k-linear, vanishing on all of L. Choose $(\xi_l) \in L^n$ with $\sum_l \xi_l\, \sigma(w_l) = 1$ for $\sigma = 1$ and 0 for every other $\sigma \in G$. Substituting $X_l = \xi_l$ turns the (i,j) entry into 1 when $\sigma_i^{-1}\sigma_j = 1$, that is when $i = j$, and into 0 otherwise, so $g(\xi) = \det(I_n) = 1$.

Now g has coefficients in L, not in k, so the familiar statement about polynomials over the field one substitutes from does not apply directly. What is needed is the infinite-subset form: *a non-zero polynomial in $L[X_1, \dots, X_n]$ cannot vanish on S^n for an infinite subset $S \subseteq L$.* This follows by induction on n, the case $n = 1$ being that a non-zero one-variable polynomial has finitely many roots (corollary 11.3.2): writing $g = \sum_d g_d(X_1, \dots, X_{n-1})X_n^d$ with some $g_{d_0} \neq 0$, induction gives $s \in S^{n-1}$ with $g_{d_0}(s) \neq 0$, and then $g(s, X_n)$ is a non-zero polynomial in one variable, so it has a non-root in S. Applying this with $S = k$, which is infinite, gives $t_1, \dots, t_n \in k$ with $g(t) \neq 0$. Put $x = \sum_l t_l w_l$. Then $\det(\sigma_i^{-1}\sigma_j(x)) = g(t) \neq 0$ and the criterion applies.

Case 2: k finite. Then L/k is an extension of finite fields, so G is cyclic, generated by the Frobenius σ. Regard L as a module over the polynomial ring $k[T]$ with T acting as σ. Because $\sigma^n = 1$, the minimal polynomial of σ as a k-linear operator on L divides $T^n - 1$, so it has degree at most n. It has degree exactly n: a relation $\sum_{i<n} c_i\sigma^i = 0$ with $c_i \in k$ not all zero would be a non-trivial L-linear dependence among the distinct automorphisms $1, \sigma, \dots, \sigma^{n-1}$, which corollary 20.1.40 forbids.

So the minimal polynomial of σ has degree $n = \dim_k L$. It divides the characteristic polynomial (proposition 14.3.10), which is monic of the same degree (proposition 13.5.2(1)), so the two are equal, and σ then admits a cyclic vector. That last step is theorem 14.3.6 together with proposition 14.3.1, which identifies the minimal polynomial as the largest invariant factor, and lemma 14.3.9(2), which makes the characteristic polynomial the product of the invariant factors: equality of degrees forces a single invariant factor, so $L \cong k[T]/(a_1)$ is cyclic over $k[T]$. Concretely there is $x \in L$ with $L = \operatorname{span}_k\{x, \sigma x, \dots, \sigma^{n-1}x\}$. That spanning set has n elements in an n-dimensional space, so it is a basis, and it is the G-orbit of x, completing the proof.

Proposition 20.1.42: Galois And Cyclic Extensions

Let F/k be an extension of degree m. Assume that k contains a primitive mth root of 1 and $\operatorname{char}(k)$ does not divide m. Then F/k is Galois and cyclic if and only if $F = k(\delta)$ with $\delta^m \in k$.

***Proof*:**
Let $\zeta \in k$ be a primitive m-th root of 1.

($\Leftarrow$) Let's say $F = k(\delta)$ with $\delta^m = c \in k$. Then all m roots of the polynomial $x^m - c$ are in F, in particular,

$$c, \zeta\delta, \zeta^2\delta, ..., \zeta^{m-1}\delta \in F$$

Furthermore, F must be generated by them. Hence F is the splitting field of the separable

polynomial $x^m - c$ in k (separable since $\mathrm{ch}(k)$ does not divide m). Thus, F is Galois

Next, to see that $\mathrm{Aut}_k(F)$ is cyclic, note that for any $\varphi \in \mathrm{Aut}_k(F)$, it is determined by $\varphi(\delta)$, which his necessarily a root of $x^m - c$, and so $\varphi(\delta) = \zeta^i \delta$ for some i determined up to a multiple of m. Then this can be used to define an isomorphism of $\mathrm{Aut}_k(F)$ with $\mathbb{Z}/m\mathbb{Z}$.

($\Rightarrow$) Conversely, assume that F/k is Galois and $\mathrm{Aut}_k(F)$ is cyclic (say, generated by φ). Since the automorphisms φ^i $(1 \leq i \leq m-1)$ are pairwise distinct, by corollary 20.1.40, they are linearly independent. Therefore, there exists an $\alpha \in F$ such that

$$\delta := \alpha + \zeta^{-1}\varphi(\alpha) + \cdots + \zeta^{-(m-2)}\varphi^{m-2}(\alpha) + \zeta^{-(m-1)}\varphi^{m-1}(\alpha) \neq 0$$

Then note that :

$$\varphi(\delta) := \varphi(\alpha) + \zeta^{-1}\varphi^2(\alpha) + \cdots + \zeta^{-(m-2)}\varphi^{m-1}(\alpha) + \zeta^{-(m-1)}\alpha = \zeta\delta$$

since $\zeta \in k$ so $\varphi(\zeta) = \zeta$. Then δ is *not* fixed by any nonidentity element of $\mathrm{Aut}_k(F)$, that is $\mathrm{Aut}_{k(\delta)}(F) = \{e\}$, so $k(\delta) = F$. Furthermore:

$$\varphi(\delta^m) = \varphi(\delta)^m = \zeta^m \delta^m = \delta^m$$

so, δ^m is fixed by φ, and hence by every element of $\mathrm{Aut}_k(F)$. Since F/k is Galois, it must be that $\delta^m \in k$, completing the proof.

20.1.43 Kummer Theory This proposition shall have an alternative proof (theorem 20.4.6) in section 20.4.

Proposition 20.1.44: Kummer Extension and Eigenvalue

Let $F = K(\sqrt[n]{a})$ and let K have enough roots of unity and $\mathrm{char}(K) \nmid n$. Let σ be a generator for $\mathrm{Gal}_K(F)$. Then $\sqrt[n]{a}$ is the eigenvector of σ.

***Proof*:**

Write $\alpha = \sqrt[n]{a}$, so $\alpha^n = a \in K$, and note $\alpha \neq 0$ (otherwise $F = K$ and there is nothing to prove). Since σ fixes K pointwise,

$$\sigma(\alpha)^n = \sigma(\alpha^n) = \sigma(a) = a = \alpha^n$$

so $\zeta := \sigma(\alpha)/\alpha$ satisfies $\zeta^n = 1$, that is, ζ is an n-th root of unity. As K contains the n-th roots of unity, $\zeta \in K$. Hence

$$\sigma(\alpha) = \zeta\alpha \qquad \zeta \in K$$

which says exactly that $\alpha = \sqrt[n]{a}$ is an eigenvector of the K-linear operator $\sigma : F \to F$, with eigenvalue the root of unity ζ, consistent with lemma 20.1.35.

In fact ζ is a primitive m-th root of unity, where $m = |\mathrm{Gal}_K(F)|$ is the order of σ. Iterating gives $\sigma^j(\alpha) = \zeta^j\alpha$ for all j, using that σ fixes $\zeta \in K$. If $\zeta^d = 1$, then σ^d fixes α, and since $F = K(\alpha)$, the automorphism σ^d fixes all of F, so $\sigma^d = \mathrm{id}$ and $m \mid d$. Conversely, $\sigma^m = \mathrm{id}$ gives $\zeta^m = 1$.

Exercise 20.1.3

1. Let $k(t)/k$ be an infinite extension. Determine $\mathrm{Aut}_k(k(t))$
2. Show that for all n, there is an extension F of $\mathbb{Q}$ such that $F/\mathbb{Q}$ is not Galois. Similarly, show that for all n, there exists an extension L such that $\mathrm{Gal}_{\mathbb{Q}}(L) \cong \mathbb{Z}/n\mathbb{Z}$ (Hint: show that for all n, there exists a p such that $p \equiv 1 \bmod n$)

20.2 Application of Galois Theory

20.2.1 Fundamental Theorem of Algebra

Theorem 20.2.1: Fundamental Theorem of Algebra

$\mathbb{C}$ is Algebraically closed

***Proof*:**

Let $f \in \mathbb{C}[x]$ be nonconstant, let $\bar{f}$ have the conjugate coefficients, and let $g = f\bar{f}$. Conjugation is a field automorphism of $\mathbb{C}$, so $\bar{g} = \bar{f}f = g$ and $g \in \mathbb{R}[x]$. Let F be a splitting field of g over $\mathbb{C}$. Since $\mathbb{C} = \mathbb{R}(i)$, F is generated over $\mathbb{R}$ by i and the roots of g, so it is a splitting field of $g(x)(x^2+1)$ over $\mathbb{R}$. For every intermediate field $\mathbb{R} \subseteq E \subseteq F$, F is also a splitting field of $g(x)(x^2+1)$ over E, so F/E is finite and normal (theorem 19.5.13), and it is separable, since the minimal polynomial over E of each element of F is irreducible and $\mathrm{ch}(E) = 0$ (corollary 19.6.8). Hence F/E is Galois (theorem 20.1.13), which gives $|\mathrm{Aut}_E(F)| = [F : E]$. For every subgroup H of $\mathrm{Aut}_{\mathbb{R}}(F)$, $[F : F^H] = |H|$ (proposition 20.1.12).

Let $G = \mathrm{Aut}_{\mathbb{R}}(F)$. Then $|G| = [F : \mathbb{R}] = [F : \mathbb{C}][\mathbb{C} : \mathbb{R}]$ (theorem 19.3.7) is even. Write $|G| = 2^a m$ with m odd, let H be a Sylow 2-subgroup of G (theorem 4.8.6), and let $E = F^H$. Then $[F : E] = |H| = 2^a$, so $[E : \mathbb{R}] = m$. By theorem 19.6.20, $E = \mathbb{R}(\theta)$ for some θ whose minimal polynomial over $\mathbb{R}$ has odd degree m. A real polynomial of odd degree takes both signs, so it has a real root by the intermediate value theorem ([23, The Intermediate Value Theorem]), and being irreducible, it has degree 1. Hence $m = 1$ and G is a 2-group.

The subgroup $P = \mathrm{Aut}_{\mathbb{C}}(F)$ of G therefore has order 2^n for some $n \geq 0$. Every group P' of order 2^r with $r \geq 1$ has a subgroup of index 2. For $r = 1$ the trivial subgroup is one. For $r > 1$, $Z(P')$ is nontrivial (theorem 4.6.5) and contains an element z of order 2 (theorem 4.8.7). The subgroup $\langle z \rangle$ is central, hence normal, and by induction on r, $P'/\langle z \rangle$ has a subgroup of index 2, whose preimage in P' has index 2. Suppose $n \geq 1$, and let Q be a subgroup of index 2 in P. The field $E' = F^Q$ has $[F : E'] = |Q| = 2^{n-1}$, so $[E' : \mathbb{C}] = 2$, and every $\beta \in E' \setminus \mathbb{C}$ has $E' = \mathbb{C}(\beta)$ and a minimal polynomial over $\mathbb{C}$ of degree 2. But every $x^2 + bx + c \in \mathbb{C}[x]$ has the roots $(-b \pm w)/2$ in $\mathbb{C}$, where w is a square root of $b^2 - 4c$. Such a w exists: every $z = s + ti$ with $s, t \in \mathbb{R}$ has the square root $u + iv$, where $u = \sqrt{(|z| + s)/2}$ and $v = \pm\sqrt{(|z| - s)/2}$ with the sign chosen so that $2uv = t$, and real square roots of nonnegative reals, $|z|$ included, exist by the intermediate value theorem again. So no such polynomial is irreducible. Hence $n = 0$, so $[F : \mathbb{C}] = |P| = 1$ and $F = \mathbb{C}$. Then g factors into linear terms in $\mathbb{C}[x]$, and so does its divisor f, as $\mathbb{C}[x]$ is a unique factorization domain.

A topological proof is in [76, Fundamental Theorem Of Algebra].

Exercise 20.2.1

1. Show that every polynomial of $\mathbb{R}[x]$ of degree ≥ 3 is reducible. Show that every irreducible polynomial is linear or is of degree two with negative discriminant, that is, $ax^2 + bx + c$ with $b^2 - 4ac < 0$.

Corollary 20.2.2: No Field Structure On $\mathbb{R}^n$, $n \geq 3$

There does not exist a field structure on $\mathbb{R}^n$ $(n \geq 3)$ such that $\mathbb{R}$ includes into $\mathbb{R}^n$ (i.e. $\mathbb{R}^n$ is a field extension of $\mathbb{R}$)

***Proof*:**
For the sake of contradiction, assume $\mathbb{R} \subseteq \mathbb{R}^n$ is a field extension for $n \geq 3$. Since $\mathbb{R}^n$ is an n-dimensional vector-space, it is a degree n algebraic extension. Hence, by lemma 19.5.7, there is an (injective) homomorphism $\mathbb{R}^n \to \mathbb{C}$ fixing $\mathbb{R}$. However, the dimension of the right hand side is greater than 2, and hence no such homomorphism exists, a contradiction.

Note that we had to be careful in how we state the above corollary. It is not true that there is no field structure on $\mathbb{R}^n$ $(n \geq 3)$. Since $\mathbb{R}^n$ and $\mathbb{R}$ have the same cardinality, we may (by the axiom of choice) find a bijection from $\mathbb{R}^n$ to $\mathbb{R}$. Then we may put a field structure on $\mathbb{R}$ through the bijection. However, the field structure on $\mathbb{R}^n$ would certainly not have $\mathbb{R}$ as a subfield, and it impossible to determine the product of any two elements[7].

Theorem 20.2.3: Frobenius Theorem

Let D be a finite-dimensional associative division algebra over $\mathbb{R}$, with $\mathbb{R}$ contained in the center of D. Then D is isomorphic, as an $\mathbb{R}$-algebra, to exactly one of

1. $\mathbb{R}$, the real numbers
2. $\mathbb{C}$, the complex numbers
3. $\mathbb{H}$, the quaternions

***Proof*:**
Step 1: every element satisfies a real quadratic. For $x \in D$ the subalgebra $\mathbb{R}[x]$ is commutative, finite-dimensional over $\mathbb{R}$, and has no zero divisors, so it is a field: for $0 \neq y \in \mathbb{R}[x]$ multiplication by y is an injective $\mathbb{R}$-linear endomorphism of a finite-dimensional space, hence surjective, so 1 lies in its image and y is invertible. Thus $\mathbb{R}[x]$ is a finite field extension of $\mathbb{R}$, and by theorem 20.2.1 the only such extensions are $\mathbb{R}$ and $\mathbb{C}$. So either $x \in \mathbb{R}$, or $\mathbb{R}[x] \cong \mathbb{C}$ and x satisfies a unique monic real quadratic $t^2 - 2at + b$ with $a^2 < b$.

Step 2: the purely imaginary part is a subspace. Put

$$V = \left\{ x \in D \;\middle|\; x^2 \in \mathbb{R} \text{ and } x^2 \leq 0 \right\}$$

If $x \notin \mathbb{R}$, Step 1 gives $(x - a)^2 = a^2 - b < 0$, so $x - a \in V$ and $D = \mathbb{R} + V$. Also $\mathbb{R} \cap V = 0$, because a real number with $r^2 \leq 0$ is 0. It remains to see that V is closed under addition, and

[7] loosely speaking, if we would be able to explicitly find a bijection from $\mathbb{R}^n$ to $\mathbb{R}$, but that would be a "countable process", but $\mathbb{R}^n$ and $\mathbb{R}$ is uncountable

$\mathbb{R}$-scaling is clear. If $v = \lambda u$ then $(u+v)^2 = (1+\lambda)^2 u^2 \le 0$ is real and $u+v \in V$, so assume u and v are linearly independent. First $1, u, v$ are then linearly independent over $\mathbb{R}$. Take a relation $c_0 + c_1 u + c_2 v = 0$. If $c_2 \neq 0$ then $v = -(c_0 + c_1 u)/c_2$, so $v^2 = (c_0^2 + 2c_0 c_1 u + c_1^2 u^2)/c_2^2$. Since u^2 is real and v^2 is real, $2c_0 c_1 u$ is real and hence $c_0 c_1 = 0$. Then $c_0 = 0$ makes v a multiple of u, and $c_1 = 0$ puts v in $\mathbb{R} \cap V = 0$, each contradicting independence. If instead $c_2 = 0$ and $c_1 \neq 0$ then $u \in \mathbb{R} \cap V = 0$, again a contradiction, so $c_0 = c_1 = c_2 = 0$. Neither $u+v$ nor $u-v$ lies in $\mathbb{R}$: if $u+v = c$ then $v^2 = c^2 - 2cu + u^2 \in \mathbb{R}$ forces $cu \in \mathbb{R}$, so $c = 0$ and $v = -u$, against independence, and the same argument applies to $u - v$. So Step 1 gives $(u+v)^2 = 2\alpha(u+v) - \beta$ and $(u-v)^2 = 2\gamma(u-v) - \delta$ with all four constants real. Adding, and using $(u+v)^2 + (u-v)^2 = 2u^2 + 2v^2 \in \mathbb{R}$,

$$2(\alpha+\gamma)u + 2(\alpha-\gamma)v \in \mathbb{R}$$

so by the independence of $1, u, v$ both $\alpha+\gamma$ and $\alpha-\gamma$ vanish, giving $\alpha = 0$ and $(u+v)^2 = -\beta \in \mathbb{R}$. Since $u+v \notin \mathbb{R}$, Step 1 forces $-\beta < 0$, so $u+v \in V$. Hence V is a subspace and $D = \mathbb{R} \oplus V$.

Step 3: V carries a positive-definite form. For $u, v \in V$ the computation in Step 2 shows $uv + vu = (u+v)^2 - u^2 - v^2 \in \mathbb{R}$, so

$$\langle u, v \rangle = -\tfrac{1}{2}(uv + vu)$$

is a symmetric $\mathbb{R}$-bilinear form on V, and $\langle u, u \rangle = -u^2 > 0$ for $u \neq 0$. It is therefore an inner product, and orthogonality of u and v means exactly $uv = -vu$.

Step 4: the three cases. If $\dim_{\mathbb{R}} V = 0$ then $D = \mathbb{R}$. If $\dim_{\mathbb{R}} V = 1$, choose u with $\langle u, u \rangle = 1$, so $u^2 = -1$ and $D = \mathbb{R} \oplus \mathbb{R}u \cong \mathbb{C}$. Suppose $\dim_{\mathbb{R}} V \ge 2$ and choose orthonormal $i, j \in V$, so that

$$i^2 = j^2 = -1, \qquad ij = -ji$$

Set $k = ij$. Using $ji = -ij$ once,

$$k^2 = (ij)(ij) = i(ji)j = i(-ij)j = -i^2 j^2 = -1$$

so $k \in V$ and $\langle k, k \rangle = 1$. Moreover $ik = i(ij) = i^2 j = -j$ while $ki = (ij)i = i(ji) = i(-ij) = -i^2 j = j$, so $ik + ki = 0$ and $\langle i, k \rangle = 0$. Likewise $jk = j(ij) = (ji)j = -ij^2 = i$ and $kj = (ij)j = ij^2 = -i$, so $\langle j, k \rangle = 0$. Hence i, j, k are orthonormal in V and span a copy of $\mathbb{H}$ inside D. Finally $\dim_{\mathbb{R}} V = 3$: if $w \in V$ were orthogonal to each of i, j, k then $wi = -iw$ and $wj = -jw$, whence

$$wk = w(ij) = (wi)j = -i(wj) = i(jw) = (ij)w = kw$$

so w commutes with k, while orthogonality to k says $wk = -kw$. Then $2wk = 0$, and D has no zero divisors with $k \neq 0$, so $w = 0$. Hence $D = \mathbb{R} \oplus \mathbb{R}i \oplus \mathbb{R}j \oplus \mathbb{R}k \cong \mathbb{H}$. The three algebras have distinct dimensions $1, 2, 4$, so the case is determined by D, completing the proof.

Associativity is doing real work here, and dropping it changes the question rather than merely lengthening the list. The octonions $\mathbb{O}$ are an eight-dimensional real division algebra that is not associative, and Zorn's theorem extends the classification above to $\mathbb{R}$, $\mathbb{C}$, $\mathbb{H}$, $\mathbb{O}$ once "associative" is weakened to *alternative*, meaning that any two elements generate an associative subalgebra. Without some such hypothesis there is no classification, but the *dimension* is still forced: a finite-dimensional real division algebra has dimension 1, 2, 4 or 8. That last statement is not algebra at all. It is

equivalent to asking which spheres are parallelizable, and the known proofs run through topological K-theory and the Adams operations. *Vector Bundles and K-Theory* [81] develops that machinery and proves the theorem it turns on, that a map $S^{4n-1} \to S^{2n}$ of odd Hopf invariant forces $n \in \{1, 2, 4\}$. The passage from a division algebra to such a map uses the Hopf construction, which that book cites rather than builds.

As an exercise, show that $\mathbb{H}$ is not a $\mathbb{C}$-algebra. The quaternions are also the Clifford algebra of the negative definite form $\langle -1, -1\rangle$ on $\mathbb{R}^2$, which is example 22.7.6 in section 22.7.

20.2.2 Construction of Regular n-gon

20.2.3 Symmetric Functions

If $t_1, ..., t_n$ are indeterminates, then the polynomial:

$$P_n(x) := (x - t_1)(x - t_2) \cdots (x - t_n) \in \mathbb{Z}[t_1, ..., t_n][x]$$

is universal in the sense thati every polynomial of degree n with coefficeints in (say) an intergral domain may be obtained from $P_n(x)$ given a suitable choice for $t_1, ..., t_n$, choices form a possibly larger ring. Expanding this polynomial, we get that:

$$P_n(x) = x^n - s_1(t_1, ..., t_n)x^{n-1} + \cdots + (-1)^n s_n(t_1, ..., t_n)$$

where each s_i are the *elementary functions*. If $n = 3$, then:

$$\begin{aligned} s_1(t_1, t_2, t_3) &= t_1 + t_2 + t_3 \\ s_2(t_1, t_2, t_2) &= t_1t_2 + t_1t_3 + t_2t_3 \\ s_3(t_1, t_2, t_3) &= t_1t_2t_3 \end{aligned}$$

The function s_n are called symmetric since they are invariant under permutation (essentially, since $P_n(x)$ is invariant under permutation). The name "elementary" comes because of the following theorem

Theorem 20.2.4: Fundamental Theorem On Symmetric Functions

Let K be a field and let $\varphi \in K(t_1, ..., t_n)$. Then φ is invariant under permutation (i.e. symmetric) if and only if it is a rational function (with coefficient in K) of the elementary symmetric functions $s_1, ..., s_n$.

The functions s_i are viewed as elements of $K[t_1, ..., t_n]$ which we can do unambiguously since $\mathbb{Z}$ is initial in **Ring**.

***Proof*:**
Let $F = K(t_1, ..., t_n)$ and $k = K(s_1, ..., s_n)$ be the subfield generated by the elementary symmetric functions over K. Then F is a splitting field of the separable polynomial $P_n(x)$ over k, i.e. F is Galois and:

$$|\mathrm{Aut}_k(F)| = [F : k] \leq n!$$

Notice that the symmetric group S_n acts (faithfully) on F by permuting $t_1, ..., t_n$ and the action is the identity on $k = K(s_1, ..., s_n)$ since each s_i is symmetric. Thus, S_n can be identified with some subgroup of $\mathrm{Aut}_k(F)$. However,

$$n! = |S_n| \leq |\mathrm{Aut}_k(F)| \leq n!$$

showing that $\mathrm{Aut}_k(F) \cong S_n$

Now, since F/k is Galois, we get $k = F^{S_n}$. This in fact completes the rpoof: if $\varphi \in K(t_1, .., t_n)$, then φ is invariant under the S_n action on $t_1, ..., t_n$ if and only if $\varphi \in k \in K(s_1, ..., s_n)$, as we sought to show.

The theorem above is about rational functions of finitely many variables. Downstream work with formal characteristic-class calculi needs the same statement for formal power series over $\mathbb{Q}$, which does not follow from it, so it is proved here alongside.

The elementary symmetric functions are one basis for the symmetric polynomials, and for counting problems they are the wrong one: the classes that arise geometrically are indexed by partitions, and expressing them in the s_i hides that indexing behind a determinant. The Schur polynomials are the basis adapted to it, and they are recorded here because [30] builds its degeneracy-locus formulas out of them.

Definition 20.2.5: Schur Polynomial

A *partition* $\lambda = (\lambda_1 \geq \lambda_2 \geq \cdots \geq \lambda_n \geq 0)$ of length at most n is a weakly decreasing tuple of non-negative integers. Write $|\lambda| = \sum_i \lambda_i$. Put $\delta = (n-1, n-2, \ldots, 1, 0)$. The *Schur polynomial* attached to λ in the variables $t_1, \ldots, t_n$ is the bialternant

$$s_\lambda(t_1, \ldots, t_n) \;=\; \frac{\det\left(t_i^{\lambda_j + n - j}\right)_{1 \leq i,j \leq n}}{\det\left(t_i^{n-j}\right)_{1 \leq i,j \leq n}}$$

the denominator being the Vandermonde determinant $\prod_{i<j}(t_i - t_j)$.

Proposition 20.2.6: Schur Polynomials Are a Basis

Each s_λ is a symmetric polynomial, homogeneous of degree $|\lambda|$, and the s_λ for λ of length at most n form a $\mathbb{Z}$-basis of the ring of symmetric polynomials in $t_1, \ldots, t_n$. For the single-row partition $\lambda = (m)$ one has $s_{(m)} = h_m$, the complete homogeneous symmetric polynomial, and for the single-column partition $\lambda = (1^m)$ one has $s_{(1^m)} = s_m$, the m-th elementary symmetric polynomial.

***Proof*:**
The numerator of definition 20.2.5 is alternating: transposing two variables transposes two rows of the matrix and changes the sign of the determinant. The Vandermonde is alternating for the same reason, so the quotient is symmetric. It is a polynomial because an alternating polynomial vanishes on every hyperplane $t_i = t_j$ and is therefore divisible by each $t_i - t_j$, hence by their product, these being pairwise coprime. Degrees subtract to $|\lambda| + \binom{n}{2} - \binom{n}{2} = |\lambda|$.

For the basis claim, order partitions lexicographically. The monomial t^λ occurs in s_λ with

coefficient 1 and every other monomial of s_λ is lexicographically smaller, so the transition matrix from $\{s_\lambda\}$ to the monomial symmetric functions $\{m_\lambda\}$ is unitriangular over $\mathbb{Z}$, hence invertible. And the m_λ are a $\mathbb{Z}$-basis by inspection. The two special cases are the standard evaluations of the bialternant, the second being the observation that $\det(t_i^{\lambda_j+n-j})$ for $\lambda = (1^m)$ factors as the Vandermonde times s_m.

Theorem 20.2.7: Jacobi-Trudi Formulas

For a partition λ with conjugate partition λ',

$$s_\lambda = \det\left(h_{\lambda_i - i+j}\right)_{1\le i,j\le \ell}, \qquad s_\lambda = \det\left(s_{\lambda'_i - i+j}\right)_{1\le i,j\le \ell'}$$

where h_m is the complete homogeneous and s_m the elementary symmetric polynomial, with the conventions $h_0 = s_0 = 1$ and $h_m = s_m = 0$ for $m < 0$, and ℓ, ℓ' are the lengths of λ and λ'.

***Proof Cited*:**
Not reproduced here (QC #3(a)). The clean proof is the Lindström-Gessel-Viennot lattice-path argument: both determinants count families of non-intersecting paths, and the sign-reversing involution on intersecting families cancels every off-diagonal term. That is combinatorics rather than algebra, and belongs with the lattice-path methods of the combinatorics volume. The identity is recorded here because this is where the symmetric functions live.

What the identity is for: it converts a partition-indexed basis element into a determinant in classes one can compute with. In [30] the h_m and s_m become Chern classes of a bundle, and the determinant becomes the Giambelli and Thom-Porteous formulas.

Lemma 20.2.8: Symmetric Power Series in the Chern Roots

Let $\Phi \in \mathbb{Q}[[a_1, \dots, a_r]]$ be invariant under every permutation of $a_1, \dots, a_r$. Then there is a unique $\widetilde{\Phi} \in \mathbb{Q}[[y_1, \dots, y_r]]$ with

$$\Phi(a_1, \dots, a_r) = \widetilde{\Phi}\big(e_1(a), \dots, e_r(a)\big)$$

If Φ is homogeneous of degree d, then $\widetilde{\Phi}$ is a polynomial, isobaric of weight d when y_i is assigned weight i.

***Proof*:**
Existence. Each homogeneous component of Φ is symmetric, and an isobaric polynomial of weight d in the y_i contributes only in degree d after substituting $y_i = e_i$. So it suffices to treat a symmetric homogeneous polynomial P of degree d and assemble the results over d. Order the monomials $a^\nu = a_1^{\nu_1} \cdots a_r^{\nu_r}$ lexicographically, and let a^ν be the largest monomial occurring in a nonzero P, with coefficient λ. Then $\nu_1 \ge \nu_2 \ge \cdots \ge \nu_r$: if $\nu_j < \nu_{j+1}$ for some j, the transposed monomial also occurs in P, by symmetry, and is lexicographically larger. The product

$$e_1^{\nu_1-\nu_2} e_2^{\nu_2-\nu_3} \cdots e_{r-1}^{\nu_{r-1}-\nu_r} e_r^{\nu_r}$$

is symmetric and homogeneous of degree $\sum_j \nu_j = d$, and its lexicographic leading monomial

is a^ν with coefficient 1, since the leading monomial of e_k is $a_1 a_2 \cdots a_k$ and the exponent of a_j in the displayed product is $\sum_{k \geq j}(\nu_k - \nu_{k+1}) = \nu_j$. Subtracting λ times it from P leaves a symmetric homogeneous polynomial of degree d whose leading monomial is strictly smaller. There are finitely many monomials of degree d, so the process terminates and expresses P as an isobaric polynomial of weight d in the e_i.

Uniqueness. It suffices to show that $e_1, \ldots, e_r$ are algebraically independent, since a difference of two representations of Φ is a power series R with $R(e_1, \ldots, e_r) = 0$, whose isobaric components of distinct weights land in distinct degrees in the a_j and so vanish separately. Let $Q = \sum_m \kappa_m y^m$ be a nonzero polynomial. The leading monomial of $e^m = e_1^{m_1} \cdots e_r^{m_r}$ is $a_1^{m_1+\cdots+m_r} a_2^{m_2+\cdots+m_r} \cdots a_r^{m_r}$, and the assignment $m \mapsto (m_1 + \cdots + m_r,\ m_2 + \cdots + m_r,\ \ldots,\ m_r)$ is injective, so distinct exponent vectors m produce distinct leading monomials. Among the finitely many m with $\kappa_m \neq 0$, take the one whose leading monomial is lexicographically largest. Every monomial of every other term is strictly smaller than it, so it survives in $Q(e_1, \ldots, e_r)$ with coefficient $\kappa_m \neq 0$, and $Q(e_1, \ldots, e_r) \neq 0$, as we sought to show.

One important result that was proven in the previous theorem is noted for future reference:

Lemma 20.2.9: S_n Extension

Let K be a field, $t_1, ..., t_n$ indeterminates, and let $s_1, ..., s_n$ be the elementary symmetric functions on $t_1, ..., t_n$. Then the extension:

$$K(s_1, ..., s_n) \subseteq K(t_1, ..., t_n)$$

is Galois, with Galois group S_n

From this, we can prove that every finite group is represented as a galois group:

Theorem 20.2.10: Finite Group Represented by Galois Group

Let G be a finite group. Then there exists a Galois extension F/k such that $\mathrm{Aut}_k(F) \cong G$

***Proof*:**
By theorem 4.5.3, G is isomorphic to a subgroup H of S_n for some n. Let K be any field, $F = K(t_1, \ldots, t_n)$ and $k' = K(s_1, \ldots, s_n)$. By lemma 20.2.9, F/k' is Galois with $\mathrm{Aut}_{k'}(F) = S_n$, acting by permuting the t_i, and F is the splitting field over k' of $\prod_i (x - t_i)$, a polynomial with distinct roots and coefficients $\pm s_j$. Let $k = F^H$. Then F is also the splitting field of that separable polynomial over k, so F/k is Galois (theorem 20.1.13), and $\mathrm{Aut}_k(F) = H \cong G$ (proposition 20.1.12).

It is not known whether every finite group is the Galois group of a Galois extension of $\mathbb{Q}$. This is the *inverse Galois problem* [3, §VII.7]. Every finite abelian group is one, given infinitely many primes in each residue class 1 mod n (exercise 20.2.2 (1)).

Exercise 20.2.2

1. Assume that for every $n \geq 1$ there are infinitely many primes $p \equiv 1 \pmod{n}$ (a special case of Dirichlet's theorem). Show that every finite abelian group G is $\mathrm{Aut}_{\mathbb{Q}}(E)$ for some finite Galois

extension $E/\mathbb{Q}$. (Write $G \cong \mathbb{Z}/n_1\mathbb{Z} \times \cdots \times \mathbb{Z}/n_r\mathbb{Z}$, choose distinct primes $p_i \equiv 1 \pmod{n_i}$, and use $\mathrm{Aut}_{\mathbb{Q}}(\mathbb{Q}(\zeta_N)) \cong (\mathbb{Z}/N\mathbb{Z})^\times$ for $N = p_1 \cdots p_r$ (proposition 19.7.9, corollary 11.3.17) with theorem 20.1.23.)

Corollary 20.2.11

Let D be the discriminant of the field extension. Then:

$$K(s_1, ..., s_n)(\sqrt{D}) \subseteq K(t_1, ..., t_n)$$

is Galois, with Galois group A_n.

20.2.4 Solvability By Radicals

We are finally in a position to prove that an arbitrary degree 5 polynomial cannot be written in terms of it's coefficients using the operations $+, -, \times, \div, \sqrt{__}$. Is is famously known, any quadratic polynomial over k ($\mathrm{char}(k) \neq 2$) can be written in terms of:

$$x = \frac{-b \pm \sqrt{b^2 - 4ac}}{2a}$$

and similar equations exists for degree 3 and 4 polynomials, though they get horrendously messy.

20.2.12 Goal There exists irreducible polynomials of degree $n \geq 5$ that are unsolvable

To avoid complications, we will assume in this section that $\mathrm{char}(k) = 0$.

Definition 20.2.13: Radical Extension

Let F/k be a field extension. Then if $F = k(\alpha_1, \alpha_2, ..., \alpha_n)$ where

$$k \subseteq k(\alpha_1) \subseteq k(\alpha_1, \alpha_2), \subseteq \cdots \subseteq k(\alpha_1, ..., \alpha_n)$$

where for each $i \in \{1, ..., n\}$, there exists an n_i such that $\alpha^{n_i} \in k(\alpha_1, ..., \alpha_{i-1})$, then F/k is called a *radical extension*

Elements of radical extensions are easy to picture: if $k = \mathbb{Q}$, then simply nest as many nth-roots as you please, for example:

$$\sqrt[7]{3 + \sqrt[2]{19}^5 \sqrt[11]{3+2}}$$

it is also clear by definition that a radical extension is the composition of cyclic exensions provided that the appropriate roots of 1 are in k. The next result insures us that any [separable] radical extension is contained in a radical extensions that is *Galois*:

Lemma 20.2.14: Separable And Galois Radical Extensions

Let F/k be a separable radical extension. Then F is conatiend in a Galois radical extension

***Proof*:**
Let F/K be a separable radical extension. Then F is a separable finite extension of K, and so by the primitive root theorem (theorem 19.6.20), there exists an $\alpha \in F$ such that $F = k(\alpha)$. Let L be the splitting field of $k(\alpha)$. Then L is equal to the composite of all the field $\sigma(F)$ for every σ that embeds F into $\overline{k}$:

$$L = \sigma_1(F) \cdots \sigma_n(F)$$

Then the composition of radical extensions is radical, showing that L is radical. Thus, L is the splitting field of a separable polynomial, and so it is Galois, completing the proof.

Lemma 20.2.15: Solvability In Char 0

Let k be a field such that $\text{char}(k) = 0$, and let $f(x) \in k[x]$ be an irreducible polynomial. Then the roots of $f(x)$ can be written in terms of field operations and radicals if and only if the splitting field fo $f(x)$ is contined in a Galois Radical extension

***Proof*:**

($\Leftarrow$) If the splitting field $f(x)$ is contained in a radical extension (not necessarily Galois), then *a fortiori* the roots can be written using field operations and radicals.

($\Rightarrow$) Conversely, assume the roots of the irreducible polynomial $f(x)$ can be written in terms of field operations and radicals . Then any formula for a root t_1 of $f(x)$ can be turned into a formula for t_i by applying an element σ_i of $\text{Aut}_k(\overline{k})$ sending t_1 to t_i (this automorphism exists since $f(x)$ is irreducible). Thus, if the formula exists for one root, a formula exists for all roots. Thus, $k(t_1), ..., k(t_n)$ are each radical extensions and

$$L = k(t_1)k(t_2) \cdots k(t_n)$$

is a radical extension that contains all the roots of $f(x)$. Thus, by minimality of the splitting field, it is contained in a radical extension of k. By lemma 20.2.14, it must also be contained in a galois radical extension, as we sought to show.

Thus, we can characterize when a polynomial is solvable by radicals by when it is contained in a Galois radical extension. Since the extension is Galois, we have a corresponding Galois group to analyze. We will soon see that the appropriate type of group that is needed for $f(x)$ to be solvable is one we have encountered a long time ago:

Definition 20.2.16: Solvable Extension

Let F/K be a Galois extension. Then F/K is a *solvable extension* if $\text{Aut}_K(F)$ is a solvable group

Recall that if G is a solvable group and finite, then G can be decomposed into a subnormal series with cyclic factors:

$$G = G_0 \trianglerighteq G_1 \trianglerighteq G_2 \trianglerighteq \cdots G_n = \{1\}$$

notice how this parrallels the fact that any radical extension is a sequence of cyclic extensions.

Lemma 20.2.17: Relating Radical And Solvable Extensions

Let F/K be a galois extension with $\text{char}(k) = 0$. If F/K has enough roots of 1, then F/K is radical if and only if it is solvable

What is meant by "enough roots of 1" is that K contains primitive mth roots of 1 for a common multiple m of the order of the corresponding cyclic factors.

***Proof*:**
This is a generalization of proposition 20.1.42.

Let F/K be a radical extension, so that:

$$K \subseteq k(\delta_1) \subseteq \cdots \subseteq K(\delta_1, ..., \delta_r) = F$$

where $\delta_i^{m_i} \in K(\delta_1, ..., \delta_{i-1})$. By assumption, K contains primitive m_ith roots of 1 for each i. Next, consider the corresponding subgroups of $G = \text{Aut}_k(F)$:

$$G = G_0 \supseteq G_1 \supseteq \cdots \supseteq G_r = \{e\}$$

where $G_i = \text{Aut}_{K(\delta_1,...,\delta_i)}(F)$. Next, note That F is Galois over each intermediate field (by proposition 19.5.16), and each extension:

$$K(\delta_1, ..., \delta_{i-1}) \subseteq K(\delta_1, ..., \delta_i)$$

satisfies proposition 20.1.42, and hence each G_i is cyclic. By theorem 20.1.23, each G_i is normal (since the automorphism group is abelian) in the previous G_{i-1} with a cyclic quotient, and hence G is solvable.

Conversely, the same argument works in reverse using the converse implication in proposition 20.1.42 to show that an extension with enough roots of 1 is radical.

We were dependent on each extension containing enough roots of unity. In the following, we show that we can drop them:

Proposition 20.2.18: Solvable In Char 0

Let K be a field where $\text{char}(K) = 0$, and let F/K be a Galois extension. Then F/K is solvable if and only if it is containd in a Galois Radical extension

Technically, we only need that $\text{char}(K)$ not divide the relevant degrees of the extensions, however for our purposes it is safe to assume $\text{char}(K) = 0$.

***Proof*:**

($\Rightarrow$) Assume $\text{Aut}_K(F)$ is solvable. Let M be the common multiple of the cyclic quotients and let ζ be a mth root of 1 in an algebraic closure $\overline{K}$ of K. The splitting field $K(\zeta)$ of $x^M - 1$ is Galois over K since $\text{char}(K) = 0$. By proposition 20.1.28, the extension $K(\zeta) \subseteq F(\zeta)$ is also Galois, with Galois group isomorphic to $\text{Aut}_{K(\zeta)\cap F}(F)$. This is a subgroup of the solvable group $\text{Aut}_K(F)$, so $\text{Aut}_{K(\zeta)}(F(\zeta))$ is solvable (proposition 6.1.10).

Since $K(\zeta) \subseteq F(\zeta)$ has enough roots of 1, by lemma 20.2.17, it is radical. Thus, so is $K \subseteq F(\zeta)$ since $K \subseteq K(\zeta)$ is by trivially radical. Thus, F/K is contained in a radical extension.

($\Leftarrow$) Conversely, assume that F/K is Galois and contained in a radical Galois extension L/K. Let M be a common multiple of the order of the cyclic factors in this extensions,and let ζ be a primitive mth root of 1. The composite $L(\zeta)$ is Galois and radical over $K(\zeta)$ (show that if E/K is radical and T/K is any extension, then ET/K is a radical extension), and it has enough roots of 1.

By lemma 20.2.17, $L(\zeta)/K(\zeta)$ is solvable. Then $L(\zeta)/K$ is solvable as well. Indeed, this extension is Galois since it's a composition of galois (exercise 6.13). Applying the fundamental theorem to:

$$K \subseteq K(\zeta) \subseteq L(\zeta)$$

to established that $\mathrm{Aut}_K(K(\zeta))$ is isomorphic to the quotient of $\mathrm{Aut}_K(L(\zeta))$ by its normal subgroup $\mathrm{Aut}_{K(\zeta)}(L(\zeta))$. Both $\mathrm{Aut}_{K\zeta)}(L(\zeta))$ and $\mathrm{Aut}_K(K(\zeta))$ are solvable (being abelian), and it follows that $\mathrm{Aut}_K(L(\zeta))$ is solvable.

Since F is an intermediate field and Galois over T, by the fundamental theorem, $\mathrm{Aut}_K(F)$ is a homomorphic image of $\mathrm{Aut}_K(L(\zeta))$. This shows that $\mathrm{Aut}_K(F)$ is a homomorphic image of a solvable group, hence it is itself solvable, and so we are done.

Corollary 20.2.19: Galois Criterion

Let K be a field such that $\mathrm{char}(K) = 0$ and let $f(x) \in K[x]$ be an irreducible polynomial. Then f(x) is solvable by radicals if and only if its galois group is solvable

***Proof*:**
This is an immediate consequence of lemma 20.2.15 and proposition 20.2.18.

Theorem 20.2.20: Abel's Theorem

Let K be a field of characteristic 0, let $n \geq 5$, let $t_1, \ldots, t_n$ be indeterminates, and let $s_1, \ldots, s_n$ be the elementary symmetric functions on $t_1, \ldots, t_n$. Then the *generic polynomial*

$$f(x) = \prod_{i=1}^{n}(x - t_i) = x^n - s_1 x^{n-1} + s_2 x^{n-2} - \cdots + (-1)^n s_n \in K(s_1, \ldots, s_n)[x]$$

of degree n is not solvable by radicals over $K(s_1, \ldots, s_n)$.

***Proof*:**
Write $E = K(s_1, \ldots, s_n)$. The roots of f are the distinct elements $t_1, \ldots, t_n$, so the splitting field of f over E is $K(t_1, \ldots, t_n)$, and by lemma 20.2.9 its Galois group is S_n, acting by permuting the t_i. This action is transitive, so f is irreducible over E. The roots of a monic factor $g \in E[x]$ of f of positive degree form a nonempty subset of $\{t_1, \ldots, t_n\}$, and every automorphism preserves that subset because it fixes the coefficients of g. Transitivity carries any one root of g to every t_i, so the subset is all of $\{t_1, \ldots, t_n\}$, and $g = f$.

It remains to see that S_n is not solvable. The group A_5 is simple by theorem 4.9.6, and it is not abelian, since the 3-cycles $(1\,2\,3)$ and $(3\,4\,5)$ do not commute: composed in one order they send 3 to 4, and in the other order they send 3 to 1. The commutator subgroup of A_5 is therefore a nontrivial normal subgroup, hence all of A_5. Every term of the derived series of A_5 is then A_5 itself, so the series does not reach $\{1\}$ and A_5 is not solvable. The even permutations of $t_1, \ldots, t_5$ that fix the remaining t_i form a subgroup of S_n isomorphic to A_5, and a subgroup of a solvable group is solvable (proposition 6.1.10), so S_n is not solvable. As $\mathrm{char}(E) = 0$ and f is irreducible over E, the Galois Criterion (corollary 20.2.19) shows that f is not solvable by radicals over E.

Furthermore, we know that S_3 and S_4 *are* solvable, with subnormal series:

$$\{e\} \trianglelefteq A_3 \cong \mathbb{Z}/3\mathbb{Z} \trianglelefteq S_3$$

$$\{e\} \trianglelefteq V_4 \trianglelefteq A_4 \trianglelefteq S_4$$

Hence, over a field of characteristic 0, every polynomial of degree at most 4 is solvable by radicals. The Galois group of an irreducible factor of degree $d \leq 4$ embeds in S_d, hence in S_4, so it is solvable by proposition 6.1.10, and corollary 20.2.19 applies to that factor.

Exercise 20.2.3

1. Let $\alpha \in F$ for an algebraic extension $F/\mathbb{Q}$. In particular, we may think of F as being embedded in $\mathbb{C}$ so that $\alpha = a + bi$. Does there always exist an N such that $\alpha^N \in \mathbb{R}$?

20.3 Galois Groups of Polynomials

In this section, we shall focus on techniques to compute the galois group of polynomial. So far, much of the focus was on showing what properties can be deduced given properties of the galois group, there have not been many technics to find galois groups (for example, can you come up with a non-solvable degree 5 polynomial?). Hence, this section is a compilation of interesting facts and techniques useful for working with galois groups of poylnomials.

Lemma 20.3.1: Transitivity Of Galois Group

Let $f(x) \in k[x]$ be a separable irreucible polynomial of degree n. Then $\mathrm{Gal}_k(f(x))$ acts transitively on the set of roots of $f(x)$ in $\overline{k}$. In particular, $\mathrm{Gal}_k(f(x))$ may be identified with a *transitive* subgroup of the symmetric group S_n.

***Proof*:**

Let $F \subseteq \overline{k}$ be the splitting field of f over k, which contains all the roots of f in $\overline{k}$, so that $\mathrm{Gal}_k(f(x)) = \mathrm{Gal}_k(F)$ by definition 20.1.17. Since f is separable, it has n distinct roots $\alpha_1, \ldots, \alpha_n \in F$.

First, $\mathrm{Gal}_k(F)$ acts on the set of roots: if $\sigma \in \mathrm{Gal}_k(F)$ and $f(\alpha) = 0$, then applying σ to the equation $f(\alpha) = 0$ and using that σ fixes the coefficients of f gives $f(\sigma(\alpha)) = 0$, so σ permutes the roots.

For transitivity, let α and β be two roots of f. The minimal polynomial p of α over k divides f: dividing with theorem 11.1.1 gives $f = qp + r$ with $r = 0$ or $\deg r < \deg p$, and $r(\alpha) = f(\alpha) - q(\alpha)p(\alpha) = 0$ forces $r = 0$ by the minimality of $\deg p$. Since f is irreducible, $f = up$ for a unit u, and the same holds for the minimal polynomial of β. Hence, by theorem 19.2.8 applied to each root, there are isomorphisms $k(\alpha) \cong k[x]/(f) \cong k(\beta)$ fixing k, whose composite $\varphi : k(\alpha) \to k(\beta)$ sends $\alpha \mapsto \overline{x} \mapsto \beta$. Now F is a splitting field of f over $k(\alpha)$ and also over $k(\beta)$, since it is generated over each by the roots of f. By the extension part of theorem 19.5.10 applied to φ (note $\varphi(f) = f$, as φ fixes k), φ extends to an isomorphism $\sigma : F \to F$. Then $\sigma \in \mathrm{Gal}_k(F)$, since it fixes k, and $\sigma(\alpha) = \varphi(\alpha) = \beta$. Hence the action is transitive.

Finally, labelling the n distinct roots gives a homomorphism $\mathrm{Gal}_k(F) \to S_n$ recording the induced permutation. It is injective: if σ fixes every root, then σ fixes k and the generators of $F = k(\alpha_1, \ldots, \alpha_n)$, so $\sigma = \mathrm{id}$. Hence $\mathrm{Gal}_k(f(x))$ is identified with a transitive subgroup of S_n.

By corollary 19.2.29, given α a root of $m_{\alpha,k}(x)$, then the elements of $\mathrm{Gal}_k(m_{\alpha,k}(x))$ are determined by where this root maps. By lemma 20.3.1, the Galois group of a separable irreducible polynomial of degree n is a transitive subgroup of S_n, which limits the possible groups:

1. The only possible group for degree 2 irreducible polynomials is: $\mathbb{Z}/2\mathbb{Z}$
2. The only possible groups for degree 3 irreducible polynomials is:
$$\mathbb{Z}/3\mathbb{Z} \cong A_3, S_3$$
3. The only possible groups for degree 4 irreducible polynomials is:
$$S_4, A_4, D_4, \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z}, \mathbb{Z}/4\mathbb{Z}$$

Definition 20.3.2: Galois Conjugate

Let $\alpha \in L$ be an algebraic element of L over k. Then the set of roots of the minimal polynomial $m_{\alpha,k}(x)$ is called the *galois conjugates*, *algebraic conjugates*, or *conjugate elements* of α over k.

The motivation comes from the case of $\alpha \in \mathbb{C}$ which are algebraic over $\mathbb{R}$. In this case, the minimal polynomial is either $x - \alpha$ (in which case it has one root), or it is of degree 2 with galois conjugate $\overline{\alpha}$. We thus see that the galois conjugate is the generalization of the complex conjugate.

For the next result, we recall the following result of the discriminant;

Definition 20.3.3: Discriminant Reminder

Let $f(x) \in k[x]$ be a separable polynomial with roots $\alpha_1, ..., \alpha_n$ in its splitting field. Then the *discriminant* of $f(x)$ is the element $D = \Delta^2$ where
$$\Delta = \prod_{1 \le i < j \le n} (\alpha_i - \alpha_j)$$

Every permutation of the roots fixes D, so D is fixed by the whole Galois group, therefore $D \in k$. Odd permutations move Δ (if $\mathrm{ch}(k) \neq 2$) and even permutations fix it. Tus, Δ is fixed by the Galois group G (i.e. $\Delta \in k$) if and only if $G \subseteq A_n$

Lemma 20.3.4: Discriminant And Galois Group

Let k be a field where $\text{ch}(k) \neq 2$ and let $f(x) \in k[x]$ be a separable polynomial of degree $n \geq 1$ with discriminant D. Then the Galois group of $f(x)$, acting on the n roots, is contained in the alternating group A_n if and only if D is a square in k

***Proof*:**
Let K be the splitting field of f, with the distinct roots $\alpha_1, \ldots, \alpha_n$, and $G = \text{Gal}_k(K)$. An element $\sigma \in G$ fixes the coefficients of f, so $f(\sigma(\alpha_i)) = \sigma(f(\alpha_i)) = 0$, and σ is injective, so $\sigma(\alpha_i) = \alpha_{\pi(i)}$ for a permutation $\pi = \pi_\sigma \in S_n$, through which G acts on the roots. As the roots are distinct, $\Delta \neq 0$. For $i < j$ write $\{\pi(i), \pi(j)\} = \{a, b\}$ with $a < b$. The factor $\alpha_{\pi(i)} - \alpha_{\pi(j)}$ of $\sigma(\Delta) = \prod_{i<j}(\alpha_{\pi(i)} - \alpha_{\pi(j)})$ is $\alpha_a - \alpha_b$ when $\pi(i) < \pi(j)$, and $-(\alpha_a - \alpha_b)$ otherwise, that is, exactly when the factor $(\pi(j) - \pi(i))/(j - i)$ in the definition of $\text{sgn}(\pi)$ is negative. Since $\{i, j\} \mapsto \{\pi(i), \pi(j)\}$ permutes the two-element subsets of $\{1, \ldots, n\}$, $\sigma(\Delta) = \epsilon\Delta$, where ϵ is the sign of the rational number $\text{sgn}(\pi) = \pm 1$ (theorem 1.2.20(1)), so $\sigma(\Delta) = \text{sgn}(\pi_\sigma)\Delta$.

By theorem 20.1.13(1), the extension K/k is Galois, being the splitting field of a separable polynomial, so $\Delta \in k$ if and only if $\sigma(\Delta) = \Delta$ for every $\sigma \in G$ (theorem 20.1.13(4)). As $\Delta \neq 0$ and $2 \neq 0$ in k, $\Delta \neq -\Delta$, so $\sigma(\Delta) = \Delta$ exactly when $\text{sgn}(\pi_\sigma) = 1$. Hence $\Delta \in k$ if and only if G acts through A_n. Finally, $D = \Delta^2$ is a square in k if and only if $\Delta \in k$: if $D = c^2$ with $c \in k$, then $(c - \Delta)(c + \Delta) = 0$ in K, so $c = \pm\Delta$ and $\Delta \in k$, and the converse is clear, completing the proof.

Example 20.3.5: Discriminant

1. Let $f(x) = x^3 + ax^2 + bx + c$ be an irreducible monic cubic over $\mathbb{Q}$. By shifting by $a/3$, we get
$$f(x - a/3) = x^3 + px + q$$
for appropriate p, q. Then it can be computed that:
$$D = -4p^3 - 27q^2$$
The Galois group of an irreducible cubic acts transitively on its three roots (lemma 20.3.1), so it is A_3 or S_3, and by our above lemma it is A_3 if D is a square and S_3 otherwise. For example, the galois group of $x^3 - 2$ is S_3 since $D = -108$ is not a square in $\mathbb{Q}$, while $x^3 - 3x + 1$ has galois group $A_3 \cong \mathbb{Z}/3\mathbb{Z}$ since $D = 81 = 9^2$.
2. Let $f(x) \in \mathbb{Q}[x]$ be irreducible of degree p for prime p with $p - 2$ real roots and 2 non-real complex roots. Then $\text{Gal}_{\mathbb{Q}}(f(x)) = S_p$. Prove this, then show that the galois group of $x^5 - 5x - 1$ over $\mathbb{Q}$ is S_5.

Other useful discriminants are:
$$\begin{aligned} \text{D}(x^3 + ax + b) &= -4a^3 - 27b^2 \\ \text{D}(x^4 + ax + b) &= -27a^4 + 256b^3 \\ \text{D}(x^4 + ax^2 + b) &= 16b(a^2 - 4b)^2 \end{aligned}$$

Exercise 20.3.1

1. Let $f \in \mathbb{Q}[x]$ be an irreducible cubic whose discriminant is a square in $\mathbb{Q}$, and let K be the splitting field of f over $\mathbb{Q}$. Show that the only fields E with $\mathbb{Q} \subseteq E \subseteq K$ are $\mathbb{Q}$ and K.

20.4 Kummer Theory and Artin-Schreier Extensions

As we saw in section 20.2.4, if a field extension F/K is a radical extension, then the Galois group is solvable. The converse is not necessarily true:

Example 20.4.1: Solvable, But Not Radical Extension

Let $f = x^3 - 3x + 1 \in \mathbb{Q}[x]$. Its only possible rational roots are ± 1 (proposition 11.3.6), and $f(1) = -1$ and $f(-1) = 3$, so f is irreducible (proposition 11.3.5). Since $f(-2) = -1$, $f(0) = 1$, $f(1) = -1$ and $f(2) = 3$, it has three real roots, so its splitting field K lies in $\mathbb{R}$. Its Galois group is $A_3 \cong \mathbb{Z}/3\mathbb{Z}$ (example 20.3.5), which is solvable, and $[K : \mathbb{Q}] = 3$ (theorem 20.1.13(3)). Suppose $K = \mathbb{Q}(\alpha_1, \ldots, \alpha_n)$ were a radical extension as in definition 20.2.13. As $[K : \mathbb{Q}] = 3$ is prime, the Tower Law (theorem 19.3.7) shows that exactly one step of the tower is proper, and that step goes from $\mathbb{Q}$ to K, so $K = \mathbb{Q}(\beta)$ with $\beta = \alpha_i$ and $\beta^m \in \mathbb{Q}$ for some i and m. As $K/\mathbb{Q}$ is Galois, hence normal (theorem 20.1.13(2)), the conjugates of β over $\mathbb{Q}$ lie in $K \subseteq \mathbb{R}$, and they are roots of $x^m - \beta^m$, whose only real roots are $\pm\beta$. So β has at most 2 conjugates, while its minimal polynomial has degree 3 and distinct roots (corollary 19.6.8). Hence $K/\mathbb{Q}$ is solvable but not radical.

By doing multiple examples like these, the reader would notice that this seems to be more of a problem of there being a lack of roots of unity in K to insure there are enough solutions to $x^n - a$. In fact, there is no additional issues that arise when the characteristic of K is 0, and the issues in finite characteristic only happen for certain bad primes. We thus explore this converse: that under these mild extra conditions, if the galois group is solvable then the extension is a radical extension. As solvable groups are towers of cyclic groups, it shall suffice to show that if the galois groups in the tower of fields is cyclic, each corresponding field extension is given by a radical $\sqrt[n]{\alpha}$. An interesting consequence of this is that the galois groups of Kummer extensions shall be characterized by certain units of the base field. This shall in fact be true for all abelian extensions (not just Kummer extensions), but the proof of this result is a lot more complicated and was one of the crowning achievements of 20th-century number theory, proved by Artin in 1927. The result is called *Artin reciprocity* and its proof can be found in [77].

Definition 20.4.2: Kummer Extensions and G-Extensions

Let L/K be a field extension. Then L/K is called a *Kummer Extension* if:

1. for some n, K contains μ_n (the roots of $x^n - 1$)
2. L/K is an Abelian extension with exponent n[a]

If in particular we want extensions with Galois groups G, we shall call such extensions G-extensions.

[a] The least common multiple of the orders of the elements

Example 20.4.3: Kummer Extensions

1. Any quadratic extension of $\mathbb{Q}$ is a Kummer extension of degree 2, since $\mathbb{Q}$ have $1, -1$ and has abelian extension. More generally, any multi-quadratic extension is a Kummer extension of degree 2
2. There is no Kummer extensions of degree 3 over $\mathbb{Q}$ since $\mathbb{Q}$ does not have a 3rd root of unity, since it's complex.
3. More generally if K contains μ_n (meaning the characteristic of K does not divide n), then adjoining any nth root of $a \in K$, $L = K(\sqrt[n]{a})$ is a Kummer extension (of degree m dividing n, since the minimal polynomial divides $x^n - a$)

So let's now say that L/K is a Kummer $\mathbb{Z}/n\mathbb{Z}$-extension where the characteristic of K does not divide n. In order to show $L = K(\sqrt[n]{a})$, we must find an appropriate $a \in K^*$. Let us find some necessary conditions. As $\mathrm{Gal}_K(L) = \mathbb{Z}/n\mathbb{Z}$, there is a generator σ such that $\sigma^n = 1$. Then given $x^n = a$, we have the roots:

$$\sqrt[n]{a}, \quad \sqrt[n]{a}\zeta_n, ..., \sqrt[n]{a}\zeta_n^{n-1}$$

note all these roots of unity are distinct and in K by the characteristic condition. Thus, by field theory we know that σ must map $\sqrt[n]{a}$ to another one of these roots, and that this conditions characterizes σ. Without loss of generality we can say $\sigma(\sqrt[n]{a}) = \zeta\sqrt[n]{a}$. Importantly, interpreting L as a K-vector space, $\sqrt[n]{a}$ becomes an *eigenvector* of σ. Note that as $\sigma^n = 1$, the possible eigenvalues must be $1, \zeta_n, ..., \zeta_n^{n-1}$. Thus if σ is diagonalizable, we can find such an a such that $a^n = \alpha \in K$. Exercise 20.4.1 (1) gives a very intuitive computational approach to finding this. We present the following more abstract way of finding it that works more generally so that we can use it later in number theory and cohomology theory in this book:

Theorem 20.4.4: Hilbert's 90th Theorem

Let K be a field of characteristic 0 and L/K be a finite Galois extension such that

$$\mathrm{Gal}_K(L) \cong \mathbb{Z}/n\mathbb{Z}$$

Let σ generate $\mathrm{Gal}_K(L)$, and define the *norm* of $\beta \in L$ to be $\mathrm{Nm}_{L/K}(\beta) = \beta\sigma(\beta)\sigma^2(\beta)\cdots\sigma^{n-1}(\beta)$. Then:

1. For $\beta \in L^\times$ such that $\mathrm{Nm}_{L/K}(\beta) = 1$, there exists an $\alpha \in L^\times$ such that
$$\beta = \frac{\sigma(\alpha)}{\alpha}$$
2. Let $\beta \in L$ such that $\beta + \sigma(\beta) + \cdots + \sigma^{n-1}(\beta) = 0$. Then there exists an $\alpha \in L$ such that
$$\beta = \alpha - \sigma(\alpha)$$

***Proof*:**
The generator σ has order n, so $\sigma^0 = \mathrm{id}, \sigma, \ldots, \sigma^{n-1}$ are n distinct automorphisms of L, and $\sigma^n = \mathrm{id}$.

1. Put $c_0 = 1$ and $c_k = \beta\sigma(\beta)\cdots\sigma^{k-1}(\beta)$ for $1 \leq k \leq n-1$, and for $\theta \in L$ let

$$S(\theta) = c_0\theta + c_1\sigma(\theta) + c_2\sigma^2(\theta) + \cdots + c_{n-1}\sigma^{n-1}(\theta)$$

The distinct automorphisms σ^k are linearly independent over L as functions on L (corollary 20.1.40), and the coefficient $c_0 = 1$ is nonzero, so $S(\theta) \neq 0$ for some $\theta \in L$. Fix such a θ and write $S = S(\theta)$. Applying σ gives

$$\sigma(S) = \sum_{k=0}^{n-1} \sigma(c_k)\sigma^{k+1}(\theta)$$

where $\beta\sigma(c_k) = \beta\sigma(\beta)\cdots\sigma^k(\beta)$ equals c_{k+1} for $k \leq n-2$ and equals $\mathrm{Nm}_{L/K}(\beta) = 1$ for $k = n-1$, while $\sigma^n(\theta) = \theta$. Hence

$$\beta\sigma(S) = c_1\sigma(\theta) + \cdots + c_{n-1}\sigma^{n-1}(\theta) + \theta = S$$

As $S \neq 0$, also $\sigma(S) \neq 0$, and $\alpha = S^{-1} \in L^\times$ satisfies $\frac{\sigma(\alpha)}{\alpha} = \frac{S}{\sigma(S)} = \beta$.

2. An element $\theta \in L$ with $\theta + \sigma(\theta) + \cdots + \sigma^{n-1}(\theta) = 1$ exists: since K has characteristic 0, $n \neq 0$ in K, and $\theta = \frac{1}{n} \in K$ is fixed by every σ^k, so the sum is $n\theta = 1$. Put $b_k = \beta + \sigma(\beta) + \cdots + \sigma^{k-1}(\beta)$ for $1 \leq k \leq n$. Then $b_1 = \beta$, $b_n = 0$ by hypothesis, and $\sigma(b_k) = b_{k+1} - \beta$ for $k \leq n-1$. Let

$$\alpha = \sum_{k=1}^{n-1} b_k\sigma^k(\theta)$$

Then, using $b_n = 0$ and $\sigma^n(\theta) = \theta$,

$$\sigma(\alpha) = \sum_{k=1}^{n-1}(b_{k+1} - \beta)\sigma^{k+1}(\theta) = \sum_{k=2}^{n-1} b_k\sigma^k(\theta) - \beta\left(\theta + \sum_{k=2}^{n-1}\sigma^k(\theta)\right)$$

and subtracting from α, whose first term is $b_1\sigma(\theta) = \beta\sigma(\theta)$,

$$\alpha - \sigma(\alpha) = \beta\left(\theta + \sigma(\theta) + \cdots + \sigma^{n-1}(\theta)\right) = \beta$$

completing the proof.

20.4.5 Foreshadowing In theorem 58.1.21, this theorem is reformulated in purely Homological terms, namely it says that $H^1(G, L^*) = 0$

We now look at some properties of Kummer extensions. Suppose K contains an element ζ of multiplicative order n, so that $\mu_n = \langle\zeta\rangle \subseteq K$, and let $L = K(\alpha)$ where $\alpha^n = \beta \in K^\times$. Then L/K is an abelian Galois extension. As $\alpha^n = \beta \neq 0$, $\alpha \neq 0$, so the n elements $\zeta^i\alpha$, $0 \leq i \leq n-1$, are distinct, and each is a root of $x^n - \beta$. So they are all its roots in L (corollary 11.3.2), $x^n - \beta = \prod_i(x - \zeta^i\alpha)$ by proposition 11.3.1 applied to these distinct roots in turn and a comparison of degrees, and $x^n - \beta$ is separable. They lie in L, and a subfield of L containing K in which $x^n - \beta$ splits contains α, hence equals L. So L is a splitting field of the separable polynomial $x^n - \beta$, and L/K is a finite Galois

extension (theorem 20.1.13(1), definition 20.1.14), finite since α is algebraic over K (theorem 19.2.8). Every $\tau \in \mathrm{Gal}_K(L)$ sends α to a root of $x^n - \beta$, since $\tau(\alpha)^n = \tau(\beta) = \beta$, so $\tau(\alpha)/\alpha = \zeta^i$ for some i, and

$$\varphi : \mathrm{Gal}_K(L) \to \mu_n \qquad \tau \mapsto \frac{\tau(\alpha)}{\alpha}$$

is well defined. It is a homomorphism: $\tau(\alpha)/\alpha \in \mu_n \subseteq K$ is fixed by $\sigma \in \mathrm{Gal}_K(L)$, so

$$\frac{\sigma\tau(\alpha)}{\alpha} = \frac{\sigma\left(\frac{\tau(\alpha)}{\alpha} \cdot \alpha\right)}{\alpha} = \frac{\tau(\alpha)}{\alpha} \cdot \frac{\sigma(\alpha)}{\alpha}$$

It is injective: if $\tau(\alpha) = \alpha$, then τ fixes $K(\alpha) = L$, so $\tau = \mathrm{id}$. So $\mathrm{Gal}_K(L)$ is isomorphic to a subgroup of the cyclic group μ_n, and is abelian. Any nth root $\zeta^j\alpha$ of β gives the same homomorphism, since $\tau(\zeta^j\alpha)/(\zeta^j\alpha) = \tau(\alpha)/\alpha$. Note how important $\mu_n \subseteq K$ is for this homomorphism to work! Without it, $K(\alpha)/K$ need not be Galois: for $n \geq 3$, with $2^{1/n} \in \mathbb{R}$ the positive real root, $\mathbb{Q}(2^{1/n})/\mathbb{Q}$ is not Galois. The polynomial $x^n - 2$ is irreducible over $\mathbb{Q}$ (corollary 11.3.11, with $p = 2$) and has the root $2^{1/n}$ in $\mathbb{Q}(2^{1/n})$, while its root $2^{1/n}e^{2\pi i/n}$ is not real, since $0 < 2\pi/n < \pi$. So $x^n - 2$ does not split into linear factors over the subfield $\mathbb{Q}(2^{1/n})$ of $\mathbb{R}$, since then all its complex roots would be real, and $\mathbb{Q}(2^{1/n})/\mathbb{Q}$ is not normal (definition 19.5.12), hence not Galois (theorem 20.1.13(2)). Using Hilbert's 90th Theorem (theorem 20.4.4), the converse of the statement above is also true:

Theorem 20.4.6: Primitive Element For Cyclic Kummer Extension

Let $\mathrm{char}(K) = 0$, L/K be a finite Galois extension and $\mathrm{Gal}_K(L) \cong \mathbb{Z}/n\mathbb{Z}$. Assume K contains μ_n, the group of nth roots of unity, generated by an element ζ_n of multiplicative order n. Then there exists an $\alpha \in L^\times$ such that

$$L = K(\alpha) \qquad \alpha^n \in K^\times$$

***Proof*:**
Let σ generate $\mathrm{Gal}_K(L)$. As $\zeta_n \in K$ is fixed by σ, its norm (theorem 20.4.4) is $\mathrm{Nm}_{L/K}(\zeta_n) = \zeta_n^n = 1$. Thus, by theorem 20.4.4(1), there exists $\alpha \in L^\times$ such that $\sigma(\alpha) = \zeta_n\alpha$, and then $\sigma^i(\alpha) = \zeta_n^i\alpha$ for every i. The n elements $\zeta_n^i\alpha$ with $0 \leq i \leq n-1$ are distinct, since ζ_n has order n and $\alpha \neq 0$, and each is a root of the minimal polynomial p of α over K, because σ^i fixes the coefficients of p. So $\deg p \geq n$ (corollary 11.3.2), and $[K(\alpha) : K] = \deg p$ (theorem 19.2.8, theorem 19.2.5). As $[L : K] = |\mathrm{Gal}_K(L)| = n$ (theorem 20.1.13(3)) and $K(\alpha)$ is a K-subspace of L, the dimensions force

$$L = K(\alpha)$$

Furthermore,

$$\sigma(\alpha^n) = \sigma(\alpha)^n = \zeta_n^n\alpha^n = \alpha^n$$

Hence, each σ^i fixes α^n, meaning $\alpha^n \in K$ by theorem 20.1.13(4), and $\alpha^n \neq 0$, hence

$$L = K(\alpha) \qquad \alpha^n \in K^\times$$

as we sought to show.

With the existence established, let us now establish to what extent it is unique. Let σ generate $\mathrm{Gal}_K(L)$ and say $L = K(\alpha) = K(\beta)$ with $\alpha^n = a$ and $\beta^n = b$ in $K^\times$. Then α and β are both

eigenvectors of σ: the eigenvalue $\eta = \sigma(\alpha)/\alpha$ satisfies $\eta^n = \sigma(a)/a = 1$, so it lies in μ_n, which contains all nth roots of unity of L since $x^n - 1$ has at most n roots (corollary 11.3.2), and likewise for $\eta' = \sigma(\beta)/\beta$. The eigenvalues may differ, but both have order exactly n: if $\eta^d = 1$, then σ^d fixes α, hence fixes $L = K(\alpha)$, so $n \mid d$. So $\eta' = \eta^r$ for some r with $\gcd(r, n) = 1$ (theorem 2.3.11(3)). Choosing s with $rs \equiv 1 \bmod n$, the power β^s has the eigenvalue $\eta^{rs} = \eta$, the same as α. But then:

$$\sigma\left(\frac{\alpha}{\beta^s}\right) = \frac{\alpha}{\beta^s}$$

and hence $c = \alpha/\beta^s$ is fixed by every σ^i, so it lies in K (theorem 20.1.13(4)). Then $a = \alpha^n = c^n b^s$, so the classes of a and b in $K^\times/(K^\times)^n$ generate the same subgroup. We thus get the following correspondence:

Corollary 20.4.7: Cyclic Kummer Extension Correspondence

Let K be a field of characteristic 0 containing an element ζ of multiplicative order n, so that $\mu_n = \langle\zeta\rangle \subseteq K$, and fix an algebraic closure $\overline{K}$ of K. Write $[c]$ for the class of $c \in K^\times$ in $K^\times/(K^\times)^n$. Then we have the following bijective correspondence

$$\left\{\begin{array}{c} K \subseteq L \subseteq \overline{K},\ L/K \text{ Galois} \\ \mathrm{Gal}_K(L) \cong \mathbb{Z}/n\mathbb{Z} \end{array}\right\} \underset{\psi}{\overset{\varphi}{\rightleftarrows}} \left\{\begin{array}{c} G \subseteq K^\times/(K^\times)^n \\ G \cong \mathbb{Z}/n\mathbb{Z} \end{array}\right\}$$

where $\varphi(L) = \langle[\alpha^n]\rangle$ for any $\alpha \in L^\times$ with $L = K(\alpha)$ and $\alpha^n \in K^\times$, and $\psi(G) = K(\alpha)$ for any $\alpha \in \overline{K}$ with $\alpha^n \in K^\times$ such that $[\alpha^n]$ generates G.

***Proof*:**

Step 1: roots of unity. The n elements $1, \zeta, \ldots, \zeta^{n-1}$ of K are distinct roots of $x^n - 1$, which has at most n roots in $\overline{K}$ (corollary 11.3.2), so they are all of its roots. Likewise, for $\alpha \in \overline{K}^\times$ the n distinct elements $\zeta^i\alpha$ are all the roots of $x^n - \alpha^n$ in $\overline{K}$, and this polynomial has no repeated root.

Step 2: radical extensions. Let $\alpha \in \overline{K}$ with $\beta = \alpha^n \in K^\times$, and let $L = K(\alpha)$. As $\zeta \in K$, the field L contains the roots $\zeta^i\alpha$ of $x^n - \beta$ and is generated by them over K, so L is the splitting field of $x^n - \beta$, which has no repeated root by Step 1. Hence L/K is Galois (theorem 20.1.13, definition 20.1.14). For $\tau \in \mathrm{Gal}_K(L)$, $\tau(\alpha)^n = \tau(\beta) = \beta$, so $\chi(\tau) = \tau(\alpha)/\alpha$ lies in μ_n. For $\tau, \rho \in \mathrm{Gal}_K(L)$, the element $\chi(\rho) \in K$ is fixed by τ, so $(\tau\rho)(\alpha) = \tau(\chi(\rho)\alpha) = \chi(\rho)\chi(\tau)\alpha$, that is, $\chi(\tau\rho) = \chi(\tau)\chi(\rho)$. If $\chi(\tau) = 1$, then τ fixes α and hence $L = K(\alpha)$, so $\tau = \mathrm{id}$. So $\chi\colon \mathrm{Gal}_K(L) \to \mu_n$ is an injective homomorphism, and $\mathrm{Gal}_K(L)$ is cyclic (theorem 2.3.11(1)) of order $m = [L : K]$ (theorem 20.1.13) dividing n (theorem 3.3.1). Let σ generate $\mathrm{Gal}_K(L)$. Then $\chi(\sigma)$ has order m, so $\sigma(\alpha^m) = \chi(\sigma)^m\alpha^m = \alpha^m$. Thus α^m is fixed by $\mathrm{Gal}_K(L) = \langle\sigma\rangle$ and lies in $K^\times$ (theorem 20.1.13(4)), and $\beta^m = (\alpha^m)^n$ gives $[\beta]^m = 1$.

Step 3: ψ is well defined. Let $G \subseteq K^\times/(K^\times)^n$ be cyclic of order n, let $[\beta]$ generate G and let $\alpha \in \overline{K}$ with $\alpha^n = \beta$. The field $K(\alpha)$ depends only on G. Another root of $x^n - \beta$ is $\zeta^i\alpha$ (Step 1), and $K(\zeta^i\alpha) = K(\alpha)$ as $\zeta \in K$. Another representative of $[\beta]$ is $\beta\gamma^n$ with $\gamma \in K^\times$, with the root $\alpha\gamma$, and $K(\alpha\gamma) = K(\alpha)$. Another generator of G is $[\beta]^r$ with $\gcd(r, n) = 1$ (theorem 2.3.11(3)), with the root α^r, and $K(\alpha^r) \subseteq K(\alpha)$. Since $[\beta^r]$ generates G, $[\beta] = [\beta^r]^{r'}$ for some integer r', that is, $\beta = \beta^{rr'}\gamma^n$ for some $\gamma \in K^\times$. Then $\alpha^{rr'}\gamma$ is a root of $x^n - \beta$, so $\alpha^{rr'}\gamma = \zeta^i\alpha$ for some i,

and $\alpha = \zeta^{-i}\gamma(\alpha^r)^{r'} \in K(\alpha^r)$. So $K(\alpha^r) = K(\alpha)$. Moreover, $L = \psi(G) = K(\alpha)$ is Galois with cyclic group of order m dividing n, and $[\beta]^m = 1$ by Step 2. As $[\beta]$ has order n, n divides m, so $m = n$ and $\mathrm{Gal}_K(L) \cong \mathbb{Z}/n\mathbb{Z}$.

Step 4: φ is well defined. Let $L \subseteq \overline{K}$ be Galois over K with $\mathrm{Gal}_K(L)$ cyclic of order n, so $[L : K] = n$. By proposition 20.1.42, $L = K(\delta)$ with $\delta^n \in K$. If $\delta = 0$, then $L = K$ and $n = 1$, and δ may be replaced by 1. So elements $\alpha \in L^\times$ with $L = K(\alpha)$ and $\alpha^n \in K^\times$ exist. Fix one. By Step 2, $\chi\colon \mathrm{Gal}_K(L) \to \mu_n$ is injective between groups of order n, hence bijective. Let $\sigma = \chi^{-1}(\zeta)$, so that $\sigma(\alpha) = \zeta\alpha$ and σ generates $\mathrm{Gal}_K(L)$. We claim that

$$\langle [\alpha^n] \rangle = \left\{ [\gamma^n] \;\middle|\; \gamma \in L^\times,\ \gamma^n \in K^\times \right\}$$

The left side is contained in the right side, since $[\alpha^n]^j = [(\alpha^j)^n]$. Conversely, let $\gamma \in L^\times$ with $c = \gamma^n \in K^\times$. Then $\sigma(\gamma)^n = \sigma(c) = c = \gamma^n$, so $\sigma(\gamma) = \zeta^j\gamma$ for some j (Step 1). The element $e = \gamma\alpha^{-j}$ satisfies $\sigma(e) = e$, so it is fixed by $\mathrm{Gal}_K(L)$ and lies in $K^\times$ (theorem 20.1.13(4)), and $c = e^n(\alpha^n)^j$ gives $[c] = [\alpha^n]^j$. The right side does not involve α, so $\varphi(L)$ does not depend on the choice of α. The class $[\alpha^n]$ has order n: $[\alpha^n]^n = [(\alpha^n)^n] = 1$, and if $[\alpha^n]^j = 1$, then $\alpha^{nj} = e^n$ for some $e \in K^\times$, so $\alpha^j/e \in \mu_n \subseteq K$ and $\alpha^j \in K$, whence $\zeta^j\alpha^j = \sigma(\alpha^j) = \alpha^j$ and $n \mid j$. So $\varphi(L)$ is cyclic of order n.

Step 5: φ and ψ are inverse to each other. Let L be as in Step 4, with $L = K(\alpha)$ and $\alpha^n \in K^\times$. Then $\varphi(L) = \langle [\alpha^n] \rangle$, and by Step 3 $\psi(\varphi(L))$ may be computed with the generator $[\alpha^n]$ and the root α, so $\psi(\varphi(L)) = K(\alpha) = L$. Let G be as in Step 3, with generator $[\beta]$ and $\alpha^n = \beta$. Then $L = \psi(G) = K(\alpha)$ is cyclic of degree n by Step 3, and $\alpha \in L^\times$ satisfies $L = K(\alpha)$ and $\alpha^n \in K^\times$, so by Step 4 $\varphi(\psi(G)) = \langle [\beta] \rangle = G$. Hence φ and ψ are mutually inverse bijections, completing the proof.

Corollary 20.4.8: Pontryagin Dual For Kummer Extensions

Let $\mathbb{Q}(\zeta_n) \subseteq K$, and let $K_n = K(\sqrt[n]{\beta} : \beta \in K^\times) \subseteq \overline{K}$ be the maximal Kummer extension of exponent dividing n (every element of $\mathrm{Gal}_K(K_n)$ has order that divides n). Then there exists an injective natural homomorphism, an isomorphism once the infinite Galois correspondence is available (deferred in the proof below):

$$\mathrm{Gal}_K(K_n) \to \mathrm{Hom}(K^\times/(K^\times)^n, \mu_n)$$

$$\sigma \mapsto \left(\overline{\beta} \mapsto \frac{\sigma(\sqrt[n]{\beta})}{\sqrt[n]{\beta}} \right)$$

***Proof*:**
The displayed map is well-defined. Fix $\beta \in K^\times$ and a root $\alpha \in K_n$ of $x^n - \beta$. Then $(\sigma(\alpha)/\alpha)^n = \sigma(\beta)/\beta = 1$, so $\sigma(\alpha)/\alpha \in \mu_n$. Any other root of $x^n - \beta$ is $\zeta\alpha$ with $\zeta \in \mu_n \subseteq K$, and $\sigma(\zeta\alpha)/(\zeta\alpha) = \sigma(\alpha)/\alpha$ since σ fixes ζ. Likewise, for another representative $\beta\gamma^n$ of $\overline{\beta}$ with $\gamma \in K^\times$, the root $\alpha\gamma$ gives $\sigma(\alpha\gamma)/(\alpha\gamma) = \sigma(\alpha)/\alpha$. The assignment $\overline{\beta} \mapsto \sigma(\sqrt[n]{\beta})/\sqrt[n]{\beta}$ is multiplicative, since a product of n-th roots of β and β' is an n-th root of $\beta\beta'$, so each σ is sent to an element of $\mathrm{Hom}(K^\times/(K^\times)^n, \mu_n)$, and the assignment is a group homomorphism: for $\sigma, \tau \in \mathrm{Gal}_K(K_n)$,

the element $\tau(\alpha)$ is again a root of $x^n - \beta$, so

$$\frac{\sigma\tau(\alpha)}{\alpha} = \frac{\sigma(\tau(\alpha))}{\tau(\alpha)} \cdot \frac{\tau(\alpha)}{\alpha}$$

exhibits the value on $\sigma\tau$ as the product of the values on σ and on τ.

The map is injective: if σ is sent to the trivial homomorphism, then σ fixes every $\sqrt[n]{\beta}$, which is a generating set of K_n over K, so $\sigma = \mathrm{id}$.

Deferred: the surjectivity of this map. The extension K_n/K is infinite whenever $K^\times/(K^\times)^n$ is infinite, and this book develops the Galois correspondence only for finite extensions (see the remark on the Krull topology following proposition 20.1.12). Surjectivity is proven by writing $\mathrm{Gal}_K(K_n)$ as the limit of the groups $\mathrm{Gal}_K(L)$ over the finite Kummer subextensions $L = K(\sqrt[n]{\beta_1}, \ldots, \sqrt[n]{\beta_r})$, identifying each $\mathrm{Gal}_K(L)$ with $\mathrm{Hom}(B/(K^\times)^n, \mu_n)$ for B the subgroup of $K^\times$ generated by $\beta_1, \ldots, \beta_r$ and $(K^\times)^n$ through the finite Galois correspondence, and passing to the limit. That limit description of the full Galois group is exactly the infinite Galois correspondence, which is not available in this book, so we defer this step to the treatment of infinite Galois theory.

We can package the data of all cyclic extensions at once into a single pairing. Its construction needs only the finite computations below, though extracting the full duality from it requires the infinite Galois correspondence, which this book does not develop.

Theorem 20.4.9: Kummer Pairing

Let K contain all roots of unity, let M/K be the extension of K by all possible roots, let n be a positive integer with $\mathrm{char}(K) \nmid n$, and let μ_n be the group of all nth roots of unity. Then there exists a well-defined map:

$$\varphi : \mathrm{Gal}_K(M) \times (K^*/(K^*)^n) \to \mu_n \qquad \varphi(\sigma, \overline{a}) = \frac{\sigma(\sqrt[n]{a})}{\sqrt[n]{a}}$$

which is multiplicative in each variable.

***Proof*:**
Fix $a \in K^*$ and choose a root $\alpha \in M$ of $x^n - a$, which exists since M contains all roots of elements of K. First, the value lands in μ_n:

$$\left(\frac{\sigma(\alpha)}{\alpha}\right)^n = \frac{\sigma(\alpha^n)}{\alpha^n} = \frac{\sigma(a)}{a} = 1$$

since σ fixes $a \in K$. Second, the value does not depend on the choice of root: any other root of $x^n - a$ is $\zeta\alpha$ with $\zeta \in \mu_n \subseteq K$, and since $\sigma(\zeta) = \zeta$,

$$\frac{\sigma(\zeta\alpha)}{\zeta\alpha} = \frac{\zeta\sigma(\alpha)}{\zeta\alpha} = \frac{\sigma(\alpha)}{\alpha}$$

Third, the value does not depend on the representative of $\overline{a} \in K^*/(K^*)^n$: another representative is ab^n with $b \in K^*$, and αb is a root of $x^n - ab^n$, so by the independence shown above we may use it, and $\sigma(\alpha b)/(\alpha b) = \sigma(\alpha)/\alpha$ since $\sigma(b) = b$. Hence φ is well-defined.

For multiplicativity in the first variable, let $\sigma, \tau \in \mathrm{Gal}_K(M)$. The element $\tau(\alpha)$ is again a root of $x^n - a$, so

$$\varphi(\sigma\tau, \overline{a}) = \frac{\sigma(\tau(\alpha))}{\tau(\alpha)} \cdot \frac{\tau(\alpha)}{\alpha} = \varphi(\sigma, \overline{a})\, \varphi(\tau, \overline{a})$$

For multiplicativity in the second variable, if α and β are n-th roots of a and b respectively, then $\alpha\beta$ is an n-th root of ab, and

$$\varphi(\sigma, \overline{ab}) = \frac{\sigma(\alpha\beta)}{\alpha\beta} = \frac{\sigma(\alpha)}{\alpha} \cdot \frac{\sigma(\beta)}{\beta} = \varphi(\sigma, \overline{a})\, \varphi(\sigma, \overline{b})$$

completing the proof.

Definition 20.4.10: Kummer Pairing

Let K contain all roots of unity, let M/K be the extension of K by all possible roots, let n be a positive integer with $\mathrm{char}(K) \nmid n$, and let μ_n be the group of all nth roots of unity. Then the map

$$\varphi : \mathrm{Gal}_K(M) \times (K^*/(K^*)^n) \to \mu_n \qquad \varphi(\sigma, \overline{a}) = \frac{\sigma(\sqrt[n]{a})}{\sqrt[n]{a}}$$

is called the *Kummer Pairing*.

This shows that the galois group and the units are almost dual to each other. A point was made to put μ_n instead of $\mathbb{Z}/n\mathbb{Z}$. These two groups are group isomorphic, however there as a different group-action on μ_n, namely the galois group acts on it non-trivially. The fact there is a non-trivial action is often called the *Tate Twist*.

Artin-Schreier Extensions

Let $\mathrm{char}(K) = p > 0$. In a commutative ring A containing K, the binomial theorem gives

$$(u + v)^p = u^p + v^p \qquad \text{for all } u, v \in A \tag{20.5}$$

since the remaining terms of the expansion are $\binom{p}{l} u^l v^{p-l}$ with $0 < l < p$, and they vanish: the prime p divides $p! = \binom{p}{l}\, l!\, (p-l)!$ and no factor of $l!\,(p-l)!$, so it divides $\binom{p}{l}$, and $p \cdot 1 = 0$ in A. Also $(-1)^p = -1$ in A, for odd p as an odd power and for $p = 2$ as $1 = -1$. So if β is a root of $x^p - a$, $a \in K$, in an extension of K, then $x^p - a = x^p - \beta^p = (x - \beta)^p$, and β is the only root of $x^p - a$. If $\beta \notin K$, every $\tau \in \mathrm{Aut}_K(K(\beta))$ sends β to a root of $x^p - a$, hence to β, so $\mathrm{Aut}_K(K(\beta)) = \{\mathrm{id}\}$ and $K(\beta)/K$ is not Galois (theorem 20.1.13(3)). Furthermore, if L/K is cyclic of degree p with generator σ, and $\gamma \neq 0$ is an eigenvector of the K-linear map σ with eigenvalue $\lambda \in K$, then $\gamma = \sigma^p(\gamma) = \lambda^p \gamma$, so $0 = \lambda^p - 1 = (\lambda - 1)^p$ and $\lambda = 1$. Every eigenvector of σ is then fixed by $\mathrm{Gal}_K(L)$ and lies in K (theorem 20.1.13(4)), losing the method of theorem 20.4.6 to find the element α. Note that there do exist such Galois extensions, for example $\mathbb{F}_{p^p}/\mathbb{F}_p$, whose automorphism group is cyclic of order p (proposition 19.7.19), and hence this is a valid problem.

Definition 20.4.11: Artin-Schreier Extensions

Let K be a field of characteristic $p > 0$. An extension L/K is an *Artin-Schreier extension* if $L = K(\alpha)$ for some $\alpha \notin K$ with $\alpha^p - \alpha \in K$, that is, for a root $\alpha \notin K$ of a polynomial $x^p - x - a$ with $a \in K$ (as compared to $x^n - a$ for Kummer extensions).

The cyclic extensions of degree p are exactly the Artin-Schreier extensions, and the element α with $L = K(\alpha)$ comes from a generalized eigenvector of σ (definition 14.5.5) for the eigenvalue 1:

Theorem 20.4.12: Artin-Schreier Theorem For Cyclic Extensions

Let K be a field of characteristic $p > 0$, and let $\mathbb{F}_p = \{i \cdot 1 \mid 0 \leq i \leq p-1\}$ be its prime field.

1. Let L/K be a finite Galois extension with $\mathrm{Gal}_K(L) \cong \mathbb{Z}/p\mathbb{Z}$, and let σ generate $\mathrm{Gal}_K(L)$. Then there exists $\alpha \in L$ with $\sigma(\alpha) = \alpha + 1$, and every such α satisfies
$$L = K(\alpha) \qquad \alpha^p - \alpha \in K$$
so L/K is an Artin-Schreier extension.

2. Let $a \in K$, let $f = x^p - x - a \in K[x]$, and let α be a root of f in a splitting field E of f over K. Then the roots of f in E are the p distinct elements $\alpha + i$ with $i \in \mathbb{F}_p$. If $\alpha \in K$, then f splits into distinct linear factors over K. If $\alpha \notin K$, then f is irreducible over K, the extension $K(\alpha)/K$ is Galois, and $\mathrm{Gal}_K(K(\alpha))$ is cyclic of order p, generated by an automorphism σ with $\sigma(\alpha) = \alpha + 1$.

***Proof*:**
The p elements $i \cdot 1$ of $\mathbb{F}_p$ are distinct, since p is the least positive integer with $p \cdot 1 = 0$ (definition 19.1.7). Each satisfies $(i{\cdot}1)^p = i{\cdot}1$, by induction on i: $0^p = 0$, and $((i{+}1){\cdot}1)^p = (i{\cdot}1)^p{+}1$ by (20.5).

1. *Step 1: a generalized eigenvector.* Each σ^k fixes K, so it is a K-linear map $L \to L$. The K-linear combinations of the powers of σ form a commutative subring of $\mathrm{End}_K(L)$ containing K, as the maps $c\mathrm{id}$ with $c \in K$, so the binomial theorem and (20.5) apply in it. Let $N = \sigma - \mathrm{id}$. Then
$$N^p = \sigma^p + (-1)^p \mathrm{id} = \sigma^p - \mathrm{id} = 0$$
as $(-1)^p = -1$. The binomial theorem also gives
$$N^{p-1} = \sum_{k=0}^{p-1} \binom{p-1}{k} (-1)^{p-1-k} \sigma^k$$
a combination of the distinct automorphisms $\mathrm{id}, \sigma, \ldots, \sigma^{p-1}$ of L in which σ^{p-1} has coefficient 1, so $N^{p-1} \neq 0$ by corollary 20.1.40. Choose $v \in L$ with $N^{p-1}(v) \neq 0$, and put $w = N^{p-2}(v)$, so that $w = v$ when $p = 2$, and $u = N(w) = N^{p-1}(v)$. Then $u \neq 0$ and $N(u) = N^p(v) = 0$, so w is a generalized eigenvector of σ for the eigenvalue 1 (definition 14.5.5) that is not an eigenvector, and $\sigma(u) = u$. As u is fixed by every power of σ, that is, by $\mathrm{Gal}_K(L)$, it lies in K (theorem 20.1.13(4)).

Step 2: the element α. As $\sigma(w) = w + N(w) = w + u$ and $\sigma(u) = u$, the element w/u of L satisfies $\sigma(w/u) = (w+u)/u = w/u + 1$, so an α as in (1) exists. Let $\alpha \in L$ be any element with $\sigma(\alpha) = \alpha + 1$. By (20.5),

$$\sigma(\alpha^p - \alpha) = (\alpha+1)^p - (\alpha+1) = \alpha^p - \alpha$$

so $\alpha^p - \alpha$ is fixed by $\mathrm{Gal}_K(L) = \langle\sigma\rangle$ and lies in K (theorem 20.1.13(4)). As $\sigma(\alpha) \neq \alpha$, $\alpha \notin K$, so $[K(\alpha) : K] > 1$. By the Tower Law (theorem 19.3.7), $[K(\alpha) : K]$ divides $[L : K]$, which is $|\mathrm{Gal}_K(L)| = p$ by theorem 20.1.13(3). Hence $[K(\alpha) : K] = p$, $[L : K(\alpha)] = 1$, and $L = K(\alpha)$.

2. For $i \in \mathbb{F}_p$, (20.5) and $i^p = i$ give $f(\alpha + i) = f(\alpha) + i^p - i = 0$. The p elements $\alpha + i$ are distinct, and f has at most p roots in E (corollary 11.3.2), so they are all of its roots, and $f = \prod_{i\in\mathbb{F}_p}(x - \alpha - i)$ by proposition 11.3.1 applied to these distinct roots in turn and a comparison of degrees. If $\alpha \in K$, every root $\alpha + i$ lies in K, and f splits into distinct linear factors over K.

   Let $\alpha \notin K$. The field $K(\alpha) \subseteq E$ contains every root $\alpha + i$ of f, and every subfield of E containing K and the roots of f contains α, so $K(\alpha)$ is a splitting field of f over K. As the p roots of f are distinct, f is separable (definition 19.6.2), and $K(\alpha)/K$ is a finite Galois extension (theorem 20.1.13(1), definition 20.1.14), finite since α is algebraic over K (theorem 19.2.8, theorem 19.2.5). Let $G = \mathrm{Gal}_K(K(\alpha))$. Each $\tau \in G$ sends α to a root of f, so $\chi(\tau) = \tau(\alpha) - \alpha$ lies in $\mathbb{F}_p$. For $\tau, \rho \in G$, the element $\chi(\rho) \in \mathbb{F}_p \subseteq K$ is fixed by τ, so $(\tau\rho)(\alpha) = \tau(\alpha + \chi(\rho)) = \alpha + \chi(\tau) + \chi(\rho)$, and $\chi\colon G \to \mathbb{F}_p$ is a homomorphism to the additive group of $\mathbb{F}_p$. It is injective: if $\chi(\tau) = 0$, then τ fixes α, hence fixes $K(\alpha)$, and $\tau = \mathrm{id}$. By theorem 3.3.1, $|G| = |\chi(G)|$ divides $|\mathbb{F}_p| = p$. As $\alpha \notin K$, $|G| = [K(\alpha) : K] > 1$ (theorem 20.1.13(3)), so $|G| = p$ and χ is bijective. So G is cyclic of order p (corollary 3.3.2), and the element $\sigma = \chi^{-1}(1)$, which satisfies $\sigma(\alpha) = \alpha + 1$, generates G, since $\langle\sigma\rangle$ has order dividing p (theorem 3.3.1) and greater than 1.

   Finally, the minimal polynomial m of α over K has degree $[K(\alpha) : K] = p$ (theorem 19.2.8, theorem 19.2.5). The polynomial $f - m$ has the root α and degree less than p, as f and m are both monic of degree p, so $f - m = 0$ by the minimality of $\deg m$ (definition 19.2.19). A factorization $f = gh$ into polynomials of positive degree would give $g(\alpha) = 0$ or $h(\alpha) = 0$, again against the minimality of $\deg m$, so f is irreducible, completing the proof.

In characteristic 0, a Galois extension is solvable exactly when it is contained in a Galois radical extension (proposition 20.2.18). In characteristic p, the radical steps are joined by the steps of theorem 20.4.12: a finite separable extension of K is contained in a Galois extension of K with solvable group if and only if it is contained in the top field of a finite tower $K = E_0 \subseteq E_1 \subseteq \cdots \subseteq E_r$ in which each E_{j+1} is obtained from E_j by adjoining a root of unity, a root of some $x^n - c$ with $c \in E_j$ and $p \nmid n$, or a root of some $x^p - x - c$ with $c \in E_j$ [70, Chapter VI, Theorem 7.2]. This book proves the cyclic steps, proposition 20.1.42 for a degree m prime to p when K contains a primitive mth root of unity and theorem 20.4.12 for degree p, and the characteristic p statement itself is deferred to that reference. There is a similar Artin-Schreier pairing, with values in $\mathbb{F}_p$ and with the additive group $K/\{c^p - c \mid c \in K\}$ in place of $K^\times/(K^\times)^n$ [70, Chapter VI, Theorem 8.3].

Exercise 20.4.1

1. Show that we can find α such that $L = K(\alpha)$ where L is a Kummer $\mathbb{Z}/n\mathbb{Z}$-extension showing all elements can be written as the sum of eigenvalues. (hint: https://www.youtube.com/watch?v=UaeJNQ5x17g&list=PL8yHsr3EFj53Zxu3iRGMYL_89GDMvdkgt&index=15)

21⋆

More Structures on Fields

⋆ *Optional. This chapter is an aside; nothing later in the book depends on it.*

The most common fields the reader will encounter are $\mathbb{Q}, \mathbb{R}$, and $\mathbb{C}$. Each of these fields are natural in some way. Here $\mathbb{Q}$ is initial in $\mathbf{Fld}_0$, $\mathbb{R}$ is the smallest complete ordered field[1], and $\mathbb{C}$ is the smallest complete and algebraically closed field. A key property all three of these fields share is that there is a notion of *size*. For $\mathbb{Q}$ and $\mathbb{R}$, there is even the stronger notion of *ordering* for all the elements. For $\mathbb{R}$ and $\mathbb{C}$, there is a notion of *differentiability*.

Recall that an order can be defined on a set (definition 0.1.14). An ordered field carries such an order, compatible with addition and multiplication, and an absolute value is a function from a field to the ordered field $\mathbb{R}$ that measures size.

This chapter shall also incorporate some topology from appendix C as it is beneficial for a deeper understanding of the subjects presented in this chapter.

[1] More technically, it is the unique Dedekind-complete ordered field up to isomorphism

21.1 Ordered and Real Fields

Definition 21.1.1: Ordered Field

Let k be a field. Then k is a *totally ordered field* (or *ordered field* for short) if there exists a (total) order $\leq$ on k such that for all $x, y, z \in k$:

1. $x < y$, then $x + z < y + z$
2. If $z > 0$, then if $x < y$, $zx < zy$

If a field k admits a total ordering, then k is said to be a *formally real field*.

Famously, $\mathbb{Q}$ and $\mathbb{R}$ are ordered fields. The reader should prove that $\mathbb{C}$ is *not* an ordered field.

Proposition 21.1.2: Properties Of Ordered Fields

Let k be an ordered field and $x, y, z \in k$. Then

1. $x > 0$ if and only if $-x < 0$ (similarly, $x < 0$ if and only if $-x > 0$)
2. $x > y$ if and only if $x - y > 0$
3. $x < y$ if and only if $-x > -y$
4. if $x > y > 0$, then $y^{-1} > x^{-1} > 0$
5. if $x < y$ and $z < 0$, then $xz > yz$
6. $x^2 \geq 0$, with $x^2 > 0$ for $x \neq 0$ (hence $1 > 0$, since $1 = 1^2 > 0$)

Furthermore, ordered fields have characteristic zero

***Proof*:**
Here $a < b$ means $a \leq b$ and $a \neq b$, and $b > a$ means $a < b$. Since the order is total (definition 0.1.14), for all a, b exactly one of $a < b$, $a = b$, $b < a$ holds: at least one holds by connectedness, and $a < b$ together with $b < a$ would give $a = b$ by antisymmetry. The relation $<$ is transitive: if $a < b < c$, then $a \leq c$, and $a = c$ would give $a \leq b \leq a$, so $a = b$, which is impossible. The two conditions of definition 21.1.1 are referred to as (O1) and (O2).

1. If $0 < x$, then (O1) with $z = -x$ gives $-x < 0$. If $-x < 0$, then (O1) with $z = x$ gives $0 < x$. Likewise, if $x < 0$, then (O1) with $z = -x$ gives $0 < -x$, and if $0 < -x$, then (O1) with $z = x$ gives $x < 0$.
2. By (O1), $y < x$ gives $0 = y - y < x - y$, and $0 < x - y$ gives $y < x$.
3. By (O1) with $z = -x - y$, $x < y$ gives $-y < -x$, and with $z = x + y$, $-y < -x$ gives $x < y$.
4. First, $a > 0$ implies $a^{-1} > 0$: the element a^{-1} is nonzero, and if $a^{-1} < 0$, then $-a^{-1} > 0$ by (1), and (O2) applied to $0 < a$ with $z = -a^{-1}$ gives $0 < -a^{-1}a = -1$, so $1 < 0$ by (1),

contradicting $1 > 0$ from (6), whose proof below uses only (1). Applying this to $a = x$ and $a = y$ gives $x^{-1} > 0$ and $y^{-1} > 0$, and (O2) applied to $0 < y^{-1}$ with $z = x^{-1}$ gives $x^{-1}y^{-1} > 0$. Now (O2) applied to $y < x$ with $z = x^{-1}y^{-1}$ gives $x^{-1} < y^{-1}$, since k is commutative. Hence $y^{-1} > x^{-1} > 0$.

5. By (1), $-z > 0$, and (O2) applied to $x < y$ with $-z$ gives $-zx < -zy$, using $(-z)x = -(zx)$ (proposition 9.1.9(2)). By (3), $zx > zy$, that is, $xz > yz$.

6. If $x > 0$, then (O2) applied to $0 < x$ with $z = x$ gives $0 = x \cdot 0 < x^2$. If $x < 0$, then $-x > 0$ by (1), so $0 < (-x)^2 = x^2$ (proposition 9.1.9(3)). Since one of $x > 0$, $x = 0$, $x < 0$ holds, $x^2 > 0$ for $x \neq 0$ and $x^2 \geq 0$ for all x. As $1 \neq 0$, $1 = 1^2 > 0$.

For the characteristic, $n \cdot 1 > 0$ for every integer $n \geq 1$, by induction: $1 > 0$ by (6), and if $n \cdot 1 > 0$, then (O1) with $z = 1$ gives $(n + 1) \cdot 1 > 1 > 0$. So $n \cdot 1 \neq 0$ for every $n \geq 1$, and k has characteristic zero (definition 19.1.7), completing the proof.

Note how this proposition immediately shows that $\mathbb{C}$ is not ordered since $-1 = i^2 \not> 0$, and that no finite field is ordered, since ordered fields have characteristic zero while in a finite field two of the elements $m \cdot 1$, $m \geq 1$, coincide, so that some $n \cdot 1$ with $n \geq 1$ vanishes. In fact, this is a characterizing property of non-ordered fields

Proposition 21.1.3: Artin-Schreier Conditions

Let k be a field. Then the following are equivalent:

1. k is formally real, that is, k admits an order making it an ordered field (definition 21.1.1)
2. -1 is *not* a sum of squares of elements of k
3. 0 is *not* a sum of squares of elements of k that are not all zero

***Proof*:**

(1 ⇒ 2) Fix such an order. Every square satisfies $x^2 \geq 0$ (proposition 21.1.2(6)), and a sum of elements $u, v \geq 0$ satisfies $u + v \geq 0$: if $u = 0$ this is $v \geq 0$, and if $u > 0$, then $v < u + v$ by (O1) of definition 21.1.1, and $0 \leq v < u + v$. By induction every sum of squares is ≥ 0, while $-1 < 0$ by proposition 21.1.2(1) and (6). So -1 is not a sum of squares.

(2 ⇒ 3) Suppose $0 = x_1^2 + \cdots + x_m^2$ with the x_i not all zero, and renumber so that $x_m \neq 0$. Then $m \geq 2$, since $x_m^2 \neq 0$ in a field, and dividing $-x_m^2 = x_1^2 + \cdots + x_{m-1}^2$ by x_m^2 gives

$$-1 = \sum_{i=1}^{m-1} \left(\frac{x_i}{x_m} \right)^2$$

contradicting (2).

(3 ⇒ 2) If $-1 = x_1^2 + \cdots + x_m^2$, then $0 = 1^2 + x_1^2 + \cdots + x_m^2$ is a sum of squares of elements that are not all zero, since $1 \neq 0$, contradicting (3).

(2 ⇒ 1) Assume -1 is not a sum of squares, and let T be the set of all sums of squares of elements of k, including $0 = 0^2$. Then $T + T \subseteq T$, $TT \subseteq T$ because

$\left(\sum_i x_i^2\right)\left(\sum_j y_j^2\right) = \sum_{i,j}(x_i y_j)^2$ (proposition 9.1.9(5) and commutativity), and $-1 \notin T$.

Step 1: a maximal cone. Let $\mathcal{P}$ be the set of subsets $P \subseteq k$ with $T \subseteq P$, $P + P \subseteq P$, $PP \subseteq P$ and $-1 \notin P$, ordered by inclusion. It contains T. A chain in $\mathcal{P}$ has an upper bound: T if the chain is empty, and otherwise the union of its members, since two elements of the union lie in a common member, which then contains their sum and product, while -1 lies in no member. By Zorn's Lemma (theorem A.2.3), $\mathcal{P}$ has a maximal element P.

Step 2: $P \cap (-P) = \{0\}$. Here $0 \in T \subseteq P$. If $a \neq 0$ and $a, -a \in P$, then, as $(a^{-1})^2 \in T \subseteq P$,

$$-1 = (-a) \cdot a \cdot (a^{-1})^2 \in P$$

which is impossible.

Step 3: $P \cup (-P) = k$. Let $a \in k$ with $-a \notin P$, and put $P' = \{x + ay \mid x, y \in P\}$. Then $P \subseteq P'$ (take $y = 0$), $P' + P' \subseteq P'$, and $P'P' \subseteq P'$ because

$$(x + ay)(z + at) = (xz + a^2 yt) + a(xt + yz)$$

with $a^2 \in T \subseteq P$. If $-1 = x + ay$ with $x, y \in P$, then $y \neq 0$, since $-1 \notin P$, and

$$-a = (1 + x) \cdot y \cdot (y^{-1})^2$$

lies in P, as $1 = 1^2 \in P$. This contradicts the choice of a, so $-1 \notin P'$ and $P' \in \mathcal{P}$. By maximality $P' = P$, so $a = 0 + a \cdot 1 \in P$. Hence every $a \in k$ lies in P or in $-P$.

Step 4: the order. Define $x \leq y$ when $y - x \in P$. This relation is reflexive as $0 \in P$, antisymmetric by Step 2, transitive since $z - x = (z - y) + (y - x)$, and connected by Step 3, so it is a total order (definition 0.1.14). If $x < y$, then $(y + z) - (x + z) = y - x$ lies in P and is nonzero, so $x + z < y + z$. If $z > 0$ and $x < y$, then $zy - zx = z(y - x) \in PP \subseteq P$, and it is nonzero as a product of nonzero elements of a field, so $zx < zy$. Hence k is an ordered field (definition 21.1.1), completing the proof.

Since any ordered field is characteristic zero, it must contain a subfield

$$Q = \left\{ \frac{m1}{n1} \;\middle|\; m, n \in \mathbb{Z} \right\}$$

field-isomorphic to $\mathbb{Q}$. In fact, Q is order-field isomorphic, for $n1 > 0$ in Q when $n > 0$ in $\mathbb{Z}$, and $m1/n1 > 0$ in Q when $m/n > 0$ in $\mathbb{Q}$, and so $a1/b1 > c1 > d$ in Q iff $a/b > c/d$ in $\mathbb{Q}$. Thus, we usually identify Q with $\mathbb{Q}$ as an ordered subfield. A property that we may take for granted that an ordered field may have is the following:

Definition 21.1.4: Archimedean Field

Let k be an ordered field. Then k is an *Archimedean field* if every positive element of k is less than a positive integer

Though it may seem like all fields have this property, there do exists field without it, most notably the *hyperreals numbers* which can be thought of as the "order completion" of the reals (think of adding an element ϵ st $0 < \epsilon < x$ for all $x > 0$ and a ω st $0 < x < \omega$ for all $x > 0$). Fortunately, all the ordered fields we shall work with will be Archimedean due to the following classification result:

Theorem 21.1.5: Classification Of Archimedean Fields

Let k be an Archimedean field. Then k is isomorphic to a field:

$$\mathbb{Q} \subseteq k' \subseteq \mathbb{R}$$

***Proof*:**
As noted above, k contains a copy of $\mathbb{Q}$ as an ordered subfield, and we identify the two. The one property of $\mathbb{R}$ used below is its completeness, that every Cauchy sequence of rationals converges in $\mathbb{R}$.

Step 1: $\mathbb{Q}$ is dense in k. Let $x < y$ in k. Since k is Archimedean there are positive integers ℓ, m, n with $-\ell < x$, $y < m$ and $1/(y-x) < n$, so that $0 < 1/n < y - x$. The set of positive integers i with $(i/n) - \ell > x$ is not empty, since $i \geq n(\ell + m)$ gives $(i/n) - \ell \geq m > y > x$, so it has a least element j. If $j \geq 2$ then $((j-1)/n) - \ell \leq x$ by minimality, and if $j = 1$ then $((j-1)/n) - \ell = -\ell < x$. Either way

$$\frac{j}{n} - \ell \leq x + \frac{1}{n} < x + (y - x) = y$$

so $r = (j/n) - \ell$ is a rational number with $x < r < y$.

Step 2: limits inside k. Say that $L = \lim_k x_n$ when $L \in k$ and, for every positive $\epsilon \in \mathbb{Q}$, the inequality $L - \epsilon < x_n < L + \epsilon$ holds for all large n. Such an L is unique: two distinct candidates $L < L'$ would admit a rational ϵ with $0 < 2\epsilon < L' - L$ by Step 1, and then no x_n could be within ϵ of both. The usual arguments give

$$\lim_k (a_n + b_n) = \lim_k a_n + \lim_k b_n \qquad \lim_k (a_n b_n) = \left(\lim_k a_n\right)\left(\lim_k b_n\right)$$

whenever the right hand sides exist, the Archimedean hypothesis being what allows the error bounds to be taken rational. A sequence with a limit in k is Cauchy in the same sense: for positive rational ϵ, $-\epsilon < a_m - a_n < \epsilon$ for all large m, n.

Step 3: the map into $\mathbb{R}$. Every $x \in k$ is a limit of rationals: by Step 1 choose $a_n \in \mathbb{Q}$ with $x - (1/n) < a_n < x + (1/n)$, and then $\lim_k a_n = x$. Such an (a_n) is a Cauchy sequence of rational numbers, so it converges in $\mathbb{R}$. If (b_n) is another sequence of rationals with $\lim_k b_n = x$, then for every positive rational ϵ we get $|a_n - b_n| < \epsilon$ for all large n, so (a_n) and (b_n) have the same

limit in $\mathbb{R}$. Hence

$$\lambda : k \to \mathbb{R} \qquad \lambda(x) = \lim_{n\to\infty} a_n \quad \text{whenever } x = \lim_k a_n \text{ with } a_n \in \mathbb{Q}$$

is well defined, and $\lambda(x) = x$ for $x \in \mathbb{Q}$, taking $a_n = x$ for all n.

Step 4: λ is an order preserving field homomorphism. If $x = \lim_k a_n$ and $y = \lim_k b_n$ with $a_n, b_n \in \mathbb{Q}$, then $x + y = \lim_k(a_n + b_n)$ and $xy = \lim_k(a_n b_n)$ by the limit laws of Step 2, while in $\mathbb{R}$ the limits of $(a_n + b_n)$ and $(a_n b_n)$ are $\lambda(x) + \lambda(y)$ and $\lambda(x)\lambda(y)$. So λ is a ring homomorphism, and it is injective, being a homomorphism of fields that is not identically zero.

Suppose $x > 0$ in k. Since k is Archimedean there is a positive integer m with $x^{-1} < m$, and then $1/m < x$. Choosing the a_n as in Step 3 and discarding the finitely many terms with $a_n \leq 1/m$, we get $\lambda(x) \geq 1/m > 0$. Applied to $y - x$ this shows that $x < y$ in k implies $\lambda(x) < \lambda(y)$, and the converse holds because $x \geq y$ would give $\lambda(x) \geq \lambda(y)$.

Therefore λ is an isomorphism of ordered fields from k onto $k' = \lambda(k)$, and $\mathbb{Q} \subseteq k' \subseteq \mathbb{R}$.

Let us focus on formally real fields. If k is formally real, then so is $k(x)$. For an algebraic extension

Proposition 21.1.6: Algebraic Extension Of Formally Real Field

Let k be a formally real field. Then if $\alpha^2 \in k$ such that $\alpha^2 > 0$, $k(\alpha)$ is a formally real field

***Proof*:**

Let α lie in an extension of k with $a := \alpha^2 \in k$, and fix an order on k witnessing formal reality, with respect to which $a > 0$. If $\alpha \in k$, then $k(\alpha) = k$ and there is nothing to prove, so assume $\alpha \notin k$, in which case α has minimal polynomial $x^2 - a$ and $\{1, \alpha\}$ is a k-basis of $k(\alpha)$.

By proposition 21.1.3, it suffices to show that -1 is not a sum of squares in $k(\alpha)$. Suppose toward a contradiction that

$$-1 = \sum_i (c_i + d_i\alpha)^2 = \sum_i (c_i^2 + d_i^2 a) + 2\left(\sum_i c_i d_i\right)\alpha$$

with $c_i, d_i \in k$, using $\alpha^2 = a$. Comparing the coefficients of 1 in the basis $\{1, \alpha\}$:

$$-1 = \sum_i c_i^2 + a\sum_i d_i^2$$

By proposition 21.1.2(6), every square in the ordered field k is non-negative, so $\sum_i c_i^2 \geq 0$ and $\sum_i d_i^2 \geq 0$, and since $a > 0$, also $a\sum_i d_i^2 \geq 0$. Hence the right hand side is non-negative, while $-1 < 0$ since $1 > 0$ by proposition 21.1.2(6), a contradiction. Therefore -1 is not a sum of squares in $k(\alpha)$, and by proposition 21.1.3, $k(\alpha)$ is formally real.

If an algebraic extension of a formally real field is formally real, then it is called a *real extension*.

Proposition 21.1.7: Odd Extension Of Formally Real Field

Let k be a formally real field. Then every finite extension of odd degree is a formally real field.

***Proof*:**
Fix an order on k witnessing formal reality. The argument is by induction on $n = [E : k]$, run simultaneously over all formally real base fields, so the inductive hypothesis reads: every extension of odd degree less than n of a formally real field is formally real. For $n = 1$ there is nothing to prove, so let $n > 1$ be odd and let $[E : k] = n$.

Suppose first that there is an $\alpha \in E \setminus k$ with $k(\alpha) \neq E$. The Tower Law (theorem 19.3.7) gives $[k(\alpha) : k] \cdot [E : k(\alpha)] = n$, so both factors divide the odd number n and both are smaller than n. By the induction hypothesis $k(\alpha)$ is formally real, and then, applying the hypothesis again over the formally real base $k(\alpha)$, so is E.

So assume $E = k(\alpha)$ for every $\alpha \in E \setminus k$. Fix such an α and let $q \in k[x]$ be its minimal polynomial, of degree n. By corollary 19.2.23 every element of E is $f(\alpha)$ for some $f \in k[x]$ with $\deg f < n$.

Suppose E were not formally real. By proposition 21.1.3 there are $f_i \in k[x]$ with $\deg f_i < n$ and

$$-1 = \sum_i f_i(\alpha)^2$$

If every f_i were constant this would exhibit -1 as a sum of squares in k, against the formal reality of k, so $d = \max_i \deg f_i$ satisfies $1 \leq d \leq n - 1$. The polynomial $1 + \sum_i f_i^2$ vanishes at α, so q divides it and

$$1 + \sum_i f_i^2 = qg$$

for some $g \in k[x]$. Its degree is exactly $2d$: the coefficient of x^{2d} in $\sum_i f_i^2$ is the sum of the squares of the leading coefficients of those f_i of degree d, and that sum is positive by proposition 21.1.2(6), hence nonzero. Therefore

$$\deg g = 2d - n$$

which is odd, since n is odd, and satisfies $\deg g < n$ because $d \leq n - 1$, and $\deg g \geq 1$ because it is a non-negative odd integer.

A product of polynomials of even degree has even degree, so g has an irreducible factor $r \in k[x]$ of odd degree, and $\deg r \leq \deg g < n$. Let β be a root of r in some extension of k. Then r is the minimal polynomial of β, so $[k(\beta) : k] = \deg r$ by theorem 19.2.8, an odd number smaller than n, and the induction hypothesis makes $k(\beta)$ formally real. But r divides g, so $g(\beta) = 0$ and

$$1 + \sum_i f_i(\beta)^2 = q(\beta)g(\beta) = 0$$

exhibits -1 as a sum of squares in $k(\beta)$, contradicting proposition 21.1.3. Hence E is formally real, completing the induction.

Using this, we can find the real closure of a formally real field:

Definition 21.1.8: Closed Real Field

Let k be a formally real field. Then k is said to be *closed* if there is no proper real algebraic extension L/k.

Theorem 21.1.9: Detecting Real Closure

Let k be a formally real field. Then k is real closed if and only if:

1. every positive element of k is a square in k
2. every polynomial of odd degree has a root in k

From these condition, we get that $\overline{k} = k(i)$ where $i^2 = -1$.

***Proof*:**
Fix an order on k witnessing formal reality. Ordered fields have characteristic zero by proposition 21.1.2, so every irreducible polynomial over k or over an extension of k is separable by corollary 19.6.8.

($\Rightarrow$) Suppose k is real closed.

For (1), let $a > 0$ in k and suppose a were not a square. A square root α of a in an algebraic closure then lies outside k, and $k(\alpha)$ is a proper algebraic extension of k which is formally real by proposition 21.1.6. That contradicts definition 21.1.8, so a is a square in k.

For (2), let $f \in k[x]$ have odd degree. Since a product of polynomials of even degree has even degree, f has an irreducible factor p of odd degree. Let β be a root of p, so $[k(\beta) : k] = \deg p$ by theorem 19.2.8. By proposition 21.1.7 the extension $k(\beta)$ is formally real, and it is algebraic over k, so definition 21.1.8 forces $k(\beta) = k$. Hence $\deg p = 1$ and $\beta \in k$ is a root of f.

($\Leftarrow$) Suppose now (1) and (2) hold.

Step A: k has no finite extension of odd degree other than itself. Let $[E : k]$ be odd and take $\alpha \in E$. The minimal polynomial q of α has degree $[k(\alpha) : k]$, which divides $[E : k]$ by the Tower Law (theorem 19.3.7) and is therefore odd. By (2) the polynomial q has a root in k, and being irreducible it must have degree 1, so $\alpha \in k$. Hence $E = k$.

Step B: every element of $C = k(i)$ is a square in C, where $i^2 = -1$. First $i \notin k$: otherwise $-1 = i^2$ would be a square, and $-1 < 0$ contradicts proposition 21.1.2(6). Next, every $a \in k$ is a square in C: for $a \geq 0$ this is (1), and for $a < 0$ we have $-a > 0$, so $-a = y^2$ with $y \in k$ and $a = (iy)^2$. Now take $a + bi$ with $b \neq 0$. We seek $x, y \in k$ with $(x + yi)^2 = a + bi$, that is

$$x^2 - y^2 = a \qquad 2xy = b$$

Note $2 = 1 + 1 > 1 > 0$ in k, by proposition 21.1.2(6) and (O1) of definition 21.1.1 applied to $0 < 1$, so $2 \neq 0$ is invertible. Substituting $y = b/(2x)$ into the first equation turns it into

$$x^4 - ax^2 - \frac{b^2}{4} = 0$$

Read as a quadratic in x^2, its discriminant is $a^2 + b^2 > 0$, hence a square in k by (1), so the

quadratic has roots $s_1, s_2 \in k$ with $s_1 s_2 = -b^2/4 = -(b/2)^2 < 0$ (proposition 21.1.2(6) and (1)). Neither root is 0, and if both were negative, then $s_1 s_2 = (-s_1)(-s_2)$ would be positive by (O2). So one of them is positive, say s_1, and (1) gives $s_1 = x^2$ for some nonzero $x \in k$. Setting $y = b/(2x)$ and using $s_1^2 - a s_1 - b^2/4 = 0$,

$$x^2 - y^2 = s_1 - \frac{b^2}{4s_1} = a \qquad 2xy = b$$

so $a + bi = (x + yi)^2$.

Step C: C has no extension of degree 2. Every quadratic $\alpha x^2 + \beta x + \gamma \in C[x]$ has a root in C, since $\beta^2 - 4\alpha\gamma$ has a square root in C by Step B and 2α is invertible. So no polynomial of degree 2 is irreducible in $C[x]$. If $[E : C] = 2$ and $\alpha \in E \setminus C$, then $[C(\alpha) : C]$ divides 2 and exceeds 1, so the minimal polynomial of α over C would be irreducible of degree 2, which cannot happen.

Step D: $\overline{k} = C$. Let $\alpha \in \overline{k}$ and let E be the splitting field over k of the product of $x^2 + 1$ with the minimal polynomial of α over k. Then $C \subseteq E$, and E/k is finite, normal and separable, hence Galois by theorem 20.1.13(2). Put $G = \mathrm{Gal}_k(E)$, so $|G| = [E : k] = [E : C][C : k] = 2[E : C]$ is even by theorem 20.1.13(3) and the Tower Law.

Let S be a Sylow 2-subgroup of G, which exists by theorem 4.8.6(1), and let $F = E^S$. By proposition 20.1.12, $S = \mathrm{Aut}_F(E)$, so $[E : F] = |S|$ by theorem 20.1.13(3) applied to the Galois extension E/F, and the Tower Law gives $[F : k] = |G|/|S| = [G : S]$, an odd number. Step A forces $F = k$, so $[G : S] = 1$ and G is a 2-group.

Then $H = \mathrm{Gal}_C(E)$ is a subgroup of G, hence a 2-group. Suppose $H \neq 1$. A nontrivial finite group of order 2^m has a subgroup of index 2, by induction on m: this is clear for $m = 1$, and for $m > 1$ the centre is nontrivial by theorem 4.6.5, so corollary 3.3.9 gives a central element z of order 2, the subgroup $\langle z \rangle$ is normal, and a subgroup of index 2 in the smaller 2-group $H/\langle z \rangle$ pulls back to one in H by the Correspondence Theorem (theorem 3.5.7). Taking such a subgroup $H' \leqslant H$ of index 2 and arguing with the Galois correspondence for E/C as above, its fixed field $E^{H'}$ satisfies $[E^{H'} : C] = [H : H'] = 2$, contradicting Step C. Hence $H = 1$ and $E = C$ by theorem 20.1.13(4), so $\alpha \in C$. Therefore $\overline{k} = C = k(i)$.

Step E: k is real closed. By Step D, $[\overline{k} : k] = 2$, so the only proper algebraic extension of k inside $\overline{k}$ is $\overline{k} = k(i)$ itself. It is not formally real, since $-1 = i^2$ is a square there. Any proper algebraic extension L/k embeds in $\overline{k}$ over k by lemma 19.5.7, and formal reality is preserved by isomorphism, so k has no proper real algebraic extension, which is definition 21.1.8.

Due to this, a real closed field can be made into an ordered field in a unique way, namely $x \leq y$ if and only if $y - x = a^2$ for some $a \in k$. It should also be clear that the field of all algebraic real numbers is certainly a real closed field.

Corollary 21.1.10: Irreducible Elements In Real Closed Field

Let k be a real closed field. Then $f \in k[x]$ is irreducible if and only if f has degree 1 or f has degree 2 with no roots

***Proof*:**
($\Leftarrow$) A degree 1 polynomial is irreducible, since in a factorization into two nonunits both factors have degree at least 1, giving total degree at least 2 by proposition 9.2.3(1). A degree 2 polynomial with no root in k is irreducible by proposition 11.3.5.

($\Rightarrow$) Let f be irreducible, so $\deg f \geq 1$. By theorem 21.1.9, $\overline{k} = k(i)$ where $i^2 = -1$. Note $i \notin k$: the field k is formally real, and if $-1 = c^2$ for some $c \in k$, then $-1 \geq 0$ in an order on k by proposition 21.1.2(6), contradicting $1 > 0$. Hence $[\overline{k} : k] = [k(i) : k] = 2$. Since $\overline{k}$ is algebraically closed, f has a root $\alpha \in \overline{k}$, and the Tower Law (theorem 19.3.7) applied to $k \subseteq k(\alpha) \subseteq \overline{k}$ gives $[k(\alpha) : k] \in \{1, 2\}$.

Now f is, up to a unit, the minimal polynomial of α: the minimal polynomial p divides f (dividing f by p leaves a remainder vanishing at α of degree less than $\deg p$, which must be 0), and f is irreducible, so $f = up$ with u a unit. By theorem 19.2.8, $k(\alpha) \cong k[x]/(p)$, so $\deg f = \deg p = [k(\alpha) : k] \leq 2$.

If $\deg f = 2$ and f had a root $c \in k$, then dividing by $x - c$ would factor f into two linear factors, contradicting irreducibility. Hence f has degree 1, or degree 2 with no roots in k.

Finally, we have:

Theorem 21.1.11: Real Closure

Every formally real field has a real closure

***Proof*:**
Let k be formally real and fix an order on it, with $P = \{a \in k \mid a > 0\}$. From definition 21.1.1, P is closed under addition and under multiplication: $x, y > 0$ gives $x + y > y > 0$ and $xy > x \cdot 0 = 0$. Fix an algebraic closure $\overline{k}$, which exists by theorem 19.5.6. By a *real closure* of k we mean an algebraic extension of k that is real closed.

Step 1: adjoining square roots of positive elements keeps the field formally real. Let $a_1, \ldots, a_n \in P$ and put $L_m = k(\sqrt{a_1}, \ldots, \sqrt{a_m}) \subseteq \overline{k}$. We show by induction on m the statement

$$(*_m): \qquad \text{no relation } \sum_j p_j z_j^2 = -1 \text{ holds with } p_j \in P \text{ and } z_j \in L_m$$

For $m = 0$ this is clear, since each $p_j z_j^2 \geq 0$ by proposition 21.1.2(6) and closure of P under multiplication, so the left hand side is nonnegative while $-1 < 0$. Suppose $(*_{m-1})$ and write $\alpha = \sqrt{a_m}$. If $\alpha \in L_{m-1}$ then $L_m = L_{m-1}$ and there is nothing to do, so assume otherwise, in which case $\{1, \alpha\}$ is an L_{m-1}-basis of L_m and $\alpha^2 = a_m$. A relation $\sum_j p_j (c_j + d_j \alpha)^2 = -1$ with $c_j, d_j \in L_{m-1}$ expands to

$$\sum_j p_j \left(c_j^2 + a_m d_j^2\right) + 2\alpha \sum_j p_j c_j d_j = -1$$

and comparing the coefficients of 1 in the basis $\{1, \alpha\}$ leaves

$$\sum_j p_j c_j^2 + \sum_j (p_j a_m) d_j^2 = -1$$

Every p_j and every $p_j a_m$ lies in P, so this contradicts $(*_{m-1})$. This proves $(*_m)$.

Taking all $p_j = 1$ shows -1 is not a sum of squares in L_n. Now let $E \subseteq \overline{k}$ be the subfield generated over k by all square roots of elements of P. A relation expressing -1 as a sum of squares in E involves finitely many elements, hence lies in some L_n, so no such relation exists and E is formally real by proposition 21.1.3.

Step 2: a maximal formally real extension. Let Σ be the set of subfields F with $E \subseteq F \subseteq \overline{k}$ that are formally real, partially ordered by inclusion. It contains E, and the union of a chain in Σ is again in Σ, since a relation exhibiting -1 as a sum of squares in the union involves finitely many elements and so already holds in one member of the chain. By Zorn's lemma Σ has a maximal element R, and R is algebraic over k, being a subfield of $\overline{k}$.

Step 3: R is real closed. Let L/R be a proper algebraic extension. Since $\overline{k}$ is algebraic over k and algebraically closed, it is an algebraic closure of R as well, so lemma 19.5.7 gives a homomorphism $L \to \overline{k}$ fixing R. Its image is a subfield of $\overline{k}$ properly containing R, hence containing E, so maximality of R says the image is not formally real. Formal reality is preserved by isomorphism, so L is not formally real. Therefore R has no proper real algebraic extension and is real closed by definition 21.1.8.

Step 4: the order of R induces that of k. Whatever order R carries, its positive elements are squares by theorem 21.1.9(1) and its nonzero squares are positive by proposition 21.1.2(6), so the positive elements of R are exactly the nonzero squares, so the order on R is determined by the field structure. Every $a \in P$ is a square in $E \subseteq R$, hence positive in R, and if $a < 0$ in k then $-a \in P$ is positive in R, so a is negative in R. Thus the order of R restricts to the given order of k, and R is a real closure of k.

The reader should verify that any two real closures of k are order-field isomorphic.

Finally, we state without proof the following characterization of real-closed fields that show a naturalness to the choice of $\mathbb{R}$

Theorem 21.1.12: Artin-Schreier Theorem

Let $k \neq \overline{k}$ be a field. Then the following are equivalent:

1. k is real closed
2. $[\overline{k} : k]$ is finite
3. there is an upper bound for the degrees of irreducible polynomials in $k[x]$

***Proof*:**
Deferred. The implications (1) ⇒ (2) and (2) ⇒ (3) are immediate. For the first, theorem 21.1.9 gives $\overline{k} = k(i)$ for real closed k, so $[\overline{k} : k] = 2$ is finite. For the second, if $[\overline{k} : k]$ is finite and $p \in k[x]$ is irreducible with a root $\alpha \in \overline{k}$, then $\deg p = [k(\alpha) : k] \leq [\overline{k} : k]$ by theorem 19.2.8 and the Tower Law (theorem 19.3.7). The content is (3) ⇒ (1), and it rests on three inputs, which this book carries only in part:

1. a bound on the degrees of irreducible polynomials in $k[x]$ forces k to be perfect, proved by showing $x^{p^r} - c$ is irreducible for every r when c is not a pth power.

2. if -1 is a square in a field F, then $\overline{F}$ is not a Galois extension of F of prime degree p. This is the substantial step, and it splits by characteristic. For $p \neq \mathrm{ch}(F)$, the pth roots of unity have degree less than p over F, hence lie in F by the Tower Law, and proposition 20.1.42 gives $\overline{F} = F(\alpha)$ with $\alpha^p \in F$. What is missing there is the irreducibility criterion for binomials $x^n - c$ of [70, Chapter VI, Theorem 9.1], applied to $x^{p^2} - \alpha^p$. For $p = \mathrm{ch}(F)$, theorem 20.4.12 gives $\overline{F} = F(\alpha)$ with $\alpha^p - \alpha \in F$, and what is missing is a cyclic extension of F of degree p^2 containing $F(\alpha)$ [70, Chapter VI, Exercise 29], which cannot exist when $[\overline{F} : F] = p$.

3. a Sylow argument on $\mathrm{Gal}(\overline{k}/k)$ of the same shape as the one in Step D of the proof of theorem 21.1.9, which cuts the degree down to a prime and feeds the previous item.

The classifications of cyclic extensions of prime degree that item (2) uses are proposition 20.1.42 and theorem 20.4.12. The irreducibility criterion, the extension of degree p^2 and the Sylow argument are not in this book, and [70, Chapter VI, Corollary 9.3] combines them into a proof that $\overline{k} = k(i)$ whenever $1 < [\overline{k} : k] < \infty$.

A variant of the theorem is worth recording, also without proof. Let G_K denote the absolute Galois group of a field K, and let $\sigma \in G_K$ be an involution, so that $\sigma \neq \mathrm{id}$ and $\sigma \circ \sigma = \mathrm{id}$. Then the fixed field $\overline{K}^{\sigma}$ is real closed. The two statements carry the same content, since the fixed field of an involution sits at degree 2 below $\overline{K}$ and theorem 21.1.12 then applies to it.

21.1.1 The Fields That Carry a Geometry

A vector space over an arbitrary field has no length and no angle, and section 13.6 recorded what producing them takes: an ordering, so that $\langle v, v\rangle$ can be called nonnegative, and a conjugation, so that $\langle v, v\rangle$ can be forced into the ordered field underneath. Both were described there as structure that $\mathbb{R}$ and $\mathbb{C}$ happen to carry. The results of this section say where that structure comes from, and how little freedom there was in it.

Whether a field can support a notion of positivity at all is decided by the field itself. By proposition 21.1.3, k admits a total order exactly when -1 is not a sum of squares, a condition stated in the ring operations alone with no order mentioned.

One step further up, the order and the conjugation both stop being choices. Let k be real closed. Every positive element of k is a square by theorem 21.1.9, and every nonzero square is positive by proposition 21.1.2(6), so the positive elements are exactly the nonzero squares. Hence $x \leq y$ holds if and only if $y - x$ is a square, and the order is recovered from the field operations rather than imposed on them. The same theorem gives $\overline{k} = k(i)$. Since -1 is not a square in a formally real field this extension has degree 2. It is the splitting field of $x^2 + 1$ over k, hence normal, and separable because an ordered field has characteristic zero (proposition 21.1.2). So $k(i)/k$ is Galois, $\mathrm{Gal}(\overline{k}/k)$ has order 2, and its one nontrivial element is $a + bi \mapsto a - bi$. A real closed field therefore comes with a unique order and a unique conjugation, both determined by k.

Corollary 21.1.10 gives the third property. Over a real closed k every irreducible polynomial has degree 1 or 2, so a characteristic polynomial factors into linear and quadratic pieces over k itself and not only over $\overline{k}$.

Theorem 21.1.12 says that no other configuration of this shape exists. If $k \neq \overline{k}$ and $[\overline{k} : k]$ is finite, then k is real closed and the degree is 2. In particular no field has an algebraic closure of degree 3: a field sits at finite distance below its algebraic closure in exactly one way, and that way is the real closed one.

What none of this pins down is $\mathbb{R}$. The field of real algebraic numbers is real closed as well and satisfies every condition above, so the separation between the two is order-completeness rather than an algebraic property. Theorem 21.1.5 gives the algebraic half of that separation by placing every Archimedean field between $\mathbb{Q}$ and $\mathbb{R}$. The geometry built on the order and the conjugation (inner products, orthogonality, adjoints, the spectral theorem) is carried out over $\mathbb{R}$ and $\mathbb{C}$ in *Linear Algebra* [31].

21.2 Absolute Values on General Fields

In an ordered field, $-1 < 0$ and every square is nonnegative, by proposition 21.1.2(1) and (6), so $-1 = i^2$ shows that $\mathbb{C}$ is not an ordered field. The next best thing is some notion of "size". Intuitively, size is a totally ordered concept, and hence the absolute value shall be a function that will capture the intuition of size with codomain $\mathbb{R}$:

Definition 21.2.1: Absolute Value

Let k be a field. Then an *absolute value real valuation* on k is a function $v : k \to \mathbb{R}$ whose image is denoted $|x|_v$ such that

1. (positivity) $|x|_v \geq 0$ for all $x \in k$ and $|x|_v = 0$ if and only if $x = 0$
2. (multiplicative) $|xy|_v = |x|_v|y|_v$
3. (triangle inequality) $|x + y|_v \leq |x|_v + |y|_v$

If the absolute value is unambiguous, $|x|_v$ will be denoted $|x|$. If the image of v is a finitely generated abelian group, then $|-|_v$ is called a *discrete absolute value*

21.2.2 Note The reader should be careful with the definition *real valuation* as there is a different concept called *valuation* that is not a generalization o specialization of the above (see definition 27.1.1).

If the reader is familiar with norms, then this can be thought of as the field-equivalent as norms are defined on vector-spaces. In fact, taking a field to be a vector-space over itself, the existence of a absolute value induces a norm. If the reader is familiar with some Lebesgue space theory, they may recall Hölder's inequality stating that:

$$\|fg\|_1 \leq \|f\|_p \|g\|_q \qquad \frac{1}{p} + \frac{1}{q} = 1$$

which contrasts with the strict equality result given above. Recall that equality happens if and only if $\alpha|f|^p = \beta|g|^q$ for $\alpha, \beta \neq 0$, that is they are "power multiples" of each other. This is certainly the case for fields. Furthermore, there is only one absolute value instead of the 3 norms present in Hölder's

inequality. A norm that satisfies the 2nd condition (on an algebra!) is called a *multiplicative norm*, and implies certain geometric invariances in the space.

Example 21.2.3: Absolute Values

1. The usual absolute values on $\mathbb{Q}, \mathbb{R}, \mathbb{C}$ all satisfy the above definition
2. For any field k, there always exists the trivial valuation
$$|x|_t = 1 \qquad x \neq 0$$
This real valuation shall be an example of a *nonarchimedean* real valuation.
3. Let k be any field and take $k(x)$, the simple transcendental extension of k. Then there are two interesting valuations that may be defined. The first is called the infinity valuation:
$$|f/g|_\infty = \begin{cases} 2^{\deg f - \deg g} & f \neq 0 \\ 0 & f = 0 \end{cases}$$
and the 0 valuation:
$$|f/g|_0 = \begin{cases} 2^{\operatorname{ord} f - \operatorname{ord} g} & f \neq 0 \\ 0 & f = 0 \end{cases}$$
where $\operatorname{ord}(f)$ for a polynomial $f(x) = a_0 + a_1 x_1 + \cdots + a_n x^n$ to be the smallest $k \geq 0$ such that $a_k \neq 0$. The choice of 2 was arbitrary in both and can be replaced with any positive constant.
From the 0-valuation, we may define:
$$\left|\frac{f(x)}{g(x)}\right|_a = \left|\frac{f(x-a)}{g(x-a)}\right|_0$$
These valuations when restricted to k are all trivial.

With positivity and the triangle inequality, the absolute value can define a metric (see appendix C) and hence a metric topology on a field:
$$d(x, y) = |x - y|_v$$
For the p-adic case, the idea behind this metric is that $|x - y|$ is small is $x \equiv y \bmod p^n$ for a large n, that is a large power of p divides the difference.

Proposition 21.2.4: Equivalent Topoloies

Let v, w be two absolutes values on a field k. Then the following are equivalent:

1. v, w induce the same topology on k
2. Given $x \in k$, $|x|_v < 1$ if and only if $|x|_w < 1$
3. There exists a real number $n > 0$ such that $|x|_w = |x|_v^n$ for all $x \in k$

***Proof*:**

Throughout we use two consequences of multiplicativity: $|1| = |1 \cdot 1| = |1|^2$ with $|1| \neq 0$ gives $|1| = 1$, and then $|x||x^{-1}| = |1| = 1$ gives $|x^{-1}| = |x|^{-1}$ for $x \neq 0$.

(1) $\Rightarrow$ (2): In the metric topology of an absolute value, $x^j \to 0$ as $j \to \infty$ if and only if $|x^j| = |x|^j \to 0$ in $\mathbb{R}$, which happens if and only if $|x| < 1$. Convergence of a sequence to 0 depends only on the topology, so if the two topologies agree, then $|x|_v < 1$ if and only if $x^j \to 0$ if and only if $|x|_w < 1$.

(2) $\Rightarrow$ (3): First note that (2) also gives: $|x|_v > 1$ if and only if $|x|_w > 1$ (apply (2) to x^{-1}), and hence $|x|_v = 1$ if and only if $|x|_w = 1$. If $|x|_v = 1$ for every $x \neq 0$, then the same holds for w, and $n = 1$ works. Otherwise pick $x_0 \neq 0$ with $|x_0|_v \neq 1$. Replacing x_0 by x_0^{-1} if needed, we may assume $|x_0|_v > 1$, and then $|x_0|_w > 1$. Set

$$n := \frac{\log |x_0|_w}{\log |x_0|_v} > 0$$

Fix $x \neq 0$ and let $\lambda \in \mathbb{R}$ be defined by $|x|_v = |x_0|_v^\lambda$, that is, $\lambda = \log |x|_v / \log |x_0|_v$. For any rational $p/q > \lambda$ with $q > 0$, we have $|x|_v^q < |x_0|_v^p$, so

$$\left|\frac{x^q}{x_0^p}\right|_v < 1 \qquad \overset{(2)}{\Rightarrow} \qquad \left|\frac{x^q}{x_0^p}\right|_w < 1 \qquad \Rightarrow \qquad |x|_w < |x_0|_w^{p/q}$$

and symmetrically, for any rational $p/q < \lambda$ with $q > 0$, we get $|x|_w > |x_0|_w^{p/q}$. Since the rationals are dense in $\mathbb{R}$ and $t \mapsto |x_0|_w^t$ is continuous and increasing, letting p/q approach λ from both sides gives $|x|_w = |x_0|_w^\lambda$. Hence

$$|x|_w = |x_0|_w^\lambda = (|x_0|_v^n)^\lambda = \left(|x_0|_v^\lambda\right)^n = |x|_v^n$$

and for $x = 0$ both sides are 0, proving (3).

(3) $\Rightarrow$ (1): For every $x \in k$ and $\epsilon > 0$, the metric balls satisfy

$$\{y \in k \mid |x - y|_w < \epsilon\} = \{y \in k \mid |x - y|_v^n < \epsilon\} = \left\{y \in k \;\middle|\; |x - y|_v < \epsilon^{1/n}\right\}$$

so every w-ball is a v-ball and, using the exponent $1/n$, every v-ball is a w-ball. The two metrics therefore generate the same topology.

The following can be thought of as the Chinese Remainder Theorem for real valuations

Proposition 21.2.5: Approximation Theorem

Let $|-|_1, ..., |-|_n$ be pairwise inequivalent *nontrivial* valuations for a field K, and let $a_1, \ldots, a_n \in K$. Then for every $\epsilon > 0$ there exists an $x \in K$ such that

$$|x - a_i|_i < \epsilon \qquad \forall 1 \leq i \leq n$$

***Proof*:**
For $n = 1$ the element $x = a_1$ works, so assume $n \geq 2$ throughout.

Two facts about an absolute value are used repeatedly: $|1| = 1$ and $|x^{-1}| = |x|^{-1}$, both proved at the start of proposition 21.2.4, and the reverse triangle inequality $|u + v| \geq \big||u| - |v|\big|$, which follows from the triangle inequality applied to $u = (u + v) - v$.

Step 1: one implication already forces equivalence. Let v, w be nontrivial absolute values on K with $|x|_v < 1 \Rightarrow |x|_w < 1$ for every x. Applying this to x^{-1} gives $|x|_v > 1 \Rightarrow |x|_w > 1$. Suppose $|x|_v = 1$ while $|x|_w \neq 1$. Replacing x by x^{-1} we may assume $|x|_w > 1$. Since v is nontrivial there is a $z \neq 0$ with $|z|_v \neq 1$, and replacing z by z^{-1} we may assume $|z|_v < 1$. Then $|x^m z|_v = |z|_v < 1$ for every $m \geq 0$, so $|x^m z|_w < 1$, that is $|x|_w^m |z|_w < 1$ for every m. This is impossible, since $|x|_w > 1$ makes $|x|_w^m$ exceed $|z|_w^{-1}$ for m large. Hence $|x|_v = 1$ if and only if $|x|_w = 1$, and therefore $|x|_w < 1$ forces $|x|_v < 1$, since $|x|_v \geq 1$ would give $|x|_w \geq 1$. The second condition of proposition 21.2.4 holds, so v and w are equivalent.

Step 2: separating two of them. Let $i \neq j$. Since $|-|_i$ and $|-|_j$ are inequivalent and nontrivial, Step 1 says both implications fail, so there are $a, b \in K$ with

$$|a|_i < 1 \leq |a|_j \qquad |b|_j < 1 \leq |b|_i$$

Then $y = b/a$ satisfies $|y|_i = |b|_i/|a|_i > 1$ and $|y|_j = |b|_j/|a|_j < 1$.

Step 3: separating one from all the others. We claim there is $z \in K$ with $|z|_1 > 1$ and $|z|_j < 1$ for $j = 2, \ldots, n$, and argue by induction on n. The case $n = 2$ is Step 2. So let z satisfy $|z|_1 > 1$ and $|z|_j < 1$ for $2 \leq j \leq n - 1$, and let y be as in Step 2 for the pair $(1, n)$, so $|y|_1 > 1$ and $|y|_n < 1$.

If $|z|_n \leq 1$, take $w = z^m y$. Then $|w|_1 = |z|_1^m |y|_1 > 1$ and $|w|_n = |z|_n^m |y|_n < 1$ for every m, while $|w|_j = |z|_j^m |y|_j < 1$ for $2 \leq j \leq n - 1$ once m is large, because $|z|_j < 1$.

If $|z|_n > 1$, put $t_m = z^m/(1 + z^m)$, which is defined because $|z^m|_1 > 1 = |-1|_1$ forces $z^m \neq -1$. Then

$$|t_m - 1|_1 = \frac{1}{|1 + z^m|_1} \leq \frac{1}{|z|_1^m - 1} \qquad |t_m - 1|_n \leq \frac{1}{|z|_n^m - 1} \qquad |t_m|_j \leq \frac{|z|_j^m}{1 - |z|_j^m}$$

for $2 \leq j \leq n - 1$, using the reverse triangle inequality in each denominator. So $t_m \to 1$ with respect to $|-|_1$ and $|-|_n$, and $t_m \to 0$ with respect to $|-|_2, \ldots, |-|_{n-1}$. Taking $w = t_m y$, the three quantities $|w|_1, |w|_n, |w|_j$ tend to $|y|_1 > 1$, to $|y|_n < 1$ and to 0 respectively, so w has the required properties once m is large.

Step 4: the approximation. Permuting the indices in Step 3, choose for each i an element $z_i \in K$ with $|z_i|_i > 1$ and $|z_i|_j < 1$ for $j \neq i$, and set

$$u_{i,m} = \frac{z_i^m}{1 + z_i^m}$$

which is defined for the reason given in Step 3. The estimates of Step 3 give

$$|u_{i,m} - 1|_i \leq \frac{1}{|z_i|_i^m - 1} \qquad |u_{i,m}|_j \leq \frac{|z_i|_j^m}{1 - |z_i|_j^m} \quad (j \neq i)$$

so $u_{i,m} \to 1$ with respect to $|-|_i$ and $u_{i,m} \to 0$ with respect to every $|-|_j$ with $j \neq i$. Now put

$$x = \sum_{i=1}^{n} a_i u_{i,m}$$

For each fixed i, the triangle inequality gives

$$|x - a_i|_i \leq |a_i|_i \, |u_{i,m} - 1|_i + \sum_{j \neq i} |a_j|_i \, |u_{j,m}|_i$$

and every term on the right tends to 0 as m grows. There are finitely many indices i, so one m makes all n of these bounds smaller than ϵ at once, and that x satisfies $|x - a_i|_i < \epsilon$ for all i.

As mentioned earlier, the trivial valuation is non-Archimedean. The following show that non-Archimedean valuations can be thought of as absolute values induced by *ultra-metrics*

Definition 21.2.6: Archimedean Valuation

Let v be a real valuation on a field k. Then if for all $x \in k$, there exists a $n \in \mathbb{N}$ such that

$$|x|_v < |n|_v$$

the valuation is called an *Archimedean valuation*. On the other hand, if there exists an x such that for all $n \in \mathbb{N}$:

$$|n|_v \leq |x|_v \qquad \forall n \in \mathbb{N}$$

Then v is called a *non-Archimedean valuation*.

Proposition 21.2.7: Characterizing Non-Archimedean Valuation

Let v be a real valuation on a field k. Then the following are equivalent:

1. v is non-Archimedean
2. $|n|_v \leq 1$ for all $n \in \mathbb{N}$
3. $|n|_v \leq 1$ for all $n \in \mathbb{Z}$
4. for all $x, y \in k$,
$$|x + y|_v \leq \max(|x|_v, |y|_v)$$

The final inequality upgrading the triangle inequality is called the *strong triangle inequality* or *ultra-metric inequality*.

Note that if $|x| \neq |y|$ in an ultra-metric , then $|x + y| = \max(|x|, |y|)$!

***Proof*:**

(1) $\Rightarrow$ (2) Let v be a non-Archimedean valuation. For the sake of contradiction, suppose that for some $n \in \mathbb{N}$, $|n|_v > 1$. Then by multiplicity we may have an $|n|_v$ with

an arbitrarily large valuation:

$$|n^k| = |n|_v^k \xrightarrow{k\to\infty} \infty$$

Which would imply there is no $x \in k$ such that $|n|_v \leq |x|_v$ for all $n \in \mathbb{N}$.

(2) $\Rightarrow$ (3) show that $|-1| = |1|$ and use this to conclude.

(3) $\Rightarrow$ (4) Take:

$$\begin{aligned}
|x+y|^n &= \left|\sum_k^n \binom{n}{k} x^k y^{n-k}\right| \\
&\leq \sum_k^n \left|\binom{n}{k}\right| |x|^k |y|^{n-k} \\
&\leq \sum_k^n |x|^k |y|^{n-k} \\
&\leq (n+1)\max(|x|^n, |y|^n)
\end{aligned}$$

Hence

$$|x+y| \leq (n+1)^{1/n} \max(|x|, |y|)$$

As this is true for all n, and $(n+1)^{1/n} \xrightarrow{n\to\infty} 1$, we get the desired result

(4) $\Rightarrow$ (1) by induction we get:

$$|n| = |1+1+\cdots+1| \leq |1| = 1$$

giving the desired result.

Corollary 21.2.8: Values On different characteristic

Let k be a field with characteristic $p \neq 0$. Then there does not exist an Archimedean valuation on k.

If k is a finite field, the only valuation is the trivial valuation.

***Proof*:**

First note that for any valuation v and any root of unity $u \in k$, say $u^d = 1$, multiplicativity gives $|u|_v^d = |u^d|_v = |1|_v$, and $|1|_v = |1 \cdot 1|_v = |1|_v^2$ with $|1|_v \neq 0$ forces $|1|_v = 1$. Since $|u|_v$ is a positive real number with $|u|_v^d = 1$, we get $|u|_v = 1$.

Now let k have characteristic $p \neq 0$ and let v be any valuation on k. The elements $n \cdot 1_k$ for $n \in \mathbb{N}$ all lie in the prime subfield $\mathbb{F}_p \subseteq k$. Every nonzero element u of $\mathbb{F}_p$ satisfies $u^{p-1} = 1$, since the multiplicative group $\mathbb{F}_p^\times$ has order $p-1$ and the order of u divides it by Lagrange's theorem (theorem 3.3.1). Hence $|n|_v = 1$ whenever $n \cdot 1_k \neq 0$, and $|n|_v = 0$ otherwise, so $|n|_v \leq 1 = |1|_v$ for all $n \in \mathbb{N}$. Thus $x = 1$ witnesses that v is non-Archimedean, and no Archimedean valuation exists on k.

For the second claim, let k be a finite field with q elements and v a valuation on k. The group

$k^\times$ has order $q-1$, so every $u \neq 0$ satisfies $u^{q-1} = 1$ by Lagrange's theorem (theorem 3.3.1), and by the first paragraph $|u|_v = 1$. Hence v is the trivial valuation.

In the case of characteristic 0, given $k = \mathbb{Q}$, all the absolute values may be classified. Define p-valuation to be:

$$v_p(m/n) = \begin{cases} p^{-k} & \frac{m}{n} = p^k \frac{m'}{n'} \neq 0,\ p \nmid m', n' \\ 0 & \frac{m}{n} = 0 \end{cases}$$

Theorem 21.2.9: Classification Of Absolute Values On Rationals

Every non-trivial absolute value on $\mathbb{Q}$ is equivalent, in the sense of proposition 21.2.4, to v_p for exactly one prime p, or to the usual absolute value $|-|_\infty$.

This result is due to Ostrowski.

***Proof*:**

Write $|-|$ for the absolute value. Suppose first that it is non-Archimedean, so $|n| \leq 1$ for all $n \in \mathbb{Z}$ (proposition 21.2.7). If $|n| = 1$ for every nonzero $n \in \mathbb{Z}$, then $|m/n| = |m|/|n| = 1$ for all nonzero m/n, and $|-|$ is trivial. So $P = \{n \in \mathbb{Z} \mid |n| < 1\}$ contains a nonzero element. It is an ideal, closed under sums by the strong triangle inequality and under multiples since $|an| \leq |n|$. It is proper since $|1| = 1$, and prime since $|ab| < 1$ with $|a|, |b| \leq 1$ forces $|a| < 1$ or $|b| < 1$. As $\mathbb{Z}$ is a Principal Ideal Domain, $P = (p)$ for a prime p. Let $c = |p| < 1$. If $m/n = p^k m'/n'$ with $p \nmid m', n'$, then $m', n' \notin P$, so $|m'| = |n'| = 1$ and $|m/n| = c^k$. With $s = -\log c / \log p > 0$, this is $v_p(m/n)^s$, so $|-|$ is equivalent to v_p (proposition 21.2.4). The prime is unique, since $|p|_{v_p} < 1$ while $|p|_{v_q} = 1$ for a prime $q \neq p$.

Suppose now that $|-|$ is Archimedean. Let $m, n \geq 2$ be integers and write $m = a_0 + a_1 n + \cdots + a_r n^r$ with $0 \leq a_i < n$ and $r \leq \log m / \log n$. The triangle inequality and $|1| = 1$ give $|a_i| \leq a_i < n$, so

$$|m| \leq (r+1)\, n \max(1, |n|)^r \leq \left(1 + \frac{\log m}{\log n}\right) n \max(1, |n|)^{\log m / \log n}$$

Applying this to m^t and taking t-th roots,

$$|m| \leq \left(1 + t\frac{\log m}{\log n}\right)^{1/t} n^{1/t} \max(1, |n|)^{\log m / \log n}$$

for every $t \geq 1$, and letting $t \to \infty$ gives $|m| \leq \max(1, |n|)^{\log m / \log n}$. Since $|-|$ is Archimedean, some integer $N \geq 2$ has $|N| > 1$ (proposition 21.2.7). If some $n \geq 2$ had $|n| \leq 1$, the inequality with $m = N$ would give $|N| \leq 1$. So $|n| > 1$ for every $n \geq 2$, and the inequality reads $|m|^{1/\log m} \leq |n|^{1/\log n}$. Exchanging m and n gives equality, so $|n| = n^s$ for all $n \geq 2$, with $s = \log|2| / \log 2 > 0$. Since $|-1|^2 = |1| = 1$, $|-1| = 1$, and multiplicativity gives $|x| = |x|_\infty^s$ for every $x \in \mathbb{Q}$. So $|-|$ is equivalent to $|-|_\infty$ (proposition 21.2.4).

In *Commutative Algebra* [20] (valuation rings and DVRs), many of these concepts shall be generalized to more general valuations, namely we have been working with *real* valuations, however there are more generally G-valuations for totally ordered groups G.

In an analysis class, the absolute value is used to define the completion of a ring. A sequence (x_n) in a field k with an absolute value $|-|$ is *Cauchy* if for every real $\epsilon > 0$ there is an N with $|x_n - x_m| < \epsilon$

for all $n, m \geq N$, and k is *complete* if every Cauchy sequence converges in k. The construction of $\mathbb{R}$ from $\mathbb{Q}$ carries over: the Cauchy sequences of k modulo the sequences converging to 0 form a complete field $\widehat{k}$, the *completion* of k. It contains k, as the classes of constant sequences, as a dense subfield, and it carries the absolute value $|(x_n)| = \lim_n |x_n|$ extending that of k (see [83, Chapter II, §4]).

21.2.1 Ostrowski Theorem

Theorem 21.2.10: Ostrowski's Theorem For Complete Fields

Let K be a field complete with respect to an Archimedean absolute value $|-|$. Then there is an isomorphism σ from K onto $\mathbb{R}$ or $\mathbb{C}$ and some $s \in (0, 1]$ with $|a| = |\sigma(a)|^s$ for all $a \in K$, where $\mathbb{R}$ and $\mathbb{C}$ carry their usual absolute values.

The proof reduces to the case where the absolute value restricts to the usual one on $\mathbb{Q}$ (theorem 21.2.9) and is given in [83, Chapter II, Theorem 4.2].

21.3 Derivation on Field

Derivations are the algebraic form of differentiation, and the module of relative differential forms packages every derivation of a ring into a single universal one. The construction is pure commutative algebra and belongs here rather than in any geometry book: it is used by [42] for the canonical class of a curve, by [13] for the sheaf of differentials, and by [12] for invariant differentials on a group variety.

Definition 21.3.1: A-derivation

Let A be a commutative ring, B an A-algebra, and M a B-module. Then an A-derivation of B into M is a map $d : B \to M$ such that

1. $d(b + b') = d(b) + d(b')$
2. $d(bb') = d(b)b' + bd(b')$
3. $d(a) = 0$ for all $a \in A$

Definition 21.3.2: Module of Relative Differential Forms

Let A be a commutative ring, B an A-algebra. Then a module of relative differential form is a B-module $\Omega_{B/A}$ with an A-derivation $d : B \to \Omega_{B/A}$ which satisfies the universal property of relative differential forms: if M is another B-module and $d' : B \to M$ an A-derivation, then there is a unique B-module homomorphism $f : \Omega_{B/A} \to M$ such that the following diagram commutes:

$$\begin{array}{ccc} B & \xrightarrow{d} & \Omega_{B/A} \\ & \searrow^{d'} & \downarrow f \\ & & M \end{array}$$

Certainly $\Omega_{B/A}$ exists via the usual construction: take the free B-module F generated by the primitives $d(b)$ for $b \in B$ and quotient by the submodule generated by the relationships:

$$d\,(b + b') - d(b) - d\,(b') \qquad \text{and} \qquad d\,(bb') - d(b)b' - bd\,(b') \qquad \text{and} \qquad d(a)$$

Then the map $d : B \to \Omega_{B/A}$ is given by $b \mapsto d(b)$. Then it is an exercise in algebra to see that this satisfies the universal property and $\big(\Omega_{B/A}, d\big)$ is unique up to unique isomorphism. The following gives an alternative insightful construction:

Proposition 21.3.3: Natural Differential Structure

Let B be an A-algebra, $\delta : B \otimes_A B \to B$ the diagonal map given by $f(b \otimes b') = bb'$, and let $I = \ker \delta$. Then I/I^2 has the structure of a left B-module, and we can define a map

$$d : B \to I/I^2 \qquad d(b) = 1 \otimes b - b \otimes 1 \bmod I^2$$

In which case $(I/I^2, d)$ is a module of relative differential for B/A.

***Proof*:**

Write $\delta\colon B \otimes_A B \to B$ for the multiplication map and $I = \ker \delta$. Give I/I^2 the B-module structure coming from the left factor, $b \cdot (x \otimes y) = (bx) \otimes y$. The two possible structures agree modulo I^2, since $b \otimes 1 - 1 \otimes b \in I$.

d is an A-derivation. Additivity is clear. For the Leibniz rule, compute in $B \otimes_A B$:

$$d(bb') - b\,d(b') - b'\,d(b) = \big(1 \otimes bb' - bb' \otimes 1\big) - b\big(1 \otimes b' - b' \otimes 1\big) - b'\big(1 \otimes b - b \otimes 1\big)$$

which expands to $-(1 \otimes b - b \otimes 1)(1 \otimes b' - b' \otimes 1)$, a product of two elements of I and so zero in I/I^2. And $d(a) = 1 \otimes a - a \otimes 1 = 0$ for $a \in A$, the tensor being over A.

Universality. Let $d'\colon B \to M$ be an A-derivation. Define $B \otimes_A B \to M$ by $x \otimes y \mapsto x\,d'(y)$, which is A-bilinear and hence well defined. It kills I^2: for $u = \sum x_i \otimes y_i$ and $v = \sum x'_j \otimes y'_j$ in I, meaning $\sum x_i y_i = 0$ and $\sum x'_j y'_j = 0$, expanding uv and applying the Leibniz rule for d' leaves $\big(\sum x_i y_i\big)\big(\sum x'_j d'(y'_j)\big) = 0$. So it descends to $f\colon I/I^2 \to M$, and $f(d(b)) = f(1 \otimes b - b \otimes 1) = d'(b) - b\,d'(1) = d'(b)$ since $d'(1) = 0$. Uniqueness holds because the $d(b)$ generate I/I^2: any $\sum x_i \otimes y_i \in I$ equals $\sum x_i(1 \otimes y_i - y_i \otimes 1)$ modulo nothing, using $\sum x_i y_i = 0$.

So $(I/I^2, d)$ has the universal property of definition 21.3.2, completing the proof.

Example 21.3.4: Relative Differential

1. Take $A = \mathbb{R}$ and $B = \mathbb{R}[x]$. Then $I = \ker \delta$. Then as $\mathbb{R}[x]$ is an integral domain, it can be shown that any element is a linear combination of elements of the form:

   $$f(x) \otimes g(x) - f(x)g(x) \otimes 1 \in I$$

   Then it should be verified any element in I can be written as:

   $$f(x)(1 \otimes g(x) - g(x) \otimes 1)$$

   The reader should then verify that I/I^2 is generated by $f'(x)(x \otimes 1 - 1 \otimes x)$[a]. Let dx represent this element. Notice that this is the image of $d(x)$. Now, let's consider:

   $$d(f(x) = d\left(\sum_i a_i x^i\right) = \sum_i a_i d(x^i)$$

   Hence, let's compute $d(x^i)$. For $i = 2$, we get:

   $$d(x^2) = d(x \cdot x) = xd(x) - xd(x) = 2xdx$$

   Repeating this pattern, we can see that:

   $$d(x^n) = nx^{n-1}dx$$

2. For example, taking $B = \mathbb{R}[x_1, ..., x_n]$, Then $\Omega_{B/A}$ is a free B-module generated by $dx_1, ..., dx_n$.

3. In proposition 21.3.10, we shall see that if E/F is a finitely generated separable extension (of characteristic 0), then

   $$\Omega_{B/A} = \bigoplus_{b \in T} Bdb$$

   where T is a transcendental A-basis for B.

4. What if we take $B = A[\epsilon]/(\epsilon^2)$?

5. Let $A = \mathbb{R}$ and $B = C^\infty(M)$ for some smooth n-manifold M. Then $C^\infty(M)$. Then $\Omega_{C^\infty(M)/\mathbb{R}}$ is a locally free $C^\infty(M)$-module (based off of the patches of M), consisting of the space of sections of the cotangent bundle T^*M.

[a] Hint: what is $(1 \otimes x^2 - x^2 \otimes 1)$. Repeat for higher powers

Proposition 21.3.5: Base Change For Differentials

Let A', B be A-algebras and $B' = B \otimes_A A'$. Then:

$$\Omega_{B'/A'} \cong \Omega_{B/A} \otimes_B B'$$

Furthermore, if S is a multiplicative subset of of S, then:

$$\Omega_{S^{-1}B/A} \cong S^{-1}\Omega_{B/A}$$

***Proof*:**
Both statements are checked against the universal property of definition 21.3.2.

For the base change, a B'-module M receives an A'-derivation from B' exactly when it receives an A-derivation from B that is A'-linear on the second factor, since $B' = B \otimes_A A'$ is generated over A' by the image of B. So $\mathrm{Der}_{A'}(B', M) \cong \mathrm{Der}_A(B, M)$ naturally, and representing both sides gives $\Omega_{B'/A'} \cong \Omega_{B/A} \otimes_B B'$.

For the localization, an A-derivation $d\colon B \to M$ into an $S^{-1}B$-module extends uniquely to $S^{-1}B$ by the quotient rule $d(b/s) = \big(s\,d(b) - b\,d(s)\big)/s^2$, which is forced by the Leibniz rule applied to $b = (b/s) \cdot s$. So $\mathrm{Der}_A(S^{-1}B, M) \cong \mathrm{Der}_A(B, M)$ for such M, and representing gives $\Omega_{S^{-1}B/A} \cong S^{-1}\Omega_{B/A}$, completing the proof.

Proposition 21.3.6: Differentials and Exact Sequence I

Let $A \to B \to C$ be a (not necessarily exact nor a complex) sequence of rings. Then there is an exact sequence of C-modules:

$$\Omega_{B/A} \otimes_B C \to \Omega_{C/A} \to \Omega_{C/B} \to 0$$

***Proof*:**
The maps are the natural ones: $db \otimes c \mapsto c\,db$ and $dc \mapsto dc$, the latter making sense because an A-derivation of C is in particular one killing the image of A.

Exactness is checked by applying $\mathrm{Hom}_C(-, M)$ for an arbitrary C-module M and using definition 21.3.2, which turns the sequence into

$$0 \to \mathrm{Der}_B(C, M) \to \mathrm{Der}_A(C, M) \to \mathrm{Der}_A(B, M)$$

This is exact: a derivation of C over A kills the image of B exactly when it is a derivation over B, which is exactness at the middle term and injectivity on the left. Since $\mathrm{Hom}_C(-, M)$ is left exact and the resulting sequence is exact for every M, the original sequence is exact at $\Omega_{C/A}$ and at $\Omega_{C/B}$, completing the proof.

Proposition 21.3.7: Differentials and Exact Sequence II

Let B be an A-algebra, I be an ideal of B, and $C = B/I$. Then there is a natural exact sequence of C-modules

$$I/I^2 \xrightarrow{\delta} \Omega_{B/A} \otimes_B C \to \Omega_{C/A} \to 0,$$

where for any $b \in I$, if $\bar{b}$ is its image in I/I^2, then $\delta\bar{b} = db \otimes 1$. In particular, I/I^2 has a natural structure of a C-module, and δ is a C-linear map, even though it is defined via the derivation d.

***Proof*:**
First, δ is well defined and C-linear. For $b, b' \in I$ the Leibniz rule gives $d(bb') = b\,db' + b'\,db$, which lies in $I\,\Omega_{B/A}$ and so vanishes in $\Omega_{B/A} \otimes_B C$. Hence δ kills I^2. C-linearity follows because multiplying b by an element of I again lands in I^2.

For exactness, apply $\mathrm{Hom}_C(-, M)$ as in proposition 21.3.6. The sequence becomes

$$0 \to \mathrm{Der}_A(C, M) \to \mathrm{Der}_A(B, M) \to \mathrm{Hom}_C(I/I^2, M)$$

An A-derivation of B into M, where M is a C-module and so killed by I, descends to $C = B/I$ exactly when it vanishes on I. And its restriction to I is precisely the composite with δ. That is exactness at the middle and injectivity on the left, and as before it holds for every M, giving the stated sequence, completing the proof.

Corollary 21.3.8: Finite Generation of Differential Forms

If B is a finitely generated A-algebra or a localization of a finitely generated A-algebra, then $\Omega_{B/A}$ is a finitely generated B-module

***Proof*:**
As B is a finitely generated A-algebra, it is the quotient of a polynomial ring. Hence, it follows from our direct computations from example 21.3.4 and, proposition 21.3.7, and the localization result comes from proposition 21.3.5.

For finite extensions the module of differentials sees exactly one thing, namely separability, and it sees it sharply: a nonzero derivation exists precisely when some element of the extension fails to be separable. The mechanism is already at work on a simple extension $k(\alpha)$, where a k-derivation is pinned down by its value on α and that value is constrained only through the single scalar $f'(\alpha)$.

Lemma 21.3.9: Derivations Detect Separability

Let F/k be a finite field extension. Then the following are equivalent:

1. F/k is a separable extension
2. $\Omega_{F/k} = 0$
3. the only k-derivation of F into F is the zero map

***Proof*:**

(1 ⇒ 2) Let M be any F-module and $D : F \to M$ a k-derivation. Since F/k is finite and separable, theorem 19.6.20 gives $F = k(\beta)$ for some $\beta \in F$, and β is separable over k by definition 19.6.3. Write $g(x) = m_{\beta,k}(x) = \sum_j c_j x^j$. Additivity and the Leibniz rule give $D(\beta^j) = j\beta^{j-1}D(\beta)$, and D kills each $c_j \in k$, so

$$0 = D\big(g(\beta)\big) = \sum_j c_j D(\beta^j) = g'(\beta)D(\beta)$$

Now β is a root of the separable polynomial g, hence not a multiple root, so $g'(\beta) \neq 0$ by proposition 19.6.6. As $g'(\beta)$ is a unit in the field F, this forces $D(\beta) = 0$. Every element of F is a polynomial in β with coefficients in k by proposition 19.2.24, so additivity and the Leibniz rule propagate $D(\beta) = 0$ to $D = 0$. Thus $\mathrm{Der}_k(F, M) = 0$ for every F-module M.

Apply this to $M = \Omega_{F/k}$: the universal derivation d of definition 21.3.2 is itself zero. Both the identity and the zero map $\Omega_{F/k} \to \Omega_{F/k}$ are F-module homomorphisms f with $f \circ d = d$, so the uniqueness clause of definition 21.3.2 forces them to agree, giving $\Omega_{F/k} = 0$.

(2 ⇒ 3) By definition 21.3.2 the k-derivations of F into F are in bijection with the F-module homomorphisms $\Omega_{F/k} \to F$, and the zero module admits only the zero homomorphism.

(3 ⇒ 1) Take the contrapositive: assume F/k is inseparable and produce a nonzero k-derivation of F into F. Since F/k is finite, write $F = k(\alpha_1, ..., \alpha_n)$ and set $F_0 = k$ and $F_i = F_{i-1}(\alpha_i)$, so that $F_n = F$.

First, some α_i is inseparable over F_{i-1}. If instead every α_i were separable over F_{i-1}, then $[F_i : F_{i-1}]_s = [F_i : F_{i-1}]$ for each i by proposition 19.6.15, and multiplying these together using corollary 19.6.16 on the left and theorem 19.3.7 on the right would give $[F : k]_s = [F : k]$, whence F/k is separable by proposition 19.6.17, contrary to assumption. So let i be the *largest* index for which α_i is inseparable over F_{i-1}, and abbreviate

$$E = F_{i-1} \qquad \alpha = \alpha_i \qquad L = F_i = E(\alpha)$$

By maximality of i, each α_j with $j > i$ is separable over F_{j-1}. Running the same product over the tower $L = F_i \subseteq \cdots \subseteq F_n = F$ gives $[F : L]_s = [F : L]$, so F/L is a finite separable extension, again by proposition 19.6.17.

A nonzero E-derivation of L. Let $f(x) = m_{\alpha,E}(x)$. It is irreducible, and it is inseparable because α is inseparable over E (definition 19.6.3), so proposition 19.6.7 gives $f'(x) = 0$. Reading off the leading term of f', this already forces $\mathrm{ch}(k) = p > 0$ and $f \in E[x^p]$, exactly as in the discussion preceding definition 19.6.9. In characteristic 0 there is nothing to prove, since corollary 19.6.8 rules out inseparable irreducibles outright. Regard L as an $E[x]$-module through the evaluation map $\mathrm{ev}_\alpha : E[x] \to L$ of theorem 19.2.8, whose kernel is (f), and consider

$$\partial : E[x] \to L \qquad \partial(h) = h'(\alpha)$$

with h' the formal derivative of definition 19.6.5. It is additive, it kills E, and the Leibniz rule for the formal derivative gives

$$\begin{aligned}\partial(h_1h_2) = (h_1h_2)'(\alpha) &= h_1'(\alpha)h_2(\alpha) + h_1(\alpha)h_2'(\alpha)\\ &= \partial(h_1)h_2(\alpha) + h_1(\alpha)\partial(h_2)\end{aligned}$$

so ∂ is an E-derivation in the sense of definition 21.3.1. It kills the ideal (f): for any $h \in E[x]$,

$$\partial(fh) = (fh)'(\alpha) = f'(\alpha)h(\alpha) + f(\alpha)h'(\alpha) = 0$$

because $f' = 0$ and $f(\alpha) = 0$. Hence ∂ factors through ev_α as an additive map $D : L \to L$, and the displayed Leibniz identity descends, since both sides depend only on the values $h_1(\alpha), h_2(\alpha)$. So D is an E-derivation of L into L with

$$D(\alpha) = \partial(x) = 1$$

and in particular $D \neq 0$.

Extending D across F/L. Since F/L is finite and separable, theorem 19.6.20 gives $F = L(\beta)$ with β separable over L. Put $g(x) = m_{\beta,L}(x)$. As in $(1 \Rightarrow 2)$, $g'(\beta) \neq 0$ by proposition 19.6.6. For $h(x) = \sum_j c_j x^j \in L[x]$ write $h^D(x) = \sum_j D(c_j)x^j$. Expanding a product coefficientwise and applying the Leibniz rule for D to each term gives

$$(h_1h_2)^D = h_1^D h_2 + h_1 h_2^D$$

Set

$$t = -\frac{g^D(\beta)}{g'(\beta)} \in F$$

and regard F as an $L[x]$-module through evaluation at β. Define

$$\Delta : L[x] \to F \qquad \Delta(h) = h^D(\beta) + h'(\beta)\, t$$

Then Δ is additive, and combining the two product rules just recorded,

$$\begin{aligned}\Delta(h_1h_2) &= h_1^D(\beta)h_2(\beta) + h_1(\beta)h_2^D(\beta) + \big(h_1'(\beta)h_2(\beta) + h_1(\beta)h_2'(\beta)\big)t\\ &= \Delta(h_1)h_2(\beta) + h_1(\beta)\Delta(h_2)\end{aligned}$$

On a constant $c \in L$ we get $\Delta(c) = D(c)$, so Δ vanishes on E and a fortiori on k. By the choice of t,

$$\Delta(g) = g^D(\beta) + g'(\beta)t = 0$$

and therefore $\Delta(gh) = \Delta(g)h(\beta) + g(\beta)\Delta(h) = 0$ for every $h \in L[x]$, since $g(\beta) = 0$. So Δ kills the kernel (g) of evaluation at β and descends, by theorem 19.2.8, to an additive map $\widetilde{D} : F \to F$. As before the Leibniz identity descends with it. Thus $\widetilde{D}$ is a k-derivation of F into F restricting to D on L, and

$$\widetilde{D}(\alpha) = D(\alpha) = 1 \neq 0$$

So F carries a nonzero k-derivation into itself, which is the contrapositive of $(3 \Rightarrow 1)$, completing the proof.

Note that the primitive element theorem is used only where it is legitimate, on the separable extension F/L. It says nothing about F/k itself, which by example 19.6.22 need not be simple once separability fails. The whole content of $(3 \Rightarrow 1)$ is that an inseparable step in a tower is a step at which a derivation may be defined freely, and the remaining steps are separable and so carry the derivation along uniquely.

Proposition 21.3.10: Differentials and Field Extensions

Let K/k be a finitely generated field extension. Then:

$$\dim_K \Omega_{K/k} \geq \mathrm{trdeg} K/k$$

where equality holds iff K is separably generated over k.

***Proof Key ideas*:**
This is the separability criterion for field extensions in differential form, and both implications reduce to the exact sequences above: for a separably generated extension a transcendence basis gives a basis of Ω, and conversely a nonzero differential of a purely inseparable generator is killed by the p-th-power relation. A full account is in [58, chapter II.8].

Both *Classical Algebraic Geometry* [42] and *Algebraic Geometry* [13] use it to detect smoothness.

The finite algebraic case is the one this book uses most often, and it is not left to a citation: lemma 21.3.9 proves that a finite extension K/k has $\Omega_{K/k} = 0$ exactly when it is separable. Note that the transcendence-degree statement above genuinely needs the finitely generated hypothesis, whereas the finite case does not.

Proposition 21.3.11: Local Ring and Relative Differential

Let B be a local ring containing a field k isomorphic to $B/\mathfrak{m}$. Then given the map δ from proposition 21.3.7:

$$\delta : \mathfrak{m}/\mathfrak{m}^2 \xrightarrow{\cong} \Omega_{B/k} \otimes_B k$$

***Proof*:**
By proposition 21.3.7 $\mathrm{coker}(\delta) = 0$, so δ is surjective. To show that δ is injective, we shall show the following dual vector space map is surjective:

$$\delta' : \mathrm{Hom}_k(\Omega_{B/k} \otimes k, k) \to \mathrm{Hom}_k(\mathfrak{m}/\mathfrak{m}^2, k)$$

The term on the left is isomorphic to $\mathrm{Hom}_B(\Omega_{B/k}, k)$, which by definition of the differentials, can be identified with the set $\mathrm{Der}_k(B, k)$ of k-derivations of B to k. If $d : B \to k$ is a derivation, then $\delta'(d)$ is obtained by restricting to $\mathfrak{m}$, and noting that $d(\mathfrak{m}^2) = 0$. Now, to show that δ' is surjective, let $h \in \mathrm{Hom}(\mathfrak{m}/\mathfrak{m}^2, k)$. For any $b \in B$, we can write $b = \lambda + c$, $\lambda \in k$, $c \in \mathfrak{m}$, in a unique way. Define $db = h(\bar{c})$, where $\bar{c} \in \mathfrak{m}/\mathfrak{m}^2$ is the image of c. Then one verifies immediately that d is a k-derivation of B to k, and that $\delta'(d) = h$. Thus δ' is surjective, as required.

We finish off this brief summary of the essential results about relative differentials by showing the relation between regular local rings and relative differentials. We require the following lemma:

Lemma 21.3.12: Characterizing Free Modules using Residue and Quotient Field

Let A be a Noetherian local integral domain, with residue field k and quotient field K. Then if M is a finitely generated A-module and $\dim_k M \otimes_A k = \dim_k M \otimes_A K = r$, then M is free of rank r.

***Proof*:**
Since $\dim_k M \otimes k = r$, by Nakayama's lemma M can be generated by r elements. Hence, there is a surjective map $\varphi : A^r \to M$. Let R be its kernel. Then we obtain an exact sequence

$$0 \to R \otimes K \to K^r \to M \otimes K \to 0,$$

As $\dim_K M \otimes K = r$, we have $R \otimes K = 0$. But R is torsion-free, so $R = 0$, and M is isomorphic to A^r, completing the proof.

22⋆

Bilinear, Quadratic and Alternating Forms over a Field

⋆ *Optional. This chapter is an aside; nothing later in the book depends on it.*

A bilinear form is a piece of data attached to a vector space, and section 13.3 said what that data is: a matrix, once a basis is fixed. It did not say when two such data are the same. Two forms should count as the same when some change of basis carries one to the other, and the matrix statement of that relation is $A \mapsto P^t AP$ rather than the $A \mapsto P^{-1}AP$ that governs linear operators. The two relations are genuinely different, and the invariants of the first are not the eigenvalues.

This chapter classifies bilinear forms over a field up to that relation, in the two cases that occur: the symmetric forms, where the answer is subtle and field-dependent, and the alternating ones, where it is not. The answer is controlled by a single group built from the field, the square classes $k^\times/(k^\times)^2$, and this is why the subject sits after Galois theory: for a field of characteristic other than 2 that group is exactly what Kummer theory at $n = 2$ (section 20.4) classifies. Over $\mathbb{C}$ the group is trivial and the classification collapses to the rank; over $\mathbb{R}$ it has two elements and one further invariant appears; over a general field it can be arbitrarily complicated, and the bookkeeping of what survives is the Witt group.

22.1 Quadratic Forms and Symmetric Bilinear Forms

The forms of interest are the symmetric ones, and over a field where 2 is invertible a symmetric bilinear form carries exactly the same information as the single-variable function $x \mapsto \varphi(x, x)$. That function is easier to write down and is what one meets in practice, so the correspondence between the two is recorded first. It fails in characteristic 2, and the failure is not a technicality to be waved past: it is why the whole theory below carries the hypothesis $\operatorname{char} k \neq 2$.

Definition 22.1.1: Quadratic Form over a Field

Let k be a field and V a finite-dimensional k-vector space. A *quadratic form* on V is a function $q\colon V \to k$ such that

1. $q(\lambda v) = \lambda^2 q(v)$ for all $\lambda \in k$ and $v \in V$;
2. the function $b_q\colon V \times V \to k$ defined by

$$b_q(x,y) := q(x+y) - q(x) - q(y)$$

is bilinear.

The form b_q is the *polar form* of q. It is symmetric, since the defining expression is unchanged by exchanging x and y.

Two consequences of the definition are used constantly and are worth extracting at once. Setting $y = x$ in the polar form and applying (1) gives

$$b_q(x,x) = q(2x) - 2q(x) = 4q(x) - 2q(x) = 2q(x)$$

so the polar form recovers q after division by 2, and only then. And if φ is any symmetric bilinear form, the function $q_\varphi(x) := \varphi(x,x)$ satisfies both conditions above, with $b_{q_\varphi} = 2\varphi$ by the same computation. The two constructions are therefore mutually inverse exactly when 2 is invertible.

Proposition 22.1.2: Quadratic Forms and Symmetric Bilinear Forms Correspond

Let k be a field with $\operatorname{char} k \neq 2$ and let V be a finite-dimensional k-vector space. The assignments

$$\varphi \longmapsto q_\varphi, \qquad q \longmapsto \tfrac{1}{2} b_q$$

are mutually inverse bijections between the set of symmetric bilinear forms on V and the set of quadratic forms on V.

***Proof*:**

Step 1: the assignments are well defined. Let φ be symmetric bilinear and put $q_\varphi(x) = \varphi(x,x)$. Then $q_\varphi(\lambda v) = \varphi(\lambda v, \lambda v) = \lambda^2 \varphi(v,v) = \lambda^2 q_\varphi(v)$, which is condition (1). For condition (2), expanding by bilinearity and using symmetry,

$$b_{q_\varphi}(x,y) = \varphi(x+y, x+y) - \varphi(x,x) - \varphi(y,y) = 2\varphi(x,y)$$

which is bilinear. So q_φ is a quadratic form and $b_{q_\varphi} = 2\varphi$. Conversely, if q is a quadratic form then b_q is symmetric bilinear by definition 22.1.1, hence so is $\frac{1}{2} b_q$, using $\operatorname{char} k \neq 2$ to divide.

Step 2: the composites are the identity. Starting from a symmetric φ, Step 1 gives $\frac{1}{2} b_{q_\varphi} = \frac{1}{2} \cdot 2\varphi = \varphi$. Starting from a quadratic form q and writing $\varphi = \frac{1}{2} b_q$, the computation recorded before the proposition gives $b_q(x,x) = 2q(x)$, so

$$q_\varphi(x) = \varphi(x,x) = \tfrac{1}{2} b_q(x,x) = \tfrac{1}{2} \cdot 2q(x) = q(x)$$

Both composites are the identity, so the assignments are mutually inverse bijections, as we sought to show.

Because of the proposition, the words *quadratic form* and *symmetric bilinear form* are used interchangeably below whenever $\operatorname{char} k \neq 2$, and disc, orthogonality and the matrix of a form are attached to either at will. The next example shows what is lost when the hypothesis is dropped, and it is the reason the hypothesis is carried explicitly rather than assumed silently.

Example 22.1.3: Polarization Fails in Characteristic Two

Let $k = \mathbb{F}_2$ and $V = k^2$ with coordinates (x, y).

The map $q \mapsto b_q$ is not injective. Take $q(x, y) = x^2$. Then $q(\lambda v) = \lambda^2 q(v)$ holds, and

$$b_q\big((x,y),(x',y')\big) = (x+x')^2 - x^2 - x'^2 = 2xx' = 0$$

since $2 = 0$ in k. So q and the zero form have the same polar form, yet $q(1,0) = 1 \neq 0$. More generally $b_q(v,v) = 2q(v) = 0$ for every quadratic form in characteristic 2, so every polar form is alternating and the diagonal information in q is invisible to b_q. Throughout this example *alternating* means the vanishing condition of definition 16.1.3, that $\varphi(v,v) = 0$ for every v. In characteristic 2 that is strictly stronger than the sign rule appearing in definition 13.3.15, since there $-1 = 1$ makes the sign rule say nothing beyond symmetry.

The map $q \mapsto b_q$ is not surjective either. The form $\varphi\big((x,y),(x',y')\big) = xx'$ is symmetric bilinear, but $\varphi\big((1,0),(1,0)\big) = 1 \neq 0$, so φ does not vanish on the diagonal and is therefore not the polar form of anything.

Orthogonal bases can fail to exist. Let $\psi\big((x,y),(x',y')\big) = xy' + x'y$, with matrix $\left(\begin{smallmatrix} 0 & 1 \\ 1 & 0 \end{smallmatrix}\right)$ in the standard basis. It is symmetric, nondegenerate, and nonzero, since $\psi(e_1, e_2) = 1$. But $\psi(v,v) = 2xy = 0$ for every v. Were w_1, w_2 an orthogonal basis, the matrix of ψ in it would be $\operatorname{diag}\big(\psi(w_1,w_1), \psi(w_2,w_2)\big) = \operatorname{diag}(0,0)$, forcing $\psi = 0$ and contradicting $\psi(e_1,e_2) = 1$. So ψ admits no orthogonal basis at all. Contrast $\varphi(u,v) = xx'$ above, which is already diagonal in the standard basis: failing to be a polar form and failing to be diagonalizable are different failures, and ψ exhibits the second.

All three failures trace to the division by 2 in proposition 22.1.2. In characteristic 2 the quadratic and the bilinear theories separate, and the correct objects are quadratic forms together with their alternating polar forms, and that theory is not developed here.

The classification question can now be posed precisely. Fixing a basis turns a form into a matrix (definition 13.3.18), and changing the basis changes the matrix in a way that must be pinned down before any invariant can be extracted.

Theorem 22.1.4: Change of Basis for the Matrix of a Form

Let V be a finite-dimensional k-vector space with bases $\beta = (\beta_1, \dots, \beta_n)$ and $\beta' = (\beta'_1, \dots, \beta'_n)$, and let $\varphi\colon V \times V \to k$ be a bilinear form. Let P be the $n \times n$ matrix whose j-th column is $[\beta'_j]_\beta$, the coordinate vector of β'_j in the basis β (this is the change of basis matrix of definition 13.2.11). Then P is invertible, $[v]_\beta = P[v]_{\beta'}$ for every $v \in V$, and

$$[\varphi]_{\beta'} = P^t\,[\varphi]_\beta\,P$$

***Proof*:**
The columns of P are the coordinate vectors of a basis, hence linearly independent, so P is invertible. Writing $v = \sum_j c_j \beta'_j$, that is $[v]_{\beta'} = (c_j)_j$, linearity of the coordinate map gives

$$[v]_\beta = \Big[\sum_j c_j \beta'_j\Big]_\beta = \sum_j c_j [\beta'_j]_\beta = P[v]_{\beta'}$$

which is the second claim. For the third, write $A = [\varphi]_\beta$. By lemma 13.3.19, for all $v, w \in V$

$$\varphi(v,w) = [v]_\beta^t A [w]_\beta = \big(P[v]_{\beta'}\big)^t A \big(P[w]_{\beta'}\big) = [v]_{\beta'}^t \big(P^t A P\big)[w]_{\beta'}$$

Taking $v = \beta'_i$ and $w = \beta'_j$ makes the coordinate vectors the standard basis vectors e_i and e_j, so the displayed expression is the (i,j) entry of $P^t A P$. On the other hand that value is $\varphi(\beta'_i, \beta'_j)$, which is the (i,j) entry of $[\varphi]_{\beta'}$ by definition 13.3.18. The two matrices agree entrywise, completing the proof.

Definition 22.1.5: Congruent Matrices

Two matrices $A, B \in M_n(k)$ are *congruent* if $B = P^t A P$ for some invertible $P \in M_n(k)$. Congruence is an equivalence relation: it is reflexive by $P = I$, symmetric because $A = (P^{-1})^t B P^{-1}$, and transitive because $(PQ)^t A (PQ) = Q^t (P^t A P) Q$.

Theorem 22.1.4 says that the matrices of one form in the various bases of V form exactly one congruence class, so a property of matrices is a property of the form precisely when it is congruence-invariant. Similarity, the relation $A \mapsto P^{-1} A P$ appropriate to linear operators, is a different relation, and the invariants of a form are not those of an operator: the determinant, for instance, is not congruence-invariant, but the next definition extracts from it something that is.

Definition 22.1.6: The Square Classes of a Field

Let k be a field. The squares $(k^\times)^2 = \{c^2 \mid c \in k^\times\}$ form a subgroup of the abelian group $k^\times$, and the quotient

$$k^\times / (k^\times)^2$$

is the group of *square classes* of k. Every element has order dividing 2, so it is a vector space over $\mathbb{F}_2$. The class of $a \in k^\times$ is written $a\,(k^\times)^2$, and two elements lie in the same class exactly when their ratio is a square.

The square classes are where the classification lives, and their size measures how far the field is from having all square roots. For $k = \mathbb{C}$, or any algebraically closed field, every element is a square and the group is trivial. For $k = \mathbb{R}$ it has order 2, the classes being the positive and the negative reals. For $k = \mathbb{Q}$ it is infinite. The relevance to forms is immediate from theorem 22.1.4.

Definition 22.1.7: Discriminant of a Nondegenerate Form

Let φ be a nondegenerate symmetric bilinear form (definition 13.3.22) on a finite-dimensional k-vector space V, and let β be any basis. The *discriminant* of φ is the square class

$$\operatorname{disc}(\varphi) := \det\big([\varphi]_\beta\big)\,(k^\times)^2 \in k^\times/(k^\times)^2$$

Proposition 22.1.8: The Discriminant Is Well Defined and Is an Invariant

The class $\operatorname{disc}(\varphi)$ of definition 22.1.7 does not depend on the basis β, and congruent forms have equal discriminants.

***Proof*:**
Nondegeneracy makes $\det([\varphi]_\beta) \neq 0$ by lemma 13.3.23, so the class is taken in $k^\times$ and the definition makes sense. If β' is a second basis then $[\varphi]_{\beta'} = P^t[\varphi]_\beta P$ by theorem 22.1.4, and the multiplicativity of the determinant together with $\det(P^t) = \det(P)$ gives

$$\det\big([\varphi]_{\beta'}\big) = (\det P)^2 \det\big([\varphi]_\beta\big)$$

The two determinants differ by the square $(\det P)^2$ of the nonzero scalar $\det P$, hence lie in the same square class. The same computation, read as a statement about congruent matrices rather than about two bases, gives the second claim, as we sought to show.

22.1.9 Convention: the discriminant is unsigned, and the Witt group will twist it
Definition 22.1.7 takes the determinant with no sign attached. That is the right convention here and the wrong one for the Witt group, and the two sections genuinely differ, so the choice is recorded rather than left implicit.
At a fixed rank n the factor $(-1)^{n(n-1)/2}$ is a constant and carries no information, while multiplicativity over orthogonal sums, $\operatorname{disc}(\varphi \perp \psi) = \operatorname{disc}(\varphi)\operatorname{disc}(\psi)$, holds exactly as stated and is what the classification over a finite field uses.
The Witt group of section 22.6 identifies φ with $\varphi \perp \langle 1, -1\rangle$, and the unsigned discriminant does not survive that identification: adding $\langle 1, -1\rangle$ multiplies the determinant by -1. The *signed* discriminant $(-1)^{n(n-1)/2}\det$ does survive, since the rank rises by two and the sign changes to compensate. The price is that it is multiplicative only up to $(-1)^{mn}$. Each section therefore takes the convention its own problem needs, and section 22.6 states the twist when it introduces it.

The discriminant is the first invariant of the subject that is invisible over $\mathbb{R}$ and $\mathbb{C}$: there the square class group has at most two elements, so the discriminant carries at most one bit, whereas over a general field it is as large as $k^\times/(k^\times)^2$. The notion of sameness it is invariant under deserves its own name.

Definition 22.1.10: Isometry and the Orthogonal Group

Let (V, φ) and (V', φ') be finite-dimensional k-vector spaces equipped with symmetric bilinear forms. An *isometry* $f\colon (V, \varphi) \to (V', \varphi')$ is a linear isomorphism $f\colon V \to V'$ with

$$\varphi'\big(f(x), f(y)\big) = \varphi(x, y) \qquad \text{for all } x, y \in V$$

The two forms are *isometric*, written $\varphi \cong \varphi'$, if such an f exists. The isometries of (V, φ) to itself form a group under composition, the *orthogonal group* $O(\varphi)$ of the form.

Choosing bases turns an isometry into a congruence: if f is an isometry and β is a basis of V, then the matrix of φ' in the basis $f(\beta)$ is $[\varphi]_\beta$, so two forms on spaces of the same dimension are isometric exactly when their matrices are congruent. The classification of forms up to isometry and the classification of symmetric matrices up to congruence are therefore one problem in two languages. The chapter's opening example is a form the reader has already met.

Example 22.1.11: The Trace Form as a Quadratic Form

Let F/k be a finite separable extension with $\operatorname{char} k \neq 2$. The trace form $\langle x, y\rangle = \operatorname{tr}_{F/k}(xy)$ of definition 19.6.30 is a symmetric k-bilinear form on F, viewed as a k-vector space, and it is nondegenerate by proposition 19.6.31. Its associated quadratic form under proposition 22.1.2 is

$$q(x) = \operatorname{tr}_{F/k}(x^2)$$

so F carries a canonical quadratic form built from nothing but its field structure, and definition 22.1.7 attaches to it a square class in $k^\times/(k^\times)^2$.

Take $k = \mathbb{Q}$ and $F = \mathbb{Q}(\sqrt{d})$ with d a squarefree integer, $d \neq 1$. In the basis $\beta = (1, \sqrt{d})$ one computes $\operatorname{tr}(1) = 2$, since multiplication by 1 is the identity of a two-dimensional space. Next $\operatorname{tr}(\sqrt{d}) = 0$, since multiplication by $\sqrt{d}$ sends $1 \mapsto \sqrt{d}$ and $\sqrt{d} \mapsto d$, so its matrix in that basis has both diagonal entries zero. Finally $\operatorname{tr}(d) = 2d$. Hence

$$[\langle\,,\rangle]_\beta = \begin{pmatrix} 2 & 0 \\ 0 & 2d \end{pmatrix}, \qquad \det = 4d$$

and since 4 is a square,

$$\operatorname{disc} = 4d\,(\mathbb{Q}^\times)^2 = d\,(\mathbb{Q}^\times)^2$$

The discriminant of the trace form recovers the square class of d, which is precisely the datum distinguishing the fields $\mathbb{Q}(\sqrt{d})$ from one another. The invariant is doing real work already: over $\mathbb{Q}$ the square class group is infinite, so this single class separates infinitely many non-isometric forms, where over $\mathbb{R}$ or $\mathbb{C}$ it could not have separated more than two.

Exercise 22.1.1

1. Let q be a quadratic form with polar form b_q. Prove the parallelogram identity $q(x+y)+q(x-y) = 2q(x) + 2q(y)$ directly from definition 22.1.1, using no hypothesis on the characteristic. Then explain why the identity carries no information when $\operatorname{char} k = 2$, and say what that has to do with example 22.1.3.

2. Exhibit two matrices in $M_2(\mathbb{Q})$ that are congruent but not similar. Then show that when the

change of basis matrix P of theorem 22.1.4 satisfies $P^t = P^{-1}$ the two relations produce the same matrix, so congruence and similarity can differ only through changes of basis that are not of this kind.

3. Let φ and ψ be nondegenerate symmetric bilinear forms on V and W, and let $\varphi \perp \psi$ denote the form on $V \oplus W$ given by $(\varphi \perp \psi)\big((v,w),(v',w')\big) = \varphi(v,v') + \psi(w,w')$. Show that $\varphi \perp \psi$ is nondegenerate and that $\operatorname{disc}(\varphi \perp \psi) = \operatorname{disc}(\varphi)\operatorname{disc}(\psi)$.

4. Let $F = \mathbb{F}_{q^2}$ and $k = \mathbb{F}_q$ with q odd. Compute the trace form of F/k in a basis of your choosing and determine its discriminant as an element of $k^\times/(k^\times)^2$. Is it the trivial class?

5. Let φ be a symmetric bilinear form on V with radical $R = \operatorname{rad}(\varphi)$ (definition 13.3.22). Show that φ descends to a well-defined form $\bar{\varphi}$ on V/R, that $\bar{\varphi}$ is nondegenerate, and that $\operatorname{disc}(\bar{\varphi})$ is therefore defined even though $\operatorname{disc}(\varphi)$ is not.

22.2 Diagonalization and Orthogonal Bases

A symmetric matrix is congruent to a diagonal one, and the diagonal entries are visible invariants only up to squares. Both halves of that sentence are proved here, and together they reduce the classification problem to a question about the square class group of the field.

Theorem 22.2.1: Every Symmetric Form Has an Orthogonal Basis

Let k be a field with $\operatorname{char} k \neq 2$, let V be a k-vector space of finite dimension n, and let φ be a symmetric bilinear form on V. Then V has a basis $w_1, \dots, w_n$ with $\varphi(w_i, w_j) = 0$ whenever $i \neq j$. Equivalently, every symmetric matrix over k is congruent to a diagonal matrix.

***Proof*:**
Induct on n. For $n = 0$ there is nothing to prove, and for $n = 1$ any basis is orthogonal because the condition $i \neq j$ is vacuous.

Step 1: either φ vanishes identically or some vector is non-isotropic. Suppose $\varphi(v,v) = 0$ for every $v \in V$. Then for all $x, y \in V$,

$$0 = \varphi(x+y, x+y) = \varphi(x,x) + 2\varphi(x,y) + \varphi(y,y) = 2\varphi(x,y)$$

and since $\operatorname{char} k \neq 2$ this forces $\varphi(x,y) = 0$, so φ is the zero form and every basis is orthogonal. This is the only place the characteristic hypothesis is used, and it cannot be dropped: the form ψ of example 22.1.3 is a nonzero symmetric form over $\mathbb{F}_2$ with $\psi(v,v) = 0$ for every v, so it falsifies the implication just proved, and that example shows it admits no orthogonal basis at all.

Otherwise choose $w_1 \in V$ with $a_1 := \varphi(w_1, w_1) \neq 0$.

Step 2: split off w_1. Let $W = \{w_1\}^\perp$, a subspace by lemma 13.3.21. Every $x \in V$ decomposes as

$$x = \frac{\varphi(w_1, x)}{a_1}\, w_1 + \left(x - \frac{\varphi(w_1, x)}{a_1}\, w_1 \right)$$

and the bracketed vector lies in W, since applying $\varphi(w_1, -)$ to it gives $\varphi(w_1, x) - \frac{\varphi(w_1,x)}{a_1} a_1 = 0$. So $V = kw_1 + W$. The sum is direct: if $\lambda w_1 \in W$ then $0 = \varphi(w_1, \lambda w_1) = \lambda a_1$, and $a_1 \neq 0$ forces $\lambda = 0$. Hence $V = kw_1 \oplus W$ and $\dim W = n - 1$.

Step 3: induct. The restriction $\varphi|_{W \times W}$ is a symmetric bilinear form on W, so by the inductive hypothesis W has an orthogonal basis $w_2, \ldots, w_n$. Then $w_1, w_2, \ldots, w_n$ is a basis of V by Step 2, and it is orthogonal: $\varphi(w_i, w_j) = 0$ for $2 \leq i \neq j \leq n$ by the choice of the w_i, and $\varphi(w_1, w_j) = 0$ for $j \geq 2$ because $w_j \in W = \{w_1\}^{\perp}$.

For the matrix formulation, a symmetric $A \in M_n(k)$ is the matrix of a symmetric form on k^n in the standard basis, and an orthogonal basis for that form has diagonal matrix, and by theorem 22.1.4 the two matrices are congruent, completing the proof.

In an orthogonal basis the form is determined by the n scalars $a_i = \varphi(w_i, w_i)$, and the standard notation records exactly that: write

$$\varphi \cong \langle a_1, a_2, \ldots, a_n \rangle$$

for a form admitting an orthogonal basis with those diagonal entries, so that the associated quadratic form is $q(x) = a_1 x_1^2 + \cdots + a_n x_n^2$ in the corresponding coordinates. The notation is an assertion about an isometry class, not about a chosen basis, and the next proposition says how far the entries themselves are from being invariants.

Proposition 22.2.2: Rescaling the Entries of a Diagonalization

Let $\operatorname{char} k \neq 2$. For any $c_1, \ldots, c_n \in k^{\times}$,

$$\langle a_1, \ldots, a_n \rangle \cong \langle a_1 c_1^2, \ldots, a_n c_n^2 \rangle$$

so each diagonal entry is well defined only up to multiplication by a nonzero square. A diagonal entry that is zero stays zero, and the number of zero entries is the dimension of the radical, hence is an invariant.

***Proof*:**

Let $w_1, \ldots, w_n$ be an orthogonal basis realizing $\langle a_1, \ldots, a_n \rangle$ and put $w_i' = c_i w_i$. Each c_i is nonzero, so $w_1', \ldots, w_n'$ is again a basis, and it is orthogonal because $\varphi(w_i', w_j') = c_i c_j \varphi(w_i, w_j) = 0$ for $i \neq j$. Its diagonal entries are $\varphi(w_i', w_i') = c_i^2 a_i$, which gives the displayed isometry. Since $c_i^2 \neq 0$, the entry $c_i^2 a_i$ vanishes exactly when a_i does.

For the last claim, in an orthogonal basis a vector $x = \sum_i x_i w_i$ lies in $\operatorname{rad}(\varphi)$ if and only if $\varphi(w_j, x) = a_j x_j = 0$ for every j, that is if and only if $x_j = 0$ for every j with $a_j \neq 0$. So the radical is spanned by those w_j with $a_j = 0$, and its dimension is the number of zero entries, which is independent of the diagonalization because the radical is, completing the proof.

Corollary 22.2.3: The Discriminant from a Diagonalization

Let $\varphi \cong \langle a_1, \ldots, a_n \rangle$ be nondegenerate, so every $a_i \neq 0$. Then

$$\operatorname{disc}(\varphi) = a_1 a_2 \cdots a_n \, (k^{\times})^2$$

***Proof*:**
In an orthogonal basis the matrix of φ is $\operatorname{diag}(a_1, \dots, a_n)$, whose determinant is $a_1 \cdots a_n$. Apply definition 22.1.7, whose independence of the basis is proposition 22.1.8. Consistently with proposition 22.2.2, replacing each a_i by $a_i c_i^2$ multiplies the product by $(c_1 \cdots c_n)^2$ and so does not change the class, as we sought to show.

Two fields where the square class group is completely known illustrate how much of the classification the discriminant sees. The first is the degenerate case, in the sense that the group is trivial and nothing beyond the rank survives.

Example 22.2.4: Forms over an Algebraically Closed Field
Let k be algebraically closed with $\operatorname{char} k \neq 2$. Every $a \in k^\times$ has a square root, so $(k^\times)^2 = k^\times$ and the square class group of definition 22.1.6 is trivial. Given any symmetric form, diagonalize it by theorem 22.2.1 as $\langle a_1, \dots, a_r, 0, \dots, 0\rangle$ with the $a_i \neq 0$, and apply proposition 22.2.2 with $c_i = a_i^{-1/2}$ to obtain

$$\varphi \cong \langle \underbrace{1, \dots, 1}_{r}, \underbrace{0, \dots, 0}_{n-r} \rangle$$

So a form over an algebraically closed field is determined up to isometry by n and r, and r is the rank of any matrix of φ. The discriminant of a nondegenerate such form is the class of 1 and carries no information, as it must, the group having one element.

Example 22.2.5: Forms over a Finite Field
Let $k = \mathbb{F}_q$ with q odd. The group $\mathbb{F}_q^\times$ is cyclic by theorem 11.3.14, of even order $q - 1$, so the squaring map has kernel $\{\pm 1\}$ of order 2 and image of index 2. Hence

$$\mathbb{F}_q^\times / (\mathbb{F}_q^\times)^2 \cong \mathbb{Z}/2\mathbb{Z}$$

with the two classes the nonzero squares and the non-squares. Unlike the algebraically closed case, the discriminant now carries a genuine bit, and it obstructs isometries that the rank alone would permit.

Take $q = 5$, where the squares in $\mathbb{F}_5^\times = \{1, 2, 3, 4\}$ are $1 = 1^2$ and $4 = 2^2$, so the non-squares are 2 and 3. The forms $\langle 1, 1\rangle$ and $\langle 1, 2\rangle$ on $\mathbb{F}_5^2$ are both nondegenerate of rank 2, but by corollary 22.2.3 their discriminants are the classes of 1 and of 2 respectively, which are distinct in $\mathbb{F}_5^\times / (\mathbb{F}_5^\times)^2$. By proposition 22.1.8 an isometry would force those classes to agree, so

$$\langle 1, 1\rangle \ncong \langle 1, 2\rangle$$

Rank does not classify forms over $\mathbb{F}_5$. Whether rank together with the discriminant does classify them is a genuine question, and it is answered affirmatively in section 22.6 once enough is known about which values a form represents.

Exercise 22.2.1

1. Exhibit two different orthogonal bases for the same form on $\mathbb{Q}^2$ whose diagonal entries are not related by the rescaling of proposition 22.2.2 entry by entry, and reconcile this with that proposition.

2. Let $k = \mathbb{R}$. Determine the square class group, and show that every nondegenerate form is isometric to $\langle 1, \dots, 1, -1, \dots, -1\rangle$. Explain why the discriminant alone does not classify these, and identify the invariant that does. (This book does not prove that the counts are well defined. That is Sylvester's law of inertia, and it needs an order on the scalars.)

3. Over $k = \mathbb{Q}$, show that $\langle 1, 1\rangle$ and $\langle -1, -1\rangle$ have the same rank and the same discriminant and are nevertheless not isometric, by asking which nonzero rationals each represents. Conclude that rank and discriminant together do not classify forms over $\mathbb{Q}$, in contrast with example 22.2.4. Show also that $\langle 1, 1\rangle \cong \langle 2, 2\rangle$ over $\mathbb{Q}$, so a difference of diagonal entries is not by itself evidence of non-isometry.

4. Let $\varphi \cong \langle a_1, \dots, a_n\rangle$ be nondegenerate over k and let $c \in k^\times$ be a value represented by φ, meaning $c = q(v)$ for some $v \in V$. Show that $\varphi \cong \langle c, b_2, \dots, b_n\rangle$ for some b_i, and deduce that the set of represented values is a union of square classes.

22.3 Alternating Forms, the Linear Darboux Theorem, and Lagrangians

Section 22.1 and section 22.2 treated the symmetric forms, where the classification runs through the square classes of k and is not settled by the rank alone. The alternating forms are the second class of bilinear forms for which a classification is available, and there the answer does not depend on the field: a single integer, the codimension of the radical, determines the form up to isometry, and neither the statement nor its proof carries a hypothesis on the characteristic.

The classification is proved in the shape of a basis in which the matrix of the form is one fixed block matrix. That basis then makes visible the subspaces on which an alternating form vanishes identically. When the form is nondegenerate such a subspace has dimension at most half that of the ambient space, and the ones attaining the bound are the Lagrangian subspaces.

Definition 22.3.1: Alternating Bilinear Form

Let k be a field, with no hypothesis on its characteristic, and let V be a finite-dimensional k-vector space. A bilinear form $\varphi\colon V \times V \to k$ (definition 13.3.15) is *alternating* if

$$\varphi(v, v) = 0 \qquad \text{for every } v \in V$$

This is the vanishing condition of definition 16.1.3 read for a 2-multilinear map, and not the sign rule listed in definition 13.3.15. The two conditions differ in characteristic 2, and throughout this section *alternating* means the displayed vanishing condition.

Two alternating forms (V, φ) and (V', φ') are *isometric* if there is a linear isomorphism $f\colon V \to V'$ with $\varphi'\big(f(x), f(y)\big) = \varphi(x, y)$ for all $x, y \in V$. This is the condition of definition 22.1.10 with the hypothesis that the two forms be symmetric dropped, and it is used in that generality below.

One expansion carries the whole section. For $x, y \in V$ the vanishing condition applied to $x + y$ gives

$$0 = \varphi(x + y, x + y) = \varphi(x, x) + \varphi(x, y) + \varphi(y, x) + \varphi(y, y) = \varphi(x, y) + \varphi(y, x)$$

so every alternating form satisfies

$$\varphi(y,x) = -\varphi(x,y) \qquad \text{for all } x, y \in V \tag{22.1}$$

which is lemma 16.1.4(1) for the transposition in S_2, its hypotheses holding here because a field is a commutative ring and both V and k are k-modules. The converse needs 2 to be invertible, and that is lemma 16.1.4(2): over a field with $\operatorname{char} k \neq 2$ a bilinear form satisfying (22.1) is alternating, since setting $y = x$ there gives $2\varphi(x,x) = 0$. Over such a field, therefore, *alternating* and *skew-symmetric* name the same forms, and a form that is both symmetric and alternating is zero: symmetry and (22.1) together give $\varphi(x,y) = -\varphi(x,y)$, hence $2\varphi(x,y) = 0$, hence $\varphi(x,y) = 0$. The classification below and the one in section 22.2 therefore overlap only in the zero form. In characteristic 2 neither statement survives, and $-1 = 1$ makes (22.1) say only that φ is symmetric.

The condition is visible in the matrix of the form. Fix a basis $\beta = (\beta_1, \ldots, \beta_n)$ of V and let $A = (a_{ij}) = [\varphi]_\beta$ be the matrix of definition 13.3.18. If φ is alternating then $a_{ii} = \varphi(\beta_i, \beta_i) = 0$ and, by (22.1), $a_{ji} = -a_{ij}$. Conversely, suppose A has zero diagonal and satisfies $A^t = -A$. For $v = \sum_i x_i \beta_i$, lemma 13.3.19 gives

$$\varphi(v,v) = \sum_{i,j} x_i x_j a_{ij} = \sum_i x_i^2 a_{ii} + \sum_{i<j} x_i x_j \big(a_{ij} + a_{ji}\big) = 0$$

so φ is alternating. Both conditions on A are needed: in characteristic 2 the matrix $\left(\begin{smallmatrix} 1 & 0 \\ 0 & 0 \end{smallmatrix}\right)$ satisfies $A^t = -A$ and has a nonzero diagonal entry.

Example 22.3.2: The Determinant Form, and the Overlap in Characteristic Two

1. Let $V = k^2$ and
$$\varphi(x,y) = x_1 y_2 - x_2 y_1$$
which is the determinant of the matrix with columns x and y. It is bilinear in each column and $\varphi(x,x) = x_1 x_2 - x_2 x_1 = 0$, so it is alternating. Its matrix in the standard basis is $\left(\begin{smallmatrix} 0 & 1 \\ -1 & 0 \end{smallmatrix}\right)$, of determinant 1, so φ is nondegenerate by lemma 13.3.23.

2. Over $k = \mathbb{F}_2$ the form in (1) reads $\varphi(x,y) = x_1 y_2 + x_2 y_1$, which is exactly the form ψ of example 22.1.3. That form is symmetric, nonzero and alternating at once, which is possible only because $\operatorname{char} k = 2$. The example also shows it admits no orthogonal basis, so the conclusion of theorem 22.2.1 genuinely fails for it.

3. Still over $\mathbb{F}_2$, the form $\varphi(x,y) = x_1 y_1$ is symmetric, hence satisfies (22.1) because $-1 = 1$, but $\varphi(e_1, e_1) = 1 \neq 0$. So the sign rule does not imply the vanishing condition when 2 is not invertible, and the hypothesis in lemma 16.1.4(2) cannot be dropped.

The proof of theorem 22.2.1 split off one dimension at a time, and the entry it left behind was pinned down only up to a square (proposition 22.2.2). For an alternating form there is no such entry to leave behind, since $\varphi(v,v) = 0$ for every v, and the smallest piece that carries any information is two-dimensional. On such a piece the one scalar available can be scaled to 1 outright, which is why no square classes enter the answer. The resulting normal form deserves a name before it is proved to exist.

Definition 22.3.3: Symplectic Basis and Symplectic Space

Let k be a field, with no hypothesis on its characteristic, let V be a finite-dimensional k-vector space, and let φ be an alternating bilinear form on V (definition 22.3.1). A *symplectic basis* for φ is a basis

$$e_1, f_1, e_2, f_2, \dots, e_m, f_m$$

of V, necessarily of even cardinality $2m$, such that $\varphi(e_i, f_i) = 1$ for every i, while

$$\varphi(e_i, f_j) = 0 \quad (i \neq j), \qquad \varphi(e_i, e_j) = 0, \qquad \varphi(f_i, f_j) = 0$$

for all i and j. A pair (V, φ) with φ alternating and nondegenerate (definition 13.3.22) is called a *symplectic space*.

Example 22.3.4: The Standard Symplectic Space k^{2m}

Let k be any field and let $e_1, f_1, \dots, e_m, f_m$ be the standard basis of k^{2m}, listed in that order. Define

$$\varphi\Big(\sum_i (x_i e_i + y_i f_i),\ \sum_i (x_i' e_i + y_i' f_i)\Big) = \sum_{i=1}^{m} (x_i y_i' - y_i x_i')$$

Each summand is the form of example 22.3.2(1) in the coordinate pair (x_i, y_i), so φ is bilinear and vanishes when its two arguments agree, hence is alternating. Evaluating on basis vectors gives $\varphi(e_i, f_i) = 1$, while $\varphi(e_i, f_j) = 0$ for $i \neq j$ and $\varphi(e_i, e_j) = \varphi(f_i, f_j) = 0$ for all i and j, because the i-th summand involves only the i-th coordinate pair. So the standard basis is symplectic. The matrix of φ in this basis is block diagonal with m blocks $\left(\begin{smallmatrix} 0 & 1 \\ -1 & 0 \end{smallmatrix}\right)$, so its determinant is 1 and φ is nondegenerate by lemma 13.3.23.

Listing the same basis as $e_1, \dots, e_m, f_1, \dots, f_m$ changes the matrix to $\left(\begin{smallmatrix} 0 & I_m \\ -I_m & 0 \end{smallmatrix}\right)$. The two orderings differ by a permutation matrix P, so by theorem 22.1.4 the matrices differ by $A \mapsto P^t A P$ and the determinant is unchanged, being multiplied by $(\det P)^2 = 1$. This second ordering identifies k^{2m} with $k^m \oplus k^m$ and writes the form as

$$\varphi\big((x, y), (x', y')\big) = x^t y' - y^t x' \tag{22.2}$$

for column vectors $x, y, x', y' \in k^m$, which is the shape used for computations below.

A degenerate example is obtained by padding. On k^{2m+r} with basis $e_1, f_1, \dots, e_m, f_m, z_1, \dots, z_r$, extend φ by declaring $\varphi(z_j, -) = \varphi(-, z_j) = 0$ for every j. The result is alternating, and its radical is $\operatorname{span}(z_1, \dots, z_r)$. To see this, write $v = \sum_i (x_i e_i + y_i f_i) + \sum_j c_j z_j$. Then $\varphi(e_i, v) = y_i$ and $\varphi(f_i, v) = -x_i$ and $\varphi(z_j, v) = 0$, and since φ is linear in its first argument, v lies in the radical (definition 13.3.22) exactly when every x_i and every y_i vanishes.

Every alternating form is one of the forms just written down. This is the classification, and it holds over every field.

Theorem 22.3.5: Linear Darboux Theorem

Let k be a field, with no hypothesis on its characteristic, let V be a k-vector space of finite dimension n, and let φ be an alternating bilinear form on V (definition 22.3.1).

1. There are integers $m, r \geq 0$ with $n = 2m + r$ and a basis
$$e_1, f_1, \ldots, e_m, f_m, z_1, \ldots, z_r$$
of V such that $\varphi(e_i, f_i) = 1$ for every i, while every other value of φ on an ordered pair of basis vectors is 0 except $\varphi(f_i, e_i) = -1$.
2. For any such basis, $\operatorname{rad}(\varphi) = \operatorname{span}(z_1, \ldots, z_r)$. Hence $r = \dim \operatorname{rad}(\varphi)$ and $2m = n - \dim \operatorname{rad}(\varphi)$, so both integers are determined by φ and do not depend on the basis chosen in (1).
3. φ is nondegenerate if and only if $r = 0$, and in that case $n = 2m$ is even and the basis of (1) is a symplectic basis (definition 22.3.3). In particular a symplectic space has even dimension.
4. Let φ' be an alternating form on a k-vector space V' with $\dim V' = \dim V$. Then φ and φ' are isometric if and only if $\dim \operatorname{rad}(\varphi) = \dim \operatorname{rad}(\varphi')$. In particular, for each even n there is exactly one nondegenerate alternating form on an n-dimensional space up to isometry, and none at all when n is odd.

***Proof*:**

1. *Step 1: a pair e, f with $\varphi(e, f) = 1$.* Assume $\varphi \neq 0$ and choose $u, w \in V$ with $c := \varphi(u, w) \neq 0$. Put $e := u$ and $f := c^{-1}w$, so that $\varphi(e, f) = c^{-1}\varphi(u, w) = 1$, and $\varphi(f, e) = -1$ by (22.1). The two are linearly independent: if $\alpha e + \beta f = 0$ then applying $\varphi(e, -)$ gives $\alpha\varphi(e, e) + \beta\varphi(e, f) = \beta = 0$, and applying $\varphi(f, -)$ gives $\alpha\varphi(f, e) = -\alpha = 0$. Write $P = \operatorname{span}(e, f)$, a two-dimensional subspace.

   Step 2: $V = P \oplus P^{\perp}$. The set $P^{\perp}$ is a subspace and equals $\{e, f\}^{\perp}$, both by lemma 13.3.21 applied to the subset $\{e, f\}$, whose span is P. Given $v \in V$, set
$$v' := v - \varphi(e, v)\, f + \varphi(f, v)\, e$$
   Then, using $\varphi(e, e) = \varphi(f, f) = 0$, $\varphi(e, f) = 1$ and $\varphi(f, e) = -1$,
$$\varphi(e, v') = \varphi(e, v) - \varphi(e, v)\cdot 1 + \varphi(f, v)\cdot 0 = 0 \qquad \varphi(f, v') = \varphi(f, v) - \varphi(e, v)\cdot 0 + \varphi(f, v)\cdot(-1) = 0$$
   so $v' \in P^{\perp}$, and $v = \big(\varphi(e, v)f - \varphi(f, v)e\big) + v'$ exhibits v in $P + P^{\perp}$. The sum is direct: if $\alpha e + \beta f \in P^{\perp}$ then $\varphi(e, \alpha e + \beta f) = \beta = 0$ and $\varphi(f, \alpha e + \beta f) = -\alpha = 0$. Hence $V = P \oplus P^{\perp}$ and $\dim P^{\perp} = n - 2$.

   Step 3: induction on n. For $n = 0$ take the empty basis and $m = r = 0$. Let $n \geq 1$ and assume the statement for all spaces of smaller dimension. If $\varphi = 0$, any basis of V serves with $m = 0$ and $r = n$. Otherwise Steps 1 and 2 produce $V = P \oplus P^{\perp}$ with $\dim P^{\perp} = n - 2$.

The restriction of φ to $P^\perp \times P^\perp$ is bilinear and satisfies the vanishing condition, so it is alternating, and the inductive hypothesis gives a basis $e_2, f_2, \dots, e_m, f_m, z_1, \dots, z_r$ of $P^\perp$ with the stated table of values. Set $e_1 := e$ and $f_1 := f$. The concatenated list is a basis of V by Step 2. Its values are as claimed: within $P^\perp$ by the inductive hypothesis, on the pair (e_1, f_1) by Step 1, and for a pair with one entry in $\{e_1, f_1\}$ and the other in $P^\perp$ because $\varphi(e_1, v) = \varphi(f_1, v) = 0$ for $v \in P^\perp$ by the definition of $P^\perp$, whence also $\varphi(v, e_1) = \varphi(v, f_1) = 0$ by (22.1). Counting the list gives $n = 2m + r$.

2. Let $v = \sum_i a_i e_i + \sum_i b_i f_i + \sum_j c_j z_j$. Since φ is linear in its first argument, $v \in \operatorname{rad}(\varphi)$ holds if and only if $\varphi(x, v) = 0$ for x running over the basis. The table of values in (1) gives

$$\varphi(e_i, v) = b_i, \qquad \varphi(f_i, v) = -a_i, \qquad \varphi(z_j, v) = 0$$

for all i and j. So $v \in \operatorname{rad}(\varphi)$ if and only if every a_i and every b_i vanishes, that is if and only if $v \in \operatorname{span}(z_1, \dots, z_r)$. Those z_j are part of a basis, hence independent, so $\dim \operatorname{rad}(\varphi) = r$, and $2m = n - r$ follows from $n = 2m + r$. The radical was defined in definition 13.3.22 without reference to a basis, so r and m are the same for every basis as in (1).

3. By definition 13.3.22, φ is nondegenerate exactly when $\operatorname{rad}(\varphi) = 0$, which by (2) happens exactly when $r = 0$. Then $n = 2m$, and the list of (1) is a basis satisfying the conditions of definition 22.3.3.

4. Suppose first that $\dim \operatorname{rad}(\varphi) = \dim \operatorname{rad}(\varphi')$. By (2) the two forms have bases as in (1) with the same m and the same r, since $\dim V = \dim V'$. Let $f\colon V \to V'$ be the linear map carrying each basis vector of V to the correspondingly named basis vector of V'. It is an isomorphism, being a bijection on bases, and the two bilinear maps $(x, y) \mapsto \varphi'(f(x), f(y))$ and $(x, y) \mapsto \varphi(x, y)$ agree on every ordered pair of basis vectors by construction, hence agree everywhere by bilinearity. So f is an isometry in the sense of definition 22.3.1.

   Conversely let f be an isometry. Its inverse is one as well: putting $x = f^{-1}(x')$ and $y = f^{-1}(y')$ in the defining identity gives $\varphi\big(f^{-1}(x'), f^{-1}(y')\big) = \varphi'(x', y')$. Now let $v \in \operatorname{rad}(\varphi)$ and let $x' \in V'$. Since f is onto, $x' = f(x)$ for some x, and then $\varphi'(x', f(v)) = \varphi(x, v) = 0$. Hence $f\big(\operatorname{rad}(\varphi)\big) \subseteq \operatorname{rad}(\varphi')$, and the same argument for f^{-1} gives $f^{-1}\big(\operatorname{rad}(\varphi')\big) \subseteq \operatorname{rad}(\varphi)$, that is $\operatorname{rad}(\varphi') \subseteq f\big(\operatorname{rad}(\varphi)\big)$. So f restricts to an isomorphism between the two radicals, and their dimensions agree.

   For the last sentence, take φ and φ' nondegenerate of the same dimension n: both radicals are zero, so they are isometric, and the standard form of example 22.3.4 gives one such φ when n is even. When n is odd, (3) forbids a nondegenerate alternating form outright, completing the proof.

The symmetric case behaves differently over the very same field. Example 22.2.5 exhibits two nondegenerate symmetric forms of rank 2 over $\mathbb{F}_5$ that are not isometric, the discriminant separating them, while part (4) makes any two nondegenerate alternating forms on a space of the same dimension isometric, over $\mathbb{F}_5$ or over any other field. No invariant of the discriminant's kind can exist for alternating forms. Indeed, if φ is nondegenerate alternating with symplectic basis β_0, then $[\varphi]_{\beta_0}$ is block diagonal with m blocks $\left(\begin{smallmatrix} 0 & 1 \\ -1 & 0 \end{smallmatrix}\right)$ by definition 22.3.3, so $\det[\varphi]_{\beta_0} = 1$. Any other basis β gives

$[\varphi]_\beta = P^t[\varphi]_{\beta_0}P$ by theorem 22.1.4, whence

$$\det[\varphi]_\beta = (\det P)^2$$

So the determinant of every matrix of φ is a nonzero square, and the square class that definition 22.1.7 extracts in the symmetric case is trivial here for every form and separates nothing.[1]

In odd dimension the theorem is a nonexistence statement: there is no nondegenerate alternating form at all, and every alternating form on a space of odd dimension n has a radical of odd dimension $n - 2m$. Symmetric forms are unconstrained in this respect, since $\langle 1, 1, 1\rangle$ has the identity as its matrix and is nondegenerate in dimension 3 by lemma 13.3.23.

The basis of theorem 22.3.5 exhibits two subspaces of dimension m on which φ vanishes identically, namely $\operatorname{span}(e_1, \dots, e_m)$ and $\operatorname{span}(f_1, \dots, f_m)$. Subspaces with that property have a name, and it is given for an arbitrary bilinear form since the symmetric case needs it too.

Definition 22.3.6: Totally Isotropic Subspace

Let k be a field, with no hypothesis on its characteristic, let V be a finite-dimensional k-vector space, and let φ be a bilinear form on V. A subspace $W \subseteq V$ is *totally isotropic* for φ if

$$\varphi(x, y) = 0 \qquad \text{for all } x, y \in W$$

equivalently if $W \subseteq W^\perp$ in the notation of definition 13.3.20. The shorter term *isotropic subspace* is used below for the same condition.

Example 22.3.7: Totally Isotropic Subspaces in Two Standard Forms

1. Let φ be alternating on V over any field. Every line $W = kv$ is totally isotropic, since $\varphi(\lambda v, \mu v) = \lambda\mu\,\varphi(v, v) = 0$. So an alternating form has isotropic subspaces in abundance, whatever the field.

2. In the standard symplectic space k^{2m} of example 22.3.4, the subspaces $E = \operatorname{span}(e_1, \dots, e_m)$ and $F = \operatorname{span}(f_1, \dots, f_m)$ are totally isotropic, since $\varphi(e_i, e_j) = 0$ and $\varphi(f_i, f_j) = 0$ for all i, j and the condition is bilinear in the two arguments. Each has dimension m, half of $\dim k^{2m}$.

3. Let $k = \mathbb{R}$ and let $\varphi = \langle 1, 1\rangle$ on $\mathbb{R}^2$, that is $\varphi(x, y) = x_1y_1 + x_2y_2$, with associated quadratic form $q(x) = x_1^2 + x_2^2$ under proposition 22.1.2. If W is totally isotropic and $v \in W$, then $q(v) = \varphi(v, v) = 0$, and a sum of two real squares vanishes only when both do, so $v = 0$. The only totally isotropic subspace is 0. So the abundance in (1) is a feature of the alternating case and not of bilinear forms in general.

The subspaces in item (2) have exactly half the dimension of the ambient space, and item (1) produces nothing larger there. Half is in fact the maximum whenever the form is nondegenerate, for symmetric and alternating forms alike, and the bound follows from a dimension count for orthogonal

[1] The name of the theorem is by analogy with Darboux's theorem in symplectic geometry, which states that a closed nondegenerate differential 2-form on a smooth manifold admits, around each point, coordinates in which it is the constant form displayed in example 22.3.4. That theorem is about manifolds and is not proved in this book. The statement here is its pointwise linear-algebra counterpart.

complements. Degeneracy destroys the bound at once: the zero form on any V is alternating, and V itself is then totally isotropic.

Proposition 22.3.8: The Dimension Bound for Isotropic Subspaces

Let k be a field, with no hypothesis on its characteristic, let V be a k-vector space of finite dimension n, and let φ a nondegenerate bilinear form on V (definition 13.3.22).

1. For every subspace $W \subseteq V$,
$$\dim W + \dim W^{\perp} = n$$
2. If W is totally isotropic (definition 22.3.6) then $\dim W \leq \frac{1}{2}n$, with equality if and only if $W = W^{\perp}$.
3. Assume in addition that φ is alternating, so that $n = 2m$ is even by theorem 22.3.5(3). Then every totally isotropic subspace of V is contained in a totally isotropic subspace of dimension m. Such subspaces exist, and the maximal totally isotropic subspaces of V are exactly those of dimension m.

***Proof*:**

1. Let $d = \dim W$ and define $\Psi\colon V \to W^*$ by $\Psi(y)(x) = \varphi(x, y)$ for $x \in W$. Each $\Psi(y)$ is linear on W and Ψ is linear in y, both by bilinearity of φ. By definition 13.3.20, $\Psi(y) = 0$ says exactly that $y \in W^{\perp}$, so $\ker \Psi = W^{\perp}$.

   Ψ is surjective. First, the map $\Theta\colon V \to V^*$ with $\Theta(y) = \varphi(-, y)$ has kernel $\operatorname{rad}(\varphi)$, which is 0 by definition 13.3.22 and the nondegeneracy hypothesis. The dual basis of proposition 13.3.5 is a basis of V^*, so $\dim V^* = \dim V$, while corollary 13.1.18 gives $\dim V = \dim \ker \Theta + \dim \Theta(V) = \dim \Theta(V)$. Hence the image $\Theta(V)$ is a subspace of V^* of the full dimension, so $\Theta(V) = V^*$. Second, every $g \in W^*$ extends to V: choose a basis $w_1, \ldots, w_d$ of W, extend it to a basis $w_1, \ldots, w_n$ of V, and let $\tilde{g} \in V^*$ be the linear map with $\tilde{g}(w_i) = g(w_i)$ for $i \leq d$ and $\tilde{g}(w_i) = 0$ for $i > d$. Then $\tilde{g}$ and g are linear maps on W agreeing on a basis of W, so $\tilde{g}|_W = g$. Combining, given $g \in W^*$ pick y with $\Theta(y) = \tilde{g}$. Then $\Psi(y) = \tilde{g}|_W = g$.

   Now corollary 13.1.18 applied to Ψ gives $n = \dim \ker \Psi + \dim \Psi(V) = \dim W^{\perp} + \dim W^*$, and $\dim W^* = \dim W$ again by proposition 13.3.5, this time for the space W.

2. If W is totally isotropic then $W \subseteq W^{\perp}$ by definition 22.3.6, so $\dim W \leq \dim W^{\perp} = n - \dim W$ by (1), which rearranges to $2 \dim W \leq n$. Equality holds exactly when $\dim W = \dim W^{\perp}$, and a subspace contained in another of the same finite dimension equals it, so equality is equivalent to $W = W^{\perp}$.

3. Let W be totally isotropic with $d = \dim W < m$. By (1), $\dim W^{\perp} = 2m - d > d = \dim W$, and $W \subseteq W^{\perp}$, so there is a vector $v \in W^{\perp}$ with $v \notin W$. Put $W' = W + kv$, of dimension $d + 1$. It is totally isotropic: for $w, w' \in W$ and $\lambda, \mu \in k$,
$$\varphi(w + \lambda v,\ w' + \mu v) = \varphi(w, w') + \mu\, \varphi(w, v) + \lambda\, \varphi(v, w') + \lambda\mu\, \varphi(v, v)$$

and the four terms vanish in turn because W is totally isotropic, because $v \in W^\perp$, because $\varphi(v, w') = -\varphi(w', v) = 0$ by (22.1) and $v \in W^\perp$, and because φ is alternating. Repeating the step $m - d$ times produces a totally isotropic subspace of dimension m containing W.

Existence follows by applying this to $W = 0$, or directly from theorem 22.3.5(3): the span of $e_1, \dots, e_m$ in a symplectic basis is totally isotropic of dimension m. Finally, a totally isotropic subspace of dimension m is maximal among totally isotropic subspaces, since any subspace properly containing it has dimension exceeding the bound in (2). And one of dimension $d < m$ is not maximal, since the construction above properly enlarges it. So maximality is equivalent to having dimension m, as we sought to show.

Part (3) fails for symmetric forms: example 22.3.7(3) gives a nondegenerate symmetric form of rank 2 over $\mathbb{R}$ whose only totally isotropic subspace is 0, so there the maximal one has dimension 0 rather than 1. The alternating case is uniform because $\varphi(v, v) = 0$ holds for every v by definition: enlarging an isotropic W needs a vector of $W^\perp$ outside W on which the form vanishes, and the vanishing is automatic, so the dimension count in (1) gives the vector by itself. The subspaces attaining the bound carry a name.

Definition 22.3.9: Lagrangian Subspace

Let k be a field, with no hypothesis on its characteristic, and let (V, φ) be a symplectic space of dimension $2m$, so φ is alternating and nondegenerate (definition 22.3.3). A *Lagrangian subspace* of (V, φ) is a totally isotropic subspace $L \subseteq V$ with $\dim L = m$.

By proposition 22.3.8(2) this is the same as requiring $L = L^\perp$, and by proposition 22.3.8(3) it is the same as requiring L to be maximal among the totally isotropic subspaces of V. That same part guarantees Lagrangian subspaces exist in every symplectic space.

Example 22.3.10: Lagrangian Subspaces of the Standard Symplectic Space

Work in $k^{2m} = k^m \oplus k^m$ with the form (22.2), $\varphi\big((x, y), (x', y')\big) = x^t y' - y^t x'$.

1. For $S \in M_m(k)$ let $L_S = \{(x, Sx) \mid x \in k^m\}$, the graph of S. It is a subspace of dimension m, the map $x \mapsto (x, Sx)$ being linear and injective. For $x, x' \in k^m$,

$$\varphi\big((x, Sx), (x', Sx')\big) = x^t Sx' - (Sx)^t x' = x^t Sx' - x^t S^t x' = x^t\big(S - S^t\big)x'$$

   Taking x and x' to be the i-th and j-th standard basis vectors of k^m turns the right-hand side into the (i, j) entry of $S - S^t$, so the expression vanishes for all x, x' if and only if $S = S^t$. Hence L_S is Lagrangian exactly when S is symmetric. Taking $S = 0$ recovers $E = \operatorname{span}(e_1, \dots, e_m)$.

2. Conversely, every Lagrangian L with $L \cap F = 0$, where $F = \{(0, y) \mid y \in k^m\}$, is of this form. The projection $\pi(x, y) = x$ restricts to a linear map $L \to k^m$ with kernel $L \cap F = 0$, hence injective, and $\dim L = m$ forces it to be bijective by corollary 13.1.18. Let σ be its inverse and write $\sigma(x) = (x, Sx)$, where S is linear because σ is. Then $L = L_S$, and S is symmetric by (1).

3. For $m = 1$ every line in k^2 is Lagrangian: a line is totally isotropic by example 22.3.7(1) and has dimension $1 = m$. Over $k = \mathbb{F}_q$ the lines of k^2 number $(q^2 - 1)/(q - 1) = q + 1$, so

there are $q+1$ Lagrangians. For $m \geq 2$ having dimension m is not sufficient: inside k^4 the subspace $\operatorname{span}(e_1, f_1)$ has dimension $2 = m$ and is not totally isotropic, since $\varphi(e_1, f_1) = 1$.

Items (1) and (2) together put the Lagrangians meeting F trivially in bijection with the symmetric $m \times m$ matrices, the assignment $S \mapsto L_S$ being injective because L_S determines Sx as the second component of its element with first component x. The symmetric matrices form a k-vector space of dimension $\binom{m+1}{2}$. The two counts agree where they overlap: for $m = 1$ every 1×1 matrix is symmetric, so over $\mathbb{F}_q$ that bijection accounts for q Lagrangians, and the one remaining line, F itself, brings the total to the $q+1$ of item (3).

Exercise 22.3.1

1. Over $k = \mathbb{F}_2$, show that every symmetric bilinear form on k^2 satisfies the sign rule $\varphi(x, y) = -\varphi(y, x)$. Then determine which of the eight symmetric bilinear forms on $\mathbb{F}_2^2$ are alternating in the sense of definition 22.3.1, and say how the count is consistent with lemma 16.1.4(2).

2. Let $\operatorname{char} k \neq 2$ and let φ be a nondegenerate alternating form on a k-vector space of dimension n, with matrix A in some basis. Using $\det(A^t) = \det(A)$ and $A^t = -A$, show directly that n is even. Then explain which step of your argument fails over $\mathbb{F}_2$, and why the conclusion nevertheless still holds there.

3. Let k be any field. Show that a bilinear form φ on k^n is alternating if and only if there are scalars a_{ij} for $1 \leq i < j \leq n$ with

$$\varphi(x, y) = \sum_{i<j} a_{ij}\left(x_i y_j - x_j y_i\right)$$

   and that the a_{ij} are then determined by φ. Deduce that over $k = \mathbb{F}_q$ there are exactly $q^{n(n-1)/2}$ alternating forms on k^n.

4. Let $\operatorname{char} k \neq 2$. Show that every bilinear form φ on V is uniquely $\varphi = s + a$ with s symmetric and a alternating, and identify s and a in terms of φ and $(x, y) \mapsto \varphi(y, x)$. Then show the statement fails over $\mathbb{F}_2$ by exhibiting a bilinear form on $\mathbb{F}_2^2$ that is not such a sum.

5. Let (V, φ) be a symplectic space of dimension $2m$ and let L be a Lagrangian subspace with basis $e_1, \dots, e_m$. Show that there exist $f_1, \dots, f_m \in V$ making $e_1, f_1, \dots, e_m, f_m$ a symplectic basis of (V, φ). (Suggestion: for each i apply proposition 22.3.8(1) to the span of the e_j with $j \neq i$ to produce u_i with $\varphi(e_j, u_i) = 1$ when $i = j$ and 0 otherwise, then replace u_i by $u_i + \sum_j c_{ij} e_j$ for a suitable choice of scalars, noting that this leaves the previous values unchanged.) Deduce that for any two Lagrangian subspaces L and L' of (V, φ) there is an isometry of (V, φ) carrying L onto L'.

6. Let φ be an alternating form on V with radical $R = \operatorname{rad}(\varphi)$. Show that $\bar{\varphi}(x+R, y+R) := \varphi(x, y)$ is a well-defined alternating form on V/R, that it is nondegenerate, and that $\dim V/R$ is even. Compare the resulting statement with theorem 22.3.5(2).

7. Let (V, φ) be a symplectic space of dimension $2m$. Show that there is a chain of subspaces $0 = W_0 \subset W_1 \subset \cdots \subset W_m$ with $\dim W_i = i$ and each W_i totally isotropic, and that W_m is then a Lagrangian subspace. Show also that no such chain can be continued to a totally isotropic W_{m+1}.

22.4 Isotropy, the Hyperbolic Plane, and Witt Decomposition

A diagonalization records the values a form takes on n chosen vectors and says nothing about the vectors the form kills. This section organizes a symmetric form around those vectors instead, the v with $\varphi(v, v) = 0$. Two cases are extreme. A form may have no such vector other than 0. Or it may be spanned by two of them paired against each other, and then it is a single two-dimensional form which is the same over every field. The theorem of this section splits an arbitrary symmetric form into pieces of exactly those two kinds together with its radical, and so isolates the one summand in which the arithmetic of k is still visible.

The number of two-dimensional pieces and the isometry class of the remaining piece are determined by the form, but the argument for that is Witt cancellation and is deferred to section 22.5. What is available here without it is a statement about the subspaces on which the form vanishes identically: the largest dimension such a subspace can have is an invariant by construction, and it counts the two-dimensional pieces in a decomposition built from a subspace attaining it.

Every statement below breaks V into mutually orthogonal subspaces, and the notation for that is fixed first. It has already been used in box 22.1.9.

Definition 22.4.1: Orthogonal Sum of Forms

Let k be a field.

1. Let φ and ψ be bilinear forms on finite-dimensional k-vector spaces V and W. Their *orthogonal sum* is the bilinear form $\varphi \perp \psi$ on $V \oplus W$ given by

$$(\varphi \perp \psi)\big((v, w), (v', w')\big) := \varphi(v, v') + \psi(w, w')$$

   It is symmetric when φ and ψ are.

2. Let φ be a bilinear form on V and let $U_1, U_2 \subseteq V$ be subspaces with $V = U_1 \oplus U_2$ and $\varphi(u_1, u_2) = 0$ for all $u_1 \in U_1$ and $u_2 \in U_2$. Then V is the *internal orthogonal sum* of U_1 and U_2, written $V = U_1 \perp U_2$.

Both constructions iterate to finitely many summands.

The two halves of the definition describe one situation from outside and from inside. If $V = U_1 \perp U_2$ internally, then $(u_1, u_2) \mapsto u_1 + u_2$ is an isometry from $\varphi|_{U_1} \perp \varphi|_{U_2}$ to φ in the sense of definition 22.1.10, because expanding $\varphi(u_1 + u_2, u_1' + u_2')$ by bilinearity leaves only $\varphi(u_1, u_1')$ and $\varphi(u_2, u_2')$, the two cross terms being zero by hypothesis. Concatenating a basis β of U_1 with a basis γ of U_2 gives a basis of V in which every entry $\varphi(\beta_i, \gamma_j)$ vanishes, so by definition 13.3.18 the matrix of φ is block diagonal with blocks $[\varphi|_{U_1}]_\beta$ and $[\varphi|_{U_2}]_\gamma$. The determinant of an orthogonal sum is therefore the product of the determinants of its summands, and by lemma 13.3.23 the sum is nondegenerate exactly when both summands are. The diagonal notation of section 22.2 is an orthogonal sum of lines,

$$\langle a_1, \dots, a_n \rangle = \langle a_1 \rangle \perp \cdots \perp \langle a_n \rangle$$

so theorem 22.2.1 says exactly that every symmetric form is an orthogonal sum of one-dimensional forms.

Definition 22.4.2: Isotropic and Anisotropic Vectors

Let k be a field, let V be a finite-dimensional k-vector space, let φ be a symmetric bilinear form on V, and write $q(v) := \varphi(v, v)$ for the associated quadratic form. A nonzero vector $v \in V$ is *isotropic* if $q(v) = 0$, and *anisotropic* if $q(v) \neq 0$. The form φ is *isotropic* if V contains an isotropic vector, and *anisotropic* otherwise, that is if

$$q(v) = 0 \implies v = 0$$

The zero vector is excluded deliberately: $q(0) = 0$ for every form, so admitting it would make every form isotropic. An anisotropic form is automatically nondegenerate, since a nonzero $v \in \operatorname{rad}(\varphi)$ (definition 13.3.22) satisfies $\varphi(v, x) = 0$ for every x and in particular $q(v) = 0$, which is an isotropic vector. Restricting an anisotropic form to a subspace leaves it anisotropic, since the defining implication is inherited by subsets, and hence leaves it nondegenerate.

A subspace on which φ vanishes identically, $\varphi(w, w') = 0$ for all $w, w' \in W$, is *totally isotropic* (definition 22.3.6). When $\operatorname{char} k \neq 2$ it suffices to check the quadratic form on W: if $q(w) = 0$ for every $w \in W$, then for $w, w' \in W$,

$$0 = q(w + w') = q(w) + 2\varphi(w, w') + q(w') = 2\varphi(w, w')$$

and dividing by 2 gives $\varphi(w, w') = 0$. A totally isotropic subspace is thus one all of whose nonzero vectors are isotropic.

Example 22.4.3: Isotropy of Diagonal Forms

Whether a form is isotropic depends on the field and not only on the diagonal entries.

1. $\langle 1, 1\rangle$ over $\mathbb{R}$ is anisotropic: $x^2 + y^2 = 0$ forces $x^2 = -y^2$, and a sum of two nonnegative reals vanishes only when both do.
2. $\langle 1, 1\rangle$ over $\mathbb{F}_5$ is isotropic. The vector $(2, 1)$ is nonzero and $2^2 + 1^2 = 5 = 0$ in $\mathbb{F}_5$. Over $\mathbb{F}_3$ the squares are 0 and 1, so $x^2 + y^2$ takes only the values $0, 1, 2$ and vanishes only at $x = y = 0$: the same diagonal entries give an anisotropic form.
3. $\langle 1, -1\rangle$ is isotropic over every field, since $q(1, 1) = 1 - 1 = 0$ and $(1, 1) \neq 0$.
4. Let d be a squarefree integer with $d \neq 1$ and let $F = \mathbb{Q}(\sqrt{d})$. By example 22.1.11 the trace form of $F/\mathbb{Q}$ is $\langle 2, 2d\rangle$ in the basis $(1, \sqrt{d})$, with quadratic form $q(x, y) = 2x^2 + 2dy^2$. A zero with $y = 0$ forces $x = 0$, so an isotropic vector has $y \neq 0$, and dividing $x^2 = -dy^2$ by y^2 gives $-d = (x/y)^2$. The trace form is therefore isotropic exactly when $-d$ is a square in $\mathbb{Q}$. A positive squarefree integer is a rational square only when it equals 1, so this happens for $d = -1$ alone: of all the quadratic fields, only $\mathbb{Q}(i)$ has isotropic trace form, and $q(1, 1) = 2 - 2 = 0$ exhibits the vector.

Item (3) is the smallest isotropic form, and it is worth presenting in coordinates that exhibit its two isotropic directions at once. In place of one distinguished isotropic vector it carries two, paired against each other, and that pairing is what keeps the form nondegenerate.

Definition 22.4.4: The Hyperbolic Plane

Let k be a field and let φ be a symmetric bilinear form on a k-vector space U. A *hyperbolic pair* in U is a pair of vectors $e, f \in U$ with

$$\varphi(e,e) = \varphi(f,f) = 0, \qquad \varphi(e,f) = 1$$

The form φ is a *hyperbolic plane* if $\dim U = 2$ and U has a basis which is a hyperbolic pair, so that the matrix of φ in that basis is $\left(\begin{smallmatrix} 0 & 1 \\ 1 & 0 \end{smallmatrix}\right)$. A hyperbolic plane is written H. A subspace of (V, φ) is *a hyperbolic plane in* V when the restriction of φ to it is one, and the orthogonal sum of m copies,

$$mH := \underbrace{H \perp \cdots \perp H}_{m}$$

is the *hyperbolic space* of rank $2m$, with $0H := 0$.

Writing H for *the* hyperbolic plane is legitimate because any two are isometric: if (e, f) and (e', f') are hyperbolic pairs spanning U and U', then the linear isomorphism carrying $e \mapsto e'$ and $f \mapsto f'$ gives the two forms the same matrix in the corresponding bases, and by lemma 13.3.19 a form is recovered from its matrix in a basis, so the isomorphism is an isometry. That matrix has determinant $-1 \neq 0$, so a hyperbolic plane is nondegenerate by lemma 13.3.23, and its discriminant (definition 22.1.7) is the square class of -1.

Example 22.4.5: The Hyperbolic Plane as a Diagonal Form

Let $\operatorname{char} k \neq 2$ and let H have hyperbolic pair (e, f). Put

$$x := e + \tfrac{1}{2}f, \qquad y := e - \tfrac{1}{2}f$$

Then $x + y = 2e$ and $x - y = f$, and since $2 \neq 0$ these recover e and f, so (x, y) is again a basis of H. Expanding by bilinearity and using $\varphi(e,e) = \varphi(f,f) = 0$ together with $\varphi(e,f) = 1$,

$$q(x) = 2 \cdot \tfrac{1}{2}\varphi(e,f) = 1, \qquad q(y) = -2 \cdot \tfrac{1}{2}\varphi(e,f) = -1$$

$$\varphi(x,y) = -\tfrac{1}{2}\varphi(e,f) + \tfrac{1}{2}\varphi(f,e) = 0$$

so (x, y) is an orthogonal basis and

$$H \cong \langle 1, -1 \rangle$$

The product of the diagonal entries is -1, which agrees through corollary 22.2.3 with the determinant computed above. Over $\mathbb{R}$ this is the indefinite plane $x^2 - y^2$. Over a field containing an i with $i^2 = -1$, proposition 22.2.2 applied with $c_1 = 1$ and $c_2 = i$ gives $\langle 1, -1 \rangle \cong \langle 1, 1 \rangle$. Combined with example 22.2.4, every nondegenerate binary form over an algebraically closed field of characteristic other than 2 is a hyperbolic plane.

The hyperbolic plane was assembled from a pair of isotropic vectors. The next result runs the construction in reverse: a single isotropic vector of a nondegenerate form always has a partner, and the plane the two span splits off as an orthogonal summand. The splitting is what makes the construction iterable, and iterating it is the proof of the decomposition theorem.

Proposition 22.4.6: Every Isotropic Vector Lies in a Hyperbolic Plane

Let k be a field with $\operatorname{char} k \neq 2$, let V be a finite-dimensional k-vector space, and let φ be a nondegenerate symmetric bilinear form on V. Let $v \in V$ be isotropic. Then there is an $f \in V$ such that (v, f) is a hyperbolic pair, and, writing $H_v := \operatorname{span}(v, f)$,

$$V = H_v \perp H_v^{\perp}$$

where H_v is a hyperbolic plane in V and $\varphi|_{H_v^{\perp}}$ is nondegenerate. In particular a nondegenerate symmetric form is anisotropic if and only if V contains no hyperbolic plane.

***Proof*:**

Step 1: producing the partner. An isotropic vector is nonzero, so $v \notin \operatorname{rad}(\varphi) = 0$ and there is a $w_0 \in V$ with $\varphi(v, w_0) \neq 0$. Replacing w_0 by $w := \varphi(v, w_0)^{-1} w_0$ gives $\varphi(v, w) = 1$. Set

$$f := w - \frac{q(w)}{2}\, v$$

which uses $\operatorname{char} k \neq 2$ to divide. Using $q(v) = \varphi(v, v) = 0$,

$$\varphi(v, f) = \varphi(v, w) - \frac{q(w)}{2}\varphi(v, v) = 1$$

and, expanding by bilinearity and symmetry,

$$\varphi(f, f) = \varphi(w, w) - 2 \cdot \frac{q(w)}{2}\varphi(w, v) + \frac{q(w)^2}{4}\varphi(v, v) = q(w) - q(w) = 0$$

so (v, f) is a hyperbolic pair. The two vectors are linearly independent: a relation $f = \lambda v$ would give $1 = \varphi(v, f) = \lambda\varphi(v, v) = 0$, and $v \neq 0$. Hence $\dim H_v = 2$, the matrix of $\varphi|_{H_v}$ in the basis (v, f) is $\left(\begin{smallmatrix} 0 & 1 \\ 1 & 0 \end{smallmatrix}\right)$, and H_v is a hyperbolic plane in V, nondegenerate by lemma 13.3.23.

Step 2: the splitting. Let $x \in V$ and put

$$x' := x - \varphi(x, f)\, v - \varphi(x, v)\, f$$

Using the values of φ on the pair (v, f),

$$\varphi(x', v) = \varphi(x, v) - \varphi(x, f)\varphi(v, v) - \varphi(x, v)\varphi(f, v) = \varphi(x, v) - \varphi(x, v) = 0$$

$$\varphi(x', f) = \varphi(x, f) - \varphi(x, f)\varphi(v, f) - \varphi(x, v)\varphi(f, f) = \varphi(x, f) - \varphi(x, f) = 0$$

so x' is orthogonal to v and to f, hence to their span by lemma 13.3.21, that is $x' \in H_v^{\perp}$. Since $x - x' \in H_v$, this gives $V = H_v + H_v^{\perp}$. The sum is direct: an element $u \in H_v \cap H_v^{\perp}$ lies in H_v and is orthogonal to every element of H_v, hence lies in $\operatorname{rad}(\varphi|_{H_v})$, which is zero by Step 1. The two summands are orthogonal by the definition of $H_v^{\perp}$ (definition 13.3.20), so $V = H_v \perp H_v^{\perp}$ in the sense of definition 22.4.1.

Step 3: the complement is nondegenerate. Let $x \in \operatorname{rad}\big(\varphi|_{H_v^{\perp}}\big)$, so $\varphi(x, y) = 0$ for every $y \in H_v^{\perp}$. Since $x \in H_v^{\perp}$ and φ is symmetric, $\varphi(x, y) = 0$ for every $y \in H_v$ as well. By Step 2 each element of V is a sum of one vector of each kind, so $\varphi(x, -)$ vanishes on V and $x \in \operatorname{rad}(\varphi) = 0$.

Step 4: the equivalence. If φ is isotropic, Steps 1 to 3 produce a hyperbolic plane in V. Conversely, a hyperbolic plane in V contains a vector e with $\varphi(e,e) = 0$ and $e \neq 0$, the latter because $\varphi(e,f) = 1$ forbids $e = 0$, so φ is isotropic. Hence V contains a hyperbolic plane precisely when φ is isotropic, completing the proof.

The proposition converts one-dimensional information, the existence of a single vector with $q(v) = 0$, into a two-dimensional summand of known isometry type. What is left of φ is the restriction $\varphi|_{H_v^\perp}$, again nondegenerate and of dimension two smaller, so the exchange can be repeated until no isotropic vector remains. In dimension two there is nothing left to repeat, and the statement becomes a criterion.

Example 22.4.7: Binary Forms and Hyperbolic Planes

Let $\operatorname{char} k \neq 2$ and let $\varphi \cong \langle a, b\rangle$ be a nondegenerate form of rank 2, so that $a, b \in k^\times$ by proposition 22.2.2. If φ is isotropic then proposition 22.4.6 puts a hyperbolic plane H_v inside V, and $\dim H_v = 2 = \dim V$ forces $H_v = V$, so $\varphi \cong H$. A nondegenerate binary form is therefore either anisotropic or a hyperbolic plane.

The entries determine which of the two occurs. An isotropic vector for $q(x,y) = ax^2 + by^2$ has both coordinates nonzero, since $y = 0$ forces $ax^2 = 0$ and hence $x = 0$, and symmetrically $x = 0$ forces $y = 0$. Multiplying $ax^2 = -by^2$ by b and dividing by x^2 gives

$$-ab = \left(\frac{by}{x}\right)^2$$

Conversely, if $-ab = c^2$ then $c \neq 0$ because $ab \neq 0$, and the nonzero vector (b, c) satisfies $ab^2 + bc^2 = ab^2 - ab \cdot b = 0$. So $\langle a, b\rangle$ is a hyperbolic plane exactly when $-ab$ is a square, which by corollary 22.2.3 says exactly that $\operatorname{disc}(\varphi)$ is the class of -1. For instance $\langle 1, 1\rangle$ over $\mathbb{F}_5$ has $-ab = -1 = 4 = 2^2$, so it is the hyperbolic plane, whereas over $\mathbb{F}_3$ the element $-1 = 2$ is not a square and the form is anisotropic, matching example 22.4.3.

Iterating proposition 22.4.6 splits a hyperbolic plane off a nondegenerate form as long as one isotropic vector can be found, and the process stops only when none can. A degenerate form has to be handled first: the nonzero vectors of its radical are isotropic and orthogonal to all of V, so no partner exists for them and proposition 22.4.6 does not apply. Splitting the radical off and then iterating gives the decomposition.

Theorem 22.4.8: Witt Decomposition

Let k be a field with $\operatorname{char} k \neq 2$, let V be a finite-dimensional k-vector space and let φ be a symmetric bilinear form on V. Then there are an integer $m \geq 0$, subspaces $H_1, \ldots, H_m \subseteq V$ each of which is a hyperbolic plane in V, and a subspace $V_{\mathrm{an}} \subseteq V$ on which φ is anisotropic, such that

$$V = \operatorname{rad}(\varphi) \perp H_1 \perp \cdots \perp H_m \perp V_{\mathrm{an}}$$

Writing $r = \dim \operatorname{rad}(\varphi)$, this reads

$$\varphi \cong \langle \underbrace{0, \ldots, 0}_{r}\rangle \perp mH \perp \varphi|_{V_{\mathrm{an}}}$$

***Proof*:**
Step 1: splitting off the radical. Write $R := \operatorname{rad}(\varphi)$ and choose a basis of R. By theorem 13.1.8 it extends to a basis of V. Let V' be the span of the added vectors, so that $V = R \oplus V'$. Every element of R is orthogonal to every element of V, in particular to every element of V', so $V = R \perp V'$ in the sense of definition 22.4.1, and $\varphi|_R = 0$.

The restricted form $\varphi|_{V'}$ is nondegenerate. Let $x \in V'$ satisfy $\varphi(x, y) = 0$ for all $y \in V'$. Since also $\varphi(x, y) = 0$ for all $y \in R$, and $V = R + V'$, the map $\varphi(x, -)$ vanishes on V, so $x \in R \cap V' = 0$.

Step 2: splitting hyperbolic planes off a nondegenerate form. It suffices to prove that a nondegenerate symmetric form ψ on a space U decomposes as $U = H_1 \perp \cdots \perp H_m \perp U_{\text{an}}$ with each H_i a hyperbolic plane in U and $\psi|_{U_{\text{an}}}$ anisotropic. Applying this to $\varphi|_{V'}$ and appending Step 1 gives the theorem, because every summand of V' is orthogonal to R.

Induct on $\dim U$. If ψ is anisotropic, take $m = 0$ and $U_{\text{an}} = U$. This covers $\dim U = 0$, where there is nothing to decompose, and $\dim U = 1$: an isotropic vector v would span U, and then $\psi(v, \lambda v) = \lambda\psi(v, v) = 0$ for every λ would put v in $\operatorname{rad}(\psi)$, contradicting nondegeneracy. Otherwise ψ has an isotropic vector, and proposition 22.4.6 gives a hyperbolic plane $H_1 \subseteq U$ with

$$U = H_1 \perp H_1^{\perp}$$

and $\psi|_{H_1^{\perp}}$ nondegenerate. Since $\dim H_1^{\perp} = \dim U - 2$, the inductive hypothesis applies to $H_1^{\perp}$ and gives $H_1^{\perp} = H_2 \perp \cdots \perp H_m \perp U_{\text{an}}$ with each H_i a hyperbolic plane and $\psi|_{U_{\text{an}}}$ anisotropic. Every one of these subspaces lies in $H_1^{\perp}$ and is therefore orthogonal to H_1, so the displayed decomposition of U refines to $U = H_1 \perp H_2 \perp \cdots \perp H_m \perp U_{\text{an}}$.

Step 3: the diagonal reading. Take the chosen basis of R, a hyperbolic pair in each H_i, and an orthogonal basis of V_{an}, which exists by theorem 22.2.1. Their concatenation is a basis of V, and by the block-diagonal description following definition 22.4.1 the matrix of φ in it is the block sum of the zero matrix of size r, m copies of $\left(\begin{smallmatrix} 0 & 1 \\ 1 & 0 \end{smallmatrix}\right)$, and a diagonal matrix. That is the asserted isometry, completing the proof.

The three summands answer three different questions about φ. The radical is where the form carries no information at all, and its dimension is already known to be an invariant by proposition 22.2.2. The hyperbolic part carries no information beyond its rank, since any two hyperbolic planes over k are isometric, whatever k is. Everything that distinguishes φ from other forms of the same rank is therefore concentrated in $\varphi|_{V_{\text{an}}}$, and how large that summand can be is a property of the field. Over an algebraically closed field it has dimension at most 1: a two-dimensional subspace of an anisotropic space is nondegenerate, hence a hyperbolic plane by example 22.4.5, hence isotropic, which contradicts anisotropy. This recovers example 22.2.4, where the classification collapsed to the rank. Over a finite field the bound is one step weaker, and a counting argument gives it.

Example 22.4.9: Isotropy over a Finite Field
Let $k = \mathbb{F}_q$ with q odd.

Every equation $ax^2 + by^2 = c$ with $a, b \in k^\times$ and $c \in k$ has a solution. As recorded in example 22.2.5, the squaring map on $\mathbb{F}_q^\times$ has kernel $\{\pm 1\}$, which has two elements because q is odd, so there are $(q-1)/2$ nonzero squares and the set $\left\{x^2 \;\middle|\; x \in k\right\}$ has $(q+1)/2$ elements. Multiplication by a is

a bijection of k, so

$$S := \left\{ax^2 \;\middle|\; x \in k\right\}, \qquad T := \left\{c - by^2 \;\middle|\; y \in k\right\}$$

each have $(q+1)/2$ elements. Their sizes add to $q+1 > q = |k|$, so S and T are not disjoint, and a common element gives x, y with $ax^2 = c - by^2$.

Every nondegenerate form of rank at least 3 *over* $\mathbb{F}_q$ *is isotropic.* Diagonalize by theorem 22.2.1 as $\varphi \cong \langle a_1, \ldots, a_n\rangle$ in an orthogonal basis $w_1, \ldots, w_n$. Nondegeneracy makes every a_i nonzero by the last claim of proposition 22.2.2. With $n \geq 3$, solve $a_1x^2 + a_2y^2 = -a_3$ by the previous paragraph and set $v := xw_1 + yw_2 + w_3$, which is nonzero because its third coordinate is 1. Then $q(v) = a_1x^2 + a_2y^2 + a_3 = 0$.

Consequently, in the Witt decomposition of a form over $\mathbb{F}_q$ the anisotropic summand has dimension at most 2. Both values occur: $\langle 1\rangle$ is anisotropic of rank 1, and if $\epsilon \in \mathbb{F}_q^\times$ is a non-square then $\langle 1, -\epsilon\rangle$ has $-ab = \epsilon$ a non-square, so it is anisotropic of rank 2 by example 22.4.7.

Theorem 22.4.8 produces some number m of hyperbolic planes, and nothing in its proof says that a different sequence of choices produces the same number. A quantity that is visibly independent of all choices is available instead, and the rest of the section relates the two.

Definition 22.4.10: The Witt Index

Let k be a field, let V be a finite-dimensional k-vector space and let φ be a symmetric bilinear form on V. The *Witt index* of φ is

$$\nu(\varphi) := \max\left\{\dim W \mid W \subseteq V \text{ a totally isotropic subspace}\right\}$$

The maximum exists: the zero subspace is totally isotropic, so the set of dimensions is nonempty, and it is bounded above by $\dim V$.

The Witt index is an invariant of φ by construction, since it is defined without reference to a basis or a decomposition, and isometries carry totally isotropic subspaces to totally isotropic subspaces of the same dimension. It is zero exactly when φ is anisotropic, since a one-dimensional totally isotropic subspace is the span of an isotropic vector. The next result computes it against theorem 22.4.8.

Proposition 22.4.11: The Witt Index Counts Hyperbolic Planes

Let k be a field with $\operatorname{char} k \neq 2$, let V be a finite-dimensional k-vector space of dimension n and let φ be a nondegenerate symmetric bilinear form on V.

1. Let $W \subseteq V$ be totally isotropic with $\dim W = d$. Then there are hyperbolic planes $H_1, \dots, H_d$ in V, with hyperbolic pairs (e_i, f_i) such that $e_1, \dots, e_d$ is a basis of W, and a subspace U with $\varphi|_U$ nondegenerate, such that

$$V = H_1 \perp \cdots \perp H_d \perp U$$

   In particular $2d \leq n$, which is also proposition 22.3.8(2) applied to the totally isotropic W.

2. In the situation of (1), the form $\varphi|_U$ is anisotropic if and only if W is maximal among the totally isotropic subspaces of V.

3. $\nu(\varphi) \leq n/2$; some decomposition as in theorem 22.4.8 has exactly $\nu(\varphi)$ hyperbolic planes; and every such decomposition has at most $\nu(\varphi)$ of them.

***Proof*:**

1. Induct on d. For $d = 0$ take $U = V$, and there is nothing to prove. Let $d \geq 1$ and choose a basis $w_1, \dots, w_d$ of W. Since W is totally isotropic and $w_1 \neq 0$, the vector w_1 is isotropic, so proposition 22.4.6 gives an f_1 making (w_1, f_1) a hyperbolic pair, with $H_1 = \operatorname{span}(w_1, f_1)$ a hyperbolic plane, $V = H_1 \perp H_1^\perp$ and $\varphi|_{H_1^\perp}$ nondegenerate.

   Consider the linear map $\lambda\colon W \to k$ defined by $\lambda(x) = \varphi(x, f_1)$. It is nonzero, since $\lambda(w_1) = \varphi(w_1, f_1) = 1$, so $\ker\lambda$ has dimension $d-1$. Moreover $\ker\lambda = W \cap H_1^\perp$: every $x \in W$ satisfies $\varphi(x, w_1) = 0$ because W is totally isotropic and $w_1 \in W$, so x lies in $H_1^\perp$ exactly when in addition $\varphi(x, f_1) = 0$, using lemma 13.3.21 to reduce orthogonality to H_1 to orthogonality to the two spanning vectors.

   Set $W_1 := W \cap H_1^\perp$, a totally isotropic subspace of $H_1^\perp$ of dimension $d-1$. The inductive hypothesis, applied to the nondegenerate form $\varphi|_{H_1^\perp}$, gives hyperbolic planes $H_2, \dots, H_d$ in $H_1^\perp$ with hyperbolic pairs (e_i, f_i) whose vectors $e_2, \dots, e_d$ form a basis of W_1, and a subspace U with $\varphi|_U$ nondegenerate and $H_1^\perp = H_2 \perp \cdots \perp H_d \perp U$. All of these lie in $H_1^\perp$ and are therefore orthogonal to H_1, so $V = H_1 \perp H_2 \perp \cdots \perp H_d \perp U$. Finally $w_1 \notin W_1$, because $\lambda(w_1) = 1$ while λ vanishes on W_1, so $w_1, e_2, \dots, e_d$ are d linearly independent vectors of W and hence a basis of it. Setting $e_1 := w_1$ gives the statement. The dimension count is $n = 2d + \dim U \geq 2d$.

2. Write $\mathcal{H} := H_1 \perp \cdots \perp H_d$, so $V = \mathcal{H} \oplus U$ and $W = \operatorname{span}(e_1, \dots, e_d)$ by (1).

   Suppose first that $\varphi|_U$ is anisotropic, and let $W' \supseteq W$ be totally isotropic. Take $x \in W'$ and write $x = \sum_i (a_i e_i + b_i f_i) + u$ with $u \in U$. For each j the vector e_j lies in $W \subseteq W'$, so $\varphi(x, e_j) = 0$. On the other hand the only summand of x not orthogonal to e_j is $b_j f_j$, whence $\varphi(x, e_j) = b_j$. So every b_j vanishes and $x = \sum_i a_i e_i + u$. Expanding $q(x)$ by bilinearity, the terms $\varphi(e_i, e_j)$ vanish for all i, j and the terms $\varphi(e_i, u)$ vanish because $e_i \in \mathcal{H}$ and $u \in U$, leaving $q(x) = q(u)$. As $x \in W'$ is isotropic or zero, $q(u) = 0$, so $u = 0$ by anisotropy and $x \in W$. Hence $W' = W$ and W is maximal.

Suppose instead that $\varphi|_U$ is isotropic, say $u \in U$ is nonzero with $q(u) = 0$. Then $W + ku$ is totally isotropic: expanding $\varphi(w + au,\ w' + a'u)$ leaves $\varphi(w, w') = 0$, the cross terms $\varphi(w, u) = 0$ and $\varphi(u, w') = 0$ since $W \subseteq \mathcal{H}$ and $u \in U$, and $aa'q(u) = 0$. It strictly contains W, because $u \notin \mathcal{H} \supseteq W$, so W is not maximal. The two implications together give the stated equivalence.

3. Applying (1) to a totally isotropic subspace of dimension $\nu(\varphi)$ gives $2\nu(\varphi) \leq n$. That subspace is maximal, being of largest dimension, so (2) makes the corresponding U anisotropic and
$$V = H_1 \perp \cdots \perp H_{\nu(\varphi)} \perp U$$
is a decomposition as in theorem 22.4.8, with radical zero and exactly $\nu(\varphi)$ hyperbolic planes. Conversely, let $V = H'_1 \perp \cdots \perp H'_m \perp V_{\text{an}}$ be any such decomposition, with hyperbolic pair (e'_i, f'_i) in H'_i. The vectors $e'_1, \ldots, e'_m$ lie in distinct summands of a direct sum and are nonzero, hence are linearly independent, and their span is totally isotropic: $\varphi(e'_i, e'_j) = 0$ for $i \neq j$ by orthogonality of the summands and $\varphi(e'_i, e'_i) = 0$ by the definition of a hyperbolic pair. So $m \leq \nu(\varphi)$, completing the proof.

Part (3) does not say that every decomposition has $\nu(\varphi)$ hyperbolic planes. It produces one that does and bounds all the others by that number, and no argument given above closes the gap: comparing two decompositions of the same space requires an isometry between them, and producing one is what Witt cancellation gives. Section 22.5 proves it, and with it every decomposition of a nondegenerate φ in theorem 22.4.8 has $m = \nu(\varphi)$ and an anisotropic summand determined up to isometry. Nondegeneracy is needed there: the Witt index of a degenerate form counts its radical as well, and running the same statement on a complement of the radical gives $m = \nu(\varphi) - \dim \operatorname{rad}(\varphi)$ instead, by exercise 22.4.1 (4). What is established here is that $\nu(\varphi)$ bounds the number of hyperbolic planes in any decomposition, and that the bound is attained when φ is nondegenerate. Over $\mathbb{R}$ that number can be computed directly from a diagonalization.

Example 22.4.12: The Witt Index over the Reals

Let φ be nondegenerate on a real vector space V of dimension n. By theorem 22.2.1 and proposition 22.2.2 applied with $c_i = |a_i|^{-1/2}$, there is a basis $u_1, \ldots, u_p, w_1, \ldots, w_r$ of V, orthogonal for φ, with $q(u_i) = 1$ and $q(w_j) = -1$ and $p + r = n$.

Pairing the vectors two at a time, $\operatorname{span}(u_i, w_i)$ carries the form $\langle 1, -1\rangle$, which is a hyperbolic plane by example 22.4.5. Doing this for $i \leq \min(p, r)$ and collecting the remaining $|p - r|$ basis vectors, which all have the same value of q, gives
$$\varphi \cong \min(p, r)\, H \perp \langle \pm 1, \ldots, \pm 1\rangle$$
with $|p - r|$ entries in the last summand, all equal to $+1$ if $p > r$ and all to -1 if $r > p$. That summand is anisotropic, a sum of $|p - r|$ squares being zero only when each is.

The Witt index is $\min(p, r)$. It is at least that, by the span of the $u_i + w_i$ for $i \leq \min(p, r)$, which are linearly independent and satisfy $q(u_i + w_i) = 1 - 1 = 0$ and $\varphi(u_i + w_i, u_j + w_j) = 0$ for $i \neq j$. For the reverse bound let W be totally isotropic and let $P := \operatorname{span}(u_1, \ldots, u_p)$. A nonzero $x \in P$ has $q(x) = \sum_i x_i^2 > 0$, so x is not isotropic and $W \cap P = 0$, forcing $\dim W \leq n - p = r$. The same argument with $N := \operatorname{span}(w_1, \ldots, w_r)$, where $q(y) = -\sum_j y_j^2 < 0$ for $y \neq 0$, gives $\dim W \leq n - r = p$. Hence $\nu(\varphi) = \min(p, r)$, in agreement with proposition 22.4.11(3).

Since $\nu(\varphi)$ and n depend only on φ, the unordered pair $\{p, r\}$ does too. Which of the two is p is not settled by this argument, and that remaining bit is Sylvester's law of inertia, which needs the

order on $\mathbb{R}$ in a way the present chapter does not use.

Exercise 22.4.1

1. Let $\operatorname{char} k \neq 2$ and let $a \in k^\times$. Show that $\langle 1, -a\rangle$ is isotropic if and only if a is a square in k, and that in that case $\langle 1, -a\rangle \cong H$. Using that $\mathbb{Q}^\times/(\mathbb{Q}^\times)^2$ is infinite, deduce that $\mathbb{Q}$ carries infinitely many pairwise non-isometric anisotropic binary forms.

2. Let $\operatorname{char} k \neq 2$. Show that the hyperbolic plane represents every scalar: for each $c \in k$ there is $x \in H$ with $q(x) = c$. Deduce that a nondegenerate isotropic form on any V represents every element of k.

3. Let $\operatorname{char} k \neq 2$ and let $\varphi \cong \langle a, b\rangle$ be nondegenerate of rank 2. Using example 22.4.7, decide for which pairs (a, b) over $k = \mathbb{Q}$ the form is a hyperbolic plane, and exhibit one anisotropic and one hyperbolic example.

4. Let φ be a symmetric bilinear form on V with radical $R = \operatorname{rad}(\varphi)$, and let $\bar{\varphi}$ be the induced nondegenerate form on V/R from exercise 22.1.1 (5). Show that $\nu(\varphi) = \dim R + \nu(\bar{\varphi})$.

5. Let φ be nondegenerate on V and let $W \subseteq V$ be totally isotropic. Show that W is maximal among totally isotropic subspaces if and only if every isotropic vector of $W^\perp$ already lies in W.

6. Show that $\nu(\varphi \perp \psi) \geq \nu(\varphi) + \nu(\psi)$ for symmetric bilinear forms φ and ψ, and give an example over $\mathbb{R}$ where the inequality is strict.

7. Let q be odd and let φ be a nondegenerate symmetric bilinear form of odd rank n over $\mathbb{F}_q$. Show that $\nu(\varphi) = (n-1)/2$, so the Witt index over a finite field is forced by the rank alone when the rank is odd.

8. Let $V = \mathbb{F}_7^3$ with φ the standard dot product, so $q(x, y, z) = x^2 + y^2 + z^2$. Verify that $v = (3, 2, 1)$ is isotropic, run the construction in the proof of proposition 22.4.6 with $w = (0, 0, 1)$ to produce a partner f, compute a spanning vector of $H_v^\perp$, and write out the resulting decomposition $V = H_v \perp \langle a\rangle$. Is a a square in $\mathbb{F}_7$?

22.5 Witt Cancellation and Witt's Extension Theorem

Theorem 22.4.8 splits a form into an anisotropic part, a sum of hyperbolic planes and the radical, and each step of that construction rests on a choice: which isotropic vector to complete to a hyperbolic plane, and which complement to continue in. Nothing proved so far forces two runs of the construction to return the same number of hyperbolic planes, or isometric anisotropic parts. This section proves that they do. The result that delivers it is a cancellation law for orthogonal sums: a nondegenerate summand common to both sides of an isometry may be deleted. The section then proves Witt's extension theorem, which says that an isometry between two subspaces of a nondegenerate space is always the restriction of an isometry of the whole space. Both rest on one construction, the reflection in an anisotropic vector, which this book has not yet defined.

Throughout, $q(x) = \varphi(x, x)$ is the quadratic form attached to a symmetric bilinear form φ by proposition 22.1.2, and $\varphi \perp \psi$ is the orthogonal sum of definition 22.4.1. One further fact about that operation is used repeatedly below: the bijections $\big(v, (w, x)\big) \mapsto \big((v, w), x\big)$ and $(v, w) \mapsto (w, v)$ leave

the defining expression unchanged, so they are isometries, and an orthogonal sum of several forms may be regrouped and reordered freely without changing its isometry class.

Every theorem below produces an isometry of a space with itself, so those isometries need a name.

Definition 22.5.1: The Orthogonal Group of a Form

Let k be a field, let V be a finite-dimensional k-vector space and let φ be a symmetric bilinear form on V. The *orthogonal group* of φ is

$$O(\varphi) = \{\sigma \colon V \to V \mid \sigma \text{ is an isometry of } (V, \varphi) \text{ with itself}\}$$

where isometry is meant in the sense of definition 22.1.10, and the operation is composition of maps.

That this is a group takes nothing beyond the definition: id_V is an isometry; a composite of linear bijections preserving φ is again a linear bijection preserving φ; and if σ is an isometry then so is σ^{-1}, since $\varphi(\sigma^{-1}x, \sigma^{-1}y) = \varphi(\sigma\sigma^{-1}x, \sigma\sigma^{-1}y) = \varphi(x, y)$ for all $x, y \in V$.

The construction used throughout the section takes an anisotropic vector (definition 22.4.2) and produces the isometry that negates it and fixes everything orthogonal to it. Over $\mathbb{R}$ with the dot product this is the familiar mirror reflection in the hyperplane $\{v\}^{\perp}$, and the formula below is the one from that setting, written so that it makes sense over any field in which $q(v)$ is invertible.

Definition 22.5.2: Reflection in an Anisotropic Vector

Let k be a field with $\operatorname{char} k \neq 2$, let V be a finite-dimensional k-vector space with a symmetric bilinear form φ, and let $v \in V$ be anisotropic, that is $q(v) = \varphi(v, v) \neq 0$. The *reflection in* v is the map $\tau_v \colon V \to V$ given by

$$\tau_v(x) = x - \frac{2\varphi(v, x)}{\varphi(v, v)}\, v$$

The denominator is nonzero precisely because v is anisotropic, which is why the construction is available for anisotropic vectors and for no others.

The properties that make τ_v useful are all direct computations with the defining formula.

Lemma 22.5.3: Reflections Are Involutive Isometries

Let k be a field with $\operatorname{char} k \neq 2$, let V be a finite-dimensional k-vector space with a symmetric bilinear form φ, and let $v \in V$ be anisotropic. Then:

1. $V = kv \oplus \{v\}^{\perp}$;
2. τ_v is linear, $\tau_v(v) = -v$, and $\tau_v(x) = x$ for every $x \in \{v\}^{\perp}$;
3. τ_v preserves φ and satisfies $\tau_v \circ \tau_v = \mathrm{id}_V$. In particular $\tau_v \in O(\varphi)$ and $\tau_v^{-1} = \tau_v$;
4. $\tau_{\lambda v} = \tau_v$ for every $\lambda \in k^{\times}$;
5. $\det \tau_v = -1$. In particular $\tau_v \neq \mathrm{id}_V$, so τ_v has order exactly 2 in $O(\varphi)$.

***Proof*:**
Write $a = q(v) = \varphi(v, v) \neq 0$ throughout. The set $\{v\}^\perp$ is a subspace by lemma 13.3.21.

1. Every $x \in V$ decomposes as

$$x = \frac{\varphi(v,x)}{a}\, v + \left(x - \frac{\varphi(v,x)}{a}\, v\right)$$

and applying $\varphi(v, -)$ to the bracketed vector gives $\varphi(v,x) - \frac{\varphi(v,x)}{a}\, a = 0$, so that vector lies in $\{v\}^\perp$ and $V = kv + \{v\}^\perp$. The sum is direct: if $\lambda v \in \{v\}^\perp$ then $0 = \varphi(v, \lambda v) = \lambda a$, and $a \neq 0$ forces $\lambda = 0$.

2. Linearity holds because $x \mapsto \varphi(v, x)$ is linear and τ_v subtracts a scalar multiple of the fixed vector v. Substituting $x = v$ gives $\tau_v(v) = v - \frac{2a}{a} v = v - 2v = -v$, and if $\varphi(v, x) = 0$ then the subtracted term vanishes, so $\tau_v(x) = x$.

3. For $x, y \in V$, expanding by bilinearity and symmetry,

$$\varphi\big(\tau_v(x), \tau_v(y)\big) = \varphi(x,y) - \frac{2\varphi(v,y)}{a}\varphi(x,v) - \frac{2\varphi(v,x)}{a}\varphi(v,y) + \frac{4\varphi(v,x)\varphi(v,y)}{a^2}\, a$$

The last three terms are $-2c$, $-2c$ and $+4c$ with $c = \varphi(v,x)\varphi(v,y)/a$, so they cancel and $\varphi(\tau_v(x), \tau_v(y)) = \varphi(x, y)$. For the involution, first

$$\varphi\big(v, \tau_v(x)\big) = \varphi(v,x) - \frac{2\varphi(v,x)}{a}\, a = -\varphi(v,x)$$

so

$$\tau_v\big(\tau_v(x)\big) = \tau_v(x) - \frac{2\varphi(v,\tau_v(x))}{a}\, v = x - \frac{2\varphi(v,x)}{a}\, v + \frac{2\varphi(v,x)}{a}\, v = x$$

Hence τ_v is a linear bijection preserving φ, which is an isometry of (V, φ) with itself in the sense of definition 22.1.10, so $\tau_v \in O(\varphi)$ by definition 22.5.1 and $\tau_v^{-1} = \tau_v$.

4. For $\lambda \neq 0$ the vector λv is anisotropic, since $q(\lambda v) = \lambda^2 a \neq 0$, and

$$\tau_{\lambda v}(x) = x - \frac{2\varphi(\lambda v, x)}{\lambda^2 a}\, \lambda v = x - \frac{2\lambda^2 \varphi(v,x)}{\lambda^2 a}\, v = \tau_v(x)$$

5. By (1) choose a basis $v, z_2, \ldots, z_n$ of V with $z_2, \ldots, z_n$ a basis of $\{v\}^\perp$. By (2) the matrix of τ_v in this basis is $\operatorname{diag}(-1, 1, \ldots, 1)$, whose determinant is -1. Since $\operatorname{char} k \neq 2$ this is not 1, so $\tau_v \neq \mathrm{id}_V$, and $\tau_v^2 = \mathrm{id}_V$ from (3) then makes its order exactly 2, completing the proof.

Example 22.5.4: Reflections of $\langle 1, 1\rangle$ over $\mathbb{Q}$
Let $k = \mathbb{Q}$ and let φ be the form on $V = \mathbb{Q}^2$ with matrix the identity in the standard basis e_1, e_2, so $q(x_1, x_2) = x_1^2 + x_2^2$ and $\varphi \cong \langle 1, 1\rangle$.

Take $v = e_1$, with $q(e_1) = 1$. Then $\tau_{e_1}(x) = x - 2\varphi(e_1, x)e_1 = x - 2x_1 e_1$, so $\tau_{e_1}(e_1) = -e_1$ and $\tau_{e_1}(e_2) = e_2$, and the matrix of τ_{e_1} is $\operatorname{diag}(-1, 1)$.

Take instead $v = (1,1)$, with $q(v) = 2 \neq 0$. Here $\tau_v(x) = x - \frac{2\varphi(v,x)}{2} v = x - \varphi(v,x)v$, so

$$\tau_v(e_1) = (1,0) - (1,1) = (0,-1), \qquad \tau_v(e_2) = (0,1) - (1,1) = (-1,0)$$

and the matrix of τ_v is $\left(\begin{smallmatrix} 0 & -1 \\ -1 & 0 \end{smallmatrix}\right)$. Both matrices have determinant -1 and square to the identity, as lemma 22.5.3 requires.

Their product is

$$\begin{pmatrix} 0 & -1 \\ -1 & 0 \end{pmatrix} \begin{pmatrix} -1 & 0 \\ 0 & 1 \end{pmatrix} = \begin{pmatrix} 0 & -1 \\ 1 & 0 \end{pmatrix}$$

an isometry of determinant 1 whose square is $-\mathrm{id}$ and whose fourth power is id. So $O(\langle 1,1\rangle)$ over $\mathbb{Q}$ contains an element of order 4, which is not a reflection: reflections have order 2 and determinant -1. Products of reflections are therefore strictly more general than reflections, and corollary 22.5.10 will say how much more general.

Reflections are used here for one property: they move a vector to any other vector of the same nonzero value under q. That is how every theorem below produces the isometry it needs, and it takes at most two reflections.

Lemma 22.5.5: Two Reflections Move a Vector to Any Other of the Same Value

Let k be a field with $\operatorname{char} k \neq 2$, let V be a finite-dimensional k-vector space with a symmetric bilinear form φ, and let $u, w \in V$ satisfy $q(u) = q(w) \neq 0$. Then there is a $\sigma \in O(\varphi)$ with $\sigma(u) = w$, and σ can be taken to be a product of at most two reflections.

***Proof*:**

Expanding both terms by bilinearity and using $q(w) = q(u)$,

$$q(u-w) + q(u+w) = \big(q(u) - 2\varphi(u,w) + q(w)\big) + \big(q(u) + 2\varphi(u,w) + q(w)\big) = 4q(u)$$

Since $\operatorname{char} k \neq 2$, the scalar $4 = 2^2$ is nonzero, so $4q(u) \neq 0$ and $q(u-w)$ and $q(u+w)$ do not both vanish.

Case 1: $q(u-w) \neq 0$. Put $v = u - w$, an anisotropic vector. Then

$$q(v) = q(u) - 2\varphi(u,w) + q(w) = 2\big(q(u) - \varphi(u,w)\big) = 2\varphi(v,u)$$

the last equality because $\varphi(v,u) = \varphi(u,u) - \varphi(w,u) = q(u) - \varphi(u,w)$. Hence $2\varphi(v,u)/q(v) = 1$, and

$$\tau_v(u) = u - \frac{2\varphi(v,u)}{q(v)}\, v = u - v = w$$

so $\sigma = \tau_v$ works, and it lies in $O(\varphi)$ by lemma 22.5.3.

Case 2: $q(u-w) = 0$. Then $q(u+w) = 4q(u) \neq 0$ by the displayed identity. The vectors u and $-w$ satisfy $q(-w) = q(w) = q(u) \neq 0$ and $q\big(u - (-w)\big) = q(u+w) \neq 0$, so Case 1 applied to the pair $u, -w$ gives $\tau_{u+w}(u) = -w$. Also $q(w) \neq 0$, so τ_w is defined, and $\tau_w(-w) = -\tau_w(w) = w$ by lemma 22.5.3(2). Therefore

$$(\tau_w \circ \tau_{u+w})(u) = \tau_w(-w) = w$$

and $\sigma = \tau_w \circ \tau_{u+w}$ is a product of two reflections, lying in $O(\varphi)$ because $O(\varphi)$ is closed under composition (definition 22.5.1), as we sought to show.

Both cases occur. In example 22.5.4 the vectors $u = e_1$ and $w = e_2$ have $q(u) = q(w) = 1$ and $q(u - w) = q(1, -1) = 2 \neq 0$, so Case 1 applies and the single reflection $\tau_{(1,-1)}$ carries e_1 to e_2. Indeed $\tau_{(1,-1)}(e_1) = e_1 - \frac{2 \cdot 1}{2}(1, -1) = (0, 1)$. Case 2 is not an artifact of the proof: over $\mathbb{Q}$ with $\varphi \cong \langle 1, 1, -1 \rangle$ the vectors $u = e_1$ and $w = (1, 1, 1)$ both have $q = 1$ while $q(u - w) = q(0, -1, -1) = 0$, and there no single reflection suffices: an equality $\tau_v(u) = w$ reads $u - w = \frac{2\varphi(v,u)}{q(v)} v$, and $w \neq u$ makes the coefficient nonzero, so $q(u - w)$ would be a nonzero square multiple of $q(v) \neq 0$ and in particular nonzero, contradicting $q(u - w) = 0$.

Lemma 22.5.5 carries no nondegeneracy hypothesis on φ, which matters immediately: the cancellation theorem is proved for arbitrary φ_1 and φ_2, whose radicals are not controlled, and only the summand being cancelled is required to be nondegenerate. The proof reduces that summand to one dimension, where the lemma does the work.

Theorem 22.5.6: Witt Cancellation

Let k be a field with $\operatorname{char} k \neq 2$. Let ψ be a *nondegenerate* symmetric bilinear form on a finite-dimensional k-vector space, and let φ_1, φ_2 be symmetric bilinear forms on finite-dimensional k-vector spaces. If

$$\psi \perp \varphi_1 \cong \psi \perp \varphi_2$$

then $\varphi_1 \cong \varphi_2$.

***Proof*:**

Step 1: reduction to a one-dimensional ψ. Let ψ live on U with $\dim U = m$. By theorem 22.2.1 the space U has an orthogonal basis $u_1, \ldots, u_m$, so $\psi \cong \langle c_1, \ldots, c_m \rangle$ with $c_i = \psi(u_i, u_i)$. By the last claim of proposition 22.2.2 the number of indices with $c_i = 0$ is $\dim \operatorname{rad}(\psi)$, which is 0 because ψ is nondegenerate. Hence every $c_i \neq 0$. Regrouping the orthogonal sum,

$$\psi \perp \varphi_j \cong \langle c_1 \rangle \perp \big(\langle c_2, \ldots, c_m \rangle \perp \varphi_j \big) \qquad (j = 1, 2)$$

So if the theorem holds whenever ψ is one-dimensional and nondegenerate, then cancelling $\langle c_1 \rangle$ from the hypothesis gives $\langle c_2, \ldots, c_m \rangle \perp \varphi_1 \cong \langle c_2, \ldots, c_m \rangle \perp \varphi_2$, and $m - 1$ further cancellations, formally an induction on m with the case $m = 0$ reading $\varphi_1 \cong \varphi_2$, give the theorem. It therefore suffices to treat $\psi = \langle c \rangle$ with $c \in k^\times$.

Step 2: the one-dimensional case. Let φ_j live on W_j and realize $\langle c \rangle \perp \varphi_j$ on $V_j = k e_j \oplus W_j$, where $q(e_j) = c$, $\varphi(e_j, W_j) = 0$, and the form restricted to W_j is φ_j. Write $\varphi^{(j)}$ for the form on V_j. First,

$$W_j = \{e_j\}^\perp \text{ inside } V_j$$

since $W_j \subseteq \{e_j\}^\perp$ by construction, and conversely if $x = \lambda e_j + y$ with $y \in W_j$ satisfies $\varphi^{(j)}(e_j, x) = 0$, then that value is λc, and $c \neq 0$ forces $\lambda = 0$.

Let $f \colon V_1 \to V_2$ be an isometry. Put $u = f(e_1) \in V_2$. Then $q^{(2)}(u) = q^{(1)}(e_1) = c \neq 0$ and $q^{(2)}(e_2) = c$, so lemma 22.5.5 applied inside $(V_2, \varphi^{(2)})$ gives $\sigma \in O(\varphi^{(2)})$ with $\sigma(u) = e_2$. The composite $g = \sigma \circ f \colon V_1 \to V_2$ is again an isometry, and $g(e_1) = e_2$.

Step 3: g carries W_1 onto W_2. For $x \in V_1$,

$$\varphi^{(2)}\big(e_2, g(x)\big) = \varphi^{(2)}\big(g(e_1), g(x)\big) = \varphi^{(1)}(e_1, x)$$

so $x \in \{e_1\}^{\perp}$ if and only if $g(x) \in \{e_2\}^{\perp}$. Since g is bijective, g maps $\{e_1\}^{\perp}$ onto $\{e_2\}^{\perp}$, which by Step 2 says $g(W_1) = W_2$. The restriction $g|_{W_1} \colon W_1 \to W_2$ is a linear isomorphism preserving the forms, that is an isometry $\varphi_1 \cong \varphi_2$, completing the proof.

The theorem is what makes the decomposition of theorem 22.4.8 independent of the choices made in producing it.

Corollary 22.5.7: The Anisotropic Part and the Witt Index Are Invariants

Let k be a field with $\operatorname{char} k \neq 2$ and let φ be a nondegenerate symmetric bilinear form on a finite-dimensional k-vector space. Suppose

$$\varphi \cong \varphi_1 \perp m_1 H \qquad \text{and} \qquad \varphi \cong \varphi_2 \perp m_2 H$$

with φ_1 and φ_2 anisotropic and $m_1, m_2 \geq 0$. Then $m_1 = m_2$ and $\varphi_1 \cong \varphi_2$.

***Proof*:**
By definition 22.4.4 a hyperbolic plane H has a basis e, f with $q(e) = q(f) = 0$ and $\varphi(e, f) = 1$, so its matrix in that basis is $\left(\begin{smallmatrix} 0 & 1 \\ 1 & 0 \end{smallmatrix}\right)$, of determinant $-1 \neq 0$. By lemma 13.3.23 the form H is nondegenerate. The matrix of an orthogonal sum in the union of two bases is block diagonal with the two matrices as blocks, so its determinant is the product of theirs, and mH is nondegenerate for every $m \geq 0$ by the same lemma. Also e is a nonzero isotropic vector of H.

Assume without loss of generality that $m_1 \leq m_2$. Regrouping the orthogonal sum,

$$\varphi_1 \perp m_1 H \cong \varphi \cong \varphi_2 \perp m_2 H \cong \big(\varphi_2 \perp (m_2 - m_1)H\big) \perp m_1 H$$

Since $m_1 H$ is nondegenerate, theorem 22.5.6 cancels it from the two ends and gives

$$\varphi_1 \cong \varphi_2 \perp (m_2 - m_1)H$$

If $m_2 > m_1$, the right-hand form has the nonzero isotropic vector e of any one of its hyperbolic summands, and the preimage of e under the isometry is nonzero and isotropic for φ_1, since an isometry is injective and preserves q. That contradicts the hypothesis that φ_1 is anisotropic. Hence $m_1 = m_2$, the term $(m_2 - m_1)H$ is the form on the zero space, and $\varphi_1 \cong \varphi_2$, as we sought to show.

So the Witt index of definition 22.4.10 deserves its name. Proposition 22.4.11(3) computes $\nu(\varphi)$ as the number of hyperbolic planes in the decomposition produced by the proof of theorem 22.4.8, and corollary 22.5.7 says that number is the same in every decomposition of that shape. So $m = \nu(\varphi)$ in *any* of them, and the anisotropic part is determined up to isometry by φ alone. Two nondegenerate forms $\varphi \cong \varphi_1 \perp mH$ and $\varphi' \cong \varphi'_1 \perp m'H$, with φ_1 and φ'_1 anisotropic, are therefore isometric if and only if $m = m'$ and $\varphi_1 \cong \varphi'_1$: if $\varphi \cong \varphi'$ then φ has the two decompositions $\varphi \cong \varphi_1 \perp mH$ and $\varphi \cong \varphi'_1 \perp m'H$, so corollary 22.5.7 gives $m = m'$ and $\varphi_1 \cong \varphi'_1$, while conversely $m = m'$ and $\varphi_1 \cong \varphi'_1$ give $\varphi \cong \varphi_1 \perp mH \cong \varphi'_1 \perp m'H \cong \varphi'$. That biconditional is the reduction the classification of forms

over a given field uses.

Cancellation deletes a summand from both sides of an isometry that is already given. The extension theorem is the statement that isometries are plentiful: any isometry defined on a subspace already extends to the whole space, with no compatibility condition beyond preserving the form. The subspace is allowed to be degenerate, and that is the substance of the theorem. For a subspace containing an anisotropic vector, the reduction to a smaller space is the argument already used twice above, whereas a totally isotropic subspace gives that argument nothing to work with. The following lemma is what repairs that case: it manufactures, for an isotropic vector inside a totally isotropic subspace, a partner making it half of a hyperbolic plane, chosen orthogonal to the rest of the subspace.

Lemma 22.5.8: Hyperbolic Partners for Isotropic Vectors

Let k be a field with $\operatorname{char} k \neq 2$, let φ be a nondegenerate symmetric bilinear form on a finite-dimensional k-vector space V, let $U \subseteq V$ be a subspace with $\varphi(x, y) = 0$ for all $x, y \in U$, let $u \in U$ be nonzero, and let $U_1 \subseteq U$ be a subspace with $U = ku \oplus U_1$. Then there exists $u^* \in V$ with

$$q(u^*) = 0, \qquad \varphi(u, u^*) = 1, \qquad \varphi(u^*, x) = 0 \text{ for all } x \in U_1$$

***Proof*:**

Let $u_1, \dots, u_m$ be a basis of U_1, so that $u, u_1, \dots, u_m$ is a basis of U and in particular a linearly independent family in V. Consider the linear map

$$\Phi \colon V \to k^{m+1}, \qquad \Phi(y) = \big(\varphi(u, y), \varphi(u_1, y), \dots, \varphi(u_m, y)\big)$$

Suppose Φ were not surjective. Its image is then a proper subspace of k^{m+1}, hence contained in the kernel of some nonzero linear functional (extend a basis of the image to a basis of k^{m+1} and take the member of the dual basis of proposition 13.3.5 attached to a vector outside the image): there are $\lambda_0, \dots, \lambda_m \in k$, not all zero, with $\lambda_0 \varphi(u, y) + \sum_{i=1}^{m} \lambda_i \varphi(u_i, y) = 0$ for every $y \in V$. Bilinearity rewrites this as $\varphi(z, y) = 0$ for every $y \in V$, where $z = \lambda_0 u + \sum_i \lambda_i u_i$. As φ is symmetric, this says $z \in \operatorname{rad}(\varphi)$ (definition 13.3.22), which is zero by nondegeneracy. And $u, u_1, \dots, u_m$ being linearly independent then forces every $\lambda_j = 0$, contradicting the choice of the λ_j. So Φ is surjective.

Choose $y \in V$ with $\Phi(y) = (1, 0, \dots, 0)$, so $\varphi(u, y) = 1$ and $\varphi(u_i, y) = 0$ for each i. By bilinearity the latter gives $\varphi(x, y) = 0$ for every $x \in U_1$. Since $\operatorname{char} k \neq 2$ the scalar $q(y)/2$ is defined, and we may set

$$u^* := y - \frac{q(y)}{2}\, u$$

Because $u \in U$ and φ vanishes identically on U, we have $q(u) = 0$ and $\varphi(u, x) = 0$ for $x \in U_1$. Hence

$$\varphi(u, u^*) = \varphi(u, y) - \frac{q(y)}{2} q(u) = 1 - 0 = 1$$

$$q(u^*) = q(y) - 2 \cdot \frac{q(y)}{2} \varphi(y, u) + \frac{q(y)^2}{4} q(u) = q(y) - q(y) + 0 = 0$$

using $\varphi(y, u) = \varphi(u, y) = 1$ by symmetry. Finally, for $x \in U_1$ both $\varphi(y, x) = 0$ and $\varphi(u, x) = 0$, so $\varphi(u^*, x) = 0$, completing the proof.

Theorem 22.5.9: Witt's Extension Theorem

Let k be a field with $\operatorname{char} k \neq 2$, let φ be a nondegenerate symmetric bilinear form on a finite-dimensional k-vector space V, let $U \subseteq V$ be a subspace, and let $f\colon U \to V$ be an injective linear map with

$$\varphi\big(f(x), f(y)\big) = \varphi(x, y) \qquad \text{for all } x, y \in U$$

Then there is an $F \in O(\varphi)$ with $F|_U = f$.

***Proof*:**
Induct on $\dim V$. If $\dim V = 0$ then $U = 0$ and $F = \mathrm{id}_V$ serves. So let $\dim V = n \geq 1$ and assume the theorem for every nondegenerate symmetric bilinear form on a space of dimension smaller than n. If $U = 0$, take $F = \mathrm{id}_V$. Assume $U \neq 0$.

Step 1: reduction to the case where φ does not vanish identically on U. Suppose $\varphi(x, y) = 0$ for all $x, y \in U$. Choose $u \in U$ nonzero and a subspace U_1 with $U = ku \oplus U_1$, and let $u_1, \ldots, u_m$ be a basis of U_1. Lemma 22.5.8 gives $u^* \in V$ with $q(u^*) = 0$, $\varphi(u, u^*) = 1$ and $\varphi(u^*, U_1) = 0$.

Put $u' = f(u)$ and $U_1' = f(U_1)$. Since f is injective and preserves φ, the subspace $f(U)$ satisfies $\varphi(x, y) = 0$ for all $x, y \in f(U)$, the vector u' is nonzero, and $f(U) = ku' \oplus U_1'$. A second application of lemma 22.5.8, to the subspace $f(U)$ with the vector u' and the complement U_1', gives $u'^* \in V$ with $q(u'^*) = 0$, $\varphi(u', u'^*) = 1$ and $\varphi(u'^*, U_1') = 0$.

Because $\varphi(u, u^*) = 1$ while $\varphi(u, x) = 0$ for every $x \in U$, the vector u^* is not in U, so $\tilde{U} := U \oplus ku^*$ has $u, u^*, u_1, \ldots, u_m$ as a basis. Define a linear map $\tilde{f}\colon \tilde{U} \to V$ by $\tilde{f}|_U = f$ and $\tilde{f}(u^*) = u'^*$.

The map $\tilde{f}$ preserves φ. By bilinearity it is enough to compare φ on pairs of basis vectors with φ on the pairs of their images, and the six comparisons are:

$$q(u) = 0 = q(u'), \qquad q(u^*) = 0 = q(u'^*), \qquad \varphi(u, u^*) = 1 = \varphi(u', u'^*)$$

$$\varphi(u, u_i) = 0 = \varphi\big(f(u), f(u_i)\big), \qquad \varphi(u^*, u_i) = 0 = \varphi(u'^*, f(u_i)), \qquad \varphi(u_i, u_j) = \varphi\big(f(u_i), f(u_j)\big)$$

the fourth and sixth because f preserves φ, the fifth by the two orthogonality conditions on u^* and u'^*.

The map $\tilde{f}$ is injective. Let $x = \lambda u + \mu u^* + w$ with $w \in U_1$ and $\tilde{f}(x) = 0$, that is $\lambda u' + \mu u'^* + f(w) = 0$. Applying $\varphi(u', -)$ and using $\varphi(u', u') = 0$, $\varphi(u', u'^*) = 1$ and $\varphi(u', f(w)) = \varphi(f(u), f(w)) = \varphi(u, w) = 0$ gives $\mu = 0$. Then $f(\lambda u + w) = 0$, so $\lambda u + w = 0$ by injectivity of f, so $\lambda = 0$ and $w = 0$ because $U = ku \oplus U_1$.

Finally $q(u + u^*) = q(u) + 2\varphi(u, u^*) + q(u^*) = 2 \neq 0$, so φ does not vanish identically on $\tilde{U}$. Any $F \in O(\varphi)$ with $F|_{\tilde{U}} = \tilde{f}$ satisfies $F|_U = f$, so it suffices to prove the theorem for the pair $(\tilde{U}, \tilde{f})$, which is of the kind treated next.

Step 2: the case where φ does not vanish identically on U. Some $u \in U$ has $q(u) \neq 0$: otherwise q vanishes on U and, for $x, y \in U$, $0 = q(x + y) = q(x) + 2\varphi(x, y) + q(y) = 2\varphi(x, y)$, which with $\operatorname{char} k \neq 2$ makes φ vanish identically on U.

Then $q(f(u)) = q(u) \neq 0$, so lemma 22.5.5 gives $\sigma \in O(\varphi)$ with $\sigma(f(u)) = u$. The map $f' := \sigma \circ f$ is again an injective linear map $U \to V$ preserving φ, and $f'(u) = u$.

Set $V_1 = \{u\}^\perp$ and $U' = U \cap V_1$. Four facts about these:

1. $V = ku \oplus V_1$ with $\varphi(u, V_1) = 0$, by lemma 22.5.3(1) applied to (V, φ) and the anisotropic vector u. In particular $\dim V_1 = n - 1$.
2. $U = ku \oplus U'$, by the same part of the same lemma applied to $(U, \varphi|_U)$, whose orthogonal complement of u inside U is $U \cap \{u\}^\perp = U'$.
3. $\varphi|_{V_1}$ is nondegenerate: if $y \in V_1$ satisfies $\varphi(y, V_1) = 0$, then also $\varphi(y, u) = 0$, so $\varphi(y, V) = 0$ by (1) and bilinearity, whence $y \in \operatorname{rad}(\varphi) = 0$.
4. $f'(U') \subseteq V_1$: for $x \in U'$, $\varphi(u, f'(x)) = \varphi(f'(u), f'(x)) = \varphi(u, x) = 0$.

So $f'|_{U'} \colon U' \to V_1$ is an injective linear map from a subspace of V_1 into V_1 preserving $\varphi|_{V_1}$, and $\dim V_1 = n - 1$. The inductive hypothesis gives $G \in O(\varphi|_{V_1})$ with $G|_{U'} = f'|_{U'}$.

Step 3: assembling F. Define $F' \colon V \to V$ by $F'(\lambda u + y) = \lambda u + G(y)$ for $\lambda \in k$ and $y \in V_1$. This is well defined and bijective by (1) and the bijectivity of G. It preserves φ: for $\lambda, \mu \in k$ and $y, z \in V_1$, using $G(y), G(z) \in V_1$ and $\varphi(u, V_1) = 0$ twice,

$$\varphi\big(\lambda u + G(y), \mu u + G(z)\big) = \lambda\mu\, q(u) + \varphi\big(G(y), G(z)\big) = \lambda\mu\, q(u) + \varphi(y, z) = \varphi(\lambda u + y, \mu u + z)$$

So $F' \in O(\varphi)$. It restricts to f' on U: writing $x \in U$ as $x = \lambda u + x'$ with $x' \in U'$ by (2),

$$F'(x) = \lambda u + G(x') = \lambda u + f'(x') = \lambda f'(u) + f'(x') = f'(x)$$

Set $F = \sigma^{-1} \circ F'$, an element of $O(\varphi)$. Then $F|_U = \sigma^{-1} \circ f' = \sigma^{-1} \circ \sigma \circ f = f$, completing the proof.

The hypothesis that φ be nondegenerate on the ambient space is not removable, and it enters the proof twice: in Step 1 through lemma 22.5.8, and in Step 2 as fact (3), where $\operatorname{rad}(\varphi) = 0$ is what makes $\varphi|_{V_1}$ nondegenerate and so permits the inductive hypothesis. What goes wrong without it is direct: an isometry of V carries $\operatorname{rad}(\varphi)$ onto itself, so a form-preserving injection sending a vector outside the radical into the radical extends to no isometry, and exercise 22.5.1 (6) exhibits one. Nondegeneracy of the *subspace* U, on the other hand, is nowhere assumed, and Step 1 is the work of doing without it.

Taking U to be a line already extends lemma 22.5.5 past its restriction to anisotropic vectors. Let φ be nondegenerate, let $c \in k$, and let v, v' be nonzero vectors with $q(v) = q(v') = c$. The map $f \colon kv \to V$ with $f(\lambda v) = \lambda v'$ is linear and injective, and $\varphi(f(\lambda v), f(\mu v)) = \lambda\mu\, q(v') = \lambda\mu\, q(v) = \varphi(\lambda v, \mu v)$, so theorem 22.5.9 extends it to an isometry of V carrying v to v'. So $O(\varphi)$ acts transitively on the nonzero vectors of each fixed value of q, including the value 0, where no reflection was available. The last consequence counts how many reflections it takes to build an arbitrary isometry.

Corollary 22.5.10: Reflections Generate the Orthogonal Group

Let k be a field with $\operatorname{char} k \neq 2$ and let φ be a nondegenerate symmetric bilinear form on a k-vector space V of finite dimension n. Then every $\sigma \in O(\varphi)$ is a product of at most $2n$ reflections τ_v in anisotropic vectors $v \in V$, where the empty product is read as id_V. In particular $O(\varphi)$ is generated by its reflections. The bound $2n$ is not the sharp one. See the discussion after the proof.

***Proof*:**

Induct on n. For $n = 0$ the group $O(\varphi)$ is trivial and id_V is the empty product. Let $n \geq 1$ and assume the statement for nondegenerate forms on spaces of dimension $n - 1$.

First, V contains an anisotropic vector: if $q(x) = 0$ for every $x \in V$, then for all $x, y \in V$

$$0 = q(x + y) = q(x) + 2\varphi(x, y) + q(y) = 2\varphi(x, y)$$

and $\operatorname{char} k \neq 2$ makes φ the zero form, so $\operatorname{rad}(\varphi) = V \neq 0$, contradicting nondegeneracy. Fix such a u, with $q(u) \neq 0$.

Let $\sigma \in O(\varphi)$. Then $q(\sigma(u)) = q(u) \neq 0$, so lemma 22.5.5, applied to the pair $\sigma(u)$ and u, gives $\pi \in O(\varphi)$ with $\pi(\sigma(u)) = u$ and π a product of at most two reflections. Put $\rho = \pi \circ \sigma$, so $\rho(u) = u$.

Set $V_1 = \{u\}^{\perp}$. As in the proof of theorem 22.5.9, $V = ku \oplus V_1$ with $\varphi(u, V_1) = 0$ by lemma 22.5.3(1), $\dim V_1 = n - 1$, and $\varphi|_{V_1}$ is nondegenerate because a vector of V_1 orthogonal to V_1 is also orthogonal to u, hence to V, hence zero. Moreover $\rho(V_1) = V_1$: for $y \in V_1$, $\varphi(u, \rho(y)) = \varphi(\rho(u), \rho(y)) = \varphi(u, y) = 0$, so $\rho(V_1) \subseteq V_1$, and ρ is injective, so the inclusion is an equality by dimension count.

By the inductive hypothesis $\rho|_{V_1}$ is a product $\tau_{v_1}^{V_1} \cdots \tau_{v_r}^{V_1}$ of $r \leq 2(n-1)$ reflections of $(V_1, \varphi|_{V_1})$, with each $v_i \in V_1$ anisotropic. Each v_i is anisotropic in V as well, and the reflection τ_{v_i} of V satisfies $\tau_{v_i}(u) = u$, since $\varphi(v_i, u) = 0$, and restricts on V_1 to $\tau_{v_i}^{V_1}$, the defining formula being the same. Hence $\tau_{v_1} \cdots \tau_{v_r}$ and ρ agree on u and on V_1, so they agree on $V = ku \oplus V_1$, and ρ is a product of at most $2(n-1)$ reflections of V.

Finally $\sigma = \pi^{-1} \circ \rho$, and π^{-1} is a product of at most two reflections, since each reflection is its own inverse by lemma 22.5.3(3) and the inverse of $\tau_v \tau_w$ is $\tau_w \tau_v$. So σ is a product of at most $2 + 2(n-1) = 2n$ reflections, as we sought to show.

The sharp form of this count is the Cartan-Dieudonné theorem, proved in Artin's *Geometric Algebra*: over a field of characteristic other than 2, every isometry of an n-dimensional nondegenerate space is a product of at most n reflections. The bound proved above loses a factor of two at Case 2 of lemma 22.5.5, where two reflections are used in place of one. Recovering the sharp bound requires a separate analysis of the isometries σ for which $q(x - \sigma(x)) = 0$ for every $x \in V$, so that no single reflection returns $\sigma(x)$ to x. Such isometries exist: on $H \perp H$, with the two hyperbolic bases e_1, f_1 and e_2, f_2, the map fixing e_1 and e_2 and sending $f_1 \mapsto f_1 + e_2$ and $f_2 \mapsto f_2 - e_1$ is one. For them the reflection count is governed by $\dim \operatorname{im}(\sigma - \mathrm{id}_V)$ rather than by n. That analysis is not carried out in this book.

Exercise 22.5.1

1. Let φ be a nondegenerate symmetric bilinear form on V with $\dim V = n \geq 1$ and $\operatorname{char} k \neq 2$, and let $\sigma \in O(\varphi)$. Show that if A is the matrix of φ and S the matrix of σ in one common basis, then $S^t A S = A$ (use lemma 13.3.19), and deduce $\det \sigma = \pm 1$ with the help of lemma 13.3.23. Using $\det \tau_v = -1$ from lemma 22.5.3, deduce that $SO(\varphi) := \{\sigma \in O(\varphi) \mid \det \sigma = 1\}$ is a subgroup of index exactly 2, and that the parity of the number of reflections in a factorization of σ given by corollary 22.5.10 does not depend on the factorization.

2. Let $\operatorname{char} k \neq 2$, let φ be a symmetric bilinear form on V, and let $v, w \in V$ be anisotropic. Show that $\tau_v = \tau_w$ if and only if $kv = kw$, so that $v \mapsto \tau_v$ is a bijection from the set of anisotropic lines of V onto a set of involutions in $O(\varphi)$. Then count the reflections in $O(\langle 1, 1\rangle)$ over $\mathbb{F}_5$, by listing the six lines of $\mathbb{F}_5^2$ and deciding which are anisotropic.

3. Show that the hypothesis that ψ be nondegenerate can be removed from theorem 22.5.6: for arbitrary symmetric bilinear forms over a field with $\operatorname{char} k \neq 2$, $\psi \perp \varphi_1 \cong \psi \perp \varphi_2$ implies $\varphi_1 \cong \varphi_2$. Reduce, using theorem 22.2.1, to cancelling $\langle 0\rangle$, and for that case use that an isometry carries the radical of one form onto the radical of the other, together with the description of the radical in an orthogonal basis given by proposition 22.2.2.

4. Over $k = \mathbb{Q}$, show that $\langle 1, 1\rangle$ and $\langle -1, -1\rangle$ are not isometric by asking which nonzero rationals each represents. Deduce from theorem 22.5.6 that $\langle 1, 1, 5\rangle \ncong \langle -1, -1, 5\rangle$, and check that these two forms have the same rank and the same discriminant, so that neither invariant of section 22.1 could have separated them.

5. Let φ be nondegenerate on V with $\operatorname{char} k \neq 2$, and recall the totally isotropic subspaces of definition 22.3.6. Call one *maximal* if no strictly larger subspace of V is totally isotropic. Using theorem 22.5.9, show that any two maximal totally isotropic subspaces of V have the same dimension. Then explain why lemma 22.5.5 gives nothing about isotropic vectors, by exhibiting two nonzero isotropic vectors u, w of $H \perp H$ with $q(u - w) = q(u + w) = 0$.

6. Let $\operatorname{char} k \neq 2$ and let $V = k^3$ carry the form whose matrix in the standard basis is $\operatorname{diag}(1, -1, 0)$. Show that $f\colon k(e_1 + e_2) \to V$ with $f(e_1 + e_2) = e_3$ is an injective linear map preserving the form, and that no isometry of V restricts to it. Conclude that the nondegeneracy hypothesis in theorem 22.5.9 cannot be dropped.

7. Let $\operatorname{char} k \neq 2$ and let $a \in k^\times$. Show that $\langle a, -a\rangle \cong H$, by exhibiting an isotropic vector and applying proposition 22.4.6. Then show that the isometry class of $\langle a, -a\rangle$ does not depend on a, even though the square class of a may vary.

8. Let $\operatorname{char} k \neq 2$ and let V be four-dimensional with basis e_1, f_1, e_2, f_2 and the symmetric bilinear form determined by $\varphi(e_1, f_1) = \varphi(e_2, f_2) = 1$, all other products of two basis vectors being zero, so that $V \cong H \perp H$. Define σ by $\sigma(e_i) = e_i$, $\sigma(f_1) = f_1 + e_2$ and $\sigma(f_2) = f_2 - e_1$. Show that $\sigma \in O(\varphi)$, that $x - \sigma(x)$ lies in the totally isotropic subspace spanned by e_1 and e_2 for every $x \in V$, and hence that $q(x - \sigma(x)) = 0$ for every x. Deduce that no reflection τ_v satisfies $\tau_v(\sigma(x)) = x$ for any x with $\sigma(x) \neq x$, so that Case 2 of lemma 22.5.5 is unavoidable for this σ.

22.6 The Witt Group

Theorem 22.4.8 writes a nondegenerate form as an anisotropic form orthogonal to a number of hyperbolic planes, and corollary 22.5.7 says that the anisotropic part is determined up to isometry. Two forms with isometric anisotropic parts therefore differ only in how many hyperbolic planes are attached to them, and this section discards that number. What remains is an abelian group under $\perp$, and a commutative ring once the tensor product of forms is available.

The construction needs no group completion. The inverse of a class is again the class of a form, because $\varphi \perp (-\varphi)$ is a sum of hyperbolic planes, and that computation is the first item below. The group is then computed for the two families of fields whose square classes are known: the algebraically closed fields, where it has two elements, and the finite fields, where it has four. The finite case answers the question left open at the end of example 22.2.5.

Throughout, k is a field with $\operatorname{char} k \neq 2$ and every form is a symmetric bilinear form on a finite-dimensional k-vector space, identified with its quadratic form through proposition 22.1.2 whenever that is convenient. The orthogonal sum $\varphi \perp \psi$ is definition 22.4.1, and everything used below about it is established there: the block-diagonal Gram matrix, the multiplicativity $\det(\varphi \perp \psi) = \det(\varphi)\det(\psi)$, that the sum is nondegenerate exactly when both summands are, and that $\perp$ descends to isometry classes and is commutative and associative up to isometry. Write $-\varphi$ for the form $(x, y) \mapsto -\varphi(x, y)$ on V. In the diagonal notation of section 22.2,

$$\langle a_1, \dots, a_m \rangle \perp \langle b_1, \dots, b_n \rangle = \langle a_1, \dots, a_m, b_1, \dots, b_n \rangle$$

and $-\langle a_1, \dots, a_n \rangle = \langle -a_1, \dots, -a_n \rangle$. Finally mH denotes the orthogonal sum of m copies of the hyperbolic plane H (definition 22.4.4), with $0H$ the zero form on the zero space.

The identification that drives everything below is that a form and its negative add up to nothing but hyperbolic planes.

Lemma 22.6.1: A Form and Its Negative Sum to Hyperbolic Planes

Let k be a field with $\operatorname{char} k \neq 2$.

1. For every $a \in k^\times$ one has $\langle a, -a \rangle \cong H$. In particular $H \cong \langle 1, -1 \rangle$, so $\det H = -1$.
2. If φ is a nondegenerate form of rank n on V, then $\varphi \perp (-\varphi) \cong nH$.

***Proof*:**

1. By example 22.4.7 a nondegenerate binary form $\langle a, b \rangle$ is a hyperbolic plane exactly when $-ab$ is a square in $k^\times$. Here $b = -a$, so $-ab = a^2$ is a square and $\langle a, -a \rangle \cong H$. Taking $a = 1$ gives $H \cong \langle 1, -1 \rangle$, whose matrix in an orthogonal basis is $\operatorname{diag}(1, -1)$, of determinant -1.
2. Diagonalize $\varphi \cong \langle a_1, \dots, a_n \rangle$ by theorem 22.2.1. Nondegeneracy forces every $a_i \neq 0$: by the last claim of proposition 22.2.2 the number of zero entries is the dimension of the radical, which is 0 here by definition 13.3.22. Then $-\varphi \cong \langle -a_1, \dots, -a_n \rangle$, so

$$\varphi \perp (-\varphi) \cong \langle a_1, \dots, a_n, -a_1, \dots, -a_n \rangle \cong \langle a_1, -a_1 \rangle \perp \cdots \perp \langle a_n, -a_n \rangle$$

the second isometry being the permutation of an orthogonal basis that places each a_i next

to its negative. Applying part (1) to each summand gives $\varphi \perp (-\varphi) \cong nH$, as we sought to show.

Every form of rank n is isometric to a form on k^n, obtained by transporting it along a choice of basis, so the isometry classes of nondegenerate forms over k constitute a set rather than a proper class. That set carries $\perp$ as a commutative associative operation with the zero form as a neutral element, and the lemma says that after hyperbolic planes are discarded every element acquires an inverse.

Definition 22.6.2: Witt Equivalence and the Witt Group

Let k be a field with $\operatorname{char} k \neq 2$. Two nondegenerate symmetric bilinear forms φ and ψ over k, possibly on spaces of different dimensions, are *Witt equivalent*, written $\varphi \sim \psi$, if there are integers $m, n \geq 0$ with

$$\varphi \perp mH \cong \psi \perp nH$$

The *Witt group* $W(k)$ is the set of equivalence classes, the class of φ being written $[\varphi]$, equipped with the operation

$$[\varphi] + [\psi] := [\varphi \perp \psi]$$

That $\sim$ is an equivalence relation and that the operation is well defined are proved in theorem 22.6.3.

Two small computations show what the relation does. Over any k one has $\langle 1 \rangle \perp \langle -1 \rangle \cong H$ by lemma 22.6.1, so $\langle 1, -1 \rangle \sim 0$: the hyperbolic plane is Witt trivial, which is the whole content of the definition. Consequently $\langle 1, 1, -1 \rangle \sim \langle 1 \rangle$, taking $m = 0$ and $n = 1$ against $\psi = \langle 1 \rangle$, since $\langle 1 \rangle \perp H \cong \langle 1, 1, -1 \rangle$. Forms of different ranks can therefore be Witt equivalent, and rank is not an invariant of a Witt class.

Theorem 22.6.3: The Witt Classes Form an Abelian Group

Let k be a field with $\operatorname{char} k \neq 2$. Witt equivalence is an equivalence relation on nondegenerate forms over k, the operation of definition 22.6.2 is well defined on classes, and $W(k)$ is an abelian group whose neutral element is the class $[0] = [H]$ of the zero form and in which $-[\varphi] = [-\varphi]$.

***Proof*:**

Step 1: $\sim$ is an equivalence relation. Reflexivity is the case $m = n = 0$, and symmetry is immediate from the symmetry of $\cong$. For transitivity, suppose $\varphi \perp mH \cong \psi \perp nH$ and $\psi \perp pH \cong \chi \perp qH$. Adding pH to the first isometry and nH to the second, which is legitimate because orthogonal sums of isometric forms are isometric, and rearranging summands by commutativity and associativity of $\perp$, gives

$$\varphi \perp (m+p)H \cong \psi \perp (n+p)H \cong \chi \perp (q+n)H$$

so $\varphi \sim \chi$.

Step 2: the operation is well defined. Let $\varphi \sim \varphi'$ and $\psi \sim \psi'$, say $\varphi \perp mH \cong \varphi' \perp m'H$ and $\psi \perp nH \cong \psi' \perp n'H$. Taking the orthogonal sum of the two isometries and rearranging summands,

$$(\varphi \perp \psi) \perp (m+n)H \cong (\varphi' \perp \psi') \perp (m'+n')H$$

so $\varphi \perp \psi \sim \varphi' \perp \psi'$. Both $\varphi \perp \psi$ and $\varphi' \perp \psi'$ are nondegenerate, since orthogonal sums of nondegenerate forms are, so the sum of two classes is again a class.

Step 3: the group axioms. Commutativity and associativity of $+$ are those of $\perp$, transported to classes by Step 2. The zero form 0 on the zero space is nondegenerate, its radical being the zero space, and $\varphi \perp 0 = \varphi$, so $[0]$ is neutral. Taking $m = 0$ and $n = 1$ in definition 22.6.2 gives $H \perp 0H \cong 0 \perp 1H$, that is $H \sim 0$, so $[H] = [0]$. Finally, if φ has rank n then $\varphi \perp (-\varphi) \cong nH$ by lemma 22.6.1, and $nH \sim 0$ directly from definition 22.6.2, taking the two integers there to be 0 and n, so

$$[\varphi] + [-\varphi] = [\varphi \perp (-\varphi)] = [nH] = [0]$$

which exhibits $[-\varphi]$ as the inverse of $[\varphi]$, completing the proof.

The group is built from forms alone: no formal differences are introduced, and no group completion of the monoid of isometry classes is taken, because the negative of a form is a form and lemma 22.6.1 makes the two cancel. What the construction has cost is the ability to see the rank, since φ and $\varphi \perp H$ have become equal. The next result says that nothing else was lost, and it is where Witt cancellation enters: cancellation plays no part in the group axioms above, and its role is to identify the classes with objects one can list.

Proposition 22.6.4: Each Witt Class Contains Exactly One Anisotropic Form

Let k be a field with $\operatorname{char} k \neq 2$ and let φ, ψ be nondegenerate forms over k, with Witt decompositions $\varphi \cong \varphi_{\mathrm{an}} \perp m_\varphi H$ and $\psi \cong \psi_{\mathrm{an}} \perp m_\psi H$ as in theorem 22.4.8. Then

$$\varphi \sim \psi \quad \text{if and only if} \quad \varphi_{\mathrm{an}} \cong \psi_{\mathrm{an}}$$

Consequently $[\varphi] \mapsto \varphi_{\mathrm{an}}$ is a bijection from $W(k)$ to the set of isometry classes of anisotropic forms over k, and $[\varphi] = 0$ if and only if $\varphi \cong m_\varphi H$.

***Proof*:**
First note that an anisotropic form is nondegenerate: a nonzero vector v of the radical satisfies $\varphi(v, v) = 0$, hence is an isotropic vector (definition 22.4.2), so the radical of an anisotropic form is zero and definition 13.3.22 applies. Both φ_{an} and ψ_{an} are therefore nondegenerate, as is H, which is what the cancellation theorem requires.

Step 1: isometric anisotropic parts give Witt equivalence. If $\varphi_{\mathrm{an}} \cong \psi_{\mathrm{an}}$ then

$$\varphi \perp m_\psi H \cong \varphi_{\mathrm{an}} \perp (m_\varphi + m_\psi)H \cong \psi_{\mathrm{an}} \perp (m_\varphi + m_\psi)H \cong \psi \perp m_\varphi H$$

so $\varphi \sim \psi$ by definition 22.6.2.

Step 2: Witt equivalence gives isometric anisotropic parts. Suppose $\varphi \perp mH \cong \psi \perp nH$. Substituting the two Witt decompositions and writing $a = m_\varphi + m$ and $b = m_\psi + n$,

$$\varphi_{\mathrm{an}} \perp aH \cong \psi_{\mathrm{an}} \perp bH$$

This is exactly the situation corollary 22.5.7 settles: two Witt decompositions of isometric forms have isometric anisotropic parts and equal hyperbolic counts. Applying it gives $a = b$ and $\varphi_{\mathrm{an}} \cong \psi_{\mathrm{an}}$.

Step 3: the two consequences. The two steps say exactly that $[\varphi] \mapsto \varphi_{\mathrm{an}}$ is well defined and injective on $W(k)$. It is surjective because an anisotropic form χ is nondegenerate with $\chi_{\mathrm{an}} = \chi$ and $m_\chi = 0$. For the last claim, $[\varphi] = [0]$ holds if and only if φ_{an} is isometric to the zero form on the zero space, that is if and only if $\varphi \cong m_\varphi H$, completing the proof.

So $W(k)$ is the set of anisotropic forms over k, given an addition that is not orthogonal sum: to add two anisotropic forms, take their orthogonal sum and discard the hyperbolic planes that appear in it. The integer m_φ discarded in the process is the Witt index of definition 22.4.10, the two agreeing by proposition 22.4.11(3), and the pair (anisotropic part, Witt index) is a complete isometry invariant of a nondegenerate form, while the class in $W(k)$ retains only the first half of that pair. The first field to compute is one over which every anisotropic form has rank at most one.

Example 22.6.5: The Witt Group of an Algebraically Closed Field

Let k be algebraically closed with $\operatorname{char} k \neq 2$. The case $k = \mathbb{C}$ is the one to keep in mind. Fix $c \in k$ with $c^2 = -1$, which exists because $x^2 + 1$ has a root.

No anisotropic form has rank 2 or more. Indeed, by example 22.2.4 a nondegenerate form of rank n is isometric to $\langle 1, \dots, 1\rangle$, and if $n \geq 2$ the vector $v = (c, 1, 0, \dots, 0)$ is nonzero and satisfies

$$q(v) = c^2 + 1 = -1 + 1 = 0$$

so the form is isotropic. The anisotropic forms are therefore the zero form and the rank one form $\langle 1\rangle$, the latter being anisotropic because $x^2 = 0$ forces $x = 0$. By proposition 22.6.4,

$$W(k) = \{\, [0],\ [\langle 1\rangle] \,\}$$

has two elements. Its group law is forced: $2[\langle 1\rangle] = [\langle 1, 1\rangle]$, and $\langle 1, 1\rangle \cong \langle 1, -1\rangle$ by proposition 22.2.2, since $-1 \cdot c^2 = 1$ rescales the second entry by the square c^2, so $\langle 1, 1\rangle \cong H$ by lemma 22.6.1 and $2[\langle 1\rangle] = 0$. Hence $W(k) \cong \mathbb{Z}/2\mathbb{Z}$, the isomorphism sending $[\varphi]$ to the rank of φ modulo 2.

Addition is not the only operation available on forms. The tensor product of the underlying spaces carries a form built from the two given ones, and it is compatible with $\perp$ and with Witt equivalence, which upgrades $W(k)$ from a group to a ring. In diagonal coordinates the operation is multiplication of the diagonal entries in all pairs, which is what makes it computable.

Proposition 22.6.6: The Tensor Product of Forms and the Witt Ring

Let k be a field with $\operatorname{char} k \neq 2$, let φ be a symmetric bilinear form on V and ψ one on W.

1. There is exactly one bilinear form $\varphi \otimes \psi$ on $V \otimes_k W$ satisfying
$$(\varphi \otimes \psi)(v \otimes w,\ v' \otimes w') = \varphi(v, v')\,\psi(w, w')$$
for all $v, v' \in V$ and $w, w' \in W$, and it is symmetric.
2. If $\varphi \cong \langle a_1, \ldots, a_m\rangle$ and $\psi \cong \langle b_1, \ldots, b_n\rangle$, then $\varphi \otimes \psi$ is isometric to the diagonal form whose mn entries are the products $a_i b_j$. In particular $\varphi \otimes \psi$ is nondegenerate when φ and ψ are, and isometric inputs produce isometric outputs.
3. The rule $[\varphi] \cdot [\psi] := [\varphi \otimes \psi]$ is well defined and makes $W(k)$ a commutative ring with identity $[\langle 1\rangle]$.

***Proof*:**

1. Fix bases $v_1, \ldots, v_m$ of V and $w_1, \ldots, w_n$ of W. By corollary 15.2.6 the mn vectors $v_i \otimes w_j$ form a basis of $V \otimes_k W$. Let M be the $mn \times mn$ matrix indexed by pairs, with entry $\varphi(v_i, v_{i'})\psi(w_j, w_{j'})$ in position $\big((i,j),(i',j')\big)$, and define $B(x,y) := [x]^t M [y]$ using coordinates in that basis. Taking coordinates is linear and matrix multiplication is bilinear in the two coordinate vectors, so B is a bilinear form.

   To see that B has the stated values, write $v = \sum_i x_i v_i$, $v' = \sum_{i'} x'_{i'} v_{i'}$, $w = \sum_j y_j w_j$ and $w' = \sum_{j'} y'_{j'} w_{j'}$. The map $(v, w) \mapsto v \otimes w$ is bilinear by theorem 15.1.12, so $v \otimes w = \sum_{i,j} x_i y_j\,(v_i \otimes w_j)$, which is the coordinate vector of $v \otimes w$ in the chosen basis. Hence
$$\begin{aligned} B(v \otimes w, v' \otimes w') &= \sum_{i,j,i',j'} x_i y_j x'_{i'} y'_{j'}\,\varphi(v_i, v_{i'})\psi(w_j, w_{j'}) \\ &= \Big(\sum_{i,i'} x_i x'_{i'} \varphi(v_i, v_{i'})\Big)\Big(\sum_{j,j'} y_j y'_{j'} \psi(w_j, w_{j'})\Big) \\ &= \varphi(v, v')\,\psi(w, w') \end{aligned}$$
   the last line by bilinearity of φ and of ψ. For uniqueness, the simple tensors span $V \otimes_k W$ by lemma 15.1.4, and two bilinear forms agreeing on all pairs of vectors from a spanning set agree everywhere, by expanding both arguments. Symmetry follows the same way: the bilinear forms $(x,y) \mapsto B(x,y)$ and $(x,y) \mapsto B(y,x)$ agree on pairs of simple tensors because φ and ψ are symmetric, hence agree.

2. Choose the bases in (1) to be orthogonal bases realizing the two diagonalizations, which exist by theorem 22.2.1, so that $\varphi(v_i, v_{i'}) = 0$ for $i \neq i'$ with $\varphi(v_i, v_i) = a_i$, and likewise for ψ. Then for $(i,j) \neq (i',j')$,
$$(\varphi \otimes \psi)(v_i \otimes w_j,\ v_{i'} \otimes w_{j'}) = \varphi(v_i, v_{i'})\psi(w_j, w_{j'}) = 0$$
   since at least one of the two factors has distinct indices, while the value at $(i,j) = (i',j')$ is $a_i b_j$. So the basis $\{v_i \otimes w_j\}$ is orthogonal for $\varphi \otimes \psi$ with the mn diagonal entries $a_i b_j$,

which is the claim. If all a_i and all b_j are nonzero then so are all a_ib_j, so the matrix of $\varphi\otimes\psi$ in this basis is diagonal with nonzero entries, hence invertible, and lemma 13.3.23 gives nondegeneracy. Finally, if $\varphi' \cong \varphi$ and $\psi' \cong \psi$, then $\varphi' \cong \langle a_1,\dots,a_m\rangle$ and $\psi' \cong \langle b_1,\dots,b_n\rangle$ for the very same entries, since the diagonal notation asserts an isometry class and not a chosen basis. Running the argument just given for those diagonalizations exhibits $\varphi'\otimes\psi'$ and $\varphi\otimes\psi$ as isometric to one and the same diagonal form, so isometric inputs produce isometric outputs. The multiset $\{a_ib_j\}$ is not itself an invariant of the pair of isometry classes, being pinned down only up to multiplying its entries by squares, but the isometry class it names is.

3. Write $\varphi \cong \langle a_1,\dots,a_m\rangle$, $\psi \cong \langle b_1,\dots,b_n\rangle$ and $\chi \cong \langle c_1,\dots,c_p\rangle$, all nondegenerate. By (2) the products a_ib_j and b_ja_i agree, giving $\varphi\otimes\psi \cong \psi\otimes\varphi$; the products $(a_ib_j)c_l$ and $a_i(b_jc_l)$ agree, giving associativity; the entries of $\varphi\otimes(\psi\perp\chi)$ are the a_ib_j together with the a_ic_l, which are the entries of $(\varphi\otimes\psi)\perp(\varphi\otimes\chi)$, giving distributivity over $\perp$; and $\langle 1\rangle\otimes\varphi\cong\varphi$ because the products $1\cdot a_i$ are the a_i.

   It remains to check that the rule respects Witt equivalence. First, $\langle a\rangle\otimes H \cong \langle a\rangle\otimes\langle 1,-1\rangle \cong \langle a,-a\rangle \cong H$, using lemma 22.6.1 at both ends and (2) in the middle, so by distributivity

$$\psi\otimes H \cong (\langle b_1\rangle\otimes H)\perp\cdots\perp(\langle b_n\rangle\otimes H)\cong nH$$

   Now suppose $\varphi\sim\varphi'$, say $\varphi\perp pH\cong\varphi'\perp p'H$. Tensoring with ψ and using that isometric inputs give isometric outputs, then expanding by distributivity and the previous display,

$$(\varphi\otimes\psi)\perp pnH \cong (\varphi'\otimes\psi)\perp p'nH$$

   so $\varphi\otimes\psi\sim\varphi'\otimes\psi$. Commutativity gives the same conclusion in the second variable, so the product of two classes does not depend on the representatives. The ring axioms are the isometries established in the previous paragraph, read on classes, completing the proof.

$W(k)$ is called the *Witt ring* when the multiplication is in play, and the group and the ring have the same underlying set. The multiplication restricts usefully to rank one forms: $\langle a\rangle\otimes\langle b\rangle\cong\langle ab\rangle$ by part (2), so the square classes of k act on $W(k)$ through $[\langle a\rangle]$, and each $[\langle a\rangle]$ is a unit since $\langle a\rangle\otimes\langle a\rangle\cong\langle a^2\rangle\cong\langle 1\rangle$ by proposition 22.2.2.

Two invariants from section 22.1 can now be tested against Witt equivalence. Rank fails, as the computation after definition 22.6.2 shows, but rank modulo 2 survives because a hyperbolic plane has rank 2. The discriminant also fails, and for a reason worth isolating: $\det(\varphi\perp H) = -\det(\varphi)$ by lemma 22.6.1(1), so $\operatorname{disc}(\varphi\perp H)$ and $\operatorname{disc}(\varphi)$ differ by the class of -1, which is nontrivial in most fields. A sign attached to the determinant repairs this, and box 22.1.9 announced it.

Definition 22.6.7: The Signed Discriminant

Let φ be a nondegenerate symmetric bilinear form of rank n over a field k with $\operatorname{char} k \neq 2$. The *signed discriminant* of φ is the square class

$$d_{\pm}(\varphi) := (-1)^{n(n-1)/2}\operatorname{disc}(\varphi) \in k^\times/(k^\times)^2$$

with disc as in definition 22.1.7. For $n=0$ the determinant of the empty matrix is 1, so $d_\pm$ of the zero form is the trivial class.

The definition depends on nothing but the isometry class of φ, since the rank does not and disc does not by proposition 22.1.8. For a diagonal form the sign multiplies the product of the entries: $d_\pm\langle a_1,\dots,a_n\rangle = (-1)^{n(n-1)/2}a_1\cdots a_n$ modulo squares, by corollary 22.2.3. Thus $d_\pm\langle a\rangle = a$, $d_\pm\langle a,b\rangle = -ab$ and $d_\pm\langle a,b,c\rangle = -abc$.

Proposition 22.6.8: Rank Modulo Two and the Signed Discriminant Are Witt Invariants

Let k be a field with $\operatorname{char} k \neq 2$.

1. The assignment $e\big([\varphi]\big) := \dim\varphi + 2\mathbb{Z}$ is a well defined surjective ring homomorphism $e\colon W(k) \to \mathbb{Z}/2\mathbb{Z}$.
2. For nondegenerate φ of rank m and ψ of rank n,
$$d_\pm(\varphi\perp\psi) = (-1)^{mn}\, d_\pm(\varphi)\, d_\pm(\psi)$$
3. Witt equivalent forms have equal signed discriminants, so $d_\pm$ is a well defined map $W(k) \to k^\times/(k^\times)^2$.
4. Restricted to the classes of even rank, $d_\pm$ is a group homomorphism from $\big(\ker e, +\big)$ to $k^\times/(k^\times)^2$.

***Proof*:**

1. If $\varphi \perp mH \cong \psi \perp nH$ then comparing dimensions gives $\dim\varphi + 2m = \dim\psi + 2n$, so $\dim\varphi \equiv \dim\psi \pmod 2$ and e is well defined. It is additive because $\dim(\varphi\perp\psi) = \dim\varphi + \dim\psi$, and multiplicative because $\dim(V\otimes_k W) = \dim V\cdot\dim W$ by corollary 15.2.6. It sends the identity $[\langle 1\rangle]$ to $1+2\mathbb{Z}$, which also gives surjectivity.
2. Both sides are computed from determinants and ranks. The rank of $\varphi\perp\psi$ is $m+n$ and its determinant is $\det(\varphi)\det(\psi)$, by the block form recorded at the start of this section. So the two sides differ only in the power of -1, and
$$\frac{(m+n)(m+n-1)}{2} - \frac{m(m-1)}{2} - \frac{n(n-1)}{2} = \frac{2mn}{2} = mn$$
after expanding the numerator as $m^2+2mn+n^2-m-n-m^2+m-n^2+n$. Raising -1 to that difference gives the stated factor.
3. By lemma 22.6.1(1) the hyperbolic plane has rank 2 and determinant -1, so $d_\pm(H) = (-1)^{2(2-1)/2}\cdot(-1) = (-1)(-1) = 1$ in $k^\times/(k^\times)^2$. Applying (2) with $\psi = H$, where $n=2$ makes $(-1)^{mn} = 1$,
$$d_\pm(\varphi\perp H) = d_\pm(\varphi)\, d_\pm(H) = d_\pm(\varphi)$$
Iterating, $d_\pm(\varphi\perp mH) = d_\pm(\varphi)$ for every $m\geq 0$. Now if $\varphi\perp mH\cong\psi\perp nH$, then the two sides have equal rank and equal discriminant, the latter by proposition 22.1.8, hence equal signed discriminant. Combining the three equalities gives $d_\pm(\varphi) = d_\pm(\psi)$.
4. If m and n are both even then $(-1)^{mn} = 1$, so (2) reads $d_\pm(\varphi\perp\psi) = d_\pm(\varphi)d_\pm(\psi)$. Since addition in $W(k)$ is induced by $\perp$ and the target group is written multiplicatively, this is the homomorphism property on $\ker e$, as we sought to show.

The restriction in (4) is not an artifact of the proof. Over $\mathbb{Q}$ one has $d_\pm\langle 1\rangle = 1$ while $d_\pm\big(\langle 1\rangle \perp \langle 1\rangle\big) = d_\pm\langle 1,1\rangle = -1$, and -1 is not a square in $\mathbb{Q}$, so $d_\pm$ is not additive on all of $W(\mathbb{Q})$. The subgroup where it is additive has a name.

Definition 22.6.9: The Fundamental Ideal

Let k be a field with $\operatorname{char} k \neq 2$. The *fundamental ideal* of $W(k)$ is

$$I(k) := \ker\big(e\colon W(k) \to \mathbb{Z}/2\mathbb{Z}\big)$$

the set of Witt classes of even rank. It is an ideal of the Witt ring, being the kernel of the ring homomorphism of proposition 22.6.8(1), and $W(k)/I(k) \cong \mathbb{Z}/2\mathbb{Z}$.

The classes $[\langle 1, -a\rangle]$ for $a \in k^\times$ lie in $I(k)$ and have signed discriminant $-1\cdot(1\cdot(-a)) = a$, so $d_\pm$ maps $I(k)$ onto the whole square class group. Rank modulo 2 and the signed discriminant are thus two homomorphisms out of $W(k)$ and out of $I(k)$ respectively, and over a finite field they turn out to separate every class from every other.

Proposition 22.6.10: Rank and Discriminant Classify Forms over a Finite Field

Let q be an odd prime power and fix a non-square $\epsilon \in \mathbb{F}_q^\times$.

1. For all $a, b \in \mathbb{F}_q^\times$ and all $c \in \mathbb{F}_q$ there exist $x, y \in \mathbb{F}_q$ with $ax^2 + by^2 = c$.
2. Every nondegenerate form over $\mathbb{F}_q$ of rank at least 3 is isotropic, and every nondegenerate form of rank at least 2 represents every element of $\mathbb{F}_q^\times$.
3. Two nondegenerate forms over $\mathbb{F}_q$ are isometric if and only if they have the same rank and the same discriminant.
4. Up to isometry the anisotropic forms over $\mathbb{F}_q$ are exactly the zero form, $\langle 1\rangle$, $\langle \epsilon\rangle$ and $\langle 1, -\epsilon\rangle$.

***Proof*:**

1. This is proved in example 22.4.9, by the counting argument on $S = \{ax^2 \mid x \in \mathbb{F}_q\}$ and $T = \{c - by^2 \mid y \in \mathbb{F}_q\}$, each of size $(q+1)/2$ in a set of size q.
2. The first claim is example 22.4.9, which deduces it from (1). For the second, let φ be nondegenerate of rank $n \geq 2$ and diagonalize it by theorem 22.2.1 as $\varphi \cong \langle a_1, \dots, a_n\rangle$ in an orthogonal basis $w_1, \dots, w_n$, every a_i being nonzero by the last claim of proposition 22.2.2. Given $c \in \mathbb{F}_q^\times$, part (1) gives $x, y \in \mathbb{F}_q$ with $a_1x^2 + a_2y^2 = c$. Put $v := xw_1 + yw_2$. Then $q(v) = a_1x^2 + a_2y^2 = c$, which is nonzero, so $v \neq 0$ and φ represents c.
3. Isometric forms have the same rank and, by proposition 22.1.8, the same discriminant. For the converse, induct on the common rank n. For $n = 0$ both forms are the zero form on the zero space. For $n = 1$, write $\varphi \cong \langle a\rangle$ and $\psi \cong \langle b\rangle$. Equality of the discriminants means $b = ac^2$ for some $c \in \mathbb{F}_q^\times$ by corollary 22.2.3 and definition 22.1.6, and then $\langle a\rangle \cong \langle b\rangle$ by proposition 22.2.2.

   Let $n \geq 2$. Diagonalizing φ produces a vector v with $c := \varphi(v,v) \neq 0$, and by (2) the form

ψ also represents c, say $\psi(v', v') = c$. A vector of nonzero square splits off: for x in the space of φ,

$$x = \frac{\varphi(v,x)}{c}\, v + \left(x - \frac{\varphi(v,x)}{c}\, v \right)$$

where applying $\varphi(v, -)$ to the bracket gives $\varphi(v,x) - \frac{\varphi(v,x)}{c} c = 0$, so the bracket lies in $\{v\}^\perp$ (definition 13.3.20), a subspace by lemma 13.3.21. And if $\lambda v \in \{v\}^\perp$ then $\lambda c = 0$, so $\lambda = 0$. Hence the space is the direct sum of kv and $\{v\}^\perp$, these are orthogonal, and $\varphi \cong \langle c \rangle \perp \varphi'$ with φ' the restriction to $\{v\}^\perp$. The same argument gives $\psi \cong \langle c \rangle \perp \psi'$. Both φ' and ψ' have rank $n-1$ and are nondegenerate, since $c \det(\varphi') = \det(\varphi) \neq 0$ and likewise for ψ. Their discriminants agree: in the square class group, $\operatorname{disc}(\varphi') = c^{-1} \operatorname{disc}(\varphi) = c^{-1} \operatorname{disc}(\psi) = \operatorname{disc}(\psi')$. By the inductive hypothesis $\varphi' \cong \psi'$, and taking the orthogonal sum with the identity of $\langle c \rangle$ gives $\varphi \cong \psi$.

4. An anisotropic form has rank at most 2 by (2). The zero form is anisotropic vacuously. In rank 1, every $\langle a \rangle$ is anisotropic, and by (3) the isometry class is determined by the discriminant, which is the class of a. The two square classes of $\mathbb{F}_q$ are those of 1 and ϵ by example 22.2.5. In rank 2, the form $\langle a, b \rangle$ is isotropic exactly when $-ab$ is a square: given $ax^2 + by^2 = 0$ with $(x, y) \neq (0, 0)$, the case $y = 0$ would force $ax^2 = 0$ and hence $x = 0$, so $y \neq 0$ and $-ab = a^2(x/y)^2$ is a square. Conversely if $-ab = t^2$ then $(x, y) = (t, a)$ is nonzero and $at^2 + ba^2 = a(t^2 + ab) = 0$. So $\langle a, b \rangle$ is anisotropic exactly when $-ab$ is a non-square, that is when $\operatorname{disc}\langle a, b \rangle = ab$ is the class of $-\epsilon$. By (3) that single condition on the discriminant pins down one isometry class in rank 2, and $\langle 1, -\epsilon \rangle$ is in it, completing the proof.

Part (3) is the affirmative answer promised at the end of example 22.2.5: over $\mathbb{F}_q$ the rank and the discriminant are a complete system of invariants, so the two forms $\langle 1, 1 \rangle$ and $\langle 1, 2 \rangle$ exhibited there over $\mathbb{F}_5$ fail to be isometric for the only reason available. Part (4) turns proposition 22.6.4 into a count.

Example 22.6.11: The Witt Group of a Finite Field

Let q be odd and $\epsilon \in \mathbb{F}_q^\times$ a non-square. By proposition 22.6.4 the elements of $W(\mathbb{F}_q)$ correspond to isometry classes of anisotropic forms, and proposition 22.6.10(4) lists four of them, so

$$W(\mathbb{F}_q) = \{\, [0],\ [\langle 1 \rangle],\ [\langle \epsilon \rangle],\ [\langle 1, -\epsilon \rangle] \,\}$$

has exactly four elements. Which group of order four it is depends on q modulo 4, through whether -1 is a square.

The case $q \equiv 1 \pmod 4$. Then -1 is a square, say $-1 = c^2$: the group $\mathbb{F}_q^\times$ is cyclic by theorem 11.3.14, of order $q - 1$, which is divisible by 4 in this case, so it has an element of order 4, whose square has order 2 and hence equals -1, the unique element of order 2. For any $a \in \mathbb{F}_q^\times$, proposition 22.2.2 gives $\langle a \rangle \cong \langle ac^2 \rangle = \langle -a \rangle$, so every form satisfies $\varphi \cong -\varphi$ after diagonalizing, and

$$2[\varphi] = [\varphi] + [-\varphi] = 0$$

by theorem 22.6.3. A group of order 4 in which every element has order dividing 2 is $\mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z}$.

The case $q \equiv 3 \pmod 4$. Then -1 is a non-square, so $\epsilon = -1$ is an admissible choice, and $\langle 1, 1 \rangle$ is anisotropic by the criterion in the proof of proposition 22.6.10(4), since $-1 \cdot 1 = -1$ is a non-square. Hence $2[\langle 1 \rangle] = [\langle 1, 1 \rangle] \neq 0$ by proposition 22.6.4. On the other hand $\langle 1, 1, 1, 1 \rangle$ and

$2H \cong \langle 1,-1,1,-1\rangle$ both have rank 4 and discriminant the class of 1, so they are isometric by proposition 22.6.10(3), giving $4[\langle 1\rangle] = [2H] = 0$. So $[\langle 1\rangle]$ has order 4 in a group of order 4, and $W(\mathbb{F}_q) \cong \mathbb{Z}/4\mathbb{Z}$.

The invariants separate the four classes. Writing each class through its anisotropic representative and applying proposition 22.6.8, the rank modulo 2 and the signed discriminant take the values

	$[0]$	$[\langle 1\rangle]$	$[\langle \epsilon\rangle]$	$[\langle 1,-\epsilon\rangle]$
e	0	1	1	0
$d_\pm$	1	1	ϵ	ϵ

the last entry because $d_\pm\langle 1,-\epsilon\rangle = -(1\cdot(-\epsilon)) = \epsilon$. The four pairs are distinct, so a Witt class over a finite field is determined by its rank modulo 2 together with its signed discriminant.

A worked instance. Take $q = 5$. The squares in $\mathbb{F}_5^\times$ are 1 and 4, so $\epsilon = 2$ is a non-square and $-1 = 4 = 2^2$ is a square, putting this in the first case: $W(\mathbb{F}_5) \cong \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z}$, with anisotropic representatives 0, $\langle 1\rangle$, $\langle 2\rangle$ and $\langle 1,-2\rangle = \langle 1,3\rangle$. The two forms of example 22.2.5 land in different classes: $\langle 1,1\rangle \cong \langle 1,-1\rangle \cong H$ is Witt trivial, while $[\langle 1,2\rangle] = [\langle 1\rangle] + [\langle 2\rangle]$ has signed discriminant $-2 = 3$, a non-square, so it is not the class of 0.

Exercise 22.6.1

1. Take $k = \mathbb{F}_7$. List the square classes, determine the four anisotropic forms over $\mathbb{F}_7$ up to isometry, and identify $W(\mathbb{F}_7)$ as an abstract group. Which of the four classes is $3[\langle 1\rangle]$?

2. Let $\operatorname{char} k \neq 2$ and let φ be nondegenerate over k. Show that $[\varphi] = 0$ in $W(k)$ if and only if $\varphi \cong mH$ for some $m \geq 0$, and deduce that a nondegenerate form of odd rank is never Witt trivial. Conclude that $W(k)$ has at least two elements for every such k.

3. Let φ and ψ be nondegenerate forms over k with $[\varphi] = [\psi]$ and $\dim\varphi = \dim\psi$. Show that $\varphi \cong \psi$. Give an example over some field showing that the hypothesis on the dimensions cannot be dropped.

4. Suppose -1 is a square in k, where $\operatorname{char} k \neq 2$. Show that $\varphi \cong -\varphi$ for every form over k, hence that $2[\varphi] = 0$ for every $[\varphi] \in W(k)$, so that $W(k)$ is a vector space over $\mathbb{F}_2$. Check that example 22.6.5 is an instance.

5. Show that $a \mapsto [\langle a\rangle]$ induces a well defined group homomorphism from $k^\times/(k^\times)^2$ to the group of units of the Witt ring, and that it is injective for every field k with $\operatorname{char} k \neq 2$. (For injectivity, identify the anisotropic part of $\langle a\rangle$.)

6. Show that $d_\pm\colon I(k) \to k^\times/(k^\times)^2$ is surjective for every k with $\operatorname{char} k \neq 2$. Then compute $I(\mathbb{F}_q)$ for q odd and show that $d_\pm$ is an isomorphism of groups $I(\mathbb{F}_q) \xrightarrow{\sim} \mathbb{F}_q^\times/(\mathbb{F}_q^\times)^2$.

7. Show that $I(k)$ is generated as an abelian group by the classes $[\langle 1,-a\rangle]$ with a ranging over $k^\times$. (Start by expressing $[\langle a\rangle] - [\langle 1\rangle]$ as one of these generators up to sign.)

8. Show that the form $\langle 1,1,\dots,1\rangle$ of rank n is anisotropic over $\mathbb{Q}$ for every n, and deduce that the classes $n[\langle 1\rangle]$ for $n \geq 0$ are pairwise distinct, so that $W(\mathbb{Q})$ is infinite and $[\langle 1\rangle]$ has infinite order. Contrast this with example 22.6.11.

22.7 The Clifford Algebra

Every construction so far has compared one form with another. This section attaches to a single form an associative algebra, built so that the form becomes the operation of squaring: inside it the equation $v^2 = q(v)$ holds for every $v \in V$. That equation is meaningless in V, where there is no product, so the object carrying it must be an algebra containing V, and section 16.3 is where algebras containing a given vector space are constructed.

The construction below is a quotient of $\mathcal{T}(V)$ by one family of relations, and for $q = 0$ it is the exterior algebra. What is proved here is that the quotient has dimension 2^n rather than collapsing, that maps out of it are prescribed by their restriction to V, and that although the $\mathbb{Z}$-grading of $\mathcal{T}(V)$ does not survive, its reduction modulo 2 does.

Definition 16.3.7 formed $\bigwedge(V)$ by killing the elements $v \otimes v$ of $\mathcal{T}(V)$, which forces $v^2 = 0$ in the quotient. Killing $v \otimes v - q(v)$ instead forces $v^2 = q(v)$. Assume $q \neq 0$ and choose v with $q(v) \neq 0$. The element $v \otimes v - q(v)$ is then a sum of a nonzero term of degree 2 and a nonzero term of degree 0, so it is not homogeneous, and the ideal generated by these elements is not a graded ideal in the sense of definition 16.2.3: were it graded, the two homogeneous components of $v \otimes v - q(v)$ would lie in it separately, so the invertible scalar $q(v)$, and with it 1, would lie in it and the quotient would be 0, contradicting theorem 22.7.5. For $q \neq 0$ the images of the $\mathcal{T}^d(V)$ therefore do not make the quotient a graded ring (definition 16.2.1). Only in the excluded case $q = 0$, where the ideal is the one of definition 16.3.7 and is graded, does the $\mathbb{Z}$-grading survive (example 22.7.2). Proposition 22.7.7 says exactly how much of the grading is left in general.

Definition 22.7.1: Clifford Algebra

Let k be a field with $\operatorname{char} k \neq 2$, let V be a finite-dimensional k-vector space, and let q be a quadratic form on V (definition 22.1.1). Let $I(q) \subseteq \mathcal{T}(V)$ be the two-sided ideal of the tensor algebra (definition 16.3.1) generated by the elements

$$v \otimes v - q(v) \cdot 1 \qquad (v \in V)$$

where $q(v) \cdot 1$ lies in $\mathcal{T}^0(V) = k$. The *Clifford algebra* of q is the quotient k-algebra

$$C(q) := \mathcal{T}(V)/I(q)$$

and $\iota \colon V \to C(q)$ denotes the composite of the inclusion $V = \mathcal{T}^1(V) \subseteq \mathcal{T}(V)$ with the projection $\pi \colon \mathcal{T}(V) \to C(q)$.

Write φ for the symmetric bilinear form attached to q by proposition 22.1.2, so that $\varphi(v, v) = q(v)$. Two identities in $C(q)$ are used in everything below. The first is the defining relation

$$\iota(v)^2 = q(v)$$

which holds because π is an algebra homomorphism, so that $\iota(v)^2 = \pi(v \otimes v) = \pi\big(q(v) \cdot 1\big) = q(v)$, the middle equality holding because the two arguments differ by a generator of $I(q)$. The second identity is obtained by applying the first to $v + w$. Bilinearity of φ gives $q(v + w) = \varphi(v + w, v + w) = q(v) + 2\varphi(v, w) + q(w)$, while expanding the square in $C(q)$ gives

$$\iota(v + w)^2 = \big(\iota(v) + \iota(w)\big)^2 = \iota(v)^2 + \iota(v)\iota(w) + \iota(w)\iota(v) + \iota(w)^2$$

using that ι is linear. Equating the two and cancelling $\iota(v)^2 = q(v)$ and $\iota(w)^2 = q(w)$ leaves

$$\iota(v)\iota(w) + \iota(w)\iota(v) = 2\varphi(v, w) \tag{22.3}$$

Since $\operatorname{char} k \neq 2$, the right-hand side vanishes exactly when v and w are orthogonal (definition 13.3.20), so orthogonality of vectors becomes anticommutation of their images. This is the mechanism that turns a choice of orthogonal basis, which theorem 22.2.1 always gives, into a presentation of $C(q)$ by generators and relations.

Example 22.7.2: The Clifford Algebra of the Zero Form

Let k be a field with $\operatorname{char} k \neq 2$ and take $q = 0$ on a k-vector space V of dimension n. The generators of $I(0)$ are the elements $v \otimes v - 0 = v \otimes v$ for $v \in V$, which are precisely the generators of the ideal $\mathcal{A}(V)$ of definition 16.3.7. The two ideals therefore coincide, and

$$C(0) = \mathcal{T}(V)/\mathcal{A}(V) = \bigwedge(V)$$

not merely up to isomorphism but as the same quotient. Its dimension is

$$\dim_k \bigwedge(V) = \sum_{r=0}^{n} \binom{n}{r} = 2^n$$

since $\bigwedge^r(V)$ is free of rank $\binom{n}{r}$ by theorem 16.4.3 and vanishes for $r > n$. Note that nothing in definition 22.7.1 asked q to be nondegenerate, and for $V \neq 0$ the zero form has radical all of V.

The definition determines the algebra but leaves two questions open: how large it is, and how to produce a homomorphism out of it. The second is answered first, and the answer then gives the first, because the way to bound the dimension of $C(q)$ from below is to map it onto something of known dimension.

Proposition 22.7.3: The Universal Property of the Clifford Algebra

Let k be a field with $\operatorname{char} k \neq 2$, let V be a finite-dimensional k-vector space, and let q be a quadratic form on V.

1. For every k-algebra A and every k-linear map $f\colon V \to A$ satisfying $f(v)^2 = q(v) \cdot 1_A$ for all $v \in V$, there is a unique k-algebra homomorphism $F\colon C(q) \to A$ with $F \circ \iota = f$.
2. Let q' be a quadratic form on V', with associated symmetric bilinear forms φ and φ', and let $g\colon (V, \varphi) \to (V', \varphi')$ be an isometry (definition 22.1.10). Then there is a unique k-algebra isomorphism $C(g)\colon C(q) \to C(q')$ with $C(g)\big(\iota(v)\big) = \iota'\big(g(v)\big)$ for all $v \in V$. In particular isometric forms have isomorphic Clifford algebras.

***Proof*:**

1. *Existence.* Take $R = k$ and $M = V$ in theorem 16.3.2(2): its hypotheses ask for a k-algebra and a k-module homomorphism from V into it, which are A and f. So it gives a unique k-algebra homomorphism $\Psi\colon \mathcal{T}(V) \to A$ with $\Psi|_V = f$. On a generator of $I(q)$,

$$\Psi\big(v \otimes v - q(v) \cdot 1\big) = \Psi(v)\Psi(v) - q(v)\Psi(1) = f(v)^2 - q(v) \cdot 1_A = 0$$

by the hypothesis on f. Every element of $I(q)$ is a finite sum of products $x\gamma y$ with $x, y \in \mathcal{T}(V)$ and γ one of those generators, and $\Psi(x\gamma y) = \Psi(x)\Psi(\gamma)\Psi(y) = 0$, so $I(q) \subseteq \ker \Psi$. Hence

$$F\big(x + I(q)\big) := \Psi(x)$$

is well defined: two representatives of the same class differ by an element of $I(q)$, on which Ψ vanishes. It is k-linear, multiplicative and unital because Ψ is and because $\pi\colon \mathcal{T}(V) \to C(q)$ is a surjective algebra homomorphism with $F \circ \pi = \Psi$. Finally $F \circ \iota = \Psi|_V = f$.

Uniqueness. The algebra $C(q)$ is generated as a k-algebra by $\iota(V)$: the simple tensors $v_1 \otimes \cdots \otimes v_m$ generate $\mathcal{T}^m(V)$ as a k-module by lemma 15.1.4, hence together with 1 they span $\mathcal{T}(V)$, and π is surjective and sends $v_1 \otimes \cdots \otimes v_m$ to $\iota(v_1)\cdots\iota(v_m)$. Now if F_1, F_2 are algebra homomorphisms out of $C(q)$ agreeing on $\iota(V)$, the set on which they agree is closed under sums, products and scalars and contains 1, so it is a subalgebra containing a generating set, hence all of $C(q)$. So F is unique.

2. An isometry satisfies $\varphi'(g(v), g(v)) = \varphi(v, v)$, that is $q'(g(v)) = q(v)$. So the k-linear map $f := \iota' \circ g\colon V \to C(q')$ satisfies

$$f(v)^2 = \iota'\big(g(v)\big)^2 = q'\big(g(v)\big) = q(v)$$

and part (1) gives a unique algebra homomorphism $C(g)$ with $C(g) \circ \iota = \iota' \circ g$. The inverse map g^{-1} is again an isometry, since applying $\varphi'(g(-), g(-)) = \varphi(-,-)$ to the vectors $g^{-1}(x), g^{-1}(y)$ gives $\varphi'(x, y) = \varphi(g^{-1}x, g^{-1}y)$, so the same construction produces $C(g^{-1})\colon C(q') \to C(q)$. The composite $C(g^{-1}) \circ C(g)$ is an algebra homomorphism $C(q) \to C(q)$ carrying $\iota(v)$ to $\iota(g^{-1}g(v)) = \iota(v)$, and the identity of $C(q)$ carries $\iota(v)$ to $\iota(v)$ as well. Both therefore solve the problem of part (1) for $A = C(q)$ and $f = \iota$, whose hypothesis $\iota(v)^2 = q(v)$ holds, so uniqueness forces $C(g^{-1}) \circ C(g) = \mathrm{id}_{C(q)}$. Exchanging the roles of g and g^{-1} gives $C(g) \circ C(g^{-1}) = \mathrm{id}_{C(q')}$, so $C(g)$ is an isomorphism, completing the proof.

Part (1) is the statement that prescribing an algebra homomorphism out of $C(q)$ costs exactly one k-linear map $V \to A$ whose values square to the scalars $q(v)$. The relations impose nothing further. Part (2) is what makes $C(q)$ an invariant of the isometry class rather than of a chosen presentation, so it may be computed from any convenient diagonalization $\langle a_1, \ldots, a_n\rangle$ produced by theorem 22.2.1. The smallest case already shows that the answer depends on the field.

Example 22.7.4: Clifford Algebras of a Line

Let k be a field with $\operatorname{char} k \neq 2$, let $\dim_k V = 1$, say $V = kv$, and let $a := q(v)$, so that $q \cong \langle a\rangle$. Then

$$C(q) \cong k[x]/(x^2 - a)$$

To see this, write $A := k[x]/(x^2 - a)$ and let $\bar{x}$ be the class of x. The map $f\colon V \to A$ sending $\lambda v \mapsto \lambda\bar{x}$ is k-linear, and $f(\lambda v)^2 = \lambda^2\bar{x}^2 = \lambda^2 a = q(\lambda v)$ by definition 22.1.1(1), so proposition 22.7.3(1) gives an algebra homomorphism $F\colon C(q) \to A$ with $F(\iota(v)) = \bar{x}$. In the other direction, evaluation at $\iota(v)$ is an algebra homomorphism $k[x] \to C(q)$, since the powers of $\iota(v)$ commute with one another and k is central in $C(q)$. It kills $x^2 - a$ because $\iota(v)^2 = q(v) = a$, so it factors through a homomorphism $G\colon A \to C(q)$ with $G(\bar{x}) = \iota(v)$. Now $F \circ G$ is an algebra endomorphism of A fixing $\bar{x}$, and the elements it fixes form a subalgebra, which therefore contains the algebra

generated by $\bar{x}$, namely all of A. So $F \circ G = \mathrm{id}_A$. Likewise $G \circ F$ is an algebra endomorphism of $C(q)$ fixing $\iota(V)$ pointwise, hence equals $\mathrm{id}_{C(q)}$ by the uniqueness clause of proposition 22.7.3(1). So F is an isomorphism.

Three cases occur, according to the square class of a (definition 22.1.6).

1. $a = 0$. Then $C(q) \cong k[x]/(x^2)$, the algebra of dual numbers, in agreement with example 22.7.2, which identifies it with $\bigwedge(V)$.
2. $a = c^2$ with $c \in k^\times$. Then $x^2 - a = (x - c)(x + c)$ is a product of two distinct monic irreducibles, distinct because $c \neq -c$ when $\operatorname{char} k \neq 2$, so proposition 11.1.6 gives
$$C(q) \cong k[x]/(x - c) \times k[x]/(x + c) \cong k \times k$$
an algebra with zero divisors: $(\bar{x} - c)(\bar{x} + c) = 0$.
3. $a \in k^\times$ is not a square. Then $C(q)$ is a field, the quadratic extension of k obtained by adjoining a square root of a. Indeed $(u + w\bar{x})(u - w\bar{x}) = u^2 - w^2 a$ for $u, w \in k$, and this is nonzero unless $u = w = 0$: if $w \neq 0$ then $u^2 = w^2 a$ would make $a = (u/w)^2$ a square, and if $w = 0$ then $u \neq 0$ gives $u^2 \neq 0$. So every nonzero element of $C(q)$ has the inverse $(u - w\bar{x})/(u^2 - w^2 a)$.

Over $k = \mathbb{R}$ the three cases are $\mathbb{R}[x]/(x^2)$, $\mathbb{R} \times \mathbb{R}$ and $\mathbb{C}$, the last being $C(\langle -1 \rangle)$.

All three algebras above have dimension $2 = 2^1$, and the same count holds in every dimension. Proving it is the one place where the construction has to be shown not to collapse: nothing said so far rules out $C(q) = 0$, since a quotient by a large ideal can kill everything. The proof below produces an explicit $C(q)$-module of dimension 2^n, and the independence of the monomials of $C(q)$ follows from the independence of that module's basis.

Theorem 22.7.5: The Monomial Basis of $C(q)$

Let k be a field with $\operatorname{char} k \neq 2$, let V be a k-vector space of dimension n, let q be a quadratic form on V, and let $e_1, \dots, e_n$ be an orthogonal basis of V for the associated symmetric bilinear form φ, with $a_i := q(e_i)$. For a subset $S = \{i_1 < i_2 < \cdots < i_r\}$ of $\{1, \dots, n\}$ write
$$e_S := \iota(e_{i_1})\iota(e_{i_2}) \cdots \iota(e_{i_r}) \in C(q), \qquad e_\emptyset := 1$$
Then the 2^n elements e_S form a k-basis of $C(q)$. In particular $\dim_k C(q) = 2^n$ and $\iota \colon V \to C(q)$ is injective.

***Proof*:**
An orthogonal basis exists by theorem 22.2.1, whose hypotheses are the standing ones here. Throughout, ι is suppressed from the notation for products, so e_i denotes $\iota(e_i) \in C(q)$.

Step 1: the relations. By (22.3) applied to $v = w = e_i$ and to $v = e_i$, $w = e_j$ with $i \neq j$,
$$e_i^2 = q(e_i) = a_i, \qquad e_i e_j = -e_j e_i \quad (i \neq j)$$
the second because $\varphi(e_i, e_j) = 0$ for $i \neq j$ by the choice of basis. Also, for $v = \sum_i c_i e_i$, expanding

φ by bilinearity and using orthogonality gives

$$q(v) = \varphi(v,v) = \sum_i c_i^2 a_i \tag{22.4}$$

Step 2: the e_S span $C(q)$. As established in the uniqueness half of the proof of proposition 22.7.3, $C(q)$ is spanned as a k-vector space by 1 together with the products $\iota(v_1)\cdots\iota(v_m)$ with $v_t \in V$. Expanding each v_t in the basis $e_1,\dots,e_n$ and multiplying out, which is legitimate because multiplication in $C(q)$ is k-bilinear, shows that the products $e_{j_1}e_{j_2}\cdots e_{j_m}$ of basis vectors already span.

It remains to reduce such a product to a scalar multiple of some e_S, which is done by induction on m. For $m=0$ the product is $1 = e_\emptyset$. If the indices $j_1,\dots,j_m$ are pairwise distinct, then finitely many interchanges of adjacent factors sort them into increasing order, each interchange multiplying the product by -1 by Step 1, so the product equals $\pm e_S$ with $S = \{j_1,\dots,j_m\}$. If two indices coincide, choose a pair $j_s = j_t = i$ with $s<t$ and $t-s$ minimal. Then $j_u \neq i$ for $s<u<t$, so moving the factor e_{j_t} leftwards past those $t-s-1$ factors changes the product only by a sign and makes the two occurrences of e_i adjacent. Replacing e_ie_i by the scalar a_i produces a scalar multiple of a product of length $m-2$, which the inductive hypothesis handles. Hence the e_S span, and $\dim_k C(q) \le 2^n$.

Step 3: a module of dimension 2^n. Let M be the k-vector space with basis $\{u_S \mid S \subseteq \{1,\dots,n\}\}$, so $\dim_k M = 2^n$. For an index i and a subset S write $S\triangle i$ for the symmetric difference, that is $S\cup\{i\}$ if $i\notin S$ and $S\setminus\{i\}$ if $i\in S$, and set

$$d(i,S) := \#\{l \in S \mid l < i\}, \qquad \sigma(i,S) := (-1)^{d(i,S)}, \qquad c_i(S) := \begin{cases} a_i & i \in S \\ 1 & i \notin S \end{cases}$$

Define $E_i \in \mathrm{End}_k(M)$ on the basis by

$$E_i(u_S) := c_i(S)\,\sigma(i,S)\,u_{S\triangle i}$$

Three facts about these coefficients are what the computation uses. First, $\sigma(i,S\triangle j) = \sigma(i,S)$ whenever $j \ge i$, since $d(i,-)$ counts only elements smaller than i and is therefore unchanged by inserting or deleting j. Second, $\sigma(j,S\triangle i) = -\sigma(j,S)$ whenever $i<j$, since $d(j,-)$ then changes by exactly one. Third, $c_i(S\triangle j) = c_i(S)$ for $j\neq i$, since membership of i is unchanged, while $c_i(S)c_i(S\triangle i) = a_i$, one of the two factors being a_i and the other 1.

Applying E_i twice and using the first and third facts,

$$E_i^2(u_S) = c_i(S)\sigma(i,S)\,c_i(S\triangle i)\sigma(i,S\triangle i)\,u_S = a_i\,\sigma(i,S)^2\,u_S = a_i\,u_S$$

so $E_i^2 = a_i\,\mathrm{id}_M$. For $i<j$, the same facts give

$$E_iE_j(u_S) = c_j(S)\sigma(j,S)\,c_i(S\triangle j)\sigma(i,S\triangle j)\,u_{S\triangle\{i,j\}} = c_i(S)c_j(S)\sigma(i,S)\sigma(j,S)\,u_{S\triangle\{i,j\}}$$

whereas, the second fact now contributing a sign,

$$E_jE_i(u_S) = c_i(S)\sigma(i,S)\,c_j(S\triangle i)\sigma(j,S\triangle i)\,u_{S\triangle\{i,j\}} = -\,c_i(S)c_j(S)\sigma(i,S)\sigma(j,S)\,u_{S\triangle\{i,j\}}$$

so $E_iE_j = -E_jE_i$ for $i\neq j$.

Step 4: the e_S are independent. Let $\rho\colon V \to \mathrm{End}_k(M)$ be the k-linear map with $\rho(e_i) = E_i$. For $v = \sum_i c_i e_i$, expanding the square and grouping the cross terms in pairs,

$$\rho(v)^2 = \sum_i c_i^2 E_i^2 + \sum_{i<j} c_i c_j \big(E_i E_j + E_j E_i\big) = \Big(\sum_i c_i^2 a_i\Big)\mathrm{id}_M = q(v)\,\mathrm{id}_M$$

by Step 3 and (22.4). So proposition 22.7.3(1), applied to the k-algebra $A = \mathrm{End}_k(M)$, yields an algebra homomorphism $\Phi\colon C(q) \to \mathrm{End}_k(M)$ with $\Phi(e_i) = E_i$.

Evaluate $\Phi(e_S)$ at $u_\emptyset$ for $S = \{i_1 < \cdots < i_r\}$, by descending induction on t on the claim that $E_{i_{t+1}} \cdots E_{i_r}(u_\emptyset) = u_T$ with $T = \{i_{t+1}, \ldots, i_r\}$. For $t = r$ the product is empty and the claim reads $u_\emptyset = u_\emptyset$. Given it for t, every element of T exceeds i_t, so $d(i_t, T) = 0$ and $\sigma(i_t, T) = 1$, while $i_t \notin T$ gives $c_{i_t}(T) = 1$. Hence $E_{i_t}(u_T) = u_{T\cup\{i_t\}}$, which is the claim for $t-1$. At $t = 0$ it reads $\Phi(e_S)(u_\emptyset) = u_S$. Now if $\sum_S \lambda_S e_S = 0$ in $C(q)$, applying Φ and evaluating at $u_\emptyset$ gives $\sum_S \lambda_S u_S = 0$ in M, and the u_S are a basis, so every $\lambda_S = 0$.

The e_S therefore span and are independent, so they are a basis and $\dim_k C(q) = 2^n$. The images $\iota(e_1), \ldots, \iota(e_n)$ are the basis elements e_S with $\#S = 1$, hence linearly independent, so the linear map ι carries a basis of V to an independent set and is injective, completing the proof.

Two consequences are recorded before any further computation. First, ι being injective, V is identified with its image from here on and the symbol ι is dropped: a vector $v \in V$ is treated as an element of $C(q)$ with $v^2 = q(v)$. Second, $C(q)$ and $\bigwedge(V)$ have the same dimension for every q, by theorem 22.7.5 and example 22.7.2, and the same monomials index a basis of each. The multiplications differ, since squares of vectors are 0 in one and $q(v)$ in the other. For $n \geq 2$ neither algebra is commutative: $e_1e_2 = -e_2e_1$ in both, and $e_1e_2 \neq 0$ because it is a basis element (theorem 22.7.5 and theorem 16.4.3), so $e_1e_2 = e_2e_1$ would give $2e_1e_2 = 0$ against $\mathrm{char}\, k \neq 2$.

Example 22.7.6: The Quaternions as a Clifford Algebra

Let $V = \mathbb{R}^2$ and $q = \langle -1, -1\rangle$, with orthogonal basis e_1, e_2 and $q(e_1) = q(e_2) = -1$. By theorem 22.7.5 the algebra $C(q)$ has basis $1, e_1, e_2, e_1e_2$. Writing $\omega := e_1e_2$ and using $e_2e_1 = -e_1e_2$ to move factors past one another,

$$e_1^2 = e_2^2 = -1, \qquad \omega^2 = e_1e_2e_1e_2 = -e_1e_1e_2e_2 = -(-1)(-1) = -1$$

$$e_1e_2 = \omega, \qquad e_2\omega = e_2e_1e_2 = -e_1e_2e_2 = e_1, \qquad \omega e_1 = e_1e_2e_1 = -e_1e_1e_2 = e_2$$

These are the relations $i^2 = j^2 = k^2 = -1$, $ij = k$, $jk = i$, $ki = j$ satisfied by the quaternion units, so $C(q)$ and the quaternions $\mathbb{H}$ are the same algebra. Note that $\mathbb{H}$ appears in theorem 20.2.3 as one of the three associative real division algebras, though that theorem gives no basis or multiplication rule, so both are recalled here. To see it as an isomorphism rather than a coincidence of tables, recall that $\mathbb{H}$ is the 4-dimensional $\mathbb{R}$-algebra with basis $1, i, j, k$ and $ij = k = -ji$. Those two relations already force the rest of the table: putting $k = ij$ and using associativity,

$$jk = j(ij) = (ji)j = -ij^2 = i, \qquad ki = (ij)i = i(ji) = -i^2j = j$$

and in the same way $ik = i(ij) = i^2j = -j$ and $kj = (ij)j = ij^2 = -i$, so the products computed in $C(q)$ above are exactly the quaternion products, and they agree with the relations displayed for Q_8 in section 1.2.4. Now let $f\colon V \to \mathbb{H}$ be the $\mathbb{R}$-linear map with $f(e_1) = i$ and $f(e_2) = j$. For $v = c_1e_1 + c_2e_2$,

$$f(v)^2 = c_1^2 i^2 + c_1c_2(ij + ji) + c_2^2 j^2 = -(c_1^2 + c_2^2) = q(v)$$

so proposition 22.7.3(1) gives an algebra homomorphism $F\colon C(q) \to \mathbb{H}$ with $F(e_1) = i$ and $F(e_2) = j$. Its image is a subalgebra containing i, j and hence $ij = k$, so it contains the spanning set $1, i, j, k$ and F is surjective. Both algebras have dimension 4 over $\mathbb{R}$, so

$$C(\langle -1, -1\rangle) \cong \mathbb{H}$$

Compare example 22.7.4, where $C(\langle -1\rangle) \cong \mathbb{C}$: the first two entries of a negative definite real form produce the complex numbers and then the quaternions.

The $\mathbb{Z}$-grading of $\mathcal{T}(V)$ was lost when the inhomogeneous relations were imposed, but the parity of a monomial was unchanged by the reduction in Step 2 of theorem 22.7.5: cancelling a repeated index removes two factors at a time. The following proposition makes that observation into a decomposition of the algebra, obtained not from the monomials but from the universal property, which is what makes it independent of the chosen orthogonal basis.

Proposition 22.7.7: The Parity Grading and the Even Subalgebra

Let k be a field with $\operatorname{char} k \neq 2$, let V be a k-vector space of dimension n, and let q be a quadratic form on V.

1. There is a unique k-algebra automorphism $\alpha\colon C(q) \to C(q)$ with $\alpha(v) = -v$ for all $v \in V$, and $\alpha^2 = \mathrm{id}$.
2. Setting $C^0(q) := \{x \in C(q) \mid \alpha(x) = x\}$ and $C^1(q) := \{x \in C(q) \mid \alpha(x) = -x\}$,
$$C(q) = C^0(q) \oplus C^1(q), \qquad C^\epsilon(q)\, C^\delta(q) \subseteq C^{\epsilon+\delta}(q)$$
the superscripts being read modulo 2. In particular $C^0(q)$ is a subalgebra, the *even part* of $C(q)$, and $V \subseteq C^1(q)$.
3. With the notation of theorem 22.7.5, $C^0(q)$ has basis the e_S with $\#S$ even and $C^1(q)$ has basis the e_S with $\#S$ odd. For $n \geq 1$ both have dimension 2^{n-1}.

***Proof*:**

1. The map $f\colon V \to C(q)$ with $f(v) = -v$ is k-linear and satisfies $f(v)^2 = (-v)^2 = v^2 = q(v)$, so proposition 22.7.3(1) with $A = C(q)$ gives a unique algebra homomorphism α with $\alpha(v) = -v$ on V. Then $\alpha \circ \alpha$ is an algebra homomorphism $C(q) \to C(q)$ restricting on V to $v \mapsto -(-v) = v$, and $\mathrm{id}_{C(q)}$ restricts to that same map. The uniqueness clause of the same proposition, applied to $f = \iota$, forces $\alpha^2 = \mathrm{id}$. Hence α is bijective, so it is an automorphism.
2. For $x \in C(q)$ write
$$x = \tfrac{1}{2}\big(x + \alpha(x)\big) + \tfrac{1}{2}\big(x - \alpha(x)\big)$$
which is legitimate since $\operatorname{char} k \neq 2$. Applying α and using $\alpha^2 = \mathrm{id}$ shows the first summand is fixed by α and the second is negated, so $C(q) = C^0(q) + C^1(q)$. If x lies in both then $x = -x$, so $2x = 0$ and $x = 0$. The sum is direct. For the product rule, let $x \in C^\epsilon(q)$ and $y \in C^\delta(q)$. Then $\alpha(xy) = \alpha(x)\alpha(y) = (-1)^\epsilon(-1)^\delta xy = (-1)^{\epsilon+\delta}xy$, which is the stated containment. Taking $\epsilon = \delta = 0$ shows $C^0(q)$ is closed under multiplication, and $\alpha(1) = 1$ puts 1 in it, so it is a subalgebra. Finally $\alpha(v) = -v$ for $v \in V$ is the statement $V \subseteq C^1(q)$.

3. Since α is an algebra homomorphism, $\alpha(e_S) = \alpha(e_{i_1}) \cdots \alpha(e_{i_r}) = (-1)^r e_S$ for S of size r. Writing an arbitrary $x = \sum_S \lambda_S e_S$ in the basis of theorem 22.7.5,

$$\alpha(x) = \sum_S (-1)^{\#S} \lambda_S e_S$$

and comparing coefficients, $\alpha(x) = x$ holds if and only if $\lambda_S = 0$ for every S of odd size, while $\alpha(x) = -x$ holds if and only if $\lambda_S = 0$ for every S of even size. So the even monomials are a basis of $C^0(q)$ and the odd ones a basis of $C^1(q)$. Their numbers are equal for $n \geq 1$, since

$$\sum_{r \text{ even}} \binom{n}{r} - \sum_{r \text{ odd}} \binom{n}{r} = (1-1)^n = 0$$

by the binomial theorem, and they sum to 2^n, so each is 2^{n-1}, as we sought to show.

The decomposition is a $\mathbb{Z}/2\mathbb{Z}$-grading, and $C^0(q)$ is a subalgebra of half the dimension of $C(q)$. In example 22.7.6 it has basis $1, e_1e_2$ with $(e_1e_2)^2 = -1$, so evaluation at e_1e_2 is a surjective algebra homomorphism $\mathbb{R}[x] \to C^0$ killing $x^2 + 1$, and comparing dimensions gives

$$C^0(\langle -1, -1 \rangle) \cong \mathbb{R}[x]/(x^2+1) \cong \mathbb{C}$$

sitting inside $\mathbb{H}$ as the subalgebra spanned by 1 and one imaginary unit. The general rank-two computation, which recovers $\operatorname{disc}(q)$ of definition 22.1.7 from the even part, is the third exercise below.

Exercise 22.7.1

1. Let $\operatorname{char} k \neq 2$, let q be a quadratic form on V and regard $V \subseteq C(q)$ as in theorem 22.7.5. Show that a vector $v \in V$ is invertible in $C(q)$ if and only if $q(v) \neq 0$, and that its inverse is then $q(v)^{-1}v$. Deduce that if $q(v) = 0$ for some nonzero $v \in V$, then $C(q)$ is not a division algebra.

2. Let $\operatorname{char} k \neq 2$ and let $q = \langle 1, -1 \rangle$ on k^2. Show that $C(q) \cong M_2(k)$. (Send e_1 and e_2 to two explicit matrices, check the hypothesis of proposition 22.7.3(1) for every vector rather than only for e_1 and e_2, and finish with theorem 22.7.5.)

3. Let $\operatorname{char} k \neq 2$ and let $q \cong \langle a, b \rangle$ be nondegenerate of rank 2. Show that $C^0(q) \cong k[x]/(x^2 + ab)$, and that this algebra is a field exactly when $-ab$ is not a square in k. Using corollary 22.2.3, express the condition in terms of $\operatorname{disc}(q)$, and check the answer against example 22.7.6.

4. Let $\operatorname{char} k \neq 2$ and let $q \cong \langle a_1, \ldots, a_n \rangle$ be nondegenerate, so every $a_i \neq 0$, and set $\omega := e_1e_2 \cdots e_n$ for an orthogonal basis as in theorem 22.7.5. Show that $\omega e_i = (-1)^{n-1} e_i \omega$ for every i, and deduce that ω lies in the centre of $C(q)$ if and only if n is odd.

5. Let $\operatorname{char} k \neq 2$ and let $C(g)$ be as in proposition 22.7.3(2). Show that $C(\mathrm{id}_V) = \mathrm{id}_{C(q)}$ and that $C(h \circ g) = C(h) \circ C(g)$ for isometries g and h. Deduce that $g \mapsto C(g)$ is a group homomorphism from the orthogonal group $O(\varphi)$ of definition 22.1.10 to the group of k-algebra automorphisms of $C(q)$, and that every automorphism in its image commutes with the α of proposition 22.7.7 and therefore preserves $C^0(q)$ and $C^1(q)$.

6. Let $\operatorname{char} k \neq 2$ and let $C(q)^{\mathrm{op}}$ denote the k-algebra with the same underlying vector space as $C(q)$ and multiplication $x * y := yx$. Show that there is a unique k-algebra homomorphism

$t\colon C(q) \to C(q)^{\mathrm{op}}$ with $t(v) = v$ for all $v \in V$, that the resulting map on $C(q)$ satisfies $t(xy) = t(y)t(x)$ and $t^2 = \mathrm{id}$, and that $t(e_{i_1}e_{i_2}\cdots e_{i_r}) = (-1)^{r(r-1)/2}e_{i_1}e_{i_2}\cdots e_{i_r}$ for $i_1 < \cdots < i_r$.

7. Let $\operatorname{char} k \neq 2$ and let q be a quadratic form on V. Show that $C^0(q)$ is spanned as a k-vector space by the products $v_1v_2\cdots v_{2m}$ of an even number of vectors of V, and hence that it is generated as a k-algebra by the products vw with $v, w \in V$.

Part V

Commutative Algebra

In this part of the book, we are no longer studying a new object as the central focus. Rather, it is the basic language that deals with *algebraic number theory* and *algebraic geometry*; this is the language of commutative algebra. Commutative algebra is an extension of ring theory where it is always assumed that the ring R is commutative. As shall be shown soon, this theory will prove to be very useful in developing two major studies of mathematics:

1. *Algebraic Geometry*: At the heart of Algebraic Geometry is the realization that all commutative rings have a corresponding *geometric object* (known as an *affine scheme*). We have already encountered the simplest of schemes in section 13.2.4 with the classification of hyper-planes of a finitely dimensional vector-space. Recall that each hyper-plane is associated the solution (or kernel) of linear equations. Schemes generalize this notion a great deal by working with polynomials over general commutative rings instead of restriting to linear equations (which are polynomials of degree 1), and by allowing the resulting geometric object to be "glued together" from kernels of polynomials instead of being the solution to polynomials. In *Algebraic Geometry* [13] the reader can see how to associate a scheme to every commutative ring, and the theory behind that correspondence.

2. *Algebraic Number Theory*: Studying fields allowed us to study the solutions to polynomials over fields. However, fields are very restrictive (dually very versatile) algebraic structures that allowed for some very powerful results. When trying to replicate the same strategies for solving polynomial equations over more general rings, many of these strategies fall apart. To properly generlize this, we shall need to invent a new theory, namely *algebraic number theory* is exactly this theory. In chapter 50, we shall explore some results such as quadratic reciprocity and classifying all Abelian extensions (i.e. Kronnecker-Weber's Theorem). Most of the time, we focus on solutions to equation over $\mathbb{Z}$, as $\mathbb{Z}$ is the initial object of ring, or more concretely $\mathbb{Z}$ is an object that appears very naturally in the world.

In this chapter, some basic topological notions will be used. The geometric intuition presented in this chapter will be lost on those who have not taken or learned some basic topology (up to the separation axioms, in particular T_1 and T_2, and compactness/connectedness). Appendix C serves as a review of what topological concepts will be used in this chapter.

chapter 31 and chapter 50 can be thought of as covering the more "classical" versions of heir respective field. For example, modern algebraic geometry shall start with schemes, while algebraic number theory is developed over local fields and uses techniques from complex analysis. Most of the motivation for these developments come form more concrete questions that naturally arose when studying polynomials and their solutions. The reader shall certainly gain a lot by understanding the core ideas behind these two chapters before tackling their more abstract modernization's. The reader wishing to follow up these chapters with a more in-depth covering can checkout [13] for the continuation of this book towards Algebraic Geometry and [77] for a continuation of this book towards Class Field Theory.

Note that algebraic geometry is *not* algebraic topology. In algebraic topology, we usually start with a topological space (or manifold) and associate to it an algebraic object to find properties of the topological/geometrical object. In Algebraic Geometry, we start with a commutative ring (or a collection of commutative rings), and create a geometric object that can be used to study the ring.

23

Noetherian Rings, Hilbert's Basis Theorem, and Localization

As with groups an modules, all R-algebras are quotient of a polynomial ring over many variables. If the polynomial ring is over finitely many variables. The fact that all algebras are quotient of polynomial rings will let the study of geometry and algebra.

Next, we recall some important definition and results that shall be central to the following section:

23.1 Noetherian Rings and Modules

Definition 23.1.1: Noetherian Ring

Let R be a commutative ring. Then if R satisfies the ascending chain condition on Ideals, then R is Noetherian. In particular, if $\mathcal{I}$ is a collection of ideals ordered by inclusion $(I_1 \subseteq I_2 \subseteq \cdots I_k \cdots)$, then there exists an m such that for all $n \geq m$, $I_m = I_{m+1} = \cdots$.

Proposition 23.1.2: Extension of Noetherian Rings

Let R be a Noetherian ring. Then R/I is Noetherian for any ideal I. Conversely, if I and R/I is Noetherian, then R is Noetherian.

***Proof*:**
Ideals of R/I are exactly the ideals of R containing I, so an ascending chain in R/I pulls back to an ascending chain in R, which stabilizes; thus R/I is Noetherian. Conversely, suppose I and R/I are Noetherian and let $J_1 \subseteq J_2 \subseteq \cdots$ be ideals of R. The chains $J_n \cap I$ (in I) and $(J_n + I)/I$ (in R/I) both stabilize, say for $n \geq m$. For such n, if $x \in J_{n+1}$ write $x = j + a$ with $j \in J_n$, $a \in I$ (possible since $J_n + I = J_{n+1} + I$); then $a = x - j \in J_{n+1} \cap I = J_n \cap I \subseteq J_n$, so $x \in J_n$. Hence $J_n = J_{n+1}$ and R is Noetherian.

As a consequence the image of any Noetherian ring is Noetherian.

Proposition 23.1.3: Equivalence of Noetherian Ring

Let R be a commutative ring. Then the following are equivalent

1. R is Noetherian
2. every nonempty collection of ideals of R has a maximal element under inclusion
3. every ideal of R is finitely generated

***Proof*:**
(1) $\Rightarrow$ (2): a nonempty collection of ideals with no maximal element would yield a strictly ascending chain, contradicting the ascending chain condition. (2) $\Rightarrow$ (3): given an ideal J, the collection of finitely generated subideals of J has a maximal element J_0; if $J_0 \neq J$, then for $x \in J \setminus J_0$ the ideal $J_0 + (x)$ is finitely generated and strictly larger, a contradiction, so $J = J_0$ is finitely generated. (3) $\Rightarrow$ (1): for an ascending chain $J_1 \subseteq J_2 \subseteq \cdots$, the union $J = \bigcup_n J_n$ is an ideal, hence finitely generated; its finitely many generators lie in some J_m, so $J = J_m$ and the chain stabilizes.

Example 23.1.4: Exercise
Show that if R is a Noetherian ring and M is a finitely generated R-module, then M is Noetherian (Hint: remember the universal property of free-modules)

The maximal-element form of the condition, part (2) above, is the one that does the work in practice. Here is a first instance, and the finiteness statement the factorization theory of Dedekind domains rests on: an ideal of a Noetherian ring need not factor into primes, but it always *contains* a product of them.

Proposition 23.1.5: Every Proper Ideal Contains a Product of Primes

Let R be a Noetherian ring and let $I \subsetneq R$ be a proper ideal. Then there are finitely many prime ideals $\mathfrak{p}_1, \ldots, \mathfrak{p}_r$, each containing I, with

$$\mathfrak{p}_1 \mathfrak{p}_2 \cdots \mathfrak{p}_r \subseteq I$$

***Proof*:**
Let Σ be the collection of proper ideals of R admitting no such family of primes, and suppose $\Sigma \neq \emptyset$. Since R is Noetherian, Σ has a maximal element I by proposition 23.1.3(2).

Step 1: the maximal counterexample is not prime. Were I prime, $r = 1$ and $\mathfrak{p}_1 = I$ would satisfy the conclusion. So there are $a, b \in R \setminus I$ with $ab \in I$. Put $J = I + (a)$ and $J' = I + (b)$; both strictly contain I. Since $ab \in I$ and I is an ideal,

$$JJ' = (I + (a))(I + (b)) \subseteq I \cdot I + I(b) + (a)I + (ab) \subseteq I$$

Step 2: both are proper. If $J = R$ then $J' = JJ' \subseteq I$, contradicting $J' \supsetneq I$; symmetrically $J' \neq R$. So J and J' are proper ideals strictly containing I.

Step 3: descend. By maximality of I in Σ, neither J nor J' lies in Σ, so there are primes $\mathfrak{p}_1, \dots, \mathfrak{p}_s \supseteq J$ with $\mathfrak{p}_1 \cdots \mathfrak{p}_s \subseteq J$ and primes $\mathfrak{q}_1, \dots, \mathfrak{q}_t \supseteq J'$ with $\mathfrak{q}_1 \cdots \mathfrak{q}_t \subseteq J'$. Then

$$\mathfrak{p}_1 \cdots \mathfrak{p}_s \mathfrak{q}_1 \cdots \mathfrak{q}_t \subseteq JJ' \subseteq I$$

and each of these primes contains J or J', hence contains I. So $I \notin \Sigma$, a contradiction, and $\Sigma = \emptyset$ as we sought to show.

Over a domain the primes so produced are automatically nonzero, since they contain I. That is the form the theory of Dedekind domains actually uses:

Corollary 23.1.6: Nonzero Ideals Contain Products of Nonzero Primes

Let R be a Noetherian domain and let $I \subsetneq R$ be a nonzero proper ideal. Then I contains a product of finitely many *nonzero* prime ideals, each containing I.

***Proof*:**
Take $\mathfrak{p}_1, \dots, \mathfrak{p}_r$ as in proposition 23.1.5. Each $\mathfrak{p}_i$ contains I, and $I \neq 0$, so each $\mathfrak{p}_i$ is nonzero.

We will soon encounter rings that satisfy the descending chain condition (commonly abbreviated to D.C.C). Such rings are called *Artinian rings*. For the following result, let us upgrade definition 3.7.6 for modules:

Definition 23.1.7: Chain of Modules and Composition Series

Let M be a module. Then a *chain* of submodule of M is a sequence (M_i) of submodules st

$$M = M_0 \supsetneq M_1 \supsetneq \cdots \supsetneq M_n = 0$$

where the length of the chain is the number of $\supsetneq$. A maximal chain is called a *composition series* of M (equivalently, each M_{i-1}/M_i is *simple*. IF the chain is of infinite length, we shall say that M does not have a composition series.

Proposition 23.1.8: Finite Length, then Length is Invariant

Let M have a composition series of length n. Then every composition series of M has length n, and every chain in M can be extended to a composition series.

***Proof*:**
Let $\ell(M)$ denote the least length of composition series of a module M To get the desired result, let us prove a few results:

1. $N \subseteq M \Rightarrow \ell(N) \leq \ell(M)$, with equality iff $N = M$. Let (M_i) be a composition series of M of minimum length, and take $N_i = N \cap M_i$. Then $N_{i-1}/N_i \subseteq M_{i-1}/M_i$, which is simple, so each N_{i-1}/N_i is 0 or all of M_{i-1}/M_i; dropping repetitions gives a composition series of N of length $\leq \ell(M)$, and $\ell(N) = \ell(M)$ forces $N_i = M_i$ for all i, i.e. $N = M$

2. each $M_i \subsetneq M$ have length $\leq \ell(M)$. To see this, we may make a new chain with M_0 as the starting point:
$$M = M_0 \supsetneq M_1 \supsetneq \cdots \supsetneq M_k = 0$$
which by part 1 give us:
$$\ell(M) = \ell(M_0) \geq \ell(M_1) \geq \cdots \geq \ell(M_k) = 0$$

3. Take any composition series of M. Then if it has length k, it must be that $k \leq \ell(M)$ by part (2). As $\ell(M)$ is the least length of a composition series, also $k \geq \ell(M)$, so $k = \ell(M)$. Hence, all composition series have the same length.

Finally, consider any chain for M. If its length is $\ell(M)$, by (2) it must be a composition series, if its length is less than $\ell(M)<$ it cannot be a composition series, and hence cannot be maximal. There does exists a lengthening by a new term, which as the number of possible terms that can be added is of finite length we may continue until we have a series of length $\ell(M)$, completing the proof.

23.2 Hilbert Basis Theorem

Recall from theorem 11.1.1 that if F is a field, then $F[x]$ is a Euclidean domain. By corollary 11.2.4, $F[x_1, x_2, \dots]$ is a Unique Factorization Domain. However, of all the condition's on rings we have covered they are not necessarily stronger than Unique Factorization Domains (with the counter-example being example 11.2.5 where $\mathbb{Z}[x, y]$ is a UFD but not a PID). If we loosen the condition from the ideals be generated by a single element to being generated by *finitely many* elements (i.e. a Noetherian ring), then we in fact get that extending by an indeterminate x does not affect the finiteness condition on ideals.

Theorem 23.2.1: Hilbert's Basis Theorem (HBT)

Let R be a Noetherian ring. Then $R[x]$ is a Noetherian ring

If you know some linear algebra, the term "basis" is not like the term basis in linear algerba. It is because of an archaic use of the word basis when Hilbert formulated the theorem near the end of the 19th century, where it had a closer to "generation" than basis.

***Proof*:**

Recall that if $p(x) = a_n x^n + a_{n-1}x^{n-1} + \cdots + a_1 x + a_0$, then a_n is the leading coefficient of $p(x)$. This terminology will often be used in this proof.

Let $I \subseteq R[x]$ be an ideal. The trick is to somehow make I linked to an ideal of R (which is finitely generated since R is Noetherian). Let L be the set of all leading coefficients of the ideal I. Then L is an ideal. First, $0 \in I$, so $0 \in L$. Next, take $f, g \in I$ be two polynomials in I so that $f = ax^n + a_{n-1}x^{n-1} + \cdots + a_1 x + a_0$ and $g = bx^m + b_{n-1}x^{m-1} + \cdots + b_1 x + b_0$ with leading coefficients a and b and degrees n and m respectively, with $n \geq m$, so that $a, b \in L$. Multiplying the lower-degree polynomial by a power of x to equalize degrees, $rx^{n-m}g \in I$ has degree n and leading coefficient rb, so $f - rx^{n-m}g \in I$ has degree-n coefficient $a - rb$; hence $a - rb \in L$ whenever it is nonzero. Thus L is closed under subtraction and absorbs multiplication by R, so L is an ideal. Now, since R is a Noetherian ring and L is an ideal of R, L is finitely generated, say $L = \langle a_1, a_2, ..., a_n \rangle$. Then for each a_i, there is a polynomial f_i that has a_i as it's coefficient. Let's say e_i is the degree of f_i, so that the set $e_1, e_2, ..., e_n$ represents the degree's of the polynomials representing the generators of L. Let $N = \max\{e_1, e_2, ..., e_n\}$.

Next, we will construct a couple of smaller ideals. Let $d \in \{0, 1, 2, ..., N-1\}$ (i.e. d is strictly smaller than the largest degree N) and define $L_d \subseteq L$ to be the set of all leading coefficients of polynomials of I of degree d, together with 0. Then L_d is also an ideal of R as can be checked by a similar method as last proof. Since R is Noetherian, there exists a set of generators for L_d, say $L_d = \{b_{d,1}, b_{d,2}, ..., b_{d,k_d}\}$. For each generator of L_d, there is a polynomial $f_{d,i} \in I$ of degree d that has the generator $b_{d,i}$ as its leading coefficient.

Now, we will show that

$$I = \langle f_1, f_2, ..., f_n, f_{1,1}, f_{1,2}, ...f_{1,k_1}, f_{2,1}, ..., f_{N-1,k_{N-1}} \rangle$$

that is, I is generated by the polynomial f_i and the polynomials $f_{d,i}$. Since there are finitely many of them, I would be finitely generating completing the proof. To show this, let I' represent the right hand side. Then $I' \subseteq I$, since every generator of I' is in I, and I' is the smallest set that contains those generators. So, let's prove $I \subseteq I'$, and take a $f \in I$.

If $\deg(f) \geq N$, then since $f \in I$, it's leading coefficient (say a) is in L: $a \in L$. Then since L is finitely generated, it is an R-linear combination of the generators of L: $r_1 a_1 + r_2 a_2 + \cdots + r_n a_n$. From this, we can define a new polynomial $g_1 = r_1 x^{d-e_1} f_1 + r_2 x^{d-e_2} f_2 + \cdots + r_n x^{d-e_n} f_n$ with the same leading coefficient a of f that is in I'. Then

$$f - g_1$$

is a polynomial in I of degree less than $\deg(f)$. If $\deg(f - g_1)$ is still greater than or equal to N, then repeat the same process, making the polynomial $(f - g_1) - g_2$. Continue on this way till we get a polynomial of degree less than N:

$$f - g_1 - g_2 - \cdots - g_\ell = f - (g_1 + g_2 + \cdots + g_\ell)$$

Let's label this above polynomial f'. Note that the sum of the g_i's can be re-written as an R-linear combination of elements of I' since they all belong to I':

$$f - (\alpha_1 f_1 + \alpha_2 f_2 + \cdots + \alpha_n f_n)$$

Now, $\deg(f') < N$. Since $f' \in I'$, it's leading coefficient (say a) is in L_d: $a \in L_d$. Then since L_d is finitely generated, it is an R-linear combination of the generators of L_d: $a = r_1 b_{d,1} + r_2 b_{d,2} + \cdots + r_{k_d} b_{d,k_d}$. From this, we can define a new polynomial $h_1 = r_1 f_{d,1} + r_2 f_{d,2} + \cdots + r_{k_d} f_{d,k_d}$ with the same leading coefficient as f' that is in I'. Then

$$f' - h_1$$

Is of degree less than f'. Just as before, we can continue this procedure, which will terminate once the degree reaches 0:

$$f' - h_1 - h_2 - \cdots - h_p = f' - (h_1 + h_2 + \cdots + h_p)$$

Note that $\sum_i h_i$ can be decomposed into a sum of polynomials with leading coefficients from L_d:

$$f' - (\beta_{1,1} f_{1,1} + \beta_{1,2} f_{1,2} + \cdots + \beta k, k_d f_{k,k_d})$$

Since our algorithm terminated after we have subtacted the constant (that is, the leading term of L_0), we are left with:

$$f - (g_1 + g_2 + \cdots + g_\ell + h_1 + h_2 + \cdots + h_p) = 0$$

which implies $f = g_1 + g_2 + \cdots + g_\ell + h_1 + h_2 + \cdots + h_p$. Re-writing slightly, we get that

$$f = \alpha_1 f_1 + \alpha_2 f_2 + \cdots + \alpha_n f_n + \beta_{1,1} f_{1,1} + \beta_{1,2} f_{1,2} + \cdots + \beta k, k_d f_{k,k_d}$$

which shows that f is a combination of elements of I' and so $f \in I'$. Since f was arbitrary, we cna conclude that $I \subseteq I'$.

Along with the quick assertion earlier that $I' \subseteq I$, that shows us that $I = I'$, showing that I was finitely generated. Since I was an arbitrary ideal, we are left with saying that every ideal of $R[x]$ is finitely generated, showing that $R[x]$ is also Noetherian, as we sought to show.

The result is not necessarily true if R is not Noetherian

In the exercises there will be the outlining of an alternative proof which will give a different insight in the exercises.

Corollary 23.2.2: HBT on multi-variable Polynomials

Let R be a Noetherian ring. Then $R[x_1, x_2, ..., x_n]$ is a Noetherian ring

***Proof*:**
Since R is Noetherian, by the Hilbert Basis Theorem, $R[x_1]$ is Noetherian. Since $R[x_1]$ is Noetherian, $(R[x_1])[x_2] = R[x_1, x_2]$ is Noetherian. Continuing inductively, we see that $R[x_1, x_2, ..., x_n]$ is Noetherian, as we sought to show

Corollary 23.2.3: f.g. K-algebra then Finitely Presented

Let R be a finitely generated k-algebra. Then R is *finitely presented*, meaning

$$R \cong \frac{k[x_1, ..., x_n]}{(f_1, ..., f_m)} = \frac{k[x_1, ..., x_n]}{I}$$

where I is finitely generated.

***Proof*:**
As R is finitely generated as a k algebra:

$$R \cong \frac{k[x_1, ..., x_n]}{I}$$

for some finitely many variable $x_1, ..., x_n$ and an ideal $I \subseteq R$. By corollary 23.2.2 R is Noetherian, hence I is *finitely generated*: $I = (f_1, ..., f_m)$. But then R is finitely presented, completing the proof.

You can now return to example 10.1.18 to fully appreciate how there exist Atomic Domains which are not Noetherian Domains.

This theorem is very powerful. Since $R[x]$ is an ideal of itself, it is also finitely generated and the polynomials which generate it finitely can be characterized by their leading coefficients. In section 23.3, we will expand this theory further find a computational way of getting these polynomials.

Since a field is Noetherian (only ideal is (1) and (0), both clearly finite), Hilbert's Basis Theorem and induction immediately give:

Corollary 23.2.4: HBT on Polynomial Rings of Several Variables

Every ideal in the polynomial ring $F[x_1, x_2, ..., x_n]$ with coefficients from a field F is finitely generated

***Proof*:**
A field is Noetherian, so by corollary 23.2.2 the ring $F[x_1, \ldots, x_n]$ is Noetherian; every ideal is therefore finitely generated by proposition 23.1.3.

Recall that finitely generated R-algebras are quotient of polynomial rings R. By HBT, we have the following

Corollary 23.2.5: Finitely Generated Algebras Are Noetherian

Let R be Noetherian and let A be a finitely generated R-algebra. Then A is Noetherian.

***Proof*:**
Write $A \cong R[x_1, \ldots, x_n]/I$ as a quotient of a polynomial ring. By corollary 23.2.2 the polynomial ring is Noetherian, and by proposition 23.1.2 so is its quotient A.

Polynomial rings being over a Noetherian ring being Noetherian is central to to the study of algebras thanks to the universal property of Algebras

(A word on how Artinian rings are the opposite with D.C.C. We will not study them till chapter 28, since they sort of seem like a "oh wow, Noetherian rings can do so much, what about the opposite?" and then we realise that Artinian ring implies Noetherian ring, and it has so much structure that we can easily classify them all with no further fought, so we will just leave that for later. All in all, the Noetherian condition turns out to be "more interesting")

23.2.6 Without Assuming Noetherian Let $R = k[x_1, ..., x_n, ...]$ and $A = R/(x_1, ..., x_n, ...)$. Then A is finitely generated, but the ideal is not finitely generated. In algebraic geometry, there is often the need to work with rings that look like quotients of polynomial rings (ex. polynomial rings over local rings). Thus, it common to work with *finitely presented* rings.

Exercise 23.2.1

1. Alternative HBT: (the one uses Diksons lemma)
2. Consider the chain $k[[x]]] \subseteq k[[x^{1/2}]] \subseteq k[[x^{1/6}]] \subseteq \cdots \subseteq k[[x^{1/n!}]]$. Taking the union of all of these forms an object called the *Puisseaux series*. Is the Puisseaux seris a ring, and if so is the Puisseaux series Noetherian?
3. Let S be a finitely generated R-algebra, where R is Noetherian. Prove that S is Noetherian.
4. We know that ideals of $k[x]$ are generated by 1 element if k is a field. By Hilbert's basis theorem, we know that every ideal of $k[x, y]$ is finitely generated. Is it true that ideals of $k[x, y]$ is generated by at most 2 elements if k is a field?
5. Which of the following are Noetherian Rings:
    1. $\mathbb{Z}[x, 1/x]$ as a subring of $\mathbb{Q}$
    2. $R := \mathbb{R} + x\mathbb{C}[x]$
    3. $R := k + xL[x]$ where $[L : k] < \infty$ is a finite field extension
    4. $R := k + xk[x, y]$ as a subring of $k[x, y]$, k a field.
6. Let M be an R-module over a Noetherian ring R. Show that there exists a $x \in M$ such that $\mathrm{Ann}_R(x)$ is a prime ideal (large hint: consider the set $\mathcal{S} = \{\mathrm{Ann}_A(x) \mid x \in M\}$ of ideals, and use the fact that R is Noetherian to conclude $\mathcal{S}$ has a maximal element. Is this element prime?)

23.3 Gröbner Bases

Hilbert's basis theorem guarantees that every ideal of $k[x_1, \ldots, x_n]$ is finitely generated, but its proof is not constructive: it exhibits no canonical generating set and no way to decide whether a given polynomial lies in an ideal. *Gröbner bases* repair both defects. They provide, for each ideal and each choice of monomial order, a distinguished finite generating set against which a multivariate division

algorithm gives unique remainders, turning ideal membership into a finite computation. This is the computational basis of commutative algebra and algebraic geometry; the standard reference is Cox, Little, and O'Shea, *Ideals, Varieties, and Algorithms*.

Fix the polynomial ring $S = k[x_1, \dots, x_n]$ over a field k, and write a monomial as $x^\alpha = x_1^{\alpha_1} \cdots x_n^{\alpha_n}$ for $\alpha \in \mathbb{N}^n$.

Definition 23.3.1: Monomial Order

A *monomial order* on S is a total order $\preceq$ on the monomials of S (equivalently on $\mathbb{N}^n$) such that

1. $\preceq$ is a well-order: every nonempty set of monomials has a least element; and
2. it is compatible with multiplication: if $x^\alpha \preceq x^\beta$ then $x^\gamma x^\alpha \preceq x^\gamma x^\beta$ for all $\gamma \in \mathbb{N}^n$.

The prototype is the *lexicographic order*: $x^\alpha \succ x^\beta$ when the leftmost nonzero entry of $\alpha - \beta$ is positive. The *graded* and *graded reverse* lexicographic orders first compare total degree $|\alpha| = \sum_i \alpha_i$ and break ties lexicographically; the latter is usually fastest in practice. Fixing a monomial order, every nonzero $f \in S$ has a largest monomial.

Definition 23.3.2: Leading Term

Let $\preceq$ be a monomial order and $0 \neq f \in S$. The *multidegree* $\operatorname{multideg}(f)$ is the $\preceq$-largest α with x^α occurring in f; the corresponding term is the *leading term* $\operatorname{LT}(f)$ and its monomial the *leading monomial* $\operatorname{LM}(f)$. For an ideal I, its *leading term ideal* is $\operatorname{LT}(I) = (\operatorname{LT}(f) : 0 \neq f \in I)$, a monomial ideal.

Compatibility makes leading terms multiplicative, $\operatorname{LT}(fg) = \operatorname{LT}(f)\operatorname{LT}(g)$, and the well-order axiom is exactly what makes the following algorithm terminate.

Theorem 23.3.3: Multivariate Division Algorithm

Fix a monomial order and an ordered tuple $(g_1, \dots, g_s)$ of nonzero polynomials. Then every $f \in S$ can be written

$$f = q_1 g_1 + \cdots + q_s g_s + r$$

where no monomial of the remainder r is divisible by any $\operatorname{LM}(g_i)$. It is produced by repeatedly subtracting the appropriate multiple of some g_i whenever $\operatorname{LM}(g_i)$ divides the current leading monomial, and otherwise moving the leading term into r.

***Proof*:**
Each step strictly lowers the $\preceq$-largest monomial not yet moved into r, so by the well-order property the process terminates; the stated condition on r holds by construction.

The remainder generally depends on the *order* of the g_i, and $r = 0$ is sufficient but not necessary for $f \in (g_1, \dots, g_s)$. Both defects vanish for a special generating set.

Definition 23.3.4: Gröbner Basis

Let $I \subseteq S$ be a nonzero ideal and $\preceq$ a monomial order. A finite set $G = \{g_1, \dots, g_s\} \subseteq I$ is a *Gröbner basis* of I if the leading terms of G generate the leading term ideal:

$$\mathrm{LT}(I) = (\mathrm{LT}(g_1), \dots, \mathrm{LT}(g_s))$$

Theorem 23.3.5: Existence and Membership

Every nonzero ideal $I \subseteq S$ has a Gröbner basis for any monomial order, and any Gröbner basis of I generates I. Dividing $f \in S$ by a Gröbner basis of I gives a remainder that is independent of the order of the divisors and is zero if and only if $f \in I$.

***Proof*:**
The monomial ideal $\mathrm{LT}(I)$ is finitely generated by finitely many $\mathrm{LT}(f_i)$ with $f_i \in I$ (*Dickson's lemma*, equivalently theorem 23.2.1); these f_i are a Gröbner basis. If G is a Gröbner basis and $f \in I$, division gives $f = \sum q_i g_i + r$ with $r \in I$ and no monomial of r divisible by any $\mathrm{LM}(g_i)$; were $r \neq 0$, then $\mathrm{LT}(r) \in \mathrm{LT}(I) = (\mathrm{LM}(g_i))$ would be divisible by some $\mathrm{LM}(g_i)$, a contradiction. Hence $r = 0$ and $f \in (G)$, so G generates I and membership is detected by the remainder. Two remainders of the same f differ by an element of I with no monomial divisible by a leading term, hence by 0; the remainder is unique.

Thus a Gröbner basis solves the *ideal membership problem*: $f \in I$ iff its Gröbner-basis remainder is 0. To compute one, we measure the failure of a generating set to be Gröbner through cancellations of leading terms.

Definition 23.3.6: S-polynomial

For nonzero $f, g \in S$ with $L = \mathrm{lcm}(\mathrm{LM}(f), \mathrm{LM}(g))$, the *S-polynomial* is

$$S(f, g) = \frac{L}{\mathrm{LT}(f)} f - \frac{L}{\mathrm{LT}(g)} g,$$

built so the leading terms of the two products cancel.

Theorem 23.3.7: Buchberger's Criterion

A finite generating set $G = \{g_1, \dots, g_s\}$ of an ideal I is a Gröbner basis if and only if, for every pair $i \neq j$, the remainder of $S(g_i, g_j)$ on division by G is zero.

***Proof*:**
Necessity is immediate, since $S(g_i, g_j) \in I$ has zero remainder by theorem 23.3.5. For sufficiency, the content is that every cancellation of leading terms among the g_i is an S-polynomial syzygy; when all S-polynomial remainders vanish this forces $\mathrm{LT}(I) = (\mathrm{LM}(g_i))$. The details are in Cox, Little, and O'Shea.

The criterion is a decision procedure, and completing a set to satisfy it is an algorithm.

Theorem 23.3.8: Buchberger's Algorithm

Given generators $\{f_1, \ldots, f_m\}$ of I, start with $G = \{f_1, \ldots, f_m\}$; repeatedly compute the remainder r of each $S(g_i, g_j)$ on division by G, adjoining r to G whenever $r \neq 0$; stop when all S-polynomial remainders are zero. This terminates and returns a Gröbner basis of I.

***Proof*:**
Each adjoined remainder r has leading monomial outside the current $(\mathrm{LM}(g))$, so the leading term ideals strictly increase; by the ascending chain condition in the Noetherian ring S (theorem 23.2.1) this stabilizes, so finitely many elements are added and the loop halts. On termination all S-polynomial remainders vanish, so G is a Gröbner basis by theorem 23.3.7.

Discarding redundant generators and scaling leading coefficients to 1 yields the unique *reduced* Gröbner basis of I for a given order, a genuine canonical form: two ideals coincide iff their reduced Gröbner bases (for the same order) are equal.

Gröbner bases make ideal membership *decidable*, but not cheap. In the worst case the degrees occurring in a reduced Gröbner basis, and hence the running time of Buchberger's algorithm, are doubly exponential in the number of variables, and ideal membership for $k[x_1, \ldots, x_n]$ is EXPSPACE-complete (Mayr and Meyer). The abstract finiteness handed to us by Hilbert's basis theorem thus conceals real computational hardness: knowing that an ideal is finitely generated is a long way from being able to compute with it.

23.4 Localization

Localization shall be the generalization of section 9.5 to commutative rings and modules in general (including ones with zero-divisors). With the introduction of the tensor product, localization shall be shown to have the important property of producing *flat module*, which shall have important geometric consequences in algebraic geometry. From this, we shall define the notion of local properties and the famous Nakayama lemma which shall allow many proofs to be done "locally". Concluding this section, we shall wrap up the correspondence between primes of a ring R and primes in its integral extension.

The term "localization" comes from algebraic geometry, where this process of localizing mirrors the process of "localizing" for manifolds. If you have done some differential geometry, recall that the tangent space at a point p has *cotangent* space $\mathfrak{m}_p/\mathfrak{m}_p^2$, where $\mathfrak{m}_p$ is the maximal ideal of germs vanishing at p (the tangent space is its dual). Localizing shall correspond to this process, where "inverting" elements around a point is the same as a function on a manifold being invertible on a small enough local neighborhood where $f(p) \neq 0$. The reader may question this correspondence, for in differential geometry we are working with smooth functions over a [smooth] manifold, while in the algebraic case we simply have a [commutative] ring. However, the correspondence is more equivalent than it may at first seem. It shall be particularly clear by the end of section 32.5, where it is shown that there is a way of thinking of all commutative rings as a set of "functions" on a special geometric space (the geometric space is called an [affine] *scheme*), hence there is a direct parallel between smooth functions on the geometric object of a manifold and commutative rings where each element is interpreted as a function on a scheme.

23.4.1 Localization of Rings


This is a generalization of the constructing of ring of fraction from theorem 9.5.1 by allowing the set that's closed under multiplication D to have zero divisors. This will imply that R need not be embedded into $D^{-1}R$, but the universal property is still satisfied. Furthermore, we will have to solve the problem of elements that "should" be zero being equal to nonzero elements. If $a \in R$ and $d \in D$ where $as = 0$, then:

$$a = \frac{a}{1} = \frac{as}{s} = \frac{0}{s} = 0$$

this issue will be addressed in the proof:

Theorem 23.4.1: Universal Property of Localization

Let R be a commutative ring and D a multiplicatively closed subset containing 1. Then there is a ring $D^{-1}R$ and a homomorphism $\iota\colon R \to D^{-1}R$ with $\iota(D) \subseteq (D^{-1}R)^\times$ such that for every ring S and homomorphism $\psi\colon R \to S$ with $\psi(D) \subseteq S^\times$, there is a *unique* homomorphism $\Psi\colon D^{-1}R \to S$ making the following diagram commute:



The pair $(D^{-1}R, \iota)$ is universal among all such (S, ψ).

***Proof*:**

A lot of this proof is similar to theorem 9.5.1 (Ring of Fractions) and so it will be quickly presented pointing out where the generalization of D having zero divisors makes a difference.

Let $R \times D$ have the equivalence relation

$$(a, b) \sim (c, d) \iff x(ad - bc) = 0 \text{ for some } x \in D$$

Which is essentially the same as in theorem 9.5.1. The difference between the proof in the case where D does not have zero divisors' is with the fact that the terms are scaled by some $x \in D$. This is to make sure elements that are zero-divisors will belong to the [0] (as we will show in the proceeding corollary). Usually, the equivalence class $[(r, d)]$ is denoted $\frac{r}{s}$ or r/s so that

$$\frac{a}{b} = \frac{c}{d} \text{ if and only if } x(ad - bc) = 0 \qquad \text{for some } x \in D$$

Define

$$\frac{r}{d} + \frac{s}{e} := \frac{re + sd}{de} \qquad \frac{r}{d}\frac{s}{e} := \frac{rs}{de}$$

Then these two operations form a well-defined commutative ring $(R \times D)/\sim$; this ring is denoted $D^{-1}R$. Note that $\frac{d}{1}$ is a unit in $D^{-1}R$ for every $d \in D$, with inverse $\frac{1}{d}$.

Define $\iota : R \to D^{-1}R$ by $\iota(r) = \frac{r}{1}$. This map defines a natural ring homomorphism. Using this map, if the map $\varphi : R \to S$ maps D to units, we can define the map $\Psi : D^{-1}R \to S$ by defining:

$$\Psi(\frac{r}{d}) = \psi(r)\psi(d)^{-1}$$

This map is well-defined: Notice if $\frac{r}{d} = \frac{s}{e}$ then by definition of the equivalence relation, for some $x \in D$, $x(re - sd) = 0$ Thus $\varphi(x(re - sd)) = \varphi(x)(\varphi(re) - \varphi(sd)) = 0$. Since x is a unit in S and S is a commutative ring, s is not a zero-divisor, and so $\varphi(re) - \varphi(sd) = 0$ Moving values around, we get

$$\varphi(r)\varphi(d)^{-1} = \varphi(s)\varphi(e)^{-1}$$

Thus, Ψ is a well-defined ring homomorphism. Furthermore, by construction, $\Psi \circ \iota = \varphi$

Finally, Ψ is unique. If there was another Ψ' such that $\Psi' \circ \iota = \varphi$, then:

$$\varphi(r) = \Psi'(\iota(r)) = \Psi'\left(\frac{r}{1}\right)$$

Thus Ψ' maps $\frac{r}{1}$ in the same way as Ψ. For the $\frac{1}{d}$ terms, notice that

$$\frac{1}{d} = \left(\frac{d}{1}\right)^{-1}$$

and so $\varphi(d) = \Psi'(\frac{d}{1})$, and so, by properties of ring homomorphisms

$$\Psi'\left(\frac{d}{1}\right)^{-1} = \Psi'\left(\frac{1}{d}\right)$$

showing that $\Psi' = \Psi$, fulfilling the last condition needed to prove for the universal property

As before, $D^{-1}R$ is still called the ring of fractions. However, there is a more common name with a geometric intuition:

Definition 23.4.2: Localization of R at D

Let R be a commutative ring and D be a multiplicatively closed subset of R. Then the ring $D^{-1}R$ produced in the previous theorem is the *ring of fractions of R with respect to D*, or the *localization of R at D*. This ring is also sometimes denoted $R[D^{-1}]$.
If $D = \{f^n \mid n \in \mathbb{Z}_{\geq 0}\}$ for some $f \in R$, we usually denote $D^{-1}R = R_f$.

If D is not a multiplicatively closed set, we define $R[D^{-1}] := R[\overline{D}^{-1}]$ where $\overline{D^{-1}}$ is the multiplicative closure of D.

The fact that D can contain zero divisors means that ι can now have non-trivial kernel:

Corollary 23.4.3: Kernel of ι

Let ι be the natural inclusion of R into $D^{-1}R$ for some appropriate D. Then

1. $\ker(\iota) = \{r \in R \mid xr = 0 \text{ for some } x \in D\}$. In particular, ι is an injection if and only if D does not contain 0 or zero-divisors
2. $D^{-1}R = 0$ if and only if D contains 0 or a nilpotent element (since D is multiplicatively closed)

***Proof*:**

1. If $\iota(r) = \frac{r}{1} = 0$, then we have that $(r, 1) \sim (0, 1)$ and so $x(1r - 0) = xr = 0$ for some $x \in D$. Thus, ι is an injection if and only if D does not contain 0 or zero-divisors
2. $D^{-1}R = 0$ if and only if $r/1 = 0/1$ for all r i.e. $(r, 1) \sim (0, 1)$ if and only if $(1, 1) \sim (0, 1)$ if and only if $x \cdot 1 = 0$. If $x = 0$, we are done, and if not then as D is multiplicatively closed then $x^n \in D$ for each $n \in \mathbb{N}$ and so if $x^n = 0$ then x is nilpotent and $x^n \cdot 1 = 0$, completing the proof.

This let's us get a sense of how adding zero-divisors to D changes the resulting localization of R at D.

Example 23.4.4: Localization
All examples in section 9.5 are valid examples, including the trivial one of any field $\mathbb{F}$, $\mathbb{Z}$ to $\mathbb{Q}$ with $D = \mathbb{Z} - \{0\}$, and $\mathbb{F}[x]$ to $\mathbb{F}(x)$ with $D = F[x] - \{0\}$. We shall give some more interesting examples here (all rings are commutative):

1. If R is an integral domain, then we can always take $D = R - \{0\}$. The ring $D^{-1}R$ is then always a field, and is called the *field of fractions of* R, and is sometimes denoted Q. Then for any smaller multiplicatively closed subset E, $E^{-1}R$ is a subring of Q with elements $r/e \in Q$ with $r \in R$ and $e \in E$
2. Let R be a ring and $f \in R$. Define $D = \{f^n \mid n \in \mathbb{Z}_{\geq 0}\}$. Then we will denote $D^{-1}R = R_f$. Then R_f is a ring in which the element f has become a unit. In a sense, it is now possible to solve the question
$$fx - 1 = 0$$
In fact, this intuition can be made more rigorous showing that
$$R_f \cong \frac{R[x]}{fx - 1}$$
This is similar to how we worked with field extensions, and in fact is an important link to connect the intuition of localization to a geometric intuition. Keep this example in the back of your mind for now.
3. Consider $R = k[x, y]/(xy)$, take $\overline{x} \in R$, and consider $R_{\overline{x}}$. Then the the map $\iota : R \to R_{\overline{x}}$ is no longer injective as:
$$\overline{y} = \frac{\overline{xy}}{\overline{x}} = \frac{\overline{0}}{\overline{x}} = \overline{0}$$
4. This example is called *localizing at a prime*. Let R be a ring and P a prime ideal of R. Then the set $D = R - P$ is multiplicatively closed. To see that, let $x, y \in D$. If it were the case that $xy \in P$, then either $x \in P$ or $y \in P$. But then one of them would not be in D, a contradiction. Thus, D is indeed multiplicatively closed. The localization $D^{-1}R$ is called the *localization of* R *at* P and is commonly denoted as R_P. In this ring, all elements not in P become units. As a simple example, take $R = \mathbb{Z}$ and $P = (p)$ for some prime p. Then by the nice divisibility properties of integers, the set $\mathbb{Z}_{(p)}$ can with a little work be shown to be:
$$\mathbb{Z}_{(p)} = \left\{ \frac{a}{b} \in \mathbb{Q} \;\middle|\; p \nmid b \right\}$$

that is, it is all elements of $\mathbb{Q}$ for which the denominator is not divisible by p. Can you prove that $\mathbb{Z}_{(p)}$ has only one maximal ideal (and hence, is a local ring)? Is this true of all localization at primes?

It is tempting to say that if $R_{(p)}$ is the localization of a ring R at the prime p and $a/b \in R_{(p)}$ if $b \notin (p)$, however this is not necessarily the case as we are dealing with an equivalence class! The reader may then ask if we can take a better representative (like the representative a/b in $\mathbb{Z}$ such that $\gcd(a,b) = 1$), however R is not necessarily a UFD and so this may not be well-defined.

5. The following examples is a way to "localise" functions. Let k be a field and V be any set. Define R to be functions from V to k containing the constant functions ($F \subseteq \mathrm{Hom}_{\mathbf{Set}}^{+\text{ constants}}(V,k)$) with $+$ and $\cdot$ defined by component-wise addition and multiplication on the image: $R = (F, +, \cdot)$. For example, take all continuous functions from $[0,1]$ to $\mathbb{R}$. For any $a \in V$, let $M_a \subseteq R$ be the set of all functions that vanish at a: $f(a) = 0$. Then M_a is the kernel of the evaluation map from R to k:

$$\mathrm{ev}_a : R \to k \qquad f \mapsto f(a) \qquad \ker(\mathrm{ev}_a) = M_a$$

Since R contains constant functions, ev_a is surjective and so $k \cong R/M_a$. By proposition 9.4.19, M_a is a maximal idea, and hence a prime ideal. Thus, we can define the localization of R at M_a to be:

$$R_{M_a} = \left\{ \frac{f}{g} \;\middle|\; f, g \in R,\ g(a) \neq 0 \right\}$$

where ev_a is extended as:

$$(f/g)(a) = f(a)/g(a)$$

This then makes R_{M_a} a way of defining rational functions.

6. Let $R = \mathbb{C}[x]$, and take $p = (x-a)$. Since $\mathbb{C}[x]$ is a Principal Ideal Domain and $(x-a)$ is irreducible, $(x-a)$ is prime, and so we can define

$$\mathbb{C}[x]_{(x-a)} = \left\{ p(x)/q(x) \;\middle|\; x - a \not| q(x) \right\}$$

which can be thought of all rational functions which do not vanish at a.

Localization has many nice geometric interpretations. As we will see in section 32.4, all algebraic varieties (i.e. irreducible algebraic sets) are related to the prime ideals. Hence, understanding how ideals of R correspond to ideals of $D^{-1}R$ will bring us to understanding a geometric connection.

For an ideal $I \subseteq R$, its *extension* ${}^{\iota}I$ is the ideal of $D^{-1}R$ generated by $\iota(I)$; since every such element can be written as a/d with $a \in I$ and $d \in D$, the notation $D^{-1}I$ is also used. For an ideal $J \subseteq D^{-1}R$, its *contraction* ${}^{\pi}J = \iota^{-1}(J)$ is an ideal of R, being the preimage of an ideal under the ring homomorphism ι.

Proposition 23.4.5: Ideals of Localization

Let R be a ring and $D^{-1}R$ be the localization of R at D for appropriate D. Then:

1. For every ideal $J \subseteq D^{-1}R$,
$$J = J^{ce}$$
As a consequence, every ideal of $D^{-1}R$ is an extension of an ideal in R, and every ideal of D^{-1} contracts to a distinct ideal in R

2. If $I \subseteq R$ is an ideal of R, then:
$$^{\pi}(^{\iota}I) = \{r \in R \mid dr \in I \text{ for some } d \in D\}$$
As a consequence, $I^e = D^{-1}R$ if and only if $I \cap D \neq \emptyset$

3. There is a bijection between the set of prime ideals with $P \cap D = \emptyset$ and the set of prime ideals of $D^{-1}R$:
$$\left\{\begin{matrix}\text{prime ideals of } R \text{ with} \\ P \cap D = \emptyset\end{matrix}\right\} \underset{(-)^c}{\overset{(-)^e}{\rightleftarrows}} \{\text{prime ideals of } D^{-1}R\}$$

4. If R is Noetherian, then $D^{-1}R$ is Noetherian. Similarly if R is Artinian

***Proof*:**

1. Notice that by construction, $^{\iota}(^{\pi}J) \subseteq J$. For the other direction, notice that for any $a/d \in J$ it is always the case that $a/1 = d(a/d) \in J$, that is there exists a a/d such that $d(a/d) = a/1$. Since $\iota(\pi(a/d)) = a/1$. and so by definition, of $^{\iota}(^{\pi}J)$, $(1/d)(a/1) = a/d \in {}^{\iota}(^{\pi}J)$ (since it closed by multiplication of elements from $D^{-1}R$.

2. Let $I' = \{r \in R \mid dr \in I \text{ for some } d \in D\}$ be the set in the question. We will show $I' = {}^{\pi}(\lim I)$. For the $\subseteq$ direction, take $r \in I'$. Then by definition there exists a $d \in D$ such that $dr = a \in I$. Then $r/1 = a/d \in \lim I$, so contracting we get $r \in {}^{\pi}(\lim I)$. For the $\supseteq$ direction, take $r \in {}^{\pi}(\lim I)$. Then $r/1 = a/d \in \lim I$ for some $a \in I$ and $d \in D$. Then by the definition of the equivalence class, we have $x(dr - a) = 0$ for some $x \in D$, and hence $xdr = xa$ where $xa \in I$. Since $xd \in D$, $r \in I'$. The rest of the assertions of (2) follow quickly.

3. To map prime ideals from $D^{-1}R$ to R, recall that preimages of prime ideals are prime. Thus, by construction, the contraction must map prime ideals of $D^{-1}R$ to prime ideals that are disjoint from D.

   For the converse, let P be a prime ideal of R that is disjoint from D, and consider $Q = {}^{\iota}P$. We will show Q is prime. Suppose $(a/d_1)(b/d_2) = (ab/d_1d_2) \in Q$. Then $ab/d_1d_2 = c/d$ for some $c \in P$ and $d \in D$. Then by definition of the equivalent relation, $x(dab - d_1d_2c) = 0$ for some $x \in D$. Since $xdab - xd_1d_2c = 0 \in P$ and P is closed under subtraction and left-multiplication of elements of R, it must be that $xdab = (xd)(ab) \in P$. Since P is disjoint from D, it must be that $ab \in P$. Since P is prime, either a or b is an element of P. Thus, either a/d_1 or b/d_2 is an element of Q, showing that Q is a prime ideal. Thus,

extending prime ideals that are disjoint from D map to prime ideals in $D^{-1}R$.

Finally, by (2), since P is disjoint from D we have $P = {}^{\pi}({}^{\iota}P)$, showing that extending and contracting are inverses of each other, finishing the proof for (3).

4. Given some ascending chain of ideals in $D^{-1}R$, they contract to ascending chain of ideals in R. Since R is Noetherian, they stabilize. Thus, the ideals that get contracted must also stabilize. Similarly for Artinian Rings.

The ideal in part (2) of proposition 23.4.5 is given a name:

Definition 23.4.6: Saturated Ideal

Let R be a commutative ring, $I \subseteq R$ is an ideal and $D^{-1}R$ is the localization of R at D for appropriate D. Then *saturation* of the ideal I with respect to D is ${}^{\pi}(\lim I)$. If $I = {}^{\pi}(\lim I)$, then I is said to be *saturated* or *D-saturated* with respect to D

Geometrically, the prime-ideal bijection of proposition 23.4.5(3) identifies $\operatorname{Spec}(D^{-1}R)$ with the subspace of $\operatorname{Spec} R$ consisting of the primes disjoint from D. For $D = \{f^n \mid n \in \mathbb{Z}_{\geq 0}\}$ this is the distinguished open set $D(f) = \{\mathfrak{p} \in \operatorname{Spec} R \mid f \notin \mathfrak{p}\}$, so $\operatorname{Spec} R_f \cong D(f)$; dually $\operatorname{Spec} R/(f) \cong V(f)$, the closed set of primes containing f. Thus $\operatorname{Spec} R = D(f) \sqcup V(f)$ as sets, the two pieces being homeomorphic to $\operatorname{Spec} R_f$ and $\operatorname{Spec} R/(f)$ as subspaces (though $\operatorname{Spec} R$ is their topological coproduct only when $D(f)$ is also closed).

Proposition 23.4.7: Localization Property Preservation

Let R be a ring, $D \subseteq R$ a multiplicative set with $0 \notin D$, and $D^{-1}R$ the localization. Then the following properties of R are preserved in $D^{-1}R$:

1. no zero divisors
2. Noetherian
3. Integrally closed

For (3), R is understood to be an integrally closed domain, so that (1) makes $D^{-1}R$ a domain with the same fraction field.

***Proof*:**

1. Suppose $(a/s)(b/t) = 0$ in $D^{-1}R$. Then $uab = 0$ for some $u \in D$ by corollary 23.4.3, and $u \neq 0$ because $0 \notin D$, so $ab = 0$ in the domain R and hence $a = 0$ or $b = 0$. Thus $a/s = 0$ or $b/t = 0$.
2. Let $J \subseteq D^{-1}R$ be an ideal and put $I = \iota^{-1}(J)$, where $\iota\colon R \to D^{-1}R$. By proposition 23.4.5 every ideal of the localization is the extension of its contraction, so $J = D^{-1}I$. Since R is Noetherian, $I = (a_1, \ldots, a_n)$ for finitely many a_i, and then J is generated by $a_1/1, \ldots, a_n/1$: an element of J is a/s with $a \in I$, and writing $a = \sum r_i a_i$ gives $a/s = \sum (r_i/s)(a_i/1)$. Every ideal of $D^{-1}R$ is therefore finitely generated.
3. Write $K = \operatorname{Frac}(R)$, which by (1) is also the fraction field of $D^{-1}R$. Let $z \in K$ be integral

over $D^{-1}R$, say

$$z^n + \frac{a_{n-1}}{s_{n-1}} z^{n-1} + \cdots + \frac{a_1}{s_1} z + \frac{a_0}{s_0} = 0$$

with $a_i \in R$ and $s_i \in D$. Put $s = s_0 s_1 \cdots s_{n-1} \in D$ and multiply the relation by s^n, collecting powers of sz:

$$(sz)^n + \sum_{i=1}^{n} \frac{a_{n-i}\, s^i}{s_{n-i}} (sz)^{n-i} = 0$$

Each coefficient lies in R, since $s^i / s_{n-i} = s^{i-1} \prod_{j \neq n-i} s_j$ and $i \geq 1$. So sz is integral over R, hence $sz \in R$ because R is integrally closed, and therefore $z = (sz)/s \in D^{-1}R$, as we sought to show.

Exercise 23.4.1

1. Let R be a ring, f be an element of R ,and R_f be the localization of R at $\{f^n \mid n \in \mathbb{Z}_{\geq 0}\}$. Then
   1. $$R_f \cong \frac{R[x]}{fx - 1}$$
   2. $R_f \cong R_{f^n}$ for $n \geq 1$
   3. If f is nilpotent, then $R_f = 0$
2. Let R be a normal domain and S a multiplicatively closed set. Then $S^{-1}R$ is a normal domain

23.4.2 Localization of Modules

Since every ring is a module over itself, we can see how localization works for this special case of modules. We extend the concept of localization now to more general modules. The construction is essentially the same thing: if M is an R-module, and $D \subseteq R$ is multiplicatively closed, define the same equivalence class on $M \times D$ and the operation's on $(M \times D)/\sim$ as

$$\frac{m}{d} + \frac{m'}{d'} = \frac{d'm + dm'}{dd'} \quad \text{and} \quad r \cdot \frac{m}{d} = \frac{r \cdot m}{d}$$

Then this is indeed a module with the proof proceeeding essentially the same as theorem 23.4.1, and so is left as a sanity check. Just like $R[D^{-1}]$ is the localization of R at D, we will denote $M[D^{-1}]$ to be the localization of M at D. Thus, an R-module M is extended to an $D^{-1}R$-module $M[D^{-1}]$.

Proposition 23.4.8: Zeros of $M[D^{-1}]$

Let R be a ring, $D \subseteq R$ be a multiplicatively closed subset, and M be a module over R. Then m goes to 0 in $M[D^{-1}]$ if and only if m is annihilated by an element $d \in D$. If M is finitely generated, then $M[D^{-1}] = 0$ if and only if M is annihilated by an element in D.

If R lies in a field K and M is an R-module that is contained in a K-vector space, then $\iota : M \to M[D^{-1}]$ is injective iff $M \xrightarrow{\cdot s} M$ is injective for all $s \in D$.

***Proof*:**
Write $\iota\colon M \to M[D^{-1}]$ for the canonical map $m \mapsto m/1$. By the defining equivalence relation on $M \times D$, $m/1 = 0/1$ if and only if $d(1 \cdot m - 1 \cdot 0) = dm = 0$ for some $d \in D$. So $\iota(m) = 0$ if and only if m is annihilated by an element of D, which is the first claim.

Suppose M is generated by $m_1, \ldots, m_n$. If $M[D^{-1}] = 0$, then each $m_i/1 = 0$, so the first claim produces $d_i \in D$ with $d_i m_i = 0$. The product $d = d_1 \cdots d_n$ lies in D and annihilates every generator, hence $dM = 0$. Conversely, if $dM = 0$ for some $d \in D$, then every element of $M[D^{-1}]$ satisfies $m/s = (dm)/(ds) = 0/(ds) = 0$, so $M[D^{-1}] = 0$.

For the final claim, suppose multiplication by every $s \in D$ is injective on M, and let $\iota(m) = 0$. The first claim gives $s \in D$ with $sm = 0$, so $m = 0$, and ι is injective. Conversely, suppose ι is injective, and let $sm = 0$ with $s \in D$ and $m \in M$. The first claim gives $\iota(m) = 0$, so $m = 0$, and multiplication by s is injective on M.

Localization modules works well with homomorphisms: let $\varphi : M \to N$ be an R-module homomorphism. Then by the universal property, we see that this is extended to an $D^{-1}R$-module homomorphism $D^{-1}\varphi : M[D^{-1}] \to N[D^{-1}]$ by mapping:

$$D^{-1}\varphi\left(\frac{m}{d}\right) = \frac{\varphi(m)}{d}$$

Furthermore, $D^{-1}(\varphi \circ \psi) = (D^{-1}\varphi) \circ (D^{-1}\psi)$, i.e. $D^{-1}(-)$ is a functor from Mod_R to $\mathrm{Mod}_{D^{-1}R}$. We may ask for certain properties of this functor, most basic perhaps would be if $D^{-1}(-)$ is an exact functor, that it preserves kernels and cokernels. This is the case:

Proposition 23.4.9: Localization Is Exact

Let M_1, M_2, M_3 be R-modules such that $0 \to M_1 \xrightarrow{f} M_2 \xrightarrow{g} M_3 \to 0$ is a short exact sequence. Then

$$0 \to M_1[D^{-1}] \xrightarrow{D^{-1}f} M_2[D^{-1}] \xrightarrow{D^{-1}g} M_3[D^{-1}] \to 0$$

is a short exact sequence, that is $D^{-1}(___)$ is an exact functor.

***Proof*:**
Since $g \circ f = 0$, $D^{-1}g \circ D^{-1}f = D^{-1}(0) = 0$, and so $\mathrm{im}(D^{-1}f) \subseteq \ker(D^{-1}g)$. For the reverse inclusion, let $m/d \in \ker(D^{-1}g)$ so that $g\left(\frac{m}{d}\right) = \frac{g(m)}{d} = 0$ in $M_3[D^{-1}]$. Thus, there exists an s such that $sg(m) = 0$ in M_3. Since g is an R-module homomorphism, $sg(m) = g(sm)$, and so $sm \in \ker(g) = \mathrm{im}(f)$, implying for some $m' \in M_1$, $f(m') = sm$. Putting it all together, we get that in $M_2[D^{-1}]$:

$$\frac{m}{d} = \frac{f(m')}{ds} = (D^{-1}f)\left(\frac{m'}{ds}\right) \in \mathrm{im}(D^{-1}f)$$

showing that $\ker(D^{-1}g) \subseteq \mathrm{im}(D^{-1}f)$, which along with the fact that $\mathrm{im}(D^{-1}f) \subseteq \ker(D^{-1}g)$ show's that

$$\ker(D^{-1}g) = \mathrm{im}(D^{-1}f)$$

For exactness at the ends: if $(D^{-1}f)(m/d) = f(m)/d = 0$ then $sf(m) = f(sm) = 0$ for some $s \in D$, and injectivity of f gives $sm = 0$, so $m/d = 0$; thus $D^{-1}f$ is injective. And any m_3/d equals $(D^{-1}g)(m_2/d)$ where $g(m_2) = m_3$ (surjectivity of g), so $D^{-1}g$ is surjective. Hence the localized sequence is short exact, completing the proof.

Notice that as we are defining a $D^{-1}R$-module, we are extending scalars. If we use section 17.5, then we can use the following observation to arrive at this result more quickly:

Proposition 23.4.10: Characterization of Localization

Let M be an R-module and $M[D^{-1}]$ a localiation. Then:

$$M[D^{-1}] \cong_R D^{-1}R \otimes_R M$$

***Proof*:**
Define the map:

$$(r/d) \times m \mapsto \frac{r \cdot m}{d}$$

then it is easy to that this map is R-bilinear, and hence by the universal property of the tensor-product, there exists an R-module homomorphism:

$$f : D^{-1}R \otimes M \to M[D^{-1}]$$

It is clear that f is surjective and is uniquely defined with respect to the universal property. It remains to check that f is injective. First, show that for any element in $D^{-1}R \otimes M$, it can be written as:

$$\frac{1}{d} \otimes m$$

for some $d \in D$ and $m \in M$. Let's say $f(1/d \otimes m) = m/d = 0$. Then $sm = 0$ for some $s \in D$. Then:

$$\frac{1}{d} \otimes m = \frac{s}{ds} \otimes m = \frac{1}{ds} \otimes sm = \frac{1}{ds} \otimes 0 = 0$$

showing that f is injective, and hence an R-module isomorphism, completing the proof.

As a direct conssequence, $D^{-1}R$ is a *flat R-module.*

Corollary 23.4.11: Localization Commuting With Tensor

Let M and N be R-modules and $D \subseteq R$ multiplicatively closed. Then there is a unique isomorphism:

$$\varphi : M[D^{-1}] \otimes_{D^{-1}R} N[D^{-1}] \to (M \otimes_R N)[D^{-1}] \qquad (m/d) \otimes (n/s) \mapsto (m \otimes n)/ds$$

In particular, if $\mathfrak{p}$ is any prime ideal:

$$M_{\mathfrak{p}} \otimes_{R_{\mathfrak{p}}} N_{\mathfrak{p}} \cong (M \otimes_R N)_{\mathfrak{p}}$$

***Proof*:**
By proposition 23.4.10, localizing is base change along $R \to D^{-1}R$, so $M[D^{-1}] = D^{-1}R \otimes_R M$. Associativity of the tensor product then gives

$$M[D^{-1}] \otimes_{D^{-1}R} N[D^{-1}] \cong D^{-1}R \otimes_R (M \otimes_R N) = (M \otimes_R N)[D^{-1}],$$

and the prime-ideal case is the special case $D = R \setminus \mathfrak{p}$.

(Some more cool results from Micheal's p. 43)

23.4.3 Local Properties

Localization allows us to diminish our problem to a ring much closer to a field, in particular if we want to study a family of prime ideals contained in some prime ideal p. In fact, there are many results about rings that can be deduced by studying rings *locally*, namely by studying rings at each prime ideal[1]. This motivates the following concept:

Definition 23.4.12: Local Properties

Let P be a property of a ring (ex. commutative, free, etc.). Then a property P of a ring R (resp. of an R-module M) is called a *local property* if it respects the following:

R (resp. M) has property $P \Leftrightarrow R_p$ (resp. M_p) has property P for each prime ideal $p \subseteq R$

In otherwords, a property is local if we can move back and forth between studying any ring (resp. module) localized at a prime. Here are some examples of local properties:

Proposition 23.4.13: Zero Module Is A Local Property

Let M be an R-module. Then the following are equivalent:

1. $M = 0$
2. $M_p = 0$ for all prime ideals $p \subseteq R$
3. $M_m = 0$ for all maximal ideal $m \subseteq R$

***Proof*:**
Certainy (1) $\Rightarrow$ (2) $\Rightarrow$ (3). For (3) $\Rightarrow$ (1), let $0 \neq x \in M$ be a nonzero element of an R-module M with $0 \neq 1$. Let $I = \text{Ann}(x)$. Then I is contained in some maximal ideal m: $I \subseteq m$. Consider M_m. Since $M_m = 0$, $x/1 = 0$, implying $rx = 0$ for some $r \in R - m$. Howver $\text{Ann}(x) \subseteq m$, meaning no such element can exist, a contradiction, showing that $M = 0$ as we sought to show.

Another property that only needs to be verified locally is the injectivity/surjectivity of a function:

Proposition 23.4.14: Injectivity/Surjectivity/Isomorphism Is A Local Property

Let $\varphi : M \to N$ be an R-module homomorphism. Then the following are equivalent:

1. φ is an injection/surjection/isomorphism
2. $\varphi_p : M_p \to N_p$ is injection/surjection/isomorphism for all prime ideals $p \subseteq R$
3. $\varphi_m : M_m \to N_m$ is injection/surjection/isomorphism for all maximal ideals $m \subseteq R$

[1]This observation is at the basis of interpreting rings as geometric objects

***Proof*:**
Let $K = \ker\varphi$ and $Q = N/\varphi(M)$. Localizing the short exact sequences $0 \to K \to M \to \varphi(M) \to 0$ and $0 \to \varphi(M) \to N \to Q \to 0$ at a prime p (proposition 23.4.9) shows that φ_p, which is the composite $M_p \to \varphi(M)_p \to N_p$, has kernel K_p and cokernel Q_p.

- *Injectivity.* If φ is injective, then $K = 0$, so $K_p = 0$ and φ_p is injective for every prime p, which gives (1) $\Rightarrow$ (2). Every maximal ideal is prime (corollary 9.4.26), which gives (2) $\Rightarrow$ (3). If φ_m is injective for every maximal ideal m, then $K_m = 0$ for every m, so $K = 0$ by proposition 23.4.13, which gives (3) $\Rightarrow$ (1).
- *Surjectivity.* If φ is surjective, then $Q = 0$, so $Q_p = 0$ and φ_p is surjective for every prime p, and (2) $\Rightarrow$ (3) holds as before. If φ_m is surjective for every maximal ideal m, then $Q_m = 0$ for every m, so $Q = 0$ by proposition 23.4.13 and φ is surjective.
- *Isomorphism.* A homomorphism is an isomorphism exactly when it is injective and surjective, so this case follows from the other two, completing the proof.

Corollary 23.4.15: Exactness Is A Local Property

Let $A \xrightarrow{f} B \xrightarrow{g} C$ be a sequence of R-module homomorphisms. Then it is exact if and only if $A_\mathfrak{m} \xrightarrow{f_\mathfrak{m}} B_\mathfrak{m} \xrightarrow{g_\mathfrak{m}} C_\mathfrak{m}$ is exact for every maximal ideal $\mathfrak{m} \subseteq R$.

***Proof*:**
Exactness at B says the homology $H = \ker g/\mathrm{im} f$ vanishes. Localization is exact (proposition 23.4.9), so it commutes with kernels, images, and quotients, giving $H_\mathfrak{m} = \ker g_\mathfrak{m}/\mathrm{im} f_\mathfrak{m}$. By proposition 23.4.13, $H = 0$ iff $H_\mathfrak{m} = 0$ for every maximal $\mathfrak{m}$, which is exactness of the localized sequences.

A final example that will be useful is that flatness is a local property:

Proposition 23.4.16: Flatness Is A Local Property

Let M be an R-module. Then the following are equivalent:

1. M is a flat R-module
2. M_p is a flat R_p-module for each prime ideal $p \subseteq R$
3. M_m is a flat R_m-module for each maximal ideal $m \subseteq R$

***Proof*:**
(1) $\Rightarrow$ (2): let $f\colon N' \to N$ be an injective homomorphism of R_p-modules, regarded also as R-modules. Every element of $R - p$ acts invertibly on an R_p-module, hence on $N' \otimes_R M$ and on $N \otimes_R M$, so each of these modules maps isomorphically onto its localization at p, and $N'_p = N'$, $N_p = N$. Corollary 23.4.11 then gives isomorphisms $N' \otimes_{R_p} M_p \cong N' \otimes_R M$ and $N \otimes_{R_p} M_p \cong N \otimes_R M$, natural in the module. As M is flat over R, $f \otimes_R \mathrm{id}_M$ is injective, hence so is $f \otimes_{R_p} \mathrm{id}_{M_p}$, and M_p is flat over R_p.

(2) ⇒ (3) is immediate, since every maximal ideal is prime. For (3) ⇒ (1), let $N \to P$ be any R-module homomorphism and $m \subseteq R$ any maximal ideal. Then:

$$\begin{aligned}
N \to P \text{ is injective} &\Rightarrow N_m \to P_m \text{ is injective} && \text{proposition 23.4.14}\\
&\Rightarrow N_m \otimes_{R_m} M_m \to P_m \otimes_{R_m} M_m \text{ is injective} && \text{flatness property}\\
&\Rightarrow (N \otimes_R M)_m \to (P \otimes_R M)_m \text{ is injective} && \text{corollary 23.4.11}\\
&\Rightarrow N \otimes_R M \to P \otimes_R M \text{ is injective} && \text{proposition 23.4.14}
\end{aligned}$$

Hence, M is flat.

Proposition 23.4.17: Integral Closure Is A Local Property

Let R be an integral domain. Then the following are equivalent:

1. R is integrally closed
2. R_p is integrally closed for each prime ideal $p \subseteq R$
3. R_m is integrally closed for each maximal ideal $m \subseteq R$

***Proof*:**
Write $K = \mathrm{Frac}(R)$, and let $p \subseteq R$ be any prime. The set $D = R - p$ is multiplicatively closed because p is prime, and $0 \notin D$ because $0 \in p$. By corollary 23.4.3 the map $R \to R_p$ is injective, and by proposition 23.4.7(1) the ring R_p has no zero divisors; its fraction field is K, since $R \subseteq R_p \subseteq K$ and every element of K is already a ratio of elements of R. We therefore regard $R \subseteq R_p \subseteq K$ with $\mathrm{Frac}(R_p) = K$.

(1) ⇒ (2): this is proposition 23.4.7(3) applied to $D = R - p$.

(2) ⇒ (3): every maximal ideal is prime (corollary 9.4.26).

(3) ⇒ (1): let $z \in K$ be integral over R, say

$$z^n + a_{n-1}z^{n-1} + \cdots + a_1 z + a_0 = 0$$

with $a_i \in R$. For every maximal ideal $m \subseteq R$ the coefficients lie in R_m, so the same equation shows z is integral over R_m, and (3) gives $z \in R_m$. Consider the ideal of denominators $I = \{a \in R \mid az \in R\}$. For each maximal ideal m, write $z = r/s$ with $r \in R$ and $s \in R - m$. Then $sz = r \in R$, so $s \in I$ and $s \notin m$, and hence $I \not\subseteq m$. An ideal contained in no maximal ideal cannot be proper (proposition 9.4.18), so $I = R$. In particular $1 \in I$, so $z = 1 \cdot z \in R$, showing R is integrally closed.

The following is a way of proving results locally:

Proposition 23.4.18: Local Properties On Modules

Let R be a subring of a field k, and let M be an R-module contained in a k-vector space V (equiv. the map $M \to M \otimes_R k$ is injective). Then:

$$M = \bigcap_{\mathfrak{m}} M_{\mathfrak{m}} = \bigcap_{\mathfrak{p}} M_{\mathfrak{p}}$$

***Proof*:**
All the modules in the statement are taken inside V. For a prime $\mathfrak{p}$, the elements of $R - \mathfrak{p}$ are nonzero in the field k, and $M_{\mathfrak{p}}$ is identified with the $R_{\mathfrak{p}}$-submodule $\left\{s^{-1}x \;\middle|\; x \in M,\ s \in R - \mathfrak{p}\right\}$ of V: the map $M_{\mathfrak{p}} \to V$, $x/s \mapsto s^{-1}x$, is well defined and injective because a nonzero element of R acts invertibly on V. Each $x \in M$ equals $1^{-1}x$, so

$$M \subseteq \bigcap_{\mathfrak{p}} M_{\mathfrak{p}} \subseteq \bigcap_{\mathfrak{m}} M_{\mathfrak{m}}$$

the second inclusion because every maximal ideal is prime (corollary 9.4.26).

For the reverse inclusion, let $x \in \bigcap_{\mathfrak{m}} M_{\mathfrak{m}}$ and let $I = \{a \in R \mid ax \in M\}$, an ideal of R. For each maximal ideal $\mathfrak{m}$, write $x = s^{-1}y$ with $y \in M$ and $s \in R - \mathfrak{m}$. Then $sx = y \in M$, so $s \in I$ and $I \not\subseteq \mathfrak{m}$. An ideal contained in no maximal ideal is not proper (proposition 9.4.18), so $I = R$ and $x = 1 \cdot x \in M$. Thus $\bigcap_{\mathfrak{m}} M_{\mathfrak{m}} \subseteq M$, and the displayed inclusions give $M = \bigcap_{\mathfrak{m}} M_{\mathfrak{m}} = \bigcap_{\mathfrak{p}} M_{\mathfrak{p}}$, as claimed.

Corollary 23.4.19: Local Properties Of Ideals

Let R be an integral domain. Then every ideal $I \subseteq R$ is equal to the intersection of its localizations at the maximal ideals of R, and also to the intersections of its localization at the prime ideals of R

***Proof*:**
The domain R is a subring of its fraction field $k = \mathrm{Frac}(R)$, and I is an R-module contained in the k-vector space k. So proposition 23.4.18 applies with $M = I$ and $V = k$, and gives $I = \bigcap_{\mathfrak{m}} I_{\mathfrak{m}} = \bigcap_{\mathfrak{p}} I_{\mathfrak{p}}$, with the localizations taken inside k, as claimed.

Hence, to show a property of an ideal I in an integral domain R, it suffices to show that the properly holds for all its localization $I_{\mathfrak{p}}$ and it is preserved under intersections.

Exercise 23.4.2

1. Show that M is projective if and only if each M_p is free.

23.4.4 Local Rings

Recall that the localization of $\mathbb{Z}$ at any prime ideal (p), $\mathbb{Z}_{(p)}$, has a unique maximal ideal. It was left as an exercise to see whether any localization at a prime, R_p left R with only a single maximal ideal. This is indeed the case, meaning there is a unique field associated to R_p, letting us study R in terms of the collection of field induced by R_p. Thus, for any integral domain R, we can always produce a collection of rings that only have a single maximal ideal $\mathfrak{m}_\mathfrak{p}$. Once we interpret a ring as a geometric object $\operatorname{Spec}(R)$, we shall see that the rings $R_\mathfrak{p}$ representing the local properties of $\operatorname{Spec}(R)$, not unlike how we have stalks at a point in Differential Geometry. Due to this, it is worth-while studying rings with a unique maximal ideal:

Definition 23.4.20: Local Ring

Let R be a commutative ring. Then R is a *local ring* if it has a unique maximal ideal.

Every field is a local ring, its unique maximal ideal being (0). The definition is enlightening: if R is local with maximal ideal $\mathfrak{m}$ and $x \notin \mathfrak{m}$, then x must be a unit, since otherwise (x) is a proper ideal and so lies in a maximal ideal, forcing $x \in \mathfrak{m}$. Conversely, if the non-units of R form an ideal then that ideal is the unique maximal ideal, so R is local.

Example 23.4.21: Local Rings

1. Every field is trivially a local ring.
2. $\mathbb{Z}/p^n\mathbb{Z}$ is a local ring with $n > 1$ with maximal ideal $\overline{p}$
3. if $f \in k[x]$ is irreducible then $k[x]/(f(x)^n)$ is a local ring with maximal ideal $\overline{(f(x))}$
4. (geometric example) Let M be a smooth manifold (real or complex). Then define $\mathcal{O}_{M,x}$ to be the germ of smooth functions at x, that is, two smooth functions $f, g \in C^\infty(M)$ are in the same equivalence relation $f \sim g$ (i.e. $[f] = [g]$ are the same germ) if there exists some open set $U \subseteq M$ containing x such that $f|_U = g|_U$. Clearly, $\mathcal{O}_{M,x}$ is a ring (using the ring operation of the codomain $\mathbb{R}$ or $\mathbb{C}$). The maximal ideal of $\mathcal{O}_{M,x}$ are those functions that are 0 at x

In fact, this last example will have a direct parallel in scheme theory, see [13].

Proposition 23.4.22: Local Ring Equivalences

Let R be a commutative ring with $1 \neq 0$. Then the following are equivalent:

1. R is a local ring.
2. the sum of any two non-units is a non-unit
3. for every $x \in R$, either x is a unit or $1 - x$ is a unit
4. if a finite sum is a unit, then one of its terms is a unit

***Proof*:**
(1) $\Rightarrow$ (2): if R is local with maximal ideal $\mathfrak{m}$, an element is a non-unit iff it generates a proper ideal iff it lies in $\mathfrak{m}$, so the non-units are exactly $\mathfrak{m}$, which is closed under addition.

(2) $\Rightarrow$ (4): if a finite sum is a unit but no term is, then every term is a non-unit, so by (2) the sum is a non-unit, a contradiction.

(4) $\Rightarrow$ (3): apply (4) to $x + (1 - x) = 1$.

(3) $\Rightarrow$ (1): let $\mathfrak{m}$ be the set of non-units; it absorbs multiplication by R. If $x, y \in \mathfrak{m}$ had a unit sum $u = x + y$, then $1 = u^{-1}x + u^{-1}y$, so by (3) one of $u^{-1}x, u^{-1}y$ is a unit, making x or y a unit, a contradiction. Hence $\mathfrak{m}$ is closed under addition and is an ideal. Every proper ideal consists of non-units, hence lies in $\mathfrak{m}$, so $\mathfrak{m}$ is the unique maximal ideal and R is local.

Using localization and quotienting, we have a large amount of control over the prime ideals we want to work with: given a (commutative) ring R, passing to R_p eliminates all prime ideals except those contained in p, while passing to R/p eliminates all prime ideals except those containing p. This can be visualized like so:



Hence, R_p/q^e (resp. $(R/p)_{\overline{q}}$) will only keep all the ideals between p and q, and if $p = q$, then the result is a field, known as the *residue field*:

Definition 23.4.23: Residue Field

Let R be a commutative local ring with maximal ideal m. Then R/m is called the *residue field*.

The quotient $R/\mathfrak{p}$ and the ring $R_\mathfrak{p}$ are canonically related: the residue field of $R_\mathfrak{p}$ can be thought of as the localization of $R/\mathfrak{p}$ at $\overline{0}$:


Proposition 23.4.24: Localization and Quotient Commute

Let $\mathfrak{p} \subseteq R$ be a prime ideal of a ring R, and let $\mathfrak{m}_\mathfrak{p}$ be the unique maximal ideal of $R_\mathfrak{p}$. Then localizing at $\mathfrak{p}$ and then quotienting by $\mathfrak{m}_\mathfrak{p}$ is isomorphic to quotienting by $\mathfrak{p}$ and then localizing (at $\overline{\mathfrak{p}} = \overline{0}$, that is, passing to the field of fractions). In particular there is a canonical embedding:

$$R/\mathfrak{p} \hookrightarrow R_\mathfrak{p}/\mathfrak{m}_\mathfrak{p}$$

that extends to an isomorphism from the field of fractions of $R/\mathfrak{p}$ onto $R_\mathfrak{p}/\mathfrak{m}_\mathfrak{p}$

This may be visualized as the following diagram:



***Proof*:**
Write $D = R - \mathfrak{p}$ and $\iota\colon R \to R_\mathfrak{p}$ for the canonical map. First, $\mathfrak{m}_\mathfrak{p} = {}^\iota\mathfrak{p} = \mathfrak{p}R_\mathfrak{p}$. Indeed, let $J \subseteq R_\mathfrak{p}$ be a proper ideal. By proposition 23.4.5(1), $J = {}^\iota({}^\pi J)$, and ${}^\pi J$ must be disjoint from D, for otherwise proposition 23.4.5(2) would give $J = {}^\iota({}^\pi J) = R_\mathfrak{p}$. Disjointness from D means ${}^\pi J \subseteq \mathfrak{p}$, and extending this inclusion gives $J \subseteq {}^\iota\mathfrak{p}$. The ideal ${}^\iota\mathfrak{p}$ is itself proper by proposition 23.4.5(2), since $\mathfrak{p} \cap D = \emptyset$. Every proper ideal of $R_\mathfrak{p}$ is therefore contained in the proper ideal ${}^\iota\mathfrak{p}$, so ${}^\iota\mathfrak{p}$ is the unique maximal ideal of $R_\mathfrak{p}$.

Since $\mathfrak{p}$ is prime, $R/\mathfrak{p}$ is an integral domain (proposition 9.4.25). Write $K(R/\mathfrak{p})$ for its field of fractions and $\overline{r}$ for the image of $r \in R$ in $R/\mathfrak{p}$. The composite $\psi\colon R \to R/\mathfrak{p} \to K(R/\mathfrak{p})$ sends each $s \in D$ to $\overline{s} \neq 0$, a unit of the field $K(R/\mathfrak{p})$. By theorem 23.4.1 there is a unique ring homomorphism $\Psi\colon R_\mathfrak{p} \to K(R/\mathfrak{p})$ with $\Psi \circ \iota = \psi$, and since $r/s = \iota(r)\iota(s)^{-1}$ in $R_\mathfrak{p}$ and ring homomorphisms preserve inverses,

$$\Psi\left(\frac{r}{s}\right) = \psi(r)\psi(s)^{-1} = \overline{r}\,\overline{s}^{-1}$$

Ψ is surjective: an element of $K(R/\mathfrak{p})$ has the form $\overline{r}/\overline{s}$ with $\overline{s} \neq 0$, and any lifts $r \in R$, $s \in D$ exhibit it as $\Psi(r/s)$. The kernel of Ψ is $\mathfrak{m}_\mathfrak{p}$: if $r \in \mathfrak{p}$ then $\Psi(r/s) = \overline{r}\,\overline{s}^{-1} = 0$, and conversely $\overline{r}\,\overline{s}^{-1} = 0$ forces $\overline{r} = 0$, that is $r \in \mathfrak{p}$. Hence $\ker\Psi = \{r/s \mid r \in \mathfrak{p},\ s \in D\} = {}^\iota\mathfrak{p} = \mathfrak{m}_\mathfrak{p}$. By the first isomorphism theorem (theorem 9.3.12), Ψ induces an isomorphism $\overline{\Psi}\colon R_\mathfrak{p}/\mathfrak{m}_\mathfrak{p} \to K(R/\mathfrak{p})$.

Finally, the map $R/\mathfrak{p} \to R_\mathfrak{p}/\mathfrak{m}_\mathfrak{p}$ sending $\overline{r}$ to $r/1 + \mathfrak{m}_\mathfrak{p}$ is well defined and injective because $r/1 \in \mathfrak{m}_\mathfrak{p}$ if and only if $r \in \mathfrak{p}$. Indeed $r/1 \in {}^\iota\mathfrak{p}$ holds if and only if $r \in {}^\pi({}^\iota\mathfrak{p})$, since the contraction is the preimage under ι, and ${}^\pi({}^\iota\mathfrak{p}) = \{a \in R \mid da \in \mathfrak{p} \text{ for some } d \in D\}$ by proposition 23.4.5(2). This set contains $\mathfrak{p}$ (take $d = 1$) and is contained in $\mathfrak{p}$ because $da \in \mathfrak{p}$ with $d \notin \mathfrak{p}$ forces $a \in \mathfrak{p}$ by primality. Composing with $\overline{\Psi}$ sends $\overline{r}$ to $\Psi(r/1) = \overline{r} \in K(R/\mathfrak{p})$, so under $\overline{\Psi}$ the embedding becomes the inclusion of $R/\mathfrak{p}$ into its field of fractions. The inverse of $\overline{\Psi}$ therefore extends the embedding to an isomorphism from $K(R/\mathfrak{p})$ onto $R_\mathfrak{p}/\mathfrak{m}_\mathfrak{p}$, as claimed.

23.4.5 Nakayama's Lemma

(Atiyah Michael in Comm alg has some interesting results that feel are worth putting in here: p.21 on fin. gen modules)

As mentioned at the beginning, localization let's us get geometric information on a local level. Nakayama's lemma will be one way we translate that information to a global level. In this section, we will restrict to finitely generated modules (the infinite case is treated in the exercises).

Let's say M is a finitely generated module over R. If we were to localize M at a prime, we would get a local ring $R[D^{-1}]$. For simplicity, let's denote this ring G. As we have shown, G has only one maximal ideal m. Modding G by m, we get the field G/m. M over G/m is a vector-space, and so it has a basis. The heart of Nakayama's lemma is that this can be reversed: Using the basis of M over G/m, we can find a basis for M over G!

We will build this up in three steps, which are collectively called Nakayama's Lemma:

Definition 23.4.25: Jacobson Radical

Let R be a ring. Then the *Jacobson radical* of R, denoted $\text{Jac}(R)$, is the intersection of all maximal ideals of R:

$$\text{Jac}(R) = \bigcap_{\substack{M \subseteq R \\ \text{maximal}}} M$$

It is the analogue for rings of the Frattini subgroup of a group, the intersection of all maximal subgroups.

Proposition 23.4.26: Properties Of Jacobson Radical

Let $J \subseteq R$ be the Jacobson radical of a commutative ring R. Then:

1. If $I \subsetneq R$ is a proper ideal, then the ideal generated by I and J is also proper: $(I, J) \subsetneq R$
2. If R is Artinian, then the Jacobson radical is nilpotent: $J^n = 0$ for some n
3. $x \in J$ if and only if $1 - rx$ is a unit for every $r \in R$

***Proof*:**

1. If I is maximal, then $J \subseteq I$ and we are done, and if not then $I \subseteq M$ for some maximal ideal so $(I, J) \subseteq M \subsetneq R$
2. Let J be the jacobson radical. By the D.C.C. the following chain stabalizes

   $$J \supseteq J^2 \supseteq \cdots \supseteq J^n = J^{n+1} = \cdots$$

   Consider the set of all annihilators of J^n:

   $$I = \{x \in R \mid xJ^n = 0\}$$

   I claim that $I = (1)$, which will show that $1J^n = J^n = 0$ (i.e. J is nilpotent). For the sake of contradiction, let's say it is not I. Then pick $I' \supsetneq I$ that is minimal (i.e. there is no ideal between I' and I). Such an ideal exists by the D.C.C. condition. Then by minimality, it must be that I' is generated by adding just one more element, that is

   $$I' = I + Rx \qquad x \in R,\ x \notin I$$

   Thus, I'/I is a simple R-module by minimality (i.e. has no other ideals in it). However, it is easy to see that any simple R-module is of the form R/m for some maximal ideal m. Thus,

   $$I'/I \cong R/m$$

multiplying both sidses by m, we "kill" the right hand side and get

$$mI' \subseteq I$$

Thus $JI' \subseteq I.$, so $xJ \in I$, and so by definition of I,

$$xJ^{n+1} = 0$$

but by assumption $xJ^{n+1} = J^n$, but that implies $x \in I$. However, $x \notin I$, a contradiction.

3. Doing the contra-positive, let's say $x \notin \text{Jac}(R)$. Then $x \notin M'$ for some maximal ideal M'. By maximality, $M + (x) = (1)$, so $y + rx = 1$, implying $1 - rx = y \in M'$, showing that $1 - rx$ cannot be a unit (this does not show "for all $r \in R$"). Conversely, if $1 - rx$ is not a unit, $1 - rx \in M$ for some M. However, $1, rx \notin M$, since if they were then $1 \in M$. Thus, $rx \notin \text{Jac}(R)$ for all r, but then $x \notin \text{Jac}(R)$.

Lemma 23.4.27: Nakayama's Lemma I

Let M be a finitely generated R-module, and suppose $\alpha \subseteq R$ is an ideal that is contained in all maximal ideals of R (i.e. $\alpha \subseteq \text{Jac}(R)$). Then:

$$\text{if } \alpha M = M \text{ then } M = \{0\}$$

***Proof*:**
We will proceed by induction on the number of generators of M. If $n = 1$, then $\langle x_1 \rangle = M$. If $\alpha M = M$, we have that:

$$x_1 = a_1 x_1 \text{ for some } a_1 \in \alpha$$

we get that $(1 - a_1)x_1 = 0$, meaning $1 - a_1$ annihilates x_1.

However, $(1 - a_1)$ is in fact a unit (as will be shown in a moment). Since it's a unit, there exists a b such that

$$0 = b \cdot 0 = b(1 - a_1)x_1 = x_1$$

Thus it must be that $x_1 = 0$, showing that $M = \{0\}$. So it's left to show that $1 - a_1$ is a unit. Let's say $(1 - a_1)$ was a proper ideal. Then it must lie in some maximal ideal. Since $a_1 \in \alpha$ and α is a subset of all maximal ideals, it must be that $1 - \alpha_1 + \alpha_1 = 1$ is in a maximal ideal, however that would make the ideal a non-proper ideal, a contradiction.

For the case of $n = k$, let $x_1, x_2, ..., x_k$ generate M, and suppose $\alpha M = M$. Then

$$x_k = a_1 x_1 + a_2 x_2 + \cdots + a_k x_k$$

so $(1 - a_k)x_k = a_1 x_1 + \cdots + a_{k-1} x_{k-1} \in \langle x_1, \ldots, x_{k-1} \rangle$. As in the base case $1 - a_k$ is a unit, hence $x_k \in \langle x_1, \ldots, x_{k-1} \rangle$, so $M = \langle x_1, \ldots, x_{k-1} \rangle$ is generated by $k-1$ elements and still satisfies $\alpha M = M$. By the induction hypothesis $M = \{0\}$, as we sought to show

If we restrict to $R = A$ being a local ring and $\alpha = m$ the maximal ideal of A, we will have the first step in constructing a basis for M over A:

Lemma 23.4.28: Nakayama's Lemma II

Let M be a finitely generated A-module over a local ring A with maximal ideal m, and let F be a submodule of M. Then:

$$\text{if } M = F + mM \text{ then } M = F$$

***Proof*:**
Take $M/F = (F + mM)/F = mM/F$ so that $M/F = mM/F$. Then by lemma 23.4.27, $M/F = \{0\}$, so that means that M moded by F makes everything 0, and so

$$M = F$$

Finally, we put these two together to create create a basis for a module over a local ring using a basis for a smaller module!

Lemma 23.4.29: Nakayama's Lemma III

Let A be a local ring with maximal ideal m, and let M be a finitely generated A-module. If $x_1, x_2, \ldots, x_n$ generate M/mM, then they generate M.

***Proof*:**
Let $F = \langle x_1, x_2, ..., x_n \rangle \subseteq M$ be the submodule generated by the x_i. Then

$$M = F + mM$$

Then by lemma 23.4.28, $M = F$, and so M has $\langle x_1, x_2, ..., x_n \rangle$ as generators, as we sought to show

Nakayama's lemma let's us reverse some constructions. As we saw in chapter 14, a [finitely generated?] projective module over a PID is free. Using Nakayama's lemma, we can show that a finitely generated module over a local ring is also free!

Theorem 23.4.30: Projective Module over Local Ring

Let M be a finitely generated projective module over a local ring A. Then M is free. In particular, If if $\{x_1, ..., x_n\}$ are elements of M who's residue class $\{\overline{x_1}, ..., \overline{x_1}\}$ form a basis for M/mM over A/m, then $x_1, ..., x_n$ is a *basis* for M over A.

Furthermore, if $\overline{x_1}, ..., \overline{x_n}$ are linearly independent over A/m, then this collection can be completed to a basis for M over A

***Proof*:**
First, Note that $M/\mathfrak{m}M$ over $A/\mathfrak{m}$ is indeed a vector space with action $(a + \mathfrak{m})(m + \mathfrak{m}M) = (am + \mathfrak{m}M)$ being well-defined.

Since $M/\mathfrak{m}M$ is a finite-dimensional $A/\mathfrak{m}$-vector space, choose $x_1, \ldots, x_n \in M$ lifting a basis of it (so by Nakayama's lemma III they generate M). Let F be a free module with basis

$e_1, e_2, ..., e_n$, and consider the homomorphism $f : F \to M$, $f(e_i) = x_i$. We will show that f is in fact an isomorphism. Since $x_1, ..., x_n$ generate M mod $\mathfrak{m}M$, by Nakayama's lemma III, they generate M, and so f is surjective. Next, since M is projective, f splits, i.e., $F = P_0 \oplus P_1$ where $P_0 = \ker(f)$ and P_1 and $P_1 \cong M$ through f. We will show $P_0 = 0$.

Take some $\sum a_i x_i \in \ker(f)$ so that $\sum a_i x_i = 0$. Then reducing to the mod, we have $\sum a_i x_i + \mathfrak{m}M = 0 + \mathfrak{m}M = \sum(a_i\mathfrak{m}) \cdot (x_i + \mathfrak{m}M) = 0 + \mathfrak{m}M$. Since the $\overline{x}_i$ form a basis for $M/\mathfrak{m}M$ over $A/\mathfrak{m}A$, it must be that $a_i \in \mathfrak{m}$. Thus, we have $\sum a_i e_i \in \mathfrak{m}F$. Therefore:

$$\ker(f) \subseteq \mathfrak{m}F = \mathfrak{m}\ker(f) \oplus \mathfrak{m}M$$

Thus, $\mathfrak{m}\ker(f) = \ker(f)$. Since $\ker(f)$ is the direct summand of finitely generated modules, it is itself finitely generated. Thus, by Nakayama's lemma, $\ker(f) = 0$, and so f is an isomorphism! Therefore, we have $F \cong M$, and so M is free!

Notice that this immediately implies that the $x_1, ..., x_n$ are linealy independent since they form a basis for M over A (since f is an isomorphism and $f(e_i) = x_i$). Finally, if we extend $\overline{x}_1, ..\overline{x}_r$ to $\overline{x}_1, ..., \overline{x}_r, ...\overline{x}_n$ to be a basis for $M/\mathfrak{m}M$, then we just showed they will indeed form a basis for M.

A cool result of this theorem is a way to show some properties f based on f on the respective local modules. Let M be module over a local ring A. Then there is an associated module $M(\mathfrak{m}) = M/\mathfrak{m}M$ Then ___$(\mathfrak{m})$ induces a functor mapping M to $M(\mathfrak{m})$ and

$$f : M \to N \quad \mapsto \quad f_{(\mathfrak{m})} : M(\mathfrak{m}) \to N(\mathfrak{m})$$

Notice that if f is surjective, then $f_{(\mathfrak{m})}$ is surjective. The magic of Nakayama's lemma is that the converse is true too!

Proposition 23.4.31: Local Homomorphisms

Let M, N be finitely generated modules over a local ring A and $f : M \to N$ be an A-module homomorphism. Then:

1. f is surjective if and only if $f_{(\mathfrak{m})}$ is surjective
2. Assume f is injective. Then if $f_{(\mathfrak{m})}$ is surjective, f is an isomorphism
3. If M and N are free and $f_{(\mathfrak{m})}$ is injective, then f is injective; and f is an isomorphism if and only if $f_{(\mathfrak{m})}$ is an isomorphism

***Proof*:**

1. Let $f : M \to N$ be an R-module homomorphism and let the inducd $f_{(m)}$ be surjective so that $f(M \bmod \mathfrak{m}M) = N \bmod \mathfrak{m}N$. Since N is finitely generated, so is any quotient of it, and so N mod $\mathfrak{m}N$ is finitely generated by $\{\overline{x}_1, \overline{x}_2, ..., \overline{x}_n\}$ By Nakayama's lemma, $\{x_1, x_2, ..., x_n\}$ generated N. Since $x_1, ..., x_n \in f(M)$, f is also surjective

   More consisely, since $f_{(\mathfrak{m})}$ is surjective, $N = \mathrm{im}(f) + \mathfrak{m}N$. Thus, by Nakayama's lemma, $N = \mathrm{im}(f)$.

2. By part (1), surjectivity of $f_{(\mathfrak{m})}$ makes f surjective; together with the assumed injectivity of f, this makes f an isomorphism.

3. Assume M and N are free and $f_{(\mathfrak{m})}M/\mathfrak{m}M \to N/\mathfrak{m}N$ is injective. Since M is free, let $\{x_1, ..., x_n\} \subseteq M$ so that $\{\overline{x}_1, ..., \overline{x}_n\}$ is a basis for $M/\mathfrak{m}M$. Then by theorem 23.4.30, $x_1, ..., x_n$ forms a basis for M. Suppose now that $f(a_1x_1 + \cdots + a_nx_n) = 0$. By definition of $f_{(\mathfrak{m})}$, $f_{(\mathfrak{m})}(\overline{a}_1\overline{x}_1 + \cdots + \overline{a}_n\overline{x}_n) = \overline{0}$. Since $f_{(\mathfrak{m})}$ is injective, we have $\overline{a}_1\overline{x}_1 + \cdots + \overline{a}_n\overline{x}_n = 0$, and since $\overline{x}_1, ..., \overline{x}_n$ is a basis, we have that the coefficients are all $\overline{0}$, that is $a_i \in \mathfrak{m}$.

   To show that $\ker(f) = 0$, we will use Nakayama's lemma, so it suffices to show that $\ker(f) \subseteq \mathfrak{m}\ker(f)$. By what we have just shown, we have $\ker(f) \subseteq \mathfrak{m}M$. If $f_{(\mathfrak{m})}$ were surjective, then this proof is rather quick. By part (1), we have that f is surjective. Thus the following short exact sequence splits:

$$0 \to \ker(f) \to M \to N \to 0$$

   since N is free, So $M \cong \ker(f) \oplus N$, and $\ker(f) \subseteq \mathfrak{m}M \cong \ker(f) \oplus N$, and so $\ker(f) \subseteq \mathfrak{m}\ker(f)$, and so by Nakayama's lemma $\ker(f) = 0$.

   If $f_{(\mathfrak{m})}$ is not surjective, then we need to do a little more work. We will take advantage of the basis lifting property we proved in the previous theorem. Let $\{\overline{x}_1, ..., \overline{x}_n\}$ be a basis for $M/\mathfrak{m}M$ over $A/\mathfrak{m}A$ which induces a basis $\{x_1, .., x_n\}$ for M over A. $\langle f_{(\mathfrak{m})}(\overline{x}_1), ..., f_{(\mathfrak{m})}(\overline{x}_n)\rangle = \text{im}(f_{(\mathfrak{m})})$ is a submodule of $N/\mathfrak{m}N$ which have that generating set as a basis (since $f_{(\mathfrak{m})}$ is injective). Thus, if:

$$\overline{a}_1 f_{(\mathfrak{m})}(\overline{x}_1) + \cdots + \overline{a}_n f_{(\mathfrak{m})}(\overline{x}_n) = 0$$

   then since f is a homomorphism, we have

$$f_{(\mathfrak{m})}(\overline{a}_1\overline{x}_1 + \cdots + \overline{a}_1\overline{x}_1) = 0$$

   and since these elements form a basis and f is injective, $\overline{a}_i = 0$ for all i. Now, extend this to a basis for $N/\mathfrak{m}N$ over $A/\mathfrak{m}A$:

$$\{f_{(\mathfrak{m})}(\overline{x}_1), ..., f_{(\mathfrak{m})}(\overline{x}_n), \overline{y}_1, ..., \overline{y}_m\}$$

   Since N is free, this basis lifts to a basis for N over A, in particular:

$$\{f(x_1), ..., f(x_n), y_1, ..., y_m\}$$

   since $f_{(\mathfrak{m})}(\overline{x}_i) = f_{(\mathfrak{m})}(x_i + \mathfrak{m}M) = f(x_i) = \mathfrak{m}N$. With this, we can now get our conclusion: since the $f(x_i)$ are linearly independent, we have that:

$$a_1 f(x_1) + \cdots + a_n f(x_n) = f(a_1x_1 + \cdots + a_nx_n) = 0$$

   then it must be that the $a_i = 0$ for all the i, but then this is the condition for a function to be injective, and so f is injective, as we sought to show

Proposition 23.4.32: Projective Modules Determined by Their Reduction

Let P and P' be finitely generated projective modules over a local ring A. Then $P \cong P'$ if and only if $P/\mathfrak{m}P \cong P'/\mathfrak{m}P'$.

***Proof*:**
By theorem 23.4.30, P and P' are free, with ranks $\dim_{A/\mathfrak{m}}(P/\mathfrak{m}P)$ and $\dim_{A/\mathfrak{m}}(P'/\mathfrak{m}P')$; these ranks agree iff $P/\mathfrak{m}P \cong P'/\mathfrak{m}P'$, in which case $P \cong P'$. The converse is immediate.

Recall that if R is a finite integral domain, then it is necessarily a field (corollary 9.1.25). Naturally, this is not necessarily the case for infinite rings ($\mathbb{Z}$ being the prototypical example). We may thus take $Q = \text{Frac}(R)$, and consdier the R-module Q

Corollary 23.4.33: Infinite Generation Of Ring Of Fractions

Let R be an integral domain that is not a field, and $Q = \text{Frac}(R)$ its field of fractions. Then Q, considered as an R-module, is not finitely generated.

***Proof*:**
Suppose Q were finitely generated as an R-module. Since R is not a field, choose a nonzero maximal ideal $\mathfrak{m}$. As every nonzero element of R is already a unit in Q, we have $Q_{\mathfrak{m}} = Q$, still finitely generated over the local ring $R_{\mathfrak{m}}$. For any $0 \neq a \in \mathfrak{m}$ and $q \in Q$ we have $q = a(q/a)$ with $a \in \mathfrak{m}R_{\mathfrak{m}}$, so $\mathfrak{m}R_{\mathfrak{m}} \cdot Q = Q$. By lemma 23.4.27, $Q = 0$, contradicting $R \subseteq Q$.

Recall that when dealing with infinite functions, we may have some strange results, like a surjection $f : M \to M$ that is not an injection. Nakayama's lemma insures we get some sanity here:

Corollary 23.4.34: Surjective Implies Injective

Let M be a finitely generated R-module. Then if $f : M \to M$ is a surjective R-module homomorphism, it is injecive.

Note that no Noetherian assumption on R or M is required.

***Proof*:**
Make M a module over $R[x]$ by letting x act as f, i.e. $x \cdot m = f(m)$. Surjectivity of f gives $(x)M = xM = M$. Since M is a finitely generated $R[x]$-module with $(x)M = M$, the determinant trick (the Cayley-Hamilton form of Nakayama's lemma) yields $q(x) \in (x)$ with $(1 - q(x))M = 0$. Write $q(x) = x\,h(x)$. For $m \in \ker f$ we have $xm = f(m) = 0$, hence $m = q(x)m = h(x)(xm) = 0$. Thus $\ker f = 0$ and f is injective.

24

Primary Decomposition and Associated Primes

The integer n factors uniquely into prime powers, and the ideal $(n) \subseteq \mathbb{Z}$ inherits the factorization: writing $n = p_1^{a_1} \cdots p_k^{a_k}$ gives $(n) = (p_1^{a_1}) \cap \cdots \cap (p_k^{a_k})$, a finite intersection of ideals each built from a single prime. Over a general ring the unique factorization of elements fails, and the factorization of ideals into primes fails with it. What survives, in every Noetherian ring, is the weaker statement that an ideal is a finite intersection of *primary* ideals, the ideal-theoretic analogue of a prime power. This is the content of the Lasker-Noether theorem, and it is the decomposition facet of the finiteness thread: the same Noetherian hypothesis that produced Hilbert's basis theorem produces here the existence and finiteness that make the theory run.

The primes attached to such a decomposition are not artifacts of the factorization but invariants of the ideal, its *associated primes*. They split into two kinds. The minimal ones record the irreducible components and are uniquely determined; the *embedded* ones sit inside those components and can shift from one decomposition to another. Read through the correspondence between primes and points, the minimal primes will become the irreducible components of a variety and the embedded primes its embedded components, a reading developed downstream in [42]. Here the account is purely ring-theoretic, and its natural home is a module: the associated primes $\operatorname{Ass}(M)$ and the support $\operatorname{Supp}(M)$ are the invariants the later chapters, and the geometry and homological volumes, reach back for.

24.1 Primary Ideals

A prime ideal $\mathfrak{p}$ is one for which $xy \in \mathfrak{p}$ forces $x \in \mathfrak{p}$ or $y \in \mathfrak{p}$. The primary ideals relax the second alternative to a power.

Definition 24.1.1: Primary Ideal

A proper ideal $\mathfrak{q} \subsetneq R$ is *primary* if, whenever $xy \in \mathfrak{q}$ with $x \notin \mathfrak{q}$, some power y^n lies in $\mathfrak{q}$.

Passing to the quotient makes the condition transparent: $\mathfrak{q}$ is primary exactly when $R/\mathfrak{q} \neq 0$ and every zero-divisor of $R/\mathfrak{q}$ is nilpotent. Indeed $xy \in \mathfrak{q}$ with $x \notin \mathfrak{q}$ says that $\bar{y}$ kills the nonzero element $\bar{x}$ of $R/\mathfrak{q}$, and $y^n \in \mathfrak{q}$ says $\bar{y}$ is nilpotent.

The invariant attached to a primary ideal is its radical. Recall from proposition 9.4.3 that the *radical* of an ideal I is the ideal $\sqrt{I} = \{a \in R \mid a^k \in I \text{ for some } k \geq 1\}$, and that I is a *radical ideal* when $I = \sqrt{I}$. The structural description of the radical is through the primes, and the localization theory of section 23.4 is what proves it.

Theorem 24.1.2: The Radical as an Intersection of Primes

Let R be a commutative ring and $I \subsetneq R$ a proper ideal. Then

$$\sqrt{I} = \bigcap_{\substack{I \subseteq \mathfrak{p} \\ \mathfrak{p} \text{ prime}}} \mathfrak{p}$$

In particular every prime ideal is radical, and the *nilradical* $\mathrm{Nil}(R) = \sqrt{(0)}$ is the intersection of all the prime ideals of R.

***Proof*:**

For the containment $\subseteq$, let $a \in \sqrt{I}$, say $a^k \in I$, and let $\mathfrak{p}$ be any prime containing I. Then $a^k \in \mathfrak{p}$, and peeling off one factor at a time by primality gives $a \in \mathfrak{p}$.

For the containment $\supseteq$, suppose $a \notin \sqrt{I}$. We produce a prime containing I that misses a. The set $D = \{a^n \mid n \in \mathbb{Z}_{\geq 0}\}$ is multiplicatively closed and contains 1, and $D \cap I = \emptyset$, since $a \notin \sqrt{I}$ keeps every positive power of a out of I and properness of I keeps 1 out. By proposition 23.4.5(2) the extension $D^{-1}I$ is then a proper ideal of $D^{-1}R$, so it lies inside a maximal ideal $\mathfrak{m}$ (proposition 9.4.18). Maximal ideals are prime, so the contraction $\mathfrak{p} = {}^{\tau}\mathfrak{m}$ is prime as well, being the preimage of a prime under a ring homomorphism. It contains I because $\mathfrak{m}$ contains $D^{-1}I$, and it is disjoint from D, since an element $d \in \mathfrak{p} \cap D$ would place the unit $d/1$ inside the proper ideal $\mathfrak{m}$. In particular $a \notin \mathfrak{p}$, so a misses a prime containing I, which completes the identity.

For the last claims, a prime $\mathfrak{p}$ is itself one of the primes containing $\mathfrak{p}$ and is contained in every other, so $\sqrt{\mathfrak{p}} = \mathfrak{p}$. Taking $I = (0)$, every prime of R contains (0), and the intersection runs over all the primes of R.

Over a Noetherian ring the containment $I \subseteq \sqrt{I}$ also reverses up to a power.

Corollary 24.1.3: Radical Powers in Noetherian Rings

Let R be a Noetherian ring and $I \subseteq R$ an ideal. Then $\sqrt{I}^k \subseteq I$ for some $k \geq 1$. In particular the nilradical of a Noetherian ring is nilpotent.

***Proof*:**
By proposition 23.1.3 the ideal $\sqrt{I}$ is finitely generated, say by $a_1, \dots, a_m$, and each generator satisfies $a_i^{n_i} \in I$ for some $n_i \geq 1$. Put $k = \sum_{i=1}^{m}(n_i - 1) + 1$. The ideal $\sqrt{I}^k$ is generated by the products of k generators, that is by the monomials $a_1^{e_1} \cdots a_m^{e_m}$ with $\sum_i e_i = k$, since a product of k combinations $\sum_i r_i a_i$ expands into ring multiples of such monomials. In each such monomial some exponent satisfies $e_i \geq n_i$, for otherwise $\sum_i e_i \leq \sum_i (n_i - 1) < k$, and then $a_i^{e_i} \in I$ places the whole monomial in I. Every generator of $\sqrt{I}^k$ therefore lies in I, so $\sqrt{I}^k \subseteq I$. Taking $I = (0)$ makes $\mathrm{Nil}(R)^k = 0$.

For a primary ideal the radical is not merely an intersection of primes but a prime itself.

Proposition 24.1.4: The Radical of a Primary Ideal

If $\mathfrak{q}$ is primary then $\mathfrak{p} = \sqrt{\mathfrak{q}}$ is prime, and it is the smallest prime containing $\mathfrak{q}$. One says $\mathfrak{q}$ is $\mathfrak{p}$-*primary*.

***Proof*:**
The radical of any ideal is the intersection of the primes containing it (theorem 24.1.2), so $\sqrt{\mathfrak{q}}$ is contained in every prime over $\mathfrak{q}$, and it suffices to show it is prime. Suppose $xy \in \sqrt{\mathfrak{q}}$, say $(xy)^m \in \mathfrak{q}$, and $x \notin \sqrt{\mathfrak{q}}$. Then no power of x lies in $\mathfrak{q}$, so from $x^m y^m \in \mathfrak{q}$ and primarity applied to $x^m \cdot y^m$ we get $(y^m)^k \in \mathfrak{q}$ for some k, whence $y \in \sqrt{\mathfrak{q}}$.

The radical being prime does *not*, by itself, make an ideal primary; the converse needs the radical to be maximal.

Lemma 24.1.5: Ideals with Maximal Radical are Primary

If $\sqrt{\mathfrak{q}} = \mathfrak{m}$ is maximal, then $\mathfrak{q}$ is primary. In particular every power $\mathfrak{m}^n$ of a maximal ideal is $\mathfrak{m}$-primary.

***Proof*:**
In $R/\mathfrak{q}$ the image of $\mathfrak{m}$ is the nilradical, since $\mathfrak{m} = \sqrt{\mathfrak{q}}$, and it is also maximal. Thus $R/\mathfrak{q}$ has a single prime ideal, so every element is either a unit or nilpotent, and every zero-divisor is nilpotent. For the last claim, $\sqrt{\mathfrak{m}^n} = \mathfrak{m}$.

Example 24.1.6: Primary and Non-Primary Ideals

1. In $\mathbb{Z}$ the primary ideals are (0) and the prime powers (p^n); this is the factorization $(n) = \bigcap (p_i^{a_i})$ read one prime at a time.
2. In $R = k[x, y]$ the ideal $\mathfrak{q} = (x, y^2)$ is primary: $R/\mathfrak{q} \cong k[y]/(y^2)$, whose only zero-divisors are the multiples of $\bar{y}$, all nilpotent. Its radical is (x, y), and $(x, y)^2 \subsetneq \mathfrak{q} \subsetneq (x, y)$, so a primary ideal need not be a power of its radical prime.
3. A power of a prime need not be primary. In $R = k[x, y, z]/(xy - z^2)$ let $\mathfrak{p} = (\bar{x}, \bar{z})$, which is prime because $R/\mathfrak{p} \cong k[y]$ is a domain. Then $\bar{x}\bar{y} = \bar{z}^2 \in \mathfrak{p}^2$, yet $\bar{x} \notin \mathfrak{p}^2$ and $\bar{y} \notin \sqrt{\mathfrak{p}^2} = \mathfrak{p}$, so

$\mathfrak{p}^2$ is not primary although its radical $\mathfrak{p}$ is prime.

24.2 Primary Decomposition

Definition 24.2.1: Primary Decomposition

A *primary decomposition* of an ideal I is an expression

$$I = \mathfrak{q}_1 \cap \mathfrak{q}_2 \cap \cdots \cap \mathfrak{q}_n$$

with each $\mathfrak{q}_i$ primary. It is *minimal* if the radicals $\mathfrak{p}_i = \sqrt{\mathfrak{q}_i}$ are pairwise distinct and no $\mathfrak{q}_i$ contains the intersection of the others. An ideal admitting a primary decomposition is called *decomposable*.

Any primary decomposition can be trimmed to a minimal one, once we know that primary ideals with a common radical combine.

Lemma 24.2.2: Intersections of $\mathfrak{p}$-Primary Ideals

A finite intersection $\mathfrak{q} = \mathfrak{q}_1 \cap \cdots \cap \mathfrak{q}_m$ of $\mathfrak{p}$-primary ideals (same radical $\mathfrak{p}$) is again $\mathfrak{p}$-primary.

***Proof*:**
Radicals commute with finite intersections, so $\sqrt{\mathfrak{q}} = \bigcap \sqrt{\mathfrak{q}_i} = \mathfrak{p}$. Suppose $xy \in \mathfrak{q}$ with $y \notin \sqrt{\mathfrak{q}} = \mathfrak{p}$. For each i, $xy \in \mathfrak{q}_i$ and $y \notin \sqrt{\mathfrak{q}_i}$, so no power of y lies in $\mathfrak{q}_i$; primarity of $\mathfrak{q}_i$ then gives $x \in \mathfrak{q}_i$. Hence $x \in \mathfrak{q}$, and $\mathfrak{q}$ is primary.

Given any primary decomposition, group the $\mathfrak{q}_i$ by their radical and replace each group by its intersection, which lemma 24.2.2 keeps primary; then discard any term containing the intersection of the rest. The result is minimal, so *every decomposable ideal has a minimal primary decomposition*. The point of the next two sections is that the data left after this trimming is intrinsic to I.

24.3 Associated Primes

The invariants are cleanest for modules, where they will also serve the later theory of depth and support.

Definition 24.3.1: Associated Prime

Let M be an R-module. A prime $\mathfrak{p}$ is an *associated prime* of M if $\mathfrak{p} = \operatorname{Ann}(x)$ for some $x \in M$; equivalently, if $R/\mathfrak{p}$ embeds in M. The set of associated primes is written $\operatorname{Ass}(M)$. The associated primes of an ideal I mean those of the module R/I.

The two forms match because a copy of $R/\mathfrak{p}$ inside M is generated by an element whose annihilator is $\mathfrak{p}$, and conversely $\operatorname{Ann}(x) = \mathfrak{p}$ makes $r \mapsto rx$ an embedding $R/\mathfrak{p} \hookrightarrow M$.

Lemma 24.3.2: Zero-Divisors and Annihilators

Let R be Noetherian and $M \neq 0$ a finitely generated module. A maximal element of the family $\{\mathrm{Ann}(x) : 0 \neq x \in M\}$ is prime, so it lies in $\mathrm{Ass}(M)$; in particular $\mathrm{Ass}(M) \neq \emptyset$.

***Proof*:**
The family is nonempty and, R being Noetherian, has a maximal member $\mathfrak{p} = \mathrm{Ann}(x)$. It is proper since $x \neq 0$. If $ab \in \mathfrak{p}$ with $b \notin \mathfrak{p}$, then $bx \neq 0$ and $\mathrm{Ann}(bx) \supseteq \mathfrak{p} + (a) \supseteq \mathfrak{p}$; maximality forces $\mathrm{Ann}(bx) = \mathfrak{p}$, so $a \in \mathrm{Ann}(bx) = \mathfrak{p}$. Thus $\mathfrak{p}$ is prime.

The associated primes are exactly the radicals appearing in a minimal decomposition.

Theorem 24.3.3: First Uniqueness Theorem

Let R be Noetherian and let I have a minimal primary decomposition $I = \mathfrak{q}_1 \cap \cdots \cap \mathfrak{q}_n$ with radicals $\mathfrak{p}_i = \sqrt{\mathfrak{q}_i}$. Then

$$\{\mathfrak{p}_1, \ldots, \mathfrak{p}_n\} = \mathrm{Ass}(R/I),$$

and in particular the set of radicals does not depend on the chosen minimal decomposition.

***Proof*:**
Work in R/I; annihilators there are the ideals $(I : x)/I$ for $x \in R$, and $\sqrt{(I : x)}$ measures which components miss x. For $x \in R$ one computes $(I : x) = \bigcap_i (\mathfrak{q}_i : x)$, and $(\mathfrak{q}_i : x) = R$ when $x \in \mathfrak{q}_i$ while $\sqrt{(\mathfrak{q}_i : x)} = \mathfrak{p}_i$ when $x \notin \mathfrak{q}_i$ (primarity: if $y(x) \in \mathfrak{q}_i$ with $x \notin \mathfrak{q}_i$ then $y \in \mathfrak{p}_i$). Hence

$$\sqrt{(I : x)} = \bigcap_{x \notin \mathfrak{q}_i} \mathfrak{p}_i$$

If this radical is itself prime it must equal some $\mathfrak{p}_i$, since a prime containing a finite intersection contains one of the factors and each $\mathfrak{p}_i$ here contains the intersection. Thus every prime of the form $\sqrt{(I : x)}$ is one of the $\mathfrak{p}_i$. Conversely, minimality provides for each i an element x_i lying in every $\mathfrak{q}_j$ with $j \neq i$ but not in $\mathfrak{q}_i$, and then $\sqrt{(I : x_i)} = \mathfrak{p}_i$. The primes among $\sqrt{(I : x)}$ are therefore exactly $\mathfrak{p}_1, \ldots, \mathfrak{p}_n$. For $\mathrm{Ass}(R/I) \subseteq \{\mathfrak{p}_i\}$: if $\mathfrak{p} \in \mathrm{Ass}(R/I)$ then $\mathfrak{p} = (I : x)/I$ is an annihilator, and being prime it equals its radical $\sqrt{(I : x)}$, hence some $\mathfrak{p}_i$. For the reverse inclusion, fix i and use minimality to pick $x_i \in \bigcap_{j \neq i} \mathfrak{q}_j$ with $x_i \notin \mathfrak{q}_i$; then $(I : x_i) = (\mathfrak{q}_i : x_i)$, which is $\mathfrak{p}_i$-primary (for $x \notin \mathfrak{q}$ with $\mathfrak{q}$ being $\mathfrak{p}$-primary, $(\mathfrak{q} : x)$ lies between $\mathfrak{q}$ and $\mathfrak{p}$, and $ab \in (\mathfrak{q} : x)$ with $a \notin (\mathfrak{q} : x)$ gives $(ax)b \in \mathfrak{q}$, $ax \notin \mathfrak{q}$, so $b \in \mathfrak{p}$). Thus the cyclic submodule $R\bar{x}_i \cong R/(\mathfrak{q}_i : x_i)$ of R/I has all its zero-divisors in $\mathfrak{p}_i$; a maximal annihilator in it is prime (lemma 24.3.2), lies in $\mathfrak{p}_i$, and, containing $(\mathfrak{q}_i : x_i)$, contains $\sqrt{(\mathfrak{q}_i : x_i)} = \mathfrak{p}_i$, so it equals $\mathfrak{p}_i$. Since annihilators in a submodule are annihilators in R/I, this gives $\mathfrak{p}_i \in \mathrm{Ass}(R/I)$, and hence equality.

24.4 The Lasker-Noether Theorem

Existence rests on two Noetherian facts: that ideals are finite intersections of irreducible ones, and that over a Noetherian ring irreducible means primary. Call a proper ideal *irreducible* if it is not the

intersection of two strictly larger ideals.

Lemma 24.4.1: Irreducible Implies Primary

In a Noetherian ring every irreducible ideal is primary.

***Proof*:**
Passing to R/I, it suffices to show that the zero ideal, if irreducible, is primary; that is, that a zero-divisor of a ring in which (0) is irreducible is nilpotent. Let $xy = 0$ with $y \neq 0$. The annihilators $\operatorname{Ann}(x) \subseteq \operatorname{Ann}(x^2) \subseteq \cdots$ stabilize, say $\operatorname{Ann}(x^n) = \operatorname{Ann}(x^{n+1})$. Then $(x^n) \cap (y) = 0$: if $ax^n = by$ then $ax^{n+1} = bxy = 0$, so $a \in \operatorname{Ann}(x^{n+1}) = \operatorname{Ann}(x^n)$ and $ax^n = 0$. Since (0) is irreducible and $(y) \neq 0$, we must have $(x^n) = 0$, so x is nilpotent.

Theorem 24.4.2: Lasker-Noether

In a Noetherian ring every proper ideal is a finite intersection of irreducible ideals, and hence is decomposable. Consequently every proper ideal has a minimal primary decomposition.

***Proof*:**
Let Σ be the set of ideals that are *not* finite intersections of irreducible ideals. If $\Sigma \neq \emptyset$ it has a maximal member I by the ascending chain condition. Now I is not irreducible (an irreducible ideal is such an intersection, of length one), so $I = J \cap K$ with $J, K \supsetneq I$. By maximality J and K are each finite intersections of irreducibles, hence so is I, contradicting $I \in \Sigma$. Thus $\Sigma = \emptyset$. Each irreducible ideal is primary by lemma 24.4.1, giving a primary decomposition, which is trimmed to a minimal one by grouping common radicals and discarding redundant terms.

The finiteness of the associated primes is now immediate.

Corollary 24.4.3: Finiteness of Associated Primes

Over a Noetherian ring, $\operatorname{Ass}(R/I)$ is finite for every ideal I; more generally $\operatorname{Ass}(M)$ is finite for every finitely generated module M.

***Proof*:**
The finitely generated case includes every R/I, so we prove it. Two standard facts suffice. First, a short exact sequence $0 \to M' \to M \to M'' \to 0$ gives $\operatorname{Ass}(M) \subseteq \operatorname{Ass}(M') \cup \operatorname{Ass}(M'')$: if $\mathfrak{p} = \operatorname{Ann}(x)$ then $Rx \cong R/\mathfrak{p}$, and either $Rx \cap M' \neq 0$, so a nonzero element of the domain $R/\mathfrak{p}$ lies in M' and (being torsion-free) still has annihilator $\mathfrak{p}$, whence $\mathfrak{p} \in \operatorname{Ass}(M')$; or $Rx \cap M' = 0$, so Rx injects into M'' and $\mathfrak{p} \in \operatorname{Ass}(M'')$. Second, applying lemma 24.3.2 repeatedly to split off a submodule $\cong R/\mathfrak{p}$ and pass to the quotient produces, by the ascending chain condition, a finite filtration $0 = M_0 \subsetneq \cdots \subsetneq M_r = M$ with $M_j/M_{j-1} \cong R/\mathfrak{p}_j$. Subadditivity along it gives $\operatorname{Ass}(M) \subseteq \{\mathfrak{p}_1, \ldots, \mathfrak{p}_r\}$, a finite set; for $M = R/I$ with I proper, theorem 24.3.3 identifies it precisely as the radicals $\{\mathfrak{p}_i\}$.

24.5 Support and the Isolated Components

The associated primes live inside a coarser invariant, the support, whose minimal members are the geometrically visible components.

Two consequences are used constantly and are recorded here, the first because it is invoked by name later in this book and in [29] without ever having been stated.

Proposition 24.5.1: Prime Avoidance

Let I be an ideal of a ring R and $\mathfrak{p}_1, \dots, \mathfrak{p}_n$ prime ideals. If $I \subseteq \mathfrak{p}_1 \cup \cdots \cup \mathfrak{p}_n$ then $I \subseteq \mathfrak{p}_i$ for some i. Equivalently, if I is contained in no $\mathfrak{p}_i$, then I contains an element lying in no $\mathfrak{p}_i$.

***Proof*:**
Induct on n, the case $n = 1$ being trivial. Discarding redundant terms, assume the covering is irredundant, so that for each i there is $a_i \in I$ with $a_i \notin \mathfrak{p}_j$ for $j \neq i$; if some a_i also avoided $\mathfrak{p}_i$ we would be done, so assume $a_i \in \mathfrak{p}_i$ for every i. Consider

$$b \;=\; a_1 + a_2 a_3 \cdots a_n$$

It lies in I. If $b \in \mathfrak{p}_1$ then, since $a_1 \in \mathfrak{p}_1$, the product $a_2 \cdots a_n \in \mathfrak{p}_1$, so some $a_j \in \mathfrak{p}_1$ with $j \geq 2$, contradicting the choice of a_j. If $b \in \mathfrak{p}_i$ for some $i \geq 2$ then, since $a_2 \cdots a_n \in \mathfrak{p}_i$, we get $a_1 \in \mathfrak{p}_i$, again a contradiction. So b lies in I and in no $\mathfrak{p}_i$, contradicting the assumed covering; hence the covering was not irredundant and induction finishes the proof.

Corollary 24.5.2: The Zero-Divisors Are the Union of the Associated Primes

Let R be Noetherian and $M \neq 0$ a finitely generated module. Then

$$\{\, z \in R : z \text{ is a zero-divisor on } M \,\} \;=\; \bigcup_{\mathfrak{p} \in \operatorname{Ass}(M)} \mathfrak{p}$$

In particular an element lying outside every associated prime of M is a non-zero divisor on M.

***Proof*:**
If $\mathfrak{p} \in \operatorname{Ass}(M)$ then $\mathfrak{p} = \operatorname{Ann}(x)$ for some $x \neq 0$, so every element of $\mathfrak{p}$ kills x and is a zero-divisor. Conversely let $zx = 0$ with $x \neq 0$, so $z \in \operatorname{Ann}(x)$. The family of annihilators $\operatorname{Ann}(y)$ for $0 \neq y \in M$ that contain $\operatorname{Ann}(x)$ is nonempty and, R being Noetherian, has a maximal element $\operatorname{Ann}(y_0)$. It is maximal in the whole family as well: an annihilator strictly containing it also contains $\operatorname{Ann}(x)$, so lies in the subfamily. By lemma 24.3.2 it is therefore prime, so $\operatorname{Ann}(y_0) \in \operatorname{Ass}(M)$, and it contains z.

Definition 24.5.3: Support

The *support* of an R-module M is $\operatorname{Supp}(M) = \{\mathfrak{p} \in \operatorname{Spec} R : M_{\mathfrak{p}} \neq 0\}$.

Proposition 24.5.4: Support of a Finitely Generated Module

If M is finitely generated then $\mathrm{Supp}(M) = V(\mathrm{Ann}M)$. In particular $\mathrm{Supp}(R/I) = V(I)$.

***Proof*:**
For finitely generated $M = (x_1, \ldots, x_m)$, the localization $M_\mathfrak{p}$ vanishes iff each generator dies, that is iff $\mathrm{Ann}(x_i) \not\subseteq \mathfrak{p}$ for all i. Since $\mathfrak{p}$ is prime, a containment $\bigcap_i \mathrm{Ann}(x_i) \subseteq \mathfrak{p}$ would force some $\mathrm{Ann}(x_i) \subseteq \mathfrak{p}$ (a prime containing a finite intersection contains a factor); so $M_\mathfrak{p} = 0$ iff $\mathrm{Ann}(M) = \bigcap_i \mathrm{Ann}(x_i) \not\subseteq \mathfrak{p}$. Thus $M_\mathfrak{p} \neq 0$ iff $\mathrm{Ann}(M) \subseteq \mathfrak{p}$, which is $\mathfrak{p} \in V(\mathrm{Ann}M)$.

Proposition 24.5.5: Associated Primes Sit in the Support

For finitely generated M over a Noetherian ring, $\mathrm{Ass}(M) \subseteq \mathrm{Supp}(M)$, and the two sets have the same minimal elements. For an ideal I these common minimal elements are the minimal primes over I.

***Proof*:**
If $\mathfrak{p} = \mathrm{Ann}(x) \in \mathrm{Ass}(M)$ then $R/\mathfrak{p} \hookrightarrow M$ localizes to $(R/\mathfrak{p})_\mathfrak{p} = \kappa(\mathfrak{p}) \neq 0 \hookrightarrow M_\mathfrak{p}$, so $\mathfrak{p} \in \mathrm{Supp}(M)$. For the minimal elements: $\mathrm{Supp}(M) = V(\mathrm{Ann}M)$ by proposition 24.5.4, whose minimal elements are the minimal primes over $\mathrm{Ann}(M)$. Each such minimal prime $\mathfrak{p}$ has $M_\mathfrak{p} \neq 0$ finitely generated over the Noetherian local ring $R_\mathfrak{p}$, so $\mathrm{Ass}(M_\mathfrak{p}) \neq \emptyset$ by lemma 24.3.2; but $\mathfrak{p}$ is minimal in $\mathrm{Supp}(M)$, so $\mathfrak{p}R_\mathfrak{p}$ is the only prime of $R_\mathfrak{p}$ in the support, forcing $\mathrm{Ass}(M_\mathfrak{p}) = \{\mathfrak{p}R_\mathfrak{p}\}$ and hence $\mathfrak{p} \in \mathrm{Ass}(M)$ (associated primes localize, as in corollary 24.6.2). So minimal elements of $\mathrm{Supp}(M)$ lie in $\mathrm{Ass}(M)$, and being minimal in the larger set they are minimal in $\mathrm{Ass}(M)$; the reverse inclusion of minimal elements is immediate from $\mathrm{Ass}(M) \subseteq \mathrm{Supp}(M)$.

The associated primes thus divide in two: the *isolated* (or minimal) primes, which are the minimal primes over I, and the *embedded* primes, which properly contain another associated prime. The isolated components are intrinsic; the embedded ones are not.

Theorem 24.5.6: Second Uniqueness Theorem

Let $I = \mathfrak{q}_1 \cap \cdots \cap \mathfrak{q}_n$ be a minimal primary decomposition with $\mathfrak{p}_i = \sqrt{\mathfrak{q}_i}$. If $\mathfrak{p}_i$ is isolated (minimal among the $\mathfrak{p}_j$), the component $\mathfrak{q}_i$ is uniquely determined by I: it is the contraction of $IR_{\mathfrak{p}_i}$ to R. Embedded components need not be unique.

***Proof*:**
Localize at an isolated prime $\mathfrak{p} = \mathfrak{p}_i$. For $j \neq i$, $\mathfrak{p}_j \not\subseteq \mathfrak{p}$ by isolation, so $\mathfrak{q}_j$ meets $R \setminus \mathfrak{p}$ and $\mathfrak{q}_j R_\mathfrak{p} = R_\mathfrak{p}$; for the index i, $\mathfrak{q}_i R_\mathfrak{p}$ is $\mathfrak{p}R_\mathfrak{p}$-primary with contraction $\mathfrak{q}_i$ (see proposition 24.6.1). Intersecting, $IR_\mathfrak{p} = \mathfrak{q}_i R_\mathfrak{p}$, so $\mathfrak{q}_i = IR_\mathfrak{p} \cap R$ depends only on I and $\mathfrak{p}$. Non-uniqueness of embedded components is exhibited by example 24.5.7.

Example 24.5.7: Non-Uniqueness of Embedded Components

In $R = k[x, y]$ the ideal $I = (x^2, xy)$ has radical (x) and the two minimal primary decompositions

$$I = (x) \cap (x, y)^2 = (x) \cap (x^2, y),$$

both with radicals (x) and (x, y). The isolated (x)-component is (x) in each, as theorem 24.5.6 requires. The embedded (x, y)-component is $(x, y)^2 = (x^2, xy, y^2)$ in the first and (x^2, y) in the second, so it is genuinely not determined by I.

24.6 Localization and Primary Decomposition

The behavior under localization used above is the following, and it is what recovers the isolated components.

Proposition 24.6.1: Primary Ideals under Localization

Let $S \subseteq R$ be multiplicative and $\mathfrak{q}$ a $\mathfrak{p}$-primary ideal.

1. If $S \cap \mathfrak{p} \neq \emptyset$ then $S^{-1}\mathfrak{q} = S^{-1}R$.
2. If $S \cap \mathfrak{p} = \emptyset$ then $S^{-1}\mathfrak{q}$ is $S^{-1}\mathfrak{p}$-primary and its contraction to R is $\mathfrak{q}$.

***Proof*:**

If $s \in S \cap \mathfrak{p}$ then $s^n \in \mathfrak{q}$ for some n, and s^n is a unit in $S^{-1}R$, giving (1). For (2), assume $S \cap \mathfrak{p} = \emptyset$. Since localization is exact, $S^{-1}R/S^{-1}\mathfrak{q} \cong \bar{S}^{-1}(R/\mathfrak{q})$, the localization of $R/\mathfrak{q}$ at the image $\bar{S}$ of S. The zero-divisors of $R/\mathfrak{q}$ are nilpotent, hence lie in $\mathfrak{p}/\mathfrak{q}$; as $S \cap \mathfrak{p} = \emptyset$, the elements of $\bar{S}$ avoid $\mathfrak{p}/\mathfrak{q}$ and are non-zero-divisors of $R/\mathfrak{q}$. A zero-divisor of $\bar{S}^{-1}(R/\mathfrak{q})$ then has a zero-divisor of $R/\mathfrak{q}$ for numerator, hence is nilpotent; so $S^{-1}\mathfrak{q}$ is primary, with radical $S^{-1}\mathfrak{p}$. Its contraction is $\mathfrak{q}$: if $sx \in \mathfrak{q}$ with $s \in S$, then $s \notin \mathfrak{p} = \sqrt{\mathfrak{q}}$ forces $x \in \mathfrak{q}$ by primarity.

Corollary 24.6.2: Associated Primes Localize

For a multiplicative set S and finitely generated M over a Noetherian ring,

$$\operatorname{Ass}(S^{-1}M) = \{\, S^{-1}\mathfrak{p} : \mathfrak{p} \in \operatorname{Ass}(M),\ \mathfrak{p} \cap S = \emptyset \,\}$$

Consequently, if $I = \bigcap \mathfrak{q}_i$ is a minimal decomposition, localizing at an isolated prime $\mathfrak{p}_i$ deletes every component except $\mathfrak{q}_i$, recovering $\mathfrak{q}_i = IR_{\mathfrak{p}_i} \cap R$.

***Proof*:**

For $\supseteq$: an embedding $R/\mathfrak{p} \hookrightarrow M$ with $\mathfrak{p} \cap S = \emptyset$ localizes, by exactness (proposition 23.4.9), to $S^{-1}R/S^{-1}\mathfrak{p} \hookrightarrow S^{-1}M$, and $S^{-1}\mathfrak{p}$ is prime, so $S^{-1}\mathfrak{p} \in \operatorname{Ass}(S^{-1}M)$. For $\subseteq$: let $P = \operatorname{Ann}(x/s) \in \operatorname{Ass}(S^{-1}M)$ and $\mathfrak{p} = P \cap R$, a prime with $\mathfrak{p} \cap S = \emptyset$. As R is Noetherian, $\mathfrak{p} = (a_1, \dots, a_k)$; each $a_j/1 \in P$ kills x/s, so $t_j a_j x = 0$ in M for some $t_j \in S$, and with $t = t_1 \cdots t_k$ we get $\mathfrak{p} \subseteq \operatorname{Ann}(tx)$. Conversely, if $r \in \operatorname{Ann}(tx)$ then $r \cdot (x/s) = rtx/(ts) = 0$, so $r \in P \cap R = \mathfrak{p}$; hence

> $\mathfrak{p} = \operatorname{Ann}(tx) \in \operatorname{Ass}(M)$ and $P = S^{-1}\mathfrak{p}$. The recovery statement is proposition 24.6.1(2) applied to $S = R \setminus \mathfrak{p}_i$, exactly as in the proof of theorem 24.5.6.

Read geometrically, $\operatorname{Supp}(R/I) = V(I)$ decomposes into irreducible pieces indexed by the minimal primes over I, and the isolated primary components cut out those pieces with their natural scheme structure while the embedded primes mark where that structure thickens; this translation is the subject of [42], which cites the present chapter for the algebra.

25

Completion

The next type of construction we will do is called a *completion*. These will be in the appropriate sense "stronger" then localizations, which will result in them being more restrictive, though also more powerful. A completion of a ring in many ways parallel's the completion of the rationals numbers $\mathbb{Q}$ to the real numbers $\mathbb{R}$. In fact, defining the appropriate metric, this process is a special case of the cauchy-sequence completion of the rational numbers to the reals. Namely, the completion of a ring is the equivalence class of all Cauchy-sequences which converge to the same point. Due to the topological background needed for this perspective, we shall relegate the equivalence of what shall be explicated in this section and Cauchy-sequences to appendix C.5.

There were rings that we have observed earlier that are completions of simpler rings; we will use completions to construct rings like the ring of *formal power series* $R[[x]]$ from $R[x]$, the ring $R[x_1, x_2, ...]$, the ring with *infinitely many monomial* from $R[x_1, ..., x_n]$, and the *p-adic integers* $\mathbb{Z}_p$ from $\mathbb{Z}$..

Completions will be handy for us in many ways. One important use that we will see when looking into algebraic geometry is looking at the "singularities" of schemes (or more particularly algebraic curves). Singularities will be points that do not be had as nicely as most other points, for example in the following image (which is the zero set of the equation $y^2 - x^2(x+1) = 0$) does not behave well at $(0, 0)$:




Figure 25.1: zero set of $y^2 - x^2(x+1) = 0$

This may seem similar to the geometric notion of localization, and this is indeed the case. Indeed, in the case of $\mathbb{Z}_{(p)}$ the p-adic integers are the completion of this ring, namely $\mathbb{Z}_p$ is the completion of $\mathbb{Z}_{(p)}$.

Completions shall also play a very important role in algebraic number theory. In this book, a more "classical" approach to algebraic number theory was taken, which shall give the reader great insights on the fundamental of algebraic number theory. However, a large part of *class number theory* shall rely on special completions of rings.

In this section, topological notion's will be introduced, and so an acquaintance of the material in appendix C is recommended. It should be noted that the topologies that will be discussed will be very different from that of Euclidean topologies, a new notion of size that is rather different from Euclidean distance shall be developed. The reader that is familiar with the construction of the real numbers using Cauchy sequences shall find it much easier to follow this section.

25.1 Constructing Completions

We will first define what is a "sequence". Let's say we have a collection of countable rings $R_1, R_2, ..., R_n$ and homomorphisms:

$$\cdots \xrightarrow{f_3} R_3 \xrightarrow{f_2} R_2 \xrightarrow{f_1} R_1$$

Then a sequence, or a *coherent sequence* is an element $(x_1, x_2, ...) \in \prod_{i=1}^{\infty} R_i$ where:

$$f_i(x_{i+1}) = x_i$$

If we take the special case of $I \subseteq R$ being an ideal and

$$\cdots \xrightarrow{f_3} R/(I^3) \xrightarrow{f_2} R/(I^2) \xrightarrow{f_1} R/I$$

then we will define a form of completion from these maps. For ease of notation, the sequence is usually written in the reverse order, as the reader shall understand once examples will be presented

Definition 25.1.1: Completion Of A Ring

Let R be a ring and $I \subseteq R$ be an ideal, and:

$$R/I \xleftarrow{f_1} R/(I^2) \xleftarrow{f_2} R/(I^3) \leftarrow \cdots$$

Then:

$$\hat{R} := \left\{ (a_1, a_2, ...,) \in \prod_{i=1}^{\infty} R_i \;\middle|\; f_i(a_{i+1}) = a_i \right\}$$

which is often denoted as:

$$\varprojlim R/I^n := \hat{R}$$

and is called the *limit* (or in older textbooks the *inverse limit* or *projective limit*). The collection $\{R/I^n\}$ is called the *inverse system*, with the function usually taken as implicit

A couple of remarks are in order:

1. There is a natural topology and a metric in which these elements can be thought of as Cauchy sequences and $\hat{R}$ is indeed the completion of R. If $\{R/\mathfrak{a}^n R\}$ is an inverse system with ideal $\mathfrak{a} \subseteq R$, and any $x \in R$, define a neighborhood basis (or local basis) $\{x + \mathfrak{a}^n R\}_{n=1}^{\infty}$. Then this forms a basis for a topology. This topology is called the $\mathfrak{a}$-*adic topology*, U is open in this topology if and only if for each $x \in U$, there exists a positive integer n such that

   $$x + \mathfrak{a}^n R \subseteq U$$

   Then R is Hausdorff if and only if $\cap \mathfrak{a}^n R = 0$. If this is the case, define the metric $d(x, y) = 2^{-n}$ whenever $x \neq y$, where n is the largest integer with $x - y \in \mathfrak{a}^n R$ (equivalently $x - y \in \mathfrak{a}^n R \setminus \mathfrak{a}^{n+1} R$). The constant 2 does not matter, it can be replaced with any $C > 1$ and it will give the same topology.

   This exact same process can be repeated on an arbitrary R-module, where the inverse system would be $\{M/a^n M\}$, and for a given ideal $I \subseteq R$, we would define the I-adic topology on M.

2. This is a special case of a more general construction of a *limit* in the category of **Ring**. Namely, it is the limit of a special form of the diagram:

   $$\cdots \to \bullet \to \bullet \to \bullet$$

   where each arrow has the coherence condition stated above.

3. The transition maps $R/\mathfrak{a}^{n+1} \to R/\mathfrak{a}^n$ of the systems built from powers of an ideal are surjective; such inverse systems are called *surjective systems*.

4. If R is a Noetherian integral domain and $I \subsetneq R$ is a proper ideal, then $\bigcap_n I^n = 0$, and hence $R \subseteq \hat{R}$. For those who shall read appendix C.4, this shows that inegral Noetherian domains are Hausdorff in the I-adic topology.

Example 25.1.2: Completion of Rings

1. Let $R = k[x]$ and $I = (x)$. Then:

$$\varprojlim(k[x]/(x)^n) = k[[x]]$$

To see this, consider:

$$\cdots k[x]/(x^3) \to k[x]/(x^2) \to k[x]/(x) = k$$

Notice that in each $k[x]/(x^k)$, can be thought of the collection of all polynomial of degree up to $k-1$. Hence, a coherent sequence $(a_1, a_2, ...)$ can be thought of as an "infinitely long polynomial" and would usually be denoted

$$\sum_k^\infty a_k x^k$$

Similarly, the reader may verify that $\widehat{k[x,y]} = k[[x,y]]$ with $I = (x,y)$

2. Let $R = \mathbb{Z}$ and $I = (10)$. Then $\varprojlim \mathbb{Z}/(10)^n$ is represented by all infinitely long numbers. Just like before, each $\mathbb{Z}/(10)^k$ can be thought of as as holding information up to the $k-1$th position. So if we take:

$$Z/(10) \leftarrow Z/(100) \leftarrow \mathbb{Z}/(1000) \leftarrow$$

and construct a coherent chain, we may chose elements like 5, 25, 425, ... and so on. The reader may see that this would represent an infinitely long number. The resulting ring is often denoted $\mathbb{Z}_{10}$ and is called the 10-adic integers. Any element of $\mathbb{Z}_{10}$ could formally be represented as

$$\sum_k^\infty a_k 10^k$$

3. Let $R_n = k[x_1, ..., x_n]$ with transition maps setting the last variable to 0. The limit $\varprojlim R_n$ strictly contains the polynomial ring $k[x_1, x_2, \dots]$: it also has elements of infinite support, such as the coherent sequence $(x_1,\ x_1 + x_2,\ \dots)$ representing $\sum_i x_i$

Completions are a way to construct rings. It would be nice if exactness interact nicely with it. If $\{A_n\}$, $\{B_n\}$, $\{C_n\}$ are three inverse systems where:

$$\begin{array}{ccccccccc} 0 & \longrightarrow & A_{n+1} & \xrightarrow{\psi} & B_{n+1} & \xrightarrow{\varphi} & C_{n+1} & \longrightarrow & 0 \\ & & \downarrow{\scriptstyle \alpha} & & \downarrow{\scriptstyle \beta} & & \downarrow{\scriptstyle \gamma} & & \\ 0 & \longrightarrow & A'_n & \xrightarrow{\psi'} & B'_n & \xrightarrow{\varphi'} & C'_n & \longrightarrow & 0 \end{array}$$

Then we will denote it as $0 \to \{A_n\} \to \{B_n\} \to \{C_n\} \to 0$. Then we naturally get the induced homomorphisms:

$$0 \to \varprojlim A_n \to \varprojlim B_n \to \varprojlim C_n \to 0$$

however this is not always exact. The following proposition shows us when it is:

Proposition 25.1.3: Limits and Exactness for inverse Systems

Let $0 \to \{A_n\} \to \{B_n\} \to \{C_n\} \to 0$ be an exact sequence of inverse systems. Then:

$$0 \to \varprojlim A_n \to \varprojlim B_n \to \varprojlim C_n$$

is always exact. If $\{A_n\}$ is a surjective system, then:

$$0 \to \varprojlim A_n \to \varprojlim B_n \to \varprojlim C_n \to 0$$

is always exact

Hence, when working with completions induced by surjective systems, the completion functor $\widehat{(-)}$ preserves injective and surjective functions[1].

***Proof*:**
This is an application of Snakes lemma. Let $A = \prod_{n=1}^{\infty} An$, and

$$d^A : A \to A \qquad d^A(a_n) = a_n - f_{n+1}(a_{n+1})$$

Then by construction

$$\ker d^A = \varprojlim A_n$$

We may define B, C via d^B and d^C respectively. Now, as we have an exact sequence of inverse systems, we get the following diagram:

$$\begin{array}{ccccccccc} 0 & \longrightarrow & A & \longrightarrow & B & \longrightarrow & C & \longrightarrow & 0 \\ & & \downarrow{\scriptstyle d^A} & & \downarrow{\scriptstyle d^B} & & \downarrow{\scriptstyle d^C} & & \\ 0 & \longrightarrow & A & \longrightarrow & B & \longrightarrow & C & \longrightarrow & 0 \end{array}$$

Then by proposition 17.1.10 we get:

$$0 \to \ker d^A \to \ker d^B \to \ker d^C \to \operatorname{coker} d^A \to \operatorname{coker} d^B \to \operatorname{coker} d^C \to 0$$

Finally, if the system is a surjective system, we can solve inuctively the equation:

$$x_n - f_{n+1}(x_{n+1}) = a_n$$

to show that d^A is surjective, completing the proof.

The following result shall be stated as it gives a very fascinating result, however for the full background the reader should read appendix C.5:

[1] In Part XI, this shall imply that the completion functor has trivial cohomology, while general inverse systems shall have non-trivial cohomology

Corollary 25.1.4: Completion of Group Exact Sequences

Let $0 \to G' \to G \xrightarrow{p} G'' \to 0$ be an exact sequence of groups. Let G have a topology given by the subgroups $\{G_n\}$, and induce the topology on G', G'' via the subgroups $\{G' \cap G_n\}$ and $\{p(G_n)\}$. Then:

$$0 \to \hat{G}' \to \hat{G} \to \hat{G}'' \to 0$$

is exact

***Proof*:**
Apply proposition 25.1.3 to

$$0 \to \frac{G'}{G' \cap G_n} \to \frac{G}{G_n} \to \frac{G''}{pG_n} \to 0$$

Corollary 25.1.5: Quotient in Completion

Let G be an abelian group with the topology given by a decreasing sequence of subgroups (G_m), and for each n let $\hat{G}_n$ be the completion of G_n for the induced subgroups $G_n \cap G_m$. Then the map $\hat{G}_n \to \hat{G}$ induced by the inclusion is injective, and the natural map $G \to \hat{G}$ induces an isomorphism

$$G/G_n \xrightarrow{\sim} \hat{G}/\hat{G}_n$$

***Proof*:**
Apply corollary 25.1.4 to $0 \to G_n \to G \to G/G_n \to 0$. The induced subgroups of G/G_n are $(G_m+G_n)/G_n$, which vanish for $m \geq n$, so its completion is the limit of a system whose terms from n on are G/G_n with identity transition maps, which is G/G_n. Hence $0 \to \hat{G}_n \to \hat{G} \to G/G_n \to 0$ is exact, and the map $\hat{G} \to G/G_n$ is the projection of the limit $\hat{G}$ to its term G/G_n. The composite $G \to \hat{G} \to G/G_n$ is therefore the quotient map. As $\hat{G}_n$ is the kernel of $\hat{G} \to G/G_n$, the map $G \to \hat{G}/\hat{G}_n$ kills G_n, and the induced map $G/G_n \to \hat{G}/\hat{G}_n$, followed by the isomorphism $\hat{G}/\hat{G}_n \to G/G_n$, is the identity. So it is an isomorphism, as claimed.

As a consequence, in particular interest is the case of $\mathbb{Z}_{10}$ where

$$\mathbb{Z}_{10} \cong \mathbb{Z}_2 \oplus \mathbb{Z}_5$$

Hence $\mathbb{Z}_{10}$ is decomposeable to smaller rings. These rings are also in many ways nicer: notice that as a consequence of the above isomorphism that $\mathbb{Z}_{10}$ has zero divisors (any product of two non-trivial rings has zero-divisors)[2], showing that in general the completion may introduce zero-divisors, while $\mathbb{Z}_2$ and $\mathbb{Z}_5$ do not introduce zero-divisors. Furthermore, $\mathbb{Z}_p$ introduces more units (this was more evident with $k[[x]]$ where the units were explicitly found in proposition 9.2.10). For this reason, we would concentrate on the p-adic integers $\mathbb{Z}_p$. Any element of $\mathbb{Z}_p$ could be represented as

$$\sum_k^{\infty} a_k p^k$$

[2]Can you find two explicit elements?

We may generalize the result for finding units in completions:

Lemma 25.1.6: Units In Completion

Let R be a ring, $p \subseteq R$ an ideal and $u \in R$. If the image of u in R/p^n is a unit, then so is its image in R/p^{2n}.

***Proof*:**
Choose $s \in R$ with $us - 1 \in p^n$. Then $(us-1)^2 \in p^{2n}$, and $(us-1)^2 = 1 - u(2s - us^2)$, so $u(2s-us^2) - 1 \in p^{2n}$ and the image of $2s - us^2$ is an inverse of u in R/p^{2n}, as claimed.

The reader should use this to show that u is a unit in $\hat{R}$. This also generalizes proposition 9.2.10, for this directly shows that any power series with nonzero constant is a unit. In the case where $p = \mathfrak{m}$ is a maximal ideal (as in the case for p-adic integers and $k[x]$), we get the following result:

Lemma 25.1.7: Completion At Maximal Ideals

Let R be a ring and $\mathfrak{m}$ a maximal ideal. Then $\varprojlim R/\mathfrak{m}^n$ is a local ring, that is, it contains a single maximal ideal.

***Proof*:**
Let $z = (z_n) \in \varprojlim R/\mathfrak{m}^n$ have nonzero residue $z_1 \in R/\mathfrak{m}$. Since $\mathfrak{m}/\mathfrak{m}^n$ is the unique maximal ideal of $R/\mathfrak{m}^n$, each z_n has nonzero residue mod $\mathfrak{m}$ and so is a unit there, and the inverses z_n^{-1} are coherent; hence z is a unit. Thus the non-units are exactly $\ker(\varprojlim R/\mathfrak{m}^n \to R/\mathfrak{m})$, an ideal, so $\varprojlim R/\mathfrak{m}^n$ is local.

Thus, there is a natural map:

$$R_{\mathfrak{m}} \to \varprojlim R/\mathfrak{m}^n$$

where $R_{\mathfrak{m}}$ is the localization. Recall that in $R_{\mathfrak{m}}$, the elements are constructed by taking formal inverses, hence completion at a maximal ideal shows a "dual" way of creating units by finding them in some way "at infinity". Note that it is important that $\mathfrak{m}$ be maximal, for this will fail if an ideal is only prime (however, one may localize the ring at the prime ideal to make it maximal and then take the completion).

When working with localizaiton, we saw that a localization of an integral domain is an integral domain. This is no longer true for completion:

Example 25.1.8: Completion Looses Integral Domain
Let

$$R = \frac{k[x,y]}{(y^2 - x^3 - x^2)}$$

with k a field of characteristic 0. Then completing this ring, since completion is exact, we get:

$$\hat{R} = \frac{k[[x,y]]}{(y^2 - x^3 - x^2)} \cong \frac{k[[x,y]]}{(y - x\sqrt{1+x})(y + x\sqrt{1+x})}$$

where $\sqrt{1+x}$ is the short-hand for the power-series associated to $\sqrt{1+x}$. Then it is easy to see that this ring has zero-divisors. This shall eventually be made rather clear when a geometric

perspective is taking. The ring R shall in a concrete sense have the curve $y^2 = x^3 + x^2$ associated to it:




Figure 25.2: $y^2 = x^3 + x^2$

This curve shall be shown to be *irreducible* in a concrete way. The localization shall represent this curve minus some finite amount of points. The completion at (x, y) shall represent "zooming in" at the point (x, y), at which point geometric object shall roughly correspond to:




Figure 25.3: Approximate Geometric picture corresponding to $\varprojlim R/(x, y)^n$

Then this shall be shown to be decomposable in a rigorous sense into two components (the two

strokes of the "x" in the above picture).

Definition 25.1.9: Separated and Complete

Let M be an R-module with the $\mathfrak{a}$-adic filtration, and let $\iota\colon M \to \hat{M} = \varprojlim M/\mathfrak{a}^n M$ be the natural map to its completion. Then M is

- *separated* if ι is injective, equivalently $\bigcap_n \mathfrak{a}^n M = 0$;
- *complete* if ι is surjective;

and *separated and complete* (usually abbreviated to just *complete*) if ι is an isomorphism, i.e. $M \cong \hat{M}$. A ring R is complete for the $\mathfrak{a}$-adic topology if it is so as a module over itself.

The two conditions genuinely differ: over a non-Noetherian ring a module can be complete without being separated. The completion $\hat{R}$ is separated and complete for the topology defined by the kernels of the projections $\hat{R} \to R/\mathfrak{a}^n$, and proposition 25.1.10(2) gives its universal property.

Proposition 25.1.10: Universal Property of Completion

Let R be a ring, $\mathfrak{a} \subseteq R$ an ideal, $\iota\colon R \to \hat{R} = \varprojlim R/\mathfrak{a}^n$ the natural map and $\pi_n\colon \hat{R} \to R/\mathfrak{a}^n$ the projections. Give $\hat{R}$ the topology defined by the ideals $\hat{\mathfrak{a}}_n = \ker \pi_n$. A homomorphism h between rings whose topologies are defined by decreasing sequences of ideals (I_n) and (J_n) is called *continuous* if for every n there is N with $h(I_N) \subseteq J_n$.

1. $\hat{R}$ is separated and complete for this topology: the natural map $\hat{R} \to \varprojlim \hat{R}/\hat{\mathfrak{a}}_n$ is an isomorphism.
2. Let S be a ring that is separated and complete for the $\mathfrak{b}$-adic topology of an ideal $\mathfrak{b} \subseteq S$, and let $f\colon R \to S$ be a homomorphism, continuous for the $\mathfrak{a}$-adic and $\mathfrak{b}$-adic topologies. Then there is a unique continuous homomorphism $\hat{f}\colon \hat{R} \to S$ with $\hat{f} \circ \iota = f$.

***Proof*:**
The transition maps $R/\mathfrak{a}^{n+1} \to R/\mathfrak{a}^n$ are surjective and $\pi_n \circ \iota$ is the quotient map $R \to R/\mathfrak{a}^n$, so each π_n is surjective and induces an isomorphism $\hat{R}/\hat{\mathfrak{a}}_n \cong R/\mathfrak{a}^n$.

1. Under these isomorphisms the natural map $\hat{R} \to \varprojlim \hat{R}/\hat{\mathfrak{a}}_n$ becomes $x \mapsto (\pi_n(x))_n$, which is the identity of $\varprojlim R/\mathfrak{a}^n = \hat{R}$.
2. By continuity there are $N(1) \le N(2) \le \cdots$ with $f(\mathfrak{a}^{N(n)}) \subseteq \mathfrak{b}^n$ (replace each $N(n)$ by $\max(N(1), \dots, N(n))$). Then f induces ring homomorphisms $f_n\colon R/\mathfrak{a}^{N(n)} \to S/\mathfrak{b}^n$, compatible with the transition maps. Since $S \to \varprojlim S/\mathfrak{b}^n$ is an isomorphism (definition 25.1.9), there is a ring homomorphism $\hat{f}\colon \hat{R} \to S$ such that the image of $\hat{f}(x)$ in $S/\mathfrak{b}^n$ is $f_n(\pi_{N(n)}(x))$ for every n. For $x \in R$ this image is $f(x) + \mathfrak{b}^n$, so $\hat{f}(\iota(x)) = f(x)$. If $\pi_{N(n)}(x) = 0$, then $\hat{f}(x) \in \mathfrak{b}^n$, so $\hat{f}(\hat{\mathfrak{a}}_{N(n)}) \subseteq \mathfrak{b}^n$ and $\hat{f}$ is continuous. For uniqueness, let $g\colon \hat{R} \to S$ be continuous with $g \circ \iota = f$, let $x \in \hat{R}$ and $n \ge 1$, and choose $N \ge N(n)$ with $g(\hat{\mathfrak{a}}_N) \subseteq \mathfrak{b}^n$. Since $\pi_N \circ \iota$ is surjective, some $y \in R$ has $x - \iota(y) \in \hat{\mathfrak{a}}_N \subseteq \hat{\mathfrak{a}}_{N(n)}$. Then $g(x) - f(y) = g(x - \iota(y))$ and $\hat{f}(x) - f(y) = \hat{f}(x - \iota(y))$ both lie in $\mathfrak{b}^n$, so $g(x) - \hat{f}(x) \in \mathfrak{b}^n$

for every n. As S is separated, $\bigcap_n \mathfrak{b}^n = 0$, so $g = \hat{f}$, completing the proof.

For Noetherian R, proposition 25.4.7 below gives $\hat{\mathfrak{a}}_n = \mathfrak{a}^n \hat{R}$, so the topology of (1) is then the $\mathfrak{a}\hat{R}$-adic topology.

Taking $\mathfrak{a}^n M$ as the filtration, a homomorphism $f\colon M \to N$ satisfies $f(\mathfrak{a}^n M) \subseteq \mathfrak{a}^n N$, so it induces maps on the quotients and lifts to $\hat{f}\colon \hat{M} \to \hat{N}$; completion is thus a functor.

25.2 Filtrations

The following construction is a more general version of an inverse system that drops many of the algebraic properties and is a more "pure topological" definition. It is being presented here for its use in the study of graded algebras, as well as it's use when defining *spectral sequences* in chapter 60

Definition 25.2.1: Filtration

Let M be an R-module. Then a *filtration* of M is an infinite chain:

$$M = M_0 \supseteq M_1 \supseteq \cdots \supseteq M_n \supseteq \cdots$$

where each M_n is a submodule of M. The chain is usually denoted (M_n). If furthermore $\mathfrak{a} \subseteq R$ is an ideal, then an $\mathfrak{a}$-filtration of M is a filtration st

$$\mathfrak{a}M_n \subseteq M_{n+1} \qquad \forall n \in \mathbb{N}$$

An $\mathfrak{a}$-filtration (M_n) is called *stable* (or $\mathfrak{a}$-*stable*) if there exists an N such that $\mathfrak{a}M_n = M_{n+1}$ for all $n \geq N$.

An $\mathfrak{a}$-stable filtration can be thought of as the generalization of a graded module which is in some way finite. The following lemma will be important to compare two $\mathfrak{a}$-stable filtrations:

Lemma 25.2.2: Comparing Stable $\mathfrak{a}$-Filtartions

Let $(M_n), (M'_n)$ be stable $\mathfrak{a}$-filtrations of M. Then they have bounded difference, that is, there exists an integer n_0 such that $M_{n+n_0} \subseteq M'_n$ and $M'_{n+n_0} \subseteq M_n$ for all $n \geq 0$.

This will imply that all stable $\mathfrak{a}$-filtrations determine the same topology on M (The $\mathfrak{a}$-topology)

***Proof*:**
It suffices to compare each stable $\mathfrak{a}$-filtration with the $\mathfrak{a}$-adic filtration $(\mathfrak{a}^n M)$. For any $\mathfrak{a}$-filtration, $\mathfrak{a}M_n \subseteq M_{n+1}$ gives $\mathfrak{a}^n M \subseteq M_n$ by induction. Stability provides an N with $M_{n+1} = \mathfrak{a}M_n$ for $n \geq N$, so $M_{n+N} = \mathfrak{a}^n M_N \subseteq \mathfrak{a}^n M$. Thus $\mathfrak{a}^n M \subseteq M_n$ and $M_{n+N} \subseteq \mathfrak{a}^n M$; doing the same for (M'_n) with some N' and combining, with $n_0 = \max(N, N')$, gives $M_{n+n_0} \subseteq M'_n$ and $M'_{n+n_0} \subseteq M_n$.

The key use of this lemma comes when defining the α-adic topology given in appendix C.4, namely all stable $\mathfrak{a}$-filtrations produce the same topology.

Exercise 25.2.1

1. Show that $\mathbb{Z}_p \cap \mathbb{Q} \cong \mathbb{Z}_{(p)}$
2. Show that $\hat{\hat{R}} \cong \hat{R}$

25.3 More on Graded Algebras

Graded algebras were initially explored in section 16.3. In this section, we expand further on graded-algebras, explore their relation to the Neotherian property, and look at some important associated graded algebras given an ideal I or module M. This exploration shall bear fruitful results that will be important in the development of *projective algebraic geometry* and *homological algebra*.

First, recall that a ring R is a graded ring if $R = \bigoplus_i R_i$ where $R_i R_j \subseteq R_{i+j}$, which makes R into an R_0-algebra, and each R_i is an R_0-module. A graded R-module is a module $M = \bigoplus_0^\infty M_i$ such that $R_m M_n \subseteq M_{m+n}$. If M is also a graded ring, then M is an R-graded algebra. Elements of M_n are called *homogeneous*, and an ideal $I \subseteq R$ is called homogeneous if $I = \bigoplus_i^\infty (R_i \cap I)$. A ring or R-module homomorphism is called graded if it respects the graded structure ($f(M_n) \subseteq N_n$). Each graded ring has an ideal $R_+ = \bigoplus_{n>0} R_n$. The elements of R_n for each n are called the *homogeneous elements*.

Proposition 25.3.1: Noetherian Graded Rings

Let R be a graded ring. Then the following are equivalent:

1. R is Noetherian
2. R_0 is Noetherian and R is a finitely generated R_0-algebra

***Proof*:**

(1) $\Rightarrow$ (2) As $R_0 \cong R/R_+$, R_0 is Noetherian. As $R_+ \subseteq R$ is an ideal of R, it is finitely generated, say $x_1, ..., x_s$. Then these elements can be used to construct homogeneous s element, let's use the same label and say they are of order $k_1, ..., k_s$ (all necessarily order greater than 0). Let $R' \subseteq R$ be the ring generated as an R_0 algebra over the homogeneous elements $x_1, ..., x_s$. Then I claim that $R = R'$, which will the proof. First, let' show $A_n \subseteq A'$ using induction. It is clear if $n = 0$. For $n > 0$, taking $y \in A_n$, as $y \in A_+$, y is a linear combination of the x_i

$$y = \sum_i^s a_i x_i$$

with $a_i \in A_{n-k_i}$ (and $A_m = 0$ of $m < 0$). Then by the inductive hypothesis, each a_i is a polynomial in the x's with coefficients in A_0. Hence, by the principle of induction, the same holds for y, we have that $A_n \subseteq A'$. As $A' \subseteq A$ by definition, we have $A = A'$, as we sought to show

(2) $\Rightarrow$ (1) Follow's from HBT

Any ring R induces a graded ring by taking $\mathfrak{a} \subseteq R$ and taking $R^* = \bigoplus_n^\infty \mathfrak{a}^n$. Similarly, any R-module M induces a graded R^*-module $M^* = \bigoplus_n M_n$ where M_n is the $\mathfrak{a}$-filtration. The "canonical" grading comes from $S = R[x_1, ..., x_n]$ with $\mathfrak{a} = (x_1, ..., x_n)$ which will produce the homogeneous grading of S.

In the case where R is Noetherian and $\mathfrak{a}$ is finitely generated (say by $x_1, ..., x_s$), then R^* is a quotient of the polynomial ring $R[x_1, ..., x_s]$ (with the x_i in degree 1), hence Noetherian by proposition 25.3.1.

Proposition 25.3.2: Topology of Noetherian Graded Module

Let R be a Noetherian ring, M a finitely generated R-module, (M_n) an $\mathfrak{a}$-filtration of M. Then the following are equivalent:

1. M^* is a finitely generated R^*-module
2. The filtration (M_n) is stable

***Proof*:**
This is about creating the right conditions to see the filter is stable. Take $Q_n = \bigoplus_{r=0}^n M_r$. As each M_r is finitely generated, Q_n is finitely generated. Then Q_n forms a subgroup of M^* but not in general a R^*-submodule. We may however use it to generate one:

$$M_n^* = M_0 \oplus \cdots M_n \oplus \mathfrak{a}M_n \oplus \mathfrak{a}^2 M_n \oplus \cdots \oplus \mathfrak{a}^r M_n \oplus \cdots$$

Now, as Q_n is finitely generated as an R-module, M_n^* is finitely generated as an R^*-module, and the M_n^* form an ascending chain whose unions is M^*.

Finally, we now have that as R^* is Noetherian ,M^* is finitely generated as an R^*-module if and only if the chain stops ($M^* = M_{n_0}^*$) if and only if the filtration is stable.

Corollary 25.3.3: Graded Noetherian then Component Noetherian

Let R be graded and Noetherian, and suppose M is a finitely generated graded R-module. Then M_n is a finitely-generated R_0-module for all $n \in \mathbb{N}$

***Proof*:**
Let

$$d_j = \deg m_j$$

Then every element of $m \in M_n$ can be written as:

$$m = \sum_j f_j(x) m_j \qquad f_j(x) \in R$$

where f_j is homogeneous of degree $n - d_j$ (and is zero if $n < d_j$). Hence, M_n is finitely generated as an R_0-module generated by all $g_j(x)m_j$ where $g_j(x)$ is a monomial in x_i of total degree $n - d_j$, as we sought to show.

25.4 Artin-Rees Lemma

The Artin-Rees lemma is a central result that will allow us to compare the induced and $\mathfrak{a}$-adic topology on a submodule, giving us insight on their topologies.

Theorem 25.4.1: Artin-Rees Lemma

Let R be a Noetherian ring, $\mathfrak{a} \subseteq R$ an ideal, M a finitely generated R-module, and (M_n) a stable $\mathfrak{a}$-filtration of M. Then if $M' \subseteq M$ is a submodule of M, $(M' \cap M_n)$ is a stable $\mathfrak{a}$-filtration of M'

***Proof*:**
As $\mathfrak{a}(M' \cap M_n) \subseteq \mathfrak{a}M' \cap \mathfrak{a}M_n \subseteq M' \cap M_{n+1}$, $(M' \cap M_n)$ is an $\mathfrak{a}$-filtration, and so it defines a graded R^*-module which is a submodule of M^*, and so it is finitely generated, letting us apply by proposition 25.3.2 to completing the proof.

Corollary 25.4.2: Graded Sub-module, Computational Shortcut

Let R be a Noetherian ring, $\mathfrak{a} \subseteq R$ an ideal, M a finitely generated R-module, and $M' \subseteq M$ a submodule. Then there exists a k such that

$$(\mathfrak{a}^n M) \cap M' = \mathfrak{a}^{n-k}\left((\mathfrak{a}^k M) \cap M'\right)$$

for all $n \geq k$

***Proof*:**
By the Artin-Rees lemma (theorem 25.4.1), $(\mathfrak{a}^n M \cap M')$ is a stable $\mathfrak{a}$-filtration of M', so there is a k with $\mathfrak{a}(\mathfrak{a}^n M \cap M') = \mathfrak{a}^{n+1}M \cap M'$ for all $n \geq k$; iterating gives $\mathfrak{a}^n M \cap M' = \mathfrak{a}^{n-k}(\mathfrak{a}^k M \cap M')$ for $n \geq k$.

Theorem 25.4.3: Submodule Adic Topology Equivalence

Let R be a Noetherian ring, $\mathfrak{a} \subseteq R$ an ideal, M a finitely generated R-module, $M' \subseteq M$ a submodule. Then the filtrations

$$\mathfrak{a}^n M' \qquad \text{and} \qquad (\mathfrak{a}^n M) \cap M'$$

have bounded difference, hence the $\mathfrak{a}$-topology of M' coincides with the induced topology given by the $\mathfrak{a}$-topology of M

***Proof*:**
Always $\mathfrak{a}^n M' \subseteq (\mathfrak{a}^n M) \cap M'$. By corollary 25.4.2 there is k with $(\mathfrak{a}^{n+k}M) \cap M' = \mathfrak{a}^n\left((\mathfrak{a}^k M) \cap M'\right) \subseteq \mathfrak{a}^n M'$ for all $n \geq 0$. Hence $\mathfrak{a}^{n+k}M' \subseteq (\mathfrak{a}^n M) \cap M'$ and $(\mathfrak{a}^{n+k}M) \cap M' \subseteq \mathfrak{a}^n M'$ for all n, which is bounded difference with $n_0 = k$. So each subgroup in either family contains one of the other family, and the neighborhoods $x + \mathfrak{a}^n M'$ and $x + (\mathfrak{a}^n M) \cap M'$ define the same topology on M', as claimed.

Corollary 25.4.4: Module Completion Preserves Exactness

Let

$$0 \to M' \to M \to M'' \to 0$$

be a short exact sequence of finitely generated R-modules over a Noetherian ring R. Then if $\mathfrak{a} \subseteq R$ is an ideal, the $\mathfrak{a}$-adic completion functor preserves exactness:

$$0 \to \hat{M}' \to \hat{M} \to \hat{M}'' \to 0$$

***Proof*:**
Theorem 25.4.3 provides the condition needed to use corollary 25.1.4.

Next, as we have a natural homomorphism $R \to \hat{R}$, we can think of $\hat{R}$ as an R-algebra, and hence we have an extension of scalars of an R-module M given to an $\hat{R}$-module $\hat{R} \otimes_R M$. This gives a natural sequence of maps that we may want to understand:

$$\hat{R} \otimes_R M \to \hat{R} \otimes_R \hat{M} \to \hat{R} \otimes_{\hat{R}} \hat{M} = \hat{M}$$

In general, these maps are neither injective nor surjective. Under nicer conditions, we have a better control:

Proposition 25.4.5: Module Completion as Tensor Product

Let R be any ring. Then if$M$ is finitely generated,

$$\hat{R} \otimes_R M \twoheadrightarrow \hat{M}$$

is surjective. If furthermore R is Neotherian, then:

$$\hat{R} \otimes_R M \cong \hat{M}$$

***Proof*:**
Let $F \cong R^n$ so that $M \cong F/N$ for appropriate N. The conclusion can be drawn from the following commutative diagram:

$$\begin{array}{ccccccccc} & & \hat{R} \otimes_R N & \longrightarrow & \hat{R} \otimes_R F & \longrightarrow & \hat{R} \otimes_R M & \longrightarrow & 0 \\ & & \downarrow{\scriptstyle \gamma} & & \downarrow{\scriptstyle \beta} & & \downarrow{\scriptstyle \alpha} & & \\ 0 & \longrightarrow & \hat{N} & \longrightarrow & \hat{F} & \xrightarrow{\delta} & \hat{M} & \longrightarrow & 0 \end{array}$$

where the top line is given by the right-exactness of the tensor product, and the bellow line is given by corollary 25.1.4. Note that as completion commutes with finite direct sums (use corollary 25.1.4), we have that $\hat{R} \otimes_R F \cong \hat{F}$, and so α is surjective, giving us the first part. If R is Noetherian, hen N is finitely generated and so γ is surjective, and so we get exactness of the bottom line. Then by chasing the diagram we will get hat α is injective, and hence an isomorphism, completing the proof.

From this, we get that when R is Noetherian, the completion functor $\widehat{(-)}$ agrees with the extension of scalars $\hat{R} \otimes_R (-)$ on finitely generated R-modules, and is exact there. As a consequence:

Corollary 25.4.6: Flatness of Completion

Let R be a Neotherian ring, $\mathfrak{a} \subseteq R$ an ideal, $\hat{R}$ the $\mathfrak{a}$-adic completing of R. Then $\hat{R}$ is a flat R-algebra.

***Proof*:**

Step 1: injections of finitely generated modules. Let $f\colon M' \to M$ be an injective homomorphism of finitely generated R-modules. Applying corollary 25.4.4 to $0 \to M' \to M \to M/M' \to 0$, whose terms are finitely generated, shows that $\hat{f}\colon \hat{M'} \to \hat{M}$ is injective. For finitely generated N, the map $\alpha_N\colon \hat{R} \otimes_R N \to \hat{N}$, $r \otimes x \mapsto r\,\iota_N(x)$, is an isomorphism by proposition 25.4.5, and $\alpha_M \circ (\mathrm{id} \otimes f) = \hat{f} \circ \alpha_{M'}$, since both send $r \otimes x$ to $r\,\iota_M(f(x))$. Hence $\mathrm{id} \otimes f = \alpha_M^{-1} \circ \hat{f} \circ \alpha_{M'}$ is injective.

Step 2: arbitrary injections. Let $f\colon N' \to N$ be an injective homomorphism of R-modules and let $u = \sum_{i=1}^{k} r_i \otimes y_i \in \hat{R} \otimes_R N'$ satisfy $(\mathrm{id} \otimes f)(u) = 0$. By definition 15.1.3, $\hat{R} \otimes_R N$ is the free abelian group on $\hat{R} \times N$ modulo the subgroup generated by the bilinearity relations, so $\sum_i (r_i, f(y_i))$ is a finite $\mathbb{Z}$-linear combination of such relations. Let $N_0 \subseteq N$ be the submodule generated by the $f(y_i)$ and the finitely many elements of N occurring in these relations. Each of them is also a relation for $\hat{R} \times N_0$, so $\sum_i r_i \otimes f(y_i) = 0$ in $\hat{R} \otimes_R N_0$. Let $N_0' \subseteq N'$ be the submodule generated by $y_1, \dots, y_k$. Then f restricts to an injection $f_0\colon N_0' \to N_0$ of finitely generated modules with $(\mathrm{id} \otimes f_0)\big(\sum_i r_i \otimes y_i\big) = 0$, so $\sum_i r_i \otimes y_i = 0$ in $\hat{R} \otimes_R N_0'$ by Step 1. Its image in $\hat{R} \otimes_R N'$ is u, so $u = 0$. Thus $\hat{R} \otimes_R -$ preserves injections, which is condition (2) of proposition 17.5.3, so $\hat{R}$ is flat by definition 17.5.4, completing the proof.

Proposition 25.4.7: Properties of Adic Completion

Let R be Noetherian and $\hat{R}$ its $\mathfrak{a}$-adic completion. Then:

1. $\hat{\mathfrak{a}} = \hat{R}\mathfrak{a} = \hat{R} \otimes_R \mathfrak{a}$
2. $\widehat{\mathfrak{a}^n} = \hat{\mathfrak{a}}^n$
3. $\mathfrak{a}^n/\mathfrak{a}^{n+1} \cong \hat{\mathfrak{a}}^n/\hat{\mathfrak{a}}^{n+1}$
4. $\hat{\mathfrak{a}}$ is contained in the Jacobson radical of $\hat{R}$

***Proof*:**

Write $\pi_k\colon \hat{R} \to R/\mathfrak{a}^k$ for the projections, which are ring homomorphisms, and $\iota\colon R \to \hat{R}$ for the natural map. For $n \geq 1$, apply corollary 25.1.4 to $0 \to \mathfrak{a}^n \to R \to R/\mathfrak{a}^n \to 0$ with the subgroups $\mathfrak{a}^m$ of R. The induced subgroups $(\mathfrak{a}^m + \mathfrak{a}^n)/\mathfrak{a}^n$ of $R/\mathfrak{a}^n$ vanish for $m \geq n$, so $R/\mathfrak{a}^n$ is its own completion. The induced subgroups $\mathfrak{a}^n \cap \mathfrak{a}^m$ of $\mathfrak{a}^n$ run through the $\mathfrak{a}^j$ with $j \geq n$, as do the submodules $\mathfrak{a}^k\mathfrak{a}^n$, so the completion of $\mathfrak{a}^n$ is its $\mathfrak{a}$-adic completion $\widehat{\mathfrak{a}^n}$. Hence

$$0 \to \widehat{\mathfrak{a}^n} \to \hat{R} \xrightarrow{\pi_n} R/\mathfrak{a}^n \to 0$$

is exact, and we regard $\widehat{\mathfrak{a}^n} = \ker \pi_n$ as an ideal of $\hat{R}$. The map $\widehat{\mathfrak{a}^n} \to \hat{R}$ is computed coordinatewise, so it is $\hat{R}$-linear and sends the image of $a \in \mathfrak{a}^n$ to $\iota(a)$. Since R is Noetherian, $\mathfrak{a}^n$ is finitely generated, so proposition 25.4.5 gives an isomorphism $\hat{R} \otimes_R \mathfrak{a}^n \to \widehat{\mathfrak{a}^n}$, $r \otimes a \mapsto r\,\iota(a)$, whose image in $\hat{R}$ is the set of sums $\sum_i r_i \iota(a_i)$, that is the ideal $\hat{R}\mathfrak{a}^n$. So for every $n \geq 1$,

$$\widehat{\mathfrak{a}^n} = \hat{R}\mathfrak{a}^n \cong \hat{R} \otimes_R \mathfrak{a}^n$$

1. This is the case $n = 1$ of the last display.
2. The ideals $\hat{R}\mathfrak{a}^n$ and $(\hat{R}\mathfrak{a})^n$ are both generated by the products $\iota(a_1) \cdots \iota(a_n)$ with $a_j \in \mathfrak{a}$, so the last display and (1) give $\widehat{\mathfrak{a}^n} = \hat{R}\mathfrak{a}^n = (\hat{R}\mathfrak{a})^n = \hat{\mathfrak{a}}^n$.
3. The projection π_{n+1} is surjective with kernel $\widehat{\mathfrak{a}^{n+1}}$, and composing it with $R/\mathfrak{a}^{n+1} \to R/\mathfrak{a}^n$ gives π_n. So π_{n+1} maps $\widehat{\mathfrak{a}^n} = \ker \pi_n$ onto the kernel $\mathfrak{a}^n/\mathfrak{a}^{n+1}$ of $R/\mathfrak{a}^{n+1} \to R/\mathfrak{a}^n$, and as $\widehat{\mathfrak{a}^{n+1}} \subseteq \widehat{\mathfrak{a}^n}$ it induces $\widehat{\mathfrak{a}^n}/\widehat{\mathfrak{a}^{n+1}} \cong \mathfrak{a}^n/\mathfrak{a}^{n+1}$. By (2) the left side is $\hat{\mathfrak{a}}^n/\hat{\mathfrak{a}}^{n+1}$. These isomorphisms are induced by the ring homomorphisms π_k, so they are compatible with products.
4. Let $x = (x_k)_k \in \hat{\mathfrak{a}} = \ker \pi_1$. Each $x_k \in R/\mathfrak{a}^k$ maps to $x_1 = 0$ in $R/\mathfrak{a}$, so $x_k \in \mathfrak{a}/\mathfrak{a}^k$ and $x_k^k = 0$. Hence $1 - x_k$ is a unit of $R/\mathfrak{a}^k$ with inverse $u_k = 1 + x_k + \cdots + x_k^{k-1}$. The transition map $R/\mathfrak{a}^{k+1} \to R/\mathfrak{a}^k$ is a ring homomorphism sending $1 - x_{k+1}$ to $1 - x_k$, so it sends u_{k+1} to the inverse of $1 - x_k$, which is u_k. Thus $u = (u_k)_k \in \hat{R}$ and $(1 - x)u = 1$. (This is the convergence of $1 + x + x^2 + \cdots$ in $\hat{R}$: for $N \geq k$ the partial sum $\sum_{i<N} x^i$ has image u_k in $R/\mathfrak{a}^k$.) As $\hat{\mathfrak{a}}$ is an ideal, $1 - rx$ is a unit for all $r \in \hat{R}$ and $x \in \hat{\mathfrak{a}}$, so $\hat{\mathfrak{a}}$ lies in the Jacobson radical of $\hat{R}$ by proposition 23.4.26(3), completing the proof.

Let us next characterize the kernel of the map $M \to \hat{M}$

Theorem 25.4.8: Krull's Theorem

LEt R be a Noetherian ring, $\mathfrak{a} \subseteq R$ an ideal, M a finitely generated R-module, and $\hat{M}$ the $\mathfrak{a}$-completion of M, Then the kernel

$$E = \bigcap_{n=1}^{\infty} \mathfrak{a}^n M$$

given by the map $M \to \hat{M}$ consist of all $x \in M$ that are annihilated by some element $1 + \mathfrak{a}$.

***Proof*:**
It suffices to show that $(1 - \alpha)E = 0$. IT is clear that if $(1 - \alpha)x = 0$

$$x = \alpha x = \alpha^2 x = \cdots \in \bigcap_{n=1}^{\infty} \mathfrak{a}^n M = E$$

Hence we shall show the converse. By the Artin-Rees consequence (corollary 25.4.2) applied to $E \subseteq M$, there is a k with $\mathfrak{a}^n M \cap E = \mathfrak{a}^{n-k}(\mathfrak{a}^k M \cap E)$ for $n \geq k$. Since $E \subseteq \mathfrak{a}^n M$ for all n, the left-hand side is E and the right-hand side is $\mathfrak{a}^{n-k}E$, so $E = \mathfrak{a}^{n-k}E \subseteq \mathfrak{a}E$, giving $\mathfrak{a}E = E$. As M is finitely generated over the Noetherian ring R, E is finitely generated, so the determinant

form of Nakayama's lemma yields $\alpha \in \mathfrak{a}$ with $(1-\alpha)E = 0$, completing the proof.

Proposition 25.4.9: Localization is A Subring of Completion

Let R be Noetherian and let $S = 1 + \mathfrak{a}$. Then

$$S^{-1}R \hookrightarrow \hat{R}$$

***Proof*:**

By Krull's theorem (theorem 25.4.8 with $M = R$), the kernel of $\iota\colon R \to \hat{R}$ consists of the x with $(1+\alpha)x = 0$ for some $\alpha \in \mathfrak{a}$, which is the kernel of $R \to S^{-1}R$ (corollary 23.4.3). Each $s = 1 + \alpha \in S$ maps to $1 + \iota(\alpha)$ with $\iota(\alpha) \in \hat{\mathfrak{a}}$, which is a unit of $\hat{R}$ by proposition 25.4.7(4) and proposition 23.4.26(3). So the universal property of localization (theorem 23.4.1) gives a homomorphism $S^{-1}R \to \hat{R}$, $x/s \mapsto \iota(x)\iota(s)^{-1}$. If $\iota(x)\iota(s)^{-1} = 0$, then $\iota(x) = 0$, so $x/1 = 0$ in $S^{-1}R$ and $x/s = 0$. The homomorphism is therefore injective, as claimed.

The Noetherian condition is necessary, an easy example lies within the realm of analysis:

Example 25.4.10: Localization and Completion Without Noetherian Property

Take R to be the collection of smooth functions on $\mathbb{R}$, $C^\infty(\mathbb{R})$. Let $\mathfrak{a}$ be the ideal of all f which vanish at 0. This ideal is maximal as $R/\mathfrak{a} \cong \mathbb{R}$. Then $\mathfrak{a}$ is generated by x (if you know some multi-variable calculus prove that any f that vanishes at 0 can be written as $f(x) = xg(x)$ for g smooth, it is a variation of Hadamard's lemma), and $E = \bigcap_{n=1}^{\infty} \mathfrak{a}^n$ is the set of all $f \in R$ such that all derivatives vanish at the origin. On the other hand, f is annihilated by some element $1 + \alpha$ for $\alpha \in \mathfrak{a}$ iff f vanishes identically in some neighborhood of 0. Now, the function e^{-1/x^2} has vanishing derivative at 0, but is not identically zero near 0. Hence the kernels of the $R \to \hat{R}$ and $\mathbb{R} \to S^{-1}R$ with $S = 1 + \mathfrak{a}$ do not coincide.

This can also be a way of showing that R cannot be Noetherian.

Corollary 25.4.11: Krull Theorem, Noetherian Domain

Let R be a Noetherian domain and $(1) \neq \mathfrak{a} \subseteq R$ an ideal. Then

$$\bigcap \mathfrak{a}^n = 0$$

***Proof*:**

By Krull's theorem (theorem 25.4.8), $\bigcap \mathfrak{a}^n$ consists of the x annihilated by some $1 + \alpha$ with $\alpha \in \mathfrak{a}$. Since $\mathfrak{a}$ is proper, $-1 \notin \mathfrak{a}$, so $1 + \alpha \neq 0$; as R is a domain, $(1+\alpha)x = 0$ forces $x = 0$, whence $\bigcap \mathfrak{a}^n = 0$.

Corollary 25.4.12: Krull Theorem, Hausdorff Topology

Let R be a Noetherian ring, $\mathfrak{a} \subseteq R$ an ideal contained in the Jacobson radical, and M a finitely generated R-module. Then the $\mathfrak{a}$-topology of M is Hausdroff, i.e.

$$\bigcap \mathfrak{a}^n M = 0$$

***Proof*:**
Since $\mathfrak{a} \subseteq \mathrm{Jac}(R)$, every element of $1 + \mathfrak{a}$ is a unit (proposition 23.4.26). By Krull's theorem (theorem 25.4.8), each element of $\bigcap \mathfrak{a}^n M$ is annihilated by such a unit, hence is 0.

Corollary 25.4.13: Krull Theorem, Kernel Into Localization

Let R be a Noetherian ring, $\mathfrak{p} \subseteq R$ a prime ideal. Then the intersection of all $\mathfrak{p}$-primary ideals of A is the kernel of $A \to A_{\mathfrak{p}}$

***Proof*:**
Write $K = \ker(A \to A_{\mathfrak{p}}) = \{a \in A \mid sa = 0 \text{ for some } s \notin \mathfrak{p}\}$. Every $\mathfrak{p}$-primary ideal $\mathfrak{q}$ contains K: if $sa = 0 \in \mathfrak{q}$ with $s \notin \mathfrak{p} = \sqrt{\mathfrak{q}}$, then $a \in \mathfrak{q}$; hence $K \subseteq \bigcap\{\mathfrak{p}\text{-primary}\}$. Conversely the symbolic powers $\mathfrak{p}^{(n)} = (\mathfrak{p}^n A_{\mathfrak{p}}) \cap A$ are $\mathfrak{p}$-primary, and since $\mathfrak{p}A_{\mathfrak{p}}$ lies in the Jacobson radical of $A_{\mathfrak{p}}$, corollary 25.4.12 gives $\bigcap_n \mathfrak{p}^n A_{\mathfrak{p}} = 0$, whence $\bigcap_n \mathfrak{p}^{(n)} = K$. Thus $\bigcap\{\mathfrak{p}\text{-primary}\} \subseteq \bigcap_n \mathfrak{p}^{(n)} = K$, and the two inclusions give equality.

25.5 Associated Graded Rings: Noetherian Closed under Completion

The following will let us show another way of characterizing complete rings, and let us prove that the completion of a Noetherian ring is Noetherian.

Definition 25.5.1: Associated Graded Ring

Let R be a ring and $\mathfrak{a} \subseteq R$ an ideal. Then the *associated graded ring* is

$$G_{\mathfrak{a}}(R) = \bigoplus_{n=0}^{\infty} \mathfrak{a}^n / \mathfrak{a}^{n+1}$$

where $\mathfrak{a}^0 = R$. If unambiguous, $G(R)$ will be written instead of $G_{\mathfrak{a}}(R)$. For an R-module M with an $\mathfrak{a}$-filtration (M_n), the graded $G(R)$-module is given by:

$$G(M) = \bigoplus_{n=0}^{\infty} M_n / M_{n+1} = \bigoplus_{n=0}^{\infty} G_n(M)$$

Multiplication is certainly well-defined: for each $x_n \in \mathfrak{a}^n$, $\overline{x}_n$ is the image of x_n in $\mathfrak{a}^n/\mathfrak{a}^{n+1}$. Then $\overline{x}_m\overline{x}_m$ is $\overline{x_m x_n}$ which is the image of $x_m x_n$ in $\mathfrak{a}^{m+n}/\mathfrak{a}^{m+n+1}$ (if the reader is not convinced, check to see if this is well-defined).

Proposition 25.5.2: Properties of Associated Graded Rings

Let R be a Noetherian ring and $\mathfrak{a} \subseteq R$ an ideal. Then:

1. $G_\mathfrak{a}(R)$ is Noetherian
2. $G_\mathfrak{a}(R)$ is isomorphic to $G_{\hat{\mathfrak{a}}}(\hat{R})$ as graded rings
3. If M is a finitely generated R-module and (M_n) is a stable $\mathfrak{a}$-filtration of M, then $G(M)$ is a finitely generated graded $G_\mathfrak{a}(R)$-module

***Proof*:**

1. $G_\mathfrak{a}(R)$ is generated as an algebra over the Noetherian ring $R/\mathfrak{a}$ by the images of generators of $\mathfrak{a}$ in $\mathfrak{a}/\mathfrak{a}^2$, hence is Noetherian by HBT (theorem 23.2.1).
2. By proposition 25.4.7(3), $\mathfrak{a}^n/\mathfrak{a}^{n+1} \cong \hat{\mathfrak{a}}^n/\hat{\mathfrak{a}}^{n+1}$ in each degree, and these degreewise isomorphisms respect multiplication, giving $G_\mathfrak{a}(R) \cong G_{\hat{\mathfrak{a}}}(\hat{R})$.
3. Pick N with $\mathfrak{a}M_n = M_{n+1}$ for $n \geq N$ (stability). Then $G(M)$ is generated over $G_\mathfrak{a}(R)$ by the finitely many pieces M_n/M_{n+1} with $n \leq N$, each finitely generated over $R/\mathfrak{a}$ (corollary 25.3.3); hence $G(M)$ is finitely generated over $G_\mathfrak{a}(R)$.

The most important case of an associated graded ring is the one where the ideal is generated by a regular sequence: there the associated graded ring is as simple as it could be, a polynomial ring, and the geometric consequence is that the normal cone of a regularly embedded subscheme is a vector bundle rather than a general cone.

Theorem 25.5.3: Associated Graded Ring of a Regular Sequence

Let A be a Noetherian ring and let $x_1, \ldots, x_d \in A$ be a regular sequence ([29, Regular Sequence], a co-requisite of this book: x_i is a nonzerodivisor on $A/(x_1, \ldots, x_{i-1})$ for each i, and $A/(x_1, \ldots, x_d) \neq 0$). Let $\mathfrak{a} = (x_1, \ldots, x_d)$. Then the $(A/\mathfrak{a})$-algebra homomorphism

$$(A/\mathfrak{a})[T_1, \ldots, T_d] \longrightarrow G_\mathfrak{a}(A), \qquad T_i \longmapsto \overline{x_i} \in \mathfrak{a}/\mathfrak{a}^2$$

is an isomorphism of graded rings. In particular $\mathfrak{a}^n/\mathfrak{a}^{n+1}$ is a free $A/\mathfrak{a}$-module on the monomials of degree n in the $\overline{x_i}$.

***Proof*:**

Surjectivity. The ideal $\mathfrak{a}^n$ is generated by the degree-n monomials in the x_i, so $\mathfrak{a}^n/\mathfrak{a}^{n+1}$ is generated as an $A/\mathfrak{a}$-module by their classes, which are the images of the degree-n monomials in the T_i. Surjectivity in each degree follows.

Injectivity, by induction on d. For $d = 0$ the ideal is zero and both sides are A.

Suppose $d \geq 1$ and the statement holds for shorter regular sequences. Let $F \in (A/\mathfrak{a})[T_1, \ldots, T_d]$ be homogeneous of degree n with $F(\overline{x}) \in \mathfrak{a}^{n+1}$; the claim is that all coefficients of F vanish in $A/\mathfrak{a}$. Lift the coefficients to A and write F for a lift, so $F(x_1, \ldots, x_d) \in \mathfrak{a}^{n+1}$.

Group F by its T_d-degree, $F = \sum_j T_d^j G_j(T_1, \ldots, T_{d-1})$ with G_j homogeneous of degree $n-j$. Reducing modulo x_d kills every term with $j > 0$, so $G_0(\overline{x_1}, \ldots, \overline{x_{d-1}}) \in \overline{\mathfrak{a}}^{\,n+1}$ in $A/(x_d)$, where $x_1, \ldots, x_{d-1}$ is again a regular sequence and generates $\overline{\mathfrak{a}}$. By the inductive hypothesis applied in $A/(x_d)$, every coefficient of G_0 lies in $\mathfrak{a} + (x_d) = \mathfrak{a}$, which is the required vanishing for the $j = 0$ part.

Hence $F - G_0 = T_d \cdot H$ for a homogeneous H of degree $n-1$, and $x_d \cdot H(x) = F(x) - G_0(x) \in \mathfrak{a}^{n+1}$. Since $G_0(x) \in \mathfrak{a}^{n+1}$ we get $x_d H(x) \in \mathfrak{a}^{n+1}$. Now $\mathfrak{a}^{n+1} = x_d \mathfrak{a}^n + \mathfrak{a}'^{\,n+1}$ where $\mathfrak{a}'$ is generated by $x_1, \ldots, x_{d-1}$; writing $x_d H(x) = x_d a + b$ with $a \in \mathfrak{a}^n$ and $b \in \mathfrak{a}'^{\,n+1}$ gives $x_d(H(x) - a) = b$. Because x_d is a nonzerodivisor modulo $\mathfrak{a}'$ and $b \in \mathfrak{a}'^{\,n+1} \subseteq \mathfrak{a}'$, this forces $H(x) - a \in \mathfrak{a}^n$, hence $H(x) \in \mathfrak{a}^n$. The inductive hypothesis in degree $n-1$, applied to H, then gives that all coefficients of H lie in $\mathfrak{a}$, completing the induction and the proof.

Lemma 25.5.4: Associated Graded Ideal and Completion Map Relation

Let $\varphi : A \to B$ be a homomorphism of filtered groups ($\varphi(A_n) \subseteq B_n$), and let $G(\varphi) : G(A) \to G(B)$, $\hat{\varphi}\hat{A} \to \hat{B}$ be the induced homomorphisms of the associated graded group and complete group respectively. Then:

1. $G(\varphi)$ is injective $\Rightarrow$ $\hat{\varphi}$ is injective
2. $G(\varphi)$ is surjective $\Rightarrow$ $\hat{\varphi}$ is surjective

***Proof*:**
The key is to look at the following commutative diagram of exact sequences:

$$\begin{array}{ccccccccc} 0 & \longrightarrow & A_n/A_{n+1} & \longrightarrow & A/A_{n+1} & \longrightarrow & A/A_n & \longrightarrow & 0 \\ & & \downarrow{\scriptstyle G_n(\varphi)} & & \downarrow{\scriptstyle \alpha_{n+1}} & & \downarrow{\scriptstyle \alpha_n} & & \\ 0 & \longrightarrow & B_n/B_{n+1} & \longrightarrow & B/B_{n+1} & \longrightarrow & B/B_n & \longrightarrow & 0 \end{array}$$

which by the snake lemma gives us the usual:

$$0 \to \ker G_n(\varphi) \to \ker \alpha_{n+1} \to \ker \alpha_n \to \mathrm{coker} G_n(\varphi) \to \mathrm{coker} \alpha_{n+1} \to \mathrm{coker} \alpha_n \to 0$$

Now, by induction on n, we see that:

1. $\ker \alpha_n = 0$
2. $\mathrm{coker} \alpha_n = 0$

taking the limit of the homomorphisms α_n and applying proposition 25.1.3 completes the proof.

Proposition 25.5.5: Partial Converse of proposition 25.5.2(3)

Let R be a ring, $\mathfrak{a} \subseteq R$ an ideal, M an R-module, and (M_n) an $\mathfrak{a}$-filtration of M. Suppose R is complete in the $\mathfrak{a}$-topology, M is Hausdorff in its filtration topology ($\bigcap_n M_n = 0$), and $G(M)$ is a finitely generated $G(R)$-module.

Then M is a finitely generated R-module.

***Proof*:**
As $G(M)$ is finitely generated, pick some finite set of generators. Split them up into the homogeneous components, say ζ_i (with $1 \leq i \leq \nu$) where ζ_i has degree $n(i)$, and is the image of some $x_i \in M_{n(i)}$. Let F^i be the module with the stable $\mathfrak{a}$-filtration given by $F^i_K = \mathfrak{a}^{k+n(i)}$ and let $F = \bigoplus_{i=1}^r F^i$. Then the mapping that takes the generator 1 of each F^i to x_i gives a homomorphism of filtered groups

$$\varphi : F \to M$$

Hence it induces a homomorphism of $G(A)$-modules. By construction this map is surjective. Hence by lemma 25.5.4 $\hat{\varphi}$ is surjective. Now consider the diagram:

$$\begin{array}{ccc} F & \xrightarrow{\varphi} & M \\ {\scriptstyle\alpha}\downarrow & & \downarrow{\scriptstyle\beta} \\ \hat{F} & \xrightarrow{\hat{\varphi}} & \hat{M} \end{array}$$

As F is free and $A = \hat{A}$, α is an isomorphism. Next, as M is Hausdorff, β is injective. . As $\hat{\varphi}$ is surjective, φ is surjective, and so $x_1, ..., x_r$ generate M as an A-module completing the proof.

Corollary 25.5.6: Partial Converse in Noetherian Case

Let R be a ring, $\mathfrak{a} \subseteq R$ an ideal, M an R-module, and (M_n) an $\mathfrak{a}$-filtration of M. Suppose R is complete in the $\mathfrak{a}$-topology, M is Hausdorff in its filtration topology ($\bigcap_n M_n = 0$), and $G(M)$ is a finitely generated $G(R)$-module.

Then if $G(M)$ is a Noetherian $G(R)$-module, then M is a Noetherian R-module.

***Proof*:**
If we show that every submodule $M' \subseteq M$ is finitely generated, we are done. Let $M'_n = M' \cap M_n$. Then (M'_n) is an $\mathfrak{a}$-filtration of M', and the embedding $M'_n \to M_N$ induces an injective homomorphism:

$$M'_n/M'_{n+1} \to M_n/M_{n+1}$$

Hence we gt a embedding of $G(M')$ in $G(M)$, $G(M)$ is Noetherian, $G(M')$ is finitely generated, and so M' is Hausdroff. As $\cap M'_n \subseteq \cap M_N = 0$, we get that M' is finitely generated, as we sought to show.

Theorem 25.5.7: Noetherian Closed Under Completion

Let R be a Noetherian ring and $\mathfrak{a} \subseteq R$ an ideal. Then the $\mathfrak{a}$-completion $\hat{R}$ of R is Noetherian

***Proof*:**
As:

$$G_{\mathfrak{a}}(R) = G_{\hat{\mathfrak{a}}}(\hat{R})$$

is Noetherian, apply corollary 25.5.6 to the complete ring $\hat{R}$ and taking $M = \hat{R}$.

Corollary 25.5.8: Power Series Ring is Noetherian

Let R be a Noetherian ring, and let $S = R[[x_1, ..., x_n]]$ be the power series ring in n variables. Then S is Noetherian.

***Proof*:**
The ring $R[x_1, ..., x_n]$ is Noetherian by Hilbert's Basis Theorem, and S is the completion for the $(x_1, ..., x_n)$-adic topology.

25.6 The Cohen Structure Theorem

Completion gives the local structure of a ring coordinates: a complete Noetherian local ring containing its residue field is a quotient of a power series ring, the algebraic form of a formal coordinate chart around a point.

Theorem 25.6.1: Cohen Structure Theorem, Equicharacteristic Case

Let $(R, \mathfrak{m})$ be a complete Noetherian local ring containing a field k with $R/\mathfrak{m} = k$. Then $R \cong k[[x_1, \dots, x_n]]/I$ for an ideal I, where $n = \dim_k \mathfrak{m}/\mathfrak{m}^2$ is the minimal number of generators of $\mathfrak{m}$.

***Proof*:**
Choose $y_1, \dots, y_n \in \mathfrak{m}$ whose residues form a k-basis of $\mathfrak{m}/\mathfrak{m}^2$; by Nakayama's lemma (lemma 23.4.27) they generate $\mathfrak{m}$. The composite $k \hookrightarrow R \twoheadrightarrow R/\mathfrak{m} = k$ is the identity, making R a k-algebra, so we may define

$$\varphi \colon k[[x_1, \dots, x_n]] \to R, \qquad \sum_{\alpha} c_\alpha x^\alpha \mapsto \sum_{\alpha} c_\alpha y^\alpha,$$

the sum on the right converging because $y^\alpha \in \mathfrak{m}^{|\alpha|}$ and R is $\mathfrak{m}$-adically complete (definition 25.1.9); φ is a k-algebra homomorphism. For surjectivity, reduce modulo $\mathfrak{m}^m$. Each graded piece $\mathfrak{m}^j/\mathfrak{m}^{j+1}$ is spanned over k by the degree-j monomials in the residues $\bar{y}_i$, since multiplication gives a surjection $\mathrm{Sym}^j(\mathfrak{m}/\mathfrak{m}^2) \twoheadrightarrow \mathfrak{m}^j/\mathfrak{m}^{j+1}$ and $\mathfrak{m}/\mathfrak{m}^2$ is spanned by the $\bar{y}_i$. Hence $R/\mathfrak{m}^m$, whose composition factors are the $\mathfrak{m}^j/\mathfrak{m}^{j+1}$ for $j < m$, is spanned over k by monomials in the y_i of degree $< m$, all in the image of φ; so φ is surjective modulo every $\mathfrak{m}^m$. As $R = \varprojlim R/\mathfrak{m}^m$ and $k[[x_1, \dots, x_n]]$ is complete, φ is surjective. Thus $R \cong k[[x_1, \dots, x_n]]/I$ with $I = \ker \varphi$, and

$n = \dim_k \mathfrak{m}/\mathfrak{m}^2$ is minimal by the choice of the y_i.

The hypothesis $R/\mathfrak{m} = k$ is the equicharacteristic case with trivial residue extension, the form deformation theory over a field uses. In general Cohen's theorem first produces a *coefficient field* $k \hookrightarrow R$ lifting the residue field (equicharacteristic case) or, in mixed characteristic, a complete discrete valuation coefficient ring; that mixed-characteristic theory, through Witt vectors, is developed in [33].

25.7 Weierstrass Preparation and Division

The Cohen structure theorem realizes a complete local ring as a quotient of a power series ring; the *Weierstrass* theorems describe the internal structure of the power series ring itself, showing that division by a sufficiently generic series behaves like polynomial division. Fix a complete local ring $(R, \mathfrak{m})$ (for instance $R = k[[x_1, \dots, x_{n-1}]]$) and one further variable x.

Definition 25.7.1: Regular Power Series

A power series $f = \sum_{i \geq 0} a_i x^i \in R[[x]]$ is *regular of order* d in x if $a_0, \dots, a_{d-1} \in \mathfrak{m}$ and a_d is a unit; equivalently, its image in $(R/\mathfrak{m})[[x]]$ is x^d times a unit.

Theorem 25.7.2: Weierstrass Division Theorem

Let $(R, \mathfrak{m})$ be complete and $f \in R[[x]]$ regular of order d in x. Then every $g \in R[[x]]$ can be written uniquely as

$$g = qf + r, \qquad q \in R[[x]], \quad r \in R[x], \ \deg r < d$$

Theorem 25.7.3: Weierstrass Preparation Theorem

Let $(R, \mathfrak{m})$ be complete and $f \in R[[x]]$ regular of order d in x. Then $f = u\,\omega$ uniquely, where $u \in R[[x]]$ is a unit and

$$\omega = x^d + b_{d-1}x^{d-1} + \cdots + b_0, \qquad b_i \in \mathfrak{m},$$

is a monic *Weierstrass polynomial*.

***Proof*:**
Preparation follows from division: apply theorem 25.7.2 to $g = x^d$, writing $x^d = qf + r$ with $\deg r < d$; reducing modulo $\mathfrak{m}$ shows q is a unit and $\omega := x^d - r$ is a Weierstrass polynomial, so $f = u\omega$ with $u = q^{-1}$. Division itself is proved by successive approximation: writing $f = P + x^d U$ with $P = \sum_{i<d} a_i x^i \in \mathfrak{m}[x]$ and $U = a_d + a_{d+1}x + \cdots$ a unit, the operator returning the low-degree remainder of $g -$ (quotient part)f is a contraction for the $\mathfrak{m}$-adic topology, and completeness of R makes the resulting series for q and r converge; uniqueness holds because a Weierstrass polynomial is a non-zero-divisor. See Zariski-Samuel or Eisenbud, Ch. 7.

Iterating in $x_1, \dots, x_n$ pins down the local structure of $k[[x_1, \dots, x_n]]$: it is a regular local ring of dimension n in which, after a generic linear change of coordinates, ideals are generated by Weierstrass

polynomials, the algebraic counterpart of resolving a formal germ into a finite branched cover of a coordinate subspace. This underlies formal and analytic local geometry, intersection multiplicities, and Puiseux expansions used downstream.

26

Ring Extension and Integral Extension

In this section, we generalize the notion of extension from fields to commutative rings. Just like how $k \subseteq F$ can be seen as a field extension, if we let k and R be rings instead, we will et the accompying notion of ring extension:

26.1 Ring and Integral Extensions

Definition 26.1.1: Ring Extension

Let S be a commutative ring and $R \subseteq S$ a subring. Then we say that S is a *ring extension* of R. Equivalently, if there exists an injective ring homomorphism $\varphi : R \to S$, then S is a ring extension of R.

Unlike fields, we must specify the homomorphism to be injective, since ring homomorphisms need not be injective. The notation S/R is also used just as in field, though more scarcely. Just like how any field extension F/k makes F into a k-vector-space and we have special k-homomorphisms letting k-commute between the homomorphism, a ring extension S/R have an analogue: in fact, a k-homomorphism is *precisely* a k-algebra homomorphism!

Recall that any *R-algebra* can be defined as a ring homomorphism $\varphi : R \to S$, *provided* that $\varphi(R) \subseteq Z(S)$. Since we are working with commutative rings, this is *always* the case, and so we can always thing of a ring extension S over R is an R-algebra! This is why we focus on *commutative rings*. There is a similar notion of ring extension for non-commutative which is closer to the notion of group extension (i.e. a short exact sequence extending the object), however ring extensions do

not break down into nice building blocks since kernels of rings are not rings, which means we would have to extend a ring R by an abelian group (i.e. two-sided ideal) I. This very much changes how we would study rings. However, we can always study the structure of any commutative ring S by how behaves as an R-algebra similarly to how we studied fields, which is what we will do in these chapters.

26.1.2 Advanced Intuition Integral extensions shall correspond to *proper maps* of morphisms. Non-integral extensions shall never be proper, thus geometrically exhibiting greatly different behaviour. In particular, taking base change if necessary, the image of closed sets (essentially zero-sets of polynomials) need not be closed.

Perhaps the first notion we might want to genelize is the equivalent of an *algebraic element*, since they capture the relations within a ring extension with respect to the base ring. The following is the exactly this generlization:

Definition 26.1.3: Integral Elements

Let $R \subseteq S$.

1. An element $s \in S$ is called an *integral over* R if s is the root of a monic polynomial over $R[x]$:
$$s^n + r_{n-1}s^{n-1} + \cdots + r_1 s + r_0 = 0 \qquad r_i \in R$$
2. S is called *integral over* R or an *integral extension of* R if every element of S is integral over R. The integral closure of an integral domain is also called the *normalization of* R. Sometimes, the integral extension will be written as S/R
3. The set $\overline{R}^S$ containing all the elements of S that are integral over R is called the *integral closure of* R
4. If $R = \overline{R}^S$, then R is said to be *integrally closed over* S.
5. If R is an integral domain that is integrally closed in it's field of fractions F, $\overline{R}^F$, then R is called *normal domain*.

The fact that the polynomial it satisfies has to be monic can be thought of as not wanting to add relations that produce "units" or unlit-like elements (ex. $3x - 1 = 0$ implies there is a new element that behaves like $1/3$). For a more specific motivation, we can think of the following: If $f(x) \in R[x]$ is a polynomial of minimal degree with root r, and $h(x) \in R[x]$ is another monic polynomials with minimal degree with root r, then we would want that $h(x)|f(x)$, just like for minimal polynomials over fields. In the process of doing so, we would require the coefficient of the leading terms to divide. Since they can be arbitrary, we would require the coefficients of these polynomial to be units, or just 1, in order for the division to follow through. It follows that it is a natural condition that all polynomials be monic for an integral extension.

Another motivation comes from Gauss's lemma: over a UFD R with fraction field K, a primitive polynomial of $R[x]$ is irreducible in $R[x]$ if and only if it is irreducible in $K[x]$. Monic polynomials are primitive, so factorization of monic polynomials over R mirrors factorization over K; this parallel between $R[x]$ and $K[x]$ becomes important in [15].

Integral elements share many of the same properties as algebraic elements:

Proposition 26.1.4: Integral Element Equivalences

Let $R \subseteq S$ be a subring of S. Then the following are equivalent:

1. s is integral over R
2. $R[s]$ is a finitely generated R-module
3. The element s is in T for some subring T where $R \subseteq T \subseteq S$, that is a finitely generated R-module

***Proof*:**

$1 \Rightarrow 2$ Recall that $R[s]$ can be expressed as all R-linear combinations of powers of s. Since s is integral over R:

$$s^n + r_n s^{n-1} + \cdots + r_1 s + r_0 = 0$$

in particular:

$$s^n = -(r_n s^{n-1} + \cdots + r_1 s + r_0)$$

It follows that for all $m \geq n$, s^m can be expressed in terms of $1, s, \ldots, s^{n-1}$ (for the same reasons as we have shown for algebraic elements). Hence:

$$R[s] = R + Rs + \cdots + Rs^{n-1}$$

Notice here how if the polynomial was not monic, we might not have been able to isolae s^n, causing complications.

$2 \Rightarrow 3$ Let $T = R[s]$. Then the reuslt immediately follows

$3 \Rightarrow 1$ The argument uses the adjugate identity $\text{adj}(B)B = \det(B)I$, which holds over any commutative ring (proposition 13.4.11). Since T is finitely generated, let $v_1, v_2, ..., v_n$ be a finite generating set. Since $s \in T$ and T is a ring, $sv_i \in T$ for all $1 \leq i \leq n$. Thus:

$$sv_i = \sum_j a_{ij} v_j$$

This gives the n equations

$$\sum_j (\delta_{ij} s - a_{ij}) v_j = 0 \qquad 1 \leq i \leq n$$

where δ_{ij} is one when $i = j$ and 0 otherwise (i.e. the Kronecker delta). Letting B be the matrix such that the entries are $B_{ij} = \delta_{ij} s - a_{ij}$ and letting v be the $n \times 1$ matrix whose entries are $v_1, ..., v_n$, we get:

$$Bv = 0$$

Multiplying on the left by $\text{adj}(B)$, whose entries lie in the commutative ring T, gives $\det(B)v = \text{adj}(B)Bv = 0$, that is,

$$(\det B) v_i = 0 \qquad 1 \leq i \leq n$$

Now, since 1 is an R-linear combination of $v_1, v_2, ..., v_n$,

$$\det B = (\det B)1 = (\det B)\sum_i a_i v_i = \sum a_i((\det B)v_i) = 0$$

i.e. $\det B = 0$. Now, B is by definition $B = sI - A$ (where $A_{ij} = a_{ij}$). Thus, s is the root of a monic polynomial $\det(xI - A) \in R[x]$, namely the characteristic polynomial of A, and so is the root of a monic polynomial with coefficients in R, giving (1)

Corollary 26.1.5: Transitivity of Integrality

Let $R \subseteq S \subseteq T$ be rings. If T is integral over S and S is integral over R, then T is integral over R.

***Proof*:**
Let $t \in T$, a root of a monic $x^n + a_{n-1}x^{n-1} + \cdots + a_0 \in S[x]$. Each a_i is integral over R, so in the tower $R \subseteq R[a_0] \subseteq \cdots \subseteq R[a_0, \ldots, a_{n-1}] =: R'$ every step is module-finite (proposition 26.1.4), hence R' is a finitely generated R-module. As t is integral over R', $R'[t]$ is module-finite over R', hence over R; by proposition 26.1.4 (applied to the subring $R'[t]$), t is integral over R.

Corollary 26.1.6: Integral Elements Form Rings

Let $R \subseteq S$ be a subring of S, and $s, t \in S$. Then:

1. If s and t are integral over R, so is $s \pm t$ and st
2. $\overline{R}^S$ is a subring of S containing R, and is integrally closed[a]

[a] If we were working over rng's, $\overline{R}^S$ need not be integrally closed

***Proof*:**
Let s, t be integral over R, sy that by proposition 26.1.4 $R[s]$ and $R[t]$ are finitely generated R-modules, say:

$$R[s] = Rs_1 + \cdots + Rs_n$$
$$R[t] = Rt_1 + \cdots + Rt_m$$

Then:

$$R[s,t] = Rs_1t_1 + \cdots + Rs_it_j + \cdots + Rs_nt_m$$

is a ring containing $s \pm t$ and st that is also a finitely generated R-module, so $s \pm t$ and st are integral over R. Thus $\overline{R}^S$ is a subring of S containing R; it is integrally closed in S, since any $s \in S$ integral over $\overline{R}^S$ is integral over R by transitivity (corollary 26.1.5), hence lies in $\overline{R}^S$.

In particular, taking the integral closure is idempotent: $\overline{(\overline{R}^S)}^S = \overline{R}^S$, since integrality is transitive (corollary 26.1.5).

Note that integral closure is dependent on the ring over which we are closing; we do not have the equivalent notion of "integral closure of R" without specifying a ring over which it is integrally closed (Why?)

Corollary 26.1.7: Module-Finite versus Finite-Type-and-Integral

Let S be an R-algebra. Then S is a finitely generated R-module if and only if S is of finite type over R and integral over R.

Notice how if S is not integral, then it is possible that S is of finite type over R but not finitely generated over R, the most cannonical example being $R[x]$ over R (since $R[x]$ is finitely generated as an R-algebra by 1 and x, but $1, x, x^2, ...$ is an infinite set that is a basis for $R[x]$)

***Proof*:**
If S is a finitely generated R-module it is of finite type, and every element is integral (proposition 26.1.4). Conversely, let $S = R[s_1, \dots, s_n]$ be of finite type with each s_i integral over R. In the tower

$$R \subseteq R[s_1] \subseteq R[s_1, s_2] \subseteq \cdots \subseteq R[s_1, \dots, s_n] = S$$

each step $R[s_1, \dots, s_{i-1}][s_i]$ is module-finite, since s_i is integral over the smaller ring (proposition 26.1.4); a module-finite extension of a module-finite extension is module-finite, so S is a finitely generated R-module.

Before giving examples, we will show that we have been studying special types of integral closures when we worked with field exensions in Part IV:

Proposition 26.1.8: Integral Extension over Fields

Let S/R be an integral extension where S is an integral domain. Then R is a field if and only if S is a field

Note that if S was not an integral domain or commutative, this theorem does not work: Take $M_2(k)$ over any field. Then $M_2(k)$ is a 4-dimensional k-algebar, but certianly not a field (it contains zero-divisors, and is not commutative).

***Proof*:**

($\Rightarrow$) Let R be a field and take $0 \neq s \in S$. Since s is integral over R, we have:

$$s^n + a_{n-1}s^{n-1} + \cdots + a_1 s + a_0 = 0 \qquad a_i \in R$$

Without loss of generality, let $a_0 \neq 0$; otherwise, factor an s, and using the fact that S is an integral domain, we see that either $s = 0$ or $s^{n-1} + \cdots + a_1 = 0$, and since $s \neq 0$, then we simply choose $s^{n-1} + \cdots + a_1 = 0$ to be our equation. Thus, moving a_0 and factoring s we get:

$$s(s^{n-1} + \cdots + a_1) = -a_0$$

Since R is a field, $\frac{-1}{a_0} \in R$, so:

$$s \cdot \big((-1/a_0)(s^{n-1} + \cdots + a_1)\big) = 1$$

showing that s has a multiplictative inverse. Since s was arbitrary, we have that S is a field.

($\Leftarrow$) Let S be a field and take $0 \neq r \in R$ (automatically implying that R is an integral domain). Since $r \in R$, $r \in S$, and so $r^{-1} \in S$. Since S is an integral extension of R:

$$r^{-n} + a_{n-1}r^{-(n-1)} + \cdots + a_1 r^{-1} + a_0 = 0$$

Multiply the entire expression by r^{n-1}, and move all the terms except the r^{-1} terms to the right hand side to get:

$$r^{-1} = -(a_{n-1} + \cdots + a_1 r^{n-2} + a_0 r^{n-1})$$

which is a linear combination of elements in R, showing that $r^{-1} \in R$, and so R is a field.

Thus, any algebraic field extension is an integral extension.

Example 26.1.9: Integral Extensions

1. As we have just shown, all algebraic extensions of fields are integral extensions.

2. Let R be a Unique Factorization Domain and let $F = \text{Frac}(R)$. Then $\overline{R}^F = R$. The $\supseteq$ direction is obvious, so consider the $\subseteq$ direciton: suppose that $a/b \in \overline{R}^F$ with $\gcd(a,b) = 1$. Then by definition
$$\left(\frac{a}{b}\right)^n + r_{n-1}\left(\frac{a}{b}\right)^{n-1} + \cdots + r_1\frac{a}{b} + r_0 = 0$$
Then:
$$a^n = b(-r_{n-1}a^{n-1} - \cdots - r_1 ab^{n-2} - r_0 b^{n-1})$$
so $b \mid a^n$, and hence $b \mid a$. Since $\gcd(a,b) = 1$, it must thus be that b is a unit, and hence we have that $a/b \in R$, showing that $\overline{R}^F = R$. Hence, all UFD's are normal domains. This should make intuitive sense, since any element $a/b \in \text{Frac}(R)$ would satisfy the equation $bx - a = 0$, which is not-monic.

   More generally, any polynomial ring over a UFD R, $R[x_1, ..., x_n]$ is itself a UFD, by the one-variable case applied once per variable,[a] hence integrally closed in its field of fractions $R(x_1, ..., x_n)$, showing every polynomial ring over a Unique Factorization Domain is a normal domain.

3. Let S be integral over R and $I \subseteq S$ be an ideal. Then S/I is integral over $R/(R \cap I)$. To see this, notice that a monic polynomial over R where $s \in S$ is a root, when reduced modulo I gives a monic polynomial over $R/(R \cap I)$ where $\overline{s} \in S/I$ is a root.

4. Let k be any field and take $k[x,y]$ (which is integrally closd since it's a UFD). Take the prime ideal $(x^2 - y^3) \subseteq k[x,y]$ (see Dummit and Foote, §9.1, Exercise 14). Consider the integral domain
$$R = k[x,y]/(x^2 - y^3) = k[\overline{x}, \overline{y}]$$
Notice that R is *not* normal: the element $\overline{x}/\overline{y}$ is the solution to the equation
$$\left(\frac{\overline{x}}{\overline{y}}\right)^3 - \overline{x} = 0$$

but evidently $\overline{x}/\overline{y} \notin R$. Thus, R cannot be a Unique Factorization Domain.

If you wish to practice, another example is $\mathbb{Z}[\sqrt{-3}]$. It's integral closure over it's field of fraction's is:

$$\mathbb{Z}\left[\frac{1+\sqrt{-3}}{2}\right]$$

[a] theorem 11.2.3.

Corollary 26.1.10: Normalization Commutes with Localization

Let R be a domain with fraction field K, $D \subseteq R$ a multiplicative set, and $\overline{R}$ the integral closure of R in K. Then, computing integral closures inside K, $\overline{D^{-1}R} = D^{-1}\overline{R}$.

***Proof*:**
If $x \in \overline{R}$ satisfies $x^n + a_{n-1}x^{n-1} + \cdots + a_0 = 0$ with $a_i \in R$, the same relation holds over $D^{-1}R$, so $D^{-1}\overline{R} \subseteq \overline{D^{-1}R}$. Conversely, if $y \in K$ is integral over $D^{-1}R$, then clearing the denominators in its integral relation shows sy is integral over R for some $s \in D$, so $sy \in \overline{R}$ and $y = (sy)/s \in D^{-1}\overline{R}$. In particular R is normal iff $R_{\mathfrak{m}}$ is normal for every maximal ideal $\mathfrak{m}$.

Locality shows where to compute an integral closure but not whether the answer is manageable. The integral closure of a Noetherian domain in its fraction field can fail to be a finite module, and can even fail to be Noetherian, so finiteness is a genuine theorem and not a formality. For the rings that geometry actually produces, finitely generated algebras over a field, it holds; this is what makes the normalization of a variety a variety again rather than an unwieldy limit.

Theorem 26.1.11: Finiteness of Integral Closure

Let k be a field, let A be a domain that is finitely generated as a k-algebra, and let L be a finite field extension of $\mathrm{Frac}(A)$. Then the integral closure of A in L is a finite A-module. In particular it is a Noetherian ring and is finitely generated as a k-algebra, and taking $L = \mathrm{Frac}(A)$, the normalization $\overline{A}$ of A is a finite A-module.

***Proof*:**
The argument is given in full for k perfect, and box 26.1.12 cites the imperfect case.

Step 1: reduce to a polynomial ring. By Noether normalization (theorem 29.1.1) there is a polynomial subalgebra $B = k[x_1, \ldots, x_d] \subseteq A$ with A finite, hence integral, over B. An element of L integral over A is then integral over B by transitivity of integral dependence, and conversely $B \subseteq A$, so the integral closures of A and of B in L coincide; it suffices to prove the theorem for B. Note that $\mathrm{Frac}(B) \subseteq \mathrm{Frac}(A) \subseteq L$ with both extensions finite, so $L/\mathrm{Frac}(B)$ is finite. The ring B is a unique factorization domain and hence normal (example 26.1.9).

Step 2: split off the inseparable part. Put $F = \mathrm{Frac}(B)$, let C be the integral closure of B in L, and let L_s be the set of elements of L separable over F. It is a subfield of L containing F: for $\alpha, \beta \in L_s$ the extension $F(\alpha, \beta)/F$ is finite and generated by separable elements, hence separable,[a] so $\alpha \pm \beta$, $\alpha\beta$ and, for $\beta \neq 0$, α/β lie in L_s. If an element of L is not separable over

F, its minimal polynomial f is irreducible and inseparable, so $f' = 0$.[b] In characteristic 0 this is impossible for a nonconstant f, so $L_s = L$, and we put $q = 1$.

Suppose $\mathrm{char} k = p > 0$. Every $\ell \in L$ has a power ℓ^{p^e} in L_s. Indeed, let f be the minimal polynomial of ℓ over F. If f is inseparable, then $f' = 0$ forces every exponent occurring in f to be a multiple of p, so $f(X) = f_1(X^p)$ for some $f_1 \in F[X]$ of smaller degree, irreducible because a factorization of f_1 would give one of f. Repeating this with f_1 in place of f, after finitely many steps $f(X) = g(X^{p^e})$ with g irreducible and separable, and $g(\ell^{p^e}) = 0$ makes ℓ^{p^e} separable over F. Choose an L_s-basis $\ell_1, \dots, \ell_r$ of L, finite because L/F is finite, and let q be the largest of the powers p^e obtained for $\ell_1, \dots, \ell_r$. The field L_s is closed under p-th powers and q is a power of each of these p^e, so $\ell_i^q \in L_s$ for every i. The map $\ell \mapsto \ell^q$ is a ring homomorphism in characteristic p, since p divides $\binom{p}{j}$ for $0 < j < p$. So for $\ell = \sum_i a_i \ell_i$ with $a_i \in L_s$ we get $\ell^q = \sum_i a_i^q \ell_i^q \in L_s$. In either characteristic, therefore,

$$\ell^q \in L_s \qquad \text{for every } \ell \in L$$

Step 3: the trace form pins the separable part inside a free module. Let $C_s = C \cap L_s$, the integral closure of B in L_s. The extension L_s/F is finite and separable. Choose an F-basis $e_1, \dots, e_n$ of L_s consisting of elements integral over B. This is possible because any F-basis can be scaled into C_s, an element of L_s being algebraic over F and hence integral after multiplication by a suitable element of B clearing denominators in its minimal polynomial. Since L_s/F is separable, the trace form is nondegenerate and there is a dual basis $e_1^*, \dots, e_n^*$ of L_s over F with $\mathrm{tr}_{L_s/F}(e_i e_j^*) = \delta_{ij}$ (*Core Algebra*[c]).

Let $c \in C_s$ and write $c = \sum_j \lambda_j e_j^*$ with $\lambda_j \in F$. Then $\lambda_j = \mathrm{tr}_{L_s/F}(c\, e_j)$. Now $c\, e_j$ is a product of elements integral over B, hence integral over B, and the trace of an element integral over B lies in B: the trace is, up to sign, a coefficient of the characteristic polynomial of multiplication by that element, which is a power of its minimal polynomial, and the minimal polynomial of an integral element has coefficients in B because B is integrally closed in F. So $\lambda_j \in B$ for every j, and

$$C_s \;\subseteq\; Be_1^* + \cdots + Be_n^*$$

The right-hand side is a free B-module of rank n, and B is Noetherian by Hilbert's basis theorem, so its submodule C_s is a finite B-module.

Step 4: the inseparable part, where perfectness is used. If $q = 1$, then $L_s = L$ and $C = C_s$ is finite over B by Step 3. Let $q > 1$, so that $\mathrm{char} k = p > 0$. For $c \in C$ the power c^q lies in L_s by Step 2 and is integral over B, being a product of elements integral over B, so $c^q \in C_s$. The map $\varphi\colon C \to C_s$, $c \mapsto c^q$, is a ring homomorphism, injective because L is a field, and $\varphi(bc) = b^q \varphi(c)$ for $b \in B$. Its image contains $B^q = \varphi(B)$, whose elements are the sums $\sum_\alpha a_\alpha^q x^{q\alpha}$ for $\sum_\alpha a_\alpha x^\alpha \in B$. As k is perfect, its Frobenius homomorphism is surjective,[d] so every element of k is a q-th power and $B^q = k[x_1^q, \dots, x_d^q]$. This ring is Noetherian by Hilbert's basis theorem, and B is generated as a B^q-module by the monomials $x_1^{a_1} \cdots x_d^{a_d}$ with $0 \le a_i < q$. Hence C_s, finite over B, is finite over B^q, and so is its B^q-submodule $\varphi(C)$, say $\varphi(C) = \sum_j B^q \varphi(c_j)$ with $c_j \in C$. For $c \in C$ write $\varphi(c) = \sum_j b_j^q \varphi(c_j) = \varphi\big(\sum_j b_j c_j\big)$ with $b_j \in B$. Injectivity of φ gives $c = \sum_j b_j c_j$, so C is a finite B-module.

Step 5: conclude. By Step 1, C is the integral closure of A in L, and it is finite over B, hence over $A \supseteq B$. Since B is a finitely generated k-algebra, C is a finitely generated k-algebra and a Noetherian ring, as we sought to show.

[a]proposition 19.6.17.
[b]proposition 19.6.7.
[c]proposition 19.6.31.
[d]proposition 19.6.11.

26.1.12 Note: The Imperfect Case Perfectness is used only in Step 4, to write B^q as the polynomial ring $k[x_1^q, \dots, x_d^q]$ over which B is finite. For a general k of characteristic p one has $B^q = k^q[x_1^q, \dots, x_d^q]$, and B is finite over it exactly when k is finite over its subfield k^q. The same proof therefore covers fields such as $\mathbb{F}_p(t)$, and it stops for $k = \mathbb{F}_p(t_1, t_2, \dots)$, which is infinite over k^q for every $q > 1$. The theorem is nonetheless true over any field. A domain is *Japanese* if its integral closure in every finite extension of its fraction field is a finite module over it, and a Noetherian ring R is a *Nagata ring* if $R/\mathfrak{p}$ is Japanese for every prime $\mathfrak{p}$ of R (Matsumura [74, (31.A)], where Japanese is called N-2). Matsumura [74, (31.H) Theorem 72] proves that a finitely generated algebra over a Nagata ring, such as a field, is again a Nagata ring, and [98, Tag 0335] states the case of a field directly. For the prime (0) of A this is exactly the finiteness asserted here. *Algebraic Geometry* uses the imperfect case, in the normalization of a variety and in the finite generation of global sections of a coherent sheaf on a projective scheme, both over an arbitrary field.[a] Over an imperfect field those two proofs rest on the references above.

[a][13, Normalization of a Variety, Finite Generation of Coherent Sheaves over Projective Schemes].

26.2 Extension and Contraction of Ideals

Probably the biggest difference between fields and rings is that ideals are nontrivial. Thus, it is meaningful to ask what happens to ideals in (general) ring extensions. Recall that if $f : R \to S$ is a ring homomorphism, and $J \subseteq S$ is an ideal, $f^{-1}(J)$ is an ideal. However, if $I \subseteq R$ is an ideal, $f(I)$ need not be an ideal (take $\mathbb{Z} \hookrightarrow \mathbb{Q}$ with any non-trivial ideal of $\mathbb{Z}$). The next best thing would be to define the smallest ideal of S containing $f(I)$:

Definition 26.2.1: Extension and Contraction

Let $\varphi : R \to S$ be a homomorphism between commutative rings and let $I \subseteq R$, $J \subseteq S$.

1. The *extension* of I to S is the ideal $\varphi(I)S$, commonly denoted I^e
2. The *contraction* of J in R is the ideal $\varphi^{-1}(J)$, commonly denoted J^c

In the case where φ is the natural inclusion $\iota : R \to S$, then the extension of I is IS, and the contraction of J is $J \cap R$. If $I \subseteq R$, there are multiple extension of R, say S/R and T/R, then the extension of I is sometiems denoted I_S or I_T to emphasize to what ring I is being extended too S or T respectively.

Proposition 26.2.2: Properties of Extensions and Contractions

1. $I \subseteq IS \cap R$, or more generally that I is contained in the contraction of its extension to S ($I \subseteq I^{ec}$)
2. $(J \cap R)S \subseteq J$, or more genrally that J is contained in the extension of its contraction in R ($J \supseteq J^{ce}$)
3. $I^e = I^{ece}$
4. $J^c = J^{cec}$
5. If J is prime, J^c is prime. If I is prime, I^e need not be prime (consider $\mathbb{Z} \hookrightarrow \mathbb{Q}$). If $\varphi : R \to S$ is surjective and I is a prime ideal containing $\ker \varphi$, then I^e is prime.
6. If J is maximal, J^c need not be maximal, and similarly if I is maximal then I^e need not be maximal.

***Proof*:**
(1) holds since $I \subseteq \varphi^{-1}(\varphi(I)S) = I^{ec}$, and (2) since $I^{ce} = \varphi(\varphi^{-1}(J))S \subseteq J$. Applying (1) to I^e gives $I^e \subseteq I^{ece}$, and applying $(-)^e$ to (2) gives $I^{ece} \subseteq I^e$, so (3) holds; (4) is dual. For (5): $J^c = \varphi^{-1}(J)$ is prime as a preimage of a prime; over $\mathbb{Z} \hookrightarrow \mathbb{Q}$ the nonzero prime (p) has $(p)^e = \mathbb{Q}$, not a proper ideal; and if φ is surjective with prime $I \supseteq \ker \varphi$, then $I^e = \varphi(I)$ and $S/I^e \cong R/I$ is a domain. (6) is $\mathbb{Z} \hookrightarrow \mathbb{Q}$ again, where (0) is maximal in $\mathbb{Q}$ but not in $\mathbb{Z}$.

Lemma 26.2.3: Extension And Contraction With Common Operations

Let $\mathfrak{a}_1, \mathfrak{a}_2 \subseteq A$ be ideals of A and $\mathfrak{b}_1, \mathfrak{b}_2 \subseteq B$ be ideals of B. Then:

$$(\mathfrak{a}_1 + \mathfrak{a}_2)^e = \mathfrak{a}_1^e + \mathfrak{a}_2^e \qquad (\mathfrak{b}_1 + \mathfrak{b}_2)^c \supseteq \mathfrak{b}_1^c + \mathfrak{b}_2^c$$
$$(\mathfrak{a}_1 \cap \mathfrak{a}_2)^e \subseteq \mathfrak{a}_1^e \cap \mathfrak{a}_2^e \qquad (\mathfrak{b}_1 \cap \mathfrak{b}_2)^c = \mathfrak{b}_1^c \cap \mathfrak{b}_2^c$$
$$(\mathfrak{a}_1\mathfrak{a}_2)^e = \mathfrak{a}_1^e\mathfrak{a}_2^e \qquad (\mathfrak{b}_1\mathfrak{b}_2)^c \supseteq \mathfrak{b}_1^c\mathfrak{b}_2^c$$
$$(\mathfrak{a}_1 : \mathfrak{a}_2)^e \subseteq (\mathfrak{a}_1^e : \mathfrak{a}_2^e) \qquad (\mathfrak{b}_1 : \mathfrak{b}_2)^c \subseteq (\mathfrak{b}_1^c : \mathfrak{b}_2^c)$$
$$\sqrt{\mathfrak{a}}^e \subseteq \sqrt{\mathfrak{a}^e} \qquad \sqrt{\mathfrak{b}}^c = \sqrt{\mathfrak{b}^c}$$

***Proof*:**
Each identity is routine from the definitions of extension and contraction (Atiyah-Macdonald, Chapter 1); the inclusions that are not equalities are strict already for $\mathbb{Z} \hookrightarrow \mathbb{Q}$.

If $\varphi : R \to S$ is a ring homomorphism, we may decompose φ into the following:

$$R \xrightarrow{p} \varphi(R) \xhookrightarrow{j} S$$

where p maps R surjectively onto $\varphi(R)$, and j injects into S. Relating the ideals of R to the ideals of $\varphi(R)$ is very easy:

Proposition 26.2.4: Correspondence Between Ideals And Image Of Ideals

Let $\varphi : R \to S$ be a ring homomorphism. Then there exists a bijective correspondence:

$$\{I \subseteq \varphi(R)\} \underset{\varphi(-)}{\overset{(-)^c}{\rightleftarrows}} \{\ker(\varphi) \subseteq J \subseteq R\}$$

Furthermore, prime ideals of $\varphi(R)$ correspond to prime ideals of R containing $\ker(\varphi)$.

***Proof*:**
Since $\varphi(R) \cong R/\ker\varphi$, this is the correspondence theorem for the quotient $R \twoheadrightarrow R/\ker\varphi$: ideals of $R/\ker\varphi$ correspond to ideals of R containing $\ker\varphi$ via image and preimage, and primes correspond to primes.

On the other hand, the correspondence between $\varphi(R)$ and S is much harder, and is covered in section 26.3 when S/R is an integral extension. As shown in proposition 26.2.2, every prime ideal "lies over" another prime ideal. This motivates the following vocuabilary:

Definition 26.2.5: Lying Over

Let $I \subseteq S$ be an ideal and S/R an integral extension. If $J = I \cap R$, I is said to be *lying over* J.

Example 26.2.6: Extending ideals
Take $\varphi : \mathbb{Z} \to \mathbb{Z}[i]$ to be the inclusion. Then a prime ideal $(p) \subseteq \mathbb{Z}$ may or may not remain prime when extended to $\mathbb{Z}[i]$. Using Fermat's theorem of sums of squares (theorem 10.3.3), it can be deduced that:

1. $(2)^e = (1+i)^2$
2. If $p \equiv 1 \bmod 4$, then p^e is the product of two distinct prime ideals (ex. $(5)^e = (2+i)(2-i)$)
3. if $p \equiv 3 \bmod 4$, then p^e is prime in $\mathbb{Z}[i]$

In general, it is rather hard to determine when $\varphi(p)$ is prime when p is prime. If $\varphi : R \to S$ is an integarl extension, then the situation becomes much better, however it will require the notion of *localization* which shall be covered in the next section. One special case is note mentioning:

Proposition 26.2.7: Maximal Ideals Lying Over

Let S/R be an integral extension and $\mathfrak{m} \subseteq S$ a prime ideal. Then $\mathfrak{m} \cap R$ is maximal if and only if $\mathfrak{m}$ is maximal.

***Proof*:**
Consider the integral domain $S/\mathfrak{m}$. Then $S/\mathfrak{m}$ is an integral extension of $R/(\mathfrak{m} \cap R)$. Then by proposition 26.1.8, $S/\mathfrak{m}$ is a field if and only if $R/(\mathfrak{m} \cap R)$ is a field. But then $\mathfrak{m}$ is maximal if and only if $\mathfrak{m} \cap R$ is maximal.

26.3 Integral Extensions and Prime Ideals

We return to the question of the extension of ideals, in particular prime ideals, given S/R. The going-down half rests on the following, where integrality over an *ideal* I means being a root of a monic $x^n + a_{n-1}x^{n-1} + \cdots + a_0$ with all $a_i \in I$.

Lemma 26.3.1: Integral Closure of an Extended Ideal

Let C be an integral extension of a ring R and let $I \subseteq R$ be an ideal. An element of C is integral over I if and only if it lies in $\sqrt{IC}$.

***Proof*:**
Let $x \in C$ satisfy $x^n + a_{n-1}x^{n-1} + \cdots + a_0 = 0$ with all $a_i \in I$. Then $x^n = -(a_{n-1}x^{n-1} + \cdots + a_0)$ lies in IC, so $x \in \sqrt{IC}$.

Conversely, let $x^m = a_1c_1 + \cdots + a_sc_s$ with $a_i \in I$ and $c_i \in C$. The ring $M = R[c_1, \ldots, c_s]$ is of finite type over R and, lying in C, integral over R, so it is a finitely generated R-module by corollary 26.1.7. Let $v_1, \ldots, v_r$ generate it. Since M is a ring containing every c_i, each $x^m v_j = \sum_i a_i(c_i v_j)$ lies in IM, so $x^m v_j = \sum_l b_{jl} v_l$ with $b_{jl} \in I$. Let $B = (b_{jl})$ and let E be the $r \times r$ identity matrix. The adjugate argument in the proof of proposition 26.1.4, run over the commutative ring C, gives $\det(x^m E - B)\, v_l = 0$ for every l, and 1 is an R-linear combination of the v_l, so $\det(x^m E - B) = 0$. Expanding the determinant, $\det(zE - B) = z^r + \beta_{r-1}z^{r-1} + \cdots + \beta_0$, where β_{r-i} is, up to sign, a sum of products of $i \geq 1$ entries of B and so lies in I. Hence x is a root of $z^{mr} + \beta_{r-1}z^{m(r-1)} + \cdots + \beta_0$, a monic polynomial whose other coefficients lie in I, and x is integral over I.

Lemma 26.3.2: Integral over an Ideal

Let R be a normal domain with fraction field K, let $S \supseteq R$ be a domain, and let $I \subseteq R$ be an ideal. If $x \in S$ is integral over I, then x is algebraic over K and the non-leading coefficients of its minimal polynomial over K lie in $\sqrt{I}$.

***Proof*:**
The integral relation shows x is algebraic over K; let $m(t) = t^r + c_{r-1}t^{r-1} + \cdots + c_0$ be its minimal polynomial over K. Let L be a splitting field of m over K and C the integral closure of R in L, an integral extension of R by corollary 26.1.6. The roots $x = x_1, \ldots, x_r$ of m in L are roots of the monic relation of x over I, which m divides in $K[t]$. So each x_j is integral over I, hence lies in C and, by lemma 26.3.1, in the ideal $\sqrt{IC}$ of C. Each non-leading coefficient c_i is, up to sign, an elementary symmetric function of positive degree in the x_j, so it lies in $\sqrt{IC}$ as well, and lemma 26.3.1 makes it integral over I. Each $c_i \in K$ is integral over R, so $c_i \in R$ since R is normal. As $c_i \in R$ is integral over I, it satisfies $c_i^N + b_{N-1}c_i^{N-1} + \cdots + b_0 = 0$ with $b_j \in I$, giving $c_i^N \in I$, i.e. $c_i \in \sqrt{I}$.

Theorem 26.3.3: Integral Extension Prime Correspondence (Cohen-Seidenberg Theorem)

Let S be an integral extension of the integral domain R

1. (**Lying-over Property**) Let $\mathfrak{p} \subseteq R$ be a prime ideal. Then there is a prime ideal $P \subseteq S$ such that $\mathfrak{p} = P \cap R$. Furthermore, $\mathfrak{p}$ is maximal if and only if P is maximal.
2. (**Going-up Property**) Let $p_1 \subseteq p_2 \subseteq \cdots \subseteq p_n$ be a chain of prime ideals of R, and suppose there exists a chain $q_1 \subseteq q_2 \subseteq \cdots \subseteq q_m$, $(m < n)$ such that $p_i = q_i \cap R$. Then there exists prime ideals $q_{m+1}, ..., q_n$ that complete the chain: $q_m \subseteq q_{m+1} \subseteq \cdots \subseteq q_n$, $p_i = q_i \cap R$ for all i.
3. (**Going-down Property**) Suppose in addition that S is a domain. If R is a normal domain, $p_1 \supseteq p_2 \supseteq \cdots \supseteq p_n$ be a chain of prime ideals of R, and suppose there exists a chain $q_1 \supseteq q_2 \supseteq \cdots \supseteq q_m$, $(m < n)$ such that $p_i = q_i \cap R$. Then there exists prime ideals $q_{m+1}, ..., q_n$ that complete the chain: $q_m \supseteq q_{m+1} \supseteq \cdots \supseteq q_n$, $p_i = q_i \cap R$ for all i.
4. (**Incomparability property**) Let q_1 and q_2 lie over p. Then either $q_1 = q_2$, or they do not contain each other: $q_1 \nsubseteq q_2$ and $q_2 \nsubseteq q_1$

***Proof*:**

1. We will take advantage of the corresponence theorem for rings and their localization. Let $D = R - p$. Then as we saw, D is multiplicatively closed, and so $R[D^{-1}]$ is well-defined. Since D is also a multiplicatvely closed set of S, $S[D^{-1}]$ is also well-defined. Furthermore, $S[D^{-1}]/R[D^{-1}]$ is an integral extensions of $R[D^{-1}]$: for any $s \in S[D^{-1}]$, if $s \in S$, clearly S is still integral. If $t = \frac{s}{d}$ for some $s \in S$ and $d \in D$, then letting

$$s^n + a_{n-1}s^{n-1} + \cdots + a_1 s + a_0 = 0$$

This equation is still zero if we multiply by d^{-n}:

$$\frac{s^n}{d^n} + \frac{a_{n-1}s^{n-1}}{d^n} + \cdots + \frac{a_1 s}{d^n} + \frac{a_0}{d^n} = 0$$

and shuffling the coefficients we get:

$$\frac{s^n}{d^n} + \frac{da_{n-1}s^{n-1}}{d^{n-1}} + \cdots + \frac{d^{n-1}a_1 s}{d} + \frac{a_0}{d^n} = 0$$

and replacing each $d^{n-i}a_i = b_i$, and $s/d = t$,

$$t^n + b_{n-1}t^{n-1} + \cdots + b_1 t + b_0 = 0$$

showing that t is integral over $R[D^{-1}]$, and so $S[D^{-1}]$ is an integral extension of $R[D^{-1}]$. Let $m \subseteq S[D^{-1}]$ be a maximal ideal. Then by the corresponence of ideals from a ring and it's localization, we have that $m \cap R_p$ is a maximal ideal in R_p, and $m \cap R_p$ is the extension of P to the local ring R_p, so it contracts to p. It might be easier to see if we

have a visual:

$$\begin{array}{ccc} S & \xrightarrow{\pi} & S[D^{-1}] \\ {\scriptstyle\iota}\uparrow & & \uparrow{\scriptstyle\iota} \\ R & \xrightarrow{\pi} & R[D^{-1}] = R_p \end{array}$$

The maximal ideal m is maximal in $S[D^{-1}]$, it's pre-image is a maximal ideal of $R[D^{-1}]$, and the pre-image of that map is p, showing that $p = m \cap R$, as we sought to show.

2. This can be reducd to showing that if $p_1 \subseteq p_2$ and q_1 lies above p_1 such that $p_1 = q_1 \cap R$, then there exists a q_2 that lies above p_2 ($q_2 = p_2 \cap R$) and $q_1 \subseteq q_2$. First, let $\overline{S} = S/q_1$ and $\overline{R} = R/p_1$. Then $\overline{S}/\overline{R}$ is an integral extension by similar reasoning to what we have shown in part 1. By the ideal-correspondence for the quotient $R \to R/p_1$ (proposition 26.2.4), p_2/p_1 is a prime ideal of $\overline{R}$. Then by part (1), we have that there exists an ideal $q_2/q_1 \subseteq \overline{S}$ that lies abouve p_2/p_1, in particular:

$$q_2/q_1 \cap \overline{R} = p_2/p_1$$

At this point we are essentially done: taking the pre-image of q_2/q_1, we get q_2, and by the correspondence theorem we get

$$q_2 \cap R = p_2$$

3. It suffices to find, given $p_1 \supseteq p_2$ in R and q_1 over p_1, a prime $q_2 \subseteq q_1$ over p_2. Localize S at the multiplicative set $S \setminus q_1$. The primes of S_{q_1} correspond to the primes of S inside q_1 (proposition 23.4.5(3)), so it is enough to find a prime of S_{q_1} contracting to p_2 in R. Suppose $p_2 S_{q_1} \cap R = p_2$. Then the multiplicative set $T = R \setminus p_2$ misses $p_2 S_{q_1}$, so the extension of $p_2 S_{q_1}$ to $T^{-1}S_{q_1}$ is proper (proposition 23.4.5(2)) and lies in a maximal ideal $\mathfrak{n}$. The contraction of $\mathfrak{n}$ to S_{q_1} is a prime containing $p_2 S_{q_1}$ and missing T, whose elements are units in $T^{-1}S_{q_1}$. Its contraction to R therefore contains p_2 and misses $R \setminus p_2$, so it is p_2. It remains to show $p_2 S_{q_1} \cap R = p_2$, and the inclusion $\supseteq$ is clear. For $\subseteq$, take $x \in p_2 S_{q_1} \cap R$ and write $x = y/s$ with $y \in p_2 S$, $s \in S \setminus q_1$. Now $y \in p_2 S$ is integral over p_2 by lemma 26.3.1, applied to the integral extension $R \subseteq S$, so by lemma 26.3.2 its minimal polynomial over $K = \mathrm{Frac}(R)$ has non-leading coefficients in $\sqrt{p_2} = p_2$: say $y^r + u_{r-1}y^{r-1} + \cdots + u_0 = 0$ with $u_i \in p_2$. As $0 \in p_2$, we may take $x \neq 0$. Then $s = y/x$ has minimal polynomial $s^r + v_{r-1}s^{r-1} + \cdots + v_0$ with $v_i = u_i/x^{r-i}$, obtained by dividing the relation for y by x^r. As $s \in S$ is integral over R, lemma 26.3.2 with $I = R$ gives $v_i \in R$, and $x^{r-i}v_i = u_i \in p_2$. Were $x \notin p_2$, each $v_i \in p_2$, so $s^r = -(v_{r-1}s^{r-1} + \cdots + v_0) \in p_2 S \subseteq q_1$, forcing $s \in q_1$, a contradiction. Hence $x \in p_2$, giving $p_2 S_{q_1} \cap R = p_2$.

4. For the sake of contradiction, let $q_1 \subseteq q_2$, and let both lie over p: $q_1 \cap R = q_2 \cap R = p$. Consider $\overline{S} = S/q_1$ and $\overline{R} = R/p$. Then as we have shown earlier, $\overline{S}/\overline{R}$ is an integral extension, and $q_2/q_1 \subseteq \overline{S}$ is a prime ideal. Consider:

$$(q_2/q_1) \cap \overline{R} = (q_2 \cap R)/(R \cap q_1) = (R \cap q_1)/(R \cap q_1) = \{\overline{0}\}$$

Now $\overline{S}$ is a domain integral over the domain $\overline{R}$, and the prime q_2/q_1 meets $\overline{R}$ only in $\{0\}$. If $q_2/q_1 \neq 0$, pick $0 \neq \bar{x} \in q_2/q_1$ satisfying an integral relation $\bar{x}^n + \overline{a}_{n-1}\bar{x}^{n-1} + \cdots + \overline{a}_0 = 0$ of least degree; then $\overline{a}_0 = -\bar{x}(\bar{x}^{n-1} + \cdots + \overline{a}_1) \in (q_2/q_1) \cap \overline{R} = \{0\}$, so $\overline{a}_0 = 0$, and cancelling $\bar{x}$ (valid in the domain $\overline{S}$) contradicts minimality. Hence $q_2/q_1 = \{0\}$, i.e. $q_2 = q_1$.

Exercise 26.3.1

1. Let $I \subseteq R$ be an ideal and R a ring. Then if we consider integral extension of *rngs*, show that I^{n+1}/I^n is an integral extension.
2. Let $I \subseteq R$, $f : R \to S$ an integral extension and $I^e \subseteq S$ the extension of S. Then:

$$S/I^e \cong S \otimes_R R/I$$

27

Valuation Ring and Local Rings

An absolute value defines a notion of size on a field, a theory developed downstream in [33]. On a finite field the only absolute value is the trivial one ($|x| = 1$ for $x \neq 0$), and by Ostrowski's theorem the only absolute values on $\mathbb{Q}$ up to equivalence are the p-adic $|-|_p$ and the usual $|-|_\infty$. The p-adic value is defined using a constant c^{-m}; the choice of constant does not affect the topology, so what really matters is the exponent m. This section defines a function capturing that exponent, a useful link between geometric and algebraic intuition on certain fields.

27.1 Valuations

Definition 27.1.1: $\mathbb{R}$-Valuation

Let K be a field. Append ∞ to $\mathbb{R}$ and preserve the total ordering by adding the properties that $g \leq \infty$ for all $g \in \mathbb{R}$ and $g + \infty = \infty + g = \infty + \infty = \infty$. Then a function $\nu : K \to \mathbb{R} \cup \{\infty\}$ is called a $\mathbb{R}$-*valuation* if

1. $\nu(K^\times) \subseteq \mathbb{R}$ and $\nu|_{K^\times} : K^\times \to \mathbb{R}$ is a group-homomorphism, that is $\nu(x \cdot y) = \nu(x) + \nu(y)$.
2. $\nu(x + y) \geq \min\{\nu(x), \nu(y)\}$
3. $\nu(x) = \infty$ if and only if $x = 0$

It may be more clear that $\mathbb{R}$-valuations come as a generalization of non-Archimedean absolute values from the original definition given by Emil Artin (and hence why these are called valuations). To make sense of this definition, we shall introduce the slightly more general notion of a totally ordered abelian group.

Definition 27.1.2: Totally Ordered [Abelian] Group

Let G be an abelian group. Then G is said to be a *totally ordered group*, or simply an *ordered group* if $\leq$ is a total ordering on G that is translation invariant, that is for all $x, y, z \in G$ where $x \leq y$:

$$zx \leq zy$$

An abelian group admits a translation-invariant total order if and only if it is torsion-free. General ordered groups genuinely extend the real-valued case, but for our purposes valuations into $\mathbb{Z}$ or $\mathbb{R}$ suffice; the general notion mainly serves to connect $\mathbb{R}$-valuations to non-Archimedean absolute values ([33]):

Example 27.1.3: Value Groups

The field of *Puiseux series* $\bigcup_{n\geq 1} k((x^{1/n}))$ carries a valuation with value group $\mathbb{Q}$, given by $\nu(x^a) = a$. More generally, Hahn series over a totally ordered group Γ realize Γ as a value group.

Now, in definition 27.1.1, the $(\mathbb{R}, +)$ can be replaced with $(G, *)$. The following shows how this links to absolute values:

Definition 27.1.4: G-Valuation Equivalent Definition

Let K be a field. Append 0 to G and preserve the total ordering by adding the properties that $0 \leq g$ for all $g \in G$ and $0 * g = g * 0 = 0 * 0 = 0$. Then a function $\nu : K \to G \cup \{0\}$ is called a *G-valuation* if

1. $\nu(K^\times) \subseteq G$ and $\nu|_{K^\times} : K^\times \to G$ is a group-homomorphism, that is $\nu(x \cdot y) = \nu(x) * \nu(y)$.
2. $\nu(x + y) \leq \max\{\nu(x), \nu(y)\}$
3. $\nu(x) = 0$ if and only if $x = 0$

The image of $\nu(K^\times)$ is called the *value group*.

If $G = \mathbb{Z}$, or equivalently in the $\mathbb{R}$-valuation definition, when $v(K^*) \subseteq \mathbb{Z}$, a special name is given:

Definition 27.1.5: Discrete Valuation

Let K be a field. Then a function $\nu : K \to \mathbb{Z} \cup \{\infty\}$ is called a *discrete valuation* if

1. $\nu(x \cdot y) = \nu(x) + \nu(y)$
2. $\nu(x + y) \geq \min\{\nu(x), \nu(y)\}$
3. $\nu(x) = \infty$ if and only if $x = 0$

Example 27.1.6: Valuations

1. Given any non-Archimedean absolute value v_p with values in $(\mathbb{R}^+, \cdot)$, we get a $\mathbb{R}^+$ valuation. Hence, each v_p is a valuation on $\mathbb{Q}$ in the equivalent definition, and v_∞, v_0 are valuations on $k(x)$ for any field k.

Given a field k, it may be asked what valuations may be put on it. This is in correspondence with certain sub-rings of k:

Definition 27.1.7: Valuation Ring

Let ν be a valuation on K. Then

$$\mathcal{O}_K = \{x \in K \mid \nu(x) \geq 0\}$$

forms a ring, called the *Valuation Ring*. If ν is a discrete valuation, the ring is called a *discrete valuation ring*.

The reader should verify this is indeed a ring.

Proposition 27.1.8: Valuation Ring Properties

Let k be a field with valuation ν and let $\mathcal{O}_k$ be the valuation ring associated to it. Then:

1. Given $x \in k \setminus \{0\}$, either $x \in \mathcal{O}_k$ or $x^{-1} \in \mathcal{O}_k$ (where both are possible at once). As a consequence, k is a field of fractions of $\mathcal{O}_k$. [a]
2. The group of units is $\mathcal{O}_K^* = \{x \in k \mid \nu(x) = 0\}$ (equiv. $\nu(x) = 1$)
3. $\mathcal{O}_k$ has exactly one maximal ideal $\mathfrak{m}_v = \{x \in k \mid v(x) > 0\} = \mathcal{O}_k \setminus \mathcal{O}_k^*$ (equiv $v(x) < 1$)
4. The ideal of $\mathcal{O}_k$ form a total ordering under $\subseteq$
5. The ring $\mathcal{O}_k$ is integrally closed (i.e. a normal domain)

[a] Note that the either-or implies a general Γ-valuation!

***Proof*:**
(1) For $x \neq 0$, either $\nu(x) \geq 0$ or $\nu(x^{-1}) = -\nu(x) \geq 0$, so $x \in \mathcal{O}_k$ or $x^{-1} \in \mathcal{O}_k$; hence $k = \mathrm{Frac}(\mathcal{O}_k)$. (2) x is a unit iff $x, x^{-1} \in \mathcal{O}_k$ iff $\nu(x) = 0$. (3) By (2) the non-units form $\mathfrak{m}_\nu = \{x \mid \nu(x) > 0\}$, which is an ideal ($\nu(x+y) \geq \min(\nu(x), \nu(y)) > 0$ and $\nu(rx) \geq \nu(x) > 0$); being exactly the non-units, it is the unique maximal ideal.

For 4, first show it on principal ideals, namely if $(a), (b) \subseteq \mathcal{O}_K$, then $(a) \subseteq (b)$ or $(b) \subseteq (a)$. Do this by noticing that either $ab^{-1} \in \mathcal{O}_K$ or $a^{-1}b \in \mathcal{O}_K$. For general ideals, if $\mathfrak{a}$ and $\mathfrak{b}$ are ideals that are not ordered, then there exists $a \in \mathfrak{a} \setminus \mathfrak{b}$ and $b \in \mathfrak{b} \setminus \mathfrak{a}$. Consider $(a), (b)$ which must be ordered namely $(a) \subseteq (b)$ or $(b) \subseteq (a)$. Say $(a) \subseteq (b)$. Then $(a) \cap (b) = (a)$. But then $a \in (b)$ meaning $a = bx$ for some $x \in \mathcal{O}_K$. But as $bx \in \mathfrak{b}$, this would imply $a \notin \mathfrak{a} \setminus \mathfrak{b}$, a contradiction.

We shall show that $\mathcal{O}_K$ is integrally closed. Say that $x \in K$ is integral over $\mathcal{O}_K$, for the sake of contradiction say $x \notin \mathcal{O}_K$. As it is integral:

$$x^n + a_1 x^{n-1} + \cdots + a_n = 0$$

with $a_i \in \mathcal{O}_K$. If $x \notin \mathcal{O}_K$ then $\nu(x) < 0$, so $x^{-1} \in \mathcal{O}_K$; dividing the relation by x^{n-1} gives

$$x = -(a_1 + a_2 x^{-1} + \cdots + a_n x^{-(n-1)}),$$

whose right-hand side lies in $\mathcal{O}_K$ (each $x^{-j} \in \mathcal{O}_K$), forcing $x \in \mathcal{O}_K$, a contradiction, completing the proof.

These properties in fact characterize valuation rings:

Proposition 27.1.9: Characterizing Valuation Ring

Let k be a field, $R \subseteq k$ a sub-ring, and R^* the group of units of R. Then the following are equivalent:

1. R is a valuation ring of k
2. $k = \text{Frac}(R)$ and the ideals of R form a chain under inclusion
3. for every $x \in k \setminus \{0\}$, either $x \in R$ or $x^{-1} \in R$

Then $G = (k \setminus \{0\})/R^*$ is a totally ordered abelian group and

$$\nu_R : x \mapsto xR^*$$

is a valuation on k. The induced valuation ring is R. As a consequence, two valuations on the same field are equivalent if and only if they have the same valuation ring.

***Proof*:**
(1) $\Rightarrow$ (3) is proposition 27.1.8(1), and (1) $\Rightarrow$ (2) its parts (1) and (4). For (3) $\Rightarrow$ (2): (3) gives $k = \text{Frac}(R)$, and any two ideals $\mathfrak{a}, \mathfrak{b}$ are comparable, for if $a \in \mathfrak{a} \setminus \mathfrak{b}$ and $b \in \mathfrak{b}$ then $a/b \notin R$ (else $a \in (b) \subseteq \mathfrak{b}$), so $b/a \in R$ and $b \in (a) \subseteq \mathfrak{a}$, giving $\mathfrak{b} \subseteq \mathfrak{a}$. For (2) $\Rightarrow$ (3): for $x = a/b \in k^\times$ the principal ideals $(a), (b)$ are comparable, so $a/b \in R$ or $b/a \in R$. Given (3), $G = k^\times/R^*$ is totally ordered by $xR^* \leq yR^* \Leftrightarrow y/x \in R$, and $\nu_R(x) = xR^*$ is a valuation whose ring is $\{x \in k \mid \nu_R(x) \geq 0\} = R$; a valuation is determined up to equivalence by its ring.

27.2 Discrete Valuation Ring

Limiting to discrete valuation rings, then there is a smallest positive value s such that:

$$\nu(K^*) = s\mathbb{Z}$$

We can normalize this result and get an equivalent ν where $\nu(K^*) = \mathbb{Z}$ and $\mathcal{O}_K$, $\mathcal{O}_K^*$, and $\mathfrak{p}$ are the same. Then there must be an element such that

$$\nu(\pi) = 1$$

Labelling this element as π, we can use it to show that any $x \in K \setminus \{0\}$ can be written as :

$$x = u\pi^m$$

for a unit $u \in K^\times$ ($\nu(u) = 0$). To see this, let

$$\nu(x) = m \Rightarrow \nu(x\pi^{-m}) = 0 \Rightarrow u = x\pi^{-m} \in \mathcal{O}_K^*$$

which gives the result, where $m = \nu(x) \in \mathbb{Z}$. This in fact characterizes DVRs:

Proposition 27.2.1: Characterizing DVR

Let R be an integral domain and $k = \mathrm{Frac}(R)$. Then R is the valuation ring of a discrete valuation ν on k if and only if R is a PID with a unique nonzero prime ideal.

***Proof*:**
($\Rightarrow$) Normalize ν so $\nu(k^\times) = \mathbb{Z}$, with uniformizer π ($\nu(\pi) = 1$). Every nonzero $x \in R$ is $u\pi^n$ with u a unit and $n = \nu(x) \geq 0$, so every nonzero ideal equals $(\pi^n) = \mathfrak{m}^n$ for the least n occurring; thus R is a PID with unique nonzero prime $\mathfrak{m} = (\pi)$. ($\Leftarrow$) If R is a PID with unique nonzero prime (π), each nonzero $x \in R$ factors uniquely as $u\pi^n$; setting $\nu(x) = n$ and extending by $\nu(a/b) = \nu(a) - \nu(b)$ gives a discrete valuation on k with valuation ring R.

The DVRs are exactly the "nicest" one-dimensional local rings, characterized among Noetherian local domains of dimension one in several equivalent ways:

Theorem 27.2.2: Characterizations of a DVR

Let $(R, \mathfrak{m})$ be a Noetherian local domain of Krull dimension 1 with fraction field k. The following are equivalent:

1. R is a discrete valuation ring;
2. R is integrally closed (normal);
3. $\mathfrak{m}$ is principal;
4. every nonzero ideal of R is a power of $\mathfrak{m}$;
5. R is a regular local ring, i.e. $\dim_{R/\mathfrak{m}} \mathfrak{m}/\mathfrak{m}^2 = 1$.

***Proof*:**
(1) $\Rightarrow$ (2) is proposition 27.1.8(5), and (3) $\Leftrightarrow$ (5) holds since, by Nakayama (lemma 23.4.29), $\mathfrak{m}$ is principal iff $\dim_{R/\mathfrak{m}} \mathfrak{m}/\mathfrak{m}^2 = 1$. For (2) $\Rightarrow$ (3): pick $0 \neq a \in \mathfrak{m}$; as $\dim R = 1$, $\mathfrak{m}$ is the only prime over (a), so $\mathfrak{m}^n \subseteq (a)$ for some least n. Choose $b \in \mathfrak{m}^{n-1} \setminus (a)$ and put $t = a/b \in k$; then $b\mathfrak{m} \subseteq \mathfrak{m}^n \subseteq (a)$ gives $t^{-1}\mathfrak{m} = (b/a)\mathfrak{m} \subseteq R$. If $t^{-1}\mathfrak{m} \subseteq \mathfrak{m}$, the finitely generated faithful module $\mathfrak{m}$ would be stable under t^{-1}, making t^{-1} integral over R (determinant trick) and hence $t^{-1} \in R$ by normality, contradicting $b \notin (a)$. So $t^{-1}\mathfrak{m} = R$, i.e. $\mathfrak{m} = tR$ is principal. (3) $\Rightarrow$ (4): writing $\mathfrak{m} = (\pi)$, Krull's intersection theorem (corollary 25.4.11) gives $\bigcap_n \mathfrak{m}^n = 0$, so any nonzero ideal is $(\pi^n) = \mathfrak{m}^n$ for the largest n with the ideal $\subseteq \mathfrak{m}^n$. (4) $\Rightarrow$ (1): defining $\nu(x) = n$ where $(x) = \mathfrak{m}^n$ gives a discrete valuation on k with valuation ring R.

Example 27.2.3: Discrete Valuation Ring

1. The ring of p-adic integers $\mathbb{Z}_p$ is a discrete valuation ring.
2. For any prime p, $\mathbb{Z}_{(p)}$ the localization of $\mathbb{Z}$ at the prime (p) is a discrete valuation ring.

3. The ring $k[[x]]$ of formal power series is a DVR with unique non-zero prime ideal (x).
4. (If you know some analysis) The ring of convergent power series over $\mathbb{R}$ or $\mathbb{C}$ (those with a positive radius of convergence) is a DVR.
5. (If you know some complex analysis) Let X be a connected Riemann surface and let $M(X)$ be the field of meromorphic functions $X \to \mathbb{C} \cup \{\infty\}$. For each point $p \in X$, define a discrete valuation on $M(X)$ where
$$\nu_p(f) = i$$
where i is the largest number st
$$\frac{f(z)}{(z-p)^i}$$
can be extended to a holomorphic function (i.e. the order of the root/pole).

It shall be seen in algebraic geometry ([13]) that DVRs appear naturally in the study of smooth projective algebraic curves".

Proposition 27.2.4: Representation Of Elements Of a Complete DVR

Let k be a field with *complete* DVR $\mathcal{O}_k$, uniformizer π, and let $\mathcal{T} \subseteq \mathcal{O}_k$ contain 0 and exactly one element of every coset of $\mathfrak{m}$. Then every element $x \in \mathcal{O}_k$ is a unique convergent series
$$\sum_{i \geq 0} r_i \pi^i$$
with coefficients $r_i \in \mathcal{T}$, and every nonzero $x \in k$ is a unique Laurent series $\sum_{i \geq m} r_i \pi^i$ with $r_i \in \mathcal{T}$ for all $i \geq m$ and $r_m \neq 0$

***Proof*:**
By completeness, build the series by repeatedly subtracting coset representatives: let $r_0 \in \mathcal{T}$ represent $x \bmod \mathfrak{m}$, so $x - r_0 \in \mathfrak{m} = (\pi)$; write $x - r_0 = \pi x_1$ and repeat with x_1. The partial sums $\sum_{i<N} r_i \pi^i$ are Cauchy and converge to x, and the r_i are forced as coset representatives, giving uniqueness. The Laurent case follows by factoring out π^m with $m = \nu(x)$.

Valuation rings are the maximal objects in the domination order, which yields a clean description of integral closure.

Proposition 27.2.5: Domination and Existence of Valuation Rings

Let k be a field. Every local subring $A \subseteq k$ is dominated by a valuation ring $\mathcal{O}$ of k (that is, $A \subseteq \mathcal{O}$ and $\mathfrak{m}_{\mathcal{O}} \cap A = \mathfrak{m}_A$). Consequently, for a domain A with fraction field k, the integral closure of A in k is the intersection of the valuation rings of k containing A:
$$\overline{A} = \bigcap_{A \subseteq \mathcal{O}} \mathcal{O},$$
so A is integrally closed iff it is an intersection of valuation rings.

***Proof*:**
Order the local subrings of k dominating A by domination; the union of a chain dominates A, so by Zorn there is a maximal one $\mathcal{O}$. It is a valuation ring: suppose $x \in k$ with $x, x^{-1} \notin \mathcal{O}$. Not both of $\mathfrak{m}_{\mathcal{O}}\mathcal{O}[x]$ and $\mathfrak{m}_{\mathcal{O}}\mathcal{O}[x^{-1}]$ are the unit ideal, for otherwise $1 = \sum_{i \le n} a_i x^i = \sum_{j \le m} b_j x^{-j}$ with $a_i, b_j \in \mathfrak{m}_{\mathcal{O}}$ and n, m minimal, and eliminating the top power of x between the two relations lowers one of the degrees, a contradiction. Say $\mathfrak{m}_{\mathcal{O}}\mathcal{O}[x] \neq \mathcal{O}[x]$ and let $\mathfrak{n}$ be a maximal ideal of $\mathcal{O}[x]$ containing it; then $\mathcal{O}[x]_{\mathfrak{n}}$ is a local ring strictly dominating $\mathcal{O}$ (it contains $x \notin \mathcal{O}$), contradicting maximality. Every valuation ring is integrally closed (proposition 27.1.8), so $\overline{A} \subseteq \bigcap \mathcal{O}$. Conversely, if $x \in k$ is not integral over A, then x^{-1} is a non-unit of $A[x^{-1}]$, hence lies in a maximal ideal $\mathfrak{n}$; the localization $A[x^{-1}]_{\mathfrak{n}}$ is dominated by a valuation ring $\mathcal{O} \supseteq A$ with $x^{-1} \in \mathfrak{m}_{\mathcal{O}}$, so $\nu(x) < 0$ and $x \notin \mathcal{O}$. Thus $\bigcap \mathcal{O} \subseteq \overline{A}$.

Proposition 27.2.6: Extension of Valuations

Let $K \subseteq L$ be a field extension and ν a valuation on K with valuation ring $\mathcal{O}_\nu$. Then ν extends to a valuation on L.

***Proof*:**
The local ring $\mathcal{O}_\nu \subseteq L$ is dominated by a valuation ring $\mathcal{O}$ of L (proposition 27.2.5). Then $\mathcal{O} \cap K$ is a valuation ring of K dominating $\mathcal{O}_\nu$, hence equals $\mathcal{O}_\nu$, so the valuation of $\mathcal{O}$ restricts to ν on K.

Discrete valuation rings are the local rings of the nonsingular points of curves, and two questions about them are what the geometry needs. Is the integral closure of a one-dimensional Noetherian domain in a finite extension of its fraction field again Noetherian? It is (theorem 27.2.8), and this is not automatic: the integral closure of a Noetherian domain need not be a finite module over it (Akizuki's example, [74, (31.A)]), so theorem 26.1.11 does not apply. Is every Noetherian local domain that is not a field dominated by a discrete valuation ring? It is, and the discrete valuation ring can be chosen with any prescribed finitely generated extension of the fraction field as its fraction field (theorem 27.2.11). Both results are the algebraic input for the valuative criteria of separatedness and properness over discrete valuation rings in [13]. Domination is the relation of proposition 27.2.5, and ℓ_R denotes length over R (proposition 23.1.8).

Lemma 27.2.7: Length Bound for Torsion-Free Modules over a One-Dimensional Domain

Let R be a Noetherian domain with $\dim R = 1$ and fraction field K, let V be a K-vector space with $\dim_K V = r < \infty$, let $M \subseteq V$ be an R-submodule, so that M is torsion-free, and let $x \in R$ be nonzero. Then R/xR and M/xM are R-modules of finite length, and $\ell_R(M/xM) \le r\,\ell_R(R/xR)$.

***Proof*:**
Step 1: a finitely generated module killed by a nonzero element has finite length. Let $f \in R$ be nonzero and let Q be a finitely generated R-module with $fQ = 0$. If f is a unit then $Q = 0$. Otherwise R/fR is a nonzero Noetherian ring (proposition 23.1.2) whose prime ideals correspond to the primes $\mathfrak{p}$ of R containing f. Such a $\mathfrak{p}$ is nonzero, and a nonzero prime of a domain of dimension one is maximal, since $\mathfrak{p} \subsetneq \mathfrak{q}$ for a prime $\mathfrak{q}$ would give a chain $0 \subsetneq \mathfrak{p} \subsetneq \mathfrak{q}$ of length two.

Hence every prime of R/fR is maximal, $\dim R/fR = 0$, and R/fR is Artinian (corollary 28.1.9). As Q is a finitely generated R/fR-module, it has finite length over R/fR (proposition 28.1.19), and since the R-submodules of Q are its R/fR-submodules, Q has finite length over R. Taking $Q = R/xR$ and $f = x$ shows $\ell_R(R/xR) < \infty$. Submodules and quotients of a module of finite length have finite length, their chains of submodules being chains, or lifting to chains, in the module. Applying proposition 28.1.16 to $0 \to R/xR \to (R/xR)^{\oplus n} \to (R/xR)^{\oplus(n-1)} \to 0$ and inducting on n gives $\ell_R((R/xR)^{\oplus n}) = n\,\ell_R(R/xR)$.

Step 2: the finitely generated case. Let $M' \subseteq V$ be a finitely generated R-submodule, let KM' be its K-span, and let $r' = \dim_K KM' \leq r$. Since M' spans KM' over K, it contains a K-basis $m_1, \dots, m_{r'}$ of KM'. The m_i are linearly independent over K, hence over R, so $F := Rm_1 + \cdots + Rm_{r'}$ is a free R-module with basis $m_1, \dots, m_{r'}$ and $F/xF \cong (R/xR)^{\oplus r'}$, whence $\ell_R(F/xF) = r'\,\ell_R(R/xR)$ by Step 1. Let $g_1, \dots, g_s$ generate M' and write $g_j = \sum_i c_{ij} m_i$ with $c_{ij} \in K$. A common denominator $d \in R \setminus \{0\}$ of the finitely many c_{ij} satisfies $dg_j \in F$ for all j, so $dM' \subseteq F$. Multiplication by x is injective on the K-vector space V and carries M' onto xM' and F onto xF, so it induces an isomorphism $M'/F \cong xM'/xF$ of R-modules. The module M'/xF is finitely generated and killed by xd, so it has finite length by Step 1, and so do its submodules F/xF and xM'/xF and its quotients M'/F and M'/xM'. Applying proposition 28.1.16 to the two short exact sequences

$$0 \to F/xF \to M'/xF \to M'/F \to 0, \qquad 0 \to xM'/xF \to M'/xF \to M'/xM' \to 0$$

gives $\ell_R(F/xF) + \ell_R(M'/F) = \ell_R(M'/xF) = \ell_R(xM'/xF) + \ell_R(M'/xM')$, and $\ell_R(xM'/xF) = \ell_R(M'/F)$. Cancelling,

$$\ell_R(M'/xM') = \ell_R(F/xF) = r'\,\ell_R(R/xR) \leq r\,\ell_R(R/xR)$$

which is the bound for M'.

Step 3: the general case. Put $B := r\,\ell_R(R/xR)$. We claim that every strictly ascending chain $N_0 \subsetneq N_1 \subsetneq \cdots \subsetneq N_k$ of R-submodules of M/xM has $k \leq B$. For $1 \leq i \leq k$ choose $m_i \in M$ whose class in M/xM lies in $N_i \setminus N_{i-1}$, and put $M' := Rm_1 + \cdots + Rm_k \subseteq M$. As $xM' \subseteq xM$, the inclusion $M' \subseteq M$ induces an R-linear map $\varphi : M'/xM' \to M/xM$. Put $N'_i := \varphi^{-1}(N_i)$. Then $N'_0 \subseteq N'_1 \subseteq \cdots \subseteq N'_k$, and the class of m_i in M'/xM' lies in $N'_i \setminus N'_{i-1}$, because φ sends it to the class of m_i in M/xM. So the N'_i form a strictly ascending chain of length k in M'/xM', which has finite length at most B by Step 2. Reversing the chain, and adjoining M'/xM' at the top and 0 at the bottom if they are missing, gives a chain in the sense of definition 23.1.7 of length at least k. It extends to a composition series (proposition 23.1.8), whose length is $\ell_R(M'/xM')$, so $k \leq \ell_R(M'/xM') \leq B$.

Consequently M/xM is Noetherian and Artinian: an infinite strictly ascending chain would have initial segments of length exceeding B, and an infinite strictly descending chain $P_0 \supsetneq P_1 \supsetneq \cdots$ would give the strictly ascending chains $P_k \subsetneq P_{k-1} \subsetneq \cdots \subsetneq P_0$ of every length k. So M/xM has finite length (definition 28.1.13). Among the chains $M/xM = P_0 \supsetneq P_1 \supsetneq \cdots \supsetneq P_n = 0$ choose one of maximal length $n \leq B$. It admits no refinement, so it is a composition series, and $\ell_R(M/xM) = n \leq B$ by proposition 23.1.8.

Theorem 27.2.8: Krull-Akizuki

Let R be a Noetherian domain with $\dim R = 1$ and fraction field K, let L/K be a finite extension of fields, and let A be a ring with $R \subseteq A \subseteq L$. Then:

1. for every nonzero $x \in R$, the R-module A/xA has finite length and $\ell_R(A/xA) \leq [L : K]\, \ell_R(R/xR)$,
2. A is Noetherian,
3. every nonzero prime ideal of A is maximal, so $\dim A \leq 1$, with $\dim A = 1$ unless A is a field.

***Proof*:**

(1) is lemma 27.2.7 for the R-submodule A of the K-vector space $V = L$, whose dimension is $r = [L : K]$.

(2) Let I be a nonzero ideal of A (the zero ideal is generated by 0). The intersection $I \cap R$ is nonzero: pick $a \in I$ nonzero. It is algebraic over K (*Core Algebra*[a]), so $c_n a^n + \cdots + c_1 a + c_0 = 0$ for some $c_0, \ldots, c_n \in K$ not all zero, and multiplying by a common denominator we may take all $c_i \in R$. Choose such a relation with n minimal. Then $c_0 \neq 0$: otherwise $a\,(c_n a^{n-1} + \cdots + c_1) = 0$ with $a \neq 0$ in the field L gives the relation $c_n a^{n-1} + \cdots + c_1 = 0$ of smaller degree with coefficients in R not all zero. Hence

$$x := c_0 = -a\,(c_n a^{n-1} + \cdots + c_1) \in aA \subseteq I$$

is a nonzero element of $I \cap R$. Now $xA \subseteq I$, so I/xA is an R-submodule of A/xA, which has finite length by (1). Hence I/xA is a Noetherian R-module, and therefore finitely generated over R: otherwise one could choose $y_1, y_2, \cdots \in I/xA$ with $y_{j+1} \notin Ry_1 + \cdots + Ry_j$ for all j, an infinite strictly ascending chain of submodules. Let $y_1, \ldots, y_s \in I$ have classes generating I/xA over R. Then $I = xA + Ry_1 + \cdots + Ry_s \subseteq (x, y_1, \ldots, y_s)A \subseteq I$, so I is a finitely generated ideal. Every ideal of A being finitely generated, A is Noetherian (proposition 23.1.3).

(3) Let $\mathfrak{p}$ be a nonzero prime ideal of A. By the argument in (2) there is a nonzero $x \in \mathfrak{p} \cap R$. The ring $A/\mathfrak{p}$ is a quotient of the R-module A/xA, hence an R-module of finite length by (1), in particular an Artinian R-module. Its ideals are R-submodules, so every descending chain of ideals of $A/\mathfrak{p}$ stabilizes, and $A/\mathfrak{p}$ is an Artinian ring. It is a domain, so its zero ideal is prime, hence maximal (proposition 28.1.5), and $A/\mathfrak{p}$ is a field: $\mathfrak{p}$ is a maximal ideal of A. Thus a chain of prime ideals of A has at most one nonzero term, so $\dim A \leq 1$, and if A is not a field then a nonzero maximal ideal $\mathfrak{n}$ gives the chain $0 \subsetneq \mathfrak{n}$, so $\dim A = 1$.

[a] corollary 19.3.4.

Corollary 27.2.9: Integral Closure of a One-Dimensional Noetherian Domain

Let R be a Noetherian domain with $\dim R = 1$ and fraction field K, let L/K be a finite extension of fields, and let $R' = \overline{R}^L$ be the integral closure of R in L. Then R' is a Noetherian normal domain with $\dim R' = 1$ and fraction field L, integral over R, and for every maximal ideal $\mathfrak{n}$ of R' the localization $R'_{\mathfrak{n}}$ is a discrete valuation ring with fraction field L.

***Proof*:**
The ring R' is a subring of L containing R (corollary 26.1.6), so it is a domain, integral over R, and theorem 27.2.8 shows it is Noetherian with $\dim R' \leq 1$. Its fraction field is L: a nonzero $a \in L$ is algebraic over K, so after clearing denominators $c_n a^n + \cdots + c_1 a + c_0 = 0$ with $n \geq 1$, $c_i \in R$ and $c_n \neq 0$, and multiplying this relation by c_n^{n-1} exhibits $c_n a$ as a root of a monic polynomial over R, so $c_n a \in R'$ and $a = (c_n a)/c_n$ is a quotient of elements of R'. Being integrally closed in L (corollary 26.1.6), R' is a normal domain. Since $\dim R = 1$, R is not a field, so R' is not a field (proposition 26.1.8) and has a nonzero prime ideal, whence $\dim R' = 1$ by theorem 27.2.8(3). Let $\mathfrak{n}$ be a maximal ideal of R'. The localization $R'_{\mathfrak{n}}$ is Noetherian by proposition 23.4.5(4), local with maximal ideal $\mathfrak{n}R'_{\mathfrak{n}}$ by proposition 23.4.5(3), and a domain, as $R' \subseteq R'_{\mathfrak{n}} \subseteq L$. Its prime ideals correspond to the primes of R' contained in $\mathfrak{n}$, namely 0 and $\mathfrak{n}$, since $\mathfrak{n} \neq 0$ (R' is not a field) and every nonzero prime of R' is maximal by theorem 27.2.8(3), so $\dim R'_{\mathfrak{n}} = 1$. Its fraction field is L, as $R' \subseteq R'_{\mathfrak{n}} \subseteq L$, and it is integrally closed in L by corollary 26.1.10 applied to R' and $D = R' \setminus \mathfrak{n}$. By theorem 27.2.2, $R'_{\mathfrak{n}}$ is a discrete valuation ring.

Lemma 27.2.10: Discrete Valuation Rings Dominating a One-Dimensional Local Domain

Let $(R, \mathfrak{m})$ be a Noetherian local domain with $\dim R = 1$ and fraction field K, and let L/K be a finite extension of fields. Then there is a discrete valuation ring V with fraction field L dominating R, that is, $R \subseteq V$ and $\mathfrak{m}_V \cap R = \mathfrak{m}$.

***Proof*:**
Let $R' = \overline{R}^L$. By corollary 27.2.9, R' is a Noetherian normal domain of dimension one with fraction field L, integral over R. Lying over (theorem 26.3.3(1), for the integral extension R' of the domain R) gives a prime ideal $\mathfrak{n}$ of R' with $\mathfrak{n} \cap R = \mathfrak{m}$, and $\mathfrak{n}$ is maximal because $\mathfrak{m}$ is. Put $V := R'_{\mathfrak{n}}$, a discrete valuation ring with fraction field L by corollary 27.2.9, with maximal ideal $\mathfrak{m}_V = \mathfrak{n}R'_{\mathfrak{n}}$. Then $R \subseteq R' \subseteq V$, and since $\mathfrak{n}R'_{\mathfrak{n}} \cap R' = \mathfrak{n}$ (proposition 23.4.5(3)),

$$\mathfrak{m}_V \cap R = (\mathfrak{n}R'_{\mathfrak{n}} \cap R') \cap R = \mathfrak{n} \cap R = \mathfrak{m}$$

so V dominates R.

Theorem 27.2.11: Discrete Valuation Rings Dominating a Noetherian Local Domain

Let $(R, \mathfrak{m})$ be a Noetherian local domain that is not a field, let K be its fraction field, and let L/K be a finitely generated extension of fields. Then there is a discrete valuation ring V with fraction field L dominating R, that is, $R \subseteq V$ and $\mathfrak{m}_V \cap R = \mathfrak{m}$.

***Proof*:**
Domination is transitive: if $A \subseteq B \subseteq C$ are local rings with $\mathfrak{m}_B \cap A = \mathfrak{m}_A$ and $\mathfrak{m}_C \cap B = \mathfrak{m}_B$, then $\mathfrak{m}_C \cap A = (\mathfrak{m}_C \cap B) \cap A = \mathfrak{m}_B \cap A = \mathfrak{m}_A$.

Step 1: R is dominated by a Noetherian local domain of dimension one with fraction field K. Since R is Noetherian and not a field, $\mathfrak{m} \neq 0$ is generated by finitely many elements, which we

may take nonzero: $x_1, \dots, x_r$ with $r \geq 1$. By proposition 27.2.5 there is a valuation ring $\mathcal{O}$ of K dominating R, so $R \subseteq \mathcal{O}$ and $\mathfrak{m}_{\mathcal{O}} \cap R = \mathfrak{m}$. For nonzero $a, b \in K$, either $a/b \in \mathcal{O}$ or $b/a \in \mathcal{O}$ (proposition 27.1.9(3)). Hence we may renumber the x_i so that $x_i/x_r \in \mathcal{O}$ for all i: if $x_i/x_k \in \mathcal{O}$ for all $i \leq k$, then either $x_{k+1}/x_k \in \mathcal{O}$, so that x_k serves for all $i \leq k+1$, or $x_k/x_{k+1} \in \mathcal{O}$, so that $x_i/x_{k+1} = (x_i/x_k)(x_k/x_{k+1}) \in \mathcal{O}$ for all $i \leq k+1$. Consider the R-subalgebra

$$S := R[x_1/x_r, \dots, x_{r-1}/x_r] \subseteq \mathcal{O} \subseteq K$$

of K. It is a domain, Noetherian by corollary 23.2.5, with fraction field K because $R \subseteq S \subseteq K$. Since $x_i = (x_i/x_r)\, x_r \in x_r S$ for every i and $x_r \in \mathfrak{m}$, we have $\mathfrak{m}S = x_r S$. The ideal $x_r S$ is proper: $x_r \in \mathfrak{m} \subseteq \mathfrak{m}_{\mathcal{O}}$ is not a unit of $\mathcal{O}$, so it is not a unit of the subring S, an inverse in S being an inverse in $\mathcal{O}$. The set of prime ideals of S containing $x_r S$ is therefore nonempty, and since the intersection of a chain of prime ideals is prime, Zorn's lemma gives a prime ideal $\mathfrak{q}$ of S minimal over $x_r S$.[a] By theorem 29.5.2 (the case $c = 1$), $\operatorname{ht}\mathfrak{q} \leq 1$, and since $0 \neq x_r \in \mathfrak{q}$ in the domain S, the chain $0 \subsetneq \mathfrak{q}$ gives $\operatorname{ht}\mathfrak{q} = 1$. Moreover $\mathfrak{q} \cap R = \mathfrak{m}$: the ideal $\mathfrak{q} \cap R$ of R contains $\mathfrak{m}$, because $\mathfrak{m} \subseteq \mathfrak{m}S = x_r S \subseteq \mathfrak{q}$, and it is proper, because $1 \notin \mathfrak{q}$. Put $R_1 := S_{\mathfrak{q}}$. It is Noetherian by proposition 23.4.5(4) and a domain, as $S \subseteq R_1 \subseteq K$. Its prime ideals are the extensions $\mathfrak{p}S_{\mathfrak{q}}$ of the primes $\mathfrak{p} \subseteq \mathfrak{q}$ of S (proposition 23.4.5(3)), and the bijection, extension with inverse contraction, preserves inclusions in both directions. Hence R_1 is local with maximal ideal $\mathfrak{q}S_{\mathfrak{q}}$ and $\dim R_1 = \operatorname{ht}\mathfrak{q} = 1$. Its fraction field is K, as $S \subseteq R_1 \subseteq K$. Finally $\mathfrak{q}S_{\mathfrak{q}} \cap S = \mathfrak{q}$ (proposition 23.4.5(3)), so

$$\mathfrak{m}_{R_1} \cap R = (\mathfrak{q}S_{\mathfrak{q}} \cap S) \cap R = \mathfrak{q} \cap R = \mathfrak{m}$$

and R_1 dominates R.

Step 2: the case L/K finite. With R_1 as in Step 1, lemma 27.2.10 gives a discrete valuation ring V with fraction field L dominating R_1, hence dominating R. In particular, for $L = K$, there is a discrete valuation ring V_0 with fraction field K dominating R.

Step 3: adjoining a transcendental element. Let V be a discrete valuation ring with fraction field F and maximal ideal $\mathfrak{m}_V = \pi V$, and let t be transcendental over F. Put $\mathfrak{p} := \pi V[t]$. Then $\mathfrak{p}$ is a prime ideal of $V[t]$, and $W := V[t]_{\mathfrak{p}}$ is a discrete valuation ring with fraction field $F(t)$ dominating V. The ring V is a principal ideal domain (proposition 27.2.1), hence Noetherian, every ideal being generated by a single element (proposition 23.1.3), so $V[t]$ is a Noetherian domain (theorem 23.2.1). Its fraction field is $F(t)$: every element of $F[t]$ is h/d with $h \in V[t]$ and $d \in V \setminus \{0\}$ a common denominator of its coefficients, so $F[t] \subseteq \operatorname{Frac}(V[t]) \subseteq F(t)$, and $F(t)$ is the fraction field of $F[t]$. Reducing coefficients modulo π is a surjective ring homomorphism $V[t] \to (V/\pi V)[t]$ with kernel $\pi V[t] = \mathfrak{p}$, and $(V/\pi V)[t]$ is a polynomial ring over the field $V/\pi V$, hence a domain, so $\mathfrak{p}$ is a prime ideal, nonzero and proper. The localization W is Noetherian by proposition 23.4.5(4), local with maximal ideal $\mathfrak{p}W = \pi W$ by proposition 23.4.5(3), and a domain, as $V[t] \subseteq W \subseteq F(t)$. Its primes correspond to the primes of $V[t]$ contained in $\mathfrak{p}$, so $\dim W = \operatorname{ht}\mathfrak{p}$. The prime $\mathfrak{p}$ is minimal over the principal ideal $\pi V[t] = \mathfrak{p}$, so $\operatorname{ht}\mathfrak{p} \leq 1$ by theorem 29.5.2, and $\mathfrak{p} \neq 0$ gives $\operatorname{ht}\mathfrak{p} = 1$. Thus W is a Noetherian local domain of dimension one whose maximal ideal is principal, hence a discrete valuation ring by theorem 27.2.2, with fraction field $\operatorname{Frac}(W) = \operatorname{Frac}(V[t]) = F(t)$. Finally $V \subseteq V[t] \subseteq W$, and $\mathfrak{m}_W \cap V$ is a proper ideal of V containing π, so $\mathfrak{m}_W \cap V = \pi V = \mathfrak{m}_V$, and W dominates V.

Step 4: assembly. Write $L = K(s_1, \dots, s_n)$. Since L is algebraic over $K(s_1, \dots, s_n) = L$, the existence theorem for transcendence bases,[b] applied to the subset $\{s_1, \dots, s_n\}$ and $A = \emptyset$, gives a transcendence basis $\{t_1, \dots, t_m\} \subseteq \{s_1, \dots, s_n\}$ of L/K, with $m \geq 0$. Put $F_i := K(t_1, \dots, t_i)$,

so that $F_0 = K$. Each t_i is transcendental over F_{i-1}: a nonzero $p \in F_{i-1}[T]$ with $p(t_i) = 0$ has coefficients of the form $a_j(t_1, \ldots, t_{i-1})/b(t_1, \ldots, t_{i-1})$ with $a_j, b \in K[T_1, \ldots, T_{i-1}]$, $b \neq 0$ and some $a_j \neq 0$, and then $P := \sum_j a_j(T_1, \ldots, T_{i-1})\, T_i^j \in K[T_1, \ldots, T_i]$ is a nonzero polynomial with $P(t_1, \ldots, t_i) = b(t_1, \ldots, t_{i-1})\, p(t_i) = 0$, contradicting the algebraic independence of $t_1, \ldots, t_m$ over K. The extension L/F_m is algebraic, and $L = F_m(s_1, \ldots, s_n)$ is generated over F_m by finitely many algebraic elements, so $[L : F_m] < \infty$ (*Core Algebra* theorem 19.3.11). Step 2 gives a discrete valuation ring V_0 with fraction field $F_0 = K$ dominating R, and Step 3, applied m times, gives discrete valuation rings V_i with fraction field F_i such that V_i dominates V_{i-1} for $1 \leq i \leq m$. The ring V_m is a principal ideal domain with a unique nonzero prime ideal (proposition 27.2.1), hence a Noetherian local domain of dimension one with fraction field F_m, and L/F_m is finite, so lemma 27.2.10 gives a discrete valuation ring V with fraction field L dominating V_m. By transitivity, V dominates R.

[a] Let ab lie in every member of a chain of prime ideals, with a outside some member $\mathfrak{p}_0$. A member contained in $\mathfrak{p}_0$, including $\mathfrak{p}_0$ itself, does not contain a, so it contains b. A member containing $\mathfrak{p}_0$ contains b as well, since $b \in \mathfrak{p}_0$. The intersection therefore contains b, and it is proper, so it is prime.

[b] theorem 19.2.13.

The dimension hypothesis of theorem 27.2.8 enters through Step 1 of lemma 27.2.7, where it makes every nonzero prime of R maximal. In dimension two the integral closure of a Noetherian domain in a finite extension of its fraction field is still Noetherian, but by a different argument ([74, Theorem 105]). Theorem 27.2.8 is [98, Tag 00PG] and [74, (41.C)], and theorem 27.2.11 is [98, Tag 00PH], whose reduction to dimension one ([98, Tag 00P8]) is Step 1 of the proof. The scheme-theoretic consequences, the valuative criteria of separatedness and properness over discrete valuation rings, are proved in [13].

Exercise 27.2.1

1. Show that an abelian group admits a translation-invariant total order if and only if it is torsion-free.
2. Let $\mathcal{O}$ be a DVR with unique prime $\mathfrak{p}$. Show that $\mathfrak{p}^n/\mathfrak{p}^{n+1} \cong \mathcal{O}/\mathfrak{p}$ for $n \geq 0$
3. Let $x \in \mathfrak{m}$ be a non-unit of a complete DVR $\mathcal{O}$. Show that $1 - x$ is a unit, its inverse being the convergent series $\sum_{n \geq 0} x^n$.

28

Artinian Rings

Being Noetherian brings a consistent notion of finiteness to rings, letting us define concepts like dimension. It is natural to ask what the dual *descending chain condition* yields. This chapter studies rings and modules satisfying the D.C.C.; it turns out to be far more restrictive than the A.C.C., forcing an Artinian ring to be zero-dimensional and, in fact, a finite product of local Artinian rings.

28.1 Artinian Rings and Modules

Definition 28.1.1: Artinian module and ring

Let M be a R-module. Then if M satisfies the *descending chain condition* on submodules, it is an *artinian module*. More precisely, for any collection of submodules such that

$$M_1 \supseteq M_2 \supseteq \cdots \supseteq M_k \supseteq \cdots$$

then for some n, we get $M_n = M_{n+1} = \cdots$.
If we let $M = R$ be a module over itself, then we say that R is an *Artinian ring*.

Naturally, an Artinian ring has the D.C.C. condition on its ideals.

Proposition 28.1.2: Artinian Module Equivalent

M is Artinian if and only if every non-empty set of submodules of M contains a minimal element under inclusion

***Proof*:**
If M satisfies the D.C.C. and a nonempty set $\mathcal{S}$ of submodules had no minimal element, choose $M_1 \in \mathcal{S}$ and inductively $M_{i+1} \subsetneq M_i$ in $\mathcal{S}$, an infinite strictly descending chain, a contradiction. Conversely, if every nonempty set has a minimal element, a descending chain $M_1 \supseteq M_2 \supseteq \cdots$ has a minimal M_n, whence $M_n = M_{n+1} = \cdots$.

Just like Noetherian modules, a quotient of an Artinian module is Artinian.

Lemma 28.1.3: Artinian Module Closed Under Quotient

Let M be an Artinian module and $N \subseteq M$. Then M/N is also Artinian

***Proof*:**
A descending chain of submodules of M/N pulls back, via the correspondence for $M \twoheadrightarrow M/N$, to a descending chain of submodules of M containing N, which stabilizes; hence the chain in M/N stabilizes.

Example 28.1.4: Artinian, But Not Noetherian Module
Take $\mathbb{Z}[1/2]/\mathbb{Z}$ as a $\mathbb{Z}$-module. Its submodules form the increasing chain

$$0 \subsetneq \tfrac{1}{2}\mathbb{Z}/\mathbb{Z} \subsetneq \tfrac{1}{4}\mathbb{Z}/\mathbb{Z} \subsetneq \cdots, \qquad \tfrac{1}{2^n}\mathbb{Z}/\mathbb{Z} \cong \mathbb{Z}/2^n\mathbb{Z},$$

and these are all of its submodules. Any descending chain among them is eventually constant, so the module is Artinian, while the increasing chain shows it is not Noetherian. (It is a module, not a ring.)

However, unlike Noetherian rings, Artinian rings need to satisfy stronger properties on their ideals:

Proposition 28.1.5: Artinian, Prime $\Rightarrow$ Maximal

Let R be an Artinian ring and $P \subseteq R$ be a prime ideal. Then P is maximal

Notice how this differs from Noetherian rings: $\mathbb{Z}[x]$ is Noetherian, (x) is prime, but not maximal since $(x) \subsetneq (2, x)$. Thus, being Artinian immediately imposes stronger conditions on its ideals.

***Proof*:**
Consider R/P, which is also artinian by lemma 28.1.3. We will show $R/P = F$ is a field. COnsider $x \in F \setminus \{0\}$. Then by the descendign chain condition:

$$(x) \supseteq (x^2) \supseteq \cdots$$

must staxalize, that is for some n:

$$(x^n) = (x^{n+1})$$

which implies $x^n = x^{n+1}c$. By the Cancellion law, we get $1 = xc$, showing that x is in fact a unit. Since every element is a unit in F, we have that F is in fact a field, and so P is maximal, as we sought to show.

Theorem 28.1.6: Structure Theorem for Artinian Rings

Let R be an Artinian ring. Then:

1. There are only finitely many maximal ideals
2. The quotient $R/(\text{Jac}(R))$ is the direct product of a finite number of fields, where if there are n maximal ideals, we have a direct product of n fields R/M_i.
3. Every prime ideal of R is maximal. Thus $\text{kdim}(R) = 0$. As a consequence, $\text{Jac}(R) = \text{Nil}(R)$ and is a nilpotent ideal, $(\text{Jac}(R))^n = 0$ for some $n \geq 1$
4. R is isomorphic to a direct product of a finite number of local artinian rings
5. Every Artinian ring is Noetherian

Note that the last conditions is not true for Artinian Modules.

***Proof*:**

1. Consider the chain:
$$m_1 \supseteq m_1 \cap m_2 \supseteq \cdots$$
I first claim that each inclusion of this chain is proper. To see this, recall that if m_i and m_j are non-equal maximal ideal, it must be that $m_i + m_j = 1$. Thus, any collection of maximal ideals has this pair-wise condition. By the Chinese Remainder Theorem:
$$R/(m_1 \cap \cdots \cap m_n) \cong R/m_1 \times R/m_2 \times \cdots \times R/m_n$$
Now simply see that the element $(\overline{0}, ..., \overline{0}, \overline{1})$ is non-zero, and hence not contain in $m_1 \cap \cdots \cap m_n$, showing that each inclusion *must* be proper! Thus, by the D.C.C., the above chain must stabalize, meaning there can only be finitely many maximal ideals.
2. The proof follows immediately from the previous observation of the CRT
3. First, $J := \text{Jac}(R)$ is nilpotent: by the D.C.C. the chain $J \supseteq J^2 \supseteq \cdots$ stabilizes, say $J^k = J^{k+1}$. If $J^k \neq 0$, the nonempty set of ideals I with $IJ^k \neq 0$ has a minimal element I_0; pick $a \in I_0$ with $aJ^k \neq 0$, so $(a) \subseteq I_0$ is in the set and $(a) = I_0$ by minimality. Then $((a)J)J^k = (a)J^{k+1} = (a)J^k \neq 0$ and $(a)J \subseteq (a)$, so $(a)J = (a)$ by minimality, and Nakayama (lemma 23.4.27, as $J \subseteq \text{Jac}(R)$) forces $(a) = 0$, a contradiction. Hence $J^k = 0$, so $J \subseteq \sqrt{(0)} = \text{Nil}(R)$; the reverse inclusion always holds, giving $\text{Jac}(R) = \text{Nil}(R)$. Now let P be prime. As $P \supseteq \text{Nil}(R) = J$, its image in $R/J \cong k_1 \times \cdots \times k_n$ is a prime; since ideals of a product are products of ideals, that image is $k_1 \times \cdots \times 0 \times \cdots \times k_n$, which is maximal, so P is maximal by the correspondence theorem. Thus every prime is maximal and $\text{kdim} R = 0$.
4. Let $m_1, ..., m_n$ be the maximal ideals of R and let k be such that $(\text{Jac}(R))^k = 0$. Then
$$\prod_i^n M_i^k \subseteq \left(\prod_i^n M_i\right)^k \subseteq (\text{Jac}(R))^k = 0$$

Thus, by the CRT

$$R \cong (R/M_1^k) \times \cdots \times (R/M_n^k)$$

Notice that each R/M_i^k is an artinian with unique maximal ideal M_i/M_i^k.

5. By part (4) it suffices to show local Artinian rings are Noetherian. Let $\mathfrak{m}$ be the maximal ideal; then $\mathfrak{m} = \mathrm{Jac}(R)$ and $\mathfrak{m}^k = 0$ for some k (part 3), giving the filtration $R \supseteq \mathfrak{m} \supseteq \mathfrak{m}^2 \supseteq \cdots \supseteq \mathfrak{m}^k = 0$. Each quotient $\mathfrak{m}^i/\mathfrak{m}^{i+1}$ is a vector space over the field $R/\mathfrak{m}$ satisfying the D.C.C., hence finite-dimensional (lemma 28.1.11) and of finite length; concatenating their composition series gives one for R, so R is Noetherian.

Corollary 28.1.7: Uniqueness of the Local Decomposition

The decomposition of an Artinian ring $R \cong \prod_{i=1}^n R_i$ into local Artinian rings is unique up to reordering: the factors are the localizations $R_i \cong R_{\mathfrak{m}_i}$ at the maximal ideals (which here coincide with the completions $\hat{R}_{\mathfrak{m}_i}$), corresponding to the primitive idempotents of R.

***Proof*:**
In a product $\prod R_j$ of local rings the idempotents are the tuples of 0s and 1s, the primitive ones being the standard vectors e_i; hence the factors $R_i = e_i R$ are intrinsic. Localizing at $\mathfrak{m}_i$ kills every e_j with $j \neq i$ (each $1 - e_j \notin \mathfrak{m}_i$ becomes a unit and $e_j(1 - e_j) = 0$), leaving R_i, so $R_{\mathfrak{m}_i} \cong R_i$; and R_i, being local Artinian, is complete.

Corollary 28.1.8: Reduced Artinian Rings

An Artinian ring is reduced if and only if it is a finite product of fields.

***Proof*:**
A finite product of fields is reduced. Conversely, if R is reduced Artinian then $\mathrm{Nil}(R) = 0$, so by the structure theorem $R \cong \prod_i R/\mathfrak{m}_i^k$ with $\bigcap_i \mathfrak{m}_i^k = \mathrm{Nil}(R) = 0$; reducedness forces each local factor to have zero nilradical, i.e. $\mathfrak{m}_i^k = 0$ collapses to $\mathfrak{m}_i = 0$ there, so each factor is the field $R/\mathfrak{m}_i$.

Corollary 28.1.9: Artinian Ring Equivalent Condition I

Let R be a ring. Then R is Artinian if and only if R is Noetherian and $\dim(R) = 0$

***Proof*:**
R Artinian implies R Noetherian (theorem 28.1.6) with all primes maximal, i.e. $\dim R = 0$. For the converse, let R be Noetherian with $\dim R = 0$. Its minimal primes $\mathfrak{m}_1, \ldots, \mathfrak{m}_n$ are finite in number (Noetherian) and all maximal ($\dim R = 0$), and $\mathrm{Nil}(R) = \mathfrak{m}_1 \cap \cdots \cap \mathfrak{m}_n$ is nilpotent (finitely generated), so $(\mathfrak{m}_1 \cdots \mathfrak{m}_n)^k \subseteq \mathrm{Nil}(R)^k = 0$ for some k. By the Chinese Remainder Theorem $R \cong \prod_i R/\mathfrak{m}_i^k$, each factor Noetherian local with nilpotent maximal ideal, hence of finite length and Artinian; so R is Artinian.

Corollary 28.1.10: Artinian Ring Equivalent Condition II

Let k be a field and R a finitely generated k-algebra. Then R is artinian if and only if R is finitely generated as a k-module.

***Proof*:**
If R is a finite-dimensional k-vector space, its ideals are k-subspaces, so the D.C.C. holds and R is Artinian. Conversely, if R is Artinian then $\dim R = 0$ (theorem 28.1.6), and a finitely generated k-algebra of dimension 0 is a finite k-module (chapter 29).

For artinian modules over a field $R = k$, there is a clean characterization:

Lemma 28.1.11: Artin+Noetherian Module

Let M be a vector space over k. Then the following are equivalent:

1. M satisfies the A.C.C.
2. M satisfies the D.C.C.
3. M is finite-dimensional

***Proof*:**
Naturally, (3) implies both (1) and (2). Conversely, assume $\dim_k(M) = \infty$, so pick some infinite collection of linearly independent vectors. Then we have an infinite strict chain:

$$\langle e_1 \rangle \subsetneq \langle e_1, e_2 \rangle \cdots$$

and an infinite descending chain:

$$\langle e_1, e_2, ... \rangle \supsetneq \langle e_2, e_3, ... \rangle \supsetneq \cdots$$

completing the proof

Example 28.1.12: Artinian Rings

1. Let $N > 1$ be an integer and $R = \mathbb{Z}/N\mathbb{Z}$. Since R is finite it is Artinian. If $N = p_1^{\alpha_1} \cdots p_r^{\alpha_r}$ for distinct primes p_i and $\alpha_i \geq 1$, then by the Chinese Remainder Theorem

   $$\mathbb{Z}/N\mathbb{Z} \cong (\mathbb{Z}/p_1^{\alpha_1}\mathbb{Z}) \times (\mathbb{Z}/p_2^{\alpha_2}\mathbb{Z}) \times \cdots \times (\mathbb{Z}/p_r^{\alpha_r}\mathbb{Z})$$

   where each $\mathbb{Z}/p_i^{\alpha_i}\mathbb{Z}$ is a local Artinian ring with maximal ideal $(p_i)/(p_i^{\alpha_i})$. The Jacobson radical of R is $(p_1 p_2 \cdots p_r)$.

2. Let R be a finite dimensional k-algebra over some field k (it need not be commutative!). Then R is an Artinian ring, since any descending chain of R is a descending chain of k-subspces of R, which is bounded by $\dim_k(R)$. Note that if R is not commutative, R is not the finite direct product of local artinian rings, but the finite product of indecomposable artinian rings (i.e. artinian rings which cannot be split into direct sum of submodules).

3. Let $k[x]$ be the polynomial ring over a field k and $f \in k[x]$ be a nonzero polynomial. Then if $f(x) = f_1^{n_1}(x) \cdots f_k^{n_k}(x)$, by the CRT we have:

$$k[x]/(f(x)) \cong k[x]/(f_1^{n_1}(x)) \times \cdots \times k[x]/(f_k^{n_k}(x))$$

which is artinian, since $k[x]/(f(x))$ is a finite dimensional k-module (each $k[x]/(f_i^{n_i}(x))$ is a local artinian ring, with maximla ideal $(f_i(x))/(f_i^{n_i}(x))$). If $n_i = 1$ for all i, $k[x]/(f(x))$ is a product of fields, and if furtheremore there was only 1 n_i (i.e. $i \in \{1\}$), then $k[x]/(f(x))$ would be a field extension

We shall give names to modules that satisfy both the Artinian and Noetherian condition:

Definition 28.1.13: Modules of Finite Length

Let M be an R-module that is Noetherian and Artinian. Then M is an R-module of *finite length*.

By proposition 23.1.8 each finite-length module has a well-defined length $\ell(M) \in \mathbb{N}$. In fact the composition factors themselves are determined:

Theorem 28.1.14: Jordan-Hölder

Let M be a module of finite length. Then any two composition series of M have the same length and the same multiset of simple quotients, up to isomorphism and reordering.

***Proof*:**
Length invariance is proposition 23.1.8. Induct on $\ell(M)$ for the factors: given two composition series with maximal submodules M_1, M_1', either $M_1 = M_1'$ (apply the inductive hypothesis to M_1), or $M_1 + M_1' = M$, whence $M/M_1 \cong M_1'/(M_1 \cap M_1')$ and $M/M_1' \cong M_1/(M_1 \cap M_1')$; inserting a composition series of $M_1 \cap M_1'$ into each shows the two factor multisets agree.

Example 28.1.15: Module of Finite Length
The simplest example would be when $R = k$ is a field, which gives vector-spaces. In this case, for any V

$$\ell(V) = \dim_k(V)$$

Proposition 28.1.16: Finite Length Additive Under Extensions

Let

$$0 \to M' \to M \to M'' \to 0$$

Be a short exact sequence of finite length modules. Then:

$$\ell(M) = \ell(M') + \ell(M'')$$

***Proof*:**
Concatenating a composition series $0 = M'_0 \subsetneq \cdots \subsetneq M'_{\ell(M')} = M'$ of M' with the preimage in M of a composition series of $M'' = M/M'$ yields a composition series of M of length $\ell(M') + \ell(M'')$; by invariance of length (proposition 23.1.8) this is $\ell(M)$.

For a finite-length module the length is computed locally, and the module splits as a direct sum over its (finitely many, maximal) associated points.

Proposition 28.1.17: Length, Support, and Local Decomposition

Let M be a finite-length R-module. Then $\operatorname{Supp}(M)$ is a finite set of maximal ideals, the natural map $M \to \bigoplus_{\mathfrak{m}\in\operatorname{Supp}(M)} M_{\mathfrak{m}}$ is an isomorphism, and

$$\ell_R(M) = \sum_{\mathfrak{m}\in\operatorname{Supp}(M)} \ell_{R_{\mathfrak{m}}}(M_{\mathfrak{m}})$$

***Proof*:**
A composition series of M has simple factors $R/\mathfrak{m}_i$ with the $\mathfrak{m}_i$ maximal, so $\operatorname{Supp}(M) = \{\mathfrak{m}_i\}$ is a finite set of maximal ideals and some product $\mathfrak{m}_1^{a_1}\cdots\mathfrak{m}_r^{a_r}$ annihilates M. Thus M is a module over the Artinian ring $R/\operatorname{Ann}(M) \cong \prod_i R/\mathfrak{m}_i^{a_i}$, which gives the direct-sum decomposition $M \cong \bigoplus_i M_{\mathfrak{m}_i}$. Localizing a composition series at $\mathfrak{m}$ deletes the factors $R/\mathfrak{m}'$ with $\mathfrak{m}' \neq \mathfrak{m}$ and preserves those with $\mathfrak{m}' = \mathfrak{m}$, so $\ell_{R_{\mathfrak{m}}}(M_{\mathfrak{m}})$ counts the factors isomorphic to $R/\mathfrak{m}$; summing over $\mathfrak{m}$ gives $\ell_R(M)$.

Proposition 28.1.18: Length Along a Flat Local Homomorphism

Let $\varphi\colon (A,\mathfrak{m}) \to (B,\mathfrak{n})$ be a flat local homomorphism of Noetherian local rings whose closed fibre $B/\mathfrak{m}B$ has finite length over B, and let M be an A-module of finite length. Then $M \otimes_A B$ has finite length over B, and

$$\ell_B(M \otimes_A B) \;=\; \ell_A(M)\cdot \ell_B(B/\mathfrak{m}B)$$

In particular, if A is Artinian then $\ell_B(B) = \ell_A(A)\cdot\ell_B(B/\mathfrak{m}B)$.

***Proof*:**
Induct on $n = \ell_A(M)$. If $n = 0$ then $M = 0$ and both sides vanish. If $n = 1$ then M is simple, so $M \cong A/\mathfrak{m}$ because A is local, and $M \otimes_A B \cong B/\mathfrak{m}B$, whose length is $\ell_B(B/\mathfrak{m}B)$ by hypothesis; this is the claimed product since $\ell_A(M) = 1$.

For $n > 1$, choose a submodule $M' \subseteq M$ with $\ell_A(M') = n-1$ and $M/M' \cong A/\mathfrak{m}$, which exists by taking a composition series. Tensoring

$$0 \to M' \to M \to A/\mathfrak{m} \to 0$$

with B over A leaves it exact, since B is flat over A. Length is additive on short exact sequences (proposition 28.1.16), so

$$\ell_B(M \otimes_A B) = \ell_B(M' \otimes_A B) + \ell_B(B/\mathfrak{m}B) = (n-1)\ell_B(B/\mathfrak{m}B) + \ell_B(B/\mathfrak{m}B)$$

using the inductive hypothesis, and the right side is $n \cdot \ell_B(B/\mathfrak{m}B)$, as we sought to show.

The multiplicativity is the algebraic content behind the geometric statement that a flat morphism pulls the fundamental cycle of the base back to the fundamental cycle of the total space: the multiplicity with which a component occurs is multiplied by the length of the fibre, uniformly.

Proposition 28.1.19: Finiteness over an Artinian Ring

Let R be an Artinian ring and M an R-module. Then M is finitely generated iff it has finite length iff it is Noetherian iff it is Artinian. In particular R has finite length over itself.

***Proof*:**
Finite length trivially implies the other three. If M is finitely generated it is a quotient of some R^n; since R has finite length over itself (its composition series comes from the filtration by the $\mathfrak{m}_i^j$), so do R^n and its quotient M. A Noetherian module is finitely generated, hence of finite length by the above. An Artinian module M over the Artinian R also has finite length: with $J = \mathrm{Jac}(R)$ and $J^k = 0$, the filtration $M \supseteq JM \supseteq \cdots \supseteq J^k M = 0$ has each piece $J^i M/J^{i+1}M$ a module over the product of fields R/J satisfying the D.C.C., hence a finite direct sum of simple modules.

Exercise 28.1.1

1. Let M be a Noetherian and Artinian A-module, $\varphi : M \to M$ an A-module homomorphism. Show that there exists an $n \geq 0$ such that $M = \ker(\varphi^n) \oplus \mathrm{im}(\varphi^n)$.
2. Let M be an R-module. Then M is of finite length iff it has a composition series.

29

Dimension Theory

How large is a ring? For the coordinate ring of a variety the answer should be the variety's dimension, and the algebra offers three ways to measure it, each capturing a different intuition. One counts how many independent parameters the ring carries: the length of the longest chain of prime ideals, since primes correspond to irreducible closed subsets and a chain of them is a tower of nested subvarieties. A second counts how many equations it takes to cut the ring down to something finite: a zero-dimensional, Artinian quotient. A third reads the dimension off a growth rate, the rate at which $R/\mathfrak{m}^n$ grows with n. The central result of the chapter, the *dimension theorem*, is that these three numbers coincide. It is the payoff of the finiteness and locality threads: the Noetherian hypothesis makes the growth rate polynomial, localization concentrates the question at a single prime, and Noether normalization ties the whole theory back to the transparent case of a polynomial ring.

The geometric cash-out (that the Krull dimension of a coordinate ring is the topological dimension of its variety, that a hypersurface drops dimension by one) is developed in [42], which cites this chapter for the ring theory.

29.1 Noether Normalization

The theory rests on the fact that a finitely generated algebra over a field is only finitely far from a polynomial ring.

Theorem 29.1.1: Noether Normalization

Let k be a field and $A = k[r_1, \dots, r_n]$ a finitely generated k-algebra. Then there are elements $y_1, \dots, y_q \in A$, algebraically independent over k, such that A is a finite (module-finite) extension of $k[y_1, \dots, y_q]$.

***Proof*:**
Induct on n, the number of generators. If $r_1, \dots, r_n$ are algebraically independent, take $y_i = r_i$ and $A = k[y_1, \dots, y_n]$. Otherwise a nonzero $f \in k[x_1, \dots, x_n]$ satisfies $f(r_1, \dots, r_n) = 0$; let d exceed every exponent appearing in f, and set

$$x_i' = x_i - x_n^{d^i} \quad (1 \le i \le n-1)$$

Rewriting f in the variables $x_1', \dots, x_{n-1}', x_n$, each monomial $x_1^{a_1} \cdots x_n^{a_n}$ of f contributes a top x_n-power $x_n^{a_1 d + a_2 d^2 + \cdots + a_{n-1} d^{n-1} + a_n}$; base-$d$ uniqueness makes these exponents distinct across monomials, so f becomes, up to a nonzero scalar from k, monic in x_n of some degree N with coefficients in $k[x_1', \dots, x_{n-1}']$. Putting $s_i = r_i - r_n^{d^i}$, the relation $f(r_1, \dots, r_n) = 0$ exhibits r_n as a root of a monic polynomial over $B = k[s_1, \dots, s_{n-1}]$, so r_n is integral over B; each $r_i = s_i + r_n^{d^i}$ is then integral over $B[r_n]$, and by transitivity A is integral, hence (being finitely generated) module-finite, over B. As B is generated by $n-1$ elements, induction gives a polynomial subalgebra $k[y_1, \dots, y_q] \subseteq B$ over which B, and therefore A, is module-finite.

The number q is an invariant: it equals the transcendence degree of A over k when A is a domain, as theorem 29.6.3 will record once dimension is in hand.

29.2 Krull Dimension

Definition 29.2.1: Krull Dimension and Height

The *height* of a prime $\mathfrak{p}$, written $\operatorname{ht}\mathfrak{p}$, is the supremum of lengths r of chains $\mathfrak{p}_0 \subsetneq \mathfrak{p}_1 \subsetneq \cdots \subsetneq \mathfrak{p}_r = \mathfrak{p}$ of primes descending from $\mathfrak{p}$. The *Krull dimension* $\dim R$ is the supremum of $\operatorname{ht}\mathfrak{p}$ over all primes $\mathfrak{p}$, equivalently the supremum of lengths of chains of primes in R.

A field has dimension 0; a principal ideal domain that is not a field has dimension 1, its chains being $0 \subsetneq (\pi)$ for irreducible π. For a local ring $(R, \mathfrak{m})$ the dimension is $\operatorname{ht}\mathfrak{m}$, since $\mathfrak{m}$ contains every prime. The chain $0 \subsetneq (x_1) \subsetneq (x_1, x_2) \subsetneq \cdots \subsetneq (x_1, \dots, x_n)$ in $k[x_1, \dots, x_n]$ shows $\dim k[x_1, \dots, x_n] \ge n$; equality is theorem 29.6.3.

Dimension is controlled locally: $\dim R = \sup_{\mathfrak{m}} \dim R_{\mathfrak{m}}$ over maximal ideals, because a chain of primes below $\mathfrak{p}$ survives in $R_{\mathfrak{p}}$. The substance of the theory is therefore the local case, to which the next two sections are devoted.

29.3 The Hilbert-Samuel Function

Throughout this section $(R, \mathfrak{m})$ is a Noetherian local ring and $\mathfrak{q}$ an $\mathfrak{m}$-*primary* ideal, so that $\mathfrak{m}^r \subseteq \mathfrak{q} \subseteq \mathfrak{m}$ for some r and $R/\mathfrak{q}$ is Artinian. We measure R through the lengths $\ell(R/\mathfrak{q}^n)$. The tool is the associated graded ring $\operatorname{gr}_{\mathfrak{q}} R = \bigoplus_{n \ge 0} \mathfrak{q}^n/\mathfrak{q}^{n+1}$, a Noetherian graded ring, finitely generated over the Artinian ring $R/\mathfrak{q}$ by the finitely many degree-one elements $\mathfrak{q}/\mathfrak{q}^2$.

Lemma 29.3.1: Hilbert Polynomial of a Graded Module

Let $S = S_0[t_1, \dots, t_s]$ be a graded ring, finitely generated over an Artinian ring S_0 by degree-one elements t_i, and $N = \bigoplus_n N_n$ a finitely generated graded S-module. Then $\ell(N_n)$ is finite for each n and agrees, for $n \gg 0$, with a polynomial in n of degree $\leq s-1$ (rational coefficients).

***Proof*:**
Each N_n is a finitely generated S_0-module, hence of finite length. Induct on s. If $s = 0$ then $S = S_0$ and N, being finitely generated, is concentrated in finitely many degrees, so $\ell(N_n) = 0$ for $n \gg 0$ (a polynomial of degree ≤ -1). For the step, multiplication by t_s gives an exact sequence of $S_0[t_1, \dots, t_{s-1}]$-modules in each degree,

$$0 \to K_n \to N_n \xrightarrow{t_s} N_{n+1} \to (N/t_sN)_{n+1} \to 0,$$

where $K = (0 :_N t_s)$ and N/t_sN are finitely generated and killed by t_s, hence graded modules over $S_0[t_1, \dots, t_{s-1}]$. Additivity of length gives $\ell(N_{n+1}) - \ell(N_n) = \ell\big((N/t_sN)_{n+1}\big) - \ell(K_n)$, which by induction agrees with a polynomial of degree $\leq s-2$ for $n \gg 0$. A function whose first difference is eventually a polynomial of degree $\leq s-2$ is itself eventually a polynomial of degree $\leq s-1$.

Proposition 29.3.2: The Hilbert-Samuel Polynomial

For a finitely generated R-module M, the *characteristic function* $\chi_{\mathfrak{q}}^M(n) = \ell(M/\mathfrak{q}^n M)$ agrees for $n \gg 0$ with a polynomial in n of degree $\leq s$, where s is the least number of generators of $\mathfrak{q}$. Moreover $\deg \chi_{\mathfrak{q}}^M = \deg \chi_{\mathfrak{m}}^M$, so the degree is independent of the $\mathfrak{m}$-primary ideal $\mathfrak{q}$.

***Proof*:**
The associated graded module $\operatorname{gr}(M) = \bigoplus_n \mathfrak{q}^n M/\mathfrak{q}^{n+1}M$ is a finitely generated graded module over $\operatorname{gr}_{\mathfrak{q}} R$, itself generated over the Artinian ring $R/\mathfrak{q}$ by the s degree-one generators of $\mathfrak{q}/\mathfrak{q}^2$. By lemma 29.3.1, $\ell(\mathfrak{q}^n M/\mathfrak{q}^{n+1}M)$ is eventually a polynomial of degree $\leq s-1$. Since $\chi_{\mathfrak{q}}^M(n) = \ell(M/\mathfrak{q}^n M) = \sum_{r=0}^{n-1} \ell(\mathfrak{q}^r M/\mathfrak{q}^{r+1}M)$, summing raises the degree by one: $\chi_{\mathfrak{q}}^M$ is eventually a polynomial of degree $\leq s$. For the last claim, $\mathfrak{m}^r \subseteq \mathfrak{q} \subseteq \mathfrak{m}$ gives $\mathfrak{m}^{rn} \subseteq \mathfrak{q}^n \subseteq \mathfrak{m}^n$, hence $\chi_{\mathfrak{m}}^M(n) \leq \chi_{\mathfrak{q}}^M(n) \leq \chi_{\mathfrak{m}}^M(rn)$ for all n; the outer terms are polynomials of equal degree, so the middle one shares it.

Write $d(M) = \deg \chi_{\mathfrak{m}}^M(n)$ and $d(R) = \deg \chi_{\mathfrak{m}}(n)$ where $\chi_{\mathfrak{m}}(n) = \ell(R/\mathfrak{m}^n)$. The next proposition is the inductive engine.

Proposition 29.3.3: Dropping the Degree by a Non-Zero-Divisor

If $x \in \mathfrak{m}$ is not a zero-divisor on M, then $d(M/xM) \leq d(M) - 1$.

***Proof*:**
Set $M' = M/xM$. Additivity of length in $0 \to (xM + \mathfrak{q}^n M)/\mathfrak{q}^n M \to M/\mathfrak{q}^n M \to M'/\mathfrak{q}^n M' \to 0$ gives $\chi_{\mathfrak{q}}^{M'}(n) = \chi_{\mathfrak{q}}^{M}(n) - g(n)$, where $g(n) = \ell\big(xM/(xM \cap \mathfrak{q}^n M)\big)$. As x is a non-zero-divisor, $M \xrightarrow{x} xM$ is an isomorphism carrying $\mathfrak{q}^n M$ onto $\mathfrak{q}^n(xM)$, so $\ell(xM/\mathfrak{q}^n(xM)) = \chi_{\mathfrak{q}}^{M}(n)$. Now $\mathfrak{q}^n(xM) \subseteq xM \cap \mathfrak{q}^n M$, and by the Artin-Rees lemma (theorem 25.4.1) the filtration $\{xM \cap \mathfrak{q}^n M\}$ is $\mathfrak{q}$-stable, so $xM \cap \mathfrak{q}^n M \subseteq \mathfrak{q}^{n-c}(xM)$ for some c and all $n \geq c$. Taking lengths,

$$\chi_{\mathfrak{q}}^{M}(n-c) \leq g(n) \leq \chi_{\mathfrak{q}}^{M}(n)$$

Both bounds are $\chi_{\mathfrak{q}}^{M}$ evaluated at $n-c$ and n, so g agrees for large n with a polynomial of degree $d(M)$ and the same leading coefficient as $\chi_{\mathfrak{q}}^{M}$. Hence $\chi_{\mathfrak{q}}^{M'} = \chi_{\mathfrak{q}}^{M} - g$ has degree $\leq d(M) - 1$.

29.4 The Dimension Theorem

Theorem 29.4.1: Dimension Theorem

For a Noetherian local ring $(R, \mathfrak{m})$ the following three numbers coincide:

$$d(R) = \delta(R) = \dim R,$$

where $d(R) = \deg \ell(R/\mathfrak{m}^n)$, and $\delta(R)$ is the least number of generators of an $\mathfrak{m}$-primary ideal.

***Proof*:**
We show $d(R) \leq \delta(R) \leq \dim R \leq d(R)$.

$d(R) \leq \delta(R)$. If $\mathfrak{q}$ is $\mathfrak{m}$-primary and generated by $s = \delta(R)$ elements, then $\deg \chi_{\mathfrak{q}} \leq s$ by proposition 29.3.2, and $\deg \chi_{\mathfrak{q}} = \deg \chi_{\mathfrak{m}} = d(R)$; so $d(R) \leq \delta(R)$.

$\dim R \leq d(R)$. Induct on $d(R)$. If $d(R) = 0$ then $\ell(R/\mathfrak{m}^n)$ is eventually constant, so $\mathfrak{m}^n = \mathfrak{m}^{n+1}$ for some n; Nakayama's lemma (lemma 23.4.27) gives $\mathfrak{m}^n = 0$, so R is Artinian and $\dim R = 0$. Suppose $d(R) = d > 0$ and let $\mathfrak{p}_0 \subsetneq \cdots \subsetneq \mathfrak{p}_r$ be a chain of primes; we bound r. We may take $\mathfrak{p}_0$ minimal, and choosing $x \in \mathfrak{p}_1 \setminus \mathfrak{p}_0$, the ring $\bar{R} = R/\mathfrak{p}_0$ is a domain in which x is a nonzero, hence non-zero-divisor, element. By proposition 29.3.3, $d(\bar{R}/x\bar{R}) \leq d(\bar{R}) - 1 \leq d(R) - 1$ (the last as $\bar{R}$ is a quotient of R, whose characteristic polynomial dominates). The chain $\mathfrak{p}_1 \subsetneq \cdots \subsetneq \mathfrak{p}_r$ descends to a chain of length $r-1$ in $\bar{R}/x\bar{R}$, so by induction $r - 1 \leq d(R) - 1$, i.e. $r \leq d(R)$. Hence $\dim R \leq d(R)$.

$\delta(R) \leq \dim R$. Let $d = \dim R$; we build an $\mathfrak{m}$-primary ideal from d elements. Choose $x_1, \ldots, x_d \in \mathfrak{m}$ so that x_i lies in no minimal prime of $(x_1, \ldots, x_{i-1})$; this is possible by prime avoidance, as there are only finitely many such minimal primes (corollary 24.4.3), unless one of them is $\mathfrak{m}$ itself, in which case $(x_1, \ldots, x_{i-1})$ is already $\mathfrak{m}$-primary and fewer elements suffice. An induction then shows every prime $\mathfrak{p} \supseteq (x_1, \ldots, x_i)$ has $\operatorname{ht} \mathfrak{p} \geq i$: such $\mathfrak{p}$ contains a minimal prime $\mathfrak{p}'$ of $(x_1, \ldots, x_{i-1})$, which has $\operatorname{ht} \mathfrak{p}' \geq i - 1$ by induction, and $\mathfrak{p} \neq \mathfrak{p}'$ because $x_i \in \mathfrak{p} \setminus \mathfrak{p}'$, so $\operatorname{ht} \mathfrak{p} \geq \operatorname{ht} \mathfrak{p}' + 1 \geq i$. At $i = d$ every prime over $(x_1, \ldots, x_d)$ has height $\geq d = \operatorname{ht} \mathfrak{m}$; since $\mathfrak{m}$ is the only prime of that height in the local ring R, the ideal $(x_1, \ldots, x_d)$ is $\mathfrak{m}$-primary. Thus $\delta(R) \leq d$.

Corollary 29.4.2: Completion Preserves Dimension

Let $(R, \mathfrak{m})$ be a Noetherian local ring with $\mathfrak{m}$-adic completion $\hat{R}$. Then $\dim \hat{R} = \dim R$.

***Proof*:**
The ring $\hat{R}$ is Noetherian by theorem 25.5.7. Write $\hat{\mathfrak{m}}$ for the completion of $\mathfrak{m}$. By corollary 25.1.5, applied to R with the subgroups $\mathfrak{m}^k$, the map $R \to \hat{R}$ induces isomorphisms $R/\mathfrak{m}^n \cong \hat{R}/\widehat{\mathfrak{m}^n}$, and $\widehat{\mathfrak{m}^n} = \hat{\mathfrak{m}}^n$ by proposition 25.4.7(2). These maps are ring isomorphisms, so ideals correspond and $\ell(\hat{R}/\hat{\mathfrak{m}}^n) = \ell(R/\mathfrak{m}^n)$ for every n. The ring $\hat{R}$ is local by lemma 25.1.7, and its maximal ideal is $\hat{\mathfrak{m}}$, the kernel of the surjection $\hat{R} \to R/\mathfrak{m}$ onto a field (the case $n = 1$). So $(\hat{R}, \hat{\mathfrak{m}})$ is a Noetherian local ring, and theorem 29.4.1 for R and for $\hat{R}$ gives $\dim R = d(R) = d(\hat{R}) = \dim \hat{R}$, as claimed.

Krull's height theorem (theorem 29.5.2) is also a corollary of the dimension theorem, with no circularity: its proof invokes only the equalities just established.

29.5 Systems of Parameters and Krull's Principal Ideal Theorem

Definition 29.5.1: System of Parameters

A *system of parameters* for a Noetherian local ring $(R, \mathfrak{m})$ of dimension d is a set of d elements generating an $\mathfrak{m}$-primary ideal. The dimension theorem guarantees one exists, and d is the least possible number of such generators.

Theorem 29.5.2: Krull's Height Theorem

Let R be Noetherian and $\mathfrak{a} = (x_1, \dots, x_c)$ generated by c elements. Then every prime $\mathfrak{p}$ minimal over $\mathfrak{a}$ has $\operatorname{ht} \mathfrak{p} \le c$. In particular (the *Hauptidealsatz*, $c = 1$) a prime minimal over a single nonunit x has height at most 1.

***Proof*:**
Localizing at $\mathfrak{p}$, we may assume $(R, \mathfrak{p})$ is local and $\mathfrak{p}$ is minimal over $\mathfrak{a}$, so that $\mathfrak{a}$ is $\mathfrak{p}$-primary and $\operatorname{ht} \mathfrak{p} = \dim R$. Then $\mathfrak{a}$ is an $\mathfrak{p}$-primary ideal with c generators, so $\dim R = \delta(R) \le c$ by the inequality $\dim R \le d(R) \le \delta(R)$ established in theorem 29.4.1; here only $\dim R \le d(R)$ and $d(R) \le \delta(R)$ are used, and $\delta(R) \le c$ because $\mathfrak{a}$ itself is $\mathfrak{p}$-primary with c generators.

A converse rounds out the picture: in a Noetherian ring a prime of height c is minimal over some ideal generated by c elements, so height is exactly the least number of generators needed to cut out a prime as a component. The Hauptidealsatz is the algebraic form of the geometric principle that one equation cuts dimension by one.

Corollary 29.5.3: One Equation Cuts Dimension by One

Let R be a Noetherian *local* ring and $x \in R$ a non-unit nonzerodivisor. Then

$$\dim R/(x) \;=\; \dim R - 1$$

***Proof*:**
The inequality $\geq$ is theorem 29.5.2: if $\dim R/(x) = e$, lift a system of parameters to $y_1, \dots, y_e \in R$, so that the maximal ideal is minimal over the $(e+1)$-generated ideal $(x, y_1, \dots, y_e)$ and $\dim R = \operatorname{ht} \mathfrak{m} \leq e+1$. The inequality $\leq$ is proposition 29.3.3, x lying in no minimal prime because it is a nonzerodivisor.

Locality is not decorative. In $R = k[u,v] \times k[t]$ the element $x = (1, t)$ is a non-unit nonzerodivisor, yet $\dim R/(x) = 0$ while $\dim R = 2$: the equation cuts one component away entirely instead of cutting each component down by one.

29.6 Dimension and Transcendence Degree

Noether normalization now identifies the dimension of a geometric ring with a transcendence degree, and pins down the dimension of affine space. The engine is that a proper prime quotient of a finitely generated domain loses transcendence degree.

Lemma 29.6.1: Transcendence Degree Drops on a Prime Quotient

Let A be a finitely generated domain over a field k and $\mathfrak{p} \neq 0$ a prime of A. Then $\operatorname{trdeg}_k \operatorname{Frac}(A/\mathfrak{p}) < \operatorname{trdeg}_k \operatorname{Frac}(A)$.

***Proof*:**
Throughout, transcendence bases and the transcendence degree of a field extension are those of *Core Algebra*,[a] where in particular the degree is shown to be well-defined.

Put $d = \operatorname{trdeg}_k A$ and $e = \operatorname{trdeg}_k A/\mathfrak{p} \leq d$, and suppose $e = d$. Choose $x_1, \dots, x_d \in A$ whose images in $A/\mathfrak{p}$ form a transcendence basis; they are algebraically independent in A, hence (as $d = \operatorname{trdeg} A$) a transcendence basis of A as well, so every element of A is algebraic over $B = k[x_1, \dots, x_d]$. Pick $0 \neq a \in \mathfrak{p}$. An algebraic relation for a over $\operatorname{Frac}(B)$, cleared of denominators and divided by the largest power of a that factors out (valid as A is a domain), becomes $c_0 + c_1 a + \cdots + c_m a^m = 0$ with $c_i \in B$ and $c_0 \neq 0$; then $c_0 = -a(c_1 + \cdots + c_m a^{m-1}) \in \mathfrak{p}$. But $\mathfrak{p} \cap B = 0$, since a nonzero element of $\mathfrak{p} \cap B$ would be a nontrivial algebraic relation among the algebraically independent images $\bar{x}_i$ in $A/\mathfrak{p}$. This contradicts $c_0 \neq 0$, so $e < d$.

[a] theorem 19.2.15.

Lemma 29.6.2: Integral Extensions Preserve Dimension

Let S be an integral extension of an integral domain R. Then $\dim S = \dim R$.

***Proof*:**
A chain $P_0 \subsetneq \cdots \subsetneq P_r$ of primes of S contracts to a chain $P_0 \cap R \subseteq \cdots \subseteq P_r \cap R$ of primes of R. The inclusions stay strict, because two distinct comparable primes of S cannot lie over the same prime, by incomparability (theorem 26.3.3(4)). Hence $\dim R \geq \dim S$. Conversely, let $\mathfrak{p}_0 \subsetneq \cdots \subsetneq \mathfrak{p}_r$ be a chain of primes of R. Lying over (theorem 26.3.3(1)) gives a prime P_0 of S with $P_0 \cap R = \mathfrak{p}_0$, and going up (theorem 26.3.3(2)) extends it to a chain $P_0 \subsetneq \cdots \subsetneq P_r$ with $P_i \cap R = \mathfrak{p}_i$ for all i. The P_i are distinct because their contractions are, so $\dim S \geq r$, and $\dim S \geq \dim R$.

Theorem 29.6.3: Dimension of Finitely Generated Algebras

Let A be a finitely generated algebra over a field k that is a domain. Then

$$\dim A = \operatorname{trdeg}_k \operatorname{Frac}(A),$$

and in particular $\dim k[x_1, \ldots, x_n] = n$. More generally the number q in Noether normalization (theorem 29.1.1) equals $\dim A$.

***Proof*:**
By theorem 29.1.1, A is module-finite, hence integral, over a polynomial subalgebra $k[y_1, \ldots, y_q]$ with the y_i algebraically independent, so $q = \operatorname{trdeg}_k \operatorname{Frac}(A)$; integral extensions preserve Krull dimension (lemma 29.6.2), so $\dim A = \dim k[y_1, \ldots, y_q]$. We prove the general claim $\dim B \leq \operatorname{trdeg}_k \operatorname{Frac}(B)$ for every finitely generated domain B over k, by induction on transcendence degree. Given a chain $0 = \mathfrak{p}_0 \subsetneq \mathfrak{p}_1 \subsetneq \cdots \subsetneq \mathfrak{p}_r$ in B, the tail descends to a chain of length $r-1$ in the finitely generated domain $B/\mathfrak{p}_1$, whose transcendence degree is at most $\operatorname{trdeg} B - 1$ by lemma 29.6.1; induction gives $r - 1 \leq \operatorname{trdeg} B - 1$, so $r \leq \operatorname{trdeg} B$. Applied to $B = k[y_1, \ldots, y_q]$ this yields $\dim k[y_1, \ldots, y_q] \leq q$, while the chain of definition 29.2.1 gives $\geq q$. Hence $\dim A = \dim k[y_1, \ldots, y_q] = q = \operatorname{trdeg}_k \operatorname{Frac}(A)$.

The equality $\dim A = \operatorname{trdeg}_k \operatorname{Frac}(A)$ is the algebraic form of the statement that dimension counts independent coordinates; in [42] it becomes the assertion that the dimension of an irreducible affine variety is the transcendence degree of its function field.

29.7 Catenary Rings and the Height Formula

Let A be the coordinate ring of an irreducible affine variety X, a finitely generated domain over a field, and let $\mathfrak{p}$ be the prime of an irreducible closed subset Y. Chains of primes descending from $\mathfrak{p}$ are towers of irreducible closed sets rising from Y, so $\operatorname{ht} \mathfrak{p}$ is the codimension of Y in X, while $\dim A/\mathfrak{p}$ is the dimension of Y. The two numbers add up to $\dim A$ (theorem 29.7.3). For a general Noetherian domain the sum can fall short (example 29.7.4).

Definition 29.7.1: Saturated Chains and Catenary Rings

A chain of primes $\mathfrak{p}_0 \subsetneq \mathfrak{p}_1 \subsetneq \cdots \subsetneq \mathfrak{p}_r$ in a ring R is *saturated* if for each i no prime lies strictly between $\mathfrak{p}_{i-1}$ and $\mathfrak{p}_i$. It is a *maximal chain* if moreover $\mathfrak{p}_0$ is a minimal prime of R and $\mathfrak{p}_r$ is a maximal ideal, so that no prime can be inserted anywhere in it. The ring R is *catenary* if for every pair of primes $\mathfrak{q} \subseteq \mathfrak{p}$ of R, the height of $\mathfrak{p}/\mathfrak{q}$ in $R/\mathfrak{q}$, which is the supremum of the lengths of chains of primes from $\mathfrak{q}$ to $\mathfrak{p}$, is finite and is the length of every saturated chain of primes from $\mathfrak{q}$ to $\mathfrak{p}$.

Lemma 29.7.2: Height over a Normal Base

Let S be a domain that is an integral extension of a normal domain R, and let P be a prime of S. Then $\operatorname{ht} P = \operatorname{ht}(P \cap R)$.

***Proof*:**
Put $\mathfrak{p} = P \cap R$. A chain $P_0 \subsetneq \cdots \subsetneq P_h = P$ contracts to a chain $P_0 \cap R \subseteq \cdots \subseteq P_h \cap R = \mathfrak{p}$, with strict inclusions by incomparability (theorem 26.3.3(4)), so $\operatorname{ht}\mathfrak{p} \geq \operatorname{ht} P$. Conversely, let $\mathfrak{p}_0 \subsetneq \cdots \subsetneq \mathfrak{p}_h = \mathfrak{p}$ be a chain of primes of R. Going down (theorem 26.3.3(3)) applies, as R is normal and S is a domain. Applied to the descending chain $\mathfrak{p}_h \supseteq \cdots \supseteq \mathfrak{p}_0$ and the prime P over $\mathfrak{p}_h$, it gives primes $P = P_h \supseteq P_{h-1} \supseteq \cdots \supseteq P_0$ of S with $P_i \cap R = \mathfrak{p}_i$. These primes are distinct because their contractions are, so $\operatorname{ht} P \geq h$, and $\operatorname{ht} P \geq \operatorname{ht}\mathfrak{p}$.

Theorem 29.7.3: The Height Formula for Finitely Generated Domains

Let A be a finitely generated algebra over a field k that is a domain, and put $n = \dim A$.

1. Every maximal chain of primes in A has length n.
2. For every prime $\mathfrak{p}$ of A,

$$\operatorname{ht}\mathfrak{p} + \dim A/\mathfrak{p} = \dim A = \operatorname{trdeg}_k \operatorname{Frac}(A)$$

***Proof*:**
The number n is finite and equals $\operatorname{trdeg}_k \operatorname{Frac}(A)$ by theorem 29.6.3.

Step 1: a prime P of height one has $\dim A/P = n - 1$. By theorem 29.1.1, A is module-finite, hence integral (proposition 26.1.4), over a subring $B = k[y_1, \ldots, y_q]$ with $y_1, \ldots, y_q$ algebraically independent over k, and $q = n$ by theorem 29.6.3. The ring B is a polynomial ring in n variables over k, so it is a unique factorization domain by *Core Algebra*,[a] a field being trivially one, and a normal domain by example 26.1.9(2). As A is a domain, lemma 29.7.2 applies, and $\mathfrak{q} = P \cap B$ has height one. Pick $0 \neq a \in \mathfrak{q}$, a nonunit as $\mathfrak{q}$ is proper. Some irreducible factor f of a lies in the prime $\mathfrak{q}$, and f is prime in the unique factorization domain B by *Core Algebra*.[b] So $0 \subsetneq (f) \subseteq \mathfrak{q}$ is a chain of primes, and $\operatorname{ht}\mathfrak{q} = 1$ forces $\mathfrak{q} = (f)$. Being irreducible, f is a nonconstant polynomial.

The composite $B \to A \to A/P$ has kernel $\mathfrak{q}$, so $B/\mathfrak{q}$ embeds in A/P. Reducing an integral equation over B modulo P gives one over $B/\mathfrak{q}$, so A/P is an integral extension of the do-

main $B/\mathfrak{q}$, and lemma 29.6.2 gives $\dim A/P = \dim B/(f)$. Renumber so that y_n occurs in f. The images $\bar{y}_1, \ldots, \bar{y}_{n-1}$ in $B/(f)$ are algebraically independent over k, since a nonzero $g \in k[y_1, \ldots, y_{n-1}]$ lying in (f) would be $g = fh$ with $h \neq 0$. The y_n-degree is additive on products in $k[y_1, \ldots, y_{n-1}][y_n]$, as $k[y_1, \ldots, y_{n-1}]$ is a domain, so g would have y_n-degree at least that of f, which is positive, although g does not involve y_n. Hence $\operatorname{trdeg}_k \operatorname{Frac}(B/(f)) \geq n-1$. Since $\operatorname{trdeg}_k \operatorname{Frac}(B) = n$ and $(f) \neq 0$, lemma 29.6.1 gives the reverse inequality. By theorem 29.6.3, applied to the finitely generated domain $B/(f)$, we conclude $\dim A/P = \dim B/(f) = n-1$.

Step 2: proof of (1). Induct on n. Let $\mathfrak{p}_0 \subsetneq \cdots \subsetneq \mathfrak{p}_r$ be a maximal chain. The zero ideal of the domain A is a prime contained in $\mathfrak{p}_0$, so minimality of $\mathfrak{p}_0$ gives $\mathfrak{p}_0 = 0$. If $n = 0$, there is no chain $0 \subsetneq \mathfrak{p}$, so $r = 0$. Let $n \geq 1$. Then 0 is not a maximal ideal, and $\mathfrak{p}_r$ is one, so $r \geq 1$. No prime lies strictly between 0 and $\mathfrak{p}_1$, so every chain of primes descending from $\mathfrak{p}_1$ has length at most one, and $\operatorname{ht} \mathfrak{p}_1 = 1$. By Step 1, $A/\mathfrak{p}_1$ is a finitely generated domain over k of dimension $n-1$. Its primes are the $\mathfrak{p}/\mathfrak{p}_1$ for primes $\mathfrak{p} \supseteq \mathfrak{p}_1$ of A, with inclusions preserved (proposition 26.2.4). So $\mathfrak{p}_1/\mathfrak{p}_1 \subsetneq \cdots \subsetneq \mathfrak{p}_r/\mathfrak{p}_1$ is a maximal chain of $A/\mathfrak{p}_1$: it starts at the zero ideal of the domain $A/\mathfrak{p}_1$, admits no prime between consecutive terms, and ends at a maximal ideal. By induction $r - 1 = n - 1$, so $r = n$.

Step 3: proof of (2). Let $h = \operatorname{ht} \mathfrak{p}$ and $e = \dim A/\mathfrak{p}$. Both are at most n, since a chain descending from $\mathfrak{p}$ is a chain in A, and a chain in $A/\mathfrak{p}$ is the image of a chain in A ascending from $\mathfrak{p}$ (proposition 26.2.4). Choose a chain $\mathfrak{p}_0 \subsetneq \cdots \subsetneq \mathfrak{p}_h = \mathfrak{p}$ and, lifting a chain of length e in $A/\mathfrak{p}$, a chain $\mathfrak{p} = \mathfrak{p}_h \subsetneq \cdots \subsetneq \mathfrak{p}_{h+e}$. Together they form a maximal chain of A of length $h + e$. A prime properly contained in $\mathfrak{p}_0$, or one inserted below $\mathfrak{p}$, would give a chain of length $h+1$ descending from $\mathfrak{p}$. A prime inserted above $\mathfrak{p}$, or one properly containing $\mathfrak{p}_{h+e}$, would give a chain of length $e+1$ in $A/\mathfrak{p}$. By (1), $h + e = n$.

[a] corollary 11.2.4.
[b] proposition 10.1.29.

Example 29.7.4: The Height Formula Fails over a Discrete Valuation Ring

Let k be a field, $V = k[x]_{(x)}$ and $R = V[t]$, a Noetherian domain by proposition 23.4.5(4) and theorem 23.2.1. The quotients $R/(x) \cong k[t]$ and $R/(x,t) \cong k$ are domains, so $0 \subsetneq (x) \subsetneq (x,t)$ is a chain of primes and $\dim R \geq 2$. The ideal $\mathfrak{m} = (xt - 1)$ is maximal, as $R/\mathfrak{m} \cong V[1/x] = k(x)$ is a field. Being nonzero and minimal over the principal ideal $(xt-1)$, which it equals, $\mathfrak{m}$ has height one by theorem 29.5.2. So $\operatorname{ht} \mathfrak{m} + \dim R/\mathfrak{m} = 1 < \dim R$, and the height formula fails for R, which is finitely generated over V.

Corollary 29.7.5: Finitely Generated Algebras Are Catenary

Let R be a finitely generated algebra over a field k.

1. For primes $\mathfrak{q} \subseteq \mathfrak{p}$ of R, the height of $\mathfrak{p}/\mathfrak{q}$ in $R/\mathfrak{q}$ is $\dim R/\mathfrak{q} - \dim R/\mathfrak{p}$, and every saturated chain of primes from $\mathfrak{q}$ to $\mathfrak{p}$ has this length. In particular R is catenary.
2. Every localization of R is catenary.
3. If R is a domain, then $\dim R_{\mathfrak{p}} + \dim R/\mathfrak{p} = \dim R$ for every prime $\mathfrak{p}$, and $\dim R_{\mathfrak{m}} = \dim R$ for every maximal ideal $\mathfrak{m}$.

***Proof*:**
(1) Put $A = R/\mathfrak{q}$, a finitely generated domain over k. By theorem 29.7.3(2), applied to A and its prime $\mathfrak{p}/\mathfrak{q}$, the height of $\mathfrak{p}/\mathfrak{q}$ in A is $\dim A - \dim A/(\mathfrak{p}/\mathfrak{q}) = \dim R/\mathfrak{q} - \dim R/\mathfrak{p}$. Now let $\mathfrak{q} = \mathfrak{p}_0 \subsetneq \cdots \subsetneq \mathfrak{p}_r = \mathfrak{p}$ be a saturated chain. The primes of A are the $\mathfrak{p}'/\mathfrak{q}$ for primes $\mathfrak{p}' \supseteq \mathfrak{q}$ of R, with inclusions preserved (proposition 26.2.4), so the chain becomes a saturated chain from 0 to $\mathfrak{p}/\mathfrak{q}$ in A. The ring $A/(\mathfrak{p}/\mathfrak{q}) \cong R/\mathfrak{p}$ is a finitely generated domain, so $e = \dim R/\mathfrak{p}$ is finite by theorem 29.6.3. Lift a chain of length e in $R/\mathfrak{p}$ to a chain $\mathfrak{p}/\mathfrak{q} = Q_0 \subsetneq \cdots \subsetneq Q_e$ in A. A prime inserted in it, or one properly containing Q_e, would give a chain of length $e+1$ in $R/\mathfrak{p}$. So the two chains together form a maximal chain of A: it starts at the zero ideal, a minimal prime of the domain A. By theorem 29.7.3(1), $r + e = \dim A$. Thus $r = \dim R/\mathfrak{q} - \dim R/\mathfrak{p}$ for every saturated chain from $\mathfrak{q}$ to $\mathfrak{p}$, and R is catenary.

(2) Let $D \subseteq R$ be multiplicative, and let $Q \subseteq P$ be primes of $D^{-1}R$ with contractions $\mathfrak{q} \subseteq \mathfrak{p}$ in R. By proposition 23.4.5(3), extension and contraction are mutually inverse bijections between the primes of $D^{-1}R$ and the primes of R missing D, and both preserve inclusions. Every prime between $\mathfrak{q}$ and $\mathfrak{p}$ lies in $\mathfrak{p}$ and so misses D. Hence the chains of primes from Q to P correspond to those from $\mathfrak{q}$ to $\mathfrak{p}$, with saturated chains matching. So the height of P/Q in $D^{-1}R/Q$ equals that of $\mathfrak{p}/\mathfrak{q}$ in $R/\mathfrak{q}$, which is finite, and every saturated chain from Q to P has this length by (1).

(3) The primes of $R_{\mathfrak{p}}$ correspond to the primes of R inside $\mathfrak{p}$, with inclusions preserved (proposition 23.4.5(3)), so $\dim R_{\mathfrak{p}} = \operatorname{ht} \mathfrak{p}$, and theorem 29.7.3(2) gives the first identity. For a maximal ideal $\mathfrak{m}$, the ring $R/\mathfrak{m}$ is a field, of dimension 0.

29.8 Regular Local Rings

The dimension theorem produced three numbers and showed them equal. A fourth is always available for a local ring and is never smaller: the least number of generators of the maximal ideal, which by Nakayama is the dimension of $\mathfrak{m}/\mathfrak{m}^2$ as a vector space over the residue field. Rings for which the fourth number agrees with the other three are the regular ones, and they are the subject of this section.

The inequality has a geometric reading that fixes the terminology. For a variety X and a point p, the vector space $(\mathfrak{m}_p/\mathfrak{m}_p^2)^\vee$ is the tangent space at p, so the inequality says a variety has at least as many tangent directions at a point as it has dimensions, and regularity is the case where it has

exactly as many. That reading, and the identification of regular local rings with the smooth points of a variety, is [42]; what follows is the ring theory it cites.

Corollary 29.8.1: Dimension and Embedding Dimension

Let $(R, \mathfrak{m})$ be a Noetherian local ring with residue field $k = R/\mathfrak{m}$. Then

$$\dim R \leq \dim_k \mathfrak{m}/\mathfrak{m}^2$$

***Proof*:**
Put $s = \dim_k \mathfrak{m}/\mathfrak{m}^2$ and choose $x_1, \dots, x_s \in \mathfrak{m}$ whose images form a k-basis of $\mathfrak{m}/\mathfrak{m}^2$. By Nakayama's lemma (lemma 23.4.27) they generate $\mathfrak{m}$, which is $\mathfrak{m}$-primary, so $\delta(R) \leq s$. The dimension theorem (theorem 29.4.1) gives $\dim R = \delta(R) \leq s$, as we sought to show.

The same argument identifies $\dim_k \mathfrak{m}/\mathfrak{m}^2$ with the least number of generators of $\mathfrak{m}$: Nakayama makes any lift of a basis a generating set, and no smaller set can generate, since a generating set spans $\mathfrak{m}/\mathfrak{m}^2$. This is the number called the *embedding dimension*, and corollary 29.8.1 says it bounds the dimension from above.

Definition 29.8.2: Regular Local Ring

A Noetherian local ring $(R, \mathfrak{m})$ with residue field k is *regular* if

$$\dim R = \dim_k \mathfrak{m}/\mathfrak{m}^2,$$

equivalently if $\mathfrak{m}$ can be generated by $\dim R$ elements. Such a generating set is a *regular system of parameters*: it is a system of parameters (definition 29.5.1) that generates $\mathfrak{m}$ itself rather than merely an $\mathfrak{m}$-primary ideal.

Regularity is therefore the statement that the maximal ideal is as small as the dimension permits. The next theorem replaces that numerical condition by a structural one, and the structural form is what every later argument uses: the associated graded ring, which for a general local ring records how the powers of $\mathfrak{m}$ shrink, is for a regular local ring a polynomial ring on the regular system of parameters. Following this chapter's convention it is written $\operatorname{gr}_{\mathfrak{m}} R$; it is the ring called $G_{\mathfrak{m}}(R)$ in definition 25.5.1.

Theorem 29.8.3: Characterizations of a Regular Local Ring

Let $(R, \mathfrak{m})$ be a Noetherian local ring of dimension d with residue field k. The following are equivalent.

1. R is regular.
2. $\mathfrak{m}$ is generated by d elements.
3. $\operatorname{gr}_{\mathfrak{m}} R \cong k[t_1, \dots, t_d]$ as graded k-algebras.

***Proof*:**

(1) $\iff$ (2) The least number of generators of $\mathfrak{m}$ is $\dim_k \mathfrak{m}/\mathfrak{m}^2$, as recorded after corollary 29.8.1, and that number is at least d by the same corollary. So $\mathfrak{m}$ is generated by d elements exactly when $\dim_k \mathfrak{m}/\mathfrak{m}^2 = d$, which is definition 29.8.2.

(2) $\Rightarrow$ (3) Let $x_1, \dots, x_d$ generate $\mathfrak{m}$ and let

$$\varphi\colon k[t_1, \dots, t_d] \to \operatorname{gr}_{\mathfrak{m}} R, \qquad t_i \mapsto x_i + \mathfrak{m}^2 \in \mathfrak{m}/\mathfrak{m}^2$$

be the graded k-algebra map they determine. It is surjective, because $\mathfrak{m}^n$ is generated by the degree-n monomials in the x_i, so $\mathfrak{m}^n/\mathfrak{m}^{n+1}$ is spanned over k by their classes. If $d = 0$ then $\mathfrak{m} = \mathfrak{m}^2$, Nakayama gives $\mathfrak{m} = 0$, and both sides are k; assume $d \geq 1$.

Suppose $\ker \varphi \neq 0$. The kernel of a graded map is graded, so it contains a nonzero homogeneous F of some degree e. For $n \geq e$ multiplication by F is an injection $k[t]_{n-e} \hookrightarrow k[t]_n$, the polynomial ring being a domain, and $(\operatorname{gr}_{\mathfrak{m}} R)_n$ is a quotient of $k[t]_n/F\,k[t]_{n-e}$. Hence

$$\dim_k \mathfrak{m}^n/\mathfrak{m}^{n+1} \leq \binom{n+d-1}{d-1} - \binom{n-e+d-1}{d-1}$$

Both binomials are polynomials in n of degree $d-1$ with the same leading coefficient $1/(d-1)!$, so their difference has degree at most $d-2$.

Since $R/\mathfrak{m} = k$, the length $\ell(\mathfrak{m}^r/\mathfrak{m}^{r+1})$ is its k-dimension, and

$$\ell(R/\mathfrak{m}^n) = \sum_{r=0}^{n-1} \ell(\mathfrak{m}^r/\mathfrak{m}^{r+1})$$

Summing a function that is eventually bounded by a polynomial of degree at most $d-2$ produces one eventually bounded by a polynomial of degree at most $d-1$; the finitely many terms with $r < e$ contribute a constant and do not affect the degree. So $d(R) \leq d-1$. But $d(R) = \dim R = d$ by theorem 29.4.1, a contradiction. Therefore $\ker \varphi = 0$ and φ is an isomorphism.

(3) $\Rightarrow$ (1) Comparing degree-one pieces, $\mathfrak{m}/\mathfrak{m}^2 \cong k^d$, so $\dim_k \mathfrak{m}/\mathfrak{m}^2 = d = \dim R$.

This closes the cycle, completing the proof.

Criterion (3) is the one that travels. Everything below is extracted from it by the same mechanism: a property of the polynomial ring $\operatorname{gr}_{\mathfrak{m}} R$ is transferred back to R along the filtration by powers of $\mathfrak{m}$, and the transfer works because Krull's theorem makes the filtration separated. The first instance is that a regular local ring has no zero-divisors, which is not visible from the numerical definition at all.

Lemma 29.8.4: A Graded Domain Lifts

Let $(R, \mathfrak{m})$ be a local ring with $\bigcap_{n\geq 0} \mathfrak{m}^n = 0$. If $\operatorname{gr}_{\mathfrak{m}} R$ is an integral domain, then so is R.

***Proof*:**
Let $a, b \in R$ be nonzero. Because $\bigcap_n \mathfrak{m}^n = 0$, neither lies in every power of $\mathfrak{m}$, so there are largest integers $r, s \geq 0$ with $a \in \mathfrak{m}^r$ and $b \in \mathfrak{m}^s$ (reading $\mathfrak{m}^0 = R$); thus $a \notin \mathfrak{m}^{r+1}$ and $b \notin \mathfrak{m}^{s+1}$. Their classes $a^* = a + \mathfrak{m}^{r+1}$ and $b^* = b + \mathfrak{m}^{s+1}$ are then nonzero in the graded pieces $(\operatorname{gr}_{\mathfrak{m}} R)_r$ and $(\operatorname{gr}_{\mathfrak{m}} R)_s$.

Since $\operatorname{gr}_{\mathfrak{m}} R$ is a domain, $a^* b^* \neq 0$ in $(\operatorname{gr}_{\mathfrak{m}} R)_{r+s}$, which says exactly that $ab \notin \mathfrak{m}^{r+s+1}$. In particular $ab \neq 0$, completing the proof.

Corollary 29.8.5: A Regular Local Ring Is a Domain

Every regular local ring is an integral domain.

***Proof*:**
Let $(R, \mathfrak{m})$ be regular of dimension d. In a local ring $\mathfrak{m}$ is the Jacobson radical, so corollary 25.4.12 applies and gives $\bigcap_n \mathfrak{m}^n = 0$. By theorem 29.8.3(3) the ring $\operatorname{gr}_{\mathfrak{m}} R$ is a polynomial ring over a field, hence a domain, and lemma 29.8.4 transfers this to R, as we sought to show.

Regularity is also insensitive to completion, for the same reason: passing to $\hat{R}$ changes neither the associated graded ring nor the dimension, and criterion (3) sees nothing else. This is what makes it legitimate to test regularity after completing, where the Cohen structure theorem (theorem 25.6.1) puts formal coordinates on the ring.

Proposition 29.8.6: Regularity and Completion

Let $(R, \mathfrak{m})$ be a Noetherian local ring and $\hat{R}$ its $\mathfrak{m}$-adic completion. Then R is regular if and only if $\hat{R}$ is regular.

***Proof*:**
The ring $\hat{R}$ is Noetherian by theorem 25.5.7, and it is local with maximal ideal $\hat{\mathfrak{m}}$ and the same residue field, since $R/\mathfrak{m}^n \cong \hat{R}/\hat{\mathfrak{m}}^n$ for every n. By proposition 25.5.2(2) the two associated graded rings agree, $\operatorname{gr}_{\mathfrak{m}} R \cong \operatorname{gr}_{\hat{\mathfrak{m}}} \hat{R}$, and by corollary 29.4.2 the two dimensions agree. Criterion (3) of theorem 29.8.3 is a statement about those two data alone, so it holds for R exactly when it holds for $\hat{R}$, completing the proof.

Example 29.8.7: Regular and Singular Local Rings

1. *Formal power series.* Let $R = k[[x_1, \ldots, x_n]]$, the completion of $A = k[x_1, \ldots, x_n]_{(x_1, \ldots, x_n)}$ (example 25.1.2). Then $\mathfrak{m} = (x_1, \ldots, x_n)$ and $\mathfrak{m}/\mathfrak{m}^2$ has the n classes $\bar{x}_i$ as a basis, so the embedding dimension is n. The dimension is also n: $\dim A = n$ because $\dim k[x_1, \ldots, x_n] = n$ by theorem 29.6.3 and localizing at a maximal ideal of height n retains it, and $\dim R = \dim A$ by corollary 29.4.2. So R is regular, with $x_1, \ldots, x_n$ a regular system of parameters, and $\operatorname{gr}_{\mathfrak{m}} R \cong k[t_1, \ldots, t_n]$ recovers the fact that a power series has a well-defined lowest-degree homogeneous part.

2. *Discrete valuation rings.* A Noetherian local domain of dimension 1 is regular exactly when

$\mathfrak{m}$ is principal, which by theorem 27.2.2 is exactly when it is a discrete valuation ring. So in dimension one, regular, normal and discrete-valuation all coincide; this is the case [42] uses to identify the smooth points of a curve.

3. *The cusp.* Let $A = k[x,y]/(y^2 - x^3)$ and $R = A_{\mathfrak{m}}$ with $\mathfrak{m} = (\bar{x}, \bar{y})$. Then $\dim R = 1$, since A is a one-dimensional domain by theorem 29.6.3 ($\operatorname{Frac}(A) = k(t)$ under $\bar{x} \mapsto t^2$, $\bar{y} \mapsto t^3$) and $\mathfrak{m}$ is maximal. But the defining relation $y^2 - x^3$ lies in $(x,y)^2$, so it imposes no linear condition: writing $\mathfrak{n} = (x,y) \subseteq k[x,y]$, one has $\mathfrak{m}/\mathfrak{m}^2 \cong \mathfrak{n}/(\mathfrak{n}^2 + (y^2 - x^3)) = \mathfrak{n}/\mathfrak{n}^2$, which is two-dimensional. So the embedding dimension is $2 > 1 = \dim R$ and R is not regular. This is the algebraic signature of the cusp of the curve $y^2 = x^3$ at the origin.

4. *A regular ring of dimension zero.* If $\dim R = 0$ then regularity forces $\mathfrak{m} = \mathfrak{m}^2$, hence $\mathfrak{m} = 0$ by Nakayama, so the regular local rings of dimension zero are exactly the fields. Contrast the Artinian local ring $k[x]/(x^2)$, which has dimension 0 and embedding dimension 1, so it is not regular; by corollary 29.8.5 it could not be, having the zero-divisor $\bar{x}$.

29.9 Regular Local Rings Are Factorial

Section 29.8 characterized regularity three ways and drew one consequence from the graded criterion, that a regular local ring is a domain. The theorem of this section is deeper and is not suggested by any of the three criteria: a regular local ring has unique factorization. It is due to Auslander and Buchsbaum, and the proof is an induction on dimension that leaves the ring at every step, passing to a localization in which the dimension has dropped.

Two criteria carry the induction, and both are worth having on their own. The first converts factoriality into a statement about height-one primes, which is what makes it accessible to dimension theory at all. The second says factoriality may be checked after inverting a single prime element. Read geometrically the theorem says that on a smooth variety every codimension-one subvariety is cut out near each point by one equation, which is how [42] uses it.

Lemma 29.9.1: Factoriality by Height-One Primes

Let R be a Noetherian domain. Then R is a unique factorization domain if and only if every prime of height one is principal.

***Proof*:**

($\Rightarrow$) Let $\mathfrak{p}$ have height one and pick $a \in \mathfrak{p}$ nonzero; a is a nonunit because $\mathfrak{p}$ is proper. Factor $a = p_1 \cdots p_r$ into irreducibles. As $\mathfrak{p}$ is prime, some $p_i \in \mathfrak{p}$, and in a unique factorization domain an irreducible element is prime (proposition 10.1.29), so (p_i) is a nonzero prime with $0 \subsetneq (p_i) \subseteq \mathfrak{p}$. A strict inclusion $(p_i) \subsetneq \mathfrak{p}$ would exhibit a chain of length two descending from $\mathfrak{p}$, contradicting $\operatorname{ht}\mathfrak{p} = 1$. Hence $\mathfrak{p} = (p_i)$.

($\Leftarrow$) A Noetherian ring satisfies the ascending chain condition on ideals, in particular on principal ideals, so by theorem 10.1.30 it suffices to show every irreducible element is prime. Let a be irreducible. Then (a) is a proper nonzero ideal, so it has a minimal prime $\mathfrak{p}$. Krull's height theorem (theorem 29.5.2) with $c = 1$ gives $\operatorname{ht}\mathfrak{p} \leq 1$, and $\mathfrak{p} \neq 0$ since $0 \neq a \in \mathfrak{p}$, so $\operatorname{ht}\mathfrak{p} = 1$. By hypothesis $\mathfrak{p} = (p)$ for some p, and $a \in (p)$ gives $a = pb$. Here p is a nonunit, so irreducibility of a forces b to be a unit; therefore $(a) = (p) = \mathfrak{p}$ is prime and a is a prime element, completing the

proof.

The criterion is what ties factoriality to the rest of this chapter: height is a dimension-theoretic invariant, and Krull's height theorem is exactly what produced the height-one prime in the second half. The next lemma is the descent step. Inverting one prime element destroys only the primes containing it, and those form a single height-one class that can be checked by hand.

Lemma 29.9.2: Nagata's Criterion

Let R be a Noetherian domain and $x \in R$ a prime element. If the localization $R_x = R[1/x]$ is a unique factorization domain, then so is R.

***Proof*:**
Both R and R_x are Noetherian domains, the latter by proposition 23.4.7(1),(2), so lemma 29.9.1 applies to each. Let $\mathfrak{p} \subseteq R$ be a prime of height one; it suffices to show $\mathfrak{p}$ is principal.

Case $x \in \mathfrak{p}$. Then $0 \subsetneq (x) \subseteq \mathfrak{p}$ with (x) prime, and $\operatorname{ht} \mathfrak{p} = 1$ forces $\mathfrak{p} = (x)$.

Case $x \notin \mathfrak{p}$. The primes of R_x are the extensions of the primes of R not meeting $\{x^n \mid n \geq 0\}$, and the correspondence preserves inclusions (proposition 23.4.5), so $\mathfrak{p}R_x$ is a prime of height one. As R_x is a unique factorization domain, lemma 29.9.1 makes $\mathfrak{p}R_x$ principal. Multiplying a generator by a power of the unit x we may take the generator to be some $a \in R$, and then $a \in \mathfrak{p}R_x \cap R = \mathfrak{p}$, the contraction of the extension of $\mathfrak{p}$ being $\mathfrak{p}$ again since $\mathfrak{p}$ misses the powers of x.

We may further assume $x \nmid a$. If $a = xa'$ then $a' \in \mathfrak{p}$, because $a \in \mathfrak{p}$, $x \notin \mathfrak{p}$ and $\mathfrak{p}$ is prime; and a' still generates $\mathfrak{p}R_x$, since x is a unit there. This replacement cannot repeat indefinitely: it would place a in $\bigcap_n (x^n)$, which is 0 by corollary 25.4.11, while $a \neq 0$.

Now $\mathfrak{p} = (a)$. One inclusion is $a \in \mathfrak{p}$. For the other, let $b \in \mathfrak{p}$. Then $b \in \mathfrak{p}R_x = aR_x$, so $x^n b = ac$ for some $c \in R$ and $n \geq 0$. If $n \geq 1$ then x divides ac; as x is prime and $x \nmid a$, it divides c, and cancelling x from both sides (legitimate in a domain) lowers n by one. Iterating gives $b \in (a)$. So every height-one prime of R is principal, and lemma 29.9.1 makes R a unique factorization domain, completing the proof.

What remains is to produce a generator for a height-one prime after inverting x, and this is where the induction's homological input enters. The prime will be visibly principal at every localization, and the problem is to pass from that local information to a single global generator. The next two lemmas do so; the first is elementary, and the second is the one place this section imports a fact it does not prove.

Lemma 29.9.3: A Finite Free Resolution Makes a Projective Module Stably Free

Let S be a ring and P a finitely generated projective S-module admitting a resolution $0 \to F_n \to \cdots \to F_0 \to P \to 0$ by finitely generated free modules. Then P is *stably free*: $P \oplus S^a \cong S^b$ for some $a, b \geq 0$.

***Proof*:**
Induct on n. If $n = 0$ then $P \cong F_0$ is free. For $n \geq 1$ put $K = \ker(F_0 \to P)$. Since P is projective the sequence $0 \to K \to F_0 \to P \to 0$ splits, so $F_0 \cong P \oplus K$; in particular K is a direct summand of a finitely generated free module, hence finitely generated projective, and $0 \to F_n \to \cdots \to F_1 \to K \to 0$ is a free resolution of length $n-1$. By induction $K \oplus S^a \cong S^b$ for some a, b. Then

$$P \oplus S^b \cong P \oplus K \oplus S^a \cong F_0 \oplus S^a$$

which is free, as we sought to show.

Lemma 29.9.4: A Locally Principal Ideal of Finite Global Dimension Is Principal

Let S be a Noetherian domain of finite global dimension and $I \subseteq S$ a nonzero ideal such that $I_{\mathfrak{q}}$ is a principal ideal of $S_{\mathfrak{q}}$ for every prime $\mathfrak{q}$ of S. Then I is principal.

***Proof*:**
Step 1: I is invertible, hence projective. Work inside $K = \operatorname{Frac}(S)$ and put $I^{-1} = \{z \in K \mid zI \subseteq S\}$, an S-submodule of K containing S. The product II^{-1} is an ideal of S; it equals S, because for each prime $\mathfrak{q}$ the localization $I_{\mathfrak{q}}$ is generated by one element $t_{\mathfrak{q}} \neq 0$, so $t_{\mathfrak{q}}^{-1} \in (I^{-1})_{\mathfrak{q}}$ and $(II^{-1})_{\mathfrak{q}} \ni t_{\mathfrak{q}} t_{\mathfrak{q}}^{-1} = 1$, and an ideal that is the unit ideal at every prime is the unit ideal (proposition 23.4.13 applied to S/II^{-1}). Choose $a_1, \ldots, a_r \in I$ and $b_1, \ldots, b_r \in I^{-1}$ with $\sum_i a_i b_i = 1$. Then $x \mapsto (b_1 x, \ldots, b_r x)$ is an S-module map $I \to S^r$, and composing with $(s_1, \ldots, s_r) \mapsto \sum_i s_i a_i$ returns x. So I is a direct summand of S^r, hence finitely generated projective, and $I_{\mathfrak{q}} \cong S_{\mathfrak{q}}$ at every prime.

Step 2: I is stably free. Finite global dimension gives I a finite resolution by finitely generated free modules, so lemma 29.9.3 applies: $I \oplus S^a \cong S^b$ for some a, b. Localizing at any prime and comparing ranks gives $1 + a = b$, so the relation reads $I \oplus S^a \cong S^{a+1}$.

Step 3: rank one and stably free give free. This is corollary 16.4.6, applied to I: it is finitely generated projective with $I_{\mathfrak{q}} \cong S_{\mathfrak{q}}$ at every prime, and Step 2 gives the required relation. So $I \cong S$ as an S-module, and the image of 1 under such an isomorphism generates I, completing the proof.

Theorem 29.9.5: Regular Local Rings Are Factorial

Every regular local ring is a unique factorization domain.

***Proof*:**
Let $(R, \mathfrak{m})$ be regular of dimension d; induct on d.

Base cases. If $d = 0$ then R is a field (example 29.8.7), which has no nonzero nonunits and is trivially factorial. If $d = 1$ then R is a Noetherian local domain whose maximal ideal is principal, hence a discrete valuation ring (theorem 27.2.2); its only height-one prime is $\mathfrak{m}$, which is principal, so lemma 29.9.1 applies.

Producing a prime element. Let $d \geq 2$. By corollary 29.8.5 R is a domain. Choose $x \in \mathfrak{m} \setminus \mathfrak{m}^2$. Its class is nonzero in $\mathfrak{m}/\mathfrak{m}^2$, so it extends to a basis, and lifting gives a minimal generating set $x, x_2, \ldots, x_d$ of $\mathfrak{m}$. Then $\mathfrak{m}/(x)$ is generated by the $d-1$ classes of $x_2, \ldots, x_d$, while

$\dim R/(x) = d-1$ because x is a nonzero nonunit in a domain (the consequence of theorem 29.5.2 recorded after it). So $R/(x)$ is regular by theorem 29.8.3(2), hence a domain by corollary 29.8.5, and therefore x is a prime element of R.

Reduction to a localization. By lemma 29.9.2 it is enough that $S = R_x$ is a unique factorization domain, and by lemma 29.9.1 it is enough that every height-one prime of S is principal. Note S is a Noetherian domain by proposition 23.4.7.

Global dimension is finite along the way. The Auslander-Buchsbaum-Serre theorem (theorem 58.2.11) makes $\operatorname{gldim} R$ finite, R being regular. Global dimension does not rise under localization: an S'-module over a localization S' of R is the localization of itself viewed as an R-module, and localizing an R-projective resolution gives an S'-projective resolution of the same length, localization being exact (proposition 23.4.9) and carrying projectives to projectives. Hence $\operatorname{gldim} S \leq \operatorname{gldim} R < \infty$, and likewise for every $R_{\mathfrak{p}}$.

The localizations are smaller regular rings. Let $\mathfrak{q}$ be a prime of S and $\mathfrak{p}$ the corresponding prime of R, so $S_{\mathfrak{q}} \cong R_{\mathfrak{p}}$ and $x \notin \mathfrak{p}$. Then $\mathfrak{p} \subsetneq \mathfrak{m}$, so $\dim R_{\mathfrak{p}} = \operatorname{ht} \mathfrak{p} < d$. Since $\operatorname{gldim} R_{\mathfrak{p}}$ is finite, the Auslander-Buchsbaum-Serre theorem in the other direction makes $R_{\mathfrak{p}}$ regular, and the induction hypothesis makes it a unique factorization domain.

Conclusion. Let $\mathfrak{P}$ be a height-one prime of S. For a prime $\mathfrak{q}$ of S, either $\mathfrak{P} \not\subseteq \mathfrak{q}$, in which case $\mathfrak{P}S_{\mathfrak{q}} = S_{\mathfrak{q}}$ is principal, or $\mathfrak{P} \subseteq \mathfrak{q}$, in which case $\mathfrak{P}S_{\mathfrak{q}}$ is a height-one prime of the unique factorization domain $S_{\mathfrak{q}}$ and is principal by lemma 29.9.1. So $\mathfrak{P}$ is a nonzero locally principal ideal of a Noetherian domain of finite global dimension, and lemma 29.9.4 makes it principal. Therefore S is a unique factorization domain, and lemma 29.9.2 carries this back to R, completing the proof.

Factoriality is the strongest of the standard finiteness conditions a local ring can carry, and the two weaker ones follow from it at once. The first is integral closure.

Corollary 29.9.6: A Unique Factorization Domain Is Integrally Closed

Every unique factorization domain is integrally closed in its fraction field.

***Proof*:**
Let R be a unique factorization domain with fraction field K and let $z \in K$ be integral over R. Write $z = a/b$ with $a, b \in R$, $b \neq 0$, sharing no irreducible factor, which unique factorization permits. From $z^n + c_{n-1}z^{n-1} + \cdots + c_0 = 0$ with $c_i \in R$, multiplying by b^n gives

$$a^n = -b\left(c_{n-1}a^{n-1} + c_{n-2}a^{n-2}b + \cdots + c_0 b^{n-1}\right)$$

So every irreducible factor p of b divides a^n, and p is prime (proposition 10.1.29), so p divides a, contrary to the choice of a and b. Hence b has no irreducible factor at all, so it is a unit and $z = ab^{-1} \in R$, as we sought to show.

Corollary 29.9.7: A Regular Local Ring Is Normal

Every regular local ring is a normal domain, and in particular is regular in codimension one.

***Proof*:**
Combine theorem 29.9.5 with corollary 29.9.6; the ring is a domain by corollary 29.8.5. For the last clause, a localization of a normal domain is normal by proposition 23.4.7(3), completing the proof.

Example 29.9.8: Normal but Not Factorial
Neither implication in

$$\text{regular} \Rightarrow \text{factorial} \Rightarrow \text{normal}$$

reverses. Let k have characteristic $\neq 2$ and let $B = k[u^2, uv, v^2] \subseteq k[u, v]$, the subring of polynomials of even total degree. Sending $x \mapsto u^2$, $y \mapsto v^2$, $z \mapsto uv$ identifies B with $k[x, y, z]/(xy - z^2)$, so B is the coordinate ring of the quadric cone.

B is normal. Let σ be the involution $u \mapsto -u$, $v \mapsto -v$ of $k[u, v]$. Its fixed ring is the even part, which is B, and its fixed field inside $k(u, v)$ is $\operatorname{Frac}(B) = k(u^2, u/v)$. Let $w \in \operatorname{Frac}(B)$ be integral over B. Then w is integral over $k[u, v]$, which is a unique factorization domain (corollary 11.2.4) and hence integrally closed by corollary 29.9.6; so $w \in k[u, v]$. Being in $\operatorname{Frac}(B)$, w is fixed by σ, so $w \in k[u, v]^\sigma = B$.

B is not factorial. In B the identity $u^2 \cdot v^2 = (uv)^2$ gives two factorizations of one element into irreducibles: each of u^2, v^2, uv has degree two, which is the least positive degree occurring in B, so none of them factors further in B, and no two of them are associates ($B^\times = k^\times$).

B is not regular. Localize at $\mathfrak{m} = (u^2, uv, v^2)$. The fraction field $k(u^2, u/v)$ has transcendence degree two over k, so $\dim B_\mathfrak{m} = 2$ by theorem 29.6.3, while $\mathfrak{m}/\mathfrak{m}^2$ has the three classes of u^2, uv, v^2 as a basis, $\mathfrak{m}^2$ being spanned by the monomials of degree four. So the embedding dimension is $3 > 2$.

The three computations are consistent with the displayed implications and show both are strict: $B_\mathfrak{m}$ is normal and not factorial, and by theorem 29.9.5 a non-factorial ring cannot be regular, which the third computation confirms directly.

29.10 Normal Domains in Codimension One

A normal domain is determined by its behaviour in codimension one. That is the content of this section, and it is what makes normality a condition one can check by looking only at the height-one primes: the ring is the intersection of the discrete valuation rings sitting at them. The result is used by the homological characterizations of normality in *Homological Algebra* [29, Serre's Criterion for Normality] and by the divisor theory of [42] and [13].

Everything rests on one fact about principal ideals, which is where normality enters.

Lemma 29.10.1: Associated Primes of a Principal Ideal Have Height One

Let R be a Noetherian normal domain and $b \in R$ a nonzero nonunit. Then every associated prime of (b) has height one.

***Proof*:**

Let $\mathfrak{p} \in \operatorname{Ass}(R/(b))$. Associated primes localize (corollary 24.6.2), so $\mathfrak{p}R_{\mathfrak{p}} \in \operatorname{Ass}\big(R_{\mathfrak{p}}/bR_{\mathfrak{p}}\big)$, and $R_{\mathfrak{p}}$ is again a Noetherian normal domain by proposition 23.4.7. Since $\operatorname{ht}\mathfrak{p} = \operatorname{kdim} R_{\mathfrak{p}}$, it suffices to treat the case where $(R,\mathfrak{m})$ is local with $\mathfrak{m} \in \operatorname{Ass}(R/(b))$ and to show $\operatorname{kdim} R = 1$.

By definition 24.3.1 there is $a \in R$ with $\mathfrak{m} = \operatorname{Ann}(\overline{a}) = (b : a)$, where $\overline{a}$ is the class of a in $R/(b)$; in particular $a \notin (b)$, since otherwise the annihilator would be all of R. Put $x = a/b \in \operatorname{Frac}(R)$, so $x \notin R$. For every $r \in \mathfrak{m}$ one has $ra \in (b)$, hence $rx = ra/b \in R$: that is, $x\mathfrak{m} \subseteq R$, and $x\mathfrak{m}$ is an R-submodule of R, so an ideal.

Case 1: $x\mathfrak{m} \subseteq \mathfrak{m}$. Then $x^n\mathfrak{m} \subseteq \mathfrak{m}$ for every n, so $R[x]\mathfrak{m} \subseteq \mathfrak{m} \subseteq R$. Choose $0 \neq c \in \mathfrak{m}$, which exists as $b \in \mathfrak{m}$ is nonzero. Then $cR[x] \subseteq R$, so $R[x] \subseteq c^{-1}R$, a cyclic R-module; as R is Noetherian, the submodule $R[x]$ is a finitely generated R-module, and proposition 26.1.4(2) makes x integral over R. Normality gives $x \in R$, contradicting $x \notin R$.

Case 2: $x\mathfrak{m} \not\subseteq \mathfrak{m}$. Then the ideal $x\mathfrak{m}$ is not contained in the unique maximal ideal, so $x\mathfrak{m} = R$. Pick $t \in \mathfrak{m}$ with $xt = 1$. For any $p \in \mathfrak{m}$ we have $xp \in R$ and $p = t\,(xp)$, so $\mathfrak{m} = tR$ is principal, and it is nonzero. A Noetherian local domain whose maximal ideal is principal and nonzero is a discrete valuation ring by theorem 27.2.2, hence of dimension one.

Case 1 is impossible, so Case 2 holds and $\operatorname{kdim} R = 1$, as we sought to show.

Theorem 29.10.2: A Normal Domain Is the Intersection of Its Height-One Localizations

Let R be a Noetherian normal domain with fraction field K. Then $R_{\mathfrak{p}}$ is a discrete valuation ring for every prime $\mathfrak{p}$ of height one, and

$$R = \bigcap_{\operatorname{ht}\mathfrak{p}=1} R_{\mathfrak{p}}$$

the intersection taken inside K.

***Proof*:**

For $\operatorname{ht}\mathfrak{p} = 1$ the ring $R_{\mathfrak{p}}$ is a Noetherian local domain of dimension one, normal by proposition 23.4.7, hence a discrete valuation ring by theorem 27.2.2.

The inclusion $R \subseteq \bigcap R_{\mathfrak{p}}$ is immediate. For the reverse, let x lie in every $R_{\mathfrak{p}}$ and write $x = a/b$ with $a, b \in R$ and $b \neq 0$. If b is a unit then $x \in R$, so assume otherwise and suppose $a \notin (b)$, aiming at a contradiction.

The class $\overline{a} \in R/(b)$ is then nonzero, and $I = \operatorname{Ann}(\overline{a}) = (b : a)$ is a proper ideal every element of which kills $\overline{a}$, hence is a zero-divisor on $R/(b)$. By corollary 24.5.2 the zero-divisors on $R/(b)$ are the union of the associated primes of (b), of which there are finitely many (corollary 24.4.3), so prime avoidance (proposition 24.5.1) places $I \subseteq \mathfrak{q}$ for a single $\mathfrak{q} \in \operatorname{Ass}(R/(b))$. By lemma 29.10.1, $\operatorname{ht}\mathfrak{q} = 1$.

Now $x \in R_{\mathfrak{q}}$ by hypothesis, so $a/b = c/s$ for some $c \in R$ and $s \notin \mathfrak{q}$, whence $sa \in bR$ and $s \in (b : a) = I \subseteq \mathfrak{q}$. That contradicts $s \notin \mathfrak{q}$. Therefore $a \in (b)$ and $x \in R$, completing the proof.

The theorem is the reason divisor theory works on a normal variety: a rational function regular at every codimension-one point is regular, so a function is controlled by its orders of vanishing along

the height-one primes alone. That reading, and the class group it supports, is [42].

30

Flatness and Faithfully-Flat Descent

Flatness is the algebraic form of continuous variation. A flat module is one against which tensoring preserves injections, so that submodule relations survive base change; for a ring map $R \to S$ it says the fibers of $\operatorname{Spec} S \to \operatorname{Spec} R$ vary without jumping. When in addition the base change loses no information (when it is *faithfully flat*), one can argue in reverse: a property that holds after tensoring up already held below. This is *descent*, and it is the reason the local models of a space determine the space. The chapter records the ring-theoretic core that the geometry books cash out as faithfully-flat and fppf descent, closing with the local criterion that detects flatness one fiber at a time, the tool deformation theory runs on.

Basic flatness is assumed from [21]. The local refinement is proved in [29, Local Criterion for Flatness] and cited here, alongside the Tor characterization it rests on.

30.1 Flat Modules

Recall from definition 17.5.4 that an R-module M is *flat* if $- \otimes_R M$ is exact, equivalently if it preserves injections; a ring map $R \to S$ is flat if S is flat as an R-module. Flatness is preserved under base change and composition, and is detected locally: M is flat over R iff $M_{\mathfrak{p}}$ is flat over $R_{\mathfrak{p}}$ for every prime $\mathfrak{p}$ (proposition 23.4.16). Localizations are flat, and for a Noetherian local ring the completion is flat (corollary 25.4.6). The homological measure of the failure of flatness is Tor: M is flat iff $\operatorname{Tor}_1^R(M, N) = 0$ for all N, and it suffices to test $N = R/\mathfrak{a}$ on finitely generated ideals; this is proved in [29] and used freely below.

30.2 Faithfully Flat Modules and Algebras

Definition 30.2.1: Faithfully Flat

An R-module M is *faithfully flat* if it is flat and, for every R-module N, the vanishing $N \otimes_R M = 0$ forces $N = 0$. A ring map $R \to S$ is faithfully flat if S is faithfully flat as an R-module.

Proposition 30.2.2: Characterizations of Faithful Flatness

For a flat R-module M the following are equivalent:

1. M is faithfully flat;
2. a sequence of R-modules is exact iff it stays exact after $- \otimes_R M$;
3. $\mathfrak{m}M \neq M$ for every maximal ideal $\mathfrak{m}$, i.e. $M \otimes_R \kappa(\mathfrak{m}) \neq 0$ for all $\mathfrak{m}$.

For a flat ring map $R \to S$ these are equivalent to $\operatorname{Spec} S \to \operatorname{Spec} R$ being surjective.

***Proof*:**
(1) $\Rightarrow$ (2): flatness already preserves exactness; conversely if $C_\bullet \otimes M$ is exact then $H(C_\bullet) \otimes M = H(C_\bullet \otimes M) = 0$ (a flat functor commutes with homology), so $H(C_\bullet) = 0$ by (1). (2) $\Rightarrow$ (3): the sequence $0 \to R/\mathfrak{m} \to 0$ is not exact, so by (2) it remains non-exact after $- \otimes M$, forcing $M/\mathfrak{m}M = (R/\mathfrak{m}) \otimes M \neq 0$. (3) $\Rightarrow$ (1): let $N \neq 0$ and $0 \neq x \in N$, so $Rx \cong R/\mathfrak{a}$ with $\mathfrak{a} = \operatorname{Ann}(x) \subseteq \mathfrak{m}$ for some maximal $\mathfrak{m}$. Tensoring with the flat M: the inclusion $Rx \hookrightarrow N$ gives an injection $Rx \otimes M \hookrightarrow N \otimes M$, while the surjection $R/\mathfrak{a} \to R/\mathfrak{m}$ gives a surjection $Rx \otimes M = M/\mathfrak{a}M \twoheadrightarrow M/\mathfrak{m}M \neq 0$; hence $Rx \otimes M \neq 0$, so $N \otimes M \neq 0$. For a flat ring map these are further equivalent to surjectivity of $\operatorname{Spec} S \to \operatorname{Spec} R$: (1) gives $S \otimes_R \kappa(\mathfrak{p}) \neq 0$ for every prime $\mathfrak{p}$, so every fibre is nonempty and the map is surjective; conversely a surjective map hits every maximal ideal, which is (3).

Corollary 30.2.3: Faithfully Flat Maps are Injective

A faithfully flat ring map $R \to S$ is injective, and $\mathfrak{a} = \mathfrak{a}S \cap R$ for every ideal $\mathfrak{a}$ of R.

***Proof*:**
Apply faithful flatness to the kernel K of $R \to S$: tensoring $0 \to K \to R \to S$ with the flat S gives $K \otimes_R S = \ker(S \to S \otimes_R S)$, the map being $s \mapsto 1 \otimes s$, which is split by the multiplication $S \otimes_R S \to S$; so $K \otimes S = 0$, whence $K = 0$. For the second claim, the map $R/\mathfrak{a} \to (R/\mathfrak{a}) \otimes_R S = S/\mathfrak{a}S$ has kernel $(\mathfrak{a}S \cap R)/\mathfrak{a}$; since $S/\mathfrak{a}S$ is faithfully flat over $R/\mathfrak{a}$ (base change of a faithfully flat map), it is injective by the first part, so $\mathfrak{a}S \cap R = \mathfrak{a}$.

Localization $R \to R_f$ is flat but rarely faithfully flat (its image in $\operatorname{Spec} R$ omits $V(f)$); by contrast a nonzero free module is faithfully flat, a finite free ring extension is faithfully flat, and for a Noetherian local ring the completion $R \to \hat{R}$ is faithfully flat.

30.3 Faithfully-Flat Descent

Faithful flatness lets a property established upstairs be brought back down.

Proposition 30.3.1: Descent of Module Properties

Let $R \to S$ be faithfully flat and M an R-module. Then M is finitely generated (respectively finitely presented, flat, or finitely generated projective) over R iff $M \otimes_R S$ has the corresponding property over S.

***Proof*:**
Necessity is base change. For sufficiency: if $M \otimes S$ is generated by finitely many elements, clear denominators so they are images of $m_i \otimes 1$; the cokernel C of $R^n \xrightarrow{(m_i)} M$ satisfies $C \otimes S = 0$, so $C = 0$ and M is finitely generated. Given that, finite presentation descends by applying the same to the kernel of $R^n \to M$ (finitely generated as $\ker \otimes S = \ker(S^n \to M \otimes S)$ is). Flatness descends because $\operatorname{Tor}_1^R(M,N) \otimes S = \operatorname{Tor}_1^S(M \otimes S, N \otimes S) = 0$ for all N, whence $\operatorname{Tor}_1^R(M,N) = 0$ by faithful flatness. Finitely generated projective descends since it equals finitely presented plus flat.

The deeper statement recovers a module, not merely a property, from data upstairs. Write $S^{\otimes 2} = S \otimes_R S$ and $S^{\otimes 3} = S \otimes_R S \otimes_R S$, with the two coprojections $p_1, p_2 \colon S \to S^{\otimes 2}$.

Theorem 30.3.2: Faithfully-Flat Descent for Modules

Let $R \to S$ be faithfully flat. Then $M \mapsto M \otimes_R S$ is an equivalence from R-modules to the category of *descent data*: pairs (N, φ) with N an S-module and $\varphi \colon p_1^* N \xrightarrow{\sim} p_2^* N$ an isomorphism over $S^{\otimes 2}$ satisfying the cocycle condition over $S^{\otimes 3}$. The inverse sends (N, φ) to the equalizer of φ-twisted coprojections $N \rightrightarrows N \otimes_S S^{\otimes 2}$.

***Proof*:**
The heart is the exactness, for every R-module M, of the *Amitsur complex*

$$0 \to M \to M \otimes_R S \to M \otimes_R S^{\otimes 2},$$

the second map being $m \otimes s \mapsto m \otimes (p_1 - p_2)(s)$. It suffices to check this after the faithfully flat base change $S \otimes_R -$, where the augmented complex acquires the contracting homotopy $s_0 \otimes s_1 \otimes \cdots \mapsto (s_0 s_1) \otimes s_2 \otimes \cdots$ (multiplication of the first two tensor factors), which shows exactness. Faithful flatness then gives exactness over R. Applying this with the canonical datum shows $M \otimes S$ recovers M as the stated equalizer, so the functor is fully faithful; the cocycle condition is exactly what makes the equalizer of a general (N, φ) an R-module whose base change is (N, φ), giving essential surjectivity.

This is the affine case of the descent that lets sheaves and torsors be glued along faithfully flat (fppf) covers, developed in [37].

30.4 The Local Criterion for Flatness

For finitely generated modules over a Noetherian local ring, flatness collapses to a single Tor, and this is what makes flatness checkable in families.

Theorem 30.4.1: Local Criterion for Flatness

Let $(R, \mathfrak{m})$ be a Noetherian local ring with residue field κ and M a finitely generated R-module. Then

$$M \text{ flat} \iff M \text{ free} \iff \operatorname{Tor}_1^R(\kappa, M) = 0$$

More generally, for a local homomorphism $(R, \mathfrak{m}) \to (S, \mathfrak{n})$ of Noetherian local rings and a finitely generated S-module M, one has M flat over R iff $\operatorname{Tor}_1^R(\kappa, M) = 0$; over an Artinian local base this is the criterion by which flatness of a deformation is tested one infinitesimal step at a time.

The equivalences and the general criterion are proved homologically in [29, Local Criterion for Flatness], which owns this theorem (DECISIONS 2026-08-17); here the point is that they reduce flatness (a condition on all modules) to the vanishing of one Tor against the residue field, and it is in this form that [37] invokes flatness over Artinian bases.

30.5 Fitting Ideals

The Fitting ideals of a finitely presented module are the ideals of minors of a presentation matrix, and they do not depend on the presentation. They cut out the loci where the number of generators jumps, commute with base change, and detect local freeness.

Lemma 30.5.1: Ideals of Minors

Let A be an $n \times m$ matrix over R. For an integer k let $I_k(A)$ be the ideal generated by the $k \times k$ minors of A, with $I_k(A) = R$ for $k \leq 0$ and $I_k(A) = 0$ for $k > \min(n, m)$. Then for every integer k:

1. $I_{k+1}(A) \subseteq I_k(A)$
2. $I_k(PAQ) \subseteq I_k(A)$ for every $p \times n$ matrix P and every $m \times q$ matrix Q, with equality when P and Q are invertible
3. $I_{k+1}(A^+) = I_k(A)$ for the $(n+1) \times (m+1)$ matrix

$$A^+ = \begin{pmatrix} A & 0 \\ 0 & 1 \end{pmatrix}$$

***Proof*:**
Over a commutative ring the determinant is unchanged by transposition, is R-linear in each row and in each column, vanishes when two columns are equal, changes sign when two rows or two columns are exchanged, and is unchanged when a multiple of one column is added to another

(proposition 13.4.6 and proposition 13.4.9).

1. For $k \leq 0$ the right side is R, and for $k+1 > \min(n,m)$ the left side is 0, so let $k \geq 1$ and $k+1 \leq \min(n,m)$. Let $B = (b_{ij})$ be a $(k+1) \times (k+1)$ submatrix of A, and let B_i be B with its first column replaced by the i-th standard basis vector. Linearity in the first column gives
$$\det B = \sum_{i=1}^{k+1} b_{i1} \det B_i$$
Subtracting b_{ij} times the first column of B_i from its j-th column, for each $j \geq 2$, leaves $\det B_i$ unchanged and turns row i into $(1, 0, \ldots, 0)$. Moving row i to the top then changes the determinant by a sign and produces the block diagonal matrix with blocks (1) and $B^{(i)}$, the submatrix of B omitting row i and column 1. So $\det B_i = \pm \det B^{(i)}$ (proposition 13.4.8). Each $B^{(i)}$ is a $k \times k$ submatrix of A, so $\det B \in I_k(A)$.

2. It suffices to show $I_k(AQ) \subseteq I_k(A)$ and $I_k(PA) \subseteq I_k(A)$, since then $I_k(PAQ) \subseteq I_k(AQ) \subseteq I_k(A)$. For $k \leq 0$ all these ideals are R, so let $k \geq 1$. Let $a_1, \ldots, a_m$ be the columns of A, fix rows $i_1 < \cdots < i_k$, and write $\bar{v} \in R^k$ for the entries of $v \in R^n$ in these rows. The minor of AQ on these rows and on columns $j_1 < \cdots < j_k$ is the determinant of the $k \times k$ matrix with columns $\sum_{l=1}^{m} q_{l j_s} \bar{a}_l$ for $s = 1, \ldots, k$. Linearity in each column expands it as
$$\sum_{l_1, \ldots, l_k = 1}^{m} q_{l_1 j_1} \cdots q_{l_k j_k} \det \begin{pmatrix} \bar{a}_{l_1} & \cdots & \bar{a}_{l_k} \end{pmatrix}$$
A term with two equal indices has two equal columns and vanishes, and a term with distinct indices is, after reordering its columns, $\pm$ the minor of A on rows $i_1, \ldots, i_k$ and columns $l_1, \ldots, l_k$. When $k > m$ every term repeats an index. So every $k \times k$ minor of AQ lies in $I_k(A)$, that is, $I_k(AQ) \subseteq I_k(A)$. A minor of a matrix equals the corresponding minor of its transpose, so $I_k(X^t) = I_k(X)$ for every matrix X, and $I_k(PA) = I_k(A^t P^t) \subseteq I_k(A^t) = I_k(A)$. If P and Q are invertible, then $A = P^{-1}(PAQ)Q^{-1}$ gives the reverse inclusion.

3. For $k \leq 0$ both sides are R (for $k = 0$ because the entry 1 of A^+ lies in $I_1(A^+)$), and for $k > \min(n,m)$ both sides are 0. Let $1 \leq k \leq \min(n,m)$ and let B be a $(k+1) \times (k+1)$ submatrix of A^+. If B uses the last row of A^+ but not its last column, then that row of B is zero and $\det B = 0$ by linearity in that row. The same holds with rows and columns exchanged. If B uses neither, then $\det B \in I_{k+1}(A) \subseteq I_k(A)$ by (1). If B uses both, then it is block diagonal with blocks B' and (1) for a $k \times k$ submatrix B' of A, so $\det B = \det B'$ (proposition 13.4.8), and every $k \times k$ submatrix B' of A arises in this way. Hence $I_{k+1}(A^+) = I_k(A)$.

Definition 30.5.2: Fitting Ideals

Let M be a finitely presented R-module with presentation $R^m \xrightarrow{A} R^n \to M \to 0$, so A is an $n \times m$ matrix. For $i \geq 0$ the *i-th Fitting ideal* of M is $\mathrm{Fitt}_i(M) = I_{n-i}(A)$, the ideal generated by the $(n-i) \times (n-i)$ minors of A, with the conventions of lemma 30.5.1: $\mathrm{Fitt}_i(M) = R$ when $n - i \leq 0$ and $\mathrm{Fitt}_i(M) = 0$ when $n - i > m$.

Proposition 30.5.3: Properties of Fitting Ideals

Let M be a finitely presented R-module with presentation $R^m \xrightarrow{A} R^n \to M \to 0$. The Fitting ideals of M are independent of the chosen presentation, and:

1. $\mathrm{Fitt}_0(M) \subseteq \mathrm{Fitt}_1(M) \subseteq \cdots$, with $\mathrm{Fitt}_i(M) = R$ for $i \geq n$, and every free module R^s has $\mathrm{Fitt}_i(R^s) = 0$ for $i < s$
2. base change: $\mathrm{Fitt}_i(M \otimes_R R') = \mathrm{Fitt}_i(M)R'$ for every ring map $R \to R'$
3. $\mathrm{Fitt}_0(M) \subseteq \mathrm{Ann}(M)$ and $\mathrm{Ann}(M)^n \subseteq \mathrm{Fitt}_0(M)$
4. for a prime $\mathfrak{p}$ and an integer $d \geq 0$, the minimal number of generators of $M_\mathfrak{p}$ is $> d$ iff $\mathrm{Fitt}_d(M) \subseteq \mathfrak{p}$

***Proof*:**

For a surjection $\pi\colon R^n \to M$, say that a matrix A presents π when $\mathrm{im}(A) = \ker \pi$, that is, when $R^m \xrightarrow{A} R^n \xrightarrow{\pi} M \to 0$ is a presentation.

Step 1: the ideals depend only on π. Let A and A', of sizes $n \times m$ and $n \times m'$, both present a surjection $\pi\colon R^n \to M$. Each column of A' lies in $\ker \pi = \mathrm{im}(A)$, so $A' = AQ$ for an $m \times m'$ matrix Q whose columns are preimages under A of the columns of A'. Symmetrically $A = A'Q'$ for some Q', and lemma 30.5.1(2) gives $I_k(A') \subseteq I_k(A) \subseteq I_k(A')$ for every k.

Step 2: a change of basis. If A presents a surjection $\pi\colon R^n \to M$ and $P \in \mathrm{GL}_n(R)$, then PA presents πP^{-1}, since $\ker(\pi P^{-1}) = P(\ker \pi) = \mathrm{im}(PA)$, and $I_k(PA) = I_k(A)$ by lemma 30.5.1(2).

Step 3: an extra generator. Let the $n \times m$ matrix A present a surjection $\pi\colon R^n \to M$, let $y \in M$, and let $\pi_y\colon R^{n+1} \to M$ agree with π on R^n and send e_{n+1} to y. Choose $c \in R^n$ with $\pi(c) = y$ and put

$$P = \begin{pmatrix} I_n & -c \\ 0 & 1 \end{pmatrix} \in \mathrm{GL}_{n+1}(R)$$

whose inverse has c in place of $-c$. Then $\pi_y P$ agrees with π on R^n and sends e_{n+1} to $y - \pi(c) = 0$, so $\ker(\pi_y P) = \ker \pi \oplus Re_{n+1} = \mathrm{im}(A^+)$, with A^+ as in lemma 30.5.1(3). By Step 2, PA^+ presents $\pi_y P P^{-1} = \pi_y$, and lemma 30.5.1(2) and (3) give

$$I_{(n+1)-i}(PA^+) = I_{(n+1)-i}(A^+) = I_{n-i}(A)$$

for every $i \geq 0$.

Step 4: any two presentations. Let A present $\pi\colon R^n \to M$ and A' present $\pi'\colon R^{n'} \to M$, and put $x_j = \pi(e_j)$ and $y_l = \pi'(e_l)$. Applying Step 3 to π once for each of $y_1, \ldots, y_{n'}$ gives the surjection $\rho\colon R^{n+n'} \to M$ sending the standard basis to $x_1, \ldots, x_n, y_1, \ldots, y_{n'}$, with a matrix B presenting it and $I_{(n+n')-i}(B) = I_{n-i}(A)$. Applying Step 3 to π' once for each of $x_1, \ldots, x_n$ gives the surjection sending the standard basis to $y_1, \ldots, y_{n'}, x_1, \ldots, x_n$, which is ρS for a permutation matrix S, with a matrix B' presenting it and $I_{(n+n')-i}(B') = I_{n'-i}(A')$. By Step 2, $S^{-1}B$ also presents ρS, with the ideals of B, and Step 1 compares it with B'. Hence $I_{n-i}(A) = I_{n'-i}(A')$ for every $i \geq 0$. Finally, if $\varphi\colon M \to M'$ is an isomorphism, then A presents $\varphi\pi\colon R^n \to M'$, so isomorphic modules have the same Fitting ideals. In (1) to (4), A is the matrix of the given presentation and π is its surjection.

1. By lemma 30.5.1(1), $\operatorname{Fitt}_i(M) = I_{n-i}(A) \subseteq I_{n-i-1}(A) = \operatorname{Fitt}_{i+1}(M)$, and $\operatorname{Fitt}_i(M) = R$ for $i \geq n$ by definition 30.5.2. The free module R^s is presented by the zero map $R \to R^s$, so $\operatorname{Fitt}_i(R^s) = I_{s-i}(0) = 0$ for $i < s$.

2. Let $\varphi\colon R \to R'$ be a ring map, and let $\varphi(A)$ be the matrix with entries $\varphi(a_{ij})$. Applying the right exact functor $R' \otimes_R -$ (theorem 17.5.1) to $0 \to \operatorname{im}(A) \to R^n \to M \to 0$ and to $0 \to \ker A \to R^m \to \operatorname{im}(A) \to 0$ shows that the sequence

$$R' \otimes_R R^m \xrightarrow{1\otimes A} R' \otimes_R R^n \to R' \otimes_R M \to 0$$

   is exact. Identifying $R' \otimes_R R^k$ with R'^k through $r' \otimes e_j \mapsto r'e_j$, by induction on k from $R' \otimes_R R \cong R \otimes_R R' \cong R'$ (proposition 15.2.7, example 15.1.13) and theorem 15.2.3, turns $1 \otimes A$ into $\varphi(A)$, since $1 \otimes Ae_j = \sum_i \varphi(a_{ij}) \otimes e_i$. So $\varphi(A)$ presents $R' \otimes_R M$, which is isomorphic to $M \otimes_R R'$ (proposition 15.2.7). A determinant is a sum of signed products of entries (definition 13.4.5), so each minor of $\varphi(A)$ is the image under φ of the corresponding minor of A. Hence $\operatorname{Fitt}_i(M \otimes_R R') = I_{n-i}(\varphi(A)) = I_{n-i}(A)R' = \operatorname{Fitt}_i(M)R'$, the conventions agreeing because $RR' = R'$ and $0R' = 0$.

3. If $m < n$ then $\operatorname{Fitt}_0(M) = 0$. Otherwise let A_S be the $n \times n$ submatrix of A on a set S of n columns. For $v \in R^n$ the adjugate identity (proposition 13.4.11) gives $\det(A_S)v = A_S \operatorname{adj}(A_S)v \in \operatorname{im}(A_S) \subseteq \operatorname{im}(A) = \ker \pi$, so $\det(A_S)\pi(v) = 0$. As π is surjective, $\det(A_S) \in \operatorname{Ann}(M)$, and these determinants generate $\operatorname{Fitt}_0(M)$.

   The ideal $\operatorname{Ann}(M)^n$ is generated by the products $a_1 \cdots a_n$ with each $a_j \in \operatorname{Ann}(M)$. Given such $a_1, \ldots, a_n$, each $a_j e_j$ lies in $\ker \pi = \operatorname{im}(A)$, since $\pi(a_j e_j) = a_j \pi(e_j) = 0$, so $a_j e_j = Ab_j$ for some $b_j \in R^m$. The $m \times n$ matrix B with columns $b_1, \ldots, b_n$ satisfies $AB = \operatorname{diag}(a_1, \ldots, a_n)$, whose determinant is $a_1 \cdots a_n$ (proposition 13.4.8). Hence $a_1 \cdots a_n \in I_n(AB) \subseteq I_n(A) = \operatorname{Fitt}_0(M)$ by lemma 30.5.1(2).

4. Let $\mathfrak{m}$ be the maximal ideal of the local ring $R_\mathfrak{p}$, let $\kappa(\mathfrak{p}) = R_\mathfrak{p}/\mathfrak{m}$, and let $\psi\colon R \to \kappa(\mathfrak{p})$ be the composite map, whose kernel is $\mathfrak{p}$ (proposition 23.4.24). Put $V = M_\mathfrak{p}/\mathfrak{m}M_\mathfrak{p}$ and $s = \dim_{\kappa(\mathfrak{p})} V$, which is finite because V is spanned by the classes of the $\pi(e_j)/1$. A generating set of $M_\mathfrak{p}$ maps onto a spanning set of V, so it has at least s elements, and lifts to $M_\mathfrak{p}$ of a basis of V generate $M_\mathfrak{p}$ by Nakayama's lemma (lemma 23.4.29), $M_\mathfrak{p}$ being finitely generated over the local ring $R_\mathfrak{p}$. So the minimal number of generators of $M_\mathfrak{p}$ is s.

   Localization is exact (proposition 23.4.9). Applied to $0 \to \operatorname{im}(A) \to R^n \to M \to 0$ and to $0 \to \ker A \to R^m \to \operatorname{im}(A) \to 0$, as for the tensor product in (2), it shows that A, with its entries read in $R_\mathfrak{p}$, presents the localized surjection $\pi_\mathfrak{p}\colon R_\mathfrak{p}^n \to M_\mathfrak{p}$. The composite $R_\mathfrak{p}^n \to M_\mathfrak{p} \to V$ is surjective with kernel $\pi_\mathfrak{p}^{-1}(\mathfrak{m}M_\mathfrak{p}) = \operatorname{im}(A) + \mathfrak{m}R_\mathfrak{p}^n$, since $\mathfrak{m}M_\mathfrak{p} = \pi_\mathfrak{p}(\mathfrak{m}R_\mathfrak{p}^n)$. Reducing modulo $\mathfrak{m}$, the matrix $\psi(A)$ therefore presents a surjection $\kappa(\mathfrak{p})^n \to V$ over the field $\kappa(\mathfrak{p})$. As in (2), $\operatorname{Fitt}_d(V) = I_{n-d}(\psi(A))$ is the ideal generated by $\psi(\operatorname{Fitt}_d(M))$, which is zero iff $\operatorname{Fitt}_d(M) \subseteq \ker \psi = \mathfrak{p}$. On the other hand $V \cong \kappa(\mathfrak{p})^s$, so by (1) and the independence of the presentation, $\operatorname{Fitt}_d(V)$ is 0 for $d < s$ and $\kappa(\mathfrak{p})$ for $d \geq s$. Hence $\operatorname{Fitt}_d(M) \subseteq \mathfrak{p}$ iff $d < s$, which is the claim.

By proposition 30.5.3(4) the closed set $V(\operatorname{Fitt}_d(M))$ consists of the primes $\mathfrak{p}$ at which $M_\mathfrak{p}$ needs more than d generators. For $d = 0$ these are the primes with $M_\mathfrak{p} \neq 0$, so $V(\operatorname{Fitt}_0(M)) = \operatorname{Supp}(M)$

(definition 24.5.3). By proposition 30.5.3(3) a prime contains $\mathrm{Fitt}_0(M)$ iff it contains $\mathrm{Ann}(M)$, since $a^n \in \mathfrak{p}$ forces $a \in \mathfrak{p}$, and this recovers proposition 24.5.4 for finitely presented M. The two ideals differ in general: over $R = k[x]$, for a field k, the module $M = (R/(x))^{\oplus 2}$ is presented by $\mathrm{diag}(x, x)$, so $\mathrm{Fitt}_0(M) = (x^2)$ while $\mathrm{Ann}(M) = (x)$.

Definition 30.5.4: Locally Free Module

A finitely presented R-module M is *locally free of rank r* if $M_\mathfrak{p}$ is a free $R_\mathfrak{p}$-module of rank r for every prime $\mathfrak{p}$.

Proposition 30.5.5: Fitting Ideals Detect Local Freeness

Let M be a finitely presented R-module and $r \geq 0$. The following are equivalent.

1. $\mathrm{Fitt}_r(M) = R$ and, if $r \geq 1$, $\mathrm{Fitt}_{r-1}(M) = 0$.
2. There are $f_1, \ldots, f_k \in R$ generating the unit ideal such that each M_{f_j} is a free R_{f_j}-module of rank r.
3. M is locally free of rank r.

***Proof*:**

(1) ⇒ (2), (3) If $R = 0$ all three conditions hold, so let $R \neq 0$, and fix a presentation $R^m \xrightarrow{A} R^n \to M \to 0$. Then $n \geq r$, since otherwise $\mathrm{Fitt}_{r-1}(M) = R$ by definition 30.5.2. With $t = n - r$, condition (1) says that $I_t(A) = R$ and $I_{t+1}(A) = 0$, the second holding automatically when $r = 0$, and $I_t(A) = R$ forces $t \leq m$. Let δ be a $t \times t$ minor of A, and let S be R_δ, or $R_\mathfrak{p}$ for a prime $\mathfrak{p}$ with $\delta \notin \mathfrak{p}$, so that δ is a unit in S. Write M_S for M_δ, respectively $M_\mathfrak{p}$. Localization is exact (proposition 23.4.9), and applied to the two short exact sequences of the proof of proposition 30.5.3(2) it shows that A, with its entries read in S, presents M_S over S, and its $(t+1) \times (t+1)$ minors vanish, being images of those of A. Renumbering the generators and the relations changes neither M_S, up to isomorphism, nor the ideals of minors (lemma 30.5.1(2)), so we may take $\delta = \det B$ in the block form

$$A = \begin{pmatrix} B & C \\ D & E \end{pmatrix}$$

with B of size $t \times t$. Then B is invertible over S (proposition 13.4.12), and so are

$$P = \begin{pmatrix} B^{-1} & 0 \\ -DB^{-1} & I_r \end{pmatrix} \qquad Q = \begin{pmatrix} I_t & -B^{-1}C \\ 0 & I_{m-t} \end{pmatrix}$$

whose inverses replace B^{-1}, $-DB^{-1}$ and $-B^{-1}C$ by B, D and $B^{-1}C$. Multiplying out,

$$PAQ = \begin{pmatrix} I_t & 0 \\ 0 & E - DB^{-1}C \end{pmatrix}$$

and $I_{t+1}(PAQ) = I_{t+1}(A) = 0$ by lemma 30.5.1(2). The $(t+1) \times (t+1)$ minor of PAQ on its first t rows and columns together with row $t+i$ and column $t+j$ is the (i, j) entry of

$E - DB^{-1}C$ (proposition 13.4.8), so $E - DB^{-1}C = 0$. The automorphism P of S^n carries $\mathrm{im}(A) = \mathrm{im}(AQ)$ onto $\mathrm{im}(PAQ) = S^t \oplus 0$, hence

$$M_S \cong S^n/\mathrm{im}(A) \cong S^n/(S^t \oplus 0) \cong S^r$$

For $t = 0$ read $\delta = 1$ and omit B, C and D: then $I_1(A) = 0$ says $A = 0$, and $M_S \cong S^n = S^r$. Taking $S = R_\delta$ for each $t \times t$ minor δ gives (2), since these minors generate $I_t(A) = R$. For a prime $\mathfrak{p}$ some $t \times t$ minor lies outside $\mathfrak{p}$, as they generate R, and $S = R_\mathfrak{p}$ gives $M_\mathfrak{p} \cong R_\mathfrak{p}^r$, which is (3).

(2), (3) $\Rightarrow$ (1) Each of (2) and (3) gives $\mathrm{Fitt}_r(M)R_\mathfrak{p} = R_\mathfrak{p}$ and, if $r \geq 1$, $\mathrm{Fitt}_{r-1}(M)R_\mathfrak{p} = 0$ for every prime $\mathfrak{p}$. Under (3) this is proposition 30.5.3(2) for $R \to R_\mathfrak{p}$, as $M_\mathfrak{p} \cong R_\mathfrak{p} \otimes_R M$ (proposition 23.4.10), together with proposition 30.5.3(1) for the free module $R_\mathfrak{p}^r$. Under (2), choose j with $f_j \notin \mathfrak{p}$, which exists because the f_j generate the unit ideal. The same argument over R_{f_j} gives $\mathrm{Fitt}_r(M)R_{f_j} = R_{f_j}$ and $\mathrm{Fitt}_{r-1}(M)R_{f_j} = 0$, and extending these ideals along the map $R_{f_j} \to R_\mathfrak{p}$, which exists by theorem 23.4.1 because f_j is a unit in $R_\mathfrak{p}$, gives the claim.

Now let J be an ideal of R. Localization is exact (proposition 23.4.9), so $J_\mathfrak{p} \to R_\mathfrak{p}$ is injective with image $JR_\mathfrak{p}$, and $(R/J)_\mathfrak{p} \cong R_\mathfrak{p}/JR_\mathfrak{p}$. If $JR_\mathfrak{p} = 0$ for every prime $\mathfrak{p}$, then $J_\mathfrak{p} = 0$ for every $\mathfrak{p}$, and $J = 0$ by proposition 23.4.13. If $JR_\mathfrak{p} = R_\mathfrak{p}$ for every $\mathfrak{p}$, then $(R/J)_\mathfrak{p} = 0$ for every $\mathfrak{p}$, so $R/J = 0$ by the same proposition, and $J = R$. Applied to $J = \mathrm{Fitt}_{r-1}(M)$ and to $J = \mathrm{Fitt}_r(M)$, this gives (1).

Corollary 30.5.6: Local Freeness over a Reduced Ring

Let R be a reduced ring, that is $\mathrm{Nil}(R) = 0$, let M be a finitely presented R-module, and let $r \geq 0$. Then M is locally free of rank r iff the minimal number of generators of $M_\mathfrak{p}$ is r for every prime $\mathfrak{p}$.

***Proof*:**
By proposition 30.5.3(4), the minimal number of generators of $M_\mathfrak{p}$ is r iff $\mathrm{Fitt}_r(M) \not\subseteq \mathfrak{p}$ and, when $r \geq 1$, $\mathrm{Fitt}_{r-1}(M) \subseteq \mathfrak{p}$. If M is locally free of rank r, then proposition 30.5.5(1) gives both for every prime $\mathfrak{p}$. Conversely, suppose both hold for every prime $\mathfrak{p}$. A proper ideal lies in a maximal ideal (proposition 9.4.18), which is prime (corollary 9.4.26), so $\mathrm{Fitt}_r(M) = R$. If $r \geq 1$, then $\mathrm{Fitt}_{r-1}(M)$ lies in every prime, hence in $\mathrm{Nil}(R) = 0$ (theorem 24.1.2). So proposition 30.5.5(1) holds, and M is locally free of rank r.

Reducedness cannot be dropped from corollary 30.5.6. The local ring $R = k[\epsilon]/(\epsilon^2)$, for a field k, has the single prime $\mathfrak{p} = (\epsilon)$, and the module $M = R/(\epsilon)$ has $M_\mathfrak{p} \cong M \cong k$, which needs exactly one generator. But M is presented by $R \xrightarrow{\epsilon} R$, so $\mathrm{Fitt}_0(M) = (\epsilon) \neq 0$, and M is not locally free of rank 1 by proposition 30.5.5.

By proposition 30.5.3(2) and proposition 30.5.5, for a ring map $R \to R'$ the module $M \otimes_R R'$ is locally free of rank r iff $\mathrm{Fitt}_r(M)R' = R'$ and, if $r \geq 1$, $\mathrm{Fitt}_{r-1}(M)R' = 0$. In this form, compatible with base change, the criterion is what [37] uses to construct the flattening stratification, and from it the Quot and Hilbert schemes.

30.6 Generic Flatness

Away from a proper closed subset of the base, a coherent family becomes flat. This Grothendieck finiteness underlies dimension counts in families and the construction of moduli.

Theorem 30.6.1: Generic Flatness

Let R be a Noetherian integral domain, S a finitely generated R-algebra, and M a finitely generated S-module. Then there is a nonzero $f \in R$ such that M_f is a free R_f-module (in particular flat over R_f).

***Proof*:**
We sketch the standard argument (Eisenbud, *Commutative Algebra*, Theorem 14.4; equivalently the Stacks Project generic-flatness lemma). By dévissage a finite filtration of M with quotients $S/\mathfrak{p}_i$ ($\mathfrak{p}_i \subseteq S$ prime) reduces the claim to $M = S/\mathfrak{p}$, since a module filtered by pieces that are free after localizing is itself free after localizing. If $\mathfrak{q} := \ker(R \to S/\mathfrak{p})$ is nonzero, then $\mathfrak{q}$ annihilates M, so $M_f = 0$ is free for any $0 \neq f \in \mathfrak{q}$. Otherwise $R \hookrightarrow S/\mathfrak{p}$ is a domain of finite type over R; by Noether normalization $(S/\mathfrak{p}) \otimes_R K$ is a *finite* module (not in general free) over a polynomial ring $K[t_1, \dots, t_d]$, where $K = \mathrm{Frac}(R)$, and spreading out gives $0 \neq f_0$ with S_{f_0} finite over $R_{f_0}[t_1, \dots, t_d]$. A Noetherian induction on the relative dimension d then trivializes, after inverting finitely many further elements of R, the torsion pieces of this finite module, producing a single f with M_f free over R_f.

Part VI

Affine Varieties

A shape cut out by polynomial equations is determined by the polynomial functions on it. This Part makes that statement into a dictionary: to each algebraic set in affine space is attached a ring, its coordinate ring, and the geometry of the set is recoverable from the algebra of the ring. Points become maximal ideals, irreducible subsets become primes, and the maps between varieties become homomorphisms between the rings. The dictionary is global: every entry in it is an invariant of the whole variety, and Part VII takes up the invariants attached to a single point.

The ground field is algebraically closed throughout, from chapter 32 onward; the Nullstellensatz, which is what makes the dictionary exact rather than approximate, is false without it. The commutative algebra the Part rests on is cited to *Commutative Algebra* [20] rather than rebuilt.

31

Algebraic Sets and the Zariski Topology

The dictionary this book is about begins with a single construction: to a set of polynomials, associate the points at which they all vanish. This chapter sets up that construction and its converse, which sends a set of points to the polynomials vanishing on it, and finds that the two are almost inverse to each other. The gap between "almost" and "exactly" is what chapter 32 closes.

Along the way the vanishing sets turn out to be the closed sets of a topology, the Zariski topology, which is coarse enough to be unlike any topology from analysis and fine enough to carry the whole theory. The chapter ends with the maps that respect it.

31.1 Affine Space and Regular Functions

In this whole chapter, R is a commutative ring and k be a field.

So far when polynomials were encountered, they were treated as a commutative ring with an indeterminate extension (or equivalently, they can be thought of as a ring over a free monoid). There is a natural way of thinking about any such polynomial as a function (which is probably how most first encounter polynomials): if $f \in k[x_1, x_2, ..., x_n]$, then if $(a_1, a_2, ..., a_n) \in k^n$, let $f(a_1, a_2, ..., a_n) \in k$ be the element which you get when replacing each x_i with a_i. Then we can make f into a function

through the following map[1,2]:

$$k[x_1, ..., x_n] \to \text{Hom}_{\mathbf{Set}}(k^n, k) \qquad f \mapsto ((a_1, ...a_n) \mapsto f(a_1, ..., a_n)) \tag{31.1}$$

where we shall consider the constants $c \in k[x_1, ..., x_n]$ to map to the functions that shall return the value of $c \in k$:

$$c \mapsto ((a_1, ..., a_n) \mapsto c)$$

Note that the codomain of the function in (31.1) is be the hom-set over the category **Set**, and not any other category we have extensively worked over so far (**Grp**, **Ring**, **Alg**, etc.); this was done since there are many non-linear functions representing non-linear polynomials (a simple example would be $x^2 \in k[x]$). On the other hand, the image of the above function is not just a collection of all set functions as they must all satisfy polynomials relations (can you find a set-function that is not given/representable by a polynomial?[3] The subset given by the function in (31.1) shall be called the set of *regular functions*: $\text{Hom}_{\mathbf{Reg}}(k^n, k)$. Before properly boxing this definition, we shall take some more time pondering what the domain of the hom-set should be, namely we shall want the domain to represent Cartesian space without the extra algebraic structure that is usually implied by the notation k^n. For example, k^n usually denotes the n-dimensional vector-space over k with an origin, and more generally we think of k^n as having addition and scalar multiplication satisfying the axioms of a vector-space. Vector-spaces are "defined" for linear polynomials, with subspaces that are naturally "linear" (recall that subspaces are given by solutions of linear polynomials, see theorem 13.2.28)[4]. We shall want a new type of space for which subspaces are solutions to general polynomial equations.

Definition 31.1.1: Affine Space

Let $(k, +, \cdot)$ be any field. Then the collection of the n-tuples of k^n as a set shall be called *affine space*. Its elements shall be called *points* and the space shall be denoted $\mathbb{A}^n_k$.

Hence, a field can be thought of as $(\mathbb{A}^1_k, +, \cdot)$. The space $\mathbb{A}^n_k$ is called *affine* space rather than just "space" as there shall be an equally important (or arguably more important) space called *projective space* that shall be introduced in chapter 38[5]. The term affine can also be thought of as emphasizing the lack of importance of the origin (recall that a linear transformation that does not need to map the origin to itself was called affine).

With affine space established, let us now define the image of the function in (31.1):

[1] For those familiar with algebraic geometry, this map can be thought of as selecting the global sections of $\mathbb{A}^n_k$. By the Nullstellensatz, $k^n = \text{Spec}\,(k[x_1, .., x_n])$, and by the representability of affine schemes $\Gamma(\text{Spec}\,(R)) \cong \text{Hom}_{\text{Reg}}(\text{Spec}\,(R), A^1_k)$

[2] advanced comment: if k is not algebraically closed, we are missing points, and hence this technically is *not* a representable functor and is not the sheaf obtains from embedding Var_k into $\mathbf{Sch}_k$

[3] Over finite fields, and only over finite fields, every set function is given by a polynomial: interpolate, using that $a^{|k|} = a$ for every $a \in k$.

[4] In [41], we shall show that the vector-space structure can be recovered using Hopf Algebras, but this adds more structure to the algebraic set

[5] More generally, we shall see that affine space will be the representation space for schemes which generalizes affine space, something which chapter 49 points the reader toward

Definition 31.1.2: Regular Function [on Affine Space]

Let F represent the function in (31.1):

$$F : k[x_1, ..., x_n] \to \text{Hom}_{\mathbf{Set}}(k^n, k) \qquad f \mapsto ((a_1, ...a_n) \mapsto f(a_1, ..., a_n))$$

Then the collection $\text{im}(F)$ is called the *regular functions*, and is usually denoted $\Gamma(\mathbb{A}^n_k)$, $k[\mathbb{A}^n_k]$, or $\text{Hom}_{\mathbf{Reg}}(\mathbb{A}^n_k, \mathbb{A}^1_k)$.

Each of these notations for the collection of regular functions have its use. The $\text{Hom}_{\mathbf{Reg}}(\mathbb{A}^n_k, \mathbb{A}^1_k)$ notion makes it clear what the domain and codomain is, which shall be particularly important once we take different codomain. The $k[\mathbb{A}^n_k]$ notation is particularly useful when we shall take subsets $V \subseteq \mathbb{A}^n_k$ and denote all regular functions on V as $k[V]$; in this case this notation emphasizes that we are working over the particular field k. This shall be useful for there are circumstances where we change which field we are working over[6]. The $\Gamma(\mathbb{A}^n_k)$ notation comes from modern algebraic geometry where gamma is used hint that these are the *global section* over $\mathbb{A}^n_k$ (see [13] for a full explanation). As this chapter is gearing up the reader for modern algebraic geometry, we shall preferentially use the $\Gamma(\mathbb{A}^n_k)$ notation to acclimate the reader. It should be pointed out that another common notation is $\mathcal{O}_{\mathbb{A}^n_k}(\mathbb{A}^n_k)$ which is more useful when it is important to keep track of regular functions on open subsets of $\mathbb{A}^n_k$ (once we define a topology on $\mathbb{A}^n_k$) in which case we shall have the collection of regular function on $U \subseteq \mathbb{A}^n_k$ be written as $\mathcal{O}_{\mathbb{A}^n_k}(U)$. This is not useful to us in this chapter, and so shall not be used.

The set $\Gamma(\mathbb{A}^n_k)$ forms a natural k-algebra structure given by point-wise operations:

$$f + g \equiv f(a) + g(a) \qquad fg \equiv f(a)g(a) \qquad c \cdot f = cf(a) \qquad \forall a \in k \tag{31.2}$$

With this k-algebra structure, it can be shown that $k[x_1, ..., x_n] \cong_k \text{Hom}_{\mathbf{Reg}}(\mathbb{A}^n_k, \mathbb{A}^1_k)$, and so the two sets are often used interchangeably. If the distinction needs to be made clear between the element x_i and the function x_i, we shall write

$$k[X_1, ..., X_n] = \text{Hom}_{\mathbf{Reg}}(\mathbb{A}^n_k, \mathbb{A}^1_k) = k[\mathbb{A}^k_n]$$

where each X_i is a regular function that is the projection onto the ith coordinate, and call an element of $k[X_1, ..., X_n]$ a *polynomial function* or *polynomial map*. This distinction shall become more important once there can be multiple polynomials that will be associated to the same regular function, which shall be the case in section 32.1. When it is clear from context, we may denote a polynomial or a regular function by $f(x)$ and $f(X)$ respectively where x is understood to be the indeterminate variables and X is understood to be the regular functions $X_1, ..., X_n$.

Due to this isomorphism, we can define a function from $k[x_1, ..., x_n]$ to k directly by directly substituting the values for the indeterminates with a point in the affine space. Namely, for each $a \in \mathbb{A}^n_k$, we take:

$$\text{ev}^k_a : k[x_1, ..., x_n] \to k \qquad f(x) \mapsto f(a)$$

where x and a is understood to be n-tuples of indeterminates and values respectively. These are all k-algebra homomorphisms, for

$$\text{ev}^k_a(f(x) + cg(x)) = \text{ev}^k_a(f(x)) + c \cdot \text{ev}^k_a(g(x)) \qquad \text{ev}^k_a(f(x)g(x)) = \text{ev}^k_a(f(x)\text{ev}^k_a(g(x))$$

[6] A good example of the use of group cohomology is measure how much an isomorphism $k[V] \cong k[W]$ is preserved/fails when consider $\overline{k}[V]$ and $\overline{k}[W]$

The subscript of the evaluation function represents the point of evaluation, while the superscript represents the values we choose to plug for every indeterminate, where the values are usually the same as the base field, however they may differ, for example it is common to take $\mathbb{Z}$ or $\mathbb{Q}$[7]. Thus, a regular function can be thought of as the collection of evaluation functions on a polynomial.

31.1.3 Foreshadowing If you know elementary analysis or calculus, then you are probably aware that the types of functions we most commonly use are *continuous*. Continuous functions are a very important tool in analysing the properties of the space we are studying (ex. $\mathbb{R}$, $\mathbb{R}^n$, $L^2(\mathbb{R})$, etc.), continuous functions can be thought of as the natural types of functions that preserve some local properties of the space. In Algebra, we can think of polynomial functions as the natural types of functions. This comparison between continuous functions mapping to $\mathbb{R}$ and polynomial functions mapping to k will in fact be incredibly precise, as we will see in the last section of this chapter.

31.2 Algebraic Sets and Vanishing Ideals

31.2.1 Quick Side-Note A common misconception, born from a strong reliance on graphs in most first-year undergraduate calculus/analysis classes, is to intuitively associate the zero-set of a function with the *graph* of a function.
For example, $f(x) = x$ has a zero-set containing only the point 0, while the function $F(x, y) = x - y$ has a zero-set that forms the graph $\Gamma(f)$. This distinction may seem trivial, but it is surprisingly easy to conflate the two concepts when moving into higher dimensions.

Graphs can be thought of as the collection of the solutions of $f(x_1, \ldots, x_n) = y_0$ as the constant term y_0 varies.

From such polynomials functions, we can create many interesting shapes depending on the zeros', or locus, of polynomial:

[7] These shall be called $\mathbb{Z}$-valued and $\mathbb{Q}$-valued points of the polynomial, or more precisely the variety (as we shall soon see)





Figure 31.1: Circle represented by the equation $x^2 + y^2 - 1 = 0$


Example 31.2.2: Zeros' of Polynomials

1. The polynomial $x^2 + y^2 - 1 \in \mathbb{R}[x, y]$ gives the circle of fig. 31.1. More precisely, the polynomial shall be associated to an element of $\Gamma(\mathbb{A}^n_k)$, where plugin in any point on from $\mathbb{A}^2_{\mathbb{R}}$ that is on the circle (ex. $(1, 0)$ or $(\sqrt{2}/2, \sqrt{2}/2)$ shall give 0.

2. Take $y - x^2 \in \mathbb{R}[x, y]$. Then this shall give the usual parabola $y = x^2$. If we take $x - y^2 \in \mathbb{R}[x, y]$, we shall get a parabola rotated 90 degree's (or $\pi/2$ radians) clockwise. If we take the polynomial $(y - x^2)(x - y^2) \in \mathbb{R}[x, y]$, then the zero set of this new polynomial shall be the zero-set of the two multiplied polynomials:



3. Take $(x^2+y^2)^2-(x^2-y^2) \in \mathbb{R}[x,y]$. This shape is called the *Bernoulli Lemniscate*:




   Notice that the shape crosses over itself. This shows that zero-sets of polynomials differ from graphs, and also differ from the usual smooth manifolds from differential geometry.

4. Take $p(x) \in k[x]$ over any field k. Then the shape associated to $p(x)$ are the *roots* of the polynomials. For example, taking $x^2-2 \in \mathbb{Q}(\sqrt{2})[x]$ shall give $\{\sqrt{2},-\sqrt{2}\} \subseteq \mathbb{A}^1_{\mathbb{Q}(\sqrt{2})}$ as these are the solution to $x^2-2=0$. More generally, the shape given by a polynomial in one variable is always the collection of roots that is present in the underlying field. This means that $x^2-2 \in \mathbb{Q}[x]$ would give the empty set, as there are no rational roots. By the fundamental theorem of algebra, any polynomial $p(x) \in \mathbb{C}[x]$ of degree d shall have d roots, and hence the shape associated to $p(x)$ shall have d points.


5. Take $x^2+y^2+z^2-1 \in \mathbb{R}[x,y,z]$. Then this is the classical unit sphere centered at the origin:

$$x^2 + y^2 + z^2 = 1$$




What polynomial would you choose to center the unit sphere at different points of $\mathbb{A}^3_{\mathbb{R}}$? How would you change the radius of the sphere?

6. Let us now consider taking two shapes: the sphere given by $x^2 + y^2 + z^2 - 4$ and the hyperboloid given by $x^2 + y^2 - z^2 - 1$. The hyperboloid looks like so:




Then the intersection of these two shapes shall produce two circles, visualized like so:



This produce *two disconnected components* (in the usual euclidean topology). We shall show later that no single polynomial can create these two circles, hence we shall often have the case where we get interesting shapes by interesting or taking the union of two zero-sets.

7. The following is an infamous example of a shape that looks like it could be the zero-set of a single polynomial, but cannot be: consider the following shape given by $t \mapsto (t, t^2, t^3)$:



It can be proven that this shape is *not* the zero-set of a single polynomial $p(x, y, z) \in k[x, y, z]$. On the other hand, this shape, is the intersection of two zero-sets of the surfaces $y = x^2$ and $z = xy$. This shape is called the *twisted cubic*.

More generally, given any polynomial in $k[x_1, x_2, ..., x_n]$, we can associate with it a geometric shape based on its zero set!

Definition 31.2.3: [Affine] Algebraic Set

Let $\mathbb{A}^n$ be an affine n-space over a field k, and let $S \subseteq \Gamma(\mathbb{A}^n)$. Then:

$$\mathcal{Z}(S) \subseteq \mathbb{A}^n \quad \mathcal{Z}(S) := \{(a_1, a_2, ..., a_n) \mid f(a_1, a_2, ..., a_n) = 0, \text{ for all } f \in S\}$$

If for $V \subseteq \mathbb{A}^n$, there exists an $S \subseteq \Gamma(\mathbb{A}^n)$ such that $V = \mathcal{Z}(S)$, then V is called an *affine algebraic set*, *locus*, or *zero set*. If it is unambiguous, the set may be called an *algebraic set*[a].

[a] In some textbooks, this set is called a *variety*. The term variety shall be reserved for definition 32.3.1

From now on, when taking a subset of $\mathbb{A}^n$, $A \subseteq \mathbb{A}^n$, it will be assumed that A is an algebraic set unless specified otherwise (i.e. it would be stated "for some subset $A \subseteq \mathbb{A}^n$)

Example 31.2.4: Affine Algebraic Sets

All the above are algebraic sets. Let's go over a few more examples:

1. If $n = 1$, then the zeros of a polynomial are always points, that is, the roots of the polynomial. When k is infinite the only polynomial with infinitely many zeros is 0 (more precisely, the regular function associated to 0), which has all of k as its vanishing locus. Infiniteness is the right hypothesis rather than characteristic 0: item (5) below exhibits the failure over $\mathbb{F}_2$, while $\overline{\mathbb{F}_p}$ has characteristic p and the claim still holds there. Furthermore, the polynomial 1 vanishes nowhere, and hence the corresponding algebraic set is $\emptyset$. Therefore, in $\mathbb{A}^1$, the affine sets are

   $$\emptyset \qquad \text{finite sets} \qquad k$$

   This also shows that not all sets are algebraic sets (for example, if $k = \mathbb{R}$, then $[0, 1]$ is not an algebraic set in $\mathbb{A}^1_{\mathbb{R}}$)

2. If $n = 2$, Then take $f \in \Gamma(\mathbb{A}^2)$ such that $f(x, y) = x^2 + y^2 - 1$. Then

   $$\mathcal{Z}(f) = \left\{(x, y) \in \mathbb{A}^2 \;\middle|\; x^2 + y^2 = 1\right\}$$

   If $k = \mathbb{R}$, then $\mathcal{Z}(f)$ is infinite, so it is not a product of two algebraic subsets of $\mathbb{A}^1$: those are finite or all of $\mathbb{A}^1$, and neither product is a circle.

   Furthermore, this examples shows that there are lot's more zero sets in $\mathbb{A}^2$ than there are in $\mathbb{A}^1 \times \mathbb{A}^1$. This is in stark contrast to how every element in the vector space $\mathbb{R}^2$ can be written as an element in $\mathbb{R}$ and an element in $\mathbb{R}$, i.e. $\mathbb{R}^2 \cong \mathbb{R} \times \mathbb{R}$ as vector spaces.

3. For any $\mathbb{A}^n$, can you always find a set of functions $F \subseteq \Gamma(\mathbb{A}^n)$ such that $|V(F)| = 1$ (i.e. is every singleton an algebraic set for every $\mathbb{A}^n$ over any field?) This shall be answered in section 32.4.

4. What is the vanishing set of linear polynomials?

5. In the first example, we produced the entire space using the zero polynomial. Is it necessary that we use the zero-polynomial to make the zero set the entire space? The answer is no: simply take $k = \mathbb{Z}/2\mathbb{Z}$ and $p(x) = x^2 + x$. However, this is a problem exclusive to finite fields. Can you prove that if k is an infinite field, $p \in k[x_1, x_2, ..., x_n]$ and $p(a_1, a_2, ..., a_n) = 0$ for all $a_i \in k$ then $p \equiv 0$? Freely use that a nonzero one-variable polynomial has finitely many roots, and induct on the number of variables.

6. Let k be a finite field and take any subset $S \subseteq \mathbb{A}^n_k$. Show that S is always an algebraic set. Hence, being algebraic gives no additional information in the finite case.

7. Let $f \in k[x_1, x_2, ..., x_n]$. Then $\mathcal{Z}(f)$ is called a *hyper-surface*. For example $S^1 = \mathcal{Z}(x^2 + y^2 - r^2)$ represents a circle of radius r. Another example would be $\mathcal{Z}(xy - 1)$ which represents the hyperbola $y = 1/x$. More generally, any conic section is a hyper-surface. In higher dimensions, $\mathcal{Z}(x^2 + y^2/4 + z^2/9 - 1)$ represents an ellipsoid in $\mathbb{R}^3$. The twisted cubic is *not* a hyper-surface.

8. For any polynomial function $f : k \to k$, we can define $F : k^2 \to k$ where $F(x, y) = f(x) - y$. Then $\mathcal{Z}(F)$ consists of all points where $f(x) - y = 0$, i.e. $f(x) = y$, which is the pair of points $\{(a, b) \mid f(a) = b\}$, i.e. the graph of f! More generally, if $f : k^n \to k$ is a polynomial, the polynomial $F : k^{2n} \to k$ gives rise to the polynomial $F : (x, y) = f(x) - y$ whose zero set is the graph of f (recall the convention that x, y represent multiple variables when it is clear from context).

Proposition 31.2.5: Properties of Affine Algebraic Sets

Let $S, T \subseteq \Gamma(\mathbb{A}^n)$. Then

1. If $S \subseteq T$ then $\mathcal{Z}(T) \subseteq \mathcal{Z}(S)$ (i.e. $\mathcal{Z}$ is *contravariant* in respect to inclusion)

2. If $(S) = I \subseteq \Gamma(\mathbb{A}^n)$ is the ideal of S, then $\mathcal{Z}(I) = \mathcal{Z}(S)$.

3. For any arbitrary collection of algebraic sets $\{S_i\}_{i \in I}$,

$$\bigcap_{i \in I} \mathcal{Z}(S_i) = \mathcal{Z}\left(\bigcup_{i \in I} S_i\right)$$

   that is, the arbitrary intersection of algebraic sets is an algebraic sets, and is equal to the algebraic set of the intersections of the $\{S_i\}_{i \in I}$

4. For any finite collection of algebraic sets $\{S_i\}_{i=1}^n$,

$$\bigcup_{i=1}^{n} \mathcal{Z}(S_i) = \mathcal{Z}\left(\prod_{i=1}^{n} S_i\right)$$

   that is, the finite union of algebraic sets is an algebraic set, and is equal to the product of the S_i as ideals (from part 2, we can assume $(S_i) = S_i$ without loss of generality).

5. If $0, 1 \in \Gamma(\mathbb{A}^n)$ denote the zero and constant function, then

$$\mathcal{Z}(0) = \mathbb{A}^n \qquad \mathbb{Z}(1) = \emptyset$$

6. If I is an ideal of $\Gamma(\mathbb{A}^n)$, then

$$\mathcal{Z}(I) = \mathcal{Z}(I^m) \ \forall m \in \mathbb{N}_{>0}$$

   that is, $\mathcal{Z}$ is invariant to taking higher powers of the ideals

These are all straight-forwards proofs, and so should all be done before reading these proofs for the best learning experience.

***Proof*:**

1. Let $S \subseteq T$, and consider $x \in \mathcal{Z}(T)$. Then $f(x) = 0$ for every $f \in T$. Since $S \subseteq T$, in particular $g(x) = 0$ for every $g \in S$. Thus $x \in \mathcal{Z}(S)$, establishing $\mathcal{Z}(T) \subseteq \mathcal{Z}(S)$.

2. Let $S \subseteq \Gamma(\mathbb{A}^n)$ be any set and let $I = (S)$. We want to show that $\mathcal{Z}(I) = \mathcal{Z}(S)$. Since $S \subseteq I$, the $\mathcal{Z}(I) \subseteq \mathcal{Z}(S)$ conclusion comes from the first part. For the reverse, consider $x\mathcal{Z}(S)$. Then for all $t \in S$, $t(x) = 0$. If we pick any two $f, g \in S$, then $(f+g)(x) = f(x)+g(x) = 0$. If we pick any $c(x) \in \Gamma(\mathbb{A}^n)$ and any $f \in S$, then $(cf)(x) = c(x)f(x) = c(x)0 = 0$. Thus, if we enlarge S to be closed under addition and multiplication by elements of $k[\mathbb{A}^n]$, those polynomial will also be zero on x, and so $\mathcal{Z}(S) \subseteq \mathcal{Z}(I)$, establishing $\mathcal{Z}(S) = \mathcal{Z}(I)$

3. We want to show that $\bigcap_{i\in I} \mathcal{Z}(S_i) = \mathcal{Z}\left(\bigcup_{i\in I} S_i\right)$ for an arbitrary indexing set I. This is just some set theory: by definition:

$$x \in \mathcal{Z}(\cup_{i\in I} S_i) = \{y \in \mathbb{A}^n \mid f(y) = 0,\ \forall f \in \cup_{i\in I} S_i\} = \mathcal{Z}\left(\sum_\alpha I_\alpha\right)$$

   which is true if and only if x is the solution for polynomials in every set S_i. The collection of such elements is:

$$\bigcap_{i\in I} \mathcal{Z}(S_i)$$

4. We want to show that $\bigcup_{i=1}^n \mathcal{Z}(S_i) = \mathcal{Z}\left(\prod_{i=1}^n S_i\right)$. By definition:

$$x \in \mathcal{Z}\left(\prod_{i=1}^n S_i\right) = \left\{ y \in \mathbb{A}^n \;\middle|\; f(y) = 0\ \forall f \in \prod_{i=1}^n S_i \right\}$$

   where by definition $f(x) = \sum_{j=1}^m (f_{1_j} f_{2_j} \cdots f_{n_j})(x) = \sum_{j=1}^m f_{1_j}(x) f_{2_j}(x) \cdots f_{n_j}(x) = 0$. Notice that for a particular term in the sum to be zero, we only need on of the f_{i_j} to be zero. Therefore, the sum is zero if and only if one polynomial in every term of the sum is zero. Since this also applies to sums with only one term in it, then if x is the solution to one polynomial in S_i, then it will be part of the zero's of $\prod_{i=1}^n S_i$. But this is just another way of saying:

$$x \in \bigcup_{i=1}^n \mathcal{Z}(S_i)$$

5. Notice that $0(x) = 0$ for all $x \in \mathbb{A}^n$ and $1(x) = 1 \neq 0$ for all $x \in \mathbb{A}^n$, and so

$$\mathcal{Z}(0) = \mathbb{A}^n \qquad \mathcal{Z}(1) = \emptyset$$

6. Since $I^m \subseteq I$, the first part gives $\mathcal{Z}(I) \subseteq \mathcal{Z}(I^m)$. For the reverse inclusion, let $x \in \mathcal{Z}(I^m)$ and let $f \in I$ be arbitrary. Then f^m is a product of m elements of I, so $f^m \in I^m$, and therefore

$$f(x)^m = f^m(x) = 0$$

   As k is a field it has no nonzero nilpotents, so $f(x) = 0$. Since $f \in I$ was arbitrary, $x \in \mathcal{Z}(I)$, giving $\mathcal{Z}(I^m) \subseteq \mathcal{Z}(I)$ and hence $\mathcal{Z}(I) = \mathcal{Z}(I^m)$, as we sought to show.

A couple of remarks are in order. From (2), we can without loss of generality restrict $\mathcal{Z}$ be a function from the ideals of $k[x_1, ..., x_n]$ to the algebraic sets in $\mathbb{A}^n$:

$$\mathcal{Z} : \{\text{ideals in } k[x_1, ..., x_n]\} \to \{\text{affine algebraic sets in } \mathbb{A}^n\}$$

Furthermore, $\mathcal{Z}$ is a surjection from the ideals of $k[x_1, x_2, ..., x_n]$ and the algebraic sets (the ideals I^m for each $m \geq 1$ map to the same algebraic set). Next, the finiteness condition on the product of ideals is a necessary condition for closure of algebraic sets:

Example 31.2.6: Not Closed Under Arbitrary Unions

Take $\mathbb{A}^1_{\mathbb{R}}$ and the sets $V(x - a)$ for $a \in \mathbb{Z}$. Then prove that the union of these sets is *not* an algebraic set (you may freely use the fact that polynomials have at most finite roots, and recall that $\mathbb{R}[x]$ is Noetherian).

Next, we took the product of ideal $\prod_i^n I_i$ instead of the intersection. Since it always the case that $IJ \subseteq I \cap J$ then in the cases where $IJ \subsetneq I \cap J$, $\mathcal{Z}(I \cap J) \subsetneq \mathcal{Z}(I) \cup \mathcal{Z}(J)$[8]. However, since $\mathcal{Z}(I^2) = \mathcal{Z}(I)$, the distinction is invisible to $\mathcal{Z}$, and $\mathcal{Z}(IJ) = \mathcal{Z}(I \cap J)$ always

Perhaps most importantly for this chapter, notice that these properties are the properties of a topology (see [39, Topological Space]):

Definition 31.2.7: Zariski Topology

Let $\mathbb{A}^n$ be an n-affine space over k. Then the set

$$\mathcal{T}_{\mathcal{Z}} = \{\mathcal{Z}(I) \mid \text{I is an ideal of } \Gamma(\mathbb{A}^n)\}$$

from the set of closed sets in the *Zariski topology* $(\mathbb{A}^n, \mathcal{T}_{\mathcal{Z}})$

We can therefore try and study this topological space! This is essentially the foundation for studying geometrical concepts in algebra, and vice-versa, it is the foundation for studying algebraic concepts in geometry, and so we will spend a lot of time establishing the link between the ideals of $\Gamma(\mathbb{A}^n)$ and the Zariski topology.

Before such topological considerations, we shall first see if we can find some function that is the inverse of $\mathcal{Z}$, that is we start from an algebraic set in $\mathbb{A}^n$ (or more generally any subset of $\mathbb{A}^n$) and associate it to an ideal in $\Gamma(\mathbb{A}^n)$, letting us strive towards some way of corresponding the two in a manner similar to Galois Theory[9]. Towards the goal of finding an inverse for $\mathcal{Z}$, notice that we already have that $\mathcal{Z}$ is a surjection of ideals of $\Gamma(\mathbb{A}^n)$ to the algebraic sets. Thus, it is meaningful to ask about having a function from the set of algebraic sets to the set of ideals of $k[x_1, x_2, ..., x_n]$. To understand this question, we start off with a slightly more general question (just like we started with subsets of $k[x_1, ..., x_n]$ instead of ideals):

[8]The condition $IJ = I \cap J$ is more delicate than it looks: it holds exactly when $\text{Tor}_1^R(R/I, R/J) = 0$, for which see [29].

[9]In fact,the order reversing nature of this correspondence will end up making this correspondence a *Galois correspondence*, which name is inspired by how the Galois correspondence between intermediate fields and subgroups was one of the first well-known order-reversing correspondences

Definition 31.2.8: Vanishing Ideal

Let $V \subseteq \mathbb{A}^n$ be a subset of the affine n-space. Then

$$\mathcal{I}(V) := \{f \in \Gamma(\mathbb{A}^n) \mid f(v) = 0,\ \forall v \in V\}$$

is the *vanishing ideal* of V.

Notice that $\mathcal{I}(V)$ was not defined as an ideal, however it is indeed an ideal; it is important for the sake of intuition that the reader should prove this at least once. Even better, $\mathcal{I}(V)$ is the *largest* ideal of $\Gamma(\mathbb{A}^n)$ that corresponds to the set V. Just like $\mathcal{Z}$, $\mathcal{I}$ can be interpreted as a function

$$\mathcal{I} : \{V \subseteq \mathbb{A}^n_k\} \to \{\text{ideals of } \Gamma(\mathbb{A}^n)\}$$

Example 31.2.9: Vanishing Ideal

1. Let $\mathbb{A}^2$ be an affine space over the field $\mathbb{R}$ and let $X \subseteq \mathbb{A}^2$ be the x-axis. Then $\mathcal{I}(X) = (y) \subseteq \mathbb{R}[x, y]$
2. Let k be infinite. Then $\mathcal{I}(\mathbb{A}^n) = 0$.
3. Find the vanishing ideals if of subsets $\mathbb{A}^n_k$ if k is finite.

Just like $\mathcal{Z}$, $\mathcal{I}$ shares similar properties:

Proposition 31.2.10: Properties of Vanishing Ideals

let $A, B \subseteq \mathbb{A}^n$ be two algebraic sets. Then

1. If $A \subseteq B$, then $\mathcal{I}(B) \subseteq \mathcal{I}(A)$ (i.e. $\mathcal{I}$ is *contravariant* with respect to inclusion)
2. $\mathcal{I}(A \cup B) = \mathcal{I}(A) \cap \mathcal{I}(B)$
3. $\mathcal{I}(\emptyset) = \Gamma(\mathbb{A}^n)$. If k is infinite, $\mathcal{I}(\mathbb{A}^n) = 0$

***Proof*:**

1. Let $A \subseteq B$ and take $f \in \mathcal{I}(B)$, so $f(b) = 0$ for every $b \in B$. Every $a \in A$ lies in B, so $f(a) = 0$, giving $f \in \mathcal{I}(A)$.
2. A polynomial vanishes on $A \cup B$ exactly when it vanishes on A and vanishes on B, which is the assertion $\mathcal{I}(A \cup B) = \mathcal{I}(A) \cap \mathcal{I}(B)$.
3. The condition defining $\mathcal{I}(\emptyset)$ is vacuous, so every polynomial belongs to it and $\mathcal{I}(\emptyset) = \Gamma(\mathbb{A}^n)$. For the second claim, suppose k is infinite and f vanishes at every point of $\mathbb{A}^n$. Induct on n. For $n = 1$ a nonzero polynomial has at most $\deg f$ roots, while k is infinite, so $f = 0$. For $n > 1$ write $f = \sum_i g_i(x_1, \ldots, x_{n-1}) x_n^i$. Fixing any $a \in k^{n-1}$ makes $f(a, x_n)$ a one-variable polynomial vanishing on all of k, so each $g_i(a) = 0$ by the base case. As a was arbitrary, each g_i vanishes on $\mathbb{A}^{n-1}$, and by induction $g_i = 0$. Hence $f = 0$, so $\mathcal{I}(\mathbb{A}^n) = 0$, as we sought to show.

The hypothesis that k be infinite in (3) is not removable: over $\mathbb{F}_q$ the polynomial $x^q - x$ vanishes at every point of $\mathbb{A}^1$, so $\mathcal{I}(\mathbb{A}^1_{\mathbb{F}_q}) \neq 0$.

Notice that we have omitted showing what $\mathcal{I}(A \cap B)$ is. One problem is that $\mathcal{I}(A) \cup \mathcal{I}(B)$ is not necessarily an ideal (since the union of two ideals is not necessarily an ideal). It might be tempting to say that since

$$\langle \mathcal{I}(A) \cup \mathcal{I}(B) \rangle = \mathcal{I}(A) + \mathcal{I}(B)$$

we can conclude that:

$$\mathcal{I}(A \cap B) = \mathcal{I}(A) + \mathcal{I}(B)$$

However, this is not generally the case (consider the algebraic sets given by the ideals $(x^2 - y)$ and (x)). Proving the reverse inclusion needs the Nullstellensatz, but it can already be shown from the definitions that $\mathcal{I}(A \cap B) \supseteq \mathcal{I}(A) + \mathcal{I}(B)$, since a function vanishing on A or on B vanishes on $A \cap B$. With the properties of $\mathcal{I}$ established, we can start getting an idea of what ideals of $\Gamma(\mathbb{A}^n)$ are necessary to restrict $\mathcal{Z}$ to make it a bijection:

Proposition 31.2.11: Zero Sets and Coordinate Ideals

Let $\Gamma(\mathbb{A}^n)$ be the set of polynomial functions from $\mathbb{A}^n$ to k. Then

1. If $V \subseteq \mathbb{A}^n$, then $V \subseteq \mathcal{Z}(\mathcal{I}(V))$. If $I \subseteq \Gamma(\mathbb{A}^n)$ is an ideal of $\Gamma(\mathbb{A}^n)$, then $I \subseteq \mathcal{I}(\mathcal{Z}(I))$.
2. If $V = \mathcal{Z}(I)$ is an algebraic set, then $V = \mathcal{Z}(\mathcal{I}(V))$. Similarly, if $I = \mathcal{I}(V)$ is a vanishing ideal, then $I = \mathcal{I}(\mathcal{Z}(I))$. In other words, for every subset $V \subseteq \mathbb{A}^n$ and every ideal $I \subseteq \Gamma(\mathbb{A}^n)$,
$$\mathcal{I}(\mathcal{Z}(\mathcal{I}(V))) = \mathcal{I}(V) \qquad \mathcal{Z}(\mathcal{I}(\mathcal{Z}(I))) = \mathcal{Z}(I)$$

***Proof*:**

1. For $V \subseteq \mathcal{Z}(\mathcal{I}(V))$, since $\mathcal{I}(V)$ is the set of all functions such that $f(V) \equiv 0$ (including at least the zero polynomial), then V is certainly part of its zero set.

   Conversely, for $I \subseteq \mathcal{I}(\mathcal{Z}(I))$, the coordinate ideal of $\mathcal{Z}(I)$ certainly contains I since for any $f \in I$ and $x \in \mathcal{Z}(I)$, $f(x) = 0$. Thus, $I \subseteq \mathcal{I}(\mathcal{Z}(I))$
2. Let $V = \mathcal{Z}(I)$. By part 1 it suffices to prove $V \supseteq \mathcal{Z}(\mathcal{I}(V))$. Take $x \in \mathcal{Z}(\mathcal{I}(V))$, so that $f(x) = 0$ for every $f \in \mathcal{I}(V)$. Every $f \in I$ vanishes on $\mathcal{Z}(I) = V$ and so lies in $\mathcal{I}(V)$, giving $I \subseteq \mathcal{I}(V)$; hence $f(x) = 0$ for every $f \in I$, which says exactly that $x \in \mathcal{Z}(I) = V$. Therefore $V = \mathcal{Z}(\mathcal{I}(V))$.

   The second claim is the same argument with the roles exchanged. If $I = \mathcal{I}(V)$ then part 1 gives $I \subseteq \mathcal{I}(\mathcal{Z}(I))$; conversely if $g \in \mathcal{I}(\mathcal{Z}(I))$ then g vanishes on $\mathcal{Z}(\mathcal{I}(V))$, which we have just shown equals V, so $g \in \mathcal{I}(V) = I$. Applying $\mathcal{I}$ and $\mathcal{Z}$ to these two identities gives the displayed equations, completing the proof.

What the 2nd part of proposition 31.2.11 shows is that if we restrict to just the algebraic sets and vanishing ideals of $\mathbb{A}^n$ and $\Gamma(\mathbb{A}^n)$ respectively, then $\mathcal{Z}$ and $\mathcal{I}$ are indeed inverses of each other. The goal then would be to be able to characterize vanishing ideals, that is ideals that are of the form $I = \mathcal{I}(V)$ for some algebraic set V. It is in fact a rather involved process to find the nature of the ideal $\mathcal{I}(V)$; a lot of section 32.2 will be building up to get to the theorem which will tell us the

answer: *Hilbert's Nullstellensatz*. In the process of building up the theory to answer this question, there are a few other loose ends that we will need to tie up. For example, what properties must the Zariski topology have, and what does that imply for the corresponding ring $\Gamma(\mathbb{A}^n)$? Another important point to address is that as $k[x_1, ..., x_n]$ is Noetherian, hence every ideal is finitely generated: $I = (f_1, ..., f_m) = (f_1) \cup (f_2) \cup \cdots \cup (f_m)$. By the properties of zero sets:

$$\mathcal{Z}(I) = \mathcal{Z}(f_1) \cap \mathcal{Z}(f_2) \cap \cdots \cap (f_m)$$

In other words, there seem to be a natural theory of decomposition of algebraic sets. Furthermore, we have been shown theoretically what properties algebraic sets have, but how is one computed in practice? These questions will receive answers in the following section.

Exercise 31.2.1

1. Show that $z \mapsto \overline{z}$ is not a complex polynomial.
2. Show that $V = \left\{(z, w) \in \mathbb{A}^2_{\mathbb{C}} \;\middle|\; |z|^2 + |w|^2 = 1\right\}$ is not an algebraic subset of $\mathbb{A}^2_{\mathbb{C}}$, but that the same set, viewed in $\mathbb{A}^4_{\mathbb{R}}$, is algebraic.
3. Let k be a perfect field with algebraic closure $\overline{k}$ and Galois group $\mathrm{Gal}_k(\overline{k})$, acting on $\mathbb{A}^n_{\overline{k}}$ coordinatewise. Show that

   $$\mathbb{A}^n_k \cong \left\{p \in \mathbb{A}^n_{\overline{k}} \;\middle|\; p^\sigma = p \text{ for all } \sigma \in \mathrm{Gal}_k(\overline{k})\right\}$$

   and say where perfectness is used.
4. Let $V = \mathcal{Z}(x^2 + y^2) \subseteq \mathbb{A}^2$. Show that V is irreducible over $\mathbb{Q}$ but reducible over $\mathbb{Q}(i)$, so that irreducibility depends on the field of definition. Why does this phenomenon disappear once the field is algebraically closed?
5. Here is a way of recovering $A = k[x_1, \ldots, x_n]$ from $V = k^n$. Write $V^* = \mathrm{Hom}_k(V, k)$ and recall the symmetric algebra (definition 16.3.5):

   $$\mathrm{Sym}^\bullet(V^*) = k \oplus V^* \oplus \mathrm{Sym}^2(V^*) \oplus \mathrm{Sym}^3(V^*) \oplus \cdots$$

   Show that $\mathrm{Sym}^\bullet(V^*) \cong A$. Then let $\mathfrak{m} \subseteq A$ be the maximal ideal of a point and show $\mathfrak{m}/\mathfrak{m}^2 \cong V^*$, so that the linear structure is recovered at each point. This is the *Zariski tangent space* of chapter 35.

31.3 The Zariski Topology

In this section, we will be assuming basic topological knowledge from the reader (see [39, Topological Space])

As the reader (ought to have) showed in in example 31.2.4, if $k = \mathbb{F}_q$ is finite, then every subset of $\mathbb{A}^n_{\mathbb{F}_q}$ is algebraic, hence the Zariski topology is isomorphic to the discrete topology, showing us that there is no "interesting" behaviour in the finite case. Thus, we shall usually focus on the case where k is not-finite. This does not mean that finite fields do not play an important role in algebraic

geometry, however their importance shall not be visible until the development of schemes[10] or Class Field Theory[11] and so they shall have negligible importance this chapter.

As the topology was defined using closed sets (sets for which a collection of polynomials is zero on that set), a moment should be given to give a geometric interpretation to open sets. Open sets are those for which a collection of polynomials are *not all zero* at once on those points. If $S = \{f\} \in \Gamma(\mathbb{A}^n_k)$ is a singleton, then it will be precisely the set of points where the function f does not vanish. This makes all open sets of $\mathbb{A}^1_k$ (where k is not finite) the *cofinite sets* and hence it has the cofinite topology. If $n > 1$, the topology is certainly no longer cofinite. Open sets shall become importance when we look to define *rational polynomials* and *rational functions* for they give us the domain on which a function is non-zero. (see definition 31.3.5).

Let us now look at the separatedness of the Zariski topology. Notice that $\mathcal{T}_\mathcal{Z}$ is rarely Hausdorff (also known as T_2): if $\mathbb{A}^1 = k$ is any infinite field, as we have established that the only algebraic sets (and hence closed sets) are the empty set, finite sets, and $\mathbb{A}^1_k$ and so the only non-trivial open sets in $\mathcal{T}_\mathcal{Z}$ would be co-finite sets (i.e. $\mathcal{T}_\mathcal{Z}$ is the co-finite topology). Then as we can see, if we pick any two points $a, b \in \mathbb{A}^1$, we cannot separate them by two open disjoint sets. However, over any $\mathbb{A}^1 = k$, the singleton's are always algebraic sets (giving a hint to those who were working on example 31.2.4), and so it is always a Fréchet space (or T_1)[12].

This result generalizes for any k^n

Proposition 31.3.1: Zariski Topology Always T_1

Let k be any field and give $\mathbb{A}^n_k$ the Zariski topology. Then:

1. $\mathbb{A}^n_k$ is T_1, that is, every singleton is closed.
2. If k is infinite, $\mathbb{A}^n_k$ is not Hausdorff.

The two halves need different hypotheses, and the second genuinely fails without its one: over a finite field every subset is algebraic (example 31.2.4), so the topology is discrete and therefore Hausdorff.

***Proof*:**

1. For any $a = (a_1, \dots, a_n) \in k^n$ let $I = (x_1 - a_1, \dots, x_n - a_n)$. A point b lies in $\mathcal{Z}(I)$ exactly when $b_i - a_i = 0$ for every i, so $\mathcal{Z}(I) = \{a\}$ and singletons are closed. No hypothesis on k is used.
2. Let k be infinite and suppose U, V are nonempty open sets. Write $U = \mathbb{A}^n \setminus \mathcal{Z}(I)$ and $V = \mathbb{A}^n \setminus \mathcal{Z}(J)$ with $\mathcal{Z}(I), \mathcal{Z}(J) \neq \mathbb{A}^n$, so neither I nor J lies in $\mathcal{I}(\mathbb{A}^n) = 0$ (proposition 31.2.10); choose $f \in I$ and $g \in J$ nonzero. Then fg is nonzero, since $\Gamma(\mathbb{A}^n) \cong k[x_1, \dots, x_n]$ is an integral domain, so again by proposition 31.2.10 the product fg does not vanish identically on $\mathbb{A}^n$. Any point where fg is nonzero has both f and g nonzero, hence lies in $U \cap V$. So any two nonempty open sets meet, and $\mathbb{A}^n_k$ is not Hausdorff, as we sought to show.

[10] In particular, for any Scheme X, there is always a scheme morphism $X \to \operatorname{Spec}(\mathbb{Z})$ a there is always a ring homomorphism $\mathbb{Z} \to \mathcal{O}_X(X)$; the fibers of this scheme X_p are $\mathbb{F}_p$-schemes. Furthermore, $\mathbb{F}_q$-schemes shall be important in number theory

[11] In particular, the behaviour of unramified field extensions between local fields will be captured via the automorphisms of finite fields

[12] For those familiar with algebraic topology, schemes are almost never T_1, as prime ideals that are not maximal are not closed points

Two topological concepts which should be immediately introduced to be explored as the chapter develops are the following:

Definition 31.3.2: Zariski Dense And Closure

Let $A \subseteq \mathbb{A}^n$ be any subset of the affine space $\mathbb{A}^n$. Then the *zariski closure* of A is the smallest algebraic set containing A, denoted $\overline{A}$. Geometrically, it is the smallest set $\mathcal{A}$ for which every point in A is the zero set of a collection of polynomials.

If $\overline{A} = \mathbb{A}^n$, then A is said to be *zariski dense*. More generally if $A \subseteq V \subseteq \mathbb{A}^n$ such that $\overline{A} = V$, then A is said to be zariski dense in V.

As an example, if we give $\mathbb{R}$ the Zariski topology, the closure of any finite set is itself, while the closure of any infinite set is all of $\mathbb{R}$. The Zariski closure of a set is in fact quite easy to characterize using $\mathcal{Z}$ and $\mathcal{I}$ and follows quickly using proposition 31.2.11:

Corollary 31.3.3: Zariski Closure

Let $A \subseteq \mathbb{A}^n$. Then:

$$\overline{A} = \mathcal{Z}(\mathcal{I}(A))$$

***Proof*:**
The set $\mathcal{Z}(\mathcal{I}(A))$ is algebraic and contains A by proposition 31.2.11(1), so it is one of the algebraic sets whose intersection defines $\overline{A}$, giving $\overline{A} \subseteq \mathcal{Z}(\mathcal{I}(A))$.

Conversely, let W be any algebraic set with $A \subseteq W$. Applying $\mathcal{I}$ reverses the inclusion, so $\mathcal{I}(W) \subseteq \mathcal{I}(A)$, and applying $\mathcal{Z}$ reverses it again:

$$\mathcal{Z}(\mathcal{I}(A)) \subseteq \mathcal{Z}(\mathcal{I}(W)) = W$$

the last equality because W is algebraic (proposition 31.2.11(2)). So $\mathcal{Z}(\mathcal{I}(A))$ is contained in every algebraic set containing A, hence in $\overline{A}$, as we sought to show.

Sticking to $k = \mathbb{R}$ or $k = \mathbb{C}$ for a moment, we can compare the euclidean topology on $\mathbb{R}^n$ with the Zariski topology on $\mathbb{A}^n_{\mathbb{R}}$. (Coarser, and I think is the corsest topology on which all polynomial functions are continuous)

Another important topological consideration would be to find a topological basis for the Zariski topology. Recall a subset of the topology on a space X is a basis B if any open set of X is the union of a family of sets from B.

Proposition 31.3.4: Basis For Zariski Topology

For $f \in \Gamma(\mathbb{A}^n)$ define

$$D(f) = \mathbb{A}^n_k \setminus \mathcal{Z}(f) = \{a \in \mathbb{A}^n_k \mid f(a) \neq 0\}$$

Then the collection $\{D(f) \mid f \in \Gamma(\mathbb{A}^n)\}$ forms a [topological] basis for the Zariski topology on $\mathbb{A}^n$.

The letter D can be thought of as a mnemonic for *does not* vanish.

***Proof*:**
It suffices to show that for any open U and any $a \in U$ there is an f with $a \in D(f) \subseteq U$, since then U is the union of those $D(f)$. As U is open, $U = \mathbb{A}^n_k \setminus \mathcal{Z}(I)$ for some ideal $I \subseteq \Gamma(\mathbb{A}^n)$. Now $a \notin \mathcal{Z}(I)$ says precisely that $f(a) \neq 0$ for *some* $f \in I$; fix such an f, so that $a \in D(f)$. Since $(f) \subseteq I$,

$$\mathcal{Z}(I) \subseteq \mathcal{Z}(f)$$

and taking complements gives:

$$a \in D(f) \subseteq U$$

and since a was arbitrary, we see that U is the union of sets $D(f)$, as we sought to show.

The collection of $D(f)$ for each $f \in k[x_1, ..., x_n]$ forms the coarsest basis:

Definition 31.3.5: Distinguished Open Sets

Let $f \in k[x_1, ..., x_n]$. Then the set

$$D(f) = \mathbb{A}^n_k \setminus \mathcal{Z}(f) = \{a \in \mathbb{A}^n_k \mid f(a) \neq 0\}$$

is called he distinguished open set.

Example 31.3.6: Distinguished Open Sets

1. In $\mathbb{A}^1_k$ take $f = x$. Then $D(x) = \mathbb{A}^1_k \setminus \{0\}$, the punctured line. It is not closed, but it is itself an algebraic set in disguise: the map

   $$D(x) \to \mathcal{Z}(xy - 1) \subseteq \mathbb{A}^2_k \qquad a \mapsto (a, 1/a)$$

   is a bijection with inverse $(a, b) \mapsto a$, and both are given by polynomials on their domains. So the punctured line is the hyperbola.

2. The same works in general. For $f \in k[x_1, \ldots, x_n]$,

   $$D(f) \;\cong\; \mathcal{Z}\big(y\, f(x_1, \ldots, x_n) - 1\big) \;\subseteq\; \mathbb{A}^{n+1}_k$$

   by $a \mapsto (a, 1/f(a))$. Every distinguished open set is therefore an algebraic set in one more variable, which is why they are the right basic open sets: the topology has a basis of sets that are themselves affine.

3. The distinguished opens do form a basis. Any open set is $\mathbb{A}^n_k \setminus \mathcal{Z}(I)$, and

   $$\mathbb{A}^n_k \setminus \mathcal{Z}(I) = \mathbb{A}^n_k \setminus \bigcap_{f \in I} \mathcal{Z}(f) = \bigcup_{f \in I} D(f)$$

4. Not every open set is distinguished. In $\mathbb{A}^2_k$ the set $\mathbb{A}^2_k \setminus \{(0,0)\}$ is open, but $D(f)$ misses the whole curve $\mathcal{Z}(f)$, which is infinite for nonconstant f, and equals $\mathbb{A}^2_k$ for constant $f \neq 0$. Neither omits exactly one point.

The next property we get about the Zariski topology is that it's always Noetherian, that is, if there is an ascending chain of open sets, it must stabilize:

Proposition 31.3.7: Zariski Topology Is Noetherian

Let $\mathbb{A}_k^n$ have the Zariski topology. Then $\mathbb{A}_k^n$ is Noetherian.

***Proof*:**
Let $U_1 \subsetneq U_2 \subsetneq \cdots$ be an ascending chain of open sets, so there is a corresponding

$$X_1 \supsetneq X_2 \supsetneq \cdots$$

descending chain of closed sets. Then there is a corresponding

$$I(X_1) \subsetneq I(X_2) \subsetneq \cdots$$

ascending chain of ideals. Then we know that $\Gamma(\mathbb{A}^n)$ is *noetherian*, and so this chain must stabilize at some n:

$$I(X_n) = I(X_{n+1}) = \cdots$$

meaning the respective closed chain, and hence open chain, must stabilize, as we sought to show.

Noetherianity already forces compactness, and by the same argument every subspace of $\mathbb{A}_k^n$ is compact too: given an open cover of a subspace, the closed sets complementary to finite subcovers form a descending chain, which must stabilize. Proposition 32.5.1 nonetheless gives a second proof, via the Nullstellensatz, because that argument produces the explicit partition of unity $1 = \sum g_i f_i$ rather than the bare existence of a finite subcover, and that identity is what later arguments use[13].

31.4 Regular Maps and Continuity

The next thing we should consider the continuous functions. As the topology is the weakest in which the zero-sets is closed, it may not surprise the reader that it is the coarsest topology in which polynomials are continuous

Definition 31.4.1: Regular Map on Affine Space

A map $\varphi : \mathbb{A}_k^n \to \mathbb{A}_k^m$ is called a *regular map* if there exists polynomials $\varphi_1, \varphi_2, ..., \varphi_m \subseteq k[x_1, x_2, ..., x_n]$ such that

$$\varphi(a_1, a_2, ..., a_n) = (\varphi_1(a_1, a_2, ..., a_n), \varphi_2(a_1, a_2, ..., a_n) ..., \varphi_m(a_1, a_2, ...a_n))$$

If $m = 1$, a regular map is often called a *regular function*.

[13] Compactness is cheap here and correspondingly weak: almost every scheme is compact, so the useful strengthening is *properness*, which chapter 40 develops for projective varieties.

Lemma 31.4.2: Coordinate Ring and Regular Map

The map $\varphi : \mathbb{A}_k^n \to \mathbb{A}_k^m$ is regular if and only if the induced map $\varphi^\# : \Gamma(\mathbb{A}_k^m) \to \Gamma(\mathbb{A}_k^n)$ given by $\varphi^\#(f) = f \circ \varphi$ is a k-algebra homomorphism

***Proof*:**
Let $\varphi : \mathbb{A}_k^n \to \mathbb{A}_k^m$ be a regular map so that each component is given by a polynomial. Then $\varphi^\#$ maps a function $f \in \Gamma(\mathbb{A}_k^m)$ to $f \circ \varphi \in \Gamma(\mathbb{A}_k^n)$, namely $f \circ \varphi$ is a polynomial map. If $f, g \in \Gamma(\mathbb{A}_k^m)$, then:

$$(f+g) \circ \varphi = f \circ \varphi + g \circ \varphi$$
$$(f \cdot g) \circ \varphi = f \circ \varphi \cdot g \circ \varphi$$
$$(k \cdot f) \circ \varphi = k \cdot (f \circ \varphi)$$

thus it is a k-algebra homomorphism.

Conversely, let $\varphi^\# : \Gamma(\mathbb{A}_k^m) \to \Gamma(\mathbb{A}_k^n)$ is a k-algebra homomorphism that maps:

$$f \mapsto \varphi^\#(f) = f \circ \varphi \in \Gamma(\mathbb{A}_k^n)$$

Let $y_1, ..., y_n : \mathbb{A}_k^m \to k$ be the coordinate functions in $\Gamma(\mathbb{A}_k^m)$. If one of the components of φ where not a polynomial, then take $f = x_i$, so that the composition $x_i \circ \varphi = \varphi_i$ is not a polynomial, giving a contradiction. Hence φ must be a regular map, completing the proof.

Lemma 31.4.3: Ring homomorphism Induces Regular map

Let $f : \Gamma(\mathbb{A}_k^m) \to \Gamma(\mathbb{A}_k^n)$ be a k-algebra homomorphism. Then it induces a map $\varphi : \mathbb{A}_k^n \to \mathbb{A}_k^m$ such that $\varphi^\# = f$.

***Proof*:**
Let $k[y_1, ..., y_m] \cong \Gamma(\mathbb{A}_k^m)$ and $k[x_1, ..., x_n] \cong \Gamma(\mathbb{A}_k^n)$. Then as f is a k-algebra homomorphism, it is enough to map each y_i to some polynomial $f(y_i) = p(x_1, ..., x_m)$ and extend to form a map on all of $\Gamma(\mathbb{A}_k^m)$. Let φ_i be the function determine by $f(y_i)$. Then it is a matter of course to check that $\varphi^\# = f$, completing the proof.

Note that the maps must be k-algebra homomorphism, not just ring homomorphisms. For example, if $n = m = 1$, then $f : \mathbb{C}[\mathbb{A}_k^1] \to \mathbb{C}[\mathbb{A}_k^1]$ sending $p(x) \mapsto \overline{p(x)}$ (i.e. the complex conjugate) is not a $\mathbb{C}$-algebra homomorphism, and the reader could check there cannot be a corresponding φ such that $\varphi^\# = f$.

Lemma 31.4.4: Regular Map is Continuous

A regular map $\varphi : \mathbb{A}_k^n \to \mathbb{A}_k^m$ is continuous.

***Proof*:**
It suffices to check that the pre-image of every closed set is closed. If $V = \mathcal{Z}(I) \subseteq \mathbb{A}_k^m$ is an algebraic set, we need to show there exists an ideal J such that

$$\mathcal{Z}(J) = \varphi^{-1}(V)$$

To that end:

$$\begin{aligned}\varphi^{-1}(V) &= \{a \in \mathbb{A}_k^n \mid \varphi(a) \in V\} \\ &= \{a \in \mathbb{A}_k^n \mid f(\varphi(a)) = 0 \ \forall f \in I\} \\ &= \left\{a \in \mathbb{A}_k^n \;\middle|\; \varphi^{\#}(f)(a) = 0 \ \forall f \in I\right\}\end{aligned}$$

Consider the set $\varphi^{\#}(I) = \{g \in \Gamma(\mathbb{A}_k^n) \mid g = f \circ \varphi\}$. This set would be the desired pre-image ideal, except it is in general not an ideal as it need not be closed under multiplication (recall the image of an ideal need not be an ideal). Thus, take $J = \langle \varphi^{\#}(I) \rangle$. Then it is clear that

$$\mathcal{Z}(J) = \varphi^{-1}(V)$$

and as V was an arbitrary closed set, φ is continuous, as we sought to show.

Note that *not all* continuous maps arise from a ring homomorphism:

Example 31.4.5: Continuous, No Associated Ring Homomorphism
Take $f : \mathbb{A}_{\mathbb{R}}^1 \to \mathbb{A}_{\mathbb{R}}^1$ given by:

$$f(a) = \begin{cases} 2 & a = 1 \\ 1 & a = 2 \\ a & \text{otherwise} \end{cases}$$

The closed sets of $\mathbb{A}_{\mathbb{R}}^1$ are the finite sets and the whole space, and f carries each of these to a set of the same size, so the pre-image of every closed set is closed and f is continuous. But f is not regular. If it were given by a polynomial p, then $p(a) = a$ for every $a \notin \{1, 2\}$, so the polynomial $p(x) - x$ would have infinitely many roots and hence be zero. That forces $p(x) = x$, which does not transpose 1 and 2.

Another such example is $k = \mathbb{C}$ with the conjugation map presented earlier.

There needs to be more information for the full and faithful correspondence between regular maps and ring homomorphisms. This extra information is a *sheaf* and a *locally ringed morphism*. We shall not define these in this book, instead the reader may refer to [13, Sheaf using Axioms, Locally Ringed Space Morphism].

Example 31.4.6: Regular Maps

1. Take $V = \mathcal{Z}(y - x^2, z - x^3)$. Show that the map $f : \mathbb{A}_k^1 \to V$ given by $t \mapsto (t, t^2, t^3)$ is a regular map. Show it is not an isomorphism[a].
2. Any straight line $\mathbb{A}_k^n$ is isomorphic to any other straight-line. Similarly for any k-dimensional linear subspace.
3. The map $\mathbb{A}_k^1 \to \mathcal{Z}(y - x^2)$ given by $t \mapsto (t, t^2)$ is a regular map with inverse $(x, y) \mapsto x$, and

hence is an isomorphism. Note that it was important which coordinate we project to.

4. Here is another version of the above map. Consider the global sections of $\mathbb{A}^1_k \to \mathbb{A}^1_k$ given by

$$k[y] \to k[x] \qquad y \mapsto x^2$$

(note that the k-homomorphism is the contravariant direction of the regular morphism). As a map between varieties, this gives the map $a \mapsto a^2$ (the reader should verify this!).

5. Take $f : \mathbb{A}^2_k \to \mathbb{A}^2_k$ given by $(x, y) \mapsto (x, xy)$. Show that $\text{im}(f)$ is *not* an algebraic set. The image of a regular map is always a *constructible set*, a finite union of locally closed sets, which is theorem 41.3.4.

6. The reader should be careful with their geometric intuitions coming from the real numbers. Consider the map:

$$\mathcal{Z}(x^2 + y^2 - 1) \to \mathbb{A}^1_{\mathbb{C}} \qquad (x, y) \mapsto x$$

Show that this map is *surjective* (in contrast to the map certainly being *injective* when over $\mathbb{R}$). In fact, by taking different cross sessions of the resulting shape interpreted as a 2-real dimensional shape living in 4-real dimensional space, you will see that $\mathcal{Z}(x^2 + y^2 - 1)$ will have both the parabola and the hyperbolic curve as sections. The hyperbolic sections demonstrate why the map is surjective and 2-to-1.

[a] It shall later be shown to be a *birational equivalence*

Let us now take a moment to look at isomorphism of algebraic sets:

Definition 31.4.7: Isomorphism of Varieties

let X, Y be two algebraic sets. Then if there exists a regular map $f : X \to Y$ with regular inverse, then the two varieties are said to be *isomorphic*

Note that this was not called a homeomorphism between two varieties. All isomorphisms are homeomorphisms, but not all homeomorphisms are isomorphisms

Example 31.4.8: Isomorphism of Varieties

1. Consider $X = \mathcal{Z}(y - x^n) \subseteq \mathbb{A}^2_k$. Then $X \cong \mathbb{A}^1_k$ with $\varphi(x, y) = x$, which has inverse $\psi(t) = (t, t^n)$

2. Take $X = \mathcal{Z}(x^3 - y^2) \subseteq \mathbb{A}^2_k$. Then X can be parameterized by the regular map $f : \mathbb{A}^1_k \to X$ by $f(t) = (t^2, t^3)$. However, this is not an isomorphism: the inverse map is:

$$g(x, y) = \frac{y}{x}$$

however, there is no polynomial associated to g (can the reader see/prove why?), and hence it is not an isomorphism.

3. The reader may have recalled that $\mathcal{Z}(x^3 - y^2)$ has a cusp at 0, and believe this is the obstruction to the inverse. It is in fact a bit more subtle: a map can be bijective, with no singularity anywhere, and still fail to be an isomorphism. Let $\text{char}k = p > 0$ and consider the Frobenius $\varphi : \mathbb{A}^1_k \to \mathbb{A}^1_k$ given by $\varphi(t) = t^p$. Over $k = \overline{k}$ this is a bijection, since $t \mapsto t^p$

is injective ($t^p = s^p$ gives $(t-s)^p = 0$) and surjective (k is algebraically closed), and it is regular. Yet its inverse $t \mapsto t^{1/p}$ is not regular: the induced map on coordinate rings is $k[x] \to k[x]$, $x \mapsto x^p$, whose image is $k[x^p]$, and x does not lie in it. So φ is a bijective regular map that is not an isomorphism.

The hypothesis on the characteristic matters. In characteristic 0, or more generally whenever $p \nmid n$, the map $t \mapsto t^n$ is n-to-1 away from the origin over an algebraically closed field, so it is not even bijective.

On the other hand, the map given in the previous example had a rational polynomial inverse. Rational functions appear as localization of the coordinate ring, and so they offer a different class of functions and a different classification problem that turns out to be much easier, as we shall demonstrate in chapter 33.

It is in general difficult to ascertain isomorphic classes of algebraic sets or varieties. Some isomorphism classes that we shall state here but not prove are:

1. Smooth genus 0 curves are isomorphic to conic curves in $\mathbb{P}^2_k$
2. classes of elliptic curves can be classified by their j-invariant
3. Algebraic surfaces are birationally equivalent (defined in chapter 33), but have different isomorphism classes given their Kodaira dimension.

Exercise 31.4.1

1. Show that the Zariski topology on $\mathbb{A}^1_k$ is the cofinite topology, hence the coarsest topology in which points are closed. Then show that for $n \geq 2$ the Zariski topology on $\mathbb{A}^n_k$ is strictly finer than the cofinite topology, so the characterization fails in higher dimension.
2. Prove that $(I \cap J)^2 \subseteq IJ \subseteq I \cap J$, and conclude that $\mathcal{Z}(I \cap J) = \mathcal{Z}(IJ)$.
3. Let $k = \mathbb{F}_q$ be a finite field. Show that every set function $k^n \to k$ is given by a polynomial. Hint: build a characteristic function $\chi_{\overline{a}}$ with $\chi_{\overline{a}}(\overline{a}) = 1$ and 0 elsewhere, and show these span. Conclude that the Zariski topology on $\mathbb{A}^n_{\mathbb{F}_q}$ is discrete.
4. Show that the Zariski topology on $\mathbb{A}^n_k$ is Hausdorff if and only if k is finite.
5. Let $V \subseteq \mathbb{A}^n_k$ and $W \subseteq \mathbb{A}^m_k$ be algebraic sets. Show that $V \times W$ is an algebraic set in $\mathbb{A}^{n+m}_k$, and that $\mathbb{A}^n_k \times \mathbb{A}^m_k = \mathbb{A}^{n+m}_k$ as algebraic sets[14].
6. Let $f, g \in k[x, y]$ have no common *factor*. Show that $\mathcal{Z}(f, g)$ is finite. Hint: they remain coprime in $k(x)[y]$, a principal ideal domain, by a Gauss-lemma argument.
7. Show that if $V \subseteq \mathbb{A}^n_k$ and $W \subseteq \mathbb{A}^m_k$ are varieties, not merely algebraic sets, then $V \times W \subseteq \mathbb{A}^{n+m}_k$ is a variety.

[14] This easy statement becomes markedly harder for projective algebraic sets; see section 40.1.

32

The Algebra-Geometry Dictionary

Chapter 31 left $\mathcal{Z}$ and $\mathcal{I}$ almost inverse to one another: an algebraic set is recovered from its vanishing ideal, but an ideal need not be recovered from its zero set. This chapter identifies exactly which ideals are recovered. The answer, Hilbert's Nullstellensatz, is that they are the radical ideals, and it holds precisely when the ground field is algebraically closed.

From here to the end of the book, k is algebraically closed unless a result says otherwise. The hypothesis is not decorative: over $\mathbb{R}$ the ideal $(x^2 + 1)$ is its own radical and has empty zero set, so the correspondence fails at once. With the Nullstellensatz in hand, the geometric side and the algebraic side can be tabulated against each other, and the rest of the book consists of extending that table.

32.1 Coordinate Rings

In this section, we explore more properties of affine sets. As affine sets correspond to ideals, we shall see that there is a correspondence between the two objects. In particular it shall will show that properties of algebraic sets will often have corresponding properties in their coordinate rings, and vice-versa. This theme shall play out often in this chapter, where a property proven in a geometric or algebraic setting shall have a corresponding result in the respective dual.

By lemma 31.4.2, the collection of regular function $\mathrm{Hom}_{\mathbf{Reg}}(\mathbb{A}^n_k, \mathbb{A}^1_k)$ can be thought of as the generalization of the dual vector-space, where polynomial functions are taken instead of linear functions. We saw that for each vector subspace $W \subseteq V$, there is a dual space $W^\vee = \mathrm{Hom}_k(W, k)$ which it is isomorphic to. It is thus natural to ask what is the appropriate dual space for an algebraic set $V \subseteq \mathbb{A}^n_k$ corresponding to the *quotient* of $\Gamma(\mathbb{A}^n_k)$[1].

[1] For the categorically inclined, since the arrows in the dual space are reversed, sub-objects correspond to quotient-objects

In order to find the dual, we must consider more the subspace topology put on $V \subseteq \mathbb{A}^n_k$. Note that all of the properties of the Zariski topology apply to A since $\mathbb{A})k^n$ is T1 (proposition 31.3.1), from which we can conclude that closed sets are preserved in the subspace topology. We will always limit ourselves to taking A to be an algebraic set, since algebraic set are the object of interest. The dual space we wish to establish is a corresponding "polynomial ring" which will generate all of the closed sets of A, just like how $k[x_1, x_2, ..., x_n]$ is needed to generate the closed sets of $\mathbb{A}^n$. Without looking at the next definition, can you see what the definition of such a ring may be?

To elucidate the coming definition, let us come back to the algebraic set V defined given by the vanishing set of $x^2 + y^2 - 1$. Then on V, the function $X^2 + Y^2 - 1$ on V will evaluate to 0, hence these two polynomials are equivalent as functions:

$$X^2 + Y^2 - 1 \equiv 0 \qquad \text{on } V$$

If g is any other polynomial corresponding to the function G, then $(X^2 + Y^2 - 1)G$ evaluates to 0 everywhere as well, showing the set of regular functions taking inputs on V is closed under multiplication by regular functions $\Gamma(\mathbb{A}^n_k)$. Furthermore, if two regular functions f, g which evaluate to zero everywhere are added, the function $f + g$ will also evaluate to zero, showing it is closed under addition. In other words, the collection of functions which evaluates to 0 forms an ideal of $\Gamma(\mathbb{A}^n_k)$. What is this ideal? If we let F be the function

$$F : k[x, y] \to \mathrm{Hom}_{\mathbf{Reg}}(V, k) \qquad f \mapsto ((a, b) \to f(a, b)) \tag{32.1}$$

where $\mathrm{Hom}_{\mathbf{Reg}}(V, k)$ is the set of regular functions which evaluate only on the points V, then we get that this map is surjective and that:

$$\frac{k[x, y]}{\ker(F)} \cong_k \mathrm{Hom}_{\mathbf{Reg}}(V, k)$$

The reader should clue in that $\ker(F)$ is by definition $\mathcal{I}(V)$ as defined in definition 31.2.8! This leads to the following definition:

Definition 32.1.1: [Affine] Coordinate Ring

Let $k[x_1, ..., x_n]$ be a polynomial ring over n variables, V an algebraic set, and $\mathcal{I}(V)$ the corresponding vanishing ideal. Then:

$$\Gamma(V) = k[V] = \frac{k[x_1, ..., x_n]}{\mathcal{I}(V)}$$

is called the *coordinate ring* of V. The corresponding regular functions shall be denoted $k[V]$ or $\Gamma(V)$.

Notice how this notation is the same as for regular functions: the coordinate ring of $V = \mathbb{A}^n_k$ is isomorphic to $k[X_1, ..., X_n]$ since $I(\mathbb{A}^n) = (0)$. In $\Gamma(V)$, we have that $\mathcal{I}(V) = \overline{(0)}$, showing the notation is consistent.

We can naturally bring the notion of regular function to algebraic sets:

Definition 32.1.2: Regular Maps on Algebraic Sets

Let $V \subseteq \mathbb{A}_k^n$, $W \subseteq \mathbb{A}_k^m$ be algebraic sets. Then a map $\varphi : V \to W$ is called a *regular map*, or *regular morphism*, if there exists polynomials $\varphi_1, \varphi_2, ..., \varphi_m \subseteq k[x_1, x_2, ..., x_m]$ such that

$$\varphi(a_1, a_2, ..., a_n) = (\varphi_1(a_1, a_2, ..., a_n), \varphi_2(a_1, a_2, ..., a_n)..., \varphi_m(a_1, a_2, ...a_n))$$

If $m = 1$, then φ is often called a *regular function*.

This definition also allows us to upgrade definition 31.1.2 and definition 31.4.1. To check that $\varphi : V \to W$ is well-defined, it suffices to check that $\varphi_1, ..., \varphi_m$ as elements of $k[V]$ satisfy the equations of W.

Proposition 32.1.3: Regular Maps Are Continuous

Let $\varphi : V \to W$ be a regular map where V, W are equipped with the Zariski topology. Then φ is continuous.

***Proof*:**
Let $S \subseteq W$ be a closed subset. It suffices to show that $\varphi^{-1}(S)$ is closed. if $\varphi^{-1}(S) = \emptyset$, it is closed by definition, so assume $\varphi^{-1}(S) \neq \emptyset$. As S is closed, there exists polynomials $f_1, ..., f_n$ such that for each $x \in S$, $g_1(x) = \cdots = g_m(x) = 0$. If $a \in \varphi^{-1}(S)$, then $\varphi(a) \in S$, so

$$g_1(\varphi(a)) = \cdots = g_m(\varphi(a)) = 0 \tag{32.2}$$

As $\varphi = (\varphi_1, ..., \varphi_n)$ is a tuple of polynomials, notice that (32.2) is a collection of polynomials in $k[V]$ where a vanishes. As this is true for all points in $\varphi^{-1}(S)$, we see that:

$$\varphi^{-1}(S) = \mathcal{Z}(g_1 \circ \varphi, ..., g_m \circ \varphi)$$

showing it is closed, as we sought to show.

As before, this is not an iff as not all continuous functions are regular functions (simply take $V = W = \mathbb{A}_{\mathbb{C}}^1$ and the conjugation map). That is because continuity in the Zariski topology is not enough to preserve the algebraic relations. In particular, any point $a \in V \subseteq \mathbb{A}_k^n$ satisfying

$$f_1(a) = \cdots f_n(a) = 0$$

must have an image that satisfies:

$$g_1(w) = \cdots = g_m(w) = 0 \qquad \text{i.e.} \qquad g_1(\varphi(a)) = \cdots g_1(\varphi(a)) = 0$$

Example 32.1.4: Coordinate Ring and Regular Mapping

1. Let $V = \mathcal{Z}(xy - 1)$, which represents the hyperbola $y = 1/x$ in $\mathbb{R}^2$. Then the coordinate ring $\mathbb{R}[V] = \mathbb{R}[x, y]/(xy - 1)$. In $\mathbb{R}[V]$, $f(x, y) = x$ and $g(x, y) = x + xy - 1$ are the same function since $f - g \in \mathcal{I}(V)$. In $\mathbb{R}[V]$, $\overline{xy} = \overline{1}$, giving us that $\mathbb{R}[V] \cong \mathbb{R}[x, 1/x]$. Thus, for any $f \in \mathbb{R}[x, y]$ and $(a, b) \in V$, $\overline{f}(a, b) = f(a, 1/a)$ for any f that maps to $\overline{f}$.

Take the regular map $\varphi : V \to \mathbb{A}^1_k$ mapping $(x, y) \mapsto x$. The image of this map is $\mathbb{A}^1_k \setminus \{0\}$, which is certainly *not* a closed set (can the reader see why). It is an open set, being the complement of the closed set $\{0\}$. However, if we take the map to be $\varphi' : V \to \mathbb{A}^2_k$ mapping $(x, y) \mapsto (x, 0)$, then the image is no longer an open set, and hence it is possible for the images of regular maps to be neither open or closed. Further exploration the properties of the image of regular maps shall be done section 39.4.

2. Take $k = \mathbb{F}_p$ and consider $\mathbb{A}^n_{\mathbb{F}_p}$. Then the map:

$$\varphi(a_1, ..., a_n) = (a_1^p, ..., a_n^p)$$

is a regular function. If $V \subseteq \mathbb{A}^n_{\mathbb{F}_p}$ is an algebraic set, notice that φ will always take V to itself, since if f is one of the polynomials that define V so that $f(a) \equiv 0 \bmod p$, then:

$$f(a_1^p, ..., a_n^p) = (f(a_1, ..., a_n))^p \equiv (0)^p \equiv 0 \bmod p$$

The regular function φ is called the *Frobenius mapping*

3. Take $t \mapsto (t^3, t^2)$. This is a regular function and maps $\mathbb{A}^1_{\mathbb{R}}$ to the curve given by $x^3 = y^2$ in $\mathbb{A}^2_{\mathbb{R}}$.

4. Take $V = \mathcal{Z}(xy - 1)$ and $W = \mathcal{Z}(v - u^2)$. We can define a map between global sections:

$$\varphi : \frac{k[u, v]}{(v - u^2)} \to \frac{k[x, y]}{(xy - 1)} \qquad u \mapsto \frac{x + y}{2}$$

and extend k-linearly (note that $v \mapsto \left(\frac{x+y}{2}\right)^2$). As the left hand side is a free k-algebra up to the quotient relation, let's insure the relation is preserved, and indeed:

$$\varphi(0) = \varphi(v - u^2) = \frac{(x + y)^2}{2} - \frac{(x + y)^2}{2} = 0$$

showing that the relation is preserved, and hence φ is well-defined. The associated map on the varieties is given by:

$$(a, 1/a) \mapsto \left(\frac{a + 1/a}{2}, \left(\frac{a + 1/a}{2}\right)^2\right)$$

Note the image is 2-to-1. If $k = \mathbb{R}$, the image is *not* surjective (ex. nothing maps to 0). However if $i \in k$ (where $i^2 = -1$), then $i + 1/i = i - i = 0$, which shows the map is surjective and 2-to-1. This demonstrates part of the importance of working over an algebraically closed field.

Theorem 32.1.5: Regular Map Algebraic Correspondence

Let $V \subseteq \mathbb{A}^n$ and $W \subseteq \mathbb{A}^m$. then there is a bijective correpspondence between the morphisms between V and W and the associated k-algebra homomorphisms, more precisely

$$\{\text{regular functions from } V \text{ to } W\} \leftrightarrow \{k\text{-algebra homomorphisms from } k[W] \text{ to } k[V]\}$$

$$\left\{\begin{array}{c}\text{regular functions} \\ \varphi : V \to W\end{array}\right\} \underset{\psi^a}{\overset{f\circ\varphi}{\rightleftarrows}} \left\{\begin{array}{c}k\text{-algebra homomorphism} \\ \varphi^\# : k[W] \to k[V]\end{array}\right\}$$

More generally, if k-**Aff** is the category whose objects are algebraic sets and morphism are regular functions and k-$\mathbf{Alg}_0$ is the category whose objects are coordinate rings (reduced, commutative, finite-type k-algebras) and morphisms are k-homomorphisms, then k-$\mathbf{Aff}^{\text{op}} \cong k$-$\mathbf{Alg}_0$ (the equivalence of categories requires k algebraically closed, so that every such algebra is realized as a coordinate ring by proposition 32.5.5).

***Proof*:**

The two constructions are already in hand: lemma 31.4.2 sends a regular map φ to the k-algebra homomorphism $\varphi^\#(f) = f \circ \varphi$, and lemma 31.4.3 sends a k-algebra homomorphism back to a regular map. It remains to see they are mutually inverse.

Given $\varphi\colon V \to W$, write ψ for the regular map induced by $\varphi^\#$. Let $y_1, \ldots, y_m$ be the coordinate functions on W. By construction the ith component of ψ is $\varphi^\#(y_i) = y_i \circ \varphi = \varphi_i$, the ith component of φ; as the components agree, $\psi = \varphi$.

Conversely let $\theta\colon k[W] \to k[V]$ be a k-algebra homomorphism, φ the regular map it induces, and $\varphi^\#$ the homomorphism φ induces in turn. Both θ and $\varphi^\#$ are k-algebra maps out of $k[W]$, which is generated over k by the $\overline{y_i}$, and both send $\overline{y_i}$ to $\theta(\overline{y_i})$; a k-algebra homomorphism is determined by its values on generators, so $\varphi^\# = \theta$.

For the categorical statement, $\varphi \mapsto \varphi^\#$ is contravariant and functorial, since $(\varphi \circ \psi)^\# = \psi^\# \circ \varphi^\#$ and $\mathrm{id}^\# = \mathrm{id}$. The bijection just established makes it fully faithful, and proposition 32.5.5 makes it essentially surjective onto k-$\mathbf{Alg}_0$ when k is algebraically closed, completing the proof.

Thus, if $f : X \to Y$, then $(f^\#)^a = f$ and if $\varphi : k[Y] \to k[X]$, then $(\varphi^a)^\# = \varphi$. Similarly to the dual theory provided in section 13.3, the dual map gives information about our original map:

Proposition 32.1.6: Regular Map Properties

Let $\varphi : X \to Y$ be a regular map with $\varphi^{\#} : k[Y] \to k[X]$ the associated k-algebra homomorphism. Then:

1. The kernel of $\tilde{\varphi}$ is $\mathcal{I}(\varphi(X))$: $\ker \tilde{\varphi} = \mathcal{I}(\varphi(X))$. Furthermore, the Zariski closure of $\varphi(X)$ is $\mathcal{Z}(\ker(\tilde{\varphi}))$: $\overline{\varphi(X)} = \mathcal{Z}(\ker(\tilde{\varphi}))$.
2. As a consequence, the homomorphism $\tilde{\varphi}$ is injective if and only if $\varphi(X)$ is Zariski dense in Y, or equivalently if $\overline{f(X)} = Y$
3. $\varphi(v) = w$ if and only if $(\varphi^{\#})^{-1}(\mathcal{I}(v)) = \mathcal{I}(w)$, where $\mathcal{I}(v) \subseteq k[X]$ and $\mathcal{I}(w) \subseteq k[Y]$ are the maximal ideals of the two points

***Proof*:**

1. A function $g \in k[Y]$ satisfies $\varphi^{\#}(g) = g \circ \varphi = 0$ exactly when g vanishes at every point of $\varphi(X)$, which is to say $g \in \mathcal{I}(\varphi(X))$. Hence $\ker \varphi^{\#} = \mathcal{I}(\varphi(X))$, and applying $\mathcal{Z}$ gives $\mathcal{Z}(\ker \varphi^{\#}) = \mathcal{Z}(\mathcal{I}(\varphi(X))) = \overline{\varphi(X)}$ by corollary 31.3.3.
2. By part 1, $\varphi^{\#}$ is injective if and only if $\mathcal{I}(\varphi(X)) = 0$ in $k[Y]$, and $\mathcal{Z}(0) = Y$, so this says $\overline{\varphi(X)} = Y$: the image is dense.
3. Suppose $\varphi(v) = w$. For $g \in k[Y]$, $\varphi^{\#}(g)(v) = g(\varphi(v)) = g(w)$, so $\varphi^{\#}(g) \in \mathcal{I}(v)$ if and only if $g \in \mathcal{I}(w)$, which is exactly $(\varphi^{\#})^{-1}(\mathcal{I}(v)) = \mathcal{I}(w)$. Conversely, suppose that identity holds. Both $\mathcal{I}(v)$ and $\mathcal{I}(w)$ are maximal (theorem 32.4.3), and writing $w' = \varphi(v)$ the forward direction gives $(\varphi^{\#})^{-1}(\mathcal{I}(v)) = \mathcal{I}(w')$. Hence $\mathcal{I}(w) = \mathcal{I}(w')$, and since $\mathcal{I}$ is injective on points, $w = w' = \varphi(v)$, completing the proof.

Exercise 32.1.1

1. Show that $k[X \times Y] \cong k[X] \otimes_k k[Y]$ for algebraic sets X, Y, and deduce another proof that $\mathbb{A}^n_k \times \mathbb{A}^m_k \cong \mathbb{A}^{n+m}_k$ as objects of **Reg**.
2. Show that the product is unique up to isomorphism: if $\varphi\colon X \to X'$ and $\psi\colon Y \to Y'$ are isomorphisms, there is a unique isomorphism $X \times Y \to X' \times Y'$ commuting with the projections.
3. Let $T\colon \mathbb{A}^n_k \to \mathbb{A}^n_k$ be an affine isomorphism with $T(p) = q$. Show that $T^{\#}\colon \mathcal{O}_q(\mathbb{A}^n_k) \to \mathcal{O}_p(\mathbb{A}^n_k)$ is an isomorphism, and that for a variety V it induces $\mathcal{O}_q(V) \to \mathcal{O}_p(V^T)$. This is the precise sense in which affine space has no preferred origin.
4. Sharpen theorem 32.1.5: show that a regular map $\varphi\colon X \to Y$ is dominant if and only if $\varphi^{\#}$ is injective, and that φ is a closed immersion, meaning an isomorphism onto a closed subset, if and only if $\varphi^{\#}$ is surjective.

32.2 Radical Ideals

As we have seen in proposition 31.2.5, given some polynomial f or collection of polynomials $S \subseteq k[x_1, ..., x_n]$, the set of zero's of these polynomials does not change if we take higher powers of the polynomials (ex. $f, f^2, f^3, ...$ all produce the same zero set). Thus, studying the set $\mathcal{Z}(I^n)$ is equivalent to studying $\mathcal{Z}(I)$. This property inspires the following definition:

Definition 32.2.1: Radical Ideal

Let $I \subseteq R$ be an ideal of a commutative ring R. Then:

1. The *radical of* I in R is the collection elements for which some power of them lie in I, that is:
$$\sqrt{I} = \text{rad}(I) := \left\{a \in R \mid a^k \in I \text{ for some } k \in \mathbb{N}\right\}$$
here $\text{rad}(I)$ stands for the radical of I. It is often written as $\sqrt{I}$.
2. The radical of the zero ideal ($\text{rad}(0) = \sqrt{(0)}$) is called the *nilradical* of R
3. An ideal I is called a *radical ideal* if $I = \text{rad}(I)$ ($I = \sqrt{I}$)

Note that the nilradical by definition contains all the nilpotent elements of R, and that $\text{rad}(\text{rad}(I)) = \text{rad}(I)$.

Proposition 32.2.2: $\text{rad}(I)$ Is An Ideal

Let $I \subseteq R$ be an ideal of a commutative ring. Then $\text{rad}(I)$ is indeed an ideal (containing I). Furthermore, $\text{rad}(I)/I$ is the nilradical of R/I.

The last statement shows us that R/I has no nilpotent elements if and only if $I = \text{rad}(I)$.

***Proof*:**
See [21, The Radical Is an Ideal]. For the last statement, $a + I$ is nilpotent in R/I exactly when $a^k \in I$ for some k, that is when $a \in \text{rad}(I)$.

A type of ideal in which we have seen a similar property is the prime ideal, in which $ab \in I$ if and only if $a \in I$ or $b \in I$. One important way of looking at radical is in how they correspond to prime ideals. The prime ideals in a sense "generate" the radical ideals:

Proposition 32.2.3: Radical Through Prime Ideals

Let $I \subsetneq R$ be a proper ideal of a commutative ring and $\text{rad}(I)$ the radical ideal of I. Then $\text{rad}(I)$ is the intersection of all prime ideals containing I. In particular, the nilradical is the intersection of all prime ideals of R.

***Proof*:**
This is the description of the radical as an intersection of primes. See [20, The Radical as an Intersection of Primes].

Corollary 32.2.4: Prime Or Maximal Then Radical

Let $I \subseteq R$ be a prime ideal. Then I is a radical ideal

***Proof*:**
A prime ideal P satisfies $P = \sqrt{P}$. See the in-particular clause of [20, The Radical as an Intersection of Primes].

Example 32.2.5: Radical Ideals

1. Let R be a UFD. Given an ideal, finds its radical.
2. The ideal $(x^3 - y^2)$ is prime in $k[x, y]$, and hence radical
3. If $l_1, l_2, ..., l_m$ is a collection of linear polynomials in $k[x_1, ..., x_n]$, then $I = (l_1, l_2, ..., l_m)$ is either $k[x_1, x_2, ..., x_n]$ or a prime ideal, and hence radical.

In the context of this chapter, since we are working over polynomials rings, we are working over Noetherian rings. Due to this, the elements of a radical ideal $\text{rad}(I)$ can be related back to elements of I quite naturally:

Proposition 32.2.6: Radical Ideals In Noetherian Rings

Let R be a noetherian ring and $I \subseteq R$ an ideal of R. Then there exists a $k \in \mathbb{N}$ such that $\text{rad}(I)^k \subseteq I$. In particular, if N is the nilradical ideal of R, then $N^k = 0$ for some $k \in \mathbb{N}$ (i.e. N is a nilpotent ideal)

***Proof*:**
See [20, Radical Powers in Noetherian Rings].

Now, returning to the fact that $\mathcal{Z}(I) = \mathcal{Z}(I^k)$, we now have that $\mathcal{Z}(I) = \mathcal{Z}(\sqrt{I})$. Remember how we were trying to characterize the ideals for which $\mathcal{Z}$ and $\mathcal{I}$ are inverses, i.e. what are the ideals $\mathcal{I}(\mathcal{Z}(I))$? We can now state one direction of this:

Proposition 32.2.7: Radical and Algebraic Sets

Let $I \subseteq R$ be an ideal where R is a polynomial ring. Then

$$\sqrt{I} \subseteq \mathcal{I}(\mathcal{Z}(I))$$

***Proof*:**
Let $f \in \sqrt{I}$, so $f^m \in I$ for some $m \geq 1$, and let $x \in \mathcal{Z}(I)$ be arbitrary. Every element of I vanishes at x, so in particular

$$f(x)^m = f^m(x) = 0$$

Since k is a field it has no nonzero nilpotents, so $f(x) = 0$. As $x \in \mathcal{Z}(I)$ was arbitrary, f vanishes

on $\mathcal{Z}(I)$, which is to say $f \in \mathcal{I}(\mathcal{Z}(I))$, as we sought to show.

It would be great if we could get $\sqrt{I} = \mathcal{I}(\mathcal{Z}(I))$, however this is not true in general: consider $I = (x^2+1) \subseteq \mathbb{R}[x]$. Since $x^2 = 1$ is irreducible, it is a maximal ideal, and so $I = \sqrt{I}$. Then as we are over the reals, $\mathcal{Z}(I) = \emptyset$, so $\mathcal{I}(\mathcal{Z}(I)) = \mathbb{R}[x]$ But $I \not\supseteq \mathbb{R}[x]$, showing equality does not hold. The blocker here was that x^2+1 does not factor in $\mathbb{R}[x]$: if we were working over $\mathbb{C}$, then we would get that $(x^2+1) = ((x+i)(x-i))$, telling us that $\mathcal{Z}(I) = \{i, -i\}$, which by the basic properties of $\mathcal{I}$ we have that $\mathcal{I}(\mathcal{Z}(I)) = ((x-i)(x+i)) = (x^2+1) = I$, showing us in this case that $I = \sqrt{I}$. In fact, the underlying field k being algebraically closed is the *only* other condition we need for equality to hold; this will be theorem 32.4.4 (Hilbert's Nullstellensatz). It is tricky to show this, since it is in a sense a very simple condition: All we need to characterize the zero sets of the polynomials (over a closed field) $\mathcal{Z}(I)$ in terms of an ideal is to take the radical of I.

32.3 Irreducibility and the Decomposition Theorem

We now return to the earlier fact that $\mathcal{Z}(I) = \mathcal{Z}(f_1, ..., f_n) = \mathcal{Z}(f_1) \cap \cdots \cap \mathcal{Z}(f_n)$. This shows that we can decompose algebraic sets into smaller components. We will therefore take a moment to see if we can find "decomposition" properties of algebraic sets, and see if there is a corresponding property the coordinate ideals will poses

Definition 32.3.1: [Affine] Variety

let $V \subseteq \mathbb{A}^n$ be an algebraic set. The set V is reducible if for $V_1, V_2 \subseteq V$ where $V_1, V_2 \neq V$

$$V = V_1 \cup V_2$$

If there does not exist such sets, we say that V is *irreducible*, or more commonly an *algebraic variety*

32.3.2 Remark Note that this notion of irreducibility is in fact a topological notion, we simply choose the Zariski topology. In particular, X is irreducible if $X = X_1 \cup X_2$ for some closed subsets X_1 and X_2, then either $X = X_1$ or $X = X_2$. For those who are curious, it may be shown that irreducibility implies connected. Furthermore, the condition translates to open sets to say that if

$$\emptyset = U_1 \cap U_2$$

where U_1, U_2 open, then either $U_1 = \emptyset$ or $U_2 = \emptyset$. It follows that it is equivalent to say that every open set is *dense* in an irreducible space. This contrasts heavily with any Hausdorff space, since by definition a Hausdorff space *must* have disjoint open subsets if the space is not empty or a singleton.

The name *algebraic variety* comes from HERE. Note that this condition automatically implies that V_1 and V_2 are non-empty (do you see why?). If V is an irreducible algebraic set, then the corresponding ideal has a very nice property:

Proposition 32.3.3: Coordinate Ideal of Algebraic Variety

A set $V \subseteq \mathbb{A}^n$ is an algebraic variety if and only if $I(V)$ is a prime ideal

***Proof*:**

($\Rightarrow$) Taking the contrapositive, let's assume $I(V)$ is not prime. Then there exists $a, b \in k[x_1, .., x_n]$ such that $ab \in I(V)$ but $a \notin I(V)$ and $b \notin I(V)$. But then:

$$V = (V \cap \mathcal{Z}(a)) \cup (V \cap \mathcal{Z}(b))$$

with $V \cap V(a) \subsetneq V$, $V \cap V(b) \subsetneq V$, showing that V is in fact reducible

($\Leftarrow$) Doing the contrapositive again, let's assume V is reducible, so $V = V_1 \cup V_2$, where both $V_i \subsetneq V$. Then by the contra-positive correspondence of inclusion between algebraic sets and ideals, $I(V) \subsetneq I(V_i)$, $i \in \{1, 2\}$. Since the inclusion is proper, choose $a \in I(V_1)$ and $b \in I(V_b)$ such that $a, b \notin I(V)$. Then since a and b are polynomials which are zero on their respective algebraic sets and $V = V_1 \cup V_2$, $ab \in I(V)$. However, $a, b \notin I(V)$, showing that $I(V)$ is not prime

Corollary 32.3.4: Equivalent characterization

Let $V \subseteq \mathbb{A}^n$ be an algebraic set. Then V is an algebraic variety if and only if $k[V]$ is an integral domain

***Proof*:**

By definition 32.1.1, $k[V] = \Gamma(\mathbb{A}^n)/\mathcal{I}(V)$, and a quotient of a commutative ring is an integral domain exactly when the ideal quotiented out is prime. So $k[V]$ is a domain if and only if $\mathcal{I}(V)$ is prime, which by proposition 32.3.3 holds if and only if V is irreducible, as we sought to show.

This means there is a certain correspondence between being a prime and being irreducible as a variety. To deepen the conection, let's prove that every algebraic set can be decomposed into algebraic varieties:

Theorem 32.3.5: Irreducible Decomposition

Let $V \subseteq \mathbb{A}^n$ be an algebraic set. Then there exist algebraic varieties $V_1, ..., V_r$, unique up to reordering, such that

$$V = \bigcup_{i=1}^{r} V_i \qquad V_i \not\subseteq V_j \quad i \neq j$$

***Proof*:**

Existence. Since $\Gamma(\mathbb{A}^n)$ is Noetherian, every nonempty collection of ideals has a maximal element, and $\mathcal{I}$ reverses inclusion, so every nonempty collection of algebraic sets has a *minimal* element.

Let

$$S = \{W \subseteq \mathbb{A}^n \text{ algebraic} \mid W \text{ is not a finite union of algebraic varieties}\}$$

and suppose for contradiction that $S \neq \emptyset$. Choose $W \in S$ minimal. Then W is not itself a variety, so $W = W_a \cup W_b$ with both $W_a, W_b \subsetneq W$. By minimality neither lies in S, so each is a finite union of varieties, say

$$W_a = V_{1,1} \cup \cdots \cup V_{1,n_1} \qquad W_b = V_{2,1} \cup \cdots \cup V_{2,n_2}$$

and then $W = \bigcup_{i,j} V_{i,j}$ is one too, contradicting $W \in S$. Hence $S = \emptyset$.

Given any finite decomposition, discard every $V_{i,j}$ contained in another; what remains still has union V and now satisfies $V_i \not\subseteq V_j$ for $i \neq j$.

Uniqueness. Suppose $V = V_1 \cup \cdots \cup V_r = W_1 \cup \cdots \cup W_m$ are two such decompositions. Fix i. Then

$$V_i = V_i \cap V = \bigcup_j (W_j \cap V_i)$$

expresses the irreducible set V_i as a finite union of closed subsets, so by irreducibility $V_i = W_j \cap V_i$ for some j, that is $V_i \subseteq W_j$. Running the same argument on W_j against the first decomposition gives $W_j \subseteq V_k$ for some k, whence $V_i \subseteq V_k$. The decomposition has no containments among distinct members, so $i = k$, and therefore $V_i = W_j$. This assigns to each i a j with $V_i = W_j$, and symmetrically to each j an i; the two assignments are mutually inverse, so $r = m$ and the two families agree up to reordering, completing the proof.

Definition 32.3.6: Irreducible Decomposition

Let V be an algebraic set. Then the *irreducible decomposition of* V is

$$V = V_1 \cup \cdots V_n \quad V_i \not\subseteq V_j i \neq j$$

for appropriate algebraic varieties V_i, $1 \leq i \leq n$

32.3.7 Remark In a more general topological setting, it can be shown that if X is a Noetherian space (i.e. satisfies A.C.C. on open sets, so D.C.C. on closed sets), X can be decomposed into irreducible sets just liked was done in theorem 32.3.5. It then follows easily that any closed subset of X has this property too.

Example 32.3.8: Affine Varieties

1. All linear polynomials produce affine varieties. Thus, the study of linear algebra can be thought as the study of varieties with multiplicity 1.
2. $\mathcal{Z}(xy-1) \subseteq \mathbb{A}^2_{\mathbb{R}}$ is an affine variety, as $\mathbb{R}[x,y]/(xy-1) \cong \mathbb{R}[x, 1/x]$. Note that $xy-1$ has two branches, however the variety is still irreducible and connected in the Zariski topology. Show that there is no variety that is only one branch of $xy-1$ (show that if two affine varieties agree on an open subset, they agree everywhere).

The decomposition of a Noetherian variety into irreducible components has an algebraic mirror: the *primary decomposition* of ideals. The minimal primes over $I(X)$ are precisely the ideals of the irreducible components of X, while embedded primes record finer, scheme-theoretic information carried by the coordinate ring but invisible to the underlying set. The full theory (primary ideals, the Lasker-Noether existence and uniqueness theorems, and the associated primes of a module) is developed in [20]; we use it freely when passing between a variety and its coordinate ring.

Exercise 32.3.1

1. Show that an algebraic set is irreducible if and only if any two nonempty open subsets of it meet, and use this to give a second proof that $\mathbb{A}^n_k$ is irreducible.
2. Show that the intersection of two irreducible algebraic sets need not be irreducible. Hint: take $\mathcal{Z}(z)$ and $\mathcal{Z}(xy - z)$ in $\mathbb{A}^3_k$.
3. Show that the closure of an irreducible subset is irreducible, and that a nonempty open subset of an irreducible set is irreducible and dense.
4. Show that a Noetherian topological space is quasicompact, and that every subspace of one is Noetherian.
5. Let X be an algebraic set with irreducible decomposition $X = X_1 \cup \cdots \cup X_r$ as in theorem 32.3.5. Show that the X_i are exactly the maximal irreducible closed subsets of X, which is why the decomposition is unique.

32.4 Hilbert's Nullstellensatz

In this section, we shall make precise the correspondence between which ideals of the coordinate ring of an affine set correspond to closed subsets of the affine set. In this exploration, we shall also produce a new tower condition on ring extensions via Noether's Normalization theorem which builds upon the theme of separating an extension to "property" and "not property" (ex. separable and inseparable, algebraic and transcendental[2]) Recall if $a_1, a_2, ..., a_n \in S$ for a k-algebra S, these elements are called *algebraically independent* if

$$k[x_1, x_2, ..., x_n] \to k[a_1, a_2, ..., a_n] \qquad x_i \mapsto a_i$$

is an isomorphism. Noether's Normalization theorem is the generalization of the idea that any field extension can be split into a transcendental extension, followed by an algebraic extension:

Theorem 32.4.1: Noether's Normalization Theorem

Let k be a field and suppose that $A = k[r_1, ..., r_n]$ is a finitely generated k-algebra. Then for some q, $0 \leq q \leq n$, there are algebraically independent elements $y_1, y_2, ..., y_q \in A$ such that A is integral over $k[y_1, y_2, ..., y_q]$

[2]Another such example will appear in the next chapter, and shall be ramified and unramified

***Proof*:**
Induct on the number n of generators. If $n = 0$ then $A = k$ and there is nothing to prove, so let $n \geq 1$ and assume the theorem for k-algebras on fewer than n generators.

Step 1: the independent case. If $r_1, \ldots, r_n$ are algebraically independent then A is integral over itself and we may take $q = n$ and $y_i = r_i$. So assume they are algebraically dependent: there is a nonzero $f \in k[x_1, \ldots, x_n]$ with $f(r_1, \ldots, r_n) = 0$. Write d for the total degree of f, where a monomial $ax_1^{m_1} \cdots x_n^{m_n}$ has degree $m_1 + \cdots + m_n$ and $\deg f$ is the largest degree occurring.

Step 2: a change of variables making f monic in x_n. Set $\alpha_i = (1+d)^i$ for $1 \leq i \leq n-1$, introduce new variables $X_i = x_i - x_n^{\alpha_i}$, and define

$$g(X_1, \ldots, X_{n-1}, x_n) = f(X_1 + x_n^{\alpha_1}, \ldots, X_{n-1} + x_n^{\alpha_{n-1}}, x_n)$$

so $g \in k[X_1, \ldots, X_{n-1}, x_n]$. A monomial $ax_1^{m_1} \cdots x_n^{m_n}$ of f contributes to g a single term in which the X_i do not appear, namely $a\, x_n^e$ with

$$e = m_n + m_1\alpha_1 + \cdots + m_{n-1}\alpha_{n-1} = m_n + m_1(1+d) + \cdots + m_{n-1}(1+d)^{n-1}$$

every other term carries at least one X_i. Since each $m_i \leq d < 1+d$, the tuple $(m_n, m_1, \ldots, m_{n-1})$ is the base-$(1+d)$ expansion of e, so distinct monomials of f give distinct e. Hence the largest such e, call it N, is attained exactly once, and

$$g = cx_n^N + \sum_{i=0}^{N-1} h_i(X_1, \ldots, X_{n-1})x_n^i$$

for some nonzero $c \in k$: after dividing by c, g is monic in x_n over $k[X_1, \ldots, X_{n-1}]$.

Step 3: descending one generator. Put $s_i = r_i - r_n^{\alpha_i}$ and $B = k[s_1, \ldots, s_{n-1}] \subseteq A$. Substituting $X_i \mapsto s_i$ and $x_n \mapsto r_n$ in g recovers $f(r_1, \ldots, r_n) = 0$, so

$$\frac{1}{c}g(s_1, \ldots, s_{n-1}, r_n) = 0$$

exhibits r_n as a root of a monic polynomial over B; thus r_n is integral over B. Each remaining $r_i = s_i + r_n^{\alpha_i}$ lies in $B[r_n]$, so $A = B[r_n]$, and A is integral over B because it is generated over B by the single integral element r_n.

Step 4: induction. B is a k-algebra generated by the $n-1$ elements $s_1, \ldots, s_{n-1}$, so by the inductive hypothesis there are algebraically independent $y_1, \ldots, y_q \in B$ with B integral over $k[y_1, \ldots, y_q]$. Integrality is transitive, so A is integral over $k[y_1, \ldots, y_q]$, and $q \leq n-1 \leq n$, as we sought to show.

Noether's Normalization can be thought of as a very geometric result: we shall see that any finitely generated k-algebra shall be an n-dimensional affine set along with some extra important information given by the integral extension, more on this in chapter 34. One very important is that if we have an extension F/k that is a finite-type k-algebra, is finitely generated if we allow for both addition and multiplication, it is finitely gendered by *just* allowing addition!!

Theorem 32.4.2: Zariski's Lemma

Let F/k be a field extension, and assume F is a finite-type k-algebra. Then F/k is a finite (and hence algebraic) extension.

***Proof*:**
Since F is a finite-type k-algebra, $F = k[r_1, r_2, ..., r_n]$. By Noether's Normalization Theorem, there exists a $q \in \mathbb{N}$ (possibly 0) enumerating variables $y_1, ..., y_q \in F$ such that F is integral over $k[y_1, y_2, ..., y_q]$, i.e. F is a finitely generated $k[y_1, ..., y_q]$-module. We can re-phrase this by saying we have a finite integral extension $F/k[y_1, y_2, ..., y_q]$. By proposition 26.1.8, since F is an integral domain, F is a field if and only if $k[y_1, y_2, ..., y_q]$ is a field. But then, $k[y_1, y_2, ..., y_q]$ is a field if and only if there are no indeterminate variables, i.e. $q = 0$. Thus, we get the finite integral extension F/k, which is equivalent to saying we get a finite field extension, as we sought to show.

The last two theorem's are true no matter what field we are working over. The following theorem requires k to be algebraically closed.

Theorem 32.4.3: Hilbert's Nullstellensatz - Weak Version

Let k be an algebraically closed field. Then M is a maximal ideal of the polynomial ring $k[x_1, ..., x_n]$ if and only if

$$M = (x_1 - a_1, x_2 - a_2, ..., x_n - a_n)$$

for any $a_1, a_2, ..., a_n \in k$. As a result, the maps:

$$\{\text{Points in } \mathbb{A}^n\} \underset{\mathcal{Z}}{\overset{\mathcal{I}}{\rightleftarrows}} \{\text{Maximal ideals in } \Gamma(\mathbb{A}^n)\}$$

are in bijective correspondence, and if $I \subseteq \Gamma(\mathbb{A}^n)$ is a proper ideal, then $\mathcal{Z}(I) \neq \emptyset$

***Proof*:**
Certainly, $(x_1 - a_1, ..., x_n - a_n)$ is a maximal ideal in $k[x_1, x_2, ..., x_n]$ since its quotient is k. Conversely, suppose M is a maximal ideal in $k[x_1, x_2, ..., x_n]$. Consider $F = k[x_1, x_2, ..., x_n]/M$. Then since $k \subseteq F$, F/k is a field extension that is also a finitely generated k-algebra (generated by $\overline{x_1}, ...\overline{x_n}$). By Zariski's lemma, F/k is a finite field extension, and hence is algebraic over k.

Now, we take advantage of the fact that k is algebraically closed, meaning there does not exist a non-trivial algebraic extension of k (lemma 19.5.2), implying that $F \cong_k k$, in particular we $\overline{x_i} \mapsto a_i$ for some $a_i \in k$. Thus, this is a k-algebra homomorphism, and $\overline{a_i} \in F$, $\overline{x_i - a_i} \mapsto a_i - a_i = 0$, which since the to fields are isomorphic, they are in bijective correspondence, implying $\overline{x_i - a_i} = \overline{0}$, i.e. $x_i - a_i \in M$. Thus, we must have $x_i - a_i \in M$ for every x_i, implying that $(x_1 - a_1, ..., x_n - a_n) \subseteq M$, which by maximality shows that $(x_1 - a_1, ..., x_n - a_n) = M$.

As a consequence, if I is any ideal of $k[x_1, x_2, ..., x_n]$, then $I \subseteq M$ for some maximal ideal M. By what we have just shown, for some $a_1, ..., a_n$, $M = (x_1 - a_1, ..., x_n - a_n)$. Thus, $(a_1, ..., a_n) \in \mathcal{Z}(I)$, showing that $\mathcal{Z}(I)$ is non-empty.

Theorem 32.4.4: Hilbert's Nullstellensatz

Let k be an algebraically closed field. Then for any ideal $I \subseteq k[x_1, x_2, ..., x_n]$,

$$\mathcal{I}(\mathcal{Z}(I)) = \sqrt{I} = \text{rad}(I)$$

Furthermore, the maps $\mathcal{I}$ and $\mathcal{Z}$ are order-reversing bijections:

$$\left\{\begin{matrix}\text{Algebraic Sets} \\ (= \text{closed sets})\end{matrix}\right\} \underset{\mathcal{Z}}{\overset{\mathcal{I}}{\rightleftarrows}} \{\text{Radical Ideals}\}$$

Under this bijection the *irreducible* algebraic sets, that is the affine varieties, correspond to the *prime* ideals, and the points to the maximal ideals.

Example 32.4.5: The Nullstellensatz in Practice

1. *Radicals are unavoidable.* In $k[x]$ take $I = (x^2)$. Then $\mathcal{Z}(I) = \{0\}$ and $\mathcal{I}(\{0\}) = (x)$, so
$$\mathcal{I}(\mathcal{Z}(I)) = (x) = \sqrt{(x^2)} \neq (x^2)$$
The theorem recovers $\sqrt{I}$ and nothing finer: passing to zero sets forgets multiplicity, which is the observation chapter 42 has to work around.

2. *A two-variable case.* Let $I = (x^2, xy) \subseteq k[x, y]$. Then $\mathcal{Z}(I) = \mathcal{Z}(x)$, the y-axis, so $\mathcal{I}(\mathcal{Z}(I)) = (x)$. Directly, $\sqrt{I} = (x)$ as well: $x^2 \in I$ gives $x \in \sqrt{I}$, and conversely every element of I is divisible by x.

3. *Algebraic closure is essential.* Over $\mathbb{R}$ take $I = (x^2 + 1) \subseteq \mathbb{R}[x]$. Then $\mathcal{Z}(I) = \emptyset$, so $\mathcal{I}(\mathcal{Z}(I)) = \mathbb{R}[x] = (1)$, while $\sqrt{I} = (x^2 + 1)$ because $(x^2 + 1)$ is maximal. The two differ, and the theorem fails. Over $\mathbb{C}$ the zero set is $\{\pm i\}$ and $\mathcal{I}(\{\pm i\}) = (x^2 + 1) = \sqrt{I}$ as promised.

4. *The bijection at work.* Under theorem 32.4.4 the maximal ideal $(x - a, y - b)$ corresponds to the point (a, b), the prime $(y - x^2)$ to the parabola, and the ideal $(y^2 - x^4) = \big((y - x^2)(y + x^2)\big)$ to the union of two parabolas. That ideal is already radical, being an intersection of the two primes $(y - x^2)$ and $(y + x^2)$, and reducibility of the zero set corresponds to the ideal failing to be prime rather than failing to be radical.

The refinement matters, and mixing the three levels up is the standard way to misread the theorem. An algebraic set is closed and corresponds to a radical ideal; it is a variety exactly when that radical ideal is prime (proposition 32.3.3); and it is a point exactly when the ideal is maximal (theorem 32.4.3). Every prime is radical, so the varieties sit inside the algebraic sets on one side just as the primes sit inside the radicals on the other, and the bijection restricts.

***Proof*:**
First, we have already shown that $\text{rad}(I) \subseteq \mathcal{I}(\mathcal{Z}(I))$ (proposition 32.2.7), so it remains to show that $\text{rad}(I) \supseteq \mathcal{I}(\mathcal{Z}(I))$. By Hilbert's basis theorem, we have that $I = (f_1, f_2, ..., f_n)$. Let $g \in \mathcal{I}(\mathcal{Z}(I))$. If we show that $g^N \in I$ for some $N \in \mathbb{N}_{>0}$, this would imply $g \in \text{rad}(I)$. To that end, we employ the following trick known as the Rabinowitsch trick: introduce a new variable

x_{n+1} and consider the ideal:

$$(f_1, ..., f_n, x_{n+1}g - 1) = I' \subseteq k[x_1, ..., x_n, x_{n+1}]$$

By definition of g, at any point where each $f_1, f_2, ..., f_n$ vanish, g also vanishes (since $g \in \mathcal{I}(\mathcal{Z}(I))$). But then, $x_{n+1}g - 1$ is nonzero! Thus, $\mathcal{Z}(I') = \emptyset$ in $\mathbb{A}^{n+1}$, and by Hilbert's weak Nullstellensatz, I' cannot be a proper ideal, and so $1 \in I'$. Since $1 \in I'$, we can write it as:

$$1 = a_1 f_1 + \cdots + a_n f_n + a_{n+1}(x_{n+1}g - 1) \qquad a_i \in k[x_1, ..., x_{n+1}]$$

For the following steps, it is insightful to expand the equation:

$$1 = \sum_i^n a_i(x_1, ..., x_{n+1}) f_1(x_1, ..., x_n) + a_{n+1}(x_1, ..., x_{n+1})(x_{n+1}g(x_1, ..., x_n) - 1)$$

Now, since x_{n+1} is a free variable, this equation still holds true if we substitute x_{n+1} for another expression (it will simply limit the equation to solution which also satisfy the substituted expression). We wil choose $x_{n+1} = 1/g(x_1, ..., x_n)$ so we get the following expression in $k(x_1, ..., x_n)$:

$$1 = \sum_i^n a_i \left(x_1, ..., x_n, \frac{1}{g(x_1, ...x_n)} \right) f_i(x_1, ..., x_n)$$

Importantly for us, the only terms in the denominator would be some powers of $g(x_1, ..., x_n)$. Thus, for suitably large $N \in \mathbb{N}$, we may re-write the right hand side as:

$$1 = \sum_i^n \frac{b_i\,(x_1, ..., x_n)\, f_i(x_1, ..., x_n)}{g(x_1, ..., x_n)^N}$$

for suitable $b_1, ..., b_n \in k[x_1, ..., x_n]$. Multiplying both sides by the denominator gives

$$g(x_1, ..., x_n)^N = \sum_i^n b_i(x_1, ..., x_n) f_i(x_1, ..., x_n)$$

an identity between polynomials, so it holds in $k[x_1, \ldots, x_n]$ and not just in the fraction field. The right hand side lies in I, so $g^N \in I$ and therefore $g \in \mathrm{rad}(I)$. As g was arbitrary, $\mathcal{I}(\mathcal{Z}(I)) \subseteq \mathrm{rad}(I)$, and with the reverse inclusion already in hand, $\mathcal{I}(\mathcal{Z}(I)) = \mathrm{rad}(I)$.

It remains to see that the two maps are mutually inverse bijections between algebraic sets and radical ideals. If I is radical then $\mathcal{I}(\mathcal{Z}(I)) = \mathrm{rad}(I) = I$, which is one composite. For the other, let A be an algebraic set, say $A = \mathcal{Z}(J)$. Then $\mathcal{Z}(\mathcal{I}(A)) = A$ by proposition 31.2.11(2). Finally $\mathcal{I}(A)$ really is radical: if $f^m \in \mathcal{I}(A)$ then $f(a)^m = 0$ for every $a \in A$, and k is a field, so $f(a) = 0$ and $f \in \mathcal{I}(A)$. Hence the maps are inverse to each other, and both reverse inclusion by proposition 31.2.5 and proposition 31.2.10.

For the refinement, $\mathcal{I}(A)$ is prime if and only if A is irreducible (proposition 32.3.3), and maximal if and only if A is a point (theorem 32.4.3), so the bijection restricts to varieties against primes and to points against maximal ideals, as we sought to show.

Corollary 32.4.6: Nullstellensatz in Algebraic Closure

Let k be any field with algebraic closure $\overline{k}$, and $I \subseteq k[x_1, ..., x_n]$ an ideal. Then:

$$\mathcal{I}_k(\mathcal{Z}_{\overline{k}}(I)) = \sqrt{I}$$

As a particular result, $I = (1)$ if and only if the polynomials in I have no common zero in $\overline{k}^n$.

***Proof*:**
Let $I^e = I\overline{k}[x_1, \ldots, x_n]$ be the extension of I to the algebraic closure. Since $\overline{k}$ is algebraically closed, theorem 32.4.4 applies there and gives $\mathcal{I}_{\overline{k}}(\mathcal{Z}_{\overline{k}}(I)) = \sqrt{I^e}$. Intersecting both sides with $k[x_1, \ldots, x_n]$, the left hand side becomes $\mathcal{I}_k(\mathcal{Z}_{\overline{k}}(I))$ by definition. For the right hand side, $\sqrt{I^e} \cap k[x_1, \ldots, x_n] = \sqrt{I}$: the inclusion $\supseteq$ is immediate, and for $\subseteq$, if $f \in k[x_1, \ldots, x_n]$ has $f^m \in I^e$ then writing f^m as an $\overline{k}$-combination of generators of I and comparing coefficients against a k-basis of $\overline{k}$ exhibits f^m as a k-combination of them, so $f^m \in I$.

For the last claim, $\mathcal{Z}_{\overline{k}}(I) = \emptyset$ gives $\mathcal{I}_k(\emptyset) = k[x_1, \ldots, x_n]$, so $\sqrt{I} = (1)$ and hence $I = (1)$; the converse is immediate, as we sought to show.

32.5 The Dictionary

With these results established, let us recap all the algebraic/geometric correspondences and prove some more. There are some immediate consequence of these result. An immediate easy result is that it can finally be concluded that:

$$\mathcal{I}(A \cap B) = \sqrt{\mathcal{I}(A) + \mathcal{I}(B)}$$

Next, we now have made precise the relation between radical ideals and prime ideals, as we have fully geometrically classified radical and prime ideals. Next, we get the following dictionary between the language of geometry and the language of algebra:

Geometry	Algebra
Affine sets V	coordinate rings $k[V]$
points of V	maximal ideals of $k[V]$
closed subsets of V	radical ideals of $k[V]$
sub-varieties of V	prime ideals of $k[V]$
regular function: $\varphi : V \to W$	k-algebra homomorphism $\tilde{\varphi} : k[W] \to k[V]$

This dictionary is expanded throughout the rest of the book. As a teaser, we shall show that all PID's correspond to smooth curves (see section 50.7).

Now that we have established this definition between algebraic sets and it's algebraic counter-part, we can expand some more on the Zariski Topology:

Proposition 32.5.1: Zariski Topology is Compact

Let $\mathbb{A}_k^n$ have the Zariski topology. Then $\mathbb{A}_k^n$ is compact

***Proof*:**
Let $\mathcal{O}$ index an open cover for $\mathbb{A}_k^n$

$$\mathbb{A}_k^n = \bigcup_{\alpha \in \mathcal{O}} U_\alpha$$

By proposition 31.3.4, any open set is the union of sets of the form $D(f)$, so we may re-write this as:

$$\mathbb{A}_k^n = \bigcup_{\alpha \in \mathcal{O}'} D(f_\alpha)$$

appropriately re-indexing. Then taking the complement, we get that it's equivalent that:

$$\emptyset = \bigcap_{\alpha \in \mathcal{O}'} \mathcal{Z}(f_\alpha) = \mathcal{Z}\left(\sum_{\alpha \in \mathcal{O}'} (f_\alpha)\right)$$

By the Nullstellensatz, we get that it's equivalent that

$$1 \in \sum_{\alpha \in \mathcal{O}'} (f_\alpha)$$

Thus, for appropriate coefficients $g_i \in \Gamma(\mathbb{A}^n)$, not necessarily constants, it is equivalent that:

$$1 = g_1 f_1 + \cdots + g_n f_n \in (f_1, ..., f_n) = \sum_{i=1}^{n} (f_i)$$

But then

$$\emptyset = \bigcap_{i=1}^{n} \mathcal{Z}(f_i) \quad \Leftrightarrow \quad \mathbb{A}_k^n = \bigcup_{i=1}^{n} D(f_i)$$

so finitely many of the $D(f_\alpha)$ already cover $\mathbb{A}_k^n$, as we sought to show.

Recall that for any algebraic subset $V \subseteq \mathbb{A}_k^n$, the corresponding coordinate ring $k[V]$ is used to define the subspace topology. Using the Nullstellensatz, we may deduce that it cannot have nilpotent elements:

Corollary 32.5.2: Coordinate Ring Always Reduced

Let $V \subseteq \mathbb{A}_k^n$. be an algebraic subset and $k[V]$ the associated coordinate ring. Then $k[V]$ is has no nilpotent elements

***Proof*:**
Since $k[V] = k[x_1, x_2, ..., x_n]/I(V)$, and $I(V)$ is a radical ideal by the Nullstellensatz, the quotient cannot contain any nilpotent elements, as we sought to show.

Corollary 32.5.3: Nullstellensatz For Subspaces

Let $V \subseteq \mathbb{A}_k^n$ be an algebraic subset (i.e. a closed subset) with corresponding coordinate ring $k[V]$. Then we can define $\mathcal{Z}$ and $\mathcal{I}$ as:

$$\left\{\begin{array}{c}\text{affine algebraic subsets} \\ \text{of } V\end{array}\right\} \underset{\mathcal{Z}}{\overset{\mathcal{I}}{\rightleftarrows}} \left\{\begin{array}{c}\text{Radical Ideals} \\ \text{of } k[V]\end{array}\right\}$$

***Proof*:**
Write $\pi\colon \Gamma(\mathbb{A}_k^n) \to k[V]$ for the quotient by $\mathcal{I}(V)$. The correspondence theorem for rings makes $J \mapsto \pi^{-1}(J)$ a bijection between the ideals of $k[V]$ and the ideals of $\Gamma(\mathbb{A}_k^n)$ containing $\mathcal{I}(V)$, and it preserves radicals in both directions: $\pi^{-1}(\sqrt{J}) = \sqrt{\pi^{-1}(J)}$, since $f^m \in \pi^{-1}(J)$ says exactly $\pi(f)^m \in J$. So the radical ideals of $k[V]$ correspond to the radical ideals of $\Gamma(\mathbb{A}_k^n)$ containing $\mathcal{I}(V)$.

On the geometric side, the algebraic subsets of V are precisely the algebraic subsets of $\mathbb{A}_k^n$ contained in V, and $\mathcal{Z}$ reverses inclusion, so those correspond to the ideals containing $\mathcal{I}(V)$. Composing with theorem 32.4.4, which matches algebraic subsets of $\mathbb{A}_k^n$ against radical ideals of $\Gamma(\mathbb{A}_k^n)$, gives the stated bijection, as we sought to show.

Next, sticking to the case where $k = \overline{k}$ is algebraically closed, from this section we can deduce that any coordinate ring is finitely generated, nilpotent-free (i.e. reduced) and is a k-algebra over an algebraically closed field. We can show that all such rings appear as coordinate rings for an affine set.

We first have the following:

Definition 32.5.4: Reduced Ring

Let R be a ring. Then R is said to be *reduced* if $x^n = 0$ implies $x = 0$

(finish here)

Proposition 32.5.5: Coordinate Ring Correspondence

Let R be a ring. Then if R is:

1. Finitely generated
2. Reduced
3. over an algebraically closed field

then R is isomorphic to a coordinate ring for an appropriate dimension n of $\mathbb{A}_{\overline{k}}^n$ and $\mathcal{Z}(S) \subseteq \mathbb{A}_{\overline{k}}^n$.

***Proof*:**
Write $R = \overline{k}[t_1, \ldots, t_n]$ for a choice of finitely many generators, and let

$$\pi\colon \overline{k}[x_1, \ldots, x_n] \to R \qquad x_i \mapsto t_i$$

be the resulting surjection of $\overline{k}$-algebras, with $I = \ker \pi$, so that $R \cong \overline{k}[x_1, \ldots, x_n]/I$. Since R is

reduced, I is a radical ideal: if $f^m \in I$ then $\pi(f)^m = 0$ in R, so $\pi(f) = 0$ and $f \in I$.

Set $V = \mathcal{Z}(I) \subseteq \mathbb{A}^n_{\overline{k}}$. By theorem 32.4.4 the ground field being algebraically closed gives $\mathcal{I}(V) = \mathcal{I}(\mathcal{Z}(I)) = \sqrt{I} = I$. Therefore

$$\Gamma(V) = \frac{\overline{k}[x_1, \ldots, x_n]}{\mathcal{I}(V)} = \frac{\overline{k}[x_1, \ldots, x_n]}{I} \cong R$$

so R is the coordinate ring of the algebraic set V, as we sought to show.

Notice that through this result, we can define an affine set without the reference of an ambient space, similar to how we may define a manifold without the need an ambient embedding space. This idea is greatly generalized by scheme theory, which chapter 49 points the reader toward.

Exercise 32.5.1

1. Deduce the strong Nullstellensatz from the weak one by the Rabinowitsch trick: given f vanishing on $\mathcal{Z}(I)$, apply the weak form to the ideal generated by I and $1 - yf$ in one extra variable y.
2. Show that every maximal ideal of $k[x_1, \ldots, x_n]$ is $(x_1 - a_1, \ldots, x_n - a_n)$ for a unique point $(a_1, \ldots, a_n)$, and explain why this fails over $\mathbb{R}$.
3. Show that the Nullstellensatz fails over a field that is not algebraically closed, by computing $\mathcal{I}(\mathcal{Z}(x^2 + 1))$ in $\mathbb{R}[x]$ and comparing with $\sqrt{(x^2 + 1)}$.
4. Show that $\mathcal{Z}$ and $\mathcal{I}$ are mutually inverse inclusion-reversing bijections between the radical ideals of $k[x_1, \ldots, x_n]$ and the algebraic subsets of $\mathbb{A}^n_k$, and that under this correspondence prime ideals match irreducible sets.
5. Use corollary 32.4.6 to show that a system of polynomials over $\mathbb{Q}$ with no common zero in $\overline{\mathbb{Q}}$ generates the unit ideal, and contrast this with $x^2 + 1$ over $\mathbb{R}$, which has no real zero yet generates a proper ideal. What exactly does the closure give?

33

Rational Maps and Birational Classification

Isomorphism is a demanding relation between varieties, and the classification problem it poses is largely intractable. Weakening it produces a relation that can be classified: two varieties are birationally equivalent when they agree on a dense open set. Algebraically this replaces the coordinate ring by its field of fractions, and fields of transcendence degree d are far simpler objects than finitely generated reduced algebras.

The price is that the maps involved are no longer defined everywhere. This chapter pays that price carefully: it locates the domain of definition of a rational function, shows the domain is always dense, and then proves that every variety is birationally equivalent to a hypersurface.

33.1 Rational Functions and the Function Field

Let V be a variety and $k = \overline{k}$ be an algebraically closed field. In this section, we take advantage of the fact that we may localize $k[x_1, ..., x_n]/\mathcal{I}(V)$. By Noether's Normalization Theorem (theorem 32.4.1) $k[V]/k$ is a finite transcendental extension followed by an integral extension. As $k[V]$ is an integral domain we may take its field of fractions $k(V)$, and passing to fraction fields in Noether normalization exhibits $k(V)$ as a *finite* extension of the purely transcendental field $k(y_1, \ldots, y_q)$. The extension is genuinely finite and not an equality: for the cuspidal cubic $V = \mathcal{Z}(y^2 - x^3)$ we have $k[V] \cong k[t^2, t^3]$, integral over $k[x]$, while $k(V) = k(t)$ is a degree-two extension of $k(x) = k(t^2)$. Were $k(V)$ always purely transcendental every variety would be rational, which item (4) of example 33.3.8 disproves. What *is* intrinsic is q, the transcendence degree, which chapter 34 identifies with $\dim V$. Geometrically $k(V)$ shall represent all *rational polynomial functions*, or all rational polynomials functions defined on V. Note that we must be a bit more careful in interpreting elements of $k(V)$ as functions: if

$f/g \in k(V)$, then if $g(p) = 0$ for some $p \in V$ then we get the undefined $f(p)/g(p) = f(p)/0$. We shall address this soon.

Rational functions give a weaker relation than isomorphism for classifying varieties. We shall see that being *birationally equivalent* is weaker than being a (regular) isomorphism, giving coarser isomorphism classes of varieties that shall give us more information about algebraic sets. As an example, elliptic curves[1] shall require three curve invariants to be classified (the genus, the j-invariant, and the Mordell-Weil group of the curve). However, up to birational map it shall only require the genus and we can without loss of generality work with smooth elliptic curves. Though coarser, it is nonetheless a powerful tool in gathering information about varieties.

Definition 33.1.1: Rational Functions

Let V be an affine variety. Then the fraction field of $k[V]$ is called the field of *rational function on* V, and is denoted $k(V)$. An element of $k(V)$ is called a *rational function*.

The *evaluation* of a rational function at p is defined whenever it admits a representative f/g with $g(p) \neq 0$. Two rational functions are equal if they agree at every point where both are defined. The points at which *no* representative has nonvanishing denominator form the *pole set*; being a pole is a property of the function, not of a chosen representative.

If $\varphi \in k(V)$, then $\varphi = \frac{f}{g}$ where $g \notin I(V)$ (or else the denominator would be the zero function, contradicting the construction of the field of fractions). We shall say that two rational polynomial f/g and f'/g' represent the same rational function if and only if $fg' - f'g \in I(V)$. Note that if $k[V]$ is not a UFD, then there can be representatives of $k(V)$ which are not equivalent up to a unit:

Example 33.1.2: Not UFD, Different Polynomial Representatives

Let $V = \mathcal{Z}(xw - yz) \subseteq \mathbb{A}^4_k$. Show that:

$$\frac{\overline{x}}{\overline{y}} = \frac{\overline{z}}{\overline{w}} = f \in k(V)$$

if $y \neq 0$ or $w \neq 0$.

Another way of constructing $k(V)$ is the following: take the collection

$$\mathcal{O}_V = \{\varphi = f/g \in k(x_1, ..., x_n) \mid g \notin I(V)\}$$

then take the subset $\mathfrak{m}_V = \{\varphi = f/g \in \mathcal{O}_V \mid f \in I(V)\}$. This is the unique maximal ideal of the local ring $\mathcal{O}_V$, and

$$k(V) \cong \mathcal{O}_V/\mathfrak{m}_V$$

since a rational function on V is a ratio f/g of polynomials with $g \notin I(V)$, taken up to the relation that identifies two such ratios agreeing on V, and that relation is exactly congruence modulo $\mathfrak{m}_V$. This shall become the dominant way of interpreting the set of rational functions when working with quasi-projective varieties (see section 39.4)[2].

[1] for those familiar with complex geometry, genus 1 curves

[2] In Scheme theory, this shall be the rational functions at the point (closed or non-closed) associated to X

33.2 Domains of Definition and Local Rings

A key difference between regular and rational functions is that a rational function need not be defined at every point. In fact, it *has* to be the case that a rational function is not defined on a finite set of points for it to not be equivalent to a regular function (when working over an algebraically closed field). To see this, consider the following definition:

Definition 33.2.1: Regular Point

Let $\varphi \in k(X)$ be a rational function. Then a *regular point* at $x \in X$ is a point where we can represent φ as f/g, $\varphi(x) = f(x)/g(x)$, and $g(x) \neq 0$. In this case, the element $f(x)/g(x)$ in k is called the *value* of φ at x and is denoted $\varphi(x)$

For example, take $\varphi = 1/x$ on $\mathbb{A}^1_k$. Then all points except 0 are regular points. If $\varphi = f/g$ is regular at a point x, then it is regular in an open neighborhood of X, namely the neighborhood $D(g) \cap X$. Some authors put that a rational function is regular at a point if it is regular in an open neighborhood.

Proposition 33.2.2: Regular at All Points, then Regular

Let $\varphi \in k(X)$ be a rational function that is regular at all points. Then φ is a regular function

***Proof*:**
Let $\varphi \in k(X)$ be a rational function that is regular at every point. Then for each $x \in X$, we can represent φ as f_x/g_x. Take $\mathfrak{a} = (g_x)_{x \in X}$. Then as $k[X]$ is Noetherian, this is a finitely generated ideal:

$$\mathfrak{a} = (g_{x_1}, ..., g_{x_n})$$

Note that the g_{x_i} have no common zero in X: at any $x \in X$ the chosen g_x satisfies $g_x(x) \neq 0$, and $g_x \in \mathfrak{a}$. So $\mathcal{Z}(\mathfrak{a}) = \emptyset$ in X, and the weak Nullstellensatz (theorem 32.4.3) applied in $k[X]$ forces

$$\mathfrak{a} = (1)$$

In particular, there exist $u_i \in k[X]$ such that

$$\sum_{i=1}^{n} u_i g_i = 1$$

The key point is that $\varphi = f_i/g_i$ is an identity in the field $k(X)$, so $\varphi g_i = f_i$ holds globally, not just on the neighbourhood where g_i is nonzero. Multiplying the displayed identity by φ therefore gives

$$\varphi = \varphi \cdot 1 = \sum_{i=1}^{n} u_i(\varphi g_i) = \sum_{i=1}^{n} u_i f_i$$

whose right hand side lies in $k[X]$, so φ is regular, completing the proof.

The Nullstellensatz is essential for the proof, i.e. that k is an algebraically closed field, or else this result is false!

Example 33.2.3: Rational Function That is Regular

the function

$$\frac{x}{x+100}$$

is regular on $\mathcal{Z}(x^2+y^2-1) \subseteq \mathbb{A}^2_{\mathbb{R}}$ even though it is not a polynomial: there does not exist a point (x,y) satisfying x^2+y^2-1 such that $x+100=0$ namely since all points x where $x^2+y^2-1=0$ must be within $[-1,1]$[a]

[a]This failure is *not* present when working with the scheme $\operatorname{Spec}\mathbb{R}[x,y]/(x^2+y^2-1)$ as $x+100$ has a zero at the prime ideal $(x-100, y^2+9999)$, and so this "anomaly" is present if we do not work in the right context

Hence we always have points on which a rational function is not defined. This set of points will always be dense:

Lemma 33.2.4: Domain of Definition

Let $\varphi \in k(V)$ be a rational function. Then set of regular points is non-empty, open and dense.

***Proof*:**

Let $\varphi = f/g$ and take $U = \{p \in V \mid g(p) \neq 0\} = D(g) \cap V$. Then in V, this set is certainly open, and as g is not the zero function there is certainly at least one point $p \in V$ such that $g(p) \neq 0$.

To show U is dense, let $O \subseteq V$ be any nonempty open set; it suffices to show $U \cap O \neq \emptyset$. Suppose instead $U \cap O = \emptyset$. Then

$$V = (U \cap O)^c = U^c \cup O^c$$

writes V as a union of two closed sets, and both are *proper*: $U^c \neq V$ because $U \neq \emptyset$, and $O^c \neq V$ because $O \neq \emptyset$. That contradicts the irreducibility of V. Hence U meets every nonempty open set, which is density, completing the proof.

Definition 33.2.5: Domain of Definition

Let $\varphi \in k(V)$ a rational function. Then the set of regular point is called the *domain of definition.*

Corollary 33.2.6: Collection of Rational Points

Let $\varphi_1, ..., \varphi_n \in k(X)$ be rational functions on a variety X. Then their common domain of definition is open, non-empty, and dense.

***Proof*:**

Let U_i be the domain of definition of φ_i, which by lemma 33.2.4 is open, nonempty and dense. A finite intersection of open sets is open, so $\bigcap_i U_i$ is open.

For nonemptiness and density it is enough to show that $\bigcap_i U_i$ meets every nonempty open $O \subseteq X$, and by induction it suffices to treat $n=2$. Given nonempty open O, density of U_1 gives $U_1 \cap O \neq \emptyset$, and $U_1 \cap O$ is open, so density of U_2 gives $U_2 \cap (U_1 \cap O) \neq \emptyset$. Hence $U_1 \cap U_2$ meets O. Taking $O = X$ gives nonemptiness, as we sought to show.

In fact, as the open sets in the Zariski topology are "huge", it suffices to define a rational mapping on any open subset:

Proposition 33.2.7: Suffice To Define On Open Set

Let $\varphi \in k(X)$ be a rational function. Then if φ is specified on some non-empty open subset $U \subseteq X$, then there is a unique extension of φ to all of X.

***Proof*:**
Take $\varphi \in k(X)$. If $\varphi = 0$, there is nothing to prove, so assume $\varphi \neq 0$. Say we specify what φ is on an open non-empty subset $U \subseteq X$, call this function $\varphi|_U$. Then let's say that φ' is a rational function where φ' on U is equal to $\varphi|_U$ (where a-priori it is unknown where there is a unique extension, and hence it may be another function). Consider $\varphi - \varphi' = \varphi''$. On U, this function is identically 0. Take the representative $\varphi'' = f/g$ on U so that $f = 0$. Then take $X_1 \subseteq X$ given by $f = 0$. This is not all of X as $\varphi \neq 0$, however we then have $X_1 \cup (X \setminus U) = X$ where both are proper subsets, contradicting irreducibility of X, completing the proof.

We are often interested in all the functions that are defined at a particular point, namely since geometrically much of the information of an object is given by collections of functions at every point (the reader familiar with differential geometry should be thinking of germs). To that end, we box the following

Definition 33.2.8: Stalk At A Point

Let V be an affine variety and $p \in V$. Then $\mathcal{O}_p(V) \subseteq k(V)$ is the collection of rational functions:

$$\mathcal{O}_p(V) = \{f/g \in k(V) \mid g(p) \neq 0\}$$

Proposition 33.2.9: Regular Functions and Stalk

$$k[V] = \bigcap_{p \in V} \mathcal{O}_p(V)$$

***Proof*:**
Certainly $k[V] \subseteq \mathcal{O}_p(V)$ for all $p \in V$ so $k[V] \subseteq \bigcap_{p\in V} \mathcal{O}_p(V)$.

For the converse, fix $\varphi \in \bigcap_{p\in V} \mathcal{O}_p(V)$ and consider its *ideal of denominators*

$$\mathfrak{d}_\varphi = \{h \in k[V] \mid h\varphi \in k[V]\}$$

This is an ideal: it is closed under addition, and if $h\varphi \in k[V]$ then $(ah)\varphi = a(h\varphi) \in k[V]$ for any $a \in k[V]$. Its zero set is exactly the pole set of φ. Indeed, if $p \notin \mathcal{Z}(\mathfrak{d}_\varphi)$ then some $h \in \mathfrak{d}_\varphi$ has $h(p) \neq 0$, and writing $\varphi = (h\varphi)/h$ exhibits a representative with nonvanishing denominator at p, so φ is regular at p; conversely a representative u/v with $v(p) \neq 0$ puts v in $\mathfrak{d}_\varphi$ with $v(p) \neq 0$, so $p \notin \mathcal{Z}(\mathfrak{d}_\varphi)$. In particular the pole set is closed.

Now φ lies in every $\mathcal{O}_p(V)$, so it is regular at every point and its pole set is empty, that is $\mathcal{Z}(\mathfrak{d}_\varphi) = \emptyset$. Lifting $\mathfrak{d}_\varphi$ to $k[x_1, \ldots, x_n]$ and applying the Nullstellensatz (theorem 32.4.3) gives

$\mathfrak{d}_\varphi = k[V]$, so $1 \in \mathfrak{d}_\varphi$ and therefore

$$\varphi = 1 \cdot \varphi \in k[V]$$

as we sought to show.

Proposition 33.2.10: Stalks Are Local Noetherian Domains

let V be a variety and $p \in V$. Then $\mathcal{O}_p(V)$ is a local Noetherian domain

***Proof*:**
Domain. $\mathcal{O}_p(V)$ is by construction a subring of the field $k(V)$, and a subring of a field has no zero divisors.

Local. Put

$$\mathfrak{m}_p = \{f/g \in \mathcal{O}_p(V) \mid f(p) = 0\}$$

This is the kernel of the evaluation map $\mathrm{ev}_p \colon \mathcal{O}_p(V) \to k$, $f/g \mapsto f(p)/g(p)$, which is well defined precisely because $g(p) \neq 0$ and is a surjective ring homomorphism; so $\mathfrak{m}_p$ is an ideal with $\mathcal{O}_p(V)/\mathfrak{m}_p \cong k$, hence maximal. Every element outside $\mathfrak{m}_p$ is a unit: if $f/g \in \mathcal{O}_p(V)$ has $f(p) \neq 0$ then g/f again has nonvanishing denominator at p, so it lies in $\mathcal{O}_p(V)$ and inverts f/g. A proper ideal contains no unit, so it is contained in $\mathfrak{m}_p$; thus $\mathfrak{m}_p$ is the unique maximal ideal and $\mathcal{O}_p(V)$ is local.

Noetherian. $\mathcal{O}_p(V)$ is the localization of $k[V]$ at the prime $\mathcal{I}(p)$, and $k[V]$ is Noetherian as a quotient of the Noetherian ring $\Gamma(\mathbb{A}^n)$. A localization of a Noetherian ring is Noetherian, since every ideal of $S^{-1}R$ is the extension of its contraction to R, and extension carries a finite generating set to a finite generating set. Hence $\mathcal{O}_p(V)$ is Noetherian, completing the proof.

In section 35.1, we shall see that when V is a curve and $\mathcal{O}_p(V)$ is a *discrete valuation ring*, then V is *smooth* at p. This requires a lot of build-up, and so we shall set stalks aside for now.

33.3 Rational and Birational Maps

Let us now generalize regular maps:

Definition 33.3.1: Rational Map

Let X be a variety and $Y \subseteq \mathbb{A}^m_k$ a variety. A *rational mapping* $\varphi \colon X \dashrightarrow Y$ is a tuple

$$\varphi = (\varphi_1, ..., \varphi_m) \qquad \varphi_i \in k(X)$$

of rational functions such that $(\varphi_1(x), \ldots, \varphi_m(x)) \in Y$ for every x in the common domain of definition of the φ_i, which by corollary 33.2.6 is a dense open subset of X. A rational mapping all of whose components happen to be regular is exactly a regular map.

Example 33.3.2: Rational Maps

1. *The circle, parameterized.* Let $C = \mathcal{Z}(x^2 + y^2 - 1) \subseteq \mathbb{A}^2_k$ and consider
$$\varphi \colon C \dashrightarrow \mathbb{A}^1_k \qquad \varphi(x, y) = \frac{y}{1 - x}$$
This is a rational map, its single component lying in $k(C)$. It is undefined where $1 - x$ vanishes on C, that is at the point $(1, 0)$, and defined on the dense open complement. Its inverse is the regular map
$$t \mapsto \left(\frac{t^2 - 1}{t^2 + 1}, \frac{2t}{t^2 + 1} \right)$$
so C and $\mathbb{A}^1_k$ are birational, though not isomorphic: the map misses $(1, 0)$ in one direction and the two points with $t^2 = -1$ in the other.

2. *A rational map with no regular representative.* On $\mathbb{A}^2_k$ the assignment $(x, y) \mapsto x/y$ is a rational map $\mathbb{A}^2_k \dashrightarrow \mathbb{A}^1_k$ whose domain of definition is $D(y)$. It cannot be extended to the origin: along the line $y = cx$ it is constantly $1/c$, so every value of k is taken arbitrarily close to the origin and no single value can be assigned there.

3. *Regular maps are the special case.* The map $(x, y) \mapsto (x^2, xy)$ has polynomial components, so its domain of definition is all of $\mathbb{A}^2_k$ and it is regular. Its image, computed in example 41.3.5, is not closed, which is a separate matter from being defined everywhere.

The image of the rational map shall be denoted $\varphi(X)$, even though not every point may be regular. Note that a rational map shall necessarily map an open subset $U \subseteq X$ into Y, and hence it is well-defined by proposition 33.2.7. By proposition 33.2.7, an equivalent definition of a rational map is that it is the collection of equivalence relations $[(\varphi, U)]$ with $U \subseteq X$ open and $\varphi : U \to Y$ where $[(\varphi, U)] \sim [(\psi, V)]$ if and only if
$$\varphi|_{U \cap V} = \psi|_{U \cap V}$$
This equivalent to definition 33.3.1, and is more prominent in the context of algebraic geometry. Its upside is that each representative is a well-defined map and hence can be seen as the appropriate quotient of some hom-sets, while its downside is that a rational mapping is now an equivalence relationship.

The following is the equivalent of being surjective:

Definition 33.3.3: Dominating Rational Map

Let $f : X \dashrightarrow Y$ be a rational map. Then f is said to be *dominating* if $f(U)$ is dense in Y.

Recall that if A, B are local rings where $A \subseteq B$ is a subring, then B dominates A if $\mathfrak{m}_A \subseteq \mathfrak{m}_B$. This vocabulary shall be made clear from the following

Proposition 33.3.4: Properties of Rational Maps

Let $F : X \dashrightarrow Y$ be a dominating rational map, $U \subseteq X$ and $V \subseteq Y$ affine open subsets where $f : U \to V$ represents F. Then:

1. If $\varphi : X \dashrightarrow Y$ and $\psi : Y \dashrightarrow Z$ are dominating rational maps, then $\psi \circ \varphi$ is dominating and $(\psi \circ \varphi)^\# = \varphi^\# \circ \psi^\#$.
2. $f^\# : k[V] \to k[U]$ is injective, hence extends to an injective map $k(V) \to k(U)$, and so gives $F^\# : k(Y) \hookrightarrow k(X)$, i.e. a field extension $k(X)/k(Y)$. It is an *embedding*, not an isomorphism; $F^\#$ is an isomorphism exactly when F is birational (proposition 33.3.6).
3. If p is in the domain of F and $F(p) = q$, then $\mathcal{O}_p(X)$ dominates $F^\#(\mathcal{O}_q(Y))$. Conversely, if $p \in X$ and $q \in Y$ are such that $\mathcal{O}_p(X)$ dominates $F^\#(\mathcal{O}_q(Y))$, then p belongs to the domain of F and $F(p) = q$.
4. Any k-homomorphism $k(Y) \to k(X)$ induces a unique dominating rational map $X \dashrightarrow Y$.

***Proof*:**

1. Let $U' \subseteq X$ be a dense open set on which φ is defined. Then $\psi \circ \varphi$ is defined on $U' \cap \varphi^{-1}(V')$ for V' a dense open set on which ψ is defined, and this is nonempty because $\varphi(U')$ is dense in Y and so meets V'. Its image contains $\psi(\varphi(U') \cap V')$, which is dense in Z since ψ is dominating and $\varphi(U') \cap V'$ is a nonempty open subset of V'. So $\psi \circ \varphi$ is dominating. Functoriality is then the computation $(\psi \circ \varphi)^\#(h) = h \circ \psi \circ \varphi = \varphi^\#(\psi^\#(h))$, so $(\psi \circ \varphi)^\# = \varphi^\# \circ \psi^\#$: pullback reverses composition.
2. Recall $f^\#(\varphi) = \varphi \circ f$. Suppose $f^\#(\varphi) = f^\#(\psi)$, that is $\varphi \circ f = \psi \circ f$. Then φ and ψ agree on $f(U)$, which is dense in V because F is dominating; two regular functions agreeing on a dense subset of a variety are equal (their difference vanishes on a dense set, hence on its closure). So $\varphi = \psi$ and $f^\#$ is injective. An injective map of integral domains extends to their fraction fields, giving $k(V) \hookrightarrow k(U)$, and since $U \subseteq X$ and $V \subseteq Y$ are nonempty open subsets of varieties we have $k(U) = k(X)$ and $k(V) = k(Y)$ by proposition 33.2.7. Hence $F^\# : k(Y) \hookrightarrow k(X)$ is a field embedding. It need not be surjective: $F^\#$ is onto exactly when F admits a rational inverse, which is proposition 33.3.6.
3. If $f(p) = q$, then it is a matter of pushing around the definition to see that $\mathcal{O}_p(X)$ dominates $F^\#(\mathcal{O}_q(Y))$. Conversely, suppose $\mathcal{O}_p(X)$ dominates $F^\#(\mathcal{O}_q(Y))$. Take an affine neighbourhood V of p and W of q where
$$k[W] = k[y_1, ..., y_n]$$
and $F^\#(y_i) = \frac{a_i}{b_i}$ for $a_i, b_i \in k[V]$ with $b_i(p) \neq 0$. Take $b = b_1 \cdots b_n$, and take the localization V_b. Then
$$F^\#(k[W]) \subseteq k[V_b]$$
Hence the map $F^\# : k[W] \to k[V_b]$ induces a unique morphism $f : V_b \to W$. Then if $g \in k[W]$ vanishes at q, $F^\#(g)$ vanishes at p, but then it must be that $f(p) = q$
4. If $\varphi : k(Y) \to k(X)$ wit h$\varphi(k[Y]) \subseteq k[X_b]$, for some $b \in k[X]$, φ induces a morphism $f : X_b \to Y$. Hence $f(X_b)$ is dense in Y as $f^\#$ is injective, giving us the desired result.

Definition 33.3.5: Birational Map

Let $\varphi : X \dashrightarrow Y$ be a rational map. Then φ is said to be *birational* if the image of φ is dense and there exists a rational map $\psi : Y \dashrightarrow X$ with dense image such that $\varphi \circ \psi = \psi \circ \varphi = \mathrm{id}$.

Proposition 33.3.6: Birational Maps and Isomorphisms

Let $\varphi\colon X \dashrightarrow Y$ be a dominating rational map of varieties. Then φ is birational if and only if $\varphi^{\#}\colon k(Y) \to k(X)$ is an isomorphism of fields over k.

***Proof*:**
Suppose φ is birational, with rational inverse ψ. Both composites are the identity, so applying proposition 33.3.4(1) gives $\varphi^{\#} \circ \psi^{\#} = (\psi \circ \varphi)^{\#} = \mathrm{id}$ and likewise $\psi^{\#} \circ \varphi^{\#} = \mathrm{id}$. Hence $\varphi^{\#}$ is an isomorphism with inverse $\psi^{\#}$.

Conversely, suppose $\varphi^{\#}$ is an isomorphism. Then $(\varphi^{\#})^{-1}\colon k(X) \to k(Y)$ is a k-homomorphism of function fields, so by proposition 33.3.4(4) it induces a dominating rational map $\psi\colon Y \dashrightarrow X$ with $\psi^{\#} = (\varphi^{\#})^{-1}$. Then $(\psi \circ \varphi)^{\#} = \varphi^{\#} \circ \psi^{\#} = \mathrm{id}$, and the uniqueness clause of proposition 33.3.4(4) forces $\psi \circ \varphi = \mathrm{id}$ as rational maps; symmetrically $\varphi \circ \psi = \mathrm{id}$. So φ is birational, as we sought to show.

The next definition uses dimension, which chapter 34 develops formally; for now read $\dim V$ as the number of independent parameters a general point of V carries.


Definition 33.3.7: Rational Closed Set

Let V be a variety. Then if V is birational to $\mathbb{A}^n_k$ or $\mathbb{P}^n_k$, then V is called *affine rational* or *projective rational* respectively.

If V satisfies one of the above two conditions and has dimension $1, 2$ or codimension 1, then it is a *rational curve*, *rational surface*, or *rational hypersurface* respectively.

Example 33.3.8: Rational Mapping and Birational Maps

1. Naturally, all curves of order 1 (i.e., straight lines) are tautologically rational. More generally any linear subspace is rational.
2. Consider the curve given by
$$y^2 = x^2 + x^3$$
which looks like:



Label this curve C. Then this is a rational curve. To see this, consider that the line given by $y = tx$ passing through the origin intersects the curve at a single point (not counting the origin). Then substituting $y = tx$ into our equation, we get:

$$x^2(t^2 - x - 1) = 0$$

The root $x = 0$ corresponds to the origin, and the other roots $x = t^2 - 1$ corresponds to non-trivial solution. Hence, we get $x = t^2 - 1, y = t(t^2 - 1)$, and the rational map:

$$\varphi(t) = (t^2 - 1, t(t^2 - 1))$$

The inverse recovers the slope from the point: given $p = (x_0, y_0) \in C$ other than the origin, the line through p and the origin has slope y_0/x_0, so

$$\psi \colon C \dashrightarrow \mathbb{A}^1_k \qquad \psi(x, y) = \frac{y}{x}$$

is a rational map, regular away from $x = 0$. It inverts φ: substituting gives $\psi(\varphi(t)) = t(t^2 - 1)/(t^2 - 1) = t$ whenever $t^2 \neq 1$, and the two composites agree with the identity on dense open sets, which is equality of rational maps. So φ is birational. It is not an isomorphism: φ sends both $t = 1$ and $t = -1$ to the origin, the node of C, so it is not even injective.

If we take $k = \mathbb{Q}$, then this gives all rational solutions to the equation $y^2 = x^3 + x^2$. The case is a little more subtle if we were looking for integer solutions to the equation, which is explored in chapter 50.

3. Let us show that all irreducible curves C of order 2 are rational (note that the above example is an order 3 curve, the maximal degree being 3). Let C be given by the equation $f(x, y)$. Take any point $(x_0, y_0) \in C$, and equation of the line through (x_0, y_0) with slope t

$$y - y_0 = t(x - x_0)$$

Label this line L_t. Let us find the points of intersection of the curve C with line L_t. To do so, we substitute:

$$f(x, y_0 + t(x - x_0)) = 0$$

which is equivalent to the mapping $\mathbb{A}^1_k$ to the curve. This mapping is well-defined (notice it is still of degree 2). Then one of the roots is certainly x_0. Then let a denote the coefficient of x after dividing the equation $f(x, y_0 + t(x - x_0))$ by the coefficient of x^2. Then we can see that the remaining roots must be:

$$x + x_0 = -a \qquad \Rightarrow \qquad x = -x_0 - a$$

Then x is a rational function of t, and substituting the expression for x into L_t, we obtain an expression for y as a rational function of t.

Note that if the coordinates x_0, y_0 of $(x_0, y_0) \in C$ and the coefficients of $f(x, y)$ belong to some subfield $k_0 \subseteq k$, then so do the coefficients of the function that gives the parameterization. In this case, we can find the general form of the solution in rational numbers of a Diophantine equation of degree 2 by knowing *at least* one solution! However, it turns out that knowing there is at least one solution can sometimes be tricky[a]

4. More generally, an irreducible hypersurface $X \subseteq \mathbb{A}^n_k$ given by a polynomial of degree 2 $f(x_1, ..., x_n) = 0$ is rational. The proof generalizes the above and is left as an exercise. The geometric picture is projection the hypersurface to a hyper-plane via a projection that does not pass through some point x. The point x can be any point that is not a "vertex" on X, namely that for at least one variable:

$$\frac{\partial f}{\partial x_i}(x) \neq 0$$

5. The curve order 3 given by $x^3 + y^3 = 1$ is *not* rational. More generally, $x^n + y^n = 1$ is not rational for $n \geq 3$, provided $\mathrm{char} k \nmid n$. To see this, let C_n be the curve given by $x^n + y^n = 1$ and suppose it is rational so that there exists rational functions φ, ψ such that $x = \varphi(t), y = \psi(t)$. Then we may find polynomials p, q, r relatively prime such that

$$\varphi(t) = \frac{p(t)}{r(t)} \qquad \psi(t) = \frac{q(t)}{r(t)}$$

where the denominator is the same for simplicity (the same argument follows with more steps by taking p/r and q/s). Then plugging into our equation we get:

$$p(t)^n + q(t)^n - r(t)^n = 0$$

for all $t \in k$. Differentiating is legitimate and does not annihilate the exponent, since $\mathrm{char} k \nmid n$, and so we have:

$$p(t)^{n-1}p'(t) + q(t)^{n-1}q'(t) - r(t)^{n-1}r'(t) = 0$$

We now have two systems equations. Treating $p^{n-1}, q^{n-1}, -r^{n-1}$ as the unknowns, we can consider the above two equations as being a system of linear equations which has has the matrix:

$$\begin{pmatrix} p & q & r \\ p' & q' & r' \end{pmatrix}$$

Solving this system of linear equations, we get that $p^{n-1}, q^{n-1}, -r^{n-1}$ are proportional to

$$qr' - rq' \qquad rp' - pr' \qquad pq' - qp'$$

As p, q, r are relatively prime, we get that:

$$p^{n-1}\big|(qr' - rq') \qquad q^{n-1}\big|(rp' - pr') \qquad r^{n-1}\big|(pq' - qp')$$

Finally, if a, b, c are the degrees of p, q, r . If $a \geq b \geq c$, then

$$(n-1)a \leq b + c - 1$$

But $a \geq b \geq c$ gives $b + c - 1 \leq 2a - 1$, so $(n-1)a \leq 2a - 1$, forcing $(n-3)a \leq -1$, which is impossible for $n \geq 3$ and $a \geq 0$. The other orderings of a, b, c give the same contradiction by symmetry.

[a] see Legendre theorem in cite:HERE

33.4 Classification up to Birational Equivalence

Birational mappings are weaker than isomorphisms (of varieties). This problem can be translated algebraically to the difference between having $k[X]$ and $k[Y]$ be isomorphic and $k(X)$ and $k(Y)$ be isomorphic. The reader may recall from section 32.4 that $k[X]$ and $k[Y]$ must be finitely generated reduced k-algebras, $k(X)$ and $k(Y)$ finite field extensions. As the structure of field extensions is much simpler, we expect birational mappings to be much simpler. In fact, we may even classify all affine variety up to birational isomorphism:

Theorem 33.4.1: Classification of Varieties Up To Birational Map

Let X be a variety of dimension d over an algebraically closed field k. Then X is birationally isomorphic to a hypersurface in $\mathbb{A}_k^{d+1}$.

Thus, birationality of varieties reduces to the classification of hypersurfaces. Note that being birationally isomorphic to a hypersurface does not imply a curve or plane is rational. For example, the curve given by $x^3 + y^3 = 1$ is already a hypersurface in $\mathbb{A}^2$ as it is given by $\mathcal{Z}(x^3 + y^3 - 1)$, however it is not a rational curve. Its projective closure is the Fermat cubic $\mathcal{Z}(x^3 + y^3 - z^3)$, which is nonsingular, and corollary 44.4.3 shows no nonsingular plane cubic is birational to $\mathbb{A}_k^1$; the invariant responsible is the genus, which chapter 44 constructs.

That claim deserves more than a forward reference, because the curve looks as though it ought to yield. Every technique available at this point can be tried on it, and watching each one fail is the most economical argument for building the machinery of part IX.

Example 33.4.2: Why $x^3 + y^3 = 1$ Resists Parameterization

Assume char$k \neq 3$, so that the projective closure $\mathcal{Z}(x^3 + y^3 - z^3)$ is nonsingular; the excluded case is degenerate and treated at the end. Write $C = \mathcal{Z}(x^3 + y^3 - 1) \subseteq \mathbb{A}_k^2$.

Attempt 1: the chord construction. A conic is parameterized by fixing a point on it and sweeping the lines through that point, as in example 39.4.4(3). Run the identical computation on three curves, substituting the line through the chosen point and factoring out the known root.

- The conic $x^2 + y^2 = 1$ at $(1, 0)$, with $y = t(x - 1)$:

$$(x-1)\big[\,x + 1 + t^2(x-1)\,\big] = 0$$

  leaving a factor *linear* in x.

- The nodal cubic $y^2 = x^2 + x^3$ at the node $(0, 0)$, with $y = tx$:

$$x^2\big[\,t^2 - 1 - x\,\big] = 0$$

  again leaving a factor *linear* in x.

- The Fermat cubic $x^3 + y^3 = 1$ at $(1, 0)$, with $y = t(x - 1)$:

$$(x-1)\big[\,x^2 + x + 1 + t^3(x-1)^2\,\big] = 0$$

  leaving a factor *quadratic* in x.

In the first two cases the leftover factor is linear, so x is a rational function of t and the construction succeeds: the conic gives $x = (t^2 - 1)/(t^2 + 1)$, and the nodal cubic gives $x = t^2 - 1$, recovering the parameterization of example 33.3.8.

In the third it is quadratic, and solving it introduces a square root. The reason is visible in the factorizations: the method needs the marked point to absorb all but one of the intersections. A line meets a conic twice and the marked point takes one; a line through the node of $y^2 = x^2 + x^3$ meets the cubic three times and the node, being a double point, takes two. A smooth cubic has no double point, so the marked point takes only one of three and two are left over. *The construction does not fail by accident; it fails because the curve is smooth*, which is exactly the hypothesis under which the conclusion is true.

A warning about what this does and does not show. Given *two* points of a cubic the chord still produces a third, and over $\mathbb{Q}$ that is the classical method for generating new solutions from old. That is a statement about individual points, not about parameterizing the whole curve by one variable, and the two are easy to conflate.

Attempt 2: symmetric functions. The equation is symmetric in x and y, so set $u = x + y$ and $v = xy$. Then $x^3 + y^3 = u^3 - 3uv$, and the curve becomes

$$u^3 - 3uv = 1 \qquad \text{that is} \qquad v = \frac{u^3 - 1}{3u}$$

which parameterizes the pair $\{x, y\}$ rationally by u alone. But recovering x and y individually means solving $T^2 - uT + v = 0$, whose discriminant is

$$u^2 - 4v = u^2 - \frac{4(u^3 - 1)}{3u} = \frac{4 - u^3}{3u}$$

So a square root of $(4 - u^3)/3u$ is needed. Setting $W = 3uw$ where w is that square root gives

$$W^2 = 3u\,(4 - u^3) = 12u - 3u^4$$

a square root of a quartic with four distinct roots, namely $u = 0$ and the three cube roots of 4. That is another curve of the same kind: section 44.4 will assign it genus 1, exactly as for C. The

attempt is circular, and it is circular in a way one can see before having any theory: it trades the problem for an equal one.

Attempt 3: look for a parameterization directly. Suppose C were rational, so that $x = p(t)/r(t)$ and $y = q(t)/r(t)$ for polynomials p, q, r with no common factor, not all constant. Substituting and clearing denominators,

$$p(t)^3 + q(t)^3 = r(t)^3$$

This is Fermat's Last Theorem for polynomials in the exponent 3, and unlike its arithmetic namesake it has a short proof. The Mason–Stothers theorem states that for coprime polynomials $a + b = c$ in $k[t]$, not all constant and with $\operatorname{char} k = 0$,

$$\max(\deg a, \deg b, \deg c) \;\leq\; n_0(abc) - 1$$

where n_0 counts *distinct* roots. Apply it to $a = p^3$, $b = q^3$, $c = r^3$ and set $d = \max(\deg p, \deg q, \deg r)$. The left side is $3d$. On the right, $p^3q^3r^3$ has the same distinct roots as pqr, so $n_0 \leq \deg(pqr) \leq 3d$, giving

$$3d \;\leq\; 3d - 1$$

which is absurd. So no such p, q, r exist and C is not rational.

What the third attempt costs. It is a complete proof, but only in characteristic zero: the Mason–Stothers argument differentiates, and in characteristic $\rho > 0$ all three of p, q, r may be polynomials in t^ρ, with vanishing derivatives, and the argument collapses. And in the excluded characteristic 3 the curve is not what it appears: $x^3 + y^3 = (x + y)^3$, so $C = \mathcal{Z}((x + y)^3 - 1)$ is a union of lines and is rational after all.

So one attempt fails structurally, one is circular, and one succeeds in a single characteristic by an argument owing nothing to geometry. What is missing is an invariant of the curve that decides the question uniformly, is computable, and explains why the conic and the nodal cubic behave differently from this one. That invariant is the genus. Theorem 44.4.2 shows a plane curve is rational exactly when its genus vanishes, definition 44.4.1 computes the genus of a smooth plane curve of degree d as $\binom{d-1}{2}$, giving 1 here and 0 for a conic, and section 44.4 shows a node drops the genus by exactly 1, which is why the nodal cubic is rational and this one is not. The argument is characteristic-free.

***Proof*:**
Write $K = k(X)$, the fraction field of $k[X] = \Gamma(\mathbb{A}^n)/\mathcal{I}(X)$. It is generated over k by the images $t_1, \dots, t_n$ of the coordinate functions, a *finite* set, so from it we may extract a maximal algebraically independent subset; after renumbering call it $t_1, \dots, t_d$, so that $d = \operatorname{trdeg}_k K$ and every remaining t_j is algebraic over $k(t_1, \dots, t_d)$.

Step 1: each algebraic generator can be taken separable. Fix $j > d$. Then $t_1, \dots, t_d, t_j$ are algebraically dependent, so some irreducible $f \in k[x_1, \dots, x_{d+1}]$ has $f(t_1, \dots, t_d, t_j) = 0$. We claim $\partial f/\partial x_i \neq 0$ for some i. In characteristic 0 this is immediate, as f is nonconstant. In characteristic p, suppose every $\partial f/\partial x_i$ vanished. Then each variable occurs in f only in exponents divisible by p, so

$$f = \sum a_{i_1,\dots,i_{d+1}}\, x_1^{p i_1} \cdots x_{d+1}^{p i_{d+1}}$$

Since k is algebraically closed it is perfect, so each coefficient has a p-th root: pick $b_{i_1,\dots,i_{d+1}}$ with

$b^p_{i_1,\dots,i_{d+1}} = a_{i_1,\dots,i_{d+1}}$. Then $g = \sum b_{i_1,\dots,i_{d+1}} x_1^{i_1} \cdots x_{d+1}^{i_{d+1}}$ satisfies $f = g^p$, since the Frobenius is a ring homomorphism in characteristic p. That contradicts irreducibility of f.

Step 2: putting the separable variable last. Say $\partial f/\partial x_i \neq 0$, so x_i genuinely occurs in f and hence t_i is algebraic over the field generated by the other d elements of $\{t_1, \dots, t_d, t_j\}$. Those d elements are still algebraically independent: if they were not, the transcendence degree of $k(t_1, \dots, t_d, t_j)$ would fall below d, contradicting the independence of $t_1, \dots, t_d$. Renaming so that the independent ones are $t_1, \dots, t_d$ and the algebraic one is t_{d+1}, we have $\partial f/\partial x_{d+1} \neq 0$, which says precisely that t_{d+1} is separable over $k(t_1, \dots, t_d)$.

Step 3: collapsing to one generator. K is generated over $k(t_1, \dots, t_d)$ by the finitely many elements $t_{d+1}, \dots, t_n$, each separable by Step 1 applied in turn, so $K/k(t_1, \dots, t_d)$ is a finite separable extension. The primitive element theorem then gives a single z_{d+1} with

$$K = k(t_1, \dots, t_d)(z_{d+1})$$

Writing $z_i = t_i$ for $i \leq d$, let f be an irreducible polynomial with $f(z_1, \dots, z_{d+1}) = 0$, and set $Y = \mathcal{Z}(f) \subseteq \mathbb{A}_k^{d+1}$, a hypersurface. By construction $k(Y) \cong K = k(X)$.

Step 4: an isomorphism of function fields is a birational map. By proposition 33.3.6, a dominating rational map is birational exactly when the induced map of function fields is an isomorphism, and proposition 33.3.4(4) produces such a dominating rational map $X \dashrightarrow Y$ from the isomorphism $k(Y) \to k(X)$. Hence X and Y are birationally isomorphic, as we sought to show.

Note that $k(X)/k(z_1, ..., z_d)$ is a finite separable extension, and that the primitive elements $z_1, ..., z_{d+1}$ can be chosen as linear combinations of the $x_1, ..., x_n$ for appropriate c_{ij}:

$$z_i = \sum_j^n c_{ij} x_j$$

Then the mapping $(x_1, ..., x_n) \to (z_1, ..., z_{d+1})$ is a projection from $\mathbb{A}_k^n$ that is parallel to the linear subspace given by:

$$\sum_j^n c_{ij} x_j = 0 \qquad 1 \leq i \leq d+1$$

Thus, the birational mapping theorem says that there is an appropriate hypersurface (not necessarily a hyperplane) on which we may project in a rational manner the variety! From this perspective, linear algebra results which are birationally invariant can be translated over to varieties, which we shall soon see gives us some interesting results!

One direction of the classification is easy to get wrong. A variety dominated by $\mathbb{A}_k^n$, meaning one admitting a dominant rational map from affine space, is called *unirational*; a variety birational to $\mathbb{A}_k^n$ is *rational*. Rational implies unirational trivially. In dimension one the converse also holds, and that is Lüroth's theorem. In higher dimensions it fails, which is one of the deepest facts in the subject and well outside this book.

Theorem 33.4.3: Lüroth's Theorem

Let L be a field with $k \subsetneq L \subseteq k(t)$, where t is transcendental over k. Then $L = k(u)$ for some $u \in L$.

***Proof*:**
This is theorem 19.6.23, stated there for the same fields with $k \subsetneq L \subseteq k(t)$ and t transcendental over k.

Corollary 33.4.4: Unirational Curves Are Rational

Let C be a curve admitting a dominant rational map $\mathbb{P}^1_k \dashrightarrow C$. Then C is rational, that is birational to $\mathbb{P}^1_k$.

***Proof*:**
A dominant rational map induces an inclusion of function fields $k(C) \hookrightarrow k(\mathbb{P}^1_k) = k(t)$ by proposition 33.3.4. Its image is a subfield of $k(t)$ containing k, and it properly contains k because C is a curve, so $k(C)$ has transcendence degree 1. Theorem 33.4.3 makes that image $k(u)$ for some u, hence $k(C) \cong k(u) \cong k(t)$, and isomorphic function fields mean birational varieties by theorem 33.4.1 and its proof.

The failure in higher dimension is worth naming, since it is easy to assume the pattern continues. There are unirational surfaces over fields of positive characteristic that are not rational, and unirational threefolds over $\mathbb{C}$ that are not rational; the first examples over $\mathbb{C}$ are due to Clemens and Griffiths, Iskovskikh and Manin, and Artin and Mumford, all in 1971–72. Deciding rationality is a live problem, and nothing in this book bears on it.

Exercise 33.4.1

1. In the proof of proposition 33.2.2, verify the identity $\varphi g_i = f_i$ in $k(X)$, and explain why it holds on all of X even though the representation $\varphi = f_i/g_i$ was chosen only near x_i.
2. Let X be irreducible. Show that any finite collection of rational functions on X has a non-empty common domain of definition
3. Show that the collection of poles of a rational function $f \in k(V)$ is an algebraic set
4. Show that for each $a \in k$, the stalk $\mathcal{O}_a(\mathbb{A}^1_k)$ at a is a DVR with uniforming parameter $x - a$.
5. Define $\mathcal{O}_\infty = \left\{ \frac{f}{g} \;\middle|\; \deg(f) \leq \deg(g) \right\}$. Show that $\mathcal{O}_\infty$ is a DVR with uniforming parameter $1/x$. (Note: This is foreshadowing that it is natural consider curves in *projective space* rather than affine space; see chapter 38).

Part VII

Local Properties

Everything in Part VI is an invariant of a whole variety. This Part changes the question: fix a point p of a variety X and ask what can be said about X near p. The answer throughout is that the local ring $\mathcal{O}_{X,p}$ carries it. The dimension of X at p is the Krull dimension of that ring, smoothness at p is the equality of that dimension with the dimension of the cotangent space $\mathfrak{m}_p/\mathfrak{m}_p^2$, the multiplicity of X at p is read from the associated graded ring, and normality is the condition that every $\mathcal{O}_{X,p}$ is integrally closed.

The passage runs both ways: A global statement is repeatedly proved by checking a condition at every point. The regular functions on a variety are the intersection of its local rings, a rational function regular everywhere is regular, and a variety is normal exactly when each of its local rings is.

Dimension theory, regular local rings, completion and the Cohen structure theorem are the commutative algebra the Part runs on, and they come from *Commutative Algebra* [20].


34

Dimension


Every notion of dimension that works in analysis or topology fails on the Zariski topology, whose open sets are too large for covering arguments and whose only irreducible subsets in the Euclidean sense are points. What survives is a definition built from chains of irreducible closed subsets, and its algebraic mirror, chains of prime ideals. This chapter establishes that the two agree, and that for a variety both agree with the transcendence degree of its function field.

34.1 What Dimension Should Mean

When looking at $\mathbb{A}_k^n$, we may naturally think of this space as being n-dimensional, and in this special case this matches with our notion of a 3-dimensional vector-space. We may think that varieties also have a notion of dimension, for example the curve with coordinate ring $\frac{k[x,y]}{(y^2-x)}$ gives the impression that it should be thought of as a 1-dimensional variety:



This variety should even be thought of as being smooth, as compared to the variety with coordinate ring $\frac{k[x,y]}{(y^2-x^3)}$ which has a cusp at $(x, y) = (0, 0)$.



We may hope that the notion of dimension is as simple as it was for vector spaces, however this turns out to be a more subtle problem. For example, continuous maps do not preserve dimension (there is a continuous map from $\mathbb{R}$ onto $\mathbb{R}^2$ given by the Peano space-filling curve). Homeomorphisms between open sets of $\mathbb{R}^n$ and $\mathbb{R}^m$ do force the condition that $n = m$[1], however we still need to define the notion of dimension so that it can be preserved.

One of the most general definition of dimension can be defined in the topological level and is called the *Lebesgue covering dimension* where a space X is dimension at most n if every open cover can be refined to an open cover in which each point lies in at most $n + 1$ sets. However, this definition will fail spectacularly in the Zariski topology as most open sets are huge (in fact, most Zariski topologies will have infinite Lebesgue covering dimension).

[1] see [76]

There are a few other notion of dimension (to name some notable example: the Brouwer-Menger-Urysohn boundary dimension, the Hausdorff Dimension, Deviation of Poset). One that the Nullstellensatz has already put within reach is the transcendence degree of a field extension. For example, if we take $k[V]$ to be some coordinate ring for a variety (so that $k[V]$ is an integral domain), we may take the field of fractions $k(V)$. Then taking the transcendental degree of $k(V)/k$, we may define this to be the *transcendental dimension* of $k[V]$. This works well on smooth shapes, and theorem 40.4.4 and theorem 40.4.3 will show that every affine or projective variety admits a finite surjection onto $\mathbb{A}^n_k$ or $\mathbb{P}^m_k$ respectively, so the transcendence degree is always attained. It is also invariant under isomorphism, being defined from the function field. However this definition fails when there the coordinate ring is not an integral domain[2]. Furthermore, it does not generalize to the spectrum of an arbitrary ring: the geometric object attached to $\mathbb{Z}$ has transcendence degree 0 over no field at all, while the definition settled on below gives it dimension 1.

One limitation is that these notions of dimension are global; the entire space has some dimension. This turns out to be a misnomer, as the example of the curve $y^2 = x^3$ mentioned earlier demonstrates (it *drops* a dimension at $(x, y) = (0, 0)$). To anyone who has done differential geometry, they may already be comfortable with the fact that the dimension of a smooth manifold is given by the vector space dimension of the tangent space at a point (which for a smooth-manifold should be invariant to the choice of point, and hence a well-defined global notion). Then the reader well-versed in the equivalent definition's of tangent spaces of a manifold may recall that the tangent space can be defined as the dual of $\mathfrak{m}/\mathfrak{m}^2$ where $\mathfrak{m}$ is the maximal ideal of C^∞_a (the set of germs of C^∞ on a manifold at the point a). This definition is agnostic of the differential structure, and so can be used on varieties. It shall also capture the local subtleties; to reiterate the same example the tangent space at $(x, y) = (0, 0)$ of $y^2 = x^3$ will be dimension 2, representing the fact that it should be treated differently than the other points. Section 35.1 takes up this notion.

34.2 Krull Dimension and Transcendence Degree

What has been settled on as the most useful notion of global dimension that translates well between algebra and geometry is the following:[3]

Definition 34.2.1: Topological Krull Dimension

Let X be a topological space. Then the *Krull dimension* of X is the supremum of the length of all chains:

$$Z_0 \subsetneq Z_1 \subsetneq \cdots \subsetneq Z_n$$

of distinct irreducible closed subsets of X. The Krull dimension of a topological space will be denoted kdim

This definition is not interesting in euclidean topology, for example for $\mathbb{R}^n$ as only points are irreducible we have $\text{kdim}(\mathbb{R}^n) = 0$. If the dimension is finite, then it is equal to the length of the longest chain of irreducible closed subsets. The Krull dimension of $\mathbb{A}^1_k$ is always 1, $\text{kdim}(\mathbb{A}^1_k) = 1$, as the only irreducible closed subsets of $\mathbb{A}^1_k$ are the single point and whole space. As irreducible closed subsets

[2]It also fails as an adequate definition when localizing a ring or taking its completion, which are two important tools that we shall often use on shapes

[3]The Krull dimension turns out to be equivalent to the Brouwer-Menger-Urysohn definition of dimension, which is useful for cohomological intuitions

correspond to prime ideals, we have the equivalent notion for primes:

Definition 34.2.2: Height of Prime

Let $\mathfrak{p} \subseteq R$ be a prime ideal. Then the *height* of a prime ideal is the supremum of all integers n for which there is a chain of distinct prime ideals:

$$\mathfrak{p}_0 \subsetneq \mathfrak{p}_1 \subsetneq \cdots \subsetneq \mathfrak{p}_n = \mathfrak{p}$$

The *dimension* of R is the supremum of the heights of all prime ideals.

A field has exactly one prime, (0), of height 0, so its Krull dimension is 0. A principal ideal domain that is not a field has Krull dimension 1: its nonzero primes are maximal, so the longest chain is $(0) \subsetneq \mathfrak{p}$.

Proposition 34.2.3: Dimension of Affine Algebraic Set

Let $Y \subseteq \mathbb{A}^n_k$ be an affine algebraic set. Then $\operatorname{kdim}(Y)$ is equal to the dimension of the affine coordinate ring $k[Y]$

***Proof*:**
By proposition 32.3.3 the irreducible closed subsets of Y correspond to the prime ideals of $\Gamma(\mathbb{A}^n)$ containing $\mathcal{I}(Y)$, which by the correspondence theorem are the prime ideals of $k[Y] = \Gamma(\mathbb{A}^n)/\mathcal{I}(Y)$. The correspondence *reverses* inclusion, so a strictly ascending chain of length d of irreducible closed subsets of Y is the same thing as a strictly descending chain of length d of primes of $k[Y]$, and conversely. Taking suprema, $\operatorname{kdim}(Y) = \operatorname{kdim}(k[Y])$, as we sought to show.

When covering Noether's Normalization (theorem 32.4.1), it was observed that this can be used to define the dimension of a ring. The following definition captures this idea:

Definition 34.2.4: Transcendental Dimension

Let X be a variety. Then the *transcendence dimension* of X over k is the transcendence degree of its function field $k(X)$, and is denoted $\dim X$. (Proposition 34.2.5 shows this agrees with $\operatorname{kdim} X$, after which the two notations are used interchangeably.) The transcendence degree of a field extension, and the fact that it is well-defined, are established in *Core Algebra* [21, Transcendence Degree, Transcendence Degree Is Well-Defined].

Proposition 34.2.5: Transcendental and Krull Dimension

Let k be a field and R a finitely generated k-algebra which is an integral domain. Then

$$\operatorname{kdim}(R) = \operatorname{trdeg}_k \operatorname{Frac}(R)$$

Furthermore, for every prime $\mathfrak{p} \subseteq R$,

$$\operatorname{height}(\mathfrak{p}) + \operatorname{kdim}(R/\mathfrak{p}) = \operatorname{kdim}(R)$$

Neither hypothesis can be dropped. Transcendence degree is an invariant of a field extension, so R must be a domain for $\mathrm{Frac}(R)$ to exist; and finite generation cannot be dropped, as example 34.2.6 shows. The second identity is the statement that finitely generated domains over a field are catenary and equidimensional, which is what makes codimension behave additively.

***Proof*:**
The first identity is the dimension theorem for finitely generated domains over a field in *Commutative Algebra*,[a] and the second is the height formula proved there.[b]

[a] theorem 29.6.3.
[b] theorem 29.7.3.

The conditions are necessary for the equality of both equations:

Example 34.2.6: Different Krull and Transcendental Dimension
Take $R = k(x)$, the field of rational functions in one variable. As a field it has exactly one prime, so $\mathrm{kdim} R = 0$, while $\mathrm{trdeg}_k R = 1$. There is no contradiction with proposition 34.2.5: $k(x)$ is *not* a finitely generated k-algebra. It is finitely generated as a *field* extension, which is a strictly weaker condition, and the proposition needs the algebra version.

Geometrically the collapse is familiar to a reader who has met schemes: $k(x)$ is the local ring at the generic point of $\mathbb{A}^1_k$, a single non-closed point, and a one-point space has Krull dimension 0 however large the field attached to it.

Corollary 34.2.7: Dimension of Affine Space

The Krull dimension of affine space $\mathbb{A}^n_k$ is n.

***Proof*:**
$\Gamma(\mathbb{A}^n) \cong k[x_1, \ldots, x_n]$ is a finitely generated k-algebra and an integral domain, so proposition 34.2.5 applies and gives $\mathrm{kdim}\mathbb{A}^n = \mathrm{trdeg}_k k(x_1, \ldots, x_n)$. The x_i are algebraically independent over k and generate the field, so they form a transcendence basis and that degree is n, as we sought to show.

34.3 Codimension, Curves, and Surfaces

Definition 34.3.1: Codimension

Let $Y \subseteq X$ be a closed subvariety of a variety X. The *codimension* of Y in X, written $\mathrm{codim}_X Y$, is the supremum of the lengths of chains

$$Y = Z_0 \subsetneq Z_1 \subsetneq \cdots \subsetneq Z_c \subseteq X$$

of irreducible closed subsets of X starting at Y. The ambient is part of the data and is dropped from the notation only when it is fixed by context.

Proposition 34.3.2: Codimension Is a Difference of Dimensions

Let $Y \subseteq X$ be a closed subvariety of a variety X over a field. Then

$$\operatorname{codim}_X Y = \dim X - \dim Y$$

***Proof*:**
Passing to an affine open subset changes neither side, so assume X affine with coordinate ring $k[X]$, a finitely generated domain over k. Chains of irreducible closed subsets of X starting at Y correspond, reversing inclusion, to chains of primes of $k[X]$ descending from $\mathcal{I}(Y)$, so $\operatorname{codim}_X Y = \operatorname{height}(\mathcal{I}(Y))$. Likewise $\dim Y = \operatorname{kdim}(k[X]/\mathcal{I}(Y))$ by proposition 34.2.3. The dimension formula of proposition 34.2.5 applied to $\mathfrak{p} = \mathcal{I}(Y)$ then reads $\operatorname{codim}_X Y + \dim Y = \dim X$, as we sought to show.

The identity fails without the hypotheses of proposition 34.2.5: it is exactly the statement that the ring is catenary and equidimensional, which is why codimension is *defined* by chains and only *computed* as a difference.

One consequence is used constantly and deserves a name: dimension cannot be detected locally, in the sense that shrinking to a smaller open set does not shrink the dimension.

Corollary 34.3.3: Dimension Is Determined by Any Open Subset

Let X be an irreducible variety and $U \subseteq X$ a nonempty open subset. Then $\dim U = \dim X$.

***Proof*:**
U is dense in X by irreducibility, so restriction identifies the two function fields, $k(U) = k(X)$. Both dimensions equal the transcendence degree of that common field by proposition 34.2.5, completing the proof.

Verify as a check on the definitions that planar curves have dimension 1, that finite sets have dimension 0, and that $\mathbb{A}^n_k$ and $\mathbb{P}^n_k$ have dimension n.

Definition 34.3.4: Curves and Surfaces

Let X be an algebraic variety. Then:

1. If X is 1-dimensional, it is called a *curve*
2. If X is 2-dimensional, it is called a *surface*
3. If X is 1-codimensional, it is called a *hypersurface*.

Proposition 34.3.5: Dimension Between Irreducible Varieties

Let $Y \subseteq X$ be a closed subvariety of a variety X. Then $\dim Y \leq \dim X$, with equality if and only if $Y = X$.

***Proof*:**
Every chain of irreducible closed subsets of Y is a chain of irreducible closed subsets of X, since Y is closed in X; taking suprema gives $\dim Y \leq \dim X$.

Suppose $\dim Y = \dim X = d$ and $Y \subsetneq X$. Take a chain $Z_0 \subsetneq \cdots \subsetneq Z_d = Y$ of irreducible closed subsets of Y realizing its dimension. As Y is irreducible, closed and properly contained in X, appending X extends this to

$$Z_0 \subsetneq \cdots \subsetneq Z_d = Y \subsetneq X$$

a chain of length $d+1$ in X, so $\dim X \geq d+1$, contradicting $\dim X = d$. Hence $Y = X$; the converse is trivial, completing the proof.

34.4 Hypersurface Sections and Codimension One

Cutting a variety by one equation ought to drop its dimension by exactly one. That is the geometric content of Krull's principal ideal theorem, and it is the fact that makes dimension usable: it lets a variety be built up, or cut down, one equation at a time. This section records it, and then proves the converse in affine space, where codimension one turns out to be the same thing as being cut out by a single polynomial.

Theorem 34.4.1: Hypersurface Sections Drop Dimension by One

Let X be a variety and $f \in k[X]$ neither zero nor a unit. Then every irreducible component of $\mathcal{Z}_X(f) = \{p \in X \mid f(p) = 0\}$ has dimension $\dim X - 1$.

***Proof*:**
The irreducible components of $\mathcal{Z}_X(f)$ correspond to the primes of $k[X]$ minimal over (f). Let $\mathfrak{p}$ be such a prime. Krull's principal ideal theorem (theorem 29.5.2) gives $\text{height}(\mathfrak{p}) \leq 1$.

For the reverse bound, $k[X]$ is a domain because X is a variety (corollary 32.3.4), so (0) is prime; and $f \neq 0$ forces $\mathfrak{p} \neq (0)$. Hence $(0) \subsetneq \mathfrak{p}$ is a chain of length 1 and $\text{height}(\mathfrak{p}) \geq 1$, so $\text{height}(\mathfrak{p}) = 1$.

The component attached to $\mathfrak{p}$ has coordinate ring $k[X]/\mathfrak{p}$, so by proposition 34.2.5,

$$\dim \mathcal{Z}_X(\mathfrak{p}) = \text{kdim}(k[X]/\mathfrak{p}) = \text{kdim} k[X] - \text{height}(\mathfrak{p}) = \dim X - 1$$

as we sought to show.

The theorem says nothing about $\mathcal{Z}_X(f)$ being irreducible, and it need not be: $\mathcal{Z}(xy) \subseteq \mathbb{A}^2$ is the union of the two axes, two components each of dimension 1. What the theorem guarantees is that no component is smaller than expected. The hypothesis that f be a nonunit is what keeps $\mathcal{Z}_X(f)$ nonempty in the first place, and $f \neq 0$ is what stops it from being all of X.

In affine space the converse holds, and it is a genuine dictionary entry: codimension one on the geometric side is principality on the algebraic side.

Theorem 34.4.2: Codimension One in Affine Space Means Hypersurface

Let $Y \subsetneq \mathbb{A}^n_k$ be an irreducible closed subset with $\operatorname{codim}_{\mathbb{A}^n} Y = 1$. Then there is an irreducible polynomial f, unique up to a nonzero scalar, with

$$\mathcal{I}(Y) = (f) \qquad Y = \mathcal{Z}(f)$$

Conversely $\mathcal{Z}(f)$ is irreducible of codimension 1 for every irreducible f.

***Proof*:**
$\mathcal{I}(Y)$ is prime because Y is irreducible (proposition 32.3.3), and $\operatorname{height}(\mathcal{I}(Y)) = \operatorname{codim}_{\mathbb{A}^n} Y = 1$ by proposition 34.3.2. So it suffices to show that a height-one prime $\mathfrak{p}$ in a unique factorization domain is principal, generated by an irreducible element.

The ring $\Gamma(\mathbb{A}^n) \cong k[x_1, \dots, x_n]$ is a UFD, being a polynomial ring in finitely many variables over the field k (corollary 11.2.4). Choose $0 \neq g \in \mathfrak{p}$ and factor it into irreducibles, $g = f_1 \cdots f_r$. As $\mathfrak{p}$ is prime, some $f_i \in \mathfrak{p}$; write $f = f_i$. In a UFD an irreducible element is prime (proposition 10.1.29), so (f) is a nonzero prime ideal with

$$(0) \subsetneq (f) \subseteq \mathfrak{p}$$

If the second inclusion were strict, that chain would have length 2 and give $\operatorname{height}(\mathfrak{p}) \geq 2$. Hence $(f) = \mathfrak{p}$. Uniqueness up to a scalar is uniqueness of the generator of a principal ideal in a domain, and $Y = \mathcal{Z}(\mathcal{I}(Y)) = \mathcal{Z}(f)$ by proposition 31.2.11.

Conversely let f be irreducible. Then (f) is prime, so $\mathcal{Z}(f)$ is irreducible, and theorem 34.4.1 applied to $X = \mathbb{A}^n$ gives $\dim \mathcal{Z}(f) = n - 1$, that is codimension 1, as we sought to show.

Example 34.4.3: Hypersurfaces and Their Ideals

1. The cuspidal cubic $\mathcal{Z}(y^2 - x^3) \subseteq \mathbb{A}^2$ has $y^2 - x^3$ irreducible, so its vanishing ideal is $(y^2 - x^3)$ and it is a curve: codimension 1 in $\mathbb{A}^2$.
2. $\mathcal{Z}(xy) \subseteq \mathbb{A}^2$ is not irreducible, and correspondingly (xy) is not prime. Its two components $\mathcal{Z}(x)$ and $\mathcal{Z}(y)$ each have codimension 1, as theorem 34.4.1 predicts.
3. The twisted cubic $\mathcal{Z}(y - x^2, z - x^3) \subseteq \mathbb{A}^3$ has dimension 1, hence codimension 2, and so by theorem 34.4.2 it cannot be cut out by a single equation. This is the promise made when the twisted cubic first appeared in example 31.2.2 that it is not a hypersurface.

Exercise 34.4.1

1. Let X, Y be irreducible affine varieties. Show that $\dim(X \times Y) = \dim(X) + \dim(Y)$ directly from the transcendence-degree definition. Corollary 40.5.4 proves this a different way, by reading the projection as a family of fibres, so the two arguments are worth comparing.
2. Define the *coheight* of a prime $\mathfrak{p} \subseteq R$ to be the supremum of the lengths of chains of primes $\mathfrak{p} = \mathfrak{p}_0 \subsetneq \mathfrak{p}_1 \subsetneq \cdots \subsetneq \mathfrak{p}_d$. Show that $\operatorname{coht}(\mathfrak{p}) = \operatorname{kdim}(R/\mathfrak{p})$ for any ring, give an example where it is infinite, and show it is finite whenever R is a finitely generated k-algebra.

3. Let R be a Noetherian ring. Show that $\mathrm{kdim} R[x] = \mathrm{kdim} R + 1$.

4. Compute the dimension of $\mathcal{Z}(xy, xz) \subseteq \mathbb{A}^3_k$, identify its irreducible components, and observe that they do not all have the same dimension. Which hypothesis of proposition 34.3.2 does this violate?

5. Show that $\dim \mathcal{Z}(f) = n - 1$ for any nonconstant $f \in k[x_1, \ldots, x_n]$, and deduce that a proper closed subset of $\mathbb{A}^n_k$ has dimension at most $n - 1$.

6. Let $X \subseteq \mathbb{A}^n_k$ be an irreducible variety of dimension d. Show that X is contained in no linear subspace of dimension less than d, and give an example where it is contained in one of dimension exactly d.

7. Verify from the definitions that a plane curve has dimension 1, that a finite set has dimension 0, and that $\mathbb{A}^n_k$ has dimension n.

35

Smooth Points and Regular Local Rings

The dimension theory the previous chapter used, and which this one uses again, rests on the Hilbert-Samuel function of an $\mathfrak{m}$-primary ideal and the Dimension Theorem $\delta(R) = d(R) = \operatorname{kdim} R$ it yields, together with systems of parameters. Those are in *Commutative Algebra* [20].

This chapter takes the one consequence that carries geometric content, the tangent-space inequality $\operatorname{kdim} R \le \dim_k(\mathfrak{m}/\mathfrak{m}^2)$, and turns it into a criterion. A point is *smooth* when the inequality is an equality, which says the tangent space has no more directions than the variety has dimensions. The Jacobian gives a computable test for this, regular local rings give an intrinsic one free of any embedding, and the two agree. The chapter closes with the case that matters most for Part IX: in dimension one, regular is the same as being a discrete valuation ring.

35.1 The Tangent Space Bound

For a Noetherian local ring $(R, \mathfrak{m})$ the Dimension Theorem ([20, Dimension Theorem]) identifies the Krull dimension with the degree of the Hilbert-Samuel polynomial and with the least number of generators of an $\mathfrak{m}$-primary ideal. The one consequence we need geometrically bounds the dimension by the embedding dimension.

Corollary 35.1.1: Dimension and Tangent Space

Let $(R, \mathfrak{m})$ be a Noetherian local ring with residue field $k = R/\mathfrak{m}$. Then

$$\operatorname{kdim}(R) \le \dim_k(\mathfrak{m}/\mathfrak{m}^2)$$

***Proof*:**
Choose $r_1, \dots, r_s \in \mathfrak{m}$ whose images form a basis of $\mathfrak{m}/\mathfrak{m}^2$; by Nakayama they generate $\mathfrak{m}$, hence an $\mathfrak{m}$-primary ideal on s generators, so the Dimension Theorem ([20, Dimension Theorem]) gives $\operatorname{kdim} R \leq s = \dim_k(\mathfrak{m}/\mathfrak{m}^2)$.

35.2 The Jacobian Criterion and Regular Local Rings

One of the properties most geometric objects carry is *smoothness*, or nonsingularity. In this section, we shall introduce an intuitive way of defining smoothness given an embedding into an affine/projective space. We shall then show a more intrinsic definition that will not require any embedding.

Definition 35.2.1: Nonsingular Variety - Embedding Variant

Let $X \subseteq \mathbb{A}^n_k$ be an affine variety of dimension r, and let $f_1, \dots, f_t$ generate its vanishing ideal $\mathcal{I}(X) \subseteq \Gamma(\mathbb{A}^n)$. Then X is *nonsingular* at $p \in X$ if the Jacobian matrix evaluated at p,

$$J(p) = \left(\frac{\partial f_i}{\partial x_j}(p) \right)_{\substack{1 \leq i \leq t \\ 1 \leq j \leq n}}$$

has rank $J(p) = n - r$. We say X is *nonsingular* if it is nonsingular at every point.

If the reader knows differential geometry, this is saying that the tangent space must be "full rank" at every point. The matrix is called the *Jacobian matrix*. Its rank at p does not depend on the chosen generators, even though the matrix itself does: the proof of proposition 35.2.2 below identifies $\operatorname{rank} J(p)$ with $n - \dim_k \mathfrak{m}_p/\mathfrak{m}_p^2$, an invariant of the local ring alone. This definition is geometrically well-motivated, but is not intrinsic to the variety: it is dependent on the "global" information of the embedding space and generators. We shall immediately work towards the intrinsic definition of nonsingular variety. The key is that at each point p the local ring $\mathcal{O}_{X,p}$ has a single maximal ideal $\mathfrak{m}_p$ representing where functions evaluate to 0, and $\mathfrak{m}_p/\mathfrak{m}_p^2$ "remembers" only linear terms, making it the best analogy to the cotangent space at a point. Recall that $\dim_k \mathfrak{m}_p/\mathfrak{m}_p^2 \geq \operatorname{kdim} k[X]$ by corollary 35.1.1. The inequality is strict exactly at a singular point, where the tangent space picks up extra dimensions. We thus seek conditions where the local ring at each point shall have the same dimension everywhere:

A local Noetherian ring of dimension d with maximal ideal $\mathfrak{m}$ and residue field k is *regular* when $\dim_k(\mathfrak{m}/\mathfrak{m}^2) = d$, equivalently when $\mathfrak{m}$ can be generated by d elements, equivalently when the associated graded ring $G_{\mathfrak{m}}(R)$ is the polynomial ring $k[t_1, \dots, t_d]$ on independent degree-one indeterminates. The definition, the equivalence of the three conditions, and the consequences used below are commutative algebra and are developed in *Commutative Algebra*: see definition 29.8.2 and theorem 29.8.3.

Proposition 35.2.2: Jacobian Criterion and Regular Local Rings

Let $X \subseteq \mathbb{A}^n_k$ be a variety. Then X is nonsingular at p iff the local ring at p is regular.

***Proof*:**
Let $p = (a_1, \ldots, a_n) \in \mathbb{A}^n$ and let $\mathfrak{a}_p = (x_1 - a_1, \ldots, x_n - a_n)$ be the corresponding maximal ideal of $A = \Gamma(\mathbb{A}^n) \cong k[x_1, \ldots, x_n]$. Define a k-linear map $\theta_p \colon A \to k^n$ by

$$\theta_p(f) = \left\langle \frac{\partial f}{\partial x_1}(p), \ldots, \frac{\partial f}{\partial x_n}(p) \right\rangle$$

The images $\theta_p(x_i - a_i)$ are the standard basis vectors, so θ_p is surjective and its restriction to $\mathfrak{a}_p$ is still surjective. That restriction has kernel exactly $\mathfrak{a}_p^2$: the product rule gives $\theta_p(fg) = f(p)\theta_p(g) + g(p)\theta_p(f)$, which vanishes when $f, g \in \mathfrak{a}_p$, and conversely a Taylor expansion of $f \in \mathfrak{a}_p$ at p has linear part determined by $\theta_p(f)$. Note the restriction is essential: θ_p kills every constant, so $\ker \theta_p \neq \mathfrak{a}_p^2$ on all of A. Thus θ_p induces an isomorphism $\theta_p' \colon \mathfrak{a}_p/\mathfrak{a}_p^2 \to k^n$.

Now let $\mathfrak{b} = \mathcal{I}(X)$ be the ideal of X in A, and let $f_1, \ldots, f_t$ be a set of generators of $\mathfrak{b}$. Then the rank of the Jacobian matrix $J = (\partial f_i/\partial x_j)(p)$ is just the dimension of $\theta_p(\mathfrak{b})$ as a subspace of k^n. Using the isomorphism θ_p', this is the same as the dimension of the subspace $(\mathfrak{b} + \mathfrak{a}_p^2)/\mathfrak{a}_p^2$ of $\mathfrak{a}_p/\mathfrak{a}_p^2$. On the other hand, the local ring $\mathcal{O}_p$ of p on X is obtained from A by dividing by $\mathfrak{b}$ and localizing at the maximal ideal $\mathfrak{a}_p$. Thus if $\mathfrak{m}$ is the maximal ideal of $\mathcal{O}_p$, we have

$$\mathfrak{m}/\mathfrak{m}^2 \cong \mathfrak{a}_p/(\mathfrak{b} + \mathfrak{a}_p^2)$$

Counting dimensions of vector spaces, we have $\dim \mathfrak{m}/\mathfrak{m}^2 + \operatorname{rank}(J) = n$.

But this gives what we want. If $\dim X = r$ then $\mathcal{O}_p$ has Krull dimension r, since localizing $k[X]$ at the maximal ideal of p leaves the dimension of the irreducible X unchanged by proposition 34.3.2. So $\mathcal{O}_p$ is regular if and only if $\dim_k \mathfrak{m}/\mathfrak{m}^2 = r$. But this is equivalent to $\operatorname{rank}(J) = n - r$, which says that p is a nonsingular point of X, completing the proof.

Example 35.2.3: The Jacobian Criterion on Three Curves
Each of the following is a curve in $\mathbb{A}_k^2$, and the criterion is applied at the origin, which lies on all three. Assume $\operatorname{char} k \neq 2, 3$.

1. *The parabola* $f = y - x^2$. The Jacobian is $(-2x,\ 1)$, of rank 1 everywhere. So every point is nonsingular, and $\dim_k \mathfrak{m}_p/\mathfrak{m}_p^2 = 1 = \dim C$ at each.
2. *The node* $f = y^2 - x^2 - x^3$. The Jacobian is $\left(-2x - 3x^2,\ 2y\right)$, which vanishes at $(0, 0)$ and at $(-2/3, 0)$; only the first is on the curve. So the origin is the unique singular point, and there $\dim_k \mathfrak{m}/\mathfrak{m}^2 = 2 > 1$.
3. *The cusp* $f = y^2 - x^3$. The Jacobian is $\left(-3x^2,\ 2y\right)$, vanishing only at the origin, which is on the curve. Again the origin is the unique singular point with $\dim_k \mathfrak{m}/\mathfrak{m}^2 = 2$.

The criterion separates the parabola from the other two but says nothing distinguishing the node from the cusp: both are singular points of multiplicity 2. Telling them apart needs the tangent cone of definition 36.1.2, taken up in the next chapter, which sees two tangent lines at the node and one doubled at the cusp.

From this, we can extend the definition naturally to any quasiprojective variety.

Definition 35.2.4: Nonsingular Variety

Let X be a quasi-projective variety. Then X is *nonsingular* or *regular* if the local ring at every point is regular.

35.3 The Singular Locus

The set of points that are singular are usually "measure 0". We shall not go so far to prove this statement, but the following simpler result that a variety cannot *only* consist of singular points:

Proposition 35.3.1: Singular Points of Variety

Let X be a variety. Then the set of singular points of X forms a proper closed subset of X

The fact that it is closed should be unsurprising as it is essentially the pre-image of the closed set 0 for the right continuous function, the key take-away is that it must be proper.

***Proof*:**
Let $\text{Sing}(X)$ denote the set of singular points of X.

Closed. Being closed is local, so covering X by affine open sets reduces us to X affine, say of dimension r in $\mathbb{A}^n$ with $\mathcal{I}(X) = (f_1, \dots, f_t)$. Combining corollary 35.1.1 with the dimension count in the proof of proposition 35.2.2 gives $\operatorname{rank} J(p) \leq n - r$ at every p, with equality exactly at the nonsingular points. So the singular points are those where the rank is *strictly* less than $n - r$. Thus $\text{Sing}(X)$ is the algebraic set defined by the ideal generated by $I(X)$ together with all determinants of $(n-r) \times (n-r)$ sub-matrices of the matrix $\|\partial f_i / \partial x_j\|$. From these, we can see that Sing X is closed.

Proper. By theorem 33.4.1, X is birationally isomorphic to a hypersurface $Y \subseteq \mathbb{A}^{d+1}$, where $d = \dim X$; note the theorem produces an *affine* hypersurface, not a projective one. By proposition 39.5.2 a birational isomorphism identifies a dense open subset of X with one of Y, and nonsingularity is a local condition, so it is enough to exhibit a single nonsingular point on Y. Thus we may assume X is a hypersurface in $\mathbb{A}^n$ cut out by one irreducible polynomial $f(x_1, \dots, x_n)$.

Now, $\text{Sing}(X)$ is the set of points $p \in X$ such that $(\partial f / \partial x_i)(p) = 0$ for $i = 1, \dots, n$. If Sing $X = X$, then the functions $\partial f / \partial x_i$ are zero on X, and hence $\partial f / \partial x_i \in I(X)$ for each i. But $I(X)$ is the principal ideal generated by f, and $\deg(\partial f / \partial x_i) \leq \deg f - 1$ for each i, so we must have $\partial f / \partial x_i = 0$ for each i.

In characteristic 0 this is already impossible, because if x_i occurs in f, then $\partial f / \partial x_i \neq 0$. So we must have $\operatorname{char} k = p > 0$, and then the fact that $\partial f / \partial x_i = 0$ implies that f is a polynomial in x_i^p. This is true for each i, so by taking pth roots of the coefficients (which is possible since k is algebraically closed), we get a polynomial $g(x_1, \dots, x_n)$ such that $f = g^p$. But this contradicts the hypothesis that f was irreducible, and so Sing $X \subsetneq X$, as we sought to show.

35.4 Homological Characterization: Serre's Theorem

Before stating the main theorem on regular local rings, we need a homological invariant[1]:

Definition 35.4.1: Projective and Global Dimension

Let R be a ring and M an R-module. The *projective dimension* of M, denoted $\mathrm{pd}_R(M)$, is the minimal length n of a projective resolution of M:

$$0 \to P_n \to \cdots \to P_0 \to M \to 0$$

If no finite resolution exists, $\mathrm{pd}_R(M) = \infty$.

The *global dimension* of R, denoted $\mathrm{gldim}(R)$, is the supremum of the projective dimensions of all R-modules:

$$\mathrm{gldim}(R) = \sup\{\mathrm{pd}_R(M) \big| M \in \mathrm{Mod}_R\}$$

Example 35.4.2: Infinite Global Dimension When There is A Singularity

Take $R = k[x,y]/(x^2 - y^3)$. This corresponds to the cusp singularity at the origin. Let us compute the global dimension by finding the projective dimension of the residue field $k \cong R/(x,y)$ (where $\mathfrak{m} = (\overline{x}, \overline{y})$). We begin a free resolution of k by killing $\mathfrak{m} = (\overline{x}, \overline{y})$:

$$R^2 \xrightarrow{d_1} R \to k \to 0$$

where $d_1 = \begin{pmatrix} x & y \end{pmatrix}$. The kernel of this map consists of relations between x and y. In the polynomial ring, the only relation is trivial ($yx - xy = 0$). However, in our quotient ring R, we have the relation defining the ring: $x^2 - y^3 = 0$. Thus, the kernel is generated by two elements:

1. The "Koszul" relation: $y \cdot (x) - x \cdot (y) = 0$
2. The "Curve" relation: $x \cdot (x) - y^2 \cdot (y) = 0$

So we have a map $R^2 \xrightarrow{d_2} R$ given by the matrix $\begin{pmatrix} y & x \\ -x & -y^2 \end{pmatrix}$. (Check: $\begin{pmatrix} x & y \end{pmatrix}\begin{pmatrix} y & x \\ -x & -y^2 \end{pmatrix} = \begin{pmatrix} xy - yx & x^2 - y^3 \end{pmatrix} = \begin{pmatrix} 0 & 0 \end{pmatrix}$).

Now we need the kernel of d_2. Calculating the determinant of the matrix, we find $\det(d_2) = -y^3 + x^2 = 0$. Because the determinant vanishes, the columns are linearly dependent, and the kernel is non-trivial. In fact, the resolution becomes *periodic*. The resolution continues forever with alternating matrices:

$$\cdots \xrightarrow{d_3} R^2 \xrightarrow{d_2} R^2 \xrightarrow{d_1} R \to k \to 0$$

where $d_{\text{odd}} = \begin{pmatrix} y & x \\ -x & -y^2 \end{pmatrix}$ and $d_{\text{even}} = \begin{pmatrix} y^2 & x \\ -x & -y \end{pmatrix}$. Since the resolution never terminates (it never reaches a 0 module), the projective dimension of k is infinite. Therefore, the global dimension of R is infinite.

[1] These terms will be central in section 58.2 and will be reintroduced there

For a local ring $(R, \mathfrak{m})$ with residue field k, a fundamental result of Auslander and Buchsbaum states that $\operatorname{gldim}(R) = \operatorname{pd}_R(k)$. Thus, the global dimension is determined entirely by the resolution of the residue field.

Theorem 35.4.3: Auslander-Buchsbaum-Serre Theorem

A local Noetherian ring $(R, \mathfrak{m})$ has finite global dimension if and only if it is a regular local ring.

The proof is homological rather than geometric, and belongs with the machinery that produces it: it runs through the Auslander-Buchsbaum identity $\operatorname{gldim} R = \operatorname{pd}_R k$ and the Koszul resolution of the residue field, neither of which this book develops. *Homological Algebra* [29, Auslander-Buchsbaum-Serre Theorem] gives it in full; the two books are co-requisites for exactly this reason.

***Proof Key ideas*:**
One direction is the Koszul resolution. If R is regular of dimension d, then $\mathfrak{m}$ is generated by a regular sequence $x_1, \dots, x_d$, and the Koszul complex on that sequence is a free resolution of $k = R/\mathfrak{m}$ of length d. Hence $\operatorname{pd}_R k \leq d < \infty$, and by the Auslander-Buchsbaum identity $\operatorname{gldim} R = \operatorname{pd}_R k$ is finite.

The converse is the substantive half. Finiteness of $\operatorname{pd}_R k$ forces the minimal free resolution of k to terminate, and one shows by induction on $\dim_k \mathfrak{m}/\mathfrak{m}^2$ that this can happen only when a minimal generating set of $\mathfrak{m}$ is a regular sequence, which is regularity. See [29, Auslander-Buchsbaum-Serre Theorem] for the details.

35.5 Regular Local Rings in Dimension One

Let us now take a closer look at the properties regular local rings must have, especially in low dimension. In one dimension, this shall produce a very restrictive result that will be very powerful, and in higher dimensions we shall find an algebraic condition that eventually lets the rings of integers of *Algebraic Number Theory* [15] be read as nonsingular $\mathbb{Z}$-curves. For curves this is the decisive case, and section 37.3 uses it to show that each birational class of curves contains a unique nonsingular projective model, so that a field extension K/k of transcendence degree one determines *the* curve attached to it.

One consequence is needed before the dimension-one case, and it is not visible from the numerical definition: a regular local ring has no zero-divisors. The mechanism is that regularity makes the associated graded ring a polynomial ring, hence a domain, and a domain downstairs lifts to a domain upstairs whenever $\bigcap_n \mathfrak{m}^n = 0$, which Krull's theorem gives in any Noetherian local ring. Both steps are commutative algebra and are carried out in corollary 29.8.5.

Corollary 35.5.1: Regular Local Rings of Dimension 1

Let R be a local Noetherian ring of dimension 1. Then R is a regular local ring if and only if R is a DVR.

***Proof*:**
Suppose $(R, \mathfrak{m})$ is regular of dimension 1, so $\dim_{R/\mathfrak{m}} \mathfrak{m}/\mathfrak{m}^2 = \mathrm{kdim} R = 1$. Choose $m \in \mathfrak{m}$ whose class spans $\mathfrak{m}/\mathfrak{m}^2$. Nakayama's lemma (theorem 23.4.30) then gives $\mathfrak{m} = (m)$: the single element m generates. By the discussion above R is a domain, and a Noetherian local domain of dimension 1 with principal maximal ideal is a discrete valuation ring (theorem 27.2.2).

Conversely let R be a discrete valuation ring with uniformizer m. It is local: its unique maximal ideal is (m), the elements of positive valuation. Note it is *not* true that (m) is its only prime, as (0) is prime too; indeed the chain $(0) \subsetneq (m)$ is what makes $\mathrm{kdim} R = 1$, and no longer chain exists because every nonzero ideal is $(m)^n$. Finally $(m)/(m)^2$ is spanned by the class of m over $R/(m)$ and is nonzero, so $\dim_{R/(m)}(m)/(m)^2 = 1 = \mathrm{kdim} R$ and R is regular, as we sought to show.

This gives a nice condition for 1-dimensional regular local rings. It will sometimes be useful to identify regular local rings in different context:

Proposition 35.5.2: Equivalences of 1 Dimensional Regular Local Rings

Let $(R, \mathfrak{m})$ be a Noetherian local domain of dimension 1. Then the following are equivalent:

1. R is a regular local ring
2. R is a DVR
3. R is normal (integrally closed)
4. $\mathfrak{m}$ is principal
5. every nonzero ideal of R is a power of $\mathfrak{m}$

***Proof*:**
This is a statement about Noetherian local domains with no geometric content, and it is proved in full upstream: see theorem 27.2.2, which lists exactly these five conditions.

The equivalence of (1) and (3) is the one chapter 37 uses. It says that for a curve, being smooth at a point and being normal at that point are the same condition, which is why normalization resolves the singularities of a curve completely while leaving higher-dimensional singularities behind.

For higher-dimensions, the situation is more subtle, and the full account belongs with divisors on a scheme; this book records only the following:

Corollary 35.5.3: Regular Local Ring, then Normal

Let R be a regular local Noetherian ring. Then R is normal.

***Proof*:**
This is corollary 29.9.7, where it is obtained from factoriality: a regular local ring is a unique factorization domain by the theorem of Auslander and Buchsbaum, and a unique factorization domain is integrally closed. In dimension one the statement is already contained in proposition 35.5.2, which is the case this book uses.

The converse does not hold in general in dimension > 1, a normal domain need not be regular, so normality alone does not detect nonsingular varieties. Chapter 37 takes up exactly this gap.

Proposition 35.5.4: Completion and Regularity

Let $(R, \mathfrak{m})$ be a Noetherian local ring and $\hat{R}$ its $\mathfrak{m}$-adic completion. Then R is regular if and only if $\hat{R}$ is regular.

***Proof*:**
This is proposition 29.8.6. The mechanism is that completion leaves the associated graded ring unchanged, $G_{\mathfrak{m}}(R) \cong G_{\hat{\mathfrak{m}}}(\hat{R})$, and leaves the dimension unchanged; the graded criterion for regularity depends on nothing else, so it holds for one exactly when it holds for the other, as we sought to show.

In this case $\hat{R}$ is again an integral domain.

Exercise 35.5.1

1. Compute the singular locus of $\mathcal{Z}(y^2 - x^3)$, of $\mathcal{Z}(y^2 - x^2 - x^3)$, and of $\mathcal{Z}(xy - z^2) \subseteq \mathbb{A}^3_k$, using proposition 35.2.2 in each case.
2. Show that the singular locus of a variety is a proper closed subset, so that the nonsingular points are dense. Where does the argument use irreducibility?
3. Let $X = \mathcal{Z}(f) \subseteq \mathbb{A}^n_k$ be a hypersurface. Show that $p \in X$ is nonsingular if and only if some $\partial f / \partial x_i$ fails to vanish at p, and give an example in characteristic $p > 0$ where every partial derivative vanishes identically on a nonconstant f.
4. Show that $\dim_k \mathfrak{m}_p / \mathfrak{m}_p^2 \geq \dim X$ at every point of a variety, with equality exactly at the nonsingular points, and identify which inequality of corollary 35.1.1 is being used.
5. Show that a regular local ring is a domain, and give an example of a Noetherian local domain that is not regular.
6. Show that the local ring of the node $\mathcal{Z}(y^2 - x^2 - x^3)$ at the origin is not a domain after completion, although it is a domain before. (This is why $\mathcal{O}_p$ alone cannot distinguish a node from a cusp, and why proposition 35.5.4 is stated for completions.)
7. Use theorem 35.4.3 to show that a regular local ring is a unique factorization domain in dimension one, and explain why the same argument does not immediately give the general case.

36

Tangent Cones and Completions

The Jacobian criterion of chapter 35 decides whether a point is smooth and stops there. It cannot tell the node $y^2 = x^2 + x^3$ from the cusp $y^2 = x^3$: both are singular at the origin, both have a one-dimensional variety with a two-dimensional cotangent space, and no invariant built from $\mathfrak{m}_p/\mathfrak{m}_p^2$ alone separates them. Yet they are visibly different curves, the node crossing itself and the cusp not.

This chapter builds the invariants that see the difference. The first keeps more of the filtration than $\mathfrak{m}_p/\mathfrak{m}_p^2$ does: the associated graded ring of $\mathcal{O}_{X,p}$, whose zero set is the cone of tangent directions and whose Hilbert polynomial is the multiplicity. The second is finer still. Passing to the completion $\hat{\mathcal{O}}_{X,p}$ makes available power series that converge in no algebraic sense, and in that larger ring the node's local equation factors while the cusp's does not; the factors are the branches of the curve through the point. The chapter closes by using regularity to show that on a smooth variety every codimension-one subvariety is locally cut out by one equation, which is the fact section 37.5 needs and could not prove.

36.1 The Tangent Cone and Multiplicity

Throughout, $X \subseteq \mathbb{A}^n_k$ is an affine variety and $p \in X$ a point, and after a translation p is the origin. Write $A = \Gamma(\mathbb{A}^n_k) = k[x_1, \dots, x_n]$ and $\mathfrak{n} = (x_1, \dots, x_n)$ for the maximal ideal at the origin.

Definition 36.1.1: Initial Form

For $0 \neq f \in A$ write $f = f_m + f_{m+1} + \cdots$ with each f_j homogeneous of degree j and $f_m \neq 0$. The *initial form* of f is $f_* = f_m$, and m is the *order* of f at the origin. For an ideal $I \subseteq A$, the *initial ideal* is $I_* = (f_* : 0 \neq f \in I)$, the ideal generated by all initial forms.

The initial form records the lowest-order behaviour of f at the origin, so it is the first place a curve's

shape shows up: for the node $f = y^2 - x^2 - x^3$ it is $y^2 - x^2$, which factors into two distinct lines when $\mathrm{char} k \neq 2$, while for the cusp $f = y^2 - x^3$ it is y^2, a single line doubled. In characteristic 2 the node's initial form is $(y + x)^2$ and the distinction collapses, so that hypothesis is carried explicitly wherever the node is used. That the initial ideal is generated by initial forms and not merely by the initial forms of a generating set is a real distinction, and the next proposition is what makes the definition intrinsic in spite of it.

Definition 36.1.2: Tangent Cone

The *tangent cone algebra* of X at p is the associated graded ring

$$\operatorname{gr}_{\mathfrak{m}_p} \mathcal{O}_{X,p} = \bigoplus_{j \geq 0} \mathfrak{m}_p^j / \mathfrak{m}_p^{j+1}$$

a graded k-algebra. The *tangent cone* $TC_p(X) \subseteq \mathbb{A}_k^n$ is the affine algebraic set $\mathcal{Z}(I_*)$, where $I = \mathcal{I}(X)$.

Proposition 36.1.3: The Tangent Cone Algebra Is Intrinsic

With the notation above, there is an isomorphism of graded k-algebras

$$\operatorname{gr}_{\mathfrak{m}_p} \mathcal{O}_{X,p} \cong A/I_*$$

In particular the tangent cone algebra does not depend on the embedding $X \subseteq \mathbb{A}_k^n$, and $TC_p(X) = \mathcal{Z}(I_*)$ is the zero set of the tangent cone algebra.

***Proof*:**

Step 1: the local ring may be replaced by the coordinate ring. Put $R = \Gamma(X) = A/I$ with maximal ideal $\mathfrak{m} = \mathfrak{n}/I$ at the origin. Each $\mathfrak{m}^j/\mathfrak{m}^{j+1}$ is annihilated by $\mathfrak{m}$, hence is a vector space over $R/\mathfrak{m} = k$, and localizing at $\mathfrak{m}$ acts as the identity on such a module. So $\operatorname{gr}_{\mathfrak{m}_p} \mathcal{O}_{X,p} \cong \operatorname{gr}_{\mathfrak{m}} R$.

Step 2: the surjection and its kernel. The quotient $A \twoheadrightarrow R$ carries $\mathfrak{n}^j$ onto $\mathfrak{m}^j$, hence induces a surjection of graded rings $\operatorname{gr}_{\mathfrak{n}} A \twoheadrightarrow \operatorname{gr}_{\mathfrak{m}} R$, and $\operatorname{gr}_{\mathfrak{n}} A \cong A$ as graded rings since $\mathfrak{n}^j/\mathfrak{n}^{j+1}$ is the space of forms of degree j. In degree j the kernel is

$$\big((I \cap \mathfrak{n}^j) + \mathfrak{n}^{j+1}\big)/\mathfrak{n}^{j+1}$$

and it remains to identify this with the degree-j part of I_*.

Step 3: the kernel is I_*. For one inclusion, let $f \in I$ have initial form f_* of degree m and let g be homogeneous of degree $j - m$. Then $gf \in I$, and since A is a domain the initial form of gf is gf_*, of degree j; so $gf \in I \cap \mathfrak{n}^j$ and $gf \equiv gf_* \pmod{\mathfrak{n}^{j+1}}$. Hence every degree-$j$ element of I_* lies in the kernel. Conversely let $a \in I \cap \mathfrak{n}^j$. Its initial form a_* has degree at least j. If the degree exceeds j then $a \in \mathfrak{n}^{j+1}$ and a contributes 0; if it equals j then $a \equiv a_* \pmod{\mathfrak{n}^{j+1}}$ with $a_* \in I_*$. So the kernel is exactly the degree-j part of I_*, completing the proof.

The proposition is what justifies the name: the left-hand side is built from $\mathcal{O}_{X,p}$ alone and knows nothing of the embedding, so the right-hand side cannot depend on it either, even though I_* is written in the coordinates of $\mathbb{A}_k^n$.

One caution follows immediately, and it is the first place this book runs into the limitation that chapter 49 takes up. The tangent cone algebra A/I_* and the tangent cone $TC_p(X) = \mathcal{Z}(I_*)$ are not equivalent data: passing from the ideal to its zero set discards nilpotents, so the coordinate ring of $TC_p(X)$ is $A/\sqrt{I_*}$ rather than A/I_*. For the cusp $I_* = (y^2)$, so the tangent cone algebra is $k[x,y]/(y^2)$ while the tangent cone is the line $\mathcal{Z}(y)$, and the doubling is visible only in the algebra. The algebra is therefore the finer invariant, and it is the one the multiplicity is defined from.

Definition 36.1.4: Multiplicity

Let $d = \operatorname{kdim}\mathcal{O}_{X,p}$. The function $j \mapsto \ell\big(\mathcal{O}_{X,p}/\mathfrak{m}_p^j\big)$ agrees for $j \gg 0$ with a polynomial in j (proposition 29.3.2) whose degree is d (theorem 29.4.1), and whose leading coefficient may be written $e/d!$ for a positive integer e. This e is the *multiplicity* of X at p, written $m_p(X)$.

Two things in that definition need saying. First, the leading coefficient is $e/d!$ with e a positive integer because a polynomial taking integer values at all large integers is an integer combination $\sum_i c_i \binom{j}{i}$ of binomial coefficients, so its degree-d coefficient is $c_d/d!$ with $c_d \in \mathbb{Z}$; here the values $\ell(\mathcal{O}_{X,p}/\mathfrak{m}_p^j)$ are lengths, hence non-negative integers, and $c_d > 0$ since the polynomial has degree exactly d and is eventually increasing. Second, the first difference of $j \mapsto \ell(\mathcal{O}_{X,p}/\mathfrak{m}_p^j)$ is $\dim_k \mathfrak{m}_p^j/\mathfrak{m}_p^{j+1}$, the Hilbert function of the tangent cone algebra, so $m_p(X)$ is determined by that algebra, and by proposition 36.1.3 by the point alone.

Proposition 36.1.5: Multiplicity of a Hypersurface

Let $n \geq 2$ and let $X = \mathcal{Z}(f) \subseteq \mathbb{A}^n_k$ be a hypersurface with f irreducible, and let $p \in X$. Then $I_* = (f_*)$ and

$$m_p(X) = \deg f_* = \text{the order of } f \text{ at } p$$

***Proof*:**
Since f is irreducible, $\mathcal{I}(X) = (f)$ by the Nullstellensatz (theorem 32.4.4), (f) being prime hence radical. Every element of (f) is gf, and A being a domain gives $(gf)_* = g_* f_*$, so every initial form of an element of (f) is a multiple of f_*; hence $I_* = (f_*)$. Write $m = \deg f_*$.

By proposition 36.1.3 the tangent cone algebra is $A/(f_*)$, whose degree-j piece has dimension $\binom{j+n-1}{n-1} - \binom{j-m+n-1}{n-1}$ for $j \geq m$, multiplication by the form f_* being injective on a domain. This is a polynomial in j of degree $n-2$ with leading coefficient $m/(n-2)!$; the identity holds for $j \geq m$, and the finitely many earlier terms shift the sum below by a constant without affecting its degree or leading coefficient. Summing over j raises the degree by one, so $\ell(\mathcal{O}_{X,p}/\mathfrak{m}_p^j)$ has degree $n-1$ and leading coefficient $m/(n-1)!$. By the dimension theorem that degree is $\operatorname{kdim}\mathcal{O}_{X,p}$, so $d = n-1$, and definition 36.1.4 gives $m_p(X) = m$, as we sought to show.

Proposition 36.1.6: Smooth Points Have Multiplicity One

If p is a smooth point of X then $m_p(X) = 1$. For a hypersurface the converse holds: an irreducible hypersurface with $m_p(X) = 1$ is smooth at p.

***Proof*:**
If p is smooth then $\mathcal{O}_{X,p}$ is regular of dimension d (proposition 35.2.2), so its tangent cone algebra is the polynomial ring $k[t_1, \dots, t_d]$ by theorem 29.8.3. Then $\dim_k \mathfrak{m}_p^j/\mathfrak{m}_p^{j+1} = \binom{j+d-1}{d-1}$, a polynomial of degree $d-1$ with leading coefficient $1/(d-1)!$, and summing gives leading coefficient $1/d!$; so $m_p(X) = 1$.

For the converse on a hypersurface $X = \mathcal{Z}(f)$, proposition 36.1.5 makes $m_p(X) = 1$ say that f_* is a nonzero linear form. That linear form is $\sum_i (\partial f/\partial x_i)(p)\, x_i$ up to translation, so some partial derivative of f is nonzero at p and the Jacobian has rank one there, which is smoothness by definition 35.2.1, completing the proof.

The converse in fact holds for every variety, not only for hypersurfaces, but its proof needs an unmixedness theorem of Nagata that this book does not develop; see [74]. What the general statement does require is irreducibility. On a reducible algebraic set multiplicity one can fail to force regularity: for $\mathcal{Z}(xz, yz) \subseteq \mathbb{A}^3_k$, a plane meeting a line, the local ring at the origin has $\dim_k \mathfrak{m}^j/\mathfrak{m}^{j+1} = j+2$ for $j \geq 1$, so $\ell(R/\mathfrak{m}^j) = j^2/2 + 3j/2 - 1$ and $m = 1$ at a point where the ring is not even a domain.

Example 36.1.7: Tangent Cones of the Node, the Cusp, and the Quadric Cone

1. *The node* $C = \mathcal{Z}(y^2 - x^2 - x^3)$ at the origin. The initial form is $y^2 - x^2 = (y-x)(y+x)$, so the tangent cone is the pair of lines $\mathcal{Z}(y-x) \cup \mathcal{Z}(y+x)$ and $m_0(C) = 2$. The two lines are the two directions in which the curve leaves the origin.

2. *The cusp* $C = \mathcal{Z}(y^2 - x^3)$ at the origin. The initial form is y^2, so $m_0(C) = 2$ as well, but the tangent cone algebra is $k[x,y]/(y^2)$ and the tangent cone is the single line $\mathcal{Z}(y)$, doubled. So the multiplicity does not separate the node from the cusp, while the tangent cone does: two distinct lines against one line with multiplicity two. This is the distinction example 35.2.3 promised.

3. *The quadric cone* $X = \mathcal{Z}(xy - z^2) \subseteq \mathbb{A}^3_k$ at the origin. Here f is already homogeneous, so $f_* = f$ and the tangent cone is X itself: a cone is its own tangent cone at its vertex. By proposition 36.1.5, $m_0(X) = 2$, and by proposition 36.1.6 the vertex is singular, which exercise set 35.5.1 found by computing the Jacobian.

4. *A smooth point.* For the parabola $\mathcal{Z}(y - x^2)$ at the origin the initial form is y, the tangent cone is the tangent line $\mathcal{Z}(y)$, and $m_0 = 1$. At a smooth point the tangent cone is always the tangent space: theorem 29.8.3 makes the tangent cone algebra a polynomial ring on d degree-one generators, so I_* is generated by linear forms.

For a plane curve the tangent cone is a form in two variables, hence a product of linear factors over the algebraically closed k; its factors are the *tangent lines* at the point and their exponents are the tangent multiplicities. That is the description chapter 42 works with, where the multiplicity of a plane curve at a point is defined directly as the order of its defining polynomial. For an *irreducible* f the two definitions agree, by proposition 36.1.5. They part company otherwise, and deliberately so: that chapter takes a plane curve to be a polynomial up to scalar rather than a zero set, so $\mathcal{Z}(y^2)$ carries multiplicity two there while as a variety it is the line $\mathcal{Z}(y)$, of multiplicity one.

36.2 Completion and Local Parameters

The tangent cone keeps more of the local ring than $\mathfrak{m}_p/\mathfrak{m}_p^2$ does, but it is still a linearization: it records the graded pieces $\mathfrak{m}_p^j/\mathfrak{m}_p^{j+1}$ and forgets how they are glued. The completion forgets nothing. It is the inverse limit of the quotients $\mathcal{O}_{X,p}/\mathfrak{m}_p^j$, so an element of it is a compatible system of Taylor approximations to arbitrary order, and the ring it lives in is large enough to contain power series that no polynomial fraction represents.

The construction of the $\mathfrak{m}$-adic completion, its Noetherianity, and the Cohen structure theorem are in *Commutative Algebra* [20, Completion Of A Ring] and are used here without redevelopment. Write $\hat{\mathcal{O}}_{X,p} = \varprojlim_j \mathcal{O}_{X,p}/\mathfrak{m}_p^j$ and $\hat{\mathfrak{m}}_p$ for its maximal ideal. The natural map $\mathcal{O}_{X,p} \to \hat{\mathcal{O}}_{X,p}$ is injective, since its kernel is $\bigcap_j \mathfrak{m}_p^j$, which vanishes in a Noetherian local ring by corollary 25.4.12. So completing loses no functions and adds many.

Theorem 36.2.1: The Completion at a Smooth Point

Let X be a variety over the algebraically closed field k and let $p \in X$ be a smooth point with $\dim_p X = d$. Then

$$\hat{\mathcal{O}}_{X,p} \cong k[[t_1, \dots, t_d]]$$

as k-algebras, and the t_i may be taken to be the images of any regular system of parameters of $\mathcal{O}_{X,p}$.

***Proof*:**
Write $(R, \mathfrak{m}) = (\mathcal{O}_{X,p}, \mathfrak{m}_p)$, a Noetherian local ring of dimension d. Its residue field is k: it equals $k[X]/\mathcal{I}(p)$ for an affine neighbourhood, and Zariski's lemma (theorem 32.4.2) makes that a finite extension of the algebraically closed k, hence k itself. Since p is smooth, R is regular (proposition 35.2.2).

Step 1: the completion is complete regular local of dimension d. The ring $\hat{R}$ is Noetherian local with maximal ideal $\hat{\mathfrak{m}}$ and the same residue field k, by theorem 25.5.7, and $\operatorname{kdim}\hat{R} = \operatorname{kdim} R = d$ by corollary 29.4.2. It is regular by proposition 35.5.4.

Step 2: Cohen's theorem gives a presentation. The ring $\hat{R}$ is complete Noetherian local, contains k, and has residue field k, so theorem 25.6.1 presents it as

$$\hat{R} \cong k[[x_1, \dots, x_n]]/I, \qquad n = \dim_k \hat{\mathfrak{m}}/\hat{\mathfrak{m}}^2$$

Regularity of $\hat{R}$ makes $n = \operatorname{kdim}\hat{R} = d$, so the presentation is $k[[x_1, \dots, x_d]]/I$, and Cohen's theorem takes the x_i to any lift of a basis of $\hat{\mathfrak{m}}/\hat{\mathfrak{m}}^2$, which a regular system of parameters of R provides.

Step 3: the ideal vanishes. This is lemma 36.2.2 below, applied to $\hat{R}$, completing the proof.

The last step is worth isolating, since it is used again in section 36.3 and its argument is independent of the geometry.

Lemma 36.2.2: A Complete Regular Local Ring Is a Power Series Ring

Let $(T, \mathfrak{n})$ be a complete Noetherian regular local ring of dimension d containing a field k with $T/\mathfrak{n} = k$. Then $T \cong k[[x_1, \dots, x_d]]$, the variables mapping to any regular system of parameters.

***Proof*:**

theorem 25.6.1 presents $T \cong S/I$ with $S = k[[x_1, \dots, x_n]]$ and $n = \dim_k \mathfrak{n}/\mathfrak{n}^2$, which regularity makes d; its proof sends the variables to any lift of a basis of $\mathfrak{n}/\mathfrak{n}^2$, that is to any regular system of parameters. It remains to show $I = 0$.

First, S is a domain. A nonzero element of S has a well-defined initial form, its lowest-degree homogeneous part, and the initial form of a product is the product of the initial forms because the polynomial ring $k[x_1, \dots, x_d]$ is a domain; so a product of nonzero elements has a nonzero initial form and is nonzero. (Completion does not preserve domains in general, so this needs the argument rather than a citation.)

Second, $\operatorname{kdim} S = d$: it is the completion of $k[x_1, \dots, x_d]_{(x_1,\dots,x_d)}$, whose dimension is d by corollary 34.2.7 and proposition 34.3.2, and corollary 29.4.2 applies.

Now suppose $I \neq 0$ and pick $0 \neq f \in I$; it is a nonunit, I being proper. Any chain of primes $\mathfrak{q}_0 \subsetneq \cdots \subsetneq \mathfrak{q}_e$ in S/I lifts to a chain of primes of S all containing f, hence all nonzero, so prepending the zero ideal, legitimate as S is a domain, gives a chain of length $e+1$ in S. Therefore $e + 1 \leq \operatorname{kdim} S = d$, so $\operatorname{kdim} S/I \leq d - 1$. But $S/I \cong T$ has dimension d, a contradiction. So $I = 0$, as we sought to show.

Definition 36.2.3: Local Parameters

A *system of local parameters* at a smooth point p of a d-dimensional variety is a regular system of parameters $t_1, \dots, t_d$ of $\mathcal{O}_{X,p}$, that is, d elements of $\mathfrak{m}_p$ generating it. For a curve, $d = 1$ and a single generator t of $\mathfrak{m}_p$ is a *local parameter* or *uniformizer* at p.

Corollary 36.2.4: Power Series Expansion

Let p be a smooth point of X with local parameters $t_1, \dots, t_d$. Every $f \in \mathcal{O}_{X,p}$ has a unique expansion as a formal power series in $t_1, \dots, t_d$ with coefficients in k, and $f \in \mathfrak{m}_p^j$ if and only if that series has no terms of degree less than j.

***Proof*:**

The composite $\mathcal{O}_{X,p} \hookrightarrow \hat{\mathcal{O}}_{X,p} \cong k[[t_1, \dots, t_d]]$ is injective by the remark before theorem 36.2.1, which gives existence and uniqueness of the expansion. Under the isomorphism $\hat{\mathfrak{m}}_p^j$ corresponds to the series of order at least j, so it remains to see that $\mathcal{O}_{X,p} \cap \hat{\mathfrak{m}}_p^j = \mathfrak{m}_p^j$. For a Noetherian local ring, corollary 25.1.5 identifies $\hat{\mathcal{O}}/\hat{\mathfrak{m}}_p^j$ with $\mathcal{O}_{X,p}/\mathfrak{m}_p^j$ compatibly with the map from $\mathcal{O}_{X,p}$, so that map composed with the projection is the projection $\mathcal{O}_{X,p} \to \mathcal{O}_{X,p}/\mathfrak{m}_p^j$, whose kernel is $\mathfrak{m}_p^j$, completing the proof.

For a curve the corollary is the statement that a regular function near a smooth point is a power series in the uniformizer, and the order of that series is the order of vanishing; definition 42.2.4 will take it as the definition. In higher dimension it is the algebraic substitute for a coordinate chart: a smooth point has no neighbourhood isomorphic to an open set of $\mathbb{A}^d_k$ in the Zariski topology, but it always has a formal one.

Example 36.2.5: Completions at Smooth and Singular Points

1. *Affine space.* At the origin of $\mathbb{A}^d_k$ the coordinates $x_1, \dots, x_d$ are local parameters and $\hat{\mathcal{O}} \cong k[[x_1, \dots, x_d]]$, which is example 25.1.2 read geometrically.
2. *A smooth plane curve.* On $C = \mathcal{Z}(y - x^2)$ the function x generates $\mathfrak{m}_0$, since $y = x^2$ in $\Gamma(C)$, so x is a uniformizer and $\hat{\mathcal{O}}_{C,0} \cong k[[x]]$. Every regular function near the origin is a power series in x alone, the variable y contributing nothing new.
3. *The parabola meets its axis.* On the same curve the function y has expansion x^2, so $\operatorname{ord}_0(y) = 2$: the axis $\mathcal{Z}(y)$ meets C doubly at the origin. That doubling is the intersection multiplicity chapter 42 will count.
4. *A singular point is not a power series ring.* At the origin of the cusp $\mathcal{Z}(y^2 - x^3)$ the ring $\hat{\mathcal{O}}$ is $k[[x, y]]/(y^2 - x^3)$, computed in proposition 36.3.1 below. It is not isomorphic to $k[[t]]$, since $\dim_k \hat{\mathfrak{m}}/\hat{\mathfrak{m}}^2 = 2$ there while $k[[t]]$ has $\dim_k (t)/(t^2) = 1$; theorem 36.2.1 of course forbids it, the origin being singular.

36.3 Formal Branches

The completion separates the node from the cusp, and it does so in the most direct way available: at the node the local equation factors, and at the cusp it does not. Neither factorization exists in $\mathcal{O}_{X,p}$, because the factors involve a square root that is a power series and not a rational function. This section makes that precise and attaches to each singular point of a curve a number, the count of branches through it.

Proposition 36.3.1: The Completion of a Plane Curve

Let $C = \mathcal{Z}(f) \subseteq \mathbb{A}^2_k$ be a plane curve with f irreducible and $p = (0, 0) \in C$. Then

$$\hat{\mathcal{O}}_{C,p} \cong k[[x, y]]/(f)$$

***Proof*:**
Write $A = k[x, y]$, $\mathfrak{n} = (x, y)$ and $R = \Gamma(C) = A/(f)$, with $\mathfrak{m}$ the image of $\mathfrak{n}$.

Step 1: the local ring may be replaced by the coordinate ring. For every j the ideal $\mathfrak{m}^j$ is $\mathfrak{m}$-primary, so $R/\mathfrak{m}^j$ is already local with maximal ideal $\mathfrak{m}/\mathfrak{m}^j$ and localizing at $\mathfrak{m}$ does nothing: $R/\mathfrak{m}^j \cong R_{\mathfrak{m}}/(\mathfrak{m}R_{\mathfrak{m}})^j$. Taking inverse limits, the $\mathfrak{m}$-adic completion of R agrees with the $\mathfrak{m}_p$-adic completion of $\mathcal{O}_{C,p} = R_{\mathfrak{m}}$. The same argument identifies the $\mathfrak{n}$-adic completion of A with that of $A_{\mathfrak{n}}$, and the former is $k[[x, y]]$ by example 25.1.2.

Step 2: complete the presentation. Completion is exact on finitely generated modules over a Noetherian ring (corollary 25.4.4), so applying it to $0 \to (f) \to A \to R \to 0$ gives $\hat{R} \cong k[[x,y]]/(f)k[[x,y]]$, and $(f)k[[x,y]]$ is the ideal generated by f there. Combining with Step 1 gives the claim, as we sought to show.

Definition 36.3.2: Formal Branch

Let p be a point of a variety X. A *formal branch* of X at p is a minimal prime of $\hat{\mathcal{O}}_{X,p}$. The number of formal branches is the number of such primes, which is finite because $\hat{\mathcal{O}}_{X,p}$ is Noetherian.

A smooth point has one branch, since $\hat{\mathcal{O}}_{X,p}$ is then a power series ring and hence a domain, whose unique minimal prime is 0. The content of the definition is at singular points, where a curve may pass through p more than once.

Proposition 36.3.3: The Node Has Two Branches, the Cusp One

At the origin,

1. if $\mathrm{char} k \neq 2$, the node $N = \mathcal{Z}(y^2 - x^2 - x^3)$ has exactly two formal branches, and $\hat{\mathcal{O}}_{N,0} \cong k[[u,v]]/(uv)$;
2. in every characteristic, the cusp $C = \mathcal{Z}(y^2 - x^3)$ has exactly one formal branch, and $\hat{\mathcal{O}}_{C,0}$ is a domain that is not a power series ring.

***Proof*:**

The node. In $k[[x]]$ the series $1 + x$ has a square root when $\mathrm{char} k \neq 2$. Seek $w = 1 + \sum_{n \geq 1} a_n x^n$ with $w^2 = 1 + x$; comparing coefficients gives $2a_1 = 1$ and, for $n \geq 2$,

$$2a_n = -\sum_{0<i<n} a_i a_{n-i}$$

Each equation determines a_n from its predecessors, division by 2 being the only division performed, so w exists, and it is a unit since $w(0) = 1$. Then in $k[[x,y]]$

$$y^2 - x^2 - x^3 = y^2 - x^2(1+x) = (y - xw)(y + xw)$$

Put $u = y - xw$ and $v = y + xw$. Both have order 1 with linear parts $y - x$ and $y + x$, which are linearly independent as $\mathrm{char} k \neq 2$, so their classes span $\mathfrak{n}/\mathfrak{n}^2$ for $\mathfrak{n}$ the maximal ideal of $k[[x,y]]$, and Nakayama's lemma (lemma 23.4.27) makes u, v generate $\mathfrak{n}$. Thus u, v is a regular system of parameters of the complete regular local ring $k[[x,y]]$, and lemma 36.2.2 gives $k[[x,y]] = k[[u,v]]$. By proposition 36.3.1, $\hat{\mathcal{O}}_{N,0} \cong k[[u,v]]/(uv)$, whose minimal primes are (u) and (v): these are prime because the quotients $k[[v]]$ and $k[[u]]$ are domains, they are minimal because $(uv) \subseteq \mathfrak{p}$ forces $u \in \mathfrak{p}$ or $v \in \mathfrak{p}$, and they are distinct. So there are exactly two branches.

The cusp. By proposition 36.3.1, $\hat{\mathcal{O}}_{C,0} \cong k[[x,y]]/(y^2 - x^3)$, so it suffices to show $y^2 - x^3$ is irreducible in $k[[x,y]]$; then $(y^2 - x^3)$ is prime, it is the unique minimal prime of the quotient, and the quotient is a domain. Suppose $y^2 - x^3 = gh$ with g, h nonunits. Setting $x = 0$ gives $y^2 = g(0,y)h(0,y)$ in $k[[y]]$, so the orders of $g(0,y)$ and $h(0,y)$ in y sum to 2; neither can be 0, since a factor with $g(0,y)$ a unit would be a unit in $k[[x,y]]$, so both orders are 1. The

Weierstrass preparation theorem (theorem 25.7.3) then writes each as a unit times a monic degree-one polynomial in y over $k[[x]]$, so

$$y^2 - x^3 = \varepsilon\,(y - a(x))(y - b(x)), \qquad a, b \in (x) \subseteq k[[x]]$$

with ε a unit. Here $(y-a)(y-b)$ is a Weierstrass polynomial of degree two, its lower coefficients lying in (x), and so is $y^2 - x^3$ itself; the uniqueness clause of the same theorem therefore forces $\varepsilon = 1$. Comparing coefficients gives $a + b = 0$ and $ab = -x^3$, so $b = -a$ and $a^2 = x^3$. Taking orders in $k[[x]]$ gives $2\,\mathrm{ord}(a) = 3$, impossible. So $y^2 - x^3$ is irreducible.

Finally $\hat{\mathcal{O}}_{C,0}$ is not a power series ring, since $\dim_k \hat{\mathfrak{m}}/\hat{\mathfrak{m}}^2 = 2$ while $\mathrm{kdim} = 1$, completing the proof.

Definition 36.3.4: Analytically Isomorphic Singularities

Two pointed varieties (X, p) and (Y, q) are *analytically isomorphic* if $\hat{\mathcal{O}}_{X,p} \cong \hat{\mathcal{O}}_{Y,q}$ as k-algebras.

The computation says more than that the node has two branches: it says the node is analytically isomorphic to the crossing of the two coordinate axes $\mathcal{Z}(xy)$ at the origin, since both completions are $k[[u, v]]/(uv)$, while the cusp belongs to a different class. This is a genuinely finer relation than isomorphism of neighbourhoods: the node and the pair of axes are not isomorphic as varieties near the origin, one being irreducible and the other not, and it is exactly the passage to the completion that makes them agree. The same argument applies to any plane curve whose tangent cone at p is two distinct lines, which definition 42.1.6 will call an ordinary double point.

The characteristic hypothesis in the first case is not a technicality. In characteristic two, $y^2 - x^2 - x^3 = (y+x)^2 - x^3$, so substituting $u = y + x$ turns the node's equation into $u^2 - x^3$: the curve is analytically a cusp there, with one branch rather than two. The tangent cone sees the same collapse, its initial form being the doubled line $(y + x)^2$.

The count of branches is a local invariant that a global construction also computes: the normalization of a curve separates its branches, so the points lying over p should correspond to them. Making that precise needs the normalization, which is chapter 37, and the comparison is carried out there as proposition 37.2.4.

36.4 Local Factoriality and Weil Divisors

The last local property of this chapter is the one section 37.5 depends on. A Weil divisor on a normal variety is a formal sum of codimension-one subvarieties, and the class group measures how far such a sum is from being the divisor of a function. That measurement is only meaningful once one knows when a codimension-one subvariety is cut out by a single equation near each point, and the answer is that smoothness suffices.

Corollary 36.4.1: A Smooth Variety Is Locally Factorial

Let X be a variety and $p \in X$ a smooth point. Then $\mathcal{O}_{X,p}$ is a unique factorization domain.

***Proof*:**
By proposition 35.2.2 the ring $\mathcal{O}_{X,p}$ is regular local, and a regular local ring is factorial by theorem 29.9.5, as we sought to show.

Theorem 36.4.2: Codimension One Is Locally Principal at a Smooth Point

Let X be a variety, $Y \subseteq X$ an irreducible closed subvariety of codimension one, and $p \in Y$ a point at which X is smooth. Then the ideal of Y in $\mathcal{O}_{X,p}$ is principal: there is $f \in \mathcal{O}_{X,p}$ generating it.

***Proof*:**
Step 1: reduce to the affine case. Choose an affine open $U \subseteq X$ containing p. Passing to U changes neither $\mathcal{O}_{X,p}$ nor the codimension, so $Y \cap U$ is an irreducible closed subvariety of U of codimension one, and its ideal $\mathcal{I}(Y \cap U) \subseteq k[U]$ is prime and contained in the maximal ideal at p, the point p lying on Y.

Step 2: the ideal has height one. By definition 34.3.1 the codimension of $Y \cap U$ in U is the supremum of lengths of chains of irreducible closed subsets ascending from $Y \cap U$, and the correspondence between irreducible closed subsets and prime ideals reverses inclusions (theorem 32.4.4), so such chains correspond to chains of primes descending from $\mathcal{I}(Y \cap U)$. Hence $\operatorname{ht} \mathcal{I}(Y \cap U) = \operatorname{codim}_U (Y \cap U) = 1$. Localizing at p preserves both primality and height, since the primes contained in $\mathcal{I}(Y \cap U)$ are exactly those surviving in the localization.

Step 3: apply factoriality. The ring $R = \mathcal{O}_{X,p}$ is a Noetherian local domain by proposition 33.2.10 and factorial by corollary 36.4.1, p being a smooth point. A height-one prime of a Noetherian factorial domain is principal, by lemma 29.9.1, which gives the generator f, completing the proof.

The theorem is what makes the class group of section 37.5 a global invariant on a smooth variety: every prime divisor is locally the zero set of one function, so a nonzero class records an obstruction to patching those local equations into a single global one, not a failure at any individual point. On a singular normal variety the obstruction is already local, and the quadric cone is the standard example.

Proposition 36.4.3: The Quadric Cone Is Not Locally Factorial at Its Vertex

Let $X = \mathcal{Z}(xy - z^2) \subseteq \mathbb{A}^3_k$ with vertex v the origin. Then $\mathcal{O}_{X,v}$ is not a unique factorization domain, and the ideal of the ruling $L = \mathcal{Z}(x, z) \subseteq X$ is a height-one prime of $\mathcal{O}_{X,v}$ that is not principal.

***Proof*:**
Write $R = \mathcal{O}_{X,v}$ with maximal ideal $\mathfrak{m}$, and let $\overline{x}, \overline{y}, \overline{z}$ be the images of the coordinates. Each lies in $\mathfrak{m} \setminus \mathfrak{m}^2$: the images of x, y, z form a basis of $\mathfrak{m}/\mathfrak{m}^2$, because the defining equation $xy - z^2$ lies in $(x, y, z)^2$ and so imposes no linear condition on $\mathfrak{m}/\mathfrak{m}^2$. An element of $\mathfrak{m} \setminus \mathfrak{m}^2$ is irreducible in R: a factorization into two nonunits would place it in $\mathfrak{m}^2$. So $\overline{x}, \overline{y}, \overline{z}$ are irreducible, and no two are associates, their classes in $\mathfrak{m}/\mathfrak{m}^2$ being linearly independent while an associate would differ by a unit and hence have proportional class.

The relation $\overline{x}\,\overline{y} = \overline{z}^{\,2}$ therefore exhibits two factorizations of one element into irreducibles that do not match up to associates and reordering, so R is not factorial. Here R is a Noetherian local domain by proposition 33.2.10, the cone being a variety, so lemma 29.9.1 applies and some height-one prime of R fails to be principal.

That prime may be named. The ideal $\mathfrak{p} = (\overline{x}, \overline{z})$ is the ideal of L in R, and it has height one, L having codimension one in X. Suppose $\mathfrak{p} = (f)$. Then f divides $\overline{x}$ and is a nonunit, and $\overline{x}$ is irreducible, so $(f) = (\overline{x})$. From $\overline{z} \in (\overline{x})$ write $\overline{z} = \overline{x}h$; then

$$\overline{x}\,\overline{y} = \overline{z}^{\,2} = \overline{x}^{\,2}h^2$$

and cancelling $\overline{x}$, legitimate in a domain, gives $\overline{y} = \overline{x}h^2$. As $\overline{y}$ is irreducible and $\overline{x}$ is not a unit, h^2 must be a unit, making $\overline{y}$ and $\overline{x}$ associates and contradicting what was shown above. So $\mathfrak{p}$ is not principal, as we sought to show.

The failure is concentrated at the vertex alone: away from v the cone is smooth, so theorem 36.4.2 applies at every other point of L and makes the ideal of L principal there. Note that L is nonetheless the zero set of a single function, since $\mathcal{Z}(x) \cap X = \mathcal{Z}(x, z^2) \cap X = L$ as a set; what fails is that no one function generates the ideal near v, and $\operatorname{div}(x) = 2L$ in section 37.5 is the quantitative form of that failure, the function that does vanish exactly on L vanishing to order two.

Exercise 36.4.1

1. Compute the tangent cone and the multiplicity at the origin of $C = \mathcal{Z}(y^2 - x^5) \subseteq \mathbb{A}^2_k$, and show that C is irreducible. How do the answers compare with the cusp $\mathcal{Z}(y^2 - x^3)$, and what does the comparison say about whether the tangent cone alone classifies plane singularities?

2. Let $\operatorname{char} k \neq 3$ and let $F = \mathcal{Z}(x^3 + y^3 - 3xy) \subseteq \mathbb{A}^2_k$ be the folium. Compute its tangent cone and multiplicity at the origin, and decide whether the origin is an ordinary double point.

3. Show that if $f \in k[x_1, \dots, x_n]$ is homogeneous and irreducible, then the tangent cone of $\mathcal{Z}(f)$ at the origin is $\mathcal{Z}(f)$ itself. Why is this what the word *cone* is meant to record?

4. Let p be a smooth point of a variety X with $\dim_p X = d$. Show that $TC_p(X)$ is a linear subspace of $\mathbb{A}^n_k$ of dimension d, and identify it with the tangent space.

5. The node $N = \mathcal{Z}(y^2 - x^2 - x^3)$ passes through $(-1, 0)$ as well as the origin. Show that N is smooth at $(-1, 0)$ and compute $m_{(-1,0)}(N)$ and the tangent cone there.

6. Let $\operatorname{char} k \neq 2$ and let $C = \mathcal{Z}(x^2 + y^2 - 1)$. Show that y is a local parameter at $(1, 0)$ and that $\hat{\mathcal{O}}_{C,(1,0)} \cong k[[y]]$. Write the expansion of $x - 1$ as a power series in y to order three.

7. Let C be a curve and $p \in C$. Show that if $\hat{\mathcal{O}}_{C,p} \cong k[[t]]$ then p is a smooth point of C, so the converse of theorem 36.2.1 holds in dimension one.

8. Show that $k[[x, y]]/(xy)$ has exactly two minimal primes, and conclude that the union of the two coordinate axes has two formal branches at the origin.

9. Show that analytically isomorphic pointed varieties have the same multiplicity and the same number of formal branches. Deduce that the node and the cusp are not analytically isomorphic when $\operatorname{char} k \neq 2$, and explain what happens to this deduction in characteristic two.

10. Show that every irreducible closed subvariety of $\mathbb{A}^n_k$ of codimension one is the zero set of a single irreducible polynomial, and that its ideal is principal in every local ring of $\mathbb{A}^n_k$. Which is the stronger statement, and why does theorem 36.4.2 not already give it?

11. Let p be a smooth point of X. Show that $\mathcal{O}_{X,p}$ is integrally closed in its fraction field, so that X is normal at every smooth point.

12. For the quadric cone $X = \mathcal{Z}(xy - z^2)$ and the ruling $L = \mathcal{Z}(x, z)$, show directly that $\mathcal{I}(L)$ is a prime of height one in $k[X]$, and that $\mathcal{Z}(x) \cap X = L$ as sets.

13. Show that the tangent cone algebra of the cusp at the origin is $k[x, y]/(y^2)$, and compute $\dim_k \mathfrak{m}^j/\mathfrak{m}^{j+1}$ for every j. Confirm that the multiplicity read from this Hilbert function is 2.

14. Let R be the local ring of $\mathcal{Z}(xz, yz) \subseteq \mathbb{A}^3_k$ at the origin, a plane meeting a line. Show $\dim_k \mathfrak{m}^j/\mathfrak{m}^{j+1} = j + 2$ for $j \geq 1$, deduce $m = 1$, and explain why this does not contradict proposition 36.1.6.

37

Normal Varieties and Normalization

A variety can fail to be smooth in two quite different ways, and only one of them is repairable by an isomorphism of the function field. Normality is the condition that isolates the repairable case: a variety is normal when its coordinate ring is integrally closed in its function field, and every variety admits a normalization, a finite birational map onto it from a normal one.

For curves normality and smoothness coincide, and the normalization is the smooth model. That gives this chapter's structural result: a field of transcendence degree one over k determines a unique nonsingular projective curve, so a curve and its function field are the same information.

37.1 Integrally Closed Domains and Normal Varieties

The map $\varphi\colon \mathbb{A}^1_k \to \mathcal{Z}(x^3 - y^2)$ given by $t \mapsto (t^2, t^3)$ of example 31.4.8 is a bijective birational morphism that is not an isomorphism. Its inverse is y/x, a rational function that is not regular at the origin. That failure has a purely algebraic signature. The coordinate ring is $k[t^2, t^3]$, its function field is $k(t)$, and the missing element $t = t^3/t^2$ satisfies

$$T^2 - t^2 = 0$$

a monic equation over $k[t^2, t^3]$. So t is integral over the coordinate ring without belonging to it: the ring is not integrally closed in its own fraction field. Normality is the condition that this cannot happen, and it will turn out to be exactly the condition under which the pathology above is absent.

Integral dependence, integral closure, and the term *normal domain* are developed in *Commutative Algebra* [20, Integral Elements] and are used here without redevelopment.

Definition 37.1.1: Normal Variety

Let X be an affine variety, so that $k[X]$ is an integral domain with fraction field $k(X)$. Then X is *normal* if $k[X]$ is integrally closed in $k(X)$.

More locally, X is *normal at* $p \in X$ if the stalk $\mathcal{O}_p(X)$ is integrally closed in $k(X)$.

The two notions agree, which is what makes normality a usable local condition rather than a global accident.

Proposition 37.1.2: Normality Is Local

An affine variety X is normal if and only if it is normal at every point.

***Proof*:**
By proposition 33.2.9, $k[X] = \bigcap_{p \in X} \mathcal{O}_p(X)$, and each $\mathcal{O}_p(X)$ is the localization of $k[X]$ at the maximal ideal $\mathcal{I}(p)$. Integral closure commutes with localization (corollary 26.1.10), which gives exactly the statement that a domain is normal precisely when all of its localizations at maximal ideals are, as we sought to show.

The first normal varieties come from a purely algebraic observation.

Proposition 37.1.3: Unique Factorization Implies Normal

Every unique factorization domain is integrally closed in its fraction field.

***Proof*:**
Let R be a UFD with fraction field K and let $x = a/b \in K$ be integral over R, written in lowest terms so that a and b share no irreducible factor. An integral relation

$$\left(\frac{a}{b}\right)^n + r_{n-1}\left(\frac{a}{b}\right)^{n-1} + \cdots + r_0 = 0 \qquad r_i \in R$$

becomes, after multiplying through by b^n,

$$a^n = -b\left(r_{n-1}a^{n-1} + r_{n-2}a^{n-2}b + \cdots + r_0 b^{n-1}\right)$$

So every irreducible factor of b divides a^n, and being prime in a UFD, divides a. As a and b are coprime, b has no irreducible factors at all, so b is a unit and $x \in R$, as we sought to show.

Example 37.1.4: Normal and Non-Normal Varieties

1. Affine space $\mathbb{A}^n_k$ is normal. Its coordinate ring is the polynomial ring $k[x_1, \ldots, x_n]$, a UFD (corollary 11.2.4), hence normal by proposition 37.1.3.
2. The cuspidal cubic $C = \mathcal{Z}(x^3 - y^2) \subseteq \mathbb{A}^2_k$ is not normal, by the computation opening this section: $t = y/x$ lies in $k(C)$ and is integral over $k[C]$ but not in it. The failure is concentrated at one point, the cusp: away from the origin x is invertible, so y/x is already

regular there and C is normal at every other point.

3. The nodal cubic $N = \mathcal{Z}(y^2 - x^2 - x^3)$ is not normal either. Its parameterization $t \mapsto (t^2 - 1, t(t^2 - 1))$ from example 33.3.8 identifies $k(N)$ with $k(t)$, and $t = y/x$ is again integral over $k[N]$ without lying in it. Here the failure sits at the node, where two branches of the curve cross.

4. The quadric cone $Q = \mathcal{Z}(xy - z^2) \subseteq \mathbb{A}^3_k$ *is* normal, and it is singular at the origin. Section 37.4 returns to this: in dimension one normality and smoothness coincide, but from dimension two onward normality is strictly weaker.

Items (2) and (3) share a shape. In both, the curve is the image of a map from a smooth curve that is injective away from a small set, and the element of the function field that fails to be regular is the one that undoes the map. Item (4) shows the shape is special to curves.

37.2 The Normalization of an Affine Variety

Given a variety that is not normal, one can ask for the closest normal variety above it. The construction is forced: take the integral closure of the coordinate ring, and read it back as a variety. The only thing that needs proof is that the result is again the coordinate ring of a variety, and that is exactly the finiteness theorem for integral closures.

Theorem 37.2.1: Existence of the Normalization

Let X be an affine variety and let $\widetilde{k[X]}$ be the integral closure of $k[X]$ in $k(X)$. Then there is an affine variety $\tilde{X}$, the *normalization* of X, with

$$k[\tilde{X}] = \widetilde{k[X]}$$

together with a morphism $\nu\colon \tilde{X} \to X$ induced by the inclusion $k[X] \hookrightarrow \widetilde{k[X]}$. Moreover:

1. $\tilde{X}$ is normal;
2. $k[\tilde{X}]$ is a finite $k[X]$-module;
3. ν is surjective with finite fibres, and induces an isomorphism $k(\tilde{X}) \cong k(X)$, so ν is birational;
4. ν restricts to an isomorphism over the set of points at which X is already normal.

***Proof*:**
Step 1: the ring is a coordinate ring. $k[X]$ is a domain, finitely generated as a k-algebra, so theorem 26.1.11 applies with $L = \mathrm{Frac}(k[X]) = k(X)$: the integral closure $\widetilde{k[X]}$ is a finite $k[X]$-module, and in particular is itself a finitely generated k-algebra. This gives (2). Being a subring of the field $k(X)$ it is a domain, hence reduced, so proposition 32.5.5 realizes it as the coordinate ring of an affine algebraic set $\tilde{X}$, which is a variety by corollary 32.3.4. The inclusion of k-algebras corresponds under theorem 32.1.5 to a morphism $\nu\colon \tilde{X} \to X$.

Step 2: normality. An element of $k(\tilde{X})$ integral over $\widetilde{k[X]}$ is integral over $k[X]$ by transitivity of integral dependence, hence already lies in $\widetilde{k[X]}$. So $\widetilde{k[X]}$ is integrally closed and $\tilde{X}$ is normal, giving (1).

Step 3: birational and surjective. Every element of $\widetilde{k[X]}$ lies in $k(X)$, so $k(\tilde{X}) = \mathrm{Frac}(\widetilde{k[X]}) = k(X)$ and ν is birational. Since $k[\tilde{X}]$ is integral over $k[X]$, the going-up property gives a prime of $k[\tilde{X}]$ over every prime of $k[X]$, and in particular a point of $\tilde{X}$ over every point of X; finiteness of the fibres follows because $k[\tilde{X}]$ is a finite $k[X]$-module. This is (3), and it is the first instance of what section 40.3 will call a *finite morphism*.

Step 4: isomorphism over the normal locus. Suppose X is normal at p, so $\mathcal{O}_p(X)$ is integrally closed. Localizing the inclusion $k[X] \subseteq \widetilde{k[X]}$ at $\mathcal{I}(p)$ and using that integral closure commutes with localization (corollary 26.1.10) gives $\mathcal{O}_p(X) = \widetilde{\mathcal{O}_p(X)}$, so ν is an isomorphism of local rings there and hence an isomorphism on a neighbourhood, which is (4), completing the proof.

Part (4) says the normalization only does work where the variety was not already normal, and part (3) says it never changes the function field. Together these make ν the minimal repair: it is birational, so it preserves everything visible to rational functions, and it is an isomorphism wherever no repair was needed. The universal property makes "minimal" precise.

Proposition 37.2.2: Universal Property of Normalization

Let X be an affine variety with normalization $\nu\colon \tilde{X} \to X$. If Y is a normal affine variety and $f\colon Y \to X$ is a dominating morphism, then f factors uniquely through ν:

$$f = \nu \circ g \qquad \text{for a unique morphism } g\colon Y \to \tilde{X}$$

***Proof*:**
Since f is dominating, $f^{\#}\colon k[X] \to k[Y]$ is injective (proposition 33.3.4(2)) and extends to an embedding $k(X) \hookrightarrow k(Y)$. Any $u \in \widetilde{k[X]}$ satisfies a monic equation over $k[X]$; applying $f^{\#}$ to that equation shows $f^{\#}(u)$ is integral over $k[Y]$, and $k[Y]$ is integrally closed because Y is normal, so $f^{\#}(u) \in k[Y]$. Hence $f^{\#}$ extends to $\widetilde{k[X]} = k[\tilde{X}] \to k[Y]$, and this extension is unique because $\widetilde{k[X]}$ sits inside $k(X)$, on which $f^{\#}$ is already determined. Applying theorem 32.1.5 converts this into the asserted unique factorization $f = \nu \circ g$, as we sought to show.

Example 37.2.3: Normalizing the Cuspidal and Nodal Cubics

1. For the cuspidal cubic $C = \mathcal{Z}(x^3 - y^2)$ with $k[C] = k[t^2, t^3]$, the integral closure in $k(t)$ is all of $k[t]$: it contains t by the opening computation, and $k[t]$ is normal by proposition 37.1.3, so nothing larger is needed. Hence $\tilde{C} = \mathbb{A}^1_k$ and ν is the parameterization $t \mapsto (t^2, t^3)$. It is bijective, and an isomorphism away from the cusp.

2. For the nodal cubic N, the same computation gives $\tilde{N} = \mathbb{A}^1_k$ with $\nu(t) = (t^2 - 1, t(t^2 - 1))$. Here ν is *not* injective: both $t = 1$ and $t = -1$ map to the origin. The normalization has pulled the two branches of the node apart, which is what separating a self-crossing requires.

3. Both examples end at $\mathbb{A}^1$: by corollary 37.4.2 below, normalizing a curve always produces a

smooth one.

The contrast between (1) and (2) is worth holding on to. A cusp is repaired without changing the underlying set, since ν is a bijection; a node is repaired by separating points that had been glued. Both are invisible to the function field, which is why birational geometry cannot see them and why a normal model is the right thing to ask for.

What the normalization separates is exactly what the completion sees, which is the comparison section 36.3 deferred to here.

Proposition 37.2.4: Branches and the Normalization of a Curve

Let C be an affine curve, $p \in C$ a point, and $\nu\colon \tilde{C} \to C$ the normalization of theorem 37.2.1. Then the number of formal branches of C at p, in the sense of definition 36.3.2, equals the number of points of $\tilde{C}$ lying over p.

***Proof Key ideas*:**

Both counts are computed by the same ring. The points of $\tilde{C}$ over p correspond to the maximal ideals of the integral closure $\tilde{\mathcal{O}}$ of $\mathcal{O}_{C,p}$ in its fraction field, which is finite over $\mathcal{O}_{C,p}$ by theorem 37.2.1 together with corollary 26.1.10, hence semilocal; and the minimal primes of $\hat{\mathcal{O}}_{C,p}$ correspond to the factors in the decomposition of $\hat{\tilde{\mathcal{O}}}$ into complete local rings, one for each maximal ideal of $\tilde{\mathcal{O}}$. Matching the two requires knowing that completion commutes with integral closure for a curve over a field, which is the statement that $\mathcal{O}_{C,p}$ is analytically unramified; that is a theorem about excellent rings and is not developed in this series. See [74].

The two cases this book uses are checked directly instead. Proposition 36.3.3 gives two branches at the node and one at the cusp, and the fifth and first exercises of exercise set 37.5.1 compute the normalizations: two points lie over the node, at $t = \pm 1$, and one over the cusp, at $t = 0$. So the counts agree in both cases, completing the argument in the cases used.

37.3 Curves, Function Fields, and Discrete Valuation Rings

Definition 37.3.1: Local Ring of Field

Let K/k be a field extension. Then A is a *local ring of* K if $\mathrm{Frac}(A) = K$ and $k \subseteq A$. If A is a DVR, we shall say that A is a *discrete valuation ring of* K.

The prototypical example of local fields over a ring are the stalks $\mathcal{O}_p(V)$ of $\kappa(V)$ for a variety V.

Theorem 37.3.2: Dominating DVR

Let C be a projective curve, $K = \kappa(C)$, and let L/K be a field extension. Let R be a DVR of L containing k. Assume $K \not\subseteq R$. Then there is a unique point $p \in C$ such that R dominates $\mathcal{O}_p(C)$.

***Proof*:**
First, such a point is unique; if R dominates $\mathcal{O}_p(C)$ and $\mathcal{O}_q(C)$, then choose $f \in \mathfrak{m}_p(C)$ so $1/f \in \mathcal{O}_q(C)$. Then $\operatorname{ord}(f) > 0$ and $\operatorname{ord}(1/f) \geq 0$, a contradiction.

Thus, let's show it exists. Let $C \subseteq \mathbb{P}^n_k$ be a projective curve (a closed one-dimensional subvariety. Without loss of generality, we may take C to not be strictly contained in any x_i-hyperplane so that $C \cap U_i \neq \emptyset$. Then in each $k_{\mathbb{P}}[C] = k[x_1, ..., x_n + 1]/I(C) \cong k[u_1, ..., u_{n+1}]$. Let

$$N = \max_{i,j}(x_i/x_j)$$

As the max is achieve, without loss of generality assume $\operatorname{ord}(x_j/x_{n+1}) = N$ for some j. Then for all i:

$$\operatorname{ord}\left(\frac{u_i}{u_{n+1}}\right) = \operatorname{ord}\left(\frac{(u_j/u_{n+1})}{(u_i/u_j)}\right) = N - \operatorname{ord}(u_j/u_i) \geq 0$$

If C_* is the affine curve corresponding to $C \cap U_{n+1}$, then $\Gamma(C_*)$ can be defined with

$$k\left[\frac{u_1}{u_{n+1}}, ..., \frac{u_n}{u_{n+1}}\right]$$

hence, $\Gamma(C_*) \subseteq R$.

Now, if $\mathfrak{m}$ is the maximal ideal of R, let $J = \mathfrak{m} \cap \Gamma(C_*)$. Then J is a prime ideal, so J corresponds to a closed subvariety $W \subseteq C_*$. IF $W = C_*$, $J = 0$, and every nonzero element of $\Gamma(C_*)$ is a unit of R. But then $K \subseteq R$, contradiction our assumption. So $W = \{p\}$ must be a point. Then R certainly dominates $\mathcal{O}_p(C_*)$, and hence dominates $\mathcal{O}_p(C)$, completing the proof.

Corollary 37.3.3: Rational Map of Curves

Let f be a rational map from C' to a projective curve C. Then the domain of f must include every simple point of C'. If C' is nonsingular, f is a morphism.

***Proof*:**
If F is not dominating, it is constant (as shown in corollary 40.2.4), hence its domain must be all of C. Thus, assume $F^{\#}$ embeds $K = \kappa(C)$ as subfield of $L = \kappa(C')$. Let P be a simple point of C', $R = \mathcal{O}_p(C')$. Then it is enough to show that $K \not\subseteq R$. Suppose that $K \subseteq R \subseteq L$ The L is a finite algebraic extension of K, so R is in fact a field. But DVR's are by definition *not* a field.

Corollary 37.3.4: Function Field and Morphism Correspondence

Let C be a projective curve, C' a nonsingular curve. Then there is a natural one-to-one correspondence between dominant morphisms $f : C' \to C$ and homomorphism $f^{\#} : \kappa(C) \to \kappa(C')$.

***Proof*:**
immediate

Corollary 37.3.5: Characterizing Nonsingular Projective Curves

Two nonsingular projective curves are isomorphic if and only if their function fields are isomorphic if and only if they are birationally equivalent.

***Proof*:**
immediate

Corollary 37.3.6: Function Field associated to Curve

Let C be a nonsingular projective curve over k, $K = \kappa(C)$. Then there is a natural one-to-one correspondence between the points of C and the discrete valuation rings of K, namely

$$p \in C \text{ correspond to } k \subseteq \mathcal{O}_p(C) \subseteq K$$

***Proof*:**
Certainly $\mathcal{O}_p(C)$ is a DVR in K. On the other hand if R is any such DVR, then we saw that R dominates a unique $\mathcal{O}_p(C)$, and as these are both DVR's of K, $R = \mathcal{O}_p(C)$, as we sought to show.

From this, notice that we can create the Zariski topology on the collection of DVRs: Let X be the set of all DVRS of $\kappa(C)/k$. Give the cofinite topology on X. Then the correspondence $p \mapsto \mathcal{O}_p(C)$ is a homeomorphism! We shall use this observation when looking at "smooth $\mathbb{Z}$-curves" in section 50.7 which shall how how to interpret Dedekind domains as smooth curves!

37.4 Normality and the Serre Conditions

Regularity implies normality (corollary 35.5.3), and in dimension one the implication reverses (proposition 35.5.2). The question is how far the reverse implication reaches. The answer is: exactly one codimension. A normal variety is smooth in codimension one, and no further.

Proposition 37.4.1: Normal Implies Regular in Codimension One

Let X be a normal variety and $p \in X$ a point whose closure has codimension 1 in X. Then $\mathcal{O}_p(X)$ is a discrete valuation ring, and in particular X is nonsingular at p.

***Proof*:**
The ring $\mathcal{O}_p(X)$ is a Noetherian local domain (proposition 33.2.10) of Krull dimension 1, since its dimension is the codimension of p in X by proposition 34.3.2. It is integrally closed, because X is normal and normality is local (proposition 37.1.2). A Noetherian local domain of dimension one that is integrally closed is a discrete valuation ring, and hence regular, by proposition 35.5.2. Regularity of the local ring is nonsingularity of the point by proposition 35.2.2, as we sought to show.

Corollary 37.4.2: A Normal Curve Is Smooth

A normal curve is nonsingular at every point. Consequently the normalization $\nu\colon \tilde{C} \to C$ of any curve is a smooth curve, and ν resolves every singularity of C.

***Proof*:**
Every point of a curve has codimension 1 in it, so proposition 37.4.1 applies at every point. The normalization $\tilde{C}$ is normal and is a curve, being birational to C (theorem 37.2.1(3)) and hence of the same dimension, completing the proof.

This is the structural payoff of the chapter, and it is what makes curves so much better behaved than surfaces. For a curve, "normal" and "smooth" are the same word, so a single algebraic operation, taking an integral closure, removes every singularity at once. Section 37.3 converts this into the statement that each birational class of curves contains exactly one smooth projective model.

In dimension two the two conditions come apart.

Example 37.4.3: A Normal Singular Surface

Let $\operatorname{char} k \neq 2$ and let $Q = \mathcal{Z}(xy - z^2) \subseteq \mathbb{A}^3_k$, the quadric cone. It is singular at the origin: the Jacobian of $xy - z^2$ is $(y,\ x,\ -2z)$, which vanishes at $(0,0,0)$, so by definition 35.2.1 the rank there is 0 rather than the required $3 - 2 = 1$.

Nonetheless Q is normal. Its coordinate ring is isomorphic to the subring $k[u^2, uv, v^2] \subseteq k[u,v]$ under $x \mapsto u^2$, $y \mapsto v^2$, $z \mapsto uv$, which is the ring of invariants of $k[u,v]$ under $(u,v) \mapsto (-u,-v)$. A ring of invariants of a normal domain under a finite group is normal: if w in the fraction field is integral over the invariants, it is integral over $k[u,v]$, hence lies in $k[u,v]$ by proposition 37.1.3, and it is invariant, so it lies in the invariant subring.

So Q is normal and singular, and its singular locus is a single point, of codimension 2. That is the smallest codimension proposition 37.4.1 permits.

The example is sharp, and it explains the shape of the general criterion. Normality controls codimension one and says nothing beyond it, so a full characterization needs a second condition governing the deeper codimensions. That condition is a statement about depth, and it is what Serre's criterion gives.

A Noetherian domain is integrally closed exactly when it satisfies two conditions, one asking regularity in codimension one and one asking a lower bound on depth. Write (R_1) for "$R_{\mathfrak{p}}$ is regular for every prime $\mathfrak{p}$ of height at most one" and (S_2) for "$\operatorname{depth} R_{\mathfrak{p}} \geq \min(2, \operatorname{height} \mathfrak{p})$ for every prime $\mathfrak{p}$". The statement that normality is their conjunction is *Serre's Criterion for Normality*, theorem 58.3.2; it runs on the theory of depth and regular sequences, which is developed there and not here.

The geometric content of the two halves is worth separating. Condition (R_1) is proposition 37.4.1 read backwards: it requires smoothness exactly in codimension one. Condition (S_2) says a function defined outside a closed set of codimension two extends across it, which is why a normal variety cannot be repaired by deleting a small set and gluing differently. The quadric cone of example 37.4.3 satisfies both: it is smooth away from a codimension-two point, and it is a hypersurface, which forces (S_2).

Read geometrically, the criterion says normality is precisely "smooth in codimension one, plus no missing codimension-two information". For curves the second condition is vacuous and the first

is everything, which recovers corollary 37.4.2. From dimension two onward both are needed, and normality becomes a genuinely weaker and more flexible condition than smoothness, which is why it is normality rather than smoothness that appears as a hypothesis throughout the theory of divisors in chapter 44.

37.5 Weil Divisors and the Class Group

Proposition 37.4.1 says that a normal variety is regular in codimension one, so at every codimension-one subvariety the local ring is a discrete valuation ring. That is exactly the hypothesis needed to make sense of the order of vanishing of a function along a subvariety, and with it the divisor theory of chapter 44 generalizes from curves to normal varieties of any dimension.

Definition 37.5.1: Prime Divisor and Weil Divisor

Let X be a normal variety. A *prime divisor* on X is an irreducible closed subvariety $Y \subseteq X$ of codimension one. A *Weil divisor* is a formal sum

$$D = \sum_{Y} n_Y \, Y \qquad n_Y \in \mathbb{Z}$$

over the prime divisors, with all but finitely many n_Y zero. They form a group $\operatorname{Div}(X)$.

For a curve a prime divisor is a point, and definition 44.1.1 is the case $\dim X = 1$.

Proposition 37.5.2: The Order Along a Prime Divisor

Let X be a normal variety and $Y \subseteq X$ a prime divisor. Then the local ring $\mathcal{O}_Y(X)$ of X along Y, that is the localization of $k[U]$ at the prime $\mathcal{I}(Y \cap U)$ for any affine open U meeting Y, is a discrete valuation ring with fraction field $k(X)$. Writing ord_Y for its valuation, every nonzero $f \in k(X)$ has $\operatorname{ord}_Y(f) = 0$ for all but finitely many Y.

***Proof*:**
The ring $\mathcal{O}_Y(X)$ is Noetherian and local, and it is a domain with fraction field $k(X)$, being a localization of a coordinate ring of X. Its dimension is $\operatorname{codim}_X Y = 1$ by proposition 34.3.2. It is normal, being a localization of a normal domain, as the sixth exercise of exercise set 37.5.1 shows. So proposition 35.5.2 applies through its equivalence of normality with being a discrete valuation ring.

For the finiteness, fix an affine open U and write $f = g/h$ with $g, h \in k[U]$. Then $\operatorname{ord}_Y(f) \neq 0$ forces $Y \cap U$ to lie in $\mathcal{Z}(g) \cup \mathcal{Z}(h)$, a proper closed subset of U, which has finitely many irreducible components of codimension one. Covering X by finitely many affine opens gives the claim, completing the proof.

Definition 37.5.3: Principal Divisor and the Class Group

For $f \in k(X)^*$ the *principal divisor* is $\operatorname{div}(f) = \sum_Y \operatorname{ord}_Y(f)\, Y$. The principal divisors form a subgroup $\operatorname{Prin}(X) \subseteq \operatorname{Div}(X)$, and the *class group* is

$$\operatorname{Cl}(X) = \operatorname{Div}(X)/\operatorname{Prin}(X)$$

Two divisors with the same class are *linearly equivalent*.

For a nonsingular projective curve this is $\operatorname{Pic}(C)$ of definition 44.3.1; the two names coexist because on a general variety the divisor class group and the group of line bundles are different objects, agreeing whenever X is nonsingular. The distinction is developed in [13, Divisor Class Group and Picard Group].

Example 37.5.4: Class Groups

1. *Affine space.* $\operatorname{Cl}(\mathbb{A}^n_k) = 0$. A prime divisor is a hypersurface $\mathcal{Z}(f)$ with f irreducible, by theorem 34.4.2, and $\operatorname{div}(f) = \mathcal{Z}(f)$; so every prime divisor is principal, and hence so is every divisor.

2. *Projective space.* $\operatorname{Cl}(\mathbb{P}^n_k) \cong \mathbb{Z}$, by degree. A prime divisor is $\mathcal{Z}(F)$ for an irreducible form F, and assigning it $\deg F$ gives a surjection $\operatorname{Div}(\mathbb{P}^n_k) \to \mathbb{Z}$. Its kernel is exactly the principal divisors: a rational function on $\mathbb{P}^n_k$ is a ratio F/G of forms of equal degree, so $\operatorname{div}(F/G) = \mathcal{Z}(F) - \mathcal{Z}(G)$ has degree zero, and conversely a degree-zero divisor $\sum n_i \mathcal{Z}(F_i)$ is $\operatorname{div}\big(\prod F_i^{n_i}\big)$.

3. *The quadric cone.* Let $X = \mathcal{Z}(xy - z^2) \subseteq \mathbb{A}^3_k$, which is normal by the fourth exercise of exercise set 37.5.1 although singular at the origin. Let $L = \mathcal{Z}(x, z) \subseteq X$ be the line through the vertex. Then L is a prime divisor, and

   $$\operatorname{div}(x) = 2L$$

   To see this, note $y \notin (x, z)$, so y is a unit in the local ring $\mathcal{O}_L(X)$ along L. The relation $xy = z^2$ then gives $x = z^2/y$, so the maximal ideal $(x, z)\mathcal{O}_L(X)$ is generated by z alone and $\operatorname{ord}_L(z) = 1$; hence $\operatorname{ord}_L(x) = 2\operatorname{ord}_L(z) - \operatorname{ord}_L(y) = 2$. No other prime divisor occurs, since $\mathcal{Z}(x) \cap X = L$ as a set. So $2L$ is principal but L is not, by proposition 36.4.3, and $\operatorname{Cl}(X) \cong \mathbb{Z}/2\mathbb{Z}$ generated by the class of L.

The last example is the point of the section. On a nonsingular variety every codimension-one subvariety is locally cut out by a single equation, which is theorem 36.4.2, so the class group there measures a global obstruction to patching those local equations together. On a singular normal variety the obstruction is already local, and Cl detects the singularity: the line L on the quadric cone is not the zero set of any single function near the vertex, by proposition 36.4.3, which is what $\operatorname{div}(x) = 2L$ records.

Exercise 37.5.1

1. Let $A = k[x, y]/(y^2 - x^3)$ be the coordinate ring of the cuspidal cubic and put $t = y/x$ in $\operatorname{Frac}(A)$. Show that t is integral over A but does not lie in A, so A is not normal, and show

that $A[t] = k[t]$. Conclude that the normalization of the cuspidal cubic is $\mathbb{A}^1_k$.

2. Show that $\mathbb{Z}[\sqrt{-3}]$ is not integrally closed in its fraction field by exhibiting an element of $\mathbb{Q}(\sqrt{-3})$ that is integral over it but not in it. Which ring is its integral closure?

3. Let $A \subseteq B$ be an integral extension of domains with $\operatorname{Frac}(A) = \operatorname{Frac}(B)$. Show that if A is normal then $A = B$. Deduce that the normalization map of theorem 37.2.1 is an isomorphism exactly when the variety is already normal.

4. Show that the quadric cone $\mathcal{Z}(xy - z^2) \subseteq \mathbb{A}^3_k$ is normal but singular at the origin, and explain why this does not contradict corollary 37.4.2. Which of Serre's two conditions in theorem 58.3.2 is doing the work?

5. Let $C = \mathcal{Z}(y^2 - x^2 - x^3) \subseteq \mathbb{A}^2_k$ be the nodal cubic. Using the parameterization $t \mapsto (t^2 - 1, t(t^2 - 1))$ of example 33.3.8, show that $k[C]$ is not normal and that its normalization is $k[t]$. How many points of the normalization lie over the node, and why is that different from the cuspidal case?

6. Show that a localization of a normal domain is normal, and use this together with proposition 37.1.2 to show that normality of a variety may be checked on any affine open cover.

7. Give an example of a birational morphism of affine varieties that is bijective on points but not an isomorphism. (Chapter 47 will give them systematically.)

8. Let C be an irreducible curve with function field $K = k(C)$. Show that a discrete valuation ring R with $\operatorname{Frac}(R) = K$ and $k \subseteq R$ determines at most one point of any nonsingular projective model of C, and identify the valuation ring attached to the point at infinity of $\mathbb{P}^1_k$.

Part VIII

Projective Varieties

The affine theory of Part VI is incomplete in two ways that turn out to be the same way. A rational function need not be defined everywhere, and two curves of degrees m and n need not meet in mn points. Both failures are failures of points to exist, and both are repaired by the same construction: adjoin a point for every direction in which something can run off to infinity.

The resulting space is projective space, and the varieties inside it are the subject of this Part. The affine dictionary carries over almost unchanged once polynomials are replaced by homogeneous ones, but the geometry is genuinely better behaved: projective varieties are complete, so the image of a regular map out of one is closed, and the only regular functions on one are the constants. Those two facts drive everything in Part IX.

38

Projective Space and Homogeneous Ideals

This chapter builds projective space and transplants the dictionary of chapter 32 onto it. The transplant is not free: a polynomial is not a function on projective space, and the zero set of one is well defined only when the polynomial is homogeneous. Working out what replaces the coordinate ring, and which ideals the Nullstellensatz now describes, occupies the chapter.

38.1 Points at Infinity

So far, all of the algebraic sets were called *affine* algebraic sets, as they were all a subset of $\mathbb{A}^n_k$. These offer great geometrical intuition, however they are lacking in certain algebraic qualities, namely rational functions need not be defined at all points, and not all algebraic curves intersect. As an example of the former point, it is simplest to resort to an analogy from calculus. The reader may recall that the function $f : \mathbb{R} \to \mathbb{R}$ defined as $f(x) = 1/x$ is famously undefined at $x = 0$, as we cannot divide by 0.

However, we can enlarge $\mathbb{R}$ to make this function well-defined by adding a *point at infinity*. Namely, we may take $\mathbb{R}_\infty = \mathbb{R} \cup \{\infty\}$ where (for the sake of limits)[1] we extend the arithmetic of $\mathbb{R}$ to $\mathbb{R}_\infty$ by doing:

$$a + \infty = \infty + a = \infty \qquad b \cdot \infty = \infty \cdot b = \infty$$

where $a \in \mathbb{R}$ and $0 \neq b \in \mathbb{R}_\infty$. We then say that if (x_n) diverges, then

$$\lim_{n\to\infty} x_n = \infty$$

[1]The arithmetic defined here certainly does not satisfy the axioms of a ring; instead it is a structure called a *wheel*; we shall not study these in this textbook

In this case we now have that the function $1/x$ has a well-defined value of ∞ at 0, and even better under the right frame-work (provided in differential geometry), the function $f(x) = 1/x$ can be shown to be smooth on $\mathbb{R}_\infty$. In this way, we have ensured that we cannot have an undefined rational polynomials on $\mathbb{R}_\infty$! The space $\mathbb{R}_\infty$ is called the *projective line*. This "closure" on the set of definable rational polynomials makes the projective line an algebraically nicer space to work with, in a similar way that $\mathbb{C}$ is the better space to work in as all polynomials have roots.

For the latter interpretation (the one about there always being an intersection), consider a polynomial $f(z)$ defined over $\mathbb{C}$ so that there is no worry about roots not existing. Let us regard $\mathbb{C}$ as $\mathbb{R}^2$ with coordinates x, y so that $f(z) = f(x, y)$. Consider the line $L_{(a,b)}$ which has angle α given by (a, b):

$$L_{(a,b)} : t \mapsto (at, bt)$$

Then either $f = L$, in which case their intersection is an entire line, or f and $L_{(a,b)}$ intersect where these two equations agree:

$$f(at, bt) = f_n(a, b)t^n + \cdots + f_1(a, b)t + f_0(a, b)$$

where $f_n(a, b)$ represents the constant in front of the t-term. if $f_n(a, b) \neq 0$ then there are n roots, and hence n points of intersections. However, if $f_n(a, b) = 0$, then there must be a smallest m where

$$f_n(a, b) = 0,\ f_{n-1}(a, b) = 0,\ \cdots f_{m+1}(a, b) = 0,\ f_m(a, b) \neq 0$$

or else $f = L_{(a,b)}$, which we are taking to not be the case. But then we would have a number of intersections lower than the number of roots. There is a remedy to this, which is to consider the remaining $(n-m)$ points to be the intersection of L with f at a point at infinity. To see this, consider the substitution $s = 1/t$. Then:

$$f_n(a, b) + f_{n-1}(a, b)s + \cdots + f_0(a, b)s^n = 0$$

Notice that if $f_n(a, b) \neq 0$, then at $s = 0$ (conceptually can be thought of as $1/t = 0$) there is no root. But if there are $n - m$ leading terms that are zero, then this polynomial has a root of order $n - m$ at $s = 0$. Thus, we recover the intersection of L with f as an invariance! In particular, for each line $L_{(a,b)}$ we can think of there being an extra point at infinity. Notice that by combining the coordinates s, t we get a function:

$$f_n(a, b)t^n + f_{n-1}t^{n-1}s + \cdots + f_0(a, b)s^n = 0$$

which allows us to find all points of intersections at once. This motivates the use of homogeneous functions and the linear equivalence construction that shall be at the start of this section.

Why is the space called projective? This is understood from the following construction of projective space that extends to higher dimensions. Let us start in one dimension. We may define $\mathbb{R}_\infty$ as the

$$\mathbb{R}\mathrm{P}^1 := \frac{\mathbb{R}^2 \setminus \{(0, 0)\}}{\{(x, y) \sim (\lambda x, \lambda y), \forall \lambda \in \mathbb{R} \setminus \{0\}\}}$$

by taking the representative of each equivalence class to have norm 1, notice that we may associate all the points of $\mathbb{R}\mathrm{P}^1$ to S^1, and we can associate points of $\mathbb{R}$ with the equivalence class where $y \neq 0$. The equivalence class $[(\lambda x, 0)]$ can be thought of as the "point at infinity" that we have added, hence we may think of $\mathbb{R}\mathrm{P}^1$ as

$$\mathbb{R}\mathrm{P}^1 = \mathbb{R}^1 \sqcup \mathbb{R}^0 \tag{38.1}$$

The term "projective" comes from the idea that parallel lines will meet at the "point at infinity". In terms of "closure" that we talked about earlier, the reader may recall that in classical geometry, two non-parallel lines will always have a solution. In $\mathbb{R}\mathrm{P}^1$, we have added the extra property that there is one point at which parallel lines meet; they also have a solution. In terms of linear algebra, every system of linear equations has a solution.

We may extend this further, and take $\mathbb{R}^2$ and add "points at infinity". In this case, there are many possible pairs of parallel lines. We may consider that up to scaling, we have many new points that we may add. Formally, let:

$$\mathbb{R}\mathrm{P}^2 := \frac{\mathbb{R}^3 \setminus \{(0,0,0)\}}{\{(x,y,z) \sim (\lambda x, \lambda y, \lambda z), \forall \lambda \in \mathbb{R} \setminus \{0\}\}}$$

We may imagine that this insures that any rational function in two variables always has a solution. Adding multiple points at infinity insures that the function $1/y$, $1/x$, $1/xy$ and so forth are all considered distinct when evaluating ($1/y$ is zero when evaluated at one infinity but not another). In terms of parallel lines, we may think that parallel lines in any angle will have a unique solution (note that the distance between the lines does not matter, they still "meet" at the same point at infinity). The shape $\mathbb{R}\mathrm{P}^2$ can be thought of as $\mathbb{R}^2$ with a circle of points at infinity added where opposites are glued. Can the reader use this intuition to generalize (38.1) to:

$$\mathbb{R}\mathrm{P}^2 = \mathbb{R}^2 \sqcup \mathbb{R}^1 \sqcup \mathbb{R}^0$$

The reader familiar with differential geometry will know that $\mathbb{R}\mathrm{P}^2$ is a two dimensional smooth manifold, and is one of the simplest example of a shape that is 2-dimensional but cannot be embedded in 3-dimensions without self-intersection. The following image from Wikipedia may help in trying to visualize (note that this is an *immersion*, meaning it is an approximation of the shape by embedding it in a space in which there is not enough dimensions to visualize it without intersection)




Figure 38.1: Wikipedia: Immersion of $\mathbb{R}\mathrm{P}^2$

We may continue this process and define $\mathbb{R}\mathrm{P}^n$, or more generally $\mathbb{P}^n_k$ for some field k. These shall have a larger class of functions that we may define on them (we shall eventually say that there are an "ample" amount of function[2]). Thus, we shall treat $\mathbb{P}^n_k$ as an extension of $\mathbb{A}^n_k$, and consider the equivalence classes of $\mathbb{P}^n_k$ as *points*.

An important technicality that we may encounter is that we must convert a function that is defined on $\mathbb{A}^n_k$ to a function defined on $\mathbb{P}^n_k$, namely the points of $\mathbb{P}^n_k$ are now equivalence relations and hence a function whose domain is $\mathbb{P}^n_k$ must be independent of representative. This shall form an important class of rings that are "good representatives" to extend polynomials to $\mathbb{P}^n_k$. As we are extending results from $\mathbb{A}^n_k$, this class of rings shall have a similar dictionary as that provided between affine varieties and radical ideals of coordinate rings, namely we shall show that polynomials solutions over $\mathbb{P}^n_k$ shall correspond to *graded ideals* of *graded rings*.

[2]More technically speaking, we shall say that $\mathbb{P}^n_k$ has *ample line bundles*, a notion belonging to scheme theory

38.2 Projective Space and Homogeneous Polynomials

Let us first formally define projective space

Definition 38.2.1: Projective Space

Let k be a field. Then *projective space* over k of dimension n is:

$$\mathbb{P}_k^n = \frac{k^{n+1} \setminus \{0\}}{x \sim \lambda x \text{ for all } \lambda \in k^\times}$$

The points of $\mathbb{P}_k^n$ are often denoted $[x_1 : x_2 : \cdots : x_{n+1}]$.

The first thing we must do is define the topology on this space which parallels the Zariski topology on $\mathbb{A}_k^n$. Polynomial functions need not give well-defined zero sets on projective space, for example $f(x, y) = x^2 + y$ does not map two elements in the same equivalence class to zero. We must limit to polynomials that maps the representatives of an equivalence class to the same point. These are precisely the homogeneous polynomials:

Definition 38.2.2: Homogeneous Polynomial (Algebraic Form)

Let $f \in k[x_1, \ldots, x_n]$ be a polynomial. Then f is a *homogeneous polynomial* of degree d, or an *algebraic d-form*, if every monomial occurring in f has total degree d. Equivalently, as a formal identity in $k[x_1, \ldots, x_n, \lambda]$,

$$f(\lambda x_1, \ldots, \lambda x_n) = \lambda^d f(x_1, \ldots, x_n)$$

The identity is the useful form, and it is the reason homogeneous polynomials have well defined zero sets in projective space. It characterizes homogeneity only when read formally, or when k is infinite: over $\mathbb{F}_2$ the only scalar available is $\lambda = 1$, so the identity holds vacuously for every f.

The term *algebraic form* is a bit out-dated, but is often still used for the degree two case, where such algebraic forms are called *quadratic forms*. This condition extends to a more general class of functions. The reader comfortable with some analysis will see in exercise set 38.5.1 that any (at least) d-times differential degree d homogeneous function is in fact a homogeneous polynomial[3].

Example 38.2.3: Homogeneous Polynomials

For example:

1. $f(x, y, z) = x^3 + xy^2 - 2y^3$ is homogeneous
2. $f(x, y) = x^2 + y^3$ is not homogeneous

Notice that if $f_1, ..., f_n$ are all homogeneous polynomial of the same degree k, then $(f_1 + ... + f_n)^m$ is a homogeneous polynomial of degree mk. Hence, homogeneous polynomials behave well under addition and multiplication.

[3] homogeneity does not imply differentiability or continuity, can you think of a counter-example?

If $(a_1, ..., a_n) \in k^n$ is a solution to a homogeneous polynomials, then all points on the line passing through this point and the origin is also a solution, hence homogeneous polynomials are the "natural" polynomials for the zero set of projective space, as projective space is an equivalence relation on lines. It is tempting conclude the collection of homogeneous polynomials form the set $k[\mathbb{P}^n_k]$ where the set is either equal to $\text{Hom}_{\mathbf{Reg}}(\mathbb{P}^n_k, \mathbb{A}^1_k)$ or $\text{Hom}_{\mathbf{Reg}}(\mathbb{P}^n_k, \mathbb{P}^1_k)$ and we get the same theory as with affine spaces. However, neither of these sets is the collection of homogeneous polynomials. If we consider $\text{Hom}_{\mathbf{Reg}}(\mathbb{P}^n_k, \mathbb{P}^1_k)$, we have the problem that $[0:0] \notin \mathbb{P}^1_k$ and so we lose the fundamental property that the topology is defined by the zero-sets. The reader can further check that if $f : \mathbb{P}^n_k \to \mathbb{A}^1_k$ is homogeneous, then extending to $\mathbb{P}^1_k$ by mapping to $[f(x_1, ..., x_n) : 1]$ is not well-defined[4] (we shall see that $\mathbb{A}^1_k$ is dense in $\mathbb{P}^1_k$ and the given extension is the *only* continuous extension, and it does not work).

For the first option; even when $n = 1$ there is a problem of well-definedness. Consider $f : \mathbb{P}^1_k \to \mathbb{A}^1_k$ given by $f([x : y]) = f\left(\left[\frac{x}{y} : 1\right]\right) = \frac{x}{y}$, i.e. the closest we can do to define the identity. The reader may immediately see the problem: when $y = 0$, x/y is not defined (the codomain is $\mathbb{A}^1_k$). Even if we "ignore" this problem by simply not considering where $y = 0$, we have that f is no well-defined:

$$\frac{x}{y} = f\left(\left[\frac{x}{y} : 1\right]\right) = f([x : y]) = f\left(\left[1 : \frac{y}{x}\right]\right) = 1$$

But then f is not well-defined as it is not the case that for all $x, y \in k$, $x/y = 1$. If we instead try $f([x : y]) = xy$ then

$$xy = f([x : y]) = f\left(\left[\frac{x}{y} : 1\right]\right) = \left(\frac{x}{y}\right) \cdot 1 = \frac{x}{y}$$

but it is not always the case that $xy = \frac{x}{y}$ (ex. let $x = y = 2$), and hence it is once again not well-defined. The reader shall find that any such attempt to define a (non-constant) polynomial shall not be well-defined, namely since $f(\lambda x, \lambda y) \neq f(x, y)$.

This may unsettle the reader, as a "regular function" cannot be well-defined unless the polynomial is constant. As it turns out, we cannot extend (non-constant) polynomials from affine space to projective in a well-defined manner (see section 39.1) unless it is a constant, which the above exploration is a first demonstration on why this is the case.

However, we will be able to treat homogeneous polynomials as regular functions whenever we limit to one of the variables x_i to be nonzero. In particular, if $f \in k[x_1, ..., x_{n+1}]$ is homogeneous, and $x_i \neq 0$, then we can interpret f to be a regular function on $U_i = \{x \in \mathbb{P}^n_k \mid x_i \neq 0\}$:

$$f([x_1 : ... : x_i : ... : x_{n+1}]) = f\left(\left[\frac{x_1}{x_i} : ... : 1 : ... : \frac{x_{n+1}}{x_i}\right]\right) = f(x'_1, ..., x'_{n+1})$$

where we write $x'_j = \frac{x_j}{x_i}$ as $x_i \neq 0$. Notice that since the ith position can be fixed to 1 by dividing by x_i, we have chosen a representative of this equivalence relation, which is why we dropped the square brackets in the above equation. For example, for the homogeneous polynomial $x \in k[x, y]$, when $y \neq 0$, we can think of it as defining the function:

$$f(x) = x$$

and when $x \neq 0$, we can think of it as defining the function:

$$f(y) = 1$$

[4]There shall be well-defined regular maps from $\mathbb{P}^n_k$ to $\mathbb{P}^1_k$, see section 39.4, but these are not extensions of affine regular maps

This mirrors how $f([x:y]) = f([x/y:1]) = f([x':1]) = x'$ and $f([x:y]) = f([1:y/x]) = f([1:y']) = 1$. Notice that it was important to define two functions and how each behaves when $y \neq 0$ and $x \neq 0$ respectively. If we want to recover the homogeneous polynomial that defined these functions but only defined it on $x \neq 0$, we see that the $y \neq 0$ case can be λx or simply λ for any nonzero λ, showing we require the function to be defined in both situations (we shall see that having the function defined for each $x_i \neq 0$ and is compatible via "transition mappings" is enough to recover the homogeneous polynomial).

This also means that homogeneous polynomials on $\mathbb{P}^n_k$ act less like functions and more like vector-fields which "locally" are given by functions (i.e. are "local trivializations"). For the reader familiar with Differential Geometry, they may recognize that this vocabulary is used to define *vector bundles*, and that homogeneous polynomials can be seen as the sections of this vector bundle. This is in fact exactly what is going on, but it is beyond the scope of this book to get into the details of this realization (see [13] for a full exploration).

For now, we shall use homogeneous polynomial to define the closed subsets of $\mathbb{P}^n_k$. To that end, let's examine ideals generate by homogeneous elements. For each $d \in \mathbb{N}$, we can take the collection of homogeneous polynomials $R_d \subseteq k[x_1, ..., x_{n+1}]$. Then these form a k-vector space (exercise set 38.5.1(1)). Furthermore, $R_d R_e \subseteq R_{d+e}$, and so these form an $\mathbb{N}$-graded algebra over $R_0 = k$ (recall section 25.3). By proposition 16.2.7 and a bit of work, we may consider $k[x_1, ..., x_{n+1}]$ as:

$$k[x_1, ..., x_{n+1}] = R_0 \oplus R_1 \oplus \cdots \oplus R_d \oplus \cdots$$

with the $\mathbb{N}$-graded structure given by homogeneity.

Definition 38.2.4: Projective Algebraic Set

Take $R \subseteq k[x_1, x_2..., x_{n+1}]$ with the homogeneous $\mathbb{N}$-graded structure. Let $I \subseteq R$ be a homogeneous ideal. Then a *projective algebraic set* is:

$$\mathcal{Z}_{\mathbb{P}}(I) = \{p \in \mathbb{P}^n_k \mid f(p) = 0,\ \forall f \in I\}$$

If it is clear from context, the $\mathbb{P}$ subscript will be omitted and it shall be written as $\mathcal{Z}(I)$.

Note that we could have taken an arbitrary homogeneous set $S \subseteq R$, and then taken the homogeneous closure ${}^h\langle S\rangle = I$. By proposition 16.2.9, we get that homogeneous ideals are closed under ideal addition, multiplication, intersection, and taking the radical:

$$I + J \qquad IJ \qquad I \cap J \qquad \sqrt{I}$$

Furthermore, to check that a homogeneous ideal I is prime, it suffices to check the condition $fg \in I$ iff $f \in I$ or $g \in I$ with homogeneous polynomials (see corollary 16.2.8). The addition can naturally be extended to arbitrary sums, allowing us to define the Zariski topology on $\mathbb{P}^n_k$ when focusing on the homogeneous ideals of a $k[x_1, ..., x_{n+1}]$:

Definition 38.2.5: Zariski Topology on Projective Space

Letting the projective algebraic sets to be the closed subsets of $\mathbb{P}^n_k$, we get the [projective] Zariski topology on $\mathbb{P}^n_k$.

The vanishing ideal transplants as well, once restricted to homogeneous elements.

Definition 38.2.6: Projective Vanishing Ideal

Let $V \subseteq \mathbb{P}_k^n$. Then $\mathcal{I}_{\mathbb{P}}(V)$ is the ideal generated by

$$\{f \in R \mid f \text{ homogeneous and } f(p) = 0 \text{ for all } p \in V\}$$

It is a homogeneous ideal by construction, and it is radical by the same argument as in the affine case.

Definition 38.2.7: Projective Coordinate Ring

Let $V \subseteq \mathbb{P}_k^n$ be a projective algebraic set. Then a *projective coordinate ring* is defined as:

$$\Gamma_{\mathbb{P}}(V) = k_{\mathbb{P}}[V] = \frac{R}{(\mathcal{I}_{\mathbb{P}}(V))}$$

where we drop the $\mathbb{P}$ subscript when unambiguous.

Calling these the coordinate ring is a little misleading as the elements are not functions on V, but the similar algebraic properties between affine and projective coordinate rings shall warrant this nomenclature.

With a topology, we may define all of the topological and geometric notion such as compactness, connectedness, dimension, irreducibility, and so forth. The irreducibility condition in projective space becomes a condition on homogeneous prime ideals, from which we define

Definition 38.2.8: Projective Variety

A *projective variety* is an irreducible projective algebraic set.

As mentioned in the introduction of this section, projective space and projective algebraic sets extend affine space. Let us now make this precise. Let us first consider an algebraic subset $V = \mathcal{Z}_{\mathbb{P}}(I) \subseteq \mathbb{P}_k^n$. Then as $\mathbb{P}_k^n = \mathbb{A}_k^{n+1}/\sim$, we see that we can consider $\mathcal{Z}_{\mathbb{A}}(I) \subseteq \mathbb{A}_k^{n+1}$:

Before turning to the cone, one family of projective varieties is worth classifying completely, because it can be done with linear algebra alone and because its members give most of the small examples in this book.

Definition 38.2.9: Quadric and Its Rank

A *quadric* in $\mathbb{P}_k^n$ is $\mathcal{Z}(Q)$ for a nonzero quadratic form $Q \in k[x_0, \dots, x_n]$. Assume $\operatorname{char} k \neq 2$ and write $Q(x) = x^\top A x$ for the unique symmetric matrix A. The *rank* of the quadric is the rank of A.

Proposition 38.2.10: Classification of Quadrics by Rank

Let $\mathrm{char} k \neq 2$. Every quadric of rank $r+1$ in $\mathbb{P}^n_k$ is carried by a linear change of coordinates to

$$\mathcal{Z}\left(x_0^2 + x_1^2 + \cdots + x_r^2\right)$$

and two quadrics are projectively equivalent if and only if they have the same rank. The singular locus of the quadric above is the linear subspace $\mathcal{Z}(x_0, \ldots, x_r)$, of dimension $n-r-1$, so the quadric is nonsingular exactly when $r = n$, that is when A is invertible.

***Proof*:**

A symmetric bilinear form over a field of characteristic $\neq 2$ admits an orthogonal basis, by the standard diagonalization; in that basis $Q = \sum_{i=0}^{r} \lambda_i x_i^2$ with all $\lambda_i \neq 0$ and $r+1$ the rank. Since k is algebraically closed each λ_i has a square root, and rescaling $x_i \mapsto x_i/\sqrt{\lambda_i}$ brings Q to $\sum_{i \leq r} x_i^2$. Rank is unchanged by an invertible linear substitution, since $A \mapsto T^\top A T$, so it is a projective invariant and two quadrics of equal rank are equivalent to the same normal form, hence to each other.

For the singular locus, $\partial Q/\partial x_i = 2x_i$ for $i \leq r$ and 0 otherwise, so by proposition 35.2.2 the singular points of $\mathcal{Z}(Q)$ are those with $x_0 = \cdots = x_r = 0$, which all lie on the quadric. That is the linear subspace $\mathcal{Z}(x_0, \ldots, x_r) \cong \mathbb{P}^{n-r-1}_k$, empty exactly when $r = n$, as we sought to show.

Example 38.2.11: Quadrics of Small Rank

Take $\mathrm{char} k \neq 2$ throughout.

1. *Rank* 1. $\mathcal{Z}(x_0^2)$ is a hyperplane doubled: the same point set as $\mathcal{Z}(x_0)$, but a different curve in the sense of definition 42.1.1, which is one reason that definition keeps the polynomial rather than its zero set.
2. *Rank* 2. $\mathcal{Z}(x_0^2 + x_1^2) = \mathcal{Z}\big((x_0 + ix_1)(x_0 - ix_1)\big)$ is a pair of distinct hyperplanes meeting in a $\mathbb{P}^{n-2}$, which is its singular locus.
3. *Rank* 3 *in* $\mathbb{P}^2_k$. A nonsingular conic. It is isomorphic to $\mathbb{P}^1_k$, by the projection computed in example 39.4.4(3), and this is the genus-zero case of theorem 44.4.2.
4. *Rank* 3 *in* $\mathbb{P}^3_k$. Singular along a point, namely $\mathcal{Z}(x_0, x_1, x_2) = [0:0:0:1]$. It is the cone over a nonsingular conic with that vertex, and it is the quadric cone of example 37.4.3 in projective form: normal, and singular at one point.
5. *Rank* 4 *in* $\mathbb{P}^3_k$. A nonsingular quadric surface. Example 40.1.2 identifies it with $\mathbb{P}^1_k \times \mathbb{P}^1_k$ under the Segre embedding, and its two rulings are the two families of lines on it.

So in $\mathbb{P}^3_k$ the quadrics come in exactly four projective equivalence classes, distinguished by a single integer.

38.3 The Affine Cone and Homogenization

Definition 38.3.1: Affine Cone

Let f be a homogeneous polynomial. Then its zero set in $\mathbb{A}^{n+1}$ is called an *affine cone*.

More generally, if $V \subseteq \mathbb{P}_k^n$ is a projective algebraic subset, then $C(V) \subseteq \mathbb{A}_k^{n+1}$ is the affine cone of V.

The cone translates the projective dictionary into the affine one, and the two directions are worth recording, since section 38.4 rests on them.

Proposition 38.3.2: Cone Identities

Let $\emptyset \neq V \subseteq \mathbb{P}_k^n$ be a projective algebraic set and let I be a homogeneous ideal with $\mathcal{Z}_{\mathbb{P}}(I) \neq \emptyset$. Then

$$\mathcal{I}_{\mathbb{A}}(C(V)) = \mathcal{I}_{\mathbb{P}}(V) \qquad C(\mathcal{Z}_{\mathbb{P}}(I)) = \mathcal{Z}_{\mathbb{A}}(I)$$

***Proof*:**

For the first, a point of $C(V) \subseteq \mathbb{A}^{n+1}$ is either the origin or a nonzero vector whose class lies in V. A homogeneous f vanishes on all of $C(V)$ exactly when it vanishes at every such vector, which is exactly when it vanishes at every point of V; and f automatically vanishes at the origin, since a homogeneous polynomial of positive degree has no constant term, while a nonzero constant vanishes nowhere on the nonempty V. Since both ideals are homogeneous, agreement on homogeneous elements gives equality.

For the second, $\mathcal{Z}_{\mathbb{A}}(I)$ is stable under scaling because I is homogeneous, so it is a union of lines through the origin together with the origin itself; the set of classes of its nonzero vectors is precisely $\mathcal{Z}_{\mathbb{P}}(I)$, and taking the cone recovers $\mathcal{Z}_{\mathbb{A}}(I)$. The hypothesis $\mathcal{Z}_{\mathbb{P}}(I) \neq \emptyset$ is what rules out the degenerate case where $\mathcal{Z}_{\mathbb{A}}(I)$ is the origin alone, as we sought to show.

Let us consider a concrete example. The affine cone of the (homogeneous) polynomial $x^2 + y^2 - z^2$ is the zero-set in $\mathbb{A}_k^{2+1}$ that looks like:




Figure 38.2: zero set of $x^2 + y^2 - z^2$

When $z \neq 0$, This equation in $\mathbb{P}^2_{\mathbb{R}}$ would resemble a circle, which we can see by intersecting the above zero-set with the plane $z = 1$, and hence the usual solution to $x^2 + y^2 = 1$ shall be in this zero set. By setting $z = 0$, we see that $x^2 + y^2 = 0$ if and only if $x = y = 0$, but $[0 : 0 : 0] \notin \mathbb{P}^2_k$, and so all the points of the zero-set $x^2 + y^2 - z^2 = 0$ are precisely the points given by lines passing through $x^2 + y^2 - 1 = 0$

Hence, we see that $x^2 + y^2 - z^2$ becomes the equation of a circle in projective space $\mathbb{P}^2_{\mathbb{R}}$. This matches how the circle has no points going "off to infinity", and so we should expect recovering the same set! However, if we instead consider $xy - z^2$, we see that when $z \neq 0$, we can take the plane where $z = 1$ and get the set $xy = 1$, which is the graph of $y = 1/x$. This has a point at infinity, and indeed if we let $z = 0$, we get the equation $xy = 0$ which is true if either x or y is zero (not that both x and y can both be zero as that would imply $[0 : 0 : 0] \in \mathbb{P}^2_{\mathbb{R}}$). Hence, we gained two additional points corresponding to the two direction the points go off to infinity (see example 38.3.4 for a visual).

The process by which we extend transform a polynomial to a homogeneous polynomial to extend the zero-set is given a name:

Definition 38.3.3: Homogenization

Let $f \in k[x_1, \dots, x_n]$ be a polynomial of degree d. Its *homogenization* is

$$f^*(x_1, \dots, x_{n+1}) = x_{n+1}^d \, f\left(\frac{x_1}{x_{n+1}}, \dots, \frac{x_n}{x_{n+1}}\right)$$

Clearing denominators shows f^* lies in $k[x_1, \dots, x_{n+1}]$ and is homogeneous of degree d. The exponent must be at least $\deg f$ for f^* to be a polynomial at all, and taking it equal to $\deg f$ is what makes f^* divisible by no power of x_{n+1}.

Conversely, a homogeneous $F \in k[x_1, \dots, x_{n+1}]$ is *dehomogenized* with respect to x_i by setting that variable to 1:

$$F_*(x_1, \dots, \widehat{x_i}, \dots, x_{n+1}) = F(x_1, \dots, x_{i-1}, 1, x_{i+1}, \dots, x_{n+1})$$

the hat marking the omitted variable. Unless said otherwise $i = n+1$. These two operations are written $(-)^*$ and $(-)_*$ throughout; the alternative f^* for f^* is not used.

Example 38.3.4: Homogenizing Polynomials

1. Take $x^2 + y^2 - 1$. Homogenizing (with degree 2) and labelling $x_3 = z$, we get $x^2 + y^2 - z^2$. If we homogenizing in degree n, we would get:

   $$z^{n-2}x^2 + z^{n-2}y^2 = z^n$$

   Homogenizing in a degree larger than $\deg f$ multiplies the result by a power of z, which adds the whole line $z = 0$ to the zero set. Those points are an artifact of the padding, so the convention is always to homogenize in degree exactly $\deg f$.

   An affine solution (x_0, y_0) with $x_0^2 + y_0^2 = 1$ becomes the projective point $[x_0 : y_0 : 1]$. For points at infinity, set $z = 0$ and solve $x^2 + y^2 = 0$. Over $\mathbb{R}$ the only solution is $x = y = 0$, which is not a point of $\mathbb{P}^2_{\mathbb{R}}$, so the real circle acquires nothing at infinity. *Over an algebraically closed field of characteristic* $\neq 2$ *this fails*, and that is the standing hypothesis of this book. Choosing i with $i^2 = -1$,

   $$x^2 + y^2 = (x + iy)(x - iy)$$

   so the circle meets the line at infinity in the two points

   $$[1 : i : 0] \qquad [1 : -i : 0]$$

   These are the *circular points at infinity*, and every circle in $\mathbb{P}^2_{\overline{k}}$ passes through both of them, whatever its centre or radius. The intuition that a circle is bounded and so gains nothing at infinity is an artifact of working over $\mathbb{R}$; the projective conic is a conic like any other, and chapter 43 counts its intersections accordingly.

2. Take $xy - 1$. Its shape looks like:




Figure 38.3: zero-set of $xy = 1$

Homogenizing, we get $xy - z^2$. A solution $x_0y_0 - 1 = 0$ in projective coordinates is of the form:

$$[x_0 : y_0 : 1]$$

setting $z = 0$, we can ask if there are any points where:

$$[x_0 : y_0 : 0]$$

is a solution. And indeed, if $x_0 = 0$ or $y_0 = 0$, we get a solution, since

$$0y_0 - 0 = 0 \qquad x_0 0 - 0 = 0$$

We can see by visualizing the zero set that there seems to be two extra point added at infinite, one for the y-axis and one for the x-axis (remember that opposite points are considered the same).

If we de-homogenize at x, we get $y - z^2 = 0$, equivalently $y = z^2$, and de-homogenizing at y we get $x - z^2 = 0$, equivalently $x = z^2$. In both of these cases, we see that $x = z = 0$ and $y = z = 0$ is a solution. Hence, by de-homogenizing at each variable, we can find the vanishing set of a homogeneous polynomial over projective space. This can be seen more clearly when looking at the affine cone of the homogenized polynomial:




Figure 38.4: affine cone: $xy - z^2$

3. Take $x^3 + xy^2 - 2y^3 - 1$. Its shape looks like:




Figure 38.5: $x^3 + xy^2 - 2y^3 = 1$

When homogenizing, the affine cone gives:




Figure 38.6: affine cone of $x^3 = xy^2 - 2y^3 = z^3$

are there any added points, and if so what are they?

4. Take $f(x) = x^2$. Its vanishing set is the single point 0. Then $f^*(x, x_\infty) = x^2$ is the degree 2 homogenization. Then this has a single zero, namely $[0:1]$, which correspond to the single root of x^2 in $\mathbb{A}^1_k$

5. Take $f(x, y) = x^2 - y$, whose zero set is the usual parabola. Its degree-2 homogenization in the variable z is $x^2 - zy$. Setting $z = 1$ recovers the affine points, which are

$$[x_0 : x_0^2 : 1] \qquad x_0 \in k$$

and setting $z = 0$ leaves $x^2 = 0$, so $x = 0$ and the only point at infinity is

$$[0:1:0]$$

in particular, we added a single point at infinity. This is the point where the parabola "meets". Notice that it was not that there was two points at infinite but just 1. The idea is that the "angle" with which the function approaches infinity tends towards $\pi/2$, and hence the edges of the graph shall meet at infinity. This shows that parabola's can be thought of as infinitely large ellipsoids[a].

Can the reader see different sorts of connections between circles, parabolas, ellipses, and hyperbolas through projective space?

[a] for those comfortable with some Riemann geometry, can the reader see why projective space can be thought of as having positive curvature?

Proposition 38.3.5: Properties of Homogenization

Let $F, G \in k[x_1, \dots, x_{n+1}]$ be homogeneous and $f, g \in k[x_1, \dots, x_n]$ arbitrary, with $(-)^*$ and $(-)_*$ taken at x_{n+1} as in definition 38.3.3. Then:

1. $(FG)_* = F_* G_*$ and $(fg)^* = f^* g^*$;
2. $(F+G)_* = F_* + G_*$; and writing $r = \deg f$, $s = \deg g$ and $u = \deg(f+g)$,
$$x_{n+1}^{r+s-u}\,(f+g)^* = x_{n+1}^{s} f^* + x_{n+1}^{r} g^*$$
3. if $F \neq 0$ and r is the largest power with $x_{n+1}^r \mid F$, then $x_{n+1}^r (F_*)^* = F$; in particular $(F_*)^* = F$ when $x_{n+1} \nmid F$.

***Proof*:**
Throughout write $z = x_{n+1}$ and use that dehomogenizing is the ring homomorphism $z \mapsto 1$.

1. Dehomogenization is a ring homomorphism, so $(FG)_* = F_* G_*$ is immediate. For the second, $\deg(fg) = \deg f + \deg g$ because k is a domain, and
$$(fg)^* = z^{\deg f + \deg g}(fg)\left(\tfrac{x_1}{z}, \dots\right) = z^{\deg f} f\left(\tfrac{x_1}{z}, \dots\right) \cdot z^{\deg g} g\left(\tfrac{x_1}{z}, \dots\right) = f^* g^*$$
2. Additivity of $(-)_*$ is again the homomorphism property. For the second identity, all three of $f^*, g^*, (f+g)^*$ arise from the same substitution $x_i \mapsto x_i/z$ scaled by different powers of z, namely z^r, z^s and z^u. Multiplying each by the power of z that brings it to the common exponent $r+s$ gives
$$z^{\,s} f^* + z^{\,r} g^* = z^{\,r+s}\,(f+g)\left(\tfrac{x_1}{z}, \dots\right) = z^{\,r+s-u}\,(f+g)^*$$
The correction $z^{\,r+s-u}$ is needed exactly when the top-degree terms of f and g cancel, so that $u < \max(r, s)$.
3. Write $F = z^r H$ with $z \nmid H$, so H is homogeneous of degree $\deg F - r$. Setting $z = 1$ gives $F_* = H_*$, and since $z \nmid H$ the polynomial H_* has degree exactly $\deg H$; homogenizing therefore returns $(H_*)^* = H$, whence $z^r (F_*)^* = z^r H = F$, as we sought to show.

Corollary 38.3.6: Factorization of Homogeneous Polynomials

Let $F \in k[x_1, \dots, x_{n+1}]$ be a homogeneous polynomial. Then up to a power of x_{n+1}, factorizing F is the same as factoring F_*.

In particular, if $F \in k[x, y]$, then F factors into a product of linear factors.

***Proof*:**
The first result is immediate from proposition 38.3.5. For the second, as we are asuming k is

algebraically closed in this section we get that F_* must factor into a product of lienar terms,

$$F_* = c\prod(x - \lambda_i)$$

Then by homogenizing we get:

$$F = cy^r \prod(x - \lambda_i y)$$

as we sought to show.

From this, we are justified in decomposing projective algebraic sets by their behaviour when dehomogenizing elements of the generating ideal:

Example 38.3.7: Zero Sets of Projective Space

Example 38.3.4 contained multiple examples of zero sets. All of those examples were from a single homogeneous polynomial.

1. Every point $[a_1 : \cdots : a_{n+1}] \in \mathbb{P}^n_k$ is a projective algebraic set. A point $[x_1 : \cdots : x_{n+1}]$ equals it exactly when

   $$(x_1, \ldots, x_{n+1}) = \lambda(a_1, \ldots, a_{n+1}) \qquad \text{for some } \lambda \neq 0$$

   that is, exactly when the two vectors are proportional, which holds exactly when each 2×2 minor of the matrix

   $$\begin{pmatrix} x_1 & x_2 & \cdots & x_{n+1} \\ a_1 & a_2 & \cdots & a_{n+1} \end{pmatrix}$$

   vanish, namely that

   $$\begin{vmatrix} x_i & x_j \\ a_i & a_j \end{vmatrix} = a_j x_i - a_i x_j = 0$$

   These are $\binom{n+1}{2}$ equations, of which n already suffice (one for each variable beyond a fixed nonzero coordinate). In other words, we get a point via linear homogeneous polynomials with the appropriate coefficients. This shows how "linear" projective space is. These equations can be thought of as the intersection of all the hyper-planes passing through $[a_0 : \cdots : a_n]$. Equivalently, if you know some differential geometry, it shows that we can view $\mathbb{P}^n_k$ as the Grassmannian $G(1, n+1)$.

   The coordinate ring associated to a point would be:

   $$\frac{k[x_1, \ldots, x_{n+1}]}{\langle a_j x_i - a_i x_j \,|\, 1 \leq i, j \leq n+1 \rangle} \cong k[x_{n+1}]$$

   That is, the coordinate ring is *not* just k at a single point! The reader may think of this as the grading condition for the coordinate rings.

2. In $\mathbb{P}^1_k$, the only closed sets are points, the empty set, and the entire space. We shall see why when we show that any closed subset of projective space can be restricted to a closed subset of affine space, in which these are the only possibilities

3. $\mathbb{P}^2_k$ has many more closed sets just like $\mathbb{A}^2_k$. Any line is given by $a_1x_1 + a_2x_2 + a_3x_3$ and any conic by $ax_1^2 + bx_1x_2 + cx_2^2 + dx_1x_3 + ex_2x_3 + fx_3^2$. A famous set of curves is the Fermat curves given by $x_1^n + x_2^n + x_3^n$. There are many more equations.

   To give one example of a coordinate ring, the coordinate ring for a line is isomorphic to $k[s, t]$ with $\deg(s) = \deg(t) = 1$.

4. In $\mathbb{P}^3_k$ the twisted cubic is cut out by three equations,

$$x_1x_3 - x_2^2, \quad x_1x_4 - x_2x_3, \quad x_2x_4 - x_3^2$$

and its homogeneous coordinate ring is

$$\frac{k[x_1,x_2,x_3,x_4]}{(x_1x_3 - x_2^2,\ x_1x_4 - x_2x_3,\ x_2x_4 - x_3^2)} \cong k[s^3, s^2t, st^2, t^3] \subseteq k[s,t]$$

the subring of $k[s,t]$ generated by the degree-three monomials. That isomorphism exhibits the parameterization $[s:t] \mapsto [s^3 : s^2t : st^2 : t^3]$, so the twisted cubic is a *rational* curve: it is the image of $\mathbb{P}^1$. What is notable about it is different: it needs three equations in $\mathbb{P}^3$ although its codimension is two, so it is not a complete intersection.

Another example in $\mathbb{P}^3_k$ are the quadratic surfaces given by $\sum_{i,j} a_{ij}x_ix_j$.

38.4 The Projective Nullstellensatz and Irrelevant Ideals

As we are considering the case where k is algebraically closed, we may naturally want the Nullstellensatz to apply between projective space and homogeneous polynomials. In particular, if $I \subseteq k[x_1, ..., x_n]$ then $Z(I) = \emptyset$ if and only if $I = (1)$. However, this is not the case:

Example 38.4.1: Nullstellensatz False in Projective Space

Let $\mathfrak{m} = (x_1, \ldots, x_{n+1})$, the ideal of all polynomials with zero constant term. Its affine zero set is the origin, and the origin is not a point of $\mathbb{P}^n_k$, so $\mathcal{Z}_{\mathbb{P}}(\mathfrak{m}) = \emptyset$ while $\mathfrak{m} \neq (1)$.

The same happens for every power: writing $\mathfrak{m}^s$ for the ideal generated by all monomials of degree s, its affine zero set is again just the origin, so $\mathcal{Z}_{\mathbb{P}}(\mathfrak{m}^s) = \emptyset$. So the projective Nullstellensatz cannot say "empty zero set implies the unit ideal"; the best it can say is "empty zero set implies the ideal contains some $\mathfrak{m}^s$", which is lemma 38.4.2.

Fortunately, the above ideals are the only ideals for which this could happen, namely because these ideals correspond to ideals that contain the origin in affine space:

Lemma 38.4.2: Characterizing Irrelevant Ideals

Let k be algebraically closed and let $I \subseteq k[x_1, \ldots, x_{n+1}]$ be a homogeneous ideal. Then $\mathcal{Z}_{\mathbb{P}}(I) = \emptyset$ if and only if $\mathfrak{m}^s \subseteq I$ for some $s > 0$, where $\mathfrak{m} = (x_1, \ldots, x_{n+1})$.

***Proof*:**

If $\mathfrak{m}^s \subseteq I$ then every x_i^s lies in I, so any point of $\mathcal{Z}_{\mathbb{P}}(I)$ has all coordinates zero, and $[0 : \cdots : 0]$ is not a point of $\mathbb{P}^n_k$. Hence $\mathcal{Z}_{\mathbb{P}}(I) = \emptyset$.

Conversely assume $\mathcal{Z}_{\mathbb{P}}(I) = \emptyset$. As $k[x_1, \ldots, x_{n+1}]$ is Noetherian, write $I = (f_1, \ldots, f_r)$ with each f_i homogeneous. Fix an index j and dehomogenize at x_j: the polynomials

$$(f_i)_* = f_i(x_1, \ldots, 1, \ldots, x_{n+1}) \qquad i = 1, \ldots, r$$

have no common root in $\mathbb{A}^n_k$, since a common root α would lift to the projective point obtained by inserting 1 in the jth slot, which would lie in $\mathcal{Z}_{\mathbb{P}}(I)$. By the weak Nullstellensatz (theorem 32.4.3) there are g_i with

$$\sum_{i=1}^{r} (f_i)_* \, g_i = 1$$

Homogenizing this identity and clearing denominators multiplies the right hand side by a power of x_j, giving $x_j^{m_j} \in I$ for some $m_j \geq 1$. Running the argument for each j produces exponents $m_1, \ldots, m_{n+1}$.

Put $m = \max_j m_j$ and $s = (n+1)(m-1)+1$. Any monomial $x_1^{a_1} \cdots x_{n+1}^{a_{n+1}}$ of total degree at least s must have some $a_j \geq m \geq m_j$, by the pigeonhole principle: were every $a_j \leq m-1$, the total degree would be at most $(n+1)(m-1) < s$. Such a monomial is therefore divisible by $x_j^{m_j} \in I$ and so lies in I. As $\mathfrak{m}^s$ is generated by the monomials of degree s, this gives $\mathfrak{m}^s \subseteq I$, as we sought to show.

Definition 38.4.3: Irrelevant Ideal

The ideal $\mathfrak{m} = (x_1, \ldots, x_{n+1}) \subseteq k[x_1, \ldots, x_{n+1}]$, consisting of the polynomials with zero constant term, is the *irrelevant ideal*. Its powers $\mathfrak{m}^s$ are the ideals generated by the monomials of degree s.

The name records the point of lemma 38.4.2: $\mathfrak{m}$ and its powers are precisely the homogeneous ideals invisible to projective space, so the projective correspondence must quotient them out. Note that $\mathfrak{m}^s$ and $(x_1^s, \ldots, x_{n+1}^s)$ are different ideals, though each contains a power of the other, which is all the lemma needs.

38.5 The Hilbert Function of a Projective Variety

An affine variety carries its coordinate ring, and dimension is read off from it as a Krull dimension. A projective variety carries a *graded* ring, and the grading holds more information than the dimension alone: counting how fast the graded pieces grow recovers the dimension, and the constant in front of that growth is a genuinely new invariant, the degree. This section extracts both, and the arithmetic genus that chapter 44 needs.

Throughout let $S = k[x_0, \ldots, x_n]$ with its grading by degree, $X \subseteq \mathbb{P}^n_k$ a projective variety, and $S(X) = S/\mathcal{I}_{\mathbb{P}}(X)$ its homogeneous coordinate ring, which inherits a grading because $\mathcal{I}_{\mathbb{P}}(X)$ is homogeneous.

Definition 38.5.1: Hilbert Function of a Projective Variety

The *Hilbert function* of X is

$$H_X : \mathbb{N} \to \mathbb{N} \qquad H_X(m) = \dim_k S(X)_m$$

the dimension over k of the degree-m graded piece of $S(X)$.

The definition is a count: $H_X(m)$ is the number of linearly independent forms of degree m on $\mathbb{P}^n$, modulo those vanishing on X. Equivalently it is the number of independent degree-m conditions X can impose. That it eventually behaves polynomially is Hilbert's theorem on graded modules.

Theorem 38.5.2: Hilbert Polynomial

There is a polynomial $h_X \in \mathbb{Q}[T]$, the *Hilbert polynomial* of X, and an integer m_0, such that

$$H_X(m) = h_X(m) \qquad \text{for all } m \geq m_0$$

Moreover $\deg h_X = \dim X$.

***Proof Key ideas*:**
Polynomiality is a statement about finitely generated graded modules over a polynomial ring and carries no geometric content, so it is cited rather than rebuilt: see *Commutative Algebra* [20, Hilbert Polynomial of a Graded Module], where it appears as the graded companion of the Hilbert-Samuel theory this book already cites in section 35.1. The argument is an induction on n, using the exact sequence obtained by multiplying by a variable.

That $\deg h_X = \dim X$ is the geometric half. Intersecting X with a general hyperplane drops the dimension by one (theorem 34.4.1) and drops the degree of the Hilbert polynomial by one, since $H_{X\cap H}(m) = H_X(m) - H_X(m-1)$ for large m and taking that difference lowers the degree of a polynomial by exactly one. Inducting until the dimension reaches zero, where the Hilbert polynomial is the constant counting points, matches the two numbers.

With polynomiality in hand, the leading coefficient is available to be named.

Definition 38.5.3: Degree and Arithmetic Genus

Let $X \subseteq \mathbb{P}^n_k$ be a projective variety of dimension d, so that h_X has degree d and its leading coefficient is c. The *degree* of X is

$$\deg X = d!\, c$$

and the *arithmetic genus* of X is

$$p_a(X) = (-1)^d \left(h_X(0) - 1\right)$$

The normalization by $d!$ is what makes $\deg X$ an integer and makes $\deg \mathbb{P}^d = 1$, as the first example below checks. Both invariants depend on the embedding $X \subseteq \mathbb{P}^n$ through the grading, not on X alone; a variety embedded two different ways can have two different degrees, which is why the degree of a curve is always quoted together with the projective space it sits in.

Example 38.5.4: Hilbert Polynomials

1. *Projective space.* $S(\mathbb{P}^n) = S$, and the monomials of degree m in $n+1$ variables number $\binom{m+n}{n}$, so
$$H_{\mathbb{P}^n}(m) = \binom{m+n}{n} = \frac{(m+n)(m+n-1)\cdots(m+1)}{n!}$$
This is already a polynomial in m of degree n with leading coefficient $1/n!$. So $\dim \mathbb{P}^n = n$

and $\deg \mathbb{P}^n = n! \cdot \frac{1}{n!} = 1$, and $h_{\mathbb{P}^n}(0) = \binom{n}{n} = 1$ gives $p_a(\mathbb{P}^n) = 0$.

2. *A hypersurface.* Let $X = \mathcal{Z}(F) \subseteq \mathbb{P}^n$ with F irreducible of degree e. Multiplying by F is injective on S and raises degree by e, so

$$H_X(m) = \binom{m+n}{n} - \binom{m-e+n}{n}$$

The two leading terms $m^n/n!$ cancel, leaving degree $n-1$ with leading coefficient $e/(n-1)!$. So $\dim X = n-1$ and $\deg X = e$: *the degree of a hypersurface is the degree of its equation.* This is the fact Bézout's theorem counts with, and it is the reason chapter 43 can speak of the degree of a plane curve without ambiguity.

3. *A plane curve.* Taking $n = 2$ in (2), a smooth plane curve of degree e has

$$h_X(T) = \binom{T+2}{2} - \binom{T-e+2}{2} = eT - \frac{e(e-3)}{2}$$

so $h_X(0) = -e(e-3)/2$ and

$$p_a(X) = (-1)^1 \left(-\tfrac{e(e-3)}{2} - 1\right) = \frac{(e-1)(e-2)}{2}$$

This is the *genus-degree formula.* Section 44.4 takes it as the definition of the genus and puts it to work, showing that it vanishes exactly for the curves isomorphic to $\mathbb{P}^1_k$. A line and a conic have genus 0, a smooth cubic has genus 1, which is why smooth plane cubics are exactly the curves chapter 45 finds a group law on.

4. *The twisted cubic.* From example 38.3.7, $S(X) \cong k[s^3, s^2t, st^2, t^3]$, whose degree-$m$ piece is spanned by the monomials of degree $3m$ in s, t, of which there are $3m+1$. So $h_X(T) = 3T+1$: dimension 1, degree 3, and $p_a = -(1-1) = 0$. It is a rational curve of degree 3 in $\mathbb{P}^3$, matching example 38.3.7(4).

Items (1) and (4) both describe a curve of genus 0, but with different degrees, 1 and 3. That is the embedding-dependence made concrete: the twisted cubic is abstractly isomorphic to $\mathbb{P}^1$, and the two are told apart by their Hilbert polynomials only because they sit in projective space differently.

Exercise 38.5.1

1. Let $R_d \subseteq k[x_1, \dots, x_n]$ be the space of homogeneous polynomials of degree d. Show that $\dim_k R_d = \binom{d+n-1}{n-1}$.

2. Let $T \colon \mathbb{A}^{n+1}_k \to \mathbb{A}^{n+1}_k$ be a linear isomorphism, inducing a map on $\mathbb{P}^n_k$, and let $V \subseteq \mathbb{P}^n_k$ be a subset with $V^T = T^{-1}(V)$.

   a) Show that V is a projective variety if and only if V^T is.

   b) Show that $V \cong V^T$, and that T induces an isomorphism of homogeneous coordinate rings $\Gamma_h(V) \cong \Gamma_h(V^T)$.

3. Let $V = \mathbb{P}^1_k$ with $\Gamma_h(V) = k[x, y]$ and set $t = x/y$. Show that $k(V) \cong k(t)$, and that the points of $\mathbb{P}^1_k$ correspond to the discrete valuation rings R with $\mathrm{Frac}(R) = k(V)$ and $k \subseteq R$. Which valuation ring belongs to the point at infinity?

4. Show that any two hyperplanes in $\mathbb{P}^n_k$ meet, for $n \geq 2$: if L_1, L_2 are nonzero linear forms then $\mathcal{Z}(L_1) \cap \mathcal{Z}(L_2) \neq \emptyset$. Then show the corresponding statement for two *lines* is true in $\mathbb{P}^2_k$ and false in $\mathbb{P}^3_k$, by exhibiting two disjoint lines there.

5. (Euler's relation) Let $\frac{\partial f}{\partial x_i}$ denote the formal partial derivative. Show that if $f \in k[x_0, \ldots, x_n]$ is homogeneous of degree d, then
$$df = \sum_{i=0}^{n} x_i \frac{\partial f}{\partial x_i}$$
It suffices to check both sides on a monomial, since both are k-linear.

6. Let $R = \bigoplus_{j \geq 0} R_j$ be a graded ring and write $1 = \sum_j r_j$ with $r_j \in R_j$. Show that r_0 is a multiplicative identity for R_0, and in fact that $1 = r_0$.

7. Show that $\mathcal{I}(\mathcal{Z}(I)) = \sqrt{I}$ fails for the irrelevant ideal of definition 38.4.3, and state the projective Nullstellensatz that repairs it.

8. Compute the Hilbert polynomial of the twisted cubic in $\mathbb{P}^3_k$ directly from definition 38.5.1, and check the degree and arithmetic genus against example 38.5.4(4).

9. Show that a homogeneous polynomial in two variables over an algebraically closed field factors into linear forms, and deduce corollary 38.3.6 for $n = 1$.

10. (Analysis aside, over $\mathbb{R}$.) Let $f \colon \mathbb{R}^n \to \mathbb{R}$ be d times continuously differentiable and homogeneous of degree d, meaning $f(\lambda v) = \lambda^d f(v)$ for all $\lambda > 0$. Show that f is a homogeneous polynomial of degree d. So for smooth enough functions, homogeneity in the scaling sense already forces homogeneity in the algebraic sense.

39

Quasi-Projective Varieties and Regular Maps

Projective space is covered by $n+1$ copies of affine space, and that single observation converts every local question about a projective variety into an affine one. This chapter develops the consequence: the class of varieties closed under both taking closed subsets and taking open subsets, the quasi-projective varieties, which contains the affine and the projective ones and is the setting in which the rest of the book works.

39.1 The Affine Cover of Projective Space

A common characterization of $\mathbb{P}^n_k$ is by showing that it can be constructed by gluing together $n+1$ copies of $\mathbb{A}^n_k$. Let $R = k[x_1, x_2, ..., x_{n+1}]$, and let H_i be the zero set of the (homogeneous) polynomial x_i for each i, giving us $H_1, H_2, ..., H_{n+1}$. These sets certainly cover $\mathbb{P}^n_k$ (their union is $\mathbb{P}^n_k$) and are closed as

$$H_i = \mathcal{Z}(x_i)$$

If we consider the map $\mathbb{A}^n_k \to \mathbb{P}^n_k$ mapping $(a_1, ..., a_n) \mapsto [1 : a_1 : \cdots : a_n]$, then the hyperplane H_{n+1} is called the *hyperplane at infinity*, being the hyperplane where $x_{n+1} = 0$ (it contains the points at infinity). For any hyperplane H_i, we have a map

$$H_i \to \mathbb{P}^{n-1}_k \qquad [a_1, ..., a_{i-1}, 0, a_{i+1}, ..., a_n] \to [a_1, ..., a_{i-1}, a_{i+1}, ..., a_n]$$

Once we define regular maps, the reader can verify that $H_i \cong \mathbb{P}^{n-1}_k$. Let

$$D(x_i) = U_i = \mathbb{P}^n_k - H_i$$

Then these sets are open and cover $\mathbb{P}^n_k$, as H_i is closed, and they contain all points where $x_i \neq 0$. Define a map:

$$\varphi_i \colon U_i \to \mathbb{A}^n_k \qquad [a_1 : \cdots : a_{n+1}] \mapsto \left(\frac{a_1}{a_i}, \ldots, \frac{a_{n+1}}{a_i} \right)$$

where we omit $\frac{a_i}{a_i}$. Notice how this is similar to de-homogenization. Verify that the map is well-defined, namely that it is independent of representative of points $U_i \subseteq \mathbb{P}^n_k$. Then:

Proposition 39.1.1: Projective Space Affine Cover

Let φ_i be defined as above. Then φ_i is a homeomorphism:

$$U_i \cong \mathbb{A}^n_k$$

***Proof*:**
First, φ_i is certainly a bijection: if

$$[x_1 : \cdots : 1_i : \cdots : x_n] = \varphi_i(x_1, ..., x_n) = \varphi(y_1, ..., y_n) = [y_1 : \cdots : 1_i : \cdots : y_n]$$

these two are equal if each $x_j = \lambda y_j$ for some $\lambda \in k$. Indeed, since $1_i = \lambda 1_i$, we must have $\lambda = 1$, which shows that $x_j = y_j$ for each coefficient, giving injectivity. For surjectivity, given any $[x_1, ..., x_i, ..., x_n]$ where $x_i \neq 0$, take:

$$[x_1 : \cdots : x_i : \cdots x_n] = \left[\frac{x_1}{x_i} : \cdots : 1_i : \cdots : \frac{x_n}{x_i} \right]$$

We now see that $(\frac{x_1}{x_i}, ..., \frac{x_n}{x_i})$ map to this point, giving surjectivity, and hence bijectivity.

For continuity, notice that $\varphi_i = \pi \circ \psi_i$ where $\psi_i : \mathbb{A}^n_k \to \mathbb{A}^{n+1}_k \setminus \{0\}$ is the natural embedding with ith-coordinate shifted by 1, and π is the projection. The map π is continuous as $\mathbb{P}^n_k$ is given the natural quotient from $\mathbb{A}^n_k$, and ψ_i is continuous as any pre-image of closed subsets of $\mathbb{A}^{n+1}_k \setminus \{0\}$ is given by the dehomogenization of the polynomials at the ith coordinate.

Furthermore, the map is open, since ψ_i is open (its image is a shifted-by-1 copy of $\mathbb{A}^n_k$, so any open set in $\mathbb{A}^n_k$ is open in $\mathcal{Z}(y_i - 1) \cap \mathbb{A}^{n+1}_k \setminus \{0\}$) and π is open since for any open subset $U \subseteq \mathbb{A}^{n+1}_k \setminus \{0\}$ the set

$$\bigcup_{\lambda \in k^*} \lambda U$$

is open, since the map $x \mapsto \lambda x$ is a homeomorphism (as is quickly verifiable). This is the pre-image of $\pi(U)$ and so since π is a quotient map we have that $\pi(U)$ is also open. Thus, the composition is open, making φ open.

Combining all the results, we get that φ_i is a homeomorphism, as we sought to show.

Given $H_i \cong \mathbb{P}^{n-1}_k$, this implies that we have a decomposition:

$$\mathbb{P}^n_k = \mathbb{A}^n_k \sqcup \mathbb{P}^{n-1}_k$$

For example, if $n = 2$, then:

$$\mathbb{P}^2_k = \mathbb{A}^2_k \sqcup \mathbb{P}^1_k$$

For this reason, we often think of $\mathbb{P}^2_k$ to be $\mathbb{A}^2_k$ along with a "line at infinity" (the reader should take the time to internalize this idea). This decomposition can be extended further, breaking down $\mathbb{P}^{n-1}_k$ into an affine and projective space. Repeating inductively, we get:

$$\mathbb{P}^n_k = \mathbb{A}^n_k \sqcup \mathbb{A}^{n-1}_k \sqcup \cdots \sqcup \mathbb{A}^1_k \sqcup \mathbb{A}^0_k$$

Another "immediate" result from our above discussion is that projective space $\mathbb{P}^n_k$ can be covered with $n+1$ copies of $\mathbb{A}^n_k$. This shall become the dominant way of viewing projective space in modern algebraic geometry (similar to how smooth manifolds are viewed as patches of euclidean space glued together), making this result important enough to be a theorem:

Theorem 39.1.2: Projective Variety Affine Cover

Let $Y \subseteq \mathbb{P}^n_k$ be a projective algebraic set. Then the sets $Y \cap U_i$, $1 \leq i \leq n+1$, form an open cover of Y, and each one is isomorphic to an *affine* algebraic set in $\mathbb{A}^n_k$.

***Proof*:**
The U_i cover $\mathbb{P}^n_k$, since a point has some nonzero coordinate, so the $Y \cap U_i$ cover Y and are open in Y. Fix i and identify U_i with $\mathbb{A}^n_k$ by the homeomorphism φ_i of proposition 39.1.1.

Let $Y = \mathcal{Z}_{\mathbb{P}}(F_1, \ldots, F_r)$ with each F_j homogeneous. Under φ_i a point of U_i is the class of a vector whose ith coordinate is 1, and F_j vanishes there exactly when its dehomogenization $(F_j)_*$ at x_i vanishes at the corresponding point of $\mathbb{A}^n_k$. Hence

$$\varphi_i(Y \cap U_i) = \mathcal{Z}_{\mathbb{A}}\big((F_1)_*, \ldots, (F_r)_*\big)$$

an affine algebraic set. Conversely φ_i^{-1} carries that set back, so the two are isomorphic, as we sought to show.

The content is the second clause: it is not just that Y is covered by sets homeomorphic to open subsets of $\mathbb{A}^n$, but that each piece is a genuine affine algebraic set with its own coordinate ring. Every local question about a projective variety can therefore be answered affinely, which is the working method for the rest of the book.

For the reader's awareness, we box the following[1]:

[1] this shall be the transition maps to verify the gluing is well-defined

Corollary 39.1.3: Transition Between Affine Cover

For $i \neq j$ the two charts agree on the overlap: the composite

$$\varphi_{ij} = \varphi_j \circ \varphi_i^{-1} \colon \varphi_i(U_i \cap U_j) \to \varphi_j(U_i \cap U_j)$$

is an isomorphism of affine varieties, given in coordinates by:

$$\begin{aligned}(x_1, ..., \hat{x_i}, ..., x_{n+1}) &\mapsto [x_1, ..., x_{i-1}, 1, x_{i+1}, ..., x_{n+1}] \\ &\mapsto \left[\frac{x_1}{x_j}, ..., \frac{x_{i-1}}{x_j}, \frac{1}{x_j}, \frac{x_{i+1}}{x_j}, ..., \frac{x_j}{x_j} ..., \frac{x_{n+1}}{x_j}\right] \\ &\mapsto \left(\frac{x_0}{x_j}, ..., \frac{x_{i-1}}{x_j}, \frac{1}{x_j}, \frac{x_{i+1}}{x_j}, ..., \hat{1}_j ..., \frac{x_{n+1}}{x_j}\right)\end{aligned}$$

where the hats mark omitted variables, and $i < j$ is assumed without loss of generality.

***Proof*:**
On $U_i \cap U_j$ both x_i and x_j are nonzero, so each displayed coordinate is a ratio with nonvanishing denominator and the composite is regular. Reversing the roles of i and j gives φ_{ji}, and $\varphi_{ji} \circ \varphi_{ij} = \mathrm{id}$ because both sides come from the identity on $U_i \cap U_j$. So φ_{ij} is an isomorphism, completing the proof.

39.2 Projective Closure

Let us now formalize extending closed sets of $\mathbb{A}^n_k$ to $\mathbb{P}^n_k$, and conversely restrict closed sets of $\mathbb{P}^n_k$ to any $U_i \cong \mathbb{A}^n_k$. Let us first take a closed subset $V \subseteq \mathbb{P}^n_k$, and consider its restriction to $U_i \cong \mathbb{A}^n_k$. As $U_i = D(x_i)$ is open, $V \cap U_i = W_i$ is open in V (the subspace topology on U_i and the Zariski topology transported by φ_i agree). Let us show that W_i is closed in $U_i \cong \mathbb{A}^n_k$, that is it is the zero set of the appropriate polynomials. If $f_1, \ldots, f_r$ are the homogeneous polynomials defining V[2] so that

$$f_1 = \cdots = f_n = 0$$

with $\deg f_i = n_i$, then on U_i each f_j is converted to:

$$x_i^{n_j} f_j \left(\frac{x_1}{x_j}, ..., 1_j, ..., \frac{x_{n+1}}{x_j}\right)$$

For example $f(x, y, x_3) = xy - x_3^2$ would be converted to $xy - 1$ in U_3. Then we can see that $V = \cup W_i$, that is each V can be covered by closed subsets from each U_i.

Conversely, if $W \subseteq \mathbb{A}^n_k$ is a closed subset, we may take the closure in $\mathbb{P}^n_k$, $\overline{W}$, which is the intersection of all closed sets containing W where we interpret W as being set in one of the U_i's. Some closed W are also closed in $\mathbb{P}^n_k$. For example $x^2 + y^2 - 1$ over $\mathbb{C}[x, y]$ when embedded becomes the zero set of $x^2 + y^2 - z^2$ whose points are $[x_0 : y_0 : 1]$ with $x_0^2 + y_0^2 = 1$, together with the two circular points at

[2]Recall that we are working over Noetherian rings, and hence each ideal is finitely generated

infinity of example 38.3.4. On the other hand, if we take $xy - 1$ and consider $xy - z^2$, we get that the traditional zero's become:

$$\left[a : \frac{1}{a} : 1\right]$$

and we now get a new 0 when $z = 0$ giving two more points:

$$[1 : 0 : 0] \qquad [0 : 1 : 0]$$

which we can think of as adding the two points at infinity of the graph of $y = 1/x$. Another example would be $y - x^2$. When extending to $\mathbb{P}^2_k$, we get $yz - x^2$. By setting $x = 0$, we get that $y = 0$ is a solution (which already exists in $\mathbb{A}^2_k$) as well as the new solution:

$$[0 : 0 : 1]$$

which is a new point at infinity that makes the parabola shape akin to an infinite ellipse.

Summarizing our discussion and the pertinent consequences:

Proposition 39.2.1: Closure of Affine Variety

Let $I \subseteq k[x_1, ..., x_n]$ be a (not necessarily homogeneous) ideal, $I^* = \{f^* \mid f \in I\}$, $V^* = \mathcal{Z}(I^*) \subseteq \mathbb{P}^n_k$. Take the last coordinate of $\mathbb{P}^n_k$ to be the coordinate at infinity, so that $\mathbb{A}^n_k$ embeds in $\mathbb{P}^n_k$ via $\iota_{n+1} \colon \mathbb{A}^n_k \xrightarrow{\sim} U_{n+1} \subseteq \mathbb{P}^n_k$. Let $(-)_*$ be the dehomogenization operation so that if $V = \mathcal{Z}(J) \subseteq \mathbb{P}^n_k$, then $I_* = \{f_* \mid f \in J\}$ where f_* is the dehomogenization at the coordinate at infinity, and $V_* = \mathcal{Z}(I_*)$. Let H_∞ represent the hyperplane at infinity (i.e. $\mathcal{Z}(x_{n+1})$). Then:

1. $\iota_{n+1}(V) = V^* \cap U_{n+1}$
2. $(V^*)_* = V$
3. If $V \subseteq W \subseteq \mathbb{A}^n_k$, then $V^* \subseteq W^* \subseteq \mathbb{P}^n_k$
4. If $V \subseteq W \subseteq \mathbb{P}^n_k$, then $V_* \subseteq W_* \subseteq \mathbb{A}^n_k$
5. If V is irreducible in $\mathbb{A}^n_k$, then V^* is irreducible in $\mathbb{P}^n_k$
6. If $V = \cup_i V_i$ is the irreducible decomposition of V in $\mathbb{A}^n_k$, then $V^* = \cup_i V_i^*$ is the irreducible decomposition of V^* in $\mathbb{P}^n_k$
7. If $V \subseteq \mathbb{A}^n_k$, then V^* is the closure of $\iota_{n+1}(V) \subseteq \mathbb{P}^n_k$ in the Zariski topology (i.e. it is the smallest algebraic set in $\mathbb{P}^n_k$ containing $\iota_{n+1}(V)$
8. If $\emptyset \neq V \subseteq \mathbb{A}^n_k$, then no irreducible component of V^* is contained in H_∞, though components may meet it
9. If $V \subseteq \mathbb{P}^n_k$ has no irreducible component contained in H_∞, then $(V_*)^* = V$

***Proof*:**
Parts (3) and (4) are immediate from the definitions, since homogenizing and dehomogenizing preserve containment of ideals and $\mathcal{Z}$ reverses it.

(1) and (2). A point of $\mathbb{A}^n_k$ satisfies f exactly when its image in U_{n+1} satisfies f^*, because f^* restricted to $x_{n+1} = 1$ is f by proposition 38.3.5(3). Intersecting with U_{n+1} therefore recovers $\iota_{n+1}(V)$, which is (1), and dehomogenizing recovers V, which is (2).

(7). By (1), V^* is a closed set whose trace on U_{n+1} is $\iota_{n+1}(V)$, so $V^* \supseteq \overline{\iota_{n+1}(V)}$. Conversely let W be any closed set containing $\iota_{n+1}(V)$, say $W = \mathcal{Z}_{\mathbb{P}}(J)$ with J homogeneous. Each $F \in J$ vanishes on $\iota_{n+1}(V)$, so F_* vanishes on V, so $F_* \in \mathcal{I}(V)$ and hence $F = x^r_{n+1}(F_*)^* \in I^*$ for some r, again by proposition 38.3.5(3). Therefore $V^* \subseteq W$, and V^* is the smallest such closed set.

(5) and (6). If V is irreducible then $\mathcal{I}(V)$ is prime, and the homogenization of a prime ideal is prime, because a product of homogeneous elements lies in I^* exactly when the product of their dehomogenizations lies in $\mathcal{I}(V)$. So V^* is irreducible, giving (5). Applying (5) and (7) to each component of $V = \bigcup_i V_i$ gives $V^* = \bigcup_i V_i^*$ with each V_i^* irreducible, and no containments among them since (3) and (2) make $V \mapsto V^*$ inclusion-reflecting; that is (6).

(8) and (9). A component of V^* contained in H_∞ would meet U_{n+1} in the empty set, so by (1) it would contribute nothing to V, contradicting (7)'s minimality. That is (8). For (9), the hypothesis makes V the projective closure of V_*, and (7) identifies that closure with $(V_*)^*$, as we sought to show.

Definition 39.2.2: Projective Closure

Let $V \subseteq \mathbb{A}^n_k$ be an algebraic set. Then $V^* \subseteq \mathbb{P}^n_k$ as defined in proposition 39.2.1 is called the *projective closure*.

Note that the homogenization of an ideal is *not* the homogenization of its generators

Example 39.2.3: Homogenization of Ideal and Generators

Let $I = (y - x^2, z - x^3)$ and $V = \mathcal{Z}(I)$ i.e. the twisted cubic in $\mathbb{A}^3_k$. Show that

1. $zw - xy \in I(V)^*$
2. $zw - xy \notin \left((y - x^2)^*, (z - x^3)^*\right)$

In other words, the ideal $(f_1^*, ..., f_n^*)$ is too small to capture all the new relations (in particular it usually adds a line at infinity).

Next, we define $k_{\mathbb{P}}(V)$ to be the localization of $k_{\mathbb{P}}[V]$. Note that if $f/g \in k(V)$ where $\deg(f) = \deg(g) = d$, then f/g is in fact a well-defined function on V, since:

$$\frac{f(\lambda x)}{g(\lambda x)} = \frac{\lambda^d f(x)}{\lambda^d g(x)} = \frac{f(x)}{g(x)}$$

there are thus many more rational functions defined on V than regular functions. The set of well-defined functions shall be given a name:

Definition 39.2.4: Function Field

Let V be a projective variety. Then:

$$\kappa(V) = \left\{ \frac{f}{g} \;\middle|\; f, g \in k_{\mathbb{P}}[V] \text{ homogeneous of the same degree, } g \notin \mathcal{I}_{\mathbb{P}}(V) \right\}$$

taken inside the fraction field of $k_{\mathbb{P}}[V]$, and modulo the usual identification $f/g = f'/g'$ when $fg' - f'g \in \mathcal{I}_{\mathbb{P}}(V)$. Elements of $\kappa(V)$ are the *rational functions* on V.

Homogeneity of f and g is what makes the ratio well defined on V: degree is not defined on a non-homogeneous element of $k_{\mathbb{P}}[V]$, and it is equality of the two degrees that makes the scaling factors λ^d cancel.

Proposition 39.2.5: Rational Functions over Projective and Affine Variety

Let $V \subseteq \mathbb{A}^n_k$ be an affine variety. Then:

$$k(V) \cong \kappa(V^*)$$

Similarly, if $V \subseteq \mathbb{P}^n_k$ is a projective variety not contained in the hyperplane at infinity. Then:

$$\kappa(V) \cong k(V_*)$$

***Proof*:**
Define a map in the direction of the claim by homogenizing:

$$\alpha \colon k(V) \to \kappa(V^*) \qquad \alpha\left(\frac{f}{g}\right) = \frac{x_{n+1}^{\deg g - \deg f} f^*}{g^*}$$

the power of x_{n+1} inserted so that numerator and denominator have the same degree, as definition 39.2.4 requires; when $\deg f > \deg g$ the correcting factor goes on the denominator instead.

Well defined. If $f/g = f'/g'$ in $k(V)$ then $fg' - f'g \in \mathcal{I}(V)$, and homogenizing that relation, using $(uv)^* = u^*v^*$ from proposition 38.3.5(1), puts the corresponding difference in $\mathcal{I}_{\mathbb{P}}(V^*)$ up to a power of x_{n+1}, which is a unit on U_{n+1} and so does not change the class.

Inverse. Dehomogenizing gives $\beta(F/G) = F_*/G_*$, and $\beta \circ \alpha = \mathrm{id}$ because $(f^*)_* = f$ for every f by proposition 38.3.5(3). For $\alpha \circ \beta = \mathrm{id}$, part (3) of that proposition gives $(F_*)^* = F$ up to a power of x_{n+1}; that power cancels between numerator and denominator since both are corrected to a common degree. Hence α is a bijection, and it is a ring homomorphism because homogenization is multiplicative and additive up to the same powers of x_{n+1}.

The second isomorphism is the first applied to V_*, using $(V_*)^* = V$ from proposition 39.2.1(9), which is exactly the hypothesis that V is not contained in the hyperplane at infinity, as we sought to show.

On the one hand, it may seem counter-intuitive that though we are restricting to degree 0 rational polynomials, we somehow get as many rational functions as when we allowed for any degree $r - s$

rational polynomial. On the other hand, this should not be too strange for the reader: the domain of definition is a dense open subset, and we shall show that V^* is the closure of V when embedded in $\mathbb{P}^n_k$.

We can define the *stalk* at p to be

$$\mathcal{O}_p(V) = \{f/g \in \kappa(V) \mid g(p) \neq 0\}$$

The same argument as proposition 33.2.10 shows $\mathcal{O}_p(V)$ is a local Noetherian domain.

Proposition 39.2.6: Stalk Defined Locally

Let $V \subseteq \mathbb{P}^n_k$ be a projective variety not contained in the hyperplane at infinity, let V_* be its dehomogenization, and let $p \in V_*$. Then:

$$\mathcal{O}_p(V) \cong \mathcal{O}_p(V_*)$$

This shows that the properties of a stalk are inherently "local", depending only on the information around the point p.

***Proof*:**
Restrict the isomorphism α of proposition 39.2.5. A rational function on V lies in $\mathcal{O}_p(V)$ exactly when it has a representative F/G with $G(p) \neq 0$; applying α and its inverse turns such representatives into representatives f/g on V_* with $g(p) \neq 0$, since dehomogenizing at x_{n+1} does not change whether a form vanishes at a point of U_{n+1}. So α carries $\mathcal{O}_p(V)$ onto $\mathcal{O}_p(V_*)$ and is a ring isomorphism between them, as we sought to show.

Next, notice there is more than one natural set of coordinates on projective space. It is natural to consider the coordinates of $\mathbb{P}^n_k$ to be given by degree 1 homogeneous functions, namely each point $x \in \mathbb{P}^n_k$ is of the form $[x_1 : \cdots : x_{n+1}]$ where $[\lambda x_1 : \cdots : \lambda x_{n+1}] = \lambda[x_1 : \cdots : x_{n+1}]$. However, we may also just as naturally choose to represent each point in any degree of homogeneity, namely:

$$[\lambda w_1 : \cdots : \lambda w_{n+1}] = [w_1 : \cdots : w_{n+1}]$$

where we can have $w_i = (x_i)^k$.

Finally, as all homogeneous polynomials must be of the same degree, we can give a rough classification of all hypersurfaces of projective space $\mathbb{P}^n_k$ of degree d. A hypersurface is defined by a single homogeneous equation. As there are $n+1$ variables, there are $\binom{n+d}{d} = N$ possible degree d monomials. Labeling them $M_1, ..., M_N$, any degree d homogeneous polynomial is of the form:

$$\sum_i^N a_i M_i$$

These hypersurface are naturally defined up to multiplication of a constant $c \in k$. But then, the coefficients determine the hypersurface up to a constant, meaning they can be associated to a point in $\mathbb{P}^N_k$, or said differently $\mathbb{P}^N_k$ *parameterizes* the degree d hypersurfaces of $\mathbb{P}^n_k$ or is the *moduli space* for the degree d hypersurfaces of $\mathbb{P}^n_k$.

Note that some points classify the same hypersurface, for example $x^2y = 0$ and $xy^2 = 0$ in $\mathbb{P}^2_k$, both of which cut out the union of the lines $x = 0$ and $y = 0$. The difference is in the multiplicity, information that would be distinguishable when working with *closed subschemes* instead of closed subsets.

39.3 Quasi-Projective Varieties

As we saw in the above, affine and projective varieties are naturally linked to each other. Many results that are proven in classical algebraic geometry apply both to projective and affine varieties. Furthermore, the open subset of projective variety (for example $\mathbb{P}^1_k$ minus the point at infinity and zero) have natural algebraic structure but are not the vanishing set of polynomials (they are the opposite, they are the non-vanishing set of polynomials). The properties of such sets often are strongly tied to varieties, or are even varieties themselves (for example $\mathbb{P}^1_k$ without the point at infinity is the closed set $\mathbb{A}^1_k$ in $\mathbb{A}^1_k$, but is an open set in $\mathbb{P}^1_k$). The definition of quasi-projective varieties aims to unify all of these.

If $X \subseteq \mathbb{P}^n_k$ is closed and $X_i = X \cap U_i$ is open in X, they are in fact *closed* in $U_i \cong \mathbb{A}^n_k$. This can be seen by de-homogenizing: if X is given by equations $f_0, ..., f_n$ where $\deg f_i = n_i$, then U_i is given by:

$$x_i^{-n_j} f_j = f(x_1, .., x_{i-1}, 1, x_{i+1}, ..., x_{n+1}) = 0$$

If we have $X_i \subseteq U_i$ which is closed, then we may consider the closure $\overline{X_i} \subseteq \mathbb{P}^n_k$ by taking the polynomials that generate X_i and homogenizing them, namely if f is one such polynomial where $\deg f = d$, then the equations describing $\overline{X_i}$ are of the form

$$x_i^l f(x_1/x_i, ..., x_{n+1}/x_i) = 0$$

Which implies that:

$$X_i = \overline{X_i} \cap U_i$$

Hence, if $X \subseteq \mathbb{P}^n_k$, then an open subset of X will correspond to a closed subset of $\mathbb{A}^n_k$. As X is an open subset of itself, it corresponds to an open subset of a closed projective algebraic set. Thus, open subsets of closed projective sets encapsulate affine and projective varieties:

Definition 39.3.1: Quasi-projective Variety

A *quasi-projective variety* is an open subset of a closed projective variety.

Example 39.3.2: Quasi-Projective Varieties

1. *Affine varieties are quasi-projective.* $\mathbb{A}^n_k$ is the standard chart $U_0 \subseteq \mathbb{P}^n_k$, an open subset, and a closed $V \subseteq \mathbb{A}^n_k$ is $\overline{V} \cap U_0$ for its projective closure. So every affine variety is open in a projective one.

2. *Projective varieties are quasi-projective*, taking the open set to be everything.

3. *Neither affine nor projective.* $\mathbb{A}^2_k \setminus \{(0,0)\}$ is open in $\mathbb{A}^2_k$, hence quasi-projective. It is not projective, carrying the nonconstant regular function x, and it is not affine: its ring of regular functions is $k[x, y]$, whose maximal ideals include one for the missing origin. The details are the fifth exercise of exercise set 39.5.1.

4. *The complement of a hypersurface.* For a form F of degree d, the set $\mathbb{P}^n_k \setminus \mathcal{Z}(F)$ is quasi-projective and in fact affine, being isomorphic to a closed subvariety of $\mathbb{A}^N$ under the Veronese of definition 41.1.1, which turns $\mathcal{Z}(F)$ into a hyperplane section.

5. *A non-example.* Over $\mathbb{C}$, the subset $\mathbb{Z} \subseteq \mathbb{C} = \mathbb{A}^1_{\mathbb{C}}$ is not quasi-projective. A locally closed

subset of $\mathbb{A}^1_{\mathbb{C}}$ is finite or cofinite, by the sixth exercise of exercise set 41.6.1, and $\mathbb{Z}$ is neither. So it is not even constructible, and by theorem 41.3.4 it is not the image of any regular map.

A closed subset $C \subseteq U$ of a quasi-projective variety is the intersection of C with a closed subset $\mathbb{P}^n_k$. The irreducible decomposition of theorem 32.3.5 carries over verbatim, since it used only that the space is Noetherian. If $Y \subseteq X \subseteq \mathbb{P}^n_k$ with Y quasi-projective, then Y is a *subvariety* of X.

It must be noted that the collection of quasi-projective varieties is larger than the collection affine and projective varieties. For example $\mathbb{A}^2_k \setminus \{(0,0)\}$ is a quasi-projective variety, but is not affine or projective.

Let X be a quasi-projective variety and $U \subseteq X$ an open subset. Define $\Gamma(U, \mathcal{O}_X) \subseteq \kappa(X)$ to be the collection of all rational functions on X that are defined at each $p \in U$. Equivalently:

$$\Gamma(U, \mathcal{O}_X) = \bigcap_{p \in U} \mathcal{O}_p(X)$$

Note that if $U = X$, then by proposition 33.2.9 and proposition 39.2.6,

$$\Gamma(X, \mathcal{O}_X) = k[X] = \Gamma(X)$$

showing this notation is consistent with our earlier definitions.

Next, let's see that checking that a quasi-projective variety is closed is an open-local condition:

Lemma 39.3.3: Closedness of Quasi-projective Variety is Open-local

Let $Y \subseteq X$ be a quasi-projective variety. Then Y is closed if and only if $X = \cup_\alpha U_\alpha$ where U_α is open and $Y \cap U_\alpha$ is closed for every α. Namely, closedness is open-local for quasi-projective varieties

***Proof*:**
If Y is closed then $Y \cap U_\alpha$ is closed in U_α for any open cover, which is the easy direction.

Conversely let $X = \bigcup_\alpha U_\alpha$ with each U_α open and each $Y \cap U_\alpha$ closed in U_α. Write $U_\alpha = X \setminus Z_\alpha$ with Z_α closed, and $Y \cap U_\alpha = T_\alpha \cap U_\alpha$ with T_α closed in X. We claim

$$Y = \bigcap_\alpha (Z_\alpha \cup T_\alpha)$$

which exhibits Y as an intersection of closed sets and so finishes the proof.

For $\subseteq$: let $y \in Y$ and fix α. Either $y \notin U_\alpha$, in which case $y \in Z_\alpha$; or $y \in U_\alpha$, in which case $y \in Y \cap U_\alpha \subseteq T_\alpha$. Either way $y \in Z_\alpha \cup T_\alpha$.

For $\supseteq$: let y lie in every $Z_\alpha \cup T_\alpha$. The U_α cover X, so $y \in U_\beta$ for some β, and then $y \notin Z_\beta$, forcing $y \in T_\beta$. Hence $y \in T_\beta \cap U_\beta = Y \cap U_\beta \subseteq Y$, as we sought to show.

The following shows that any variety is fundamentally locally affine:

Lemma 39.3.4: Varieties Are Locally Affine

Let X be a quasi-projective variety. Then every $x \in X$ has an open neighborhood that is isomorphic to an affine variety

***Proof*:**
Take $X \subseteq \mathbb{P}_k^n$. If $x \in U_{n+1}$, then $x \in X \cap U_{n+1}$ and by definition of a quasi-projective variety:

$$X \cap U_{n+1} = Y - Y_1$$

where Y_1, Y are closed subsets of U_{n+1}. As $x \in Y$, there exists a polynomial f with coordinates in U_{n+1} where $f = 0$ on Y_1 and $f(x) \neq 0$. Let $D(f) = Y \setminus \mathcal{Z}(f)$, the subset of Y on which f does not vanish. It is open in Y and contains x, and it misses Y_1 entirely since f vanishes there, so $D(f) \subseteq Y \setminus Y_1 = X \cap U_{n+1}$ is an open neighbourhood of x inside X.

I claim this neighborhood is isomorphic to an affine variety. If $(f_1, ..., f_m)$ is the ideal associated to $Y \subseteq U_{n+1}$, then define the variety in $\mathbb{A}_k^{n+1}$ via:

$$f_1(x_1, ..., x_n) = \cdots = f_m(x_1, ..., x_n) = 0 \qquad f(x_1, ..., x_n)x_{n+1} = 1$$

i.e.

$$Z = \mathcal{Z}(f_1, ..., f_m, f \cdot x_{n+1} - 1)$$

Then the mapping

$$\varphi(x_1, ..., x_{n+1}) \to (x_1, ..., x_n)$$

gives a regular mapping from Z into $D(f)$, and

$$\psi(x_1, ..., x_n) \to (x_1, ..., x_n, f(x_1, ..., x_n)^{-1})$$

is a regular mapping of $D(f)$ into Z. The two composites are the identity: $\varphi \circ \psi$ drops the last coordinate that ψ appended, and $\psi \circ \varphi$ restores it, since a point of Z satisfies $f \cdot x_{n+1} = 1$ and so has $x_{n+1} = f^{-1}$ determined by the others. Hence $D(f) \cong Z$, an affine variety, as we sought to show.

This result also showed that principal open sets (definition 31.3.5) are naturally associated to an affine algebraic set, and that the regular function on $D(f)$ are:

$$k[D(f)] = k[X][1/f]$$

In particular f is nonzero on $D(f)$, so this is well defined. Overall, when checking if a mapping between quasi-projective is regular, it suffices to check that any affine variety in the codomain has a closed pre-image.

39.4 Regular Maps

Let us now define regular mappings on quasi-projective varieties. This definition should extend that of affine varieties where a polynomial function was given for each coordinate.

Recall that a rational map on $\mathbb{P}_k^n$ is the quotient of two homogeneous polynomials, with degree $r - s$ where r, s is the degree of the numerator and denominator respectively. A regular point x of a rational function f would be a point where f can be represented by p/q with $q(x) \neq 0$. When working over projective varieties, we shall have that most rational polynomials are not rational functions; we shall require that $r = s$, that is it must be of degree 0.

Definition 39.4.1: Regular Point [on Quasi-projective Variety]

Let X be a quasi-projective variety and $f \in \kappa(X)$ a rational function. Then f is *regular at* $x \in X$ if it admits a representative $f = p/q$ with p, q homogeneous of the same degree and $q(x) \neq 0$. Such a q is then nonzero on the whole open set $D(q)$, so being regular at x is a condition on a neighbourhood of x rather than on x alone.

If f is regular at every point of X it is called *regular* on X. The *set* of regular functions on X is written $k[X]$.

When we defined a regular function before, it was an element of the coordinate ring. We have now defined it to be locally regular at all points. When k is algebraically closed, these two are in fact the same. If X is irreducible, then this is the result of proposition 33.2.2. For the general case, say $f = p_x/q_x$ where $q_x \neq 0$ on U_x so that on U_x:

$$q_x f = p_x \tag{39.1}$$

Then this equation holds on all of X. To see this, choose a regular functions that vanishes on $X \setminus U_x$ but not at x (recall that U_x is dense in X), and multiply it by $p_x q_x$. Then we see that (39.1) must hold outside of U_x as both sides of the equality will vanish. Then like the irreducible case, we can now find points $x_1, ..., x_n$ and regular functions $h_1, ..., h_n$ such that

$$\sum_i^n q_x h_i = 1$$

Then for each x_i, multiplying by h_i and adding up we get:

$$f = \sum_i^n p_x h_i$$

and hence f is regular in the same sense given in definition 32.1.2. Recall that it was mentioned that if $X = \mathbb{P}^n_k$ that $k[\mathbb{P}^n_k]$ consists of only constants functions. We shall soon show that if $X = V \subseteq \mathbb{P}^n_k$ is any projective variety that $k[V]$ is the collection of constant functions.

Definition 39.4.2: Regular Map [On Quasi-projective Variety]

Let $f\colon X \to Y$ be a map of quasi-projective varieties with $Y \subseteq \mathbb{P}^m_k$. Then f is *regular* if for every $x \in X$ there is a standard affine chart $U_i \subseteq \mathbb{P}^m_k$ containing $f(x)$ and an open neighbourhood W of x with $f(W) \subseteq U_i$, such that each of the m coordinate functions of $f|_W$ is regular in the sense of definition 39.4.1.

The collection of regular function is denoted $k[X]$, $\mathcal{O}_X(X)$, or $\Gamma(X)$[a], and the collection of regular mapping between two quasi-projective varieties is denoted $\mathrm{Hom}_{\mathbf{Reg}}(X, Y)$.

[a] This notation shall become more prominent in modern algebraic geometry

This definition of regular function is well-defined and is independent of choice of U_i: if $f(x) = (y_0, ..., \hat{1}_i, ..., y_m) \in U_i$ (where the hat indicates omission), it is also contained in U_j when $y_j \neq 0$, and the coordinates of this point in U_i are of the form:

$$(y_0/y_j, ..., 1/y_j, ..., \hat{1}_j, ..., y_m/y_j)$$

Hence, given the mapping $f : U \to U_i$ is given by

$$(f_0, .., \hat{1}_i, .., f_m)$$

then $f : U \to U_j^m$ is given by $(f_0/f_j, ..., 1/f_j, ..., \hat{1}_j, ..., f_m/f_j)$. As $f_j(x) \neq 0$ and the set U' of points of U where $f_j = 0$ is open. Then on U', the functions $f_0/f_j, ..., 1/f_j, ..., \hat{1}_j, ..., f_m/f_j$ are regular, and so $f : U' \to U_j^m$ is regular.

If we have an affine closed set, by theorem 32.1.5 the regular mapping $f\colon X \to Y$ is determined by the pullback $f^{\#}\colon k[Y] \to k[X]$. This is not the case if X, Y are projective, for as mentioned a few times already we shall have $k[X]$ and $k[Y]$ consist of only constant functions. However, it must be noted that for a general quasi-projective variety, $k[X]$ could be quite large[3]. If X is isomorphic to a closed subset of an affine space, it shall be called an *affine variety*, and if it isomorphic to a closed subset of projective space, it shall be called *projective variety*. Not all quasi-projective varieties are affine or projective (for example $\mathbb{A}_k^2 \setminus \{(0,0)\}$).

Let us now characterize regular maps form quasi-projective varieties to projective space[4]. To understand such a map, start with a regular mapping f on X and a point $x \in X$ where $f(x) \in \mathbb{A}_k^m = U_0^m$ so that there is an open neighborhood where $f = (f_1, ..., f_m) : U \to U_i^m$. Then as it is regular we can write $f_i = p_i/q_i$ where p_i, q_i are of the same degree in homogeneous coordinates and $q_i(x) \neq 0$. Taking the l.c.m. of such fractions we get that $f_i = F_i/F_0$ where $F_0, ..., F_m$ are forms of the same degree and $F_0(x) \neq 0$; overall we can think of the point $f(x) \in U_i^m$ as the point:

$$f(x) = [F_0(x) : \cdots : F_m(x)] \in \mathbb{P}_k^m$$

in projective space. Note that there is more than one representative for such a regular function, namely if

$$F(x) = [F_0(x) : \cdots : F_m(x)] \qquad G(x) = [G_0(x) : \cdots : G_m(x)]$$

then they are the same point if and only if $F_i G_j = F_j G_i$ on X for all $0 \leq i, j \leq m$. This gives us an explicit condition for when $Y = \mathbb{P}_k^m$:

Proposition 39.4.3: Equivalent Regular Function

Let $X \subseteq \mathbb{P}_k^n$ be an irreducible quasi-projective variety and $f\colon X \to \mathbb{P}_k^m$ a map of sets. Then f is regular if and only if it can be written as

$$f = [F_0 : \cdots : F_m]$$

for forms F_i of a common degree in the homogeneous coordinates of $\mathbb{P}_k^n$, not all vanishing at any point of X. Two such presentations $[F_0 : \cdots : F_m]$ and $[G_0 : \cdots : G_m]$ define the same map exactly when

$$F_i G_j = F_j G_i \text{ on } X \text{ for all } 0 \leq i, j \leq m$$

***Proof*:**

Suppose f has such a presentation and fix $x \in X$. Some $F_j(x) \neq 0$, and on the open set $D(F_j) \cap X$ the coordinates of f in the chart U_j are the ratios F_i/F_j, each a quotient of forms of equal degree with nonvanishing denominator. By definition 39.4.1 these are regular, so f is

[3] Shafarevich mentions that Rees and Nagata constructed an example where $k[X]$ is not finitely generated

[4] This is in fact a larger exploration that culminates in the theory of line bundles on a projective scheme

regular.

Conversely let f be regular and fix x with $f(x) \in U_j$. In that chart f has coordinates $f_i = p_i/q_i$ with p_i, q_i forms of equal degree and $q_i(x) \neq 0$. Clearing denominators over $Q = q_0 \cdots q_m$ rewrites these as $f_i = F_i/F_j$ with all F_i forms of one degree and $F_j(x) \neq 0$, which is the required presentation near x. Two such local presentations agree on the overlap of their domains, which is a nonempty open subset of the irreducible X and hence dense, so they agree wherever both are defined and glue.

For the last clause, the two presentations give the same point of $\mathbb{P}^m_k$ at x exactly when the vectors $(F_0(x), \ldots, F_m(x))$ and $(G_0(x), \ldots, G_m(x))$ are proportional, which is the vanishing of every 2×2 minor $F_iG_j - F_jG_i$, as in example 38.3.7(1). Requiring it at every point of X is the stated condition, as we sought to show.

Example 39.4.4: Regular Mappings

1. *Projection*: Let $E \subseteq \mathbb{P}^n_k$ be a d-dimensional subspace given by $n - d$ linearly independent linear equations $(L_1, ..., L_{n-d})$. In homogeneous coordinates, the equations L_i are called *linear forms*. The mapping:

   $$\pi(x) = (L_1(x) : \cdots : L_{n-d}(x))$$

   is well-defined and is called the projection with center E. Notice this set is regular on $\mathbb{P}^n_k \setminus E$ as the L_i's do not vanish simultaneously. Then for any $X \subseteq \mathbb{P}^n_k$ where $X \cap E = \emptyset$ and X is closed, we have a regular mapping

   $$\pi : X \to \mathbb{P}^{n-d-1}_k$$

   Geometrically, we can interpret the mapping as follows. Take any $(n - d - 1)$-dimensional subspace $H \subseteq \mathbb{P}^n_k$ with $H \cap E = \emptyset$. Through any point $x \in \mathbb{P}^n_k \setminus E$ and the space E, there passes a unique $(d + 1)$-dimensional subspace E_x. Then this subspace intersects H at a unique point, namely $\pi(x)$. If X intersects E, but does not contain it, then this is a rational mapping.

   We have seen the case where $d = 0$ before (think of the hyperbola to $\mathbb{A}^1_k$)

2. Take $V = \mathcal{Z}(y - x^2, z - x^3)$ (i.e. the twisted cubic). This is a rational curve with parameterization:

   $$t \mapsto (t, t^2, t^3)$$

   Let us now homogenize this variety. The homogenization of this map is:

   $$[s : t] \mapsto \left[1 : \frac{t}{s} : \frac{t^2}{s^2} : \frac{t^3}{s^3}\right] = \left[s^3 : ts^2 : t^2s : t^3\right]$$

3. Take $V = \mathcal{Z}(x^2 + y^2 - z^2)$; the projectivization of the circle. Define the map:

   $$f : \mathbb{P}^1_k \to V \qquad [s : t] \to [s^2 - t^2 : 2st : s^2 + t^2]$$

   This is an isomorphism, with inverse $[x : y : z] \mapsto [x + z : y]$. Checking the composite, $(s^2 - t^2)^2 + (2st)^2 = (s^2 + t^2)^2$, so f lands in V; and at $f([s : t])$ we have $x + z = 2s^2$

and $y = 2st$, so $[x + z : y] = [2s^2 : 2st] = [s : t]$ whenever $s \neq 0$, the case $t \neq 0$ being symmetric. So a smooth conic in $\mathbb{P}^2_k$ is isomorphic to $\mathbb{P}^1_k$, which is the genus-zero case of example 38.5.4(3).

4. *The Veronese and Segre embeddings* give further regular maps into larger projective spaces, and are the tools that turn products and degree-d hypersurfaces into linear data. Section 40.1 constructs the Segre embedding and chapter 41 the Veronese.

39.5 Rational Functions on Quasi-Projective Varieties

When working with affine varieties, we had the quotient of two regular functions. However, mentioned a few times, on $\mathbb{P}^n_k$ there are only constant regular functions, and a rational function, being the ratio of two regular functions, would still be constant.

The solution is to recall the definition of $\mathcal{O}_X$, namely:

$$\mathcal{O}_X = \{\varphi = f/g \in k(x_1, \dots, x_{n+1}) \mid f, g \text{ homogeneous of equal degree, } g \notin \mathcal{I}_{\mathbb{P}}(X)\}$$

where f and g are of the same degree. Then take the subset $\mathfrak{m}_X = \{\varphi = f/g \in \mathcal{O}_X \mid f \in I(X)\}$.

Definition 39.5.1: Rational Function On quasi-projective Variety

Let X be a quasi-projective variety. Then the set of rational functions on X is given by:

$$k(X) \cong \mathcal{O}_X/\mathfrak{m}_X$$

By a reasoning similar to proposition 33.2.7, a homogeneous function vanishes on X if and only if it vanishes on an open subset $U \subseteq X$. Hence $k(X) = k(U)$. As a consequence:

$$k(X) = k(\overline{X})$$

Due to this, when studying rational functions on quasi-projective spaces, we may reduce to studying rational functions to affine or projective varieties, which often leads most results to focus on the irreducible case. The set of regular points shall be called the *domain of definition*. If $f \colon X \to \mathbb{P}^m_k$, then it is determined by specifying $m + 1$ forms $[F_0 : \cdots : F_m]$ of $n + 1$ homogeneous coordinates of projective space $\mathbb{P}^n_k$ containing X (where at least one form must not vanish on X). Furthermore, if f can be given by functions $[f_0 : \cdots f_m]$ where each f_i are regular at all $x \in X$ and not all vanish at this point, then the map is regular at x, and hence determines a regular mapping of some neighborhood x into $\mathbb{P}^m_k$.

We saw before that birational maps are weaker than isomorphisms. However, rational maps are regular on an open dense set (as the reader should verify with quasi-projective varieties). This leads to the following result:

Proposition 39.5.2: Reduction To Open Subset

Let X, Y be irreducible varieties. Then X and Y are birationally isomorphic if and only if they contain isomorphic open subsets $U \subseteq X$ and $V \subseteq Y$.

***Proof*:**
If X and Y contain isomorphic open subsets then those subsets are dense, since X and Y are irreducible, and an isomorphism between dense open sets is a birational map. That is the easy direction.

Conversely let $f\colon X \dashrightarrow Y$ be birational with inverse g. Let $U_1 \subseteq X$ and $V_1 \subseteq Y$ be their domains of definition, both dense open by lemma 33.2.4. Put

$$U = U_1 \cap f^{-1}(V_1) \qquad V = V_1 \cap g^{-1}(U_1)$$

Each is open, and each is nonempty: $f(U_1)$ is dense in Y so it meets the nonempty open V_1, and symmetrically.

Shrinking once more, replace U by $U \cap g(V)$ and V by $V \cap f(U)$, which are again nonempty and open because f and g are dominating. On these sets both composites are defined everywhere and agree with the identity on a dense subset, hence equal it: two regular maps into a variety agreeing on a dense subset are equal, since their equalizer is closed. So $f|_U\colon U \to V$ and $g|_V\colon V \to U$ are mutually inverse isomorphisms, as we sought to show.

Exercise 39.5.1

1. Write down the $n+1$ standard charts of $\mathbb{P}^n_k$ explicitly and compute the transition map between two of them for $n = 1$ and $n = 2$. Verify that the transitions are regular where defined, as corollary 39.1.3 asserts.

2. Show that the projective closure of the parabola $\mathcal{Z}(y - x^2) \subseteq \mathbb{A}^2_k$ is $\mathcal{Z}(yz - x^2)$, and identify the point it acquires at infinity. Do the same for the hyperbola $\mathcal{Z}(xy - 1)$.

3. Let $V \subseteq \mathbb{A}^3_k$ be the twisted cubic, with $\mathcal{I}(V) = (y - x^2,\, z - x^3)$. Homogenize those two generators and show that their common projective zero set is strictly larger than the projective closure of V. Conclude that the projective closure is obtained by homogenizing every element of $\mathcal{I}(V)$, not just a set of generators.

4. Show that a regular function on a quasi-projective variety is continuous for the Zariski topology, and deduce that the locus where two regular maps agree is closed.

5. Show that $\mathbb{A}^2_k \setminus \{0\}$ is a quasi-projective variety and that every regular function on it extends to $\mathbb{A}^2_k$. Deduce that it is not isomorphic to any affine variety.

6. Verify the irreducible decomposition theorem for quasi-projective varieties: every quasi-projective variety is a finite union of irreducible closed subsets, none containing another, and the decomposition is unique.

7. Show that $[s : t] \mapsto [s^2 : st : t^2]$ is an isomorphism of $\mathbb{P}^1_k$ onto the conic $\mathcal{Z}(xz - y^2) \subseteq \mathbb{P}^2_k$, and compare with example 39.4.4(3).

8. Show that a rational function on an irreducible quasi-projective variety is determined by its restriction to any nonempty open subset, which is proposition 39.5.2, and give an example showing this fails for reducible varieties.

40

Completeness and Finite Maps

The property that makes projective varieties worth the trouble is completeness: the projection $X \times Y \to Y$ is a closed map whenever X is projective. It is the algebraic counterpart of compactness, and it yields at once that the image of a projective variety under a regular map is closed and that the only regular functions on a projective variety are constant.

Proving it requires knowing what a product of projective varieties is, which is not the naive thing. From there the chapter turns to finite maps, the algebraic mirror of integral extensions, and the theorem that every variety is a finite cover of a space as simple as $\mathbb{A}^m$ or $\mathbb{P}^m$. It closes by measuring a map against its fibres: the dimension of the source is the dimension of the target plus the dimension of the generic fibre, and the special fibres can only be bigger.

40.1 Products and the Segre Embedding

The direct product of algebraic sets $X \subseteq \mathbb{A}^n_k$ and $Y \subseteq \mathbb{A}^m_k$ is again algebraic, and lives in $\mathbb{A}^{n+m}_k$. If $X' \subseteq \mathbb{A}^p_k$ and $Y' \subseteq \mathbb{A}^q_k$ are algebraic sets with $X \cong X'$ and $Y \cong Y'$, then $X \times Y \cong X' \times Y' \subseteq \mathbb{A}^{p+q}_k$, showing that this definition is embedding-independent. The projective case is not so simple. There is no N with $\mathbb{P}^n_k \times \mathbb{P}^m_k \cong \mathbb{P}^N_k$; what there is instead is a *closed embedding* into $\mathbb{P}^N_k$ for $N = (n+1)(m+1)-1$, whose image is a proper subvariety cut out by explicit quadratic equations. Finding that embedding is the business of this section. Defining the product also gives the tool that section 40.2 needs.

To start, recall that $\mathbb{A}^n_k \times \mathbb{A}^m_k \cong \mathbb{A}^{n+m}_k$. A first attempt at understanding $\mathbb{P}^n_k \times \mathbb{P}^m_k$ would be to consider $\mathbb{P}^{n+m}_k$. However, this space is dependent on the representation of the homogeneous points in $\mathbb{P}^n_k$ and $\mathbb{P}^m_k$, for example if $[2:0] = [1:0] \in \mathbb{P}^1_k$, and $[3:0] = [1:0] \in \mathbb{P}^1_k$, then:

$$[1:1:0] \neq [2:3:0] \in \mathbb{P}^2_k$$

Furthermore, if we choose $[x_1 : x_2] \in \mathbb{P}^1_k$ and $[y_1 : y_2] \in \mathbb{P}^1_k$, which point in $\mathbb{P}^2_k$ ought to represent this

point? To resolve this, we shall "twist-multiply"

$$[x_1y_1 : x_1y_2 : x_2y_1 : x_2y_2] \in \mathbb{P}_k^{(1+1)(1+1)-1}$$

Notice that for $[\lambda x_1 : \lambda x_2]$ and $[\mu y_1 : \mu y_2]$ then:

$$[\lambda\mu x_1y_1 : \lambda\mu x_1y_2 : \lambda\mu x_2y_1 : \lambda\mu x_2y_2] = [x_1y_1 : x_1y_2 : x_2y_1 : x_2y_2] \in \mathbb{P}_k^3$$

and hence is independent of representation. Generalizing this, we define for any

$$x = [x_0 : \cdots : x_n], y = [y_0 : \cdots : y_m] \qquad w = [w_{ij}] \in \mathbb{P}_k^{(n+1)(m+1)-1},\ w_{ij} = x_iy_j$$

Consider now the embedding $\varphi : \mathbb{P}_k^n \times \mathbb{P}_k^m \to \mathbb{P}_k^{(n+1)(m+1)-1}$ given by the above. The image is indeed a closed subset, for it satisfies the equations:

$$w_{ij}w_{kl} - w_{il}w_{kj} = 0 \tag{40.1}$$

which hold because both sides equal $x_ix_ky_jy_l$ once $w_{ij} = x_iy_j$ is substituted. The construction is natural in the sense that it matches the standard affine charts on both sides. Write $\mathbb{A}^n$ for $\mathbb{A}_k^n$ and let $U_i \subseteq \mathbb{P}_k^n$ be the ith standard affine chart, so $U_i \cong \mathbb{A}^n$. Then:

$$\varphi(U_i \times U_j) = W_{ij} = \mathbb{A}_{ij}^N \cap \varphi(\mathbb{P}_k^n \times \mathbb{P}_k^m)$$

where $N = (n+1)(m+1) - 1$ and $\mathbb{A}_{ij}^N$ is the set of points of $\mathbb{P}_k^N$ where $w_{ij} \neq 0$. Consider now the set $\mathbb{A}_{00}^N$. Take a point in projective space where $w_{00} \neq 0$ so that it corresponds to a point in $\mathbb{A}_{00}^N$:

$$[w_{ij}] = \varphi(x, y) \in \mathbb{P}_k^N$$

Take $z_{ij} = w_{ij}/w_{00}$, $x_i = u_i/u_0$, $y_j = v_j/v_0$ as the inhomogeneous coordinates. Then:

$$z_{i0} = x_i \qquad z_{0j} = y_j \qquad z_{ij} = x_iy_j = z_{i0}z_{0j}$$

So $\mathbb{A}_{00}^N \cong \mathbb{A}^{n+m}$ with coordinates $(x_1, \ldots, x_n, y_1, \ldots, y_m)$, the isomorphism being induced by φ. Hence φ is indeed the natural choice for the embedding of $\mathbb{P}_k^n \times \mathbb{P}_k^m$. This may feel more natural if we recall that each point of projective space $[a_0 : \cdots a_n] \in \mathbb{P}_k^n$ is closed and given by a system of linear equations

$$a_ix_j - a_jx_i = 0$$

mirroring (40.1). Notice that we may interpret the point $[w_{ij}]$ as an $(n+1) \times (m+1)$ matrix given by multiplying the points x and y as a $(n+1, 1)$ matrix and a $(1, m+1)$ matrix respectively (note the resulting rank of the matrix will be 1). From this, we may define the product of two quasi-projective varieties

Definition 40.1.1: Segre Embedding: Product of Projective Space

Let $V \subseteq \mathbb{P}_k^n, W \subseteq \mathbb{P}_k^m$ be two quasi-projective varieties. Then:

$$V \times W \subseteq \varphi(\mathbb{P}_k^n \times \mathbb{P}_k^m) \subseteq \mathbb{P}_k^{(n+1)(m+1)-1}$$

is the product of the quasi-projective varieties V, W.

Example 40.1.2: Product of Projective Lines
Let $V = W = \mathbb{P}^1_k$ and consider $\varphi(\mathbb{P}^1_k \times \mathbb{P}^1_k) \subseteq \mathbb{P}^3_k$. This set satisfies the equation:

$$w_{11}w_{00} - w_{01}w_{10} = 0$$

which is a nondegenerate quadric Q in $\mathbb{P}^3_k$. Let us consider the set

$$\varphi(\{\alpha\} \times \mathbb{P}^1_k)$$

then given $\alpha = [\alpha_0 : \alpha_1]$, these are all points in $\mathbb{P}^3_k$ such that

$$\alpha_1 w_{00} - \alpha_0 w_{10} = 0 \qquad \alpha_1 w_{01} - \alpha_0 w_{11} = 0$$

These equations give lines in $\mathbb{P}^3_k$. Similarly for $\varphi(\mathbb{P}^1_k \times \{\beta\})$. The two rulings of the quadric are visible in the following picture:




Figure 40.1: Segre Embedding of Product of Projective Lines

The closed subsets of $\text{im}\varphi \subseteq \mathbb{P}^{(n+1)(m+1)-1}_k$ correspond well with the closed subsets of $\mathbb{P}^n_k \times \mathbb{P}^m_k$. Let us start with seeing which subset of $\mathbb{P}^n_k \times \mathbb{P}^m_k$ are algebraic subsets under the Segre Embedding. Let $X \subseteq \mathbb{P}^{(n+1)(m+1)-1}_k$ be a sub-variety so that it is defined by homogeneous equations $f_i(w_{00}, ..., w_{nm})$. Then these induce the homogeneous polynomials $g_i(u_0, ..., u_n, v_0, ..., v_m)$ on $\mathbb{P}^n_k \times \mathbb{P}^m_k$ where the u_i, v_j are the same homogeneous degree. Conversely, if there are two systems of homogeneous equations taking variables of the same homogeneous degree in u_i, v_j, then there exists homogeneous polynomials taking variables in $u_i v_j$. If the degrees of the variables u_i and v_j differ, say the former are of degree r and the latter of degree s, then we can create the system of homogeneous equations:

$$v_j^{r-s} g_i(u_0, \ldots, u_n, v_0, \ldots, v_m) = 0$$

assuming $r > s$. One important consequence of this is that we can directly check for a set $Z \subseteq \mathbb{P}^n_k \times \mathbb{P}^m_k$ being closed by looking for a single polynomial in $\mathbb{P}^{(n+1)(m+1)-1}_k$ instead of looking for two polynomials in each separate projective space and verifying the set is the direct product of those two closed sets. Let us box this for future reference:

Proposition 40.1.3: Segre Embedding is Closed

Let $\varphi : \mathbb{P}_k^n \times \mathbb{P}_k^m \to \mathbb{P}_k^{(n+1)(m+1)-1}$ be the Segre embedding. Then $\operatorname{im}\varphi$ is closed. Furthermore, $X \subseteq \mathbb{P}_k^n \times \mathbb{P}_k^m$ is closed if and only if $\varphi(X) \subseteq \operatorname{im}\varphi$ is closed.

***Proof*:**

The image is closed. Substituting $w_{ij} = x_i y_j$ shows every point of $\operatorname{im}\varphi$ satisfies (40.1). Conversely let $w = [w_{ij}]$ satisfy all those relations, and pick (a, b) with $w_{ab} \neq 0$. Set $x_i = w_{ib}$ and $y_j = w_{aj}$. Then for all i, j,

$$x_i y_j = w_{ib} w_{aj} = w_{ij} w_{ab}$$

using (40.1), so $[x_i y_j] = [w_{ij}]$ after scaling by w_{ab}, and $w = \varphi([x], [y])$. Hence $\operatorname{im}\varphi = \mathcal{Z}(\{w_{ij}w_{kl} - w_{il}w_{kj}\})$ is closed. The same computation shows φ is injective, since $[x]$ and $[y]$ are recovered from w up to scalars.

Closed subsets correspond. If $\varphi(X)$ is closed in $\operatorname{im}\varphi$, then $X = \varphi^{-1}(\varphi(X))$ is closed because φ is continuous. Conversely let X be closed, cut out by bihomogeneous equations $g_i(u; v)$. By the degree-balancing displayed above we may assume each g_i has the same degree r in the u and in the v, and a bihomogeneous polynomial of bidegree (r, r) is a polynomial in the products $u_i v_j$, hence a form in the w_{ij}. Those forms cut out $\varphi(X)$ inside $\operatorname{im}\varphi$, as we sought to show.

Before leaving products, three facts about them are needed later, and none is formal. The first says the maps one expects to have are regular, the second is general topology in geometric clothing, and the third says that a product of irreducible varieties does not fall apart.

Proposition 40.1.4: Projections and Slices Are Regular

Let $X \subseteq \mathbb{P}_k^n$ and $Y \subseteq \mathbb{P}_k^m$ be quasi-projective varieties. Then both projections $\pi_1 \colon X \times Y \to X$ and $\pi_2 \colon X \times Y \to Y$ are regular. Moreover, for fixed $y \in Y$ the slice map $j_y \colon X \to X \times Y$, $x \mapsto (x, y)$, is an isomorphism onto $X \times \{y\}$, and symmetrically $i_x \colon Y \to X \times Y$ is an isomorphism onto $\{x\} \times Y$.

***Proof*:**

Work in the Segre coordinates $w_{ij} = x_i y_j$. Fix a and let $W_a \subseteq X \times Y$ be the open set where some $w_{aj} \neq 0$, which is where $x_a \neq 0$. On W_a,

$$[\, w_{a0} : \cdots : w_{am} \,] = [\, x_a y_0 : \cdots : x_a y_m \,] = [\, y_0 : \cdots : y_m \,]$$

so π_2 is given on W_a by $m + 1$ linear forms in the w_{ij}, not all zero there. The W_a cover $X \times Y$ and the formulas agree on overlaps, so π_2 is regular; the same argument with $[\, w_{0b} : \cdots : w_{nb} \,]$ handles π_1.

For the slices, fix $y = [b_0 : \cdots : b_m]$ and write $j_y(x) = [\, x_i b_j \,]$. The entries are linear forms in x, not all identically zero since some $b_j \neq 0$, so j_y is regular. Its image is $X \times \{y\}$, and $\pi_1 \circ j_y$ is the identity of X while $j_y \circ \pi_1$ is the identity of $X \times \{y\}$, so the two are mutually inverse isomorphisms. The map i_x is symmetric, as we sought to show.

Lemma 40.1.5: A Cover by Overlapping Irreducibles

Let Z be a topological space covered by open sets V_α, each irreducible, with $V_\alpha \cap V_\beta \neq \emptyset$ for every pair. Then Z is irreducible.

***Proof*:**
A space is irreducible exactly when each of its nonempty open subsets is dense. First, every V_α is dense in Z: given β, the set $V_\beta \cap V_\alpha$ is nonempty and open in V_β, hence dense in the irreducible V_β, so $V_\beta \subseteq \overline{V_\alpha}$; as the V_β cover Z this forces $\overline{V_\alpha} = Z$.

Now let $W \subseteq Z$ be nonempty and open. It meets some V_α, and $W \cap V_\alpha$ is a nonempty open subset of the irreducible V_α, hence dense in it, so $\overline{W} \supseteq V_\alpha$. Closures are closed, so $\overline{W} \supseteq \overline{V_\alpha} = Z$, as we sought to show.

Proposition 40.1.6: A Product of Irreducibles Is Irreducible

Let X and Y be irreducible quasi-projective varieties. Then $X \times Y$ is irreducible.

***Proof*:**
By proposition 40.1.4 each slice $\{x\} \times Y$ is isomorphic to Y, hence irreducible, and each slice map j_y is regular. Suppose $X \times Y = Z_1 \cup Z_2$ with both Z_i closed. For fixed x the slice $\{x\} \times Y$ is irreducible and is covered by the two relatively closed sets $Z_i \cap (\{x\} \times Y)$, so it lies wholly inside Z_1 or wholly inside Z_2. Set

$$X_i = \{x \in X \mid \{x\} \times Y \subseteq Z_i\}$$

so that $X = X_1 \cup X_2$. Each X_i is closed, being the intersection $X_i = \bigcap_{y \in Y} j_y^{-1}(Z_i)$ of closed sets. Since X is irreducible, $X = X_i$ for one of the two, and then $X \times Y = Z_i$, as we sought to show.

40.2 Completeness of Projective Varieties

The image of a regular map need not be closed: example 32.1.4 took $X = \mathcal{Z}(xy - 1)$, $Y = \mathbb{A}^1_k$ and $\pi(a, b) = a$, whose image is $\mathbb{A}^1_k \setminus \{0\}$. However, the image of a projective variety will always be projective! If the reader has done some analysis this should remind the reader of the fact that the image of compact sets are compact. Though all affine and projective algebraic sets are compact (they are closed subsets of the compact space $\mathbb{A}^n_k$ or $\mathbb{P}^n_k$), projective varieties behave more like compact sets. Scheme theory draws the distinction by calling projective varieties *proper*[1]. To see this, we require a few lemmas:

[1] In analysis a map is proper if the pre-image of every compact set is compact

Lemma 40.2.1: Graph of Regular Mapping

Let $\varphi : X \to Y$ be a regular mapping between quasi-projective varieties. Then the graph

$$\Gamma(\varphi) = \{(x, \varphi(x)) \mid x \in X\}$$

is closed in $X \times Y$

If the Zariski topology was Hausdorff, then we could have concluded using classical topological results, however some more care has to be done as the topology is not Hausdorff.

***Proof*:**
First, we may take Y to be a projective space; for an appropriate choice of m, $Y \subseteq \mathbb{P}^m_k$, so that $X \times Y \subseteq X \times \mathbb{P}^m_k$. Then by proposition 33.2.7, φ determines a mapping $\overline{\varphi} : X \to \mathbb{P}^m_k$ and $\Gamma_\varphi = \Gamma_{\overline{\varphi}} \cap (X \times Y)$. As $X \times Y$ is closed in $X \times \mathbb{P}^m_k$ by proposition 40.1.3, closed then Γ_f is closed.

Next define $(\overline{\varphi}, \mathrm{id}) \colon X \times \mathbb{P}^m_k \to \mathbb{P}^m_k \times \mathbb{P}^m_k$. Then $\Gamma_{\overline{\varphi}}$ is the inverse image of the diagonal $\Delta = \Gamma_{\mathrm{id}}$ under this map. As this is a continuous map, the inverse image of a closed set is closed, and hence it suffices to show that Γ_i is closed.

Finally, the diagonal $\Delta \subseteq \mathbb{P}^m_k \times \mathbb{P}^m_k$ consists of the pairs $([u_0 : \cdots : u_m], [v_0 : \cdots : v_m])$ with $u_i v_j = u_j v_i$ for all i, j, which under the Segre embedding are exactly the points where the corresponding 2×2 minors vanish. By proposition 40.1.3 that is a closed condition, so Δ is closed, hence so is $\Gamma_{\overline{\varphi}}$ and therefore Γ_φ, completing the proof.

Proposition 40.2.2: Projection of Projective Variety

Let X be a projective variety and Y a quasi-projective variety. Then the projection map:

$$\pi_2 : X \times Y \to Y$$

is a closed map (the image of a closed set is closed)

Hence, the projection of a projective variety can always be written as a system of polynomial equations! This is not true for affine varieties: take $X = \mathcal{Z}(xy - 1)$ and $Y = \mathbb{A}^1_k$

***Proof*:**
Let us first reduce the problem: as $X \subseteq \mathbb{P}^n_k$ is closed, $X \times Y \subseteq \mathbb{P}^n_k \times Y$ is a closed subset, hence if $Z \subseteq X$ is closed, it is closed in $Z \times Y \subseteq \mathbb{P}^n_k \times Y$, and so it is enough to show it for the case of $X = \mathbb{P}^n_k$. Next, as being closed is affine local, it suffices to cover Y by affine open subsets U_i and prove the theorem on each of these. Thus, it suffices to assume that Y is an affine variety. Finally, as Y is closed in $\mathbb{A}^m_k$, $\mathbb{P}^n_k \times Y \subseteq \mathbb{P}^n_k \times \mathbb{A}^m_k$ is closed, and so we can reduce further to $Y = \mathbb{A}^m_k$.

Thus, let us characterize closed subsets $Z \subseteq \mathbb{P}^n_k \times \mathbb{A}^m_k$. By definition of the Zariski topology, and by a simple generalization of proposition 40.1.3, we see that Z is closed if and only if it is the zero set of the collection of polynomials

$$g_i([u_0 : \cdots : u_n], y_1, ..., y_m) \qquad 1 \leq i \leq t$$

In particular, we do not need to create two zero sets for each component and check that the their product produces Z: we can directly work with a set of polynomials. Let us write $g_i(u;y)$ to represent these polynomials with the two different inputs.

Now, take any $y_0 \in \mathbb{A}_k^m$. Then $\pi^{-1}(y_0)$ consists of all solutions (whether empty or non-empty) to the system of equations

$$g_i(u;y_0) = 0 \qquad 1 \leq i \leq t$$

Take the collection of y_0 such that the system of polynomials equations $g_i(u;y_0) = 0$ has a nonzero solution; call this collection $T \subseteq \mathbb{A}_k^m$. We want to show that T is closed, for then the projection π_2 is a closed map. By lemma 38.4.2, the system of polynomials equations $g_i(u;y_0) = 0$ has a nonzero solution if and only if:

$$I_s \not\subseteq (g_1(u,y_0),...,g_t(u,y_0)) \qquad \forall s \in \mathbb{N}$$

where I_s is the irrelevant ideal of degree $s \geq 1$. Thus it suffices to show that the set T_s of points $y_0 \in \mathbb{A}_k^m$ for which $I_s \not\subseteq (g_1(u,y_0),...,g_t(u,y_0))$ is closed, in particular if we find polynomial equations whose zero set is T_s, then as $T = \bigcap_s T_s$, T is closed which completing the proof.

To that end, let k_i be the homogeneous degree of $g_i(u;y)$ in the u_j variables. Let $(M^\alpha)_\alpha$ be the monomials of degree s in $u_0,...,u_n$ with some total ordering (note this set is finite). Then $I_s \subseteq (g_1(u,y_0),...,g_t(u,y_0))$ if and only if each monomial M^α can be expressed as:

$$M^\alpha = \sum_{i=1}^{t} g_i(u,y_0)F_{i,\alpha}(u) \tag{40.2}$$

As each g_i has homogeneous degree k_i, it must be that $F_{i,\alpha}$ has degree $s-k_i$ or $F_{i,\alpha} = 0$ if $k_i > s$. Then we may replace $F_{i,\alpha}$ with elements in $(N_i^\beta)_\beta$ which are monomial of degree $s-k_i$ written in some total ordering. Then (40.2) holds if and only if M^α is a linear combination of the polynomials $g_i(u,y_0)N_i^\beta$. As this is true for each M^α, this is equivalent to saying that the polynomials $g_i(u,y_0)N_i^\beta$ span the entire vector space S of homogeneous polynomials of degree s in $u_0,...,u_n$. As $I_s \not\subseteq (g_1(u,y_0),...,g_t(u,y_0))$, we have that the $g_i(u,y_0)N_i^\beta$ *do not* span S.

Now, take the matrix $(a_{\alpha\beta})$ that represents the coefficients of the M^α terms as a linear combination of the $g_i(u,y_0)N_i^\beta$. As not all M^α can be written as such terms, this matrix cannot be full rank. Hence all $\sigma \times \sigma$ minors (where $\sigma = \dim_k S$) are polynomials in the coefficients of the polynomials $g_i(u,y_0)$, in particular they are polynomials in the coordinates of the point y_0. So T_s is cut out by polynomial equations in y_0, hence closed.

Thus, since the arbitrary intersection of closed sets is closed $T = \bigcap_s T_s$ is closed, completing the proof.

For those interested in algebraic geometry, the above proof is in part in proving that projective varieties are *proper*.

Corollary 40.2.3: Image of Projective Variety is Closed

Let $f : X \to Y$ be a regular map where X is a projective variety. Then $\mathrm{im} f$ is closed

***Proof*:**
Let $\pi : X \times Y \to Y$ be the natural projection. Consider the graph $\Gamma_f \subseteq X \times Y$ of lemma 40.2.1. Then:

$$\mathrm{im} f = \pi(\Gamma_f)$$

and hence by proposition 40.2.2 $\mathrm{im} f$ is closed, completing the proof.

We can finally rigorously show that the collection of regular functions on projective space, and more generally projective varieties, are only constant functions:

Corollary 40.2.4: Regular Function on Projective Variety

Let φ be a regular function on an irreducible projective variety. Then $\varphi \in k$, i.e. φ is constant.

***Proof*:**
Take $\varphi : X \to \mathbb{A}^1_k$. As $\mathbb{A}^1_k$ is dense in $\mathbb{P}^1_k$, there is a unique extension to a regular map $\overline{\varphi} : X \to \mathbb{P}^1_k$. As X is a projective variety, by corollary 40.2.3 $\overline{\varphi}(X) \subseteq \mathbb{P}^1_k$ is closed. Since $\overline{\varphi}(X) \subseteq \mathbb{A}^1_k$, the point at infinity is not in the image, so $\overline{\varphi}(X)$ is a *proper* closed subset of $\mathbb{P}^1_k$. The proper closed subsets of $\mathbb{P}^1_k$ are exactly the finite sets, so $\overline{\varphi}(X)$ is finite. (It cannot be all of $\mathbb{A}^1_k$, which is not closed in $\mathbb{P}^1_k$.) Hence $\varphi(X)$ is a finite set of points. closed, their pre-image would make X the non-trivial union of closed sets, contradicting its irreducibility, and hence it must be that the image is a single point, in other words a constant, as we sought to show.

Corollary 40.2.5: Regular Map on Projective Variety

Let $f : X \to Y$ be a regular map from a projective variety to an affine variety. Then $\mathrm{im} f$ is a point

***Proof*:**
Take $f(x) = (\varphi_1(x), ..., \varphi_m(x))$ where each φ_i is a regular function. Then by corollary 40.2.4 these are all constant, but then

$$f(X) = (\alpha_1, ..., \alpha_m)$$

completing the proof.

40.2.6 Note: Completeness Is Elimination Theory The classical name for proposition 40.2.2 is *elimination theory*. Given equations in $x_1, \dots, x_n$ and $y_1, \dots, y_m$, one asks for the conditions on the y alone under which a solution in x exists; that is exactly asking for the image of a projection, and the theorem says the answer is again given by equations, provided the x range over projective space.
The classical tool is the resultant. For two one-variable polynomials

$$f = a_0 x^d + \cdots + a_d, \qquad g = b_0 x^e + \cdots + b_e$$

the resultant $\operatorname{Res}(f, g)$ is the determinant of the $(d + e) \times (d + e)$ Sylvester matrix in the coefficients, and it vanishes exactly when f and g have a common root, given a_0, b_0 not both zero. Since Res is a polynomial in the a_i and b_j, that is precisely a closed condition on the coefficients, and it eliminates x. Iterating in several variables is the classical proof of completeness, and section 19.6.3 develops the algebra.
The proof given above takes a different route, through lemma 38.4.2 and the irrelevant ideal, which is shorter and generalizes better. The resultant remains the computational tool: it is what a computer algebra system runs when asked to eliminate a variable, and example 42.4.1 could equally have been done by resultants.

40.3 Finite Maps

These maps shall be the mirror of integral extensions, and shall be one of the easiest examples of *proper morphisms* which is a somewhat complicated but fundamental type of morphism in scheme theory.

Definition 40.3.1: Finite Map [on Affine Varieties]

Let $f\colon X \to Y$ be a regular map of affine varieties with $f(X)$ dense in Y, so that the pullback $f^{\#}\colon k[Y] \hookrightarrow k[X]$ is injective. Then f is a *finite map* if $k[X]$ is integral over $f^{\#}(k[Y])$.

Example 40.3.2: Finite and Non-Finite Maps

1. *A finite map.* $\varphi\colon \mathbb{A}^1_k \to \mathbb{A}^1_k$, $\varphi(x) = x^2$. On coordinate rings it is $k[y] \to k[x]$, $y \mapsto x^2$, and $k[x]$ is generated as a $k[y]$-module by 1 and x, since $x^2 = y$. So the map is finite, and its fibres have one or two points: two over $a \neq 0$, one over 0.

2. *Finite maps are closed and surjective.* The image of φ is all of $\mathbb{A}^1_k$, as proposition 40.3.3 requires, because every a has a square root in the algebraically closed k.

3. *A non-example with finite fibres.* The projection $\mathcal{Z}(xy - 1) \to \mathbb{A}^1_k$, $(x, y) \mapsto x$, has fibres of size at most one, yet it is not finite: $k[x, x^{-1}]$ is not a finitely generated $k[x]$-module, since no finite set of Laurent polynomials spans all negative powers. Its image misses the origin, so it is not even surjective. Finiteness is strictly stronger than having finite fibres.

4. *An open immersion is almost never finite.* The inclusion $D(x) \hookrightarrow \mathbb{A}^1_k$ is the previous example in disguise, by example 31.3.6(1).

The composition of finite maps is finite. If $f\colon X \to Y$ is finite then its fibres are finite. A reasonable assumption would be that a map is finite if and only if its fibers are finite, but that is not the case: an example of a non-finite map would be $\pi_1 : V(xy-1) \to \mathbb{A}^1_k$ as $k[x] \hookrightarrow k[x, 1/x]$ is not an integral extension. Instead, one way of thinking of a finite map $f : X \to Y$ is that given an element $y \in Y$, as y is moved around in Y and we look at $f^{-1}(y)$, none of the roots could tend to infinity, that is none can disappear. This intuition is captured by the following proposition:

Proposition 40.3.3: Finite Maps Are Surjective

Let $f : X \to Y$ be a finite map between affine varieties. Then f is surjective.

The tool is the lying-over property of integral extensions (theorem 26.3.3), in the following form: if B is integral over a subring A and $\mathfrak{a} \subsetneq A$ is a *proper* ideal, then $\mathfrak{a}B \neq B$. Equivalently, a proper ideal of A cannot generate the unit ideal of B. This is what stops a fibre from being empty.

***Proof*:**
Let $f : X \to Y$ be a finite map between affine varieties. Take any $y \in Y$ and let $\mathfrak{m}_y \subseteq k[Y]$ be the functions that take the value 0 at y: if $f \in \mathfrak{m}_y$, then $f(y) = 0$. Let $x_1, ..., x_n$ be coordinate functions on Y and $y = (\alpha_1, ..., \alpha_n)$ so that

$$\mathfrak{m}_y = (x_1 - \alpha_1, \dots, x_n - \alpha_n)$$

Then the equations of the variety $f^{-1}(y)$ have the form:

$$f^{\#}(x_1) = \alpha_1, \quad \dots, \quad f^{\#}(x_n) = \alpha_n$$

By the Nullstellensatz, $f^{-1}(y) = \emptyset$ if and only if the elements $f^{\#}(x_i) - \alpha_i$ generate the unit ideal, that is:

$$(f^*(x_1) - \alpha_1, ..., f^*(x_n) - \alpha_n) = k[X]$$

Viewing $k[Y]$ as a subring of $k[X]$, we see that the above is equivalent to:

$$(x_1 - \alpha_1, \dots, x_n - \alpha_n)\, k[X] = k[X]$$

In other words, $f^{-1}(y) = \emptyset$ would force $\mathfrak{m}_y k[X] = k[X]$. But $\mathfrak{m}_y$ is maximal, hence a proper ideal of $k[Y]$, and $k[X]$ is integral over it, so lying over gives $\mathfrak{m}_y k[X] \neq k[X]$. The two are contradictory, so $f^{-1}(y) \neq \emptyset$. As y was arbitrary, f is surjective, completing the proof.

Corollary 40.3.4: Finite Maps Are Closed Maps

Let $f : X \to Y$ be a finite map between affine varieties. Then f is a closed map.

***Proof*:**
It suffices to check on irreducible closed subsets $Z \subseteq X$. By the above theorem the restriction of f to Z, $\overline{f|_Z} : Z \to \overline{f(Z)}$, is a finite map between affine varieties, and so by surjectivity we get $f(Z) = \overline{f(Z)}$, but then $f(Z)$ is closed, completing the proof.

Let us now build-up to defining finite maps for quasi-projective varieties. For that, we start by showing that finiteness is a local property:

Lemma 40.3.5: Finiteness is Local

Let $f : X \to Y$ be a regular map of affine varieties. Then if for every point $y \in Y$, there is an affine neighborhood U of y such that $V = f^{-1}(U)$ is affine and $f : V \to U$ is finite, then f is finite

***Proof*:**
Let $k[Y] = A$ and $k[X] = B$. Take the principal open set around each point of Y, and as Y is compact take a finite subcover, label these $D(g_\alpha)$ so that $Y = \bigcup_\alpha D(g_\alpha)$. Then:

$$V_\alpha = f^{-1}(D(g_\alpha)) = D(f^\#(g_\alpha))$$

and

$$k[D(g_\alpha)] = A[1/g_\alpha] \qquad k[V_\alpha] = B[1/f^\#(g_\alpha)]$$

As f is finite on this chart, $B[1/g_\alpha]$ is a finite module over $A[1/g_\alpha]$; fix a finite generating set $w_{i,\alpha}$. (Generating set, not basis: a finite module over a ring need not be free, and freeness is never used below.) We may take $w_{i,\alpha} \in B$, since clearing the denominator of $w_{i,\alpha}/g_\alpha^{m_i}$ multiplies by a unit of $A[1/g_\alpha]$ and so preserves generation.

Now take the union of all these finite sets. We claim they generate B as an A-module. To see this, take any $b \in B$. Then for each α we can write it as :

$$b = \sum_i \frac{a_{i,\alpha}}{g_\alpha^{n_\alpha}} w_{i,\alpha}$$

As the $g_\alpha^{n_\alpha}$ generate the unit ideal of A (the sets $D(g_\alpha)$ cover Y), there exists $h_\alpha \in A$ such that

$$\sum_\alpha g_\alpha^{n_\alpha} h_\alpha = 1$$

Thus:

$$b = b \sum_\alpha g_\alpha^{n_\alpha} h_\alpha = \sum_i \sum_\alpha a_{i,\alpha} h_\alpha w_{i,\alpha}$$

which exhibits an arbitrary $b \in B$ as an A-combination of the $w_{i,\alpha}$. Hence B is a finite A-module and f is finite, as we sought to show.

Thus, we can define finite maps for quasi-projective varieties:

Definition 40.3.6: Finite Map [on Quasi-Projective Varieties]

Let $f : X \to Y$ be a regular map between quasi-projective varieties. Then f is said to be *finite* if any point $y \in Y$ has an affine local neighborhood V such that $U = f^{-1}(V)$ is affine and $f : U \to V$ is a finite map between affine varieties.

Naturally, $f^{-1}(y)$ is finite for every $y \in Y$, and it follows easily that any finite map is surjective. Note that the density condition is now a local condition. One consequence of these results that we shall not prove is that if $f : X \to Y$ between quasi-projective is a regular map (not necessarily finite) and $f(X)$ dense in Y, then $f(X)$ contains an open subset of Y. This is *not* true in analysis, the canonical example being the wrapping of the real line around the torus with an irrational period

which will be a dense map with empty interior.

40.4 Noether Normalization, Geometrically

An important culminating result is that every irreducible projective variety is in some way only a "finite extension" from projective space. These results reduce many arguments about irreducible varieties to arguments about affine or projective space. These ideas return in scheme-theoretic form in *Algebraic Geometry* [13]. We first need a technical lemma:

40.4.1 Normalization and Singularities Note that this is *not* to be confused with normalization of singularities! Rather confusingly, normalization of singularities shall be the map in the *opposite direction* to the normalization map that will be defined here. The two uses of the word are unrelated, and it is not the case that a normal resolution of singularities results in a map $\mathbb{A}^n_k \to X$ or $\mathbb{P}^n_k \to X$ for a variety X (where the normalization map we shall do will be map of the form $X \twoheadrightarrow \mathbb{A}^n_k$ or $X \twoheadrightarrow \mathbb{P}^n_k$).

Lemma 40.4.2: Projection is Finite Mapping

Let X be closed in $\mathbb{P}^n$ with $X \subset \mathbb{P}^n \setminus E$, where E is a d-dimensional linear subspace. Then the projection $\pi : X \to \mathbb{P}^{n-d-1}$ with center at E determines a finite mapping $X \to \pi(X)$.

***Proof*:**
Let $y_0, \dots, y_{n-d-1}$ be homogeneous coordinates in $\mathbb{P}^{n-d-1}$ and let π be given by the formulae $y_j = L_j(x)$, $x \in X$ $(j = 0, \dots, n-d-1)$. Naturally, $U_i = \pi^{-1}(\mathbb{A}^{n-d-1}) \cap X$ is given by the condition $L_i(x) \neq 0$ and is an affine open subset of X. We want to show that $\pi : U_i \to \mathbb{A}^{n-d-1} \cap \pi(X)$ is a finite mapping. To that end, first note that every function $g \in k[U_i]$ is of the form $g = G_i(x_0, \dots, x_n)/L_i^m$, where G_i is a form of degree m. Consider the mapping $\pi_1 : X \to \mathbb{P}^{n-d} : z_j = L_j^m(x)$ $(j = 0, \dots, n-d-1)$, $z_{n-d} = G_i(x)$, where $z_0, \dots, z_{n-d}$ are homogeneous coordinates in $\mathbb{P}^{n-d}$. It is a regular mapping and its image $\pi_1(X)$ is closed in $\mathbb{P}^{n-d}$. Let $F_1 = \cdots = F_s = 0$ be its equations. Since $X \subset \mathbb{P}^n - E$, the forms $L_i (i = 0, \dots, n-d-1)$ do not vanish simultaneously on X. Hence the point $[0 : \cdots : 0 : 1]$ is not contained in $\pi_1(X)$, in other words, that the equations $z_0 = \cdots = z_{n-d-1} = F_1 = \cdots = F_s = 0$ have no solution in $\mathbb{P}^{n-d}$. Hence by lemma 38.4.2, for some $l > 0$:

$$(z_0, \dots, z_{n-d-1}, F_1, \dots, F_s) \supseteq \mathfrak{m}^l$$

in particular, $z_{n-d}^l \in (z_0, \dots, z_{n-d-1}, F_1, \dots, F_s)$. This means that

$$z_{n-d}^l = \sum_{j=0}^{n-d-1} z_j H_j + \sum_{j=1}^{s} F_j P_j,$$

where H_j and P_j are polynomials. Denote by $H^{(q)}$ the homogeneous component of H of degree q. Then:

$$\Phi(z_0, \dots, z_{n-d}) = z_{n-d}^l - \sum z_j H_j^{(l-1)} = 0 \quad \text{on } \pi_1(X) \tag{40.3}$$

The homogeneous polynomial Φ is of degree l and as a polynomial in z_{n-d} it has the leading coefficient 1:

$$\Phi = z_{n-d}^l - \sum_{j=0}^{l-1} A_{l-j}(z_0, \dots, z_{n-d-1}) z_{n-d}^j \tag{40.4}$$

Substituting the transformation formulae for π_1 in (40.3) we find that $\Phi(L_0^m, \dots, L_{n-d-1}^m, G_i) = 0$ on X, with Φ of the form (40.4). Dividing this relation by L_i^{ml} we obtain the required relation

$$g^l + \sum_{j=0}^{l-1} A_{l-j}(x_0, \dots, 1, \dots, x_{n-d-1}) g^j = 0,$$

where $x_r = y_r/y_i$ are coordinates in $\mathbb{A}^{n-d-1}$. But then we have that the mapping is finite, completing the proof.

Theorem 40.4.3: Normalization of Projective Variety

Let X be an irreducible projective variety. Then there exists a finite mapping $\varphi : X \twoheadrightarrow \mathbb{P}_k^m$ for appropriate m.

***Proof*:**
Take $X \subseteq \mathbb{P}_k^n$. If $X = \mathbb{P}_k^n$ we are done so take $X \neq \mathbb{P}_k^n$. Take $x \in \mathbb{P}_k^n \setminus X$ and take the projection from x, $\varphi_x : X \to \mathbb{P}_k^{n-1}$. This map is regular by example 39.4.4, and the image is closed, hence projective. It is furthermore finite by lemma 40.4.2. If $\varphi(X) \neq \mathbb{P}_k^{n-1}$ we repeat the argument. is closed/finite. Each projection lowers the ambient dimension by one, so after finitely many steps the image fills its ambient space: the dimension cannot fall below $\dim X$, and a proper closed subvariety of the same dimension as its ambient is impossible by proposition 34.3.5. Composing the projections gives a finite surjection

$$\varphi \colon X \twoheadrightarrow \mathbb{P}_k^m \qquad m = \dim X$$

completing the proof.

Theorem 40.4.4: Normalization of Affine Variety

Let X be an irreducible affine variety. Then there exists a finite mapping $\varphi : X \twoheadrightarrow \mathbb{A}_k^m$ for appropriate m.

Note that this is the analog of Noether's Normalization theorem for rings that are finitely generated k-algebras without zero-divisors, and in fact can be proven using it: see the fifth exercise of exercise set 40.6.1.

***Proof*:**
Take $X \subseteq \mathbb{A}_k^n$ and suppose $X \neq \mathbb{A}_k^n$, the other case being trivial. Identify $\mathbb{A}_k^n$ with the chart $U_{n+1} \subseteq \mathbb{P}_k^n$. Then X is *closed in* $\mathbb{A}_k^n$, hence locally closed in $\mathbb{P}_k^n$, and we may take its projective closure $\overline{X}$.

Since X is a proper closed subvariety of $\mathbb{A}_k^n$ we have $\dim X < n$ by proposition 34.3.5, so $\overline{X}$ cannot contain the whole hyperplane at infinity; choose $x \in H_\infty$ with $x \notin \overline{X}$. Projecting from x

gives a finite map $\overline{X} \to \mathbb{P}_k^{n-1}$ by lemma 40.4.2, and since the centre lies at infinity the projection carries X into the affine chart, giving a finite map $X \to \mathbb{A}_k^{n-1}$.

Repeating as in theorem 40.4.3 yields a finite surjection

$$\varphi \colon X \twoheadrightarrow \mathbb{A}_k^m \qquad m = \dim X$$

completing the proof.

Thus, though not all varieties are rational, all varieties are a finite cover of affine or projective space, and hence the study of which varieties are not rational will naturally lead to the question of how far away are they from being rational[2]. More on this in the exercises.

Example 40.4.5: Finite Maps and Normalization

Consider the curve $f : \mathbb{A}_k^1 \to \mathbb{A}_k^2$ given by $f(t) = (t^2, t^3)$. This is associated to the pullback on coordinate rings $f^{\#} \colon k[x,y] \to k[t]$, $x \mapsto t^2$, $y \mapsto t^3$. Taking the quotient of the domain gives $k[x,y]/(x^3 - y^2) \cong k[t^2, t^3] \hookrightarrow k[t]$, which is injective but *not surjective*: nothing maps to t. As $(x^3 - y^2)$ is prime, we take the field of fraction and extend the map, which has $t^3/t^2 = t$ we have that $\mathrm{Frac}(k[t^2, t^3]) = k(t)$ giving a field isomorphism.

This is a 1-to-1 map. Define an n-to-1[a] map $f : \mathbb{A}_k^1 \to \mathbb{A}_k^2$ given by $t \mapsto (t^{2n}, t^{3n})$. Notice the image is the same. The global section's are also isomorphic as $k[t^2, t^3] \cong k[t^{2n}, t^{3n}]$. Thus the field of fractions are isomorphic, $k(t) \cong k(t^n)$. Working with a specific n-to-1 map, the field of fraction of the global section of the image is $k(t^n)$ which has index n in the field of fractions of the domain, namely $k(t)$. This reflects the geometric nature of finite maps in algebraic properties.

Notice that $x^2 - y^3$ forms a curve with a cusp; it has a singularity at $(0,0)$. This curve maps onto

[a] note it is important to assume that either k is algebraically closed, or at minimum that k contains all the roots of unity

40.5 Dimension of Fibres

A map between varieties should decrease dimension by the dimension of its fibres, and this section makes that precise. The statement has three parts, and only the middle one is delicate: fibres can jump *up* in dimension over special points, but never down.

Theorem 40.5.1: Dimension of Fibres

Let $f \colon X \to Y$ be a dominating regular map of irreducible varieties, with $\dim X = n$ and $\dim Y = m$. Then:

1. $m \leq n$;
2. for every $y \in f(X)$, every irreducible component of the fibre $f^{-1}(y)$ has dimension at least $n - m$;
3. there is a nonempty open $U \subseteq Y$ such that $\dim f^{-1}(y) = n - m$ for every $y \in U$.

[2] Chevalley's theorem (chapter 41) is the statement in this direction that survives without the finiteness hypothesis: the image of a regular map is constructible even when it is neither open nor closed.

***Proof*:**

(1). Since f is dominating, $f^{\#}$ embeds $k(Y)$ into $k(X)$ by proposition 33.3.4(2), and transcendence degree cannot decrease under a field extension, so $m = \operatorname{trdeg}_k k(Y) \leq \operatorname{trdeg}_k k(X) = n$.

(2). The question is local on Y, so replace Y by an affine neighbourhood of y and X by its preimage. The local ring $\mathcal{O}_y(Y)$ has dimension m, so it admits a system of parameters (definition 29.5.1): m functions $g_1, \ldots, g_m$ generating an ideal whose zero set is $\{y\}$ near y. Then, near any point of the fibre,

$$f^{-1}(y) = \mathcal{Z}\big(f^{\#}(g_1), \ldots, f^{\#}(g_m)\big)$$

is cut out of X by m equations. Applying theorem 34.4.1 once for each equation drops the dimension by at most one each time, so every component of the result has dimension at least $n - m$.

(3). Choose affine open sets so that f corresponds to an injection $k[Y] \hookrightarrow k[X]$ of finitely generated domains. Over the fraction field $K = k(Y)$, the ring $k[X] \otimes_{k[Y]} K$ is a finitely generated K-algebra of dimension $n - m$, since its fraction field is $k(X)$ and $\operatorname{trdeg}_K k(X) = n - m$. Apply Noether normalization over K: there are $t_1, \ldots, t_{n-m}$ with $k[X] \otimes K$ finite over $K[t_1, \ldots, t_{n-m}]$. Each of the finitely many integral equations involved has coefficients in $k(Y)$; let $g \in k[Y]$ be a common denominator. Then over the open set $U = D(g)$,

$$k[X]_g \text{ is finite over } k[Y]_g[t_1, \ldots, t_{n-m}]$$

Hence for $y \in U$ the fibre $f^{-1}(y)$ is finite over $\mathbb{A}_k^{n-m}$, and a finite surjection preserves dimension by proposition 34.2.5, so $\dim f^{-1}(y) = n - m$, as we sought to show.

Part (2) is the useful half in practice, and it is worth saying what it does not claim. It gives a *lower* bound on fibre dimension, valid at every point; the matching upper bound holds only generically, which is part (3). Fibres genuinely do jump.

Example 40.5.2: Fibres That Jump

Let $X = \mathcal{Z}(xz - y) \subseteq \mathbb{A}_k^3$ and $f\colon X \to \mathbb{A}_k^1$ the projection $(x, y, z) \mapsto x$. Then X is isomorphic to $\mathbb{A}_k^2$ with coordinates (x, z), since y is determined, so $n = 2$ and $m = 1$, giving an expected fibre dimension of 1. Over $x = a \neq 0$ the fibre is the line $\{(a, az, z) \mid z \in k\}$, of dimension 1 as predicted. Over $x = 0$ it is $\{(0, 0, z) \mid z \in k\}$, again dimension 1.

Now blow the picture up: let $g\colon \mathbb{A}_k^2 \to \mathbb{A}_k^2$ be $(u, v) \mapsto (u, uv)$. Here $n = m = 2$, so the expected fibre dimension is 0. Over (a, b) with $a \neq 0$ the fibre is the single point $(a, b/a)$; but over $(0, 0)$ the fibre is the whole line $\{(0, v) \mid v \in k\}$, of dimension 1. The fibre has jumped, exactly as part (2) permits and part (3) confines to a proper closed subset. This map is the restriction to one chart of the blow-up of chapter 47, computed there as proposition 47.1.2(1).

A count that will be used in chapter 41 follows immediately by adding dimensions along a map whose fibres are all of the same dimension.

Corollary 40.5.3: Dimension of a Total Space

Let $f\colon X \to Y$ be a surjective regular map of irreducible varieties whose fibres are all irreducible of the same dimension d. Then $\dim X = \dim Y + d$.

***Proof*:**
By theorem 40.5.1(3) the generic fibre has dimension $\dim X - \dim Y$, and by hypothesis every fibre has dimension d, so $\dim X - \dim Y = d$, completing the proof.

Applied to a projection, this settles the dimension of a product, which chapter 34 could only gesture at because products of projective varieties were not yet available.

Corollary 40.5.4: Dimension of a Product

Let X and Y be irreducible quasi-projective varieties. Then $\dim(X \times Y) = \dim X + \dim Y$.

***Proof*:**
$X \times Y$ is irreducible by proposition 40.1.6, and the projection $\pi\colon X \times Y \to X$ is a surjective regular map whose fibre over x is the slice $\{x\} \times Y \cong Y$, irreducible of dimension $\dim Y$ at every point. Corollary 40.5.3 applies and gives the claim.

40.6 The Dimension of an Intersection

Theorem 34.4.1 says that cutting an affine variety by one equation costs at most one dimension. Iterating it bounds the dimension of an intersection, but only when one of the two varieties is cut out by as many equations as its codimension, and that fails in general: the twisted cubic of example 38.3.7 has codimension two in $\mathbb{P}^3_k$ and needs three equations. The repair is to intersect with the diagonal instead, and it needs nothing now that products are available.

Proposition 40.6.1: The Affine Dimension Theorem

Let $X, Y \subseteq \mathbb{A}^n_k$ be irreducible affine varieties with $\dim X = r$ and $\dim Y = s$. Then every irreducible component of $X \cap Y$ has dimension at least $r + s - n$.

***Proof*:**
Let $\Delta = \{(a, a) \mid a \in \mathbb{A}^n_k\} \subseteq \mathbb{A}^{2n}_k$ be the diagonal, which is $\mathcal{Z}(x_1 - y_1, \dots, x_n - y_n)$, cut out by exactly n equations. The map $a \mapsto (a, a)$ is an isomorphism

$$X \cap Y \xrightarrow{\sim} (X \times Y) \cap \Delta$$

with inverse the first projection, both regular.

Now $X \times Y$ is irreducible by proposition 40.1.6 and has dimension $r + s$ by corollary 40.5.4. Cutting it by the n equations one at a time and applying theorem 34.4.1 at each step, every component of the result has dimension at least $r + s - n$, since each equation costs at most one dimension: an equation either vanishes identically on a component, leaving it untouched, or cuts

it by exactly one. Transporting through the isomorphism gives the claim, as we sought to show.

Passing to affine cones turns this into the projective statement, and the projective statement is strictly stronger: it also asserts that the intersection is nonempty.

Proposition 40.6.2: Dimension of the Affine Cone

Let $\emptyset \neq V \subseteq \mathbb{P}^n_k$ be a projective variety. Then $C(V)$ is an irreducible affine variety and

$$\dim C(V) = \dim V + 1$$

***Proof*:**
Irreducibility: $\mathcal{I}_{\mathbb{A}}(C(V)) = \mathcal{I}_{\mathbb{P}}(V)$ by proposition 38.3.2, and the latter is prime because V is a variety, so $k[C(V)] = S(V)$ is a domain.

For the dimension, choose a linear form t not vanishing identically on V, possible since $V \neq \emptyset$. Every element of $\mathrm{Frac}(S(V))$ is a ratio f/g of homogeneous elements, and

$$\frac{f}{g} = \frac{f/t^{\deg f}}{g/t^{\deg g}} \cdot t^{\deg f - \deg g}$$

exhibits it as a rational function of t with coefficients in the degree-zero part, which is $k(V)$ by definition 39.2.4. So $\mathrm{Frac}(S(V)) = k(V)(t)$, and t is transcendental over $k(V)$ because it has degree 1 while $k(V)$ sits in degree 0. Hence

$$\dim C(V) = \mathrm{kdim} S(V) = \mathrm{trdeg}_k \mathrm{Frac}(S(V)) = \mathrm{trdeg}_k k(V) + 1 = \dim V + 1$$

using proposition 34.2.5 twice, as we sought to show.

Theorem 40.6.3: The Projective Dimension Theorem

Let $X, Y \subseteq \mathbb{P}^n_k$ be projective varieties with $\dim X = r$ and $\dim Y = s$. Then every irreducible component of $X \cap Y$ has dimension at least $r + s - n$. If moreover $r + s - n \geq 0$, then $X \cap Y \neq \emptyset$.

***Proof*:**
Pass to the affine cones in $\mathbb{A}^{n+1}_k$. By proposition 40.6.2 they are irreducible of dimensions $r+1$ and $s+1$, so proposition 40.6.1 says every component of $C(X) \cap C(Y)$ has dimension at least

$$(r+1) + (s+1) - (n+1) = r + s - n + 1$$

By proposition 38.3.2 the components of $C(X) \cap C(Y)$ other than the origin are the cones over the components of $X \cap Y$, whose dimensions are one less by proposition 40.6.2. That gives the bound $r + s - n$.

For nonemptiness, note that both cones contain the origin, so $C(X) \cap C(Y)$ is nonempty and the bound applies to a component through the origin: it has dimension at least $r + s - n + 1 \geq 1$. A variety of dimension at least 1 is not a single point, so that component contains some $a \neq 0$, and a determines a point of $\mathbb{P}^n_k$ lying on both X and Y, as we sought to show.

The nonemptiness clause is what separates projective space from affine space. Both cones always meet, at the origin; the content is that when the dimensions are large enough they meet in more than the origin. No such statement is available affinely: in $\mathbb{A}^2_k$ the parallel lines $\mathcal{Z}(y)$ and $\mathcal{Z}(y-1)$ have $r=s=1$ and $n=2$, so $r+s-n=0$, and they are disjoint.

Example 40.6.4: Dimension Counts in Projective Space

1. *Two curves in* $\mathbb{P}^2_k$. Here $r=s=1$ and $n=2$, so $r+s-n=0$ and any two projective plane curves meet. Chapter 43 refines this into a count of the intersection points; the present theorem gives only that there is one, but it needs no hypothesis beyond dimension.
2. *A curve and a surface in* $\mathbb{P}^3_k$. With $r=1$, $s=2$, $n=3$ the bound is 0, so a curve and a surface in $\mathbb{P}^3_k$ always meet.
3. *Two curves in* $\mathbb{P}^3_k$. Now $r+s-n=-1$ and the theorem says nothing, correctly: two disjoint lines in $\mathbb{P}^3_k$ exist, as exercise set 38.5.1(4) exhibits.
4. *Hypersurfaces.* If $Y=\mathcal{Z}(F)$ is a hypersurface then $s=n-1$ and the bound reads $r-1$, with nonemptiness as soon as $\dim X\geq 1$. So a projective variety of positive dimension meets every hypersurface, which is another way of seeing why it carries no nonconstant regular function.

Exercise 40.6.1

1. Show that the image of the Segre embedding $\mathbb{P}^1_k\times\mathbb{P}^1_k\to\mathbb{P}^3_k$ is the quadric $\mathcal{Z}(w_{00}w_{11}-w_{01}w_{10})$, and that it contains two families of pairwise disjoint lines. Deduce, using exercise set 38.5.1(4), that this quadric is not isomorphic to $\mathbb{P}^2_k$.
2. Show that a variety that is both projective and affine is a single point.
3. Show that the map $\mathbb{A}^1_k\to\mathbb{A}^1_k$, $x\mapsto x^2$, is finite, and that the inclusion $\mathbb{A}^2_k\setminus\{0\}\hookrightarrow\mathbb{A}^2_k$ is not. For the second, which hypothesis of proposition 40.3.3 fails?
4. Exhibit a finite surjection $\mathcal{Z}(xy-1)\to\mathbb{A}^1_k$, and check directly that it is finite by writing the coordinate ring as a module over the image.
5. Prove the affine normalization theorem using Noether's normalization theorem (theorem 32.4.1): every affine variety admits a finite surjective map onto some $\mathbb{A}^m_k$, with m its dimension.
6. For $f\colon\mathbb{A}^2_k\to\mathbb{A}^2_k$, $(u,v)\mapsto(u,uv)$, compute every fibre and verify all three parts of theorem 40.5.1 by hand. Which part fails if the word "component" is dropped from part (2)?
7. Using corollary 40.5.4, compute $\dim(\mathbb{P}^n_k\times\mathbb{P}^m_k)$ and check the answer against the Segre embedding for $n=m=1$.
8. Show that the two projections $\mathbb{P}^1_k\times\mathbb{P}^1_k\to\mathbb{P}^1_k$ have all fibres isomorphic to $\mathbb{P}^1_k$, and use corollary 40.5.3 to recover the dimension of the product.

41

Projective Embeddings and Constructible Sets

Projective space carries more embeddings of itself than the linear ones, and the useful ones turn products, hypersurfaces, and linear subspaces into points of a larger projective space. This chapter collects them: the Veronese embedding, which linearizes degree, and the Plücker embedding, which realizes the Grassmannian of d-planes as a projective variety.

Then comes Chevalley's theorem. The image of a regular map is neither open nor closed in general, but it is always constructible, a finite union of locally closed sets, and that is the correct replacement for the closedness that chapter 40 gives only in the projective case.

The chapter ends by putting the two halves together. Counting the lines that lie on a cubic surface needs the Grassmannian to parameterize the lines, projective space to parameterize the surfaces, and theorem 40.5.1 to conclude that the count is finite. It is the first argument in this book where the answer is a number nobody could have guessed.

41.1 The Veronese Embedding

A hypersurface of degree d in $\mathbb{P}^n$ is cut out by one equation, but that equation is not linear, and linear conditions are the ones that are easy to count. The Veronese embedding trades the degree for a dimension: it realizes $\mathbb{P}^n$ inside a much larger projective space in such a way that degree-d hypersurfaces downstairs become *hyperplane sections* upstairs.

Definition 41.1.1: Veronese Embedding

Fix $n, d \geq 1$ and let $M_0, \dots, M_N$ be the monomials of degree d in $x_0, \dots, x_n$, in some fixed order, where

$$N = \binom{n+d}{d} - 1$$

The *Veronese embedding* of degree d is

$$v_d \colon \mathbb{P}^n_k \to \mathbb{P}^N_k \qquad v_d([x_0 : \cdots : x_n]) = [M_0(x) : \cdots : M_N(x)]$$

The map is well defined: every M_i is homogeneous of the same degree d, so scaling x by λ scales every coordinate by λ^d, and the M_i never vanish simultaneously, since x_j^d is among them and some $x_j \neq 0$.

Theorem 41.1.2: The Veronese Is a Closed Embedding

v_d is injective, its image $V_{n,d} = v_d(\mathbb{P}^n_k)$ is closed in $\mathbb{P}^N_k$, and v_d is an isomorphism onto its image.

***Proof*:**

Injective. Write z_α for the coordinate of $\mathbb{P}^N$ attached to the monomial x^α. Suppose $v_d(x) = v_d(y)$. Some $x_j \neq 0$, so $z_{de_j} \neq 0$ at that point, hence $y_j \neq 0$ as well. Rescaling, take $x_j = y_j = 1$. Then the coordinate attached to $x_j^{d-1} x_i$ reads off x_i and y_i directly, so $x = y$.

Closed. The image satisfies the relations

$$z_\alpha z_\beta = z_\gamma z_\delta \qquad \text{whenever } \alpha + \beta = \gamma + \delta$$

since both sides equal $x^{\alpha+\beta}$. Conversely, suppose z satisfies them all and $z_{de_j} \neq 0$ for some j; normalize $z_{de_j} = 1$ and set $x_i = z_{(d-1)e_j + e_i}$. The relations then force $z_\alpha = x^\alpha$ for every α, by induction on how far α is from de_j. Hence the image is exactly the closed set cut out by those quadrics.

Isomorphism onto the image. The inverse is given on the open set $z_{de_j} \neq 0$ by $z \mapsto [z_{(d-1)e_j + e_0} : \cdots : z_{(d-1)e_j + e_n}]$, a tuple of forms of the same degree with no common zero there, hence regular by proposition 39.4.3. These agree on overlaps because both compute the same point, so they glue to a regular inverse, as we sought to show.

The payoff is the promised trade.

Corollary 41.1.3: Hypersurfaces Become Hyperplane Sections

Let F be a form of degree d in $x_0, \dots, x_n$. Then there is a hyperplane $H \subseteq \mathbb{P}^N_k$ with

$$v_d\big(\mathcal{Z}(F)\big) = V_{n,d} \cap H$$

Consequently every degree-d hypersurface in $\mathbb{P}^n_k$ is the pullback of a hyperplane under v_d.

***Proof*:**
Write $F = \sum_\alpha c_\alpha x^\alpha$, the sum over monomials of degree d. Let $H = \mathcal{Z}(L)$ where $L = \sum_\alpha c_\alpha z_\alpha$, a linear form. Then $L(v_d(x)) = \sum_\alpha c_\alpha x^\alpha = F(x)$, so $v_d(x) \in H$ if and only if $F(x) = 0$, as we sought to show.

Example 41.1.4: Small Veronese Embeddings

1. $v_2 \colon \mathbb{P}^1_k \to \mathbb{P}^2_k$, $[s : t] \mapsto [s^2 : st : t^2]$. Here $N = \binom{3}{2} - 1 = 2$ and the image is the conic $\mathcal{Z}(z_0 z_2 - z_1^2)$. This is the isomorphism $\mathbb{P}^1 \cong$ smooth conic met in example 39.4.4(3), in coordinates.
2. $v_3 \colon \mathbb{P}^1_k \to \mathbb{P}^3_k$, $[s : t] \mapsto [s^3 : s^2 t : st^2 : t^3]$, whose image is the twisted cubic of example 38.3.7(4). So the twisted cubic is a Veronese image, which is another way of seeing that it is rational.
3. $v_2 \colon \mathbb{P}^2_k \to \mathbb{P}^5_k$ is the *Veronese surface*, the classical example of a smooth surface in $\mathbb{P}^5$ that is not contained in any hyperplane.

The construction also gives a clean way to think about the parameter space of section 39.2: the degree-d forms on $\mathbb{P}^n$, taken up to scalar, are the points of $\mathbb{P}^N_k$, and corollary 41.1.3 says the hypersurface a point cuts out is the corresponding hyperplane section of the Veronese. The following is a first payoff.

Proposition 41.1.5: Parameterizing Reducible Hypersurfaces

Fix n and d, and let $\mathbb{P}^N_k$, $N = \binom{n+d}{d} - 1$, be the projective space parameterizing degree-d forms in $n+1$ variables up to scalar, as in section 39.2. Then the set of points corresponding to *reducible* forms is closed in $\mathbb{P}^N_k$.

***Proof*:**
A reducible form of degree d factors as a product of forms of degrees j and $d-j$ for some $1 \le j \le d-1$. Writing Z_j for the set of points of $\mathbb{P}^N_k$ arising this way, the set of reducible forms is $\bigcup_{j=1}^{d-1} Z_j$, a finite union, so it suffices to show each Z_j is closed.

Let $N_j = \binom{n+j}{j} - 1$ and $N_{d-j} = \binom{n+d-j}{d-j} - 1$ be the corresponding parameter spaces. Multiplication of forms gives a map

$$\mu \colon \mathbb{P}^{N_j}_k \times \mathbb{P}^{N_{d-j}}_k \to \mathbb{P}^N_k$$

which is well defined, since scaling either factor scales the product, and regular, since the coefficients of a product are bilinear in the coefficients of the factors. Its image is exactly Z_j.

The source is a product of projective spaces, hence a projective variety by proposition 40.1.3, so $Z_j = \mu(\mathbb{P}^{N_j}_k \times \mathbb{P}^{N_{d-j}}_k)$ is closed by corollary 40.2.3. That is the whole point of completeness: the image of a projective variety is closed, which for an affine source would fail. Hence the reducible locus is closed, as we sought to show.

For $n = 1$ and $d = 2$ this recovers a familiar fact: a binary quadratic form $ax^2 + bxy + cy^2$ is reducible exactly when its discriminant $b^2 - 4ac$ vanishes, a single equation in the coefficients.

41.2 Grassmannians and the Plücker Embedding

The Veronese parameterizes hypersurfaces. The Grassmannian parameterizes linear subspaces, and it is the space one needs in order to ask questions like "how many lines lie on a surface". As with the Veronese, the construction realizes a set of geometric objects as the points of a projective variety.

Definition 41.2.1: Grassmannian

Let $0 < r < n$. The *Grassmannian* $G(r, n)$ is the set of r-dimensional linear subspaces of k^n. Equivalently, since an r-dimensional subspace of k^n is an $(r-1)$-dimensional linear subspace of $\mathbb{P}_k^{n-1}$, it is the set of $(r-1)$-planes in $\mathbb{P}_k^{n-1}$.

The two readings differ only by a shift, and both are used: $G(2, 4)$ is the space of 2-dimensional subspaces of k^4, which is the space of *lines* in $\mathbb{P}_k^3$. That is the case section 41.4 needs, and there the columns of k^4 are indexed by $0, 1, 2, 3$ to match the coordinates $x_0, \dots, x_3$ on $\mathbb{P}_k^3$, writing the Plücker coordinates as p_{ij} with $0 \le i < j \le 3$.

To make $G(r, n)$ a variety, represent a subspace by a basis and kill the ambiguity in that choice.

Definition 41.2.2: Plücker Embedding

Let $W \subseteq k^n$ be an r-dimensional subspace with basis $w_1, \dots, w_r$. Writing the w_i as the rows of an $r \times n$ matrix, let $p_{i_1 \cdots i_r}$ be the $r \times r$ minor on columns $i_1 < \cdots < i_r$. The *Plücker embedding* is

$$\rho \colon G(r, n) \to \mathbb{P}_k^{\binom{n}{r}-1} \qquad \rho(W) = [\, p_{i_1 \cdots i_r} \,]_{i_1 < \cdots < i_r}$$

Proposition 41.2.3: The Plücker Embedding Is Well Defined and Injective

ρ does not depend on the choice of basis, and it is injective.

***Proof*:**

Changing basis replaces the matrix A by gA for some $g \in \mathrm{GL}_r(k)$, and the Cauchy-Binet formula multiplies every maximal minor by the single scalar $\det g \neq 0$. So the tuple of minors changes by an overall scalar and its class in projective space is unchanged. Not all minors vanish, since the rows are independent and so some r columns are independent.

For injectivity, recover W from $\rho(W)$: a vector $v \in k^n$ lies in W exactly when the $(r+1) \times n$ matrix obtained by appending v has all its maximal minors zero, and expanding those minors along the appended row writes each as a linear form in v with coefficients among the $p_{i_1 \cdots i_r}$. So the Plücker coordinates determine W as the common zero set of an explicit system of linear equations, as we sought to show.

Theorem 41.2.4: The Grassmannian Is a Projective Variety

The image of ρ is closed in $\mathbb{P}_k^{\binom{n}{r}-1}$, so $G(r,n)$ is a projective variety. Its dimension is

$$\dim G(r,n) = r(n-r)$$

***Proof*:**
Closed. The image is cut out by the *Plücker relations*, the quadratic equations expressing that a tuple of $\binom{n}{r}$ numbers arises as the maximal minors of an $r \times n$ matrix. These are quadrics in the $p_{i_1 \cdots i_r}$; example 41.2.5(2) writes them out in the first case where there is more than one. Their zero set is closed, and the argument of proposition 41.2.3 shows a point satisfying them determines an r-dimensional subspace, so the zero set is exactly $\mathrm{im}\rho$.

Dimension. Cover $G(r,n)$ by the open sets $U_{i_1 \cdots i_r} = \{p_{i_1 \cdots i_r} \neq 0\}$. On $U_{1 \cdots r}$, every subspace has a unique basis whose matrix is $[\, I_r \big| B \,]$ with B an arbitrary $r \times (n-r)$ matrix: row-reduce using the invertible left block. The entries of B are free coordinates, giving $U_{1 \cdots r} \cong \mathbb{A}_k^{r(n-r)}$. These charts are irreducible and pairwise meet, since any two nonempty open subsets of an irreducible space do, so $G(r,n)$ is irreducible by lemma 40.1.5, and corollary 34.3.3 reads its dimension off a single chart as $r(n-r)$, as we sought to show.

Example 41.2.5: Grassmannians

1. $G(1,n) = \mathbb{P}_k^{n-1}$: a line through the origin in k^n is a point of $\mathbb{P}^{n-1}$, and the Plücker map is the identity. Dimension $1 \cdot (n-1) = n-1$, as it should be.
2. $G(2,4)$, the lines in $\mathbb{P}_k^3$. Here $\binom{4}{2} = 6$, so ρ lands in $\mathbb{P}_k^5$ with coordinates $p_{12}, p_{13}, p_{14}, p_{23}, p_{24}, p_{34}$, and there is exactly one Plücker relation:

   $$p_{12}p_{34} - p_{13}p_{24} + p_{14}p_{23} = 0$$

   So $G(2,4)$ is a quadric hypersurface in $\mathbb{P}_k^5$, of dimension $2 \cdot 2 = 4$, matching theorem 34.4.1, which gives $5 - 1 = 4$.
3. $G(r,n) \cong G(n-r,n)$, by sending a subspace to its annihilator in the dual space. So the lines in $\mathbb{P}^3$ and the planes in $\mathbb{P}^3$ form isomorphic families, both of dimension 4.

The count in item (2) is the one section 41.4 runs on: the lines in $\mathbb{P}^3$ form a 4-dimensional family, and asking how many of them lie on a given surface is a question about intersecting that family with a condition.

41.3 Constructible Sets and Chevalley's Theorem

Chapter 40 showed that the image of a *projective* variety under a regular map is closed. For a general regular map the image can be neither closed nor open: the projection of $\mathcal{Z}(xy-1)$ to the x-axis is $\mathbb{A}_k^1 \setminus \{0\}$, which is open, while the image of $(x,y) \mapsto (x, xy)$ is $(\mathbb{A}_k^1 \setminus \{0\}) \times \mathbb{A}_k^1$ together with the

single point $(0,0)$, which is neither. Chevalley's theorem says the second example is as bad as it gets: images are always finite unions of pieces of that shape.

Definition 41.3.1: Locally Closed and Constructible Sets

Let X be a variety. A subset $S \subseteq X$ is *locally closed* if $S = U \cap Z$ with U open and Z closed, equivalently if S is open in its own closure. A subset is *constructible* if it is a finite union of locally closed sets.

Proposition 41.3.2: Constructible Sets Form a Boolean Algebra

The constructible subsets of X are closed under finite union, finite intersection, and complement. They are the smallest such family containing the open sets.

***Proof*:**
Closure under finite union is the definition. For intersection, $(U_1 \cap Z_1) \cap (U_2 \cap Z_2) = (U_1 \cap U_2) \cap (Z_1 \cap Z_2)$ is locally closed, and intersection distributes over the finite unions.

For complement, it suffices to complement one locally closed set, since the complement of a finite union is the finite intersection of the complements and intersections are handled. And

$$X \setminus (U \cap Z) = (X \setminus U) \cup (X \setminus Z)$$

a union of a closed set and an open set, both locally closed. Finally any family closed under these operations and containing the opens contains every $U \cap Z$, hence every constructible set, as we sought to show.

The theorem rests on the fact that a dominating map hits a dense open set. Section 40.3 stated this without proof; it follows from the generic finiteness of theorem 40.5.1(3).

Lemma 41.3.3: A Dominating Image Contains a Dense Open Set

Let $f\colon X \to Y$ be a dominating regular map of irreducible varieties. Then $f(X)$ contains a nonempty open subset of Y.

***Proof*:**
Passing to affine open subsets changes neither hypothesis nor conclusion, so assume X and Y affine. The proof of theorem 40.5.1(3) produced $g \in k[Y]$ and $t_1, \dots, t_{n-m}$ such that

$$k[X]_g \text{ is finite over } k[Y]_g[t_1, \dots, t_{n-m}]$$

Geometrically this says f restricted over $D(g)$ factors as a finite map followed by a projection $D(g) \times \mathbb{A}_k^{n-m} \to D(g)$. A finite map is surjective by proposition 40.3.3, and the projection is surjective, so the composite is surjective onto $D(g)$. Hence $f(X) \supseteq D(g)$, a nonempty open subset of Y, as we sought to show.

Theorem 41.3.4: Chevalley's Theorem

Let $f\colon X \to Y$ be a regular map of varieties. Then f carries constructible sets to constructible sets. In particular $f(X)$ is constructible.

***Proof*:**
Since a constructible set is a finite union of locally closed sets, and the image of a union is the union of the images, it suffices to treat $f(X)$ itself, with X replaced by a locally closed subset. Decomposing X into irreducible components (theorem 32.3.5) and Y into the closure of the image, we may assume X and Y irreducible and f dominating.

Argue by Noetherian induction on Y: suppose the result holds for every proper closed subvariety of Y. By lemma 41.3.3 there is a nonempty open $U \subseteq Y$ with $U \subseteq f(X)$. Then

$$f(X) = U \cup f\big(X \setminus f^{-1}(U)\big)$$

The set $X' = X \setminus f^{-1}(U)$ is closed in X, and $f(X') \subseteq Y \setminus U$, a proper closed subset of Y. Applying the inductive hypothesis to $f|_{X'}\colon X' \to Y \setminus U$, which is a regular map of varieties with strictly smaller target, shows $f(X')$ is constructible. As U is open, hence constructible, and constructible sets are closed under finite union (proposition 41.3.2), $f(X)$ is constructible.

The induction terminates because Y is a Noetherian topological space (proposition 31.3.7), so there is no infinite strictly descending chain of closed subsets, completing the proof.

Chevalley's theorem is the right general statement, and the closed-image theorem of corollary 40.2.3 is the special case where properness upgrades "constructible" to "closed". It is also the statement that survives into scheme theory unchanged, where it becomes the assertion that a finite-type morphism of Noetherian schemes has constructible image.

Example 41.3.5: The Image That Is Neither Open Nor Closed
Take $f\colon \mathbb{A}^2_k \to \mathbb{A}^2_k$, $f(x,y) = (x, xy)$. For $x = a \neq 0$ the fibre over (a,b) is the single point $(a, b/a)$, so every such (a,b) is hit; for $x = 0$ the image of the line $x = 0$ is the single point $(0,0)$. Hence

$$\mathrm{im} f = \big((\mathbb{A}^1_k \setminus \{0\}) \times \mathbb{A}^1_k\big) \;\cup\; \{(0,0)\}$$

The first piece is open, the second is closed, and the union is neither. It is constructible, being a union of two locally closed sets, exactly as theorem 41.3.4 requires. This is also the map of example 40.5.2, whose fibre over the origin jumped in dimension; the jump and the failure of openness are the same phenomenon.

41.4 Application: Lines on a Cubic Surface

The Grassmannian and the fibre-dimension theorem together answer a question that would otherwise be inaccessible: how many lines lie on a surface in $\mathbb{P}^3$? For a general cubic surface the answer is a finite number, and the argument that it is finite is a dimension count of exactly the kind this Part was built to support.

Fix the two parameter spaces. Lines in $\mathbb{P}^3_k$ form $G = G(2,4)$, of dimension 4 by theorem 41.2.4.

Cubic surfaces in $\mathbb{P}^3_k$ are the nonzero degree-3 forms in four variables up to scalar, so they form $\mathbb{P}^{19}_k$: there are $\binom{3+3}{3} = 20$ monomials of degree 3 in four variables. Note that this parameter space contains reducible and singular surfaces too, which is harmless and in fact necessary, since a parameter space has to be complete to be useful.

The strategy is to put lines and surfaces into a single variety and project it two ways. Set

$$I = \left\{(\ell, S) \in G \times \mathbb{P}^{19}_k \;\middle|\; \ell \subseteq S\right\}$$

Projecting to G organizes I by the line; over a fixed line the cubics containing it form a linear system, and that side computes $\dim I$. Projecting to $\mathbb{P}^{19}$ organizes I by the surface, and its fibres are the sets of lines to be counted.

Lemma 41.4.1: The Incidence Variety

I is an irreducible projective variety of dimension 19, and $\pi_1 \colon I \to G$ is surjective with every fibre a linear subspace $\mathbb{P}^{15} \subseteq \mathbb{P}^{19}$.

***Proof*:**
Work chart by chart on G. By the proof of theorem 41.2.4 the open set $U \subseteq G$ where $p_{01} \neq 0$ is isomorphic to $\mathbb{A}^4_k$, with coordinates a, b, c, d naming the plane spanned by $(1, 0, a, b)$ and $(0, 1, c, d)$; the corresponding line $\ell_{abcd} \subseteq \mathbb{P}^3_k$ is the image of

$$[s : t] \longmapsto [\, s : t : as + ct : bs + dt \,]$$

Let $T = T_{abcd}$ be the linear automorphism of k^4 fixing e_2, e_3 and sending e_0, e_1 to $(1, 0, a, b)$ and $(0, 1, c, d)$. Its matrix is lower triangular with 1s on the diagonal, so $\det T = 1$, and both T and T^{-1} have entries that are polynomials in a, b, c, d. By construction T carries the line $\mathcal{Z}(x_2, x_3)$ onto ℓ_{abcd}, so for a cubic form F,

$$F \text{ vanishes on } \ell_{abcd} \iff F \circ T \text{ vanishes on } \mathcal{Z}(x_2, x_3) \iff F \circ T \text{ has no term in } x_0, x_1 \text{ alone}$$

the last step because the restriction of $F \circ T$ to $\mathcal{Z}(x_2, x_3)$ is obtained by setting $x_2 = x_3 = 0$, leaving exactly the four terms $x_0^3, x_0^2 x_1, x_0 x_1^2, x_1^3$.

Now consider

$$\Psi \colon U \times \mathbb{P}^{19}_k \to U \times \mathbb{P}^{19}_k \qquad \big((a, b, c, d), [F]\big) \mapsto \big((a, b, c, d), [F \circ T_{abcd}]\big)$$

The coefficients of $F \circ T$ are linear in those of F with coefficients polynomial in a, b, c, d, and $F \circ T \neq 0$ because T is invertible, so Ψ is a regular map; the same formula with T^{-1} gives its inverse, so Ψ is an isomorphism. The displayed equivalence says precisely that Ψ carries $\pi_1^{-1}(U)$ onto $U \times L$, where $L \subseteq \mathbb{P}^{19}$ is the *fixed* linear subspace of cubics whose four coefficients on $x_0^3, x_0^2 x_1, x_0 x_1^2, x_1^3$ vanish. Those four coordinates are independent, so $L \cong \mathbb{P}^{15}$, and

$$\pi_1^{-1}(U) \cong \mathbb{A}^4_k \times \mathbb{P}^{15}_k$$

Three consequences follow, all of them local statements verified on each of the six charts of G in turn, the computation being identical after permuting coordinates.

I is closed. $U \times L$ is closed in $U \times \mathbb{P}^{19}$, hence so is $\pi_1^{-1}(U)$, and being closed is a local condition on a cover. Since $G \times \mathbb{P}^{19}$ is projective by proposition 40.1.3, I is a projective variety.

π_1 is surjective with fibre $\mathbb{P}^{15}$. Under Ψ the fibre over (a,b,c,d) becomes $\{(a,b,c,d)\} \times L$, so it is a linear $\mathbb{P}^{15}$, in particular nonempty and irreducible of dimension 15.

I is irreducible of dimension 19. Each $\pi_1^{-1}(U)$ is irreducible by proposition 40.1.6, and any two of the six meet, since the charts of the irreducible G do and the fibres of π_1 are nonempty. Lemma 40.1.5 makes I irreducible, and then corollary 40.5.3 applied to π_1 gives $\dim I = 4+15 = 19$, as we sought to show.

The count now hinges on a single input from outside the dimension theory: one cubic surface whose lines can be counted by hand, and which has finitely many. The Fermat cubic is the traditional choice, but its 27 lines take work to enumerate; the following surface is singular, has only three lines, and settles the matter in half a page.

Lemma 41.4.2: A Cubic Surface With Exactly Three Lines

Let $S_0 = \mathcal{Z}(x_0x_1x_2 - x_3^3) \subseteq \mathbb{P}^3_k$. Then S_0 is an irreducible cubic surface, and the only lines contained in it are $\mathcal{Z}(x_3, x_0)$, $\mathcal{Z}(x_3, x_1)$ and $\mathcal{Z}(x_3, x_2)$.

***Proof*:**

Irreducibility. Read $x_0x_1x_2 - x_3^3$ as a polynomial in x_3 over the unique factorization domain $k[x_0, x_1, x_2]$. Its leading coefficient is -1, its middle coefficients are 0, and its constant term $x_0x_1x_2$ lies in (x_0) but not in (x_0^2). Eisenstein's criterion at the prime x_0 applies, so the polynomial is irreducible and S_0 is a variety.

The three lines lie on it. On $\mathcal{Z}(x_3, x_i)$ both $x_0x_1x_2$ and x_3^3 vanish identically.

There are no others. Let $\ell \subseteq S_0$ be a line, parameterized by $[s:t] \mapsto [g_0 : g_1 : g_2 : g_3]$, where the g_i are linear forms in s, t spanning a two-dimensional space, that being what makes the image a line rather than a point. The defining equation restricts to $g_0g_1g_2 = g_3^3$ in $k[s,t]$.

If $g_3 \equiv 0$ then $g_0g_1g_2 \equiv 0$, and $k[s,t]$ is a domain, so $g_i \equiv 0$ for some $i \leq 2$; then $\ell \subseteq \mathcal{Z}(x_3, x_i)$, and as both are lines they are equal.

If $g_3 \not\equiv 0$, change coordinates on the source $\mathbb{P}^1$ so that $g_3 = t$, which is possible because g_3 is a nonzero linear form. Then $g_0g_1g_2 = t^3$. None of g_0, g_1, g_2 is zero, and each divides t^3 in the unique factorization domain $k[s,t]$, in which t is prime; the only linear divisors of t^3 are the scalar multiples of t. So $g_i = c_it$ for every $i \leq 2$ as well, making all four g_i proportional, which contradicts the requirement that they span a two-dimensional space of linear forms. Hence this case does not occur, as we sought to show.

Theorem 41.4.3: Lines on a Cubic Surface

Every cubic surface in $\mathbb{P}^3_k$ contains a line, and there is a nonempty open subset $U \subseteq \mathbb{P}^{19}_k$ such that a cubic surface parameterized by a point of U contains only finitely many.

***Proof*:**

Write $\pi_2 \colon I \to \mathbb{P}^{19}_k$ for the second projection. By lemma 41.4.1 the source is an irreducible projective variety with $\dim I = 19 = \dim \mathbb{P}^{19}_k$, so $\pi_2(I)$ is closed by corollary 40.2.3 and irreducible, being the continuous image of an irreducible space.

π_2 is surjective. The fibre $\pi_2^{-1}(S_0)$ over the surface of lemma 41.4.2 is a set of three points, so it is nonempty of dimension 0; in particular $S_0 \in \pi_2(I)$. Suppose $\pi_2(I) \neq \mathbb{P}^{19}$. Then $\pi_2(I)$ is a proper closed subvariety, so $\dim \pi_2(I) \leq 18$ by proposition 34.3.5. Applying theorem 40.5.1(2) to the dominating map $\pi_2 \colon I \to \pi_2(I)$ forces every component of every fibre to have dimension at least $19 - 18 = 1$, contradicting the fibre over S_0. Hence $\pi_2(I) = \mathbb{P}^{19}$, which says exactly that every cubic surface contains a line.

The general fibre is finite. Now π_2 is a dominating map of irreducible varieties with $\dim I = \dim \mathbb{P}^{19}$, so theorem 40.5.1(3) gives a nonempty open $U \subseteq \mathbb{P}^{19}$ with $\dim \pi_2^{-1}(S) = 19 - 19 = 0$ for every $S \in U$. Such a fibre is closed in the projective I, hence an algebraic set, and by theorem 32.3.5 it has finitely many irreducible components. Each component is closed, irreducible and of dimension 0, hence a single point: a closed irreducible set with two distinct points $p \neq q$ contains the proper closed subset $\{p\}$, giving a chain of length 1 and so dimension at least 1. The fibre is therefore finite, as we sought to show.

The dimension count says "finitely many". The classical refinement, that a *smooth* cubic surface contains exactly 27 lines, needs more than dimension theory: one exhibits the 27 on a single smooth cubic and then shows the number is constant across the smooth locus of the family. On the Fermat cubic $\mathcal{Z}(x_0^3 + x_1^3 + x_2^3 + x_3^3)$, in characteristic zero, they are the lines

$$x_0 = \alpha x_1, \quad x_2 = \beta x_3 \qquad \alpha^3 = \beta^3 = -1$$

together with the images of these nine under the two other ways of splitting $\{x_0, x_1, x_2, x_3\}$ into pairs, giving $3 \times 9 = 27$. The count is due to Cayley and Salmon in 1849; a full treatment is in Shafarevich or in Hartshorne's chapter on surfaces.

41.4.4 Note: Where the Numbers Come From The two numbers in the proof are worth keeping straight. The 19 is $\binom{6}{3} - 1$: cubic forms in four variables, up to scalar. The 15 is $19 - 4$, where the 4 counts the coefficients of a binary cubic, that is the number of conditions imposed by requiring a cubic to vanish on a fixed line. The coincidence $\dim I = \dim \mathbb{P}^{19}$ is exactly what makes the answer finite and nonzero. Had the incidence variety been larger, every cubic would carry infinitely many lines; had it been smaller, the general cubic would carry none, which is what happens for surfaces of degree 4 and above.

41.5 Degree, Linear Sections, and Bézout in $\mathbb{P}^n$

Definition 38.5.3 defined the degree of a projective variety as $d!$ times the leading coefficient of its Hilbert polynomial. That is a definition one can compute with and not one that says anything geometric. This section gives the geometry: the degree counts points, and degrees multiply under intersection. Both statements need theorem 40.6.3 to know that the intersections in question are nonempty and of the right size.

Theorem 41.5.1: Degree Counts Points of a Linear Section

Let $X \subseteq \mathbb{P}_k^n$ be a projective variety of dimension r and degree d. Then for a general linear subspace $L \subseteq \mathbb{P}_k^n$ of dimension $n - r$, the intersection $X \cap L$ is a finite set of exactly d points.

***Proof*:**
The intersection is finite and nonempty. By theorem 40.6.3 every component of $X \cap L$ has dimension at least $r + (n - r) - n = 0$, and the intersection is nonempty. For a general L the dimension is exactly 0: choosing L as an intersection of r hyperplanes, each successive hyperplane may be chosen to contain no component of what remains, since a component is a proper closed subset of $\mathbb{P}^n_k$ and the hyperplanes containing a fixed subvariety form a proper linear subspace of the dual space. Each such cut drops the dimension by exactly one by theorem 34.4.1, so after r cuts the dimension is 0 and the set is finite.

The count. Write $S = S(X)$ for the homogeneous coordinate ring and let $\ell_1, \dots, \ell_r$ be the linear forms cutting out L. Since no ℓ_i vanishes on a component of the successive intersections, each ℓ_i is a nonzerodivisor on the successive quotients, so

$$H_{X\cap L}(m) = \dim_k \left(S/(\ell_1, \dots, \ell_r)\right)_m$$

and each quotient by a nonzerodivisor of degree 1 takes the mth graded piece to the difference of the mth and $(m-1)$st. Iterating r times, the Hilbert polynomial of $X \cap L$ is the rth finite difference of h_X. As h_X has degree r with leading coefficient $d/r!$, its rth finite difference is the constant d.

Finally $X \cap L$ is a finite set of points, and the Hilbert polynomial of a finite set of N distinct points in $\mathbb{P}^n_k$ is the constant N: the restriction map from forms of degree m to functions on the points is surjective for m large, by choosing forms separating the points. Hence $N = d$, as we sought to show.

So the degree of a plane curve is the number of points in which a general line meets it, the degree of the twisted cubic is the number of points in which a general plane meets it, which example 38.5.4(4) computed as 3, and the degree of $\mathbb{P}^r$ itself is 1, a general linear space of complementary dimension meeting it once.

The same bookkeeping gives the general form of Bézout's theorem. Stated for hypersurfaces it is a count of degrees; the plane-curve case of chapter 43 is the case $n = 2$, refined there to include local multiplicities.

Theorem 41.5.2: Bézout's Theorem in $\mathbb{P}^n$

Let $F_1, \dots, F_r$ be forms in $k[x_0, \dots, x_n]$ of degrees $d_1, \dots, d_r$ with $r \leq n$, and suppose $X = \mathcal{Z}(F_1, \dots, F_r)$ has dimension exactly $n - r$, the smallest its dimension can be. Then X has degree

$$\deg X = d_1 d_2 \cdots d_r$$

counting components with multiplicity.

***Proof*:**
Induct on r. For $r = 1$, the computation of example 38.5.4(2) gives $H_X(m) = \binom{m+n}{n} - \binom{m-d_1+n}{n}$, whose leading term is $d_1 m^{n-1}/(n-1)!$, so $\deg X = d_1$: the degree of a hypersurface is the degree of its equation.

For the inductive step, let $X' = \mathcal{Z}(F_1, \dots, F_{r-1})$, of dimension $n - r + 1$ by the hypothesis that each cut is proper, and of degree $d_1 \cdots d_{r-1}$ by induction. Cutting X' by F_r drops the dimension by exactly one, so F_r vanishes on no component of X' and is therefore a nonzerodivisor on

$S(X')$. Multiplication by F_r is then injective and raises degree by d_r, giving the exact sequence of graded pieces

$$0 \to S(X')_{m-d_r} \to S(X')_m \to S(X)_m \to 0$$

so $h_X(m) = h_{X'}(m) - h_{X'}(m - d_r)$. Write $N = n - r + 1$ and $h_{X'}(m) = \frac{e}{N!}m^N + \cdots$ with $e = \deg X'$. Since $m^N - (m - d_r)^N = Nd_r m^{N-1} + \cdots$, the difference has degree $N - 1 = n - r$ with leading coefficient

$$\frac{e}{N!} \cdot Nd_r \;=\; \frac{e\,d_r}{(N-1)!} \;=\; \frac{e\,d_r}{(n-r)!}$$

By definition 38.5.3 the degree of X is $(n - r)!$ times that leading coefficient, namely $e\,d_r = d_1 \cdots d_r$, as we sought to show.

Example 41.5.3: Degrees of Intersections

1. *Two quadric surfaces in $\mathbb{P}^3_k$.* Each has degree 2, and if their intersection is a curve then theorem 41.5.2 gives it degree 4. A general such curve is the elliptic quartic; it is not a plane curve, since a plane curve of degree 4 has genus 3 by definition 44.4.1 while this one has genus 1.

2. *The twisted cubic is not a complete intersection.* It has degree 3 and codimension 2 in $\mathbb{P}^3_k$. Were it $\mathcal{Z}(F_1, F_2)$ with $\deg F_i = d_i$, theorem 41.5.2 would force $d_1 d_2 = 3$, so $\{d_1, d_2\} = \{1, 3\}$ and the curve would lie in the plane $\mathcal{Z}(F_1)$. It does not: its parameterization $[s^3 : s^2t : st^2 : t^3]$ spans $\mathbb{P}^3_k$, since the four coordinate functions are linearly independent. This is the promise made in example 38.3.7.

3. *A line and a plane in $\mathbb{P}^3_k$.* Degrees 1 and 1, dimensions 1 and 2, so the intersection has dimension 0 and degree 1: exactly one point, which is the familiar statement that a line not contained in a plane meets it once.

41.6 Cones, Projections, and Secant Varieties

The embeddings of the previous sections all enlarge the ambient space. This one goes the other way: given a variety in $\mathbb{P}^N_k$, project it into a smaller projective space and ask when nothing is lost. The construction has already been used twice without being set up — to identify a conic with $\mathbb{P}^1_k$ in theorem 44.4.2, and to exhibit a finite map in section 40.3 — and the obstruction to it is a variety worth naming in its own right.

Definition 41.6.1: Cone and Join

Let $X, Y \subseteq \mathbb{P}^N_k$ be disjoint projective varieties. The *join* $J(X, Y)$ is the closure of the union of the lines $\overline{xy}$ for $x \in X$ and $y \in Y$. When $Y = \{p\}$ is a single point, $J(X, p)$ is the *cone* over X with vertex p.

Definition 41.6.2: Projection from a Point

Let $p \in \mathbb{P}_k^N$ and let $H \cong \mathbb{P}_k^{N-1}$ be a hyperplane not containing p. The *projection from* p is

$$\pi_p \colon \mathbb{P}_k^N \setminus \{p\} \to H \qquad q \mapsto \overline{pq} \cap H$$

In coordinates with $p = [0 : \cdots : 0 : 1]$ and $H = \mathcal{Z}(x_N)$, it is $[x_0 : \cdots : x_N] \mapsto [x_0 : \cdots : x_{N-1}]$, visibly regular away from p.

Proposition 41.6.3: Projection Is a Finite Morphism

Let $X \subseteq \mathbb{P}_k^N$ be a projective variety and $p \notin X$. Then π_p restricts to a morphism $X \to \mathbb{P}_k^{N-1}$ whose image is closed of the same dimension as X, and whose fibres are finite.

***Proof*:**
Since $p \notin X$, the map π_p is defined at every point of X, and it is regular there by definition 41.6.2. Its image is closed by corollary 40.2.3, X being projective.

The fibre over a point h is $X \cap \overline{ph}$, the intersection of X with a line through p. That line is not contained in X, since $p \notin X$, so the intersection is a proper closed subset of the line and hence finite. Finiteness of the fibres forces $\dim \pi_p(X) = \dim X$ by theorem 40.5.1(3), whose generic fibre dimension is then 0, as we sought to show.

Projection is injective on X exactly when no line through p meets X twice, and it is an immersion when in addition no tangent line to X passes through p. Both conditions say that p avoids a certain subvariety, and naming those subvarieties is what makes the argument work.

Definition 41.6.4: Secant and Tangent Varieties

Let $X \subseteq \mathbb{P}_k^N$ be a projective variety. The *secant variety* $\operatorname{Sec}(X)$ is the closure of the union of the lines $\overline{xy}$ over pairs of distinct points $x, y \in X$. The *tangent variety* $\operatorname{Tan}(X)$ is the closure of the union of the embedded tangent spaces $T_x X \cong \mathbb{P}_k^r$ over the nonsingular points x of X, where $r = \dim X$.

Proposition 41.6.5: Dimension of the Secant Variety

Let $X \subseteq \mathbb{P}_k^N$ be a projective variety of dimension r. Then

$$\dim \operatorname{Sec}(X) \leq 2r + 1 \qquad \dim \operatorname{Tan}(X) \leq 2r$$

***Proof*:**
Consider the incidence variety

$$I = \overline{\{(x, y, z) \mid x \neq y \in X,\ z \in \overline{xy}\}} \ \subseteq\ X \times X \times \mathbb{P}_k^N$$

Projecting to $X \times X$ has fibre the line $\overline{xy}$, of dimension 1, over the open set where $x \neq y$. So $\dim I \leq \dim(X \times X) + 1 = 2r + 1$ by corollary 40.5.4 and theorem 40.5.1. Now $\operatorname{Sec}(X)$ is the image of I under the third projection, and the image of a projective variety is closed

of dimension at most that of the source, by corollary 40.2.3 and theorem 40.5.1(1). Hence $\dim \operatorname{Sec}(X) \leq 2r+1$.

For $\operatorname{Tan}(X)$ run the same argument over X alone. The incidence $\{(x,z) \mid x \in X \text{ nonsingular},\ z \in T_xX\}$ projects to the smooth locus of X, of dimension r, with fibre the embedded tangent space T_xX, of dimension r. So it has dimension at most $2r$, and $\operatorname{Tan}(X)$, being its image, has dimension at most $2r$, as we sought to show.

The bound is what makes projection useful: as soon as the ambient space is large enough, a point can be chosen outside the secant variety, and projecting from it loses nothing.

Theorem 41.6.6: Every Projective Variety Embeds in $\mathbb{P}^{2r+1}$

Let $X \subseteq \mathbb{P}^N_k$ be a projective variety of dimension r. If $N > 2r+1$, then there is a point $p \notin \operatorname{Sec}(X)$, and π_p maps X isomorphically onto its image in $\mathbb{P}^{N-1}_k$. Iterating, X is isomorphic to a projective variety in $\mathbb{P}^{2r+1}_k$.

***Proof*:**

By proposition 41.6.5, $\dim \operatorname{Sec}(X) \leq 2r+1 < N$, so $\operatorname{Sec}(X)$ is a proper closed subset of $\mathbb{P}^N_k$ and a point p outside it exists. Note $X \subseteq \operatorname{Sec}(X)$ whenever $\dim X \geq 1$, so $p \notin X$ and proposition 41.6.3 applies.

π_p is injective on X: if $\pi_p(x) = \pi_p(y)$ with $x \neq y$ then p lies on the line $\overline{xy}$, hence in $\operatorname{Sec}(X)$, contrary to choice. It is also an immersion: a tangent line to X is a limit of secant lines, so $\operatorname{Tan}(X) \subseteq \operatorname{Sec}(X)$ and no tangent line to X passes through p either. An injective morphism of projective varieties that is an immersion is an isomorphism onto its closed image.

Repeating drops the ambient dimension by one each time and stops at $N = 2r+1$, as we sought to show.

Example 41.6.7: Projections in Practice

1. *A curve in $\mathbb{P}^3_k$.* Here $r = 1$, so $2r+1 = 3$ and theorem 41.6.6 says every projective curve embeds in $\mathbb{P}^3_k$. It does not say $\mathbb{P}^2_k$: projecting once more from a point of $\operatorname{Sec}(X)$ is unavoidable when $N = 3$, and the image acquires singularities. That is why plane curves are special and why chapter 42 must handle singular ones.

2. *The twisted cubic.* Its secant variety is all of $\mathbb{P}^3_k$, since $\dim \operatorname{Sec} \leq 3$ and the secant lines already sweep out a three-dimensional set. So no projection to $\mathbb{P}^2_k$ is an isomorphism, consistent with the twisted cubic being a rational curve of degree 3 while every plane cubic has genus 1.

3. *A conic.* Projection from a point of the conic itself, rather than from outside it, is the map of theorem 44.4.2: a line through p meets the conic once more, so the projection is a bijection to $\mathbb{P}^1_k$. This is the degenerate case $p \in X$, excluded from proposition 41.6.3, and it lowers the dimension of the image rather than preserving it.

Exercise 41.6.1

1. Write out the Veronese embedding $\mathbb{P}^1_k \to \mathbb{P}^2_k$ for $d = 2$ and identify its image. Then do $d = 3$ and show the image is the twisted cubic of example 38.3.7.
2. Compute $N = \binom{n+d}{d} - 1$ for $(n, d) = (2, 2)$ and describe the Veronese surface in $\mathbb{P}^5_k$. Show that it contains no lines, although it is covered by conics.
3. Verify corollary 41.1.3 explicitly for $n = 1$, $d = 2$: exhibit the hyperplane of $\mathbb{P}^2_k$ cutting out a prescribed pair of points of $\mathbb{P}^1_k$.
4. Take the 2-plane in k^4 spanned by $(1, 0, a, b)$ and $(0, 1, c, d)$. Compute its six Plücker coordinates and verify the relation $p_{01}p_{23} - p_{02}p_{13} + p_{03}p_{12} = 0$ directly.
5. Show that $G(1, n) \cong \mathbb{P}^{n-1}_k$ and that $G(n-1, n) \cong \mathbb{P}^{n-1}_k$, and check both against the dimension formula of theorem 41.2.4.
6. Show that a subset of $\mathbb{A}^1_k$ is constructible if and only if it is finite or cofinite. Deduce that every constructible subset of $\mathbb{A}^1_k$ is either open or closed, so the phenomenon of example 41.3.5 needs at least two dimensions.
7. Give a dominating regular map whose image is not open, and one whose image is not closed. Explain how theorem 41.3.4 accommodates both.
8. Repeat the dimension count of section 41.4 for surfaces of degree e in $\mathbb{P}^3_k$: show that the incidence variety has dimension $\binom{e+3}{3} - 1 + 3 - e$ and conclude that a general surface of degree $e \geq 4$ contains no line, while every quadric contains a one-parameter family.

Part IX

Curves

The fundamental theorem of algebra counts the roots of a polynomial in one variable, and does so exactly because $\mathbb{C}$ is algebraically closed. This Part asks for the two-variable analogue: given two plane curves, how many points do they share? Over $\mathbb{A}^2$ the question has no clean answer, since curves can miss each other or meet at infinity. In $\mathbb{P}^2$ it does, and the answer, Bézout's theorem, is that two curves of degrees m and n meet in exactly mn points.

Making that exact requires deciding what a point of intersection is worth, which is the intersection number of chapter 42. The counting then organizes itself into a group, the divisor class group of chapter 44, whose appearance on a cubic curve is the classical group law. The Part closes by removing the singularities that made the counting delicate in the first place.

42

Intersection Multiplicity

Two curves meeting at a point may cross transversally, be tangent, or meet at a singularity of one or both. Any count of intersections that is to be well behaved must weigh these cases differently. This chapter constructs the weight.

The route runs through the local ring at the point. The multiplicity of a curve at a point turns out to be readable off that ring alone, and at a nonsingular point the ring is a discrete valuation ring, so it carries an order function that already sees tangency. The intersection number of two curves is then the dimension of a single quotient of the local ring of the plane, and it is pinned down by eight properties which double as an algorithm for computing it.

42.1 Plane Curves, Multiplicity, and Tangent Lines

The fundamental theorem of algebra counts the roots of a one-variable polynomial over an algebraically closed field, and it can be read geometrically: a curve of degree n meets the line $x = 0$ in n points, provided the points are weighted correctly. This Part generalizes that reading to two curves, and the weight is what this chapter constructs.

Affine space is the wrong home for the statement. Take the two concentric circles $x^2 + y^2 - 1$ and $x^2 + y^2 - 4$ in $\mathbb{A}^2_{\mathbb{C}}$: both have degree 2, so the count should be 4, and yet they share no point at all. Passing to $\mathbb{P}^2_{\mathbb{C}}$ repairs it. The homogenizations $x^2 + y^2 - z^2$ and $x^2 + y^2 - 4z^2$ meet where $z = 0$ and $x^2 + y^2 = 0$, which is the pair of *circular points* $[1 : \pm i : 0]$ already met in example 38.3.4. Two points, not four, so the weights must be 2 each, and indeed the two circles are tangent to each other at both. The rest of this chapter builds the notion of weight that makes such counts come out, and chapter 43 proves they always do.

The development follows Fulton [102]. Throughout, k is algebraically closed.

A plane curve in the sense of this Part is not quite a variety. The point of the intersection theory is

to count with multiplicity, and multiplicity is information that $\mathcal{Z}(f)$ throws away: $\mathcal{Z}(f)$ and $\mathcal{Z}(f^2)$ are the same set. So the object of study is the polynomial, taken up to scalar.

Definition 42.1.1: Plane Curve

An *affine plane curve* is an equivalence class of nonconstant polynomials in $k[x,y]$, where $f \sim g$ if and only if $f = \alpha g$ for some $\alpha \in k^*$. A *projective plane curve* is the same with $k[x,y]$ replaced by the nonconstant homogeneous polynomials of $k[x,y,z]$. The *degree* of a curve is the degree of any of its representatives.

This is a deliberate departure from definition 34.3.4, where a curve was a one-dimensional variety. The two agree on the underlying point set, since $\mathcal{Z}(f)$ for $f \in k[x,y]$ nonconstant is a hypersurface in $\mathbb{A}^2_k$ and so has dimension 1 by theorem 34.4.2; they differ in that the present notion remembers repeated factors. Homogenizing an affine plane curve and taking the closure in $\mathbb{P}^2_k$ gives a projective plane curve, as in section 38.3, and the two constructions are inverse away from the line at infinity.

Write $f = \prod_{i=1}^{n} f_i^{e_i}$ for the factorization into distinct irreducible factors, which is available because $k[x,y]$ and $k[x,y,z]$ are unique factorization domains. The curve f is *irreducible* if $n = 1$ and $e_1 = 1$; the component f_i is *simple* if $e_i = 1$ and *multiple* otherwise[1].

The local ring at a point is the algebraic object that stores intersection data, and it was already constructed in chapter 32.

Example 42.1.2: Curves Versus Their Zero Sets

1. Let $f = y - x^2$ and $g = (y - x^2)^2$. Then $\mathcal{Z}(f) = \mathcal{Z}(g)$ as subsets of $\mathbb{A}^2_k$, both being the parabola, yet f and g are different plane curves in the sense of definition 42.1.1: one has degree 2 and the other degree 4. Everything this Part counts distinguishes them. A general line meets $\mathcal{Z}(f)$ in 2 points and $\mathcal{Z}(g)$ in 4, once multiplicity is accounted for, which is what theorem 43.1.1 will record.

2. The multiplicity at a point behaves the same way. At the origin, $f = y - x^2$ has lowest form y, so $m_0(f) = 1$ and the origin is a nonsingular point; while $g = (y - x^2)^2$ has lowest form y^2, so $m_0(g) = 2$. The zero set is nonsingular as a set and the curve g is not.

3. *Irreducible components with multiplicity.* The curve $h = x^2 y = x \cdot x \cdot y$ has $\mathcal{Z}(h) = \mathcal{Z}(xy)$, the union of the two axes, but as a curve h has the y-axis as a *double* component and the x-axis as a simple one. The factorization $h = \prod f_i^{e_i}$ records $e = (2,1)$, and proposition 42.1.7 will read $m_0(h) = 2 \cdot 1 + 1 \cdot 1 = 3$ off it.

Keeping the polynomial rather than its zero set is exactly what lets these distinctions be made, and it is the reason chapter 49 points at schemes, where the same information is carried intrinsically.

[1] In [13] schemes recover this information intrinsically: the scheme $\operatorname{Spec} k[x,y]/(f^2)$ is not the scheme $\operatorname{Spec} k[x,y]/(f)$, even though the two have the same points. Working with polynomials up to scalar is the classical workaround.

Definition 42.1.3: Recall: Stalk At A Point

Let V be a variety and $p \in V$ a point. The *stalk* at p is

$$\mathcal{O}_p(V) = \{f/g \in k(V) \mid g(p) \neq 0\}$$

By proposition 33.2.10 it is a Noetherian local domain, with maximal ideal $\mathfrak{m}_p(V) = \{f/g \in \mathcal{O}_p(V) \mid f(p) = 0\}$.

The intuition is that $\mathcal{O}_p(V)$ holds exactly the rational functions defined at p, which is why a denominator is allowed as long as it does not vanish there. For a curve f, write $\mathcal{O}_p(f)$ for the stalk of $\mathcal{Z}(f)$, and $\mathfrak{m}_p(f)$ for its maximal ideal.

Almost every computation below is easier at the origin, and moving a point there is harmless.

Definition 42.1.4: Linear Coordinate Change

Let $\mathbb{A}^n_k$ be affine space with coordinate ring $k[x_1, \dots, x_n]$. A bijective affine transformation $T\colon \mathbb{A}^n_k \to \mathbb{A}^n_k$ is called a *linear change of coordinates*.

If $T = (T_1, \dots, T_n)$ then T acts on functions by $f(x_1, \dots, x_n) \mapsto f(T_1, \dots, T_n)$, and any such T decomposes into a translation followed by a bijective linear transformation. The first invariant to define this way is the multiplicity, obtained by translating the point of interest to the origin and reading off the lowest-degree term.

Definition 42.1.5: Multiplicity

Let $f \in k[x, y]$ be an affine plane curve and $p \in \mathcal{Z}(f)$. After a translation taking p to the origin, write

$$f = f_m + f_{m+1} + \cdots + f_d$$

for the decomposition into homogeneous components, where $f_m \neq 0$. The *multiplicity* of f at p, written $m_p(f)$, is m.

The definition does not depend on the translation chosen, since a translation carrying the origin to itself is the identity, and $m_p(f) \geq 1$ exactly because $f(p) = 0$. The multiplicity measures how badly the curve degenerates at p: it is 1 precisely when p is a nonsingular point of f in the sense of chapter 35, because f_1 is the differential of f at the origin and $f_1 \neq 0$ is the condition that some partial derivative survive.

The lowest form f_m carries more than its degree. Over an algebraically closed field a nonzero binary form factors completely into linear factors, so

$$f_m = \prod_{i=1}^{s} L_i^{r_i} \qquad \sum_i r_i = m$$

with the L_i pairwise non-proportional linear forms.

Definition 42.1.6: Tangent Lines of a Plane Curve

With notation as above, the lines $\mathcal{Z}(L_i)$ are the *tangent lines* to f at p, and r_i is the multiplicity of $\mathcal{Z}(L_i)$ as a tangent. A line through p that is not one of the $\mathcal{Z}(L_i)$ is assigned tangent multiplicity 0. The form f_m itself is the *tangent cone*.
The point p is an *ordinary multiple point* if f has $m = m_p(f)$ distinct tangent lines there, that is if every $r_i = 1$. An ordinary double point is a *node*.

This is the plane-curve case of definition 36.1.2: the initial form f_m generates the initial ideal of (f), so the tangent cone algebra is $k[x, y]/(f_m)$ and its zero set is the union of the tangent lines, while $m_p(f)$ agrees with the multiplicity of definition 36.1.4 by proposition 36.1.5. What the plane case adds is the factorization: a binary form splits into linear factors over the algebraically closed k, so the cone is literally a union of lines counted with multiplicity, which is false for a cone in three or more variables.

At a nonsingular point $m = 1$, so there is a single tangent line $\mathcal{Z}(f_1)$, and f_1 is the linear part of f. That recovers the familiar formula: for $p = (a, b)$ a nonsingular point of f, the tangent line is

$$\frac{\partial f}{\partial x}(p)\,(x - a) + \frac{\partial f}{\partial y}(p)\,(y - b) = 0$$

which is the definition of chapter 35 specialized to a plane curve. For a projective plane curve $F \in k[x, y, z]$ the point p is nonsingular when the three partials $\partial_x F, \partial_y F, \partial_z F$ do not all vanish at p, and the tangent line is then $\mathcal{Z}\big(\sum_i \partial_i F(p)\, x_i\big)$; passing to an affine chart recovers the two-variable statement.

Multiplicities and tangents both behave multiplicatively across the factorization of f.

Proposition 42.1.7: Multiplicity Across Components

Let $f = \prod_i f_i^{e_i}$ be an affine plane curve, factored into distinct irreducibles, and let $p \in \mathcal{Z}(f)$. Then

$$m_p(f) = \sum_i e_i\, m_p(f_i)$$

and a line L tangent to f_i with multiplicity r_i is tangent to f with multiplicity $\sum_i e_i r_i$. Consequently p is a nonsingular point of f if and only if it lies on exactly one f_i, that component is simple, and p is a nonsingular point of it.

***Proof*:**
Translate p to the origin. In the graded domain $k[x, y]$ the lowest form of a product is the product of the lowest forms, so the lowest form of f is $\prod_i (f_i)_{m_i}^{e_i}$ where $m_i = m_p(f_i)$; taking degrees gives the first claim, and reading off the linear factors gives the second.

For the last claim, $m_p(f) = 1$ forces exactly one term of $\sum_i e_i m_p(f_i)$ to be nonzero and equal to 1, so exactly one f_i passes through p, its exponent e_i is 1, and $m_p(f_i) = 1$. The converse is the same computation read backwards, as we sought to show.

42.2 Local Rings of Plane Curves

The multiplicity was defined by writing down a polynomial and looking at its lowest term, which is a coordinate-dependent recipe even if the answer is not. This section shows that $m_p(f)$ is visible inside the local ring $\mathcal{O}_p(f)$ alone, and that the nonsingular points are exactly those where that ring is as simple as a one-dimensional local ring can be.

Theorem 42.2.1: Multiplicity and Local Ring

Let f be an irreducible affine plane curve and $p \in \mathcal{Z}(f)$. Write $\mathcal{O} = \mathcal{O}_p(f)$ and $\mathfrak{m}$ for its maximal ideal. Then for all sufficiently large n,

$$m_p(f) = \dim_k \left(\frac{\mathfrak{m}^n}{\mathfrak{m}^{n+1}} \right)$$

so the multiplicity of f at p is determined by the local ring $\mathcal{O}_p(f)$.

***Proof*:**

The quotient maps $\mathcal{O}/\mathfrak{m}^{n+1} \to \mathcal{O}/\mathfrak{m}^n$ have kernel $\mathfrak{m}^n/\mathfrak{m}^{n+1}$, giving a short exact sequence of k-vector spaces

$$0 \to \mathfrak{m}^n/\mathfrak{m}^{n+1} \to \mathcal{O}/\mathfrak{m}^{n+1} \to \mathcal{O}/\mathfrak{m}^n \to 0$$

Dimension is additive along a short exact sequence of finite-dimensional vector spaces, so it suffices to prove

$$\dim_k \left(\mathcal{O}/\mathfrak{m}^n\right) = n\, m_p(f) + s$$

for a constant s independent of n and all $n \geq m_p(f)$; subtracting consecutive values then leaves $m_p(f)$.

Translate so that $p = (0,0)$ and write $I = (x,y) \subseteq k[x,y]$, so that $\mathcal{I}(\{p\}) = I$. Since $\mathcal{Z}(I^n) = \{p\}$, corollary 42.2.7 and the third exercise of exercise set 42.4.1 give

$$\frac{k[x,y]}{(I^n, f)} \cong \frac{\mathcal{O}_p(\mathbb{A}^2_k)}{(I^n, f)\mathcal{O}_p(\mathbb{A}^2_k)} \cong \frac{\mathcal{O}_p(f)}{I^n \mathcal{O}_p(f)} \cong \mathcal{O}/\mathfrak{m}^n$$

the last isomorphism because $\mathfrak{m}$ is generated by the images of x and y. So the problem is to compute $\dim_k k[x,y]/(I^n, f)$.

Let $m = m_p(f)$. Multiplication by f gives a map

$$\psi \colon \frac{k[x,y]}{I^{n-m}} \to \frac{k[x,y]}{I^n} \qquad \psi(\overline{g}) = \overline{fg}$$

which is well defined because $f \in I^m$, and injective: $k[x,y]$ is a graded domain, so the lowest form of fg is the product of those of f and g, whence $fg \in I^n$ forces $g \in I^{n-m}$. Its image is $(I^n, f)/I^n$, the kernel of the projection $\varphi \colon k[x,y]/I^n \to k[x,y]/(I^n, f)$, so

$$0 \to \frac{k[x,y]}{I^{n-m}} \xrightarrow{\psi} \frac{k[x,y]}{I^n} \xrightarrow{\varphi} \frac{k[x,y]}{(I^n, f)} \to 0$$

is exact. Now $k[x,y]/I^t$ has as a basis the monomials of degree less than t, of which there are $1 + 2 + \cdots + t = \frac{t(t+1)}{2}$, as the second exercise of exercise set 42.4.1 records. Additivity therefore

gives

$$\dim_k(\mathcal{O}/\mathfrak{m}^n) = \frac{n(n+1)}{2} - \frac{(n-m)(n-m+1)}{2} = nm - \frac{m(m-1)}{2}$$

valid for all $n \geq m$. This has the required shape with $s = -\frac{m(m-1)}{2}$, a constant, as we sought to show.

Example 42.2.2: Multiplicity from the Local Ring

Take p the origin and compute $\dim_k \mathfrak{m}^n/\mathfrak{m}^{n+1}$ in each case, which theorem 42.2.1 says stabilizes at $m_p(f)$.

1. *A nonsingular point.* $f = y - x^2$. Here $\mathcal{O}_p(f) \cong k[x]_{(x)}$, since $y = x^2$ on the curve, and $\mathfrak{m} = (x)$. So $\mathfrak{m}^n/\mathfrak{m}^{n+1}$ is spanned by x^n alone and has dimension 1 for every n. That matches $m_p(f) = 1$.
2. *The node.* $f = y^2 - x^2 - x^3$, with $m_p(f) = 2$. The formula of the proof gives $\dim_k \mathcal{O}/\mathfrak{m}^n = 2n - \binom{2}{2} = 2n - 1$ for $n \geq 2$, so $\dim_k \mathfrak{m}^n/\mathfrak{m}^{n+1} = (2n+1) - (2n-1) = 2$ for $n \geq 2$, matching $m_p(f) = 2$.
3. *The cusp.* $f = y^2 - x^3$, again with $m_p(f) = 2$ since the lowest form is y^2. The same computation gives 2 again.

The node and the cusp have the same multiplicity and the same sequence of dimensions, so the local ring sees the multiplicity and not the tangent cone. What separates them is the number of tangent lines, which is definition 42.1.6, or equivalently the number of branches, which example 47.3.3 separates by blowing up.

The theorem already separates the nonsingular points from the rest, since they are the ones where the successive quotients have dimension 1. The next result says what that means ring-theoretically.

Corollary 42.2.3: Simple Points and Multiplicity

Let f be an irreducible affine plane curve and $p \in \mathcal{Z}(f)$. Then p is a nonsingular point of f if and only if $\mathcal{O}_p(f)$ is a discrete valuation ring. In that case, if L is a line through p that is not tangent to f at p, the image of its defining linear form generates $\mathfrak{m}_p(f)$.

***Proof*:**

Suppose p is nonsingular and L is a line through p that is not tangent there. Change coordinates so that $p = (0,0)$, the tangent line is $\mathcal{Z}(y)$, and $L = \mathcal{Z}(x)$. It suffices to show that $\mathfrak{m} = \mathfrak{m}_p(f)$ is generated by the image of x, since $\mathfrak{m}$ is generated by the images of x and y.

Because $\mathcal{Z}(y)$ is the tangent line, the lowest form of f is a nonzero multiple of y, and after scaling f we may take $f = y + (\text{terms of degree} \geq 2)$. Collect the terms containing y: what remains involves x alone and has degree at least 2, since the only degree-one term of f is y. Hence

$$f = yg - x^2 h \qquad g = 1 + (\text{terms of positive degree}), \quad h \in k[x,y]$$

In $k[\mathcal{Z}(f)]$ this reads $yg = x^2 h$, and $g(p) = 1 \neq 0$ makes g a unit in $\mathcal{O}_p(f)$, so

$$y = x^2 h g^{-1} \in (x)$$

Therefore $\mathfrak{m} = (x)$ is principal. By proposition 33.2.10 the ring $\mathcal{O}_p(f)$ is a Noetherian local domain, and it has Krull dimension 1 by proposition 34.3.2, since $\mathcal{Z}(f)$ is a curve and $\{p\}$ has codimension 1 in it. So proposition 35.5.2 applies, and its implication (4) $\Rightarrow$ (2) makes $\mathcal{O}_p(f)$ a discrete valuation ring.

Conversely, if $\mathcal{O}_p(f)$ is a discrete valuation ring then $\mathfrak{m}/\mathfrak{m}^2$ is one-dimensional, generated by the image of a uniformizer, and the same holds for every $\mathfrak{m}^n/\mathfrak{m}^{n+1}$. By theorem 42.2.1 this common dimension is $m_p(f)$, so $m_p(f) = 1$ and p is nonsingular, completing the proof.

Now that $\mathcal{O}_p(f)$ is known to be a discrete valuation ring at a nonsingular point, its valuation can be named. This is the invariant that chapter 43 uses to read off intersection numbers.

Definition 42.2.4: Order Function at a Simple Point

Let f be an irreducible plane curve and p a nonsingular point of f, so that $\mathcal{O}_p(f)$ is a discrete valuation ring by corollary 42.2.3. The *order function* at p

$$\operatorname{ord}_p^f \colon \mathcal{O}_p(f) \setminus \{0\} \to \mathbb{N}$$

is the discrete valuation of $\mathcal{O}_p(f)$: writing t for a uniformizing parameter, $\operatorname{ord}_p^f(g)$ is the unique m with $g = ut^m$ for a unit $u \in \mathcal{O}_p(f)$. By convention $\operatorname{ord}_p^f(0) = \infty$. The definition extends to $k(f)$ by $\operatorname{ord}_p^f(g/h) = \operatorname{ord}_p^f(g) - \operatorname{ord}_p^f(h)$, taking values in $\mathbb{Z}$.

Geometrically $\operatorname{ord}_p^f(g)$ counts how many times g vanishes at p along f, and the computation just made says that the order function sees tangency. A line L meeting f transversally at p has $\operatorname{ord}_p^f(L) = 1$, because its linear form generates $\mathfrak{m}$. The tangent line has order at least 2: in the coordinates of the proof it is $\mathcal{Z}(y)$, and

$$\operatorname{ord}_p^f(y) = \operatorname{ord}_p^f(x^2 h g^{-1}) = 2\operatorname{ord}_p^f(x) + \operatorname{ord}_p^f(hg^{-1}) \geq 2$$

since g^{-1} is a unit and $h \in \mathcal{O}_p(f)$.

The last ingredient of the chapter is a decomposition for the coordinate ring of a finite set of points. It says that such a ring sees each of its points separately, which is what will let a global intersection count be assembled from local ones.

Lemma 42.2.5: Coordinate Ring For Finite Points

Let $I \subseteq k[x_1, \ldots, x_n]$ be an ideal with $\mathcal{Z}(I) = \{p_1, \ldots, p_m\}$ finite, and write $\mathcal{O}_i = \mathcal{O}_{p_i}(\mathbb{A}^n_k)$. Then

$$\frac{k[x_1, \ldots, x_n]}{I} \cong \prod_{i=1}^{m} \frac{\mathcal{O}_i}{I\mathcal{O}_i}$$

and in particular the left side is a finite-dimensional k-vector space.

***Proof*:**
Put $R = k[x_1, \ldots, x_n]/I$. Its maximal ideals correspond by the Nullstellensatz (theorem 32.4.4) to the points of $\mathcal{Z}(I)$, so there are m of them and every prime of R is maximal, that is $\operatorname{kdim} R = 0$. As R is a finitely generated k-algebra it is Noetherian, so corollary 28.1.9 makes R Artinian, and corollary 28.1.10 makes it finite-dimensional over k.

Now theorem 28.1.6 decomposes R as a finite product of local Artinian rings, one for each maximal ideal, the factors being the localizations $R_{\mathfrak{m}_i}$. It remains only to identify $R_{\mathfrak{m}_i}$ geometrically: localizing $k[x_1, \ldots, x_n]/I$ at the maximal ideal of p_i is the same as localizing $k[x_1, \ldots, x_n]$ there and then dividing by the extended ideal, since localization is exact, and that is $\mathcal{O}_i/I\mathcal{O}_i$, as we sought to show.

This is a case where the algebra was done once upstream and should not be done again. The classical proof constructs idempotents e_i by hand and verifies the Chinese-remainder decomposition directly; the Artinian structure theorem is that construction in general form, and the only genuinely geometric step is the Nullstellensatz translation at the start.

Corollary 42.2.6: Dimension of Coordinate Ring of Finite Points

With notation as above,

$$\dim_k \frac{k[x_1, \ldots, x_n]}{I} = \sum_{i=1}^{m} \dim_k \left(\mathcal{O}_i/I\mathcal{O}_i\right)$$

***Proof*:**
Dimension is additive over a finite direct product of vector spaces, so this is lemma 42.2.5 read on dimensions, completing the proof.

Corollary 42.2.7: Coordinate Ring at a Single Point

Let $I \subseteq k[x_1, \ldots, x_n]$ satisfy $\mathcal{Z}(I) = \{p\}$. Then

$$\frac{k[x_1, \ldots, x_n]}{I} \cong \frac{\mathcal{O}_p(\mathbb{A}^n_k)}{I\,\mathcal{O}_p(\mathbb{A}^n_k)}$$

***Proof*:**
This is lemma 42.2.5 with $m = 1$, completing the proof.

One further consequence of the local rings being discrete valuation rings deserves recording here, since chapter 45 needs it: on a smooth curve, a rational map to a projective variety has no points of indeterminacy at all.

Lemma 42.2.8: Rational Maps on Smooth Curves

Let C be an irreducible curve, $V \subseteq \mathbb{P}^N_k$ a *projective* variety, and $\varphi\colon C \dashrightarrow V$ a rational map. If $p \in C$ is a nonsingular point, then φ is regular at p. If C is smooth, then φ is a regular morphism.

***Proof*:**
Since p is a nonsingular point of the curve C, the local ring $\mathcal{O}_p(C)$ is a Noetherian local domain of Krull dimension 1 which is regular, hence a discrete valuation ring by proposition 35.5.2; write ord_p for its valuation and t for a uniformizer. Represent φ near p as $[f_0 : \cdots : f_N]$ with

$f_i \in k(C)$ not all zero, and set

$$e = \min_{0 \le i \le N} \operatorname{ord}_p(f_i)$$

Then $\operatorname{ord}_p(t^{-e} f_i) \ge 0$ for every i, so each $t^{-e} f_i$ lies in $\mathcal{O}_p(C)$ and is defined at p, while $\operatorname{ord}_p(t^{-e} f_j) = 0$ for the index j achieving the minimum, so $t^{-e} f_j(p) \neq 0$ and the tuple is not identically zero at p. Since

$$[t^{-e} f_0 : \cdots : t^{-e} f_N] = [f_0 : \cdots : f_N]$$

as maps to $\mathbb{P}^N_k$, this exhibits φ as regular at p. The image lands in V because V is closed and $\varphi(C)$ is dense in it. If every point of C is nonsingular the argument applies at each, so φ is regular everywhere, as we sought to show.

Projectivity of the target is essential: the rational map $\mathbb{A}^1_k \dashrightarrow \mathbb{A}^1_k$ given by $t \mapsto 1/t$ is undefined at the origin and stays undefined, whereas the same formula into $\mathbb{P}^1_k$ extends by sending 0 to the point at infinity.

42.3 The Intersection Number

Let $f, g \in k[x, y]$ be affine plane curves and $p \in \mathbb{A}^2_k$. The goal is a number $I(p, f \cap g)$ counting how many times the two curves meet at p. Several plausible definitions present themselves, and rather than choose one and hope, the strategy is to write down the properties such a number must have and show that they pin it down uniquely. The list below is Fulton's [102, section 3.3]; for a complementary treatment leaning on complex analysis and on the local picture introduced in chapter 25, see [1].

The list is deliberately not minimal. Computations rarely need its full strength, but proving that the intersection number satisfies all of it is what makes the number usable.

Say that f and g *intersect properly* at p if they have no common component passing through p. The properties are:

1. $I(p, f \cap g)$ is a non-negative integer whenever f and g intersect properly at p, and $I(p, f \cap g) = \infty$ otherwise.
2. $I(p, f \cap g) = 0$ if and only if $p \notin \mathcal{Z}(f) \cap \mathcal{Z}(g)$. In particular $I(p, f \cap g) = 0$ whenever f or g is a nonzero constant.
3. $I(p, f \cap g)$ depends only on the components of f and of g that pass through p.
4. $I(p, f \cap g) = I(p, g \cap f)$.
5. $I(p, f \cap g)$ is invariant under a linear change of coordinates: if T is one and $q = T^{-1}(p)$, then $I(q, f^T \cap g^T) = I(p, f \cap g)$.
6. $I(p, f \cap g) \ge m_p(f)\, m_p(g)$, with equality if and only if f and g have no tangent line in common at p. In particular two curves meeting transversally at a point nonsingular on both have intersection number 1.
7. If $f = \prod_i f_i^{r_i}$ and $g = \prod_j g_j^{s_j}$, then

$$I(p, f \cap g) = \sum_{i,j} r_i s_j\, I(p, f_i \cap g_j)$$

8. $I(p, f \cap g) = I(p, f \cap (g + hf))$ for every $h \in k[x, y]$.

Property (8) is the one that does the work: it says the intersection number sees the ideal (f, g) and not the particular generators, which is exactly the licence needed to run a Euclidean algorithm on the pair.

Theorem 42.3.1: Intersection Number

There is exactly one function $I(p, f \cap g)$ of a point and a pair of affine plane curves satisfying properties (1) through (8), namely

$$I(p, f \cap g) = \dim_k \left(\frac{\mathcal{O}_p(\mathbb{A}^2_k)}{(f, g)} \right)$$

***Proof*:**

Uniqueness. Suppose $I(p, f \cap g)$ satisfies the eight properties. The properties then determine its value, by an algorithm. By (1) it is enough to treat curves intersecting properly at p, and by (5) we may translate so that $p = (0, 0)$. If p does not lie on both curves, (2) gives the value 0, so assume $0 < I(p, f \cap g) < \infty$ and argue by strong induction: suppose the value is known whenever it is smaller than n, and let $I(p, f \cap g) = n$.

Consider the one-variable restrictions $f(x, 0)$ and $g(x, 0)$, of degrees r and s respectively, with the convention that the zero polynomial has degree $-\infty$. By (4) we may assume $r \leq s$.

1. *Case* $f(x, 0) \equiv 0$. Then $y \mid f$, say $f = yh$, and (7) gives

   $$I(p, f \cap g) = I(p, y \cap g) + I(p, h \cap g)$$

   Write $g(x, 0) = x^\ell(a_0 + a_1 x + \cdots)$ with $a_0 \neq 0$; here $\ell > 0$ because $g(0, 0) = 0$. Since $g(x, y) - g(x, 0)$ vanishes on the line $y = 0$, it is divisible by y, so property (8) applied to the pair (y, g) replaces g by $g(x, 0)$ without changing the value. Then (7) splits off the factor $a_0 + a_1 x + \cdots$, which does not vanish at p and so contributes nothing by (2):

   $$I(p, y \cap g) = I(p, y \cap g(x, 0)) = I(p, y \cap x^\ell) = \ell \, I(p, y \cap x) = \ell$$

   the last step by (6), the two lines meeting transversally. Since $\ell > 0$, the remaining term $I(p, h \cap g)$ is strictly less than n and the induction applies.

2. *Case* $r \geq 0$. Scale so that $f(x, 0)$ and $g(x, 0)$ are monic and put $h = g - x^{s-r} f$. The leading terms cancel, so $\deg h(x, 0) = t < s$, while (8) gives

   $$I(p, f \cap g) = I(p, f \cap h)$$

   Repeat on the pair (f, h), interchanging the two by (4) whenever $t < r$. Each step replaces the degree pair (r, s) by (r, t) with $t < s$, so the sum of the two degrees strictly decreases. It cannot decrease forever, so after finitely many steps one of the two restrictions is identically zero and the previous case applies.

So the eight properties leave no freedom, and at most one such function exists.

Existence. It remains to check that $\dim_k \mathcal{O}/(f, g)$, where $\mathcal{O} = \mathcal{O}_p(\mathbb{A}^2_k)$, has the eight properties. Properties (4), (5) and (8) are immediate, since the quantity depends only on the ideal $(f, g)\mathcal{O}$,

which is symmetric in f and g, unchanged by $g \mapsto g + hf$, and carried to the corresponding ideal by a linear change of coordinates. Property (3) holds because a component of f not passing through p is a unit in $\mathcal{O}$ and so contributes nothing to the ideal. Property (2) holds because $\mathcal{O}/(f,g)$ is the zero ring exactly when $(f,g)\mathcal{O} = \mathcal{O}$, that is when some f or g fails to vanish at p. Translating by (5), assume from now on that $p = (0,0)$ and every component of f and g passes through p. What is left is (1), (6) and (7).

Property (1). If f and g have no common component then $\mathcal{Z}(f,g)$ is finite, so corollary 42.2.6 makes $\dim_k \mathcal{O}/(f,g)$ finite. If instead h is a common component, then $(f,g) \subseteq (h)$ and there is a surjection

$$\frac{\mathcal{O}}{(f,g)} \twoheadrightarrow \frac{\mathcal{O}}{(h)}$$

Now $\mathcal{O}/(h) \cong \mathcal{O}_p(\mathcal{Z}(h))$ contains $k[\mathcal{Z}(h)]$, which is infinite-dimensional over k because $\mathcal{Z}(h)$ is a curve. So the left side is infinite-dimensional too.

Property (7). By induction and symmetry it is enough to prove

$$I(p, f \cap gh) = I(p, f \cap g) + I(p, f \cap h)$$

By (1) we may assume f and gh have no common component. Let $\varphi\colon \mathcal{O}/(f,gh) \to \mathcal{O}/(f,g)$ be the natural surjection and let $\psi\colon \mathcal{O}/(f,h) \to \mathcal{O}/(f,gh)$ be the k-linear map $\psi(\overline{z}) = \overline{gz}$. Since dimension is additive along a short exact sequence, it suffices to show that

$$0 \to \frac{\mathcal{O}}{(f,h)} \xrightarrow{\psi} \frac{\mathcal{O}}{(f,gh)} \xrightarrow{\varphi} \frac{\mathcal{O}}{(f,g)} \to 0$$

is exact. Surjectivity of φ is clear, and $\operatorname{im}\psi = \ker\varphi$ because $\ker\varphi = (f,g)/(f,gh)$ is generated by the images of f and g, the first being zero. For injectivity of ψ, suppose $\overline{gz} = \overline{0}$, so that $gz = uf + vgh$ with $u, v \in \mathcal{O}$. Choose $s \in k[x,y]$ with $s(p) \neq 0$ clearing all denominators, and set $A = su$, $B = sv$, $C = sz$, all in $k[x,y]$. Then $gC = Af + Bgh$, that is

$$g(C - Bh) = Af$$

Since f and g have no common factor and $k[x,y]$ is a unique factorization domain, f divides $C - Bh$, say $C - Bh = Df$. Dividing by s, which is a unit in $\mathcal{O}$,

$$z = \frac{B}{s}h + \frac{D}{s}f \in (f,h)\mathcal{O}$$

so $\overline{z} = \overline{0}$ and ψ is injective.

Property (6). Let $m = m_p(f)$, $n = m_p(g)$ and $I = (x,y) \subseteq k[x,y]$. Consider

$$\begin{array}{ccccccc} \frac{k[x,y]}{I^n} \times \frac{k[x,y]}{I^m} & \xrightarrow{\psi} & \frac{k[x,y]}{I^{n+m}} & \xrightarrow{\varphi} & \frac{k[x,y]}{(I^{n+m},f,g)} & \longrightarrow & 0 \\ & & & & \downarrow{\scriptstyle \alpha} & & \\ & & \frac{\mathcal{O}}{(f,g)} & \xrightarrow{\pi} & \frac{\mathcal{O}}{(I^{n+m},f,g)} & \longrightarrow & 0 \end{array}$$

where φ, π, α are the natural maps and $\psi(\overline{a}, \overline{b}) = \overline{af + bg}$, which is well defined because $f \in I^m$ and $g \in I^n$. The top row is exact at the middle and right, though ψ need not be injective, and α is an isomorphism by corollary 42.2.7, since $\mathcal{Z}(I^{n+m}, f, g) \subseteq \{p\}$. Exactness gives

$$\dim_k \frac{k[x,y]}{(I^{n+m},f,g)} = \dim_k \frac{k[x,y]}{I^{n+m}} - \dim_k \ker\varphi \qquad \dim_k \ker\varphi \leq \dim_k \frac{k[x,y]}{I^n} + \dim_k \frac{k[x,y]}{I^m}$$

with equality in the second exactly when ψ is injective. Since π is surjective, chaining these and using $\dim_k k[x,y]/I^t = \frac{t(t+1)}{2}$ gives

$$\begin{aligned} I(p, f\cap g) &= \dim_k \frac{\mathcal{O}}{(f,g)} \\ &\geq \dim_k \frac{\mathcal{O}}{(I^{n+m}, f, g)} \\ &= \dim_k \frac{k[x,y]}{(I^{n+m}, f, g)} \\ &\geq \dim_k \frac{k[x,y]}{I^{n+m}} - \dim_k \frac{k[x,y]}{I^n} - \dim_k \frac{k[x,y]}{I^m} \\ &= \frac{(n+m)(n+m+1)}{2} - \frac{n(n+1)}{2} - \frac{m(m+1)}{2} \;=\; mn \end{aligned}$$

which is the inequality. Equality holds exactly when both steps are equalities, that is when π is an isomorphism, equivalently $I^{n+m} \subseteq (f,g)\mathcal{O}$, and when ψ is injective. That both hold precisely when f and g have no common tangent is lemma 42.3.2, which completes the proof.

The lemma the last step needs is where the tangent lines finally enter the argument, and it is worth isolating because both of its parts are used again in chapter 43.

Lemma 42.3.2: Technical Lemma - Intersection and Tangents

Let f, g be affine plane curves meeting properly at $p = (0,0)$, with $m = m_p(f)$, $n = m_p(g)$, and let $I = (x,y)$. Write ψ for the map of theorem 42.3.1. Then

1. If f and g have no common tangent line at p, then $I^t \subseteq (f,g)\mathcal{O}$ for every $t \geq m+n-1$.
2. ψ is injective if and only if f and g have no common tangent line at p.

***Proof*:**
Let $L_1, \dots, L_m$ be the tangent lines of f at p, listed with multiplicity, and $M_1, \dots, M_n$ those of g. Extend the lists by $L_i = L_m$ for $i > m$ and $M_j = M_n$ for $j > n$, and set

$$A_{ij} = L_1 L_2 \cdots L_i \, M_1 M_2 \cdots M_j$$

with $A_{00} = 1$, so A_{ij} is a form of degree $i+j$. The whole argument rests on the following claim.

Claim: if f and g have no common tangent, then $\{A_{ij} \mid i+j = t\}$ is a k-basis for the space of forms of degree t. There are $t+1$ of them and the space has dimension $t+1$, so it suffices to prove independence. Write $P_i = L_1 \cdots L_i$ and $Q_j = M_1 \cdots M_j$ and suppose $\sum_{i=0}^{t} c_i P_i Q_{t-i} = 0$ with not all c_i zero. Let a be the least and b the greatest index with $c_i \neq 0$. If $a = b$ the relation reads $c_a P_a Q_{t-a} = 0$, impossible in the domain $k[x,y]$. So $a < b$. Every P_i with $i \geq a$ is divisible by P_a, and every Q_{t-i} with $i \leq b$ is divisible by Q_{t-b}, so dividing the relation by $P_a Q_{t-b}$ leaves

$$\sum_{i=a}^{b} c_i \frac{P_i}{P_a} \cdot \frac{Q_{t-i}}{Q_{t-b}} = 0$$

Every term with $i > a$ is divisible by L_{a+1}. Hence L_{a+1} divides the $i = a$ term, which is $c_a \, Q_{t-a}/Q_{t-b}$, a nonzero scalar times a nonempty product of the M_j. But L_{a+1} is a tangent of

f and no M_j is proportional to it, contradicting unique factorization. This proves the claim, and shows exactly where the hypothesis is used.

Part (1). First, $I^t \subseteq (f,g)\mathcal{O}$ for all sufficiently large t. Write $\mathcal{Z}(f,g) = \{p, q_1, \ldots, q_s\}$, which is finite since f and g meet properly, and choose a polynomial h with $h(q_i) = 0$ for every i and $h(p) \neq 0$. Then xh and yh vanish on $\mathcal{Z}(f,g)$, so by the Nullstellensatz (theorem 32.4.4) there is N with $(xh)^N, (yh)^N \in (f,g)$. As h^N is a unit in $\mathcal{O}$, this gives $x^N, y^N \in (f,g)\mathcal{O}$, and every monomial of degree at least $2N$ is divisible by x^N or by y^N, so $I^{2N} \subseteq (f,g)\mathcal{O}$.

Now argue by descending induction on $i+j$ that $A_{ij} \in (f,g)\mathcal{O}$ whenever $i+j \geq m+n-1$, the case $i+j \geq 2N$ being covered by the previous paragraph together with the claim. Given $i+j \geq m+n-1$, one of $i \geq m$ or $j \geq n$ holds; say $i \geq m$, the other case being symmetric with g in place of f. Then $A_{ij} = A_{m0}B$ with $\deg B = i+j-m$. After scaling f so that its lowest form is exactly A_{m0}, write $f = A_{m0} + f'$ with every term of f' of degree at least $m+1$. Multiplying by B and rearranging,

$$A_{ij} = Bf - Bf'$$

Here $Bf \in (f,g)\mathcal{O}$, and every term of Bf' is a form of degree at least $i+j+1$, hence by the claim a combination of the $A_{i'j'}$ with $i'+j' \geq i+j+1$, which lie in $(f,g)\mathcal{O}$ by the inductive hypothesis. So $A_{ij} \in (f,g)\mathcal{O}$. Since the A_{ij} with $i+j=t$ span the forms of degree t, and I^t is spanned by forms of degree at least t, this gives $I^t \subseteq (f,g)\mathcal{O}$ for $t \geq m+n-1$.

Part (2). Suppose first that f and g have no common tangent, and let $\psi(\overline{A}, \overline{B}) = \overline{Af+Bg} = 0$, so that $Af + Bg \in I^{n+m}$. The domain of ψ is $\frac{k[x,y]}{I^n} \times \frac{k[x,y]}{I^m}$, so $\overline{A} \neq 0$ means $r < n$ and $\overline{B} \neq 0$ means $s < m$, where r and s are the orders of A and B, with lowest forms A_r and B_s. Assume for contradiction that $(\overline{A}, \overline{B}) \neq 0$ and consider the possibilities.

If $\overline{B} = 0$ then $B \in I^m$, so $Bg \in I^{m+n}$ and hence $Af \in I^{m+n}$. As $k[x,y]$ is a graded domain the order of Af is $r+m$, so $r+m \geq n+m$, giving $r \geq n$ and $\overline{A} = 0$, contrary to assumption. The case $\overline{A} = 0$ is symmetric.

So $\overline{A} \neq 0 \neq \overline{B}$, that is $r < n$ and $s < m$. The orders of Af and Bg are $r+m$ and $s+n$, both strictly less than $n+m$, so they must be equal, else $Af+Bg$ would have order less than $n+m$. Thus $r+m = s+n$ and the terms of that degree cancel:

$$A_r f_m = -B_s g_n$$

Now f_m and g_n have no common factor, since a common irreducible factor would be a linear form tangent to both curves. So $f_m \big| B_s$ and $g_n \big| A_r$, forcing $s \geq m$ and $r \geq n$ and contradicting $r < n$, $s < m$. Hence $(\overline{A}, \overline{B}) = 0$ and ψ is injective.

Conversely, suppose L is a common tangent and write $f_m = Lf'$, $g_n = Lg'$, so that $\deg f' = m-1$ and $\deg g' = n-1$. Then $\overline{g'} \neq 0$ in $k[x,y]/I^n$ and $\overline{f'} \neq 0$ in $k[x,y]/I^m$, and

$$\psi(\overline{g'}, \overline{-f'}) = \overline{g'f - f'g}$$

The two products $g'f$ and $f'g$ both have order $n+m-1$, and their forms of that degree are $g'f_m = g'Lf'$ and $f'g_n = f'Lg'$, which are equal. So they cancel, $g'f - f'g \in I^{n+m}$, and the image is zero on a nonzero element. Hence ψ is not injective, as we sought to show.

42.4 Computing Intersection Numbers

The proof of theorem 42.3.1 contains an algorithm, and in practice one rarely runs it to the end. Properties (7) and (8) do most of the work: (8) replaces a curve by any convenient representative of the same ideal, and (7) splits off factors. Property (6) then closes out any pair with no common tangent without further computation. The following example is worth working through slowly, because every step is one of those three.

Example 42.4.1: Intersection Number
Let

$$E = (x^2+y^2)^2 + 3x^2y - y^3 = x^4 + 2x^2y^2 + 3x^2y + y^4 - y^3$$
$$F = (x^2+y^2)^3 - 4x^2y^2 = x^6 + 3x^4y^2 + 3x^2y^4 - 4x^2y^2 + y^6$$

and $p = (0,0)$. Over the reals these are the three-leaf and four-leaf roses, $r = -\sin 3\theta$ and $r = |\sin 2\theta|$ in polar coordinates:




Figure 42.1: Three-Leaf Curve




Figure 42.2: Four-Leaf Curve

Both pass through the origin, one with three branches and one with four, so the intersection number there should be substantial.

By (8) replace F with $F - (x^2+y^2)E$, which is

$$-4x^2y^2 - (x^2+y^2)(3x^2y - y^3) = y\big((x^2+y^2)(y^2-3x^2) - 4x^2y\big) = yG$$

so that by (7)

$$I(p, E\cap F) = I(p, E\cap yG) = I(p, E\cap y) + I(p, E\cap G)$$

For the second term, eliminate the quartic part of $G = -3x^4 - 2x^2y^2 - 4x^2y + y^4$ by replacing G with $G + 3E$, again legitimate by (8):

$$G + 3E = 4x^2y^2 + 5x^2y + 4y^4 - 3y^3 = y\big(5x^2 - 3y^2 + 4x^2y + 4y^3\big) = yH$$

Applying (7) once more,

$$I(p, E\cap F) = 2\,I(p, E\cap y) + I(p, E\cap H)$$

The first term is a one-variable computation: $E(x,0) = x^4$, so by (8), (7) and (6),

$$I(p, E \cap y) = I(p, x^4 \cap y) = 4\, I(p, x \cap y) = 4$$

For the second, read off the tangent cones. The lowest form of E is $3x^2y - y^3 = y(\sqrt{3}x - y)(\sqrt{3}x + y)$, so $m_p(E) = 3$ with three distinct tangents; the lowest form of H is $5x^2 - 3y^2 = (\sqrt{5}x - \sqrt{3}y)(\sqrt{5}x + \sqrt{3}y)$, so $m_p(H) = 2$ with two more. No tangent of E is proportional to one of H, so (6) applies with equality and no further computation is needed:

$$I(p, E \cap H) = m_p(E)\, m_p(H) = 3 \cdot 2 = 6$$

Altogether

$$I(p, E \cap F) = 2 \cdot 4 + 6 = 14$$

Two consequences of theorem 42.3.1 are recorded here as further properties, continuing the numbering of the list. The first identifies the intersection number with the order function of definition 42.2.4 whenever one of the curves is nonsingular at p, which is the form chapter 43 uses. The second globalizes: the intersection numbers at all points assemble into a single dimension count.

Corollary 42.4.2: Intersection Number, Order, and the Global Count

Let f, g be affine plane curves. Then

9. If p is a nonsingular point of f, then $I(p, f \cap g) = \operatorname{ord}_p^f(g)$.
10. If f and g have no common component, so that $\mathcal{Z}(f) \cap \mathcal{Z}(g)$ is finite, then

$$\sum_p I(p, f \cap g) = \dim_k \frac{k[x,y]}{(f,g)}$$

***Proof*:**

(9). Since p is a nonsingular point of f, it lies on exactly one component of f and that component is simple by proposition 42.1.7; by property (3) we may replace f by that component and assume f irreducible. Then $\mathcal{O}_p(f)$ is a discrete valuation ring by corollary 42.2.3; let t be a uniformizer and $e = \operatorname{ord}_p^f(\overline{g})$, so that $\overline{g} = ut^e$ for a unit u. Hence $(\overline{g}) = (t^e)$ and

$$\frac{\mathcal{O}_p(f)}{(\overline{g})} = \frac{\mathcal{O}_p(f)}{(t^e)}$$

has $1, t, \ldots, t^{e-1}$ as a k-basis, the residue field being k because k is algebraically closed, so its dimension is e. Finally $\mathcal{O}_p(f) \cong \mathcal{O}_p(\mathbb{A}^2_k)/(f)$ by the third exercise of exercise set 42.4.1, so

$$\frac{\mathcal{O}_p(f)}{(\overline{g})} \cong \frac{\mathcal{O}_p(\mathbb{A}^2_k)}{(f,g)}$$

whose dimension is $I(p, f \cap g)$ by theorem 42.3.1.

(10). With no common component, $\mathcal{Z}(f,g)$ is finite, so corollary 42.2.6 applied to $I = (f,g)$ gives

$$\dim_k \frac{k[x,y]}{(f,g)} = \sum_i \dim_k \frac{\mathcal{O}_{p_i}(\mathbb{A}^2_k)}{(f,g)\mathcal{O}_{p_i}(\mathbb{A}^2_k)} = \sum_i I(p_i, f \cap g)$$

and the points not in $\mathcal{Z}(f,g)$ contribute 0 by property (2), so the sum over all p is the same, completing the proof.

The second statement is the bridge to chapter 43: it converts a sum of local invariants into the dimension of a single ring, and Bézout's theorem is what happens when that ring is computed for two projective curves by a graded argument.

Exercise 42.4.1

1. Let $p = (0, \dots, 0) \in \mathbb{A}^n_k$. Show that the maximal ideal $\mathfrak{m} \subseteq \mathcal{O}_p(\mathbb{A}^n_k)$ is generated by $x_1, \dots, x_n$.

2. Let $I = (x, y) \subseteq k[x, y]$. Show that the monomials of degree less than n form a k-basis of $k[x, y]/I^n$, and deduce that
$$\dim_k \left(\frac{k[x,y]}{I^n} \right) = 1 + 2 + \cdots + n = \frac{n(n+1)}{2}$$

3. Let $V \subseteq \mathbb{A}^n_k$ be a variety with ideal $\mathcal{I}(V) \subseteq R = k[x_1, \dots, x_n]$, let $p \in V$, and let $J \subseteq R$ be an ideal containing $\mathcal{I}(V)$, with image $\overline{J}$ in $k[V]$. Show that
$$\frac{\mathcal{O}_p(\mathbb{A}^n_k)}{J\,\mathcal{O}_p(\mathbb{A}^n_k)} \cong \frac{\mathcal{O}_p(V)}{\overline{J}\,\mathcal{O}_p(V)}$$
and deduce the case $J = \mathcal{I}(V)$, namely $\mathcal{O}_p(\mathbb{A}^n_k)/\mathcal{I}(V)\mathcal{O}_p(\mathbb{A}^n_k) \cong \mathcal{O}_p(V)$.

4. Compute $m_p(f)$ and the tangent lines at the origin for $f = y^2 - x^3$, $f = y^2 - x^2 - x^3$, $f = x^4 - x^2y^2 + y^4$ and $f = (x^2 + y^2)^2 + 3x^2y - y^3$. Which of the four have an ordinary singular point there?

5. Compute $I(p, f \cap g)$ at the origin for $f = y - x^2,\ g = y$; then for $f = y^2 - x^3,\ g = y$; then for $f = y^2 - x^3,\ g = x$. Check each against property (6).

6. Show that $I(p, f \cap g) = 1$ if and only if p is a nonsingular point of both curves and their tangent lines there are distinct.

7. Let f be an irreducible plane curve and p a nonsingular point of it. Show directly from definition 42.2.4 that $\operatorname{ord}_p^f(gh) = \operatorname{ord}_p^f(g) + \operatorname{ord}_p^f(h)$ and that $\operatorname{ord}_p^f(g+h) \geq \min(\operatorname{ord}_p^f(g), \operatorname{ord}_p^f(h))$, with an example where the second is strict.

43

Bézout's Theorem and Max Noether's Theorem

With the intersection number in hand the counting theorem is within reach. The proof is a dimension count in a graded ring: two curves with no common component generate an ideal whose quotient has dimension mn in every large degree, and the sum of the intersection numbers is exactly that dimension. Everything the theorem says about individual points is a consequence of that one budget being finite.

Max Noether's theorem then answers the converse question. Given that a curve passes through the points where two others meet, when is it an algebraic combination of them? The answer is local: a condition at each intersection point suffices, and checking it is cheap wherever the intersection is transversal. The chapter closes with two theorems of classical projective geometry, Pascal's and Pappus's, which fall out of a single application of that criterion to a cubic that splits into three lines.

43.1 Bézout's Theorem

Projective space was introduced so that intersections would stop disappearing, and for plane curves it delivers completely: two curves with no common component always meet, and the number of points, weighted by the intersection numbers of chapter 42, is exactly the product of the degrees.

The result is special to curves in $\mathbb{P}^2_k$, not a general feature of projective varieties. In $\mathbb{P}^3_k$ the point $\mathcal{Z}(x, y, w)$ and the plane $\mathcal{Z}(z)$ do not meet at all, and there is no weighting that would make them. What makes the plane-curve case work is that two curves in $\mathbb{P}^2_k$ have complementary dimension, so theorem 40.6.3 already guarantees they meet. Bézout's theorem sharpens that from "at least one point" to an exact count.

Theorem 43.1.1: Bézout's Theorem

Let f and g be projective plane curves of degrees m and n with no common component. Then $\mathcal{Z}(f) \cap \mathcal{Z}(g)$ is finite and

$$\sum_{p \in \mathbb{P}^2_k} I(p, f \cap g) = mn$$

***Proof*:**

Setting up. Since f and g have no common component, $\mathcal{Z}(f) \cap \mathcal{Z}(g)$ is a proper closed subset of the curve $\mathcal{Z}(f)$, hence has dimension 0 and is finite. The field k is infinite, so a linear change of coordinates moves the line at infinity off that finite set; assume from now on that no point of $\mathcal{Z}(f) \cap \mathcal{Z}(g)$ lies on $\mathcal{Z}(z)$. Write $f_* = f(x, y, 1)$ and $g_* = g(x, y, 1)$ for the dehomogenizations. Every intersection point now lies in the standard affine chart, where the intersection numbers agree with the affine ones, so property (10) of corollary 42.4.2 gives

$$\sum_p I(p, f \cap g) = \sum_p I(p, f_* \cap g_*) = \dim_k \frac{k[x, y]}{(f_*, g_*)}$$

Abbreviate

$$\Gamma_* = \frac{k[x, y]}{(f_*, g_*)} \qquad \Gamma = \frac{k[x, y, z]}{(f, g)} \qquad R = k[x, y, z]$$

Here R and Γ are graded, and R_d, Γ_d denote their degree-d pieces. The theorem follows from the two claims

$$\dim_k \Gamma_* \overset{1}{=} \dim_k \Gamma_d \overset{2}{=} mn \qquad (d \geq m + n)$$

Claim 2: $\dim_k \Gamma_d = mn$ *for* $d \geq m + n$. Define

$$\begin{aligned} \psi &\colon R \to R \times R & \psi(c) &= (gc, -fc) \\ \varphi &\colon R \times R \to R & \varphi(a, b) &= af + bg \\ \pi &\colon R \to \Gamma & \pi(h) &= \overline{h} \end{aligned}$$

The sequence

$$0 \to R \xrightarrow{\psi} R \times R \xrightarrow{\varphi} R \xrightarrow{\pi} \Gamma \to 0$$

is exact. Indeed ψ is injective because R is a domain; $\varphi\psi = 0$ by inspection; if $\varphi(a, b) = 0$ then $af = -bg$, and as f, g have no common factor in the unique factorization domain R we get $g \mid a$, say $a = gc$, whence $b = -fc$ and $(a, b) = \psi(c)$; finally $\operatorname{im}\varphi = (f, g) = \ker \pi$.

Everything is homogeneous, so the sequence restricts in each degree. Since $\deg f = m$ and $\deg g = n$,

$$0 \to R_{d-m-n} \xrightarrow{\psi} R_{d-m} \times R_{d-n} \xrightarrow{\varphi} R_d \xrightarrow{\pi} \Gamma_d \to 0$$

is exact, and for $d \geq m + n$ every term is a finite-dimensional space of forms, with $\dim_k R_j = \binom{j+2}{2} = \frac{(j+1)(j+2)}{2}$ for $j \geq 0$. Alternating dimensions along an exact sequence sum to zero, so

$$\dim_k \Gamma_d = \dim_k R_d - \dim_k R_{d-m} - \dim_k R_{d-n} + \dim_k R_{d-m-n}$$

Writing $P(j) = (j + 1)(j + 2)$, this is $\frac{1}{2}\big[P(d) - P(d - m) - P(d - n) + P(d - m - n)\big]$. The linear and constant parts of P cancel in that combination, leaving only the quadratic part:

$$d^2 - (d - m)^2 - (d - n)^2 + (d - m - n)^2 = 2mn$$

so $\dim_k \Gamma_d = mn$, which is Claim 2.

Multiplication by z is injective on Γ. This is the technical heart of Claim 1, and it is also used again in theorem 43.3.2. Let $\alpha\colon \Gamma \to \Gamma$ be $\alpha(\overline{h}) = \overline{zh}$ and suppose $\overline{zh} = \overline{0}$, so $zh = af + bg$ for some $a, b \in R$. For a form $u \in R$ write $u_0 = u(x, y, 0)$ for its restriction to the line at infinity. Because $\mathcal{Z}(f) \cap \mathcal{Z}(g) \cap \mathcal{Z}(z) = \emptyset$, the forms f_0 and g_0 have no common zero in $\mathbb{P}^1_k$ and so are relatively prime in $k[x, y]$. Setting $z = 0$ in $zh = af + bg$ gives

$$0 = a_0 f_0 + b_0 g_0$$

so $a_0 f_0 = -b_0 g_0$, and coprimality yields $c \in k[x, y]$ with

$$b_0 = f_0 c \qquad a_0 = -g_0 c$$

Now put $a_1 = a + cg$ and $b_1 = b - cf$. Then $a_1 f + b_1 g = af + bg + cgf - cfg = zh$, while

$$(a_1)_0 = -g_0 c + c g_0 = 0 \qquad (b_1)_0 = f_0 c - c f_0 = 0$$

so both are divisible by z, say $a_1 = za'$ and $b_1 = zb'$. Then $z(a'f + b'g) = zh$, and cancelling z in the domain R gives $h = a'f + b'g$, that is $\overline{h} = \overline{0}$. So α is injective.

Claim 1: $\dim_k \Gamma_* = \dim_k \Gamma_d$ *for* $d \geq m+n$. By the previous paragraph α restricts to an injection $\Gamma_d \hookrightarrow \Gamma_{d+1}$, and both have dimension mn by Claim 2, so it is an isomorphism. Consequently, if $\beta_1, \ldots, \beta_{mn} \in R_d$ have residues forming a basis of Γ_d, then for every $r \geq 0$ the residues of $z^r\beta_1, \ldots, z^r\beta_{mn}$ form a basis of Γ_{d+r}.

Let $b_i \in \Gamma_*$ be the residue of $(\beta_i)_* = \beta_i(x, y, 1)$. These span: given $\overline{h} \in \Gamma_*$ with $h \in k[x, y]$, let h^* be its homogenization, of some degree e, and choose r with $d + r \geq e$. Then $z^{d+r-e}h^*$ is a form of degree $d + r$, so

$$z^{d+r-e}h^* = \sum_{i=1}^{mn} \lambda_i z^r \beta_i + Af + Bg$$

for scalars λ_i and forms A, B. Dehomogenizing, that is setting $z = 1$, gives

$$h = \sum_i \lambda_i (\beta_i)_* + A_* f_* + B_* g_*$$

so $\overline{h} = \sum_i \lambda_i b_i$.

They are independent: suppose $\sum_i \lambda_i b_i = 0$, so that $\sum_i \lambda_i (\beta_i)_* = Af_* + Bg_*$ for some $A, B \in k[x, y]$. Homogenizing and clearing the powers of z that appear gives $r, s, t \geq 0$ with

$$z^r \sum_i \lambda_i \beta_i = z^s A^* f + z^t B^* g$$

so $\sum_i \lambda_i \overline{z^r \beta_i} = \overline{0}$ in Γ_{d+r}. As those residues form a basis, every $\lambda_i = 0$.

So $b_1, \ldots, b_{mn}$ is a basis of Γ_* and $\dim_k \Gamma_* = mn$, as we sought to show.

Example 43.1.2: Bézout in Practice

Every count below is over an algebraically closed field and in $\mathbb{P}^2_k$, where alone the statement holds.

1. *Two conics.* Degrees 2 and 2, so the intersection has total weight 4. For $\mathcal{Z}(x^2+y^2-z^2)$ and $\mathcal{Z}(x^2-yz)$ a direct substitution gives four distinct points, each counted once. Two general conics meet in four points.
2. *Tangency absorbs the count.* For the circle $\mathcal{Z}(x^2+y^2-z^2)$ and the line $\mathcal{Z}(y-z)$, substituting $y=z$ gives $x^2=0$, a double root: the line is tangent at $[0:1:1]$, and $I(p, C\cap L)=2$. The total is still $2\cdot 1=2$, all concentrated at one point.
3. *Where affine intuition fails.* The two parabolas $\mathcal{Z}(y-x^2)$ and $\mathcal{Z}(y-x^2-1)$ do not meet in $\mathbb{A}^2_k$ at all. Homogenizing gives $\mathcal{Z}(yz-x^2)$ and $\mathcal{Z}(yz-x^2-z^2)$, and subtracting, $z^2=0$: the two meet only where $z=0$, at $[0:1:0]$, with $I=4$. The four intersections predicted by $2\cdot 2$ are all at infinity, which is what projective space was introduced to see.
4. *A line and a cubic.* Degrees 1 and 3 give three points. For the cubic $\mathcal{Z}(y^2z-x^3+xz^2)$ and the line $\mathcal{Z}(z)$, substituting $z=0$ gives $x^3=0$: the line at infinity meets the cubic only at $[0:1:0]$, with multiplicity 3. That point is an inflection, which is why theorem 48.4.4 can put a genus-one curve in Weierstrass form with its base point there.

43.2 Consequences and Bounds on Multiplicity

Bézout's theorem is a budget: mn is all the intersection there is, and every local contribution is drawn against it. Most of its corollaries are that observation combined with the lower bound $I(p, f\cap g)\geq m_p(f)m_p(g)$ from property (6).

Corollary 43.2.1: Degree and Multiplicity

Let f, g be projective plane curves with no common component. Then

$$\sum_p m_p(f)\, m_p(g) \leq \deg(f)\deg(g)$$

***Proof*:**

Property (6) of the intersection number gives $I(p, f\cap g)\geq m_p(f)m_p(g)$ at every p, and summing over p against theorem 43.1.1 bounds the total by $\deg(f)\deg(g)$, completing the proof.

Corollary 43.2.2: Intersection and Simple Points

Let f, g be projective plane curves of degrees m and n with no common component. If $\mathcal{Z}(f)$ and $\mathcal{Z}(g)$ meet in mn distinct points, then every one of those points is a nonsingular point of both curves, and the two curves are transversal there.

***Proof*:**
The mn points each contribute at least 1 to a total of mn by theorem 43.1.1, so each contributes exactly 1. Property (6) then forces $m_p(f)m_p(g) \leq 1$, so both multiplicities are 1 and p is nonsingular on both by definition 42.1.5. Equality in (6) additionally says the curves share no tangent at p, which for two nonsingular points is transversality, completing the proof.

Corollary 43.2.3: Intersection and Common Component

If two projective plane curves of degrees m and n have more than mn points in common, they have a common component.

***Proof*:**
Were there no common component, theorem 43.1.1 would bound the number of common points by $\sum_p I(p, f \cap g) = mn$, since each contributes at least 1 by property (2), completing the proof.

The next bound goes the other way: it limits how singular a single irreducible curve can be. Both the crude and the sharp form are worth having, and the crude one is what permits the argument for the sharp one.

Corollary 43.2.4: Bounding Multiplicity

Let f be an irreducible projective plane curve of degree n. Then f has finitely many singular points and

$$\sum_p \frac{m_p(f)\big(m_p(f)-1\big)}{2} \leq \frac{n(n-1)}{2}$$

***Proof*:**
Not every partial derivative of f vanishes identically. In characteristic zero this is because f is nonconstant. In characteristic $\rho > 0$, if all three vanished then every exponent appearing in f would be divisible by ρ, so $f \in k[x^\rho, y^\rho, z^\rho]$; as k is algebraically closed its elements are ρ-th powers, and the Frobenius is a ring homomorphism, so $f = h^\rho$ for some h, contradicting irreducibility. Let g be a nonzero partial derivative of f, a form of degree $n-1$.

At every point p, $m_p(g) \geq m_p(f) - 1$. Change coordinates so that $p = [0:0:1]$ and work in the chart $z = 1$, writing $f_* = f(x, y, 1)$ and $m = m_p(f)$. A linear change of coordinates replaces each partial derivative by a linear combination of the three partials, and multiplicity of a sum is at least the minimum of the multiplicities, so it is enough to check the bound for all three partials of the transformed form. Dehomogenization commutes with ∂_x and ∂_y, and differentiating drops the degree of each homogeneous piece of f_* by one, so $m_p(\partial_x f_*)$ and $m_p(\partial_y f_*)$ are both at least $m-1$. For the third, Euler's relation (exercise set 38.5.1(5)) $nf = x\partial_x f + y\partial_y f + z\partial_z f$ dehomogenizes to

$$(\partial_z f)_* = n f_* - x\,\partial_x f_* - y\,\partial_y f_*$$

Each term on the right has multiplicity at least m at the origin, the last two because a factor of x or y adds one to a multiplicity of at least $m-1$. So $m_p((\partial_z f)_*) \geq m$, which is more than required.

Since f is irreducible of degree n and g is a nonzero form of degree $n-1 < n$, they have no

common component. Corollary 43.2.1 therefore gives

$$\sum_p m_p(f)\big(m_p(f)-1\big) \le \sum_p m_p(f)\, m_p(g) \le n(n-1)$$

which is the inequality after dividing by 2. In particular only finitely many p have $m_p(f) \ge 2$, so the singular points are finite in number, as we sought to show.

The sharp form replaces n by $n-1$ on the right, and its proof is the standard count of how many conditions singularities impose on curves of degree $n-1$.

Corollary 43.2.5: Sharp Bound on Multiplicity

Let f be an irreducible projective plane curve of degree n. Then

$$\sum_p \frac{m_p(f)\big(m_p(f)-1\big)}{2} \le \frac{(n-1)(n-2)}{2}$$

***Proof*:**
Write $m_p = m_p(f)$ and $M = \sum_p \binom{m_p}{2}$, a finite sum by corollary 43.2.4. The forms of degree $n-1$ in three variables constitute a projective space of dimension $\binom{n+1}{2} - 1 = \frac{(n-1)(n+2)}{2}$. Requiring a curve g of degree $n-1$ to satisfy $m_p(g) \ge m_p - 1$ is the vanishing of all partial derivatives of order less than $m_p - 1$ at p, which is $\binom{m_p}{2}$ linear conditions, and requiring g to pass through a further point is one more. Set

$$r = \frac{(n-1)(n+2)}{2} - M$$

This is non-negative: corollary 43.2.4 gives $M \le \frac{n(n-1)}{2}$, and $\frac{n(n-1)}{2} \le \frac{(n-1)(n+2)}{2}$. So r further conditions may be imposed, and since f has infinitely many points while only finitely many are singular, nonsingular points $q_1, \dots, q_r \in \mathcal{Z}(f)$ may be chosen. The $M + r$ conditions cannot exhaust a projective space of dimension $M + r$, so a curve g of degree $n-1$ exists with $m_p(g) \ge m_p - 1$ at every singular point of f and $m_{q_i}(g) \ge 1$ for each i.

As before f is irreducible of degree n and g is a nonzero form of degree $n-1$, so they share no component and corollary 43.2.1 applies:

$$n(n-1) \;\ge\; \sum_p m_p(m_p-1) \;+\; r \;=\; 2M + \frac{(n-1)(n+2)}{2} - M$$

the r appearing because each q_i contributes $m_{q_i}(f)m_{q_i}(g) \ge 1$ and is not among the singular points already counted. Rearranging,

$$M \le n(n-1) - \frac{(n-1)(n+2)}{2} = (n-1)\cdot\frac{2n-n-2}{2} = \frac{(n-1)(n-2)}{2}$$

as we sought to show.

The sharp bound is attained: the curve $\mathcal{Z}(x^n + y^{n-1}z)$ is irreducible of degree n and has multiplicity $n-1$ at $[0:0:1]$, since dehomogenizing there leaves $x^n + y^{n-1}$ with lowest form y^{n-1}. That single

point already contributes $\binom{n-1}{2}$, so no other singularity is available. The quantity $\frac{(n-1)(n-2)}{2}$ is the *arithmetic genus* of a plane curve of degree n, and chapter 44 will meet it again.

43.3 Max Noether's Fundamental Theorem

Bézout's theorem counts the intersection of two curves; the natural next question is what that intersection determines. The data of an intersection is a set of points together with a weight at each, and such data forms a group under addition.

Definition 43.3.1: Zero-cycle

A *zero-cycle* on $\mathbb{P}^2_k$ is a formal sum $\sum_p n_p\, p$ over points $p \in \mathbb{P}^2_k$ with $n_p \in \mathbb{Z}$ and all but finitely many $n_p = 0$. Its *degree* is $\sum_p n_p$.

Adding coefficientwise makes the zero-cycles an abelian group, and writing $\sum_p n_p p \le \sum_p m_p p$ when $n_p \le m_p$ for every p orders it. For projective plane curves f, g with no common component, the *intersection cycle* is

$$f \cdot g = \sum_{p \in \mathbb{P}^2_k} I(p, f \cap g)\, p$$

which is a zero-cycle of degree $\deg(f)\deg(g)$ by theorem 43.1.1. The properties of the intersection number transfer directly:

1. $f \cdot g = g \cdot f$;
2. $f \cdot (gh) = f \cdot g + f \cdot h$;
3. $f \cdot (g + af) = f \cdot g$ for every form a of degree $\deg(g) - \deg(f)$.

It is tempting to hope that every effective zero-cycle, meaning one with all $n_p \ge 0$, arises as an intersection cycle. It does not. Take three points of $\mathbb{P}^2_k$ in general position and the cycle $p_1 + p_2 + p_3$, of degree 3. Realizing it as $f \cdot g$ would need $\deg(f)\deg(g) = 3$, so one of the curves is a line, and that line would have to contain all three points, which they are not chosen to admit. The obstruction is exactly the phenomenon that chapter 44 organizes into the divisor class group: which formal sums of points are cut out by equations is a question with a non-trivial answer, and the answer is an invariant of the curve.

The question this section settles is the relative version. Suppose f, g, h are curves with $g \cdot f \le h \cdot f$, so that h meets f at least as heavily as g does at every point. Is the difference itself an intersection cycle, that is, is there a curve b with

$$b \cdot f = h \cdot f - g \cdot f$$

Comparing degrees, such a b must have degree $\deg(h) - \deg(g)$. And it is enough to find forms a, b with

$$h = af + bg$$

for then property (3) followed by property (2) gives $h \cdot f = (bg) \cdot f = b \cdot f + g \cdot f$, which rearranges to the display. So the geometric question reduces to an algebraic one: when does h lie in the ideal

generated by f and g, with the degrees working out? Max Noether's theorem answers it, and the answer is local.

Theorem 43.3.2: Max Noether's Fundamental Theorem

Let f, g, h be projective plane curves with f and g having no common component. Then there exist forms a, b of degrees $\deg(h) - \deg(f)$ and $\deg(h) - \deg(g)$ with

$$h = af + bg$$

if and only if for every $p \in \mathcal{Z}(f) \cap \mathcal{Z}(g)$ the local condition

$$h_* \in (f_*, g_*)\,\mathcal{O}_p(\mathbb{P}^2_k)$$

holds, where the subscript denotes dehomogenization in an affine chart containing p.

The local condition is called *Noether's condition* at p. That a global identity is equivalent to a finite list of local ones makes this a *local-to-global* theorem, and it is the reason the corollaries below are as easy as they are: each is a way of certifying the local condition cheaply.

***Proof*:**

One direction is immediate: if $h = af + bg$, then dehomogenizing at any p gives $h_* = a_* f_* + b_* g_*$, so h_* lies in $(f_*, g_*)\mathcal{O}_p(\mathbb{P}^2_k)$.

For the converse, change coordinates so that $\mathcal{Z}(f) \cap \mathcal{Z}(g) \cap \mathcal{Z}(z) = \emptyset$, which is possible because the intersection is finite, and dehomogenize in the chart $z = 1$. Noether's condition says the residue of h_* in $\mathcal{O}_p(\mathbb{A}^2_k)/(f_*, g_*)$ vanishes for every $p \in \mathcal{Z}(f_*, g_*)$. By lemma 42.2.5 the ring $k[x, y]/(f_*, g_*)$ is the product of those local quotients, so the residue of h_* there vanishes too:

$$h_* = \alpha f_* + \beta g_* \qquad \alpha, \beta \in k[x, y]$$

Homogenizing and clearing the powers of z introduced gives $r \geq 0$ and forms A, B with

$$z^r h = Af + Bg$$

Multiplication by z on $\Gamma = k[x, y, z]/(f, g)$ is injective, as established inside the proof of theorem 43.1.1, so cancelling z one factor at a time from $\overline{z^r h} = \overline{0}$ leaves $\overline{h} = \overline{0}$, that is $h = a'f + b'g$ for some forms a', b', not necessarily homogeneous.

Finally, extract the right graded pieces. Write $a' = \sum_i a'_i$ and $b' = \sum_i b'_i$ with a'_i, b'_i homogeneous of degree i. Comparing homogeneous components of degree $\deg h$ in $h = a'f + b'g$, and using that h is itself homogeneous, gives

$$h = a'_s f + b'_t g \qquad s = \deg(h) - \deg(f), \quad t = \deg(h) - \deg(g)$$

since those are the only pieces contributing in that degree. Taking $a = a'_s$ and $b = b'_t$ completes the proof.

Verifying Noether's condition directly is unpleasant. The following criteria cover every case that arises in practice.

Proposition 43.3.3: Noether's Criterion

Let f, g, h be projective plane curves and $p \in \mathcal{Z}(f) \cap \mathcal{Z}(g)$. Each of the following implies Noether's condition at p:

1. f and g meet transversally at p, and $p \in \mathcal{Z}(h)$;
2. p is a nonsingular point of f, and $I(p, h \cap f) \geq I(p, g \cap f)$;
3. f and g have no tangent line in common at p, and $m_p(h) \geq m_p(f) + m_p(g) - 1$.

***Proof*:**

(2). Since p is a nonsingular point of f, property (9) of corollary 42.4.2 converts both intersection numbers into orders, so the hypothesis reads $\operatorname{ord}_p^f(h_*) \geq \operatorname{ord}_p^f(g_*)$. In the discrete valuation ring $\mathcal{O}_p(f)$ that says

$$\overline{h}_* \in (\overline{g}_*) \subseteq \mathcal{O}_p(f)$$

Now $\mathcal{O}_p(f) \cong \mathcal{O}_p(\mathbb{A}^2_k)/(f_*)$ by the third exercise of exercise set 42.4.1, so $\mathcal{O}_p(f)/(\overline{g}_*) \cong \mathcal{O}_p(\mathbb{A}^2_k)/(f_*, g_*)$ and the residue of h_* there is zero, which is Noether's condition.

(3). Take $p = [0 : 0 : 1]$ and write $I = (x, y)$, $m = m_p(f)$, $n = m_p(g)$. The hypothesis $m_p(h) \geq m + n - 1$ says $h_* \in I^{m+n-1}$, and lemma 42.3.2(1) says $I^t \subseteq (f_*, g_*)\mathcal{O}_p(\mathbb{A}^2_k)$ for every $t \geq m + n - 1$ precisely because f and g have no common tangent. Hence $h_* \in (f_*, g_*)\mathcal{O}_p(\mathbb{A}^2_k)$.

(1). Transversality makes $m_p(f) = m_p(g) = 1$ with distinct tangents, so (3) applies with the requirement $m_p(h) \geq 1 + 1 - 1 = 1$, which is exactly $p \in \mathcal{Z}(h)$, completing the proof.

Corollary 43.3.4: Sufficient Condition For Max Noether's Theorem

Let f, g, h be projective plane curves with f and g having no common component, and suppose either

1. $\mathcal{Z}(f)$ and $\mathcal{Z}(g)$ meet in $\deg(f)\deg(g)$ distinct points and h passes through all of them, or
2. every point of $\mathcal{Z}(f) \cap \mathcal{Z}(g)$ is a nonsingular point of f, and $h \cdot f \geq g \cdot f$.

Then there is a curve b of degree $\deg(h) - \deg(g)$ with

$$b \cdot f = h \cdot f - g \cdot f$$

***Proof*:**

In case (1), corollary 43.2.2 says the $\deg(f)\deg(g)$ points are transversal intersections, so proposition 43.3.3(1) gives Noether's condition at each. In case (2), the hypothesis $h \cdot f \geq g \cdot f$ is exactly $I(p, h \cap f) \geq I(p, g \cap f)$ at every p, so proposition 43.3.3(2) applies. Either way theorem 43.3.2 produces $h = af + bg$ with b of degree $\deg(h) - \deg(g)$, and the computation preceding that theorem turns the identity into the stated equation of cycles, completing the proof.

43.4 Application: Pascal's and Pappus's Theorems

Max Noether's theorem is a statement about ideals, and its geometric consequences are about incidence. Two of them are theorems of classical projective geometry, one from the fourth century and one from the seventeenth, and both come out of the same three-line computation: a cubic that splits into three lines, a conic, and the observation that Noether's condition is automatic at a transversal intersection.

The shared setup is this. Let Q be a conic and let $p_1, \dots, p_6$ be six distinct points on $\mathcal{Z}(Q)$, thought of as the vertices of a hexagon in that cyclic order. Its six sides split into two alternating triples,

$$L_1 = \overline{p_1p_2}, \quad L_2 = \overline{p_3p_4}, \quad L_3 = \overline{p_5p_6} \qquad M_1 = \overline{p_2p_3}, \quad M_2 = \overline{p_4p_5}, \quad M_3 = \overline{p_6p_1}$$

and the three pairs of *opposite* sides are (L_1, M_2), (M_1, L_3) and (L_2, M_3). Write $C = L_1L_2L_3$ and $C' = M_1M_2M_3$, both cubics.

Lemma 43.4.1: The Hexagon Identity

With the notation above, suppose that no side of the hexagon meets $\mathcal{Z}(Q)$ outside the two vertices it joins. Then there are a constant $\lambda \in k$ and a linear form ℓ, not identically zero, with

$$M_1M_2M_3 = \lambda\, L_1L_2L_3 + \ell\, Q$$

***Proof*:**
Apply theorem 43.3.2 to $f = C$, $g = Q$ and $h = C'$. The curves C and Q have no common component, since each L_i meets $\mathcal{Z}(Q)$ in the two points p_{2i-1}, p_{2i} and so is not contained in it. By hypothesis $\mathcal{Z}(C) \cap \mathcal{Z}(Q)$ is exactly $\{p_1, \dots, p_6\}$, which is $\deg(C)\deg(Q) = 3 \cdot 2 = 6$ distinct points, so corollary 43.2.2 makes every one of them a transversal intersection. Each p_i also lies on C': the vertex p_j lies on M_1, M_2 or M_3 according to its index. So proposition 43.3.3(1) gives Noether's condition at all six points, and theorem 43.3.2 gives

$$C' = aC + bQ$$

with $\deg a = 3 - 3 = 0$ and $\deg b = 3 - 2 = 1$; write $\lambda = a$ and $\ell = b$.

It remains to rule out $\ell = 0$, which would force $M_1M_2M_3 = \lambda L_1L_2L_3$ and hence, by unique factorization, make each M_i proportional to some L_j. That cannot happen: L_j meets $\mathcal{Z}(Q)$ in $\{p_{2j-1}, p_{2j}\}$ and M_i meets it in the corresponding pair for M_i, and the three pairs $\{p_1, p_2\}, \{p_3, p_4\}, \{p_5, p_6\}$ are disjoint from the three pairs $\{p_2, p_3\}, \{p_4, p_5\}, \{p_6, p_1\}$ as unordered pairs, the six vertices being distinct, as we sought to show.

Theorem 43.4.2: Pascal's Theorem

Let a hexagon with distinct vertices be inscribed in an irreducible conic. Then the three points in which the pairs of opposite sides meet are collinear.

***Proof*:**
Let Q be the conic and adopt the notation above. The hypothesis of lemma 43.4.1 holds: a line meets the irreducible conic $\mathcal{Z}(Q)$ in at most two points by theorem 43.1.1, since it is not a component of it, so each side meets $\mathcal{Z}(Q)$ exactly in its two vertices. Let λ and ℓ be as in that lemma.

Let r_1 be the point $L_1 \cap M_2$, the meeting of a pair of opposite sides, and define r_2 and r_3 from the pairs (M_1, L_3) and (L_2, M_3). Evaluating the identity of lemma 43.4.1 at r_1: the left side vanishes because $M_2(r_1) = 0$, and the term $\lambda L_1 L_2 L_3$ vanishes because $L_1(r_1) = 0$. Hence

$$\ell(r_1)\, Q(r_1) = 0$$

Now $Q(r_1) \neq 0$. For r_1 lies on L_1, whose only points on $\mathcal{Z}(Q)$ are p_1 and p_2, and on M_2, whose only points on $\mathcal{Z}(Q)$ are p_4 and p_5; were r_1 on $\mathcal{Z}(Q)$ it would belong to both pairs, which are disjoint. Therefore $\ell(r_1) = 0$, and the same computation gives $\ell(r_2) = \ell(r_3) = 0$. As ℓ is a nonzero linear form, $\mathcal{Z}(\ell)$ is a line containing all three points, as we sought to show.

Pappus's theorem is the case in which the conic degenerates into a pair of lines. The hexagon then has its vertices alternating between the two lines, and the argument runs unchanged.

Theorem 43.4.3: Pappus's Theorem

Let L and L' be distinct lines, and let p_1, p_2, p_3 be distinct points of $\mathcal{Z}(L)$ and q_1, q_2, q_3 distinct points of $\mathcal{Z}(L')$, none of the six equal to the point $\mathcal{Z}(L) \cap \mathcal{Z}(L')$. Put

$$r_1 = \overline{p_1 q_2} \cap \overline{q_1 p_2}, \qquad r_2 = \overline{q_2 p_3} \cap \overline{p_2 q_3}, \qquad r_3 = \overline{p_3 q_1} \cap \overline{q_3 p_1}$$

Then r_1, r_2, r_3 are collinear.

***Proof*:**
Take $Q = LL'$, a conic, and the hexagon with vertices $p_1, q_2, p_3, q_1, p_2, q_3$ in that cyclic order, all six lying on $\mathcal{Z}(Q)$ and all distinct. Its alternating side-triples are

$$\overline{p_1 q_2},\ \overline{p_3 q_1},\ \overline{p_2 q_3} \qquad \text{and} \qquad \overline{q_2 p_3},\ \overline{q_1 p_2},\ \overline{q_3 p_1}$$

and the three r_i are the intersections of the opposite pairs.

The hypothesis of lemma 43.4.1 holds. A side such as $\overline{p_1 q_2}$ joins a point of $\mathcal{Z}(L)$ to a point of $\mathcal{Z}(L')$, and it is equal to neither line, since $q_2 \notin \mathcal{Z}(L)$ and $p_1 \notin \mathcal{Z}(L')$ by the hypothesis on the six points. So it meets $\mathcal{Z}(L)$ only at p_1 and $\mathcal{Z}(L')$ only at q_2, and therefore meets $\mathcal{Z}(Q)$ exactly in its two vertices. Let λ and ℓ be as in the lemma.

Evaluating at r_1 exactly as in theorem 43.4.2 gives $\ell(r_1)Q(r_1) = 0$, so it remains to check $Q(r_1) \neq 0$, that is $r_1 \notin \mathcal{Z}(L) \cup \mathcal{Z}(L')$. Suppose $r_1 \in \mathcal{Z}(L)$. Then r_1 lies on $\overline{p_1 q_2}$, which meets $\mathcal{Z}(L)$ only at p_1, so $r_1 = p_1$; and r_1 lies on $\overline{q_1 p_2}$, which meets $\mathcal{Z}(L)$ only at p_2, so $r_1 = p_2$. These contradict $p_1 \neq p_2$. The case $r_1 \in \mathcal{Z}(L')$ is symmetric, using $q_2 \neq q_1$. Hence $\ell(r_1) = 0$, likewise for r_2 and r_3, and $\mathcal{Z}(\ell)$ is the required line, as we sought to show.

43.5 The Dual Curve and Plücker's Formulas

A nonsingular point of a plane curve has a tangent line, and a line in $\mathbb{P}^2_k$ is a point of the dual projective space. So a curve determines a second curve, and the numerical relations between the two are the oldest quantitative statements in the subject.

Definition 43.5.1: Dual Space and Dual Curve

The *dual projective space* $(\mathbb{P}^2_k)^\vee$ is the set of lines in $\mathbb{P}^2_k$, itself a $\mathbb{P}^2_k$ by sending $\mathcal{Z}(a_0x_0 + a_1x_1 + a_2x_2)$ to $[a_0 : a_1 : a_2]$. For an irreducible plane curve C, the *dual curve* $C^\vee \subseteq (\mathbb{P}^2_k)^\vee$ is the closure of the set of tangent lines to C at its nonsingular points. The *class* of C is $\deg C^\vee$.

By corollary 43.2.4 the nonsingular points of C are all but finitely many, so $C^\vee$ is the closure of the image of a map defined on a dense open set: the *Gauss map*

$$\gamma\colon C \dashrightarrow (\mathbb{P}^2_k)^\vee \qquad p \mapsto \big[\partial_0 F(p) : \partial_1 F(p) : \partial_2 F(p)\big]$$

whose coordinates are the partials of the defining form, by the tangent-line formula of definition 42.1.6. It is a rational map of curves, so $C^\vee$ is an irreducible curve by lemma 42.2.8 applied to a nonsingular model.

Proposition 43.5.2: The Class of a Nonsingular Curve

Let C be a nonsingular plane curve of degree $d \geq 2$ with $\mathrm{char} k = 0$. Then

$$\deg C^\vee = d(d-1)$$

***Proof*:**

A line of $(\mathbb{P}^2_k)^\vee$ is the set of lines of $\mathbb{P}^2_k$ through a fixed point q, so by theorem 41.5.1 the degree of $C^\vee$ is the number of points in which $C^\vee$ meets such a line for general q, counted through the Gauss map. In characteristic zero that map is birational onto its image for a nonsingular plane curve, so the count of points of $C^\vee$ equals the count of tangent lines to C through q; it is here, and only here, that the characteristic hypothesis is used.

A point $p \in C$ has its tangent line through $q = [q_0 : q_1 : q_2]$ exactly when

$$P_q(p) \;=\; q_0\,\partial_0 F(p) + q_1\,\partial_1 F(p) + q_2\,\partial_2 F(p) \;=\; 0$$

The form P_q has degree $d-1$ and is the *polar* of C with respect to q. It is not the zero form for general q: the partials $\partial_i F$ are not all zero, since $\mathrm{char} k = 0$ and F is nonconstant, and a general linear combination of forms that are not all zero is nonzero. And F does not divide P_q, because $\deg P_q = d - 1 < d$ while F is irreducible. So C and $\mathcal{Z}(P_q)$ have no common component.

Theorem 43.1.1 therefore counts the intersection as $d(d-1)$ with multiplicity. For general q the intersections are transversal, so there are $d(d-1)$ distinct points and as many tangent lines through q, as we sought to show.

Example 43.5.3: Classes of Small Curves
A nonsingular conic has $d = 2$ and class 2: through a general point of the plane there pass exactly two tangent lines to a conic, and the dual of a conic is again a conic.

A nonsingular cubic has $d = 3$ and class 6. That number is the reason the dual of a smooth cubic is a sextic and not a cubic: dualizing does not preserve degree, and $(C^\vee)^\vee = C$ only because the two operations are inverse, not because the degrees match.

Singular points reduce the class, because a singular point has no well-defined tangent and the Gauss map is undefined there. The bookkeeping is Plücker's, and it is stated here rather than proved: the corrections require the genus and the behaviour of δ-invariants under duality.

43.5.4 Note: Plücker's Formulas Let C be an irreducible plane curve of degree d over a field of characteristic zero, with δ ordinary double points and κ ordinary cusps and no other singularities, and let $d^\vee$ be its class. Then

$$d^\vee = d(d-1) - 2\delta - 3\kappa$$

and dually, writing $\delta^\vee$ and $\kappa^\vee$ for the bitangents and inflections of C,

$$d = d^\vee(d^\vee - 1) - 2\delta^\vee - 3\kappa^\vee$$

The genus is common to both and is given by

$$g = \frac{(d-1)(d-2)}{2} - \delta - \kappa$$

consistently with the genus drop recorded in section 44.4, a node and a cusp each costing 1.
For a nonsingular cubic, $\delta = \kappa = 0$ gives $d^\vee = 6$, and the second formula reads $3 = 30 - 2\delta^\vee - 3\kappa^\vee$; with $\delta^\vee = 0$, since a smooth cubic has no bitangent, this gives $\kappa^\vee = 9$. Those nine are the inflection points, recovering by a completely different route the count obtained in exercise set 45.3.1 from the Hessian and theorem 45.2.2.
A proof needs the resolution of chapter 47 together with the genus, and is in [102, chapter 9] and in [56] analytically.

Exercise 43.5.1

1. Let X be an irreducible curve. Show that $k[X] = \bigcap_{p \in X} \mathcal{O}_p(X)$, the intersection being taken inside $k(X)$.
2. Show that a line and an irreducible conic are nonsingular curves, either directly from definition 42.1.5 or from one of the corollaries of section 43.2.
3. Let C and C' be cubics with $C \cdot C' = \sum_{i=1}^{9} p_i$ for nine distinct points, and let Q be a conic with $Q \cdot C = \sum_{i=1}^{6} p_i$. Assuming $p_1, \dots, p_6$ are nonsingular points of C, show that p_7, p_8, p_9 lie on a line. (Run the argument of lemma 43.4.1 with Q in place of the conic there.)
4. Show that the bound of corollary 43.2.5 fails for reducible curves by exhibiting a reducible curve of degree n violating it.

5. Verify that theorem 43.4.3 really is theorem 43.4.2 for a degenerate conic, by checking that the two proofs differ only in the verification that $r_i \notin \mathcal{Z}(Q)$.

6. Two conics meet in at most four points unless they share a component. Deduce that five points in general position determine a unique conic, and say what "general position" has to mean.

44

Divisors on Curves

The intersection cycles of section 43.3 are formal sums of points on a curve, and such sums form a group under addition. Not every formal sum is cut out by an equation, and the failure is measured by quotienting out the sums that arise from rational functions. What remains is the divisor class group, an invariant of the curve alone.

This chapter builds that group. Its degree-zero part is what chapter 45 identifies with the classical chord-tangent law on a cubic, and one book later it becomes the Jacobian. Its structure also detects rationality: a nonsingular plane curve is a copy of $\mathbb{P}^1$ exactly when distinct points on it are linearly equivalent, and that happens only in degrees 1 and 2. The invariant separating the cases is the genus, and the chapter closes by giving the genus-degree formula of section 38.5 that job.

44.1 Divisors and Their Degree

Throughout, C is an irreducible projective curve over the algebraically closed field k, and C is *nonsingular* unless said otherwise. Every local ring $\mathcal{O}_p(C)$ is then a discrete valuation ring by proposition 35.5.2, so every point carries an order function ord_p as in definition 42.2.4.

Section 37.5 already defined Weil divisors on any normal variety. A nonsingular projective curve is normal by corollary 35.5.3, and its prime divisors are its points, every point having codimension one. So the following is definition 37.5.1 specialized, restated here because the curve case is the one the rest of this Part uses.

Definition 44.1.1: Divisor on a Curve

A *divisor* on C is a formal sum

$$D = \sum_{p \in C} n_p \, p \qquad n_p \in \mathbb{Z}$$

with $n_p = 0$ for all but finitely many p. The divisors form an abelian group $\operatorname{Div}(C)$ under coefficientwise addition. The *degree* of D is $\deg D = \sum_p n_p$, and D is *effective*, written $D \geq 0$, if every $n_p \geq 0$. Write $D \geq D'$ for $D - D' \geq 0$.

A divisor is the same kind of object as a zero-cycle (definition 43.3.1), with the points confined to C. The intersection cycle of section 43.3 is the first source of divisors: if C is a nonsingular plane curve and G is a plane curve with no component in common, then $G \cdot C$ is an effective divisor on C, of degree $\deg(G)\deg(C)$ by theorem 43.1.1.

The second source is rational functions, and it is the one that matters.

Definition 44.1.2: Divisor of a Rational Function

Let $f \in k(C)^*$ be a nonzero rational function. Its *divisor* is

$$\operatorname{div}(f) = \sum_{p \in C} \operatorname{ord}_p(f) \, p$$

The divisor of zeros is $\operatorname{div}_0(f) = \sum_{\operatorname{ord}_p(f) > 0} \operatorname{ord}_p(f)\, p$ and the divisor of poles is $\operatorname{div}_\infty(f) = -\sum_{\operatorname{ord}_p(f) < 0} \operatorname{ord}_p(f)\, p$, so that $\operatorname{div}(f) = \operatorname{div}_0(f) - \operatorname{div}_\infty(f)$ with both parts effective.

The definition needs justification: the sum must be finite.

Proposition 44.1.3: A Rational Function Has Finitely Many Zeros and Poles

Let $f \in k(C)^*$. Then $\operatorname{ord}_p(f) = 0$ for all but finitely many $p \in C$, so $\operatorname{div}(f)$ is a divisor.

***Proof*:**
The set where $\operatorname{ord}_p(f) > 0$ is where f vanishes. Writing $f = g/h$ with g, h regular on some affine open $U \subseteq C$ and h not identically zero, the zeros of f in U lie in $\mathcal{Z}(g) \cap U$, a proper closed subset of the irreducible curve C, hence finite by proposition 34.3.5. The same argument applied to $1/f$ handles the poles, and $C \setminus U$ is finite for the same reason. So only finitely many points contribute, as we sought to show.

Example 44.1.4: Divisors on the Projective Line

Take $C = \mathbb{P}^1_k$ with coordinate x on the standard chart and ∞ the point at infinity.

1. *A function with a zero and a pole.* $\operatorname{div}(x) = 0 - \infty$, written $(0) - (\infty)$: the function x vanishes to order 1 at the origin and has a simple pole at infinity, since $1/x$ is a uniformizer there. Its degree is 0, as theorem 44.2.2 requires.

2. *Higher order.* $\operatorname{div}(x^n) = n(0) - n(\infty)$ for $n \in \mathbb{Z}$, negative n interchanging the roles. So every divisor supported on $\{0, \infty\}$ of degree 0 is principal.

3. *A general ratio.* For $f = (x-a)/(x-b)$ with $a \neq b$,

$$\operatorname{div}(f) = (a) - (b)$$

with no contribution at infinity, the numerator and denominator having equal degree. This is the computation behind proposition 44.2.4: every degree-zero divisor on the line is a combination of such differences.

4. *A divisor that is not principal.* The single point (0) has degree $1 \neq 0$, so by theorem 44.2.2 it is not $\operatorname{div}(f)$ for any f. On $\mathbb{P}^1_k$ the degree is the only obstruction, by proposition 44.2.4; on a curve of positive genus it is not, which is what theorem 44.2.5 shows.

The two sources are compatible in the case that matters, and the computation is worth doing once.

Proposition 44.1.5: Divisors from Ratios of Forms

Let $C \subseteq \mathbb{P}^2_k$ be a nonsingular plane curve and let G, H be forms of the same degree e, neither divisible by C. Then G/H defines a rational function on C and

$$\operatorname{div}\left(\frac{G}{H}\right) = G \cdot C - H \cdot C$$

***Proof*:**
The ratio G/H is a quotient of two forms of equal degree, so it is a well defined element of $k(C)$, nonzero because H does not divide G modulo C.

Fix $p \in C$. Property (9) of corollary 42.4.2 says that at a nonsingular point of C the intersection number is an order: $I(p, C \cap G) = \operatorname{ord}_p(G_*)$, where G_* is the dehomogenization of G in a chart containing p, and likewise for H. Choosing the same chart for both, $\operatorname{ord}_p(G_*/H_*) = \operatorname{ord}_p(G_*) - \operatorname{ord}_p(H_*)$ because ord_p is a valuation. The coefficient of p in $G \cdot C - H \cdot C$ is exactly that difference, and the chart cancels because G and H have the same degree, as we sought to show.

44.2 Principal Divisors and Linear Equivalence

Definition 44.2.1: Principal Divisor and Linear Equivalence

This is definition 37.5.3 for a curve. A divisor of the form $\operatorname{div}(f)$ for some $f \in k(C)^*$ is *principal*. The principal divisors form a subgroup $\operatorname{Prin}(C) \subseteq \operatorname{Div}(C)$, since $\operatorname{div}(fg) = \operatorname{div}(f) + \operatorname{div}(g)$. Two divisors D and D' are *linearly equivalent*, written $D \sim D'$, if $D - D'$ is principal.

The first structural fact is that the degree cannot see the difference between linearly equivalent divisors.

Theorem 44.2.2: Principal Divisors Have Degree Zero

Let C be a nonsingular projective plane curve and $f \in k(C)^*$. Then $\deg \operatorname{div}(f) = 0$. Consequently $D \sim D'$ implies $\deg D = \deg D'$.

***Proof*:**
Write $f = G/H$ with G, H forms of the same degree e, neither divisible by C; this is possible because $k(C)$ consists of exactly such ratios. By proposition 44.1.5, $\operatorname{div}(f) = G \cdot C - H \cdot C$. Both intersection cycles have degree $e \deg(C)$ by theorem 43.1.1, so the difference has degree 0. The consequence is immediate from additivity of the degree, completing the proof.

That Bézout's theorem is what makes this work is worth pausing on. The statement $\deg \operatorname{div}(f) = 0$ says a rational function on a projective curve has as many zeros as poles, and its analytic counterpart is the argument principle. Projectivity is essential: on $\mathbb{A}^1_k$ the function x has one zero and no poles.

The converse question is when a degree-zero divisor is principal, and the first thing to settle is which functions have no divisor at all.

Proposition 44.2.3: Functions with Trivial Divisor

Let C be a nonsingular projective curve and $f \in k(C)^*$ with $\operatorname{div}(f) = 0$. Then f is constant.

***Proof*:**
If $\operatorname{div}(f) = 0$ then $\operatorname{ord}_p(f) \geq 0$ at every p, so f lies in every local ring $\mathcal{O}_p(C)$ and is therefore a regular function on all of C. A regular function on a projective variety is constant by corollary 40.2.4, completing the proof.

On the simplest curve the converse of theorem 44.2.2 holds outright, and the computation is the model for everything later.

Proposition 44.2.4: Divisors on the Projective Line

Every divisor of degree 0 on $\mathbb{P}^1_k$ is principal. In particular any two points of $\mathbb{P}^1_k$ are linearly equivalent.

***Proof*:**
Let $D = \sum_i n_i p_i$ have degree 0, and write $p_i = [a_i : b_i]$ with $L_i = b_i x - a_i y$ the linear form vanishing exactly at p_i. Fix an index j with p_j distinct from the others. For $i \neq j$ the ratio L_i/L_j is a rational function on $\mathbb{P}^1_k$, and in the affine chart containing p_i the form L_i generates the maximal ideal at p_i while L_j is a unit there, so $\operatorname{ord}_{p_i}(L_i/L_j) = 1$; symmetrically $\operatorname{ord}_{p_j}(L_i/L_j) = -1$, and the order is 0 elsewhere. Hence $\operatorname{div}(L_i/L_j) = p_i - p_j$. Set

$$f = \prod_i \left(\frac{L_i}{L_j}\right)^{n_i}$$

a legitimate rational function since the exponents are integers. Then $\operatorname{div}(f) = \sum_i n_i(p_i - p_j) = D - (\deg D)\, p_j = D$, as we sought to show.

For curves of higher degree the answer is different, and the difference is the whole subject. The following theorem is the engine: on a plane curve of degree at least three, distinct points are never linearly equivalent. Its proof is a single application of Max Noether's theorem.

Theorem 44.2.5: Distinct Points Are Not Equivalent

Let C be a nonsingular projective plane curve of degree $d \geq 3$, and let $p, q \in C$ satisfy $p \sim q$. Then $p = q$.

***Proof*:**
Suppose $\operatorname{div}(f) = p - q$ and write $f = G/H$ with G, H forms of the same degree e, neither divisible by C. By proposition 44.1.5 this reads $G \cdot C - H \cdot C = p - q$, that is

$$G \cdot C + q = H \cdot C + p$$

an equality of effective divisors.

Choose a line L through p and write $L \cdot C = p + E$, so $E \geq 0$ has degree $d - 1 \geq 2$ by theorem 43.1.1. Then

$$(LH) \cdot C = L \cdot C + H \cdot C = p + E + H \cdot C = E + q + G \cdot C \;\geq\; G \cdot C$$

Every point of C is nonsingular, so corollary 43.3.4(2) applies to the curve C, the curve G and the curve LH, and produces a curve of degree $\deg(LH) - \deg(G) = (e+1) - e = 1$, that is a line L', with

$$L' \cdot C = (LH) \cdot C - G \cdot C = E + q$$

So L and L' both cut E out of C, one with p left over and the other with q. Now E is effective of degree $d - 1 \geq 2$, and there are two cases. If its support contains two distinct points, then L and L' share those two points and hence coincide. Otherwise $E = (d-1)r$ for a single point r, and since $d - 1 \geq 2$ both lines meet C at r with multiplicity at least 2, making each of them the tangent line to C at r, which is unique by definition 42.1.6; again they coincide.

With $L = L'$, comparing $L \cdot C = p + E$ against $L' \cdot C = q + E$ gives $p = q$, as we sought to show.

The hypothesis $d \geq 3$ is not an artefact. For $d = 1$ the curve is a line and proposition 44.2.4 says all its points are equivalent; for $d = 2$ the leftover divisor E has degree 1, a single point, which does not determine a line, and indeed a nonsingular conic is isomorphic to $\mathbb{P}^1_k$ by the computation in example 39.4.4. The theorem is the first place where a plane curve of degree three behaves differently from every curve seen so far.

44.3 The Picard Group

Definition 44.3.1: Picard Group

The *Picard group* of a nonsingular projective curve C, which is its class group $\mathrm{Cl}(C)$ in the sense of definition 37.5.3, is

$$\mathrm{Pic}(C) = \frac{\mathrm{Div}(C)}{\mathrm{Prin}(C)}$$

The class of a divisor D is written $[D]$. The subgroup of classes of degree zero is written $\mathrm{Pic}^0(C)$.

By theorem 44.2.2 the degree descends to a homomorphism $\deg\colon \mathrm{Pic}(C) \to \mathbb{Z}$, and it is surjective for a plane curve, since a hyperplane section has degree $d \neq 0$ and any class of degree n can be built from points. Its kernel is $\mathrm{Pic}^0(C)$, so there is a short exact sequence

$$0 \to \mathrm{Pic}^0(C) \to \mathrm{Pic}(C) \xrightarrow{\deg} \mathbb{Z} \to 0$$

All the geometry is in Pic^0.

Example 44.3.2: The Picard Group of the Line

For $C = \mathbb{P}^1_k$, proposition 44.2.4 says every degree-zero divisor is principal, so $\mathrm{Pic}^0(\mathbb{P}^1_k) = 0$ and the degree map is an isomorphism $\mathrm{Pic}(\mathbb{P}^1_k) \cong \mathbb{Z}$. The Picard group is as small as it can be, and this is exactly the statement that no formal sum of points on the line carries information beyond how many points it has.

The contrast with a curve of higher degree is total. On a nonsingular plane cubic, Pic^0 turns out to be in bijection with the points of the curve itself, and the bijection carries the chord-tangent operation of section 45.1 to addition of divisor classes. That is section 45.2, and the one general fact it needs is recorded here.

Lemma 44.3.3: Hyperplane Sections Are All Equivalent

Let C be a nonsingular plane curve and L, M lines, neither a component of C. Then $L \cdot C \sim M \cdot C$.

***Proof*:**

The ratio L/M is a quotient of forms of degree 1, so proposition 44.1.5 gives $\mathrm{div}(L/M) = L \cdot C - M \cdot C$, which is therefore principal, completing the proof.

More generally the same argument shows $G \cdot C \sim G' \cdot C$ for any two curves G, G' of equal degree meeting C properly, so the class of a plane section depends only on the degree. This is the statement that a plane curve carries a distinguished element of $\mathrm{Pic}(C)$ in each degree, and everything computed below is measured against it.

44.4 The Genus of a Plane Curve

Section 38.5 computed the arithmetic genus of a nonsingular plane curve of degree d from its Hilbert polynomial and found

$$p_a = \frac{(d-1)(d-2)}{2}$$

That computation was about the embedding. This section gives the number a job.

Definition 44.4.1: Genus of a Nonsingular Plane Curve

The *genus* of a nonsingular projective plane curve C of degree d is

$$g(C) = \frac{(d-1)(d-2)}{2}$$

which is its arithmetic genus in the sense of definition 38.5.3.

So a line and a conic have genus 0, a cubic has genus 1, a quartic genus 3, and no plane curve has genus 2: the sequence $0, 0, 1, 3, 6, 10, \ldots$ skips it. Curves of genus 2 exist, but none of them embeds in $\mathbb{P}^2_k$ as a nonsingular curve.

The genus was introduced as a number attached to an embedding, and the following theorem is the first evidence that it is measuring the curve itself.

Theorem 44.4.2: Genus Zero Means Rational

Let C be a nonsingular projective plane curve of degree d. The following are equivalent:

1. $g(C) = 0$;
2. $d \leq 2$;
3. $C \cong \mathbb{P}^1_k$;
4. some two distinct points of C are linearly equivalent.

***Proof*:**
(1) $\Leftrightarrow$ (2) is arithmetic: $(d-1)(d-2)/2 = 0$ exactly when $d = 1$ or $d = 2$.

(2) $\Rightarrow$ (3): a line is $\mathbb{P}^1_k$. For a nonsingular conic C, fix $p \in C$ and project from p onto any line not through it. A line through p meets C in one further point by theorem 43.1.1, the tangent at p being the case where that point is p itself, so the projection is a bijection $C \to \mathbb{P}^1_k$; it is regular away from p, and regular at p by lemma 42.2.8, with a regular inverse for the same reason. Example 39.4.4(3) carries the computation out explicitly for $\mathcal{Z}(x^2 + y^2 - z^2)$.

(3) $\Rightarrow$ (4): an isomorphism carries rational functions to rational functions and preserves orders, hence carries principal divisors to principal divisors and linear equivalence to linear equivalence. Any two points of $\mathbb{P}^1_k$ are linearly equivalent by proposition 44.2.4, and a curve has more than one point, so the same holds on C.

(4) $\Rightarrow$ (2): this is theorem 44.2.5 in contrapositive form, which says $d \geq 3$ forces distinct points to be inequivalent, completing the proof.

Corollary 44.4.3: Nonsingular Plane Cubics Are Not Rational

A nonsingular projective plane cubic has genus 1 and is not isomorphic to $\mathbb{P}^1_k$. In particular it is not a rational curve.

***Proof*:**
Its genus is $(3-1)(3-2)/2 = 1 \neq 0$, so theorem 44.4.2 rules out $C \cong \mathbb{P}^1_k$. A rational curve is birational to $\mathbb{P}^1_k$, and a birational map between nonsingular projective curves is an isomorphism by lemma 42.2.8 applied in both directions, completing the proof.

This settles a claim made in passing in chapter 33, that the classification of elliptic curves up to birational equivalence needs the genus: the cubics are exactly the plane curves the genus first distinguishes from $\mathbb{P}^1_k$, and theorem 45.2.2 says what replaces the vanishing Picard group when it does.

Singular curves are handled by passing to a nonsingular model, which is what chapter 37 was built for, and the genus drops in a way controlled by the singularities.

44.4.4 Note: The Genus of a Singular Plane Curve Let C be an irreducible plane curve of degree d whose singular points are all *ordinary*, meaning m_p distinct tangent lines at a point of multiplicity m_p (definition 42.1.6), and let $\tilde{C}$ be its normalization (chapter 37), a nonsingular curve birational to C. Then

$$g(\tilde{C}) = \frac{(d-1)(d-2)}{2} - \sum_{p} \frac{m_p(m_p-1)}{2}$$

each singular point costing exactly $\binom{m_p}{2}$. The formula is proved in theorem 47.4.1, by counting adjoint curves of degree $d-3$ rather than by any computation on a blow-up.
That the right side is non-negative is corollary 43.2.5, proved in chapter 43 by a dimension count on curves of degree $d-1$, which now reads as the statement that a genus cannot be negative. The extremal curve $\mathcal{Z}(x^d + y^{d-1}z)$ of section 43.2 attains the bound and is rational, as section 47.4 exhibits explicitly.

Exercise 44.4.1

1. Show that $\operatorname{div}(fg) = \operatorname{div}(f) + \operatorname{div}(g)$ and $\operatorname{div}(1/f) = -\operatorname{div}(f)$, so that $\operatorname{Prin}(C)$ is a subgroup of $\operatorname{Div}(C)$ and $f \mapsto \operatorname{div}(f)$ is a homomorphism $k(C)^* \to \operatorname{Div}(C)$.
2. Deduce from proposition 44.2.3 that the kernel of that homomorphism is k^*, so that $\operatorname{Prin}(C) \cong k(C)^*/k^*$.
3. Let C be a nonsingular plane curve of degree d and H a line. Show that the class $[H \cdot C]$ generates the image of deg in $\mathbb{Z}$ if and only if $d = 1$, and describe the image in general.
4. Show that on a nonsingular plane cubic C with base point O, a point p satisfies $p \oplus p \oplus p = \varphi(O, O)$ if and only if p is an inflection point. Deduce, using theorem 45.2.2, that the inflection points form a subgroup of $E_k(C, O)$ when O is itself an inflection point.

5. Show that a divisor D on a nonsingular projective curve satisfies $D \sim 0$ and $D \geq 0$ only if $D = 0$.

6. Give an example of two divisors on a nonsingular plane cubic that have the same degree but are not linearly equivalent, and prove they are not.

45

The Group Law on Cubic Curves

A line meets a nonsingular cubic in three points, and that fact alone produces a group. The construction is elementary, its verification is not: associativity is a statement about the nine intersection points of two cubics, and the proof runs through Max Noether's theorem.

The chapter then explains where the group came from. Under the divisor theory of chapter 44 the chord-tangent law is addition in $\mathrm{Pic}^0(C)$, transported to the curve by $p \mapsto [p - O]$, and the hard-won associativity becomes the associativity of a quotient group. That description also settles the one loose end of the construction: it needed a base point, and nothing distinguishes one choice from another, but the target $\mathrm{Pic}^0(C)$ mentions no base point at all. The group obtained is the object that *Elliptic Curves* [25] takes as its subject.

45.1 The Chord-Tangent Construction

Let C be a nonsingular projective plane cubic. It is irreducible: were $C = C_1C_2$ a proper factorization, theorem 43.1.1 would give $\mathcal{Z}(C_1)$ and $\mathcal{Z}(C_2)$ a common point, and proposition 42.1.7 makes any such point singular on C. So no line is a component of C, and theorem 43.1.1 says every line meets it in exactly three points counted with multiplicity. Given $p, q \in \mathcal{Z}(C)$, not necessarily distinct, let L be the line through them, taken to be the tangent line at p when $p = q$. Then

$$L \cdot C = p + q + r$$

for a unique third point r, again with multiplicity. This defines a map

$$\varphi\colon \mathcal{Z}(C) \times \mathcal{Z}(C) \to \mathcal{Z}(C) \qquad \varphi(p, q) = r$$

which is visibly symmetric, and which satisfies $\varphi(p, \varphi(p, q)) = q$, since the line realizing the left side is the same L.

Figure 45.1 shows the two cases.




Figure 45.1: The chord through p and q meets the cubic in a third point. When $p = q$ the chord is replaced by the tangent line at p.

The map φ is a symmetric binary operation, but it is not a group law: there is no identity, since $\varphi(p, q) = q$ would force p to lie on the tangent at q for every q. The repair is to compose with φ once more against a chosen base point. Fix any $O \in \mathcal{Z}(C)$ and define

$$p \oplus q = \varphi\big(O, \varphi(p, q)\big)$$

Lemma 45.1.1: The Base Point Is an Identity

For every $p \in \mathcal{Z}(C)$, $O \oplus p = p \oplus O = p$.

***Proof*:**
Symmetry of φ gives $O \oplus p = p \oplus O$, so it is enough to compute one. Setting $q = \varphi(O, p)$, the involution property gives

$$O \oplus p = \varphi\big(O, \varphi(O, p)\big) = \varphi(O, q) = p$$

as we sought to show.

Before the group law can be proved, one point needs care. The natural guess for the inverse of p is $\varphi(p, O)$, and the natural guess for collinearity is that three collinear points sum to O. Both are false for a general base point, and the reason is that $\varphi(O, O)$, the third point on the tangent at O, need not be O itself. A point p with $\varphi(p, p) = p$ is one where the tangent line meets C triply, that is an *inflection point*, and a nonsingular cubic has only finitely many of them.

Lemma 45.1.2: Collinearity and the Sum

Let $p, q, r \in \mathcal{Z}(C)$. Then p, q, r are collinear, in the sense that $L \cdot C = p + q + r$ for some line L, if and only if

$$p \oplus q \oplus r = \varphi(O, O)$$

In particular, if the base point O is an inflection point then $\varphi(O, O) = O$ and three collinear points sum to the identity.

***Proof*:**
Suppose p, q, r are collinear, so $r = \varphi(p, q)$. Then $p \oplus q = \varphi(O, r)$, and

$$(p \oplus q) \oplus r = \varphi\Big(O, \varphi\big(\varphi(O, r),\, r\big)\Big)$$

The points O, r and $\varphi(O, r)$ are collinear by definition of φ, so $\varphi(\varphi(O, r), r) = O$, and the right side is $\varphi(O, O)$.

Conversely, suppose $p \oplus q \oplus r = \varphi(O, O)$, and let $r' = \varphi(p, q)$, so that p, q, r' are collinear. By the first part $p \oplus q \oplus r' = \varphi(O, O)$ as well, so r and r' have the same image under the map $x \mapsto (p \oplus q) \oplus x$. That map is injective once $\oplus$ is known to be a group law. Proposition 45.1.4 establishes this using only the involution property of φ and lemma 45.1.3, never the present converse, so there is no circularity. Hence $r = r'$ and p, q, r are collinear, as we sought to show.

The associativity of $\oplus$ is the hard point, and it rests on the following consequence of Max Noether's theorem: two cubics that agree with C in eight of their nine intersection points agree in the ninth as well.

Lemma 45.1.3: Cubic Point Counting

Let C be an irreducible cubic and C', C'' cubics with no component in common with C. Suppose

$$C' \cdot C = \sum_{i=1}^{9} p_i \qquad C'' \cdot C = \sum_{i=1}^{8} p_i + q$$

where the p_i are nonsingular points of C, not necessarily distinct. Then $q = p_9$.

***Proof*:**
Suppose $q \neq p_9$ and choose a line L through p_9 not passing through q, possible because the lines through p_9 sweep out the plane and only one of them contains q. Write $L \cdot C = p_9 + r + s$.

The quartic LC'' satisfies

$$(LC'') \cdot C = L \cdot C + C'' \cdot C = \sum_{i=1}^{9} p_i + q + r + s \;\geq\; C' \cdot C$$

Every point of $\mathcal{Z}(C') \cap \mathcal{Z}(C)$ is a nonsingular point of C by hypothesis, so corollary 43.3.4(2) applies to the triple (C, C', LC'') and produces a curve of degree $\deg(LC'') - \deg(C') = 4 - 3 = 1$, that is a line L', with

$$L' \cdot C = (LC'') \cdot C - C' \cdot C = q + r + s$$

Now L and L' coincide. If $r \neq s$, both contain the two distinct points r and s, and two distinct points determine a line. If $r = s$, then $L \cdot C \geq 2r$ and $L' \cdot C \geq 2r$, so both are tangent to C at the nonsingular point r, and the tangent line there is unique by definition 42.1.6.

But $L' = L$ forces q to lie on L, contradicting the choice of L. Hence $q = p_9$, as we sought to show.

Proposition 45.1.4: Group Law For Cubics

Let C be a nonsingular projective plane cubic and $O \in \mathcal{Z}(C)$ a base point. Then $\mathcal{Z}(C)$ with the operation $\oplus$ is an abelian group with identity O, in which the inverse of p is

$$\ominus p = \varphi\big(p, \varphi(O, O)\big)$$

Write $E_k(C, O)$ for this group.

***Proof*:**
Commutativity is the symmetry of φ, and O is an identity by lemma 45.1.1.

Inverses. Let $t = \varphi(O, O)$ and $\ominus p = \varphi(p, t)$. Only the involution property is needed: by definition of $\oplus$,

$$p \oplus \ominus p = \varphi\big(O, \varphi(p, \ominus p)\big) = \varphi\big(O, \varphi(p, \varphi(p, t))\big) = \varphi(O, t) = \varphi\big(O, \varphi(O, O)\big) = O$$

the third equality applying $\varphi(p, \varphi(p, -)) = \mathrm{id}$ and the last applying $\varphi(O, \varphi(O, -)) = \mathrm{id}$.

Associativity. Let $p, q, r \in \mathcal{Z}(C)$ and introduce six lines by

$$\begin{array}{lll} L_1 \cdot C = p + q + s' & M_1 \cdot C = O + s' + s & L_2 \cdot C = s + r + t' \\ M_2 \cdot C = q + r + u' & L_3 \cdot C = O + u' + u & M_3 \cdot C = p + u + t'' \end{array}$$

so that $s = \varphi(O, s') = p \oplus q$ and $u = \varphi(O, u') = q \oplus r$. Then

$$(p \oplus q) \oplus r = \varphi(O, \varphi(s, r)) = \varphi(O, t') \qquad p \oplus (q \oplus r) = \varphi(O, \varphi(p, u)) = \varphi(O, t'')$$

so it suffices to prove $t' = t''$. Put $C' = L_1 L_2 L_3$ and $C'' = M_1 M_2 M_3$, both cubics with no component in common with the irreducible C, since a line meets C in three points and so is not a component. Adding the three displayed cycles in each row,

$$C' \cdot C = p + q + s' + s + r + t' + O + u' + u \qquad C'' \cdot C = O + s' + s + q + r + u' + p + u + t''$$

The two agree in the eight points O, p, q, r, s, s', u, u', and every point of $\mathcal{Z}(C)$ is nonsingular, so lemma 45.1.3 gives $t' = t''$.

Thus $\oplus$ is an abelian group law, completing the proof.

The group depends on the base point only up to isomorphism, and the isomorphism is explicit. Given a second base point O', set $Q = \varphi(O, O')$ and

$$\alpha \colon E_k(C, O) \to E_k(C, O') \qquad \alpha(p) = \varphi(Q, p)$$

This sends O to O', since the line through Q and O is the line through O, O' and Q. That α is a

group isomorphism is proved in section 45.3, once section 45.2 has identified $E_k(C,O)$ with a group of divisor classes and made the computation one line rather than a chain of collinearity arguments.

45.2 The Group Law via the Picard Group

The chord-tangent law was constructed by hand, and its associativity cost a nine-point argument through Max Noether. This section explains where the group comes from: it is $\mathrm{Pic}^0(C)$, transported to the curve.

Throughout, C is a nonsingular projective plane cubic with base point O, and φ, $\oplus$ are as in section 45.1. The bridge is a single linear equivalence.

Proposition 45.2.1: The Chord-Tangent Law Is Addition of Classes

For all $p, q \in C$,

$$p + q \;\sim\; (p \oplus q) + O$$

Consequently the map

$$\theta\colon E_k(C,O) \to \mathrm{Pic}^0(C) \qquad \theta(p) = [\,p - O\,]$$

is a group homomorphism.

***Proof*:**
Let $r = \varphi(p,q)$ and $s = \varphi(O,r) = p \oplus q$, and let L and M be the lines realizing them, so that

$$L \cdot C = p + q + r \qquad M \cdot C = O + r + s$$

By lemma 44.3.3 these are linearly equivalent, and subtracting the common r gives $p+q \sim O+s$, which is the display.

For the consequence, θ lands in Pic^0 because $\deg(p - O) = 0$, and

$$\theta(p) + \theta(q) = [\,p + q - 2O\,] = [\,(p \oplus q) + O - 2O\,] = [\,(p \oplus q) - O\,] = \theta(p \oplus q)$$

using the display in the middle step, as we sought to show.

Theorem 45.2.2: The Group Law Is the Picard Group

Let C be a nonsingular projective plane cubic with base point O. Then

$$\theta\colon E_k(C,O) \longrightarrow \mathrm{Pic}^0(C) \qquad \theta(p) = [\,p - O\,]$$

is an isomorphism of abelian groups.

***Proof*:**
It is a homomorphism by proposition 45.2.1.

Injective. If $\theta(p) = \theta(q)$ then $p - O \sim q - O$, so $p \sim q$, and theorem 44.2.5 gives $p = q$, the cubic having degree 3.

Surjective. Let D have degree 0 and write $D = \sum_{i=1}^{n} p_i - \sum_{j=1}^{n} q_j$, the two counts being equal because $\deg D = 0$; points may repeat, and $n = 0$ gives $D = 0 = \theta(O)$. First,

$$\sum_{i=1}^{n} p_i \;\sim\; (p_1 \oplus \cdots \oplus p_n) + (n-1)O$$

by induction on n. The case $n = 1$ is trivial. Given the statement for n, add p_{n+1} to both sides and apply proposition 45.2.1 to the pair $(p_1 \oplus \cdots \oplus p_n,\ p_{n+1})$, which replaces their sum by $(p_1 \oplus \cdots \oplus p_{n+1}) + O$; that is the statement for $n + 1$.

Writing $P = p_1 \oplus \cdots \oplus p_n$ and $Q = q_1 \oplus \cdots \oplus q_n$ and subtracting the two instances, the $(n-1)O$ terms cancel and $D \sim P - Q$. Finally

$$[P - Q] = [P - O] - [Q - O] = \theta(P) - \theta(Q) = \theta(P \ominus Q)$$

so D lies in the image, as we sought to show.

Associativity of $\oplus$, which proposition 45.1.4 obtained from lemma 45.1.3 and so ultimately from Max Noether's theorem, is now visible as the associativity of addition in a quotient group. The two proofs are not independent: theorem 44.2.5 itself runs through Max Noether. What changes is the source of the difficulty. In section 45.1 it is a configuration of six lines. Here it is the statement that a rational function on a cubic cannot have a single simple pole.

45.2.3 Note: Which Facts Are Doing the Work Two theorems carry theorem 45.2.2, and they pull in opposite directions. Lemma 44.3.3 says linear equivalence is coarse enough that all line sections agree, which is what makes θ additive. Theorem 44.2.5 says it is fine enough that points stay apart, which is what makes θ injective. On a conic the second fails and Pic^0 collapses to zero; on a line there is nothing to say at all. Degree three is the smallest case where both hold, which is the precise sense in which the group law is a phenomenon of cubics.

45.3 Independence of the Base Point

The construction of $\oplus$ required choosing O, and nothing recommends one point over another. Theorem 45.2.2 settles the matter at once, because its target does not mention O.

Theorem 45.3.1: Independence of the Base Point

Let C be a nonsingular projective plane cubic and $O, O' \in C$. Then

$$E_k(C, O) \;\cong\; E_k(C, O')$$

both being isomorphic to $\mathrm{Pic}^{\,0}(C)$, which is defined without reference to a base point.

***Proof*:**
Write θ_O and $\theta_{O'}$ for the two maps of theorem 45.2.2, each an isomorphism onto $\mathrm{Pic}^{\,0}(C)$. Then $\theta_{O'}^{-1} \circ \theta_O$ is an isomorphism $E_k(C, O) \to E_k(C, O')$, completing the proof.

The explicit map promised in section 45.1 is almost that one, differing by an inversion.

Proposition 45.3.2: The Explicit Isomorphism

Let $Q = \varphi(O, O')$ and $\alpha(p) = \varphi(Q, p)$. Then $\alpha \colon E_k(C, O) \to E_k(C, O')$ is a group isomorphism, and

$$\theta_{O'}\big(\alpha(p)\big) = -\,\theta_O(p)$$

***Proof*:**
The points Q, p and $\alpha(p)$ are collinear by definition of φ, and so are O, O' and Q. By lemma 44.3.3 the two line sections are linearly equivalent:

$$Q + p + \alpha(p) \;\sim\; O + O' + Q$$

Cancelling Q and rearranging gives $\alpha(p) - O' \sim O - p$, that is

$$\theta_{O'}\big(\alpha(p)\big) = [\,\alpha(p) - O'\,] = [\,O - p\,] = -[\,p - O\,] = -\theta_O(p)$$

So $\alpha = \theta_{O'}^{-1} \circ (-\mathrm{id}) \circ \theta_O$. Inversion is an automorphism of an abelian group, and θ_O, $\theta_{O'}$ are isomorphisms, so α is one too, as we sought to show.

That the natural explicit map inverts is not a defect of the choice; no map defined by a single application of φ can avoid it, since φ itself reverses the sign. Composing twice, $p \mapsto \varphi(O', \varphi(Q, p))$ is the base-point-free isomorphism $\theta_{O'}^{-1}\theta_O$ on the nose.

45.3.3 Note: What the Group Does and Does Not Depend On The *group* $E_k(C, O)$ depends on O only up to isomorphism, and the isomorphism class is that of $\mathrm{Pic}^{\,0}(C)$. What does depend on O is the identification of points of C with group elements: which point is the identity, and hence which triples sum to zero. Choosing O to be an inflection point makes lemma 45.1.2 read in its familiar form, three collinear points summing to the identity, and this is why the literature almost always makes that choice for a curve given in Weierstrass form, where the point at infinity is an inflection.

Exercise 45.3.1

1. Show that a nonsingular *projective* plane curve must be irreducible, and give a nonsingular *affine* plane curve that is not.
2. Let C be a nonsingular plane cubic with base point O. Show that $\varphi(O, O) = O$ if and only if O is an inflection point, and that in that case the inverse of proposition 45.1.4 takes the familiar form $\ominus p = \varphi(p, O)$.
3. With O an inflection point, show that the inflection points of C are exactly the elements of order dividing 3 in $E_k(C, O)$, and bound their number using theorem 43.1.1 and the Hessian.
4. Show that a nonsingular plane cubic has no point p with $\varphi(p, p) = p$ other than its inflection points.
5. Let C be a nonsingular plane cubic and $p, q \in C$ with $p \sim q$ as divisors. Show $p = q$, and explain precisely which step of the argument fails on a nonsingular conic.
6. Compare the labour of verifying associativity of $\oplus$ directly on $y^2 = x^3 + 1$ with $O = [0 : 1 : 0]$, for three points of your choosing, against the one-line argument of theorem 45.2.2.

46

Differential Forms and the Canonical Class

Every invariant of a curve met so far has been extrinsic: the degree depends on an embedding, the multiplicity on a choice of coordinates, the divisor class group on nothing at all but says little by itself. This chapter constructs the invariant that governs the rest, the canonical class, and it does so from the one piece of machinery not yet used, differentiation.

Derivations, the module $\Omega_{B/A}$ and its universal property, and the two fundamental exact sequences are commutative algebra, developed in section 21.3; this chapter takes them as given and does the geometry. What comes out is a divisor class attached to a curve with no choices at all, whose degree is $2g-2$, and which chapter 48$\star$ shows to be the error term in Riemann's inequality.

46.1 Differential Forms on a Variety

Definition 46.1.1: Differentials on a Variety

Let X be an affine variety over k. The *module of differentials* of X is $\Omega_X = \Omega_{k[X]/k}$, the module of relative differential forms of definition 21.3.2, together with the universal k-derivation $d\colon k[X] \to \Omega_X$. Its elements are the *differential forms* on X.
For $p \in X$ the *forms at* p are $\Omega_{X,p} = \Omega_X \otimes_{k[X]} \mathcal{O}_p(X)$, and for an irreducible X the *rational differential forms* are $\Omega_{k(X)/k}$, a vector space over $k(X)$.

Example 46.1.2: Modules of Differentials

1. *Affine space.* $\Omega_{\mathbb{A}^n_k}$ is free of rank n over $k[x_1, \dots, x_n]$ with basis $dx_1, \dots, dx_n$, since a k-derivation is determined by arbitrary choices of the dx_i. This is the first exercise of exercise set 46.2.1.
2. *A nonsingular plane curve.* On $C = \mathcal{Z}(y - x^2)$ the relation $dy = 2x\,dx$ holds, so Ω_C is generated by dx alone and is free of rank $1 = \dim C$, as proposition 46.1.3 predicts.
3. *The cuspidal cubic.* On $C = \mathcal{Z}(y^2 - x^3)$ the relation is $2y\,dy = 3x^2\,dx$. At the origin both coefficients vanish, so the relation imposes nothing there and $\Omega_{C,0} \otimes k$ has dimension 2, while $\dim C = 1$. By proposition 46.1.3 the origin is singular, which is the fifth exercise of exercise set 46.2.1. Away from the origin the relation is nontrivial and Ω is free of rank 1.
4. *A form with a pole.* On $\mathbb{P}^1_k$ the form dx has $\operatorname{div}(dx) = -2(\infty)$, computed in the second exercise of exercise set 46.2.1. Its degree -2 is $2g - 2$ with $g = 0$, which is theorem 46.2.4 in the smallest case.

Two facts do all the work, and both are transported from the algebra.

Proposition 46.1.3: Differentials Detect Smoothness

Let X be a variety of dimension n and $p \in X$. Then

$$\dim_k \Omega_{X,p} \otimes_{\mathcal{O}_p(X)} k \;=\; \dim_k \mathfrak{m}_p/\mathfrak{m}_p^2$$

so p is a nonsingular point if and only if that dimension is n. If X is nonsingular then $\Omega_{X,p}$ is a free $\mathcal{O}_p(X)$-module of rank n.

***Proof*:**
Apply the second fundamental exact sequence (proposition 21.3.7) to $k[X] \to \mathcal{O}_p(X) \to k$ with $I = \mathfrak{m}_p$. Since $\Omega_{k/k} = 0$, it reads

$$\mathfrak{m}_p/\mathfrak{m}_p^2 \xrightarrow{\delta} \Omega_{X,p} \otimes k \to 0$$

and δ is injective because a k-linear functional on $\mathfrak{m}_p/\mathfrak{m}_p^2$ extends to a k-derivation of $\mathcal{O}_p(X)$, by sending f to the class of $f - f(p)$; so δ has a left inverse. That gives the displayed equality, and corollary 35.1.1 identifies the right side with n exactly at the nonsingular points.

For freeness, $\Omega_{X,p}$ is a finitely generated module over the Noetherian local ring $\mathcal{O}_p(X)$ by corollary 21.3.8, whose fibre has dimension n; a finitely generated module over a regular local ring whose fibre dimension equals the generic rank is free, which is lemma 21.3.12, completing the proof.

Corollary 46.1.4: Rational Differentials on a Curve

Let C be a nonsingular projective curve. Then $\Omega_{k(C)/k}$ is a one-dimensional vector space over $k(C)$. If t is a uniformizer at a point p, then dt is a basis, and every rational differential form is $f\,dt$ for a unique $f \in k(C)$.

***Proof*:**
By proposition 46.1.3 the module $\Omega_{C,p}$ is free of rank 1 over $\mathcal{O}_p(C)$, so tensoring up to the fraction field gives $\dim_{k(C)} \Omega_{k(C)/k} = 1$.

For the basis, $\mathcal{O}_p(C)$ is a discrete valuation ring with uniformizer t and $\mathfrak{m}_p/\mathfrak{m}_p^2$ is spanned by the class of t, so dt generates $\Omega_{C,p} \otimes k$ under the isomorphism of proposition 46.1.3. Nakayama's lemma then makes dt a generator of the free rank-one module $\Omega_{C,p}$, hence a basis after tensoring with $k(C)$, completing the proof.

46.2 The Canonical Class

A nonzero rational differential form on a curve has zeros and poles, exactly as a rational function does, and they assemble into a divisor. The point of the section is that the divisor class does not depend on the form.

Definition 46.2.1: The Divisor of a Differential Form

Let C be a nonsingular projective curve and $\omega \in \Omega_{k(C)/k}$ nonzero. For $p \in C$ with uniformizer t, write $\omega = f\,dt$ with $f \in k(C)$ as in corollary 46.1.4, and set $\operatorname{ord}_p(\omega) = \operatorname{ord}_p(f)$. The *divisor* of ω is

$$\operatorname{div}(\omega) = \sum_{p \in C} \operatorname{ord}_p(\omega)\, p$$

Proposition 46.2.2: The Divisor of a Form Is Well Defined

$\operatorname{ord}_p(\omega)$ does not depend on the choice of uniformizer, and $\operatorname{ord}_p(\omega) = 0$ for all but finitely many p, so $\operatorname{div}(\omega)$ is a divisor.

***Proof*:**
Let s be another uniformizer at p, so $s = ut$ with u a unit of $\mathcal{O}_p(C)$. Then $ds = u\,dt + t\,du$, and writing $du = u'\,dt$ with $u' \in \mathcal{O}_p(C)$ gives $ds = (u + tu')\,dt$. The coefficient $u + tu'$ is a unit, being u modulo $\mathfrak{m}_p$, so $\omega = f\,dt = f(u + tu')^{-1} ds$ and the order of the coefficient is unchanged.

For finiteness, cover C by finitely many affine opens; on each, $\omega = f\,dg$ for some $f, g \in k[U]$, and $\operatorname{ord}_p(\omega) \neq 0$ only where f or dg degenerates, a proper closed subset, hence finite by proposition 34.3.5, completing the proof.

Theorem 46.2.3: The Canonical Class

Let C be a nonsingular projective curve. Any two nonzero rational differential forms on C have linearly equivalent divisors, so their common class

$$K_C = [\operatorname{div}(\omega)] \ \in \ \operatorname{Pic}(C)$$

is an invariant of C, the *canonical class*. A divisor in that class is a *canonical divisor*.

***Proof*:**
Let ω, ω' be nonzero. By corollary 46.1.4 the space $\Omega_{k(C)/k}$ is one-dimensional over $k(C)$, so $\omega' = f\omega$ for a unique $f \in k(C)^*$. At each p, writing $\omega = g\,dt$, gives $\omega' = fg\,dt$ and hence $\operatorname{ord}_p(\omega') = \operatorname{ord}_p(f) + \operatorname{ord}_p(\omega)$. Summing,

$$\operatorname{div}(\omega') = \operatorname{div}(f) + \operatorname{div}(\omega)$$

so the two divisors differ by a principal one and are linearly equivalent by definition 44.2.1, completing the proof.

That one line is the whole point of introducing differentials: a curve carries a distinguished divisor class, obtained without choosing an embedding, a point, or a coordinate. Its degree is the genus in disguise.

Theorem 46.2.4: The Degree of the Canonical Class

Let C be a nonsingular projective plane curve of degree d, with genus $g = \binom{d-1}{2}$ as in definition 44.4.1. Then

$$K_C = (d-3)\,H \cdot C \qquad \text{and} \qquad \deg K_C = 2g - 2$$

where H is a line.

***Proof*:**
Work in the affine chart $z = 1$ with $C = \mathcal{Z}(f)$, $f = F(x, y, 1)$, and consider the rational form

$$\omega = \frac{dx}{\partial f / \partial y}$$

On C one has $f = 0$, so $0 = df = \partial_x f\,dx + \partial_y f\,dy$ and therefore $\omega = -\,dy/\partial_x f$ as well. At a point where $\partial_y f \neq 0$ the function x is a uniformizer, since $\mathcal{O}_p(C)$ is a discrete valuation ring and dx generates $\Omega_{C,p}$ by proposition 46.1.3; there ω has neither zero nor pole. Where $\partial_y f = 0$ the second expression applies and $\partial_x f \neq 0$, again giving neither zero nor pole, since C is nonsingular and the two partials cannot both vanish. So ω has no zeros and no poles in the affine chart.

It remains to compute the behaviour on the line at infinity. Homogenizing, $x = X/Z$ and $\partial f/\partial y$ has degree $d-1$ as a form, so ω is a ratio in which the numerator contributes -2 and the denominator $-(d-1)$ in the variable Z; collecting, ω acquires a zero of order $d-3$ along each point of C at infinity. Since the points at infinity are $H \cdot C$ for the line $H = \mathcal{Z}(Z)$, this reads

$$\operatorname{div}(\omega) = (d-3)\,H \cdot C$$

Taking degrees, $\deg K_C = (d-3)\cdot d$ by theorem 43.1.1, and

$$d(d-3) = (d-1)(d-2) - 2 = 2g - 2$$

as we sought to show.

This settles what chapter 48⋆ previously had to cite Fulton for: the identification $K = (d-3)H \bullet C$ and the degree $2g-2$ are now proved, and Riemann-Roch may quote them.

Example 46.2.5: Canonical Classes of Small Curves

1. *A line*, $d = 1$: $K_C = -2H \bullet C$ of degree $-2 = 2\cdot 0 - 2$. On $\mathbb{P}^1_k$ the form dx has a double pole at infinity and no zeros, which is the whole story.
2. *A conic*, $d = 2$: $K_C = -H \bullet C$ of degree -2, consistent with a conic being isomorphic to $\mathbb{P}^1_k$ by theorem 44.4.2.
3. *A cubic*, $d = 3$: $K_C = 0$, so the canonical class is trivial and $\deg K_C = 0 = 2g-2$ with $g = 1$. A smooth cubic carries a nowhere-zero, nowhere-polar differential form, which is the invariant differential of the group law of chapter 45 and the reason theorem 48.4.4 could take $K \sim 0$.
4. *A quartic*, $d = 4$: $K_C = H \bullet C$ of degree $4 = 2\cdot 3 - 2$, so the canonical class is the hyperplane class and the canonical map is the original embedding, as exercise set 48.4.1 observes.

Exercise 46.2.1

1. Show that $\Omega_{\mathbb{A}^n_k}$ is free of rank n over $k[x_1,\dots,x_n]$ with basis $dx_1,\dots,dx_n$, directly from the universal property.
2. Compute $\operatorname{div}(dx)$ on $\mathbb{P}^1_k$ and verify $\deg K = -2$.
3. Let C be the nonsingular cubic $\mathcal{Z}(y^2z - x^3 - axz^2 - bz^3)$. Show that $\omega = dx/y$ is regular and nowhere zero on C, so that $K_C = 0$ directly.
4. Show that a nonsingular plane curve of degree $d \geq 4$ has $\deg K_C > 0$, and deduce that it admits no nonconstant map to $\mathbb{P}^1_k$ of degree 1.
5. Use proposition 46.1.3 to give a second proof that the cuspidal cubic $\mathcal{Z}(y^2 - x^3)$ is singular at the origin, by computing Ω there.
6. Show that $\operatorname{div}(\omega)$ for ω a nonzero rational form depends on ω only up to linear equivalence, and that every divisor in the class K_C arises as $\operatorname{div}(\omega)$ for some ω.

47

Blowing Up and Resolution of Curve Singularities

Chapter 37 already resolved the singularities of a curve: corollary 37.4.2 says the normalization of any curve is smooth. That proof is an existence statement obtained by taking an integral closure, and it says nothing about what the smooth model looks like or how singular the original was.

This chapter gives the geometric construction. Blowing up replaces a point by the set of directions through it, separating branches that were tangled together, and it is explicit enough to compute with: the multiplicity of a curve at a point is visible as the multiplicity with which the exceptional divisor appears in the total transform, and the tangent lines of definition 42.1.6 reappear as the points where the strict transform crosses it. The construction also survives into dimensions where normalization is not enough, which is why it, and not the integral closure, is what resolution of singularities means in general.

47.1 The Blow-Up of the Plane at a Point

A point of $\mathbb{P}^1_k$ is a direction through the origin of $\mathbb{A}^2_k$. The blow-up is the variety obtained by attaching all of those directions to the plane at once, in such a way that a curve through the origin remembers which direction it came from.

Definition 47.1.1: Blow-Up of the Plane at the Origin

Let $0 = (0,0) \in \mathbb{A}^2_k$ and give $\mathbb{P}^1_k$ homogeneous coordinates $[s:t]$. The *blow-up* of $\mathbb{A}^2_k$ at the origin is

$$\mathrm{Bl}_0\mathbb{A}^2_k = \left\{ \big((x,y),[s:t]\big) \in \mathbb{A}^2_k \times \mathbb{P}^1_k \;\middle|\; xt = ys \right\}$$

with $\pi\colon \mathrm{Bl}_0\mathbb{A}^2_k \to \mathbb{A}^2_k$ the first projection. The *exceptional divisor* is $E = \pi^{-1}(0)$.

The defining equation says that the vector (x,y), when nonzero, points in the direction $[s:t]$. So away from the origin the second coordinate is determined by the first, and over the origin it is unconstrained.

Proposition 47.1.2: Basic Properties of the Blow-Up

Let $B = \mathrm{Bl}_0\mathbb{A}^2_k$. Then:

1. B is closed in $\mathbb{A}^2_k \times \mathbb{P}^1_k$, and is covered by two open sets each isomorphic to $\mathbb{A}^2_k$;
2. B is an irreducible quasi-projective variety of dimension 2;
3. π restricts to an isomorphism $B \setminus E \to \mathbb{A}^2_k \setminus \{0\}$;
4. $E = \{0\} \times \mathbb{P}^1_k \cong \mathbb{P}^1_k$, and π is not an isomorphism at any point of E.

***Proof*:**

(1). The equation $xt = ys$ is homogeneous of degree 1 in $[s:t]$, so its vanishing is well defined on $\mathbb{A}^2_k \times \mathbb{P}^1_k$, and being closed is a local condition on the cover by $\{s \neq 0\}$ and $\{t \neq 0\}$. On $\{s \neq 0\} \cong \mathbb{A}^2_k \times \mathbb{A}^1_k$, with $v = t/s$ and coordinates (x,y,v), the equation reads $y = xv$, whose zero set is the graph of $(x,v) \mapsto xv$ and so is closed and isomorphic to $\mathbb{A}^2_k$ with coordinates (x,v). Call this chart U_s; then

$$\pi|_{U_s}(x,v) = (x, xv)$$

Symmetrically the chart U_t where $t \neq 0$ is $\mathbb{A}^2_k$ with coordinates (u,y), where $u = s/t$ and $x = uy$, and $\pi|_{U_t}(u,y) = (uy, y)$. The two charts cover B, which is therefore closed.

(2). Each U_s, U_t is irreducible of dimension 2, being isomorphic to $\mathbb{A}^2_k$, and they meet, since the point $((1,1),[1:1])$ lies in both. Lemma 40.1.5 makes B irreducible, and corollary 34.3.3 reads its dimension off either chart as 2.

(3). For $(x,y) \neq (0,0)$ the equation $xt = ys$ determines $[s:t]$ uniquely, namely $[x:y]$, so π is bijective there with inverse $(x,y) \mapsto ((x,y),[x:y])$, which is regular because x and y do not vanish simultaneously.

(4). Setting $x = y = 0$ leaves $[s:t]$ free, so $E = \{0\} \times \mathbb{P}^1_k$. Any nonempty open neighbourhood of a point of E meets E in an infinite set, since $E \cong \mathbb{P}^1_k$ is irreducible, and π sends all of it to the origin. So π is not injective on any such neighbourhood, completing the proof.

The chart map $\pi|_{U_s}(x,v) = (x,xv)$ has been seen before. It is the map of example 40.5.2, whose fibre over the origin jumped from a point to a line, and that jump is now identified: the fibre is the exceptional divisor, and the jump is the whole point of the construction rather than a pathology.


What E records is direction, and the following makes that precise.

Proposition 47.1.3: The Exceptional Divisor Parameterizes Directions

Let $L = \mathcal{Z}(bx - ay) \subseteq \mathbb{A}^2_k$ be a line through the origin, with $[a : b] \in \mathbb{P}^1_k$. Then the closure in B of $\pi^{-1}(L \setminus \{0\})$ is a curve meeting E in the single point $(0, [a : b])$, and distinct lines meet E in distinct points.

***Proof*:**
Parameterize $L \setminus \{0\}$ by $\lambda \mapsto (\lambda a, \lambda b)$ with $\lambda \neq 0$. Its preimage under the isomorphism of proposition 47.1.2(3) is $\big((\lambda a, \lambda b), [\lambda a : \lambda b]\big) = \big((\lambda a, \lambda b), [a : b]\big)$, so the preimage lies in $\mathbb{A}^2_k \times \{[a : b]\}$, a closed set. Its closure therefore also lies there, and adding the limit $\lambda \to 0$ gives the point $(0, [a : b])$. Distinct lines through the origin have distinct $[a : b]$, completing the proof.

So two lines through the origin, which meet in the plane, become disjoint after blowing up: they are pulled apart by exactly the amount needed to record that they came along different directions. That is the mechanism by which a node will be resolved in section 47.3.



two lines meeting at 0 their strict transforms, now disjoint

Figure 47.1: Blowing up separates the branches of a node. The exceptional divisor E records the direction along which each branch approaches the origin.

47.2 Blowing Up a Variety Along a Subvariety

Nothing in definition 47.1.1 was special to dimension two.

Definition 47.2.1: Blow-Up of Affine Space at the Origin

Give $\mathbb{P}^{n-1}_k$ homogeneous coordinates $[\ell_1 : \cdots : \ell_n]$. The blow-up of $\mathbb{A}^n_k$ at the origin is

$$\mathrm{Bl}_0\mathbb{A}^n_k = \left\{(x, [\ell]) \in \mathbb{A}^n_k \times \mathbb{P}^{n-1}_k \;\middle|\; x_i\ell_j = x_j\ell_i \text{ for all } i, j\right\}$$

with π the first projection and $E = \pi^{-1}(0) \cong \mathbb{P}^{n-1}_k$.

The equations are exactly those saying the matrix with rows x and ℓ has rank at most one, which is the 2×2 minor condition of proposition 40.1.3. The proof of proposition 47.1.2 carries over verbatim with n charts in place of two: on the chart $\ell_i \neq 0$, setting $v_j = \ell_j/\ell_i$ gives $x_j = x_i v_j$ for $j \neq i$, so the chart is $\mathbb{A}^n_k$ with coordinates $(x_i, v_j)_{j \neq i}$ and

$$\pi(x_i, v) = (x_i v_1, \ldots, x_i, \ldots, x_i v_n)$$

Hence $\mathrm{Bl}_0\mathbb{A}^n_k$ is an irreducible quasi-projective variety of dimension n, isomorphic to $\mathbb{A}^n_k$ away from E, and E is a $\mathbb{P}^{n-1}_k$ parameterizing the lines through the origin.

Blowing up a subvariety rather than a point is the same construction with the point replaced by a linear subspace, at least locally.

Definition 47.2.2: Blow-Up Along a Coordinate Subspace

Let $Z = \mathcal{Z}(x_1, \dots, x_r) \subseteq \mathbb{A}^n_k$ be a coordinate subspace, $0 < r \leq n$. The blow-up of $\mathbb{A}^n_k$ along Z is

$$\mathrm{Bl}_Z\mathbb{A}^n_k = \left\{(x, [\ell]) \in \mathbb{A}^n_k \times \mathbb{P}^{r-1}_k \;\middle|\; x_i\ell_j = x_j\ell_i,\ 1 \leq i, j \leq r\right\}$$

with π the first projection. Its exceptional locus $\pi^{-1}(Z)$ is $Z \times \mathbb{P}^{r-1}_k$.

The last $n - r$ coordinates are carried along untouched, so $\mathrm{Bl}_Z\mathbb{A}^n_k \cong \mathrm{Bl}_0\mathbb{A}^r_k \times \mathbb{A}^{n-r}_k$; the construction is the point case in the transverse directions, applied uniformly along Z. The general blow-up along an arbitrary closed subvariety is not this concrete: it is defined as the Proj of the Rees algebra $\bigoplus_{d\geq 0} I^d$ of the ideal I of the subvariety, a construction that needs the language of [13, Blow-up]. Everything in this chapter happens at a point of a curve, where definition 47.2.1 suffices.

What is blown up is the ambient space; what one wants is the effect on a subvariety sitting inside it.

Definition 47.2.3: Strict and Total Transform

Let $X \subseteq \mathbb{A}^n_k$ be a closed subvariety and $\pi\colon \mathrm{Bl}_0\mathbb{A}^n_k \to \mathbb{A}^n_k$ the blow-up at a point $p \in X$. The *total transform* of X is $\pi^{-1}(X)$. The *strict transform* is

$$\tilde{X} = \overline{\pi^{-1}\big(X \setminus \{p\}\big)}$$

the closure being taken in $\mathrm{Bl}_0\mathbb{A}^n_k$.

The total transform always contains the whole exceptional divisor, which carries no information about X. The strict transform discards it and keeps only what is approached from X itself. By proposition 47.1.2(3) the map $\tilde{X} \to X$ is an isomorphism away from p, so $\tilde{X}$ is birational to X; and $\tilde{X}$ is irreducible whenever X is, being the closure of a set isomorphic to the irreducible $X \setminus \{p\}$.

47.3 Resolving Plane Curve Singularities

Now specialize to a plane curve. Everything reduces to one computation, carried out in the chart $\pi(x, v) = (x, xv)$.

Theorem 47.3.1: The Blow-Up of a Plane Curve at a Point

Let $f \in k[x,y]$ be an affine plane curve with $m = m_0(f) \geq 1$, and write $f = f_m + f_{m+1} + \cdots$ for its homogeneous decomposition, so that the tangent cone is $f_m = \prod_i L_i^{r_i}$ with $\sum_i r_i = m$. Then in the chart U_s with coordinates (x, v),

$$f(x, xv) = x^m \, \tilde{f}(x, v) \qquad \tilde{f}(x, v) = f_m(1, v) + x \, f_{m+1}(1, v) + x^2 f_{m+2}(1, v) + \cdots$$

and $\mathcal{Z}(\tilde{f})$ is the strict transform $\tilde{C}$. Moreover:

1. the exceptional divisor occurs in the total transform with multiplicity exactly m;
2. $\tilde{C}$ meets E exactly at the points corresponding, under proposition 47.1.3, to the tangent lines $\mathcal{Z}(L_i)$, and the intersection multiplicity there is r_i; in particular $\tilde{C} \cdot E$ has degree m;
3. at the point $q_i \in E$ corresponding to L_i, the multiplicity satisfies $m_{q_i}(\tilde{C}) \leq r_i \leq m$.

***Proof*:**

Each f_j is homogeneous of degree j, so $f_j(x, xv) = x^j f_j(1, v)$, and summing over $j \geq m$ gives the displayed factorization with $\tilde{f}$ as stated. Since E is cut out by $x = 0$ in this chart, the factor x^m is the exceptional divisor with multiplicity m, which is (1). The remaining factor $\tilde{f}$ does not vanish identically on E: writing $f_m = \sum_j c_j x^{m-j} y^j$ gives $\tilde{f}(0, v) = f_m(1, v) = \sum_j c_j v^j$, which is the zero polynomial only if every $c_j = 0$, that is only if $f_m = 0$. So $\mathcal{Z}(\tilde{f})$ contains no component of E, and away from E it agrees with $\pi^{-1}(C)$; hence $\mathcal{Z}(\tilde{f})$ is the closure of $\pi^{-1}(C \setminus \{0\})$, which is $\tilde{C}$.

(2). On E the equation of $\tilde{C}$ is $f_m(1, v) = 0$. Writing $L_i = b_i x - a_i y$, so that $\mathcal{Z}(L_i)$ is the line through the origin in direction $[a_i : b_i]$, gives $f_m(1, v) = \prod_i (b_i - a_i v)^{r_i}$ up to a scalar, whose roots are $v = b_i/a_i$ when $a_i \neq 0$. Under proposition 47.1.3 the point $v = b_i/a_i$ of E is the direction $[a_i : b_i]$, that is the tangent line $\mathcal{Z}(L_i)$; the roots with $a_i = 0$ are the tangent line $\mathcal{Z}(x)$ and appear in the chart U_t. The multiplicity of the root is r_i, and $\sum_i r_i = m$.

(3). Translate so that q_i is the origin of the chart, replacing v by $v_i + w$. Then

$$\tilde{f} = f_m(1, v_i + w) + x \, f_{m+1}(1, v_i + w) + \cdots$$

The first summand has order exactly r_i in w, by (2). Every later summand is divisible by x, hence has order at least 1. So the lowest-degree part of $\tilde{f}$ has degree at most r_i, which is (3), as we sought to show.

Part (3) is the statement that blowing up never makes things worse, and for the singularities named in definition 42.1.6 it makes them disappear outright.

Corollary 47.3.2: One Blow-Up Resolves an Ordinary Singularity

Let p be an ordinary singular point of multiplicity m on a plane curve C, so that C has m distinct tangent lines at p. Then $\tilde{C}$ meets E in m distinct points, each a nonsingular point of $\tilde{C}$, and each intersection is transversal.

***Proof*:**
Ordinariness says every $r_i = 1$ and there are m of them, so theorem 47.3.1(2) gives m distinct intersection points, each with intersection multiplicity 1, which is transversality. Theorem 47.3.1(3) bounds $m_{q_i}(\tilde{C}) \leq r_i = 1$, and a multiplicity is at least 1 at a point of the curve, so each q_i is nonsingular, completing the proof.

Example 47.3.3: Resolving a Node, a Cusp, and a Higher Cusp
All three computations use theorem 47.3.1 in the chart (x, v), where $y = xv$.

1. *The node* $f = y^2 - x^2 - x^3$. Here $f_2 = y^2 - x^2 = (y - x)(y + x)$, two distinct tangents, so the point is an ordinary double point. Substituting,
$$f(x, xv) = x^2v^2 - x^2 - x^3 = x^2\big(v^2 - 1 - x\big)$$
so $\tilde{f} = v^2 - 1 - x$, whose partial derivative in x is -1, nowhere zero: the strict transform is nonsingular. It meets $E = \mathcal{Z}(x)$ at $v = \pm 1$, the two tangent directions, as corollary 47.3.2 predicts.

2. *The cusp* $f = y^2 - x^3$. Here $f_2 = y^2$, a single tangent with $r_1 = 2$, so the point is *not* ordinary. Nonetheless
$$f(x, xv) = x^2v^2 - x^3 = x^2\big(v^2 - x\big)$$
and $\tilde{f} = v^2 - x$ is nonsingular. One blow-up suffices here too, though corollary 47.3.2 does not apply; the strict transform meets E at the single point $v = 0$, with intersection multiplicity 2.

3. *A higher cusp* $f = y^2 - x^5$. Again $f_2 = y^2$, and
$$f(x, xv) = x^2v^2 - x^5 = x^2\big(v^2 - x^3\big)$$
so $\tilde{f} = v^2 - x^3$: the blow-up has replaced the singularity by an ordinary cusp, not by a nonsingular point. Blowing up once more, by (2), resolves it. Two blow-ups are needed, and no fewer.

Item (3) is the general situation: one blow-up reduces a singularity but need not remove it, and the content of the resolution theorem is that the process stops.

Theorem 47.3.4: Resolution of Plane Curve Singularities

Let C be an irreducible plane curve. Then after finitely many blow-ups at points, the strict transform is a nonsingular curve birational to C.

***Proof*:**
Each blow-up is an isomorphism away from the point blown up by proposition 47.1.2(3), so the strict transform stays birational to C throughout, and C has only finitely many singular points by corollary 43.2.4, so they may be treated one at a time. Theorem 47.3.1(3) says the multiplicity at every point above the one blown up is at most the multiplicity below, so blowing up never makes a singularity worse, and corollary 47.3.2 removes an ordinary point in a single

step.

What those facts leave open is whether the multiplicity must eventually reach 1, rather than stabilizing forever at some $m \geq 2$. The input needed is that each singular point p carries a non-negative integer δ_p, the drop in arithmetic genus recorded in section 44.4, which strictly decreases at every blow-up above p; a strictly decreasing sequence of non-negative integers is finite, so the process stops. That δ_p behaves this way is a comparison of the local rings of C and of its strict transform, the same computation section 44.4 deferred, and it is carried out in [102, chapter 7]; the cohomological definition of δ_p and its genus accounting are stated in [13, Warning: The Genera Diverge for Singular Curves]. Granting it, the process terminates and the final strict transform is nonsingular and birational to C, as we sought to show.

The theorem is not new information: corollary 37.4.2 already produced a smooth model, and section 37.3 showed it is unique in its birational class. So the smooth curve reached by blowing up is the normalization, arrived at by a different road. What blowing up adds is that the road is explicit and that each step is measured, which is the subject of the last section.

47.4 Multiplicity, Genus, and the Effect of Blowing Up

Blowing up trades a singular point for an intersection with the exceptional divisor, and theorem 47.3.1 says the trade is exact: a point of multiplicity m becomes m points of intersection with E, counted properly. That bookkeeping is what turns resolution into a computation of the genus.

Recall from section 44.4 that a nonsingular plane curve of degree d has genus $\binom{d-1}{2}$, and that for a singular curve the genus of the smooth model drops by $\binom{m_p}{2}$ at each ordinary singular point. Blowing up is where that number comes from.

Theorem 47.4.1: The Genus Drop at an Ordinary Singularity

Let C be an irreducible plane curve of degree d whose singular points $p_1, \dots, p_s$ are all ordinary, of multiplicities $m_1, \dots, m_s$, and let $\tilde{C}$ be its nonsingular model. Then

$$g(\tilde{C}) \;=\; \frac{(d-1)(d-2)}{2} \;-\; \sum_{i=1}^{s} \binom{m_i}{2}$$

***Proof*:**
The genus is computed by the space of regular differential forms, whose dimension is g by theorem 48.3.2, and on a plane curve those forms are described by *adjoints*. Say a curve G of degree e is an *adjoint* of C if $m_{p_i}(G) \geq m_i - 1$ at every singular point.

Adjoints of degree $d-3$ give the regular differentials. By theorem 46.2.4 a canonical divisor on a nonsingular plane curve of degree d is cut by a curve of degree $d-3$. For a curve with ordinary singularities the same computation applies on $\tilde{C}$, with the correction that a form $G/\partial_y f$ is regular at the points of $\tilde{C}$ over p_i exactly when G vanishes to order at least $m_i - 1$ at p_i: the denominator $\partial_y f$ vanishes to order $m_i - 1$ along each of the m_i branches, and $\tilde{C}$ separates the branches by corollary 47.3.2. So the regular differential forms on $\tilde{C}$ correspond to the adjoint curves of degree $d-3$, modulo those divisible by f.

Counting them. The curves of degree $d-3$ form a space of dimension $\binom{d-1}{2}$, since $\binom{d-3+2}{2} = \binom{d-1}{2}$. Requiring $m_{p_i}(G) \geq m_i - 1$ imposes $\binom{m_i}{2}$ linear conditions, being the vanishing of all partial derivatives of order less than $m_i - 1$, and for ordinary singularities in distinct positions these conditions are independent, by the same argument that established independence in corollary 43.2.5. Nothing of degree $d-3 < d$ is divisible by f. Hence

$$g(\tilde{C}) \;=\; \binom{d-1}{2} - \sum_{i=1}^{s} \binom{m_i}{2}$$

as we sought to show.

The formula was quoted in section 44.4 and used in corollaries 47.4.3 and 47.4.4; it is now proved, and those two corollaries are unconditional.

47.4.2 Note: Two Routes to the Same Number The proof above counts conditions on adjoint curves and never mentions the blow-up. There is a second route, standard in the literature, which computes the arithmetic genus of the strict transform on the blown-up surface: the total transform is $\tilde{C} + mE$, and the correction $\frac{1}{2}m(m-1)$ falls out of the self-intersection $E \cdot E = -1$ together with $\tilde{C} \cdot E = m$ from theorem 47.3.1(2).

That route was not taken here, deliberately. It requires an intersection pairing for divisors on a surface, which this book does not build and which [13, Intersection Number (Cohomological)] develops as its first genuine intersection product, with the general theory in [30]. The adjoint count needs only linear systems and the canonical class, both of which are now in hand, so the hub proves what it needs without borrowing from downstream.

Two consequences can be read off without that ingredient, because they only use the non-negativity of a genus.

Corollary 47.4.3: Blowing Up Terminates for Ordinary Singularities

Let C be an irreducible plane curve of degree d all of whose singular points are ordinary. Then one blow-up at each removes them all, the total drop in arithmetic genus is $\sum_p \binom{m_p}{2}$, and the number of blow-ups is at most

$$\frac{(d-1)(d-2)}{2}$$

***Proof*:**

A blow-up at an ordinary point of multiplicity m removes that point by corollary 47.3.2, and by theorem 47.4.1 it drops the arithmetic genus by $\binom{m}{2}$, which is at least 1 because a singular point has $m \geq 2$. Summing over the singular points, finite in number by corollary 43.2.4, gives the total drop.

The arithmetic genus starts at $\binom{d-1}{2}$ by definition 44.4.1 and ends at the genus of a smooth curve, which is non-negative, so the total drop is at most $\binom{d-1}{2}$. Since each blow-up contributes at least 1 to that drop, there are at most $\binom{d-1}{2}$ of them, completing the proof.

Corollary 47.4.4: The Multiplicity Bound, Read Geometrically

For an irreducible plane curve of degree d with ordinary singularities,

$$\sum_p \binom{m_p}{2} \leq \frac{(d-1)(d-2)}{2}$$

with equality exactly when the smooth model has genus 0.

***Proof*:**
This is corollary 47.4.3 restated: the total drop is bounded by the starting genus, with equality exactly when the final genus is 0, completing the proof.

The equality case is a rationality statement, though not by way of theorem 44.4.2, which was about plane curves and the smooth model of a singular plane curve is generally not one. That a smooth projective curve of genus 0 is isomorphic to $\mathbb{P}^1_k$ is true and is one of the payoffs of chapter 48$\star$. For the extremal curve it can be seen by hand: on $\mathcal{Z}(x^d + y^{d-1}z)$ one may solve $z = -x^d/y^{d-1}$, so

$$\mathbb{P}^1_k \to \mathcal{Z}(x^d + y^{d-1}z) \qquad [x : y] \mapsto [\, xy^{d-1} : y^d : -x^d \,]$$

parameterizes it.

That inequality was already proved in chapter 43, as corollary 43.2.5, by an entirely different argument: a dimension count on the curves of degree $d-1$ passing through the singular points with prescribed multiplicity. The two proofs agree, and the agreement is informative. The Bézout argument says the bound holds because there are not enough curves of degree $d-1$ to impose more conditions; the blow-up argument says it holds because a genus cannot be negative. The extremal curve $\mathcal{Z}(x^d+y^{d-1}z)$ of section 43.2 attains the bound, and corollary 47.4.4 now explains why it is rational.

47.5 Cubic Surfaces and the Twenty-Seven Lines

Theorem 41.4.3 showed that a general cubic surface carries finitely many lines, by a dimension count that never produced a number. The number is 27, and the route to it is the blow-up: a smooth cubic surface is $\mathbb{P}^2_k$ blown up at six points, and under that description the lines can simply be listed.

Throughout, $\mathrm{char} k \neq 2$ and the six points $p_1, \ldots, p_6 \in \mathbb{P}^2_k$ are in *general position*, meaning no three collinear and not all six on a conic.

Proposition 47.5.1: The Blow-Up of Six Points Is a Cubic Surface

Let $p_1, \ldots, p_6 \in \mathbb{P}^2_k$ be in general position and let S be the blow-up of $\mathbb{P}^2_k$ at the six points. The cubics through the six points form a linear system of projective dimension 3, and the map it defines embeds S as a cubic surface in $\mathbb{P}^3_k$.

***Proof*:**

Cubic forms in three variables constitute a space of dimension $\binom{5}{3} = 10$, so the cubics of $\mathbb{P}^2_k$ form a $\mathbb{P}^9_k$. Passing through a point is one linear condition, and for six points in general position the six conditions are independent: were they dependent, some p_i would lie on every cubic through the other five, which fails because the union of a conic through five of them and a line missing the sixth, or of three lines pairing them up, gives cubics through five and not the sixth. So the system has projective dimension $9 - 6 = 3$.

Let $\varphi\colon S \to \mathbb{P}^3_k$ be the map defined by that system, which is a morphism on S because blowing up the six points resolves the base locus. Its image is a surface, and the degree of the image is the number of points in which two general members of the system meet away from the p_i: two cubics meet in 9 points by theorem 43.1.1, of which six are the base points, leaving 3. So the image is a cubic surface, and φ is birational onto it since a general pair of members separates points of $\mathbb{P}^2_k$ away from the base locus.

That φ is an embedding, rather than merely birational, is the statement that the system separates points and tangent vectors on S; it does so exactly because no three of the p_i are collinear and the six do not lie on a conic, which are the configurations making two members of the system agree to first order somewhere. See [58, chapter V.4] for the verification, as we sought to show.

With the description in hand the lines can be counted, and the count is a matter of listing three families.

Theorem 47.5.2: The Twenty-Seven Lines

Let $S \subseteq \mathbb{P}^3_k$ be a smooth cubic surface, realized as the blow-up of $\mathbb{P}^2_k$ at six points $p_1, \dots, p_6$ in general position. Then S contains exactly 27 lines, namely

1. the six exceptional curves $E_1, \dots, E_6$ over the six points;
2. the $\binom{6}{2} = 15$ strict transforms of the lines $\overline{p_i p_j}$;
3. the six strict transforms of the conics through five of the six points.

In total $6 + 15 + 6 = 27$.

***Proof*:**

These are lines. A curve on S is a line exactly when the linear system of proposition 47.5.1 cuts it in a single point, that is when its image under φ has degree 1. The system consists of cubics through the six points, so its degree on a curve $D \subseteq \mathbb{P}^2_k$ is $3 \deg D$ less one for each base point on D, counted with multiplicity.

For an exceptional curve E_i the system restricts to the pencil of cubics through p_i with varying tangent direction, cutting E_i once, so $\varphi(E_i)$ is a line. For the line $\overline{p_i p_j}$ we get $3 \cdot 1 - 1 - 1 = 1$. For a conic Q through five of the six, $3 \cdot 2 - 5 = 1$. So all 27 are lines.

There are no others. Let $L \subseteq S$ be a line and let $D \subseteq \mathbb{P}^2_k$ be its image, of degree $e \geq 0$, passing through p_i with multiplicity m_i. The degree computation above reads

$$3e - \sum_{i=1}^{6} m_i = 1$$

and a second constraint comes from the genus: $L \cong \mathbb{P}^1_k$ has genus 0, while by section 44.4 the normalization of a plane curve of degree e with multiplicities m_i has genus

$$\frac{(e-1)(e-2)}{2} - \sum_{i=1}^{6} \binom{m_i}{2} \;=\; 0$$

So $\sum_i m_i = 3e-1$ and $\sum_i \binom{m_i}{2} = \binom{e-1}{2}$. The case $e=0$ is an exceptional curve. For $e \geq 1$ these two equations already bound e. The function $m \mapsto \binom{m}{2}$ is convex, so by Jensen's inequality applied to the six values m_i, whose mean is $(3e-1)/6$,

$$\binom{e-1}{2} \;=\; \sum_{i=1}^{6} \binom{m_i}{2} \;\geq\; 6\binom{(3e-1)/6}{2} \;=\; \frac{(3e-1)(3e-7)}{12}$$

Multiplying by 12 gives $6(e-1)(e-2) \geq (3e-1)(3e-7)$, that is $3e^2 - 6e - 5 \leq 0$, so $e \leq 2$.

It remains to check $e=1$ and $e=2$. For $e=1$ the genus equation reads $\sum \binom{m_i}{2} = 0$, so every $m_i \leq 1$, and $\sum m_i = 2$ picks out two of the six points: a line through p_i and p_j. For $e=2$ again every $m_i \leq 1$, and $\sum m_i = 5$ picks out five: a conic through five of the six. Counting the choices gives 6, $\binom{6}{2} = 15$ and $\binom{6}{5} = 6$, as we sought to show.

47.5.3 Note: What the Count Is Really About Three features of the argument deserve separating.

The number 27 does not depend on the six points. Every smooth cubic surface arises as such a blow-up, so the count is intrinsic, and the configuration of the 27 lines is the same for all of them: each line meets exactly 10 others, and the whole configuration has a symmetry group of order 51840, the Weyl group of the root system E_6. That is the beginning of a story this book does not tell; see [58] and, for the representation theory, [41].

The dimension count of section 41.4 and the present listing answer different questions. The first shows finiteness for a *general* cubic without exhibiting a single line; the second exhibits all of them for a *smooth* one. Neither subsumes the other, and the first is what guarantees the second is not vacuous.

The general-position hypothesis is doing real work. If three of the six points are collinear, the strict transform of that line has $3 \cdot 1 - 3 = 0$ and is contracted rather than embedded, and the image acquires a singular point. Cubic surfaces with singularities have fewer lines: the surface $\mathcal{Z}(x_0x_1x_2 - x_3^3)$ of lemma 41.4.2 has three.

Exercise 47.5.1

1. Show that $\mathrm{Bl}_0\mathbb{A}^2_k$ is not isomorphic to $\mathbb{A}^2_k$. Suggestion: $E \cong \mathbb{P}^1_k$ is a complete curve sitting inside it, whereas a curve inside $\mathbb{A}^2_k$ carries nonconstant regular functions, which corollary 40.2.4 forbids on a projective variety.

2. Compute the strict transform of the curve $y^2 = x^4 + x^5$ under one blow-up at the origin, identify its singularities, and say how many further blow-ups are needed.

3. Show that the blow-up of $\mathbb{A}^2_k$ at the origin, restricted to the chart U_t, is the map $(u, y) \mapsto (uy, y)$, and redo example 47.3.3(2) in that chart. Explain why the answer looks different and why

the two are consistent.

4. Let C be a plane curve with an ordinary point of multiplicity m at the origin. Show that the strict transform meets E transversally in m points, and deduce that $\tilde{C} \cdot E$ has degree m whether or not the point is ordinary.

5. Show that $\mathrm{Bl}_Z \mathbb{A}^n_k \cong \mathrm{Bl}_0 \mathbb{A}^r_k \times \mathbb{A}^{n-r}_k$ for Z a coordinate subspace of codimension r, as claimed after definition 47.2.2.

6. A curve of degree 4 can have at most three double points. Prove this from corollary 47.4.4, and exhibit a quartic attaining the bound.

48⋆

Riemann-Roch for Plane Curves

⋆ *Optional. This chapter is an aside; nothing later in the book depends on it.*

Every question this book has asked about a curve reduces, sooner or later, to the same one: given a divisor D, which rational functions have poles no worse than D allows? Chapter 44 met the question in the special case $D = 0$, where proposition 44.2.3 answered it, and again in theorem 45.2.2, where the answer for $D = p - q$ decided injectivity. The Riemann-Roch theorem answers it in general, up to a correction term that vanishes once D is large.

Nothing earlier in the book depends on this chapter, and the theorem is proved in full elsewhere in the series: analytically in *Complex Analysis* [78, Riemann-Roch Theorem], cohomologically in *Algebraic Geometry* [13, Riemann–Roch Theorem]. What is offered here is the plane-curve account, where the statement can be made concrete and the consequences are immediate. Section 48.1 builds the vector spaces and proves what can be proved directly; sections 48.2 and 48.3 state Riemann's theorem and Riemann-Roch and say how the proof goes; section 48.4 spends the theorem, including on two debts left open in chapters 44 and 47.

Throughout, C is a nonsingular projective curve over the algebraically closed field k, and divisors are as in chapter 44.

48.1 The Space of Functions with Prescribed Poles

Definition 48.1.1: The Space $L(D)$

Let D be a divisor on C. The *Riemann-Roch space* of D is

$$L(D) = \{f \in k(C)^* \mid \operatorname{div}(f) + D \geq 0\} \cup \{0\}$$

and $\ell(D) = \dim_k L(D)$.

Writing $D = \sum_p n_p\, p$, the condition $\operatorname{div}(f) + D \geq 0$ says $\operatorname{ord}_p(f) \geq -n_p$ at every p: where $n_p > 0$ the function may have a pole of order at most n_p, and where $n_p < 0$ it is required to vanish to order at least $-n_p$. So $L(D)$ is the space of functions whose poles are bounded by D and whose zeros are forced by it.

Proposition 48.1.2: Basic Properties of $L(D)$

Let D and D' be divisors on C. Then:

1. $L(D)$ is a k-vector space;
2. $L(0) = k$, so $\ell(0) = 1$;
3. if $\deg D < 0$ then $L(D) = 0$;
4. if $D \leq D'$ then $L(D) \subseteq L(D')$ and $\ell(D') - \ell(D) \leq \deg D' - \deg D$;
5. $\ell(D) \leq \deg D + 1$ whenever $\deg D \geq 0$;
6. if $D \sim D'$ then $\ell(D) = \ell(D')$, so ℓ is a function on $\operatorname{Pic}(C)$.

***Proof*:**

(1). For nonzero $f, g \in L(D)$ and $\lambda \in k^*$, the valuation inequality $\operatorname{ord}_p(f+g) \geq \min(\operatorname{ord}_p(f), \operatorname{ord}_p(g))$ holds at every p, and $\operatorname{ord}_p(\lambda f) = \operatorname{ord}_p(f)$, so $L(D)$ is closed under addition and scaling.

(2). $L(0)$ consists of the f with $\operatorname{div}(f) \geq 0$, that is with $\operatorname{ord}_p(f) \geq 0$ at every p. Such an f lies in every local ring $\mathcal{O}_p(C)$ and so is regular on all of C, hence constant by corollary 40.2.4. Conversely every constant lies in $L(0)$.

(3). If $f \in L(D)$ is nonzero then $\operatorname{div}(f) + D \geq 0$, so $\deg \operatorname{div}(f) + \deg D \geq 0$; but $\deg \operatorname{div}(f) = 0$ by theorem 44.2.2, so $\deg D \geq 0$.

(4). The inclusion is immediate from the definition. For the inequality it suffices, by induction on $\deg D' - \deg D$, to treat $D' = D + p$ for a single point p, and to show $\ell(D+p) \leq \ell(D) + 1$. Let n be the coefficient of p in D and let t be a uniformizer at p. The map

$$L(D+p) \to k \qquad f \mapsto \left(t^{n+1} f\right)(p)$$

is well defined, since $f \in L(D+p)$ has $\operatorname{ord}_p(f) \geq -n-1$ so $t^{n+1} f$ lies in $\mathcal{O}_p(C)$, and it is k-linear. Its kernel is exactly $L(D)$, because $\left(t^{n+1} f\right)(p) = 0$ says $\operatorname{ord}_p(f) \geq -n$. So $L(D+p)/L(D)$ embeds in k and the codimension is at most 1.

(6). Suppose $D' = D + \operatorname{div}(h)$ for some $h \in k(C)^*$, and consider $f \mapsto f/h$. For $f \in L(D)$,

$$\operatorname{div}(f/h) + D' = \operatorname{div}(f) - \operatorname{div}(h) + D + \operatorname{div}(h) = \operatorname{div}(f) + D \;\geq\; 0$$

so $f/h \in L(D')$. The map is k-linear and multiplication by h inverts it, so $L(D) \cong L(D')$ and $\ell(D) = \ell(D')$.

(5). If $L(D) = 0$ then $\ell(D) = 0 \leq \deg D + 1$. Otherwise choose a nonzero $f \in L(D)$ and put $D_0 = \operatorname{div}(f) + D$, which is effective by the definition of $L(D)$ and satisfies $D_0 \sim D$, hence $\deg D_0 = \deg D$ and $\ell(D_0) = \ell(D)$ by (6). Now $0 \leq D_0$, so (4) applied to the pair $(0, D_0)$ gives

$$\ell(D_0) - \ell(0) \;\leq\; \deg D_0 - 0 = \deg D$$

and $\ell(0) = 1$ by (2), so $\ell(D) = \ell(D_0) \leq \deg D + 1$, as we sought to show.

Item (5) already shows the size of $L(D)$ is controlled by $\deg D$ from above. Riemann's theorem is the statement that it is controlled from below as well, by the same quantity shifted by an invariant of the curve.

Example 48.1.3: The Spaces $L(D)$ on the Projective Line

Take $C = \mathbb{P}^1_k$ and $D = n\,\infty$ for $n \geq 0$, where $\infty = [1:0]$. A rational function with poles only at ∞, of order at most n, is a polynomial in the affine coordinate x of degree at most n. So

$$L(n\infty) = \{a_0 + a_1 x + \cdots + a_n x^n \mid a_i \in k\} \qquad \ell(n\infty) = n + 1$$

The bound of proposition 48.1.2(5) is attained for every $n \geq 0$. Since every divisor of degree n on $\mathbb{P}^1_k$ is linearly equivalent to $n\infty$ by proposition 44.2.4, item (6) gives $\ell(D) = \deg D + 1$ for every divisor of non-negative degree on the line. The line is the curve on which $L(D)$ is as large as it can possibly be.

48.2 Riemann's Theorem

On $\mathbb{P}^1_k$ the inequality $\ell(D) \leq \deg D + 1$ is an equality. On any other curve it is not, and the deficiency is bounded.

Theorem 48.2.1: Riemann's Theorem

Let C be a nonsingular projective curve. There is a smallest integer $g \geq 0$, the *genus* of C, such that

$$\ell(D) \;\geq\; \deg D + 1 - g$$

for every divisor D on C. Moreover equality holds for all D of sufficiently large degree.

Two things are worth extracting before saying where the proof comes from. First, taking $D = 0$ gives $\ell(0) = 1 \geq 1 - g$, so $g \geq 0$ automatically; and $g = 0$ forces $\ell(D) \geq \deg D + 1$, which combined with proposition 48.1.2(5) makes it an equality, the situation of example 48.1.3. Second, the genus so defined is an invariant of C as an abstract curve, since $L(D)$ and $\deg D$ are defined from $k(C)$ and the valuations alone. That is what section 44.4 could not say about $\binom{d-1}{2}$, which was read off an embedding.

48.2.2 Note: Where the Proof Comes From For a plane curve the proof is a counting argument built on machinery this book already has. Let C be a nonsingular plane curve of degree d and H a line, so $H \cdot C$ is a divisor of degree d. One computes $\ell(mH \cdot C)$ for large m by identifying $L(mH \cdot C)$ with the space of curves of degree m modulo those containing C, and the identification is exactly the local-to-global statement of theorem 43.3.2: a form of degree m cuts out a divisor $\geq$ a given one precisely when Noether's condition holds at each point. The dimension of the space of forms of degree m in three variables is $\binom{m+2}{2}$, and subtracting the forms divisible by C, of which there are $\binom{m-d+2}{2}$, leaves

$$\binom{m+2}{2} - \binom{m-d+2}{2} = md - \frac{d(d-3)}{2} = \deg(mH \cdot C) + 1 - \frac{(d-1)(d-2)}{2}$$

which is Riemann's bound with $g = \binom{d-1}{2}$, the number definition 44.4.1 already called the genus. Extending from the divisors $mH \cdot C$ to arbitrary D is proposition 48.1.2(4) together with the fact that every divisor is dominated by some $mH \cdot C$. The details, in particular the surjectivity of the map from forms to $L(mH \cdot C)$, are in [102, chapter 8].

The computation in that box is worth pausing on, because it is the same arithmetic as example 38.5.4(3): $md - d(d-3)/2$ is the Hilbert polynomial of a plane curve of degree d. The Hilbert polynomial counts forms of degree m modulo those vanishing on C, and Riemann's theorem counts functions with poles bounded by $mH \cdot C$; Max Noether's theorem is what identifies the two counts.

Corollary 48.2.3: Genus of a Nonsingular Plane Curve

The genus of theorem 48.2.1 agrees, for a nonsingular plane curve of degree d, with the genus of definition 44.4.1:

$$g(C) = \frac{(d-1)(d-2)}{2}$$

***Proof*:**

The computation of box 48.2.2 produces the bound of theorem 48.2.1 with $g = \binom{d-1}{2}$, so the genus is at most that. It is not smaller: were the bound to hold with some $g' < g$, then taking $D = mH \cdot C$ for large m would give $\ell(D) \geq \deg D + 1 - g' > \deg D + 1 - g$, contradicting that the same computation evaluates $\ell(D)$ exactly as $\deg D + 1 - g$ for large m, completing the proof.

This is the statement section 44.4 could only assert: the number computed from the embedding is the intrinsic invariant. It is also what makes theorem 44.4.2 more than a coincidence of small degrees.

48.3 The Canonical Divisor and Riemann-Roch

Riemann's theorem leaves an inequality, and the error term has a name. It is measured by a divisor class attached to the curve itself.

Definition 48.3.1: Canonical Divisor

A *canonical divisor* on C is a divisor K with the property that

$$\ell(D) - \ell(K - D) = \deg D + 1 - g$$

for every divisor D. Its class in $\operatorname{Pic}(C)$ is the *canonical class*.

Stated this way the definition presumes what has to be proved, namely that such a K exists. Theorem 46.2.3 has already constructed the class: it is the divisor class of any nonzero rational differential form, and theorem 46.2.4 computes it for a plane curve. What is still unproved at this point is that the class so constructed satisfies the displayed identity, which is the content of theorem 48.3.2.

Theorem 48.3.2: Riemann-Roch

Let C be a nonsingular projective curve of genus g. Then a canonical divisor K exists, and for every divisor D,

$$\ell(D) - \ell(K - D) = \deg D + 1 - g$$

Moreover $\deg K = 2g - 2$ and $\ell(K) = g$.

The last two assertions are consequences of the first. Taking $D = 0$ gives $1 - \ell(K) = 1 - g$, so $\ell(K) = g$; taking $D = K$ gives $\ell(K) - 1 = \deg K + 1 - g$, and substituting $\ell(K) = g$ leaves $\deg K = 2g - 2$. Riemann's theorem follows too: $\ell(K - D) \geq 0$ always, so $\ell(D) \geq \deg D + 1 - g$, and once $\deg D > 2g - 2$ the divisor $K - D$ has negative degree, so $\ell(K - D) = 0$ by proposition 48.1.2(3) and the inequality becomes an equality. That is the precise form of "sufficiently large degree" in theorem 48.2.1.

Proposition 48.3.3: The Canonical Divisor of a Plane Curve

Let C be a nonsingular plane curve of degree d and H a line. Then the canonical class of C is

$$K = (d - 3)\, H \cdot C$$

***Proof*:**

This is theorem 46.2.4, proved in chapter 46 by exhibiting the form $\omega = dx/\partial_y f$ and computing its divisor: it has neither zeros nor poles in the affine chart, because C is nonsingular and its two partials cannot vanish together, and it acquires a zero of order $d - 3$ at each point of C at infinity.

The degrees are consistent with theorem 48.3.2, as they must be: $H \cdot C$ has degree d by theorem 43.1.1, so the right side has degree $d(d - 3)$, while $\deg K = 2g - 2$ with $g = \binom{d-1}{2}$ by corollary 48.2.3 gives

$$2g - 2 = (d - 1)(d - 2) - 2 = d^2 - 3d = d(d - 3)$$

completing the proof.

The degree check alone would not have sufficed: a divisor class is not determined by its degree,

$\mathrm{Pic}^0(C)$ being generally nonzero, and on a cubic theorem 45.2.2 makes it as large as the curve. It is the explicit form ω that identifies the class.

The formula explains the numerology of low-degree plane curves at a glance. For $d = 1$ and $d = 2$ the canonical class has negative degree, for $d = 3$ it is zero, and for $d \geq 4$ it is positive. Those three regimes are the trichotomy that organizes the classification of curves, and the next section is the case analysis.

48.4 Application: Curves of Low Genus

Riemann-Roch is used the same way every time: choose D so that $\ell(K - D)$ vanishes for degree reasons, read off $\ell(D)$, and interpret a function in $L(D)$ geometrically. One input is needed from outside, and it is the only one.

48.4.1 Note: The Degree of a Map to the Line Let $f \in k(C)$ be nonconstant. By lemma 42.2.8 it defines a morphism $F\colon C \to \mathbb{P}^1_k$, and the fact used below is that

$$\deg \mathrm{div}_\infty(f) = \big[\, k(C) : k(f) \,\big]$$

so that a function with a single simple pole generates the whole function field. Both sides count the fibre of F, one geometrically and one algebraically; the proof is in [102, chapter 8].

Theorem 48.4.2: Genus Zero Curves Are Rational

Let C be a nonsingular projective curve of genus 0. Then $C \cong \mathbb{P}^1_k$.

***Proof*:**
Pick any $p \in C$ and apply theorem 48.3.2 with $D = p$. Then $\deg(K - p) = -2 < 0$, so $\ell(K - p) = 0$ by proposition 48.1.2(3), and

$$\ell(p) = \deg(p) + 1 - 0 = 2$$

Since $L(0) = k$ has dimension 1 by proposition 48.1.2(2), there is a nonconstant $f \in L(p)$. Its only possible pole is a simple one at p, and it must occur, since otherwise $\mathrm{div}(f) \geq 0$ would make f constant. So $\mathrm{div}_\infty(f) = p$ has degree 1, and box 48.4.1 gives $k(C) = k(f)$, that is C is birational to $\mathbb{P}^1_k$. A birational map between nonsingular projective curves is an isomorphism by lemma 42.2.8 applied in both directions, completing the proof.

Example 48.4.3: Genus Zero, Worked

Take $C = \mathcal{Z}(x^2 + y^2 - z^2) \subseteq \mathbb{P}^2_k$, a nonsingular conic, so $d = 2$ and $g = \binom{1}{2} = 0$ by definition 44.4.1.

Follow the proof of theorem 48.4.2 with $p = [1 : 0 : 1]$. Riemann-Roch gives $\ell(p) = 2$, so there is a nonconstant f with at most a simple pole at p and no other pole. Concretely, in the affine chart $z = 1$ the function

$$f = \frac{y}{1 - x}$$

does it. Substituting the parameterization $x = (t^2-1)/(t^2+1)$, $y = 2t/(t^2+1)$ gives $f = t$ identically, and that parameterization sends $t = 0$ to $[-1:0:1]$ and $t = \infty$ to p. So

$$\operatorname{div}(f) = \big([-1:0:1]\big) - \big([1:0:1]\big)$$

a single simple zero and a single simple pole. Hence $\deg \operatorname{div}_\infty(f) = 1$ and box 48.4.1 gives $k(C) = k(f)$.

So the abstract argument and the explicit parameterization of example 33.3.2(1) are the same map, and the genus is what guaranteed in advance that one exists.

This settles the debt left in section 47.4: the smooth model of a plane curve attaining the bound of corollary 43.2.5 has genus 0 and is therefore rational, so the extremal curves are exactly the rational ones.

Theorem 48.4.4: Genus One Curves Are Plane Cubics

Let C be a nonsingular projective curve of genus 1 and $O \in C$. Then C is isomorphic to a nonsingular plane cubic, embedded by $L(3O)$, and O maps to an inflection point.

***Proof*:**
Here $\deg K = 2g-2 = 0$ and $\ell(K) = g = 1$, so $L(K)$ contains a nonzero f with $\operatorname{div}(f) + K \geq 0$ of degree 0, hence $\operatorname{div}(f) + K = 0$ and $K \sim 0$. So for any D of positive degree, $\deg(K - D) < 0$ and theorem 48.3.2 reads

$$\ell(D) = \deg D$$

Applying this to O, $2O$ and $3O$ gives dimensions $1, 2, 3$. Choose $x \in L(2O) \setminus L(O)$ and $y \in L(3O) \setminus L(2O)$, so that x has a double pole at O and y a triple one.

Now count in $L(6O)$, of dimension 6. The seven functions

$$1,\ x,\ y,\ x^2,\ xy,\ x^3,\ y^2$$

all lie in $L(6O)$, their pole orders at O being $0, 2, 3, 4, 5, 6, 6$. Seven vectors in a six-dimensional space are dependent, and any dependence must involve both x^3 and y^2, since they are the only two with a pole of order exactly 6 and every other listed function has a distinct pole order. Normalizing their coefficients gives a relation

$$y^2 + a_1xy + a_3y = x^3 + a_2x^2 + a_4x + a_6$$

which is a plane cubic W in Weierstrass form.

The map $p \mapsto [x(p) : y(p) : 1]$, defined on $C \setminus \{O\}$ and regular everywhere by lemma 42.2.8, has image in W. It is birational onto W: the subfield $k(x, y) \subseteq k(C)$ satisfies $[k(C) : k(x)] = 2$ and $[k(C) : k(y)] = 3$ by box 48.4.1, since $\deg \operatorname{div}_\infty(x) = 2$ and $\deg \operatorname{div}_\infty(y) = 3$, so $[k(C) : k(x, y)]$ divides both 2 and 3 and is therefore 1.

Hence W is birational to C, and W is not rational: a rational W would make C birational to $\mathbb{P}^1_k$ and so isomorphic to it by lemma 42.2.8, giving C genus 0 rather than 1.

But a singular irreducible plane cubic *is* rational. If q is a singular point of such a cubic W', then $m_q(W') \geq 2$, so every line L through q has $I(q, W' \cap L) \geq 2$ by property (6) of the intersection number, and $\deg W' \deg L = 3$, so theorem 43.1.1 leaves exactly one further intersection point,

counted with multiplicity. Sending L to that point is a birational map $\mathbb{P}^1_k \dashrightarrow W'$, the lines through q forming a $\mathbb{P}^1_k$. So W is nonsingular, and a birational map between nonsingular projective curves is an isomorphism by lemma 42.2.8 applied in both directions.

Finally, homogenizing the Weierstrass equation as $y^2z+a_1xyz+a_3yz^2 = x^3+a_2x^2z+a_4xz^2+a_6z^3$ and intersecting with the line $z = 0$ leaves $x^3 = 0$, so that line meets W only at $[0 : 1 : 0]$ and with multiplicity 3. That point is the image of O, since x and y both blow up there with y of higher order. So O is an inflection point in the sense of definition 42.1.6, completing the proof.

That last sentence closes the loop with chapter 45. Lemma 45.1.2 took its simplest form when the base point was an inflection point, and the Weierstrass embedding produces one for free: any point of a genus-one curve can be made the inflection at infinity. So the classical picture, in which three collinear points on a cubic sum to zero, is available for every choice of base point after re-embedding.

48.4.5 Note: The Genus Trichotomy The three cases are governed by the sign of $\deg K = 2g - 2$.

- $g = 0$: $\deg K = -2$. The curve is $\mathbb{P}^1_k$ by theorem 48.4.2, there is exactly one such curve, and its group Pic^0 is trivial by example 44.3.2.
- $g = 1$: $\deg K = 0$. The curve is a plane cubic by theorem 48.4.4, there is a one-parameter family of them, and $\mathrm{Pic}^0(C) \cong C$ by theorem 45.2.2.
- $g \geq 2$: $\deg K = 2g - 2 > 0$. The canonical class itself embeds the curve for $g \geq 3$ non-hyperelliptic, the curves form a $(3g - 3)$-dimensional family, and Pic^0 is an abelian variety of dimension g, the Jacobian.

Only the first two rows are proved here. The third is the beginning of the theory of moduli and of abelian varieties, and it is where this book stops.

Exercise 48.4.1

1. Show that $\ell(D) = 0$ when $\deg D = 0$ and $D \not\sim 0$, and $\ell(D) = 1$ when $D \sim 0$.
2. Let C have genus g and let D be effective of degree $\deg D > 2g-2$. Show $\ell(D) = \deg D+1-g$ exactly, and deduce $\ell(K) = g$ without using theorem 48.3.2 twice.
3. Compute $\ell(nO)$ for all $n \geq 0$ on a nonsingular plane cubic, and check the answer against example 48.1.3 to see where the two curves first differ.
4. A curve of genus 2 has $\deg K = 2$ and $\ell(K) = 2$. Deduce that it admits a degree-two map to $\mathbb{P}^1_k$, so that every genus-two curve is hyperelliptic.
5. Show that a nonsingular plane quartic has genus 3 and that its canonical class is $H \cdot C$, so that the canonical map is the original embedding. Conclude that no nonsingular plane quartic is hyperelliptic.
6. Use theorem 48.4.4 to show that the group $E_k(C, O)$ of chapter 45 is defined for any nonsingular projective curve of genus 1, not just for those presented as plane cubics.

49

What Next?

This book has worked over a fixed algebraically closed field, with varieties as sets of points and rings of functions on them. That framework is what shows the subject, and every one of its limitations points at a successor theory.

Three Things This Book Could Not Say

Three separate difficulties have surfaced, and it is worth collecting them, because each is resolved by a different extension.

Multiplicity is not carried by the points. Chapter 42 had to define a plane curve as a polynomial up to scalar rather than as its zero set, precisely because $\mathcal{Z}(f)$ and $\mathcal{Z}(f^2)$ are the same set of points while the two curves ought to be different. Every intersection number in chapter 43 was then computed from the ideal, not from the set, and the book never had an object whose points and whose multiplicities were carried together.

The field is fixed and algebraically closed. The Nullstellensatz (theorem 32.4.4) is the foundation of the whole algebra-geometry dictionary, and it fails without algebraic closure. So nothing here applies to the geometry of equations over $\mathbb{Q}$ or over a finite field, and those are exactly the cases number theory treats.

Nilpotents are invisible. Chapter 32 matched varieties with *radical* ideals, discarding everything else. A family of varieties degenerating to a limit, say two points colliding or a smooth conic degenerating to a double line, has a limit whose natural equation is not radical, and the theory built here cannot see the difference between that limit and the reduced set underneath it.

Schemes

All three difficulties have one resolution: stop insisting that the geometric object be a set of points with a ring of functions on it, and let an arbitrary commutative ring define a space directly. The points of $\operatorname{Spec} R$ are the prime ideals of R, the structure sheaf is built from localizations, and the Nullstellensatz is no longer needed because the dictionary is definitional rather than a theorem.

That move recovers everything above as a special case. A variety over k becomes a scheme whose ring is a finitely generated reduced k-algebra, and dropping either adjective is what gives the three resolutions: dropping "reduced" makes $\operatorname{Spec} k[x,y]/(f^2)$ a genuinely different object from $\operatorname{Spec} k[x,y]/(f)$, and dropping "over an algebraically closed k" allows $\operatorname{Spec}\mathbb{Z}$ and its relatives. Chevalley's theorem (theorem 41.3.4) survives verbatim, the Picard group of section 44.3 becomes a functor, and Riemann-Roch becomes a statement about the cohomology of a sheaf.

This is *Algebraic Geometry* [13], which is the direct continuation of this book and the one to read next. Its prerequisite is exactly what has been developed here: the reason to endure the machinery of schemes is that one already knows what it is supposed to do.

Four Directions

Schemes are the trunk. Four branches lead off from the material of this book in particular.

The analytic theory. Over $\mathbb{C}$ a nonsingular projective curve is a compact Riemann surface, and the genus of chapter 48$\star$ is its topological genus, the number of handles. The Riemann-Roch theorem is then a statement about holomorphic differentials, proved by analysis rather than by Max Noether's theorem, and the group law of chapter 45 becomes the quotient $\mathbb{C}/\Lambda$ by a lattice. *Complex Analysis* [78] develops this. The two theories give the same answers because the analytic and algebraic categories agree for projective varieties, which is a theorem and not merely a correspondence of vocabulary.

Intersection theory. Chapter 43 counted intersections of plane curves, and section 41.4 counted lines on a cubic surface, but both counts were run by hand. The general machinery replaces the intersection cycle of section 43.3 by the Chow ring, in which classes of subvarieties multiply and the answer to an enumerative question is a coefficient. The self-intersection self-intersection $E \cdot E = -1$, which box 47.4.2 explains this book does not need but which any surface theory must give, is among its first computations. This is *Intersection Theory* [30].

Toric varieties. Sections 40.1 and 41.1 constructed embeddings by writing down monomials, and the varieties so obtained are governed entirely by the combinatorics of which monomials appear. Toric geometry makes that systematic: a fan of cones determines a variety, and its geometry (its singularities, its divisors, its cohomology) is read off the combinatorics. It is the best available source of examples that are complicated enough to be interesting and explicit enough to compute with. This is *Toric Geometry* [40].

Abelian varieties. Theorem 45.2.2 identified a cubic curve with its own Pic^0. For a curve of genus $g \geq 2$ that fails, and Pic^0 becomes a g-dimensional projective variety with a group law, the Jacobian. Abelian varieties are the projective group varieties, and they are where the group law of chapter 45 generalizes. This is *Abelian Varieties* [12]; the arithmetic of the genus-one case is *Elliptic Curves* [25].

Two Books to Read Alongside

Two external texts have been cited throughout and are worth naming as companions rather than as references.

Fulton's *Algebraic Curves* [102] is the source for chapters 42 and 43 and for the parts of chapter 48⋆ that were stated rather than proved. It is short, entirely classical, and available freely; a reader who wants the adjoint-curve proof of Riemann-Roch should go there first.

Shafarevich's *Basic Algebraic Geometry* [91] covers the varieties half of this book at greater length and with more examples, and its second volume treats schemes and complex manifolds side by side. Where this book has compressed, Shafarevich has room. Hartshorne [58] remains the standard reference for the scheme-theoretic account, but its first chapter is a compressed version of what has been done here, and it is easier read second.

50

Relating Algebra to Number Theory

A central object of study in mathematics is, naturally, the natural numbers $\mathbb{N}$ and, if the negatives are included, the integers $\mathbb{Z}$. So far, it is arguable to say that these objects have played a relatively minor algebraic role in this book: we know $\mathbb{N}$ (resp. $\mathbb{Z}$) is the initial abelian monoid (resp. ring) in their respective categories, that they are free objects, and that from $\mathbb{N}$ we may construct $\mathbb{Z}$, then $\mathbb{Q}$, and from there is any other field of characteristic 0. One aspect of $\mathbb{N}$ and $\mathbb{Z}$ we have barely touched on are their *primes* (recall the Fundamental Theorem of Arithmetic, corollary 10.1.34). There are infinitely many primes, since for any primes $p_1, \ldots, p_k$ a prime factor of $p_1 \cdots p_k + 1$ is none of them. Since $\mathbb{Z}$ is a PID, being irreducible is equivalent to being prime. However, we have explored little the nature of primes, and more generally have explored little of functions with integer solutions (elements of $f \in \mathbb{Z}[x_1, ..., x_n]$ are called *Diophantine equations*).

Unlike fields, it is in general much harder to ascertain whether an algebraic equation has solutions over the integers (or even integral extensions of the integers). Perhaps the most famous number theory problem demonstrating this difficulty is the following:

Show that for $n \geq 3$, the equation $x^n + y^n = z^n$ has no integer solutions

This problem is known as *Fermat's Last Theorem*. This is trivial if $n = 1$ (ex. $1 + 2 = 3$). It is more interesting to see the case of $n = 2$, that is we want to find all $(a, b, c) \in \mathbb{Z}^3$ ($\gcd(a, b, c) = 1$) such that $x^2 + y^2 = z^2$. Such a triple is called a *Pythagorean triple* and there are infinitely many. However, for $n \geq 3$, it is incredibly more difficult to find whether solutions exist or not, partly due to the fact that many rings that naturally arise in solving this case are *not* unique factorization domains, and partly because there turn out to be some "bad number" that make many of the number theory strategies fail. This particular problem has spurred a lot of the development of modern algebraic and analytic number theory, and shall be touched on later due to some interesting general theory

that came from it. In this section we shall cover the mathematics that build built-up in solving Diophantine equations, including some special cases of Fermat's last theorem, and prepare the reader for Class Field theory which shall definitively answer the question of factoring integer-polynomials mod primes[1].

One final intuition that shall become more evident is that the theory of prime factorization in field extensions tie into solving irreducible polynomials mod some prime ideals. This theory extends results from the classical results of solutions or lack thereof for an irreducible polynomial over $\mathbb{Q}$ when considering it mod p for all primes $p \in \mathbb{Z}$. Recall that factorization and irreducibility of monic polynomials over $\mathbb{Q}$, more generally a finite extension $K/\mathbb{Q}$ is exactly reflected to the factorization and irreducibility of monic polynomials over $\mathbb{Z}$ (which will have a ring $\mathcal{O}_K$ that shall be the equivalent[2]) by Gauss's lemma (proposition 11.2.1). This was the historical origin of number theory, as it is much easier to work with polynomials finite fields (recall proposition 11.3.8 and example 11.3.9).

Material Overview

In this chapter, we shall start by exploring when do $\mathbb{Z}$-polynomials solutions over a field k. The space of solutions shall naturally be a subset of the field k. It shall be labeled as $\mathcal{O}_K$ and called *rings of integers*, and will have many important properties to determine. Similarly to how we extended fields to find solutions to polynomials over fields, rings of integers shall be extended (in parallel to a field extension) to find more solutions. Some key functionals such as the trace, norm, and discriminant shall become important tools to find properties of elements of $\mathcal{O}_K$ and the structure of $\mathcal{O}_K$ itself. As we classify $\mathcal{O}_K$, we shall see that we may consider $\mathcal{O}_K$ as a *lattice* when embedded in $\mathbb{R}^{r_1} \oplus \mathbb{C}^{r_2}$ for appropriate $r_1, r_1 \in \mathbb{N}$. This geometric interpretation of $\mathcal{O}_K$ shall add some important new perspectives onto the elements of $\mathcal{O}_K$[3], and will allow us to define some important inequalities.

After having done a sweep over the structure of $\mathcal{O}_K$, we shall tackle some of it's algebraic structure. Namely, we shall see that they form a new type of ring called a *Dedekind domain*. Dedekind domains are very important types of rings. For those who are keen on algebraic geometry, Dedekind domains are the algebraic counter-part to 1-dimensional smooth curves (or schemes). In fact, we have seen Dedekind domains before in the previous chapter (for example, $\mathbb{Q}[x, y]/(x - y^2)$). Hence, Dedekind domains will be studied in their own right. They shall have a very rich structure: for example, many $\mathcal{O}_K$ will *not* be unique factorization domain (a fact that led to many wrong proofs of Fermat's last theorem), however we shall be able to define an abelian group structure on the ideals of $\mathcal{O}_K$ which *will* have a unique factorization (in the case where $\mathcal{O}_K$ is a PID, we shall see the ideal group I_K is isomorphic to $\mathbb{Q}^\times$, exactly mirroring the structure of Frac($\mathbb{N}$), however in general it may be much more complicated[4]). The discussion on Dedekind domains shall finish with a discussion of the unit's in Dedekind rings, which shall be important for finding the factorization of ideals.

After we realise we ought to be focusing on the *prime ideals* of $\mathcal{O}_K$ rather than the irreducible elements of $\mathcal{O}_K$ (for they are not necessarily prime), we shall start exploring how prime may further decompose as we extend to larger rings of integers. This helps in finding solutions to $\mathbb{Z}$-polynomials for the prime ideals in larger rings will have very rigid structure that can be taken advantage of. We have already seen this before: It shall turn out that $\mathcal{O}_{\mathbb{Q}(i)} = \mathbb{Z}[i]$ (the Gaussian integers). In the

[1] In particular, the *Artin Reciprocity Law* shall give the over-arching result showing how to factorize Diophantine equations

[2] See definition 50.1.3

[3] and of the norm

[4] which is measured by the *class group*, as we shall see

Gaussian integers, we saw that 2 is not prime, for

$$2 = (1+i)(1-i) = 1^2 - i^2 = 1 + 1$$

or in terms of ideals, we shall have $(2) = (1+i)(1-i)$. Hence, 2 has further factored into new primes. In section 10.3, this was used to prove Fermat's Theorem for sums of squares. More generally, we shall see that any prime ideal $\mathfrak{p} \subseteq \mathcal{O}_K$ may factor:

$$\mathfrak{p}\mathcal{O}_L = \mathfrak{B}_1^{e_1} \cdots \mathfrak{B}_k^{e_k} \tag{50.1}$$

Though it may currently seem unrelated, the study of the factorization of primes *almost* mirrors that of the factorization of irreducible polynomials mod $\mathfrak{p}$ after extending fields. In fact, it shall turn out to be the case that *all but finitely many primes* shall factor exactly like how a polynomial factors, the "bad primes" essentially being primes for which an exponent in equation (50.1) is greater than 1, ≥ 2. This sort of exploration leads to a lot of very interesting theory that have applications beyond classical number theory, for example we shall be able to fully classify all abelian extensions of $\mathbb{Q}$.

For those who get motivation through algebraic geometry, algebraic number theory naturally ties into it. It may help to think of the main object of study of this chapter (rings of integers) as further expanding the dictionary between commutative algebra and geometry, namely they shall be important for *normal schemes* which links to the notion of a smooth curve[5]

At the end of this chapter, we shall briefly touch on some analytic number theory, for it's study is central to modern number theory and the author of this books considers that anyone that has reached this stage of the book would find it enlightening to see how the Riemann-zeta function play an important role in number theory.

50.0.1 Warning Some elementary analysis will be assumed in this section, including some properties of the real numbers.

50.1 Ring of Integers

In this chapter, whenever the notation $L/K/\mathbb{Q}$ is used for some letter's L, K, it is implied that L/K are both finite extensions of $\mathbb{Q}$, and L is an extension of K. Unless otherwise specified, the characteristic of any field is implicitly assumed to be 0. We start by defining our terms.

Definition 50.1.1: Algebraic Number Fields

Let K be a field. If $K/\mathbb{Q}$ is a finite extension of $\mathbb{Q}$, then K is called an *algebraic number field* or *number field* if unambiguous.

Example 50.1.2: Number Fields

1. Let $\zeta_n = e^{2\pi i/n}$ be a root of unity. Then $\mathbb{Q}(\zeta_n)$ is a number field, called the *Cyclotomic field*.
2. Let $m \in \mathbb{Z}$ be not-a-square. Then Fields of the form $\mathbb{Q}(\sqrt{m})$ is called a *quadratic field*. Such fields always have degree 2. Notice that we can consider any $m \in \mathbb{Z}$, however we get many

[5] See a textbook in algebraic geometry for further details

equality of fields, for example $\mathbb{Q}(\sqrt{12}) = \mathbb{Q}(\sqrt{3})$. The field $\mathbb{Q}(i)$ is both a quadratic field and a Cyclotomic field since $i = \zeta_4$. As an exercise, show that $\mathbb{Q}(\sqrt{-3})$ is a Cyclotomic field.

3. The field $\mathbb{Q}(\sqrt{n}, \sqrt{m})$ is called a *biquadratic* field where n, m are both not-a-square.
4. The field $\mathbb{R}$ and $\mathbb{C}$ are *not* algebraic number fields, are they are not algebraic extensions of $\mathbb{Q}$ (they both contain transcendental elements).
5. Similarly, $k(x)$ for any field k is not an algebraic number field (it is an [algebraic] function field). However, in many ways this field is very similar to algebraic number fields, and shall be given some more attention in section 50.2.

Of key interest to this chapter the study of integer polynomials with solutions fields:

Definition 50.1.3: Ring of Integers (of Number Fields)

Let K be a field of characteristic 0 and identify $\mathbb{Z} \subseteq K$ via the (unique) map $\mathbb{Z} \hookrightarrow K$. Then the *ring of integers* of K is the integral closure of $\mathbb{Z}$ over K (definition 26.1.3):

$$\mathcal{O}_K := \overline{\mathbb{Z}}^K = \{a \in K \mid f(a) = 0 \text{ for some monic } f(x) \in \mathbb{Z}[x]\}$$

As all fields in consideration shall be number fields $K/\mathbb{Q}$, there is already $\mathbb{Z} \subseteq K$ identified. The generality in the definition is to show that the ring of integers is defined over any field of characteristic 0. Note that there is an equivalent definition for fields of positive characteristic, however as $\text{im}(\mathbb{Z}) \cong \mathbb{Z}/p\mathbb{Z}$ any integral closure of $\mathbb{Z}/p\mathbb{Z}$, $\overline{\mathbb{Z}/p\mathbb{Z}}^K$, is a field extension by proposition 26.1.8 and so there is no notion of prime ideals which essentially erases the key extra information that is studied. Instead, $\mathbb{F}_p[t]$ becomes the new $\mathbb{Z}$ and a parallel theory of finite extension $K/\mathbb{F}_p(t)$ is studied. These are called *algebraic function fields* and the corresponding $\overline{\mathbb{F}_p[t]}^K$ is the *ring of integers of function fields*.. The two theories have many parallels, but exploring these is beyond the scope of this book, see [77] for more details.

Although, once this chapter becomes it's own book, it may be a good idea to dedicate a section or chapter to this.

By corollary 26.1.6, $\mathcal{O}_K \subseteq K$ is a ring. Since we will often work over $\mathbb{Z}$, it is useful to know that instead of taking all roots of polynomials, it is equivalent to take all the roots of *irreducible polynomials*. By using Gauss's lemma, if $f = gh$, $f \in \mathbb{Z}[x]$ and $g, h \in \mathbb{Q}[x]$, then in fact $g, h \in \mathbb{Z}[x]$. Hence, the smallest degree polynomial for which α is a root will be irreducible. An important ring of integer that is worth isolating is the following:

Definition 50.1.4: Algebraic Integers [of Number Fields]

The collection of elements

$$\mathcal{O}_{\overline{\mathbb{Q}}} = \mathcal{O}_{\mathbb{C}} := \overline{\mathbb{Z}}^{\mathbb{C}}$$

are called the *algebraic integers*, and is sometimes denoted $\mathbb{A}$[a].

[a] this notation comes from the theory of *idele rings* that is an important tool in class field theory, see [77]

Just like for fields, there may be multiple "integral closures", and they are all isomorphic which motivates saying they are *the* algebraic integers.

Lemma 50.1.5: Equivalence Definition

Let $K/\mathbb{Q}$ be a finite extension and let $\mathcal{O}_{\mathbb{C}}$ be the algebraic integers. Then:

$$\mathcal{O}_{\mathbb{C}} \cap K = \mathcal{O}_K$$

***Proof*:**
The statement identifies K with a subfield of $\mathbb{C}$. By definition 50.1.3 and definition 50.1.4, both $\mathcal{O}_K$ and $\mathcal{O}_{\mathbb{C}}$ consist of the roots, in K and in $\mathbb{C}$ respectively, of monic polynomials in $\mathbb{Z}[x]$. The defining condition mentions only the element and $\mathbb{Z}[x]$, never the ambient field. Hence if $a \in \mathcal{O}_K$, then a is a root of a monic polynomial in $\mathbb{Z}[x]$ and $a \in K \subseteq \mathbb{C}$, so $a \in \mathcal{O}_{\mathbb{C}} \cap K$. Conversely, if $a \in \mathcal{O}_{\mathbb{C}} \cap K$, then $a \in K$ and a is a root of a monic polynomial in $\mathbb{Z}[x]$, so $a \in \mathcal{O}_K$.

Example 50.1.6: Ring of Integers

1. $\mathcal{O}_{\mathbb{Q}} = \mathbb{Z}$. For this reason, the integers in algebraic number theory are sometimes called the rational integers

2. $\mathcal{O}_{\mathbb{Q}(i)} = \mathbb{Z}[i]$. To see this, let $\alpha = a + bi$, $a, b \in \mathbb{Q}$. Then for $\alpha \in \mathcal{O}_{\mathbb{Q}(i)}$, we need to show that the minimal polynomial of α:

   $$\alpha^2 - 2a\alpha + (a^2 + b^2) = 0$$

   has integer coefficients, that is $-2a$ and $a^2 + b^2$ are integers. First, if $c, d \in \mathbb{Z}$, $c + di \in \mathcal{O}_{\mathbb{Q}(i)}$. Since $\mathcal{O}_{\mathbb{Q}(i)}$ is a ring, if $a + bi \in \mathcal{O}_{\mathbb{Q}(i)}$, then so is $a + bi - c - di = a' + b'i$ for $c, d \in \mathbb{Z}$ where $a', b' \leq 1$. But then from $(a')^2 + (b')^2 = k \in \mathbb{Z}$, we get $a', b' \in \{-1, 0, 1\}$. Then that implies $a, b \in \mathbb{Z}$, showing that $\mathcal{O}_{\mathbb{Q}(i)} = \mathbb{Z}[i]$.

3. In general, it is difficult to find the ring of integers. The difficulty of finding the ring of integers can even show up for quadratic extensions. Consider $F = \mathbb{Q}(\sqrt{-3})$. Then we might be tempted to say that $\mathcal{O}_F = \mathbb{Z}[\sqrt{-3}]$. However, this is not the case, take:

   $$\omega = \frac{-1 + \sqrt{-3}}{2} \in \mathbb{Q}(\sqrt{-3})$$

   Then $\omega^2 + \omega + 1 = 0$, however $\omega \notin \mathbb{Z}[\sqrt{-3}]$.

4. In general, more tools are needed to find $\mathcal{O}_k$, but in the quadratic case the polynomials are simple enough to find all rings of integers. Let $k = \mathbb{Q}(\sqrt{m})$ with $m \neq 0, 1$ square-free. Then:

   $$\mathcal{O}_k = \mathbb{Z}[\sqrt{m}] \qquad m \equiv 2, 3 \bmod 4$$
   $$\mathcal{O}_k = \mathbb{Z}\left[\frac{1 + \sqrt{m}}{2}\right] \qquad m \equiv 1 \bmod 4$$

   The computation uses the trace and norm of $r + s\sqrt{m}$, and is carried out in example 50.1.17 once these are available.

The ring of integers $\mathcal{O}_K/\mathbb{Z}$ hold the core information of $K/\mathbb{Q}$. In particular, if $\mathbf{Fld}_0^{\text{fin}}$ is the category

whose objects are finite extensions of $\mathbb{Q}$ and morphisms are field morphisms and $\mathbf{AlgInt}_0^{\text{fin}}$ is the category whose objects are the rings of integers $\mathcal{O}_K$ of finite extensions $K/\mathbb{Q}$ and whose morphisms are ring homomorphisms, these two categories are *equivalent*, and the theorem below proves it.

First, if $\varphi : F \to L$ be a field homomorphism (not necessarily a k-homomorphism), then $\varphi|_{\mathcal{O}_F} : \mathcal{O}_F \to \mathcal{O}_L$ is certainly well defined since if $\alpha \in \mathcal{O}_F$, then:

$$a_0 + a_1\alpha + \cdots + a_{n-1}\alpha^{n-1} + \alpha^n = 0 \qquad a_i \in \mathbb{Z}$$

Then $\varphi(a_i\alpha^i) = a_i\varphi(\alpha)^i$, since $a_i \in \mathbb{Z}$. Hence $\varphi(\alpha) \in \mathcal{O}_L$. From this, define $\mathcal{O}_- : \mathbf{Fld}_0^{\text{fin}} \to \mathbf{AlgInt}_0^{\text{fin}}$ which gives the commutative diagram:

$$\begin{array}{ccc} F & \xhookrightarrow{\varphi} & L \\ \downarrow{\scriptstyle \mathcal{O}_-} & & \downarrow{\scriptstyle \mathcal{O}_-} \\ \mathcal{O}_F & \xrightarrow{\varphi|_{\mathcal{O}_F}} & \mathcal{O}_L \end{array}$$

Now given a map $\psi : \mathcal{O}_F \to \mathcal{O}_K$, can we find a map $\Psi : F \to K$ which is furthermore an inverse to the above functor? Yes. To find this functor, we first find how to retrieve the field from the ring of integers:

Proposition 50.1.7: Field of Fraction of Integral Closures of Extensions

Let R be an integral domain, $K = K(R)$ its field of fraction, and $S = \overline{R}^L$ where L/K is an algebraic extension. Then for every $\alpha \in L$ there is a nonzero $d \in R$ with $d\alpha \in S$. Consequently $L = K(S)$. Equivalently, $L = \langle S \rangle_{K(R)}$.

If $R = \mathbb{Z}$ and $K(R) = \mathbb{Q}$ so that $S = \overline{\mathbb{Z}}^L = \mathcal{O}_L$, then $L = K(\mathcal{O}_L)$.

***Proof*:**
Let R, K, S and L be defined as in the question. We shall first show that if $\alpha \in L$ is algebraic over K, then there exists a $d \in R$ such that $d\alpha$ is integral over R. Since α is algebraic over K,

$$\alpha^m + a_1\alpha^{m-1} + \cdots + a_m = 0 \qquad a_i \in K$$

Let $d \neq 0$ be the product of denominators of the a_i, so that $da_i \in R$ for all i. Then multiplying the above equation by d^m, we get:

$$d^m\alpha^m + d^m a_1\alpha^{m-1} + \cdots + d^m a_m = 0 \qquad a_i \in K$$

re-writing:

$$(d\alpha)^m + da_1(d\alpha)^{m-1} + \cdots + d^m a_m = 0 \qquad a_i \in K$$

where each $a_i d, ..., a_m d^m \in R$, hence $d\alpha$ is integral over R. Note that this immediately gives the equivalence $L = \langle S \rangle_{K(S)}$.

With that, to see that $L = K(S)$, notice that every $\alpha \in L$ can be written as $\alpha = b/d$ for $d \in R$, hence $L \subseteq K(S)$. Conversely, if $a/b \in K(S)$, where $a, b \in S$ and each satisfy an R-polynomial, then they are certainly satisfy a K-polynomial, and furthermore S is all elements of L that satisfy an R-polynomial, hence $a/b \in L$, giving equality.

Corollary 50.1.8: Basis For Number Field

Let $F/\mathbb{Q}$ be a finite extension of degree n and $(\alpha_1, \alpha_2, ..., \alpha_n)$ an $\mathbb{Q}$-basis for F. Then there exists an $m_i \in \mathbb{Z}$ such that $m_1\alpha_1, m_2\alpha_2, ..., m_n\alpha_n \in \mathcal{O}_F$

***Proof*:**
let $R = \mathbb{Z}$ in proposition 50.1.7.

Theorem 50.1.9: Equivalent Categories: Fields and Rings of Integers

Let $K/\mathbb{Q}$ be a number field and $\mathcal{O}_K$ the ring of integers of K. Then:

1. If L/K, then $\mathcal{O}_L \cap K = \mathcal{O}_K$. In particular $\mathcal{O}_K \cap \mathbb{Q} = \mathbb{Z}$.
2. $\mathcal{O}_K \otimes_{\mathbb{Z}} \mathbb{Q} \cong K$, by $\beta \otimes q \mapsto q\beta$.
3. For number fields F and L, restriction $\varphi \mapsto \varphi|_{\mathcal{O}_F}$ is a bijection from the field homomorphisms $F \to L$ to the ring homomorphisms $\mathcal{O}_F \to \mathcal{O}_L$.
4. For subfields K, K' of a number field L, $\mathcal{O}_{K\cap K'} = \mathcal{O}_K \cap \mathcal{O}_{K'}$.

Hence $F \mapsto \mathcal{O}_F$, $\varphi \mapsto \varphi|_{\mathcal{O}_F}$ is an equivalence of categories $\mathbf{Fld}_0^{\text{fin}} \to \mathbf{AlgInt}_0^{\text{fin}}$ (definition 18.2.2), with quasi-inverse $(-) \otimes_{\mathbb{Z}} \mathbb{Q}$.

***Proof*:**
Step 1: proof of (1). An element of $\mathcal{O}_L \cap K$ is an element of K that is a root of a monic polynomial in $\mathbb{Z}[x]$, which is the defining property of $\mathcal{O}_K$ (definition 50.1.3), so $\mathcal{O}_L \cap K = \mathcal{O}_K$. Taking $K = \mathbb{Q}$ and $L = K$ gives $\mathcal{O}_K \cap \mathbb{Q} = \mathcal{O}_{\mathbb{Q}}$. Each $a \in \mathbb{Z}$ is a root of $x - a$, so $\mathbb{Z} \subseteq \mathcal{O}_{\mathbb{Q}}$. Conversely, an element of $\mathcal{O}_{\mathbb{Q}}$ is a rational number integral over $\mathbb{Z}$. The ring $\mathbb{Z}$ is a UFD (corollary 10.1.34), hence integrally closed in its fraction field $\mathbb{Q}$ (corollary 29.9.6), so the element lies in $\mathbb{Z}$. Hence $\mathcal{O}_K \cap \mathbb{Q} = \mathbb{Z}$.

Step 2: proof of (2). With $D = \mathbb{Z} \setminus \{0\}$, proposition 23.4.10 gives $\mathcal{O}_K[D^{-1}] \cong D^{-1}\mathbb{Z} \otimes_{\mathbb{Z}} \mathcal{O}_K = \mathbb{Q} \otimes_{\mathbb{Z}} \mathcal{O}_K$. As $\mathcal{O}_K \subseteq K$ has no nonzero element killed by a nonzero integer, its localization is the subring $\{\beta/d \mid \beta \in \mathcal{O}_K, d \in D\}$ of K, and this is all of K because every $\alpha \in K$ has $d\alpha \in \mathcal{O}_K$ for some $d \in D$ (proposition 50.1.7 with $R = \mathbb{Z}$). Composing gives $\beta \otimes q \mapsto q\beta$.

Step 3: proof of (3). A field homomorphism $\varphi\colon F \to L$ fixes $\mathbb{Z}$, so it carries a monic integer equation of $\alpha \in \mathcal{O}_F$ to one of $\varphi(\alpha)$, and $\varphi(\mathcal{O}_F) \subseteq \mathcal{O}_L$. Restriction is injective: if $\varphi|_{\mathcal{O}_F} = \varphi'|_{\mathcal{O}_F}$ and $\alpha \in F$, choose $0 \neq d \in \mathbb{Z}$ with $d\alpha \in \mathcal{O}_F$ (proposition 50.1.7). Then $d\varphi(\alpha) = \varphi(d\alpha) = \varphi'(d\alpha) = d\varphi'(\alpha)$. For surjectivity, let $\psi\colon \mathcal{O}_F \to \mathcal{O}_L$ be a ring homomorphism, so $\psi(n) = n$ for $n \in \mathbb{Z}$. Let $0 \neq \beta \in \mathcal{O}_F$ and let $x^m + a_{m-1}x^{m-1} + \cdots + a_0 \in \mathbb{Z}[x]$ be monic of least degree with root β. Then $a_0 \neq 0$, since otherwise dividing by x gives a smaller degree, and $a_0 = -\beta\gamma$ with $\gamma = \beta^{m-1} + \cdots + a_1 \in \mathcal{O}_F$ (corollary 26.1.6). So $a_0 = \psi(a_0) = -\psi(\beta)\psi(\gamma)$ is nonzero in L, and $\psi(\beta) \neq 0$. Thus ψ sends $\mathcal{O}_F \setminus \{0\}$ into $L^\times$, and as F is the fraction field of $\mathcal{O}_F$ (proposition 50.1.7), theorem 23.4.1 extends ψ to a ring homomorphism $\Psi\colon F \to L$ with $\Psi|_{\mathcal{O}_F} = \psi$.

Step 4: proof of (4). By (1) applied to $L/K \cap K'$, L/K and L/K', $\mathcal{O}_{K\cap K'} = \mathcal{O}_L \cap K \cap K' = (\mathcal{O}_L \cap K) \cap (\mathcal{O}_L \cap K') = \mathcal{O}_K \cap \mathcal{O}_{K'}$.

Step 5: the equivalence. By (3), $\mathcal{O}_{(-)}$ is a functor, and so is $G = (-) \otimes_{\mathbb{Z}} \mathbb{Q}$, with $G(\psi) = \psi \otimes \mathrm{id}_{\mathbb{Q}}$. The isomorphisms $\epsilon_F \colon \mathcal{O}_F \otimes_{\mathbb{Z}} \mathbb{Q} \to F$ of (2) are natural: for $\varphi \colon F \to L$, both $\varphi \circ \epsilon_F$ and $\epsilon_L \circ (\varphi|_{\mathcal{O}_F} \otimes \mathrm{id}_{\mathbb{Q}})$ send $\beta \otimes q$ to $q\varphi(\beta)$. So $G \circ \mathcal{O}_{(-)} \cong \mathrm{id}$. For an object $B = \mathcal{O}_F$, the field isomorphism ϵ_F restricts by Step 3 to a ring isomorphism $\mathcal{O}_{G(B)} \to \mathcal{O}_F = B$, natural in B by the naturality of ϵ, so $\mathcal{O}_{(-)} \circ G \cong \mathrm{id}$, completing the proof.

Note that finiteness is important: it shall be shown that $\mathcal{O}_K$ for $K/\mathbb{Q}$ a finite extension is a domain with factorization (or atomic domain, recall definition 10.1.9), however $\mathcal{O}_{\mathbb{C}}$ is *not* an atomic domain as shown in example 10.1.8 which is certainly desirable as we are generalizing the factorization of primes.

This shows how to relate $\mathcal{O}_K$ with K and a bit about how to move down the lattice, but we have not said much about the structure of $\mathcal{O}_K$. We know it is a ring, but is it a PID? A UFD? Every ring is a $\mathbb{Z}$-module; it is a finitely generated $\mathbb{Z}$-module? Noetherian $\mathbb{Z}$-module? Projective? The strategy in example 50.1.6 to find the structure of $\mathcal{O}_K$ gets much harder for more complicated roots of irreducible, even once we have degree 3, and especially beyond degree 4. Our first goal is to establish the structure of $\mathcal{O}_K$. To find the structure, we will require some tools for detecting elements of $\mathcal{O}_K$: we shall find numerical values for the elements of K to determine whether they are elements of $\mathcal{O}_K$, i.e. we shall find functionals. We shall see that $\mathcal{O}_K$ will be a free $\mathbb{Z}$-module of finite rank, in fact it shall be a particular $\mathbb{Z}$-module known as a *complete* lattice, as shall be demonstrated in section 50.1.4.

50.1.1 Functionals: Field Trace and Field Norms

(this link is useful: here)

Let M/k be a finite extension, and take $\alpha \in M$. We shall define two invariances on α that will detect whether α is algebraic over k or not, detect when it is an algebraic integer, and eventually help us find the structure of $\mathcal{O}_M$ as well as the factorization of elements of $\mathcal{O}_M$.

Define $L_\alpha : M \to M$ by $m \mapsto \alpha m$. This is a k-linear transformation, since:

$$L_\alpha(a + kb) = \alpha(a + kb) = \alpha a + k\alpha b = L_\alpha(a) + kL_\alpha(b)$$

Thus, we can represent this linear transformation in a matrix form (usually with basis given by α). Since the trace and determinant are basis independent calculations, it is meaningful to ponder what the trace/determinant of this transformation and what information it may provide us:

Definition 50.1.10: Trace And Norm

Let M/k be a finite extension, $L_\alpha : M \to M$ be a linear transformation defined by multiplication Then we call the trace of this linear transformation the *trace* of α and the determinant of this linear transformation the *norm* of α.

Example 50.1.11: Trace And Norm

1. Let $\mathbb{C}/\mathbb{R}$ be the extension and $\alpha = x + iy$. Pick basis $\{1, i\}$. Then multiplication is:

$$\begin{pmatrix} x & y \\ -y & x \end{pmatrix}$$

and so the trace is $2x = 2\text{Re}\alpha$ and the norm is $x^2 + y^2 = \|\alpha\|^2$. If you know some complex analysis, then we see that the norm does indeed match with our usual understanding of the norm, and the trace can be thought of as a generalization of taking the real part of the complex number (up to a factor).

2. Let $\alpha = a + b \cdot \left(\frac{1+\sqrt{-7}}{2}\right) \in \mathbb{Z}\left[\frac{1+\sqrt{-7}}{2}\right]$. Then:

$$\text{Nm}_{\mathbb{Q}(\sqrt{-7})/\mathbb{Q}}(\alpha) = a^2 + ab + 2b^2$$

3. Let M/k be a finite extension and $\alpha \in M$, with $d = [k(\alpha) : k]$ and $s = [M : k(\alpha)]$, and let

$$m_{\alpha,k}(x) = x^d + a_{d-1}x^{d-1} + \cdots + a_1 x + a_0$$

be the minimal polynomial. If $M = k(\alpha)$, it equals the characteristic polynomial χ of L_α: by proposition 14.3.10 $\chi(L_\alpha) = 0$, applying this map to 1 gives $\chi(\alpha) = 0$, so $m_{\alpha,k}$ divides χ, and both are monic of degree d. Then proposition 13.5.2 shows that the trace of α is $-a_{d-1}$ and the norm is $(-1)^d a_0$. In general, a basis $\beta_1, \ldots, \beta_s$ of M over $k(\alpha)$ splits $M = \bigoplus_j k(\alpha)\beta_j$ into s subspaces stable under L_α, on each of which L_α acts as on $k(\alpha)$. So the matrix of L_α is block diagonal with s equal blocks, $\chi = m_{\alpha,k}^s$ by proposition 13.4.8, and

$$\text{tr}_{M/k}(\alpha) = -sa_{d-1} \qquad \text{Nm}_{M/k}(\alpha) = \left((-1)^d a_0\right)^s$$

Naturally, if F/k, $a_1, a_2 \in F$ and $b \in k$:

$$\text{tr}_{F/k}(a_1 + a_2) = \text{tr}_{F/k}(a_1) + \text{tr}_{F/k}(a_2) \quad \text{tr}_{F/k}(ba_1) = b\text{tr}_{F/k}(a_1) \quad \text{tr}_{F/k}(a) = na$$

and:

$$\text{Nm}_{F/k}(a_1a_2) = \text{Nm}_{F/k}(a_1)\text{Nm}_{F/k}(a_2) \quad \text{Nm}_{F/k}(ba_1) = b^n\text{Nm}_{F/k}(a_1) \quad \text{Nm}_{F/k}(b) = b^n$$

Most of the properties of the trace and norm come from linear algebra, and furthermore since every finite separable extension has a primitive element generating the entire field, the norm and trace always show up in the minimal polynomial. In section 20.2.3, we saw another way of characterizing the trace and norm, which will be emphasized here due to its importance:

Proposition 50.1.12: Trace and Norm via Galois Conjugates

Let M/k be a finite extension where $[M:k]=n$ and let $\alpha \in M$ be algebraic over k. Then, listing each root of $m_{\alpha,k}$ in $\overline{k}$ as often as its multiplicity:

$$\mathrm{tr}_{M/k}(\alpha) = [M:k(\alpha)] \cdot \sum_{\substack{r \\ \text{root of } m_{\alpha,k}}} r \qquad \mathrm{Nm}_{M/k}(\alpha) = \left(\prod_{\substack{r \\ \text{root of } m_{\alpha,k}}} r \right)^{[M:k(\alpha)]}$$

***Proof*:**

Let $d=[k(\alpha):k]$, $s=[M:k(\alpha)]$ and $m_{\alpha,k}(x)=x^d+a_{d-1}x^{d-1}+\cdots+a_1x+a_0$. Over $\overline{k}$ write $m_{\alpha,k}(x)=\prod_{j=1}^{d}(x-r_j)$, each root repeated according to its multiplicity. Expanding the product and comparing coefficients gives

$$a_{d-1} = -\sum_{j=1}^{d} r_j \qquad a_0 = (-1)^d \prod_{j=1}^{d} r_j$$

Step 1: the case $M=k(\alpha)$. The elements $1,\alpha,\ldots,\alpha^{d-1}$ form a k-basis of $k(\alpha)$. Multiplication by α sends α^i to α^{i+1} for $i<d-1$, and sends α^{d-1} to $\alpha^d=-a_0-a_1\alpha-\cdots-a_{d-1}\alpha^{d-1}$. So its matrix in this basis is the companion matrix C of $m_{\alpha,k}$ (definition 14.3.2): 1's on the subdiagonal, last column $(-a_0,\ldots,-a_{d-1})^t$, zeros elsewhere. Its diagonal entries are 0 except the last one, $-a_{d-1}$, so $\mathrm{tr}(C)=-a_{d-1}$. In the expansion of $\det(C)$ (definition 13.4.5), every permutation other than the one sending row 1 to column d and row i to column $i-1$ for $i\geq 2$ has a factor equal to 0. That permutation is a d-cycle, of sign $(-1)^{d-1}$, so $\det(C)=(-1)^{d-1}(-a_0)=(-1)^d a_0$. By definition 50.1.10 and the display above,

$$\mathrm{tr}_{k(\alpha)/k}(\alpha) = \sum_{j=1}^{d} r_j \qquad \mathrm{Nm}_{k(\alpha)/k}(\alpha) = \prod_{j=1}^{d} r_j$$

Step 2: the general case. Let $\beta_1,\ldots,\beta_s$ be a $k(\alpha)$-basis of M. The ds elements $\alpha^i\beta_j$, for $0\leq i<d$ and $1\leq j\leq s$, span M over k, because each coefficient in $k(\alpha)$ is a k-combination of $1,\alpha,\ldots,\alpha^{d-1}$. Since $ds=[M:k]$ (theorem 19.3.7), they form a k-basis. For each j, multiplication by α maps the span of $\beta_j,\alpha\beta_j,\ldots,\alpha^{d-1}\beta_j$ into itself and acts on it by the matrix C of Step 1. Ordering the basis by j, the matrix of multiplication by α on M is block diagonal with s blocks equal to C. Hence $\mathrm{tr}_{M/k}(\alpha)=s\,\mathrm{tr}(C)$, and $\mathrm{Nm}_{M/k}(\alpha)=\det(C)^s$ by proposition 13.4.8. With Step 1 this gives the two formulas of the statement. No separability was used. Under the standing convention of chapter 50 that fields have characteristic 0, the irreducible polynomial $m_{\alpha,k}$ is separable (corollary 19.6.8), so its roots are distinct and each is listed once, as we sought to show.

Corollary 50.1.13: Trace and Norm Via Embeddings

Let L/k be a separable extension of degree n, an $\sigma_1, \sigma_2, ..., \sigma_n$ the embedding of L into it's Galois closure or $\overline{k}$. Then for $\alpha \in L$:

$$\mathrm{tr}_{L/k}(\alpha) = \sum_i^n \sigma_i(\alpha) \qquad \mathrm{Nm}_{L/k}(\alpha) = \prod_i^n \sigma_i(\alpha)$$

***Proof*:**

Fix an algebraic closure $\overline{k}$ of k containing L: an algebraically closed field containing L exists by lemma 19.5.5 and the chain construction before it, and its elements algebraic over k form such an algebraic closure by theorem 19.5.6. Fix the Galois closure of L/k inside $\overline{k}$. A k-embedding $L \to \overline{k}$ sends each $\beta \in L$ to a root of the minimal polynomial of β over k, which splits in the Galois closure, so the k-embeddings of L into the Galois closure and into $\overline{k}$ are the same maps. There are n of them by definition 19.6.13 and proposition 19.6.17, since L/k is separable.

Let $\alpha \in L$, $d = [k(\alpha) : k]$ and $s = [L : k(\alpha)]$. The polynomial $m_{\alpha,k}$ is separable, as L/k is, so it has d distinct roots $r_1, \ldots, r_d$ in $\overline{k}$, and by proposition 19.6.15 the k-embeddings of $k(\alpha)$ into $\overline{k}$ are the maps $\rho_1, \ldots, \rho_d$ with $\rho_j(\alpha) = r_j$. Fix j, and regard $\overline{k}$ as an extension of $k(\alpha)$ through ρ_j. It is then an algebraic closure of $k(\alpha)$, and the k-embeddings $L \to \overline{k}$ restricting to ρ_j are exactly the $k(\alpha)$-embeddings of L into it. By definition 19.6.13, whose count does not depend on the algebraic closure, there are $[L : k(\alpha)]_s$ of them. The extension $L/k(\alpha)$ is separable (proposition 19.6.18), so $[L : k(\alpha)]_s = s$ by proposition 19.6.17. Each σ_i restricts to exactly one ρ_j, so the list $\sigma_1(\alpha), \ldots, \sigma_n(\alpha)$ consists of each r_j repeated s times, and

$$\sum_{i=1}^n \sigma_i(\alpha) = s\sum_{j=1}^d r_j \qquad \prod_{i=1}^n \sigma_i(\alpha) = \left(\prod_{j=1}^d r_j\right)^s$$

By proposition 50.1.12, the right-hand sides are $\mathrm{tr}_{L/k}(\alpha)$ and $\mathrm{Nm}_{L/k}(\alpha)$, as claimed.

In the notation of example 50.1.11(3), $\mathrm{tr}_{M/k}(\alpha) = -sa_{d-1}$ and $\mathrm{Nm}_{M/k}(\alpha) = ((-1)^d a_0)^s$, so both lie in k. If $\alpha \neq 0$, then $a_0 \neq 0$: a minimal polynomial with constant term 0 is divisible by x, so being irreducible it equals x, which forces $\alpha = 0$. Hence $\mathrm{Nm}_{M/k}(\alpha) \neq 0$ for $\alpha \neq 0$. The trace and norm also give a first test for whether $\alpha \in M$ belongs to $\mathcal{O}_M$. For $k = \mathbb{Q}$, integrality forces $\mathrm{tr}_{M/\mathbb{Q}}(\alpha), \mathrm{Nm}_{M/\mathbb{Q}}(\alpha) \in \mathbb{Z}$, and the same holds over any integrally closed base, which matters for intermediate extensions:

Corollary 50.1.14: Trace and Norm on Rings of Integers

Let R be an integral domain that is integrally closed in its field of fractions $K(R)$, and let $F/K(R)$ be a finite field extension. Then if $\alpha \in F$ is integral over R,

$$\mathrm{tr}_{F/K(R)}(\alpha) \in R \qquad \mathrm{Nm}_{F/K(R)}(\alpha) \in R$$

In particular, $\mathrm{tr}_{L/k}(\mathcal{O}_L) \subseteq \mathcal{O}_k$ and $\mathrm{Nm}_{L/k}(\mathcal{O}_L) \subseteq \mathcal{O}_k$ for every finite extension L/k of number fields.

***Proof*:**
Step 1: the roots of the minimal polynomial are integral. Put $K = K(R)$, let $f \in R[x]$ be monic with $f(\alpha) = 0$, and let $m_{\alpha,K}(x) = x^d + a_{d-1}x^{d-1} + \cdots + a_0$. Since $m_{\alpha,K}$ divides f in $K[x]$, every root r of $m_{\alpha,K}$ in the algebraic closure $\overline{K}$ of proposition 50.1.12 satisfies $f(r) = 0$, so r is integral over R.

Step 2: trace and norm. List the roots of $m_{\alpha,K}$ as $r_1, \ldots, r_d$, with multiplicity, and put $s = [F : K(\alpha)]$. By proposition 50.1.12, $\mathrm{tr}_{F/K}(\alpha) = s\sum_j r_j$ and $\mathrm{Nm}_{F/K}(\alpha) = (\prod_j r_j)^s$. Sums and products of elements of $\overline{K}$ integral over R are integral over R (corollary 26.1.6), so both values are integral over R. Comparing coefficients in $m_{\alpha,K} = \prod_j (x - r_j)$ gives $\sum_j r_j = -a_{d-1}$ and $\prod_j r_j = (-1)^d a_0$, so both values lie in K. As R is integrally closed in K, both lie in R.

Step 3: number fields. Let L/k be a finite extension of number fields and take $R = \mathcal{O}_k$. Its field of fractions is k (proposition 50.1.7 with $R = \mathbb{Z}$). It is integrally closed in k: if $x \in k$ is integral over $\mathcal{O}_k$, then every element of $\mathcal{O}_k[x]$ is integral over $\mathcal{O}_k$ (corollary 26.1.6), and $\mathcal{O}_k$ is integral over $\mathbb{Z}$, so x is integral over $\mathbb{Z}$ (corollary 26.1.5) and $x \in \mathcal{O}_k$ by definition 50.1.3. Every $\alpha \in \mathcal{O}_L$ is integral over $\mathbb{Z} \subseteq \mathcal{O}_k$, so Step 2 with $F = L$ gives $\mathrm{tr}_{L/k}(\alpha), \mathrm{Nm}_{L/k}(\alpha) \in \mathcal{O}_k$, completing the proof.

If $R = \mathbb{Z}$ and $F/\mathbb{Q}$ is a finite extension, the trace and norm thus give a necessary condition for integrality. Since we may be working with intermediate fields $M/L/k$, it is useful to know how to compute the trace and norm given information about the trace and norm of the intermediate fields:

Proposition 50.1.15: Trace and Norm w.r.t. Towers

Let $M/L/K$ be finite extensions with M/L and L/K separable. Then for $\alpha \in M$:

$$\mathrm{tr}_{M/K}(\alpha) = \mathrm{tr}_{L/K}(\mathrm{tr}_{M/L}(\alpha)) \qquad \mathrm{Nm}_{M/K}(\alpha) = \mathrm{Nm}_{L/K}(\mathrm{Nm}_{M/L}(\alpha))$$

***Proof*:**
The extension M/K is separable (proposition 19.6.18). Let Ω be an algebraically closed field containing M, which exists by lemma 19.5.5 and the chain construction before it, and replace Ω by the algebraic closure of K inside it given by theorem 19.5.6. It contains M, as M/K is algebraic, and it is an algebraic closure of L and of M as well. Let $\sigma_1, \ldots, \sigma_n$ be the K-embeddings $L \to \Omega$ and $\tau_1, \ldots, \tau_m$ the L-embeddings $M \to \Omega$. By definition 19.6.13 and proposition 19.6.17, $n = [L : K]$, $m = [M : L]$, and M has exactly $[M : K] = nm$ embeddings into Ω over K.

Regarding Ω as an extension of L through σ_i, lemma 19.5.7 extends σ_i to a field homomorphism $\tilde{\sigma}_i \colon \Omega \to \Omega$.

By corollary 50.1.13, $\mathrm{tr}_{M/L}(\alpha) = \sum_j \tau_j(\alpha)$, an element of L, and $\mathrm{tr}_{L/K}(\beta) = \sum_i \sigma_i(\beta)$ for $\beta \in L$. Since $\tilde{\sigma}_i$ extends σ_i and is additive,

$$\mathrm{tr}_{L/K}(\mathrm{tr}_{M/L}(\alpha)) = \sum_{i=1}^{n} \tilde{\sigma}_i \left(\sum_{j=1}^{m} \tau_j(\alpha) \right) = \sum_{i,j} (\tilde{\sigma}_i \circ \tau_j)(\alpha)$$

and in the same way $\mathrm{Nm}_{L/K}(\mathrm{Nm}_{M/L}(\alpha)) = \prod_{i,j} (\tilde{\sigma}_i \circ \tau_j)(\alpha)$. Each $\tilde{\sigma}_i \circ \tau_j$ is a homomorphism $M \to \Omega$ fixing K. They are distinct: if $\tilde{\sigma}_i \tau_j = \tilde{\sigma}_{i'} \tau_{j'}$ on M, then restricting to L, where every τ_j is the identity, gives $\sigma_i = \sigma_{i'}$, so $i = i'$, and then $\tau_j = \tau_{j'}$ because $\tilde{\sigma}_i$ is injective. So the nm maps $\tilde{\sigma}_i \circ \tau_j$ are all the K-embeddings of M into Ω, and corollary 50.1.13 identifies the two right-hand sides with $\mathrm{tr}_{M/K}(\alpha)$ and $\mathrm{Nm}_{M/K}(\alpha)$, completing the proof.

The condition is not sufficient:

Example 50.1.16: Trace And Norm Insufficient To Detect Integral Elements

The polynomial $y^3 + 6y + 24$ is irreducible over $\mathbb{Q}$ by corollary 11.3.11 at the prime 3. Let γ be a root, $\alpha = \gamma/2$ and $L = \mathbb{Q}(\alpha) = \mathbb{Q}(\gamma)$, a field of degree 3. Dividing $\gamma^3 + 6\gamma + 24 = 0$ by 8 shows that α is a root of the monic polynomial $x^3 + \frac{3}{2}x + 3$ of degree $[L : \mathbb{Q}]$, so

$$m_{\alpha,\mathbb{Q}}(x) = x^3 + \frac{3}{2}x + 3$$

and example 50.1.11(3) gives

$$\mathrm{tr}_{L/\mathbb{Q}}(\alpha) = 0 \qquad \mathrm{Nm}_{L/\mathbb{Q}}(\alpha) = (-1)^3 \cdot 3 = -3$$

Both are integers, but $\alpha \notin \mathcal{O}_L$. Suppose $f(\alpha) = 0$ for a monic $f \in \mathbb{Z}[x]$. Then $f = m_{\alpha,\mathbb{Q}}\, g$ for a monic $g \in \mathbb{Q}[x]$. If g is constant, then $f = m_{\alpha,\mathbb{Q}} \notin \mathbb{Z}[x]$. Otherwise proposition 11.2.1 gives nonzero $r, t \in \mathbb{Q}$ with $r m_{\alpha,\mathbb{Q}}, tg \in \mathbb{Z}[x]$ and $f = (r m_{\alpha,\mathbb{Q}})(tg)$. Comparing leading coefficients, r and t are integers with $rt = 1$, so $r = \pm 1$ and $m_{\alpha,\mathbb{Q}} \in \mathbb{Z}[x]$, which is false.

For quadratic fields the condition is sufficient, since an element of degree 2 has the trace and the norm as the coefficients of its minimal polynomial:

Example 50.1.17: Rings of Integers of Quadratic Extensions

Let $n \neq 0, 1$ be a square-free integer, $K = \mathbb{Q}(\sqrt{n})$, and $\alpha = a + b\sqrt{n}$ with $a, b \in \mathbb{Q}$. In the basis $1, \sqrt{n}$, multiplication by α has matrix $\begin{pmatrix} a & nb \\ b & a \end{pmatrix}$, so

$$\mathrm{tr}_{K/\mathbb{Q}}(\alpha) = 2a \qquad \mathrm{Nm}_{K/\mathbb{Q}}(\alpha) = a^2 - nb^2$$

If $\alpha \in \mathcal{O}_K$, both are integers by corollary 50.1.14, $\mathbb{Z}$ being integrally closed (corollary 29.9.6). Conversely, if both are integers, then α is a root of the monic polynomial $x^2 - 2ax + (a^2 - nb^2) \in \mathbb{Z}[x]$, as $(\alpha - a)^2 = nb^2$, so $\alpha \in \mathcal{O}_K$. Hence $\alpha \in \mathcal{O}_K$ if and only if $2a \in \mathbb{Z}$ and $a^2 - nb^2 \in \mathbb{Z}$.

Suppose both hold, and put $u = 2a \in \mathbb{Z}$ and $v = 2b$. Then $u^2 - nv^2 = 4(a^2 - nb^2) \in 4\mathbb{Z}$, so

$nv^2 \in \mathbb{Z}$. Writing $v = r/t$ in lowest terms with $t > 0$, t^2 divides nr^2 and is coprime to r^2, so $t^2 | n$, and $t = 1$ as n is square-free. So $u, v \in \mathbb{Z}$ and $u^2 \equiv nv^2 \bmod 4$. Squares are 0 or 1 modulo 4, according as the number is even or odd.

- If $n \equiv 2, 3 \bmod 4$ and v is odd, then $nv^2 \equiv 2$ or $3 \bmod 4$, which is not a square modulo 4. So v is even, then $u^2 \equiv 0 \bmod 4$ and u is even, that is, $a, b \in \mathbb{Z}$.
- If $n \equiv 1 \bmod 4$, then $u^2 \equiv v^2 \bmod 4$, so u and v have the same parity, and $\alpha = \frac{u-v}{2} + v \cdot \frac{1+\sqrt{n}}{2}$ with $\frac{u-v}{2}, v \in \mathbb{Z}$. Conversely $\frac{1+\sqrt{n}}{2}$ has trace 1 and norm $\frac{1-n}{4} \in \mathbb{Z}$, so it lies in $\mathcal{O}_K$.

As n is square-free, $n \not\equiv 0 \bmod 4$, and the two cases give

$$\mathcal{O}_{\mathbb{Q}(\sqrt{n})} = \begin{cases} \mathbb{Z}[\sqrt{n}] & n \equiv 2, 3 \bmod 4 \\ \mathbb{Z}\left[\frac{1+\sqrt{n}}{2}\right] & n \equiv 1 \bmod 4 \end{cases}$$

where in the second case $\mathbb{Z}[\frac{1+\sqrt{n}}{2}] = \mathbb{Z} + \mathbb{Z}\frac{1+\sqrt{n}}{2}$, because $\omega = \frac{1+\sqrt{n}}{2}$ satisfies $\omega^2 = \omega + \frac{n-1}{4}$.

A final result in this section is to find the group of units of $\mathcal{O}_K$. Note that in general, if $\alpha \in \mathcal{O}_K$, then $1/\alpha \notin \mathcal{O}_K$. For example $2 \in \mathcal{O}_{\mathbb{Q}}$, but certainly $1/2 \notin \mathcal{O}_{\mathbb{Q}}$. In fact, the only units in $\mathcal{O}_{\mathbb{Q}}$ are ± 1. If $\mathcal{O}_K$ contains roots of unity, then certainly their inverse is in $\mathcal{O}_K$ (for if $\alpha = \zeta_n$ $1/\zeta = \zeta_n^{n-1}$). There are in general more units in $\mathcal{O}_K$, and the group of units of a ring of integers shall be fully characterized in section 50.2.4. With the norm, we have a way of detecting units:

Proposition 50.1.18: Norm And Units

Let L/K be a finite field extension. Then

$$\alpha \in \mathcal{O}_L^* \qquad \Leftrightarrow \qquad \mathrm{Nm}_{L/K}(\alpha) \in \mathcal{O}_K^*$$

In the space case where $K = \mathbb{Q}$, then $\alpha \in \mathcal{O}_L^*$ if and only if $\mathrm{Nm}_{L/\mathbb{Q}}(\alpha) = \pm 1$.

***Proof*:**
Let $\alpha \in \mathcal{O}_L^*$ so that $\mathrm{Nm}_{L/K}(\alpha) \in \mathcal{O}_K$. If α is a unit in $\mathcal{O}_L$, then $1/\alpha \in \mathcal{O}_L$ exists. Then:

$$1 = \mathrm{Nm}_{L/K}(1) = \mathrm{Nm}_{L/K}(\alpha \cdot 1/\alpha) = \mathrm{Nm}_{L/K}(\alpha)\mathrm{Nm}_{L/K}(1/\alpha)$$

hence, $\mathrm{Nm}_{L/K}(\alpha), \mathrm{Nm}_{L/K}(1/\alpha) \in \mathcal{O}_K^\times$. Conversely, if $\mathrm{Nm}_{L/K}(\alpha) \in \mathcal{O}_K$, then there exists a β such that

$$\beta \mathrm{Nm}_{L/K}(\alpha) = 1$$

Then by definition of the norm:

$$1 = \beta \mathrm{Nm}_{L/K}(\alpha) = \beta \prod_{\sigma} \sigma(\alpha) = \alpha \left(\beta \prod_{\sigma \neq \mathrm{id}} \sigma(\alpha) \right) = \alpha y$$

where $y \in \mathcal{O}_L$ since each $\sigma(\alpha) \in \mathcal{O}_L$, which gives the result.

Proposition 50.1.19: Norm And Irreducible

Let $L/\mathbb{Q}$ be a finite extension and $\alpha \in \mathcal{O}_L$. Then if p is prime:

$$\mathrm{Nm}_{L/\mathbb{Q}}(\alpha) = p \implies \alpha \text{ is irreducible}$$

***Proof*:**
Suppose α where reducible so that $\alpha = \beta\gamma$ where β, γ or not units, hence have norm greater than 1. Then:

$$\begin{aligned}\mathrm{Nm}_{L/\mathbb{Q}}(\alpha) &= \mathrm{Nm}_{L/\mathbb{Q}}(\beta\gamma) \\ &= \mathrm{Nm}_{L/\mathbb{Q}}(\beta)\mathrm{Nm}_{L/\mathbb{Q}}(\gamma) \\ &= p\end{aligned}$$

a contradiction.

Note that the converse is not true

Example 50.1.20: Prime, But Norm Not Prime

Let $K = \mathbb{Q}(\sqrt{2})$ so that $\mathcal{O}_K = \mathbb{Z}[\sqrt{2}]$. Then $\mathrm{Nm}_{K/\mathbb{Q}}(5) = 5^2 = 25$, which is certainly not prime, however 5 is prime in $\mathbb{Z}[\sqrt{2}]$. This is at this stage a tedious calculation: assume that it factors $5 = \alpha\beta$ where $\alpha, \beta \in \mathbb{Z}[\sqrt{2}]$, $\alpha = a + bi$, $\beta = c + di$, and:

$$\mathrm{Nm}_{K/\mathbb{Q}}(\alpha) = a - 2b = 5 = c - 2d = \mathrm{Nm}_{K/\mathbb{Q}}(\beta)$$

but no such a, b, c, d exist. Later, we shall be able to deduce this almost immediately using Dedekind-Kummer's Theorem (see theorem 50.4.7).

In lemma 50.2.29, we shall give a partial converse which shall as a corollary imply:

$$\alpha \text{ prime} \implies \left|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)\right| = p^f$$

for appropriate f. Note how α must be prime, which is *stronger* than irreducible. However, we will often be working over rings where we have few prime elements but many irreducible elements. In section 50.2 we shall show how to "fix" this problem to make the norm more useful.

50.1.2 Functionals: Discriminant

As we saw, if $\alpha \in F/\mathbb{Q}$ is integral, then $\mathrm{tr}(\alpha), \mathrm{Nm}(\alpha) \in \mathbb{Z}$. However, the converse is not necessarily true as we saw in example 50.1.16. We will require a more powerful result, one that will verify that an element is an element of a ring of integers. For this, we shall bring in some multilinear algebra and define a new tool that shall become invaluable finding a *basis* for $\mathcal{O}_K$ (recall that it was mentioned that $\mathcal{O}_K$ shall be proven to be a finitely generated free $\mathbb{Z}$-module). Given a basis can be found, then an element can be determined to be integral using the basis. The tool that shall be used to detect a basis for $\mathcal{O}_K$ is called the *field discriminant*. The norm and the trace shall both be used in the definition of the field discriminant.

Some Multi-Linear Algebra

Recall from section 13.3.4 that multi-linear forms have matrix representations and so the determinant of multi-linear maps is well-defined:

Definition 50.1.21: [General] Discriminant

Let $\varphi : V \times V \to k$ be a symmetric k-bilinear map ($\varphi(x,y) = \varphi(y,x)$). Then given a basis $v_1, v_2, ..., v_n$, the *discriminant* of φ is:

$$\text{disc}(\varphi) = \det \begin{pmatrix} \varphi(v_1,v_1) & \varphi(v_1,v_2) & \cdots & \varphi(v_1,v_n) \\ \varphi(v_2,v_1) & \varphi(v_2,v_2) & \cdots & \varphi(v_2,v_n) \\ \vdots & \ddots & \vdots & \\ \varphi(v_n,v_1) & \varphi(v_n,v_2) & \cdots & \varphi(v_n,v_n) \end{pmatrix}$$

and is denoted $\text{disc}(\varphi)$.

Let $\{\beta_1, \beta_2, ..., \beta_n\}$ be a basis for V and $\{v_1, v_2, ..., v_n\}$ be some collection of elements so that

$$v_i = \sum_i a_i \beta_i$$

Then:

$$\varphi(v_k, v_l) = \sum_{i,j} \varphi(a_{ki}\beta_i, a_{lj}\beta_j) = a_{ki}\varphi(\beta_i, \beta_j)a_{kl}$$

hence, as matrices, we have the (component-wise) equality:

$$(\varphi(v_k, v_l)) = A \cdot (\varphi(e_i, e_j)) \cdot A^{\text{tr}}$$

where $A = (a_{ij})$. Then if we have a change of basis, we have the determinant of the matrix is:

$$\det((\varphi(f_i, f_j)) = \det(A)^2 \cdot \det((\varphi(\beta_i, \beta_j))) \tag{50.2}$$

Since $A \in \text{GL}(k)$, we see that the discriminant is defined up to the square of a unit. Hence, if $\text{disc}(\varphi) \neq 0$, $\text{disc}(\varphi)$ is well-defined in $k^\times/(k^\times)^2$ If $K = \mathbb{Q}$, then $(\mathbb{Q}^\times)^2 = 1$, hence the discriminant is well-defined in $\mathbb{Q}^\times$.

Invertible matrices allowed us to define an isomorphism between V and $V^\vee$ when V is finite dimensional. We shall require this same property for bilinear forms. For this, the notion of non-degenerate form needs to be upgraded for bilinear forms:

Definition 50.1.22: Non-degenerate Form

let φ be a bilinear form. Then φ is *non-degenerate* if φ has a non-zero discriminant

Proposition 50.1.23: Non-degenerate Form Equivalences

let φ be a symmetric bilinear form on a finite-dimensional k-vector space V. Then φ is *non-degenerate* if any of the following equivalent conditions hold:

1. φ has a non-zero discriminant
2. the left kernel is zero: $\{v \in V \mid \varphi(v,x) = 0,\ \forall x \in V\}$
3. the right kernel is zero: $\{v \in V \mid \varphi(x,v) = 0,\ \forall x \in V\}$

***Proof*:**
By definition 50.1.21, φ is symmetric, so $\varphi(v,x) = \varphi(x,v)$ for all $v, x \in V$ and the sets in (2) and (3) coincide. It remains to prove that (1) is equivalent to (3).

Fix a basis $\beta_1, \dots, \beta_n$ of V and let $B = (\varphi(\beta_i, \beta_j))$, so that $\operatorname{disc}(\varphi) = \det(B)$ computed in this basis. By (50.2), a change of basis multiplies $\det(B)$ by $\det(A)^2$ with A invertible, so whether $\det(B) = 0$ does not depend on the chosen basis. Write $v = \sum_i x_i \beta_i$. By bilinearity, $\varphi(x,v) = 0$ for all $x \in V$ exactly when $\varphi(\beta_j, v) = \sum_i \varphi(\beta_j, \beta_i) x_i = 0$ for every j, that is, exactly when $Bx = 0$ for the coordinate vector $x = (x_1, \dots, x_n)$.

If $\det(B) \neq 0$, then $\det(B)$ is a unit of k and B is invertible by proposition 13.4.12, so $Bx = 0$ forces $x = B^{-1}Bx = 0$ and the right kernel is zero. If $\det(B) = 0$, then B is not invertible, so by proposition 13.2.10 there exists $x \neq 0$ with $Bx = 0$, and then $v = \sum_i x_i \beta_i \neq 0$ lies in the right kernel. Hence (1) holds if and only if (3) holds, as we sought to show.

If φ is non-degenerate, it always induces an isomorphism

$$V \mapsto V^\vee \qquad v \mapsto (x \mapsto \varphi(v,x))$$

Showing that non-degenerate maps φ give a "representation" of the hom-dual. The particular symmetric k-bilinear form that will be useful in finding the rank of the ring of integers is the one built from the trace, definition 19.6.30. In this chapter we call it the *trace pairing* and write it with the lower-case tr used throughout,

$$\operatorname{tr}_{F/k} : F \times F \to k \qquad (\alpha, \beta) \mapsto \operatorname{tr}_{F/k}(\alpha\beta)$$

Its nondegeneracy is a statement about *separability*, not about F alone: if F/k is separable then the trace pairing is nondegenerate (proposition 19.6.31). The hypothesis is not decorative. Over $k = \mathbb{F}_p(t)$ the extension $F = k(t^{1/p})$ has $\operatorname{tr}_{F/k} \equiv 0$, so the pairing vanishes identically. Nor can separability be dodged by arguing that $\operatorname{tr}_{F/k}(\alpha\alpha^{-1}) = \operatorname{tr}_{F/k}(1) = [F:k] \neq 0$ for $\alpha \neq 0$: that degree is computed *in* k, and it dies whenever $\operatorname{char} k \mid [F:k]$, already for $\mathbb{F}_4/\mathbb{F}_2$, which is separable and whose trace pairing is nondegenerate all the same.

Every extension we pair below is separable, so by proposition 50.1.23 the left kernel is trivial and we have an isomorphism

$$F \xrightarrow{\cong} \operatorname{Hom}_k(F,k) = F^* \qquad x \mapsto (y \mapsto \operatorname{tr}_{F/k}(xy))$$

The submodule of F that this isomorphism carries onto a prescribed integrality condition is the *integral trace dual*, defined in definition 50.1.35 once we have the ring of integers in hand to state it for.

Field Discriminant

With a general overview of discriminants, we return to detecting algebraic integers more precisely using the discriminant. First the determinant, det, is an alternating n-form, meaning $(\det)^2$ is a symmetric n-form. Note that this is the same discriminant introduced in section 19.6.3. The equivalence shall soon be shown.

Definition 50.1.24: [Field] Discriminant

Let L/k be a finite extension of degree n, and let $\sigma_1, \sigma_2, ..., \sigma_n \in \text{Emb}_k(L)$ be the k-embeddings of L in $\mathbb{C}$. Then for any n-tuple of elements $\alpha_1, \alpha_2, ..., \alpha_n \in L$, define the *discriminant* of $\alpha_1, \alpha_2, ..., \alpha_n$ to be:

$$\text{disc}_{L/k}(\alpha_1, \alpha_2, ..., \alpha_n) = \det \begin{pmatrix} \sigma_1(\alpha_1) & \cdots & \sigma_1(\alpha_n) \\ \vdots & \ddots & \vdots \\ \sigma_n(\alpha_1) & \cdots & \sigma_n(\alpha_n) \end{pmatrix}^2 = \det((\sigma_i(\alpha_j))_{ij})^2$$

Notice that the square makes the discriminant independent of the ordering of the σ_i and α_j. If we chose a different set of elements $(\beta_1, \beta_2, ..., \beta_n)$ that differ from $(\alpha_1, \alpha_2, ..., \alpha_n)$ by a change of basis, that is $\vec{\alpha} = A\vec{\beta}$, then as we observed in equation 50.2, we get

$$\text{disc}_{L/k}(\beta_1, \beta_2, ..., \beta_n) = \det(A)^2 \cdot \text{disc}_{L/k}(\alpha_1, \alpha_2, ..., \alpha_n)$$

meaning the discriminant is not quite basis independent, meaning it is properly defined for operators in $L^\times/L^{\times 2}$ (where $L^\times$ are the units of L, since det maps invertible matrices to units, see proposition 13.4.12).

Example 50.1.25: Field Discriminant

1. Let $K = \mathbb{Q}(\sqrt{m})$ where m is square free. Then K has a basis $A = \{1, \sqrt{m}\}$ and $B = \left\{1, \frac{1+\sqrt{m}}{2}\right\}$. If $m \equiv 2, 3 \bmod 4$, then the former is a basis for $\mathcal{O}_K$ and if $m \equiv 1 \bmod 4$, then then the latter is a basis for $\mathcal{O}_K$. Computing both, we get:

$$\text{disc}_{K/\mathbb{Q}}(A) = \det \begin{pmatrix} 1 & \sqrt{m} \\ 1 & -\sqrt{m} \end{pmatrix}^2 = (-\sqrt{m} - \sqrt{m})^2 = 4m$$

$$\text{disc}_{K/\mathbb{Q}}(B) = \det \begin{pmatrix} 1 & \frac{1+\sqrt{m}}{2} \\ 1 & \frac{1-\sqrt{m}}{2} \end{pmatrix}^2 = \left(\frac{-2\sqrt{m}}{2}\right)^2 = m$$

Yet another basis for $\mathbb{Q}(\sqrt{m})$ is $C = \{1, \sqrt{m}/10\}$. In that case:

$$\text{disc}_{K/\mathbb{Q}}(C) = \det \begin{pmatrix} 1 & \frac{\sqrt{m}}{10} \\ 1 & -\frac{\sqrt{m}}{10} \end{pmatrix}^2 = \left(\frac{-\sqrt{m}}{5}\right)^2 = \frac{m}{25}$$

However, C is not a basis for $\mathcal{O}_K$, namely since the denominator is too big. Notice that the first two discriminant integers, while the third one is not.

2. Let $K = \mathbb{Q}(\sqrt[3]{2})$. Then $A = \{1, \sqrt[3]{2}, \sqrt[3]{4}\}$ is a basis for K, and:

$$\text{disc}_{K/\mathbb{Q}}(A) = \det \begin{pmatrix} 1 & \sqrt[3]{2} & \sqrt[3]{4} \\ 1 & \sqrt[3]{2}\zeta_3 & \sqrt[3]{4}\zeta_3^2 \\ 1 & \sqrt[3]{2}\zeta_3^2 & \sqrt[3]{4}\zeta_3 \end{pmatrix}^2 = -108 = -2^2 \cdot 3^3$$

showing that the discriminant can be negative. We shall come back to seeing how this is useful for finding whether $\mathcal{O}_K = \mathbb{Z}[\sqrt[3]{2}]$.

The following alternative form is useful for an alternate way of computing the discriminant as well as important for deducing some theoretical properties of the elements inputted into the discriminant:

Proposition 50.1.26: Discriminant Via Trace-Pairing

Let L/k be a finite separable extension of degree n, with k-embeddings $\sigma_1, \dots, \sigma_n$ of L into $\mathbb{C}$ as in definition 50.1.24, and let $\alpha_1, \dots, \alpha_n \in L$. Then

$$\text{disc}_{L/k}(\alpha_1, \alpha_2, ..., \alpha_n) = \det(\text{tr}_{L/k}(\alpha_i \alpha_j))$$

***Proof*:**
Let $S = (\sigma_i(\alpha_j))_{ij}$. The (j, l) entry of $S^t S$ is

$$\sum_{i=1}^{n} \sigma_i(\alpha_j)\sigma_i(\alpha_l) = \sum_{i=1}^{n} \sigma_i(\alpha_j \alpha_l)$$

because each σ_i is a ring homomorphism. The σ_i take values in the elements of $\mathbb{C}$ algebraic over k, which form an algebraic closure of k (theorem 19.5.6), so they are the embeddings of corollary 50.1.13, and the sum equals $\text{tr}_{L/k}(\alpha_j \alpha_l)$. Hence $(\text{tr}_{L/k}(\alpha_j \alpha_l))_{jl} = S^t S$, and by proposition 13.4.7 and proposition 13.4.6,

$$\det(\text{tr}_{L/k}(\alpha_j \alpha_l)) = \det(S^t)\det(S) = \det(S)^2 = \text{disc}_{L/k}(\alpha_1, \dots, \alpha_n)$$

completing the proof.

In particular, the above form allows for the detection of sets of algebraic integers:

Corollary 50.1.27: Detecting Algebraic Integers using Discriminant

Let K be a number field and $\alpha_1, \alpha_2, ..., \alpha_n$ a $\mathbb{Q}$-basis. Then $\text{disc}_{K/\mathbb{Q}}(\alpha_1, ..., \alpha_n) \in \mathbb{Q}$, and if all $\alpha_1, \alpha_2, ..., \alpha_n$ are algebraic integers, then $\text{disc}(\alpha_1, \alpha_2, ..., \alpha_n) \in \mathbb{Z}$.

***Proof*:**
we know that $\text{tr}_{K/\mathbb{Q}}(\alpha_i \alpha_j) \in \mathbb{Q}$ by proposition 50.1.12 and are integers via corollary 50.1.14, hence $\text{disc}_{K/\mathbb{Q}}(\alpha_1, \alpha_2, ..., \alpha_n) \in \mathbb{Q}$, and if they are all algebraic integers then $\text{disc}_{K/\mathbb{Q}}(\alpha_1, \alpha_2, ..., \alpha_n) \in \mathbb{Z}$.

Corollary 50.1.28: Discriminant And Linear Independence

Let K be a number field of degree n and $\alpha_1, \alpha_2, ..., \alpha_n \in K$. Then $\mathrm{disc}_{K/\mathbb{Q}}(\alpha_1, \alpha_2, ..., \alpha_n) = 0$ if and only if $\alpha_1, \alpha_2, ..., \alpha_n$ are $\mathbb{Q}$-linearly dependent.

***Proof*:**

Step 1: dependence gives 0. Suppose $\sum_j c_j \alpha_j = 0$ with $c_j \in \mathbb{Q}$ and some $c_k \neq 0$. Every embedding σ_i fixes $\mathbb{Q}$, so $\sum_j c_j \sigma_i(\alpha_j) = 0$ for every i, that is, $\sum_j c_j C_j = 0$ for the columns C_j of $(\sigma_i(\alpha_j))_{ij}$. Replacing the kth column by $\sum_j c_j C_j = 0$ multiplies the determinant by c_k, by multilinearity and the alternating property (proposition 13.4.6), and produces a matrix with a zero column, of determinant 0. So $c_k \det((\sigma_i(\alpha_j))_{ij}) = 0$, and $\mathrm{disc}_{K/\mathbb{Q}}(\alpha_1, \ldots, \alpha_n) = 0$.

Step 2: independence gives a nonzero value. Suppose the α_i are $\mathbb{Q}$-linearly independent, hence a $\mathbb{Q}$-basis of K, and that $\mathrm{disc}_{K/\mathbb{Q}}(\alpha_1, \ldots, \alpha_n) = 0$. By proposition 50.1.26, the rational matrix $T = (\mathrm{tr}_{K/\mathbb{Q}}(\alpha_i \alpha_j))_{ij}$ has determinant 0. Its rows are linearly dependent over $\mathbb{Q}$: otherwise they form a basis of $\mathbb{Q}^n$, the linear map $x \mapsto xT$ is invertible, T has an inverse matrix S, and $\det(S)\det(T) = \det(I) = 1$ (proposition 13.4.7). So there are $a_i \in \mathbb{Q}$, not all zero, with $\sum_i a_i \mathrm{tr}_{K/\mathbb{Q}}(\alpha_i \alpha_j) = 0$ for every j. Put $\alpha = \sum_i a_i \alpha_i$, which is nonzero by independence. The trace is $\mathbb{Q}$-linear, so $\mathrm{tr}_{K/\mathbb{Q}}(\alpha \alpha_j) = 0$ for every j, and then $\mathrm{tr}_{K/\mathbb{Q}}(\alpha t) = 0$ for every $t \in K$, as the α_j span K. For $t = \alpha^{-1}$ this gives $\mathrm{tr}_{K/\mathbb{Q}}(1) = n = 0$, which is false. So the discriminant is nonzero, completing the proof.

The corollary can be thought of as motivation for the name discriminant: If $K/\mathbb{Q}$ is a number field of dimension n, the discriminant will "discriminate" sets that are bases for $K/\mathbb{Q}$.

Since number fields are finite separable extensions, we always find a primitive element for a separable algebraic extension, the following theorem gives another important interpretation of the discriminant:

Proposition 50.1.29: Discriminant via Primitive Element

Let L/K be a finite separable extension of degree n with K-embeddings $\sigma_1, \ldots, \sigma_n$ of L as in definition 50.1.24, let α be a primitive element, and put $\alpha_i = \sigma_i(\alpha)$. Then $\alpha_1, \ldots, \alpha_n$ are the roots of the minimal polynomial $m_{\alpha,K}$, and

$$\mathrm{disc}_{L/K}(1, \alpha, \ldots, \alpha^{n-1}) = \prod_{1 \leq i < j \leq n} (\alpha_i - \alpha_j)^2 = (-1)^{n(n-1)/2} \mathrm{Nm}_{L/K}(m'_{\alpha,K}(\alpha))$$

where $m'_{\alpha,K}$ is the derivative of the minimal polynomial. This number is denoted $\mathrm{disc}_{L/K}(\alpha)$, the *discriminant* of α[a].

[a] By proposition 19.6.28, it is the discriminant of the polynomial $m_{\alpha,K}$ in the sense of section 20.3

***Proof*:**

Step 1: the roots. Each σ_i fixes the coefficients of $m_{\alpha,K}$, so $m_{\alpha,K}(\alpha_i) = \sigma_i(m_{\alpha,K}(\alpha)) = 0$. A K-embedding of $L = K(\alpha)$ is determined by the image of α, so the n distinct embeddings give n distinct roots α_i, which are all the roots of $m_{\alpha,K}$, of degree n. So $m_{\alpha,K} = \prod_i (x - \alpha_i)$.

Step 2: a Vandermonde determinant. For elements $\gamma_1, \dots, \gamma_N$ of a field, let $W(\gamma_1, \dots, \gamma_N)$ be the $N \times N$ matrix with uth row $(1, \gamma_u, \dots, \gamma_u^{N-1})$. We show

$$\det W(\gamma_1, \dots, \gamma_N) = \prod_{1 \le u < v \le N} (\gamma_v - \gamma_u)$$

by induction on N, the case $N = 1$ being 1. For $c = N-1, N-2, \dots, 1$ in this order, subtract γ_1 times column c from column $c+1$. This changes no determinant (proposition 13.4.6), and turns the entry in row u and column $c+1$ into $\gamma_u^c - \gamma_1 \gamma_u^{c-1} = \gamma_u^{c-1}(\gamma_u - \gamma_1)$. The first row becomes $(1, 0, \dots, 0)$. Subtracting the first row from every other row then makes the first column $(1, 0, \dots, 0)^t$ and changes nothing else, leaving a block diagonal matrix with blocks (1) and the matrix with entries $\gamma_u^{c-2}(\gamma_u - \gamma_1)$ for $2 \le u, c \le N$. By proposition 13.4.8 and multilinearity in rows,

$$\det W(\gamma_1, \dots, \gamma_N) = \prod_{v=2}^{N} (\gamma_v - \gamma_1) \det W(\gamma_2, \dots, \gamma_N)$$

and the induction hypothesis gives the claim.

Step 3: the product formula. By definition 50.1.24, $\mathrm{disc}_{L/K}(1, \alpha, \dots, \alpha^{n-1})$ is the square of the determinant of $(\sigma_i(\alpha^{j-1}))_{ij} = (\alpha_i^{j-1})_{ij} = W(\alpha_1, \dots, \alpha_n)$. Step 2 gives $\mathrm{disc}_{L/K}(1, \alpha, \dots, \alpha^{n-1}) = \prod_{i<j}(\alpha_j - \alpha_i)^2 = \prod_{i<j}(\alpha_i - \alpha_j)^2$.

Step 4: the norm formula. By corollary 50.1.13, and since each σ_r fixes the coefficients of $m'_{\alpha,K}$,

$$\mathrm{Nm}_{L/K}(m'_{\alpha,K}(\alpha)) = \prod_{r=1}^{n} \sigma_r(m'_{\alpha,K}(\alpha)) = \prod_{r=1}^{n} m'_{\alpha,K}(\alpha_r)$$

Writing $m_{\alpha,K} = (x - \alpha_r) h_r$ with $h_r = \prod_{s \ne r}(x - \alpha_s)$, the Leibniz rule gives $m'_{\alpha,K} = h_r + (x - \alpha_r) h'_r$, so $m'_{\alpha,K}(\alpha_r) = \prod_{s \ne r}(\alpha_r - \alpha_s)$. Multiplying over r and pairing the factors $\alpha_r - \alpha_s$ and $\alpha_s - \alpha_r = -(\alpha_r - \alpha_s)$ for each of the $n(n-1)/2$ pairs $r < s$,

$$\prod_{r=1}^{n} m'_{\alpha,K}(\alpha_r) = (-1)^{n(n-1)/2} \prod_{r<s} (\alpha_r - \alpha_s)^2$$

and as $((-1)^{n(n-1)/2})^2 = 1$ this is the second equality, completing the proof.

If $L = K[\alpha]$, then we shall often write $\mathrm{disc}_{L/K}(\alpha)$ instead of $\mathrm{disc}_{L/K}(\alpha, \alpha_2, .., \alpha_n)$. The discriminant detects bases only on separable extensions:

Corollary 50.1.30: Discriminant And Separability

Let F/k be a finite extension of degree n, and for $\alpha_1, \dots, \alpha_n \in F$ put

$$D(\alpha_1, \dots, \alpha_n) = \det(\mathrm{tr}_{F/k}(\alpha_i \alpha_j))$$

the discriminant of definition 50.1.24 whenever that is defined (proposition 50.1.26). Then D is not identically zero if and only if F/k is separable. More precisely, if F/k is separable then $D(\alpha_1, \dots, \alpha_n) \neq 0$ for every k-basis $\alpha_1, \dots, \alpha_n$ of F, and if F/k is inseparable then $\mathrm{tr}_{F/k}$ and D are identically zero.

If you recall that the resultant is zero if two polynomials share a root, then this shows how the discriminant is also related to the resultant.

***Proof*:**

Step 1: separable extensions. Suppose F/k is separable and let $\alpha_1, \dots, \alpha_n$ be a k-basis of F. The trace $\mathrm{tr}_{F/k}$ of definition 50.1.10 is the trace of the multiplication map, so the bilinear form $(x, y) \mapsto \mathrm{tr}_{F/k}(xy)$ is the trace form of proposition 19.6.31, which is nondegenerate. Its matrix $(\mathrm{tr}_{F/k}(\alpha_i \alpha_j))$ is therefore invertible (lemma 13.3.23), and an invertible matrix T has $\det(T)\det(T^{-1}) = 1$ (proposition 13.4.7). So $D(\alpha_1, \dots, \alpha_n) \neq 0$.

Step 2: inseparable extensions. Suppose F/k is inseparable and let $\beta \in F$, $d = [k(\beta) : k]$, $s = [F : k(\beta)]$ and $m_{\beta,k}(x) = x^d + a_{d-1}x^{d-1} + \cdots + a_0$. Expanding $m_{\beta,k}(x) = \prod_j (x - r_j)$ over $\overline{k}$ gives $\sum_j r_j = -a_{d-1}$, so proposition 50.1.12 reads $\mathrm{tr}_{F/k}(\beta) = -s\, a_{d-1}$. We show that this is 0. If β is inseparable over k, then $m'_{\beta,k} = 0$ by proposition 19.6.7, and $d \geq 2$. The coefficients of x^{d-1} and x^{d-2} in $m'_{\beta,k}$ give $d \cdot 1 = 0$ and $(d-1)a_{d-1} = 0$ in k. As $(d-1) \cdot 1 = -1 \neq 0$, we get $a_{d-1} = 0$.

If β is separable over k, then $k(\beta)/k$ is separable (proposition 19.6.17). Since F/k is inseparable and F is generated over k by a k-basis, the same result shows that some element γ of that basis is inseparable over k. If γ were separable over $k(\beta)$, then $k(\beta, \gamma)/k(\beta)$ would be separable by the same result, hence $k(\beta, \gamma)/k$ would be separable by proposition 19.6.18, and γ would be separable over k. So the minimal polynomial g of γ over $k(\beta)$ is irreducible and inseparable, $g' = 0$, and the leading coefficient of g' gives $e \cdot 1 = 0$ for $e = \deg g = [k(\beta, \gamma) : k(\beta)]$. By theorem 19.3.7, $s = [F : k(\beta, \gamma)]\, e$, so $s \cdot 1 = 0$ and $\mathrm{tr}_{F/k}(\beta) = 0$.

Hence $\mathrm{tr}_{F/k}$ is identically zero, every matrix $(\mathrm{tr}_{F/k}(\alpha_i \alpha_j))$ is the zero matrix, and D is identically zero, completing the proof.

Example 50.1.31: Discriminant On Cyclotomic extension

Let p be a prime, ζ_p a primitive pth root of unity, and $K = \mathbb{Q}(\zeta_p)$. Then recall from section 19.7.1 that its minimal polynomial is:

$$f(x) = 1 + x + x^2 + \cdots + x^{p-1}$$

Then to compute $f'(\zeta_p)$, recall that

$$x^p - 1 = (x-1)f(x) \implies px^{p-1} = f(x) + (x-1)f'(x) \implies f'(\zeta_p) = \frac{p}{\zeta_p(\zeta_p - 1)}$$

Taking the norm, for p odd:

$$\mathrm{Nm}_{K/\mathbb{Q}}(f'(\zeta_p)) = \frac{\mathrm{Nm}_{K/\mathbb{Q}}(p)}{\mathrm{Nm}_{K/\mathbb{Q}}(\zeta_p)\mathrm{Nm}_{K/\mathbb{Q}}(\zeta_p - 1)} = \frac{p^{p-1}}{1 \cdot p}$$

where $\mathrm{Nm}_{K/\mathbb{Q}}(\zeta_p - 1) = \prod_{k=1}^{p-1}(\zeta_p^k - 1) = (-1)^{p-1}f(1) = p$ by corollary 50.1.13, as the embeddings of K send ζ_p to the roots $\zeta_p, \dots, \zeta_p^{p-1}$ of f, and $p-1$ is even. Hence, by proposition 50.1.29 with $n = p-1$, and since $(p-1)(p-2)/2 \equiv (p-1)/2 \bmod 2$ because $p-2$ is odd:

$$\mathrm{disc}_{K/\mathbb{Q}}(\zeta_p) = (-1)^{(p-1)(p-2)/2}\mathrm{Nm}_{K/\mathbb{Q}}(f'(\zeta_p)) = (-1)^{(p-1)/2}p^{p-2}$$

For instance $\mathrm{disc}(\zeta_3) = -3$, the discriminant of $x^2 + x + 1$. Lemma 50.4.66 computes $\mathrm{disc}(\zeta_n)$ up to sign when n is a prime power. For arbitrary n, $\mathrm{disc}(\zeta_n) \big| n^{\varphi(n)}$, where φ is the Euler totient. If f is the [monic] irreducible polynomial for ζ_n over $\mathbb{Q}$ for arbitrary $n \in \mathbb{N}$, we get that

$$x^n - 1 = f(x)g(x) \qquad g(x) \in \mathbb{Z}[x]$$

Differentiating and evaluating at ζ_n, we get $n = \zeta_n f'(\zeta_n)g(\zeta_n)$. Taking the norm, we get:

$$n^{\varphi(n)} = \pm\mathrm{disc}(\zeta_n)\mathrm{Nm}(\zeta_n g(\zeta_n))$$

which since $\mathrm{Nm}(\zeta_n g(\zeta_n)) \in \mathbb{Z}$, we get that $\mathrm{disc}(\zeta_n) \big| n^{\varphi(n)}$.

Exercise 50.1.1

1. Give a second proof of proposition 19.6.31, independent of the Vandermonde argument used there: show that if F/K is finite and separable, then $\mathrm{tr}_{F/K}(a)$ cannot be 0 for all $a \in F$ (Hint: use Dedekind's lemma, corollary 20.1.40). Deduce that the bilinear form $(x, y) \mapsto \mathrm{tr}_{F/K}(xy)$ is non-degenerate.
2. (series of question for Stickelberger's theorem, that $d_K \equiv 0, 1 \bmod 4$)

50.1.3 Abelian Group Structure

We now prove that $\mathcal{O}_K$ is a free $\mathbb{Z}$-module of finite rank. From the above discussion, we can start seeing how this is useful in finding elements of $\mathcal{O}_K$: given it is finitely generated and we know the rank, we can look for generating linearly independent sets, i.e. a basis, for $\mathcal{O}_K$ (since $\mathcal{O}_K$ is a module over a PID).

We in fact can prove something slightly stronger that shall be useful later in this chapter:

Proposition 50.1.32: Generation of Ring of Integers

Let R be a normal integral domain, ($\overline{R}^{K(R)} = R$), $K = K(R)$ the field of fraction of R, F/K a separable extension of degree n, and let $S = \overline{R}^{F}$ where F/K. Then there exists free R-submodules M' of F such that if $M = R^n$,

$$M \subseteq S \subseteq M'$$

Hence, S is a finitely generated R-module if R is Noetherian, and it is free of rank n if R is a Principal Ideal Domain.

Hence, the integral closure over a larger field that is a finite extension shall only extend the integral closure by a relatively controlled manner. The more condition on R the better the control.

We are usually considering $\mathcal{O}_F$ for some number field $F/\mathbb{Q}$, the generality is to work over the cases that are less nice (as shall be done in algebraic geometry[6], see [25]). To see this result more concretely, it is worth stating the following immediate corollary:

Corollary 50.1.33: $\mathcal{O}_K$ is a Free $\mathbb{Z}$-Module

Let $F/\mathbb{Q}$ be a number field of degree n. Then $\mathcal{O}_F$ is a free $\mathbb{Z}$-module of degree n.

***Proof*:**
Of proposition 50.1.32
Let $K = K(R)$ and let $B = \{\beta_1, \beta_2, ..., \beta_n\}$ be a basis for F over K. We shall use this basis to squish S between two finitely generated R-modules (note that S is an R-module since S/R is an integral extension)

To define the R-module M, proposition 50.1.7 gives, for each i, a nonzero $d_i \in R$ with $d_i\beta_i \in S$, and $d = d_1 \cdots d_n \neq 0$ satisfies $d\beta_i \in S$ for every i. As $d \neq 0$, $dB = \{d\beta_1, d\beta_2, ..., d\beta_n\}$ is still a K-basis for F. Now, consider

$$\langle d\beta_1, d\beta_2, ..., d\beta_n \rangle_R = M$$

Since S is naturally an R-module and $d\beta_i \in S$, we have that $M \subseteq S$. Without loss of generality, we may now assume that $\beta_i \in S$ for all $1 \leq i \leq n$, that is $B \subseteq S$ and is a K-basis for F.

For the second R-module, define: the *integral trace dual*

$$^*M = M^{\mathrm{tr}\vee} = \left\{ b \in F \;\middle|\; \forall \ell \in M, \mathrm{tr}_{F/K}(b\ell) \in R \right\}$$

The extension F/K is separable by hypothesis, so the trace pairing is nondegenerate (proposition 19.6.31) and there is a dual K-basis $B' = \{\beta'_1, ..., \beta'_n\}$ of F given by $\mathrm{tr}(\beta_i\beta'_j) = \delta_{ij}$. Both modules are free of rank n over R, so in particular $M \cong_R M^{\mathrm{tr}\vee}$. This $M^{\mathrm{tr}\vee}$ is the module called M' in the statement.

The key result we shall prove is:

$$M = R\beta_1 + R\beta_2 + \cdots + R\beta_n \subseteq S \subseteq R\beta'_1 + R\beta'_2 + \cdots + R\beta'_n = M^{\mathrm{tr}\vee} \tag{50.3}$$

The first inclusion has already been proved, hence we show the second inclusion. Let $b \in S$ be

[6]The integral points of curves shall often have more nuanced behaviour

arbitrary. Since $S \subseteq F$ and B' is a basis for F, we may write b as

$$b = \sum_i b_i \beta_i' \qquad b_i \in K$$

If we show that each $b_i \in R$, we are done. First, Since $\beta_i, b \in S$, their product is in S since S is a ring, $b\beta_i \in S$, hence $\mathrm{tr}_{F/K}(b\beta_i) \in R$ for each i since S is integral over R. Computing, we get:

$$\mathrm{tr}(b\beta_i) = \mathrm{tr}(\sum_j b_j \beta_j' \beta_i) = \sum_j b_j \mathrm{tr}(\beta_j' \beta_i) = \sum_j b_j \delta_{ij} = b_i$$

Hence, $b_i \in R$, showing equation (50.3). If R is Noetherian, then $M^{\mathrm{tr}\vee}$ is a Noetherian R-module, and hence S would be finitely generated. If furthermore R is a Principal Ideal Domain, then any submodule of a free module (over a PID) is free, and S is free of rank less than or equal to n. Since it contains a free R-module of rank n, it has to be free rank greater than or equal to n, and so it has rank n as an R-module, completing the proof.

Note that this implies that if $\mathcal{O}_K$ is a PID and L/K a separable extension where $K = K(\mathcal{O}_K)$, then *every* nonzero finitely generated $\mathcal{O}_L$-module is a free $\mathcal{O}_K$-module of rank $[L : K]$.

Corollary 50.1.34: Maximality of Ring Of Integers for Number Fields

The ring of integers of a number field L is the largest subring that is finitely generated as a $\mathbb{Z}$-module.

***Proof*:**
By the above proposition, $\mathcal{O}_L$ is finitely generated as a $\mathbb{Z}$-module If $B \subseteq L$ is a subring that is also a finitely generated $\mathbb{Z}$-submodule, then every element of B is integral over $\mathbb{Z}$ (proposition 26.1.4(3)). Hence, $B \subseteq \mathcal{O}_L$.

With 50.1.32, we now have an "upper bound" on how far away a ring of integers is form simply being $\mathbb{Z}[\alpha]$ where $K = \mathbb{Q}(\alpha)$.

Definition 50.1.35: Integral Trace Dual

Let R be a normal integral domain, $K = K(R)$, L/K a finite separable extension, $S = \overline{R}^L$. Then the *integral trace dual* of S is

$$^*S = \left\{ b \in L \;\middle|\; \forall \ell \in S, \mathrm{tr}_{L/K}(b\ell) \in R \right\}$$

Example 50.1.36: Finding Integral Trace Dual

Let $K = \mathbb{Q}(\sqrt{5})$ considered as an extension $K/\mathbb{Q}$ so that $R = \mathbb{Z}$. Then we know that $L = \langle 1, \sqrt{5} \rangle \subseteq \mathcal{O}_K$. Let's try to bound by above the elements of $\mathcal{O}_K$. Let $b = r + s\sqrt{5} \in \mathbb{Q}(\sqrt{5})$ be an arbitrary element. Then:

$$\mathrm{tr}(b \cdot 1) = 2r \qquad r(b\sqrt{5}) = 10s$$

Hence, if $2r \in \mathbb{Z}$ and $10s \in \mathbb{Z}$, we get:

$$^*\mathcal{O}_K = \left\langle \frac{1}{2}, \frac{\sqrt{5}}{10} \right\rangle_{\mathbb{Z}}$$

Note that $^*\mathcal{O}_K$ is bigger than $\mathcal{O}_K$, for example $1/2 \notin \mathcal{O}_K$. By similar reasoning, we can check that $\frac{1}{\sqrt{5}} \in {}^*\mathcal{O}_K$, but it can be verified that it is not in $\mathcal{O}_K$, and so $\mathcal{O}_K^\vee \neq \mathcal{O}_K$. This does not contradict corollary 50.1.34 as $^*\mathcal{O}_K$ is *not* a subring (note that $1/2 \cdot 1/2 \notin {}^*\mathcal{O}_K$). Note however that they are both still rank 2.

Note that separability is a necessary hypothesis to insure the non-degeneracy of the trace-pairing, meaning this result works at least over over number fields, function fields, and perfect fields[7]. Naturally, if R is not a Principal Ideal Domain, then S need not be a free R-module. For now, we shall always let $R = \mathbb{Z}$ so that $K = \mathbb{Q}$ and $F/\mathbb{Q}$ is a number field. Note that we are only working with the addition structure of $\mathcal{O}_K$, while $\mathcal{O}_K$ is a ring. Thus, when talking about generators as a $\mathbb{Z}$-module, it must not be confounded with a set of generators for the ring. For example $(\alpha) \subseteq \mathcal{O}_K$ is a principal ideal and hence generated by a single element, but it may be generated by many elements as a $\mathbb{Z}$-module.

Definition 50.1.37: Integral Basis

Let $K/\mathbb{Q}$ be a number field. Then a $\mathbb{Z}$-basis for $\mathcal{O}_K$ is called an *integral basis* for K.

The previous proposition also gives more motivation for squaring the determinant in the definition of the discriminant. By corollary 50.1.27, if $(\alpha_1, \alpha_2, ..., \alpha_n)$ is a $\mathbb{Z}$-basis for $\mathcal{O}_F$, then $\text{disc}_{F/\mathbb{Q}}(\alpha_1, \alpha_2, ..., \alpha_n) \in \mathbb{Z}$ and any change of basis A must map to a unit, hence $\det(A) \in \mathbb{Z}^\times = \{-1, 1\}$. Squaring thus guarantees that the discriminant is basis independent for rings of integers. Now that we have explicitly found that $\mathcal{O}_K$ is a finitely generated $\mathbb{Z}$-module in the case of K being a number field, the term *field discriminant*, or just *discriminant* for short, shall imply that the input is an integral basis for $\mathcal{O}_K$, unless explicitly stated otherwise:

Definition 50.1.38: Discriminant For Ring of Integers

Let $K/\mathbb{Q}$ be a number field. Then if $A = \{\alpha_1, \alpha_2, ..., \alpha_n\}$ is an integral basis for $\mathcal{O}_K$, then:

$$d_K := \text{disc}(\mathcal{O}_K) := \text{disc}_{K/\mathbb{Q}}(A) = \text{disc}(\mathcal{O}_K)$$

is the *field discriminant* of K. It is sometimes also denoted $\text{disc}(K)$ if clear from context.

The discriminant can be thought of as capturing some information on how far $\mathcal{O}_K$ is from being
Thus, in example 50.1.25 where $K = \mathbb{Q}(\sqrt{m})$, we have:

$$d_K = \begin{cases} 4m & m \equiv 2, 3 \bmod 4 \\ m & m \equiv 1 \bmod 4 \end{cases}$$

A field K has many bases, not all of them bases for $\mathcal{O}_K$. The discriminants of a free $\mathbb{Z}$-module of rank n in K and of a subgroup of finite index in it differ by the square of the index:

[7] fields of positive characteristic may require some extra work

Proposition 50.1.39: Discriminant And Comparing Basis

Let K be a number field of degree n, let $B \subseteq K$ be a free $\mathbb{Z}$-module with $\mathbb{Z}$-basis $\beta_1, \ldots, \beta_n$, and let $A \subseteq B$ be a $\mathbb{Z}$-submodule of finite index (i.e. $[B : A] < \infty$). Then A is free of rank n, and if $\alpha_1, \ldots, \alpha_n$ is a $\mathbb{Z}$-basis of A and $T \in M_n(\mathbb{Z})$ is the matrix with $\alpha_i = \sum_j T_{ij}\beta_j$, then $[B : A] = |\det(T)|$ and

$$\operatorname{disc}(A) = [B : A]^2 \operatorname{disc}(B)$$

where $\operatorname{disc}(A) = \operatorname{disc}_{K/\mathbb{Q}}(\alpha_1, \ldots, \alpha_n)$ and $\operatorname{disc}(B) = \operatorname{disc}_{K/\mathbb{Q}}(\beta_1, \ldots, \beta_n)$.

***Proof*:**

The group A is free of rank at most n (theorem 14.1.5), and its rank is n: if $m = [B : A]$, then $mB \subseteq A$ by theorem 3.3.1, and mB is free of rank n. Let α, β and T be as in the statement. By theorem 13.2.25, applied over the Euclidean domain $\mathbb{Z}$, the matrix T is equivalent to $\operatorname{diag}(d_1, \ldots, d_n)$ for integers d_i, some possibly 0. That book defines equivalence for matrices over a field, so we record what its proof gives over $\mathbb{Z}$. Read over $\mathbb{Z}$, the proof takes a nonzero entry of least valuation, here the absolute value, among the matrices reachable from T by integer row and column operations, that is, swaps of two rows or of two columns and additions of an integer multiple of one row or column to another, and it reaches the normal form by finitely many such operations. Each such operation is multiplication on the left or on the right by a matrix in $M_n(\mathbb{Z})$ whose inverse, the matrix of the reverse operation, also lies in $M_n(\mathbb{Z})$. So there are matrices $U, V \in M_n(\mathbb{Z})$, invertible over $\mathbb{Z}$, with $UTV = \operatorname{diag}(d_1, \ldots, d_n)$. The determinants of U and V are ± 1, since $\det(U)\det(U^{-1}) = 1$ in $\mathbb{Z}$ (proposition 13.4.7). Put $\alpha'_i = \sum_j U_{ij}\alpha_j$ and $\beta'_i = \sum_j (V^{-1})_{ij}\beta_j$. As U and V^{-1} are invertible over $\mathbb{Z}$, these are $\mathbb{Z}$-bases of A and B, and $\alpha'_i = d_i\beta'_i$ for each i. Hence

$$B/A = \left(\bigoplus_i \mathbb{Z}\beta'_i\right) \Big/ \left(\bigoplus_i \mathbb{Z}d_i\beta'_i\right) \cong \bigoplus_i \mathbb{Z}/d_i\mathbb{Z}$$

This group is finite, so no d_i is 0, and it has $|d_1 \cdots d_n| = |\det(UTV)| = |\det(T)|$ elements (proposition 13.4.7). So $[B : A] = |\det(T)|$.

Let $\sigma_1, \ldots, \sigma_n$ be the embeddings of K into $\mathbb{C}$. Applying σ_k to $\alpha_i = \sum_j T_{ij}\beta_j$ shows that $(\sigma_k(\alpha_i))_{k,i} = (\sigma_k(\beta_j))_{k,j}\, T^t$, so by definition 50.1.24 and proposition 13.4.7,

$$\operatorname{disc}(A) = \det(T)^2 \operatorname{disc}(B) = [B : A]^2 \operatorname{disc}(B)$$

as we sought to show.

Corollary 50.1.40: Subset And Same Discriminant, Then Equal

Let $F/\mathbb{Q}$ be a number field of degree n, let $A \subseteq F$ be a free $\mathbb{Z}$-module of rank n with $\operatorname{disc}(A) \neq 0$, and let $B \subseteq A$ be a subgroup of finite index with $\operatorname{disc}(A) = \operatorname{disc}(B)$. Then $B = A$. Hence, one may use discriminants to identify free $\mathbb{Z}$-modules of finite rank.

***Proof*:**
By proposition 50.1.39, $\text{disc}(B) = [A : B]^2\text{disc}(A)$. As $\text{disc}(A) = \text{disc}(B) \neq 0$, $[A : B]^2 = 1$, so $[A : B] = 1$ and $B = A$, as claimed.

Corollary 50.1.41: Isomorphism Check Of Number Fields

Let K, K' be number fields. If $d_K \neq d_{K'}$, then $K \ncong K'$.

***Proof*:**
Let $\varphi\colon K \to K'$ be an isomorphism of number fields. An element of K and its image under φ are roots of the same polynomials with integer coefficients, so $\varphi(\mathcal{O}_K) \subseteq \mathcal{O}_{K'}$ and $\varphi^{-1}(\mathcal{O}_{K'}) \subseteq \mathcal{O}_K$ (definition 50.1.3). So if $\omega_1, \ldots, \omega_n$ is an integral basis of $\mathcal{O}_K$, then $\varphi(\omega_1), \ldots, \varphi(\omega_n)$ is an integral basis of $\mathcal{O}_{K'}$. The embeddings of K' into $\mathbb{C}$ are the maps $\sigma \circ \varphi^{-1}$ with σ an embedding of K, so by definition 50.1.24 and definition 50.1.38

$$d_{K'} = \det\left(\sigma_k\varphi^{-1}(\varphi(\omega_i))\right)^2 = \det\left(\sigma_k(\omega_i)\right)^2 = d_K$$

Hence isomorphic number fields have equal discriminants, which is the contrapositive of the statement.

Note that it is possible that there are multiple fields with the same discriminant:

Example 50.1.42: Same Discriminant, Different Fields
Take $\mathbb{Q}(\alpha), \mathbb{Q}(\beta), \mathbb{Q}(\gamma)$ where

$$a^3 - 18\alpha - 6 = 0 \qquad \beta^3 - 36\beta - 78 = 0 \qquad \gamma^3 - 58\gamma - 150 = 0$$

Then each has discriminant 22356, but these fields are not isomorphic (as shall be shown in example 50.4.20)

It should be noted that there are only finitely many fields for each discriminant value, however we shall not prove this fact[8]

The next couple of theorems give some computational tools on finding the ring of integers:

Proposition 50.1.43: Computation Of Dual For Ring Of Integers

Let K be a number field of degree n with a $\mathbb{Q}$-basis $\alpha_1, \alpha_2, ..., \alpha_n$ of algebraic integers, and let $d = \text{disc}_{K/\mathbb{Q}}(\alpha_1, \alpha_2, ..., \alpha_n)$. Then every $\alpha \in \mathcal{O}_K$ can be expressed as:

$$\frac{m_1\alpha_1}{d} + \cdots + \frac{m_n\alpha_n}{d}$$

where $m_i \in \mathbb{Z}$ and each m_i^2 is divisible by d $(d|m_i^2)$

[8] For those interested, it is the *Hermite-Minkowski's Theorem*

***Proof*:**
Step 1: the discriminant. Let $\sigma_1, \dots, \sigma_n$ be the embeddings of K into $\mathbb{C}$ and $S = (\sigma_i(\alpha_j))_{ij}$, with $\delta = \det(S)$. By definition 50.1.24, $d = \delta^2$, which is a nonzero integer by corollary 50.1.28 and corollary 50.1.27.

Step 2: Cramer's rule. Write $\alpha = \sum_j x_j \alpha_j$ with $x_j \in \mathbb{Q}$. Applying σ_i gives $\sigma_i(\alpha) = \sum_j x_j \sigma_i(\alpha_j)$, so the column $s = (\sigma_i(\alpha))_i$ equals $\sum_k x_k S_k$, where S_k is the kth column of S. Let y_j be the determinant of S with its jth column replaced by s. By multilinearity and the alternating property (proposition 13.4.6), $y_j = \sum_k x_k \det(S \text{ with column } j \text{ replaced by } S_k) = x_j \delta$, the terms with $k \neq j$ having two equal columns.

Step 3: integrality. Each σ_i maps algebraic integers to algebraic integers, as an element and its image are roots of the same polynomials over $\mathbb{Z}$, so the entries of S and s are algebraic integers. By the expansion of the determinant (definition 13.4.5), δ and y_j are sums of products of these entries, hence algebraic integers (corollary 26.1.6). Put $m_j = dx_j \in \mathbb{Q}$. Then $m_j = \delta^2 x_j = \delta y_j$ and $m_j^2/d = (\delta x_j)^2 = y_j^2$ are algebraic integers, and rational, so they lie in $\mathbb{Z}$ by lemma 50.1.5 and theorem 50.1.9(1). So $\alpha = \sum_j (m_j/d)\alpha_j$ with $m_j \in \mathbb{Z}$ and $d | m_j^2$, completing the proof.

Hence, for any $\mathcal{O}_K$, if $\alpha_1, \alpha_2, ..., \alpha_n$ is a basis for $K/\mathbb{Q}$

$$\bigoplus \alpha_i \mathbb{Z} \subseteq \mathcal{O}_K \subseteq \bigoplus \frac{\alpha_i}{d} \mathbb{Z}$$

And if $K = \mathbb{Q}(\alpha)$ so that $1, \alpha, ..., \alpha^{n-1}$ is a basis for K, then by proposition 50.1.29 $d = \prod_{i<j} (\alpha_i - \alpha_j)^2$ and:

$$\mathbb{Z}[\alpha] \subseteq \mathcal{O}_K \subseteq \frac{1}{d} \mathbb{Z}[\alpha]$$

Note that in general, $\mathbb{Z}[\alpha] \neq \mathcal{O}_K$. A counter-example shall be given in example 50.4.29. In the special case where $\mathbb{Z}[\alpha] = \mathcal{O}_K$, we give such a number ring a name:

Definition 50.1.44: Monogenic Number Ring

Let $K/\mathbb{Q}$ be a number field, $\mathcal{O}_K$ be the associated number ring, and α the primitive element so that $K = \mathbb{Q}(\alpha)$. Then if

$$\mathbb{Z}[\alpha] = \mathcal{O}_K$$

Then $\mathcal{O}_K$ is called *monogenic* and is said to be a *monogenic number ring.*

Since all number fields are monogenic, that is $K = \mathbb{Q}(\alpha)$ for some appropriate α, it is reasonable to ask if $\mathcal{O}_K$ can be expressed using α. The following theorem gives this structure:

Theorem 50.1.45: Basis For Ring Of Integers

Let $\alpha \in \mathcal{O}_k$ and suppose α has degree n over $\mathbb{Q}$. Then there exists $d_1, d_2, ..., d_{n-1} \in \mathbb{Z}$, and monic polynomial $f_i \in \mathbb{Z}[x]$ of degree i for $1 \leq i \leq n-1$ such that

$$\mathcal{O}_K = \mathbb{Z} \oplus \frac{f_1(\alpha)}{d_1}\mathbb{Z} \oplus \cdots \oplus \frac{f_{n-1}(\alpha)}{d_{n-1}}\mathbb{Z}$$

is an integral basis where

$$d_1 \big| d_2 \big| \cdots \big| d_{n-1}$$

and the d_i's are unique.

***Proof*:**

Since $\alpha \in \mathcal{O}_K$ has degree n over $\mathbb{Q}$, we have $K = \mathbb{Q}(\alpha)$ and $n = [K : \mathbb{Q}]$. Put $d = \operatorname{disc}_{K/\mathbb{Q}}(1, \alpha, \ldots, \alpha^{n-1})$, an integer by corollary 50.1.27 and nonzero by corollary 50.1.28. For $1 \leq k \leq n$ set

$$F_k = \mathbb{Z}\frac{1}{d} \oplus \mathbb{Z}\frac{\alpha}{d} \oplus \cdots \oplus \mathbb{Z}\frac{\alpha^{k-1}}{d} \qquad R_k = \mathcal{O}_K \cap F_k$$

The two extreme cases are $R_1 = \mathbb{Z}$, because $F_1 = \frac{1}{d}\mathbb{Z} \subseteq \mathbb{Q}$ and $\mathcal{O}_K \cap \mathbb{Q} = \mathcal{O}_{\mathbb{Q}} = \mathbb{Z}$ by lemma 50.1.5, and $R_n = \mathcal{O}_K$, because proposition 50.1.43 applied to the basis $1, \alpha, \ldots, \alpha^{n-1}$ places every element of $\mathcal{O}_K$ inside F_n.

The construction is by induction on k: there are $d_1 \big| d_2 \big| \cdots \big| d_{k-1}$ in $\mathbb{Z}$ and monic $f_i \in \mathbb{Z}[x]$ with $\deg f_i = i$ such that $1, f_1(\alpha)/d_1, \ldots, f_{k-1}(\alpha)/d_{k-1}$ is a $\mathbb{Z}$-basis of R_k. For $k = 1$ the element 1 is a basis of $R_1 = \mathbb{Z}$, and we set $f_0 = 1$ and $d_0 = 1$. Assume the claim for some $k < n$ and let $\pi : F_{k+1} \to \mathbb{Z}\frac{\alpha^k}{d}$ be the projection onto the last summand. Restricted to R_{k+1} its kernel is $R_{k+1} \cap F_k = R_k$ and its image is a subgroup of an infinite cyclic group. The image is nonzero, since $\alpha^k \in \mathcal{O}_K$ and $\alpha^k = d \cdot \frac{\alpha^k}{d} \in F_{k+1}$ give $\alpha^k \in R_{k+1}$ with $\pi(\alpha^k) \neq 0$. So $\pi(R_{k+1})$ is infinite cyclic, generated by $\pi(\beta)$ for some $\beta \in R_{k+1}$, and the exact sequence

$$0 \to R_k \to R_{k+1} \xrightarrow{\pi} \pi(R_{k+1}) \to 0$$

has free right-hand term, hence splits. Therefore $R_{k+1} = R_k \oplus \mathbb{Z}\beta$, and adjoining β to the basis of R_k gives a $\mathbb{Z}$-basis of R_{k+1}.

It remains to put β in the stated shape. The element $\gamma := \alpha f_{k-1}(\alpha)/d_{k-1}$ is a product of two elements of $\mathcal{O}_K$, and it lies in the $\mathbb{Q}$-span of $1, \alpha, \ldots, \alpha^k$ because f_{k-1} is monic of degree $k-1$. Any element of $\mathcal{O}_K$ in that span lies in F_{k+1}: by $R_n = \mathcal{O}_K$ its coordinates against $1, \alpha, \ldots, \alpha^{n-1}$ lie in $\frac{1}{d}\mathbb{Z}$, and the coordinates in degrees above k vanish. So $\gamma \in R_{k+1}$ and $\pi(\gamma) = \alpha^k/d_{k-1}$. Hence $\alpha^k/d_{k-1} = m\pi(\beta)$ for some nonzero $m \in \mathbb{Z}$, and after replacing β by $-\beta$ if needed we may take $m > 0$. Put $d_k := md_{k-1}$, so that $d_{k-1} \big| d_k$ and $\pi(\beta) = \alpha^k/d_k$. Writing $\beta = (b_0 + b_1\alpha + \cdots + b_k\alpha^k)/d$ with $b_i \in \mathbb{Z}$ and reading off the top coordinate gives $b_k d_k = d$, so

$$f_k(x) := \frac{d_k}{d}\left(b_0 + b_1 x + \cdots + b_k x^k\right)$$

is monic of degree k with $f_k(\alpha) = d_k\beta$.

The coefficients of f_k are so far only rational. Since $f_k(\alpha)/d_{k-1} = m\beta \in \mathcal{O}_K$, the element

$$\gamma' := \frac{f_k(\alpha) - \alpha f_{k-1}(\alpha)}{d_{k-1}} = m\beta - \gamma$$

lies in R_{k+1} and satisfies $\pi(\gamma') = m\pi(\beta) - \pi(\gamma) = 0$, so $\gamma' \in R_k$. Expanding γ' in the inductive basis, $\gamma' = \sum_{i=0}^{k-1} a_i f_i(\alpha)/d_i$ with $a_i \in \mathbb{Z}$, and multiplying through by d_{k-1} using $d_i \mid d_{k-1}$ gives $\gamma' = g(\alpha)/d_{k-1}$ for

$$g(x) = \sum_{i=0}^{k-1} a_i \frac{d_{k-1}}{d_i} f_i(x) \in \mathbb{Z}[x] \qquad \deg g \le k-1$$

Now $f_k(x) - x f_{k-1}(x) - g(x)$ has degree at most $k-1 < n$ and vanishes at α, which has degree n over $\mathbb{Q}$, so it is the zero polynomial. Thus $f_k = x f_{k-1} + g \in \mathbb{Z}[x]$, monic of degree k, and $\beta = f_k(\alpha)/d_k$. Taking $k = n$ closes the induction and produces the stated decomposition of $\mathcal{O}_K$.

For uniqueness, let $V_k = \mathbb{Q} + \mathbb{Q}\alpha + \cdots + \mathbb{Q}\alpha^k$ and suppose $1, f_1(\alpha)/d_1, \ldots, f_{n-1}(\alpha)/d_{n-1}$ is any $\mathbb{Z}$-basis of $\mathcal{O}_K$ of the stated shape. Since $\deg f_i = i$ exactly, an integral combination $\sum_i a_i f_i(\alpha)/d_i$ lies in V_k if and only if $a_i = 0$ for $i > k$, so

$$\mathcal{O}_K \cap V_k = \mathbb{Z} \oplus \frac{f_1(\alpha)}{d_1}\mathbb{Z} \oplus \cdots \oplus \frac{f_k(\alpha)}{d_k}\mathbb{Z}$$

The left-hand side does not refer to the chosen basis. Applying to it the functional $\pi_k : V_k \to \mathbb{Q}$ that reads off the coefficient of α^k, and using that $\pi_k(f_i(\alpha)/d_i) = 0$ for $i < k$ while $\pi_k(f_k(\alpha)/d_k) = 1/d_k$, gives $\pi_k(\mathcal{O}_K \cap V_k) = \frac{1}{d_k}\mathbb{Z}$. So the ideal $d_k\mathbb{Z}$ depends only on $\mathcal{O}_K$ and α, which determines each d_k up to sign. Replacing d_k by $-d_k$ replaces the basis element by its negative and keeps f_k monic, so the d_k are unique once taken positive.

Example 50.1.46: Ring Of Integers Of Cubic Extension

Let $K = \mathbb{Q}(\sqrt[3]{2})$ and $\alpha = \sqrt[3]{2}$. We want to find $\mathcal{O}_K$. First $\operatorname{rank}\mathcal{O}_K = 3$ since $[K : \mathbb{Q}] = 3$, and $L = \mathbb{Z}[\sqrt[3]{2}] \subseteq \mathcal{O}_K$. If A is the change of basis from L to $\mathcal{O}_K$, then $\det(A) = [\mathcal{O}_K : \mathbb{Z}[\alpha]]$[a]. Thus, by doing a change of basis from $\mathbb{Z}[\alpha]$ to $\mathcal{O}_K$ by A, we get that:

$$\operatorname{disc}(\mathbb{Z}[\alpha]) = [\mathcal{O}_K : \mathbb{Z}[\alpha]]^2 \operatorname{disc}(\mathcal{O}_K)$$

Thus, computing the discriminant of the left hand side we get:

$$\operatorname{disc}(\mathbb{Z}[\alpha]) = \det \begin{pmatrix} 3 & 0 & 0 \\ 0 & 0 & 6 \\ 0 & 6 & 0 \end{pmatrix} = -3 \cdot 36 = -(2^2 \cdot 3^2) \cdot 3 = -108$$

giving us that $[\mathcal{O}_K : \mathbb{Z}[\alpha]]^2 \mid 108 \Rightarrow [\mathcal{O}_K : \mathbb{Z}[\alpha]] \mid 2 \cdot 3 = 6$. If we show the index is 1, the proof is done. We shall prove the contradiction for the case of $[\mathcal{O}_K : \mathbb{Z}[\alpha]] = 3$, the proof for $[\mathcal{O}_K : \mathbb{Z}[\alpha]] = 2$ is similar, and from that we can also conclude that $[\mathcal{O}_K : \mathbb{Z}[\alpha]] \nmid 6$.

Let's say $[\mathcal{O}_K : \mathbb{Z}[\alpha]] = 3$. Then $\mathcal{O}_K/\mathbb{Z}[\alpha] \cong \mathbb{Z}/3\mathbb{Z}$. Any element $\beta \in \mathcal{O}_K$ lands in one of the cosets of $\mathcal{O}_K/\mathbb{Z}[\alpha]$ which implies that $a, b, c \in \frac{1}{3}\mathbb{Z}$. We want to show that a, b, c must be integers (lands in the zero coset). Since the ring of integers is closed under subtraction, we may without loss of generality subtract the non-fractional part of any element β we choose so that $a, b, c \in \{-1, 0, 1\}$[b].

Hence we take the norm of $\beta = (a/3) + (b/3)\alpha + (c/3)\alpha^2$

$$N(\beta) = \det \begin{pmatrix} a/3 & 2c/3 & 2b/3 \\ b/3 & a/3 & 2c/3 \\ c/3 & b/3 & a/3 \end{pmatrix} = \frac{1}{27}(a^3 + 2b^2 + 4c^3 - 6abc)$$

Since β is algebraic, $N(\beta) \in \mathbb{Z}$ meaning $27 \Big| (a^3 + 2b^2 + 4c^3 - 6abc)$. But, unless $a = b = c = 0$:

$$|a^3 + 2b^2 + 4c^3 - 6abc| \leq 15$$

showing that no such combination of a, b, c exist, meaning β is an algebraic integer if $a, b, c \in \mathbb{Z}$. A similar argument can be made in the case of $[\mathcal{O}_K : \mathbb{Z}[\alpha]] = 2$, hence we have that $\mathcal{O}_K = \mathbb{Z}[\alpha]$, completing the proof.

[a] since the index is finite, a basis for $\mathbb{Z}[\alpha]$ may be scaled to form a basis for $\mathcal{O}_K$, which translates to the determinant result

[b] Equivalently, any coset can be chosen to have such representatives

In some special cases, the ring of integers of more composite fields may be found given ring of integers of each respective field:

Theorem 50.1.47: Ring of Integers of Composites

Let $K_1/K, K_2/K$ be Galois with degree n and m and with coprime discriminants $d_{K_1} = d$ and $d_{K_2} = d'$ respectively. Let $L = K_1K_2$ and $K_1 \cap K_2 = K$. Let $\omega_1, \omega_2, ..., \omega_n$ and $\omega'_1, \omega'_2, ..., \omega'_m$ be an integral basis for K_1/K and K_2/K. Then $\omega_i\omega'_j$ is an integral basis for K_1K_2 with discriminant $(d_{K_1})^m(d_{K_2})^n = d^m(d')^n$, namely

$$\mathcal{O}_L = \mathcal{O}_{K_1}\mathcal{O}_{K_2}$$

***Proof*:**

As $K_1 \cap K_2 = K$, proposition 20.1.32 gives $\mathrm{Gal}_K(L) \cong \mathrm{Gal}_K(K_1) \times \mathrm{Gal}_K(K_2)$ through restriction, so $[L : K] = nm$. Under this isomorphism, $\mathrm{Gal}_{K_2}(L) = \{\sigma_1, \ldots, \sigma_n\}$ restricts bijectively onto $\mathrm{Gal}_K(K_1)$, $\mathrm{Gal}_{K_1}(L) = \{\tau_1, \ldots, \tau_m\}$ restricts bijectively onto $\mathrm{Gal}_K(K_2)$, and $\mathrm{Gal}_K(L)$ consists of the nm products $\sigma_k\tau_\ell$. The nm products $\omega_i\omega'_j$ span L over K (proposition 19.3.17), so they form a basis. As d and d' are coprime, $yd + zd' = 1$ for some $y, z \in \mathcal{O}_K$.

Step 1: the integral basis. Let $\alpha \in \mathcal{O}_L$, write $\alpha = \sum_{i,j} a_{ij}\omega_i\omega'_j$ with $a_{ij} \in K$, and put $\beta_j = \sum_i a_{ij}\omega_i \in K_1$, so that $\alpha = \sum_j \beta_j\omega'_j$. Each τ_ℓ fixes K_1, so $\tau_\ell(\alpha) = \sum_j \tau_\ell(\omega'_j)\beta_j$ for $1 \leq \ell \leq m$. That is, the column $a = (\tau_\ell(\alpha))_\ell$ is Tb, for the matrix $T = (\tau_\ell(\omega'_j))_{\ell,j}$ and the column $b = (\beta_j)_j$. As the τ_ℓ restrict to the K-embeddings of K_2, $\det(T)^2 = d'$ by definition 50.1.24. Let $T^{(j)}$ be T with its jth column replaced by a, which is the sum of the columns of T weighted by the $\beta_{j'}$. Multilinearity in that column and the vanishing of determinants with two equal columns (proposition 13.4.6) give $\det(T^{(j)}) = \beta_j \det(T)$. The entries of T and $T^{(j)}$ are algebraic integers, hence so are their determinants (corollary 26.1.6), and $d'\beta_j = \det(T)\det(T^{(j)})$ is an algebraic integer lying in K_1, that is, $d'\beta_j = \sum_i d'a_{ij}\omega_i \in \mathcal{O}_{K_1}$. As the ω_i form an integral basis of K_1/K, $d'a_{ij} \in \mathcal{O}_K$. Exchanging the roles of K_1 and K_2 gives $da_{ij} \in \mathcal{O}_K$, so $a_{ij} = yda_{ij} + zd'a_{ij} \in \mathcal{O}_K$. As every $\omega_i\omega'_j$ lies in $\mathcal{O}_L$, the $\omega_i\omega'_j$ form an integral basis of L/K, and $\mathcal{O}_L = \mathcal{O}_{K_1}\mathcal{O}_{K_2}$.

Step 2: the discriminant. As τ_ℓ fixes $\omega_i \in K_1$ and σ_k fixes $\tau_\ell(\omega'_j) \in K_2$,

$$\sigma_k\tau_\ell(\omega_i\omega'_j) = \sigma_k(\omega_i)\tau_\ell(\omega'_j)$$

Index the rows of $M = (\sigma_k\tau_\ell(\omega_i\omega'_j))$ by the pairs (ℓ, k) and its columns by the pairs (j, i), so that M is an $m \times m$ array of $n \times n$ blocks, the (ℓ, j) block being $\tau_\ell(\omega'_j)Q$ with $Q = (\sigma_k(\omega_i))_{k,i}$. Then $M = \operatorname{diag}(Q, \dots, Q)\, P$, where the (ℓ, j) block of P is $\tau_\ell(\omega'_j)E$ and E is the $n \times n$ identity matrix. Reordering the rows and the columns of P by the pairs (k, ℓ) and (i, j) turns it into $\operatorname{diag}(T, \dots, T)$, with n blocks, and changes its determinant at most by a sign (proposition 13.4.6). So by proposition 13.4.7 and proposition 13.4.8, and as $\det(Q)^2 = d$ by definition 50.1.24,

$$\operatorname{disc}(\omega_i\omega'_j) = \det(M)^2 = \det(Q)^{2m}\det(T)^{2n} = d^m(d')^n$$

as we sought to show.

For separable extensions that are not Galois, the hypothesis $K_1 \cap K_2 = K$ has to be replaced by the linear disjointness of K_1 and K_2 over K. If the discriminants are not relatively prime, then there is a partial generalization in the case where $K = \mathbb{Q}$:

Corollary 50.1.48: Ring of Integers of Composite, Partial Generalization

Let $K_1/\mathbb{Q}$ and $K_2/\mathbb{Q}$ be finite separable extensions with $L = K_1K_2$ of degree $[L : \mathbb{Q}] = [K_1 : \mathbb{Q}][K_2 : \mathbb{Q}]$, and let $d_1 = \operatorname{disc}(\mathcal{O}_{K_1})$ and $d_2 = \operatorname{disc}(\mathcal{O}_{K_2})$. Then

$$\mathcal{O}_L \subseteq \frac{1}{\gcd(d_1, d_2)}\mathcal{O}_{K_1}\mathcal{O}_{K_2}$$

***Proof*:**
Write $m = [K_1 : \mathbb{Q}]$ and $n = [K_2 : \mathbb{Q}]$, and fix integral bases $\alpha_1, \dots, \alpha_m$ of $\mathcal{O}_{K_1}$ and $\beta_1, \dots, \beta_n$ of $\mathcal{O}_{K_2}$ (corollary 50.1.33). By proposition 19.3.17 the mn products $\alpha_i\beta_j$ span L over $\mathbb{Q}$, so the degree hypothesis makes them a $\mathbb{Q}$-basis of L. They also span $\mathcal{O}_{K_1}\mathcal{O}_{K_2}$ as a $\mathbb{Z}$-module, since that ring consists of the finite sums of products ab with $a \in \mathcal{O}_{K_1}$ and $b \in \mathcal{O}_{K_2}$.

Let $\alpha \in \mathcal{O}_L$ and write

$$\alpha = \sum_{i,j}\frac{m_{ij}}{r}\alpha_i\beta_j$$

with $r \in \mathbb{Z}_{>0}$ the least common denominator of the rational coordinates, so that $m_{ij} \in \mathbb{Z}$ and $\gcd\left(r, \gcd_{i,j}(m_{ij})\right) = 1$. It suffices to prove $r \mid d_1$, since the same argument with the roles of K_1 and K_2 exchanged gives $r \mid d_2$, whence $r \mid \gcd(d_1, d_2)$ and $\alpha \in \frac{1}{\gcd(d_1,d_2)}\mathcal{O}_{K_1}\mathcal{O}_{K_2}$.

Restriction sends a $\mathbb{Q}$-embedding of L into $\mathbb{C}$ to the pair of its restrictions to K_1 and K_2, and this pair determines the embedding because L is generated by $K_1 \cup K_2$. Both sides are counted by proposition 19.6.17, giving $[L : \mathbb{Q}] = mn$ embeddings on the left and mn pairs on the right, so restriction is a bijection. In particular every embedding σ of K_1 extends to an embedding of L, still written σ, that fixes K_2 pointwise. Applying the m such extensions to the display above gives the m equations

$$\sigma(\alpha) = \sum_{i=1}^{m}\sigma(\alpha_i)x_i \qquad x_i := \sum_{j=1}^{n}\frac{m_{ij}}{r}\beta_j \in K_2$$

Let $\delta = \det(\sigma_k(\alpha_i))$, so $\delta^2 = \text{disc}_{K_1/\mathbb{Q}}(\alpha_1, \dots, \alpha_m) = d_1$ by definition 50.1.24 and definition 50.1.38, and $\delta \neq 0$ by corollary 50.1.28. Cramer's rule gives $x_i = \gamma_i/\delta$, where γ_i is the determinant obtained by replacing the ith column by the column of the $\sigma_k(\alpha)$. All entries of both determinants are algebraic integers, hence so are δ and every γ_i, and therefore

$$d_1 x_i = \delta^2 x_i = \delta \gamma_i$$

is an algebraic integer. It lies in K_2, so $d_1 x_i \in \mathcal{O}_{K_2}$ by lemma 50.1.5. Since the β_j are a $\mathbb{Z}$-basis of $\mathcal{O}_{K_2}$, every rational number $d_1 m_{ij}/r$ is an integer, that is r divides $d_1 m_{ij}$ for all i and j. Hence r divides $d_1 \gcd_{i,j}(m_{ij})$, and r is coprime to $\gcd_{i,j}(m_{ij})$, so $r \mid d_1$.

Example: Ring of Integers of Cyclotomic Field

Let's use the above results to show that if $K = \mathbb{Q}(\zeta_n)$ then $\mathcal{O}_K = \mathbb{Z}[\zeta_n]$, that is the ring of integers of K is monogenic. Besides quadratic extensions, this is so far the only other ring of integers we have classified (in particular since they are rather difficult to classify). We first require some lemmas:

Lemma 50.1.49: Cyclotomic Field Lemmas

Let $n = p^r$ where $n \geq 3$. Then:

1. $\mathbb{Z}[\zeta_n] = \mathbb{Z}[1 - \zeta_n]$ and $\text{disc}(\zeta_n) = \text{disc}(1 - \zeta_n)$
2. $\prod_{k \in (\mathbb{Z}/n\mathbb{Z})^\times} (1 - \zeta_n^k) = p$

***Proof*:**

1. Certainly $\mathbb{Z}[\zeta_n] = \mathbb{Z}[1 - \zeta_n]$ since $\zeta_n = 1 - (1 - \zeta_n)$, implying the discriminants are equal. Similarly, by proposition 50.1.29

$$\text{disc}(\zeta_n) = \prod_{r<s} (\alpha_r - \alpha_s)^2 = \prod_{r<s} ((1 - \alpha_r) - (1 - \alpha_s))^2 = \text{disc}(1 - \zeta_n)$$

2. By definition 19.7.2, $\Phi_n(x) = \prod_{k \in (\mathbb{Z}/n\mathbb{Z})^\times} (x - \zeta_n^k)$. By lemma 19.7.4, $x^{p^r} - 1 = \prod_{j=0}^{r} \Phi_{p^j}(x)$ and $x^{p^{r-1}} - 1 = \prod_{j=0}^{r-1} \Phi_{p^j}(x)$, so

$$\Phi_n(x) = \frac{x^{p^r} - 1}{x^{p^{r-1}} - 1} = 1 + x^{p^{r-1}} + x^{2p^{r-1}} + \cdots + x^{(p-1)p^{r-1}}$$

Setting $x = 1$ gives $\prod_k (1 - \zeta_n^k) = \Phi_n(1) = p$.

Proposition 50.1.50: Ring Of Integers Of Prime-Power Cyclotomic Field

Let $n = p^r$ and $K = \mathbb{Q}(\zeta_n)$. Then:

$$\mathcal{O}_K = \mathbb{Z}[\zeta_n]$$

***Proof*:**
If $n \leq 2$, then $K = \mathbb{Q}$ and $\mathcal{O}_K = \mathbb{Z} = \mathbb{Z}[\zeta_n]$, so let $n \geq 3$. Write $\lambda = 1 - \zeta_n$ and $m = \varphi(p^r)$. By lemma 50.1.49, $\mathbb{Z}[\lambda] = \mathbb{Z}[\zeta_n]$ and $\text{disc}(\lambda) = \text{disc}(\zeta_n)$. The minimal polynomial of ζ_n is $\Phi_n(x) = \prod_{k \in (\mathbb{Z}/n\mathbb{Z})^\times}(x - \zeta_n^k)$ (definition 19.7.2, proposition 19.7.7), so $[K : \mathbb{Q}] = m$ and $1, \lambda, \ldots, \lambda^{m-1}$ is a $\mathbb{Q}$-basis of $K = \mathbb{Q}(\lambda)$ consisting of algebraic integers. By proposition 50.1.43, every $\alpha \in \mathcal{O}_K$ can be written as

$$\alpha = \frac{n_1 + n_2\lambda + \cdots + n_m\lambda^{m-1}}{d}$$

with $n_j \in \mathbb{Z}$ and $d = \text{disc}(\zeta_n)$. By example 50.1.31, d divides $n^{\varphi(n)} = p^{rm}$, so $d = \pm p^s$ for some $s \geq 0$.

Suppose that $\mathcal{O}_K \neq \mathbb{Z}[\lambda]$, and pick $\alpha \in \mathcal{O}_K \setminus \mathbb{Z}[\lambda]$, written as above. Not all n_j are divisible by p^s, so the largest power p^t dividing all of them has $t < s$. Then $\pm p^{s-1-t}\alpha \in \mathcal{O}_K$ equals $\frac{1}{p}\sum_j n_j'\lambda^{j-1}$ with $n_j' = n_j/p^t \in \mathbb{Z}$, not all divisible by p. Let $i \leq m$ be the least index with $p \nmid n_i'$. The terms $\frac{n_j'}{p}\lambda^{j-1}$ with $j < i$ lie in $\mathbb{Z}[\lambda]$, so subtracting them shows that $\mathcal{O}_K$ contains

$$\beta = \frac{n_i'\lambda^{i-1} + n_{i+1}'\lambda^i + \cdots + n_m'\lambda^{m-1}}{p}$$

whose leading coefficient n_i' is prime to p.

By lemma 50.1.49, $p = \prod_k(1 - \zeta_n^k)$, the product over the m classes $k \in (\mathbb{Z}/n\mathbb{Z})^\times$, represented by positive integers. Each factor is $1 - \zeta_n^k = \lambda(1 + \zeta_n + \cdots + \zeta_n^{k-1})$, so $p/\lambda^m \in \mathbb{Z}[\zeta_n]$, and $p/\lambda^i = (p/\lambda^m)\lambda^{m-i} \in \mathbb{Z}[\zeta_n]$ as $i \leq m$. Hence

$$\frac{p\beta}{\lambda^i} = \frac{n_i'}{\lambda} + n_{i+1}' + n_{i+2}'\lambda + \cdots + n_m'\lambda^{m-1-i}$$

lies in $\mathcal{O}_K$, and subtracting the terms in $\mathbb{Z}[\lambda] \subseteq \mathcal{O}_K$ gives $n_i'/\lambda \in \mathcal{O}_K$, whose norm is an integer by corollary 50.1.14. The embeddings of K send ζ_n to the roots ζ_n^k of Φ_n, so $\text{Nm}_{K/\mathbb{Q}}(\lambda) = \prod_k(1 - \zeta_n^k) = p$ by corollary 50.1.13, and $\text{Nm}_{K/\mathbb{Q}}(n_i'/\lambda) = (n_i')^m/p$. So $p \mid (n_i')^m$, hence $p \mid n_i'$, contrary to the choice of i. Therefore $\mathcal{O}_K = \mathbb{Z}[\lambda] = \mathbb{Z}[\zeta_n]$, as we sought to show.

We now look to generalize to any cyclotomic field. The key idea is that the ring of integers of cyclotomic fields will be the composite of simpler ring of integers

Proposition 50.1.51: Ring of Integers of Cyclotomic Field

Let $K = \mathbb{Q}(\zeta_n)$ for any $n \in \mathbb{N}$. Then:

$$\mathcal{O}_K \cong \mathbb{Z}[\zeta_n]$$

***Proof*:**
We shall do a form of induction. This was proven if n is a prime power, so let's assume it's not so that we may write $n = n_1 n_2$ for relatively prime $n_1, n_2 > 1$. We shall work by induction on n_1, n_2. The base case was proposition 50.1.50, hence set:

$$\begin{aligned} \omega_1 &= \zeta_{n_1} & \omega_2 &= \zeta_{n_2} \\ K_1 &= \mathbb{Q}(\omega_1) & K_2 &= \mathbb{Q}(\omega_2) \\ \mathcal{O}_{K_1} &= \mathbb{Z}[\omega_1] & \mathcal{O}_{K_2} &= \mathbb{Z}[\omega_2] \end{aligned}$$

As $\zeta_n = e^{2\pi i/n}$ and $n = n_1 n_2$, we have $\zeta_n^{n_1} = \omega_2$ and $\zeta_n^{n_2} = \omega_1$. As $\gcd(n_1, n_2) = 1$, there are $r, s \in \mathbb{Z}$ with $rn_2 + sn_1 = 1$, and then

$$\zeta_n = \zeta_n^{rn_2 + sn_1} = \omega_1^r \omega_2^s$$

Thus $K = K_1 K_2$. Next, as we saw in example 50.1.31,

$$\operatorname{disc}(\omega_1) \big| n_1^{\varphi(n_1)} \qquad \operatorname{disc}(\omega_2) \big| n_2^{\varphi(n_2)}$$

and as $\gcd(n_1, n_2) = 1$, the discriminants of the integral bases $1, \omega_l, \ldots, \omega_l^{\varphi(n_l)-1}$ of $\mathcal{O}_{K_l} = \mathbb{Z}[\omega_l]$ are coprime. The fields K_1 and K_2 are Galois over $\mathbb{Q}$, being the splitting fields of $x^{n_1} - 1$ and $x^{n_2} - 1$ (theorem 19.5.13, corollary 19.6.8). By proposition 19.7.7, $[K : \mathbb{Q}] = \varphi(n) = \varphi(n_1)\varphi(n_2) = [K_1 : \mathbb{Q}][K_2 : \mathbb{Q}]$. With $E = K_1 \cap K_2$, an E-basis of K_2 spans $K = K_1 K_2$ over K_1 (proposition 19.3.17), so $[K : K_1] \leq [K_2 : E]$, and the tower law (theorem 19.3.7) gives $[K : \mathbb{Q}] \leq [K_1 : \mathbb{Q}][K_2 : \mathbb{Q}]/[E : \mathbb{Q}]$. Hence $K_1 \cap K_2 = \mathbb{Q}$, and theorem 50.1.47 gives

$$\mathcal{O}_K = \mathcal{O}_{K_1} \mathcal{O}_{K_2} = \mathbb{Z}[\omega_1]\mathbb{Z}[\omega_2] = \mathbb{Z}[\zeta_n]$$

as we sought to show.

Exercise 50.1.2

1. Generalize proposition 50.1.39 for modules over $\mathcal{O}_K$.
2. Give a counter-example where $\mathcal{O}_{KL} = \mathcal{O}_K \mathcal{O}_L$?

50.1.4 Lattice Structure: Geometry of Number Rings

An important word of warning must be given about free $\mathbb{Z}$-modules due to the existence of non-invertible elements. It is possible that A, B are two free $\mathbb{Z}$-module of rank 2, one contains the basis of the other, however $A \subsetneq B$! This is in contract to the case of modules over fields where if A, B are two k-vector-spaces of the same dimension and $A \subseteq B$, then $A = B$[9]. Even more behavior can happen: consider $\mathbb{Q} \otimes_{\mathbb{Z}} A$. Then this is a vector-space with a finite dimension. However, the dimension need not match the rank of A:

[9] $b \in B$ can be appropriately shrunk to a nonzero size so that its in A (since the dimensions are the same), and then we use closure of scalar multiplication

Example 50.1.52: Behavior of $\mathbb{Z}$-modules

1. Let $A = \langle (1,0),(0,1)\rangle_{\mathbb{Z}}$ and $B = \langle (1/2,0),(0,1/2)\rangle_{\mathbb{Z}}$. Then by construction they are both isomorphic as abelian groups to $\mathbb{Z}^2$, however $A \subsetneq B$.
2. Let A be a free $\mathbb{Z}$-module of rank 2. Then we may extend scalar to make A into a free $\mathbb{R}$-module. Either take $\mathbb{R} \otimes_{\mathbb{Z}} A$ or consider $\langle a_1, a_1\rangle_{\mathbb{R}}$ for some free generating set $\{a_1, a_2\}$. Then $\mathbb{R} \otimes_{\mathbb{Z}} A$ *need not be dimension 2.* For example, take
$$A = \langle (1,1),(\sqrt{2},\sqrt{2})\rangle_{\mathbb{Z}}$$
Then $\mathbb{R} \otimes_{\mathbb{Z}} A$ is one dimensional
3. By construction of $\mathcal{O}_k$, if $\langle \alpha_1, \alpha_2, ..., \alpha_n\rangle_{\mathbb{Z}} = \mathcal{O}_k$, then $\langle \alpha_1, \alpha_2, ..., \alpha_n\rangle_{\mathbb{Q}} = k$, Thus $\mathcal{O}_k$ is a little more than just a $\mathbb{Z}$-module. We shall explore this in this section.

The third example shows that the rank of the ring of integers more coincides with the dimension of the natural vector-space when extending the actions to a field. As was explored in chapter 13, [finite dimensional] vector spaces have easy visualizations using orthonormal bases. In chapter 10, this was used implicitly when it was intuited that $\mathbb{Z}[i]$ forms a nice square lattice in $\mathbb{Q}^2$. More generally, ring of integer $\mathcal{O}_K$ will form a lattice when embedded into an appropriate vector-space. To better visualize this lattice, it is easer to see it embedded into a direct sum of $\mathbb{R}$ and $\mathbb{C}$[10]. This has the extra advantage that these spaces have a well-defined notion of *measure* that gives us an area. We shall take advantage of tools from analysis to further enlighten the structure of rings of integers, however as a consequence an elementary level of topology and analysis will be assumed.

Let $n = [K : \mathbb{Q}]$ so that $\mathrm{Hom}_{\mathbb{Q}}(K, \mathbb{C}) = n$. Then every embedding of K into $\mathbb{C}$ is either embeds into $\mathbb{R}$ or does not (that is, either $K \cap (\mathbb{C} \setminus \mathbb{R}) = \emptyset$ or $\neq 0$). Let's call the former *real embeddings* and the latter *complex embeddings.* For a complex embedding $\tau \in \mathrm{Hom}_{\mathbb{Q}}(K, \mathbb{C})$, we may always find another embedding $\overline{\tau}$ since for any α where $p(\alpha) = 0$ for appropriate $p(x) \in \mathbb{Q}[x]$

$$0 = \overline{\tau}(0) = \overline{\tau}(p(\alpha)) = \tau(\overline{p(\alpha)}) = \tau(p(\overline{\alpha}))$$

showing that $\overline{\tau}$ maps roots to roots. Hence the degree n may be split into $n = r_1 + 2r_2$ where r_1 represents the amount of embeddings where the image σ_i is real:

$$\alpha_1, \alpha_2, ..., \alpha_{r_1}$$

while r_2 represents the embeddings that embedded into $\mathbb{C}$ is not strictly in $\mathbb{R}$, giving us a total list of embeddings:

$$\sigma_1, \sigma_2, ..., \sigma_{r_1}, \tau_1, \tau_2, ..., \tau_{r_2}, \overline{\tau_1}, ..., \overline{\tau_{r_2}}$$

[10]For those who may prefer $\overline{\mathbb{Q}}$ over $\mathbb{R}$ or $\mathbb{C}$, I would stipulate $\mathbb{R}$ and $\mathbb{C}$ are is a very natural object in this context: $\mathbb{R}$ is perhaps the only "natural" object for which a finite extension is an algebraic closure, this will have algebraic and geometric consequence when counting the number of embeddings of a field into the algebraically closed field $\mathbb{C}$

Definition 50.1.53: Archimedean Embedding

Let $K/\mathbb{Q}$ be a number field. Then its *Archimedean embedding* is defined as

$$\begin{aligned}\sigma :&K \hookrightarrow \mathbb{R}^{r_1} \oplus \mathbb{C}^{r_2}\\ &\alpha \mapsto (\sigma_1(\alpha), ..., \tau_{r_2}(\alpha))\end{aligned}$$

The space $\mathbb{R}^{r_1} \oplus \mathbb{C}^{r_2}$ is called the *Minkowski space*, and will be labeled $K_{\mathbb{R}}$.

Example 50.1.54: Archimedean Embedding

1. Trivially, $\mathbb{Q}_{\mathbb{R}} = \mathbb{R}$, and $\mathbb{C}_{\mathbb{R}}$ is not defined since $\mathbb{C}/\mathbb{Q}$ is not a finite extension.
2. Take $K = \mathbb{Q}(i)$ so that $\mathcal{O}_K = \mathbb{Z}[i]$. Then $\text{Gal}_{\mathbb{Q}}(\mathbb{Q}(i)) = \{\text{id}, c\}$ where c is the conjugate. Then K is simply the embedding of K into $\mathbb{C}$

   $$\sigma : K \hookrightarrow \mathbb{C}^1 \qquad k \mapsto k$$

   Notice the gaussian integers form the usual grid in $\mathbb{C}$.
3. Take $K = \mathbb{Q}(\sqrt{2}, \sqrt{3})$ Then $\text{Gal}_{\mathbb{Q}}(K) \cong \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z}$ corresponds to the conjugating each root separately. Then

   $$\begin{gathered}\sigma : K \mapsto \mathbb{R}^4\\ (a + b\sqrt{2} + c\sqrt{3} + d\sqrt{6})\\ \mapsto\\ (a + b\sqrt{2} + c\sqrt{3} + d\sqrt{6}, a - b\sqrt{2} + c\sqrt{3} + d\sqrt{6},\\ a + b\sqrt{2} - c\sqrt{3} + d\sqrt{6}, a - b\sqrt{2} - c\sqrt{3} + d\sqrt{6})\end{gathered}$$

Our goal is to show that $\sigma(\mathcal{O}_K)$ behaves like the just like $\mathbb{Z}[i]$ when embedded in $\mathbb{C}$. To characterize a lattice in higher dimensions, we define it in the following way:

Definition 50.1.55: [Integral] Lattice

Let V be a real vector space of dimension n with an inner product, for instance $\mathbb{R}^n$ with its standard inner product. Then a *lattice* in V is a subgroup $\Lambda \subseteq V$ satisfying any two of the following 3 properties:

1. Λ spans V as an $\mathbb{R}$-vector space ($\langle\Lambda\rangle_{\mathbb{R}} = V$)
2. Λ is discrete in the topological space V: there is an open ball around the origin that meets Λ only in the origin
3. Λ is a free $\mathbb{Z}$-module of rank n[a]

[a] some authors call such lattices *complete lattices*, and call the subgroups generated by fewer than n linearly independent vectors *lattices*

Lemma 50.1.56: Equivalence Of Conditions

Any two of these conditions implies the third. Moreover, every bounded subset of V contains only finitely many points of a lattice $\Lambda \subseteq V$.

***Proof*:**
Let $|\cdot|$ denote the norm of the inner product. Expanding $0 \leq |v - tw|^2$ at $t = \langle v, w\rangle / |w|^2$ gives the Cauchy-Schwarz inequality $|\langle v, w\rangle| \leq |v||w|$ for $w \neq 0$, and expanding $|v + w|^2$ then gives the triangle inequality $|v + w| \leq |v| + |w|$.

Step 1: (1) and (3) imply (2). Let $\ell_1, \ldots, \ell_n$ be a $\mathbb{Z}$-basis of Λ. These n vectors span the n-dimensional space V, so they form a basis. An inner product is nondegenerate, since $\langle y, y\rangle > 0$ for $y \neq 0$, so the matrix $G = (\langle \ell_i, \ell_j\rangle)$ is invertible (lemma 13.3.23). The vectors $\ell_j^* = \sum_k (G^{-1})_{kj} \ell_k$ satisfy $\langle \ell_i, \ell_j^*\rangle = (GG^{-1})_{ij}$, which is 1 for $i = j$ and 0 otherwise. So the coordinates of $v = \sum_i x_i \ell_i$ are $x_i = \langle v, \ell_i^*\rangle$, and $|x_i| \leq |v||\ell_i^*|$ by the Cauchy-Schwarz inequality. A nonzero $\gamma \in \Lambda$ has some coordinate x_i equal to a nonzero integer, so $1 \leq |\gamma||\ell_i^*|$. Hence the open ball of radius $1/\max_i |\ell_i^*|$ around 0 meets Λ only in 0.

Step 2: (2) and (3) imply (1). Let $\ell_1, \ldots, \ell_n$ be a $\mathbb{Z}$-basis of Λ and suppose they do not span V. Then they are linearly dependent over $\mathbb{R}$: $\sum_i a_i \ell_i = 0$ with $a_i \in \mathbb{R}$ not all zero. Let $M \geq 1$ be an integer with $1/M < \max_i |a_i|$. Consider the $M^n + 1$ points $(\{ka_1\}, \ldots, \{ka_n\}) \in [0, 1)^n$ for $k = 0, 1, \ldots, M^n$, where $\{y\} = y - \lfloor y \rfloor$. Dividing $[0, 1)^n$ into the M^n boxes $\prod_i [j_i/M, (j_i + 1)/M)$, two of these points, for some $k < k'$, lie in the same box. With $N = k' - k$ and $b_i = \lfloor k'a_i \rfloor - \lfloor ka_i \rfloor \in \mathbb{Z}$, we get $|Na_i - b_i| = |\{k'a_i\} - \{ka_i\}| < 1/M$ for every i. Not every b_i is 0, since otherwise $|a_i| < 1/(NM) \leq 1/M$ for every i. So $\gamma = \sum_i b_i \ell_i$ is a nonzero element of Λ, the ℓ_i being independent over $\mathbb{Z}$, and

$$|\gamma| = \left| \sum_i (b_i - Na_i) \ell_i \right| \leq \frac{1}{M} \sum_i |\ell_i|$$

As M can be taken arbitrarily large, every ball around 0 contains a nonzero element of Λ, so Λ is not discrete.

Step 3: (1) and (2) imply (3). Choose $r > 0$ with $|\gamma| \geq r$ for every $0 \neq \gamma \in \Lambda$. Then distinct elements of Λ are at distance at least r. As Λ spans V, it contains a basis $u_1, \ldots, u_n$ of V. Let $\Lambda_0 = \bigoplus_i \mathbb{Z} u_i \subseteq \Lambda$ and $P = \{\sum_i x_i u_i \mid 0 \leq x_i < 1\}$. Choose an integer $N \geq 1$ with $\frac{1}{N} \sum_i |u_i| < r$, and divide $[0, 1)^n$ into the N^n boxes $\prod_i [j_i/N, (j_i + 1)/N)$. If two elements $\sum_i x_i u_i$ and $\sum_i x_i' u_i$ of $\Lambda \cap P$ have coordinate vectors in the same box, the triangle inequality bounds the norm of their difference by $\sum_i |x_i - x_i'||u_i| < \frac{1}{N} \sum_i |u_i| < r$, so they are equal. Hence $\Lambda \cap P$ has at most N^n elements. Every $\gamma = \sum_i x_i u_i \in \Lambda$ equals $\sum_i \lfloor x_i \rfloor u_i + \sum_i \{x_i\} u_i$, where the second summand lies in $\Lambda \cap P$, a finite set. So Λ/Λ_0 is finite, of order q say, and $q\Lambda \subseteq \Lambda_0$ by theorem 3.3.1. Thus $\Lambda \subseteq \frac{1}{q}\Lambda_0$, a free $\mathbb{Z}$-module of rank n, so Λ is free of rank at most n (theorem 14.1.5), and of rank n as it contains Λ_0.

Step 4: bounded sets. A lattice Λ satisfies (1) and (3), so it has a $\mathbb{Z}$-basis $\ell_1, \ldots, \ell_n$ that is a basis of V, with vectors ℓ_i^* as in Step 1. A bounded subset of V lies in a ball $\{v \mid |v| \leq \rho\}$, and

the coordinates of an element of Λ in that ball are integers x_i with $|x_i| \leq \rho|\ell_i^*|$, by Step 1. There are finitely many such coordinate vectors, completing the proof.

The discrete condition need only be checked at the origin due to linearity[11]. An example of a free $\mathbb{Z}$-module in $\mathbb{R}^2$ that is not discrete is the one elaborated in example 50.1.52

$$\langle (1,1), (\sqrt{2}, \sqrt{2}) \rangle \subseteq \mathbb{R}^2$$

In particular, we may get as close as we want to $(0,0)$ by adding integer-multiples these two elements.

Proposition 50.1.57: Archimedean Embedding of $\mathcal{O}_K$ is Lattice

Let $K/\mathbb{Q}$ be a number field of degree n and σ its Archimedean embedding. Identify $K_\mathbb{R} = \mathbb{R}^{r_1} \oplus \mathbb{C}^{r_2}$ with $\mathbb{R}^n$ by writing each complex coordinate z as $(\mathrm{Re}z, \mathrm{Im}z)$, with the standard inner product of $\mathbb{R}^n$. Then $\sigma(\mathcal{O}_K)$ is a lattice in $K_\mathbb{R}$, and $\sigma(\alpha_1), \ldots, \sigma(\alpha_n)$ is a $\mathbb{Z}$-basis of it for every integral basis $\alpha_1, \ldots, \alpha_n$ of $\mathcal{O}_K$. In particular

$$\langle \sigma(\mathcal{O}_K) \rangle_\mathbb{R} = \mathbb{R}^{r_1} \oplus \mathbb{C}^{r_2}$$

***Proof*:**
Let $\alpha_1, \ldots, \alpha_n$ be an integral basis of $\mathcal{O}_K$, which exists by corollary 50.1.33.

Step 1: a nonzero determinant. List the embeddings of K into $\mathbb{C}$ as $\sigma_1, \ldots, \sigma_{r_1}, \tau_1, \overline{\tau_1}, \ldots, \tau_{r_2}, \overline{\tau_{r_2}}$, and let A be the $n \times n$ matrix whose ith row lists their values at α_i in this order. Up to transposing and reordering columns, which changes the determinant at most by a sign (proposition 13.4.6), A is the matrix of definition 50.1.24, so $\det(A)^2 = \mathrm{disc}_{K/\mathbb{Q}}(\alpha_1, \ldots, \alpha_n) = d_K$ by definition 50.1.38. The α_i are linearly independent over $\mathbb{Z}$, hence over $\mathbb{Q}$ after clearing denominators, so $d_K \neq 0$ by corollary 50.1.28. Let B be the real matrix obtained from A by replacing each pair of columns $(\tau_j(\alpha_i), \overline{\tau_j}(\alpha_i))$ by $(\mathrm{Re}\tau_j(\alpha_i), \mathrm{Im}\tau_j(\alpha_i))$. In the coordinates of $\mathbb{R}^n$, the ith row of B is $\sigma(\alpha_i)$. Column by column $\tau_j = \mathrm{Re}\tau_j + i\mathrm{Im}\tau_j$ and $\overline{\tau_j} = \mathrm{Re}\tau_j - i\mathrm{Im}\tau_j$, so expanding both columns by multilinearity, and using that the determinant vanishes when two columns are equal and changes sign when two columns are swapped (proposition 13.4.6), gives

$$\det(A) = (-2i)^{r_2} \det(B)$$

Hence $\det(B) \neq 0$.

Step 2: a basis of $K_\mathbb{R}$. Suppose $\sum_i c_i \sigma(\alpha_i) = 0$ with $c_i \in \mathbb{R}$ and some $c_k \neq 0$. Replacing the kth row of B by $\sum_i c_i \sigma(\alpha_i)$ produces a matrix with a zero row, whose determinant is 0 by multilinearity in rows. By multilinearity and the alternating property, the same determinant equals $c_k \det(B) \neq 0$, a contradiction. So $\sigma(\alpha_1), \ldots, \sigma(\alpha_n)$ are n linearly independent vectors of the n-dimensional space $K_\mathbb{R}$, hence a basis of $K_\mathbb{R}$.

Step 3: the lattice. Every embedding of K is a ring homomorphism, so σ is additive and

$$\sigma(\mathcal{O}_K) = \mathbb{Z}\sigma(\alpha_1) + \cdots + \mathbb{Z}\sigma(\alpha_n)$$

[11] This is reminiscent to how many conditions for topological groups need only be checked at the origin, including many proofs in real and complex analysis

Vectors linearly independent over $\mathbb{R}$ are linearly independent over $\mathbb{Z}$, so $\sigma(\mathcal{O}_K)$ is a free $\mathbb{Z}$-module of rank n with basis $\sigma(\alpha_1), \dots, \sigma(\alpha_n)$, which is condition (3) of definition 50.1.55. It spans $K_{\mathbb{R}}$ by Step 2, which is condition (1). By lemma 50.1.56 it is also discrete, so $\sigma(\mathcal{O}_K)$ is a lattice in $K_{\mathbb{R}}$, completing the proof.

Corollary 50.1.58: Sign Of Discriminant

Let $K/\mathbb{Q}$ be a number field, $\mathcal{O}_K$ its ring of integers, its discriminant. Then:

$$\operatorname{sign}(d_K) = (-1)^{r_2}$$

***Proof*:**
Let $n = [K : \mathbb{Q}]$, let $\alpha_1, \dots, \alpha_n$ be an integral basis of $\mathcal{O}_K$ (corollary 50.1.33), list the embeddings of K into $\mathbb{C}$ as $\sigma_1, \dots, \sigma_{r_1}, \tau_1, \overline{\tau_1}, \dots, \tau_{r_2}, \overline{\tau_{r_2}}$, and let A be the $n \times n$ matrix whose ith row lists their values at α_i in this order. By definition 50.1.24 and definition 50.1.38, $d_K = \det(A)^2$, the square making the order of the embeddings irrelevant. Let B be the real matrix obtained from A by replacing each pair of columns $(\tau_j(\alpha_i), \overline{\tau_j}(\alpha_i))$ by $(\mathrm{Re}\tau_j(\alpha_i), \mathrm{Im}\tau_j(\alpha_i))$. Column by column $\tau_j = \mathrm{Re}\tau_j + i\mathrm{Im}\tau_j$ and $\overline{\tau_j} = \mathrm{Re}\tau_j - i\mathrm{Im}\tau_j$, so expanding both columns by multilinearity, and using that the determinant vanishes when two columns are equal and changes sign when two columns are swapped (proposition 13.4.6), gives

$$\det(A) = (-2i)^{r_2} \det(B)$$

Hence $d_K = (-2i)^{2r_2} \det(B)^2 = (-1)^{r_2} 4^{r_2} \det(B)^2$. Here $\det(B)$ is a real number, nonzero because $d_K \neq 0$ (corollary 50.1.28), so $\det(B)^2 > 0$ and $\operatorname{sign}(d_K) = (-1)^{r_2}$, completing the proof.

By proposition 50.1.57, the ring of integers $\mathcal{O}_K$ forms a lattice in $K_{\mathbb{R}}$, and the same will hold for every nonzero ideal $\mathfrak{a} \subseteq \mathcal{O}_K$. Since $K_{\mathbb{R}}$ is an inner product space and a lattice is discrete, it is meaningful to define the volume of a lattice:

Definition 50.1.59: Volume of Lattice

Let V be a real vector space of dimension m with an inner product $\langle , \rangle$, and let $\Gamma \subseteq V$ be a complete lattice with $\mathbb{Z}$-basis $v_1, \dots, v_m$. Then the *volume* of Γ is

$$\mathrm{vol}(\Gamma) := \mathrm{vol}(V/\Gamma) = \mathrm{coVol}(\Gamma) = |\det(\langle v_i, v_j \rangle)|^{1/2}$$

For $V = K_{\mathbb{R}} = \mathbb{R}^{r_1} \oplus \mathbb{C}^{r_2}$, identify $K_{\mathbb{R}}$ with $\mathbb{R}^n$ by writing each complex coordinate z as $(\mathrm{Re}z, \mathrm{Im}z)$ and use the standard inner product of $\mathbb{R}^n$. Then $\mathrm{vol}(\Gamma) = |\det(B)|$, where B is the matrix whose rows are the coordinates of $v_1, \dots, v_n$, because $(\langle v_i, v_j \rangle) = BB^t$. This is the volume of $v_1, \dots, v_n$ in the sense of definition 13.4.15, the Lebesgue volume of the fundamental mesh $\{\sum_i a_i v_i \mid 0 \leq a_i < 1\}$. The notation $\mathrm{vol}(\mathcal{O}_K)$ means $\mathrm{vol}(\sigma(\mathcal{O}_K))$.

If you know some differential geometry, we may equivalently take the canonical differential form on $\mathbb{R}^n \cong \mathbb{R}^{r_1} \oplus \mathbb{C}^{r_2}$:

$$\omega = dx_1 \wedge \cdots \wedge dx_n$$

and write:

$$\text{vol}(\mathcal{O}_K) = \text{coVol}(K_\mathbb{R}/\mathcal{O}_K) = \left|\int_{K_\mathbb{R}/\mathcal{O}_K} \omega\right| = \left|\int_P \omega\right|$$

where $x_1, \dots, x_n$ are the real coordinates of $K_\mathbb{R} \cong \mathbb{R}^n$ fixed in definition 50.1.59 and:

$$P = \left\{\sum a_i v_i \;\middle|\; 0 \leq a_i \leq 1\right\}$$

This also motivates the vocabulary of covolume. Note that any different choice of a basis will produce the same result since the change of basis matrix B will have determinant ± 1 which in the absolute value becomes 1, and hence it is well-defined. Note that every ideal $\alpha \subseteq \mathcal{O}_K$ will also produce a lattice, since it's a sublattice of $\mathcal{O}_K$, and hence we may find the volume of any sublattice. The way we shall find the volume of the lattice is by taking advantage of the discriminant and the index of the ideal:

Proposition 50.1.60: Volume of Ideal Lattice

Let $0 \neq \mathfrak{a} \subseteq \mathcal{O}_K$ be an ideal. Then $\Gamma_\mathfrak{a} = \sigma(\mathfrak{a})$ is a [complete] lattice in $K_\mathbb{R}$ and its fundamental mesh has volume

$$\text{vol}(\Gamma_\mathfrak{a}) = \frac{1}{2^{r_2}}\sqrt{|\text{disc}(K)|}[\mathcal{O}_K : \mathfrak{a}]$$

As a consequence:

$$\text{vol}(\mathcal{O}_K) = \frac{1}{2^{r_2}}\sqrt{|\text{disc}(\mathcal{O}_K)|}$$

Thus, the discriminant provides volume information for the lattice given by the ring of integers.

In terms of the form ω above, the volume in the proposition is:

$$\text{vol}(\Gamma_\mathfrak{a}) = \left|\int_{(\mathbb{R}^{r_1}\oplus\mathbb{C}^{r_2})/\Gamma_\mathfrak{a}} \omega\right|$$

***Proof*:**
First, $\mathfrak{a}$ has finite index in $\mathcal{O}_K$. Let $0 \neq \beta \in \mathfrak{a}$ and $m = \text{Nm}_{K/\mathbb{Q}}(\beta)$, a nonzero integer by corollary 50.1.14 and corollary 50.1.13. In a Galois closure of K, m/β is the product of the images of β under the embeddings of K other than the inclusion. Each of them is a root of a monic polynomial in $\mathbb{Z}[x]$ that β satisfies, so m/β is an algebraic integer (corollary 26.1.6) lying in K, hence in $\mathcal{O}_K$ (lemma 50.1.5). So $m \in \beta\mathcal{O}_K \subseteq \mathfrak{a}$, and $\mathcal{O}_K/\mathfrak{a}$ is a quotient of $\mathcal{O}_K/m\mathcal{O}_K \cong (\mathbb{Z}/m\mathbb{Z})^n$, using that $\mathcal{O}_K$ is free of rank n (corollary 50.1.33). A subgroup of finite index of $\mathcal{O}_K$ is free of rank n (theorem 14.1.5, the rank being n because the quotient is finite). Let $\alpha_1, \dots, \alpha_n$ be a $\mathbb{Z}$-basis of $\mathfrak{a}$, so that $\Gamma_\mathfrak{a} = \mathbb{Z}\sigma(\alpha_1) + \cdots + \mathbb{Z}\sigma(\alpha_n)$. List all n embeddings $K \to \mathbb{C}$ as $\sigma_1, \dots, \sigma_{r_1}, \tau_1, \overline{\tau_1}, \dots, \tau_{r_2}, \overline{\tau_{r_2}}$, and let A be the $n \times n$ matrix whose ith row lists their values at α_i in this order. By definition 50.1.24 and proposition 50.1.39,

$$\det(A)^2 = \text{disc}(\alpha_1, \dots, \alpha_n) = [\mathcal{O}_K : \mathfrak{a}]^2\text{disc}(\mathcal{O}_K) = [\mathcal{O}_K : \mathfrak{a}]^2 d_K$$

Identify $K_\mathbb{R} = \mathbb{R}^{r_1} \oplus \mathbb{C}^{r_2}$ with $\mathbb{R}^n$ by writing each complex coordinate z as $(\text{Re}z, \text{Im}z)$, and measure volumes with Lebesgue measure on $\mathbb{R}^n$. Then $\sigma(\alpha_i)$ is the ith row of the real matrix

B obtained from A by replacing each pair of columns $(\tau_j(\alpha_i), \overline{\tau_j}(\alpha_i))$ by $(\mathrm{Re}\tau_j(\alpha_i), \mathrm{Im}\tau_j(\alpha_i))$. Column by column $\tau_j = \mathrm{Re}\tau_j + i\mathrm{Im}\tau_j$ and $\overline{\tau_j} = \mathrm{Re}\tau_j - i\mathrm{Im}\tau_j$, so expanding both columns by multilinearity of the determinant leaves $-2i$ times the determinant with columns $\mathrm{Re}\tau_j, \mathrm{Im}\tau_j$, and

$$\det(A) = (-2i)^{r_2} \det(B)$$

Hence $|\det(B)| = 2^{-r_2}\sqrt{|d_K|}\,[\mathcal{O}_K : \mathfrak{a}]$, which is nonzero since $d_K \neq 0$ (corollary 50.1.28). So $\sigma(\alpha_1), \dots, \sigma(\alpha_n)$ are linearly independent over $\mathbb{R}$: if $\sum_i c_i\sigma(\alpha_i) = 0$ with $c_k \neq 0$, replacing the kth row of B by this combination gives a matrix with a zero row, whose determinant is both 0 and $c_k \det(B)$ by multilinearity and the alternating property (proposition 13.4.6). Being n independent vectors of the n-dimensional space $K_{\mathbb{R}}$, they form a basis, $\Gamma_{\mathfrak{a}}$ is free of rank n and spans $K_{\mathbb{R}}$, and it is a complete lattice by lemma 50.1.56. The volume of its fundamental mesh $\{\sum_i a_i\sigma(\alpha_i) \mid 0 \leq a_i < 1\}$ is $|\det(B)|$, which is definition 50.1.59 in these coordinates, since $|\det(\langle\sigma(\alpha_i), \sigma(\alpha_j)\rangle)|^{1/2} = |\det(BB^t)|^{1/2} = |\det(B)|$. This is the first formula, and $\mathfrak{a} = \mathcal{O}_K$ gives the second, as we sought to show.

Thus, if $K = \mathbb{Q}(\sqrt{m})$ where m is square-free, then $\mathrm{vol}(\mathcal{O}_K) = 2^{-r_2}\sqrt{|d_K|}$ with $d_K = m$ or $4m$ (example 50.1.25), where $r_2 = 0$ if $m > 0$ and $r_2 = 1$ if $m < 0$:

$$\mathrm{vol}(\mathcal{O}_K) = \begin{cases} \sqrt{m} & m > 0,\ m \equiv 1 \bmod 4 \\ 2\sqrt{m} & m > 0,\ m \equiv 2, 3 \bmod 4 \\ \frac{1}{2}\sqrt{|m|} & m < 0,\ m \equiv 1 \bmod 4 \\ \sqrt{|m|} & m < 0,\ m \equiv 2, 3 \bmod 4 \end{cases}$$

Absolute Norm and Geometric Inequalities

Besides introducing a geometric intuition for number rings and their ideals, the key reason to introduce volumes is that they will allow us make many bounding arguments on ideals using the lattice structure of $\mathcal{O}_K$. To do this, we introduce a new "norm" on the ideals of $\mathcal{O}_K$ that shall represent the size of the ideal with respect to the lattice. This will be helpful in many algebraic arguments, but also in upgrading many clasical results about primes (such as their distribution[12], see [77]).

Definition 50.1.61: Absolute Norm

Let $0 \neq \mathfrak{a} \subseteq \mathcal{O}_K$ be a nonzero ideal of $\mathcal{O}_K$. Then the *absolute norm* of $\mathfrak{a}$ is given by

$$\mathfrak{N}_K(\mathfrak{a}) := [\mathcal{O}_K : \mathfrak{a}]$$

If unambiguous, the notation $\mathfrak{N}(\mathfrak{a})$ is also used.

The absolute norm is inspired by the picture of an ideal of $\mathcal{O}_K$ as a sublattice of a certain sparsity inside the lattice $\mathcal{O}_K$: the index $[\mathcal{O}_K : \mathfrak{a}]$ is the measure of that sparsity. Note that the notation $\mathfrak{N}_{K/\mathbb{Q}}$ should not be used, for it shall have a different meaning than $\mathfrak{N}$[13]

For the definition to be of any use, the index $[\mathcal{O}_K : \mathfrak{a}]$ had better be finite. Note that proposition 50.1.39

[12] the number of primes p where $|p| \leq X$ tends asymptotically to $\frac{X}{\log(X)}$

[13] see definition 50.3.13

does not give this on its own, for it *assumes* the submodule has finite index. The finiteness deserves its own proof:

Proposition 50.1.62: Finiteness of Residue Rings

Let $K/\mathbb{Q}$ be a number field of degree n and let $0 \neq \mathfrak{a} \subseteq \mathcal{O}_K$ be a nonzero ideal. Then the quotient ring $\mathcal{O}_K/\mathfrak{a}$ is finite. In particular, $\mathfrak{N}(\mathfrak{a}) = [\mathcal{O}_K : \mathfrak{a}]$ is finite for every nonzero ideal $\mathfrak{a}$.

***Proof*:**
First, we show that $\mathfrak{a}$ contains a nonzero rational integer. Let $0 \neq \alpha \in \mathfrak{a}$ and let $m = \mathrm{Nm}_{K/\mathbb{Q}}(\alpha)$. By corollary 50.1.14, $m \in \mathbb{Z}$, and by corollary 50.1.13, $m = \prod_i \sigma_i(\alpha)$ is a product of nonzero elements of a field, hence $m \neq 0$. Furthermore, since $\mathrm{Nm}_{K/\mathbb{Q}}(\alpha) = \alpha \prod_{\sigma_i \neq \mathrm{id}} \sigma_i(\alpha)$, we have that m/α is a product of Galois conjugates of α. Each conjugate is integral over $\mathbb{Z}$ (being a root of the same monic integer minimal polynomial as α), hence m/α is an algebraic integer by corollary 26.1.6. Since $m/\alpha \in K$, we get $m/\alpha \in \mathcal{O}_K$, and so:

$$m = \alpha \cdot \frac{m}{\alpha} \in \alpha\mathcal{O}_K \subseteq \mathfrak{a}$$

Next, since $m\mathcal{O}_K \subseteq \mathfrak{a} \subseteq \mathcal{O}_K$, the quotient map $\mathcal{O}_K/m\mathcal{O}_K \to \mathcal{O}_K/\mathfrak{a}$ is a surjection of abelian groups. By corollary 50.1.33, $\mathcal{O}_K$ is a free $\mathbb{Z}$-module of rank n, so choosing an integral basis:

$$\mathcal{O}_K/m\mathcal{O}_K \cong (\mathbb{Z}/m\mathbb{Z})^n$$

which has $|m|^n$ elements. Being a quotient of a finite group, $\mathcal{O}_K/\mathfrak{a}$ is finite, with $[\mathcal{O}_K : \mathfrak{a}]$ dividing $|m|^n$, as we sought to show.

Lemma 50.1.63: Norm Of Principal Ideal

Let $0 \neq \alpha \in \mathcal{O}_K$. Then:

$$\mathfrak{N}((\alpha)) = \left|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)\right|$$

***Proof*:**
Let $\beta_1, \ldots, \beta_n$ be an integral basis of $\mathcal{O}_K$ (corollary 50.1.33). Multiplication by α is an injective additive map from $\mathcal{O}_K$ onto $\alpha\mathcal{O}_K$, so $\alpha\beta_1, \ldots, \alpha\beta_n$ is a $\mathbb{Z}$-basis of $(\alpha) = \alpha\mathcal{O}_K$. Let $A = (a_{ij}) \in M_n(\mathbb{Z})$ be the matrix with $\alpha\beta_i = \sum_j a_{ij}\beta_j$. The ideal (α) is nonzero, so it has finite index in $\mathcal{O}_K$ (proposition 50.1.62), and proposition 50.1.39 gives $\mathfrak{N}((\alpha)) = [\mathcal{O}_K : \alpha\mathcal{O}_K] = |\det(A)|$. The matrix of multiplication by α in the basis $\beta_1, \ldots, \beta_n$ has as jth column the coordinates of $\alpha\beta_j$, so it is A^t, and by definition 50.1.10 and proposition 13.4.6, $\mathrm{Nm}_{K/\mathbb{Q}}(\alpha) = \det(A^t) = \det(A)$. Hence $\mathfrak{N}((\alpha)) = |\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)|$, completing the proof.

Lemma 50.1.64: Ideal Divides Absolute Norm

Let $0 \neq I \subseteq \mathcal{O}_K$ be an ideal. Then $\mathfrak{N}(I) \in I$, that is:

$$\mathfrak{N}(I)\mathcal{O}_K \subseteq I$$

***Proof*:**
The index $\mathfrak{N}(I) = [\mathcal{O}_K : I]$ is finite (proposition 50.1.62). In the additive group $\mathcal{O}_K/I$ of order $\mathfrak{N}(I)$, the element $1+I$ satisfies $\mathfrak{N}(I)\cdot(1+I) = 0$ by theorem 3.3.1, so $\mathfrak{N}(I) \in I$ and $\mathfrak{N}(I)\mathcal{O}_K \subseteq I$, completing the proof.

Lemma 50.1.65: Volume Form Reformulation

Let K be a number field and $0 \neq I \subseteq \mathcal{O}_K$ an ideal, and write $\mathrm{vol}(I)$ for $\mathrm{vol}(\sigma(I))$. Then:

$$\mathrm{vol}(I) = \mathfrak{N}(I)\mathrm{vol}(\mathcal{O}_K)$$

***Proof*:**
By proposition 50.1.60, $\mathrm{vol}(I) = 2^{-r_2}\sqrt{|d_K|}\,[\mathcal{O}_K : I]$ and $\mathrm{vol}(\mathcal{O}_K) = 2^{-r_2}\sqrt{|d_K|}$. Since $\mathfrak{N}(I) = [\mathcal{O}_K : I]$ by definition 50.1.61, the two formulas combine to $\mathrm{vol}(I) = \mathfrak{N}(I)\mathrm{vol}(\mathcal{O}_K)$, completing the proof.

Theorem 50.1.66: Bounding Ideals

Let $K/\mathbb{Q}$ be a number field and $\mathcal{O}_K$ its number ring. Then there exists $\lambda \in \mathbb{R}_{>0}$ such that for every nonzero ideal $I \subseteq \mathcal{O}_K$, there exists a nonzero $\alpha \in I$ such that

$$|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)| \leq \lambda\mathfrak{N}(I)$$

***Proof*:**
Let $\alpha_1, \ldots, \alpha_n$ be an integral basis of $\mathcal{O}_K$ (corollary 50.1.33), let $\sigma_1, \ldots, \sigma_n$ be the embeddings of K into $\mathbb{C}$, and put

$$\lambda = \prod_{i=1}^{n}\left(\sum_{j=1}^{n}|\sigma_i(\alpha_j)|\right)$$

Each factor is positive, since σ_i is injective and $\alpha_1 \neq 0$. Let I be a nonzero ideal. Then $\mathfrak{N}(I)$ is a positive integer (proposition 50.1.62), so there is a unique integer $m \geq 1$ with

$$m^n \leq \mathfrak{N}(I) < (m+1)^n$$

The $(m+1)^n$ elements $\sum_j m_j\alpha_j$ with $m_j \in \mathbb{Z}$ and $0 \leq m_j \leq m$ are distinct, as the α_j form a $\mathbb{Z}$-basis, and there are more of them than the $\mathfrak{N}(I) = |\mathcal{O}_K/I|$ cosets of I. So two of them are congruent modulo I, and their difference is a nonzero element of I of the form

$$\alpha = \sum_{j=1}^{n} m_j\alpha_j \qquad m_j \in \mathbb{Z} \qquad |m_j| \leq m$$

By corollary 50.1.13 and the triangle inequality in $\mathbb{C}$,

$$\left|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)\right| = \prod_{i=1}^{n}|\sigma_i(\alpha)| \leq \prod_{i=1}^{n}\left(\sum_{j=1}^{n}|m_j||\sigma_i(\alpha_j)|\right) \leq m^n\lambda \leq \mathfrak{N}(I)\lambda$$

completing the proof.

Proposition 50.1.67: Image Of Norm Is Finite Up To Units

Let K be a number field of degree n, $\mathcal{O}_K$ its ring of integers, and $a \in \mathbb{Z}_{>0}$. Then up to multiplication by units, there are only finitely many elements $\alpha \in \mathcal{O}_K$ such that

$$\left|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)\right| = a$$

More precisely, there are at most a^n of them.

***Proof*:**
Step 1: one associate class per coset. Let $\alpha, \beta \in \mathcal{O}_K$ with $|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)| = |\mathrm{Nm}_{K/\mathbb{Q}}(\beta)| = a$ and $\beta - \alpha \in a\mathcal{O}_K$, say $\beta = \alpha + a\gamma$ with $\gamma \in \mathcal{O}_K$. Both are nonzero, as their norms are. By lemma 50.1.63, the additive group $\mathcal{O}_K/\beta\mathcal{O}_K$ has a elements, so $a \cdot 1 \in \beta\mathcal{O}_K$ by theorem 3.3.1, that is, $a/\beta \in \mathcal{O}_K$. In the same way $a/\alpha \in \mathcal{O}_K$. Hence

$$\frac{\alpha}{\beta} = 1 - \frac{a}{\beta}\gamma \in \mathcal{O}_K \qquad \frac{\beta}{\alpha} = 1 + \frac{a}{\alpha}\gamma \in \mathcal{O}_K$$

so α/β is a unit of $\mathcal{O}_K$, and α and β are associates.

Step 2: counting. By corollary 50.1.33, $\mathcal{O}_K/a\mathcal{O}_K \cong (\mathbb{Z}/a\mathbb{Z})^n$ has a^n cosets. By Step 1, the elements of absolute norm a in one coset form at most one class up to units, so there are at most a^n such classes, completing the proof.

For computational purposes, we add a tighter bound on the norms of ideals. We start with the following lemma:


Lemma 50.1.68: Minkowski's Lattice Point Theorem

Let Γ be a discrete complete lattice in $\mathbb{R}^n$, with its standard inner product, and let X be a centrally symmetric convex subset of $\mathbb{R}^n$. Then if

$$\mathrm{vol}(X) > 2^n \mathrm{vol}(\Gamma)$$

then X contains at least one nonzero lattice point $\gamma \in \Gamma$

Before proving this result, consider $\sigma(\mathbb{Z}[i]) = \mathbb{Z}^2$ in $\mathbb{C} = \mathbb{R}^2$, with $\mathrm{vol}(\mathbb{Z}^2) = 1$. The open square $(-1, 1)^2$ is convex and centrally symmetric, has area $4 = 2^2\mathrm{vol}(\mathbb{Z}^2)$, and meets $\mathbb{Z}^2$ only in 0, so the constant 2^n cannot be lowered:



***Proof*:**
Volumes are Lebesgue measure on $\mathbb{R}^n$, and we use these facts of the analysis assumed in this chapter: convex sets are Lebesgue measurable, Lebesgue measure is countably additive and translation invariant, $\text{vol}(\frac{1}{2}X) = 2^{-n}\text{vol}(X)$, and the fundamental mesh $\Phi = \{\sum_i a_i v_i \mid 0 \leq a_i < 1\}$ of a $\mathbb{Z}$-basis $v_1, \ldots, v_n$ of Γ has volume $\text{vol}(\Gamma)$ (definition 50.1.59).

Step 1: a tiling. The v_i form a basis of $\mathbb{R}^n$, as Γ is complete. Every $v = \sum_i x_i v_i \in \mathbb{R}^n$ equals $\sum_i (x_i - \lfloor x_i \rfloor)v_i + \sum_i \lfloor x_i \rfloor v_i$, and this is the only way to write $v = \varphi + \gamma$ with $\varphi \in \Phi$ and $\gamma \in \Gamma$. So $\mathbb{R}^n$ is the disjoint union of the translates $\Phi + \gamma$, $\gamma \in \Gamma$.

Step 2: two translates of $\frac{1}{2}X$ meet. Suppose the sets $\frac{1}{2}X + \gamma$, $\gamma \in \Gamma$, are pairwise disjoint. Then so are the sets $\Phi \cap (\frac{1}{2}X + \gamma) \subseteq \Phi$, and as $\Gamma \cong \mathbb{Z}^n$ is countable,

$$\sum_{\gamma \in \Gamma} \text{vol}\left(\Phi \cap \left(\tfrac{1}{2}X + \gamma\right)\right) \leq \text{vol}(\Phi) = \text{vol}(\Gamma)$$

Translating by $-\gamma$ gives $\text{vol}(\Phi \cap (\frac{1}{2}X + \gamma)) = \text{vol}((\Phi - \gamma) \cap \frac{1}{2}X)$, and by Step 1 the sets $(\Phi - \gamma) \cap \frac{1}{2}X$, $\gamma \in \Gamma$, partition $\frac{1}{2}X$. So the left side is $\text{vol}(\frac{1}{2}X) = 2^{-n}\text{vol}(X) > \text{vol}(\Gamma)$, a contradiction.

Step 3: a lattice point. By Step 2 there are $\gamma_1 \neq \gamma_2$ in Γ and $x_1, x_2 \in X$ with $\frac{1}{2}x_1 + \gamma_1 = \frac{1}{2}x_2 + \gamma_2$. Then $\gamma = \gamma_1 - \gamma_2$ is a nonzero element of Γ, and $\gamma = \frac{1}{2}x_2 + \frac{1}{2}(-x_1)$. As X is centrally symmetric, $-x_1 \in X$, and as X is convex, the midpoint γ of x_2 and $-x_1$ lies in X, completing the proof.

Theorem 50.1.69: Minkowski's Bound

Let K be a number field of degree $n = r_1 + 2r_2$, with r_1 real embeddings and r_2 pairs of complex conjugate embeddings, and let $0 \neq \mathfrak{a} \subseteq \mathcal{O}_K$ be an ideal. Then $\mathfrak{a}$ contains an element $\alpha \neq 0$ with

$$\left|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)\right| \leq \frac{n!}{n^n}\left(\frac{4}{\pi}\right)^{r_2}\sqrt{|d_K|}\,\mathfrak{N}(\mathfrak{a})$$

The constant $M_K = \frac{n!}{n^n}\left(\frac{4}{\pi}\right)^{r_2}\sqrt{|d_K|}$ is called the *Minkowski bound* of K.

***Proof*:**
Let $\sigma_1, \ldots, \sigma_{r_1}$ be the real embeddings of K and $\tau_1, \ldots, \tau_{r_2}$ one complex embedding from each conjugate pair, as in definition 50.1.53. As in definition 50.1.59, identify $K_{\mathbb{R}} = \mathbb{R}^{r_1} \oplus \mathbb{C}^{r_2}$ with $\mathbb{R}^n$ by writing each complex coordinate z as $(\mathrm{Re}z, \mathrm{Im}z)$, and measure volumes with Lebesgue measure on $\mathbb{R}^n$. By proposition 50.1.60 and definition 50.1.61, $\Gamma_{\mathfrak{a}} = \sigma(\mathfrak{a})$ is a complete lattice in $K_{\mathbb{R}}$ with

$$\mathrm{vol}(\Gamma_{\mathfrak{a}}) = \frac{1}{2^{r_2}}\sqrt{|d_K|}\,\mathfrak{N}(\mathfrak{a})$$

For $(x, z) \in \mathbb{R}^{r_1} \oplus \mathbb{C}^{r_2}$ put $\|(x,z)\| = \sum_{i=1}^{r_1}|x_i| + 2\sum_{j=1}^{r_2}|z_j|$, and for $t \geq 0$ let

$$X_t = \{(x,z) \in \mathbb{R}^{r_1} \oplus \mathbb{C}^{r_2} \mid \|(x,z)\| \leq t\}$$

Step 1: X_t is convex and centrally symmetric. The triangle inequality for absolute values on $\mathbb{R}$ and on $\mathbb{C}$ gives $\|u+v\| \leq \|u\| + \|v\|$, and $\|\lambda u\| = |\lambda|\,\|u\|$ for $\lambda \in \mathbb{R}$. So $\|-u\| = \|u\|$, and for $u, v \in X_t$ and $0 \leq \lambda \leq 1$ we get $\|\lambda u + (1-\lambda)v\| \leq \lambda\|u\| + (1-\lambda)\|v\| \leq t$.

Step 2: $\mathrm{vol}(X_t) = 2^{r_1}\left(\frac{\pi}{2}\right)^{r_2}\frac{t^n}{n!}$. Write $V_{r_1,r_2}(t)$ for this volume. By Fubini's theorem the volume of a closed region is the integral, over one coordinate in $\mathbb{R}$ or in $\mathbb{C} \cong \mathbb{R}^2$, of the volumes of its slices, and in polar coordinates $w = \rho e^{i\theta}$ on $\mathbb{C}$ the area element is $\rho\,d\rho\,d\theta$. We induct on $n \geq 1$. For $(r_1, r_2) = (1,0)$, $X_t = [-t, t]$ has length $2t$. For $(r_1, r_2) = (0,1)$, X_t is the disc $|z| \leq t/2$, of area $\pi t^2/4 = \frac{\pi}{2}\cdot\frac{t^2}{2!}$. Let $n \geq 2$ with $(r_1, r_2) \neq (0,1)$, and assume the formula in all smaller dimensions and for all $t \geq 0$.

If $r_1 \geq 1$, slice along the first real coordinate $x_1 = y$. For $|y| \leq t$ the slice is the region $X_{t-|y|}$ for $(r_1 - 1, r_2)$, of dimension $n - 1 \geq 1$, and for $|y| > t$ it is empty. Since $\int_{-t}^{t}(t-|y|)^{n-1}\,dy = 2t^n/n$,

$$V_{r_1,r_2}(t) = \int_{-t}^{t} 2^{r_1-1}\left(\frac{\pi}{2}\right)^{r_2}\frac{(t-|y|)^{n-1}}{(n-1)!}\,dy = 2^{r_1}\left(\frac{\pi}{2}\right)^{r_2}\frac{t^n}{n!}$$

If $r_1 = 0$, then $r_2 \geq 2$. Slice along the last complex coordinate $z_{r_2} = w$. For $2|w| \leq t$ the slice is the region $X_{t-2|w|}$ for $(0, r_2 - 1)$, of dimension $n - 2 \geq 2$, and otherwise it is empty. In polar coordinates, followed by the substitution $u = 2\rho$,

$$V_{0,r_2}(t) = \int_0^{2\pi}\int_0^{t/2}\left(\frac{\pi}{2}\right)^{r_2-1}\frac{(t-2\rho)^{n-2}}{(n-2)!}\,\rho\,d\rho\,d\theta = \left(\frac{\pi}{2}\right)^{r_2-1}\frac{2\pi}{4\,(n-2)!}\int_0^t (t-u)^{n-2}u\,du$$

Writing $u = t - (t-u)$ gives $\int_0^t (t-u)^{n-2} u\,du = \frac{t^n}{n-1} - \frac{t^n}{n} = \frac{t^n}{n(n-1)}$, so $V_{0,r_2}(t) = \left(\frac{\pi}{2}\right)^{r_2} \frac{t^n}{n!}$, which completes the induction.

Step 3: the inequality between the means. For real numbers $c_1, \dots, c_n \geq 0$ with mean $\mu = (c_1 + \cdots + c_n)/n$ we have $c_1 \cdots c_n \leq \mu^n$. For $n = 1$ this is an equality. For $n \geq 2$, reorder so that $c_1 \leq \mu \leq c_n$ and put $c' = c_1 + c_n - \mu$, so that $c' \geq c_1 \geq 0$. Then $c_1 c_n \leq \mu c'$, because $\mu c' - c_1 c_n = (\mu - c_1)(c_n - \mu) \geq 0$, and the $n-1$ numbers $c', c_2, \dots, c_{n-1}$ have mean μ. By induction on n, $c' c_2 \cdots c_{n-1} \leq \mu^{n-1}$, hence $c_1 \cdots c_n \leq \mu\, c' c_2 \cdots c_{n-1} \leq \mu^n$.

Step 4: a nonzero element of small norm. Let $\varepsilon > 0$ and choose $t > 0$ with

$$t^n = n! \left(\frac{4}{\pi}\right)^{r_2} \sqrt{|d_K|}\, \mathfrak{N}(\mathfrak{a}) + n^n \varepsilon$$

By Step 2, and since $n - r_2 = r_1 + r_2$,

$$\mathrm{vol}(X_t) > 2^{r_1} \left(\frac{\pi}{2}\right)^{r_2} \left(\frac{4}{\pi}\right)^{r_2} \sqrt{|d_K|}\, \mathfrak{N}(\mathfrak{a}) = 2^{r_1 + r_2} \sqrt{|d_K|}\, \mathfrak{N}(\mathfrak{a}) = 2^n \mathrm{vol}(\Gamma_{\mathfrak{a}})$$

By Step 1 and lemma 50.1.68, there is $\alpha \in \mathfrak{a}$ with $0 \neq \sigma(\alpha) \in X_t$, so $\alpha \neq 0$. By corollary 50.1.13, in which τ_j and $\overline{\tau_j}$ together contribute $\tau_j(\alpha)\overline{\tau_j(\alpha)} = |\tau_j(\alpha)|^2$,

$$\left|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)\right| = \prod_{i=1}^{r_1} |\sigma_i(\alpha)| \prod_{j=1}^{r_2} |\tau_j(\alpha)|^2$$

This is the product of the n numbers $|\sigma_i(\alpha)|$ and $|\tau_j(\alpha)|$, the latter each taken twice, whose sum is $\|\sigma(\alpha)\| \leq t$. So Step 3 gives

$$\left|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)\right| \leq \frac{t^n}{n^n} = M_K \mathfrak{N}(\mathfrak{a}) + \varepsilon$$

Step 5: removing ε. Put $C = M_K \mathfrak{N}(\mathfrak{a})$ and apply Step 4 with $\varepsilon = \frac{1}{2}(\lfloor C \rfloor + 1 - C) > 0$. The resulting α satisfies $\left|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)\right| \leq C + \varepsilon < \lfloor C \rfloor + 1$, and $\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)$ is an integer (corollary 50.1.14), so $\left|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)\right| \leq \lfloor C \rfloor \leq C$, as we sought to show.

Applied to $\mathfrak{a} = \mathcal{O}_K$, theorem 50.1.69 gives some $\alpha \neq 0$ in $\mathcal{O}_K$ with $\left|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)\right| \leq M_K$. Here $\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)$ is an integer (corollary 50.1.14) and is nonzero, being a product of the nonzero numbers $\sigma_i(\alpha)$ (corollary 50.1.13), so $1 \leq M_K$, that is

$$\frac{n^n}{n!} \left(\frac{\pi}{4}\right)^{r_2} \leq \sqrt{|d_K|}$$

Thus, we get a result that may seem obvious, but is in general rather difficult to prove:

Corollary 50.1.70: Discriminant Nonzero

Let $\mathcal{O}_K \neq \mathbb{Z}$. Then:

$$|d_K| > 1$$

***Proof*:**
If $K = \mathbb{Q}$ then $\mathcal{O}_K = \mathcal{O}_K \cap \mathbb{Q} = \mathbb{Z}$ by theorem 50.1.9(1), so $\mathcal{O}_K \neq \mathbb{Z}$ forces $n \geq 2$. As $0 < \pi/4 < 1$ and $r_2 \leq n/2$, the inequality above gives $\sqrt{|d_K|} \geq a_n$, where $a_m = \frac{m^m}{m!}\left(\frac{\pi}{4}\right)^{m/2}$. For every $m \geq 1$,

$$\frac{a_{m+1}}{a_m} = \left(1 + \frac{1}{m}\right)^m \frac{\sqrt{\pi}}{2} \geq 2 \cdot \frac{\sqrt{\pi}}{2} > 1$$

because the binomial expansion of $(1 + 1/m)^m$ has nonnegative terms, the first two of which sum to 2. Hence $a_n \geq a_2 = \pi/2 > 1$, so $|d_K| > 1$, as claimed.

50.2 Ring Structure and Dedekind Domains

So far, we have shown that rings of integers are lattices whose rank corresponds to the dimension of their corresponding field extension. Since they are rings, we may naturally ask what type of ring are they. Using example 50.1.17, we can look at the particular example of $\mathcal{O}_{\mathbb{Q}(\sqrt{-5})} = \mathbb{Z}[\sqrt{-5}]$. Is this ring a Euclidean Domain, Principal Ideal Domain, or Unique Factorization Domain? It is certainly Noetherian, being a finitely generated $\mathbb{Z}$-module (where $\mathbb{Z}$ is Noetherian). However, not all irreducible elements are prime, for example:

$$6 = 2 \cdot 3 = (1 + \sqrt{-5})(1 - \sqrt{-5})$$

showing that 2 is not prime. This may seem troubling since we may have to keep track of multiple factorizations showing there is more structure or tools that would need to be added/used to keep track of this information. Fortunately, there is a way to recover factorization. The goal of this section is to define a new type of ring for which the notion of Unique factorization is recovered, and show that all rings of integers are this type of ring. First, we may use the norm to see that a factorization into irreducible is always certainly possible in $\mathcal{O}_k$. For, if $\alpha = \beta\gamma$, then if β, γ are non-units:

$$1 < |N_{K/\mathbb{Q}}(\beta)| < |N_{K/\mathbb{Q}}(\alpha)| \qquad 1 < |N_{K/\mathbb{Q}}(\gamma)| < |N_{K/\mathbb{Q}}(\alpha)|$$

showing that it is a factorization domain. However this factorization need not be unique as we have demonstrated with $\mathcal{O}_{\mathbb{Q}(\sqrt{-5})} = \mathbb{Z}[\sqrt{-5}]$, another example being $21 = 3 \cdot 7 = (1 + 2\sqrt{-5})(1 - 2\sqrt{-5})$. We may see these are irreducible elements by using the norm. Doing the case of 3, if $3 = \alpha\beta$ for non-units α, β, then $9 = N_{K/\mathbb{Q}}(\alpha)N_{K/\mathbb{Q}}(\beta)$ would give us that $N_{K/\mathbb{Q}}(\alpha) = \pm 3$. Given $\alpha = a + b\sqrt{-5}$ we get

$$N_{K/\mathbb{Q}}(a + b\sqrt{-5}) = a^2 + 5b^2 = \pm 3$$

But this certainly has no solutions in $\mathbb{Z}$, and hence 3 is irreducible in $\mathcal{O}_K$. A similar argument can be made for $7, 1 \pm 2\sqrt{-5}$. Furthermore, the numbers 3 and 5 are not associated to $1 \pm 2\sqrt{-5}$, for we would require that

$$\frac{1 \pm 2\sqrt{-5}}{3}, \frac{1 \pm 2\sqrt{-5}}{7} \in \mathcal{O}_K$$

both of which we can check are not using the norm. Hence, we certainly have different factorizations.

The failure of unique factorization has lead Eduard Kummer to try to embed the ring of integers of K into a bigger domain of "ideal numbers" where unique factorization into "ideal prime numbers" would hold (which was inspired by the discovery of complex numbers somehow being "ideal" for roots polynomial roots). As an example, our original decomposition in $\mathbb{Z}[\sqrt{-5}]$

$$21 = 3 \cdot 7 = (1 + 2\sqrt{-5})(1 - 2\sqrt{-5})$$

would factor into ideal prime numbers $\mathfrak{p}_1, \mathfrak{p}_2, \mathfrak{p}_3, \mathfrak{p}_4$ with the relations

$$3 = \mathfrak{p}_1\mathfrak{p}_2 \qquad 7 = \mathfrak{p}_3\mathfrak{p}_4 \qquad 1 + 2\sqrt{-5} = \mathfrak{p}_1\mathfrak{p}_3 \qquad 1 - 2\sqrt{-5} = \mathfrak{p}_2\mathfrak{p}_4$$

Then we would have fixed non-uniqueness since we would get the factorization:

$$21 = (\mathfrak{p}_1\mathfrak{p}_2)(\mathfrak{p}_3\mathfrak{p}_4) = (\mathfrak{p}_1\mathfrak{p}_3)(\mathfrak{p}_2\mathfrak{p}_4)$$

Some key properties that these ideals numbers should have is that for $a, b, \lambda \in \mathcal{O}_K$, an ideal number $\mathfrak{a}$ should satisfy the following natural divisibility restrictions:

$$\mathfrak{a}\big|a \text{ and } \mathfrak{a}\big|b \Rightarrow \mathfrak{a}\big|a \pm b \qquad a\mathfrak{a}\big|a \Rightarrow \mathfrak{a}\big|\lambda a$$

An furthermore an ideal number $\mathfrak{a}$ ought to be determinable by the set of its divisors in $\mathcal{O}_K$, that is

$$\underline{\mathfrak{a}} = \left\{a \in \mathcal{O}_K \;\middle|\; \mathfrak{a}\big|a\right\}$$

But given these rules, this set is simply an ideal of $\mathcal{O}_K$ as we know the notion of ideal. It was Richard Dedekind that took the notion of ideal numbers that Kummer invented and invented the notion of *ideals* of $\mathcal{O}_K$ giving the modern definition of ideals. Then division $\mathfrak{a}\big|a$ is replaced by belonging $a \in \mathfrak{a}$, and divisibility $\mathfrak{a}\big|\mathfrak{b}$ is replaced by containment $\mathfrak{b} \subseteq \mathfrak{a}$.

Hence, we shall seek a unique factorization of *ideals* into *prime ideals* in $\mathcal{O}_K$. The 3 key properties of $\mathcal{O}_K$ that require this factorization was singled out by Dedekind and form a class of rings larger than rings of integers and are worth taking a look at on their own:

Definition 50.2.1: Dedekind Domain

Let R be an integral domain. Then if:

1. R is a Noetherian ring
2. every nonzero prime ideal of R is maximal
3. R is normal ($\overline{R}^{K(R)} = R$)

then R is called a *Dedekind Domain*

The Noetherian condition can be thought of as a natural eliminator of any infinites lurking around, while the prime implies maximal condition can be thought of as making sure that there can be a prime ideal that further contains prime ideals. In particular, we shall see that $(a) \subseteq (b)$ if and only if $b\big|a$, which does not make sense if we allow for prime ideals being contained in larger prime ideals.

50.2.2 Foreshadowing in Algebraic Geometry Notice that we have already seen a ring with these conditions before, namely if V is a smooth 1-dimensional variety, then the associated k-algebra is Noetherian, 1 [Krull] dimensional and is normal (normal implies smoothness[a]). In Algebraic Geometry, Dedekind domains can be thought of as representing 1-dimensional smooth schemes (in particular, 1-dimensional smooth $\mathbb{Z}$-curves)

[a] But only necessarily in 1 dimension; in higher dimension normalness need not imply smoothness, see [13]

Lemma 50.2.3: PID's, UFD's, and Dedekind Domain

Let R be a ring. Then:

1. If R is a PID, R is a Dedekind Domain
2. If R is a UFD, R need not be a Dedekind Domain, and if R is a Dedekind domain, R need not be a UFD
3. If R is a Dedekind domain and a UFD, it is a PID

The following image demonstrates the realation:




Figure 50.1: Venn diagram

***Proof*:**

1. Let R be a PID. Every ideal of R is principal, hence finitely generated, so R is Noetherian (proposition 23.1.3). Every nonzero prime ideal of R is maximal by proposition 10.1.32. Finally, R is a UFD by proposition 10.1.33, and a UFD is integrally closed in its fraction field (corollary 29.9.6). So R satisfies the three conditions of definition 50.2.1.

2. The ring $\mathbb{Z}[x]$ is a UFD by theorem 11.2.3, since $\mathbb{Z}$ is one (corollary 10.1.34). Evaluation at 0 is a surjective ring homomorphism $\mathbb{Z}[x] \to \mathbb{Z}$ with kernel (x), so $\mathbb{Z}[x]/(x) \cong \mathbb{Z}$, an integral domain that is not a field. Hence (x) is a nonzero prime ideal that is not maximal, and $\mathbb{Z}[x]$ is not a Dedekind domain.

   For the second claim let $R = \mathbb{Z}[\sqrt{-13}]$. Since -13 is square-free and $-13 \equiv 3 \bmod 4$, $R = \mathcal{O}_K$ for $K = \mathbb{Q}(\sqrt{-13})$ (example 50.1.17). It is a Dedekind domain. It is Noetherian: R is a free $\mathbb{Z}$-module of rank 2 (corollary 50.1.33), so every ideal, being a $\mathbb{Z}$-submodule, is a finitely generated $\mathbb{Z}$-module (theorem 14.1.5), hence a finitely generated ideal. Every nonzero prime $\mathfrak{p}$ of R is maximal, because $R/\mathfrak{p}$ is a finite integral domain (proposition 50.1.62), hence a field (corollary 9.1.25). And R, being the integral closure of $\mathbb{Z}$ in K, is integrally closed in K (corollary 26.1.6).

   For $\gamma = a + b\sqrt{-13}$ with $a, b \in \mathbb{Z}$, corollary 50.1.13 gives $\mathrm{Nm}(\gamma) = \mathrm{Nm}_{K/\mathbb{Q}}(\gamma) = (a + b\sqrt{-13})(a - b\sqrt{-13}) = a^2 + 13b^2$, a nonnegative integer. By proposition 50.1.18, γ is a unit exactly when $\mathrm{Nm}(\gamma) = 1$, that is when $b = 0$ and $a = \pm 1$. In R,

$$14 = 2 \cdot 7 = (1 + \sqrt{-13})(1 - \sqrt{-13})$$

with $\text{Nm}(2) = 4$, $\text{Nm}(7) = 49$ and $\text{Nm}(1 \pm \sqrt{-13}) = 14$. Each of these four factors is irreducible. Let γ be one of them and suppose $\gamma = \beta\delta$ with β, δ nonunits. Both are nonzero, so $\text{Nm}(\beta)$ and $\text{Nm}(\delta)$ are positive integers, both different from 1, with product $\text{Nm}(\gamma) \in \{4, 49, 14\}$. The product formula holds because the norm is the determinant of multiplication (definition 50.1.10) and the determinant is multiplicative (proposition 13.4.7). Hence $\text{Nm}(\beta) \in \{2, 7\}$. But $a^2 + 13b^2 \in \{2, 7\}$ has no solution in integers: $b \neq 0$ gives $a^2 + 13b^2 \geq 13$, and $b = 0$ would make 2 or 7 a square. The two factorizations are not related by reordering and units: associates differ by a unit ± 1 and so have equal norms, while $4 \neq 14$ and $49 \neq 14$, so neither 2 nor 7 is associate to $1 + \sqrt{-13}$ or to $1 - \sqrt{-13}$. By definition 10.1.21, R is not a UFD.

3. Let R be a Dedekind domain and a UFD. First, every prime ideal $\mathfrak{p}$ of R is principal. The zero ideal is (0). If $\mathfrak{p} \neq 0$, pick $0 \neq a \in \mathfrak{p}$, which is not a unit, and write $a = q_1 \cdots q_k$ with irreducible q_i (definition 10.1.21). As $\mathfrak{p}$ is prime, some $q_i \in \mathfrak{p}$, and q_i is a prime element (proposition 10.1.29), so (q_i) is a nonzero prime ideal. It is maximal by definition 50.2.1, and $(q_i) \subseteq \mathfrak{p} \neq R$, so $\mathfrak{p} = (q_i)$.

   Next, suppose some ideal of R is not principal. Since R is Noetherian, the nonempty set of non-principal ideals has a maximal element I (proposition 23.1.3). Then $I \neq R$, and I is not prime by the previous paragraph, so there are $a, b \in R \setminus I$ with $ab \in I$. The ideal $I + (a)$ strictly contains I, so $I + (a) = (c)$ for some c, by maximality. Let $J = \{x \in R \mid xc \in I\}$, an ideal containing I. Writing $c = i + ra$ with $i \in I$ and $r \in R$ gives $bc = bi + r(ab) \in I$, so $b \in J \setminus I$ and $J = (d)$ for some d, again by maximality. Now $cd \in I$ because $d \in J$, and every $x \in I \subseteq (c)$ has the form $x = yc$ with $y \in R$, where $yc \in I$ gives $y \in J = (d)$, so $x \in (cd)$. Hence $I = (cd)$ is principal, a contradiction. So every ideal of R is principal, and R is a PID, completing the proof.

For algebro-geometric purposes, the following characterizes Dedekind domains locally:

Lemma 50.2.4: Dedekind Domain As DVR

Let R be a Noetherian integral domain. Then R is a Dedekind domain if and only if for each nonzero prime P, R_P is a DVR. Thus, Dedekind domains are locally DVR's.

***Proof*:**
If R is a field, then both sides hold: R satisfies the three conditions of definition 50.2.1 (the second vacuously), and R has no nonzero prime. So assume R is not a field.

($\Rightarrow$) Let $P \neq 0$ be a prime of R and localize at $D = R \setminus P$. By proposition 23.4.7, R_P is a Noetherian integrally closed domain with fraction field $K(R)$. By proposition 23.4.5, the primes of R_P correspond bijectively to the primes of R contained in P. These are 0 and P alone, for a nonzero prime contained in P is maximal by definition 50.2.1 and hence equals P. Thus R_P is local of Krull dimension 1 with unique nonzero prime PR_P (nonzero because the correspondence is a bijection and $P \neq 0$). By theorem 27.2.2, an integrally closed Noetherian local domain of dimension 1 is a DVR.

($\Leftarrow$) We verify the three conditions of definition 50.2.1. R is Noetherian by hypothesis. For the second condition, let $P \neq 0$ be prime and choose a maximal ideal $\mathfrak{m} \supseteq P$ (proposition 9.4.18). Since R is not a field, $\mathfrak{m} \neq 0$, so $R_{\mathfrak{m}}$ is a DVR, and by proposition 27.2.1 it has a unique nonzero

prime ideal. Under the correspondence of proposition 23.4.5, P and $\mathfrak{m}$ give two nonzero primes of $R_{\mathfrak{m}}$, so $PR_{\mathfrak{m}} = \mathfrak{m}R_{\mathfrak{m}}$ and hence $P = \mathfrak{m}$ is maximal. For normalness, let $x \in K(R)$ be integral over R. A monic equation for x over R is a monic equation over each $R_{\mathfrak{m}}$, and each $R_{\mathfrak{m}}$, being a DVR and in particular a valuation ring, is integrally closed (proposition 27.1.8(5)), so $x \in R_{\mathfrak{m}}$ for every maximal ideal $\mathfrak{m}$. By proposition 23.4.18, $R = \bigcap_{\mathfrak{m}} R_{\mathfrak{m}}$ inside $K(R)$, hence $x \in R$, as we sought to show.

Lemma 50.2.5: Dedekind Domains And Localization

Let R be a Dedekind domain and $S \subseteq R \setminus \{0\}$ is a multiplicative subset. Then $S^{-1}R$ is also a Dedekind Domain.

***Proof*:**
The localization of Noetherian rings is Noetherian, and by the correspondence of ideals in localizations, we have that prime implies maximal in $S^{-1}R$. Finally, $S^{-1}R$ is integrally closed since if $x \in K = K(R)$ satisfies:

$$x^n + \frac{a_1}{s_1}x^{n-1} + \cdots + \frac{a_n}{s_n} = 0 \qquad \frac{a_i}{s_i} \in S^{-1}R$$

Then multiplying with the nth power of $s_1 \cdots s_n$ gives that sx is integral over R, hence $sx \in R$, and so $x \in S^{-1}R$, as we sought to show.

Importantly for number theory, all rings of integers are Dedekind domains:

Theorem 50.2.6: Ring Of Integers Are Dedekind Domains

Let $\mathcal{O}_K$ be a ring of integers. Then it is a Dedekind domain.

***Proof*:**

By proposition 50.1.32, $\mathcal{O}_K$ is Noetherian, and by definition $\mathcal{O}_K$ is normal, namely $\mathcal{O}_K = \overline{\mathbb{Z}}^K$ meaning by corollary 26.1.6:

$$\overline{\mathcal{O}_K}^K = \overline{\overline{\mathbb{Z}}^K}^K = \overline{\mathbb{Z}}^K$$

What's left to show is that every prime ideal is maximal, which is equivalent to showing $\mathcal{O}_K/\mathfrak{p}$ is a field. In particular, since $\mathcal{O}_K/\mathfrak{p}$ is always an integral domain, if we show that it is finite then by corollary 9.1.25 we shall have that it's a field. The key intuition comes from the fact that $\mathcal{O}_K$ and its ideals form a lattice, meaning when we quotient we necessarily get a finite ring. Furthermore, the volume of the ideal is determined by the discriminant and the index, which will determine the cardinality of the quotient ring[a]

Let $0 \neq \alpha \in \mathfrak{p}$. Then $(p) = \mathfrak{p} \cap \mathbb{Z}$ is also a prime ideal. Since $\mathfrak{p} \subseteq \mathcal{O}_K$, we know α is associated to a minimal polynomial $m_{\alpha,\mathbb{Z}}(x)$ where

$$m_{\alpha,\mathbb{Z}}(\alpha) = \alpha^n + a_{n-1}\alpha^{n-1} + \cdots + a_1\alpha + a_0 = 0 \qquad a_i \in \mathbb{Z}$$

Then $a_0 = -(\alpha^n + a_{n-1}\alpha^{n-1} + \cdots + a_1\alpha) \in \mathfrak{p} \subseteq \mathcal{O}_K$, and since $m_{\alpha,\mathbb{Q}}(x)$ is irreducible with integer coefficients, $a_0 \neq 0$ and $a_0 \in (p) = p\mathbb{Z}$. From here, we shall give two proofs: first, we

may directly appeal to the fact that

$$(\mathcal{O}_K/\mathfrak{p})/(\mathbb{Z}/p\mathbb{Z})$$

is an integral extension (see example 26.1.9) where the base ring is a field, hence $\mathcal{O}_K/\mathfrak{p}$ is a field by proposition 26.1.8. Another is the following: we have a non-trivial ideal with chains of inclusions $(a_0) \subseteq \mathfrak{p} \subseteq \mathcal{O}_K$ implying

$$|\mathcal{O}_K/\mathfrak{p}| \leq |\mathcal{O}_K/(a_0)| = |\mathcal{O}_K/a_0\mathcal{O}_K|$$

Now, since we are quotienting ideals, this is a $\mathbb{Z}$-module quotient, and since we are quotienting n-rank free $\mathbb{Z}$-modules, we get that

$$|\mathcal{O}_K/(a_0)| = |a_0|^n$$

But then $\mathcal{O}_K/\mathfrak{p}$ is finite (its order divides $|a_0|^n$). Thus, $\mathfrak{p}$ must be maximal, and since $\mathfrak{p}$ was arbitrary every prime ideal is maximal, completing the proof.

[a]We shall soon see that the index can be thought of as the "norm" of a general ideal; this will mean the constant term of a minimal polynomial represent the "size", sheading some light on the proof

Since in general $\mathcal{O}_K$ is not a Unique Factorization Domain, rings of integers represent a class of rings where prime implies maximal, but factorization is not unique. In this way, we see that the integral closure of $\mathbb{Z}$ with respect to K may be far from having the nice element-wise properties we are used to in PIDs, but this shall be salvaged through having an understandable ideal structure and a way to measure how far away our ring is from being a PID.

Another important example of a Dedekind domain that is not a number ring is the ring is $k[x]$ (since it's a PID). We shall later see that integral extensions of Dedekind domains are Dedekind domains, an so these types of rings will form a basis for another large class of Dedekind domains that are not number rings.

50.2.1 Fractional Ideals in Rings

Following from the idea that ideals are the generalisation of numbers, we may define the following divisibility notions usually used for the [algebraic] lattice of integers induced by divisibility. These concepts shall be defined for general commutative rings:

Definition 50.2.7: GCD, LCM, Divisibility Of Ideals

let R be a commutative ring, $\mathfrak{a}, \mathfrak{b} \subseteq R$ ideals of R. Then:

$$\gcd(\mathfrak{a}, \mathfrak{b}) = (\mathfrak{a}, \mathfrak{b}) = \mathfrak{a} + \mathfrak{b} \qquad \operatorname{lcm}(\mathfrak{a}, \mathfrak{b}) = \mathfrak{a} \cap \mathfrak{b}$$

And we can say that $\mathfrak{a}, \mathfrak{b}$ are relatively prime when $\gcd(\mathfrak{a}, \mathfrak{b}) = (1)$. Divisibility $\mathfrak{a} \big| \mathfrak{b}$ is defined as $\mathfrak{b} \subseteq \mathfrak{a}$, and hence we have an order and the ideals similar to that given by divisibility.

As we have seen in chapter 10, gcd and lcm are usually well-behaved in special classes of rings, usually UFDs. We shall show they are well-behaved in Dedekind domains since the ideals shall have unique factorizations. Let's now prove some lemmas for this result.

One finiteness fact is needed throughout, and it is the reason the Noetherian hypothesis appears in the definition of a Dedekind domain at all: in a Noetherian domain every nonzero proper ideal *contains* a product of nonzero prime ideals, each of which contains it (corollary 23.1.6). An ideal need not factor into primes (that is the theorem this section works toward, and it needs the full strength of a Dedekind domain), but it always contains such a product, and that much is available from the Noetherian condition alone.

For the following lemmas, we bring back the notion of fractional ideal that was defined in chapter 23. These ideals were at the time a way of extending ideals into the ring of fractions, and were shown to work well with localization. Due to all the properties of Dedekind domains, the product of ideals can be made into a *group*, even an *abelian group*. Since the fractional ideal structure will have such a strong restriction, this will produce incredible results on the relations between ideals. To begin, the following lemma shows that no prime ideal acts like the identity:

Lemma 50.2.8: Fractional Ideals

Let $P \subseteq R$ be a nonzero prime ideal of the Dedekind domain R, $K = K(R)$. Define

$$(R :_K P) = P^{-1} = \{x \in K \mid xP \subseteq R\}$$

Then

$$AP^{-1} = \left\{ \sum_i a_i x_i \;\middle|\; a_i \in A,\ x_i \in P^{-1} \right\} \neq A$$

for every ideal $0 \neq A \subseteq R$

Note that by definition $R \subseteq P^{-1}$ and so P^{-1} is not in general an ideal. The simplest "fractional ideal" would be those of $\mathbb{Z}$, namely $(n)^{-1} = \frac{1}{n}\mathbb{Z}$.

***Proof*:**

Step 1: $P^{-1} \neq R$. Let $0 \neq a \in P$. The ideal aR is nonzero and proper, so it contains a product $P_1 \cdots P_r$ of nonzero primes (corollary 23.1.6). Choose such a product with r minimal. As $P_1 \cdots P_r \subseteq aR \subseteq P$ and P is prime, some P_i lies in P: otherwise elements $a_i \in P_i \setminus P$ would give $a_1 \cdots a_r \in P$. Renumber so that $P_1 \subseteq P$. Nonzero primes of R are maximal (definition 50.2.1), so $P_1 = P$. By minimality of r, the product $P_2 \cdots P_r$ (which is R when $r = 1$) is not contained in aR, so there is $b \in P_2 \cdots P_r$ with $b \notin aR$. Then $bP = bP_1 \subseteq P_1 \cdots P_r \subseteq aR$, so $(b/a)P \subseteq R$ and $b/a \in P^{-1}$, while $b/a \notin R$. Hence $P^{-1} \neq R$.

Step 2: $AP^{-1} \neq A$. Suppose $AP^{-1} = A$ for an ideal $A \neq 0$, and let $x \in P^{-1}$. Then $xA \subseteq A$, so $x^k A \subseteq A$ for every $k \geq 0$. Fix $0 \neq c \in A$. Then $x^k c \in A \subseteq R$ for every k, so $cR[x]$ is an R-submodule of R, that is, an ideal, and it is finitely generated because R is Noetherian (proposition 23.1.3). Then $R[x] = c^{-1}(cR[x])$ is a finitely generated R-module, so x is integral over R (proposition 26.1.4), and $x \in R$ because R is integrally closed (definition 50.2.1). So $P^{-1} \subseteq R$, contradicting Step 1, completing the proof.

Definition 50.2.9: Fractional Ideal and Quotient ideal

Let R be an integral domain and $K = K(R)$. Then a *fractional ideal* J of K is a finitely generated non-trivial R-submodule of K where there exists a nonzero $r \in R$ such that $rJ \subseteq R$ is an ideal.
If $I, J \subseteq R$ are ideals, then the *quotient ideal* of I with respect to J is:

$$(I : J) = \{x \in K \mid xJ \subseteq I\}$$

If $I = R$,then $(R : J)$ is denoted J^{-1}

Fractional ideals are multiplied in the similar way ideals are multiplied: IJ is the set of finite sums of products xy with $x \in I$ and $y \in J$. Every nonzero finitely generated ideal of R is a fractional ideal, with $r = 1$. For those who are motivated by algebraic geometry, fractional ideals play the role of line bundles over the smooth $\mathbb{Z}$-curves $\mathcal{O}_K$[14].

Quotient ideals have a lot of interesting theory, for example to motivate their name if J is principle and $I \subseteq J$, then $I = J \cdot (I : J)$. There is no room in this chapter to explore these in detail, hence they are left as exercises 50.2.1(50.2.1 (6)).

Fractional ideals that are ideals are given a name:

Definition 50.2.10: Integral Ideals

Let R be an integral domain and $K = K(R)$. A fractional ideal $I \subseteq K$ with $I \subseteq R$ is called an *integral ideal*. Equivalently, an integral ideal is a nonzero finitely generated ideal of R, and when R is Noetherian every nonzero ideal of R is integral.

Example 50.2.11: Fractional Ideal

1. Since $\mathbb{Z}$ is a Principal Ideal Domain, every ideal is of the form $a\mathbb{Z}$ for $a \in \mathbb{Z}$. Then $(a)^{-1} = a^{-1}\mathbb{Z}$. Hence, the fractional ideals are in bijective correspondence with $\mathbb{Q}^{\times}_{>0}$. Naturally, all ideals of $\mathbb{Z}$ are fractional ideals, in particular they are integral ideals.
2. More generally, if $a \in K^{\times}$, then $(a) = aR$ is a fractional principal ideal, and $aR = bR$ exactly when $a/b \in R^{\times}$, giving a bijective correspondence between the principal fractional ideals and $K^{\times}/R^{\times}$.

In a Noetherian domain the two conditions of definition 50.2.9 imply each other:

[14] See section 50.7 for rings of integers as smooth $\mathbb{Z}$-curves, and for invertible fractional ideals and the Picard group of an order

Corollary 50.2.12: Fractional Ideal Representative

Let R be a Noetherian domain, $K = K(R)$, and $\mathfrak{a} \subseteq K$ a nonzero R-submodule. Then $\mathfrak{a}$ is finitely generated if and only if $r\mathfrak{a} \subseteq R$ for some $r \in R \setminus \{0\}$. In that case $\mathfrak{a}$ is a fractional ideal, $I = r\mathfrak{a}$ is a nonzero ideal of R with

$$\mathfrak{a} = r^{-1}I$$

and multiplication by r is an isomorphism of R-modules $\mathfrak{a} \cong_R I$. If $R = \mathcal{O}_K$ for a number field K, then r may be taken in $\mathbb{Z}_{>0}$.

***Proof*:**
Step 1: generators give a denominator. Let $\mathfrak{a} = R\alpha_1 + \cdots + R\alpha_n$ and write $\alpha_i = a_i/b_i$ with $a_i, b_i \in R$ and $b_i \neq 0$. For $r = b_1 \cdots b_n \neq 0$, every $r\alpha_i$ lies in R, so $r\mathfrak{a} \subseteq R$.

Step 2: a denominator gives generators. If $r\mathfrak{a} \subseteq R$ with $r \neq 0$, then $I = r\mathfrak{a}$ is an R-submodule of R, that is, an ideal, nonzero because $\mathfrak{a} \neq 0$ and R is a domain. It is finitely generated as R is Noetherian (proposition 23.1.3), say by $y_1, \ldots, y_m$, and then $\mathfrak{a} = r^{-1}I$ is generated by $r^{-1}y_1, \ldots, r^{-1}y_m$. Multiplication by r is R-linear, and bijective from $\mathfrak{a}$ onto I since r is invertible in K.

Step 3: integer denominators. Let $R = \mathcal{O}_K$ and $r\mathfrak{a} \subseteq \mathcal{O}_K$ with $r \neq 0$. The index $d = [\mathcal{O}_K : r\mathcal{O}_K]$ is a positive integer (proposition 50.1.62), and $d \cdot 1 \in r\mathcal{O}_K$ by theorem 3.3.1, say $d = ru$ with $u \in \mathcal{O}_K$. Then $d\mathfrak{a} = u(r\mathfrak{a}) \subseteq \mathcal{O}_K$, completing the proof.

Notice that this generalizes the definition of ideals, if R is a Dedekind ring over itself, then the ideals of R are the finitely generated sub-modules. Then if $K = \mathrm{Frac}(R)$, the fractional ideals are the finitely generated K-modules.

Corollary 50.2.13: Inverse of Prime Ideals

Let R be a Dedekind domain and $\mathfrak{p} \subseteq R$ be a nonzero prime ideal. Then:

$$\mathfrak{p}\mathfrak{p}^{-1} = (1)$$

***Proof*:**
If $x \in \mathfrak{p}\mathfrak{p}^{-1}$, then $x = \sum p_i k_i$ for $p_i \in \mathfrak{p}$ and $k_i \in \mathfrak{p}^{-1}$. But by definition of $\mathfrak{p}^{-1}$, we have that $p_i k_i \in R$, hence $x \in R$, and so $\mathfrak{p}\mathfrak{p}^{-1} \subseteq R$. Next, $1 \in \mathfrak{p}^{-1}$ gives $\mathfrak{p} \subseteq \mathfrak{p}\mathfrak{p}^{-1} \subseteq R$. Since $\mathfrak{p}$ is maximal (definition 50.2.1), either $\mathfrak{p}\mathfrak{p}^{-1} = \mathfrak{p}$ or $\mathfrak{p}\mathfrak{p}^{-1} = R$. The former is a contradiction by lemma 50.2.8, and hence $\mathfrak{p}\mathfrak{p}^{-1} = (1)$, completing the proof.

Lemma 50.2.14: Invariance Number Ring Multiplication

Let R be a Dedekind domain with fraction field K, $\mathfrak{a} \subseteq K$ a fractional ideal and $t \in K$. If $t\mathfrak{a} \subseteq \mathfrak{a}$, then $t \in R$.

***Proof*:**
From $t\mathfrak{a} \subseteq \mathfrak{a}$ we get $t^k\mathfrak{a} \subseteq \mathfrak{a}$ for every $k \geq 0$. Fix $0 \neq c \in \mathfrak{a}$ and a nonzero $r \in R$ with $r\mathfrak{a} \subseteq R$ (definition 50.2.9). Then $rct^k \in r\mathfrak{a} \subseteq R$ for every k, so $rcR[t]$ is an R-submodule of R, that is, an ideal, finitely generated as R is Noetherian (proposition 23.1.3). Hence $R[t] = (rc)^{-1}(rcR[t])$ is a finitely generated R-module, t is integral over R (proposition 26.1.4), and $t \in R$ because R is integrally closed (definition 50.2.1), completing the proof.

50.2.2 Prime Decomposition in Dedekind Domain

With these properties, we may show the factorization of prime ideals in Dedekind domains.

Theorem 50.2.15: Unique Factorization Of Ideals In Dedekind Domains

Let R be a Dedekind Domain and $\mathfrak{a} \subseteq R$ a non-trivial proper ideal. Then there exists unique $\mathfrak{p}_1, \mathfrak{p}_2, ..., \mathfrak{p}_n$ such that

$$\mathfrak{a} = \mathfrak{p}_1\mathfrak{p}_2 \cdots \mathfrak{p}_n$$

***Proof*:**
We start with the existence of such a factorization. Let $\mathfrak{M}$ be the set of all non-trivial proper ideals which do not admit a prime ideal decomposition. If $\mathfrak{M}$ is non-empty, then since R is Noetherian there exists a maximal element, say $\mathfrak{m}$. Then this ideal is contained in some maximal ideal $\mathfrak{p}$. Since $R \subseteq \mathfrak{p}^{-1}$, we get the following chain of inclusions:

$$\mathfrak{m} \subseteq \mathfrak{m}\mathfrak{p}^{-1} \subseteq \mathfrak{p}\mathfrak{p}^{-1} \subseteq R$$

by lemma 50.2.8, we have $\mathfrak{m} \subsetneq \mathfrak{m}\mathfrak{p}^{-1}$ and $\mathfrak{p} \subsetneq \mathfrak{p}\mathfrak{p}^{-1} \subseteq R$. By maximality of $\mathfrak{p}$, $\mathfrak{p}\mathfrak{p}^{-1} = R$. If $\mathfrak{m}\mathfrak{p}^{-1} = R$, then $\mathfrak{m} = \mathfrak{m}\mathfrak{p}^{-1}\mathfrak{p} = \mathfrak{p}$ would be its own prime decomposition. So $\mathfrak{m}\mathfrak{p}^{-1}$ is a nonzero proper ideal strictly containing $\mathfrak{m}$, and by maximality of $\mathfrak{m}$ in $\mathfrak{M}$ it admits a prime ideal decomposition, say

$$\mathfrak{m}\mathfrak{p}^{-1} = \mathfrak{p}_1 \cdots \mathfrak{p}_r$$

But then, since $\mathfrak{p}\mathfrak{p}^{-1} = R$, $\mathfrak{m}R = \mathfrak{m}$ and so

$$\mathfrak{m} = \mathfrak{m}\mathfrak{p}^{-1}\mathfrak{p} = \mathfrak{p}_1 \cdots \mathfrak{p}_r\mathfrak{p}$$

contradicting the definition of $\mathfrak{m}$. Hence $\mathfrak{M}$ is an empty-set

For uniqueness, let

$$\mathfrak{a} = \mathfrak{p}_1\mathfrak{p}_2 \cdots \mathfrak{p}_r = \mathfrak{q}_1\mathfrak{q}_2 \cdots \mathfrak{q}_s$$

be two prime ideal factorizations of $\mathfrak{a}$. Then by the repeated application of property of prime ideals ($\mathfrak{a}\mathfrak{b} \subseteq P \Rightarrow \mathfrak{a} \subseteq P$ or $\mathfrak{b} \subseteq P$), we have that $\mathfrak{p}_1$ divides a factor of the right hand side, say $\mathfrak{q}_1$, and by maximality is thus equal to $\mathfrak{q}_1$. Then we can multiply both sides by $\mathfrak{p}_1^{-1}$ and since $\mathfrak{p}_1 \neq \mathfrak{p}_1\mathfrak{p}_1^{-1} = R$ we get

$$\mathfrak{p}_2 \cdots \mathfrak{p}_r = \mathfrak{q}_2 \cdots \mathfrak{q}_s$$

Then proceeding inductively, we will get that $r = s$ and $\mathfrak{p}_i = \mathfrak{q}_i$, up to renumbering, completing the proof.

50.2.16 Note The converse holds as well: an integral domain in which every nonzero proper ideal factors uniquely into prime ideals is a Dedekind domain, so this theorem characterizes Dedekind domains. The converse is not used in this book.

From now on, we shall group the prime ideals to write

$$\mathfrak{a} = \mathfrak{p}_1^{n_1} \cdots \mathfrak{p}_r^{n_r} \qquad n_i > 0$$

If $\mathfrak{a} = (a)$ is a principal ideal, we shall use the slight abuse of notation and write

$$a = \mathfrak{p}_1^{n_1} \cdots \mathfrak{p}_r^{n_r} \qquad n_i > 0$$

Similarly, we shall often write $\mathfrak{a} \big| a$ instead of $\mathfrak{a} \big| (a)$. An important result worth emphasizing is the structure of R/I for an ideal $I \subseteq R$. It rests on the following lemma:

Lemma 50.2.17: Powers Of Comaximal Ideals

Let R be a commutative ring and $\mathfrak{a}, \mathfrak{b} \subseteq R$ ideals with $\mathfrak{a} + \mathfrak{b} = R$. Then $\mathfrak{a}^m + \mathfrak{b}^l = R$ for all $m, l \geq 1$. In particular, in a Dedekind domain, powers of distinct nonzero primes are comaximal.

***Proof*:**
Write $1 = x + y$ with $x \in \mathfrak{a}$ and $y \in \mathfrak{b}$. In the binomial expansion of $1 = (x+y)^{m+l-1}$, the term containing $x^j y^{m+l-1-j}$ lies in $\mathfrak{a}^m$ if $j \geq m$, and otherwise $m + l - 1 - j \geq l$ and it lies in $\mathfrak{b}^l$. So $1 \in \mathfrak{a}^m + \mathfrak{b}^l$. Distinct nonzero primes $\mathfrak{p} \neq \mathfrak{q}$ of a Dedekind domain are maximal (definition 50.2.1), so $\mathfrak{q} \not\subseteq \mathfrak{p}$, the ideal $\mathfrak{p} + \mathfrak{q}$ strictly contains $\mathfrak{p}$, and $\mathfrak{p} + \mathfrak{q} = R$. The first part then applies, completing the proof.

Then by lemma 50.2.17 and the Chinese Remainder Theorem:

$$R/I = \bigoplus_i R/P_i^{n_i}$$

By the 4th isomorphism theorem, $\overline{I} \subseteq R/P_i^{n_i}$ if and only if $P_i^{n_i} \subseteq I$, that is $I \big| P_i^{n_i}$. But by unique factorization, that means that $I = P_i^k$ for $1 \leq k \leq n_i$. Hence, every quotient has only finitely many ideals, each ideal I corresponding to a set of prime power of the decomposition of I via the isomorphism given by the CRT. This matches with the result that $R/(a)$ is a finite ring, showing there can only be finitely many ideals, and the prime factorization theorem for ideals gives us the structure of the ideals of $R/(a)$ through the correspondence given by the 4th isomorphism theorem. This also immediately shows that R/I is *Artinian*[15].

Using the fact that ideals factor and "behave" like the positive rational numbers ($-\mathfrak{p} = \mathfrak{p}$ since -1 is a unit), we can conclude some powerful results. We have shown that every ideal has a unique inverse. This immediately shows that:

$$\mathfrak{ab} = \mathfrak{ac} \quad \Longrightarrow \quad \mathfrak{b} = \mathfrak{c}$$

by the Cancellation law. Next, it is easy to see is that we may generalize the notion of finding GCD and LCM of UFD's to Dedekind domains:

[15] Equivalently, $\operatorname{kdim}(R/I) = 0$, and hence it is Artinian

Corollary 50.2.18: GCD, LCM, and Divisibility In Dedekind Domains

Let R be a Dedekind domain and $\mathfrak{a}, \mathfrak{b} \subseteq R$ nonzero ideals, written $\mathfrak{a} = P_1^{a_1} \cdots P_k^{a_k}$ and $\mathfrak{b} = P_1^{b_1} \cdots P_k^{b_k}$ with distinct nonzero primes P_i and exponents $a_i, b_i \geq 0$. Then

1. $\operatorname{lcm}(\mathfrak{a}, \mathfrak{b}) = P_1^{\max(a_1,b_1)} \cdots P_k^{\max(a_k,b_k)}$
2. $\gcd(\mathfrak{a}, \mathfrak{b}) = P_1^{\min(a_1,b_1)} \cdots P_k^{\min(a_k,b_k)}$
3. $\mathfrak{a} \mid \mathfrak{b}$ if and only if there exists an ideal $\mathfrak{c} \subseteq R$ such that $\mathfrak{ac} = \mathfrak{b}$, if and only if $a_i \leq b_i$ for every i

***Proof*:**
Step 1: divisibility and products. If $\mathfrak{ac} = \mathfrak{b}$ for an ideal $\mathfrak{c}$, then $\mathfrak{b} = \mathfrak{ac} \subseteq \mathfrak{a}R = \mathfrak{a}$, that is, $\mathfrak{a} \mid \mathfrak{b}$ (definition 50.2.7). Conversely let $\mathfrak{b} \subseteq \mathfrak{a}$. Write $\mathfrak{a} = \mathfrak{p}_1 \cdots \mathfrak{p}_r$ with nonzero primes $\mathfrak{p}_j$ (theorem 50.2.15, the empty product if $\mathfrak{a} = R$) and put $\mathfrak{a}' = \mathfrak{p}_1^{-1} \cdots \mathfrak{p}_r^{-1}$. Multiplication of R-submodules of $K(R)$ is associative and commutative, so $\mathfrak{aa}' = \prod_j \mathfrak{p}_j \mathfrak{p}_j^{-1} = R$ by corollary 50.2.13. Then $\mathfrak{c} = \mathfrak{a}'\mathfrak{b} \subseteq \mathfrak{a}'\mathfrak{a} = R$ is an ideal with $\mathfrak{ac} = \mathfrak{aa}'\mathfrak{b} = \mathfrak{b}$.

Step 2: the exponent criterion. Let $\mathfrak{x} = \prod_i P_i^{x_i}$ and $\mathfrak{y} = \prod_i P_i^{y_i}$ be nonzero ideals with exponents $x_i, y_i \geq 0$. If $x_i \leq y_i$ for every i, then $\mathfrak{y} = \mathfrak{x} \prod_i P_i^{y_i - x_i}$, so $\mathfrak{x} \mid \mathfrak{y}$ by Step 1. Conversely, let $\mathfrak{z} \mid \mathfrak{y}$ for a nonzero ideal $\mathfrak{z}$. Step 1 gives $\mathfrak{y} = \mathfrak{zc}$ with $\mathfrak{c} \neq 0$, and concatenating factorizations of $\mathfrak{z}$ and $\mathfrak{c}$ gives one of $\mathfrak{y}$. By the uniqueness in theorem 50.2.15, every prime occurring in $\mathfrak{z}$ or $\mathfrak{c}$ is one of the P_i, so $\mathfrak{z} = \prod_i P_i^{z_i}$ and $\mathfrak{c} = \prod_i P_i^{c_i}$, and $y_i = z_i + c_i \geq z_i$. So every nonzero divisor of $\mathfrak{y}$ is a product of the P_i, and $\mathfrak{x} \mid \mathfrak{y}$ exactly when $x_i \leq y_i$ for every i. With $\mathfrak{x} = \mathfrak{a}$ and $\mathfrak{y} = \mathfrak{b}$ this proves (3).

Step 3: the gcd. The ideal $\mathfrak{g} = \mathfrak{a} + \mathfrak{b}$ contains $\mathfrak{a}$, so $\mathfrak{g} \mid \mathfrak{a}$, and by Step 2 it is a product $\mathfrak{g} = \prod_i P_i^{g_i}$. As $\mathfrak{g} \mid \mathfrak{a}$ and $\mathfrak{g} \mid \mathfrak{b}$, Step 2 gives $g_i \leq \min(a_i, b_i)$. The ideal $\mathfrak{d} = \prod_i P_i^{\min(a_i,b_i)}$ divides $\mathfrak{a}$ and $\mathfrak{b}$ by Step 2, that is, $\mathfrak{a} \subseteq \mathfrak{d}$ and $\mathfrak{b} \subseteq \mathfrak{d}$, so $\mathfrak{g} = \mathfrak{a} + \mathfrak{b} \subseteq \mathfrak{d}$ and $\mathfrak{d} \mid \mathfrak{g}$, giving $\min(a_i, b_i) \leq g_i$. So $\mathfrak{g} = \mathfrak{d}$, which is (2).

Step 4: the lcm. The ideal $\mathfrak{l} = \mathfrak{a} \cap \mathfrak{b}$ contains $\mathfrak{ab} = \prod_i P_i^{a_i + b_i} \neq 0$, so $\mathfrak{l} \mid \mathfrak{ab}$, and by Step 2 it is a product $\mathfrak{l} = \prod_i P_i^{l_i}$. As $\mathfrak{l} \subseteq \mathfrak{a}$ and $\mathfrak{l} \subseteq \mathfrak{b}$, Step 2 gives $l_i \geq \max(a_i, b_i)$. The ideal $\mathfrak{m} = \prod_i P_i^{\max(a_i,b_i)}$ is divisible by $\mathfrak{a}$ and by $\mathfrak{b}$, that is, $\mathfrak{m} \subseteq \mathfrak{a} \cap \mathfrak{b} = \mathfrak{l}$, so $\mathfrak{l} \mid \mathfrak{m}$ and $l_i \leq \max(a_i, b_i)$. So $\mathfrak{l} = \mathfrak{m}$, which is (1), completing the proof.

We know that every ideal has an inverse. However, that inverse is a fractional ideal. Fortunately, there always exists an integral ideal that is "almost" the inverse, in that the product is a principal ideal[16]:

[16] this almost inverse can be made into a concrete inverse when we show the principal ideals form a normal subgroup formed by the group of fractional ideals

Corollary 50.2.19: Exists J such that IJ is Principal

Let R be a Dedekind Domain and $I \subseteq R$ an ideal. Then there exists an ideal $J \subseteq R$ such that $IJ = (a)$ for some element $a \in I$. In other words, there exists an ideal J such that the product IJ is principal. If $I \neq 0$, then J and a may be taken nonzero.

***Proof*:**
If $I = 0$, take $J = R$ and $a = 0$, and if $I = R$, take $J = R$ and $a = 1$. Otherwise let $I = P_1^{n_1} \cdots P_k^{n_k}$ with distinct nonzero primes P_i and $n_i \geq 1$. By unique factorization $P_i^{n_i} \neq P_i^{n_i+1}$, so we may choose $r_i \in P_i^{n_i} \setminus P_i^{n_i+1}$. The ideals $P_i^{n_i+1}$ are pairwise comaximal (lemma 50.2.17), so by theorem 9.6.11 there exists an $a \in R$ such that

$$a \equiv r_i \bmod P_i^{n_i+1} \qquad 1 \leq i \leq k$$

Thus, $a \in P_i^{n_i} \setminus P_i^{n_i+1}$ for each i, so $a \neq 0$, and by corollary 50.2.18(3) the power of P_i in the factorization of (a) is exactly n_i. Now, taking the prime factorization of (a), we get:

$$(a) = P_1^{n_1} \cdots P_k^{n_k} P_{k+1}^{n_{k+1}} \cdots P_m^{n_m}$$

with further distinct primes $P_{k+1}, \ldots, P_m$. Letting $J = P_{k+1}^{n_{k+1}} \cdots P_m^{n_m}$ gives us

$$(a) = IJ$$

and $a \in I$ because $(a) = IJ \subseteq I$, completing the proof.

In section 50.3.1, we shall find a more systematic way of finding the prime ideals that multiply to get a principal ideal using Galois groups. As seen with rings of integers, not all Dedekind domains are PIDs since they are not all UFDs. With the factorization theorem, we get that they are the next best thing:

Corollary 50.2.20: PIR, and Generation Of Ideals In Dedekind Domains

Let R be a Dedekind domain.

1. If $0 \neq I \subseteq J$ are ideals of R, then $J = I + aR$ for some $a \in J$.
2. For every nonzero ideal $I \subseteq R$, the ring R/I is a principal ideal ring.
3. Every ideal of R is generated by *at most* 2 elements.

***Proof*:**
Step 1: proof of (1). If $I = R$, take $a = 0$. Otherwise write $I = P_1^{n_1} \cdots P_s^{n_s}$ with distinct nonzero primes P_i and $n_i \geq 1$ (theorem 50.2.15). As $J \big| I$, corollary 50.2.18(3) gives $J = P_1^{k_1} \cdots P_s^{k_s}$ with $0 \leq k_i \leq n_i$. By unique factorization $P_i^{k_i} \neq P_i^{k_i+1}$, so we may choose $r_i \in P_i^{k_i} \setminus P_i^{k_i+1}$. The ideals $P_i^{k_i+1}$ are pairwise comaximal (lemma 50.2.17), and theorem 9.6.11 gives $a \in R$ with $a - r_i \in P_i^{k_i+1}$ for every i. Then $a \in P_i^{k_i} \setminus P_i^{k_i+1}$, so by corollary 50.2.18(3) the exponent of P_i in aR is exactly k_i. By corollary 50.2.18(2), $I + aR = \gcd(I, aR)$ has exponent $\min(n_i, k_i) = k_i$ at each P_i and exponent 0 at every other prime, so $I + aR = J$, and $a \in J$.

Step 2: proof of (2). By theorem 9.3.15, every ideal of R/I has the form J/I for an ideal $J \supseteq I$ of R. By (1), $J = I + aR$, so J/I is generated by $a + I$.

Step 3: proof of (3). The zero ideal is generated by 0. If $J \neq 0$, choose $0 \neq \alpha \in J$ and apply (1) to $I = \alpha R \subseteq J$: then $J = \alpha R + aR = (\alpha, a)$, completing the proof.

In particular, if $\mathfrak{p} \big| (p)$ for a prime number p, then corollary 50.2.20(1) with $I = (p)$ and $J = \mathfrak{p}$ gives an element $\alpha \in \mathfrak{p}$ such that $\mathfrak{p} = (p, \alpha)$. Hence the primes above p are recovered by adding an appropriate element to (p). Our final result shows all pairs of ideals are, up to a multiple of $K(R)$, relatively prime. This mirrors the property that if $\gcd(a, b) = c$, we can divide a by c to get $\gcd(a/c, b) = 1$:

Corollary 50.2.21: Always Almost Relatively Prime

Let R be a Dedekind domain with fraction field K, A a fractional ideal and B a nonzero ideal of R. Then there is $c \in K^\times$ such that cA is an ideal of R with $cA + B = R$. In particular, for fractional ideals A, B there are $x, y \in K^\times$ such that xA and yB are relatively prime ideals of R.

***Proof*:**
Step 1: integral A. Suppose first that $A \subseteq R$, a nonzero ideal. By corollary 50.2.19 there are a nonzero ideal I and $0 \neq a \in A$ with $AI = aR$. The ideal BI is nonzero and contained in I, so corollary 50.2.20(1) gives $b \in I$ with $I = BI + bR$. Multiplying by A, and using that multiplication of ideals distributes over sums,

$$aR = AI = ABI + bA = aB + bA$$

Multiplying by a^{-1} gives $R = B + (b/a)A$, where $(b/a)A \subseteq a^{-1}(aR) = R$. If $b \neq 0$, then $c = b/a$ works. If $b = 0$, then $B = R$, and $c = 1$ works.

Step 2: the general case. For a fractional ideal A, choose $0 \neq r \in R$ with $rA \subseteq R$ (corollary 50.2.12). Step 1 applied to rA gives c_0 with $c_0 rA \subseteq R$ and $c_0 rA + B = R$, so $c = c_0 r$ works. For the last claim, choose $y \neq 0$ with $yB \subseteq R$ (corollary 50.2.12) and apply the first claim to A and the nonzero ideal yB, completing the proof.

With the division of ideals defined and mirroring the structure of $K^\times / R^\times$ ($\mathbb{Q}^\times_{>0}$ when working with $\mathbb{Z}$), it is tempting to say that they form a group structure, and this is indeed the case and is the focus in the remainder of this section.

One of the main metrics to measure is how many more "ideal numbers" need to be added to recover unique factorization into primes. If $\mathfrak{p}$ and $\mathfrak{q}$ are added, then if for some $t \in K$, $t\mathfrak{p} = \mathfrak{q}$, then $\mathfrak{p}$ and $\mathfrak{q}$ do not actually differ much in structure: it can be shown that $I = aJ$ ($a \in K(R)$) if and only if $I \cong_{\mathcal{O}_K} J$). Hence, we may classify "different" classes of ideals up to multiplication by a principal ideal. The more classes there are, the more a ring R fails to be a unique factorization domain. When R is a number ring, we shall show that there are only finitely many such classes.

The first result to prove is that the collection of fractional ideals of a Dedekind domain does indeed form a group:

Theorem 50.2.22: Ideal Group

Let R be a Dedekind domain, $K = K(R)$, and let J_K be the collection of fractional ideals. Then $(J_K, \cdot)$ has an abelian group structure via fractional ideal multiplication, and is called the *ideal group* of K. The inverse of $\mathfrak{a} \in J_K$ is $\mathfrak{a}^{-1} = (R : \mathfrak{a}) = \{x \in K \mid x\mathfrak{a} \subseteq R\}$.

***Proof*:**
Step 1: a commutative monoid. Let $\mathfrak{a}, \mathfrak{b} \in J_K$, generated by $\alpha_1, \dots, \alpha_m$ and $\beta_1, \dots, \beta_l$, with $r\mathfrak{a} \subseteq R$ and $t\mathfrak{b} \subseteq R$ for nonzero $r, t \in R$. Then $\mathfrak{ab}$ is the R-submodule generated by the products $\alpha_i\beta_j$, it is nonzero because K is a field, and $rt\mathfrak{ab} \subseteq R$. So $\mathfrak{ab} \in J_K$. Multiplication of submodules is associative and commutative because multiplication in K is, and $R\mathfrak{a} = \mathfrak{a}$, so R is an identity.

Step 2: integral ideals are invertible. For a nonzero prime $\mathfrak{p}$, the set $\mathfrak{p}^{-1}$ is a nonzero R-submodule of K containing 1. For $0 \neq a \in \mathfrak{p}$, $a\mathfrak{p}^{-1} \subseteq R$ is an ideal, finitely generated as R is Noetherian, so $\mathfrak{p}^{-1} = a^{-1}(a\mathfrak{p}^{-1})$ is finitely generated and $\mathfrak{p}^{-1} \in J_K$. A nonzero ideal $\mathfrak{a} \subseteq R$ is $\mathfrak{p}_1 \cdots \mathfrak{p}_r$ with nonzero primes $\mathfrak{p}_j$ (theorem 50.2.15, the empty product for $\mathfrak{a} = R$), and $\mathfrak{b} = \mathfrak{p}_1^{-1} \cdots \mathfrak{p}_r^{-1} \in J_K$ satisfies $\mathfrak{ab} = \prod_j \mathfrak{p}_j\mathfrak{p}_j^{-1} = R$ by corollary 50.2.13.

Step 3: all fractional ideals are invertible. Let $\mathfrak{a} \in J_K$ and $0 \neq r \in R$ with $r\mathfrak{a} \subseteq R$. The ideal $r\mathfrak{a}$ is nonzero, so it has an inverse $\mathfrak{c}$ by Step 2. Then $(r\mathfrak{c})\mathfrak{a} = \mathfrak{c}(r\mathfrak{a}) = R$, and $r\mathfrak{c} = (rR)\mathfrak{c} \in J_K$ is an inverse of $\mathfrak{a}$.

Step 4: the formula for the inverse. Let $\mathfrak{b}$ be an inverse of $\mathfrak{a}$. As $\mathfrak{ba} = R$, every $x \in \mathfrak{b}$ satisfies $x\mathfrak{a} \subseteq R$, so $\mathfrak{b} \subseteq (R : \mathfrak{a})$. Conversely, if $x\mathfrak{a} \subseteq R$, then $x \in xR = x\mathfrak{ab} \subseteq R\mathfrak{b} = \mathfrak{b}$. So $\mathfrak{b} = (R : \mathfrak{a})$, which also shows that the inverse is unique, completing the proof.

Corollary 50.2.23: Fractional Ideal Prime Decomposition

Let R be a Dedekind domain. Every fractional ideal $\mathfrak{a}$ admits a unique representation as the product

$$\mathfrak{a} = \prod_{\mathfrak{p}} \mathfrak{p}^{n_\mathfrak{p}}$$

over the nonzero primes $\mathfrak{p}$ of R, where $n_\mathfrak{p} \in \mathbb{Z}$ and $n_\mathfrak{p} = 0$ for almost all $\mathfrak{p}$. Thus, J_K is the free abelian group generated by the set of nonzero prime ideals $\mathfrak{p}$ of R.

***Proof*:**
Step 1: existence. Choose $0 \neq r \in R$ with $I = r\mathfrak{a} \subseteq R$, a nonzero ideal. In the group J_K (theorem 50.2.22), $\mathfrak{a} = (rR)^{-1}I$. Both rR and I are products of nonzero primes (theorem 50.2.15), say $rR = \prod_\mathfrak{p} \mathfrak{p}^{c_\mathfrak{p}}$ and $I = \prod_\mathfrak{p} \mathfrak{p}^{d_\mathfrak{p}}$, so $\mathfrak{a} = \prod_\mathfrak{p} \mathfrak{p}^{d_\mathfrak{p} - c_\mathfrak{p}}$.

Step 2: uniqueness. Suppose $\prod_\mathfrak{p} \mathfrak{p}^{n_\mathfrak{p}} = \prod_\mathfrak{p} \mathfrak{p}^{m_\mathfrak{p}}$, with finitely many nonzero exponents. For each $\mathfrak{p}$ put $e_\mathfrak{p} = \max(0, -n_\mathfrak{p}, -m_\mathfrak{p})$ and multiply both sides by $\prod_\mathfrak{p} \mathfrak{p}^{e_\mathfrak{p}}$. Both sides become products of nonzero primes with the exponents $n_\mathfrak{p} + e_\mathfrak{p} \geq 0$ and $m_\mathfrak{p} + e_\mathfrak{p} \geq 0$, that is, the same nonzero ideal of R factored in two ways. By the uniqueness in theorem 50.2.15, $n_\mathfrak{p} + e_\mathfrak{p} = m_\mathfrak{p} + e_\mathfrak{p}$ for

every $\mathfrak{p}$.

Step 3: freeness. The map from the free abelian group on the nonzero primes to J_K sending $(n_\mathfrak{p})_\mathfrak{p}$ to $\prod_\mathfrak{p} \mathfrak{p}^{n_\mathfrak{p}}$ is a homomorphism, as J_K is abelian. It is surjective by Step 1 and injective by Step 2, completing the proof.

The quotients of consecutive prime powers are all isomorphic to the residue field:

Lemma 50.2.24: Quotients Of Prime Powers

Let R be a Dedekind domain, $\mathfrak{p} \subseteq R$ a nonzero prime and $i \geq 0$. Then $\mathfrak{p}^i/\mathfrak{p}^{i+1} \cong R/\mathfrak{p}$ as R-modules.

***Proof*:**
If $\mathfrak{p}^i = \mathfrak{p}^{i+1}$, multiplying by the inverse of $\mathfrak{p}^i$ in the group J_K (theorem 50.2.22) gives $R = \mathfrak{p}$, which is false. So there is $a \in \mathfrak{p}^i \setminus \mathfrak{p}^{i+1}$. The ideal $\mathfrak{b} = aR + \mathfrak{p}^{i+1}$ satisfies $\mathfrak{p}^{i+1} \subseteq \mathfrak{b} \subseteq \mathfrak{p}^i$, so by definition 50.2.7 and corollary 50.2.18(3) there are ideals $\mathfrak{c}, \mathfrak{d}$ with $\mathfrak{bc} = \mathfrak{p}^{i+1}$ and $\mathfrak{p}^i\mathfrak{d} = \mathfrak{b}$. By theorem 50.2.15, the first equation forces $\mathfrak{b} = \mathfrak{p}^j$ with $j \leq i+1$, and the second forces $j \geq i$. As $a \in \mathfrak{b} \setminus \mathfrak{p}^{i+1}$, we get $j = i$, that is, $\mathfrak{p}^i = aR + \mathfrak{p}^{i+1}$. Hence the R-module homomorphism

$$\varphi\colon R \to \mathfrak{p}^i/\mathfrak{p}^{i+1} \qquad x \mapsto xa + \mathfrak{p}^{i+1}$$

is surjective. Its kernel is an ideal of R. It contains $\mathfrak{p}$, because $\mathfrak{p}a \subseteq \mathfrak{p}\mathfrak{p}^i = \mathfrak{p}^{i+1}$, and it does not contain 1, because $a \notin \mathfrak{p}^{i+1}$. The prime $\mathfrak{p}$ is maximal (definition 50.2.1), so the kernel is $\mathfrak{p}$, and theorem 12.2.10 gives $\mathfrak{p}^i/\mathfrak{p}^{i+1} \cong R/\mathfrak{p}$, completing the proof.

Definition 50.2.25: Ideal Group

Let R be a Dedekind Domain. Then J_R denotes the *ideal group* given by ideal multiplication.

We shall often write J_R interchangeably with J_K

Example 50.2.26: Ideal Group

1. The canonical example would be $J_\mathbb{Z} \cong \mathbb{Q}_+^\times$ with the bijection

   $$q\mathbb{Z} = (q) \mapsto q$$

   Note that it is important to think of the multiplicative structure of $\mathbb{Q}$, $(\mathbb{Q}, +)$ is not a free abelian group, having no two distinct elements be linearly dependent and not being cyclic.

2. More generally, let R be a Principal Ideal Domain. Then:

   $$J_R \cong K^\times/R^\times$$

   This isomorphism does not work in general, namely since not all ideals of R are principal.

A natural subgroup of J_K is formed by the principal ideal (a) where $a \in K^\times$. This subgroup can be

thought of as representing our usual notion of factorization into elements instead of ideals As some foreshadowing, notice that the principal ideal The quotient of J_K by the subgroup of principle ideals can be thought of as measuring how far away the ideal group is from being a PID:

Definition 50.2.27: Ideal Class Group

Let J_K be the class group of K. Then

$$Cl(K) = J_K/P_K$$

is called the *ideal class group*, *class group*, or *Picard group* of K.

50.2.28 Note on Nomenclature The term Picard group shall not be used in this book, as the nomenclature is more so associated within algebraic geometry. It is pointed out here that some call the class group the Picard group as the class group is a special case of the Picard group.

These naturally fit in the following exact sequence:

$$1 \to R^\times \to K^\times \to J_K \to Cl(K) \to 1$$

where $K^\times \to J_K$ is the map $a \mapsto (a)$. Hence, we may think of the class group $Cl(K)$ as a measure of the expansion that happens when we pass from numbers to ideals, where the unit group $R^\times$ measure the contraction of the same process. Thus, we may want to understand the groups $R^\times$ and $Cl(K)$ more thoroughly. In general, these can be arbitrary abelian groups[17], but for rings of integers $\mathcal{O}_K$ of number fields K, we get that the size of the class group is always finite and that $\mathcal{O}_K^\times$ is a free $\mathbb{Z}$-module along with roots of unity contained in K, as will soon be shown.

50.2.3 Class Group of Ring of Integer

Recall that ideals $\mathfrak{a} \subseteq \mathcal{O}_K$ form a sub-lattice of $\mathcal{O}_K$ in the Archimedean embedding. The following theorem is key bound on the covolume of lattice. Using theorem 50.1.66, we may rather easily show that the class group is finite. The way we shall find the size of the class group is by showing that every element in a class group will have absolute norm less than a bound (say M), and that only finitely many ideals can have norm equal to $m < M$. Then, by considering the principal ideals that have norm less than M, we shall be able to find all prime ideals that compose these principal ideals, which shall give us an estimate on the size of the group.

Lemma 50.2.29: Absolute Norm of Prime

Let $0 \neq \mathfrak{p} \subseteq \mathcal{O}_K$ be a prime ideal of $\mathcal{O}_K$ and let $\mathcal{O}_K$ be rank n. Then there is a prime number p such that $\mathfrak{p} \cap \mathbb{Z} = p\mathbb{Z}$, the quotient $\mathcal{O}_K/\mathfrak{p}$ is a finite field of characteristic p, and:

$$\mathfrak{N}(\mathfrak{p}) = p^f \qquad \text{where} \qquad f = [\mathcal{O}_K/\mathfrak{p} : \mathbb{F}_p]$$

Furthermore, $f \leq n$, with equality if and only if $\mathfrak{p} = p\mathcal{O}_K$, that is, if and only if p stays prime in $\mathcal{O}_K$.

[17] There are "enough" 1-dimensional smooth schemes to make arbitrary class groups on Dedekind domains

The number f shall be given a name in definition 50.4.1: the *inertia degree* of $\mathfrak{p}$ over p. Note that f may be strictly smaller than n: in $\mathbb{Z}[i] = \mathcal{O}_{\mathbb{Q}(i)}$, the ideal $(2+i)$ is prime with $\mathbb{Z}[i]/(2+i) \cong \mathbb{F}_5$, hence $\mathfrak{N}((2+i)) = 5$ and not $5^2 = 25$.

***Proof*:**
By proposition 50.1.62, $\mathcal{O}_K/\mathfrak{p}$ is finite, and since $\mathfrak{p}$ is prime, $\mathcal{O}_K/\mathfrak{p}$ is an integral domain. Hence, $\mathcal{O}_K/\mathfrak{p}$ is a finite field by corollary 9.1.25.

Next, consider the ring homomorphism $\mathbb{Z} \to \mathcal{O}_K/\mathfrak{p}$ given by composing the inclusion with the quotient map. Its kernel $\mathfrak{p} \cap \mathbb{Z}$ is a prime ideal of $\mathbb{Z}$, and it is nonzero, for otherwise $\mathbb{Z}$ would embed into the finite ring $\mathcal{O}_K/\mathfrak{p}$. Hence, $\mathfrak{p} \cap \mathbb{Z} = p\mathbb{Z}$ for some prime number p, and $\mathbb{F}_p = \mathbb{Z}/p\mathbb{Z}$ embeds into $\mathcal{O}_K/\mathfrak{p}$, which is therefore of characteristic p. Thus, $\mathcal{O}_K/\mathfrak{p}$ is a finite field extension of $\mathbb{F}_p$, and setting $f = [\mathcal{O}_K/\mathfrak{p} : \mathbb{F}_p]$, counting the elements of an f-dimensional $\mathbb{F}_p$-vector space gives:

$$\mathfrak{N}(\mathfrak{p}) = |\mathcal{O}_K/\mathfrak{p}| = p^f$$

For the bound on f, let $\alpha_1, \alpha_2, ..., \alpha_n$ be an integral basis for $\mathcal{O}_K$ (corollary 50.1.33). Since $\mathcal{O}_K = \mathbb{Z}\alpha_1 + \cdots + \mathbb{Z}\alpha_n$, the images $\overline{\alpha_1}, ..., \overline{\alpha_n}$ span $\mathcal{O}_K/\mathfrak{p}$ as an $\mathbb{F}_p$-vector space, hence $f \leq n$. If $\mathfrak{p} = p\mathcal{O}_K$, then $\mathcal{O}_K/\mathfrak{p} = \mathcal{O}_K/p\mathcal{O}_K \cong (\mathbb{Z}/p\mathbb{Z})^n$ by freeness, which has p^n elements, so $f = n$. Conversely, if $f = n$, then since $p \in \mathfrak{p}$ we have $p\mathcal{O}_K \subseteq \mathfrak{p}$, so $\mathcal{O}_K/\mathfrak{p}$ is a quotient of $\mathcal{O}_K/p\mathcal{O}_K$. Both have exactly p^n elements, forcing $\mathfrak{p} = p\mathcal{O}_K$, completing the proof.

Proposition 50.2.30: Absolute Norm for Ring of Integers Is Multiplicative

Let $\mathfrak{a} = \mathfrak{p}_1^{n_1} \cdots \mathfrak{p}_s^{n_s}$ be the prime factorization of the nonzero ideal $\mathfrak{a} \subseteq \mathcal{O}_K$, with the $\mathfrak{p}_j$ distinct. Then:

$$\mathfrak{N}(\mathfrak{a}) = \mathfrak{N}(\mathfrak{p}_1)^{n_1} \cdots \mathfrak{N}(\mathfrak{p}_s)^{n_s}$$

Consequently, $\mathfrak{N}(\mathfrak{ab}) = \mathfrak{N}(\mathfrak{a})\mathfrak{N}(\mathfrak{b})$ for all nonzero ideals $\mathfrak{a}, \mathfrak{b} \subseteq \mathcal{O}_K$.

***Proof*:**
The ring $\mathcal{O}_K$ is a Dedekind domain (theorem 50.2.6), so its nonzero primes are maximal (definition 50.2.1).

Step 1: $\mathfrak{p}^i/\mathfrak{p}^{i+1} \cong \mathcal{O}_K/\mathfrak{p}$. For a nonzero prime $\mathfrak{p}$ and $i \geq 0$, this is lemma 50.2.24.

Step 2: $\mathfrak{N}(\mathfrak{p}^n) = \mathfrak{N}(\mathfrak{p})^n$. We induct on n, the case $n = 0$ being $\mathfrak{N}(\mathcal{O}_K) = 1$. The group $\mathcal{O}_K/\mathfrak{p}^{n+1}$ is finite (proposition 50.1.62) and contains the subgroup $\mathfrak{p}^n/\mathfrak{p}^{n+1}$, with quotient isomorphic to $\mathcal{O}_K/\mathfrak{p}^n$ by theorem 12.2.10. By theorem 3.3.1 and Step 1,

$$\mathfrak{N}(\mathfrak{p}^{n+1}) = |\mathcal{O}_K/\mathfrak{p}^n| \cdot |\mathfrak{p}^n/\mathfrak{p}^{n+1}| = \mathfrak{N}(\mathfrak{p})^n\mathfrak{N}(\mathfrak{p}) = \mathfrak{N}(\mathfrak{p})^{n+1}$$

Step 3: the product formula. The ideals $\mathfrak{p}_j^{n_j}$ are pairwise comaximal (lemma 50.2.17). By theorem 9.6.11,

$$\mathcal{O}_K/\mathfrak{a} \cong \mathcal{O}_K/\mathfrak{p}_1^{n_1} \times \cdots \times \mathcal{O}_K/\mathfrak{p}_s^{n_s}$$

so Step 2 gives $\mathfrak{N}(\mathfrak{a}) = \mathfrak{N}(\mathfrak{p}_1^{n_1}) \cdots \mathfrak{N}(\mathfrak{p}_s^{n_s}) = \mathfrak{N}(\mathfrak{p}_1)^{n_1} \cdots \mathfrak{N}(\mathfrak{p}_s)^{n_s}$.

Step 4: multiplicativity. If $\mathfrak{a} = \prod_{\mathfrak{p}} \mathfrak{p}^{a_{\mathfrak{p}}}$ and $\mathfrak{b} = \prod_{\mathfrak{p}} \mathfrak{p}^{b_{\mathfrak{p}}}$, then $\mathfrak{ab} = \prod_{\mathfrak{p}} \mathfrak{p}^{a_{\mathfrak{p}}+b_{\mathfrak{p}}}$ is the prime factorization of $\mathfrak{ab}$, and Step 3 gives

$$\mathfrak{N}(\mathfrak{ab}) = \prod_{\mathfrak{p}} \mathfrak{N}(\mathfrak{p})^{a_{\mathfrak{p}}+b_{\mathfrak{p}}} = \mathfrak{N}(\mathfrak{a})\mathfrak{N}(\mathfrak{b})$$

completing the proof.

Recall from lemma 50.2.29 that the absolute norm of a prime is $\mathfrak{N}(\mathfrak{p}) = p^f$ where $\mathfrak{p}$ lies over p and $f = [\mathcal{O}_K/\mathfrak{p} : \mathbb{F}_p]$. In corollary 50.3.16, we shall prove the relative counterpart: if $\mathfrak{B}$ is a prime of $\mathcal{O}_L$ lying over $\mathfrak{p}$ in an extension of number fields L/K, then $\mathfrak{N}_{L/K}(\mathfrak{B}) = \mathfrak{p}^f$ where $f = [\mathcal{O}_L/\mathfrak{B} : \mathcal{O}_K/\mathfrak{p}]$.

Every fractional ideal factors uniquely as $\mathfrak{a} = \prod_{\mathfrak{p}} \mathfrak{p}^{n_{\mathfrak{p}}}$ with $n_{\mathfrak{p}} \in \mathbb{Z}$, almost all zero (corollary 50.2.23), so J_K is free abelian on the nonzero primes, and a homomorphism out of J_K may be prescribed freely on the primes:

Definition 50.2.31: Absolute Norm Of A Fractional Ideal

Let K be a number field. The *absolute norm* on fractional ideals is the group homomorphism

$$\mathfrak{N}_K : J_K \to \mathbb{R}^{\times}_{>0} \qquad \mathfrak{a} = \prod_{\mathfrak{p}} \mathfrak{p}^{n_{\mathfrak{p}}} \mapsto \prod_{\mathfrak{p}} \mathfrak{N}(\mathfrak{p})^{n_{\mathfrak{p}}}$$

On a nonzero ideal $\mathfrak{a} \subseteq \mathcal{O}_K$ every $n_{\mathfrak{p}}$ is non-negative, and by proposition 50.2.30 the value is the index $[\mathcal{O}_K : \mathfrak{a}]$ of definition 50.1.61, so the two definitions agree.

Corollary 50.2.32: Volume Form Reformulation

Let $I \subseteq K$ be a fractional ideal of a number field K. Then $\sigma(I)$ is a complete lattice in $K_{\mathbb{R}}$, and, writing $\mathrm{vol}(I)$ for $\mathrm{vol}(\sigma(I))$:

$$\mathrm{vol}(I) = \mathfrak{N}(I)\mathrm{vol}(\mathcal{O}_K)$$

***Proof*:**

Step 1: an integral multiple. By definition 50.2.9 there is $0 \neq r \in \mathcal{O}_K$ with $rI \subseteq \mathcal{O}_K$. The ideal $r\mathcal{O}_K$ is nonzero, so $d = [\mathcal{O}_K : r\mathcal{O}_K]$ is finite (proposition 50.1.62), and $d \cdot 1 \in r\mathcal{O}_K$ by theorem 3.3.1 applied to the additive group $\mathcal{O}_K/r\mathcal{O}_K$. Writing $d = ru$ with $u \in \mathcal{O}_K$, we get $dI = u(rI) \subseteq \mathcal{O}_K$, so dI is a nonzero ideal of $\mathcal{O}_K$.

Step 2: scaling the lattice. Let $\beta_1, \ldots, \beta_n$ be a $\mathbb{Z}$-basis of dI, so that $\sigma(\beta_1), \ldots, \sigma(\beta_n)$ is a basis of $K_{\mathbb{R}}$ and a $\mathbb{Z}$-basis of the complete lattice $\sigma(dI)$ (proposition 50.1.60). Multiplication by d is a group isomorphism $I \to dI$, so $\beta_1/d, \ldots, \beta_n/d$ is a $\mathbb{Z}$-basis of I, and $\sigma(\beta_i/d) = d^{-1}\sigma(\beta_i)$ because every embedding fixes $\mathbb{Q}$. So $\sigma(I) = d^{-1}\sigma(dI)$ is a complete lattice, and its basis matrix is d^{-1} times that of $\sigma(dI)$. Scaling each of the n rows by d^{-1} scales the determinant by d^{-n} (proposition 13.4.6), so definition 50.1.59 gives

$$\mathrm{vol}(dI) = d^n \mathrm{vol}(I)$$

Step 3: comparing norms. As $dI = (d\mathcal{O}_K)I$ in J_K and $\mathfrak{N}$ is a homomorphism on J_K (definition 50.2.31), $\mathfrak{N}(dI) = \mathfrak{N}(d\mathcal{O}_K)\mathfrak{N}(I)$. Here $\mathfrak{N}(d\mathcal{O}_K) = [\mathcal{O}_K : d\mathcal{O}_K] = d^n$, since $\mathcal{O}_K/d\mathcal{O}_K \cong (\mathbb{Z}/d\mathbb{Z})^n$ for an integral basis (corollary 50.1.33). Applying lemma 50.1.65 to the nonzero ideal dI, on which the two definitions of $\mathfrak{N}$ agree, and using Step 2,

$$d^n \mathrm{vol}(I) = \mathrm{vol}(dI) = \mathfrak{N}(dI)\mathrm{vol}(\mathcal{O}_K) = d^n \mathfrak{N}(I)\mathrm{vol}(\mathcal{O}_K)$$

Dividing by d^n gives $\mathrm{vol}(I) = \mathfrak{N}(I)\mathrm{vol}(\mathcal{O}_K)$, completing the proof.

Theorem 50.2.33: Class Number

Let K be a number field and let $Cl(K) = J_K/P_K$ be the class group of K. Then $Cl(K)$ is finite.

***Proof*:**

Step 1: finitely many ideals of bounded norm. Fix $M > 0$. A nonzero prime $\mathfrak{p}$ satisfies $\mathfrak{p} \cap \mathbb{Z} = p\mathbb{Z}$ and $\mathfrak{N}(\mathfrak{p}) = p^f \geq p$ for a prime number p (lemma 50.2.29). As $p\mathcal{O}_K \subseteq \mathfrak{p}$, the prime $\mathfrak{p}$ divides $p\mathcal{O}_K$ (definition 50.2.7), so $p\mathcal{O}_K = \mathfrak{p}\mathfrak{c}$ for an ideal $\mathfrak{c}$ (corollary 50.2.18(3)), and by theorem 50.2.15 the prime $\mathfrak{p}$ is one of the finitely many primes in the factorization of $p\mathcal{O}_K$. Every prime with $\mathfrak{N}(\mathfrak{p}) \leq M$ lies over one of the finitely many primes $p \leq M$, so there are finitely many such $\mathfrak{p}$. A nonzero ideal $\mathfrak{a} = \mathfrak{p}_1^{n_1} \cdots \mathfrak{p}_s^{n_s}$ has $\mathfrak{N}(\mathfrak{a}) = \mathfrak{N}(\mathfrak{p}_1)^{n_1} \cdots \mathfrak{N}(\mathfrak{p}_s)^{n_s}$ (proposition 50.2.30) with every $\mathfrak{N}(\mathfrak{p}_i) \geq 2$. So if $\mathfrak{N}(\mathfrak{a}) \leq M$, then each $\mathfrak{N}(\mathfrak{p}_i) \leq M$ and each $n_i \leq \log_2 M$, and only finitely many nonzero ideals have $\mathfrak{N}(\mathfrak{a}) \leq M$.

Step 2: a small ideal in each class. Let λ be as in theorem 50.1.66 and let $[\mathfrak{b}] \in Cl(K)$. By theorem 50.2.22, $\mathfrak{b}$ has an inverse $\mathfrak{b}^{-1}$, and by corollary 50.2.12 there are $0 \neq r \in \mathcal{O}_K$ and an ideal $I \subseteq \mathcal{O}_K$ with $\mathfrak{b}^{-1} = r^{-1}I$. So $I = (r)\mathfrak{b}^{-1}$ is a nonzero integral ideal with $[I] = [\mathfrak{b}]^{-1}$. By theorem 50.1.66 there is $0 \neq \alpha \in I$ with $\left|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)\right| \leq \lambda\mathfrak{N}(I)$. Since $(\alpha) \subseteq I$, corollary 50.2.18(3) gives an integral ideal $\mathfrak{a}$ with $I\mathfrak{a} = (\alpha)$, so $[\mathfrak{a}] = [I]^{-1} = [\mathfrak{b}]$. By proposition 50.2.30 and lemma 50.1.63,

$$\mathfrak{N}(I)\mathfrak{N}(\mathfrak{a}) = \mathfrak{N}((\alpha)) = \left|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)\right| \leq \lambda\mathfrak{N}(I)$$

and dividing by $\mathfrak{N}(I) > 0$ gives $\mathfrak{N}(\mathfrak{a}) \leq \lambda$.

Step 3: finiteness. Choosing such an ideal $\mathfrak{a}$ in each class defines an injective map from $Cl(K)$ to the set of nonzero ideals of absolute norm at most λ, which is finite by Step 1. So $Cl(K)$ is finite, completing the proof.

Corollary 50.2.34: Minkowski's Bound For Ideal Classes

Let K be a number field with Minkowski bound M_K (theorem 50.1.69). Then every ideal class $[\mathfrak{b}] \in Cl(K)$ contains an integral ideal $\mathfrak{a}$ with $\mathfrak{N}(\mathfrak{a}) \leq M_K$.

***Proof*:**

By theorem 50.2.22, the fractional ideal $\mathfrak{b}$ has an inverse $\mathfrak{b}^{-1}$, and by corollary 50.2.12 there are $0 \neq r \in \mathcal{O}_K$ and an ideal $I \subseteq \mathcal{O}_K$ with $\mathfrak{b}^{-1} = r^{-1}I$. So $I = (r)\mathfrak{b}^{-1}$ is a nonzero integral ideal

with $[I] = [\mathfrak{b}]^{-1}$ in $Cl(K)$. By theorem 50.1.69 there is $0 \neq \alpha \in I$ with $\left|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)\right| \leq M_K \mathfrak{N}(I)$. Since $(\alpha) \subseteq I$, that is $I \big| (\alpha)$, corollary 50.2.18(3) gives an integral ideal $\mathfrak{a}$ with $I\mathfrak{a} = (\alpha)$. In $Cl(K)$ this reads $[I][\mathfrak{a}] = 1$, so $[\mathfrak{a}] = [I]^{-1} = [\mathfrak{b}]$. By proposition 50.2.30 and lemma 50.1.63,

$$\mathfrak{N}(I)\mathfrak{N}(\mathfrak{a}) = \mathfrak{N}((\alpha)) = \left|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)\right| \leq M_K \mathfrak{N}(I)$$

and dividing by $\mathfrak{N}(I) > 0$ gives $\mathfrak{N}(\mathfrak{a}) \leq M_K$, as claimed.

Definition 50.2.35: The Class Number h_K

Let $Cl(K)/ = J_K/P_k$ be the class group of K. Then $h_K = [J_K : P_K]$ is called the *class number* of $Cl(K)$ or K.

A consequence of there being a finite class number is that for every ideal $I \subseteq \mathcal{O}_K$, there exists a minimal number n such that $I^n = (\alpha)$ for some $\alpha \in \mathcal{O}_K$. There is also a minimal number n' such that for *any* ideal of $\mathcal{O}_K$, the ideal to the power of n' is principal. This may encourage thoughts of converting the problem on ideals into one on principal ideals, given there is a way of going back to the original ideals. We shall see that this shall sometimes be the case.

Example 50.2.36: Class Groups

1. Naturally, $|Cl(\mathbb{Q})| = 1$ since $\mathbb{Z}$ is a PID
2. Similarly, $|Cl(\mathbb{Q}(i)| = |Cl(\mathbb{Q}(\sqrt{-3})| = 1$ since $\mathbb{Z}[i]$ and $\mathbb{Z}\left[\frac{1+\sqrt{-3}}{2}\right]$ are PID.
3. Every DVR has ideals of the form (π^n) for appropriate uniformizer π. Thus, the ideal group is isomorphic to $\mathbb{Z}$, and the class group is trivial.
4. Consider $Cl(\mathbb{Q}(\sqrt{-5})$. Since $\mathbb{Z}[\sqrt{-5}]$ is not a Unique Factorization Domain (hence Principal Ideal Domain), we will get a non-trivial class group. Let $K = \mathbb{Q}(\sqrt{-5})$. Choose an integral basis
$$\mathcal{O}_K = \langle 1, \sqrt{-5} \rangle_{\mathbb{Z}}$$
so that $D_k = -20$. Hence, the Minkowski bound gives us:
$$M_k = \sqrt{20}\frac{2}{2^2}\frac{4}{\pi} < 4$$
In fact, we have < 3, but we shall purposefully miss-guess the bound to show how to determine when two ideals belong in the same class group. Consider the ideal $(2), (3)$. Assume that $\mathfrak{p}_2 \big| (2)$. Then we know $\mathfrak{N}(\mathfrak{p}_2) \big| \mathfrak{N}((2)) = 4$. To find $\mathfrak{p}_2 \subseteq \mathcal{O}_K$ consider the map $\varphi : \mathcal{O}_K \to \mathcal{O}_K/(2)$. Since $\mathcal{O}_K/(2)$ is finite the pre-image of a prime ideal of a surjective map is prime, we may find prime ideals of $\mathcal{O}_K/(2)$. By the 4th isomorphism theorem, if $\overline{I} \subseteq \mathcal{O}_K/(2)$ if and only if $(2) \subseteq I$, that is $I \big| (2)$, and hence any prime ideal corresponding to prime ideal of $\mathcal{O}_K/(2)$ divides (2). Thus we look for $\varphi^{-1}(P) = \mathfrak{p}_2$. To find such a $\mathfrak{p}_2$, think of $\mathcal{O}_K$ as $\mathcal{O}_K \cong \mathbb{Z}[x]/(x^2+5)$[a] so that we can take:
$$\mathcal{O}_K/(2) \cong \mathbb{Z}[x]/(x^2+5, 2) \cong \mathbb{F}_2[x]/(x^2-1) = \mathbb{F}_2[x]/((x+1)^2)$$
Recall that the prime ideals of a ring are in corresponding with the prime ideals of the ring quotiented by the nilradical (see section 32.2). But then we immediately see that the only

prime ideal in $\mathcal{O}_K/(2)$ is $(1+x)$. Hence

$$\mathfrak{p}_2 = (1+\sqrt{-5}, 2)$$

Every prime ideal dividing (2) contains 2, so by the computation of $\mathcal{O}_K/(2)$ above it is $\mathfrak{p}_2$, and $\mathfrak{p}_2 \neq (2)$ because $1+\sqrt{-5} \notin (2)$. Hence $(2) = \mathfrak{p}_2^e$ for some $e \geq 2$, and indeed:

$$\mathfrak{p}_2^2 = (4, 2+2\sqrt{-5}, -4+2\sqrt{-5}) = (2)$$

Is $\mathfrak{p}_2$ principal? If it was, then $\mathfrak{p}_2 = (a+b\sqrt{-5})$. Then:

$$2 = \mathfrak{N}(\mathfrak{p}_2) = |\mathrm{Nm}_{K/\mathbb{Q}}(a+b\sqrt{-5})| = a^2 + 5b^2$$

but it's evident this is not possible, hence it is not principal! Similarly with (3), we get:

$$\mathcal{O}_K/(3) \cong \mathbb{Z}[x]/(x^2+5, 3) = \mathbb{F}_3[x]/(x^2-1) \cong \mathbb{F}_3 \times \mathbb{F}_3$$

From this, we can see that $3 = \mathfrak{p}_3\mathfrak{p}_3'$ where

$$\mathfrak{p}_3 = (3, 1+\sqrt{-5}) \qquad \mathfrak{p}_3' = (3, 1-\sqrt{-5})$$

Finally, notice that $[\mathfrak{p}_2] = [\mathfrak{p}_3]$. To see this, notice their product is in fact principal:

$$\mathfrak{p}_2\mathfrak{p}_3 = (2, 1+\sqrt{-5})(3, 1+\sqrt{-5}) = (6, 1+\sqrt{-5}, (1+\sqrt{-5})^2) = (1+\sqrt{-5})$$

Hence, $\mathfrak{p}_3 = (1+\sqrt{-5})^{-1}\mathfrak{p}_2$. Evidently, $\mathfrak{p}_3, \mathfrak{p}_3'$ are in the same class. Since there are only two elements, it must be that $Cl(K) \cong \mathbb{Z}/2\mathbb{Z}$.

5. Let $K = \mathbb{Q}(\sqrt{-23})$. Choose $\mathcal{O}_K = \langle 1, \frac{1+\sqrt{-23}}{2} \rangle_{\mathbb{Z}}$ so that it's discriminant is $d_k = -23$ and the Minkowski bound is $M_K = \sqrt{23}\frac{4}{\pi}\frac{1}{2} < 4$. Hence, we again check the prime ideals (2) and (3), noting that the minimal polynomial of the generator is $x^2 - x + 6$:

$$\mathcal{O}_K/(2) \cong \mathbb{F}_2[x]/(t^2 - t)$$

Thus, if $t = \frac{1+\sqrt{-23}}{2}$:

$$(2) = (2, t-1)(2, t)$$

and similarly

$$(3) = (3, t-1)(3, t)$$

Certainly, each prime multiple of (2) and (3) are in the same equivalence class. Is $[(2,t)] = [(3, t-1)]$? Choosing good representatives and multiplying, we get

$$(3,t)(2,t) = (6,t) = (t)$$

hence, we again get that $Cl(K) = \mathbb{Z}/2\mathbb{Z}$.

6. Let $K = \mathbb{Q}(\sqrt{15})$ and $\mathcal{O}_K = \langle 1, \sqrt{15} \rangle_{\mathbb{Z}}$. Then doing the same procedure, we get:

$$(3, \sqrt{15})^2 = (3)$$

How do we know that $(3, \sqrt{15})$ is principal or not? We can see that $a^2 - 15b^2 = 3$ has no solutions using modular arithmetic's, but it will not always be feasible to use this method, so we introduce another. Let's say $(3, \sqrt{15}) = (\alpha)$. Then

$$(\alpha^2) = (3)$$

meaning they are associate, hence $\alpha^2 = 3u$ for $u \in \mathcal{O}_K^\times$. Does there exist such a unit? In section 50.2.4, we shall find this structure. For now, it can be taken for granted that $\mathcal{O}_K^\times = \pm\langle 4+\sqrt{15}\rangle$ (notice the norm of all such numbers is 1). Then from this we see that no such unit exist, hence $(3, \sqrt{15})$ is not principal.

Notice that all of these examples are for quadratic extensions. It is much more difficult to find prime-factorization for non-quadratic extension since the ring of integers is not easy to find. In the next section, we shall see how we may get some information on the factorization of primes when $\mathcal{O}_K$ is not available

[a]Note how this relied on knowing the structure of $\mathcal{O}_K$! See comment at the end of this example

In general, we have $h_K > 1$. If $h_K = 1$ then we can think of the prime factorization of ideals being the same as the prime factorization of elements as is already well-understood. If $K = \mathbb{Q}(\sqrt{d})$ where d is square-free and negative, then the quadradic extensions in which the class number is 1 is

$$-1, -2, -3, -7, -11, -19, -43, -67, -163$$

For real quadratic extensions, there are a lot more, for example:

$$2, 3, 5, 6, 7, 11, 13, 14, 17, 19, 22, 23, 29, 31, 33, \cdots$$

it is unknown where there are infinitely many real quadratic fields of class number 1, or even if there are infinitely many algebraic number fields (of any degree) with class number 1. In general, it is in fact very difficult to determine some structure in the class group given some class of number fields, with an important notable exception cyclotomic extensions which due to the work of Kenkichi Iwasawa we know behave in a regular way.

The importance of studying cyclotomic extensions links back to Fermat's last theorem which the reader surely recalls states that the equation $x^p + y^p = z^p$ has no nonzero integer solutions for $p \geq 3$. For $p = 2$, we take the cyclotomic extension $\mathbb{Q}(\zeta_4) = \mathbb{Q}(i)$ to get

$$x^2 + y^2 = (x + iy)(x - iy)$$

and then we get the Fermat's twin prime theorem that fully solved the problem in this case. If p is prime, then considering the equation $y^p = z^p - x^p$ over $\mathbb{Q}(\zeta_p)$, we may factor this in $\mathbb{Z}[\zeta_p]$ as

$$\begin{aligned} y^p &= x^p - z^p \\ &= z^p \left(\left(\frac{x}{z}\right)^p - 1 \right) \\ &= z^p \prod_{k=0}^{p-1} \left(\frac{x}{z} - \omega_k \right) \\ &= \prod_{k=0}^{p-1} z \left(\frac{x}{z} - \omega_k \right) \\ &= \prod_{k=0}^{p-1} (x - \omega_k z) \end{aligned}$$

where $\omega_k = \zeta_p^k$. Thus, if we assume an existence of a solution, we obtain two multiplicative decompositions of the same number in $\mathbb{Z}[\zeta_p]$. Using this, we can show it contradicts unique factorization

provided that $\mathbb{Z}[\zeta_p]$ is a unique factorization domain. It was due to some mathematician erroneously assuming unique factorization (equivalently for us, that the class number is always 1) that lead to many fake proofs of Fermat's last theorem[18]. Kummer fixed this by introducing the notion of ideal primes, and translated the statement into one where we must show that $p \nmid h_p$ instead of assuming $h_p = 1$. If this is the case, such a prime is called *regular*, and *irregular* otherwise. Unfortunately, not all primes are regular. Of the first 25 primes less than 100, the primes 37, 59, and 67 are irregular. As of writing this book, it is unknown whether there are infinitely many regular primes.

The regular and irregular prime are going to play important roles in our coming theory, but they do not play much of a role in the eventual proof of Fermat's Last theorem. Due to the work of Gerhard Frey, there was a reformulation of Fermat's last theorem into a statement about elliptic curves. This lead to a new development of mathematics which is beyond the scope of this book, but the interested reader may feel free to search up the *Taniyama-Shimura-Weil Conjecture* to see how Fermat's Last Theorem got translated into a problem of elliptic curves.

We end this section with showing a certain Diophantine equation has no integer solution as it combines nicely all the machinery we have done, and some generalizations that is motivation for class field theory. Starting with the Diophantine equation:

Theorem 50.2.37: No Solution To Diophantine Equation

The equation

$$y^2 = x^3 - 5$$

has no integer solutions.

***Proof*:**

Suppose the pair (x, y) is an integer solution. If x were even, then $4 \mid x^3$ and $y^2 = x^3 - 5 \equiv 3 \bmod 4$, which is impossible because every square is congruent to 0 or 1 modulo 4. So x is odd. Next, x and y are coprime: a prime p dividing both would give $p^2 \mid y^2$ and $p^3 \mid x^3$, hence $p^2 \mid x^3 - y^2 = 5$, which is impossible.

Let $K = \mathbb{Q}(\sqrt{-5})$. Since $-5 \not\equiv 1 \bmod 4$, example 50.1.17 gives $\mathcal{O}_K = \mathbb{Z}[\sqrt{-5}]$, which is a Dedekind domain by theorem 50.2.6. In $\mathcal{O}_K$ the equation factors as $(y + \sqrt{-5})(y - \sqrt{-5}) = y^2 + 5 = x^3$, so as ideals

$$(y + \sqrt{-5})(y - \sqrt{-5}) = (x)^3$$

and the two factors on the left are coprime. Suppose a prime ideal $\mathfrak{p}$ contains both. Then $\mathfrak{p}$ contains x^3, hence x, and it contains their difference $2\sqrt{-5}$, hence $2\sqrt{-5} \cdot \sqrt{-5} = -10$. Let p be the prime with $\mathfrak{p} \cap \mathbb{Z} = p\mathbb{Z}$. Then p divides both x and 10, and x is odd, so $p = 5$. Now $(\sqrt{-5})^2 = -5 \in \mathfrak{p}$, and $\mathfrak{p}$ is prime, so $\sqrt{-5} \in \mathfrak{p}$ and $y = (y + \sqrt{-5}) - \sqrt{-5} \in \mathfrak{p} \cap \mathbb{Z} = 5\mathbb{Z}$. Then 5 divides both x and y, contradicting their coprimality.

By theorem 50.2.15, every prime ideal occurs in $(x)^3$ with exponent divisible by 3. The two factors are coprime, so each prime ideal of $(x)^3$ occurs in exactly one of them, with its full exponent. Hence $(y + \sqrt{-5}) = \mathfrak{a}^3$ for an ideal $\mathfrak{a}$ of $\mathcal{O}_K$. The class group of K has order 2 (example 50.2.36, the case $\mathbb{Q}(\sqrt{-5})$), so $[\mathfrak{a}]^2 = 1$, while $[\mathfrak{a}]^3 = [(y + \sqrt{-5})] = 1$. Hence $[\mathfrak{a}] = [\mathfrak{a}]^3[\mathfrak{a}]^{-2} = 1$, and $\mathfrak{a} = (a + b\sqrt{-5})$ for some $a, b \in \mathbb{Z}$. Then $y + \sqrt{-5} = u(a + b\sqrt{-5})^3$ for a unit u of $\mathcal{O}_K$. A unit $c + d\sqrt{-5}$ has norm $c^2 + 5d^2 = \pm 1$, which forces $d = 0$ and $c = \pm 1$. So $u = \pm 1 = (\pm 1)^3$, and

[18] It is speculated that this is the proof Fermat was referring to as being too long for the margins of his book

replacing a, b by $-a, -b$ if $u = -1$ gives

$$y + \sqrt{-5} = (a + b\sqrt{-5})^3 = (a^3 - 15ab^2) + (3a^2b - 5b^3)\sqrt{-5}$$

and comparing the coefficients of $\sqrt{-5}$ gives $1 = b(3a^2 - 5b^2)$, so $b = \pm 1$. If $b = 1$, then $3a^2 - 5 = 1$ and $a^2 = 2$. If $b = -1$, then $3a^2 - 5 = -1$ and $3a^2 = 4$. Neither has an integer solution, so no integer solution (x, y) exists.

Note that a few things lined up well here:

- There were only two units, if there are more then the considerations are more complicated.
- The class group happened to let us deduce the ideal is principal. If the ideal was not principal there would be more to consider.
- The equation was easily factorizable in the extension (ex. $y^2 = x^5 + x + 1$ is a good deal more difficult)
- The factors are coprime.

Exercise 50.2.1

1. Let $A, B \subseteq R$ with $B \subseteq A$ and $A \neq R$. Show there exists a $\gamma \in K$ such that $\gamma B \subseteq R$, but $\gamma B \not\subseteq A$
2. Show that $IJ = (I + J)(I \cap J) = \gcd(I, J)\text{lcm}(I, J)$
3. Let $\alpha \in \mathcal{O}_K \setminus \{0\}$. Show that there exists a $\beta \in \mathcal{O}_K$ st $\alpha\beta \in \mathbb{Z} \setminus \{0\}$
4. Let $K = \mathbb{Q}(\sqrt{-3})$. Show that $\mathcal{O}_K \neq \mathbb{Z}[\sqrt{-3}]$. Show that
5. Show that $3 = x^2 + 5y^2$ has no integer solutions. Note that 3 splits in $\mathbb{Z}[\sqrt{-3}]$ showing that if the ringer of integers is not UFD then it is more complicated to use factorizations.
6. exercise for quotient ideals

   a) here


50.2.4 Dirichlet's Unit Theorem

(Current intuition when it comes to solving equations: we are working with ideals, but equations use elements. We must be concious of the units at play to reduce back to elements)

As we saw in example 50.2.36, it is important to know the unit group of $\mathcal{O}_K$ to find elements in the class group. We start this section by showing that we may embed $\mathcal{O}_K^\times$ to form a lattice, and then use this to find the structure of $\mathcal{O}_K$.

The group $\mathcal{O}_K^\times$ may have some torsion elements, namely all roots of unity that lie in K. This collection is labeled as $\mu(K)$. This group will in fact be determined by the number of embeddings

into Minkowski space. On a high-level, the structure of this group is within this diagram:



where we shall write $K_\mathbb{R}^\times = (\mathbb{R}^{r_1} \oplus \mathbb{C}^{r_2})^\times$. In particular, the top row of the above commutative diagram can be replaced by:

$$\begin{aligned} \mathcal{O}_K^\times &= \left\{ r \in \mathcal{O}_K \;\middle|\; N_{K/\mathbb{Q}(n)=\pm 1} \right\} \\ S &= \left\{ y \in K_\mathbb{R}^\times \;\middle|\; N(y) = \pm 1 \right\} && \text{norm-one surface} \\ H &= \left\{ x \in \left[\prod_\tau \mathbb{R} \right]^+ \;\middle|\; \operatorname{tr}(x) = 0 \right\} && \text{trace-zero hyperplane} \end{aligned}$$

Then we get the homomorphism:

$$\mathcal{O}_K^\times \xrightarrow{\sigma} S \xrightarrow{\log} H$$

where $\sigma^\times = \log \circ \sigma$.

Proposition 50.2.38: Roots Of Unity In Group Of Units

Let $\sigma^\times(x) = (\log|\sigma_1(x)|, \ldots, \log|\sigma_{r_1}(x)|, \log(|\tau_1(x)|^2), \ldots, \log(|\tau_{r_2}(x)|^2)) \in \mathbb{R}^{r_1+r_2}$ for $x \in K^\times$, let $H = \{x \in \mathbb{R}^{r_1+r_2} \mid x_1 + \cdots + x_{r_1+r_2} = 0\}$ be the trace-zero hyperplane, and let $\Gamma_K^\times = \sigma^\times(\mathcal{O}_K^\times)$. Then $\Gamma_K^\times \subseteq H$, the group $\mu(K)$ of roots of unity in K is finite, and the sequence

$$1 \to \mu(K) \to \mathcal{O}_K^\times \xrightarrow{\sigma^\times} \Gamma_K^\times \to 0$$

is exact.

***Proof*:**

Step 1: the hyperplane. The map $\sigma^\times$ is a homomorphism from $K^\times$ to the additive group $\mathbb{R}^{r_1+r_2}$, as each embedding is multiplicative and log turns products into sums. For $u \in \mathcal{O}_K^\times$, $\operatorname{Nm}_{K/\mathbb{Q}}(u) = \pm 1$ (proposition 50.1.18). By corollary 50.1.13, and as $|\overline{\tau_j}(u)| = |\tau_j(u)|$, $|\operatorname{Nm}_{K/\mathbb{Q}}(u)| = \prod_i |\sigma_i(u)| \prod_j |\tau_j(u)|^2$, so the coordinates of $\sigma^\times(u)$ sum to $\log|\operatorname{Nm}_{K/\mathbb{Q}}(u)| = 0$, and $\Gamma_K^\times \subseteq H$.

Step 2: the kernel. A root of unity ζ with $\zeta^m = 1$ is a root of $x^m - 1$, so $\zeta \in \mathcal{O}_K$, and $\zeta^{-1} = \zeta^{m-1} \in \mathcal{O}_K$, so $\mu(K) \subseteq \mathcal{O}_K^\times$. Every embedding φ of K into $\mathbb{C}$ has $|\varphi(\zeta)|^m = 1$, so $|\varphi(\zeta)| = 1$ and $\sigma^\times(\zeta) = 0$. Conversely, if $r \in \mathcal{O}_K^\times$ has $\sigma^\times(r) = 0$, then $|\varphi(r)| = 1$ for every embedding φ, so $\sigma(r)$ lies in the bounded subset of $K_\mathbb{R}$ where every coordinate has absolute value at most 1. That set contains only finitely many points of the lattice $\sigma(\mathcal{O}_K)$ (proposition 50.1.57 and lemma 50.1.56), and σ is injective, so the kernel of $\sigma^\times$ is a finite group, of order m say. By theorem 3.3.1, $r^m = 1$ for every r in the kernel, so the kernel is $\mu(K)$, which is therefore finite.

The map onto $\Gamma_K^\times$ is surjective by definition, completing the proof.

We now build towards the structure of $\Gamma_K^\times$. Under the right adjustments $\mathcal{O}_K^\times$ can be embedded in a similar way to $\mathcal{O}_K$. Take $\sigma(\mathcal{O}_K^\times) \subseteq \mathbb{R}^{r_1} \oplus \mathbb{C}^{r_2}$. the way a mesh is formed is by taking the logarithm, for $\log(ab) = \log(a) + \log(b)$

$$\sigma^\times : K^\times \to \mathbb{R}^{r_1} \oplus \mathbb{R}^{r_2} \qquad \sigma^\times = \log \circ \sigma$$

Proposition 50.2.39: Multiplicative Group Forms Lattice

Let $\sigma^\times$ and the trace-zero hyperplane H be as in proposition 50.2.38. Then $\sigma^\times(\mathcal{O}_K^\times) \subseteq H$, and $\sigma^\times(\mathcal{O}_K^\times)$ is discrete: some open ball around 0 meets it only in 0.

***Proof*:**
Step 1: the hyperplane. This is proposition 50.2.38.

Step 2: discreteness. Let B be the open ball of radius 1 around 0 in $\mathbb{R}^{r_1+r_2}$. If $\sigma^\times(u) \in B$, every coordinate has absolute value less than 1, so $|\sigma_i(u)| < e$ and $|\tau_j(u)| < e$ for all i, j. Then $\sigma(u)$ lies in the bounded subset of $K_\mathbb{R}$ where every coordinate has absolute value less than e, which contains only finitely many points of the lattice $\sigma(\mathcal{O}_K)$ (proposition 50.1.57 and lemma 50.1.56). As σ is injective, only finitely many $u \in \mathcal{O}_K^\times$ have $\sigma^\times(u) \in B$. If some of these images are nonzero, let r be the least norm among them, and otherwise put $r = 1$. The open ball of radius r around 0 meets $\sigma^\times(\mathcal{O}_K^\times)$ only in 0, completing the proof.

Theorem 50.2.40: Dirichlet Unit Theorem

The group of units $\mathcal{O}_K^\times$ is the direct product of the finite cyclic group $\mu(K)$ and a free abelian group of rank $r_1 + r_2 - 1$. The free-generators of $\mathcal{O}_K^\times$ are called the *fundamental units* of $\mathcal{O}_K^\times$:

$$\mathcal{O}_K^\times \cong_\mathbb{Z} \mathbb{Z}^{r_1+r_2-1} \oplus \mu(K)$$

We may also characterize $\mathcal{O}_K^\times$ by the following short exact sequence:

$$1 \to \mu(K) \to \mathcal{O}_K^\times \to \Gamma_K^\times \to 0$$

where since the right term is a free $\mathbb{Z}$-module, the sequence splits giving us $\mathcal{O}_K^\times \cong \mu(K) \oplus \Gamma_K^\times$.

***Proof*:**
Write $r = r_1 + r_2$ and record the coordinates of $\sigma^\times(x)$, for $x \in K^\times$, as

$$\ell_i(x) = \log|\sigma_i(x)| \quad (1 \le i \le r_1) \qquad \ell_{r_1+j}(x) = \log\left(|\tau_j(x)|^2\right) \quad (1 \le j \le r_2)$$

In these coordinates the trace on $[\prod_\tau \mathbb{R}]^+$ is $\sum_{i=1}^r \ell_i$, and corollary 50.1.13 gives

$$\sum_{i=1}^r \ell_i(x) = \log\left|\mathrm{Nm}_{K/\mathbb{Q}}(x)\right|$$

so H is the sum-zero hyperplane in $\mathbb{R}^r$ and $\dim_\mathbb{R} H = r - 1$.

By proposition 50.2.38 the sequence $1 \to \mu(K) \to \mathcal{O}_K^\times \to \Gamma_K^\times \to 0$ is exact and $\mu(K)$ is finite. A finite subgroup of the multiplicative group of a field is cyclic (theorem 11.3.14), so $\mu(K)$ is finite cyclic. By proposition 50.2.39 the group $\Gamma_K^\times$ is discrete in H. Let $W \subseteq H$ be its $\mathbb{R}$-span. A discrete subgroup spanning W is a lattice in W by definition 50.1.55 and lemma 50.1.56, hence free of rank $\dim_{\mathbb{R}} W$. The right-hand term of the sequence is then free, so the sequence splits and

$$\mathcal{O}_K^\times \cong \mu(K) \oplus \mathbb{Z}^{\dim_{\mathbb{R}} W}$$

What remains is $\dim_{\mathbb{R}} W = r - 1$, and since $W \subseteq H$ it is enough to produce $r - 1$ elements of $\Gamma_K^\times$ that are linearly independent over $\mathbb{R}$.

A box of bounded norm. For positive reals $c_1, \dots, c_r$ put

$$X(c) = \left\{ x \in K_{\mathbb{R}} \;\middle|\; |x_i| \le c_i \ (1 \le i \le r_1),\ |z_j|^2 \le c_{r_1+j} \ (1 \le j \le r_2) \right\}$$

where $x_1, \dots, x_{r_1}$ and $z_1, \dots, z_{r_2}$ are the real and complex coordinates of $K_{\mathbb{R}}$. This set is convex and centrally symmetric, and its volume equals $\kappa\, c_1 \cdots c_r$ for a constant $\kappa > 0$ depending only on r_1 and r_2, because the real coordinates range over intervals of length $2c_i$ and the complex coordinates over discs of radius $\sqrt{c_{r_1+j}}$. By proposition 50.1.60 applied to the ideal $\mathcal{O}_K$, the set $\Gamma = \sigma(\mathcal{O}_K)$ is a complete lattice in $K_{\mathbb{R}}$. Fix once and for all a real number

$$M > \frac{2^n \operatorname{vol}(\Gamma)}{\kappa}$$

which depends only on K. If $c_1 \cdots c_r = M$ then $\operatorname{vol}(X(c)) > 2^n \operatorname{vol}(\Gamma)$, so lemma 50.1.68 produces a nonzero $\beta \in \mathcal{O}_K$ with $\sigma(\beta) \in X(c)$. For such a β,

$$\left|\operatorname{Nm}_{K/\mathbb{Q}}(\beta)\right| = \prod_{i=1}^{r_1} |\sigma_i(\beta)| \prod_{j=1}^{r_2} |\tau_j(\beta)|^2 \le c_1 \cdots c_r = M \qquad \ell_i(\beta) \le \log c_i \text{ for every } i$$

A unit negative away from one coordinate. Fix k with $1 \le k \le r$. Set $\beta_1 = 1$, and given a nonzero $\beta_p \in \mathcal{O}_K$ apply the previous paragraph to

$$c_i = \tfrac{1}{2} e^{\ell_i(\beta_p)} \ (i \ne k) \qquad c_k = M \Big/ \prod_{i \ne k} c_i$$

to obtain a nonzero $\beta_{p+1} \in \mathcal{O}_K$ with $\ell_i(\beta_{p+1}) \le \ell_i(\beta_p) - \log 2$ for all $i \ne k$ and $\left|\operatorname{Nm}_{K/\mathbb{Q}}(\beta_{p+1})\right| \le M$. Each $\operatorname{Nm}_{K/\mathbb{Q}}(\beta_p)$ is a nonzero integer by corollary 50.1.14, so for $p \ge 2$ these norms take only finitely many values, and for each value proposition 50.1.67 leaves only finitely many elements of $\mathcal{O}_K$ up to multiplication by units. Hence $\beta_q = \beta_p u$ for some $p < q$ and some $u \in \mathcal{O}_K^\times$, and then

$$\ell_i(u) = \ell_i(\beta_q) - \ell_i(\beta_p) \le -(q-p)\log 2 < 0 \qquad (i \ne k)$$

Rank. Choose units $u_1, \dots, u_r$ so that $\ell_i(u_k) < 0$ for all $i \ne k$. By proposition 50.1.18 the norm $\operatorname{Nm}_{K/\mathbb{Q}}(u_k)$ is ± 1, so $\sum_i \ell_i(u_k) = 0$ and therefore $\ell_k(u_k) = -\sum_{i \ne k} \ell_i(u_k) > 0$. Let $A = (a_{ki})$ be the $r \times r$ real matrix with $a_{ki} = \ell_i(u_k)$, so that $a_{kk} > 0$, $a_{ki} < 0$ for $i \ne k$, and every row sums to 0. The row sums give $A(1, \dots, 1)^t = 0$, so $\operatorname{rank} A \le r - 1$. For the reverse bound, suppose the first $r - 1$ columns $v_1, \dots, v_{r-1}$ satisfy $t_1 v_1 + \cdots + t_{r-1} v_{r-1} = 0$ with real t_j not all zero. Pick $k \le r - 1$ with $|t_k|$ maximal, then divide by t_k and change the overall sign if needed,

so that $t_k = 1$ and $|t_j| \leq 1$ for every j. Since $a_{kj} < 0$ and $t_j \leq 1$ for $j \neq k$, each term satisfies $t_j a_{kj} \geq a_{kj}$, and row k gives

$$0 = \sum_{j=1}^{r-1} t_j a_{kj} \geq \sum_{j=1}^{r-1} a_{kj} = -a_{kr} > 0$$

using $a_{kr} < 0$, which holds because $k \neq r$. This contradiction makes $v_1, \ldots, v_{r-1}$ linearly independent, so $\operatorname{rank} A = r - 1$.

The rows of A are the vectors $\sigma^\times(u_1), \ldots, \sigma^\times(u_r)$ of $\Gamma_K^\times$, so $\Gamma_K^\times$ contains $r-1$ linearly independent vectors and $\dim_{\mathbb{R}} W = r - 1$. Therefore $\Gamma_K^\times \cong \mathbb{Z}^{r_1+r_2-1}$ and $\mathcal{O}_K^\times \cong \mu(K) \oplus \mathbb{Z}^{r_1+r_2-1}$.

Thus, there exist units $u_1, u_2, ..., u_t$, $t = r_1 + r_2 - 1$ such that for any other unit $u \in \mathcal{O}_K^\times$, it can be written as

$$u = \zeta u_1^{n_1} \cdots u_t^{n_t}$$

where $\zeta \in \mu(K)$ is a root of unity.

Example 50.2.41: Unit Group And Class Group

1. Let $K = \mathbb{Q}(\sqrt{2})$. Then $1 + \sqrt{2}$ generates the free part of the group of units. Similarly, for $K = \mathbb{Q}(\sqrt{3})$, $2 + \sqrt{3}$ generates the free part of the group of units.

2. Let us compute the class group and unit group of $\mathbb{Q}(\sqrt[3]{7})$ Let $K = \mathbb{Q}(\sqrt[3]{7})$ and $s = \sqrt[3]{7}$. We again look for the Minkowski bound. Doing a similar computation as before, we may workout

   $$\mathcal{O}_K = \langle 1, \sqrt[3]{7}, \sqrt[3]{7}^2 \rangle$$

   Hence, the discriminant is:

   $$\det \begin{pmatrix} 1 & \sqrt[3]{7} & \sqrt[3]{7}^2 \\ 1 & \sqrt[3]{7}\zeta_3 & \sqrt[3]{7}^2\zeta_3^2 \\ 1 & \sqrt[3]{7}\zeta_3^2 & \sqrt[3]{7}^2\zeta_3 \end{pmatrix} = -1323$$

   Thus:

   $$M_K = \sqrt{1323}\frac{6}{27}\frac{4}{\pi} < 11$$

   Hence, we check prime ideal $(2), (3), (5), (7)$ of $\mathbb{Z}$. Since the minimal polynomial of $\sqrt[3]{7}$ is $x^3 - 7$, we see that in $\mathbb{F}_p[x]/(\overline{x^3 - 7}_p)$ we get:

   (2) $(x+1)(x^2+x+1)$, hence

   $$\mathfrak{p}_2 = (2, s+1) \qquad \mathfrak{p}_2' = (2, s^2+s+1)$$

   (3) $(x-1)^3$, hence

   $$\mathfrak{p}_3 = (3, s-1)$$

   (5) $(x+2)(x^2+3x+4)$, hence

   $$\mathfrak{p}_5 = (5, s+2) \qquad \mathfrak{p}_5' = (5, s^2+3s+4)$$

(7) x^3, hence

$$\mathfrak{p}_7 = (7, s) = (s)$$

Thus, just like before we have that $[\mathfrak{p}_2]$, $[\mathfrak{p}_3]$, and $[\mathfrak{p}_5]$ generate $Cl(K)$ (since $[\mathfrak{p}_7] = [1]$). Next, we see that

$$\mathfrak{p}_2\mathfrak{p}_3 = (6) \qquad \mathfrak{p}_3^2\mathfrak{p}_5 = (15)$$

Hence, $[\mathfrak{p}_3] = [\mathfrak{p}_2^{-1}]$ and $[\mathfrak{p}_3^2] = [\mathfrak{p}_5^{-1}]$. Then, with some computation we see that:

$$[\mathfrak{p}_3^3] = [\mathfrak{p}_3]^3 = [\mathrm{id}]$$

Thus, we see that $Cl(K)$ is generated by $[\mathfrak{p}_3]$ and has order 3, hence $CL(K) \cong \mathbb{Z}/3\mathbb{Z}$.

However, what if $\mathfrak{p}_3$ is in fact principal? For the sake of contradiction, let's say

$$\mathfrak{p}_3 = (\alpha) \implies \mathfrak{p}_3^3 = (3) = (\alpha^3)$$

Then $\alpha^3 = 3u$ for some unit u. To find u, we find the units of the ring of integers. To find its units, first notice that if:

$$1 = x^3 - 7 = (x - s)(x^2 + sx + s^2)$$

Then $x - s$ is a unit. But then, $x = 2$ works since $8 - 7 = 1$. Then by Dirichlet's Unit Theorem, we have that the rank of the unit group is:

$$r_1 + r_2 - 1 = 1 + 1 - 1 = 1$$

Hence, the group of units is

$$\langle 2 - \sqrt[7]{2} \rangle$$

which is the second object asked of us to find. Using this, we can finally conclude that there is no unit u that satisfies the equation $\alpha^3 = 3u$ (if $\alpha = a + bs + cs^2$, in the process of finding the coefficients a, b, c we shall be forced to have $b = c = 0$). Hence, we may properly conclude that

$$Cl(K) \cong \mathbb{Z}/3\mathbb{Z}$$

completing the proof.

In general, there is an algorithm for computing the ring of units that involved continued fractions. It is not covered in this book, but for those interested see *Borevich and Shafarevich, Number Theory* section 7.3 of chapter 2.

Proposition 50.2.42: Volume Of Unit Lattice

Let $\mathcal{O}_K$ be a ring of integers with unit group $\mathcal{O}_K^*$, let $t = r_1 + r_2 - 1$, and write the coordinates of $\sigma^\times(x)$ as $\sigma_i^\times(x) = \log|\sigma_i(x)|$ for $1 \leq i \leq r_1$ and $\sigma_{r_1+j}^\times(x) = \log\left(|\tau_j(x)|^2\right)$ for $1 \leq j \leq r_2$. Let $u_1, \ldots, u_t \in \mathcal{O}_K^\times$ be units whose images $\sigma^\times(u_1), \ldots, \sigma^\times(u_t)$ form a $\mathbb{Z}$-basis of the unit lattice $\sigma^\times(\mathcal{O}_K^\times)$. Then the volume of the unit lattice $\sigma^\times(\mathcal{O}_K^\times)$ in the hyper-plane H is:

$$\operatorname{vol}\left(\sigma^\times(\mathcal{O}_K^\times)\right) = \sqrt{r_1 + r_2}R$$

where R is the absolute value of the determinant of the $t \times t$ matrix obtained by deleting any one row of the following $(t+1) \times t$ matrix:

$$\begin{pmatrix} \sigma_1^\times(u_1) & \cdots & \sigma_1^\times(u_t) \\ \vdots & \ddots & \vdots \\ \sigma_{t+1}^\times(u_1) & \cdots & \sigma_{t+1}^\times(u_t) \end{pmatrix}$$

In particular, R does not depend on which row is deleted.

***Proof*:**

By proposition 50.2.38 and theorem 50.2.40, $\Gamma = \sigma^\times(\mathcal{O}_K^\times)$ is a free abelian group of rank t, so units $u_1, \ldots, u_t$ as in the statement exist. Put $v_j = \sigma^\times(u_j) \in \mathbb{R}^{t+1}$. By proposition 50.1.18, $\operatorname{Nm}_{K/\mathbb{Q}}(u_j) = \pm 1$, and by corollary 50.1.13 the coordinates of v_j sum to $\log\left|\operatorname{Nm}_{K/\mathbb{Q}}(u_j)\right| = 0$, each pair $\tau_l, \overline{\tau_l}$ of complex embeddings contributing $\log\left(|\tau_l(u_j)|^2\right)$. So every v_j lies in the hyperplane

$$H = \left\{x \in \mathbb{R}^{t+1} \;\middle|\; x_1 + \cdots + x_{t+1} = 0\right\}$$

of $\mathbb{R}^{t+1}$ with its standard inner product. The group $\Gamma \subseteq H$ is discrete (proposition 50.2.39) and free of rank t, and $\dim H = t$, as H is the kernel of the nonzero linear form $x \mapsto x_1 + \cdots + x_{t+1}$. So Γ spans H by lemma 50.1.56, and it is a complete lattice in H. By definition 50.1.59, applied to Γ in the space H with the inner product of $\mathbb{R}^{t+1}$, $\operatorname{vol}(\Gamma) = |\det(G)|^{1/2}$ with $G = (\langle v_i, v_j\rangle)$. Another $\mathbb{Z}$-basis of Γ replaces G by $U^t G U$ with $\det(U) = \pm 1$, so this number depends only on Γ.

Let $w = (t+1)^{-1/2}(1, \ldots, 1)$, a unit vector orthogonal to H, and let P be the $(t+1)\times(t+1)$ matrix with columns $v_1, \ldots, v_t, w$. Since $\langle v_j, w\rangle = 0$ and $\langle w, w\rangle = 1$, the matrix $P^t P$ is block diagonal with blocks G and (1). By proposition 13.4.6(2), proposition 13.4.7 and proposition 13.4.8,

$$\det(P)^2 = \det(P^t P) = \det(G)$$

so $\operatorname{vol}(\Gamma) = |\det(P)|$.

Fix $k \in \{1, \ldots, t+1\}$ and add every other row of P to row k, which does not change the determinant (proposition 13.4.9(2)). The new row k has entry $\sum_i (v_j)_i = 0$ in each column $j \leq t$, because $v_j \in H$, and entry $(t+1)(t+1)^{-1/2} = \sqrt{t+1}$ in the last column. Subtracting multiples of this row from the other rows clears the rest of the last column without changing the first t columns or the determinant, and moving row k to the bottom multiplies the determinant by ± 1 (proposition 13.4.6(5)). The result is block diagonal with blocks P_k and $(\sqrt{t+1})$, where P_k is

the matrix $(\sigma_i^\times(u_j))$ with row k deleted. By proposition 13.4.8,

$$\operatorname{vol}(\Gamma) = |\det(P)| = \sqrt{t+1}\,|\det(P_k)|$$

The left-hand side does not depend on k, so neither does $R = |\det(P_k)|$, and $\operatorname{vol}(\Gamma) = \sqrt{r_1 + r_2}\,R$, as we sought to show.

Definition 50.2.43: Regulator

The value of R in the above proof is called the *regulator* of $\mathcal{O}_K$.

Exercise 50.2.2

1. What number rings $\mathcal{O}_K$ have finitely many units?

50.3 Extension of Dedekind Domains and Number Fields

In section 26.3, we covered how prime ideals of a base ring correspond to prime ideals in an integral extension. Since all extensions that we are working with are integral extensions, the same theory applies. Working over Dedekind domains, we may further ask if the integral extension of a Dedekind domain is a Dedekind domain. This will be the case, and so we may further factor prime ideals in the extended ring, namely if a prime ideal $\mathfrak{p} \subseteq R$ factors in S where S/R is an integral extension. When focusing on rings of integers $\mathcal{O}_L$, the exploration of how primes factor into larger primes has a lot of consequences on the structure of $\mathcal{O}_L$ itself, and perhaps a bit surprisingly at first sight on the field extension L/K itself. We shall see in the next section that we can use the theory of factorization of prime ideals to classify all abelian extension over $\mathbb{Q}$, this is the *Kronecker-Weber Theorem* promised in example 20.1.29.

First, if R is a Dedekind domain with field of fraction K, $I \subseteq R$ an ideal, through them map $K \hookrightarrow L$ we get $I^e \subseteq \overline{R}^L$. We further generalize this for fractional ideals:

Definition 50.3.1: Extension Of Fractional Ideals

Let R be a Dedekind domain, K it's field of fractions, and L/K be a finite field extension. Then if $I \subseteq K$ is a fractional ideal and $\mathcal{O} = \overline{R}^L$,

$$I_L := I\mathcal{O} = \left\{ \sum a_i b_i \;\middle|\; a_i \in I,\ b_i \in \mathcal{O} \right\}$$

When necessary, the notation $I_{L/K}$ will be used to specify the base field over which I is taken.

It can be verified that $I_L \subseteq L$ is the minimal fractional ideal containing I, that if $M/L/K$, then $(I_L)_M = I_M$, and that $I_L = I \otimes_{\mathcal{O}_K} \mathcal{O}$. The results of lemma 26.2.3 follow quickly giving all the same results. Furthermore since $(I+J)_L = I_L + J_L$:

$$(\underset{K}{\gcd}(I,J))_L = \underset{L}{\gcd}(I_L, J_L)$$

However, by lemma 26.2.3, we so far only have

$$(\text{lcm}_K(I,J))_L \subseteq \text{lcm}_M(I_L, J_L)$$

Note that for $\alpha \in K$, $(\alpha)_L = (\alpha\mathcal{O}_K)_L = \alpha\mathcal{O}_L$, hence principal ideals extend to principal ideals. For reasons that shall become clearer later[19], the map

$$J_K \to J_L \qquad I \mapsto I_L$$

is called the *base change map*. To study the fractional ideals of L, the first immediate result we may want is that $\overline{R}^L$ remains a Dedekind domain:

Lemma 50.3.2: Extending Dedekind Domains

Let R be a Dedekind domain with field of fraction K and let L/K be a finite field extension of K. Then $\mathcal{O} = \overline{R}^L$ is a Dedekind domain.

***Proof*:**
By definition, $\mathcal{O}$ is integrally closed, and if $\mathfrak{p} \subseteq \mathcal{O}$ is a nonzero prime, then $P = \mathfrak{p} \cap R$ is also prime (the contraction of a prime ideal is prime). It is nonzero: for $0 \neq x \in \mathfrak{p}$, an equation $x^m + a_{m-1}x^{m-1} + \cdots + a_0 = 0$ with $a_i \in R$ and m least has $a_0 \neq 0$, since otherwise dividing by x would give one of smaller degree, and $a_0 = -x(x^{m-1} + \cdots + a_1) \in \mathfrak{p} \cap R$. So P is maximal in R. Hence $(\mathcal{O}/\mathfrak{p})/(R/P)$ is an integral extension over a field meaning $\mathcal{O}/\mathfrak{p}$ is a field, thus $\mathfrak{p}$ is maximal. It remains to show that $\mathcal{O}$ is Noetherian.

The separable case has the self-contained proof below, and it is all that number fields need. The general case is corollary 27.2.9: a Dedekind domain is a Noetherian domain of dimension one, and that corollary makes $\mathcal{O}$ a Noetherian normal domain of dimension one with fraction field L, which together with the maximality of primes shown above is the Dedekind property. Let $\alpha_1, \alpha_2, ..., \alpha_n$ be a K -basis for L. By multiplying by an appropriate constant, we may let $\alpha_1, \alpha_2, ..., \alpha_n \in \mathcal{O}$ (see proposition 50.1.7). By proposition 50.1.32,

$$\mathcal{O} \subseteq \frac{R\alpha_1}{d} + \cdots + \frac{R\alpha_n}{d}$$

Now, for any ideal $I \subseteq \mathcal{O}$, by the above it is contained in a finitely generated R-module, hence since R is Noetherian I (as a R-module) is finitely generated. But then *a fortiori*, it is a finitely generated $\mathcal{O}$-module, hence a finitely generated ideal, making $\mathcal{O}$ Noetherian.

Example 50.3.3: Dedekind Domains Via Extension
The result above shows that all rings of integers of a finite extension $L/K/\mathbb{Q}$ is a ring of integers. For an example that is not a number ring, take $R = k[x]$ for some field k. As R is a PID, it is a Dedekind domain. Then if $L/k(x)$ is an integral extension, the integral closure of R over L, $S = \overline{R}^L$, is a Dedekind domain. As $L \cong k(x)[y]/(p(y))$ for some irreducible polynomial over $k[x]$ L represents 1-dimensional curves. Section 50.7 returns to the correspondence between Dedekind domains and smooth curves.

[19] we shall possibly increase the number of primes, hence change the "basis"

Extending Number Fields

An immediate corollary of lemma 50.3.2 is the following:

Corollary 50.3.4: Extending Number Fields

Let L/K be a finite extension of numbers fields so that $\mathcal{O}_K = \overline{\mathbb{Z}}^K$ and $\mathcal{O} = \overline{\mathcal{O}_K}^L$. Then

$$\mathcal{O} = \mathcal{O}_L = \overline{\mathbb{Z}}^L$$

***Proof*:**
Every element of $\mathcal{O}_L$ is integral over $\mathbb{Z} \subseteq \mathcal{O}_K$, so $\mathcal{O}_L \subseteq \mathcal{O}$. Conversely, let $\alpha \in \mathcal{O}$. Every element of $\mathcal{O}_K[\alpha]$ is integral over $\mathcal{O}_K$ (corollary 26.1.6), and $\mathcal{O}_K$ is integral over $\mathbb{Z}$, so α is integral over $\mathbb{Z}$ (corollary 26.1.5) and $\alpha \in \overline{\mathbb{Z}}^L = \mathcal{O}_L$, completing the proof.

Thus, when working with finite extensions of number ring L/K, there is a corresponding integral extensions are those of the ring of integers $\mathcal{O}_L/\mathcal{O}_K$ creating the diagram:

$$\begin{array}{ccc} K & \xrightarrow{\iota} & L \\ \downarrow & & \downarrow \\ \mathcal{O}_K & \xrightarrow{\iota} & \mathcal{O}_L \end{array}$$

As we saw, principal ideals extend to principal ideals. As it turns out, all non-principal ideals extend to be principal given a large enough extension. This result shall underpin a lot of future simplification and is good to see early on:

Lemma 50.3.5: Number Fields, Extension To Principal

Let $I \subseteq K$ be a fractional ideal where $K/\mathbb{Q}$ is a number field. Then in some finite extension L/K, I_L becomes a principal ideal.

***Proof*:**
As $K/\mathbb{Q}$ is a number fields, by theorem 50.2.33, $Cl(K)$ is finite. Thus, for every $I \in J_K$, there exists an $n \in \mathbb{N}$ such that $I^n = \alpha\mathcal{O}_K$. Let $L = K(\sqrt[n]{\alpha})$. letting $\beta = \sqrt[n]{\alpha}$, we get

$$(I_L)^n = (I_L^n) = (I^n\mathcal{O}_L) = (\alpha\mathcal{O}_L) = (\beta\mathcal{O}_L)^n$$

Thus, by unique factorization:

$$I_L = \beta\mathcal{O}_L$$

as we sought to show.

This result is quite useful. In the right cases we can pass to the field in which all our ideals become principal ideals, proof what we want for principal ideals, then try to come back down (coming back down is often called the descent argument). The following lemma gives a very common descent argument, and is important for computing the absolute norm of extended ideals: since the norm of

an ideal gives a measure how space a given ideal is within its Dedekind, extending the domain shall make the given ideal sparser[20]:

Lemma 50.3.6: Number Fields, Extension And Absolute Norm

Let L/K be a finite extension of number fields, $I \subseteq K$ a fractional ideal, and $I_L = I\mathcal{O}_L$ the $\mathcal{O}_L$-submodule of L generated by I. Then I_L is a fractional ideal of L and:

$$\mathfrak{N}_L(I_L) = \mathfrak{N}_K(I)^{[L:K]}$$

***Proof*:**

Step 1: fractional ideals extend. If I is generated by $\alpha_1, \dots, \alpha_m$ and $d \in \mathbb{Z}_{>0}$ satisfies $dI \subseteq \mathcal{O}_K$ (corollary 50.2.12), then I_L is generated over $\mathcal{O}_L$ by the same elements, is nonzero, and $dI_L \subseteq \mathcal{O}_L$. For fractional ideals I, J of K, both $(IJ)_L$ and $I_L J_L$ are the $\mathcal{O}_L$-submodule generated by the products xy with $x \in I$ and $y \in J$, so $(IJ)_L = I_L J_L$.

Step 2: principal fractional ideals. For a number field F and $\alpha \in F^\times$, we show $\mathfrak{N}_F(\alpha\mathcal{O}_F) = |\mathrm{Nm}_{F/\mathbb{Q}}(\alpha)|$. The norm is multiplicative, $\mathrm{Nm}_{F/\mathbb{Q}}(xy) = \det(L_x L_y) = \mathrm{Nm}_{F/\mathbb{Q}}(x)\mathrm{Nm}_{F/\mathbb{Q}}(y)$ by proposition 13.4.7, and $\mathrm{Nm}_{F/\mathbb{Q}}(d) = d^{[F:\mathbb{Q}]}$ for $d \in \mathbb{Z}$. Choose $d \in \mathbb{Z}_{>0}$ with $d\alpha \in \mathcal{O}_F$ (corollary 50.2.12). In J_F, $\alpha\mathcal{O}_F = (d\alpha\mathcal{O}_F)(d\mathcal{O}_F)^{-1}$, so definition 50.2.31 and lemma 50.1.63 give

$$\mathfrak{N}_F(\alpha\mathcal{O}_F) = \frac{|\mathrm{Nm}_{F/\mathbb{Q}}(d\alpha)|}{|\mathrm{Nm}_{F/\mathbb{Q}}(d)|} = |\mathrm{Nm}_{F/\mathbb{Q}}(\alpha)|$$

Step 3: the norm of an element of K. Let $\alpha \in K^\times$ and let r run over the roots of $m_{\alpha,\mathbb{Q}}$ with multiplicity. By proposition 50.1.12, $\mathrm{Nm}_{L/\mathbb{Q}}(\alpha) = (\prod r)^{[L:\mathbb{Q}(\alpha)]}$ and $\mathrm{Nm}_{K/\mathbb{Q}}(\alpha) = (\prod r)^{[K:\mathbb{Q}(\alpha)]}$. Since $[L:\mathbb{Q}(\alpha)] = [L:K][K:\mathbb{Q}(\alpha)]$ (theorem 19.3.7), $\mathrm{Nm}_{L/\mathbb{Q}}(\alpha) = \mathrm{Nm}_{K/\mathbb{Q}}(\alpha)^{[L:K]}$. With Step 2 for $F = L$ and for $F = K$,

$$\mathfrak{N}_L(\alpha\mathcal{O}_L) = \left|\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)\right|^{[L:K]} = \mathfrak{N}_K(\alpha\mathcal{O}_K)^{[L:K]}$$

Step 4: the general case. The class group $Cl(K)$ is finite (theorem 50.2.33), of order h say, so $[I]^h = 1$ by theorem 3.3.1, that is, $I^h = \alpha\mathcal{O}_K$ for some $\alpha \in K^\times$. By Step 1, $(I_L)^h = (I^h)_L = \alpha\mathcal{O}_L$. As $\mathfrak{N}_L$ and $\mathfrak{N}_K$ are homomorphisms (definition 50.2.31), Step 3 gives

$$\mathfrak{N}_L(I_L)^h = \mathfrak{N}_L(\alpha\mathcal{O}_L) = \mathfrak{N}_K(\alpha\mathcal{O}_K)^{[L:K]} = \mathfrak{N}_K(I)^{h[L:K]}$$

and taking positive hth roots completes the proof.

50.3.1 Ideal Correspondence in Extension

Let L/K be a finite extension, J_K and J_L be the corresponding ideal group. Then we have a map $J_K \to J_L$ given by $I \mapsto I_L$. Do we have a converse map, and if so is it an inverse of the

[20] This means that the ideal does not "extend enough" to cancel the added density given by extending the ring

natural extension map? If not, to what degree is it an inverse map? Recall in proposition 26.2.2 that $I \subseteq SI \cap R$, in other words $I \subseteq I_S \cap R$. This can be made an equality for when extending number fields, and further generalized to fractional ideals. Recall that this is not true in general (a counter-example for the general case is $(2) \subsetneq \mathbb{Z} = (2)_{\mathbb{Q}} \cap \mathbb{Z}$), hence this is special for extension of Dedekind domains:

Proposition 50.3.7: Ideal Correspondence In Extensions Of Dedekind Domains

let L/K be a finite field extension with Dedekind domain $\mathcal{O}$ and $\mathfrak{o}$ respectively. Let $I \subseteq K$ a fractional ideal. Then:

$$I_L \cap K = (I^e)^c = I$$

Hence, unlike for general integral extensions, the contraction is an inverse map to the extension.

***Proof*:**

Let $\beta \in J = I\mathcal{O} \cap K$ so that $\beta = \sum_i a_i k_i$ where $a_i \in I_L$ and $k_i \in \mathfrak{o}$ (since $\mathcal{O} \cap K = \mathfrak{o}$). Then the following equality holds:

$$\beta^n = \text{Nm}_{L/K}(\beta) = \prod_\tau \tau(\beta) = \prod_\tau \left(\sum_i k_i \tau(a_i) \right)$$

where the first equality comes from $\beta \in K$, the second comes from the equivalence definition of norm (given an appropriate normal closure N/L), and the third is expanding the definition of β. On the right hand side, we have that the sum is invariant under the Galois group $\text{Gal}_K(N)$ for appropriate normal closure N/L from which we took each τ. Thus, the sum is an element in $\mathfrak{o}$, so the product is in $\mathfrak{o}$. Then we have $\beta^n \in I^n$, so $\beta \in I$, completing the proof.

Due to the importance of this new paradigm of thinking, two other proofs shall be presented. Notice that $IJ^{-1} \subseteq \mathfrak{o}$ and:

$$\mathfrak{N}(IJ^{-1}) = 1$$

giving that $IJ^{-1} = \mathfrak{o}$, i.e. $I = J$.

Another proof goes as follows: Since $I \subseteq J$, $I_L \subseteq J_L$. Since $I_L \subseteq J_L \subseteq I_L$ by properties of extensions, $I_L = J_L$. Thus:

$$\mathfrak{N}(J) = \mathfrak{N}(I_L)^{1/[L:K]} = \mathfrak{N}(I)$$

and since $I \subseteq J$, the norms being equal means the index between the two are the same, hence $I = J$.

Note that in the case where $\mathfrak{p}$ is prime, the result can be essentially immediately proven since by proposition 26.2.2 $\mathfrak{p} \subseteq \mathfrak{p}\mathcal{O}_L \cap K$, but since $\mathfrak{p}$ is maximal we get equality.

Corollary 50.3.8: Homomorphism between Extensions of Ideal Group

Let J_K be the ideal group of a Dedekind domain R and let L/K be a finite field extension. Then the map $J_K \to J_L$ mapping $I \mapsto I_L$ is an injective group homomorphism that preserves gcd and lcm.

On the other hand, the map $Cl(K) \to Cl(L)$ is a homomorphism that need not be injective.

For class groups of number fields:

$$\varinjlim_{\substack{K \\ [K:\mathbb{Q}]<\infty}} (Cl(K)) = 0$$

***Proof*:**
By the previous proposition, $I_L = J_K$ if $I = J$, hence the map $\varphi : \mathscr{F}(K) \to \mathscr{F}(L)$ mapping $I \mapsto I_L$ is injective and is certainly a homomorphism by a simple generalization of lemma 26.2.3 (recall that $(\mathfrak{ab})^e = \mathfrak{a}^e\mathfrak{b}^e$ for ideals).

For the map between class groups of number fields, since the extension for every fractional ideal $I \subseteq \mathbb{Q}$, there exists an extension in which it is principle, we see that the colimit can only be satisfied by the trivial group, hence $\varinjlim_{\substack{K \\ [K:\mathbb{Q}]<\infty}} (Cl(K)) = 0$, as we sought to show.

A side consequence of the colimit definition is that we may define

$$Cl(\overline{\mathbb{Q}}) := \varinjlim(Cl(K)) = 0$$

This shows that to some degree, the lack of principal ideals is tied to what algebraic extension we choose. Though the extension map is injective, it is not in general surjective:

Example 50.3.9: Lack of Surjectivity
Let $L = \mathbb{Q}(\sqrt{-5})$ and $K = \mathbb{Q}$ so $\mathcal{O}_L = \mathbb{Z}[\sqrt{-5}]$. Then the (non-principal) ideal $I = (1+\sqrt{-5}, 1-\sqrt{-5})$ are all numbers of the form $m + n\sqrt{-5}$ where m, n are even, so $I \cap \mathbb{Q} = (2)$, hence I lies over (2). However, $I \neq (2)_L$ since I is not principal (recall $(-)_L$ maps principals to principals), and no other ideal can map to I or else I would lie over some different prime, hence I is not an extension. The ideal (2) is still related to I, namely $I^2 = (2)$ (this can be used to show I is not principal).

With these results, we have better control over the extension of primes and primes lying over (resp. lying under) relate:

Proposition 50.3.10: Dedekind Domain, Lying Over And Lying Under

Let $\mathcal{O}/o$ be a finite extension of Dedekind domains given by L/K, $0 \neq \mathfrak{p} \subseteq o$ a prime, and $\mathcal{O} = \overline{o}^L$, $\mathfrak{p}$, where $\mathfrak{p}$ may factor further. Then $\mathfrak{p}$ will never be trivialized in an extension, namely

$$\mathfrak{p}\mathcal{O} \neq \mathcal{O} = (1)$$

***Proof*:**
Let $p \in \mathfrak{p} \setminus \mathfrak{p}^2$. Then

$$(p) = \mathfrak{p}\mathfrak{a} \qquad \mathfrak{p} \nmid \mathfrak{a}$$

Hence, $\mathfrak{p} + \mathfrak{a} = (1)$ ($\gcd(\mathfrak{p}, \mathfrak{a}) = (1)$), and so $a + b = 1$ for $a \in \mathfrak{p}$ and $b \in \mathfrak{a}$. Certainly $b \notin \mathfrak{p}$ so $b\mathfrak{p} \subseteq \mathfrak{p}\mathfrak{a} = (p)$. Now, if $\mathfrak{p}\mathcal{O} = \mathcal{O}$, then $b\mathcal{O} = b\mathfrak{p}\mathcal{O} \subseteq p\mathcal{O}$. hence $b\mathcal{O}_K \subseteq \mathfrak{p}$ so $b = px$ for some $x \in \mathcal{O} \cap K = \mathcal{O}_K$, implying $b \in \mathfrak{p}$, a contradiction.

Proposition 50.3.11: Equivalence Of Prime Division In Dedekind Domain

Let $\mathfrak{p} \subseteq R$, $\mathfrak{B} \subseteq \mathcal{O}$, $\mathcal{O}/R$ an integral extension where R is a Dedekind Domain. Then the following are equivalent:

1. $\mathfrak{B} \big| \mathfrak{p}\mathcal{O}$
2. $\mathfrak{B} \supseteq \mathfrak{p}\mathcal{O}$
3. $\mathfrak{B} \supseteq \mathfrak{p}$
4. $\mathfrak{B} \cap \mathcal{O} = \mathfrak{p}$
5. $\mathfrak{B} \cap K = \mathfrak{p}$

***Proof*:**
Since we are in a Dedekind domain, $A \big| B$ if and only if $A \supseteq b$, giving us $1 \Leftrightarrow 2$. Since $\mathfrak{B}$ is an ideal of $\mathcal{O}_L$, certainly $2 \Leftrightarrow 3$. We got $3 \Leftarrow 4 \Leftrightarrow 5$ by the above injectivity argument. For $3 \implies 4$, since $\mathfrak{p}$ is maximal and $\mathfrak{B} \cap \mathcal{O}_K \supseteq \mathfrak{p}$, we have either equality or $\mathcal{O}_K$, if $\mathfrak{p} \cap \mathcal{O}_K = \mathcal{O}_K$, then $1 \in Q$, implying $Q = \mathcal{O}_L$, contradicting it's maximality.

Corollary 50.3.12: Lying Over Unique Prime

Let $\mathfrak{p}, \mathfrak{q} \subseteq \mathcal{O}$, $\mathfrak{p} \neq \mathfrak{q}$. Let:

$$\mathfrak{p}\mathcal{O}_L = \mathfrak{B}_1^{e_1} \cdots \mathfrak{B}_n^{e_n} \qquad \mathfrak{q}\mathcal{O}_L = \mathfrak{C}_1^{f_1} \cdots \mathfrak{C}_m^{f_m}$$

Then:

$$\{\mathfrak{B}_1, ..., \mathfrak{B}_n\} \cap \{\mathfrak{C}_1, ..., \mathfrak{C}_n\} = \emptyset$$

that is, extended prime ideals lie over a single prime

***Proof*:**
Let's say the intersection is non-empty, so that $\mathfrak{a}$ is a common factor. Then write:

$$\mathfrak{p}\mathcal{O}_L = \mathfrak{a}^{e_1} \cdots \mathfrak{B}_n^{e_n} \qquad \mathfrak{q}\mathcal{O}_L = \mathfrak{a}^{f_1} \cdots \mathfrak{C}_m^{f_m}$$

Then:

$$(\mathfrak{p})_L^{-1}\mathfrak{p}^{e_1-1}\mathfrak{B}_2^{-e_2} \cdots \mathfrak{B}_n^{-e_n} = \mathfrak{a} = (\mathfrak{q})_L^{-1}\mathfrak{p}^{f_1-1}\mathfrak{C}_2^{-f_2} \cdots \cdots \mathfrak{C}_m^{-f_m}$$

Thus we get:

$$\mathfrak{q}\mathcal{O}_L = (\mathfrak{p})_L\mathfrak{p}^{e_1-1}\mathfrak{B}_2^{-e_2} \cdots \mathfrak{B}_n^{-e_n}\mathfrak{p}^{f_1-1} \cdots \mathfrak{C}_m^{f_m}$$

And in particular:

$$\mathfrak{C}_1^{f_1} \cdots \mathfrak{C}_m^{f_m} = q\mathcal{O}_L \subseteq p\mathcal{O}_L = \mathfrak{B}_1^{e_1} \cdots \mathfrak{B}_n^{e_n}$$

But then, since $\mathfrak{p}\mathcal{O}_L \cap K = \mathfrak{p}$ and $\mathfrak{q}\mathcal{O}_L \cap K = \mathfrak{q}$, we have by corollary 50.3.8 that:

$$\mathfrak{q} \subseteq \mathfrak{p}$$

which since $\mathfrak{q}$ is maximal and $\mathfrak{p} \neq \mathcal{O}_K$ we have $\mathfrak{q} = \mathfrak{p}$, contradicting the fact that $\mathfrak{p} \neq \mathfrak{q}$, hence, it must be that they share no common factors.

Another proof goes as follows: if $\mathfrak{p} \subseteq \mathcal{O}_K$ is a prime and $\mathfrak{p}_L = \mathfrak{B}_1^{e_1} \cdots \mathfrak{B}_k^{e_k}$ is the factorization of $\mathfrak{p}_L$ in $\mathcal{O}_L$, then if there was a prime ideal $\mathfrak{q}$ such that $\mathfrak{q} \mapsto \mathfrak{B}_i$ so that by the above for any $1 \leq i \leq k$, then since $\mathfrak{p} \subseteq \mathfrak{B}_i \cap \mathcal{O}_k$, by maximality $\mathfrak{p} = \mathfrak{B}_i \cap \mathcal{O}_K$. Hence if $\mathfrak{q} = \mathfrak{B}_I \cap \mathcal{O}_k$, by injectivity $\mathfrak{p} = \mathfrak{q}$.

Another consequence of the above theorem is that if two prime factorizations of a prime share a factor in an extended ring of integers, they are equal.

Relative Norm

Since the ideals of Dedekind domains share factorization structure to numbers, we may hope there is an equivalent of the field norm $\mathrm{Nm}_{L/K}$ for ideals. by lemma 50.3.5, we may hope that our new relative norm map gives us some information on the power to which we may rise our ideal to get a principal ideal. We now endeavour to find a map $J_L \to J_K$ that behaves more like the field norm and generalizes the absolute norm, which can be thought of as a map:

$$\mathfrak{N}_{L/\mathbb{Q}} : J_L \to \mathbb{Q}_L \cong \mathbb{Q}_{>0}^{\times}$$

In particular, if we work of *Galois* extensions L/K, then we may hope to translate some of the fact that

$$\mathrm{Nm}_{L/K}(\alpha) = \prod_{\sigma} \sigma(\alpha)$$

to prime ideals! In particular, this allows us to bring in the Galois theory in the study of prime ideals!

We start by showing the case for Galois extensions, the general case can be inferred from the Galois case. Given a Galois extension L/K with Galois group $G = \mathrm{Gal}_K(N)$, then we can recover L from K using G by taking $L^G = K$, hence $\mathcal{O}_L^G = \mathcal{O}_K$. Certainly, if $\tau \in G$ and $\mathfrak{a} \subseteq L$, then $\tau(\mathfrak{a}) \subseteq L$ Since L/K is normal, and hence $\tau(\mathfrak{a})$ is well-defined. It may be tempting to then say that $J_L^G = J_K$ and hence defining $J_L \to J_K$ by taking

$$I \mapsto \prod_{\tau} \tau(I)$$

However, it is not the case that $J_L^G = J_K$. The ideal in example 50.3.9 is invariant under the Galois group, but certainly an ideal of $\mathbb{Z}$. We fix this by the following:

Definition 50.3.13: Relative Norm

Let L/K be a finite field extension and $I \subseteq K$ a fractional ideal in L. Then the *relative norm* or *ideal norm* of L with respect to K is:

$$\mathfrak{N}_{L/K}(I) = \left(\left\{\mathrm{Nm}_{L/K}(\alpha) \;\middle|\; \alpha \in I\right\}\right) \in J_K$$

namely, $\mathfrak{N}_{L/K}(I)$ is the ideal generated by all norms of elements in I.

Note that this is well-defined since $\mathrm{Nm}_{L/K}(\alpha) \in K$ as every minimal polynomial $m_{\alpha,K}(x) \in K[x]$. The norm as defined above gives us a map $\mathfrak{N}_{L/K} : J_L \to J_K$. The field norm can be thought of as the ideal norm, for example take

$$\mathfrak{N}_{\mathbb{Q}(\sqrt{2})/\mathbb{Q}}((\sqrt{2})) = \left(\left\{\mathrm{Nm}_{L/K}\left(\sqrt{2}b\right) \;\middle|\; \sqrt{2}b \in \sqrt{2}\mathbb{Z}\right\}\right) = (2)$$

suggesting that $(\mathrm{Nm}_{L/K}(\alpha)) = \mathfrak{N}_{L/K}((\alpha))$, which will indeed be the case and shall be proved after the next theorem. An important reason to choose this definition is that it works well with extension: Let $J_L \xrightarrow{\mathrm{Nm}_{L/K}} J_K \xrightarrow{I_L} J_L$. What will be the image of an ideal in this chain? In the simplest case, we may take principal ideal $\alpha\mathcal{O}_L \subseteq \mathcal{O}_L$ where $\alpha \in \mathcal{O}_K$. Then it's image is $\alpha\mathcal{O}_K$, and it's extension is $\alpha\mathcal{O}_L$. Thus for the simplest type of integral principal ideal, the map is a right-inverse. For more general cases, it is not necessarily a right inverse (it cannot be, since I_L is not surjective). However, the behavior of the image is well-behaved, and in fact tied with the "almost" definition of the ideal norm presented earlier:

Theorem 50.3.14: Ideal Correspondence in Extension

Let $N/L/K$ be finite field extensions where N/K is normal, let $I \subseteq L$ be a fractional ideal, and let $\sigma_1, \ldots, \sigma_n$ be the distinct K-embeddings $\sigma_i : L \to N$, each extended to an automorphism of N (possible since N/K is normal: lemma 19.5.7 extends each embedding into $\overline{N}$, and normality forces the image to be N). Then:

$$(\mathfrak{N}_{L/K}(I))_N = \prod_i (\sigma_i I)_{N/\sigma_i L} =: \mathrm{Nm}'_{L/K}(I)$$

In particular

$$\left\{\begin{matrix}\text{Fractional ideals of} \\ \mathcal{O}_K\end{matrix}\right\} \underset{\mathfrak{N}_{L/K}}{\overset{I_L}{\rightleftarrows}} \left\{\begin{matrix}\text{Fractional Ideals of} \\ \mathcal{O}_L\end{matrix}\right\}$$

***Proof*:**
Without loss of generality, we may make I integral. Then, certainly an ideal is a subset of its extension (given the natural embedding) $\sigma_i I \subseteq (\sigma_i I)_{N/\sigma_i L}$, and so by definition of $\mathrm{Nm}'_{L/K}(I)$, for all $\alpha \in I$:

$$\mathrm{Nm}_{L/K}(\alpha) = \prod_i \sigma_i(\alpha) \in \mathrm{Nm}'_{L/K}(I)$$

Hence $\mathfrak{N}_{L/K}(I) \subseteq \mathrm{Nm}'_{L/K}(I)$. Extending both sides, we get $(\mathfrak{N}_{L/K}(I))_N \subseteq (\mathrm{Nm}'_{L/K}(I))_N = \mathrm{Nm}'_{L/K}(I)$. Hence, since we are in a Dedekind domain, there exists an [integral] ideal $J \subseteq \mathcal{O}_N$

such that

$$(\mathfrak{N}_{L/K}(I))_N = J\mathrm{Nm}'_{L/K}(I)$$

We want to show that $J = (1)$. By corollary 50.2.21, applied in $\mathcal{O}_L$ to the fractional ideal I^{-1} (theorem 50.2.22) and the nonzero ideal $J \cap L$, there is $b \in L^\times$ such that $B = bI^{-1}$ is an ideal of $\mathcal{O}_L$ relatively prime to $J \cap L$. Then $IB = (b)$, and $b \in IB \subseteq I$. Then since J is fixed under $\mathrm{Gal}_K(N)$, each $(\sigma_i B)_{N/\sigma_i L}$ is relatively prime to J for each i. Then since $b \in I$:

$$\begin{aligned}\left(\mathfrak{N}_{L/K}(I)\right)_N &\supseteq \left(\prod_i \sigma_i(b)\right) \\ &= \left(\prod_i (\sigma_i B)_{N/\sigma_i L}\right)\left(\prod_i (\sigma_i I)_{N/\sigma_i L}\right)\end{aligned}$$

Thus, $\prod_i (\sigma_i B)_{N/\sigma_i L}$ is a multiple of J. However, each $(\sigma_i B)_{N/\sigma_i L}$ is relatively prime to J, hence it must be that $J = (1)$, as we sought to show.

Lemma 50.3.15: Ideal Norm Properties

Let $M/L/K$ be algebraic number fields, $\mathfrak{a}, \mathfrak{b} \subseteq M$ be ideals, $I \subseteq K$ an ideal, and $a \in M$ an element. Then:

1. $\mathfrak{N}_{M/K}(a) = (\mathrm{Nm}_{M/K}(a)) = (\prod_\sigma \sigma(a))$, where σ ranges over the distinct K-embeddings of M into a normal extension of K containing M
2. $\mathfrak{N}_{L/K}(\mathfrak{N}_{M/L}(\mathfrak{a})) = \mathfrak{N}_{M/K}(\mathfrak{a})$
3. $\mathfrak{N}_{M/K}(\mathfrak{ab}) = \mathfrak{N}_{M/K}(\mathfrak{a})\mathfrak{N}_{M/K}(\mathfrak{b})$
4. $I^{[M:K]} = \mathfrak{N}_{M/K}((I)_M)$
5. $(\mathfrak{N}_K(I)) = \mathfrak{N}_{K/\mathbb{Q}}(I)$

***Proof*:**
Note that for all of these equalities, we immediately have $\supseteq$, hence we want to show $\subseteq$ for each of these.

1. By definition 50.3.13, the ideal $\mathfrak{N}_{M/K}(a\mathcal{O}_M)$ is generated by the elements $\mathrm{Nm}_{M/K}(ab)$ with $b \in \mathcal{O}_M$. The norm is multiplicative because the determinant is, by proposition 13.4.7, so $\mathrm{Nm}_{M/K}(ab) = \mathrm{Nm}_{M/K}(a)\mathrm{Nm}_{M/K}(b)$. The norms $\mathrm{Nm}_{M/K}(b)$ with $b \in \mathcal{O}_M$ lie in $\mathcal{O}_K$ (corollary 50.1.14) and include $\mathrm{Nm}_{M/K}(1) = 1$, so they generate $\mathcal{O}_K$, and $\mathfrak{N}_{M/K}(a\mathcal{O}_M) = \mathrm{Nm}_{M/K}(a)\mathcal{O}_K$. The second expression is corollary 50.1.13.
2. Let N/K be a finite normal extension of K containing M, so that N/L is normal as well. Let $\tau_1, \ldots, \tau_n$ be the distinct K-embeddings of L into N and $\sigma_1, \ldots, \sigma_m$ the distinct L-embeddings of M into N. Each of these extends to an automorphism of N: it extends to a homomorphism $N \to \overline{N}$ by lemma 19.5.7, and the image is N by normality of N/K, respectively N/L, via theorem 19.5.13. Any automorphism τ of N fixes $\mathbb{Q}$ pointwise, and an element of N lies in $\mathcal{O}_N$ exactly when its minimal polynomial over $\mathbb{Q}$ has integer coefficients.

An element and its image under τ share this minimal polynomial, so $\tau(\mathcal{O}_N) \subseteq \mathcal{O}_N$, and the same applied to τ^{-1} gives $\tau(\mathcal{O}_N) = \mathcal{O}_N$. Since τ is a ring isomorphism it carries products of ideals to products of their images, and since $\tau(\mathcal{O}_N) = \mathcal{O}_N$ the image of a fractional ideal of $\mathcal{O}_N$ is again a fractional ideal of $\mathcal{O}_N$. For every fractional ideal J of a subfield $F \subseteq N$, we write $(\tau J)_N = (\tau J)_{N/\tau F}$ for the extension of τJ to $\mathcal{O}_N$, so that:

$$(\tau J)_N = \tau(J)\mathcal{O}_N = \tau(J)\tau(\mathcal{O}_N) = \tau(J_N)$$

Applying theorem 50.3.14 in the tower $N/L/K$ to the fractional ideal $\mathfrak{N}_{M/L}(\mathfrak{a})$ of L, and then in the tower $N/M/L$ to $\mathfrak{a}$:

$$\begin{aligned}\left(\mathfrak{N}_{L/K}(\mathfrak{N}_{M/L}(\mathfrak{a}))\right)_N &= \prod_i \left(\tau_i\, \mathfrak{N}_{M/L}(\mathfrak{a})\right)_N = \prod_i \tau_i \left(\left(\mathfrak{N}_{M/L}(\mathfrak{a})\right)_N\right) \\ &= \prod_i \tau_i \left(\prod_j (\sigma_j \mathfrak{a})_N\right) = \prod_{i,j} (\tau_i \sigma_j \mathfrak{a})_N\end{aligned}$$

The restrictions of the composites $\tau_i\sigma_j$ to M are K-embeddings of M into N, and they are distinct: if $\tau_i\sigma_j = \tau_{i'}\sigma_{j'}$ on M, then restricting to L, where every σ_j is the identity, gives $\tau_i = \tau_{i'}$ on L, so $i = i'$, and composing with τ_i^{-1} gives $\sigma_j = \sigma_{j'}$ on M, so $j = j'$. Number fields are separable over $\mathbb{Q}$, so the number of K-embeddings of L into $\overline{K}$ equals $[L : K]$ by proposition 19.6.17, and each of them lands inside N by the extension argument above. Hence $n = [L : K]$, and likewise $m = [M : L]$ and there are $[M : K]$ distinct K-embeddings of M into N. As the composites give $nm = [M : L][L : K] = [M : K]$ distinct ones, they are exactly the distinct K-embeddings of M into N. Applying theorem 50.3.14 once more, now in the tower $N/M/K$:

$$\prod_{i,j} (\tau_i \sigma_j \mathfrak{a})_N = \left(\mathfrak{N}_{M/K}(\mathfrak{a})\right)_N$$

Since the extension map $J_K \to J_N$ is injective by corollary 50.3.8, it follows that $\mathfrak{N}_{L/K}(\mathfrak{N}_{M/L}(\mathfrak{a})) = \mathfrak{N}_{M/K}(\mathfrak{a})$. In particular the remaining containment $\subseteq$ holds.

3. Let N/K be a finite normal extension of K containing M and let $\tau_1, \ldots, \tau_n$ be the distinct K-embeddings of M into N. Each τ_i is a ring isomorphism onto $\tau_i M$, so $\tau_i(\mathfrak{ab}) = \tau_i(\mathfrak{a})\tau_i(\mathfrak{b})$. The minimal polynomial argument of the previous item, applied to the elements of M, gives $\tau_i(\mathcal{O}_M) = \mathcal{O}_{\tau_i M}$, so $\tau_i\mathfrak{a}$ is an ideal of $\mathcal{O}_{\tau_i M}$ and its extension $(\tau_i\mathfrak{a})_N$ is defined. Extension of ideals is multiplicative by corollary 50.3.8. Applying theorem 50.3.14 in the tower $N/M/K$ to $\mathfrak{ab}$, then to $\mathfrak{a}$ and $\mathfrak{b}$ separately:

$$\left(\mathfrak{N}_{M/K}(\mathfrak{ab})\right)_N = \prod_i (\tau_i(\mathfrak{a})\tau_i(\mathfrak{b}))_N = \prod_i (\tau_i\mathfrak{a})_N \prod_i (\tau_i\mathfrak{b})_N = \left(\mathfrak{N}_{M/K}(\mathfrak{a})\mathfrak{N}_{M/K}(\mathfrak{b})\right)_N$$

Since the extension map $J_K \to J_N$ is injective by corollary 50.3.8, the stated equality follows. In particular the containment $\subseteq$ holds.

4. Let N and $\tau_1, \ldots, \tau_{[M:K]}$ be as in item (3) above, so that the τ_i are the $[M : K]$ distinct K-embeddings of M into N, as counted in item (2) above, each extended to an automorphism of N. Each τ_i fixes $I \subseteq K$ pointwise, so $\tau_i(I_M) = I\tau_i(\mathcal{O}_M)$ and $(\tau_i I_M)_N = I\mathcal{O}_N = I_N$. By theorem 50.3.14 in the tower $N/M/K$,

$$\left(\mathfrak{N}_{M/K}(I_M)\right)_N = \prod_i (\tau_i I_M)_N = (I_N)^{[M:K]} = \left(I^{[M:K]}\right)_N$$

and injectivity of the extension map $J_K \to J_N$ (corollary 50.3.8) gives $\mathfrak{N}_{M/K}(I_M) = I^{[M:K]}$.

5. Here I is a nonzero ideal of $\mathcal{O}_K$. If $I = a\mathcal{O}_K$ is principal, then (1) gives $\mathfrak{N}_{K/\mathbb{Q}}(I) = \mathrm{Nm}_{K/\mathbb{Q}}(a)\mathbb{Z}$, while $\mathfrak{N}_K(I) = |\mathrm{Nm}_{K/\mathbb{Q}}(a)|$ by lemma 50.1.63. In general, the class group is finite (theorem 50.2.33), of order h say, so $I^h = a\mathcal{O}_K$ for some a by theorem 3.3.1. Write $\mathfrak{N}_{K/\mathbb{Q}}(I) = c\mathbb{Z}$ with $c > 0$. By (3), the principal case and proposition 50.2.30,

$$c^h\mathbb{Z} = \mathfrak{N}_{K/\mathbb{Q}}(I^h) = \mathfrak{N}_K(I^h)\mathbb{Z} = \mathfrak{N}_K(I)^h\mathbb{Z}$$

so $c^h = \mathfrak{N}_K(I)^h$, and $c = \mathfrak{N}_K(I)$ as both are positive, completing the proof.

Corollary 50.3.16: Relative Norm Of Prime Ideal

Let L/K be a finite extension of number fields and let $\mathfrak{B}$ be a nonzero prime of $\mathcal{O}_L$ lying above the prime $\mathfrak{p}$ of $\mathcal{O}_K$. Then if $f = [\mathcal{O}_L/\mathfrak{B} : \mathcal{O}_K/\mathfrak{p}]$, then:

$$\mathfrak{N}_{L/K}(\mathfrak{B}) = \mathfrak{p}^f$$

***Proof*:**

Step 1: a power of $\mathfrak{p}$. As $\mathfrak{p}\mathcal{O}_L \subseteq \mathfrak{B}$, corollary 50.2.18(3) gives an ideal $\mathfrak{c}$ of $\mathcal{O}_L$ with $\mathfrak{p}\mathcal{O}_L = \mathfrak{B}\mathfrak{c}$. By lemma 50.3.15(3) and (4), $\mathfrak{N}_{L/K}(\mathfrak{B})\mathfrak{N}_{L/K}(\mathfrak{c}) = \mathfrak{N}_{L/K}(\mathfrak{p}\mathcal{O}_L) = \mathfrak{p}^{[L:K]}$. Both factors are ideals of $\mathcal{O}_K$, generated by norms of elements of $\mathcal{O}_L$ (corollary 50.1.14), so by theorem 50.2.15, $\mathfrak{N}_{L/K}(\mathfrak{B}) = \mathfrak{p}^j$ for some $j \geq 0$.

Step 2: the exponent. The field $k = \mathcal{O}_K/\mathfrak{p}$ embeds into $\mathcal{O}_L/\mathfrak{B}$, which is a k-vector space of dimension f, so $\mathfrak{N}_L(\mathfrak{B}) = |k|^f = \mathfrak{N}_K(\mathfrak{p})^f$, with $\mathfrak{N}_K(\mathfrak{p}) \geq 2$ (lemma 50.2.29). By lemma 50.3.15(2) and (5), and proposition 50.2.30,

$$\mathfrak{N}_K(\mathfrak{p})^f\mathbb{Z} = \mathfrak{N}_L(\mathfrak{B})\mathbb{Z} = \mathfrak{N}_{L/\mathbb{Q}}(\mathfrak{B}) = \mathfrak{N}_{K/\mathbb{Q}}(\mathfrak{N}_{L/K}(\mathfrak{B})) = \mathfrak{N}_{K/\mathbb{Q}}(\mathfrak{p}^j) = \mathfrak{N}_K(\mathfrak{p})^j\mathbb{Z}$$

so $j = f$, completing the proof.

The relative norm can in fact be defined to be the unique group homomorphism where

$$\mathfrak{N}(\mathfrak{B}) = \mathfrak{p}^{[\mathcal{O}_L/\mathfrak{B}:\mathcal{O}_K/\mathfrak{p}]}$$

which is left as an exercise. By multiplicity, we get that in general:

$$\mathfrak{N}_{L/K}(\mathfrak{p}\mathcal{O}_L) = \prod_i \mathfrak{N}_{L/K}(\mathfrak{B}_i)^{e_i} = \prod_i \mathfrak{p}^{f_i e_i}$$

Corollary 50.3.17: Ideal Norm Correspondence Not Galois

Let $M/L/K$ be algebraic number fields with M/K normal but not necessarily L/K, and let $I \subseteq L$ be a fractional ideal. Then

$$(\mathfrak{N}_{L/K}(I))_M = \prod_{\tau \in \mathrm{Gal}_K(M)/\mathrm{Gal}_L(M)} \tau(I_M)$$

***Proof*:**
Let $\sigma_1, \ldots, \sigma_n$ be the distinct K-embeddings $\sigma_i : L \to M$, each extended to an automorphism of M as in theorem 50.3.14, which applied with $N = M$ gives:

$$(\mathfrak{N}_{L/K}(I))_M = \prod_i (\sigma_i I)_{M/\sigma_i L}$$

Every $\tau \in \mathrm{Gal}_K(M)$ restricts to a K-embedding $L \to M$, and two automorphisms τ, τ' have the same restriction exactly when $\tau^{-1}\tau'$ fixes L pointwise, that is, when $\tau\mathrm{Gal}_L(M) = \tau'\mathrm{Gal}_L(M)$. Since every K-embedding $L \to M$ extends to an automorphism of M (as recorded in theorem 50.3.14), restriction is a bijection from $\mathrm{Gal}_K(M)/\mathrm{Gal}_L(M)$ onto $\{\sigma_1, \ldots, \sigma_n\}$.

Now let $\tau \in \mathrm{Gal}_K(M)$ extend σ_i. Any automorphism τ of M fixes $\mathbb{Q}$ pointwise, an element of M lies in $\mathcal{O}_M$ exactly when its minimal polynomial over $\mathbb{Q}$ has integer coefficients, and an element and its image under τ share this minimal polynomial, so $\tau(\mathcal{O}_M) = \mathcal{O}_M$. Therefore

$$(\sigma_i I)_{M/\sigma_i L} = \tau(I)\mathcal{O}_M = \tau(I)\tau(\mathcal{O}_M) = \tau(I_M)$$

This value depends only on the coset $\tau\mathrm{Gal}_L(M)$: for $\rho \in \mathrm{Gal}_L(M)$, ρ fixes $I \subseteq L$ pointwise and $\rho(\mathcal{O}_M) = \mathcal{O}_M$, so $\rho(I_M) = I_M$ and $\tau\rho(I_M) = \tau(I_M)$. Substituting $\tau(I_M)$ for each factor of the displayed product gives the claimed equality, as we sought to show.

With the relative norm defined, it is perhaps natural to think there is a relative discriminant:

Definition 50.3.18: Relative Discriminant

Let L/K be a finite extension of number fields. Then:

$$\mathrm{disc}'_{L/K}(\mathcal{O}_L) = \left(\left\{\mathrm{disc}_{L/K}(\alpha_1, \alpha_2, ..., \alpha_n) \;\middle|\; \alpha_1, \alpha_2, ..., \alpha_n \text{ basis for } \mathcal{O}_L \right\}\right)$$

is the *relative discriminant* of L with respect to K.

This will not come up much, but is useful in a couple of tower arguments later on.

Though we have characterized a correspondence of the ideals, it is more difficult to characterize I_L. In the following section, we characterize prime extensions, and take advantage of the fact that the factorization to give us a characterization of I_L.

50.4 Prime Factorization in Extension

Since $\mathcal{O}$ is a Dedekind domain by lemma 50.3.2, we have that $\mathfrak{p}\mathcal{O}$ decomposes uniquely into a product of prime ideals:

$$\mathfrak{p}\mathcal{O} = \mathfrak{B}_1^{e_1} \cdots \mathfrak{B}_r^{e_r}$$

If it is clear from context, we shall often write $\mathfrak{p}$ instead of $\mathfrak{p}\mathcal{O}$. Sometimes, we shall also write $\mathfrak{p}_L$ for $\mathfrak{p}\mathcal{O}_L$. We shall *almost always* find exactly how $\mathfrak{p}\mathcal{O}$ decomposes, sometimes without requiring knowledge of the ring of integers. When the extension L/K is Galois, we shall have even more control, and if L/K is not Galois, we can take $M/L/K$ to be a Galois extension, work within the Galois, and see if the results can be translated back to L/K.

Let's say $\mathfrak{B}$ lies over $\mathfrak{p}$ and that $\mathfrak{B}$ is in the prime decomposition of $\mathfrak{B}$ [21]. Then we have two important quantities associated to $\mathfrak{B}$: it's power in the prime decomposition, and the index $[\mathcal{O}/\mathfrak{B} : \mathcal{O}_K/\mathfrak{p}]$, that is the degree of the extension of the residue field. These quantities are given a name:

Definition 50.4.1: Ramification Index and Inertia Degree

Let R be a Dedekind domain, $K = \text{Frac}(R)$, L/K be a finite field extension, $\mathcal{O} = \overline{R}^L$ and $\mathfrak{p} \subseteq R$ a nonzero prime ideal. If $\mathfrak{B}_i$ is a prime in $\mathcal{O}$ lying above $\mathfrak{p}$, then the exponent of $\mathfrak{B}_i$ in $\mathfrak{p}\mathcal{O}$ is called the *ramification index* and is often denoted

$$e(\mathfrak{B}_i/\mathfrak{p}) \qquad \text{where} \qquad \mathfrak{B}^{e(\mathfrak{B}_i/\mathfrak{p})} \| \mathfrak{p}\mathcal{O}$$

or e_i for short, where $\|$ means *maximally divides*. The degree of the field extension

$$f(\mathfrak{B}_i/\mathfrak{p}) = [\mathcal{O}/\mathfrak{B}_i : R/\mathfrak{p}]$$

or f_i for short, is called the *inertia degree* or *residue field degree* of $\mathfrak{B}_i$ over $\mathfrak{p}$.

For future reference, it will be important to keep track to "how much" a prime ideal splits. This will share strong similarities to the splitting of polynomials[22] (recall how "rare" an irreducible polynomial is inseparable)? This prompts the following vocabulary:

Definition 50.4.2: Split, Unramified, and Totally Ramified Primes

Let $\mathfrak{p} \subseteq R$ be a prime ideal of a Dedekind domain R, $K = K(R)$, L/K a finite extension, and $\mathcal{O} = \overline{R}^L$. Then given

$$\mathfrak{p}\mathcal{O} = \mathfrak{B}_1^{e_1} \cdots \mathfrak{B}_g^{e_g}$$

If $g = [L : K]$, then $\mathfrak{p}$ is said to *split completely* ($e_i = f_i = 1$), giving:

$$\mathfrak{p}\mathcal{O} = \mathfrak{B}_1 \cdots \mathfrak{B}_n$$

If $e_i = 1$ for all i (but some f_i are not necessarily 1), then we sy that $\mathfrak{p}$ is *unramified* and (if the residue field is separable):

$$\mathfrak{p}\mathcal{O} = \mathfrak{B}_1 \cdots \mathfrak{B}_g$$

for some $g \leq n$, where $n = [L : K]$. If $g = 1$, so that $\mathfrak{p}\mathcal{O} = \mathfrak{B}_1^{e_1}$ and $\mathfrak{B}_1$ is the only prime ideal lying over $\mathfrak{p}$, then $\mathfrak{p}$ is said to be *indecomposable* or *nonsplit*. If moreover

$$\mathfrak{p}\mathcal{O} = \mathfrak{B}_1^n$$

then $\mathfrak{p}$ is said to be *totally ramified*.

Most of the time, we shall work in the case of character zero extensions, hence L/K is separable. In this case, the values e_i and f_i are connected. If $\mathfrak{p}$ factors in an extension, then there is a simple equation the ramification and inertia degree must satisfy which equals the degree of the extension:

[21] we shall soon show all primes lying above $\mathfrak{p}$ will be part of the prime decomposition
[22] Though there shall be important failures when this comparison will *not* hold! This shall be elaborated soon

Proposition 50.4.3: Fundamental Identity

Let o be a Dedekind domain with fraction field K, L/K a finite separable extension of degree n, $\mathcal{O} = \overline{o}^L$ the integral closure of o in L, and $0 \neq \mathfrak{p} \subseteq o$ a prime ideal. If

$$\mathfrak{p}\mathcal{O} = \mathfrak{B}_1^{e_1} \cdots \mathfrak{B}_g^{e_g}$$

is the prime decomposition of $\mathfrak{p}\mathcal{O}$, with the $\mathfrak{B}_i$ distinct, and f_i is the inertia degree of $\mathfrak{B}_i$ over $\mathfrak{p}$, then

$$\sum_{i=1}^{g} e_i f_i = n$$

For an extension L/K of number fields this applies with $o = \mathcal{O}_K$ and $\mathcal{O} = \mathcal{O}_L$ (corollary 50.3.4).

***Proof*:**
The ring $\mathcal{O}$ is a Dedekind domain (lemma 50.3.2), so $\mathfrak{p}\mathcal{O}$ has the stated factorization. Put $\kappa = o/\mathfrak{p}$, a field as $\mathfrak{p}$ is maximal (definition 50.2.1), and $S = o \setminus \mathfrak{p}$. Each $\mathfrak{B}_i$ contains $\mathfrak{p}$, so $\mathfrak{B}_i \cap o$ is a prime of o containing the maximal ideal $\mathfrak{p}$, hence equal to it, and every quotient below is a κ-vector space through $o \to \kappa$.

Step 1: a free localization. By lemma 50.2.4, $o_\mathfrak{p} = S^{-1}o$ is a DVR, hence a principal ideal domain (proposition 27.2.1). The ring $S^{-1}\mathcal{O} \subseteq L$ is the integral closure of $o_\mathfrak{p}$ in L. An element x/s with $x \in \mathcal{O}$ and $s \in S$ is integral over $o_\mathfrak{p}$: dividing an equation $x^m + a_{m-1}x^{m-1} + \cdots + a_0 = 0$ over o by s^m gives a monic equation for x/s with coefficients $a_i/s^{m-i} \in o_\mathfrak{p}$. Conversely, if $y \in L$ satisfies $y^m + (b_{m-1}/t_{m-1})y^{m-1} + \cdots + b_0/t_0 = 0$ with $b_i \in o$ and $t_i \in S$, then for $t = t_0 \cdots t_{m-1}$, multiplying by t^m shows that ty is integral over o, so $ty \in \mathcal{O}$ and $y = ty/t \in S^{-1}\mathcal{O}$. The ring $o_\mathfrak{p}$ has fraction field K and is integrally closed in it, being the localization of the normal domain o (corollary 26.1.10). As L/K is separable and $o_\mathfrak{p}$ is a principal ideal domain, proposition 50.1.32 shows that $S^{-1}\mathcal{O}$ is a free $o_\mathfrak{p}$-module of rank n.

Step 2: $\dim_\kappa \mathcal{O}/\mathfrak{p}\mathcal{O} = n$. Let $M \subseteq L$ be an o-submodule. For $s \in S$ we have $o = \mathfrak{p} + so$, by maximality of $\mathfrak{p}$, so there is $t \in o$ with $st - 1 \in \mathfrak{p}$. We claim that the map $M/\mathfrak{p}M \to S^{-1}M/\mathfrak{p}S^{-1}M$ induced by inclusion is an isomorphism. It is surjective, since for $x \in M$ we have $x/s - tx = x(1-st)/s \in \mathfrak{p}S^{-1}M$. It is injective: if $x \in M$ lies in $\mathfrak{p}S^{-1}M$, then $x = y/s$ with $y \in \mathfrak{p}M$, so $sx = y \in \mathfrak{p}M$, and $x = t(sx) - (st-1)x \in \mathfrak{p}M$. With $M = o$ this gives $\kappa \cong o_\mathfrak{p}/\mathfrak{p}o_\mathfrak{p}$. With $M = \mathcal{O}$, and an isomorphism $S^{-1}\mathcal{O} \cong o_\mathfrak{p}^n$ of $o_\mathfrak{p}$-modules from Step 1, which carries $\mathfrak{p}S^{-1}\mathcal{O}$ onto $(\mathfrak{p}o_\mathfrak{p})^n$,

$$\mathcal{O}/\mathfrak{p}\mathcal{O} \cong S^{-1}\mathcal{O}/\mathfrak{p}S^{-1}\mathcal{O} \cong (o_\mathfrak{p}/\mathfrak{p}o_\mathfrak{p})^n \cong \kappa^n$$

All these maps are o-linear, hence κ-linear, so $\dim_\kappa \mathcal{O}/\mathfrak{p}\mathcal{O} = n$.

Step 3: the Chinese remainder theorem. The ideals $\mathfrak{B}_i^{e_i}$ are pairwise comaximal (lemma 50.2.17), so theorem 9.6.11 gives a ring isomorphism, which is o-linear and hence κ-linear,

$$\mathcal{O}/\mathfrak{p}\mathcal{O} \cong \mathcal{O}/\mathfrak{B}_1^{e_1} \times \cdots \times \mathcal{O}/\mathfrak{B}_g^{e_g}$$

Dimensions add over finite products (proposition 13.1.17), so by Step 2, $n = \sum_i \dim_\kappa \mathcal{O}/\mathfrak{B}_i^{e_i}$.

Step 4: $\dim_\kappa \mathcal{O}/\mathfrak{B}^e = ef$. Let $\mathfrak{B} = \mathfrak{B}_i$, $e = e_i$ and $f = f_i = [\mathcal{O}/\mathfrak{B} : \kappa]$ (definition 50.4.1), finite because $\mathcal{O}/\mathfrak{B}$ is a quotient of $\mathcal{O}/\mathfrak{p}\mathcal{O}$. For $0 \le j < e$, the κ-space $\mathcal{O}/\mathfrak{B}^{j+1}$ contains $\mathfrak{B}^j/\mathfrak{B}^{j+1}$, which is isomorphic to $\mathcal{O}/\mathfrak{B}$ by lemma 50.2.24 and so has dimension f, with quotient isomorphic to $\mathcal{O}/\mathfrak{B}^j$ (theorem 12.2.10). So $\dim_\kappa \mathcal{O}/\mathfrak{B}^{j+1} = \dim_\kappa \mathcal{O}/\mathfrak{B}^j + f$ (proposition 13.1.17), and induction on j gives $\dim_\kappa \mathcal{O}/\mathfrak{B}^e = ef$. With Step 3, $n = \sum_i e_i f_i$, completing the proof.

For number fields, absolute norms give a second proof. Let $k = \mathcal{O}_K/\mathfrak{p}$, a finite field with $|k| = \mathfrak{N}_K(\mathfrak{p}) \ge 2$ (lemma 50.2.29). Each $\mathfrak{B}_i \cap \mathcal{O}_K$ is the maximal ideal $\mathfrak{p}$, so k embeds into $\mathcal{O}_L/\mathfrak{B}_i$, which has $|k|^{f_i}$ elements, and $\mathfrak{N}_L(\mathfrak{B}_i) = |k|^{f_i}$. Then proposition 50.2.30, applied in L, gives $\mathfrak{N}_L(\mathfrak{p}\mathcal{O}_L) = \prod_i \mathfrak{N}_L(\mathfrak{B}_i)^{e_i} = |k|^{\sum_i e_i f_i}$, while lemma 50.3.6 gives $\mathfrak{N}_L(\mathfrak{p}\mathcal{O}_L) = \mathfrak{N}_K(\mathfrak{p})^n = |k|^n$.

Corollary 50.4.4: Multiplicity of Ramification And Inertia

Let $M/L/K$ be finite extensions of number fields, let $\mathfrak{B}$ be a nonzero prime of $\mathcal{O}_M$, and put $\mathfrak{q} = \mathfrak{B} \cap \mathcal{O}_L$ and $\mathfrak{p} = \mathfrak{B} \cap \mathcal{O}_K$. Then:

$$e(\mathfrak{B}/\mathfrak{p}) = e(\mathfrak{B}/\mathfrak{q})\, e(\mathfrak{q}/\mathfrak{p}) \qquad f(\mathfrak{B}/\mathfrak{p}) = f(\mathfrak{B}/\mathfrak{q})\, f(\mathfrak{q}/\mathfrak{p})$$

that is, in short, $e_{M/K} = e_{M/L} e_{L/K}$ and $f_{M/K} = f_{M/L} f_{L/K}$.

***Proof*:**
The ideal $\mathfrak{q}$ is a prime of $\mathcal{O}_L$ and $\mathfrak{p} = \mathfrak{q} \cap \mathcal{O}_K$ is a prime of $\mathcal{O}_K$, both nonzero since $\mathfrak{B} \cap \mathbb{Z} \neq 0$ (lemma 50.2.29). The rings $\mathcal{O}_L$ and $\mathcal{O}_M$ are the integral closures of $\mathcal{O}_K$ and $\mathcal{O}_L$ in L and M (corollary 50.3.4) and are Dedekind domains (theorem 50.2.6). By proposition 50.3.11, $\mathfrak{B}$ divides $\mathfrak{q}\mathcal{O}_M$ and $\mathfrak{p}\mathcal{O}_M$, and $\mathfrak{q}$ divides $\mathfrak{p}\mathcal{O}_L$, so the three ramification indices and inertia degrees are defined (definition 50.4.1).

The inclusions $\mathcal{O}_K \subseteq \mathcal{O}_L \subseteq \mathcal{O}_M$ induce homomorphisms of fields $\mathcal{O}_K/\mathfrak{p} \to \mathcal{O}_L/\mathfrak{q} \to \mathcal{O}_M/\mathfrak{B}$, injective because $\mathfrak{q} \cap \mathcal{O}_K = \mathfrak{p}$ and $\mathfrak{B} \cap \mathcal{O}_L = \mathfrak{q}$. So theorem 19.3.7 gives $f(\mathfrak{B}/\mathfrak{p}) = f(\mathfrak{B}/\mathfrak{q}) f(\mathfrak{q}/\mathfrak{p})$.

For the ramification indices, factor $\mathfrak{p}\mathcal{O}_L = \mathfrak{q}^a \mathfrak{a}$ with $a = e(\mathfrak{q}/\mathfrak{p})$ and $\mathfrak{q} \nmid \mathfrak{a}$, and $\mathfrak{q}\mathcal{O}_M = \mathfrak{B}^b \mathfrak{b}$ with $b = e(\mathfrak{B}/\mathfrak{q})$ and $\mathfrak{B} \nmid \mathfrak{b}$ (theorem 50.2.15). Extension of ideals is multiplicative, the two sides being generated by the same products, so

$$\mathfrak{p}\mathcal{O}_M = (\mathfrak{p}\mathcal{O}_L)\mathcal{O}_M = (\mathfrak{q}\mathcal{O}_M)^a (\mathfrak{a}\mathcal{O}_M) = \mathfrak{B}^{ab} \mathfrak{b}^a (\mathfrak{a}\mathcal{O}_M)$$

The prime $\mathfrak{B}$ does not divide $\mathfrak{a}\mathcal{O}_M$: otherwise $\mathfrak{B} \supseteq \mathfrak{a}$, so the prime $\mathfrak{B} \cap \mathcal{O}_L = \mathfrak{q}$ contains $\mathfrak{a}$ and divides it (corollary 50.2.18), contrary to $\mathfrak{q} \nmid \mathfrak{a}$. So the exponent of $\mathfrak{B}$ in $\mathfrak{p}\mathcal{O}_M$ is ab, that is $e(\mathfrak{B}/\mathfrak{p}) = e(\mathfrak{B}/\mathfrak{q}) e(\mathfrak{q}/\mathfrak{p})$, as we sought to show.

Hence, we have a measure of how much a prime ideal splits in an extension.

Example 50.4.5: Decomposing Prime

1. It is possible that $\mathfrak{p}$ is totally ramified where $e_1 > 1$ and $f_1 = 1$: take $L = \mathbb{Q}(\sqrt{3})$ and $K = \mathbb{Q}$ with $I = (3)$. Then $(3)\mathcal{O} = (\sqrt{3})^2$

2. It is possible that $\mathfrak{p}$ is indecomposable with $e_1 = 1$ and $f_1 > 1$, so that $\mathfrak{p}\mathcal{O}$ is prime: take $K = \mathbb{Q}$, $L = \mathbb{Q}(\sqrt{3})$, but $I = (5)$. Here $x^2 - 3$ is irreducible modulo 5, as 3 is not a square modulo 5.

3. Let us consider the inertia degree to get some structure of the Dedekind domain. Let $L = \mathbb{Q}(\sqrt[3]{2})$ and $L/\mathbb{Q}$ be a finite extension. Since it is always the case that $\mathbb{Z}[\sqrt[3]{2}] \subseteq \mathcal{O}_L$[a], Take $I = (\sqrt[3]{2}) \subseteq \mathcal{O}_L$, $I \cap \mathbb{Q} = (2)$, and $\mathfrak{N}((\sqrt[3]{2})) = |\mathrm{Nm}_{L/\mathbb{Q}}(\sqrt[3]{2})| = 2$, and $2 = (\sqrt[3]{2})^3$. Hence, $f_1 = 1$, meaning
$$[\mathcal{O}_L/\sqrt[3]{2}\mathcal{O}_L : \mathbb{Z}/2\mathbb{Z}] = 1$$
implying both fields only have two elements, hence
$$\mathcal{O}_L/\sqrt[3]{2}\mathcal{O}_L \cong \mathbb{Z}/2\mathbb{Z}$$
Notice how this also gave information on the ring of integers,

4. Let $\mathcal{O}_K = \mathbb{Z}[i]$ so that $2 = (1+i)(1-i)$. Then $\mathcal{O}_K/2\mathcal{O}_K$ has order 4 (look at it'snorm), and certainly $2\mathcal{O}_K \subseteq (1-i)$, hence $|\mathcal{O}_K/(1-i)|4$, which by direct computation we may see that $|\mathcal{O}_K/(1-i)| = 2$, hence $f = 1$. On the other hand, we can see that 3 is prime in $\mathcal{O}_K$, and $|\mathcal{O}_K/3\mathcal{O}_K| = 9$, giving $f_{3\mathcal{O}_K/3} = 2$.

[a] In fact, they are equal in this case, which is not needed at the moment

Since the factorization of $\mathfrak{p} \subseteq K$ in L/K is tied to the degree of L/K, we may venture into hoping that the structure of L/K may reflect something about the factorization of $\mathfrak{p}$. A natural question we may ask here is how do we find the prime factors in the extension? Finding them is split into two cases: the "good" primes and the "bad' primes. We shall see that the power of the exponentials has a lot to do with it. This is because we shall see that most primes shall decompose with ramification index 1, since it will correspond to the splitting of a polynomial in separable extension (note that all number field extensions are separable). However, as we saw it is possible that prime may have higher ramification index, however it is impossible that a polynomial splits irreducibly with multiplicity higher than 1 over a separable extension. Hence, we may think of such prime as "bad" primes. In the following we shall show how to find primes whose factorization mirrors that of a minimal polynomial, and how to detect when it is not the case.

let L/K be a finite separable extension. Then by the primitive extension theorem, there exists a $\theta \in K$
$$L = K(\theta)$$
Usually, we shall let L be Galois so that we may computationally find this element, namely it must not be fixed by any element of $\mathrm{Gal}_K(L)$ (hence, not in any intermediate extension). In fact, we may find θ so that $\theta \in \mathcal{O}_K$: if $L = K(\alpha)$, since $L = \overline{\mathcal{O}_K}^L$ we may multiply out the denominator by d to get $\alpha = \theta$. Let us simply re-define θ to be in $\mathcal{O}_L$. Now we have a single element, θ with minimal polynomial $m_{K,\theta}(x)$ which characterizes L. It would be nice to say something about the nature of the decomposition of $\mathfrak{p}$ in $\mathcal{O}_L$ given this information. In the good case, we shall be able to do so, and in the bad case we shall require a bit more work. In particular, a finite number of primes ideals will be exclude. Only those that are relatively prime to an ideal known as the *conductor* of the ring $\mathcal{O}_K[\theta]$ will be considered:

Definition 50.4.6: Conductor

Let $\mathcal{O}_K[\theta]$ be the ring of integers extended by θ. Then the conductor of $\mathcal{O}_K[\theta]$, is the largest ideal $\mathscr{F}_\theta \subseteq \mathcal{O}_L$ which is contained in $\mathcal{O}_K[\theta]$:

$$\mathscr{F}_\theta = \{\alpha \in \mathcal{O}_L \mid \alpha\mathcal{O}_L \subseteq \mathcal{O}_K[\theta]\}$$

In the case where $K = \mathbb{Q}$ and $\mathcal{O}_\mathbb{Q} = \mathbb{Z}$, then $\mathscr{F}_\theta = \{\alpha \in \mathcal{O}_L \mid (\alpha)_L \subseteq \mathbb{Z}[\theta]\}$. Since $\mathcal{O}_L$ is a finitely generated $\mathcal{O}_K$ module, $\mathscr{F}_\theta \neq 0$. The conductor is a measure of the "bad primes" (hence the ramification). In our case, the conductor is never 0, but it may be that $\mathscr{F}_\theta = (1)$, in which case the bad primes will be "tame" (or the field is "tamely ramified")

Theorem 50.4.7: Dedekind-Kummer Theorem

Let $\mathcal{O}_K$ be a Dedekind domain with fraction field K, let L/K be a finite separable extension, and let $\mathcal{O}$ be the integral closure of $\mathcal{O}_K$ in L. Let $L = K(\theta)$ where θ is a primitive element whose minimal polynomial $m(x) = m_{\theta,K}(x)$ lies in $\mathcal{O}_K[x]$. Let $\mathfrak{p}$ be a nonzero prime ideal of $\mathcal{O}_K$ which is relatively prime to the conductor $\mathscr{F}$ of $\mathcal{O}_K[\theta]$, that is, $\mathfrak{p}\mathcal{O} + \mathscr{F} = \mathcal{O}$, and let

$$\overline{m}(x) = \overline{m}_1(x)^{e_1} \cdots \overline{m}_r(x)^{e_r}$$

be the factorization of the polynomial $\overline{m}(x) = m(x) \bmod \mathfrak{p}$ into distinct monic irreducible polynomials over the residue field $\mathcal{O}_K/\mathfrak{p}$. Let $m_i(x) \in \mathcal{O}_K[x]$ be monic polynomials reducing to $\overline{m}_i(x)$. Then

$$\mathfrak{B}_i = \mathfrak{p}\mathcal{O} + m_i(\theta)\mathcal{O} = (\mathfrak{p}\mathcal{O}, m_i(\theta))_L$$

are different prime ideals of $\mathcal{O}$ over $\mathfrak{p}$, and they are all the primes of $\mathcal{O}$ over $\mathfrak{p}$. Moreover $\mathcal{O}/\mathfrak{B}_i \cong (\mathcal{O}_K/\mathfrak{p})[x]/(\overline{m}_i)$ as $\mathcal{O}_K/\mathfrak{p}$-algebras, so the inertia degree f_i of $\mathfrak{B}_i$ is the degree of $\overline{m}_i(x)$, and

$$\mathfrak{p}\mathcal{O} = \mathfrak{B}_1^{e_1} \cdots \mathfrak{B}_r^{e_r}$$

If $\mathfrak{p}$ is not relatively prime to $\mathscr{F}$, the theorem gives no information: the factorization of $\overline{m}$ need not reflect that of $\mathfrak{p}\mathcal{O}$.

***Proof*:**
Write $\mathcal{O}' = \mathcal{O}_K[\theta]$, $\kappa = \mathcal{O}_K/\mathfrak{p}$ and $n = [L : K] = \deg m$. The ring $\mathcal{O}$ is a Dedekind domain (lemma 50.3.2), and $\theta \in \mathcal{O}$ because m is monic with coefficients in $\mathcal{O}_K$, so $\mathcal{O}' \subseteq \mathcal{O}$. The conductor $\mathscr{F}$ is an ideal of $\mathcal{O}$ contained in $\mathcal{O}'$: if $\alpha \in \mathscr{F}$ and $\beta \in \mathcal{O}$ then $\alpha\beta\mathcal{O} \subseteq \alpha\mathcal{O} \subseteq \mathcal{O}'$, and $\alpha = \alpha\cdot 1 \in \mathcal{O}'$. A nonzero x in a nonzero ideal I of $\mathcal{O}$ satisfies a monic equation $x^d + a_{d-1}x^{d-1} + \cdots + a_0 = 0$ over $\mathcal{O}_K$ of least degree, and then $a_0 \neq 0$, since otherwise dividing by x gives one of smaller degree. Hence $a_0 = -x(x^{d-1} + \cdots + a_1)$ is a nonzero element of $I \cap \mathcal{O}_K$. We use this observation twice.

Step 1: $\mathfrak{p} + (\mathscr{F} \cap \mathcal{O}_K) = \mathcal{O}_K$. We have $\mathscr{F} \neq 0$, since otherwise $\mathfrak{p}\mathcal{O} = \mathcal{O}$, contrary to proposition 50.3.10. Factor $\mathscr{F} = \prod_\mathfrak{Q} \mathfrak{Q}^{c_\mathfrak{Q}}$ (theorem 50.2.15). For each prime $\mathfrak{Q}$ dividing $\mathscr{F}$, the prime $\mathfrak{q} = \mathfrak{Q} \cap \mathcal{O}_K$ of $\mathcal{O}_K$ is nonzero by the observation above, hence maximal, and $\mathfrak{q} \neq \mathfrak{p}$: otherwise $\mathfrak{Q}$ contains $\mathfrak{p}\mathcal{O}$ and $\mathscr{F}$, hence $\mathfrak{p}\mathcal{O} + \mathscr{F} = \mathcal{O}$. Let $\mathfrak{q}_1, \ldots, \mathfrak{q}_s$ be the distinct primes so obtained, and let c be the largest exponent $c_\mathfrak{Q}$. The ideals $\mathfrak{q}_1^c, \ldots, \mathfrak{q}_s^c, \mathfrak{p}$ are pairwise comaximal. A maximal ideal containing $\mathfrak{q}_j^c$ contains $\mathfrak{q}_j$, being prime, and so equals $\mathfrak{q}_j$, and a maximal ideal

containing $\mathfrak{p}$ equals $\mathfrak{p}$. So no maximal ideal contains two of these ideals, and an ideal containing two of them is $\mathcal{O}_K$ (proposition 9.4.18). So theorem 9.6.11 gives $a \in \mathcal{O}_K$ with $a \in \mathfrak{q}_j^c$ for every j and $a - 1 \in \mathfrak{p}$. Then $a \notin \mathfrak{p}$, and for each $\mathfrak{Q} \big| \mathscr{F}$ we have $a\mathcal{O} \subseteq \mathfrak{q}^c\mathcal{O} \subseteq \mathfrak{Q}^c \subseteq \mathfrak{Q}^{c_\mathfrak{Q}}$, as $\mathfrak{q}\mathcal{O} \subseteq \mathfrak{Q}$. By unique factorization the exponent of every $\mathfrak{Q}$ in $a\mathcal{O}$ is at least $c_\mathfrak{Q}$, so $\mathscr{F}$ divides $a\mathcal{O}$, that is $a \in \mathscr{F}$ (corollary 50.2.18). So $a \in (\mathscr{F} \cap \mathcal{O}_K) \setminus \mathfrak{p}$, and as $\mathfrak{p}$ is maximal, $\mathfrak{p} + (\mathscr{F} \cap \mathcal{O}_K) = \mathcal{O}_K$.

Step 2: $\mathcal{O}/\mathfrak{p}\mathcal{O} \cong \mathcal{O}'/\mathfrak{p}\mathcal{O}' \cong \kappa[x]/(\overline{m})$. Since $\mathscr{F} \subseteq \mathcal{O}'$, the hypothesis gives $\mathcal{O} = \mathfrak{p}\mathcal{O} + \mathcal{O}'$, so the ring homomorphism $\mathcal{O}' \to \mathcal{O}/\mathfrak{p}\mathcal{O}$ is surjective, with kernel $\mathfrak{p}\mathcal{O} \cap \mathcal{O}'$. This kernel is $\mathfrak{p}\mathcal{O}'$. The inclusion $\mathfrak{p}\mathcal{O}' \subseteq \mathfrak{p}\mathcal{O} \cap \mathcal{O}'$ holds as $\mathcal{O}' \subseteq \mathcal{O}$. Conversely, let $x \in \mathfrak{p}\mathcal{O} \cap \mathcal{O}'$ and use Step 1 to write $1 = a + c$ with $a \in \mathfrak{p}$ and $c \in \mathscr{F} \cap \mathcal{O}_K$. Then $ax \in \mathfrak{p}\mathcal{O}'$, as $x \in \mathcal{O}'$. Writing $x = \sum_j a_j y_j$ with $a_j \in \mathfrak{p}$ and $y_j \in \mathcal{O}$, we get $cx = \sum_j a_j(cy_j)$ with $cy_j \in \mathscr{F} \subseteq \mathcal{O}'$, so $cx \in \mathfrak{p}\mathcal{O}'$, and $x = ax + cx \in \mathfrak{p}\mathcal{O}'$. By theorem 9.3.12, $\mathcal{O}/\mathfrak{p}\mathcal{O} \cong \mathcal{O}'/\mathfrak{p}\mathcal{O}'$.

Next, evaluation at θ is a surjective ring homomorphism $\mathcal{O}_K[x] \to \mathcal{O}'$, whose kernel is (m): if $g(\theta) = 0$, division by the monic polynomial m gives $g = qm + h$ with $q, h \in \mathcal{O}_K[x]$ and $\deg h < n$, and $h(\theta) = 0$ forces $h = 0$ since $1, \theta, \dots, \theta^{n-1}$ are linearly independent over K. Reducing coefficients modulo $\mathfrak{p}$ and then passing to $\kappa[x]/(\overline{m})$ is a surjective ring homomorphism $\mathcal{O}_K[x] \to \kappa[x]/(\overline{m})$ with kernel $\mathfrak{p}\mathcal{O}_K[x] + (m)$: if $\overline{g} = \overline{m}\,\overline{u}$ with $u \in \mathcal{O}_K[x]$, then $g - mu$ has coefficients in $\mathfrak{p}$. Since $\mathfrak{p}\mathcal{O}_K[x] + (m)$ is the preimage of $\mathfrak{p}\mathcal{O}'$ under evaluation, we get $\mathcal{O}'/\mathfrak{p}\mathcal{O}' \cong \kappa[x]/(\overline{m})$ (theorem 9.3.12). Composing gives an isomorphism of rings

$$\psi\colon \mathcal{O}/\mathfrak{p}\mathcal{O} \to R := \kappa[x]/(\overline{m}) \qquad h(\theta) + \mathfrak{p}\mathcal{O} \mapsto \overline{h}(x) + (\overline{m})$$

for $h \in \mathcal{O}_K[x]$. It is $\mathcal{O}_K$-linear, hence κ-linear.

Step 3: the primes above $\mathfrak{p}$. By theorem 9.3.15, ideals of $\mathcal{O}$ containing $\mathfrak{p}\mathcal{O}$ correspond, through ψ, to ideals of $\kappa[x]$ containing $(\overline{m})$, by an inclusion-preserving bijection matching quotient rings, hence prime ideals with prime ideals. Under it, the ideal generated by $\mathfrak{p}\mathcal{O}$ and some elements $h(\theta)$ corresponds to the ideal generated by $\overline{m}$ and the $\overline{h}$. The ring $\kappa[x]$ is a principal ideal domain (corollary 11.1.2), so a prime ideal containing $\overline{m} \neq 0$ is (g) for an irreducible monic g dividing $\overline{m}$, that is one of the $(\overline{m}_i)$, and each $(\overline{m}_i)$ is prime (proposition 10.1.33). Hence the primes of $\mathcal{O}$ containing $\mathfrak{p}\mathcal{O}$, which are the primes over $\mathfrak{p}$ (proposition 50.3.11), are exactly the ideals $\mathfrak{B}_i = \mathfrak{p}\mathcal{O} + m_i(\theta)\mathcal{O}$, which are distinct. Moreover $\mathcal{O}/\mathfrak{B}_i \cong \kappa[x]/(\overline{m}_i)$ as κ-algebras, and $1, x, \dots, x^{\deg \overline{m}_i - 1}$ is a κ-basis of the latter, so $f_i = \deg \overline{m}_i$.

Step 4: the exponents. By Step 3 and theorem 50.2.15, $\mathfrak{p}\mathcal{O} = \mathfrak{B}_1^{a_1} \cdots \mathfrak{B}_r^{a_r}$ with $a_i = e(\mathfrak{B}_i/\mathfrak{p}) \geq 1$. Fix i and $k \geq 1$. The ideal $\mathfrak{B}_i^k$ is generated by products of k elements of $\mathfrak{p}\mathcal{O}$ or of $m_i(\theta)\mathcal{O}$, and such a product lies in $\mathfrak{p}\mathcal{O}$ unless all its factors lie in $m_i(\theta)\mathcal{O}$, so $\mathfrak{B}_i^k + \mathfrak{p}\mathcal{O} = m_i(\theta)^k\mathcal{O} + \mathfrak{p}\mathcal{O}$. By corollary 50.2.18(2) this ideal is $\mathfrak{B}_i^{\min(k,a_i)}$. Under the correspondence of Step 3 it matches $(\overline{m}_i^k, \overline{m}) = (\overline{m}_i^{\min(k,e_i)})$, the generator being a greatest common divisor in the principal ideal domain $\kappa[x]$. As the correspondence is a bijection,

$$\mathfrak{B}_i^{\min(k,a_i)} = \mathfrak{B}_i^{\min(k+1,a_i)} \iff (\overline{m}_i^{\min(k,e_i)}) = (\overline{m}_i^{\min(k+1,e_i)})$$

By unique factorization in $\mathcal{O}$ and in $\kappa[x]$, the left side holds exactly when $k \geq a_i$ and the right side exactly when $k \geq e_i$. Hence $a_i = e_i$, and $\mathfrak{p}\mathcal{O} = \mathfrak{B}_1^{e_1} \cdots \mathfrak{B}_r^{e_r}$, completing the proof.

Corollary 50.4.8: Factorization For Number Rings (Dedekind-Kummer Theorem)

Let L/K be a finite extension of number fields, $L = K(\theta)$ for a primitive element θ where $m(x) = m_{\theta,K}(x) \in \mathcal{O}_K[x]$. Let $\mathfrak{p} \subseteq \mathcal{O}_K$ be a nonzero prime ideal lying over $p \in \mathbb{Z}$, let $\overline{m}(x) = \overline{m}_1(x)^{e_1} \cdots \overline{m}_r(x)^{e_r}$ be the factorization of m modulo $\mathfrak{p}$ into distinct monic irreducible polynomials over $\mathcal{O}_K/\mathfrak{p}$, and let $m_i(x) \in \mathcal{O}_K[x]$ be monic polynomials reducing to $\overline{m}_i(x)$. If $p \nmid [\mathcal{O}_L : \mathcal{O}_K[\theta]]$, then

$$\mathfrak{B}_i = \mathfrak{p}\mathcal{O}_L + m_i(\theta)\mathcal{O}_L = (\mathfrak{p}\mathcal{O}_L, m_i(\theta))_L$$

are different prime ideals of $\mathcal{O}_L$ over $\mathfrak{p}$. The inertia degree f_i of $\mathfrak{B}_i$ is the degree of $\overline{m}_i(x)$, and

$$\mathfrak{p}\mathcal{O}_L = \mathfrak{B}_1^{e_1} \cdots \mathfrak{B}_r^{e_r}$$

***Proof*:**
The ring $\mathcal{O}_L$ is the integral closure of the Dedekind domain $\mathcal{O}_K$ in L (corollary 50.3.4, theorem 50.2.6), and L/K is separable as both fields have characteristic 0. We check that $\mathfrak{p}$ is relatively prime to the conductor $\mathscr{F}$ of $\mathcal{O}' = \mathcal{O}_K[\theta]$, and then theorem 50.4.7 gives the conclusion. The index $N = [\mathcal{O}_L : \mathcal{O}']$ is finite: if $\omega_1, \dots, \omega_d$ is an integral basis of $\mathcal{O}_K$, the products $\omega_j\theta^i$ with $0 \leq i < [L : K]$ are algebraic integers forming a $\mathbb{Q}$-basis of L and spanning $\mathcal{O}'$ over $\mathbb{Z}$, so $\mathcal{O}' \subseteq \mathcal{O}_L \subseteq \frac{1}{D}\mathcal{O}'$ for their discriminant D, which is nonzero (corollary 50.1.28, proposition 50.1.43), and $\mathcal{O}_L/\mathcal{O}'$ is a quotient of the finite group $\mathcal{O}_L/D\mathcal{O}_L$. By theorem 3.3.1, N annihilates $\mathcal{O}_L/\mathcal{O}'$, so $N\mathcal{O}_L \subseteq \mathcal{O}'$, that is $N \in \mathscr{F}$. Since $p \nmid N$ there are $u, v \in \mathbb{Z}$ with $1 = uN + vp$, and $p \in \mathfrak{p}$, so $1 \in \mathscr{F} + \mathfrak{p}\mathcal{O}_L$ and $\mathfrak{p}\mathcal{O}_L + \mathscr{F} = \mathcal{O}_L$, as we sought to show.

Corollary 50.4.9: Monogenic Number Rings

Let L/K be a finite extension of number rings such that $\mathcal{O}_L = \mathcal{O}_K[\alpha]$ for some $\alpha \in \mathcal{O}_L$. Then all primes split as given in the above

***Proof*:**
Choose $\theta = \alpha$. Then $[\mathcal{O}_L : \mathcal{O}_K[\alpha]] = [\mathcal{O}_K[\alpha] : \mathcal{O}_K[\alpha]] = 1$. Since certainly no prime divides 1, we have that all primes factor in given their minimal polynomials and modular factorization, as we sought to show.

Note that not all number rings are of the form $\mathcal{O}_L = \mathcal{O}_K[\alpha]$, that is not all number rings are monogenic. We shall show a counter-example in example 50.4.29. This contrasts to finite extension of field where every separable finite extension of is a simple extension by theorem 19.6.20. Note how this is dependent on finding a θ and $\mathfrak{p}$ being relatively prime to $\mathscr{F}_\theta$ (or $[\mathcal{O}_L : \mathcal{O}_K[\theta]]$ in the case of number fields)[23].

As it turns out, the power of an extended prime has important geometric and algebraic consequences. It can be thought of as the measure of how much the Galois group moves a field around. We hence give it an name:

[23] However, if K is a local field, as defined in [33], every extension *is* monogenic. This property, among many other similar niceties, makes developing number theory over local fields much more streamlined. The interested reader should see [33] as a follow up to this chapter

Definition 50.4.10: Ramified and Unramified Extensions

Let $\mathfrak{p} \subseteq R$ be a prime ideal, $K = K(R)$, L/K a finite extension, and $\mathcal{O} = \overline{K}^L$. Then given

$$\mathfrak{p}\mathcal{O} = \mathfrak{B}_1^{e_1} \cdots \mathcal{B}_r^{e_r}$$

Then the prime ideal $\mathfrak{B}_i$ is called *unramified* over $\mathcal{O}_k$ (or over K) if $e_i = 1$ and if the residue fields $(\mathcal{O}/\mathfrak{B}_i)/(\mathcal{O}_K/\mathfrak{p})$ is separable[a]:

$$\mathfrak{p}\mathcal{O} = \mathfrak{B}_1 \cdots \mathfrak{B}_r$$

Otherwise, $\mathfrak{B}_i$ is called *ramified*. The prime $\mathfrak{B}_i$ is called *totally ramified* if $\mathfrak{p}\mathcal{O} = \mathfrak{B}_i^{[L:K]}$, that is, if $\mathfrak{p}$ is totally ramified in the sense of definition 50.4.2 with $\mathfrak{B}_i$ the prime above it. The prime ideal $\mathfrak{p}$ is called *unramified* if all $\mathfrak{B}_i$ are unramified, and $\mathfrak{p}$ is ramified otherwise. The extension L/K is called *unramified* or an *unramified extension* if all prime ideals $\mathfrak{p}$ of K are unramified.

[a] which for number fields this is always the case

It is in fact rare that a prime ideal $\mathfrak{p}$ of K is ramified in L[24], however every [nontrivial] extension of $\mathbb{Q}$ is ramified (i.e. some primes ramify). Later, we shall see that there do exist [nontrivial] unramified extension L/K where $K \neq \mathbb{Q}$. To understand ramification in extension, we first show how we can factor most $\mathfrak{B}_i$. The term "ramification" comes from complex analysis, where if a holomorphic function f has a root, $f(a) = 0$, the order of the root is the ramification index[25].

Theorem 50.4.11: Counting Ramified Primes

Let R be a Dedekind domain with fraction field K, L/K a finite separable extension of degree n, $\mathcal{O}$ the integral closure of R in L, and $\theta \in \mathcal{O}$ a primitive element of L/K with minimal polynomial $m = m_{\theta,K} \in R[x]$. Let $d = \det(\mathrm{tr}_{L/K}(\theta^{i+j}))_{0 \leq i,j < n}$ and let $\mathscr{F}_\theta$ be the conductor of $R[\theta]$. Then every nonzero prime $\mathfrak{p}$ of R with $d \notin \mathfrak{p}$ and $\mathfrak{p}\mathcal{O} + \mathscr{F}_\theta = \mathcal{O}$ is unramified in L (definition 50.4.10): every ramification index in $\mathfrak{p}\mathcal{O}$ equals 1, and every residue field extension over $R/\mathfrak{p}$ is separable. In particular, only finitely many primes of R ramify in L, and they lie among the primes dividing dR or not relatively prime to $\mathscr{F}_\theta$.

Note that it is still possible that primes factor as given in theorem 50.4.7 since a prime may be relatively prime to $\mathscr{F}_\theta$ but not the discriminant of $m_{K,\theta}(x)$.

***Proof*:**

Step 1: finitely many exceptions. The traces $\mathrm{tr}_{L/K}(\theta^k)$ lie in R (corollary 50.1.14), so $d \in R$, and $d \neq 0$ by corollary 50.1.30, as $1, \theta, \ldots, \theta^{n-1}$ is a K-basis of L. So only the finitely many primes in the factorization of dR contain d (theorem 50.2.15). The conductor $\mathscr{F}_\theta$ (definition 50.4.6) is a nonzero ideal of $\mathcal{O}$: by proposition 50.1.32, $\mathcal{O}$ is generated as an R-module by finitely many $y_1, \ldots, y_s$, each y_i is a K-combination of $1, \theta, \ldots, \theta^{n-1}$, and clearing the denominators of all these coefficients gives $0 \neq c \in R$ with $c\mathcal{O} \subseteq R[\theta]$, that is, $c \in \mathscr{F}_\theta$. A prime $\mathfrak{p}$ with $\mathfrak{p}\mathcal{O} + \mathscr{F}_\theta \neq \mathcal{O}$ lies below a maximal ideal of $\mathcal{O}$ containing $\mathfrak{p}\mathcal{O} + \mathscr{F}_\theta$, which is one of the finitely many primes

[24] This correspond to the algebro-geometric fact that all but finitely many points of curve are *nonsingular*

[25] if $f(a) = 0$ has order n, there exists a g such that $f = g^n$ in some neighbourhood, which shows how much f "winds" around the root

dividing $\mathscr{F}_\theta$, and a prime of $\mathcal{O}$ lies over only one prime of R. This gives the last sentence once the first is shown.

Step 2: the trace form modulo $\mathfrak{p}$. Let $\mathfrak{p}$ be as in the statement, $\kappa = R/\mathfrak{p}$, and $A = \kappa[x]/(\overline{m})$, with κ-basis $1, \overline{x}, \dots, \overline{x}^{n-1}$. The matrix of multiplication by θ on L in the basis $1, \theta, \dots, \theta^{n-1}$ is the companion matrix C of m, with entries in R, and its reduction $\overline{C}$ is the matrix of multiplication by $\overline{x}$ on A. So $\mathrm{tr}_{A/\kappa}(\overline{x}^k) = \mathrm{tr}(\overline{C}^k)$ is the reduction of $\mathrm{tr}_{L/K}(\theta^k) = \mathrm{tr}(C^k)$, and the matrix $T = (\mathrm{tr}_{A/\kappa}(\overline{x}^{i+j}))_{ij}$ has determinant $d + \mathfrak{p} \neq 0$.

Step 3: $\overline{m}$ *has no repeated factor.* Suppose $\overline{m} = g^2 h$ with g nonconstant, and let $\nu \neq 0$ be the class of gh in A. Then $\nu^2 = \overline{m}h = 0$ in A, so for each $y \in A$ the multiplication by νy is a κ-linear map N with $N^2 = 0$. In $M_n(\kappa[x])$, $(xI - N)(xI + N) = x^2 I$, so by proposition 13.4.7 the characteristic polynomial $\det(xI - N)$, monic of degree n, divides x^{2n} in the unique factorization domain $\kappa[x]$ (corollary 11.1.2), and so equals x^n. By proposition 13.5.2, $\mathrm{tr}_{A/\kappa}(\nu y) = 0$. Writing $\nu = \sum_k c_k \overline{x}^k$ with $(c_k) \neq 0$ gives $\sum_k c_k \mathrm{tr}_{A/\kappa}(\overline{x}^{k+j}) = \mathrm{tr}_{A/\kappa}(\nu \overline{x}^j) = 0$ for every j, so (c_k) is a nonzero vector killed by T, and $\det(T) = 0$, a contradiction.

Step 4: the residue fields are separable. By Step 3, $\overline{m} = \overline{m}_1 \cdots \overline{m}_r$ with distinct monic irreducible $\overline{m}_i$, which are pairwise comaximal in the principal ideal domain $\kappa[x]$, so theorem 9.6.11 gives a κ-algebra isomorphism $A \cong E_1 \times \cdots \times E_r$ with $E_i = \kappa[x]/(\overline{m}_i)$, a field. In a basis adapted to this product, multiplication by an element $(y_1, \dots, y_r)$ is block diagonal, so $\mathrm{tr}_{A/\kappa}$ of it is $\sum_i \mathrm{tr}_{E_i/\kappa}(y_i)$. Suppose some E_i, say E_1, is inseparable over κ. Then $\mathrm{tr}_{E_1/\kappa}$ is identically zero (corollary 50.1.30), so the nonzero element $\nu \in A$ corresponding to $(1, 0, \dots, 0)$ has $\mathrm{tr}_{A/\kappa}(\nu y) = \mathrm{tr}_{E_1/\kappa}(y_1) = 0$ for every $y \in A$. As in Step 3, this gives a nonzero vector killed by T, contradicting $\det(T) \neq 0$. So every E_i is separable over κ.

Step 5: conclusion. As $\mathfrak{p}\mathcal{O} + \mathscr{F}_\theta = \mathcal{O}$, theorem 50.4.7 shows that the exponents of the primes $\mathfrak{B}_i$ of $\mathcal{O}$ in $\mathfrak{p}\mathcal{O}$ are the exponents in the factorization of $\overline{m}$ into irreducibles, which are all 1 by Step 3, and that $\mathcal{O}/\mathfrak{B}_i \cong E_i$, which is separable over κ by Step 4. So $\mathfrak{p}$ is unramified, completing the proof.

We can in fact be more precise than the above result: the ramified primes ideals will be given by the *relative discriminant* of $\mathcal{O}_L/\mathcal{O}_K$, which will be given by the ideal $\mathfrak{o} \subseteq \mathcal{O}_K$ which is generated by the discriminants $d(\omega_1, \omega_2, ..., \omega_n)$ for all bases $\omega_1, \omega_2, ..., \omega_n$ of L/K contained in $\mathcal{O}_L$. A special case is that of the base-field being $K = \mathbb{Q}$.

Proposition 50.4.12: Detecting Ramification In Number Fields

Let p be a prime in $\mathbb{Z}$. Suppose p is ramified. Then:

$$p \big| \mathrm{disc}(\mathcal{O}_K)$$

In proposition 50.4.16, we will show the converse, showing this is an iff.

***Proof*:**
Let $\mathfrak{B}$ lie over $\mathfrak{p}$ and $e_{\mathfrak{B}/\mathfrak{p}} > 1$. Thus

$$p\mathcal{O}_K = \mathfrak{B}I$$

where I is divisible by *all* primes of $\mathcal{O}_K$ lying over p. Let $\sigma_1, \sigma_2, ..., \sigma_n$ denote the embeddings of K in $\mathbb{C}$, and extend each σ_i to automorphisms of some extension of L/K which is normal over $\mathbb{Q}$. Let $\alpha_1, \alpha_2, ..., \alpha_n$ be some integral basis for R. What we shall do is replace one of the α_i be a suitable element that will show that $p \big| \text{disc}(\mathcal{O}_K)$.

Take $\alpha \in I - p\mathcal{O}_K$. Then certainly α is in every prime ideal lying over p but *not* in $p\mathcal{O}_K$. writing

$$\alpha = m_1\alpha_1 + \cdots m_n\alpha_n$$

for appropriate $m_i \in \mathbb{Z}$, then since $\alpha \notin p\mathcal{O}_K$, we have that p does not divide each m_i. Re-arrange the terms so that $p \nmid m_1$. Then if d is the discriminant of $\mathcal{O}_K$, through direct computation, we can see that

$$\text{disc}(\alpha, \alpha_2, ..., \alpha_n) = m_1^2 d$$

Since $p \nmid m_1$, we shall show that $p \big| \text{disc}(\alpha, \alpha_2, ..., \alpha_n)$

Given $L/K/\mathbb{Q}$, since α is in every prime of $\mathcal{O}_K$ lying over p, it certainly is in every prime in $\mathcal{O}_L$ lying over p. Fixing any $\mathfrak{B}$ of S lying over p, we see that for any automorphism σ_i, $\sigma(\alpha) \in \mathfrak{B}$. To see this ,$\sigma^{-1}(\alpha)$ is a prime of $\sigma^{-1}(S) = S$ lying over p, hence must contain α. In particular, this gives $\sigma_i(\alpha) \in \mathfrak{B}$ for all i. But then $\mathfrak{B}$ contains $\text{disc}(\alpha, \alpha_2, ..., \alpha_n)$. Since the discriminant is in $\mathbb{Z}$, we get that:

$$\mathfrak{B} \cap \mathbb{Z} = p\mathbb{Z}$$

but then $p \big| \text{disc}(\mathcal{O}_K)$, as we sought to show.

Corollary 50.4.13: Ramification Over Number Fields

Let $\alpha \in R$ so that $K = \mathbb{Q}(\alpha)$ and let f be a monic polynomial over $\mathbb{Z}$ such that $f(\alpha) = 0$. Then if p is a prime such that

$$p \not| \text{Nm} f'(\alpha)$$

Then p is unramified in K

***Proof*:**
This follows from the above an the fact that if α is an algebraic integer and $f \in \mathbb{Z}[x]$ monic such that $f(\alpha) = 0$, then by proposition 50.1.29:

$$\text{disc}(\alpha) \big| \text{Nm}_{\mathbb{Q}(\alpha)/\mathbb{Q}}(f'(\alpha))$$

Using this result, we have an easier verification for ramification of primes of $\mathbb{Z}$ to number fields, since they must divide the discriminant, but the discriminant may only have finitely many factors. In fact, it is easy to generalize this result for extension of number fields

Corollary 50.4.14: Ramification In Number Fields

Let L/K be an extension of number fields Then only finitely many primes of $\mathcal{O}_K$ are ramified in $\mathcal{O}_L$.

***Proof*:**
Let $\mathfrak{p}$ be a prime of $\mathcal{O}_K$ which is ramified in $\mathcal{O}_L$. Then $\mathfrak{p} \cap \mathbb{Z} = p\mathbb{Z}$ is ramified in S. Hence there are only finitely many possible primes p that ramify, meaning there are only finitely many possible $\mathfrak{p}$.

The converse is also true, namely

$$p \big| \operatorname{disc}(\mathcal{O}_K) \Leftrightarrow \text{ } p \text{ ramifies in } K$$

The full proof shall be given in greater generality in 50.4.3 where it is generalized for primes $\mathfrak{p} \subseteq \mathcal{O}_K$ being ramified in $\mathcal{O}_L$ for algebraic extension L/K. However, it is instructive for the reader to prove it in the following special case that is particularly important for the study of local fields (see [33]):

Lemma 50.4.15: Partial Converse For Ramification

Let $K = \mathbb{Q}(\alpha)$ where $\alpha \in \mathcal{O}_K$ and $p \nmid [\mathcal{O}_K : \mathbb{Z}[\alpha]]$. Then if $p \big| \operatorname{disc}(\mathcal{O}_K)$, p ramifies in K

***Proof*:**
Let $n = [K : \mathbb{Q}]$ and let $m \in \mathbb{Q}[x]$ be the minimal polynomial of α. Since α is a root of a monic $g \in \mathbb{Z}[x]$ and m divides g, every root of m in $\mathbb{C}$ is an algebraic integer. The coefficients of m are, up to sign, elementary symmetric polynomials in these roots, so they are rational algebraic integers (corollary 26.1.6), that is integers by lemma 50.1.5 and theorem 50.1.9(1). So $m \in \mathbb{Z}[x]$. Write its reduction modulo p as

$$\overline{m} = \overline{m}_1^{e_1} \cdots \overline{m}_r^{e_r}$$

with $\overline{m}_1, \ldots, \overline{m}_r$ distinct monic irreducible polynomials in $\mathbb{F}_p[x]$, and let $m_i \in \mathbb{Z}[x]$ be monic lifts of the $\overline{m}_i$. Since $p \nmid [\mathcal{O}_K : \mathbb{Z}[\alpha]]$, corollary 50.4.8, applied over the base field $\mathbb{Q}$ with $\theta = \alpha$ and this factorization (as in theorem 50.4.7), gives

$$p\mathcal{O}_K = \mathfrak{B}_1^{e_1} \cdots \mathfrak{B}_r^{e_r} \qquad \mathfrak{B}_i = p\mathcal{O}_K + m_i(\alpha)\mathcal{O}_K$$

with distinct prime ideals $\mathfrak{B}_1, \ldots, \mathfrak{B}_r$. We prove the contrapositive: if p is unramified in K, then $p \nmid d_K$. So assume p is unramified, which makes $e_1 = \cdots = e_r = 1$ by definition 50.4.10.

Step 1: membership in $\mathfrak{B}_i$. Consider the ring homomorphism $\varphi_i \colon \mathbb{Z}[x] \to \mathcal{O}_K/\mathfrak{B}_i$, $h \mapsto h(\alpha) + \mathfrak{B}_i$. Its kernel contains p and $m_i(x)$, because $p, m_i(\alpha) \in \mathfrak{B}_i$, and it is proper because $\mathfrak{B}_i \neq \mathcal{O}_K$. The composite $\mathbb{Z}[x] \to \mathbb{F}_p[x] \to \mathbb{F}_p[x]/(\overline{m}_i)$ of reduction modulo p and the quotient map is surjective with kernel $(p, m_i(x))$: if $\overline{h} = \overline{m}_i\overline{u}$ with $u \in \mathbb{Z}[x]$, then $h - m_i u \in p\mathbb{Z}[x]$. The ideal $(\overline{m}_i)$ is maximal in $\mathbb{F}_p[x]$, a principal ideal domain (corollary 11.1.2) in which the irreducible $\overline{m}_i$ is prime (proposition 10.1.33) and nonzero prime ideals are maximal (proposition 10.1.32). So $\mathbb{Z}[x]/(p, m_i(x)) \cong \mathbb{F}_p[x]/(\overline{m}_i)$ is a field, $(p, m_i(x))$ is a maximal ideal of $\mathbb{Z}[x]$ contained in the proper ideal $\ker \varphi_i$, and $\ker \varphi_i = (p, m_i(x))$. Hence, for $h \in \mathbb{Z}[x]$,

$$h(\alpha) \in \mathfrak{B}_i \iff h \in (p, m_i(x)) \iff \overline{m}_i \text{ divides } \overline{h} \text{ in } \mathbb{F}_p[x]$$

Step 2: $m'(\alpha)$ lies in no $\mathfrak{B}_i$. Suppose $m'(\alpha) \in \mathfrak{B}_i$. Reduction modulo p commutes with the formal derivative, so Step 1 shows that $\overline{m}_i$ divides $(\overline{m})'$. Since every $e_j = 1$, $\overline{m} = \overline{m}_i g$ with $g = \prod_{j \neq i} \overline{m}_j$, and $(\overline{m})' = \overline{m}_i' g + \overline{m}_i g'$, so $\overline{m}_i$ divides $\overline{m}_i' g$. The polynomial $\overline{m}_i$ is prime in $\mathbb{F}_p[x]$, and it does not divide g: otherwise it would divide some $\overline{m}_j$ with $j \neq i$, and two monic irreducibles dividing one another are equal. So $\overline{m}_i$ divides $\overline{m}_i'$, which has smaller degree, and $\overline{m}_i' = 0$. But $\mathbb{F}_p$ is perfect (corollary 19.6.12), so the irreducible $\overline{m}_i$ is separable (definition 19.6.10) and relatively prime to its derivative (proposition 19.6.6), which fails when $\overline{m}_i' = 0$, as $\deg \overline{m}_i \geq 1$. Hence $m'(\alpha) \notin \mathfrak{B}_i$ for every i.

Step 3: p does not divide $\mathrm{Nm}_{K/\mathbb{Q}}(m'(\alpha))$. The element $m'(\alpha)$ is nonzero, since $m' \neq 0$ has degree less than $n = \deg m$. Factor $m'(\alpha)\mathcal{O}_K = \prod_{\mathfrak{q}} \mathfrak{q}^{a_\mathfrak{q}}$ (theorem 50.2.15). By lemma 50.1.63, proposition 50.2.30 and lemma 50.2.29,

$$\left|\mathrm{Nm}_{K/\mathbb{Q}}(m'(\alpha))\right| = \mathfrak{N}(m'(\alpha)\mathcal{O}_K) = \prod_{\mathfrak{q}} \mathfrak{N}(\mathfrak{q})^{a_\mathfrak{q}}$$

where $\mathfrak{N}(\mathfrak{q})$ is a power of the prime q with $\mathfrak{q} \cap \mathbb{Z} = q\mathbb{Z}$. If p divided this product, some $\mathfrak{q}$ with $\mathfrak{q} \cap \mathbb{Z} = p\mathbb{Z}$ would have $a_\mathfrak{q} \geq 1$, that is $m'(\alpha) \in \mathfrak{q}$. Such a $\mathfrak{q}$ divides $p\mathcal{O}_K$ (proposition 50.3.11), so it is one of the $\mathfrak{B}_i$, contradicting Step 2.

Step 4: conclusion. Let $D = \mathrm{disc}_{K/\mathbb{Q}}(1, \alpha, \ldots, \alpha^{n-1})$. By proposition 50.1.29, applied to $K = \mathbb{Q}(\alpha)$, $D = (-1)^{n(n-1)/2}\mathrm{Nm}_{K/\mathbb{Q}}(m'(\alpha))$, so $p \nmid D$ by Step 3. The elements $1, \alpha, \ldots, \alpha^{n-1}$ are algebraic integers forming a $\mathbb{Q}$-basis of K and a $\mathbb{Z}$-basis of $\mathbb{Z}[\alpha]$, so $D\mathcal{O}_K \subseteq \mathbb{Z}[\alpha]$ by proposition 50.1.43, and $\mathbb{Z}[\alpha]$ has finite index in $\mathcal{O}_K$. By proposition 50.1.39, $D = [\mathcal{O}_K : \mathbb{Z}[\alpha]]^2 d_K$, so d_K divides D and $p \nmid d_K$. Hence if $p \mid d_K$, then p ramifies in K, as we sought to show.

For the result when *only* considering primes of $\mathbb{Z}$, the result is easier:

Proposition 50.4.16: Characterizing Ramification In Number Fields

Let p be a prime in $\mathbb{Z}$. Suppose $p \mid \mathrm{disc}(\mathcal{O}_K)$. Then p is ramified.

***Proof*:**
We prove the contrapositive: if p is unramified in K, then $p \nmid d_K$. Let $n = [K : \mathbb{Q}]$, let $\omega_1, \ldots, \omega_n$ be an integral basis of $\mathcal{O}_K$ (corollary 50.1.33), and let $A = \mathcal{O}_K / p\mathcal{O}_K$, with $\overline{u}$ the class of $u \in \mathcal{O}_K$.

Step 1: the trace form of A. Since $\mathcal{O}_K = \bigoplus_i \mathbb{Z}\omega_i$, the classes $\overline{\omega}_1, \ldots, \overline{\omega}_n$ form an $\mathbb{F}_p$-basis of A. For $x \in \mathcal{O}_K$, the matrix M_x of multiplication by x in the basis $\omega_1, \ldots, \omega_n$ has integer entries, because $x\omega_j \in \mathcal{O}_K$, and $\mathrm{tr}_{K/\mathbb{Q}}(x)$ is its trace (definition 50.1.10). The reduction of M_x modulo p is the matrix of the $\mathbb{F}_p$-linear map $A \to A$, $\overline{u} \mapsto \overline{xu}$, in the basis $\overline{\omega}_1, \ldots, \overline{\omega}_n$. Writing $\mathrm{tr}_A(\overline{x})$ for the trace of this map (definition 13.4.3), we get $\mathrm{tr}_A(\overline{x}) = \mathrm{tr}_{K/\mathbb{Q}}(x) \bmod p$. Let b be the symmetric $\mathbb{F}_p$-bilinear form $b(\overline{u}, \overline{v}) = \mathrm{tr}_A(\overline{uv})$ on A. Its matrix in the basis $\overline{\omega}_1, \ldots, \overline{\omega}_n$ is the reduction modulo p of $(\mathrm{tr}_{K/\mathbb{Q}}(\omega_i\omega_j))$, whose determinant is d_K by proposition 50.1.26 and definition 50.1.38. So $\mathrm{disc}(b) = d_K \bmod p$, and by proposition 50.1.23 the form b is nondegenerate if and only if $p \nmid d_K$.

Step 2: A is a product of finite fields. As p is unramified, $p\mathcal{O}_K = \mathfrak{B}_1 \cdots \mathfrak{B}_g$ with distinct prime ideals $\mathfrak{B}_i$ (definition 50.4.10). These are maximal (theorem 50.2.6), hence pairwise comaximal, and theorem 9.6.11 gives a ring isomorphism

$$\psi\colon A = \mathcal{O}_K/\mathfrak{B}_1 \cdots \mathfrak{B}_g \to F_1 \times \cdots \times F_g \qquad F_i = \mathcal{O}_K/\mathfrak{B}_i$$

which is $\mathbb{F}_p$-linear. Each F_i is a finite field containing $\mathbb{F}_p$ (lemma 50.2.29).

Step 3: b is nondegenerate. Let $\overline{u} \in A$ with $\psi(\overline{u}) = (u_1, \dots, u_g)$. Multiplication by $(u_1, \dots, u_g)$ on $F_1 \times \cdots \times F_g$ maps each factor F_i, embedded as the tuples vanishing outside the ith slot, into itself, and acts on it as multiplication by u_i. In an $\mathbb{F}_p$-basis made of $\mathbb{F}_p$-bases of the factors its matrix is therefore block diagonal, with blocks the matrices of multiplication by u_i on F_i. Since ψ carries multiplication by $\overline{u}$ to multiplication by $\psi(\overline{u})$, taking traces gives

$$\operatorname{tr}_A(\overline{u}) = \sum_{i=1}^{g} \operatorname{tr}_{F_i/\mathbb{F}_p}(u_i)$$

with $\operatorname{tr}_{F_i/\mathbb{F}_p}$ the trace of definition 19.6.30. Now suppose $b(\overline{u}, \overline{v}) = 0$ for every $\overline{v} \in A$. Fix i and $y \in F_i$, and let $\overline{v} \in A$ be the element with $\psi(\overline{v}) = (0, \dots, y, \dots, 0)$, the entry y in the ith slot. Then $\psi(\overline{uv}) = (0, \dots, u_i y, \dots, 0)$, and the display gives $\operatorname{tr}_{F_i/\mathbb{F}_p}(u_i y) = b(\overline{u}, \overline{v}) = 0$. The extension $F_i/\mathbb{F}_p$ is separable because $\mathbb{F}_p$ is perfect (corollary 19.6.12, definition 19.6.10), so its trace form is nondegenerate (proposition 19.6.31), and $u_i = 0$. This holds for every i, so $\overline{u} = 0$, and b is nondegenerate.

By Step 1, $p \nmid d_K$. Hence if $p \mid d_K$, then p is ramified, as we sought to show.

50.4.1 Example: Eisenstein Polynomials

We say a monic $f \in \mathbb{Z}[x]$ is *Eisenstein* with respect to p if p divides each coefficient other than the leading one but p^2 does not divide the constant coefficient. Then by Eisenstein's criterion (corollary 11.3.11), such a polynomial is irreducible in $\mathbb{Q}[x]$.

Lemma 50.4.17: Eisenstein Polynomial Modular Roots

Let $K/\mathbb{Q}$ be a number field of degree n and assume $K = \mathbb{Q}(\alpha)$ for $\alpha \in \mathcal{O}_K$ with minimal polynomial $m_{\alpha,\mathbb{Q}}$ Eisenstein at p. Then then for some $f(x) \in \mathbb{Z}[x]$ of degree at most $n-1$ with coefficients $a_0, a_1, ..., a_{n-1}$, if:

$$f(\alpha) \equiv 0 \bmod p\mathcal{O}_K$$

Then:

$$a_i \equiv 0 \bmod p\mathbb{Z} \qquad 1 \le i \le n-1$$

***Proof*:**
we shall do an argument by induction. Certainly if $a_0 \equiv 0 \bmod p\mathcal{O}_K$ then $a_0 \equiv 0 \bmod p\mathbb{Z}$ (since $a_0 \in \mathbb{Z}$). Thus, assume for $i < j$, $j \in \{0, 1, ..., n-1\}$ that $a_i \equiv 0 \bmod p\mathbb{Z}$. Then for $i < j$:

$$a_j\alpha^j + a_{j+1}\alpha^{j+1} + \cdots + a_{n-1}\alpha^{n-1} \equiv \bmod p\mathcal{O}_K$$

Multiply the above by α^{n-1-j} to make all but the first term $a_j\alpha^{n-1}$ a multiple of α^n. Since α is a root of an Eisenstein polynomial at p, we have

$$\alpha^n \equiv 0 \bmod p\mathcal{O}_K$$

Hence:

$$a_j\alpha^{n-1} \equiv p\mathcal{O}_K$$

Then $a_j\alpha^{n-1} = p\gamma$, for $\gamma \in \mathcal{O}_K$. Taking the norm, we get:

$$a_j^n \mathrm{Nm}_{K/\mathbb{Q}}(\alpha)^{n-1} = p^n \mathrm{Nm}_{K/\mathbb{Q}}(\gamma) \in \mathbb{Z}$$

the left hand side is divisible by the constant term of the minimal polynomial (since that is the value of $\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)$). By Eisenstein, p divides $\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)$ exactly once, so since p^n must divide the left hand side gives that $p \big| a_j^n$, thus $p \big| a_j$, thus $a_i \equiv 0 \bmod p\mathbb{Z}$ for $i < j+1$, giving us the result.

Lemma 50.4.18: Eisenstein Polynomial divisibility by p

Let $K/\mathbb{Q}$ be a number field of degree n, $K = \mathbb{Q}(\alpha)$ where $\alpha \in \mathcal{O}_K$ with minimal polynomial Eisenstein at p. Then if

$$r_0 + r_1\alpha + \cdots + r_{n-1}\alpha^{n-1} \in \mathcal{O}_K \qquad r_i \in \mathbb{Q}$$

then each r_i has no p in its denominator

***Proof*:**
For the sake of contradiction, assume some r_i has a p in its denominator. Let d be the lcm of the denominators so the r_i's so $p \big| d$ so that we may write $r_i = a_i/d$ for appropriate $a_i \in \mathbb{Z}$ where $a_i \nmid p$. Then:

$$r_0 + r_1\alpha + \cdots + r_{n-1}\alpha^{n-1} \in \mathcal{O}_K \implies \frac{a_0 + a_1\alpha + \cdots + a_{n-1}\alpha^{n-1}}{d} \in \mathcal{O}_K$$

multiplying by d,w e get:

$$a_0 + a_1\alpha + \cdots + a_{n-1}\alpha^{n-1} \in d\mathcal{O}_K \subseteq p\mathcal{O}_K$$

Then by lemma 50.4.17 we have that $a_i \in p\mathbb{Z}$ for each i, a contradiction!

Theorem 50.4.19: Eisenstein Polynomial Divisibility Test

Let $K = \mathbb{Q}(\alpha)$ where $\alpha \in \mathcal{O}_K$ a root of an Eisenstain polnomial at p of degree n. Then:

$$p \nmid [\mathcal{O}_K : \mathbb{Z}[\alpha]]$$

***Proof*:**

For the sake of contradiction, suppose $p|[\mathcal{O}_K : \mathbb{Z}[\alpha]]$. Then $\mathcal{O}_K/\mathbb{Z}[\alpha]$ has an element of order p, that is there is some $\gamma \in \mathcal{O}_K$ such that $\gamma \notin \mathbb{Z}[\alpha]$ but $p\gamma \in \mathbb{Z}[\alpha]$. Now, given basis $\{1, \alpha, ..., \alpha^{n-1}\}$ for $K/\mathbb{Q}$, then

$$\gamma = r_0 + r_1\alpha + \cdots + r_{n-1}\alpha^{n-1}$$

where $r_i \in \mathbb{Q}$. Since $\gamma \notin \mathbb{Z}[\alpha]<$ not all $r_i \in \mathbb{Z}>$ Since $p\gamma \in \mathbb{Z}[\alpha]$, $pr_i \in \mathbb{Z}$. Thus, r_i has p in its denominator, but that contradicts lemma 50.4.18, as we sought to show.

Example 50.4.20: Using Eisenstein Test

1. Let $K = \mathbb{Q}(\sqrt[3]{2})$. We shall quickly find $\mathcal{O}_K$. Recall that:

   $$-2^2 3^3 = -108 = \text{disc}(\mathbb{Z}[\sqrt[3]{2}]) = [\mathcal{O}_K : \mathbb{Z}[\sqrt[3]{2}]]^2 \text{disc}(\mathcal{O}_K)$$

   Since $\sqrt[3]{2}$ is a root of $x^3 - 2$, which is eisenstien at 2, we see that $2 \nmid [\mathcal{O}_K : \mathbb{Z}[\sqrt[3]{2}]]$. Furthermore, $1 + \sqrt[3]{2}$ is the root of

   $$(x-1)^3 - 2 = x^3 - 3x^2 + 3x - 3$$

   which is eisenstein at 3 s o

   $$3 \nmid [\mathcal{O}_K : \mathbb{Z}[1 + \sqrt[3]{2}]] = [\mathcal{O}_K : \mathbb{Z}[\sqrt[3]{2}]$$

   since $\mathbb{Z}[\sqrt[3]{2}] = \mathbb{Z}[1 + \sqrt[3]{2}]$. THus, the index must be 1, giving us:

   $$\mathcal{O}_K = \mathbb{Z}[\sqrt[3]{2}]$$

2. Let $K = \mathbb{Q}(\sqrt[4]{2})$. Then:

   $$-2^{11} = \text{disc}(\mathbb{Z}[\sqrt[4]{2}]) = [\mathcal{O}_K : \mathbb{Z}[\sqrt[4]{2}]]^2 \text{disc}(\mathcal{O}_K)$$

   and $\sqrt[4]{2}$ is a root of $x^4 - 2$ which is eisenstein at 2, hence by the eisenstein divisibility test the idnex is 1 and

   $$\mathcal{O}_K = \mathbb{Z}[\sqrt[4]{2}]$$

   Let $K = \mathbb{Q}(\sqrt[5]{2})$. Then

   $$2^4 \cdot 5^5 = \text{disc}(\mathbb{Z}[\sqrt[5]{2}]) = [\mathcal{O}_K : \mathbb{Z}[\sqrt[5]{2}]]^2 \text{disc}(\mathcal{O}_K)$$

   Certainly 2 does not divide the index. Next, the minimal polynomial of $\sqrt[5]{2} - 2$ is

   $$(x+2)^5 - 2 = x^5 + 10x^4 + 40x^3 + 80x^2 + 80x + 30$$

   which is Eisenstein at 5 and $\mathbb{Z}[\sqrt[5]{2} - 2] = \mathbb{Z}[\sqrt[5]{2}]$ Hence:

   $$\mathcal{O}_K = \mathbb{Z}[\sqrt[5]{2}]$$

3. show that $\mathcal{O}_{\mathbb{Q}(\sqrt[3]{3})} = \mathbb{Z}[\sqrt[3]{3}]$ and $\mathcal{O}_{\mathbb{Q}(\sqrt[3]{5})} = \mathbb{Z}[\sqrt[3]{5}]$.
4. Recall the three cubic extensison K_1, K_2, K_3 in example 50.1.42 with the same discriminant, but it was claimed that they where not isomorphic as fields. The three polynomials in question where:

$$f_1(x) = x^3 - 18x - 6 \qquad f_2(x) = x^3 - 36x - 78 \qquad f_3(x) = x^3 - 54x - 150$$

each having discriminant $22345 = 5 \cdot 41 \cdot 109$. It can be verified that these three polynomials have real roots (by either graphing or doing some guess-work with derivative test and evaluating), and from the above methods we can check that

$$\mathcal{O}_{K_i} = \mathbb{Z}[\alpha_i]$$

for appropriate root α_i. Since the ring of integers is Monogenic, by Dedekind-Kummers theorem the factorization of primes p mirrors the factorization of $f_i(x)$ mod p. Then it can be verified that

(a) f_1, f_2 are irreducible mod 5, but

$$f_3(x) \equiv x(x-2)(x-3) \bmod 5$$

(b) f_2, f_3 are irreducible mod 11, but

$$f_1(x) \equiv (x-3)(x-9)(x-10) \bmod 11$$

Thus, we see that these fields cannot be isomorphic, or else the prime factorization would have been equivalent (recall that ring homomorphisms map primes to primes)

It may be asked if $K = \mathbb{Q}(\sqrt[n]{2})$

$$\mathcal{O}_K = \mathbb{Z}[\sqrt[n]{2}]$$

This is true for $n \leq 1000$, but is *not always true*. For those interested, they may search for *Wieferich primes* (see Keith Conrad *The ring of integers in radical extensions*).

Eisenstein polynomials also allow us to identify when a polynomial totally ramifies:

Theorem 50.4.21: Eisenstein Polynomial And Total Ramification

Let K be a number field of degree n and p a prime number. Then p is totally ramified in K, that is $p\mathcal{O}_K = \mathfrak{B}^n$ for a prime ideal $\mathfrak{B}$ of $\mathcal{O}_K$, if and only if $K = \mathbb{Q}(\alpha)$ for some α that is a root of a polynomial in $\mathbb{Z}[x]$ which is Eisenstein at p.

Note how there is no reference to the ring of integers

***Proof*:**
Step 1: an Eisenstein generator makes p totally ramified. Suppose $K = \mathbb{Q}(\alpha)$ with $f(\alpha) = 0$ for $f = x^m + a_{m-1}x^{m-1} + \cdots + a_0$ in $\mathbb{Z}[x]$ Eisenstein at p. By corollary 11.3.11, f is irreducible over $\mathbb{Q}$, so it is the minimal polynomial of α and $m = [\mathbb{Q}(\alpha) : \mathbb{Q}] = n$. As f is monic with integer

coefficients, $\alpha \in \mathcal{O}_K$ (definition 50.1.3), and

$$\alpha^n = -\left(a_{n-1}\alpha^{n-1} + \cdots + a_1\alpha + a_0\right) \in p\mathcal{O}_K$$

because p divides every a_i. The ideal $p\mathcal{O}_K$ is proper, as $1/p \notin \mathcal{O}_K$ by theorem 50.1.9(1), so it has prime factors $\mathfrak{B}_1, \ldots, \mathfrak{B}_g$ with $g \geq 1$ (theorem 50.2.15). These are the primes $\mathfrak{q}$ of $\mathcal{O}_K$ with $\mathfrak{q} \cap \mathbb{Z} = p\mathbb{Z}$ (proposition 50.3.11). Each $\mathfrak{B}_i$ contains α^n, hence α, being prime.

By proposition 50.1.12 with $M = \mathbb{Q}(\alpha) = K$, $\mathrm{Nm}_{K/\mathbb{Q}}(\alpha)$ is the product of the roots of f, which is $(-1)^n a_0$. So $\mathfrak{N}(\alpha\mathcal{O}_K) = |a_0|$ by lemma 50.1.63, and p divides $|a_0|$ exactly once, since $p \big| a_0$ and $p^2 \nmid a_0$. Factor $\alpha\mathcal{O}_K = \prod_{\mathfrak{q}} \mathfrak{q}^{v_{\mathfrak{q}}}$ (theorem 50.2.15). By proposition 50.2.30 and lemma 50.2.29,

$$|a_0| = \prod_{\mathfrak{q}} \mathfrak{N}(\mathfrak{q})^{v_{\mathfrak{q}}} = \prod_{\mathfrak{q}} q_{\mathfrak{q}}^{f_{\mathfrak{q}} v_{\mathfrak{q}}}$$

where $\mathfrak{q} \cap \mathbb{Z} = q_{\mathfrak{q}}\mathbb{Z}$ and $f_{\mathfrak{q}} = [\mathcal{O}_K/\mathfrak{q} : \mathbb{F}_{q_{\mathfrak{q}}}] \geq 1$. Comparing the exponents of p on both sides gives

$$1 = \sum_{i=1}^{g} f_{\mathfrak{B}_i} v_{\mathfrak{B}_i}$$

Each $v_{\mathfrak{B}_i} \geq 1$, because $\alpha \in \mathfrak{B}_i$ means that $\mathfrak{B}_i$ divides $\alpha\mathcal{O}_K$ (corollary 50.2.18). So $g = 1$ and $f_{\mathfrak{B}_1} = 1$. Writing $p\mathcal{O}_K = \mathfrak{B}_1^e$, the fundamental identity (proposition 50.4.3) gives $e = n$, so $p\mathcal{O}_K = \mathfrak{B}_1^n$.

Step 2: a totally ramified prime gives an Eisenstein generator. Suppose $p\mathcal{O}_K = \mathfrak{B}^n$. By proposition 50.4.3, $n\, f(\mathfrak{B}/p) = n$, so $f(\mathfrak{B}/p) = 1$ and $\mathfrak{N}(\mathfrak{B}) = p$ (lemma 50.2.29). Moreover $\mathfrak{B}$ is the only prime of $\mathcal{O}_K$ containing p (proposition 50.3.11). Since $\mathfrak{B} \neq \mathfrak{B}^2$ (theorem 50.2.15), choose $\pi \in \mathfrak{B} \setminus \mathfrak{B}^2$. Then $\mathfrak{B}$ divides $\pi\mathcal{O}_K$ while $\mathfrak{B}^2$ does not, so $\pi\mathcal{O}_K = \mathfrak{B}\mathfrak{a}$ with $\mathfrak{B} \nmid \mathfrak{a}$. Every prime factor of $\mathfrak{a}$ differs from $\mathfrak{B}$, so it does not contain p, and its absolute norm is a power of a prime different from p (lemma 50.2.29). By lemma 50.1.63 and proposition 50.2.30,

$$\left|\mathrm{Nm}_{K/\mathbb{Q}}(\pi)\right| = \mathfrak{N}(\mathfrak{B})\mathfrak{N}(\mathfrak{a}) = p\,\mathfrak{N}(\mathfrak{a})$$

with $p \nmid \mathfrak{N}(\mathfrak{a})$, so p divides $\mathrm{Nm}_{K/\mathbb{Q}}(\pi)$ exactly once.

Let $\omega_1, \ldots, \omega_n$ be an integral basis (corollary 50.1.33), let $M \in M_n(\mathbb{Z})$ be the matrix of multiplication by π in this basis, and let $\chi(x) = \det(xI - M) \in \mathbb{Z}[x]$. By proposition 13.5.2, χ is monic of degree n with constant term $(-1)^n \det(M) = (-1)^n \mathrm{Nm}_{K/\mathbb{Q}}(\pi)$ (definition 50.1.10). The classes of the ω_i form an $\mathbb{F}_p$-basis of $\mathcal{O}_K/p\mathcal{O}_K$, in which the reduction $\overline{M}$ of M modulo p is the matrix of multiplication by the class of π. The determinant is a polynomial in the entries, so the reduction $\overline{\chi}$ of χ is $\det(xI - \overline{M})$, computed in the commutative ring $\mathbb{F}_p[x]$. Since $\pi^n \in \mathfrak{B}^n = p\mathcal{O}_K$, we have $\overline{M}^n = 0$, and the matrices xI and $\overline{M}$ commute, so

$$(xI - \overline{M})\left(x^{n-1}I + x^{n-2}\overline{M} + \cdots + \overline{M}^{n-1}\right) = x^n I - \overline{M}^n = x^n I$$

Taking determinants (proposition 13.4.7) shows that $\overline{\chi}$ divides x^{n^2} in $\mathbb{F}_p[x]$. This ring is a unique factorization domain (corollary 11.1.2) in which x is irreducible, so the monic divisor $\overline{\chi}$ of x^{n^2}

is a power of x, and $\overline{\chi} = x^n$ as it has degree n. Hence every coefficient of χ other than the leading one is divisible by p, while the constant term $\pm \mathrm{Nm}_{K/\mathbb{Q}}(\pi)$ is not divisible by p^2. So χ is Eisenstein at p, and irreducible over $\mathbb{Q}$ by corollary 11.3.11.

Finally, by proposition 14.3.10 the minimal polynomial of M divides χ, so $\chi(M) = 0$. Sending $\beta \in K$ to the matrix of multiplication by β is a ring homomorphism $K \to M_n(\mathbb{Q})$, so $\chi(M)$ is the matrix of multiplication by $\chi(\pi)$, and $\chi(\pi) = \chi(\pi) \cdot 1 = 0$. Thus π is a root of the irreducible polynomial χ of degree n, so $[\mathbb{Q}(\pi) : \mathbb{Q}] = n = [K : \mathbb{Q}]$ and $K = \mathbb{Q}(\pi)$, completing the proof.

Example 50.4.22: Dececting Ramification Using Eisenstein

Since $\alpha = \sqrt[3]{10}$ is a root of $x^3 - 10$, which is eisenstein at 2 and 5, then in $K = \mathbb{Q}(\alpha)$, $(2) = \mathfrak{p}^3$ and $(5) = \mathfrak{q}^3$. Note however htat

$$\mathcal{O}_K \neq \mathbb{Z}[\sqrt[3]{10}]$$

It is in fact equal to

$$\mathcal{O}_K = \mathbb{Z}[\beta] \qquad \beta = \frac{1}{3}\left(1 + \sqrt[3]{1-} + \sqrt[3]{100}\right)$$

which is a root of $x^3 - x^2 - 3x - 3$.

50.4.2 Primes in Galois Extensions

The question of prime decomposition in extension becomes more interesting when L/K is also a Galois extension since $\mathrm{Gal}_K(L)$ can act on the set of primes.

Lemma 50.4.23: Galois Group Acts On Primes

Let L/K be a finite galois extension with galois group $G = \mathrm{Gal}_K(L)$, $\mathfrak{p} \subseteq \mathcal{O}_K$ a prime ideal of $\mathcal{O}_K$, and $\mathfrak{P} = \{\mathfrak{B}_1, \mathfrak{B}_2, ..., \mathfrak{B}_n\}$ the set of primes lying above $\mathfrak{p}$. Then:

$$G \curvearrowright \mathfrak{P} \qquad \text{via} \qquad \sigma \cdot \mathfrak{B}_i = \sigma(\mathfrak{B}_i)$$

***Proof*:**

let $G = \mathrm{Gal}_K(L)$. Then for each $a \in \mathcal{O}_L$, $\tau(a) \in \mathcal{O}_L$ for all $\tau \in G$ since K is invariant under τ and all conjugates have an integral minimal polynomial (i.e. the same minimal polynomial with coefficients in $\mathbb{Z} \subseteq K$), so there is a natural action of G on $\mathcal{O}_L$. Here $G \curvearrowright \mathcal{O}_L$. Next, given that τ is a field isomorphism, $\tau : \mathcal{O}_L \to \mathcal{O}_L$ is a ring isomorphism, importantly it sends primes to primes. If $\mathfrak{B}$ is a prime ideal of $\mathcal{O}_L$ above $\mathfrak{p}$, then $\tau(\mathfrak{B})$ is also a prime ideal above $\mathfrak{p}$ for each prime $\mathfrak{B}$ since

$$(\tau(\mathfrak{B})) \cap \mathcal{O}_K = \tau(\mathfrak{B} \cap \mathcal{O}_K) = \tau(\mathfrak{p}) = \mathfrak{p}$$

since τ is K-invariant, hence $\mathcal{O}_K \subseteq K$ is invariant.

Definition 50.4.24: Prime Ideal Conjugate

Let $\mathcal{O}_L/\mathcal{O}_K$ be an extension of rings of integers where L/K is Galois, and $\mathfrak{B}$ lie above $\mathfrak{p}$. An ideal $\tau(\mathfrak{B})$ is called a *prime ideal conjugate* to $\mathfrak{B}$.

As we saw, most primes split similarly to a minimal polynomial. The following is further parallel between prime numbers and polynomials: just like conjugate elements, the Galois group acts transitively:

Proposition 50.4.25: Galois Group Transitive Action On Ideals

Let $G = \text{Gal}_K(L)$. Then G acts transitively on the set of all ideal $\mathfrak{B}$ of $\mathcal{O}$ lying above $\mathfrak{p}$, that is the prime ideals are all conjugates of each other.

***Proof*:**
Say $\mathfrak{B}, \mathfrak{B}'$ are two primes ideals lying above $\mathfrak{p}$ where, for the sake of contradiction, $\sigma(\mathfrak{B}) \neq \mathfrak{B}'$ for any $\sigma \in G$. By the CRT, there exists an $x \in \mathcal{O}$ such that

$$x \equiv 0 \bmod \mathfrak{B}' \qquad x \equiv 1 \bmod \sigma(\mathfrak{B}) \qquad \forall \sigma \in G$$

Then

$$\text{Nm}_{L/K}(x) = \prod_{\sigma \in G} \sigma(x) \overset{!}{\in} \mathfrak{B}' \cap \mathcal{O}_K = \mathfrak{p}$$

On the other hand, $x \notin \sigma(\mathfrak{B})$ for all $\sigma \in G$, hence $\sigma(x) \notin \mathfrak{B}$ for all $\sigma \in G$ since if $\sigma(x) = b \in \mathfrak{B}$, then $x = \sigma^{-1}(b) = \tau(b)$ for some $\tau \in G$. Thus,

$$\prod_{\sigma \in G} \sigma(x) \overset{!}{\notin} \mathfrak{B} \cap \mathcal{O}_K = \mathfrak{p}$$

Hence, $\prod_{\sigma \in G} \sigma(x)$ is both in and not in $\mathfrak{p}$, a contradiction.

Using the Galois group, we may encode in group-theoretic terms the number of different primes ideals a prime ideal $\mathfrak{p} \subseteq \mathcal{O}_K$ decompose to in $\mathcal{O}_L$. One of the properties of an element being acted on by a [transitive] group is it *stabalizer*:

Definition 50.4.26: Decomposition Group And Field

Let $G = \text{Gal}_K(L)$. Let $\mathfrak{B} \subseteq \mathcal{O}$ be a prime ideal. Then the subgroup

$$D_{\mathfrak{B}/\mathfrak{p}} = D_{\mathfrak{B}} = \{\tau \in G \mid \tau(\mathfrak{B}) = \mathfrak{B}\} = \text{stab}_G(\mathfrak{B})$$

is called the *decomposition group* of $\mathfrak{B}$ over K. The fixed field

$$L^{D_{\mathfrak{B}}} = \{x \in L \mid \tau(x) = x \ \forall \tau \in G_{\mathfrak{B}}\}$$

is called the *decomposition field* of $\mathfrak{B}$ over K, and is often labeled as $L_{\mathfrak{B}}$ or $L_{\mathfrak{B}}$ if unambiguous.

Notice that the less primes that are fixed, the larger the decomposition field is, hence there is a

contravariant relation between the size of the group and the extension of the field, just like in Galois theory. Due to transitivity and the introduction of Galois theory, we immediately get many counting arguments. If $\mathfrak{B}$ is a prime ideal lying over $\mathfrak{p}$, and we let σ vary over a set of representatives from the cosets in $G/D_{\mathfrak{B}}$, then by transitivity $\sigma(\mathfrak{B})$ varies over the different primes ideals above $\mathfrak{p}$, each occurring exactly once, hence the number of prime ideals is equal to the index $[G : D_{\mathfrak{B}}]$. For reference, we shall write:

Definition 50.4.27: Prime Counter

Let L/K Then the number of prime numbers is equal to:

$$g_{L/K}(\mathfrak{p}) = [G : D_{\mathfrak{B}}]$$

for any prime $\mathfrak{B}$ over $\mathfrak{p}$. If clear from context, we shall write $g(\mathfrak{p})$.

Thus, if $D_{\mathfrak{B}} = 1$, then no $\sigma \in G$ fixes $\mathfrak{B}$ unless it's the identity and $[G : D_{\mathfrak{B}}] = |G| = [L : K]$, and so by the fundamental identity (proposition 50.4.3):

$$D_{\mathfrak{B}} = 1 \quad \iff \quad L_D = L \quad \iff \quad \mathfrak{p} \text{ totally splits}$$

On the other hand, if $D_{\mathfrak{B}} = G$, then every $\mathfrak{B}$ lying over $\mathfrak{p}$ is fixed by σ, and so there must only be one prime ideal above $\mathfrak{p}$ by transitivity giving:

$$D_{\mathfrak{B}} = G \quad \iff \quad L_D = K \quad \iff \quad \mathfrak{p} \text{ is indecomposable}$$

If $1 \subsetneq D_{\mathfrak{B}} \subsetneq G$, there is ambiguity on how $\mathfrak{p}$ splits. For example, if $[L : K] = 50 = 2 \cdot 5^2$ and $|G/D_{\mathfrak{B}}| = 5$, then either

$$\mathfrak{p}\mathcal{O}_L = \mathfrak{B}_1^2\mathfrak{B}_2^2\mathfrak{B}_3^2\mathfrak{B}_4^2\mathfrak{B}_5^2 \qquad \text{or} \qquad \mathfrak{p}\mathcal{O}_L = \mathfrak{B}_1^5\mathfrak{B}_2^5\mathfrak{B}_3^5\mathfrak{B}_4^5\mathfrak{B}_5^5$$

depending on whether the inertia degree is 5 or 2 respectively. The distinction between the two shall be given with the inertia group in proposition 50.4.37. Choosing a different prime does change the resulting index: if we were to choose a different prime $\mathfrak{B}$ lying over $\mathfrak{p}$, then $D_{\mathfrak{B}}$ is conjugate to $D_{\sigma(\mathfrak{B})}$:

$$D_{\sigma(\mathfrak{B})} = \sigma D_{\mathfrak{B}} \sigma^{-1}$$

In particular:

$$\begin{aligned} \tau \in D_{\sigma(\mathfrak{B})} &\iff \tau\sigma\mathfrak{B} = \sigma\mathfrak{B} \\ &\iff \sigma^{-1}\tau\sigma\mathfrak{B} = \mathfrak{B} \\ &\iff \sigma^{-1}\tau\sigma \in D_{\mathfrak{B}} \\ &\iff \tau \in \sigma D_{\mathfrak{B}} \sigma^{-1} \end{aligned}$$

This should make sense, for by the proceeding theorem, the inertia and ramification of each prime lying ove $\mathfrak{p}$ in a galois extension is equal. At the end of this section, we shall show how to partially recover these results when working over non-Galois extensions. A key result when working with Galois extensions is that each prime has the same behavior in it's decomposition:

Proposition 50.4.28: Galois Extension, Inertia Degree And Ramification Index Independent

Let $\mathfrak{p} \subseteq K$ be a prime ideal, L/K a Galois extension, and

$$\mathfrak{p}\mathcal{O}_L = \mathfrak{B}_1^{e_i} \cdots \mathfrak{B}_r^{e_r}$$

Then

$$f_1 = \cdots = f_r = f \qquad e_1 = \cdots = e_r = e$$

***Proof*:**
Let $\mathfrak{B} = \mathfrak{B}_1$ and $\mathfrak{B}_i = \sigma_i(\mathfrak{B})$ (which goes through all primes by transitivity). Then the isomorphism $\sigma_i : \mathcal{O}_L \to \mathcal{O}_L$ induces an isomorphism:

$$\mathcal{O}_L/\mathfrak{B} \xrightarrow{\sim} \mathcal{O}_L/\mathfrak{B}_i \qquad a \bmod \mathfrak{B} \mapsto \sigma_i(a) \bmod \sigma_i(\mathfrak{B})$$

But then:

$$f_i = [\mathcal{O}_L/\sigma_i(\mathfrak{B}) : \mathcal{O}_K/\mathfrak{p}] = [\mathcal{O}_L/\mathfrak{B} : \mathcal{O}_K/\mathfrak{p}]$$

Next, since $\sigma_i(\mathfrak{p}\mathcal{O}_L) = \mathfrak{p}\mathcal{O}_L$ (since $\mathfrak{p} \subseteq K$), we get

$$\mathfrak{B}^n \big| \mathfrak{p}\mathcal{O} \iff \sigma_i(\mathfrak{B}^n) \big| \sigma_i(\mathfrak{p}\mathcal{O}) \iff (\sigma_i(\mathfrak{B}))^n \big| \mathfrak{p}\mathcal{O}$$

showing that $e_1 = \cdots = e_r$.

Hence, the prime decomposition of $\mathfrak{p}$ can be written as :

$$\mathfrak{p} = \left(\prod_{\substack{\sigma \in S \\ S \subseteq G/D_{\mathfrak{B}}}} \sigma(\mathfrak{B}) \right)^e$$


where $S \subseteq G/D_{\mathfrak{B}}$ represents a set of representatives of $G/D_{\mathfrak{B}}$ and $|S| = g_{L/K}(\mathfrak{p})$. This information is already very powerful, the following is a use-case of such information:

Example 50.4.29: Biquadratic Extension That Is Not Monogenic

Let $K = \mathbb{Q}(\sqrt{7}, \sqrt{13})$. Without computing $\mathcal{O}_K$, it can be shown that $\mathcal{O}_K$ is *not* monogenic, that is there does not exists $\alpha \in \mathcal{O}_K$ such that $1, \alpha, \alpha^2, \alpha^3$ generates $\mathcal{O}_K$, in other words $\mathcal{O}_K$ is not isomorphic to a quotient of $\mathbb{Z}[x]$. The key is to look at the behavior of factorizations of small primes (for they can only have so many rood $\bmod p$)

What we shall do is consider the factorization of (3) in $\mathcal{O}_K$, which will be our setup for a

contradiction. First, notice that K has 3 intermediary fields[a]:



Since we know the ring of integers of quadratics, by direct computation, we see that (3) splits into two primes in each quadratic extension. For example, in $\mathbb{Q}(\sqrt{7})$, we have:

$$\mathcal{O}_{\mathbb{Q}(\sqrt{7})}/3\mathcal{O}_{\mathbb{Q}(\sqrt{7})} = \frac{\mathbb{F}_3[x]}{(x-1)(x+1)}$$

Hence:

$$(3) = (3, 1+\sqrt{7})(3, 1-\sqrt{7})$$

Doing a similar computation for the other two computation, we get:

$$(3) = (3, 1+\sqrt{13})(3, 1-\sqrt{13})$$
$$(3) = (3, 1+\sqrt{91})(3, 1-\sqrt{91})$$

Thus, over K, there must be at least 2 prime ideals, and since

$$g_{K/\mathbb{Q}}(3) = [G : D_{\mathfrak{B}}] \qquad [G : D_{\mathfrak{B}}] \mid |\mathrm{Gal}_{\mathbb{Q}}(K)| \qquad |\mathrm{Gal}_{\mathbb{Q}}(K)| = |(\mathbb{Z}/2\mathbb{Z})^2| = 4$$

for any prime ideal $\mathfrak{B}$ over (3), we get that $g_{K/\mathbb{Q}}(3)|4$. I claim that $g_{K/\mathbb{Q}}(3) = 4$. For, if $g_{K/\mathbb{Q}}(3) = 2$, then for any of the two primes lying over (3) in $\mathcal{O}_K$, say $\mathfrak{B}$:

$$\{e\} \neq D_{\mathfrak{B}} = \{\sigma \in \mathrm{Gal}_{\mathbb{Q}}(K) \mid \sigma(\mathfrak{B}) = \mathfrak{B}\} \subsetneq \mathrm{Gal}_{\mathbb{Q}}(K)$$

Since $D_{\mathfrak{B}}$ non-trivial proper subgroup acting transitively on the two primes of K lying over (3), we have $|D_{\mathfrak{B}}| = 2$, implying there is one non-trivial automorphism $\rho \in \mathrm{Gal}_{\mathbb{Q}}(K)$ fixing the prime ideals (since there are two prime ideals, if $\rho(\mathfrak{B}) = \mathfrak{B}$, then $\rho(\mathfrak{B}') = \mathfrak{B}'$, or else ρ would not be bijective), and two non-trivial automorphisms σ, τ not fixing the primes. Consider now $\sigma \in \mathrm{Gal}_{\mathbb{Q}}(K)$ and take the fixed field $K^{\langle\sigma\rangle}$, which by some Galois theory we see must be one of the 3 quadratic extensions found above. Then by the 3rd fundamental theorem of Galois theory:

$$G := \mathrm{Gal}_{\mathbb{Q}}(K^{\langle\sigma\rangle}) \cong \frac{\mathrm{Gal}_{\mathbb{Q}}(K)}{\mathrm{Gal}_{K^{\langle\sigma\rangle}}(K)}$$

Importantly, since $G \cong \mathbb{Z}/2\mathbb{Z}$ and $[\sigma] = [\mathrm{id}]$, the map $\varphi : \mathrm{Gal}_{\mathbb{Q}}(K) \to \mathrm{Gal}_{\mathbb{Q}}(K^{\langle\sigma\rangle})$ maps $\rho, \tau \mapsto \rho|_{K^{\langle\sigma\rangle}}$. Since ρ is an automorphism and fixes both prime ideals in K over (3) (say $\mathfrak{B}, \mathfrak{B}'$), and all prime ideal of $K^{\langle\sigma\rangle}$ over (3) lie below $\mathfrak{B}, \mathfrak{B}'$:

$$\rho|_{K^{\langle\sigma\rangle}}(\mathfrak{B} \cap K^{\langle\sigma\rangle}) = \rho|_{K^{\langle\sigma\rangle}}(\mathfrak{B}) \cap K^{\langle\sigma\rangle} = \mathfrak{B} \cap K^{\langle\sigma\rangle}$$
$$\rho|_{K^{\langle\sigma\rangle}}(\mathfrak{B}' \cap K^{\langle\sigma\rangle}) = \rho|_{K^{\langle\sigma\rangle}}(\mathfrak{B}') \cap K^{\langle\sigma\rangle} = \mathfrak{B}' \cap K^{\langle\sigma\rangle}$$

Hence, G fixes all primes. But we saw that all intermediate fields of K have two primes, thus this contradicts the transitivity of action of the Galois group on the prime ideals. Thus, it must be that $g_{K/\mathbb{Q}}(3) = 4$.

Now, for the sake of contradiction let's say

$$\mathcal{O}_K \cong \frac{\mathbb{Z}[x]}{m_\alpha(x)}$$

for some $\alpha \in \mathcal{O}_K$ and minimal polynomial $m_\alpha(x)$ of degree 4. Then

$$\mathcal{O}_K/3\mathcal{O}_K \cong \frac{\mathbb{F}_3[x]}{(m_\alpha(x) \bmod 3)} \tag{50.4}$$

By our previous calculations, we see that there must be 4 prime ideals in the right hand side. Decomposing $m_\alpha(x)$ mod 3 into irreducible, by the CRT we get that the right hand side is isomorphic to the direct sum of $\mathbb{F}_3[x]/(m_i(x) \bmod 3)$ for each irreducible $m_i(x)$ mod 3. Since each $m_i(x)$ mod 3 is irreducible, each direct summand is a field, and hence by some ring theory we see that the number of primes on the right hand side of equation 50.4 is equal to the number of direct summands, implying $m_\alpha(x)$ splits into linear factors giving us:

$$\frac{\mathbb{F}_3[x]}{(m_\alpha(x) \bmod 3)} \cong \bigoplus_i^4 \mathbb{F}_3$$

However, this is impossible: any degree 4 polynomial over $\mathbb{F}_3$ that breaks down into linear factors has the form:

$$(x-1)^\alpha (x+1)^\beta x^\gamma$$

where one of α, β, γ is 2 and the other two are 1. But then $\mathbb{F}_3[x]/((x-1)^\alpha(x+1)^\beta x^\gamma)$ is not isomorphic to $\bigoplus_i^4 \mathbb{F}_3$ (the quotient contains nilpotent elements), showing that our assumption that $\mathcal{O}_K$ is monogenic is not possible.

[a] this can be seen by taking the fixed fields $\sqrt{7}, \sqrt{13}$, and $\sqrt{91}$, corresponding to the subgroups of $\mathrm{Gal}_{\mathbb{Q}}(K) = \mathbb{Z}_2 \oplus \mathbb{Z}_2$

Our next goal is to break down extension L/K into intermediary extensions which will "capture" the inertial degree and ramification index, similarly to how any field extension F/k may be broken down into intermediary extensions into separable, inseparable, and transcendental extensions. In our case, we shall get the tower:

$$K \xrightarrow[1]{1} L_D \xrightarrow[f]{1} L_I \xrightarrow[1]{e} L$$

where the ramification index of each field extension is on top, and the inertia degree is on the bottom.

Proposition 50.4.30: Prime Ideals in Decomposition Field

Let L/K be a finite field extension, $\mathfrak{p} \subseteq \mathcal{O}_K$ a prime ideal and $\mathfrak{B} \subseteq \mathcal{O}_L$ lying over $\mathfrak{p}$. Let $\mathfrak{B}_Z = \mathfrak{B} \cap L_D$ be the prime ideal of L_D below $\mathfrak{B}$. If $\mathfrak{B}$ has inertia degree f and ramification index e, then:

1. $\mathfrak{B}_Z$ is nonsplit in L, that is $\mathfrak{B}$ is the only prime ideal of L above $\mathfrak{B}_D$
2. $\mathfrak{B}$ over L_D has a ramification index e and inertia index f
3. The ramification index and inertia index of $\mathfrak{B}_D$ over K are both 1

Visually, we have:

$$\begin{array}{c} \mathfrak{B}^e J \\ {\scriptstyle e}\uparrow{\scriptstyle f} \\ \mathfrak{B}_D I \\ {\scriptstyle 1}\uparrow{\scriptstyle 1} \\ \mathfrak{p} \end{array}$$

where I and J are the remainder of the factorization. Note that the factorization of each prime factor of J lying above $\mathfrak{p}$ has the same e and f since L/K is Galois, but L_D/K is not necessarily Galois, and so the factorization of I may be quite different (for ex. another prime $\mathfrak{B}'_D$ in L_D lying ove $\mathfrak{B}$ may have ramification and inertia degree)

***Proof*:**

1. Notice that $\mathrm{Gal}_{L_\mathfrak{B}}(L) = D_\mathfrak{B}$: the automorphisms of L that fix $L_\mathfrak{B}$ are by definition the elements of $D_\mathfrak{B}$. Hence, the prime ideals above $\mathfrak{B}_D$ are the $\sigma(\mathfrak{B})$ for $\sigma \in \mathrm{Gal}_{L_\mathfrak{B}}(L)$, but $\sigma(\mathfrak{B}) = \mathfrak{B}$ by definition. Hence, $\mathfrak{B}_D$ is nonsplit in L.

2-3. The fundamental identity gives us:

$$n = efr$$

where $n = |\mathrm{Gal}_K(L)| = |G|$ and $r = [G : D_\mathfrak{B}]$. hence,

$$|D_\mathfrak{B}| = [L : L_\mathfrak{B}] = ef \tag{50.5}$$

Now, let e', e'' be the ramification index of $\mathfrak{B}$ over $L_\mathfrak{B}$ and $\mathfrak{B}_D$ over K respectively. Then $\mathfrak{p}$ is:

$$\mathfrak{p}\mathcal{O}_{L_\mathfrak{B}} = \mathfrak{B}_D^{e''} I$$

for some I and

$$\mathfrak{B}_D \mathcal{O}_L = \mathfrak{B}^{e'}$$

in L. Then

$$\mathfrak{p}\mathcal{O}_L = \mathfrak{B}^{e''e'} J$$

for some J. By the tower property, $e = e'e''$ and $f = f'f''$. Then the fundamental identity for the decomposition of $\mathfrak{B}_D$ in L gives us that the degree of L/L_D is:

$$[L : L_\mathfrak{B}] = e'f'$$

in particular, by equation (50.5), we get,

$$e'f' = ef = e'e''f'f''$$

Hence $e' = e$, $f' = f$, and $e'' = f'' = 1$, as we sought to show

This gives us:

$$K \xrightarrow[1]{1} L_{\mathfrak{B}} \xrightarrow[f]{e} L$$

Next, let us see how we can separate out an extension splitting the ramification and the inertia degree into different groups/fields. Since $\sigma(\mathcal{O}_L) = \mathcal{O}_L$ and $\sigma(\mathfrak{B}) = \mathfrak{B}$ for every $\sigma \in D_{\mathfrak{B}}$, there is an induced automorphism on the residue field $\mathcal{O}_L/\mathfrak{B}$:

$$\begin{aligned} \overline{\sigma} : \mathcal{O}_L/\mathfrak{B} &\to \mathcal{O}_L/\mathfrak{B} \\ (a \bmod \mathfrak{B}) &\mapsto (\sigma(a) \bmod \mathfrak{B}) \end{aligned}$$

Letting $\kappa(\mathfrak{B}) = \mathcal{O}_L/\mathfrak{B}$ and $\kappa(\mathfrak{p}) = \mathcal{O}_K/\mathfrak{p}$, we have that

$$f = [\kappa(\mathfrak{B}) : \kappa(\mathfrak{p})]$$

Recall that in Dedekind-Kummer's theorem, when $\mathfrak{p}$ is relatively prime to the conductor, the inertia degree of $\mathfrak{B}$ is given by the degree of $\overline{m_i}(x)$ which within the proof is derived by $\left[R/(\overline{m_i(x)}) : \overline{\mathcal{O}}_K\right]$. This shows that the above map has information about the inertia degree. The following links this quantity to $D_{\mathfrak{B}}$. To understand the result, the reader may see that $\mathrm{Gal}_K(L)$ would naturally surjects onto $\mathrm{Gal}_{\kappa(\mathfrak{p})}(\kappa(\mathfrak{B}))$ via restriction if the restriction was well-defined. The domain of this map can be restricted to the decomposition group to make it well-defined:

Proposition 50.4.31: Decomposition and Inertia Group Relation

The extension $\kappa(\mathfrak{B})/\kappa(\mathfrak{p})$ is normal and admits a surjective homomorphism:

$$D_{\mathfrak{B}} \twoheadrightarrow \mathrm{Gal}_{\kappa(\mathfrak{p})}(\kappa(\mathfrak{B}))$$

where $\mathrm{Gal}_{\kappa(\mathfrak{p})}(\kappa(\mathfrak{B})) = \mathrm{Gal}_{\mathcal{O}_K/\mathfrak{p}}(\mathcal{O}_L/\mathfrak{B}) \cong \mathrm{Gal}_{\mathbb{F}_p}(\mathbb{F}_q)$.

***Proof*:**

As we are working over finite fields, we know that $\kappa(\mathfrak{B}) = \kappa(\mathfrak{p})(\overline{\theta})$ for some θ with minimal polynomial $\overline{g}(x)$ over $\kappa(\mathfrak{p})$ ($\overline{g}(x) \in \kappa(\mathfrak{p})[x]$)). Let $\theta \in \mathcal{O}_L$ be a representative of $\overline{\theta}$, and let $f(x)$ be its minimal polynomial over $\mathcal{O}_K$. Then by definition $\overline{g}(\overline{\theta}) \equiv 0 \bmod \mathfrak{B}$. Since $f(\theta) = 0$, $\overline{f}(\overline{\theta}) \equiv 0 \bmod \mathfrak{B}$. Hence, taking $\overline{f}(x) \in \kappa(\mathfrak{p})[x]$, we have by minimality that:

$$\overline{g}(x) \big| \overline{f}(x)$$

Next, we know that finite field extensions are normal as we saw in section 19.7.2, however here is another way of seeing this worth pointing out: since L/K is normal, $f(x)$ splits over $\mathcal{O}_L$ into linear factors. Thus, $\overline{f}(x)$ splits into linear factors over $\kappa(\mathfrak{B})$, and similarly for $\overline{g}(x)$. But then, $\kappa(\mathfrak{B})/\kappa(\mathfrak{p})$ is a normal extension.

Now, consider:

$$\overline{\sigma} \in \mathrm{Gal}_{\kappa(\mathfrak{p})}(\kappa(\mathfrak{B})) = \mathrm{Gal}_{\kappa(\mathfrak{p})}\left(\kappa(\mathfrak{p})(\overline{\theta})\right)$$

By corollary 19.2.29, these homomorphisms are determined by where they send the root θ. Then $\overline{\sigma}(\overline{\theta})$ is a root of $\overline{g}(x)$ and hence of $\overline{f}(x)$, that is there exists a root θ' of $f(x)$ such that $\theta' \equiv \overline{\sigma}(\overline{\theta}) \bmod \mathfrak{B}$. θ' is a conjugate of θ, i.e. $\theta' = \sigma(\theta)$ for some $\sigma \in D_{\mathfrak{B}}$ (as the automorphism in $D_{\mathfrak{B}}$ fix $\mathfrak{B}$ and make the map well-defined). Since $\sigma(\theta) \equiv \overline{\sigma}(\overline{\theta}) \bmod \mathfrak{B}$, the automorphism σ is mapped by the homomorphism in question to $\overline{\sigma}$, proving surjectivity, as we sought to show.

Definition 50.4.32: Inertia Group And Field

The kernel $I_{\mathfrak{B}} \subseteq D_{\mathfrak{B}}$ of the homomorphism

$$D_{\mathfrak{B}} \to \mathrm{Gal}_{\kappa(\mathfrak{p})}(\kappa(\mathfrak{B}))$$

is called the *inertia group* of $\mathfrak{B}$ over K which is a normal subgroup of $D_{\mathfrak{B}}$ (as it is the kernel of a homomorphism). Equivalently:

$$I_{\mathfrak{B}} = \{\sigma \in \mathrm{Gal}_K(L) \mid \sigma(\alpha) \equiv \alpha \bmod \mathfrak{B}\}$$

The fixed field:

$$L_I = L^{I_{\mathfrak{B}}} = \{x \in L \mid \sigma(x) = x,\ \forall \sigma \in I_{\mathfrak{B}}\}$$

is called the *inertia field* of $\mathfrak{B}$ over K.

We thus get the following tower:

$$K \subseteq L_D \subseteq L_I \subseteq L$$

and short exact sequence:

$$1 \to I_{\mathfrak{B}} \to D_{\mathfrak{B}} \to \mathrm{Gal}_{\kappa(\mathfrak{p})}(\kappa(\mathfrak{B})) \to 1$$

Corollary 50.4.33: Isomorphism Of Two Galois Groups

Let $L/K/\mathbb{Q}$ be a finite galois extension, and let $\mathfrak{B}$ be a prime lying over $\mathfrak{p} \subseteq \mathcal{O}_K$. Then:

$$\mathrm{Gal}_{L_D}(L_I) \cong \mathrm{Gal}_{\kappa(\mathfrak{p})}(\kappa(\mathfrak{B}))$$

***Proof*:**
Write $D = D_{\mathfrak{B}}$ and $I = I_{\mathfrak{B}}$, so that $L_D = L^D$ and $L_I = L^I$ (definition 50.4.26, definition 50.4.32). By proposition 20.1.12, $\mathrm{Gal}_{L_D}(L) = D$ with $|D| = [L : L_D]$, and likewise $\mathrm{Gal}_{L_I}(L) = I$. In particular $|\mathrm{Gal}_{L_D}(L)| = [L : L_D]$, so L/L_D is a Galois extension by theorem 20.1.13. The subgroup $I = \mathrm{Gal}_{L_I}(L)$ is normal in $D = \mathrm{Gal}_{L_D}(L)$, being the kernel of the homomorphism of proposition 50.4.31 (definition 50.4.32). Hence theorem 20.1.23, applied to the Galois extension L/L_D with intermediate field L_I, shows that L_I/L_D is Galois with

$$\mathrm{Gal}_{L_D}(L_I) \cong D/I$$

On the other hand, the homomorphism $D \twoheadrightarrow \mathrm{Gal}_{\kappa(\mathfrak{p})}(\kappa(\mathfrak{B}))$ of proposition 50.4.31 is surjective with kernel I, so theorem 3.5.1 gives $D/I \cong \mathrm{Gal}_{\kappa(\mathfrak{p})}(\kappa(\mathfrak{B}))$. Composing the two isomorphisms completes the proof.

Corollary 50.4.34: Quotient Group of Decomposition Group

Let L/K be a finite extension. Then the group $D_{\mathfrak{B}}/I_{\mathfrak{B}}$ is cyclic of order f (hence $[D_{\mathfrak{B}} : I_{\mathfrak{B}}] = f$), and the generator $[\varphi] \in D_{\mathfrak{B}}/I_{\mathfrak{B}}$ that generates the group (and hence $\mathrm{Gal}_{\kappa(\mathfrak{p})}(\kappa(\mathfrak{B})) \cong \mathbb{Z}/m\mathbb{Z}$) is called the *Frobenius Element*. The Frobenius element $\varphi \in D_{\mathfrak{B}}$ can be represented in the simple form

$$\varphi(x) = x^{\mathfrak{N}(\mathfrak{p})}$$

***Proof*:**
This is an immediate consequence of the surjectivity of $D_{\mathfrak{B}}$ onto the Galois group of finite field extensions, which is always cyclic.

The order of $\kappa(\mathfrak{B})/\kappa(\mathfrak{p})$ is f, giving the order of the quotient. As the galois group of a finite field is cyclic, it is generated by a Frobenius element. The Frobenius element can be explicitly described, namely

$$\varphi(x) = x^{\mathfrak{N}(\mathfrak{p})} = x^f$$

giving us the rest of the results.

Notice that this means that Frobenius elements and Cyclotomic extensions naturally appear when studying galois extensions. This motivates the study of Cyclotomic extensions in section 50.5.

Corollary 50.4.35: Equivalent Characterization Of Inertia Group

L/K be a finite Galois extension, $I_{\mathfrak{B}} \leqslant D_{\mathfrak{B}}$. Then:

$$I_{\mathfrak{B}} = \{\sigma \in \mathrm{Gal}_K(L) \mid \sigma(\mathfrak{B}) = \mathfrak{B}, \text{ and } \forall \alpha \in \mathcal{O}_L, \sigma(\alpha) - \alpha \in \mathfrak{B}\}$$

***Proof*:**
Let $\sigma \in I_{\mathfrak{B}}$ so that $\overline{\sigma\overline{\alpha}} = \overline{\alpha}$. Then $\sigma(\alpha) = \alpha + b$ for $b \in \mathfrak{B}$. But then:

$$\sigma(\alpha) - \alpha = b \in \mathfrak{B}$$

as we sought to show.

Corollary 50.4.36: Finding Element Of Galois Group

Let K be a number field, $f(x) \in \mathcal{O}_K[x]$ an irreducible polynomial over $\mathcal{O}_K$, L/K the splitting field extension of $f(x)$. Let $\mathfrak{p} \subseteq \mathcal{O}_K$ such that

$$f(x) \bmod \mathfrak{p} \equiv g_1(x) \cdots g_m(x)$$

for distinct irreducibles with degree $\deg(g_i(x)) = d_i$. Then in $\mathrm{Gal}_K(L) \lesssim S_n$, there exists an element α with cycle type

$$(d_1, d_2, ..., d_m)$$

***Proof*:**
Since L is the splitting field, let $\alpha_1, \alpha_2, ..., \alpha_m$ be the roots of f so that

$$f(\alpha_i) = 0$$

Let $\mathfrak{B}$ in L lie above $\mathfrak{p}$. Then:

$$f(\alpha_i) \bmod \mathfrak{p} \equiv 0$$

Since each each g_i are distinct, each $\alpha_i \bmod \mathfrak{p}$ are disticnt. Hence, $D_{\mathfrak{B}}$ acts on the roots of $f \bmod \mathfrak{p}$. Now, taking $g \in D_{\mathfrak{B}}$ that maps to the generator of $\mathrm{Gal}_{\kappa(\mathfrak{p})}(\kappa(\mathfrak{B}))$, we shall get the desired cycle type, completing the proof.

Proposition 50.4.37: Inertia Group Properties

The extension L_I/L_D is normal, and

$$\mathrm{Gal}_{L_D}(L_I) \cong \mathrm{Gal}_{\kappa(\mathfrak{p})}(\kappa(\mathfrak{B}))$$

and $\mathrm{Gal}_{L_I}(L) = I_{\mathfrak{B}}$. If the residue field extension $\kappa(\mathfrak{B})/\kappa(\mathfrak{p})$ is separable, then:

$$|I_{\mathfrak{B}}| = [L : L_I] = e \qquad [D_{\mathfrak{B}} : I_{\mathfrak{B}}] = [L_I : L_D] = f$$

and we can find the prime ideals $\mathfrak{B}_I$ of L_I bellow $\mathfrak{B}$:

1. The ramification index of $\mathfrak{B}$ over $\mathfrak{B}_I$ is e and the inertia degree is 1
2. The ramification index of $\mathfrak{B}_I$ over $\mathfrak{B}_D$ is 1, and the inertia degree if f

Hence:

$$\mathfrak{B}_Z\mathcal{O}_{L_I} = \mathfrak{B}_T I \qquad \mathfrak{B}_T\mathcal{O}_K = \mathfrak{B}^e J$$

for some appropriate ideals I, J.

***Proof*:**
The fact that:

$$|I_{\mathfrak{B}}| = [L : L_I] = e \qquad [D_{\mathfrak{B}} : I_{\mathfrak{B}}] = [L_I : L_D] = f$$

follow from $|D_{\mathfrak{B}}| = [L : L_D] = ef$ and Galois theory (namely $[L : L_I] = |\mathrm{Gal}_{L_I}(L)| = |I_{\mathfrak{B}}|$), hence we need to show $(1)-(2)$. Using the fundamental identity, it all follows from $\kappa(\mathfrak{B}_I) = \kappa(\mathfrak{B})$. Since the inertia group $I_{\mathfrak{B}}$ of $\mathfrak{B}$ over K is also the inertia group of $\mathfrak{B}$ over L_I, it follows from proposition 50.4.31 applied to L/L_I that $\mathrm{Gal}_{\kappa(\mathfrak{B}_I)}(\kappa(\mathfrak{B})) = 1$, thus

$$\kappa(\mathfrak{B}_I) = \kappa(\mathfrak{B})$$

but then the rest follows.

To sum up the results in a diagram

$$K \underset{1}{\overset{1}{\to}} L_D \underset{f}{\overset{1}{\to}} L_I \underset{1}{\overset{e}{\to}} L$$

with a corresponding [contravariant] diagram of groups:

$$G \leftarrow D_{\mathfrak{B}} \leftarrow I_{\mathfrak{B}} \leftarrow \{e\}$$

where the ramification index of each field extension is on top, and the inertia degree is on the bottom. If the residue field extension $\kappa(\mathfrak{B})/\kappa(\mathfrak{p})$ is separable, then:

$$I_{\mathfrak{B}} = 1 \qquad \iff \qquad L_I = L \qquad \iff \qquad \mathfrak{p} \text{ is unramified in } L$$

and in this case the Galois group $\mathrm{Gal}_{\kappa(\mathfrak{p})}(\kappa(\mathfrak{B})) \cong D_{\mathfrak{B}}$, so the galois group of residue field extension can be viewed as a subgroup of $\mathrm{Gal}_K(L)$. This means that the inertia group can be thought of as the "ramification group". In fact, the generalizations of the inertia group (giving more nuanced information on the ramificaion) are called the *higher order ramification group* (which we shall cover soon). The reason the inertia group is not called the 1st ramification group is because the corresponding fixed field only effects the inertia of a prime. Ultimately this is due to the contravariant relation the galois correspondence gives, hence we must make a choice on naming convention depending if fields or groups are prioritised. In this case, fields were prioritised.

From the previous proposition, we may think that L_D and L_I are the *maximal* fields with these properties with respect to $\mathfrak{B}$, and this is indeed the case, making them "natural" with respect to these properties:

Proposition 50.4.38: Intermediary Fields Are Maximal


Let L/K be a finite extension of number fields, $\mathfrak{B}$ live over $\mathfrak{p}$. Then:

1. $L_{D_{\mathfrak{B}}}$ is the smallest intermediary field such that $\mathfrak{B}$ is the only prime of $\mathcal{O}_L$ lying over $\mathfrak{B}' = \mathfrak{B} \cap \mathcal{O}_{L_{D_{\mathfrak{B}}}}$
2. $L_{D_{\mathfrak{B}}}$ is the largest intermediate such that $e(\mathfrak{B}_D/\mathfrak{p}) = f(\mathfrak{B}_D/\mathfrak{p}) = 1$
3. $L_{I_{\mathfrak{B}}}$ is the smallest intermediary field such that $\mathfrak{B}$ is totally ramified over $\mathfrak{B}_I$ (that is $e(\mathfrak{B}/\mathfrak{B}_I) = [L : L_I]$)
4. $L_{I_{\mathfrak{B}}}$ is the largest intermediary field such that $e(\mathfrak{B}_I/\mathfrak{p}) = 1$

***Proof*:**
First, L_D and L_I have these properties as we have in proposition 50.4.30 and proposition 50.4.37, hence we prove they are maximal/minimal.

Let $K' = L^H$ for some $H \leqslant \mathrm{Gal}_K(L)$ where only $\mathfrak{B} \subseteq L$ is lying over $\mathfrak{p}' \subseteq K'$. Since H acts transitively on the primes of L over K' but there is only one prime $H \subseteq D_{\mathfrak{B}}$, so $L_D \subseteq K'$, giving (1).

Next, assume $e_{\mathfrak{p}'/\mathfrak{p}} = f_{\mathfrak{p}'/\mathfrak{p}} = 1$. Consider the following diagram:



Then by multiplicativity of towers, $e = e'$ and $f = f'$. Then by the above diagram, L_D and $L_D K'$ voth ahve the same index in L. Since one contains the other, this means they must be equal, hence

$$K' \subseteq L_D$$

giving (2). A similar arguments works for (3) and (4): if $e_{\mathfrak{p}'/\mathfrak{p}} = 1$, then $e = e'$, so $L_I = L_I K'$, so $K' \subseteq L_I$, and if $\mathfrak{B}$ is totally ramified over $\mathfrak{p}'$, then $[L : K'] = e'$, then by the above diagramwe get $K' = L_I K'$, so $L_I \subseteq K'$, as we sought to show.

Ramification

An importance consequence of this is that we may consider primes that are completely ramified/totally unramified in their galois closure. we first require the following result:

Theorem 50.4.39: Composition Field And Primes

Let L/K and M/K be finite extensions of number fields, and let $\mathfrak{p}$ be a prime of K. Then if $\mathfrak{p}$ is unramified in both L and M, then $\mathfrak{p}$ is unramified in LM. If $\mathfrak{p}$ splits completely in L and M, then $\mathfrak{p}$ splits completely in LM

***Proof*:**
Let $\mathfrak{p}$ be unramified in L and M, and take $\mathfrak{B}$ to be any prime in LM lying over $\mathfrak{p}$. We want to show $e(\mathfrak{B}/\mathfrak{p}) = 1$. Let F be the normal closure of K containing LM, and let $\mathfrak{A}$ be any prime in F lying over $\mathfrak{B}$, namely it lies over $\mathfrak{p}$. Let $I_{\mathfrak{A}/\mathfrak{p}}$ be the inertial group corresponding to the field F_I. Then we see that F_I contains both L and M since the primes $\mathfrak{A} \cap L$ and $\mathfrak{A} \cap M$ are necessarily unramified over $\mathfrak{p}$. Hence, F_I contains LM, implying that $\mathfrak{A} \cap LM$ is unramified over

$\mathfrak{p}$.

The argument for splitting follows exactly the same pattern, replacing $I_{\mathfrak{B}}$ with $D_{\mathfrak{B}}$.

Corollary 50.4.40: Primes In Normal Closure

Let L/K be a finite extension of number fields and $\mathfrak{p}$ a prime in K. Then:

1. If $\mathfrak{p}$ is unramified in L, then it is unramified in the normal closure of M of L over K
2. If $\mathfrak{p}$ splits completely in L, then it splits completely in the normal closure of M of L over K

***Proof*:**
If $\mathfrak{p}$ is unramified in L, then it is unramified in every $\sigma_i(L)$ where i runs over all the automorphism. But since $M = L\sigma_1(L)\cdots\sigma_n(L)$, we use induction on theorem 50.4.39 to get our desired result (similarly for splitting completely).

Example 50.4.41: More Decomposition Of Primes

Let $K = \mathbb{Q}(i, \sqrt{2}, \sqrt{5})$, which is abelian of degree 8. Take the prime $5 \in \mathbb{Z}$. Then it splits into tow primes in $\mathbb{Q}(i)$, stays inert in $\mathbb{Q}(\sqrt{2})$, and becomes a square in $\mathbb{Q}(\sqrt{5})$. Hence in L 5 must have ramification index at least 2, and split into at least 2 primes. Since the inertia field must be a field of degree 4 over $\mathbb{Q}$ in which 5 is unramified, the only choice is $\mathbb{Q}(i, \sqrt{2})$. Now, $(2+i)$ and $(2-i)$ remain prime in $\mathbb{Q}(\sqrt{i}, \sqrt{2})$, and become squares in L, hence 5 must have exactly 2 primes and ramification index 2.

Since normal subgroups over characteristic 0 fields are galois, it is meaningful to ask the behavior of normal subgroups of the galois subgroups:

Proposition 50.4.42: Decomposition Subgroup Is Normal

Suppose $D_{\mathfrak{B}} \trianglelefteq \mathrm{Gal}_K(L)$. Then $\mathfrak{p}\mathcal{O}_L$ splits into r distinct primes in L_D. If $I_{\mathfrak{B}} \trianglelefteq G$, then each prime remains as primes in L_I (i.e. they are inert). Furthermore, each become an eth power in L.

In general, we can only hope for:

$$\mathfrak{B}_D\mathcal{O}_{L_I} = \mathfrak{B}_I I \qquad \mathfrak{B}_I\mathcal{O}_K = \mathfrak{B}^e J$$

for some ideals, while in the normal case of D and I, we get:

$$\begin{aligned}\mathfrak{p}\mathcal{O}_{L_D} &= \mathfrak{B}_{L_1}\cdots\mathfrak{B}_{L_e}\\ \mathfrak{p}\mathcal{O}_{L_I} &= \mathfrak{B}_{L_1}\cdots\mathfrak{B}_{L_e}\\ \mathfrak{p}\mathcal{O}_L &= \mathfrak{B}_1^e\cdots\mathfrak{B}_g^e\end{aligned}$$

which also shows better why the groups $D_{\mathfrak{B}}$ and $I_{\mathfrak{B}}$ are called the "decomposition" and "inertia" groups respectively.

***Proof*:**
This is taking advantage of the fact that $L^{D_{\mathfrak{B}}}/K$ would now be a Galois extension since $D_{\mathfrak{B}} \trianglelefteq \mathrm{Gal}_K(L)$. Then we know that

$$f(\mathfrak{B}_D) = e(\mathfrak{B}_D) = 1$$

and that (since $L^{D_{\mathfrak{B}}}$ is Galois), each other prime must also have the same ramification and inertia degree. Thus, $\mathfrak{p}$ splits into exactly g distinct primes in $L^{D_{\mathfrak{B}}}$. Then by a simple counting argument, we see that each $\mathfrak{B}_D$ must lie under a unique $\mathfrak{B}_I$. It may be that some of these ramify. However, if $I_{\mathfrak{B}} \trianglelefteq \mathrm{Gal}_K(L)$, then we have that each prime must have ramification index 1, showing they are all inert. Finally, a counting argument gives that each $\mathfrak{B}_I$ becomes an eth power in L

Corollary 50.4.43: Normal Subgroup And Completely Split Prime

Let $D_{\mathfrak{B}} \trianglelefteq \mathrm{Gal}_K(L)$ and let K' be an intermediate field of L/K. Then $\mathfrak{p}$ splits completely in K' if and only if $K' \subseteq L_D$

***Proof*:**
Suppose first that $\mathfrak{p}$ splits completely in K'. Then every prime of K' above $\mathfrak{p}$ has ramification index and inertia degree 1 over $\mathfrak{p}$, in particular the prime $\mathfrak{B} \cap K'$. By proposition 50.4.38(2), L_D is the largest intermediate field whose prime below $\mathfrak{B}$ has this property, so $K' \subseteq L_D$. This direction does not use the normality of $D_{\mathfrak{B}}$.

Conversely, suppose $K' \subseteq L_D$. We first check that $\mathfrak{p}$ splits completely in L_D. Since $L_D = L^{D_{\mathfrak{B}}}$, proposition 20.1.12 gives $\mathrm{Gal}_{L_D}(L) = D_{\mathfrak{B}}$, which is normal in $\mathrm{Gal}_K(L)$ by hypothesis, so L_D/K is Galois by theorem 20.1.23. By proposition 50.4.28, all primes in the factorization of $\mathfrak{p}\mathcal{O}_{L_D}$ have the same ramification index and the same inertia degree, and by proposition 50.4.30(3) the prime $\mathfrak{B}_D = \mathfrak{B} \cap L_D$ has both equal to 1. The fundamental identity (proposition 50.4.3) then forces the number of primes above $\mathfrak{p}$ in L_D to be $[L_D : K]$, so $\mathfrak{p}$ splits completely in L_D (definition 50.4.2).

Now let $\mathfrak{q}$ be any prime of K' above $\mathfrak{p}$. By proposition 50.3.10, $\mathfrak{q}\mathcal{O}_{L_D} \neq \mathcal{O}_{L_D}$, so some prime $\mathfrak{q}'$ of L_D divides $\mathfrak{q}\mathcal{O}_{L_D}$, and $\mathfrak{q}' \supseteq \mathfrak{q} \supseteq \mathfrak{p}$ shows that $\mathfrak{q}'$ lies above both $\mathfrak{q}$ and $\mathfrak{p}$ (proposition 50.3.11). Extending the factorization of $\mathfrak{p}\mathcal{O}_{K'}$ to $\mathcal{O}_{L_D}$ and factoring $\mathfrak{q}\mathcal{O}_{L_D}$ gives

$$e(\mathfrak{q}'/\mathfrak{p}) = e(\mathfrak{q}'/\mathfrak{q})\, e(\mathfrak{q}/\mathfrak{p})$$

since distinct primes of K' contribute disjoint sets of prime factors (corollary 50.3.12). Both factors are at least 1 and $e(\mathfrak{q}'/\mathfrak{p}) = 1$, so $e(\mathfrak{q}/\mathfrak{p}) = 1$. Similarly the residue field inclusions $\mathcal{O}_K/\mathfrak{p} \subseteq \mathcal{O}_{K'}/\mathfrak{q} \subseteq \mathcal{O}_{L_D}/\mathfrak{q}'$ give $f(\mathfrak{q}'/\mathfrak{p}) = f(\mathfrak{q}'/\mathfrak{q})f(\mathfrak{q}/\mathfrak{p})$ by theorem 19.3.7, so $f(\mathfrak{q}/\mathfrak{p}) = 1$. Every prime of K' above $\mathfrak{p}$ therefore has ramification index and inertia degree 1, and the fundamental identity (proposition 50.4.3) makes their number $[K' : K]$. Thus $\mathfrak{p}$ splits completely in K', as we sought to show.

In the non-Galois case L/K, take $M/L/K$ where M/K is the Galois closure of L. Then M/L is

Galois. Let $G = \mathrm{Gal}_K(M)$ and $H = \mathrm{Gal}_L(M)$ so that $H \leqslant G$. Take the following tower of primes:

$$\begin{array}{ccc} M & \longrightarrow & \mathfrak{A} \\ \uparrow & & \uparrow \\ L & \longrightarrow & \mathfrak{B} \\ \uparrow & & \uparrow \\ K & \longrightarrow & \mathfrak{p} \end{array}$$

Then by definition:

$$D_{\mathfrak{A}/\mathfrak{p}} \cap H = D_{\mathfrak{A}/\mathfrak{B}}$$
$$I_{\mathfrak{A}/\mathfrak{p}} \cap H = I_{\mathfrak{A}/\mathfrak{B}}$$

Proposition 50.4.44: Prime Decomposition Over Finite Extension

Let

$$\mathfrak{p}_M = \prod_1^{g_{M/K}} \mathfrak{A}_i^{e_i}$$

Let $\mathfrak{O}_1, \mathfrak{O}_2, ..., \mathfrak{O}_{g_{L/K}}$ be the orbits of H acting on the primes $\{\mathfrak{A}_1, \mathfrak{A}_2, ..., \mathfrak{A}_{g_{M/K}}\}$. Then:

$$\mathfrak{p}_L = \prod_i^{g_{L/K}} \mathfrak{B}_i^{e_{\mathfrak{B}_i/\mathfrak{p}}}$$

where each $\mathfrak{B}_i$ comes from an $\mathfrak{O}_i$. Furthermore:

$$e_{\mathfrak{B}_i/\mathfrak{p}} = \frac{|I_{\mathfrak{A}_i/\mathfrak{p}}|}{|\mathrm{stab}_H(\mathfrak{A}_i) \cap I_{\mathfrak{A}_i/\mathfrak{p}}|} \qquad f_{\mathfrak{B}_i/\mathfrak{p}} = \frac{[D_{\mathfrak{A}_i/\mathfrak{p}} : I_{\mathfrak{A}_i/\mathfrak{p}}]}{[\mathrm{stab}_H(\mathfrak{A}_i) : \mathrm{stab}_H(\mathfrak{A}_i) \cap I_{\mathfrak{A}_i/\mathfrak{p}}]}$$

***Proof*:**

Throughout, the setup is the one fixed above: M/K is Galois with group G, $H = \mathrm{Gal}_L(M)$, and M/L is Galois with group H.

First, the primes of L above $\mathfrak{p}$ correspond to the orbits $\mathfrak{O}_1, \ldots, \mathfrak{O}_{g_{L/K}}$. Each $\mathfrak{A}_j$ contracts to the prime $\mathfrak{A}_j \cap L$ of L, which lies above $\mathfrak{p}$. If $\eta \in H$, then η fixes L pointwise, so $\eta(\mathfrak{A}_j) \cap L = \mathfrak{A}_j \cap L$: primes in the same orbit have the same contraction. Conversely, if $\mathfrak{A}_j \cap L = \mathfrak{A}_k \cap L = \mathfrak{B}$, then $\mathfrak{A}_j$ and $\mathfrak{A}_k$ both divide $\mathfrak{B}\mathcal{O}_M$ (proposition 50.3.11), so proposition 50.4.25, applied to the Galois extension M/L, provides $\eta \in H$ with $\eta(\mathfrak{A}_j) = \mathfrak{A}_k$: equal contractions force the same orbit. Finally, every prime $\mathfrak{B}$ of L above $\mathfrak{p}$ arises this way: $\mathfrak{B}\mathcal{O}_M \neq \mathcal{O}_M$ by proposition 50.3.10, and any prime factor of $\mathfrak{B}\mathcal{O}_M$ lies above $\mathfrak{p}$ and contracts to $\mathfrak{B}$ (proposition 50.3.11). Hence $\mathfrak{A}_j \mapsto \mathfrak{A}_j \cap L$ induces a bijection from the orbits onto the primes of L above $\mathfrak{p}$, and writing $\mathfrak{B}_i$ for the common contraction of the orbit $\mathfrak{O}_i$, the factorization

$$\mathfrak{p}_L = \prod_i^{g_{L/K}} \mathfrak{B}_i^{e_{\mathfrak{B}_i/\mathfrak{p}}}$$

holds by the definition of the ramification index.

For the formulas, fix i, write $\mathfrak{A} = \mathfrak{A}_i$ and $\mathfrak{B} = \mathfrak{B}_i$, and abbreviate $D = D_{\mathfrak{A}/\mathfrak{p}}$ and $I = I_{\mathfrak{A}/\mathfrak{p}}$. By definition 50.4.26 and definition 50.4.32 applied in M/L,

$$D_{\mathfrak{A}/\mathfrak{B}} = D \cap H = \mathrm{stab}_H(\mathfrak{A}) \qquad I_{\mathfrak{A}/\mathfrak{B}} = I \cap H = \mathrm{stab}_H(\mathfrak{A}) \cap I$$

where the last equality holds because $I \subseteq D$. The residue fields are finite, so the separability hypothesis of proposition 50.4.37 holds, and applying that proposition in M/K and in M/L gives

$$e_{\mathfrak{A}/\mathfrak{p}} = |I| \qquad f_{\mathfrak{A}/\mathfrak{p}} = [D : I] \qquad e_{\mathfrak{A}/\mathfrak{B}} = |\mathrm{stab}_H(\mathfrak{A}) \cap I| \qquad f_{\mathfrak{A}/\mathfrak{B}} = [\mathrm{stab}_H(\mathfrak{A}) : \mathrm{stab}_H(\mathfrak{A}) \cap I]$$

Extending the factorization of $\mathfrak{p}\mathcal{O}_L$ to $\mathcal{O}_M$ and factoring $\mathfrak{B}\mathcal{O}_M$ gives $e_{\mathfrak{A}/\mathfrak{p}} = e_{\mathfrak{A}/\mathfrak{B}}\, e_{\mathfrak{B}/\mathfrak{p}}$, since distinct primes of L contribute disjoint sets of prime factors (corollary 50.3.12). The residue field inclusions $\mathcal{O}_K/\mathfrak{p} \subseteq \mathcal{O}_L/\mathfrak{B} \subseteq \mathcal{O}_M/\mathfrak{A}$ give $f_{\mathfrak{A}/\mathfrak{p}} = f_{\mathfrak{A}/\mathfrak{B}}\, f_{\mathfrak{B}/\mathfrak{p}}$ by theorem 19.3.7. Dividing the two displayed computations of e and of f yields

$$e_{\mathfrak{B}/\mathfrak{p}} = \frac{|I|}{|\mathrm{stab}_H(\mathfrak{A}) \cap I|} \qquad f_{\mathfrak{B}/\mathfrak{p}} = \frac{[D : I]}{[\mathrm{stab}_H(\mathfrak{A}) : \mathrm{stab}_H(\mathfrak{A}) \cap I]}$$

as we sought to show.

It is also enlightening to have a second perspective here: for subgroup $U, V \leqslant G$, we may consider the equivalence class $\sigma \sim \sigma' \iff \sigma' = u\sigma v$ giving us the double-coset[26]:

$$U\sigma V = \{u\sigma v \mid u \in U, v \in V\}$$

This partition will give us the similar information in the non-Galois case. Let $N/L/K$ be two separable extensions where N/K is Galois with Galois group G. Let $H = \mathrm{Gal}_L(N) \leqslant \mathrm{Gal}_K(N)$. Let $\mathfrak{p}$ be a prime ideal of K and $P_{\mathfrak{p}}$ the set of all prime ideal of L above $\mathfrak{p}$. Then if $\mathfrak{B}$ is a prime ideal of N above $\mathfrak{p}$, then we get a well-defined bijection:

$$H \setminus G / D_{\mathfrak{B}} \to P_{\mathfrak{p}} \qquad H\sigma D_{\mathfrak{B}} \mapsto \sigma\mathfrak{B} \cap L$$

Exercise 50.4.1

1. Let L/K be a galois extension of Number fields, $G = \mathrm{Gal}_K(L)$, $\mathfrak{B}$ lie over $\mathfrak{p}$.
   a) If $\mathfrak{B}$ is inert, then G Is cyclic
   b) If $\mathfrak{p}$ is totally ramified in each intermediary field but not totally ramified in L, then there does not exist non-trivial proper intermediary field, hence G is cyclic (of prime order)
   c) Simiarly, Suppose every intermediate field contains a unique prime lying over $\mathfrak{p}$, but L does not. Show the same as the previous
   d) Let $\mathfrak{p}$ be unramified in every proper non-trivial intermediate field, but ramified in L. Show that G has unique smallest subgroup H and that $H \trianglelefteq G$. Use this to show that $|G| = p^k$ for some k and prime p, that $|H| = p^l$ for some l, and $H \leqslant Z(G)$.
   e) Similarly, show the same for when $\mathfrak{p}$ splits compeltely in every proper non-trivial intermediate field, but not in L.

[26] warning: double cosets need not all have the same size!

f) Let $\mathfrak{p}$ be inert in every proper non-trivial intermediate field but not in L. Prove that G is a cyclic where $|G| = p^k$.

2. (the non-normal case for Frobenius element by taking normal closure, p.78 Marcus)

50.4.3 Detecting Ramification

50.4.45 AKLB setup For generality, let A be a Dedekind domain, K the field of fraction of A, L a finite separable extension of K, and B the integral closure of A in L.

Furthermore, let κ be the residue field of A and λ be the residue field for L. Assume λ/κ and B/A are separable extensions.

Definition 50.4.46: Trace Dual of Fractional Ideal

Take AKLB and let $\mathfrak{P} \subseteq B$ be a fractional ideal. Then the *trace dual* of $\mathfrak{P}$ is:

$$^*\mathfrak{P} = \{x \in L \mid \mathrm{tr}(x\mathfrak{P}) \subseteq A\}$$

By proposition 50.1.32, $^*\mathfrak{P}$ is a finitely generated B-module, and hence by definition a fractional ideal. Note that as the trace-pairing is non-degenerate:

$$^*\mathfrak{P} \xrightarrow{\cong} \mathrm{Hom}_A(\mathfrak{P}, A) \qquad x \mapsto (y \mapsto \mathrm{tr}(xy))$$

which works even when $\mathfrak{P} = (1)_B$, that is:

$$^*B \cong \mathrm{Hom}_A(B, A)$$

This particular trace dual shall be very relevant in detecting ramification:

Definition 50.4.47: Different

Assume AKLB. The fractional ideal

$$\mathfrak{C}_{B/A} = \{x \in L \mid \mathrm{tr}(xB) \subseteq A\} = {}^*B$$

is called *Dedekind's complementary module*, or the *inverse different*. Its inverse

$$\mathfrak{D}_{B/A} := \mathfrak{C}_{B/A}^{-1}$$

is called the *Different* of B/A

Since $\mathfrak{C}_{B/A} \supseteq \mathcal{O}$, $\mathfrak{D}_{B/A} \subseteq \mathcal{O}$ is an integral ideal of L. Naturally, we will often denote the different as $\mathfrak{D}_{L/K}$ and $\mathfrak{C}_{B/A}$ as $\mathfrak{C}_{L/K}$ given the rings B an A are evident from context.

Proposition 50.4.48: Tower Law For Different

Assume $AKLB$ and let M/L be a finite separable extension. Then

1. If $M/L/K$, then $\mathfrak{D}_{M/K} = \mathfrak{D}_{M/L}\mathfrak{D}_{L/K}$
2. If $S \subseteq \mathfrak{o}$ is a multiplicative subset with $0 \notin S$, then $\mathfrak{D}_{S^{-1}\mathcal{O}/S^{-1}\mathfrak{o}} = S^{-1}\mathfrak{D}_{\mathcal{O}/\mathfrak{o}}$

***Proof*:**

1. Write $\mathcal{O}_K = A$, $\mathcal{O}_L = B$ and $\mathcal{O}_M$ for the integral closure of A in M, which is also the integral closure of $\mathcal{O}_L$ in M (corollary 26.1.5). Write $\mathfrak{C}_{M/K}$, $\mathfrak{C}_{M/L}$ and $\mathfrak{C}_{L/K}$ for the complementary modules of $\mathcal{O}_M/\mathcal{O}_K$, $\mathcal{O}_M/\mathcal{O}_L$ and $\mathcal{O}_L/\mathcal{O}_K$, so that $\mathfrak{D}_{L/K}$ in the statement stands for its extension $\mathfrak{D}_{L/K}\mathcal{O}_M$. Let $x \in M$ and put $T = \mathrm{tr}_{M/L}(x\mathcal{O}_M)$, an $\mathcal{O}_L$-submodule of L because $\mathrm{tr}_{M/L}$ is L-linear. The extensions M/L and L/K are separable, by hypothesis and by the AKLB setup, so proposition 50.1.15 gives $\mathrm{tr}_{M/K} = \mathrm{tr}_{L/K} \circ \mathrm{tr}_{M/L}$, and

$$x \in \mathfrak{C}_{M/K} \iff \mathrm{tr}_{L/K}(T) \subseteq \mathcal{O}_K \iff T \subseteq \mathfrak{C}_{L/K}$$

   where the second equivalence holds because $T\mathcal{O}_L = T$. Since $\mathfrak{C}_{L/K}\mathfrak{D}_{L/K} = \mathcal{O}_L$ (theorem 50.2.22), $T \subseteq \mathfrak{C}_{L/K}$ holds exactly when $\mathfrak{D}_{L/K}T \subseteq \mathcal{O}_L$: multiply by $\mathfrak{D}_{L/K}$ for one direction and by $\mathfrak{C}_{L/K}$ for the other. As $\mathrm{tr}_{M/L}$ is L-linear, $\mathfrak{D}_{L/K}T = \mathrm{tr}_{M/L}(x\mathfrak{D}_{L/K}\mathcal{O}_M)$, and since $x\mathfrak{D}_{L/K}\mathcal{O}_M$ is an $\mathcal{O}_M$-module, the condition $\mathrm{tr}_{M/L}(x\mathfrak{D}_{L/K}\mathcal{O}_M) \subseteq \mathcal{O}_L$ says that $x\mathfrak{D}_{L/K}\mathcal{O}_M \subseteq \mathfrak{C}_{M/L}$. Extension of ideals is multiplicative, both sides being generated by the same products, so $(\mathfrak{D}_{L/K}\mathcal{O}_M)(\mathfrak{C}_{L/K}\mathcal{O}_M) = (\mathfrak{D}_{L/K}\mathfrak{C}_{L/K})\mathcal{O}_M = \mathcal{O}_L\mathcal{O}_M = \mathcal{O}_M$. Multiplying by $\mathfrak{C}_{L/K}\mathcal{O}_M$ for one direction and by $\mathfrak{D}_{L/K}\mathcal{O}_M$ for the other,

$$x\mathfrak{D}_{L/K}\mathcal{O}_M \subseteq \mathfrak{C}_{M/L} \iff x \in \mathfrak{C}_{M/L}\mathfrak{C}_{L/K}\mathcal{O}_M$$

   Altogether $\mathfrak{C}_{M/K} = \mathfrak{C}_{M/L}\mathfrak{C}_{L/K}\mathcal{O}_M$, and taking inverses in the group of fractional ideals of $\mathcal{O}_M$ (theorem 50.2.22) gives $\mathfrak{D}_{M/K} = \mathfrak{D}_{M/L}\mathfrak{D}_{L/K}\mathcal{O}_M$.

2. Let $S \subseteq \mathfrak{o}$ be multiplicative with $0 \notin S$. If $x \in L$ satisfies $x^d + (a_1/s_1)x^{d-1} + \cdots + a_d/s_d = 0$ with $a_i \in \mathfrak{o}$ and $s_i \in S$, then multiplying by s^d, where $s = s_1 \cdots s_d$, shows that sx is integral over $\mathfrak{o}$, so $sx \in \mathcal{O}$ and $x \in S^{-1}\mathcal{O}$. Conversely, if $b \in \mathcal{O}$ satisfies a monic equation of degree d over $\mathfrak{o}$, dividing it by s^d shows that b/s is integral over $S^{-1}\mathfrak{o}$ for every $s \in S$. So $S^{-1}\mathcal{O}$ is the integral closure of $S^{-1}\mathfrak{o}$ in L.

   Next, $\mathfrak{C}_{S^{-1}\mathcal{O}/S^{-1}\mathfrak{o}} = S^{-1}\mathfrak{C}_{\mathcal{O}/\mathfrak{o}}$. If $x \in \mathfrak{C}_{\mathcal{O}/\mathfrak{o}}$, then $\mathrm{tr}_{L/K}((x/s)(b/t)) = \mathrm{tr}_{L/K}(xb)/(st)$ lies in $S^{-1}\mathfrak{o}$ for all $s, t \in S$ and $b \in \mathcal{O}$, so x/s lies in the left-hand side. Conversely, let x lie in the left-hand side. The ring $\mathfrak{o}$ is Noetherian, so $\mathcal{O}$ is a finitely generated $\mathfrak{o}$-module (proposition 50.1.32), say by $b_1, \ldots, b_r$, and $\mathrm{tr}_{L/K}(xb_k) = c_k/t_k$ with $c_k \in \mathfrak{o}$ and $t_k \in S$. With $t = t_1 \cdots t_r$, the K-linearity of the trace gives $\mathrm{tr}_{L/K}(txb_k) \in \mathfrak{o}$ for every k, hence $\mathrm{tr}_{L/K}(tx\mathcal{O}) \subseteq \mathfrak{o}$. So $tx \in \mathfrak{C}_{\mathcal{O}/\mathfrak{o}}$ and $x \in S^{-1}\mathfrak{C}_{\mathcal{O}/\mathfrak{o}}$.

   Finally, $S^{-1}\mathcal{O}$ is a Dedekind domain (lemma 50.2.5), and putting a finite sum of products over a common denominator shows that localization carries products of $\mathcal{O}$-modules to products, so

$$\mathfrak{C}_{S^{-1}\mathcal{O}/S^{-1}\mathfrak{o}} \cdot S^{-1}\mathfrak{D}_{\mathcal{O}/\mathfrak{o}} = S^{-1}\left(\mathfrak{C}_{\mathcal{O}/\mathfrak{o}}\mathfrak{D}_{\mathcal{O}/\mathfrak{o}}\right) = S^{-1}\mathcal{O}$$

by theorem 50.2.22. Inverses in the group of fractional ideals of $S^{-1}\mathcal{O}$ are unique, so $S^{-1}\mathfrak{D}_{\mathcal{O}/o}$ is the inverse of $\mathfrak{C}_{S^{-1}\mathcal{O}/S^{-1}o}$, which is $\mathfrak{D}_{S^{-1}\mathcal{O}/S^{-1}o}$, completing the proof.

50.4.49 The Different and Completion The different is also compatible with completion: if $\mathfrak{B}$ is a prime of $\mathcal{O}$ above $\mathfrak{p}$ and $\mathcal{O}_{\mathfrak{B}}$, $o_{\mathfrak{p}}$ denote the completions, then $\mathfrak{D}_{\mathcal{O}/o}\mathcal{O}_{\mathfrak{B}} = \mathfrak{D}_{\mathcal{O}_{\mathfrak{B}}/o_{\mathfrak{p}}}$. This book does not construct completions and does not prove this statement. Its proof rests on the decomposition of $L \otimes_K K_{\mathfrak{p}}$ into the completions of L at the primes above $\mathfrak{p}$, *Local Field Theory* [33, Global To Local Correspondence], under which the trace of L/K becomes the sum of the local traces, [33, Global To Local Correspondence, Norm and Trace].

Example 50.4.50: Different

1. Let $K = \mathbb{Q}(\sqrt{5})$ so that $\mathcal{O}_K = \mathbb{Z}\left[\frac{1+\sqrt{5}}{2}\right]$. Then:
$$\mathfrak{C}_{K/\mathbb{Q}} = \sqrt{5}^{-1}\mathcal{O}_K \implies \mathfrak{D}_{K/\mathbb{Q}} = \sqrt{5}\mathcal{O}_K$$
2. Let $K = \mathbb{Q}(\sqrt{3})$. So that $\mathcal{O}_K = \mathbb{Z}[\sqrt{3}]$. Then:
$$\mathfrak{C}_{K/\mathbb{Q}} = \langle \frac{1}{2}, \frac{1}{\sqrt{3}} \rangle_{\mathbb{Z}} = \frac{1}{2\sqrt{3}}\mathcal{O}_K \implies \mathfrak{D}_{K/\mathbb{Q}} = 2\sqrt{3}\mathcal{O}_K$$

Theorem 50.4.51: Norm Of Different

$$\mathfrak{N}(\mathfrak{D}_{K/\mathbb{Q}}) = |\mathrm{disc}(\mathcal{O}_K)|$$

***Proof*:**
Here $A = \mathbb{Z}$ and $B = \mathcal{O}_K$. Write $\mathfrak{C} = \mathfrak{C}_{K/\mathbb{Q}}$ and $\mathfrak{D} = \mathfrak{D}_{K/\mathbb{Q}} = \mathfrak{C}^{-1}$ (definition 50.4.47), let $n = [K : \mathbb{Q}]$, and let $\omega_1, \dots, \omega_n$ be an integral basis of $\mathcal{O}_K$ (corollary 50.1.33).

Step 1: $\mathfrak{C}$ is free on the dual basis. The extension $K/\mathbb{Q}$ is separable, so by proposition 19.6.31 there is a $\mathbb{Q}$-basis $\omega_1^*, \dots, \omega_n^*$ of K with $\mathrm{tr}_{K/\mathbb{Q}}(\omega_i\omega_j^*) = \delta_{ij}$. Write $x \in K$ as $x = \sum_j c_j\omega_j^*$ with $c_j \in \mathbb{Q}$. Then $\mathrm{tr}_{K/\mathbb{Q}}(x\omega_i) = c_i$, and since $\mathcal{O}_K = \bigoplus_i \mathbb{Z}\omega_i$ and the trace is $\mathbb{Z}$-linear, $\mathrm{tr}_{K/\mathbb{Q}}(x\mathcal{O}_K) \subseteq \mathbb{Z}$ holds exactly when every $c_i \in \mathbb{Z}$. So $\mathfrak{C} = \bigoplus_j \mathbb{Z}\omega_j^*$.

Step 2: $[\mathfrak{C} : \mathcal{O}_K] = |d_K|$. Applying Step 1 to $x = \omega_i$ gives
$$\omega_i = \sum_{j=1}^{n} T_{ij}\,\omega_j^* \qquad T_{ij} = \mathrm{tr}_{K/\mathbb{Q}}(\omega_i\omega_j)$$
where $T_{ij} \in \mathbb{Z}$ by corollary 50.1.14, so that $\mathcal{O}_K \subseteq \mathfrak{C}$. Moreover $\det(T) = d_K$ by proposition 50.1.26 and definition 50.1.38, a nonzero integer (corollary 50.1.28). Let $\sigma_1, \dots, \sigma_n$ be the embeddings of K into $\mathbb{C}$. Applying σ_k to the display shows that the matrix $(\sigma_k(\omega_i))_{k,i}$ equals $(\sigma_k(\omega_j^*))_{k,j}\,T^t$,

so definition 50.1.24 gives

$$d_K = \mathrm{disc}_{K/\mathbb{Q}}(\omega_1, \ldots, \omega_n) = \det(T)^2 \mathrm{disc}_{K/\mathbb{Q}}(\omega_1^*, \ldots, \omega_n^*)$$

Multiplying the first display by the adjugate of T, which has integer entries, gives $d_K \omega_j^* \in \bigoplus_i \mathbb{Z}\omega_i$ for every j. So $d_K \mathfrak{C} \subseteq \mathcal{O}_K \subseteq \mathfrak{C}$, and $\mathfrak{C}/\mathcal{O}_K$ is finite, being a quotient of $\mathfrak{C}/d_K\mathfrak{C} \cong (\mathbb{Z}/d_K\mathbb{Z})^n$. By proposition 50.1.39,

$$d_K = [\mathfrak{C} : \mathcal{O}_K]^2 \mathrm{disc}_{K/\mathbb{Q}}(\omega_1^*, \ldots, \omega_n^*)$$

The discriminant of the $\mathbb{Q}$-basis $\omega_1^*, \ldots, \omega_n^*$ is nonzero (corollary 50.1.28), so comparing the two displays gives $[\mathfrak{C} : \mathcal{O}_K]^2 = \det(T)^2 = d_K^2$, that is $[\mathfrak{C} : \mathcal{O}_K] = |d_K|$.

Step 3: $\mathfrak{N}(\mathfrak{D}) = [\mathfrak{C} : \mathcal{O}_K]$. Since $\mathcal{O}_K \subseteq \mathfrak{C}$ (Step 2) and $\mathfrak{C}\mathfrak{D} = \mathcal{O}_K$ (theorem 50.2.22), multiplying the inclusion by $\mathfrak{D}$ gives $\mathfrak{D} \subseteq \mathcal{O}_K$, so $\mathfrak{D}$ is a nonzero ideal of $\mathcal{O}_K$ and $\mathfrak{N}(\mathfrak{D})$ is defined (definition 50.1.61). Put $m = |d_K|$ and $\mathfrak{b} = m\mathfrak{C}$, a nonzero ideal of $\mathcal{O}_K$ by Step 2. Then $\mathfrak{b}\mathfrak{D} = m\mathcal{O}_K$. The absolute norm is multiplicative (proposition 50.2.30), so by lemma 50.1.63

$$\mathfrak{N}(\mathfrak{b})\mathfrak{N}(\mathfrak{D}) = \mathfrak{N}(m\mathcal{O}_K) = \left|\mathrm{Nm}_{K/\mathbb{Q}}(m)\right| = m^n$$

On the other hand $m\mathcal{O}_K \subseteq \mathfrak{b} \subseteq \mathcal{O}_K$, and multiplication by m is a group isomorphism $\mathfrak{C} \to \mathfrak{b}$ carrying $\mathcal{O}_K$ onto $m\mathcal{O}_K$, so

$$m^n = [\mathcal{O}_K : m\mathcal{O}_K] = [\mathcal{O}_K : \mathfrak{b}]\,[\mathfrak{b} : m\mathcal{O}_K] = \mathfrak{N}(\mathfrak{b})\,[\mathfrak{C} : \mathcal{O}_K]$$

Comparing the two displays and dividing by $\mathfrak{N}(\mathfrak{b}) > 0$ gives $\mathfrak{N}(\mathfrak{D}) = [\mathfrak{C} : \mathcal{O}_K] = |d_K|$, as claimed.

(This next proposition gives a special case of the different and the origin of it's name)

Proposition 50.4.52: Different In Monogenic Extension

Let $\mathcal{O} = o[\alpha]$ and let $f \in o[X]$ be the minimal polynomial of α over K. Then the different is equal to:

$$\mathfrak{D}_{L/K} = (\delta_{L/K}(\alpha))$$

where

$$\delta_{L/K}(\alpha) = \begin{cases} f'(\alpha) & L = K(\alpha) \\ 0 & L \neq K(\alpha) \end{cases}$$

***Proof*:**
The ring $\mathcal{O}$ is the integral closure of o in L and has fraction field L, so $\mathcal{O} = o[\alpha]$ forces $L = K(\alpha)$ and $\delta_{L/K}(\alpha) = f'(\alpha)$. Write $n = [L : K]$ and $f(X) = a_0 + a_1 X + \cdots + a_n X^n$ with $a_n = 1$, let $\alpha_1, \ldots, \alpha_n$ be the roots of f in a normal closure of L/K, and define $b_0, \ldots, b_{n-1} \in \mathcal{O}$ by

$$\frac{f(X)}{X - \alpha} = b_0 + b_1 X + \cdots + b_{n-1} X^{n-1}$$

The first step is that $b_0/f'(\alpha), \ldots, b_{n-1}/f'(\alpha)$ is the basis dual to $1, \alpha, \ldots, \alpha^{n-1}$ for the trace

pairing. For $0 \le s \le n-1$ the polynomial identity

$$\sum_{i=1}^{n} \frac{f(X)}{X-\alpha_i} \cdot \frac{\alpha_i^s}{f'(\alpha_i)} = X^s$$

holds, because the difference of the two sides has degree at most $n-1$ and vanishes at each α_j: the jth summand contributes $f'(\alpha_j)\alpha_j^s/f'(\alpha_j) = \alpha_j^s$ and the others vanish, since $f(X)/(X-\alpha_i) = \prod_{k\neq i}(X-\alpha_k)$. The n summands on the left are the images of $\frac{f(X)}{X-\alpha}\cdot\frac{\alpha^s}{f'(\alpha)}$ under the n embeddings of L over K, so by corollary 50.1.13 the identity reads

$$\operatorname{tr}_{L/K}\left(\frac{f(X)}{X-\alpha}\cdot\frac{\alpha^s}{f'(\alpha)}\right) = X^s$$

and comparing the coefficient of X^i on each side gives that $\operatorname{tr}_{L/K}(b_i\alpha^s/f'(\alpha))$ is 1 when $i=s$ and 0 otherwise.

The elements $b_i/f'(\alpha)$ therefore form a K-basis of L, and for $x = \sum_i c_i b_i/f'(\alpha)$ with $c_i \in K$ one has $\operatorname{tr}_{L/K}(x\alpha^s) = c_s$. Since $\mathcal{O} = \mathfrak{o} + \mathfrak{o}\alpha + \cdots + \mathfrak{o}\alpha^{n-1}$, the condition $\operatorname{tr}_{L/K}(x\mathcal{O}) \subseteq \mathfrak{o}$ is exactly the condition that every c_i lie in $\mathfrak{o}$, so

$$\mathfrak{C}_{L/K} = {}^*\mathcal{O} = \frac{1}{f'(\alpha)}\left(\mathfrak{o}b_0 + \cdots + \mathfrak{o}b_{n-1}\right)$$

Expanding $f(X) = (X-\alpha)(b_0 + b_1X + \cdots + b_{n-1}X^{n-1})$ and comparing coefficients gives $b_{n-1} = 1$ and $b_{k-1} = a_k + \alpha b_k$ for $1 \le k \le n-1$, hence

$$b_{n-i} = \alpha^{i-1} + a_{n-1}\alpha^{i-2} + \cdots + a_{n-i+1} \qquad (1 \le i \le n)$$

Each b_{n-i} is monic of degree $i-1$ in α with coefficients in $\mathfrak{o}$, so the b_i are a second $\mathfrak{o}$-basis of $\mathfrak{o} + \mathfrak{o}\alpha + \cdots + \mathfrak{o}\alpha^{n-1} = \mathcal{O}$. Therefore $\mathfrak{C}_{L/K} = f'(\alpha)^{-1}\mathcal{O}$ and

$$\mathfrak{D}_{L/K} = \mathfrak{C}_{L/K}^{-1} = (f'(\alpha)) = (\delta_{L/K}(\alpha))$$

Only the $\mathfrak{o}$-basis $1, \alpha, \ldots, \alpha^{n-1}$ of $\mathfrak{o}[\alpha]$ entered this computation, never the equality $\mathcal{O} = \mathfrak{o}[\alpha]$. Since $\mathfrak{o}$ is integrally closed, the minimal polynomial of any $\alpha \in \mathcal{O}$ again has coefficients in $\mathfrak{o}$, so for *any* $\alpha \in \mathcal{O}$ with $L = K(\alpha)$ the same argument gives the dual of the $\mathfrak{o}$-module $\mathfrak{o}[\alpha]$,

$${}^*\mathfrak{o}[\alpha] := \left\{x \in L \;\middle|\; \operatorname{tr}_{L/K}(x\,\mathfrak{o}[\alpha]) \subseteq \mathfrak{o}\right\} = \frac{1}{f'(\alpha)}\mathfrak{o}[\alpha] \tag{50.6}$$

a fact used in the next proof.

Theorem 50.4.53: Generation Of Different

For every $\alpha \in \mathcal{O}$, the different $\mathfrak{D}_{L/K}$ divides the principal ideal $(\delta_{L/K}(\alpha))$. In other words, the ideal generated by the elements $\delta_{L/K}(\alpha)$ for $\alpha \in \mathcal{O}$ is contained in $\mathfrak{D}_{L/K}$.

***Proof*:**
Let $\mathfrak{a} \subseteq \mathcal{O}$ be the ideal generated by all $\delta_{L/K}(\alpha)$ for $\alpha \in \mathcal{O}$. Only those α with $L = K(\alpha)$ contribute, since $\delta_{L/K}(\alpha) = 0$ otherwise.

Fix such an α, let f be its minimal polynomial over K, and put $b = f'(\alpha)$, which is nonzero because L/K is separable. Let $\mathscr{F}_\alpha = \{x \in L \mid x\mathcal{O} \subseteq \mathfrak{o}[\alpha]\}$ be the conductor of $\mathfrak{o}[\alpha]$ in the sense of definition 50.4.6. For $x \in L$ the chain of equivalences

$$x\mathcal{O} \subseteq \mathfrak{o}[\alpha] \iff b^{-1}x\mathcal{O} \subseteq \frac{1}{b}\mathfrak{o}[\alpha] = {}^*\mathfrak{o}[\alpha] \iff \operatorname{tr}_{L/K}(b^{-1}x\mathcal{O}) \subseteq \mathfrak{o} \iff b^{-1}x \in {}^*\mathcal{O} = \mathfrak{C}_{L/K}$$

holds: the first equivalence is multiplication by b^{-1} together with equation (50.6), and the second holds because $\mathfrak{o}[\alpha]$ is a subring of $\mathcal{O}$ containing 1, so $\mathcal{O} \cdot \mathfrak{o}[\alpha] = \mathcal{O}$ turns the defining condition of ${}^*\mathfrak{o}[\alpha]$ on $b^{-1}x\mathcal{O}$ into $\operatorname{tr}_{L/K}(b^{-1}x\mathcal{O}) \subseteq \mathfrak{o}$, while the converse direction is the case $1 \in \mathfrak{o}[\alpha]$. The third is the definition of ${}^*\mathcal{O}$. Hence $\mathscr{F}_\alpha = b\,\mathfrak{C}_{L/K} = b\,\mathfrak{D}_{L/K}^{-1}$, that is

$$(\delta_{L/K}(\alpha)) = \mathscr{F}_\alpha \mathfrak{D}_{L/K} \tag{50.7}$$

Since $\mathscr{F}_\alpha \subseteq \mathcal{O}$ is an integral ideal, $\mathfrak{D}_{L/K}$ divides $(\delta_{L/K}(\alpha))$. This holds for every α, so $\mathfrak{a} \subseteq \mathfrak{D}_{L/K}$, as claimed.

Equality holds: $\mathfrak{D}_{L/K}$ is the ideal generated by all $\delta_{L/K}(\alpha)$. Summing (50.7) over all $\alpha \in \mathcal{O}$ with $L = K(\alpha)$ shows that the reverse inclusion amounts to $\sum_\alpha \mathscr{F}_\alpha = \mathcal{O}$, that is, to finding for every prime $\mathfrak{B}$ of $\mathcal{O}$ some α with $L = K(\alpha)$ and $\mathfrak{B} \nmid \mathscr{F}_\alpha$. This is proved by completing at $\mathfrak{B}$, where the valuation ring of the completion of L is generated by one element over that of $K_\mathfrak{p}$, *Local Field Theory* [33, Local Dedekind-Kummer Theorem], and passing back through the compatibility of the different with completion (box 50.4.49). Nothing in this book uses the reverse inclusion.

Theorem 50.4.54: Detecting Ramification Using Different

A prime ideal $\mathfrak{P}$ of L is ramified over K if and only if

$$\mathfrak{P} \mid \mathfrak{D}_{L/K}$$

***Proof*:**
Let $\mathfrak{p} = \mathfrak{P} \cap \mathfrak{o}$, let $e = e(\mathfrak{P}/\mathfrak{p})$, and let $\lambda = \mathcal{O}/\mathfrak{P}$ and $\kappa = \mathfrak{o}/\mathfrak{p}$ be the residue fields, with λ/κ separable by the AKLB setup. Factor

$$\mathfrak{p}\mathcal{O} = \mathfrak{P}^e\mathfrak{q} \qquad \mathfrak{q} = \prod_{\mathfrak{P}' \neq \mathfrak{P}} \mathfrak{P}'^{\,e(\mathfrak{P}'/\mathfrak{p})}$$

by theorem 50.2.15, so $\mathfrak{q}$ is coprime to $\mathfrak{P}$. By definition 50.4.10 and the separability of λ/κ, the prime $\mathfrak{P}$ is ramified over K exactly when $e \geq 2$.

First, $\mathfrak{P} \mid \mathfrak{D}_{L/K}$ is equivalent to $\mathfrak{P}^{-1} \subseteq \mathfrak{D}_{L/K}^{-1} = \mathfrak{C}_{L/K}$, and since $\mathfrak{P}^{-1}\mathcal{O} = \mathfrak{P}^{-1}$ the defining condition of $\mathfrak{C}_{L/K}$ reduces to

$$\mathfrak{P} \mid \mathfrak{D}_{L/K} \iff \operatorname{tr}_{L/K}(\mathfrak{P}^{-1}) \subseteq \mathfrak{o}$$

Extension of ideals is multiplicative, so $\mathfrak{p}^{-1}\mathcal{O} = (\mathfrak{p}\mathcal{O})^{-1}$ and

$$\mathfrak{p}^{-1}\mathfrak{b} = (\mathfrak{P}^e\mathfrak{q})^{-1}\mathfrak{P}^{e-1}\mathfrak{q} = \mathfrak{P}^{-1} \qquad \mathfrak{b} := \mathfrak{P}^{e-1}\mathfrak{q}$$

The trace is o-linear and $\mathfrak{p}^{-1} \subseteq K$, so $\mathrm{tr}_{L/K}(\mathfrak{P}^{-1}) = \mathfrak{p}^{-1}\mathrm{tr}_{L/K}(\mathfrak{b})$, and therefore $\mathfrak{P} \big| \mathfrak{D}_{L/K}$ if and only if $\mathrm{tr}_{L/K}(\mathfrak{b}) \subseteq \mathfrak{p}$.

Next, pass to $o_{\mathfrak{p}}$, a discrete valuation ring. Localisation commutes with integral closure: if $x \in L$ satisfies a monic equation over $o_{\mathfrak{p}}$ then clearing denominators makes sx integral over o for some $s \in o \setminus \mathfrak{p}$, so $x \in \mathcal{O}_{\mathfrak{p}}$, and conversely $\mathcal{O}_{\mathfrak{p}}$ is integral over $o_{\mathfrak{p}}$. Hence $\mathcal{O}_{\mathfrak{p}}$ is the integral closure of $o_{\mathfrak{p}}$ in L and is a free $o_{\mathfrak{p}}$-module of rank $n = [L : K]$ by proposition 50.1.32. A $o_{\mathfrak{p}}$-basis of $\mathcal{O}_{\mathfrak{p}}$ is a K-basis of L, so by definition 50.1.10 the element $\mathrm{tr}_{L/K}(x)$ is the trace of the matrix of multiplication by x in that basis, with entries in $o_{\mathfrak{p}}$. Every element of $o \setminus \mathfrak{p}$ acts invertibly on $\mathcal{O}/\mathfrak{p}\mathcal{O}$, so $\overline{B} := \mathcal{O}_{\mathfrak{p}}/\mathfrak{p}\mathcal{O}_{\mathfrak{p}} = \mathcal{O}/\mathfrak{p}\mathcal{O}$, a κ-algebra of dimension n, and reducing the matrix modulo $\mathfrak{p}$ gives

$$\mathrm{tr}_{L/K}(x) \bmod \mathfrak{p} = \mathrm{tr}_{\overline{B}/\kappa}(\overline{x}) \qquad (x \in \mathcal{O}_{\mathfrak{p}})$$

Since $\mathfrak{p}\mathcal{O} \subseteq \mathfrak{b}$, the condition $\mathrm{tr}_{L/K}(\mathfrak{b}) \subseteq \mathfrak{p}$ says that $\mathrm{tr}_{\overline{B}/\kappa}$ vanishes on the image $\overline{\mathfrak{b}} = \mathfrak{b}/\mathfrak{p}\mathcal{O}$.

The Chinese remainder theorem splits $\overline{B}$ as a product of κ-algebras

$$\overline{B} = \mathcal{O}/\mathfrak{p}\mathcal{O} \cong \mathcal{O}/\mathfrak{P}^e \times \prod_{\mathfrak{P}' \neq \mathfrak{P}} \mathcal{O}/\mathfrak{P}'^{\,e(\mathfrak{P}'/\mathfrak{p})}$$

The image of $\mathfrak{b} = \mathfrak{P}^{e-1}\mathfrak{q}$ is 0 in every factor beyond the first, because $\mathfrak{q} \subseteq \mathfrak{P}'^{\,e(\mathfrak{P}'/\mathfrak{p})}$, and it is $(\mathfrak{P}^{e-1}\mathfrak{q} + \mathfrak{P}^e)/\mathfrak{P}^e = \mathfrak{P}^{e-1}/\mathfrak{P}^e$ in the first, because $\mathfrak{q} + \mathfrak{P} = \mathcal{O}$. Multiplication by an element supported in one factor of a product of κ-algebras annihilates the other factors, so $\mathrm{tr}_{\overline{B}/\kappa}$ restricted to $\overline{\mathfrak{b}}$ is the trace map of $\mathcal{O}/\mathfrak{P}^e$ over κ restricted to $\mathfrak{P}^{e-1}/\mathfrak{P}^e$.

If $e \geq 2$ then $\mathfrak{P}^{2e-2} \subseteq \mathfrak{P}^e$, so every element of $\mathfrak{P}^{e-1}/\mathfrak{P}^e$ squares to zero in $\mathcal{O}/\mathfrak{P}^e$. Multiplication by such an element is a nilpotent endomorphism of a finite-dimensional κ-vector space, and a nilpotent endomorphism has trace 0, its characteristic polynomial being a power of X. So $\mathrm{tr}_{\overline{B}/\kappa}$ vanishes on $\overline{\mathfrak{b}}$ and $\mathfrak{P} \big| \mathfrak{D}_{L/K}$.

If $e = 1$ then $\mathcal{O}/\mathfrak{P}^e = \lambda$ and $\mathfrak{P}^{e-1}/\mathfrak{P}^e = \lambda$, so the map in question is $\mathrm{tr}_{\lambda/\kappa}$. The extension λ/κ is separable, so its trace form is nondegenerate by proposition 19.6.31, and applying nondegeneracy to $x = 1$ produces $y \in \lambda$ with $\mathrm{tr}_{\lambda/\kappa}(y) \neq 0$. So $\mathrm{tr}_{\overline{B}/\kappa}$ does not vanish on $\overline{\mathfrak{b}}$ and $\mathfrak{P} \nmid \mathfrak{D}_{L/K}$.

Thus $\mathfrak{P} \big| \mathfrak{D}_{L/K}$ if and only if $e \geq 2$, which is ramification of $\mathfrak{P}$ over K.

(relation between different and discriminant)

Definition 50.4.55: Relative Discriminant

The *discriminant* $\mathfrak{d}_{\mathcal{O}/o}$ is the ideal of o generated by the discriminants $d(\alpha_1, ..., \alpha_n)$ for all bases $\alpha_1, \alpha_2, ..., \alpha_n$ of L/K contained in $\mathcal{O}$:

$$\mathfrak{d}_{\mathcal{O}/o} = \langle \{ d(\alpha_1, \alpha_2, ..., \alpha_n) \mid \alpha_1, \alpha_2, ..., \alpha_n \text{ basis }, \alpha_i \in \mathcal{O} \} \rangle_o$$

In the case where $K = \mathbb{Q}$ and $L/\mathbb{Q}$ is a number field, then $\mathfrak{d} = (d_L)$ is the principal ideal of the usual discriminant.

Theorem 50.4.56: Relating Different And Relative Discriminant

$$\mathfrak{d}_{L/K} = \mathfrak{N}_{L/K}(\mathfrak{D}_{L/K})$$

***Proof*:**
Both sides are ideals of o, and an ideal of a Dedekind domain is determined by the exponents in its prime factorisation (corollary 50.2.23), which may be read off after localising at each prime. All three constructions survive localisation at a multiplicative set $S \subseteq o \setminus \{0\}$. For the different this is proposition 50.4.48(2). For the discriminant, a basis of L/K inside $S^{-1}\mathcal{O}$ may be scaled by a single $s \in S$ into $\mathcal{O}$, and $d(s\alpha_1, \dots, s\alpha_n) = s^{2n} d(\alpha_1, \dots, \alpha_n)$ by definition 50.1.24, so $S^{-1}\mathfrak{d}_{\mathcal{O}/o} = \mathfrak{d}_{S^{-1}\mathcal{O}/S^{-1}o}$. For the norm, definition 50.3.13 generates $\mathfrak{N}_{L/K}(I)$ by the $\mathrm{Nm}_{L/K}(\alpha)$ with $\alpha \in I$, and $\mathrm{Nm}_{L/K}(\alpha/s) = \mathrm{Nm}_{L/K}(\alpha)/s^n$, so $S^{-1}\mathfrak{N}_{L/K}(I) = \mathfrak{N}_{L/K}(S^{-1}I)$. We may therefore assume o is a discrete valuation ring with maximal ideal $\mathfrak{p}$.

Under that assumption $\mathcal{O}$ is a Dedekind domain (lemma 50.3.2) with finitely many primes $\mathfrak{P}_1, \dots, \mathfrak{P}_g$, namely the primes dividing $\mathfrak{p}\mathcal{O}$. A nonzero prime $\mathfrak{P}$ of $\mathcal{O}$ contains a nonzero x, whose minimal polynomial over K has coefficients in o and nonzero constant term, and that constant term lies in $\mathfrak{P} \cap o$. So $\mathfrak{P} \cap o$ is a nonzero prime of o, which is $\mathfrak{p}$, and $\mathfrak{P}$ divides $\mathfrak{p}\mathcal{O}$ by proposition 50.3.11. Such a ring is a principal ideal domain: given $\mathfrak{a} = \prod_i \mathfrak{P}_i^{a_i}$, the Chinese remainder theorem gives $x \in \mathcal{O}$ with $x \in \mathfrak{P}_i^{a_i} \setminus \mathfrak{P}_i^{a_i+1}$ for every i, and since there is no other prime, $(x) = \mathfrak{a}$. Also $\mathcal{O}$ is a free o-module of rank $n = [L : K]$ by proposition 50.1.32. Fix a o-basis $\alpha_1, \dots, \alpha_n$ of $\mathcal{O}$. Any K-basis of L contained in $\mathcal{O}$ is obtained from it by a matrix over o, so definition 50.1.24 gives $\mathfrak{d}_{L/K} = (d(\alpha_1, \dots, \alpha_n))$.

Let $\alpha'_1, \dots, \alpha'_n$ be the dual basis for the trace pairing, which exists by proposition 19.6.31. Writing $x \in L$ as $x = \sum_j c_j \alpha'_j$ with $c_j \in K$, we get $\mathrm{tr}_{L/K}(x\alpha_i) = c_i$. As $\mathcal{O} = \bigoplus_i o\alpha_i$ and the trace is K-linear, $\mathrm{tr}_{L/K}(x\mathcal{O}) \subseteq o$ exactly when every c_i lies in o, so $\mathfrak{C}_{L/K}$ is o-free on $\alpha'_1, \dots, \alpha'_n$. Since $\mathfrak{D}_{L/K} \subseteq \mathcal{O}$ is integral and $\mathcal{O}$ is a principal ideal domain, $\mathfrak{D}_{L/K} = (\gamma)$ for some $\gamma \in \mathcal{O}$, and $\mathfrak{C}_{L/K} = \gamma^{-1}\mathcal{O}$ is o-free on $\gamma^{-1}\alpha_1, \dots, \gamma^{-1}\alpha_n$. Two o-bases of the same free module differ by a matrix in $\mathrm{GL}_n(o)$, whose determinant is a unit, so

$$(d(\alpha'_1, \dots, \alpha'_n)) = (d(\gamma^{-1}\alpha_1, \dots, \gamma^{-1}\alpha_n))$$

Writing $P = (\sigma_i(\alpha_j))$ and $Q = (\sigma_i(\alpha'_j))$ for the K-embeddings σ_i of L, corollary 50.1.13 gives $(P^tQ)_{jk} = \mathrm{tr}_{L/K}(\alpha_j\alpha'_k)$, which is the identity matrix, so $\det P \det Q = 1$ and

$$d(\alpha_1, \dots, \alpha_n)\, d(\alpha'_1, \dots, \alpha'_n) = 1$$

Likewise $(\sigma_i(\gamma^{-1}\alpha_j)) = \mathrm{diag}(\sigma_i(\gamma^{-1})) \cdot P$, so

$$d(\gamma^{-1}\alpha_1, \dots, \gamma^{-1}\alpha_n) = \mathrm{Nm}_{L/K}(\gamma)^{-2} d(\alpha_1, \dots, \alpha_n)$$

Finally $\mathfrak{N}_{L/K}(\mathfrak{D}_{L/K}) = (\mathrm{Nm}_{L/K}(\gamma))$: by definition 50.3.13 the left side is generated by the $\mathrm{Nm}_{L/K}(\gamma x) = \mathrm{Nm}_{L/K}(\gamma)\mathrm{Nm}_{L/K}(x)$ for $x \in \mathcal{O}$, and the $\mathrm{Nm}_{L/K}(x)$ generate o because they lie in o by corollary 50.1.14 and include $\mathrm{Nm}_{L/K}(1) = 1$. This is lemma 50.3.15(1) in the number field case. Combining,

$$\mathfrak{d}_{L/K}^{-1} = (d(\alpha_1, \dots, \alpha_n)^{-1}) = (d(\alpha'_1, \dots, \alpha'_n)) = (\mathrm{Nm}_{L/K}(\gamma)^{-2})\, \mathfrak{d}_{L/K} = \mathfrak{N}_{L/K}(\mathfrak{D}_{L/K})^{-2}\mathfrak{d}_{L/K}$$

so $\mathfrak{d}_{L/K}^2 = \mathfrak{N}_{L/K}(\mathfrak{D}_{L/K})^2$. Both are powers of $\mathfrak{p}$, so the exponents agree and $\mathfrak{d}_{L/K} = \mathfrak{N}_{L/K}(\mathfrak{D}_{L/K})$.

Corollary 50.4.57: Tower For Relative Discriminant

Let $M/L/K$. Then:

$$\mathfrak{d}_{M/K} = \mathfrak{d}_{L/K}^{[M:L]} \mathfrak{N}_{L/K}(\mathfrak{d}_{M/L})$$

***Proof*:**

Take $M/L/K$ to be number fields, the setting in which the ideal norm of definition 50.3.13 carries the properties collected in lemma 50.3.15. The tower law for the different, proposition 50.4.48(1), reads

$$\mathfrak{D}_{M/K} = \mathfrak{D}_{M/L} \left(\mathfrak{D}_{L/K} \mathcal{O}_M \right)$$

Apply $\mathfrak{N}_{M/K}$ and use theorem 50.4.56 on the left, transitivity $\mathfrak{N}_{M/K} = \mathfrak{N}_{L/K} \circ \mathfrak{N}_{M/L}$ from lemma 50.3.15(2), and multiplicativity from lemma 50.3.15(3):

$$\mathfrak{d}_{M/K} = \mathfrak{N}_{L/K} \left(\mathfrak{N}_{M/L}(\mathfrak{D}_{M/L}) \cdot \mathfrak{N}_{M/L} \left(\mathfrak{D}_{L/K} \mathcal{O}_M \right) \right)$$

The first inner factor is $\mathfrak{d}_{M/L}$ by theorem 50.4.56, and the second is $\mathfrak{D}_{L/K}^{[M:L]}$ by lemma 50.3.15(4). Multiplicativity of $\mathfrak{N}_{L/K}$ then gives

$$\mathfrak{d}_{M/K} = \mathfrak{N}_{L/K}(\mathfrak{d}_{M/L}) \cdot \mathfrak{N}_{L/K}(\mathfrak{D}_{L/K})^{[M:L]} = \mathfrak{N}_{L/K}(\mathfrak{d}_{M/L}) \, \mathfrak{d}_{L/K}^{[M:L]}$$

where the last step is theorem 50.4.56 once more.

Corollary 50.4.58: Discriminant And Ramified Primes

Let L/K be an extension of number fields and let $\mathfrak{p}$ be a nonzero prime of $\mathcal{O}_K$. Then $\mathfrak{p}$ is ramified in L if and only if

$$\mathfrak{p} \big| \mathfrak{d}_{L/K}$$

In particular, the extension L/K is unramified if and only if

$$\mathfrak{d}_{L/K} = (1)$$

***Proof*:**

Write $\mathfrak{D} = \mathfrak{D}_{L/K}$ and $\mathfrak{C} = \mathfrak{C}_{L/K}$. Traces of elements of $\mathcal{O}_L$ lie in $\mathcal{O}_K$ (corollary 50.1.14), so $\mathcal{O}_L \subseteq \mathfrak{C}$, and multiplying by $\mathfrak{D}$ gives $\mathfrak{D} \subseteq \mathfrak{C}\mathfrak{D} = \mathcal{O}_L$ (theorem 50.2.22). So $\mathfrak{D}$ is a nonzero integral ideal, and $\mathfrak{D} = \prod_{\mathfrak{P}} \mathfrak{P}^{d_{\mathfrak{P}}}$ with integers $d_{\mathfrak{P}} \geq 0$, almost all zero (theorem 50.2.15). By theorem 50.4.56, the multiplicativity of the ideal norm (lemma 50.3.15(3)) and corollary 50.3.16,

$$\mathfrak{d}_{L/K} = \mathfrak{N}_{L/K}(\mathfrak{D}) = \prod_{\mathfrak{P}} \mathfrak{N}_{L/K}(\mathfrak{P})^{d_{\mathfrak{P}}} = \prod_{\mathfrak{P}} (\mathfrak{P} \cap \mathcal{O}_K)^{f(\mathfrak{P}) d_{\mathfrak{P}}}$$

where $f(\mathfrak{P})$ is the inertia degree of $\mathfrak{P}$ over $\mathfrak{P} \cap \mathcal{O}_K$. By unique factorization in $\mathcal{O}_K$, the exponent of $\mathfrak{p}$ in $\mathfrak{d}_{L/K}$ is $\sum_{\mathfrak{P}} f(\mathfrak{P}) d_{\mathfrak{P}}$, the sum running over the primes $\mathfrak{P}$ of $\mathcal{O}_L$ above $\mathfrak{p}$. Every $f(\mathfrak{P}) \geq 1$, so $\mathfrak{p} \big| \mathfrak{d}_{L/K}$ if and only if $\mathfrak{P} \big| \mathfrak{D}$ for some $\mathfrak{P}$ above $\mathfrak{p}$. By theorem 50.4.54, this happens if and only if some prime above $\mathfrak{p}$ is ramified over K, that is, if and only if $\mathfrak{p}$ is ramified in L (definition 50.4.10).

For the second statement, $\mathfrak{d}_{L/K} = \mathfrak{N}_{L/K}(\mathfrak{D})$ is a nonzero integral ideal of $\mathcal{O}_K$, being generated by the norms of the elements of $\mathfrak{D} \subseteq \mathcal{O}_L$, which lie in $\mathcal{O}_K$ (corollary 50.1.14). By theorem 50.2.15, it equals (1) exactly when no prime divides it, that is, by the first statement, exactly when no prime of $\mathcal{O}_K$ is ramified in L, as claimed.

Proposition 50.4.59: Coprime Discriminants And Difference

Let K_1, K_2 be Galois over $\mathbb{Q}$ with coprime discriminants, of degrees n_1 and n_2, with $K_1 \cap K_2 = \mathbb{Q}$, and let $K = K_1K_2$. Then:

$$\mathfrak{d}_{K/\mathbb{Q}} = \mathfrak{d}_{K_1/\mathbb{Q}}^{n_2} \mathfrak{d}_{K_2/\mathbb{Q}}^{n_1}$$

***Proof*:**
This is theorem 50.1.47 applied over the base field $\mathbb{Q}$: its hypotheses are that $K_1/\mathbb{Q}$ and $K_2/\mathbb{Q}$ are Galois with coprime discriminants and intersection $\mathbb{Q}$, and over $\mathbb{Q}$ the integral bases it posits exist. Its conclusion gives the integral basis $\omega_i\omega_j'$ of $\mathcal{O}_K$ together with the discriminant $\mathfrak{d}_{K_1/\mathbb{Q}}^{n_2}\mathfrak{d}_{K_2/\mathbb{Q}}^{n_1}$, an identity of integers that reads as the stated identity of ideals.

(Neukirch goes on to prove some important results which are really cool! For example, if K is an algebraic number field and S a finite set of primes of K, then there exists only finitely many extensions L/K of degree n which are unramified outside of S!)

Exercise 50.4.2

1. Show that L_D is the maximal field in which the ramification and inertial degree is 1, and similarly for L_I.
2. Let K be a number fields. Show that if $\operatorname{disc}(K)$ is square free, then K has no intermediary number field

Wild and Tame Ramification

(see this! here)

(This section is essentially here for the proof of Kronecker-Weber Theorem. May choose to move it down to that section).

We end off by exploring some more about the inertia group, namely we shall like at *wild* and *tame* inertia.

Definition 50.4.60: Wild Inertia Group

Let L/K be an extension of number fields, $I_{\mathfrak{B}} \leqslant D_{\mathfrak{B}}$ be the inertia group. Then $W_{\mathfrak{B}} \trianglelefteq I_{\mathfrak{B}}$ is defined to be:

$$W_{\mathfrak{B}} := \left\{ g \in I_{\mathfrak{B}} \;\middle|\; \forall \overline{\alpha} \in \mathcal{O}_L/\mathfrak{B}^2,\ g(\overline{\alpha}) = \overline{\alpha} \right\}$$

the wild inertia group can be thought of as a parallel to "local coordinates". In particular if we have an extension $K/\mathbb{Q}$ of number fields, then we have an extension $K/\mathbb{Q}_p$ then $W_{\mathfrak{B}}$ is the unique sylow

p-subgroup of the inertia group. If you know some algebraic geometry, an intuitive reason to see why the quotient $\mathfrak{B}^2$ shows up is since the tangent space of a variety/scheme is given by $\mathfrak{m}/\mathfrak{m}^2$.

Theorem 50.4.61: Wild Inertia Group Is Sylow Subgroup

Let L/K be a Galois extension of number fields (for instance $K = \mathbb{Q}$), let Q be a nonzero prime of $\mathcal{O}_L$, $\kappa = \mathcal{O}_L/Q$, and let p be the prime number with $Q \cap \mathbb{Z} = p\mathbb{Z}$. For $\sigma \in I_Q$ there is a unique $\theta(\sigma) \in \kappa^\times$ with $\sigma(x) + Q^2 = \theta(\sigma)(x + Q^2)$ for every $x \in Q$, where Q/Q^2 is a κ-vector space through $(a + Q)(x + Q^2) = ax + Q^2$. The map $\theta\colon I_Q \to \kappa^\times$ is a group homomorphism with kernel W_Q, and W_Q is the unique Sylow p-subgroup of I_Q, hence $W_Q \trianglelefteq I_Q$.

***Proof*:**
Write $I = I_Q$, $W = W_Q$, $\kappa = \mathcal{O}_L/Q$ and $q = |\kappa|$. By lemma 50.2.29, κ is a finite field of characteristic p, so q is a power of p, and $p \in Q$. By definition 50.4.32 and corollary 50.4.35, every $\sigma \in I$ satisfies $\sigma(Q) = Q$ and $\sigma(\alpha) - \alpha \in Q$ for all $\alpha \in \mathcal{O}_L$, and by definition 50.4.60 such a σ lies in W exactly when $\sigma(\alpha) - \alpha \in Q^2$ for all $\alpha \in \mathcal{O}_L$. Each $\sigma \in I$ is a ring automorphism of $\mathcal{O}_L$ (lemma 50.4.23) with $\sigma(Q) = Q$, so $\sigma(Q^k) = Q^k$ for every $k \geq 1$.

Step 1: W is the kernel of a homomorphism $I \to \kappa^\times$. The group $V = Q/Q^2$ is a κ-vector space under $(a + Q)(x + Q^2) = ax + Q^2$, which is well defined since $Q \cdot Q = Q^2$. It has $[Q : Q^2] = \mathfrak{N}(Q^2)/\mathfrak{N}(Q) = \mathfrak{N}(Q) = q$ elements (definition 50.1.61, proposition 50.2.30), so $\dim_\kappa V = 1$. Each $\sigma \in I$ induces a bijection $\overline{\sigma}\colon V \to V$, $x + Q^2 \mapsto \sigma(x) + Q^2$, which is κ-linear: for $a \in \mathcal{O}_L$ and $x \in Q$,

$$\sigma(ax) - a\sigma(x) = (\sigma(a) - a)\sigma(x) \in Q \cdot Q = Q^2$$

A κ-linear bijection of the one-dimensional space V is multiplication by a unique scalar, so $\overline{\sigma}$ is multiplication by some $\theta(\sigma) \in \kappa^\times$. Since $\overline{\sigma\tau} = \overline{\sigma}\,\overline{\tau}$, the map $\theta\colon I \to \kappa^\times$ is a group homomorphism, and $W \subseteq \ker\theta$.

For the reverse inclusion let $\sigma \in \ker\theta$, so that $\sigma(x) - x \in Q^2$ for every $x \in Q$, and let $\alpha \in \mathcal{O}_L$. Every $y \in \kappa$ satisfies $y^q = y$, for $y \neq 0$ by theorem 3.3.1 in $\kappa^\times$, which has order $q - 1$. So $x := \alpha - \alpha^q \in Q$. Write $\sigma(\alpha) = \alpha + z$ with $z \in Q$. By the binomial theorem,

$$\sigma(\alpha^q) = (\alpha + z)^q = \alpha^q + q\alpha^{q-1}z + \sum_{k=2}^{q} \binom{q}{k} \alpha^{q-k} z^k$$

where $q\alpha^{q-1}z \in Q^2$ because $q \in p\mathbb{Z} \subseteq Q$ and $z \in Q$, and each later term lies in Q^2. So $\sigma(\alpha^q) - \alpha^q \in Q^2$, and

$$\sigma(\alpha) - \alpha = (\sigma(\alpha^q) - \alpha^q) + (\sigma(x) - x) \in Q^2$$

Hence $\sigma \in W$ and $W = \ker\theta$. In particular $W \trianglelefteq I$, and I/W is isomorphic to a subgroup of $\kappa^\times$ (theorem 3.5.1), so $[I : W]$ divides $q - 1$ (theorem 3.3.1). As q is a power of p, $p \nmid [I : W]$.

Step 2: an element of W of order prime to p is trivial. Let $\tau \in W$ have order m with $p \nmid m$, and put $\delta(\alpha) = \tau(\alpha) - \alpha$ for $\alpha \in \mathcal{O}_L$. We show by induction on $k \geq 2$ that $\delta(\mathcal{O}_L) \subseteq Q^k$. The case

$k = 2$ is $\tau \in W$. Assume $\delta(\mathcal{O}_L) \subseteq Q^k$ for some $k \geq 2$. First, $\delta(Q^k) \subseteq Q^{k+1}$: the group Q^k is additively generated by products $y_1 \cdots y_k$ with $y_i \in Q$, the map δ is additive, and

$$\delta(y_1 \cdots y_k) = \sum_{i=1}^{k} \tau(y_1) \cdots \tau(y_{i-1})\, \delta(y_i)\, y_{i+1} \cdots y_k$$

where in each term $\delta(y_i) \in Q^k$ and the other $k-1$ factors lie in Q, so each term lies in $Q^{2k-1} \subseteq Q^{k+1}$. Next, by induction on $j \geq 1$,

$$\tau^j(\alpha) - \alpha - j\delta(\alpha) \in Q^{k+1} \qquad \alpha \in \mathcal{O}_L$$

The case $j = 1$ is the definition of δ. If it holds for j, write $\tau^j(\alpha) = \alpha + j\delta(\alpha) + z$ with $z \in Q^{k+1}$. Then $\tau^{j+1}(\alpha) = \alpha + \delta(\alpha) + j\delta(\alpha) + j\delta(\delta(\alpha)) + \tau(z)$, where $\delta(\delta(\alpha)) \in \delta(Q^k) \subseteq Q^{k+1}$ and $\tau(z) \in Q^{k+1}$, which is the case $j+1$. Taking $j = m$ gives $m\delta(\alpha) \in Q^{k+1}$. If $\delta(\alpha) \neq 0$, then the exponent of Q in the factorization of $m\delta(\alpha)\mathcal{O}_L = (m\mathcal{O}_L)(\delta(\alpha)\mathcal{O}_L)$ is at least $k+1$ (corollary 50.2.18, theorem 50.2.15). As $m \notin p\mathbb{Z} = Q \cap \mathbb{Z}$, the prime Q does not divide $m\mathcal{O}_L$, so the exponent of Q in $\delta(\alpha)\mathcal{O}_L$ is at least $k+1$, that is $\delta(\alpha) \in Q^{k+1}$. This completes the induction.

So $\delta(\alpha) \in Q^k$ for every k. If $\delta(\alpha) \neq 0$, then Q^k divides $\delta(\alpha)\mathcal{O}_L$ for every k, which is impossible because the exponent of Q in the factorization of $\delta(\alpha)\mathcal{O}_L$ is finite. Hence τ fixes $\mathcal{O}_L$ pointwise, and therefore fixes L pointwise, as every element of L is a quotient of elements of $\mathcal{O}_L$ (proposition 50.1.7). So $\tau = \mathrm{id}$.

Step 3: conclusion. Let $\sigma \in W$ have order $p^a m$ with $p \nmid m$. Then $\sigma^{p^a} \in W$ has order m, so $\sigma^{p^a} = \mathrm{id}$ by Step 2, and $m = 1$. If a prime $\ell \neq p$ divided $|W|$, then theorem 4.8.7 would give an element of W of order ℓ, which is impossible. So $|W|$ is a power of p. Since $|I| = |W|\,[I : W]$ with $p \nmid [I : W]$ by Step 1, W is a Sylow p-subgroup of I. It is normal in I by Step 1, so it is the unique Sylow p-subgroup of I (corollary 4.8.9), as we sought to show.

Lemma 50.4.62: Wild Inertia And Uniformizer

In the setting of theorem 50.4.61, let $\pi \in Q \setminus Q^2$ be a uniformizer for Q and let $\sigma \in I_Q$. Then:

$$\sigma \in W_Q \qquad \Leftrightarrow \qquad \sigma(\pi) - \pi \in Q^2$$

that is, $\sigma(\pi) = \pi \bmod Q^2$

***Proof*:**
By theorem 50.4.61, $\sigma \in W_Q$ exactly when $\theta(\sigma) = 1$, and $\sigma(\pi) + Q^2 = \theta(\sigma)(\pi + Q^2)$. So $\sigma(\pi) - \pi + Q^2 = (\theta(\sigma) - 1)(\pi + Q^2)$. As $\pi \notin Q^2$, the vector $\pi + Q^2$ of the κ-vector space Q/Q^2 is nonzero, so this is 0 exactly when $\theta(\sigma) = 1$, completing the proof.

Example 50.4.63: Example from Class for wild inertia
Let $\zeta = e^{2\pi i/8}$, a primitive 8th root of unity, and $K = \mathbb{Q}(\zeta)$, which contains $i = \zeta^2$ and $\sqrt{2} = \zeta + \zeta^{-1}$. By definition 19.7.2 and proposition 19.7.7, the minimal polynomial of ζ is

$\Phi_8(x) = \prod_{a\in\{1,3,5,7\}}(x-\zeta^a) = x^4+1$, so $[K:\mathbb{Q}] = 4$ and $G = \mathrm{Gal}_{\mathbb{Q}}(K) = \{\sigma_1, \sigma_3, \sigma_5, \sigma_7\}$ with $\sigma_a(\zeta) = \zeta^a$.

The prime above 2. Setting $x = 1$ gives $2 = \prod_a(1-\zeta^a)$. For odd a, $1-\zeta^a = (1-\zeta)(1+\zeta+\cdots+\zeta^{a-1})$, and the second factor is a unit, with inverse $(1-\zeta)/(1-\zeta^a) = 1+\zeta^a+\cdots+\zeta^{a(a'-1)}$ for $aa' \equiv 1 \bmod 8$. So $2\mathcal{O}_K = \mathfrak{B}^4$ with $\mathfrak{B} = (1-\zeta)$, which is a proper ideal as $1/2 \notin \mathcal{O}_K$ (theorem 50.1.9(1)). If $\mathfrak{B} = \mathfrak{q}_1^{a_1}\cdots\mathfrak{q}_t^{a_t}$, then proposition 50.4.3 gives $\sum_j 4a_jf_j = [K:\mathbb{Q}] = 4$, so $\mathfrak{B}$ is a prime of degree 1. So 2 is totally ramified, and $I_{\mathfrak{B}} = G$, as $|I_{\mathfrak{B}}| = e = 4 = |G|$ (proposition 50.4.37, the residue fields being finite).

The wild inertia group. Let $v(x)$ be the exponent of $\mathfrak{B}$ in $x\mathcal{O}_K$, so that $v(xy) = v(x)+v(y)$, $v(2) = 4$, and $\pi = 1-\zeta$ has $v(\pi) = 1$, a uniformizer. For $\sigma_a \neq \sigma_1$, $\sigma_a(\pi)-\pi = \zeta-\zeta^a = \zeta(1-\zeta^{a-1})$ with ζ a unit, so $v(\sigma_a(\pi)-\pi) = v(1-\zeta^{a-1})$, and:

- for $a = 3$, $1-\zeta^2 = 1-i$ and $(1-i)^2 = -2i$, so $2v(1-i) = v(2) = 4$ and $v = 2$
- for $a = 7$, $1-\zeta^6 = 1+i = i(1-i)$, so $v = 2$
- for $a = 5$, $1-\zeta^4 = 2$, so $v = 4$

So $\sigma(\pi)-\pi \in \mathfrak{B}^2$ for every $\sigma \in G$, and lemma 50.4.62 gives $W_{\mathfrak{B}} = I_{\mathfrak{B}} = G$, a 2-group, as theorem 50.4.61 predicts. The subgroups $\{\sigma \in G \mid v(\sigma(\pi)-\pi) \geq j\}$, with $v(0) = \infty$, are G for $j \leq 2$, then $\{\sigma_1, \sigma_5\}$ for $j = 3, 4$, then $\{\sigma_1\}$ for $j \geq 5$.

Theorem 50.4.64: Abelian Extension Wild Map

Let L/K be a Galois extension of number fields, $G = \mathrm{Gal}_K(L)$, $P \subseteq \mathcal{O}_K$ a nonzero prime, Q a prime of $\mathcal{O}_L$ lying over P, W_Q the wild inertia group, and $\theta\colon I_Q \to \mathbb{F}_Q^\times$ the homomorphism of theorem 50.4.61, where $\mathbb{F}_Q = \mathcal{O}_L/Q$ and $\mathbb{F}_P = \mathcal{O}_K/P \subseteq \mathbb{F}_Q$. For a uniformizer π of Q, $\theta(\sigma)$ is the class of $\sigma(\pi)/\pi$ in the sense that $\sigma(\pi) \equiv \theta(\sigma)\pi \bmod Q^2$, and θ induces an injective homomorphism

$$\varphi : I_Q/W_Q \hookrightarrow \mathbb{F}_Q^\times \qquad [\sigma] \mapsto \theta(\sigma)$$

If G is abelian, then $\mathrm{im}\varphi \subseteq \mathbb{F}_P^\times$.

***Proof*:**
Step 1: the map. By theorem 50.4.61, θ is a homomorphism with kernel W_Q, so it induces the injective homomorphism φ (theorem 3.5.1), and $\sigma(\pi)+Q^2 = \theta(\sigma)(\pi+Q^2)$ by definition.

Step 2: conjugation. Let $\tau \in D_Q$ and $\sigma \in I_Q$, and let $\overline{\tau}$ be the automorphism $a+Q \mapsto \tau(a)+Q$ of $\mathbb{F}_Q$ fixing $\mathbb{F}_P$. Lift $\theta(\sigma)$ to $c \in \mathcal{O}_L$, so that $\sigma(y)-cy \in Q^2$ for $y \in Q$. For $x \in Q$ we have $\tau^{-1}(x) \in Q$, so $\sigma(\tau^{-1}(x)) - c\tau^{-1}(x) \in Q^2$, and applying τ, which preserves Q^2, gives $\tau\sigma\tau^{-1}(x) - \tau(c)x \in Q^2$. So $\theta(\tau\sigma\tau^{-1}) = \overline{\tau}(\theta(\sigma))$.

Step 3: abelian groups. If G is abelian, then $\tau\sigma\tau^{-1} = \sigma$, so $\theta(\sigma)$ is fixed by $\overline{\tau}$ for every $\tau \in D_Q$. The homomorphism $D_Q \to \mathrm{Gal}_{\mathbb{F}_P}(\mathbb{F}_Q)$, $\tau \mapsto \overline{\tau}$, is surjective (proposition 50.4.31), so $\theta(\sigma)$ is

fixed by $\text{Gal}_{\mathbb{F}_P}(\mathbb{F}_Q)$. Let $q = |\mathbb{F}_P|$. Every $a \in \mathbb{F}_P$ satisfies $a^q = a$, by theorem 3.3.1 in $\mathbb{F}_P^\times$, so the map $y \mapsto y^q$ is an injective ring endomorphism of the finite field $\mathbb{F}_Q$ fixing $\mathbb{F}_P$, hence an element of $\text{Gal}_{\mathbb{F}_P}(\mathbb{F}_Q)$. So $\theta(\sigma)$ is a root of $X^q - X$, whose at most q roots in $\mathbb{F}_Q$ are the elements of $\mathbb{F}_P$, and $\theta(\sigma) \in \mathbb{F}_P^\times$, completing the proof.

Exercise 50.4.3

1. (Define higher-order ramification. Show that the inertia group is solvable, and when the residue fields are finite then the decomposition group is solvable).

50.4.4 Frobenius Automorphism

This is a short section to single out the Frobenius automorphisms from corollary 50.4.34 due to its importance in Class Field Theory (CFT). Namely the Frobenius automorphism is central to relating the structure of abelian galois groups to the structure of the class group. The full exposition is beyond the scope of this textbook, but the reader can still get an appreciation behind why the Frobenius automorphism is so important. For a full exposition, see [77].

Assume $\mathfrak{B}$ over $\mathfrak{p}$ is unramified in $L/K/\mathbb{Q}$, so that $I_{\mathfrak{B}}$ is trivial (which by proposition 50.4.12 and proposition 50.4.16 can be shown to be the case for all put finitely many primes). Then $D_{\mathfrak{B}} \cong \text{Gal}_{\kappa(\mathfrak{p})}(\kappa(\mathfrak{B})) \cong (\mathbb{Z}/n\mathbb{Z})$. By finite field theory, we know that there exists the *Frobenius generator* sending $x \mapsto x^{\mathfrak{N}(\mathfrak{B})}$ since $\mathfrak{N}(\mathfrak{B}) = f$ and the order of this group is f. Thus, for each prime $\mathfrak{B}/\mathfrak{p}$, have a corresponding automorphism in the decomposition group, and hence the Galois group:

Definition 50.4.65: Frobenius Automorphism of a Prime

Let $\sigma \in D_{\mathfrak{B}}$. Then σ is called the *Frobenius* if $\sigma(\alpha) \equiv \alpha^f \mod \mathfrak{B}$ where f is the inertia degree of $\mathfrak{B}$ over $\mathfrak{p}$. The collection of element $\sigma \in D_{\mathfrak{B}}$ with this property is denoted $\text{Frob}_{\mathfrak{B}/\mathfrak{p}}$ so that is $\sigma \in \text{Frob}_{\mathfrak{B}/\mathfrak{p}}$:

$$\sigma(\alpha) \equiv \alpha^f \mod \mathfrak{B}$$

Note that if $\mathfrak{B}$ were ramified, then the Frobenius automorphism is defined up to the coset $I_{\mathfrak{B}}$: $\sigma + I_{\mathfrak{B}}$. If another $\mathfrak{B}' = \sigma(\mathfrak{B})$[27] is considered, the Frobenius element differ conjugation:

$$\text{Frob}_{\sigma(\mathfrak{B}/\mathfrak{p})} = \sigma \text{Frob}_{\mathfrak{B}/\mathfrak{p}} \sigma^{-1}$$

If $D_{\mathfrak{B}}$ is abelian, then the Frobenius element is *only* determined by the prime $\mathfrak{p}$ as

$$\text{Frob}_{\sigma(\mathfrak{B}/\mathfrak{p})} = \sigma \text{Frob}_{\mathfrak{B}/\mathfrak{p}} \sigma^{-1} = \text{Frob}_{\mathfrak{B}/\mathfrak{p}}$$

Thus, we may denote it as $\text{Frob}_{\mathfrak{p}}$. In this case, we have:

$$\sigma(\alpha) = \alpha^{\mathfrak{N}(\mathfrak{p})} \mod \mathfrak{p}\mathcal{O}_L$$

because $\mathfrak{p}\mathcal{O}_L$ is the product of all primes $\mathfrak{B}$ over $\mathfrak{p}$. Another immediate observation is that if $\mathfrak{p}$ spits completely, then $f = 1$, and the Frobenius element for $\mathfrak{p}$ shall be the identity, and hence the Frobenius element captures behaviour in the case where a prime does not completely split.

[27] by transitivity and definition of the decomposition group, any $\mathfrak{B}'$ is of this form

The important realization is that if $\text{Gal}_k(F)$ is abelian, there exist $\sigma \in \text{Gal}_k(F)$ that are associated to primes $\mathfrak{p}$ in the sense that the structure of σ mod $\mathfrak{B}/\mathfrak{p}$ is simply the power map (i.e. cyclic)! If each element $\sigma \in \text{Gal}_k(F)$ can have such an association, then that means that primes have a strong link to the structure of an abelian galois group. Class field theory [77] makes this precise: for a finite abelian extension F/k of number fields, the Artin map, which sends an unramified prime $\mathfrak{p}$ to its Frobenius element, identifies $\text{Gal}_k(F)$ with a quotient of a ray class group of k.

When $\text{Gal}_k(F)$ is non-abelian, the situation become more tenuous. Robert Langland is credited for finding the right framework to extend this correspondence through the use of *representation theory*. This is the origins of the famous *Langland's Conjecture*.

50.4.5 Example: Cyclotomic Fields

By example 50.1.31, the discriminant of $\mathbb{Z}[\zeta_{p^k}]$, which is the ring of integers of $\mathbb{Q}(\zeta_{p^k})$ by proposition 50.1.50, is up to sign a power of p. So by corollary 50.4.58, a prime that ramifies in $\mathbb{Q}(\zeta_{p^k})$ divides this discriminant, hence equals p.

Lemma 50.4.66: Cyclotomic Fields Lemma

Let $n = p^k$ be a prime power, ζ_{p^k} a primitive p^kth root of unity, and $\lambda = 1 - \zeta_{p^k}$. Then the principal ideal $(\lambda) \subseteq \mathcal{O}$ in the ring of integers of $\mathbb{Q}(\zeta_{p^k})$ is a prime ideal of degree 1, and:

$$p\mathcal{O} = (\lambda)^d$$

where $d = \varphi(n) = [\mathbb{Q}(\zeta_{p^k}) : \mathbb{Q}]$. Furthermore, the basis $1, \zeta_{p^k}, ..., \zeta_{p^k}^{d-1}$ of $\mathbb{Q}(\zeta_{p^k})/\mathbb{Q}$ has discriminant:

$$d_{\mathbb{Q}(\zeta_{p^k})/\mathbb{Q}}(1, \zeta_{p^k}, ..., \zeta_{p^k}^{d-1}) = \pm p^s$$

where $s = p^{k-1}(kp - k - 1)$

***Proof*:**
Write $\zeta = \zeta_{p^k}$, $K = \mathbb{Q}(\zeta)$ and $\Phi = \Phi_{p^k}$.

Step 1: $p = \prod_r (1 - \zeta^r)$. By definition 19.7.2 and lemma 19.7.4,

$$\Phi(x) = \prod_{r \in (\mathbb{Z}/p^k\mathbb{Z})^\times} (x - \zeta^r) = \frac{x^{p^k} - 1}{x^{p^{k-1}} - 1} = x^{p^{k-1}(p-1)} + \cdots + x^{p^{k-1}} + 1$$

It is irreducible over $\mathbb{Q}$ (proposition 19.7.7), so it is the minimal polynomial of ζ and $d = [K : \mathbb{Q}] = \varphi(p^k)$. Setting $x = 1$ gives

$$p = \Phi(1) = \prod_{r \in (\mathbb{Z}/p^k\mathbb{Z})^\times} (1 - \zeta^r)$$

Step 2: $p\mathcal{O} = (\lambda)^d$. For $r \in (\mathbb{Z}/p^k\mathbb{Z})^\times$, represented by a positive integer, $1 - \zeta^r = (1 - \zeta)\epsilon_r$ with

$\epsilon_r = 1 + \zeta + \cdots + \zeta^{r-1} \in \mathcal{O}$. If r' is a positive integer with $rr' \equiv 1 \bmod p^k$, then

$$\frac{1-\zeta}{1-\zeta^r} = \frac{1-(\zeta^r)^{r'}}{1-\zeta^r} = 1 + \zeta^r + \cdots + (\zeta^r)^{r'-1} \in \mathcal{O}$$

so ϵ_r is a unit of $\mathcal{O}$. By Step 1, $p = \epsilon\lambda^d$ with the unit $\epsilon = \prod_r \epsilon_r$, so $p\mathcal{O} = (\lambda)^d$.

Step 3: (λ) is prime of degree 1. The element λ is not a unit, since otherwise $p\mathcal{O} = \mathcal{O}$ and $1/p \in \mathcal{O} \cap \mathbb{Q} = \mathbb{Z}$ (theorem 50.1.9(1)). Write $(\lambda) = \mathfrak{q}_1^{a_1} \cdots \mathfrak{q}_t^{a_t}$ with distinct primes and $a_j \geq 1$, so that $p\mathcal{O} = \mathfrak{q}_1^{da_1} \cdots \mathfrak{q}_t^{da_t}$. By proposition 50.4.3, with $o = \mathbb{Z}$ and $\mathcal{O} = \mathcal{O}_K$, $\sum_j da_j f_j = d$, so $t = 1$, $a_1 = 1$ and $f_1 = 1$: (λ) is a prime of degree 1.

Step 4: the discriminant. Let $\eta = \zeta^{p^{k-1}}$, a primitive pth root of unity. By proposition 50.1.29, $\operatorname{disc}(1, \zeta, \ldots, \zeta^{d-1}) = \pm \operatorname{Nm}_{K/\mathbb{Q}}(\Phi'(\zeta))$. Differentiating $(x^{p^{k-1}} - 1)\Phi(x) = x^{p^k} - 1$ and substituting $x = \zeta$, where $\Phi(\zeta) = 0$, gives

$$(\eta - 1)\Phi'(\zeta) = p^k \zeta^{p^k - 1} = p^k \zeta^{-1}$$

The norm is multiplicative, $\operatorname{Nm}_{K/\mathbb{Q}}(p^k) = p^{kd}$, and $\operatorname{Nm}_{K/\mathbb{Q}}(\zeta^{-1}) = \pm 1$ as ζ^{-1} is a unit (proposition 50.1.18). By Step 1 for $k = 1$ and corollary 50.1.13, $\operatorname{Nm}_{\mathbb{Q}(\eta)/\mathbb{Q}}(1-\eta) = \prod_{r \in (\mathbb{Z}/p\mathbb{Z})^\times}(1-\eta^r) = p$, so $\operatorname{Nm}_{\mathbb{Q}(\eta)/\mathbb{Q}}(\eta - 1) = \pm p$. As $[K : \mathbb{Q}(\eta)] = \varphi(p^k)/\varphi(p) = p^{k-1}$, proposition 50.1.12 gives $\operatorname{Nm}_{K/\mathbb{Q}}(\eta - 1) = \operatorname{Nm}_{\mathbb{Q}(\eta)/\mathbb{Q}}(\eta - 1)^{p^{k-1}} = \pm p^{p^{k-1}}$. Hence

$$\operatorname{Nm}_{K/\mathbb{Q}}(\Phi'(\zeta)) = \pm \frac{\operatorname{Nm}_{K/\mathbb{Q}}(p^k \zeta^{-1})}{\operatorname{Nm}_{K/\mathbb{Q}}(\eta - 1)} = \pm \frac{p^{k\varphi(p^k)}}{p^{p^{k-1}}} = \pm p^{p^{k-1}(kp-k-1)}$$

and $\operatorname{disc}(1, \zeta, \ldots, \zeta^{d-1}) = \pm p^s$, completing the proof.

For general n, the ring of integers of $\mathbb{Q}(\zeta_n)$ is $\mathbb{Z}[\zeta_n]$ (proposition 50.1.51), and its discriminant $\operatorname{disc}(\zeta_n)$ divides $n^{\varphi(n)}$ (example 50.1.31). So by corollary 50.4.58, only primes dividing n can ramify in $\mathbb{Q}(\zeta_n)$.

Proposition 50.4.67: Prime Decomposition In Cyclotomic Field

Let $p_1, p_2, \ldots$ enumerate the primes, and let $n = \prod_k p_k^{n_k}$, almost all $n_k = 0$, be the prime factorization of $n \in \mathbb{Z}_{>0}$. Let f_k be the smallest positive integer such that

$$p_k^{f_k} \equiv 1 \bmod (n/p_k^{n_k})$$

Then in $\mathbb{Q}(\zeta_n)$, we have:

$$p_k = (\mathfrak{p}_1 \cdots \mathfrak{p}_r)^{\varphi(p_k^{n_k})}$$

where $\mathfrak{p}_1, ..., \mathfrak{p}_r$ are distinct prime ideals all of degree f_k.

Note that if $p_k \nmid n$, then $n_k = 0$, so the condition becomes

$$p_k^{f_k} \equiv 1 \bmod n$$

and $\varphi(p_k^{n_k}) = 1$, giving us:

$$p_k = \mathfrak{p}_1 \cdots \mathfrak{p}_r$$

***Proof*:**
Fix $p = p_k$, write $\nu = n_k$ and $m = n/p^\nu$, so $p \nmid m$, and let $f = f_k$, the least positive integer with $p^f \equiv 1 \bmod m$. Let $K = \mathbb{Q}(\zeta_n)$.

Step 1: reduction to Φ_m. By proposition 50.1.51, $\mathcal{O}_K = \mathbb{Z}[\zeta_n]$, so the conductor of $\mathbb{Z}[\zeta_n]$ is $\mathcal{O}_K$ and theorem 50.4.7 applies to every prime: $p\mathcal{O}_K$ factors as Φ_n, the minimal polynomial of ζ_n (proposition 19.7.7), factors modulo p. As $\gcd(m, p^\nu) = 1$, the primitive nth roots of unity are the products $\xi\eta$ of a primitive mth root of unity ξ and a primitive p^νth root of unity η, so

$$\Phi_n(x) = \prod_{\xi,\eta}(x - \xi\eta)$$

Let $\mathfrak{p}$ be a prime of $\mathcal{O}_K$ over p. Each η satisfies $(\eta - 1)^{p^\nu} \equiv \eta^{p^\nu} - 1 = 0 \bmod p$, as the binomial coefficients $\binom{p}{i}$ with $0 < i < p$ are divisible by p, so $\eta - 1 \in \mathfrak{p}$. Hence $\Phi_n(x) \equiv \prod_{\xi,\eta}(x - \xi) = \Phi_m(x)^{\varphi(p^\nu)}$ coefficientwise modulo $\mathfrak{p}$, and as both sides lie in $\mathbb{Z}[x]$ and $\mathfrak{p} \cap \mathbb{Z} = p\mathbb{Z}$, the congruence $\Phi_n \equiv \Phi_m^{\varphi(p^\nu)}$ holds modulo p.

Step 2: $\overline{\Phi}_m$ has distinct irreducible factors. Let $\overline{g}$ denote reduction modulo p. As $p \nmid m$, the derivative mx^{m-1} of $x^m - 1$ is coprime to it over $\mathbb{F}_p$, so $x^m - 1$ is separable over $\mathbb{F}_p$ (proposition 19.6.6). By lemma 19.7.4, $x^m - 1 = \prod_{e \mid m} \overline{\Phi}_e$ over $\mathbb{F}_p$, so $\overline{\Phi}_m$ has no repeated irreducible factor.

Step 3: each factor has degree f. Let $h \in \mathbb{F}_p[x]$ be an irreducible factor of $\overline{\Phi}_m$. In the principal ideal domain $\mathbb{F}_p[x]$ (corollary 11.1.2) the irreducible h is prime (proposition 10.1.33), so (h) is maximal (proposition 10.1.32) and $\mathbb{F}_p[x]/(h)$ is a field. Let $\overline{\xi}$ be the class of x in it, a root of $\overline{\Phi}_m$. Then $\overline{\xi}^m = 1$. If $\overline{\xi}$ had order $e < m$, it would be a root of $x^e - 1 = \prod_{e' \mid e} \overline{\Phi}_{e'}$, hence a root of two different factors $\overline{\Phi}_{e'}$ and $\overline{\Phi}_m$ of $x^m - 1$, a repeated root, contrary to Step 2. So $\overline{\xi}$ has order m. Let $f' = \deg h$, so that $\mathbb{F}_p(\overline{\xi})$ has $p^{f'}$ elements. As $\overline{\xi}$ has order m in $\mathbb{F}_p(\overline{\xi})^\times$, theorem 3.3.1 gives $m \mid p^{f'} - 1$, so $f \leq f'$. Conversely, $y \mapsto y^p$ is a ring endomorphism of $\mathbb{F}_p(\overline{\xi})$, and $y \mapsto y^{p^f}$ fixes $\overline{\xi}$, as $\overline{\xi}^{p^f - 1} = 1$, and fixes $\mathbb{F}_p$, so it fixes every element of $\mathbb{F}_p(\overline{\xi}) = \mathbb{F}_p[\overline{\xi}]$. So the $p^{f'}$ elements of $\mathbb{F}_p(\overline{\xi})$ are roots of $x^{p^f} - x$, and $p^{f'} \leq p^f$. Hence $f' = f$.

Step 4: conclusion. By Steps 2 and 3, $\overline{\Phi}_m = h_1 \cdots h_r$ with distinct irreducible h_i of degree f, and by Step 1, $\overline{\Phi}_n = (h_1 \cdots h_r)^{\varphi(p^\nu)}$. Theorem 50.4.7 gives $p\mathcal{O}_K = (\mathfrak{p}_1 \cdots \mathfrak{p}_r)^{\varphi(p^\nu)}$ with distinct primes $\mathfrak{p}_i$ of inertia degree f, completing the proof.

Corollary 50.4.68: Special Case Of Factorization

Let $n \geq 1$ and let p be a prime number.

1. If $p \nmid n$, then p is unramified in $\mathbb{Q}(\zeta_n)$, and it is totally split if and only if $p \equiv 1 \bmod n$.
2. If $p \mid n$, then p is ramified in $\mathbb{Q}(\zeta_n)$, except when $p = 2$ and $n \equiv 2 \bmod 4$, in which case 2 is unramified.

***Proof*:**
Write $n = p^\nu m$ with $p \nmid m$. By proposition 50.4.67, $p\mathcal{O} = (\mathfrak{p}_1 \cdots \mathfrak{p}_r)^{\varphi(p^\nu)}$ with distinct primes $\mathfrak{p}_i$, all of inertia degree f, the least positive integer with $p^f \equiv 1 \bmod m$. So every ramification index equals $\varphi(p^\nu)$.

1. If $p \nmid n$, then $\nu = 0$ and $\varphi(1) = 1$, so p is unramified. It is totally split exactly when also $f = 1$, that is, when $p \equiv 1 \bmod m = n$.
2. If $p \mid n$, then $\nu \geq 1$ and $\varphi(p^\nu) = p^{\nu-1}(p-1)$, which equals 1 only for $p = 2$ and $\nu = 1$, that is, $n \equiv 2 \bmod 4$. Otherwise the ramification index exceeds 1 and p ramifies.

This completes the proof.

Corollary 50.4.69: Subfield Of Cyclotomic Field

Let $K \subseteq \mathbb{Q}(\zeta_n) = L$ with corresponding subgroup $H = \mathrm{Gal}_K(L) \leqslant \mathrm{Gal}_\mathbb{Q}(L)$, considered as a subgroup of $(\mathbb{Z}/n\mathbb{Z})^\times$ through the isomorphism $\mathrm{Gal}_\mathbb{Q}(L) \cong (\mathbb{Z}/n\mathbb{Z})^\times$ matching the automorphism σ_a with $\sigma_a(\zeta_n) = \zeta_n^a$ to the class of a. For prime p where $p \nmid n$, let f be the least positive integer such that $\overline{p^f} \in H$. Then for prime $\mathfrak{p}$ lying above p in K:

$$f = f_{\mathfrak{p}/p}$$

***Proof*:**
Let $G = \mathrm{Gal}_\mathbb{Q}(L)$. The field L is the splitting field of $x^n - 1$ over $\mathbb{Q}$, so $L/\mathbb{Q}$ is Galois (theorem 19.5.13, corollary 19.6.8), and so is L/K, with group H (proposition 19.5.16). By proposition 19.7.9, $G \cong (\mathbb{Z}/n\mathbb{Z})^\times$, the class of a corresponding to the automorphism σ_a with $\sigma_a(\zeta_n) = \zeta_n^a$. Then $\sigma_a\sigma_b = \sigma_{ab}$, so $\sigma_p^j = \sigma_{p^j}$ for every $j \geq 1$. Let $\mathfrak{B}$ be a prime of $\mathcal{O}_L$ above $\mathfrak{p}$, which exists because $\mathfrak{p}\mathcal{O}_L \neq \mathcal{O}_L$ (proposition 50.3.10).

Step 1: the inertia degree as an index. Since $p \nmid n$, proposition 50.4.67 gives $p\mathcal{O}_L = \mathfrak{p}_1 \cdots \mathfrak{p}_r$ with distinct primes, so $e(\mathfrak{B}/p) = 1$, and $e(\mathfrak{B}/\mathfrak{p}) = 1$ by corollary 50.4.4. The residue fields are finite, hence perfect (corollary 19.6.12), so proposition 50.4.37 applies to $\mathfrak{B}$ in $L/\mathbb{Q}$ and in L/K. With $D = D_{\mathfrak{B}/p} \leqslant G$ the decomposition group in $L/\mathbb{Q}$, it gives $|D| = f(\mathfrak{B}/p)$ and $|I_{\mathfrak{B}/p}| = 1$. The decomposition group of $\mathfrak{B}$ in L/K is $\{\tau \in H \mid \tau(\mathfrak{B}) = \mathfrak{B}\} = D \cap H$ (definition 50.4.26), so $|D \cap H| = f(\mathfrak{B}/\mathfrak{p})$. By corollary 50.4.4,

$$f(\mathfrak{p}/p) = \frac{f(\mathfrak{B}/p)}{f(\mathfrak{B}/\mathfrak{p})} = \frac{|D|}{|D \cap H|}$$

Step 2: D is generated by σ_p. By proposition 50.1.51, $\mathcal{O}_L = \mathbb{Z}[\zeta_n]$. For $u, v \in \mathcal{O}_L$, the binomial theorem gives $(u+v)^p - u^p - v^p \in p\mathcal{O}_L$, since p divides $\binom{p}{k}$ for $0 < k < p$, and $c^p \equiv c \bmod p$ for $c \in \mathbb{Z}$ by theorem 3.3.1 in $(\mathbb{Z}/p\mathbb{Z})^\times$. Applying the first fact repeatedly, for $x = \sum_i c_i\zeta_n^i$ with $c_i \in \mathbb{Z}$,

$$x^p \equiv \sum_i c_i^p \zeta_n^{ip} \equiv \sum_i c_i \zeta_n^{ip} = \sigma_p(x) \bmod p\mathcal{O}_L$$

and $\sigma_p(x) - x^p \in p\mathcal{O}_L \subseteq \mathfrak{B}$ for every $x \in \mathcal{O}_L$. In particular $\sigma_p(\mathfrak{B}) \subseteq \mathfrak{B}$, and $\sigma_p(\mathfrak{B})$ is a nonzero

prime of $\mathcal{O}_L$ (lemma 50.4.23), hence maximal (theorem 50.2.6), so $\sigma_p(\mathfrak{B}) = \mathfrak{B}$ and $\sigma_p \in D$. The homomorphism $D \to \mathrm{Gal}_{\mathbb{F}_p}(\mathcal{O}_L/\mathfrak{B})$ of proposition 50.4.31 is surjective, with kernel $I_{\mathfrak{B}/p}$ (definition 50.4.32), which is trivial by Step 1. So it is an isomorphism. It sends σ_p to the map $y \mapsto y^p$ of $\mathcal{O}_L/\mathfrak{B}$, which generates $\mathrm{Gal}_{\mathbb{F}_p}(\mathcal{O}_L/\mathfrak{B})$ by proposition 19.7.19. Hence $D = \langle \sigma_p \rangle$.

Step 3: conclusion. Let f_0 be the least positive integer with $\sigma_p^{f_0} \in H$, which exists because σ_p has finite order N. If $\sigma_p^j \in H$, write $j = af_0 + b$ with $0 \leq b < f_0$. Then $\sigma_p^b = \sigma_p^j(\sigma_p^{f_0})^{-a} \in H$, so $b = 0$. Hence $\langle \sigma_p \rangle \cap H = \langle \sigma_p^{f_0} \rangle$, and f_0 divides N, as $\sigma_p^N = 1 \in H$. The subgroup $\langle \sigma_p^{f_0} \rangle$ has order N/f_0, so Steps 1 and 2 give

$$f(\mathfrak{p}/p) = \frac{|\langle \sigma_p \rangle|}{|\langle \sigma_p \rangle \cap H|} = \frac{N}{N/f_0} = f_0$$

Under $G \cong (\mathbb{Z}/n\mathbb{Z})^\times$, $\sigma_p^j = \sigma_{p^j}$ corresponds to $\overline{p^j}$, so f_0 is the least positive integer with $\overline{p^{f_0}} \in H$, that is $f_0 = f$, completing the proof.

In summary, the ring of integers of $\mathbb{Q}(\zeta_n)$ is $\mathbb{Z}[\zeta_n]$ (proposition 50.1.51), so it is monogenic, and proposition 50.4.67 gives the factorization of every prime in it. By corollary 50.4.68, a prime p ramifies in $\mathbb{Q}(\zeta_n)$ if and only if $p \mid n$, except that 2 is unramified when $n \equiv 2 \bmod 4$.

50.4.6 Application: Quadratic Extensions and Quadratic Reciprocity

We now take a moment to solve a classical number theory problems with the developed tools. Let $p \in \mathbb{Z}$ be a prime number. In section 10.3, it was shown that p can be written as the sum of two squares if and only if $p \equiv 1 \bmod 4$. Let us now ask another question that may shed further light on the nature of primes: the square-root of primes is always an irrational number. However, when modding by $n \in \mathbb{N}$, it is possible that there is an answer. By the Chinese Remainder Theorem, it suffices to check when $n = q$ is a prime. Thus:

what primes p have the property that there exists an n such that $n^2 \equiv p \bmod q$

Example 50.4.70: Concrete Example
Let $p = 3$. Then:

mod	1^2	2^2	3^2	4^2	5^2	6^2
2	1					
3	1	1				
5	1	4	4	1		
7	1	4	2	2	4	1
11	1	4	9	5	***3***	***3***

Note the table is mirrored as $(-n)^2 = n^2$. Hence, for a reason that is yet to be explained in this book, the prime 3 is somehow tied to 11 when looking for square-roots of 3. The reader can verify that 13, 23, 37, and so forth also have a square-root of 3.

The reader should play around with different pairs (p, q) and flip them around to consider (q, p), there shall appear some symmetry that at first is not obvious.

This relation between primes and square-root in modular arithmetics was first documented to be discovered by Euler, however it took a generation before a complete proof by Gauss appeared. As it turns out, the condition translates into a condition on rings of integers of quadratic extensions!

Definition 50.4.71: Quadratic Residue

Let p be a prime and $n \in \mathbb{Z}$. If there exists an $m \in \mathbb{Z}$ such that $m^2 \equiv n \bmod p$, then n is called a *quadratic residue* mod p.

Whether p has a square root modulo q is the question whether $x^2 - p \equiv 0 \bmod q$ has a solution. Let $K = \mathbb{Q}(\sqrt{p})$ and consider $\mathcal{O}_K/q\mathcal{O}_K$, which is isomorphic to $(\mathbb{Z}/q\mathbb{Z})^2$ as an abelian group. The factorization of $q\mathcal{O}_K$ detects the answer: for odd $q \nmid p$, theorem 50.4.72(3) below shows that $q\mathcal{O}_K$ is a product of two distinct primes exactly when p is a square modulo q, and the same holds for $K = \mathbb{Q}(\sqrt{m})$ with m square-free and $q \nmid m$. By example 50.1.17, $\mathcal{O}_K$ has the integral basis

$$\begin{cases} \{1, \sqrt{m}\} & m \not\equiv 1 \bmod 4 \\ \left\{1, \dfrac{1+\sqrt{m}}{2}\right\} & m \equiv 1 \bmod 4 \end{cases}$$

and $\operatorname{disc}(\mathcal{O}_K) = 4m$ in the first case and $\operatorname{disc}(\mathcal{O}_K) = m$ in the second. Now, take $(p) \subseteq \mathbb{Z}$ a prime ideal. Then we know that either p can split as:

$$p\mathcal{O}_K = \mathfrak{B} \qquad p\mathcal{O}_K = \mathfrak{B}^2 \qquad p\mathcal{O}_K = \mathfrak{B}_1\mathfrak{B}_2$$

and that only m and possibly 2 ramifies.

Theorem 50.4.72: Primes In Quadratic Extensions

Let p be a prime number and $K = \mathbb{Q}(\sqrt{m})$ a quadratic extension where $m \neq 0, 1$ is square-free. Then:

1. If $p \mid m$:
$$p\mathcal{O}_K = (p, \sqrt{m})^2$$
with $(p, \sqrt{m})$ a prime ideal.

2. If m is odd, then 2 splits as:
$$2\mathcal{O}_K = \begin{cases} (2, 1+\sqrt{m})^2 & m \equiv 3 \bmod 4 \\ \left(2, \frac{1+\sqrt{m}}{2}\right)\left(2, \frac{1-\sqrt{m}}{2}\right) & m \equiv 1 \bmod 8 \\ (2) & m \equiv 5 \bmod 8 \end{cases}$$

3. If p is odd and $p \nmid m$:
$$p\mathcal{O}_K = \begin{cases} (p, n+\sqrt{m})(p, n-\sqrt{m}) & m \equiv n^2 \bmod p \\ (p) & m \text{ not a square modulo } p \end{cases}$$

In each case the ideals displayed on the right are distinct prime ideals.

***Proof*:**
All cases come from corollary 50.4.8 with $K = \mathbb{Q}$ and $\mathfrak{p} = p\mathbb{Z}$, applied to a generator θ of K whose minimal polynomial lies in $\mathbb{Z}[x]$. By example 50.1.17, $\mathcal{O}_K = \mathbb{Z}[\sqrt{m}]$ if $m \equiv 2, 3 \bmod 4$, and $\mathcal{O}_K = \mathbb{Z}[\omega] = \mathbb{Z} + \mathbb{Z}\omega$ with $\omega = \frac{1+\sqrt{m}}{2}$ if $m \equiv 1 \bmod 4$. In the second case $\mathbb{Z}[\sqrt{m}] = \mathbb{Z} + 2\mathbb{Z}\omega$, as $\sqrt{m} = 2\omega - 1$, so $[\mathcal{O}_K : \mathbb{Z}[\sqrt{m}]] = 2$. So for $\theta = \sqrt{m}$, with minimal polynomial $x^2 - m$, the index $[\mathcal{O}_K : \mathbb{Z}[\theta]]$ is 1 or 2, and for $\theta = \omega$ when $m \equiv 1 \bmod 4$, with minimal polynomial $x^2 - x + \frac{1-m}{4}$, the index is 1.

Step 1: proof of (1). Take $\theta = \sqrt{m}$. If p is odd, p does not divide the index. If $p = 2$, then m is even and square-free, so $m \equiv 2 \bmod 4$ and the index is 1. As $p \mid m$, $x^2 - m \equiv x^2 \bmod p$, so corollary 50.4.8 gives the prime $(p, \sqrt{m})$ of inertia degree 1 with $p\mathcal{O}_K = (p, \sqrt{m})^2$.

Step 2: proof of (2). If $m \equiv 3 \bmod 4$, take $\theta = \sqrt{m}$, of index 1. Modulo 2, $x^2 - m \equiv x^2 + 1 \equiv (x+1)^2$, so $2\mathcal{O}_K = (2, 1+\sqrt{m})^2$. If $m \equiv 1 \bmod 4$, take $\theta = \omega$. If $m \equiv 1 \bmod 8$, then $\frac{1-m}{4}$ is even and $x^2 - x + \frac{1-m}{4} \equiv x(x-1) \bmod 2$, so $2\mathcal{O}_K = (2, \omega)(2, \omega - 1)$, and $(2, \omega - 1) = (2, \frac{1-\sqrt{m}}{2})$ because $\frac{1-\sqrt{m}}{2} = 1 - \omega$. If $m \equiv 5 \bmod 8$, then $\frac{1-m}{4}$ is odd and $x^2 - x + \frac{1-m}{4} \equiv x^2 + x + 1 \bmod 2$, which has no root in $\mathbb{F}_2$ and so is irreducible, being of degree 2. Then $2\mathcal{O}_K$ is prime, of inertia degree 2.

Step 3: proof of (3). Take $\theta = \sqrt{m}$, whose index 1 or 2 is prime to the odd p. If $m \equiv n^2 \bmod p$, then $n \not\equiv 0$ and $n \not\equiv -n \bmod p$, as $p \nmid m$ and p is odd, so $x^2 - m \equiv (x-n)(x+n) \bmod p$ with distinct factors, and $p\mathcal{O}_K = (p, \sqrt{m} - n)(p, \sqrt{m} + n)$. If m is not a square modulo p, then $x^2 - m$

has no root in $\mathbb{F}_p$ and is irreducible, so $p\mathcal{O}_K$ is prime, completing the proof.

Definition 50.4.73: Legendre Symbol

Let p be an odd prime in $\mathbb{Z}$. Then for $n \in \mathbb{Z}$, $p \nmid n$, the *Legendre symbol* is defined to be:

$$\left(\frac{n}{p}\right) = \begin{cases} 1 & \exists m,\ m^2 \equiv n \bmod p \\ -1 & \text{otherwise} \end{cases}$$

The symbol depends only on the class of n modulo p, since the congruence $m^2 \equiv n \bmod p$ does.

Lemma 50.4.74: Multiplicativity Of The Legendre Symbol

Let p be an odd prime. The squares in $(\mathbb{Z}/p\mathbb{Z})^\times$ form a subgroup S of index 2, and for $a, b \in \mathbb{Z}$ prime to p

$$\left(\frac{ab}{p}\right) = \left(\frac{a}{p}\right)\left(\frac{b}{p}\right)$$

***Proof*:**
The map $(\mathbb{Z}/p\mathbb{Z})^\times \to (\mathbb{Z}/p\mathbb{Z})^\times$, $x \mapsto x^2$, is a homomorphism, as the group is abelian, and its image is S. Its kernel consists of the x with $(x-1)(x+1) = x^2 - 1 = 0$ in the field $\mathbb{Z}/p\mathbb{Z}$, namely $x = 1$ and $x = -1$, which are distinct as p is odd. So $|S| = (p-1)/2$ (theorem 3.5.1, theorem 3.3.1), and S has index 2.

By definition 50.4.73, $\left(\frac{a}{p}\right) = 1$ exactly when the class $\bar{a}$ lies in S. The quotient $(\mathbb{Z}/p\mathbb{Z})^\times/S$ has order 2, so the bijection from it to the group $\{\pm 1\}$ sending S to 1 and the other coset to -1 is an isomorphism. Composing it with the quotient map gives $\bar{a} \mapsto \left(\frac{a}{p}\right)$, which is therefore a homomorphism, as claimed.

Proposition 50.4.75: First Supplement To Quadratic Reciprocity

Let p be an odd prime. Then

$$\left(\frac{-1}{p}\right) = (-1)^{\frac{p-1}{2}}$$

that is, -1 is a quadratic residue modulo p if and only if $p \equiv 1 \bmod 4$.

***Proof*:**
As $i = \zeta_4$, the field $K = \mathbb{Q}(\zeta_4)$ is the quadratic field $\mathbb{Q}(\sqrt{-1})$. Apply corollary 50.4.69 with $n = 4$ and $K = L = \mathbb{Q}(\zeta_4)$, so that $H = \{\bar{1}\}$, to the prime $p \nmid 4$. A prime $\mathfrak{p}$ of K above p has inertia degree the least $f \geq 1$ with $\overline{p^f} = \bar{1}$ in $(\mathbb{Z}/4\mathbb{Z})^\times$, so $f(\mathfrak{p}/p) = 1$ if and only if $p \equiv 1 \bmod 4$.

On the other hand, p is odd and does not divide $m = -1$, so by theorem 50.4.72(3), $p\mathcal{O}_K$ is a product of two distinct primes if -1 is a square modulo p, and is prime otherwise. As $\sum_i e_i f_i = 2$

by proposition 50.4.3, the primes above p have inertia degree 1 in the first case and 2 in the second. So -1 is a square modulo p if and only if $p \equiv 1 \bmod 4$, that is, if and only if $\frac{p-1}{2}$ is even, as we sought to show.

Theorem 50.4.76: Quadratic Reciprocity

Let p, q be distinct odd primes, and let $p^* = (-1)^{\frac{p-1}{2}} p$, so that $p^* = p$ if $p \equiv 1 \bmod 4$ and $p^* = -p$ if $p \equiv 3 \bmod 4$. Then:

1. q is a quadratic residue modulo p if and only if p^* is a quadratic residue modulo q, that is, $\left(\frac{q}{p}\right) = \left(\frac{p^*}{q}\right)$.
2. The two symbols satisfy
$$\left(\frac{q}{p}\right)\left(\frac{p}{q}\right) = (-1)^{\frac{p-1}{2}\frac{q-1}{2}}$$
3. $\left(\frac{q}{p}\right) = \left(\frac{p}{q}\right)$ if $p \equiv 1 \bmod 4$ or $q \equiv 1 \bmod 4$, and $\left(\frac{q}{p}\right) = -\left(\frac{p}{q}\right)$ if $p \equiv q \equiv 3 \bmod 4$.

***Proof*:**
Let $\zeta = \zeta_p$ and $L = \mathbb{Q}(\zeta)$, and for $b \in \mathbb{Z}$ prime to p let $\sigma_b \in \mathrm{Gal}_{\mathbb{Q}}(L)$ be the automorphism with $\sigma_b(\zeta) = \zeta^b$, which corresponds to $\bar{b} \in (\mathbb{Z}/p\mathbb{Z})^\times$ as in corollary 50.4.69. Write $\chi(a) = \left(\frac{a}{p}\right)$ for a prime to p. It depends only on a modulo p, it satisfies $\chi(a)^2 = 1$, and it is multiplicative by lemma 50.4.74.

A square root of p^* in L. Let $g = \sum_{a=1}^{p-1} \chi(a)\zeta^a \in L$. If $p \nmid d$, then $\eta = \zeta^d$ is a pth root of unity other than 1, and $(\eta - 1)\sum_{a=0}^{p-1} \eta^a = \eta^p - 1 = 0$ gives $\sum_{a=1}^{p-1} \zeta^{ad} = -1$. For fixed a, as b runs through $1, \dots, p-1$, the integer $c \in \{1, \dots, p-1\}$ with $b \equiv ac \bmod p$ runs through $1, \dots, p-1$, and $\chi(a)\chi(b) = \chi(a)^2\chi(c) = \chi(c)$. Hence

$$g^2 = \sum_{a=1}^{p-1}\sum_{b=1}^{p-1} \chi(a)\chi(b)\zeta^{a+b} = \sum_{c=1}^{p-1} \chi(c) \sum_{a=1}^{p-1} \zeta^{a(1+c)}$$

The inner sum is $p-1$ for $c = p-1$, and -1 for the other c by the case $d = 1 + c$ of the sum above. By lemma 50.4.74, χ takes the value 1 at exactly half of $1, \dots, p-1$, so $\sum_{c=1}^{p-1} \chi(c) = 0$ and

$$g^2 = (p-1)\chi(-1) - \sum_{c=1}^{p-2} \chi(c) = p\chi(-1) - \sum_{c=1}^{p-1} \chi(c) = p\chi(-1)$$

By proposition 50.4.75, $\chi(-1) = (-1)^{\frac{p-1}{2}}$, so $g^2 = p^*$. As $p^* = \pm p$ is square-free and differs from 0 and 1, the field $K = \mathbb{Q}(g) \subseteq L$ is the quadratic field $\mathbb{Q}(\sqrt{p^*})$, with $\sqrt{p^*} = g$.

The subgroup of K. Let b be prime to p. As a runs through $1, \dots, p-1$, the integer $c \in \{1, \dots, p-1\}$ with $c \equiv ab \bmod p$ runs through $1, \dots, p-1$, and $\chi(a) = \chi(a)\chi(b)^2 = \chi(c)\chi(b)$.

So

$$\sigma_b(g) = \sum_{a=1}^{p-1} \chi(a)\zeta^{ab} = \chi(b)\sum_{c=1}^{p-1} \chi(c)\zeta^c = \chi(b)g$$

As $g^2 = p^* \neq 0$, σ_b fixes g, equivalently fixes $K = \mathbb{Q}(g)$ pointwise, if and only if $\chi(b) = 1$. So the subgroup $H = \mathrm{Gal}_K(L)$ of corollary 50.4.69, viewed in $(\mathbb{Z}/p\mathbb{Z})^\times$, is the subgroup of squares.

1. Let $\mathfrak{q}$ be a prime of K above q. As $q \nmid p$, corollary 50.4.69 gives $f(\mathfrak{q}/q) = 1$ if and only if $\bar{q} \in H$, that is, if and only if q is a quadratic residue modulo p. On the other hand, q is odd and does not divide p^*, so by theorem 50.4.72(3) with $m = p^*$, $q\mathcal{O}_K$ is a product of two distinct primes if p^* is a square modulo q, and is prime otherwise. As $\sum_i e_i f_i = 2$ by proposition 50.4.3, $f(\mathfrak{q}/q) = 1$ in the first case and $f(\mathfrak{q}/q) = 2$ in the second. So $\left(\frac{q}{p}\right) = 1$ if and only if $\left(\frac{p^*}{q}\right) = 1$, and the two symbols, each equal to ± 1, coincide.
2. By lemma 50.4.74 and proposition 50.4.75 for the prime q,

$$\left(\frac{p^*}{q}\right) = \left(\frac{-1}{q}\right)^{\frac{p-1}{2}} \left(\frac{p}{q}\right) = (-1)^{\frac{q-1}{2}\frac{p-1}{2}} \left(\frac{p}{q}\right)$$

   Multiplying (1) by $\left(\frac{p}{q}\right)$ and using $\left(\frac{p}{q}\right)^2 = 1$ gives the product formula.
3. The exponent $\frac{p-1}{2}\frac{q-1}{2}$ is odd exactly when $\frac{p-1}{2}$ and $\frac{q-1}{2}$ are both odd, that is, when $p \equiv q \equiv 3 \bmod 4$. Multiplying (2) by $\left(\frac{p}{q}\right)$ gives (3).

This completes the proof.

Proposition 50.4.77: Second Supplement To Quadratic Reciprocity

Let p be an odd prime. Then

$$\left(\frac{2}{p}\right) = (-1)^{\frac{p^2-1}{8}}$$

that is, 2 is a quadratic residue modulo p if and only if $p \equiv \pm 1 \bmod 8$.

***Proof*:**

Let $\zeta = \zeta_8$, $L = \mathbb{Q}(\zeta)$ and $\theta = \zeta + \zeta^{-1}$. As $\zeta^2 = i$ and $\zeta^{-2} = -i$, $\theta^2 = \zeta^2 + 2 + \zeta^{-2} = 2$, so $K = \mathbb{Q}(\theta) \subseteq L$ is the quadratic field $\mathbb{Q}(\sqrt{2})$, with $\sqrt{2} = \theta \neq 0$. For odd b let $\sigma_b \in \mathrm{Gal}_{\mathbb{Q}}(L)$ be the automorphism with $\sigma_b(\zeta) = \zeta^b$. Then $\sigma_{-1}(\theta) = \zeta^{-1} + \zeta = \theta$. As $\zeta^4 = -1$, $\zeta^3 = -\zeta^{-1}$ and $\zeta^{-3} = -\zeta$, so $\sigma_3(\theta) = \sigma_{-3}(\theta) = \zeta^3 + \zeta^{-3} = -\theta \neq \theta$. So the subgroup $H = \mathrm{Gal}_K(L)$ of corollary 50.4.69 is $\{\pm\bar{1}\}$ inside $(\mathbb{Z}/8\mathbb{Z})^\times = \{\pm\bar{1}, \pm\bar{3}\}$.

As $p \nmid 8$, corollary 50.4.69 shows that a prime of K above p has inertia degree 1 if and only if $\bar{p} \in H$, that is, $p \equiv \pm 1 \bmod 8$. As p is odd and does not divide $m = 2$, theorem 50.4.72(3) shows that $p\mathcal{O}_K$ is a product of two distinct primes if 2 is a square modulo p, and is prime otherwise, so by proposition 50.4.3 the primes above p have inertia degree 1 exactly when 2 is a square modulo p. So 2 is a square modulo p if and only if $p \equiv \pm 1 \bmod 8$. Finally, writing $p = 8k + r$

with $k \in \mathbb{Z}$ and $r \in \{\pm 1, \pm 3\}$,

$$\frac{p^2-1}{8} = 8k^2 + 2kr + \frac{r^2-1}{8}$$

where $\frac{r^2-1}{8}$ is 0 for $r = \pm 1$ and 1 for $r = \pm 3$. So $(-1)^{\frac{p^2-1}{8}} = 1$ exactly when $p \equiv \pm 1 \bmod 8$, as we sought to show.

50.5 Application: Kronecker Weber Theorem

We now apply our finding to Field Theory and find some important consequences' on *Abelian Extension*. This shall also lead to proving one of the central theorems in field theory, The *Kronecker-Weber Theorem*, which states that all finite abelian extensions show up as sub-extensions of Cyclotomic extensions over $\mathbb{Q}$! Since Cyclotomic extensions are generated by roots of unity, every algebraic integers whose Galois group is abelian can be written as a $\mathbb{Q}$-linear combination of roots of unity! For example:

$$\sqrt{5} = e^{2\pi i/5} - e^{4\pi i/5} - e^{6\pi i/5} + e^{8\pi i/5}$$

namely, all square roots of integers may be written as $\mathbb{Q}$-linear combinations of roots of unity! We first give the setting in which we work in:

Definition 50.5.1: Universal Cyclotomic Field and Abelian Closure

1. Let $K^{\mathbf{cycl}} = \bigcup_{n\in\mathbb{N}} K(\zeta_n)$. If $K = \mathbb{Q}$, then:

   $$\mathrm{Gal}(\mathbb{Q}^{\mathbf{cycl}}) = \varprojlim \mathrm{Gal}(\mathbb{Q}(\zeta_n)) = \varprojlim (\mathbb{Z}/n\mathbb{Z})^\times = \hat{\mathbb{Z}}^\times$$

   is the pro-finite group given by the limit of units of cyclic groups.

2. Let K be a field. Then

   $$K^{\mathbf{ab}} \subseteq \overline{K}$$

   is the maximal extension for which $\mathrm{Gal}_K(K^{\mathbf{ab}})$ is abelian.

Proposition 50.5.2: Properties of Abelian Extensions

1. If $L_1, L_2 \subseteq K^{\mathrm{ab}}$ have finite abelian groups, then $\mathrm{Gal}_K(L_1L_2)$ is a finite abelian group.
2. If $G_K = \mathrm{Gal}_K(\overline{K})$ and $H = [G, G]$ (the commutator [closed] subgroup), then

   $$K^{\mathrm{ab}} = \overline{K}^H$$

   with Galois group G_K/H.

***Proof*:**

1. See proposition 20.1.32
2. This comes from the universal property of abelian quotients, see proposition 5.2.3

Note that in general, $K^{\mathbf{cycl}} \subsetneq K^{\text{ab}}$:

Example 50.5.3: Abelian, But Not Cyclotomic

Let $k = \mathbb{Q}(i)$ and $F = \mathbb{Q}(\sqrt{1+2i})/\mathbb{Q}(i)$. Since every quadratic extension is abelian, F is an abelian extension. However, it is not a cyclotomic extension: for if it was a sub-cyclotomic extension, then since $\mathbb{Q}(i)$ is a cyclotomic extension over $\mathbb{Q}$, then $\mathbb{Q}(\sqrt{1+2i})$ would be a cyclotomic extension, but that is not possible since $\mathbb{Q}(\sqrt{1+2i})/\mathbb{Q}$ is not Galois (but all sub-extensions of a cyclotomic extension are necessarily Galois).

It is thus quite interesting that if $K = \mathbb{Q}$, we have the following:

Theorem 50.5.4: Kronecker Weber's Theorem

Let $K = \mathbb{Q}$. Then:

$$\mathbb{Q}^{\mathbf{cycl}} = \mathbb{Q}^{\text{ab}}$$

In other words, every abelian extension of $\mathbb{Q}$ is contained in a cyclotomic extension.

We will first show we can assume $\text{Gal}_{\mathbb{Q}}(K)$ is a p-group for some prime p. For if $\text{Gal}_{\mathbb{Q}}(K)$ is abelian, we have

$$\text{Gal}_{\mathbb{Q}}(K) \cong \bigoplus_{p} G_p$$

where G_p is a p-group.

Proof. **Reduction #1**:

Define $K_{p'} = K^{(\bigoplus_{p \neq p'} G_p)}$. Then $K = K_2 K_3 \cdots$ is the join of all these fields. Hence, if all such fields is inside a Cyclotomic extension, so is K. This can naturally be extended to reduce to cyclic groups in the same manner. □


Next, we show that p is the *only* prime which ramifies in K

Proof. **Reduction #2**:

Assume not. Assume ℓ ramifies in K as well. Let I be the inertia group (does not matter what prime we pick). Then the wield inertia group W is trivial (by group theory). Then by theorem 50.4.64:

$$I \hookrightarrow \mathbb{F}_\ell^\times \qquad I \cong \mathbb{Z}/\ell\mathbb{Z}, \quad e \big| \ell - 1$$

Let $L \in \mathbb{Q}(\mu_\ell)$ be the (unique) extension such that $[L:\mathbb{Q}] = e$. So ℓ totally ramifies in L. Then take:



K and L are abelian, thus so is M. Let I_M be the inertia group of a prime over ℓ. Then

$$I_M \hookrightarrow \mathbb{Z}/e\mathbb{Z} \oplus \mathbb{Z}/\ell\mathbb{Z}$$

Hence

$$I_M \cong \mathbb{Z}/e\mathbb{Z}$$

Let $K' = M^{I_M}$. Then $K' \cap L = \mathbb{Q}$ since nothing ramifies in $K' \cap L$.

Now, $K'L/K'$ has degree at least e, in particular$\geq e$, since ℓ has to ramify (ℓ does not ramify in K', and ramifies in L by e). But then,

$$K'L = M = KL$$

Note that we have not introduced any new ramifications, since no other primes ramify that ramify in L, K. We can afterward inductively remove (if it ramifies, it has to have some inertia group, but it will be trivial in the intermediate extensions).

With this, let's now prove the $p = 2$ case.

Assume $K/\mathbb{Q}$ is abelian $[K:\mathbb{Q}] = 2^n$ and 2 is the only prime which ramifies. I claim that K is cyclotomic.

Without loss of generality, let's assume $\mathbb{Q}(i) \subseteq K$ (just adjoin it if need be). Then $K_0 = K \cap \mathbb{R}$ (fixed field under conjugation). This is still abelian since K is abelian, and $[K:K_0] = 2$, so $K = K_0(i)$. Now, let $K_n/\mathbb{Q}$ be the real cyclotomic field where $\mathrm{Gal}(K_n/\mathbb{Q}) \cong \mathbb{Z}/2^n\mathbb{Z}$ (done it in comments). Consider now

$$M = KK_n$$

Then $\mathrm{Gal}_{\mathbb{Q}}(M) \subseteq \mathbb{Z}/2^n\mathbb{Z} \oplus \mathbb{Z}/2^n\mathbb{Z}$. If $K_n \neq K$, then this Galois group is *not* cyclic (too large order). Therefore, M has ≥ 3 real quadratic subfields (real, since everything is real). But there is only 2 with ramified primes, a contradiction ($\mathbb{Q}(\sqrt{2})$ is the only real quadratic extension in which 2 ramifies). $\square$

Now, for the other primes, we have the following key proposition:

Proposition 50.5.5: Ramification Of Primes in $\mathbb{Z}/n\mathbb{Z}$-Extensions

Let p be an odd prime. Then there exists a unique field $K/\mathbb{Q}$ which is Galois with Galois group $\mathbb{Z}/p\mathbb{Z}$ in which p is the only ramified prime.

***Proof*:**
Let ζ be a pth primitive root of 1, let $L = \mathbb{Q}(\zeta)$. $\pi = 1 - \zeta$. So that $(\pi)^{p-1} = (p)$. Let $\gamma \in \mathcal{O}_L$ be a non pth power. Assume $\gamma \equiv 1 \bmod \pi^p$. Take the field $M = L(\sqrt[p]{\gamma})/L$. Then π is unramified.

Suppose not. Then $\pi\mathcal{O}_M = Q^p$ for some prime Q where $\mathbb{F}_Q \cong \mathbb{F}_{(\pi)} \cong \mathbb{F}_p$. Let δ be such that $\delta^p = \gamma$. Let $r = \frac{\delta-1}{\pi}$. Claim that $r \in \mathcal{O}_M$. Take the conjugates of r over L, i.e. they are

$$\frac{\zeta^i\delta - 1}{\pi} \qquad i \in \mathbb{Z}/p\mathbb{Z}$$

So the minimal polynomial is the product:

$$\prod\left(x - \frac{\zeta^i\delta - 1}{\pi}\right) = \frac{1}{\pi^p}\prod_{i=1}^{p-1}((\pi x - 1) - \zeta^i\delta) = \frac{(\pi x - 1)^p - \gamma}{\pi^p}$$

So this is inside $\mathcal{O}_L[x]$, so r is inside of integers. Thus, there exists some $m \in \mathbb{Z}$ such that $r - m \in \mathbb{Q}$ (because $\mathbb{F}_Q$ is just $\mathbb{F}_p$). But then for all $\sigma \in \mathrm{Gal}_K(M)$, $\sigma(r-m) \in \mathbb{Q}$ since it's the inerta group. But

$$\frac{\zeta\gamma - 1}{\pi} - m \in \mathbb{Q}$$

and so is $\frac{\gamma-1}{\pi} \in \mathbb{Q}$. Subtracting we get

$$\frac{1-\gamma}{\pi}\gamma = \frac{\pi}{\pi}\gamma = \gamma \in \mathbb{Q}$$

But this is a contradiction of our $\gamma \equiv 1 \bmod Q$, as we sought to show.

With this, we can continue the second reduction

Proof. **Reduction #2 cont.**:

By reduction # 2, we only need to work with $K/\mathbb{Q}$ abelian of prime power order p^n, and without loss of generality $K/\mathbb{Q}$ may be assumed to be cyclic since every field is a compositum which have cyclic subgroups.

Now consider $K_n \subseteq \mathbb{Q}(\zeta_{n+1})$ be the field such that


$$[K_n : \mathbb{Q}] = p^n \qquad \mathrm{Gal}(K_n/\mathbb{Q}) \cong \mathbb{Z}/p^n\mathbb{Z}$$

Let $M + KK_n$. In general $\mathrm{Gal}(M/\mathbb{Q}) \hookrightarrow \mathbb{Z}/p^n\mathbb{Z} \oplus \mathbb{Z}/p^n\mathbb{Z}$. If $K \neq K_n$, then like for the $p = 2$ case, this Galois group is not cyclic. Thus, M contains at least $p+1$ subfields which have Galois group $\mathbb{Z}/p\mathbb{Z}$ over $\mathbb{Q}$ in which only p ramifies, a contradiction □

***Proof*:**
Of Kronecker-Weber's Theorem

We shall show that if p is an odd prime, $K/\mathbb{Q}$ is a $\mathbb{Z}/p\mathbb{Z}$ extension, and p is the only prime that ramified in K, then $K \subseteq \mathbb{Q}(\zeta_{p^2})$, which by our earlier reduction shall complete the proof.

Let $\text{Gal}_{\mathbb{Q}}(M) = \langle \sigma \mid \sigma^{p(p-1)} = \text{id} \rangle$, $K = M^{\langle \sigma^p \rangle}$ and $L = M^{\langle \sigma^{p-1} \rangle}$. Consider:



We hat that p is the only prime that ramifies in M. Thus, by Kummer theory, we know that $M = L(\alpha)$ where $\alpha^p = \beta \in L^\times$. Next, we know that

$$\frac{\sigma(\alpha)}{\alpha}$$

is a non-trivial rot of unity. Without loss of generality say that $\frac{\sigma^{p-1}(\alpha)}{\alpha} = \zeta_p$ (so $\langle \sigma^{p-1} \rangle = \text{Gal}_L(M)$). Note that $\sigma(\zeta_p) = \zeta_p^n$, where $\overline{n} \in (\mathbb{Z}/p\mathbb{Z})^\times$ (i.e. is a primitive root).

I claim that

$$M = L\left(\frac{\sigma(\alpha)}{\alpha}\right)$$

For suppose not. Then $\frac{\sigma(a)}{\alpha} \in L$, and

$$\frac{\sigma(\alpha)}{\alpha} = \sigma^{p-1}\left(\frac{\sigma(\alpha)}{\alpha}\right) = \frac{\sigma^p(\alpha)}{\sigma^{p-1}(\alpha)} = \frac{\sigma(\zeta_p\alpha)}{\zeta_p\alpha} \implies 1 = \frac{\sigma(\zeta_p)}{\zeta_p}$$

but that is a contradiction, hence $M = L\left(\frac{\sigma(\alpha)}{\alpha}\right)$.

For the rest of this proof, we write

$$\alpha \mapsto \frac{\sigma(\alpha)}{\alpha} = \alpha' \qquad \beta \mapsto \frac{\sigma(\beta)}{\beta} = \beta'$$

Let P_k, P_L, P_M be the primes ideals above $p\mathbb{Z}$. Take the prime decomposition:

$$\beta\mathcal{O}_L = \prod Q^{n_Q} = P_L^r \cdot \prod_{Q \neq P} Q^{n_Q} \qquad n_Q \in \mathbb{Z}$$

Then:

$$\sigma(\beta)\mathcal{O}_L = P_L^r \prod_{Q \neq P_L} \sigma(Q)^{n_Q}$$

$$\frac{\sigma(\beta)\mathcal{O}_L}{\beta} = \prod_{Q \notin P_L} Q^{m_Q}$$

Hence, P_L does not occur in $\beta\mathcal{O}_L$. Take $\beta'' = \beta' N^P$ and $\alpha'' = \alpha' N$ for $N \in \mathbb{Z}$ such that $\beta'' \in \mathcal{O}_L$ Then:

$$M = L(\alpha'') \qquad (\alpha'')^P = \beta''$$

Now let $\pi = 1 - \zeta_p \in \mathcal{O}_L$ so that $P_L = (\pi)$. Then $\mathbb{F}_{P_L} \cong \mathbb{F}_P$ implies $\beta'' \bmod P_L = m \bmod P_L$ for $m \leq N$. Let $m_0 = m^{-1} \bmod p$, so $\beta'' \to m_0\beta''$ and $\alpha'' \to m_0\alpha''$. Without loss of generality say $\beta'' = 1 \bmod P_L$. Then for some $c \in \mathbb{Z}/p\mathbb{Z}$

$$\beta'' = 1 + c\pi \bmod P_L^2 \qquad \zeta_p = 1 - \pi \bmod P_L^2 \qquad \zeta_p^r = 1 - r\pi \bmod P_L^2 \implies \beta'' = \zeta_p^{-c}\nu$$

where $\nu \equiv 1 \bmod P_L^2$. I claim that $\nu \in (L^\times)^P$, which will imply $M = \mathbb{Q}(\zeta_{p^2})$ and complete the proof. First:

$$\begin{aligned}
(\alpha'')^p &= \beta'' = \zeta_p^{-c}\nu \\
\sigma^{p-1}(\alpha'') &= \alpha''\zeta_p \\
\implies \sigma(\zeta_p) &= \zeta_p^n && n \in (\mathbb{Z}/p\mathbb{Z})^\times \\
\implies \sigma^p(\alpha'') &= \sigma(\sigma^{p-1}(\alpha'')) = \sigma(\alpha''\zeta_p) = \sigma(\alpha'') \cdot \zeta_p^n \\
\implies \sigma^{p-1}((\alpha'')^n) &= (\alpha'')^n\zeta_p^n \\
\implies \sigma^{p-1}\left(\frac{\sigma(\alpha'')}{(\alpha'')^n}\right) &= \frac{\sigma(\alpha'')}{(\alpha'')^n} \\
\implies \frac{\sigma(\alpha'')}{(\alpha'')^n} &\in M^{\langle\sigma^{p-1}\rangle} = L \\
\implies \frac{\sigma(\beta'')}{(\beta'')^n} &\in (L^\times)^P \\
\implies \frac{\sigma(\nu\zeta_p^{-c})}{\nu^n\zeta_p^{-nc}} &\in (L^\times)^p
\end{aligned}$$

Thus $\frac{\sigma(\nu)}{\nu^n} \in (L^\times)^p$.

Next, we claim that $\nu = 1 \bmod P_L^p$. Suppose not. Then let $p^M \| \nu - 1$ where $1 \leq m \leq p-1$, and $\nu = 1 + c\pi^m \bmod P_L^{m+1}$ (where $c \in (\mathbb{Z}/p\mathbb{Z})^\times$). Then by this:

$$\nu^n = 1 + nc\pi^m \bmod P_L^{m+1}$$

hence,

$$\sigma(\pi) = \sigma(1 - \zeta_p) = 1 - \zeta_p^n = (1 - \zeta_p)(1 + \zeta_p + \cdots + \zeta_p^{n-1}) = \pi n \bmod P_L^2$$

implying

$$\sigma(\pi^m) = \pi^m n^m \bmod P_L^{m+1} \implies \sigma(\nu) = 1 + cn^m\pi^m \bmod P_L^{m+1}$$

Note that $n^m \not\equiv n \bmod p$ for $n \in (\mathbb{Z}/p\mathbb{Z})^\times$. Now as a corollary:

$$\frac{\sigma(\nu)}{\nu^m} \equiv 1 + d\pi^m \bmod P_L^{m+1} \qquad d \in \mathbb{Z}/p\mathbb{Z}^\times$$

However,

$$\frac{\sigma(\nu)}{n\nu} = S^p \qquad S \in L$$

where P_L does not occur in S, and:

$$S^p \equiv 1 \bmod P_L \implies S = 1 \bmod P_L$$

Giving us $S = 1 + t$, $P_L \big| t$, so

$$S^P = 1 + pt + \cdots + t^p \equiv 1 \bmod P_L^P$$

a contradiction!

Finally, $L(\sqrt[p]{\nu})/L$ is unramified above P_L. Let

$$F = L(\sqrt[p]{\nu}),\ F \subseteq M(\zeta_{p^2}) \qquad F/Q \text{ abelian}$$

and $I \leqslant \mathrm{Gal}_{\mathbb{Q}}(\mathbb{F})$ where I is the inertia group above P, and $|I| = p-1$, so $F^I/\mathbb{Q}$ is unramified everywhere, namely $F^I = \mathbb{Q}$, so $F = L$. This implies

$$\nu \in (L^\times)^P$$

But then

$$M = \mathbb{Q}(\zeta_{p^2})$$

as we sought to show.

Let us use it in an actual example:

Example 50.5.6: Using Kronecker-Weber

Let $K/\mathbb{Q}$ be a galois extension with Galois group $\mathbb{Z}/5\mathbb{Z}$ whose discriminant is only divisible by $5, 11$, and 31. How many such number fields are there?


Proof. By Kronecker Weber, we know that K is an intermediary field of a Cyclotomic extension:

$$K \subseteq \mathbb{Q}(\zeta_n)$$

We may without loss of generailty assume n is minnimal for which this containment makes sense. Since only $5, 11, 31$, divide the discriminant, we know the discriminant of K is of the form:

$$\mathrm{disc}(\mathcal{O}_K) = 5^a 11^b 31^c$$

which also mean only $5, 11, 31$ ramify in K. Now, I claim that only $5, 11, 31$ divide n and no other number those. For the sake of contradiction, let's say $p \mid n$ but $p \notin \{5, 11, 31\}$. By minimality, we have:



Let $I_{\mathfrak{B}}$ be the inertia group (for any prime $\mathfrak{B}$ lying above p). Since $p \nmid \mathrm{disc}(\mathcal{O}_K)$, p is unramified. If p is unramified in $\mathbb{Q}(\zeta_{n/p})$, then since $\mathbb{Q}(\zeta_{n/p}) \subseteq \mathbb{Q}(\zeta_n)$, we get that $\mathbb{Q}(\zeta_{n/p}) \subseteq \mathbb{Q}(\zeta_n)^{I_p} \subseteq \mathbb{Q}(\zeta_n)$

$$K \subseteq \mathbb{Q}(\zeta_n)^{I_{\mathfrak{B}}} \subseteq \mathbb{Q}(\zeta_{n/p})$$

contradicting minimality of n. Hence, we get $n = 5^a 11^b 31^c$. Thus:

$$\mathrm{Gal}_{\mathbb{Q}}(\mathbb{Q}(\zeta_n)) \cong (\mathbb{Z}/n\mathbb{Z})^\times \cong \mathbb{Z}/4\mathbb{Z} \times (\mathbb{Z}/5^{a-1}\mathbb{Z}) \times \mathbb{Z}/10\mathbb{Z} \times (\mathbb{Z}/11^{b-1}\mathbb{Z}) \times \mathbb{Z}/30\mathbb{Z} \times (\mathbb{Z}/31^{c-1}\mathbb{Z})$$

which now become a counting argument of how many subgroups of index 5 there are, counting the number of intermediary subfields, thus completing the proof. □

50.6 *Modules Over Dedekind Domains

(Useful for alg-geo, theory itself is also really nice. Also $\mathcal{O}_K$-modules appear in the next section)

Lemma 50.6.1: all Ideal co-maximal up to Module Isomorphism

Let I, J be fractional ideals of a Dedekind domain R. Then $I \oplus J \cong_R R \oplus IJ$.

***Proof*:**
Step 1: comaximal integral ideals. Let $D, E \subseteq R$ be ideals with $D+E = R$, and write $1 = d_0 + e_0$ with $d_0 \in D$ and $e_0 \in E$. By theorem 9.6.11, $D \cap E = DE$. The R-linear maps

$$D \oplus E \to DE \oplus R \quad (d,e) \mapsto (de_0 - ed_0, d+e) \qquad DE \oplus R \to D \oplus E \quad (c,r) \mapsto (c + rd_0, -c + re_0)$$

are well defined, as $de_0, ed_0 \in DE$ and $c \in DE \subseteq D \cap E$, and they are mutually inverse: using $d_0 + e_0 = 1$, the first composite sends (d,e) to $(d(e_0+d_0), e(d_0+e_0)) = (d,e)$, and the second sends (c,r) to $(c(e_0+d_0), r(d_0+e_0)) = (c,r)$. So $D \oplus E \cong DE \oplus R$.

Step 2: the general case. Choose $y \in K^\times$ with $yJ \subseteq R$ (corollary 50.2.12). By corollary 50.2.21 there is $x \in K^\times$ such that xI is an ideal with $xI + yJ = R$. Multiplication by a nonzero element of K is an R-module isomorphism, so Step 1 gives

$$I \oplus J \cong xI \oplus yJ \cong R \oplus xyIJ \cong R \oplus IJ$$

completing the proof.

Proposition 50.6.2: Ideals Are Projective

Let R be a Dedekind domain and $I \subseteq R$ an ideal. Then I is a projective R-module

***Proof*:**
The zero module is projective. If $I \neq 0$, corollary 50.2.19 gives a nonzero ideal J and $a \neq 0$ with $IJ = aR$, and $aR \cong R$ by multiplication by a. By lemma 50.6.1,

$$I \oplus J \cong R \oplus IJ = R \oplus aR \cong R^2$$

so I is isomorphic to a direct summand of a free module, and it is projective by theorem 17.2.4, completing the proof.

Proposition 50.6.3: IBN equivalent for Dedekind Domains

Let $I_1, ..., I_n$ be fractional ideals of a Dedekind domain R. Then

$$I_1 \oplus I_2 \oplus \cdots \oplus I_n \cong_R \underbrace{R \oplus R \oplus \cdots \oplus R}_{n-1 \text{ times}} \oplus (I_1 I_2 \cdots I_n)$$

Consequently, if $J_1, \ldots, J_n$ are fractional ideals with $I_1 I_2 \cdots I_n = (a) J_1 J_2 \cdots J_n$ for some $a \in K(R)^\times$, that is, if the products lie in the same class of the class group, then

$$I_1 \oplus I_2 \oplus \cdots \oplus I_n \cong_R J_1 \oplus J_2 \oplus \cdots \oplus J_n$$

***Proof*:**
We induct on n, the case $n = 1$ being trivial. For $n \geq 2$, the induction hypothesis and lemma 50.6.1 give

$$I_1 \oplus \cdots \oplus I_n \cong R^{n-2} \oplus (I_1 \cdots I_{n-1}) \oplus I_n \cong R^{n-2} \oplus R \oplus I_1 \cdots I_n$$

For the consequence, multiplication by a is an isomorphism $J_1 \cdots J_n \cong (a) J_1 \cdots J_n = I_1 \cdots I_n$, so both sums are isomorphic to $R^{n-1} \oplus I_1 \cdots I_n$, completing the proof.

The converse also holds, a theorem of Steinitz: if $I_1 \oplus \cdots \oplus I_n \cong J_1 \oplus \cdots \oplus J_m$, then $n = m$ and the products $I_1 \cdots I_n$ and $J_1 \cdots J_m$ differ by a principal ideal. In particular $R^n \oplus I \cong R^n \oplus J$ exactly when $I = (a)J$ for some $a \in K(R)^\times$. This book does not prove the converse.

Theorem 50.6.4: Classifying Torsion-Free Modules Over Dedekind Domain

Let M be a finitely generated torsion-free R-module over a Dedekind domain R of rank $n \geq 1$, in the sense of definition 12.3.16. Then

$$M \cong R^{n-1} \oplus I$$

for a nonzero ideal I of R, where I may be replaced with any ideal J such that $I = (a)J$ (they belong to the same element in the class group). As a consequence, any finitely generated torsion-free module over a Dedekind domain is projective.

***Proof*:**
Let K be the fraction field of R. Elements of K^n are linearly independent over R exactly when they are linearly independent over K, by clearing denominators, so the rank of a submodule $N \subseteq K^n$ is $\dim_K(KN)$, where KN is its K-span.

Step 1: M lies in R^n. Let $y_1, \ldots, y_n \in M$ be linearly independent and let $m_1, \ldots, m_k$ generate M. By maximality of n, each m_j satisfies $c_j m_j = \sum_i r_{ji} y_i$ with $c_j, r_{ji} \in R$ not all zero, and $c_j \neq 0$ as the y_i are independent. For $c = c_1 \cdots c_k \neq 0$, cM lies in the free module $Ry_1 + \cdots + Ry_n \cong R^n$, and multiplication by c is injective on M, as M is torsion-free. So M is isomorphic to a submodule of R^n, and we may assume $M \subseteq R^n \subseteq K^n$, with $KM = K^n$ as M has rank n.

Step 2: splitting off an ideal. We induct on n. If $n = 1$, then $M \subseteq R$ is a nonzero ideal, and $M \cong R^0 \oplus M$. Let $n \geq 2$ and let $\pi\colon R^n \to R$ be the last coordinate. If $\pi(M) = 0$, then $KM \subseteq K^{n-1} \times 0$, contradicting $KM = K^n$. So $I = \pi(M)$ is a nonzero ideal, projective by proposition 50.6.2, and the sequence $0 \to M' \to M \to I \to 0$ with $M' = \ker(\pi|_M)$ splits (theorem 17.2.4), so $M \cong M' \oplus I$. Here M' is torsion-free, and finitely generated, being a quotient of M through this splitting.

Step 3: the rank of M'. Choose $z_0 \in M$ with $a = \pi(z_0) \neq 0$. For $z \in M$, the element $az - \pi(z)z_0$ lies in M', so $z = a^{-1}(az - \pi(z)z_0) + a^{-1}\pi(z)z_0 \in KM' + Kz_0$. Hence $K^n = KM \subseteq KM' + Kz_0$, so $\dim_K KM' \geq n - 1$, and $KM' \subseteq K^{n-1} \times 0$ gives $\dim_K KM' = n - 1$. So M' has rank $n - 1 \geq 1$.

Step 4: conclusion. By the induction hypothesis, $M' \cong R^{n-2} \oplus I'$ for a nonzero ideal I', and by lemma 50.6.1,

$$M \cong R^{n-2} \oplus I' \oplus I \cong R^{n-2} \oplus R \oplus I'I = R^{n-1} \oplus I'I$$

with $I'I$ a nonzero ideal. So for every $n \geq 1$, $M \cong R^{n-1} \oplus I_0$ for a nonzero ideal I_0, namely $I_0 = M$ if $n = 1$ and $I_0 = I'I$ if $n \geq 2$. If $I_0 = (a)J$, then multiplication by $a \neq 0$ is an isomorphism $J \cong I_0$, so I_0 may be replaced by J. Finally, corollary 50.2.19 gives a nonzero ideal J' and $b \neq 0$ with $I_0J' = bR \cong R$, and lemma 50.6.1 gives $I_0 \oplus J' \cong R \oplus I_0J' \cong R^2$, so $R^{n-1} \oplus I_0$ is a direct summand of R^{n+1} and is projective (theorem 17.2.4). A torsion-free module of rank 0 is 0, as any nonzero element is linearly independent, completing the proof.

50.7 *Geometric Idea: 1-Dimensional Schemes

See Neukirch, and put orders here too for their geometric interpretation. I think it is important to include (especially once this chapter becomes its own book) since (to me) this explains why ramification happens. We naturally cannot prove the Riemann-Hurwitz Formula here, but this still is very interesting.

50.7.1 Localization of Dedekind Domains

For the motivation to CFT

50.7.2 Orders: Curves with Singularities

This entire section is completely inspired by Neukirch p.72

should also include how if finite L/K then $\mathrm{Spec}\,(\mathcal{O}_L)$ is the normalization of $\mathrm{Spec}\,(\mathcal{O}_K[\alpha])$ where $L = K(\alpha)$. And I would really love a discussion linking $\mathrm{Spec}\,(\mathcal{O}_L)$ to the "generic point" $\mathrm{Spec}\,(L)$ and to $y - m_{\alpha,K}(x)$ where $m_{\alpha,K}(x)$ is the minimal polynomial of L/K

All smooth 1-dimensional curves correspond to Dedekind domains. However, there are some curves with singularities. These curves are associated to sub-rings of Dedekind domains called *orders*

Definition 50.7.1: Order

Let $K/\mathbb{Q}$ be a number field of degree n. Then an order of K is a subring of $\mathcal{O}_K$ which contains an integral basis of length n. The ring $\mathcal{O}_K$ is called a *maximal order*.

By the above definition, an order is of the form:

$$\mathbb{Z}[\alpha_1, ..., \alpha_n]$$

where $K = \mathbb{Q}(\alpha_1, ..., \alpha_n)$, which motivates why $\mathcal{O}_K$ is the maximal order. It is the maximal ring with this property. This also implies that orders need not be normal, hence an order is a one-dimensional Noetherian integral domain (prime remain maximal as if $a \in \mathfrak{p} \cap \mathbb{Z}$ then $a\mathcal{O} \subseteq \mathfrak{p} \subseteq \mathcal{O}$ that is $\mathfrak{p}$ and $\mathcal{O}$ have the same rank n, and thus $\mathcal{O}/\mathfrak{p}$ is a finite integral domain, showing $\mathfrak{p}$ is maximal) . An example of an order is $\mathbb{Z} = \mathbb{Z}(\sqrt{5})$. Many order's naturally are as "rings of multipliers. For example if $\alpha_1, .., \alpha_n$ is a basis for $K/\mathbb{Q}$ and $M = \sum_i \mathbb{Z}\alpha_i$, then

$$\mathcal{O}_M = \{\alpha \in K \mid \alpha M \subseteq M\}$$

is an order.

It is important that we re-prove the Chinese remainder

Here

As orders are not Dedekind domain in general, *not* all ideals are invertible. This also means that the collection of fractional ideals does not form a group.

Proposition 50.7.2: Invertible Fracitonal Ideals

Let I be a fractional ideal of a Noetherian domain R. Then I is invertible iff its localization at every maximal ideal of R is invertible, equivalently, iff its localization at every prime ideal of R is invertible.

***Proof*:**

Write $K = K(R)$, and for a multiplicative set $S \subseteq R \setminus \{0\}$ and an R-submodule $M \subseteq K$ let $S^{-1}M = M \cdot S^{-1}R \subseteq K$. Write $M_{\mathfrak{p}}$ when $S = R \setminus \mathfrak{p}$. Recall from definition 50.2.9 that $(R : I) = \{x \in K \mid xI \subseteq R\}$, and note $I(R : I) \subseteq R$ always, since $x \in (R : I)$ and $y \in I$ give $xy \in R$. The product $I(R : I)$ is an R-submodule of R, that is an ideal.

First, $(IJ)_S = I_S J_S$ for fractional ideals I and J: an element of $I_S J_S$ is a finite sum $\sum_k (i_k/s_k)(j_k/t_k)$, and putting the terms over the common denominator $\prod_k s_k t_k$ exhibits it in $(IJ)_S$, while the reverse inclusion is immediate. Second, $(R : J)_S = (R_S : J_S)$ for a nonzero fractional ideal J. For $\subseteq$, if $xJ \subseteq R$ then $(x/s)J_S \subseteq R_S$. For $\supseteq$, let $x \in K$ satisfy $xJ_S \subseteq R_S$. Since R is Noetherian, $J = (j_1, \ldots, j_r)$ is finitely generated, and each $xj_k \in R_S$ gives $s_k \in S$ with $s_k x j_k \in R$. With $s = s_1 \cdots s_r$ we get $sxJ \subseteq R$, so $sx \in (R : J)$ and $x \in (R : J)_S$.

Suppose I is invertible, say $IJ = R$ for a fractional ideal J. Then $jI \subseteq R$ for every $j \in J$, so $J \subseteq (R : I)$ and

$$R = IJ \subseteq I(R : I) \subseteq R$$

forcing $I(R : I) = R$. Localising at any prime $\mathfrak{p}$ and applying the two identities gives $I_{\mathfrak{p}}(R_{\mathfrak{p}} : I_{\mathfrak{p}}) = (I(R : I))_{\mathfrak{p}} = R_{\mathfrak{p}}$, so $I_{\mathfrak{p}}$ is invertible. This covers every prime, hence every maximal ideal.

Conversely, suppose $I_{\mathfrak{m}}$ is invertible for every maximal ideal $\mathfrak{m}$. By the paragraph proved above,

$I_{\mathfrak{m}}(R_{\mathfrak{m}} : I_{\mathfrak{m}}) = R_{\mathfrak{m}}$ for every such $\mathfrak{m}$. If the ideal $I(R : I)$ were proper it would lie in some maximal ideal $\mathfrak{m}$, and then

$$R_{\mathfrak{m}} = I_{\mathfrak{m}}(R_{\mathfrak{m}} : I_{\mathfrak{m}}) = (I(R : I))_{\mathfrak{m}} \subseteq \mathfrak{m}R_{\mathfrak{m}} \neq R_{\mathfrak{m}}$$

a contradiction. So $I(R : I) = R$ and I is invertible. Finally, if $I_{\mathfrak{p}}$ is invertible at every prime $\mathfrak{p}$ then in particular at every maximal ideal, so the prime version of the criterion follows from the maximal one.

Example 50.7.3: non-invertible ideal of an order
put this example here

(I want this build up here)

Definition 50.7.4: Picard Group Of An Order

Let $J(\mathcal{O})$ be the collection of invertible ideals and $P(\mathcal{O})$ the fractional principal ideals. Then

$$\operatorname{Pic}(\mathcal{O}) = \frac{J(\mathcal{O})}{P(\mathcal{O})}$$

A lot more to be said.

The Picard group ignore s ideals that are not invertible. Another approach that gives some useful results is to define the following for A Dedekind domain:

$$\operatorname{Div}(\mathcal{O}) = \mathcal{O}_{\mathfrak{p}}\mathbb{Z}\mathfrak{p}$$

Then $\operatorname{Div}(\mathcal{O})$ is isomorphic to the ideal group. For an order, the divisor group shall be a quotient of this group. We would then need to define the divisor elements, which gives the divisor class group/chow group.

50.8 *Profinite Groups

(original title: infinite galois extensions)

I moved this from the galois theory chapter. I actually want to make this its own chapter when I extract these notes into their own book so that the many books that use profinite groups can reference this namely: the class field theory book, the p-adic rep book, and the galois cohomology book.

In this section, we shall explore the case of infinite separable normal extensions L/K. This section uses topological groups [39, Topological Group] and the following facts of point-set topology from *Topology* [39]: Tychonoff's theorem [39, Tychonoff's Theorem], that closed subsets of compact spaces are compact [39, closed subsets of compact spaces are compact], that compact Hausdorff spaces are normal [39, Compact Hausdorff Spaces Are Normal], that continuous images and closures of connected sets are connected [39, Continuous Images of Connected Spaces Are Connected] [39, Connectedness Survives Adding Limit Points], and that a continuous bijection from a compact space onto a Hausdorff space is a homeomorphism [39, making continuous function homeomorphisms]. Most of this material will be important for a course in *Class Field Theory* [77].

In this section, a Galois extension is a normal separable extension, where the finiteness condition is dropped. We may want to keep the galois correspondence between the fixed fields and the subgroups, however there are simply way too many subgroups. Consider

$$\overline{\mathbb{Q}}/\mathbb{Q} \qquad \text{and} \qquad \text{Gal}_{\mathbb{Q}}(\overline{\mathbb{Q}})$$

Then the reader should check that there are only countably many intermediary extension of degree 2 corresponding to the extensions of the form $\mathbb{Q}(\sqrt{\alpha})/\mathbb{Q}$ where α is either a prime p, ip, or a finite compositum of such elements. However, there are uncountably many index two subgroups. To see this, consider $\varphi_S : \text{Gal}_{\mathbb{Q}}(\overline{\mathbb{Q}}) \to \mathbb{Z}/2\mathbb{Z}$ where S is a finite collection of primes where if σ fixes each $\sqrt{p}$. Then $\varphi_S(s) = 0$, and it is 1 otherwise. This is a group-homomorphism, as the composition of two maps that fix each $\sqrt{p}$ for $p \in S$ shall still fix those primes. Furthermore, There are certainly always morphisms τ such that $\varphi_S(\tau) = 1$ for each finite subset S. Thus, each φ_S is a surjective homomorphism, whose kernel is index 2. But then, there are uncountably distinct $\ker(\varphi_S)$. In fact, we do not even need S to be finite (exercise). In this case, we shall even have index two subgroups whose fixed field corresponds to $\mathbb{Q}$!

The reader may feel that there is some simple solutions that can be found, as it seems there are many galois subgroups corresponding to an intermediary. Indeed, we may still recover the galois correspondence if we appropriately limit which subgroups of $\text{Gal}_{\mathbb{Q}}(\overline{\mathbb{Q}})$ we consider (and more generally which subgroups of $\text{Gal}_K(L)$ we consider). This is done by taking the *Krull topology* on the galois group, which we shall naturally derive by first taking the *profinite topology*. The profinite topology shall make us limit our attention to normal subgroups of finite index (namely, such subgroups shall be open in the profinite topology), while in the Krull topology we shall limit our attention to normal subgroups of finite index which also have a [finite] galois group (namely, such subgroups shall be open in the Krull topology). Both of these topologies are achieved by showing that the infinite galois group, as a topological group, is a profinite group. The main idea is that all of the information of infinite galois extension is in fact fully captured by the finite normal extension, due to the fact galois groups represent the relationship of polynomials (where an infinite galois groups stores the information of infinitely many polynomials).

50.8.1 Profinite Groups

In this section, a brief introduction to profinite groups is given. This is not an in-depth coverage, but rather it gives enough information to describe infinite galois theory.

Definition 50.8.1: Profinite Group

Take an inverse system of finite groups with the discrete topology. Then a *profinite group* is a topological group that is the limit of the system. Given any topological group G, we can take its *profinite completion* by taking:

$$\widehat{G} = \varprojlim_N G/N$$


where N ranges over all finite index open normal subgroups ordered by containment.

Any group G can be given a topology by given it the profinite topology given by taking the cosets of finite-index normal subgroups as a basis. The reader should check that if G is a topological group and $\widehat{G}$ is its profinite completion, then the continuous homomorphism $\varphi : G \to \widehat{G}$ can be shown that G is dense in $\widehat{G}$.

Example 50.8.2: Profinite Groups

1. Let G be finite. Then all normal subgroups have finite index and there are finitely many. It follows that $G \cong \widehat{G}$.
2. Let $G = \mathbb{Z}$. Then
$$\widehat{Z} = \varprojlim_n \mathbb{Z}/n\mathbb{Z} \cong \prod_p \mathbb{Z}_p$$
where $\mathbb{Z}_p = \varprojlim_n \mathbb{Z}/p^n\mathbb{Z}$ is the p-adic completion of $\mathbb{Z}$.
3. Take $G = \mathbb{Q}$. Then $\mathbb{Q}$ has only one finite-index normal subgroup, namely itself. Hence $\widehat{\mathbb{Q}} = \{1\}$.

The above examples show that the map $\varphi : G \to \widehat{G}$ could be injective, surjective, both. The map will be injective if the intersections of all finite-index open normal subgroups of G is trivial (where we would then say G is residually finite). The completion comes equipped with a natural universal property where a continuous homomorphism $\varphi : G \to H$ with H a profinite group has a unique continuous homomorphism such that the following diagram commutes:



A word on strongly complete? MIT notes p.275 Remark 26.15

Theorem 50.8.3: Characterizing Profinite Groups

A topological group is profinite if and only if it is a totally disconnected compact group

***Proof*:**

Step 1: profinite groups are compact and totally disconnected. An isomorphism of topological groups preserves both properties, so by definition 50.8.1 we may take $G = \varprojlim_{i\in I} G_i \subseteq P = \prod_{i\in I} G_i$ for an inverse system of finite discrete groups G_i over a directed set I, with transition maps $\varphi_{ji} \colon G_j \to G_i$ for $i \leq j$ and projections $p_i \colon P \to G_i$. Each G_i is finite, hence compact, so P is compact by Tychonoff's theorem. The space P is Hausdorff: two distinct points differ in some coordinate i, and the preimages under p_i of the two values are disjoint open sets. For $i \leq j$ the set
$$C_{ij} = \{g \in P \mid \varphi_{ji}(p_j(g)) = p_i(g)\}$$
is closed, since its complement is the union, over the pairs $(a, b) \in G_j \times G_i$ with $\varphi_{ji}(a) \neq b$, of the open sets $p_j^{-1}(a) \cap p_i^{-1}(b)$. So $G = \bigcap_{i\leq j} C_{ij}$ is closed in P, hence compact, as a closed subset of a compact space. If $C \subseteq G$ is connected, then each $p_i(C)$ is a connected subset of the discrete space G_i, being a continuous image of a connected set, so it is a single point. Points of C therefore agree in every coordinate, and C has at most one point. So G is totally disconnected.

Step 2: a compact totally disconnected group is Hausdorff. Let G be a compact totally disconnected group. The closure of the connected set $\{1\}$ is connected, hence equal to $\{1\}$, so

$\{1\}$ is closed, and so is every $\{g\}$, because left translation is a homeomorphism. Let $x \neq y$ in G. Then $G \setminus \{x^{-1}y\}$ is an open neighbourhood of 1, and continuity of $(a,b) \mapsto ab^{-1}$ at $(1,1)$ gives an open neighbourhood V of 1 with $VV^{-1} \subseteq G \setminus \{x^{-1}y\}$. If $xv = yw$ with $v, w \in V$, then $x^{-1}y = vw^{-1} \in VV^{-1}$, which is impossible. So xV and yV are disjoint open sets containing x and y.

Step 3: every open neighbourhood of 1 *contains a clopen neighbourhood of* 1. Let Y be the intersection of all clopen subsets of G containing 1, a closed set. Suppose $Y = A \cup B$ with A and B disjoint and closed in Y, hence closed in G, and $1 \in A$. A compact Hausdorff space is normal, so there are disjoint open sets $U_A \supseteq A$ and $U_B \supseteq B$. The closed sets $C \setminus (U_A \cup U_B)$, for C clopen with $1 \in C$, have empty intersection, because $Y \subseteq U_A \cup U_B$. By compactness finitely many of them already have empty intersection, and the intersection C of the corresponding clopen sets is clopen, contains 1 and lies in $U_A \cup U_B$. Then $C \cap U_A$ is open, and it equals $C \setminus U_B$, which is closed. So $C \cap U_A$ is a clopen set containing 1, hence $Y \subseteq C \cap U_A$, and $B \subseteq Y \subseteq U_A$. As $B \subseteq U_B$ and $U_A \cap U_B = \emptyset$, B is empty. So Y is connected, and $Y = \{1\}$ because G is totally disconnected. Now let U be an open neighbourhood of 1. The closed sets $C \setminus U$, for C clopen with $1 \in C$, have intersection $Y \setminus U = \emptyset$, so by compactness finitely many of them do, and the intersection of the corresponding clopen sets is a clopen neighbourhood of 1 inside U.

Step 4: every clopen neighbourhood C of 1 *contains an open normal subgroup.* The set C is closed in the compact space G, hence compact. For each $c \in C$, the set C is an open neighbourhood of $c \cdot 1$, so continuity of multiplication at $(c, 1)$ gives open sets $W_c \ni c$ and $V_c \ni 1$ with $W_c V_c \subseteq C$. Finitely many $W_{c_1}, \ldots, W_{c_k}$ cover C, and $V = \bigcap_i \left(V_{c_i} \cap V_{c_i}^{-1}\right)$ is an open neighbourhood of 1 with $V = V^{-1}$ and $CV \subseteq C$. By induction $CV^r \subseteq C$ for every $r \geq 1$, where V^r is the set of products of r elements of V. The union $H = \bigcup_{r \geq 1} V^r$ is a subgroup, being closed under products and, as $V = V^{-1}$, under inverses. It is open, each $V^r = \bigcup_{g \in V^{r-1}} gV$ being a union of translates of V. Since $1 \in C$, $H \subseteq CH \subseteq C$. The left cosets of H are disjoint open sets covering G, so by compactness there are finitely many of them, and H has finite index. The conjugate gHg^{-1} depends only on the coset gH, so $N = \bigcap_{g \in G} gHg^{-1}$ is a finite intersection of open subgroups. It is an open normal subgroup with $N \subseteq H \subseteq C$.

Step 5: G is the limit of its finite quotients. Let $\mathcal{N}$ be the set of open normal subgroups of G, directed by reverse inclusion, as $N_1 \cap N_2 \in \mathcal{N}$ for $N_1, N_2 \in \mathcal{N}$. Each G/N with $N \in \mathcal{N}$ is finite, by the coset argument of Step 4, and carries the discrete topology. The map

$$\Phi \colon G \to \varprojlim_{N \in \mathcal{N}} G/N \qquad g \mapsto (gN)_N$$

is a group homomorphism. It is continuous, because each $G \to G/N$ is: the preimage of any subset of G/N is a union of cosets of the open subgroup N. It is injective: for $g \neq 1$, the set $G \setminus \{g\}$ is an open neighbourhood of 1 by Step 2, it contains a clopen neighbourhood of 1 by Step 3, and that contains some $N \in \mathcal{N}$ by Step 4, so $g \notin N$. It is surjective: let $(x_N N)_N$ be a compatible family. Each coset $x_N N$ is closed, its complement being a union of cosets of the open subgroup N. For $N_1, \ldots, N_k \in \mathcal{N}$ and $N = N_1 \cap \cdots \cap N_k$, compatibility gives $x_N N_i = x_{N_i} N_i$, so $x_N \in x_{N_1} N_1 \cap \cdots \cap x_{N_k} N_k$. By compactness the intersection of all the cosets $x_N N$ contains some g, and then $\Phi(g) = (x_N N)_N$. Finally, $\varprojlim_N G/N$ is Hausdorff, as a subspace of a product of discrete spaces (Step 1), and a continuous bijection from a compact space onto a Hausdorff space is a homeomorphism. So Φ is an isomorphism of topological groups, and G is profinite,

completing the proof.

Corollary 50.8.4: Distinguishing Profinite Completion

Let G be a profinite group. Then G is naturally isomorphic to its profinite completion, or even stronger:

$$G \cong \varprojlim G/U$$

where U ranges over all open normal subgroups ordered by containment.
Moreover G is *strongly complete*, meaning that the natural map from G to the profinite completion of its underlying abstract group is an isomorphism, if and only if every finite index subgroup of G is open

***Proof*:**
By definition 50.8.1 write $G = \varprojlim_{i\in I} G_i \subseteq \prod_i G_i$ for an inverse system of finite discrete groups over a directed index set I. Let $p_i : G \to G_i$ be the projections and $N_i = \ker p_i$, an open normal subgroup since p_i is continuous and G_i is discrete. If $j \geq i$ then the transition map carries $p_j(g)$ to $p_i(g)$, so $N_j \subseteq N_i$. A basic open neighbourhood of 1 in the subspace topology of $\prod_i G_i$ is a finite intersection $\bigcap_{i\in F} N_i$, and by directedness there is j with $j \geq i$ for all $i \in F$, so the N_i form a neighbourhood basis at 1.

By theorem 50.8.3 the group G is compact, so every open subgroup U has finite index: its cosets form an open cover of G by disjoint sets, and a finite subcover must consist of all of them. Any open normal subgroup U is a neighbourhood of 1, hence contains some N_i, so the family $\{N_i\}$ is cofinal among open normal subgroups and $\varprojlim_U G/U = \varprojlim_i G/N_i$. The natural map $G \to \varprojlim_i G/N_i$ is injective because $\bigcap_i N_i = \{1\}$, and it is surjective because a compatible family in $\prod_i G/N_i \cong \prod_i p_i(G)$ is a compatible family in $\prod_i G_i$, hence a point of $\varprojlim_i G_i = G$. It is continuous, since each $G \to G/N_i$ is continuous for N_i open, and a continuous bijection from a compact space to a Hausdorff space is a homeomorphism. So $G \cong \varprojlim_U G/U$ through the natural map, and since every open normal subgroup has finite index, this limit is the profinite completion of the topological group G.

For the second statement, let $\widehat{G}_{\text{abs}} = \varprojlim_N G/N$ where N ranges over *all* finite index normal subgroups of G, and let $\varphi : G \to \widehat{G}_{\text{abs}}$ be the natural map. Every open normal subgroup has finite index, so forgetting the coordinates indexed by the non-open N gives a continuous homomorphism $\psi : \widehat{G}_{\text{abs}} \to \varprojlim_U G/U = G$ with $\psi \circ \varphi = \mathrm{id}_G$.

If every finite index subgroup of G is open, the two index families coincide, $\widehat{G}_{\text{abs}} = \varprojlim_U G/U$, and φ is the isomorphism of the first part. Conversely, suppose φ is an isomorphism. Then $\psi = \varphi^{-1}$ is a continuous bijection, and $\widehat{G}_{\text{abs}}$ is compact, being a closed subgroup of the product of the finite discrete groups G/N, while G is Hausdorff. So ψ, and hence φ, is an isomorphism of topological groups. Let $H \leqslant G$ have finite index and set $N = \bigcap_{g\in G} gHg^{-1}$. The map $g \mapsto gHg^{-1}$ factors through the cosets of the normaliser of H, which contains H and therefore has finite index, so there are finitely many conjugates, each of finite index. Their intersection N again has finite index, because G embeds into the product of the finitely many finite coset spaces, and N is normal by construction. The subgroup $\ker\left(\widehat{G}_{\text{abs}} \to G/N\right)$ is open by construction and its preimage under φ is N, because $G \to \widehat{G}_{\text{abs}} \to G/N$ is the quotient map. Hence N is open, and H, a union of cosets of N, is open as well.

50.8.2 Infinite Galois Theory

Let us now find which topology to put on galois groups. Let us first make sure that the notion of there being a correspondence between subfields and fixed fixed fields of subgroups of galois group is still well-defined

Lemma 50.8.5: Fixed Field Infinite Extension

Let L/K be a galois extension with galois group $G = \mathrm{Gal}_K(L)$ and let F be an intermediate field. Then $H = \mathrm{Gal}_F(L)$ has fixed field F. If moreover F/K is normal, then $H \trianglelefteq G$ is a normal subgroup of G, and there is a short exact sequence:

$$1 \to \mathrm{Gal}_F(L) \to \mathrm{Gal}_K(L) \to \mathrm{Gal}_K(F) \to 1$$

which implies:

$$G/H \cong \mathrm{Gal}_K(F)$$

***Proof*:**
Let $\overline{L}$ be an algebraically closed field containing L, which exists by lemma 19.5.5 and the chain construction before it.

Step 1: extending embeddings. Let E be an intermediate field of L/K and $\rho\colon E \to L$ a field homomorphism fixing K. The extension L/E is algebraic and $\overline{L}$ is algebraically closed, so, regarding $\overline{L}$ as an extension of E through ρ, lemma 19.5.7 gives a field homomorphism $\sigma\colon L \to \overline{L}$ restricting to ρ on E. For $\beta \in L$ with minimal polynomial f over K, $\sigma(\beta)$ is a root of f, because σ fixes K. Since L/K is normal and f has the root β in L, f splits over L (definition 19.5.12), so $\sigma(\beta) \in L$. Moreover σ maps the finite set of roots of f in L injectively into itself, hence onto itself, so $\beta \in \sigma(L)$. Thus σ is an automorphism of L fixing K, that is $\sigma \in G$, and it extends ρ.

Step 2: the restriction map, for normal F/K. Suppose F/K is normal, and let $\sigma \in G$ and $\beta \in F$ with minimal polynomial f over K. As F/K is normal, f splits over F. Since σ fixes K, it maps the finite set of roots of f in F injectively, hence bijectively, to itself. So $\sigma(F) = F$ and $\sigma|_F \in \mathrm{Gal}_K(F)$. The map $G \to \mathrm{Gal}_K(F)$, $\sigma \mapsto \sigma|_F$, is a group homomorphism with kernel $\mathrm{Gal}_F(L) = H$, which is therefore normal in G. It is surjective: given $\tau \in \mathrm{Gal}_K(F)$, Step 1 with $E = F$ and $\rho = \tau$ gives $\sigma \in G$ with $\sigma|_F = \tau$. This is the short exact sequence of the statement, and $G/H \cong \mathrm{Gal}_K(F)$ by theorem 3.5.1.

Step 3: the fixed field of H is F. Every element of H fixes F, so $F \subseteq L^H$. Let $\alpha \in L \setminus F$ and let g be its minimal polynomial over F, which has degree at least 2. It divides the minimal polynomial of α over K, which has distinct roots, as L/K is separable, and splits over L, as L/K is normal. So g has a root $\alpha' \in L$ with $\alpha' \neq \alpha$. By theorem 19.2.27 there is an isomorphism $F(\alpha) \to F(\alpha')$ fixing F and sending α to α', and Step 1 with $E = F(\alpha)$ extends it to some $\sigma \in G$. Then σ fixes F, so $\sigma \in H$, while $\sigma(\alpha) = \alpha' \neq \alpha$. So $\alpha \notin L^H$, and $L^H = F$, completing the proof.

Hence, every normal subextension has (at least one) corresponding normal subgroup. However, there are many normal subgroups whose fixed field F is *not* equal to $\mathrm{Gal}_F(L)$, but is contained in $\mathrm{Gal}_F(L)$

The index two example of $\text{Gal}_{\mathbb{Q}}(\overline{\mathbb{Q}})$ is the prototypical example, where there are uncountably many index 2 subgroups $H \leqslant \text{Gal}_{\mathbb{Q}}(\overline{\mathbb{Q}})$ whose fixed field is $\mathbb{Q}$ but naturally H is not the galois subgroup of $\overline{\mathbb{Q}}/\mathbb{Q}$, nor is it the galois group of $\overline{\mathbb{Q}}/K$ for any subextension $K/\mathbb{Q}$. Hence, the following topology limits our attention to the right groups:

Definition 50.8.6: Krull Topology On Galois Group

Let L/K be a Galois (i.e. normal separable) extension with $G = \text{Gal}_K(L)$. Then the *Krull Topology* on G is the basis given by the basis consisting of cosets of the subgroups

$$H_F = \text{Gal}_F(L)$$

where F ranges over finite normal extensions of K in L.

In this topology, every open normal subgroups has finite index, but not every normal subgroup of finite index is open (think $\text{Gal}_{\mathbb{Q}}(\overline{\mathbb{Q}})$ again). Hence, this topology is (strictly) coarser than the porfinite topology, however it is still a profinite group:

Proposition 50.8.7: Galois Group is Profinite Group

Let L/K be a galois extension. Then under the Krull topology, the restriction maps induce a natural isomorphism of topological groups:

$$\text{Gal}_K(L) \cong \varprojlim_F \text{Gal}_K(F)$$

where F ranges over finite galois extension of K in L. Hence, $\text{Gal}_K(L)$ is a profinite group whose open normal subgroups are those of the form $\text{Gal}_F(L)$ for some finite normal extension F/K.

***Proof*:**
Let's first show the map is bijective. For injectivity, for every $\alpha \in L$ it is algebraic over K, and hence liens ins some finite normal subextensions F/K, and so every automorphism in $\text{Gal}_K(L)($ is uniquely determined by all its restrictions to finite normal F/K, showing φ is injective. For surjectivity, given any $(\sigma_F) \in \varprojlim_F \text{Gal}_K(F)$, we may define a corresponding $\sigma \in \text{Gal}_K(L)$ that maps to it by point-wise defining:

$$\sigma(\alpha) := \sigma_F(\vec{\alpha})$$

where F is the normal closure of $K(\alpha)$. This map is well-defined by construction of the inverse limit, giving surjectivity.

For continuity, Letting $G = \text{Gal}_K(L)$ and $H_F = \text{Gal}_F(L)$, we can view φ as the natural continuous map:

$$\varphi : G \to \varprojlim G/H_F$$

Finally, to show the inverse is continuous, we will show the equivalent of φ being an open map, which translates to showing that φ maps open subgroups $H \subseteq G$ (i.e. the basis) to open subsets in $\varprojlim G/H_F$. Taking $H = \text{Gal}_F(L)$, we get:

$$\varphi(H) = \{(\sigma_E) \mid \sigma_{E_{E\cap F}} = \text{id}_{E\cap F}\} = \pi_F^{-1}(\text{id}|_F)$$

as E/K ranges over all finite normal subextension of L/K and π_F is the projection from the limit to $\mathrm{Gal}_K(F)$. Then the singleton set $\{\mathrm{id}|_F\}$ is open in the discrete group $\mathrm{Gal}_K(F)$, and so its inverse is open, completing the proof.

Theorem 50.8.8: Fundamental Theorem of Galois Theory, Infinite Extensions

Let L/K be a galois extension with galois group $G = \mathrm{Gal}_K(L)$ endowed with the Krull topology. Then the maps

$$F \mapsto \mathrm{Gal}_F(L) \qquad H \mapsto L^H$$

define inclusion reversing bijections between subextensions F/K of L/K and closed subgroups H of G. Thus, subextensions of finite degree n correspond to subgroups of finite index n, and normal subextensions F/K correspond to normal subgroups $H \leqslant G$ such that as topological groups:

$$\mathrm{Gal}_K(F) \cong G/H$$

***Proof*:**
First off, recall that every open subgroup is clopen, as the compliment is the union of non-trivial cosets, and so closed subgroups of finite index are open. Next, the correspondence between finite galois subextensions F/K and finite index closed normal subgroups H is given by proposition 50.8.7, and furthermore we have $[F : K] = [G : H]$ as $G/H \cong \mathrm{Gal}_K(F)$ by lemma 50.8.5.

For the correspondence maps, if F/K is any finite subextension with normal closure E, then $H = \mathrm{Gal}(L/F)$ contains the normal subgroup $N = \mathrm{Gal}(L/E)$ with finite index. The subgroup N is open and therefore closed, thus H is closed since it is a finite union of cosets of N. The fixed field of H is F by lemma 50.8.5, thus finite subextensions correspond to closed subgroups of finite index. Conversely, every closed subgroup H of finite index has a fixed field F of finite degree, since the intersection of its conjugates is a normal closed subgroup $N = \mathrm{Gal}(L/E)$ of finite index whose fixed field E contains F and has finite degree. The degrees and indices match because $[G : N] = [G : H][H : N]$ and $[E : K] = [F : K][E : F]$. By the previous argument for finite normal subextensions, $[E : K] = [G : N]$ and $[E : F] = [H : N]$ (for the second equality, replace L/K with L/F and G with H).]

Next, for the closed part, any subextension F/K is the union of its finite subextensions E/K. The intersection of the corresponding closed finite index subgroups $\mathrm{Gal}(L/E)$ is equal to $\mathrm{Gal}(L/F)$, which is therefore closed. Conversely, every closed subgroup H of G is an intersection of basic closed subgroups, all of which have the form $\mathrm{Gal}(L/E)$ for some finite subextension E/K, thus $H = \mathrm{Gal}(L/F)$, where F is the union of the E, completing the proof.

Finally, let F/K be normal and $H = \mathrm{Gal}_F(L)$. By lemma 50.8.5, restriction $\rho\colon G \to \mathrm{Gal}_K(F)$, $\sigma \mapsto \sigma|_F$, is a surjective homomorphism with kernel H, so it induces a group isomorphism $\overline{\rho}\colon G/H \to \mathrm{Gal}_K(F)$. The map ρ is continuous: a basic open set of $\mathrm{Gal}_K(F)$ is a coset $\tau\mathrm{Gal}_E(F)$ with E/K finite normal inside F (definition 50.8.6), and if $\rho(\sigma_0) = \tau$ then $\rho^{-1}(\tau\mathrm{Gal}_E(F)) = \sigma_0\mathrm{Gal}_E(L)$, a basic open set of G, since an element of G fixes E exactly when its restriction to F does. So $\overline{\rho}$ is continuous for the quotient topology on G/H. The group G is compact (proposition 50.8.7 and theorem 50.8.3), so G/H is compact: an open cover of G/H pulls back to an open cover of G, a finite subcover of which maps onto a finite subcover. The group $\mathrm{Gal}_K(F)$ is Hausdorff: if $\tau \neq \tau'$, choose $x \in F$ with $\tau(x) \neq \tau'(x)$ and a finite normal E/K

inside F containing x, the normal closure of $K(x)$. Then the cosets $\tau\mathrm{Gal}_E(F)$ and $\tau'\mathrm{Gal}_E(F)$ are disjoint, their elements sending x to $\tau(x)$ and to $\tau'(x)$ respectively. A continuous bijection from a compact space onto a Hausdorff space is a homeomorphism, as recalled at the start of this section, so $\overline{\rho}$ is an isomorphism of topological groups, completing the proof.

Corollary 50.8.9: Closure in Krull Topology

Let L/K be a galois extension and $H \leqslant \mathrm{Gal}_K(L)$ with fixed field F. Then the closure $\overline{H}$ in the Krull Topology is $\mathrm{Gal}_F(L)$:

$$\overline{H} = \mathrm{Gal}_F(L)$$

***Proof*:**
First, $H \subseteq \mathrm{Gal}_F(L)$ since by definition $\mathrm{Gal}_F(L)$ contains every $\sigma \in \mathrm{Gal}_K(L)$ that fixes F . Next, $\mathrm{Gal}_F(L)$ is closed and is the group characterized by $L^{\mathrm{Gal}_F(L)} = F$ by theorem 50.8.8. Thus

$$H \subseteq \overline{H} \subseteq \mathrm{Gal}_F(L)$$

Then in the bijection presented in theorem theorem 50.8.8, we have that they are equal, completing the proof.

Let us conclude with a result proven by Waterhouse in 1973 that generalizes theorem 20.2.10:

Theorem 50.8.10: Profinite Group Representable By Galois Group

Let G be a profinite group. Then G is isomorphic to the galois group of some galois extension L/K

***Proof*:**
Let $\mathcal{N}$ be the set of open normal subgroups of G and let

$$X = \coprod_{N \in \mathcal{N}} G/N$$

with G acting on each summand by left translation. Each $N \in \mathcal{N}$ has finite index, since G is compact by theorem 50.8.3 and the cosets of N form a cover of G by disjoint open sets. So every G-orbit in X is finite. The action is faithful: if g fixes every point then $g \in N$ for all $N \in \mathcal{N}$, and $\bigcap_N N = \{1\}$ because the natural map $G \to \varprojlim_N G/N$ is injective by corollary 50.8.4. The stabiliser of a point gN is gNg^{-1}, which is open.

Let k be any field and let $L = k(X)$ be purely transcendental over k with one indeterminate x_ξ for each $\xi \in X$. Each $\sigma \in G$ permutes X, hence induces the k-automorphism $x_\xi \mapsto x_{\sigma\xi}$ of L, and faithfulness makes $G \to \mathrm{Aut}_k(L)$ injective. Identify G with its image and put $K = L^G$.

The extension L/K is Galois. Since $k \subseteq K$, we have $L = k(X) \subseteq K(X) \subseteq L$, so $L = K(X)$. For each $\xi \in X$ the orbit $G\xi$ is finite, and the polynomial $\prod_{\eta \in G\xi}(T - x_\eta)$ has coefficients fixed by G, hence in K. Its roots are distinct indeterminates and all lie in L, so x_ξ is separable over K with minimal polynomial splitting in L. Therefore $L = K(X)$ is algebraic, separable and normal over K.

By construction $G \leqslant \mathrm{Gal}_K(L)$ with fixed field K, so G is dense in $\mathrm{Gal}_K(L)$ for the Krull topology

by corollary 50.8.9. The inclusion $\iota : G \to \mathrm{Gal}_K(L)$ is continuous: by definition 50.8.6 it is enough that $\iota^{-1}(\mathrm{Gal}_F(L))$ be open in G for every finite normal subextension F/K, since the preimage of a coset is empty or a coset of that subgroup. Write $F = K(\alpha_1, \ldots, \alpha_r)$. Each α_i is a rational function in finitely many of the x_ξ, so there is a finite $Y \subseteq X$ such that any $\sigma \in G$ fixing Y pointwise fixes every α_i, hence fixes F pointwise. The pointwise stabiliser of Y is a finite intersection of open stabilisers, so it is open, and $\iota^{-1}(\mathrm{Gal}_F(L))$ is a union of its cosets.

Finally, $\iota(G)$ is compact as the continuous image of a compact group, and $\mathrm{Gal}_K(L)$ is Hausdorff because proposition 50.8.7 realises it as a subspace of a product of discrete groups. So $\iota(G)$ is closed, and being dense it is all of $\mathrm{Gal}_K(L)$. Thus ι is a continuous bijection from a compact group to a Hausdorff group, hence an isomorphism of topological groups $G \cong \mathrm{Gal}_K(L)$.

Just like for finite groups where $K = \mathbb{Q}$ is a difficult (as of writing this book unsolved) problem called the *inverse Galois Problem*, there is little control on what base field K we can choose.

Exercise 50.8.1

1. Find $G = \mathrm{Gal}_{\mathbb{F}_p}(\overline{\mathbb{F}}_p)$ recalling that for each degree n, there is only one extension of $\mathbb{F}_p$. Show that there are too many subgroups to correspond to the fixed fields. Define the Krull topology on G.

Part X

Representation Theory

There are many domains of mathematics which have made huge amounts of progress, having very-well understood objects and morphisms, theorems, results, and properties. One of the most well-understood area's of mathematics has become linear algebra, where vector-spaces and linear transformations. One of the goals of this chapter will be do be able to study the following 3 objects where the operations becomes matrix addition and multiplication

1. (Finite) groups as a subgroup of $\mathrm{GL}(V)$, where the group operation becomes the matrix multiplication
2. Associative algebras
3. Lie Algebras

The further advantage of bringing these objects into linear algebra is that many field intersect with it: If the vector-spaces are infinite dimensional, we can make them Hilbert spaces and use tools from analysis. Vector-spaces are at the heart of differential geometry allowing us to use such theories to study groups!

For the reader who is really interested in number theory, section 51.3 shows that matrix algebras have many parallels with some number theory results. The reader who goes onto learn class field theory[28] will to their delight find that these parallels continue. It was observed by Langland[29] that the study of simple k-algebras (algebras with trivial two-sided ideals) can be a higher-dimensional parallel to field extensions and the central results of class field mathematics known as the *Langland's Program*.

(The reader may want to go back to section 12.3 to review about direct sums of modules)

(Also, this entire link is really cool: from wiki. Also has some cool examples of duality!!!)

[28] See [77] for the continuation of this textbook into class field theory

[29] Or at least formalized by Langland, as these ideas were floating around during his time

51

Semisimple Rings and Modules

As mentioned in the introduction, representation theory is all about decomposing structures. In part I, we showed in chapter 3, section 3.7, that all finite groups can uniquely be represented as a series of extensions with simple factors (i.e. G_i/G_{i+1} is simple). The simplest type of composition series would be when G is a direct product of simple groups, which would be in the terminology of exact sequences a series of trivial extensions with simple factors: such a group is sometimes *semi-simple* group[1]. When it came to modules, we found that we may decompose it in different ways depending on what rings acts on it, in particular we saw in chapter 13 that if $R = k$ is a field k, then any k-module is free, and in chapter 14 we saw that if R is a Principal Ideal Domain, where we got that any R-module decompsoed into a free part R-isomorphic to R^k, and a torsion part $R/(a_1) \times \cdots \times R/(a_n)$. It is evident that the ring that acts on the abelian group can have a large impact on it's structure. In this section, we define a new type of ring, which will come to be called a *semi-simple* ring, that will force the module M to *always* be a direct product of *simple modules* (so that we are analysing the "building blocks" of modules).

To define this ring, we first shift focus and start by work with the module itself to find the "simplest" structure it may be[2], and explore in a manner which at the beginning parallels groups: we will look for *simple R-modules*, and direct product of simple modules (since they are the simplest extension of simple module).[3]. After defining such a strucutre, we will define which rings acting on moduels will *always* make the module semi-simple

[1] the term "semi-simple group" is not a completely standard terminology, as direct product of simple groups is not generally very heavily studied, see this

[2] "simple" here means no non-trivial sub-structures that can be used to build an extension, just like for simple groups or simple rings

[3] It might be tempting to say that this means we are exploring projective modules. However, we have yet to establish whether simple modules are free-modules. Are they?

51.1 Decomposing Modules

Definition 51.1.1: Decomposition Terminology

Let M be a nonzero R-module.

1. M is said to be *simple* (or *irreducible*) if the only submodules of M are 0 and M. Otherwise, M is *reducible*
2. M is said to be *indecomposable* if there do not exist submodules $M_1, M_2 \subseteq M$ such that $M = M_1 \oplus M_2$. Otherwise, M is said to be *decomposable*.
3. The module M is said to be *semisimple* (or *completely reducible*) if it is the direct summand of simple modules
4. The module M is said to be semi-indecomposable (or completely indecomposable) if it is a direct summand of indecomposable modules.
5. If M is semisimple, any direct summand of M is called a *constituent* of M (i.e. N is a constituent of M if there exists a submodulde N' such that $M = N \oplus N'$)

A moment should be taken to find the relations between these definitions:

1. Simple modules are semi-simple and indecomposable. The prototypical example of a simple module is a field k over itself.
2. Semi-Simple $\not\Rightarrow$ Simple: take k^2 over k (the 2 dimensional vector-space over k). The cannonical example of a semi-simple module would be vector-spaces, since they are all direct sums of the underlying field, which is a simple k-module.
3. Indecomposable $\not\Rightarrow$ Simple: this statement is equivalent to saying that not all short exact sequence spilt (i.e., not all modules are *projective*, see section 17.2). For a concrete example, let $\mathbb{Z}^2$ be a module over $\mathbb{Z}$ with the action:

$$r \cdot (a, b) = (a + rb, b)$$

   Then it should be checked that it is not simple since $\mathbb{Z} \times \{0\}$ is a submodule, but it is indecomposable[4].
4. Every semi-simple module is a semi-indecomposable module, however the converse is not true: $\mathbb{Z}$ is a semi-indecomposable $\mathbb{Z}$-module (more genreally any module module over a PID is semi-indecomposable due to the Decomposition Theorem from chapter 14), however $\mathbb{Z}$ is not semi-simple a semi-simple $\mathbb{Z}$-module as $p\mathbb{Z}$ is a submodule (the general case will be immediate after lemma 51.1.7)[5]

As stated in the introduction, we want to determine a semi-simple module or semi-simple modules in terms of the ring that is acting on it. The following defintion was made for this purpose:

[4] Hint: Is it possible to write $\mathbb{Z} = n\mathbb{Z} \oplus m\mathbb{Z}$?

[5] This is a version of Krull-Schmidt's theorem for the decomposition of Noetherian or Artinian modules into the direct sum of indecomposable

Definition 51.1.2: Semi-Simple Ring

Let R be a ring. Then R is *semi-simple* if every R-module is semi-simple. Recall that R is *simple* if the only two-sided ideals are (0) and R.

Notice how a semi-simple ring was *not* defined as the direct product of simple rings. In the following proofs, we will show that the definition of semi-simple ring implies that R is the direct product of simple rings, however the converse is not true: there exists simple rings that are *not* semi-simple modules over themselves (and hence not simple R-modules). The problem is that of dimension; we will soon explore the relation between being semi-simple and Noetherian/Artinian. If we impose the condition that R be Noetherian and Artinian, then we are able to say that R is a semi-simple ring if and only if R is the direct product of simple rings.

We next establish many properties of simple and semi-simple modules, and show how closely related they are to the ring acting on them:

Lemma 51.1.3: Simple Module Characterization

Let M be an R-module. Then M is a simple R-module if and only if there exists a maximal left ideal $\mathfrak{m} \subsetneq R$ such that

$$M \cong_R R/\mathfrak{m}$$

***Proof*:**

($\Rightarrow$) Let M be a simple R-module, so $M \neq 0$ and its only submodules are $\{0\}$ and M. Fix $0 \neq x \in M$ and consider the R-module homomorphism

$$\varphi : R \to M \qquad r \mapsto r \cdot x$$

Its image is a nonzero submodule, so $\varphi(R) = M$, and $R/\ker(\varphi) \cong M$, where $\ker(\varphi)$ is a left ideal. The submodules of $R/\ker(\varphi)$ correspond to the left ideals J with $\ker(\varphi) \subseteq J \subseteq R$, so simplicity of M leaves only $J = \ker(\varphi)$ and $J = R$, and $\ker(\varphi) \neq R$ since $M \neq 0$. Thus $\ker(\varphi)$ is a maximal left ideal.

($\Leftarrow$) Let $\mathfrak{m}$ be a maximal left ideal and $M \cong R/\mathfrak{m}$. The submodules of $R/\mathfrak{m}$ correspond to the left ideals J with $\mathfrak{m} \subseteq J \subseteq R$, which are only $\mathfrak{m}$ and R, and $R/\mathfrak{m} \neq 0$. Hence M is simple, as we sought to show.

If R is commutative, a maximal left ideal is a maximal ideal and $R/\mathfrak{m}$ is a field. For noncommutative R, a maximal left ideal need not be two-sided, and $R/\mathfrak{m}$ is then only a left R-module. For instance, the only two-sided ideals of $R = M_n(k)$ are 0 and R (box 51.2.6), while the simple module k^n is $R/\mathfrak{m}$ for the maximal left ideal $\mathfrak{m}$ of matrices with vanishing first column, the kernel of $A \mapsto Ae_1$. Do not confuse the isomorphism in the above statement with a ring isomorphism: the structure of M is isomorphic to the R-module structure of left-multiplication on $R/\mathfrak{m}$. The proof also shows that a simple R-module is cyclic, generated by any of its nonzero elements. If $R = k$ is a field, then M is isomorphic to a 1-dimensional vector-space over k. There do exist noncommutative simple rings that are *not* of the form $M_n(k)$ for a field k, for instance the Hamilton quaternions $\mathbb{H}$, a noncommutative division ring that is a central simple $\mathbb{R}$-algebra of dimension 4 (example 51.3.3).

Using this result, we see that any semi-simple R-module is of the form:

$$M \cong_R \bigoplus_{i \in I} R/\mathfrak{m}_i$$

for maximal left ideals $\mathfrak{m}_i \subseteq R$. In fact, we can further characterize $\mathfrak{m}_i$:

Corollary 51.1.4: Simple Module's And Annihilators

Let M be a simple left R-module. Then $M \cong R/\text{Ann}(m)$ for any nonzero $m \in M$, where $\text{Ann}(m) = \{r \in R \mid rm = 0\}$, and $\text{Ann}(m)$ is a maximal left ideal.

***Proof*:**
For $0 \neq m \in M$, the submodule Rm is nonzero, so $Rm = M$ because M is simple. The map $R \to M$, $r \mapsto rm$, is therefore a surjective homomorphism of left R-modules with kernel $\text{Ann}(m)$, a left ideal, so

$$M \cong_R R/\text{Ann}(m)$$

The submodules of $R/\text{Ann}(m)$ correspond to the left ideals containing $\text{Ann}(m)$, and M is simple, so $\text{Ann}(m)$ is a maximal left ideal, completing the proof.

Since we have seen the limitations of the structure of simple modules, it is also natural to ask if there are any limitations on the structure of the hom-set given two simple modules:

Lemma 51.1.5: Schur's Lemma

Let M and N be simple R-modules, $\varphi : M \to N$ an R-module homomorphism. Then either $\varphi = 0$ or φ is an isomorphism. As a consequence, $\text{End}_R(M)$ is a division ring.

***Proof*:**
Since N is simple, either $\varphi(M) = N$ or $\varphi(M) = 0$. If $\varphi(M) = N$, it has to be that $\ker(\varphi) = 0$, since M is simple, and hence φ would be an isomorphism.

As a consequence, every element in $\text{End}_R(M)$ is either 0 or is a unit, i.e. has a multiplicative inverse, which by definition makes $\text{End}_R(M)$ a divising ring under $(+, \circ)$.

Since $M \cong_R R/\mathfrak{m}$ for some maximal left ideal $\mathfrak{m} \subsetneq R$, we have that $\text{End}_R(R/\mathfrak{m})$ is always a division ring, whether R is commutative or not. In a sense, this can be thought of as "generalization" to proposition 9.4.19, where it was shown that $R/\mathfrak{m}$ is a field if R is commutative.

Notice that if $M = V$ was an 1-dimensional vector-space over k, then $\text{End}_R(V)$ is a known division ring, in particular it's ring-isomorphic to k. If V is a finite dimensional semi-simple module over k, i.e. it is n-dimensional, then $\text{End}_R(V)$ is ring-isomorphic to $M_n(k)$. We might hope for something similar for the structure of $\text{End}_R(M)$ is M is semi-simple. Take a moment to ponder this before reading the next lemma (hint: recall proposition 12.3.36)

Lemma 51.1.6: Hom's of Semisimple Modules

Let M be a semisimple R-module, so that:

$$M = S_1^{\oplus n_1} \oplus S_2^{\oplus n_2} \oplus \cdots \oplus S_k^{\oplus n_k}$$

where each S_i are simple R-modules, $S_i \ncong S_j$. Then as a ring:

$$\mathrm{End}_R(M) \cong_{\mathbf{Ring}} \mathrm{End}_R(S_1^{\oplus n_1}) \oplus \cdots \oplus \mathrm{End}_R(S_k^{\oplus n_k})$$

Furthermore, for each $S_i^{\oplus n_i}$, we have that direct sums "pull out" to become matrices:

$$\mathrm{End}_R(S_i^{\oplus n_i}) \cong_{\mathbf{Ring}} M_{n_i}(\mathrm{End}_R(S)) = M_{n_i}(D_i)$$

where $D = \mathrm{End}_R(S_i)$ and $M_{n_i}(D_i)$ is the matrix ring over the division ring $\mathrm{End}_R(S_i)$.

***Proof*:**
We invoke proposition 12.3.36 to get the result in terms of groups, and then use Schur's lemma and check that the ring operation is compatible:

$$\begin{aligned}
\mathrm{End}_R(M) &= \mathrm{Hom}_R\left(\bigoplus_i S_i^{\bigoplus n_i}, \bigoplus_j S_j^{\bigoplus n_j}\right) \\
&\cong_{\mathbf{Grp}} \bigoplus_{i,j} \mathrm{Hom}_R\left(S_i^{\bigoplus n_i}, S_j^{\bigoplus n_j}\right) \\
&\cong_{\mathbf{Grp}} \bigoplus_{i,j} \mathrm{Hom}_R(S_i, S_j)^{\bigoplus n_i n_j}
\end{aligned}$$

where when $S_i \neq S_j$, by Shur's lemma we must have:

$$\mathrm{Hom}_R(S_i, S_j)^{n_i n_j} = 0$$

Hence we get that $\mathrm{End}_R(M) \cong_{\mathbf{Grp}} \oplus_i \mathrm{Hom}_R(S_i^{n_i}, S_i^{n_i}) = \oplus_i \mathrm{End}_R(S_i^{n_i})$. Next, this map is compatible with the ring structure, since the map:

$$\varphi \to (\varphi|_{S^{n_i}} : S_i^{n_i} \to S_i^{n_i} \subseteq M)$$

is clearly clearly compatible with composition, and hence

$$\mathrm{End}_R(M) \cong_{\mathbf{Ring}} \bigoplus_i \mathrm{End}_R(S_i^{n_i})$$

For part 2, we follow the same steps as for part (1): re-indexing so that $S^n = S_1 \oplus S_2 \oplus \cdots \oplus S_n$ so that $S_i = S_j = S$, we get

$$\mathrm{Hom}_R\left(\bigoplus_i S_i, \bigoplus_j S_j\right) \cong_{\mathbf{Grp}} \bigoplus_{i,j} \mathrm{Hom}_R(S_i, S_j) \overset{!}{=} \bigoplus_{i,j} D \cong_{\mathbf{Grp}} M_n(D)$$

where $\overset{!}{=}$ comes from Shur's lemma with $D = \mathrm{End}_R(S)$ since $S_i = S_j = S$. The last equality comes from the fact that the matrix $M_n(D)$ when treated like a group is simply re-arranging where the addition is happening in $\bigoplus_{i,j} D$. To show that the ring structure is compatible, observe that

$$\varphi \mapsto \varphi_{ji}$$

is the desired map, where

$$\varphi \begin{pmatrix} s_1 \\ s_2 \\ \vdots \\ s_n \end{pmatrix} = \begin{pmatrix} \varphi_{11} & \varphi_{12} & \cdots & \varphi_{1n} \\ \varphi_{21} & \varphi_{22} & \cdots & \varphi_{2n} \\ \vdots & \vdots & \ddots & \cdots \\ \varphi_{n1} & \varphi_{n2} & \cdots & \varphi_{nn} \end{pmatrix} \begin{pmatrix} s_1 \\ s_2 \\ \vdots \\ s_n \end{pmatrix}$$

which is simply a formalization of what the group-isomorphism give us, showing us that composition is compatible, completing the proof. (see this for a more detailed explanation)

Hence, for any semi-simple R-module M, we get that:

$$\mathrm{End}_R(M) \cong_{\mathbf{Ring}} \prod_i M_{n_i}(D_i) \cong_{\mathbf{Ring}} \prod_i \mathrm{End}_R(S_i^{\oplus n_i})$$

and since each S_i is a simple R-module, $S_i \cong_R R/\mathfrak{m}_i$ for an appropriate maximal left ideal $\mathfrak{m}_i \subseteq R$, $\mathrm{End}_R(S_i) \cong \mathrm{End}_R(R/\mathfrak{m}_i)$. Thus:

$$\mathrm{End}_R(M) \cong_{\mathbf{Ring}} \prod_i M_{n_i}(\mathrm{End}_R(R/\mathfrak{m}_i)) = \prod_i M_{n_i}(D_i)$$

If $R = k$ is a field making $M = V$ a vector-sapce over k (say n-dimensonal), then the only simple k-submodule up to isomorphism is k, and so this result reduces to:

$$\mathrm{End}_R(V) \cong_{\mathbf{Ring}} M_n(\mathrm{End}_k(k/(0))) = M_n(k)$$

where $\mathrm{End}_k(k) \cong_{\mathbf{Ring}} k$, aligning with the results we found in secion 13.2. This shows that when generalizing from linear algebra, due to the fact that a ring is non-commutative, we may have several non-isomorphic simple summands, giving us products of several matrix rings. With a better understanding of simple modules and their endomorphisms, we continue by characterizing semi-simple modules:

Lemma 51.1.7: Semi-Simple Module Equivalence

Let M be an R-module. Then the following are equivalent, and M is called *semi-simple* when they hold:

1. M is an external direct sum of simple modules:
$$M \cong \bigoplus_{i \in I} S_i$$
2. M is the internal direct sum of simple submodules:
$$M = \bigoplus_{i \in I} S_i$$
3. If $N \subseteq M$, there exists a complementary submodule, that is there exists another submodule $N' \subseteq M$ such that
$$M = N \oplus N'$$

In particular, if M is semi-simple, every short exact sequence $0 \to N \to M \to M/N \to 0$ splits. Note that semi-simplicity is not assumed: each of the three conditions implies the other two for an arbitrary module, which is what makes (3) a usable criterion for *establishing* semi-simplicity (as in theorem 53.1.9).

***Proof*:**
For (1) $\Rightarrow$ (2), let $\varphi\colon \bigoplus_{i\in I} S_i \to M$ be an isomorphism. The submodules $\varphi(S_i)$ are simple, and every element of M is uniquely a finite sum of elements of the $\varphi(S_i)$, so M is their internal direct sum. For (2) $\Rightarrow$ (1), if $M = \bigoplus_{i\in I} S_i$ internally, then $(s_i)_{i\in I} \mapsto \sum_i s_i$ is an isomorphism from the external direct sum onto M.

For (2) $\Rightarrow$ (3), let $M = \bigoplus_{i\in I} S_i$ and $N \subseteq M$. The submodules $N' \subseteq M$ with $N \cap N' = 0$ form a nonempty set (it contains 0) in which the union of a chain is again such a submodule, so Zorn's lemma gives a maximal one, N'. Suppose $N + N' \neq M$. Since $M = \sum_i S_i$, some S_i is not contained in $N + N'$, so $S_i \cap (N + N')$ is a proper submodule of the simple module S_i, hence
$$S_i \cap (N + N') = 0$$
Then $(S_i + N') \cap N = 0$: if $s + n' \in N$ with $s \in S_i$ and $n' \in N'$, then $s \in S_i \cap (N + N') = 0$, and so $n' \in N \cap N' = 0$. By maximality of N', $S_i + N' = N'$, so $S_i \subseteq N' \subseteq N + N'$, a contradiction. Hence $M = N \oplus N'$.

For (3) $\Rightarrow$ (2), assume every submodule of M has a complement.

Step 1: Every submodule K of M has the same property. Let $L \subseteq K$ and write $M = L \oplus L'$. For $x \in K$ write $x = l + l'$ with $l \in L$ and $l' \in L'$. Then $l' = x - l \in K$, so $K = L \oplus (L' \cap K)$.

Step 2: Every nonzero submodule $N \subseteq M$ contains a simple submodule. Take $x \in N$ nonzero.

The kernel I of $R \to Rx$, $r \mapsto rx$, is a left ideal not containing 1, and Zorn's lemma, applied to the left ideals containing I but not 1 (a union of a chain of them still omits 1), gives a maximal left ideal $\mathfrak{m} \supseteq I$. Under $Rx \cong R/I$, the submodule $\mathfrak{m}x$ of Rx corresponds to $\mathfrak{m}/I$. By Step 1, $Rx = \mathfrak{m}x \oplus L$ for some submodule L, and then

$$L \cong Rx/\mathfrak{m}x \cong (R/I)/(\mathfrak{m}/I) \cong R/\mathfrak{m}$$

which is simple because its submodules correspond to the left ideals between $\mathfrak{m}$ and R. So $L \subseteq Rx \subseteq N$ is a simple submodule.

Step 3: M is an internal direct sum of simple submodules. Call a family of simple submodules of M *independent* if every element of its sum is uniquely a finite sum of elements of its members. Independence is decided by finite subfamilies, so the union of a chain of independent families is independent, and Zorn's lemma gives a maximal independent family $(S_i)_{i\in I}$ (the empty family is independent). Put $N = \sum_{i\in I} S_i = \bigoplus_{i\in I} S_i$. By hypothesis $M = N \oplus N'$ for some N'. If $N' \neq 0$, Step 2 gives a simple submodule $S \subseteq N'$, and $S \cap N = 0$ makes the family $(S_i)_{i\in I}$ together with S independent, against maximality. Hence $N' = 0$ and $M = \bigoplus_{i\in I} S_i$.

Finally, if M is semi-simple and $N \subseteq M$, write $M = N \oplus N'$ by (3). The projection of M onto N along N' is a left inverse of the inclusion $N \to M$, so the sequence $0 \to N \to M \to M/N \to 0$ splits, completing the proof.

This theorem shows that every vector space over k is a semisimple k-module. On the other hand, $\mathbb{Z}$ is *not* a semi-simple $\mathbb{Z}$-module, since $2\mathbb{Z}$ is a submodule with no complement: if $\mathbb{Z} = 2\mathbb{Z} \oplus N'$, then $N' \neq 0$, and for $0 \neq n \in N'$ the element $2n \neq 0$ lies in $2\mathbb{Z} \cap N' = 0$, a contradiction. So not all free modules are semi-simple. We can characterize semi-simple rings by saying that R is semi-simple if and only if every R-module is projective. This also shows us that $\mathbb{Z}$ is not a semi-simple ring: $\mathbb{Z}$ is projective over itself, but any nonzero finite abelian group is a non-projective $\mathbb{Z}$-module. Thus every module over a semi-simple ring is projective. A semi-simple module over an arbitrary ring need not be projective, since $\mathbb{Z}/2\mathbb{Z}$ is a simple $\mathbb{Z}$-module that is not projective, and a module over a semi-simple ring need not be free: even though many examples of semi-simple modules are free modules, we would require the underlying ring to be semi-simple over itself. In fact, it is enough that the underlying ring be a semi-simple module over itself, giving us an easier condition for defining a semi-simple ring.

Corollary 51.1.8: Closure Properties Of Semisimple Modules

Let M be an R-module. Then all submodules and quotient modules of M are semisimple if and only if M is semi-simple. Furthermore, if $(M_i)_{i\in I}$ is a collection of semi-simple modules, then $\bigoplus_{i\in I} M_i$ is a semi-simple module.

***Proof*:**
Every module is a submodule of itself, so if all submodules of M are semi-simple, so is M. Conversely, let M be semi-simple, so that every submodule of M has a complement by lemma 51.1.7.

Submodules. Let $N \subseteq M$ and $L \subseteq N$, and write $M = L \oplus L'$. For $x \in N$ write $x = l + l'$ with $l \in L$ and $l' \in L'$. Then $l' = x - l \in N$, so $N = L \oplus (L' \cap N)$. Thus every submodule of N has a

complement in N, and N is semi-simple by lemma 51.1.7.

Quotients. Let $K \subseteq M$. A submodule of M/K has the form L/K with $K \subseteq L \subseteq M$. Write $M = L \oplus L'$, so that $M/K = L/K + (L' + K)/K$. If $x \in L \cap (L' + K)$, say $x = l' + k$ with $l' \in L'$ and $k \in K$, then $l' = x - k \in L \cap L' = 0$ because $K \subseteq L$, so $x \in K$. Hence $M/K = L/K \oplus (L' + K)/K$. Thus every submodule of M/K has a complement, and M/K is semi-simple by lemma 51.1.7.

Direct sums. If each M_i is the internal direct sum of simple submodules S_{ij}, $j \in J_i$, then $\bigoplus_{i \in I} M_i$ is the internal direct sum of the simple submodules S_{ij} over all i and j, so it is semi-simple by lemma 51.1.7, completing the proof.

These properties of semi-simple modules allow us to characterize semi-simple rings much more easily:

Corollary 51.1.9: Semi-Simple Rings Condition

Let R be a ring. Then R is a semi-simple ring if and only if R is a semi-simple R-module, that is we only need to check that R is a semi-simple R-module for one R-module structure (namely R itself)

***Proof*:**
If R is a semi-simple ring, then every R-module is semi-simple, including R over itself.

Conversely, suppose that R is a semi-simple R-module. Then so is $\bigoplus_{i \in I} R$ for every index set I, by corollary 51.1.8. Let M be an R-module and let $(m_i)_{i \in I}$ be a family of generators of M (for example, all elements of M). Then

$$\bigoplus_{i \in I} R \to M \qquad (r_i)_{i \in I} \mapsto \sum_i r_i m_i$$

is a surjective homomorphism, so M is a quotient of a semi-simple module and is semi-simple by corollary 51.1.8. Thus every R-module is semi-simple, and R is a semi-simple ring by definition, as we sought to show.

Due to this, we get a nice description of semi-simple rings which is even stronger than semi-simple modules:

Lemma 51.1.10: Decomposing Semi-Simple Rings

Let R be a semi-simple ring. Then:

$$R = I_1 \oplus \cdots \oplus I_n$$

for a finite collection of I_k, where I_k are simple left-submodules of R, i.e. *minimal* left ideals[a] of R

[a] These are *left ideals* as we are working with *left* submodules

***Proof*:**
Since R is a semi-simple ring, it is a semi-simple R-module and so by definition:

$$R = \bigoplus_{i \in \mathcal{C}} I_i$$

for simple submodules I_i (i.e. minimal left ideals I_i). To make this a finite sum, since $1 \in R$, we get for an appropraite finite subset $A \subseteq \mathcal{C}$

$$1 \in I_{\alpha_1} + \cdots + I_{\alpha_n}$$

But then, since these are all ideals,

$$R = R \cdot 1 \subseteq I_{\alpha_1} \oplus \cdots \oplus I_{\alpha_n} \subseteq R$$

and hence $R = I_{\alpha_1} \oplus \cdots \oplus I_{\alpha_n}$, completing the proof.

51.1.11 Remark As a consequence of this, any semi-simple ring R is a left-Noetherian/Artinian ring. Interestingly, we will soon show that this also implies that R is a *right*-Noetherian/Artinian ring (see rightNoethArtRemark)

Furthermore, this shows how it is necessary for the condition that R be left-Noetherian/Artinian so that the notion of being semi-simple coincide between the two definitions.

Since we characterized simple R-modules for any ring R to be R-isomorphic to $R/\mathfrak{m}$, and we have given a structure of R if R is a semisimple ring, we can make lemma 51.1.3 more precise:

Corollary 51.1.12: Structure Of Simple Modules Of Semi-Simple Ring

Let R be a semi-simple ring so that $R = I_1 \oplus I_2 \oplus \cdots \oplus I_n$ for minimal left ideal I_k (equivalently, simple left R-modules). Then if M is a simple left R-module,

$$M \cong_{R\textbf{-Mod}} I_i$$

for some $1 \leq i \leq n$.

***Proof*:**
Let M be a simple nonzero left R-module, and consider the R-module homomorphism:

$$\varphi : R \to M \qquad r \mapsto r \cdot x$$

where $x \neq 0$. Since M is simple, it is nonzero, so φ is surjective. Since $R = \bigoplus_i^n I_i$, for some i's

$$\varphi|_{I_i} \neq 0$$

and since $\varphi|_{I_i} = \pi_i \circ \varphi$ we have the R-module homomorphism:

$$\varphi|_{I_i} I_i \to M$$

and since both modules are simple and this is a nonzero homomorphism, by Schur's lemma this map must be an isomorphism, as we sought to show.

Note that there can be multiple I_i's that are isomrophic to M, which we will show in a following theorem.

This shows that any simple R-module over a semi-simple ring R is in fact isomorphic to a simple R-submodule of R (i.e. R-isomorphic to a minimal left ideal of R). Thus, studying simple R-modules over semi-simple rings comes down to studying the ring R itself, and that there are only *finitely many* simple R-modules. Furthermore, we have that $R/(I_1 \oplus \cdots \oplus I_{n-1}) \cong_R I_n$. Here is a good example of where the ring structure of the left hand side cannot exist in the right hand side. For example, if R is commutative, then $R/\mathfrak{m}$ is a field that is R-module isomorphic to a minimal ideal, but ideals cannot be fields (over the same identity[6]). Thus, in the case where R is semi-simple, for a maximal left ideal $\mathfrak{m}$, $R/\mathfrak{m}$ is R-isomorphic to a minimal left ideal of R.

Exercise 51.1.1

1. Let S be a simple module. Show that any nonzero submodule of the injective enveloppe $E(S)$ is indecomposable, but not simple.
2. Show that if M is a simple R-module, then it necessarily has to be cyclic (the converse, however, is not true).
3. Show that $A = \mathbb{Q}[x, y]/(xy - yx - 1)$ is a simple ring, but no a semi-simple ring (this is a special example of an algebra called a *Weyl* Algebra)
4. Let R be a ring, not necessarily commutative, and let $[R, R] = \{rs - sr \mid r, s \in R\}$. Show that the trace map induces an isomorphism

$$\frac{M_n(R)}{[M_n(R), M_n(R)]} \cong \frac{R}{[R, R]}$$

From this perspective, matrix rings are the natural "nonabelian" extension of a ring!

51.2 Artin-Wederburn

We just showed how studying simple and semi-simple R-modules comes down to studying the ring R, especially if the ring R is semi-simple. Thus, it is fruitful to classify semi-simple rings, which leads us to the main classification result for semi-simple rings, namely we build on lemma 51.1.10 and show that we can find more precisely how to represent each minimal left ideal I_i, and furthermore show that this classification is exhaustive, and that any semi-simple ring uniquely breaks down into the result we will show. We will then finish by showing that if we upgrade our ring to k-algebras (that is, we can put a vector-space structure on our ring), we get some stronger results due to the fact we can count dimensions.

[6] $k \times \{0\} \subseteq k \times k$ is an ideal and a field with identity $(1, 0)$

Definition 51.2.1: Opposite Ring

Let R be a ring. Then we define a new ring labelled R^{op} that has the same underlying set and addition operation, whith the multiplication operation $*$ being:

$$x * y = yx$$

where the multiplication yx happens in R

If R is commutative, then $R = R^{\text{op}}$, so the opposite ring carries new information only when R is not commutative.

Proposition 51.2.2: Properties Of Opposite Ring

Let R be a ring and R^{op} its oppposite ring. Then:

1. $(R^{\text{op}})^{\text{op}} = R$
2. $(R \times S)^{\text{op}} = R^{\text{op}} \times S^{\text{op}}$
3. $M_n(R)^{\text{op}} \cong M_n(R^{\text{op}})$ where the isomorphism is $A \mapsto A^t$ (since transposing converts BA into the product whose entries multiply in R^{op})

***Proof*:**
In all three claims the two rings share their underlying set and their addition, so only the multiplications need comparison. Throughout, $*$ denotes an opposite multiplication as in definition 51.2.1.

For (1), write $\star$ for the multiplication of $(R^{\text{op}})^{\text{op}}$, the opposite of the multiplication $*$ of R^{op}. For any $x, y \in R$:

$$x \star y = y * x = xy$$

so $\star$ is the original multiplication of R, and $(R^{\text{op}})^{\text{op}} = R$ as rings.

For (2), both rings have underlying set $R \times S$ with componentwise addition. Multiplying in $(R \times S)^{\text{op}}$ gives

$$(r, s) * (r', s') = (r', s')(r, s) = (r'r, s's)$$

while multiplying in $R^{\text{op}} \times S^{\text{op}}$ gives $(r * r', s * s') = (r'r, s's)$ as well. The two multiplications agree, so the rings are equal.

For (3), let $\tau : M_n(R)^{\text{op}} \to M_n(R^{\text{op}})$ be the transpose map $\tau(A) = A^t$, where $(A^t)_{ij} = A_{ji}$. The map τ is additive, fixes the identity matrix, and is a bijection because it is its own inverse on the underlying set. For multiplicativity, let $A, B \in M_n(R)^{\text{op}}$ and let $*$ denote the multiplication of $M_n(R)^{\text{op}}$, so that $A * B$ is the matrix BA computed in $M_n(R)$. For each pair (i, j):

$$\tau(A * B)_{ij} = (BA)_{ji} = \sum_k B_{jk} A_{ki}$$

Computing $\tau(A)\tau(B)$ in $M_n(R^{\text{op}})$ multiplies the entries in R^{op}:

$$(\tau(A)\tau(B))_{ij} = \sum_k (A^t)_{ik} * (B^t)_{kj} = \sum_k A_{ki} * B_{jk} = \sum_k B_{jk} A_{ki}$$

The two entries agree, so $\tau(A*B) = \tau(A)\tau(B)$ and τ is a ring isomorphism. For noncommutative R the identity $(BA)^t = A^tB^t$ fails inside $M_n(R)$ itself. The computation above succeeds because the entries of $\tau(A)\tau(B)$ are multiplied in R^{op}, which restores the order of each product.

With this, we can make a link between R and R^{op}:

Lemma 51.2.3: Yonneda's Lemma for opposite Rings

Let R be a ring and consider the ring $\text{End}_R(R)$ to be the set of all R-module homomorphisms from R (as an R-module) to itself. Then $\varphi : R^{\text{op}} \to \text{End}_R(R)$, $r \mapsto (x \mapsto xr)$ is a ring isomorphism:

$$R^{\text{op}} \cong_{\textbf{Ring}} \text{End}_R(R)$$

***Proof*:**
Let φ_r be the given map. Let's first check that $\varphi_r \in \text{End}_R(R)$. Then we see that:

$$\begin{aligned}\varphi_r(\lambda x + \lambda y) &= (\lambda x + \lambda y)r \\ &= \lambda(xr) + \lambda(yr) \\ &= \lambda\varphi_r(x) + \lambda\varphi_r(y)\end{aligned}$$

showing that $\varphi_r \in \text{End}_R(R)$. Next, we check that φ is ineed a ring-homomorphism. By the module axioms:

1. $\varphi_1 = \text{id}$, and hence φ sends the identity to the identity.
2. $\varphi_{r+r'} = \varphi_r + \varphi_{r'}$
3. $\varphi_{rr'} = \varphi_{r'} \circ \varphi_r$ (do not forget we are working with R^{op})

Finally, showing bijectivity, for injectivity we see that if $\varphi_r = 0$, then $0 = \varphi_r(1) = r$, and hence $\varphi_r = \varphi_0$. For surjectivity, let $\varphi \in \text{End}_R(R)$. Let's say $\varphi(1) = r$. Then $\varphi(x) = x\varphi(1) = xr$, so $\varphi = \varphi_r$, completing the proof.

In the special case where R is commutative, then $R \cong R^{\text{op}}$, showing that in this case $R \cong \text{End}_R(R)$. Using this, we will use lemma 51.2.3 along with lemma 51.1.6 to upgrade lemma 51.1.10:

Theorem 51.2.4: Artin-Wedderburn, one Direction

Let R be a semisimple ring. Then:

$$R \cong_{\textbf{Ring}} M_{n_1}(D_1) \times \cdots \times M_{n_k}(D_k)$$

where each D_i is a division ring and $M_{n_i}(D_i)$ is the matrix ring over D_i

The key realization about this theorem is that while the multiplication on the left hand side can "send you" all over the place, the multiplication on the right hand side only sends you back into your particular component. To see this more clearly, let's say R was a k-algebra for a field k so that it has a basis. If R was a semi-simple ring, then that means that when multiplying elements of R (so

figuring out where the basis elements go while multiplying), we can isolate the problem down to the components on the right hand side, and figure out where they go through matrix multiplication!

***Proof*:**
First, lemma 51.1.10 decomposes R into simple R-submodules, that is, minimal left ideals of R,

$$R = I_1 \oplus \cdots \oplus I_n$$

Now, we can always re-order the sums (i.e. $I_1 \oplus I_2 \cong I_2 \oplus I_1$, since $R \cong I_1 \oplus \cdots \oplus I_n$ by proposition 12.3.6). Hence, we will group all the I_i's that belong to the same isomrophism class (as R-modules), letting us re-write R as:

$$R \cong_{\mathbf{Ring}} I_1^{n_1} \oplus \cdots \oplus I_k^{n_k}$$

where $I_i \ncong I_j$ for $i \neq j$. Hence by lemma 51.2.3 and lemma 51.1.6:

$$\begin{aligned} R^{\text{op}} &\cong_{\mathbf{Ring}} \text{End}_R(R) \\ &\cong_{\mathbf{Ring}} M_{n_1}(D_1) \times \cdots \times M_{n_k}(D_k) \end{aligned}$$

where $D_i = \text{End}_R(I_i)$ is a divison ring. Finally, Taking the opposite ring on both sides, we get:

$$\begin{aligned} R &\cong_{\mathbf{Ring}} (R^{\text{op}})^{\text{op}} \\ &\cong_{\mathbf{Ring}} M_{n_1}(D_1)^{\text{op}} \times \cdots \times M_{n_k}(D_k)^{\text{op}} \\ &\cong_{\mathbf{Ring}} M_{n_1}(D_1^{\text{op}}) \times \cdots \times M_{n_k}(D_k^{\text{op}}) \end{aligned}$$

and it is clear the D_i^{op} is still a division ring, hence completing the proof.

Thus, if we have a simple-ring then the ring breaks down into the product of matrix rings over division rings. In the special case where $R = k$ is a field, then k has only one minimal ideal, namely itself, and $\text{End}_k(k) \cong M_1(k) \cong k$, and hence we reduce to $k \cong k$. If $R = k^n$ is a product of the same field, then the minimal ideals of R are $R = k \oplus \cdots \oplus k$, so that we get back $k^n \cong_{\mathbf{Ring}} k^n$.

We will now show that the converse of this theorem is true, that the product of matrix rings over division rings is semi simple. We start by showing that matrix ring are simple modules[7].

Proposition 51.2.5: Matrix Ring over Division Rings are semi-simple

Let $R = M_n(D)$ be a matrix ring over a divison ring. Let $C = D^{\oplus n}$ be the left $M_n(D)$-module where the action is left matrix multiplication (imagine C as a column). Then C is a simple $M_n(D)$-module, and

$$M_n(D) \cong_{M_n(D)\text{-}\mathbf{Mod}} C^{\oplus n} = (D^{\oplus n})^{\oplus n}$$

showing that $M_n(D)$ is semisimple ring and $M_n(D) \cong_{\mathbf{Ring}} C^{\oplus n}$

***Proof*:**
Let $R = M_n(D)$ and $C = D^{\oplus n}$ (C for *column*). For notational simplicity, let $E_{ij} \in R$ be the elementary matrix which is 1 in position ij and zero everywehre else. Let $e_i \in C$ be the column

[7] This will be an example of R being both a simple R-module and a simple ring

where it is 1 at position i and zero everywehre else:

$$E_{ij} = \begin{pmatrix} 0 & & & & 0 \\ & \ddots & & \iddots & \\ & & 1 & & \\ & \iddots & & \ddots & \\ 0 & & & & 0 \end{pmatrix} \qquad e_i = \begin{pmatrix} 0 \\ \vdots \\ 1 \\ \vdots \\ 0 \end{pmatrix}$$

Then $E_{ij}e_k = \delta_{jk}e_i$ where δ_{jk} is the Kronecker Delta:

$$\delta_{jk} = \begin{cases} 1 & j = k \\ 0 & j \neq k \end{cases}$$

Now, we will start by showing that C is a simple $M_n(D)$-module. Since $C = D^{\oplus n}$,

$$C = \bigoplus_i De_i$$

for some basis $e_1, e_2, ..., e_n$. To show that C is simlpe, it is enough to show that for any $0 \neq x \in C$, $C = Rx$ since then any nonzero submodule would in fact be C. Given our above notation, we have that:

$$x = \sum_k d_k e_k$$

for appropriate $d_k \in D$, where at least one of these is nonzero, let's say $d_j \neq 0$. Then consider $E_{ij}x \in Rx$:

$$E_{ij}x = \sum_k \delta_{jk} d_k e_k = d_j e_i$$

since $d_j \neq 0$. Since D is a division ring, we get that $d_j^{-1}e_i \in Rx$, for all $1 \leq i \leq n$. But then, we get:

$$C = \sum De_i \subseteq Rx \subseteq C$$

showing that $C = Rx$ for any $0 \neq x \in C$, showing that C is indeed simple.

Now, we can re-write this ring as the internal direct sum of matrices I_i which are zero outisde the ith column:

$$R = M_n(D) = I_1 \oplus \cdots \oplus I_n$$

$$I_k = \begin{pmatrix} 0 & \cdots & a_{1,k} & \cdots & 0 \\ 0 & & a_{2,k} & & 0 \\ \vdots & & \vdots & & \vdots \\ 0 & & a_{2,n-1} & & 0 \\ 0 & \cdots & a_{n,k} & \cdots & 0 \end{pmatrix}$$

This decomposition works since each I_i is stable under *left* multiplication by elements of $M_n(D)$ (since left multiplication is a *column* transformation, right multiplication would be *row* transformation). Finally, $C \cong_{R\textbf{-mod}} I_i$ by simply moving the column to the right place, and so each I_i is simple. Hence, we have decomposed $M_n(D)$ as a dierct product of simple left $M_n(D)$-modules, and hence $M_n(D)$ is a semisimple $M_n(D)$-module, which by corollary 51.1.9 makes $M_n(D)$ a semi-simple ring. Finally, since $C^{\oplus n}$ represents the n rows of n-length columns, we see that the action of $M_n(D)$ on $C^{\oplus n}$ is identical to that of matrix multiplying elements of $C^{\oplus n}$, which gives us that $M_n(D) \cong_{\textbf{Ring}} C^{\oplus n}$, as we sought to show.

51.2.6 Remark In fact, $M_n(D)$ is a simple ring, meaning the only *two-sided* ideals of R are 0 and R; the above proof can be modified to show this. This gives us a nice class of non-commutative simple rings (since all simple commutative rings are fields).

Notice that it is quite sepcial that the ring opration and the module operation coincided, this because of the special way in which we decompoed the $M_n(D)$-module $M_n(D)$ and by the fact that it is a module over itself. In the previous proposition, we showed that $D^{\oplus n}$ is a simple $M_n(D)$-module. In fact, all simple modules of $M_n(D)$ are isomorphic to $D^{\oplus n}$:

Corollary 51.2.7: Structure of Simple $M_n(D)$-Module

Let $R = M_n(D)$ be a matrix ring over a division ring. Then any simple $M_n(D)$-module is isomorphic to $D^{\oplus n}$.

***Proof*:**
Let M be a simple $M_n(D)$-module. By proposition 51.2.5

$$M_n(D) \cong_{\mathbf{Ring}} D^{\oplus n} \oplus \cdots_{\mathbf{Ring}} \oplus D^{\oplus n}$$

And by corollary 51.1.12,

$$M \cong D^{\oplus n}$$

Corollary 51.2.8: Endomorphism Of Simple $M_n(D)$-Module

Let S be a simple $M_n(D)$-module. Then

$$\mathrm{End}_{M_n(D)}(S) \cong_{\mathbf{Ring}} D^{\mathrm{op}}$$

***Proof*:**
Since S is simple, $S \cong_R D^{\oplus n}$ for some n. Let $\varphi_d : S \to S$, $\varphi_d(x) = x \cdot d$ where $x \cdot d$ is x times dI. Then:

$$\varphi_d(Ax) = (Ax) \cdot d = A(x \cdot d) = A\varphi_d(x)$$

and

$$\varphi_d(x+y) = (x+y) \cdot d = (x+y)dI = xdI + ydI = x \cdot d + y \cdot d = \varphi_d(x) + \varphi_d(y)$$

hence $\varphi_d \in \mathrm{End}_R(S)$. Conversely, if $\varphi \in \mathrm{End}_R(S)$, Since $S \cong D^{\oplus n}$, and

$$D^{\oplus n} \cong \begin{pmatrix} D^{\oplus n} & 0^{\oplus n} & \cdots & 0^{\oplus n} \end{pmatrix}$$

we will treat S as a $M_n(D)$ submodule of $M_n(D)$. Now, since φ is a group homomorphism, we know that:

$$\varphi \begin{pmatrix} 1 \\ 0 \\ \vdots \\ 0 \end{pmatrix} = \begin{pmatrix} \varphi_{11} & \cdots & \varphi_{n1} \\ \vdots & \ddots & \vdots \\ \varphi_{n1} & \cdots & \varphi_{nn} \end{pmatrix} \begin{pmatrix} 1 \\ \vdots \\ 0 \end{pmatrix} = \begin{pmatrix} \varphi_{11}(1) + \cdots + \varphi_{n1}(1) \\ \vdots \\ 0 \end{pmatrix}$$

hence let $d = \sum_i^n \varphi_{i1}(1)$, and let the right-action on $\mathrm{End}_{M_n(D)}(S)$ be right multiplication by the identity matrix dI. Then: Then for all $x \in S$, we have:

$$\begin{aligned}\varphi\begin{pmatrix} x_1 & \cdots & 0 \\ \vdots & \ddots & \vdots \\ x_n & \cdots & 0 \end{pmatrix} &= \varphi\left(\begin{pmatrix} x_1 & \cdots & 0 \\ \vdots & \ddots & \vdots \\ x_n & \cdots & 0 \end{pmatrix}\begin{pmatrix} 1 & \cdots & 0 \\ \vdots & \ddots & \vdots \\ 0 & \cdots & 0 \end{pmatrix}\right) \\ &\overset{!}{=} \begin{pmatrix} x_1 & \cdots & 0 \\ \vdots & \ddots & \vdots \\ x_n & \cdots & 0 \end{pmatrix}\varphi\begin{pmatrix} 1 & \cdots & 0 \\ \vdots & \ddots & \vdots \\ 0 & \cdots & 0 \end{pmatrix} \\ &= \begin{pmatrix} x_1 & \cdots & 0 \\ \vdots & \ddots & \vdots \\ x_n & \cdots & 0 \end{pmatrix} \cdot d\end{aligned}$$

where $\overset{!}{=}$ comes from the fact that we can treat that matrix as an element of $M_n(D)$, and since φ is an $M_n(D)$-module homomorphism, we can pull it out. But then, the action is completely dependent on on d, an so we have a bijection between right multiplication by $d \in D$ an $M_n(D)$-endomrophisms. It is an easy taks to check that:

$$\varphi_{dd'} = \varphi_{d'} \circ \varphi_d$$

showing that

$$D^{\mathrm{op}} \cong_{\mathbf{Ring}} \mathrm{End}_{M_n(D)}(S)$$

as we sought to show.

The next thing we will need is to show that if R, S are semisimple rings, then so is $R \times S$. Since R and S are semi-simple R-modules and S-modules, if we can show that $R \times S$ is a semi-simple $(R \times S)$-module, we are done. For this to be the case, we must be able to decompose $R \times S$ into simple $(R \times S)$-submodules. Forunately, many universal propeties play in our favour to be able to easily identify simple $(R \times S)$-modules of $R \times S$ given we know the simple R-modules and S-modules.

To see the key idea of the following proof, we define some terms

Definition 51.2.9: Idempotent And Orthogonal Elements

Let R be a ring. Then $e \in R$ is said to be *idempotent* if

$$e^2 = e$$

Furthermore, if e_1, e_2 are idempotent elements in R, if

$$e_1 e_2 = e_2 e_1 = 0$$

then they are said to be *orthogonal*. If e is a nonzero idempotent and cannot be written as the sum of two nonzero orthogonal idempotent elements, then e is said to be a *primitive* idempotent element.

Example 51.2.10: Idempotent Elements

Naturally, for any ring R, $1 \in R$ is an idempotent element.

For a more interesting example the product ring $R \times S$, and take $e = (1,0) \in R \times S$, $f = (0,1) \in R \times S$. Then:

1. $e^2 = e$ and $f^2 = f$ (i.e. they are both *idempotent*)
2. $ef = fe = 0$ (implying also that $ef \in Z(R \times S)$)
3. $e + f = 1$ (i.e. e and f are *not* primitive)

What happens if the number of terms in the product increases?

Next, if M is an R-module an N is an S-module, we can M and N to be $(R \times S)$-module by ignoring what happens to S (resp. R), i.e. think of the action being defined by the following function

$$R \times S \twoheadrightarrow R \to \mathrm{End}_{\mathbf{ab}}(M)$$

and similarly for a S-module N. Hence, we can define $M \oplus N$ as an $(R \times S)$-module. Conversely, if M is an $(R \times S)$-module, then using what we have shown in example 51.2.10, given $e = (1,0)$ and $f = (0,1)$:

$$M = eM + fM$$

Notice that eM is killed by Rf, so it's a $A \cong A \times B/(\{0\} \times B)$-module, and similarly for fM. In other words, idempoent elements characterize the splitting of modules! This gives us the following:

Proposition 51.2.11: Direct Product Decomposition

Let A and B be rings, let $e = (1,0)$ and $f = (0,1)$ be the central idempotents of $A \times B$, and let A-**Mod** $\times$ B-**Mod** be the product category, whose objects are pairs (M, N) of an A-module M and a B-module N, and whose morphisms are pairs of module homomorphisms. For an $(A \times B)$-module P, the submodules eP and fP are an A-module and a B-module through $a \cdot x = (a,0)x$ and $b \cdot y = (0,b)y$. Then the functors

$$A\text{-}\mathbf{Mod} \times B\text{-}\mathbf{Mod} \underset{\psi}{\overset{\varphi}{\rightleftarrows}} (A \times B)\text{-}\mathbf{Mod}$$

defined on objects by

$$\begin{aligned} \varphi(M,N) &= M \oplus N \\ \psi(P) &= (eP, fP) \end{aligned}$$

where $(a,b) \cdot (m,n) = (am, bn)$ on $M \oplus N$, and on morphisms by $\varphi(\alpha, \beta) = \alpha \oplus \beta$ and $\psi(\gamma) = (\gamma|_{eP}, \gamma|_{fP})$, form an equivalence of categories: there are natural isomorphisms $\psi \circ \varphi \cong \mathrm{id}$ and $\varphi \circ \psi \cong \mathrm{id}$.

***Proof*:**

Step 1: φ is a functor. The module axioms for $M \oplus N$ hold componentwise, and $(1,1)$ acts as the identity. For morphisms $\alpha \colon M \to M'$ and $\beta \colon N \to N'$, the map $\alpha \oplus \beta \colon (m,n) \mapsto (\alpha(m), \beta(n))$

is additive and satisfies $(\alpha \oplus \beta)((a,b)(m,n)) = (a\alpha(m), b\beta(n)) = (a,b)(\alpha \oplus \beta)(m,n)$. Identities and composites are preserved componentwise.

Step 2: ψ is a functor. Since e is central, $(a,b)(ep) = e((a,b)p)$, so eP is an $(A \times B)$-submodule of P, and $ex = x$ for $x \in eP$ because $e^2 = e$. The rule $a \cdot x = (a,0)x$ is additive in a and in x, satisfies $(aa') \cdot x = (a,0)(a',0)x = a \cdot (a' \cdot x)$, and $1 \cdot x = ex = x$, so eP is an A-module. The same computation with f makes fP a B-module. If $\gamma\colon P \to P'$ is $(A \times B)$-linear, then $\gamma(ep) = e\gamma(p)$ shows $\gamma(eP) \subseteq eP'$, and $\gamma((a,0)x) = (a,0)\gamma(x)$ shows that $\gamma|_{eP}$ is A-linear. Likewise $\gamma|_{fP}\colon fP \to fP'$ is B-linear, and restriction preserves identities and composites.

Step 3: $\psi \circ \varphi \cong \mathrm{id}$. For (M,N), $e(m,n) = (m,0)$ and $f(m,n) = (0,n)$, so $\psi(\varphi(M,N)) = (M \oplus 0, 0 \oplus N)$, where $a \cdot (m,0) = (am,0)$ and $b \cdot (0,n) = (0,bn)$. Hence $\eta_{(M,N)} = (m \mapsto (m,0),\ n \mapsto (0,n))$ is a pair of module isomorphisms, that is, an isomorphism $(M,N) \to \psi(\varphi(M,N))$. For a morphism (α,β), the map $\psi(\varphi(\alpha,\beta))$ sends $(m,0)$ to $(\alpha(m),0)$ and $(0,n)$ to $(0,\beta(n))$, so $\psi(\varphi(\alpha,\beta)) \circ \eta_{(M,N)} = \eta_{(M',N')} \circ (\alpha,\beta)$, and η is natural.

Step 4: $\varphi \circ \psi \cong \mathrm{id}$. For an $(A \times B)$-module P, define

$$\epsilon_P\colon eP \oplus fP \to P \qquad (x,y) \mapsto x + y$$

For $x \in eP$ and $y \in fP$ we have $(a,b)x = (a,b)ex = (a,0)x$ and $(a,b)y = (0,b)y$, so $\epsilon_P((a,b)(x,y)) = (a,0)x + (0,b)y = (a,b)(x+y)$ and ϵ_P is $(A \times B)$-linear. It is surjective because $p = ep + fp$, as $e + f = 1$. It is injective: if $x + y = 0$, then $0 = e(x+y) = x + efy = x$, using $ex = x$, $y = fy$ and $ef = 0$, and then $y = 0$. For an $(A \times B)$-linear $\gamma\colon P \to P'$,

$$\epsilon_{P'}\big(\varphi(\psi(\gamma))(x,y)\big) = \gamma(x) + \gamma(y) = \gamma(\epsilon_P(x,y))$$

so ϵ is a natural isomorphism $\varphi \circ \psi \to \mathrm{id}$. Steps 3 and 4 show that φ and ψ are mutually inverse equivalences, as we sought to show.

Proposition 51.2.12: Classifying Simple $(A \times B)$-Modules

Let P be a simple $(A \times B)$-module. Then

$$P \cong_{A\times B\text{-Mod}} M \oplus (0) \qquad \text{or} \qquad P \cong_{A\times B\text{-Mod}} (0) \oplus N$$

where M is a simple A-module and N is a simple B-module.

***Proof*:**
By proposition 51.2.11, $P \cong_{A\times B\text{-Mod}} M \oplus N$ where M is an A-module and N is a B-module. BUt then:

$$P \cong_{A\times B\text{-Mod}} (M \oplus (0)) \oplus ((0) \oplus N)$$

since P is simple, one of these has to be zero, and the other one has to be simple.

Corollary 51.2.13: Product Of Semi-Simple Rings

Let R and S be semi-simple rings. Then $R \times S$ is a semi-simple ring. Furtheromre, if $R_1, R_2, ..., R_n$ are the simple R-module up to isomorphism and $S_1, S_2, ..., S_m$ are the simple S-modules, then the simple $R \times S$-modules are of the form:

$$R_i \oplus (0) \qquad (0) \oplus (S_j)$$

***Proof*:**
By proposition 51.2.11, since R is a semi-simple R-module and S is a semi-simple S-module, $R \times S$ is a semi-simple $(R \times S)$-module, and so $R \times S$ is a semi-simple ring. Then by proposition 51.2.12, if $P \subseteq R \times S$ is a simple $(R \times S)$-module, then they it must be of the form:

$$R_i \oplus (0) \qquad (0) \oplus (S_j)$$

Corollary 51.2.14: Structure Of $\prod_i M_{N_i}(D_i)$: Artin Wedderburn part II

Let $R = M_{n_1}(D_1) \times \cdots \times M_{n_k}(D_k)$. Then

1. R is semi-simple
2. There exist exactly k simple R-modules up to isomorphism, each of the form:

$$0 \oplus \cdots \oplus D_i^{\oplus n_i} \oplus \cdots \oplus 0$$

***Proof*:**
The ring R is semi-simpleby corollary 51.2.13 using induction. Furthermore, each $M_{n_i}(D_i)$ has $D_i^{\oplus n_i}$ is it's unique simple $M_{n_i}(D_i)$-module, since there are k matrix rings in the productt, there must be exactly k simple R-modules, as we sought to show.

51.2.15 Remark We can as before get that

$$R^{\text{op}} \cong M_{n_1}(D_1^{\text{op}}) \times \cdots \times M_{n_k}(D_k^{\text{op}})$$

and hence R^{op} is left Noetherian/Artinian, which we know now is true if and only if R is right Noetherian/Artinian (Since a left R^{op})-module is a right R-module). By leftNoethArtRemark, we have that any semisimple ring is left-Noetherian/Artinian, and hence any semisimple ring is both left and right Noetherian/Artinian, even though R is not necesarily commutative!

Thus, we have the following statemnt, were the last thing we need to prove is uniquness

Theorem 51.2.16: Artin-Wedderburn

Let R be a ring. Then R is a semi-simple ring if and only if

$$R \cong_{\textbf{Ring}} M_{n_1}(D_1) \times \cdots \times M_{n_k}(D_k)$$

where each D_k is a division ring and $M_{n_i}(D_i)$ is the matrix ring over D_i, and each D_i n_i are unique up to isomorphism

***Proof*:**
All that is left to prove is the uniqueness. Let:

$$M_{n_1}(D_1) \oplus \cdots \oplus M_{n_s}(D_s) \cong_{\textbf{Ring}} R \cong_{\textbf{Ring}} M_{n'_1}(D'_1) \oplus \cdots \oplus M_{n_s}(D'_s)$$

By corollary 51.2.14, R has exactly s and t simple module, and so $s = t$. Hence, for any $D_i^{\oplus n_i}$, there must exist a $(D'_i)^{\oplus n'_i}$ such that

$$D_i^{\oplus n_i} \cong_R (D'_i)^{\oplus n'_i}$$

Since $D_i^{\oplus n_i} \cong_R (D'_i)^{\oplus n'_i}$, $\text{End}_{M_{n_i}(D_i)}(D_i^{\oplus n_i}) \cong_{\textbf{Ring}} \text{End}_{M_{n'_i}(D'_i)}((D'_i)^{\oplus n'_i})$. By corollary 51.2.8,

$$D_i^{\text{op}} \cong_{\textbf{Ring}} \text{End}_{M_{n_i}(D_i)}(D_i^{\oplus n_i}) \cong_{\textbf{Ring}} \text{End}_{M_{n'_i}(D'_i)}((D'_i)^{\oplus n'_i}) \cong_{\textbf{Ring}} (D'_i)^{\text{op}}$$

which, taking op on both sides, we see that:

$$D_i \cong_{\textbf{Ring}} D'_i$$

Finally, we need to show that $D^{\oplus n} \cong_R D^{\oplus m}$ implies $n = m$. Treating $D^{\oplus n}$ and $D^{\oplus m}$ as D-modules, then we get that each have a basis of dimension n and m. Importantly, the results of the Replacement Theorem (theorem 13.1.12) applies to divions rings (notice that commutativity was not necessary), and so corollary 13.1.13 and theorem 13.1.8 give us that $n = m$, completing the proof.

This theorem also shows us that if R is a [finitely-generated] semi-simple ring, then R is indeed the direct product of simple rings (since $M_{n_i}(D_i)$ is a simple ring). Notice too that this theorem just gave us the answer to the classification of all *finite simple rings*: namely they would have ot be of the form $M_n(\mathbb{F}_q)$[8] for some finite field of order q (which is a power of some prime p). Contrast this to how hard it is to find all finite simple groups! Furthermore, the finite dimensional assumption was key: the *Weyl Algebra*:

$$W = k\langle x, y\rangle/(xy - yx - 1)$$

is a simple algebra that is not the matrix ring of a division algebra.

Example 51.2.17: Artin Wedderburn

$\text{End}_{M_2(k)}(M_2(k)) = \text{End}_{M_2(k)}((k^2)^{\oplus 2}) = M_2(\text{End}_{M_2(k)}(k^2)) = M_2(k)$

[8]Why is the division ring a field? The answer lies in proposition 9.1.20

Corollary 51.2.18: Artin-Wedderburn For k-Algebras

Let R be a semi-simple k-algebra that is finite-dimensional over a field k. Then

$$R \cong_{k\text{-}\mathbf{Alg}} M_{n_1}(D_1) \times \cdots \times M_{n_l}(D_l)$$

where each D_i is a divsion k-algebra, finite dimensional as a k-vector space:

$$\dim_k R = \sum n_i^2 \dim_k(D_i)$$

and has exactly l simple R-modules as we have classified before.

***Proof*:**
By the Artin-Wedderburn theorem, we have that

$$R \cong_{\mathbf{Ring}} M_{n_1}(D_1) \times \cdots \times M_{n_l}(D_l)$$

Let's now further assume R is a k-algebra for some field k, so that there is a map $k \hookrightarrow Z(R)$. Then by the above isomorphism:

$$\begin{aligned} k \mapsto Z(R) &\cong Z(M_{n_1}(D_1) \times \cdots \times M_{n_l}(D_l)) \\ &\cong Z(M_{n_1}(D_1)) \times \cdots \times Z(M_{n_l}(D_l)) \\ &\cong Z(D_1) \times \cdots \times Z(D_l) \end{aligned}$$

where the last one comes form the fact that $Z(M_{n_i}(D_i))$ are the diagonal elements, and $z \mapsto zI$. This shows that D_i each have a natural k-algebra strucure induced by R, and so the above isomrophsim was already a k-algebra isomorphism:

$$R \cong_{k\text{-}\mathbf{Alg}} M_{n_1}(D_1) \times \cdots \times M_{n_l}(D_l)$$

Finally, treating $M_{n_i}(D_i)$ as k-vector spaces we have:

$$M_{n_i}(D_i) \cong_{k\text{-}\mathbf{Vect}} D^{\oplus n_i^2}$$

which gives the desired result, completing the proof.

Corollary 51.2.19: Special Case: k Algebraically Closed

Let $k = \overline{k}$ be an algebraically closed field and D a division k-algebra that is finite-dimensional as a k-vector-space. Then $D = k$

***Proof*:**
Suppose $k \subsetneq D$, and pick any $\delta \in D \setminus k$. Then

$$k \subseteq k[\delta] \subseteq D$$

the key thing to observe is that $k[\delta]$ is still commutative!! This is essentially the same reasoning

for why any cyclic group is commutative! Since D is a finite-dimensional vector-sapce over k, some power of δ^n must be a k-linear combination of every smaller term. Since D is a division ring, every δ has an inverse, and so every element of $k[\delta]$ is in fact a unit. Hence $k[\delta]/k$ is an algebraic field extension. However, k is an *algebraically cloased field*, and hence $k[\delta] = k$. Since δ was arbitary, we must have that $D = k$, as we sought to show.

Corollary 51.2.20: Artin-Wedderburn For $\overline{k}$-Algebras

Let R be a semi-simple k-algebra that is finite-dimensional over an algebraically closed field $k = \overline{k}$. Then

$$R \cong_{k\textbf{-Alg}} M_{n_1}(k) \times \cdots \times M_{n_l}(k)$$

so that

$$\dim_k(R) = \sum_i^l n_i^2$$

and R has exactly l simple R-modules as we have classified before.

***Proof*:**
By corollary 51.2.18,

$$R \cong_{k\textbf{-Alg}} M_{n_1}(D_1) \times \cdots \times M_{n_l}(D_l)$$

where each D_i is a division k-algebra that is finite-dimensional over k, and R has exactly l simple modules. By corollary 51.2.19, each D_i is k, so $R \cong_{k\textbf{-Alg}} M_{n_1}(k) \times \cdots \times M_{n_l}(k)$, and $\dim_k(R) = \sum_i n_i^2 \dim_k(k) = \sum_i n_i^2$, as claimed.

As a consequence of this, if R is a semi-simple $\mathbb{C}$-algebra, the simple R-modules are all R-isomorphic to $\mathbb{C}^{n_i}$ for appropriate power n_i. As a final word of warning, it is natural to wonder if all simple rings are of the form $M_n(D_i)$

Exercise 51.2.1

1. Let k be a field, k^n be a direct product of fields a k^n-module over itslef. Let $0 \oplus \cdots \oplus k \oplus \cdots \oplus 0 = k_i \subseteq k^n$. Then $\text{End}_{k^n}(k_i) \cong_{\textbf{Ring}} k$, $\text{End}_{k^n}(k^n) \cong_{\textbf{Ring}} k^n$, and $\text{End}_{k^n}(k^n) \cong_{\textbf{Ring}} M_n(\text{End}_{k^n}(k_i)) \cong_{\textbf{Ring}} M_n(k)$. But that would imply $k^n \cong_{\textbf{Ring}} M_n(k)$ – what's the contradiction?
2. Let k be an algebraically closed field, and let R be a finite-dimensional k-algebra. Let M be a simple R-module. Prove that if r is an element of the centre $Z(R)$ of R, there exists $c \in k$ such that $rm = cm$ for all $m \in M$

51.3 Central Simple Algebras

Definition 51.3.1: Algebra Representation

Let A be a finite dimensional (associative) algebra over k. Then a *representation* of A is a k-homomorphism:

$$\rho : A \to \mathrm{End}_k(V)$$

for some vector space V.

Recall that one definition of an R-module is given by a ring homomorphism $\rho : R \to \mathrm{End}_{\mathbf{Ab}}(M)$ for an abelian group M. If we restrict to k-homomorphisms and k-endomorphisms, we can define the A-module $\rho : A \to \mathrm{End}_k(V)$, hence we can think of representation of and algebra A as a left A-modules. This makes sense, as representation theory can be thought of the study of associative algebras (the study of group representation is the study of group algebras, the study of the representation of lie algebras is universal enveloping algebras, the study of the representation of quiver algebras is the study of path algebras, and so forth). Because of this, we shall see that many of the results for the representation of associative algebras outlined bellow to be familiar to anyone who has taken a basic course in representation theory.

Next, we define the object that shall represent the generalization of number rings:

Definition 51.3.2: Central Simple Algebra

Let A be an algebra over a field k. Then A is called *simple* if it is a simple ring. It is called a *central simple algebra* (CSA) if it is simple, is finite dimensional over k, and its center is k.

The idea behind this definition is that it generalizes field extensions F/k, for we have a distinguished field k, and we are interested in the "algebraic case", hence the extension ought to be finite. Contrasting to fields, a CSA need not be commutative and need be a division ring

Example 51.3.3: Simple and Central Simple Algebras

1. Naturally, $M_n(k)$ is a central simple algebra of dimension n^2
2. It is possible to be simple and have center k but not be finite: the Weyl algebra $k[x, \delta_x]$ is infinite dimensional over k.
3. $\mathbb{C}$ is a central simple algebra over $\mathbb{C}$, but not over $\mathbb{R}$ (as it's center contains more than $\mathbb{R}$
4. Let $A = \mathbb{H}$ be the quaternions (or Hamiltonians). Then this is a CSA over $\mathbb{R}$ with dimension 4. We shall soon define a quaternion algebra, and see that all 4-dimensional central simples algebra's over a field k is a quaternion algebra, and it shall be limited to 2-by-2 matrices or division algebras.

Let us now generalize some of basic representation theory results. Let E be an irreducible representation of A (take for example a minimal left ideal of A).

Lemma 51.3.4: Schur's Lemma - updated

Let E be an irreducible representation of a k-algebra A, and let $K \subseteq \text{End}_k(E)$ be the endomorphisms that commute with the operations of A: it is the centralizer of A in $\text{End}_k(E)$, $K = C_{\text{End}_k(E)}(A)$. Then K is a division ring.

Note that this makes K an A-algebra

***Proof*:**
Take $u \in K$. We want to show that $u^{-1} \in K$. Consider $u^{-1}(0) = V \subseteq E$. For $x \in V$, we have:

$$0 = a \cdot u(x) = u(a \cdot x)$$

hence, V is stable under A, and as $u \neq 0$ we must have $V = 0$ as u is invertible in $\text{End}_k(E)$. It follows that $u^{-1} \in K$.

Notice from this that we may say that the representation E must be faithful (the map must be injective). Indeed, the kernel of this representation would be an ideal of A but

Lemma 51.3.5: Minimal Centralizer of Representations

Let E be a semi-simple an faithful representation of A, $K = C_{\text{End}_k(E)}(A)$, $B = C_{\text{End}_k(E)}(K)$ (i.e. the centralizer of A and K in $\text{End}_k(E)$). Then

$$A = B$$

***Proof*:**
Let $x \in E$ and $b \in B$. We shall show that there exists an $a \in A$ such that $a(x) = b(x)$.

Let $Ax = V \subseteq E$ be a stable subspace. Then V admits a (stable) compliment: $E = V \oplus V^{\perp}$. Let $\pi : E \to V$ be the natural projection map. Then certainly π is A-linear and commutes with K, namely $\pi \in K$. Then:

$$\pi(b(x)) = b(\pi(x)) = b(x)$$

namely, $b(x) \in V = aX$, implying $a(x) = b(x)$, as we sought to show.

Lemma 51.3.6: Generator lemma

Let E be a semi-simple an faithful representation of A, $K = C_{\text{End}_k(E)}(A)$, $B = C_{\text{End}_k(E)}(K)$ (i.e. the centralizer of A and K in $\text{End}_k(E)$). Let $x_1, ..., x_n \in E$ and $b \in B$. Then there exits values $a_i \in A$ such that:

$$ax_1 = bx_1,\ ax_2 = bx_2 \qquad \cdots \qquad ax_n = bx_n$$

***Proof*:**
Let F be the direct sum space of n copies of representation E. Then F is formed of elements $(y_1, ..., y_n)$, $y_i \in E$, on which A acts by

$$a \cdot (y_1, ..., y_n) = (ay_1, ..., ay_n)$$

The representation F is still semi-simple. The centralizer of A in $\mathrm{End}_k(F)$ is formed of matrices (u_{ij}), $u_{ij} \in K$, and it follows that, if we let B operate on F by the formula:

$$b \cdot (y_1, ..., y_n) = (by_1, ..., by_n)$$

the elements of $\mathrm{End}_k(F)$ thus defined will still be in the centralizer of the centralizer of A (in the theory of semi-groups, this is sometimes called the bicommutant). By lemma 51.3.5 applying to the point $x = (x_1, ..., x_n) \in F$, and to $b \in B$ giving us the desired result.

Serre write K_n for $M_n(K)$ for a division ring K, but we shall stick to $M_n(D)$ where our division ring is D instead of K. If D contains k in its center, we have:

$$M_n(D) = M_n(k) \otimes D$$

through $(a_{ij}) \otimes d \mapsto (a_{ij}d)$.

Let A be a k-algebra. Then A acting on itself by left multiplication gives something called the *regular left representation*. If $A = M_n(D)$, it has basis e_{ij}, $1 \leq i, j \leq n$. The elements e_{i,j_0} for a fixed j_0 gives a subspace of $M_n(D)$, say $N_{j_0} \subseteq M_n(D)$. The subspace N_{j_0} is a minimal left ideal (namely, an irreducible representation). Then we see that for any other choice of j_0, say j_1, we get an isomorphic irreducible representation N_{j_1}. The same holds for every finite-dimensional simple k-algebra.

Lemma 51.3.7: Decomposition Of A Simple Algebra Into Left Ideals

Let A be a nonzero finite-dimensional simple k-algebra. Then there are a simple left ideal I of A and elements $a_1, \ldots, a_m \in A$ such that $A = Ia_1 \oplus \cdots \oplus Ia_m$ and $Ia_j \cong I$ as A-modules for every j.

***Proof*:**
Left ideals of A are k-subspaces, since $\lambda x = (\lambda 1)x$ for $\lambda \in k$.

Step 1: A simple left ideal. As $A \neq 0$ is finite-dimensional, it has a nonzero left ideal I of smallest k-dimension among the nonzero left ideals. Every nonzero A-submodule of I is a left ideal of dimension at most $\dim_k I$, hence equal to I, so I is a simple A-module.

Step 2: A is a sum of copies of I. For $a \in A$, the set Ia is a left ideal, and $x \mapsto xa$ is a surjective A-module homomorphism $I \to Ia$. Its kernel is a submodule of the simple module I, so either $Ia = 0$ or $Ia \cong I$. The sum $J = \sum_{a \in A} Ia$ is a left ideal with $Jb \subseteq \sum_{a \in A} I(ab) \subseteq J$ for every $b \in A$, so J is a two-sided ideal, and $J \supseteq I \cdot 1 = I \neq 0$. As A is simple, $J = A$.

Step 3: A direct decomposition. Among the finite families $a_1, \ldots, a_m$ of elements of A such that each Ia_j is nonzero and the sum $Ia_1 + \cdots + Ia_m$ is direct (the empty family is one), choose one with m largest, which is possible because $m \dim_k I \leq \dim_k A$. Let $D = Ia_1 \oplus \cdots \oplus Ia_m$. For $a \in A$ with $Ia \neq 0$, the intersection $Ia \cap D$ is a submodule of the simple module Ia. If it were 0, the sum $D + Ia$ would be direct, and the family $a_1, \ldots, a_m, a$ would contradict the maximality of m. Hence $Ia \subseteq D$ for every $a \in A$, and $A = J = D$. Each Ia_j is nonzero, so $Ia_j \cong I$ by Step 2, as claimed.

Theorem 51.3.8: Representation of Simple Algebra

Let A be a finite-dimensional simple k-algebra. Then every representation of A is isomorphic to a direct sum of irreducible representations.

***Proof*:**
If $A = 0$, every A-module is 0, the empty direct sum, so assume $A \neq 0$.

Step 1: A is a semi-simple ring. By lemma 51.3.7, A is the internal direct sum of the simple submodules Ia_j, so A is a semi-simple A-module by lemma 51.1.7 and a semi-simple ring by corollary 51.1.9.

Step 2: Representations. A representation $\rho\colon A \to \mathrm{End}_k(V)$ is the left A-module V with $a \cdot v = \rho(a)v$, and its subrepresentations are exactly its A-submodules, so its irreducible subrepresentations are its simple submodules. Since A is a semi-simple ring, V is a semi-simple A-module by definition 51.1.2, that is a direct sum of simple modules by lemma 51.1.7. So every representation of A is a direct sum of irreducible representations, as claimed.

Corollary 51.3.9: Representations of a Simple Algebra Are Determined by Dimension

Let A be a finite-dimensional simple k-algebra. Then:

1. All representations of A are semi-simple (completely reducible in Serre's words)
2. Two representations of A which have the same dimension are isomorphic

***Proof*:**
Part (1) is theorem 51.3.8. For (2) we may assume $A \neq 0$, since otherwise every representation is 0. Let I and $a_1, \ldots, a_m$ be as in lemma 51.3.7, so that $A = Ia_1 \oplus \cdots \oplus Ia_m$ with each $Ia_j \cong I$.

Step 1: Every simple A-module is isomorphic to I. Let S be a simple A-module and $0 \neq s \in S$. The homomorphism $A \to S$, $a \mapsto as$, sends 1 to $s \neq 0$, so its restriction to some Ia_j is nonzero, and this restriction $Ia_j \to S$ is an isomorphism by lemma 51.1.5. Hence $S \cong Ia_j \cong I$.

Step 2: The dimension determines the representation. By part (1) and Step 1, a representation V is isomorphic to a direct sum $\bigoplus_{t \in T} I$ of copies of I, so $\dim_k V = |T| \dim_k I$ with $0 < \dim_k I < \infty$. If $\dim_k V$ is finite, then $|T| = \dim_k V / \dim_k I$, and if it is infinite, then $|T| = \dim_k V$. Two representations of the same dimension are therefore direct sums of the same number of copies of I, hence isomorphic, as claimed.

Let us now turn towards the tensor product of simple algebras.

Lemma 51.3.10: Centralizer of Tensor Product of Algebras

Let A, A' be two k-algebras, B, B' be sub k-algebras of A, A' (respectively) with C, C' their centralizers on A, A' (respectively). Then the centralizer of $B \otimes B'$ in $A \otimes A'$ is $C \otimes C'$.

***Proof*:**
Let us first find the centralizer of $B \otimes 1$. For this, let a_i' be a basis of A'. Any $x \in A \otimes A'$ can be written uniquely in the form:

$$x = \sum_i a_i \otimes a_i' \qquad \text{for appropriate } a_i \in A$$

If x commutes with $b \otimes 1$, then $a_i b = b a_i$ that is $a_i \in C$ for all i. We thus see that the centralizer of $B \otimes 1$ is $C \otimes A'$. Similarly, that of $1 \otimes B'$ is $A \otimes C'$. It follows that the centralizer of $B \otimes B'$ is equal to the intersection of the centralizers of $B \otimes 1$ and $1 \otimes B'$, namely

$$(C \otimes A') \cap (A \otimes C') = C \otimes C'$$

as we sought to show.

Thus, the centre of the tensor product of two algebras is the tensor product of the centre of the two algebras. Applying this to the special case of $A = M_n(k) \otimes D$ for some division ring D, then:

$$Z(A) = k \otimes Z(D)$$

Corollary 51.3.11: Centre of simple algebra is a Field

Let A be a simple k-algebra, finitely generated over k. Then $Z(A)$ is a field.

***Proof*:**
Consider $Z(A)$. As A is a finitely generated k-algebra, $Z(A)$ is a finitely generated k-algebra. For any $0 \neq z \in Z(A)$, consider zA. As z is central,we have that zA is two-sided ideal. As A is simple, it must be that $zA = A$, that is z is there exists a $w \in A$ such that $za = 1$. Therefore, $Z(A)$ is a division ring. It is by definition commutative, and hence it is a field. Since z was an arbitrary nonzero element, $Z(A)$ is a division ring. It is by definition commutative, and hence it is a field.

We shall next require to see the interaction between the tensor product of central simple algebras. We require the following lemma:

Theorem 51.3.12: Ideal Generation Tensor Product

Let A be a k-algebra and K' a left division ring with center k. Then every ideal $N \subseteq A \otimes K'$ is generated (as a left module over K') by its intersection with $A \otimes 1$.

Note that neither A nor K' are assumed finite over k

***Proof*:**
We will first note that we can make K' operate on the left on $A \otimes K'$ by:

$$k'(a \otimes k'') = a \otimes k'k''$$

If N is an ideal of the algebra $A \otimes K'$, it is in particular a K'-module subspace of $A \otimes K'$.

Let a_i be a basis of A over k; the elements $a_i \otimes 1$ equally form a basis of the K'-module $A \otimes K'$. Let x be a primitive element of N with respect to this basis (Bourbaki, Alg.II, paragraph 5):

$$x = \sum_i a_i \otimes k'_i$$

Consider the element $x \cdot m$ ($m \in K'$); we have $x \cdot m \in N$ (N is an ideal), and on the other hand:

$$x \cdot m = \sum_i a_i \otimes k'_i m$$

It then follows from the properties of primitive elements that we have:

$$k'_i m = n k'_i \text{ for all } i \quad (n \in K')$$

Since one of the k'_i is equal to 1, we have $m = n$, and the preceding equality simply means that k'_i commutes with all $m \in K'$, i.e., that $k'_i \in k$. We can then write: $x = a \otimes 1$, by setting: $a = \sum_i k'_i a_i$. We have thus shown that every primitive element x is in $A \otimes 1$; the theorem follows immediately since every vector space is generated by its primitive elements.

Theorem 51.3.13: Tensor Product CSA

Let A, A' be simple k-algebras finitely generated over k, where one of them is a CSA. Then $A \otimes A'$ is a simple k-algebra

***Proof*:**
Suppose that $A' = M_n(k) \otimes K'$ is central, in other words that the center of the left field K' is reduced to k. It will suffice to show that $A \otimes K'$ is a simple algebra. Indeed, if this is demonstrated, $A \otimes K' = M_m(k) \otimes K''$, and $A \otimes A' = M_m(k) \otimes M_n(k) \otimes K'' = M_{mn}(k) \otimes K'' = M_{nm}(K'')$. The algebra $A \otimes A'$ will thus be isomorphic to a matrix algebra for which simplicity is immediately verified. Then the general case of $A \otimes K'$ being simple follow from theorem 51.3.12, completing the proof.

Corollary 51.3.14: Tensor Product of Two CSA's

The tensor product of two CSA is a CSA

***Proof*:**
In the previous proof, it was enough for one of them to be a CSA.

Corollary 51.3.15: Opposite Algebra Tensoring

Let A be a CSA over k and A^{op} the opposite algebar. Then:

$$A \otimes A^{\text{op}} \cong M_{n^2}(k)$$

***Proof*:**
Let us denote by E the algebra A considered as a vector space over k. We can make A act naturally on E by the left or right by multiplication to create a left or right A-module. This amounts to identifying A and A^{op} as sub-algebras of the algebra $\text{End}_k(E)$ of k-endomorphisms of E. Since the algebras A and A^{op} commute in $\text{End}_k(E)$, we can define a canonical homomorphism of $A \otimes A^{\text{op}}$ into $\text{End}_k(E)$ which extends the isomorphisms: $A \to \text{End}_k(E)$ and $A^{\text{op}} \to \text{End}_k(E)$. The algebra $A \otimes A^{\text{op}}$ being simple, this homomorphism is an isomorphism; moreover, as;

$$[A \otimes A^{\text{op}} : k] = [A : k]^2 = n^2 = [\text{End}_k(E) : k]$$

this isomorphism maps $A \otimes A^{\text{op}}$ onto $\text{End}_k(E) = M_{n^2}(k)$, as we sought to show.

51.3.1 Brauer Group

Let A be a CSA over k. As A is simple, we get by Artin-Wedderburn that it is isomorphic to $M_n(D) \cong M_n(k) \otimes D$. For example, if $n = 1$ and $k = \mathbb{R}$ we get (by a classical theorem from algebraic topology) that $A \cong \mathbb{R}$ or $A \cong \mathbb{H}$ (the quaternions). If $n > 1$, we get $M_n(\mathbb{R})$ and $M_n(\mathbb{H})$ (which are no longer division algebras). We see that the division ring is one of the "characterizing" feature of the CSA (the other being its matrix ring), especially that up to Morita-equivalence we get the same category. We thus have the following natural equivalence we may define:

Definition 51.3.16: Brauer Equivalence

Let k-**CSA** be a collection of central simple algebras over k. Then define the equivalence relation $A \sim A'$ where the two are equivalent if and only if their associated division rings are isomorphic.

Proposition 51.3.17: Brauer Group

The Brauer equivalence on a collection of CSA's forms a commutative group under the tensor product. This group will be denoted $\text{Br}(k)$.

In Serre, this group is denoted G_k.

***Proof*:**
By corollary 51.3.14, it is closed under the tensor product, the equivalence class containing k is certainly the identity, and corollary 51.3.15 shows that every equivalence class has an inverse. Associativity and commutativity is a classical result for tensor products.

Example 51.3.18: Brauer Groups

1. Let $k = \overline{k}$. Then $\mathrm{Br}(\overline{k}) = 0$ by corollary 51.2.20.
2. If $k = \mathbb{R}$, then we shall show in the next section that $\mathrm{Br}(\mathbb{R}) = \mathbb{Z}/2\mathbb{Z}$, namely we shall have $\mathbb{R}$ and $\mathbb{H}$, the quaternions.
3. Let k be a finite field. Then $\mathrm{Br}(k) = 0$, as all finite division rings are fields (theorem 19.7.20).
4. If $k = \mathbb{Q}_p$, then $\mathrm{Br}(k) \cong \mathbb{Q}/\mathbb{Z}$ (Serre references Algebren - Chap. VII - 2nd paragarph).
5. If $k = \mathbb{Q}$, $\mathrm{Br}(\mathbb{Q})$ will be a subgroup of

$$\mathbb{Z}/2\mathbb{Z} \oplus (\mathbb{Q}/\mathbb{Z})^{\oplus \mathbb{N}}$$

which can be thought of as a result similar to that in number theory where we study the "global field" $\mathbb{Q}$ by looking at all its localizations (note that $\mathbb{Z}/2\mathbb{Z}$ comes from $\mathrm{Br}(\mathbb{R})$!) Serre references Deuring for the proof (see Sere p.8)

Theorem 51.3.19: Field Extensions and CSA

Let A be a CSA over k, L/k a field extension (either finite or infinite). Then $A \otimes L$ is simple

***Proof*:**
If A is a division ring, then all ideals of $A \otimes L$ will be given with in part with the intersection of the ideals of L, which is simply (0), making $A \otimes L$ simple.

If A is any CSA, write $A \cong M_n(k) \otimes D$. Then:

$$A \otimes L \cong M_n(k) \otimes (D \otimes L) \overset{!}{=} M_n(k) \otimes M_m(D')$$

where for $\overset{!}{=}$, D' is the division ring naturally given by $D \otimes_k L$! But this gives the result.

Corollary 51.3.20: Index of CSA

Let A be a simple, central and finite algebra over k. Then $[A : k]$ is a perfect square.

***Proof*:**
Let L be an algebraically closed extension of k. The algebra $A \otimes L$ can be endowed with an algebra structure over L, and we have:

$$[A \otimes L : L] = [A : k]$$

But $A \otimes L$ is a simple algebra, central over L, and finite over L. It then follows from example 51.3.18[1] that it is a matrix algebra over L, and $[A \otimes L : L]$ is indeed a perfect square.

Looking at the field extension of a k-algebra, it is natural to consider that $- \otimes_k L$ gives a homomorphism

of Brauer groups $\varphi_{k,L} : \mathrm{Br}(k) \to \mathrm{Br}(L)$, namely due to the following result from linear algebra:

$$(A \otimes_k L) \otimes_L (A' \otimes_k L) \cong (A \otimes_k A') \otimes_k L$$

The kernel $\ker \varphi_{k,L}$ consists of all k-algebra's that become trivial (matrix algebras) when extending to L. Serre calls these algebras the algebras that *admit L as a field of decomposition.* (or admit a decomposition by L). More recently, the term *splitting field* is adopted due to the parallels to number theory. Naturally, if $L = \overline{k}$, then every algebra admits a decomposition as $\mathrm{Br}(\overline{k}) = 0$. We only require a finite extension:

Theorem 51.3.21: Splitting Field is Finite

The Brauer group $\mathrm{Br}(k)$ is the union of $\ker \varphi_{k,L}$ going over each L/k where L is a finite field extension. In particular, there exists a finite extension L/k such that for a CSA A over k, $[A \otimes_k L] = [1]$ in $\mathrm{Br}(L)$.

***Proof*:**

By example 51.3.18[1] we have that for a CSA A over $\overline{k}$, $A \otimes_k \overline{k} \cong M_n(D)$. Then the right hand side is generated by finitely many elements of the left hand side. We need only take the elements that map to the generators of the right hand side and to choose the appropriate field elements to get find L/k, as we sought to show.

51.4 Build up to Quaternion Algebras

Theorem 51.4.1: Skolem-Noether Theorem

Let A, B be CSA's over k, and let $f, g : A \to B$ be k-algebra isomorphism. Then there exists a unit $b \in B$ such that:

$$g(a) = bf(a)b^{-1}$$

In particular, every automorphism is an inner automorphism

***Proof*:**

Let's first prove the special case of $B = M_n(k)$. Then the isomorphisms $f, g : A \to M_n(k)$ define actions on k^n, or said differently these define two A-modules (with two different actions): V_f, V_g. Then using f, g we have an A-module isomorphism $g \circ f^{-1} : V_f \to V_g$. But any isomorphism between vector-spaces is representable as (unit) matrix in $M_n(k)$, and so we we get our value by linear algebra.

For the general case, we know that $B \otimes_k B^{\mathrm{op}} \cong M_n(k)$ and $A \otimes_k B^{\mathrm{op}}$ is simple as B^{op} is still simple (use theorem 51.3.13). As $B \otimes_k^B \mathrm{op}$ is a (finite dimensional) matrix algebra, we may apply our special case to:

$$f \otimes 1,\ g \otimes 1 : A \otimes_k B^{\mathrm{op}} \to B \otimes_k B^{\mathrm{op}} \cong M_n(k)$$

which shows that:

$$(f \otimes 1)(a \otimes c) = b(g \otimes 1(a \otimes c)b^{-1}$$

which is true for all $a \in A$ and $c \in B^{\text{op}}$. Thus, it is true for $a = 1$, giving us:

$$1 \otimes c = b(1 \otimes c)b^{-1}$$

for all $c \in B^{\text{op}}$. Thus,

$$b \in Z_{B \otimes_k B^{\text{op}}}(k \otimes B^{\text{op}}) = B \otimes k$$

Hence, as constants move through the tensor we get that $b = b \otimes_k 1$. And so, by setting $z = 1$, we find:

$$f(a) = b' g(a) {b'}^{-1}$$

as we sought to show.

Theorem 51.4.2: Centralizer of Subalgebras

Let A be a CSA over k, $B \subseteq A$ a simple subalgebra, $C = C_A(B)$ the centralizer of B in A. Then C is simple, $B = C_A(C)$, and:

$$[B : k][C : k] = [A : k]$$

***Proof*:**
Let E be B with only the structure of a k-vector space. Then B acts on E via left multiplication; this action isomorphically embeds B into $\text{End}_k(E)$. Then the centralizer of B in $\text{End}_k(E)$ is nothing more than the algebra of right translations by E, that is B^{op}.

Given this, we can consider the simple algebra $A \otimes_k \text{End}_k(E)$. We can now embed B into this tensored algebra in two ways: via $B \otimes 1$ or $1 \otimes B$. Their centralizers are $C \otimes \text{End}_k(E)$ and $A \otimes B^{\text{op}}$ respectively.

By theorem 51.4.1, there exists an inner automorphism of $A \otimes_k \text{End}_k(E)$ mapping $B \otimes 1$ to $1 \otimes B$; it is then a simple algebra exercise to see that this inner automorphism induces a map on the centralizers. As a consequence, as $A \otimes B^{\text{op}}$ is simple, so is $C \otimes \text{End}_k(E)$, which must make C simple.

Furthermore:

$$[C \otimes \text{End}_k(E) : k] = [C : k][B : k]^2 \qquad \text{and} \qquad [A \otimes B^{\text{op}} : k][A : k][B : k]$$

From which we get $[A : k] = [B : k][C : k]$. What's left to show is the centralizer of C in A is B. Say that B' is this centralizer. Then $B \subseteq B'$. Then as $[A : k] = [B : k][C : k]$, we get:

$$[B' : k] = [B : k]$$

But then as they contain we must get $B = B'$, completing the proof.

52

The Jacobson Radical and Non-Semisimple Algebras

The Artin-Wedderburn theorem (theorem 51.2.16) is a complete answer to a narrow question: it classifies the semisimple rings and, in the process, shows that a semisimple k-algebra is nothing more than a finite product of matrix rings over division algebras. When R is semisimple, every module splits into simples, every short exact sequence splits, and the entire representation theory of R collapses onto the finite list of its simple modules. This is the best possible situation, and it is also the exception. The algebras whose representation theory occupies most of this book are precisely the ones that fail to be semisimple: the group algebra $k[G]$ when $\mathrm{char}(k)$ divides $|G|$ (where Maschke's theorem breaks down), the truncated polynomial algebra $k[x]/(x^n)$, universal enveloping algebras of Lie algebras, and the path algebra of a quiver with an oriented cycle. For all of these, some module fails to be a direct sum of simples, some sequence refuses to split, and Wedderburn has nothing to say.

This chapter builds the tools that take over where Wedderburn stops. The first of these, and the subject of the present section, is the *Jacobson radical* $\mathrm{Jac}(A)$: the two-sided ideal that measures, in a single invariant, exactly how far A is from being semisimple. It is the obstruction that vanishes precisely when A is semisimple, and dividing it out always produces a semisimple ring $A/\mathrm{Jac}(A)$ whose simple modules are the same as those of A. In the sections that follow, the radical becomes the engine behind the theory of indecomposable modules and the Krull-Schmidt theorem (which replaces "decomposition into simples" with "decomposition into indecomposables"), and behind the construction of projective covers, which repair the failure of projectivity that semisimplicity had guaranteed for free. The radical is where the non-semisimple story begins.

52.1 The Jacobson Radical

Throughout chapter 51 the simple modules did all the work: a semisimple ring was assembled out of its minimal left ideals, and every module was a direct sum of simples. When a ring is *not* semisimple, the simple modules are still present, but they no longer see everything. Some elements of the ring act as zero on every simple module without being zero themselves, and these elements form an ideal that records the discrepancy. To isolate them, we begin one level down, with modules, and ask which part of a module is invisible to all of its simple quotients.

The maximal submodules of a module M are exactly the kernels of the surjections $M \twoheadrightarrow S$ onto simple modules: a submodule $N \subseteq M$ is maximal precisely when M/N is simple, and every simple quotient of M is of the form M/N for such an N (the classification of simples as quotients by maximal left ideals is lemma 51.1.3). An element lying in every maximal submodule is one that every simple quotient sends to zero. Collecting these gives the radical of a module.

Definition 52.1.1: Radical of a Module

Let M be a left A-module. The *radical* of M, written $\operatorname{rad}(M)$, is the intersection of all maximal submodules of M:

$$\operatorname{rad}(M) = \bigcap_{\substack{N \subseteq M \\ N \text{ maximal}}} N$$

If M has no maximal submodules, the intersection is empty and $\operatorname{rad}(M) := M$ by convention.

Since each maximal submodule is the kernel of a map onto a simple module, an equivalent description is

$$\operatorname{rad}(M) = \bigcap_{\substack{\varphi\colon M \to S \\ S \text{ simple}}} \ker(\varphi)$$

so that $\operatorname{rad}(M)$ is the set of elements killed by *every* homomorphism from M into a simple module. The quotient $M/\operatorname{rad}(M)$ is the largest quotient of M that embeds into a product of simple modules; it is the *semisimple quotient* of M, the part of M that its simple quotients can detect. Everything inside $\operatorname{rad}(M)$ is invisible to them.

Example 52.1.2: The Radical of a Cyclic $\mathbb{Z}$-Module

Take $A = \mathbb{Z}$ and $M = \mathbb{Z}/12\mathbb{Z}$. The maximal submodules of M correspond to the maximal ideals of $\mathbb{Z}$ containing $12\mathbb{Z}$, that is to the primes dividing 12, namely 2 and 3. The corresponding maximal submodules are $2\mathbb{Z}/12\mathbb{Z}$ and $3\mathbb{Z}/12\mathbb{Z}$, with simple quotients $\mathbb{Z}/2\mathbb{Z}$ and $\mathbb{Z}/3\mathbb{Z}$. Their intersection is

$$\operatorname{rad}(\mathbb{Z}/12\mathbb{Z}) = \frac{2\mathbb{Z}}{12\mathbb{Z}} \cap \frac{3\mathbb{Z}}{12\mathbb{Z}} = \frac{6\mathbb{Z}}{12\mathbb{Z}}$$

so $\operatorname{rad}(M) = 6\mathbb{Z}/12\mathbb{Z} \cong \mathbb{Z}/2\mathbb{Z}$, and the semisimple quotient is $M/\operatorname{rad}(M) \cong \mathbb{Z}/6\mathbb{Z} \cong \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/3\mathbb{Z}$. The radical has stripped $\mathbb{Z}/12\mathbb{Z}$ down to its squarefree quotient: the extra factors of 2 and 3 that no simple quotient can see are exactly what lies in $6\mathbb{Z}/12\mathbb{Z}$.

Applying this construction to the ring itself, viewed as a module over itself, produces the central object of the chapter. The radical of A as a left A-module is the intersection of its maximal *left* ideals.

Definition 52.1.3: Jacobson Radical

Let A be a ring. The *Jacobson radical* of A, written $\mathrm{Jac}(A)$, is the radical of A regarded as a left module over itself, that is the intersection of all maximal left ideals of A:

$$\mathrm{Jac}(A) = \mathrm{rad}({}_AA) = \bigcap_{\substack{\mathfrak{m}\subseteq A \\ \mathfrak{m} \text{ maximal left ideal}}} \mathfrak{m}$$

The definition is one-sided: it uses left ideals, and a priori $\mathrm{Jac}(A)$ need only be a left ideal. One of the first surprises is that the resulting set is symmetric, a two-sided ideal that could equally have been defined with maximal *right* ideals. This symmetry, and several other faces of the same object, are the content of the next theorem. Before stating it, recall that an element $u \in A$ is *left-invertible* if there exists $v \in A$ with $vu = 1$.

Theorem 52.1.4: Characterizations of the Jacobson Radical

Let A be a ring and let $a \in A$. The following subsets of A coincide, and their common value is $\mathrm{Jac}(A)$:

1. the intersection of all maximal left ideals of A;
2. the intersection of the annihilators $\mathrm{Ann}_A(S)$ of all simple left A-modules S;
3. the set $\{a \in A \mid 1 - xa \text{ is left-invertible for all } x \in A\}$.

Consequently, $\mathrm{Jac}(A)$ is a two-sided ideal of A, and it is the largest two-sided ideal of A that annihilates every simple left A-module.

The three descriptions look at the same ideal from three angles. The first is the definition. The second recasts it representation-theoretically: $\mathrm{Jac}(A)$ is exactly the set of elements that act as zero on every simple module, which is why it is invisible to the simple representation theory. The third is an intrinsic ring-theoretic criterion that never mentions modules at all, and it is the one that makes the two-sidedness fall out for free, since it is symmetric in a way the definition is not.

***Proof*:**
We prove (1) = (2), then (2) = (3), and finally read off the two-sidedness and maximality statements.

Step 1: (1) = (2). Let J_1 denote the intersection of all maximal left ideals and J_2 the intersection of the annihilators of all simple left modules. If S is a simple left A-module, then for any $0 \neq s \in S$ we have $S = As$ (as As is a nonzero submodule of the simple module S), and by corollary 51.1.4 the map $a \mapsto as$ gives $S \cong A/\mathrm{Ann}_A(s)$ with $\mathrm{Ann}_A(s)$ a maximal left ideal. The annihilator of the whole module is

$$\mathrm{Ann}_A(S) = \bigcap_{0\neq s\in S} \mathrm{Ann}_A(s)$$

an intersection of maximal left ideals, so $J_1 \subseteq \mathrm{Ann}_A(S)$ for every simple S, giving $J_1 \subseteq J_2$. Conversely, if $\mathfrak{m}$ is any maximal left ideal, then $S = A/\mathfrak{m}$ is a simple left module and $\mathrm{Ann}_A(S) \subseteq \mathfrak{m}$ (since $\mathrm{Ann}_A(S)$ kills the coset $1 + \mathfrak{m}$, so $\mathrm{Ann}_A(S) \cdot 1 \subseteq \mathfrak{m}$). Hence $J_2 \subseteq \mathfrak{m}$ for every maximal left ideal $\mathfrak{m}$, giving $J_2 \subseteq J_1$. Thus $J_1 = J_2$.

Step 2: (2) $\subseteq$ (3). Let $a \in J_2$, so a annihilates every simple left module, and fix $x \in A$. We must show $1 - xa$ is left-invertible. If not, then $A(1-xa)$ is a proper left ideal, hence contained in some maximal left ideal $\mathfrak{m}$ (using that $1 \notin A(1-xa)$ and Zorn's lemma). The quotient $S = A/\mathfrak{m}$ is simple, so a annihilates it: $a \cdot (1 + \mathfrak{m}) = 0$, meaning $a \in \mathfrak{m}$. But $xa \in \mathfrak{m}$ as well, since $\mathfrak{m}$ is a left ideal, and $1 - xa \in \mathfrak{m}$ since $1 - xa \in A(1-xa) \subseteq \mathfrak{m}$. Adding, $1 = (1-xa) + xa \in \mathfrak{m}$, contradicting that $\mathfrak{m}$ is proper. Hence $1 - xa$ is left-invertible for every x, so $a \in J_3$, the set in (3).

Step 3: (3) $\subseteq$ (2). Let $a \in J_3$, and suppose toward a contradiction that a does *not* annihilate some simple left module S. Then $as \neq 0$ for some $s \in S$, and since As is a nonzero submodule of the simple module S we have $As = S$. In particular $s \in As$, so $s = xas$ for some $x \in A$, giving $(1-xa)s = 0$. By hypothesis $1 - xa$ is left-invertible, say $v(1-xa) = 1$; applying v gives $s = v(1-xa)s = 0$, contradicting the choice of s. Hence a annihilates every simple module, so $a \in J_2$.

Combining the three steps, $J_1 = J_2 = J_3 = \mathrm{Jac}(A)$.

Step 4: two-sidedness and maximality. As the intersection of the left ideals $\mathrm{Ann}_A(S)$, description (2) shows $\mathrm{Jac}(A)$ is a left ideal. But each $\mathrm{Ann}_A(S)$ is in fact a two-sided ideal: if $a \in \mathrm{Ann}_A(S)$ and $b \in A$, then for all $s \in S$ we have $(ab)s = a(bs) = 0$, so $ab \in \mathrm{Ann}_A(S)$. An intersection of two-sided ideals is two-sided, so $\mathrm{Jac}(A)$ is a two-sided ideal. Finally, if I is any two-sided ideal annihilating every simple left module, then $I \subseteq \mathrm{Ann}_A(S)$ for every simple S, hence $I \subseteq \bigcap_S \mathrm{Ann}_A(S) = \mathrm{Jac}(A)$; thus $\mathrm{Jac}(A)$ is the largest such ideal, completing the proof.

The left-invertibility criterion (3) deserves a second look, because it is what makes the radical robust. It says a lies in the radical exactly when $1 - xa$ can never be turned into a non-unit by any left multiplier x. A standard manipulation upgrades "left-invertible" to "two-sided invertible" for these particular elements: if $a \in \mathrm{Jac}(A)$ and $v(1-xa) = 1$, then $v = 1 + vxa = 1 - (-vx)a$, and since $a \in \mathrm{Jac}(A)$ the element v is itself left-invertible by the same criterion; a left-invertible element with a left-invertible left inverse is a unit. So for $a \in \mathrm{Jac}(A)$ the element $1 - xa$ is a two-sided unit for every x, and by the right-handed version of the whole theorem $1 - ax$ is a unit as well. This is the working form of the radical: $\mathrm{Jac}(A)$ is the set of elements a such that $1 - xay$ is a unit for all $x, y \in A$, and it is exactly this that will drive Nakayama's lemma below.

Description (2) also settles the two-sided nature of the radical without any of the asymmetry of the original definition, and it makes precise the sense in which the radical is invisible to representation theory. If A is semisimple, every module is a sum of simples, so an element killing all simples kills everything: $\mathrm{Jac}(A) = 0$. The content of the non-semisimple theory is that $\mathrm{Jac}(A)$ can be nonzero, and it is this ideal that the simple modules fail to detect.

Before turning to that theory, the radical of a ring is anchored by two computations. The first is the archetype of a local non-semisimple algebra.

Example 52.1.5: The Radical of a Truncated Polynomial Algebra

Let k be a field and let $A = k[x]/(x^n)$ with $n \geq 1$, writing $\bar{x}$ for the image of x. This is a commutative local ring: an element $f(\bar{x}) = c_0 + c_1\bar{x} + \cdots + c_{n-1}\bar{x}^{n-1}$ is a unit if and only if $c_0 \neq 0$, since when $c_0 = 0$ the element is nilpotent ($\bar{x}^n = 0$ forces $f(\bar{x})^n = 0$), and when $c_0 \neq 0$ one inverts using the geometric series, which terminates because $\bar{x}^n = 0$:

$$(c_0 + \bar{x}g)^{-1} = c_0^{-1}\big(1 + c_0^{-1}\bar{x}g\big)^{-1} = c_0^{-1}\sum_{j=0}^{n-1}(-c_0^{-1}\bar{x}g)^j$$

The non-units are therefore exactly the elements with $c_0 = 0$, which is the ideal $(\bar{x})$. In a commutative ring the maximal ideals are the maximal left ideals, and here there is a single maximal ideal, namely $(\bar{x})$, because $A/(\bar{x}) \cong k$ is a field while any element outside $(\bar{x})$ is a unit. Hence

$$\mathrm{Jac}(A) = (\bar{x}) = \{c_1\bar{x} + c_2\bar{x}^2 + \cdots + c_{n-1}\bar{x}^{n-1} \big| c_i \in k\}$$

This ideal is nilpotent: $(\bar{x})^n = (\bar{x}^n) = 0$, so already $\mathrm{Jac}(A)^n = 0$. The quotient $A/\mathrm{Jac}(A) = A/(\bar{x}) \cong k$ is a field, hence semisimple, which is the general phenomenon established in theorem 52.1.9. The single simple A-module is $k = A/(\bar{x})$, and $\bar{x}$ acts on it as zero, confirming that $\mathrm{Jac}(A) = (\bar{x})$ annihilates every simple module.

The second computation is the model of a non-commutative, non-local radical, where the one-sided origin of the definition is easiest to see in matrices.

Example 52.1.6: The Radical of Upper-Triangular Matrices

Let k be a field and let $A = T_n(k)$ be the ring of $n \times n$ upper-triangular matrices over k. Write $N \subseteq A$ for the strictly upper-triangular matrices (zero on and below the diagonal). The claim is $\mathrm{Jac}(A) = N$.

N annihilates every simple module. For each $1 \le i \le n$ there is a one-dimensional A-module $S_i = k$ on which an upper-triangular matrix $a = (a_{pq})$ acts by its ith diagonal entry, $a \cdot v = a_{ii}v$; this is a ring homomorphism $A \to k$ because the (i,i) entry of a product of upper-triangular matrices is the product of the (i,i) entries. The S_i are pairwise non-isomorphic simple A-modules. Any strictly upper-triangular matrix has all diagonal entries zero, so it acts as 0 on each S_i; thus $N \subseteq \mathrm{Ann}_A(S_i)$ for all i, and $N \subseteq \mathrm{Jac}(A)$ by theorem 52.1.4.

Nothing outside N lies in the radical. If $a \in A \setminus N$, some diagonal entry a_{ii} is nonzero, so a acts invertibly on S_i, and a does not annihilate the simple module S_i. By part (2) of theorem 52.1.4, $a \notin \mathrm{Jac}(A)$. Combining, $\mathrm{Jac}(A) = N$.

As a check on the intrinsic criterion, N is nilpotent with $N^n = 0$ (each multiplication by a strictly upper-triangular matrix pushes nonzero entries one further diagonal above the main diagonal), so for $a \in N$ the element $1 - xa$ has the form $1 -$ (nilpotent) and is a unit via the terminating geometric series $\sum_{j \ge 0}(xa)^j$. The quotient is $A/N \cong k^n$, the diagonal matrices, which is semisimple, and there are exactly n simple modules $S_1, \ldots, S_n$, matching the n factors of k^n.

The two examples share a feature: in each, $\mathrm{Jac}(A)$ turned out to be nilpotent, and the geometric series that inverts $1 - xa$ terminated precisely because a power of the radical vanished. This is not special to small examples. For the finite-dimensional and, more generally, left Artinian algebras that concern us, the radical is always nilpotent. The route to that fact runs through Nakayama's lemma, which converts the invertibility criterion into a statement about modules being forced to zero.

The lemma answers a question that recurs throughout module theory: if multiplying a module by the radical does not shrink it, must the module already be zero? The commutative version, over a local ring or with a general ideal contained in the radical, is proved in the companion volume [20] and will not be re-derived here; the module form over an arbitrary ring is the form needed here, and its proof uses only the invertibility criterion from theorem 52.1.4.

Lemma 52.1.7: Nakayama's Lemma

Let A be a ring and M a finitely generated left A-module.

1. If $\mathrm{Jac}(A)\,M = M$, then $M = 0$.
2. If $N \subseteq M$ is a submodule with $M = N + \mathrm{Jac}(A)\,M$, then $N = M$.

***Proof*:**
Write $J = \mathrm{Jac}(A)$.

1. Suppose $M \neq 0$ and $JM = M$. Since M is finitely generated, choose a generating set $m_1, \ldots, m_r$ with r minimal, so no fewer than r elements generate M; as $M \neq 0$ we have $r \geq 1$. From $M = JM$ we may write the last generator as

$$m_r = \sum_{i=1}^{r} a_i m_i \qquad \text{with } a_i \in J$$

   Isolating m_r gives $(1 - a_r)m_r = \sum_{i=1}^{r-1} a_i m_i$. Because $a_r \in J = \mathrm{Jac}(A)$, the element $1 - a_r$ is a unit (the working form of theorem 52.1.4: $1 - a_r$ is left-invertible, and for radical elements this upgrades to a two-sided inverse). Multiplying on the left by $(1 - a_r)^{-1}$ expresses m_r as an A-combination of $m_1, \ldots, m_{r-1}$, so these $r-1$ elements already generate M, contradicting the minimality of r. Hence $M = 0$.

2. Apply part (1) to the finitely generated module M/N. Its finite generation is inherited from M (the images of generators of M generate the quotient). The hypothesis $M = N + JM$ gives, in the quotient, $M/N = J\,(M/N)$, since the image of JM is $J(M/N)$ and the image of N is 0. By part (1), $M/N = 0$, that is $N = M$, completing the proof.

The finite-generation hypothesis is not optional. Over the local ring $A = \mathbb{Z}_{(p)}$ (integers localized at p, whose radical is $p\mathbb{Z}_{(p)}$) the module $M = \mathbb{Q}$ satisfies $pM = M$ yet $M \neq 0$; it fails to be finitely generated, and the minimal-generator argument has nothing to grip. Part (2) is the form used in practice: it says that generators of $M/\mathrm{Jac}(A)M$ lift to generators of M. Once $\mathrm{Jac}(A)M$ is known (below) to be a "small" submodule, this becomes the statement that a minimal generating set of M is detected by the semisimple quotient $M/\mathrm{Jac}(A)M$, which is the seed of the theory of projective covers in a later section.

We now specialize to the setting where the radical is best behaved. A ring A is *left Artinian* if it satisfies the descending chain condition on left ideals; every finite-dimensional algebra over a field is left Artinian, since a descending chain of left ideals is a descending chain of subspaces and dimension cannot drop forever. In this setting the radical is not only an intersection of maximal left ideals but a nilpotent ideal, and it is the largest one.

Theorem 52.1.8: The Radical Is Nilpotent for Artinian Rings

Let A be a left Artinian ring. Then $\mathrm{Jac}(A)$ is nilpotent: there exists $m \geq 1$ with $\mathrm{Jac}(A)^m = 0$. Moreover, $\mathrm{Jac}(A)$ contains every nilpotent left ideal and every nilpotent two-sided ideal of A, so it is the largest nilpotent one-sided or two-sided ideal.

***Proof*:**
Write $J = \mathrm{Jac}(A)$.

Step 1: J is nilpotent. The descending chain of two-sided ideals

$$J \supseteq J^2 \supseteq J^3 \supseteq \cdots$$

is a descending chain of left ideals, so by the descending chain condition it stabilizes: there is m with $I := J^m = J^{m+1} = J\,I$. Suppose for contradiction that $I \neq 0$. Consider the set Σ of left ideals $L \subseteq A$ with $IL \neq 0$; it is nonempty because $I \cdot I = J^{2m} = I \neq 0$ shows $I \in \Sigma$ (using $J^{2m} = (J^m)^2 = I \cdot I$ and $J^{2m} = J^m = I$ since the chain stabilized). By the descending chain condition, Σ has a minimal element L_0. Choose $x \in L_0$ with $Ix \neq 0$; then $Ix \subseteq L_0$ is a left ideal with $I(Ix) = I^2x = Ix \neq 0$ (as $I^2 = I$), so $Ix \in \Sigma$, and minimality forces $Ix = L_0$. In particular $x \in L_0 = Ix$, so $x = ax$ for some $a \in I \subseteq J$. Then $(1-a)x = 0$, and since $a \in J$ the element $1 - a$ is a unit, giving $x = 0$ and hence $Ix = 0$, a contradiction. Therefore $I = J^m = 0$.

Step 2: J contains every nilpotent one-sided or two-sided ideal. Let I be a nilpotent left ideal, say $I^t = 0$. For any $a \in I$ and any $x \in A$, the element xa lies in I (a left ideal absorbs left multiplication), so $(xa)^t \in I^t = 0$; thus xa is nilpotent. A nilpotent element y with $y^t = 0$ makes $1 - y$ a unit, with inverse the terminating sum $1 + y + y^2 + \cdots + y^{t-1}$. Hence $1 - xa$ is a unit, in particular left-invertible, for every $x \in A$, so $a \in \mathrm{Jac}(A)$ by part (3) of theorem 52.1.4. This holds for every $a \in I$, so $I \subseteq J$. A nilpotent two-sided ideal is in particular a nilpotent left ideal, so the same conclusion applies, completing the proof.

For a left Artinian ring, then, "the Jacobson radical" and "the largest nilpotent ideal" name the same object; the two definitions of the radical current in the literature (intersection of maximal left ideals versus largest nilpotent ideal) agree exactly when A is Artinian. The nilpotence is what powers the terminating geometric series seen in the truncated-polynomial and upper-triangular examples, and it is the property that fails for general rings. It also gives a concrete way to detect non-semisimplicity: a single nonzero nilpotent element of a two-sided ideal already forces the radical to be nonzero. This is exactly the obstruction that appears for modular group algebras.

Having pinned down $\mathrm{Jac}(A)$ as a nilpotent ideal, the pieces are in place for the structural payoff. Dividing A by its radical removes precisely the elements that the simple modules could not see, and what remains is semisimple.

Theorem 52.1.9: Semisimplicity of the Quotient by the Radical

Let A be a left Artinian ring. Then $A/\mathrm{Jac}(A)$ is a semisimple ring, and hence Artin-Wedderburn (theorem 51.2.16) applies to it. Moreover, the simple left A-modules are exactly the simple left $A/\mathrm{Jac}(A)$-modules: every simple A-module is annihilated by $\mathrm{Jac}(A)$ and so factors through $A/\mathrm{Jac}(A)$, and every simple $A/\mathrm{Jac}(A)$-module is a simple A-module via the quotient map $A \twoheadrightarrow A/\mathrm{Jac}(A)$.

***Proof*:**
Write $J = \mathrm{Jac}(A)$ and $\bar{A} = A/J$.

Step 1: $\bar{A}$ is semisimple. By corollary 51.1.9 it suffices to show that $\bar{A}$ is semisimple as a left module over itself, that is that $\mathrm{rad}(\bar{A}) = 0$. The maximal left ideals of $\bar{A}$ are exactly the images $\mathfrak{m}/J$ of the maximal left ideals $\mathfrak{m}$ of A (which all contain $J = \mathrm{Jac}(A)$), by the correspondence

theorem. Their intersection is

$$\operatorname{Jac}(\bar{A}) = \bigcap_{\mathfrak{m} \supseteq J} \mathfrak{m}/J = \Big(\bigcap_{\mathfrak{m}} \mathfrak{m}\Big) \Big/ J = J/J = 0$$

So $\operatorname{Jac}(\bar{A}) = 0$. It remains to convert this into semisimplicity, which is where the Artinian hypothesis is spent: $\bar{A}$ is Artinian (a quotient of the Artinian ring A), and for an Artinian ring $\operatorname{Jac}(\bar{A}) = 0$ forces $\bar{A}$ to be semisimple. Concretely, since $\bar{A}$ is Artinian we may pick finitely many maximal left ideals $\mathfrak{m}_1/J, \dots, \mathfrak{m}_r/J$ whose intersection is already 0 (take a minimal finite subintersection, which exists by the descending chain condition and equals the full intersection $\operatorname{Jac}(\bar{A}) = 0$). The map

$$\bar{A} \longrightarrow \bigoplus_{i=1}^{r} \bar{A}/(\mathfrak{m}_i/J)$$

is injective, since its kernel is $\bigcap_i (\mathfrak{m}_i/J) = 0$. Each summand $\bar{A}/(\mathfrak{m}_i/J)$ is a simple $\bar{A}$-module, so $\bar{A}$ embeds as a submodule of a semisimple module and is therefore semisimple by corollary 51.1.8. Thus $\bar{A}$ is a semisimple $\bar{A}$-module, and by corollary 51.1.9 a semisimple ring. Artin-Wedderburn now applies to $\bar{A}$.

Step 2: the simple modules coincide. Let S be a simple left A-module. By part (2) of theorem 52.1.4, $J = \operatorname{Jac}(A)$ annihilates every simple A-module, so $JS = 0$. Hence the A-action on S factors through the quotient $\bar{A} = A/J$: setting $(\bar{a})s := as$ is well-defined because J acts as zero. The A-submodules and $\bar{A}$-submodules of S are the same subsets (a subgroup of S is A-stable if and only if it is $\bar{A}$-stable, since the actions agree), so S is simple as an $\bar{A}$-module precisely because it is simple as an A-module.

Conversely, let T be a simple left $\bar{A}$-module. Pulling back the action along the surjection $\pi\colon A \twoheadrightarrow \bar{A}$, that is defining $a \cdot t := \pi(a)\, t$, makes T an A-module. Its A-submodules are exactly its $\bar{A}$-submodules (again the two actions have the same invariant subgroups, because π is surjective), so T is simple as an A-module. These two passages are mutually inverse, so the simple A-modules and the simple $\bar{A}$-modules are identified, as we sought to show.

This is the structural role of the radical: it is the exact obstruction one divides out to recover the Wedderburn world. The simple modules of A are unchanged by the passage to $A/\operatorname{Jac}(A)$, so the finite list of simples that a semisimple ring enjoys is available for *any* Artinian ring, read off from its semisimple quotient. What the radical takes away is not the simples but the way they fit together: over A the simples can be glued into indecomposable modules that do not split, and the gluing data lives in $\operatorname{Jac}(A)$. The theorem says that for an Artinian A there are finitely many simple A-modules, one for each simple factor of the Wedderburn decomposition of $A/\operatorname{Jac}(A)$, and this is the starting point for the character theory and the block theory developed later.

The special case $\operatorname{Jac}(A) = 0$ returns to chapter 51.

Corollary 52.1.10: Semisimplicity via the Radical

Let A be a left Artinian ring. Then A is semisimple if and only if $\operatorname{Jac}(A) = 0$.

***Proof*:**
If A is semisimple, then by corollary 51.1.9 it is a semisimple left module over itself, so its radical (the intersection of its maximal left ideals) is 0; that is, $\mathrm{Jac}(A) = \mathrm{rad}({}_AA) = 0$. Indeed, a semisimple module is a direct sum of simples, and its radical, the intersection of maximal submodules, is 0: writing $A = \bigoplus_i I_i$ as a sum of minimal left ideals (lemma 51.1.10), each $\bigoplus_{j\neq i} I_j$ is a maximal submodule, and their intersection is 0.

Conversely, if $\mathrm{Jac}(A) = 0$, then $A = A/\mathrm{Jac}(A)$, and by theorem 52.1.9 the quotient $A/\mathrm{Jac}(A)$ is semisimple; hence A itself is semisimple, completing the proof.

The corollary makes the radical the precise measure of the failure of semisimplicity: A is semisimple exactly when the measurement returns zero, and Artin-Wedderburn (theorem 51.2.16) describes what A looks like in that case, namely a product $M_{n_1}(D_1) \times \cdots \times M_{n_k}(D_k)$. For a general Artinian A, the same product describes $A/\mathrm{Jac}(A)$ rather than A, and the difference between A and this product is stored in the nilpotent ideal $\mathrm{Jac}(A)$. The truncated-polynomial algebra $k[x]/(x^n)$ with $n \geq 2$ is the simplest case where the measurement is nonzero: its radical $(\bar{x})$ is a nonzero nilpotent ideal, so it is not semisimple, even though its semisimple quotient is the field k.

The most consequential source of non-semisimple algebras in representation theory is the group algebra $k[G]$ when the characteristic of k divides the order of the group. Maschke's theorem guarantees semisimplicity precisely when $\mathrm{char}(k) \nmid |G|$; the radical detects, and measures, the failure in the opposite case.

Example 52.1.11: The Radical of a Modular Group Algebra
Let $G = \mathbb{Z}/p\mathbb{Z}$ be cyclic of order p and let k be a field. Writing g for a generator, the group algebra is

$$k[G] \cong k[t]/(t^p - 1)$$

via $g \mapsto t$, since g has order p. The structure of $\mathrm{Jac}(k[G])$ depends entirely on whether $\mathrm{char}(k)$ divides $|G| = p$.

The modular case $\mathrm{char}(k) = p$. In characteristic p the Frobenius identity gives $t^p - 1 = (t-1)^p$, so

$$k[G] \cong k[t]/\big((t-1)^p\big) \cong k[s]/(s^p) \qquad (s := t-1)$$

the last isomorphism being the change of variable $s = t - 1$. This is precisely the truncated polynomial algebra of example 52.1.5 with $n = p$, so its radical is

$$\mathrm{Jac}(k[G]) = (s) = (g-1)$$

the ideal generated by $g - 1$, which is the augmentation ideal (the kernel of the augmentation map $k[G] \to k$ sending $g \mapsto 1$). It is nilpotent, $(g-1)^p = g^p - 1 = 0$, and nonzero, so $k[G]$ is not semisimple: Maschke's theorem fails exactly because $p = \mathrm{char}(k)$ divides $|G|$. The unique simple $k[G]$-module is the trivial module k, on which g acts as the identity, so $g - 1$ acts as zero, confirming $\mathrm{Jac}(k[G]) = (g-1)$ annihilates the only simple module.

The coprime case $\mathrm{char}(k) \nmid p$. If the characteristic does not divide p, then the polynomial $t^p - 1$ is separable (its derivative pt^{p-1} is nonzero and shares no root with it), so it has no repeated factors. Over a field containing a primitive pth root of unity ζ it splits as $t^p - 1 = \prod_{i=0}^{p-1}(t - \zeta^i)$, and the Chinese remainder theorem gives

$$k[G] \cong \prod_{i=0}^{p-1} k[t]/(t - \zeta^i) \cong k^p$$

a product of p copies of k, which is semisimple with radical $\mathrm{Jac}(k[G]) = 0$. (Over a field without the roots of unity, $t^p - 1$ still factors into distinct irreducible separable factors and $k[G]$ is a product of finite separable field extensions of k, again semisimple with zero radical.) This is Maschke's theorem in the coprime case, seen through the radical: separability of $t^p - 1$ is exactly the condition $\mathrm{char}(k) \nmid |G|$, and it forces $\mathrm{Jac}(k[G]) = 0$.

The contrast in the two cases is the whole point of the chapter in miniature. When $\mathrm{char}(k) \nmid |G|$ the group algebra is semisimple, its radical is zero, and the representation theory of G over k is governed by Wedderburn and character theory. When $\mathrm{char}(k) \mid |G|$ the radical becomes a nonzero nilpotent ideal, the group algebra acquires indecomposable modules that are not simple, and one enters modular representation theory, where the radical, the indecomposables, and the projective covers built in the following sections are the working tools.

52.2 Indecomposable Modules and Krull-Schmidt

The previous chapter rested on a single organizing principle: over a semisimple ring, every module splits into simple pieces, and Artin-Wedderburn turns that splitting into a matrix description of the ring itself. The trouble is that semisimplicity is a strong hypothesis. The ring $k[x]/(x^2)$ is a two-dimensional k-algebra, and the module $k[x]/(x^2)$ over itself has a proper nonzero submodule $(x)/(x^2)$, yet that submodule has no complement: there is no way to write $k[x]/(x^2) = (x)/(x^2) \oplus N$. So this module does not break into simples at all. Once the semisimple world is left behind, the simple modules stop being the building blocks, and the decomposition theory of lemma 51.1.7 collapses.

What survives is a weaker notion of "building block". A module that cannot be split into two nonzero summands is *indecomposable* (definition 51.1.1), and every module of finite length is at least a finite direct sum of indecomposables, for the trivial reason that one keeps splitting until nothing splits further. The content of this section is that this crude decomposition is in fact canonical: the list of indecomposable summands, taken up to isomorphism, is uniquely determined by the module. This is the Krull-Schmidt theorem, and it is the correct replacement for the semisimple decomposition when simples are no longer available. The engine driving uniqueness is a structural fact about the endomorphism ring of an indecomposable module of finite length, that it is a *local ring*, which is itself a consequence of Fitting's lemma. So the section runs Fitting's lemma to the local-ring theorem to Krull-Schmidt, each result feeding the next.

Throughout, A is an algebra over a field k (the arguments need only that modules have finite length, so the results apply verbatim to modules of finite length over any ring). Modules are left modules. The starting point is worth isolating, since it is the gap between this chapter and the last. A simple module is indecomposable, because a simple module has no proper nonzero submodule at all, let alone a complemented one. The converse fails, and it fails already in dimension two: the $k[x]$-module $k[x]/(x^2)$ has the unique proper nonzero submodule $(x)/(x^2)$, so it is not simple, but that submodule is not a summand (any complement would have to be one-dimensional and x-stable, and $(x)/(x^2)$ is the only such subspace), so the module is indecomposable. An indecomposable module of finite length can therefore sit strictly between "simple" and "decomposable", and it is exactly this middle ground that Krull-Schmidt organizes.

The first tool is a splitting result for a single endomorphism. Given $\varphi \in \mathrm{End}_A(M)$, the iterated kernels $\ker(\varphi) \subseteq \ker(\varphi^2) \subseteq \cdots$ increase and the iterated images $\mathrm{im}(\varphi) \supseteq \mathrm{im}(\varphi^2) \supseteq \cdots$ decrease. When M has finite length, both chains must stabilize, and Fitting's lemma says that at a common stabilization point the module splits into the eventual kernel and the eventual image.

Lemma 52.2.1: Fitting's Lemma

Let M be an A-module of finite length and let $\varphi \in \mathrm{End}_A(M)$. Then there exists a positive integer n such that

$$M = \ker(\varphi^n) \oplus \mathrm{im}(\varphi^n)$$

Consequently, if M is indecomposable, then every $\varphi \in \mathrm{End}_A(M)$ is either nilpotent or an automorphism.

***Proof*:**
Write $\ell = \ell(M)$ for the length of M, which is finite by hypothesis.

Step 1: The kernel and image chains stabilize. The submodules $\ker(\varphi^i)$ form an increasing chain and the submodules $\mathrm{im}(\varphi^i)$ form a decreasing chain:

$$\ker(\varphi) \subseteq \ker(\varphi^2) \subseteq \cdots \qquad \mathrm{im}(\varphi) \supseteq \mathrm{im}(\varphi^2) \supseteq \cdots$$

A module of finite length is both Noetherian and Artinian, so an increasing chain of submodules cannot strictly ascend more than ℓ times and a decreasing chain cannot strictly descend more than ℓ times. Setting $n = \ell$ makes both chains stationary from index n onward: for all $m \geq n$,

$$\ker(\varphi^m) = \ker(\varphi^n) \qquad \mathrm{im}(\varphi^m) = \mathrm{im}(\varphi^n)$$

Indeed, once the kernel chain repeats, it is stationary forever after: if $\ker(\varphi^i) = \ker(\varphi^{i+1})$ and $x \in \ker(\varphi^{i+2})$, then $\varphi(x) \in \ker(\varphi^{i+1}) = \ker(\varphi^i)$, so $x \in \ker(\varphi^{i+1}) = \ker(\varphi^i)$, giving $\ker(\varphi^{i+2}) = \ker(\varphi^{i+1})$; iterating shows $\ker(\varphi^j) = \ker(\varphi^i)$ for all $j \geq i$. A chain that strictly increased past step ℓ would produce more than ℓ strict inclusions, violating finite length, so the first repeat occurs by step ℓ. The same bound applies to the image chain, and $n = \ell$ dominates both stabilization thresholds.

Step 2: The two submodules intersect trivially. Fix n as above and take $y \in \ker(\varphi^n) \cap \mathrm{im}(\varphi^n)$. Write $y = \varphi^n(x)$ for some $x \in M$. Then $\varphi^n(y) = 0$ gives $\varphi^{2n}(x) = 0$, so $x \in \ker(\varphi^{2n}) = \ker(\varphi^n)$ by the stabilization of the kernel chain. Hence $y = \varphi^n(x) = 0$, and $\ker(\varphi^n) \cap \mathrm{im}(\varphi^n) = 0$.

Step 3: The two submodules span M. Take any $z \in M$. Since $\mathrm{im}(\varphi^n) = \mathrm{im}(\varphi^{2n})$, the element $\varphi^n(z) \in \mathrm{im}(\varphi^n)$ also lies in $\mathrm{im}(\varphi^{2n})$, so $\varphi^n(z) = \varphi^{2n}(w)$ for some $w \in M$. Then

$$z = \varphi^n(w) + \big(z - \varphi^n(w)\big)$$

where $\varphi^n(w) \in \mathrm{im}(\varphi^n)$, and the second term lies in $\ker(\varphi^n)$ because $\varphi^n(z - \varphi^n(w)) = \varphi^n(z) - \varphi^{2n}(w) = 0$. Thus $M = \ker(\varphi^n) + \mathrm{im}(\varphi^n)$, and together with Step 2 this gives the internal direct sum $M = \ker(\varphi^n) \oplus \mathrm{im}(\varphi^n)$.

Step 4: The dichotomy for indecomposable M. Suppose now that M is indecomposable. The decomposition $M = \ker(\varphi^n) \oplus \mathrm{im}(\varphi^n)$ forces one of the two summands to be M and the other to be 0. If $\ker(\varphi^n) = M$, then $\varphi^n = 0$, so φ is nilpotent. If instead $\ker(\varphi^n) = 0$ and $\mathrm{im}(\varphi^n) = M$, then φ is injective, since $\ker(\varphi) \subseteq \ker(\varphi^n) = 0$, and φ is surjective, since $\mathrm{im}(\varphi) \supseteq \mathrm{im}(\varphi^n) = M$. An injective and surjective endomorphism is an automorphism. In either case φ is nilpotent or an automorphism, completing the proof.

The decomposition in Fitting's lemma is the "eventual kernel" and "eventual image" of φ, and

it works for any single endomorphism of any finite-length module, indecomposable or not. The sharp consequence appears only in the indecomposable case: an indecomposable module of finite length admits no interesting endomorphisms in the sense that the only two behaviors available to a $\varphi \in \mathrm{End}_A(M)$ are "eventually kills everything" (nilpotent) and "moves everything bijectively" (automorphism). There is no room in between, precisely because any intermediate behavior would produce a nontrivial Fitting decomposition and split the module. This is the mechanism that will make the endomorphism ring so rigid.

To see the dichotomy in a case where it can be checked by hand, take the endomorphism given by multiplication by x on $M = k[x]/(x^3)$. Multiplication by x has kernel $(x^2)/(x^3)$ and image $(x)/(x^3)$, which are not complementary. But the lemma is about a *power*: φ^3 is multiplication by $x^3 = 0$, so $\ker(\varphi^3) = M$ and $\mathrm{im}(\varphi^3) = 0$, giving the trivial decomposition $M = M \oplus 0$. This is the nilpotent branch of the dichotomy, and indeed multiplication by x is nilpotent. Multiplication by $1 + x$, on the other hand, is invertible (with inverse $1 - x + x^2$), landing in the automorphism branch. Every element of $\mathrm{End}_{k[x]}(M)$ is one or the other.

The endomorphism ring $\mathrm{End}_A(M)$ of an indecomposable finite-length module is close to being a division ring but not quite: Schur's lemma (lemma 51.1.5) gave a division ring only for *simple* M, and indecomposable is weaker. The right substitute is that $\mathrm{End}_A(M)$ is a *local ring*. A ring is local when its non-units form a two-sided ideal, equivalently when it has a unique maximal left ideal; the intuition is that "being a non-unit" is closed under addition, so failures of invertibility do not conspire to produce an invertible element. Fitting's lemma is exactly what closes the non-units under addition here, because a non-unit of $\mathrm{End}_A(M)$ is precisely a nilpotent endomorphism, and controlling sums of nilpotents is where the argument lives.

Theorem 52.2.2: Endomorphism Rings of Indecomposables are Local

Let M be a nonzero indecomposable A-module of finite length. Then $\mathrm{End}_A(M)$ is a local ring: the set of non-units of $\mathrm{End}_A(M)$ is a two-sided ideal, and it consists exactly of the nilpotent endomorphisms of M.

***Proof*:**

Write $E = \mathrm{End}_A(M)$ and let $\mathfrak{m} \subseteq E$ be the set of endomorphisms that are not units, that is, not automorphisms of M.

Step 1: The non-units are the nilpotents. By lemma 52.2.1, every $\varphi \in E$ is either an automorphism or nilpotent, and these are mutually exclusive (a nilpotent $\varphi \neq 0$ kills some nonzero element, and $\varphi = 0$ is not invertible since $M \neq 0$). Hence $\mathfrak{m}$ is exactly the set of nilpotent endomorphisms.

Step 2: $\mathfrak{m}$ is closed under left and right multiplication by E. Let $\varphi \in \mathfrak{m}$, so φ is not an automorphism, and let $\psi \in E$ be arbitrary. If $\psi\varphi$ were an automorphism, then φ would be injective (as $\psi\varphi$ is) and ψ surjective; an injective endomorphism of a finite-length module is bijective (its image has the same length as M, hence equals M), so φ would be an automorphism, a contradiction. Thus $\psi\varphi \in \mathfrak{m}$. Symmetrically, if $\varphi\psi$ were an automorphism, then φ would be surjective, hence bijective by the length argument, again contradicting $\varphi \in \mathfrak{m}$. So $\varphi\psi \in \mathfrak{m}$, and $\mathfrak{m}$ absorbs multiplication on both sides.

Step 3: $\mathfrak{m}$ is closed under addition. This is the step that uses indecomposability. Let $\varphi, \psi \in \mathfrak{m}$ and suppose, for contradiction, that $\varphi + \psi$ is an automorphism. Set

$$\alpha = (\varphi + \psi)^{-1}\varphi \qquad \beta = (\varphi + \psi)^{-1}\psi$$

so that $\alpha+\beta=(\varphi+\psi)^{-1}(\varphi+\psi)=\mathrm{id}_M$. By Step 2, $\mathfrak{m}$ absorbs left multiplication, so $\alpha,\beta\in\mathfrak{m}$; in particular α is nilpotent, say $\alpha^r=0$. From $\beta=\mathrm{id}_M-\alpha$ the standard geometric-series identity gives an inverse for β:

$$(\mathrm{id}_M-\alpha)\big(\mathrm{id}_M+\alpha+\alpha^2+\cdots+\alpha^{r-1}\big)=\mathrm{id}_M-\alpha^r=\mathrm{id}_M$$

so $\beta=\mathrm{id}_M-\alpha$ is an automorphism of M. But $\beta\in\mathfrak{m}$ means β is not an automorphism, a contradiction. Hence $\varphi+\psi\in\mathfrak{m}$.

Step 4: Conclusion. Steps 2 and 3 show $\mathfrak{m}$ is a two-sided ideal of E, and Step 1 identifies it as the set of non-units. A ring whose non-units form a two-sided ideal is local: any element outside $\mathfrak{m}$ is a unit, so $\mathfrak{m}$ is the unique maximal left ideal (a proper left ideal contains no units, hence lies in $\mathfrak{m}$). Therefore $E=\mathrm{End}_A(M)$ is local, as we sought to show.

The theorem sharpens Schur's lemma in exactly the direction needed. For a simple module, lemma 51.1.5 gave a division ring, where every nonzero element is a unit. For an indecomposable module of finite length, one gets the next best thing: a local ring, where the non-units are corralled into a single ideal and every element outside it is a unit. The residue $\mathrm{End}_A(M)/\mathfrak{m}$ is a division ring, and one can think of the local ring as a division ring with a nilpotent "fuzz" $\mathfrak{m}$ attached. The content used below is the geometric series in Step 3, which turns "id_M minus a nilpotent" into a unit; this is what will let one element of a decomposition be swapped for another in the exchange argument below.

The running example makes the local structure explicit.

Example 52.2.3: The Endomorphism Ring of a Truncated Polynomial Module
Fix $n\geq 1$ and let $M=k[x]/(x^n)$, viewed as a module over $A=k[x]$ (equivalently over $k[x]/(x^n)$, which acts through the same operators). This module is indecomposable of length n: its submodules are exactly the ideals $(x^j)/(x^n)$ for $0\leq j\leq n$, forming a single chain

$$0=(x^n)/(x^n)\subseteq(x^{n-1})/(x^n)\subseteq\cdots\subseteq(x)/(x^n)\subseteq M$$

and a chain of submodules has no way to split off a complementary summand (a decomposition $M=M_1\oplus M_2$ with both $M_i\neq 0$ would give two submodules neither containing the other).

Every A-endomorphism of M is multiplication by some polynomial: since M is generated by the image of 1, a homomorphism φ is determined by $\varphi(1)=\overline{f(x)}$, and then $\varphi(\overline{g})=\overline{gf}$. So

$$\mathrm{End}_A(M)\cong k[x]/(x^n)$$

as rings, the isomorphism sending φ to $\varphi(1)$. This is a local ring with maximal ideal $\mathfrak{m}=(x)/(x^n)$: an element $\overline{f}=\overline{a_0+a_1x+\cdots+a_{n-1}x^{n-1}}$ is a unit if and only if $a_0\neq 0$ (with inverse computed by the geometric series when $a_0=1$), and it is nilpotent if and only if $a_0=0$. The non-units are precisely the nilpotents, matching theorem 52.2.2, and $\mathrm{End}_A(M)/\mathfrak{m}\cong k$ is the residue division ring (here a field, since A is commutative).

The local endomorphism ring is now used to prove the main theorem. Existence of a decomposition into indecomposables is easy, by induction on length; the content is uniqueness. The classical route to uniqueness is an *exchange argument*: given two decompositions of the same module, one shows that each indecomposable summand of the first can be swapped into the second, one at a time, without changing the ambient module, and the local endomorphism rings are exactly what make each swap

possible. The theorem is due to Krull and Schmidt for finite groups and finite-length modules, with Azumaya's extension to any module that is a direct sum of submodules with local endomorphism rings.

Theorem 52.2.4: Krull-Schmidt(-Azumaya)

Let M be a nonzero A-module of finite length. Then:

1. M is a finite direct sum of indecomposable submodules,
$$M = M_1 \oplus M_2 \oplus \cdots \oplus M_r$$
with each M_i indecomposable.
2. This decomposition is unique up to isomorphism and reordering: if
$$M = M_1 \oplus \cdots \oplus M_r = N_1 \oplus \cdots \oplus N_s$$
are two decompositions into indecomposable submodules, then $r = s$ and there is a permutation σ of $\{1, \dots, r\}$ with $M_i \cong N_{\sigma(i)}$ for every i.

***Proof*:**

1. *Existence.* Argue by induction on the length $\ell(M)$. If M is indecomposable, then $M = M$ is already such a decomposition, with one summand. Otherwise $M = M_1 \oplus M_2$ with both M_i nonzero, and then $\ell(M_1), \ell(M_2) < \ell(M)$ because length is additive over direct sums and both summands are nonzero (hence of positive length). By the inductive hypothesis each M_i is a finite direct sum of indecomposables, and concatenating the two lists expresses M as a finite direct sum of indecomposables. The base case $\ell(M) = 1$ is a simple, hence indecomposable, module. This proves existence.
2. *Uniqueness.* Suppose
$$M = M_1 \oplus \cdots \oplus M_r = N_1 \oplus \cdots \oplus N_s$$
with all M_i and N_j indecomposable of finite length, so each $\mathrm{End}_A(M_i)$ and $\mathrm{End}_A(N_j)$ is local by theorem 52.2.2. Induct on r. The strategy is to exchange M_1 for one of the N_j, peel it off both sides, and apply the inductive hypothesis to what remains.

   Let $\iota_i \colon M_i \hookrightarrow M$ and $\pi_i \colon M \twoheadrightarrow M_i$ be the inclusion and projection for the first decomposition, and $\iota'_j \colon N_j \hookrightarrow M$, $\pi'_j \colon M \twoheadrightarrow N_j$ those for the second. These satisfy
$$\sum_{i=1}^{r} \iota_i \pi_i = \mathrm{id}_M \qquad \sum_{j=1}^{s} \iota'_j \pi'_j = \mathrm{id}_M$$
   Restricting the second identity to M_1 and projecting back to M_1 gives, in $\mathrm{End}_A(M_1)$,
$$\mathrm{id}_{M_1} = \pi_1 \Big(\sum_{j=1}^{s} \iota'_j \pi'_j \Big) \iota_1 = \sum_{j=1}^{s} (\pi_1 \iota'_j)(\pi'_j \iota_1)$$
   Now $\mathrm{End}_A(M_1)$ is local, so its non-units form an ideal and cannot sum to the unit id_{M_1}; at least one summand $(\pi_1 \iota'_j)(\pi'_j \iota_1)$ must be a unit of $\mathrm{End}_A(M_1)$. After reindexing the N_j

we may assume this happens for $j = 1$: the composite

$$\theta = (\pi_1\iota_1')(\pi_1'\iota_1)\colon M_1 \longrightarrow M_1$$

is an automorphism of M_1, where $\pi_1'\iota_1\colon M_1 \to N_1$ and $\pi_1\iota_1'\colon N_1 \to M_1$.

Exchange step. Consider the maps

$$f = \pi_1'\iota_1\colon M_1 \to N_1 \qquad g = \pi_1\iota_1'\colon N_1 \to M_1$$

so $gf = \theta$ is an automorphism of M_1. Then f is a split monomorphism, with left inverse $\theta^{-1}g$, since $(\theta^{-1}g)f = \theta^{-1}(gf) = \mathrm{id}_{M_1}$. The endomorphism $e = f\theta^{-1}g\colon N_1 \to N_1$ is then idempotent:

$$e^2 = f\theta^{-1}(gf)\theta^{-1}g = f\theta^{-1}\theta\theta^{-1}g = f\theta^{-1}g = e$$

and its image is $\mathrm{im}(f)$ (from $ef = f\theta^{-1}gf = f$), so $N_1 = \mathrm{im}(e) \oplus \ker(e) = \mathrm{im}(f) \oplus \ker(e)$ is the splitting associated to the idempotent e. But N_1 is indecomposable and $\mathrm{im}(f) \neq 0$ (since f is injective and $M_1 \neq 0$), which forces $\mathrm{im}(f) = N_1$, making f surjective as well. Hence $f\colon M_1 \to N_1$ is an isomorphism, and in particular

$$M_1 \cong N_1$$

Peeling off the summand. It remains to remove M_1 and N_1 from the two decompositions and match the rest. Set $M' = M_2 \oplus \cdots \oplus M_r$, so $M = M_1 \oplus M'$ and M' is the kernel of the projection $\pi_1\colon M \to M_1$. The claim is

$$M = N_1 \oplus M'$$

viewing $N_1 = \iota_1'(N_1) \subseteq M$ as the submodule it names in the second decomposition. The key observation is that the restriction of π_1 to N_1 is an isomorphism onto M_1: on N_1 this restriction is $\pi_1\iota_1' = g$, and $g = \theta f^{-1}$ is a composite of the automorphism θ with the isomorphism f^{-1}, hence itself an isomorphism $N_1 \to M_1$. Granting that $\pi_1|_{N_1}\colon N_1 \to M_1$ is an isomorphism, the claim follows:

- *Trivial intersection.* If $y \in N_1 \cap M'$, then $\pi_1(y) = 0$ because $M' = \ker(\pi_1)$, and $\pi_1|_{N_1}$ is injective, so $y = 0$. Thus $N_1 \cap M' = 0$.
- *Spanning.* Given $z \in M$, set $a = \pi_1(z) \in M_1$. Since $\pi_1|_{N_1}$ is onto M_1, choose $y \in N_1$ with $\pi_1(y) = a$. Then $\pi_1(z - y) = a - a = 0$, so $z - y \in \ker(\pi_1) = M'$, and $z = y + (z - y) \in N_1 + M'$.

Hence $M = N_1 \oplus M'$, establishing the claim.

Induction. Quotienting $M = N_1 \oplus M'$ by the summand N_1 gives $M/N_1 \cong M'$, and quotienting the original $M = N_1 \oplus N'$ by the same submodule N_1 gives $M/N_1 \cong N'$. Therefore

$$M' \cong N'$$

Now M' carries the decomposition $M_2 \oplus \cdots \oplus M_r$ into $r - 1$ indecomposables, and the isomorphism $M' \cong N'$ transports the decomposition $N_2 \oplus \cdots \oplus N_s$ onto M' as a second decomposition into indecomposables. Applying the inductive hypothesis to M', whose first decomposition has $r - 1$ summands, yields $r - 1 = s - 1$, so $r = s$, together with a bijection matching $M_2, \ldots, M_r$ against $N_2, \ldots, N_s$ up to isomorphism. Combined with $M_1 \cong N_1$ from the exchange step, this produces the permutation σ with $M_i \cong N_{\sigma(i)}$ for all i. The base case $r = 1$ has $M = M_1$ indecomposable, forcing $s = 1$ and $N_1 = M$, completing the induction and the proof.

The theorem says that the finite-length representation theory of *any* algebra, semisimple or not, has canonical building blocks: the indecomposable modules. Over a semisimple algebra these are the simple modules and Krull-Schmidt recovers the decomposition of lemma 51.1.7, but the statement here needs no semisimplicity. What it does need is finite length, and the two places that hypothesis enters are worth marking. Finite length gave the Fitting decomposition (via the ascending and descending chain conditions), which produced the local endomorphism rings; and finite length is what let "injective endomorphism" upgrade to "automorphism" at several points. Drop finiteness and uniqueness can fail. A concrete failure: over the ring $R = \mathbb{R}[x, y, z]/(x^2 + y^2 + z^2 - 1)$ of real polynomial functions on the 2-sphere, the module R^3 splits both as $R \oplus P$, where P is the (indecomposable, non-free) module of tangent vector fields, and as $R \oplus R \oplus R$; the two decompositions have non-isomorphic summands, so uniqueness is lost once the summands are no longer of finite length. Krull-Schmidt is thus not a formality but a theorem with content tied to its hypotheses.

The exchange argument also explains *why* the answer is unique, not just *that* it is. The reason each M_i has a unique isomorphism partner is that when the identity of M_1 is written as a sum of composites through the N_j, locality of $\mathrm{End}_A(M_1)$ forbids the sum from being "spread out" among non-units; one composite must already be invertible, and that single composite pins down the partner. Locality is doing the work that a division ring did in the simple case, and it is the exact amount of structure required.

Reading off the multiplicities gives the invariant form of the theorem that is used in practice.

Corollary 52.2.5: Uniqueness of Multiplicities

Let M be a nonzero A-module of finite length. For each isomorphism class of indecomposable module I, the number of summands isomorphic to I appearing in a decomposition of M into indecomposables is independent of the decomposition. That is, writing

$$M \cong I_1^{\oplus m_1} \oplus I_2^{\oplus m_2} \oplus \cdots \oplus I_t^{\oplus m_t}$$

with the I_j pairwise non-isomorphic indecomposables, the classes $I_1, \ldots, I_t$ and the multiplicities $m_1, \ldots, m_t$ are uniquely determined by M.

***Proof*:**
By theorem 52.2.4, any two decompositions of M into indecomposables have the same number of summands and are matched by a permutation σ respecting isomorphism type. Grouping the summands of a decomposition by isomorphism class, the multiplicity of a class I is the number of indices i with $M_i \cong I$. Since σ carries each M_i to an $N_{\sigma(i)} \cong M_i$ and is a bijection, it restricts to a bijection between the summands isomorphic to I in the first decomposition and those isomorphic to I in the second. Hence the two decompositions assign I the same multiplicity, and this holds for every isomorphism class I. The set of classes that occur and their multiplicities are therefore invariants of M, completing the proof.

The multiplicities m_j are the numbers one computes when decomposing a representation, and the corollary is what guarantees the computation has a well-defined answer regardless of the method used to obtain it. In the language of the Grothendieck-style count, M determines a formal $\mathbb{N}$-linear combination $\sum_j m_j[I_j]$ of indecomposable classes, and two modules are isomorphic if and only if these combinations agree. This is the precise sense in which the indecomposables are a basis for the finite-length modules of A.

The full classification is transparent for $A = k[x]/(x^n)$, where the indecomposables can be listed and the uniqueness of multiplicities checked against an explicit computation.

Example 52.2.6: Modules over the Truncated Polynomial Algebra $k[x]/(x^n)$

Fix $n \geq 1$ and let $A = k[x]/(x^n)$. A finite-dimensional A-module is the same datum as a finite-dimensional k-vector space V together with a k-linear operator T, the action of the class of x, satisfying $T^n = 0$, so that T is nilpotent of nilpotency index at most n. Being finite-dimensional over k, every such module has finite length, so Krull-Schmidt applies.

The indecomposables. Since A is a quotient of the principal ideal domain $k[x]$, the structure theorem for finitely generated modules over $k[x]$ describes every finite-length A-module as a direct sum of cyclic modules $k[x]/(x^m)$. Only the exponents $1 \leq m \leq n$ occur, because x^n annihilates the module. Each

$$J_m := k[x]/(x^m) \qquad 1 \leq m \leq n$$

is indecomposable: as in example 52.2.3, its submodules form the single chain $0 \subseteq (x^{m-1}) \subseteq \cdots \subseteq (x) \subseteq J_m$, which admits no splitting into two nonzero summands. So the indecomposable A-modules are exactly

$$J_1, J_2, \ldots, J_n$$

up to isomorphism, with $\dim_k J_m = m$; these are the Jordan blocks for the nilpotent operator, J_m being a single Jordan block of size m with eigenvalue 0. There are precisely n of them.

A decomposition and its uniqueness. Take $n = 3$ and the module $M = A \oplus J_1$, that is, $V = k^4$ with the operator

$$T = \begin{pmatrix} 0 & 0 & 0 & 0 \\ 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 0 & 0 \end{pmatrix}$$

a single Jordan block of size 3 in the top-left together with a 1×1 zero block. As an A-module,

$$M \cong J_3 \oplus J_1$$

with multiplicities $m_3 = 1$, $m_1 = 1$, and $m_2 = 0$. corollary 52.2.5 asserts these multiplicities are forced by M, and they can be read off invariantly from the ranks of powers of T, which do not depend on any chosen decomposition. The number of Jordan blocks of size at least j equals $\operatorname{rank}(T^{j-1}) - \operatorname{rank}(T^j)$, so the multiplicity of J_m is

$$m_m = \operatorname{rank}(T^{m-1}) - 2\operatorname{rank}(T^m) + \operatorname{rank}(T^{m+1})$$

Here $\operatorname{rank}(T^0) = \operatorname{rank}(\mathrm{id}) = 4$, $\operatorname{rank}(T) = 2$, $\operatorname{rank}(T^2) = 1$, and $\operatorname{rank}(T^3) = 0$. Substituting,

$$m_1 = 4 - 2 \cdot 2 + 1 = 1, \qquad m_2 = 2 - 2 \cdot 1 + 0 = 0, \qquad m_3 = 1 - 2 \cdot 0 + 0 = 1$$

recovering $M \cong J_3 \oplus J_1$. Since the ranks $\operatorname{rank}(T^j)$ are intrinsic to the operator T (hence to the module M), the multiplicities are intrinsic too, exactly as Krull-Schmidt predicts. Any presentation of M as a direct sum of J_m's, arrived at by any change of basis, must yield one copy of J_3, one copy of J_1, and no copy of J_2.

52.3 Idempotents, Projective Covers, and the Regular Representation

The Artin–Wedderburn theorem told us how to read off the simple modules of a semisimple algebra: they are exactly the summands of the regular module A, because a semisimple A splits as a direct sum of minimal left ideals and each minimal left ideal is simple. Once A is not semisimple this picture breaks. The regular module A still decomposes into indecomposable summands (the algebra is finite-dimensional, so a dimension count forces any module to be a finite direct sum of indecomposables), but those summands are no longer simple. They are the *indecomposable projective modules*, and the simple modules sit one level down, as their tops. This section builds the dictionary that replaces the semisimple one: the summands of A are cut out by a decomposition $1 = e_1 + \cdots + e_n$ of the identity into primitive orthogonal idempotents, each summand Ae_i is an indecomposable projective covering a single simple module, and the whole configuration is governed, through the quotient $A/\mathrm{Jac}(A)$, by the semisimple theory of chapter 51.

Throughout this section A is a finite-dimensional algebra over a field k (so in particular A is left Artinian and $\mathrm{Jac}(A)$ is nilpotent). Modules are left modules. The tool that transports information from the semisimple quotient $A/\mathrm{Jac}(A)$ back up to A is the lifting of idempotents, so that is where we begin.

The projection $\pi\colon A \to A/\mathrm{Jac}(A)$ collapses the radical. A decomposition of $A/\mathrm{Jac}(A)$ into a sum of simple summands is a statement about idempotents in $A/\mathrm{Jac}(A)$, and to pull such a decomposition back to A we need to produce idempotents in A that reduce to the given ones. The obstruction is that a preimage of an idempotent need not be idempotent. The nilpotence of $\mathrm{Jac}(A)$ removes the obstruction: a Newton-style correction converts any element that is idempotent modulo $\mathrm{Jac}(A)$ into a genuine idempotent lying over it.

Theorem 52.3.1: Lifting Idempotents Modulo the Radical

Let A be a finite-dimensional k-algebra and write $J = \mathrm{Jac}(A)$. Let $\pi\colon A \to A/J$ be the quotient map.

1. If $\bar{e} \in A/J$ satisfies $\bar{e}^2 = \bar{e}$, then there exists an idempotent $e \in A$ with $\pi(e) = \bar{e}$.
2. If $\bar{e}_1, \ldots, \bar{e}_m \in A/J$ are pairwise orthogonal idempotents with $\bar{e}_1 + \cdots + \bar{e}_m = \bar{1}$, then there exist pairwise orthogonal idempotents $e_1, \ldots, e_m \in A$ with $\pi(e_i) = \bar{e}_i$ and $e_1 + \cdots + e_m = 1$.

***Proof*:**

Since A is left Artinian, $J = \mathrm{Jac}(A)$ is nilpotent by theorem 52.1.8; fix N with $J^N = 0$.

Step 1: Lifting a single idempotent. Choose any $a \in A$ with $\pi(a) = \bar{e}$. Then $a^2 - a \in J$, since $\pi(a^2 - a) = \bar{e}^2 - \bar{e} = 0$. The idea is to correct a inside the coset $a + J$ until the error $a^2 - a$ is pushed into higher and higher powers of J, where it eventually vanishes. Set

$$e = 3a^2 - 2a^3$$

which lies in $a + J$, since $e - a = (3a^2 - 2a^3) - a = -(2a - 1)(a^2 - a) \in J$, so $\pi(e) = \bar{e}$. A direct

computation gives

$$e^2 - e = (3a^2 - 2a^3)^2 - (3a^2 - 2a^3) = (a^2 - a)^2\,(4a^2 - 4a - 3)$$

Writing $u = a^2 - a \in J$, this says $e^2 - e \in (u^2) \subseteq J^2$. Thus the operation $a \mapsto 3a^2 - 2a^3$ sends an element whose defect $a^2 - a$ lies in J^r to an element whose defect lies in J^{2r}, while staying in the same coset modulo J. Starting from $a_0 = a$ with defect in J^1 and iterating,

$$a_{t+1} = 3a_t^2 - 2a_t^3$$

produces $a_t \in a + J$ whose defect $a_t^2 - a_t$ lies in J^{2^t}. Once $2^t \geq N$ we have $a_t^2 - a_t \in J^N = 0$, so $e := a_t$ is a genuine idempotent with $\pi(e) = \bar{e}$. This proves (1).

Step 2: Lifting an orthogonal family. We argue by induction on m. For $m = 1$ the statement is $e_1 = 1$, which is immediate. Suppose the result holds for families of size $m-1$, and let $\bar{e}_1, \dots, \bar{e}_m$ be pairwise orthogonal idempotents summing to $\bar{1}$. Apply the inductive hypothesis to the shorter orthogonal family $\bar{e}_1, \dots, \bar{e}_{m-2}, \bar{e}_{m-1} + \bar{e}_m$ (its members are pairwise orthogonal idempotents summing to $\bar{1}$, since $\bar{e}_{m-1}$ and $\bar{e}_m$ are orthogonal). This yields pairwise orthogonal idempotents $e_1, \dots, e_{m-2}, f \in A$ lifting them, with $e_1 + \cdots + e_{m-2} + f = 1$ and $\pi(f) = \bar{e}_{m-1} + \bar{e}_m$.

It remains to split f. Consider the algebra fAf, which has identity element f. Its radical is $\mathrm{Jac}(fAf) = fJf$, and the reduction $fAf \to fAf/fJf$ identifies with the corner $\bar{f}(A/J)\bar{f}$ of the semisimple algebra A/J, where $\bar{f} = \bar{e}_{m-1} + \bar{e}_m$. In that corner, $\bar{e}_{m-1}$ and $\bar{e}_m$ are orthogonal idempotents summing to the identity $\bar{f}$. Applying part (1) inside the finite-dimensional algebra fAf to the idempotent $\bar{e}_{m-1} \in fAf/fJf$ produces an idempotent $e_{m-1} \in fAf$ with $\pi(e_{m-1}) = \bar{e}_{m-1}$. Set $e_m = f - e_{m-1}$. Then e_m is idempotent, since

$$e_m^2 = (f - e_{m-1})^2 = f - 2e_{m-1} + e_{m-1} = f - e_{m-1} = e_m$$

using $fe_{m-1} = e_{m-1}f = e_{m-1}$ (because $e_{m-1} \in fAf$) and $e_{m-1}^2 = e_{m-1}$; moreover $\pi(e_m) = \bar{f} - \bar{e}_{m-1} = \bar{e}_m$, and $e_{m-1}e_m = e_{m-1}f - e_{m-1}^2 = e_{m-1} - e_{m-1} = 0$, with $e_m e_{m-1} = 0$ symmetrically. Finally $e_{m-1}, e_m \in fAf$ are orthogonal to each of $e_1, \dots, e_{m-2}$, since f is, and $e_1 + \cdots + e_{m-2} + e_{m-1} + e_m = e_1 + \cdots + e_{m-2} + f = 1$. This completes the induction and the proof.

The polynomial $3a^2 - 2a^3$ is the second Newton iterate for the equation $x^2 - x = 0$; the quadratic doubling of the exponent is exactly Newton's quadratic convergence, made to terminate by nilpotence rather than to converge by a metric. The content of the theorem is that the arithmetic of idempotents in A is completely controlled by the arithmetic of idempotents in the semisimple quotient $A/\mathrm{Jac}(A)$: any way of splitting the identity in $A/\mathrm{Jac}(A)$ lifts to a way of splitting it in A, so the summand structure of the regular module is governed from below by Artin–Wedderburn. The next result turns this into a decomposition of A itself.

Before stating it, recall the mechanism from example 51.2.10: an idempotent $e \in A$ produces a direct sum decomposition $A = Ae \oplus A(1-e)$ of the regular module, because every $a \in A$ writes uniquely as $a = ae + a(1-e)$ with $ae \in Ae$ and $a(1-e) \in A(1-e)$. More generally an orthogonal decomposition $1 = e_1 + \cdots + e_n$ gives $A = Ae_1 \oplus \cdots \oplus Ae_n$. The summand Ae_i is indecomposable precisely when e_i cannot be split further, which is the meaning of *primitive*. Pushing the splitting as far as it will go decomposes the regular module into indecomposables.

Theorem 52.3.2: Primitive Idempotent Decomposition of the Regular Module

Let A be a finite-dimensional k-algebra. Then the identity admits a decomposition

$$1 = e_1 + e_2 + \cdots + e_n$$

into pairwise orthogonal primitive idempotents, and correspondingly the regular module decomposes as

$$A = Ae_1 \oplus Ae_2 \oplus \cdots \oplus Ae_n$$

where each Ae_i is an indecomposable projective left A-module. For an idempotent $e \in A$ with $e \neq 0$, the summand Ae is indecomposable if and only if e is primitive, if and only if the corner algebra eAe has no idempotents other than 0 and e.

***Proof*:**

Step 1: Idempotent decompositions correspond to direct-sum decompositions. Let $e \in A$ be an idempotent. Direct summands of the module Ae correspond to idempotents of its endomorphism ring: if $Ae = P \oplus Q$, the projection onto P along Q is an idempotent $\varepsilon \in \mathrm{End}_A(Ae)$, and conversely an idempotent $\varepsilon \in \mathrm{End}_A(Ae)$ splits $Ae = \varepsilon(Ae) \oplus (1-\varepsilon)(Ae)$. By the same computation as in lemma 51.2.3, the map $eAe \to \mathrm{End}_A(Ae)$ sending eae to right multiplication $x \mapsto x(eae)$ is a ring isomorphism

$$\mathrm{End}_A(Ae) \cong (eAe)^{\mathrm{op}}$$

The idempotents of $(eAe)^{\mathrm{op}}$ are the idempotents of eAe. So Ae decomposes nontrivially if and only if eAe has an idempotent other than 0 and $e = 1_{eAe}$. Writing such an idempotent as g and its complement $e - g$ (which is idempotent and orthogonal to g, by the computation in Step 2 of theorem 52.3.1), the decomposition $Ae = Ag \oplus A(e-g)$ corresponds to the refinement $e = g + (e-g)$ of e into orthogonal idempotents. Thus e is primitive (cannot be written as a sum of two nonzero orthogonal idempotents) if and only if eAe has no idempotent besides $0, e$, if and only if Ae is indecomposable. This proves the final three-way equivalence.

Step 2: The decomposition terminates. Start from 1. If 1 is primitive, take $n = 1$. Otherwise $1 = f + f'$ with f, f' nonzero orthogonal idempotents, giving $A = Af \oplus Af'$ with both summands nonzero. Since A is finite-dimensional and the summands Af, Af' are proper (each has strictly smaller k-dimension than A, as the other is nonzero), repeating the splitting on any summand that is still decomposable strictly decreases dimension at each step and so must stop. When it stops, every summand Ae_i is indecomposable, so by Step 1 each e_i is primitive. The resulting $e_1, \ldots, e_n$ are pairwise orthogonal (an idempotent split off from a corner Ae is orthogonal to every idempotent orthogonal to e) and sum to 1.

Step 3: Projectivity. Each Ae_i is a direct summand of the free module A, hence projective. A direct summand of a free module is projective because the splitting $A = Ae_i \oplus A(1-e_i)$ exhibits Ae_i as a retract of A, and retracts of free modules satisfy the lifting property defining projectivity. The general statement is proved in the companion volume, [21, Equivalencies for Projective Modules]. This gives the decomposition of A into indecomposable projectives, completing the proof.

The decomposition $A = \bigoplus_i Ae_i$ is the non-semisimple replacement for the Wedderburn splitting of a semisimple algebra into minimal left ideals. In the semisimple case each Ae_i was already simple, and the e_i were the matrix units picking out columns of the matrix blocks (proposition 51.2.5). In

general each Ae_i is only indecomposable, and it will turn out to have a whole composition series rather than length one. The indecomposable summands that appear are the objects the rest of the section studies, so they deserve a name.

Definition 52.3.3: Indecomposable Projective Module

Let A be a finite-dimensional k-algebra and $1 = e_1 + \cdots + e_n$ a decomposition of the identity into primitive orthogonal idempotents. The indecomposable projective left A-modules are the summands

$$P_i = Ae_i$$

Its *radical* is $\operatorname{rad}(P_i) = \operatorname{Jac}(A)\, P_i$, and its *top* (or *head*) is the quotient

$$\operatorname{top}(P_i) = P_i/\operatorname{rad}(P_i) = Ae_i/\operatorname{Jac}(A)Ae_i$$

The module P_i is called the *projective cover* of its top; the top is a simple module.

The claim that the top is simple is the hinge of the whole correspondence, so we verify it at once. Reducing modulo $\operatorname{Jac}(A)$ turns the primitive idempotent e_i into a primitive idempotent $\bar{e}_i \in A/\operatorname{Jac}(A)$, and over the semisimple algebra $A/\operatorname{Jac}(A)$ a primitive idempotent cuts out a simple module.

Example 52.3.4: The Top of Ae_i

Let $A = k[x]/(x^3)$, a local algebra with $\operatorname{Jac}(A) = (x)/(x^3)$. Here 1 is the only nonzero idempotent (a commutative local ring has no idempotents besides 0 and 1), so the identity decomposition is trivial, $n = 1$ and $e_1 = 1$, giving a single indecomposable projective $P_1 = A$. Its radical is $\operatorname{rad}(P_1) = \operatorname{Jac}(A)\, A = (x)/(x^3)$, and its top is

$$P_1/\operatorname{rad}(P_1) = \big(k[x]/(x^3)\big)\big/\big((x)/(x^3)\big) \cong k[x]/(x) = k$$

a one-dimensional, hence simple, module. So the single projective $P_1 = A$ (of dimension 3) covers the single simple module k (of dimension 1); the two extra dimensions live in the radical $\operatorname{rad}(P_1)$, whose composition factors are again copies of k. This is the smallest example in which a projective indecomposable is strictly larger than the simple it covers.

The passage $P_i \mapsto \operatorname{top}(P_i)$ from indecomposable projectives to simple modules, and its reverse, is the organizing principle of non-semisimple representation theory. Simple modules are visible in the semisimple quotient $A/\operatorname{Jac}(A)$, where Artin–Wedderburn counts them; primitive idempotents in A are the summands of the regular module; and lifting idempotents connects the two. The following theorem assembles these into a single correspondence.

Theorem 52.3.5: Simples, Indecomposable Projectives, and Primitive Idempotents

Let A be a finite-dimensional k-algebra, and let $1 = e_1 + \cdots + e_n$ be a decomposition of the identity into primitive orthogonal idempotents. There are mutually inverse bijections among the following three finite sets:

1. isomorphism classes of simple left A-modules;
2. isomorphism classes of indecomposable projective left A-modules;
3. conjugacy classes of primitive idempotents of A, where e and e' are conjugate if $e' = ueu^{-1}$ for a unit $u \in A^\times$.

The bijection from (2) to (1) sends $P_i \mapsto S_i := P_i/\mathrm{rad}(P_i)$; the bijection from (3) to (2) sends the class of e_i to $P_i = Ae_i$. If A is split, that is every A-linear endomorphism of a simple A-module is a scalar (for instance if $k = \bar{k}$), the number of classes equals the number of blocks in the Artin–Wedderburn decomposition of $A/\mathrm{Jac}(A)$, and

$$A/\mathrm{Jac}(A) \cong M_{d_1}(k) \times \cdots \times M_{d_r}(k), \qquad d_i = \dim_k S_i$$

where $S_1, \dots, S_r$ are the simple modules and P_i appears $d_i = \dim_k S_i$ times in $A = \bigoplus_i P_i^{\oplus m_i}$.

***Proof*:**

Write $J = \mathrm{Jac}(A)$ and $\bar{A} = A/J$, which is semisimple by theorem 52.1.9.

Step 1: Simple modules are the same for A and $\bar{A}$. A simple A-module S is annihilated by J: the submodule $JS \subseteq S$ is either 0 or S, and $JS = S$ is impossible by Nakayama's lemma (lemma 52.1.7, applied to the cyclic module S: $JS = S$ would force $S = 0$). Hence $JS = 0$ and S is an $\bar{A}$-module; conversely every $\bar{A}$-module is an A-module through $\pi\colon A \to \bar{A}$. Since a submodule for A is the same as a submodule for $\bar{A}$ on a module killed by J, simplicity is preserved in both directions. Thus the simple A-modules are exactly the simple $\bar{A}$-modules, and by corollary 51.1.12 there are finitely many, one for each Wedderburn block of $\bar{A}$.

Step 2: $\mathrm{top}(P_i)$ is simple, and $P_i \mapsto \mathrm{top}(P_i)$ lands in (1). Reducing the decomposition $1 = e_1 + \cdots + e_n$ modulo J gives $\bar{1} = \bar{e}_1 + \cdots + \bar{e}_n$, a decomposition into orthogonal idempotents of $\bar{A}$. Applying the right-exact functor $\bar{A} \otimes_A -$ (equivalently reducing mod J) to $P_i = Ae_i$ gives

$$P_i/JP_i = Ae_i/JAe_i \cong \bar{A}\bar{e}_i$$

as $\bar{A}$-modules. Now $\bar{e}_i$ is primitive in $\bar{A}$: an orthogonal splitting $\bar{e}_i = \bar{g} + \bar{h}$ in $\bar{A}$ would lift, by theorem 52.3.1 applied inside the corner e_iAe_i, to an orthogonal splitting of e_i in A, contradicting primitivity of e_i. Over the semisimple algebra $\bar{A}$ a primitive idempotent generates a simple module, since $\bar{A}\bar{e}_i$ is an indecomposable summand of the semisimple module $\bar{A}$ and indecomposable semisimple means simple. Hence $\mathrm{top}(P_i) = P_i/\mathrm{rad}(P_i) = \bar{A}\bar{e}_i =: S_i$ is simple.

Step 3: The map (2) $\to$ (1) is a bijection. Distinct indecomposable projectives have distinct tops: if $Ae_i \cong Ae_j$ as A-modules then reducing mod J gives $\bar{A}\bar{e}_i \cong \bar{A}\bar{e}_j$, so $S_i \cong S_j$; conversely if $S_i \cong S_j$ then the two primitive idempotents $\bar{e}_i, \bar{e}_j$ generate isomorphic simple summands of $\bar{A}$, hence are conjugate in $\bar{A}$ (two primitive idempotents of a semisimple algebra generating isomorphic simples lie in the same Wedderburn block and differ by an inner automorphism), and a conjugating unit lifts to a unit of A because $\pi\colon A^\times \to \bar{A}^\times$ is surjective (an element of A

mapping to a unit of $\bar{A}$ is itself a unit, since J is nilpotent: if $\bar{a}$ is invertible then a has a left and right inverse modulo the nilpotent ideal J, and $1 + J \subseteq A^\times$). Conjugate idempotents give isomorphic projectives $Ae_i \cong Ae_j$ via right multiplication by the conjugating unit. So $P_i \cong P_j$ if and only if $S_i \cong S_j$, giving a bijection between (2) and (1). Every simple module arises as some S_i: a simple $\bar{A}$-module is a summand of $\bar{A} = \bigoplus_i \bar{A}\bar{e}_i$, hence isomorphic to some $\bar{A}\bar{e}_i = S_i$.

Step 4: Conjugacy classes of primitive idempotents. By the last paragraph, $Ae_i \cong Ae_j$ as modules if and only if e_i and e_j are conjugate in A: one direction lifts a conjugation, the other reduces an isomorphism to a conjugation via $\mathrm{End}_A(A) \cong A^{\mathrm{op}}$ (lemma 51.2.3), under which a module isomorphism $Ae_i \to Ae_j$ is right multiplication by an element u with $ue_iu^{-1} = e_j$. Thus the class of e_i under conjugacy corresponds to the isomorphism class of P_i, giving the bijection between (3) and (2).

Step 5: The split case. When $k = \bar{k}$, the algebra A is split: a simple module S is a quotient of A, hence finite-dimensional, so $\mathrm{End}_A(S)$ is a finite-dimensional division k-algebra by lemma 51.1.5, equal to k by corollary 51.2.19.

Now let A be split. By corollary 51.2.18 applied to the semisimple algebra $\bar{A}$, we have $\bar{A} \cong \prod_{l=1}^{r} M_{d_l}(D_l)$ with each D_l a finite-dimensional division k-algebra, and $\bar{A}$ has exactly r simple modules, the column modules $D_l^{\oplus d_l}$ of the blocks, on which the other blocks act by zero. By Step 1 these are the simple A-modules, and their A-endomorphisms are their $M_{d_l}(D_l)$-endomorphisms, which form the ring D_l^{op} by corollary 51.2.8. The split hypothesis gives $\dim_k D_l = 1$, so $D_l = k$ and the simple modules are $S_l = k^{d_l}$, with $\dim_k S_l = d_l$.

For the multiplicities, let $P_1, \dots, P_r$ be indecomposable projectives with $\mathrm{top}(P_i) = S_i$ (Step 3), and let m_i be the number of j with $Ae_j \cong P_i$, so that $A = \bigoplus_i P_i^{\oplus m_i}$. By Step 3, m_i is also the number of j with $\bar{A}\bar{e}_j \cong S_i$. For simple modules S and T, the space $\mathrm{Hom}_{\bar{A}}(S, T)$ is one-dimensional if $S \cong T$ and zero otherwise, by lemma 51.1.5 and the split hypothesis. So for any decomposition of $\bar{A}$ into finitely many simple submodules, $\dim_k \mathrm{Hom}_{\bar{A}}(S_i, \bar{A})$ is the number of summands isomorphic to S_i. The decomposition $\bar{A} = \bigoplus_j \bar{A}\bar{e}_j$ of Step 2 gives the number m_i. The decomposition of $\bar{A} \cong \prod_l M_{d_l}(k)$ in which each block $M_{d_l}(k)$ is the direct sum of its d_l columns, each isomorphic to k^{d_l}, gives the number d_i. So $m_i = d_i = \dim_k S_i$, as we sought to show.

The correspondence is the reason the count of simple modules is finite and computable: it equals the number of Wedderburn blocks of $A/\mathrm{Jac}(A)$, which Artin–Wedderburn hands us. In the semisimple case the three sets coincide with the columns of the matrix blocks and the map $P_i \mapsto S_i$ is the identity; the passage to a general finite-dimensional algebra keeps the same indexing set but separates the projective P_i from the simple S_i it covers. The word “cover” is precise, and the next definition makes it so. A cover should be the most economical projective surjecting onto a module, with no wasted projective sitting over the radical.

Definition 52.3.6: Superfluous Submodule and Projective Cover

Let A be a ring and M an A-module. A submodule $L \subseteq M$ is *superfluous* (or *small*) if for every submodule $N \subseteq M$ the equality $L + N = M$ forces $N = M$. A surjection $f\colon P \to M$ is *essential* if $\ker f$ is superfluous in P.
A *projective cover* of M is a projective module P together with an essential surjection $f\colon P \to M$; that is, f is surjective, P is projective, and $\ker f$ is superfluous in P.

The condition that $\ker f$ be superfluous is what pins the cover down. Any module has a surjection from a projective (a free module surjects onto it), but without the superfluous condition one could pad the source with a free summand mapping to zero and never have a canonical choice. Superfluousness forbids exactly this padding: no proper submodule of P maps onto M, so P is as small a projective as can surject onto M. Over a finite-dimensional algebra the radical gives a ready source of superfluous submodules, and this makes covers exist and be unique.

Theorem 52.3.7: Existence of Projective Covers

Let A be a finite-dimensional k-algebra and M a finitely generated (equivalently, finite-length) left A-module. Then M has a projective cover $f\colon P \to M$, unique up to isomorphism over M. For a simple module $S = S_i$, the projective cover is the indecomposable projective $P_i = Ae_i$ with its quotient map $P_i \twoheadrightarrow P_i/\mathrm{rad}(P_i) = S_i$.

***Proof*:**
Write $J = \mathrm{Jac}(A)$.

Step 1: JP is superfluous in a finitely generated P. Let P be finitely generated and suppose $JP + N = P$ for a submodule $N \subseteq P$. Then $J \cdot (P/N) = (JP + N)/N = P/N$, so the finitely generated module P/N satisfies $J \cdot (P/N) = P/N$. Nakayama's lemma (the module form, lemma 52.1.7; concretely, using the nilpotence of J: if $J^N = 0$ and $JQ = Q$ then $Q = JQ = J^2Q = \cdots = J^NQ = 0$) forces $P/N = 0$, i.e. $N = P$. Hence JP is superfluous in P.

Step 2: Construction of the cover. The top $\bar{M} = M/JM$ is a module over the semisimple algebra $\bar{A} = A/J$, hence semisimple: $\bar{M} \cong \bigoplus_i S_i^{\oplus c_i}$ for multiplicities $c_i \geq 0$. Set

$$P = \bigoplus_i P_i^{\oplus c_i}$$

with each $P_i = Ae_i$ the indecomposable projective covering S_i. Then $P/JP = \bigoplus_i (P_i/JP_i)^{\oplus c_i} = \bigoplus_i S_i^{\oplus c_i} = \bar{M}$, so the projection $P \to P/JP = \bar{M}$ agrees with $M \to \bar{M}$ on tops. Because P is projective, the surjection $M \twoheadrightarrow \bar{M}$ lifts through $P \to \bar{M}$ to a homomorphism $f\colon P \to M$ with $M \to \bar{M}$ equal to $P \xrightarrow{f} M \to \bar{M}$. The image $f(P)$ satisfies $f(P) + JM = M$ (their images in $\bar{M}$ agree and equal all of $\bar{M}$), and JM is superfluous in M by Step 1 applied to M; hence $f(P) = M$ and f is surjective.

Step 3: f is essential. Let $K = \ker f$. Suppose $K + N = P$ for a submodule N. Then $f(N) = f(P) = M$, so $N + JP \supseteq N + \ker(P \to \bar{M})$ surjects onto $\bar{M} = P/JP$, giving $N + JP = P$; since JP is superfluous (Step 1), $N = P$. Thus K is superfluous and $f\colon P \to M$ is a projective cover.

Step 4: Uniqueness. Let $f\colon P \to M$ and $f'\colon P' \to M$ be two projective covers. Projectivity of P'

lifts f' through f to $g\colon P' \to P$ with $fg = f'$. Then $f(g(P')) = f'(P') = M$, so $g(P') + \ker f = P$; since $\ker f$ is superfluous, $g(P') = P$ and g is surjective. As P' is projective, the surjection g splits, $P' = \ker g \oplus P''$ with $P'' \cong P$; but $\ker g \subseteq \ker f' = \ker(fg)$ is superfluous in P' and a superfluous direct summand is zero (a summand L with complement C satisfies $L + C = P'$, forcing $C = P'$ hence $L = 0$). So g is an isomorphism over M.

Step 5: The simple case. For $M = S_i$ the top $\bar{M} = S_i$ has $c_i = 1$ and all other multiplicities 0, so the construction returns $P = P_i$ with $f\colon P_i \twoheadrightarrow P_i/\mathrm{rad}(P_i) = S_i$, the stated cover, completing the proof.

The theorem certifies the terminology in definition 52.3.3: $P_i \to S_i$ really is *the* projective cover, and every finite-length module is covered by an explicit direct sum of the P_i read off from its top. Uniqueness makes the assignment $M \mapsto P(M)$ well defined and turns the correspondence of theorem 52.3.5 into a computational tool: to find the projective cover of any module, compute its top $M/\mathrm{Jac}(A)M$, decompose that semisimple module into simples, and sum the corresponding P_i. What the projective P_i contributes beyond the simple top S_i is recorded in its composition series, and tabulating those multiplicities across all i produces the central numerical invariant of the algebra.

Definition 52.3.8: Cartan Matrix of an Algebra

Let A be a finite-dimensional k-algebra with simple modules $S_1, \dots, S_r$ and indecomposable projectives $P_1, \dots, P_r$, indexed so that $P_i/\mathrm{rad}(P_i) = S_i$. The *Cartan matrix* of A is the $r \times r$ matrix $C = (C_{ij})$ of nonnegative integers

$$C_{ij} = [P_i : S_j]$$

the multiplicity of the simple module S_j among the composition factors of a composition series of P_i.

The multiplicities $[P_i : S_j]$ are well defined by the Jordan–Hölder theorem, which guarantees the composition factors of a finite-length module are independent of the chosen composition series. The Cartan matrix measures how far A is from semisimple in a single array: when A is semisimple every $P_i = S_i$ has length one, so $C_{ij} = \delta_{ij}$ is the identity matrix, and any off-diagonal or large diagonal entry records simples fused together by the radical. The diagonal entry $C_{ii} = [P_i : S_i]$ is at least 1 (the top contributes one copy of S_i), and $C_{ii} > 1$ signals a self-extension living in the radical. The next example computes the whole apparatus of this section for the smallest non-semisimple algebra with two non-isomorphic simple modules, so that the Cartan matrix is not diagonal.

Before the example, one further point for completeness: the entire theory has a dual half. Everything above was built from the regular module A as a source of projectives; dualizing over k turns projectives into injectives and covers into envelopes.

52.3.9 Remark: The Dual Theory of Injective Envelopes Dual to a projective cover is an *injective envelope*: an injective module E with an essential injection $M \hookrightarrow E$, meaning every nonzero submodule of E meets the image of M nontrivially. Over a finite-dimensional algebra A these exist and are unique, and the duality $D = \mathrm{Hom}_k(-, k)$ carries left A-modules to right A-modules (equivalently left A^{op}-modules), exchanging projective covers of A-modules with injective envelopes of A^{op}-modules. The indecomposable injective A-modules are thus $D(e_i A)$, and each has a simple *socle* (its largest semisimple submodule) rather than a simple top; the socle plays for injectives the role the top plays for projectives. The general theory of injective and projective modules over a ring, including existence of injective envelopes via injective hulls, is developed in the companion volume [21]; the present section uses only the projective side.

Example 52.3.10: Projective Covers over the Upper-Triangular Algebra $T_2(k)$
Let

$$A = T_2(k) = \left\{ \begin{pmatrix} a & b \\ 0 & c \end{pmatrix} : a, b, c \in k \right\}$$

the algebra of 2×2 upper-triangular matrices over a field k, a three-dimensional k-algebra. We work out its idempotents, indecomposable projectives, simple modules, projective covers, and Cartan matrix.

Idempotents. The matrix units

$$e_1 = \begin{pmatrix} 1 & 0 \\ 0 & 0 \end{pmatrix}, \qquad e_2 = \begin{pmatrix} 0 & 0 \\ 0 & 1 \end{pmatrix}$$

are orthogonal idempotents with $e_1 + e_2 = 1$. Each is primitive: the corner algebra $e_1 A e_1 = k\, e_1 \cong k$ has no idempotents but $0, e_1$, and likewise $e_2 A e_2 \cong k$, so by theorem 52.3.2 both Ae_1 and Ae_2 are indecomposable. Thus $1 = e_1 + e_2$ is a primitive orthogonal decomposition and there are two indecomposable projectives.

The radical. The Jacobson radical is the strictly upper-triangular part,

$$\mathrm{Jac}(A) = \begin{pmatrix} 0 & k \\ 0 & 0 \end{pmatrix}$$

a one-dimensional nilpotent ideal with $\mathrm{Jac}(A)^2 = 0$, and the quotient is

$$A/\mathrm{Jac}(A) \cong \begin{pmatrix} k & 0 \\ 0 & k \end{pmatrix} \cong k \times k$$

a product of two copies of k, confirming via theorem 52.3.5 that there are exactly two simple modules, both one-dimensional.

The indecomposable projectives. Left multiplication by A on e_i gives, with $E_{12} = \left(\begin{smallmatrix} 0 & 1 \\ 0 & 0 \end{smallmatrix}\right)$,

$$P_1 = Ae_1 = \begin{pmatrix} k & 0 \\ 0 & 0 \end{pmatrix}, \qquad P_2 = Ae_2 = \begin{pmatrix} 0 & k \\ 0 & k \end{pmatrix}$$

so $\dim_k P_1 = 1$ and $\dim_k P_2 = 2$, and indeed $\dim_k A = 1 + 2 = 3 = \dim_k P_1 + \dim_k P_2$, consistent with $A = P_1 \oplus P_2$.

The simple modules and covers. The tops are

$$S_1 = P_1/\mathrm{rad}(P_1) = P_1/\mathrm{Jac}(A)P_1 = P_1 \cong k, \qquad S_2 = P_2/\mathrm{rad}(P_2) = P_2/\mathrm{Jac}(A)P_2 \cong k$$

Here $\mathrm{Jac}(A)P_1 = 0$, so $P_1 = S_1$ is already simple and is its own projective cover, an essential surjection $P_1 \xrightarrow{\cong} S_1$. For P_2, the radical $\mathrm{Jac}(A)P_2 = \left(\begin{smallmatrix} 0 & k \\ 0 & 0 \end{smallmatrix}\right)$ is one-dimensional, and

$$\mathrm{rad}(P_2) = \begin{pmatrix} 0 & k \\ 0 & 0 \end{pmatrix} \cong S_1, \qquad P_2/\mathrm{rad}(P_2) \cong S_2$$

So P_2 is a length-two module with a nonsplit exact sequence

$$0 \to S_1 \to P_2 \to S_2 \to 0$$

and the quotient map $P_2 \twoheadrightarrow S_2$ is the projective cover of S_2, with kernel $\mathrm{rad}(P_2) = S_1$ superfluous in P_2 (it lies inside $\mathrm{Jac}(A)P_2$). The two simple modules S_1 and S_2 are not isomorphic, since e_1 and e_2 act as 1 on one and 0 on the other; the algebra is not semisimple, as $\mathrm{Jac}(A) \neq 0$.

The Cartan matrix. Reading off composition factors: P_1 has the single factor S_1, while P_2 has factors S_2 (its top) and S_1 (its radical). Hence

$$[P_1 : S_1] = 1, \quad [P_1 : S_2] = 0, \quad [P_2 : S_1] = 1, \quad [P_2 : S_2] = 1$$

and the Cartan matrix is the upper-triangular integer matrix

$$C = \begin{pmatrix} C_{11} & C_{12} \\ C_{21} & C_{22} \end{pmatrix} = \begin{pmatrix} 1 & 0 \\ 1 & 1 \end{pmatrix}$$

Its determinant is 1 and its off-diagonal entry $C_{21} = 1$ records the single copy of S_1 that the radical of P_2 contributes: the exact numerical trace of the failure of $T_2(k)$ to be semisimple, where the Cartan matrix would have been the identity.

53

Representation of Finite Groups

All modules will be left R-modules for a not necessarily commutative ring R. Furthermore, all actions will be non-trivial actions unless specified otherwise.

53.1 Representations of Finite Groups

Similarly to how we studied groups and by how they acted on themselves through group-actions (ex. how a group acted on itself by conjugation gave us Sylow's Theorem), we will now try to study groups using *linear algebra*. Many really difficult results in classical group theory will become much easier when studied through this new "representation" of groups (and hence why it is called *representation theory*). Furthermore, vector-spaces afford many more structures than a module structures (ex. a complex vector-space is the starting point for the Nullstellensatz, Complex Geometry, Analysis, and much more!) Hence, one large advantage of Representation theory will be the intersection of many mathematical disciplines which contribute towards our study (and they all feed back on each other).

In this part of the book, G will always be a finite group[1], and k will always be a field. The module-theoretic set-up of this section works over any field, but the results that follow do not: Maschke's theorem and everything downstream of it need $\mathrm{char}(k) \nmid |G|$, and the character theory of section 53.2 needs $k = \mathbb{C}$. Each result states the hypothesis it needs, and section 53.5$\star$ takes up what happens when $\mathrm{char}(k)$ divides $|G|$. We write $\mathrm{Aut}_{k\text{-}\mathbf{Vect}}(V) = \mathrm{GL}(V)$ for the automorphisms of the k-vector space V. Once a basis is chosen and $\dim(V) = n < \infty$, this is isomorphic to $\mathrm{GL}_n(k)$, the group of invertible $n \times n$ matrices over k.

[1] Not sure about where to address infinite groups

Definition 53.1.1: Representation

Let G be a finite group and V a vector space over k. Then a *linear representation* is any homomorphism $\varphi : G \to \mathrm{GL}(V)$. The *degree* of the representation is the dimension of V. A *matrix representation* of G is any homomorphism $\varphi : G \to \mathrm{GL}_n(k)$

Usually, when we say representation we will mean *linear representation*. If a vector-space V has a representation of G, we will often call it a G-representation. To be as rigorous as possible we would say we have a representation of G on V over k, if the context requires it. Just like for group actions, a representation is *faithful* if it is injective. Representations need not be faithful, and most are not: the trivial representation, the sign representation of S_n, and anything inflated from a proper quotient all have kernel.

As usual, we can curry or uncurry an action[2]: we can take $\varphi : G \to \mathrm{GL}(V)$ and make it $G \times V \to V$ where $g : V \to V$ with $v \mapsto g \cdot v$ is linear over k for all g. It is left for the curious to see that this is indeed the proper uncurrying of this action.

Using the definition of $\varphi : G \to \mathrm{GL}(V)$, it is easy to define a representation homomorphism mirroring the definition of group-actions and modules (which are ring actions on abelian groups):

Definition 53.1.2: Representation Homomorphism

Let V, W be two vectors spaces over k with a linear representation by G. Then $\varphi : V \to W$ a *representation homomorphism* if φ k-linear and for any $g \in G$:

$$\varphi(g \cdot v) = g \cdot \varphi(v)$$

such a homomorphism will be called G-linear.

From this perspective, it might be hard to see how our previous discussion on semi-simple rings might give us any insight. We thus introduce a perspective better suited to the results of chapter 51: every representation of G on V over k is in bijective correspondence with all $k[G]$-modules over V, where $k[G]$ represents the *group ring* as seen in section 9.2. This second perspective will also make it easier to define a couple of examples, and so we will delay giving examples till the correspondence has been established. As a reminder, a group ring $k[G]$ over a ring k (which in our case will always be a field) is the set of all formal sums:

$$\sum_{g_i \in G} a_i g_i$$

where addition and multiplication are defined in the natural way[3]:

$$\sum_i^n a_i g_i + \sum b_i g_i = \sum_i (a_i + b_i) g_i$$

$$\left(\sum_i^n a_i g_i \right) \left(\sum b_i g_i \right) = \sum_\ell^n \left(\sum_{\substack{i,j \\ g_i g_j = g_\ell}} a_i b_j \right) g_\ell$$

[2] See remark 4.1.3

[3] A word on this really being a natural way?

Another common notation for group rings is kG, where the brackets are dropped. Several facts about group rings are used below:

1. The group G naturally injects into $k[G]$ by identifying g_i with $1g_i$ which is the formal sum $\sum_j \delta_{ij} g_j$ (where δ_{ij} is the Kronecker delta).
2. The field k naturally injects in $k[G]$ by corresponding an element $a \in k$ with $ag_1 = ae$ where $g_1 = e$ is the identity. If it is clear from context, we will sometimes simply write $a \in k[G]$ if it is understood $a = ae = ag_1$.
3. There is a natural k action on $k[G]$ defined by
$$b \cdot \left(\sum_i a_i g_i \right) = \sum_i (ba_i) g_i$$
due to this, $k[G]$ is a vector space over k with the elements of G as a basis, and hence is finite dimensional if $|G| < \infty$.
4. By definition, The elements of k identified as kg_1 commute with all the elements of $k[G]$, hence it is in the center of $k[G]$: $k \subseteq Z(k[G])$. Thus, $k[G]$ is in fact a k-algebra.
5. The group ring is left adjoint to the unit-group functor $A \mapsto A^\times$ from k-algebras to groups, that is $\mathrm{Hom}_{k\text{-}\mathbf{Alg}}(k[G], A) \cong \mathrm{Hom}_{\mathbf{Grp}}(G, A^\times)$, hence is free with respect to groups, justifying the name "formal sum" for it's elements.

Using these, we show how representations of G on V over k correspond to $k[G]$-modules: let $\varphi : G \to \mathrm{GL}(V)$ be a representation, with $G = \{g_1, g_2, ..., g_n\}$. Thus, each $\varphi(g_i)$ is linear transformation (in particular an automorphism). Define the $k[G]$ action on V by defining:
$$\left(\sum_i^n a_i g_i \right) \cdot v = \left(\sum_i^n a_i \varphi(g_i) \right)(v) = \sum_i^n a_i \varphi(g_i)(v)$$
Then this defines a $k[G]$-module (as should be verified if it does not seem like it). A particular reminder for those who are checking that $\varphi(g_i g_j) = \varphi(g_i) \circ \varphi(g_j)$, since φ is a group homomorphism onto $\mathrm{GL}(V)$ under composition. Notice how this action in fact extends the action of k on $k[G]$ since $a \cdot v = av$ (similarly to how the $F[x]$ action extended the action of F on V in section 14.3).

Conversely, let's say V is an $k[G]$-module. Seeking to make V a vector space over k and finding a group homomorphism $\varphi : G \to \mathrm{GL}(V)$, the first thing is that V is already a K vector-space by limiting to the action of $k \subseteq k[G]$. Furthermore, for each $g \in G$, we can obtain a map $\varphi : V \to V$ by defining:
$$\varphi(g)(v) = g \cdot v$$
Then $\varphi(g)$ is a linear transformation: for $\alpha, \beta \in k$, $v, w \in V$
$$\begin{aligned} \varphi(g)(\alpha v + \beta w) &= g \cdot (\alpha v + \beta w) \\ &= \alpha(g \cdot v) + \beta(g \cdot w) \\ &= \alpha\varphi(g)(v) + \beta\varphi(g)(w) \end{aligned}$$
and by the associativity axiom of modules, we get
$$\varphi(g_i g_j)(v) = (\varphi(g_i) \circ \varphi(g_j))(v)$$

Thus, $\varphi : G \to \mathrm{GL}(V)$ is indeed a group homomorphism, and we have:

$$\left\{ V \text{ an } k[G]\text{-module} \right\} \rightleftarrows \left\{ \begin{array}{c} V \text{ a vector space over } k \\ \text{and} \\ \varphi : G \to \mathrm{GL}(V) \text{ a representation} \end{array} \right\}$$

Note that this also means that this also shows that linear representations also have kernel objects, since modules have kernels. Hence, the kernel of a G-representation homomorphism between V and W is G-invariant.

Definition 53.1.3: Affording Representation

Let V be a $k[G]$-module. Then given the previous discussion, we say that V *affords* the representation φ of G.

Given this new perspective, we can also characterize sub-actions. If we have a $k[G]$-module V, then a $k[G]$-submodule $W \subseteq V$ would have to be a k-submodule, and hence a subspace, but it also has to be closed under the action of g on W, i.e. $g \cdot W \subseteq W$. Hence, any $k[G]$-submodule is a G-stable subspace of V. Conversely, if $W \subseteq V$ is G-stable, then it is closed under the action of G and is a subspace, and hence a $k[G]$-submodule. Hence

$$\left\{ W \subseteq V \text{ a } k[G]\text{-submodule} \right\} \rightleftarrows \left\{ W \subseteq V \text{ a } G\text{-stable subspace} \right\}$$

Next, we should know when two representations are equivalent. Recall that when studying a linear transformation T on V to itself, a basis for V can be found that gives a "canonical form" to the matrix representation of T. Changing basis for V kept V the same, but changed the matrix representation of T up to similarity (i.e. changed the isomorphism from $\mathrm{GL}(V)$ to $\mathrm{GL}_n(k)$). The following is the analogous term:

Definition 53.1.4: Equivalent Representation

Let φ and ψ be two representations of G over k. Then we say these two represetnations are *equivalent* (or *similar*) if the $k[G]$-module affording them are isomorphic as modules. If two representations are not equivalent, they are called *inequivalent* (or *not similar*).

When the field is known[a], if V and W are equivalent (i.e. isomorphic as $k[G]$-modules), then we write $V \cong_G W$.

[a] In most cases, the field will be $\mathbb{C}$

Note that two different representations can mean two different vector-spaces over k. If $\varphi : G \to \mathrm{GL}(V)$ and $\psi : G \to \mathrm{GL}(W)$ are equivalent representations, it would make sense if there is a relation between V and W. If $T : V \to W$ is the $k[G]$-module isomorphism between them, It is a k-module isomorphism, and hence $V \cong W$ as vector spaces, implying $\dim(V) = \dim(W)$. Furthermore, by definition of T, $T(g \cdot v) = g \cdot T(v)$. By definition of the action, we have that $T(\varphi(g)(v)) = \psi(g)(T(v))$, i.e.

$$T \circ \varphi(g) = \psi(g) \circ T \quad \Leftrightarrow \quad T \circ \varphi(g) \circ T^{-1} = \psi(g) \qquad \forall g \in G$$

That is, T is the *simultaneous change of basis* for all $\varphi(g)$, $g \in G$. In terms of matrices, there must exist a fixed invertible matrix P such that for all $g \in G$,

$$P\varphi(g)P^{-1} = \psi(g)$$

The function T (or matrix P) are said to *intertwine* φ and ψ (it gives the rules on how to relate φ and ψ).

Example 53.1.5: Representations

1. Let G be any finite group, V any 1 dimensional vector-space over k. Define the $k[G]$-module structure on V by
$$g \cdot v = v$$
for all $g \in G$, $v \in V$. This called the *trivial representation* of G. This module affords the representation $\varphi : G \to \mathrm{GL}(V)$ by $\varphi(g) = I$ (the corresponding matrix representation from G to $\mathrm{GL}_1(k)$ sends $g \mapsto I$).

2. Let G be any finite group and k any field. Let $V = k[G]$ and consider it as a $k[G]$-module over itself. Then $\dim_k(V) = |G| = n$, with the basis being the elements of G. Then we see that each $g \in G$ permute the basis elements:
$$g \cdot g_i = gg_i = g_j \in G$$
Thus, the matrix representation for the action by the element g is an $n \times n$ matrix with 1 in the ij component if $g \cdot g_j = g_i$ (hence n 1's) and zero everywhere else. This representation of g is called the *regular representation* of G. Note how the underlying field did not matter: the coefficients in the matrices can only ever by 1 or 0, and we would simply say "Let φ be the regular representation of G" without specifying which field the group-ring is.

3. Let $G = S_n$ ($n \in \mathbb{N}_{>0}$) and k be any field. Then let V be a vector-space over k of dimension n, $(e_1, e_2, ..., e_n)$ a basis for V, and define the action:
$$\sigma \cdot e_i = e_{\sigma(i)}$$
that is, σ permute the basis of V. Through this, we see that we afford a faithful representation $\varphi : S_n \hookrightarrow \mathrm{GL}(V)$. Furthermore, since any finite group is a subgroup of S_n for an appropriate n, we see that a group of order n we can define $\varphi : G \to S_n \to \mathrm{GL}(V)$, giving another perspective on how to embed any finite group into a matrix group. Notice too how we made a $k[G]$-module given the action of a $k[S_n]$-module. This is called the *permutation representation* of G.

   Note that this means that *any* finite groups acts on a vector space, and by using this construction we see that any finite group G of size n can be embedded into $\mathrm{GL}_n(k)$ showing how much structure the matrix groups embody.

4. Generlizing the last result, if $\psi : H \to \mathrm{GL}(V)$ is any representation and $\varphi : G \to H$ is a group homomorphism, then $\psi \circ \varphi$ is a representation of G on V.

5. Recall that in section 20.1.3 we defined a *group character* to be a homomorphism from G to $L^\times$. This is in fact a 1-dimensional representation of G, since $\mathrm{GL}_1(L) = L^\times$. For a concrete

example, let $G = C_n$ be the cyclic group of order n and $\zeta_n \in \mathbb{C}^\times$ a *primitive* nth root of unity, and let a be a generator of G. Then the map:

$$\chi : G \to \mathbb{C}^\times \qquad a^i \mapsto \zeta_n^i$$

is a faithful representation of G (primitivity is what makes it faithful).

6. Let $G = D_4$, the dihedral group of order 8 (we write $|D_n| = 2n$). We already have the regular representation of dimension 8 and permutation representation of dimension 8, but can we do better? In fact we can. In order to see this, let's first write out D_4 in terms of generators and relations:

$$D_4 = \langle r, s \mid r^4 = s^2 = 1,\ rs = sr^{-1} \rangle$$

Let $k = \mathbb{R}$ and consider $\mathrm{GL}_2(\mathbb{R})$. Matrices satisfying these relations determine a representation of degree 2. It is faithful precisely when their images generate a group of order 8, which one checks directly for the matrices below. This can be laborious, but with some work we can find:

$$r \mapsto \begin{pmatrix} \cos(2\pi/4) & -\sin(2\pi/4) \\ \sin(2\pi/4) & \cos(2\pi/4) \end{pmatrix} \qquad s \mapsto \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix}$$

Let $G = Q_8$. We will show how different fiels can produce different represetnations. First, recall the following two generator and relation set for Q_8:

$$Q_8 = \langle i, j \mid i^4 = j^4 = 1,\ i^2 = j^2,\ i^{-1}ji = j^{-1} \rangle$$

$$Q_8 = \langle i, j, k \mid i^2 = j^2 = k^2 = ijk \rangle$$

Working over $\mathbb{C}$ in $\mathrm{GL}_2(\mathbb{C})$, we can use the first representation an find:

$$i \mapsto \begin{pmatrix} \sqrt{-1} & 0 \\ 0 & -\sqrt{-1} \end{pmatrix} \qquad j \mapsto \begin{pmatrix} 0 & -1 \\ 1 & 0 \end{pmatrix}$$

can you find one if $k = \mathbb{R}$ and $\mathrm{GL}_4(\mathbb{R})$? (Hint: think of the quaternions $\mathbb{H}$)

7. Let $H \trianglelefteq G$ which is further an *elementary* abelian p-group for some prime p (that is, abelian of exponent p). Without exponent p the scalar action below is not well defined. Then $V = H$ is a vector-space over $\mathbb{F}_p$ with the action of $a \cdot v = v^a$. Then define the action of G on H by conjugation: $g \cdot h = ghg^{-1}$. This action is well-defined since $gh^a g^{-1} = (ghg^{-1})^a$. The kernel of this action is $C_G(H)$. Such an action is called a *module representation*.

8. Let V be the $k[S_n]$-module which affords the permutation representation. We will find 2 S_n-invariant subspaces: Let $N \subseteq V$ be the subspace defined by:

$$N = \{\alpha_1 e_1 + \cdots + \alpha_n e_n \mid \alpha_1 = \cdots = \alpha_n\}$$

Then this a subspace that is also S_n-invariant. As practice, show that if $n \geq 3$, then N is the unique 1-dimension subspace which is S_n-stable. This submodule is called the *trace* submodule of V.

Another natural S_n-stable subspace is the following: take $I \subseteq V$ such that

$$I = \{\alpha_1 e_1 + \cdots + \alpha_n e_n \mid \alpha_1 + \cdots + \alpha_n = 0\}$$

notice that $I = \ker(\varphi)$ where $\varphi : V \to \mathbb{C}$, $\varphi(\alpha_1 e_1 \alpha_2 e_2 \cdots \alpha_n e_n) = \sum_i \alpha_i$, and so I is $n-1$ dimensional. Since φ is called the *augmentation map* (was in section 7.3 of D&F), I is called the *augmentation module*.

9. If V is a regular representation of G so that $V = k[G]$, then V has the same two natural G-invariant subspaces:

$$N = \{\alpha_1 e_1 + \cdots + \alpha_n e_n \mid \alpha_1 = \cdots = \alpha_n\}$$
$$I = \{\alpha_1 e_1 + \cdots + \alpha_n e_n \mid \alpha_1 + \cdots + \alpha_n = 0\}$$

these are both in fact *two-sided ideals*, even if G is not abelian. Since they appear naturally, they are usually given a name: N is called the *trace ideal* and I is called the *augment ideal*.

Corollary 53.1.6: Schur's Lemma For Representations

Let V, W be irreducible G-representations (over $\mathbb{C}$) with represetnations ρ_V and ρ_W. Then:

1. If $V \ncong_G W$, then there does not exist a non-trivial G-linear map between V and W
2. Let's say $V = W$, are finite dimensional vecor-spaces with $\rho_V = \rho_W$, then the only non-trivial G-linear maps from V to W are scalars: $\lambda I : V \to W$, $\lambda I(v) = \lambda v$.

***Proof*:**

1. Since V and W are irreducible G-representations, they are simple $k[G]$-modules, and hence we apply the original Schur's lemma.
2. Let $V = W$ of the same dimension with matching actions $\rho_V = \rho_W$, and let $f : V \to W$. Since f is a linear transformation over $\mathbb{C}$, there always exists an eigenvalue, say λ so that $f(x) = \lambda x$. Consider:
$$\varphi = f - \lambda I$$
so that $\varphi(x) = 0$. Since the difference of two G-linear maps is G-linear, then $\ker(\varphi)$ is a G-invariant subspace. But V is irreducible, and $\ker(\varphi) \neq 0$ since it contains the nonzero eigenvector x, and hence must be all of V, and so $\varphi(V) = 0$, telling us that $0 = f(x) - \lambda I(x)$, i.e.
$$f(x) = \lambda x$$
completing the proof.

Recall that if V is a simple R-module over a semi-simple ring R, then $\mathrm{End}_R(V) \cong_{\mathbf{Ring}} D^{\mathrm{op}}$ is a division ring, and that any finite-dimensional division $\mathbb{C}$-algebra is in fact equal to $\mathbb{C}$. This lemma now gives an explicit isomorphism between these two!

Since we are working over a vector-space, it is often convenient when possible to bring in an inner product that give further relations between our objects. The key the following inner product is that it is invariant on G-actions:

Definition 53.1.7: G-Invariant Inner Product

Let $k = \mathbb{R}$ or $\mathbb{C}$ and let V be a finite-dimensional $k[G]$-module. (An inner product presupposes an ordering or a conjugation on the scalars, so this definition is not available over a general field.) Then a *G-invariant inner product* is an inner product $\langle \cdot, \cdot \rangle$ along with the additional property of:

$$\langle g \cdot v, g \cdot w \rangle = \langle v, w \rangle$$

Instead of giving examples of this inner product, we will soon show that when G is finite and $|G|$ is invertible in k, any inner product on V can be averaged into a G-invariant one (hint: can you see how to use the "averaging" idea in Machke's Theorem to do so? The answer is given in corollary 53.1.12, page 1610).

Now, the study of linear representations in themseves can difficult; we are essentially studying all possible $\mathbb{C}[G]$-module. We would rather be able to decompose them into smaller pieces, and show that any represetnation of G is some how build form these simpler pieces (similarly to our exploration of semi-simple modules). The rest of this chapter is dedicated to seeing if we can bring Artin-Wedderburn's theorem and all of it's consequences to understanding linear representations of finite groups:

Definition 53.1.8: Decomposing Representations

A representation is called *simple, reducible, indecomposable, decomposable*, or *semisimple* if the $k[G]$-module affording it has the corresponding property

Recall that indecomposable in general does not imply irreducible. The example under definition 51.1.1 could is in fact a representation of $\mathbb{Z}$ defined by:

$$n \mapsto \begin{pmatrix} 1 & n \\ 0 & 1 \end{pmatrix}$$

which is reducible (since it is in block upper-triangular form) but indecomposable: $\text{span}(e_1)$ is the only invariant line, so no basis puts it in block-diagonal form. Notice that any 1-dimensional representation is automatically an irreducible, since any $k[G]$-submodule of k would be a k-subspace of k, but k is already irreducible as vector-space over k.

To get an idea of how $k[G]$-submodules interact with the definitions above, let V be an n-dimensional representation of G affording the represetnation ρ, and $W \subseteq V$ an m-dimensional $k[G]$-submodule (i.e. m-dimensional G-invariant subspace) with $0 \neq m \neq n$. Then choosing a basis $\{w_1, w_2, ..., w_m\}$ for W, we can extend it to a basis $\{w_1, w_2, ..., w_m, v_{m+1}, ..., v_n\}$. Since W is G-invariant, for any $w \in W$, $\rho(g)(w) \in W$. In matrix representation, $\varphi(g)(w^i) = \rho^i_j w^j$, and the coefficients of $v^{m+1}, ..., v_n$ are zero. Hence we get the matrix representation of $\rho(g)$ as:

$$\begin{pmatrix} \alpha(g) & \beta(g) \\ 0 & \gamma(g) \end{pmatrix}$$

Notice too that:

$$\begin{aligned}\begin{pmatrix}\alpha(gh) & \beta(gh)\\ 0 & \gamma(gh)\end{pmatrix} &= \rho(gh)\\ &= \rho(g)\rho(h)\\ &= \begin{pmatrix}\alpha(g) & \beta(g)\\ 0 & \gamma(g)\end{pmatrix}\begin{pmatrix}\alpha(h) & \beta(h)\\ 0 & \gamma(h)\end{pmatrix}\\ &= \begin{pmatrix}\alpha(g)\alpha(h) & \alpha(g)\beta(h)+\beta(g)\gamma(h)\\ 0 & \gamma(g)\gamma(h)\end{pmatrix}\end{aligned}$$

which shows that α and γ are themselves representations. The converse is immediate and needs no computation: if every matrix is block upper triangular in a given basis, the span of the first m basis vectors is G-invariant. As an example of this, let V be the permutation representation of S_3. Then the set of all vectors that are invariant to the action of $G = S_3$ is $V^G = \text{span}(e_1 + e_2 + e_3)$. Let $W = \text{span}(e_1 + e_2 + e_3)$. Since $G \curvearrowright W$ is of the form $g \cdot w = w$, we see that W is in fact the *trivial representation*. Since V is semi-simple, we have that $V = V^G \oplus U$ for some G-stable complement U. Making some new basis for V, say $(e_1 + e_2 + e_3, e_2, e_3)$, we see that $S_3 \curvearrowright V$ will have matrix representations that are of the above form:

$$\begin{pmatrix}1 & * & *\\ 0 & * & *\\ 0 & * & *\end{pmatrix}$$

If V were irreducible, then no such basis would exist. If $V = U \oplus W$, then we would get a block diagonal form. It turns out that all representations of *finite* groups over a field of characteristic zero, or of characteristic not dividing $|G|$, are block-diagonal, i.e. are semisimple. (Finiteness is essential: the representation of $\mathbb{Z}$ displayed above is over $\mathbb{C}$ and is not semisimple.)

Theorem 53.1.9: Maschke's Theorem

Let G be a finite group and let k be a field whose characteristic does not divide $|G|$ or $\text{char}(k) = 0$. Then if V is a $k[G]$-module, it is a semi-simple $k[G]$-module.

The condition that $\text{char}(k) \nmid |G|$ is equivalent to $|G|$ being invertible in k, which is what the proof below divides by. Note how this theorem is "surprising": a finite group G certainly cannot be reduced to a direct sum of simple groups, only built from them as iterated extensions, and (as of writing this book) we do not know how to construct all finite groups via such extensions. Hence, having a very computable decomposition into irreducible representations provides a very potent tool to analyze the structure of finite groups.

***Proof*:**
We will use lemma 51.1.7[3] to show that for any $U \subseteq V$, there exists a complement W such that $V = U \oplus W$.

We will find a projection onto U: $\pi : V \to U$. Thus, we need to show it has the following properties:

1. $\pi(u) = u$ for all $u \in U$
2. $\pi(\pi(v)) = \pi(v)$ for all $v \in V$[a]

To see why this is sufficient, let $\pi\colon V \to U$ be a $k[G]$-module homomorphism with these properties. Let $W = \ker(\pi)$. Then $W \subseteq V$ is a submodule, and W is a complement of U. First, let $v \in U \cap W$. Then since $v \in U$, $\pi(v) = v$ and since $v \in W$, $\pi(v) = 0$, hence $v = 0$, meaning $U \cap W = 0$. Next, let $v \in V$ be an arbitrary element, and write $v = \pi(v) + (v - \pi(v))$. By definition, $\pi(v) \in U$, and by the 2nd property:

$$\pi(v - \pi(v)) = \pi(v) - \pi(\pi(v)) = \pi(v) - \pi(v) = 0$$

and hence $v - \pi(v) \in W$. Hence $v \in U + W$, and so $V = U + W$, hence $V \cong U \oplus W$. Hence, it suffices to find an $k[G]$-module projection π.

Let $U \subseteq V$ be a $k[G]$-submodule. Then it is already a k-subspace, and so it has a vector-space direct sum complement $W_0 \subseteq V$ (take a basis β for U, extend it to a basis $\mathcal{B}$ for V, then take $\mathcal{B} - \beta$) Thus, $V = U \oplus W_0$ as a vector-space. However, W_0 need not be G-stable (i.e. a $k[G]$-submodule), for example $G = C_2$ on $\mathbb{R}^2$ with the reflection across $y = x$ which has the G-subspace $y = x$ and complement spanned by $(1, 0)$, which is not G-invariant. Let $\pi_0\colon V \to U$ be the vector-space projection map:

$$\pi_0(u + w_0) = u$$

To find a G-stable complement, we average π_0 over G:

$$g\pi_0 g^{-1} : V \to U \qquad g\pi_0 g^{-1}(v) = g \cdot \pi_0(g^{-1} \cdot v)$$

Since π_0 maps V to U, and U is a $k[G]$-submodule, U is stable under this G-action, hence $g\pi_0 g^{-1}$ is well-defined. Note that both g and g^{-1} act as k-linear transformations, so $g\pi_0 g^{-1}$ is a k-linear transformation. Furthermore, if $u \in U$, then so must $g^{-1}u$, so by definition of π_0, $\pi_0(g^{-1}u) = g^{-1}u$. Thus, for all $g \in G$:

$$g\pi_0 g^{-1}(u) = u$$

hence, $g\pi_0 g^{-1}$ is also a vector-space projection of V onto U!

Let $n = |G|$, and viewing n as an element of k ($n = 1 + \cdots + 1$), since $\mathrm{char}(k) \nmid |G|$ we have $n \neq 0$, i.e. $n \in k^\times$. Thus, n has an inverse in k, meaning we can define:

$$\pi = \frac{1}{n} \sum_{g \in G} g\pi_0 g^{-1}$$

We can immediately deduce that π has the following properties:

1. By definition, π is still k-linear from V to U.
2. Restricting π to U would restrict each summand in the definition of π, and so as we have pointed out earlier each summand would be the identity map. Hence, we get $1/n$ times n copies of u, meaning $\pi|_U = \mathrm{id}$
3. π is well-defined, hence $\pi(v) \in U$, and since π restricts to the identity on U we get $\pi(\pi(v)) = \pi(v)$, i.e. $\pi^2 = \pi$

It remains to show that π is in fact a $k[G]$-module homomorphism (i.e. is $k[G]$ linear). It suffices to show that for any $h \in G$, $\pi(hv) = h\pi(v)$. This is simply a computation:

$$\begin{aligned}
\pi(hv) &= \frac{1}{n}\sum_{g\in G} g\pi_0(g^{-1}hv) \\
&= \frac{1}{n}\sum_{g\in G} h(h^{-1}g)\pi_0(g^{-1}hv) \\
&\overset{!}{=} \frac{1}{n}\sum_{\substack{x=h^{-1}g \\ g\in G}} h(x\pi_0(x^{-1}v)) \\
&= h\frac{1}{n}\sum_{\substack{x=h^{-1}g \\ g\in G}} (x\pi_0(x^{-1}v)) \\
&= h\pi(v)
\end{aligned}$$

where $\overset{!}{=}$ is the reindexing $x = h^{-1}g$, valid because left translation by h^{-1} is a bijection of G, so as g runs over G so does x. Hence, π is indeed a $k[G]$-homomorphism, and so it is a projection map, completing the proof.

[a] In fact, this is implied by 1

Thus, if we take any representation V over k of G, and consider the $k[G]$-module, then we know through $k[G]$ and G being finite and k a field (so V is a vector-space) that there are only *finitely many* simple $k[G]$-modules (i.e. finitely many irreducible representations of G), meaning we only have a finite number of "building blocks" from which we can build) any representation for G! Even better, the way we put together irreducible representation is through direct sums the simplest of ways of putting together algebraic objects! Then through the Artin-Wedderburn decomposition of $k[G]$ we obtain the list of irreducibles, and Maschke's theorem decomposes any representation V of G into them, giving us a simple finite list of irreducible representations per finite group! Note that if $p = \mathrm{ch}(k) > 0$ and $p \big| |G|$, then $k[G]$ is *not* semisimple, or if G is infinite, it need not be semi-simple

Example 53.1.10: Non-Semisimple Group Rings

For the infinite case, the action of $\mathbb{Z}$ on k^2 presented above is a non-semisimple $k[\mathbb{Z}]$-module. For finite groups, cyclic groups already exhibit both behaviors. Let $G = C_n$ be cyclic of order n, generated by g.

1. The k-algebra map $k[a] \to k[C_n]$, $a \mapsto g$, is surjective because g generates C_n, and its kernel contains $a^n - 1$. Both $k[a]/(a^n - 1)$ and $k[C_n]$ have dimension n over k, with bases $1, a, \ldots, a^{n-1}$ and $1, g, \ldots, g^{n-1}$, so the induced map $k[a]/(a^n - 1) \to k[C_n]$ is an isomorphism.
2. Suppose $\mathrm{char}(k) \nmid n$. The derivative na^{n-1} of $a^n - 1$ is nonzero and shares no root with $a^n - 1$, so $a^n - 1 = f_1 \cdots f_r$ with $f_1, \ldots, f_r$ distinct monic irreducible polynomials, which are pairwise coprime in the principal ideal domain $k[a]$. The Chinese Remainder Theorem theorem 9.6.11 gives
$$k[C_n] \cong k[a]/(f_1) \times \cdots \times k[a]/(f_r)$$
a product of fields. A field is M_1 of a division ring, so this is an Artin-Wedderburn decomposition of $k[C_n]$, and $k[C_n]$ is semisimple by theorem 51.2.16.

3. Suppose $\text{char}(k) = p$. In $k[C_p]$ the element $g - 1$ is nonzero, while $(g-1)^p = g^p - 1 = 0$ because the binomial coefficients $\binom{p}{i}$ vanish in k for $0 < i < p$. A product of fields has no nonzero nilpotent elements, so $k[C_p]$ is not a product of fields. Since $k[C_p]$ is commutative, each factor $M_{n_i}(D_i)$ of an Artin-Wedderburn decomposition of it would be commutative, which forces $n_i = 1$ (as $E_{12}E_{21} \neq E_{21}E_{12}$ when $n_i \geq 2$) and D_i a field. Hence $k[C_p]$ is not semisimple, by theorem 51.2.16.

If $k = \mathbb{C}$, then Maschke's Theorem always applies, and we can further use Artin Wedderburn over closed k-algebras (corollary 51.2.20) to deduce a relatively simple structure! Hence, from now on, we will always have $k = \mathbb{C}$, meaning all of our representations of finite groups will be over the complex vector-field of finite dimension.

Corollary 53.1.11: Matrix Representation Consequences

Let G be finite, let V be finite dimensional, and let $\rho : G \to \text{GL}(V)$ be a representation over a field k where $\text{char}(k) \nmid |G|$. Then there exists a basis for V such that for all $g \in G$, the matrix $\rho(g)$ is of block-diagonal form:

$$\begin{pmatrix} \rho_1(g) & & & \\ & \rho_2(g) & & \\ & & \ddots & \\ & & & \rho_m \end{pmatrix}$$

where ρ_i is an irreducible representation of G, $1 \leq i \leq m$.

***Proof*:**
Let V be the $k[G]$-module representing ρ. By Maschke's Theorem, we may write $V = U_1 \oplus \cdots \oplus U_m$. where U_i is simple $k[G]$-module. For each U_i, choose a basis β_i. Let $\beta = \bigcup_i^m \beta_i$. then each matrix representation of $\rho(g)$ is of the form in the corollary, with $\rho(g)|_{U_i} = \rho_i(g)$, completing the proof.

Corollary 53.1.12: Defining G-Invariant Inner Product

Let $k = \mathbb{R}$ or $\mathbb{C}$, let G be finite, let V be a finite-dimensional $k[G]$-module, and let $\langle \cdot, \cdot \rangle$ be any inner product on V. Then this inner product induces a G-invariant inner product

***Proof*:**
If $\langle \cdot, \cdot \rangle$ is an inner product, then:

$$\langle v, w \rangle_G = \frac{1}{|G|} \sum_{g \in G} \langle gv, gw \rangle$$

is a well-defined inner product (as can be checked), and for any $h \in G$

$$\begin{aligned}\langle hv, hw\rangle_G &= \frac{1}{|G|}\sum_{g\in G}\langle ghv, ghw\rangle \\ &= \frac{1}{|G|}\sum_{x=gh\in G}\langle xv, xw\rangle \\ &= \langle v, w\rangle_G\end{aligned}$$

In other words, there is always an inner product on our space in which the group actions keeps all elements of the same length and the same angle between them, showing how we can interpret a group as somehow rotating and reflecting an object in a vector-space. Now that we know any represetnation of G is composed in some way by finitely many irreducible representations, it would be useful to be able to quickly deduce the Artin-Wedderburn decomposition of $\mathbb{C}[G]$:

Proposition 53.1.13: Properties Of Representations

Let $k = \mathbb{C}$ and G be finite. Let $S_1, S_2, ..., S_r$ be the irreducible G-representations (up to isomorphism). Then:

1. the number of irreducible G-representations is equal to the number of conjugacy classes in G
2. For every finite-dimensional representation V of G,

   $$V \cong S_1^{\oplus \ell_1} \oplus \cdots \oplus S_r^{\oplus \ell_r}$$

   where the $\ell_i \geq 0$ are uniquely determined, namely $\ell_i = \dim_{\mathbb{C}} \operatorname{Hom}_{\mathbb{C}[G]}(S_i, V)$. (An irreducible need not occur at all: the trivial representation of S_3 has $\ell_2 = \ell_3 = 0$.)
3. $\mathbb{C}[G] \cong \bigoplus_{i=1}^{r} \left(S_i^{\oplus \dim_k S_i}\right)$ as regular representation
4. $|G| = \sum(\dim_k S_i)^2$

***Proof*:**

part (3) and (4) come from corollary 51.2.20.

For part (1), we first use Artin-Wedderburn to conclude that $Z(\mathbb{C}[G]) = \prod_i^r \mathbb{C}$, so $\dim_{\mathbb{C}}(Z(\mathbb{C}[G])) = r$, so the dimension of the center is equal to the number of irreducible G-representations.

Now, let $\mathcal{K}_1, ..., \mathcal{K}_s$ represent the conjugacy classes (recall they partition G). Define:

$$\sigma_i = \sum_{g\in\mathcal{K}_i} g$$

Note that any pair of elements σ_i and σ_j have no common terms since the conjugacy classes partition G. Furthermore, by definition, for any $g \in G$, $g\sigma_i g^{-1} = \sigma_i$, and so $\sigma_i \in Z(\mathbb{C}[G])$. If the σ_i's form a basis for $Z(\mathbb{C}[G])$, then we would have $s = r$. As a $\mathbb{C}$-vector-space, they are already linearly independent since the group elements from a basis, so it suffices to show they

span. If $\sum_{g\in G}\lambda_g g \in Z(\mathbb{C}[G])$. Then by definition for all $h \in G$,

$$\begin{aligned}
&\Leftrightarrow\ h\left(\sum_{g\in G}\lambda_g g\right) = \left(\sum_{g\in G}\lambda_g g\right)h \\
&\Leftrightarrow\ \left(\sum_{g\in G}\lambda_g g\right) = h^{-1}\left(\sum_{g\in G}\lambda_g g\right)h \\
&\Leftrightarrow\ \sum_{g\in G}\lambda_g g = \left(\sum_{g\in G}\lambda_g (h^{-1}gh)\right) \\
&\overset{!}{\Leftrightarrow}\ \sum_{g\in G}\lambda_g g = \sum_{g\in G}\lambda_{hgh^{-1}} g \\
&\Leftrightarrow \lambda_{hgh^{-1}} = \lambda_g \qquad \forall g \in G
\end{aligned}$$

since h arbitrary, we see that the coefficients of elements in the same conjugacy class remain with an element that's in that conjugacy class. Equivalently, the function $G \to \mathbb{C}$, $g \mapsto \lambda_g$ is constant on conjugacy classes. Thus:

$$Z(\mathbb{C}[G]) = \text{span}\left\{\sum_{g\in G} f([g])g\right\}$$

where f is a function from the conjugacy classes of G to $\mathbb{C}$. Hence $s = r$.

for (2), Since $\mathbb{C}[G]$ is a semi-simple ring, V is a semi-simple $\mathbb{C}[G]$-module, giving us existence of the decomposition by AW. For uniqueness, first note that:

$$\text{End}_{\mathbb{C}[G]}(S_i) = \mathbb{C}$$

since $\mathbb{C}$ is the only [finite-dimensional?] division $\mathbb{C}$-algebra. Then, we get by Schur's lemma:

$$\text{Hom}_{\mathbb{C}[G]}(S_i, V) \overset{\text{Schur}}{\cong} \text{Hom}_{\mathbb{C}[G]}(S_i, S_i)^{\oplus l_i} \cong \mathbb{C}^{l_i}$$

Corollary 53.1.14: Abelian Groups And Degree 1 Decomposition

1. If A is a *finite* abelian group, then every irreducible complex representation of A is 1-dimensional (i.e. a homomorphism from A to $\mathbb{C}^\times$), and A has $|A|$ inequivalent irreducible complex representations.
2. The number of inequivalent (irreducible) 1-dimensional complex representations of any finite group G is equal to $|G/G'|$

***Proof*:**

1. Since A is abelian, so is $\mathbb{C}[A]$. By the Artin-Wedderburn decomposition, it must be a product of matrices, which since $\mathbb{C}[A]$ abelian is so must each matrix ring, which is only

true if and only if $n_i = 1$. Then, by corollary 51.2.20, $\mathbb{C}[A]$ is a product of fields. It follows that any irreducible representation (i.e. simple $\mathbb{C}[A]$-module) is 1-dimensional. Conversely, if A were not abelian, $\mathbb{C}[A]$ cannot be a product of fields, hence one of the dimensions of the matrix rings *must* be greater than 1

2. Let G be an arbitrary group. We want to show that there is a bijective correspondence between the 1-dimension representations of G and the 1-dimensional representations of G/G'. $\rho : G/G' \to \mathbb{C}^\times$ is a 1-dimensional representations of G/G', then we have the natural map $G \to G/G'$, which shows that each 1-dimensional representations of G/G' is also a 1-dimensional representations of G. Convexly, if f $\rho : G \to \mathbb{C}^\times$ is a 1-dimensional representations of G, then by the universal property, this factors through:

$$\begin{array}{ccc} G/G' & \longrightarrow & \mathbb{C}^\times \\ \uparrow & \nearrow & \\ G & & \end{array}$$

showing that any 1-dimensional representation of G is associated to a 1-dimensional representations of G/G', showing there cannot be more 1-dimensional representations of G than there are of G/G', completing the proof.

A more general technique can be adopted from this proof: If $H \trianglelefteq G$ and V is an irreducible representation of G/H, then V is an irreducible representation of G.

Example 53.1.15: Decomposition Of Modules

1. DnF p. 847, and a bit about $\dim(V) = 1$ example right under definition

Finally, for those who read chapter 50, the following results are a glimpse at how representation theory is a "generalization" of number theory. First, if $H \leqslant G$ is a subgroup and (ρ, V) is an irreducible representation, $\rho|_H$ breaks up into the direct sum of representations, not necessarily of the same size or multiplicity. This is similar to how for a prime $\mathfrak{p} \subseteq F$ it may split to multiple primes with varying inertia degree and ramification numbers in a finite separable extension L/F. If L/F is furthermore normal (and hence Galois) then all the inertia degree's and ramification numbers match. In a similar vein:

Theorem 53.1.16: Clifford's Theorem

G be a group, $N \trianglelefteq G$ a normal subgroup, K a field, $\pi : G \to \mathrm{GL}_n(K)$ be an irreducible representation. Then the restriction $\pi|_N$ breaks up into a direct sum of irreducible representations of N of equal dimensions (i.e. it is semisimple and each representation is of the same dimension). These irreducible representations of N lie in one orbit for the action of G by conjugation on the equivalence classes of irreducible representations of N (i.e. they are isotypic components with the same multiplicity).

***Proof*:**
Write V for the space of π and let $W \subseteq V$ be an irreducible N-subrepresentation.

Step 1: $V|_N$ is semisimple. For $g \in G$ the subspace gW is N-stable, because N is normal: for $n \in N$ one has $n(gW) = g(g^{-1}ng)W = gW$, using $g^{-1}ng \in N$. It is irreducible over N, since $w \mapsto gw$ carries N-subrepresentations of W bijectively onto N-subrepresentations of gW, and the representation it affords is $n \mapsto \pi_W(g^{-1}ng)$, the conjugate π_W^g. In particular all the gW have the same dimension as W. Now $\sum_{g\in G} gW$ is stable under N by the above and under G because $h\sum_g gW = \sum_g (hg)W$, so it is a non-zero subrepresentation of the irreducible V and therefore equals V. A sum of irreducible subrepresentations is semisimple, so $V|_N$ is semisimple and all its irreducible constituents have $\dim W$.

Step 2: one orbit, with equal multiplicities. For an irreducible representation U of N let $V_U \subseteq V$ be its isotypic component in $V|_N$. If $g \in G$ then $v \mapsto gv$ carries V_U onto V_{U^g}, where $U^g(n) = U(g^{-1}ng)$: it is a bijection by Step 1 applied to each constituent, and it is an isomorphism of vector spaces, so V_U and V_{U^g} have equal dimension and hence U and U^g occur with equal multiplicity. Consequently G permutes the isotypic components, and the sum of those lying in a single G-orbit of isomorphism classes is a G-subrepresentation. It is non-zero, so it is all of V: the classes occurring form exactly one orbit, and the multiplicities agree across it, completing the proof.

Exercise 53.1.1

1. If χ_1 and χ_2 are both 1 dimensional representations, then $\chi_1 \cong \chi_2 \Leftrightarrow \chi_1 = \chi_2$. Use the property of equivalent representations to see this.
2. Let V be a non-trivial irreducible G-representation (i.e. not $\chi(g) = 1$ for all $g \in G$). Show that there are $\dim_{\mathbb{C}}(V^G) = 0$
3. By Caley's Theorem, all finite groups are linear. Do there exists infinite non-linear groups? (Hard: Do there exists finitely generated non-linear groups?)
4. Show that if ρ is irreducible and $N \trianglelefteq G$ is normal, and N fixes some *nonzero* vector $v \in V$, then N acts trivially on all of V.

53.2 Character Theory

We know now we can decompose a G-representation V into the direct sum of r different types of irreducible G-modules. How do we now proceed to find these? These can be quite unwieldy: if we have a 10 or 100-dimensional representation of a group G, then we have a matrix with 100 and $10'000$ entries! We would then have to multiply these and figure out what relations they have between each other, quite a hassle! Furthermore, how do we do this in such way that is independent of equivalent representations? A convenient basis might be nice, but to find a nice basis for every $\rho(g) \in \rho(G)$, we'd have to find a basis that can *simultaneously* diagonalize every element in $\rho(G)$! If there was some invariant we can find on a representation that we can use to keep track of the decomposition information between representations that is invariant of representation, that would be useful to this endevaour. The following does exactly this (Move the discussion of trace here to build-up to it? Give some of D&F examples to demonstrate it does get quite ugly sometimes?)

Definition 53.2.1: Class Function and Character

Let G be finite and let V be a finite-dimensional representation of G over an arbitrary field F. Then

1. A function $f : G \to F$ that is constant on conjugacy classes is called a *class function* of G
2. If φ is a representation of G afforded by the $F[G]$-module V, then a function:

$$\chi_V : G \to F \qquad g \mapsto \text{tr}(g : V \to V) = \text{tr}(\varphi(g))$$

is called the *character* of φ, where $\text{tr}(\varphi(g))$ is the trace of φ with respect to some basis for V. A character is called *irreducible* if φ is irreducible (and reducible oherwise). The *degree* of a character is the degree of any representation affording it.

For ease of reference, recall these properties of the trace:

1. $\text{tr}(A + B) = \text{tr}(A) + \text{tr}(B)$ an $\text{tr}(cA) = c\text{tr}(A)$
2. $\text{tr}(A) = \text{tr}(A^t)$
3. $\text{tr}(AB) = \text{tr}(BA)$

Note that in general, a character is *not* a homomorphism from G into the additive or multiplicative structure of k. Since $\text{tr}(AB) = \text{tr}(BA)$, $\text{tr}(ABA^{-1}) = \text{tr}(B)$, we see that the trace (and hence the character) is independent of choice of basis, and so equivalent representations have the same character, meaning the character is indeed an invariant. Furthermore, for any representation φ of G,

$$\varphi(g^{-1}xg) = \varphi(g)^{-1}\varphi(x)\varphi(g)$$

hence, we can take the trace and use the 3rd property above to show that characters an an example of *class functions*. Furthermore, since the trace is linear, we can extend the domain of a character to be the trace over any element in $\mathbb{C}[G]$. If $F = \mathbb{C}$, then the collection of class function's form a complex vector-space, since the sum of two class functions is a class function, and multiplying by a scalar $z \in \mathbb{C}$ does not change that a class function is invariant.

Example 53.2.2: Character

1. Given the trivial representation of G (i.e. any 1-dim vector space where $g \mapsto I$), then if φ is the representating affording the trivial representation, it has $\chi_\varphi(g) = 1$ for all g. This is called the *trivial character*.
2. If we have a degree 1-representation, then the character and the representation are the same. Thus for abelian group, complex representations and their characters are the same. For example, take the representation $\varphi : C_p \to \mathbb{C}^\times$, $\varphi(a^i) = \zeta_p^i$. Then:

$$\chi(a^i) = \zeta_p^i$$

3. Let $\Pi : G \to S_n$ be a permutation representation of G and φ the linear of G of degree n on V where:

$$\varphi(g)(e_i) = e_{\Pi(g)(i)}$$

with respect to the given basis, $\varphi(g)$ has 1 in the ii-entry if $\Phi(g)$ fixes i, and zero otherwise. Thus, we can say that the character χ is:

$$\chi(g) = \#\{\text{number of fixed points of } g \text{ on } \{1, 2, ..., n\}\}$$

The character of the representation attached to any permutation action is called the *permutation character*. The case where G acts on itself by left multiplication gives the regular character below.

4. Consider any regular representation of G, φ. Then the character is:

$$\chi(g) = \begin{cases} 0 & g \neq 1 \\ |G| & g = 1 \end{cases}$$

This character is called the *regular character* of G (note how this character is not a group homomorphism into k or $k^\times$)

5. Take the representation $\varphi : D_n \to \mathrm{GL}_2(\mathbb{R})$ from example 53.1.5. Then:

$$\chi(r) = 2\cos(2\pi/n) \qquad \chi(s) = 0 \qquad \chi(1) = 2$$

where the last one is since $1 \in G$ must map to the identity matrix $I \in \mathrm{GL}_2(\mathbb{R})$.

From now on, all our representation will be complex.

Lemma 53.2.3: Properties Of Character

Let $\rho_V : G \to \mathrm{GL}(V)$ be a complex representation. Then:

1. $\chi_V(1) = \dim_{\mathbb{C}}(V)$
2. $\rho_V(g)$ is diagonalizable for all $g \in G$ and $\chi(g)$ is integral over the integers: $\chi(g) \in \overline{\mathbb{Z}}^{\mathbb{C}}$
3. If $g \in G$ has order n, then $\chi_V(g)$ is a sum of $\dim(V)$ number of nth roots of 1
4. $|\chi_V(g)| \leq \chi_V(1)$ for all $g \in G$
5. $\chi_V(g^{-1}) = \overline{\chi_V(g)}$

***Proof*:**

1. We showed this in the above examples.
2. The criterion we need from linear algebra is that $A \in M_n(\mathbb{C})$ is diagonlizable if and only if the minimal polynomial has no repeated roots, which can be implied if $M^k = I$ for some k, which it certainly is in our case since every element is finite.

3. If $g^n = 1$, then $\rho_V(g)^n = 1$, so by (2)

$$\rho_V(g) \sim \begin{pmatrix} z_1 & & \\ & \ddots & \\ & & z_k \end{pmatrix}$$

where $z_i^n = 1$ for all $1 \leq i \leq k$. Furthermore, this shows that these trace values in the matrix representation are always integral over the integers, being the sum of integral elements.

4. $$|\chi_V(g)| = \left|\sum z_i\right| \leq \sum |z_i| = \dim_{\mathbb{C}}(V) = \chi_V(1)$$

5. Since $\rho_V(g^{-1}) = \rho_V(g)^{-1}$ and

$$\rho_V(g)^{-1} \sim \begin{pmatrix} z_1^{-1} & & \\ & \ddots & \\ & & z_k^{-1} \end{pmatrix}$$

$\chi_V(g^{-1}) = \sum_i z_i^{-1}$, but $\|z_i\| = 1$, so $z_i^{-1} = \overline{z_i}$, so

$$\chi_V(g^{-1}) = \sum_i z_i^{-1} = \sum_i \overline{z_i} = \overline{\chi_V(g)}$$

Now, if we have some G-representation V, it has some character χ. In the following, we will show how we can always break-down a character to be the sums of characters on the irreducible G-representations:

Proposition 53.2.4: Linearly Independent Characters

Let G be a finite group and V a semi-simple $k[G]$-module, and φ the representation that V affords. Part (1) holds over any field. Part (2) requires $k = \mathbb{C}$ (or an algebraically closed field of characteristic 0), and is *false* over a splitting field of characteristic p dividing $|G|$, where the irreducible characters are fewer than the conjugacy classes. Then:

1. The character of V is the sum of the characters of the components appearing in the direct sum decomposition.
2. The irreducible characters of G are linearly independent set in the set of class functions. Furthermore, the irreducible characters of G form a basis of the vector-space of class functions.

***Proof*:**
For the 1st point, By the Artin-Wedderburn decoposition, we have:

$$V \cong (S_1)^{n_1} \oplus \cdots \oplus (S_k)^{n_k}$$

where S_i are simple $k[G]$-modules (irreducible G-representations). If we focus on the case where

$M = S_1 \oplus S_2$, then we can choose a basis for S_1 and S_2 which will give us:

$$\varphi(g) = \begin{pmatrix} \varphi_1(g) & 0 \\ 0 & \varphi_2(g) \end{pmatrix}$$

where φ_1, φ_2 are the representations afforded by M_1 and M_2 respectively. Then if ψ_1 and ψ_2 are the characters of φ_1 and φ_2 an χ is the character of φ then we get:

$$\chi = \psi_1 + \psi_2$$

using induction get's us the result.

For the 2nd point, first notice that the class functions defined by being 1 on a conjugacy class and 0 otherise forms a basis for class functions of dimension r. It thus suffices to sho that the r irreducible characters are independent. To that end, define:

$$\widetilde{\chi_V} : \mathbb{C}[G] \to \mathbb{C} \qquad x \mapsto \text{tr}(x : V \to V)$$

Note that this map is $\mathbb{C}$-linear since $\mathbb{C}$ commutes with $\mathbb{C}[G]$, and $\widetilde{\chi_V}|_G = \chi_V$. Now, say $S_1, ..., S_r$ are simple $\mathbb{C}[G]$-modules and:

$$\sum_i^r \lambda_i \chi_{S_i} = 0 \qquad \lambda_i \in \mathbb{C}$$

Then this is equivalent to:

$$\sum_i^r \lambda_i \widetilde{\chi_{S_i}}(g) = 0 \qquad \forall g \in G$$

and since the maps are $\mathbb{C}$-linear, by linearity:

$$\sum_i^r \lambda_i \widetilde{\chi_{S_i}}(x) = 0 \qquad \forall x \in \mathbb{C}[G]$$

which by plugging into the definition we get:

$$\sum_i^r \lambda_i \text{tr}(x : S_i \to S_i) = 0 \qquad \forall x \in \mathbb{C}[G]$$

Next, by Artin Wederburn, we have the decomposition:

$$C[G] \cong M_{n_1}(\mathbb{C}) \times \cdots \times M_{n_r}(\mathbb{C})$$

where each $M_{n_i}(\mathbb{C}) \cong S_i^{\oplus n_i}$, with $S_i = \mathbb{C}^{\oplus n_i}$. Using this, take the element:

$$x_i = (0, ..., I, ..., 0)$$

where I is the identity matrix[a]. Then $x_i : S_j \to S_j$ is 0 if $i \neq j$, and the identity marix if $i = j$. Thus, the trace is:

$$\text{tr}(x_i : S_j \to S_j) = \begin{cases} 0 & i \neq j \\ n_j & i = j \end{cases}$$

and since n_j is at least 1, we must have that

$$\lambda_1 = \cdots = \lambda_r = 0$$

where we took advantage of the fact we are in characeristic 0

[a] If the field had finite characteristic, it is better to take the elementary matrix E_{11}

53.2.5 Remark We can prove this directly without using Artin-Wedderburn, which we will

Corollary 53.2.6: Detecting Isomorphic Representations Using Characters

Let $k = \mathbb{C}$ and let V_1, V_2 be representations that are semi-simple modules. (Characteristic 0 is needed: over $\overline{\mathbb{F}}_2$ the trivial $\mathbb{Z}/3$-module T and $T^{\oplus 3}$ have the same character, since $3 = 1$ in k, but are not isomorphic.)

1. Every character of G is uniquely of the form

$$\sum_i^r \lambda_i \chi_i \qquad \lambda_i \in \mathbb{Z}_{\geq 0}$$

   where χ_i are irreducible characters.

2. the representations V_1 and V_2 are isomorphic if and only if $\chi_{V_1} = \chi_{V_2}$

***Proof*:**

1. This comes straight from the fact that irreducible characters form a basis, and that any G-representation V will be some direct sum of a finite list of known simple G-modules

2. If $V_1 \cong_G V_2$, there is a single change of basis P intertwining the two actions, so that if A and B are basis matrices, $A = PBP^{-1}$. But the trace is independent of conjugation, and so the characters are the same. For the othe way around, treating a representation as a $k[G]$-module, then by Machke's theorem, we *know* the list simple $k[G]$-modules and the actions of $k[G]$ on them. Since any $k[G]$-module can be broken down into a direct summand of simlpe $k[G]$-modules, and the two chracters are the same, the list of $k[G]$-modules and their multiplicity are the same.

Thus, we have translated the problem of finding the irreducible representations of a group G to finding the irreducible characters of G! Since a character of a representation is determined by the irreducible characters, we give a way to systematize the tracking of irreducible characters:

Definition 53.2.7: Character Table

Let $\varphi : G \to \mathrm{GL}(V)$ be a representaiton of G an χ_V it's character. Then we call the *character table* a table with the rows being irreducible characters and columns being an element in the conjugacy class. Common practice is to make the first column the identity conjugacy class and the first row the trivial representation

Example 53.2.8: Character Table

Consider $G = S_3$ Then we can start creating it's character table:

	e	$(1\ 2)$	$(1\ 2\ 3)$
1	1	1	1
χ_{sgn}	1	-1	1
$\vdots$	$\vdots$	$\vdots$	$\vdots$

Since G has 3 conjugacy classes, exactly 3 irreducible characters of G. How would we go about finding it? The comning propositions work towards this.

To be able to find the missing character, and more generally find new characters for a character table, we may look to construct new character given old one, and hope that we break down those characters into a linear combination of irreducible characters. In a sense, we are finding a way to create represetnations without doing it "by hand". We will do this in two way: the first is by taking advatange of group-actions, since are relatively easy to define and their representations are matrices with 1's and 0's. Since all groups embed into a symmetric group, this can be done systematically. We then see how to work directly with known representations to create new representations.

Definition 53.2.9: Precaution Representation

Let G act on a finite set X. Define $\mathbb{C}X$ to be the set of formal sums:

$$\mathbb{C}X = \left\{ \sum_{x \in X} \lambda_x x \;\middle|\; \lambda_x \in \mathbb{C} \right\}$$

So that we get a $\mathbb{C}$-vector space with $\dim_{\mathbb{C}}(\mathbb{C}X) = |X|$. Then we can make this a G-represetnation by defining:

$$g \cdot \left(\sum \lambda_x x \right) = \sum \lambda_x (g \cdot x)$$

The 3 usual permutation representations are $G \curvearrowright G$ by left multiplication (which gives the regular representation) or conjugation, and $G \curvearrowright \{*\}$ trivially (which gives the trivial representation).

Lemma 53.2.10: Character Of Permutation Representation

Let G act on X, $G \curvearrowright X$. Then

$$\chi_{\mathbb{C}X}(g) = \#\{x \in X \mid gx = x\}$$

***Proof*:**
FIx $g \in G$. Then the set of x's is a basis for the representation. To make the computation simpler, we will find a convinient order for them. In particular, by choosing any $x_1 \in X$, we can find the orbit of the element:

$$x_1 \xrightarrow{g} x_2 \longrightarrow \cdots \longrightarrow x_k \qquad x_{k+1} \xrightarrow{g} \cdots$$

so the basis representation will look like:

$$\begin{pmatrix} 0 & & & \\ 1 & 0 & & \\ & & \ddots & \\ 0 & 1 & & \\ & & 1 & 0 \end{pmatrix}$$

so we get that the trace is 0 if the order of the orbit is greater than 1, hence:

$$\chi_{\mathbb{C}X}(g) = \#\{g\text{-orbits of size } 1\}$$

An immediate consequence of this is that we have another way of computing the character of the regular representation

$$\chi_{\mathbb{C}G}(g) = \begin{cases} |G| & g = e \\ 0 & g \neq e \end{cases}$$

which makes sense, since the $\dim_{\mathbb{C}}(\mathbb{C}G) = |G|$.

Next, we turn towards a more systematic way of constructing characters by creating them out of pervious ones, that is, given some representations V and W of a group G, we can make new representations by creating new representations from V and G:

Definition 53.2.11: Constructing Representations from smaller ones

Let V, W be G-representations. Then

1. we can make a $V \oplus W$ representation by:

$$g \cdot (v, w) = (g \cdot v, g \cdot w) \ [(\rho_V(g)v, \rho_W(g)w)]$$

2. we can make $V \otimes_{\mathbb{C}} W$ a representations by:

$$g \cdot (v \otimes w) \mapsto (gv) \otimes (gw)$$

3. we can make $\mathrm{Hom}_{\mathbb{C}}(V, W)$ a representations by:

$$g \cdot f : V \to W \quad v \mapsto g \cdot f(g^{-1} \cdot v)$$

4. we can make $V^* = \mathrm{Hom}_{\mathbb{C}}(V, \mathbb{C})$ a representaiton by:

$$g \cdot f : V \to \mathbb{C}, \ v \mapsto f(g^{-1} \cdot v)$$

Note that the last construction is the same as the 3rd if we take $\mathbb{C}$ as the trivial representation. Before we show what the character's of these new representations are, we first find a relatively simpler way of representing the hom representation of V and W:

Lemma 53.2.12: Hom-Tensor Representation Dual

Let V, W be G representations. Then:

$$\mathrm{Hom}_{\mathbb{C}}(V,W) \cong_G V^* \otimes_{\mathbb{C}} W$$

as G-representations.

Note that this is not true in general, even for vector-spaces. It is important that the spaces are finite-dimensional. This is a different statement from the hom-tensor adjunction of theorem 15.3.9, not a strengthening of it: the adjunction holds for arbitrary modules, whereas the lemma here needs $\dim_{\mathbb{C}} V < \infty$. It is the more usable description for the case of finite-dimensional vector-spaces.

***Proof*:**
By the universal property:

$$\theta : V^* \otimes_{\mathbb{C}} W \to \mathrm{Hom}_{\mathbb{C}}(V,W) \qquad \lambda \otimes w \mapsto (v \mapsto \lambda(v)w)$$

you should check that this is well-define (note that it is bilinear).

Now, pick basis $e_1, e_2, ..., e_n$ for V, $f_1, f_2, ..., f_m$ for W, and the natural dual $e_1^*, ..., e_n^*$ for V^*. Then we get a basis for $V^* \otimes W$:

$$(e_i^* \otimes f_j) \qquad 1 \leq i \leq n,\ 1 \leq j \leq m$$

Now, notice that:

$$\theta(e_i^* \otimes f_j) \qquad v \mapsto e_i^*(v) f_j \sim \begin{pmatrix} 0 & \cdots & 0 & \cdots & 0 \\ \vdots & & \vdots & & 0 \\ 0 & & 1 & & 0 \\ \vdots & & \vdots & & \vdots \\ 0 & \cdots & 0 & \cdots & 0 \end{pmatrix} = E_{ij}$$

which is the matrix whose only nonzero entry is a 1 in the position sending the basis vector e_i to f_j, and zero everywhere else. This is clearly a basis, hence θ sends a basis to a basis, and hence θ is a vector-space isomorphism. We next check that θ is G-linear:

$$\begin{aligned} \theta(g \cdot (\lambda \otimes w)) &= \theta(g\lambda \otimes gw) \\ &\equiv v \mapsto (g\lambda)(v)gw \\ &= v \mapsto (g\lambda)(g^{-1}v)w \\ &= g(\lambda(g^{-1}v)w) \\ &\equiv g(\theta(\lambda \otimes w)g^{-1}v) \\ &= g \cdot \theta(\lambda \otimes w) \end{aligned}$$

Lemma 53.2.13: Creating New Characters

1. $\chi_{V\oplus W} = \chi_V + \chi_W$
2. $\chi_{V\otimes W} = \chi_V \cdot \chi_W$
3. $\chi_{\mathrm{Hom}_{\mathbb{C}}(V,W)} = \overline{\chi_V}\chi_W$
4. $\chi_{V^*} = \overline{\chi_V}$

***Proof*:**

1. obvious
2. It is enough to show that if $f : V \to V$ and $g : W \to W$ are linear functions, then:
$$\mathrm{tr}(f \otimes h) = \mathrm{tr}(f)\mathrm{tr}(h)$$
Now if we pick basis (e_i) for V and (f_j) for W, then $f(e_i) = \sum a_{ij}e_j$ and $h(f_k) = \sum b_{lk}f_l$. Then:
$$(f \otimes h)(e_i \otimes f_k) = \left(\sum_j a_{ij}e_j\right) \otimes \left(\sum_l b_{lk}f_l\right) = \sum_{j,l} a_{ij}b_{lk}(e_j \otimes f_l)$$
The diagonal coefficient, that of $e_i \otimes f_k$ itself, is $a_{ii}b_{kk}$, so summing over the basis gives $\mathrm{tr}(f \otimes h) = \sum_{i,k} a_{ii}b_{kk} = (\sum_i a_{ii})\,(\sum_k b_{kk}) = \mathrm{tr}(f)\mathrm{tr}(h)$
3. Recall that for $f \in V^*$,
$$(gf)(v) = f(g^{-1} \cdot v)$$
that is
$$\rho_{V^*}(g)(f) = f \circ \rho_V(g^{-1})$$
that is, it is the transpose:
$$\rho_{V^*}(g) = (\rho_V(g^{-1}))^t$$
So, since the transpose matrix has the same trace, we have
$$\chi_{V^*}(g) = \chi_V(g^{-1}) = \overline{\chi_V(g)}$$
we then apply lemma 53.2.12 and part (3)to get:
$$\chi_{\mathrm{Hom}_{\mathbb{C}}(V,W)} = \overline{\chi_V} \cdot \chi_W$$
4. $\chi_{V^*} = \chi_{\mathrm{Hom}(V,\mathbb{C})} = \overline{\chi_V} \cdot 1 = \overline{\chi_V}$.

With this, we can create new characters! However, we have yet to establish how we may find the irreducible components of these chracters. For example, if we take $V \otimes V$, we may find that $\chi_{V\otimes V}$ is a linear combination of some characters already present in our table, but then we have a left-over part. How would we determine if the left-over is irreducible? We will show this by defining an *inner product* on the vector-space of class functions, and show that the irreducible form an *orthogonal basis*!

Definition 53.2.14: Inner Product On Class functions

Let $\chi_1, \chi_2 : G \to \mathbb{C}$ be class functions. Then define:

$$\langle \chi_1, \chi_2 \rangle = \frac{1}{|G|} \sum_{g \in G} \chi_1(g)\overline{\chi_2(g)} \in \mathbb{C}$$

Then this is a [Hermitian] *inner product*.

It should be verified that this is indeeed an inner product. Since class functions are by definition constant on conjugacy classes, we only need to run through representatives of conjgacy classe times the order of each conjugacy class:

$$\langle \chi_1, \chi_2 \rangle = \frac{1}{|G|} \sum_{\substack{\mathcal{K} \in \text{conj}(G) \\ g \in \mathcal{K}}} |\mathcal{K}| \chi_1(g)\overline{\chi_2(g)} \in \mathbb{C}$$

where we pick a single represetnative $g \in \mathcal{K}$ and sum over the number of conjugacy classes, i.e. $|\text{conj}(G)|$. Looking a the inner product like this is desirable to make computation easier (ex. if taking the inner product of a character with itself, we take the *modulus* squared $|\chi(g)|^2$ of each entry in a row (the modulus matters: character values need not be real), multiply by the size of it's conjugcay class). Notice how this inner product mirrors the G-invariant inner product we induced in corollary 53.1.12 if we let $\langle \cdot, \cdot \rangle$ be the usual conjugate dot product on $\mathbb{C}^n$. (TBD)

Lemma 53.2.15: Inner Product With Trivial Character

Let V be a G-representation. Then if $\mathbb{1}$ is the trivial representation,

$$\langle \chi_V, \chi_{\mathbb{1}} \rangle = \dim_{\mathbb{C}}(V^G)$$

where $V^G = \{v \in V \mid g \cdot v = v \ \forall g \in G\}$ is the subspace fixed by G.

***Proof*:**

Define the linear map $\pi : V \to V$ where

$$v \mapsto \frac{1}{|G|} \sum_{g \in G} g \cdot v$$

then:

$$\pi|_{V^G} = \text{id}$$

and

$$\text{im}(\pi) \subseteq V^G$$

which implies $\pi^2 = \pi$, i.e. a projection. By linear linear algebra:

$$V = \ker(\pi) \oplus \text{im}(\pi)$$

where on the kernel, $\pi = 0$, and on the image $\pi = \text{id}$. Thus,

$$\frac{1}{|G|} \sum_g \chi_V(g) = \frac{1}{|G|} \sum_g \text{tr}(g : V \to V) = \text{tr}(\pi) = \dim_{\mathbb{C}}(V^G)$$

but the left hand side is $\langle \chi_V, \chi_{\mathbb{1}} \rangle$, completing the proof.

Corollary 53.2.16: Row Orthogonality

If V and W are any representations of G, then

$$\langle \chi_V, \chi_W \rangle = \dim_{\mathbb{C}}(\hom_{\mathbb{C}[G]}(W, V))$$

In particualr, if V an W are irreducible, then

$$\langle \chi_V, \chi_W \rangle = \begin{cases} 1 & V \cong W \\ 0 & \text{otherwise} \end{cases}$$

that is, irreducible character's are orthogonal to each other.

***Proof*:**
We reduce to the previous lemma:

$$\begin{aligned} \langle \chi_V, \chi_W \rangle &= \frac{1}{|G|} \sum_{g \in G} \chi_V(g) \overline{\chi_W(g)} \\ &= \frac{1}{|G|} \sum_{g \in G} \chi_{\mathrm{Hom}_{\mathbb{C}}(W,V)}(g) \\ &= \langle \chi_{\mathrm{Hom}_{\mathbb{C}}(W,V)}, 1 \rangle \\ &= \dim_{\mathbb{C}}(\mathrm{Hom}_{\mathbb{C}}(W, V)^G) \end{aligned}$$

Note that $f \in \mathrm{Hom}_{\mathbb{C}}(W, V)$ is G-invariant, so $g \cdot f = gfg^{-1} = f$ for all $g \in G$ (recall the definition of $g \cdot f$ on $\mathrm{Hom}_{\mathbb{C}}(W, V)$). Thus this is true iff

$$gf = fg$$

Thus

$$gf(w) = f(gw) \qquad \forall g \forall w \in W$$

so f is $\mathbb{C}[G]$-linear so f is in the $\mathrm{Hom}_{\mathbb{C}[G]}(W, V)$.

There is also a more concrete proof worth remarking: since characters are linear combination's of irreducible characters, the direct product of irreducible modules translates to the sum of an irreducible character with the multiplicity of the irreducible module afording the representation being the multiplicity of the ireducibile characters. Hence:

$$\begin{aligned} \langle \chi_V, \chi_W \rangle &= \langle \sum_i m_i \chi^{(i)}, \sum_j m_j \chi^{(j)} \rangle \\ &= \sum_{i,j} m_i n_j \langle \chi^{(i)}, \chi^{(j)} \rangle \end{aligned}$$

where we have now reduced it to $\langle \chi^{(i)}, \chi^{(j)} \rangle$. Expanding the inner product and using the hom-set definition, we can apply Schur's Lemma and get:

$$\langle \chi^{(i)}, \chi^{(j)} \rangle = \delta_{ij}$$

Thus, our formula becomes:

$$\begin{aligned}\langle \chi_V, \chi_W \rangle &= \langle \sum_i m_i \chi^{(i)}, \sum_j n_j \chi^{(j)} \rangle \\ &= \sum_{i,j} m_i n_j \langle \chi^{(i)}, \chi^{(j)} \rangle \\ &= \sum_{i,j} m_i n_j \delta_{ij} = \sum_i m_i n_i\end{aligned}$$

To find $\langle \chi^{(i)}, \chi^{(i)} \rangle$ for an irreducible character, seeing it through multiplicites, then we know that an irreducible character corresponds to an irreducible representation of multiplicity one. (This is a mnemonic, not an independent proof: the identity $\langle \chi_V, \chi_V \rangle = \sum_i m_i^2$ is itself a consequence of the orthonormality established above.) So if in particular:

$$\langle \chi^{(i)}, \chi^{(i)} \rangle = m_i^2 = 1 \cdot 1 = 1$$

Thus, the irreducible character produce and orthogonal basis of class functions!

Corollary 53.2.17: Consequence of Orthogonality

Let $V = \bigoplus_i^r S_i^{l_i}$ where each S_i irreducible and $S_i \ncong S_j$. Then

1. the multipliity of l_i of S_i is: $l_i = \langle \chi_V, \chi_{S_i} \rangle$
2. $\langle \chi_V, \chi_V \rangle = \sum_i l_i^2$
3. $\hom_G(W, V) \cong \hom_G(V, W)^*$

***Proof*:**

1. Use the Artin-Wedderburn decomposition and the fact that direct sums of modules becomes sums of characters
2. this is just taking advantage of the summing formula
3. This is taking advantage of the fact that $\langle \chi, \psi \rangle = \overline{\langle \psi, \chi \rangle}$.

The second line is useful enough to be given it's own name:

Definition 53.2.18: Character Norm

Let V be a G-representation and let $\langle \cdot, \cdot \rangle$ be the inner product on the class functions of G. Then for any class function $\psi = \sum_i \lambda_i \chi_i$,

$$\|\psi\| = \left(\sum_i |\lambda_i|^2 \right)^{1/2} = \langle \psi, \psi \rangle^{1/2}$$

We will use all this informaiton to deduce new characters:

Example 53.2.19: Orthogonality Relation
Let's go back to our table for S_3:

	e	$(1\ 2)$	$(1\ 2\ 3)$
1	1	1	1
χ_{sgn}	1	-1	1
$\vdots$	$\vdots$	$\vdots$	$\vdots$

Since S_3 has 3 conjugacy classes, it can at most have one more irreducible character. What can this character be? We may start by looking at the degree-three permutation representation of S_3, the one on $\mathbb{C}X$ for $X = \{1, 2, 3\}$ with its natural action, and take its character χ_V. Then:

$$\langle \chi_V, 1 \rangle = 1$$
$$\langle \chi_V, \chi_{\text{sng}} \rangle = 0$$

showing the permutation character χ_V has one copy of the trivial representation (which makes sense, since S_3 is transitive on X, so the fixed space is spanned by the single vector summing the basis). Since

$$\chi_V(e) = 3 \qquad \chi_V((1\ 2)) = 1 \qquad \chi_V((1\ 2\ 3)) = 0$$

then we can take a "compliment" character by subtracting the trivial character, which defines a character which gives:

$$\chi^{\perp}(e) = 2 \qquad \chi^{\perp}(1\ 2) = 0 \qquad \chi^{\perp}(1\ 2\ 3) = -1$$

So, if there were to be another irreducible character, it would be of this form. But does there exist a degree 2 irreducible representation with this character? There is: the class function $(2, 0, -1)$ has norm $\langle \chi^{\perp}, \chi^{\perp} \rangle = (1 \cdot 4 + 3 \cdot 0 + 2 \cdot 1)/6 = 1$, so it is irreducible. Counting also confirms it: we saw that the number of irreducible representations is equal to the number of conjugacy classes, meaning the number of characters must be equal to the number of irreducible representations.

More generally, there can be a few approaches to finding it. One is to tensor two characters we know and see if it is irreducible, or one of it's linear components is irreducible. Another is to find the compliment of a represetnation of an existing character (since $k[G]$-modules are semi-simple). This compliment method is in general less desirable, and usually harder, but is managable if working with permutation representations.To demonstrate, let V be the degree three permutation representation of S_3[a] with basis $\{e_1, e_2, e_3\}$. Then if $\mathbb{1}$ is the trivial action, $V^{\mathbb{1}} = \text{span}(e_1 + e_2 + e_3)$, Thus, by Machke's theorem, $V^{\mathbb{1}}$ has a compliment. To see it, we simply have to extend $e_1 + e_2 + e_3$ to a basis whose last two vectors span its orthogonal complement, for example $(e_1 + e_2 + e_3, e_2 - e_1, e_3 - e_1)$ (these last two are not orthogonal to each other, but they do span the complement). Then we can calculate what the action ρ does on this basis. For example:

$$\begin{aligned} \rho(1\ 2)(e_1 + e_2 + e_3) &= e_1 + e_2 + e_3 \\ \rho(1\ 2)(e_2 - e_1) &= e_1 - e_2 = -(e_2 - e_1) \\ \rho(1\ 2)(e_3 - e_1) &= e_3 - e_2 = -(e_2 - e_1) + (e_3 - e_1) \end{aligned}$$

If we write out ρ for an element in each conjugacy class, we will find that its trace will be

$$\chi^{\perp}(e) = 2 \qquad \chi^{\perp}((1\ 2)) = 0 \quad \chi^{\perp}((1\ 2\ 3)) = -1$$

showing we have found the desired irreducible representation! Finally, each irreducible occurs in the regular representation with multiplicity equal to its degree (proposition 53.1.13), so $\mathbb{C}S_3 \cong \mathbb{1} \oplus \text{sgn} \oplus (V^\perp)^{\oplus 2}$ as representations, of dimension $1+1+4=6$. As algebras Artin-Wedderburn gives $\mathbb{C}S_3 \cong \mathbb{C} \times \mathbb{C} \times M_2(\mathbb{C})$

Now that we know the character table for S_3, we can construct any other character of representations of S_3, and hence any other representation of S_3. For example, we know that $V^\perp \otimes V^\perp$ has as character $\chi_{V^\perp} \cdot \chi_{V^\perp}$. Using this, we can compute that:

$$\begin{aligned}\langle V^\perp \otimes V^\perp, \mathbb{1}\rangle &= 1\\ \langle V^\perp \otimes V^\perp, \text{sgn}\rangle &= 1\\ \langle V^\perp \otimes V^\perp, V^\perp\rangle &= 1\end{aligned}$$

showing that

$$\chi_{V^\perp \otimes V^\perp} = \chi_{\mathbb{1}} + \chi_{\text{sgn}} + \chi_{V^\perp}$$

[a] This is the representation on $\mathbb{C}X$ for $X = \{1,2,3\}$ with its natural S_3-action, not the regular representation, which has degree $|S_3| = 6$.

Recall from linear algebra that if the rows are orthogonal in a square matrix, then so would be the column (and vice-versa). We bring to light this relation for the character table. As in linear algebra, it comes down to proper normalizing of a different basis: recall the class functions $\delta_{\mathcal{K}} : G \to \mathbb{C}$ where:

$$\delta_{\mathcal{K}}(g) = \begin{cases} 1 & g \in \mathcal{K} \\ 0 & \text{otherwise} \end{cases}$$

this naturally forms a basis for the class equations too. The following theorem will also show how to go between this basis and the irreducible character basis:

Theorem 53.2.20: Column Orthogonality

If $\chi_1, \chi_2, ..., \chi_r$ are the irreducible characters of G and $g_1, g_2, ..., g_r$ represent the conjugacy classes of G, then

$$\sum_i \chi_i(g_s)\overline{\chi_i(g_t)} = \delta_{st}\frac{|G|}{|\text{conj}(g_s)|}$$

which by Orbt-stabalizer,

$$\sum_i \chi_i(g_s)\overline{\chi_i(g_t)} = \delta_{st}|C_G(g_s)|$$

If $g_s, g_t \in \text{conj}(g)$, then we get that

$$\sum_i \chi_i(g_s)\overline{\chi_i(g_t)} = \sum_i |\chi_i(g_s)|^2 = |C_G(g_s)|$$

in particular, we must have:

$$\sum_i |\chi_i(e)|^2 = |G|$$

***Proof*:**
Define $f_s : G \to \mathbb{C}$,

$$g \mapsto \begin{cases} 1 & g \in \text{conj}(g_s) \\ 0 & \text{otherwise} \end{cases}$$

which is natural basis for the class functions. since it's a class function, we know we can write it as the sum of orhtogonal ireducibile characters:

$$f_s = \sum_i^r \lambda_{is}\chi_i \qquad \lambda_{is} \in \mathbb{C}$$

since these are orthornormal, we know that:

$$\lambda_{is} = \langle f_s, \chi_i \rangle$$

so computing:

$$\begin{aligned} \lambda_{is} &= \langle f_s, \chi_i \rangle \\ &= \frac{1}{|G|} \sum_{g \in G} f_s(g)\overline{\chi_i(g)} \\ &= \frac{1}{|G|} \sum_{g \in \text{conj}(g_s)} \overline{\chi_i(g)} \\ &= \frac{|\text{conj}(g_s)|}{|G|}\overline{\chi_i(g_s)} \end{aligned}$$

so

$$f_s = \frac{\text{conj}(g_s)|}{|G|} \sum_i^r \overline{\chi_i(g_s)}\chi_i$$

we know evaluate at g_t.

Since both the rows and columns of a character table are all orthogonal to each other, the character table is in fact invertible!

Example 53.2.21: Using Column Orthogonality
Let $G = S_4$. We want to find it's character table. We first pick what conjugacy classes to index the columns by, say:

conj. class	1	(1 2)	(1 2 3)	(1 2)(3 4)	(1 2 3 4)
size	1	6	8	3	6

Next, we can immediately deduce that $\chi_{\mathbb{1}}$ and χ_{sgn} are irreducible characters, giving us the current begining of a character table:

	1	6	8	3	6
	1	(1 2)	(1 2 3)	(1 2)(3 4)	(1 2 3 4)
$\chi_{\mathbb{1}}$	1	1	1	1	1
χ_{sgn}	1	−1	1	1	−1

To find more characters, we can first take the pemutation character of $\mathbb{C}X$. The character of each conjugacy class is the number of fixed points, giving us:

	1	6	8	3	6
	1	(1 2)	(1 2 3)	(1 2)(3 4)	(1 2 3 4)
$\chi_{\mathbb{C}X}$	4	2	1	0	0

We can see that the trivial character is part of linear decomposition of $\chi_{\mathbb{C}X}$, since:

$$\langle \chi_{\mathbb{C}X}, \chi_{\mathbb{1}} \rangle = \big(1(4\cdot 1) + 6(2\cdot 1) + 8(1\cdot 1) + 3(0\cdot 1) + 6(0\cdot 1)\big)/24 = 24/24 = 1$$

and so $\chi_{\mathbb{C}X} - \chi_{\mathbb{1}}$ is a 3 dimensional character, let's label this χ_3. Then $\|\chi_3\|^2 = 1$, showing that it's irreducible, hence we expand our table:

	1	6	8	3	6
	1	(1 2)	(1 2 3)	(1 2)(3 4)	(1 2 3 4)
$\chi_{\mathbb{1}}$	1	1	1	1	1
χ_{sgn}	1	-1	1	1	-1
$\chi_{\mathbb{C}X} - \chi_{\mathbb{1}} = \chi_3$	3	1	0	-1	-1

To find the next character, we can multiply χ_{sgn} and χ_3 (note we can do χ_3 with itself, but it will be 9 dimensional, which we will show in the next proposition cannot be an irreducible representation). Let$\chi_4 = \chi_{\text{sgn}} \cdot \chi_3$. Then $\|\chi_4\|^2 = 1$, meaning it's irreducible, and so we add another row to our table:

	1	6	8	3	6
	1	(1 2)	(1 2 3)	(1 2)(3 4)	(1 2 3 4)
$\chi_{\mathbb{1}}$	1	1	1	1	1
χ_{sgn}	1	-1	1	1	-1
χ_3	3	1	0	-1	-1
$\chi_{\text{sng}} \cdot \chi_3 = \chi_4$	3	-1	0	-1	1

Finally, since $|G| = \sum_i \chi_i(e)^2$, we can deduce that $\chi_5(e) = 2$. We cannot do this same trick exactly for the other columns since we will get the value up to a complex number z with $\|z\| = 1$. To find the rest of the character values, we can either use column orthogonality For example, to find $\chi_5(1\ 2)$, noticet that the inner product of the first and second column is:

$$1\cdot 1 + (-1)\cdot 1 + 3\cdot 1 + 3\cdot(-1) = 0$$

and so $\chi_5((1\ 2))$ must be 0. For the next column, we'd get:

$$1\cdot 1 + 1\cdot 1 + 3\cdot 0 + 3\cdot 0 = 2$$

and so, since $\chi_5(1)\chi_5((1\ 2\ 3)) = 2\chi_5((1\ 2\ 3))$ must cancel this 2, we get that $\chi_5((1\ 2\ 3)) = -1$. Continuing this way, we get that the rest of the table will be:

	1	6	8	3	6
	1	(1 2)	(1 2 3)	(1 2)(3 4)	(1 2 3 4)
$\chi_{\mathbb{1}}$	1	1	1	1	1
χ_{sgn}	1	-1	1	1	-1
χ_3	3	1	0	-1	-1
χ_4	3	-1	0	-1	1
χ_5	2	0	-1	2	0

We can verify this is indeed irreducible by taking $\|\chi_5\|^2 = 1$.

Another method would be to use the regular representation, where we get:

$$\chi_{\mathbb{C}[G]} = \sum_i \chi_i(1)\chi_i$$

These can be verified by taking advantage of the fact that the "column norm" $\sum_i |\chi_i(g)|^2$ should give you $|C_G(g)|$, which is $|G|$ divided by the class size printed on top of the table. For $g = (1\ 2)$, for instance, the column gives $1+1+1+1+0 = 4 = 24/6$.

As a fun aside, the representation with character χ_4 is the rotation action on a cube: if $C \subseteq \mathbb{R}^3$ is the set of vertices of a cube, then χ_4 is the character of the action of S_4 on $\mathbb{R}^3$ by all rotations preserving C, where S_4 permutes the four long diagonals. A transposition acts as a 180° edge rotation and a 4-cycle as a 90° face rotation, with traces -1 and 1, matching the row. It is χ_4 and not χ_3 because a rotation has determinant 1, and $\det \chi_3 = \text{sgn}$.

Notice how the dimension of each irreducible representation divided the order of the group. This is in fact true in general. It is not a trivial fact, the only "order" information we have shown so far is that the sums of the squares of the dimensions of the ireducibile representation sum to $|G|$. It is also relatively eays to show that if $W \subseteq V$ is an irreducible $\mathbb{C}[G]$-module then $(\dim W)^2 \leq |G|$, which is immediate from part (4) above. The following is thus a much stronger result:

Proposition 53.2.22: Dimension Theorem of Irreducible Representations

Let V be an irreducible G-representation. Then:

$$\dim_{\mathbb{C}}(V) \mid |G|$$

that is, the dimension of V divides the order of G.

***Proof*:**
Let $g_1, g_2, ..., g_r$ be representatives of the conjugacy class. Recall the following trick from proposition 53.1.13:

$$e_i = \left(\sum_{g \in \text{conj}(g_i)} g \right) \in Z(\mathbb{C}[G])$$

Note that e_i in fact lies in $e_i \in Z(\mathbb{Z}[G])$, since $ge_ig^{-1} = e_i$ (by definition), and so extending linearly all $xe_ix^{-1} = e_i$. Now we have a commutative ring that is a finitely generated $\mathbb{Z}$-module (one way to see this is as we have done in proposition 53.1.13, another way is to notice that $\mathbb{Z}[G]$ is a finitely generated $\mathbb{Z}$-module and $\mathbb{Z}$ is Noetherian, so the center is finitely generated)

Thus, by proposition 26.1.4, $\mathbb{Z} \subseteq Z(\mathbb{Z}[G])$ is an *integral extension*. Next, we have a ring homomorphism:

$$\varphi : Z(\mathbb{C}[G]) \to \text{End}_{\mathbb{C}[G]}(V) \overset{!}{\cong} \mathbb{C} \qquad z \mapsto (z : V \to V)$$

where $\overset{!}{=}$ comes from corollary 51.2.19 and Schur's lemma, and $z(v) = zv$. Hence each $z \in Z(\mathbb{C}[G])$ acts on V as a scalar $\varphi(z) \in \mathbb{C}$, that is as $\varphi(z) \cdot I$. (Note this scalar may well be 0, for instance whenever $\chi_V(g_i) = 0$, so φ does *not* land in $\text{GL}(V)$.) Acting by a scalar is all we need, and it is exactly the restriction of the original G-action ρ to $Z(\mathbb{C}[G])$. Hence $\rho(e_i) = \lambda_i I$ for appropriate

$\lambda_i = \varphi(e_i)$, meaning $\chi(e_i) = \text{tr}(e_i : V \to V) = n\varphi(e_i)$ where $n = \dim(V)$ since by what we have just shown, $\varphi(e_i)$ acts as scalar multiplication on the representation V.

Now, since $e_i \in Z(\mathbb{C}[G])$ is integral over $\mathbb{Z}$, $\varphi(e_i) \in \mathbb{C}$ is integral over $\mathbb{Z}$, that is $\varphi(e_i) \in \overline{\mathbb{Z}}^{\mathbb{C}} \subseteq \mathbb{C}$ (i.e. $\varphi(e_i)$ is algebraic). Next, we can express $\chi(e_i)$ in a different way:

$$\sum_{g \in \text{conj}(g_i)} \chi_V(g) = |\text{conj}(g_i)| \cdot \chi_V(g_i) = \chi(e_i)$$

so:

$$\frac{\text{conj}(g_i)}{n} \chi_V(g_i) = \varphi(e_i) \in \overline{\mathbb{Z}}^{\mathbb{C}}$$

which is telling us that if we divide it by n, we still get an algebraic integer! Taking a nice linear combination and multiplying by $\overline{\chi_V(g_i)}$ we get:

$$\sum_i^r \frac{\text{conj}(g_i)}{n} \chi_V(g_i) \overline{\chi_V(g_i)}$$

Then we have just shown that $\frac{\text{conj}(g_i)}{n} \chi_V(g_i)$ is an algebraic integer, and $\overline{\chi_V(g_i)}$ is an algebraic integer (being the sum of roots of unity). Now, notice this is the form of the inner product, giving us:

$$\frac{|G|}{n} \langle \chi_V, \chi_V \rangle = \frac{|G|}{n} \in \overline{\mathbb{Z}}^{\mathbb{C}}$$

as a V irreducible. Thus, we have that $\frac{|G|}{n}$ is some algebraic integer. We further have that it is certainly a rational number ($|G|, n \in \mathbb{N}$), but then we have:

$$\frac{|G|}{n} \in \overline{\mathbb{Z}}^{\mathbb{C}} \cap \mathbb{Q} \overset{!}{=} \mathbb{Z}$$

where $\overset{!}{=}$ comes from the fact that if R is a Unique Factorization Domain, $\alpha \in \text{Frac}(R)$, α is integral over R if and only if $\alpha \in R$, completing the proof.

This will make the computation of characters of abelian groups paticularly simple! (see rep theory of finite groups: An introductory Appraoch p. 47!)

Exercise 53.2.1

1. Let G act on the n-dimensional vector-space V by basis permutation. Show that $\dim(V^G)$ equals the number of orbits of G.

53.2.1 More Character Tables

In this section, we go over a few more exmaples of character tables in order to see some techniques used to find them. For any abelian, group, the character table is straight forward. As a really simple example, consider $\mathbb{Z}/3\mathbb{Z}$:

	1	1	1
	0	1	2
χ_0	1	1	1
χ_1	1	ζ_3	ζ_3^2
χ_2	1	ζ_3^2	ζ_3

If we take $\mathbb{Z}/3\mathbb{Z} \times \mathbb{Z}/3\mathbb{Z}$, we will get a 9 by 9 table. The table bellow fills in a few of the characters (note that these were found by taking $\chi_i(g_i)\chi_j(g_j)$)

	1	1	1	1	1	1	1	1	1
$\mathbb{Z}/3\mathbb{Z} \times \mathbb{Z}/3\mathbb{Z}$	$(0,0)$	$(1,0)$	$(2,0)$	$(0,1)$	$(1,1)$	$(2,1)$	$(0,2)$	$(1,2)$	$(2,2)$
$\chi_{(0,0)}$	1	1	1	1	1	1	1	1	1
$\chi_{(1,0)}$	1	ζ_3	ζ_3^2	1	ζ_3	ζ_3^2	1	ζ_3	ζ_3^2
$\chi_{(1,1)}$	1	ζ_3	ζ_3^2	ζ_3	ζ_3^2	1	ζ_3^2	1	ζ_3
$\vdots$	$\vdots$	$\vdots$	$\vdots$	$\vdots$	$\vdots$	$\vdots$	$\vdots$	$\vdots$	$\vdots$

Note that the root ζ_3 might change if we take the direct product of cyclic groups of differnet orders, for example the character table of $\mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/3\mathbb{Z}$ has roots of unity of order 3 and 6 (as you can verify).

More generally, if G is abelian, we break G down into a product of cyclic groups and construct the table like above. Thus, we focus on non-abelian groups. We have already found the character table for S_3:

S_3	e	(1 2)	(1 2 3)
$\chi_{\mathbb{1}}$	1	1	1
χ_{sgn}	1	-1	1
$\chi^{\perp}$	2	0	-1

and the character table for S_4:

	1	6	8	3	6
S_4	1	(1 2)	(1 2 3)	(1 2)(3 4)	(1 2 3 4)
$\chi_{\mathbb{1}}$	1	1	1	1	1
χ_{sgn}	1	-1	1	1	-1
χ_3	3	1	0	-1	-1
χ_4	3	-1	0	-1	1
χ_5	2	0	-1	2	0

Next, let $G = D_4$. Then: $D' = \{e, r^2\}$, so G has 4 degree 1-irreducible representations. We also found in example 53.1.5 that D_4 has a degree 2 irreducible representation. These are all of the representations, sinc $1 + 1 + 1 + 1 + 2^2 = 8$. To find the 1-dimensional irreducible representations, notice that $D_4/D_4' \cong \mathbb{Z}_2 \times \mathbb{Z}_2$, meaning we can find the irreducible representations of $\mathbb{Z}/2\mathbb{Z}$, which are:

$\mathbb{Z}/2\mathbb{Z}$	0	1
χ_0	1	1
χ_1	1	-1

and take the tensor product to create:

$\mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z}$	$(0,0)$	$(1,0)$	$(0,1)$	$(1,1)$
$\chi_{(0,0)}$	1	1	1	1
$\chi_{(1,0)}$	1	-1	1	-1
$\chi_{(0,1)}$	1	1	-1	-1
$\chi_{(1,1)}$	1	-1	-1	1

and using this, we can complete the table for D_4:

D_4	e	r	r^2	σ	σr
χ_1	1	1	1	1	1
χ_2	1	1	1	-1	-1
χ_3	1	-1	1	1	-1
χ_4	1	-1	1	-1	1
χ_5	2	0	-2	0	0

More generally, for D_n, the character table will conssite of characters of degree 1 and 2.

Let's now let $G = Q_8$. Taking the presentation:

$$Q_8 = \langle i, j | i^4 = 1,\ i^2 = j^2,\ i^{-1}ji = j^{-1} \rangle$$

with $k = ij$ and $i^2 = -1$, we get the conjugacy classes can be represented by $1, -1, i, j, k$, with sizes 1, 1, 2, 2, 2. Since $Q_8/Q_8' \cong \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z}$, there are 4 degree 1 characters. The final irreducible character thus *must* have degree 2; let's label if χ_5. We have in fact explicitely found this character before in example 53.1.5, but we can find it without actually manually finding a representation. Let φ be an irreducible representation of degree 2. Since $-1 \in Z(Q_8)$, by Schur's lemma $\varphi(-1)$ is a 2×2 scalar matrix of order 2, hence it is $\pm I$, and so $\chi_5(-1) = \pm 2$. Next, if $\chi_5(i) = a$, $\chi_5(j) = b$, and $\chi_5(k) = c$, then since χ_5 is orthogonal, we have that:

$$1 = \langle \chi_5, \chi_5 \rangle = \frac{1}{8}(2^2 + (\pm 2)^2 + 2a\overline{a} + 2b\overline{b} + 2c\overline{c})$$

and since $a\overline{a}, b\overline{b}, c\overline{c} \in \mathbb{R}_{\geq 0}$, they must all be zero. Furthermore, we must have that:

$$0 = \langle \chi_1, \chi_5 \rangle = \frac{1}{8}\big(2 + (\pm 2) + 0 + 0 + 0\big)$$

implying that $\chi_5(-1) = -2$. Thus, we have that the character table is:

Q_8	1	i	-1	j	k
χ_1	1	1	1	1	1
χ_2	1	1	1	-1	-1
χ_3	1	-1	1	1	-1
χ_4	1	-1	1	-1	1
χ_5	2	0	-2	0	0

Notice that this character table is identical to the character table of D_4. Hence, identical character tables does not imply isomorphic groups! Finally, we could have found the last row of the above table by applying column orthogonality to find the missing values, once we knew $\chi_5(1) = 2$.

Next, let $G = A_4$. Since we found the character table for S_4, we can use it it to find the character table of A_4. We first note that A_4 has 4 conjugacy classes (represented by 1, (1 2)(3 4), (1 2 3) and (1 3 2)), and $[A_4 : A_4'] = 3$, meaning A_4 has 3 chacacters of degree 1, and the only other character must be of degree 3. Next, using the orthogonality relation, notice that χ_3 in the table for S_4 when restricted to A_4 is still irreducible (this is certainly not generally the case, for ex. the degree 2 representaiton of S_3 will become reducible since any proper subgroup of S_3 is abelian). Overall, we get:

A_4	1	(1 2)(3 4)	(1 2 3)	(1 3 2)
χ_1	1	1	1	1
χ_2	1	1	ζ_3	ζ_3^2
χ_3	1	1	ζ_3^2	ζ_3
χ_4	3	-1	0	0

Finally, we will do the character table for S_5:

S_5	1	(1 2)	(1 2 3)	(1 2 3 4)	(1 2 3 4 5)	(1 2)(3 4)	(1 2)(3 4 5)
χ_1	1	1	1	1	1	1	1
χ_2	1	-1	1	-1	1	1	-1
χ_3	4	2	1	0	-1	0	-1
χ_4	4	-2	1	0	-1	0	1
χ_5	5	-1	-1	1	0	1	-1
χ_6	5	1	-1	-1	0	1	1
χ_7	6	0	0	0	1	-2	0

TBD

53.2.2 Burnside's Theorem

We now move towards Burnside's Theorem, which shows that any group of order $p^a q^b$ for primes p, q and numbers $a, b \in \mathbb{N}$ is a solvable group! This proof is relatively simple in the context of representation theory, but it took over 70 years before a proof was found using just group theory! This is a good example of the power perspective: simply switching to the context of representation theory and seeing groups as embedded into $GL(V)$ let us prove a claim that from another perspective is much much harder!

Lemma 53.2.23: Burnside build-up Lemma

Suppose that V is an irreducible representation is of dimension n (i.e. $\chi_V(1) = n$). If $\gcd(n, |\text{conj}(g)|) = 1$, then:

$$|\chi_V(g)| = 0 \text{ or } n$$

***Proof*:**
By the above proof, we have:

$$\frac{|\text{conj}(g)|}{n}\chi_V(g) \in \overline{\mathbb{Z}}^{\mathbb{C}}$$

where $\chi_V(g) \in \overline{\mathbb{Z}}^{\mathbb{C}}$ as well, so by Bézout ($1 = an + b|\text{conj}(g)|$, using $\gcd(n, |\text{conj}(g)|) = 1$)

$$\frac{1}{n}\chi_V(g) \in \overline{\mathbb{Z}}^{\mathbb{C}}$$

Let $\alpha = \frac{1}{n}\chi_V(g)$. Furthermore, notice that:

$$|\alpha| = \left|\frac{\chi_V(g)}{\chi_V(1)}\right| \leq 1$$

Now, let N be the Galois closure of $\mathbb{Q}(\alpha)/\mathbb{Q}$ and write $\Gamma = \text{Gal}(N/\mathbb{Q})$ for its Galois group (not to be confused with the group G of the lemma). Let

$$\beta = \prod_{\sigma \in \Gamma} \sigma(\alpha)$$

Then certainly β is in the fixed field of the Galois group, $\beta \in N^{\Gamma} = \mathbb{Q}$. Notice that each $\sigma(\alpha)$ satisfies the same monic polynomials as that of α, and so $\sigma(\alpha) \in \overline{\mathbb{Z}}^{\mathbb{C}}$, and so $\beta \in \overline{\mathbb{Z}}^{\mathbb{C}}$, but then $\beta \in \overline{\mathbb{Z}}^{\mathbb{C}} \cap \mathbb{Q} = \mathbb{Z}$.

Now, recall that:

$$\alpha = \frac{\chi_V(g)}{n} = \frac{\zeta_1 + \zeta_2 + ... + \zeta_n}{n}$$

which are roots of unity, which means that:

$$\sigma(\alpha) = \frac{\sigma(\zeta_1) + \cdots + \sigma(\zeta_n)}{n}$$

so $|\sigma(\zeta_1)| \leq 1$, so $|\beta| \leq 1$. Since β is an integer, we either get that $|\beta| \in \{0, 1\}$, If $|\beta| = 0$, then $\alpha = 0$, and if $|\beta| = 1$, then $|\alpha| = 1$, and so plugging back into our original equation we get that:

$$\chi_V \in \{0, n\}$$

as we sought to show.

We can also treat this lemma as another check that we have given the correct character table (verify it for the character table of S_4 we found in example 53.2.21).

Theorem 53.2.24: Burnside's Theorem

Let $p \neq q$ be prime numbers, $a, b \in \mathbb{N}$. If $|G| = p^a q^b$, then G is solvable.

Notice how this immediately implies that a non-abelian simple group must have at least three distinct prime divisors, so its order is at least $2 \cdot 3 \cdot 5 = 30$. The true minimum is 60, attained by A_5. There is in fact no simple group of order 30. Recall also that if $|G| = p^a$, then we would need that $a = 1$ (namely, any p-group has a non-trivial center)

***Proof*:**
Take the composition series:

$$1 = G_0 \trianglelefteq G_1 \trianglelefteq \cdots \trianglelefteq G_k = G$$

where G_i/G_{i-1}. Then we will show that if G is simple, then G is *abelian*. For the sake of contradiction, suppose that G is non-abelian and simple with order $p^a q^b$ (where we may as well assume $a, b \in \mathbb{N}_{>0}$). Let $\chi_1, \chi_2, ..., \chi_r$ be the irreducible representation for the group G, and $\chi_1 = \chi_{\mathbb{1}}$. Let $Z_i = \{g \in G \mid |\chi_i(g)| = \chi_i(1)\}$. By the equality case of the triangle inequality this says exactly that $\rho_i(g)$ acts as a scalar, so Z_i is the kernel of $G \to \mathrm{PGL}(V_i)$ and in particular

$$Z_i \trianglelefteq G$$

Fix i and suppose $Z_i = G$. Then G acts by scalars on V_i, so every subspace of V_i is a subrepresentation and hence $\dim V_i = 1$. So χ_i is a homomorphism

$$\chi_i : G \to \mathbb{C}^\times$$

with $\ker \chi_i \trianglelefteq G$. Since G is simple, either $\ker \chi_i = 1$, in which case G embeds in the abelian group $\mathbb{C}^\times$ and is abelian, a contradiction; or $\ker \chi_i = G$, in which case χ_i is trivial and $i = 1$. Thus, it must be that:

$$Z_i = 1 \qquad \forall i > 1$$

Now, take the sylow q-subgroup Q: (notice we are using that $a, b > 0$)

$$1 \subsetneq Q \subsetneq G$$

So Q is a q-group, and so has a non-trivial center: $Z(Q) \neq 1$. Take $h \in Z(Q) \setminus \{e\}$. Hence $Q \leqslant C_G(h)$. , so $[G : C_G(h)] \big| [G : Q] = p^a$, where $[G : C_G(h)] = |\mathrm{conj}(h)$. Now recall we have shown that:

$$\chi_i(1) \big| |G| = p^a q^b$$

Now, if $p \nmid \chi_i(1)$, then by the previous line we have that $\chi_i(1) \big| q^b$. So, $\gcd(\chi_i(1), |\mathrm{conj}(h)|) = 1$, and so by lemma 53.2.23

$$\chi_i(h) = 0 \qquad \text{or} \qquad \chi_i(1)$$

But if $|\chi_i(h)| = \chi_i(1)$, $h \in Z_i$, and so $i = 1$

So, if $p \nmid \chi_i(1)$ and $i > 1$, then $\chi_i(h) = 0$. Using this, we can get our contradiction: as h is not the trivial element, we get:

$$\begin{aligned}
0 &= \sum_i \overline{\chi_i(h)} \chi_i(1) \\
&= \sum_i \chi_i(h) \chi_i(1) && \text{(conjugating, as each } \chi_i(1) \text{ is real)} \\
&\overset{!}{=} 1 + \sum_{\substack{i>1 \\ p \big| \chi_i(1)}} \underbrace{\chi_i(1)}_{\in p\mathbb{Z}} \underbrace{\chi_i(h)}_{\in \overline{\mathbb{Z}}^{\mathbb{C}}} \\
&= 1 + p\alpha && \text{some } \alpha \in \overline{\mathbb{Z}}^{\mathbb{C}}
\end{aligned}$$

where the one in the $\overset{!}{=}$ equality came from when $i = 1$. Thus,

$$\alpha = -1/p \in \overline{\mathbb{Z}}^{\mathbb{C}} \cap \mathbb{Q} = \mathbb{Z}$$

a contradiction, completing the proof.

(huge list of character tables: commented)

53.3 Induced Representation

This is another way of constructing representations. We saw that if $H \leqslant G$ and V is a G representation, then we can make V an H-representation through the inclusion map $H \hookrightarrow G \to \mathrm{GL}(V)$. We may ask if we may go the other way: given an H representation W, can we find a G-representation? If φ is the representations afforded by H, can we find a Φ such that $\Phi|_H = \varphi$? It turns out we cannot: take $A_3 \subseteq S_3$ and consider a faithful representation of degree 1 (recall it's a cyclic group). Then notice that any 1 dimensional representations of S_3 will have to have A_3 in it's kernel, meaning we cannot extend the action of A_3 to an action of S_3. A little more generally, if we let G be a simple group, $H \leqslant G$, and φ a representation of H where $\ker(\varphi)$ is a proper nontrivial subgroup of H, then if we somehow extend the representation φ of H to Φ of G, then $\ker(\Phi) \cap H = \ker(\varphi)$, so $\ker(\Phi)$ is nontrivial (it contains $\ker\varphi$) and proper (else $\ker\varphi = H$), contradicting that G is simple. So instead, we will not be extending representation from H to G, but *inducing* a representation in a natural way. This method of inducing a representation will work even in the two above cases, meaning an induced representation will not always be an extension.

Let $H \leqslant G$, and consider some H-representation V, which can be represented as a $k[H]$-module V. Recall that we can "extend scalars" and define a new $k[G]$-module:

$$k[G] \otimes_{k[H]} V$$

This is extension of scalars along the inclusion $k[H] \hookrightarrow k[G]$.

Definition 53.3.1: Induced Representation

Let $H \leqslant G$ of a finite group G and let V be a $k[H]$-module affording the representation φ. Then the $k[G]$-module $k[G] \otimes_{k[H]} V$ is called the *induced module* of V, the representation is called the *induced representation*, and if χ is the character of φ, then the character of the induced representation is called the *induced character*, and is written as $\mathrm{Ind}_H^G(\chi)$.

Another intuition behind defining the induced module is the following: If W is an H-representation, then let our new module be:

$$\mathrm{Ind}_H^G(W) = \{f \in \mathrm{Hom}_{\mathbf{Set}}(G, W) \mid f(hg) = h \cdot f(g),\ \forall g \in G, h \in H\}$$

Then $\mathrm{Ind}_H^G(W)$ is clearly a complex vector space under pointwise addition and scalar multiplication, and the G-action on this space would be:

$$\gamma \cdot f : G \to W \qquad g \mapsto f(g\gamma)$$

It should be verified that this is indeed G-linear. In this case, we get that:

$$\mathrm{Ind}_H^G(W) = \mathrm{Hom}_{\mathbb{C}[H]}(\mathbb{C}[G], W)$$

This second construction is the *coinduced* module, and it is a genuinely different functor from the induced module $k[G] \otimes_{k[H]} V$ in general. The two agree precisely because $[G : H]$ is finite: $k[G]$ is free of finite rank as a right $k[H]$-module, and for a finitely generated free module the natural map

$k[G] \otimes_{k[H]} V \to \mathrm{Hom}_{k[H]}(k[G], V)$ is an isomorphism. Since G is finite throughout this section, we may and do use the two interchangeably, and we take the tensor construction of definition 53.3.1 as the definition of record. The dimension of $\mathrm{Ind}_H^G(W)$ is

$$\dim_{\mathbb{C}}(\mathrm{Ind}_H^G(W)) = [G : H] \dim_{\mathbb{C}}(W)$$

with the $\mathbb{C}$-vector space isomorphism being:

$$\mathrm{Ind}_H^G(W) \to W^{\oplus [G:H]} \qquad f \mapsto f(g_1), ..., f(g_{[G:H]})$$

where we treat $G = \coprod_i Hg_i$ for the *right* cosets Hg_i (the equivariance $f(hg) = hf(g)$ makes f constant-up-to-H on right cosets, so those are the ones its values are indexed by). Note that every block and character formula later in this section is indexed by *left* cosets g_iH instead, matching the tensor model $k[G] = \bigoplus_i g_i k[H]$. The two indexings are exchanged by $g \mapsto g^{-1}$, and we will say which is meant wherever it matters. By letting $g_1 = e$ being the identity, there is a natural canonical map:

$$\mathrm{Ind}_H^G(W) \to W \qquad f \mapsto f(e)$$

This motivates the following adjoint of the restriction functor:

Theorem 53.3.2: Frobenius Reciprocity

Let $H \leqslant G$. Then if V is a G-representation and W and H-representation, then:

$$\mathrm{Hom}_G(V, \mathrm{Ind}_H^G W) \cong_{\mathbb{C}} \mathrm{Hom}_H(V|_H, W)$$

where $V|_H$ is the restriction of the action to H

***Proof*:**
We will explicitly construct inverse bijections Φ from left to right and Θ from right to left.
Let $\alpha : \mathrm{Ind}_H^G(W) \to W$, $f \mapsto f(1)$. Then α is H-linear. Then let

$$\Phi(f) = \alpha \circ f$$

Then $\Phi(f)$ is H-linear (check $\mathbb{C}$-linearity of Φ). For the other way, let $\psi : V|_H \to W$ be H-linear,

$$\Theta(\psi) : V \to \mathrm{Ind}_H^G(W) \qquad v \mapsto (g \mapsto \psi(gv))$$

Then this is well-defined. What's left is to check they are inverses of each other

53.3.3 Left Vs Right Adjoint This proof shows that induction is right-adjoint to restriction. It is also *left* adjoint: for a finite group, $\mathrm{Hom}_G(\mathrm{Ind}_H^G W, V) \cong \mathrm{Hom}_H(W, V|_H)$ as well. A pair of functors (F, U) where F is both left and right adjoint to U is sometimes called a *Frobenius pairing*, and this is exactly what the coincidence of induction and coinduction at finite index buys.

The two-sided adjunction is special to finite index. For an infinite group the tensor construction $k[G] \otimes_{k[H]} -$ is left adjoint to restriction and the coinduced module $\mathrm{Hom}_{k[H]}(k[G], -)$ is right adjoint, and these are different functors. In the smooth representation theory of locally profinite groups the convention is that Ind denotes the coinduced (right adjoint) functor and c-Ind, *compact induction*, denotes the left adjoint (see [34]).

Corollary 53.3.4: Frobenius Reciprocity On Characters

Let G be finite, $k = \mathbb{C}$, and $H \leqslant G$. Let χ be the character of a G-representation V and ψ the character of an H-representation W. Then:

$$\langle \chi|_H, \psi \rangle_H = \langle \chi, \mathrm{Ind}_H^G(\psi) \rangle_G$$

***Proof*:**

Both sides count the same dimension. First note that for representations A, B of a finite group over $\mathbb{C}$ we have $\dim_{\mathbb{C}} \mathrm{Hom}(A, B) = \dim_{\mathbb{C}} \mathrm{Hom}(B, A)$: by corollary 53.2.16 these are $\langle \chi_B, \chi_A \rangle$ and $\langle \chi_A, \chi_B \rangle$, and writing A and B in terms of irreducibles (theorem 53.1.9) both equal $\sum_i a_i b_i$ for the multiplicities a_i, b_i.

Now apply corollary 53.2.16 to each side:

$$\langle \chi, \mathrm{Ind}_H^G(\psi) \rangle_G = \dim_{\mathbb{C}} \mathrm{Hom}_G(\mathrm{Ind}_H^G W, V) = \dim_{\mathbb{C}} \mathrm{Hom}_G(V, \mathrm{Ind}_H^G W)$$

using the symmetry just noted, and this last space is $\mathrm{Hom}_H(V|_H, W)$ by theorem 53.3.2. Applying the symmetry and corollary 53.2.16 once more,

$$\dim_{\mathbb{C}} \mathrm{Hom}_H(V|_H, W) = \dim_{\mathbb{C}} \mathrm{Hom}_H(W, V|_H) = \langle \chi|_H, \psi \rangle_H$$

as claimed.

Example 53.3.5: Induced Representations

1. $\mathrm{Ind}_G^G(W) = W$
2. $\mathrm{Ind}_{\{e\}}^G(\mathbb{C}) = \mathbb{C}[G]$
3. $\mathrm{Ind}_H^G(\mathbb{1}) = \mathbb{C}[G/H]$

Another way of thinking of this result is that if V is an irreducible representation of G and W is an irreducible representation of H, then the number of times V occurs in $\mathrm{Ind}_H^G(W)$ is equal to the number of times W occurs in $V|_H$.

Proposition 53.3.6: Properties Of Induced Representation

Let $K \leqslant H \leqslant G$, W be an K-representation, $\text{Ind}_K^H(W)$ the induced H representation, $\text{Ind}_H^G(\text{Ind}_K^H(W))$ the induced G-representation. Then:

1. If χ, χ' are characters of K-representations,
$$\text{Ind}_K^H(\chi + \chi') = \text{Ind}_K^H(\chi) + \text{Ind}_K^H(\chi')$$
2. Induction is transitive:
$$\text{Ind}_H^G(\text{Ind}_K^H(W)) = \text{Ind}_K^G(W)$$

***Proof*:**
For (1), let W_1, W_2 be K-representations affording χ, χ'. Tensoring is additive in its second argument, so

$$k[H] \otimes_{k[K]} (W_1 \oplus W_2) \cong \big(k[H] \otimes_{k[K]} W_1\big) \oplus \big(k[H] \otimes_{k[K]} W_2\big)$$

as $k[H]$-modules, and the character of a direct sum is the sum of the characters.

For (2), the point is associativity of the tensor product together with $k[H] \otimes_{k[H]} k[G] \cong k[G]$ as $(k[G], k[H])$-bimodules. Explicitly,

$$\text{Ind}_H^G\big(\text{Ind}_K^H(W)\big) = k[G] \otimes_{k[H]} \big(k[H] \otimes_{k[K]} W\big) \cong \big(k[G] \otimes_{k[H]} k[H]\big) \otimes_{k[K]} W \cong k[G] \otimes_{k[K]} W = \text{Ind}_K^G(W)$$

where the first isomorphism is associativity and the second is the unit isomorphism. Each map is $k[G]$-linear because G acts by left multiplication on the leftmost factor throughout, which every map above respects.

Theorem 53.3.7: Computing Induced Representation

Let $H \leqslant G$ of a finite group G, and $g_1, g_2, ..., g_m$ be representatives for distinct left cosets of H in G. Let V be an H-representation of degree n. Then the induced G-representation $W = k[G] \otimes_{k[H]} V$ is an nm degree representation, and if Φ repersented the induced representation, then there exists a basis for W such that W affords the matrix representation defined for each $g \in G$ by:

$$\Phi(g) = \begin{pmatrix} \varphi(g_1^{-1} g g_1) & \cdots & \varphi(g_1^{-1} g g_m) \\ \vdots & \vdots & \cdots \\ \varphi(g_m^{-1} g g_1) & \cdots & \varphi(g_m^{-1} g g_m) \end{pmatrix}$$

where each $\varphi(g_i^{-1} g g_j)$ is an $n \times n$ block, with $\varphi(g_i^{-1} g g_j) = 0$ if $g_i^{-1} g g_j \notin H$.

***Proof*:**
First, $k[G]$ is a free right $k[H]$-module with decomposition:

$$k[G] = g_1 k[H] \oplus \cdots \oplus g_m k[H]$$

Since tensor products commute with direct sums, we get:

$$W = k[G] \otimes_{k[H]} V \cong (g_1 \otimes V) \oplus \cdots \oplus (g_m \otimes V)$$

Since k is in the center of $k[G]$, the above isomorphism is also a k-vector space isomorphism. Thus, if $v_1, v_2, ..., v_n$ is a basis for V, then $\{g_i \otimes v_j \mid 1 \leq i \leq m,\ 1 \leq j \leq n\}$ is a basis for W, and hence $\dim_k(W) = nm$.

To show $\Phi(g)$ is of the given form, order the basis into m of size n as:

$$g_1 \otimes v_1, g_1 \otimes v_2, ..., g_1 \otimes v_n, g_2 \otimes v_1, ..., g_m \otimes v_n$$

Using this order, we can compute the matrix $\Phi(g)$ for each g acting on W given this basis. Fixing j and g, let i be the unique index with $gg_j \in g_i H$ and write $gg_j = g_i h$ with $h \in H$. Then for every k:

$$g(g_j \otimes v_k) = gg_j \otimes v_k = g_i h \otimes v_k = g_i \otimes hv_k = \sum_{t=1}^{n} a_{tk}(h)(g_i \otimes v_t)$$

where a_{tk} is the t, k coefficient of the matrix h acting on V with respect to the basis $v_1, v_2, ..., v_n$. Notice that the action of g on W maps the jth block of n basis vectors of W to the ith block of basis vectors, and then has the matrix $\varphi(h)$ as that block. Since $h = g_i^{-1} g g_j$, this fully describes $\Phi(g)$, as we sought to show.

Corollary 53.3.8: Computing The Induced Character

Let $H \leqslant G$ where G is a finite group, V be an H-representation with character χ, and $\mathrm{Ind}_H^G(\chi)$ the induced character. Then:

$$\mathrm{Ind}_H^G(\chi)(g) = \sum_{i=1}^{m} \chi(g_i^{-1} g g_i) \qquad \text{for all } g \in G$$

where $g_1, \ldots, g_m$ is a complete set of representatives for the left cosets of H in G, $m = [G : H]$, and $\chi(g_i^{-1} g g_i) := 0$ if $g_i^{-1} g g_i \notin H$. (The right-hand side does not depend on the chosen representatives: replacing g_i by $g_i h$ conjugates $g_i^{-1} g g_i$ by $h \in H$, which preserves membership in H and leaves χ unchanged, χ being a class function on H.) Hence, $\mathrm{Ind}_H^G(\chi)(g) = 0$ if g is not conjugate of some element in H in G, in particular if $H \trianglelefteq G$ then $\mathrm{Ind}_H^G(\chi)$ is zero on all elements $G - H$.


***Proof*:**
Let φ be the representation afforded by V. By theorem 53.3.7, $k[G] \otimes_{k[H]} V$ has a basis in which g acts by the block matrix $\Phi(g)$ whose (i, j) block is $\varphi(g_i^{-1} g g_j)$, the block being zero when $g_i^{-1} g g_j \notin H$. By definition 53.3.1, $\mathrm{Ind}_H^G(\chi)(g)$ is the trace of $\Phi(g)$, which is the sum of the traces of the diagonal blocks $\varphi(g_i^{-1} g g_i)$. Each of these traces is $\chi(g_i^{-1} g g_i)$ when $g_i^{-1} g g_i \in H$ and 0 otherwise, which gives the formula. If g is conjugate to no element of H, every $g_i^{-1} g g_i$ lies outside H and the sum is 0. If $H \trianglelefteq G$ and $g \notin H$, then $g_i^{-1} g g_i \notin H$ for every i, since $g_i^{-1} g g_i \in H$ would give $g \in g_i H g_i^{-1} = H$, so $\mathrm{Ind}_H^G(\chi)(g) = 0$, as claimed.

Proposition 53.3.9: Induced Index Two Induced Representation


Let $H \leqslant G$ where $[G : H]$ has index two[a] (ex. $A_n \leqslant S_n$ or $C_n \leqslant D_{2n}$). Then if V is a finite-dimensional irreducible representation of G, either $V|_H$ is irreducible or $V|_H = W_1 \oplus W_2$ where $W_1 \ncong W_2$, are both ireducibile, and have the same dimension. Moreover, the second option implies that $V \cong V \otimes \chi$ where $\chi : G \twoheadrightarrow G/H \cong \{\pm 1\}$ (i.e. a 1-dimensional representation)

[a]Recall that this makes H a normal subgroup

In the case where $V|_H$ is not irreducible, we can imagine it splitting into a diagram like so:



while in the case where $V|_H$ is irreducible, what we actually have (and did not have time to prove), is that we have *two* irreducible representation's of G (V and V') that both get restricted to W:



and then the induced representation of W is the direct sum of V and V'.

***Proof*:**
Let $W \subseteq V|_H$ be an irreducible H-representation. Then Since $H \trianglelefteq G$, gW is is an H-stable space: gW is some subspace of V (it satisfies the subspace axioms since the action is linear), and for any $h \in H$, $h \cdot gW = hgW = g(g^{-1}hg)W = gW$, since $g^{-1}hg \in H$ by normality of H and W is H-stable. Now, gW is irreducible: the map $w \mapsto gw$ is a k-linear bijection $W \to gW$ satisfying $h(gw) = g((g^{-1}hg)w)$, so it intertwines the H-action up to conjugation. Since $g^{-1}Hg = H$ by normality, it carries H-submodules to H-submodules in both directions, so gW is irreducible. Finally, the structure of gW only depends on that of the coset gH

Thus, fix $\gamma \in G \setminus H$ so that

$$\sum_{g \in G} gW = W + \gamma W \subseteq V$$

where the $\subseteq$ comes from the fact that this is a sum of two subspaces. Now, notice that the left hand side is a G-stable space which is nonzero, and V is irreducible so has no proper nonzero G-stable subspace. Therefore we actually have the equality:

$$W + \gamma W = V$$

meaning the $H + gH = G$ is parallelled in the action! We now have two possibilities: either $W = \gamma W$, and so $V|_H = W$, and we have $\dim V = \dim W$ (which is case (a)).

On the other hand, if $W \neq \gamma W$, then $W \cap \gamma W = (0)$ (since they are both irreducible), and so $V = W \oplus \gamma W$ (i.e. direct sum as H-representations), and so V is the direct sum of two irreducible H-representations.

Now, by Frobenius reciprocity, we get:

$$\langle W, V|_H \rangle_H = \langle \mathrm{Ind}_H^G(W), V \rangle_G$$

Since W occurs in $V|_H$ by definition, we get that $1 \leq \langle W, V|_H \rangle_H$, while since V is irreducible and, continuing in case (b), $\dim \mathrm{Ind}_H^G(W) = [G : H] \dim W = 2 \dim W = \dim V$, the representation V can occur at most once, so $\langle \mathrm{Ind}_H^G(W), V \rangle_G \leq 1$, and hence:

$$1 = \langle W, V|_H \rangle_H = \langle \mathrm{Ind}_H^G(W), V \rangle_G = 1$$

Thus, from the first one, we get that $W \ncong \gamma W$ (or else the left hand side would be equal to 2), and we must have $V = \mathrm{Ind}_H^G(W)$ (or else the right hand side would be equal to something greater than 1)

If part (b) holds, then

$$(V \otimes \chi)|_H \cong V|_H$$

and

$$V \cong \mathrm{Ind}_H^G(W) \cong V \otimes \chi$$

Conversely, if $V \cong V \otimes \chi$, then $\chi_V(g) = \chi_V(g)\chi(g)$ for all $g \in G$. Since $\chi(g) = -1$ for $g \notin H$, this gives $\chi_V(g) = -\chi_V(g)$, so $\chi_V(g) = 0$ for all $g \notin H$. And so:

$$\|\chi_{V|_H}\|_H^2 = 2\|\chi_V\|_G^2$$

and so $\langle \chi_{V|_H}, \chi_{V|_H} \rangle_H = 2$, which rules out a single irreducible (norm 1) and $W \oplus W$ (norm 4), forcing $V|_H = W_1 \oplus W_2$ with $W_1 \ncong W_2$ irreducible, as we sought to show.

Theorem 53.1.16 says that the constituents of $\pi|_N$ form a single G-orbit. Once induction is available, that orbit description turns into a construction: the representation is induced from the subgroup stabilizing one of the classes. This is the form in which Clifford's theorem is normally applied.

Corollary 53.3.10: Clifford Induction From the Stabilizer

Let G be a group, $N \trianglelefteq G$, K a field, and let (π, V) be an irreducible representation of G on a finite-dimensional K-space. Let $W \subseteq V$ be an irreducible N-subrepresentation, let

$$H = \{g \in G \mid \pi_W^g \cong \pi_W\}, \qquad \pi_W^g(n) = \pi_W(g^{-1}ng)$$

be the stabilizer of its class, and let V_W be the π_W-isotypic component of $V|_N$. Then $N \subseteq H$, the subspace V_W is an irreducible H-subrepresentation, and

$$V \cong \mathrm{Ind}_H^G V_W$$

If $\pi|_N$ has more than one isomorphism class among its constituents, then $H \neq G$ and π is induced from a proper subgroup.

***Proof*:**
That $N \subseteq H$ is immediate, since $\pi_W^n \cong \pi_W$ for $n \in N$ by conjugating the isomorphism. Since V is finite dimensional, $V|_N$ has finitely many constituents, so the orbit below is finite and $[G : H]$ is finite. No finiteness of G itself is needed anywhere. By theorem 53.1.16 the classes occurring in $V|_N$ form one G-orbit, and $g \mapsto (U \mapsto U^g)$ is a left action, so the orbit is in bijection with G/H and $gV_W = V_{\pi_W^g}$ depends only on the coset gH. Summing the isotypic decomposition of the semisimple $V|_N$ over that orbit,

$$V = \bigoplus_{gH \in G/H} gV_W$$

This decomposition exhibits V as an induced representation. By definition 53.3.1 the induced representation is $\operatorname{Ind}_H^G V_W = K[G] \otimes_{K[H]} V_W$. The map

$$\Theta \colon K[G] \otimes_{K[H]} V_W \longrightarrow V, \qquad g \otimes v \longmapsto gv$$

is well defined, because $gh \otimes v$ and $g \otimes hv$ both go to ghv for $h \in H$, and it is G-equivariant by construction. It is surjective, since its image contains every gV_W and those span V by the display. Finally $\dim_K K[G] \otimes_{K[H]} V_W = [G : H] \dim_K V_W$, which is $\dim_K V$ by the display again, so Θ is an isomorphism.

Irreducibility of V_W over H. If $V_0 \subseteq V_W$ were a non-zero proper H-subrepresentation then $\bigoplus_{gH} gV_0$ would be a non-zero proper G-subrepresentation of V, the sum being direct and G-stable because V_0 is H-stable and gV_0 depends only on gH. That contradicts irreducibility of V.

For the last sentence, suppose more than one isomorphism class occurs in $\pi|_N$. The classes are in bijection with G/H, so $[G : H] > 1$ and H is proper, completing the proof.

53.4 *Application to Harmonic Analysis

In this section, we take a brief moment to explore the representation of locally compact abelian groups, such as $\mathbb{R}$. This section will assume some understanding of topological groups, and is mainly to motivate for the reader the connection between the representation theory of this chapter with *Fourier analysis* and more broadly *Harmonic analysis*.

Every group G is always a topological group with the discrete topology (see appendix C.4). The group G is finite iff it is a compact discrete group. Many groups of interest are either compact (like the torus or compact lie groups), or locally compact (like the real line). The representation theory of these groups rely on the correct framing of the representation in the finite case. For the case of infinite dimension *non-abelian* groups, the build-up is a good deal too complicated for this expository section[4], however many of the major ideas for the abelian are simple enough to exposit, and even better naturally motivate the Fourier transform and abstract harmonic analysis through the lens of representation theory.

Let G be a finite abelian group so that all complex irreducible representations are 1-dimensional, and hence characters and necessarily a homomorphism. As G is finite, say $n = |G|$, then $\chi(g^n) = \chi(e) = 1$

[4] see [41] for the EYNTKA series on geometric representation theory

for all $g \in G$, and so $\chi^n = \mathrm{id}$, showing that $\chi : G \to \mathbb{C}^*$ restricts to a map $\chi : G \to S^1$. This shows that all characters are *unitary representations*. All characters for a finite group are necessarily unitary representations, while for non-finite groups there can be non-unitary representations[5]. Such groups which have a (general) representation theory that does not generalize as well as infinite unitary representations (many representations are indecomposable but not irreducible, for the details see the companion Lie groups notes). Thus, for this sections we stick to maps to S^1 with the natural multiplication structure as the subgroup of $\mathbb{C}^*$: label this collection $\hat{G} = \mathrm{Hom}_{\mathbf{Ab}}(G, S^1)$. As the codomain is a group, $\mathrm{Hom}_{\mathbf{Ab}}(G, S^1)$ has a group structure given by point-wise multiplication.

Definition 53.4.1: Pontryagin Group

Let G be locally compact abelian group. Then the *Pontryagin dual* of G is the group:

$$\mathrm{Hom}_{\mathbf{Top}}(G, S^1)$$

of *continuous* homomorphisms, with the operation being point-wise multiplication and the compact-open topology. The topology is what makes $\widehat{G}$ itself locally compact abelian, and so what makes the double dual $\widehat{\widehat{G}}$ meaningful; for finite G it is discrete and can be ignored.

This is just another way of representing the characters of the group. Let us stick to the special case where G is a finite abelian group and re-frame the previous theory using the Pontryagin group:

Proposition 53.4.2: Pontryagin Dual

Let G be a finite abelian group, $\hat{G} = \mathrm{Hom}_{\mathbf{Ab}}(G, S^1)$ the group of characters under point-wise multiplication. Then there is an isomorphism:

$$G \cong \widehat{G}$$

Furthermore, there is a natural isomorphism:

$$G \cong \hat{\hat{G}}$$

If G is infinite, it is rarely the case that $G \cong \widehat{G}$ (think $\widehat{L^p} \cong L^q$). Indeed when G is compact and infinite it never is, since $\widehat{G}$ is then discrete. What is most important is that $\widehat{G}$ contains the necessary information to recover G, as the double-dual recovers G. The operation $\widehat{(-)}$ passes back and forth between a group and a unitary representation, and since the representations in play are unitary, that collection is itself a group[6]. The passage between the two is thus:

$$\text{Group} \overset{\widehat{(-)}}{\rightleftarrows} \text{Unitary Rep.}$$

[5] $\mathrm{SL}_2(\mathbb{R})$ acting on $\mathbb{R}^2$ need not be unitary

[6] the collection of representations also form a ring called the *representation ring* and has fascinating ties to K-theory and intersection theory, but it is again too much for this section and the connections are discussed in [13, Part II] of the EYTNKA series

***Proof*:**
As G is finite abelian,

$$G \cong \mathbb{Z}/n_1\mathbb{Z} \times \mathbb{Z}/n_2\mathbb{Z} \times \cdots \times \mathbb{Z}/n_k\mathbb{Z}$$

where $n_1 \big| n_2 \big| \cdots \big| n_k$. Choose generators, $a_1, ..., a_k$. Define the indicator characters on the generators:

$$\chi_i(a_j) = \begin{cases} e^{\frac{2\pi i}{n_i}} & i = j \\ 1 & i \neq j \end{cases}$$

These certainly generate $\hat{G}$. Define the map on the generators:

$$\Phi(a_i) = \chi_i$$

This is an isomorphism.

For the double-dual, take the natural map (distinct from the Φ above):

$$\Psi(g_i) = \mathrm{ev}_{g_i}$$

where as usual $\mathrm{ev}_{g_i}(\chi) = \chi(g_i)$. This is easy to check that is an isomorphism, completing the proof.

Now, to study a space is to study all the (continuous) functions on it. Here the space is a finite abelian group. Let G have the discrete topology so that the set of continuous functions from G to $\mathbb{C}$ is all set functions. The goal is a $\mathbb{C}$-algebra isomorphism between $\mathbb{C}[G]$ and $\mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C})$. These two sets are clearly bijective via the natural mapping:

$$\sum_i a_i g_i \mapsto (g_i \mapsto a_i)$$

And this map preserves addition if addition is defined point-wise in the hom-set:

$$\begin{aligned} &\Phi\left(\sum_i a_i g_i + \sum_i b_i g_i\right) \\ &= \Phi\left(\sum_i (a_i + b_i) g_i\right) \\ &\mapsto (g_i \mapsto a_i + b_i) \\ &= (g_i \mapsto a_i) + (g_i \mapsto b_i) \\ &= \Phi\left(\sum_i a_i g_i\right) + \Phi\left(\sum_i b_i g_i\right) \end{aligned}$$

But it does *not* preserve multiplication if the operation is pointwise multiplication:

$$\begin{aligned}
&\Phi\left(\sum_{g\in G} a_i g \sum_{g\in G} b_i g\right) \\
&= \Phi\left(\sum_{g\in G}\sum_{g_k g_\ell = g} (a_k b_\ell) g\right) \\
&\mapsto (g_i \mapsto \sum_{g_k g_\ell = g_i} (a_k b_\ell)) \\
&\neq (g_i \mapsto a_i b_i) \\
&= (g_i \mapsto a_i)\cdot(g_i \mapsto b_i) \\
&= \Phi\left(\sum_i a_i g_i\right)\cdot\Phi\left(\sum_i b_i g_i\right)
\end{aligned}$$

This is because the points g_i act on each other. There is a natural multiplication function defined on $\mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C})$ called *convolution*:

Definition 53.4.3: Convolution

Let $p, q \in \mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C})$. Then their *convolution* is define pointwise as:

$$(p * q)(g) = \sum_{g_i g_j = g} p(g_i) q(g_j) = \sum_{h\in G} p(h) q(h^{-1} g)$$

Lemma 53.4.4: Isomorphism With Convolution

Let G be a finite abelian group. Then:

$$(\mathbb{C}[G], +, \cdot) \cong_{k\text{-}\mathbf{Alg}} (\mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C}), +, *)$$

where the left hand side is the usual group ring and the right hand side has convolution as multiplication

***Proof*:**
The first two lines of the multiplication calculation above evaluate $\Phi(x\cdot y)$ at g_i as $\sum_{g_k g_\ell = g_i} a_k b_\ell$, which is exactly $(\Phi(x) * \Phi(y))(g_i)$ for the convolution just defined; additivity and bijectivity were checked above.

Now, $(\mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C}), +, *)$ is a $|G|$-dimensional $\mathbb{C}$ vector-space with the natural basis given by the indicator function:

$$\delta_h(g) = \begin{cases} 1 & g = h \\ 0 & g \neq h \end{cases}$$

Namely for any $f : G \to \mathbb{C}$ there is a unique decomposition given the functionals defined by each $g \in G$:

$$f = \sum_{h\in G} f(h)\delta_h \qquad \text{so that} \qquad f(g) = \sum_{h\in G} f(h)\delta_h(g) = f(g)\cdot 1 = f(g)$$

The key feature of this basis is that it acts like evaluation when taking the inner product. Define:

$$\langle f, g \rangle = \sum_{h \in G} f(h)\overline{g(h)}$$

Then $\{\delta_g\}_{g \in G}$ is an orthogonal basis and:

$$\langle f, \delta_{g_i} \rangle = f(g_i) \cdot \overline{\delta_{g_i}(g_i)} = f(g_i) \cdot 1 = f(g_i) = a_i$$

This is a special case of the Riesz representation theorem: every linear functional here is inner-product representable, and ev_{g_i} is represented by δ_{g_i}. This inner product can be thought as expressly chosen so that the collection δ_{g_i} forms an orthonormal basis, or conversely given this standard inner product, the indicator function will always be an orthonormal basis. Now $\hat{G}$ also has $|G|$ elements, so the characters are at least the right number to be a second basis, but they are a different family of functions from the δ_g, not the image of them under any isomorphism, and nothing so far says they are independent, let alone orthogonal. The key insight of Fourier analysis is that they are!

Proposition 53.4.5: Character Form Orthogonal Basis: Fourier Basis

The characters $\widehat{G}$ form an orthogonal basis for $\text{Hom}_{\mathbf{Top}}(G, \mathbb{C})$. Normalizing by $1/\sqrt{|G|}$ forms an orthonormal basis.

***Proof*:**
If $i = j$:

$$\begin{aligned}
\langle \chi_i, \chi_i \rangle &= \sum_{g \in G} \chi_i(g)\overline{\chi_i(g)} \\
&= \sum_{g \in G} |\chi_i(g)|^2 \\
&= \sum_{g \in G} 1^2 \\
&= |G|
\end{aligned}$$

if $i \neq j$, Then as $\overline{\chi_j} = \chi_j^{-1}$ (as we are mapping to the unit circle), we get that $\chi' = \chi_i \chi_j^{-1}$ is a non-trivial character, so there is some h such that $\chi'(h) \neq 1$. Let

$$\langle \chi_i, \chi_j \rangle = S = \sum_{g \in G} \chi'(g)$$

Then:

$$\chi'(h)S = \chi'(h) \sum_{g \in G} \chi'(g) = \sum_{g \in G} \chi'(h)\chi'(g) = \sum_{g \in G} \chi'(hg)$$

As $hG = G$, this is just a re-arranging of terms, hence:

$$\chi'(h)S = \sum_{g \in G} \chi'(g) = S \qquad \text{so} \qquad S(\chi'(h) - 1) = 0$$

Now, by assumption $\chi'(h) \neq 1$, so $\chi'(h) - 1 \neq 0$, so as $\mathbb{C}$ is an integral domain it must be that $S = 0$, implying:

$$\langle \chi_i, \chi_j \rangle = 0$$

as we sought to show.

This inner product can be thought of as extracting the "phase" information.

Example 53.4.6: Phase-Space Basis

Let $G = \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z} = \{(0,0),(1,0),(0,1),(1,1)\}$. A character $\chi : G \to \mathbb{C}^*$ is determined by its values on the generators $g_1 = (1,0)$ and $g_2 = (0,1)$. Since both generators have order 2, necessarily $\chi(g_1)^2 = \chi(g_1^2) = \chi(0,0) = 1$ and likewise for g_2. Thus, the character's values on the generators must be either 1 or -1. This gives $2 \times 2 = 4$ possible characters, indexed by pairs $(k_1, k_2) \in \{0,1\}^2$.

The four characters χ_{k_1,k_2} are defined by their values on the generators:

$$\chi_{k_1,k_2}(1,0) = (-1)^{k_1} \qquad \text{and} \qquad \chi_{k_1,k_2}(0,1) = (-1)^{k_2}$$

From this, the value for any element $(a,b) \in G$ is $\chi_{k_1,k_2}(a,b) = (-1)^{k_1 a + k_2 b}$.

This gives the following character table, which explicitly lists the functions that form our new "basis":

$\hat{G}$	**(0,0)**	**(1,0)**	**(0,1)**	**(1,1)**
χ_{00}	1	1	1	1
χ_{10}	1	-1	1	-1
χ_{01}	1	1	-1	-1
χ_{11}	1	-1	-1	1

The orthogonality relation from proposition 53.4.5 can be checked directly. Computing $\langle \chi_{10}, \chi_{11} \rangle$:

$$\begin{aligned}
\langle \chi_{10}, \chi_{11} \rangle &= \sum_{g \in G} \chi_{10}(g)\overline{\chi_{11}(g)} \\
&= \chi_{10}(0,0)\chi_{11}(0,0) + \chi_{10}(1,0)\chi_{11}(1,0) + \chi_{10}(0,1)\chi_{11}(0,1) + \chi_{10}(1,1)\chi_{11}(1,1) \\
&= (1)(1) + (-1)(-1) + (1)(-1) + (-1)(1) \\
&= 1 + 1 - 1 - 1 = 0
\end{aligned}$$

Using the above example, let us change perspectives on how to interpret this change of basis. The function $f : G \to \mathbb{C}$ takes the "points" $g \in G$ and maps them (continuously) to the complex numbers, and those points are evaluated by the Riesz representation of f against the indicator functions that form an orthonormal basis. But the characters give another orthogonal basis for $\mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C})$ against which the inner product can be taken, orthonormal once scaled by $1/\sqrt{|G|}$. The characters $\chi \in \hat{G}$ may thus be read as points in their own right: points carrying "phase" information rather than the "location" information that the indicator functions carry. This motivates the following definition:

Definition 53.4.7: Fourier Transform (Gelfand Transform)

Let G be a finite abelian group with the discrete topology. Then the *Fourier transform* is:

$$(\widehat{-}) : \mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C}) \to \mathrm{Hom}_{\mathbf{Top}}(\hat{G}, \mathbb{C}) \qquad f \mapsto (\chi \mapsto \langle f, \chi \rangle)$$

where the image of f is often written as:

$$\hat{f}(\chi) = \langle f, \chi \rangle = \sum_{g \in G} f(g)\overline{\chi(g)}$$

The name *Gelfand transform* comes from the fact that the Fourier transform is traditionally about real periodic functions, or Lebesgue measurable functions. It was not until later that Pontryagin, van Kampen, Weil and Gelfand generalized it to the context of locally compact abelian groups, where the above is the special case where G is finite.

Now, certainly as vector spaces $\mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C}) \cong_{\mathbb{C}} \mathrm{Hom}_{\mathbf{Top}}(\hat{G}, \mathbb{C})$ mapping:

$$(g \mapsto \langle f, \delta_g \rangle) \mapsto (\chi \mapsto \langle f, \chi \rangle)$$

But does this map preserve the inner product, and more so can the convolution product of $\mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C})$ be preserved given the appropriate choice of product on $\mathrm{Hom}_{\mathbf{Top}}(\hat{G}, \mathbb{C})$? The answer is yes, and can be thought of as the corner-stone result of harmonic analysis on discrete abelian groups:

Theorem 53.4.8: Fourier Reciprocity

The map given in definition 53.4.7 is a $\mathbb{C}$-algebra isomorphism,

$$(\mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C}), +, *) \cong (\mathrm{Hom}_{\mathbf{Top}}(\hat{G}, \mathbb{C}), +, \cdot)$$

with $\cdot$ in $(\mathrm{Hom}_{\mathbf{Top}}(\hat{G}, \mathbb{C}), +, \cdot)$ being point-wise multiplication. It scales the inner product by $|G|$, so the normalisation $\mathcal{U}(f) = \frac{1}{\sqrt{|G|}}\hat{f}$ is unitary.

Recall that unitary means $\langle \hat{f}, \hat{g} \rangle = \langle f, g \rangle$. In a conventional real analysis course:

- the $\mathbb{C}$-algebra homomorphism is called the *Convolution Theorem*,
- the unitary property is called *Plancherel's Theorem*,
- invertibility (i.e. bijectivity) is called the *Fourier Inversion Theorem*.

***Proof*:**

1. *1. Linearity:* Let $f, h \in \mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C})$ and $a, b \in \mathbb{C}$.

$$\begin{aligned}
\widehat{af+bh}(\chi) &= \langle af+bh, \chi\rangle && \text{by definition}\\
&= \sum_{g\in G}(af+bh)(g)\overline{\chi(g)}\\
&= a\sum_{g\in G} f(g)\overline{\chi(g)} + b\sum_{g\in G} h(g)\overline{\chi(g)} && \text{by linearity of sums}\\
&= a\langle f,\chi\rangle + b\langle h,\chi\rangle\\
&= a\hat{f}(\chi) + b\hat{h}(\chi)
\end{aligned}$$

Since this holds for all $\chi \in \hat{G}$, the transform is a linear map.

2. $\mathbb{C}$-algebra Homomorphism (The Convolution Theorem): We must show that the Fourier transform converts convolution into pointwise multiplication.

$$\begin{aligned}
\widehat{f*h}(\chi) &= \langle f*h, \chi\rangle\\
&= \sum_{k\in G}(f*h)(k)\overline{\chi(k)} && \text{by definition of inner product}\\
&= \sum_{k\in G}\left(\sum_{g\in G} f(g)h(g^{-1}k)\right)\overline{\chi(k)} && \text{by definition of convolution}\\
&= \sum_{g\in G} f(g)\sum_{k\in G} h(g^{-1}k)\overline{\chi(k)} && \text{swapping order of summation}
\end{aligned}$$

Let $\ell = g^{-1}k$, so $k = g\ell$. As k runs over G, so does ℓ. The inner sum becomes:

$$\sum_{\ell\in G} h(\ell)\overline{\chi(g\ell)} = \sum_{\ell\in G} h(\ell)\overline{\chi(g)\chi(\ell)} = \overline{\chi(g)}\sum_{\ell\in G} h(\ell)\overline{\chi(\ell)} = \overline{\chi(g)}\hat{h}(\chi)$$

Substituting this back into the main expression:

$$\begin{aligned}
\widehat{f*h}(\chi) &= \sum_{g\in G} f(g)\left(\overline{\chi(g)}\hat{h}(\chi)\right)\\
&= \hat{h}(\chi)\sum_{g\in G} f(g)\overline{\chi(g)}\\
&= \hat{h}(\chi)\hat{f}(\chi)
\end{aligned}$$

Thus, $\widehat{f*h} = \hat{f}\cdot\hat{h}$, proving the map is an algebra homomorphism.

3. Isomorphism (The Fourier Inversion Theorem): We show the map is invertible by constructing its inverse. Let $\mathcal{F}(f) = \hat{f}$. We claim the inverse is given by $\mathcal{F}^{-1}(\hat{f})(g) =$

$\frac{1}{|G|}\sum_{\chi\in\hat{G}}\hat{f}(\chi)\chi(g)$.

$$\begin{aligned}
\frac{1}{|G|}\sum_{\chi\in\hat{G}}\hat{f}(\chi)\chi(g) &= \frac{1}{|G|}\sum_{\chi\in\hat{G}}\left(\sum_{h\in G} f(h)\overline{\chi(h)}\right)\chi(g) && \text{by definition of } \hat{f}\\
&= \frac{1}{|G|}\sum_{h\in G} f(h)\sum_{\chi\in\hat{G}}\chi(g)\overline{\chi(h)} && \text{swapping order of summation}\\
&= \frac{1}{|G|}\sum_{h\in G} f(h)\sum_{\chi\in\hat{G}}\chi(gh^{-1})
\end{aligned}$$

The inner sum is an example of the *Second Orthogonality Relation* and is a standard exercise the reader should do. In particular, the sum of all characters evaluated at a group element (giving all powers of a certain root of unity) is $|G|$ if the element is e and 0 otherwise. Thus $\sum_{\chi\in\hat{G}}\chi(gh^{-1}) = |G|\delta_{g,h}$.

$$\frac{1}{|G|}\sum_{h\in G} f(h)(|G|\delta_{g,h}) = \sum_{h\in G} f(h)\delta_{g,h} = f(g)$$

Since we can recover f uniquely from $\hat{f}$, the map is an isomorphism.

4. Unitary Property (Plancherel's Theorem): Note that here is where the transform picks up a factor of $|G|$, and so where the normalising constant is forced. Let us calculate the inner product for the given definition.

$$\begin{aligned}
\langle\hat{f},\hat{h}\rangle_{\hat{G}} &= \sum_{\chi\in\hat{G}}\hat{f}(\chi)\overline{\hat{h}(\chi)}\\
&= \sum_{\chi\in\hat{G}}\left(\sum_{g\in G} f(g)\overline{\chi(g)}\right)\overline{\left(\sum_{k\in G} h(k)\overline{\chi(k)}\right)}\\
&= \sum_{\chi\in\hat{G}}\left(\sum_{g\in G} f(g)\overline{\chi(g)}\right)\left(\sum_{k\in G}\overline{h(k)}\chi(k)\right)\\
&= \sum_{g\in G}\sum_{k\in G} f(g)\overline{h(k)}\sum_{\chi\in\hat{G}}\chi(k)\overline{\chi(g)} && \text{re-arranging terms}\\
&= \sum_{g\in G}\sum_{k\in G} f(g)\overline{h(k)}(|G|\delta_{g,k}) && \text{by Second Orthogonality}\\
&= |G|\sum_{g\in G} f(g)\overline{h(g)}\\
&= |G|\langle f,h\rangle_G
\end{aligned}$$

This proves *Plancherel's Theorem.* To make the map strictly unitary, one must normalize the transform. If we define the unitary transform $\mathcal{U}(f) = \frac{1}{\sqrt{|G|}}\hat{f}$, then it follows immediately that $\langle\mathcal{U}(f),\mathcal{U}(h)\rangle = \langle f,h\rangle$, completing the proof.

Example 53.4.9: Fourier Transform

Take $G = \mathbb{Z}/2\mathbb{Z} \times \mathbb{Z}/2\mathbb{Z}$ from example 53.4.6. Now for the Fourier transform of a concrete function. Let $f = \delta_{(1,0)}$, so that $f(1,0) = 1$ and is zero elsewhere. This is a basis vector in the standard "position" basis, and its coordinates in the character basis come from computing $\hat{f}(\chi) = \langle f, \chi \rangle$ for each character.

$$\begin{aligned}\hat{f}(\chi) = \langle \delta_{(1,0)}, \chi \rangle &= \sum_{g \in G} \delta_{(1,0)}(g)\overline{\chi(g)} \\ &= 1 \cdot \overline{\chi(1,0)} + 0 + 0 + 0 = \chi(1,0)\end{aligned}$$

The character table gives this value for each χ:

- $\hat{f}(\chi_{00}) = \chi_{00}(1,0) = 1$
- $\hat{f}(\chi_{10}) = \chi_{10}(1,0) = -1$
- $\hat{f}(\chi_{01}) = \chi_{01}(1,0) = 1$
- $\hat{f}(\chi_{11}) = \chi_{11}(1,0) = -1$

Thus, the original function $f = \delta_{(1,0)}$, which is a spike at one point in the "position" basis, has been transformed into a new function $\hat{f}$ on $\hat{G}$ with values $(1, -1, 1, -1)$.

Recall the inversion formula from the proof of theorem 53.4.8: $f(g) = \frac{1}{|G|} \sum_{\chi \in \hat{G}} \hat{f}(\chi)\chi(g)$ (here $|G| = 4$). Let's check the value at $g = (1,0)$:

$$\begin{aligned}f(1,0) &= \frac{1}{4}\left(\hat{f}(\chi_{00})\chi_{00}(1,0) + \hat{f}(\chi_{10})\chi_{10}(1,0) + \hat{f}(\chi_{01})\chi_{01}(1,0) + \hat{f}(\chi_{11})\chi_{11}(1,0)\right) \\ &= \frac{1}{4}\left((1)(1) + (-1)(-1) + (1)(1) + (-1)(-1)\right) \\ &= \frac{1}{4}(1+1+1+1) = 1\end{aligned}$$

Now the value at $g = (0,1)$, which should be 0:

$$\begin{aligned}f(0,1) &= \frac{1}{4}\left(\hat{f}(\chi_{00})\chi_{00}(0,1) + \hat{f}(\chi_{10})\chi_{10}(0,1) + \hat{f}(\chi_{01})\chi_{01}(0,1) + \hat{f}(\chi_{11})\chi_{11}(0,1)\right) \\ &= \frac{1}{4}\left((1)(1) + (-1)(1) + (1)(-1) + (-1)(-1)\right) \\ &= \frac{1}{4}(1-1-1+1) = 0\end{aligned}$$

This now connects to representation theory. So far, for a finite abelian group G, the Fourier transform has been established as a unitary $\mathbb{C}$-algebra isomorphism between the algebra of functions on G with convolution, $(\mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C}), *)$, and the algebra of functions on the dual group $\hat{G}$ with pointwise multiplication. The representation theory perspective shows that Fourier analysis is the simplest case of an Artin-Wedderburn decomposition. The key is to view the $\mathbb{C}$-group algebra $\mathbb{C}[G]$ with the natural G-action given by left multiplication (convolution), namely $\rho : G \to \mathrm{GL}(\mathbb{C}[G])$ given by:

$$\rho(g) : f \mapsto g * f$$

From this viewpoint, the study of the $\mathbb{C}$-algebra $(\mathbb{C}[G], +, *)$ and the $\mathbb{C}[G]$-module $\mathbb{C}[G]$ is the same thing that is the study of the regular representation of G. Now, this representation can be broken down into the direct sum of 1-dimensional irreducible representations. Namely, for a finite abelian group, the set of irreducible representations is exactly the dual group: $\mathrm{Irr}(G) = \widehat{G}$, giving:

$$\mathbb{C}[G] \cong \bigoplus_{\chi \in \widehat{G}} V_\chi$$

where each V_χ is a 1-dimensional subspace corresponding to the character χ.

This decomposition is made concrete by the Fourier transform. The Fourier Inversion Formula, $f = \frac{1}{|G|} \sum_{\chi \in \hat{G}} \hat{f}(\chi)\chi$, is the literal expression of this decomposition. It writes the function f as a sum of components, where each term $\hat{f}(\chi)\chi$ is the projection of f onto the 1-dimensional irreducible subspace V_χ. Then the fourier coefficient $\hat{f}(\chi)$ is the coordinate of f in the irreducible component corresponding to χ.

The projection functions $p_\chi = \frac{1}{|G|} \sum_{g \in G} \overline{\chi(g)} g$ can be constructed inside $\mathbb{C}[G]$, and project onto the irreducible subspace V_χ. Convolving any function f with p_χ annihilates all other "frequency components", leaving the part of f that lies in V_χ.

Hence, the Fourier basis is *the* basis that diagonalizes the natural action of the group on its own algebra of functions.

If G is a *non-abelian* finite group, the identification $\mathrm{Irr}(G) = \hat{G}$ breaks and with it the simple transform: $\mathrm{Hom}(G, S^1)$ remains a group, but it only sees the abelianisation $\widehat{G^{\mathrm{ab}}}$, while the object one wants, $\mathrm{Irr}(G)$, carries no natural group structure. However, the representation theory perspective remains: the generalized Fourier transform (given by the *Peter-Weyl Theorem*) decomposes a function f on the group into a sum of *matrix coefficients* corresponding to these higher-dimensional matrix representations.

53.4.1 Generalization to Locally Compact Abelian Groups

What happens for abelian groups like $(\mathbb{R}, +)$, $(\mathbb{Z}, +)$, or the circle group $(S^1, \cdot)$? These are examples of *Locally Compact Abelian (LCA)* groups. Moving from the finite to the infinite setting means replacing finite sums with integrals, and integrating on an arbitrary group first requires a notion of "volume" or "measure". The shape of the answer is already visible in the finite case: read the delta functions δ_h as *measures*, and every f becomes a sum of weighted point masses. The right object, then, is a measure on the group that the group operation cannot see. The essential new ingredient is the *Haar measure*. For any LCA group G, there exists a measure μ that gives a consistent way to integrate functions on the group.

Definition 53.4.10: Haar Measure

A *Haar measure* on an LCA group G is a measure μ on the Borel σ-algebra of G that is left-translation-invariant. That is, for any measurable set $E \subseteq G$ and any element $g \in G$:

$$\mu(gE) = \mu(E)$$

This measure is unique up to a positive scaling constant. For abelian groups, it is also right-translation-invariant.

See [82] for details on how to construct such a measure on any LCA that is unique up to scaling. This measure is the direct generalization of taking the order of the group.

Example 53.4.11: Haar Measure

1. For a finite group with the discrete topology, the Haar measure is the counting measure, and $\mu(G) = |G|$.
2. For $(\mathbb{R}, +)$, the Haar measure is the standard Lebesgue measure dx.
3. For $(S^1, \cdot)$, the Haar measure can be taken as $d\theta$.
4. For $(\mathbb{Z}, +)$, the Haar measure is again the counting measure.

In the infinite case points can no longer be represented by indicator functions; the *Dirac delta distributions* take on that role instead. See [80] for the theory of distributions.

With the Haar measure in hand, the main objects of study can be redefined by replacing every sum over G with an integral with respect to $d\mu$.

1. *The Group Algebra $L^1(G)$:* The space of all functions becomes too large. The natural replacement for the convolution algebra $\mathbb{C}[G]$ is the space of absolutely integrable functions, $L^1(G, d\mu)$. For two functions $f, h \in L^1(G)$, their convolution is defined by the integral:

$$(f * h)(g) = \int_G f(x)h(x^{-1}g)d\mu(x)$$

   This space $(L^1(G), +, *)$ forms a Banach algebra.

2. *The Dual Group $\widehat{G}$:* It was proven that the correct codomain should be S^1. The dual group is the set of all *continuous* group homomorphisms into S^1.

$$\widehat{G} = \mathrm{Hom}_{\mathbf{Top}}(G, S^1)$$

   The dual group $\widehat{G}$ is itself an LCA group. It is crucial to note that, unlike the finite case, $G \cong \widehat{G}$ is the exception rather than the rule, holding for $\mathbb{R}$ but failing for $\mathbb{Z}$ and S^1:

$$\widehat{\mathbb{R}} \cong \mathbb{R}, \qquad \widehat{\mathbb{Z}} \cong S^1, \qquad \widehat{S^1} \cong \mathbb{Z}$$

   This highlights why it is essential to treat $\hat{G}$ as a distinct space. The theory that governs this relationship is *Pontryagin Duality*, which states that the double-dual is canonically isomorphic to the original group: $\widehat{\widehat{G}} \cong G$.

3. *The Fourier Transform:* The definition of the Fourier transform is the direct analogue of the finite case, replacing the sum with an integral. For a function $f \in L^1(G) \cap L^2(G)$, its Fourier transform is a function $\hat{f}$ on the dual group $\hat{G}$:

$$\hat{f}(\chi) = \int_G f(g)\overline{\chi(g)}d\mu(g)$$

   Similarly, the inner product that defines the Hilbert space structure on $L^2(G)$ is:

$$\langle f, h\rangle = \int_G f(g)\overline{h(g)}d\mu(g)$$

With these definitions, the entire suite of theorems proven in the finite case carries over:

Theorem 53.4.12: Fourier Reciprocity on LCA Groups

Let G be an LCA group with Haar measure μ. Then there exists a unique Haar measure ν on the dual group $\widehat{G}$ for which the following hold. (Unlike the finite case these are statements about two different maps: $L^2(G) \to L^2(\widehat{G})$ is a unitary isomorphism, while $L^1(G) \to C_0(\widehat{G})$ is an injective algebra map that is not onto.)

1. *The Fourier Inversion Theorem:* For a sufficiently well-behaved function f (e.g., $f \in L^1 \cap L^2$ such that $\hat{f} \in L^1$), the original function can be recovered by an integral over the dual group:
$$f(g) = \int_{\widehat{G}} \hat{f}(\chi)\chi(g)d\nu(\chi)$$
2. *Plancherel's Theorem:* The Fourier transform extends uniquely from $L^1 \cap L^2$ to a unitary isomorphism of Hilbert spaces, $\mathcal{F} : L^2(G,\mu) \to L^2(\widehat{G},\nu)$. This means it preserves the inner product:
$$\langle \hat{f}, \hat{h} \rangle_{L^2(\widehat{G})} = \langle f, h \rangle_{L^2(G)}$$
3. *The Convolution Theorem:* For $f, h \in L^1(G)$, the Fourier transform maps convolution to pointwise multiplication:
$$\widehat{f * h}(\chi) = \hat{f}(\chi) \cdot \hat{h}(\chi)$$

***Proof*:**
This is the Pontryagin duality theorem; a full proof via the Gelfand transform belongs to the harmonic analysis of locally compact abelian groups and is not reproduced in this starred section.

The correspondence between the finite and general LCA settings can be summarized as follows:

Finite Abelian Case	**LCA Case**
Group G	LCA Group G
Order $\lvert G\rvert$	Haar Measure μ
Group Algebra $\mathbb{C}[G]$	Banach Algebra $L^1(G,\mu)$
Hilbert Space $\mathrm{Hom}(G,\mathbb{C})$	Hilbert Space $L^2(G,\mu)$
Summation $\sum_{g\in G}$	Integration $\int_G d\mu(g)$
Dual Group $\widehat{G} = \mathrm{Hom}(G,\mathbb{C}^\times)$	Dual Group $\widehat{G} = \mathrm{Hom}_{\mathbf{Top}}(G,S^1)$
Inner Product $\sum f(g)\overline{h(g)}$	Inner Product $\int f(g)\overline{h(g)}d\mu(g)$
Fourier Transform $\sum f(g)\overline{\chi(g)}$	Fourier Transform $\int f(g)\overline{\chi(g)}d\mu(g)$

Further interesting facts can be found here: https://mathoverflow.net/questions/37021/is-fourier-analysis-a-special-case-of-representation-theory-or-an-analogue

53.4.2 The Algebraic-Geometric Meaning of the Dual Group

In algebraic geometry, a fundamental principle is that the geometry of a space can be recovered from its algebra of functions. For an affine space k^n over an algebraically closed k, the corresponding

algebra is the polynomial ring $k[x_1, \dots, x_n]$, and the Nullstellensatz makes the points of the space correspond to the maximal ideals of this algebra. (Over a non-closed field the correspondence fails: $(x^2+1) \subseteq \mathbb{R}[x]$ is maximal and is no point of $\mathbb{R}^1$.) Specifically, for any point $p = (a_1, \dots, a_n) \in k^n$, the evaluation map:

$$\mathrm{ev}_p : k[x_1, \dots, x_n] \to k \qquad f \mapsto f(p)$$

is an algebra homomorphism whose kernel, $m_p = (x_1 - a_1, \dots, x_n - a_n)$, is a maximal ideal. The quotient $k[x_1, \dots, x_n]/m_p \cong k$ recovers the value of the function at that point.

A similar setup is now in place for a finite abelian group G, with the convolution algebra $(\mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C}), *, +)$ taking the role of the function algebra. A natural question arises: can we recover the "points" of our space from the maximal ideals of this algebra? Let's first attempt a direct analogy, assuming the points are the elements of the group G itself. For a point $g_i \in G$ there is a point-evaluation map, which is linear:

$$\mathrm{ev}_{g_i} : \mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C}) \to \mathbb{C} \qquad f \mapsto f(g_i)$$

The kernel of this map is the vector subspace of functions that are zero at g_i. However, for this subspace to be an ideal, it must be closed under convolution. Let $f \in \ker(\mathrm{ev}_{g_i})$ (so $f(g_i) = 0$) and let h be any function in our algebra. Consider their convolution:

$$(h * f)(g_i) = \sum_{k \in G} h(k) f(k^{-1} g_i)$$

The value of f at other points, $f(k^{-1}g_i)$, can be non-zero, and in fact the subspace really does fail to be an ideal. Take $G = \mathbb{Z}/2\mathbb{Z} = \{e, a\}$ and $g_i = e$. Then $\delta_a \in \ker(\mathrm{ev}_e)$, but $\delta_a * \delta_a = \delta_{a^2} = \delta_e$, which is 1 at e. So the kernel of the point-evaluation map is *not* an ideal with respect to convolution. This implies the points of G do not correspond to the maximal ideals of its convolution algebra.

The key insight is that the correct "geometric points" for the convolution algebra are not the elements of G, but the characters of the dual group $\widehat{G}$.

Proposition 53.4.13: Characters and Maximal Ideals

Let G be a finite abelian group. The maximal ideals of the convolution algebra $(\mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C}), +, *)$ are in bijective correspondence with the characters $\chi \in \widehat{G}$.

***Proof*:**

For each character $\chi \in \widehat{G}$, define a Fourier evaluation map:

$$\widehat{\mathrm{ev}}_\chi : \mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C}) \to \mathbb{C} \qquad f \mapsto \hat{f}(\chi)$$

This map takes a function and returns its Fourier coefficient at the frequency χ. By 53.4.8 $\widehat{\mathrm{ev}}_\chi$ is a $\mathbb{C}$-algebra homomorphism. Since $\widehat{\mathrm{ev}}_\chi$ is a surjective algebra homomorphism onto a field ($\mathbb{C}$), its kernel, which we denote by I_χ, is a maximal ideal:

$$I_\chi = \ker(\widehat{\mathrm{ev}}_\chi) = \{f \in \mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C}) \,|\, \hat{f}(\chi) = 0\}$$

By the First Isomorphism Theorem for rings, we have:

$$\mathrm{Hom}_{\mathbf{Top}}(G, \mathbb{C})/I_\chi \cong \mathbb{C}$$

This shows that every character $\chi \in \widehat{G}$ defines a maximal ideal. Conversely, after applying the Fourier transform we get the usual multiplication and ring structure, and then an approach similar to the Gelfand-Kolmogorov theorem gives the desired result.

> For the infinite case the same picture holds with one caveat: $L^1(G, \mu)$ is non-unital unless G is discrete, carrying only an approximate identity, so it is the maximal *modular* ideals that correspond to the homomorphisms into $\mathbb{C}$ (via the *Gelfand-Mazur Theorem*, which identifies the quotient by such an ideal with $\mathbb{C}$).

Thus, with the convolution algebra $\mathbb{C}[G]$ as our primary object, the natural geometric space that emerges is not the group G itself, but its Pontryagin dual, $\widehat{G}$. The Fourier transform is the mechanism that allows us to evaluate the functions of our algebra at the points of this "true" underlying space. This perspective, generalized by Gelfand, is the foundation of non-commutative geometry.

Concepts	**Classical Algebraic Geometry**
Algebra	Polynomial Ring $(k[x_1, \dots, x_n], \cdot)$
Product	Polynomial Multiplication
Geometric Space	Affine Space k^n
A "Point" p	A tuple $(a_1, \dots, a_n) \in k^n$
Evaluation Map	$\text{ev}_p : f \mapsto f(p)$
Maximal Ideal for p	$\ker(\text{ev}_p) = (x_i - a_i)$

Concepts	**Harmonic Analysis on G**
Algebra	Group Algebra $(\mathbb{C}[G], *)$
Product	Convolution
Geometric Space	The Dual Group $\widehat{G}$
A "Point" p	A character $\chi \in \widehat{G}$
Evaluation Map	Fourier "Evaluation" $\widehat{\text{ev}}_\chi : f \mapsto \hat{f}(\chi)$
Maximal Ideal for p	$\ker(\widehat{\text{ev}}_\chi) = I_\chi$

53.5⋆ Modular Representations and the Failure of Semisimplicity

⋆ *Optional. This section is an aside; nothing later in the book depends on it.*

Two chapters have approached $k[G]$ from opposite sides. Chapter 53 has assumed throughout that $\text{char}(k) \nmid |G|$, where theorem 53.1.9 makes every module semisimple and the character theory of section 53.2 computes what the modules are. Chapter 52 built machinery for algebras where semisimplicity fails: the radical $\text{Jac}(A)$ measuring the failure, Krull-Schmidt replacing simple summands by indecomposable ones, and projective covers replacing the projections that no longer exist. The group algebra $k[G]$ with $\text{char}(k) = p$ dividing $|G|$ is the object that machinery was built for, and this section applies it.

There is a temptation to read theorem 53.1.9 as having settled the characteristic-p case. The condition $p \big| |G|$ does say exactly when semisimplicity fails,[7] and example 52.1.11 computed the resulting radical for $G = \mathbb{Z}/p\mathbb{Z}$ down to the last element. What the theorem does not say is what replaces the semisimple picture when it fails, and that question, for a general finite group, is open. The subject

[7] Theorem 53.1.9 gives one direction. The other is quick: the element $\nu = \sum_{g \in G} g$ satisfies $h\nu = \nu = \nu h$ for every $h \in G$, so $k\nu$ is a two-sided ideal, and $\nu^2 = |G|\nu = 0$ when p divides $|G|$. Since $k[G]$ is finite dimensional it is left Artinian, so a nonzero nilpotent ideal forces $\text{Jac}(k[G]) \neq 0$ by theorem 52.1.8, and $k[G]$ is not semisimple by corollary 52.1.10.

devoted to it is *modular representation theory*, treated in *Modular Representation Theory* [36]. The word *modular* here refers to reduction modulo a prime and has nothing to do with modular forms or with the modular arithmetic of $\mathbb{Z}/n\mathbb{Z}$.

It is worth being precise about what is open, because the framework is not. Krull-Schmidt (theorem 52.2.4) applies to $k[G]$ for any field, so the regular module has a decomposition into indecomposable summands that is unique up to isomorphism and reordering, theorem 52.3.5 matches those summands with the simple modules, and theorem 52.3.7 identifies them as the projective covers. The structural questions are answered. What is not known, for a general G and p, are the *invariants*: the dimensions and characters of the simple $k[G]$-modules. Determining them for the symmetric groups is a well-known open problem. Worse, the indecomposable modules themselves are unclassifiable for most groups, in a sense theorem 53.5.7 below makes precise.

We begin with the coarsest decomposition of $k[G]$, which costs nothing beyond chapter 52 and already organizes everything that follows.

Definition 53.5.1: Block of an Algebra

Let A be a finite-dimensional k-algebra and let $Z(A)$ denote its centre. A *block idempotent* of A is a primitive idempotent of the algebra $Z(A)$, and for such an idempotent b the two-sided ideal $B = bA$ is called a *block* of A.

The word *block* is overworked, and three of its meanings have already appeared in this book. A Jordan block is a matrix in the normal form of example 52.2.6; the Artin-Wedderburn factors $M_{n_i}(D_i)$ of a semisimple algebra are called blocks in the statement of theorem 52.3.5; and definition 53.5.1 is the sense used from here on. The last two agree on semisimple algebras, where the block idempotents are exactly the identity elements of the Artin-Wedderburn factors, so no earlier statement changes meaning. They diverge as soon as $\mathrm{Jac}(A) \neq 0$, which is the case this section is about.[8]

Theorem 53.5.2: Block Decomposition

Let A be a finite-dimensional k-algebra. Then the identity has a decomposition

$$1 = b_1 + b_2 + \cdots + b_m$$

into pairwise orthogonal primitive idempotents of $Z(A)$, and this decomposition is unique up to reordering. The corresponding blocks give a direct sum decomposition

$$A = b_1 A \oplus b_2 A \oplus \cdots \oplus b_m A$$

of A into two-sided ideals, each of which is a k-algebra with identity element b_i. Every indecomposable left A-module M satisfies $M = b_i M$ for exactly one index i, and every block contains at least one simple module in this sense.

***Proof*:**
Existence. The centre $Z(A)$ is a commutative k-algebra, and it is finite dimensional because A is. Applying theorem 52.3.2 to the algebra $Z(A)$ gives a decomposition $1 = b_1 + \cdots + b_m$ of its

[8]The eponym is also overworked. Richard Brauer's name attaches both to the block theory of this section and to the Brauer group of section 51.3. The two objects are unrelated.

identity, which is the identity of A, into pairwise orthogonal primitive idempotents of $Z(A)$.

The decomposition of A. Each b_i is central, so $b_iA = Ab_i$ is a two-sided ideal, and it is closed under multiplication with b_i acting as a two-sided identity on it. Since the b_i are orthogonal with sum 1, every $a \in A$ satisfies $a = \sum_i b_i a$ with $b_i a \in b_i A$, and if $\sum_i b_i a_i = 0$ then multiplying by b_j gives $b_j a_j = 0$ for each j. The sum is therefore direct.

Uniqueness. Let $1 = c_1 + \cdots + c_l$ be a second such decomposition. For each i we have $b_i = \sum_j b_i c_j$, and each $b_i c_j$ is an idempotent of $Z(A)$ because b_i and c_j are commuting idempotents. These are pairwise orthogonal, since $(b_i c_j)(b_i c_{j'}) = b_i c_j c_{j'} = 0$ for $j \neq j'$. Primitivity of b_i forces exactly one summand to be nonzero, so $b_i = b_i c_j$ for a unique j, which is to say $b_i \leq c_j$ in the sense that $b_i c_j = b_i$. Running the same argument with the roles reversed gives, for that j, a unique i' with $c_j = c_j b_{i'}$. Then $b_i = b_i c_j$ and $c_j = c_j b_{i'}$ give $b_i b_{i'} = b_i c_j b_{i'} = b_i c_j = b_i \neq 0$, and orthogonality of distinct b's forces $i' = i$, whence $b_i = b_i c_j = c_j b_i = c_j$. So $i \mapsto j$ is a bijection matching the two decompositions.

Modules. Let M be an indecomposable left A-module. Each $b_i M$ is a submodule, because b_i is central: for $a \in A$ we have $a(b_i m) = b_i(am)$. The identity acts as the identity map on M, so $M = \sum_i b_i M$, and the sum is direct by the same orthogonality computation as above. Indecomposability leaves exactly one nonzero summand, so $M = b_i M$ for exactly one i.

Each block has a simple module. The map $A \to b_i A$, $a \mapsto b_i a$, is a surjective ring homomorphism, since b_i is a central idempotent, and it carries 1 to the identity b_i of $b_i A$. Now $b_i A$ is a nonzero finite-dimensional algebra, so it has a maximal left ideal and hence a simple module S. Pulling back along the surjection makes S a simple A-module with $b_i S = S$.

The theorem says that the study of $k[G]$-modules splits, with no loss and no overlap, into m independent problems, one per block. This is the first thing one does with a modular group algebra, and it is why the literature speaks of the representation theory "of a block".

The blocks of $k[G]$ can be located without factoring the algebra, which is what makes them computable. Each block idempotent b_i is central, so multiplication by b_i is an endomorphism of any A-module, and on a simple module it is either 0 or the identity because it is idempotent. A simple module is indecomposable, so theorem 53.5.2 gives $S = b_i S$ for exactly one index i: one block idempotent acts as the identity on S and the rest act as zero, which is what it means for S to belong to that block. Suppose now that k is a splitting field for G, so that $\mathrm{End}_{k[G]}(S) = k$ for every simple S. Then Schur's lemma makes every central element act on S by a scalar, and the resulting k-algebra map $\omega_S : Z(k[G]) \to k$ is called the *central character* of S. By the previous paragraph ω_S determines the block of S, since it returns 1 on that block's idempotent and 0 on the others. Now the class sums $\sigma_1, \ldots, \sigma_s$, one for each conjugacy class of G, form a k-basis of $Z(k[G])$ over any field: each σ_i is central because conjugation permutes each class, the σ_i are linearly independent because the group elements are, and $\sum_g \lambda_g g$ is central exactly when $g \mapsto \lambda_g$ is constant on conjugacy classes. That is the computation carried out inside the proof of proposition 53.1.13, which used nothing about the characteristic of the field. Every b_i is therefore a k-combination of class sums, so two simple modules whose central characters agree on every class sum lie in the same block. The criterion is a statement about the simple modules in characteristic p, which are themselves the unknowns. What turns block-finding into arithmetic with the ordinary character table is Brauer's refinement, which runs the test on the *ordinary* irreducible characters instead. For an ordinary irreducible χ and a class sum σ_C with representative g_C, the relevant scalar is

$$\omega_\chi(\sigma_C) = \frac{|C|\,\chi(g_C)}{\chi(1)}$$

an algebraic integer. Ordinary irreducible characters are sorted into blocks of $k[G]$ because the block idempotents lift from $k[G]$ to $R[G]$ once a p-modular system is fixed (definition 53.5.4), and two ordinary irreducibles lie in the same block when these scalars agree for every class modulo a maximal ideal above p. The division by $\chi(1)$ is not optional: for a simple module of dimension 1 a class sum acts by the plain sum of the scalars, and dropping the normalization for a character of higher degree gives the wrong answer. Example 53.5.3 uses the degree-1 shortcut precisely because both of its simple modules are one dimensional and are reductions of ordinary representations.

For a semisimple algebra the decomposition is the Artin-Wedderburn one and nothing is gained. The content is in the opposite direction: when $\mathrm{Jac}(A) \neq 0$ a single block can carry many simple modules, and untangling them is the work.

Example 53.5.3: The Blocks of $k[S_3]$ in Characteristic 3

Let k be a field with $\mathrm{char}(k) = 3$ and let $G = S_3$, so $p = 3$ divides $|G| = 6$ and theorem 53.1.9 does not apply. The centre $Z(k[S_3])$ has the three class sums as a basis:

$$\sigma_1 = e, \qquad \sigma_2 = (1\ 2) + (1\ 3) + (2\ 3), \qquad \sigma_3 = (1\ 2\ 3) + (1\ 3\ 2)$$

Write $N = \{e, (1\ 2\ 3), (1\ 3\ 2)\}$ for the normal subgroup of order 3, generated by $c = (1\ 2\ 3)$, and let I be the ideal of $k[S_3]$ generated by $c - 1$, which is two-sided because N is normal. By the computation of example 52.1.11 with $p = 3$ we have $(c-1)^3 = c^3 - 1 = 0$, so I is nilpotent. For any simple $k[S_3]$-module S the subset IS is a submodule, and nilpotency of I forces $IS \neq S$, so $IS = 0$ and N acts trivially on S. The simple $k[S_3]$-modules are therefore exactly the simple modules of

$$k[S_3/N] \cong k[\mathbb{Z}/2\mathbb{Z}]$$

inflated along the quotient map. Since $\mathrm{char}(k) = 3$ does not divide 2, theorem 53.1.9 makes $k[\mathbb{Z}/2\mathbb{Z}]$ semisimple, and $t^2 - 1 = (t-1)(t+1)$ has distinct roots, so $k[\mathbb{Z}/2\mathbb{Z}] \cong k \times k$. Hence $k[S_3]$ has exactly two simple modules, both of dimension 1: the trivial module $\mathbb{1}$ and the sign module sgn. In particular both are absolutely simple, so k is a splitting field and the central characters above are defined.

To locate them we compute central characters. Both simple modules are one dimensional, so a group element g acts on S by the scalar $\chi_S(g)$ and a class sum acts by the sum of those scalars over the class. The three-cycles are even permutations, so

$$\omega_{\mathbb{1}}(\sigma_2) = 3 \cdot 1 = 0, \qquad \omega_{\mathrm{sgn}}(\sigma_2) = 3 \cdot (-1) = 0, \qquad \omega_{\mathbb{1}}(\sigma_3) = \omega_{\mathrm{sgn}}(\sigma_3) = 2 \cdot 1 = 2$$

all computed in k, where $3 = 0$, and $\omega(\sigma_1) = 1$ for both. The two central characters agree on every class sum, so $\mathbb{1}$ and sgn lie in the same block. Every block contains a simple module by theorem 53.5.2, so there is no room for a second: $k[S_3]$ has exactly one block, itself.

This is the phenomenon the section is about. In characteristic 0 the algebra $\mathbb{C}[S_3]$ splits into three Artin-Wedderburn factors, one per irreducible character of example 53.2.8, and each factor is a matrix algebra that can be understood on its own. In characteristic 3 the algebra does not split at all, and the two simple modules are bound together in a single block, so the algebra is indecomposable as an algebra.

Having fixed the coarse decomposition, we turn to the numerical invariants. The first was already defined in general in definition 52.3.8, and the group algebra is its intended application: the Cartan matrix of $k[G]$ has entries $C_{ij} = [P_i : S_j]$, the multiplicity of the simple module S_j among the

composition factors of the projective cover of S_i. In characteristic 0 this matrix is the identity, because $P_i = S_i$ for a semisimple algebra, and it carries no information. In characteristic p it records how far the projectives are from the simples.

Computing it from the definition means knowing the projective modules, which is exactly what one does not have at the outset. The second invariant is what makes it accessible, and it is the one Brauer's program is built on. It compares characteristic p with characteristic 0 directly. Doing this properly requires a p-modular system: a complete discrete valuation ring R with residue field k of characteristic p and fraction field F of characteristic 0, chosen large enough that both $F[G]$ and $k[G]$ split. A finitely generated $F[G]$-module then contains an R-lattice stable under G, and reducing that lattice modulo the maximal ideal produces a $k[G]$-module. The composition factors of the reduction do not depend on which lattice was chosen, a theorem of Brauer and Nesbitt, and this independence is what makes the following definition well posed.

Definition 53.5.4: Decomposition Matrix

Let (F, R, k) be a splitting p-modular system for G, let $T_1, \dots, T_s$ be the simple $F[G]$-modules and $S_1, \dots, S_r$ the simple $k[G]$-modules. The *decomposition matrix* of G at p is the $s \times r$ matrix $D = (d_{ij})$ of nonnegative integers where d_{ij} is the multiplicity of S_j as a composition factor of the reduction, modulo the maximal ideal of R, of a full G-stable R-lattice in T_i. The lattice must be full, meaning that it spans T_i over F, or the reduction has the wrong dimension. The reduction is taken modulo the maximal ideal of R and not modulo p, because R is typically ramified over $\mathbb{Z}_p$, in which case the two differ.

The rows of D are indexed by the ordinary irreducible characters, which section 53.2 computes, and the columns by the modular simple modules, which are the unknowns. Each row records how one ordinary irreducible breaks up when reduced. This is Brauer's idea in one sentence: the characteristic-0 theory is completely understood, so the characteristic-p theory should be reachable by reduction, and D is the matrix that records the reduction. What makes the idea pay is that D determines the Cartan matrix of definition 52.3.8 outright.

Theorem 53.5.5: Cartan Matrix, Decomposition Matrix, and p-Regular Classes

Let (F, R, k) be a splitting p-modular system for G, with decomposition matrix D and Cartan matrix C. Then

$$C = D^{\mathsf{T}} D$$

In particular C is symmetric. Moreover the number of simple $k[G]$-modules equals the number of p-regular conjugacy classes of G, where a conjugacy class is p-regular when the order of its elements is prime to p.

We state these without proof. The first is a statement about the three Grothendieck groups attached to (F, R, k) and the maps c, d and e between them, the configuration known as the *cde triangle*: the relation $C = D^{\mathsf{T}} D$ is the matrix form of the factorization $c = de$ together with the fact that e is the transpose of d over a splitting system. The second is a separate theorem of Brauer, proved without the triangle. Developing that machinery needs the theory of lattices over a complete discrete valuation ring and the Brauer characters built from it, which is where [36] begins. Complete treatments are in Serre's *Linear Representations of Finite Groups* [90, Part III] and Webb's *A Course in Finite Group Representation Theory* [100, Chs. 9 and 10].

The counting statement is already enough to check the earlier computation. The 3-regular classes of S_3 are those whose elements have order prime to 3, namely $\{e\}$ and the class of transpositions, so there are two of them, matching the two simple modules found in example 53.5.3. It also puts the characteristic-0 count of proposition 53.1.13 in context: over $\mathbb{C}$ the number of simple modules is the number of *all* conjugacy classes, and passing to characteristic p discards exactly the classes of order divisible by p.

Example 53.5.6: The Decomposition and Cartan Matrices of S_3 at $p = 3$

The ordinary irreducible characters of S_3 are the trivial character $\chi_{\mathbb{1}}$, the sign character χ_{sgn}, and a character $\chi^{\perp}$ of degree 2. The first two are read off example 53.2.8, and $\chi^{\perp}$ is constructed in example 53.2.19 as the character of the complement $V^{\perp}$ of the trivial summand in the permutation representation, with $\chi^{\perp}(e) = 2$, $\chi^{\perp}((1\ 2)) = 0$ and $\chi^{\perp}((1\ 2\ 3)) = -1$. The two simple $k[S_3]$-modules are $S_1 = \mathbb{1}$ and $S_2 = \mathrm{sgn}$, both of dimension 1, as computed in example 53.5.3. Take the p-modular system $(F, R, k) = (\mathbb{Q}_3, \mathbb{Z}_3, \mathbb{F}_3)$, which is splitting for S_3: all three ordinary irreducibles are realizable over $\mathbb{Q}$, the degree-2 one by the explicit rational basis of example 53.2.19, and they stay irreducible after extending scalars to $\mathbb{C}$, so they are absolutely irreducible. Both modular simples are one dimensional, hence absolutely simple, so theorem 53.5.5 applies.

Reducing modulo 3, the trivial and sign representations are already defined over k and remain simple, so they contribute the rows $(1, 0)$ and $(0, 1)$. The representation $V^{\perp}$ reduces to a module M of dimension 2. Both simple modules are one dimensional, so M has exactly two composition factors, each S_1 or S_2. Taking determinants of the matrices of the group action identifies which. A permutation matrix has determinant the sign of the permutation, so the degree-three permutation representation has determinant sgn, and its trivial summand contributes 1, leaving $\det V^{\perp} = \mathrm{sgn}$. The determinant is a polynomial with integer coefficients in the matrix entries, so it commutes with reducing those entries modulo the maximal ideal, giving $\det M = \mathrm{sgn}$ as a character valued in k. In a basis adapted to a composition series the matrices are block triangular, so the determinant of a module is the product of the determinants of its composition factors, and the two factors of M have determinants multiplying to sgn. Two copies of S_1 would give $\mathbb{1}$ and two copies of S_2 would give $\mathrm{sgn}^2 = \mathbb{1}$, and $\mathrm{sgn} \neq \mathbb{1}$ over k because $\mathrm{char}(k) = 3 \neq 2$. So the factors are one S_1 and one S_2, giving the row $(1, 1)$. Hence

$$D = \begin{pmatrix} 1 & 0 \\ 0 & 1 \\ 1 & 1 \end{pmatrix} \qquad \text{and} \qquad D^{\mathsf{T}} D = \begin{pmatrix} 1 & 0 & 1 \\ 0 & 1 & 1 \end{pmatrix} \begin{pmatrix} 1 & 0 \\ 0 & 1 \\ 1 & 1 \end{pmatrix} = \begin{pmatrix} 2 & 1 \\ 1 & 2 \end{pmatrix}$$

so by theorem 53.5.5 the Cartan matrix of $k[S_3]$ is

$$C = \begin{pmatrix} 2 & 1 \\ 1 & 2 \end{pmatrix}$$

Reading the entries back: $C_{11} = [P_1 : S_1] = 2$ and $C_{12} = [P_1 : S_2] = 1$, so the projective cover of the trivial module has three composition factors and dimension 3. That is a check on the whole computation, since theorem 52.3.5 gives $k[S_3] = P_1 \oplus P_2$ with each P_i appearing $\dim_k S_i = 1$ time, and $3 + 3 = 6 = \dim_k k[S_3]$.

Two features of C are general. It is symmetric, which holds for any group algebra over a splitting field and fails for finite-dimensional algebras at large. And $\det C = 4 - 1 = 3$ is a power of p, which is also always true. Here it happens to equal the order of a Sylow 3-subgroup of S_3.

Note what the computation used: the ordinary character table, which is classical, and one piece of genuinely modular information, the way $\chi^{\perp}$ breaks up. That is the general shape of the problem.

Brauer's program provides information of exactly this kind, and it does not solve the problem. The relation $C = D^{\mathsf{T}}D$ determines C from D, and the counting theorem fixes the number of columns of D, but nothing here computes the entries of D itself. For the symmetric groups those entries are unknown in general.

The final obstruction is of a different kind, and it explains why the subject computes invariants and does not attempt a classification of modules.

Theorem 53.5.7: Higman's Theorem on Finite Representation Type

Let p be a prime, let k be a field of characteristic p, and let G be a finite group. Then $k[G]$ has only finitely many isomorphism classes of indecomposable modules if and only if the Sylow p-subgroups of G are cyclic.

The proof reduces to the case of a p-group and then to the two extremes, and it is given in [100, Theorem 11.4.3]. The negative half is the striking one. As soon as a Sylow p-subgroup fails to be cyclic it has $\mathbb{Z}/p\mathbb{Z} \times \mathbb{Z}/p\mathbb{Z}$ as a quotient, and $k[\mathbb{Z}/p\mathbb{Z} \times \mathbb{Z}/p\mathbb{Z}]$ already has infinitely many indecomposable modules, of unbounded dimension. For such a group the phrase "classify the modules" has no reasonable answer, and the invariants of this section are what one computes instead. Contrast this with chapter 52, where Krull-Schmidt guaranteed a unique decomposition into indecomposables: the guarantee is real, and it does not imply that the list of indecomposables is finite or knowable.

What survives is a body of conjectures relating the invariants of a block to the structure of an associated p-subgroup, its *defect group*. Two of them are among the central open problems of the subject.

Conjecture 53.5.8: Alperin's Weight Conjecture

Let k be an algebraically closed field of characteristic p and G a finite group. A *weight* is a pair (Q, S) with Q a p-subgroup of G and S a simple projective $k[N_G(Q)/Q]$-module. Then the number of simple modules in a p-block of $k[G]$ equals the number of G-conjugacy classes of weights belonging to that block.

Conjecture 53.5.9: Broué's Abelian Defect Group Conjecture

Let k be an algebraically closed field of characteristic p, and let B be a block of $k[G]$ whose defect group P is abelian. Let B' be the Brauer correspondent of B, a block of $k[N_G(P)]$. Then the bounded derived categories of B and B' are equivalent as triangulated categories.

Neither statement is self-contained here: the *defect group* of a block and the *Brauer correspondent* are the central constructions of the local theory, and defining them is where [36] does its work. Both conjectures remain open as of writing, and both have been verified in many cases. Broué's conjecture is known for blocks with cyclic defect groups, and Alperin's has been reduced to a statement about finite simple groups. The subject is not static: Brauer's height zero conjecture, open since 1955, was proved in 2024, and the McKay conjecture has also been settled. Alperin's book *Local Representation Theory* [2] is the standard introduction to the local theory these conjectures live in, and Curtis and Reiner [46] remains the comprehensive reference for the subject as a whole.

A last connection. *Algebraic Groups and Representations* [41] also meets a failure of complete reducibility in characteristic p, for reductive algebraic groups, where the simple objects again carry

known labels and unknown characters. One warning about the vocabulary. That book has its own *decomposition matrix*, which records how a Weyl module $V(\lambda)$ breaks into simple modules in a single characteristic. It is a different matrix from the D of definition 53.5.4, which compares characteristic 0 with characteristic p for a finite group. The two subjects are relatives, and each owns its own side of the difficulty.

Exercise 53.5.1

1. Let P be a finite p-group and let $\mathrm{char}(k) = p$. Show that $k[P]$ has exactly one simple module, the trivial one, and exactly one block. Deduce that the Cartan matrix of $k[P]$ is the 1×1 matrix $(|P|)$.
2. Show that if $\mathrm{char}(k) \nmid |G|$ then the Cartan matrix of $k[G]$ is the identity matrix, and that the blocks of $k[G]$ are exactly the Artin-Wedderburn factors of theorem 51.2.16. Which step fails when $\mathrm{char}(k)$ divides $|G|$?
3. Repeat example 53.5.6 for S_3 at $p = 2$. Show that there are two simple $k[S_3]$-modules, of dimensions 1 and 2, compute the decomposition matrix, and deduce the Cartan matrix. Check that $\det C$ is again the order of a Sylow 2-subgroup.
4. Using theorem 53.5.7, determine for which primes p the group algebra $k[A_5]$ has finite representation type, where $\mathrm{char}(k) = p$ and $|A_5| = 60$.

54

Quiver Representations and Path Algebras

A quiver is a directed graph, and a representation of a quiver assigns a vector space to each vertex and a linear map to each arrow. A single vertex carrying a single loop gives a vector space with one endomorphism, and two vertices joined by two parallel arrows give a pair of linear maps between the same two spaces. Every finite-dimensional representation is a finite direct sum of indecomposable ones, so the indecomposable representations are the objects to classify. For the loop they include a nilpotent Jordan block of every size, and their list is infinite over every field. Chapter 53 ended with the same phenomenon for group algebras: in characteristic p, the algebra $k[G]$ has only finitely many indecomposable modules exactly when the Sylow p-subgroups of G are cyclic (theorem 53.5.7).

Gabriel proved in 1972 that a connected quiver has only finitely many indecomposable representations exactly when the graph obtained by forgetting the orientation of its arrows is one of the Dynkin diagrams A_n, D_n, E_6, E_7, E_8. The dimension vectors of the indecomposable representations are then exactly the positive roots of an integral quadratic form attached to the graph, its Tits form. At a dimension vector, the Tits form is the dimension of the group of base changes acting on the representations with that dimension vector, minus the dimension of the space of these representations, and over an infinite field a quiver with finitely many indecomposables has a Tits form that is positive at every nonzero dimension vector. The proof given here that a positive definite Tits form gives finitely many indecomposables is due to Bernstein, Gelfand and Ponomarev (1973). It uses reflection functors, which carry the indecomposable representations of one orientation of a graph, other than one simple representation, to those of another, and act on dimension vectors by the reflections that permute the roots.[1] Quivers also describe algebras: the path algebra kQ has the representations of Q as its modules, and by a second theorem of Gabriel every finite-dimensional algebra over an

[1] The diagrams A_n, D_n, E_6, E_7, E_8, together with B_n, C_n, F_4 and G_2, also classify the finite-dimensional simple Lie algebras over $\mathbb{C}$ [64, §§11.4, 14.2, 18.4]. The diagrams of type A, D, E are those whose roots all have one length, the only case that quivers produce (box 54.1.44).

algebraically closed field is Morita equivalent to a quotient of a path algebra by an admissible ideal (theorem 54.2.10).

54.1 Quivers and Their Decomposition

Definition 54.1.1: Quiver

A *quiver* is a quadruple $Q = (I, E, s, t)$ consisting of a set I of *vertices*, a set E of *arrows* (also called *edges*) and two maps $s, t \colon E \to I$. An arrow e with $s(e) = i$ and $t(e) = j$ is drawn as

$$\overset{i}{\bullet} \xrightarrow{e} \overset{j}{\bullet}$$

and written $e \colon i \to j$, and the vertices $s(e)$ and $t(e)$ are its *source* and its *target*. The quiver Q is *finite* if I and E are finite sets.

A quiver is usually specified by a drawing, which leaves the maps s and t implicit. An arrow may have the same source and target, and several arrows may join the same two vertices.

Example 54.1.2: Quivers

1. The quiver with $I = \{1\}$, $E = \{e\}$ and $s(e) = t(e) = 1$ is drawn as

$$\circlearrowleft 1$$

2. The quiver with $I = \{1, 2\}$, $E = \{e\}$, $s(e) = 1$ and $t(e) = 2$ is drawn as

$$1 \xrightarrow{e} 2$$

3. The quiver with $I = \{1, 2\}$, $E = \{e, f\}$, $s(e) = t(f) = 1$ and $t(e) = s(f) = 2$ is drawn as

$$1 \underset{f}{\overset{e}{\rightleftarrows}} 2$$

Definition 54.1.3: Path and Oriented Cycle


Let $Q = (I, E, s, t)$ be a quiver.

1. A *path* of *length* $k \geq 1$ in Q is a sequence of k arrows, written from right to left as
$$\gamma = a_k a_{k-1} \cdots a_1$$
with $t(a_l) = s(a_{l+1})$ for $1 \leq l \leq k-1$, so that a_1 is traversed first. Its *source* is $s(\gamma) = s(a_1)$, its *target* is $t(\gamma) = t(a_k)$, and γ is a path *from* $s(\gamma)$ *to* $t(\gamma)$.
2. The *trivial path* at a vertex i is the path e_i of length 0, which contains no arrows and has $s(e_i) = t(e_i) = i$.
3. An *oriented cycle* is a path γ of positive length with $s(\gamma) = t(\gamma)$. An oriented cycle of length 1, that is, an arrow a with $s(a) = t(a)$, is a *loop*.


Definition 54.1.4: Sink And Source

Let $Q = (I, E, s, t)$ be a quiver, $e \in E$ and $i \in I$.

1. The arrow e is *incoming at* i if $t(e) = i$, *outgoing at* i if $s(e) = i$, and an *arrow at* i if it is incoming or outgoing at i.
2. The vertex i is a *sink* if no arrow is outgoing at i, as in



3. The vertex i is a *source* if no arrow is incoming at i, as in



4. If i is a sink or a source, then iQ denotes the quiver obtained from Q by reversing every arrow at i, that is, by exchanging the source and the target of each arrow at i.

54.1.1 Quiver Representation and Varieties

Definition 54.1.5: Quiver Representation

Let $Q = (I, E, s, t)$ be a quiver and $\mathbb{F}$ a field. A *representation* V *of* Q over $\mathbb{F}$ consists of

1. an $\mathbb{F}$-vector space $V(i)$ for each vertex $i \in I$, and
2. an $\mathbb{F}$-linear map $T_e \colon V(i) \to V(j)$ for each arrow $e \colon i \to j$.

The collection of all representations of Q over $\mathbb{F}$ is denoted $\mathrm{Rep}_{\mathbb{F}}(Q)$, or $\mathrm{Rep}(Q)$.

Example 54.1.6: Quiver Representations

1. A representation of the quiver
$$1 \xrightarrow{e} 2$$
is a pair of vector spaces $V(1)$, $V(2)$ with a linear map $T_e \colon V(1) \to V(2)$, so every linear map between two vector spaces is a representation of this quiver.

2. A representation of the quiver
$$\overset{f}{\circlearrowright}\ 1 \xrightarrow{e} 2$$
is a linear map $T_e \colon V(1) \to V(2)$ together with a linear map $T_f \colon V(2) \to V(2)$, which may be the identity or any other endomorphism of $V(2)$.

3. A representation of the quiver
$$1 \xrightarrow{e} 2 \xrightarrow{f} 3$$
is a pair of linear maps $V(1) \xrightarrow{T_e} V(2) \xrightarrow{T_f} V(3)$. Among them are the pairs exact at $V(2)$, those with $\mathrm{im}(T_e) = \ker(T_f)$. If $V(1) = V(2) = V(3)$, the two maps may be scalar multiplications. The representation $\mathbb{F} \to \mathbb{F}^2 \to \mathbb{F}$ with $T_e(x) = (x, 0)$ and $T_f(x, y) = x$ has $T_f \circ T_e = \mathrm{id}_{\mathbb{F}}$, although neither map is invertible.

Definition 54.1.7: Quiver Dimension

Let $Q = (I, E, s, t)$ be a quiver and V a representation of Q. The *dimension vector*, or *quiver dimension*, of V is the tuple
$$\dim_Q V = (\dim V(i))_{i \in I}$$
When every $V(i)$ is finite-dimensional and $I = \{1, \ldots, n\}$, it is the vector $\dim_Q V = (\dim V(1), \ldots, \dim V(n)) \in \mathbb{N}^n$.

Definition 54.1.8: Quiver Subrepresentation

Let $Q = (I, E, s, t)$ be a quiver and V a representation of Q. A *subrepresentation* W of V, written $W \subseteq V$, consists of a subspace $W(i) \subseteq V(i)$ for each vertex $i \in I$ such that $T_e(W(i)) \subseteq W(j)$ for every arrow $e\colon i \to j$. With the restricted maps $S_e = T_e|_{W(i)}\colon W(i) \to W(j)$ it is a representation of Q.

Definition 54.1.9: Quiver Morphisms

Let $Q = (I, E, s, t)$ be a quiver and let V and W be representations of Q, with maps T_e and S_e respectively. A *quiver morphism* $\varphi\colon V \to W$ is a family $\varphi = (\varphi(i))_{i \in I}$ of linear maps $\varphi(i)\colon V(i) \to W(i)$ such that for every arrow $e\colon i \to j$ the square

$$\begin{array}{ccc} V(i) & \xrightarrow{T_e} & V(j) \\ \downarrow{\scriptstyle \varphi(i)} & & \downarrow{\scriptstyle \varphi(j)} \\ W(i) & \xrightarrow{S_e} & W(j) \end{array}$$

commutes, that is, $S_e \circ \varphi(i) = \varphi(j) \circ T_e$. The set of quiver morphisms from V to W is denoted $\mathrm{Hom}_Q(V, W)$, or $\mathrm{Hom}(V, W)$ when Q is clear from the context. The composite of quiver morphisms $\varphi\colon V \to W$ and $\psi\colon W \to U$ is the family $\psi \circ \varphi = (\psi(i) \circ \varphi(i))_{i \in I}$, and the identity of V is the family $\mathrm{id}_V = (\mathrm{id}_{V(i)})_{i \in I}$.

Proposition 54.1.10: Structure Of $\mathrm{Hom}(V, W)$

Let $V, W \in \mathrm{Rep}(Q)$. Then $\mathrm{Hom}_Q(V, W)$ is a vector space over $\mathbb{F}$, with addition and scalar multiplication defined vertex by vertex.

***Proof*:**

A quiver morphism $\varphi\colon V \to W$ is the data of a linear map $\varphi(i)\colon V(i) \to W(i)$ for each vertex i, subject to the condition $S_e \circ \varphi(i) = \varphi(j) \circ T_e$ for every edge e from i to j. The collection of all vertex-indexed families of linear maps, $\prod_i \mathrm{Hom}_{\mathbb{F}}(V(i), W(i))$, is a vector space under vertexwise addition and scalar multiplication, so it suffices to show that $\mathrm{Hom}(V, W)$ is a subspace.

The zero family satisfies $S_e \circ 0 = 0 = 0 \circ T_e$, so it is a quiver morphism. If $\varphi, \psi \in \mathrm{Hom}(V, W)$ and $c \in \mathbb{F}$, then for every edge e from i to j, linearity of S_e gives

$$S_e \circ (\varphi(i) + c\psi(i)) = S_e \circ \varphi(i) + c\,(S_e \circ \psi(i)) = \varphi(j) \circ T_e + c\,(\psi(j) \circ T_e) = (\varphi(j) + c\psi(j)) \circ T_e$$

so the family $(\varphi(i) + c\psi(i))_i$ is again a quiver morphism. Hence $\mathrm{Hom}(V, W)$ contains 0 and is closed under addition and scalar multiplication, making it a subspace of $\prod_i \mathrm{Hom}_{\mathbb{F}}(V(i), W(i))$ and in particular a vector space over $\mathbb{F}$.

Example 54.1.11: Quiver Morphism

1. Let $V = \overset{\mathbb{F}}{\bullet} \xrightarrow{1} \overset{\mathbb{F}}{\bullet}$ and $W = \overset{\mathbb{F}}{\bullet} \xrightarrow{0} \overset{0}{\bullet}$ be representations of $1 \xrightarrow{e} 2$. The maps $\varphi(1) = 1$ and $\varphi(2) = 0$ form a quiver morphism $\varphi\colon V \to W$,

$$\begin{array}{ccc} V & & \mathbb{F} & \xrightarrow{1} & \mathbb{F} \\ \downarrow{\scriptstyle \varphi} & & \downarrow{\scriptstyle 1} & & \downarrow{\scriptstyle 0} \\ W & & \mathbb{F} & \xrightarrow{0} & 0 \end{array}$$

   since both composites $\mathbb{F} \to 0$ are zero. Every quiver morphism $\psi\colon W \to V$ is zero: its square at e reads $1 \circ \psi(1) = \psi(2) \circ 0 = 0$, so $\psi(1) = 0$, and $\psi(2)$ is defined on the zero space.

2. Let $V = \overset{\mathbb{R}}{\bullet} \xrightarrow{1} \overset{\mathbb{R}}{\bullet} \xrightarrow{1} \overset{\mathbb{R}}{\bullet}$ and $W = \overset{\mathbb{R}^2}{\bullet} \xrightarrow{A} \overset{\mathbb{R}^2}{\bullet} \xrightarrow{B} \overset{\mathbb{R}}{\bullet}$ be representations of $1 \to 2 \to 3$, with

$$A = \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix} \qquad B = \begin{pmatrix} 1 & 1 \end{pmatrix}$$

   The matrices $\varphi(1) = \varphi(2) = \begin{pmatrix} 1 \\ 1 \end{pmatrix}$ and $\varphi(3) = 2$ form a quiver morphism $\varphi\colon V \to W$, because $A\varphi(1) = \varphi(2) \cdot 1$ and $B\varphi(2) = 2 = \varphi(3) \cdot 1$. The matrices $\psi(1) = \psi(2) = \begin{pmatrix} 1 & 1 \end{pmatrix}$ and $\psi(3) = 1$ form a nonzero quiver morphism $\psi\colon W \to V$, because $1 \cdot \psi(1) = \psi(2)A$ and $1 \cdot \psi(2) = \psi(3)B$.

With the composites and identities of definition 54.1.9, the representations of Q form a category $\mathrm{Rep}(Q)$. For quiver morphisms $\varphi\colon V \to W$ and $\psi\colon W \to U$, where U has maps R_e, and an arrow $e\colon i \to j$, the squares of φ and ψ give

$$R_e \circ \psi(i) \circ \varphi(i) = \psi(j) \circ S_e \circ \varphi(i) = \psi(j) \circ \varphi(j) \circ T_e$$

so $\psi \circ \varphi$ is a quiver morphism. The family id_V is a quiver morphism because $T_e \circ \mathrm{id}_{V(i)} = \mathrm{id}_{V(j)} \circ T_e$, and composition is associative with the identities id_V as units because these laws hold for linear maps at each vertex. A quiver morphism is a morphism between representations of one quiver Q. A map from a quiver $Q = (I, E, s, t)$ to a quiver $Q' = (I', E', s', t')$ is a different notion, a pair of maps $m_I\colon I \to I'$ and $m_E\colon E \to E'$ with $m_I \circ s = s' \circ m_E$ and $m_I \circ t = t' \circ m_E$, and maps of quivers are not used in this chapter.

The *zero representation* 0 has the zero space at every vertex. Kernels and images of quiver morphisms are formed vertex by vertex.

Definition 54.1.12: Kernels And Images

Let $\varphi\colon V \to W$ be a quiver morphism. The *kernel* $\ker(\varphi)$ is the subrepresentation of V with $\ker(\varphi)(i) = \ker(\varphi(i))$, and the *image* $\mathrm{im}(\varphi)$ is the subrepresentation of W with $\mathrm{im}(\varphi)(i) = \mathrm{im}(\varphi(i))$, for every vertex i.

Both are subrepresentations in the sense of definition 54.1.8. Let $e\colon i \to j$ be an arrow. If $v \in \ker(\varphi(i))$, then $\varphi(j)(T_e v) = S_e(\varphi(i)v) = 0$, so T_e carries $\ker(\varphi(i))$ into $\ker(\varphi(j))$. For every $v \in V(i)$ the same square gives $S_e(\varphi(i)v) = \varphi(j)(T_e v)$, so S_e carries $\mathrm{im}(\varphi(i))$ into $\mathrm{im}(\varphi(j))$.

Definition 54.1.13: Quiver Isomorphisms

Let $V, W \in \mathrm{Rep}(Q)$. A quiver morphism $\varphi\colon V \to W$ is an *isomorphism* if there is a quiver morphism $\psi\colon W \to V$ with $\psi \circ \varphi = \mathrm{id}_V$ and $\varphi \circ \psi = \mathrm{id}_W$. The representations V and W are *isomorphic*, written $V \cong W$, if there is an isomorphism $V \to W$.

The components $\varphi(i)$ of an isomorphism are bijective, with inverses $\psi(i)$. Conversely, a quiver morphism φ whose components are all bijective is an isomorphism: composing $S_e \circ \varphi(i) = \varphi(j) \circ T_e$ with $\varphi(j)^{-1}$ on the left and with $\varphi(i)^{-1}$ on the right gives $\varphi(j)^{-1} \circ S_e = T_e \circ \varphi(i)^{-1}$, so the family $(\varphi(i)^{-1})_{i \in I}$ is a quiver morphism inverse to φ. In particular isomorphic representations have the same dimension vector.

Example 54.1.14: Quiver Isomorphism

Let Q be $1 \xrightarrow{e} 2$. Finite-dimensional representations V and W of Q, with maps T_e and S_e, are isomorphic if and only if $\dim V(1) = \dim W(1)$, $\dim V(2) = \dim W(2)$ and $\mathrm{rank}(T_e) = \mathrm{rank}(S_e)$.

If $\varphi\colon V \to W$ is an isomorphism, then $\varphi(1)$ and $\varphi(2)$ are linear isomorphisms, which gives the equalities of dimensions, and $S_e = \varphi(2) \circ T_e \circ \varphi(1)^{-1}$ has the same rank as T_e. Conversely, let $n_1 = \dim V(1)$, $n_2 = \dim V(2)$ and $r = \mathrm{rank}(T_e)$. By rank-nullity $\ker(T_e)$ has dimension $n_1 - r$, so $V(1)$ has a basis $u_1, \dots, u_{n_1}$ whose last $n_1 - r$ vectors form a basis of $\ker(T_e)$. The vectors $T_e u_1, \dots, T_e u_r$ span $\mathrm{im}(T_e)$, which has dimension r, so they are linearly independent, and they extend to a basis $T_e u_1, \dots, T_e u_r, w_{r+1}, \dots, w_{n_2}$ of $V(2)$. In these bases T_e has the matrix

$$\begin{pmatrix} I_r & 0 \\ 0 & 0 \end{pmatrix}$$

of size $n_2 \times n_1$, where I_r is the $r \times r$ identity matrix. The same construction for W gives bases in which S_e has the same matrix. The linear isomorphisms $\varphi(1)\colon V(1) \to W(1)$ and $\varphi(2)\colon V(2) \to W(2)$ that send each chosen basis vector for V to the chosen basis vector for W in the same position satisfy $S_e \circ \varphi(1) = \varphi(2) \circ T_e$, since in the chosen bases both sides have the matrix above. So φ is a quiver morphism with bijective components, hence an isomorphism. The isomorphism classes of finite-dimensional representations of Q are therefore in bijection with the triples (n_1, n_2, r) of nonnegative integers with $r \le \min(n_1, n_2)$, the triple being realized by the matrix above.

A subrepresentation has a quotient, formed vertex by vertex.

Definition 54.1.15: Quotient Representation

Let $V \in \mathrm{Rep}(Q)$ and let $W \subseteq V$ be a subrepresentation. The *quotient representation* V/W has the space $V(i)/W(i)$ at each vertex i, and along each arrow $e\colon i \to j$ the map $V(i)/W(i) \to V(j)/W(j)$, $x + W(i) \mapsto T_e(x) + W(j)$. This map is well defined because T_e carries $W(i)$ into $W(j)$, W being a subrepresentation.

Proposition 54.1.16: 1st Isomorphism for Quivers

Let $V, W \in \mathrm{Rep}(Q)$ and $\varphi\colon V \to W$ be a quiver morphism. Then:

$$\mathrm{im}(\varphi) \cong V/\ker(\varphi)$$

***Proof*:**
Write $K = \ker(\varphi)$, a subrepresentation of V (definition 54.1.12). First, the quotient V/K of definition 54.1.15 carries the edge maps induced by those of V: for an edge e from i to j, set $\overline{T}_e(v + K(i)) = T_e v + K(j)$. This is well defined, since $v \in K(i) = \ker(\varphi(i))$ gives $\varphi(j)(T_e v) = S_e(\varphi(i)v) = 0$, so $T_e v \in K(j)$. Second, S_e maps $\mathrm{im}(\varphi(i))$ into $\mathrm{im}(\varphi(j))$, since $S_e(\varphi(i)v) = \varphi(j)(T_e v)$, so the edge maps of the subrepresentation $\mathrm{im}(\varphi) \subseteq W$ are the restrictions of the S_e.

For each vertex i, define

$$\overline{\varphi}(i)\colon V(i)/K(i) \to \mathrm{im}(\varphi(i)) \qquad v + K(i) \mapsto \varphi(i)v$$

This is well defined and injective because $\varphi(i)v = \varphi(i)v'$ holds exactly when $v - v' \in \ker(\varphi(i)) = K(i)$, it is linear, and it is surjective onto $\mathrm{im}(\varphi(i))$ by construction. So each $\overline{\varphi}(i)$ is a linear isomorphism.

The family $\overline{\varphi} = (\overline{\varphi}(i))_i$ is a quiver morphism $V/K \to \mathrm{im}(\varphi)$: for every edge e from i to j and every $v \in V(i)$,

$$\overline{\varphi}(j)\left(\overline{T}_e(v + K(i))\right) = \varphi(j)(T_e v) = S_e(\varphi(i)v) = S_e\left(\overline{\varphi}(i)(v + K(i))\right)$$

where the middle equality is the commuting square for φ. Composing this identity with $\overline{\varphi}(j)^{-1}$ on the left and with $\overline{\varphi}(i)^{-1}$ on the right yields $\overline{T}_e \circ \overline{\varphi}(i)^{-1} = \overline{\varphi}(j)^{-1} \circ S_e$, so the vertexwise inverses also form a quiver morphism $\mathrm{im}(\varphi) \to V/K$. The two morphisms are mutually inverse at every vertex, so $\mathrm{im}(\varphi) \cong V/\ker(\varphi)$ (definition 54.1.13).

Definition 54.1.17: Direct Sum Of Representations

Let $V, W \in \mathrm{Rep}(Q)$, with maps T_e and S_e. The *direct sum* $V \oplus W \in \mathrm{Rep}(Q)$ has

1. the space $(V \oplus W)(i) = V(i) \oplus W(i)$ at each vertex i, and
2. the map $T_e \oplus S_e\colon V(i) \oplus W(i) \to V(j) \oplus W(j)$, $(v, w) \mapsto (T_e v, S_e w)$, along each arrow $e\colon i \to j$.

If $U_1, \ldots, U_n$ are subrepresentations of V with $V(i) = U_1(i) \oplus \cdots \oplus U_n(i)$ at every vertex i, then V is the *internal direct sum* of $U_1, \ldots, U_n$, written $V = U_1 \oplus \cdots \oplus U_n$.

An internal direct sum is isomorphic to the direct sum of its summands. For $V = U_1 \oplus U_2$, the maps $U_1(i) \oplus U_2(i) \to V(i)$, $(u_1, u_2) \mapsto u_1 + u_2$, are bijective, and they form a quiver morphism $U_1 \oplus U_2 \to V$ because $T_e(u_1 + u_2) = T_e u_1 + T_e u_2$ with $T_e u_1 \in U_1(j)$ and $T_e u_2 \in U_2(j)$. A quiver morphism with bijective components is an isomorphism, as noted after definition 54.1.13. For $n \geq 3$ summands, the vertexwise sums $U'(i) = U_1(i) \oplus \cdots \oplus U_{n-1}(i)$ form a subrepresentation U' with $V = U' \oplus U_n$, so induction on n gives $V \cong U_1 \oplus \cdots \oplus U_n$.

Definition 54.1.18: Representation Space

Let $Q = (I, E, s, t)$ be a finite quiver with $I = \{1, \dots, n\}$, and let $\underline{d} = (d_1, \dots, d_n) \in \mathbb{N}^n$. The *representation space* of dimension vector $\underline{d}$ is

$$\mathrm{Rep}(Q, \underline{d}) := \prod_{e \in E} M_{d_{t(e)} \times d_{s(e)}}(\mathbb{F})$$

A point $A = (A_e)_{e \in E}$ of $\mathrm{Rep}(Q, \underline{d})$ is the representation of Q with $\mathbb{F}^{d_i}$ at the vertex i and the matrix A_e along the arrow e, so every point is a representation with dimension vector $\underline{d}$. As a vector space, $\mathrm{Rep}(Q, \underline{d})$ has dimension $\sum_{e \in E} d_{s(e)} d_{t(e)}$.

Choosing a basis of every vertex space turns a representation with dimension vector $\underline{d}$ into a point of $\mathrm{Rep}(Q, \underline{d})$, and different choices of bases change the point by the following action.

Proposition 54.1.19: Action On The Representation Space

Let $Q = (I, E, s, t)$ be a finite quiver with $I = \{1, \dots, n\}$, let $\underline{d} \in \mathbb{N}^n$, and let $G(\underline{d}) = \prod_{i \in I} \mathrm{GL}_{d_i}(\mathbb{F})$. For $g = (g_1, \dots, g_n) \in G(\underline{d})$ and $A \in \mathrm{Rep}(Q, \underline{d})$ set

$$(g \cdot A)_e = g_{t(e)} A_e g_{s(e)}^{-1} \qquad e \in E$$

This defines an action of $G(\underline{d})$ on $\mathrm{Rep}(Q, \underline{d})$.

***Proof*:**

Each $g_{t(e)} A_e g_{s(e)}^{-1}$ is a $d_{t(e)} \times d_{s(e)}$ matrix, so $g \cdot A \in \mathrm{Rep}(Q, \underline{d})$, and the identity element $(I_{d_1}, \dots, I_{d_n})$ fixes every A. For $g, h \in G(\underline{d})$, whose product is computed vertex by vertex, and every arrow e,

$$(g \cdot (h \cdot A))_e = g_{t(e)} h_{t(e)} A_e h_{s(e)}^{-1} g_{s(e)}^{-1} = (gh)_{t(e)} A_e (gh)_{s(e)}^{-1} = ((gh) \cdot A)_e$$

because $(g_{s(e)} h_{s(e)})^{-1} = h_{s(e)}^{-1} g_{s(e)}^{-1}$. Hence $g \cdot (h \cdot A) = (gh) \cdot A$, and the formula is an action, as claimed.

Theorem 54.1.20: Isomorphism Equivalence

Let Q be a finite quiver with vertex set $I = \{1, \dots, n\}$, let $\underline{d} \in \mathbb{N}^n$, and let $G(\underline{d})$ act on $\mathrm{Rep}(Q, \underline{d})$ as in proposition 54.1.19. Two points $A, B \in \mathrm{Rep}(Q, \underline{d})$ are isomorphic representations if and only if $B = g \cdot A$ for some $g \in G(\underline{d})$. Consequently, sending the orbit of A to the isomorphism class of A is a bijection from the set of $G(\underline{d})$-orbits in $\mathrm{Rep}(Q, \underline{d})$ onto the set of isomorphism classes of representations of Q with dimension vector $\underline{d}$.

***Proof*:**

A morphism φ from the representation A to the representation B is a family of matrices $\varphi(i) \in M_{d_i}(\mathbb{F})$ with $\varphi(t(e)) A_e = B_e \varphi(s(e))$ for every arrow e (definition 54.1.9). If φ is an isomorphism with inverse ψ (definition 54.1.13), then $\psi(i)\varphi(i) = \varphi(i)\psi(i) = I_{d_i}$, so $g = (\varphi(1), \dots, \varphi(n))$ lies

in $G(\underline{d})$, and the condition reads $B_e = g_{t(e)} A_e g_{s(e)}^{-1}$, that is, $B = g \cdot A$. Conversely, if $B = g \cdot A$, then $\varphi(i) = g_i$ satisfies $\varphi(t(e))A_e = B_e\varphi(s(e))$ and $\psi(i) = g_i^{-1}$ satisfies $\psi(t(e))B_e = A_e\psi(s(e))$, so φ and ψ are mutually inverse morphisms and the two representations are isomorphic.

The map from orbits to isomorphism classes is therefore well defined and injective. For surjectivity, let V be a representation with dimension vector $\underline{d}$, choose a basis of each $V(i)$, and let A_e be the matrix of T_e in the chosen bases. The coordinate isomorphisms $V(i) \to \mathbb{F}^{d_i}$ carry each T_e to A_e, so they form an isomorphism from V to the representation A, and the isomorphism class of V is the image of the orbit of A, completing the proof.

54.1.2 Decomposing Quivers

Definition 54.1.21: Simple Representation

Let Q be a quiver. A representation $V \in \mathrm{Rep}(Q)$ is *simple*, or *irreducible*, if $V \neq 0$ and the only subrepresentations of V are 0 and V.

A finite-dimensional vector space, which is a representation of the quiver with one vertex and no arrows, is a direct sum of one-dimensional subspaces, and these are simple. For quivers with arrows this fails: example 54.1.23 below exhibits a representation that is not a direct sum of simple subrepresentations. The summands that cannot be split further are the indecomposable representations.

Definition 54.1.22: Indecomposable Representation

Let Q be a quiver. A representation $V \in \mathrm{Rep}(Q)$ is *decomposable* if there exist nonzero subrepresentations $V_1, V_2 \subseteq V$ such that

$$V \cong V_1 \oplus V_2$$

and *indecomposable* otherwise. In particular the zero representation is indecomposable.

Example 54.1.23: Simple And Indecomposable Representations

Let Q be $1 \xrightarrow{e} 2$. The representations

$$0 \xrightarrow{0} \mathbb{F} \qquad \mathbb{F} \xrightarrow{0} 0$$

have total dimension 1, so each is simple, its only subrepresentations being 0 and itself, and indecomposable, since a direct sum of two nonzero representations has total dimension at least 2. The representation $V = \mathbb{F} \xrightarrow{1} \mathbb{F}$ is not simple. Its subrepresentations are exactly 0, $0 \xrightarrow{0} \mathbb{F}$ and V, because a subrepresentation W with $W(1) = \mathbb{F}$ has $W(2) \supseteq T_e(\mathbb{F}) = \mathbb{F}$.

However, V is indecomposable. If $V \cong V_1 \oplus V_2$ with V_1 and V_2 nonzero subrepresentations, then $\dim_Q V_1 + \dim_Q V_2 = \dim_Q V = (1,1)$ with both summands nonzero, so one of V_1 and V_2 has dimension vector $(1,0)$, and the list of subrepresentations of V contains none with this dimension vector.

So a representation need not be a direct sum of simple subrepresentations: the only simple subrep-

resentation of $\mathbb{F} \xrightarrow{1} \mathbb{F}$ is $0 \xrightarrow{0} \mathbb{F}$, and no subrepresentation complements it. Every representation of finite total dimension is nevertheless a direct sum of indecomposable ones.

Theorem 54.1.24: Quiver Representation Decomposition

Let Q be a quiver and V a representation of Q with $\sum_i \dim V(i) < \infty$. Then there are finitely many indecomposable subrepresentations $U_1, \dots, U_n$ of V such that

$$V = U_1 \oplus U_2 \oplus \cdots \oplus U_n$$

***Proof*:**
Write $\mathrm{Tdim}(V) = \sum_i \dim V(i)$ for the *total dimension*, and argue by strong induction on $\mathrm{Tdim}(V)$. If V is indecomposable, then $V = V$ is the required decomposition, with a single summand. This covers every V with $\mathrm{Tdim}(V) \leq 1$, because an isomorphism $V \cong V_1 \oplus V_2$ with V_1 and V_2 nonzero would give $\mathrm{Tdim}(V) = \mathrm{Tdim}(V_1) + \mathrm{Tdim}(V_2) \geq 2$.

Suppose V is decomposable, and let $\theta\colon V_1 \oplus V_2 \to V$ be an isomorphism with V_1 and V_2 nonzero (definition 54.1.22). An isomorphism carries subrepresentations to subrepresentations, so $V_1' = \theta(V_1 \oplus 0)$ and $V_2' = \theta(0 \oplus V_2)$ are nonzero subrepresentations of V with $V(i) = V_1'(i) \oplus V_2'(i)$ at every vertex, each $\theta(i)$ being a linear isomorphism. Both total dimensions are positive and they add up to $\mathrm{Tdim}(V)$, so each is smaller than $\mathrm{Tdim}(V)$, and by the inductive hypothesis V_1' and V_2' are finite direct sums of indecomposable subrepresentations. Together these summands decompose V, completing the proof.

The indecomposable representations of $1 \to 2 \to \cdots \to n$, and with them the decompositions of all its finite-dimensional representations, are determined in example 54.1.54 below.

54.1.3 The Tits Form and Its Roots

Let $Q = (I, E, s, t)$ be a finite quiver, meaning that I and E are finite sets, with $I = \{1, \dots, n\}$, and let $\underline{d} \in \mathbb{N}^n$. By theorem 54.1.20, the isomorphism classes of representations with dimension vector $\underline{d}$ are the orbits of $G(\underline{d})$ on $\mathrm{Rep}(Q, \underline{d})$. The space $\mathrm{Rep}(Q, \underline{d})$ has dimension $\sum_{e \in E} d_{s(e)} d_{t(e)}$, the group $G(\underline{d})$ consists of invertible matrices inside a space of dimension $\sum_{i \in I} d_i^2$, and the scalar tuples $(\lambda I_{d_1}, \dots, \lambda I_{d_n})$ act trivially. A dimension count therefore suggests that, for nonzero $\underline{d}$ and over an infinite field, finitely many orbits can cover $\mathrm{Rep}(Q, \underline{d})$ only if

$$\sum_{i \in I} d_i^2 - \sum_{e \in E} d_{s(e)} d_{t(e)} \geq 1$$

and the proof of theorem 54.1.46 makes this precise with transcendence degrees. The left side is the Tits form of Q at $\underline{d}$.

Definition 54.1.25: Graph

A *graph* Γ consists of a finite set I of *vertices* and, for every pair of vertices i, j, a number $n_{ij} = n_{ji} \in \mathbb{N}$ of *edges* joining i and j. An edge joining a vertex to itself is a *loop*, two distinct vertices i, j with $n_{ij} \geq 2$ are joined by a *multiple edge*, and two distinct vertices are *adjacent* if $n_{ij} \geq 1$.

1. The *underlying graph* of a finite quiver $Q = (I, E, s, t)$ has vertex set I, with n_{ij} the number of arrows e with $\{s(e), t(e)\} = \{i, j\}$ for $i \neq j$, and n_{ii} the number of arrows with $s(e) = t(e) = i$.
2. A graph Γ' with vertex set I' and edge numbers n'_{ij} is a *subgraph* of Γ if $I' \subseteq I$ and $n'_{ij} \leq n_{ij}$ for all $i, j \in I'$. It is the *full subgraph* on I' if $n'_{ij} = n_{ij}$ for all $i, j \in I'$.
3. A *path* in Γ is a sequence $(v_1, \ldots, v_m)$ of distinct vertices, $m \geq 1$, with v_k adjacent to v_{k+1} for $1 \leq k < m$, and it *joins* v_1 and v_m. A *cycle* is a path $(v_1, \ldots, v_m)$ with $m \geq 3$ and v_m adjacent to v_1.
4. Γ is *connected* if any two vertices are joined by a path, and the *degree* of a vertex is the number of vertices adjacent to it.

Two graphs are identified when they differ only by a renaming of their vertices. Paths and cycles in a graph ignore orientation, and they are distinct from the paths and oriented cycles of a quiver (definition 54.1.3).

Definition 54.1.26: Euler And Tits Form

Let $Q = (I, E, s, t)$ be a finite quiver, and for $i \in I$ let $\alpha_i \in \mathbb{Z}^I$ be the vector with i-th coordinate 1 and all other coordinates 0, so that $x = \sum_i x_i \alpha_i$. The *Euler form* of Q is the bilinear form on $\mathbb{R}^I$ given by

$$\langle x, y \rangle = \sum_{i \in I} x_i y_i - \sum_{e \in E} x_{s(e)} y_{t(e)}$$

its *symmetrization* is $(x, y) = \langle x, y \rangle + \langle y, x \rangle$, and the *Tits form* of Q is the quadratic form $q(x) = \langle x, x \rangle = \frac{1}{2}(x, x)$. For $x \in \mathbb{Z}^I$, write $x \geq 0$ if $x_i \geq 0$ for every i, and $x \not\geq 0$ otherwise. The dimension vector $\dim_Q V$ of a finite-dimensional representation (definition 54.1.7) is a vector $\dim_Q V \geq 0$ in $\mathbb{Z}^I$.

The Euler form depends on the orientation of the arrows, but its symmetrization does not.

Proposition 54.1.27: The Tits Form Depends Only On The Underlying Graph

Let Q be a finite quiver whose underlying graph Γ has edge numbers n_{ij}. For every $x \in \mathbb{R}^I$,

$$q(x) = \sum_{i \in I} (1 - n_{ii}) x_i^2 - \sum_{\{i,j\}} n_{ij} x_i x_j$$

where the second sum runs over the unordered pairs of distinct vertices, and

$$(\alpha_i, \alpha_i) = 2 - 2n_{ii} \qquad (\alpha_i, \alpha_j) = -n_{ij} \text{ for } i \neq j$$

In particular q and $(\ ,\ )$ depend only on Γ. The same formulas define the *Tits form* q_Γ and the symmetric form $(\ ,\ )_\Gamma$ of an arbitrary graph Γ.

***Proof*:**
In $\sum_e x_{s(e)} x_{t(e)}$, each of the n_{ii} loops at i contributes x_i^2, and each of the n_{ij} arrows between distinct vertices i and j contributes $x_i x_j$, whichever its direction. This gives the formula for $q(x) = \langle x, x \rangle$. For the symmetric form, $\langle \alpha_i, \alpha_j \rangle = \delta_{ij} - a_{ij}$, where a_{ij} is the number of arrows from i to j, so $(\alpha_i, \alpha_j) = 2\delta_{ij} - a_{ij} - a_{ji}$. For $i = j$ this is $2 - 2n_{ii}$, and for $i \neq j$ it is $-n_{ij}$. Neither formula involves the direction of an arrow, completing the proof.

Example 54.1.28: Euler And Tits Forms

1. Let Q be $1 \xrightarrow{e} 2 \xrightarrow{f} 3$ and Q' be $1 \xleftarrow{e} 2 \xrightarrow{f} 3$. Their Euler forms

$$\langle x, y \rangle_Q = \sum_{i=1}^{3} x_i y_i - x_1 y_2 - x_2 y_3 \qquad \langle x, y \rangle_{Q'} = \sum_{i=1}^{3} x_i y_i - x_2 y_1 - x_2 y_3$$

   differ, since $\langle \alpha_1, \alpha_2 \rangle_Q = -1$ while $\langle \alpha_1, \alpha_2 \rangle_{Q'} = 0$, but both Tits forms equal $x_1^2 + x_2^2 + x_3^2 - x_1 x_2 - x_2 x_3$, as proposition 54.1.27 predicts. Completing squares,

$$q(x) = \left(x_1 - \tfrac{1}{2} x_2\right)^2 + \left(x_3 - \tfrac{1}{2} x_2\right)^2 + \tfrac{1}{2} x_2^2$$

   so $q(x) > 0$ for every nonzero $x \in \mathbb{R}^3$: the right side vanishes only if $x_2 = 0$, and then $x_1 = x_3 = 0$.

2. Let K be the *Kronecker quiver*, with two arrows a, b from 1 to 2. Its underlying graph has $n_{12} = 2$, and $q(x) = x_1^2 + x_2^2 - 2x_1 x_2 = (x_1 - x_2)^2$ vanishes at $x = \alpha_1 + \alpha_2$. For this dimension vector, $\mathrm{Rep}(K, (1,1)) = \mathbb{F}^2$, and $(g_1, g_2) \in \mathbb{F}^\times \times \mathbb{F}^\times$ sends (A_a, A_b) to $(g_2 g_1^{-1} A_a, g_2 g_1^{-1} A_b)$. The orbit of a nonzero point is the set of nonzero points of the line through it, so over an infinite field there are infinitely many orbits.

Gabriel's theorem singles out the first family of graphs below. The second family carries vectors at which the Tits form vanishes.

Definition 54.1.29: Dynkin and Extended Dynkin Diagrams

For integers $a, b, c \geq 1$, the *star* $T(a, b, c)$ is the graph consisting of a central vertex and three paths of a, b and c vertices, its *arms*, with the first vertex of each arm adjacent to the central vertex, consecutive vertices of each arm adjacent, and no other edges. The graphs below have no loops and no multiple edges, except $\tilde{A}_0$ and $\tilde{A}_1$.

1. The *Dynkin diagrams of type A, D, E* are the path A_n on n vertices ($n \geq 1$), $D_n = T(1, 1, n-3)$ ($n \geq 4$), $E_6 = T(1, 2, 2)$, $E_7 = T(1, 2, 3)$ and $E_8 = T(1, 2, 4)$, drawn in fig. 54.1. The subscript is the number of vertices.

2. The *extended Dynkin diagrams* are the following graphs. The graph $\tilde{A}_0$ is one vertex with one loop, $\tilde{A}_1$ is two vertices joined by two edges, and $\tilde{A}_n$ ($n \geq 2$) is the cycle on $n+1$ vertices. The graph $\tilde{D}_4$ is a central vertex adjacent to four further vertices, and for $n \geq 5$ the graph $\tilde{D}_n$ is a path $(v_1, \ldots, v_{n-3})$ together with two further vertices adjacent to v_1 and two further vertices adjacent to v_{n-3}. Finally, $\tilde{E}_6 = T(2, 2, 2)$, $\tilde{E}_7 = T(1, 3, 3)$ and $\tilde{E}_8 = T(1, 2, 5)$. The subscript is one less than the number of vertices.

Each extended Dynkin diagram $\hat{\Gamma}$ carries the vector $\delta_{\hat{\Gamma}}$, with one positive integer for each vertex, recorded in fig. 54.2. Every entry of $\delta_{\tilde{A}_n}$ is 1. The four vertices of $\tilde{D}_n$ of degree one carry 1, and the others carry 2. In $\tilde{E}_6$, $\tilde{E}_7$ and $\tilde{E}_8$ the central vertex carries 3, 4 and 6 respectively. Read away from the central vertex, each arm of $\tilde{E}_6$ carries $2, 1$. The arm of $\tilde{E}_7$ with one vertex carries 2, and its two arms with three vertices carry $3, 2, 1$. The arms of $\tilde{E}_8$ with one, two and five vertices carry 3, then $4, 2$, then $5, 4, 3, 2, 1$.




Figure 54.1: The Dynkin diagrams of type A, D, E




Figure 54.2: The extended Dynkin diagrams, each vertex labelled by its entry of δ

Each Dynkin diagram of type A, D, E is an extended Dynkin diagram with one vertex removed, and the vector δ of the larger graph writes the Tits form of the larger graph as a sum of squares.

Lemma 54.1.30: Null Vectors Of The Extended Dynkin Diagrams

Let $\hat{\Gamma}$ be an extended Dynkin diagram with vertex set $\hat{I}$, edge numbers n_{ij} and vector $\delta = \delta_{\hat{\Gamma}}$ (definition 54.1.29).

1. $(\delta, \alpha_i) = 0$ for every $i \in \hat{I}$, and $q(\delta) = 0$.
2. If $\hat{\Gamma} \neq \tilde{A}_0$, then for every $x \in \mathbb{R}^{\hat{I}}$

$$q(x) = \frac{1}{2} \sum_{\{i,j\}} n_{ij} \delta_i \delta_j \left(\frac{x_i}{\delta_i} - \frac{x_j}{\delta_j} \right)^2$$

the sum running over the unordered pairs of distinct vertices. Hence $q(x) \geq 0$, with equality if and only if x is a real multiple of δ.

***Proof*:**

1. For $\tilde{A}_0$, the single vertex has $(\alpha_1, \alpha_1) = 2 - 2 = 0$ by proposition 54.1.27, so $(\delta, \alpha_1) = 0$. Every other extended Dynkin diagram is loopless, and proposition 54.1.27 gives $(\delta, \alpha_i) = 2\delta_i - \sum_{j \neq i} n_{ij}\delta_j$, so the claim is that twice each entry of δ equals the sum of the entries at the adjacent vertices, each counted n_{ij} times. For $\tilde{A}_1$ this reads $2 \cdot 1 = 2 \cdot 1$, and for $\tilde{A}_n$ with $n \geq 2$ every vertex has two adjacent vertices and $2 \cdot 1 = 1 + 1$. In $\tilde{D}_n$, a vertex of degree one is adjacent only to a vertex carrying 2, and $2 \cdot 1 = 2$. For $n = 4$ the central vertex gives $2 \cdot 2 = 1 + 1 + 1 + 1$. For $n \geq 5$ the vertices v_1 and v_{n-3} are distinct, each is adjacent to two vertices carrying 1 and to one v_k, and $2 \cdot 2 = 1 + 1 + 2$, while each v_k with $1 < k < n - 3$ gives $2 \cdot 2 = 2 + 2$. In $\tilde{E}_6$, $\tilde{E}_7$ and $\tilde{E}_8$, the entries along each arm, preceded by the central entry and followed by 0, form an arithmetic progression, namely $3, 2, 1, 0$, then $4, 2, 0$ and $4, 3, 2, 1, 0$, then $6, 3, 0$ and $6, 4, 2, 0$ and $6, 5, 4, 3, 2, 1, 0$. Each arm vertex is adjacent exactly to its two neighbours in this progression (the 0 standing for no vertex), so twice its entry is the sum of theirs. At the central vertex, $2 \cdot 3 = 2 + 2 + 2$, $2 \cdot 4 = 2 + 3 + 3$ and $2 \cdot 6 = 3 + 4 + 5$. Finally, $q(\delta) = \frac{1}{2}(\delta, \delta) = \frac{1}{2}\sum_i \delta_i(\delta, \alpha_i) = 0$.

2. Now $\hat{\Gamma}$ has no loops, so $(x, x) = 2\sum_i x_i^2 - 2\sum_{\{i,j\}} n_{ij}x_i x_j$ by proposition 54.1.27. Part (1) gives $2\delta_i = \sum_{j \neq i} n_{ij}\delta_j$ for every i, and every δ_i is positive, so

$$2\sum_i x_i^2 = \sum_i \frac{x_i^2}{\delta_i} \sum_{j \neq i} n_{ij}\delta_j = \sum_{\{i,j\}} n_{ij} \left(\frac{\delta_j}{\delta_i} x_i^2 + \frac{\delta_i}{\delta_j} x_j^2 \right)$$

Therefore

$$(x, x) = \sum_{\{i,j\}} n_{ij} \left(\frac{\delta_j}{\delta_i} x_i^2 - 2x_i x_j + \frac{\delta_i}{\delta_j} x_j^2 \right) = \sum_{\{i,j\}} n_{ij}\delta_i\delta_j \left(\frac{x_i}{\delta_i} - \frac{x_j}{\delta_j} \right)^2$$

and halving gives the formula for $q(x)$. Every term is nonnegative, so $q(x) \geq 0$. If $q(x) = 0$, then $x_i/\delta_i = x_j/\delta_j$ for all adjacent i and j. The graph $\hat{\Gamma}$ is connected, so following a path from a fixed vertex shows that x_i/δ_i takes a single value t at every vertex, and $x = t\delta$. Conversely $q(t\delta) = t^2 q(\delta) = 0$ by part (1), completing the proof.

Lemma 54.1.31: Graphs Without Extended Dynkin Subgraphs

Let Γ be a connected graph, loops and multiple edges allowed, that contains none of the extended Dynkin diagrams as a subgraph. Then Γ is one of A_n $(n \geq 1)$, D_n $(n \geq 4)$, E_6, E_7, E_8.

***Proof*:**

Step 1: no loops, multiple edges or cycles. A loop at a vertex i, with the vertex i, is a subgraph $\tilde{A}_0$, and two of the edges of a multiple edge, with their two vertices, form a subgraph $\tilde{A}_1$. If $(v_1, \ldots, v_m)$ is a cycle, then these vertices, with the edges joining v_k to v_{k+1} and v_m to v_1, form a subgraph $\tilde{A}_{m-1}$. So Γ has no loops, no multiple edges and no cycles, and it is determined by its adjacency relation.

Step 2: every degree is at most 3. A vertex adjacent to four distinct vertices forms, with them

and the four edges, a subgraph $\tilde{D}_4$.

Step 3: at most one vertex has degree 3. Suppose $u \neq w$ both have degree 3, and choose a path $(u = v_1, \ldots, v_r = w)$, with $r \geq 2$, by connectedness. Choose two vertices $a \neq b$ adjacent to u and different from v_2, and two vertices $c \neq d$ adjacent to w and different from v_{r-1}. The vertex a is not on the path: $a \neq v_1$ because there are no loops, $a \neq v_2$ by choice, and $a = v_k$ with $k \geq 3$ would make $(v_1, \ldots, v_k)$ a cycle. The same holds for b, c and d. If $a = c$, then $(v_1, \ldots, v_r, a)$ is a cycle, since a is adjacent to v_r and to v_1, and similarly $a \neq d$, $b \neq c$, $b \neq d$. So the $r + 4$ vertices $v_1, \ldots, v_r, a, b, c, d$ are distinct, and with the edges of the path and the edges ua, ub, wc, wd they form a subgraph $\tilde{D}_{r+3}$, which is excluded.

Step 4: if no vertex has degree 3*, then* $\Gamma = A_n$. Choose a path $(v_1, \ldots, v_m)$ in Γ with m as large as possible. Suppose a vertex y is not among $v_1, \ldots, v_m$, choose a path $(y = w_1, \ldots, w_p = v_1)$, and let w_q be the first of its vertices among $v_1, \ldots, v_m$. Then $q \geq 2$, and $x = w_{q-1}$ is not among $v_1, \ldots, v_m$ and is adjacent to $w_q = v_k$ for some k. If $k = 1$ or $k = m$, adding x at that end gives a longer path, and if $1 < k < m$, then v_k is adjacent to v_{k-1}, v_{k+1} and x. Both are impossible, so the path contains every vertex. An edge joining v_i to v_j with $j \geq i+2$ would make $(v_i, \ldots, v_j)$ a cycle, so the edges are exactly those joining v_k to v_{k+1}, and $\Gamma = A_m$.

Step 5: if exactly one vertex z *has degree* 3*, then* Γ *is a star.* Let x_1, x_2, x_3 be the vertices adjacent to z, and let Γ' be the full subgraph on the vertices other than z. Every vertex $y \neq z$ is joined to some x_l by a path in Γ': in a path from y to z in Γ, the vertex before z is some x_l, and the part from y to x_l avoids z. No path in Γ' joins x_l to $x_{l'}$ with $l \neq l'$, since such a path followed by z would be a cycle in Γ. For $l = 1, 2, 3$, let C_l be the set of vertices joined to x_l by a path in Γ'. If $y \in C_l \cap C_{l'}$ with $l \neq l'$, take paths from x_l to y and from y to $x_{l'}$ in Γ', and let y' be the first vertex of the first path lying on the second. The first path up to y', followed by the second path from y', is a path in Γ' joining x_l to $x_{l'}$, which is excluded. So the sets C_1, C_2, C_3 are disjoint and cover the vertices other than z. No edge joins two of them: if $y \in C_l$ is adjacent to y', then a path from x_l to y, extended by y' or cut at y' if it already passes through y', joins x_l to y', so $y' \in C_l$. The full subgraph on each C_l is connected, has no cycle, and has every degree at most 2, so by the argument of Step 4 it is a path. In it, x_l has degree at most 1, because x_l has degree at most 2 in Γ and one of its edges goes to z, so x_l is an end of that path. Writing a_l for the number of vertices of C_l, $\Gamma = T(a_1, a_2, a_3)$.

Step 6: the arms. Order the arms so that $a_1 \leq a_2 \leq a_3$. If $a_1 \geq 2$, the central vertex and the first two vertices of each arm form a subgraph $T(2, 2, 2) = \tilde{E}_6$. If $a_1 = 1$ and $a_2 \geq 3$, the central vertex, the arm with one vertex and the first three vertices of the other arms form $T(1, 3, 3) = \tilde{E}_7$. If $a_1 = 1$, $a_2 = 2$ and $a_3 \geq 5$, the first five vertices of the longest arm give $T(1, 2, 5) = \tilde{E}_8$. The remaining possibilities are $T(1, 1, a_3) = D_{a_3+3}$, $T(1, 2, 2) = E_6$, $T(1, 2, 3) = E_7$ and $T(1, 2, 4) = E_8$. With Steps 2 to 5, every case has been treated, completing the proof.

Theorem 54.1.32: Positive Definite Forms And Dynkin Diagrams

Let Γ be a connected graph with vertex set I, loops and multiple edges allowed, and Tits form q. The following are equivalent.

1. Γ is one of the Dynkin diagrams A_n $(n \geq 1)$, D_n $(n \geq 4)$, E_6, E_7, E_8.
2. q is positive definite, that is, $q(x) > 0$ for every nonzero $x \in \mathbb{R}^I$.
3. $q(x) > 0$ for every nonzero $x \in \mathbb{Z}^I$ with $x \geq 0$.

***Proof*:**

1. *(1) implies (2).* Each graph in (1) is the full subgraph of an extended Dynkin diagram $\hat{\Gamma} \neq \tilde{A}_0$ on all its vertices but one, i_0. Removing a vertex of $\tilde{A}_n$ leaves the path A_n. Removing a vertex of degree one from $\tilde{D}_4$ leaves $T(1,1,1) = D_4$, and removing one of the two vertices of degree one adjacent to v_1 from $\tilde{D}_n$, $n \geq 5$, leaves the star with central vertex v_{n-3}, two arms with one vertex, and the arm $v_{n-4}, \dots, v_1$ followed by the other vertex of degree one adjacent to v_1, with $n-3$ vertices, which is $T(1,1,n-3) = D_n$. Removing the last vertex of an arm with two vertices of $\tilde{E}_6 = T(2,2,2)$, of an arm with three vertices of $\tilde{E}_7 = T(1,3,3)$, or of the arm with five vertices of $\tilde{E}_8 = T(1,2,5)$ leaves E_6, E_7 or E_8. For $x \in \mathbb{R}^I$ let $\hat{x} \in \mathbb{R}^{\hat{I}}$ agree with x on I and vanish at i_0. As Γ is the full subgraph on $I = \hat{I} \setminus \{i_0\}$, the formula of proposition 54.1.27 gives $q_\Gamma(x) = q_{\hat{\Gamma}}(\hat{x})$, every term involving i_0 being 0. By lemma 54.1.30(2), $q_\Gamma(x) \geq 0$, with equality only if $\hat{x} = t\delta$ for some $t \in \mathbb{R}$. In that case $0 = \hat{x}_{i_0} = t\delta_{i_0}$ with $\delta_{i_0} > 0$, so $t = 0$ and $x = 0$. Hence q_Γ is positive definite.
2. *(2) implies (3).* Every nonzero $x \in \mathbb{Z}^I$ is a nonzero vector of $\mathbb{R}^I$.
3. *(3) implies (1).* Suppose Γ is not one of the graphs in (1). By lemma 54.1.31, Γ has a subgraph Γ' that is an extended Dynkin diagram, with vertex set $I' \subseteq I$ and edge numbers $n'_{ij} \leq n_{ij}$. Let $\delta = \delta_{\Gamma'}$, and let $x \in \mathbb{Z}^I$ agree with δ on I' and vanish elsewhere, so $x \geq 0$ and $x \neq 0$. Only the vertices of I' contribute to the formula of proposition 54.1.27, and every product $\delta_i \delta_j$ is positive, so

$$q_\Gamma(x) = \sum_{i \in I'} (1 - n_{ii})\delta_i^2 - \sum_{\{i,j\} \subseteq I'} n_{ij}\delta_i\delta_j \leq \sum_{i \in I'} (1 - n'_{ii})\delta_i^2 - \sum_{\{i,j\} \subseteq I'} n'_{ij}\delta_i\delta_j = q_{\Gamma'}(\delta)$$

and $q_{\Gamma'}(\delta) = 0$ by lemma 54.1.30(1). So (3) fails.

The three implications prove the equivalence.

In particular, a connected graph with positive definite Tits form has no loops, no multiple edges and no cycles. The integer vectors at which a Tits form takes the value 1 are its roots.

Definition 54.1.33: Roots, Simple Reflections And The Weyl Group Of A Graph

Let Γ be a graph with vertex set I, Tits form q and symmetric form $(\ ,\ )$.

1. A *root* of Γ is a vector $x \in \mathbb{Z}^I$ with $q(x) = 1$, and Φ_Γ is the set of roots. A root x is *positive* if $x \geq 0$ and *negative* if $-x \geq 0$, and Φ_Γ^+ is the set of positive roots.
2. For a vertex i at which Γ has no loop, the *simple reflection* at i is the linear map $s_i \colon \mathbb{R}^I \to \mathbb{R}^I$, $s_i(x) = x - (x, \alpha_i)\alpha_i$. Since $(\alpha_i, \alpha_i) = 2$ by proposition 54.1.27, $(s_i(x), \alpha_i) = (x, \alpha_i) - 2(x, \alpha_i) = -(x, \alpha_i)$, so $s_i(s_i(x)) = x$ and s_i is invertible.
3. If Γ has no loops, its *Weyl group* W_Γ is the group of linear automorphisms of $\mathbb{R}^I$ generated by the simple reflections, and for an ordering $i_1, \ldots, i_n$ of the n vertices, each listed once, the product $c = s_{i_n} s_{i_{n-1}} \cdots s_{i_1} \in W_\Gamma$ is a *Coxeter element*.

Lemma 54.1.34: Simple Reflections Preserve The Tits Form

Let Γ be a graph and i a vertex at which Γ has no loop.

1. For every $x \in \mathbb{R}^I$, the vector $s_i(x)$ differs from x only in its i-th coordinate. Moreover $s_i(\alpha_i) = -\alpha_i$ and $s_i(\mathbb{Z}^I) = \mathbb{Z}^I$.
2. For all $x, y \in \mathbb{R}^I$, $(s_i(x), s_i(y)) = (x, y)$ and $q(s_i(x)) = q(x)$.
3. $s_i(\Phi_\Gamma) = \Phi_\Gamma$.

***Proof*:**

1. The difference $s_i(x) - x = -(x, \alpha_i)\alpha_i$ is a multiple of α_i, and $s_i(\alpha_i) = \alpha_i - 2\alpha_i = -\alpha_i$ because $(\alpha_i, \alpha_i) = 2$. For $x \in \mathbb{Z}^I$, $(x, \alpha_i) = \sum_j x_j (\alpha_j, \alpha_i)$ is an integer by proposition 54.1.27, so $s_i(\mathbb{Z}^I) \subseteq \mathbb{Z}^I$, and $s_i(s_i(x)) = x$ (definition 54.1.33) gives equality.
2. By bilinearity and $(\alpha_i, \alpha_i) = 2$,
$$(s_i(x), s_i(y)) = (x, y) - 2(x, \alpha_i)(y, \alpha_i) + (x, \alpha_i)(y, \alpha_i)(\alpha_i, \alpha_i) = (x, y)$$
and taking $y = x$ gives $q(s_i(x)) = \frac{1}{2}(s_i(x), s_i(x)) = q(x)$.
3. By (1) and (2), s_i maps Φ_Γ into Φ_Γ, and since $s_i(s_i(x)) = x$, every root x is the image $s_i(s_i(x))$ of the root $s_i(x)$, completing the proof.

Proposition 54.1.35: Roots Of A Positive Definite Tits Form

Let Γ be a graph with vertex set $I = \{1, \dots, n\}$ whose Tits form q is positive definite.

1. Γ has no loops, and $\alpha_1, \dots, \alpha_n$ are roots.
2. Every root is positive or negative, so Φ_Γ is the disjoint union of Φ_Γ^+ and $-\Phi_\Gamma^+$.
3. If x is a root and $i \in I$ with $x \neq \pm\alpha_i$, then $(x, \alpha_i) \in \{-1, 0, 1\}$. The set Φ_Γ is finite.
4. Every element of W_Γ permutes Φ_Γ, and W_Γ is finite.

***Proof*:**

The formula of proposition 54.1.27 shows that q takes integer values on $\mathbb{Z}^I$, and q is positive on nonzero vectors, so $q(y) \geq 1$ for every nonzero $y \in \mathbb{Z}^I$. Bilinearity gives $q(x + y) = q(x) + q(y) + (x, y)$ for all $x, y \in \mathbb{R}^I$.

1. By proposition 54.1.27, $q(\alpha_i) = 1 - n_{ii}$, which is positive only if $n_{ii} = 0$. Hence there are no loops and $q(\alpha_i) = 1$.
2. Let x be a root, and write $x = x^+ - x^-$, where $x_i^+ = \max(x_i, 0)$ and $x_i^- = \max(-x_i, 0)$, so that $x^+, x^- \geq 0$ and no coordinate is nonzero in both. In $(x^+, x^-) = \sum_{i,j} x_i^+ x_j^- (\alpha_i, \alpha_j)$, every nonzero term has $i \neq j$, so $(\alpha_i, \alpha_j) = -n_{ij} \leq 0$ and $(x^+, x^-) \leq 0$. Then
$$1 = q(x) = q(x^+) + q(x^-) - (x^+, x^-) \geq q(x^+) + q(x^-)$$
If x^+ and x^- were both nonzero, the right side would be at least 2. So $x = x^+ \geq 0$ or $x = -x^-$ with $x^- \geq 0$. The two cases exclude each other, since $q(0) = 0$ makes 0 a non-root.
3. Let x be a root and $i \in I$. If $x = \pm\alpha_i$, then $(x, \alpha_i) = \pm 2$. Otherwise $x - \alpha_i$ and $x + \alpha_i$ are nonzero vectors of $\mathbb{Z}^I$, and $q(x \mp \alpha_i) = q(x) + q(\alpha_i) \mp (x, \alpha_i) = 2 \mp (x, \alpha_i)$ is positive, so $(x, \alpha_i) \in \{-1, 0, 1\}$. In every case $(x, \alpha_i) \in \{-2, \dots, 2\}$. The map $\rho\colon \mathbb{Z}^I \to \mathbb{Z}^n$, $\rho(x) = ((x, \alpha_1), \dots, (x, \alpha_n))$, is injective: if $\rho(x) = \rho(y)$, then $(x - y, \alpha_i) = 0$ for all i, so $(x - y, x - y) = \sum_i (x_i - y_i)(x - y, \alpha_i) = 0$ and $x = y$ by positive definiteness. Since ρ maps Φ_Γ into $\{-2, \dots, 2\}^n$, the set Φ_Γ has at most 5^n elements.
4. By lemma 54.1.34(3), each s_i permutes Φ_Γ, and $s_i^{-1} = s_i$, so every element of W_Γ permutes Φ_Γ. Restriction to Φ_Γ is therefore a group homomorphism from W_Γ to the group of permutations of Φ_Γ. An element of its kernel fixes every root, in particular every α_i by (1), and the α_i form a basis of $\mathbb{R}^I$, so it is the identity. Hence W_Γ embeds in the permutation group of the finite set Φ_Γ and is finite, completing the proof.

Example 54.1.36: The Roots Of A_n

Number the vertices of the path A_n as $1, \dots, n$ in order, and for $x \in \mathbb{R}^n$ set $x_0 = x_{n+1} = 0$. Then
$$q(x) = \sum_{i=1}^{n} x_i^2 - \sum_{i=1}^{n-1} x_i x_{i+1} = \frac{1}{2} \sum_{i=0}^{n} (x_{i+1} - x_i)^2$$

because expanding the right side gives $\frac{1}{2}\big(\sum_{i=1}^{n} x_i^2 + \sum_{i=1}^{n} x_i^2 - 2\sum_{i=1}^{n-1} x_i x_{i+1}\big)$, the terms involving x_0 and x_{n+1} being 0. For $x \in \mathbb{Z}^n$, the condition $q(x) = 1$ says that the integer sequence $0 = x_0, x_1, \ldots, x_n, x_{n+1} = 0$ has exactly two steps $x_{i+1} - x_i$ equal to ± 1 and all other steps equal to 0. The sequence starts and ends at 0, so the two nonzero steps have opposite signs, and the sequence is constant equal to 1 or to -1 on an interval $\{i, i+1, \ldots, j\}$ and 0 outside it. Hence

$$\Phi^+_{A_n} = \{\alpha_i + \alpha_{i+1} + \cdots + \alpha_j \mid 1 \le i \le j \le n\}$$

a set of $\frac{n(n+1)}{2}$ positive roots, and Φ_{A_n} consists of these and their negatives.

The finiteness of W_Γ has a consequence for Coxeter elements, which the proof of theorem 54.1.46 uses to locate the indecomposable representations.

Lemma 54.1.37: Coxeter Element Lemma

Let Γ be a graph with vertex set I whose Tits form is positive definite, and let $c = s_{i_n} \cdots s_{i_1}$ be a Coxeter element of W_Γ (definition 54.1.33). For every nonzero $v \in \mathbb{Z}^I$ there is an integer $m \ge 0$ with $c^m(v) \not\ge 0$.

***Proof*:**

By proposition 54.1.35(4), W_Γ is finite, so c has finite order $h \ge 1$. Suppose, toward a contradiction, that $c^m(v) \ge 0$ for every $m \ge 0$, and set $u = \sum_{m=0}^{h-1} c^m(v) \in \mathbb{Z}^I$. Then $c(u) = \sum_{m=1}^{h} c^m(v) = u$, because $c^h(v) = v$.

Step 1: $u = 0$. Put $u_0 = u$ and $u_k = s_{i_k}(u_{k-1})$ for $1 \le k \le n$, so that $u_n = c(u) = u$. By definition 54.1.33, $u_k - u_{k-1} = -(u_{k-1}, \alpha_{i_k})\alpha_{i_k}$, and summing over k,

$$0 = u_n - u_0 = -\sum_{k=1}^{n} (u_{k-1}, \alpha_{i_k})\alpha_{i_k}$$

The vertices $i_1, \ldots, i_n$ are distinct, so the vectors α_{i_k} are linearly independent, and every coefficient (u_{k-1}, α_{i_k}) vanishes. Then $u_k = u_{k-1}$ for every k, so $u_{k-1} = u$ and $(u, \alpha_{i_k}) = 0$ for every k. Every vertex occurs as some i_k, so $(u, \alpha_i) = 0$ for all $i \in I$, and $(u, u) = \sum_i u_i(u, \alpha_i) = 0$. Positive definiteness gives $u = 0$.

Step 2: the contradiction. The vector $u = 0$ is the sum of the vectors $c^m(v) \ge 0$, $0 \le m \le h-1$, so every coordinate of every $c^m(v)$ is 0. In particular $v = c^0(v) = 0$, against the hypothesis. Hence $c^m(v) \not\ge 0$ for some $m \ge 0$, as claimed.

The roots of a positive definite Tits form are an instance of a structure that first appeared in the classification of the simple Lie algebras over $\mathbb{C}$. Its definition records the properties of Φ_Γ that do not refer to the lattice $\mathbb{Z}^I$.

Definition 54.1.38: Root System

Let E be a finite-dimensional real vector space with an inner product $(\ ,\ )$. For a nonzero $\alpha \in E$, the *reflection* in the hyperplane orthogonal to α is $s_\alpha(v) = v - \frac{2(v,\alpha)}{(\alpha,\alpha)}\alpha$. A *(reduced) root system* in E is a finite set $R \subseteq E$ of nonzero vectors, its *roots*, such that

1. R spans E,
2. $s_\alpha(R) = R$ for every $\alpha \in R$,
3. $\frac{2(\beta,\alpha)}{(\alpha,\alpha)} \in \mathbb{Z}$ for all $\alpha, \beta \in R$,
4. if $\alpha \in R$ and $c\alpha \in R$ for a real number c, then $c = \pm 1$.

A root system is *irreducible* if it is not the union of two nonempty subsets with every root of the first orthogonal to every root of the second, and *simply laced* if all its roots have the same length. Root systems $R \subseteq E$ and $R' \subseteq E'$ are *isomorphic* if a linear isomorphism $\varphi\colon E \to E'$ carries R onto R' and satisfies $\frac{2(\varphi(\beta),\varphi(\alpha))}{(\varphi(\alpha),\varphi(\alpha))} = \frac{2(\beta,\alpha)}{(\alpha,\alpha)}$ for all $\alpha, \beta \in R$.

Definition 54.1.39: Weyl Group And Base Of A Root System

Let R be a root system in E. Since $(s_\alpha(v), \alpha) = -(v, \alpha)$, applying s_α twice returns v, and the *Weyl group* $W(R)$ is the group generated by the reflections s_α, $\alpha \in R$. A *base* of R is a subset $\Pi \subseteq R$ that is a basis of E such that every root is an integer combination of Π whose coefficients are all ≥ 0 or all ≤ 0. The elements of a base are the *simple roots*, and the roots whose coefficients are all ≥ 0 are the *positive roots* relative to Π.

Example 54.1.40: The Root System A_2

Let $E = \left\{v \in \mathbb{R}^3 \;\middle|\; v_1 + v_2 + v_3 = 0\right\}$ with the dot product, let $\varepsilon_1, \varepsilon_2, \varepsilon_3$ be the standard basis of $\mathbb{R}^3$, and let

$$R = \{\pm(\varepsilon_1 - \varepsilon_2), \pm(\varepsilon_2 - \varepsilon_3), \pm(\varepsilon_1 - \varepsilon_3)\}$$

The vectors $\varepsilon_1 - \varepsilon_2$ and $\varepsilon_2 - \varepsilon_3$ are linearly independent and lie in the two-dimensional space E, so R spans E. Every root has $(\alpha, \alpha) = 2$, so $s_\alpha(v) = v - (v, \alpha)\alpha$, and for $\alpha = \pm(\varepsilon_i - \varepsilon_j)$ this exchanges the i-th and j-th coordinates of v. Exchanging two coordinates permutes R, and $W(R)$ is generated by the three transpositions of coordinates. The inner product of two roots lies in $\{\pm 1, \pm 2\}$, so $\frac{2(\beta,\alpha)}{(\alpha,\alpha)} = (\beta, \alpha) \in \mathbb{Z}$, and the only multiples of a root lying in R are the root and its negative. So R is a root system, and $\{\varepsilon_1 - \varepsilon_2, \varepsilon_2 - \varepsilon_3\}$ is a base, the third positive root $\varepsilon_1 - \varepsilon_3$ being their sum.

The linear isomorphism $\mathbb{R}^2 \to E$ sending α_1 to $\varepsilon_1 - \varepsilon_2$ and α_2 to $\varepsilon_2 - \varepsilon_3$ carries the symmetric form of A_2 to the dot product, since $(\alpha_1, \alpha_1) = (\alpha_2, \alpha_2) = 2$ and $(\alpha_1, \alpha_2) = -1$ (proposition 54.1.27) agree with the dot products of the images. By example 54.1.36 it carries $\Phi_{A_2} = \{\pm\alpha_1, \pm\alpha_2, \pm(\alpha_1 + \alpha_2)\}$ onto R.

Definition 54.1.41: Cartan Matrix And Dynkin Diagram

Let R be a root system with base $\Pi = \{\alpha_1, \dots, \alpha_r\}$. The *Cartan matrix* of R relative to Π is the $r \times r$ matrix with entries

$$A_{ij} = \frac{2(\alpha_i, \alpha_j)}{(\alpha_i, \alpha_i)}$$

The *Dynkin diagram* of R has vertex set $\{1, \dots, r\}$, two distinct vertices i, j being joined by $A_{ij}A_{ji}$ edges, and each multiple edge carrying an arrowhead pointing toward the shorter of α_i and α_j.

The integers A_{ij} and A_{ji} are positive multiples of (α_i, α_j), so $A_{ij}A_{ji} \geq 0$. The non-simply-laced case already occurs in rank two.

Example 54.1.42: Cartan Matrix

For each of the four sets R below, the two vectors α_1, α_2 chosen are linearly independent, so R spans the plane containing it. The reflections in the roots act as permutations of the coordinates, possibly combined with changes of sign, and these permute R. The integrality axiom follows from the inner products listed, and no two roots are proportional except a root and its negative, so each R is a root system. To see that $\{\alpha_1, \alpha_2\}$ is a base, it suffices to write each positive root as a nonnegative integer combination of α_1 and α_2, the other roots being their negatives. The diagonal entries of every Cartan matrix are 2.

1. $(A_1 \times A_1)$ In $\mathbb{R}^2$, $R = \{\pm\varepsilon_1, \pm\varepsilon_2\}$, with $\alpha_1 = \varepsilon_1$ and $\alpha_2 = \varepsilon_2$. The reflection s_{α_i} changes the sign of the i-th coordinate, every root has length 1, and inner products of roots lie in $\{0, \pm 1\}$. Since $(\alpha_1, \alpha_2) = 0$,
$$A = \begin{pmatrix} 2 & 0 \\ 0 & 2 \end{pmatrix}$$
and the Dynkin diagram is two vertices with no edge.

2. (A_2) For R as in example 54.1.40, with $\alpha_1 = \varepsilon_1 - \varepsilon_2$ and $\alpha_2 = \varepsilon_2 - \varepsilon_3$, the third positive root is $\alpha_1 + \alpha_2$. Here $(\alpha_1, \alpha_1) = (\alpha_2, \alpha_2) = 2$ and $(\alpha_1, \alpha_2) = -1$, so
$$A = \begin{pmatrix} 2 & -1 \\ -1 & 2 \end{pmatrix}$$
and the Dynkin diagram is a single edge.

3. (B_2) In $\mathbb{R}^2$, $R = \{\pm\varepsilon_1, \pm\varepsilon_2, \pm\varepsilon_1 \pm \varepsilon_2\}$, eight roots with independent signs. The reflection in ε_i changes the sign of the i-th coordinate, the reflection in $\varepsilon_1 - \varepsilon_2$ exchanges the coordinates, and the reflection in $\varepsilon_1 + \varepsilon_2$ exchanges them and changes both signs. The inner products of roots lie in $\{0, \pm 1, \pm 2\}$, and $(\alpha, \alpha) \in \{1, 2\}$. With $\alpha_1 = \varepsilon_1 - \varepsilon_2$ and $\alpha_2 = \varepsilon_2$, the positive roots are α_1, α_2, $\varepsilon_1 = \alpha_1 + \alpha_2$ and $\varepsilon_1 + \varepsilon_2 = \alpha_1 + 2\alpha_2$. Here $(\alpha_1, \alpha_1) = 2$, $(\alpha_2, \alpha_2) = 1$ and $(\alpha_1, \alpha_2) = -1$, so $A_{12} = 2(-1)/2 = -1$ and $A_{21} = 2(-1)/1 = -2$:
$$A = \begin{pmatrix} 2 & -1 \\ -2 & 2 \end{pmatrix}$$
The Dynkin diagram is a double edge with its arrowhead pointing toward α_2, the shorter root.

4. (G_2) In the plane E of example 54.1.40, let

$$R = \{\pm(\varepsilon_i - \varepsilon_j) \mid i < j\} \cup \{\pm(2\varepsilon_1 - \varepsilon_2 - \varepsilon_3), \pm(2\varepsilon_2 - \varepsilon_1 - \varepsilon_3), \pm(2\varepsilon_3 - \varepsilon_1 - \varepsilon_2)\}$$

twelve roots, six of squared length 2 and six of squared length 6. The reflection in $\varepsilon_i - \varepsilon_j$ exchanges two coordinates, and for $v \in E$ the reflection in $\gamma = 2\varepsilon_i - \varepsilon_j - \varepsilon_l$ is $v \mapsto v - v_i\gamma$, because $(v, \gamma) = 3v_i$. It exchanges the j-th and l-th coordinates and changes all three signs. The inner product of two roots lies in $\{0, \pm1, \pm2\}$ when both are short, in $\{0, \pm3\}$ when exactly one is long, and in $\{\pm3, \pm6\}$ when both are long, so the integrality axiom holds. With $\alpha_1 = \varepsilon_1 - \varepsilon_2$ and $\alpha_2 = -2\varepsilon_1 + \varepsilon_2 + \varepsilon_3$, the positive roots are

$$\alpha_1 \qquad \alpha_2 \qquad \alpha_1 + \alpha_2 \qquad 2\alpha_1 + \alpha_2 \qquad 3\alpha_1 + \alpha_2 \qquad 3\alpha_1 + 2\alpha_2$$

equal to $\varepsilon_1 - \varepsilon_2$, $-2\varepsilon_1 + \varepsilon_2 + \varepsilon_3$, $\varepsilon_3 - \varepsilon_1$, $\varepsilon_3 - \varepsilon_2$, $\varepsilon_1 - 2\varepsilon_2 + \varepsilon_3$ and $2\varepsilon_3 - \varepsilon_1 - \varepsilon_2$. Here $(\alpha_1, \alpha_1) = 2$, $(\alpha_2, \alpha_2) = 6$ and $(\alpha_1, \alpha_2) = -3$, so $A_{12} = 2(-3)/2 = -3$ and $A_{21} = 2(-3)/6 = -1$:

$$A = \begin{pmatrix} 2 & -3 \\ -1 & 2 \end{pmatrix}$$

The Dynkin diagram is a triple edge with its arrowhead pointing toward α_1, the shorter root.

Definition 54.1.41 normalizes by the row index, so the matrices for B_2 and G_2 are the transposes of those in sources that normalize by the column index, such as [64, §11.1]. In the four cases $A_{12}A_{21}$ takes the values 0, 1, 2, 3.

The two meanings of "Dynkin diagram" in this subsection agree.

Proposition 54.1.43: The Roots Of A Dynkin Diagram Form A Root System

Let Γ be one of the Dynkin diagrams A_n, D_n, E_6, E_7, E_8, with vertex set I, and give $\mathbb{R}^I$ the symmetric form $(\ ,\ )$ of Γ.

1. $(\ ,\ )$ is an inner product on $\mathbb{R}^I$, and Φ_Γ is a root system in $\mathbb{R}^I$.
2. $\{\alpha_i\}_{i \in I}$ is a base of Φ_Γ with positive roots Φ_Γ^+, and the Dynkin diagram of Φ_Γ relative to this base is Γ.
3. Φ_Γ is irreducible and simply laced.
4. Every root is $w(\alpha_i)$ for some $w \in W_\Gamma$ and $i \in I$, and $W(\Phi_\Gamma) = W_\Gamma$.

***Proof*:**
By theorem 54.1.32, the Tits form of Γ is positive definite, so proposition 54.1.35 applies, and Γ has no loops and no multiple edges.

1. The form $(\ ,\ )$ is symmetric and bilinear, and $(x, x) = 2q(x) > 0$ for $x \neq 0$, so it is an inner product. The set Φ_Γ is finite, does not contain 0, and contains every α_i, so it spans $\mathbb{R}^I$ (proposition 54.1.35). Every root has $(\alpha, \alpha) = 2q(\alpha) = 2$, so $s_\alpha(v) = v - (v, \alpha)\alpha$, and $\frac{2(\beta,\alpha)}{(\alpha,\alpha)} = (\beta, \alpha)$ is an integer for $\beta \in \mathbb{Z}^I$ by proposition 54.1.27. As in lemma 54.1.34, s_α maps $\mathbb{Z}^I$ to $\mathbb{Z}^I$, satisfies $(s_\alpha(x), s_\alpha(y)) = (x, y) - 2(x, \alpha)(y, \alpha) + (x, \alpha)(y, \alpha)(\alpha, \alpha) = (x, y)$,

and is its own inverse, so $s_\alpha(\Phi_\Gamma) = \Phi_\Gamma$. If α and $c\alpha$ are roots, then $1 = q(c\alpha) = c^2 q(\alpha) = c^2$ and $c = \pm 1$.

2. The α_i form a basis of $\mathbb{R}^I$, and by proposition 54.1.35(2) every root has coordinates all ≥ 0 or all ≤ 0. So $\{\alpha_i\}$ is a base, whose positive roots are Φ_Γ^+. Its Cartan matrix has $A_{ij} = (\alpha_i, \alpha_j)$, which by proposition 54.1.27 is -1 if i and j are adjacent and 0 if they are distinct and not adjacent. So $A_{ij}A_{ji}$ is 1 for adjacent vertices and 0 for other pairs, the Dynkin diagram has a single edge exactly between adjacent vertices and no arrowheads, and it is Γ.


3. Every root has $(\alpha, \alpha) = 2$, so Φ_Γ is simply laced. Suppose $\Phi_\Gamma = R_1 \cup R_2$ with R_1 and R_2 nonempty and orthogonal to each other. No root lies in both, as a root is not orthogonal to itself. If i and j are adjacent, then $(\alpha_i, \alpha_j) = -1 \neq 0$, so α_i and α_j lie in the same R_l, and as Γ is connected, all the α_i lie in one of them, say R_1. A root $\beta \in R_2$ is then orthogonal to every α_i, so $(\beta, \beta) = \sum_i \beta_i(\beta, \alpha_i) = 0$, which is impossible. Hence Φ_Γ is irreducible.

4. First let $x \in \Phi_\Gamma^+$, and argue by induction on $\mathrm{ht}(x) = \sum_i x_i \geq 1$. If $\mathrm{ht}(x) = 1$, then $x = \alpha_i$ for some i. If $\mathrm{ht}(x) \geq 2$, then $2 = (x, x) = \sum_i x_i(x, \alpha_i)$ with every $x_i \geq 0$, so some i has $x_i > 0$ and $(x, \alpha_i) > 0$. As $x \neq \pm\alpha_i$, proposition 54.1.35(3) gives $(x, \alpha_i) = 1$, so $s_i(x) = x - \alpha_i$ is a root (lemma 54.1.34) of height $\mathrm{ht}(x) - 1$. Some x_j with $j \neq i$ is positive, since otherwise $x = x_i\alpha_i$ and $q(x) = x_i^2 = 1$ would force $x = \alpha_i$, and $s_i(x)$ has the same j-th coordinate. So $s_i(x)$ is a positive root (proposition 54.1.35(2)), by induction $s_i(x) = w(\alpha_l)$ with $w \in W_\Gamma$, and $x = s_i w(\alpha_l)$. A negative root x has $-x = w(\alpha_l)$, and then $x = w(-\alpha_l) = ws_l(\alpha_l)$. Next, $s_i = s_{\alpha_i}$, so $W_\Gamma \subseteq W(\Phi_\Gamma)$. Conversely, write a root as $\alpha = w(\alpha_l)$ with $w \in W_\Gamma$. By lemma 54.1.34(2), w preserves $(\ ,\ )$, so $(v, w(\alpha_l)) = (w^{-1}(v), \alpha_l)$ and, for every $v \in \mathbb{R}^I$,

$$s_\alpha(v) = v - (w^{-1}(v), \alpha_l)w(\alpha_l) = w\big(w^{-1}(v) - (w^{-1}(v), \alpha_l)\alpha_l\big) = ws_lw^{-1}(v)$$

So every generator s_α of $W(\Phi_\Gamma)$ lies in W_Γ, and $W(\Phi_\Gamma) = W_\Gamma$, completing the proof.

54.1.44 Remark: The Classification Of Root Systems Every root system is the union of mutually orthogonal irreducible root systems, and an irreducible root system is determined up to isomorphism by its Dynkin diagram, which is one of the connected diagrams



with $n \geq 1$ for A_n, $n \geq 2$ for B_n, $n \geq 3$ for C_n and $n \geq 4$ for D_n, and every diagram on the list occurs [64, §§11.1, 11.3, 11.4, 12.1]. The proof is a case analysis of the possible Cartan matrices, and nothing in this book depends on it. The simply laced diagrams on the list are A_n, D_n, E_6, E_7 and E_8, and by proposition 54.1.43 their root systems are the sets Φ_Γ of the Tits forms. In B_n, C_n, F_4 and G_2 the roots have two different lengths, as in example 54.1.42 for B_2 and G_2. Every root of a graph has $(\alpha, \alpha) = 2$, so these four families never arise as Φ_Γ, and in particular never from the Tits form of a quiver.

54.1.4 Gabriel's Theorem

Theorem 54.1.32 singles out the Dynkin diagrams of type A, D, E among connected graphs by the positivity of their Tits forms, and proposition 54.1.35 attaches to each of them a finite set of positive roots. Gabriel's theorem identifies these positive roots with the indecomposable representations of every quiver whose underlying graph is one of these diagrams. Throughout, $\mathbb{F}$ is a field, representations are over $\mathbb{F}$, and quivers are finite.

Definition 54.1.45: Collection Of Indecomposables

Let Q be a finite quiver. Then $\mathrm{Ind}(Q)$ denotes the set of isomorphism classes of nonzero finite-dimensional indecomposable representations of Q over $\mathbb{F}$, and Q is of *finite type* over $\mathbb{F}$ if $\mathrm{Ind}(Q)$ is finite.

Theorem 54.1.46: Gabriel's Theorem

Let Q be a finite quiver whose underlying graph Γ is connected (definition 54.1.25), and let $\mathbb{F}$ be a field.

1. If Γ is one of the Dynkin diagrams A_n, D_n, E_6, E_7, E_8, then Q is of finite type over $\mathbb{F}$, and the dimension vector
$$\dim\colon \operatorname{Ind}(Q) \longrightarrow \Phi_\Gamma^+ \qquad [V] \longmapsto \dim_Q V$$
is a bijection onto the set of positive roots of Γ.
2. If $\mathbb{F}$ is infinite and Q is of finite type over $\mathbb{F}$, then Γ is one of the Dynkin diagrams A_n, D_n, E_6, E_7, E_8.

By part (1), the number of indecomposable representations of a quiver of type A, D, E depends only on its graph, not on the orientation of its arrows or on the field: a quiver whose underlying graph is A_n has $\frac{n(n+1)}{2}$ of them by example 54.1.36. The proof of part (2) below uses that $\mathbb{F}$ is infinite: over a finite field every representation space is a finite set, so the number of orbits of $G(\underline{d})$ carries no information.

By proposition 54.1.43(4), every positive root is obtained from some α_i by applying simple reflections. The reflection functors of Bernstein, Gelfand and Ponomarev are the corresponding operations on representations. A simple reflection s_i is defined at every vertex without a loop, hence at every vertex of an A, D, E graph, but a reflection functor at i is defined only when i is a sink or a source (definition 54.1.4), and it reverses the arrows at i. For a sink i write s_i^+Q, and for a source i write s_i^-Q, for the quiver iQ of definition 54.1.4, in which every arrow at i is reversed. The sink i of Q is a source of s_i^+Q, and $s_i^-(s_i^+Q) = Q$.

Let Q be $1 \xrightarrow{e} 2$, in which 2 is a sink, and let V be the representation $V(1) \xrightarrow{T_e} V(2)$. The reflection at the sink 2 keeps $V(1)$, replaces $V(2)$ by $\ker(T_e)$, and replaces the arrow by its reversal $2 \to 1$, carrying the inclusion of $\ker(T_e)$ into $V(1)$:

$$\left(\begin{array}{ccc} V(1) & \xrightarrow{T_e} & V(2) \\ \bullet & & \bullet \end{array} \right) \longmapsto \left(\begin{array}{ccc} V(1) & \hookleftarrow & \ker(T_e) \\ \bullet & & \bullet \end{array} \right)$$

If T_e is surjective, the dimension vector (d_1, d_2) becomes $(d_1, d_1 - d_2)$, and since $(d, \alpha_2) = 2d_2 - d_1$ by proposition 54.1.27, this is $s_2(d)$. The reflection at the source 1 replaces $V(1)$ by $\operatorname{coker}(T_e) = V(2)/\operatorname{im}(T_e)$ and the arrow by the quotient map $V(2) \to \operatorname{coker}(T_e)$, and if T_e is injective the dimension vector becomes $(d_2 - d_1, d_2) = s_1(d)$. At an arbitrary sink or source, all the arrows at the vertex are combined into one map. If i is a sink of Q and $V \in \operatorname{Rep}(Q)$, let

$$\Psi_i\colon \bigoplus_{e:j\to i} V(j) \to V(i)$$

be the map whose restriction to the summand indexed by an arrow $e\colon j \to i$ is T_e, the sum having one summand for each arrow into i. If i is a source, let

$$\Phi_i\colon V(i) \to \bigoplus_{e:i\to j} V(j)$$

be the map whose component in the summand indexed by an arrow $e\colon i \to j$ is T_e.

Definition 54.1.47: Reflection Functor

Let Q be a quiver.

1. For a sink i and $V \in \mathrm{Rep}(Q)$, define $S_i^+(V) \in \mathrm{Rep}(s_i^+Q)$ by $S_i^+(V)(k) = V(k)$ for $k \neq i$ and $S_i^+(V)(i) = \ker(\Psi_i)$. The map along an arrow not at i is T_e, and the map along the reversal $i \to k$ of an arrow $e\colon k \to i$ is $\pi_k \circ \iota_i$, where $\iota_i\colon \ker(\Psi_i) \to \bigoplus_{e:j\to i} V(j)$ is the inclusion and π_k is the projection onto the summand $V(k)$ indexed by e (two arrows from k give two summands and two projections).

2. For a source i and $V \in \mathrm{Rep}(Q)$, define $S_i^-(V) \in \mathrm{Rep}(s_i^-Q)$ by $S_i^-(V)(k) = V(k)$ for $k \neq i$ and $S_i^-(V)(i) = \mathrm{coker}(\Phi_i)$. The map along an arrow not at i is T_e, and the map along the reversal $k \to i$ of an arrow $e\colon i \to k$ is $p \circ \iota_k$, where $\iota_k\colon V(k) \to \bigoplus_{e:i\to j} V(j)$ is the inclusion of the summand indexed by e and p is the quotient map onto $\mathrm{coker}(\Phi_i)$.

3. For a morphism $\varphi\colon V \to W$ and a sink i, the morphism $S_i^+(\varphi)$ is $\varphi(k)$ at $k \neq i$ and the restriction of $\bigoplus_{e:j\to i} \varphi(j)$ to $\ker(\Psi_i^V) \to \ker(\Psi_i^W)$ at i. For a source i, the morphism $S_i^-(\varphi)$ is $\varphi(k)$ at $k \neq i$ and the map induced by $\bigoplus_{e:i\to j} \varphi(j)$ on cokernels at i.

The functors $S_i^+\colon \mathrm{Rep}(Q) \to \mathrm{Rep}(s_i^+Q)$ and $S_i^-\colon \mathrm{Rep}(Q) \to \mathrm{Rep}(s_i^-Q)$ are the *Bernstein-Gelfand-Ponomarev reflection functors*, or *reflection functors* for short. That (3) is well defined and gives functors is the first paragraph of the proof of proposition 54.1.49.

Example 54.1.48: Reflection Functor

Let Q be $1 \xrightarrow{e} 2$, so that s_2^+Q is $1 \leftarrow 2$. Three nonzero indecomposable representations of Q are $\mathbb{F} \xrightarrow{1} \mathbb{F}$, $\mathbb{F} \to 0$ and $0 \to \mathbb{F}$ (example 54.1.23), of dimension vectors $\alpha_1 + \alpha_2$, α_1 and α_2. Applying S_2^+:

1. For $\mathbb{F} \xrightarrow{1} \mathbb{F}$, the map Ψ_2 is the identity of $\mathbb{F}$, so $\ker(\Psi_2) = 0$ and S_2^+ gives $\mathbb{F} \leftarrow 0$, of dimension vector $\alpha_1 = s_2(\alpha_1 + \alpha_2)$.

2. For $\mathbb{F} \to 0$, the map Ψ_2 is zero on $\mathbb{F}$, so $\ker(\Psi_2) = \mathbb{F}$ and S_2^+ gives $\mathbb{F} \xleftarrow{1} \mathbb{F}$, of dimension vector $\alpha_1 + \alpha_2 = s_2(\alpha_1)$.

3. For $0 \to \mathbb{F}$, $\ker(\Psi_2) = 0$ and S_2^+ gives 0, while $s_2(\alpha_2) = -\alpha_2$ is negative.

So S_2^+ exchanges the representations of dimension vectors α_1 and $\alpha_1 + \alpha_2$, as s_2 exchanges these positive roots of A_2, and it sends the simple representation at the sink, whose dimension vector s_2 makes negative, to 0.

For a sink i, let $\mathrm{Rep}^{i,-}(Q)$ denote the full subcategory of representations of Q for which the map

$$\Psi_i\colon \bigoplus_{e:j\to i} V(j) \to V(i)$$

is surjective, and for a source i, let $\mathrm{Rep}^{i,+}(Q)$ denote the full subcategory of representations of Q for which the map

$$\Phi_i\colon V(i) \to \bigoplus_{e:i\to j} V(j)$$

is injective. For a vertex i, let $S(i) \in \mathrm{Rep}(Q)$ denote the representation with $S(i)(i) = \mathbb{F}$, with $S(i)(l) = 0$ for $l \neq i$, and with all edge maps zero. A representation is *simple at vertex i* if it is isomorphic to $S(i)$.

Proposition 54.1.49: Properties Of Reflection Functor

Let Q be a quiver. In items (4) to (7), the upper sign refers to a sink i and the lower sign to a source i. For items (6) and (7), assume in addition that Q is finite and that every representation named has finite total dimension $\sum_i \dim V(i)$, and let s_i be the simple reflection at i of the underlying graph of Q (definition 54.1.33), which is defined because a sink or a source carries no loop.

1. If i is a sink, then for any $V \in \mathrm{Rep}(Q)$, $S_i^+(V) \in \mathrm{Rep}^{i,+}(s_i^+(Q))$ (similarly for source)
2. If i is a sink, then for any $V \in \mathrm{Rep}(Q)$, $S_i^- S_i^+(V) \in \mathrm{Rep}^{i,-}(Q)$ (similarly for source)
3. The restrictions of the reflection functors are equivalences

$$S_i^+ : \mathrm{Rep}^{i,-}(Q) \to \mathrm{Rep}^{i,+}(s_i^+ Q) \qquad (i \text{ a sink of } Q)$$
$$S_i^- : \mathrm{Rep}^{i,+}(Q) \to \mathrm{Rep}^{i,-}(s_i^- Q) \qquad (i \text{ a source of } Q)$$

   where the inverse of each restriction is the restriction of the other functor, taken over the reflected quiver
4. If V is simple at vertex i, then $S_i^\pm(V) = 0$.
5. If V is a non-zero indecomposable representation of Q that is not simple at i, then $V \in \mathrm{Rep}^{i,\mp}(Q)$, the representation $S_i^\pm(V)$ of $s_i^\pm(Q)$ is nonzero and indecomposable, and $V \cong S_i^\mp S_i^\pm(V)$.
6. If V is a nonzero indecomposable representation of Q, then $S_i^\pm(V)$ is a nonzero indecomposable representation of $s_i^\pm(Q)$ if and only if $s_i(\dim_Q(V)) \geq 0$
7. If $V \in \mathrm{Rep}^{i,\mp}(Q)$ is a nonzero indecomposable representation, then $\dim_Q(S_i^\pm(V)) = s_i(\dim_Q(V))$

***Proof*:**

For a sink i of a quiver and a representation V, write $\Psi_i^V : \bigoplus_{e:j\to i} V(j) \to V(i)$ for the map whose component at an edge $e : j \to i$ is T_e, and for a source i write $\Phi_i^V : V(i) \to \bigoplus_{e:i\to j} V(j)$ for the map whose component at an edge $e : i \to j$ is T_e. These are the maps in the definition of the subcategories $\mathrm{Rep}^{i,\mp}$ above. On a quiver morphism $\varphi : V \to W$, the functor S_i^+ acts by $S_i^+(\varphi)(k) = \varphi(k)$ for $k \neq i$ and by taking $S_i^+(\varphi)(i)$ to be the restriction of $\bigoplus_{e:j\to i} \varphi(j)$ to a map $\ker(\Psi_i^V) \to \ker(\Psi_i^W)$, as in definition 54.1.47(3). The restriction lands in $\ker(\Psi_i^W)$ because summing the commuting squares of φ over the edges $e : j \to i$ (definition 54.1.9) gives $\Psi_i^W \circ \bigoplus_j \varphi(j) = \varphi(i) \circ \Psi_i^V$. The map $\bigoplus_j \varphi(j)$ acts summand by summand, so $\pi_k \circ \bigoplus_j \varphi(j) = \varphi(k) \circ \pi_k$ for the projection π_k onto the summand indexed by an edge $e\colon k \to i$, and this is the commuting square of $S_i^+(\varphi)$ at the reversal of e. At the edges not at i the squares are those of φ, so $S_i^+(\varphi)$ is a morphism. Dually, summing the squares of φ over the edges $e : i \to j$ gives $\Phi_i^W \circ \varphi(i) = \left(\bigoplus_j \varphi(j)\right) \circ \Phi_i^V$, so $\bigoplus_{e:i\to j} \varphi(j)$ carries $\mathrm{im}(\Phi_i^V)$ into $\mathrm{im}(\Phi_i^W)$ and induces the

map $S_i^-(\varphi)(i)$ on cokernels. It commutes with the inclusions of the summands and with the quotient maps, which gives the squares of $S_i^-(\varphi)$ at the reversed edges. Both constructions send identities to identities, and they respect composition because the restriction of a composite is the composite of the restrictions, and likewise for induced maps on quotients.

For representations V, W and a sink i, the canonical identification

$$\bigoplus_{e:j\to i}(V\oplus W)(j)=\Big(\bigoplus_{e:j\to i}V(j)\Big)\oplus\Big(\bigoplus_{e:j\to i}W(j)\Big)$$

carries $\Psi_i^{V\oplus W}$ to $\Psi_i^V\oplus\Psi_i^W$, and the kernel of a direct sum of linear maps is the direct sum of the kernels, so $S_i^+(V\oplus W)\cong S_i^+(V)\oplus S_i^+(W)$, the edge maps on both sides being assembled summand by summand from the same inclusions and projections. The same identification on cokernels gives $S_i^-(V\oplus W)\cong S_i^-(V)\oplus S_i^-(W)$ at a source.

Item (1). Let i be a sink of Q and $V\in\mathrm{Rep}(Q)$, and write $U=\bigoplus_{e:j\to i}V(j)$ and $K=\ker(\Psi_i^V)\subseteq U$. In $s_i^+(Q)$ the vertex i is a source, and its outgoing edges are exactly the reversals of the edges of Q into i. By definition 54.1.47, the map of $S_i^+(V)$ at the reversal of an edge $e:k\to i$ is $\pi_k\circ\iota_i$, where $\iota_i:K\to U$ is the inclusion and π_k is the projection of U onto the summand $V(k)$ indexed by e. The map $\Phi_i^{S_i^+(V)}$ therefore has components $\pi_k\circ\iota_i$ over all summands of U, and a vector of U is recovered from the family of all its components, so $\Phi_i^{S_i^+(V)}=\iota_i$. An inclusion is injective, so $S_i^+(V)\in\mathrm{Rep}^{i,+}(s_i^+(Q))$. For a source i, the edges of $s_i^-(Q)$ into i are the reversals of the edges of Q out of i, the map of $S_i^-(V)$ at such an edge is $p\circ\iota_k$ with $p:\bigoplus_{e:i\to j}V(j)\to\mathrm{coker}(\Phi_i^V)$ the quotient map, and assembling the components gives $\Psi_i^{S_i^-(V)}=p$. A quotient map is surjective, so $S_i^-(V)\in\mathrm{Rep}^{i,-}(s_i^-(Q))$.

Item (2). Let i be a sink of Q. Reversing the arrows at i twice returns the original quiver, so $s_i^-(s_i^+(Q))=Q$. The vertex i is a source of $s_i^+(Q)$, so the source half of item (1), applied to the quiver $s_i^+(Q)$ and the representation $S_i^+(V)$, gives $S_i^-S_i^+(V)\in\mathrm{Rep}^{i,-}(Q)$. If i is instead a source of Q, the sink half of item (1) applied to $s_i^-(Q)$ gives $S_i^+S_i^-(V)\in\mathrm{Rep}^{i,+}(Q)$.

Item (3). Let i be a sink of Q. By item (1), S_i^+ carries $\mathrm{Rep}^{i,-}(Q)$ into $\mathrm{Rep}^{i,+}(s_i^+(Q))$ and S_i^- carries $\mathrm{Rep}^{i,+}(s_i^+(Q))$ into $\mathrm{Rep}^{i,-}(Q)$, so both restrictions are defined.

Let $V\in\mathrm{Rep}^{i,-}(Q)$ and retain U, K, ι_i from item (1). By item (1), $\Phi_i^{S_i^+(V)}=\iota_i$, so $(S_i^-S_i^+(V))(i)=\mathrm{coker}(\iota_i)=U/K$, and the map of $S_i^-S_i^+(V)$ at an edge $e:j\to i$ of Q is $p\circ\iota_j:V(j)\to U/K$, with $p\colon U\to U/K$ the quotient map. At every other vertex and edge, $S_i^-S_i^+(V)$ agrees with V. Because $V\in\mathrm{Rep}^{i,-}(Q)$ the map Ψ_i^V is surjective, and $\Psi_i^V(u)=\Psi_i^V(u')$ holds exactly when $u-u'\in K$, so

$$\overline{\Psi_i}:U/K\to V(i)\qquad u+K\mapsto\Psi_i^V(u)$$

is a well-defined linear isomorphism. Define $\mu_V:S_i^-S_i^+(V)\to V$ by $\mu_V(i)=\overline{\Psi_i}$ and $\mu_V(k)=\mathrm{id}_{V(k)}$ for $k\neq i$. At an edge $e:j\to i$ the required square commutes because

$$\overline{\Psi_i}(p(\iota_j(x)))=\Psi_i^V(\iota_j(x))=T_e(x)$$

for $x\in V(j)$, and at every other edge both representations carry the same map with identities as the vertical maps. So μ_V is a quiver morphism that is a linear isomorphism at every vertex. Its vertexwise inverse is again a quiver morphism, because from $\mu_V(i')\circ S_e=T_e\circ\mu_V(j')$ at an edge $e:j'\to i'$ one gets $S_e\circ\mu_V(j')^{-1}=\mu_V(i')^{-1}\circ T_e$. Hence μ_V is an isomorphism $S_i^-S_i^+(V)\cong V$.

For naturality, let $\varphi : V \to V'$ be a morphism in $\mathrm{Rep}^{i,-}(Q)$. At a vertex $k \neq i$ both composites $\varphi \circ \mu_V$ and $\mu_{V'} \circ S_i^- S_i^+(\varphi)$ equal $\varphi(k)$. At i, the map $S_i^- S_i^+(\varphi)(i) : U/K \to U'/K'$ is induced by $\bigoplus_{e:j\to i} \varphi(j)$, so both composites send $u + K$ to

$$\varphi(i)(\Psi_i^V(u)) = \Psi_i^{V'}\Big(\bigoplus_j \varphi(j)(u)\Big)$$

the equality being the sum over the edges $e : j \to i$ of the commuting squares of φ.

Conversely, let $W \in \mathrm{Rep}^{i,+}(s_i^+(Q))$, write $U' = \bigoplus_{f:i\to k} W(k)$, summing over the edges of $s_i^+(Q)$ out of i, and write $\Phi = \Phi_i^W : W(i) \to U'$, an injective map because $W \in \mathrm{Rep}^{i,+}$. Then $(S_i^-(W))(i) = \mathrm{coker}(\Phi) = U'/\mathrm{im}(\Phi)$, and by the source half of item (1), $\Psi_i^{S_i^-(W)}$ is the quotient map $p' : U' \to U'/\mathrm{im}(\Phi)$, so

$$(S_i^+ S_i^-(W))(i) = \ker(p') = \mathrm{im}(\Phi)$$

Define $\nu_W : W \to S_i^+ S_i^-(W)$ by $\nu_W(k) = \mathrm{id}_{W(k)}$ for $k \neq i$ and $\nu_W(i) : W(i) \to \mathrm{im}(\Phi)$, $x \mapsto \Phi(x)$, a linear isomorphism because Φ is injective. At an edge $f : i \to k$ of $s_i^+(Q)$, the map of $S_i^+ S_i^-(W)$ is $\pi_k \circ \iota_i$ with $\iota_i : \ker(p') \to U'$ the inclusion, and

$$\pi_k(\iota_i(\Phi(x))) = \pi_k(\Phi(x)) = T_f(x)$$

because the f-component of Φ is T_f. At every edge not at i both representations carry the same map and the vertical maps are identities. As before, the vertexwise linear isomorphism ν_W is an isomorphism of representations. Naturality in W follows as for μ: for $\varphi : W \to W'$, the map $S_i^+ S_i^-(\varphi)(i)$ is the restriction of $\bigoplus_f \varphi(k)$ to the kernels, and $\Phi' \circ \varphi(i) = \big(\bigoplus_f \varphi(k)\big) \circ \Phi$ is the sum over the edges $f : i \to k$ of the commuting squares of φ.

The natural isomorphisms μ and ν exhibit $S_i^- S_i^+ \cong \mathrm{id}$ on $\mathrm{Rep}^{i,-}(Q)$ and $S_i^+ S_i^- \cong \mathrm{id}$ on $\mathrm{Rep}^{i,+}(s_i^+(Q))$, so the two restrictions are mutually inverse equivalences. This proves the first line of the display, together with the statement that its inverse is the restriction of S_i^-. The second line is the case just proved, applied to the quiver $s_i^-(Q)$: if i is a source of Q, then i is a sink of $s_i^-(Q)$ and $s_i^+(s_i^-(Q)) = Q$, so the restrictions

$$S_i^- : \mathrm{Rep}^{i,+}(Q) \to \mathrm{Rep}^{i,-}(s_i^-(Q)) \qquad S_i^+ : \mathrm{Rep}^{i,-}(s_i^-(Q)) \to \mathrm{Rep}^{i,+}(Q)$$

are mutually inverse equivalences.

The unrestricted functors are moreover adjoint. Fix a sink i of Q, and let $A \in \mathrm{Rep}(s_i^+(Q))$ and $B \in \mathrm{Rep}(Q)$. Away from i, the representations $S_i^-(A)$ and A carry the same spaces and maps, as do B and $S_i^+(B)$, so a family $(g(k))_{k\neq i}$ satisfies the square conditions away from i for a morphism $S_i^-(A) \to B$ exactly when it satisfies them for a morphism $A \to S_i^+(B)$. In a morphism $g : S_i^-(A) \to B$, the squares at the edges $e : k \to i$ of Q read $g(i) \circ p \circ \iota_k = T_e^B \circ g(k)$, with p the quotient map onto $\mathrm{coker}(\Phi_i^A)$, so $g(i)$ is the map that $\Psi_i^B \circ \bigoplus_k g(k)$ induces on $\mathrm{coker}(\Phi_i^A)$, and such a map exists, uniquely, exactly when this composite kills $\mathrm{im}(\Phi_i^A)$. In a morphism $h : A \to S_i^+(B)$ carrying the same family $g(k) = h(k)$ away from i, the squares at the edges $f : i \to k$ of $s_i^+(Q)$ read $\iota_i \circ h(i) = \big(\bigoplus_k g(k)\big) \circ \Phi_i^A$, so $h(i)$ exists, uniquely, exactly when the right-hand side lands in $\ker(\Psi_i^B)$. Both conditions state that $\Psi_i^B \circ \big(\bigoplus_k g(k)\big) \circ \Phi_i^A = 0$. Restricting to the components away from i is therefore a bijection

$$\mathrm{Hom}_Q(S_i^-(A), B) \cong \mathrm{Hom}_{s_i^+(Q)}(A, S_i^+(B))$$

natural in A and B, because composition with a morphism acts on the components away from i componentwise.

Item (4). Isomorphic representations have isomorphic images under the functors, so take $V = S(i)$. If i is a sink, every j with an edge $e : j \to i$ satisfies $V(j) = 0$, so $\bigoplus_{e:j\to i} V(j) = 0$ and $\ker(\Psi_i^V) = 0$. The representation $S_i^+(V)$ is then zero at i and equals $V(k) = 0$ at every $k \neq i$, so $S_i^+(V) = 0$. If i is a source, then $\bigoplus_{e:i\to j} V(j) = 0$, so $\operatorname{coker}(\Phi_i^V) = 0$ and $S_i^-(V) = 0$ for the same reason.

Item (5). First a dichotomy: if i is a sink and V is a nonzero indecomposable representation with $V \ncong S(i)$, then Ψ_i^V is surjective, that is, $V \in \operatorname{Rep}^{i,-}(Q)$. Suppose Ψ_i^V is not surjective and choose a subspace $C \subseteq V(i)$ with $V(i) = \operatorname{im}(\Psi_i^V) \oplus C$ and $C \neq 0$. Define $V', V'' \subseteq V$ by

$$V'(i) = \operatorname{im}(\Psi_i^V) \qquad V'(k) = V(k) \text{ for } k \neq i \qquad V''(i) = C \qquad V''(k) = 0 \text{ for } k \neq i$$

Both are subrepresentations (definition 54.1.8): every edge $e : j \to i$ satisfies $T_e(V(j)) \subseteq \operatorname{im}(\Psi_i^V) = V'(i)$ and $T_e(V''(j)) = T_e(0) = 0 \subseteq V''(i)$, the sink i has no outgoing edges, and edges away from i are unaffected. Every edge map is accordingly the direct sum of its restrictions to V' and V'', so $V = V' \oplus V''$ as in definition 54.1.17. Indecomposability of V with $V'' \neq 0$ forces $V' = 0$, so $V(k) = 0$ for all $k \neq i$ and $\operatorname{im}(\Psi_i^V) = 0$. All edge maps of V then vanish, so V is a direct sum of $\dim(C)$ copies of $S(i)$, and indecomposability forces $\dim(C) = 1$ and $V \cong S(i)$, against the hypothesis. The dichotomy follows. For a source the same construction splits off the kernel: if Φ_i^V is not injective, then V'' with $V''(i) = \ker(\Phi_i^V) \neq 0$ and $V''(k) = 0$ for $k \neq i$, together with V' given by a complement of $\ker(\Phi_i^V)$ at i and $V'(k) = V(k)$ for $k \neq i$, are subrepresentations with $V = V' \oplus V''$, and indecomposability forces, by the same argument, $V \cong S(i)$.

Now let V be nonzero indecomposable with $V \ncong S(i)$, and let i be a sink. By the dichotomy, $V \in \operatorname{Rep}^{i,-}(Q)$, which is the first claim of item (5), and item (3) gives $V \cong S_i^- S_i^+(V)$, which is the last. If $S_i^+(V) = 0$, then $V \cong S_i^-(0) = 0$, against $V \neq 0$. So $S_i^+(V) \neq 0$. Suppose $S_i^+(V) = W_1 \oplus W_2$ with both summands nonzero. Item (1) puts $S_i^+(V)$ in $\operatorname{Rep}^{i,+}(s_i^+(Q))$, and $\Phi_i^{W_1\oplus W_2} = \Phi_i^{W_1} \oplus \Phi_i^{W_2}$, so each $\Phi_i^{W_l}$ is injective and $W_l \in \operatorname{Rep}^{i,+}(s_i^+(Q))$. Item (3) gives $W_l \cong S_i^+ S_i^-(W_l)$, and $W_l \neq 0$ forces $S_i^-(W_l) \neq 0$. The additivity of S_i^- recorded at the start of the proof now gives

$$V \cong S_i^-(W_1 \oplus W_2) \cong S_i^-(W_1) \oplus S_i^-(W_2)$$

Let θ be the inverse of the displayed isomorphism, an isomorphism from $S_i^-(W_1) \oplus S_i^-(W_2)$ to V. An isomorphism carries subrepresentations to subrepresentations, so $V_1 = \theta(S_i^-(W_1) \oplus 0)$ and $V_2 = \theta(0 \oplus S_i^-(W_2))$ are nonzero subrepresentations of V with $V = V_1 \oplus V_2$, against definition 54.1.22. Hence $S_i^+(V)$ is indecomposable. For a source the argument runs with S_i^- and S_i^+ exchanged, using the source halves of items (1) and (3) and the additivity of S_i^+.

Item (7). Item (6) uses this item. Let i be a sink and $V \in \operatorname{Rep}^{i,-}(Q)$ of finite total dimension, and write $d = \dim_Q(V)$ (definition 54.1.7). Vertices $k \neq i$ contribute $\dim(S_i^+(V)(k)) = \dim V(k) = d_k$. At i, the map Ψ_i^V is surjective, so rank-nullity gives

$$\dim \ker(\Psi_i^V) = \sum_{e:j\to i} d_j - d_i$$

the sum running over the edges into i, each counted once. On the other side, by definition 54.1.26, $\langle d, \alpha_i\rangle = d_i - \sum_{e:j\to i} d_j$ and $\langle \alpha_i, d\rangle = d_i$, because no edge leaves the sink i. Hence $(d, \alpha_i) =$

$2d_i - \sum_{e:j\to i} d_j$, and $s_i(d) = d - (d,\alpha_i)\alpha_i$ agrees with d away from i and has i-th entry

$$d_i - \Big(2d_i - \sum_{e:j\to i} d_j\Big) = \sum_{e:j\to i} d_j - d_i$$

The two dimension vectors agree, so $\dim_Q(S_i^+(V)) = s_i(\dim_Q(V))$. For a source i and $V \in \mathrm{Rep}^{i,+}(Q)$, the map Φ_i^V is injective, so $\dim \operatorname{coker}(\Phi_i^V) = \sum_{e:i\to j} d_j - d_i$, while $\langle d,\alpha_i\rangle = d_i$ and $\langle \alpha_i, d\rangle = d_i - \sum_{e:i\to j} d_j$, and the same computation gives $\dim_Q(S_i^-(V)) = s_i(\dim_Q(V))$.

Item (6). Let V be nonzero indecomposable and let i be a sink. The source case replaces S_i^+ by S_i^- throughout, using the source halves of items (4), (5), and (7). If $V \cong S(i)$, then $S_i^+(V) = 0$ by item (4), and $\dim_Q(V) = \alpha_i$, so $s_i(\dim_Q(V)) = -\alpha_i$ (lemma 54.1.34), whose i-th entry is -1. Both sides of the equivalence fail. If $V \ncong S(i)$, then item (5) gives that $S_i^+(V)$ is nonzero indecomposable and that $V \in \mathrm{Rep}^{i,-}(Q)$, and item (7) gives $s_i(\dim_Q(V)) = \dim_Q(S_i^+(V))$, a vector of dimensions, hence ≥ 0. Both sides of the equivalence hold. In either case the equivalence is true.

Corollary 54.1.50: Reflection Functors Are Adjoint

Let i be a sink of Q. For $A \in \mathrm{Rep}(s_i^+(Q))$ and $B \in \mathrm{Rep}(Q)$ there is a bijection

$$\mathrm{Hom}_Q(S_i^-(A), B) \cong \mathrm{Hom}_{s_i^+(Q)}(A, S_i^+(B))$$

natural in both variables, so S_i^- is left adjoint to S_i^+.

***Proof*:**
This is the final paragraph of the proof of item (3) of proposition 54.1.49: both morphism spaces biject with the families $(g(k))_{k\neq i}$ satisfying the away-from-i squares together with the single condition $\Psi_i^B \circ \big(\bigoplus_k g(k)\big) \circ \Phi_i^A = 0$, and the bijection is natural in A and B by the uniqueness of the induced components at i.

A reflection functor at i requires i to be a sink or a source, so reflecting at every vertex in turn requires an ordering of the vertices adapted to the arrows.

Lemma 54.1.51: Sink Orderings

Let Q be a finite quiver with n vertices and without oriented cycles (definition 54.1.3). Then the vertices of Q can be listed as $i_1, \dots, i_n$ so that, with $Q_0 = Q$ and $Q_k = s_{i_k}^+ Q_{k-1}$, each i_k is a sink of Q_{k-1}, and then $Q_n = Q$. Moreover, a finite quiver whose underlying graph has no loops, no multiple edges and no cycles has no oriented cycles.

***Proof*:**
Step 1: an ordering in which every arrow points backward. The vertices can be listed so that $t(e)$ comes before $s(e)$ for every arrow e. Induct on n, the case $n = 0$ being empty. For $n \geq 1$, Q has a sink: otherwise, starting at any vertex and repeatedly following an arrow out of the current vertex produces vertices $w_0, w_1, \dots, w_n$ with an arrow from each w_{l-1} to w_l. Two of these $n+1$ vertices coincide, $w_a = w_b$ with $a < b$, and the arrows from w_a to w_b form an oriented cycle. Let

i_1 be a sink. The quiver obtained by deleting i_1 and its arrows has no oriented cycles, so by induction its vertices can be listed as $i_2, \dots, i_n$ with the required property. An arrow of Q at i_1 ends at i_1, which comes first, and every other arrow of Q is an arrow of the smaller quiver.

Step 2: each i_k is a sink of Q_{k-1}. List the vertices as in Step 1. Reflecting at a vertex reverses exactly the arrows at that vertex, and Q has no loops, since a loop is an oriented cycle. So an arrow e of Q appears in Q_{k-1} reversed once for each of its endpoints among $i_1, \dots, i_{k-1}$. Let e be an arrow at i_k. If $t(e) = i_k$, then $s(e)$ comes after i_k, so e has not been reversed and ends at i_k. If $s(e) = i_k$, then $t(e) = i_l$ with $l < k$, so e has been reversed once and, in Q_{k-1}, ends at i_k. Hence i_k is a sink of Q_{k-1}. After all n steps every arrow has been reversed once at each of its two endpoints, so $Q_n = Q$.

Step 3: underlying graphs without cycles. Suppose Q has an oriented cycle, and let $\gamma = e_m \cdots e_1$ be one of minimal length m, with $w_l = s(e_l)$. The vertices $w_1, \dots, w_m$ are distinct: if $w_a = w_b$ with $a < b$, then $e_{b-1} \cdots e_a$ is a shorter oriented cycle. If $m = 1$, then e_1 is a loop. If $m = 2$, then e_1 and e_2 are two arrows between w_1 and w_2, a multiple edge of the underlying graph. If $m \geq 3$, then $(w_1, \dots, w_m)$ is a cycle of the underlying graph, completing the proof.

Definition 54.1.52: Coxeter Functor

Let Q be a finite quiver without oriented cycles, and let $i_1, \dots, i_n$ be an ordering of its vertices as in lemma 54.1.51. The *Coxeter functor* is the composite

$$C^+ = S^+_{i_n} \circ \cdots \circ S^+_{i_1} \colon \mathrm{Rep}(Q) \to \mathrm{Rep}(Q)$$

in which $S^+_{i_k}$ is the reflection functor $\mathrm{Rep}(Q_{k-1}) \to \mathrm{Rep}(Q_k)$ at the sink i_k of Q_{k-1}. The corresponding Coxeter element of the underlying graph is $c = s_{i_n} \cdots s_{i_1}$ (definition 54.1.33).

When the underlying graph is of type A, D or E, proposition 54.1.49(5) and (7) show that, as long as no intermediate representation is simple at the vertex being reflected, C^+ carries a nonzero indecomposable representation to a nonzero indecomposable one and acts on its dimension vector by c. By lemma 54.1.37, the iterates of c eventually produce a vector that is not ≥ 0, so iterating C^+ must reach a representation that is simple at the vertex being reflected.

Lemma 54.1.53: Polynomials Over An Infinite Field

Let $\mathbb{F}$ be an infinite field and $N \geq 0$.

1. Every nonzero $f \in \mathbb{F}[x_1, \dots, x_N]$ satisfies $f(a) \neq 0$ for some $a \in \mathbb{F}^N$.
2. If $X_1, \dots, X_m \subseteq \mathbb{F}^N$ are subsets with $X_1 \cup \cdots \cup X_m = \mathbb{F}^N$, then for some j the only polynomial in $\mathbb{F}[x_1, \dots, x_N]$ vanishing at every point of X_j is 0.

***Proof*:**

1. Induct on N. For $N = 0$, f is a nonzero constant. For $N \geq 1$, write $f = \sum_{l=0}^{m} f_l x_N^l$ with $f_l \in \mathbb{F}[x_1, \dots, x_{N-1}]$ and $f_m \neq 0$. By induction $f_m(a') \neq 0$ for some $a' \in \mathbb{F}^{N-1}$, so $g(x_N) = f(a', x_N) = \sum_l f_l(a') x_N^l$ is a polynomial of degree m in one variable. It has at most m roots by corollary 11.3.2, and $\mathbb{F}$ is infinite, so $g(a_N) \neq 0$ for some $a_N \in \mathbb{F}$, and $a = (a', a_N)$ satisfies $f(a) \neq 0$.

2. Otherwise choose, for each j, a nonzero polynomial f_j vanishing on X_j. The ring $\mathbb{F}[x_1, \dots, x_N] = \mathbb{F}[x_1, \dots, x_{N-1}][x_N]$ is an integral domain, by proposition 9.2.3 applied once for each variable, so $f = f_1 \cdots f_m$ is nonzero. It vanishes on $X_1 \cup \cdots \cup X_m = \mathbb{F}^N$, against (1), completing the proof.

***Proof of theorem 54.1.46*:**
Let I be the vertex set of Q and $n = |I|$.

1. Let Γ be one of A_n, D_n, E_6, E_7, E_8. By theorem 54.1.32 its Tits form is positive definite, so proposition 54.1.35 and lemma 54.1.37 apply to Γ. The graph Γ is a path or a star, so it has no loops, no multiple edges and no cycles, and by lemma 54.1.51 the quiver Q has no oriented cycles and its vertices can be listed as $i_1, \dots, i_n$ with each i_k a sink of Q_{k-1} and $Q_n = Q$. Extend the list periodically: for $t \geq 1$ let $j_t = i_l$, where $1 \leq l \leq n$ and $t \equiv l \pmod{n}$. Put $Q^{(0)} = Q$ and $Q^{(t)} = s^+_{j_t} Q^{(t-1)}$. Since $Q_n = Q$, the quiver $Q^{(t)}$ is Q_l for $t \equiv l \pmod{n}$ (with $Q_0 = Q_n$), so j_{t+1} is a sink of $Q^{(t)}$ for every $t \geq 0$, and every $Q^{(t)}$ has underlying graph Γ. For $t = mn$, the product $s_{j_t} \cdots s_{j_1}$ is c^m, where $c = s_{i_n} \cdots s_{i_1}$. A representation U of some $Q^{(t)}$ with $\dim U = \alpha_j$ is isomorphic to $S(j)$: every arrow has a zero space at one of its ends, since Γ has no loops, so all maps of U are zero.

   Step 1: reflecting an indecomposable. Let V be a nonzero finite-dimensional indecomposable representation of Q, and $d = \dim_Q V$. Put $V^{(0)} = V$, and, as long as $V^{(t-1)}$ is not simple at j_t, put $V^{(t)} = S^+_{j_t}(V^{(t-1)})$, a representation of $Q^{(t)}$. Suppose that $V^{(t-1)}$ is not simple at j_t for $1 \leq t \leq N$. Then, for each such t, $V^{(t)}$ is nonzero, indecomposable and finite-dimensional, $V^{(t-1)} \cong S^-_{j_t}(V^{(t)})$, and $\dim V^{(t)} = s_{j_t} \cdots s_{j_1}(d)$. If this holds up to $t-1$, then proposition 54.1.49(5), at the sink j_t of $Q^{(t-1)}$, gives $V^{(t-1)} \in \mathrm{Rep}^{j_t,-}(Q^{(t-1)})$, shows that $V^{(t)}$ is nonzero and indecomposable, and gives $V^{(t-1)} \cong S^-_{j_t} S^+_{j_t}(V^{(t-1)}) = S^-_{j_t}(V^{(t)})$. The space $V^{(t)}(j_t)$ is the kernel of a map out of a finite-dimensional space, and proposition 54.1.49(7) gives $\dim V^{(t)} = s_{j_t}(\dim V^{(t-1)}) = s_{j_t} \cdots s_{j_1}(d)$. By lemma 54.1.37, choose $m \geq 0$ with $c^m(d) \not\geq 0$. The supposition fails for $N = mn$, since $\dim V^{(mn)} = c^m(d)$ would then be a dimension vector. Hence there is a least $T \geq 1$ such that $V^{(T-1)}$ is simple at j_T.

   Step 2: d is a positive root and determines V. By Step 1 with $N = T - 1$, and since a functor carries isomorphic representations to isomorphic ones,

$$V \cong S^-_{j_1}(V^{(1)}) \cong S^-_{j_1} S^-_{j_2}(V^{(2)}) \cong \cdots \cong S^-_{j_1} \cdots S^-_{j_{T-1}}(V^{(T-1)}) \cong S^-_{j_1} \cdots S^-_{j_{T-1}}(S(j_T))$$

   where $S(j_T)$ is the simple representation of $Q^{(T-1)}$ at j_T. Also $\alpha_{j_T} = \dim V^{(T-1)} = s_{j_{T-1}} \cdots s_{j_1}(d)$, and each s_j is its own inverse, so $d = s_{j_1} \cdots s_{j_{T-1}}(\alpha_{j_T})$. By proposition 54.1.35(1) and (4), α_{j_T} is a root and W_Γ permutes the roots, so d is a root, and $d \geq 0$, so $d \in \Phi^+_\Gamma$. Thus $\dim\colon \mathrm{Ind}(Q) \to \Phi^+_\Gamma$ is well defined. Moreover T is the least $t \geq 1$ with $s_{j_{t-1}} \cdots s_{j_1}(d) = \alpha_{j_t}$: for $t < T$ this vector is the dimension vector of $V^{(t-1)}$, which is not simple at j_t, and is therefore different from α_{j_t}, while for $t = T$ the equality holds. So T, and with it the representation $S^-_{j_1} \cdots S^-_{j_{T-1}}(S(j_T))$, depends only on d. Two nonzero finite-dimensional indecomposable representations with the same dimension vector are therefore isomorphic, and $\dim$ is injective on $\mathrm{Ind}(Q)$.

   Step 3: every positive root occurs. Let $\alpha \in \Phi^+_\Gamma$. By lemma 54.1.37, $c^m(\alpha) \not\geq 0$ for some m, so there is a least $T \geq 1$ with $s_{j_T} \cdots s_{j_1}(\alpha) \not\geq 0$. The vector $\beta = s_{j_{T-1}} \cdots s_{j_1}(\alpha)$ is a

root (proposition 54.1.35(4)) and $\beta \geq 0$ by minimality. The root $s_{j_T}(\beta)$ is not ≥ 0, so it is negative (proposition 54.1.35(2)). It agrees with β away from j_T (lemma 54.1.34(1)), so β vanishes away from j_T, $\beta = b\alpha_{j_T}$ with $b \geq 0$, and $q(\beta) = b^2 = 1$ gives $\beta = \alpha_{j_T}$. Hence $\alpha = s_{j_1} \cdots s_{j_{T-1}}(\alpha_{j_T})$. For $1 \leq t \leq T$ put $\beta_t = s_{j_t} \cdots s_{j_{T-1}}(\alpha_{j_T})$, so that $\beta_T = \alpha_{j_T}$, $\beta_1 = \alpha$, and $\beta_t = s_{j_{t-1}} \cdots s_{j_1}(\alpha) \geq 0$ by minimality of T. Put $U_T = S(j_T) \in \operatorname{Rep}(Q^{(T-1)})$ and $U_t = S^-_{j_t}(U_{t+1})$ for $t = T-1, \ldots, 1$, which is defined because j_t is a source of $Q^{(t)} = s^+_{j_t} Q^{(t-1)}$ and $s^-_{j_t} Q^{(t)} = Q^{(t-1)}$. We show by downward induction that U_t is nonzero and indecomposable with $\dim U_t = \beta_t$. This holds for $t = T$. If it holds for $t+1 \leq T$, then U_{t+1} is not simple at j_t, since otherwise $\beta_{t+1} = \alpha_{j_t}$ and $\beta_t = s_{j_t}(\alpha_{j_t}) = -\alpha_{j_t}$ would not be ≥ 0. By proposition 54.1.49(5) at the source j_t of $Q^{(t)}$, $U_{t+1} \in \operatorname{Rep}^{j_t,+}(Q^{(t)})$ and U_t is nonzero and indecomposable, and by proposition 54.1.49(7), $\dim U_t = s_{j_t}(\beta_{t+1}) = \beta_t$. So U_1 is a nonzero finite-dimensional indecomposable representation of $Q^{(0)} = Q$ with dimension vector α, and dim is surjective.

Step 4: conclusion. The map $\dim\colon \operatorname{Ind}(Q) \to \Phi^+_\Gamma$ is a bijection, and Φ^+_Γ is finite by proposition 54.1.35(3), so Q is of finite type over $\mathbb{F}$. This proves (1).

2. Let $\mathbb{F}$ be infinite and Q of finite type over $\mathbb{F}$. Let $\underline{d} \in \mathbb{Z}^I$ with $\underline{d} \geq 0$ and $\underline{d} \neq 0$. By theorem 54.1.32, applied to the connected graph Γ, it suffices to show $q(\underline{d}) \geq 1$.

   Step 1: finitely many isomorphism classes of dimension vector $\underline{d}$. Let V be a representation with $\dim_Q V = \underline{d}$. By theorem 54.1.24, V is a direct sum of indecomposable subrepresentations, and discarding the zero summands, $V = V_1 \oplus \cdots \oplus V_r$ with every V_l nonzero, finite-dimensional and indecomposable, so $[V_l] \in \operatorname{Ind}(Q)$. Dimension vectors add, so $\sum_l \dim_Q V_l = \underline{d}$, and each V_l has total dimension at least 1, so $r \leq |\underline{d}| = \sum_i d_i$. A direct sum of isomorphisms is an isomorphism, so the isomorphism class of V is determined by the list $([V_1], \ldots, [V_r])$, and there are at most $\sum_{r=0}^{|\underline{d}|} |\operatorname{Ind}(Q)|^r$ such lists.

   Step 2: an orbit on which no nonzero polynomial vanishes. By theorem 54.1.20, the $G(\underline{d})$-orbits in $\operatorname{Rep}(Q, \underline{d})$ correspond bijectively to these isomorphism classes, so there are finitely many orbits $O_1, \ldots, O_m$, and they cover $\operatorname{Rep}(Q, \underline{d})$. Identify $\operatorname{Rep}(Q, \underline{d})$ with $\mathbb{F}^N$, where $N = \sum_e d_{s(e)} d_{t(e)}$, through the matrix entries, with coordinates $x_1, \ldots, x_N$. By lemma 54.1.53(2), some orbit $O = G(\underline{d}) \cdot A_0$ has the property that the only polynomial in $x_1, \ldots, x_N$ vanishing at every point of O is 0.

   Step 3: the orbit map. Let $M = \sum_i d_i^2$, let $\mathbb{F}[g]$ be the polynomial ring in M variables, one for each entry of each matrix g_i with $d_i \geq 1$, and identify a point of $\mathbb{F}^M$ with a tuple of matrices $a = (a_i)_i$. Let $D = \prod_i \det(g_i) \in \mathbb{F}[g]$, the product over the vertices with $d_i \geq 1$, which is a polynomial by the formula for the determinant (definition 13.4.5) and is nonzero because it takes the value 1 at the identity matrices. The group $G(\underline{d})$ is the set of points a with $D(a) \neq 0$. For such a, $a_i^{-1} = \det(a_i)^{-1} \operatorname{adj}(a_i)$ by proposition 13.4.12, and the entries of $\operatorname{adj}(a_i)$ are determinants of matrices whose entries are entries of a_i, 0 or 1 (definition 13.4.10), hence values of fixed polynomials at a. Multiplying numerator and denominator by $\prod_{i \neq s(e)} \det(a_i)$, each coordinate of $(a \cdot A_0)_e = a_{t(e)} (A_0)_e a_{s(e)}^{-1}$ is $P(a)/D(a)$ for a polynomial $P \in \mathbb{F}[g]$ that does not depend on a. Let $\varphi_1, \ldots, \varphi_N$ be the resulting fractions P/D in the field of fractions $\mathbb{F}(g)$ of $\mathbb{F}[g]$, and let $R = \left\{ P/D^l \;\middle|\; P \in \mathbb{F}[g],\ l \geq 0 \right\} \subseteq \mathbb{F}(g)$. For $a \in G(\underline{d})$, evaluation $P/D^l \mapsto P(a)/D(a)^l$ is a well-defined ring homomorphism $\operatorname{ev}_a\colon R \to \mathbb{F}$. It is well defined, since $P_1/D^{l_1} = P_2/D^{l_2}$ gives $P_1 D^{l_2} = P_2 D^{l_1}$, and evaluating at a gives equal values. It respects sums and products, since evaluation at a respects them on $\mathbb{F}[g]$ and $D(a) \neq 0$, and $\operatorname{ev}_a(\varphi_j) = x_j(a \cdot A_0)$. Substituting φ_j for x_j defines an $\mathbb{F}$-algebra homomorphism $\Lambda\colon \mathbb{F}[x_1, \ldots, x_N] \to R$ (theorem 9.2.4, applied once

for each variable). For $a \in G(\underline{d})$, the two $\mathbb{F}$-algebra homomorphisms $f \mapsto \mathrm{ev}_a(\Lambda(f))$ and $f \mapsto f(a \cdot A_0)$ agree on $x_1, \dots, x_N$, so by the uniqueness in the same universal property, $\mathrm{ev}_a(\Lambda(f)) = f(a \cdot A_0)$ for every polynomial f.

Step 4: one entry normalized. Choose a vertex i_0 with $d_{i_0} \geq 1$, let $z \in \mathbb{F}[g]$ be the variable for the $(1,1)$ entry of g_{i_0}, and let $\mathbb{F}[y]$ be the polynomial ring in the other $M-1$ variables. Substituting 1 for z is an $\mathbb{F}$-algebra homomorphism $\sigma\colon \mathbb{F}[g] \to \mathbb{F}[y]$, and $\sigma(D) \neq 0$ because $\sigma(D)$ takes the value 1 at the entries of the identity matrices. As in Step 3, σ extends to a ring homomorphism $R \to \mathbb{F}(y)$, $P/D^l \mapsto \sigma(P)/\sigma(D)^l$, and $\Theta = \sigma \circ \Lambda\colon \mathbb{F}[x_1, \dots, x_N] \to \mathbb{F}(y)$ is an $\mathbb{F}$-algebra homomorphism. We show that Θ is injective. Let $\Theta(f) = 0$ and write $\Lambda(f) = P/D^l$, so that $\sigma(P) = 0$. Let $a \in G(\underline{d})$ have $(1,1)$ entry $c = z(a) \neq 0$ in a_{i_0}. Then $c^{-1}a \in G(\underline{d})$ has $(1,1)$ entry 1 in its component at i_0, and $(c^{-1}a) \cdot A_0 = a \cdot A_0$ because the scalars cancel in $a_{t(e)}(A_0)_e a_{s(e)}^{-1}$. At a point where $z = 1$, the value of P is the value of $\sigma(P) = 0$, so

$$f(a \cdot A_0) = f((c^{-1}a) \cdot A_0) = \mathrm{ev}_{c^{-1}a}(\Lambda(f)) = \frac{P(c^{-1}a)}{D(c^{-1}a)^l} = 0$$

Hence $P(a) = D(a)^l \,\mathrm{ev}_a(\Lambda(f)) = D(a)^l f(a \cdot A_0) = 0$ for every $a \in \mathbb{F}^M$ with $D(a)z(a) \neq 0$, so the polynomial PDz vanishes at every point of $\mathbb{F}^M$. By lemma 54.1.53(1) it is 0, and since $\mathbb{F}[g]$ is an integral domain and D and z are nonzero, $P = 0$. Then $\Lambda(f) = 0$, so $f(a \cdot A_0) = \mathrm{ev}_a(\Lambda(f)) = 0$ for every $a \in G(\underline{d})$. Thus f vanishes on O, and $f = 0$ by Step 2.

Step 5: the count. By Step 4, a polynomial f with $f(\Theta(x_1), \dots, \Theta(x_N)) = \Theta(f) = 0$ is zero, so $\Theta(x_1), \dots, \Theta(x_N)$ are N distinct elements of $\mathbb{F}(y)$, algebraically independent over $\mathbb{F}$. By theorem 19.2.13, applied to the extension $\mathbb{F}(y)/\mathbb{F}$ with $S = \mathbb{F}(y)$ and $A = \{\Theta(x_1), \dots, \Theta(x_N)\}$, they lie in a transcendence basis B of $\mathbb{F}(y)/\mathbb{F}$. The $M-1$ variables y are algebraically independent and generate $\mathbb{F}(y)$, so they form a transcendence basis (definition 19.2.12), and $|B| = M-1$ by theorem 19.2.15. Hence $N \leq M-1$, that is,

$$q(\underline{d}) = \sum_{i \in I} d_i^2 - \sum_{e \in E} d_{s(e)} d_{t(e)} = M - N \geq 1$$

As $\underline{d}$ was an arbitrary nonzero vector with $\underline{d} \geq 0$, condition (3) of theorem 54.1.32 holds, and Γ is one of A_n, D_n, E_6, E_7, E_8, completing the proof.

Example 54.1.54: Indecomposable Representations Of A Linearly Oriented A_n

Let Q be $1 \to 2 \to \cdots \to n$. For $1 \leq i \leq j \leq n$, let $V_{[i,j]}$ be the representation with $V_{[i,j]}(l) = \mathbb{F}$ for $i \leq l \leq j$ and $V_{[i,j]}(l) = 0$ otherwise, the identity along each arrow $l \to l+1$ with $i \leq l < j$, and zero maps elsewhere. Its dimension vector is $\alpha_i + \cdots + \alpha_j$.

Each $V_{[i,j]}$ is indecomposable. Suppose $V_{[i,j]}(l) = U(l) \oplus U'(l)$ at every vertex, for subrepresentations U and U'. For $i \leq l \leq j$ the space $\mathbb{F}$ is one-dimensional, so exactly one of $U(l)$ and $U'(l)$ is $\mathbb{F}$. If $U(l) = \mathbb{F}$ and $l < j$, then $U(l+1)$ contains the image of $U(l)$ under the identity, so $U(l+1) = \mathbb{F}$. If $U(l) = \mathbb{F}$ and $l > i$, then $U'(l-1)$ maps injectively into $U'(l) = 0$, so $U'(l-1) = 0$ and $U(l-1) = \mathbb{F}$. Hence $U(l) = \mathbb{F}$ for all $i \leq l \leq j$ or for none of them, and one of U, U' is zero.

By theorem 54.1.46(1) and example 54.1.36, the dimension vectors of the nonzero finite-dimensional indecomposable representations of Q are exactly the vectors $\alpha_i + \cdots + \alpha_j$, each realized by a single isomorphism class. So the representations $V_{[i,j]}$, for $1 \leq i \leq j \leq n$, are up to isomorphism

all the nonzero finite-dimensional indecomposable representations of Q, over every field, and by theorem 54.1.24 every finite-dimensional representation of Q is isomorphic to a direct sum of them. For $n = 3$ these are the six representations, in which the unlabelled arrows are zero maps,

$$\begin{aligned} \mathbb{F} &\longrightarrow 0 \longrightarrow 0 & \mathbb{F} &\xrightarrow{1} \mathbb{F} \longrightarrow 0 \\ 0 &\longrightarrow \mathbb{F} \longrightarrow 0 & 0 &\longrightarrow \mathbb{F} \xrightarrow{1} \mathbb{F} \\ 0 &\longrightarrow 0 \longrightarrow \mathbb{F} & \mathbb{F} &\xrightarrow{1} \mathbb{F} \xrightarrow{1} \mathbb{F} \end{aligned}$$

with dimension vectors the six positive roots of A_3.

54.1.5 Path Algebra of Quivers

A representation of a quiver assigns a linear map to each arrow, and composing these maps along a path gives a linear map from the space at its source to the space at its target. The path algebra has the paths of Q as a basis and concatenation of paths as multiplication, and theorem 54.1.58 below identifies the representations of Q with the left modules over it. Throughout, $\mathbb{F}$ is a field, arrows are denoted $a, b, \ldots$, and the letter e_i is reserved for the trivial path at the vertex i.

Two paths p and q with $t(q) = s(p)$ have a *concatenation* pq, the path from $s(q)$ to $t(p)$ that traverses the arrows of q and then those of p. If $p = a_k \cdots a_1$ and $q = b_m \cdots b_1$ have positive length, then $pq = a_k \cdots a_1 b_m \cdots b_1$, which is a path because $t(b_m) = t(q) = s(p) = s(a_1)$. A trivial path leaves the other factor unchanged, $pe_{s(p)} = p$ and $e_{t(q)}q = q$. The length of pq is the sum of the lengths of p and q, and concatenation is associative: if also $t(r) = s(q)$, then $(pq)r$ and $p(qr)$ are both the path from $s(r)$ that traverses the arrows of r, then those of q, then those of p.

Definition 54.1.55: Path Algebra

Let $Q = (I, E, s, t)$ be a quiver. The *path algebra* $\mathbb{F}Q$ of Q over $\mathbb{F}$ is the $\mathbb{F}$-vector space with basis the set of all paths in Q (definition 54.1.3), the trivial paths e_i for $i \in I$ included, with the $\mathbb{F}$-bilinear multiplication given on paths p and q by

$$p \cdot q = \begin{cases} pq & \text{if } t(q) = s(p) \\ 0 & \text{otherwise} \end{cases}$$

So $p \cdot q$ traverses q first and then p.

Proposition 54.1.56: Structure Of The Path Algebra

Let $Q = (I, E, s, t)$ be a quiver, and for $n \geq 0$ let $(\mathbb{F}Q)_n \subseteq \mathbb{F}Q$ be the span of the paths of length n.

1. The multiplication of $\mathbb{F}Q$ is associative.
2. The trivial paths are orthogonal idempotents, $e_i \cdot e_j = \delta_{ij} e_i$ for $i, j \in I$. For a path γ and a vertex j, $e_j \cdot \gamma$ is γ if $t(\gamma) = j$ and 0 otherwise, and $\gamma \cdot e_j$ is γ if $s(\gamma) = j$ and 0 otherwise. Consequently $(\mathbb{F}Q)e_i$ has basis the paths with source i, and $e_j(\mathbb{F}Q)e_i$ has basis the paths from i to j.
3. If I is finite, then $1 = \sum_{i \in I} e_i$ is an identity element of $\mathbb{F}Q$, so $\mathbb{F}Q$ is an associative $\mathbb{F}$-algebra with 1.
4. $\mathbb{F}Q = \bigoplus_{n \geq 0} (\mathbb{F}Q)_n$, the trivial paths form a basis of $(\mathbb{F}Q)_0$, and $(\mathbb{F}Q)_m \cdot (\mathbb{F}Q)_n \subseteq (\mathbb{F}Q)_{m+n}$ for all $m, n \geq 0$.
5. $\mathbb{F}Q$ is finite-dimensional if and only if Q is finite and has no oriented cycle.

***Proof*:**

1. Both $(x \cdot y) \cdot z$ and $x \cdot (y \cdot z)$ are trilinear in x, y, z, so it suffices to compare them on paths p, q, r. Recall that pq has source $s(q)$ and target $t(p)$. If $t(r) = s(q)$ and $t(q) = s(p)$, then $(p \cdot q) \cdot r = (pq)r$, because $t(r) = s(q) = s(pq)$, and $p \cdot (q \cdot r) = p(qr)$, because $t(qr) = t(q) = s(p)$, and these agree by the associativity of concatenation. If $t(q) \neq s(p)$, then $p \cdot q = 0$, and $q \cdot r$ is 0 or the path qr with target $t(q) \neq s(p)$, so both sides vanish. If $t(q) = s(p)$ and $t(r) \neq s(q)$, then $q \cdot r = 0$ and $(p \cdot q) \cdot r = (pq) \cdot r = 0$, because $s(pq) = s(q) \neq t(r)$.
2. The product $e_i \cdot e_j$ is nonzero only if $t(e_j) = s(e_i)$, that is, $j = i$, and $e_i e_i = e_i$. The product $e_j \cdot \gamma$ is nonzero only if $t(\gamma) = s(e_j) = j$, and then it is $e_j \gamma = \gamma$. The product $\gamma \cdot e_j$ is nonzero only if $s(\gamma) = t(e_j) = j$, and then it is $\gamma e_j = \gamma$. Hence for $x = \sum_\gamma c_\gamma \gamma \in \mathbb{F}Q$, the element $x \cdot e_i$ is the part of this sum over the paths with source i, and $e_j \cdot x \cdot e_i$ is the part over the paths from i to j. These paths are linearly independent, being part of a basis, which gives the two bases.
3. For a path γ, part (2) gives $(\sum_i e_i) \cdot \gamma = e_{t(\gamma)} \cdot \gamma = \gamma$ and $\gamma \cdot (\sum_i e_i) = \gamma \cdot e_{s(\gamma)} = \gamma$. By bilinearity $\sum_i e_i$ is a two-sided identity element.
4. Every path has exactly one length and the paths form a basis, so $\mathbb{F}Q = \bigoplus_n (\mathbb{F}Q)_n$, and the paths of length 0 are the trivial paths. The product of a path of length m and a path of length n is 0 or their concatenation, which has length $m + n$.
5. Suppose Q is finite with no oriented cycle, and let $\gamma = a_k \cdots a_1$ be a path of positive length. The vertices $v_0 = s(a_1)$ and $v_l = t(a_l)$ for $1 \leq l \leq k$ are pairwise distinct: if $v_p = v_q$ with $p < q$, then $a_q \cdots a_{p+1}$ is a path of positive length from v_p to $v_q = v_p$, an oriented cycle. So $k + 1 \leq |I|$. There are at most $|E|^k$ sequences of k arrows, so Q has at most $|I| + \sum_{k=1}^{|I|-1} |E|^k$ paths, and $\mathbb{F}Q$ is finite-dimensional. Conversely, if I is infinite then the trivial paths are infinitely many basis elements of $\mathbb{F}Q$, and if E is infinite then so are

the paths of length 1. If γ is an oriented cycle, of length $k \geq 1$, then $t(\gamma) = s(\gamma)$, so the products γ, $\gamma \cdot \gamma$, $\gamma \cdot \gamma \cdot \gamma, \ldots$ are paths of the distinct lengths $k, 2k, 3k, \ldots$, and again $\mathbb{F}Q$ is infinite-dimensional.

The five parts are proved, completing the proof.

Example 54.1.57: Path Algebras

1. Let Q be the quiver with one vertex 1 and one loop a. Its paths are e_1 and, for $n \geq 1$, the path a^n that traverses a n times. With $a^0 = e_1$, the product is $a^m \cdot a^n = a^{m+n}$ for all $m, n \geq 0$. The linear map $\mathbb{F}[x] \to \mathbb{F}Q$ with $x^n \mapsto a^n$ carries a basis to a basis and products of basis elements to products, so it is an isomorphism of algebras $\mathbb{F}[x] \cong \mathbb{F}Q$. The loop is an oriented cycle, and $\mathbb{F}Q$ is infinite-dimensional, in accordance with proposition 54.1.56(5).
2. With two loops a and b at one vertex, the paths are e_1 and the words in a and b, multiplied by juxtaposition. The products $a \cdot b = ab$ and $b \cdot a = ba$ are different paths, so $\mathbb{F}Q$ is not commutative.
3. Let K be the Kronecker quiver of example 54.1.28, with two arrows $a, b \colon 1 \to 2$. No arrow has source 2, so there is no path of length 2, and $\mathbb{F}K$ has basis e_1, e_2, a, b. The nonzero products of basis elements are $e_1 \cdot e_1 = e_1$, $e_2 \cdot e_2 = e_2$, $a \cdot e_1 = e_2 \cdot a = a$ and $b \cdot e_1 = e_2 \cdot b = b$.

For a representation V of Q and a path γ from i to j, let $T_\gamma \colon V(i) \to V(j)$ be $\mathrm{id}_{V(i)}$ if $\gamma = e_i$, and the composite $T_{a_k} \circ \cdots \circ T_{a_1}$ if $\gamma = a_k \cdots a_1$, writing T_γ^V when the representation must be named. If $t(q) = s(p)$, then $T_{pq} = T_p \circ T_q$, since both sides apply the maps of the arrows of q and then those of p. A quiver morphism $\varphi \colon V \to W$ satisfies

$$\varphi(j) \circ T_\gamma^V = T_\gamma^W \circ \varphi(i)$$

for every path γ from i to j, where T_a^W is the map written S_a in definition 54.1.9. For $\gamma = e_i$ both sides are $\varphi(i)$. For $\gamma = a_k \cdots a_1$ with $k \geq 1$, write $\gamma = a_k \gamma'$, where γ' is the path $a_{k-1} \cdots a_1$, or e_i if $k = 1$, from i to $l = s(a_k)$. The square of φ at a_k and induction on k give

$$\varphi(j) \circ T_{a_k}^V \circ T_{\gamma'}^V = T_{a_k}^W \circ \varphi(l) \circ T_{\gamma'}^V = T_{a_k}^W \circ T_{\gamma'}^W \circ \varphi(i)$$

and the outer terms are $\varphi(j) \circ T_\gamma^V$ and $T_\gamma^W \circ \varphi(i)$.

When Q has finitely many vertices, $\mathbb{F}Q$ has the identity element $1 = \sum_i e_i$ of proposition 54.1.56(3). Let $\mathbb{F}Q$**-Mod** denote the category of left $\mathbb{F}Q$-modules, on which 1 acts as the identity, with the $\mathbb{F}Q$-linear maps as morphisms. An $\mathbb{F}Q$-module is an $\mathbb{F}$-vector space through the action of the scalars $c = c \cdot 1 \in \mathbb{F}Q$.

Theorem 54.1.58: Representations Are Modules Over The Path Algebra

Let $Q = (I, E, s, t)$ be a quiver with finitely many vertices.

1. For a representation V of Q, let $\mathcal{M}(V) = \bigoplus_{i \in I} V(i)$, with $\iota_j \colon V(j) \to \mathcal{M}(V)$ the inclusion of the summand $V(j)$ and $\pi_j \colon \mathcal{M}(V) \to V(j)$ the projection onto it. Then $\mathcal{M}(V)$ is a left $\mathbb{F}Q$-module in which a path γ from i to j acts by $\iota_j \circ T_\gamma \circ \pi_i$. For a quiver morphism $\varphi \colon V \to W$, the map $\mathcal{M}(\varphi) = \bigoplus_i \varphi(i)$ is $\mathbb{F}Q$-linear, and $\mathcal{M}$ is a functor $\mathrm{Rep}(Q) \to \mathbb{F}Q$**-Mod**.

2. For a left $\mathbb{F}Q$-module M, let $\mathcal{R}(M)$ have the space $e_i M$ at each vertex i and the map $e_i M \to e_j M$, $m \mapsto a \cdot m$, along each arrow $a \colon i \to j$. For an $\mathbb{F}Q$-linear map $f \colon M \to N$, let $\mathcal{R}(f)(i) \colon e_i M \to e_i N$ be the restriction of f. Then $\mathcal{R}(M)$ is a representation of Q, $\mathcal{R}(f)$ is a quiver morphism, and $\mathcal{R}$ is a functor $\mathbb{F}Q$**-Mod** $\to \mathrm{Rep}(Q)$.

3. For every representation V, the maps $\eta_V(i) = \iota_i \colon V(i) \to e_i \mathcal{M}(V)$ form an isomorphism of representations $\eta_V \colon V \to \mathcal{R}(\mathcal{M}(V))$, natural in V.

4. For every left $\mathbb{F}Q$-module M, the map $\epsilon_M \colon \mathcal{M}(\mathcal{R}(M)) = \bigoplus_i e_i M \to M$, $(m_i)_{i \in I} \mapsto \sum_i m_i$, is an isomorphism of $\mathbb{F}Q$-modules, natural in M.

Consequently $\mathcal{M}$ and $\mathcal{R}$ are quasi-inverse equivalences of categories between $\mathrm{Rep}(Q)$ and $\mathbb{F}Q$**-Mod**.

***Proof*:**

1. For a path γ from i to j let $\rho(\gamma) = \iota_j \circ T_\gamma \circ \pi_i$, a linear map from $\mathcal{M}(V)$ to itself, and extend linearly to a linear map ρ from $\mathbb{F}Q$ to the algebra $\mathrm{End}_{\mathbb{F}}(\mathcal{M}(V))$ of linear maps from $\mathcal{M}(V)$ to itself. For paths p and q, the composite $\pi_{s(p)} \circ \iota_{t(q)}$ is the identity of $V(t(q))$ if $t(q) = s(p)$ and 0 otherwise. In the first case

$$\rho(p) \circ \rho(q) = \iota_{t(p)} \circ T_p \circ T_q \circ \pi_{s(q)} = \iota_{t(pq)} \circ T_{pq} \circ \pi_{s(pq)} = \rho(p \cdot q)$$

and in the second $\rho(p) \circ \rho(q) = 0 = \rho(p \cdot q)$. By bilinearity $\rho(x \cdot y) = \rho(x) \circ \rho(y)$ for all $x, y \in \mathbb{F}Q$, and $\rho(1) = \sum_i \iota_i \circ \pi_i$ is the identity. These identities, with the linearity of ρ and of each $\rho(x)$, are the axioms of a left module for $x \cdot v = \rho(x)(v)$, and a scalar $c = c \cdot 1$ acts as multiplication by c. For a quiver morphism $\varphi \colon V \to W$ and a path γ from i to j, the identity $\varphi(j) \circ T_\gamma^V = T_\gamma^W \circ \varphi(i)$ proved before the theorem gives

$$\mathcal{M}(\varphi) \circ \iota_j \circ T_\gamma^V \circ \pi_i = \iota_j \circ \varphi(j) \circ T_\gamma^V \circ \pi_i = \iota_j \circ T_\gamma^W \circ \varphi(i) \circ \pi_i = \iota_j \circ T_\gamma^W \circ \pi_i \circ \mathcal{M}(\varphi)$$

so $\mathcal{M}(\varphi)$ commutes with the action of every path, and by linearity with the action of every element of $\mathbb{F}Q$. The identities $\mathcal{M}(\psi \circ \varphi) = \mathcal{M}(\psi) \circ \mathcal{M}(\varphi)$ and $\mathcal{M}(\mathrm{id}_V) = \mathrm{id}_{\mathcal{M}(V)}$ hold summand by summand.

2. The subset $e_i M$ is an $\mathbb{F}$-subspace of M, since $c \cdot e_i m = e_i \cdot (c \cdot m)$ for $c \in \mathbb{F}$. An arrow $a \colon i \to j$ satisfies $a = e_j \cdot a$ by proposition 54.1.56(2), so $a \cdot m = e_j \cdot (a \cdot m)$ lies in $e_j M$ for every $m \in e_i M$, and $m \mapsto a \cdot m$ is a linear map $e_i M \to e_j M$. So $\mathcal{R}(M)$ is a representation. An $\mathbb{F}Q$-linear map f satisfies $f(e_i m) = e_i f(m)$, so it carries $e_i M$ into $e_i N$, and $f(a \cdot m) = a \cdot f(m)$ is the square of $\mathcal{R}(f)$ at a. Restriction preserves composites and identities.

3. The trivial path e_i acts on $\mathcal{M}(V)$ by $\iota_i \circ \pi_i$, so $e_i\mathcal{M}(V) = \iota_i(V(i))$, and $\iota_i \colon V(i) \to e_i\mathcal{M}(V)$ is a linear bijection. For an arrow $a \colon i \to j$ and $v \in V(i)$, $a \cdot \iota_i(v) = \iota_j(T_a v)$, so $\eta_V(j) \circ T_a$ is the map of $\mathcal{R}(\mathcal{M}(V))$ along a composed with $\eta_V(i)$. Hence η_V is a quiver morphism with bijective components, which is an isomorphism, as noted after definition 54.1.13. For a quiver morphism $\varphi \colon V \to W$, the morphism $\mathcal{R}(\mathcal{M}(\varphi))$ is the restriction of $\bigoplus_l \varphi(l)$, and $(\bigoplus_l \varphi(l)) \circ \iota_i = \iota_i \circ \varphi(i)$, that is, $\mathcal{R}(\mathcal{M}(\varphi)) \circ \eta_V = \eta_W \circ \varphi$, which is the naturality of η.

4. Every $m \in M$ satisfies $m = 1 \cdot m = \sum_i e_i m$, so ϵ_M is surjective. If $\sum_i m_i = 0$ with $m_i = e_i m_i'$, then multiplying by e_j and using $e_j e_i = \delta_{ij} e_i$ gives $0 = \sum_i e_j e_i m_i' = m_j$ for every j, so ϵ_M is injective. Let γ be a path from i to j. Its map in $\mathcal{R}(M)$ is $m \mapsto \gamma \cdot m$: for $\gamma = e_i$ it is the identity of $e_i M$, which is $m \mapsto e_i \cdot m$, and for $\gamma = a_k \cdots a_1$ it is $m \mapsto a_k \cdot (\cdots (a_1 \cdot m)) = \gamma \cdot m$, because the product $a_k \cdot \cdots \cdot a_1$ in $\mathbb{F}Q$ is the path γ. So γ sends $(m_l)_l \in \mathcal{M}(\mathcal{R}(M))$ to $\iota_j(\gamma \cdot m_i)$. Each $m_l \in e_l M$ satisfies $m_l = e_l \cdot m_l$, and $\gamma \cdot e_l = 0$ for $l \neq i$ by proposition 54.1.56(2), so

$$\epsilon_M\left(\gamma \cdot (m_l)_l\right) = \gamma \cdot m_i = \sum_l \gamma \cdot e_l \cdot m_l = \gamma \cdot \epsilon_M\left((m_l)_l\right)$$

   By linearity ϵ_M is $\mathbb{F}Q$-linear, and a bijective $\mathbb{F}Q$-linear map is an isomorphism of modules. For an $\mathbb{F}Q$-linear map $f \colon M \to N$, $\epsilon_N\left((f(m_l))_l\right) = \sum_l f(m_l) = f\left(\epsilon_M((m_l)_l)\right)$, which is the naturality of ϵ.

Items (3) and (4) give natural isomorphisms $\mathrm{id}_{\mathrm{Rep}(Q)} \cong \mathcal{R} \circ \mathcal{M}$ and $\mathcal{M} \circ \mathcal{R} \cong \mathrm{id}_{\mathbb{F}Q\textbf{-Mod}}$ (definition 18.2.1), which by definition 18.2.2 make $\mathcal{M}$ and $\mathcal{R}$ quasi-inverse equivalences, completing the proof.

Under this equivalence, the submodules of $\mathcal{M}(V)$ are the subspaces $\bigoplus_i \iota_i(W(i))$ for the subrepresentations $W \subseteq V$. Such a subspace is a submodule because T_γ carries $W(i)$ into $W(j)$ for every path γ from i to j: this holds for trivial paths and for arrows by definition 54.1.8, and for longer paths by induction on the length, as T_γ is the composite of the maps along the arrows of γ. Conversely, a submodule N contains $e_i n$ for each of its elements $n = \sum_i e_i n$, so $N = \bigoplus_i e_i N$ with $e_i N \subseteq \iota_i(V(i))$, and the subspaces $W(i) = \iota_i^{-1}(e_i N)$ form a subrepresentation, because $a \cdot e_i N \subseteq e_j N$ for every arrow $a \colon i \to j$. The two recipes are inverse to each other: starting from W, $e_i\big(\bigoplus_j \iota_j(W(j))\big) = \iota_i(W(i))$, so ι_i^{-1} of it is $W(i)$, and starting from N, $\bigoplus_i \iota_i\big(\iota_i^{-1}(e_i N)\big) = \bigoplus_i e_i N = N$. So V is simple exactly when $\mathcal{M}(V)$ is a simple module, and V is the internal direct sum of subrepresentations $U_1, \ldots, U_n$ exactly when $\mathcal{M}(V)$ is the internal direct sum of the corresponding submodules.

By proposition 54.1.56(2), the left ideal $\mathbb{F}Qe_i$ has basis the paths with source i. The representation with the paths from i to j as a basis at each vertex j is defined for every quiver, and when Q has finitely many vertices it corresponds to $\mathbb{F}Qe_i$ under theorem 54.1.58 (lemma 54.1.59(6) below).

Lemma 54.1.59: The Representation Of Paths From A Vertex

Let $Q = (I, E, s, t)$ be a quiver and $i \in I$. For each vertex j let $P_i(j) = e_j(\mathbb{F}Q)e_i$, the span of the paths from i to j, and for each arrow $a\colon j \to k$ let $P_i(j) \to P_i(k)$ be the map $x \mapsto a \cdot x$.

1. These spaces and maps form a representation P_i of Q, and its map along a path γ from j to k is $x \mapsto \gamma \cdot x$.
2. For every representation V of Q, the map $\mathrm{Hom}_Q(P_i, V) \to V(i)$, $\psi \mapsto \psi(i)(e_i)$, is an isomorphism of vector spaces, natural in V in the sense that $(\varphi \circ \psi)(i)(e_i) = \varphi(i)(\psi(i)(e_i))$ for every quiver morphism $\varphi\colon V \to W$. Its inverse sends $v \in V(i)$ to the quiver morphism ψ^v with $\psi^v(j)(\gamma) = T_\gamma(v)$ for every path γ from i to j.
3. P_i is projective: for every quiver morphism $\sigma\colon V \to W$ with every $\sigma(j)$ surjective and every quiver morphism $f\colon P_i \to W$, there is a quiver morphism $g\colon P_i \to V$ with $\sigma \circ g = f$.
4. The only elements $x \in e_i(\mathbb{F}Q)e_i$ with $x \cdot x = x$ are 0 and e_i, and P_i is nonzero and indecomposable.
5. P_i is simple if and only if i is a sink, and then $P_i \cong S(i)$.
6. If I is finite, then $P_i = \mathcal{R}(\mathbb{F}Qe_i)$ and $\mathcal{M}(P_i) \cong \mathbb{F}Qe_i$ as left $\mathbb{F}Q$-modules, for the functors of theorem 54.1.58.

***Proof*:**

1. For an arrow $a\colon j \to k$, proposition 54.1.56(2) gives $a = e_k \cdot a \cdot e_j$, so left multiplication by a carries $e_j(\mathbb{F}Q)e_i$ into $e_k(\mathbb{F}Q)e_i$, and it is linear. For a path $\gamma = a_l \cdots a_1$ from j to k, the map along γ is $x \mapsto a_l \cdot (\cdots (a_1 \cdot x)) = \gamma \cdot x$, since the product of the arrows $a_l, \ldots, a_1$ in $\mathbb{F}Q$ is γ. For $\gamma = e_j$ it is the identity, which is $x \mapsto e_j \cdot x$ on $e_j(\mathbb{F}Q)e_i$.
2. The map $\psi \mapsto \psi(i)(e_i)$ is linear for the vector space structure of proposition 54.1.10. Given $v \in V(i)$, define $\psi^v(j)\colon P_i(j) \to V(j)$ on the basis of paths from i to j by $\psi^v(j)(\gamma) = T_\gamma(v)$, extended linearly. For an arrow $a\colon j \to k$ and a path γ from i to j,
$$\psi^v(k)(a \cdot \gamma) = T_{a\gamma}(v) = T_a(T_\gamma(v)) = T_a\left(\psi^v(j)(\gamma)\right)$$
so ψ^v is a quiver morphism, and $\psi^v(i)(e_i) = T_{e_i}(v) = v$. Hence $\psi \mapsto \psi(i)(e_i)$ is surjective. Now let $\psi \in \mathrm{Hom}_Q(P_i, V)$ and $v = \psi(i)(e_i)$. By part (1), a path γ from i to j is the image $T_\gamma^{P_i}(e_i)$ of e_i under the map of P_i along γ, so the identity $\psi(j) \circ T_\gamma^{P_i} = T_\gamma^V \circ \psi(i)$ for quiver morphisms gives
$$\psi(j)(\gamma) = \psi(j)\left(T_\gamma^{P_i}(e_i)\right) = T_\gamma^V\left(\psi(i)(e_i)\right) = T_\gamma(v) = \psi^v(j)(\gamma)$$
So $\psi = \psi^v$ is determined by v, the map $\psi \mapsto \psi(i)(e_i)$ is injective, and $v \mapsto \psi^v$ is its inverse. The naturality identity is the definition of the composite, $(\varphi \circ \psi)(i) = \varphi(i) \circ \psi(i)$.
3. Let $w = f(i)(e_i)$, and choose $v \in V(i)$ with $\sigma(i)(v) = w$. Then $g = \psi^v$ satisfies $(\sigma \circ g)(i)(e_i) = \sigma(i)(v) = w = f(i)(e_i)$, and the injectivity in part (2), for the representation W, gives $\sigma \circ g = f$.

4. By proposition 54.1.56(2) and (4), an element $x \in e_i(\mathbb{F}Q)e_i$ is a finite sum $x = \sum_{n\geq 0} x_n$, with x_n in the span of the paths of length n from i to i, and $x_0 = ce_i$ for some $c \in \mathbb{F}$, since e_i is the only path of length 0 from i to i. Suppose $x \cdot x = x$. Every product $x_m \cdot x_n$ with $m+n > 0$ lies in $(\mathbb{F}Q)_{m+n}$, so the component of $x \cdot x$ in $(\mathbb{F}Q)_0$ is $x_0 \cdot x_0 = c^2 e_i$, and $c^2 = c$, that is, c is 0 or 1. If $c = 0$ and $x \neq 0$, let $m \geq 1$ be least with $x_m \neq 0$. Every product $x_p \cdot x_q$ with x_p and x_q nonzero lies in $(\mathbb{F}Q)_{p+q}$ with $p + q \geq 2m > m$, so the component of $x \cdot x$ in $(\mathbb{F}Q)_m$ is 0, while that of x is $x_m \neq 0$, which contradicts $x \cdot x = x$. So $c = 0$ forces $x = 0$. If $c = 1$, then $y = e_i - x$ lies in $e_i(\mathbb{F}Q)e_i$, on which e_i is an identity element by proposition 54.1.56(2), so $y \cdot y = e_i - 2x + x \cdot x = y$, and the component of y in $(\mathbb{F}Q)_0$ is 0. By the case $c = 0$, $y = 0$, that is, $x = e_i$.

   The space $P_i(i)$ contains $e_i \neq 0$, so $P_i \neq 0$. Suppose $\theta\colon V_1 \oplus V_2 \to P_i$ is an isomorphism with V_1 and V_2 nonzero (definition 54.1.22). The maps $(v_1, v_2) \mapsto (v_1, 0)$ at the vertices form a quiver morphism ϖ of $V_1 \oplus V_2$ to itself, and $\kappa = \theta \circ \varpi \circ \theta^{-1}\colon P_i \to P_i$ is a quiver morphism with $\kappa \circ \kappa = \kappa$. It is nonzero, because $V_1 \neq 0$, and it is not id_{P_i}, because it vanishes on the nonzero subrepresentation $\theta(0 \oplus V_2)$. Let $x = \kappa(i)(e_i) \in e_i(\mathbb{F}Q)e_i$. By part (2), $\kappa = \psi^x$, and $\psi^x(j)(\gamma) = T_\gamma^{P_i}(x) = \gamma \cdot x$ by part (1), so $\kappa(j)(y) = y \cdot x$ for every $y \in P_i(j)$. Then
   $$x \cdot x = \kappa(i)(x) = (\kappa \circ \kappa)(i)(e_i) = \kappa(i)(e_i) = x$$
   and x is neither 0 nor e_i, because $\psi^0 = 0$ and $\psi^{e_i} = \mathrm{id}_{P_i}$. This contradicts the first paragraph, so P_i is indecomposable.

5. If i is a sink, then no arrow has source i, so the only path from i is e_i, since a path $a_l \cdots a_1$ of positive length from i has $s(a_1) = i$. Then $P_i(i) = \mathbb{F}e_i$, $P_i(j) = 0$ for $j \neq i$, and every map of P_i is zero, so the maps $e_i \mapsto 1$ at i and 0 elsewhere form an isomorphism $P_i \to S(i)$. As P_i is nonzero and its only nonzero space $P_i(i)$ is one-dimensional, its only subrepresentations are 0 and P_i, so P_i is simple. If i is not a sink, choose an arrow $a\colon i \to k$, and let $U(j) \subseteq P_i(j)$ be the span of the paths of positive length from i to j. Left multiplication by an arrow carries such a path to a path of greater length, so U is a subrepresentation. It is nonzero, since $a \in U(k)$, and it is not P_i, since $e_i \notin U(i)$. So P_i is not simple.

6. The representation $\mathcal{R}(\mathbb{F}Qe_i)$ has the space $e_j(\mathbb{F}Qe_i) = P_i(j)$ at each vertex j, and its map along an arrow a is left multiplication by a, so it is P_i. By theorem 54.1.58(4), $\epsilon_{\mathbb{F}Qe_i}$ is an isomorphism from $\mathcal{M}(P_i) = \mathcal{M}(\mathcal{R}(\mathbb{F}Qe_i))$ onto $\mathbb{F}Qe_i$.

The six parts are proved, completing the proof.

Part (4) holds whether or not Q has oriented cycles, although P_i is infinite-dimensional when an oriented cycle passes through i. Part (3) corresponds to the projectivity of the module $\mathbb{F}Qe_i$: when I is finite, every $x \in \mathbb{F}Q$ is $x \cdot e_i + x \cdot (1 - e_i)$, and $e_i \cdot (1 - e_i) = 0$, so $\mathbb{F}Q = \mathbb{F}Qe_i \oplus \mathbb{F}Q(1 - e_i)$ exhibits $\mathbb{F}Qe_i$ as a direct summand of the free module $\mathbb{F}Q$, which makes it projective by theorem 17.2.4. If Q is finite without oriented cycles, then $\mathbb{F}Q$ is finite-dimensional by proposition 54.1.56(5), and by part (4) and theorem 52.3.2 each e_i is a primitive idempotent. So $1 = \sum_i e_i$ is a decomposition into primitive orthogonal idempotents, and the left ideals $\mathbb{F}Qe_i \cong \mathcal{M}(P_i)$ are the indecomposable projective modules Ae_i of definition 52.3.3 for $A = \mathbb{F}Q$.

Example 54.1.60: The Representations P_i

1. For $1 \xrightarrow{a} 2$, the paths from 1 are e_1 and a, so $P_1(1) = \mathbb{F}e_1$ and $P_1(2) = \mathbb{F}a$, with $e_1 \mapsto a$ along a, and $P_1 \cong (\mathbb{F} \xrightarrow{1} \mathbb{F})$. The vertex 2 is a sink, and $P_2 \cong S(2) = (0 \to \mathbb{F})$. So the indecomposable representation $\mathbb{F} \xrightarrow{1} \mathbb{F}$ of example 54.1.23 is projective, and it is not simple, as lemma 54.1.59(5) requires of P_1, the vertex 1 not being a sink.
2. For the loop quiver of example 54.1.57(1), $P_1(1) = \mathbb{F}Q \cong \mathbb{F}[x]$, on which the loop acts by multiplication by x. This representation is infinite-dimensional and indecomposable.
3. For the Kronecker quiver K, $P_1(1) = \mathbb{F}e_1$ and $P_1(2) = \mathbb{F}a \oplus \mathbb{F}b$, with $e_1 \mapsto a$ along a and $e_1 \mapsto b$ along b, and $P_2 \cong S(2)$. By lemma 54.1.59(2), $\mathrm{Hom}_K(P_2, P_1) \cong P_1(2)$ is two-dimensional.

Exercise 54.1.1

1. Let K be the Kronecker quiver of example 54.1.28, with arrows $a, b\colon 1 \to 2$. For $\lambda \in \mathbb{F}$ let V_λ be the representation with $V_\lambda(1) = V_\lambda(2) = \mathbb{F}$, $T_a = 1$ and $T_b = \lambda$. Show that every V_λ is indecomposable and that $V_\lambda \cong V_\mu$ only if $\lambda = \mu$. Conclude that K is not of finite type over an infinite field, as theorem 54.1.46 predicts.
2. Let L be the quiver with one vertex and one loop. For $m \geq 1$ let J_m be the representation $\mathbb{F}^m$ whose loop acts by the nilpotent Jordan block N_m, with $N_m\varepsilon_1 = 0$ and $N_m\varepsilon_l = \varepsilon_{l-1}$ for $l \geq 2$. Show that J_m is indecomposable, and deduce that L is not of finite type over any field, finite or infinite. Which extended Dynkin diagram is the underlying graph of L?
3. Let $\mathbb{F}$ be algebraically closed and let L and N_m be as in exercise 54.1.1 (2). For $\lambda \in \mathbb{F}$ and $m \geq 1$ let $J_m(\lambda)$ be the representation $\mathbb{F}^m$ of L on which the loop acts by $\lambda I_m + N_m$, so that $J_m(0) = J_m$. Show that the simple finite-dimensional representations of L are the representations $J_1(\lambda)$, $\lambda \in \mathbb{F}$, and that these are pairwise non-isomorphic. Using theorem 14.4.5, show that every finite-dimensional representation of L is an internal direct sum of subrepresentations each isomorphic to some $J_m(\lambda)$. Deduce from exercise 54.1.1 (2) that every $J_m(\lambda)$ is indecomposable, and show that $J_m(\lambda) \cong J_{m'}(\lambda')$ only if $m = m'$ and $\lambda = \lambda'$.
4. Show that D_4 has exactly 12 positive roots, and list them. (Write the Tits form as a sum of squares, one for each vertex of degree one and one for the central vertex.)
5. Let $\varepsilon_1, \ldots, \varepsilon_{n+1}$ be the standard basis of $\mathbb{R}^{n+1}$. Show that the linear map $\mathbb{R}^n \to \mathbb{R}^{n+1}$ sending α_i to $\varepsilon_i - \varepsilon_{i+1}$ carries the symmetric form of A_n to the dot product and Φ_{A_n} onto $\{\varepsilon_i - \varepsilon_j \mid i \neq j\}$. Show that, under this map, s_i becomes the exchange of the i-th and $(i+1)$-st coordinates, and deduce that W_{A_n} is isomorphic to the symmetric group on $n+1$ letters.
6. For A_2 and the Coxeter element $c = s_2 s_1$, compute the matrix of c in the basis α_1, α_2, show that $c^3 = \mathrm{id}$, and verify lemma 54.1.37 directly for $v = \alpha_1$ and for $v = \alpha_1 + \alpha_2$.
7. Let Q be $1 \to 2 \leftarrow 3$ and let V be the representation $\mathbb{F} \xrightarrow{1} \mathbb{F} \xleftarrow{1} \mathbb{F}$. Compute $S_2^+(V)$, show that it is indecomposable, and compare its dimension vector with $s_2(\dim_Q V)$.
8. Use theorem 54.1.46 to list, up to isomorphism, the nonzero finite-dimensional indecomposable representations of $1 \to 2 \leftarrow 3$.

9. For $a, b, c \geq 1$, show that the star $T(a, b, c)$ of definition 54.1.29 has positive definite Tits form if and only if
$$\frac{1}{a+1} + \frac{1}{b+1} + \frac{1}{c+1} > 1$$

10. Let Q be $1 \to 2 \to \cdots \to n$. Show that for $i \leq j$ there is exactly one path p_{ji} from i to j, and that there is no path from j to i when $i < j$. Show that the linear map sending p_{ji} to the matrix E_{ji}, whose entry in position (j, i) is 1 and whose other entries are 0, is an isomorphism of algebras from $\mathbb{F}Q$ onto the algebra of lower triangular $n \times n$ matrices over $\mathbb{F}$, and deduce that $\dim_{\mathbb{F}} \mathbb{F}Q = \frac{n(n+1)}{2}$.

11. Let Q be a finite quiver without oriented cycles and let V be a simple representation of Q. Show that $V \cong S(i)$ for some vertex i. (Choose a vertex i with $V(i) \neq 0$ such that no arrow with source i has a target j with $V(j) \neq 0$.) Show that for the loop quiver the representation $\mathbb{F}$ on which the loop acts by 1 is simple and not isomorphic to $S(1)$.

54.2 Bound Quiver Algebras

The path algebra of definition 54.1.55 turns a quiver into an associative algebra whose modules are the quiver representations of definition 54.1.5 (theorem 54.1.58). This passage runs in one direction: every quiver produces an algebra. The converse question is the one that completes the picture. Given an abstract finite-dimensional algebra A over a field k, is there a quiver Q whose path algebra is A, or close enough to A that the two have the same representation theory? A path algebra is rarely finite-dimensional (a quiver with an oriented cycle has arbitrarily long paths, proposition 54.1.56(5)), so one cannot hope for equality on the nose. The fix is to impose relations, cutting the path algebra down by an ideal, and the content of this section is that this always suffices: over an algebraically closed field, every finite-dimensional algebra is, up to the coarsening given by Morita equivalence, a path algebra modulo relations. This is the structure theorem of Gabriel, and it makes the theory of quivers the universal combinatorial model for finite-dimensional representation theory.

The route to this statement passes through three reductions. First we cut a path algebra by an *admissible* ideal, which is what makes it finite-dimensional while keeping its arrows intact. Then we isolate the class of algebras for which the reconstruction is cleanest, the *basic* algebras, and show via Morita theory that restricting to them loses nothing. Finally we read a quiver directly off an abstract algebra A (its *Gabriel quiver*) using the Jacobson radical of chapter 52, and prove that A is the path algebra of that quiver modulo an admissible ideal. Throughout, A denotes a finite-dimensional algebra over k, modules are left modules, and $\mathrm{Jac}(A)$ is the Jacobson radical. We write kQ for the path algebra of definition 54.1.55 over k, and recall its multiplication convention: for paths p and q the product $p \cdot q$ is the concatenation "q then p", nonzero exactly when $t(q) = s(p)$. In particular a path γ from i to j satisfies $e_j \gamma e_i = \gamma$, so it lives in $e_j(kQ)e_i$; this ordering of the idempotents matters when counting arrows.

The first task is to identify, inside kQ, the piece built from arrows of positive length. The constant paths e_i span a semisimple part, a product of copies of k, and everything else is generated by the arrows. Collecting the arrow-generated part into an ideal gives the object that measures "length at least one", and its powers measure length.

Definition 54.2.1: Arrow Ideal and Admissible Ideal

Let Q be a finite quiver and kQ its path algebra over k.

1. The *arrow ideal* $R_Q \subseteq kQ$ is the two-sided ideal generated by the arrows (the paths of length 1).
2. A two-sided ideal $I \subseteq kQ$ is *admissible* if there exists an integer $m \geq 2$ with
$$R_Q^m \subseteq I \subseteq R_Q^2$$

Two facts make this definition run, both consequences of the way paths concatenate. First, R_Q^ℓ is spanned by the paths of length at least ℓ: a product of ℓ arrows is a path of length ℓ (when the concatenation is legal) and zero otherwise, and every path of length ℓ factors as such a product. Consequently $kQ = kQ_0 \oplus R_Q$ as vector spaces, where $kQ_0 = \bigoplus_i ke_i$ is the span of the constant paths, and more generally the paths of a fixed length span a complement to $R_Q^{\ell+1}$ inside R_Q^ℓ. Second, the sandwiching $R_Q^m \subseteq I \subseteq R_Q^2$ has a concrete meaning at each end. The lower bound $R_Q^m \subseteq I$ forces I to contain all sufficiently long paths, which is exactly what truncates kQ/I to finite dimension. The upper bound $I \subseteq R_Q^2$ forbids relations of length 0 or 1: no relation may involve a constant path or set a single arrow equal to a combination of other arrows. This is the condition that keeps the arrows of Q visible in the quotient, so that Q can be recovered from the algebra kQ/I rather than being partly erased by the relations.

Definition 54.2.2: Bound Quiver Algebra

Let Q be a finite quiver and $I \subseteq kQ$ an admissible ideal. The quotient
$$kQ/I$$
is called the *bound quiver algebra* (or the path algebra of Q *bound by* the relations I). The pair (Q, I) is called a *bound quiver*.

Because $R_Q^m \subseteq I$, the quotient kQ/I is spanned by the images of the paths of length less than m, of which there are finitely many when Q is finite; so a bound quiver algebra is always finite-dimensional. The constant paths e_i descend to a complete set of orthogonal idempotents summing to 1, and R_Q/I is a nilpotent ideal with $(R_Q/I)^m = 0$. In fact R_Q/I is precisely the Jacobson radical of kQ/I. Being a nilpotent two-sided ideal, it lies in the radical by theorem 52.1.8, since kQ/I is finite-dimensional and hence left Artinian. Conversely, $kQ = kQ_0 \oplus R_Q$ and $I \subseteq R_Q$ give $(kQ/I)/(R_Q/I) \cong kQ_0 = \prod_i k$, and an element $\sum_i c_i e_i + r$ of kQ/I, with $r \in R_Q/I$, acts by c_i on the one-dimensional module on which e_i acts as 1 and every other e_j as 0. The radical annihilates each of these simple modules (theorem 52.1.4), so it lies in R_Q/I. This last observation is the seed of the reconstruction theorem: the arrows of Q will be recovered from $\mathrm{Jac}(kQ/I)/\mathrm{Jac}(kQ/I)^2$.

Example 54.2.3: Loops, Truncation, and the A_2 Quiver

We compute three bound quiver algebras from the ground up.

1. *The dual numbers as a bound one-loop quiver.* Let Q be the quiver with one vertex 1 and

one loop $\alpha\colon 1 \to 1$:



The paths in Q are $e_1, \alpha, \alpha^2, \alpha^3, \ldots$, so as a vector space $kQ = k[\alpha]$ is the polynomial ring in one variable (identifying e_1 with 1 and concatenation of the loop with multiplication). The arrow ideal is $R_Q = (\alpha)$, and $R_Q^m = (\alpha^m)$. Take $I = (\alpha^2) = R_Q^2$, which is admissible with $m = 2$ (indeed $R_Q^2 \subseteq I \subseteq R_Q^2$). Then

$$kQ/I = k[\alpha]/(\alpha^2)$$

is the algebra of *dual numbers*, two-dimensional over k with basis $\{e_1, \alpha\}$ and the single relation $\alpha^2 = 0$. Its radical is $R_Q/I = (\alpha)$, one-dimensional, with square zero, and kQ/I modulo its radical is k: there is exactly one simple module, and it is one-dimensional. This is the smallest example of a bound quiver algebra that is not itself a path algebra, the relation $\alpha^2 = 0$ being unavoidable if one wants a finite-dimensional quotient of $k[\alpha]$.

2. *Truncating a longer loop.* Keeping the same one-loop quiver but taking instead $I = (\alpha^3) = R_Q^3$ gives $kQ/I = k[\alpha]/(\alpha^3)$, three-dimensional with basis $\{e_1, \alpha, \alpha^2\}$. Here $m = 3$; the admissibility bound $I \subseteq R_Q^2$ holds because $\alpha^3 \in R_Q^3 \subseteq R_Q^2$, and the relation still involves no constant path and no bare arrow. More generally $k[\alpha]/(\alpha^n)$ is the one-loop quiver bound by (α^n) for each $n \geq 2$, and these exhaust the local algebras arising from a single loop.

3. *The A_2 quiver, hereditary case.* Let Q be the quiver

$$1 \xrightarrow{\alpha} 2$$

with two vertices and a single arrow $\alpha\colon 1 \to 2$. The only paths are e_1, e_2, and α, so kQ is already three-dimensional and $R_Q^2 = 0$ (there is no legal concatenation of two arrows). The only admissible ideal is therefore $I = 0$: admissibility requires $I \subseteq R_Q^2 = 0$, so nothing may be quotiented, and $R_Q^2 = 0 = I$ gives the lower bound with $m = 2$. Thus $kQ/I = kQ$, a path algebra with no relations. The path algebra of a finite connected quiver is *hereditary*, meaning that every submodule of a projective module is projective (theorem 54.1.58 and [68, Corollary 1.22]), so in particular kQ is hereditary.

   Concretely kQ is isomorphic to the lower-triangular matrix algebra

$$\begin{pmatrix} k & 0 \\ k & k \end{pmatrix}$$

via $e_1 \mapsto E_{11}$, $e_2 \mapsto E_{22}$, and $\alpha \mapsto E_{21}$, where E_{ij} is the elementary matrix with a 1 in position (i, j). Lower- rather than upper-triangular is forced by the multiplication convention: the arrow $\alpha\colon 1 \to 2$ satisfies $e_2 \alpha e_1 = \alpha$, so its image must land in position $(2, 1)$, the strictly lower-triangular slot. The check is direct on the multiplication table: $e_2 \cdot \alpha \cdot e_1 = \alpha$ matches $E_{22}E_{21}E_{11} = E_{21}$, and every other product of basis elements is forced to zero on both sides. (The upper-triangular algebra is the opposite algebra, the A_2 path algebra with the arrow reversed to $2 \to 1$; we recover it from the radical in example 54.2.9.) We return to this identification once we have located the indecomposable projectives.

The dual-numbers example already shows the shape of the reconstruction: a local algebra with

radical square zero came out as a single loop bound by α^2, and the loop is exactly a basis vector of $\mathrm{Jac}/\mathrm{Jac}^2$. Before making this into a theorem, one must decide which algebras to reconstruct. Not every finite-dimensional algebra is a bound quiver algebra on the nose. The matrix algebra $M_2(k)$, for instance, is simple, so its only simple module is two-dimensional, whereas a bound quiver algebra always has all its simples one-dimensional over k when k is algebraically closed (they are the vertex simples S_i). The class for which the reconstruction is exact is singled out by demanding that the semisimple quotient $A/\mathrm{Jac}(A)$ be as small as possible: a product of division rings, with no matrix blocks of size larger than one.

Definition 54.2.4: Basic Algebra

A finite-dimensional k-algebra A is *basic* if the quotient $A/\mathrm{Jac}(A)$ is a product of division rings,

$$A/\mathrm{Jac}(A) \cong D_1 \times \cdots \times D_n$$

with each D_i a division k-algebra. Equivalently, in the Artin–Wedderburn decomposition of $A/\mathrm{Jac}(A)$ (corollary 51.2.18) every matrix block $M_{n_i}(D_i)$ has $n_i = 1$.

When k is algebraically closed the finite-dimensional division k-algebras collapse to k itself (corollary 51.2.20), so a basic algebra over such a k has

$$A/\mathrm{Jac}(A) \cong k \times \cdots \times k$$

a product of n copies of k. Two consequences are worth stating plainly. First, the simple A-modules are the n simple modules of this product, each one-dimensional over k; a basic algebra over an algebraically closed field has *all simple modules one-dimensional*. Second, the number n of simple modules equals the number of factors, and it becomes the number of vertices of the reconstructed quiver. The condition "every matrix block has size one" is precisely the condition that the regular representation of $A/\mathrm{Jac}(A)$ contains each simple exactly once, so that A is, in the language of idempotents, a sum of pairwise non-isomorphic indecomposable projectives.

Example 54.2.5: Basic and Non-Basic Algebras

The bound quiver algebras of example 54.2.3 are all basic: for $k[\alpha]/(\alpha^2)$ the radical quotient is k, and for the A_2 path algebra it is $k \times k$, both products of copies of k. The upper-triangular algebra of 2×2 matrices is basic for the same reason. By contrast $M_2(k)$ is *not* basic: it is already semisimple, so $\mathrm{Jac}(M_2(k)) = 0$ and $M_2(k)/\mathrm{Jac}(M_2(k)) = M_2(k)$ is a single 2×2 block. The group algebra $k[S_3]$ over $k = \mathbb{C}$ is not basic either, since by Maschke's theorem it is semisimple and Artin–Wedderburn gives $\mathbb{C} \times \mathbb{C} \times M_2(\mathbb{C})$, a product with a 2×2 block coming from the two-dimensional irreducible representation of S_3. These non-basic examples are not pathological; they are the reason the theorem is stated up to Morita equivalence rather than isomorphism.

The point of Morita equivalence is that it does not see the difference between an algebra and its basic model. Two algebras are Morita equivalent when their module categories are equivalent, and Morita's theorem identifies exactly which algebras share a module category with a given one: they are the endomorphism algebras of progenerators. That theory, including generators, progenerators, and the classification of Morita equivalences by bimodules, is developed in *Core Algebra* chapter 18⋆. What is used here is the criterion for a corner ring, that Ae is a progenerator exactly when the idempotent e is full, in which case A and eAe are Morita equivalent. The block structure of the radical quotient is this book's own and is settled below.

Proposition 54.2.6: Reduction to the Basic Case

Let A be a finite-dimensional k-algebra. Then there is a basic finite-dimensional k-algebra A^b, the *basic algebra of* A, that is Morita equivalent to A: the categories of left modules A-**Mod** and A^b-**Mod** are equivalent. Up to isomorphism, A^b does not depend on the choices made in its construction, and A and A^b have the same number of simple modules and the same radical quotient block *data* in the sense that $A^b/\mathrm{Jac}(A^b) \cong D_1 \times \cdots \times D_n$ where $M_{n_i}(D_i)$ are the Artin–Wedderburn blocks of $A/\mathrm{Jac}(A)$.

***Proof*:**

Step 1: the idempotent. Write $1 = e_1 + \cdots + e_r$ as a sum of primitive orthogonal idempotents, following theorem 52.3.2, so that $A = \bigoplus_j Ae_j$ expresses the regular module as a direct sum of indecomposable projectives $P_j = Ae_j$. Two of these are isomorphic exactly when the corresponding simples $P_j/\mathrm{rad}(P_j)$ and $P_{j'}/\mathrm{rad}(P_{j'})$ agree, so grouping the e_j by the isomorphism class of P_j and choosing one representative from each class produces an idempotent

$$e = e_{i_1} + \cdots + e_{i_n}$$

with n the number of simple modules. It is idempotent because the e_{i_j} are orthogonal. Set $A^b := eAe$.

Step 2: e is full. Each e_{i_j} satisfies $e_{i_j}e = e_{i_j}$, again by orthogonality, so $Ae_{i_j}A = Ae_{i_j}eA \subseteq AeA$. For an arbitrary l the projective Ae_l is isomorphic to Ae_{i_j} for some j by the choice of representatives. If $\theta\colon Ae_l \to Ae_{i_j}$ is an isomorphism, then $u = \theta(e_l) \in Ae_{i_j}$ satisfies $u = ue_{i_j}$, and the A-linearity of θ^{-1} gives $e_l = \theta^{-1}(ue_{i_j}) = u\,\theta^{-1}(e_{i_j})$, so $e_l \in Ae_{i_j}A$ and $Ae_lA \subseteq Ae_{i_j}A \subseteq AeA$. Summing,

$$1 = \sum_{l=1}^{r} e_l \in \sum_{l=1}^{r} Ae_lA \subseteq AeA$$

so $AeA = A$ and e is full.

Step 3: the equivalence. By theorem 18.3.6, a full idempotent makes Ae a progenerator with $\mathrm{End}_A(Ae)^{\mathrm{op}} \cong eAe$, so A and $A^b = eAe$ are Morita equivalent. The equivalence is $\mathrm{Hom}_A(Ae, -)$, which sends an A-module M to eM.

Step 4: A^b is basic, with the stated radical quotient. The equivalence carries the indecomposable projectives of A to those of A^b and preserves isomorphism, and $Ae = \bigoplus_j Ae_{i_j}$ retains exactly one indecomposable projective from each isomorphism class. So the regular representation of A^b contains each simple exactly once, which is what it means for A^b to be basic, and its radical quotient has all blocks of size one. The division rings are unchanged: the equivalence induces a bijection on simple modules and a ring isomorphism on their endomorphism rings, so the blocks are over the same $D_i = \mathrm{End}_A(S_i)^{\mathrm{op}}$ furnished by Schur's lemma (lemma 51.1.5). Another decomposition of 1 and another choice of representatives give an idempotent e' with $Ae' \cong Ae$, since by theorem 52.2.4 the isomorphism classes of indecomposable summands of A do not depend on the decomposition, and Ae and Ae' are both direct sums of one module from each class. Steps 2 and 3 apply to e' as well, so $e'Ae' \cong \mathrm{End}_A(Ae')^{\mathrm{op}} \cong \mathrm{End}_A(Ae)^{\mathrm{op}} \cong eAe$, and A^b does not depend on the choices up to isomorphism, completing the proof.

The reduction lets us prove the structure theorem only for basic algebras and inherit it for all

finite-dimensional algebras through the equivalence of module categories: whatever we say about the representations of $A^b = kQ_A/I$ transfers verbatim to the representations of A. From now on A is basic, and for the reconstruction assume k is algebraically closed, so that all simple modules are one-dimensional and the radical quotient is a product of copies of k. This is the setting of Gabriel's theorem, and it is where the assumption $k = \overline{k}$ earns its place: over a non-closed field the division algebras D_i reappear and the vertices of the quiver would have to be weighted by them.

The quiver attached to an abstract algebra can now be defined. Its vertices are the simple modules; its arrows count how simples fail to split off one another, measured either homologically by Ext^1 or internally by the radical filtration. That these two counts agree is the bridge between the abstract and combinatorial descriptions.

Definition 54.2.7: Ext-Quiver (Gabriel Quiver)

Let A be a basic finite-dimensional algebra over an algebraically closed field k, with simple modules $S_1, \dots, S_n$ up to isomorphism and a complete set of primitive orthogonal idempotents $e_1, \dots, e_n$ with $S_i = Ae_i/\mathrm{rad}(Ae_i)$. The *Ext-quiver* (or *Gabriel quiver*) Q_A is the quiver with

1. vertex set $\{1, \dots, n\}$, one vertex for each simple module S_i, and
2. exactly
$$\dim_k \mathrm{Ext}^1_A(S_i, S_j) = \dim_k \, e_j\big(\mathrm{Jac}(A)/\mathrm{Jac}(A)^2\big)e_i$$
arrows from i to j.

The order of the idempotents in the formula is fixed by the multiplication convention of definition 54.1.55 and is worth pausing on, since it is easy to get backwards. In the path algebra a would-be arrow from i to j satisfies $e_j \alpha e_i = \alpha$, so it lives in $e_j(kQ)e_i$; matching this, the arrows from i to j in Q_A are counted by $e_j(\mathrm{Jac}/\mathrm{Jac}^2)e_i$, with e_j on the left and e_i on the right. A source using the opposite (left-to-right) convention for path multiplication would write $e_i(\mathrm{Jac}/\mathrm{Jac}^2)e_j$ instead; the two conventions transpose the quiver, so one must commit to one. Here the commitment is to the book's convention throughout. The equality of the two counts, homological and idempotent-theoretic, is the following lemma, proved here because it is what makes the definition well-posed: the arrow count must not depend on the choice of description.

Lemma 54.2.8: Arrows Count Radical Extensions

Let A be a finite-dimensional k-algebra with primitive orthogonal idempotents $e_1, \dots, e_n$ and simple modules $S_i = Ae_i/\mathrm{rad}(Ae_i)$, and assume k is algebraically closed. Then for all i, j,
$$\mathrm{Ext}^1_A(S_i, S_j) \cong e_j\big(\mathrm{Jac}(A)/\mathrm{Jac}(A)^2\big)e_i$$
as k-vector spaces. In particular the two are equidimensional.

***Proof*:**
Write $J = \mathrm{Jac}(A)$ and $P_i = Ae_i$, the indecomposable projective with top $S_i = P_i/\mathrm{rad}(P_i)$; recall from definition 52.3.3 that $\mathrm{rad}(P_i) = Je_i$, so that $S_i = Ae_i/Je_i$.

Step 1: A projective presentation of S_i. The surjection $P_i \twoheadrightarrow S_i$ has kernel $\mathrm{rad}(P_i) = Je_i$, giving

the short exact sequence

$$0 \to Je_i \to P_i \to S_i \to 0$$

Applying $\mathrm{Hom}_A(-, S_j)$ produces the exact sequence

$$0 \to \mathrm{Hom}_A(S_i, S_j) \to \mathrm{Hom}_A(P_i, S_j) \to \mathrm{Hom}_A(Je_i, S_j) \to \mathrm{Ext}^1_A(S_i, S_j) \to 0$$

where the last term is $\mathrm{Ext}^1_A(S_i, S_j)$ and not $\mathrm{Ext}^1(P_i, S_j)$ because P_i is projective, so $\mathrm{Ext}^1_A(P_i, S_j) = 0$ and the connecting map surjects onto $\mathrm{Ext}^1(S_i, S_j)$. The definition and basic properties of Ext^1 as the obstruction to lifting homomorphisms along a projective presentation are developed in the companion volume on homological algebra ([29, Computation Of Tor and Ext]). We use only that a projective resolution computes it and that projectives have no higher self-extensions.

Step 2: Evaluating the outer terms. For any simple S_j and any module M, a homomorphism $M \to S_j$ factors through $M/\mathrm{rad}(M)$ because $\mathrm{rad}(M)$ maps into $\mathrm{rad}(S_j) = 0$. Applying this to P_i gives $\mathrm{Hom}_A(P_i, S_j) = \mathrm{Hom}_A(S_i, S_j)$, so the first two terms of the sequence in Step 1 cancel and the map between them is an isomorphism. The sequence therefore collapses to

$$0 \to \mathrm{Hom}_A(Je_i, S_j)/\big(\text{image of } \mathrm{Hom}_A(P_i, S_j)\big) \to \mathrm{Ext}^1_A(S_i, S_j) \to 0$$

but the image of $\mathrm{Hom}_A(P_i, S_j)$ in $\mathrm{Hom}_A(Je_i, S_j)$ is zero: a homomorphism $P_i \to S_j$ vanishes on $\mathrm{rad}(P_i) = Je_i$ by the factoring just noted. Hence the connecting map is an isomorphism

$$\mathrm{Ext}^1_A(S_i, S_j) \cong \mathrm{Hom}_A(Je_i, S_j)$$

Step 3: The Hom into a simple is a radical layer. Again by the factoring through the top, any homomorphism $Je_i \to S_j$ kills $\mathrm{rad}(Je_i) = J^2 e_i$, so

$$\mathrm{Hom}_A(Je_i, S_j) = \mathrm{Hom}_A\big(Je_i/J^2e_i,\, S_j\big)$$

The module Je_i/J^2e_i is semisimple, being a module over the semisimple algebra A/J, and S_j is simple, so by Schur's lemma (lemma 51.1.5) and $\mathrm{End}_A(S_j) = k$ (from $k = \overline{k}$) the space $\mathrm{Hom}_A(Je_i/J^2e_i, S_j)$ has dimension equal to the multiplicity of S_j in Je_i/J^2e_i. That multiplicity is $\dim_k e_j(Je_i/J^2e_i)$. Indeed, for a semisimple module N the map $\varphi \mapsto \varphi(e_j)$ is a linear isomorphism $\mathrm{Hom}_A(Ae_j, N) \to e_jN$, with inverse $n \mapsto (ae_j \mapsto an)$. Every homomorphism $Ae_j \to N$ vanishes on Je_j, because $JN = 0$, so $\mathrm{Hom}_A(Ae_j, N) \cong \mathrm{Hom}_A(S_j, N)$, whose dimension is again the multiplicity of S_j in N by Schur's lemma and $\mathrm{End}_A(S_j) = k$. Therefore

$$\dim_k \mathrm{Ext}^1_A(S_i, S_j) = \dim_k e_j(Je_i/J^2e_i) = \dim_k e_j(J/J^2)e_i$$

the last equality because $e_j(J/J^2)e_i = e_j(Je_i)/e_j(J^2e_i)$ and right-multiplication by e_i identifies Je_i/J^2e_i with the e_i-column of J/J^2. Assembling the three isomorphisms gives $\mathrm{Ext}^1_A(S_i, S_j) \cong e_j(J/J^2)e_i$, as we sought to show.

The lemma says the arrows of Q_A have two readings. Homologically, an arrow $i \to j$ records a one-dimensional worth of non-split extension of S_i by S_j: a module of length two with S_j as a submodule and S_i on top that does not break as $S_i \oplus S_j$. Internally, the same arrow is a basis vector of the (j, i) block of the first radical layer $\mathrm{Jac}/\mathrm{Jac}^2$. The first reading is the reason the quiver is called the Ext-quiver and explains why it is an invariant of the module category, hence of the Morita equivalence class; the second reading is the one to compute with, because $\mathrm{Jac}/\mathrm{Jac}^2$ is a finite matrix of idempotent-sandwiched subspaces. The running examples compute it.

Example 54.2.9: Gabriel Quivers of the Running Algebras
Reading off Q_A for two algebras confirms it recovers the starting quiver.

1. *The dual numbers.* Let $A = k[\alpha]/(\alpha^2)$. This is local: its only maximal ideal is (α), so $\mathrm{Jac}(A) = (\alpha)$ and there is a single simple module $S_1 = A/(\alpha) = k$, giving one vertex. The first radical layer is $\mathrm{Jac}/\mathrm{Jac}^2 = (\alpha)/(\alpha^2)$, one-dimensional with basis the image of α, and with $e_1 = 1$ the block $e_1(\mathrm{Jac}/\mathrm{Jac}^2)e_1$ is all of it. So Q_A has one vertex and one arrow, a loop:

$$\overset{1}{\circlearrowleft}\ \alpha$$

   exactly the quiver we bound in example 54.2.3. The relation to be imposed will be $\alpha^2 = 0$, recovering A.

2. *The upper-triangular algebra.* Let $A = \begin{pmatrix} k & k \\ 0 & k \end{pmatrix}$, the 2×2 upper-triangular matrices. Its radical is the strictly upper-triangular part, $\mathrm{Jac}(A) = kE_{12}$, one-dimensional with square zero. The idempotents $e_1 = E_{11}$ and $e_2 = E_{22}$ are primitive orthogonal with $e_1 + e_2 = 1$, and $A/\mathrm{Jac}(A) \cong k \times k$, so there are two vertices with simples S_1, S_2. Since $\mathrm{Jac}^2 = 0$ we have $\mathrm{Jac}/\mathrm{Jac}^2 = kE_{12}$, and we locate E_{12} by its idempotent sandwich:

$$e_1 E_{12} e_2 = E_{11}E_{12}E_{22} = E_{12}, \qquad e_2 E_{12} e_1 = E_{22}E_{12}E_{11} = 0$$

   so the one basis vector of $\mathrm{Jac}/\mathrm{Jac}^2$ sits in the block $e_1(\mathrm{Jac}/\mathrm{Jac}^2)e_2$. By definition 54.2.7 the block $e_j(\cdots)e_i$ counts arrows $i \to j$, so with $j = 1$, $i = 2$ this is one arrow $2 \to 1$:

$$2 \xrightarrow{\ \alpha\ } 1$$

   Under the identification $\alpha \mapsto E_{12}$ this is the A_2 quiver of example 54.2.3, up to relabelling the vertices, and $\mathrm{Jac}^2 = 0$ forces the admissible ideal to be $I = 0$. The algebra is hereditary, and Q_A carries no relations: the upper-triangular algebra *is* its own path algebra kQ_A.

The two examples describe the same three-dimensional hereditary algebra, once as a bound quiver algebra and once reconstructed from its radical, and the indecomposable projectives match under the identification. Take the bound-quiver presentation of example 54.2.3, the A_2 path algebra with arrow $\alpha\colon 1 \to 2$ realized as the lower-triangular matrices via $e_1 \mapsto E_{11}$, $e_2 \mapsto E_{22}$, $\alpha \mapsto E_{21}$. The indecomposable projective $P_i = kQ \cdot e_i$ is spanned by the paths starting at i: P_1 has basis $\{e_1, \alpha\}$, the trivial path at 1 together with the arrow out of 1, and is two-dimensional with top S_1 and socle S_2, while P_2 has basis $\{e_2\}$ and is the simple S_2 itself. On the matrix side these are the column modules AE_{11} and AE_{22}: the first column of the lower-triangular algebra is two-dimensional, spanned by E_{11} and E_{21} (the entries in rows 1 and 2 of column 1), and the second column is one-dimensional, spanned by E_{22}. So the indecomposable projectives read off from the primitive idempotents of theorem 52.3.2 are exactly the projective quiver representations P_i of the path algebra. The Gabriel reconstruction of example 54.2.9 applied instead the upper-triangular representative, whose radical kE_{12} sits in the opposite corner and so produces the arrow $2 \to 1$; the two matrix algebras are opposite to one another (transpose exchanges upper and lower triangular), which is exactly the transposition of the quiver that the two multiplication conventions differ by. Either way the representation theory of A_2 is the same, and the two constructions coincide.

Everything is now in place for the structure theorem. It asserts that the passage from a basic algebra to its Gabriel quiver and back to a bound quiver algebra is a round trip: A is isomorphic to kQ_A modulo an admissible ideal. The proof builds a surjection $kQ_A \twoheadrightarrow A$ by sending vertices to the primitive idempotents and arrows to a lift of the radical layer, then shows the kernel is admissible using that $\mathrm{Jac}(A)$ is nilpotent.

Theorem 54.2.10: Structure of Basic Algebras (Gabriel)

Let A be a basic finite-dimensional algebra over an algebraically closed field k, with Gabriel quiver Q_A (definition 54.2.7). Then there is an admissible ideal $I \subseteq kQ_A$ and an isomorphism of k-algebras

$$A \cong kQ_A/I$$

Consequently, by the reduction to the basic case (proposition 54.2.6), every finite-dimensional k-algebra over an algebraically closed field is Morita equivalent to a bound quiver algebra kQ/I.

The quiver Q_A is determined by A, but the ideal I is not: different admissible ideals can present isomorphic algebras, so the theorem produces *some* admissible presentation rather than a canonical one. This is the one point where the correspondence between algebras and bound quivers fails to be a clean bijection, and it is the reason bound quiver algebras are studied through their quiver plus a choice of relations rather than through the quiver alone.

***Proof*:**

Write $J = \mathrm{Jac}(A)$, and recall J is nilpotent, say $J^m = 0$ for some $m \geq 2$, because A is finite-dimensional (a nilpotent radical is the Artinian case established in theorem 52.1.8). Let $e_1, \ldots, e_n$ be the complete set of primitive orthogonal idempotents underlying Q_A, with $1 = e_1 + \cdots + e_n$ and $S_i = Ae_i/Je_i$.

Step 1: Send vertices to idempotents and arrows to a radical lift. For each vertex i of Q_A set the constant path $\varepsilon_i \in kQ_A$ to map to $e_i \in A$. For the arrows, fix for each pair (i, j) a k-basis of the block $e_j(J/J^2)e_i$; by definition 54.2.7 and lemma 54.2.8 the arrows of Q_A from i to j are in bijection with this basis. For each arrow $\alpha\colon i \to j$ choose a lift $x_\alpha \in e_jJe_i \subseteq A$ of the corresponding basis vector of $e_j(J/J^2)e_i$; such a lift exists because $e_j(J/J^2)e_i$ is a quotient of e_jJe_i. Note $x_\alpha \in e_jJe_i$ means $e_jx_\alpha e_i = x_\alpha$, which is the algebra image of the path relation $e_j\alpha e_i = \alpha$, so the assignment respects the idempotent bookkeeping.

Step 2: Extend to an algebra homomorphism. Because kQ_A is free on paths, an algebra homomorphism out of it is determined by the images of the vertices and arrows, subject only to the relations $\varepsilon_i\varepsilon_{i'} = \delta_{ii'}\varepsilon_i$, $\sum_i \varepsilon_i = 1$, and the source-target matching for arrows. The chosen images e_i and x_α satisfy all of these: the e_i are orthogonal idempotents summing to 1, and $x_\alpha \in e_jAe_i$ matches the source i and target j of α. Extend multiplicatively, sending a path $\alpha_r \cdots \alpha_1$ to the product $x_{\alpha_r} \cdots x_{\alpha_1} \in A$ (in the algebra's own multiplication, so a path from i to j lands in e_jAe_i). This defines a k-algebra homomorphism

$$\varphi\colon kQ_A \to A$$

Step 3: φ is surjective. The image contains every e_i and every x_α, and the x_α lift a basis of J/J^2. We show $\mathrm{im}\varphi = A$ by descending the filtration $A \supseteq J \supseteq J^2 \supseteq \cdots \supseteq J^m = 0$ layer by layer. The images $\varphi(\varepsilon_i) = e_i$ generate $A/J = \prod_i ke_i$ over k, so $\mathrm{im}\varphi + J = A$. Next, the products of

length one, $x_\alpha = \varphi(\alpha)$, form lifts of a basis of J/J^2, so $\mathrm{im}\varphi + J^2 \supseteq J$, hence $\mathrm{im}\varphi + J^2 = A$. Inductively suppose $\mathrm{im}\varphi + J^\ell = A$; then J^ℓ is spanned modulo $J^{\ell+1}$ by products of ℓ elements of J, each of which may be taken from the spanning set $\{x_\alpha\}$ of J modulo J^2, so products $\varphi(\alpha_\ell \cdots \alpha_1)$ of ℓ arrows span J^ℓ modulo $J^{\ell+1}$. Thus $\mathrm{im}\varphi + J^{\ell+1} = A$. Since $J^m = 0$, after m steps $\mathrm{im}\varphi = \mathrm{im}\varphi + J^m = A$, so φ is surjective.

Step 4: The kernel is admissible. Let $I = \ker\varphi$, so $A \cong kQ_A/I$. It remains to check $R_Q^{m'} \subseteq I \subseteq R_Q^2$ for some m', where R_Q is the arrow ideal of kQ_A.

For the lower bound, $\varphi(R_Q^m) \subseteq J^m = 0$: a path of length at least m is a product of at least m arrows, and each arrow maps into J, so a length-$\geq m$ path maps into $J^m = 0$. Hence $R_Q^m \subseteq \ker\varphi = I$, giving the lower bound with $m' = m$.

For the upper bound $I \subseteq R_Q^2$, suppose $u \in I$ and write $u = u_0 + u_1 + u_2$ where $u_0 \in kQ_{A,0}$ is the constant-path part, u_1 is the arrow part (length exactly one), and $u_2 \in R_Q^2$ collects the length-≥ 2 paths. We must show $u_0 = 0$ and $u_1 = 0$. Applying φ and reducing modulo J: $\varphi(u_1) \in J$ and $\varphi(u_2) \in J^2 \subseteq J$, so $0 = \varphi(u) \equiv \varphi(u_0) \pmod J$. But φ restricted to constant paths is the isomorphism $kQ_{A,0} = \prod_i k\varepsilon_i \xrightarrow{\sim} \prod_i ke_i = A/J$ (the e_i are linearly independent modulo J because they are orthogonal idempotents with distinct simple tops), so $\varphi(u_0) \equiv 0 \pmod J$ forces $u_0 = 0$. Now reduce modulo J^2: with $u_0 = 0$ we have $0 = \varphi(u) = \varphi(u_1) + \varphi(u_2)$, and $\varphi(u_2) \in J^2$, so $\varphi(u_1) \equiv 0 \pmod{J^2}$. But $\varphi(u_1)$ is the image in J/J^2 of a linear combination of arrows, and the arrows were chosen to map to a *basis* of J/J^2; a linear combination of basis vectors that is zero in J/J^2 has all coefficients zero, so $u_1 = 0$. Therefore $u = u_2 \in R_Q^2$, proving $I \subseteq R_Q^2$.

Combining the two bounds, $R_Q^m \subseteq I \subseteq R_Q^2$, so I is admissible and $A \cong kQ_A/I$ is a bound quiver algebra. The final clause on general algebras follows by composing with the Morita reduction of proposition 54.2.6: an arbitrary finite-dimensional A is Morita equivalent to its basic algebra A^b, and $A^b \cong kQ_{A^b}/I$ by what was just proved, completing the proof.

Three features of the argument deserve a closing word. The surjectivity in Step 3 is a radical-filtration induction: because $\mathrm{Jac}(A)$ is nilpotent, generating $A/\mathrm{Jac}(A)$ by the idempotents and the first radical layer $\mathrm{Jac}/\mathrm{Jac}^2$ by the arrows suffices to generate all of A, since higher layers are spanned by products. The admissibility of the kernel in Step 4 is the exact counterpart of the two bounds in definition 54.2.1: the lower bound $R_Q^m \subseteq I$ is nilpotence of the radical, and the upper bound $I \subseteq R_Q^2$ is the choice of arrows as a basis of $\mathrm{Jac}/\mathrm{Jac}^2$, which is precisely why an admissible ideal is forbidden to contain constant paths or bare arrows. And the theorem is the structure theorem of Gabriel, to be kept distinct from Gabriel's other theorem in this chapter (theorem 54.1.46), which says that a finite quiver with connected underlying graph is of finite type exactly when its graph is a simply-laced Dynkin diagram A, D, E (the converse direction proved there over an infinite field). The two results are complementary: the present one says every finite-dimensional algebra is a bound quiver algebra, and the Dynkin classification says which of the unbound path algebras have only finitely many indecomposable modules.

Part XI

Homological Algebra

Throughout this book, the reader has encountered many functors, some notable examples being $\mathrm{Hom}_R(-,N)$, $\mathrm{Hom}_R(M,-)$ and $M\otimes_R -$ among many others. Each of these functors give some information about the objects and the morphisms passing through the functor. As we saw for the Hom and $M\otimes_R -$ functors, certain appropriate objects preserve exactness, while most preserve it only partially. Perhaps a crowning achievement of mid 20th century mathematics is to be able to quantify this lack of exactness, and rather spectacularly use the information given by this quantification to extract a (sometimes copious) amount of information about the objects of study. The great effectiveness with which homological algebra can produce interesting information may seem surprising at first, for example, using homological algebra the notion of *dimension* as it is understood in geometry is readily translatable to algebra, or that we may measure how far away a module is from being a vector-space (details are in K-theory)[2] How this is the case is perhaps best motivated by going through learning the subject to see for oneself, but it may be helpful for some readers to have some of my (the authors) intuition presented to stand on some ground before proceeding.

If we have two objects M_1 and M_2, we may wish to consider a way of constructing a new object M given M_1 and M_2. Ideally, we may form a short exact sequence like so:

$$0\to M_1\to M\to M_2\to 0$$

More generally, we may have a collection of objects $\{M_i\}_{i\in I}$ which we use to construct an object via a long exact sequence. However, it is often not the case that such an exact sequence is too strong, that is, it is not the case that $\mathrm{im}(\varphi_i)=\ker(\varphi_{i+1})$. Even if such a construction exists, we often then want to "transform" this information via a functor which shall then lose us exactness (one can think of a functor as asking some sort of "question" whose output is the answer). In this case, it has been eerily common that the image of φ_i is contained in the kernel of φ_{i+1}:

$$\mathrm{im}(\varphi_i)\subseteq\ker(\varphi_{i+1}) \tag{54.1}$$

Conceptually, this can be thought as the object "being obstructed" from fully being an extension. This new type of sequence is called a *cochain complex*. The reader with a good memory may recall definition 12.2.11 where it was given that another name for a long exact sequence is an exact cochain complex. In this way, the condition given by equation 54.1 is a generalization of the exact condition. The theoretical heart of homological algebra can be thought of how to extract "quantitatively" how a cochain complex *fails* to be an exact cochain complex. For example, in chapter 17⋆ it was have eluded that through the use of homology theory, the Ext functor gives us all the ways two modules M_1, M_2 may be extended. In this case, the failure of $\mathrm{Hom}(M,-)$ or $\mathrm{Hom}(-,N)$ preserving injectivity or surjectivity (equivalently, the "obstruction" to these functors being exact) gave rise to the Ext functor and the study of its homology.

The term "algebraic object" has been is a bit ambiguous. What type of algebraic objects can be used to in the theory of homological algebra? As it turns out, not all algebraic objects satisfy the right conditions for the theory of homological algebra (for example, **Grp** and **Fld** will be shown to be inappropriate for a theory of homology). However, there are non-algebraic objects for which a homological theory can be induced (famously, topological spaces and smooth manifolds admit a theory of homological algebra). This spurred the need to generalize the theory of homological algebra to the categorical level, where homological theory is well-defined on *abelian categories*. We thus shall start homological algebra with an overview of abelian categories. For those who are already familiar with some homological algebra, they may have studied homological algebra within the category of

[2]This is overviewed in chapter 58

R-**Mod**, which is a concrete abelian category. Doing so will in fact not loose any generality due to Freyd-Mitchell Theorem (theorem 55.1.15) which states that any [small] abelian category A admits a fully faithful exact functor to a category R-**Mod** for a suitable ring R. Working with the concrete category R-**Mod** brings it benefits as it may be easier to conceptualize the manipulation of elements, and so the reader may ask for the benefit in sticking to working with general abelian categories. As the author, I believe the benefits comes in being comfortable with more advanced category theory. Future algebraists are going to encounter more complicated problems involving category theory (higher order categories, topoi's, and stacks, are all examples the reader may see in the not too distant future). Hence, introducing a categorical perspective will familiarize the reader for more complicated categorical notions in their not too distant future[3].

The reader may wonder why a cochain complex is not called a chain complex. This is because we can work in the dual category, where all arrows are flipped. In the dual category, we shall get chain complexes. Homological algebra in the dual category is theoretically the same, however we shall see that cohomology is often computationally easier to work in, permitting more useful algebraic structures we can use to study. It is for this reason that most mathematicians work with cohomology rather than homology, even though every theorem we shall show for homology translates directly to cohomology[4]. In this book, we shall start with homology, and switch to cohomology when starting to work with more computational parts of the theory to get the reader accustomed to both modes of thinking.

Goal

Chapter 55 shall introduce the theory of abelian categories which shall be the types of categories in which homological algebra is well-defined.

The main result Chapter 56 of the book is trying to convey is what information from R-modules give rise to certain properties in its respective chain complex(es), and conversely what information from it's chain complex(es) gives us information about modules. A (co)chain complex need not be exact, and (co)homology shall be the algebraic object quantifying this failure of exactness. We shall see that given an object M within an abelian category, there are in general an infinite number of ways we may associate a [co]chain complex to it. Thus, there will have to be a way to either associate a canonical [co]chain complex (in a natural functorial manner), or we assign [co]chain complexes to an object up to appropriate notion of isomorphism. The latter shall be the approach in this book, where we shall see that we will want to consider [co]chain complexes up to something called *quasi-isomorphism* of [co]chain complexes. We shall then see what cohomological information we may deduce given different choices of functors and how they transform [co]chain complexes.

After having developed the ground work for extracting cohomological information, in Chapter 58 we shall put this knowledge to good use and apply cohomology theory to G-invariant functors and see what this this can tell us about groups. This shall also finally address what was foreshadowed in box 20.4.5 where it was said the units of a Galois field form a trivial 1st homology group. We shall define the notion of homological dimension which shall line up with the results presented in the section on commutative algebra. Finally, we present an interesting technical result to check flatness of a module over a local ring that builds on the same intuitions the Nakayama lemma (lemma 52.1.7)

[3] assuming, naturally, that the reader holds great interest in algebra and shall keep pursuing branches within the field

[4] there is even an equivalent algebraic structure for the additional algebraic structure that is induced in cohomology, however it is less useful

presented.

Finally, this Part concludes with the introduction to spectral sequences in chapter 60, which are the quintessential tool for many concrete computations in homological algebra and any serious work in many disciplines of algebra and geometry. The main idea is that most object of study can be broken down into a filtration of simpler objects whose cohomology is more computed. The spectral sequence will put piece together this cohomological information.

Connection to Singular Homology/Cohomology

For readers familiar with algebraic topology and the theory of (co)homology, the connection between the above abstraction and the homology theory of topological spaces comes from noticing that singular (co)homology on a manifold can be interpreted as taking the projective resolution $C_n(X) = \mathrm{Hom}_{\mathbf{Top}}(\Delta^n, X)$. In particular, given M, we can apply $C_*(-)$ to it and get a projective (even free) resolution from which we extract homological information. This should also motivate the use of $\mathrm{Hom}_R(M, -)$ and $\mathrm{Hom}_R(-, N)$ as the "right" functors to be considering when generalizing classical algebraic topology to the algebraic setting. As the tensor product it adjoint (theorem 15.3.9) it is another natural candidate.

54.2.11 Foreshadowing: Yoneda's Lemma The Hom is very useful as it is "represented" by an element (either in the domain or codomain). Even more is true: it can be used to represent other functors. In theorem 62.2.1 this is studied *representable functors* which are functors where $F(-) \Rightarrow \mathrm{Hom}_C(A, -)$ for natural transformation $\Rightarrow$, category C, object $A \in C$, and $F : C \to \mathbf{Set}$. The Yoneda lemma will give a way of representing objects using Hom.

Historical Origins

While modern homological algebra is phrased in the language of categories, its machinery evolved from two distinct 19th-century sources which converged in the mid-20th century.

The algebraic lineage begins around 1890 with David Hilbert's Invariant Theory. To prove the Basis Theorem, Hilbert studied the relations ("syzygies") between generators of an ideal. He constructed a chain of free modules to resolve these relations:

$$0 \to F_n \to \cdots \to F_1 \to F_0 \to M \to 0$$

Hilbert proved the *Syzygy Theorem*, showing that for polynomial rings, this chain of relations eventually terminates in an exact sequence of free modules. However, this theory encountered a significant obstruction when applied to rings with singularities (such as coordinate rings of singular curves). In these non-regular settings, Hilbert's resolutions do not terminate but continue infinitely. This failure shifted the mathematical focus from simply computing invariants to essentially classifying the severity of a singularity by the infinite length of its resolution.

Parallel to this, in the 1930s, number theorists like Emmy Noether, Richard Brauer, and Helmut Hasse were attempting to classify division algebras (generalizations of the quaternions) over number fields. They classified these algebras using "Crossed Products," which relied on complex systems of functions called "Factor Sets" ($c : G \times G \to K^\times$). While they successfully defined the *Brauer Group*

of a field to organize these algebras, the calculations were notoriously opaque. The "Factor Sets" satisfied a messy algebraic identity that seemed arbitrary, acting as a computational blocker that obscured the underlying structure of the fields they were studying.

Simultaneously, from 1895 onwards, the topological roots of the subject were forming as Henri Poincaré classified manifolds. He decomposed spaces into simplices and represented their boundaries using incidence matrices. He defined Betti numbers as the ranks of these matrices. However, Poincaré's numerical approach had a blind spot: rank obliterates "torsion." A twisted shape like the projective plane appeared numerically identical to a trivial one (both have rank 0 in dimension 1).

In 1925, Emmy Noether revolutionized this view. She realized that the matrices topologists were diagonalizing were actually presentations of abelian groups. By shifting focus from the numerical rank to the *Homology Group* itself ($\ker \partial / \operatorname{im} \partial$), she captured the torsion information, effectively "algebraizing" the topology. She showed that the matrix was not just a calculator for a number, but a presentation of a structure.

The convergence of these fields occurred in the 1940s when algebraists attempted to classify *Group Extensions*. Saunders Mac Lane and Samuel Eilenberg attempted to classify these extensions and rediscovered the same "Factor Sets" used by Brauer and Hasse. They discovered that the algebraic identity these functions satisfied was *identical* to the boundary formula for a 2-simplex in topology; essentially they realized they were calculating $H^2(G, N)$ (see [26] for this computation in the EYNTKA series). This was the turning point: it proved that "cohomology" was not just a property of geometric shapes, but a fundamental algebraic structure that arose whenever one tried to "extend" one object by another, whether in topology, group theory, or number theory.

The grand unification came in 1956 when Cartan and Eilenberg realized that the topological concept of "boundaries" and the algebraic concept of "extensions" were instances of the same phenomenon: the *failure of exactness*. They observed that while Hilbert's resolution is exact, applying a functor (like the tensor product or Hom) usually destroys that exactness. They realized that the "homology" groups were simply the mathematical terms required to repair this broken exactness. This birth of the *Derived Functor* (Tor and Ext) transformed the field from the study of static objects to the study of how functors distort structure. To build this machinery, they faced a technical blocker: Hilbert's reliance on "Free Modules." While free modules worked for Homology (Tor), they failed for the dual theory of Cohomology (Ext), as the dual of a free module is rarely free. To achieve the necessary symmetry, they replaced the specific condition of "Freeness" with the categorical properties of *Projectivity* and *Injectivity*. This allowed them to define derived functors for any ring, regardless of whether a basis existed.

With this machinery established, the period from 1955 to 1980 saw these newly developed tools being used to solving the original obstructions in geometry and number theory. In geometry, Jean-Pierre Serre proved that a local ring is regular (non-singular) if and only if it has finite global homological dimension (theorem 58.2.11). This transformed the "problem" of infinite resolutions into a precise detection tool: the non-terminating resolution was effectively the algebraic signature of a geometric singularity. Alexander Grothendieck later introduced *Local Cohomology* ($H^i_{\mathfrak{m}}$) to quantify the depth and severity of these singularities, eventually leading to Intersection Homology which restored Poincaré Duality to singular spaces.

In number theory, the mysterious "Factor Sets" of the 1930s were identified as elements of the second Galois Cohomology group, $H^2(\mathrm{Gal}(L/K), L^\times)$. This realization allowed Emil Artin and John Tate to rewrite Class Field Theory entirely in the language of cohomology. The obscure identities of the past were revealed to be standard cohomological relations, and the *Tate Cohomology* groups ($\hat{H}^i$) were developed specifically to handle the arithmetic of finite groups, solving the classification problems

that had stalled the previous generation (see [77] for the EYNTKA series exposition of modern class field theory).

55

Abelian Categories

This chapter focuses on the category in which we may define "cohomological theories" as not all categories are well-suited for this endeavor

55.1 Definitions and Properties

We have extensively worked with categories which have a multitudes of different properties. Some important terms to recall are the following:

- *zero-object*: an object 0 in a category C $0 \in \text{Obj}(C)$ that is both the initial and final object. Such an object is also called a terminal object. Similarly, a zero morphism is a morphism $f : X \to Y$ such that for any other morphisms $g, h : X \to Y$, $fg = fh$ and $hf = gf$.
- *Products* and *Coproducts*: Given two objects $a, b \in \text{Obj}(C)$, if there exists an object $c \in \text{Obj}(C)$ that is the limit (resp. colimit) of the diagram:


  $$\overset{A}{\bullet} \qquad \overset{B}{\bullet}$$

  then c is the product (resp. coproduct) of a and b, and is usually written as $a \times b$ (resp. $a \amalg b$)
- *kernels* and *cokernels*: Given a morphism $f : a \to b$, the kernel (resp. cokernel) of f is an object k and a morphism $\iota : k \to a$ such that k is the limit (resp. colimit) of the diagarm:


  $$\overset{a}{\bullet} \xrightarrow{f} \overset{b}{\bullet}$$

  with the added restriction that the map $\varphi : k \to y$ must be the zero morphism (namely, by commutativity, $f\iota = 0_{kb}$ must be the zero morphism). In terms of diagrams, we get that that

for any $\iota' : K \to A$ such that $f\pi\iota' = 0$, that there exists a morphism φ such that the following diagram commutes:



and simmilarly for cokernels:



Kernels and cokernels do not necessarily exist in a category, or not all morphisms have kernels (ex. the category of finitely generated R-modules for any ring R need has morphisms without kernels). Furthermore, monomorphism need not be kernels (not all subgroups are normal) and epimorphisms need not be cokernels (recall $\mathbb{Z} \to \mathbb{Q}$ is an epimorphism in **Ring**)

Not all categories we have worked with have these properties. For example, **Fld** does not have products (what would be the characteristic of the product of $\mathbb{F}_p$ and $\mathbb{F}_q$ for $p \neq q$?), some categories do not have zero morphisms (set being an example), some have monomorphisms/epimorphisms that do not correspond to kernels (as showed above). We first limit our attention to categories which have these nice properties:

Definition 55.1.1: Additive Category

Let **A** be a category. Then **A** is said to be *additive* if it has a zero-object, has both finite products and coproducts, and each $\mathrm{Hom}_A(X, Y)$ can be given an abelian group structure such that the composition of maps:

$$\mathrm{Hom}_A(X, Y) \times \mathrm{Hom}_A(Y, Z) \to \mathrm{Hom}_A(X, Z)$$

is bilinear. A functor between additive categories is *additive* if it is a group homomorphism on hom-sets.

A functor between two additive categories is called an *additive functor* if the maps between the hom-sets is a homomorphism.

The term "additive" comes froms the fact that we may interpret the additive category as a monoidal category (a category which we may add a functor $\otimes : C \times C \to C$ that is given the property of a monoid operation, for an additive category this would be the direct product), where the hom-sets are "enriched" to also be abelian groups. Another way of looking at additive categories is in which the algebra of matrices is well-defined.

Example 55.1.2: Additive Categories

1. The category of R-modules is an example of an additive category.

2. **Grp** is not additive, for $\mathrm{Hom}_{\mathbf{Grp}}(A, B)$ does not have an abelian group strucuture satisfying the above condition.
3. The category of matrices over a ring is an additive category.
4. The category of finitely generated R-modules is an additive category

A key realisation is that in the absence of kernels and cokernels as objects monomorphisms and epimorphisms take their place:

Lemma 55.1.3: Additive Categories: Monomorphisms and Kernels I

Let A be an additive category. Then kernels are monomorphisms and cokernels are epimorphisms

***Proof*:**
Let $k\colon K \to A$ be a kernel of $\varphi\colon A \to B$, and let $f, g\colon X \to K$ satisfy $k \circ f = k \circ g$. Because the hom-sets of an additive category are abelian groups and composition is bilinear, this says $k \circ (f - g) = 0$.

Now apply the universal property of the kernel to the zero morphism $0\colon X \to A$. It satisfies $\varphi \circ 0 = 0$, so there is a *unique* morphism $u\colon X \to K$ with $k \circ u = 0$. Both $f - g$ and the zero morphism $X \to K$ have this property, so uniqueness forces $f - g = 0$, that is $f = g$. Hence k is a monomorphism.

The statement for cokernels is the same argument in the opposite category: a cokernel of φ in A is a kernel of φ in A^{op}, an additive category, and a monomorphism there is an epimorphism in A, completing the proof.

Note that kernels and cokernels need not exist in an additive category, hence the converse of each accession need not be the case (in a vacuous way). If a morphism φ has a kernel then we may identify exactly what this kernel is:

Lemma 55.1.4: Additive Categories: Monomorphisms and Kernels II

Let A be an additive category and $\varphi : X \to Y$ a morphism. Then:

1. If φ has a kernel, then φ is a monomorphism if and only if $0 \to X$ is its kernel
2. If φ has a cokernel, then φ is an epimorphism if and only if $Y \to 0$ is its cokernel

***Proof*:**

1. Suppose first that the zero morphism $0 \to X$ is a kernel of φ, and let $f, g\colon Z \to X$ satisfy $\varphi \circ f = \varphi \circ g$. Then $\varphi \circ (f - g) = 0$, so $f - g$ factors through the kernel: there is $u\colon Z \to 0$ with $f - g = 0 \circ u = 0$. Hence $f = g$ and φ is a monomorphism.

   Conversely suppose φ is a monomorphism and let $k\colon K \to X$ be a kernel of φ. From

$\varphi \circ k = 0 = \varphi \circ 0$ and φ monic it follows that $k = 0$. But k is itself a monomorphism by lemma 55.1.3, and $k \circ \mathrm{id}_K = 0 = k \circ 0$, so $\mathrm{id}_K = 0$. An object whose identity is the zero morphism is a zero object, so $K \cong 0$ and the kernel is $0 \to X$.

2. This is the statement of (1) in the opposite category, where kernels and monomorphisms become cokernels and epimorphisms.

This completes the proof.

As mentioned, it is not guaranteed that kernels and cokernels exist. We shall shortly axiomatically add them to our category by adding them into the definition of a new category that supersedes additive categories, but first we show a few more important results about abelian categories. Namely, in an additive category, products and coproducts are equivalent:

Lemma 55.1.5: Additive Categories: Products and Coproducts

Let A be an additive category and $X, Y \in \mathrm{Obj}(A)$. Then if $X \times Y$ exists, so does $X \amalg Y$, and if $X \amalg Y$ exists, so does $X \times Y$. Furthermore,

$$X \times Y \cong X \amalg Y$$

***Proof*:**
Suppose $P = X \times Y$ exists, with projections $p_X \colon P \to X$ and $p_Y \colon P \to Y$. Let $i_X \colon X \to P$ be the unique morphism with $p_X i_X = \mathrm{id}_X$ and $p_Y i_X = 0$, and let $i_Y \colon Y \to P$ be defined symmetrically; both exist by the universal property of the product.

Step 1: The key identity $i_X p_X + i_Y p_Y = \mathrm{id}_P$. Two morphisms out of P into P agree as soon as their composites with p_X and with p_Y agree, again by the universal property of the product. Compute

$$p_X(i_X p_X + i_Y p_Y) = (p_X i_X)p_X + (p_X i_Y)p_Y = \mathrm{id}_X \circ p_X + 0 \circ p_Y = p_X$$

using bilinearity of composition, and symmetrically $p_Y(i_X p_X + i_Y p_Y) = p_Y$. Since id_P has the same two composites, the identity holds.

Step 2: (P, i_X, i_Y) is a coproduct. Let $f \colon X \to Z$ and $g \colon Y \to Z$ be given and set $h = f p_X + g p_Y \colon P \to Z$. Then

$$h i_X = f(p_X i_X) + g(p_Y i_X) = f, \qquad h i_Y = f(p_X i_Y) + g(p_Y i_Y) = g$$

so h is a morphism with the required restrictions. For uniqueness, suppose h' also satisfies $h' i_X = f$ and $h' i_Y = g$. Then by Step 1,

$$h' = h' \mathrm{id}_P = h'(i_X p_X + i_Y p_Y) = (h' i_X)p_X + (h' i_Y)p_Y = f p_X + g p_Y = h$$

Hence P with i_X, i_Y satisfies the universal property of $X \amalg Y$, and in particular $X \times Y \cong X \amalg Y$.

If instead $X \amalg Y$ is assumed to exist, the same argument in the opposite category produces the product, completing the proof.

Hence, additive categories behave very much like abelian groups, however as we pointed out kernels and cokernels need not exist. We thus define a new category that forces these conditions:

Definition 55.1.6: Abelian Category

[Abelian Category] Let A be an additive category. Then A is an *abelian* category if

1. kernels and cokernels exist in A;
2. every monomorphism is the kernel of some morphism, and every epimorphism is the cokernel of some morphism.

The second condition is not a consequence of the first, and it is the one that does the work. An additive category satisfying only (1) is called *pre-abelian*, and there the canonical map from the coimage to the image of a morphism (theorem 55.1.9) need not be an isomorphism; the category of torsion-free abelian groups is pre-abelian but not abelian, since $\mathbb{Z} \xrightarrow{2} \mathbb{Z}$ is there both a monomorphism and an epimorphism without being an isomorphism. Condition (2) rules this out, and is what makes lemma 55.1.8 true.

Note that lemma 55.1.4 is a weaker statement, not this one: it characterizes a monomorphism by having *zero* kernel, which says nothing about whether the monomorphism is itself a kernel.

Since each kernel is associated to a monomorphism, we may intuitively think of the association:

$$\text{kernel} \iff \text{submodule}$$

and similarly:

$$\text{cokernel} \iff \text{quotient module}$$

In many ways, an abelian category should be thought of as the minimum number of conditions necessary to define exact sequence[1]. To see this, we require the following:

Lemma 55.1.7: Abelian Category: Kernels And Cokernels

Let A be an abelian category. Then every kernel is the kernel of its cokernel, and every cokernel is the cokernel of its kernel.

***Proof*:**
Let $k\colon K \to A$ be a kernel, say of $\varphi\colon A \to B$, and let $c\colon A \to C$ be a cokernel of k. The claim is that k is a kernel of c.

First, $c \circ k = 0$ holds by the definition of a cokernel. Now let $t\colon T \to A$ satisfy $c \circ t = 0$; a unique factorization of t through k is needed. Since $\varphi \circ k = 0$ and c is the cokernel of k, the morphism φ factors as $\varphi = \bar{\varphi} \circ c$ for some $\bar{\varphi}\colon C \to B$. Therefore

$$\varphi \circ t = \bar{\varphi} \circ c \circ t = 0$$

and since k is the kernel of φ, there is a unique $u\colon T \to K$ with $k \circ u = t$. Uniqueness is automatic because k is a monomorphism by lemma 55.1.3. So k satisfies the universal property of $\ker c$.

[1]Those familiar with some algebraic topology may find it insightful that an abelian category is the the category with ninimum number of condition so that the snake lemma (theorem 56.1.20) holds

The dual statement, that every cokernel is the cokernel of its kernel, is this argument in the opposite category, completing the proof.

Lemma 55.1.8: Abelian Categories: Isomorphisms

[Abelian Categories, Isomorphisms] Let A be an abelian category and $\varphi : A \to B$ a morphism in A. Then if φ is a monomorphism and an epimorphism, it is an isomorphism

Note that this does not hold in additive categories, nor even in pre-abelian ones: condition (2) of definition 55.1.6 is exactly what the proof below uses.

***Proof*:**
Since φ is an epimorphism, condition (2) of definition 55.1.6 makes it the cokernel of some morphism $\psi\colon C \to A$. By the definition of a cokernel $\varphi \circ \psi = 0$, so ψ factors through $\ker\varphi$ by the universal property of the kernel.

Now φ is also a monomorphism, so $\ker\varphi = 0$ by lemma 55.1.4. The factorization of the previous paragraph then runs through the zero object, so $\psi = 0$ outright and φ is a cokernel of the zero morphism $0 \to A$. But the identity $\mathrm{id}_A\colon A \to A$ is also a cokernel of $0 \to A$: any $f\colon A \to X$ with $f \circ 0 = 0$, which is every f, factors uniquely through id_A. Cokernels are unique up to unique isomorphism, so there is an isomorphism $A \to B$ commuting with φ and id_A, which forces φ to be that isomorphism, as we sought to show.

Theorem 55.1.9: Abelian Category: Canonical Decomposition

[Abelian Category, Canonical Decomposition] Let A be an abelian category and $\varphi : A \to B$ a morphism. Write $C = \mathrm{coker}(\ker\varphi)$ and $K = \ker(\mathrm{coker}\varphi)$. Then φ decomposes in the following cannonical way:

$$A \twoheadrightarrow C \xrightarrow[\tilde{\varphi}]{} K \rightarrowtail B, \qquad A \xrightarrow{\varphi} B$$

where the first morphism is an epimorphism, the last a monomorphism, and the middle morphism $\tilde{\varphi}$ is an *isomorphism*.

***Proof*:**
Write $k\colon N \to A$ for $\ker\varphi$ and $p\colon A \to C$ for its cokernel, and $q\colon B \to Q$ for $\mathrm{coker}\varphi$ and $\iota\colon K \to B$ for its kernel. By lemma 55.1.3 the morphism p is an epimorphism and ι is a monomorphism.

Step 1: φ factors through ι. Since q is the cokernel of φ, $q \circ \varphi = 0$, and since ι is the kernel of q there is a unique $\varphi'\colon A \to K$ with $\varphi = \iota \circ \varphi'$.

Step 2: φ' factors through p. From $\iota \circ \varphi' \circ k = \varphi \circ k = 0$ and ι monic it follows that $\varphi' \circ k = 0$. As p is the cokernel of k, there is a unique $\tilde{\varphi}\colon C \to K$ with $\varphi' = \tilde{\varphi} \circ p$. Combining, $\varphi = \iota \circ \tilde{\varphi} \circ p$, which is the displayed factorization.

Step 3: ι is the smallest subobject through which φ factors. Let $m\colon V \to B$ be any monomorphism with $\varphi = m \circ \psi$ for some ψ. By condition (2) of definition 55.1.6 the monomorphism m is a kernel, so by lemma 55.1.7 it is the kernel of its own cokernel; write $d\colon B \to D$ for $\operatorname{coker} m$, so that $m = \ker d$. Then

$$d \circ \varphi = d \circ m \circ \psi = 0$$

so d factors through the cokernel of φ, say $d = \bar{d} \circ q$. Since $\iota = \ker q$ gives $q \circ \iota = 0$, it follows that $d \circ \iota = \bar{d} \circ q \circ \iota = 0$, and therefore ι factors through $\ker d = m$.

Step 4: φ' is an epimorphism. Let $c\colon K \to W$ be the cokernel of φ' and $n\colon V \to K$ its kernel. From $c \circ \varphi' = 0$ the morphism φ' factors as $\varphi' = n \circ \psi$, whence $\varphi = \iota \circ n \circ \psi$. The composite $\iota \circ n$ is a monomorphism, being a composite of two (each is a kernel, so lemma 55.1.3 applies), so Step 3 gives a t with $\iota = \iota \circ n \circ t$. As ι is monic this yields $n \circ t = \mathrm{id}_K$, so n is a split epimorphism as well as a monomorphism, hence an isomorphism by lemma 55.1.8. Then $c \circ n = 0$ with n invertible forces $c = 0$; but c is a cokernel, hence an epimorphism by lemma 55.1.3, and $\mathrm{id}_W \circ c = 0 = 0 \circ c$ then gives $\mathrm{id}_W = 0$, so $W \cong 0$. A morphism with zero cokernel is an epimorphism, so φ' is one.

Step 5: $\tilde{\varphi}$ is an isomorphism. By Step 4 the composite $\tilde{\varphi} \circ p = \varphi'$ is an epimorphism, and if $u \circ \tilde{\varphi} = 0$ then $u \circ \tilde{\varphi} \circ p = 0$ and hence $u = 0$; so $\tilde{\varphi}$ is an epimorphism. Dually, running Steps 1 to 4 in the opposite category shows that the induced morphism $C \to B$, which is $\iota \circ \tilde{\varphi}$, is a monomorphism; and a composite $g \circ h$ can be a monomorphism only if h is, so $\tilde{\varphi}$ is a monomorphism. Being both, it is an isomorphism by lemma 55.1.8, completing the proof.

From the above, we may think of $\ker(\operatorname{coker}) : K \to B$ as representing the "image" of φ:

Lemma 55.1.10: Abelian Category: Images

Let $\varphi : A \to B$ be a morphism in an abelian category, and let $\iota : K \to B$ be the kernel of the cokernel of φ. Then:

1. ι is a monomorphism
2. φ factors through ι
3. ι is initial with these properties

***Proof*:**
Part (1) is lemma 55.1.3, since ι is a kernel. Part (2) is Step 1 of the proof of theorem 55.1.9: writing $q = \operatorname{coker}\varphi$, the identity $q \circ \varphi = 0$ makes φ factor uniquely through $\iota = \ker q$.

Part (3) is the minimality established in Step 3 of that proof: if $m\colon V \to B$ is any monomorphism through which φ factors, then ι factors through m. Concretely, m is a kernel by condition (2) of definition 55.1.6, hence the kernel of its own cokernel d by lemma 55.1.7; then $d \circ \varphi = 0$ makes d factor through q, so $d \circ \iota = 0$ and ι factors through $\ker d = m$, as we sought to show.

Definition 55.1.11: Abelian Category: Image

Let $\varphi : A \to B$ be a morphism in an abelian category. Then the *iamge* of φ is $\ker(\text{coker}(\varphi))$ and is denoted $\text{im}(\varphi)$. Similarly, its co-image is $\text{coker}(\ker(\varphi))$ and is dentoed $\text{coim}(\varphi)$.

With our intuition from working with R-modules, given a morphism $\varphi : A \to B$ with image $\iota : K \to B$, we may imagine there is an induced epimorphism $\overline{\varphi} : A \to K$. This is indeed the case:

Proposition 55.1.12: Abelian Category: sub object and quotient objects

Let $\varphi : A \to B$ be a morphism in an abelian category with image $\text{im}\varphi\colon K \to B$ and coimage $\text{coim}\,\varphi\colon A \to C$. Then the induced morphism $A \to K$ is an epimorphism and the induced morphism $C \to B$ is a monomorphism.

***Proof*:**
The induced morphism $A \to K$ is the morphism φ' of theorem 55.1.9, shown to be an epimorphism in Step 4 of that proof. The induced morphism $C \to B$ is the composite $\iota \circ \tilde{\varphi}$, a composite of a monomorphism with an isomorphism, hence a monomorphism, completing the proof.

From the cannonical decomposition, we may say that the image and coimage are "isomorphic" (which is not strictly true since these are morphisms, however by the Freyd-Mitchell Theorem this is a safe way of looking at it).

Definition 55.1.13: Abelian Category: Exactness

Consider a sequence of objects in an abelian category

$$\cdots \to A \xrightarrow{\varphi} B \xrightarrow{\psi} C \to \cdots$$

This sequence is *exact at* B if:

1. $\psi \circ \varphi = 0$
2. $\text{coker}\varphi \circ \ker \psi = 0$

and it is *exact* if it is exact at each of its interior objects.

Example 55.1.14: Categorical Exactness

1. In R-Mod, $\ker \psi$ is the inclusion of $\{b \in B \mid \psi(b) = 0\}$ and $\text{coker}\varphi$ is the projection $B \to B/\text{im}\varphi$. So condition (2) says that every b with $\psi(b) = 0$ lies in $\text{im}\varphi$, condition (1) says $\text{im}\varphi \subseteq \ker \psi$, and together they are the usual condition $\text{im}\varphi = \ker \psi$.
2. The sequence $0 \to A \xrightarrow{\varphi} B \to 0$ is exact if and only if φ is an isomorphism. The cokernel of $0 \to A$ is id_A, so exactness at A says that $\ker \varphi$ is the zero morphism. A kernel is a monomorphism (lemma 55.1.3), so its object is then a zero object, which means that φ is a monomorphism (lemma 55.1.4). In the same way, the kernel of $B \to 0$ is id_B, so exactness at B says that the epimorphism $\text{coker}\varphi$ is zero, which means that φ is an epimorphism. A

morphism that is both is an isomorphism (lemma 55.1.8), and an isomorphism is both.

3. For objects A and B, let $P = A \times B$ with projections p_A, p_B, and let i_A, i_B be as in the proof of lemma 55.1.5, so that $p_A i_A = \mathrm{id}_A$, $p_B i_A = 0$, $p_B i_B = \mathrm{id}_B$ and $i_A p_A + i_B p_B = \mathrm{id}_P$. Then $0 \to A \xrightarrow{i_A} P \xrightarrow{p_B} B \to 0$ is exact. As in (2), exactness at A and at B means that i_A is a monomorphism and p_B an epimorphism, which hold because $p_A i_A = \mathrm{id}_A$ and $p_B i_B = \mathrm{id}_B$. At P, $p_B i_A = 0$, and every t with $p_B t = 0$ satisfies $t = (i_A p_A + i_B p_B)t = i_A(p_A t)$, the factorization being unique as i_A is monic. So i_A is a kernel of p_B, and $\mathrm{coker} i_A \circ \ker p_B = \mathrm{coker} i_A \circ i_A = 0$.

Freyd-Mitchell Theorem

As mentioned, R-mod is an abelian category, and as we shall develop a bit later it the categories R-mod "represent" all abelian categories.

Theorem 55.1.15: Freyd-Mitchell Theorem

Let A be a small abelian category. Then there is a fully faithful exact functor $A \to R\text{-Mod}$ for a suitable ring R. Such a functor reflects exactness: a sequence in A is exact if and only if its image in R-Mod is.

***Proof Key ideas*:**
The proof constructs R as the endomorphism ring of a suitable injective cogenerator in the category of left exact functors $A^{\mathrm{op}} \to \mathbf{Ab}$, and occupies a chapter's worth of category theory that this book does not otherwise need; it is given in full in *An Introduction to Homological Algebra* [101], §1.6. The idea is that A embeds into its category of left exact presheaves by Yoneda, that this larger category is a Grothendieck category with enough injectives, and that a single injective cogenerator there converts the whole category into modules over its endomorphism ring.

The clause about reflecting exactness is immediate from the rest and is what the theorem is used for: a fully faithful exact functor reflects kernels and cokernels, so a diagram chase valid in R-Mod transfers back to A. This is what permits the element-based arguments in lemma 56.1.22 and throughout chapter 60.

55.2 Localization of Categories

The constructions of this book repeatedly produce morphisms that ought to be invertible but are not. The model for what to do about it is already familiar from commutative algebra: a ring R and a multiplicative set S of elements one wishes to invert are replaced by $S^{-1}R$, together with a map $R \to S^{-1}R$ that is universal among ring maps sending S into the units. Nothing in that description mentions elements of a ring rather than morphisms of a category, and the same universal property can be imposed one level up.

The payoff comes in chapter 56, where the class to be inverted is the class of quasi-isomorphisms and

the resulting category is the derived category. The construction is recorded here, before it is needed, because it is a statement about categories and not about complexes.

Definition 55.2.1: Localization of a Category

Let $\mathcal{C}$ be a category and W a class of morphisms of $\mathcal{C}$. A *localization* of $\mathcal{C}$ at W is a category $\mathcal{C}[W^{-1}]$ together with a functor $Q\colon \mathcal{C} \to \mathcal{C}[W^{-1}]$ such that

1. $Q(w)$ is an isomorphism for every $w \in W$;
2. for every category $\mathcal{D}$ and every functor $F\colon \mathcal{C} \to \mathcal{D}$ carrying each element of W to an isomorphism, there is a functor $\overline{F}\colon \mathcal{C}[W^{-1}] \to \mathcal{D}$ with $\overline{F} \circ Q = F$, and $\overline{F}$ is unique with this property.

As with every universal property, the definition determines the answer up to canonical isomorphism as soon as an answer exists: two localizations receive unique comparison functors from one another whose composites must be the identity, by the uniqueness clause applied to Q itself. Existence is the substantive point, and it is settled by a construction that simply writes down the morphisms that formal inversion forces to exist.

Theorem 55.2.2: Existence of the Localization

Let $\mathcal{C}$ be a category and W a class of morphisms. Then a localization $Q\colon \mathcal{C} \to \mathcal{C}[W^{-1}]$ exists.

***Proof*:**

Step 1: The construction. Let $\mathcal{C}[W^{-1}]$ have the same objects as $\mathcal{C}$. For objects X and Y, consider finite *zigzags* from X to Y: alternating strings of morphisms of $\mathcal{C}$

$$X = X_0 \;\; \text{⊢} X_1 \;\; \text{⊢} \;\; \cdots \;\; \text{⊢} X_n = Y$$

in which each link $X_i \text{⊢} X_{i+1}$ is either a morphism $X_i \to X_{i+1}$ of $\mathcal{C}$, called a forward link, or a morphism $X_{i+1} \to X_i$ that belongs to W, called a backward link. Enlarging W to contain all identities and to be closed under composition changes neither the class of functors inverting it nor, therefore, the localization, so assume this without loss of generality; it is what makes the second move below well formed. Impose on the collection of zigzags the smallest equivalence relation generated by: replacing two consecutive forward links by their composite; replacing two consecutive backward links by their composite; deleting a forward or backward link that is an identity; and deleting a pair of adjacent links w forward followed by w backward, or w backward followed by w forward, for $w \in W$. Let $\mathrm{Hom}_{\mathcal{C}[W^{-1}]}(X, Y)$ be the collection of equivalence classes, with composition given by concatenation, which is well defined because the generating relations are local to the links they touch. Concatenation is associative and the empty zigzag is an identity, so this is a category. Let Q send an object to itself and a morphism to the one-link forward zigzag.

Step 2: Q inverts W. For $w \in W$ the backward one-link zigzag on w is a morphism in the opposite direction, and concatenating it with the forward one-link zigzag on w in either order produces a pair of adjacent links which the last generating relation deletes, leaving the empty zigzag. So $Q(w)$ is an isomorphism.

Step 3: The universal property. Let $F\colon \mathcal{C} \to \mathcal{D}$ carry W into isomorphisms. Define $\overline{F}$ to be F on objects, and on a zigzag to be the composite in $\mathcal{D}$ obtained by applying F to each forward link and $F(-)^{-1}$ to each backward link. Each generating relation is respected: composites go to composites by functoriality, identities to identities, and an adjacent pair w, w of opposite orientation goes to $F(w)F(w)^{-1}$ or $F(w)^{-1}F(w)$, both identities. So $\overline{F}$ is well defined on equivalence classes, and it is a functor because concatenation goes to composition. By construction $\overline{F} \circ Q = F$.

For uniqueness, suppose $G \circ Q = F$ for a functor G. Every morphism of $\mathcal{C}[W^{-1}]$ is a concatenation of one-link zigzags, each of which is $Q(f)$ or $Q(w)^{-1}$; a functor is determined by its values on these, and $G(Q(f)) = F(f)$ forces $G(Q(w)^{-1}) = G(Q(w))^{-1} = F(w)^{-1}$. So G agrees with $\overline{F}$ on every morphism, completing the proof.

55.2.3 Warning: Localization and Set Theory The construction above builds each $\mathrm{Hom}_{\mathcal{C}[W^{-1}]}(X, Y)$ out of *all* zigzags, and for a category $\mathcal{C}$ that is not small there is no guarantee that the result is a set rather than a proper class. The property at risk is *local smallness*: the localization of a locally small category need not be locally small.

Two remedies are standard. The first is to assume $\mathcal{C}$ small, which excludes the category of modules over a ring and every category of complexes of modules. The second is to exhibit a calculus of fractions as in theorem 55.2.5, which replaces arbitrary zigzags by roofs. This alone does not bound anything, since the roofs over a fixed object are indexed by a proper class. What is needed in addition is that the W-morphisms into each object admit a *set* that is cofinal among them, and a multiplicative system with that property is what makes the localization locally small.

The zigzag description settles existence and is useless for computation: a morphism is an equivalence class of arbitrarily long strings, and deciding when two strings agree is not something one does by hand. Under a mild hypothesis on W every zigzag collapses to a single roof, and then morphisms become genuinely manipulable.

Definition 55.2.4: Multiplicative System

A class W of morphisms in a category $\mathcal{C}$ is a *multiplicative system* if


1. W contains every identity and is closed under composition;
2. (Ore condition) for every $f\colon Z \to B$ in $\mathcal{C}$ and every $t\colon V \to B$ in W there are $t'\colon Z' \to Z$ in W and $f'\colon Z' \to V$ in $\mathcal{C}$ with $f \circ t' = t \circ f'$;
3. for every pair $f, g\colon X \to Y$ and every $s\colon Y \to Y'$ in W with $s \circ f = s \circ g$, there is $t\colon X' \to X$ in W with $f \circ t = g \circ t$.

Condition (2) is what lets two roofs be composed, and condition (3) is what makes the resulting notion of equality between roofs transitive. Both are visible in the ring case: for a commutative ring every S is a multiplicative system, and the conditions are the familiar manipulations that put two fractions over a common denominator.

Theorem 55.2.5: Calculus of Fractions

Let W be a multiplicative system in $\mathcal{C}$. Then:

1. every morphism $A \to B$ in $\mathcal{C}[W^{-1}]$ is represented by a *roof*



   with $s \in W$, standing for $Q(f) \circ Q(s)^{-1}$;

2. if two roofs (s, f) and (s', f') are *commonly dominated*, meaning there are $u\colon Z'' \to Z$ and $u'\colon Z'' \to Z'$ with $su = s'u' \in W$ and $fu = f'u'$, then they represent the same morphism;

3. conversely, two roofs representing the same morphism are commonly dominated, so that roofs modulo common domination compute $\mathrm{Hom}_{\mathcal{C}[W^{-1}]}(A, B)$.

***Proof*:**

Step 1: Roofs compose. Given roofs $A \xleftarrow{s} Z \xrightarrow{f} B$ and $B \xleftarrow{t} V \xrightarrow{g} C$, apply the Ore condition to $f\colon Z \to B$ and $t \in W$ to obtain $t'\colon Z' \to Z$ in W and $f'\colon Z' \to V$ with $ft' = tf'$. Then $A \xleftarrow{st'} Z' \xrightarrow{gf'} C$ is a roof, since $st' \in W$ by closure under composition, and in $\mathcal{C}[W^{-1}]$ it represents

$$Q(g)Q(f')Q(t')^{-1}Q(s)^{-1} = Q(g)Q(t)^{-1}Q(f)Q(s)^{-1}$$

the identity following by rearranging $Q(f)Q(t') = Q(t)Q(f')$, both $Q(t)$ and $Q(t')$ being invertible. This is the composite of the two given morphisms.

Step 2: Part (2). Suppose (s, f) and (s', f') are commonly dominated by u, u'. Since $su = s'u'$ lies in W and $Q(s)$ is invertible, $Q(u)$ is invertible too, and then

$$Q(f)Q(s)^{-1} = Q(fu)Q(su)^{-1} = Q(f'u')Q(s'u')^{-1} = Q(f')Q(s')^{-1}$$

so the two roofs represent the same morphism.

Step 3: Common domination is an equivalence relation. Reflexivity and symmetry are immediate. For transitivity, suppose Z_1 dominates (s, f) and (s', f') through u_1, v_1 with $\sigma_1 := su_1 = s'v_1 \in W$, and Z_2 dominates (s', f') and (s'', f'') through u_2, v_2 with $\sigma_2 := s'u_2 = s''v_2 \in W$. Apply the Ore condition to $\sigma_1\colon Z_1 \to A$ and $\sigma_2 \in W$ to get $t'\colon Z_3 \to Z_1$ in W and $w\colon Z_3 \to Z_2$ with $\sigma_1 t' = \sigma_2 w$. Then

$$s'(v_1 t') = \sigma_1 t' = \sigma_2 w = s'(u_2 w)$$

so condition (3) of definition 55.2.4, applied to the parallel pair $v_1t', u_2w\colon Z_3 \rightrightarrows Z'$ and to $s' \in W$, yields $t\colon Z_4 \to Z_3$ in W with $v_1t't = u_2wt$. The roof with middle leg $\sigma_1 t't \in W$ and legs $u_1t't$ and v_2wt then dominates both (s, f) and (s'', f''): the middle leg lies in W by closure, and the two outer compatibilities follow because $fu_1 = f'v_1$ and $f''v_2 = f'u_2$ both factor through f'.

Step 4: Part (1). Every morphism of $\mathcal{C}[W^{-1}]$ is a zigzag, and it suffices to show every zigzag is equivalent to one of the form backward-then-forward. Assign to a zigzag the number of pairs $i < j$ with link i forward and link j backward. Composing two adjacent links of the same orientation strictly decreases the length and does not increase this number; and given an adjacent pair $Z \xrightarrow{f} B \xleftarrow{t} V$ with $t \in W$, the Ore condition gives $Z \xleftarrow{t'} Z' \xrightarrow{f'} V$ with $t' \in W$ and $ft' = tf'$, which represents the same morphism because $Q(t)^{-1}Q(f) = Q(f')Q(t')^{-1}$, and which strictly decreases the count. The count cannot decrease forever, so the process terminates at a zigzag with no forward link preceding a backward one; composing along each run leaves a single roof.

Step 5: Part (3). What remains is the converse of Step 2. The standard route builds the category whose morphisms are roofs modulo common domination, with composition as in Step 1, and checks that this is well defined on classes, associative and unital, and that it satisfies the universal property of definition 55.2.1; comparing with $\mathcal{C}[W^{-1}]$ through that universal property then forces the two to agree, which is exactly the converse. Those verifications are bookkeeping of the same kind as Steps 1 and 3, carrying no further idea, and they are carried out in full in *An Introduction to Homological Algebra* [101]. This completes the proof.

55.2.1 Serre Subcategories and the Quotient

Localizing a category at a class of morphisms is one way to force objects to become isomorphic. There is a second, available when the ambient category is abelian: kill a class of *objects* and keep track of what survives. The result is again abelian, which is what makes it useful, and it is the construction under the localization sequence in K-theory.

Definition 55.2.6: Serre Subcategory

Let $\mathcal{A}$ be an abelian category. A non-empty full subcategory $\mathcal{B} \subseteq \mathcal{A}$ is a *Serre subcategory* if it is closed under subobjects, quotient objects, and extensions: for every short exact sequence

$$0 \to A' \to A \to A'' \to 0$$

in $\mathcal{A}$, the object A lies in $\mathcal{B}$ if and only if both A' and A'' do.

The single biconditional packages all three closure conditions. It is strictly stronger than a two-out-of-three rule: from $A \in \mathcal{B}$ alone it concludes that *both* A' and A'' lie in $\mathcal{B}$, and that direction, which is what gives closure under subobjects and quotients, is the one the proof below leans on most.

Example 55.2.7: Torsion Modules

Let R be a commutative domain. The torsion modules form a Serre subcategory of R-**Mod**: a submodule of a torsion module is torsion, a quotient of one is torsion, and if A' and A'' are torsion in $0 \to A' \to A \to A'' \to 0$ then every $a \in A$ has $ra \in A'$ for some $r \neq 0$ and then $sra = 0$ for some $s \neq 0$, so A is torsion.

By contrast the free R-modules are *not* a Serre subcategory: they are closed under neither quotients (over $R = \mathbb{Z}$, $\mathbb{Z} \twoheadrightarrow \mathbb{Z}/2$) nor subobjects in general.

Theorem 55.2.8: The Quotient Abelian Category

Let $\mathcal{A}$ be a small abelian category and $\mathcal{B} \subseteq \mathcal{A}$ a Serre subcategory. Then there is an abelian category $\mathcal{A}/\mathcal{B}$ and an exact functor $\pi\colon \mathcal{A} \to \mathcal{A}/\mathcal{B}$ with the following properties.

1. $\pi(B) = 0$ for every $B \in \mathcal{B}$, and an object A of $\mathcal{A}$ has $\pi(A) = 0$ if and only if $A \in \mathcal{B}$.
2. π is universal: any exact functor $F\colon \mathcal{A} \to \mathcal{D}$ into an abelian category with $F(B) = 0$ for all $B \in \mathcal{B}$ factors as $F = \bar{F} \circ \pi$ for an exact $\bar{F}\colon \mathcal{A}/\mathcal{B} \to \mathcal{D}$, unique up to natural isomorphism.

The category $\mathcal{A}/\mathcal{B}$ is the *Gabriel quotient* of $\mathcal{A}$ by $\mathcal{B}$.

***Proof*:**
The construction is a localization in the sense of definition 55.2.1, taken at the class

$$W = \{\, f \in \mathcal{A} \;:\; \ker f \in \mathcal{B} \text{ and } \operatorname{coker} f \in \mathcal{B} \,\}$$

of morphisms whose kernel and cokernel are both killed, and $\mathcal{A}/\mathcal{B} := \mathcal{A}[W^{-1}]$ with π the canonical functor. Existence is theorem 55.2.2, which needs no hypothesis on W; smallness of $\mathcal{A}$ is what keeps the result locally small, by box 55.2.3.

That W is a multiplicative system is where the Serre condition is consumed, and each clause of definition 55.2.4 uses it differently, so all three are worth doing.

Identities and composition. Every identity has zero kernel and cokernel, and $0 \in \mathcal{B}$ since $\mathcal{B}$ is non-empty and closed under subobjects. For composition, take $f\colon A \to A'$ and $g\colon A' \to A''$ in W. Two elementary exact fragments suffice, and neither needs the full six-term Ker-Coker sequence, which this book does not have at this point. First, $\ker f \subseteq \ker(gf)$ and f carries $\ker(gf)$ into $\ker g$, giving

$$0 \to \ker f \to \ker(gf) \to \ker g$$

so $\ker(gf)$ is an extension of a subobject of $\ker g$ by $\ker f$. Dually,

$$\operatorname{coker} f \to \operatorname{coker}(gf) \to \operatorname{coker} g \to 0$$

exhibits $\operatorname{coker}(gf)$ as an extension of $\operatorname{coker} g$ by a quotient of $\operatorname{coker} f$. Closure under subobjects, quotients and extensions puts both in $\mathcal{B}$, so $gf \in W$.

The Ore condition. Given $t\colon B \to B'$ in W and $f\colon Z \to B'$, form the pullback of t along f. Its projection $t'\colon B \times_{B'} Z \to Z$ has $\ker t' \cong \ker t$ and $\operatorname{coker} t' \hookrightarrow \operatorname{coker} t$. The first is formal; the second holds because $\operatorname{im} t' = f^{-1}(\operatorname{im} t)$, so $Z/f^{-1}(\operatorname{im} t) \hookrightarrow B'/\operatorname{im} t$, an element argument legitimate here because $\mathcal{A}$ is small and theorem 55.1.15 embeds it exactly-and-fully faithfully in a module category. Hence $\ker t' \in \mathcal{B}$ and, by closure under *subobjects*, $\operatorname{coker} t' \in \mathcal{B}$, so $t' \in W$.

The cancellation condition. Suppose $sf = sg$ for $f, g\colon A \to B$ and $s \in W$. Here it is the additive structure of $\mathcal{A}$ that does the work, and no pullback helps. Set $h = f - g$, so $sh = 0$ and hence $\operatorname{im} h \subseteq \ker s$. Since $\ker s \in \mathcal{B}$, closure under subobjects gives $\operatorname{im} h \in \mathcal{B}$. Let $t\colon K \rightarrowtail A$ be the kernel of $A \twoheadrightarrow \operatorname{im} h$. Then $\ker t = 0$ and $\operatorname{coker} t \cong \operatorname{im} h \in \mathcal{B}$, so $t \in W$, and $ht = 0$ gives $ft = gt$.

For (1), $\pi(B) = 0$ because $B \to 0$ lies in W when $B \in \mathcal{B}$. The converse needs an argument, and it is worth giving the right one, since the tempting route is circular: from $\pi(A) = 0$ one would like to say $A \to 0$ is inverted, hence lies in W, hence has kernel A in $\mathcal{B}$. But "inverted $\Rightarrow$ in

> W" is the statement that W is *saturated*, and definition 55.2.1 gives only the inclusion, not the converse.
>
> Argue from clause (3) of theorem 55.2.5 instead. If $\pi(A) = 0$ then $\mathrm{id}_{\pi(A)} = 0$, so the roofs $(\mathrm{id}_A, \mathrm{id}_A)$ and $(\mathrm{id}_A, 0)$ from A to A represent the same morphism, and clause (3) makes them commonly dominated: there is $t\colon Z \to A$ with $t \in W$ and $\mathrm{id}_A \circ t = 0 \circ t$, that is $t = 0$. A zero map has $\mathrm{coker} t = A$, and $t \in W$ puts that cokernel in $\mathcal{B}$. Hence $A \in \mathcal{B}$. Exactness of π and the abelian structure on $\mathcal{A}/\mathcal{B}$ are transported along the calculus of fractions, kernels and cokernels being computed by representative fractions. Clause (2) is clause (2) of definition 55.2.1 together with the observation that an exact F killing $\mathcal{B}$ inverts every element of W: exactness gives $\ker F(f) = F(\ker f) = 0$ and $\mathrm{coker} F(f) = F(\mathrm{coker} f) = 0$, and a map both monic and epic in an abelian category is an isomorphism. That produces a functor $\bar{F}$ with $\bar{F}\pi = F$. That $\bar{F}$ is moreover *exact* then follows in two lines, granting that kernels and cokernels in $\mathcal{A}/\mathcal{B}$ are computed as π-images of those in $\mathcal{A}$: every morphism of $\mathcal{A}/\mathcal{B}$ is $\pi(f)$ composed with an isomorphism, so it is enough to check on π-images, where $\bar{F}(\ker \pi f) = \bar{F}\pi(\ker f) = F(\ker f) = \ker F(f)$. That the transported kernels and cokernels are indeed computed this way is part of the verification recorded as omitted below.
>
> What is omitted is the routine verification that the transported kernels and cokernels satisfy the abelian axioms, which is a diagram chase on representative fractions with no new idea in it. The construction is Gabriel's, as we sought to show.

The quotient is the categorical analogue of localizing a ring: for R commutative and $S \subseteq R$ multiplicative, $S^{-1}R$**-mod** is the quotient of R**-mod** by the S-torsion modules. That example is the one to keep in mind, and it is the case that appears in the localization sequence of algebraic K-theory.

56

Complexes and (co)Homology

Let **A** be a fixed abelian category, which by theorem 55.1.15 may without loss of generality it can be considered ${}_R\text{Mod}$. In this chapter, we shall focus on studying (co)chains of such modules, that is sequence of modules that respect equation (54.1):

$$\text{im}(d^n) \subseteq \ker(d^{n+1})$$

The collection of all chains shall be denoted $\text{Ch}(\mathbf{A})$. We shall see that $\text{Ch}(\mathbf{A})$ is an abelian category, the notion of extensions (and snakes lemma) is well defined, which will be explored. In the right categories, it is relatively easy to construct a concrete complex given the category has enough objects, for example $M \in \text{Obj}(R\text{-}\mathbf{Mod})$ always has a complex known as a *free resolution* (see definition 12.3.27). There will be many different ways of creating complexes given an object, giving us different types of resolutions. We shall see that when a category has enough projective objects (resp. Injective objects), then "up to homotopy equivalence", projective resolutions shall be *initial* (resp. final) in the category of complexes $\text{Ch}(A)$. Thus, we shall take the time to develop the homology theory in categories with enough projective or injective objects. We shall see that under appropriate circumstances, taking (co)homology of a projective resolution of an object can give us some important information about said object.

Homology and cohomology are duals of each other, which means on the theoretical level they are the same. As cohomology is the more computationally useful tool, we shall be focusing on cohomology on this chapter, with the idea that the reader shall be comfortable being able to switch indices when necessary. Taking the cohomology of a complex shall be shown to be an additive functorial process, meaning for a given morphism of complexes $\alpha^\bullet : A^\bullet \to B^\bullet$, we shall get a morphism each cohomology $H^i(\alpha) : H^i(A^\bullet) \to H^i(B^\bullet)$ which will be shown can be to form a new complex $H^\bullet(\alpha) : H^\bullet(A^\bullet) \to H^\bullet(B^\bullet)$.

The goal of this chapter is to show how to extract information given a complexes (co)homology. Given this, it is important to know what information a morphism of complexes preserves in cohomology, that is given a morphism of complexes, $\alpha^\bullet : A^\bullet \to B^\bullet$, when is $H^\bullet(\alpha) : H^\bullet(A^\bullet) \to H^\bullet(B^\bullet)$ an

isomorphism? This shall lead us to the notion of *quasi-isomorphisms*, and their "representation" through mapping cones. As it turns out, quasi-isomorphisms do not behave nicely in general. What we shall then seek out is a stricter concept known as a *homotopy equivalence* that will still be a quasi-isomorphism, but will be invertible in the appropriate category.

56.1 Basic Definition and Properties

Starting with defining the generalization of an exact sequence:

Definition 56.1.1: Chain Complex

A *chain complex* $(C_\bullet, d_\bullet)$ is a sequence of objects and morphisms:

$$\cdots \xleftarrow{d_i} M_i \xleftarrow{d_{i+1}} M_{i+1} \xleftarrow{d_{i+2}} \cdots$$

with the indices running through $\mathbb{Z}$, such that

$$d_i \circ d_{i+1} = 0$$

and each d_i is called a *boundary map*. Similarly, a *cochain complex* $(C^\bullet, d^\bullet)$ is a sequence of objects

$$\cdots \xrightarrow{d^{i-1}} M^i \xrightarrow{d^i} M^{i+1} \xrightarrow{d^{i+1}} \cdots$$

with the indices running through $\mathbb{Z}$, such that

$$d^i \circ d^{i-1} = 0$$

where $d^\bullet$ is called the *differential*[a].

[a] Due to it's origin's in differential geometry and algebraic topology

Chains and cochains can be interchanged by taking

$$M_i = M^{-i}$$

Working with one or the other makes essentially no difference for homological algebra. In certain cases, some structures present themselves more in the cohomological case (ex. a natural ring structure called the *cohomology ring* shall become important to us), and so we opt to work with the cohomology, even though at this stage this can be considered to be an arbitrary choice. The condition that $d^i \circ d^{i-1} = 0$ is the same as $\mathrm{im} d^{i-1} \subseteq \ker d^i$. If the complex is exact, then $\mathrm{im} d^{i-1} = \ker d^i$ for all i. We also often write $C^\bullet$ instead of $(C^\bullet, d^\bullet)$ if the mappings $d^\bullet$ are clear from context or implied. In some textbooks, even the bullet is dropped and M represents the complex. Sometime, for homology, the notation $\partial_\bullet$ shall be used instead of $d_\bullet$ due to it's connection to being the boundary map for topological spaces when creating complexes out of topological spaces[1].The condition that $d^i \circ d^{i-1} = 0$ (resp. $d_i \circ d_{i+1} = 0$) is often abbreviated to $d \circ d = 0$.

Due to historical origins in algebraic topology, the kernel and image of the differential

[1] Similarly, $d^\bullet$ stands for the *differential* due to it's link to the derivative, which would be explored in a class in algebraic topology, or see EYNTKA Algebraic Topology

Definition 56.1.2: Cycles and Boundaries

Let $C_\bullet$ (resp. $C^\bullet$) be a chain complex (resp. cochain complex). Then:

1. $\ker(d_n)$ is called the *n-cycles* of $C_\bullet$ and $\operatorname{im}(d_{n+1})$ is called the n-boundary of $C_\bullet$. The n-cycle is represented as $Z_n = Z_n(C_\bullet)$ and the *n-boundary* is represented as $B_n = B_n(C_\bullet)$
2. $\ker(d^n)$ is called the *n-cocycles* of $C^\bullet$ and $\operatorname{im}(d^{n-1})$ is called the *n-coboundary* of $C^\bullet$. The n-cocycle is represented as $Z^n = Z^n(C^\bullet)$ and the n-coboundary is represented as $B^n = B^n(C^\bullet)$

The name cycles and boundaries has its origin in algebraic topology:

Example 56.1.3: Cycles and Boundaries

Let T be the boundary of a triangle, with vertices v_0, v_1, v_2 and oriented edges $e_{01} = [v_0, v_1]$, $e_{12} = [v_1, v_2]$ and $e_{20} = [v_2, v_0]$. Its simplicial chain complex has $C_1 = \mathbb{Z}e_{01} \oplus \mathbb{Z}e_{12} \oplus \mathbb{Z}e_{20}$, $C_0 = \mathbb{Z}v_0 \oplus \mathbb{Z}v_1 \oplus \mathbb{Z}v_2$ and $C_n = 0$ otherwise, with $d_1[v_i, v_j] = v_j - v_i$. Since $d_1(ae_{01} + be_{12} + ce_{20}) = (c-a)v_0 + (a-b)v_1 + (b-c)v_2$, the 1-cycles are the multiples of $z = e_{01} + e_{12} + e_{20}$, the chain that runs once around the triangle. As $C_2 = 0$, the only 1-boundary is 0, so z is a cycle that is not a boundary, and $Z_1/B_1 \cong \mathbb{Z}$ detects the hole enclosed by T.

The collection of all complexes forms a Category:

Definition 56.1.4: Category Of Complexes

Let $\mathbf{A}$ be an abelian category. Then $\mathrm{Ch}^\bullet(\mathbf{A})$ is a new category called the *category of complexes of A* where

1. $\mathrm{Obj}(\mathrm{Ch}^\bullet(\mathbf{A})) = \{\text{cochain complexes in } \mathbf{A}\}$
2. For two complexes $C^\bullet$ and $N^\bullet$, a morphism $\alpha^\bullet \in \mathrm{Hom}_{\mathrm{Ch}(\mathbf{A})}(C^\bullet, N^\bullet)$ consists of morphisms such that the following diagram commute:

$$\begin{array}{ccccccccc}
\cdots & \longrightarrow & M^{i-1} & \xrightarrow{d^{i-1}_{C^\bullet}} & M^i & \xrightarrow{d^i_{C^\bullet}} & M^{i+1} & \longrightarrow & \cdots \\
 & & \downarrow{\scriptstyle \alpha^{i-1}} & & \downarrow{\scriptstyle \alpha^{i-1}} & & \downarrow{\scriptstyle \alpha^{i-1}} & & \\
\cdots & \longrightarrow & N^{i-1} & \xrightarrow{d^{i-1}_{N^\bullet}} & N^i & \xrightarrow{d^i_{N^\bullet}} & N^{i+1} & \longrightarrow & \cdots
\end{array}$$

Similarly for $\mathrm{Ch}_\bullet(\mathbf{A})$ with chain complexes.

If unambiguous, the bullet is dropped giving $\mathrm{Ch}(\mathbf{A})$. It should be checked that $\mathrm{Ch}(A)$ is indeed a category. There are many variations of $\mathrm{Ch}(A)$ which will be important:

1. $C^+(A)$ is the full subcategory of $\mathrm{Ch}(A)$ of complexes which are bounded from bellow, so that $L^i = 0$ for $i \ll 0$
2. $C^-(A)$ is the full subcategory of $\mathrm{Ch}(A)$ of complexes which are bounded from above, so that $L^i = 0$ for $i \gg 0$
3. $C^{\geq 0}(A)$ (resp. $C^{\leq 0}$) for which $L^i = 0$ for $i \leq 0$ (resp. $i \geq 0$)

4. P, I are full subcategories of A consisting of projective and injective objects in A respectively, and hence we have $\mathrm{Ch}(P)$, $\mathrm{Ch}(I)$, and all its variants

There are also a few simple functors we may immediately define:

1. Take $\iota_r : \mathbf{A} \to \mathrm{Ch}(\mathbf{A})$ that sends an object A form $\mathbf{A}$ to a complex that is zero every and A in the rth degree. We shall commonly identify A with the complex given by ι_0.
2. Take $s_r : \mathrm{Ch}(\mathbf{A}) \to \mathrm{Ch}(\mathbf{A})$ which shifts over the complex, namely
$$C^\bullet \mapsto M[r]^\bullet$$
where $M[r]^i = M^{i+r}$ and $d^i_{M[r]^\bullet} = (-1)^r d^{i+r}_{C^\bullet}$ (the $(-1)^r$ shall be explained shortly).
3. the canonical truncations $\tau^{\leq n}$ and $\tau^{\geq n}$, defined in definition 56.1.12 once cohomology is available.

More importantly, $\mathrm{Ch}(A)$ is an abelian category, allowing the notion of exactness between complexes to be well-defined:

Lemma 56.1.5: Complex Category Is Abelian

Let A be an abelian category and $\mathrm{Ch}(A)$ the category of complexes of A. Then $\mathrm{Ch}(A)$ is an abelian category, in which kernels and cokernels are computed degreewise. In particular, a sequence of complexes is exact if and only if it is exact in each degree.

***Proof*:**
Write $d^n_C \colon C^n \to C^{n+1}$ for the differentials of a complex $C^\bullet$. Every condition below is checked in each degree n.

Step 1: $\mathrm{Ch}(A)$ *is additive (definition 55.1.1).* For chain maps $\alpha, \beta \colon C^\bullet \to D^\bullet$ put $(\alpha+\beta)^n = \alpha^n + \beta^n$. By bilinearity of composition in A,
$$d^n_D(\alpha^n + \beta^n) = \alpha^{n+1} d^n_C + \beta^{n+1} d^n_C = (\alpha^{n+1} + \beta^{n+1}) d^n_C$$
so $\alpha+\beta$ is a chain map, and the same computation shows that $-\alpha$ and the zero family are chain maps. The group axioms hold in each degree, so $\mathrm{Hom}_{\mathrm{Ch}(A)}(C^\bullet, D^\bullet)$ is an abelian group, and composition, which is computed degreewise, is bilinear because composition in A is. The complex $0^\bullet$ with a zero object in every degree is a zero object of $\mathrm{Ch}(A)$, since the unique morphisms $0 \to C^n$ and $C^n \to 0$ commute with all differentials (every composite through 0 is zero).

For complexes $C^\bullet$ and $D^\bullet$, let $P^n = C^n \times D^n$ with projections p_C, p_D, and let i_C, i_D be the morphisms into P^n with $p_C i_C = \mathrm{id}$, $p_D i_C = 0$, $p_C i_D = 0$ and $p_D i_D = \mathrm{id}$ (the degree is dropped from this notation). Then $i_C p_C + i_D p_D = \mathrm{id}_{P^n}$, since both sides have the same composites with p_C and with p_D. Put $d^n_P = i_C d^n_C p_C + i_D d^n_D p_D$. These identities give
$$d^{n+1}_P d^n_P = i_C d^{n+1}_C d^n_C p_C + i_D d^{n+1}_D d^n_D p_D = 0 \qquad p_C d^n_P = d^n_C p_C \qquad d^n_P i_C = i_C d^n_C$$
and the same identities with D in place of C, so $P^\bullet$ is a complex and p_C, p_D, i_C, i_D are chain maps satisfying the same identities in $\mathrm{Ch}(A)$. If $\alpha \colon T^\bullet \to C^\bullet$ and $\beta \colon T^\bullet \to D^\bullet$ are chain

maps, then $\gamma = i_C\alpha + i_D\beta$ is a chain map with $p_C\gamma = \alpha$ and $p_D\gamma = \beta$, and any γ' with these two properties equals $(i_Cp_C + i_Dp_D)\gamma' = i_C\alpha + i_D\beta$. So $P^\bullet$ is a product of $C^\bullet$ and $D^\bullet$. If $\alpha\colon C^\bullet \to T^\bullet$ and $\beta\colon D^\bullet \to T^\bullet$ are chain maps, then $h = \alpha p_C + \beta p_D$ satisfies $hi_C = \alpha$ and $hi_D = \beta$, and any h' with these two properties equals $h'(i_Cp_C + i_Dp_D) = \alpha p_C + \beta p_D$. So $P^\bullet$ is also a coproduct. Iterating gives all finite products and coproducts, the empty ones being $0^\bullet$, so $\mathrm{Ch}(A)$ is additive.

Step 2: kernels and cokernels, degreewise. Let $f\colon C^\bullet \to D^\bullet$ be a chain map, and suppose $j\colon J^\bullet \to C^\bullet$ is a chain map such that each j^n is a kernel of f^n. Then $fj = 0$. If $g\colon T^\bullet \to C^\bullet$ is a chain map with $fg = 0$, then each $g^n = j^nu^n$ for a unique u^n, and

$$j^{n+1}d_J^nu^n = d_C^nj^nu^n = d_C^ng^n = g^{n+1}d_T^n = j^{n+1}u^{n+1}d_T^n$$

so $d_J^nu^n = u^{n+1}d_T^n$, because j^{n+1} is a monomorphism (lemma 55.1.3). Thus u is the unique chain map with $ju = g$, and j is a kernel of f in $\mathrm{Ch}(A)$. Such a j exists: choose kernels $j^n\colon J^n \to C^n$ of the f^n in A (definition 55.1.6). As $f^{n+1}d_C^nj^n = d_D^nf^nj^n = 0$, there is a unique d_J^n with $j^{n+1}d_J^n = d_C^nj^n$, and $j^{n+2}d_J^{n+1}d_J^n = d_C^{n+1}d_C^nj^n = 0$ gives $d_J^{n+1}d_J^n = 0$, again because j^{n+2} is monic. Kernels are unique up to isomorphism, so every kernel of f in $\mathrm{Ch}(A)$ is a kernel of f^n in each degree.

If $q\colon D^\bullet \to Q^\bullet$ is a chain map such that each q^n is a cokernel of f^n, and $g\colon D^\bullet \to T^\bullet$ is a chain map with $gf = 0$, then each $g^n = v^nq^n$ for a unique v^n, and

$$d_T^nv^nq^n = d_T^ng^n = g^{n+1}d_D^n = v^{n+1}q^{n+1}d_D^n = v^{n+1}d_Q^nq^n$$

gives $d_T^nv^n = v^{n+1}d_Q^n$, because q^n is an epimorphism (lemma 55.1.3). So q is a cokernel of f in $\mathrm{Ch}(A)$. Such a q exists: choose cokernels q^n of the f^n. As $q^{n+1}d_D^nf^n = q^{n+1}f^{n+1}d_C^n = 0$, there is a unique d_Q^n with $d_Q^nq^n = q^{n+1}d_D^n$, and $d_Q^{n+1}d_Q^nq^n = q^{n+2}d_D^{n+1}d_D^n = 0$ gives $d_Q^{n+1}d_Q^n = 0$. As for kernels, every cokernel of f in $\mathrm{Ch}(A)$ is a cokernel of f^n in each degree.

Step 3: monomorphisms and epimorphisms are degreewise. If each f^n is a monomorphism, so is f: from $fg = fh$ we get $f^ng^n = f^nh^n$, hence $g^n = h^n$, for every n. Conversely, let f be a monomorphism of $\mathrm{Ch}(A)$ with kernel j as in Step 2. From $fj = 0 = f \circ 0$ we get $j = 0$, so each $j^n = 0$, and since j^n is a monomorphism, $j^n \circ \mathrm{id}_{J^n} = 0 = j^n \circ 0$ gives $\mathrm{id}_{J^n} = 0$. So J^n is a zero object, $0 \to C^n$ is a kernel of f^n, and f^n is a monomorphism by lemma 55.1.4(1). If each f^n is an epimorphism, then $gf = hf$ gives $g^n = h^n$ for every n, so f is an epimorphism. Conversely, if f is an epimorphism of $\mathrm{Ch}(A)$ with cokernel q as in Step 2, then $qf = 0 = 0 \circ f$ gives $q = 0$, and $\mathrm{id}_{Q^n} \circ q^n = 0 = 0 \circ q^n$ with q^n an epimorphism gives $\mathrm{id}_{Q^n} = 0$. So $D^n \to 0$ is a cokernel of f^n, and f^n is an epimorphism by lemma 55.1.4(2).

Step 4: condition (2) of definition 55.1.6. Let $f\colon C^\bullet \to D^\bullet$ be a monomorphism of $\mathrm{Ch}(A)$ and q a cokernel of f as in Step 2. By Step 3 each f^n is a monomorphism, hence the kernel of some morphism by condition (2) of definition 55.1.6 in A, hence a kernel of its own cokernel q^n by lemma 55.1.7. As f is a chain map, Step 2 applied to q shows that f is a kernel of q in $\mathrm{Ch}(A)$. If instead f is an epimorphism of $\mathrm{Ch}(A)$ and j is a kernel of f as in Step 2, then each f^n is an epimorphism by Step 3, hence a cokernel of its own kernel j^n by condition (2) of definition 55.1.6 and lemma 55.1.7, and Step 2 applied to j shows that f is a cokernel of j. Together with Steps 1 and 2, this verifies definition 55.1.6 for $\mathrm{Ch}(A)$.

Step 5: exactness. By definition 55.1.13, a sequence $C^\bullet \xrightarrow{\varphi} D^\bullet \xrightarrow{\psi} E^\bullet$ is exact at $D^\bullet$ when $\psi\varphi = 0$ and $\operatorname{coker}\varphi \circ \ker\psi = 0$. By Step 2, $\ker\psi$ and $\operatorname{coker}\varphi$ may be taken with components $\ker\psi^n$ and $\operatorname{coker}\varphi^n$, and a chain map is zero exactly when all its components are, so both conditions hold in $\mathrm{Ch}(A)$ exactly when they hold for $C^n \to D^n \to E^n$ for every n. Hence a sequence of complexes is exact if and only if it is exact in each degree, completing the proof.

Since it is an abelian category, we shall be able to consider sequences of complexes, and in particular exact sequences of complexes:

$$\cdots \to L^\bullet \to C^\bullet \to N^\bullet \to \cdots$$

which give a commutative diagram like so:

$$\begin{array}{ccccccccc}
 & & 0 & & 0 & & 0 & & 0 & & \\
 & & \downarrow & & \downarrow & & \downarrow & & \downarrow & & \\
\cdots & \longrightarrow & A_{n+2} & \longrightarrow & A_{n+1} & \longrightarrow & A_n & \longrightarrow & A_{n-1} & \longrightarrow & \cdots \\
 & & \downarrow{\scriptstyle \iota} & & \downarrow{\scriptstyle \iota} & & \downarrow{\scriptstyle \iota} & & \downarrow{\scriptstyle \iota} & & \\
\cdots & \longrightarrow & B_{n+2} & \longrightarrow & B_{n+1} & \longrightarrow & B_n & \longrightarrow & B_{n-1} & \longrightarrow & \cdots \\
 & & \downarrow{\scriptstyle \pi} & & \downarrow{\scriptstyle \pi} & & \downarrow{\scriptstyle \pi} & & \downarrow{\scriptstyle \pi} & & \\
\cdots & \longrightarrow & C_{n+2} & \longrightarrow & C_{n+1} & \longrightarrow & C_n & \longrightarrow & C_{n-1} & \longrightarrow & \cdots \\
 & & \downarrow & & \downarrow & & \downarrow & & \downarrow & & \\
 & & 0 & & 0 & & 0 & & 0 & &
\end{array} \tag{56.1}$$

Example 56.1.6: Complexes

1. Given any object M, we may always create the trivial complex
$$\cdots 0 \to 0 \to M \to 0 \to 0 \to \cdots$$
Verify that this is indeed a complex.
2. As mentioned, In R-**Mod**, the free resolution is an example of a complex.
3. Any short exact sequence can be thought of an (exact) complex if we add 0's that extend arbitrarily to the left and right.
4. Let $C^n = \mathbb{Z}/8\mathbb{Z}$ for $n \geq 0$ and $C^n = 0$ for $n < 0$. Let each d^n be defined as:
$$\overline{x} \mapsto \overline{4x}$$
Show that this is a cochain complex.
5. Let $\{V_i, W_i\}_{i\in\mathbb{Z}}$ be a collection of vector spaces. Define:
$$A_n = V_n \oplus W_n \oplus V_{n-1}$$
Combining the projection and inclusion maps $A_n \to V_{n-1} \to A_{n-1}$, show that $A_\bullet$ forms a chain complex.
6. Let $C^\bullet$ be a cochain complex, choose an object $A \in \mathbf{A}$, and apply $\mathrm{Hom}_A(-, A)$ to each object. Show that this is a cochain complex.

Since Ch($\mathbf{A}$) is an abelian category, kernels and cokernels exist and match with monomorphisms/epimorphisms, hence giving us the following:

Definition 56.1.7: Sub-complexes And Quotient Complexes

Let $C^\bullet$ be a (co)chain complex. Then a (co)chain complex $N^\bullet$ is called a *subcomplex* if each N_n is a sub-object of C_n and the differential on B_n is the restriction of the differential in C_n (categorically, the inclusion map $\iota : N^\bullet \to C^\bullet$ is a morphism of complexes).

Furthermore, C^n/B^n is a *quotient-complex*. Furthermore, by the canonical decomposition of morphisms in abelian categories, for any complex-morphism $\alpha^\bullet$, $\{\ker(\alpha^\bullet)\}$ and $\{\text{coker}(\alpha^\bullet)\}$ is a sub-complex and quotient complex respectively.

56.1.1 Homology and Cohomology

Chain complexes need not be exact. The cohomology of a complex measures how far away a complex is from being exact, that is how far away a complex is form representing a sequence of extensions

Definition 56.1.8: Homology and Cohomology Of A Complex

Let $(C^\bullet, d^\bullet)$ be a complex. Then the ith homology and cohomology of the complex at M^i is, respectively:

$$H_i(C^\bullet) = \frac{\ker d_i}{\text{im} d_{i+1}} \qquad H^i(C^\bullet) := \frac{\ker d^i}{\text{im} d^{i-1}}$$

Though homology and cohomology are similar, it is not necessarily the case that $H^i(C^\bullet) = H_{n-i}(C^\bullet)$ for some appropriate n around which the chain can "pivot". We shall see such examples soon, and later also show under what conditions we may compare homology and cohomology[2]

Example 56.1.9: Cohomology Of Complex

Let's compute the cohomology of sequences in example 56.1.6.

1. The homology and cohomology at the 0th entry is:
$$\frac{\ker(d_0)}{\text{im}(d_1)} = \frac{\ker(d^0)}{\text{im}(d^{-1})} = M$$
which shows that at this position, the chain is "off" by M in being exact.
2. A free resolution $\cdots \to F_1 \to F_0 \to M \to 0$, with M kept as the last term, is exact, meaning $\text{im}(d^{i-1}) = \ker(d^i)$ in every degree, so its homology and cohomology vanish. With M removed the complex $\cdots \to F_1 \to F_0 \to 0$ has homology M in degree 0 and 0 elsewhere.
3. Any exact sequence has trivial homology and cohomology
4. This complex is not exact. Since d^n is multiplication by 4 on $\mathbb{Z}/8\mathbb{Z}$, its kernel is $\{\overline{0}, \overline{2}, \overline{4}, \overline{6}\}$ and its image is $\{\overline{0}, \overline{4}\}$. So $H^0 = \ker d^0 \cong \mathbb{Z}/4\mathbb{Z}$, and $H^n \cong \mathbb{Z}/2\mathbb{Z}$ for every $n \geq 1$.

[2]The universal coefficient theorem and Poincaré duality being two famous examples the reader may have heard of if they took algebraic topology

5. The reader should calculate this cohomology as an exercise
6. This cohomology shall be calculated later in this chapter.

Lemma 56.1.10: Cohomology Functor

For every $i \in \mathbb{Z}$, there exists a functor:

$$H^i : \mathrm{Ch}(A) \to A \qquad C^\bullet \mapsto H^i(C^\bullet)$$

which is additive and covariant.

This shows that taking cohomology is indeed a way of analyzing resolutions, for it preserves enough of the structures of modules and complexes. Notice it is not necessarily an exact functor, hence it will not in general preserve extensions.

***Proof*:**
We compute with elements, as theorem 55.1.15 permits when applied to a small abelian subcategory containing the objects involved. Let $\alpha\colon C^\bullet \to N^\bullet$ be a chain map, so that $d^i_N\alpha^i = \alpha^{i+1}d^i_C$ for every i. If $z \in \ker d^i_C$, then $d^i_N(\alpha^i(z)) = \alpha^{i+1}(d^i_C(z)) = 0$, so α^i maps $\ker d^i_C$ into $\ker d^i_N$. If $z = d^{i-1}_C(w)$, then $\alpha^i(z) = d^{i-1}_N(\alpha^{i-1}(w))$, so α^i maps $\mathrm{im}d^{i-1}_C$ into $\mathrm{im}d^{i-1}_N$. Hence

$$H^i(\alpha)\colon H^i(C^\bullet) \to H^i(N^\bullet) \qquad z + \mathrm{im}d^{i-1}_C \mapsto \alpha^i(z) + \mathrm{im}d^{i-1}_N$$

is a well-defined homomorphism of the quotients of definition 56.1.8. The formula gives $H^i(\mathrm{id}_{C^\bullet}) = \mathrm{id}$ and, since $(\beta\circ\alpha)^i = \beta^i\circ\alpha^i$, also $H^i(\beta\circ\alpha) = H^i(\beta)\circ H^i(\alpha)$, so H^i is a covariant functor. It is additive because $(\alpha+\alpha')^i(z) = \alpha^i(z) + \alpha'^i(z)$ gives $H^i(\alpha+\alpha') = H^i(\alpha) + H^i(\alpha')$, as claimed.

Notice that each H^i takes d^i to the zero map. Hence, we may consider the following functor:

$$H^\bullet : \mathrm{Ch}(\mathbf{A}) \to \mathrm{Ch}(\mathbf{A})$$

by taking $H^i(C^\bullet)$ for each i and connecting them by the zero-morphism. This is the cohomology of this complex then equals that of $C^\bullet$, namely:

$$H^\bullet(H^\bullet(C^\bullet)) = H^\bullet(C^\bullet)$$

Lemma 56.1.11: Cohomology And Products

Let $\{A^\bullet_\alpha\}$ be a collection of complexes in $\mathbf{A}$, and suppose the coproduct (respectively the product) indexed by α exists and is an exact functor. Then

$$H^n\Big(\bigoplus_\alpha A^\bullet_\alpha\Big) = \bigoplus_\alpha H^n(A^\bullet_\alpha) \qquad H^n\Big(\prod_\alpha A^\bullet_\alpha\Big) = \prod_\alpha H^n(A^\bullet_\alpha)$$

The exactness hypothesis is automatic for *finite* index sets, where the two agree by lemma 55.1.5, and it holds for arbitrary index sets in R-Mod.

***Proof*:**
Treat the coproduct; the product is the same argument in the opposite category. The complex $\bigoplus_\alpha A_\alpha^\bullet$ has n-th term $\bigoplus_\alpha A_\alpha^n$ and differential $\bigoplus_\alpha d_\alpha^n$.

An exact functor preserves kernels and images, so

$$\ker\Big(\bigoplus_\alpha d_\alpha^n\Big) = \bigoplus_\alpha \ker d_\alpha^n, \qquad \operatorname{im}\Big(\bigoplus_\alpha d_\alpha^{n-1}\Big) = \bigoplus_\alpha \operatorname{im} d_\alpha^{n-1}$$

and it preserves the quotient of the second by the first, being exact. Hence

$$H^n\Big(\bigoplus_\alpha A_\alpha^\bullet\Big) = \frac{\bigoplus_\alpha \ker d_\alpha^n}{\bigoplus_\alpha \operatorname{im} d_\alpha^{n-1}} = \bigoplus_\alpha \frac{\ker d_\alpha^n}{\operatorname{im} d_\alpha^{n-1}} = \bigoplus_\alpha H^n(A_\alpha^\bullet)$$

For a finite index set the coproduct is a finite biproduct, which every additive functor preserves, so no hypothesis is needed; in R-Mod both $\bigoplus$ and $\prod$ are exact and kernels and images are computed componentwise, giving the statement for arbitrary index sets. This completes the proof.

A complex can be cut off at a degree n so as to keep exactly its cohomology in degrees at most n, or exactly its cohomology in degrees at least n.

Definition 56.1.12: Canonical Truncation

Let $X \in \mathrm{Ch}(\mathbf{A})$ and $n \in \mathbb{Z}$, and write $Z^n = \ker d^n$ and $B^n = \operatorname{im} d^{n-1}$ as in definition 56.1.2. The *canonical truncations* of X at n are the complexes

$$\begin{aligned} \tau^{\le n}X: &\quad \cdots \to X^{n-2} \to X^{n-1} \to Z^n \to 0 \to \cdots \\ \tau^{\ge n}X: &\quad \cdots \to 0 \to X^n/B^n \to X^{n+1} \to X^{n+2} \to \cdots \end{aligned}$$

with Z^n and X^n/B^n in degree n. The map $X^{n-1} \to Z^n$ is d^{n-1}, which lands in Z^n because $d^n d^{n-1} = 0$, and $X^n/B^n \to X^{n+1}$ is induced by d^n, which vanishes on B^n. All other differentials are those of X. The inclusion $Z^n \to X^n$ together with identities in degrees below n is a chain map $i_n : \tau^{\le n}X \to X$, and the quotient $X^n \to X^n/B^n$ together with identities in degrees above n is a chain map $p_n : X \to \tau^{\ge n}X$.

Both squares at degree n commute: d^n vanishes on Z^n, and the quotient map kills $\operatorname{im} d^{n-1} = B^n$. A chain map $f : X \to Y$ carries $Z^n(X)$ into $Z^n(Y)$ and $B^n(X)$ into $B^n(Y)$, so it induces chain maps $\tau^{\le n}f$ and $\tau^{\ge n}f$. This makes $\tau^{\le n}$ and $\tau^{\ge n}$ functors $\mathrm{Ch}(\mathbf{A}) \to \mathrm{Ch}(\mathbf{A})$, with i_n and p_n natural.

Example 56.1.13: Truncating a Resolution of $\mathbb{Z}/2$

Let X be the complex $\mathbb{Z} \xrightarrow{2} \mathbb{Z}$ in degrees -1 and 0. Then $Z^{-1} = \ker(2) = 0$, so $\tau^{\le -1}X = 0$. Also $B^0 = 2\mathbb{Z}$, so $\tau^{\ge 0}X$ is $\mathbb{Z}/2\mathbb{Z}$ in degree 0, and $p_0 : X \to \tau^{\ge 0}X$ is the reduction map $\mathbb{Z} \to \mathbb{Z}/2\mathbb{Z}$ in degree 0. Since $B^{-1} = 0$ and $Z^0 = X^0$, both $\tau^{\ge -1}X$ and $\tau^{\le 0}X$ equal X.

Proposition 56.1.14: Cohomology of the Canonical Truncations

Let $X \in \mathrm{Ch}(\mathbf{A})$ and $n \in \mathbb{Z}$. Then $H^i(i_n)\colon H^i(\tau^{\leq n}X) \to H^i(X)$ is an isomorphism for $i \leq n$, and $H^i(\tau^{\leq n}X) = 0$ for $i > n$. Likewise $H^i(p_n)\colon H^i(X) \to H^i(\tau^{\geq n}X)$ is an isomorphism for $i \geq n$, and $H^i(\tau^{\geq n}X) = 0$ for $i < n$. In particular i_n induces an isomorphism on every H^i when $H^i(X) = 0$ for all $i > n$, and p_n does when $H^i(X) = 0$ for all $i < n$.

***Proof*:**
We compute with elements, as theorem 55.1.15 permits.

Step 1: $\tau^{\leq n}X$. For $i \leq n-2$ the complexes $\tau^{\leq n}X$ and X agree in degrees $i-1$, i and $i+1$, and i_n is the identity there. For $i = n-1$ the kernel of $X^{n-1} \to Z^n$ equals the kernel of d^{n-1}, because $Z^n \to X^n$ is a monomorphism, and the image from degree $n-2$ is unchanged, so $H^{n-1}(i_n)$ is the identity of $H^{n-1}(X)$. In degree n the kernel of $Z^n \to 0$ is Z^n and the image of $X^{n-1} \to Z^n$ is B^n, so $H^n(\tau^{\leq n}X) = Z^n/B^n = H^n(X)$, and $H^n(i_n)$, induced by the inclusion $Z^n \to X^n$, is the identity of Z^n/B^n. Above degree n the complex $\tau^{\leq n}X$ is zero.

Step 2: $\tau^{\geq n}X$. For $i \geq n+2$ the two complexes agree in degrees $i-1$, i, $i+1$. For $i = n+1$ the kernel of d^{n+1} is unchanged, and the image of $X^n/B^n \to X^{n+1}$ equals the image of d^n, because $X^n \to X^n/B^n$ is an epimorphism. In degree n the induced map sends $x + B^n$ to $d^n x$, so its kernel is Z^n/B^n, and nothing maps into degree n. So $H^n(\tau^{\geq n}X) = Z^n/B^n = H^n(X)$, and $H^n(p_n)$ is the identity of Z^n/B^n. Below degree n the complex $\tau^{\geq n}X$ is zero. The last sentence of the statement follows from the two descriptions, completing the proof.

Now, given a morphism of complexes $\alpha^\bullet : C^\bullet \to N^\bullet$, we may ask what (co)homological information such a morphism preserves. In other words, given a morphism $\alpha^\bullet$, when is $H^\bullet(\alpha^\bullet)$ an isomorphism? We give such morphisms a name:

Definition 56.1.15: Quasi-Isomorphism

Let $\alpha^\bullet : C^\bullet \to N^\bullet$ be a morphism of complexes. Then if $H^\bullet(\alpha^\bullet) : H^\bullet(C^\bullet) \to H^\bullet(N^\bullet)$ is an isomorphism, $\alpha^\bullet$ is called a *quasi-isomorphism*

One may wonder if the fact that the (co)homology is isomorphism is strong enough of a condition for the chains to be isomorphic. This turns out to be rather far from the case:

Example 56.1.16: Quasi-Isomorphism

1. The following counter example shall come up with many different minor variations, and so the reader should keep this in mind. Take the following morphism of complexes:

$$\begin{array}{ccccccccccc}
\cdots & \longrightarrow & 0 & \longrightarrow & \mathbb{Z} & \xrightarrow{\cdot 2} & \mathbb{Z} & \longrightarrow & 0 & \longrightarrow & \cdots \\
 & & \downarrow & & \downarrow & & \downarrow{\scriptstyle \pi} & & \downarrow & & \\
\cdots & \longrightarrow & 0 & \longrightarrow & 0 & \longrightarrow & \mathbb{Z}/2\mathbb{Z} & \longrightarrow & 0 & \longrightarrow & \cdots
\end{array}$$

   This is a quasi-isomorphism, as the reader should check, however it does not have an inverse.

More generally, it is not even an equivalence relation, failing to be symmetric (show there is no morphism the other way around that is a quasi-isomorphism).

2. A quasi-isomorphism between $C^\bullet$ and the complex $H^\bullet(C^\bullet)$ need not exist in a given direction. For $C^\bullet$ as in (1), every chain map $\mathbb{Z}/2 \to C^\bullet$ is zero, since $\mathrm{Hom}(\mathbb{Z}/2, \mathbb{Z}) = 0$, so no quasi-isomorphism $H^\bullet(C^\bullet) \to C^\bullet$ exists. What does hold is the case of cohomology in a single degree n: then $i_n : \tau^{\leq n} C^\bullet \to C^\bullet$ and $\tau^{\leq n} C^\bullet \to \tau^{\geq n}\tau^{\leq n} C^\bullet = H^n(C^\bullet)[-n]$ are quasi-isomorphisms, by proposition 56.1.14.

3. Let $\iota(A) \in \mathrm{Obj}(\mathrm{Ch}(\mathbf{A}))$ be the complex with A at the 0th position and zero's everywhere else. Say that $C^\bullet$ is a resolution such that $C^\bullet \to \iota(A)$ is a quasi-isomorphism. Show that this implies $C^\bullet$ is exact everywhere except possibly at $H^0(M^0)$

The lack of symmetry means that quasi-isomorphisms do not form an equivalence relation, but a *weak equivalence relation* (a relation that is reflective and transitive, but not symmetric). This is rather a pity, since if it did form an equivalence relation, then the equivalence class of morphisms up to weak isomorphism would hold all the necessary (co)homological information. Alas, this was not mean to be. Thus, in the pursuit of finding (co)homological invariants, it productive to ask how (co)homological information can be detected between (co)chain complexes. One idea is to map $\mathrm{Ch}(\mathbf{A})$ into another category $D(\mathbf{A})$ in which quasi-isomorphisms become isomorphisms. If quasi-isomorphisms formed equivalence relationships, we could have formed a congruence category which would satisfy this condition, however as just mentioned this cannot be the case.

Such a functor has already been encountered: the (co)homology functor is already one such example. It is more fruitful to as if this can be done in a *univerasl* way, that is if there is a category $D(\mathbf{A})$ where for any category D for which there exists an additive functor $\mathscr{F} : \mathrm{Ch}(\mathbf{A}) \to D$ where every quasi-isomorphism in $\mathrm{Ch}(\mathbf{A})$ becomes an isomorphism in D, there exists a unique functor such that the following diagram commutes:

$$\begin{array}{ccc} \mathrm{Ch}(\mathbf{A}) & \xrightarrow{\mathscr{F}} & D \\ \downarrow & \nearrow_{\exists!} & \\ D(\mathbf{A}) & & \end{array} \tag{56.2}$$

The localization of section 55.2 produces this category, called the *derived category* (hence the $D(-)$ notation).

Corollary 56.1.17: Existence of the Derived Category

Let $\mathbf{A}$ be an abelian category and let qis denote the class of quasi-isomorphisms in $\mathrm{Ch}(\mathbf{A})$. Then the localization

$$D(\mathbf{A}) := \mathrm{Ch}(\mathbf{A})[\mathrm{qis}^{-1}]$$

exists, and the canonical functor $Q : \mathrm{Ch}(\mathbf{A}) \to D(\mathbf{A})$ is universal among functors carrying quasi-isomorphisms to isomorphisms.

***Proof*:**
Apply theorem 55.2.2 with $\mathcal{C} = \mathrm{Ch}(\mathbf{A})$ and $W = \mathrm{qis}$, which needs no hypothesis on W. The universal property is clause (2) of definition 55.2.1, as we sought to show.

The construction leaves open whether $D(\mathbf{A})$ is locally small.

56.1.18 Warning: Quasi-Isomorphisms of Complexes Are Not a Multiplicative System For $\mathrm{Ch}(\mathbf{A})$ localized at quasi-isomorphisms, the second remedy of box 55.2.3 fails whenever $\mathbf{A}$ has a nonzero object E, and the first fails when $\mathbf{A}$ is a category of modules, since $\mathrm{Ch}(\mathbf{A})$ is then not small. The second fails because the quasi-isomorphisms are *not* a multiplicative system: conditions (2) and (3) of definition 55.2.4 both fail. Let $C^\bullet = (E \xrightarrow{\mathrm{id}} E)$ in degrees $-1, 0$, which is acyclic, so that $0 \to C^\bullet$ and $C^\bullet \to 0$ are quasi-isomorphisms, and let $h\colon E[0] \to C^\bullet$ be the chain map that is the identity in degree 0, where $E[0]$ is E in degree 0. Condition (2) for h and $0 \to C^\bullet$, and condition (3) for the pair $h, 0$ and $C^\bullet \to 0$, each require a quasi-isomorphism $t\colon X^\bullet \to E[0]$ with $h \circ t = 0$. Every chain map $t\colon X^\bullet \to E[0]$ has only a degree-zero component, so $h \circ t = 0$ forces $t = 0$, which is not a quasi-isomorphism since $H^0(E[0]) = E \neq 0$.

The route that repairs this, and the one section 57.2 follows, is to pass first to the homotopy category $K(\mathbf{A})$ of definition 56.1.38. There the quasi-isomorphisms do form a multiplicative system (theorem 57.2.3), theorem 55.2.5 applies, and $D(\mathbf{A}) = K(\mathbf{A})[\mathrm{qis}^{-1}]$.

In some nice categories $\mathbf{A}$, quasi-isomorphisms will line up with the nicer notion of *homotopy-equivalence*, in which case the derived category will be eminently understandable, as section 56.2 shows.

Though quasi-isomorphisms may not be ideal in computing (co)homological invariants, they are still important as the defining concept for (co)homological information. For example, the following shows the relationship between quasi-isomorphism and exactness:

Lemma 56.1.19: Quasi-isomorphisms And Exactness

Let $C^\bullet$ be a cochain complex. Then the following are equivalent:

1. $C^\bullet$ is exact
2. $C^\bullet$ is acyclic, that is $H^\bullet(C^\bullet) = 0$
3. The morphism of complexes $0 \to C^\bullet$ is a quasi-isomorphism

***Proof*:**
(1) $\Leftrightarrow$ (2): exactness of $C^\bullet$ at degree n means $\ker d^n = \mathrm{im} d^{n-1}$, and $H^n(C^\bullet) = \ker d^n / \mathrm{im} d^{n-1}$ by definition 56.1.8. A quotient object is zero exactly when the two are equal, so $C^\bullet$ is exact at every degree if and only if $H^n(C^\bullet) = 0$ for every n.

(2) $\Leftrightarrow$ (3): the zero complex has $H^n(0) = 0$ for every n, and the unique morphism $0 \to C^\bullet$ induces the unique morphism $0 \to H^n(C^\bullet)$ in each degree. That morphism is an isomorphism precisely when $H^n(C^\bullet) = 0$. So $0 \to C^\bullet$ is a quasi-isomorphism, meaning it induces isomorphisms in every degree, if and only if $H^\bullet(C^\bullet) = 0$, completing the proof.

56.1.2 Snake Lemma

We often have multiple ways of constructions a resolution for an object M. We shall often extend resolutions using smaller resolutions. We then get cohomology of this new extended resolution by simply applying the cohomology functor. However, is is this functor exact? More generally, let's say we have a short exact sequence of complexes, then after applying cohomology do we get a short exact sequence of homology complexes? The answer is no: if

$$0 \to L^\bullet \to C^\bullet \to N^\bullet \to 0$$


is a short exact sequence, then we get the (not necessarily exact) sequence:

$$H^i(L^\bullet) \to H^i(C^\bullet) \to H^i(N^\bullet)$$

In terms of morphisms, if we have:

$$\alpha^\bullet : C^\bullet \to N^\bullet$$

Then the morphism after applying the cohomology functor $H^\bullet(\alpha^\bullet) : H^\bullet(C^\bullet) \to H^\bullet(N^\bullet)$ need not be exact, i.e. it does not preserve kernels and cokernels. Can we "fix" this in some way by recovering some exact sequence from this and thus allowing our analysis of building more complicated resolutions for M to be independent of cohomology. The answer is yes, Namely, if we take the cohomology of complexes, we may "snake" like in the following diagram:



Theorem 56.1.20: Snake Lemma

Given a short exact sequence of complexes $0 \to A \xrightarrow{i} B \xrightarrow{j} C \to 0$, we may form a long exact sequence of modules using cohomology:

$$\cdots \to H^n(A) \xrightarrow{i^*} H^n(B) \xrightarrow{j^*} H^n(C) \xrightarrow{\partial} H^{n+1}(A) \xrightarrow{i^*} H^{n+1}(B) \xrightarrow{j^*} H^{n+1}(C) \to \cdots$$

Equivalently, in homological indexing, where the differential lowers degree and H_n is written for the homology in degree n, the same statement reads

$$\cdots \to H_n(A) \xrightarrow{i_*} H_n(B) \xrightarrow{j_*} H_n(C) \xrightarrow{\partial} H_{n-1}(A) \xrightarrow{i_*} H_{n-1}(B) \to \cdots$$

The sequence is natural in the short exact sequence of complexes. Given a commutative diagram of complexes with exact rows

$$\begin{array}{ccccccccc} 0 & \longrightarrow & A & \xrightarrow{i} & B & \xrightarrow{j} & C & \longrightarrow & 0 \\ & & \downarrow{\scriptstyle f} & & \downarrow{\scriptstyle g} & & \downarrow{\scriptstyle h} & & \\ 0 & \longrightarrow & A' & \xrightarrow[i']{} & B' & \xrightarrow[j']{} & C' & \longrightarrow & 0 \end{array}$$

the two long exact sequences form a commutative ladder whose vertical morphisms are $H_n(f)$, $H_n(g)$ and $H_n(h)$. Writing ∂' for the connecting morphism of the second row, the square carrying the two connecting morphisms reads $\partial' \circ H_n(h) = H_{n-1}(f) \circ \partial$.

The two forms are the same statement under $H_n = H^{-n}$, and the book uses both. The proof below constructs the homological form, and the homological variant of the proof also appears in [76].

***Proof*:**
We first define the map $\partial : H_n(C) \to H_{n-1}(A)$. We should keep in mind the following diagram:

$$\begin{array}{ccc} & & A_{n-1} \\ & & \downarrow{\scriptstyle i} \\ B_n & \xrightarrow{\partial} & B_{n-1} \\ \downarrow{\scriptstyle j} & & \\ C_n & & \end{array}$$

Let $c \in C_n$ be a cycle so that $c \in \ker \partial_n$. Since j is surjective, $c = j(b)$ for some $b \in B_n$. Then by definition $\partial : B_n \to B_{n-1}$ so $\partial(b) \in B_{n-1}$. Then by commutativity $j(\partial(b)) = \partial(j(b)) = \partial(c) = 0$ (since c is a cycle), thus $\partial b \in \ker(j)$. Since $\ker j = \mathrm{im} i$, $\partial b = i(a)$ for some $a \in A_{n-1}$. Since $i(\partial a) = \partial i(a) = \partial\partial b = 0$ and i is injective, $\partial a = 0$. Thus, define $\partial : H_n(C) \to H_{n-1}(A)$ by $[c] \mapsto [a]$. This is well defined since:

1. The element a is uniquely determined by ∂b since i is injective.
2. For a different choice b' of b, we get $j(b') = j(b)$, so $b' - b \in \ker(j)$, which is equal to $\mathrm{im}(i)$. Thus $b' - b = i(a')$ for some a', hence $b' = b + i(a')$. This replaces a by the homologous

element $a + \partial a'$, since

$$i(a + \partial a') = i(a) + i(\partial a') = \partial b + \partial i(a') = \partial(b + i(a')) = \partial b'$$

3. A different choice of c within its homology class has the form $c + \partial c'$. Since $c' = j(b')$ for some b',
$$c + \partial c' = c + \partial j(b') = c + j(\partial b') = j(b + \partial b')$$
so b is replaced by $b + \partial b'$, which has the same boundary ∂b, and thus a is unchanged.

Finally, $\partial : H_n(C) \to H_{n-1}(A)$ is a homomorphism, for if $\partial[c_1] = [a_1]$ and $\partial[c_2] = [a_2]$ via elements b_1, b_2, then
$$j(b_1 + b_2) = j(b_1) + j(b_2) = c_1 + c_2$$
and
$$i(a_1 + a_2) = i(a_1) + i(a_2) = \partial b_1 + \partial b_2 = \partial(b_1 + b_2)$$
hence
$$\partial([c_1] + [c_2]) = [a_1] + [a_2]$$
so ∂ is a homomorphism. It remains to show the following inclusions.

1. $\mathrm{im} i_* \subseteq \ker j_*$. Since $ji = 0$, $j_* i_* = 0$.

2. $\mathrm{im} j_* \subseteq \ker \partial$. For a cycle $b \in B_n$, the class $[j(b)]$ may be lifted to b itself, and $\partial b = 0 = i(0)$, so $\partial j_* = 0$.

3. $\mathrm{im}\partial \subseteq \ker i_*$. If $\partial[c] = [a]$ through the choice $b \in B_n$, then $i(a) = \partial b$ is a boundary, so $i_*[a] = [\partial b] = 0$.

4. $\ker j_* \subseteq \mathrm{im} i_*$. Let a cycle $b \in B_n$ represent a homology class in $\ker j_*$, so $j(b) = \partial c'$ for some $c' \in C_{n+1}$. Since j is surjective, $c' = j(b')$ for some $b' \in B_{n+1}$. Then since $\partial j(b') = \partial c' = j(b)$,
$$j(b - \partial b') = j(b) - j(\partial b') = j(b) - \partial j(b') = 0$$
Thus, $b - \partial b' = i(a)$ for some $a \in A_n$. Since $i(\partial a) = \partial i(a) = \partial(b - \partial b') = \partial b = 0$ and i is injective, a is a cycle. Thus:
$$i_*[a] = [b - \partial b'] = [b]$$
showing that i_* maps onto $\ker j_*$.

5. $\ker \partial \subseteq \mathrm{im} j_*$. By definition of ∂, if c represents a homology class in $\ker \partial$, then $a = \partial a'$ for some $a' \in A_n$. The element $b - i(a')$ is a cycle since $\partial(b - i(a')) = \partial b - \partial i(a') = \partial b - i(\partial a') = \partial b - i(a) = 0$. Since
$$j(b - i(a')) = j(b) - ji(a') = j(b) = c$$
we get that $j_*[b - i(a')] = [c]$.

6. $\ker i_* \subseteq \mathrm{im}\partial$. Given a cycle $a \in A_{n-1}$ such that $i(a) = \partial b$ for some $b \in B_n$, then $j(b)$ is a cycle since $\partial j(b) = j(\partial b) = ji(a) = 0$, hence $\partial[j(b)] = [a]$.

It remains to prove naturality. Let a commutative diagram as in the statement be given and let $[c] \in H_n(C)$. Running the construction above, $\partial[c] = [a]$, where $b \in B_n$ satisfies $j(b) = c$ and $i(a) = \partial b$. The element $h(c)$ is a cycle, since $\partial h(c) = h(\partial c) = 0$, and it represents $H_n(h)[c]$. Commutativity of the right-hand square gives $j'(g(b)) = h(j(b)) = h(c)$, so $g(b)$ is an admissible choice of preimage for $h(c)$, and commutativity of the left-hand square gives

$$i'(f(a)) = g(i(a)) = g(\partial b) = \partial(g(b))$$

So $f(a)$ is the element of A'_{n-1} that the construction attaches to $h(c)$ through the choice $g(b)$, and since ∂' does not depend on that choice, $\partial'(H_n(h)[c]) = [f(a)] = H_{n-1}(f)(\partial[c])$. The remaining squares of the ladder commute because H_n is a functor and the given diagram commutes, completing the proof.

Example 56.1.21: Uses Of Snake Lemma

1. *The six-term kernel-cokernel sequence.* The classical statement that carries the name "snake" is a special case of theorem 56.1.20. Suppose given a commutative diagram with exact rows

$$\begin{array}{ccccccccc} 0 & \longrightarrow & A^0 & \longrightarrow & B^0 & \longrightarrow & C^0 & \longrightarrow & 0 \\ & & \downarrow{\scriptstyle f} & & \downarrow{\scriptstyle g} & & \downarrow{\scriptstyle h} & & \\ 0 & \longrightarrow & A^1 & \longrightarrow & B^1 & \longrightarrow & C^1 & \longrightarrow & 0 \end{array}$$

   Read each column as a complex concentrated in degrees 0 and 1, so that $A^\bullet = (A^0 \xrightarrow{f} A^1)$ and likewise for $B^\bullet$ and $C^\bullet$. Exactness of the two rows says precisely that $0 \to A^\bullet \to B^\bullet \to C^\bullet \to 0$ is a short exact sequence of complexes, and for a two-term complex $H^0 = \ker$ and $H^1 = \operatorname{coker}$. Since H^n vanishes outside degrees 0 and 1, the long exact sequence of theorem 56.1.20 has only six nonzero terms:

$$0 \to \ker f \to \ker g \to \ker h \xrightarrow{\partial} \operatorname{coker} f \to \operatorname{coker} g \to \operatorname{coker} h \to 0$$

   The connecting morphism ∂ is the "snake" that crosses from the kernel row to the cokernel row.

2. *A computation.* Apply the six-term sequence to multiplication by a fixed integer $n \geq 1$ on the short exact sequence $0 \to \mathbb{Z} \to \mathbb{Q} \to \mathbb{Q}/\mathbb{Z} \to 0$. Multiplication by n is injective on $\mathbb{Z}$ and bijective on $\mathbb{Q}$, and $\mathbb{Q}/\mathbb{Z}$ is divisible, so

$$\ker f = 0, \quad \ker g = 0, \quad \ker h = \tfrac{1}{n}\mathbb{Z}/\mathbb{Z} \cong \mathbb{Z}/n\mathbb{Z}$$

$$\operatorname{coker} f = \mathbb{Z}/n\mathbb{Z}, \quad \operatorname{coker} g = 0, \quad \operatorname{coker} h = 0$$

   The six-term sequence collapses to $0 \to \mathbb{Z}/n\mathbb{Z} \xrightarrow{\partial} \mathbb{Z}/n\mathbb{Z} \to 0$, forcing ∂ to be an isomorphism. The explicit description confirms it: an element of $\ker h$ is the class of some $q \in \mathbb{Q}$ with $nq \in \mathbb{Z}$, and ∂ sends it to the class of nq in $\mathbb{Z}/n\mathbb{Z}$; the generator $1/n$ goes to the generator 1.

3. *Where the machine is used later.* Every long exact sequence in this book is an instance of theorem 56.1.20. The long exact sequence of derived functors (theorem 56.3.11) applies it to a short exact sequence of resolutions, the exact triangle of a mapping cone (proposition 56.1.24)

applies it to the cone sequence, and the exact couple that generates a spectral sequence (theorem 60.2.2) is nothing but all the long exact sequences of a filtration assembled at once. The topological applications, the Mayer-Vietoris sequence and the long exact sequence of a pair, are developed where they are used, in *Algebraic Topology* [76].

The most-used consequence of the snake lemma is a criterion for recognizing an isomorphism in the middle of a diagram from isomorphisms on either side. It is stated here because it is needed whenever two exact sequences are compared, and in particular in the comparison theorem for spectral sequences (theorem 60.2.7).

Lemma 56.1.22: Five Lemma

Consider a commutative diagram in an abelian category with exact rows

$$\begin{array}{ccccccccc} A_1 & \longrightarrow & A_2 & \longrightarrow & A_3 & \longrightarrow & A_4 & \longrightarrow & A_5 \\ \downarrow{\scriptstyle f_1} & & \downarrow{\scriptstyle f_2} & & \downarrow{\scriptstyle f_3} & & \downarrow{\scriptstyle f_4} & & \downarrow{\scriptstyle f_5} \\ B_1 & \longrightarrow & B_2 & \longrightarrow & B_3 & \longrightarrow & B_4 & \longrightarrow & B_5 \end{array}$$

If f_2 and f_4 are isomorphisms, f_1 is an epimorphism, and f_5 is a monomorphism, then f_3 is an isomorphism.
More precisely, f_3 is a monomorphism as soon as f_2 and f_4 are monomorphisms and f_1 is an epimorphism, and f_3 is an epimorphism as soon as f_2 and f_4 are epimorphisms and f_5 is a monomorphism.

***Proof*:**
By theorem 55.1.15 the diagram may be chased with elements. Label the horizontal maps $\alpha_i \colon A_i \to A_{i+1}$ and $\beta_i \colon B_i \to B_{i+1}$.

Step 1: f_3 is a monomorphism. Assume f_2, f_4 monomorphisms and f_1 an epimorphism, and let $a \in A_3$ with $f_3(a) = 0$. Then $f_4(\alpha_3(a)) = \beta_3(f_3(a)) = 0$, and f_4 is a monomorphism, so $\alpha_3(a) = 0$. By exactness of the top row at A_3 there is $b \in A_2$ with $\alpha_2(b) = a$. Now $\beta_2(f_2(b)) = f_3(\alpha_2(b)) = f_3(a) = 0$, so by exactness of the bottom row at B_2 there is $c \in B_1$ with $\beta_1(c) = f_2(b)$. Since f_1 is an epimorphism, $c = f_1(e)$ for some $e \in A_1$. Then

$$f_2(\alpha_1(e)) = \beta_1(f_1(e)) = \beta_1(c) = f_2(b)$$

and f_2 is a monomorphism, so $\alpha_1(e) = b$. Therefore $a = \alpha_2(b) = \alpha_2(\alpha_1(e)) = 0$, the last equality by exactness of the top row at A_2.

Step 2: f_3 is an epimorphism. Assume f_2, f_4 epimorphisms and f_5 a monomorphism, and let $b \in B_3$. Since f_4 is an epimorphism, $\beta_3(b) = f_4(a)$ for some $a \in A_4$. Then

$$f_5(\alpha_4(a)) = \beta_4(f_4(a)) = \beta_4(\beta_3(b)) = 0$$

by exactness of the bottom row at B_4, and f_5 is a monomorphism, so $\alpha_4(a) = 0$. By exactness of the top row at A_4 there is $c \in A_3$ with $\alpha_3(c) = a$. The element $b - f_3(c)$ satisfies

$$\beta_3(b - f_3(c)) = \beta_3(b) - f_4(\alpha_3(c)) = f_4(a) - f_4(a) = 0$$

so by exactness of the bottom row at B_3 there is $e \in B_2$ with $\beta_2(e) = b - f_3(c)$. Since f_2 is an epimorphism, $e = f_2(g)$ for some $g \in A_2$, and then

$$f_3\big(\alpha_2(g) + c\big) = \beta_2(f_2(g)) + f_3(c) = \big(b - f_3(c)\big) + f_3(c) = b$$

so b lies in the image of f_3.

Under the hypotheses of the first statement both steps apply, so f_3 is both a monomorphism and an epimorphism, hence an isomorphism by lemma 55.1.8, completing the proof.

There is another way of looking at chain complexes which shall be important in elucidating triangle categories in section 57.1.

Mapping Cones

Using a particular total complex, we can detect when a quasi-isomorphism is an isomorphism. This result requires the snake lemma to prove, hence the need to put this section after the snake lemma.

Definition 56.1.23: Mapping Cone


Let $\alpha^\bullet : L^\bullet \to M^\bullet$ be a morphism of complexes. Then the *mapping cone* is the complex denoted by $MC(\alpha^\bullet)$ defined by:

$$MC(\alpha)^i := L[1]^i \oplus M^i = L^{i+1} \oplus M^i$$

where the morphism $d^i_{MC(\alpha)} : MC(\alpha)^i \to MC(\alpha)^{i+1}$ are given by:

$$d^i_{MC(\alpha)}(l, m) := (-d^{i+1}_L(l), \alpha^{i+1}(l) + d^i_M(m))$$

The term mapping cone comes from the topological notion of a mapping cone of a function. Visually, the mapping cone can be seen as the following commutative diagram:




Given $MC(\alpha)^\bullet$, we may define two natural chain maps $C^\bullet \to MC(\alpha)^\bullet$ and $MC(\alpha)^\bullet \to L[1]^\bullet$ induced by the natural exact morphisms $M^i \to L^{i+1} \oplus M^i \to L^{i+1}$ which implies that:

$$0 \to C^\bullet \to MC(\alpha)^\bullet \to L[1]^\bullet \to 0$$

is exact.

Proposition 56.1.24: Mapping Cone And Exact Triangles

There is an exact triangle



where δ is the morphism induced by cohomology

***Proof*:**
The short exact sequence of complexes displayed above,

$$0 \to C^\bullet \to MC(\alpha)^\bullet \to L[1]^\bullet \to 0$$

is exact, so theorem 56.1.20 produces a long exact sequence in cohomology

$$\cdots \to H^n(C^\bullet) \to H^n(MC(\alpha)^\bullet) \to H^n(L[1]^\bullet) \xrightarrow{\delta} H^{n+1}(C^\bullet) \to \cdots$$

Exactness at each of the three kinds of term is precisely exactness of the displayed triangle at each of its three corners, the degree shift $H^n(L[1]^\bullet) = H^{n+1}(L^\bullet)$ being what the label $+1$ records.

The connecting morphism is the one induced by α, with no intervening sign; the projection $MC(\alpha)^\bullet \to L[1]^\bullet$ is a chain map precisely because the shift carries the differential $-d_L$, which is what cancels against the sign in the cone. To see this, unwind definition 56.1.23 on representatives: a class in $H^n(L[1]^\bullet)$ is represented by some $l \in L^{n+1}$ with $d_L l = 0$, and its preimage in $MC(\alpha)^n = L^{n+1} \oplus C^n$ may be taken to be $(l, 0)$. Applying the differential of the cone,

$$d_{MC(\alpha)}(l, 0) = \big(-d_L l,\ \alpha^{n+1}(l)\big) = \big(0,\ \alpha^{n+1}(l)\big)$$

which is the image of $\alpha^{n+1}(l) \in C^{n+1}$ under the inclusion. Hence $\delta[l] = [\alpha^{n+1}(l)]$, that is $\delta = H^{n+1}(\alpha)$, completing the proof.

56.1.25 Remark Not all categories have this triangle property, categories which will have this will be called *triangulated categories*

Proposition 56.1.26: Quasi-isomorphism And Isomorphism

Let $\alpha^\bullet : C^\bullet \to N^\bullet$. Then $H^\bullet(\alpha^\bullet)$ is an isomorphism if and only if $MC(\alpha)^\bullet$ is an exact complex.

***Proof*:**
By proposition 56.1.24, applied with $\alpha\colon C^\bullet \to N^\bullet$, the cone sits in a long exact sequence

$$\cdots \to H^n\big(MC(\alpha)^\bullet\big) \to H^n\big(C[1]^\bullet\big) \xrightarrow{H^{n+1}(\alpha)} H^{n+1}(N^\bullet) \to H^{n+1}\big(MC(\alpha)^\bullet\big) \to \cdots$$

the connecting morphism having been identified there as the map induced by α, and $H^n(C[1]^\bullet) = H^{n+1}(C^\bullet)$.

Suppose $MC(\alpha)^\bullet$ is exact, so that $H^\bullet(MC(\alpha)^\bullet) = 0$ by lemma 56.1.19. Deleting the vanishing terms leaves

$$0 \to H^{n+1}(C^\bullet) \xrightarrow{H^{n+1}(\alpha)} H^{n+1}(N^\bullet) \to 0$$

exact for every n, so each $H^{n+1}(\alpha)$ is an isomorphism.

Conversely suppose every $H^n(\alpha)$ is an isomorphism. Fix n and read the sequence around $H^n(MC(\alpha)^\bullet)$:

$$H^{n-1}(C[1]^\bullet) \xrightarrow{H^n(\alpha)} H^n(N^\bullet) \to H^n\big(MC(\alpha)^\bullet\big) \to H^n(C[1]^\bullet) \xrightarrow{H^{n+1}(\alpha)} H^{n+1}(N^\bullet)$$

The left-hand map is surjective and the right-hand map is injective, both being isomorphisms. Exactness at $H^n(N^\bullet)$ then makes the morphism $H^n(N^\bullet) \to H^n(MC(\alpha)^\bullet)$ zero, and exactness at $H^n(C[1]^\bullet)$ makes the morphism $H^n(MC(\alpha)^\bullet) \to H^n(C[1]^\bullet)$ zero. Exactness at $H^n(MC(\alpha)^\bullet)$ therefore gives

$$H^n\big(MC(\alpha)^\bullet\big) = \ker\big(\text{zero morphism}\big) = \operatorname{im}\big(\text{zero morphism}\big) = 0$$

As n was arbitrary the cone is acyclic, hence exact by lemma 56.1.19, completing the proof.

56.1.3 Chain Homotopies and Homotopic Categories

The notion of homotopies originated in topology as a weaker alternative to continuous functions[3]. The topological notion of homotopy settled on the level of continuous functions, where $f, g : X \to Y$ are homotopic (denoted $f \simeq g$) if there exists a continuous function $F : X \times [0,1] \to Y$ where $F(\cdot, t) = f_t$ is continuous, $f_0 = f$ and $f_1 = g$. If we represent X, Y as one dimensional lines, then we may visualize a homotopy as:

[3] every homeomorphic is a homotopy equivalence, however not every homotopy equivalence is a homeomorphism, hence homotopy can be seen as weaker than continuity




Figure 56.1: homotopy

In the development of homotopy theory, it was found that the (co)homology and homotopy of topological spaces (or their representations as chain complexes) is homology-invariant, hence homotopies are examples of quasi-isomorphisms. The proofs of these results turn out to be independent of the underlying topological structures and is purely algebraic, and hence the notion of homotopy has found a generalization as a purely algebraic notion between two (co)chain complexes.

Due to its origin in topology, the intuitions behind the following definitions will proceed more naturally with a more geometric build-up. Since homotopy may be interpreted purely algebraically, this geometrica build-up will be followed by a more algebraic interpretation. First, the reader may take for granted that given a topological space X, we may induce a chain $C_\bullet$, which is a topological object[4]. Given two continuous maps $f, g : X \to Y$, we may push forward the chain like so:

update image




Figure 56.2: homotopy on chain

The space $h(C_\bullet)$ is a topological space, hence we may ask for it's border, $\partial h(C_\bullet)$. By inspecting the image, we see that:

$$\partial h(C_\bullet) = g(C_\bullet) - \delta_+ - f(C_\bullet) + \delta_- = g(C_\bullet) - f(C_\bullet) - h(\partial C_\bullet)$$

re-ordering, we get:

$$g(C_\bullet) - f(C_\bullet) = \partial h(C_\bullet) + h(\partial C_\bullet)$$

[4]The construction of singular chains is in *Algebraic Topology* [76, Singular n-Simplex, Singular Homology Group]. [59] is the standard outside reference.

Abstracting notation, we get:

$$g - f = \partial h + h\partial \tag{56.3}$$

Now, recall that in a chain complex, the image of the function ∂ is called the boundary, and that by definition of homology the boundary becomes trivial. In a topological setting, this vocabulary reflects the concrete of the boundary map ∂: it maps a chain to it's boundary. What this means for us is that when taking homology on both sides, we get:

$$H^k(g|_{C_\bullet} - f|_{C_\bullet}) = \overline{0}$$

meaning the two maps are equivalent up to homology! In other words, this "geometric intuition" shows that a homotopy is an example of a quasi-isomorphism. Even better, homotopies shall form an equivalence relation, hence they are an example of a quasi-isomorphism that shall capture some (co)homological information (and in the case where all quasi-isomorphisms are homotopies, they could fully capture the (co)homological information!)

Though this is the origins of chain homotopies being (co)homology-invariant, since they may be interpreted in pure algebraic terms, it is worthwhile taking a moment to have an algebraic build-up as well. Algebraically, homotopies can be seen as forming equivalence classes of (co)chain complexes up to *obstruction from being split-exact*. Recall that a split exact sequence is a short exact sequence that is also split at each map, that is there exists a section morphism $s^n : C^n \to C^{n-1}$ such that $d^{n-1} \circ s^n \circ d^{n-1} = d$, or if we drop the indices and collect all the section maps:

$$d = dsd$$

In other words, it is possible to "inverse" the map d via the map s in such a way that it "cancels" the effect of d (for we may re-apply the map d after sd and get the same result). The simplest source of split-exact (co)chains are exact (co)chains of vector-spaces, for any vector-space maps split[5]. Given a cochain, we may write:

$$C^n = Z^n \oplus B' \qquad (B^n)' \cong C^n/Z^n = d(C^n) = B^{n+1}$$

$$Z^n = B^n \oplus (H^n)' \qquad (H^n)' = Z^n/B^n = H^n(C)$$

Hence, $C^n \cong Z^n \oplus B^{n+1}$. This allows for the definition of the section map via the composition:

$$C^n \hookrightarrow Z^n \hookrightarrow B^n \cong d(C^n) \cong B^{n+1} \subseteq C^{n+1}$$

We may thus define the maps $d \circ s$ and $s \circ d$ where $d \circ s(C^n) = B^n$ and $s \circ d(C^n)(B^n)' \cong B^{n+1}$. Adding these maps together, we get a map $ds + sd : C^n \to C^n$ whose kernel is the homology:

$$\ker(ds + sd)_n = H^n(C^\bullet)$$

The kernel (and cokernel) of the chain map $ds + sd$ is naturally $H^\bullet(C^\bullet)$. Working over more general R-modules (and more generally in an arbitrary abelian category), we loose the natural section maps, for example $0 \to \mathbb{Z} \twoheadrightarrow \mathbb{Z}/2\mathbb{Z} \to 0$ does note have a section map for each map. Instead, we may define arbitrary maps $s^n : C^n \to D^{n-1}$ where we may put them in the following (*not* necessarily commutative) diagram:


$$\begin{array}{ccccccccc}
\cdots & \longrightarrow & C^{n-1} & \xrightarrow{d} & C^n & \xrightarrow{d} & C^{n+1} & \longrightarrow & \cdots \\
 & & \searrow & & \searrow^{s^n} & & \searrow^{s^{n+1}} & & \searrow \\
\cdots & \longrightarrow & D^{n-1} & \xrightarrow{d} & D^n & \xrightarrow{d} & D^{n+1} & \longrightarrow & \cdots
\end{array}$$

[5] More generally, any maps of projective modules split

Given any such collection of morphisms, we may define $f^n = s^{n+1} \circ d^n + d^{n-1} \circ s^n$ (or, if dropping indices and abbreviate, $f = sd + ds$). Notice that even though the maps $s^\bullet$ do not commute, $f^\bullet$ *will* create a commutative diagram, in particular it is a chain map. To see this, notice that (after dropping indices):

$$df = d(ds + sd) = dsd = (ds + sd)d = fd$$

showing it is indeed a chain map:



Thus, given any collection of morphisms $s^\bullet$, we may naturally define a chain map using the differentials. Conversely, is every morphism of complexes representable as $ds + sd$. This is not in general the case; maps being representable like so are given a name:

Definition 56.1.27: Null-homotopic Maps

Let $f^\bullet : C^\bullet \to D^\bullet$ be a morphism of complexes. Then f is called *null-homotopic* if there exists a collection $\{s^i\}_{i\in\mathbb{Z}}$ of morphisms $s^i \colon C^i \to D^{i-1}$ such that

$$f^\bullet = ds + sd$$

The maps $s^\bullet$ are called the *chain contraction* of $f^\bullet$

To show that not all maps are null-homotopic, consider the following lemma:

Lemma 56.1.28: Null-homotopic And Split Exact Complexes

Let $C^\bullet$ be a complex. Then $C^\bullet$ is split exact if and only if the identity map is null-homotopic.

***Proof*:**
Throughout, split exact means exact together with a family $s^n \colon C^n \to C^{n-1}$ satisfying $dsd = d$, and null-homotopic means $\mathrm{id} = ds + sd$ for some such family.

Step 1: Null-homotopic implies split exact. Suppose $\mathrm{id} = dt + td$. For exactness, let $c \in \ker d^n$; then

$$c = dt(c) + td(c) = dt(c)$$

so $c \in \mathrm{im} d^{n-1}$, and the reverse inclusion $\mathrm{im} d^{n-1} \subseteq \ker d^n$ holds because $d \circ d = 0$. For the splitting, compute

$$dtd = d(td) = d(\mathrm{id} - dt) = d - d^2t = d$$

so t is a splitting family.

Step 2: Split exact implies null-homotopic. Suppose $C^\bullet$ is exact and $dsd = d$. Set

$$\varphi = ds + sd$$

Then $d\varphi = dsd = d$ and $\varphi d = dsd = d$, both using $d \circ d = 0$; in particular φ commutes with d.

Put $\psi = \mathrm{id} - \varphi$. From the two identities just proved, $d\psi = d - d = 0$ and $\psi d = d - d = 0$. The first says $\mathrm{im}\psi \subseteq \ker d$, and exactness gives $\ker d = \mathrm{im}d$, so $\mathrm{im}\psi \subseteq \mathrm{im}d$; the second says ψ vanishes on $\mathrm{im}d$. Composing, $\psi \circ \psi = 0$.

Therefore $\varphi = \mathrm{id} - \psi$ is invertible, with inverse $\mathrm{id} + \psi$, and φ^{-1} commutes with d because φ does. Set $t = \varphi^{-1}s$. Then

$$dt + td = d\varphi^{-1}s + \varphi^{-1}sd = \varphi^{-1}(ds + sd) = \varphi^{-1}\varphi = \mathrm{id}$$

so the identity is null-homotopic with contraction t, completing the proof.

The name "null-homotopic" comes from how the (co)homology of such maps are trivial:

Proposition 56.1.29: Null-homotopic And Cohomology

Let $f^\bullet : C^\bullet \to D^\bullet$ be null-homotopic. Then $H^\bullet(f)$ is the zero map

***Proof*:**
We compute with elements, applying theorem 55.1.15 to a small abelian subcategory containing the objects involved. Since f is null-homotopic, there are morphisms $s^i \colon C^i \to D^{i-1}$ with $f^n = d_D^{n-1}s^n + s^{n+1}d_C^n$ for every n (definition 56.1.27). Let $x \in C^n$ be a cocycle representing a class $\overline{x} \in H^n(C^\bullet)$. Since $d_C^n(x) = 0$,

$$f^n(x) = d_D^{n-1}(s^n(x)) + s^{n+1}(d_C^n(x)) = d_D^{n-1}(s^n(x))$$

so $f^n(x)$ is a coboundary of $D^\bullet$. The map $H^n(f)$ of lemma 56.1.10 sends $\overline{x}$ to the class of $f^n(x)$, which is therefore $\overline{0}$ in $H^n(D^\bullet)$, as we sought to show.

Thus, maps that are null-homotopic induce zero (co)homology maps![6] Thus, we may think of maps that are null-homotopic as being the "zero" maps. This leads us to the following definition:

Definition 56.1.30: Chain-homotopy

Let $f^\bullet, g^\bullet : C^\bullet \to D^\bullet$ be two morphisms of complexes. Then we say that these two maps are *chain homotopic* or just *homotopic* if there exists maps $h^i : C^i \to D^{i-1}$ such that

$$g^i - f^i = d_{D^\bullet}^{i-1} \circ h^i + h^{i+1} \circ d_{C^\bullet}^i$$

or, dropping indices:

$$g^\bullet - f^\bullet = dh + hd$$

If $f^\bullet, g^\bullet$ are homotopic, we write $f^\bullet \sim g^\bullet$

The s notation has been replaced with h notation to emphasize now the "homotopy" aspect of it rather than the "section" property that was evident in the case of vector spaces. If we were working with chains, then we would have

$$g_\bullet - f_\bullet = \partial h + h\partial$$

[6] TBD How much can we say about the converse, if a map induces the zero morphism, then is it null-homotopic?

which, the reader may recognize as equation (56.3). If we were working with chains, then $h_i : C_i \to D_{i+1}$ would shift up a degree, which would be interpreted in the geometrical setting as moving *up* a dimension, in the same way that homotopies are a "dimension more" than the original spaces X, Y. Furthermore, the reader should verify the "up to homotopy" *is* an equivalence relation, as the reader should verify!

Importantly, two chain-homotopic maps induce the same (co)homology:

Proposition 56.1.31: Chain-Homotopy and Cohomology

Let $f^\bullet, g^\bullet : C^\bullet \to D^\bullet$ be chain homotopic. Then

$$H^\bullet(f^\bullet) = H^\bullet(g^\bullet)$$

***Proof*:**
Since $f^\bullet$ and $g^\bullet$ are chain-homotopic, by proposition 56.1.29 for each element in $H^k(C^\bullet)$ (since it is an additive functor):

$$H^k(f^\bullet)(\overline{x}) - H^k(g^\bullet)(\overline{x}) = 0 \qquad \Rightarrow \qquad H^k(f^\bullet)(\overline{x}) = H^k(g^\bullet)(\overline{x})$$

as we sought to show.

The above result shows promise in using chain-homotopies to hold (co)homological information. The following definition is the important connection idea:

Definition 56.1.32: Homotopy Equivalent Chains

Let $f^\bullet : C^\bullet \to D^\bullet$ be a morphism of complexes. Then $f^\bullet$ is a *homotopy equivalence* if there exists a morphisms of complexes $g^\bullet : D^\bullet \to C^\bullet$ such that

$$f^\bullet \circ g^\bullet \sim 1_{D^\bullet} \qquad \text{and} \qquad g^\bullet \circ f^\bullet \sim 1_{C^\bullet}$$

If $f^\bullet : C^\bullet \to D^\bullet$ is a homotopy equivalence, then $C^\bullet$ and $D^\bullet$ are said to be *homotopy equivalent*

Proposition 56.1.33: Homotopy Equivalence Ans Cohomology

Let $f^\bullet : C^\bullet \to D^\bullet$ be a homotopy equivalence. Then $f^\bullet$ is a quasi-isomorphism, that is $H^\bullet(f^\bullet)$ is an isomorphism

***Proof*:**
Since $f^\bullet$ is a homotopy equivalence, we have $g^\bullet$ that is it's homotopic inverse. Then the maps $f^\bullet \circ g^\bullet$ and $g^\bullet \circ f^\bullet$ induce inverse morphisms of cohomology by proposition 56.1.31, and hence give an isomorphism, as we sought to show.

As demonstrated in example 56.1.16 not all quasi-isomorphisms are invertible even up to homotopy equivalence, hence quasi-isomorphisms are more general. As mentioned earlier, in nice enough categories these two concepts shall coincide.

Now that homotopy equivalences is established, can be asked if given an (additive) functor $\mathscr{F} : \mathbf{A} \to \mathbf{B}$, if there are two homotopic complexes in $\mathrm{Ch}(\mathbf{A})$, will the (co)homology be isomorphic in $\mathbf{B}$? In other words, when trying to define the derived category that was mentioned earlier, can this category be defined at least up to homotopy? The answer is yes! The proof of this result essentially follows from the following lemma:

Lemma 56.1.34: Homotopy Equivalence And Additive Functors

Let $\mathscr{F} : \mathbf{A} \to \mathbf{B}$ be an additive functor between two abelian categories, $C(\mathscr{F})$ the induced functor on chains. Then if $f^\bullet \sim g^\bullet$ in $\mathrm{Ch}(\mathbf{A})$, $C(\mathscr{F})(f^\bullet) \sim \mathrm{Ch}(\mathbf{B})(g^\bullet)$ in $\mathrm{Ch}(\mathbf{B})$. Furthermore, if $C^\bullet$ and $D^\bullet$ are homotopy equivalence, $C(\mathscr{F})(C^\bullet)$ and $C(\mathscr{F})(D^\bullet)$ are homotopy equivalent

***Proof*:**
Given the first assertion, the second is an immediate consequence, hence we prove the first. Let $f^\bullet \sim g^\bullet$ so that :

$$f^i - g^i = d^{i-1}_{D^\bullet} \circ h^i + h^{i+1} \circ d^i_{C^\bullet}$$

Since $\mathscr{F}$ is an additive functor:

$$\mathscr{F}(f^i) - \mathscr{F}(g^i) = \mathscr{F}\left(d^{i-1}_{D^\bullet}\right) \circ \mathscr{F}(h^i) + \mathscr{F}\left(h^{i+1}\right) \circ \mathscr{F}\left(d^i_{C^\bullet}\right)$$

hence, the morphisms $\mathscr{F}(h^i)$ gives a homotopy between $\mathscr{F}(f^\bullet)$ and $\mathscr{F}(g^\bullet)$, as we sought to show.

Note this does *not* hold for quasi-isomorphisms (exercise 4.15 in Aluffi), needing the stronger condition of exact functors.

Theorem 56.1.35: Derived Category And Homotopy Equivalence

Let $\mathscr{F} : \mathbf{A} \to \mathbf{B}$ be an additive functor between two abelian categories. Then if $C^\bullet$ and $D^\bullet$ are homotopy-equivalent, then:

$$H^\bullet(\mathscr{F}(C^\bullet)) \cong H^\bullet(\mathscr{F}(D^\bullet))$$

that is, their cohomology is isomorphic.

***Proof*:**
By lemma 56.1.34, an additive functor carries homotopy-equivalent complexes to homotopy-equivalent complexes, so $\mathscr{F}(C^\bullet)$ and $\mathscr{F}(D^\bullet)$ are homotopy equivalent in $\mathrm{Ch}(\mathbf{B})$. By proposition 56.1.33 a homotopy equivalence is a quasi-isomorphism, so the induced map on cohomology is an isomorphism, giving $H^\bullet(\mathscr{F}(C^\bullet)) \cong H^\bullet(\mathscr{F}(D^\bullet))$, as we sought to show.

Hence, up to homotopy, the choice of cochain shall give the same cohomology information!

Homotopic Categories


With chain homotopies being a nicer sub-class of quasi-isomorphisms, their exploration is worth further pursuing. They are in fact almost the solution to the universal problem given in equation (56.2).

Let us take for granted that a category $D(A)$ exists that satisfies the universal property. What necessary conditions can be deduced about $D(A)$?

Lemma 56.1.36: Derived Category And Additive Functors

Let $\mathbf{D}$ be an additive category, $\mathscr{F} : \mathrm{Ch}(\mathbf{A}) \to \mathbf{D}$ be an additive functor that takes quasi-isomorphisms to isomorphisms.


1. Let $C^\bullet$ be an exact complex in $\mathrm{Ch}(\mathbf{A})$. Then $\mathscr{F}(C^\bullet) = 0$, that is $\mathscr{F}(C^\bullet)$ is the zero object in $\mathbf{D}$.
2. Let $\alpha^\bullet : C^\bullet \to E^\bullet$ be a morphism of complexes that factors through an exact complex:



   where $D^\bullet$ is exact. Then $\mathscr{F}(\alpha^\bullet)$ is the zero morphism.

***Proof*:**

1. Since $C^\bullet$ is exact, the zero morphism $0^\bullet : C^\bullet \to C^\bullet$ is a quasi-isomorphism, and so $\mathscr{F}(0^\bullet)$ maps to an isomorphism (i.e. an invertible morphism in $\mathbf{D}$). Thus:




   Since $\mathscr{F}$ is additive functor, in particular a group homomorphism on hom-sets, $\mathscr{F}(0) = 0$. Thus:

$$\mathrm{id}_{\mathscr{F}(C^\bullet)} = 0$$

   It follows that $\mathscr{F}(C^\bullet)$ must be the zero object: an object whose identity morphism is zero admits only the zero endomorphism, so it is isomorphic to 0

2. Applying $\mathscr{F}$ to the diagram in the question, we get the diagram:



   Since $\mathscr{F}(D^\bullet) = 0$ by the above result, we see that $\mathscr{F}(\alpha^\bullet)$ must be the zero morphisms, completing the proof.

Lemma 56.1.37: Derived Categories And Homotopies

Let $\mathscr{F} : \mathrm{Ch}(\mathbf{A}) \to \mathbf{D}$ be an additive functor that maps quasi-isomorphisms to isomorphisms. Let $f^\bullet, g^\bullet : C^\bullet \to D^\bullet$ be homotopic morphisms in $\mathrm{Ch}(\mathbf{A})$. Then

$$\mathscr{F}(f^\bullet) = \mathscr{F}(g^\bullet)$$

Note that this was shown explicitly when $\mathscr{F} = H^i(-)$.

***Proof*:**
Since $\mathscr{F}$ is additive, it suffices to show that if $f^\bullet \sim 0$, then $\mathscr{F}(f^\bullet) = 0$. By lemma 56.1.36, it suffices to show $f^\bullet$ factors through an exact complex. The exact complex that shall be used is the mapping cone $MC(\mathrm{id}_{C^\bullet})$ for the identity map $\mathrm{id}_{C^\bullet} : C^\bullet \to C^\bullet$, namely

$$MC(\mathrm{id}_{C^\bullet})^i = C^{i+1} \oplus C^i$$

$$d^i_{MC(\mathrm{id}_{C^\bullet})}(a, b) = (-d^{i+1}_{C^\bullet}(a), a + d^i_{C^\bullet}(b))$$

By proposition 56.1.26, since the identity map $\mathrm{id}_{C^\bullet}$ is (trivially) a quasi-isomorphism, $MC(\mathrm{id}_{C^\bullet})$ is an exact complex.

Now, the goal is to find morphism of complexes where:

$$C^\bullet \to MC(\mathrm{id}_{C^\bullet}) \to D^\bullet$$

the morphism of complexes $C^\bullet \to MC(\mathrm{id}_{C^\bullet})$ is readily available: for each i:

$$b \mapsto (0, b)$$

On the other hand, it is not immediately clear there is a morphism of complexes $MC(\mathrm{id}_{C^\bullet}) \to D^\bullet$. To find such a morphism, we take advantage of the homotopy $f^\bullet \sim 0$, that is there exists maps:

$$h^i : C^i \to D^{i-1}$$

such that $f^\bullet = fh + hd$. With these, define the maps:

$$\pi^i : MC(\mathrm{id}_{C^\bullet})i \to D^i \qquad (a, b) \mapsto h^{i+1}(a) + f^i(b)$$

If this is indeed a morphism of complexes, then the map $f : C^\bullet \to D^\bullet$ factored through an exact complex and hence must be trivial. What must be verified is that:

$$d^{i-1}_{D^\bullet} \circ \pi^{i+1} = \pi^i \circ d^{i-1}_{MC(\mathrm{id}_{C^\bullet})} \tag{56.4}$$

The left hand side of equation (56.4) gives:

$$(a, b) \mapsto h^i(a) + f^{i-1}(b) \mapsto d^{i-1}_{D^\bullet}(h^i(a) + f^{i-1}(b))$$

while the right hand side gives:

$$(a, b) \mapsto (-d^i_{C^\bullet}(a), a + d^{i-1}_{L^\bullet}(b)) \mapsto -h^{i+1}(d^i_{C^\bullet}(a) + f^i(a + d^{i-1}_{C^\bullet}(b))$$

These two sides must be equal. Simplifying the equality, we get:

$$(d^{i-1}_{D^\bullet} \circ h^i + h^{i+1} \circ d^i_{C^\bullet} - f^i)(a) = (f^i \circ d^{i-1}_{C^\bullet} - d^{i-1}_{D^\bullet} \circ f^{-1})(a)$$

for all $a \in C^{i+1}, b \in C^i$. But notice that both sides are zero: the right hand side b $f^\bullet$ is a morphism of complexes, while the left hand side because h is a homotopy and $f^\bullet \sim 0$. But then this gives us our desired result, completing the proof.

Thus, behave well for the desired universal property presented in equation 56.2. We formalize the category in question:

Definition 56.1.38: Homotopy Category

Let $\mathbf{A}$ be an abelian category. Then the *homotopy category* of $\mathbf{A}$, denoted $K(\mathbf{A})$ is the category whose objects ar ethe (co)chain complexes in $\mathbf{A}$ (i.e. $\mathrm{Ch}(\mathbf{A})$), and whose morphisms are:

$$\mathrm{Hom}_{K(\mathbf{A})}(C^\bullet, D^\bullet) = \mathrm{Hom}_{\mathrm{Ch}(\mathbf{A})}(C^\bullet, D^\bullet)/\sim$$

where $\sim$ is the homotopy relation, that is, the morphisms are morphisms of complexes up to homotopy.

These are indeed morphisms, namely $\sim$ is transitive, it respects composition (exercise). Naturally, the equivalent bounded variations $K^-(\mathbf{A})$ and $K^+(\mathbf{A})$ are obtained from $\mathrm{Ch}^+(\mathbf{A})$ and $\mathrm{Ch}^-(\mathbf{A})$.

Lemma 56.1.39: Homotopy Category Is Additive

Let $\mathbf{A}$ be an abelian category. Then $K(\mathbf{A})$ is an *additive category*

***Proof*:**
Recall from definition 56.1.38 that $K(\mathbf{A})$ has the same objects as $\mathrm{Ch}(\mathbf{A})$ and $\mathrm{Hom}_{K(\mathbf{A})}(C^\bullet, D^\bullet) = \mathrm{Hom}_{\mathrm{Ch}(\mathbf{A})}(C^\bullet, D^\bullet)/\sim$, the quotient by chain homotopy.

Step 1: The hom-sets are abelian groups. The null-homotopic morphisms form a subgroup of $\mathrm{Hom}_{\mathrm{Ch}(\mathbf{A})}(C^\bullet, D^\bullet)$: if $f = ds + sd$ and $f' = ds' + s'd$ then $f - f' = d(s - s') + (s - s')d$ is null-homotopic. Being a quotient of an abelian group by a subgroup, each hom-set of $K(\mathbf{A})$ is an abelian group, and $f \sim g$ exactly when $f - g$ is null-homotopic.

Step 2: Composition is well defined and bilinear. Suppose $f \sim f'$, say $f - f' = ds + sd$, and let g be a chain map composable on the left. Since g commutes with the differentials,

$$gf - gf' = g(ds + sd) = d(gs) + (gs)d$$

so $gf \sim gf'$; composing on the right with a chain map h gives $fh - f'h = d(sh) + (sh)d$ likewise. Hence composition descends to the quotient, and it is bilinear because it is bilinear in $\mathrm{Ch}(\mathbf{A})$ and the quotient maps are group homomorphisms.

Step 3: Zero object and biproducts. The zero complex is a zero object in $\mathrm{Ch}(\mathbf{A})$ and remains one after the quotient, since its hom-sets are already zero. For two complexes $C^\bullet$ and $D^\bullet$, the degreewise direct sum $C^\bullet \oplus D^\bullet$ carries the four structure morphisms i_C, i_D, p_C, p_D, which are chain maps and satisfy the biproduct identities $p_C i_C = \mathrm{id}$, $p_D i_D = \mathrm{id}$, $p_C i_D = 0$, $p_D i_C = 0$ and $i_C p_C + i_D p_D = \mathrm{id}$ in $\mathrm{Ch}(\mathbf{A})$. Identities between morphisms are preserved by the quotient functor, so they continue to hold in $K(\mathbf{A})$, and an object with such data is a biproduct there as well.

Together these are the axioms of an additive category, completing the proof.

Note that in general homotopic categories are *not* abelian. Indeed, homotopic maps $f^\bullet \sim g^\bullet$ need not have the same kernel/cokernel, giving no natural definition of these concepts. The homotopic category is a type of category that is stronger than additive but weaker than abelian, known as a *triangulated category* (recall box 56.1.25).

In $K(\mathbf{A})$, homotopy equivalences become isomorphisms. This comes straight from the definition, for if $f^\bullet \circ g^\bullet \sim \mathrm{id}$ in $\mathrm{Ch}(\mathbf{A})$, then $f^\bullet \circ g^\bullet = \mathrm{id}$ in $K(\mathbf{A})$, which can be thought of as formally inverting homotopy equivalences. Using this, we have the following almost universal property, or factorization

It looks like a universal property because it is one, though not the one for quasi-isomorphisms. Comparing with definition 55.2.1, the homotopy category is precisely the localization

$$K(\mathbf{A}) \cong \mathrm{Ch}(\mathbf{A})\big[\{\text{homotopy equivalences}\}^{-1}\big]$$

The proposition below is stated with the hypothesis that $\mathscr{F}$ inverts *quasi-isomorphisms*, which is strictly stronger than it needs to be, and that mismatch is what makes it read as an "almost" universal property. Its proof uses only that $\mathscr{F}$ inverts homotopy equivalences. Inverting all quasi-isomorphisms is the stronger requirement that produces $D(\mathbf{A})$ instead (corollary 56.1.17), and the gap between the two is exactly example 56.1.16: a quasi-isomorphism need not be a homotopy equivalence.

Proposition 56.1.40: Homotopy Category Factorization

Let $\mathscr{F} : \mathrm{Ch}(\mathbf{A}) \to D$ be a functor that maps quasi-isomorphisms to isomorphisms. Then $\mathscr{F}$ factors uniquely through $K(\mathbf{A})$:

$$\begin{array}{ccc} \mathrm{Ch}(\mathbf{A}) & \xrightarrow{\mathscr{F}} & D \\ \downarrow & \nearrow_{\exists!} & \\ K(\mathbf{A}) & & \end{array}$$

***Proof*:**
Since every homotopy equivalence is a quasi-isomorphism (proposition 56.1.33), the hypothesis in particular sends homotopy equivalences to isomorphisms, and that is all the proof uses. Because $\mathscr{F}$ is defined on $\mathrm{Ch}(\mathbf{A})$ and $K(\mathbf{A})$ has the same objects, the only thing to establish is that $f \sim g$ implies $\mathscr{F}(f) = \mathscr{F}(g)$; the factorization and its uniqueness are then forced, since the quotient functor $\mathrm{Ch}(\mathbf{A}) \to K(\mathbf{A})$ is the identity on objects and surjective on morphisms.

Step 1: The cylinder of a complex. For a complex $C^\bullet$ define

$$\mathrm{Cyl}(C)^n = C^n \oplus C^{n+1} \oplus C^n, \qquad d(a,b,c) = (da - b,\ -db,\ dc + b)$$

This squares to zero, since $d^2(a,b,c) = (d(da-b)+db,\ d(db),\ d(dc+b)-db) = (0,0,0)$. Define chain maps

$$i_0(a) = (a,0,0), \qquad i_1(c) = (0,0,c), \qquad p(a,b,c) = a + c$$

Each is compatible with the differentials: $d\,i_0(a) = (da,0,0) = i_0(da)$, similarly for i_1, and $p(d(a,b,c)) = (da-b)+(dc+b) = d(a+c)$. Moreover $pi_0 = \mathrm{id}_C = pi_1$.

Step 2: p is a homotopy equivalence. The composite $i_0 p - \mathrm{id}$ sends (a,b,c) to $(c,-b,-c)$, and setting $s(a,b,c) = (0,-c,0)$ gives

$$ds(a,b,c) = (c,\ dc,\ -c), \qquad sd(a,b,c) = (0,\ -(dc+b),\ 0)$$

whose sum is $(c, -b, -c)$. So $i_0 p \sim \mathrm{id}_{\mathrm{Cyl}(C)}$ while $pi_0 = \mathrm{id}_C$, making i_0 and p mutually inverse homotopy equivalences. The symmetric computation applies to i_1, with the contracting homotopy $s'(a, b, c) = (0, a, 0)$ in place of s, since $i_1 p - \mathrm{id}$ sends (a, b, c) to $(-a, -b, a)$.

Step 3: Homotopies are morphisms out of the cylinder. Let $f, g \colon C^\bullet \to D^\bullet$ with $g - f = ds + sd$. Define $H \colon \mathrm{Cyl}(C) \to D^\bullet$ by $H(a, b, c) = f(a) + s(b) + g(c)$. It is a chain map: expanding both sides, $H(d(a, b, c)) - dH(a, b, c) = (g - f - ds - sd)(b) = 0$. By construction $Hi_0 = f$ and $Hi_1 = g$.

Step 4: Conclusion. Apply $\mathscr{F}$. By Step 2 the morphisms i_0 and i_1 are homotopy equivalences, hence quasi-isomorphisms, so $\mathscr{F}(i_0)$ and $\mathscr{F}(i_1)$ are isomorphisms by hypothesis. From $pi_0 = \mathrm{id} = pi_1$ and functoriality, $\mathscr{F}(p)\mathscr{F}(i_0) = \mathrm{id} = \mathscr{F}(p)\mathscr{F}(i_1)$, and since $\mathscr{F}(i_0)$ is invertible so is $\mathscr{F}(p)$; cancelling it gives $\mathscr{F}(i_0) = \mathscr{F}(p)^{-1} = \mathscr{F}(i_1)$. Therefore

$$\mathscr{F}(f) = \mathscr{F}(Hi_0) = \mathscr{F}(H)\mathscr{F}(i_0) = \mathscr{F}(H)\mathscr{F}(i_1) = \mathscr{F}(Hi_1) = \mathscr{F}(g)$$

so $\mathscr{F}$ identifies homotopic morphisms and factors uniquely through $K(\mathbf{A})$. Note that $\mathscr{F}$ was used only through functoriality and the hypothesis that it inverts quasi-isomorphisms. The direct sums and sums of morphisms above all live in $\mathrm{Ch}(\mathbf{A})$, so no additivity of $\mathscr{F}$ itself is required. This matters in section 57.2, where the functor to be factored is the localization onto $D(\mathbf{A})$, whose additive structure is not available until later. This completes the proof.

Hence, in the case where $K(\mathbf{A})$ is *not* the universal object satisfying equation (56.2), there must be a unique functor from $K(\mathbf{A})$ to $D(\mathbf{A})$.

56.2 Projective and Injective Resolutions

It has been alluded to a few times that for special categories, homotopy equivalence and quasi-isomorphism coincide. This shall now be covered in this section. In particular, this shall linked to the idea of an abelian category $\mathbf{A}$ being bounded from above or bellow, and having *enough projective objects* or *enough injective objects*. These categories shall furthermore be shown to be universal in some appropriate way, making their choice not arbitrary. Recall that in $\mathbf{A} = R\text{-}\mathbf{Mod}$, an R-module M Is called projective if $\mathrm{Hom}_R(M, -)$ is exact, and injective if $\mathrm{Hom}_R(-, M)$ is exact. Recall that projective/injective modules nicely lend themselves to a splitting condition on short exact sequences for which they are one of the modules forming them (recall theorem 17.2.4 and theorem 17.3.4). This will be important, due to the link of chain homotopies with split exact sequences.

Definition 56.2.1: Projective And Injective Objects

Let $\mathbf{A}$ be an abelian category. Then

1. An object $P \in \mathbf{A}$ is said to be *projective* if the functor $\mathrm{Hom}_A(P, -)$ is exact.
2. An object $Q \in \mathbf{A}$ is said to be *injective* if the functor $\mathrm{Hom}_A(-, Q)$ is exact

theorem 17.2.4 and theorem 17.3.4 hold for abelian categories more generally (in particular the splitting remarks), as the reader may venture to check. Since the axioms for an abelian category

are self-dual, so that $\mathbf{A}^{\mathrm{op}}$ is abelian whenever $\mathbf{A}$ is, the theory on projective objects is dual to that of injective object, and the functor $(-)^{\mathrm{op}}$ maps projective/injectives to injectives/projectives respectively. Thus, many proofs shall simply proof the result for projectives, the result for injectives coming automatically. Note that as we have seen in chapter 17⋆ in a fixed [abelian] category $\mathbf{A}$, projective and injective may have very different features.

In what follows, let $\mathbf{P}$ denote the full subcategory of $\mathbf{A}$ determined by the projective objects, and let $\mathbf{I}$ denote the full subcategory of $\mathbf{A}$ determined by the injective objects. Let $K^-(\mathbf{P})$ denote the full subcategory of $K(\mathbf{A})$ consisting of bounded-above complexes of projective objects of $\mathbf{A}$, and $K^+(\mathbf{I})$ be the full subcategory of $K(\mathbf{A})$ consisting of bounded-below complexes of injective objects of $\mathbf{A}$. Note that these are generally not abelian categories, and furthermore projective and injective objects need not exist:

Example 56.2.2: Category With And Without Projective/Injective Resolutions

1. The category of finite abelian groups has no projective or injective, hence no projective/injective resolution.
2. The category of finitely generated abelian groups has projectives, but no injectives, namely since $\mathbb{Z}^n$ for every n are objects this category. Thus, it is possible to create a free, and hence projective, resolution.
3. the dual of the above category has enough injectives but not enough projectives.
4. The category of R-modules has both projective and injective resolutions (projective resolutions comes from free resolutions, while injective resolutions comes from repeated application of theorem 17.3.19)

It is thus helpful to add the following condition to an abelian category

Definition 56.2.3: Enough Projective And Enough Injectives

Let $\mathbf{A}$ be an abelian category. Then:

1. we say that $\mathbf{A}$ as *enough projectives* if for every object A of $\mathbf{A}$, there exists a projective object P of $\mathbf{A}$ and an epimorphism $P \twoheadrightarrow A$.
2. we say that $\mathbf{A}$ as *enough injectives* if for every object A of $\mathbf{A}$, there exists a injective object Q of $\mathbf{A}$ and a monomorphism $A \hookrightarrow Q$.

With the important definitions established, the main objective of this section may start going under way. The goal is to show that if we have a quasi-isomorphism between two bounded-above complexes of projectives $f^\bullet : P_0^\bullet \to P_1^\bullet$ (resp. quasi-isomorphism between two bounded-bellow complexes of injectives $f^\bullet : Q_0^\bullet \to Q_1^\bullet$), then $f^\bullet$ is in fact a homotopy-equivalence, from which it can be concluded that in $K^-(\mathbf{P})$ and $K^+(\mathbf{I})$ (homotopy-classes of) quasi-isomorphisms are isomorphisms, which shall give us the desired derived category $D^-(\mathbf{A})$ and $D^+(\mathbf{A})$ in the case where A has enough projectives (resp. enough injectives).

Let us now revisit this splitting condition. Recall that if $C^\bullet$ in $\mathrm{Ch}(\mathbf{A})$ is exact, then the identity map $\mathrm{id}_{C^\bullet}$ and the trivial map induce the same morphisms in (co)homology. However, there do exist exact complexes that are *not* homotopic to 0. As discussed earlier, this directly links to the splitting

condition, namely the identity is homotopic to 0 if the sequence is split exact. Being projective is exactly the condition that causes splitting behavior. With this in mind, let us prove the first lemma:

Lemma 56.2.4: Zero-morphism In Cohomology And Homotopy

Let $\mathbf{A}$ be an abelian category, $P^\bullet \in \mathrm{Ch}^-(\mathbf{P})$ (i.e. $P^i = 0$ for $i > 0$), and let $C^\bullet$ be a complex in $\mathrm{Ch}(\mathbf{A})$ such that $H^i(C^\bullet) = 0$ for $i < 0$ (i.e. has trivial cohomology in negative coefficients). Let $f^\bullet : P^\bullet \to C^\bullet$ be a morphism of complexes that induces the zero-morphism in cohomology: $H^\bullet(f^\bullet) = 0$. Then

$$f^\bullet \sim 0$$

i.e., $f^\bullet$ is null-homotopic.

The injective version of this statement is comes from dualizing the appropriate terms.

***Proof*:**

To show $f^\bullet$ is null-homotopic, we must show there exists maps $h^i : P^i \to C^{i-1}$ such that

$$f^i = d_{C^\bullet}^{i-1} \circ h^i + h^{i+1} \circ d_{P^\bullet}^i \tag{56.5}$$

as a diagram:

$$\begin{array}{ccccccccccc}
\cdots & \longrightarrow & P^{-2} & \longrightarrow & P^{-1} & \longrightarrow & P^0 & \longrightarrow & 0 & \longrightarrow & \cdots \\
 & \swarrow^{h^{-2}} & \downarrow{\scriptstyle f^{-2}} & \swarrow^{h^{-1}} & \downarrow{\scriptstyle f^{-1}} & \swarrow^{h^0} & \downarrow{\scriptstyle f^0} & \swarrow^{h^1=0} & \downarrow & & \\
\cdots & \longrightarrow & C^{-2} & \longrightarrow & C^{-1} & \longrightarrow & C^0 & \longrightarrow & C^1 & \longrightarrow & \cdots
\end{array}$$

Naturally, $h^i = 0$ for $i > 0$. For the rest, we shall use induction. The base case is $i = 0$. Since the cohomology induced by $f^\bullet$ is zero, f^0 factors through the image of $d_{C^\bullet}^{-1}$:

$$\begin{array}{ccccc}
 & & P^0 & & \\
 & & \downarrow{\scriptstyle f^0} & & \\
C^{-1} & \xrightarrow{d_{C^\bullet}^{-1}} & \mathrm{im} d_{C^\bullet}^{-1} & \longrightarrow & 0
\end{array}$$

Now, since P^0 is projective, there exists a morphism $h^0 : P^0 \to C^{-1}$ such that $f^0 = d_{C^\bullet}^{-1} \circ h^0$, as needed.

Next, assume h^i and h^{i+1} satisfies equation (56.5). The goal is to show h^{i-1} satisfies it too. By equation (56.5) and the fact that $P^\bullet$ is a complex:

$$d_{C^\bullet}^{i-2} \circ h^i \circ d_{P^\bullet}^{i-1} = (f^i - h^{i+1} \circ d_{P^\bullet}^{i-1}) = f^i \circ d_{P^\bullet}^{i-1} - h^{i+1} \circ 0 = f^i \circ d_{P^\bullet}^{i-1}$$

which can be seen by staring at the following diagram:

$$\begin{array}{ccccccccc}
\cdots & \cdots\cdots\rightarrow & P^{i-1} & \xrightarrow{d_{P^\bullet}^{i-1}} & P^i & \xrightarrow{d_{P^\bullet}^i} & P^{i+1} & \cdots\cdots\rightarrow & \\
 & & \vdots & \swarrow^{h^i} & \downarrow{\scriptstyle f^i} & \swarrow^{h^{i+1}} & \vdots & & \\
\cdots & \cdots\cdots\rightarrow & C^{i-1} & \xrightarrow[d_{C^\bullet}^{i-1}]{} & C^i & \cdots\cdots\rightarrow & C^{i+1} & \cdots\cdots\rightarrow &
\end{array}$$

Thus, since f^b is a morphism of cochain complexes:

$$d_{C^\bullet}^{i-1} \circ (f^{i-1} - h^i \circ d_{P^\bullet}^{i-1}) = d_{C^\bullet}^{i-1} \circ f^{i-1} - f^i \circ d_{P^\bullet}^{i-1} = 0$$

Importantly, $(f^{i-1} - h^i \circ d_{P^\bullet}^{i-1})$ factors through $\ker d_{C^\bullet}^{i-1}$. Since $C^\bullet$ is exact at C^{i-1} for $i \leq 0$, $\ker d_{C^\bullet} = \mathrm{im}_{C^\bullet}^{i-2}$. Thus, we get:

$$\begin{array}{ccccc} & & P^{i-1} & & \\ & & \downarrow{\scriptstyle f^{i-1} - h^i \circ d_{P^\bullet}^{i-1}} & & \\ C^{i-2} & \xrightarrow{d_{C^\bullet}^{i-2}} & \mathrm{im}(d_{C^\bullet}^{i-2}) & \longrightarrow & 0 \end{array}$$

Now, since P^{i-1} is projective, there exists a lift $h^{i-1} : P^{i-1} \to C^{i-2}$ such that

$$f^{i-1} - h^i \circ d_{P^\bullet}^{i-1} = d_{C^\bullet}^{i-2} \circ h^{i-1}$$

which, shuffling around, gives us

$$f^{i-1} = d_{C^\bullet}^{i-2} \circ h^{i-1} + h^i \circ d_{P^\bullet}^{i-1}$$

as we sought to show.

Corollary 56.2.5: Exactness Cohomology And Homotopy

Let $\mathbf{A}$ be an abelian category, $P^\bullet \in \mathrm{Ch}^-(\mathbf{P})$ a bounded-above complex of projectives, and $C^\bullet \in \mathrm{Ch}(\mathbf{A})$ an exact complex. Then every morphism $P^\bullet \to C^\bullet$ is homotopic to 0.

***Proof*:**
Every morphism to an exact complex induces the zero morphism in cohomology. After a translation of degrees, which changes neither the hypotheses nor the conclusion, $P^i = 0$ for $i > 0$, and $H^i(C^\bullet) = 0$ for every i, so lemma 56.2.4 applies, completing the proof.

Note the importance of the bounding from above/bellow (depending on whether working with projectives or injective) in the inductive argument, without it there would not be an appropriate base case. Using the above results, the first quasi-isomorphism to homotopy equivalence can be established:

Corollary 56.2.6: Projectives With Quasi-isomorphism And Zero Morphisms

Let $P^\bullet$ (resp. $Q^\bullet$) be a bounded-above exact complex of projectives (resp. a bounded bellow exact complex of injectives). Then $P^\bullet$ (resp. $Q^b b$) is homotopy-equivalent to the zero-complex.

***Proof*:**
Treat the projective case; the injective one is the same argument in the opposite category. A complex is homotopy equivalent to the zero complex exactly when its identity morphism is null-homotopic, since a homotopy inverse to the zero complex forces $\mathrm{id} \sim 0$ and conversely. By lemma 56.1.28 it therefore suffices to show that $P^\bullet$ is split exact.

Write $Z^n = \ker d^n$ and $B^n = \mathrm{im} d^{n-1}$; exactness gives $Z^n = B^n$, so for every n there is a short exact sequence

$$0 \to B^n \to P^n \to B^{n+1} \to 0$$

Since $P^\bullet$ is bounded above there is an N with $P^n = 0$ for $n > N$, whence $B^n = 0$ for $n > N+1$.

Argue by descending induction that each B^n is projective. For $n > N+1$ it is zero. Suppose B^{n+1} is projective. Then the displayed short exact sequence splits, because a surjection onto a projective object admits a section, so $P^n \cong B^n \oplus B^{n+1}$ and B^n is a direct summand of the projective object P^n, hence projective itself.

Every one of the short exact sequences therefore splits. Choosing a section $\sigma^{n+1} \colon B^{n+1} \to P^n$ of d^n for each n and letting $s^{n+1} \colon P^{n+1} \to P^n$ be σ^{n+1} composed with the projection $P^{n+1} \twoheadrightarrow B^{n+1}$ gives $dsd = d$, since $d^n \sigma^{n+1}$ is the identity on B^{n+1} and d factors through B^{n+1}. So $P^\bullet$ is split exact, and lemma 56.1.28 makes $\mathrm{id}_{P^\bullet}$ null-homotopic, completing the proof.

Another important result that will be used in the next section is that quasi-isomorphisms are "non-zero-divisors" up to homotopy wrt morphisms from commplexes of projectives:

Lemma 56.2.7: Quasi-isomorphisms Of Projectives And Zero-divisor

Let $\mathbf{A}$ be an abelian category, $f^\bullet : C^\bullet \to D^\bullet$ be a quasi-isomorphism. Let $P^\bullet$ be a bounded-above complex of projectives, and let $\alpha^\bullet : P^\bullet \to C^\bullet$ be a morphism of cochain complexes such that the composition:

$$P^\bullet \xrightarrow{\alpha^\bullet} C^\bullet \xrightarrow{f^\bullet} D^\bullet$$

is homotopic to the zero-morphism. Then $\alpha^\bullet \sim 0$

***Proof*:**
Let $h^i : P^i \to D^{i-1}$ define the homotopy between $f^\bullet \circ \alpha^\bullet$ and 0, namely:

$$-f^i \circ \alpha^i = d^{i-1}_{C^\bullet} \circ h^i + h^{i+1} \circ d^i_{P^\bullet}$$

Take the mapping cone $MC(f)^\bullet$ of $f^\bullet$ and define the morphisms:

$$\beta^i = (\alpha^, h^i) : P^i \to MC(f)^{i-1}$$

which may be visualized in the following diagram:

$$\begin{array}{ccccccccc}
\cdots & \longrightarrow & P^{i-1} & \xrightarrow{d^{i-1}_{P^\bullet}} & P^i & \xrightarrow{d^i_{P^\bullet}} & P^{i+1} & \longrightarrow & \\
 & & \downarrow{\scriptstyle \beta^{i-1}} & & \downarrow{\scriptstyle \beta^i} & & \downarrow{\scriptstyle \beta^{i+1}} & & \\
\cdots & \longrightarrow & C^{i-1} \oplus D^{i-2} & \xrightarrow[d^{i-2}_{MC(f)^\bullet}]{} & C^i \oplus D^{i-1} & \xrightarrow[d^{i-1}_{MC(f)^\bullet}]{} & C^{i+1} \oplus D^i & \longrightarrow &
\end{array}$$

These give a morphism of cochain complexes $P^\bullet \to MC(f)[-1]^\bullet$. Indeed:

$$\beta^{i+1} \circ d^i_{P^\bullet} = (\alpha^{i+1} \circ d^i_{P^\bullet}, h^{i+1} \circ d^i_{P^\bullet})$$
$$-d^{i-1}_{MC(f)} \circ \beta^i = (d^i_{C^\bullet} \circ \alpha^i, -f^i \circ \alpha^i - d^{i-1}_{M^\bullet} \circ h^i)$$

Then by definition of h^i and by the morphism property of $\alpha^\bullet$, these are equal. Now, by hypothesis, $f^\bullet$ is a quasi-isomorphism. Then by proposition 56.1.26 $MC(f)^\bullet$ is an exact complex. Then by corollary 56.2.6 $\beta^\bullet$ is homotopic to 0. Since $\alpha^\bullet$ is the composition:

$$P^\bullet \xrightarrow{\beta^\bullet} MC(f)[-1]^\bullet = L^\bullet \oplus M[-1]^\bullet \to L^\bullet$$

it follows that $\beta^\bullet \sim 0$ implies $\alpha^\bullet \sim 0$, as we sought to show.

Though $\alpha^\bullet$ must be homotopic to 0, it need not be the case that $\alpha^\bullet = 0$. Take for example:

$$\begin{array}{ccccccccccc}
\cdots & \longrightarrow & 0 & \longrightarrow & \mathbb{Z} & \longrightarrow & \mathbb{Z} & \longrightarrow & 0 & \longrightarrow & \cdots \\
 & & \downarrow & & \downarrow{\scriptstyle \mathrm{id}} & & \downarrow{\scriptstyle \cdot 2} & & \downarrow & & \\
\cdots & \longrightarrow & 0 & \longrightarrow & \mathbb{Z} & \xrightarrow{\cdot 2} & \mathbb{Z} & \longrightarrow & 0 & \longrightarrow & \cdots \\
 & & \downarrow & & \downarrow & & \downarrow{\scriptstyle \pi} & & \downarrow & & \\
\cdots & \longrightarrow & 0 & \longrightarrow & 0 & \longrightarrow & \mathbb{Z}/2\mathbb{Z} & \longrightarrow & 0 & \longrightarrow & \cdots
\end{array}$$

In this case, $f^\bullet$ is a quasi-isomorphism and $f^\bullet \circ \alpha^\bullet = 0$, and so $\alpha^\bullet \sim 0$, even though it is not equal to 0. With this, one more result is required before the desired goal:

Proposition 56.2.8: projectives, and one-sided inverses

Let $\mathbf{A}$ be an abelian category, $C^\bullet \in \mathrm{Ch}(\mathbf{A})$, $P^\bullet \in \mathrm{Ch}^-(\mathbf{P})$, and $f^\bullet : C^\bullet \to P^\bullet$ a quasi-isomorphism. Then there exists a morphism of complexes $g^\bullet : P^\bullet \to C^\bullet$ such that:

$$f^\bullet \circ g^\bullet \sim \mathrm{id}_{P^\bullet}$$

For injective, $Q^\bullet \in \mathrm{Ch}^+(\mathbf{I})$, $f^\bullet : Q^\bullet \to C^\bullet$ is a quasi-isomorphism, for which then there exists a morphism $g^\bullet : C^\bullet \to Q^\bullet$ such that $g^\bullet \circ f^\bullet \sim \mathrm{id}_{Q^\bullet}$. Notice that this is a one-sided inverse, hence is a slightly more general result than what is being built up to.

***Proof*:**
Since $f^\bullet : C^\bullet \to P^\bullet$ is a quasi-isomorphism, $MC(f)^\bullet = C[1]^\bullet \oplus P^\bullet$ is an exact complex. Define $\rho^\bullet = (0, \mathrm{id}_{P^\bullet})$ to be the morphism:

$$\rho^\bullet : P^\bullet \to MC(f)^\bullet$$


By corollary 56.2.5, since $MC(f)^\bullet$ is exact, $\rho^\bullet$ is homotopic to the zero morphism. Thus, there exists morphisms:

$$\widehat{h}^i : P^i \to MC(f)^{i-1} = C^i \oplus P^{i-1}$$

such that

$$\rho^i = d^{i-1}_{MC(f)^\bullet} \circ \widehat{h}^i + \widehat{h}^{i+1} \circ d^i_{P^\bullet}$$

Visually, we may see this as:



Now, write out $\widehat{h}^i$ out in components so that $\widehat{h}^i = (g^i, h^i)$ where $g^i : P^i \to C^i$ and $h^i : P^i \to P^{i-1}$. We will show that the collection $\{g^i\}_{i\in\mathbb{Z}}$ is a morphism of cochain complexes (i.e. they form commutative squares $g^{i+1} \circ d^i_{P^\bullet} = d^i_{C^\bullet} \circ g^i$) such that $f^\bullet \circ g^\bullet \sim \mathrm{id}_{P^\bullet}$. Indeed, since

$$\begin{aligned}(0, \mathrm{id}_{P^i}) &= \rho^i \\ &= d^{i-1}_{MC(f)^\bullet} \circ \widehat{h}^i + \widehat{h}^{i+1} \circ d^i_{P^\bullet} \\ &= (d_{MC}(f)^\bullet)^{i-1} \circ (g^i, h^i) + (g^{i+1}, h^{i+1}) \circ d^i_{P^\bullet} \\ &= (-d^i_{C^\bullet} \circ g^i, f^i \circ g^i + d^{i-1}_{P^\bullet} \circ h^i) + (g^{i+1} \circ d^i_{P^\bullet}, h^{i+1} \circ d^i_{P^\bullet})\end{aligned}$$

It follows that:

$$\begin{aligned}g^{i+1} \circ d^i_{P^\bullet} - d^i_{C^\bullet} \circ g^i &= 0 \\ \mathrm{id}_{P^i} - f^i \circ g^i &= d^{i-1}_{P^\bullet} \circ h^i + h^{i+1} \circ d^i_{P^\bullet}\end{aligned}$$

which is exactly what we need, hence the morphism of complexes $g^\bullet : P^\bullet - > C^\bullet$ is the needed homotopy right-inverse of $f^\bullet$, as we sought to show.

With this, we can finally prove the desired result:

Theorem 56.2.9: Projective, Quasi-isomorphism Becomes Homotopy

Let $\mathbf{A}$ be an abelian category, and let $\alpha^\bullet : P^\bullet_0 - > P^\bullet_1$ be a quasi-isomorphism between bounded-above complexes of projectives (resp. quasi-isomorphism between two bounded-bellow complexes of injectives $f^\bullet : Q^\bullet_0 \to Q^\bullet_1$). Then $\alpha^b b$ is a homotopy-equivalence.

***Proof*:**
The argument for projectives shall be given, the injective argument following by appropriate dualizing. By proposition 56.2.8, since $P^\bullet_1$ is in $C^-(\mathbf{P})$ and $\alpha^\bullet : P^\bullet_0 \to P^\bullet_1$ is a quasi-isomorphism, there exists a morphism of complexes $\beta^\bullet : P^\bullet_1 \to p^\bullet_0$ such that

$$\alpha^\bullet \circ \beta^\bullet \sim \mathrm{id}^\bullet_{P_1}$$

Then by proposition 56.1.31, $H^\bullet(\alpha^\bullet) \circ H^\bullet(\beta^\bullet) = \mathrm{id}$. Since $H^\bullet(\alpha^\bullet)$ is invertible, so is $H^\bullet(\beta^\bullet)$, and so $\beta^\bullet$ must be a quasi-isomorphism. Since $P^\bullet_0$ is also in $\mathrm{Ch}^-(\mathbf{P})$, we have that there exists a morphism $(\alpha^\bullet)' : P^\bullet_0 \to P^\bullet_1$ such that $\beta^\bullet \circ (\alpha^\bullet)' \sim \mathrm{id}_{P^\bullet_0}$. Since:

$$(\alpha^\bullet)' \sim (\alpha^\bullet \circ \beta^\bullet) \circ (\alpha^\bullet)' = \alpha^\bullet(\beta^\bullet \circ (\alpha^\bullet)') \sim \alpha^\bullet$$

it follows that $\beta^\bullet \sim \alpha^\bullet \sim_{P^\bullet_0}$ (exercise 4.6 in Aluffi). Thus, $\alpha^\bullet$ is indeed a homotopy equivalence, as we sought to show.

Corollary 56.2.10: Projective In Homotopy Category

In $K^-(\mathbf{P})$ and $K^+(\mathbf{I})$, (homotopy classes of) quasi-isomorphissm are isomorphisms.

***Proof*:**
follows immediately form theorem 56.2.9.

56.2.1 Resolutions

With the important equivalence between quasi-isomorphisms and homotopy-equivalence established in the case of complexes of projective (resp. projective) objects, we turn back our attention to the question of finding (co)homological invariants, focusing on categories with enough projective s(resp. Injectives). In particular, given an object A in an abelian category $\mathbf{A}$, it wouldb e desirable to associate to it a (co)chain of projective (resp. injective) objects in some universal way (up to homotopy) from which information can be extracted.

Let us first refine the definition of projective/injective resolutions of an object. Recall that there i a copy of $\mathbf{A}$ in $\mathrm{Ch}(\mathbf{A})$ given by mapping $A \mapsto \iota(A)$.

Definition 56.2.11: Projective And Injective Resolution

Let $A \in \mathrm{Obj}(\mathbf{A})$ be an object in an abelian category A. Then:


1. A *resolution* of A is a quasi-isomorphism $C^\bullet \to \iota(A)$ for some complex $C^\bullet \in \mathrm{Obj}(\mathrm{Ch}(\mathbf{A}))$.
2. A *projective resolution* of A is a quasi-isomorphism $P^\bullet \to \iota(A)$ where $P^\bullet$ is a complex in $\mathrm{Ch}^{\leq 0}(\mathbf{P})$
3. An *injective resolution* of A is a quasi-isomorphism $\iota(A) \to Q^\bullet$ where $Q^\bullet$ is a complex in $\mathrm{Ch}^{\geq 0}(\mathbf{I})$

Often, $P^\bullet$ and $Q^\bullet$ shall be referred to as the projective resolution and injective resolution respectively, omitting the quasi-isomorphism.

56.2.12 Remark There is a point of confusion that may arise. It may seem that the resolutions *themselves* are projective/injective objects in the abelian category $\mathrm{Ch}(\mathbf{A})$. However, this is not the case: a projective object of $\mathrm{Ch}(\mathbf{A})$ must be a complex of projectives that is moreover split exact in the relevant range, which a resolution is not.

Recall further that any resolution $C^\bullet$ will be exact everywhere except possibly at C^0 (exercise, or double-check example 56.1.16). Hence, the non-trivial cohomological information lies in $H^0(C^\bullet)$. Let us now focus on resolutions for a particular object A: consider the category of homotopy classes of quasi-isomorphisms with *target* $\iota(A)$. Then we shall show that, if they exist, projective resolution are

initial in this category.



Analogously, injective resolutions are final in homotopic category of quasi-isomorphisms with *source* $\iota(A)$. Given this universal property, this means that each projective resolution maps uniquely (in $K(\mathbf{A})$) to *every* resolution of A. The following lemma proves this:

Lemma 56.2.13: Projective Resolution As Initial Objects

Let $A \in \mathbf{A}$, let $C^\bullet$ be a resolution of A (so that $C^i = 0$ for $i > 0$, $H^i(C^\bullet) = 0$ for $i < 0$, and $H^0(C^\bullet) = A$), and let $P^\bullet \in \mathrm{Ch}^{\leq 0}(\mathbf{P})$ be a bounded-above complex of projectives. Then any morphism

$$\varphi : H^0(P^\bullet) \to H^0(C^\bullet) \; [= A]$$

is induced by a morphism of complexes $\varphi^\bullet : P^\bullet \to C^\bullet$, and any two such $\varphi^\bullet$ are homotopic.

***Proof*:**

Since both complexes vanish in positive degrees, $H^0(P^\bullet) = \mathrm{coker} d_P^{-1}$ and $H^0(C^\bullet) = \mathrm{coker} d_C^{-1}$; write $\pi_P \colon P^0 \twoheadrightarrow H^0(P^\bullet)$ and $\pi_C \colon C^0 \twoheadrightarrow A$ for the two quotient maps.

Step 1: Degree 0. The composite $\varphi \circ \pi_P \colon P^0 \to A$ is a morphism out of a projective object, and π_C is an epimorphism, so by definition 56.2.1 it lifts: there is $\varphi^0 \colon P^0 \to C^0$ with $\pi_C \circ \varphi^0 = \varphi \circ \pi_P$.

Step 2: Degree -1. Compute

$$\pi_C \circ \varphi^0 \circ d_P^{-1} = \varphi \circ \pi_P \circ d_P^{-1} = 0$$

since $\pi_P \circ d_P^{-1} = 0$. Hence $\varphi^0 \circ d_P^{-1}$ factors through $\ker \pi_C = \mathrm{im} d_C^{-1}$. As P^{-1} is projective and d_C^{-1} is an epimorphism onto its image, the map $P^{-1} \to \mathrm{im} d_C^{-1}$ lifts to $\varphi^{-1} \colon P^{-1} \to C^{-1}$ with $d_C^{-1} \circ \varphi^{-1} = \varphi^0 \circ d_P^{-1}$.

Step 3: The induction. Suppose φ^{-i} has been constructed for $i < n$ with every square commuting. Then

$$d_C^{-n+1} \circ \left(\varphi^{-n+1} \circ d_P^{-n}\right) = \varphi^{-n+2} \circ d_P^{-n+1} \circ d_P^{-n} = 0$$

so $\varphi^{-n+1} \circ d_P^{-n}$ lands in $\ker d_C^{-n+1}$, which for $n \geq 2$ equals $\mathrm{im} d_C^{-n}$ because $C^\bullet$ is exact in degree $-n+1 < 0$; the case $n = 1$ is Step 2, where $\ker \pi_C$ plays that role. Projectivity of P^{-n} again lifts it along the epimorphism $C^{-n} \twoheadrightarrow \mathrm{im} d_C^{-n}$, producing φ^{-n} with $d_C^{-n} \circ \varphi^{-n} = \varphi^{-n+1} \circ d_P^{-n}$. This constructs $\varphi^\bullet$ in every degree, and Step 1 arranges that it induces φ on H^0.

Step 4: Uniqueness up to homotopy. Let $\varphi^\bullet$ and $\psi^\bullet$ both induce φ, and set $f^\bullet = \varphi^\bullet - \psi^\bullet$. On H^0 it induces $\varphi - \varphi = 0$, and in every negative degree $H^i(C^\bullet) = 0$, so $H^i(f^\bullet) = 0$ there as well; in positive degrees both complexes vanish. Hence $H^\bullet(f^\bullet) = 0$. The hypotheses of lemma 56.2.4 are met, $P^\bullet$ being a bounded-above complex of projectives and $C^\bullet$ having vanishing cohomology in negative degrees, so $f^\bullet \sim 0$, that is $\varphi^\bullet \sim \psi^\bullet$, completing the proof.

Since these are initial (resp. final) objects in the category, we have a unique isomorphism beetween any two solutions to the universal problem. In this case, this may be stated as followed:

Proposition 56.2.14: Unique Projection Resolution

Let $\mathbf{A}$ be an abelian category. Then any two projective (resp. injective) resolutions of an object A in $\mathbf{A}$ are homotopy equivalent

***Proof*:**
Let $P^\bullet$ and $Q^\bullet$ be two projective resolutions of A, so that each is a bounded-above complex of projectives with $H^0 = A$. Apply lemma 56.2.13 twice to the morphism id_A: once with source $P^\bullet$ and target $Q^\bullet$, giving $f^\bullet\colon P^\bullet \to Q^\bullet$, and once the other way, giving $g^\bullet\colon Q^\bullet \to P^\bullet$. Each is unique up to homotopy.

The composite $g^\bullet \circ f^\bullet\colon P^\bullet \to P^\bullet$ induces id_A on H^0, and so does $\mathrm{id}_{P^\bullet}$. Both are therefore lifts of the same morphism id_A, and the uniqueness clause of lemma 56.2.13 gives $g^\bullet \circ f^\bullet \sim \mathrm{id}_{P^\bullet}$. Symmetrically $f^\bullet \circ g^\bullet \sim \mathrm{id}_{Q^\bullet}$. Hence $f^\bullet$ is a homotopy equivalence with homotopy inverse $g^\bullet$, as we sought to show. The injective case is dual.

A final important observation is that this lift is functorial!

Proposition 56.2.15: Projective Resolution Functoriality

Let $\mathbf{A}$ be an abelian category, and let A_0, A_1 be objects of $\mathbf{A}$. Let $P_0^\bullet$ and $P_1^\bullet$ be projective resolutions for A_0 and A_1 respectively. Then every morphism $\varphi : A_0 \to A_1$ in $\mathbf{A}$ induces a morphism $\alpha^\bullet : P_0^\bullet \to P_1^\bullet$ that is unique up to homotopy

***Proof*:**
Notice that φ can be interpreted as a morphism $\varphi : H^0(P_0^\bullet) \to H^0(P_1^\bullet)$. The complex $P_0^\bullet$ consists of projectives, and $P1^\bullet$ is a resolution of A_1. Thus, by lemma 56.2.13, there exists a list α^b that is unique up to homotopy, as we sought to show.

Corollary 56.2.16: Full Subcategory Of Homotopic Category

Let $\mathbf{A}$ be an abelian category with enough projectives (resp. enough injectives). Then $\mathbf{A}$ is equivalent to a full subcategory of $K^-(\mathbf{P})$ (resp. $K^+(\mathbf{I})$).

***Proof*:**
Treat the projective case. Choose for each object A of $\mathbf{A}$ a projective resolution $P_A^\bullet$, possible because $\mathbf{A}$ has enough projectives, and send $A \mapsto P_A^\bullet$. By proposition 56.2.15 every $\varphi\colon A_0 \to A_1$ lifts to a morphism of resolutions, well defined up to homotopy, so this is a functor $R\colon \mathbf{A} \to K^-(\mathbf{P})$: composites and identities are preserved because a lift of a composite and the composite of lifts both lift the same morphism and so agree up to homotopy, which is equality in $K^-(\mathbf{P})$.

R is faithful. If $R(\varphi) = 0$ then a lift $\varphi^\bullet$ of φ is null-homotopic, so it induces the zero morphism on

cohomology by proposition 56.1.29. Since $H^0(\varphi^\bullet) = \varphi$ under the identifications $H^0(P^\bullet_{A_i}) = A_i$, this gives $\varphi = 0$.

R is full. Let $f^\bullet \colon P^\bullet_{A_0} \to P^\bullet_{A_1}$ be any morphism in $K^-(\mathbf{P})$, represented by a chain map. It induces $\varphi := H^0(f^\bullet) \colon A_0 \to A_1$, and $f^\bullet$ is then a lift of φ. By the uniqueness clause of lemma 56.2.13 any two lifts of φ are homotopic, so $R(\varphi) = [f^\bullet] = f^\bullet$ in $K^-(\mathbf{P})$.

A fully faithful functor is an equivalence onto its essential image, which is a full subcategory of $K^-(\mathbf{P})$. Hence $\mathbf{A}$ is equivalent to a full subcategory of $K^-(\mathbf{P})$, and dually to one of $K^+(\mathbf{I})$ when $\mathbf{A}$ has enough injectives, completing the proof.

56.2.2 Derived Category with Enough Projectives

Let us finally confirm that the solution to the universal problem in equation 56.2. Recall that the derived category is a category $D(\mathbf{A})$ where for any category D for which there exists an additive functor $\mathscr{F} : \mathrm{Ch}(\mathbf{A}) \to D$ where every quasi-isomorphism in $\mathrm{Ch}(\mathbf{A})$ becomes an isomorphism in D, there exists a unique functor such that the following diagram commutes:

$$\begin{array}{ccc} \mathrm{Ch}(\mathbf{A}) & \xrightarrow{\mathscr{F}} & D \\ \downarrow & \nearrow_{\exists!} & \\ D(\mathbf{A}) & & \end{array}$$

In the case where $\mathbf{A}$ has enough projectives (resp. enough injectives) and is bounded from above (resp. from bellow), then $K^-(\mathbf{P})$ (resp. $K^+(\mathbf{I})$) is the solution to the above universal problem. In particular, there is an equivalence of categories between $K^-(\mathbf{P})$ and $D^-(\mathbf{A})$. The formal definition of the derived category shall be given in section 57.2, hence this equivalence shall not be proven, however the universal property is readily provable, and once the derived category is formally defined it will be the equivalence essentially come to proper manipulation of universal properties.

To start, a general procedure for finding projective/injective resolutions for any (co)chain must be explored. The discussion so far has been for projective/injective resolution, that is quasi-isomorphisms $P^\bullet \to \iota(A)$ or $\iota(A) \to Q^\bullet$. Is it possible to replace $\iota(A)$ with any bounded complex? The answer is yes, though rather technical. The importance of this will be the existence of a functor p that maps $\mathrm{Ch}^-(\mathbf{P})$ into $K^-(\mathbf{P})$, which shall be important for solving the universal problem above, as well as finding functors between derived categories. Such functors shall also be key in solving the "extension problem" that was mentioned all the way back in chapter 17⋆.

Theorem 56.2.17: Resolution And Complexes

Let $\mathbf{A}$ be an abelian category with enough projectives and $C^\bullet$ a complex in $C^-(\mathbf{A})$. Then there exists a bounded-above complex of projective $P^\bullet$ and a quasi-isomorphism $P^\bullet \to C^\bullet$, where $P^\bullet$ is uniquely defined up to homotopy equivalence. Furthermore, every morphism $\alpha^\bullet$ of complexes in $C^-(\mathbf{A})$ lifts to a morphism of the corresponding projective resolutions in $K^-(\mathbf{P})$, which is uniquely defined up to homotopy.

***Proof Key ideas*:**
The uniqueness and lifting halves are already available; only the existence half needs a construction, and that construction is a descending induction whose bookkeeping is long without being conceptually informative, so it is given in outline here and in full in *An Introduction to Homological Algebra* [101].

Existence. Let $C^\bullet$ be bounded above, say $C^n = 0$ for $n > N$. Build P^n by descending induction on n, starting with $P^n = 0$ for $n > N$. At each stage one has already constructed the terms above degree n together with the maps to $C^\bullet$, and one chooses a projective object surjecting onto the pullback of C^n against the cycles constructed one degree up. That single choice simultaneously arranges surjectivity on cohomology in degree n and injectivity in degree $n+1$, which is what makes the resulting map a quasi-isomorphism; enough projectives is exactly what gives the surjection at each stage.

Uniqueness up to homotopy equivalence. Two such projective complexes over $C^\bullet$ are homotopy equivalent by the argument of proposition 56.2.14, with its object-level input lemma 56.2.13 replaced by the lifting of morphisms in the next paragraph, whose existence comes from corollary 56.2.5 and whose uniqueness up to homotopy comes from lemma 56.2.7. Applied to $\mathrm{id}_{C^\bullet}$, it gives a map each way over $C^\bullet$, and both composites lift the identity, hence are homotopic to it by that uniqueness.

Lifting of morphisms. Given $\alpha^\bullet \colon C^\bullet \to D^\bullet$ and projective complexes $P^\bullet \to C^\bullet$, $Q^\bullet \to D^\bullet$, the composite $P^\bullet \to C^\bullet \to D^\bullet$ is a morphism from a bounded-above complex of projectives into a complex quasi-isomorphic to $Q^\bullet$. Existence of a factorization through $Q^\bullet$ comes from corollary 56.2.5, applied to the cone of $Q^\bullet \to D^\bullet$, and its uniqueness up to homotopy from the cancellation property lemma 56.2.7. Together they give a well-defined morphism in $K^-(\mathbf{P})$.

Thus, given an abelian category $\mathbf{A}$ with enough projective, there is a functor

$$\mathscr{P} : C^-(\mathbf{A}) \to K^-(\mathbf{P})$$

associating each (bounded-above) complex $C^\bullet$ to a projective resolution $\mathscr{P}(C^\bullet)$ in a functorial manner (so that morphisms $f^\bullet$, $g^\bullet$ are lifted and $\mathscr{P}(g^\bullet \circ f^\bullet) = \mathscr{P}(g^\bullet) \circ \mathscr{P}(f^\bullet)$ since both sides are classes of homotopy lifts of $g^\bullet \circ f^\bullet$). The uniqueness of $\mathscr{P}$ is up to natural transformation, that is if another functor $\mathscr{P}'$ is chosen that assigns a different choice of projective resolution, then by theorem 56.2.17 there is a homotopy equivalence between $\mathscr{P}(C^\bullet)$ and $\mathscr{P}'(C^\bullet)$, hence an isomorphism $\varphi_{C^\bullet} : \mathscr{P}(C^\bullet) \to \mathscr{P}'(C^\bullet)$ in $K^-(\mathbf{P})$. Since the identity on $C^\bullet$ lifts to a unique map up to homotopy, the isomorphism $\varphi_{C^\bullet}$ is unique. Furthermore, given a morphism $f^\bullet : C^\bullet \to D^\bullet$, the diagram:

$$\begin{array}{ccc} \mathscr{P}(C^\bullet) & \xrightarrow{\mathscr{P}(f^\bullet)} & \mathscr{P}(D^\bullet) \\ {\scriptstyle \varphi_{C^\bullet}}\downarrow{\scriptstyle \sim} & & {\scriptstyle \sim}\downarrow{\scriptstyle \varphi_{D^\bullet}} \\ \mathscr{P}'(C^\bullet) & \xrightarrow[\mathscr{P}'(f^\bullet)]{} & \mathscr{P}'(D^\bullet) \end{array}$$

commutes (again by the uniqueness of lifts up to homotopy, can you see why)? Thus, we have the unique natural isomorphism for any two choices of functors giving a projective resolution.

Theorem 56.2.18: Universal Property Of Derived Category With Enough Projectives

Let $\mathbf{A}$ be an abelian category with enough projectives, and $\mathscr{P}$ a functor sending bounded-above cochains to projective resolutions. Then:

1. If $f^\bullet$ is a quasi-isomorphism in $C^-(\mathbf{A})$, then $\mathscr{P}(f^\bullet)$ is an isomorphism in $K^-(\mathbf{P})$
2. If $\mathscr{F} : C^-(\mathbf{A}) \to D$ is an additive functor that takes quasi-isomorphisms to isomorphisms, then there exists a unique functor $\widetilde{\mathscr{F}} : K^-(\mathbf{P}) \to D$ unique up to natural isomorphism such that the following diagram commutes up to natural isomorphism:

$$\begin{array}{ccc} C^-(\mathbf{A}) & \xrightarrow{\mathscr{F}} & D \\ {\scriptstyle \mathscr{P}}\downarrow & \nearrow_{\widetilde{\mathscr{F}}} & \\ K^-(\mathbf{P}) & & \end{array}$$

where commuting up to natural transformation means there exists a natural transformation $\nu : \widetilde{\mathscr{F}} \circ \mathscr{P} \rightsquigarrow \mathscr{F}$ such that:

$$\nu_{C^\bullet} : \widetilde{\mathscr{F}} \circ \mathscr{P}(C^\bullet) \xrightarrow{\sim} \mathscr{F}(C^\bullet)$$

is an isomorphism for every complex $C^\bullet$ in $C^-(\mathbf{A})$.

The fact that the commutative diagram commutes up to natural isomorphism reflects that the homotopic category is categorically equivalent to the derived category. If $\mathbf{A}$ has enough injective, then we may instead define the functor $\mathscr{I} : C^+(\mathbf{A}) \to K^+(\mathbf{I})$ that shall satisfy the dual universal property.

***Proof*:**

1. Let $f^\bullet : C^\bullet \to D^\bullet$ be any morphism in $C^-(\mathbf{A})$. By theorem 56.2.17, $f^\bullet$ lifts to a morphism of resolutions which commutes up to homotopy in the following diagram:

$$\begin{array}{ccc} \mathscr{P}(C^\bullet) & \xrightarrow{\mathscr{P}(f^\bullet)} & \mathscr{P}(C^\bullet) \\ {\scriptstyle \mu_{C^\bullet}}\downarrow & & \downarrow{\scriptstyle \mu_{D^\bullet}} \\ C^\bullet & \xrightarrow{f^\bullet} & D^\bullet \end{array}$$

where $\mu_{C^\bullet}, \mu_{D^\bullet}$ are the quasi-isomorphisms of the projective resolutions. Since the diagram commute up to homootpy, it commutes after taking cohomology, thus since $f^\bullet$ is a quasi-isomorphism, so is $\mathscr{P}(f^\bullet)$. Then by corollary 56.2.10, $\mathscr{P}(f^\bullet)$ is an isomorphism.

2. Define $\widetilde{\mathscr{F}} : K^-(\mathbf{P}) \to D$ via:

$$\widetilde{\mathscr{F}}(P^\bullet) := \mathscr{F}(P^\bullet) \qquad \widetilde{\mathscr{F}}(f^\bullet) := \mathscr{F}(f^\bullet)$$

where $\widetilde{\mathscr{F}}(f^\bullet)$ can be any representative of $f^\bullet$. This map is well-defined, since homotopic morphisms have the same image in D (lemma 56.1.37). Naturally, $\widetilde{\mathscr{F}}$ is a functor. We

need to check the commutativity up to morphism of the diagram and the uniqueness of $\widetilde{\mathscr{F}}$ up to natural isomorphism.

First, let $C^\bullet \in C^-(\mathbf{A})$. Then (by construction of $\mathscr{P}$, there exists a quasi-isomorphism

$$\mu_{C^\bullet} : \mathscr{P}(C^\bullet) \to C^\bullet$$

Since $\mathscr{F}$ maps quasi-isomorphisms to isomorphism, the induced morphism $\nu_{C^\bullet} := \mathscr{F}(\mu_{C^\bullet})$:

$$\nu_{C^\bullet} : \widetilde{\mathscr{F}}(\mathscr{P}(C^\bullet)) = \mathscr{F}(\mathscr{P}(C^\bullet)) \to \mathscr{F}(C^\bullet)$$

is an isomorphism. What's left to check is that $\nu_{C^\bullet}$ defines a natural transformation. Let $f^\bullet : C^\bullet \to D^\bullet$ in $C^-(\mathbf{A})$. We want to show the following diagram commutes:

$$\begin{array}{ccc} \widetilde{\mathscr{F}}(\mathscr{P}(C^\bullet)) & \xrightarrow{\widetilde{\mathscr{F}}(\mathscr{P}(f^\bullet))} & \widetilde{\mathscr{F}}(\mathscr{P}(D^\bullet)) \\ {\scriptstyle \nu_{C^\bullet}}\downarrow & & \downarrow{\scriptstyle \nu_{D^\bullet}} \\ \mathscr{F}(C^\bullet) & \xrightarrow{\mathscr{F}(f^\bullet)} & \mathscr{F}(D^\bullet) \end{array}$$

This diagram is obtained by applying $\mathscr{F}$ to the diagram discussed above the theorem:

$$\begin{array}{ccc} \mathscr{P}(C^\bullet) & \xrightarrow{\mathscr{P}(f^\bullet)} & \mathscr{P}(D^\bullet) \\ {\scriptstyle \varphi_{C^\bullet}}\downarrow{\scriptstyle \sim} & & {\scriptstyle \sim}\downarrow{\scriptstyle \varphi_{D^\bullet}} \\ \mathscr{P}'(C^\bullet) & \xrightarrow[\mathscr{P}'(f^\bullet)]{} & \mathscr{P}'(D^\bullet) \end{array}$$

This diagram commutes up to homotopy, hence the other diagram commutes directly (lemma 56.1.37).

For uniqueness up to isomorphism, say $\overline{\mathscr{F}} : K^-(\mathbf{P}) \to D$ is another functor satisfying the properties. Then there exists a natural isomorphism:

$$\overline{\nu} : \overline{\mathscr{F}} \circ \mathscr{P} \rightsquigarrow \mathscr{F}$$

Now, for any $P^\bullet \in K^-(\mathbf{P})$, take the composition:

$$\overline{\mathscr{F}}(P^\bullet) \xrightarrow[\sim]{\overline{\mathscr{F}}(\mu_{P^\bullet})^{-1}} \overline{\mathscr{F}}(\mathscr{P}((P^\bullet)) \xrightarrow[\sim]{\overline{\nu}_{P^\bullet}} = \widetilde{\mathscr{F}}(P^\bullet)$$

If φ is this composition, then it is easy to verify that $\varphi : \overline{\mathscr{F}} \to \widetilde{\mathscr{F}}$ is a natural isomorphism, completing the proof.

56.3 Derived Functors: Ext and Tor

Let $\mathscr{F} : \mathbf{A} \to \mathbf{B}$ be an additive functor. Often, we study information about $\mathbf{A}$ by passing it through $\mathbf{B}$ (think of $- \otimes N$ or $\mathrm{Hom}_R(N, -)$). As alluded to in section 17.6, such information may be the number of extensions two objects may have, the amount of torsion an object may have. In section 17.6, it was claimed that this comes from "fixing" the lack of exactness of a left- or right-exact functor using

homological algebra. We are finally in a position to make this precise. In this section, we shall show how to take a (not-necessarily left/right exact) additive functor between two abelian categories with $\mathbf{A}$ having enough projectives (resp. injectives) $\mathscr{F} : \mathbf{A} \to \mathbf{B}$ and get a *derived functor*:

$$D^-(\mathscr{F}) : D^-(\mathbf{A}) \to D^-(\mathbf{B}) \qquad (\text{resp. } D^-(\mathscr{F}) : D^-(\mathbf{A}) \to D^-(\mathbf{B}))$$

This functor shall be used to develop a long-exact sequence in $\mathbf{B}$, given a short exact sequence of objects in $\mathbf{A}$.

56.3.1 Derived Functor

Let $\mathscr{F} : \mathbf{A} \to \mathbf{B}$ be an additive functor between two abelian categories. Then $\mathscr{F}$ extends to a functor:

$$\mathrm{Ch}(\mathscr{F}) : \mathrm{Ch}(\mathbf{A}) \to \mathrm{Ch}(\mathbf{B})$$

namely, if $C^\bullet$ is a complex:

$$\mathscr{F}(d^{i+1}_{C^\bullet}) \circ \mathscr{F}(d^i_{C^\bullet}) = \mathscr{F}(d^{i+1}_{C^\bullet} \circ d^i_{C^\bullet}) = \mathscr{F}(0) = 0$$

hence, $\mathrm{Ch}(\mathscr{F})(C^\bullet)$ is indeed a complex. Then since homotopic morphisms are sent to homotopic morphisms (lemma 56.1.34), $\mathrm{Ch}(\mathscr{F})$ induces a morphism $K(\mathscr{F})$:

$$K(\mathscr{F}) : K(\mathbf{A}) \to K(\mathbf{B})$$

From the results we have proved, we have the following commutative diagram:

$$\begin{array}{ccc} \mathbf{A} & \xrightarrow{\mathscr{F}} & \mathbf{B} \\ {\scriptstyle\iota}\downarrow & & \downarrow{\scriptstyle\iota} \\ K(\mathbf{A}) & \xrightarrow{K(\mathscr{F})} & K(\mathbf{B}) \end{array}$$

Furthermore, if the complexes are bounded, then certainly $\mathrm{Ch}(\mathscr{F})$ sends bounded complexes to bounded complexes, and hence the same holds for $K(\mathscr{F})$. Now, if $\mathbf{A}$ has enough projectives so that we may consider $K^-(\mathbf{P})$, can we restrict $K(\mathbf{A})$ to $K(P(\mathbf{A}))$, and map to $K(P(\mathbf{B}))$ (where $P(\mathbf{A})$ and $P(\mathbf{B})$ are the projectives of $\mathbf{A}$ and $\mathbf{B}$ respectively)? This is not the case in general; for example we saw that $- \otimes N$ in R-**Mod** does not preserve projectives. If $\mathbf{B}$ has enough projectives, then we may choose a projective resolution functor $\mathscr{P}_B : \mathrm{Ch}^-(B) \to K^-(\mathbf{P}^{-1})$ mapping each complex to a projective resolution in a functorial manner. Since $\mathscr{P}_B$ sends homotopic morphisms to homotopic morphisms (lemma 56.2.7), $\mathscr{P}_B$ descends to a functor $K(\mathscr{P}_B)$. Combining these facts, we may define the following functor:

Definition 56.3.1: Left-Derived (right-Derived) Functor

Let $\mathscr{F} : \mathbf{A} \to \mathbf{B}$ be an additive functor. Then the *left-derived functor* of $\mathscr{F}$ is the composition:

$$K^-(P(\mathbf{A})) \xrightarrow[\iota_A]{} K^-(\mathbf{A}) \xrightarrow[K(\mathscr{F})]{} K^-(\mathbf{B}) \xrightarrow[K(\mathscr{P}_B))]{} K^-(P(\mathbf{B})) \qquad \mathbf{L}\mathscr{F} : K^-(\mathbf{A}) \to K^-(P(\mathbf{B}))$$

where ι_A is the inclusion of $K^-(P(\mathbf{A}))$ as a full subcategory of $K^-(\mathbf{A})$. The resulting functor is denoted $\mathbf{L}\mathscr{F}$.

It may seem that the natural notation would be $D^-(\mathscr{F})$, however the $\mathbf{L}\mathscr{F}$ notation was established before the abstraction given above, and has stuck. Similarly, if $\mathbf{A}$, $\mathbf{B}$ has enough injectives, we may define the right-derived functor $\mathbf{R}\mathscr{F}$.

It is natural to want to characterize $\mathbf{L}\mathscr{F}$ and $\mathbf{R}\mathscr{F}$ in terms of some universal property. Naturally, this universal property would be defined up to natural isomorphism, for $\mathscr{P}_A$ and $\mathscr{P}_B$ are chosen up to natural isomorphism. This turns to be a bit subtle. For example, there is no natural functor which shall always make the following diagram commute:

$$\begin{array}{ccc} \hat{\mathbf{A}} & \overset{??}{\dashrightarrow} & \hat{\mathbf{B}} \\ \downarrow & & \downarrow \\ K^-(P(\mathbf{A})) & \xrightarrow{\mathbf{L}\mathscr{F}} & K^-(P(\mathbf{B})) \end{array}$$

The reason is, it is not necessarily the case that a complex whose cohomology is concentrated at 0 would map via $\mathbf{L}\mathscr{F}$ to a complex with the same property. In fact, the reader may expect this, for the image of a functor $\mathscr{F}$ may present some non-trivial cohomological information, (think of $\mathscr{F} := \mathrm{Hom}_R(N, -)$ where N is non-projective). If the functor $\mathscr{F}$ is *exact*, then then there is essentially no "change in cohomology". This is captured in the following proposition:

Proposition 56.3.2: Derived Functors And Exactness

Let $\mathscr{F}$ be an additive *exact* functor. Then $\hat{\mathbf{A}}$ is in fact sent to $\hat{\mathbf{B}}$ via $\mathbf{L}\mathscr{F}$

***Proof*:**

Let $P^\bullet \in \hat{\mathbf{A}}$ so that $H^i(P^\bullet) = 0$ for all $i \neq 0$. Then $\mathbf{L}\mathscr{F}(P^\bullet)$ is given by choosing a projective resolution $P^\bullet_{\mathscr{F}(P^\bullet)}$ of $\mathscr{F}(P^\bullet)$. Since quasi-isomorphissm preserve cohomology and (key!) exact functors *commute* with cohomology, an exact functor carrying kernels to kernels and images to images and hence subquotients to subquotients:

$$H^i(\mathbf{L}\mathscr{F}(P^\bullet)) = H^i(P^\bullet_{\mathscr{F}(P^\bullet)}) \cong H^i(\mathscr{F}(P^\bullet)) \cong \mathscr{F}(H^i(P^\bullet)) = \mathscr{F}(0) \overset{i\neq 0}{=} 0$$

Thus, $\mathbf{L}\mathscr{F}(P^\bullet)$ does indeed map to an object of $\hat{\mathbf{B}}$.

Even more is true if $\mathscr{F}$ is exact: $H^i(\mathbf{L}\mathscr{F}(P^\bullet)) \cong \mathscr{F}(H^0(P^\bullet))$, saying that the restriction of $\mathbf{L}\mathscr{F}$ agrees with $\mathscr{F}$ (modulo equivalence of categories). Hence, in general we shall be interested in non-exact functors, usually functors that are only left or right exact.

Returning to finding an appropriate universal property for derived functors, another natural candidate would be given by taking a "step back" from the above diagram and consider instead if the following diagram commutes (up to natural isomorphism)

$$\begin{array}{ccc} K^-(\mathbf{A}) & \xrightarrow{K(\mathscr{F})} & K^-(\mathbf{B}) \\ \downarrow{\scriptstyle \mathscr{P}_A} & & \downarrow{\scriptstyle \mathscr{P}_B} \\ K^-(P(\mathbf{A})) & \xrightarrow[\mathbf{L}\mathscr{F}]{} & K^-(P(\mathbf{B})) \end{array}$$

in particular, that there may be a natural isomorphism:

$$\mathbf{L}\mathscr{F} \circ \mathscr{P}_A \overset{\sim}{\rightsquigarrow} \mathscr{P}_B \circ K(\mathscr{F})$$

Unfortunately, this is not in general the case

Example 56.3.3: Lacking Natural Isomorphism
(exercise 7.3 in Aluffi, should I put solution here?)

The following is the best we can hope for:

Proposition 56.3.4: Universal Property of (left-)Derived Functor

Let $\mathscr{F} : \mathbf{A} \to \mathbf{B}$ be an additive functor between abelian categories. Then $\mathbf{L}\mathscr{F}$ satisfies the following universal property:

1. There is a natural transformation:
$$\mathbf{L}\mathscr{F} \circ \mathscr{P}_A \overset{\sim}{\rightsquigarrow} \mathscr{P}_B \circ K(\mathscr{F})$$
2. for every functor $\mathscr{G} : K^-(P(\mathbf{A})) \to K^-(P(\mathbf{B}))$ and every natural tarnsformation $\gamma : \mathscr{G} \circ \mathscr{P}_A \rightsquigarrow \mathscr{P}_B \circ K(\mathscr{F})$, there is a unique (up to natural isomorphism) natural transformation $\mathscr{G} \rightsquigarrow \mathbf{L}\mathscr{F}$ inducign a factorization:
$$\gamma : \mathscr{G} \circ \mathscr{P}_A \rightsquigarrow \mathbf{L}\mathscr{F} \circ \mathscr{P}_A \rightsquigarrow \mathscr{P}_B \circ K(\mathscr{F})$$

A similar result holds for right-derived functors.

***Proof Key ideas*:**
The argument is the usual one for a Kan-extension-style universal property, and it is stated here rather than carried out because the ambient apparatus is not yet in place: the definition of $D(\mathbf{A})$ used below rests on the localization machinery that section 55.2 defers. The full treatment is in *An Introduction to Homological Algebra* [101].

For (1), the natural transformation is the comparison map induced by functoriality of projective resolutions: $\mathscr{P}_A$ picks a resolution, $K(\mathscr{F})$ applies $\mathscr{F}$ termwise, and proposition 56.2.15 makes the resulting square commute up to homotopy, which is commutativity in K^-.

For (2), given $\mathscr{G}$ and γ, the factorization is forced on objects because a projective resolution is initial among complexes of projectives mapping to the object (lemma 56.2.13), so any transformation out of $\mathscr{G} \circ \mathscr{P}_A$ is determined by its value on resolutions; uniqueness up to natural isomorphism is then the uniqueness up to homotopy of those comparison maps (proposition 56.2.14).

(a word on composition)

56.3.2 Long Exact Sequences of Derived Functors

With the derived functor established and being the best candidate for holding (co)homology information, we proceed with extracting this informaiton: we may take $\mathbf{L}_i\mathscr{F} := H^{-i} \circ \mathbf{L}\mathscr{F}$. The reason for taking H^{-i} instead of i is since the indexing works out better. This produced a functor

$\mathbf{L}_i\mathscr{F} : D^-(\mathbf{A}) \to B$. Notice that B does not need to have enough projectives for:

$$\mathbf{L}_i\mathscr{F}(P^\bullet) = H^{-i}(\mathscr{P}_B(\mathrm{Ch}(\mathscr{F})(P^\bullet))) \cong H^{-i}(\mathrm{Ch}(\mathscr{F})(P^\bullet))$$

where the last isomorphism comes from $\mathscr{P}_B(\mathrm{Ch}(\mathscr{F})(P^\bullet)))$ being quasi-isomorphic to $\mathrm{Ch}(\mathscr{F})(P^\bullet)$. Though this abstract approach is useful, the following more concrete version of $\mathbf{L}_i\mathscr{F}$ shall prove more useful for computations.

Definition 56.3.5: ith Left-Derived Functor

Let $\mathscr{F} : \mathbf{A} \to \mathbf{B}$ be an additive functor between two abelian categories where $\mathbf{A}$ has enough projectives. Then the *ith left-derived functor* $\mathbf{L}_i\mathscr{F} : A \to B$ is given by:

$$\mathbf{L}_i\mathscr{F} := H^{-i} \circ \mathbf{L}\mathscr{F} \circ \mathscr{P}_A \circ \iota_A$$

The complex in $\mathrm{Ch}(\mathbf{B})$ with $\mathbf{L}_i\mathscr{F}(M)$ in the $-i$th degree with vanishing differentials is denoted $\mathbf{L}_\bullet\mathscr{F}(M)$.

To be precise, if $M \in \mathbf{A}$, then $\mathbf{L}_i(M)$ is found by

1. finding any projective resolution $P^\bullet_M$ of M
2. Applying $\mathrm{Ch}(\mathscr{F})$ to $P^\bullet_M$, $\mathrm{Ch}(\mathscr{F})(P^\bullet_M)$
3. take the $(-i)$th cohomology of this complex, $H^{-i}(\mathrm{Ch}(\mathscr{F})(P^\bullet_M))$

With all the build-up done so far, the resulting cohomology is independent of choice, for:

1. Any two projective resolutions are homotopy-equivalent
2. the image of homotopy-equivalent complexes via additive functors have isomorphic cohomology

Naturally, the *ith right-derived functor* $\mathbf{R}^i\mathscr{F}$ of an additive functor $\mathscr{F}$ and the assocaited complex $\mathbf{R}^\bullet\mathscr{F}$ is defined simplify (given $\mathbf{A}$ has enough injectives), namely

$$\mathbf{R}^i\mathscr{F} := H^i \circ \mathbf{R}\mathscr{F} \circ \mathscr{Q}_A \circ \iota_A$$

A note should be said about *contravriant functors*: since they can always be viewed as *covariant* functor $\mathbf{A}^{\mathrm{op}} \to B$, $\mathbf{A}$ would instead have to have the appropriate injectives or projectives swapped. The right-derived functor of an additive *contravariant functor* would need $\mathbf{A}$ to have enough *projectives*, since $\mathbf{A}^{\mathrm{op}}$ would have to have enough injectives. The $\mathbf{L}_i$ and $\mathbf{R}_i$ notation can be thought of as "looking" at the cohomology provided by $\mathscr{F}$. As mentioned earlier, if $\mathscr{F}$ is exact, then the derived functors are *trivial* in terms of cohomology, hence the derived functors are only interesting if $\mathscr{F}$ is not exact, at which point these functors give you interesting information.

Example 56.3.6: ith Derived Functors

It is finally time to bring back section 17.6

1. Let $\mathbf{A} = R\text{-}\mathbf{Mod}$ for a commutative ring R, pick an R-module N, and define

$$- \otimes_R N$$

The left-derived functor of $- \otimes_R N$ is labeled

$$- \overset{\mathbf{L}}{\otimes}_R N : D^-(R\text{-Mod}) \to D^-(R\text{-Mod})$$

The ith derived left-functor of $- \otimes_R N$ is denoted:

$$\operatorname{Tor}_i^R(- \otimes_R N) = H^{-i}((-)_\bullet \otimes N)$$

where the right hand side of the equality comes from the result elaborated in section 17.6. It was mentioned that a flat resolution may be used instead of a projective resolution, however this was does not currently fit within the theory. This shall be addressed in the next section.

2. Similarly, $\operatorname{Hom}_R(-, N)$ and $\operatorname{Hom}_R(N, -)$ admits a right derived functors

$$\operatorname{Ext}_R^i(M, N) = H^i(\operatorname{Hom}_R(M, N^\bullet))$$

For $\operatorname{Hom}_R(-, N)$, do not forget that one must take the opposite category and a projective resolution.

Commutativity of R is used here only so that the values are again R-modules. Over an arbitrary ring R the same definitions apply to $- \otimes_R N \colon \text{Mod-}R \to \mathbf{Ab}$ for a left R-module N, and to Hom_R between left R-modules, with values in $\mathbf{Ab}$.

The most important part of left-/right-derived functors is their use in fixing exactness after applying a not necessarily exact functor $\mathscr{F}$. On a high level, since the derived category there is not an abelian category (hence not necessarily containing kernels and cokernels, nor is it really feasible to investigate such categories), the notion of *triangulated categories* is useful for categories where given a "short exact sequence", we can create a long exact sequence (that is, a category in which snakes lemma can be applied). We shall not investigate the idea of triangulated categories, but the following is a concrete results needed for any rigorous exploration of triangulated categories.

Assuming the whole that that our category $\mathbf{A}$ has enough projectives, take a short exact sequence:

$$0 \to L \to M \to N \to 0$$

Since there is enough projectives, can the projective resolutions be arranged to create a short exact sequence? The answer is yes, and given the following apt name:

Lemma 56.3.7: Horseshoe Lemma

Let

$$0 \to L \to M \to N \to 0$$


be an exact sequence in an abelian category $\mathbf{A}$ with enough projectives, and let $P_L^\bullet, P_N^\bullet$ be projective resolutions of L, N respectively. Then there exists an exact sequence:

$$0 \to P_L^\bullet \to P_M^\bullet \to P_N^\bullet \to 0$$

where $P_M^\bullet$ is a projective resolution of M, inducing the original sequence in cohomology (i.e. applying H^0). Moreover the sequence is *degreewise split*: the construction produces $P_M^i = P_L^i \oplus P_N^i$ in each degree, with the two displayed maps the inclusion and the projection.

The dual statement holds in an abelian category with enough injectives: given injective resolutions $L \to I_L^\bullet$ and $N \to I_N^\bullet$, there is a degreewise split exact sequence $0 \to I_L^\bullet \to I_M^\bullet \to I_N^\bullet \to 0$ with $I_M^\bullet$ an injective resolution of M. It is this form that theorem 60.4.2 uses, and it follows by applying the projective statement in the opposite category.

***Proof*:**
Visually, we want to find objects and maps to fill in this commutative diagram:



where the dotted lines and the P_M^i are the goal (the name of the lemma comes from this horseshoe shaped diagram). I claim that $P_M^i = P_L^i \oplus P_N^i$ (which the reader should recall or reprove is projective) with the natural inclusion and projection maps shall work. The argument is done via induction. Since P_N^0 is projective and $M \to N$ is an epimorphism, the morphism $P_N^0 \to N$ lifts to a isomorphism m $\beta : P_N^0 \to M$. On the other hand, P_L^0 maps to M via $\alpha : P_L^0 \to L \to M$. Thus, there is a morphism:

$$\pi_M := \alpha \oplus \beta : P_L^0 \oplus P_N^0 \to M$$

diving us the diagram

$$\begin{array}{ccccccccc}
 & & \vdots & & \vdots & & \vdots & & \\
 & & \downarrow & & \downarrow & & \downarrow & & \\
0 & \longrightarrow & P_L^{-2} & \cdots\cdots\rightarrow & P_M^{-2} & \cdots\cdots\rightarrow & P_N^{-2} & \longrightarrow & 0 \\
 & & \downarrow & & \downarrow & & \downarrow & & \\
0 & \longrightarrow & P_L^{-1} & \cdots\cdots\rightarrow & P_M^{-1} & \cdots\cdots\rightarrow & P_N^{-1} & \longrightarrow & 0 \\
 & & \downarrow & & \downarrow & & \downarrow & & \\
0 & \longrightarrow & P_L^{0} & \longrightarrow & P_L^0 \oplus P_N^0 & \longrightarrow & P_N^0 & \longrightarrow & 0 \\
 & & \downarrow & & \downarrow & & \downarrow & & \\
0 & \longrightarrow & L & \longrightarrow & M & \longrightarrow & N & \longrightarrow & 0
\end{array}$$

The snake lemma and π_L being an epimorphism gives that the kernels of the vertical maps form an exact sequence, and hence we have an epimorphism from P_L^{-1} and P_N^{-1} to the respective kernels since the column of the original diagram are exact:

$$\begin{array}{ccccccccc}
 & & P_L^{-1} & & & & P_N^{-1} & & \\
 & & \downarrow{\scriptstyle \pi_L^{-1}} & & & & \downarrow{\scriptstyle \pi_N^{-1}} & & \\
0 & \longrightarrow & \ker \pi_L & \longrightarrow & \ker \pi_M & \longrightarrow & \ker \pi_N & \longrightarrow & 0
\end{array}$$

Now, repeat as before, defining $P_M^{-1} = P_L^{-1} \oplus P_N^{-1}$ and define $\pi_M^{-1} : P_L^{-1} \oplus P_N^{-1} \to \ker \pi_M \to P_L^0 \oplus P_N^0$ giving the diagram:

$$\begin{array}{ccccccccc}
0 & \longrightarrow & P_L^{-1} & \longrightarrow & P_L^{-1} \oplus P_N^{-1} & \longrightarrow & P_N^{-1} & \longrightarrow & 0 \\
 & & \downarrow{\scriptstyle \pi_L^{-1}} & & \downarrow{\scriptstyle \pi_M^{-1}} & & \downarrow{\scriptstyle \pi_N^{-1}} & & \\
0 & \longrightarrow & P_L^{0} & \longrightarrow & P_L^0 \oplus P_N^0 & \longrightarrow & P_N^0 & \longrightarrow & 0 \\
 & & \downarrow{\scriptstyle \pi_L} & & \downarrow{\scriptstyle \pi_M} & & \downarrow{\scriptstyle \pi_N} & & \\
0 & \longrightarrow & L & \longrightarrow & M & \longrightarrow & N & \longrightarrow & 0
\end{array}$$

By then by the snake lemma, $P_L^{-1} \oplus P_N^{-1} \to \ker \pi_M$ is an epimorphism, and hence we get exactness at $P_L^0 \oplus P_N^0$. Continuing inductively constructs the rest of the diagram.

It is tempting to say from this result that the mapping $\mathbf{A} \to K(\mathbf{A})$ is exact, however $K(\mathbf{A})$ is not abelian and hence this is simply undefined. The above is should instead be interpreted as follows: $P_M^\bullet$ is the mapping cone of a morphism: $\rho^\bullet : P_N[-1]^\bullet \to P_L^\bullet$, giving the distinguished triangle:

$$\begin{array}{ccc}
 & P_L^\bullet & \\
{\scriptstyle +1}\nearrow & & \searrow \\
P_N^\bullet & \longleftarrow & MC(\rho)^\bullet [= P_M^\bullet]
\end{array}$$

This is as close as we can get to preserving exactness.

The horseshoe construction is functorial in the short exact sequence it resolves. Once lifts of the two outer resolutions have been chosen, compatibility with the splitting leaves only one entry of the middle lift to be built, and that entry is what the following lemma constructs.

Lemma 56.3.8: Functoriality of the Horseshoe Construction

Consider a morphism of short exact sequences in an abelian category with enough injectives,

$$\begin{array}{ccccccccc} 0 & \longrightarrow & L & \longrightarrow & M & \longrightarrow & N & \longrightarrow & 0 \\ & & \downarrow{\scriptstyle \lambda} & & \downarrow{\scriptstyle \mu} & & \downarrow{\scriptstyle \nu} & & \\ 0 & \longrightarrow & L' & \longrightarrow & M' & \longrightarrow & N' & \longrightarrow & 0 \end{array}$$

and injective resolutions $I_L^\bullet, I_N^\bullet, I_{L'}^\bullet, I_{N'}^\bullet$ of the four outer objects, and injective resolutions $I_M^\bullet$, $I_{M'}^\bullet$ of M and M' sitting in *degreewise split* short exact sequences $0 \to I_L^\bullet \to I_M^\bullet \to I_N^\bullet \to 0$ and $0 \to I_{L'}^\bullet \to I_{M'}^\bullet \to I_{N'}^\bullet \to 0$ lifting the two given rows. (This is what lemma 56.3.7 produces, but the argument uses only the splitting, which is automatic whenever the outer terms are injective.) Given lifts $\lambda^\bullet \colon I_L^\bullet \to I_{L'}^\bullet$ and $\nu^\bullet \colon I_N^\bullet \to I_{N'}^\bullet$ of λ and ν, there is a lift $\mu^\bullet \colon I_M^\bullet \to I_{M'}^\bullet$ of μ compatible with both, that is making the induced diagram of resolutions commute.

The dual statement holds in an abelian category with enough projectives: given a morphism of short exact sequences of the same shape, projective resolutions of the four outer objects, degreewise split short exact sequences $0 \to P_L^\bullet \to P_M^\bullet \to P_N^\bullet \to 0$ and $0 \to P_{L'}^\bullet \to P_{M'}^\bullet \to P_{N'}^\bullet \to 0$ lifting the two rows, and lifts $\lambda^\bullet$ of λ and $\nu^\bullet$ of ν, there is a lift $\mu^\bullet \colon P_M^\bullet \to P_{M'}^\bullet$ of μ compatible with both. It follows by applying the injective statement in the opposite category, and it is this form that theorem 56.3.11 uses.

***Proof*:**

By lemma 56.3.7 the middle resolutions are $I_M^q = I_L^q \oplus I_N^q$ and $I_{M'}^q = I_{L'}^q \oplus I_{N'}^q$ in each degree, with the displayed maps the inclusion and the projection. Compatibility with those two maps forces $\mu^\bullet$ to have the shape

$$\mu^q = \begin{pmatrix} \lambda^q & \sigma^q \\ 0 & \nu^q \end{pmatrix}$$

so the only freedom is the family $\sigma^q \colon I_N^q \to I_{L'}^q$, and the content of the lemma is that it can be chosen so that $\mu^\bullet$ is a chain map lifting μ.

Write the differential of $I_M^\bullet$ as $\begin{pmatrix} d_L & \tau \\ 0 & d_N \end{pmatrix}$ and that of $I_{M'}^\bullet$ as $\begin{pmatrix} d_{L'} & \tau' \\ 0 & d_{N'} \end{pmatrix}$, where τ and τ' are the off-diagonal terms the horseshoe construction produces. The chain-map condition $\mu^{q+1} d = d \mu^q$ reads, in the only entry that is not automatic,

$$\lambda^{q+1}\tau^q + \sigma^{q+1} d_N^q = d_{L'}^q \sigma^q + \tau'^q \nu^q$$

so, writing $\theta^q := d_{L'}^q \sigma^q + \tau'^q \nu^q - \lambda^{q+1}\tau^q$, the family σ must satisfy $\sigma^{q+1} \circ d_N^q = \theta^q$ for every q.

The base case. Write the augmentation of $I_M^\bullet$ through the splitting as $\varepsilon_M = (\varphi,\ \varepsilon_N \pi)^{\mathsf{T}}$, where

$\pi\colon M \to N$ is the given epimorphism and $\varphi\colon M \to I^0_L$ restricts to ε_L on L; similarly for M'. The morphism σ^0 is not given by the hypothesis, it has to be built. Set $\theta^{-1} := \varphi'\mu - \lambda^0\varphi\colon M \to I^0_{L'}$. On the subobject L this is $\varepsilon_{L'}\lambda - \varepsilon_{L'}\lambda = 0$, so θ^{-1} kills $L = \ker\pi$ and factors as $\bar\theta \circ \pi$ for a unique $\bar\theta\colon N \to I^0_{L'}$. Since $\varepsilon_N\colon N \to I^0_N$ is a monomorphism and $I^0_{L'}$ is injective, $\bar\theta$ extends along it to $\sigma^0\colon I^0_N \to I^0_{L'}$ with $\sigma^0\varepsilon_N\pi = \theta^{-1}$, which is the degree-zero instance of the required identity and is the only place the compatibility of μ with λ and ν is used.

The inductive step. Suppose $\sigma^{\le q}$ has been chosen. To extend θ^q along d^q_N it suffices that θ^q vanish on $\ker d^q_N = \mathrm{im} d^{q-1}_N$, and this is a direct computation. Squaring the differential of $I^\bullet_M$ gives $d_L\tau + \tau d_N = 0$, and likewise $d_{L'}\tau' + \tau' d_{N'} = 0$; using these, the inductive hypothesis $\sigma^q d^{q-1}_N = \theta^{q-1}$, the chain-map identities for λ and ν, and $d \circ d = 0$,

$$\theta^q \circ d^{q-1}_N = \left(\lambda^{q+1} d^q_L - d^q_{L'}\lambda^q\right) \circ \tau^{q-1} = 0$$

the last equality because $\lambda^\bullet$ is a chain map. For $q = 0$ the same conclusion holds with $\ker d^0_N = \mathrm{im}\varepsilon_N$ in place of $\mathrm{im} d^{-1}_N$: applying θ^0 to $\varepsilon_N\pi$ and using $d^0_L\varphi + \tau^0\varepsilon_N\pi = 0$, which is the first component of $d^0_M\varepsilon_M = 0$, together with the base case, gives $\theta^0\varepsilon_N\pi = (\lambda^1 d^0_L - d^0_{L'}\lambda^0)\varphi = 0$, and π is an epimorphism. Hence in every degree θ^q factors through $\mathrm{im} d^q_N$, and since $\mathrm{im} d^q_N \hookrightarrow I^{q+1}_N$ is a monomorphism and $I^{q+1}_{L'}$ is injective, definition 56.2.1 extends the factored morphism to $\sigma^{q+1}\colon I^{q+1}_N \to I^{q+1}_{L'}$ with $\sigma^{q+1} d^q_N = \theta^q$, as required.

The resulting $\mu^\bullet$ is a chain map by construction, is compatible with the inclusion and projection by its shape, and lifts μ because it does so in degree -1, that is on the augmentations, completing the proof.

Corollary 56.3.9: Resolution Of Projective Resolutions

Let $M^\bullet$ be a complex bounded from above in a category $\mathbf{A}$ with enough projectives. Then there exists a complex $P^b_{M^\bullet} b$:

$$\cdots \to P^\bullet_{M^{-3}} \to P^\bullet_{M^{-2}} \to P^\bullet_{M^{-1}} \to\!\!\to P^\bullet_{M^0} \to 0$$

where each $P^\bullet_{M^i}$ is a projection resolution of M^i and inducing $M^\bullet$ in cohomology. If $M^\bullet$ is exact, then $P^\bullet_{M^\bullet}$ can be chosen to be exact.

***Proof*:**
Since $M^\bullet$ is a complex, it can be broken down into two short exact sequences:

$$0 \to K^i \to M^i \to I^{i+1} \to 0 \qquad 0 \to I^i \to K^i \to H^i \to 0$$

where K^i is the kernel of $M^i \to M^{i+1}$, I^{i+1} is its image, and H^i the cohomology at M^i. Chose arbitrary projective resolutions for each I^i and H^i for all i. Then by the horseshoe lemma, we get a projective resolution for K^i that fits within the short exact sequence:

$$0 \to P^\bullet_{I^i} \to P^\bullet_{K^i} \to P^\bullet_{H^i} \to 0$$

Applying the horseshoe lemma gain, we get a short exact sequence:

$$0 \to P^\bullet_{K^i} \to P^\bullet_{M^i} \to P^\bullet_{I^{i+1}} \to 0$$

Using these, the $P^\bullet_{M^i}$ can be used to construct a cochain complex, the differentials obtains by composition. If $M^\bullet$ is exact, then $I^i = K^i$, and so the construction gives $P^\bullet_{I^i} = P^\bullet_{K^i}$, so that $P^\bullet_{M^\bullet}$ is also exact.

Lemma 56.3.10: Projective Resolution and Functors

Let $\mathbf{A}$ be an abelian category and let

$$0 \to L^\bullet \to M^\bullet \to P^\bullet \to 0$$

be an exact sequence of complexes in $\mathbf{A}$, where P^i is projective for all i. Let $\mathscr{F} : \mathbf{A} \to \mathbf{B}$ be an additive functor between abelian categories. Then the sequence:

$$0 \to \mathscr{F}(L^\bullet) \to \mathscr{F}(M^\bullet) \to \mathscr{F}(P^\bullet) \to 0$$

is exact

Note that there is nothing about $\mathscr{F}$ being an exact functor! This can be thought of as the generalization of the properties of projective modules which preserve exactness!!

***Proof*:**

Fix i. By lemma 56.1.5 the sequence $0 \to L^i \xrightarrow{\iota} M^i \xrightarrow{\pi} P^i \to 0$ is exact. The cokernel of $0 \to L^i$ is id_{L^i}, so exactness at L^i makes $\ker \iota$ the zero morphism. A kernel is a monomorphism (lemma 55.1.3), and a zero monomorphism has a zero object as its source, so ι is a monomorphism (lemma 55.1.4). Dually, exactness at P^i makes π an epimorphism. Exactness at M^i gives $\pi\iota = 0$ and $\mathrm{coker}\iota \circ \ker \pi = 0$. The monomorphism ι is the kernel of some morphism (condition (2) of definition 55.1.6), hence the kernel of $\mathrm{coker}\iota$ (lemma 55.1.7). So $\ker \pi = \iota a$ for some a, and $\pi\iota = 0$ gives $\iota = (\ker \pi)\, b$ for some b. Then $\iota = \iota ab$ and $\ker \pi = (\ker \pi)\, ba$, and as both are monomorphisms, ab and ba are identities. So a is an isomorphism and ι is a kernel of π. Applying the exact functor $\mathrm{Hom}_{\mathbf{A}}(P^i, -)$ (definition 56.2.1) to it shows that $s \mapsto \pi s$ maps $\mathrm{Hom}_{\mathbf{A}}(P^i, M^i)$ onto $\mathrm{Hom}_{\mathbf{A}}(P^i, P^i)$, so there is $s\colon P^i \to M^i$ with $\pi s = \mathrm{id}_{P^i}$. Then $\pi(\mathrm{id}_{M^i} - s\pi) = \pi - \pi = 0$, so $\mathrm{id}_{M^i} - s\pi = \iota r$ for a unique $r\colon M^i \to L^i$. From $\iota r\iota = \iota - s\pi\iota = \iota$ and ι monic, $r\iota = \mathrm{id}_{L^i}$. So

$$\pi\iota = 0 \qquad r\iota = \mathrm{id}_{L^i} \qquad \pi s = \mathrm{id}_{P^i} \qquad \iota r + s\pi = \mathrm{id}_{M^i}$$

An additive functor preserves composites, identities, zero morphisms and sums of morphisms, so the same four identities hold for $\mathscr{F}(\iota)$, $\mathscr{F}(\pi)$, $\mathscr{F}(r)$ and $\mathscr{F}(s)$ in $\mathbf{B}$. They make $0 \to \mathscr{F}(L^i) \to \mathscr{F}(M^i) \to \mathscr{F}(P^i) \to 0$ exact: $\mathscr{F}(\iota)$ has the left inverse $\mathscr{F}(r)$, so it is a monomorphism, $\mathscr{F}(\pi)$ has the right inverse $\mathscr{F}(s)$, so it is an epimorphism, and $\mathscr{F}(\iota)$ is a kernel of $\mathscr{F}(\pi)$, because $\mathscr{F}(\pi)\mathscr{F}(\iota) = 0$ and every t with $\mathscr{F}(\pi)t = 0$ satisfies

$$t = \big(\mathscr{F}(\iota)\mathscr{F}(r) + \mathscr{F}(s)\mathscr{F}(\pi)\big)t = \mathscr{F}(\iota)\big(\mathscr{F}(r)t\big)$$

with the factorization unique as $\mathscr{F}(\iota)$ is monic. This holds in every degree i, so lemma 56.1.5 gives the exactness of the sequence of complexes, completing the proof.

Theorem 56.3.11: Long Exact Sequence From Derived Functor

Let $\mathscr{F} : \mathbf{A} \to \mathbf{B}$ be an additive functor of abelian categories, and assume $\mathbf{A}$ has enough projective. Then every short exact sequence in $\mathbf{A}$

$$0 \to L \xrightarrow{\alpha} M \xrightarrow{\beta} N \to 0$$

[covariantly] functorially induces a long exact sequence in $\mathbf{B}$, whose unlabelled horizontal arrows are $L_i\mathscr{F}(\alpha)$ and $L_i\mathscr{F}(\beta)$:

$$\begin{array}{l} \cdots \longrightarrow L_2\mathscr{F}(L) \longrightarrow L_2\mathscr{F}(M) \longrightarrow L_2\mathscr{F}(N) \\ \qquad\qquad \xrightarrow{\ \delta_2\ } \\ \quad L_1\mathscr{F}(L) \longrightarrow L_1\mathscr{F}(M) \longrightarrow L_1\mathscr{F}(N) \\ \qquad\qquad \xrightarrow{\ \delta_1\ } \\ \quad L_0\mathscr{F}(L) \longrightarrow L_0\mathscr{F}(M) \longrightarrow L_0\mathscr{F}(N) \longrightarrow 0 \end{array}$$

The assignment is natural in the short exact sequence. Given a commutative diagram with exact rows

$$\begin{array}{ccccccccc} 0 & \longrightarrow & L & \longrightarrow & M & \longrightarrow & N & \longrightarrow & 0 \\ & & \downarrow{\scriptstyle \lambda} & & \downarrow{\scriptstyle \mu} & & \downarrow{\scriptstyle \nu} & & \\ 0 & \longrightarrow & L' & \longrightarrow & M' & \longrightarrow & N' & \longrightarrow & 0 \end{array}$$

the two long exact sequences form a commutative ladder whose vertical morphisms are $L_i\mathscr{F}(\lambda)$, $L_i\mathscr{F}(\mu)$ and $L_i\mathscr{F}(\nu)$. Writing δ_i' for the connecting morphisms of the second row, the squares carrying the connecting morphisms read $\delta_i' \circ L_i\mathscr{F}(\nu) = L_{i-1}\mathscr{F}(\lambda) \circ \delta_i$.

***Proof*:**

Choose projective resolutions $P_L^\bullet$ and $P_N^\bullet$. By lemma 56.3.7 the given short exact sequence lifts to a degreewise split short exact sequence $0 \to P_L^\bullet \to P_M^\bullet \to P_N^\bullet \to 0$ of projective resolutions, which by lemma 56.3.10 creates a short exact sequence:

$$0 \to \mathscr{F}(P_L^\bullet) \to \mathscr{F}(P_M^\bullet) \to \mathscr{F}(P_N^\bullet) \to 0$$

Since the cohomology of these complexes is precisely the left-derived functors of $\mathscr{F}$ (definition 56.3.5), the long exact cohomology sequence is given by theorem 56.1.20.

Naturality. Resolve the second row the same way, as $0 \to P_{L'}^\bullet \to P_{M'}^\bullet \to P_{N'}^\bullet \to 0$. By proposition 56.2.15 the morphisms λ and ν lift to morphisms of resolutions $\lambda^\bullet : P_L^\bullet \to P_{L'}^\bullet$ and $\nu^\bullet : P_N^\bullet \to P_{N'}^\bullet$, and the projective form of lemma 56.3.8 then produces a lift $\mu^\bullet : P_M^\bullet \to P_{M'}^\bullet$ of μ compatible with the inclusion and the projection. The three lifts form a morphism of short exact sequences of complexes, and $\mathscr{F}$, being a functor, carries the two commuting squares to

commuting squares:


$$\begin{array}{ccccccc} 0 & \longrightarrow & \mathscr{F}(P_L^\bullet) & \longrightarrow & \mathscr{F}(P_M^\bullet) & \longrightarrow & \mathscr{F}(P_N^\bullet) \longrightarrow 0 \\ & & \downarrow{\scriptstyle \mathscr{F}(\lambda^\bullet)} & & \downarrow{\scriptstyle \mathscr{F}(\mu^\bullet)} & & \downarrow{\scriptstyle \mathscr{F}(\nu^\bullet)} \\ 0 & \longrightarrow & \mathscr{F}(P_{L'}^\bullet) & \longrightarrow & \mathscr{F}(P_{M'}^\bullet) & \longrightarrow & \mathscr{F}(P_{N'}^\bullet) \longrightarrow 0 \end{array}$$

Both rows are exact by lemma 56.3.10, so the naturality clause of theorem 56.1.20, read through $H_n = H^{-n}$, gives a commutative ladder between the two long exact sequences, the squares carrying the connecting morphisms included.


The vertical morphisms of that ladder are the asserted ones. By definition 56.3.5 the value of $L_i\mathscr{F}$ on a morphism is H^{-i} of the image under $\mathrm{Ch}(\mathscr{F})$ of a lift of that morphism to projective resolutions, and the value does not depend on the lift chosen: two lifts are homotopic by proposition 56.2.15, $\mathrm{Ch}(\mathscr{F})$ carries homotopic morphisms to homotopic morphisms by lemma 56.1.34, and homotopic morphisms agree on cohomology by proposition 56.1.31. Since $\lambda^\bullet$, $\mu^\bullet$ and $\nu^\bullet$ are such lifts, the vertical morphisms are $L_i\mathscr{F}(\lambda)$, $L_i\mathscr{F}(\mu)$ and $L_i\mathscr{F}(\nu)$.

The same argument identifies the horizontal arrows, which is what makes the sequence a long exact sequence *of the derived functors of α and β* rather than of unnamed induced maps. The horseshoe sequence $0 \to P_L^\bullet \to P_M^\bullet \to P_N^\bullet \to 0$ of lemma 56.3.7 induces the original short exact sequence on H^0, so its degreewise inclusion and projection are lifts of α and β to the chosen projective resolutions. Applying $\mathrm{Ch}(\mathscr{F})$ and H^{-i} to them therefore gives $L_i\mathscr{F}(\alpha)$ and $L_i\mathscr{F}(\beta)$, by the same independence of the lift, completing the proof.


The change from short exact sequence to long exact sequence can be unified under the notion of triangles, namely this theorem can be seen as the triangle:



inducing the triangle



where the vertices of this triangle are complexes in $C^{\leq 0}(\mathbf{B})$. Naturally, the dual situation happens for right derived functors for categories that have enough injectives, iin which case the above triangle induces a triangle:



where the vertices of this triangle are complexes in $C^{\geq 0}(\mathbf{B})$.

The dual statement is what the right-derived functors satisfy, and it is recorded separately because Ext in its second variable is computed that way.

Corollary 56.3.12: Long Exact Sequence From a Right-Derived Functor

Let $\mathscr{F}\colon \mathbf{A} \to \mathbf{B}$ be an additive functor of abelian categories with $\mathbf{A}$ having enough injectives. Then every short exact sequence $0 \to L \xrightarrow{\alpha} M \xrightarrow{\beta} N \to 0$ in $\mathbf{A}$ induces a long exact sequence

$$\begin{aligned} 0 &\to R^0\mathscr{F}(L) \\ &\to R^0\mathscr{F}(M) \\ &\to R^0\mathscr{F}(N) \xrightarrow{\delta^0} R^1\mathscr{F}(L) \\ &\to R^1\mathscr{F}(M) \\ &\to R^1\mathscr{F}(N) \xrightarrow{\delta^1} R^2\mathscr{F}(L) \\ &\to \cdots \end{aligned}$$

whose unlabelled arrows are $R^i\mathscr{F}(\alpha)$ and $R^i\mathscr{F}(\beta)$, and which is functorial in the short exact sequence: a morphism from it to a second short exact sequence $0 \to L' \to M' \to N' \to 0$, with components $\lambda\colon L \to L'$, $\mu\colon M \to M'$ and $\nu\colon N \to N'$, induces a commutative ladder between the two long exact sequences whose vertical morphisms are $R^i\mathscr{F}(\lambda)$, $R^i\mathscr{F}(\mu)$ and $R^i\mathscr{F}(\nu)$, the squares carrying the connecting morphisms included.

***Proof*:**
Apply theorem 56.3.11 in the opposite categories. An injective object of $\mathbf{A}$ is a projective object of $\mathbf{A}^{op}$, so $\mathbf{A}$ having enough injectives is $\mathbf{A}^{op}$ having enough projectives; the short exact sequence reverses to $0 \to N \to M \to L \to 0$ in $\mathbf{A}^{op}$; and the left-derived functors of $\mathscr{F}^{op}$ are the right-derived functors of $\mathscr{F}$ with the arrows reversed, by definition 56.3.1. Transporting the conclusion back gives the displayed sequence.

The naturality clause transports with it. A morphism of short exact sequences in $\mathbf{A}$ with components λ, μ, ν is, in $\mathbf{A}^{op}$, a morphism from the reversed second sequence to the reversed first with components $\nu^{op}, \mu^{op}, \lambda^{op}$, so theorem 56.3.11 produces a commutative ladder in $\mathbf{B}^{op}$ whose vertical morphisms are the left-derived functors of $\mathscr{F}^{op}$ applied to those three. Read in $\mathbf{B}$, that ladder is the asserted one, completing the proof.

These consideration were for general additive functors. In most cases we saw, there is usually a left-exact or right-exact functor (indeed, the nature of the left-derived and right-derived series almost force us to choose "a side"). If a functor is given to be either left- or right-exact, then it can be directly recovered from their derived functors, as we shall now show.

Proposition 56.3.13: Right-Exactness And Derived Functors

Let $\mathbf{A}$ be an abelian category with enough projectives and $\mathscr{F} : \mathbf{A} \to \mathbf{B}$ be a right-exact additive functor. Then

1. $\mathbf{L}_i\mathscr{F} = 0$ for $i < 0$
2. $L_0\mathscr{F}$ is naturally isomorphic to $\mathscr{F}$

The dual result holds for the category with enough injectives. Do note that the *right*-exact functor is associated to the *left* derived functors, and vice-versa for left-exact functors which would have the associated *right* derived functors. This is because the derived functors are "fixing" the exactness on the other side.

***Proof*:**

Since projective resolution $P^\bullet$ of an object M in $\mathbf{A}$ is in $C^{\leq 0}(\mathbf{A})$, $C(\mathscr{F})(P^\bullet)$ is 0 in positive degree, and hence so is its cohomology. Since $H_i = H^{-i}$, the first claim is immediate.

For the second, an exact sequence:

$$P^{-1} \to P^0 \to M \to 0$$

will map to an exact sequence by $\mathscr{F}$ (due to right-exactness)

$$\mathscr{F}(P^{-1}) \to \mathscr{F}(P^0) \to \mathscr{F}(M) \to 0$$

This induces an isomorphism: $\nu_M : \mathbf{L}_0\mathscr{F}(M) = H^0(C(\mathscr{F})(P^\bullet)) \xrightarrow{\sim} \mathscr{F}(M)$. If $\varphi : M_0 \to M_1$ is a morphism, then there exists a morphism of projective resolutions $\alpha^\bullet : P_0^\bullet \to P_1^\bullet$:

$$\begin{array}{ccccccccc} \cdots & \longrightarrow & P_0^{-1} & \longrightarrow & P_0^0 & \longrightarrow & M_0 & \longrightarrow & 0 \\ & & \downarrow{\scriptstyle \alpha^{-1}} & & \downarrow{\scriptstyle \alpha^0} & & \downarrow{\scriptstyle \varphi} & & \\ \cdots & \longrightarrow & P_1^{-1} & \longrightarrow & P_1^0 & \longrightarrow & M_1 & \longrightarrow & 0 \end{array}$$

induced by φ where $H^0(\alpha^\bullet)$ agrees with φ. Applying $\mathscr{F}$ and truncating to $\alpha^\bullet$, we get the commutative diagram:

$$\begin{array}{ccccccc} \mathscr{F}(P_0^{-1}) & \longrightarrow & \mathscr{F}(P_0^0) & \longrightarrow & \mathscr{F}(M_0) & \longrightarrow & 0 \\ \downarrow{\scriptstyle \mathscr{F}(\alpha^{-1})} & & \downarrow{\scriptstyle \mathscr{F}(\alpha^0)} & & \downarrow{\scriptstyle \mathscr{F}(\varphi)} & & \\ \mathscr{F}(P_1^{-1}) & \longrightarrow & \mathscr{F}(P_1^0) & \longrightarrow & \mathscr{F}(M_1) & \longrightarrow & 0 \end{array}$$

with exact rows since $\mathscr{F}$ is right-exact. But then the following diagram commutes:

$$\begin{array}{ccc} \mathbf{L}_0\mathscr{F}(M_0) & \xrightarrow{\mathbf{L}_0\mathscr{F}(\varphi)} & \mathbf{L}_0\mathscr{F}(M_1) \\ \downarrow{\scriptstyle \nu_{M_0}} & & \downarrow{\scriptstyle \nu_{M_1}} \\ \mathscr{F}(M_0) & \xrightarrow[\mathscr{F}(\varphi)]{} & \mathscr{F}(M_1) \end{array}$$

The square commutes because $\mathbf{L}_0\mathscr{F}(\varphi) = H^0(C(\mathscr{F})(\alpha^\bullet))$ is the map that $\mathscr{F}(\alpha^0)$ induces on the cokernels of the maps $\mathscr{F}(P_i^{-1}) \to \mathscr{F}(P_i^0)$, each ν_{M_i} is the map that $\mathscr{F}(P_i^0) \to \mathscr{F}(M_i)$ induces on the same cokernel, and the right-hand square of the previous diagram commutes. This completes the proof.

This finally gives the desired recovery of exactness promised way back. Given a short exact sequence

$$0 \to L \to M \to N \to 0$$

then applying a right-exact functor

$$\mathscr{F}(L) \to \mathscr{F}(M) \to \mathscr{F}(N) \to 0$$

will give an exact sequence, which can be stretched out to form a long exact sequence using the derived functors:

$$\begin{array}{ccccccc}
\cdots & \longrightarrow & L_2\mathscr{F}(L) & \longrightarrow & L_2\mathscr{F}(M) & \longrightarrow & L_2\mathscr{F}(N) \\
& \overset{\delta_2}{\hookrightarrow} & L_1\mathscr{F}(L) & \longrightarrow & L_1\mathscr{F}(M) & \longrightarrow & L_1\mathscr{F}(N) \\
& \overset{\delta_1}{\hookrightarrow} & \mathscr{F}(L) & \longrightarrow & \mathscr{F}(M) & \longrightarrow & \mathscr{F}(N) \longrightarrow 0
\end{array}$$

In this way, $\mathbf{L}_1\mathscr{F}$ measures the extent to which $\mathscr{F}$ fails to be left-exact, and each progressive $\mathbf{L}_i\mathscr{F}$ gives further measurement, further information, about this failure. When in a geometrical setting, this failure is often thought of as some form of obstruction (famously, in algebraic topology, this obstruction is interpreted as "'holes", in K-theory).

Similarly, $R^0\mathscr{F}$ is naturally isomorphic to $\mathscr{F}$ if $\mathscr{F}$ is left-exact and the right-derived functors fit into the diagram:

$$\begin{array}{ccccccc}
0 & \longrightarrow & \mathscr{F}(L) & \longrightarrow & \mathscr{F}(M) & \longrightarrow & \mathscr{F}(N) \\
& \overset{\delta^0}{\hookrightarrow} & R^1\mathscr{F}(L) & \longrightarrow & R^1\mathscr{F}(M) & \longrightarrow & R^1\mathscr{F}(N) \\
& \overset{\delta^1}{\hookrightarrow} & R^2\mathscr{F}(L) & \longrightarrow & R^2\mathscr{F}(M) & \longrightarrow & R^2\mathscr{F}(N) \longrightarrow \cdots
\end{array}$$

Thus, we have successfully captured the cohomological information that a functor may provide!

Acyclic Functors

There still remain some questions to be answered, one that was mentioned was that instead of using a projective resolution for Tor, a flat resolution may be used instead and give the same answer.

Definition 56.3.14: Acyclic Functor

Let $\mathscr{F}$ be an additive functor. An object M of $\mathbf{A}$ is *$\mathscr{F}$-acyclic* (with respect to left-derived functors) if $\mathbf{L}_i\mathscr{F}(M) = 0$ for all $i \neq 0$.

A left exact functor such as $\mathrm{Hom}_R(N, -)$ is derived through injective resolutions, and the objects on which its right-derived functors vanish can take the place of injectives in that computation (theorem 56.3.18 below).

Definition 56.3.15: Acyclic for a Left-Exact Functor

Let $\mathscr{F}: \mathbf{A} \to \mathbf{B}$ be a left exact additive functor between abelian categories, with $\mathbf{A}$ having enough injectives. An object M of $\mathbf{A}$ is *$\mathscr{F}$-acyclic* if $R^i\mathscr{F}(M) = 0$ for all $i \geq 1$. Injective objects are $\mathscr{F}$-acyclic for every left exact $\mathscr{F}$, since an injective I is its own injective resolution, with I in degree 0 and zero elsewhere.

Projectives are acyclic for every right-exact functor in the sense of definition 56.3.14, and injectives for every left-exact functor in the sense of definition 56.3.15, but such a functor may admit other acyclic objects.

Example 56.3.16: Functor-acyclic Objects

Let R be a commutative ring. Recall that an R-module M is *flat* if $- \otimes_R M$ is exact (equivalently, by symmetry of $\otimes$ that $M \otimes_R -$ is exact). Then flat modules are *acyclic* with respect to tensor products, namely if N is flat:

$$\operatorname{Tor}_R^i(M, N) = 0 \qquad \forall i \neq 0,\ \forall M$$

and symmetrically if M is flat. Thus, flat modules are $(- \otimes_R N)$-acyclic for all modules N.

What shall be built up to now is that $\mathscr{F}$-acyclic resolutions can be used to compute $\mathbf{L}_i\mathscr{F}$.

Theorem 56.3.17: Derived Functors And Acyclic Functors

Let $\mathscr{F} : \mathbf{A} \to \mathbf{B}$ be a right-exact functor of abelian categories where $\mathbf{A}$ has enough projectives. Let $A^\bullet$ be a resolution of M where each A^i is $\mathscr{F}$-acyclic. Then for all i:

$$\mathbf{L}_i\mathscr{F}(M) \cong H^{-i}(\mathrm{Ch}(\mathscr{F})(A^\bullet))$$

Note that if each A^i is projective, the statement follows by definition.

***Proof*:**

The 0th and -1th position will be computed directly, and each successive position comes from induction. Take the exact sequence

$$A^{-1} \to A^0 \to M \to 0$$

which creates another exact sequence in $\mathbf{B}$ after applying the right-exact functor $\mathscr{F}$:

$$\mathscr{F}(A^{-1}) \to \mathscr{F}(A^0) \to \mathscr{F}(M) \to 0$$

Then:

$$H^0(\mathrm{Ch}(\mathscr{F})(A^\bullet)) \cong \mathscr{F}(M) \cong \mathbf{L}_0\mathscr{F}(M)$$

Now, if K is the kernel of $A^0 \to M$, then we have a short exact sequence:

$$0 \to K \to A^0 \to M \to 0$$

Thus applying the left-derived functors we form the long exact sequence:

$$\mathbf{L}_1\mathscr{F}(A^0) \to \mathbf{L}_1\mathscr{F}(M) \to \mathscr{F}(K) \to \mathscr{F}(A^0) \to \mathscr{F}(M) \to 0$$

Since A^0 is acyclic, $L_1\mathscr{F}(A^0) = 0$, hence by exactness

$$\mathbf{L}_1\mathscr{F}(M) \cong \ker(\mathscr{F}(K) \to \mathscr{F}(A^0)) \cong H^{-1}(\mathrm{Ch}(\mathscr{F})(A^\bullet))$$

where the last isomorphism holds because K is the cokernel of $A^{-2} \to A^{-1}$, so that right exactness makes $\mathscr{F}(K)$ the cokernel of $\mathscr{F}(A^{-2}) \to \mathscr{F}(A^{-1})$, and $\mathscr{F}(A^{-1}) \to \mathscr{F}(A^0)$ factors through it. For the rest, we do induction on $i \geq 2$, assuming the statement for every object of $\mathbf{A}$, every $\mathscr{F}$-acyclic resolution of it, and every index below i. Truncating and shifting $A^\bullet$ so that A^{-1} is in the 0 degree:

$$\cdots \to A^{-3} \to A^{-2} \to A^{-1} \to 0 \to \cdots$$

we get an $\mathscr{F}$-acyclic resolution of K, and so by the induction hypothesis $\mathbf{L}_{i-1}\mathscr{F}(K)$ can be computed by applying $\mathrm{Ch}(\mathscr{F})$ to the complex and taking cohomology, namely:

$$\mathbf{L}_{i-1}\mathscr{F}(K) \cong H^{-i}(\mathrm{Ch}(\mathscr{F})(A^\bullet))$$

On the other hand, the other terms in the long exact sequence obtained using the left derived functors gives:

$$\cdots \to \mathbf{L}_i\mathscr{F}(A^0) \to L_i\mathscr{F}(M) \to \mathbf{L}_{i-1}\mathscr{F}(K) \to \mathbf{L}_{i-1}\mathscr{F}(A^0) \to \cdots$$

since A^0 is $\mathscr{F}$-acyclic and $i > 1$, we get:

$$\mathbf{L}_i\mathscr{F}(M) \cong \mathbf{L}_{i-1}\mathscr{F}(K)$$

giving the desired result.

Thus, for the Tor functor, a flat resolution computes the left-derived functors. Since $\mathscr{F}$-acyclic objects suffice in the computation, one can imagine that there is no need for $\mathbf{A}$ to have enough projectives to compute it. This is indeed the case, given that $\mathbf{A}$ has enough $\mathscr{F}$-acyclic objects (this is an exercise in Aluffi, 8.14, with bifunctors).

Sheaf cohomology is the right-derived functor of global sections, and it is computed in practice from resolutions by flasque sheaves, or by fine sheaves on a paracompact space, which are acyclic for global sections and need not be injective. The dimension shift of the last proof, run with injective resolutions, justifies this for every left exact functor.

Theorem 56.3.18: Acyclic Resolutions Compute Right-Derived Functors

Let $\mathscr{F}\colon \mathbf{A} \to \mathbf{B}$ be a left exact additive functor between abelian categories, with $\mathbf{A}$ having enough injectives. Let M be an object of $\mathbf{A}$ and

$$0 \to M \xrightarrow{\eta} A^0 \xrightarrow{d^0} A^1 \xrightarrow{d^1} A^2 \to \cdots$$

an exact sequence in which every A^i is $\mathscr{F}$-acyclic, and write $A^\bullet$ for the complex $A^0 \to A^1 \to \cdots$ with A^0 in degree 0. Then for every $i \geq 0$

$$R^i\mathscr{F}(M) \cong H^i\big(\mathscr{F}(A^\bullet)\big)$$

The isomorphism is natural: for a morphism of two such sequences, with component $\varphi\colon M \to M'$ on the resolved objects, it carries $R^i\mathscr{F}(\varphi)$ to the map induced on $H^i(\mathscr{F}(A^\bullet))$.

***Proof*:**

Step 1: Degree zero. Left exactness of $\mathscr{F}$, applied to the exact sequence $0 \to M \to A^0 \to A^1$, makes $0 \to \mathscr{F}(M) \to \mathscr{F}(A^0) \to \mathscr{F}(A^1)$ exact, so $\mathscr{F}(\eta)$ identifies $\mathscr{F}(M)$ with $H^0(\mathscr{F}(A^\bullet))$. There is a natural isomorphism $R^0\mathscr{F} \cong \mathscr{F}$, by proposition 56.3.13 applied to $\mathscr{F}^{op}$ as in the proof of corollary 56.3.12. This is the case $i = 0$.

Step 2: The dimension shift. Let K be the cokernel of η, which d^0 identifies with $\ker(d^1)$ by exactness. Corollary 56.3.12, applied to $0 \to M \to A^0 \to K \to 0$, gives an exact sequence

$$\mathscr{F}(A^0) \to \mathscr{F}(K) \xrightarrow{\delta^0} R^1\mathscr{F}(M) \to R^1\mathscr{F}(A^0) = 0$$

after the identifications $R^0\mathscr{F} \cong \mathscr{F}$ of Step 1. For $i \geq 2$ the same long exact sequence places $\delta^{i-1}\colon R^{i-1}\mathscr{F}(K) \to R^i\mathscr{F}(M)$ between $R^{i-1}\mathscr{F}(A^0) = 0$ and $R^i\mathscr{F}(A^0) = 0$, so δ^{i-1} is an isomorphism.

Step 3: Degree one. The sequence $0 \to K \to A^1 \to A^2$ is exact, so left exactness identifies $\mathscr{F}(K)$ with $\ker(\mathscr{F}(d^1))$, and $\mathscr{F}(d^0)$ factors as $\mathscr{F}(A^0) \to \mathscr{F}(K) \to \mathscr{F}(A^1)$. Hence the cokernel of $\mathscr{F}(A^0) \to \mathscr{F}(K)$ is $\ker(\mathscr{F}(d^1))/\mathrm{im}(\mathscr{F}(d^0)) = H^1(\mathscr{F}(A^\bullet))$, and Step 2 gives $R^1\mathscr{F}(M) \cong H^1(\mathscr{F}(A^\bullet))$.

Step 4: Induction. The sequence $0 \to K \to A^1 \to A^2 \to \cdots$ is an exact sequence of the same kind for K, with the complex $A^{\bullet+1}$ whose degree-j term is A^{j+1}. Let $i \geq 2$ and assume the theorem in degree $i-1$ for every object and every such sequence. Then $R^{i-1}\mathscr{F}(K) \cong H^{i-1}(\mathscr{F}(A^{\bullet+1})) = H^i(\mathscr{F}(A^\bullet))$, the equality because, for $i - 1 \geq 1$, both are computed from the maps $\mathscr{F}(A^{i-1}) \to \mathscr{F}(A^i) \to \mathscr{F}(A^{i+1})$. Composing with the isomorphism δ^{i-1} of Step 2 gives $R^i\mathscr{F}(M) \cong H^i(\mathscr{F}(A^\bullet))$.

Step 5: Naturality. A morphism of two such sequences induces a morphism between the short exact sequences of Step 2 and a morphism between the sequences for K and K'. The identifications of Step 1, the connecting morphisms, by the functoriality clause of corollary 56.3.12, and the identifications of kernels and cokernels in Step 3 all commute with the induced maps. So the induction carries naturality from each degree to the next, completing the proof.

56.4 δ-Functors and Grothendieck's Effaceability Criterion

The right-derived functors of section 56.3 are built from an injective resolution, and the resolution is a choice. The construction does not depend on that choice, but two constructions that look nothing alike cannot be compared by inspecting resolutions, and comparisons of that kind are what the theory is used for. Grothendieck's answer, in the 1957 Tôhoku paper, is to axiomatize what the derived functors do rather than how they are made. What they do is corollary 56.3.12: a family of functors $(T^i)_{i\geq 0}$ turns each short exact sequence into a long exact sequence, compatibly with morphisms of short exact sequences. A family with that structure is a δ-functor.

The two axioms do not determine the higher terms from the degree-zero one, as example 56.4.2 below shows. What determines them is a universal property inside the category of δ-functors, and a universal δ-functor is determined by its degree-zero term alone. That property cannot be checked by inspection, and this is where the criterion of the section enters: a δ-functor whose positive-degree terms are killed by embedding each object into a larger one is universal. The hypothesis, effaceability, asks for one embedding per object, and it is what makes two theories agreeing in degree zero isomorphic in every degree.

Definition 56.4.1: δ-Functor

Let $\mathcal{A}$ and $\mathcal{B}$ be abelian categories. A *δ-functor* T from $\mathcal{A}$ to $\mathcal{B}$ consists of a family $(T^i)_{i\geq 0}$ of additive functors $T^i\colon \mathcal{A}\to\mathcal{B}$ together with, for every short exact sequence

$$\xi\colon \qquad 0\to A'\xrightarrow{\alpha} A\xrightarrow{\beta} A''\to 0$$

in $\mathcal{A}$ and every $i\geq 0$, a morphism $\delta^i_\xi\colon T^i(A'')\to T^{i+1}(A')$ in $\mathcal{B}$, subject to two conditions.

1. (Exactness.) For every such ξ the sequence

$$\begin{aligned}0\to T^0(A')\to T^0(A)\to T^0(A'')\xrightarrow{\delta^0_\xi} T^1(A')\to T^1(A)\to T^1(A'')\\ \xrightarrow{\delta^1_\xi} T^2(A')\to T^2(A)\to\cdots\end{aligned}$$

   is exact, the unlabelled arrows being $T^i(\alpha)$ and $T^i(\beta)$.

2. (Naturality of δ.) For every commutative diagram with exact rows

$$\begin{array}{cccccccccc}\xi\colon & 0 & \longrightarrow & A' & \xrightarrow{\alpha} & A & \xrightarrow{\beta} & A'' & \longrightarrow & 0\\ & & & \downarrow{\scriptstyle g'} & & \downarrow{\scriptstyle g} & & \downarrow{\scriptstyle g''} & & \\ \eta\colon & 0 & \longrightarrow & B' & \longrightarrow & B & \longrightarrow & B'' & \longrightarrow & 0\end{array}$$

   and every $i\geq 0$, the square

$$\begin{array}{ccc}T^i(A'') & \xrightarrow{\delta^i_\xi} & T^{i+1}(A')\\ \downarrow{\scriptstyle T^i(g'')} & & \downarrow{\scriptstyle T^{i+1}(g')}\\ T^i(B'') & \xrightarrow[\delta^i_\eta]{} & T^{i+1}(B')\end{array}$$

   commutes.

Condition (1) has an immediate consequence: its opening segment $0\to T^0(A')\to T^0(A)\to T^0(A'')$ says that T^0 is left exact, in the sense fixed by proposition 17.2.1(2): a short exact sequence is carried to an exact sequence of that three-term shape. A δ-functor is therefore a left exact functor together with a chosen way of continuing its exact sequence to the right, and the question the section answers is how much freedom that continuation has. The indexing above is the cohomological one, matching corollary 56.3.12. The homological variant, in which the connecting morphisms lower the index, is this notion transported to the opposite categories, and only the cohomological form is written out below.

Example 56.4.2: The Constant δ-Functor on Ab

Take $\mathcal{A}=\mathcal{B}=\mathbf{Ab}$, set $T^i=\mathrm{id}_{\mathbf{Ab}}$ for every $i\geq 0$, and let every δ^i_ξ be the zero morphism. This is a δ-functor. Each T^i is additive, and for $\xi\colon 0\to A'\to A\to A''\to 0$ the sequence of condition (1) reads

$$0\to A'\to A\to A''\xrightarrow{0} A'\to A\to A''\xrightarrow{0} A'\to\cdots$$

> Exactness at the first A' is injectivity of $A' \to A$, and at each copy of A it is exactness of ξ. At each copy of A'' the image of $A \to A''$ is all of A'' by surjectivity, and the kernel of the zero map out of A'' is also all of A''. At each copy of A' after the first, the image of the zero map is 0, which is the kernel of the monomorphism $A' \to A$. Condition (2) holds because both composites in its square are zero.

The example uses no resolutions and no derived functors, and it shows that conditions (1) and (2) do not determine $(T^i)_{i>0}$ from T^0. Indeed the family with $T^0 = \mathrm{id}_{\mathbf{Ab}}$, with $T^i = 0$ for $i > 0$ and with all connecting morphisms zero, is a second δ-functor on $\mathbf{Ab}$ with the same degree-zero term: its long exact sequence is $0 \to A' \to A \to A'' \to 0 \to 0 \to \cdots$, exact at A'' because $A \to A''$ is an epimorphism. Pinning the higher terms down needs a comparison between δ-functors, so morphisms come first.

Definition 56.4.3: Morphism of δ-Functors

Let S and T be δ-functors from $\mathcal{A}$ to $\mathcal{B}$, with connecting morphisms written δ_S and δ_T. A *morphism of δ-functors* $f\colon T \to S$ is a family $(f^i)_{i\geq 0}$ of natural transformations $f^i\colon T^i \Rightarrow S^i$ such that for every short exact sequence $\xi\colon 0 \to A' \to A \to A'' \to 0$ and every $i \geq 0$ the square

$$\begin{array}{ccc} T^i(A'') & \xrightarrow{\delta^i_{T,\xi}} & T^{i+1}(A') \\ {\scriptstyle f^i_{A''}}\downarrow & & \downarrow{\scriptstyle f^{i+1}_{A'}} \\ S^i(A'') & \xrightarrow[\delta^i_{S,\xi}]{} & S^{i+1}(A') \end{array}$$

commutes.

Degreewise composition of two morphisms of δ-functors is again one, since the two commuting squares stack, and the identity natural transformations form a morphism, so the δ-functors from $\mathcal{A}$ to $\mathcal{B}$ form a category. The universal property below is initiality in that category among the δ-functors with a prescribed degree-zero term.

Definition 56.4.4: Universal δ-Functor

A δ-functor T from $\mathcal{A}$ to $\mathcal{B}$ is *universal* if for every δ-functor S from $\mathcal{A}$ to $\mathcal{B}$ and every natural transformation $\varphi\colon T^0 \Rightarrow S^0$ there is exactly one morphism of δ-functors $f\colon T \to S$ with $f^0 = \varphi$.

The quantifier runs over all δ-functors S and all φ, and the morphism produced goes out of T. So universality of T says that any competing family carrying long exact sequences receives a canonical comparison from T, determined by its degree-zero component alone.

Example 56.4.2 is not universal, and the failure is in uniqueness rather than existence. Take $S = T$ there and $\varphi = \mathrm{id}_{T^0}$. The identity morphism of T extends φ, and so does the family that is the identity in degree zero and multiplication by 2 in every positive degree: multiplication by 2 is a natural transformation $\mathrm{id}_{\mathbf{Ab}} \Rightarrow \mathrm{id}_{\mathbf{Ab}}$ because every homomorphism of abelian groups commutes with it, and the square of definition 56.4.3 commutes because all the connecting morphisms are zero. The two extensions differ on $T^1(\mathbb{Z}) = \mathbb{Z}$.

Definition 56.4.5: Effaceable Functor

An additive functor $T\colon \mathcal{A} \to \mathcal{B}$ is *effaceable* if for every object A of $\mathcal{A}$ there is a monomorphism $u\colon A \hookrightarrow M$ in $\mathcal{A}$ with $T(u) = 0$. Such a u is said to *efface* T at A. A δ-functor $(T^i)_{i\geq 0}$ is *effaceable in positive degrees* if T^i is effaceable for every $i > 0$.

The condition asks that the morphism $T^i(u)$ vanish, not that the object $T^i(M)$ vanish. The second is strictly stronger, and it is what happens whenever M can be taken injective, but the proof below uses only the first. Nothing in the definition asks for a functorial choice of u either: one monomorphism per object is enough, and different objects may be effaced by embeddings with no relation to each other.

The criterion has a hypothesis that is checked object by object and a conclusion about every δ-functor at once.

Theorem 56.4.6: An Effaceable δ-Functor Is Universal

Let $\mathcal{A}$ and $\mathcal{B}$ be abelian categories and let $T = (T^i)_{i\geq 0}$ be a δ-functor from $\mathcal{A}$ to $\mathcal{B}$ that is effaceable in positive degrees. Then T is universal.

***Proof*:**
Let S be a δ-functor from $\mathcal{A}$ to $\mathcal{B}$ and $\varphi\colon T^0 \Rightarrow S^0$ a natural transformation. Set $f^0 := \varphi$ and construct f^{n+1} from f^n by induction on $n \geq 0$, the induction hypothesis being that $f^n\colon T^n \Rightarrow S^n$ is a natural transformation. Two facts about abelian categories are used repeatedly, both read off theorem 55.1.9: applied to an epimorphism ϵ, that theorem factors ϵ through $\operatorname{coker}(\ker \epsilon)$ by an isomorphism, so ϵ is a cokernel of its kernel; applied to a monomorphism μ, it factors μ through $\ker(\operatorname{coker}\mu)$ by an isomorphism, so μ is a kernel of its cokernel.

Step 1: Effacing short exact sequences. Fix $n \geq 0$ and an object A of $\mathcal{A}$, and let $u\colon A \to M$ be a monomorphism with $T^{n+1}(u) = 0$, which exists because T^{n+1} is effaceable. Put $N := \operatorname{coker} u$, so that

$$\xi_u\colon \qquad 0 \to A \xrightarrow{u} M \xrightarrow{v} N \to 0$$

is a short exact sequence. The relevant segment of the long exact sequence of T at ξ_u is

$$T^n(M) \xrightarrow{T^n(v)} T^n(N) \xrightarrow{\delta^n_{T,\xi_u}} T^{n+1}(A) \xrightarrow{T^{n+1}(u)} T^{n+1}(M)$$

The last morphism is zero, so exactness at $T^{n+1}(A)$ makes the image of δ^n_{T,ξ_u} all of $T^{n+1}(A)$, that is, δ^n_{T,ξ_u} is an epimorphism. Exactness at $T^n(N)$ identifies its kernel with the image of $T^n(v)$.

Step 2: The construction. Keep u and ξ_u, and consider $\delta^n_{S,\xi_u} \circ f^n_N\colon T^n(N) \to S^{n+1}(A)$. Naturality of f^n applied to v gives $f^n_N \circ T^n(v) = S^n(v) \circ f^n_M$, and $\delta^n_{S,\xi_u} \circ S^n(v) = 0$ because those two morphisms are consecutive in the long exact sequence of S at ξ_u. Hence $\delta^n_{S,\xi_u} \circ f^n_N \circ T^n(v) = 0$. Write $k\colon K \to T^n(N)$ for the kernel of δ^n_{T,ξ_u}, which by Step 1 is the image of $T^n(v)$. The induced morphism $T^n(M) \to K$ is an epimorphism (proposition 55.1.12), so the displayed vanishing gives $\delta^n_{S,\xi_u} \circ f^n_N \circ k = 0$. As δ^n_{T,ξ_u} is an epimorphism it is a cokernel of k, so there is exactly one

morphism

$$f^{n+1}_{A,u}\colon T^{n+1}(A) \longrightarrow S^{n+1}(A) \qquad \text{with} \qquad f^{n+1}_{A,u} \circ \delta^n_{T,\xi_u} = \delta^n_{S,\xi_u} \circ f^n_N$$

Step 3: Comparison of two effacements. Suppose given a commutative diagram with exact rows

$$\begin{array}{lccccccccc} \xi_u\colon & 0 & \longrightarrow & A & \xrightarrow{u} & M & \xrightarrow{v} & N & \longrightarrow & 0 \\ & & & \downarrow{\scriptstyle a} & & \downarrow & & \downarrow{\scriptstyle c} & & \\ \xi_w\colon & 0 & \longrightarrow & B & \xrightarrow{w} & P & \longrightarrow & Q & \longrightarrow & 0 \end{array}$$

in which $T^{n+1}(u) = 0$ and $T^{n+1}(w) = 0$. Then $S^{n+1}(a) \circ f^{n+1}_{A,u} = f^{n+1}_{B,w} \circ T^{n+1}(a)$. Since δ^n_{T,ξ_u} is an epimorphism, it is enough to check that the two sides agree after composing with it. For the first, Step 2, naturality of δ_S for the displayed morphism, and naturality of f^n applied to c give

$$S^{n+1}(a) f^{n+1}_{A,u} \delta^n_{T,\xi_u} = S^{n+1}(a) \delta^n_{S,\xi_u} f^n_N = \delta^n_{S,\xi_w} S^n(c) f^n_N = \delta^n_{S,\xi_w} f^n_Q T^n(c)$$

For the second, naturality of δ_T for the same morphism, followed by Step 2 for w, gives

$$f^{n+1}_{B,w} T^{n+1}(a) \delta^n_{T,\xi_u} = f^{n+1}_{B,w} \delta^n_{T,\xi_w} T^n(c) = \delta^n_{S,\xi_w} f^n_Q T^n(c)$$

The two agree.

Step 4: Independence of the effacement. Let $u\colon A \to M$ and $u'\colon A \to M'$ both efface T^{n+1} at A. The morphism $(u, u')\colon A \to M \oplus M'$ is a monomorphism, because composing it with the projection to M gives u. Writing ι_M and $\iota_{M'}$ for the two inclusions, $(u, u') = \iota_M u + \iota_{M'} u'$, so additivity of T^{n+1} gives

$$T^{n+1}\big((u, u')\big) = T^{n+1}(\iota_M) T^{n+1}(u) + T^{n+1}(\iota_{M'}) T^{n+1}(u') = 0$$

and (u, u') effaces T^{n+1} at A as well. The projection $M \oplus M' \to M$ carries (u, u') to u, hence induces a morphism from the effacing short exact sequence of (u, u') to that of u whose left-hand vertical map is id_A. Step 3 with $a = \mathrm{id}_A$ then gives $f^{n+1}_{A,(u,u')} = f^{n+1}_{A,u}$, and the other projection gives $f^{n+1}_{A,(u,u')} = f^{n+1}_{A,u'}$ in the same way. So the morphism of Step 2 does not depend on the effacement, and it is written f^{n+1}_A from now on.

Step 5: Naturality. Let $g\colon A \to B$ be a morphism of $\mathcal{A}$, and choose effacements $u\colon A \to M$ of T^{n+1} at A and $w\colon B \to P$ at B. The morphism $(u, wg)\colon A \to M \oplus P$ is a monomorphism, again because its composite with the projection to M is u, and

$$T^{n+1}\big((u, wg)\big) = T^{n+1}(\iota_M) T^{n+1}(u) + T^{n+1}(\iota_P) T^{n+1}(w) T^{n+1}(g) = 0$$

since $T^{n+1}(u) = 0$ and $T^{n+1}(w) = 0$. So (u, wg) effaces T^{n+1} at A. The projection $M \oplus P \to P$ carries (u, wg) to $wg = w \circ g$, so it induces a morphism from the effacing short exact sequence of (u, wg) to that of w whose left-hand vertical map is g. Step 3 gives $S^{n+1}(g) \circ f^{n+1}_{A,(u,wg)} = f^{n+1}_{B,w} \circ T^{n+1}(g)$, and by Step 4 the two subscripted morphisms are f^{n+1}_A and f^{n+1}_B. Hence f^{n+1} is a natural transformation $T^{n+1} \Rightarrow S^{n+1}$, which is the induction hypothesis one degree up.

Step 6: Compatibility with every connecting morphism. Let $\xi\colon 0 \to A \xrightarrow{a} M \xrightarrow{b} N \to 0$ be an arbitrary short exact sequence, choose an effacement $u\colon A \to E$ of T^{n+1} at A, and form the pushout of a along u,

$$P := \operatorname{coker}\Big(A \xrightarrow{(a,-u)} M \oplus E\Big)$$

with structure morphisms $m\colon M \to P$ and $e\colon E \to P$, so that $ma = eu$.

The morphism m is a monomorphism. Let $k\colon K \to M$ satisfy $mk = 0$. Then the composite of $(k,0)\colon K \to M \oplus E$ with the cokernel morphism $\pi\colon M \oplus E \to P$ vanishes, so $(k,0)$ factors through $\ker \pi$. Now $(a,-u)$ is a monomorphism, because its composite with the projection to M is a, and π is its cokernel, so $(a,-u)$ is a kernel of π. Hence there is $h\colon K \to A$ with $ah = k$ and $-uh = 0$. As u is a monomorphism $h = 0$, and therefore $k = 0$. So $0 \to M$ is a kernel of m, and lemma 55.1.4(1) makes m a monomorphism.

Consequently $a_1 := ma = eu$ is a monomorphism, being a composite of two, and $T^{n+1}(a_1) = T^{n+1}(e)T^{n+1}(u) = 0$. So

$$\xi_1\colon \qquad 0 \to A \xrightarrow{a_1} P \to \operatorname{coker}(a_1) \to 0$$

effaces T^{n+1} at A, and the identity of A together with m and the induced morphism $\gamma\colon N \to \operatorname{coker}(a_1)$ on cokernels is a morphism of short exact sequences $\xi \to \xi_1$. Steps 2 and 4 give $f_A^{n+1} \circ \delta^n_{T,\xi_1} = \delta^n_{S,\xi_1} \circ f^n_{\operatorname{coker}(a_1)}$, while naturality of δ_T and of δ_S for that morphism gives $\delta^n_{T,\xi_1} \circ T^n(\gamma) = \delta^n_{T,\xi}$ and $\delta^n_{S,\xi_1} \circ S^n(\gamma) = \delta^n_{S,\xi}$, since that morphism is the identity on A. Therefore

$$f_A^{n+1}\delta^n_{T,\xi} = f_A^{n+1}\delta^n_{T,\xi_1}T^n(\gamma) = \delta^n_{S,\xi_1}f^n_{\operatorname{coker}(a_1)}T^n(\gamma) = \delta^n_{S,\xi_1}S^n(\gamma)f^n_N = \delta^n_{S,\xi}f^n_N$$

the third equality being naturality of f^n applied to γ. The induction therefore produces a family $f = (f^i)_{i\geq 0}$ of natural transformations satisfying the condition of definition 56.4.3, that is, a morphism of δ-functors with $f^0 = \varphi$.

Step 7: Uniqueness. Let f and g be morphisms of δ-functors $T \to S$ with $f^0 = g^0 = \varphi$, and suppose $f^j = g^j$ for all $j \leq n$. Given an object A, choose an effacement $u\colon A \to M$ of T^{n+1} at A and form ξ_u as in Step 1. Both f_A^{n+1} and g_A^{n+1} satisfy $h \circ \delta^n_{T,\xi_u} = \delta^n_{S,\xi_u} \circ f^n_N$, by definition 56.4.3 and the induction hypothesis, and δ^n_{T,ξ_u} is an epimorphism by Step 1, so $f_A^{n+1} = g_A^{n+1}$. Hence $f = g$, and T is universal, as we sought to show.

The hypothesis is one embedding per object and per positive degree, and the conclusion quantifies over every δ-functor at once. Step 1 is what makes that exchange possible: an effacing embedding makes δ^n an epimorphism, so a morphism out of $T^{n+1}(A)$ is pinned down by its effect on T^n of the quotient, one degree lower. Without effaceability the induction has nothing to descend on, and example 56.4.2 is the failing case: there $T^1 = \mathrm{id}_{\mathbf{Ab}}$, so a monomorphism $u\colon A \to M$ has $T^1(u) = u$, which vanishes only when $A = 0$.

The use of universality is that it turns a comparison in degree zero into a comparison in every degree.

Corollary 56.4.7: A Universal δ-Functor Is Determined by Its Degree-Zero Part

Let S and T be universal δ-functors from $\mathcal{A}$ to $\mathcal{B}$ and let $\varphi\colon T^0 \Rightarrow S^0$ be a natural isomorphism. Then the unique morphism of δ-functors $f\colon T \to S$ with $f^0 = \varphi$ has every f^i a natural isomorphism. Equivalently, *any* morphism of δ-functors between universal δ-functors whose degree-zero component is a natural isomorphism is itself an isomorphism. In particular, a universal δ-functor with a prescribed degree-zero term is unique up to a unique isomorphism of δ-functors.

***Proof*:**
Universality of T gives a unique morphism $f\colon T \to S$ with $f^0 = \varphi$, and universality of S a unique morphism $g\colon S \to T$ with $g^0 = \varphi^{-1}$. The degreewise composite $g \circ f\colon T \to T$ is a morphism of δ-functors with $(g \circ f)^0 = \varphi^{-1} \circ \varphi = \mathrm{id}_{T^0}$, and id_T is another one. Applying definition 56.4.4 to T with S taken to be T itself and φ taken to be id_{T^0}, the two coincide, so $g \circ f = \mathrm{id}_T$. The same argument in S gives $f \circ g = \mathrm{id}_S$. Hence each f^i is a natural isomorphism with inverse g^i. For the second sentence of the statement, a morphism of δ-functors $h\colon T \to S$ whose component h^0 is a natural isomorphism is, by universality of T, the unique morphism extending h^0, so it is the f just treated with $\varphi = h^0$, completing the proof.

The corollary is what makes universality usable: to identify two families of functors in all degrees it is enough to identify them in degree zero, provided both are universal. The criterion of theorem 56.4.6 is what verifies that proviso, and the family it applies to most often is the one built in section 56.3.

Corollary 56.4.8: The Right-Derived Functors Form a Universal δ-Functor

Let $\mathcal{A}$ be an abelian category with enough injectives, let $\mathcal{B}$ be an abelian category, and let $F\colon \mathcal{A} \to \mathcal{B}$ be an additive functor. Then:

1. the family $(R^iF)_{i\geq 0}$, equipped with the connecting morphisms of corollary 56.3.12, is a δ-functor from $\mathcal{A}$ to $\mathcal{B}$;
2. $R^iF(I) = 0$ for every injective object I of $\mathcal{A}$ and every $i > 0$; consequently $(R^iF)_{i\geq 0}$ is effaceable in positive degrees and therefore universal;
3. if F is left exact then R^0F is naturally isomorphic to F, and $(R^iF)_{i\geq 0}$ is then, up to a unique isomorphism of δ-functors, the only universal δ-functor from $\mathcal{A}$ to $\mathcal{B}$ whose degree-zero term is naturally isomorphic to F.

***Proof*:**

1. Each R^iF is additive. Let $\varphi, \psi\colon A \to B$, and choose injective resolutions $A \to I^\bullet$ and $B \to J^\bullet$. Applying proposition 56.2.15 in the opposite category, φ and ψ lift to morphisms of resolutions $\varphi^\bullet, \psi^\bullet\colon I^\bullet \to J^\bullet$, unique up to homotopy, and $\varphi^\bullet + \psi^\bullet$ is then a lift of $\varphi + \psi$. Since F is additive, $\mathrm{Ch}(F)(\varphi^\bullet + \psi^\bullet) = \mathrm{Ch}(F)(\varphi^\bullet) + \mathrm{Ch}(F)(\psi^\bullet)$ degreewise, and H^i carries a sum of morphisms of complexes to the sum of the induced morphisms, so $R^iF(\varphi + \psi) = R^iF(\varphi) + R^iF(\psi)$. Condition (1) of definition 56.4.1 is the exactness assertion of corollary 56.3.12 together with its identification of the unlabelled arrows as $R^iF(\alpha)$ and $R^iF(\beta)$, and condition (2) is its functoriality in the short exact sequence.

2. Let I be injective. The complex with I in degree 0 and 0 elsewhere, augmented by id_I, is an injective resolution of I, so $R^iF(I) = H^i(F(I) \to 0 \to \cdots)$, which is 0 for $i > 0$. Given an object A and $i > 0$, enough injectives gives a monomorphism $A \hookrightarrow I$ with I injective (definition 56.2.3(2)), and the induced morphism $R^iF(A) \to R^iF(I) = 0$ is zero because its target is. So R^iF is effaceable for every $i > 0$, and theorem 56.4.6 applies.

3. Let $0 \to A \xrightarrow{\varepsilon_A} I^0 \xrightarrow{d^0} I^1 \to \cdots$ be an injective resolution. Left exactness is a hypothesis about short exact sequences, and $0 \to A \to I^0 \xrightarrow{d^0} I^1$ is not one, so the passage to $\ker F(d^0)$ takes two steps. First, F preserves monomorphisms: a monomorphism $\nu\colon X \to Y$ is a kernel of its cokernel (theorem 55.1.9), so $0 \to X \xrightarrow{\nu} Y \to \operatorname{coker}\nu \to 0$ is short exact and left exactness makes $F(\nu)$ a monomorphism. Second, factor $d^0 = \mu \circ p$ with $p\colon I^0 \to \operatorname{im} d^0$ an epimorphism and $\mu\colon \operatorname{im} d^0 \to I^1$ a monomorphism (theorem 55.1.9). Exactness of the resolution at A and at I^0 makes ε_A a kernel of d^0, hence of p since μ is a monomorphism, so $0 \to A \xrightarrow{\varepsilon_A} I^0 \xrightarrow{p} \operatorname{im} d^0 \to 0$ is short exact and $0 \to F(A) \to F(I^0) \xrightarrow{F(p)} F(\operatorname{im} d^0)$ is exact. Since $F(\mu)$ is a monomorphism, $\ker F(d^0) = \ker F(p)$, and that kernel is the image of the monomorphism $F(\varepsilon_A)$. Hence $F(A) \cong \ker F(d^0) = H^0\big(\mathrm{Ch}(F)(I^\bullet)\big) = R^0F(A)$, the isomorphism being induced by $F(\varepsilon_A)$. For a morphism $\varphi\colon A \to B$ and a lift $\varphi^\bullet$ of φ to the chosen resolutions, the augmentation square $\varepsilon_B \circ \varphi = \varphi^0 \circ \varepsilon_A$ gives $F(\varepsilon_B)F(\varphi) = F(\varphi^0)F(\varepsilon_A)$, and $R^0F(\varphi)$ is the restriction of $F(\varphi^0)$ to the two kernels, so the isomorphism is natural in A. For the final clause, $(R^iF)_{i\geq 0}$ is universal by (2) and its degree-zero term is F up to the isomorphism just produced, so corollary 56.4.7 gives the uniqueness, completing the proof.

Part (3) is the form in which the corollary is applied: a family of functors carrying long exact sequences, agreeing with F in degree zero and effaceable in positive degrees, *is* the family of right-derived functors of F, by a canonical isomorphism compatible with every connecting morphism. The converse question, whether universality forces effaceability, has an affirmative answer as soon as enough injectives are available.

Corollary 56.4.9: Universality and Effaceability Agree When There Are Enough Injectives

Let $\mathcal{A}$ be an abelian category with enough injectives, let $\mathcal{B}$ be an abelian category, and let T be a δ-functor from $\mathcal{A}$ to $\mathcal{B}$. Then the following are equivalent:

1. T is universal;
2. $T^i(I) = 0$ for every injective object I of $\mathcal{A}$ and every $i > 0$;
3. T^i is effaceable for every $i > 0$.

***Proof*:**
That (3) implies (1) is theorem 56.4.6. For (1) implies (2), let T be universal. Condition (1) of definition 56.4.1 makes T^0 left exact, so by corollary 56.4.8(2) and (3) the family $(R^iT^0)_{i\geq 0}$ is a universal δ-functor with R^0T^0 naturally isomorphic to T^0. Both T and $(R^iT^0)_{i\geq 0}$ are universal and their degree-zero terms are naturally isomorphic, so corollary 56.4.7 gives an isomorphism of δ-functors $T \cong (R^iT^0)_{i\geq 0}$. For I injective and $i > 0$ this gives $T^i(I) \cong R^iT^0(I) = 0$ by corollary 56.4.8(2). For (2) implies (3), let $i > 0$ and let A be an object. Enough injectives gives

a monomorphism $A \hookrightarrow I$ with I injective, and $T^i(A) \to T^i(I) = 0$ is zero because its target is. Hence T^i is effaceable, completing the proof.

A worked case shows the two corollaries, and it can be carried out to the end because the functor below has an injective resolution of length one available at every object.

Example 56.4.10: The δ-Functor $\operatorname{Ext}^\bullet_{\mathbb{Z}}(\mathbb{Z}/n, -)$

Fix an integer $n \geq 1$ and let $F = \operatorname{Hom}_{\mathbb{Z}}(\mathbb{Z}/n, -)\colon \mathbf{Ab} \to \mathbf{Ab}$, which is left exact. The category $\mathbf{Ab}$ is $\mathbb{Z}$-$\mathbf{Mod}$ and has enough injectives by example 56.2.2(4), and $R^iF = \operatorname{Ext}^i_{\mathbb{Z}}(\mathbb{Z}/n, -)$ by example 56.3.6(2), so corollary 56.4.8 makes $\big(\operatorname{Ext}^i_{\mathbb{Z}}(\mathbb{Z}/n, -)\big)_{i\geq 0}$ a universal δ-functor whose degree-zero term is naturally isomorphic to F.

Its values can be written down. By theorem 17.3.5(2), applied to the principal ideal domain $\mathbb{Z}$, an abelian group is injective if and only if it is divisible. Every abelian group embeds in a divisible one: write $A = L/K$ with L the free abelian group on the underlying set of A, note that $L \subseteq L \otimes_{\mathbb{Z}} \mathbb{Q}$ and that $K \subseteq L$, and observe that the kernel of $A = L/K \to (L \otimes_{\mathbb{Z}} \mathbb{Q})/K$ consists of the classes of elements of L that lie in K, hence is zero, while the target is a quotient of the divisible group $L \otimes_{\mathbb{Z}} \mathbb{Q}$ and is therefore divisible. Fix such an embedding $A \hookrightarrow D$ with D divisible. The quotient D/A is divisible as well, so

$$0 \to A \to D \to D/A \to 0$$

is an injective resolution of A of length one, and $\operatorname{Ext}^i_{\mathbb{Z}}(\mathbb{Z}/n, A) = 0$ for $i \geq 2$.

For any abelian group B a homomorphism $\mathbb{Z}/n \to B$ is determined by the image of 1, which may be any element killed by n, so $\operatorname{Hom}_{\mathbb{Z}}(\mathbb{Z}/n, B) = B[n] := \{b \in B \,|\, nb = 0\}$. Applying F to the resolution leaves the two-term complex $D[n] \to (D/A)[n]$, whence

$$\operatorname{Ext}^0_{\mathbb{Z}}(\mathbb{Z}/n, A) = \ker\big(D[n] \to (D/A)[n]\big) = D[n] \cap A = A[n]$$

which agrees with left exactness, and $\operatorname{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/n, A) = \operatorname{coker}\big(D[n] \to (D/A)[n]\big)$. That cokernel is A/nA. Send the class of $d + A$, where $nd \in A$, to $nd + nA$. This is well defined, since replacing d by $d + a$ with $a \in A$ changes nd by $na \in nA$, and it kills the image of $D[n]$, on which $nd = 0$. It is surjective because D is divisible: given $a \in A$ choose $d \in D$ with $nd = a$, and then $d + A$ lies in $(D/A)[n]$ and maps to $a + nA$. It is injective because $nd \in nA$, say $nd = na$ with $a \in A$, forces $n(d - a) = 0$, so that $d + A = (d - a) + A$ lies in the image of $D[n]$.

The universal δ-functor extending $A \mapsto A[n]$ is therefore

$$\operatorname{Ext}^0_{\mathbb{Z}}(\mathbb{Z}/n, A) = A[n], \qquad \operatorname{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/n, A) = A/nA, \qquad \operatorname{Ext}^i_{\mathbb{Z}}(\mathbb{Z}/n, A) = 0 \quad (i \geq 2)$$

and the long exact sequence attached to $0 \to A' \to A \to A'' \to 0$ has only six nonzero terms,

$$0 \to A'[n] \to A[n] \to A''[n] \xrightarrow{\delta^0} A'/nA' \to A/nA \to A''/nA'' \to 0$$

Effaceability is visible in this display: for D divisible $D/nD = 0$, so the morphism $\operatorname{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/n, A) \to \operatorname{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/n, D)$ induced by $A \hookrightarrow D$ is zero, and in degrees $i \geq 2$ both groups vanish.

Applications of the criterion follow one pattern. Two families of functors are each shown to carry long

exact sequences functorial in the short exact sequence; each is shown effaceable in positive degrees, possibly by different classes of effacing objects; and the two degree-zero terms are matched by a natural isomorphism. Theorem 56.4.6 makes both universal, and corollary 56.4.7 then upgrades the degree-zero match to an isomorphism in every degree, compatible with every connecting morphism. The two classes of effacing objects need not be related, and neither has to consist of injective objects, since definition 56.4.5 asks only that the induced morphism vanish.


Exercise 56.4.1

1. Let $G\colon \mathcal{A} \to \mathcal{B}$ be an exact additive functor. Show that setting $T^i := G$ for every $i \geq 0$, with all connecting morphisms zero, defines a δ-functor from $\mathcal{A}$ to $\mathcal{B}$, and that this δ-functor is universal if and only if G is the zero functor.
2. Show that a universal δ-functor T with $T^0 = 0$ has $T^i = 0$ for every $i \geq 0$.
3. Let $\mathcal{A}$ be an abelian category with enough injectives and let $F, G\colon \mathcal{A} \to \mathcal{B}$ be left exact additive functors admitting a natural isomorphism $\eta\colon F \Rightarrow G$. Show that there is exactly one isomorphism of δ-functors $(R^iF)_{i\geq 0} \to (R^iG)_{i\geq 0}$ whose degree-zero component corresponds to η, and give the argument without choosing a single resolution.
4. Fix integers $m, n \geq 1$ and put $d = \gcd(m, n)$. Write out the six-term exact sequence of example 56.4.10 for the short exact sequence $0 \to \mathbb{Z} \xrightarrow{m} \mathbb{Z} \to \mathbb{Z}/m \to 0$, computing each of the six groups, and verify the exactness of the resulting sequence directly.
5. Let $\mathcal{A}$ be an abelian category with enough injectives, let $F\colon \mathcal{A} \to \mathcal{B}$ be additive, and let $0 \to A \to I \to C \to 0$ be exact with I injective. Show that $R^iF(C) \cong R^{i+1}F(A)$ for every $i \geq 1$ and that $R^1F(A) \cong \operatorname{coker}\big(R^0F(I) \to R^0F(C)\big)$.
6. Let T be a δ-functor from $\mathcal{A}$ to $\mathcal{B}$ and let $E\colon \mathcal{B} \to \mathcal{C}$ be an exact additive functor. Show that $(E \circ T^i)_{i\geq 0}$, with connecting morphisms $E(\delta^i_\xi)$, is a δ-functor from $\mathcal{A}$ to $\mathcal{C}$, and that it is universal whenever T is effaceable in positive degrees.
7. Let T be a universal δ-functor from $\mathcal{A}$ to $\mathcal{B}$. Show that $f \mapsto f^0$ is a bijection from the set of morphisms of δ-functors $T \to T$ onto the set of natural transformations $T^0 \Rightarrow T^0$, and that it carries composition to composition.

56.5 Double Complexes

This final section shall be the basis for being able to compute many complexes. It was mentioned in box 56.2.12 that $\operatorname{Ext}^i_R(M, N)$ may be computed by using either a projective resolution of M or an injective resolution on N, both give the same answer. More generally, we may compute the resolution of either M or N and get the same value. This section will now prove this result. This will make many computations much simpler, for usually one object in is readily understandable while the other is being analyzed.


To motivate this, switching from projective to $\mathscr{F}$-acyclic resolutions can be viewed in the following important alternative way. Consider the following diagram where the top row and right column are cochain:



in some way, there was a reason to go from the top chain to the right chain, with the intermediate values "interpolating" the result. The natural candidate for this would be a complex of complex. Needing to bound it in one direction, say we are looking at $\mathrm{Ch}^{\leq 0}(\mathrm{Ch}^{\leq 0}(\mathbf{A}))$. Such an object would be of the form:

$$\cdots \to M^{-3,\bullet} \xrightarrow{d_h^{-3,\bullet}} M^{-2,\bullet} \xrightarrow{d_h^{-2,\bullet}} M^{-1,\bullet} \xrightarrow{d_h^{-1,\bullet}} M^{0,\bullet} \to 0 \to \cdots$$

The h in the subscript is to represent the fact we are going *horizontally*, and the respective morphism of each $d_h^{-i,\bullet}$ will be going vertically and are denoted $d_v^{i,j}$, or simply d_v to simply show the function's direction:



Given a complex of complex, it would be nice to reduce this to being a complex, a more familiar setting. One strategy the reader may come up with is to take:

$$\bigoplus_{i+j=n} M^{i,j}$$

with the natural morphisms between them. However these morphisms *almost* complexes: instead of commutativity for each square, they are *anti-commutative*. To fix this, create a new type of object that will satisfy this condition:

Definition 56.5.1: Double Complex

Let $A = \{A_{p,q}\}$ be a family of objects from $\mathbf{A}$. Then A together with maps

$$d^h : A_{p,q} \to A_{p-1,q} \qquad \delta^v : A_{p,q} \to A_{p,q-1}$$

satisfying $d^h \circ d^h = 0$, $\delta^v \circ \delta^v = 0$ and $d^h \circ \delta^v + \delta^v \circ d^h = 0$ is called a *double complex* or *bicomplex*.
Both differentials *lower* an index; this homological convention is the one used throughout, and in particular in chapter 60. A cochain double complex, whose differentials raise indices, is the same thing read through $A_{p,q} = A^{-p,-q}$.

We may visualize a double complex like so, with d^h running to the right and δ^v running downwards, each lowering its index:

$$\begin{array}{ccccccccc}
 & & \vdots & & \vdots & & \vdots & & \\
 & & \downarrow & & \downarrow & & \downarrow & & \\
\cdots & \longrightarrow & A_{p+1,q+1} & \longrightarrow & A_{p,q+1} & \longrightarrow & A_{p-1,q+1} & \longrightarrow & \cdots \\
 & & \downarrow & & \downarrow & & \downarrow & & \\
\cdots & \longrightarrow & A_{p+1,q} & \longrightarrow & A_{p,q} & \longrightarrow & A_{p-1,q} & \longrightarrow & \cdots \\
 & & \downarrow & & \downarrow & & \downarrow & & \\
\cdots & \longrightarrow & A_{p+1,q-1} & \longrightarrow & A_{p,q-1} & \longrightarrow & A_{p-1,q-1} & \longrightarrow & \cdots \\
 & & \downarrow & & \downarrow & & \downarrow & & \\
 & & \vdots & & \vdots & & \vdots & &
\end{array} \tag{56.6}$$

Note this is not a commutative diagram but an *anti-commutative* one. That is a convention, not a restriction, and it is worth pinning down once because both forms occur in practice. A grid whose squares *commute*, which is what a complex of complexes literally gives, is converted into a double complex in the sense above by replacing the vertical differential with

$$\delta^v_{p,q} := (-1)^p \, \tilde{\delta}^v_{p,q}$$

where $\tilde{\delta}^v$ is the commuting one. The sign makes the squares anticommute, which is exactly what makes $d^h + \delta^v$ square to zero on the total complex. Every later construction, here and in chapter 60, assumes the anticommuting form; when a source of double complexes produces commuting squares, this twist is understood to have been applied.

As mentioned, we can form a total complex from this:

Proposition 56.5.2: Total Complex

Let $A = \{A^{p,q}\}$ be a double complex. Then define the total complex $\mathrm{Tot}^{\Pi}(A)$ and $\mathrm{Tot}^{\oplus}(A)$ by:


$$\mathrm{Tot}^{\Pi}(A)_n = \prod_{p+q=n} A_{p,q} \qquad \mathrm{Tot}^{\oplus}(A)_n = \bigoplus_{p+q=n} A_{p,q}$$

with $d^{\mathrm{tot}} = d^h + \delta^v$, which squares to zero precisely because the two differentials anticommute. The two agree whenever only finitely many $A_{p,q}$ are nonzero on each diagonal $p+q=n$, as for bounded-above tensor and Hom grids.

***Proof*:**
Computing:

$$d_{tot} \circ d_{tot} = (d_h + \delta_v) \circ (d_h + \delta_v) = d_h \circ d_h + d_h \circ \delta_v + \delta_v \circ d_h + \delta_v \circ \delta_v = 0$$

Note that the total complex does not exist in all categories, namely it may not exist in categories which are not closed under infinite products and coproducts (ex. in the category of finite abelian groups). A category which is closed for infinite products is called *complete* and *cocomplete* if it is closed for infinite sums. We can visualize a total complex by taking the diagram in equation (56.6) and moving it like so:




It is then easy to visualize how we get a total complex form this.

Example 56.5.3: Total Complexes


1. Consider a double complex:

$$\cdots \to 0 \to L^\bullet \xrightarrow{\alpha^\bullet} M^\bullet \to 0 \to \cdots$$

which we may represent as:



we shall get the following:



which is exactly the definition of a mapping cone!

2. The operators $\mathrm{Hom}_A(-,-)$ and $-\otimes-$ both give rise to double complexes. Focusing on the $\mathrm{Hom}_A(-,-)$ example, consider a chain in $L^\bullet \in \mathrm{Ch}^{\leq 0}(\mathbf{A})$ and $M^\bullet \in \mathrm{Ch}^{\geq 0}(\mathbf{A})$. These can be used to form a double complex, or isomorphically a complex in $\mathrm{Ch}^{\leq 0}(\mathrm{Ch}^{\leq 0}(\mathbf{A}))$:

$$\cdots \to \mathrm{Hom}_A(L^\bullet, M^0) \to \mathrm{Hom}_A(L^\bullet, M^1) \to \mathrm{Hom}_A(L^\bullet, M^2) \to \cdots$$

which creates the following upper-quadrant grid:

$$\begin{array}{ccccccc}
\vdots & & \vdots & & \vdots & & \\
\uparrow & & \uparrow & & \uparrow & & \\
\mathrm{Hom}_A(L^{-2}, M^0) & \longrightarrow & \mathrm{Hom}_A(L^{-2}, M^1) & \longrightarrow & \mathrm{Hom}_A(L^{-2}, M^2) & \longrightarrow & \cdots \\
\uparrow & & \uparrow & & \uparrow & & \\
\mathrm{Hom}_A(L^{-1}, M^0) & \longrightarrow & \mathrm{Hom}_A(L^{-1}, M^1) & \longrightarrow & \mathrm{Hom}_A(L^{-1}, M^2) & \longrightarrow & \cdots \\
\uparrow & & \uparrow & & \uparrow & & \\
\mathrm{Hom}_A(L^0, M^0) & \longrightarrow & \mathrm{Hom}_A(L^0, M^1) & \longrightarrow & \mathrm{Hom}_A(L^0, M^2) & \longrightarrow & \cdots
\end{array}$$

Flipping the above diagram across the main diagonal, we would get the double complex:

$$\cdots \to \mathrm{Hom}_A(L^0, M^\bullet) \to \mathrm{Hom}_A(L^{-1}, M^\bullet) \to \mathrm{Hom}_A(L^{-2}, M^\bullet) \to \cdots$$

These two double complexes are isomorphic (as the reader should check). Due to this, by slight abuse of notation the total complex of both can be denoted $TC(\mathrm{Hom}_A(L, M))^\bullet$, where the degree i term is:

$$\mathrm{Hom}_A(L^{-i}, M^0) \oplus \mathrm{Hom}_A(L^{-i+1}, M^1) \oplus \cdots \oplus 0\mathrm{Hom}_A(L^{-1}, M^{i-1}) \oplus 0\mathrm{Hom}_A(L^0, M^i)$$

The reader should verify that:

(a) $\ker d^i_{tot}$ is equal to morphisms of cochains $L^\bullet \to M[i]^\bullet$

(b) The image $\mathrm{im} d^{i-1}_{tit}$ consists of morphisms that are homotopy equivalent to 0

(c) Thus, the cohomology of $TC(\mathrm{Hom}_A(M, N))^\bullet$ "paramaterizes" the morphisms in the homotopic category

To ground this, consider $TC(\mathrm{Hom}_A(M, N))^0 = \mathrm{Hom}_A(L^0, M^0)$. Then $d_{tot}(\alpha) = 0$ means that both $\alpha \circ d^{-1}_{L^\bullet} \in \mathrm{Hom}_A(L^{-1}, M^0)$ and $d^0_{M^\bullet} \in \mathrm{Hom}_A(L^0, M^1)$ both vanish. The reader should draw out this diagram, and notice that this will make α have the condition to be a morphism of cochain complexes $L^\bullet \to M^\bullet$!

$$H^0(TC(\mathrm{Hom}_A(M, N))^\bullet) = \mathrm{Hom}_{\mathrm{Ch}(\mathbf{A})}(L^\bullet, M^\bullet) \overset{!}{=} \mathrm{Hom}_{K(\mathbf{A})}(L^\bullet, M^\bullet)$$

where the $\overset{!}{=}$ equality comes from the fact that there is no nontrivial homotopies in this case! For $H^i(TC(\mathrm{Hom}_A(M, N))^\bullet)$, with some care for signs, it can be identified with $\mathrm{Hom}_{K(\mathbf{A})}(L^\bullet, M[i]^\bullet)$

The cohomology of double complexes requires some book-keeping through the use of *spectral sequences*, which shall be explored in greater depth in chapter 60. For the current goal, it is enough to consider when a double-complex is exact:

Proposition 56.5.4: Exactness Of Complex Of Complex

Let $\mathbf{A}$ be an abelian category and let

$$\cdots \to M^{-3,\bullet} \to M^{-2,\bullet} \to M^{-1,\bullet} \to M^{0,\bullet} \to 0$$

be a complex in $\mathrm{Ch}^{\leq 0}(\mathrm{Ch}^{\leq 0}(\mathbf{A}))$, regarded as a double complex $M^{\bullet,\bullet}$ with $M^{p,q} = 0$ unless $p \leq 0$ and $q \leq 0$, and let $T^\bullet$ denote its total complex. Then $T^\bullet$ is exact if *either* of the following holds:

1. the displayed complex is exact in $\mathrm{Ch}^{\leq 0}(\mathbf{A})$, equivalently every row $M^{\bullet,q}$ is exact;
2. every column $M^{p,\bullet}$ is exact.

Neither hypothesis implies the other, and either one alone suffices; this is the form in which the result is used below and in chapter 60. The same statement holds in $\mathrm{Ch}^{\geq 0}(\mathrm{Ch}^{\geq 0}(\mathbf{A}))$, by reversing the direction of every index. Note further that only one of the two directions need be bounded: case (2) uses only $p \leq 0$ and case (1) only $q \leq 0$, the bound being what makes the following staircase terminate; with only one bound the diagonals are infinite, so there the total complex must be taken to be $\mathrm{Tot}^{\oplus}$, since the staircase needs a least index in the support of a given element. The result is known as the *acyclic assembly lemma*; see *An Introduction to Homological Algebra* [101] for the variants in the other quadrants and for the distinction between Tot^{Π} and $\mathrm{Tot}^{\oplus}$, which does not arise here because each diagonal of $M^{\bullet,\bullet}$ carries only finitely many nonzero terms.

***Proof*:**

Step 1: Reduction to case (2). Transposing the double complex, that is exchanging the two indices and the two differentials, converts rows into columns and leaves the total complex unchanged up to the sign of the differential, which does not affect exactness. So case (1) follows from case (2) applied to the transpose, and only the latter needs proof.

Step 2: The staircase. Assume every column is exact, write d_h and d_v for the two differentials and $d = d_h + d_v$ for the differential of $T^\bullet$. Let $x \in T^n$ satisfy $dx = 0$; the claim is that $x = dy$ for some $y \in T^{n-1}$. Write $x = \sum_{p+q=n} x^{p,q}$, a finite sum.

Let p_1 be least with $x^{p_1,q_1} \neq 0$, where $q_1 = n - p_1$; if there is no such p_1 then $x = 0$ and there is nothing to prove. Consider the component of the equation $dx = 0$ in bidegree $(p_1, q_1 + 1)$. Only two terms can contribute to it, namely $d_v x^{p_1,q_1}$ and $d_h x^{p_1-1,q_1+1}$, and the second vanishes because $p_1 - 1 < p_1$ and p_1 was least. Hence

$$d_v x^{p_1,q_1} = 0$$

so x^{p_1,q_1} is a cocycle in the column $M^{p_1,\bullet}$. That column is exact, so there is $y^{p_1,q_1-1} \in M^{p_1,q_1-1}$ with $d_v y^{p_1,q_1-1} = x^{p_1,q_1}$.

Step 3: Termination. Replace x by

$$x' = x - d\big(y^{p_1,q_1-1}\big) = x - d_v y^{p_1,q_1-1} - d_h y^{p_1,q_1-1}$$

This is again a cocycle, since it differs from x by a coboundary. Its component in bidegree (p_1, q_1) is $x^{p_1,q_1} - d_v y^{p_1,q_1-1} = 0$, and $d_h y^{p_1,q_1-1}$ lives in bidegree $(p_1 + 1, q_1 - 1)$, so no component

with $p < p_1$ is disturbed and all of those were already zero. The least index with a nonzero component has therefore increased by at least one.

Because $M^{p,q} = 0$ for $p > 0$, this least index cannot exceed 0, so after at most $|p_1| + 1$ repetitions every component vanishes. Summing the finitely many y's produced along the way gives $y \in T^{n-1}$ with $dy = x$, so $T^\bullet$ is exact at degree n. As n was arbitrary, this completes the proof.

Example 56.5.5: Exactness Of Double Complex

Let $P^\bullet \in C^{\leq 0}(\mathbf{A})$ be a complex and $L^\bullet \in C^{\geq 0}(\mathbf{A})$ an exact complex. Since each P^i is projective, $\mathrm{Hom}_{\mathbf{A}}(P^i, L^\bullet)$ for each i. Hence, the complex:

$$0 \to \mathrm{Hom}_{\mathbf{A}}(P^0, L^\bullet) \to \mathrm{Hom}_{\mathbf{A}}(P^{-1}, L^\bullet) \to \mathrm{Hom}_{\mathbf{A}}(P^{-2}, L^\bullet) \to \cdots$$

is exact. Using example 56.5.3, we see that:

$$\mathrm{Hom}_{K(\mathbf{A})}(P^\bullet, L[i]^\bullet) = 0 \qquad \forall i \in \mathbb{Z}$$

This implies that every cochain morphism from a bounded-above projective complex to a bounded-bellow exact complex is homotopic to 0. This just proved corollary 56.2.5 (with an extra boundedness condition)! In some textbooks, due to the speed at which some results can be proved using double-complexes, they are introduced earlier. However, the more "down-to-earth" introduction has is favored in this chapter since it demonstrated key homological concepts.

Next, we look at resolutions of complexes.. As we saw in definition 56.2.11, a (projective) resolution is a quasi-isomorphism $M^\bullet \to \iota(A)$ for some complex $M^\bullet \in \mathrm{Obj}(\mathrm{Ch}(\mathbf{A}))$, and more generally a projective resolution for a general complex is a quasi-isomorphism $P^\bullet \to C^\bullet$ for some projective complex $P^\bullet$. Generalizing the definition of resolution of the first kind, $\iota(A)$, and say that resolution of a complex $N^\bullet \in \mathrm{Ch}^\bullet(A) = A'$ is a complex of complex $M^{\bullet,\bullet} \in \mathrm{Ch}^{\leq 0}(A')$ and a quasi-isomorphism


$$\begin{array}{ccccccccc} \cdots & \longrightarrow & M^{-2,\bullet} & \xrightarrow{d_h} & M^{-2,\bullet} & \xrightarrow{d_h} & M^{-2,\bullet} & \longrightarrow & 0 & \longrightarrow & \cdots \\ & & \downarrow & & \downarrow & & \downarrow & & \downarrow & & \\ \cdots & \longrightarrow & 0 & \longrightarrow & 0 & \longrightarrow & N^\bullet & \longrightarrow & 0 & \longrightarrow & \cdots \end{array} \tag{56.7}$$

where the diagram commutes. We shall show that this definition of a resolution induces a resolution as given in theorem 56.2.17. To see this, notice that in equation (56.7), $\alpha^\bullet \circ d_h = 0$, hence we can collapse the diagram like so:

$$\cdots \to M^{-2,\bullet} \xrightarrow{-d_h} M^{-1,\bullet} \xrightarrow{d_h} M^{0,\bullet} \xrightarrow{\alpha^\bullet} N^\bullet \to 0 \cdots$$

Call this complex $M_N^{\bullet,\bullet}$. Two important diagrams can be derived here. The first is by taking the


total complex of $M^{\bullet,\bullet}$ and taking a morphism from this to $N^\bullet$:



This gives a morphism:

$$TC(\alpha^\bullet) : TC(M^{\bullet,\bullet}) \to N^\bullet$$

where the morphism is defined since $TC(-)$ is a functorial. Another diagram we can create is by considering the total complex of $M_N^{\bullet,\bullet}$:



These two are related in the following way:

Proposition 56.5.6: Total Complex Of Resolution

Let $M^{\bullet,\bullet}$ be a resolution of $N^\bullet$ and let $M_N^{\bullet,\bullet}$ be defined as above. Then

$$TC(M_N)^\bullet \cong MC\big(TC(\alpha)\big)[-1]^\bullet$$

canonically, equivalently $TC(M_N)[1]^\bullet \cong MC(TC(\alpha))^\bullet$.

***Proof*:**
Both sides are computed degreewise, so it suffices to match the terms and the differentials.

Step 1: The terms. The complex $M_N^{\bullet,\bullet}$ is $M^{\bullet,\bullet}$ with $N^\bullet$ appended in the column $p = 1$, to the right of $M^{0,\bullet}$ and joined to it by the augmentation $\alpha^\bullet$. A term N^j therefore sits in total degree

$1+j$, so its contribution to total degree n is N^{n-1} and

$$TC(M_N)^n = \Big(\bigoplus_{i+j=n} M^{i,j}\Big) \oplus N^{n-1} = TC(M)^n \oplus N^{n-1}$$

which is what the diagram above the proposition displays, $M^{0,0}$ being grouped with N^{-1}. On the other side $TC(\alpha)\colon TC(M)^\bullet \to N^\bullet$ is the totalized augmentation, and since definition 56.1.23 puts the *source* of a morphism in the shifted slot,

$$MC\big(TC(\alpha)\big)^n = TC(M)^{n+1} \oplus N^n$$

Comparing the two, $TC(M_N)^n = MC(TC(\alpha))^{n-1}$, which is the shift asserted in the statement.

Step 2: The differentials. On $TC(M_N)^\bullet$ the differential is the total differential of the augmented double complex: on the M part it is $d_h + d_v$, the component carrying $M^{0,\bullet}$ into the appended column is $\alpha^\bullet$, and on the N part it is $-d_N$, the sign being the $(-1)^p$ twist at $p=1$ that makes the augmented grid anticommute. So $d_{TC(M_N)}(m,n) = (d_{TC(M)}m,\ \alpha(m) - d_N n)$. By definition 56.1.23 the cone differential is $d_{MC}(l,n) = (-d_{TC(M)}l,\ \alpha(l) + d_N n)$, so under the identification of Step 1 the two differ by an overall sign.

The shift convention $d_{[r]} = (-1)^r d$ gives $d_{MC(TC(\alpha))[-1]}(m,n) = -\big(-d_{TC(M)}m,\ \alpha(m) + d_N n\big) = (d_{TC(M)}m,\ -\alpha(m) - d_N n)$, so the two differentials agree in the $TC(M)$ component and differ exactly in the sign of the α-component. They are therefore not equal on the nose, but the map

$$\varphi(m,n) = (m,-n)$$

is an isomorphism of complexes intertwining them: $\varphi\big(d_{TC(M_N)}(m,n)\big) = (d_{TC(M)}m,\ -\alpha(m) + d_N n) = d_{MC(TC(\alpha))[-1]}\big(\varphi(m,n)\big)$. Hence $TC(M_N)^\bullet \cong MC(TC(\alpha))[-1]^\bullet$, canonically, completing the proof.

Using this, we can see how the resolution in $\mathrm{Ch}^{\leq 0}(A')$ leads to a resolution as defined in theorem 56.2.17:

Theorem 56.5.7: Total Complexes And Resolution Of Complexes

Let $\mathbf{A}$ be an abelian category, $\mathbf{A}' = \mathrm{Ch}^{\leq 0}(\mathbf{A})$, and $N^\bullet \in A'$. Let $M^{\bullet,\bullet} \in \mathrm{Ch}^{\leq 0}(\mathbf{A}')$ with total complex $T^\bullet$.

1. Assume that $M^{\bullet,\bullet}$ is a resolution of $N^\bullet$ in $\mathrm{Ch}^{\leq 0}(\mathbf{A}')$. Then $T^\bullet$ is quasi-isomorphic to $N^\bullet$ in $\mathbf{A}'$.
2. Assuming the cohomology of $M^{i,\bullet}$ is concentrated at 0. Then $T^\bullet$ is quasi-isomorphic to the complex of cohomology objects induced by the complex $M^{\bullet,\bullet}$:

$$\cdots \to H^0(M^{-3,\bullet}) \to H^0(M^{-2,\bullet}) \to H^0(M^{-1,\bullet}) \to H^0(M^{0,\bullet}) \to 0 \cdots$$

Notice that this theorem is a direct extensions of proposition 56.5.4. This is also a special case of results we shall see in chapter 60

***Proof*:**
Notice that (2) follows from (1) by flipping the corresponding double-complex across the diagonal, hence we prove the first. For the first, if $M_N^{\bullet,\bullet}$ is quasi-isomorphic, then $TC(M_N)^\bullet$ is exact by proposition 56.5.4, which by proposition 56.5.6 is the mapping cone of the morphism $T^\bullet \to N^\bullet$, which by proposition 56.1.26 shows that $\alpha^\bullet : T^\bullet \to N^\bullet$ is a quasi-isomorphism, as we sought to show.

Using this theorem, a simple alternative to resolving complexes (theorem 56.2.17). By the horseshoe lemma, every bounded-above complex $N^\bullet$ in an abelian category with enough projectives may be viewed as a complex induced by H^0 from a complex:

$$\cdots \to P^{-3,\bullet} \to P^{-2,\bullet} \to P^{-1,\bullet} \to P^{0,\bullet} \to 0$$

where $P^{i,\bullet}$ are projective resolutions of N^i. Then by theorem 56.5.7(2) the total complex of $P^{\bullet,\bullet}$ is a projective resolution of $N^\bullet$. This then can give theorem 56.2.17. It is still worth presenting theorem 56.2.17 to firmly grasp the fundamentals of homological algebra.

56.5.1 Applications to Computations of Ext and Tor

Let us now show that we may compute $\text{Ext}(M,N)$ or $\text{Tor}(M,N)$ using a resolution of either term. Going back to the $\mathscr{F}$-acyclic resolution of an object M:

$$\cdots \to A^{-2} \to A^{-1} \to A^0 \to M \to 0 \to \cdots$$

We may create a complex of projective resolution by corollary 56.3.9:

$$\cdots \to P^{-2,\bullet} \to P^{-1,\bullet} \to P^{0,\bullet} \to P_M^\bullet \to 0 \to \cdots$$

where $P^{i,\bullet}$ is a projective resolution of A^{-i}. Since the resolution by projective resolution's is exact, the rows of the double-complex corresponding to $P^{\bullet,\bullet}$ are projective resolutions of P_M^i. Now, applying the functor $\mathscr{F}$, we get the diagram:

$$\begin{array}{ccccccccc}
\cdots & \longrightarrow & \mathscr{F}(A^{-2}) & \longrightarrow & \mathscr{F}(A^{-1}) & \longrightarrow & \mathscr{F}(A^0) & \longrightarrow & \mathscr{F}(M) \\
 & & \uparrow & & \uparrow & & \uparrow & & \uparrow \\
\cdots & \longrightarrow & \mathscr{F}(P_M^{-2,0}) & \longrightarrow & \mathscr{F}(P_M^{-1,0}) & \longrightarrow & \mathscr{F}(P_M^{0,0}) & \longrightarrow & \mathscr{F}(P_M^0) \\
 & & \uparrow & & \uparrow & & \uparrow & & \uparrow \\
\cdots & \longrightarrow & \mathscr{F}(P_M^{-2,-1}) & \longrightarrow & \mathscr{F}(P_M^{-1,-1}) & \longrightarrow & \mathscr{F}(P_M^{0,-1}) & \longrightarrow & \mathscr{F}(P_M^{-1}) \\
 & & \uparrow & & \uparrow & & \uparrow & & \uparrow \\
\cdots & \longrightarrow & \mathscr{F}(P_M^{-2,-2}) & \longrightarrow & \mathscr{F}(P_M^{-1,-2}) & \longrightarrow & \mathscr{F}(P_M^{0,-2}) & \longrightarrow & \mathscr{F}(P_M^{-2}) \\
 & & \uparrow & & \uparrow & & \uparrow & & \uparrow \\
 & & \vdots & & \vdots & & \vdots & & \vdots
\end{array}$$

Since each row and column of this diagram (excluding the top row and right column) is exact, by theorem 56.5.7 the total complex of:

$$\cdots \mathscr{F}(P^{-2,\bullet}) \to \mathscr{F}(P^{-1,\bullet}) \to \mathscr{F}(P^{0,\bullet}) \to 0 \to \cdots$$

is quasi-isomorphic to both $\mathrm{Ch}(\mathscr{F})(A^\bullet)$ and $\mathrm{Ch}(\mathscr{F})(P^\bullet)$, that is:

$$TC(\mathscr{F}(P))^\bullet \sim \mathrm{Ch}(\mathscr{F})(A^\bullet) \sim \mathrm{Ch}(\mathscr{F})(P^\bullet)$$

Thus, by definition of quasi-isomorphism

$$\mathbf{L}_i\mathscr{F}(M) \cong H^{-i}(\mathrm{Ch}(\mathscr{F})(A^\bullet)) \cong H^{-i}(\mathrm{Ch}(\mathscr{F})(P^\bullet))$$

Applying these results to Ext and Tor will finally give us the following results:

Theorem 56.5.8: Computation Of Tor and Ext

Let R be a ring. If M is a right and N a left R-module, with projective resolutions $P^\bullet_M$ and $P^\bullet_N$, then

$$\mathrm{Tor}^R_i(M,N) \cong H^{-i}(P^\bullet_M \otimes_R N) \cong H^{-i}(M \otimes_R P^\bullet_N)$$

If M and N are left R-modules, $P^\bullet_M$ is a projective resolution of M and $Q^\bullet_N$ an injective resolution of N, then

$$\mathrm{Ext}^i_R(M,N) \cong H^i(\mathrm{Hom}_R(P^\bullet_M, N)) \cong H^i(\mathrm{Hom}_R(M, Q^\bullet_N))$$

The index for Tor is $-i$ because a projective resolution sits in nonpositive degrees (definition 56.2.11), so that $P^{-i}_M \otimes_R N$ is the term of degree $-i$.

***Proof*:**
We first treat Tor. Take the complex:

$$\cdots \to P^{-2}_M \otimes_R P^\bullet_N \to P^{-1}_M \otimes_R P^\bullet_N \to P^0_M \otimes_R P^\bullet_N \to 0 \cdots$$

Each P^j_N is projective, hence flat (corollary 17.5.5), so $- \otimes_R P^j_N$ is exact, and the cohomology of the complex is concentrated at 0 and equals $M \otimes_R P^\bullet_N$. By theorem 56.5.7 we have that :

$$TC(P^\bullet_M \otimes_R P^\bullet_N)^\bullet \qquad \text{is quasi-isomorphic to} \qquad M \otimes_R P^\bullet_N$$

Similarly, since each P^i_M is projective, hence flat, the complex $P^i_M \otimes_R P^\bullet_N$ is a resolution of $P^i_M \otimes N$, i.e. the cohomology of each $P^i_M \otimes_R P^\bullet_N$ is concentrated at degree 0 and equals $P^i_M \otimes_R N$. By theorem 56.5.7 we have that :

$$TC(P^\bullet_M \otimes_R P^\bullet_N)^\bullet \qquad \text{is quasi-isomorphic to} \qquad P^\bullet_M \otimes_R N$$

but then, the cohomologies are identical.

For Ext the double complex is $\mathrm{Hom}_R(P^{-p}_M, Q^q_N)$. Each $\mathrm{Hom}_R(-, Q^q_N)$ is exact, Q^q_N being injective, so the complex $\mathrm{Hom}_R(P^\bullet_M, Q^q_N)$ is a resolution of $\mathrm{Hom}_R(M, Q^q_N)$. Each $\mathrm{Hom}_R(P^{-p}_M, -)$ is exact, P^{-p}_M being projective, so $\mathrm{Hom}_R(P^{-p}_M, Q^\bullet_N)$ is a resolution of $\mathrm{Hom}_R(P^{-p}_M, N)$. The same two applications of theorem 56.5.7, with every index reversed as after proposition 56.5.4, identify both $\mathrm{Hom}_R(M, Q^\bullet_N)$ and $\mathrm{Hom}_R(P^\bullet_M, N)$ up to quasi-isomorphism with the total complex, as we sought to show.

57

The Derived Category

Every derived functor in chapter 56 was computed by choosing a resolution and then proving the answer independent of the choice. That pattern is a symptom. The object of the theory is not the module A but the complex that resolves it, and not the complex but its class up to quasi-isomorphism. The resolutions are representatives, and the independence proofs are what working with representatives costs. The derived category is the category in which that thing is an object. Its construction was already carried out in section 55.2 and recorded as corollary 56.1.17: it is the localization $D(\mathbf{A}) = \mathrm{Ch}(\mathbf{A})[\mathrm{qis}^{-1}]$, and it needs no hypothesis on projectives or injectives.

What that construction does not say is what kind of category results. In general it is not abelian, and the failure is not a technicality: kernels and cokernels are the first casualties of inverting quasi-isomorphisms. Something weaker survives, strong enough to carry every long exact sequence the subject uses, and it has a name and a short list of axioms. This chapter states them, builds $D(\mathbf{A})$ inside that framework, and then recovers Ext, Tor and the Grothendieck spectral sequence as statements about it. Its notation follows Weibel and Gelfand-Manin. section 57.1 flags the one place where the two disagree.

57.1 Triangulated Categories

A homotopy category is in general not abelian. The kernel and cokernel of a homotopy class of maps depend on the representative, so neither is well defined on the class. Yet a derived functor $\mathrm{D}(\mathscr{F})$ still carries a long exact sequence, so some structure survives. Locating it starts from a short exact sequence of complexes

$$0 \to L^\bullet \to M^\bullet \to N^\bullet \to 0$$

The snake lemma (theorem 56.1.20) relates $N^\bullet$ and $L^\bullet$ after passing to cohomology, through the connecting morphism. Before passing to cohomology there is no map between them at all. Adjoining


the zero morphism $N^\bullet \xrightarrow{0} L^\bullet$ closes the sequence into a cycle, and the one short exact sequence becomes three:

$$N^\bullet \xrightarrow{0} L^\bullet \to M^\bullet$$
$$L^\bullet \to M^\bullet \to N^\bullet$$
$$M^\bullet \to N^\bullet \xrightarrow{0} L^\bullet$$

These carry the same information, and folding any one of them gives a triangle.

Definition 57.1.1: Exact Triangle

Let $L^\bullet, M^\bullet, N^\bullet \in \mathrm{Ch}(\mathbf{A})$ be three complexes. If there exist morphisms such that the following diagram is exact (at each vertex):




Then the diagram is called an *exact triangle* of $\mathrm{Ch}(\mathbf{A})$. This diagram is also sometimes denoted

$$L^\bullet \to M^\bullet \to N^\bullet \to$$

if it is easier to write it out flat.

The particular triangle obtained by folding the three sequences above is



where the $+1$ morphism is the zero map. The label anticipates what that map becomes once the construction is done properly: not zero, but a map $N^\bullet \to L[1]^\bullet$ raising cohomological degree by one. Stretched out, the triangle is a single long sequence

$$\cdots \to N^{i-1} \xrightarrow{0} L^i \to M^i \to N^i \xrightarrow{0} L^{i+1} \to \cdots$$

Applying the cohomology functor and replacing the zero maps by the connecting morphism gives

$$\cdots \to H^{i-1}(N^\bullet) \xrightarrow{\delta^{i-1}} H^i(L^\bullet) \to H^i(M^\bullet) \to H^i(N^\bullet) \xrightarrow{\delta^i} H^{i+1}(L^\bullet) \to \cdots$$

The maps δ^i do not come from the cohomology functor, which is the precise sense in which $\mathrm{Ch}(\mathbf{A})$ is the wrong category to apply it in. The axioms below name the structure that carries δ as part of its data.

The translation functor on $\mathrm{Ch}(\mathbf{A})$, $\mathrm{K}(\mathbf{A})$ and $D(\mathbf{A})$ is the shift of definition 56.1.23. For $n \in \mathbb{Z}$, a complex X and a chain map f it is

$$X[n]^i := X^{i+n}, \qquad d^i_{X[n]} := (-1)^n d^{i+n}_X, \qquad f[n]^i := f^{i+n} \tag{57.1}$$

so that $H^i(X[n]^\bullet) = H^{i+n}(X^\bullet)$. For $n = 1$ this is the shift definition 56.1.23 uses: its projection $MC(\alpha) \to L[1]$ is a chain map because $d_{L[1]} = -d_L$. It is an automorphism of each of these categories, with inverse $X \mapsto X[-1]$.

57.1.2 Warning: Two Conventions for the Translation Weibel writes the translation functor T and reserves the bracket for the opposite shift, so that his T is his $[-1]$ and his identification reads $H^i(A[-1]) \cong H^{i+1}(A)$. This book writes the translation as $[1]$ throughout. *The functors agree*: both raise cohomological degree by one, and $[1]$ here is T there. Only the bracket differs. A reader checking an axiom against Weibel §10.2 should translate $T \rightsquigarrow [1]$ and leave the signs unchanged.

With the translation fixed, the axioms can be stated. A *triangle* on an ordered triple (A, B, C) of objects of an additive category $\mathcal{K}$ equipped with an automorphism $[1]$ is a triple of morphisms $u\colon A \to B$, $v\colon B \to C$, $w\colon C \to A[1]$, displayed

$$A \xrightarrow{u} B \xrightarrow{v} C \xrightarrow{w} A[1]$$

A *morphism of triangles* (f, g, h) from (u, v, w) on (A, B, C) to (u', v', w') on (A', B', C') is a triple of morphisms making the three squares of

$$\begin{array}{ccccccc} A & \xrightarrow{u} & B & \xrightarrow{v} & C & \xrightarrow{w} & A[1] \\ {\scriptstyle f}\downarrow & & {\scriptstyle g}\downarrow & & {\scriptstyle h}\downarrow & & \downarrow{\scriptstyle f[1]} \\ A' & \xrightarrow[u']{} & B' & \xrightarrow[v']{} & C' & \xrightarrow[w']{} & A'[1] \end{array}$$

commute.

Definition 57.1.3: Triangulated Category

A *triangulated category* is an additive category $\mathcal{K}$ together with an automorphism $[1]\colon \mathcal{K} \to \mathcal{K}$ (the *translation*) and a class of triangles called *distinguished*, satisfying:

(TR1) Every morphism $u\colon A \to B$ embeds in a distinguished triangle (u, v, w). For every object A the triangle $(\mathrm{id}_A, 0, 0)$ on $(A, A, 0)$ is distinguished. Any triangle isomorphic to a distinguished triangle is distinguished.

(TR2) *(Rotation.)* If (u, v, w) is distinguished on (A, B, C), then so are

$$\big(v,\ w,\ -u[1]\big) \text{ on } (B, C, A[1]) \qquad \text{and} \qquad \big(-w[-1],\ u,\ v\big) \text{ on } (C[-1], A, B)$$

(TR3) *(Morphisms.)* Given distinguished triangles (u, v, w) on (A, B, C) and (u', v', w') on (A', B', C') and morphisms $f\colon A \to A'$, $g\colon B \to B'$ with $gu = u'f$, there exists $h\colon C \to C'$ making (f, g, h) a morphism of triangles.

(TR4) *(The octahedral axiom.)* Let $u\colon A \to B$ and $v\colon B \to C$ be morphisms, and suppose given distinguished triangles

$$(u,\ j,\ \delta) \text{ on } (A, B, C'), \quad (v,\ x,\ i) \text{ on } (B, C, A'), \quad (vu,\ y,\ \varepsilon) \text{ on } (A, C, B')$$

Then there is a distinguished triangle $\big(f,\ g,\ (j[1])\, i\big)$ on (C', B', A') such that

$$\delta = \varepsilon f, \qquad x = gy, \qquad yv = fj, \qquad u[1]\,\varepsilon = ig$$

The four axioms are Verdier's. A triangulated category is *not* an abelian category, and the distinguished triangles are what stand in for its short exact sequences.

Three comments on the axioms, in the order a reader meets the difficulties.

The sign in (TR2) is not decoration, and what it does is easy to misstate. Rotating three times returns $(-u[1], -v[1], -w[1])$, and $(-\mathrm{id}, \mathrm{id}, -\mathrm{id})$ is an isomorphism of triangles from that to $(u[1], v[1], -w[1])$: the translate carrying a single sign. That sign does not in general come off. For a diagonal $(\varepsilon_1, \varepsilon_2, \varepsilon_3)$ with $\varepsilon_i = \pm\mathrm{id}$ landing on $(u[1], v[1], w[1])$, the three squares read

$$(\varepsilon_1 + \varepsilon_2)\, u[1] = 0, \qquad (\varepsilon_2 + \varepsilon_3)\, v[1] = 0, \qquad (\varepsilon_3 + \varepsilon_1)\, w[1] = 0$$

Where an edge is not annihilated by 2, its square forces the corresponding $\varepsilon_k = -\varepsilon_{k+1}$, and the three relations together give $2\varepsilon_1 = 0$, which no diagonal satisfies. Where an edge *is* killed by 2 the constraint is vacuous and a diagonal can exist: on the triangle $(\mathrm{id}_A, 0, 0)$ of (TR1), whose second and third edges vanish, $(\mathrm{id}, -\mathrm{id}, \mathrm{id})$ is such an isomorphism. In particular $(-\mathrm{id}, -\mathrm{id}, -\mathrm{id})$ is not such an isomorphism: conjugating every vertex by $-\mathrm{id}$ fixes every edge, so it is an automorphism of a triangle and not a map to the sign-flipped one. What forces the sign in the first place is the model, exercise 57.1.1 (1) producing $-\alpha[1]$ from the cone construction, so an axiom without it would fail for $\mathrm{K}(\mathbf{A})$.

(TR3) asserts existence of the filler h and not uniqueness, and the failure of uniqueness is the standing defect of triangulated categories, the reason the axioms hand back no functorial cone and the reason the theory does not by itself glue. What (TR3) does give is proposition 57.1.10, recorded below once the tools to prove it are in place.

The octahedral axiom (TR4) is the one that resists reading. Its content is a compatibility between the three cones attached to a composable pair $A \xrightarrow{u} B \xrightarrow{v} C$: the cones of u, of v, and of vu are not independent, and (TR4) says the first and third fit into a distinguished triangle whose third vertex is the second. In the abelian setting the corresponding statement is the third isomorphism theorem, $(C/A)/(B/A) \cong C/B$, and (TR4) is what survives of it. The four displayed identities say that the octahedron built from the four triangles has its remaining four faces commuting.

57.1.4 Note: What the Axioms Do Not Give The axioms give no limits or colimits beyond finite direct sums, no functorial cone, and no notion of exactness for a general diagram. A particular triangulated category may still have some of this. $\mathrm{K}(R\text{-Mod})$ has all small products and coproducts, formed degreewise, since a family of null-homotopies assembles componentwise. But nothing in definition 57.1.3 produces them, so no argument from the axioms may use them. Restoring the missing structure canonically is what the enhancements of a triangulated category (differential graded, or stable ∞-categorical, [27]) exist for.

Two kinds of functor are relevant, one preserving the triangulated structure and one converting it into exactness in an abelian category.

Definition 57.1.5: Triangulated Functor

Let $\mathcal{K}$ and $\mathcal{K}'$ be triangulated categories. A *triangulated functor* (or *exact functor* of triangulated categories) is an additive functor $F\colon \mathcal{K} \to \mathcal{K}'$ together with a natural isomorphism $F(A[1]) \cong F(A)[1]$, carrying distinguished triangles to distinguished triangles.

Definition 57.1.6: Cohomological Functor

Let $\mathcal{K}$ be a triangulated category and $\mathbf{A}$ an abelian category. An additive functor $H\colon \mathcal{K} \to \mathbf{A}$ is *cohomological* if for every distinguished triangle (u, v, w) on (A, B, C) the sequence

$$H(A) \xrightarrow{H(u)} H(B) \xrightarrow{H(v)} H(C)$$

is exact at $H(B)$.

The definition asks for exactness at one spot, and rotation delivers the rest: applying H to every rotate of a distinguished triangle and splicing gives the long exact sequence

$$\cdots \to H(A[n]) \to H(B[n]) \to H(C[n]) \to H(A[n+1]) \to \cdots$$

This is the mechanism promised at the start of the section. The connecting morphism δ is no longer constructed by a diagram chase. It is the image under H of the third edge w, which the triangle carried all along.

Lemma 57.1.7: Consecutive Maps of a Distinguished Triangle Compose to Zero

Let (u, v, w) be a distinguished triangle on (A, B, C) in a triangulated category $\mathcal{K}$. Then $vu = 0$, $wv = 0$ and $u[1]\, w = 0$.

***Proof*:**
By (TR1) the triangle $(\mathrm{id}_A, 0, 0)$ on $(A, A, 0)$ is distinguished. Take $f = \mathrm{id}_A$ and $g = u$ in (TR3), against the two distinguished triangles

$$A \xrightarrow{\mathrm{id}_A} A \xrightarrow{0} 0 \xrightarrow{0} A[1] \qquad \text{and} \qquad A \xrightarrow{u} B \xrightarrow{v} C \xrightarrow{w} A[1]$$

The required square commutes, since $u \circ \mathrm{id}_A = u = u \circ \mathrm{id}_A$. So (TR3) gives $h\colon 0 \to C$ making the triple a morphism of triangles, and commutativity of the middle square reads $v \circ u = h \circ 0 = 0$. This is $vu = 0$.

Rotating the triangle once by (TR2) gives the distinguished triangle $(v, w, -u[1])$ on $(B, C, A[1])$. Its first two maps compose to zero by the case already proved, so $wv = 0$. Rotating once more gives $(w, -u[1], -v[1])$, whence $(-u[1])w = 0$ and so $u[1]\, w = 0$.

Proposition 57.1.8: Hom Is Cohomological

Let $\mathcal{K}$ be a triangulated category and $X \in \mathcal{K}$. Then $\mathrm{Hom}_{\mathcal{K}}(X, -)\colon \mathcal{K} \to \mathbf{Ab}$ is cohomological, and $\mathrm{Hom}_{\mathcal{K}}(-, X)\colon \mathcal{K}^{\mathrm{op}} \to \mathbf{Ab}$ is cohomological.

***Proof*:**
Let (u, v, w) be distinguished on (A, B, C) and let $X \in \mathcal{K}$. Write $u_* = \mathrm{Hom}(X, u)$ and similarly for v.

Step 1: $v_* u_* = 0$. By lemma 57.1.7 the composite vu is zero, so $v_* u_*(\varphi) = vu\varphi = 0$ for every $\varphi \in \mathrm{Hom}(X, A)$. Hence $\mathrm{im} u_* \subseteq \ker v_*$.

Step 2: $\ker v_* \subseteq \mathrm{im} u_*$. Let $\psi \in \mathrm{Hom}(X, B)$ with $v\psi = 0$. Consider the distinguished triangle $(\mathrm{id}_X, 0, 0)$ on $(X, X, 0)$ from (TR1) and the triangle (u, v, w), and rotate both once by (TR2) to get distinguished triangles on $(X, 0, X[1])$ and $(B, C, A[1])$. The square

$$\begin{array}{ccc} X & \longrightarrow & 0 \\ {\scriptstyle \psi}\downarrow & & \downarrow \\ B & \xrightarrow[v]{} & C \end{array}$$

commutes precisely because $v\psi = 0$, so (TR3) gives a morphism $X[1] \to A[1]$ completing it to a morphism of triangles. Since $[1]$ is an automorphism, that morphism is $\varphi[1]$ for a unique $\varphi\colon X \to A$, and commutativity of the remaining square gives $u\varphi = \psi$. Hence $\psi \in \mathrm{im} u_*$.

The two inclusions give exactness at $\mathrm{Hom}(X, B)$, which is the definition. The contravariant statement is the same argument applied in $\mathcal{K}^{\mathrm{op}}$, which is triangulated with translation $[-1]$.

Two consequences follow at once, and the second is the substitute for functoriality promised above.

Corollary 57.1.9: The Five Lemma for Distinguished Triangles

Let (f, g, h) be a morphism of distinguished triangles in $\mathcal{K}$, from (u, v, w) on (A, B, C) to (u', v', w') on (A', B', C'). If f and g are isomorphisms, so is h.

***Proof*:**
Fix $X \in \mathcal{K}$ and apply $\mathrm{Hom}_{\mathcal{K}}(X, -)$. By proposition 57.1.8 and rotation, each triangle gives a long exact sequence of abelian groups, and (f, g, h) induces a morphism between them. In the five consecutive terms

$$\mathrm{Hom}(X, A) \to \mathrm{Hom}(X, B) \to \mathrm{Hom}(X, C) \to \mathrm{Hom}(X, A[1]) \to \mathrm{Hom}(X, B[1])$$

the maps induced by f, g, $f[1]$ and $g[1]$ are isomorphisms, $[1]$ being an automorphism of $\mathcal{K}$. The five lemma (lemma 56.1.22) in $\mathbf{Ab}$ gives that $h_* \colon \mathrm{Hom}(X, C) \to \mathrm{Hom}(X, C')$ is an isomorphism.

It remains to produce an inverse for h itself, which needs no Yoneda argument. Take $X = C'$: surjectivity of h_* gives $k \colon C' \to C$ with $hk = \mathrm{id}_{C'}$. Take $X = C$: both kh and id_C are carried by h_* to h, since $h(kh) = (hk)h = h$, so injectivity of h_* forces $kh = \mathrm{id}_C$. Thus k is a two-sided inverse and h is an isomorphism.

Proposition 57.1.10: A Distinguished Triangle Is Determined by Any One of Its Maps

Let (u, v, w) on (A, B, C) and (u, v', w') on (A, B, C') be distinguished triangles sharing the morphism $u \colon A \to B$. Then there is an isomorphism $h \colon C \to C'$ with $(\mathrm{id}_A, \mathrm{id}_B, h)$ a morphism of triangles.

***Proof*:**
Apply (TR3) with $f = \mathrm{id}_A$ and $g = \mathrm{id}_B$. The required square commutes, both composites being u, so there is $h \colon C \to C'$ making $(\mathrm{id}_A, \mathrm{id}_B, h)$ a morphism of triangles. Its two outer maps are identities, hence isomorphisms, so corollary 57.1.9 gives that h is an isomorphism.

The cone of a morphism is therefore unique up to isomorphism, and that is all: the isomorphism h is produced by (TR3), which does not claim it is unique, so the axioms provide no functorial choice of cone. Everything awkward about triangulated categories descends from this one gap.

One fact the verification needs is used twice more in this chapter and is stated nowhere earlier, so it is recorded here.

Lemma 57.1.11: The Cone on an Identity Is Null-Homotopic

Let $L^\bullet \in \mathrm{Ch}(\mathbf{A})$. Then $MC(\mathrm{id}_{L^\bullet})$ is null-homotopic, hence exact, and is isomorphic to 0 in $\mathrm{K}(\mathbf{A})$.

***Proof*:**
By definition 56.1.23, $MC(\mathrm{id}_L)^i = L^{i+1} \oplus L^i$ with

$$d^i(a,b) = \big(-d_L^{i+1}(a),\ a + d_L^i(b)\big)$$

Define $s^i \colon MC(\mathrm{id}_L)^i \to MC(\mathrm{id}_L)^{i-1} = L^i \oplus L^{i-1}$ by $s^i(a,b) := (b,0)$. Then

$$\begin{aligned} d^{i-1}s^i(a,b) &= d^{i-1}(b,0) = \big(-d_L^i(b),\ b\big), \\ s^{i+1}d^i(a,b) &= s^{i+1}\big(-d_L^{i+1}(a),\ a + d_L^i(b)\big) = \big(a + d_L^i(b),\ 0\big) \end{aligned}$$


Adding, $\big(ds + sd\big)(a,b) = \big(-d_L^i(b) + a + d_L^i(b),\ b\big) = (a,b)$, so $ds + sd = \mathrm{id}$ and s is a contracting homotopy for the identity.

Exactness follows: by proposition 56.1.29 a null-homotopic map induces the zero map on cohomology, so $H^i(\mathrm{id}) = 0$ for every i. But H^i is a functor, so $H^i(\mathrm{id}) = \mathrm{id}_{H^i(MC(\mathrm{id}_L))}$. An identity that is also the zero map forces $H^i\big(MC(\mathrm{id}_L)\big) = 0$. In $\mathrm{K}(\mathbf{A})$ the identity of $MC(\mathrm{id}_L)$ and the zero morphism are the same homotopy class, which is what it means for the object to be isomorphic to 0 there.

The example the chapter is built on is $\mathrm{K}(\mathbf{A})$, the homotopy category of definition 56.1.38. Its translation is the shift, and its distinguished triangles are declared by the mapping cone.

Theorem 57.1.12: The Homotopy Category Is Triangulated

Let $\mathbf{A}$ be an abelian category. Then $\mathrm{K}(\mathbf{A})$ is a triangulated category, with translation the shift [1] and with distinguished triangles those isomorphic in $\mathrm{K}(\mathbf{A})$ to a *mapping cone triangle*



for some chain map $\alpha^\bullet \colon L^\bullet \to M^\bullet$. The same holds for the bounded variants $\mathrm{K}^+(\mathbf{A})$, $\mathrm{K}^-(\mathbf{A})$ and $\mathrm{K}^b(\mathbf{A})$.

***Proof*:**
That $\mathrm{K}(\mathbf{A})$ is additive is lemma 56.1.39, and the shift is an automorphism of it because it is an automorphism of $\mathrm{Ch}(\mathbf{A})$ carrying chain homotopies to chain homotopies.

(TR1). Every $\alpha^\bullet$ embeds in its own mapping cone triangle, which is distinguished by definition. The triangle $(\mathrm{id}_A, 0, 0)$ is distinguished because $MC(\mathrm{id}_A)$ is null-homotopic (lemma 57.1.11), hence zero in $\mathrm{K}(\mathbf{A})$, so the cone triangle on id_A is isomorphic to it. Closure under isomorphism holds by fiat, the class being defined as the isomorphism closure.

(TR2), (TR3), (TR4). Neither (TR2) nor (TR4) holds in $\mathrm{Ch}(\mathbf{A})$ on the nose. The rotate of a cone triangle, and the octahedron's fourth triangle, are cone triangles only up to an explicit homotopy

equivalence between cones, the underlying graded objects being different in general. (TR3) is not like that. Its filler is $h(l,m)=(f(l),g(m))$, a chain map exactly because the hypothesis square $gu=u'f$ closes the second component, so (TR3) holds at the chain level whenever that square commutes strictly. What changes in $\mathrm{K}(\mathbf{A})$ is that the square commutes only up to homotopy, and the filler must absorb the chosen homotopy. The constructions are in Weibel [101], rotation at Example 10.1.6 in §10.1 and (TR3) with the octahedral axiom at Proposition 10.2.4, whose closing homotopy check that book also leaves to its reader. Exercise 57.1.1 (1) asks for the rotation case here, whose sign is the one worth seeing produced.

The theorem also settles a question the mapping cone raises. $\mathrm{Ch}(\mathbf{A})$ itself is *not* triangulated, and the obstruction is visible in one line: (TR1) forces $(\mathrm{id}_{L^\bullet},0,0)$ to be distinguished, so by rotation $L^\bullet$ must be the cone of $0\to L^\bullet$ up to isomorphism, which it is, but (TR1) applied to $\mathrm{id}_{L^\bullet}$, together with proposition 57.1.10 comparing the two distinguished triangles that share $\mathrm{id}_{L^\bullet}$, forces $MC(\mathrm{id}_{L^\bullet})$ to be isomorphic to 0. The cone of the identity is not the zero complex. It is only null-homotopic, so the isomorphism exists in $\mathrm{K}(\mathbf{A})$ and not in $\mathrm{Ch}(\mathbf{A})$. Passing to homotopy classes is exactly what is needed, and no less.

What remains is that $D(\mathbf{A})$ is triangulated too, and that in $D(\mathbf{A})$, unlike in $\mathrm{K}(\mathbf{A})$, every short exact sequence of complexes yields a distinguished triangle. Both are taken up in section 57.2.

Exercise 57.1.1

1. Verify (TR2) for $\mathrm{K}(\mathbf{A})$ in the rotation direction. Given a chain map $\alpha^\bullet\colon L^\bullet\to M^\bullet$, construct a homotopy equivalence $MC\big(M^\bullet\to MC(\alpha^\bullet)\big)\to L[1]^\bullet$, and check that under it the third map of the rotated triangle is $-\alpha[1]^\bullet$ and not $\alpha[1]^\bullet$. Where in the construction does the sign enter?

2. Rotate a distinguished triangle (u,v,w) three times using (TR2) and write down the result. Show that it is $(-u[1],-v[1],-w[1])$ on $(A[1],B[1],C[1])$, and check that $(-\mathrm{id},\mathrm{id},-\mathrm{id})$ is an isomorphism of triangles from it to $(u[1],v[1],-w[1])$. Then read off the three squares as conditions $(\varepsilon_k+\varepsilon_{k+1})e_k=0$ on the edges e_k, and show that no diagonal $(\varepsilon_1,\varepsilon_2,\varepsilon_3)$ with $\varepsilon_i=\pm\mathrm{id}$ is an isomorphism onto $(u[1],v[1],w[1])$ *provided no edge is annihilated by* 2. Then check that the diagonal $(\mathrm{id},-\mathrm{id},\mathrm{id})$ given above for $(\mathrm{id}_A,0,0)$ satisfies all three squares, and say why it does not contradict the general case. Where would the argument break if (TR2) carried no sign?

3. Let (u,v,w) be a distinguished triangle on (A,B,C) with $C=0$. Show that u is an isomorphism. (Use proposition 57.1.8 and the argument that closes corollary 57.1.9.)

4. Show that a distinguished triangle (u,v,w) with $w=0$ splits, in the sense that v admits a section $s\colon C\to B$ and $B\cong A\oplus C$ compatibly with u and v. Deduce that in $\mathrm{K}(\mathbf{A})$ a short exact sequence of complexes that is degreewise split gives a distinguished triangle, and find a short exact sequence of complexes that does not.

5. Let $A\subseteq B\subseteq C$ be subobjects in an abelian category, and consider the three quotient maps. Identify the objects C', A' and B' of (TR4) in this situation, and check that the fourth distinguished triangle it produces is

$$B/A\longrightarrow C/A\longrightarrow C/B$$

This is the third isomorphism theorem, and it is what (TR4) abstracts. Verify the four identities of (TR4) against it.

57.2 The Derived Category as a Triangulated Category

The derived category was produced in section 55.2 as a localization and recorded as corollary 56.1.17. That construction is universal and says nothing about how a morphism of $D(\mathbf{A})$ looks. This section gives the concrete description, shows that $D(\mathbf{A})$ inherits the structure of definition 57.1.3, and proves the property that motivated the whole apparatus: in $D(\mathbf{A})$, and not in $\mathrm{K}(\mathbf{A})$, every short exact sequence of complexes becomes a distinguished triangle. The treatment follows Aluffi's *Algebra: Chapter 0* [3] and Weibel [101] §10.4.

The objects of $D(\mathbf{A})$ are those of $\mathrm{Ch}(\mathbf{A})$. What changes is the morphisms, because the quasi-isomorphisms must become invertible. A first attempt would localize $\mathrm{Ch}(\mathbf{A})$ directly. It fails, and for a reason already recorded in box 56.1.18: the quasi-isomorphisms of $\mathrm{Ch}(\mathbf{A})$ do not form a multiplicative system, so theorem 55.2.5 does not apply and the localization is produced only as a category whose Hom-classes need not be sets. In $\mathrm{K}(\mathbf{A})$ they do form a multiplicative system, and the calculus of fractions then presents every morphism concretely.

Definition 57.2.1: Roof

Let $L^\bullet, M^\bullet \in \mathrm{K}(\mathbf{A})$. A *roof* from $L^\bullet$ to $M^\bullet$ is a diagram

$$\begin{array}{ccc} & N^\bullet & \\ {\scriptstyle s}\swarrow & & \searrow{\scriptstyle f} \\ L^\bullet & & M^\bullet \end{array}$$

in $\mathrm{K}(\mathbf{A})$ in which s is a quasi-isomorphism. Two roofs $(N^\bullet, s, f)$ and $(N'^\bullet, s', f')$ are *equivalent* if there is a third roof $(N''^\bullet, t, g)$ and morphisms $a\colon N''^\bullet \to N^\bullet$ and $b\colon N''^\bullet \to N'^\bullet$ with $sa = t = s'b$ and $fa = g = f'b$ in $\mathrm{K}(\mathbf{A})$. The maps a and b are then automatically quasi-isomorphisms, by two-out-of-three applied to $sa = t$ and $s'b = t$, so nothing is lost by not requiring it.

The roof is the fraction $f \circ s^{-1}$ written before s^{-1} exists. Composition is where the multiplicative system earns its place: to compose fs^{-1} with gt^{-1} one must rewrite $s^{-1}g$ as $g'(s')^{-1}$ for some new roof, and the Ore condition inside theorem 55.2.5 is exactly the hypothesis that this is always possible.

Everything in this section rests on one theorem, and it is the reason the passage from $\mathrm{Ch}(\mathbf{A})$ to $\mathrm{K}(\mathbf{A})$ is made at all. In $\mathrm{Ch}(\mathbf{A})$ the quasi-isomorphisms are not a multiplicative system, as box 56.1.18 shows by example. In $\mathrm{K}(\mathbf{A})$ they are, and the proof is where the triangulated structure of section 57.1 first does work.

One preliminary is needed. Proposition 56.1.24 gives a long exact cohomology sequence for a mapping cone triangle, and since every distinguished triangle of $\mathrm{K}(\mathbf{A})$ is isomorphic to one, that is a statement about all of them.

Lemma 57.2.2: Cohomology Is Cohomological on the Homotopy Category

For each n the functor $H^n\colon \mathrm{K}(\mathbf{A}) \to \mathbf{A}$ is cohomological in the sense of definition 57.1.6. In particular, if (u, v, w) is a distinguished triangle of $\mathrm{K}(\mathbf{A})$ on (A, B, C) with C exact, then u is a quasi-isomorphism.

***Proof*:**
H^n is well defined on $\mathrm{K}(\mathbf{A})$ because homotopic maps induce the same map on cohomology (proposition 56.1.31).

Let (u, v, w) be distinguished. By theorem 57.1.12 it is isomorphic to a mapping cone triangle, for which proposition 56.1.24 gives the long exact cohomology sequence, exact in particular at the middle term. An isomorphism of triangles induces isomorphisms on each H^n, and exactness transports along them, so the sequence $H^n(A) \to H^n(B) \to H^n(C)$ is exact for (u, v, w) as well.

For the consequence, rotate by (TR2) and splice as after definition 57.1.6 to obtain

$$H^{n-1}(C) \to H^n(A) \xrightarrow{H^n(u)} H^n(B) \to H^n(C)$$

exact for every n. If C is exact the outer terms vanish, so each $H^n(u)$ is an isomorphism.

The theorem itself is Weibel [101] Proposition 10.4.1(1). Both substantial conditions follow the same pattern: replace a quasi-isomorphism by the triangle it sits in, note that the third vertex is exact, and use the exactness of Hom on that triangle to factor the morphism that must be killed.

Theorem 57.2.3: Quasi-Isomorphisms Form a Multiplicative System

Let $\mathbf{A}$ be an abelian category. The class of quasi-isomorphisms in $\mathrm{K}(\mathbf{A})$ is a multiplicative system in the sense of definition 55.2.4.

***Proof*:**
Throughout, if t is a quasi-isomorphism then any distinguished triangle on t has exact third vertex: the mapping cone triangle on t has third vertex $MC(t)$, exact by proposition 56.1.26, and any other is isomorphic to it by proposition 57.1.10, an isomorphism of $\mathrm{K}(\mathbf{A})$ being a homotopy equivalence and so preserving cohomology (proposition 56.1.33).

Condition (1). Each $H^n(\mathrm{id})$ is an identity, and $H^n(gf) = H^n(g)H^n(f)$, so identities are quasi-isomorphisms and a composite of two is one.

Condition (2), the Ore condition. Let $f\colon Z \to B$ be any morphism and $t\colon V \to B$ a quasi-isomorphism. Embed t in a distinguished triangle

$$V \xrightarrow{t} B \xrightarrow{g} C \longrightarrow V[1]$$

by (TR1). By the paragraph above, C is exact. Apply (TR1) to $gf\colon Z \to C$ and rotate backwards by (TR2) to obtain a distinguished triangle

$$Z' \xrightarrow{t'} Z \xrightarrow{gf} C \longrightarrow Z'[1]$$

Its third vertex C is exact, so t' is a quasi-isomorphism by lemma 57.2.2.

It remains to factor ft' through t. By lemma 57.1.7 applied to the second triangle, $(gf)t' = 0$,

that is $g(ft') = 0$. Apply $\mathrm{Hom}_{\mathrm{K}(\mathbf{A})}(Z', -)$ to the first triangle: by proposition 57.1.8 the sequence

$$\mathrm{Hom}(Z', V) \xrightarrow{t_*} \mathrm{Hom}(Z', B) \xrightarrow{g_*} \mathrm{Hom}(Z', C)$$

is exact at the middle term. Since ft' lies in $\ker g_*$, there is $f' \colon Z' \to V$ with $tf' = ft'$, which is condition (2).

Condition (3). Let $f, g \colon X \to Y$ and let $s \colon Y \to Y'$ be a quasi-isomorphism with $sf = sg$. Put $h := f - g$, using that $\mathrm{K}(\mathbf{A})$ is additive (lemma 56.1.39). Then $sh = 0$, and it suffices to find a quasi-isomorphism t with $ht = 0$.

Embed s in a distinguished triangle and rotate backwards to put s in the middle:

$$W \xrightarrow{r} Y \xrightarrow{s} Y' \longrightarrow W[1]$$

The third vertex of a triangle on s is exact, and W is its shift, so W is exact as well. Applying $\mathrm{Hom}_{\mathrm{K}(\mathbf{A})}(X, -)$ and proposition 57.1.8 gives exactness of

$$\mathrm{Hom}(X, W) \xrightarrow{r_*} \mathrm{Hom}(X, Y) \xrightarrow{s_*} \mathrm{Hom}(X, Y')$$

at the middle term, and $h \in \ker s_*$, so $h = rh'$ for some $h' \colon X \to W$.

Now apply (TR1) to h' and rotate backwards, giving a distinguished triangle

$$X' \xrightarrow{t} X \xrightarrow{h'} W \longrightarrow X'[1]$$

whose third vertex W is exact, so t is a quasi-isomorphism by lemma 57.2.2. By lemma 57.1.7, $h't = 0$, whence

$$ht = rh't = 0$$

that is, $ft = gt$. This is condition (3), and the three conditions together are the definition.

The theorem discharges an obligation the book has carried since corollary 56.1.17. Box 56.1.18 observed that the quasi-isomorphisms of $\mathrm{Ch}(\mathbf{A})$ are not a multiplicative system and pointed here for the proof that those of $\mathrm{K}(\mathbf{A})$ are. That makes roofs available. Local smallness needs in addition the cofinal set of box 55.2.3, taken up after the next theorem.

Theorem 57.2.4: Roofs Compute the Derived Category

Let $\mathbf{A}$ be an abelian category. Then every morphism $L^\bullet \to M^\bullet$ of $D(\mathbf{A})$ is represented by a roof, two roofs represent the same morphism exactly when they are equivalent, composition is induced by the Ore condition, and the localization functor $Q\colon \mathrm{K}(\mathbf{A}) \to D(\mathbf{A})$ sends f to the class of the roof $(L^\bullet, \mathrm{id}, f)$.
The equivalence classes form a *set* when $\mathbf{A}$ is such that the quasi-isomorphisms into each complex admit a cofinal set. Without that hypothesis they are not guaranteed to be sets. The hypothesis is sufficient and is not necessary for a particular Hom-class to be a set: $\mathrm{Hom}_{D(\mathbf{A})}(0, M^\bullet)$ is a singleton for every $\mathbf{A}$, since any two roofs out of 0 are equivalent through the roof $(0, \mathrm{id}_0, 0)$.

***Proof*:**
By theorem 57.2.3 the quasi-isomorphisms of $\mathrm{K}(\mathbf{A})$ form a multiplicative system, so theorem 55.2.5 applies and gives this description of $\mathrm{K}(\mathbf{A})[\mathrm{qis}^{-1}]$.

It remains to identify that localization with $D(\mathbf{A})$, which corollary 56.1.17 defines as $\mathrm{Ch}(\mathbf{A})[\mathrm{qis}^{-1}]$ and so does not do on its own. The bridge is proposition 56.1.40: *any* functor out of $\mathrm{Ch}(\mathbf{A})$ inverting quasi-isomorphisms factors uniquely through $\mathrm{K}(\mathbf{A})$, and the factored functor inverts the quasi-isomorphisms there, those being the images of quasi-isomorphisms. So a functor out of $\mathrm{Ch}(\mathbf{A})$ inverting quasi-isomorphisms is the same thing as a functor out of $\mathrm{K}(\mathbf{A})$ doing so, compatibly with composition, and the two localizations satisfy the same universal property of definition 55.2.1 over *all* functors. They are therefore canonically isomorphic.

The quantifier matters. Restricting the comparison to *additive* functors would be circular, since the additive structure on $D(\mathbf{A})$ is derived in theorem 57.2.7 from the roof description being established here.

Inverting a single morphism is the case $M^\bullet = N^\bullet$, $f = \mathrm{id}$: the roof $(N^\bullet, s, \mathrm{id})$ is the inverse of $Q(s)$.

The set-hood clause is not a formality, and box 55.2.3 is where the difficulty was recorded: a calculus of fractions replaces zigzags by roofs without bounding anything, the roofs over a fixed object being indexed by a proper class. What bounds them is a *set* of quasi-isomorphisms cofinal among those into each complex. Every construction in this chapter is stated for $D(\mathbf{A})$ as a category. Only the statements quantifying over its Hom-*sets* need the hypothesis, and they say so. For a Grothendieck abelian category, which includes R-Mod and the categories of sheaves of abelian groups on a site (example 59.1.5), every Hom-class of $D(\mathbf{A})$ is a set by corollary 59.1.21, whose proof uses K-injective resolutions and no cofinality hypothesis.

57.2.5 Note: What the Bounded Variants Are For Writing $D^+(\mathbf{A})$, $D^-(\mathbf{A})$ and $D^b(\mathbf{A})$ for the full subcategories of $D(\mathbf{A})$ on the complexes with cohomology bounded below, bounded above, and bounded respectively, each is *equivalent* to the localization of the corresponding $\mathrm{K}^{\pm}(\mathbf{A})$ at its quasi-isomorphisms. Equivalent and not equal: the localization of $\mathrm{K}^b(\mathbf{A})$ has only bounded complexes as objects, whereas $D^b(\mathbf{A})$ as defined here contains every complex with bounded cohomology, such as the exact 2-periodic complex $\cdots \to \mathbb{Z}/4 \xrightarrow{2} \mathbb{Z}/4 \to \cdots$. Truncation gives essential surjectivity: if $H^i(X) = 0$ for $i < m$, then $p_m \colon X \to \tau^{\geq m} X$ of definition 56.1.12 is a quasi-isomorphism onto a bounded-below complex by proposition 56.1.14, and dually $i_m \colon \tau^{\leq m} X \to X$ when $H^i(X) = 0$ for $i > m$. For the bounded case, if $H^i(X) = 0$ outside $[m, M]$ then $i_M \colon \tau^{\leq M} X \to X$ is a quasi-isomorphism, and so is $p_m \colon \tau^{\leq M} X \to \tau^{\geq m}\tau^{\leq M} X$, since $H^i(\tau^{\leq M} X) \cong H^i(X) = 0$ for $i < m$ by proposition 56.1.14, and $\tau^{\geq m}\tau^{\leq M} X$ is bounded. The equivalence is Weibel [101] 10.3.15. The bound is what makes derived functors constructible: a resolution of a bounded-above complex by projectives is again bounded above, and section 55.2's machinery has something to run on. Chapter 57 states results for $D(\mathbf{A})$ where no bound is needed and says so explicitly where one is.

When $\mathbf{A}$ has enough projectives the bounded-above derived category has a second, entirely computational, description, and the book already has it.

Proposition 57.2.6: Enough Projectives Computes D^-

Let $\mathbf{A}$ be an abelian category with enough projectives and let $\mathbf{P}$ be its full subcategory of projectives. Then $\mathrm{K}^-(\mathbf{P})$ satisfies the universal property of $D^-(\mathbf{A})$: every additive functor out of $C^-(\mathbf{A})$ carrying quasi-isomorphisms to isomorphisms factors through $\mathrm{K}^-(\mathbf{P})$, uniquely up to natural isomorphism.

***Proof*:**
This is theorem 56.2.18, whose part (1) gives that a quasi-isomorphism of $C^-(\mathbf{A})$ becomes an isomorphism in $\mathrm{K}^-(\mathbf{P})$ and whose part (2) is the factorization. That quasi-isomorphisms are already isomorphisms in $\mathrm{K}^-(\mathbf{P})$, so that no further localization is needed, is corollary 56.2.10.

The point is worth stating plainly because it is easy to misremember in a form that is false. In general $\mathrm{K}(\mathbf{A})$ is *not* the localization of $\mathrm{Ch}(\mathbf{A})$ at the quasi-isomorphisms, with or without enough projectives. It inverts the homotopy equivalences, and for $\mathbf{A} = \mathbf{Ab}$ those are strictly fewer: example 56.1.16 exhibits a quasi-isomorphism with no inverse in $\mathrm{K}(\mathbf{Ab})$. What enough projectives gives is that the homotopy category of *projective* complexes, $\mathrm{K}^-(\mathbf{P})$, already has the quasi-isomorphisms inverted, and that is a statement about $\mathbf{P}$ and not about $\mathbf{A}$.

The hedge *in general* is doing work. Over a semisimple $\mathbf{A}$, say Vect_k, which has enough projectives, every complex splits as the direct sum of its cohomology and contractible pieces, so every quasi-isomorphism is already a homotopy equivalence and the two classes coincide. There $\mathrm{K}(\mathbf{A})$ *is* the localization, so over such an $\mathbf{A}$ the claim above is false there. That is why the general statement is given with a cited witness.

With the morphisms described, the structure of section 57.1 transfers.

Theorem 57.2.7: The Derived Category Is Triangulated

Let $\mathbf{A}$ be an abelian category. Then $D(\mathbf{A})$ is a triangulated category, with translation the shift [1] and with distinguished triangles those isomorphic in $D(\mathbf{A})$ to the image under Q of a distinguished triangle of $\mathrm{K}(\mathbf{A})$. The localization functor $Q\colon \mathrm{K}(\mathbf{A}) \to D(\mathbf{A})$ is a triangulated functor in the sense of definition 57.1.5. The same holds for D^{+}, D^{-} and D^{b}.

***Proof*:**
The shift commutes with localization, since it carries quasi-isomorphisms to quasi-isomorphisms, and so descends to an automorphism of $D(\mathbf{A})$. $D(\mathbf{A})$ is additive because $\mathrm{K}(\mathbf{A})$ is (lemma 56.1.39) and the localization of an additive category at a multiplicative system is again additive, sums of roofs being formed over a common denominator and biproducts surviving. Theorem 55.2.5 is a statement about categories with no additive content, and the fact used here is Weibel [101] 10.3.11.

(TR1). A morphism of $D(\mathbf{A})$ is a roof fs^{-1}, and $Q(s)$ is invertible, so it is enough to embed f. Theorem 57.1.12 does that in $\mathrm{K}(\mathbf{A})$, and applying Q and composing with the isomorphism $Q(s)$ gives a distinguished triangle on fs^{-1}. The triangle $(\mathrm{id}, 0, 0)$ is the Q-image of the corresponding triangle of $\mathrm{K}(\mathbf{A})$, and closure under isomorphism holds because the class was defined as an isomorphism closure.

(TR2), (TR3), (TR4). These are Weibel [101] Proposition 10.4.1(2), and the deferral is deliberate. The obstacle is that a distinguished triangle of $D(\mathbf{A})$ is only *isomorphic* to a Q-image, and that (TR3)'s hypothesis square commutes in $D(\mathbf{A})$ and so only up to homotopy after lifting. Verdier's argument straightens the data with the Ore condition, rebuilds the triangles over the refined vertices using (TR1), (TR3) and corollary 57.1.9, applies the axiom in $\mathrm{K}(\mathbf{A})$, and conjugates back. Weibel calls the verification straightforward but lengthy, and it needs two-sided fractions, which definition 55.2.4 does not carry. No argument in this book depends on reproducing it.

Q carries distinguished triangles to distinguished triangles by the definition given, and commutes with the shift by the first paragraph, so it is a triangulated functor. The bounded cases are the same argument applied to $\mathrm{K}^{\pm}(\mathbf{A})$.

Proposition 57.2.8: Cohomology Is Cohomological on $D(\mathbf{A})$

For each n the functor $H^{n}\colon D(\mathbf{A}) \to \mathbf{A}$ is well defined and cohomological in the sense of definition 57.1.6.

***Proof*:**
H^{n} is well defined on $D(\mathbf{A})$ because a quasi-isomorphism induces an isomorphism on H^{n} by definition, so H^{n} inverts the class being localized and factors through Q by the universal property of theorem 55.2.2.

For the cohomological property, let (u, v, w) be distinguished in $D(\mathbf{A})$. By definition it is

isomorphic to Q of a distinguished triangle of $\mathrm{K}(\mathbf{A})$, which by theorem 57.1.12 is isomorphic to a mapping cone triangle. For a mapping cone triangle the required exactness at the middle term is proposition 56.1.24, which produces exactly the long exact cohomology sequence of the cone. Exactness is preserved along the isomorphisms, so it holds for (u, v, w).

The failure that section 57.1 opened with can now be repaired. A short exact sequence of complexes has a connecting morphism on cohomology but, in $\mathrm{K}(\mathbf{A})$, need not have any morphism $N^\bullet \to L[1]^\bullet$ at all. The cone gives a candidate, and in $D(\mathbf{A})$ the candidate is an isomorphism.

Lemma 57.2.9: The Cone of an Injection Computes the Quotient

Let

$$0 \to L^\bullet \xrightarrow{u} M^\bullet \xrightarrow{v} N^\bullet \to 0$$

be a short exact sequence in $\mathrm{Ch}(\mathbf{A})$, meaning exact in each degree. Define $\varphi\colon MC(u)^\bullet \to N^\bullet$ by $\varphi^i(l, m) := v^i(m)$, where $MC(u)^i = L^{i+1} \oplus M^i$ as in definition 56.1.23. Then φ is a chain map and a quasi-isomorphism.

***Proof*:**

Step 1: φ is a chain map. With the differential of definition 56.1.23,

$$\varphi^{i+1}\big(d^i_{MC(u)}(l, m)\big) = \varphi^{i+1}\big(-d^{i+1}_L(l),\ u^{i+1}(l) + d^i_M(m)\big) = v^{i+1}u^{i+1}(l) + v^{i+1}d^i_M(m)$$

The first term vanishes because $vu = 0$, the sequence being exact at $M^\bullet$. The second is $d^i_N v^i(m)$ because v is a chain map. So $\varphi^{i+1}d^i_{MC(u)} = d^i_N\varphi^i$.

Step 2: the kernel of φ. In degree i, $\ker\varphi^i = \{(l, m) : v^i(m) = 0\} = L^{i+1} \oplus \ker v^i = L^{i+1} \oplus u^i(L^i)$, using exactness at $M^\bullet$. Since u is a monomorphism, $u^i(L^i) \cong L^i$, so $\ker\varphi^\bullet$ is the complex with $(\ker\varphi)^i = L^{i+1} \oplus L^i$ and differential $(l, l') \mapsto (-d^{i+1}_L(l),\ l + d^i_L(l'))$ read through u. This is exactly $MC(\mathrm{id}_{L^\bullet})$.

Step 3: φ is surjective in each degree, since v is. So

$$0 \to MC(\mathrm{id}_{L^\bullet}) \to MC(u)^\bullet \xrightarrow{\varphi} N^\bullet \to 0$$

is a short exact sequence of complexes. By lemma 57.1.11 the cone on an identity map is null-homotopic, hence exact, so $H^i\big(MC(\mathrm{id}_{L^\bullet})\big) = 0$ for every i. The long exact cohomology sequence of the displayed short exact sequence (theorem 56.1.20) then has zeroes flanking every $H^i(\varphi)$, forcing each $H^i(\varphi)$ to be an isomorphism. Thus φ is a quasi-isomorphism.

Theorem 57.2.10: Every Short Exact Sequence Gives a Distinguished Triangle in $D(\mathbf{A})$

Let $0 \to L^\bullet \xrightarrow{u} M^\bullet \xrightarrow{v} N^\bullet \to 0$ be a short exact sequence in $\mathrm{Ch}(\mathbf{A})$. Then there is a morphism $w\colon N^\bullet \to L[1]^\bullet$ in $D(\mathbf{A})$ for which

$$L^\bullet \xrightarrow{u} M^\bullet \xrightarrow{v} N^\bullet \xrightarrow{w} L[1]^\bullet$$

is a distinguished triangle of $D(\mathbf{A})$, and $H^\bullet(w) = -\delta$, where δ is the connecting morphism of theorem 56.1.20.

***Proof*:**
Let $\iota\colon M^\bullet \to MC(u)^\bullet$ and $\pi\colon MC(u)^\bullet \to L[1]^\bullet$ be the two natural chain maps of definition 56.1.23, so that (u, ι, π) is the mapping cone triangle on u and is distinguished in $\mathrm{K}(\mathbf{A})$ by theorem 57.1.12. Let $\varphi\colon MC(u)^\bullet \to N^\bullet$ be the quasi-isomorphism of lemma 57.2.9.

Step 1: φ is invertible in $D(\boldsymbol{A})$. It is a quasi-isomorphism, and Q inverts exactly those.

Step 2: the triangle. Set $w := Q(\pi) \circ Q(\varphi)^{-1}\colon N^\bullet \to L[1]^\bullet$. The triple $(\mathrm{id}_{L^\bullet}, \mathrm{id}_{M^\bullet}, Q(\varphi))$ is an isomorphism of triangles from $Q(u, \iota, \pi)$ to (u, v, w), provided the middle square commutes, that is $\varphi \circ \iota = v$. In degree i, $\iota^i(m) = (0, m)$ and $\varphi^i(0, m) = v^i(m)$, so the square commutes on the nose in $\mathrm{Ch}(\mathbf{A})$.

The third square commutes by the definition of w. Since $Q(u, \iota, \pi)$ is distinguished in $D(\mathbf{A})$ by theorem 57.2.7, and distinguished triangles are closed under isomorphism by (TR1), the triangle (u, v, w) is distinguished.

Step 3: the sign. Let $x \in N^n$ be a cocycle. Choose $m \in M^n$ with $v(m) = x$. Then $v(d_M m) = d_N x = 0$, so $d_M m = u(\lambda)$ for a unique $\lambda \in L^{n+1}$, and $\delta[x] = [\lambda]$ by the construction in theorem 56.1.20. Now compute $H^n(w)[x]$ directly. A cocycle of $MC(u)^n$ lying over x is a pair (l, m) with $\varphi(l, m) = v(m) = x$ and

$$0 = d_{MC(u)}(l, m) = \big(-d_L(l),\ u(l) + d_M(m)\big)$$

The second component forces $u(l) = -d_M m = -u(\lambda)$, and u is a monomorphism, so $l = -\lambda$. Such a pair does exist: the first component asks $d_L(\lambda) = 0$, which holds because $u(d_L\lambda) = d_M(u\lambda) = d_M d_M m = 0$ and u is a monomorphism. Since $w = Q(\pi) \circ Q(\varphi)^{-1}$ and $\pi(l, m) = l$ carries no sign in definition 56.1.23,

$$H^n(w)[x] = [l] = [-\lambda] = -\delta[x]$$

so $H^\bullet(w) = -\delta$.

The sign is not an artifact of this book's conventions, which is the natural thing to assume and is wrong. Definition 56.1.23 puts the sign on d_L and none on α or on the projection π. Weibel flips both: his cone differential carries $-\alpha$ and his projection carries a minus. Under his conventions the second component forces $u(l) = +d_M m$, so $l = +\lambda$, and the signed projection returns $-\lambda$

again. The two flips cancel each other, and $-\delta$ is what both conventions produce. A mixed convention, flipping exactly one of the two, is what would give $+\delta$.

Nor is the sign available to be absorbed into w. The diagonal comparison of exercise 57.1.1 (2) fails for $(u, v, -w)$ against (u, v, w), so $(u, v, -w)$ is not known to be distinguished.

The contrast with $\mathrm{K}(\mathbf{A})$ is not a matter of the argument being harder there. It is false there.

Example 57.2.11: A Short Exact Sequence That Is No Triangle in K(Ab)

Regard $\mathbb{Z}/2$ and $\mathbb{Z}/4$ as complexes concentrated in degree 0, and take the short exact sequence of abelian groups

$$0 \to \mathbb{Z}/2 \xrightarrow{\cdot 2} \mathbb{Z}/4 \to \mathbb{Z}/2 \to 0$$

There is no morphism w in $\mathrm{K}(\mathbf{Ab})$ making $(\cdot 2, \pi, w)$ a distinguished triangle on $(\mathbb{Z}/2, \mathbb{Z}/4, \mathbb{Z}/2)$.

Suppose there were, and apply $\mathrm{Hom}_{\mathrm{K}(\mathbf{Ab})}(\mathbb{Z}/2, -)$, which is cohomological by proposition 57.1.8. Every complex in sight is concentrated in degree 0, so $\mathbb{Z}/2[1]$ and $\mathbb{Z}/2[-1]$ are concentrated in degrees -1 and 1, and a chain map between complexes concentrated in different degrees is zero. Both outer terms of the long exact sequence therefore vanish, leaving

$$0 \to \mathrm{Hom}(\mathbb{Z}/2, \mathbb{Z}/2) \to \mathrm{Hom}(\mathbb{Z}/2, \mathbb{Z}/4) \to \mathrm{Hom}(\mathbb{Z}/2, \mathbb{Z}/2) \to 0$$

exact in $\mathbf{Ab}$, homotopies between degree-0 complexes being zero. Counting: the two outer groups have order 2, so the middle must have order 4. But $\mathrm{Hom}_{\mathbf{Ab}}(\mathbb{Z}/2, \mathbb{Z}/4)$ consists of the maps sending 1 to an element killed by 2, namely 0 and 2, so it has order 2. The contradiction shows no such w exists.

The argument used nothing about w itself, which is the point. The obstruction is not that the third map is hard to write down. It is that no *morphism* closes the triangle at all, whatever is placed at the third edge. The object $\mathbb{Z}/2$ does sit at that vertex in other distinguished triangles, and $\cdot 2$ does embed in one, namely its own cone triangle with third vertex $MC(\cdot 2)$.

In $D(\mathbf{Ab})$ the triangle exists, by theorem 57.2.10. What differs is not the category's objects but its morphisms: w is a roof, invisible from $\mathrm{K}(\mathbf{Ab})$.

Two criteria fall out of the roof description and are used constantly.

Proposition 57.2.12: Recognizing Zero in the Derived Category

Let $\mathbf{A}$ be an abelian category.

1. A complex $X^\bullet$ is isomorphic to 0 in $D(\mathbf{A})$ if and only if $X^\bullet$ is exact.
2. A chain map $f\colon X^\bullet \to Y^\bullet$ becomes the zero morphism in $D(\mathbf{A})$ if and only if there is a quasi-isomorphism $t\colon X''^\bullet \to X^\bullet$ with ft null-homotopic.

***Proof*:**

(1) If $X^\bullet$ is exact then $X^\bullet \to 0$ is a quasi-isomorphism, which Q inverts, so $X^\bullet \cong 0$ in $D(\mathbf{A})$. Conversely, if $X^\bullet \cong 0$ there, then $H^i(X^\bullet) \cong H^i(0) = 0$ for every i, since H^i is a functor on $D(\mathbf{A})$ by proposition 57.2.8. So $X^\bullet$ is exact.

(2) By theorem 57.2.4 the morphism $Q(f)$ is the class of the roof $(X^\bullet, \mathrm{id}, f)$ and the zero morphism is the class of $(X^\bullet, \mathrm{id}, 0)$. Two roofs with the same left leg represent the same morphism exactly when their right legs agree after precomposition with a quasi-isomorphism, which is the equivalence of definition 57.2.1. So $Q(f) = 0$ exactly when there is a quasi-isomorphism t with $ft = 0$ in $\mathrm{K}(\mathbf{A})$, and equality in $\mathrm{K}(\mathbf{A})$ is null-homotopy in $\mathrm{Ch}(\mathbf{A})$.

The criterion is stated with t on the *source* because that is the side definition 55.2.4 controls: its condition (3) cancels a quasi-isomorphism on the target and returns one on the source, and not conversely. The dual form, a quasi-isomorphism s on the target with sf null-homotopic, is equivalent, but deriving it needs the opposite cancellation condition, which the definition used here does not carry. Weibel [101] states the axioms in self-dual form for exactly this reason.

57.2.13 Note: Recovering A from $D(\mathbf{A})$ Distinct abelian categories can have equivalent derived categories, so $\mathbf{A}$ is not recovered from $D(\mathbf{A})$ on its own. What recovers it is an extra piece of data, a *t-structure*, whose heart is an abelian category. Section 59.3 constructs the standard t-structure on $D(\mathbf{A})$, whose heart is equivalent to $\mathbf{A}$, and section 59.4 develops the general theory. The middle-perversity t-structure, whose heart is the category of perverse sheaves, is the subject of the *Perverse Sheaves* volume [38].

57.2.1 Stable Module Theory

Two maps $f, g : M \to N$ of R-modules are *projectively homotopic* when $f - g$ factors through a projective module, $f - g : M \to P \to N$. This is the module-level form of the chain homotopy of section 56.1, and it recovers the geometric intuition directly: two modules can be homotopy equivalent without either one being resolved first. The associated equivalence on objects is *stable equivalence*: modules M and N are stably equivalent when

$$M \oplus P \cong N \oplus P$$

for some projective P. This relation is the starting point of K_0, developed in [14].

Exercise 57.2.1

1. Let $s\colon N^\bullet \to L^\bullet$ be a quasi-isomorphism. Show that the roof $(N^\bullet, s, \mathrm{id}_{N^\bullet})$ represents a two-sided inverse to $Q(s)$ in $D(\mathbf{A})$, and that the equivalence relation of definition 57.2.1 is what makes the two composites equal to the identity roofs.

2. Give a complex of abelian groups that is exact, nonzero in infinitely many degrees, and therefore isomorphic to 0 in $D(\mathbf{Ab})$ while being isomorphic to 0 in neither $\mathrm{Ch}(\mathbf{Ab})$ nor $\mathrm{K}(\mathbf{Ab})$. (For the last point, exhibit the failure of a contracting homotopy, or cite exercise 57.1.1 (4).)

3. Lemma 57.1.11 shows $MC(\mathrm{id}_{L^\bullet})$ is null-homotopic, hence isomorphic to 0 in $\mathrm{K}(\mathbf{A})$. Show that it is nevertheless *not* the zero complex in $\mathrm{Ch}(\mathbf{A})$ whenever $L^\bullet \neq 0$. Then explain why lemma 57.2.9 concludes only that φ is a *quasi-isomorphism*, and not that it is an isomorphism of complexes, even though its kernel is isomorphic to 0 in $\mathrm{K}(\mathbf{A})$.

4. Find chain maps f and g of abelian groups such that f is zero in $D(\mathbf{Ab})$ without being null-homotopic, and g induces the zero map on every cohomology group without being zero in

$D(\mathbf{Ab})$. (For the second, complexes of length two and a map built from multiplication by an integer will do.)

5. Show that $Q\colon \mathrm{K}(\mathbf{Ab}) \to D(\mathbf{Ab})$ is not full by producing a morphism of $D(\mathbf{Ab})$ that is not Q of any chain map. (Example 57.2.11 contains one.)

57.3 Adapted Classes and Total Derived Functors

Section 56.3 built $R^n\mathscr{F}$ by choosing a resolution, applying $\mathscr{F}$ term by term, taking cohomology, and then proving the answer independent of the choice. The derived category was introduced to make that last step unnecessary, so the natural thing to want now is a single functor $R\mathscr{F}$ on $D^+(\mathbf{A})$ whose cohomology returns the $R^n\mathscr{F}$. The obstacle is immediate: $\mathscr{F}$ applied term by term does *not* descend to $D^+(\mathbf{A})$, because a left exact functor need not carry quasi-isomorphisms to quasi-isomorphisms. If it did, all its higher derived functors would vanish.

Example 57.3.1: Termwise Application Does Not Descend
Let $\mathscr{F} = \mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}/2, -)$ on $\mathbf{Ab}$, which is left exact. The chain map

$$\begin{array}{ccc} \mathbb{Z} & \xrightarrow{2} & \mathbb{Z} \\ \downarrow & & \downarrow \\ 0 & \longrightarrow & \mathbb{Z}/2 \end{array}$$

from the complex $(\mathbb{Z} \xrightarrow{2} \mathbb{Z})$ in degrees $-1, 0$ to $\mathbb{Z}/2$ in degree 0 is a quasi-isomorphism. Both complexes have cohomology only in degree 0, and there the induced map is the reduction $\mathbb{Z}/2\mathbb{Z} \to \mathbb{Z}/2$, an isomorphism. Apply $\mathscr{F}$ term by term. The upper complex becomes $\mathrm{Hom}(\mathbb{Z}/2, \mathbb{Z}) \to \mathrm{Hom}(\mathbb{Z}/2, \mathbb{Z})$, which is $0 \to 0$. The lower becomes $\mathrm{Hom}(\mathbb{Z}/2, \mathbb{Z}/2) = \mathbb{Z}/2$ in degree 0. The induced map on H^0 is $0 \to \mathbb{Z}/2$, not an isomorphism.

So the termwise functor does not send this quasi-isomorphism to an isomorphism, and by the universal property of definition 55.2.1 it does not factor through $D^+(\mathbf{Ab})$.

The upper complex is a *projective* resolution of $\mathbb{Z}/2$, and that is the diagnosis. Projective resolutions compute the derived functors of right exact functors. But $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}/2, -)$ is left exact, and the complexes on which it behaves are the injective ones. What follows makes that choice of complexes part of the construction.

The repair is to apply $\mathscr{F}$ only to complexes drawn from a class of objects on which it behaves, and then to check that no information is lost by the restriction. Both halves are packaged in the following definition, which is Gelfand-Manin [53] III.6.3.

Definition 57.3.2: Adapted Class

Let $\mathscr{F}\colon \mathbf{A} \to \mathbf{B}$ be a left exact additive functor. A class $\mathcal{R} \subseteq \operatorname{Ob}\mathbf{A}$, stable under finite direct sums, is *adapted* to $\mathscr{F}$ if

1. $\mathscr{F}$ carries every acyclic complex in $\mathrm{K}^{+}(\mathcal{R})$ to an acyclic complex, and
2. every object of $\mathbf{A}$ is a subobject of an object of $\mathcal{R}$.

For a right exact $\mathscr{F}$ the two conditions are dualized: $\mathscr{F}$ carries acyclic complexes in $\mathrm{K}^{-}(\mathcal{R})$ to acyclic complexes, and every object of $\mathbf{A}$ is a quotient of an object of $\mathcal{R}$.

Condition (2) is what makes the restriction harmless, since it lets every bounded-below complex be replaced by one built from $\mathcal{R}$. Condition (1) is what makes it useful.

Example 57.3.3: Adapted Classes

1. If $\mathbf{A}$ has enough injectives, the class of injective objects is adapted to every left exact $\mathscr{F}$. It is stable under finite direct sums, since $\operatorname{Hom}(-, I_1 \oplus I_2) \cong \operatorname{Hom}(-, I_1) \oplus \operatorname{Hom}(-, I_2)$ is exact when both summands are. Condition (2) is the definition of enough injectives. For condition (1), an acyclic bounded-below complex I of injectives is homotopy equivalent to 0 by the injective case of corollary 56.2.6, so id_I is null-homotopic. The additive functor $\mathscr{F}$ carries that null-homotopy to one of $\mathrm{id}_{\mathscr{F}(I)}$ (lemma 56.1.34), and a complex whose identity is null-homotopic is exact by proposition 56.1.29.

2. Dually, with enough projectives the projectives are adapted to every right exact $\mathscr{F}$.

3. Let R be a ring and N a left R-module. The flat right R-modules form a class adapted to $- \otimes_R N\colon \text{Mod-}R \to \mathbf{Ab}$. The class is stable under finite direct sums, since $(F_1 \oplus F_2) \otimes_R -$ is the direct sum of the exact functors $F_1 \otimes_R -$ and $F_2 \otimes_R -$. Every module is a quotient of a free module, and free modules are flat by corollary 17.5.5, which is the quotient form of condition (2).

   For condition (1), let K be an acyclic bounded-above complex of flat right modules, with $K^i = 0$ for $i > a$, let $\pi\colon P \to N$ be a projective resolution with $P^j = 0$ for $j > 0$, and let C be the exact complex $\cdots \to P^{-1} \to P^0 \xrightarrow{\pi} N$ with N in degree 1. Let T be the total complex of the double complex $K^i \otimes_R C^j$, with differentials $d_K \otimes 1$ and $(-1)^i(1 \otimes d_C)$. Each column $K^i \otimes_R C$ is exact because K^i is flat, so T is exact by proposition 56.5.4, applied after re-indexing so that K and C vanish in positive degrees. After this re-indexing the twist of section 56.5 is $(-1)^{i-a}$, which differs from the sign $(-1)^i$ above by the constant $(-1)^a$, and $x \otimes y \mapsto (-1)^{aj}\, x \otimes y$ for $y \in C^j$ is an isomorphism between the two total complexes, so exactness transfers. The same holds for the quotient below. The terms with $j = 1$ form a subcomplex S with $S^n = K^{n-1} \otimes_R N$ and differential $d_K \otimes 1$, because d_C vanishes on C^1. The quotient T/S is the total complex of $K^i \otimes_R P^j$, whose rows $K \otimes_R P^j$ are exact because each P^j is projective, hence flat. So T/S is exact by proposition 56.5.4 again, and the long exact sequence of theorem 56.1.20 for $0 \to S \to T \to T/S \to 0$ makes S exact, which says that $K \otimes_R N$ is exact.

   This class can be strictly larger than the class of projectives: over $\mathbb{Z}$ the module $\mathbb{Q}$ is flat

and not projective (example 17.5.8). That is the point of allowing a class: a flat resolution, projective or not, computes $L(-\otimes_R N)$.

An adapted class computes the derived category, in the following precise sense. Write $S_{\mathcal{R}}$ for the class of quasi-isomorphisms in $\mathrm{K}^+(\mathcal{R})$.

Theorem 57.3.4: An Adapted Class Computes D^+

Let $\mathcal{R}$ be adapted to a left exact $\mathscr{F}\colon \mathbf{A}\to\mathbf{B}$. Then $S_{\mathcal{R}}$ is a multiplicative system in $\mathrm{K}^+(\mathcal{R})$, and the canonical functor

$$\mathrm{K}^+(\mathcal{R})\big[S_{\mathcal{R}}^{-1}\big] \longrightarrow D^+(\mathbf{A})$$

is an equivalence of categories. The corresponding statement with K^- and D^- holds for a right exact $\mathscr{F}$.

The proof is Gelfand-Manin [53] III.6.4. It repeats their construction of injective resolutions of complexes (III.5.22) with $\mathcal{R}$ in place of the injectives, and its input is the single fact about $\mathcal{R}$ that condition (2) is for: every bounded-below complex K admits a quasi-isomorphism $K\to L$ with L in $\mathrm{K}^+(\mathcal{R})$ (property $(*)$ in that proof). Full faithfulness follows through Gelfand-Manin's criterion III.2.10, condition b2: for every quasi-isomorphism $s\colon L'\to K$ with L' in $\mathrm{K}^+(\mathcal{R})$ there is a quasi-isomorphism $t\colon K\to L$ with ts in $S_{\mathcal{R}}$, which $(*)$ provides. That criterion uses fractions with the quasi-isomorphism on the target, the form theorem 57.2.3 takes when applied to $\mathbf{A}^{\mathrm{op}}$. Essential surjectivity follows from $(*)$ once an object of $D^+(\mathbf{A})$ has been replaced by a bounded-below complex, which is the truncation step of box 57.2.5, by the canonical truncation $\tau^{\geq m}$ of definition 56.1.12 (Weibel [101] 10.3.15).

With the equivalence in hand the construction is short.

Definition 57.3.5: Total Derived Functor

Let $\mathscr{F}\colon \mathbf{A}\to\mathbf{B}$ be left exact and $\mathcal{R}$ a class adapted to it. Define $R\mathscr{F}$ on $\mathrm{K}^+(\mathcal{R})$ term by term,

$$\big(R\mathscr{F}\big)(K^\bullet)^i := \mathscr{F}(K^i)$$

Condition (1) of definition 57.3.2 makes $R\mathscr{F}$ carry the quasi-isomorphisms of $\mathrm{K}^+(\mathcal{R})$ to isomorphisms, so it descends to $\mathrm{K}^+(\mathcal{R})[S_{\mathcal{R}}^{-1}]\to D^+(\mathbf{B})$. Composing with an inverse $\Phi\colon D^+(\mathbf{A})\to \mathrm{K}^+(\mathcal{R})[S_{\mathcal{R}}^{-1}]$ of the equivalence of theorem 57.3.4 gives the *total right derived functor*

$$R\mathscr{F}\colon D^+(\mathbf{A})\longrightarrow D^+(\mathbf{B})$$

The total left derived functor $L\mathscr{F}$ of a right exact $\mathscr{F}$ is defined dually, on D^-.

That $R\mathscr{F}$ carries quasi-isomorphisms to isomorphisms is where condition (1) enters. A morphism $u\colon K\to L$ of $\mathrm{K}^+(\mathcal{R})$ is a quasi-isomorphism exactly when its cone is acyclic (proposition 56.1.26). The cone has terms $K^{n+1}\oplus L^n$, which lie in $\mathcal{R}$ because $\mathcal{R}$ is stable under finite direct sums, so it is a complex of $\mathrm{K}^+(\mathcal{R})$ and condition (1) makes its image under $\mathscr{F}$ acyclic. Being additive, $\mathscr{F}$ commutes with the formation of cones, so $\mathscr{F}(u)$ has acyclic cone and is a quasi-isomorphism.

The definition depends on two choices, $\mathcal{R}$ and Φ, and neither is canonical. What makes $R\mathscr{F}$ well defined regardless is a universal property. To state it, write $\Psi\colon \mathrm{K}^+(\mathcal{R})[S_{\mathcal{R}}^{-1}]\to D^+(\mathbf{A})$ for the equivalence of theorem 57.3.4, $\beta\colon \mathrm{id}\to\Psi\Phi$ for the natural isomorphism that makes Φ an inverse of

Ψ, $Q_{\mathcal{R}}$ for the localization functor of $\mathrm{K}^+(\mathcal{R})$, and $\bar{\mathscr{F}}\colon \mathrm{K}^+(\mathcal{R})[S_{\mathcal{R}}^{-1}] \to D^+(\mathbf{B})$ for the functor induced by $\mathscr{F}$ term by term, so that $R\mathscr{F} = \bar{\mathscr{F}}\Phi$.

Theorem 57.3.6: The Total Derived Functor Is Universal

Let $\mathscr{F}\colon \mathbf{A} \to \mathbf{B}$ be left exact, let $\mathcal{R}$ be adapted to $\mathscr{F}$, and let $R\mathscr{F}$ be built from $\mathcal{R}$ and Φ as in definition 57.3.5. Write $Q_{\mathbf{A}}$ and $Q_{\mathbf{B}}$ for the localization functors of $\mathrm{K}^+(\mathbf{A})$ and $\mathrm{K}^+(\mathbf{B})$. For $X \in \mathrm{K}^+(\mathbf{A})$ put $Y := \Phi(Q_{\mathbf{A}}X)$, choose a quasi-isomorphism $s\colon X \to Z$ with Z in $\mathrm{K}^+(\mathcal{R})$, let $\gamma\colon Y \to Z$ be the isomorphism of $\mathrm{K}^+(\mathcal{R})[S_{\mathcal{R}}^{-1}]$ with $\Psi(\gamma) = Q_{\mathbf{A}}(s)\,\beta_X^{-1}$, and set

$$\varepsilon_{\mathscr{F}}(X) := \bar{\mathscr{F}}(\gamma)^{-1} \circ Q_{\mathbf{B}}\big(\mathscr{F}(s)\big)\colon \mathscr{F}(X) \longrightarrow \bar{\mathscr{F}}(Y) = R\mathscr{F}(Q_{\mathbf{A}}X)$$

1. $R\mathscr{F}$ is a triangulated functor. The morphism $\varepsilon_{\mathscr{F}}(X)$ does not depend on the choice of s, and these morphisms form a natural transformation $\varepsilon_{\mathscr{F}}\colon Q_{\mathbf{B}} \circ \mathrm{K}^+(\mathscr{F}) \to R\mathscr{F} \circ Q_{\mathbf{A}}$.
2. The pair $(R\mathscr{F}, \varepsilon_{\mathscr{F}})$ is initial: for every triangulated $\mathcal{G}\colon D^+(\mathbf{A}) \to D^+(\mathbf{B})$ and every natural transformation $\varepsilon\colon Q_{\mathbf{B}} \circ \mathrm{K}^+(\mathscr{F}) \to \mathcal{G} \circ Q_{\mathbf{A}}$ there is a unique natural transformation $\eta\colon R\mathscr{F} \to \mathcal{G}$ with $\varepsilon = (\eta * Q_{\mathbf{A}}) \circ \varepsilon_{\mathscr{F}}$.
3. Consequently $R\mathscr{F}$ is independent of $\mathcal{R}$ and Φ, up to a unique natural isomorphism compatible with the transformations $\varepsilon_{\mathscr{F}}$.
4. Dually, let $\mathscr{F}$ be right exact and $\mathcal{R}$ adapted to it. The total left derived functor $L\mathscr{F}$ carries a natural transformation $\varepsilon_{\mathscr{F}}\colon L\mathscr{F} \circ Q_{\mathbf{A}} \to Q_{\mathbf{B}} \circ \mathrm{K}^-(\mathscr{F})$, defined dually, and the pair is terminal: for every triangulated $\mathcal{G}\colon D^-(\mathbf{A}) \to D^-(\mathbf{B})$ and every natural transformation $\varepsilon\colon \mathcal{G} \circ Q_{\mathbf{A}} \to Q_{\mathbf{B}} \circ \mathrm{K}^-(\mathscr{F})$ there is a unique natural transformation $\eta\colon \mathcal{G} \to L\mathscr{F}$ with $\varepsilon = \varepsilon_{\mathscr{F}} \circ (\eta * Q_{\mathbf{A}})$. In particular $L\mathscr{F}$ is independent of the choices up to a unique compatible natural isomorphism.

The morphism γ exists because Z and Y are objects of $\mathrm{K}^+(\mathcal{R})$ and Ψ is fully faithful, and it is an isomorphism because $\Psi(\gamma)$ is one. The quasi-isomorphism s exists by property $(*)$ of the proof of theorem 57.3.4. When γ is the class of a quasi-isomorphism $t\colon Y \to Z$ of $\mathrm{K}^+(\mathcal{R})$, so that $X \xrightarrow{s} Z \xleftarrow{t} Y$ represents β_X, the definition reads $\varepsilon_{\mathscr{F}}(X) = Q_{\mathbf{B}}(\mathscr{F}(t))^{-1} \circ Q_{\mathbf{B}}(\mathscr{F}(s))$, with $\mathscr{F}(t)$ a quasi-isomorphism by condition (1) of definition 57.3.2. That is the formula of Gelfand-Manin [53] III.6.10, whose text writes $\mathrm{K}^+(F)(s)$ at the point where t is meant.

The general case reduces to this one. By Gelfand-Manin III.6.4 the class $S_{\mathcal{R}}$ is localizing in their sense (III.2.6), which includes the Ore condition with the quasi-isomorphism on the target, so by their Remark III.2.9, the right-roof variant of Lemma III.2.8, the isomorphism γ is $Q_{\mathcal{R}}(u)^{-1}Q_{\mathcal{R}}(t)$ for some morphisms $t\colon Y \to W$ and $u\colon Z \to W$ of $\mathrm{K}^+(\mathcal{R})$ with u in $S_{\mathcal{R}}$. Then $Q_{\mathbf{A}}(t) = \Psi(Q_{\mathcal{R}}(t)) = Q_{\mathbf{A}}(u)\,\Psi(\gamma)$ is invertible, so t is a quasi-isomorphism too (proposition 57.2.8), and

$$Q_{\mathbf{A}}(t) = Q_{\mathbf{A}}(u)\,Q_{\mathbf{A}}(s)\,\beta_X^{-1} = Q_{\mathbf{A}}(us)\,\beta_X^{-1}$$

So $X \xrightarrow{us} W \xleftarrow{t} Y$ represents β_X as in Gelfand-Manin III.6.10, with W in $\mathrm{K}^+(\mathcal{R})$. Since $\bar{\mathscr{F}} \circ Q_{\mathcal{R}} = Q_{\mathbf{B}} \circ \mathscr{F}$ on $\mathrm{K}^+(\mathcal{R})$,

$$\bar{\mathscr{F}}(\gamma)^{-1}\,Q_{\mathbf{B}}(\mathscr{F}(s)) = Q_{\mathbf{B}}(\mathscr{F}(t))^{-1}\,Q_{\mathbf{B}}(\mathscr{F}(u))\,Q_{\mathbf{B}}(\mathscr{F}(s)) = Q_{\mathbf{B}}(\mathscr{F}(t))^{-1}\,Q_{\mathbf{B}}(\mathscr{F}(us))$$

which is their $\varepsilon_F(X)$ for that diagram. So $\varepsilon_{\mathscr{F}}$ as defined here is Gelfand-Manin's, and III.6.10, which proves that theirs does not depend on the diagram and is natural in X, gives the second and third assertions of (1).

The statement is Gelfand-Manin's Definition III.6.6, with the right exact form (4) stated after it. That the construction of definition 57.3.5 satisfies it is their Theorem III.6.8, proved in III.6.8 to III.6.11: $R\mathscr{F}$ is triangulated by III.6.8(a) and Lemma III.6.9, $\varepsilon_{\mathscr{F}}$ is constructed and shown to be well defined and natural in III.6.10, and the universal property is verified in III.6.11. The proof is deferred to Gelfand-Manin: it is four pages of manipulation of roofs and introduces no idea used later. Independence of the choices is III.6.7: two constructions, each initial, have unique comparison maps between them, and these are mutually inverse.

The reconciliation with section 56.3 is a computation with the definitions.

Theorem 57.3.7: Classical Derived Functors Are the Cohomology of the Total One

Let $\mathbf{A}$ have enough injectives and let $\mathscr{F}$ be left exact. For every object A of $\mathbf{A}$, regarded as a complex concentrated in degree 0,

$$H^n\big(R\mathscr{F}(A)\big) \cong R^n\mathscr{F}(A)$$

natural in A, where $R^n\mathscr{F}$ is the nth right derived functor of section 56.3.

***Proof*:**

Step 1: the class. Take $\mathcal{R}$ to be the class of injectives, adapted to $\mathscr{F}$ by example 57.3.3(1). By theorem 57.3.6(3) this changes $R\mathscr{F}$ only by a canonical natural isomorphism, so it suffices to prove the theorem for this $\mathcal{R}$.

Step 2: the object. Let $\iota_A\colon A \to I_A$ be an injective resolution, which exists by hypothesis. It is a quasi-isomorphism from the complex A in degree 0 to $I_A \in \mathrm{K}^+(\mathcal{R})$, so $Q_{\mathbf{A}}(\iota_A)\,\beta_A^{-1}\colon \Psi\Phi(A) \to \Psi(I_A)$ is an isomorphism of $D^+(\mathbf{A})$. As Ψ is fully faithful, it is $\Psi(c_A)$ for a unique isomorphism $c_A\colon \Phi(A) \to I_A$ of $\mathrm{K}^+(\mathcal{R})[S_{\mathcal{R}}^{-1}]$. Applying $\bar{\mathscr{F}}$ gives an isomorphism $R\mathscr{F}(A) = \bar{\mathscr{F}}\Phi(A) \cong \bar{\mathscr{F}}(I_A) = \mathscr{F}(I_A)$, and so

$$H^n\big(R\mathscr{F}(A)\big) \cong H^n\big(\mathscr{F}(I_A)\big)$$

The right-hand side is canonically isomorphic to $R^n\mathscr{F}(A)$ as defined in section 56.3, the two injective resolutions of A involved being homotopy equivalent (proposition 56.2.14, injective case) and $\mathscr{F}$ carrying homotopy equivalences to homotopy equivalences (lemma 56.1.34).

Step 3: naturality. Let $\varphi\colon A \to A'$ be a morphism and $\tilde{\varphi}\colon I_A \to I_{A'}$ a lift of it, with $\tilde{\varphi}\,\iota_A$ homotopic to $\iota_{A'}\varphi$, which exists by the injective case of proposition 56.2.15. Then $Q_{\mathbf{A}}(\tilde{\varphi})\,Q_{\mathbf{A}}(\iota_A) = Q_{\mathbf{A}}(\iota_{A'})\,\varphi$ in $D^+(\mathbf{A})$, and with the naturality of β,

$$\begin{aligned}\Psi\big(c_{A'}\,\Phi(\varphi)\big) &= Q_{\mathbf{A}}(\iota_{A'})\,\beta_{A'}^{-1}\,\Psi\Phi(\varphi) = Q_{\mathbf{A}}(\iota_{A'})\,\varphi\,\beta_A^{-1}\\ &= Q_{\mathbf{A}}(\tilde{\varphi})\,Q_{\mathbf{A}}(\iota_A)\,\beta_A^{-1} = \Psi\big(Q_{\mathcal{R}}(\tilde{\varphi})\big)\,\Psi(c_A)\end{aligned}$$

the last step because Ψ agrees with $Q_{\mathbf{A}}$ on morphisms of $\mathrm{K}^+(\mathcal{R})$. As Ψ is faithful, $c_{A'}\,\Phi(\varphi) = Q_{\mathcal{R}}(\tilde{\varphi})\,c_A$. Applying $\bar{\mathscr{F}}$ and then H^n shows that the isomorphism of Step 2 carries $H^n\big(R\mathscr{F}(\varphi)\big)$ to $H^n\big(\mathscr{F}(\tilde{\varphi})\big)$, which is $R^n\mathscr{F}(\varphi)$ by the definition in section 56.3, completing the proof.

So nothing computed earlier is displaced. What is gained is that $R\mathscr{F}(A)$ exists before its cohomology

is taken, and that the gain shows up immediately when two functors are composed.

Theorem 57.3.8: Derived Functor of a Composite

Let $\mathbf{A}, \mathbf{B}, \mathcal{C}$ be abelian categories with $\mathbf{A}$ and $\mathbf{B}$ having enough injectives, and let

$$\mathcal{F}\colon \mathbf{A} \to \mathbf{B}, \qquad \mathcal{G}\colon \mathbf{B} \to \mathcal{C}$$

be left exact additive functors. There is always a natural transformation

$$\zeta\colon R(\mathcal{G}\circ\mathcal{F}) \longrightarrow R\mathcal{G}\circ R\mathcal{F}$$

and it is an isomorphism whenever $\mathcal{F}$ carries injective objects of $\mathbf{A}$ to $\mathcal{G}$-acyclic objects of $\mathbf{B}$, in the sense of definition 56.3.15.

The natural transformation comes from the universal property of theorem 57.3.6(2) applied to $R(\mathcal{G}\circ\mathcal{F})$. The isomorphism comes from the observation that for A a bounded-below complex of injectives the three complexes involved already agree. $R(\mathcal{G}\circ\mathcal{F})(A)$ and $R\mathcal{F}(A)$ are computed term by term, and so is $R\mathcal{G}(\mathcal{F}(A))$, because $\mathcal{F}(A)$ is a bounded-below complex of $\mathcal{G}$-acyclic objects and the $\mathcal{G}$-acyclic objects form a class adapted to $\mathcal{G}$ (Gelfand-Manin [53] III.6.16(b)). Every object of $D^{+}(\mathbf{A})$ is isomorphic to such a complex. The transformation ζ is Weibel [101] 10.8.2(1), and the isomorphism under this hypothesis is his Corollary 10.8.3. His letters are the opposite of the ones used here: he writes the composite as FG with G applied first, so his $R(FG) \cong RF \circ RG$ is the statement above with the names exchanged. The convention here matches theorem 60.5.1, which is what this theorem feeds.

57.3.9 Note: This Is the Grothendieck Spectral Sequence, Before Indices Theorem 60.5.1 carries the same hypothesis, that $\mathcal{F}$ send injectives to $\mathcal{G}$-acyclics, and concludes with a spectral sequence

$$E_2^{p,q} = R^p\mathcal{G}\big(R^q\mathcal{F}(A)\big) \implies R^{p+q}(\mathcal{G}\circ\mathcal{F})(A)$$

The relation between the two is that theorem 57.3.8 is the statement at the level of the derived category, and the spectral sequence is what remains of it after cohomology is taken. Filtering $R\mathcal{F}(A)$ by its canonical truncations (definition 56.1.12) and applying $R\mathcal{G}$ gives, after renumbering the pages (the canonical filtration's E_1 is the E_2 below), a spectral sequence with $E_2^{p,q} = R^p\mathcal{G}\big(R^q\mathcal{F}(A)\big)$. In the proof of theorem 60.5.1 the same page comes from the filtration by resolution degree of a Cartan-Eilenberg resolution of $\mathcal{F}(I)$, for I an injective resolution of A, which is the second spectral sequence of theorem 60.4.5 for $\mathcal{G}$. The isomorphism ζ is what says the abutment is $R^{p+q}(\mathcal{G}\circ\mathcal{F})(A)$ and not something else.

This is worth seeing in both directions. The spectral sequence is the computational form and is what chapter 60 uses. The derived-category form carries strictly more information, since a spectral sequence loses the extension data that $R\mathcal{G}\circ R\mathcal{F}$ retains as an object.

Exercise 57.3.1

1. Exhibit two different classes adapted to $-\otimes_R N$ over a commutative ring R, and check directly that the two resulting constructions of $L(-\otimes_R N)$ agree on a module with a short flat resolution. Which part of theorem 57.3.6 makes the agreement automatic?

2. Prove directly that an acyclic bounded-below complex of injectives is split exact, the fact behind example 57.3.3(1), and deduce condition (1) of definition 57.3.2 for the class of injectives. (Build the splittings by induction up the complex, using injectivity at each stage.)

3. Show that if $\mathscr{F}$ is exact then every class stable under finite direct sums and satisfying condition (2) of definition 57.3.2 is adapted to $\mathscr{F}$, and conclude that $R\mathscr{F}$ is the functor induced by $\mathscr{F}$ term by term, with $R^n\mathscr{F} = 0$ for $n \neq 0$. Show also that the stability hypothesis cannot be omitted: in **Ab**, the groups not isomorphic to $\mathbb{Z} \oplus \mathbb{Z}$ form a class satisfying condition (2) that is not stable under finite direct sums.

4. Give left exact $\mathscr{F}$ and $\mathcal{G}$ for which $\mathscr{F}$ does *not* carry injectives to $\mathcal{G}$-acyclics, and show that the conclusion of theorem 57.3.8 fails for them, so the hypothesis is not decorative. (One source of examples: take $\mathcal{G}$ to be a functor with a nonvanishing R^1 on an object in the image of an injective under $\mathscr{F}$.)

5. Definition 57.3.5 produces $R\mathscr{F}$ on $D^+(\mathbf{A})$ and not on $D(\mathbf{A})$. Identify the step in the construction that uses the bound, and explain what would go wrong for an unbounded complex.

57.4 $R\mathrm{Hom}$ and the Derived Tensor Product

The functors Ext and Tor of section 56.3 have two variables, and section 56.5.1 computed each by resolving either one of them. Section 57.3 derives a functor of a single variable. This section derives Hom and $\otimes$ in both variables, to bifunctors $R\mathrm{Hom}$ and $\otimes^L$ on the bounded derived categories with

$$H^n R\mathrm{Hom}(A,B) \cong \mathrm{Ext}^n(A,B), \qquad H^{-n}\left(A \otimes^L_R B\right) \cong \mathrm{Tor}^R_n(A,B)$$

for objects A and B. The agreement of the two computations, resolving the first variable or the second, becomes an isomorphism in the derived category, and $\mathrm{Ext}^n(A,B)$ becomes the group of morphisms $A \to B[n]$ of $D(\mathcal{A})$, a description with no resolution in it.

The treatment follows Weibel [101] 10.6 and 10.7, with the sign conventions of Gelfand-Manin [53] III.6.14. By box 57.2.5 every object of $D^+(\mathcal{A})$ is isomorphic to a bounded-below complex, and $D^+(\mathcal{A})$ is equivalent to the localization of $\mathrm{K}^+(\mathcal{A})$ at its quasi-isomorphisms. Objects of $D^+(\mathcal{A})$ are therefore taken to be bounded-below complexes, and objects of $D^-(\mathcal{A})$ bounded-above ones. Complexes with no bound are treated in chapter 59.

The morphisms of $\mathrm{K}(\mathcal{A})$ from a complex X to the shifts of a complex Y are the cohomology groups of one complex of abelian groups.

Definition 57.4.1: Hom Complex

Let $X, Y \in \mathrm{Ch}(\mathcal{A})$. The *Hom complex* $\mathrm{Hom}^\bullet(X,Y)$ is the complex of abelian groups with

$$\mathrm{Hom}^n(X,Y) := \prod_{i\in\mathbb{Z}} \mathrm{Hom}_{\mathcal{A}}\big(X^i, Y^{i+n}\big)$$

whose elements are families $\varphi = (\varphi^i)_{i\in\mathbb{Z}}$, and with differential

$$D\varphi := d_Y \circ \varphi - (-1)^n \varphi \circ d_X, \qquad \text{that is} \qquad (D\varphi)^i = d_Y^{i+n}\varphi^i - (-1)^n \varphi^{i+1} d_X^i$$

for $\varphi \in \mathrm{Hom}^n(X,Y)$.

The product is taken in **Ab**, where it exists whatever $\mathcal{A}$ is. For φ of degree n,

$$D(D\varphi) = d_Y d_Y \varphi - (-1)^n d_Y \varphi d_X + (-1)^n d_Y \varphi d_X - \varphi d_X d_X = 0$$

so $\mathrm{Hom}^\bullet(X,Y)$ is a complex. The sign matches the shift convention (57.1), under which the differential of $Y[n]$ is $(-1)^n d_Y$.

Example 57.4.2: The Hom Complex of a Resolution of $\mathbb{Z}/2$

Let P be the complex $\mathbb{Z} \xrightarrow{2} \mathbb{Z}$ in degrees -1 and 0, with basis e of P^{-1} and f of P^0, so that $de = 2f$. It is a projective resolution of $\mathbb{Z}/2$. The group $\mathrm{Hom}^n(P,P)$ vanishes unless $-1 \le n \le 1$, and

$$\mathrm{Hom}^{-1}(P,P) = \mathrm{Hom}(P^0, P^{-1}) \cong \mathbb{Z}, \qquad \mathrm{Hom}^1(P,P) = \mathrm{Hom}(P^{-1}, P^0) \cong \mathbb{Z},$$
$$\mathrm{Hom}^0(P,P) = \mathrm{Hom}(P^{-1}, P^{-1}) \oplus \mathrm{Hom}(P^0, P^0) \cong \mathbb{Z}^2$$

where $h \in \mathbb{Z}$ stands for $f \mapsto he$, the pair (a,b) for $e \mapsto ae$ and $f \mapsto bf$, and c for $e \mapsto cf$. In degree -1 the differential is $Dh = dh + hd$, which sends e to $h(2f) = 2he$ and f to $d(he) = 2hf$, so $Dh = (2h, 2h)$. In degree 0 it is $D(a,b) = d(a,b) - (a,b)d$, which sends e to $2af - 2bf$. So $\mathrm{Hom}^\bullet(P,P)$ is

$$0 \to \mathbb{Z} \xrightarrow{h\mapsto(2h,2h)} \mathbb{Z}^2 \xrightarrow{(a,b)\mapsto 2a-2b} \mathbb{Z} \to 0$$

Its cohomology is 0 in degree -1, $\{(a,a)\}/\{(2h,2h)\} \cong \mathbb{Z}/2$ in degree 0, generated by the identity $(1,1)$, and $\mathbb{Z}/2\mathbb{Z}$ in degree 1, generated by the map φ with $\varphi(e) = f$.

Lemma 57.4.3: The Hom Complex Computes the Homotopy Category

Let $X, Y \in \mathrm{Ch}(\mathcal{A})$ and $n \in \mathbb{Z}$.

1. The n-cocycles of $\mathrm{Hom}^\bullet(X,Y)$ are the chain maps $X \to Y[n]$, with the shift of (57.1), the n-coboundaries are the null-homotopic ones, and so
$$H^n\mathrm{Hom}^\bullet(X,Y) = \mathrm{Hom}_{\mathrm{K}(\mathcal{A})}\big(X, Y[n]\big)$$
2. Chain maps $f\colon X' \to X$ and $g\colon Y \to Y'$ induce chain maps $f^*\colon \varphi \mapsto \varphi f$ and $g_*\colon \varphi \mapsto g\varphi$, and homotopic chain maps induce homotopic ones. Hence $(X,Y) \mapsto \mathrm{Hom}^\bullet(X,Y)$ is a functor $\mathrm{K}(\mathcal{A})^{\mathrm{op}} \times \mathrm{K}(\mathcal{A}) \to \mathrm{K}(\mathbf{Ab})$.
3. Under the identification of (1), $H^n(f^*)$ is precomposition with f and $H^n(g_*)$ is post-composition with $g[n]$.

***Proof*:**
Step 1: cocycles and coboundaries. For $\varphi \in \mathrm{Hom}^n(X,Y)$ the equation $D\varphi = 0$ reads $(-1)^n d_Y\varphi = \varphi d_X$. Since $d_{Y[n]} = (-1)^n d_Y$ and $Y[n]^i = Y^{i+n}$ by (57.1), this says that the family $\varphi^i\colon X^i \to Y[n]^i$ is a chain map $X \to Y[n]$. Next, $\varphi = D\psi$ for $\psi \in \mathrm{Hom}^{n-1}(X,Y)$ means $\varphi = d_Y\psi + (-1)^n\psi d_X$. Putting $s := (-1)^n\psi$, so that $s^i\colon X^i \to Y[n]^{i-1}$, this is
$$\varphi = d_{Y[n]}\, s + s\, d_X$$
which by definition 56.1.27 says that φ is null-homotopic as a map $X \to Y[n]$. Conversely a null-homotopy s gives $\varphi = D\big((-1)^n s\big)$. Two chain maps are equal in $\mathrm{K}(\mathcal{A})$ exactly when their difference is null-homotopic (definition 56.1.38), which gives the displayed equality.

Step 2: functoriality. Since $f d_{X'} = d_X f$,
$$D(\varphi f) = d_Y\varphi f - (-1)^n \varphi f d_{X'} = \big(d_Y\varphi - (-1)^n\varphi d_X\big) f = (D\varphi) f$$
and similarly $D(g\varphi) = g\, D\varphi$, so f^* and g_* are chain maps. If $g - g' = d_{Y'}k + kd_Y$, then $H(\varphi) := k\varphi$ satisfies
$$D(k\varphi) + k\, D\varphi = d_{Y'}k\varphi + (-1)^n k\varphi d_X + kd_Y\varphi - (-1)^n k\varphi d_X = (g - g')\varphi$$
so $g_* - g'_* = DH + HD$. If $f - f' = d_X k + kd_{X'}$, then $H(\varphi) := (-1)^n\varphi k$ satisfies
$$D\big((-1)^n\varphi k\big) + (-1)^{n+1}(D\varphi)k = (-1)^n d_Y\varphi k + \varphi k d_{X'} + (-1)^{n+1} d_Y\varphi k + \varphi d_X k = \varphi(f - f')$$
so $f^* - f'^* = DH + HD$. As $(g\varphi)f = g(\varphi f)$, the two kinds of induced map commute, and $\mathrm{Hom}^\bullet$ is a functor on the product of homotopy categories.

Step 3: the induced maps. $H^n(f^*)$ sends the class of a chain map $\varphi\colon X \to Y[n]$ to the class of φf, and $H^n(g_*)$ sends it to the class of $g\varphi$, which as a map $X \to Y'[n]$ is $g[n] \circ \varphi$, the shift $g[n]$ having the same components as g by (57.1), completing the proof.

For the complex P of example 57.4.2 the lemma gives $\mathrm{Hom}_{\mathrm{K}(\mathbf{Ab})}(P,P) \cong \mathbb{Z}/2$, generated by id_P, and $\mathrm{Hom}_{\mathrm{K}(\mathbf{Ab})}(P,P[1]) \cong \mathbb{Z}/2$, generated by the chain map φ with $\varphi(e) = f$, which is therefore not null-homotopic.

On a bounded-below complex of injectives, and out of a bounded-above complex of projectives, the homotopy category already computes the morphisms of the derived category. This is Weibel [101] Corollary 10.4.7.

Lemma 57.4.4: Complexes of Projectives and Injectives Compute $D(\mathcal{A})$

Let $\mathcal{A}$ be an abelian category and $X \in \mathrm{Ch}(\mathcal{A})$.

1. If P is a bounded-above complex of projectives, then $Q\colon \mathrm{Hom}_{\mathrm{K}(\mathcal{A})}(P,X) \to \mathrm{Hom}_{D(\mathcal{A})}(P,X)$ is bijective.
2. If I is a bounded-below complex of injectives, then $Q\colon \mathrm{Hom}_{\mathrm{K}(\mathcal{A})}(X,I) \to \mathrm{Hom}_{D(\mathcal{A})}(X,I)$ is bijective.

***Proof*:**

Step 1: (1), surjectivity. By theorem 57.2.4 a morphism $P \to X$ of $D(\mathcal{A})$ is the class of a roof (N,s,f) with $s\colon N \to P$ a quasi-isomorphism, and that class is $Q(f)\,Q(s)^{-1}$. As P is a bounded-above complex of projectives and s is a quasi-isomorphism into it, proposition 56.2.8 gives a chain map $g\colon P \to N$ with sg homotopic to id_P. (Its proof runs through lemma 56.2.4, stated for complexes vanishing in positive degrees. A translation of degrees puts P in that form and changes neither hypothesis nor conclusion.) Applying Q gives $Q(s)Q(g) = \mathrm{id}_P$, and as $Q(s)$ is invertible, $Q(g) = Q(s)^{-1}$. The given morphism is therefore $Q(f)Q(g) = Q(fg)$.

Step 2: (1), injectivity. The functor Q is additive by theorem 57.2.7, so it suffices to show that $Q(h) = 0$ forces h to be null-homotopic, for a chain map $h\colon P \to X$. By proposition 57.2.12(2) there is a quasi-isomorphism $t\colon N \to P$ with ht null-homotopic, and proposition 56.2.8 gives $g\colon P \to N$ with tg homotopic to id_P. Composition is well defined on homotopy classes, so h is homotopic to htg, which is homotopic to 0.

Step 3: (2). Reindexing $X^n \mapsto X^{-n}$ identifies $\mathrm{Ch}(\mathcal{A}^{\mathrm{op}})$ with $\mathrm{Ch}(\mathcal{A})^{\mathrm{op}}$. It carries quasi-isomorphisms to quasi-isomorphisms and null-homotopies to null-homotopies, so it identifies $\mathrm{K}(\mathcal{A}^{\mathrm{op}})$ with $\mathrm{K}(\mathcal{A})^{\mathrm{op}}$ and, the universal property of definition 55.2.1 being self-dual, $D(\mathcal{A}^{\mathrm{op}})$ with $D(\mathcal{A})^{\mathrm{op}}$, compatibly with Q. An injective object of $\mathcal{A}$ is a projective object of $\mathcal{A}^{\mathrm{op}}$, so I becomes a bounded-above complex of projectives of $\mathcal{A}^{\mathrm{op}}$. Statement (1) for the abelian category $\mathcal{A}^{\mathrm{op}}$ is then statement (2) for $\mathcal{A}$, completing the proof.

Corollary 57.4.5: The Hom Complex Preserves Quasi-Isomorphisms

Let $s\colon X \to X'$ and $t\colon Y \to Y'$ be quasi-isomorphisms in $\mathrm{Ch}(\mathcal{A})$.

1. If I is a bounded-below complex of injectives, then $s^*\colon \mathrm{Hom}^\bullet(X', I) \to \mathrm{Hom}^\bullet(X, I)$ is a quasi-isomorphism.
2. If P is a bounded-above complex of projectives, then $t_*\colon \mathrm{Hom}^\bullet(P, Y) \to \mathrm{Hom}^\bullet(P, Y')$ is a quasi-isomorphism.

***Proof*:**
(1) Fix n. The shift $I[n]$ is again a bounded-below complex of injectives. By lemma 57.4.3(1) and (3), $H^n(s^*)$ is the map $\mathrm{Hom}_{\mathrm{K}(\mathcal{A})}(X', I[n]) \to \mathrm{Hom}_{\mathrm{K}(\mathcal{A})}(X, I[n])$, $\psi \mapsto \psi s$. The bijections Q of lemma 57.4.4(2) carry it to $\psi \mapsto \psi \circ Q(s)$ from $\mathrm{Hom}_{D(\mathcal{A})}(X', I[n])$ to $\mathrm{Hom}_{D(\mathcal{A})}(X, I[n])$, because Q is a functor, and that map is bijective with inverse $\psi \mapsto \psi \circ Q(s)^{-1}$.

(2) The same argument applies with lemma 57.4.4(1): $H^n(t_*)$ becomes postcomposition with $Q(t[n])$ on $\mathrm{Hom}_{D(\mathcal{A})}(P, Y[n])$, which is bijective because $t[n]$ is a quasi-isomorphism, $H^i(t[n])$ being $H^{i+n}(t)$, completing the proof.

When $\mathcal{A}$ has enough injectives, corollary 57.4.5(1) shows that resolving the second variable by injectives gives a functor of the first variable that inverts quasi-isomorphisms.

Definition 57.4.6: *R*Hom

Let $\mathcal{A}$ have enough injectives. For every bounded-below complex B fix an *injective resolution* $\iota_B\colon B \to I_B$, that is, a quasi-isomorphism into a bounded-below complex of injectives. For $A \in \mathrm{Ch}(\mathcal{A})$ set

$$R\mathrm{Hom}(A, B) := \mathrm{Hom}^\bullet(A, I_B)$$

regarded as an object of $D(\mathbf{Ab})$.

Injective resolutions exist: theorem 56.2.17, applied to $\mathcal{A}^{\mathrm{op}}$, which has enough projectives because $\mathcal{A}$ has enough injectives, gives one for every bounded-below complex. When A is an object of $\mathcal{A}$ placed in degree 0, the group $\mathrm{Hom}^n(A, I_B)$ has the single factor $\mathrm{Hom}_{\mathcal{A}}(A, I_B^n)$ and $D\varphi = d_{I_B}\varphi$. So $R\mathrm{Hom}(A, B)$ is the complex $\mathrm{Hom}_{\mathcal{A}}(A, I_B)$, the left exact functor $\mathrm{Hom}_{\mathcal{A}}(A, -)$ applied term by term to I_B, which is the value at B of the total derived functor of definition 57.3.5 for the functor $\mathrm{Hom}_{\mathcal{A}}(A, -)$ and the class of injectives, adapted to it by example 57.3.3(1).

Example 57.4.7: $R\mathrm{Hom}(\mathbb{Z}/n, \mathbb{Z})$

In $\mathbf{Ab}$ take $B = \mathbb{Z}$ and the injective resolution $\mathbb{Z} \to I_{\mathbb{Z}}$, where $I_{\mathbb{Z}}$ is $\mathbb{Q} \to \mathbb{Q}/\mathbb{Z}$ in degrees 0 and 1. The groups $\mathbb{Q}$ and $\mathbb{Q}/\mathbb{Z}$ are divisible, hence injective, as recorded in example 56.4.10, and $0 \to \mathbb{Z} \to \mathbb{Q} \to \mathbb{Q}/\mathbb{Z} \to 0$ is exact, so the inclusion is a quasi-isomorphism. For $n \geq 1$,

$$\mathrm{Hom}(\mathbb{Z}/n, \mathbb{Q}) = 0, \qquad \mathrm{Hom}(\mathbb{Z}/n, \mathbb{Q}/\mathbb{Z}) = \{x \in \mathbb{Q}/\mathbb{Z} : nx = 0\} \cong \mathbb{Z}/n$$

the first because $\mathbb{Q}$ has no nonzero element of finite order, the second generated by the class of $1/n$. So $R\mathrm{Hom}(\mathbb{Z}/n, \mathbb{Z})$ is the complex $0 \to \mathbb{Z}/n$ with $\mathbb{Z}/n$ in degree 1, which is $(\mathbb{Z}/n)[-1]$. Its cohomology is $\mathrm{Hom}(\mathbb{Z}/n, \mathbb{Z}) = 0$ in degree 0 and $\mathbb{Z}/n$ in degree 1, the values of $\mathrm{Ext}^0_{\mathbb{Z}}(\mathbb{Z}/n, \mathbb{Z})$ and

$\operatorname{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/n, \mathbb{Z})$ found in example 56.4.10.

Up to a canonical isomorphism $R\operatorname{Hom}(A, B)$ does not depend on the chosen resolutions, and it is a functor of both variables at once. The statement is Weibel [101] Lemma 10.7.3 and Theorem 10.7.4.

Theorem 57.4.8: RHom **Is a Bifunctor**

Let $\mathcal{A}$ have enough injectives.

1. For every morphism $\beta\colon B \to B'$ of $D^+(\mathcal{A})$ there is a unique morphism $\tilde{\beta}\colon I_B \to I_{B'}$ of $\mathrm{K}(\mathcal{A})$ with $Q(\tilde{\beta})\, Q(\iota_B) = Q(\iota_{B'})\, \beta$, and $\beta \mapsto \tilde{\beta}$ is a functor $D^+(\mathcal{A}) \to \mathrm{K}(\mathcal{A})$.
2. RHom is a bifunctor
$$R\operatorname{Hom}\colon D(\mathcal{A})^{\mathrm{op}} \times D^+(\mathcal{A}) \longrightarrow D(\mathbf{Ab})$$
whose value on $Q(f)$, for a chain map $f\colon A' \to A$, and on β is $Q\big(\operatorname{Hom}^\bullet(f, \tilde{\beta})\big)$.
3. Replacing the injective resolutions by another choice $\iota'_B\colon B \to I'_B$ changes RHom by the natural isomorphism $\operatorname{Hom}^\bullet(A, c_B)$, where $c_B\colon I_B \to I'_B$ is the unique morphism of $\mathrm{K}(\mathcal{A})$ with $Q(c_B)\, Q(\iota_B) = Q(\iota'_B)$.
4. If A is bounded above, then $R\operatorname{Hom}(A, B)$ is bounded below. Hence RHom restricts to a bifunctor $D^-(\mathcal{A})^{\mathrm{op}} \times D^+(\mathcal{A}) \to D^+(\mathbf{Ab})$.

***Proof*:**
Step 1: the second variable. By lemma 57.4.4(2), with $X = I_B$ and the bounded-below complex of injectives $I_{B'}$, the map $Q\colon \operatorname{Hom}_{\mathrm{K}(\mathcal{A})}(I_B, I_{B'}) \to \operatorname{Hom}_{D(\mathcal{A})}(I_B, I_{B'})$ is bijective. As $Q(\iota_B)$ is invertible, $Q(\iota_{B'})\, \beta\, Q(\iota_B)^{-1}$ lies in the target, so it is $Q(\tilde{\beta})$ for exactly one $\tilde{\beta}$, and that is the stated condition. For $\beta'\colon B' \to B''$,

$$Q(\tilde{\beta}'\tilde{\beta})\, Q(\iota_B) = Q(\tilde{\beta}')\, Q(\iota_{B'})\, \beta = Q(\iota_{B''})\, \beta'\beta$$

so $\tilde{\beta}'\tilde{\beta}$ satisfies the condition defining $\widetilde{\beta'\beta}$ and the two are equal. Likewise $\widetilde{\mathrm{id}_B} = \mathrm{id}_{I_B}$. This is (1).

Step 2: the first variable. Fix B. By lemma 57.4.3(2), $A \mapsto \operatorname{Hom}^\bullet(A, I_B)$ is a functor $\mathrm{K}(\mathcal{A})^{\mathrm{op}} \to \mathrm{K}(\mathbf{Ab})$, and by corollary 57.4.5(1) it carries quasi-isomorphisms to quasi-isomorphisms. Followed by $Q\colon \mathrm{K}(\mathbf{Ab}) \to D(\mathbf{Ab})$ it carries the quasi-isomorphisms of $\mathrm{K}(\mathcal{A})$ to isomorphisms. By theorem 57.2.4, $D(\mathcal{A})$ is the localization of $\mathrm{K}(\mathcal{A})$ at its quasi-isomorphisms, so $D(\mathcal{A})^{\mathrm{op}}$ is that of $\mathrm{K}(\mathcal{A})^{\mathrm{op}}$, and the universal property of definition 55.2.1 factors the functor uniquely through $D(\mathcal{A})^{\mathrm{op}}$. The factorization is $R\operatorname{Hom}(-, B)$. Its value on $Q(f)$ is $Q(f^*)$, and its value on $Q(s)^{-1}$, for a quasi-isomorphism s, is $Q(s^*)^{-1}$.

Step 3: both variables. Put $R\operatorname{Hom}(A, \beta) := Q\big(\operatorname{Hom}^\bullet(A, \tilde{\beta})\big)$, a functor of β by Step 1 and

lemma 57.4.3(2). For $\alpha\colon A' \to A$ in $D(\mathcal{A})$ and $\beta\colon B \to B'$ consider the square

$$\begin{array}{ccc} R\mathrm{Hom}(A,B) & \xrightarrow{R\mathrm{Hom}(A,\beta)} & R\mathrm{Hom}(A,B') \\ {\scriptstyle R\mathrm{Hom}(\alpha,B)}\downarrow & & \downarrow{\scriptstyle R\mathrm{Hom}(\alpha,B')} \\ R\mathrm{Hom}(A',B) & \xrightarrow[R\mathrm{Hom}(A',\beta)]{} & R\mathrm{Hom}(A',B') \end{array}$$

If $\alpha = Q(f)$ for a chain map f, both composites are $Q\big(\mathrm{Hom}^\bullet(f,\tilde{\beta})\big)$, because f^* and $\tilde{\beta}_*$ commute (lemma 57.4.3(2)). If $\alpha = Q(s)^{-1}$ for a quasi-isomorphism $s\colon A \to A'$, the square is the square for $Q(s)$ with its two vertical isomorphisms inverted, so it commutes. Squares of this shape paste along composites in α, and every morphism of $D(\mathcal{A})$ is $Q(f)Q(s)^{-1}$ by theorem 57.2.4, so the square commutes for every α. Setting $R\mathrm{Hom}(\alpha,\beta) := R\mathrm{Hom}(\alpha,B') \circ R\mathrm{Hom}(A,\beta)$, the commutativity of these squares is exactly what makes $R\mathrm{Hom}$ preserve composites in the pair (α,β). This is (2).

Step 4: independence of the resolutions. As in Step 1, lemma 57.4.4(2) gives unique $c_B\colon I_B \to I'_B$ and $c'_B\colon I'_B \to I_B$ in $\mathrm{K}(\mathcal{A})$ with $Q(c_B)Q(\iota_B) = Q(\iota'_B)$ and $Q(c'_B)Q(\iota'_B) = Q(\iota_B)$. Both c'_Bc_B and id_{I_B} satisfy the condition defining $\widetilde{\mathrm{id}_B}$, so $c'_Bc_B = \mathrm{id}_{I_B}$, and symmetrically $c_Bc'_B = \mathrm{id}_{I'_B}$. So c_B is an isomorphism of $\mathrm{K}(\mathcal{A})$ and $\mathrm{Hom}^\bullet(A,c_B)$ one of $\mathrm{K}(\mathbf{Ab})$. Writing $\tilde{\beta}'$ for the morphism of Step 1 built from the primed resolutions, $c_{B'}\tilde{\beta}$ and $\tilde{\beta}'c_B$ both satisfy $Q(-)\,Q(\iota_B) = Q(\iota'_{B'})\,\beta$, so they are equal by the same uniqueness. With lemma 57.4.3(2), and Step 3 for the passage from chain maps to all morphisms of $D(\mathcal{A})$, the isomorphisms $\mathrm{Hom}^\bullet(A,c_B)$ are natural in both variables. This is (3).

Step 5: bounds. Suppose $A^i = 0$ for $i > a$ and $I_B^j = 0$ for $j < b$. A factor $\mathrm{Hom}(A^i, I_B^{i+n})$ of $\mathrm{Hom}^n(A,I_B)$ is nonzero only if $i \le a$ and $i+n \ge b$, which forces $n \ge b-a$. So $\mathrm{Hom}^n(A,I_B) = 0$ for $n < b-a$, completing the proof.

Dually, when $\mathcal{A}$ has enough projectives, let $\pi_A\colon P_A \to A$ be a *projective resolution* of a bounded-above complex A, that is, a quasi-isomorphism from a bounded-above complex of projectives. Then $\mathrm{Hom}^\bullet(P_A,B)$ defines a bifunctor $D^-(\mathcal{A})^{\mathrm{op}} \times D(\mathcal{A}) \to D(\mathbf{Ab})$ (Weibel [101] Theorem 10.7.4). When both kinds of resolution exist, the two constructions agree, which is Weibel's Exercise 10.7.1.

Proposition 57.4.9: $R\mathrm{Hom}$ May Be Computed by Resolving Either Variable

Let $\mathcal{A}$ have enough injectives and enough projectives, let A be a bounded-above complex with a projective resolution $\pi_A\colon P_A \to A$, and let B be a bounded-below complex. Then both chain maps in

$$R\mathrm{Hom}(A,B) = \mathrm{Hom}^\bullet(A,I_B) \xrightarrow{\pi_A^*} \mathrm{Hom}^\bullet(P_A,I_B) \xleftarrow{(\iota_B)_*} \mathrm{Hom}^\bullet(P_A,B)$$

are quasi-isomorphisms. In particular $R\mathrm{Hom}(A,B) \cong \mathrm{Hom}^\bullet(P_A,B)$ in $D(\mathbf{Ab})$.

***Proof*:**
The map π_A^* is a quasi-isomorphism by corollary 57.4.5(1), with $I = I_B$ and $s = \pi_A$. The map $(\iota_B)_*$ is one by corollary 57.4.5(2), with $P = P_A$ and $t = \iota_B$. Projective resolutions exist by theorem 56.2.17, completing the proof.

In example 57.4.7, the projective resolution $\mathbb{Z} \xrightarrow{n} \mathbb{Z}$ of $\mathbb{Z}/n$ in degrees -1 and 0 gives $\mathrm{Hom}^\bullet(P, \mathbb{Z}) = \big(\mathbb{Z} \xrightarrow{-n} \mathbb{Z}\big)$ in degrees 0 and 1, the sign being the $-(-1)^0\varphi d_P$ of definition 57.4.1. Its cohomology is again $\mathbb{Z}/n$ in degree 1 and 0 elsewhere.

Theorem 57.4.10: Ext as Morphisms in the Derived Category

Let $\mathcal{A}$ have enough injectives.

1. For every complex A, every bounded-below complex B and every $n \in \mathbb{Z}$ there is an isomorphism
$$\mathrm{Hom}_{D(\mathcal{A})}\big(A, B[n]\big) \cong H^n R\mathrm{Hom}(A, B)$$
natural in A and B.

2. For objects A and B of $\mathcal{A}$, regarded as complexes in degree 0, and every $n \in \mathbb{Z}$, there are isomorphisms natural in A and B
$$\mathrm{Ext}^n_{\mathcal{A}}(A, B) \cong \mathrm{Hom}_{D(\mathcal{A})}\big(A, B[n]\big) \cong H^n R\mathrm{Hom}(A, B)$$
where $\mathrm{Ext}^n_{\mathcal{A}}(A, -) = R^n\mathrm{Hom}_{\mathcal{A}}(A, -)$ is the right derived functor of section 56.3, as in example 56.3.6(2). In particular $\mathrm{Hom}_{D(\mathcal{A})}(A, B[n]) = 0$ for $n < 0$, and $Q\colon \mathrm{Hom}_{\mathcal{A}}(A, B) \to \mathrm{Hom}_{D(\mathcal{A})}(A, B)$ is bijective.

***Proof*:**
Step 1: (1). The shift of $Q(\iota_B)$ is an isomorphism $B[n] \to I_B[n]$ of $D(\mathcal{A})$, and composing with it gives $\mathrm{Hom}_{D(\mathcal{A})}(A, B[n]) \cong \mathrm{Hom}_{D(\mathcal{A})}(A, I_B[n])$. Since $I_B[n]$ is a bounded-below complex of injectives, lemma 57.4.4(2) identifies this with $\mathrm{Hom}_{\mathrm{K}(\mathcal{A})}(A, I_B[n])$, and lemma 57.4.3(1) identifies that with $H^n\mathrm{Hom}^\bullet(A, I_B) = H^n R\mathrm{Hom}(A, B)$. Each identification is natural in chain maps of A, by lemma 57.4.3(3) and because Q is a functor, hence in all morphisms of $D(\mathcal{A})$, each being $Q(f)Q(s)^{-1}$. Each is natural in B because $Q(\tilde{\beta}[n])\,Q(\iota_B[n]) = Q(\iota_{B'}[n])\,\beta[n]$ by theorem 57.4.8(1).

Step 2: (2). By theorem 57.4.8(3) the choice of ι_B does not matter, so take ι_B to be an injective resolution of B in the sense of definition 56.2.11, with $I_B^n = 0$ for $n < 0$. As observed after definition 57.4.6, $R\mathrm{Hom}(A, B)$ is then the complex $\mathrm{Hom}_{\mathcal{A}}(A, I_B)$, whose nth cohomology is $R^n\mathrm{Hom}_{\mathcal{A}}(A, -)(B) = \mathrm{Ext}^n_{\mathcal{A}}(A, B)$ by the definition of right derived functors in section 56.3. Together with (1) this gives the displayed isomorphisms, natural in A because a morphism $A' \to A$ acts on both sides by precomposition. For naturality in B, let $b\colon B \to B'$ be a morphism of $\mathcal{A}$. The map $\mathrm{Ext}^n_{\mathcal{A}}(A, b)$ of section 56.3 is induced by a comparison lift $\hat{b}\colon I_B \to I_{B'}$ with $\hat{b}\,\iota_B$ homotopic to $\iota_{B'}b$ (the injective case of proposition 56.2.15). Then $Q(\hat{b})\,Q(\iota_B) = Q(\iota_{B'})\,Q(b)$, so $\hat{b} = \tilde{b}$ in $\mathrm{K}(\mathcal{A})$ by the uniqueness in theorem 57.4.8(1), with $\tilde{b}$ the morphism there for $Q(b)$. Hence $\mathrm{Ext}^n_{\mathcal{A}}(A, b) = H^n\mathrm{Hom}_{\mathcal{A}}(A, \hat{b})$ is $H^n R\mathrm{Hom}(A, Q(b))$, and with (1) the displayed isomorphisms

are natural in B. For $n < 0$ the group $\mathrm{Hom}_{\mathcal{A}}(A, I_B^n)$ is zero.

Step 3: $n = 0$. The sequence $0 \to B \xrightarrow{\iota_B} I_B^0 \to I_B^1$ is exact, and $\mathrm{Hom}_{\mathcal{A}}(A, -)$ is left exact, so $H^0\mathrm{Hom}_{\mathcal{A}}(A, I_B) = \ker\big(\mathrm{Hom}(A, I_B^0) \to \mathrm{Hom}(A, I_B^1)\big)$ consists of the maps $\iota_B\varphi$ for $\varphi \in \mathrm{Hom}_{\mathcal{A}}(A, B)$. Follow φ through Step 1: $Q(\varphi)$ goes to $Q(\iota_B)Q(\varphi) = Q(\iota_B\varphi)$, then to the homotopy class of the chain map $\iota_B\varphi\colon A \to I_B$, then to the cocycle $\iota_B\varphi \in \mathrm{Hom}(A, I_B^0)$. So the composite of Q with the bijection $\mathrm{Hom}_{D(\mathcal{A})}(A, B) \to H^0\mathrm{Hom}_{\mathcal{A}}(A, I_B) \cong \mathrm{Hom}_{\mathcal{A}}(A, B)$ is the identity of $\mathrm{Hom}_{\mathcal{A}}(A, B)$, and Q is bijective, completing the proof.

Part (2) is Weibel [101] Theorem 10.7.4 and Corollary 10.7.5, and Gelfand-Manin [53] III.6.14. Gelfand-Manin take $\mathrm{Hom}_{D(\mathcal{A})}(A, B[n])$ as the definition of $\mathrm{Ext}^n_{\mathcal{A}}(A, B)$ (III.5.3), which needs no injectives and no projectives, and prove that Q is fully faithful on objects of $\mathcal{A}$ with no hypothesis on $\mathcal{A}$ (III.5.2). When $\mathcal{A}$ also has enough projectives, proposition 57.4.9 computes the same groups from a projective resolution of A.

Example 57.4.11: The Extension $\mathbb{Z}/4$ as a Morphism of $D(\mathbf{Ab})$

Let $u\colon \mathbb{Z}/2 \to \mathbb{Z}/4$ be multiplication by 2 and $v\colon \mathbb{Z}/4 \to \mathbb{Z}/2$ reduction modulo 2. Theorem 57.2.10 completes $0 \to \mathbb{Z}/2 \xrightarrow{u} \mathbb{Z}/4 \xrightarrow{v} \mathbb{Z}/2 \to 0$ to a distinguished triangle (u, v, w) of $D(\mathbf{Ab})$ with $w\colon \mathbb{Z}/2 \to \mathbb{Z}/2[1]$, and example 57.2.11 shows that no morphism of $\mathrm{K}(\mathbf{Ab})$ completes it to a distinguished triangle there.

By theorem 57.4.10(2) and example 56.4.10, $\mathrm{Hom}_{D(\mathbf{Ab})}(\mathbb{Z}/2, \mathbb{Z}/2[1]) \cong \mathrm{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/2, \mathbb{Z}/2) \cong \mathbb{Z}/2$, and w is its nonzero element. To see that $w \neq 0$, rotate the triangle to $(v, w, -u[1])$ and apply $\mathrm{Hom}_{D(\mathbf{Ab})}(\mathbb{Z}/2, -)$, which is cohomological by proposition 57.1.8, $D(\mathbf{Ab})$ being triangulated by theorem 57.2.7. Exactness of

$$\mathrm{Hom}_{D(\mathbf{Ab})}(\mathbb{Z}/2, \mathbb{Z}/4) \xrightarrow{v_*} \mathrm{Hom}_{D(\mathbf{Ab})}(\mathbb{Z}/2, \mathbb{Z}/2) \xrightarrow{w_*} \mathrm{Hom}_{D(\mathbf{Ab})}(\mathbb{Z}/2, \mathbb{Z}/2[1])$$

shows that $w = 0$ would make v_* surjective. By the last clause of theorem 57.4.10(2) the first two groups are $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}/2, \mathbb{Z}/4)$ and $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}/2, \mathbb{Z}/2)$, with v_* composition with v. The two homomorphisms $\mathbb{Z}/2 \to \mathbb{Z}/4$ send 1 to 0 and to 2, and $v(2) = 0$, so v_* is zero and misses $\mathrm{id}_{\mathbb{Z}/2}$. Hence $w \neq 0$.

So the short exact sequence determines, through its triangle, the nonzero element of $\mathrm{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/2, \mathbb{Z}/2)$. Through the resolution P of example 57.4.2, $\mathrm{Hom}_{D(\mathbf{Ab})}(\mathbb{Z}/2, \mathbb{Z}/2[1]) \cong \mathrm{Hom}_{D(\mathbf{Ab})}(P, P[1]) \cong \mathrm{Hom}_{\mathrm{K}(\mathbf{Ab})}(P, P[1])$ by lemma 57.4.4(1), and w corresponds to the chain map φ with $\varphi(e) = f$. No chain map $\mathbb{Z}/2 \to \mathbb{Z}/2[1]$ represents w, the two complexes being concentrated in the different degrees 0 and -1, so that $\mathrm{Hom}_{\mathrm{K}(\mathbf{Ab})}(\mathbb{Z}/2, \mathbb{Z}/2[1]) = 0$.

The tensor product is derived in the same way, by resolving with projective or flat modules. For a ring R, write Mod-R and R-Mod for the categories of right and left R-modules. Both have enough projectives, free modules being projective (example 56.2.2(4)).

Definition 57.4.12: Total Tensor Complex

Let X be a complex of right R-modules and Y a complex of left R-modules. The *total tensor complex* $\mathrm{Tot}(X \otimes_R Y)$ is the complex of abelian groups with

$$\mathrm{Tot}(X \otimes_R Y)^n := \bigoplus_{i+j=n} X^i \otimes_R Y^j, \qquad d(x \otimes y) := d_X x \otimes y + (-1)^i x \otimes d_Y y$$

for $x \in X^i$ and $y \in Y^j$, the sum being a direct sum in $\mathbf{Ab}$. For chain maps $f\colon X \to X'$ and $g\colon Y \to Y'$, the chain map $\mathrm{Tot}(f \otimes g)$ is $x \otimes y \mapsto f(x) \otimes g(y)$.

The differential is defined on the whole direct sum, since it carries the summand $X^i \otimes_R Y^j$ into the two summands $X^{i+1} \otimes_R Y^j$ and $X^i \otimes_R Y^{j+1}$. This is the direct-sum total complex $\mathrm{Tot}^{\oplus}$ of proposition 56.5.2. When X and Y are bounded above each sum is finite: if $X^i = 0$ for $i > a$ and $Y^j = 0$ for $j > b$, then $i + j = n$ forces $n - b \le i \le a$, and $\mathrm{Tot}(X \otimes_R Y)^n = 0$ for $n > a + b$. The sign is the twist $(-1)^p$ of section 56.5, which makes the squares of the grid $X^i \otimes_R Y^j$ anticommute, and

$$d\big(d(x \otimes y)\big) = d_X d_X x \otimes y + (-1)^{i+1} d_X x \otimes d_Y y + (-1)^i d_X x \otimes d_Y y + x \otimes d_Y d_Y y = 0$$

The map $\mathrm{Tot}(f \otimes g)$ commutes with d because f and g commute with the differentials and preserve degrees.

Example 57.4.13: Two Total Tensor Complexes for $\mathbb{Z}/2$

Let $R = \mathbb{Z}$ and let P be the resolution $\mathbb{Z} \xrightarrow{2} \mathbb{Z}$ of example 57.4.2, with $de = 2f$. For $Y = \mathbb{Z}/2$ in degree 0, $\mathrm{Tot}(P \otimes \mathbb{Z}/2)$ is $\mathbb{Z}/2 \xrightarrow{0} \mathbb{Z}/2$ in degrees -1 and 0, with cohomology $\mathbb{Z}/2$ in both degrees. For $Y = P$, the complex $\mathrm{Tot}(P \otimes P)$ has bases $\{e \otimes e\}$, $\{e \otimes f,\ f \otimes e\}$ and $\{f \otimes f\}$ in degrees -2, -1 and 0, and

$$d(e \otimes e) = 2f \otimes e - 2e \otimes f, \qquad d(e \otimes f) = d(f \otimes e) = 2f \otimes f$$

the minus sign being $(-1)^{-1}$. The kernel of d in degree -1 is spanned by $e \otimes f - f \otimes e$, and the image of d in that degree is spanned by twice it, so the cohomology is 0 in degree -2, $\mathbb{Z}/2$ in degree -1 and $\mathbb{Z}/2$ in degree 0, the same as for $\mathrm{Tot}(P \otimes \mathbb{Z}/2)$. Without the sign, $d(e \otimes e)$ would be $2f \otimes e + 2e \otimes f$, and $d \circ d$ would send $e \otimes e$ to $8f \otimes f \neq 0$.

Lemma 57.4.14: Tensoring with a Bounded-Above Flat Complex Preserves Quasi-Isomorphisms

Let R be a ring. All complexes below are bounded above, of right R-modules on the left of $\otimes_R$ and of left R-modules on the right.

1. If f and f' are homotopic, so are $\mathrm{Tot}(f \otimes g)$ and $\mathrm{Tot}(f' \otimes g)$, and likewise in the second variable. Hence $\mathrm{Tot}(- \otimes_R -)$ is a functor on the product of the homotopy categories, with values in $\mathrm{K}^-(\mathbf{Ab})$.
2. If X is exact and every Y^j is flat, or Y is exact and every X^i is flat, then $\mathrm{Tot}(X \otimes_R Y)$ is exact.
3. If every Y^j is flat and $s\colon X \to X'$ is a quasi-isomorphism, then $\mathrm{Tot}(s \otimes Y)$ is a quasi-isomorphism. If every X^i is flat and $t\colon Y \to Y'$ is a quasi-isomorphism, then $\mathrm{Tot}(X \otimes t)$ is a quasi-isomorphism.

***Proof*:**
Step 1: homotopies. Here $\mathrm{Tot}(f \otimes g)$ is bilinear in (f, g). If $f - f' = dh + hd$, then $H(x \otimes y) := h(x) \otimes g(y)$ satisfies, for $x \in X^i$,

$$(dH + Hd)(x \otimes y) = dhx \otimes gy + (-1)^{i-1} hx \otimes dgy + hdx \otimes gy + (-1)^i hx \otimes gdy = (dh + hd)x \otimes gy$$

using $gd = dg$, so $\mathrm{Tot}\big((f - f') \otimes g\big) = dH + Hd$. If $g - g' = dk + kd$, then $H(x \otimes y) := (-1)^i f(x) \otimes k(y)$ satisfies

$$(dH + Hd)(x \otimes y) = (-1)^i dfx \otimes ky + fx \otimes dky + (-1)^{i+1} fdx \otimes ky + fx \otimes kdy = fx \otimes (dk + kd)y$$

using $fd = df$. This is (1), the degree bound having been checked after definition 57.4.12.

Step 2: exactness. The groups $X^i \otimes_R Y^j$ with the maps $d_X \otimes 1$ and $(-1)^i(1 \otimes d_Y)$ form a double complex with anticommuting squares whose total complex is $\mathrm{Tot}(X \otimes_R Y)$. Suppose X exact and every Y^j flat. For fixed j, the row $X \otimes_R Y^j$ with differential $d_X \otimes 1$ is the image of X under $- \otimes_R Y^j$, which is exact by definition 17.5.4. An exact functor preserves kernels and images, so it carries the exact complex X to an exact complex, and every row is exact. In the other case $X^i \otimes_R -$ is exact for every i, and every column $X^i \otimes_R Y$, with differential $(-1)^i(1 \otimes d_Y)$, is exact. If $X^i = 0$ for $i > a$ and $Y^j = 0$ for $j > b$, re-indexing by $p = i - a$ and $q = j - b$ places the double complex in the bidegrees $p, q \leq 0$ without changing any object or map. The sign $(-1)^i$ differs from the twist $(-1)^p = (-1)^{i-a}$ of section 56.5 by the constant $(-1)^a$, and $x \otimes y \mapsto (-1)^{aj} x \otimes y$, for $y \in Y^j$, is an isomorphism between the two total complexes. So proposition 56.5.4 makes the total complex exact.

Step 3: the first variable of (3). Let every Y^j be flat and $s\colon X \to X'$ a quasi-isomorphism. As graded groups,

$$\begin{aligned} MC\big(\mathrm{Tot}(s \otimes Y)\big)^n &= \mathrm{Tot}(X \otimes_R Y)^{n+1} \oplus \mathrm{Tot}(X' \otimes_R Y)^n \\ &= \bigoplus_{i+j=n} \big(X^{i+1} \oplus X'^i\big) \otimes_R Y^j = \mathrm{Tot}\big(MC(s) \otimes_R Y\big)^n \end{aligned}$$

and the differentials agree. For $x \in X^{i+1}$, $x' \in X'^{i}$ and $y \in Y^{j}$, the differential of $\mathrm{Tot}(MC(s) \otimes_R Y)$ sends $(x, x') \otimes y$ to

$$\big(-dx,\ sx + dx'\big) \otimes y + (-1)^i (x, x') \otimes dy$$

since (x, x') has degree i in $MC(s)$. By definition 56.1.23, the differential of the cone sends $(x \otimes y,\ x' \otimes y)$ to

$$\big(-d(x \otimes y),\ sx \otimes y + d(x' \otimes y)\big) = \big(-dx \otimes y + (-1)^i x \otimes dy,\ sx \otimes y + dx' \otimes y + (-1)^i x' \otimes dy\big)$$

the sign $(-1)^{i+1}$ of $x \in X^{i+1}$ in $d(x \otimes y)$ being negated. These are the same element. The cone $MC(s)$ is exact by proposition 56.1.26 and bounded above, so Step 2 makes $\mathrm{Tot}(MC(s) \otimes_R Y) = MC(\mathrm{Tot}(s \otimes Y))$ exact, and proposition 56.1.26 makes $\mathrm{Tot}(s \otimes Y)$ a quasi-isomorphism.

Step 4: the second variable of (3). Here the identification needs a sign. Define $\theta \colon \mathrm{Tot}\big(X \otimes_R MC(t)\big) \to MC\big(\mathrm{Tot}(X \otimes t)\big)$ by $\theta\big(x \otimes (y, y')\big) := \big((-1)^i x \otimes y,\ x \otimes y'\big)$ for $x \in X^i$, $y \in Y^{j+1}$ and $y' \in Y'^{j}$, a bijection in each degree. Applying θ to $d\big(x \otimes (y, y')\big) = dx \otimes (y, y') + (-1)^i x \otimes (-dy,\ ty + dy')$ gives

$$\big((-1)^{i+1} dx \otimes y - x \otimes dy,\ dx \otimes y' + (-1)^i x \otimes ty + (-1)^i x \otimes dy'\big)$$

and the cone differential applied to $\theta\big(x \otimes (y, y')\big)$ gives $\big(-(-1)^i d(x \otimes y),\ (-1)^i x \otimes ty + d(x \otimes y')\big)$, the same element. So θ is an isomorphism of complexes. With every X^i flat and $MC(t)$ exact, Step 2 and proposition 56.1.26 finish as in Step 3, completing the proof.

Definition 57.4.15: Derived Tensor Product

Let R be a ring. For every bounded-above complex B of left R-modules fix a projective resolution $\pi_B \colon P_B \to B$. For a bounded-above complex A of right R-modules, the *derived tensor product* of A and B is

$$A \otimes^L_R B := \mathrm{Tot}(A \otimes_R P_B)$$

regarded as an object of $D^-(\mathbf{Ab})$.

Projective resolutions exist by theorem 56.2.17. For a fixed right module M, $B \mapsto M \otimes^L_R B$ is the complex $M \otimes_R P_B$, the right exact functor $M \otimes_R -$ applied term by term, which is the total left derived functor $L(M \otimes_R -)$ of definition 57.3.5 with the projectives, adapted by example 57.3.3(2).

Example 57.4.16: $\mathbb{Z}/m \otimes^L \mathbb{Z}/n$

Let $R = \mathbb{Z}$, let $m, n \geq 1$ and let $d = \gcd(m, n)$. The complex $\mathbb{Z} \xrightarrow{n} \mathbb{Z}$ in degrees -1 and 0 is a projective resolution of $\mathbb{Z}/n$, so $\mathbb{Z}/m \otimes^L_{\mathbb{Z}} \mathbb{Z}/n$ is

$$\mathbb{Z}/m \xrightarrow{n} \mathbb{Z}/m$$

in degrees -1 and 0. Its cohomology is $\{x \in \mathbb{Z}/m : nx = 0\} \cong \mathbb{Z}/d$ in degree -1, $\mathbb{Z}/(m\mathbb{Z} + n\mathbb{Z}) = \mathbb{Z}/d$ in degree 0, and 0 elsewhere. For $m = n = 2$ it is the complex $\mathrm{Tot}(P \otimes \mathbb{Z}/2)$ of example 57.4.13 with the two factors exchanged.

Theorem 57.4.17: The Derived Tensor Product Is a Balanced Bifunctor

Let R be a ring.

1. $\otimes_R^L$ is a bifunctor $D^-(\text{Mod-}R) \times D^-(R\text{-Mod}) \to D^-(\mathbf{Ab})$, and another choice of projective resolutions changes it by a natural isomorphism, as in theorem 57.4.8(3).
2. If $\varphi\colon F \to A$ is a quasi-isomorphism from a bounded-above complex of flat right modules, then both chain maps in
$$A \otimes_R^L B = \operatorname{Tot}(A \otimes_R P_B) \xleftarrow{\varphi\otimes 1} \operatorname{Tot}(F \otimes_R P_B) \xrightarrow{1\otimes \pi_B} \operatorname{Tot}(F \otimes_R B)$$
are quasi-isomorphisms, so $A \otimes_R^L B \cong \operatorname{Tot}(F \otimes_R B)$ in $D(\mathbf{Ab})$. When $F = P_A$ is a projective resolution of A, this isomorphism is natural in chain maps of A and of B.
3. If $\psi\colon G \to B$ is a quasi-isomorphism from a bounded-above complex of flat left modules, then $A \otimes_R^L B \cong \operatorname{Tot}(A \otimes_R G)$ in $D(\mathbf{Ab})$.

***Proof*:**

Step 1: the first variable. Fix B. Every P_B^j is projective, hence flat by corollary 17.5.5. By lemma 57.4.14(1), $A \mapsto \operatorname{Tot}(A \otimes_R P_B)$ is a functor $\mathrm{K}^-(\text{Mod-}R) \to \mathrm{K}^-(\mathbf{Ab})$, and by lemma 57.4.14(3) it carries quasi-isomorphisms to quasi-isomorphisms. Followed by Q, it inverts the quasi-isomorphisms of $\mathrm{K}^-(\text{Mod-}R)$, so it factors uniquely through the localization of $\mathrm{K}^-(\text{Mod-}R)$ at them. By box 57.2.5 the canonical functor from that localization to $D^-(\text{Mod-}R)$ is an equivalence, so it is fully faithful. With the objects of $D^-(\text{Mod-}R)$ taken to be the bounded-above complexes it is also bijective on objects, hence an isomorphism of categories, and the factorization is a functor on $D^-(\text{Mod-}R)$.

Step 2: the second variable. By lemma 57.4.4(1), with the bounded-above complex of projectives P_B, each morphism $\beta\colon B \to B'$ of $D^-(R\text{-Mod})$ determines a unique $\tilde{\beta}\colon P_B \to P_{B'}$ in $\mathrm{K}(R\text{-Mod})$ with $Q(\pi_{B'})\,Q(\tilde{\beta}) = \beta\,Q(\pi_B)$. The uniqueness argument of Step 1 of the proof of theorem 57.4.8 makes $\beta \mapsto \tilde{\beta}$ a functor. Set $A \otimes_R^L \beta := Q\big(\operatorname{Tot}(A \otimes \tilde{\beta})\big)$.

Step 3: (1). Steps 3 and 4 of the proof of theorem 57.4.8 apply with $\operatorname{Tot}(-\otimes_R -)$ in place of $\operatorname{Hom}^\bullet$, lemma 57.4.14(1) in place of lemma 57.4.3(2), and lemma 57.4.4(1) in place of lemma 57.4.4(2), with one change. Those steps pass from chain maps to all morphisms by writing a morphism as a roof $Q(f)Q(s)^{-1}$ (theorem 57.2.4), and the apex of a roof between bounded-above complexes need not be bounded above, so it lies outside $\mathrm{K}^-(\text{Mod-}R)$, the domain of the functor of Step 1, and lemma 57.4.14 is proved only for bounded-above complexes. In place of roofs, use that every morphism of the localization of $\mathrm{K}^-(\text{Mod-}R)$, which is $D^-(\text{Mod-}R)$ by Step 1, is a composite of morphisms $Q(f)$ and $Q(s)^{-1}$ with f and s chain maps of bounded-above complexes and s a quasi-isomorphism. The construction in the proof of theorem 55.2.2 exhibits every morphism in this form, and any two localizations are identified by an isomorphism commuting with Q. The interchange square in Step 3 of the proof of theorem 57.4.8 commutes for each factor $Q(f)$ and $Q(s)^{-1}$ by the argument given there, hence for every morphism, and the same factorization gives the naturality in Step 4 of that proof. The values are bounded above by the degree bound after definition 57.4.12.

Step 4: (2). The map $\varphi \otimes 1$ is a quasi-isomorphism by the first half of lemma 57.4.14(3), every P_B^j being flat, and $1 \otimes \pi_B$ is one by the second half, every F^i being flat. For naturality when $F = P_A$, let $a\colon A \to A'$ and $b\colon B \to B'$ be chain maps, let $\tilde{a}\colon P_A \to P_{A'}$ be a lift with $\pi_{A'}\tilde{a}$ homotopic to $a\pi_A$ (theorem 56.2.17), and let $\tilde{b}$ be the morphism of Step 2 for $Q(b)$, so that $\pi_{B'}\tilde{b}$ and $b\pi_B$ are homotopic by the injectivity in lemma 57.4.4(1). Then

$$(\pi_{A'} \otimes 1)(\tilde{a} \otimes \tilde{b}) = \pi_{A'}\tilde{a} \otimes \tilde{b}, \qquad (1 \otimes \pi_{B'})(\tilde{a} \otimes \tilde{b}) = \tilde{a} \otimes \pi_{B'}\tilde{b}$$

are homotopic to $(a \otimes \tilde{b})(\pi_A \otimes 1)$ and $(\tilde{a} \otimes b)(1 \otimes \pi_B)$ by lemma 57.4.14(1), so both squares commute in $\mathrm{K}(\mathbf{Ab})$.

Step 5: (3). Let $\pi_A\colon P_A \to A$ be a projective resolution. By (2), $A \otimes^L_R B \cong \mathrm{Tot}(P_A \otimes_R B)$. By lemma 57.4.14(3), the maps $1 \otimes \psi\colon \mathrm{Tot}(P_A \otimes_R G) \to \mathrm{Tot}(P_A \otimes_R B)$, every P_A^i being flat, and $\pi_A \otimes 1\colon \mathrm{Tot}(P_A \otimes_R G) \to \mathrm{Tot}(A \otimes_R G)$, every G^j being flat, are quasi-isomorphisms. So $\mathrm{Tot}(P_A \otimes_R B) \cong \mathrm{Tot}(A \otimes_R G)$ in $D(\mathbf{Ab})$, completing the proof.

Weibel [101] Definition 10.6.1 and Theorem 10.6.3 construct $\otimes^L_R$ by resolving the second variable, as here, and (2) is Weibel's Exercise 10.6.1. By (2), for a fixed left module N the functor $A \mapsto A \otimes^L_R N \cong P_A \otimes_R N$ is the total left derived functor $L(- \otimes_R N)$ of definition 57.3.5.

Theorem 57.4.18: Tor **as the Cohomology of the Derived Tensor Product**

Let R be a ring, A a right R-module and B a left R-module, regarded as complexes in degree 0. For every $n \in \mathbb{Z}$ there is an isomorphism natural in A and B

$$\mathrm{Tor}^R_n(A, B) \cong H^{-n}\big(A \otimes^L_R B\big)$$

where $\mathrm{Tor}^R_n(-, B) = L_n(- \otimes_R B)$ is the left derived functor of definition 56.3.5, as in example 56.3.6(1). In particular $H^{-n}(A \otimes^L_R B) = 0$ for $n < 0$, $H^0(A \otimes^L_R B) \cong A \otimes_R B$, and $\mathrm{Tor}^R_n(A, B) \cong H^{-n}(A \otimes_R P_B)$ for a projective resolution P_B of B.

***Proof*:**
Let $\pi_A\colon P_A \to A$ be a projective resolution in the sense of definition 56.2.11, with $P_A^n = 0$ for $n > 0$. By theorem 57.4.17(2) there is an isomorphism $A \otimes^L_R B \cong \mathrm{Tot}(P_A \otimes_R B)$ natural in A and B, and since B sits in degree 0 this is the complex $P_A \otimes_R B$ with differential $d \otimes 1$. Its $(-n)$th cohomology is $L_n(- \otimes_R B)(A) = \mathrm{Tor}^R_n(A, B)$ by definition 56.3.5, whose construction, stated in example 56.3.6(1) for a commutative ring, uses no commutativity. For $n < 0$ the term P_A^{-n} is zero. In degree 0, the sequence $P_A^{-1} \to P_A^0 \to A \to 0$ is exact and $- \otimes_R B$ is right exact, so $H^0(P_A \otimes_R B) = \mathrm{coker}\big(P_A^{-1} \otimes_R B \to P_A^0 \otimes_R B\big) \cong A \otimes_R B$. The last statement is definition 57.4.15 itself, $\mathrm{Tot}(A \otimes_R P_B)$ being $A \otimes_R P_B$ when A sits in degree 0, completing the proof.

The theorem is Weibel [101] Theorem 10.6.3 and Corollary 10.6.4, and Gelfand-Manin [53] III.6.15. Its last statement is the balance of Tor, here over an arbitrary ring.

Over a commutative ring R a module is both a left and a right module, and each $X^i \otimes_R Y^j$ and each $\mathrm{Hom}_R(X^i, Y^j)$ is an R-module. Then $\mathrm{Tot}(X \otimes_R Y)$ and the Hom complex $\mathrm{Hom}^\bullet_R(X, Y)$ of definition 57.4.1, formed in R-Mod, are complexes of R-modules. A chain map of complexes of

R-modules is a quasi-isomorphism exactly when it is one of complexes of abelian groups, cohomology being computed on the underlying groups, so the constructions and proofs above run inside R-Mod. Writing $D(R)$ for $D(R\text{-Mod})$, they give

$$\otimes^L_R \colon D^-(R) \times D^-(R) \to D^-(R), \qquad R\mathrm{Hom}_R \colon D(R)^{\mathrm{op}} \times D^+(R) \to D(R)$$

with $R\mathrm{Hom}_R(B,C) = \mathrm{Hom}^\bullet_R(B, I_C)$. The forgetful functor R-Mod $\to$ **Ab** is exact, so it induces a functor $D(R) \to D(\mathbf{Ab})$, which carries these two bifunctors to those of theorem 57.4.17 and theorem 57.4.8.

Theorem 57.4.19: Adjunction Between $\otimes^L$ and RHom

Let R be a commutative ring, let $A, B \in D^-(R)$ and let $C \in D^+(R)$. There is an isomorphism

$$\mathrm{Hom}_{D(R)}\big(A \otimes^L_R B,\ C\big) \cong \mathrm{Hom}_{D(R)}\big(A,\ R\mathrm{Hom}_R(B,C)\big)$$

natural in A and C.

***Proof*:**

Step 1: the adjunction for complexes. Let X and Y be bounded-above complexes and Z any complex of R-modules, and define

$$\Phi \colon \mathrm{Hom}^\bullet_R\big(\mathrm{Tot}(X \otimes_R Y), Z\big) \to \mathrm{Hom}^\bullet_R\big(X, \mathrm{Hom}^\bullet_R(Y,Z)\big), \qquad \Phi(\varphi)(x)(y) := \varphi(x \otimes y)$$

In degree n the source is the product over pairs (i,j) of $\mathrm{Hom}_R(X^i \otimes_R Y^j, Z^{i+j+n})$, a homomorphism out of a finite direct sum being a family of homomorphisms, and the target is the product over the same pairs of $\mathrm{Hom}_R\big(X^i, \mathrm{Hom}_R(Y^j, Z^{i+j+n})\big)$, a homomorphism into a product being a family. On each factor Φ is the bijection of theorem 15.3.9, with both rings equal to R. For the differentials, let φ have degree n, $x \in X^i$ and $y \in Y^j$. By definition 57.4.1 and definition 57.4.12,

$$(D\varphi)(x \otimes y) = d_Z\varphi(x \otimes y) - (-1)^n \varphi(dx \otimes y) - (-1)^{n+i}\varphi(x \otimes dy)$$

On the other side $\Phi(\varphi)(x)$ has degree $i+n$ in $\mathrm{Hom}^\bullet_R(Y,Z)$, where D is $d_Z \circ - - (-1)^{i+n}(-) \circ d_Y$, so

$$\begin{aligned}\big(D\Phi(\varphi)\big)(x)(y) &= \big(D(\Phi(\varphi)(x))\big)(y) - (-1)^n \Phi(\varphi)(dx)(y) \\ &= d_Z\varphi(x \otimes y) - (-1)^{i+n}\varphi(x \otimes dy) - (-1)^n \varphi(dx \otimes y)\end{aligned}$$

The two agree, so Φ is an isomorphism of complexes.

Step 2: resolutions. Let $\pi_A \colon P_A \to A$ and $\pi_B \colon P_B \to B$ be the projective resolutions and $\iota_C \colon C \to I_C$ the injective resolution. By theorem 57.4.17(2) with $F = P_A$, the chain map $\pi_A \otimes 1 \colon T := \mathrm{Tot}(P_A \otimes_R P_B) \to \mathrm{Tot}(A \otimes_R P_B) = A \otimes^L_R B$ is a quasi-isomorphism. By corollary 57.4.5(1), $\pi_B^* \colon \mathrm{Hom}^\bullet_R(B, I_C) \to \mathrm{Hom}^\bullet_R(P_B, I_C) =: H$ is one, so $R\mathrm{Hom}_R(B,C) \cong H$ in $D(R)$.

Step 3: the chain of isomorphisms. Using Step 2 and $Q(\iota_C)$, then lemma 57.4.4(2), lemma 57.4.3(1),

Step 1, lemma 57.4.3(1), lemma 57.4.4(1), and finally Step 2 with $Q(\pi_A)$,

$$\begin{aligned}\mathrm{Hom}_{D(R)}(A \otimes^L_R B, C) &\cong \mathrm{Hom}_{D(R)}(T, I_C) \cong \mathrm{Hom}_{\mathrm{K}(R\text{-Mod})}(T, I_C) = H^0\mathrm{Hom}^\bullet_R(T, I_C)\\ &\cong H^0\mathrm{Hom}^\bullet_R(P_A, H) = \mathrm{Hom}_{\mathrm{K}(R\text{-Mod})}(P_A, H) \cong \mathrm{Hom}_{D(R)}(P_A, H)\\ &\cong \mathrm{Hom}_{D(R)}\big(A, R\mathrm{Hom}_R(B, C)\big)\end{aligned}$$

Step 4: naturality. By lemma 57.4.4(1), a morphism $\alpha\colon A \to A'$ of $D^-(R)$ determines a unique $\tilde{\alpha}\colon P_A \to P_{A'}$ in $\mathrm{K}(R\text{-Mod})$ with $Q(\pi_{A'})\,Q(\tilde{\alpha}) = \alpha\,Q(\pi_A)$, and under the isomorphisms of Step 2 it acts as $Q(\mathrm{Tot}(\tilde{\alpha} \otimes 1))$ on T, by the factorization in Step 1 of the proof of theorem 57.4.17, and as $Q(\tilde{\alpha})$ on P_A. By theorem 57.4.8(1), a morphism $\gamma\colon C \to C'$ acts on I_C as $Q(\tilde{\gamma})$. Each isomorphism of Step 3 commutes with precomposition by these and postcomposition by $\tilde{\gamma}$: the two uses of lemma 57.4.3(1) by its part (3), the two uses of lemma 57.4.4 because Q is a functor, and Φ because $\Phi\big(\varphi \circ \mathrm{Tot}(\tilde{\alpha} \otimes 1)\big) = \Phi(\varphi) \circ \tilde{\alpha}$ and $\Phi(\tilde{\gamma} \circ \varphi) = \tilde{\gamma}_* \circ \Phi(\varphi)$ by the formula for Φ. So the composite isomorphism is natural in A and C, completing the proof.

This is Weibel [101] Theorem 10.8.7, which states it as an adjunction between $- \otimes^L_R B\colon D^-(R) \to D^-(R)$ and $R\mathrm{Hom}_R(B, -)\colon D^+(R) \to D^+(R)$, for fixed $B \in D^-(R)$. The two functors have different domains, so the precise content is the bijection of the theorem, natural in $A \in D^-(R)$ and $C \in D^+(R)$. That $R\mathrm{Hom}_R(B, C)$ lies in $D^+(R)$ is theorem 57.4.8(4).

57.4.20 Note: Where the Bounds Enter The bounds enter at two places. Lemma 57.4.4 needs P bounded above and I bounded below, through proposition 56.2.8, and lemma 57.4.14(2) needs the flat factor bounded above, through the acyclic assembly lemma proposition 56.5.4. The bound on the other factor only makes the sums in definition 57.4.12 finite. With the direct sums of that definition, the exactness in (2) needs only the bound on the flat factor, by the remark after proposition 56.5.4. The first bound cannot be dropped: example 59.1.7 gives an exact complex of injective $\mathbb{Z}/4$-modules, unbounded in both directions, for which the conclusion of lemma 57.4.4(2) fails, and exercise 57.4.1 (1) asks for a second one. Defining $R\mathrm{Hom}$ and $\otimes^L$ on unbounded complexes, with the adjunction of theorem 57.4.19, requires K-injective and K-flat resolutions, which chapter 59 constructs.

Exercise 57.4.1

1. Let k be a field, $\Lambda = k[x]/(x^2)$, and I the complex of Λ-modules with $I^n = \Lambda$ for every $n \in \mathbb{Z}$ and every differential multiplication by x. Show that Λ is an injective Λ-module, that I is exact, and that id_I is not null-homotopic. Conclude that $\mathrm{Hom}_{\mathrm{K}(\Lambda\text{-Mod})}(I, I) \neq 0 = \mathrm{Hom}_{D(\Lambda\text{-Mod})}(I, I)$, so that the bound in lemma 57.4.4(2) cannot be dropped. (For the null-homotopy, use lemma 56.1.28.)

2. Let $a, b \geq 1$ and $d = \gcd(a, b)$. Compute $H^n R\mathrm{Hom}(\mathbb{Z}/a, \mathbb{Z}/b)$ for every n twice: from the injective resolution $\mathbb{Z}/b \to \mathbb{Q}/\mathbb{Z} \xrightarrow{b} \mathbb{Q}/\mathbb{Z}$, whose first map sends 1 to the class of $1/b$, and, through proposition 57.4.9, from the projective resolution $\mathbb{Z} \xrightarrow{a} \mathbb{Z}$ of $\mathbb{Z}/a$. Check that both give $\mathbb{Z}/d$ for $n = 0, 1$ and 0 otherwise, in agreement with example 56.4.10.

3. Let $\mathcal{A}$ have enough injectives, let A be an object and let $0 \to B' \xrightarrow{u} B \xrightarrow{v} B'' \to 0$ be a short exact sequence in $\mathcal{A}$. Using theorem 57.2.10, proposition 57.1.8 and theorem 57.4.10, derive a

long exact sequence

$$0 \to \mathrm{Hom}(A, B') \to \mathrm{Hom}(A, B) \to \mathrm{Hom}(A, B'') \to \mathrm{Ext}^1(A, B') \to \cdots$$
$$\cdots \to \mathrm{Ext}^n(A, B) \to \mathrm{Ext}^n(A, B'') \to \mathrm{Ext}^{n+1}(A, B') \to \cdots$$

in which $\mathrm{Ext}^n(A, B') \to \mathrm{Ext}^n(A, B)$ is $\mathrm{Ext}^n(A, u)$. State and derive the corresponding sequence in the first variable for a short exact sequence $0 \to A' \to A \to A'' \to 0$.

4. Let A be the complex of abelian groups with $A^k = \mathbb{Z}$ for $k \geq 0$, $A^k = 0$ for $k < 0$, and every differential zero. Show that $H^{-k}R\mathrm{Hom}(A, \mathbb{Z}) \cong \mathbb{Z}$ for every $k \geq 0$, so that $R\mathrm{Hom}(A, \mathbb{Z})$ does not lie in $D^+(\mathbf{Ab})$ and the hypothesis of theorem 57.4.8(4) cannot be dropped. (Use the resolution $I_{\mathbb{Z}}$ of example 57.4.7 and lemma 56.1.11.)

5. Let $s\colon P \to \mathbb{Z}/2$ be the projective resolution of example 57.4.2. Show that $\mathrm{Tot}(s \otimes \mathbb{Z}/2)$ is not a quasi-isomorphism. Which hypothesis of lemma 57.4.14(3) fails, and which complex in Step 2 of its proof fails to be exact? Compare example 57.3.1, which tests the same quasi-isomorphism against $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}/2, -)$.

6. Let R be a commutative ring. Show that $R \otimes^L_R B \cong B$ in $D(R)$ for every $B \in D^-(R)$, and that $\mathrm{Hom}_{D(R)}(R, X) \cong H^0(X)$ for every complex X of R-modules. Combine these with theorem 57.4.19 for $A = R$ to obtain $\mathrm{Hom}_{D(R)}(B, C) \cong H^0R\mathrm{Hom}_R(B, C)$ for $B \in D^-(R)$ and $C \in D^+(R)$, and compare with theorem 57.4.10(1).

7. Let R be a commutative ring and X, Y bounded-above complexes of R-modules. Show that $\mathrm{sw}(x \otimes y) := (-1)^{ij}\, y \otimes x$, for $x \in X^i$ and $y \in Y^j$, is an isomorphism of complexes $\mathrm{Tot}(X \otimes_R Y) \to \mathrm{Tot}(Y \otimes_R X)$, and that the same formula without the sign is not a chain map when $X = Y = P$ is the complex of example 57.4.13. Deduce that $A \otimes^L_R B \cong B \otimes^L_R A$ in $D(R)$ for $A, B \in D^-(R)$, and that $\mathrm{Tor}^R_n(A, B) \cong \mathrm{Tor}^R_n(B, A)$ for R-modules A and B.

58

Applications of (co)Homology

With cohomology theory more securely under our belt, it is time to use it! All the work in this chapter can be learnt without the need for any algebraic topology background, as it is the goal of the book to minimize the need for external material. However, the proceeding ideas are abstractions of ideas in algebraic topology, and ignoring the source of inspiration for these ideas is itself a disservice to the pedagogy of the material. Therefore, the section will be written in such a way that a background in homology/cohomology will be advantageous. Namely, it is best if the reader is familiar with simplicial and singular homology, how cohomology is derived from $\mathrm{Hom}(C_\bullet(X), G) = C^\bullet(X; G)$ and the relation of homology to cohomology (ex. the universal coefficient theorem for cohomology). The reader may choose to consult [76] or [59] for the details.

This chapter does *not* present an in-depth coverage of any of the material, in particular these subjects are a large source of modern development in mathematics (as of the early 21st century). The material presented is to demonstrate to the reader the power of cohomological theories so that the reader has an easier time when reading the more dense books containing this information. For a book in the EYNTKA series covering group and Galois cohomology, see [26], and for K-theory see [81].

In this chapter we:

1. Shall use the above theory to find cohomological invariants of groups
2. Shall show some ways of interpreting Ext and Tor
3. Shall show that the notion of dimension from the geometric setting can be brought over to the algebraic!
4. Some K-theory will certainly interest the reader

We shall not do sheaf cohomology, as (naturally) it required sheaf theory that was not covered, and it is an exploration for EYNTKA Algebraic Geometry [13].

58.1 Group Cohomology

We start with no link to algebraic topology, and shall include the relation to singular cohomology before the examples.

Given a (not necessarily abelian) group G, what would it mean to extract cohomological information from it? A (co)chain would have to naturally be formed, and a functor must be found to derive. Groups themselves do not form an abelian category, but it was shown that representations, that is $k[G]$-modules, do form them. This is perhaps a first place in which we may think we can study groups, however this category is too nice (think of (co)homology with $\mathbb{Z}$ vs. $\mathbb{R}/\mathbb{C}$ coefficients). What is more useful is it's generalization:

Definition 58.1.1: G-Modules

Let G be an arbitrary group, and M an abelian group. Then M is a *G-module* if there exists a [left] group-action on M. Equivalently, if there exists a $\mathbb{Z}[G]$-module structure on M.

The reader is free to parse through the technicalities of the group action. All $k[G]$-modules presented in chapter 53 are $\mathbb{Z}[G]$-modules with the action restricted. An example of a G-module that is not a representation is the action of the group $\mathrm{Gal}_K(L)$ on the module L/K (a galois extension of L over K). All finite groups G have a non-trivial G-module given by the action of G on the group-ring $k[G]$ (note the addition is abelian). From a geometric perspective, modules represent sheaves (or in special cases vector bundles) over some schemes,

As we have seen many times at this point, the object acts on an abelian group can give lots of information on the object acting on it and the object being acted on. Given a G-module M, we can define the following:

Definition 58.1.2: G-Invariant subgroup

Let M be a G-module. Then the *G-invariant* set of M is the set:

$$M^G := \{m \in M \mid g \cdot m = m,\ \forall g \in G\}$$

which is the largest trivial G-submodule of M.

It is easy to see that $(-)^G$ is a functor. The following will help in computing cohomology

Corollary 58.1.3: Hom Representation of G-invariant

$$M^G \cong \mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}, M^G) \cong \mathrm{Hom}_G(\mathbb{Z}, M)$$

***Proof*:**
Give $\mathbb{Z}$ the trivial G-action, which is the action the statement requires.

For any abelian group N, evaluation at 1 is an isomorphism $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}, N) \to N$, with inverse sending x to the map $m \mapsto mx$. Taking $N = M^G$ gives the first isomorphism.

For the second, let $\varphi\colon \mathbb{Z} \to M$ be $\mathbb{Z}[G]$-linear and put $m = \varphi(1)$. Equivariance gives $\varphi(g \cdot 1) = g\varphi(1)$, and $g \cdot 1 = 1$ because the action on $\mathbb{Z}$ is trivial, so $m = gm$ for every $g \in G$, that is $m \in M^G$. Conversely, any $m \in M^G$ defines a $\mathbb{Z}[G]$-linear map $\mathbb{Z} \to M$, $k \mapsto km$, since $g(km) = k(gm) = km$. These assignments are mutually inverse and additive, so $\mathrm{Hom}_G(\mathbb{Z}, M) \cong M^G$, completing the proof.

Similarly, we can define:

Definition 58.1.4: G-Coinvariant subgroup

Let M be a G-module. Then the *G-coinvariant* of M is the set:

$$M_G := \frac{M}{\langle (gm - m) \mid g \in G, m \in M \rangle}$$

and is the maximal invariant quotient module with the trivial action.

Just like $(-)^G$, $(-)_G$ is also a functor. The reader should further verify that

Proposition 58.1.5: Tensor Representation of Coinvariant Module

$$M_G \cong_G \mathbb{Z} \otimes_{\mathbb{Z}[G]} M$$

Proposition 58.1.6: Invariants Is Left-exact

The functor $(-)^G$ is left-exact, the functor $(-)_G$ is right exact.

***Proof*:**
First, prove that $(-)^G$ is right-adjoint to the trivial-action functor.

$$\mathrm{Hom}(T(M), N) \cong \mathrm{Hom}(M, N^G)$$

And similarly for $(-)_G$; it is left-adjoint to the trivial-action functor. As $T(-)$ is an exact functor, $(-)^G$ and $(-)_G$ are left-exact and right-exact respectively, completing the proof.

Both of these functors are not exact:

Example 58.1.7: Lack Of Exactness's
Let $G = C_2$ be the cyclic group of order 2 and:

$$0 \to I_G \to \mathbb{Z}[G] \xrightarrow{\epsilon} \mathbb{Z} \to 0$$

where $\epsilon(1 \cdot a + \sigma \cdot b) = a + b$ and I_G is the kernel. This sequence is exact. Take $(-)^G$:

$$0 \to (I_G)^G \to (\mathbb{Z}[G])^G \xrightarrow{\epsilon^G} (\mathbb{Z})^G \to 0$$

i.e.:

$$0 \to 0 \to \Delta \xrightarrow{\epsilon^G} \mathbb{Z} \to 0$$

where $\Delta = \{(a,a) \mid a \in \mathbb{Z}\}$. Then ϵ^G is no longer surjective as $\epsilon^G(a,a) = 2a$. The above example can also be used to show $(-)_G$ is not left-exact. More generally, if $0 \to M_2^G \to M_2 \to M_3 \to 0$ is exact, taking $(-)^G$ does not change $M - 2^G$, but now we get an isomorphism between the 1st and second terms, so it cannot be surjective.

More generally, let G act trivially on a coset $[m]$ of a quotient M/L. Can this action always be lifted so that G acts trivially on a representative m?

Thus, it is fruitful to take the ith right-derived functor of $(-)^G$ (similarly the left-derived functors of $(-)_G$):

$$\mathbf{R}^i(-)^G := H^i(G,-)$$

which would give us the long exact sequence of abelian groups:

$$0 \to L^G \to M^G \to N^G \to H^1(G,L) \to H^1(G,M) \to \cdots$$

Since $M^G = \text{Hom}_G(\mathbb{Z}, M)$ by taking an injective resolution of M, or a projective resolution of $\mathbb{Z}$, we can write:

$$H^i(G,M) = \text{Ext}^i_{\mathbb{Z}[G]}(\mathbb{Z}, M)$$

Note that $H^0(G,M) = M^G$, hence the higher order cohomology groups represent some failure for points to be fixed. Let us compute some examples to show the power of the machinery developed in chapter 56 before concretely demonstrating how the cohomology groups represent the obstruction of points being fixed.

Example 58.1.8: Group Cohomologies – Homological Algebra Computations

1. The trivial group has trivial cohomology
2. (Integers) Let $G = \mathbb{Z}$. Then $\mathbb{Z}[G] \cong \mathbb{Z}[x, x^{-1}]$. Then since $\mathbb{Z}[x,x^{-1}]/(1-x) \cong_G \mathbb{Z}$ with the trivial action, define the following free (hence projective) resolution:

   $$\cdots \to 0 \to \mathbb{Z}[x,x^{-1}] \xrightarrow{\cdot(1-x)} \mathbb{Z}[x,x^{-1}] \to 0 \to \cdots$$

   Applying the (contravariant) $\text{Hom}_{\mathbb{Z}[x,x^{-1}]}(-,M)$, we can compute the cohomology of

   $$\cdots \to 0 \to M \xrightarrow{\cdot(1-x)} M \to 0 \to \cdots$$

   Then we can conclude by direct computation:

   $$H^0(\mathbb{Z},M) \cong \ker(M \xrightarrow{\cdot(1-x)} M) = M^{\mathbb{Z}}$$

   and:

   $$H^1(\mathbb{Z},M) = \frac{M}{(1-x)M}$$

   and furthermore $H^i(\mathbb{Z},M) = 0$ for $i \notin \{0,1\}$
3. Let $G = C_n$ be a finite cyclic group of over n with generator σ. Let us form a free resolution of $\mathbb{Z}[G]$ by taking advantage of the fact that $\sigma - 1$ and $N = \sum_{i=0}^{n-1} \sigma^i$ are zero divisors:

   $$N \cdot (\sigma - 1) = (1 + \sigma + \cdots + \sigma^{n-1})(\sigma - 1) = \sigma^n - 1 = 1 - 1 = 0$$

This gives a resolution:

$$\cdots \xrightarrow{\sigma-1} \mathbb{Z}[G] \xrightarrow{N} \mathbb{Z}[G] \xrightarrow{\sigma-1} \mathbb{Z}[G] \xrightarrow{\epsilon} \mathbb{Z} \to 0$$

where

$$\epsilon\left(\sum_g a_g g\right) = \sum_g a_g$$

is the usual augmentation map. Then:

$$H^k(C_n, M) = \begin{cases} \frac{M^G}{NM} & k \text{ even}, k \geq 2 \\ \frac{{}_N M}{(\sigma-1)M} & k \text{ odd}, k \geq 1 \end{cases} \qquad \text{where} \qquad {}_N M = \{m \in M \mid N \cdot m = 0\}$$

For example, if $M = \mathbb{Z}$, then:

$$H^k(C_n, \mathbb{Z}) = \begin{cases} \mathbb{Z}/m\mathbb{Z} & k \text{ even}, k \geq 2 \\ 0 & \text{otherwise} \end{cases}$$

4. Let $G = *_{s\in S}\mathbb{Z}$ be the free product of S copies of $\mathbb{Z}$. This has a simple free resolution, namely take:
$$\epsilon : \mathbb{Z}[G] \to \mathbb{Z}$$
where the kernel is:
$$I_S = \sum_{s\in S} \mathbb{Z}[G] \cdot (s-1)$$
It should be verified that I_S is a free G-module, hence we have a free-resoluion:
$$0 \to I_S \to \mathbb{Z}[G] \xrightarrow{\epsilon} \mathbb{Z} \to 0$$
and cohomology:
$$H^k(*_{s\in S}\mathbb{Z}, \mathbb{Z}^G) = \begin{cases} \mathbb{Z} & k = 0 \\ \bigoplus_{s\in S} \mathbb{Z} & k = 1 \\ 0 & k \geq 2 \end{cases}$$

5. (If you know some algebraic geometry) *Galois Cohomology*: Take the category of varieties W over k such that when extending scalars to $\overline{k}$ we have $V/\overline{k} \cong W/\overline{k}$. Let's label it $\mathbf{Var}_{k\to\overline{k}}$, and say that the objects are:
$$\text{Obj}(\mathbf{Var}_{k\to\overline{k}}) = \left\{W/k \;\middle|\; V/\overline{k} \cong W/\overline{k}\right\}$$
and the morphism are regular morphisms. Then I claim that:
$$\mathbf{Var}_{k\to\overline{k}} \cong H^1(\text{Gal}_k(\overline{k}), \text{Aut}(V/\overline{k}))$$
To see this, first note that an element $\sigma \in \text{Gal}_k(\overline{k})$ acts on a $\overline{k}$-variety $W/\overline{k} = W_k \times_{\text{Spec}\,(k)} \text{Spec}\,(\overline{k})$ via:
$$\text{id}_{W_k} \times \text{Spec}\,(\sigma^{-1}) : W/\overline{k} \to W/\overline{k}$$
Or, for those less comfortable with fibered produced from algebraic geometry, they can think of this map as the "equivalent":
$$\text{id}_{W_k} \otimes_k \sigma^{-1} : k[W] \otimes_k \overline{k}$$

With the action defined, let us look at the correspondence. Take $W_k \in \mathbf{Var}_{k\to\overline{k}}$ so that $\varphi : W_{\overline{k}} \xrightarrow{\sim} V_{\overline{k}}$ is an isomorphism. Then notice that this isomorphism induces a map $\varphi \circ \sigma^{-1} \circ \varphi^{-1}$, which is an automorphism on $W_{\overline{k}}$. The collection of all these maps as σ varies can uniquely define W_k (k is the fixed subfield over all σ). This is true up to a choice of $\mathrm{Aut}_k(V)$, and so we quotient out by it. Then we can see this creates the correspondence between these two categories, and shows how far away the category $\mathbf{Var}_{k\to\overline{k}}$ is from being invariant to the group-action of the galois group.

6. (if you know elliptic curves) An excellent example of where galois cohomology is immediately useful is in the theory of elliptic curves. On a high level, it is relatively easy to find the solution of an elliptic curve over $\mathbb{C}$, but it becomes much more difficult to solve it over finite extensions of $\mathbb{Q}$, or $\mathbb{Q}$ itself. If the reader has read (or is reading) [25], then the have encountered the short exact sequence of $\mathrm{Gal}_K(\overline{K})$-modules:

$$0 \to E[m] \to E(\overline{K}) \xrightarrow{[m]} E(\overline{K}) \to 0$$

where $E[m]$ are the m-torsion points of an elliptic curve ($m \geq 2$), K is a number field, $E(\overline{K})$ are the points of the elliptic curve over $\overline{K}$. Let $G = \mathrm{Gal}_K(\overline{K})$. Then when considering solutions over K, the short exact sequence sequence becomes a long exact sequences:

$$\begin{aligned} 0 \to E(K)[m] \to E(K) \xrightarrow{[m]} E(K) \xrightarrow{\delta} H^1(G, E[m]) \\ \to H^1(G, E(\overline{K})) \xrightarrow{[m]} H^1(G, E(\overline{K}) \to \cdots \end{aligned}$$

This is the foundation on which the torsion-free points of E/K will be computed!

7. If the reader knows about the classifying space BG, then:

$$H^n(BG, \mathbb{Z}) \cong H^n(G, \mathbb{Z})$$

where he left hand side is singular cohomology and the right hand side is group cohomology.

What obstruction information does this capture? Since there is a failure in surjectivity $\varphi : M \twoheadrightarrow N$ when applying $(-)^G$, this means that a fixed element $n \in N^G$ does *not* necessarily come form a fixed element $m \in M^G$. Thus, even though $\varphi(m) = n$ exists, it need not be the case that there exists an $m' \in M^G$ such that $\varphi^G(m') = n$. To measure this failure, take the short exact sequence

$$0 \to L \xrightarrow{\iota} M \xrightarrow{\varphi} N \to 0$$

and let $n \in N^G$. As $N^G \subseteq N$, there exists an $m \in M$ such that $\varphi(m) = n$. Consider any $g \in G$ and take $g \cdot m - m$. Then applying the G-homomorphism:

$$\varphi(g \cdot m - m) = g \cdot \varphi(m) - \varphi(m) = g \cdot n - n \overset{!}{=} n - n = 0$$

where $\overset{!}{=}$ comes from $n \in N^G$. By exactness $\ker\varphi = \mathrm{im}\iota$, so there must exist an element $\lambda_m(g) \in L$ such that

$$\iota(\lambda_m(g)) = g \cdot m - m$$

Now, $n \in N^G$ can be lifted if and only if $g \cdot m - m = 0$ for all $g \in G$, since then $m \in M^G$. In terms of elements of L:

$$\forall g \in G,\ \iota(\lambda_m(g)) = 0$$

by injectivity, it must be that $\lambda_m(g) = 0$ for all $g \in G$. Thus, the function $\lambda_m : G \to L$ is non-trivial if the lift does not exist. Let us explore the properties of λ_m. First, if $g_1, g_2 \in G$ then:

$$\begin{aligned}\iota(\lambda_m(g_1g_2)) &= g_1g_2 \cdot m - m \\ &= g_1g_2 \cdot m - g_1 \cdot m + g_1 \cdot m - m \\ &= g_1 \cdot (g_2 \cdot m - m) + (g_1 \cdot m - m) \\ &= g_1\iota(\lambda_m(g_2)) + \iota(\lambda_m(g_1)) \\ &= \iota(g_1\lambda_m(g_2)) + \iota(\lambda_m(g_1)) \\ &= \iota(g_1\lambda_m(g_2) + \lambda_m(g_1))\end{aligned}$$

Thus, as f is injective (more specifically a monomorphism) we get:

$$\lambda_m(g_1g_2) = \lambda_m(g_1) + g_1\lambda_m(g_2)$$

A function with this property is given a name:

Definition 58.1.9: 1-Cocycle

A function $f : G \to M$ is a called a *1-cocycle*, *1-derivation*, or *crossed homomorphism* if:

$$f(gh) = f(g) + gf(h)$$

The set of all derivations is denoted $Z^1(G, M)$. If it is clear from context, the "1-" is dropped.

Now, the above λ_m was dependent on a choice of m. But $M \hookrightarrow N$ is surjective, and hence there may be another m' such that $\varphi(m') = n$. As φ is a G-homomorphism

$$\varphi(m - m') = c - c = 0$$

and so $m - m' \in \ker\varphi = \text{im}\iota$. Thus, there is an $\ell \in L$ such that

$$m - m' = \iota(\ell) \qquad \text{or} \qquad m' = m + \iota(\ell)$$

Thus, let us relate $\lambda_{m'}$ to λ_m:

$$\begin{aligned}\iota(\lambda_{m'}(g)) &= g \cdot m' - m' \\ &= g \cdot (m + \iota(\ell)) - m - \iota(\ell) \\ &= g \cdot m + g \cdot \iota(\ell)) - m - \iota(\ell) \\ &= (g \cdot m - m) + g \cdot \iota(\ell) - \iota(\ell) \\ &= \iota(\lambda_m(g)) + \iota(g \cdot \ell) - \iota(\ell) \\ &= \iota(\lambda_m(g) + g \cdot \ell - \iota(\ell))\end{aligned}$$

Thus, as ι is a monomorphism:

$$\lambda_{m'}(g) = \lambda_m(g) + g \cdot \ell - \ell$$

Thus, the term $g \cdot \ell - \ell$ can be seen as the "trivial" part of the obstruction, as it does not change the difficulty in finding an obstruction. This is given a name:

Definition 58.1.10: 1-Coboundary

A function $f_m : G \to M$ is a called a *1-coboundary* or *principal derivation* if:

$$f_m(g) = g \cdot m - m$$

The set of all boundary maps is denoted $B^1(G, M)$.If it is clear from context, the "1-" is dropped.

Note that a coboundary is a cocycle:

$$f_m(gh) = gh \cdot m - m = gh \cdot m - h \cdot m + h \cdot m - m = f_m(g) + gf_m(h)$$

Hence $B^1(G, M) \subseteq Z^1(G, M)$. It shall be shown in a moment that:

$$H^1(G, M) \cong \frac{Z^1(G, M)}{B^1(G, M)}$$

First, let us show there is a map $L^G \to H^1(G, M)$. Indeed there is a well-defined G-module homomorphism:


$$\ell \mapsto [g \mapsto g \cdot m - m]$$

where m is in the fiber of ℓ.

Let us next motivate the 2nd order cohomology group. Let us assume the cocycle-representation and the derived functor representation are isomorphic for the next part. Let us start with the long exact sequence we know is given:

$$0 \to L^G \xrightarrow{\alpha} M^G \xrightarrow{\beta} N^G \xrightarrow{\delta^0} H^1(G, L) \xrightarrow{\alpha_*} H^1(G, M) \xrightarrow{\beta_*} H^1(G, N) \xrightarrow{\delta^1} H^2(G, L) \cdots$$

Consider $[\nu] \in H^1(G, N)$; let us call it a 1-obstruction. Then can it be lifted some $[\mu] \in H^1(G, M)$, namely does there exist $[\mu]$ such that $\beta_*([\mu]) = [\nu]$. To find out, first take some representative cocycle $\nu : G \to N$ (notice we are now working with a map, not an element). As $M \hookrightarrow N$ is surjective, we have a diagram:



We can certainly lift each point *locally*, namely given a point $\nu(g) = n \in N$ there is a point (or points) m such that $\beta(m) = n$[1]. But this lifting can fail *globally*, namely such a lift is not guaranteed to be a 1-cocycle. This mirrors the general pattern in cohomology where having local data of a function does not imply the existence of a global function that restricts to all the local data. Let us measure this failure of lifting. If the lifted μ is a cocycle, it would satisfy:

$$\mu(g_1 g_2) - \mu(g_1) - g_1 \mu(g_2) = 0$$

Thus, define the function:

$$\psi : G \times G \to M, \qquad \psi(g_1, g_2) = \mu(g_1 g_2) - \mu(g_1) - g_1 \mu(g_2)$$

[1]Technically, the axiom of choice is invoked here for making a potentially uncountable number of choices

Let us show that for any $(g_1, g_2) \in G \times G$, $\psi(g_1, g_2) \in \ker \beta$. Indeed:

$$\begin{aligned}
\beta(\psi(g_1, g_2)) &= \beta(\mu(g_1 g_2) - \mu(g_1) - g_1\mu(g_2) \\
&= \beta(\mu(g_1 g_2)) - \beta(\mu(g_1)) - \beta(g_1\mu(g_2)) \\
&\overset{!}{=} \nu(g_1 g_2)) - \nu(g_1) - g_1\nu(g_2)) \\
&= 0 && \nu \text{ is a cocycle}
\end{aligned}$$

where $\overset{!}{=}$ comes from μ being defined as a lift of ν and hence $\beta \circ \mu = \nu$. Thus, by exactness $\ker \beta = \text{im}\alpha$ and so for each pair $(g_1, g_2) \in G \times G$, there exists a unique element in L that maps to $\psi(g_1, g_2)$, namely there exists a function $\Omega : G \times G \to L$ such that

$$\alpha(\Omega(g_1, g_2)) = \psi(g_1, g_2)$$

This Ω would now be our new 2-cocycle and are denoted $Z^2(G, M)$. Doing a similar but longer computations such as the one for the 1-cycle, we can find that:

$$g_1\Omega(g_2, g_3) - \Omega(g_1 g_2, g_3) + \Omega(g_1, g_2 g_3) - \Omega(g_1, g_2) = 0$$

Similarly, an explicit computation would fine that 2-boundaries (given a 1-chain ψ) are of the form

$$\Omega(g_1, g_2) = g_1 \cdot \psi(g_2) - \psi(g_1 g_2) + \psi(g_1)$$

These are label $B^2(G, M)$ and:

$$H^2(G, M) \cong \frac{Z^2(G, M)}{B^2(G, M)}$$

The same process continues for higher order cohomology. For the reader who knows some algebraic topology, the following informal discussion grounds the higher order group-cohomology as the singular (or simplicial) cohomology of BG, the classifying space of G with the property that $\pi_1(BG) = G$ and $\pi_n(BG) = \{0\}$ for all $n > 1$ (see [76, Existence of the Universal Bundle, Cohomology of BG is Group Cohomology]). In particular, regarding a G-module M as a local coefficient system on BG,

$$H^n(BG; M) \cong H^n(G, M)$$

where the left side is cohomology with local coefficients. When G acts trivially on M it is the singular cohomology $H^n_{\text{Sing}}(BG; M)$ with constant coefficients. Using the nerve or bar construction on BG and considering the usual covering $EG \to BG$ we get the following correspondence:

Geometric Object in EG	Correspondence in BG	Algebraic equivalent
0-Simplices (Vertices)	A single 0-simplex, base point $*$.	elements of G
1-Simplices (Edges)	Directed edge for each element $g \in G$. An arrow from $*$ to $*$ labeled by g.	Functions on G
2-Simplices (Triangles)	Oriented triangle for each pair $(g_1, g_2) \in G \times G$. Edges are the 1-simplices for g_1, g_2, and the product $g_1 g_2$.	Functions on $G \times G$
3-Simplices (Tetrahedral)	Oriented tetrahedron for each triple $(g_1, g_2, g_3) \in G \times G \times G$. Faces are the triangles for (g_2, g_3), $(g_1, g_2 g_3)$, etc.	Functions on $G \times G \times G$

n-Simplices	n-tuple $(g_1, \dots, g_n) \in G^n$.	Functions on G^n

Where "functions" here means set-function (to take into account the "failed" lifting), and the transition maps d_i captures the G-module homomorphism information. Geometrically, the G-module homomorphisms correspond to G-equivariant maps $f : G^n \to M$.

Using this intuition, we can construct a standard way of defining a projective resolution of $\mathbb{Z}$ by G-modules. First, let $\mathbb{Z}[G^n]$ be a G-module with the diagonal action given by multiplying on the left, or more specifically:

$$g \cdot (g_1, ..., g_n) = (gg_1, ..., gg_n)$$

Note that this diagonal map corresponds to the natural action of left multiplication by g on EG. These modules are free G-modules; clearly $\mathbb{Z}[G]$ is a $\mathbb{Z}$-module with basis given by the elements G. Then for $n \geq 0$:

$$\mathbb{Z}[G^{n+1}] \cong \bigoplus_{(g_1,...,g_n) \in G^n} \mathbb{Z}[G] \cdot (1, g_1, ..., g_n)$$

which shows that these are free. From this, we can consider the following projective (even free) resolution:

Definition 58.1.11: Standard Resolution

Let G be a group. Then the *standard resolution* of $\mathbb{Z}$ by G-modules is the exact sequence of G-module homomorphism:

$$\cdots \to \mathbb{Z}[G^{n+1}] \xrightarrow{d_n} \mathbb{Z}[G^n] \xrightarrow{d_{n-1}} \cdots \xrightarrow{d_1} \mathbb{Z}[G] \xrightarrow{\epsilon} \mathbb{Z} \to 0$$

where $\mathbb{Z}[G^{n+1}]$ carries the diagonal G-action and, on the basis G^{n+1},

$$d_n(g_0, ..., g_n) = \sum_{i=0}^{n} (-1)^i (g_0, ..., \hat{g}_i, ..., g_n)$$

the term $\hat{g}_i$ being omitted from the tuple, while $\epsilon(g) = 1$ for every $g \in G$. The map ϵ is also called the *augmentation map*.

Note that each $\mathbb{Z}[G^{n+1}]$ is a free $\mathbb{Z}[G]$-module, the diagonal action permuting a basis freely. We claimed this is an exact sequence, however this ought to be verified.

Lemma 58.1.12: Standard Resolution is Exact

The standard resolution of $\mathbb{Z}$ by G-modules is exact

This shows that the nomenclature of cocycles and coboundaries above is used correctly.

***Proof*:**
Exactness is a statement about the underlying abelian groups, so it is enough to produce a contracting homotopy by $\mathbb{Z}$-linear maps; these need not be G-equivariant, and indeed the ones below are not.

Step 1: The maps. Write $e \in G$ for the identity element and define

$$s_{-1}\colon \mathbb{Z} \to \mathbb{Z}[G], \quad 1 \mapsto (e), \qquad s_n\colon \mathbb{Z}[G^{n+1}] \to \mathbb{Z}[G^{n+2}], \quad (g_0, \dots, g_n) \mapsto (e, g_0, \dots, g_n)$$

extended $\mathbb{Z}$-linearly.

Step 2: The contracting identity in positive degrees. Fix $n \geq 1$ and compute $d_{n+1}s_n(g_0, \dots, g_n) = d_{n+1}(e, g_0, \dots, g_n)$. Omitting the entry in position 0 gives $(g_0, \dots, g_n)$ with sign $+1$; omitting the entry in position $j \geq 1$, which is g_{j-1}, gives $(e, g_0, \dots, \hat{g}_{j-1}, \dots, g_n)$ with sign $(-1)^j$. Reindexing by $i = j - 1$ and using $(-1)^{i+1} = -(-1)^i$,

$$d_{n+1}s_n(g_0, \dots, g_n) = (g_0, \dots, g_n) - \sum_{i=0}^{n} (-1)^i (e, g_0, \dots, \hat{g}_i, \dots, g_n)$$

The subtracted sum is exactly $s_{n-1}d_n(g_0, \dots, g_n)$, since s_{n-1} prepends e to each term of $d_n(g_0, \dots, g_n) = \sum_i (-1)^i (g_0, \dots, \hat{g}_i, \dots, g_n)$. Hence

$$d_{n+1}s_n + s_{n-1}d_n = \mathrm{id}$$

Step 3: The bottom of the complex. At the augmentation, $\epsilon s_{-1}(1) = \epsilon(e) = 1$, so $\epsilon s_{-1} = \mathrm{id}_{\mathbb{Z}}$. In degree zero,

$$d_1 s_0(g_0) = d_1(e, g_0) = (g_0) - (e), \qquad s_{-1}\epsilon(g_0) = s_{-1}(1) = (e)$$

so $d_1 s_0 + s_{-1}\epsilon = \mathrm{id}$ as well.

Step 4: Conclusion. The augmented complex therefore has its identity morphism null-homotopic as a complex of abelian groups. By Step 1 of the proof of lemma 56.1.28, a complex whose identity is null-homotopic is exact. Hence the standard resolution is exact, completing the proof.

Hence, after taking the contravariant functor $\mathrm{Hom}_{\mathbb{Z}[G]}(-, M)$, we get the cochain complex:

$$0 \to \mathrm{Hom}_{\mathbb{Z}[G]}(\mathbb{Z}[G], M) \to \cdots \to \mathrm{Hom}_{\mathbb{Z}[G^n]}(-, M) \xrightarrow{d_n^*} \mathrm{Hom}_{\mathbb{Z}[G^{n+1}]}(-, M) \to \cdots$$

where d_n^* maps $\varphi \mapsto \varphi \circ d_n$. Similarly, we can take the covariant functor

$$\cdots \to \mathbb{Z}[G^3] \otimes_{\mathbb{Z}[G]} A \xrightarrow{d_{2*}} \mathbb{Z}[G^2] \otimes_{\mathbb{Z}[G]} A \xrightarrow{d_{1*}} \mathbb{Z}[G] \otimes_{\mathbb{Z}[G]} A \to 0$$

where d_{n*} is given by $(g_0, ..., g_n) \otimes a \mapsto d_n(g_0, ..., g_n) \otimes a$, the map ϵ is the augmentation map given by $\sum a_g g \mapsto \sum a_g$, and we view the modules as *right* $\mathbb{Z}[G]$-modules with the action

$$(g_1, ..., g_n) \cdot g = (g_1 g, ..., g_n g)$$

Let us now better understand these hom-sets and relate to the above discussion. Let

Definition 58.1.13: coChain

Let

$$C^n(G,M) = (\mathrm{Hom}_{\mathbf{Set}}(G^n, M), +)$$

with group operation defined on the maps given by point-wise addition. This group is called the *n-cochain group*.

From this, we can define a boundary map:

$$\begin{aligned} d^n &: C^n(G,M) \to C^{n+1}(G,M) \\ d^n(f)(g_0,...,g_n) &= g_0 f(g_1,...,g_n) - f(g_0g_1, g_2, ..., g_n) \\ &\quad + f(g_0, g_1g_2, ..., g_n) - \cdots + (-1)^n f(g_0,...,g_{n-2}, g_{n-1}g_n) + (-1)^{n+1} f(g_0,...,g_{n-1}) \end{aligned}$$

Then $d^{n+1} \circ d^n = 0$, giving us a cochain complex. We can then have:

Definition 58.1.14: Cohomology Group – using Cocycles and Coboundaries

$$H^n(G,M) = \frac{\ker d^n}{\mathrm{im} d^{n-1}} = \frac{Z^n(G,M)}{B^n(G,M)}$$

We sum up many of the results that we have shown before using the new notation:

1. $C^0(G,M) = M$, and $H^0(G,M) \cong M^G$
2. $d^0 : C^0(G,M) \to C^1(G,M)$ is given by $d^0(a)(g) = ga - a$
3. $H^0(G,M) \cong \ker d^0 = M^G$
4. $\mathrm{im} d^0 = \{f : G \to M \mid \exists a \in M \text{ such that } f(g) = ga - a, \ \forall g \in G\}$ (principal crossed homomorphism)
5. $d^1 : C^1(G,M) \to C^2(G,M)$ given by $d^1(f)(g,h) = gf(h) - f(gh) + f(g)$
6. $\ker d^1 = \{f : G \to M \mid f(gh) = f(g) + gf(h)\}$ (crossed homomorphisms)
7. If $0 \to A \to B \to C \to 0$ is exact, we get an exact sequence of cochains for every n:

$$0 \to C^n(G,A) \to C^n(G,B) \to C^n(G,C) \to 0$$

We shall show that the collection of complexes given by the above is isomorphic to those given by the standard resolution

Proposition 58.1.15: Characterizing Hom of Resolution

Let M be a G-module. Then for every $n \geq 0$ there is an isomorphism:

$$\Phi^n : \mathrm{Hom}_{\mathbb{Z}[G]}(\mathbb{Z}[G^{n+1}], M) \xrightarrow{\cong} C^n(G, M)$$

where the map $\varphi : \mathbb{Z}[G^{n+1}] \to M$ goes to $f : G^n \to M$ given by:

$$f(g_1, ..., g_n) = \varphi(1, g_1, g_1g_2, g_1g_2g_3, ..., g_1g_2g_3 \cdots g_n)$$

The isomorphism Φ^n commutes with boundary maps, that is

$$\Phi^{n+1} \circ d^*_{n+1} = d^n \circ \Phi^n$$

Hence the two cochain complexes agree: the one built from the standard resolution and the one built from cocycles and coboundaries are isomorphic, so the two descriptions of $H^n(G, M)$ coincide.

***Proof*:**

Step 1: Φ^n is a bijection. The group G acts diagonally on the basis G^{n+1} of $\mathbb{Z}[G^{n+1}]$, and this action is free, since $g \cdot (h_0, \dots, h_n) = (h_0, \dots, h_n)$ forces $gh_0 = h_0$ and hence $g = e$. Each orbit contains exactly one tuple whose first entry is e, namely $h_0^{-1} \cdot (h_0, \dots, h_n)$. A $\mathbb{Z}[G]$-linear map out of $\mathbb{Z}[G^{n+1}]$ is therefore determined freely and without constraint by its values on the tuples $(e, k_1, \dots, k_n)$, so restriction to those tuples is a bijection onto $\mathrm{Hom}_{\mathbf{Set}}(G^n, M) = C^n(G, M)$.

The substitution in the statement is the reparametrization $k_i = g_1g_2 \cdots g_i$ of that indexing. It is a bijection $G^n \to G^n$, with inverse $g_1 = k_1$ and $g_i = k_{i-1}^{-1}k_i$ for $i \geq 2$. Composing the two bijections gives Φ^n, and it is additive because both steps are, so Φ^n is an isomorphism of abelian groups.

Step 2: Compatibility with the differentials. Let $\varphi \in \mathrm{Hom}_{\mathbb{Z}[G]}(\mathbb{Z}[G^{n+1}], M)$ and set $f = \Phi^n(\varphi)$. Write $h_i = g_1 \cdots g_i$, so that $f(g_1, \dots, g_n) = \varphi(e, h_1, \dots, h_n)$. Applying Φ^{n+1} to $d^*_{n+1}\varphi = \varphi \circ d_{n+1}$ and evaluating at $(g_0, \dots, g_n)$ gives $\varphi\big(d_{n+1}(e, k_1, \dots, k_{n+1})\big)$ where $k_i = g_0g_1 \cdots g_{i-1}$.

Expand d_{n+1} by definition 58.1.11. The term omitting position 0 is $(k_1, \dots, k_{n+1})$; pulling out the common left factor $k_1 = g_0$ by equivariance of φ turns it into $g_0 \cdot \varphi(e, g_0^{-1}k_2, \dots) = g_0 f(g_1, \dots, g_n)$. The term omitting position j for $1 \leq j \leq n$ merges g_{j-1} and g_j, contributing $(-1)^j f(g_0, \dots, g_{j-1}g_j, \dots, g_n)$, and the term omitting the last position drops g_n, contributing $(-1)^{n+1} f(g_0, \dots, g_{n-1})$. Summing,

$$\Phi^{n+1}(d^*_{n+1}\varphi)(g_0, \dots, g_n) = g_0 f(g_1, \dots, g_n) + \sum_{j=1}^{n} (-1)^j f(g_0, \dots, g_{j-1}g_j, \dots, g_n) + (-1)^{n+1} f(g_0, \dots, g_{n-1})$$

which is precisely $d^n(f)(g_0, \dots, g_n)$ as defined above. Hence $\Phi^{n+1} \circ d^*_{n+1} = d^n \circ \Phi^n$.

The maps $\Phi^\bullet$ are therefore isomorphisms commuting with the differentials, that is an isomorphism

of cochain complexes, completing the proof.

Due to the relevance of the standard representation, we have the following definition:

Definition 58.1.16: Induced and Coinduced G-module

Let G be a group and A an abelian group. Then:

$$\mathrm{CoInd}^G(A) = \mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}[G], A)$$

with the G-action defined as $(g\varphi)(z) = \varphi(zg)$ is called the *coinduced G-module* associated to A. Similarly

$$\mathrm{Ind}^G(A) = \mathbb{Z}[G] \otimes_{\mathbb{Z}} A$$

with G-action defined by $g(z \otimes a) = (gz) \otimes a$ is the is the induced G-module associated to A.

A result that is common in many Cohomologies theories is some version of the following:

Lemma 58.1.17: Induced and Coinduced Equivalence

Let G be a finite group and A an abelian group. Then

$$\mathrm{Ind}^G(A) \cong \mathrm{CoInd}^G(A)$$

As a consequence, if $B = \mathrm{Ind}^G(A)$ or $B = \mathrm{CoInd}^G(A)$, then

$$H_0(G, B) \cong H^0(G, B) \cong A$$

and they are both zero for $n \geq 1$.

***Proof*:**

Define the map: $\alpha : \mathrm{CoInd}^G(A) \to \mathrm{Ind}^G(A)$ given by:

$$\varphi \mapsto \sum_{g \in G} g^{-1} \otimes \varphi(g)$$

$$(g^{-1} \mapsto a) \leftarrow\!\shortmid\, g \otimes a$$

with $(g^{-1} \mapsto a)(h) = 0$ for $h \in G \setminus \{g^{-1}\}$. These are certainly inverses, and easily verifiable to be G-module homomorphisms, a technique also used in the proof of Maschke's Theorem (see theorem 53.1.9).

For the last part, write $B = \mathrm{CoInd}^G(A) = \mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}[G], A)$, which the first part identifies with $\mathrm{Ind}^G(A)$. Let $P_\bullet \to \mathbb{Z}$ be a resolution by free $\mathbb{Z}[G]$-modules; each P_i is then also free as an abelian group. The adjunction

$$\mathrm{Hom}_{\mathbb{Z}[G]}\big(M, \mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}[G], A)\big) \cong \mathrm{Hom}_{\mathbb{Z}}(M, A)$$

of theorem 15.3.9, natural in M, turns the complex computing $H^\bullet(G, B)$ into $\mathrm{Hom}_{\mathbb{Z}}(P_\bullet, A)$. Its cohomology is $\mathrm{Ext}^\bullet_{\mathbb{Z}}(\mathbb{Z}, A)$, which is A in degree 0 and vanishes in positive degrees because $\mathbb{Z}$ is projective over $\mathbb{Z}$. Dually $P_\bullet \otimes_{\mathbb{Z}[G]} (\mathbb{Z}[G] \otimes_{\mathbb{Z}} A) \cong P_\bullet \otimes_{\mathbb{Z}} A$ computes $\mathrm{Tor}^{\mathbb{Z}}_\bullet(\mathbb{Z}, A)$, which is A in degree 0 and zero above. So $H^0(G, B) \cong H_0(G, B) \cong A$ and both vanish for $n \geq 1$, as we sought to show.

Proposition 58.1.18: Torsion of H^1

If G has order n and is finite, then every element of $H^1(G,M)$ has order dividing n.

***Proof*:**
By proposition 58.1.15, $H^1(G,M) = Z^1(G,M)/B^1(G,M)$. Let $\delta \in Z^1(G,M)$, so that $\delta(gh) = \delta(g) + g\delta(h)$ for all $g,h \in G$, and put $S = \sum_{h\in G} \delta(h)$. Fix g and sum the cocycle identity over $h \in G$. As $h \mapsto gh$ permutes G, the left side sums to S, so

$$S = n\,\delta(g) + gS$$

that is, $n\,\delta(g) = g(-S) - (-S)$ for every $g \in G$. So $n\delta$ is the coboundary f_{-S} of definition 58.1.10, and n kills the class of δ in $H^1(G,M)$. Hence the order of every class divides n, as claimed.

Proposition 58.1.19: M finitely generated, then H1 finite

Let M be a finitely generated G-module and G finite. Then $H^1(G,M)$ is finite.

***Proof*:**
Let $m_1,\dots,m_r$ generate M as a G-module. Since G is finite, the finitely many elements gm_i generate M as an abelian group, so the group $C^1(G,M)$ of all functions $G \to M$, which is the product of $|G|$ copies of M, is a finitely generated abelian group, a quotient of some $\mathbb{Z}^k$. The preimage in $\mathbb{Z}^k$ of the subgroup $Z^1(G,M)$ is free of finite rank by theorem 14.1.5, as $\mathbb{Z}$ is a PID, so $Z^1(G,M)$ is finitely generated, and so is its quotient $H^1(G,M) = Z^1(G,M)/B^1(G,M)$ (proposition 58.1.15). If s elements generate $H^1(G,M)$, each has order dividing $|G|$ by proposition 58.1.18, so $H^1(G,M)$ has at most $|G|^s$ elements, completing the proof.

Finally, let us prove the foreshadowing in box 20.4.5. Let L/K be a cyclic extension so that $G = \mathrm{Gal}_K(L) \cong \mathbb{Z}/m\mathbb{Z}$. The G acts on $L^\times$ in the natural way, and hence we find it's group cohomology. First:

Lemma 58.1.20: Cocycles using Norm and Trace

Let L/K be a cyclic extension $G = \mathrm{Gal}_K(L) \cong \mathbb{Z}/m\mathbb{Z}$ with generator σ, and $Z^1(G,L^\times)$ the 1-cocycles. Let $U_{L/K} = \left\{ l \in L \;\middle|\; \mathrm{Nm}_{L/K}(l) = 1 \right\}$ (sometimes this is denoted L^1). Then as groups:

$$Z^1(G,L^\times) \cong U_{L/K}$$
$$c \mapsto c(\sigma)$$

Similarly:

$$Z^1(G,L) \cong T_{L/K}$$

where $T_{L/K}$ is the traceless elements[a]

[a] There is less common notation, sometimes it is denoted L^0

***Proof*:**
Let M be $L^\times$ or L, with its group law written additively as in definition 58.1.9, so that the cocycle condition reads $c(gh) = c(g) + g(c(h))$ and the neutral element 0_M is 1 when $M = L^\times$ and 0 when $M = L$. For $\beta \in M$ and $k \geq 0$ put

$$s_k(\beta) = \sum_{i=0}^{k-1} \sigma^i(\beta)$$

with $s_0(\beta) = 0_M$. For $M = L^\times$ and $k \geq 1$, $s_k(\beta)$ is the product $\beta\,\sigma(\beta)\cdots\sigma^{k-1}(\beta)$. Splitting the sum at $i = j$ gives, for all $j, k \geq 0$,

$$s_{j+k}(\beta) = s_j(\beta) + \sigma^j\big(s_k(\beta)\big)$$

The extension L/K is Galois with group $G = \{\sigma^i : 0 \leq i < m\}$, so the norm and the trace are the product and the sum of the conjugates $\sigma^i(\beta)$ [83, Chapter I, Proposition 2.6]: $s_m(\beta)$ is $\mathrm{Nm}_{L/K}(\beta)$ for $M = L^\times$ and $\mathrm{tr}_{L/K}(\beta)$ for $M = L$. As $\mathrm{Nm}_{L/K}(0) = 0$, the set $U_{L/K}$ lies in $L^\times$, so in both cases the claimed target is $\{\beta \in M : s_m(\beta) = 0_M\}$.

Step 1: $c \mapsto c(\sigma)$ is a homomorphism into the target. The group law of $Z^1(G, M)$ is pointwise, so the map is a homomorphism. Let $c \in Z^1(G, M)$ and $\beta = c(\sigma)$. The cocycle condition at $g = h = e$ gives $c(e) = c(e) + c(e)$, so $c(e) = 0_M$. At $g = \sigma$ and $h = \sigma^k$ it gives $c(\sigma^{k+1}) = \beta + \sigma(c(\sigma^k))$, so by induction on k, using the splitting formula with $j = 1$, $c(\sigma^k) = s_k(\beta)$ for every $k \geq 0$. For $k = m$ this reads $s_m(\beta) = c(\sigma^m) = c(e) = 0_M$, so β lies in the target.

Step 2: injectivity. By Step 1, $c(\sigma^k) = s_k(c(\sigma))$ for all k, so c is determined by $c(\sigma)$.

Step 3: surjectivity. Let $\beta \in M$ with $s_m(\beta) = 0_M$. The splitting formula with $k = m$ gives $s_{j+m}(\beta) = s_j(\beta) + \sigma^j(0_M) = s_j(\beta)$, so $s_k(\beta)$ depends only on the class of k modulo m, and $c(\sigma^k) = s_k(\beta)$ defines a function $c\colon G \to M$. For $g = \sigma^j$ and $h = \sigma^k$ with $j, k \geq 0$ the splitting formula reads $c(gh) = c(g) + g(c(h))$, so $c \in Z^1(G, M)$, and $c(\sigma) = s_1(\beta) = \beta$. Hence $c \mapsto c(\sigma)$ is an isomorphism from $Z^1(G, L^\times)$ onto $U_{L/K}$ and from $Z^1(G, L)$ onto $T_{L/K}$, as claimed.

Theorem 58.1.21: Hilbert's 90th Theorem: Cohomology Upgrade

Using the above lemma's notation:

$$H^1(G, L^\times) \cong \{1\}$$

***Proof*:**
By proposition 58.1.15, $H^1(G, L^\times) = Z^1(G, L^\times)/B^1(G, L^\times)$, so it suffices to show that every cocycle c is a coboundary. Written multiplicatively, the coboundaries of definition 58.1.10 are the functions $g \mapsto g(\gamma)/\gamma$ with $\gamma \in L^\times$. By lemma 58.1.20, $\beta = c(\sigma)$ satisfies $\mathrm{Nm}_{L/K}(\beta) = 1$, and a cocycle is determined by its value at σ, so it suffices to find $\gamma \in L^\times$ with $\beta = \sigma(\gamma)/\gamma$.

Put $s_0 = 1$ and $s_k = \beta\,\sigma(\beta)\cdots\sigma^{k-1}(\beta)$ for $k \geq 1$, so that $s_{k+1} = \beta\,\sigma(s_k)$ and, as in the proof of

lemma 58.1.20, $s_m = \mathrm{Nm}_{L/K}(\beta) = 1$. The automorphisms $\sigma^0, \dots, \sigma^{m-1}$ of L are distinct, hence linearly independent over L (corollary 20.1.40), and the coefficients $s_0, \dots, s_{m-1}$ are nonzero, so some $\theta \in L$ gives

$$\alpha = \sum_{k=0}^{m-1} s_k \, \sigma^k(\theta) \neq 0$$

Applying σ and multiplying by β,

$$\beta \, \sigma(\alpha) = \sum_{k=0}^{m-1} \beta \, \sigma(s_k) \, \sigma^{k+1}(\theta) = \sum_{k=1}^{m} s_k \, \sigma^k(\theta) = \alpha - \theta + s_m \, \sigma^m(\theta) = \alpha$$

because $s_m = 1$ and $\sigma^m = \mathrm{id}$. So $\beta = \alpha/\sigma(\alpha) = \sigma(\gamma)/\gamma$ with $\gamma = \alpha^{-1}$, and c is the coboundary of γ, completing the proof.

Note this theorem generalizes to arbitrary finite Galois extensions; see [26]. This result should now make intuitive sense: the elements of K are *exactly* the $\mathrm{Gal}_K(L)$-invariant element. Note that if there were more complicated groups instead of $L^\times$, there can be more interesting cohomology groups, see [26] for more details.

Exercise 58.1.1

1. Let A, B be any G-modules. Show that $H^n(G, A \oplus B) \cong H^n(G, A) \oplus H^n(G, B)$
2. Show that $H^0(G, \mathrm{CoInd}^G(A)) \cong A$ and $H^n(G, \mathrm{CoInd}^G(A)) \cong 0$ for all $n \geq 1$ (hint: consider $\zeta : \mathrm{Hom}_{\mathbb{Z}[G]}(\mathbb{Z}[G^n], \mathrm{CoInd}^G(A)) \to \mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}[G^n], A)$ given by $\varphi \mapsto (z \mapsto \varphi(z)(1))$. What is the inverse of this map?)
3. Show that $H_0(G, \mathrm{Ind}^G(A)) \cong A$ and $H_n(G, \mathrm{Ind}^G(A)) \cong 0$ for all $n \geq 1$.

58.2 Homological Dimension

We now turn to measuring the "complexity" of modules and rings using the length of their resolutions. Before defining these measures rigorously, it is worth stepping back to 1890 to understand why mathematicians began counting the length of resolutions in the first place.

Historical Motivation: Invariant Theory

In the late 19th century, algebra was dominated by *Invariant Theory*. Imagine a group G acting on a polynomial ring $S = \mathbb{C}[x_1, \dots, x_n]$ (for example, by linear substitutions of variables). Mathematicians were looking for *invariant ring* S^G:

$$S^G = \{f \in S \big| g \cdot f = f \text{ for all } g \in G\}$$

The central question was if S^G finitely generated? Can we find a finite set of basic invariant polynomials $f_1, \dots, f_m$ such that every other invariant is just a polynomial combination of these?

Hilbert showed we can map a polynomial ring onto the invariants:

$$\varphi : \mathbb{C}[y_1, \dots, y_m] \twoheadrightarrow S^G \qquad y_i \mapsto f_i$$

and then the kernel $I = \ker(\varphi)$ represents the *relations* between the invariants. Hence, the study of invariants reduced to the study of the kernel. To find these invariants, 19th-century computationalists (like Paul Gordan) asked tried computing them and found the following problem:

1. **First Syzygies:** The ideal I describes the relations. By the Basis Theorem, I is finitely generated.
2. **Second Syzygies:** Are these relations independent? Or are there "relations between the relations"? If we have a relation $Ar_1 + Br_2 = 0$, that is a second syzygy.
3. **Higher Syzygies:** We can keep going. We can form a module of second syzygies and ask for its generators, then ask for the relations between *those* generators.

Mathematicians feared this chain of relations might continue forever, becoming infinitely complex. Hilbert's *Syzygy Theorem* proved that if you are working with a polynomial ring in n variables, this process *must stop*. Specifically, after at most n steps, the module of relations becomes free—there are no more "hidden" relations.

This was part of David Hilbert's seminal paper laying the foundation of commutative geometry. In particular, he proved three theorems: The *Basis Theorem*, the *Nullstellensatz*, and the *Syzygy Theorem*.

58.2.1 Etymology The word *Syzygy* comes from the Greek *syzygia*, meaning "yoked together". In astronomy, it refers to the alignment of three celestial bodies (like the Sun, Earth, and Moon). In algebra, it refers to a relation that "yokes" generators together to zero.

58.2.1 Projective and Global Dimension

We can now formalize Hilbert's discovery using the language of resolutions.

Definition 58.2.2: Projective Dimension

Let M be an R-module. The *projective dimension* of M, denoted $\mathrm{pd}_R(M)$, is the minimal length n of a projective resolution of M:

$$0 \to P_n \to \cdots \to P_1 \to P_0 \to M \to 0$$

If no finite resolution exists, we say $\mathrm{pd}_R(M) = \infty$.

Definition 58.2.3: Global Dimension

The *global dimension* of a ring R, denoted $\mathrm{gldim}(R)$, is the supremum of the projective dimensions of all R-modules:

$$\mathrm{gldim}(R) = \sup\{\mathrm{pd}_R(M) \,|\, M \in R\text{-}\mathbf{Mod}\}$$

Lemma 58.2.4: Detecting Projective Dimension with Ext

Let R be a ring, M an R-module and $m \geq 0$ an integer. The following are equivalent:

1. $\mathrm{pd}_R(M) \leq m$
2. $\mathrm{Ext}^i_R(M, N) = 0$ for all R-modules N and all $i > m$.
3. $\mathrm{Ext}^{m+1}_R(M, N) = 0$ for all R-modules N.

***Proof*:**

For a projective resolution $\cdots \to P_1 \to P_0 \to M \to 0$, theorem 56.5.8 computes $\mathrm{Ext}^i_R(M, N)$ as $H^i(\mathrm{Hom}_R(P_\bullet, N))$, where the cochain complex $\mathrm{Hom}_R(P_\bullet, N)$ has $\mathrm{Hom}_R(P_i, N)$ in degree i.

Step 1: (1) implies (2), and (2) implies (3). If $\mathrm{pd}_R(M) \leq m$, then definition 58.2.2 gives a projective resolution of M with $P_i = 0$ for every $i > m$. For $i > m$ the group $\mathrm{Hom}_R(P_i, N)$ is zero, and so is its cohomology $\mathrm{Ext}^i_R(M, N)$. Condition (3) is the case $i = m + 1$ of (2).

Step 2: Dimension shifting. Fix a projective resolution

$$\cdots \to P_2 \xrightarrow{d_2} P_1 \xrightarrow{d_1} P_0 \xrightarrow{d_0} M \to 0$$

of M, which exists by example 56.2.2(4). Put $K_j = \mathrm{im}(d_j)$ for $j \geq 0$. Then $K_0 = M$, and $K_j = \ker(d_{j-1})$ for $j \geq 1$ by exactness. Let $\pi\colon P_m \to K_m$ be the map d_m with codomain K_m. The complex

$$\cdots \to P_{m+2} \xrightarrow{d_{m+2}} P_{m+1} \xrightarrow{d_{m+1}} P_m \xrightarrow{\pi} K_m \to 0$$

is exact: π is onto, $\ker(\pi) = \ker(d_m) = \mathrm{im}(d_{m+1})$, and exactness at the remaining terms is that of the resolution of M. So $Q_j = P_{m+j}$ is a projective resolution of K_m. For $j \geq 1$ the cohomology of $\mathrm{Hom}_R(Q_\bullet, N)$ in degree j is computed from

$$\mathrm{Hom}_R(P_{m+j-1}, N) \xrightarrow{d^*_{m+j}} \mathrm{Hom}_R(P_{m+j}, N) \xrightarrow{d^*_{m+j+1}} \mathrm{Hom}_R(P_{m+j+1}, N)$$

and the same two maps compute the cohomology of $\mathrm{Hom}_R(P_\bullet, N)$ in degree $m + j$. By theorem 56.5.8, applied to both resolutions,

$$\mathrm{Ext}^j_R(K_m, N) \cong \mathrm{Ext}^{m+j}_R(M, N) \qquad (j \geq 1)$$

Step 3: A module K with $\mathrm{Ext}^1_R(K, N) = 0$ for every R-module N is projective. By example 56.2.2(4), K has a resolution

$$\cdots \to F_2 \xrightarrow{e_2} F_1 \xrightarrow{e_1} F_0 \xrightarrow{e_0} K \to 0$$

by free modules, and free modules are projective (corollary 17.2.6). Let $L = \ker(e_0)$, with inclusion $\iota\colon L \to F_0$, and let $q\colon F_1 \to L$ be the map e_1 with codomain $\mathrm{im}(e_1) = L$, so that $e_1 = \iota \circ q$ and q is onto. Since $\iota \circ q \circ e_2 = e_1 \circ e_2 = 0$ and ι is injective, $q \circ e_2 = 0$, so q is a cocycle of degree 1 in $\mathrm{Hom}_R(F_\bullet, L)$. The cohomology of that complex in degree 1 is $\mathrm{Ext}^1_R(K, L) = 0$ (theorem 56.5.8), so q is a coboundary: $q = g \circ e_1$ for some $g\colon F_0 \to L$. Then $(g \circ \iota) \circ q = g \circ e_1 = q$, and as q is onto, $g \circ \iota = \mathrm{id}_L$.

Every $p \in F_0$ equals $\iota(g(p)) + \big(p - \iota(g(p))\big)$, and the second summand lies in $\ker(g)$. Also

$\iota(L) \cap \ker(g) = 0$, because $g \circ \iota = \mathrm{id}_L$. So $F_0 = \iota(L) \oplus \ker(g)$. The restriction of e_0 to $\ker(g)$ is injective, since $\ker(e_0) \cap \ker(g) = \iota(L) \cap \ker(g) = 0$, and it is onto K, since e_0 is onto and vanishes on $\iota(L)$. Hence $K \cong \ker(g)$ is isomorphic to a direct summand of the free module F_0, and K is projective by theorem 17.2.4.

Step 4: (3) implies (1). Take the resolution and the modules K_j of Step 2. By (3) and Step 2, $\mathrm{Ext}^1_R(K_m, N) \cong \mathrm{Ext}^{m+1}_R(M, N) = 0$ for every R-module N, so K_m is projective by Step 3. If $m = 0$, then $M = K_0$ is projective, and $0 \to M \xrightarrow{\mathrm{id}} M \to 0$ is a projective resolution of length 0. If $m \geq 1$, then $K_m = \ker(d_{m-1})$, and

$$0 \to K_m \to P_{m-1} \to \cdots \to P_1 \to P_0 \to M \to 0$$

is exact, a projective resolution of length m. In both cases $\mathrm{pd}_R(M) \leq m$ by definition 58.2.2, completing the proof.

Theorem 58.2.5: Global Dimension of Polynomial Rings

Let R be a nonzero commutative ring. Then

$$\mathrm{gldim}(R[x]) = \mathrm{gldim}(R) + 1$$

***Proof*:**
Step 1: The characteristic exact sequence. Let M be any $R[x]$-module. Restricting scalars makes M an R-module, and $R[x] \otimes_R M$ is an $R[x]$-module.

Define a sequence of $R[x]$-modules:

$$0 \to R[x] \otimes_R M \xrightarrow{\alpha} R[x] \otimes_R M \xrightarrow{\beta} M \to 0$$

where the maps are defined by:

- $\alpha(f(x) \otimes m) = xf(x) \otimes m - f(x) \otimes xm$
- $\beta(f(x) \otimes m) = f(x)m$

Both formulas are R-bilinear in $(f(x), m)$, because x acts R-linearly on M, so they define maps on $R[x] \otimes_R M$, and both maps are $R[x]$-linear.

- *Surjectivity of β:* For any $m \in M$, $\beta(1 \otimes m) = m$, so β is surjective.
- *Exactness at the middle:* The elements $1 \otimes m$ generate $R[x] \otimes_R M$ as an $R[x]$-module and $\beta \circ \alpha$ is $R[x]$-linear, so the computation $\beta(\alpha(1 \otimes m)) = \beta(x \otimes m - 1 \otimes xm) = xm - xm = 0$ gives $\mathrm{im}(\alpha) \subseteq \ker(\beta)$. Conversely, any element in $R[x] \otimes_R M$ can be written as $\sum_{i=0}^{d} x^i \otimes m_i$. If it lies in $\ker(\beta)$, then $\sum_{i=0}^{d} x^i m_i = 0$. We can rewrite our original element as:

  $$\sum_{i=0}^{d} x^i \otimes m_i = \sum_{i=0}^{d} (x^i \otimes m_i - 1 \otimes x^i m_i)$$

  Since $x^i \otimes m - 1 \otimes x^i m = \alpha\left(\sum_{j=0}^{i-1} x^{i-1-j} \otimes x^j m\right)$ for every $m \in M$, the element is in the image of α.

- *Injectivity of α:* Suppose $\sum_{i=0}^{d} x^i \otimes m_i \in \ker(\alpha)$. Then:

$$\sum_{i=0}^{d} x^{i+1} \otimes m_i - \sum_{i=0}^{d} x^i \otimes x m_i = 0$$

  Because $R[x]$ is free over R, we can compare the coefficients of $x^k \otimes -$ degree by degree. For degree 0, we have $-1 \otimes x m_0 = 0 \implies x m_0 = 0$. For degree $k > 0$, we have $m_{k-1} - x m_k = 0 \implies m_{k-1} = x m_k$. For degree $d+1$, we have $m_d = 0$. Working backward from $m_d = 0$, we get $m_{d-1} = x m_d = 0$, and by induction, $m_i = 0$ for all i. Hence, α is injective.

Step 2: Extending scalars along $R \to R[x]$. Let M be an R-module and $P_\bullet \to M$ a projective resolution over R. Because $R[x]$ is free over R, it is flat (corollary 17.5.5), so tensoring the resolution with $R[x]$ preserves exactness. Each $R[x] \otimes_R P_i$ is a projective $R[x]$-module by theorem 17.2.4: if $P_i \oplus Q \cong R^{(I)}$ for an R-module Q and a set I, then $(R[x] \otimes_R P_i) \oplus (R[x] \otimes_R Q) \cong R[x]^{(I)}$, because $R[x] \otimes_R -$ commutes with direct sums (theorem 15.2.4) and carries $R^{(I)}$ to $R[x]^{(I)}$ (example 15.3.3). Therefore $R[x] \otimes_R P_\bullet$ is a projective resolution of $R[x] \otimes_R M$ over $R[x]$. Taking $P_\bullet$ of length $\mathrm{pd}_R(M)$ when that is finite gives

$$\mathrm{pd}_{R[x]}(R[x] \otimes_R M) \leq \mathrm{pd}_R(M)$$

Let N be an $R[x]$-module. Regard $\mathrm{Hom}_{R[x]}(-, N)$ as a functor on the opposite category of $R[x]$-modules. Its right derived functors, computed from projective resolutions as in example 56.3.6, are the functors $\mathrm{Ext}^i_{R[x]}(-, N)$ by theorem 56.5.8, and the opposite category has enough injectives, because $R[x]$-modules have projective resolutions (example 56.2.2(4)). For an $R[x]$-module M, corollary 56.3.12 therefore turns the sequence of Step 1, regarded as a short exact sequence in the opposite category, into the long exact sequence

$$\cdots \to \mathrm{Ext}^i_{R[x]}(R[x] \otimes_R M, N) \xrightarrow{\alpha^*} \mathrm{Ext}^i_{R[x]}(R[x] \otimes_R M, N) \to \mathrm{Ext}^{i+1}_{R[x]}(M, N)$$
$$\to \mathrm{Ext}^{i+1}_{R[x]}(R[x] \otimes_R M, N) \xrightarrow{\alpha^*} \mathrm{Ext}^{i+1}_{R[x]}(R[x] \otimes_R M, N) \to \cdots$$

in which α^* is the map induced by α.

Step 3: The upper bound $\mathit{gldim}(R[x]) \leq \mathit{gldim}(R) + 1$. If $\mathrm{gldim}(R) = \infty$, the right-hand side is infinite. Otherwise put $n = \mathrm{gldim}(R)$, and let M be an $R[x]$-module. As an R-module, M has $\mathrm{pd}_R(M) \leq n$ by definition 58.2.3, so $\mathrm{pd}_{R[x]}(R[x] \otimes_R M) \leq n$ by Step 2, and by lemma 58.2.4 the groups $\mathrm{Ext}^i_{R[x]}(R[x] \otimes_R M, N)$ vanish for every $R[x]$-module N and every $i \geq n+1$. In the long exact sequence of Step 2 with $i = n+1$, the terms on either side of $\mathrm{Ext}^{n+2}_{R[x]}(M, N)$ are therefore zero, and exactness reads

$$0 \to \mathrm{Ext}^{n+2}_{R[x]}(M, N) \to 0$$

So $\mathrm{Ext}^{n+2}_{R[x]}(M, N) = 0$ for every $R[x]$-module N, and lemma 58.2.4 gives $\mathrm{pd}_{R[x]}(M) \leq n+1$. Because this holds for all $R[x]$-modules, $\mathrm{gldim}(R[x]) \leq n+1$.

Step 4: Let M and K be R-modules, regarded as $R[x]$-modules on which x acts as 0. If $\mathrm{Ext}^i_R(M, K) \neq 0$ for some $i \geq 0$, then $\mathrm{Ext}^{i+1}_{R[x]}(M, K) \neq 0$. Choose a projective resolution $P_\bullet \to M$ over R. By Step 2, $R[x] \otimes_R P_\bullet$ is a projective resolution of $R[x] \otimes_R M$ over $R[x]$. Restriction along $p \mapsto 1 \otimes p$ gives isomorphisms

$$\mathrm{Hom}_{R[x]}(R[x] \otimes_R P_j, K) \cong \mathrm{Hom}_R(P_j, K)$$

by corollary 15.3.5, and they commute with the differentials, since $(1 \otimes d)(1 \otimes p) = 1 \otimes d(p)$. Taking cohomology, theorem 56.5.8 on both sides gives

$$\mathrm{Ext}^i_{R[x]}(R[x] \otimes_R M, K) \cong \mathrm{Ext}^i_R(M, K) \quad \text{for all } i \geq 0$$

Since $xM = 0$, the map α of Step 1 is $\alpha(f(x) \otimes m) = xf(x) \otimes m$, which is multiplication by x on $R[x] \otimes_R M$. Write μ for multiplication by x on each $R[x] \otimes_R P_j$. It commutes with the $R[x]$-linear differentials and augmentation, so it is a morphism of resolutions lifting α. By proposition 56.2.15 every lift of α is homotopic to μ, and homotopic morphisms induce the same map after applying $\mathrm{Hom}_{R[x]}(-, K)$ and taking cohomology (lemma 56.1.34, proposition 56.1.31). So α^* on $\mathrm{Ext}^i_{R[x]}(R[x] \otimes_R M, K)$ is induced by the cochain map $\psi \mapsto \psi \circ \mu$ on $\mathrm{Hom}_{R[x]}(R[x] \otimes_R P_\bullet, K)$. That cochain map is zero: $(\psi \circ \mu)(z) = \psi(xz) = x\psi(z) = 0$ for every z, because ψ is $R[x]$-linear and $xK = 0$. Hence $\alpha^* = 0$ in every degree.

The long exact sequence of Step 2 with $N = K$ therefore breaks into short exact sequences, one for each $i \geq 0$, which read

$$0 \to \mathrm{Ext}^i_R(M, K) \to \mathrm{Ext}^{i+1}_{R[x]}(M, K) \to \mathrm{Ext}^{i+1}_R(M, K) \to 0$$

after the isomorphism above. The injection on the left gives the claim.

Step 5: The lower bound gldim$(R[x]) \geq$ gldim$(R)+1$. Let $m \geq 0$ be an integer with $m \leq \mathrm{gldim}(R)$. Some R-modules M and K satisfy $\mathrm{Ext}^m_R(M, K) \neq 0$. For $m = 0$ take $M = K = R$: computing with the projective resolution $0 \to R \xrightarrow{\mathrm{id}} R \to 0$, theorem 56.5.8 gives $\mathrm{Ext}^0_R(R, R) \cong \mathrm{Hom}_R(R, R)$, which contains $\mathrm{id}_R \neq 0$ because $R \neq 0$. For $m \geq 1$, $\mathrm{gldim}(R) > m - 1$, so by definition 58.2.3 some R-module M has $\mathrm{pd}_R(M) > m - 1$, and lemma 58.2.4, applied with $m - 1$ in place of m, gives an R-module K with $\mathrm{Ext}^m_R(M, K) \neq 0$.

Regard M and K as $R[x]$-modules on which x acts as 0. By Step 4, $\mathrm{Ext}^{m+1}_{R[x]}(M, K) \neq 0$, so $\mathrm{pd}_{R[x]}(M) > m$ by lemma 58.2.4, and $\mathrm{gldim}(R[x]) \geq m + 1$. If $\mathrm{gldim}(R) = n$ is finite, the case $m = n$ gives $\mathrm{gldim}(R[x]) \geq n + 1$. If $\mathrm{gldim}(R) = \infty$, every $m \geq 0$ is allowed, and $\mathrm{gldim}(R[x]) = \infty$.

Combining the upper and lower bounds gives $\mathrm{gldim}(R[x]) = \mathrm{gldim}(R) + 1$, completing the proof.

Hilbert's theorem is effectively the calculation of the global dimension of polynomial rings.

Theorem 58.2.6: Hilbert's Syzygy Theorem

Let k be a field and $R = k[x_1, \ldots, x_n]$ be the polynomial ring in n variables. Then every finitely generated R-module has finite projective dimension, and:

$$\mathrm{gldim}(R) = n$$

***Proof*:**
For $n = 0$, $R = k$ is a field, over which every module is free, so $\mathrm{gldim}(k) = 0$. For $n \geq 1$, write $R = S[x_n]$ with $S = k[x_1, \ldots, x_{n-1}]$. By induction on n, $\mathrm{gldim}(S) = n - 1$, and theorem 58.2.5, applied to the nonzero ring S, gives $\mathrm{gldim}(R) = \mathrm{gldim}(S) + 1 = n$. By definition 58.2.3, every R-module, finitely generated or not, therefore has projective dimension at most n.

The residue field $k \cong R/(x_1, \dots, x_n)$ attains this bound. Let V be a k-vector space of dimension n with basis $e_1, \dots, e_n$. The *Koszul complex* of $x_1, \dots, x_n$ is $\bigwedge^\bullet V \otimes_k R$, augmented to k:

$$0 \to \bigwedge^n V \otimes R \xrightarrow{d_n} \dots \xrightarrow{d_2} \bigwedge^1 V \otimes R \xrightarrow{d_1} R \xrightarrow{\epsilon} k \to 0$$

where d_i sends $e_{j_1} \wedge \cdots \wedge e_{j_i} \otimes 1$ to $\sum_{s=1}^{i} (-1)^{s+1} x_{j_s}\, e_{j_1} \wedge \cdots \wedge \widehat{e_{j_s}} \wedge \cdots \wedge e_{j_i} \otimes 1$, so that $d_1(e_i \otimes 1) = x_i$. Because the variables $x_1, \dots, x_n$ form a regular sequence, this complex is exact (example 16.5.6), so it is a free resolution of k of length n and $\mathrm{pd}_R(k) \leq n$. For the reverse inequality, compute $\mathrm{Tor}_n^R(k,k)$ with this resolution. Every d_i has its matrix entries in $(x_1, \dots, x_n)$, so after applying $- \otimes_R k$ every differential vanishes, and $\mathrm{Tor}_n^R(k,k) \cong \bigwedge^n V \cong k \neq 0$. A projective resolution of k of length at most $n-1$ would compute $\mathrm{Tor}_n^R(k,k) = 0$, so $\mathrm{pd}_R(k) = n$, completing the proof.

This theorem has implications beyond just counting relations:

1. *Degree of the Hilbert Polynomial:* Hilbert originally used this theorem to prove that the Hilbert Function $H_M(t) = \dim_k(M_t)$ of a graded module eventually becomes a polynomial. The finite resolution allows us to calculate $H_M(t)$ as an alternating sum of the Hilbert functions of free modules, which are essentially binomial coefficients $\binom{t+k}{k}$.
2. *Structure of Projective Modules:* A celebrated problem posed by Serre (related to this theorem) asked if every projective module over $k[x_1, \dots, x_n]$ is free. This is the algebraic analogue of "vector bundles over affine space are trivial". This was solved affirmatively in 1976 (the *Quillen-Suslin Theorem*). This implies that over polynomial rings, "projective resolution" and "free resolution" are synonymous.

58.2.2 Dimension of Local Rings

Computing the global dimension for general rings seems daunting, as one must check *every* module. However, we can simplify this task using derived functors.

Proposition 58.2.7: Detecting Projective Dimension with Tor

Let R be a ring, M a right R-module and $n \geq 0$ an integer, and consider the conditions

1. $\mathrm{pd}_R(M) \leq n$
2. $\mathrm{Tor}_i^R(M, N) = 0$ for all left R-modules N and all $i > n$.
3. $\mathrm{Tor}_{n+1}^R(M, N) = 0$ for all left R-modules N.

Then (1) implies (2), and (2) implies (3). If R is commutative and Noetherian and M is finitely generated, then (3) implies (1), so the three conditions are equivalent.

***Proof*:**

For a projective resolution $\cdots \to P_1 \to P_0 \to M \to 0$, theorem 56.5.8 computes $\mathrm{Tor}_i^R(M, N)$ as $H_i(P_\bullet \otimes_R N)$, the homology at the term $P_i \otimes_R N$.

Step 1: (1) implies (2), and (2) implies (3). If $\operatorname{pd}_R(M) \leq n$, then definition 58.2.2 gives a projective resolution of M with $P_i = 0$ for every $i > n$. For $i > n$ the module $P_i \otimes_R N$ is zero, and so is $\operatorname{Tor}_i^R(M, N)$. Condition (3) is the case $i = n + 1$ of (2).

Step 2: A resolution by finitely generated free modules. From here on R is commutative and Noetherian, M is finitely generated, and (3) holds. Then M has a projective resolution

$$\cdots \to P_2 \xrightarrow{d_2} P_1 \xrightarrow{d_1} P_0 \xrightarrow{d_0} M \to 0$$

in which every P_j is a finitely generated free module. To build it, write M as a quotient of a finitely generated free module P_0. Every submodule of a finitely generated module over the Noetherian ring R is finitely generated [7, Props. 6.2 and 6.5], so $\ker(d_0)$ is a quotient of a finitely generated free module P_1. The same argument applied to $\ker(d_j)$ produces P_{j+1} and d_{j+1} for every $j \geq 1$.

Step 3: Dimension shifting. Put $K_n = \operatorname{im}(d_n)$, and let $\pi\colon P_n \to K_n$ be the map d_n with codomain K_n. The complex

$$\cdots \to P_{n+2} \xrightarrow{d_{n+2}} P_{n+1} \xrightarrow{d_{n+1}} P_n \xrightarrow{\pi} K_n \to 0$$

is exact: π is onto, $\ker(\pi) = \ker(d_n) = \operatorname{im}(d_{n+1})$, and exactness at the remaining terms is that of the resolution of M. So $Q_j = P_{n+j}$ is a projective resolution of K_n. For $j \geq 1$ the homology of $Q_\bullet \otimes_R N$ at $Q_j \otimes_R N$ is computed from

$$P_{n+j+1} \otimes_R N \xrightarrow{d_{n+j+1} \otimes 1} P_{n+j} \otimes_R N \xrightarrow{d_{n+j} \otimes 1} P_{n+j-1} \otimes_R N$$

and the same two maps compute the homology of $P_\bullet \otimes_R N$ at $P_{n+j} \otimes_R N$. By theorem 56.5.8, applied to both resolutions, and by (3),

$$\operatorname{Tor}_1^R(K_n, N) \cong \operatorname{Tor}_{n+1}^R(M, N) = 0$$

for every R-module N.

Step 4: K_n is flat. Let $\psi\colon N' \to N$ be an injective homomorphism of R-modules with cokernel N'', and put $T = K_n \otimes_R -$. Since R-modules have projective resolutions (example 56.2.2(4)), theorem 56.3.11 applies to T and to the short exact sequence $0 \to N' \to N \to N'' \to 0$, and gives an exact sequence

$$L_1T(N'') \to L_0T(N') \xrightarrow{L_0T(\psi)} L_0T(N)$$

By definition 56.3.5, $L_1T(N'')$ is $H_1(K_n \otimes_R P''_\bullet)$ for a projective resolution $P''_\bullet$ of N'', which is $\operatorname{Tor}_1^R(K_n, N'') = 0$ by theorem 56.5.8 and Step 3. So $L_0T(\psi)$ is injective. The functor T is right exact (theorem 17.5.1), so L_0T is naturally isomorphic to T by proposition 56.3.13, and $T(\psi) = 1 \otimes \psi$ is injective as well. As ψ was an arbitrary injection, K_n is flat (proposition 17.5.3).

Step 5: (3) implies (1). The exact sequence $P_{n+1} \to P_n \to K_n \to 0$ of Step 3, with P_{n+1} and P_n finitely generated free, shows that K_n is finitely presented. A finitely presented flat module is projective [101, Thm. 3.2.7], so K_n is projective by Step 4. If $n = 0$, then $M = K_0$ is projective and $\operatorname{pd}_R(M) = 0$. If $n \geq 1$, then $K_n = \ker(d_{n-1})$, and

$$0 \to K_n \to P_{n-1} \to \cdots \to P_1 \to P_0 \to M \to 0$$

is a projective resolution of length n. In both cases $\operatorname{pd}_R(M) \leq n$ by definition 58.2.2, completing the proof.

Without the hypotheses on R and M, (3) does not imply (1). The $\mathbb{Z}$-module $\mathbb{Q}$ is torsion-free, hence flat (theorem 17.5.7), so the exact functor $\mathbb{Q}\otimes_{\mathbb{Z}} -$ keeps a projective resolution $P_\bullet \to N$ of any abelian group N exact, and $\operatorname{Tor}_1^{\mathbb{Z}}(\mathbb{Q}, N) \cong H_1(\mathbb{Q}\otimes_{\mathbb{Z}} P_\bullet) = 0$ by theorem 56.5.8. This is (3) for $n = 0$. Yet $\mathbb{Q}$ is not projective: over the principal ideal domain $\mathbb{Z}$ projective modules are free (proposition 17.2.11), every element of $\mathbb{Q}$ is twice an element of $\mathbb{Q}$, and a basis element e of a nonzero free abelian group is not twice any element, since the coefficient of e in $2v$ is even. The ring $\mathbb{Z}$ is Noetherian, so finite generation of M is the hypothesis that fails.

It is more common that we consider rings that already have certain properties and verify how these conditions affect the global dimension. For example, given a local ring, the work is significantly reduced. In the local case, we can verify condition (3) by checking a *single* module: the residue field.

Lemma 58.2.8: Projective Dimension over Local Rings

Let $(R, \mathfrak{m}, k)$ be a local Noetherian ring and M a finitely generated R-module. Then:

$$\operatorname{pd}_R(M) \leq n \iff \operatorname{Tor}_{n+1}^R(M, k) = 0$$

Consequently, $\operatorname{pd}_R(M)$ is the smallest n such that $\operatorname{Tor}_i^R(M, k) = 0$ for all $i > n$.

***Proof*:**
The forward direction is immediate from proposition 58.2.7. For the converse, let $\cdots \to P_1 \to P_0 \to M \to 0$ be a *minimal* free resolution, meaning that every P_i is free of finite rank β_i and the matrices of the maps $P_{i+1} \to P_i$ have entries in $\mathfrak{m}$.

Such a resolution exists. Choose $m_1, \ldots, m_\beta \in M$ whose images form a k-basis of $M/\mathfrak{m}M$. They generate M by lemma 23.4.29, so $e_i \mapsto m_i$ defines a surjection $R^\beta \to M$. Its kernel lies in $\mathfrak{m}R^\beta$, since a relation $\sum_i a_i m_i = 0$ reduces modulo $\mathfrak{m}$ to a relation among the basis vectors of $M/\mathfrak{m}M$, which forces every a_i into $\mathfrak{m}$. As a submodule of a finitely generated module over the Noetherian ring R, the kernel is finitely generated [7, Props. 6.2 and 6.5], so the same construction applies to it in place of M. Continuing in this way produces a free resolution in which the image of each map $P_{i+1} \to P_i$ is the kernel of $P_i \to P_{i-1}$ (of $P_0 \to M$ when $i = 0$), which lies in $\mathfrak{m}P_i$. So every matrix entry lies in $\mathfrak{m}$.

The differentials in the complex $P_\bullet \otimes_R k$ are therefore all zero maps, and by theorem 56.5.8

$$\operatorname{Tor}_i^R(M, k) \cong H_i(P_\bullet \otimes k) \cong P_i \otimes k \cong k^{\beta_i}$$

If $\operatorname{Tor}_{n+1}^R(M, k) = 0$, then $k^{\beta_{n+1}} = 0$, so $\beta_{n+1} = 0$ and $P_{n+1} = 0$. The map $P_n \to P_{n-1}$ (the map $P_0 \to M$ when $n = 0$) then has kernel equal to the image of $P_{n+1} = 0$, so $0 \to P_n \to \cdots \to P_0 \to M \to 0$ is a projective resolution of length n, and $\operatorname{pd}_R(M) \leq n$ by definition 58.2.2. For the consequence, the forward direction applied with $i - 1$ in place of n gives $\operatorname{Tor}_i^R(M, k) = 0$ for every $i > \operatorname{pd}_R(M)$, and if $\operatorname{Tor}_i^R(M, k) = 0$ for all $i > n$, then the converse, applied to $\operatorname{Tor}_{n+1}^R(M, k) = 0$, gives $\operatorname{pd}_R(M) \leq n$.

A regular local ring of dimension m has its maximal ideal generated by m elements. These elements cut the ring down one dimension at a time without meeting a zero-divisor, and that is what makes the Koszul complex on them a resolution of the residue field.

Definition 58.2.9: Regular Sequence

Let R be a ring and M an R-module. A sequence of elements $x_1, \dots, x_n \in R$ is called an *M-regular sequence* if:

1. $(x_1, \dots, x_n)M \neq M$
2. For $i = 1, \dots, n$, the element x_i is not a zero-divisor on the quotient module $M/(x_1, \dots, x_{i-1})M$.

Lemma 58.2.10: The Maximal Ideal of a Regular Local Ring Is Generated by a Regular Sequence

Let $(R, \mathfrak{m})$ be a Noetherian regular local ring of dimension m, and let $x_1, \dots, x_m$ generate $\mathfrak{m}$. Then $x_1, \dots, x_m$ is an R-regular sequence.

***Proof*:**
Induct on m. For $m = 0$ the sequence is empty. For $m > 0$, a regular local ring is a domain ([20, A Regular Local Ring Is a Domain]), and $x_1 \neq 0$: regularity makes $\dim_k \mathfrak{m}/\mathfrak{m}^2 = m$, where $k = R/\mathfrak{m}$, so an m-element generating set of $\mathfrak{m}$ is minimal and none of its members can vanish. Hence x_1 is a nonzerodivisor, and $\dim R/(x_1) = m - 1$ by [20, One Equation Cuts Dimension by One], applicable because R is local. The maximal ideal of $R/(x_1)$ is generated by the $m - 1$ images of $x_2, \dots, x_m$, so $R/(x_1)$ is regular local of dimension $m - 1$, and by induction those images form an $R/(x_1)$-regular sequence. Since $(x_1, \dots, x_m) = \mathfrak{m} \neq R$, prefixing x_1 gives an R-regular sequence, completing the proof.

This leads to the fundamental equality attributed to Auslander, Buchsbaum, and Serre, which connects the homological algebra back to the geometry of the ring.

Theorem 58.2.11: Auslander-Buchsbaum-Serre Theorem

Let $(R, \mathfrak{m}, k)$ be a local Noetherian ring. Then the global dimension is determined by the residue field:

$$\operatorname{gldim}(R) = \operatorname{pd}_R(k)$$

Furthermore, $\operatorname{gldim}(R)$ is finite if and only if R is a *regular local ring*, that is, if and only if $\mathfrak{m}$ can be generated by $\dim R$ elements ([20, Regular Local Ring]).

This theorem is the bridge between algebra and geometry. Regularity is a condition on the number of generators of $\mathfrak{m}$, equivalently on the associated graded ring ([20, Characterizations of a Regular Local Ring]), while global dimension is a homological condition on resolutions. Geometrically the regular local rings are the local rings at the nonsingular points of a variety, which is the reading [42] develops.

***Proof*:**
By definition 58.2.3, $\operatorname{gldim}(R) \geq \operatorname{pd}_R(k)$, which settles the case $\operatorname{pd}_R(k) = \infty$. Otherwise let $n = \operatorname{pd}_R(k)$, and let M be any finitely generated R-module. By lemma 58.2.8, $\operatorname{pd}_R(M) \leq n$ holds once $\operatorname{Tor}^R_{n+1}(M, k) = 0$. Since $\operatorname{pd}_R(k) = n$, definition 58.2.2 gives a projective resolution

$Q_\bullet$ of k with $Q_i = 0$ for every $i > n$. Computing with this resolution of the second variable, theorem 56.5.8 gives

$$\operatorname{Tor}^R_{n+1}(M,k) \cong H_{n+1}(M \otimes_R Q_\bullet) = 0$$

because the term $M \otimes_R Q_{n+1}$ is zero. Hence $\operatorname{pd}_R(M) \leq n$. This holds for every finitely generated M, in particular for every cyclic module R/I. By the Global Dimension Theorem [101, Thm. 4.1.2], $\operatorname{gldim}(R)$ is the supremum of $\operatorname{pd}_R(R/I)$ over the ideals I of R, so $\operatorname{gldim}(R) \leq n$, and hence $\operatorname{gldim}(R) = n$.

For the second statement, let R be regular of dimension m and let $x_1, \dots, x_m$ generate $\mathfrak{m}$. By lemma 58.2.10 they form a regular sequence, so by [21, Exactness of the Koszul Complex] the Koszul complex on $x_1, \dots, x_m$ is a finite free resolution of $R/\mathfrak{m} = k$ of length m. Hence $\operatorname{pd}_R(k) \leq m$, and $\operatorname{gldim}(R) = \operatorname{pd}_R(k) \leq m$ is finite. The converse, that finite global dimension forces R to be regular, is Serre's theorem [101, Main Thm. 4.4.16].

Definition 58.2.12: Regular Ring

A Noetherian ring A is *regular* if $A_\mathfrak{p}$ is a regular local ring for every prime ideal $\mathfrak{p}$ of A.

Lemma 58.2.13: Localization Does Not Raise Global Dimension

Let A be a commutative ring and $S \subseteq A$ a multiplicative set. Every $S^{-1}A$-module M, regarded as an A-module through $A \to S^{-1}A$, satisfies $\operatorname{pd}_{S^{-1}A}(M) \leq \operatorname{pd}_A(M)$. Consequently

$$\operatorname{gldim}(S^{-1}A) \leq \operatorname{gldim}(A)$$

***Proof*:**
Let M be an $S^{-1}A$-module. If $\operatorname{pd}_A(M) = \infty$ there is nothing to prove. Otherwise put $n = \operatorname{pd}_A(M)$ and choose, by definition 58.2.2, a projective resolution

$$0 \to P_n \to \cdots \to P_1 \to P_0 \to M \to 0$$

over A. Localization at S preserves short exact sequences (proposition 23.4.9), hence every exact sequence, since an exact sequence is spliced from short exact sequences through its images. So

$$0 \to S^{-1}P_n \to \cdots \to S^{-1}P_1 \to S^{-1}P_0 \to S^{-1}M \to 0$$

is an exact sequence of $S^{-1}A$-modules. Each $S^{-1}P_i$ is projective over $S^{-1}A$: if $P_i \oplus Q \cong A^{(I)}$ for an A-module Q and a set I, then $S^{-1}P_i \oplus S^{-1}Q \cong (S^{-1}A)^{(I)}$, because localization commutes with direct sums.

The localized sequence ends in $S^{-1}M$, and the map $\varphi\colon M \to S^{-1}M$, $\varphi(m) = m/1$, is an isomorphism of $S^{-1}A$-modules. An element $s \in S$ acts on M as the unit $s/1$ of $S^{-1}A$. For $a \in A$ and $s \in S$, the element $m' = (a/s)m$ of M satisfies $sm' = am$, so

$$\frac{a}{s} \cdot \varphi(m) = \frac{am}{s} = \frac{sm'}{s} = \frac{m'}{1} = \varphi\Big(\frac{a}{s}\, m\Big)$$

and φ is $S^{-1}A$-linear. It is injective, since $m/1 = 0$ means $um = 0$ for some $u \in S$, and u acts on M invertibly. It is surjective, since the display with $a = 1$ reads $m/s = \varphi\big((1/s)m\big)$. Composing

the augmentation with φ^{-1} turns the localized sequence into a projective resolution of M over $S^{-1}A$ of length n, so $\mathrm{pd}_{S^{-1}A}(M) \leq n$.

By definition 58.2.3, $\mathrm{gldim}(S^{-1}A)$ is the supremum of $\mathrm{pd}_{S^{-1}A}(M)$ over all $S^{-1}A$-modules M, and each of these is at most $\mathrm{pd}_A(M) \leq \mathrm{gldim}(A)$, completing the proof.

Combined with theorem 58.2.11, the lemma shows that a Noetherian ring A of finite global dimension is regular, since each $A_\mathfrak{p}$ is then a Noetherian local ring of global dimension at most $\mathrm{gldim}(A)$.

Corollary 58.2.14: Polynomial Rings over Regular Rings Are Regular

Let A be a regular ring. Then the polynomial ring $A[t_1, \ldots, t_n]$ is a regular ring for every $n \geq 0$.

***Proof*:**
Since $A[t_1, \ldots, t_n] = A[t_1, \ldots, t_{n-1}][t_n]$, induction on n reduces the claim to $n = 1$. Write t for the variable. The ring $A[t]$ is Noetherian by Hilbert's Basis Theorem (theorem 23.2.1).

Let P be a prime ideal of $A[t]$ and $\mathfrak{p} = P \cap A$, a prime ideal of A. The multiplicative set $A \setminus \mathfrak{p}$ is contained in $A[t] \setminus P$, and inverting it coefficientwise gives $(A \setminus \mathfrak{p})^{-1}A[t] = A_\mathfrak{p}[t]$. Let T be the image of $A[t] \setminus P$ in $A_\mathfrak{p}[t]$. By the universal property of localization (theorem 23.4.1), both $T^{-1}(A_\mathfrak{p}[t])$ and $A[t]_P$ are initial among $A[t]$-algebras in which every element of $A[t] \setminus P$ becomes a unit. Hence $A[t]_P \cong T^{-1}(A_\mathfrak{p}[t])$ is a localization of $A_\mathfrak{p}[t]$.

The ring $A_\mathfrak{p}$ is a regular local ring by definition 58.2.12, in particular Noetherian and local, so the implication from regularity to finite global dimension in theorem 58.2.11 gives $\mathrm{gldim}(A_\mathfrak{p}) < \infty$. Then lemma 58.2.13 and theorem 58.2.5 give

$$\mathrm{gldim}(A[t]_P) \leq \mathrm{gldim}(A_\mathfrak{p}[t]) = \mathrm{gldim}(A_\mathfrak{p}) + 1 < \infty$$

The ring $A[t]_P$ is local, and it is Noetherian as a localization of the Noetherian ring $A[t]$ (proposition 23.4.5). The implication from finite global dimension to regularity in theorem 58.2.11 therefore makes $A[t]_P$ a regular local ring. As P was an arbitrary prime of $A[t]$, the Noetherian ring $A[t]$ is regular.

Geometrically, $\mathrm{Spec}\, A[t_1, \ldots, t_n] = \mathrm{Spec}\, A \times_{\mathrm{Spec}\,\mathbb{Z}} \mathbb{A}^n_\mathbb{Z}$, so the product of a regular affine scheme with affine n-space is regular.

58.2.3 Beyond Regularity: The Hierarchy of Singularities

The Auslander-Buchsbaum-Serre theorem (theorem 58.2.11) presents a stark dichotomy: a local ring either has finite global dimension (and is geometrically smooth), or its global dimension is completely infinite.

For decades, algebraists sought to understand the "infinite" case. If a ring is singular, just *how* singular is it? How chaotic do the infinite free resolutions become? This inquiry led to a classification

of local Noetherian rings, a hierarchy that measures the severity of singularities based on homological behavior.

The complexity of a ring that fails to be regular is measured with the regular sequences of definition 58.2.9. Intuitively, a regular sequence is a sequence of elements that "cut down" the dimension of the module as cleanly and efficiently as possible, without creating any hidden nilpotent, and the maximal length of one is a new invariant.

Definition 58.2.15: Depth

Let $(R, \mathfrak{m})$ be a local Noetherian ring and M a finitely generated R-module. The *depth* of M, denoted $\operatorname{depth}(M)$, is the maximum length of an M-regular sequence contained in the maximal ideal $\mathfrak{m}$.

Depth is always bounded above by the Krull dimension ($\operatorname{depth}(R) \leq \operatorname{kdim}(R)$, proved as corollary 58.2.22 below). The gap between a ring's depth and its dimension is one of the primary measures of how "bad" a singularity is.

As defined, depth is a maximum over regular sequences, which makes it awkward to compute and awkward to use: knowing that *some* regular sequence has length n says nothing about whether a *given* regular element extends to one. Rees's theorem removes both difficulties at once by identifying depth with a vanishing degree for Ext, from which it follows that every maximal regular sequence has the same length.

Theorem 58.2.16: Depth via Ext (Rees)

Let $(R, \mathfrak{m}, k)$ be a Noetherian local ring and $M \neq 0$ a finitely generated R-module. If $x_1, \dots, x_n \in \mathfrak{m}$ is an M-regular sequence, then

$$\operatorname{Ext}^i_R(k, M) = 0 \text{ for } i < n, \qquad \operatorname{Ext}^n_R(k, M) \cong \operatorname{Hom}_R\big(k,\, M/(x_1, \dots, x_n)M\big)$$

Consequently every maximal M-regular sequence in $\mathfrak{m}$ has length $\min\big\{i \mid \operatorname{Ext}^i_R(k, M) \neq 0\big\}$, and in particular they all have the same length, namely $\operatorname{depth}(M)$.

***Proof*:**

Step 1: $\mathfrak{m}$ acts as zero on $\operatorname{Ext}^i_R(k, M)$. For $x \in \mathfrak{m}$, multiplication by x on $\operatorname{Ext}^i_R(k, M)$ is induced by multiplication by x on the first argument, which is the zero map $k \to k$; functoriality makes the induced map zero.

Step 2: the displayed formulas, by induction on n. For $n = 0$ there is nothing to prove, $\operatorname{Ext}^0_R(k, M) \cong \operatorname{Hom}_R(k, M)$ by proposition 56.3.13. Let $n \geq 1$ and put $M' = M/x_1M$, which is nonzero by Nakayama's lemma. As x_1 is a non-zero divisor on M, there is a short exact sequence

$$0 \to M \xrightarrow{x_1} M \to M' \to 0$$

and corollary 56.3.12, applied to $\operatorname{Hom}_R(k, -)$, gives a long exact sequence in which every map induced by x_1 vanishes by Step 1. It therefore breaks into short exact sequences

$$0 \to \operatorname{Ext}^i_R(k, M) \to \operatorname{Ext}^i_R(k, M') \to \operatorname{Ext}^{i+1}_R(k, M) \to 0$$

for every i. Now $x_2, \dots, x_n$ is an M'-regular sequence of length $n - 1$, so by induction

$\operatorname{Ext}^i_R(k, M') = 0$ for $i < n-1$ and $\operatorname{Ext}^{n-1}_R(k, M') \cong \operatorname{Hom}_R(k, M/(x_1, \ldots, x_n)M)$. Reading the displayed sequence for $i < n-1$ forces $\operatorname{Ext}^i_R(k, M) = 0$ and $\operatorname{Ext}^{i+1}_R(k, M) = 0$, so $\operatorname{Ext}^j_R(k, M) = 0$ for all $j < n$. Reading it at $i = n-1$, the left-hand term vanishes, so $\operatorname{Ext}^n_R(k, M) \cong \operatorname{Ext}^{n-1}_R(k, M')$, which is the claimed Hom.

Step 3: maximality. A regular sequence $x_1, \ldots, x_n$ is maximal exactly when no element of $\mathfrak{m}$ is a non-zero divisor on $N = M/(x_1, \ldots, x_n)M$, that is when $\mathfrak{m}$ consists of zero-divisors on N. The zero-divisors on N are the union of its associated primes ([20, The Zero-Divisors Are the Union of the Associated Primes]), of which there are finitely many ([20, Finiteness of Associated Primes]), so prime avoidance ([20, Prime Avoidance]) makes this equivalent to $\mathfrak{m} \in \operatorname{Ass}(N)$, that is to $\operatorname{Hom}_R(k, N) \neq 0$. By Step 2 that says $\operatorname{Ext}^n_R(k, M) \neq 0$, while $\operatorname{Ext}^i_R(k, M) = 0$ for $i < n$. So n is the least degree in which $\operatorname{Ext}^\bullet_R(k, M)$ is nonzero, a quantity independent of the sequence chosen, completing the proof.

Two consequences are immediate and are used throughout what follows: a given M-regular sequence in $\mathfrak{m}$ extends to one of length $\operatorname{depth}(M)$, since any maximal extension of it has that length; and $\operatorname{depth}(M) = 0$ exactly when $\mathfrak{m} \in \operatorname{Ass}(M)$.

Using this, we can make the Auslander-Buchsbaum-Serre theorem more refined by looking at modules over R:

Theorem 58.2.17: Auslander-Buchsbaum Formula

Let $(R, \mathfrak{m}, k)$ be a local Noetherian ring, and let M be a non-zero finitely generated R-module with finite projective dimension. Then:

$$\operatorname{pd}_R(M) + \operatorname{depth}(M) = \operatorname{depth}(R)$$

***Proof Key ideas*:**
The proof is an induction on $\operatorname{depth}(M)$ whose steps are standard commutative algebra rather than homological algebra; it is given in full in *An Introduction to Homological Algebra* [101, Thm. 4.4.15].

The base case is $\operatorname{depth}(M) = 0$, where $\mathfrak{m}$ is an associated prime of M and one shows $\operatorname{pd}_R(M) = \operatorname{depth}(R)$ directly from a minimal free resolution: the length of that resolution is detected by $\operatorname{Tor}^R_i(M, k)$ against the residue field (lemma 58.2.8), and the depth of R bounds where those groups can survive.

The inductive step reduces the depth of M by one. If $\operatorname{depth}(M) > 0$ and $\operatorname{depth}(R) > 0$, prime avoidance applied to $\operatorname{Ass}(R) \cup \operatorname{Ass}(M)$ produces an $x \in \mathfrak{m}$ regular on both M and R; passing to M/xM over $R/(x)$ drops both $\operatorname{depth}(M)$ and $\operatorname{depth}(R)$ by one while leaving pd unchanged, so the formula for the quotient gives the formula for M. The remaining case is $\operatorname{depth}(R) = 0$, handled separately: there finite projective dimension forces M to be free, so both sides of the formula vanish.

The two theorems combine into the numerical statement that the applications actually use: for a regular local ring the global dimension is not merely finite, it is the Krull dimension.

Corollary 58.2.18: Global Dimension of a Regular Local Ring

Let $(R, \mathfrak{m}, k)$ be a Noetherian regular local ring of dimension m. Then

$$\operatorname{gldim}(R) \;=\; \operatorname{depth}(R) \;=\; \dim R \;=\; m$$

In particular every finitely generated R-module has projective dimension at most $\dim R$.

***Proof*:**

Step 1: $\operatorname{depth}(R) \geq m$. Choose $x_1, \ldots, x_m$ generating $\mathfrak{m}$, possible by regularity. By lemma 58.2.10 they form a regular sequence, which lies in $\mathfrak{m}$ and has length m, so $\operatorname{depth}(R) \geq m$.

Step 2: $\operatorname{pd}_R(k) \leq m$. By Step 1 and [21, Exactness of the Koszul Complex], the Koszul complex on $x_1, \ldots, x_m$ is a finite free resolution of $R/\mathfrak{m} = k$ of length m. So $\operatorname{pd}_R(k) \leq m$.

Step 3: assembly. Theorem 58.2.11 gives $\operatorname{gldim}(R) = \operatorname{pd}_R(k)$, finite by Step 2, so the Auslander-Buchsbaum formula (theorem 58.2.17) applies to $M = k$. Every element of $\mathfrak{m}$ annihilates the nonzero module k and is therefore a zerodivisor on it, so no element of $\mathfrak{m}$ is k-regular and $\operatorname{depth}(k) = 0$. The formula reads $\operatorname{pd}_R(k) = \operatorname{depth}(R)$. Combining the three steps,

$$m \leq \operatorname{depth}(R) = \operatorname{pd}_R(k) = \operatorname{gldim}(R) \leq m$$

so $\operatorname{depth}(R)$, $\operatorname{pd}_R(k)$ and $\operatorname{gldim}(R)$ all equal $m = \dim R$, completing the proof.

Using depth and other structural properties, local rings can be classified into a strict chain of implications:

$$\text{Regular} \implies \text{Complete Intersection} \implies \text{Gorenstein} \implies \text{Cohen-Macaulay}$$

The chain stops at Cohen-Macaulay: it does *not* continue to normal or reduced. The hypersurface $k[[x, y]]/(xy)$ is a complete intersection, hence Gorenstein and Cohen-Macaulay, and it is reduced, but it is not normal, being not even a domain. By Serre's criterion (theorem 58.3.2) normality is the conjunction of R_1 and S_2; Cohen-Macaulay gives S_2 and says nothing about R_1, which is where the implication fails. The correct companion chain runs

$$\text{Regular} \implies \text{Normal} \implies \text{Reduced}$$

While these definitions are strictly for *local* rings, we say a Noetherian ring has one of these properties if its localization at every prime ideal has it (for regularity this is definition 58.2.12).

Complete Intersections: These are the "nicest" singularities. Geometrically, they are spaces cut out by exactly the correct number of equations (e.g., a 1D curve in $\mathbb{C}^3$ defined by exactly two equations). Algebraically, R is the quotient of a regular local ring by a regular sequence. While modules over these rings can have infinite projective dimension, their free resolutions are highly predictable, eventually becoming periodic.

Gorenstein Rings: These rings represent spaces with "symmetric" singularities. They are exactly the spaces where a generalized form of Poincaré Duality still holds. Algebraically, a local ring is Gorenstein if it has finite injective dimension over itself. The free resolutions over Gorenstein rings exhibit a mirror symmetry when the functor $\operatorname{Hom}_R(-, R)$ is applied.

Cohen-Macaulay Rings: This is perhaps the most important class of singular rings in algebraic geometry, and the one the subsection below treats properly. A local ring is Cohen-Macaulay if its depth equals its Krull dimension (definition 58.2.19). Geometrically, these spaces are "equidimensional" and lack hidden, embedded fuzzy components. Here, the Auslander-Buchsbaum formula perfectly aligns with the geometric dimension.

Normal Rings: A ring is normal if it is integrally closed in its total ring of fractions. Geometrically, this means the space is "smooth in codimension 1". For example, a 2D normal surface can have an isolated singular point (like the tip of a cone), but it cannot have a singular crease or folded line running through it.

Reduced Rings: A ring is reduced if it contains no non-zero nilpotents ($x^n = 0 \implies x = 0$). Geometrically, this simply means the space has no "thickness" or "fuzz"; it is a classical geometric space uniquely determined by the values of functions at its points.

58.2.4 Cohen-Macaulay Rings

Of the classes just listed, Cohen-Macaulay is the one downstream geometry actually uses, and it deserves more than a description. Two facts are wanted: that a system of parameters in such a ring is automatically a regular sequence, so that the naive count of equations is the honest one; and that the ring carries no embedded associated primes, so that a subscheme cut out this way has no hidden components. Both follow from a single inequality relating depth to the dimensions of the associated primes. Associated primes, prime avoidance, and the identification of the zero-divisors with the union of the associated primes are those of [20, Associated Prime, Prime Avoidance, Zero-Divisors and Annihilators].

Definition 58.2.19: Cohen-Macaulay Ring

A Noetherian local ring $(R, \mathfrak{m})$ is *Cohen-Macaulay* if $\operatorname{depth}(R) = \operatorname{kdim}(R)$. A Noetherian ring is Cohen-Macaulay if its localization at every prime is. More generally a finitely generated module $M \neq 0$ over a Noetherian local ring is *Cohen-Macaulay* if $\operatorname{depth}(M) = \operatorname{kdim}(M)$, the dimension of $R/\operatorname{Ann}(M)$.

Lemma 58.2.20: Depth Drops by One Modulo a Non-Zero Divisor

Let $(R, \mathfrak{m})$ be Noetherian local, $M \neq 0$ finitely generated, and $x \in \mathfrak{m}$ a non-zero divisor on M. Then $\operatorname{depth}(M/xM) = \operatorname{depth}(M) - 1$.

***Proof*:**
Prepending x to any M/xM-regular sequence in $\mathfrak{m}$ yields an M-regular sequence, so $\operatorname{depth}(M) \geq \operatorname{depth}(M/xM) + 1$ directly from definition 58.2.15.

For the reverse, extend x to a maximal M-regular sequence $x, y_1, \ldots, y_m$ in $\mathfrak{m}$; this is possible, and the result has length $\operatorname{depth}(M)$, by theorem 58.2.16. Then $y_1, \ldots, y_m$ is an M/xM-regular sequence, so $\operatorname{depth}(M/xM) \geq m = \operatorname{depth}(M) - 1$. Combining the two, both are equalities, as we sought to show.

Proposition 58.2.21: Depth Is Bounded by the Dimension of Every Associated Prime

Let $(R, \mathfrak{m})$ be Noetherian local, $M \neq 0$ finitely generated, and $\mathfrak{p} \in \operatorname{Ass}(M)$. Then

$$\operatorname{depth}(M) \;\leq\; \operatorname{kdim}(R/\mathfrak{p})$$

***Proof*:**
Induct on $n = \operatorname{depth}(M)$. For $n = 0$ there is nothing to prove. Let $n > 0$ and let $x \in \mathfrak{m}$ be a non-zero divisor on M, which exists because the depth is positive. Since $\mathfrak{p}$ consists of zero-divisors on M, [20, The Zero-Divisors Are the Union of the Associated Primes] gives $x \notin \mathfrak{p}$.

Write $\mathfrak{p} = \operatorname{Ann}(m)$ with $m \neq 0$. We first arrange $m \notin xM$. If $m = xm_1$ then $\operatorname{Ann}(m_1) = \mathfrak{p}$: an r killing m_1 kills m, and conversely $rm = 0$ gives $rxm_1 = 0$, whence $rm_1 = 0$ as x is a non-zero divisor. Iterating produces $m = x^k m_k$ with $\operatorname{Ann}(m_k) = \mathfrak{p}$ for each k, and the submodules $Rm \subseteq Rm_1 \subseteq Rm_2 \subseteq \cdots$ ascend. As M is Noetherian the chain stabilizes, say $Rm_k = Rm_{k+1}$, so $m_{k+1} = rm_k = rx\, m_{k+1}$ for some r; then $(1 - rx)m_{k+1} = 0$, and $1 - rx$ is a unit because $x \in \mathfrak{m}$, forcing $m_{k+1} = 0$ and hence $m = 0$. That contradiction means the iteration halts, so we may take $m \notin xM$.

Let $N = Rm$ and let $\overline{N}$ be its image in M/xM, nonzero by the previous paragraph. Every element of $\mathfrak{p}$ kills N, hence $\overline{N}$; and x kills $\overline{N}$ too, since $xN \subseteq xM$. So $\operatorname{Ann}(\overline{N}) \supseteq \mathfrak{p} + (x)$. Choose $\mathfrak{q} \in \operatorname{Ass}(\overline{N}) \subseteq \operatorname{Ass}(M/xM)$, nonempty by [20, Zero-Divisors and Annihilators]. Then $\mathfrak{q} \supseteq \mathfrak{p} + (x)$, and $\mathfrak{q} \neq \mathfrak{p}$ because $x \notin \mathfrak{p}$, so $\mathfrak{q} \supsetneq \mathfrak{p}$ and $\operatorname{kdim}(R/\mathfrak{q}) \leq \operatorname{kdim}(R/\mathfrak{p}) - 1$. By lemma 58.2.20 and the inductive hypothesis applied to M/xM and $\mathfrak{q}$,

$$n - 1 \;=\; \operatorname{depth}(M/xM) \;\leq\; \operatorname{kdim}(R/\mathfrak{q}) \;\leq\; \operatorname{kdim}(R/\mathfrak{p}) - 1$$

which is the assertion.

Corollary 58.2.22: Depth Is at Most the Dimension

For $M \neq 0$ finitely generated over a Noetherian local ring, $\operatorname{depth}(M) \leq \operatorname{kdim}(M)$. In particular $\operatorname{depth}(R) \leq \operatorname{kdim}(R)$, so Cohen-Macaulay is the extremal case.

***Proof*:**
$\operatorname{Ass}(M)$ is nonempty ([20, Zero-Divisors and Annihilators]); pick $\mathfrak{p}$ in it. Then $\mathfrak{p} \supseteq \operatorname{Ann}(M)$, so $\operatorname{kdim}(R/\mathfrak{p}) \leq \operatorname{kdim}(R/\operatorname{Ann}(M)) = \operatorname{kdim}(M)$, and proposition 58.2.21 bounds the depth by the left-hand side.

This is the inequality asserted informally above, and a Cohen-Macaulay ring is one in which it is an equality (definition 58.2.19).

Corollary 58.2.23: A Cohen-Macaulay Ring Has No Embedded Associated Primes

Let $(R, \mathfrak{m})$ be a Cohen-Macaulay local ring of dimension d. Then every $\mathfrak{p} \in \operatorname{Ass}(R)$ satisfies $\operatorname{kdim}(R/\mathfrak{p}) = d$, and every such $\mathfrak{p}$ is a minimal prime of R. In particular R has no embedded associated primes, and R is equidimensional.

***Proof*:**
For $\mathfrak{p} \in \operatorname{Ass}(R)$, proposition 58.2.21 gives $d = \operatorname{depth}(R) \leq \operatorname{kdim}(R/\mathfrak{p}) \leq d$, so $\operatorname{kdim}(R/\mathfrak{p}) = d$. If $\mathfrak{p}$ were not minimal it would strictly contain a prime $\mathfrak{p}_0$, and then $\operatorname{kdim}(R/\mathfrak{p}) < \operatorname{kdim}(R/\mathfrak{p}_0) \leq d$, a contradiction. An associated prime that is minimal is by definition not embedded.

Theorem 58.2.24: A System of Parameters in a Cohen-Macaulay Local Ring Is a Regular Sequence

Let $(R, \mathfrak{m})$ be a Cohen-Macaulay local ring of dimension d and let $x_1, \dots, x_d \in \mathfrak{m}$ be a system of parameters, that is d elements generating an $\mathfrak{m}$-primary ideal. Then $x_1, \dots, x_d$ is a regular sequence, and $R/(x_1, \dots, x_d)$ is Cohen-Macaulay of dimension zero.

***Proof*:**
Induct on d, the case $d = 0$ being the empty sequence. Let $d > 0$. Since $x_1, \dots, x_d$ generate an $\mathfrak{m}$-primary ideal, the images of $x_2, \dots, x_d$ generate an $\mathfrak{m}$-primary ideal of $R/(x_1)$, so $\operatorname{kdim} R/(x_1) \leq d-1$ by the dimension theorem of [20, Dimension Theorem]; and $\operatorname{kdim} R/(x_1) \geq d-1$ by Krull's height theorem there. So $\operatorname{kdim} R/(x_1) = d-1$.

Now x_1 is a non-zero divisor. Suppose $x_1 \in \mathfrak{p}$ for some $\mathfrak{p} \in \operatorname{Ass}(R)$. By corollary 58.2.23, $\operatorname{kdim}(R/\mathfrak{p}) = d$; but $\mathfrak{p} \supseteq (x_1)$ gives a surjection $R/(x_1) \twoheadrightarrow R/\mathfrak{p}$ and hence $\operatorname{kdim} R/(x_1) \geq d$, contradicting the previous paragraph. So x_1 lies outside every associated prime and is a non-zero divisor by [20, The Zero-Divisors Are the Union of the Associated Primes].

By lemma 58.2.20, $\operatorname{depth} R/(x_1) = d - 1 = \operatorname{kdim} R/(x_1)$, so $R/(x_1)$ is Cohen-Macaulay of dimension $d-1$, and the images of $x_2, \dots, x_d$ are a system of parameters for it. The inductive hypothesis makes them a regular sequence there, which is exactly the statement that $x_1, \dots, x_d$ is a regular sequence on R and that the final quotient is Cohen-Macaulay of dimension zero.

The form geometry reaches for is slightly more general: the elements need not be a full system of parameters, only as many as the height of the ideal they generate.

Corollary 58.2.25: Height-Many Elements in a Cohen-Macaulay Ring Form a Regular Sequence

Let R be a Cohen-Macaulay local ring and let $x_1, \dots, x_h \in R$ generate an ideal $I = (x_1, \dots, x_h)$ of height h. Then $x_1, \dots, x_h$ is a regular sequence.

***Proof*:**
Let $\mathfrak{p}$ be a prime minimal over I with $\operatorname{ht} \mathfrak{p} = h$, which exists because the height of I is the minimum of $\operatorname{ht} \mathfrak{q}$ over primes $\mathfrak{q}$ minimal over I. Localizing, $R_{\mathfrak{p}}$ is Cohen-Macaulay of dimension h (localization of a Cohen-Macaulay local ring at a prime is Cohen-Macaulay, and $\dim R_{\mathfrak{p}} = \operatorname{ht} \mathfrak{p} = h$), and the images of $x_1, \dots, x_h$ generate an ideal primary to the maximal ideal of $R_{\mathfrak{p}}$, since $\mathfrak{p}$ is minimal over I. They are therefore a system of parameters of $R_{\mathfrak{p}}$, hence a regular sequence there by theorem 58.2.24.

To descend, induct on i: suppose $x_1, \dots, x_{i-1}$ is a regular sequence on R and that x_i is a zero divisor on $M = R/(x_1, \dots, x_{i-1})$. Then x_i lies in an associated prime $\mathfrak{q}$ of M ([20, Zero-Divisors and Annihilators]), and M is Cohen-Macaulay of dimension $\dim R - i + 1$ by

theorem 58.2.24 applied step by step, so $\mathfrak{q}$ has no embedded components by corollary 58.2.23 and $\dim R/\mathfrak{q} = \dim R - i + 1$. But $\mathfrak{q} \supseteq (x_1, \ldots, x_i)$ forces $\operatorname{ht}\mathfrak{q} \geq$ the height of that ideal, and comparing with the localized statement above bounds $\dim R/\mathfrak{q}$ strictly below $\dim R - i + 1$, a contradiction. So each x_i is a non-zero divisor on the preceding quotient, as we sought to show.

58.3 Serre's Criterion for Normality

Depth and regularity are conditions on a local ring; imposing them at every prime, with a strength that grows with the height, produces the two families of conditions Serre introduced. Their point is the theorem below: normality, which is a statement about integral closure and has no homological content on its face, is exactly the conjunction of a regularity condition in codimension one and a depth condition everywhere.

Definition 58.3.1: Serre's Conditions

Let R be a Noetherian ring and $k \geq 0$ an integer. Then R satisfies

- (R_k) if $R_{\mathfrak{p}}$ is a regular local ring for every prime $\mathfrak{p}$ with $\operatorname{ht}\mathfrak{p} \leq k$;
- (S_k) if $\operatorname{depth}(R_{\mathfrak{p}}) \geq \min\left(k,\ \operatorname{ht}\mathfrak{p}\right)$ for every prime $\mathfrak{p}$.

Both conditions weaken as attention moves to primes of large height: (R_k) says nothing about primes of height above k, and (S_k) asks only for depth k once the height reaches k. A regular ring satisfies (R_k) for every k, and a Cohen-Macaulay ring satisfies (S_k) for every k, since there $\operatorname{depth} R_{\mathfrak{p}} = \operatorname{kdim} R_{\mathfrak{p}} = \operatorname{ht}\mathfrak{p}$.

Theorem 58.3.2: Serre's Criterion for Normality

Let R be a Noetherian domain. Then R is integrally closed in its fraction field if and only if it satisfies (R_1) and (S_2).

***Proof*:**

Necessity. Suppose R is normal. For (R_1), a prime of height zero is (0) and $R_{(0)}$ is a field, which is regular; and for $\operatorname{ht}\mathfrak{p} = 1$ the ring $R_{\mathfrak{p}}$ is a discrete valuation ring by [20, A Normal Domain Is the Intersection of Its Height-One Localizations], hence regular.

For (S_2) let $\mathfrak{p}$ be a prime. If $\operatorname{ht}\mathfrak{p} = 0$ there is nothing to prove. If $\operatorname{ht}\mathfrak{p} = 1$ then $R_{\mathfrak{p}}$ is a discrete valuation ring, whose maximal ideal is generated by a non-zero divisor, so its depth is at least $1 = \min(2, 1)$. Suppose $\operatorname{ht}\mathfrak{p} \geq 2$, so that $\min(2, \operatorname{ht}\mathfrak{p}) = 2$. The ring $R_{\mathfrak{p}}$ is a Noetherian normal domain, so any nonzero $b \in \mathfrak{p}R_{\mathfrak{p}}$ is a non-zero divisor and $\operatorname{depth}(R_{\mathfrak{p}}) \geq 1$. By [20, Associated Primes of a Principal Ideal Have Height One], every associated prime of $bR_{\mathfrak{p}}$ has height one, so $\mathfrak{p}R_{\mathfrak{p}}$, of height at least two, is not one of them; hence $\operatorname{depth}(R_{\mathfrak{p}}/bR_{\mathfrak{p}}) \neq 0$ by the second consequence of theorem 58.2.16. Then lemma 58.2.20 gives $\operatorname{depth}(R_{\mathfrak{p}}) = \operatorname{depth}(R_{\mathfrak{p}}/bR_{\mathfrak{p}}) + 1 \geq 2$.

Sufficiency. Suppose R satisfies (R_1) and (S_2), and write K for its fraction field. Every prime of height one has $R_{\mathfrak{p}}$ regular local of dimension one by (R_1), hence a discrete valuation ring, hence integrally closed. An intersection of integrally closed subrings of K each with fraction field K is

integrally closed, so it suffices to prove

$$R = \bigcap_{\operatorname{ht}\mathfrak{p}=1} R_{\mathfrak{p}}$$

One inclusion is immediate. For the other, let x lie in every such $R_{\mathfrak{p}}$, write $x = a/b$ with $b \neq 0$, and suppose $a \notin (b)$. Then $\operatorname{Ann}(\overline{a}) = (b : a)$ is a proper ideal consisting of zero-divisors on $R/(b)$, so as in [20, The Zero-Divisors Are the Union of the Associated Primes] together with prime avoidance it lies in a single $\mathfrak{q} \in \operatorname{Ass}(R/(b))$.

The height of $\mathfrak{q}$ is one. It is at least one because R is a domain and $b \neq 0$. If it were at least two, then (S_2) would give $\operatorname{depth}(R_{\mathfrak{q}}) \geq 2$, and b is a non-zero divisor in $\mathfrak{q}R_{\mathfrak{q}}$, so lemma 58.2.20 would give $\operatorname{depth}(R_{\mathfrak{q}}/bR_{\mathfrak{q}}) \geq 1$, whence $\mathfrak{q}R_{\mathfrak{q}} \notin \operatorname{Ass}(R_{\mathfrak{q}}/bR_{\mathfrak{q}})$ by theorem 58.2.16. But associated primes localize, so $\mathfrak{q} \in \operatorname{Ass}(R/(b))$ makes $\mathfrak{q}R_{\mathfrak{q}}$ associated to $R_{\mathfrak{q}}/bR_{\mathfrak{q}}$, a contradiction.

So $\operatorname{ht}\mathfrak{q} = 1$ and $x \in R_{\mathfrak{q}}$ by hypothesis; that produces $s \notin \mathfrak{q}$ with $sa \in bR$, so $s \in (b : a) \subseteq \mathfrak{q}$, a contradiction. Hence $a \in (b)$ and $x \in R$, completing the proof.

Geometrically, (R_1) says a normal variety is smooth away from a closed set of codimension at least two, and (S_2) says a function defined outside such a set extends across it. That reading, and the divisor theory it supports, is [42].

58.4 The Local Criterion for Flatness

One of the most powerful applications of Nakayama's Lemma and homological algebra is the Local Criterion for Flatness. Checking whether a module is flat directly from the definition (that tensoring preserves exactness) can be extremely difficult. The local criterion reduces this to checking exactness against a single module (the residue field), or checking that regular sequences map to regular sequences.

Theorem 58.4.1: Local Criterion for Flatness

Let $\varphi : (R, \mathfrak{m}) \to (S, \mathfrak{n})$ be a local homomorphism of Noetherian local rings, and let M be a finitely generated S-module. Then the following are equivalent:

1. M is flat over R.
2. $\operatorname{Tor}_1^R(M, R/\mathfrak{m}) = 0$.
3. The natural multiplication map $\mathfrak{m} \otimes_R M \to \mathfrak{m}M$ is an isomorphism.

***Proof*:**

The implication (1) $\Rightarrow$ (2) is trivial since M is flat implies $\operatorname{Tor}_i^R(M, -) = 0$ for all $i > 0$. The equivalence (2) $\iff$ (3) follows from applying $- \otimes_R M$ to the short exact sequence $0 \to \mathfrak{m} \to R \to R/\mathfrak{m} \to 0$, which gives the long exact sequence in Tor:

$$0 = \operatorname{Tor}_1^R(R, M) \to \operatorname{Tor}_1^R(R/\mathfrak{m}, M) \to \mathfrak{m} \otimes_R M \to R \otimes_R M \to R/\mathfrak{m} \otimes_R M \to 0$$

Since $R \otimes_R M \cong M$, the kernel of $M \to M/\mathfrak{m}M$ is precisely $\mathfrak{m}M$. Thus $\operatorname{Tor}_1^R(R/\mathfrak{m}, M) = 0$ if and only if $\mathfrak{m} \otimes_R M \to \mathfrak{m}M$ is injective (and it is always surjective).

For (2) $\Rightarrow$ (1), we must show that $\operatorname{Tor}_1^R(M, N) = 0$ for all finitely generated R-modules N. We proceed by induction on the length of N. By Nakayama's Lemma (lemma 23.4.27), if $N \neq 0$, we can find a non-zero quotient $N \to R/\mathfrak{m}$. Let K be the kernel, so we have $0 \to K \to N \to R/\mathfrak{m} \to 0$. The long exact sequence in Tor gives:

$$\operatorname{Tor}_1^R(K, M) \to \operatorname{Tor}_1^R(N, M) \to \operatorname{Tor}_1^R(R/\mathfrak{m}, M) = 0$$

Thus, $\operatorname{Tor}_1^R(K, M)$ surjects onto $\operatorname{Tor}_1^R(N, M)$. By iterating this process (using the Artin-Rees lemma and the $\mathfrak{m}$-adic filtration on N; theorem 25.4.1), one can show that $\operatorname{Tor}_1^R(N, M) \subseteq \mathfrak{m}\operatorname{Tor}_1^R(N, M)$. Since M is a finitely generated S-module and S is Noetherian, $\operatorname{Tor}_1^R(N, M)$ is a finitely generated S-module. By Nakayama's Lemma (applied over S, since $\mathfrak{m}S \subseteq \mathfrak{n}$), we conclude $\operatorname{Tor}_1^R(N, M) = 0$.

In algebraic geometry, we often deal with regular local rings and regular sequences. The Local Criterion gives us an incredibly useful corollary for checking flatness in terms of regular sequences. This is the algebraic engine behind an infamous result known as the "Miracle Flatness" theorem, an important "shortcut" for proving flatness in [13].

Corollary 58.4.2: Regular Sequence Criterion for Flatness

Let $\varphi : (R, \mathfrak{m}) \to (S, \mathfrak{n})$ be a local homomorphism of Noetherian local rings, and M a finitely generated S-module. Let $x \in \mathfrak{m}$ be a non-zero divisor on R. Then M is flat over R if and only if both of the following hold if and only if:

1. x is a non-zero divisor on M, and
2. M/xM is flat over $R/(x)$.

By induction, if $x_1, \ldots, x_d \in \mathfrak{m}$ is a regular sequence in R, then M is flat over R if and only if $x_1, \ldots, x_d$ forms a regular sequence on M and $M/(x_1, \ldots, x_d)M$ is flat over $R/(x_1, \ldots, x_d)$.

***Proof*:**

($\Rightarrow$): If M is flat over R, applying $- \otimes_R M$ to the exact sequence $0 \to R \xrightarrow{\cdot x} R \to R/(x) \to 0$ yields the exact sequence $0 \to M \xrightarrow{\cdot x} M \to M/xM \to 0$. Thus x is a non-zero divisor on M. Furthermore, base change preserves flatness, so $M/xM \cong M \otimes_R R/(x)$ is flat over $R/(x)$.

($\Leftarrow$): Assume x is regular on M and M/xM is flat over $R/(x)$. We want to show M is flat. Since M/xM is flat over $R/(x)$, $\operatorname{Tor}_1^{R/(x)}(R/\mathfrak{m}, M/xM) = 0$. Combined with the fact that x is regular on M, this gives $\operatorname{Tor}_1^R(R/\mathfrak{m}, M) = 0$: taking a free resolution $F_\bullet \to M$ over R, regularity of x on both R and M makes $F_\bullet \otimes_R R/(x)$ a free resolution of M/xM over $R/(x)$, so $\operatorname{Tor}_i^{R/(x)}(N, M/xM) \cong \operatorname{Tor}_i^R(N, M)$ for every $R/(x)$-module N, and $N = R/\mathfrak{m}$ is one. By the Local Criterion for Flatness (theorem 58.4.1), M is flat over R.

The variant that geometry actually asks for reverses the roles: rather than a regular sequence downstairs, one is handed an element that is a nonzerodivisor *on the fibre*, and wants to conclude that it was a nonzerodivisor upstairs all along. This is how flatness of a family cut out by equations

gets verified one equation at a time.

Corollary 58.4.3: Fibrewise Nonzerodivisor Criterion for Flatness

Let $\varphi : (R, \mathfrak{m}) \to (S, \mathfrak{n})$ be a local homomorphism of Noetherian local rings with $\kappa = R/\mathfrak{m}$, let M be a finitely generated S-module that is flat over R, and let $u \in \mathfrak{n}$. If u is a non-zero divisor on $M/\mathfrak{m}M = M \otimes_R \kappa$, then u is a non-zero divisor on M, and M/uM is flat over R.

***Proof*:**
Write $K = \ker(u : M \to M)$ and $M' = M/K$, so that multiplication by u factors as a surjection $M \twoheadrightarrow M'$ followed by an injection $M' \hookrightarrow M$, and $N := M/uM$ is the cokernel of the latter. Both sequences

$$0 \to K \to M \to M' \to 0, \qquad 0 \to M' \xrightarrow{u} M \to N \to 0$$

are exact by construction.

Step 1: N is flat. Apply $- \otimes_R \kappa$ to the second sequence. Flatness of M gives $\operatorname{Tor}_1^R(\kappa, M) = 0$, so the long exact sequence begins

$$0 \to \operatorname{Tor}_1^R(\kappa, N) \to M' \otimes_R \kappa \to M \otimes_R \kappa \to N \otimes_R \kappa \to 0$$

Now right-exactness applied to the first sequence makes $M \otimes_R \kappa \to M' \otimes_R \kappa$ surjective, and composing it with $M' \otimes_R \kappa \to M \otimes_R \kappa$ recovers multiplication by u on $M \otimes_R \kappa$, which is injective by hypothesis. A surjection whose composite with a further map is injective is itself injective, so $M \otimes_R \kappa \to M' \otimes_R \kappa$ is an isomorphism, and therefore $M' \otimes_R \kappa \to M \otimes_R \kappa$ is injective as well. Hence $\operatorname{Tor}_1^R(\kappa, N) = 0$, and N is flat over R by theorem 58.4.1.

Step 2: $K = 0$. Since M and N are both flat over R, the second sequence forces M' to be flat too: for any R-module T the long exact sequence reads $0 = \operatorname{Tor}_2^R(T, N) \to \operatorname{Tor}_1^R(T, M') \to \operatorname{Tor}_1^R(T, M) = 0$. In particular $\operatorname{Tor}_1^R(\kappa, M') = 0$, so applying $- \otimes_R \kappa$ to the first sequence leaves $K \otimes_R \kappa \to M \otimes_R \kappa$ injective. But Step 1 showed $M \otimes_R \kappa \to M' \otimes_R \kappa$ is an isomorphism, so exactness at $M \otimes_R \kappa$ makes the image of $K \otimes_R \kappa$ zero. An injective map with zero image is zero, so $K/\mathfrak{m}K = 0$. As K is a submodule of the finitely generated module M over the Noetherian ring S, it is finitely generated, and $\mathfrak{m}S \subseteq \mathfrak{n}$, so Nakayama gives $K = 0$.

A third consequence is the one deformation arguments in geometry lean on: a resolution of a flat object stays a resolution after restriction to a fibre. Without it a resolution built on a total space says nothing about the special fibres it was built to compare.

Proposition 58.4.4: Restriction of a Resolution to a Fibre

Let R be a ring, A an R-algebra, and M an A-module that is flat over R. Let

$$0 \to G_n \to G_{n-1} \to \cdots \to G_0 \to M \to 0$$

be an exact sequence of A-modules with every G_i flat over R. Then for every R-algebra $R \to k$, applying $- \otimes_R k$ leaves the sequence exact:

$$0 \to G_n \otimes_R k \to \cdots \to G_0 \otimes_R k \to M \otimes_R k \to 0$$

In particular, if $X \to S$ is a morphism of schemes, $\mathscr{F}$ a quasi-coherent sheaf on X flat over S, and $G_\bullet \to \mathscr{F}$ a resolution by quasi-coherent sheaves flat over S, then the restriction of $G_\bullet \to \mathscr{F}$ to any fibre X_s is a resolution of $\mathscr{F}|_{X_s}$.

***Proof*:**
Break the sequence into short exact pieces $0 \to Z_{i+1} \to G_i \to Z_i \to 0$ with $Z_0 = M$ and $Z_{n+1} = 0$. We show by induction on i that every Z_i is flat over R, the base case $Z_0 = M$ being the hypothesis. Given that Z_i is R-flat, the sequence $0 \to Z_{i+1} \to G_i \to Z_i \to 0$ has flat right-hand and middle terms, so the long exact sequence of $\operatorname{Tor}^R(-, N)$ gives $0 = \operatorname{Tor}_2^R(Z_i, N) \to \operatorname{Tor}_1^R(Z_{i+1}, N) \to \operatorname{Tor}_1^R(G_i, N) = 0$ for every N, whence Z_{i+1} is flat. The induction therefore gives flatness of every syzygy.

Now tensor each short exact piece with k over R. Flatness of Z_i makes $\operatorname{Tor}_1^R(Z_i, k) = 0$, so $0 \to Z_{i+1} \otimes_R k \to G_i \otimes_R k \to Z_i \otimes_R k \to 0$ is exact. Splicing the pieces back together reassembles the long sequence, still exact. The sheaf statement is this one applied on affine opens, flatness and exactness both being local, as we sought to show.

Exercise 58.4.1

1. Let $R = k[x, y]$. Find a free resolution for the module $M = R/(x^2, xy, y^2)$. What is the length of this resolution?
2. Show that over $R = \mathbb{Z}$, the module $M = \mathbb{Q}$ has projective dimension 1, but does not have a finite *free* resolution if we require finitely generated free modules (which is impossible since $\mathbb{Q}$ is not finitely generated).
3. Why does the Syzygy theorem fail for $R = k[x_1, x_2, \dots]$ (infinite variables)? Find a module with infinite projective dimension.

58.5 The Limit of a Tower and Its First Derived Functor

The functors derived so far in this chapter have been Hom and $\otimes$, and the objects they were applied to were modules over a ring. The functor of this section is neither, and its source category is not a category of modules: it is the limit, applied to a sequence of abelian groups indexed by $\mathbb{N}$ with maps running backwards. The limit of such a sequence is left exact and not exact, so it has derived functors like any other left-exact functor. What is special is how few of them there are. Exactly one

is nonzero, it admits a description with no resolutions in it at all, and it vanishes under a hypothesis satisfied in most of the situations where the limit is taken.

That last point is why the section exists. A cohomology theory evaluated on an infinite complex, the cohomology of an infinite-dimensional classifying space, the completion of a ring: each is computed as a limit over a sequence of finite approximations, and in each the answer is the naive limit *provided* a single obstruction group vanishes. Naming that group is what allows the provision to be checked rather than assumed.[2]

Definition 58.5.1: Tower of Abelian Groups

A *tower* of abelian groups is a sequence $A_\bullet = (A_n)_{n\geq 0}$ of abelian groups together with homomorphisms

$$A_0 \xleftarrow{f_1} A_1 \xleftarrow{f_2} A_2 \xleftarrow{f_3} \cdots$$

called the *transition maps*. For $m \geq n$ write $f_{n,m}\colon A_m \to A_n$ for the composite $f_{n+1}\circ\cdots\circ f_m$, with $f_{n,n} = \mathrm{id}_{A_n}$.
A *morphism of towers* $u\colon A_\bullet \to B_\bullet$ is a family of homomorphisms $u_n\colon A_n \to B_n$ with $u_n \circ f_{n+1} = g_{n+1}\circ u_{n+1}$ for every n, where $g_\bullet$ denotes the transition maps of $B_\bullet$. Towers and their morphisms form an abelian category, in which kernels, cokernels, images and exactness are all computed degreewise.

That the category is abelian with everything computed degreewise is what makes the section possible: a sequence of towers is exact exactly when each of its levels is exact, so the hypotheses of every result below can be checked one group at a time. The limit itself is the group of coherent families, and the observation that turns it into something derivable is that this group is the kernel of a single explicit map.

Definition 58.5.2: The Limit and $\varprojlim^1$ of a Tower

Let $A_\bullet$ be a tower of abelian groups. Define

$$d^A\colon \prod_{n\geq 0} A_n \to \prod_{n\geq 0} A_n, \qquad d^A\big((a_n)_n\big) = \big(a_n - f_{n+1}(a_{n+1})\big)_n$$

The *limit* of the tower is $\varprojlim A_\bullet := \ker d^A$, and the *first derived functor of the limit* is

$$\varprojlim{}^1 A_\bullet := \operatorname{coker} d^A$$

Both are functors from towers to abelian groups: a morphism $u\colon A_\bullet \to B_\bullet$ induces $\prod u_n$ on products, and $d^B \circ \prod u_n = \prod u_n \circ d^A$ because $u_n f_{n+1} = g_{n+1}u_{n+1}$, so $\prod u_n$ carries $\ker d^A$ into $\ker d^B$ and descends to cokernels.

The kernel is the usual object under a different description. An element $(a_n) \in \prod A_n$ lies in $\ker d^A$ precisely when $a_n = f_{n+1}(a_{n+1})$ for every n, which is the condition that the family be compatible with the transition maps; so $\ker d^A$ is the group of coherent sequences, with the projections $\varprojlim A_\bullet \to A_n$

[2]The older literature writes this group $\varprojlim^1$ and calls it the first derived functor of the inverse limit. This series says *limit* and names the shape of the diagram separately, so the notation here is $\varprojlim^1$ and the phrase is "the limit of a tower".

obtained by restricting the product projections. The cokernel measures how far d^A is from being surjective, and the content of the next theorem is that this single group is the entire obstruction to the limit being exact.

Theorem 58.5.3: The Six-Term Sequence of the Limit

Let $0 \to A_\bullet \to B_\bullet \to C_\bullet \to 0$ be a short exact sequence of towers of abelian groups. Then there is an exact sequence

$$0 \to \varprojlim A_\bullet \to \varprojlim B_\bullet \to \varprojlim C_\bullet \xrightarrow{\partial} \varprojlim{}^1 A_\bullet \to \varprojlim{}^1 B_\bullet \to \varprojlim{}^1 C_\bullet \to 0$$

natural in the short exact sequence.

The sequence says two things worth separating. Reading the left half, the limit is left exact but its failure to preserve surjections is entirely accounted for by the connecting map ∂ into $\varprojlim^1 A_\bullet$: if that group vanishes, $\varprojlim B_\bullet \to \varprojlim C_\bullet$ is onto. Reading the right half, the sequence *stops*. There is no seven-term continuation, and proposition 58.5.4 explains why: the higher derived functors are zero, so no further obstruction can appear.

***Proof*:**
Write $P(A) = \prod_{n\geq 0} A_n$ and likewise for B and C, and let $u\colon A_\bullet \to B_\bullet$, $v\colon B_\bullet \to C_\bullet$ be the given morphisms.

Step 1: The two rows are short exact. By definition 58.5.1 exactness of a sequence of towers is checked degreewise, so $0 \to A_n \to B_n \to C_n \to 0$ is exact for every n. A product of short exact sequences of abelian groups is short exact, since kernels, images and surjectivity of a family of maps into a product are all tested coordinatewise (this is the exactness of arbitrary products in R-Mod recorded in lemma 56.1.11). Hence

$$0 \to P(A) \xrightarrow{\prod u_n} P(B) \xrightarrow{\prod v_n} P(C) \to 0$$

is exact, and the same sequence serves as both rows of the diagram below.

Step 2: The squares commute. Take the vertical maps to be d^A, d^B, d^C:

$$\begin{array}{ccccccccc} 0 & \longrightarrow & P(A) & \xrightarrow{\prod u_n} & P(B) & \xrightarrow{\prod v_n} & P(C) & \longrightarrow & 0 \\ & & \downarrow{\scriptstyle d^A} & & \downarrow{\scriptstyle d^B} & & \downarrow{\scriptstyle d^C} & & \\ 0 & \longrightarrow & P(A) & \xrightarrow{\prod u_n} & P(B) & \xrightarrow{\prod v_n} & P(C) & \longrightarrow & 0 \end{array}$$

Commutativity of the left square is the computation already made in definition 58.5.2: for $(a_n) \in P(A)$,

$$d^B\big((u_n(a_n))_n\big) = \big(u_n(a_n) - g_{n+1}(u_{n+1}(a_{n+1}))\big)_n = \big(u_n(a_n) - u_n(f_{n+1}(a_{n+1}))\big)_n$$

using $g_{n+1}u_{n+1} = u_n f_{n+1}$, and the right-hand side is $\prod u_n$ applied to $d^A((a_n))$. The right square is the same computation for v.

Step 3: Apply the snake lemma and identify the terms. Read each of the three vertical maps as a complex concentrated in degrees 0 and 1, so that the diagram of Step 2 is a short exact

sequence of two-term complexes. This is exactly the reading carried out in example 56.1.21(1): for a two-term complex $H^0 = \ker$ and $H^1 = \operatorname{coker}$, and $H^n = 0$ otherwise, so the long exact sequence of theorem 56.1.20 has only six nonzero terms,

$$0 \to \ker d^A \to \ker d^B \to \ker d^C \xrightarrow{\partial} \operatorname{coker} d^A \to \operatorname{coker} d^B \to \operatorname{coker} d^C \to 0$$

The connecting map is the one built in the proof of theorem 56.1.20, by the recipe: given $c \in \ker d^C$, choose $b \in P(B)$ with $\prod v_n(b) = c$, note that $d^B(b)$ has zero image in $P(C)$ and so equals $\prod u_n(a)$ for a unique $a \in P(A)$, and set $\partial(c) := [a] \in \operatorname{coker} d^A$. By definition 58.5.2 the three kernels are $\varprojlim A_\bullet$, $\varprojlim B_\bullet$, $\varprojlim C_\bullet$ and the three cokernels are $\varprojlim{}^1 A_\bullet$, $\varprojlim{}^1 B_\bullet$, $\varprojlim{}^1 C_\bullet$, which is the displayed sequence.

Step 4: Naturality. Let (s,t,r) be a morphism from $0 \to A_\bullet \to B_\bullet \to C_\bullet \to 0$ to a second short exact sequence $0 \to \tilde{A}_\bullet \to \tilde{B}_\bullet \to \tilde{C}_\bullet \to 0$, so $s\colon A_\bullet \to \tilde{A}_\bullet$ and so on, with both squares commuting. Each of s,t,r induces a map on products commuting with the relevant d, by the computation of Step 2, so the four maps other than ∂ are natural for the reason that they are restrictions and quotients of $\prod s_n$, $\prod t_n$, $\prod r_n$.

For ∂, take $c \in \varprojlim C_\bullet$ and run the recipe of Step 3, producing b and a with $\partial(c) = [a]$. Applying s gives $\big[\prod s_n(a)\big]$. Running the recipe instead on $\prod r_n(c)$, one *may* take $\prod t_n(b)$ as the required lift, since $\prod \tilde{v}_n(\prod t_n(b)) = \prod r_n(\prod v_n(b)) = \prod r_n(c)$; and then

$$d^{\tilde{B}}\Big(\prod t_n(b)\Big) = \prod t_n\big(d^B(b)\big) = \prod t_n\Big(\prod u_n(a)\Big) = \prod \tilde{u}_n\Big(\prod s_n(a)\Big)$$

so the unique preimage is $\prod s_n(a)$ and $\tilde{\partial}(\prod r_n(c)) = \big[\prod s_n(a)\big]$ as well. The two agree, and the value does not depend on the lift chosen, that being the well-definedness already established for $\tilde{\partial}$ in the target sequence. Hence the square through ∂ commutes, completing the proof.

The name given to $\operatorname{coker} d^A$ in definition 58.5.2 has so far been unearned: nothing above identifies it with a derived functor in the sense of definition 56.3.5 and the right-derived construction recorded alongside it. The identification is genuine, and it is what permits both the notation and the assertion made after theorem 58.5.3 that the sequence terminates.

Proposition 58.5.4: $\varprojlim{}^1$ Is the First Derived Functor of the Limit

The category of towers of abelian groups has enough injectives, and the functor $\varprojlim$ is left exact. Writing $R^n \varprojlim$ for its right derived functors,

$$R^0 \varprojlim \cong \varprojlim, \qquad R^1 \varprojlim \cong \varprojlim{}^1, \qquad R^n \varprojlim = 0 \text{ for } n \geq 2$$

***Proof Key ideas*:**
Two ingredients are used here and not proved: that the category of towers has enough injectives, and that the right derived functors of $\varprojlim$ are computed by the two-term complex

$$P(A) \xrightarrow{d^A} P(A)$$

placed in degrees 0 and 1. Both are established in [101, §3.5]. The deferral is deliberate rather than incidental: constructing the injectives is long, and nothing in this book or in the books citing

this section uses more than the two-term description, which definition 58.5.2 and theorem 58.5.3 give on their own.

Granting the two ingredients, the rest is a reading-off. Left exactness of $\varprojlim$ is the left half of theorem 58.5.3, proved above without any of this. The displayed complex has $H^0 = \ker d^A = \varprojlim A_\bullet$ and $H^1 = \operatorname{coker} d^A = \varprojlim{}^1 A_\bullet$ by definition 58.5.2, and it is concentrated in degrees 0 and 1, so $H^n = 0$ for $n \geq 2$. These three groups are the values of $R^0 \varprojlim$, $R^1 \varprojlim$ and $R^n \varprojlim$ for $n \geq 2$, which is the statement.

With the sequence in hand the practical question is when the obstruction vanishes. The condition is not that the transition maps be surjective, which would be too strong to be useful, but that the images they produce inside any fixed level eventually stop shrinking.

Definition 58.5.5: Mittag-Leffler Condition

A tower $A_\bullet$ satisfies the *Mittag-Leffler condition* if for every n the decreasing chain of subgroups

$$A_n = \operatorname{im} f_{n,n} \supseteq \operatorname{im} f_{n,n+1} \supseteq \operatorname{im} f_{n,n+2} \supseteq \cdots$$

is eventually constant: there is an $m_0 \geq n$ with $\operatorname{im} f_{n,m} = \operatorname{im} f_{n,m_0}$ for all $m \geq m_0$. The common value $A'_n := \bigcap_{m \geq n} \operatorname{im} f_{n,m}$ is the *stable image* in level n.

The condition is deliberately weak. It permits the transition maps to be far from surjective, and it permits the stable image to be a proper subgroup of A_n; it forbids only an infinite strictly decreasing chain of images inside a single level. A tower whose transition maps are all surjective satisfies it with $A'_n = A_n$, and a tower whose transition maps are eventually zero in each level satisfies it with $A'_n = 0$.

Theorem 58.5.6: Mittag-Leffler Vanishing

If a tower $A_\bullet$ of abelian groups satisfies the Mittag-Leffler condition, then $\varprojlim{}^1 A_\bullet = 0$.

***Proof*:**

The claim is that d^A is surjective. Two special cases are treated first, and the general case reduces to them.

Step 1: Surjective transition maps. Suppose every f_{n+1} is surjective, and let $(b_n) \in P(A)$ be given. Set $a_0 := 0$, and having chosen a_n, use surjectivity of f_{n+1} to choose $a_{n+1} \in A_{n+1}$ with $f_{n+1}(a_{n+1}) = a_n - b_n$. Then

$$a_n - f_{n+1}(a_{n+1}) = a_n - (a_n - b_n) = b_n$$

for every n, so $d^A((a_n)) = (b_n)$ and d^A is surjective.

Step 2: Transition maps eventually zero in each level. Suppose instead that for each n there is an $m_1 \geq n$ with $f_{n,m} = 0$ for all $m \geq m_1$. Given $(b_n) \in P(A)$, the sum

$$a_n := \sum_{k \geq n} f_{n,k}(b_k)$$

has only finitely many nonzero terms and so defines an element of A_n. Since $f_{n+1} \circ f_{n+1,k} = f_{n,k}$

for $k \geq n+1$,

$$f_{n+1}(a_{n+1}) = \sum_{k \geq n+1} f_{n,k}(b_k) = a_n - f_{n,n}(b_n) = a_n - b_n$$

so again $a_n - f_{n+1}(a_{n+1}) = b_n$ and d^A is surjective.

Step 3: The general Mittag-Leffler case. Let A'_n be the stable image of definition 58.5.5, and let $m_0(n)$ be an index with $\mathrm{im} f_{n,m} = A'_n$ for all $m \geq m_0(n)$. The subgroups A'_n form a subtower: for $m \geq n+1$ one has $f_{n+1}(\mathrm{im} f_{n+1,m}) = \mathrm{im} f_{n,m}$, so $f_{n+1}(A'_{n+1}) \subseteq \bigcap_{m \geq n+1} \mathrm{im} f_{n,m} = A'_n$.

That subtower has surjective transition maps. Let $x \in A'_n$ and choose $m \geq \max\{m_0(n), m_0(n+1)\}$. Since $x \in \mathrm{im} f_{n,m}$ there is $z \in A_m$ with $f_{n,m}(z) = x$; put $y := f_{n+1,m}(z)$. Then $y \in \mathrm{im} f_{n+1,m} = A'_{n+1}$ because $m \geq m_0(n+1)$, and $f_{n+1}(y) = f_{n+1}(f_{n+1,m}(z)) = f_{n,m}(z) = x$. So $f_{n+1} \colon A'_{n+1} \to A'_n$ is onto, and Step 1 gives $\varprojlim{}^1 A'_\bullet = 0$.

The quotient tower $(A_n/A'_n)_n$ has transition maps that are eventually zero in each level: for $m \geq m_0(n)$ the image of $A_m/A'_m \to A_n/A'_n$ is $(\mathrm{im} f_{n,m} + A'_n)/A'_n = A'_n/A'_n = 0$. So Step 2 gives $\varprojlim{}^1(A_\bullet/A'_\bullet) = 0$.

Now apply theorem 58.5.3 to the short exact sequence of towers $0 \to A'_\bullet \to A_\bullet \to A_\bullet/A'_\bullet \to 0$, which is exact degreewise by construction. Its last three terms read

$$\varprojlim{}^1 A'_\bullet \to \varprojlim{}^1 A_\bullet \to \varprojlim{}^1 (A_\bullet/A'_\bullet) \to 0$$

with the two outer groups zero, so $\varprojlim{}^1 A_\bullet = 0$, completing the proof.

Corollary 58.5.7: Surjective Towers Have Vanishing $\varprojlim^1$

If every transition map of a tower $A_\bullet$ is surjective, then $\varprojlim{}^1 A_\bullet = 0$. Consequently, for a short exact sequence of towers $0 \to A_\bullet \to B_\bullet \to C_\bullet \to 0$ in which $A_\bullet$ has surjective transition maps, the sequence of limits

$$0 \to \varprojlim A_\bullet \to \varprojlim B_\bullet \to \varprojlim C_\bullet \to 0$$

is exact.

***Proof*:**
A surjective tower satisfies the Mittag-Leffler condition with $A'_n = A_n$, so theorem 58.5.6 applies; equivalently this is Step 1 of that proof on its own. Substituting $\varprojlim{}^1 A_\bullet = 0$ into theorem 58.5.3 makes the connecting map ∂ land in the zero group, so the first four terms of the six-term sequence give the displayed short exact sequence, as we sought to show.

The corollary is the form in which the result is usually met, and it is the statement proved directly, without the surrounding theory, in proposition 25.1.3, where it is what makes completion along a surjective system an exact operation. The theory developed here names the group that appears once the surjectivity hypothesis is dropped: the cokernels left unlabelled in that argument are the $\varprojlim^1$ terms.

Example 58.5.8: The Tower of Residue Rings $\mathbb{Z}/p^n\mathbb{Z}$

Fix a prime p and let $T_\bullet$ be the tower $T_n = \mathbb{Z}/p^n\mathbb{Z}$ with transition maps the natural reductions $\mathbb{Z}/p^{n+1}\mathbb{Z} \twoheadrightarrow \mathbb{Z}/p^n\mathbb{Z}$ (so $T_0 = 0$). A coherent family is a sequence of residues agreeing under reduction, which is precisely a p-adic integer, so

$$\varprojlim T_\bullet = \mathbb{Z}_p$$

Every transition map is surjective, so corollary 58.5.7 gives $\varprojlim^1 T_\bullet = 0$. This is the typical situation: the obstruction is absent and the limit behaves as expected.

The next example shows that the obstruction is not always absent, and that it can be large. It is worth working through, because a reader who meets only towers with surjective transition maps will reasonably conclude that $\varprojlim^1$ is a formality.

Example 58.5.9: A Tower With Nonvanishing $\varprojlim^1$

Keep p fixed and let $S_\bullet$ be the tower of subgroups $S_n = p^n\mathbb{Z} \subseteq \mathbb{Z}$, with transition maps the inclusions $p^{n+1}\mathbb{Z} \hookrightarrow p^n\mathbb{Z}$. Rescaling by $p^n\mathbb{Z} \cong \mathbb{Z}$ identifies $S_\bullet$ with the tower

$$\mathbb{Z} \xleftarrow{p} \mathbb{Z} \xleftarrow{p} \mathbb{Z} \xleftarrow{p} \cdots$$

Mittag-Leffler fails: inside $S_n = p^n\mathbb{Z}$ the image $\operatorname{im} f_{n,m}$ is $p^m\mathbb{Z}$, and these subgroups shrink strictly as m grows, so the chain in definition 58.5.5 is never constant. The limit vanishes, since $\varprojlim S_\bullet \subseteq \bigcap_{n\geq 0} p^n\mathbb{Z} = 0$.

To compute $\varprojlim^1 S_\bullet$, let $\underline{\mathbb{Z}}$ denote the constant tower with $\underline{\mathbb{Z}}_n = \mathbb{Z}$ and all transition maps the identity, and let $T_\bullet$ be the tower of example 58.5.8. The quotient maps $\mathbb{Z} \to \mathbb{Z}/p^n\mathbb{Z}$ assemble into a short exact sequence of towers

$$0 \to S_\bullet \to \underline{\mathbb{Z}} \to T_\bullet \to 0$$

exact in each level because $p^n\mathbb{Z}$ is the kernel of $\mathbb{Z} \to \mathbb{Z}/p^n\mathbb{Z}$, and compatible with the transition maps by construction. The identity transition maps of $\underline{\mathbb{Z}}$ are surjective, so $\varprojlim \underline{\mathbb{Z}} = \mathbb{Z}$ and $\varprojlim^1 \underline{\mathbb{Z}} = 0$ by corollary 58.5.7; and $\varprojlim T_\bullet = \mathbb{Z}_p$ with $\varprojlim^1 T_\bullet = 0$ by example 58.5.8. Feeding all of this into theorem 58.5.3 leaves

$$0 \to 0 \to \mathbb{Z} \to \mathbb{Z}_p \xrightarrow{\partial} \varprojlim{}^1 S_\bullet \to 0 \to 0 \to 0$$

where the map $\mathbb{Z} \to \mathbb{Z}_p$ is the canonical inclusion. Exactness identifies ∂ as a surjection whose kernel is the image of $\mathbb{Z}$, so

$$\varprojlim{}^1 S_\bullet \cong \mathbb{Z}_p/\mathbb{Z}$$

This is nonzero, and not by a small margin: $\mathbb{Z}_p$ is uncountable while $\mathbb{Z}$ is countable, so the quotient is uncountable. The failure of $\varprojlim$ to be exact on this sequence is exactly the failure of the inclusion $\mathbb{Z} \hookrightarrow \mathbb{Z}_p$ to be onto.

Exercise 58.5.1

1. Let A be an abelian group and $\underline{A}$ the constant tower with every level A and every transition map the identity. Compute $\varprojlim \underline{A}$ and $\varprojlim^1 \underline{A}$ directly from definition 58.5.2, without invoking corollary 58.5.7, by exhibiting a solution of $d^{\underline{A}}((a_n)) = (b_n)$ for an arbitrary (b_n).

2. Show that a tower in which every A_n is a finite group satisfies the Mittag-Leffler condition, and conclude that $\varprojlim^1 A_\bullet = 0$. Where does the argument fail for a tower of finitely generated abelian groups?

3. Give a morphism of towers $u\colon B_\bullet \to C_\bullet$ that is surjective in every level but for which $\varprojlim B_\bullet \to \varprojlim C_\bullet$ is not surjective. Name the group in theorem 58.5.3 that receives the resulting obstruction, and say which tower it is computed from.

4. Let $A_\bullet$ be a tower and let $A_\bullet^{(2)}$ be the tower $A_0 \leftarrow A_2 \leftarrow A_4 \leftarrow \cdots$ obtained by keeping the even levels and composing transition maps in pairs. Show that $\varprojlim A_\bullet \cong \varprojlim A_\bullet^{(2)}$ and that $A_\bullet$ satisfies the Mittag-Leffler condition if and only if $A_\bullet^{(2)}$ does.

5. Let $A_\bullet$ be the tower of subgroups $A_n = (n!)\mathbb{Z} \subseteq \mathbb{Z}$ with the inclusions as transition maps, so that rescaling identifies it with $\mathbb{Z} \xleftarrow{1} \mathbb{Z} \xleftarrow{2} \mathbb{Z} \xleftarrow{3} \cdots$, the n-th transition map being multiplication by n. Show that Mittag-Leffler fails and that $\varprojlim A_\bullet = 0$, then run the argument of example 58.5.9 with $\mathbb{Z}/(n!)\mathbb{Z}$ in place of $\mathbb{Z}/p^n\mathbb{Z}$ to compute $\varprojlim^1 A_\bullet$. The limit of the quotient tower is the profinite completion $\widehat{\mathbb{Z}}$ rather than $\mathbb{Z}_p$; say which property of the sequence $(n!)$ is responsible, and give $\varprojlim^1 A_\bullet$ itself.

6. In the situation of example 58.5.9, make the connecting map $\partial\colon \mathbb{Z}_p \to \varprojlim^1 S_\bullet$ explicit by running the construction of ∂ from theorem 58.5.3: given a p-adic integer presented as a coherent family of residues, produce a representative in $\prod_n S_n$ of the class it maps to, and check that the class does not depend on the lifts chosen.

59

Unbounded Derived Categories and t-Structures

The derived functors of chapter 57 are defined on complexes bounded on one side, bounded below for RF and for the second variable of $R\mathrm{Hom}$ and bounded above for LF and $\otimes^L$, because the injective and projective resolutions that compute them are bounded on that side. For a bounded-below complex I of injectives the map $Q\colon \mathrm{Hom}_{\mathrm{K}}(X, I) \to \mathrm{Hom}_D(X, I)$ is bijective for every complex X (lemma 57.4.4(2)), and without the bound this fails. The complex of $\mathbb{Z}/4$-modules with $\mathbb{Z}/4$ in every degree and every differential multiplication by 2 consists of injectives and is exact, yet its identity is not null-homotopic (example 59.1.7). The K-injective and K-flat complexes of Spaltenstein [95] are resolutions that need no bound. With them the right derived functor of an additive functor out of a Grothendieck abelian category, and $R\mathrm{Hom}$ and $\otimes^L$ over a commutative ring, extend to unbounded complexes, and the tensor-Hom adjunction of theorem 57.4.19 holds for the extended functors.

The second half answers the question of box 57.2.13, what in $D(\mathcal{A})$ recovers $\mathcal{A}$. The canonical truncations of definition 56.1.12 descend to $D(\mathcal{A})$. There they cut out the full subcategories of complexes with cohomology in degrees at most 0 and at least 0, and every complex sits in a distinguished triangle whose first vertex lies in the first subcategory and whose third vertex has cohomology in degrees at least 1. The complexes in both subcategories, those with cohomology concentrated in degree 0, form a full subcategory equivalent to $\mathcal{A}$. The axioms satisfied by the two halves define the t-structures of Beilinson, Bernstein and Deligne [8], and the heart of every t-structure is an abelian category.

59.1 Grothendieck Abelian Categories and K-Injective Resolutions

A bounded-below complex of injectives I computes the morphisms into it in the derived category: by lemma 57.4.4(2) the map $Q\colon \mathrm{Hom}_{\mathrm{K}(\mathcal{A})}(X, I) \to \mathrm{Hom}_{D(\mathcal{A})}(X, I)$ is bijective for every complex X. Without the bound this fails already for a complex of injective $\mathbb{Z}/4$-modules (example 59.1.7), and the same terms $\mathbb{Z}/4$ carry a second complex for which it holds (example 59.1.10). The replacement for the bound is therefore a condition on the complex as a whole, K-injectivity [95]. Over a Grothendieck abelian category, such as the category of modules over a ring or of sheaves of modules on a ringed site, every complex has a K-injective resolution. With these resolutions the Hom-classes of $D(\mathcal{A})$ are sets, and every additive functor has a right derived functor on all of $D(\mathcal{A})$, which for a left exact functor agrees on bounded-below complexes with the total derived functor of section 57.3.

Grothendieck's construction of injective objects, and its extension to K-injective complexes, produce them as colimits of transfinite sequences of monomorphisms, and both arguments need colimits over directed index sets to preserve exactness ([98, Tag 079H], [98, Tag 079P]).

Definition 59.1.1: Directed System and Its Colimit

A *directed poset* is a nonempty partially ordered set I in which any two elements have a common upper bound. Let $\mathcal{C}$ be a category. A *directed system* over I in $\mathcal{C}$ is a family of objects $(A_i)_{i\in I}$ with morphisms $\varphi_{ij}\colon A_i \to A_j$ for $i \le j$, such that $\varphi_{ii} = \mathrm{id}$ and $\varphi_{jk}\varphi_{ij} = \varphi_{ik}$ whenever $i \le j \le k$. A *morphism* $f\colon (A_i, \varphi_{ij}) \to (B_i, \psi_{ij})$ of directed systems over I is a family of morphisms $f_i\colon A_i \to B_i$ with $f_j\varphi_{ij} = \psi_{ij}f_i$ for $i \le j$.

A *colimit* of (A_i, φ_{ij}) is an object $\varinjlim_i A_i$ with morphisms $\lambda_i\colon A_i \to \varinjlim_i A_i$ satisfying $\lambda_j\varphi_{ij} = \lambda_i$, such that for every object T and every family $t_i\colon A_i \to T$ with $t_j\varphi_{ij} = t_i$ there is a unique $t\colon \varinjlim_i A_i \to T$ with $t\lambda_i = t_i$ for all i.

The simplest directed systems are increasing unions, and for them the colimit is the union.

Example 59.1.2: An Increasing Union of Submodules

Let M be an R-module and $(M_i)_{i\in I}$ a family of submodules indexed by a directed poset, with $M_i \subseteq M_j$ for $i \le j$ and $\bigcup_i M_i = M$. With the inclusions as φ_{ij} this is a directed system, and M with the inclusions $\lambda_i\colon M_i \to M$ is its colimit. Given a compatible family $t_i\colon M_i \to T$, define $t(x) := t_i(x)$ for any i with $x \in M_i$. This does not depend on i: if $x \in M_i \cap M_j$, choose $k \ge i, j$, and compatibility gives $t_i(x) = t_k(x) = t_j(x)$. Two elements x, y lie in a common M_k, so $t(rx + y) = t_k(rx + y) = rt(x) + t(y)$ and t is a homomorphism, with $t\lambda_i = t_i$. It is the only one, since every element of M lies in some M_i.

For instance $\mathbb{Q} = \bigcup_{n\ge 0} \frac{1}{n!}\mathbb{Z}$, an increasing union since $\frac{1}{n!}\mathbb{Z} \subseteq \frac{1}{(n+1)!}\mathbb{Z}$, and every p/q with $q \ge 1$ equals $p(q-1)!/q!$. Multiplication by $n!$ identifies $\frac{1}{n!}\mathbb{Z}$ with $\mathbb{Z}$, and under these identifications the inclusion $\frac{1}{n!}\mathbb{Z} \subseteq \frac{1}{(n+1)!}\mathbb{Z}$ becomes multiplication by $n+1$ on $\mathbb{Z}$. So $\mathbb{Q}$ is the colimit of $\mathbb{Z} \xrightarrow{1} \mathbb{Z} \xrightarrow{2} \mathbb{Z} \xrightarrow{3} \cdots$, with $\lambda_n(a) = a/n!$.

A morphism f of directed systems induces $\varinjlim f\colon \varinjlim_i A_i \to \varinjlim_i B_i$, the unique morphism with

$(\varinjlim f)\lambda_i^A = \lambda_i^B f_i$. It exists because the family $\lambda_i^B f_i$ is compatible: $\lambda_j^B f_j \varphi_{ij} = \lambda_j^B \psi_{ij} f_i = \lambda_i^B f_i$. In an abelian category with all set-indexed direct sums every directed system has a colimit, the cokernel of the morphism

$$\bigoplus_{i \le j} A_i \longrightarrow \bigoplus_{i \in I} A_i$$

whose restriction to the summand indexed by the pair (i, j) is $e_i - e_j\varphi_{ij}$, where e_i is the inclusion of the summand A_i. A morphism $t\colon \bigoplus_i A_i \to T$ vanishes on this morphism exactly when $te_i = te_j\varphi_{ij}$ for all $i \le j$, that is, when $(te_i)_i$ is a compatible family. So the universal properties of the direct sum and of the cokernel combine into that of the colimit, with λ_i the composite of e_i and the projection onto the cokernel.

Proposition 59.1.3: Directed Colimits of Modules Are Exact

Let R be a ring, I a directed poset and (M_i, φ_{ij}) a directed system of R-modules over I.

1. The colimit $\varinjlim_i M_i$ exists. Every element of it is $\lambda_i(x)$ for some $i \in I$ and $x \in M_i$, and $\lambda_i(x) = 0$ if and only if $\varphi_{ik}(x) = 0$ for some $k \ge i$.

2. Let $0 \to A \xrightarrow{f} B \xrightarrow{g} C \to 0$ be morphisms of directed systems of R-modules over I such that $0 \to A_i \to B_i \to C_i \to 0$ is exact for every i. Then the sequence

$$0 \to \varinjlim_i A_i \xrightarrow{\varinjlim f} \varinjlim_i B_i \xrightarrow{\varinjlim g} \varinjlim_i C_i \to 0$$

   is exact.

***Proof*:**

1. The category of R-modules has direct sums, so the colimit is the quotient $(\bigoplus_i M_i)/N$, where N is the submodule generated by the elements $e_i(x) - e_j(\varphi_{ij}x)$ for $i \le j$ and $x \in M_i$. An element of the quotient is a finite sum $\sum_{r=1}^{s} \lambda_{i_r}(x_r)$. As I is directed, induction on s gives $k \in I$ with $k \ge i_1, \dots, i_s$, and then $\lambda_{i_r}(x_r) = \lambda_k\varphi_{i_r k}(x_r)$, so the sum is $\lambda_k\big(\sum_r \varphi_{i_r k}(x_r)\big)$. If $\varphi_{ik}(x) = 0$ then $\lambda_i(x) = \lambda_k\varphi_{ik}(x) = 0$.

   Conversely let $\lambda_i(x) = 0$, that is, $e_i(x) \in N$. The generators are closed under multiplication by scalars, since $r\big(e_a(y) - e_b(\varphi_{ab}y)\big) = e_a(ry) - e_b(\varphi_{ab}(ry))$, so

$$e_i(x) = \sum_{r=1}^{s} \big(e_{a_r}(y_r) - e_{b_r}(\varphi_{a_r b_r} y_r)\big)$$

   with $a_r \le b_r$. Let J be the finite set $\{i, a_1, b_1, \dots, a_s, b_s\}$ and choose an upper bound k of J. Both sides of the equation lie in the summand $\bigoplus_{j \in J} M_j$, on which $\psi(e_j(z)) := \varphi_{jk}(z)$ defines a homomorphism ψ to M_k. For $a \le b$ in J, $\psi\big(e_a(y) - e_b(\varphi_{ab}y)\big) = \varphi_{ak}(y) - \varphi_{bk}\varphi_{ab}(y) = 0$, so applying ψ to the equation gives $\varphi_{ik}(x) = 0$.

2. Write φ, ψ, χ for the transition maps of A, B, C, and use (1) to write every element of a colimit as $\lambda_i(x)$ for some i and x. If $(\varinjlim f)(\lambda_i a) = \lambda_i(f_i a) = 0$, then (1) gives $k \ge i$ with $0 = \psi_{ik}f_i(a) = f_k\varphi_{ik}(a)$. As f_k is injective, $\varphi_{ik}(a) = 0$ and $\lambda_i(a) = 0$, so $\varinjlim f$ is injective.

Every $\lambda_i(c)$ is $\lambda_i(g_i b) = (\varinjlim g)(\lambda_i b)$ for some $b \in B_i$, so $\varinjlim g$ is surjective. The composite $(\varinjlim g)(\varinjlim f)$ satisfies $(\varinjlim g)(\varinjlim f)\lambda_i = \lambda_i g_i f_i = 0$ for every i, so it is 0 by the uniqueness in the universal property. Finally let $(\varinjlim g)(\lambda_i b) = \lambda_i(g_i b) = 0$. By (1) there is $k \geq i$ with $0 = \chi_{ik} g_i(b) = g_k \psi_{ik}(b)$, so $\psi_{ik}(b) = f_k(a)$ for some $a \in A_k$, by exactness at B_k. Then $\lambda_i(b) = \lambda_k \psi_{ik}(b) = \lambda_k f_k(a) = (\varinjlim f)(\lambda_k a)$, which is exactness at $\varinjlim_i B_i$ and completes the proof.

Directedness enters (2) through (1): a common upper bound k places two elements of a colimit in a single M_k, where they can be compared. The three properties of R-Mod that Grothendieck's axioms abstract are arbitrary direct sums, the exactness of proposition 59.1.3(2), and an object detecting nonzero morphisms. For the last, a homomorphism $f\colon M \to N$ is nonzero exactly when $f(m) \neq 0$ for some m, that is, when $f \circ u \neq 0$ for the map $u\colon R \to M$, $r \mapsto rm$.

Definition 59.1.4: Grothendieck Abelian Category

An abelian category $\mathcal{A}$ is a *Grothendieck abelian category* if it satisfies the following.

(AB3) Every family $(A_t)_{t \in T}$ of objects indexed by a set has a direct sum $\bigoplus_t A_t$.

(AB5) Colimits over directed posets are exact: for every directed poset I and all morphisms of directed systems $0 \to A \to B \to C \to 0$ over I such that $0 \to A_i \to B_i \to C_i \to 0$ is exact for every i, the sequence $0 \to \varinjlim_i A_i \to \varinjlim_i B_i \to \varinjlim_i C_i \to 0$ is exact.

(G) There is a *generator*: an object U such that for every nonzero morphism $f\colon X \to Y$ there is a morphism $u\colon U \to X$ with $fu \neq 0$.

The colimits in (AB5) exist by (AB3), as the cokernel of the morphism $\bigoplus_{i \leq j} A_i \to \bigoplus_{i \in I} A_i$ with components $e_i - e_j \varphi_{ij}$. This is the definition of [98, Tag 079B], whose discussion of (AB5) states the exactness condition for systems over a directed set, as here. The generator there is required to satisfy the following: for every subobject $N \subseteq M$ with $N \neq M$ some morphism $U \to M$ does not factor through N. The two forms agree. Given such N, apply (G) to the nonzero quotient $f\colon M \to M/N$, and note that $u\colon U \to M$ factors through $N = \ker f$ exactly when $fu = 0$. Given a nonzero $f\colon X \to Y$, apply the subobject form to $\ker f \neq X$.

Example 59.1.5: Module and Sheaf Categories

1. For a ring R the category R-Mod is a Grothendieck abelian category. Direct sums give (AB3), proposition 59.1.3(2) is (AB5), and R is a generator: if $f\colon M \to N$ is nonzero, choose m with $f(m) \neq 0$ and let $u\colon R \to M$ be $r \mapsto rm$. Then $fu(1) = f(m) \neq 0$.
2. For a ringed site $(\mathcal{C}, \mathcal{O})$, the category of $\mathcal{O}$-modules is a Grothendieck abelian category [98, Tag 07A5]. For the constant sheaf of rings $\mathbb{Z}$ its objects are the sheaves of abelian groups on $\mathcal{C}$, and for $\mathcal{C}$ the open sets of a topological space they are the sheaves of abelian groups on the space.

The axioms of definition 59.1.4 are Grothendieck's, from the paper in which he proved that injective objects exist in this generality [98, Tag 079A]. In the proof the generator plays the role that the ring plays in Baer's criterion (theorem 17.3.5), and its subobjects the role of the ideals.

Theorem 59.1.6: Grothendieck Abelian Categories Have Enough Injectives

Let $\mathcal{A}$ be a Grothendieck abelian category. There are a functor $E\colon \mathcal{A} \to \mathcal{A}$ and a natural transformation $\upsilon\colon \mathrm{id} \to E$ such that for every object M the morphism $\upsilon_M\colon M \to E(M)$ is a monomorphism and $E(M)$ is injective. In particular $\mathcal{A}$ has enough injectives (definition 56.2.3).

The proof is a transfinite construction that uses nothing from homological algebra beyond (AB5) and the generator, and it is deferred to [98, Tag 079H].

***Proof Key ideas*:**
Fix a generator U. The replacement for Baer's criterion is [98, Tag 079G]: an object is injective if every morphism into it from a subobject $N \subseteq U$ extends to U. For an object M, form the pushout $\mathbf{M}(M)$ of $M \leftarrow \bigoplus N \to \bigoplus U$, the sums running over all pairs of a subobject $N \subseteq U$ and a morphism $\varphi\colon N \to M$. Then every such φ extends to $U \to \mathbf{M}(M)$, and $M \to \mathbf{M}(M)$ is a monomorphism. Iterate transfinitely, taking colimits at limit ordinals, up to an ordinal whose cofinality exceeds the cardinality of the set of subobjects of U. A morphism from a subobject of U into the final stage then factors through an earlier stage, by (AB5) and that cardinality bound [98, Tag 079F], and so extends to U. The criterion makes the final stage injective, and every step is functorial in M, which gives E and υ as claimed.

For R-Mod, through example 59.1.5(1), the theorem gives enough injectives over an arbitrary ring, together with injective embeddings compatible with homomorphisms.

When the category is fixed, $\mathrm{Hom}_{\mathrm{K}}$ and Hom_D abbreviate $\mathrm{Hom}_{\mathrm{K}(\mathcal{A})}$ and $\mathrm{Hom}_{D(\mathcal{A})}$. Recall from lemma 56.1.19 that a complex is acyclic, meaning that its cohomology vanishes, exactly when it is exact.

Example 59.1.7: An Exact Complex of Injectives That Is Not Contractible
Let I be the complex of $\mathbb{Z}/4$-modules with $I^n = \mathbb{Z}/4$ for every $n \in \mathbb{Z}$ and every differential multiplication by 2.

1. $\mathbb{Z}/4$ is an injective $\mathbb{Z}/4$-module. By theorem 17.3.5(1) it suffices to extend homomorphisms from the ideals 0, $2\mathbb{Z}/4$ and $\mathbb{Z}/4$ to $\mathbb{Z}/4$, and only $2\mathbb{Z}/4 = \{0, 2\}$ needs an argument. A homomorphism $g\colon 2\mathbb{Z}/4 \to \mathbb{Z}/4$ satisfies $2g(2) = g(4) = g(0) = 0$, so $g(2) \in \{0, 2\}$. If $g(2) = 0$ then g extends by 0, and if $g(2) = 2$ it extends by the identity of $\mathbb{Z}/4$.
2. I is exact: the kernel and the image of multiplication by 2 on $\mathbb{Z}/4$ are both $\{0, 2\}$.
3. id_I is not null-homotopic. Every $\mathbb{Z}/4$-linear endomorphism of $\mathbb{Z}/4$ is multiplication by its value at 1, so a family $s^n\colon I^n \to I^{n-1}$ consists of multiplications by elements $a_n \in \mathbb{Z}/4$. Then $d^{n-1}s^n + s^{n+1}d^n$ is multiplication by $2a_n + 2a_{n+1}$, which sends 1 into $\{0, 2\}$ and so is never the identity.

So id_I is a nonzero element of $\mathrm{Hom}_{\mathrm{K}(\mathbb{Z}/4\text{-Mod})}(I, I)$. But I is exact, hence isomorphic to 0 in $D(\mathbb{Z}/4\text{-Mod})$ by proposition 57.2.12(1), and $\mathrm{Hom}_{D(\mathbb{Z}/4\text{-Mod})}(I, I) = 0$. The map $Q\colon \mathrm{Hom}_{\mathrm{K}}(I, I) \to \mathrm{Hom}_D(I, I)$ is not injective, and the conclusion of lemma 57.4.4(2) fails for this complex of injectives.

The defect in the example is a nonzero homotopy class of maps from an acyclic complex into I,

namely id_I.

Definition 59.1.8: K-Injective Complex

Let $\mathcal{A}$ be an abelian category. A complex $I \in \mathrm{Ch}(\mathcal{A})$ is *K-injective* if $\mathrm{Hom}_{\mathrm{K}(\mathcal{A})}(X, I) = 0$ for every acyclic complex X. A *K-injective resolution* of a complex X is a quasi-isomorphism $X \to I$ with I K-injective.

This is [98, Tag 070H]. The complex of example 59.1.7 is not K-injective, since id_I is a nonzero element of $\mathrm{Hom}_{\mathrm{K}}(I, I)$ with I acyclic.

Lemma 59.1.9: Shifts of K-Injective Complexes

Let $\mathcal{A}$ be an abelian category and $I \in \mathrm{Ch}(\mathcal{A})$ a K-injective complex. Then $I[n]$ is K-injective for every $n \in \mathbb{Z}$.

***Proof*:**
Let X be an acyclic complex. By (57.1) the shift $[-n]$ is an automorphism of $\mathrm{K}(\mathcal{A})$ inverse to $[n]$, so $f \mapsto f[-n]$ is a bijection from $\mathrm{Hom}_{\mathrm{K}}(X, I[n])$ to $\mathrm{Hom}_{\mathrm{K}}(X[-n], I)$. The complex $X[-n]$ is acyclic, since $H^i(X[-n]) = H^{i-n}(X) = 0$ by (57.1), and I is K-injective, so $\mathrm{Hom}_{\mathrm{K}}(X[-n], I) = 0$. Hence $\mathrm{Hom}_{\mathrm{K}}(X, I[n]) = 0$, as we sought to show.

By lemma 57.4.3(1), $H^n\mathrm{Hom}^\bullet(X, I) = \mathrm{Hom}_{\mathrm{K}}(X, I[n])$, so with the lemma I is K-injective exactly when the Hom complex $\mathrm{Hom}^\bullet(X, I)$ is acyclic for every acyclic X. This is the definition of [95, p. 1.1], which credits it to J. Bernstein.

Example 59.1.10: Complexes of Injectives With Zero Differential

Let $(E_n)_{n\in\mathbb{Z}}$ be injective objects of $\mathcal{A}$ and E the complex with $E^n = E_n$ and every differential zero. For every complex X,

$$\mathrm{Hom}_{\mathrm{K}(\mathcal{A})}(X, E) \cong \prod_{n\in\mathbb{Z}} \mathrm{Hom}_{\mathcal{A}}\big(H^n(X), E_n\big)$$

and in particular E is K-injective.

Write $Z^n = \ker d_X^n$ and $B^n = \mathrm{im} d_X^{n-1}$. A chain map $f\colon X \to E$ is a family $f^n\colon X^n \to E_n$ with $f^{n+1}d_X^n = 0 \circ f^n = 0$, so each f^n vanishes on B^n, and the chain maps are $\prod_n \mathrm{Hom}(X^n/B^n, E_n)$. A null-homotopy s has $f^n = 0 \circ s^n + s^{n+1}d_X^n = s^{n+1}d_X^n$ with $s^{n+1}\colon X^{n+1} \to E_n$. The differential d_X^n factors as $X^n \to X^n/Z^n \cong B^{n+1} \hookrightarrow X^{n+1}$, and since E_n is injective, $\mathrm{Hom}(X^{n+1}, E_n) \to \mathrm{Hom}(B^{n+1}, E_n)$ is surjective (definition 56.2.1). So the maps of the form $s^{n+1}d_X^n$ are exactly those factoring through $X^n \to X^n/Z^n$, that is, $\mathrm{Hom}(X^n/Z^n, E_n)$. Applying the exact functor $\mathrm{Hom}(-, E_n)$ to

$$0 \to H^n(X) = Z^n/B^n \to X^n/B^n \to X^n/Z^n \to 0$$

identifies $\mathrm{Hom}(X^n/B^n, E_n)/\mathrm{Hom}(X^n/Z^n, E_n)$ with $\mathrm{Hom}(H^n(X), E_n)$, by restriction. Over $\mathbb{Z}/4$ with every $E_n = \mathbb{Z}/4$, injective by example 59.1.7(1), this complex is K-injective, while the complex of example 59.1.7 has the same terms and differential 2 and is not.

Proposition 59.1.11: K-Injective Complexes Compute Morphisms in $D(\mathcal{A})$

Let $\mathcal{A}$ be an abelian category and $I \in \mathrm{Ch}(\mathcal{A})$. The following are equivalent.

1. I is K-injective.
2. For every quasi-isomorphism $s\colon X' \to X$ the map $s^*\colon \mathrm{Hom}_{\mathrm{K}}(X, I) \to \mathrm{Hom}_{\mathrm{K}}(X', I)$, $f \mapsto fs$, is bijective.
3. For every complex X the map $Q\colon \mathrm{Hom}_{\mathrm{K}}(X, I) \to \mathrm{Hom}_{D}(X, I)$ is bijective.

***Proof*:**

(1) implies (2). By theorem 57.1.12 the mapping cone triangle $X' \xrightarrow{s} X \xrightarrow{v} MC(s) \xrightarrow{w} X'[1]$ is distinguished in $\mathrm{K}(\mathcal{A})$, and by (TR2) so is $\big(-w[-1], s, v\big)$ on $(MC(s)[-1], X', X)$. The complex $MC(s)$ is acyclic by proposition 56.1.26, and so is $MC(s)[-1]$. The functor $\mathrm{Hom}_{\mathrm{K}}(-, I)$ is cohomological by proposition 57.1.8, and applied to the two triangles it gives sequences

$$\mathrm{Hom}_{\mathrm{K}}(MC(s), I) \xrightarrow{v^*} \mathrm{Hom}_{\mathrm{K}}(X, I) \xrightarrow{s^*} \mathrm{Hom}_{\mathrm{K}}(X', I) \xrightarrow{(-w[-1])^*} \mathrm{Hom}_{\mathrm{K}}(MC(s)[-1], I)$$

exact at $\mathrm{Hom}_{\mathrm{K}}(X, I)$ and at $\mathrm{Hom}_{\mathrm{K}}(X', I)$. The two outer groups vanish because I is K-injective, so s^* is injective and surjective.

(2) implies (3). By theorem 57.2.4 a morphism $X \to I$ of $D(\mathcal{A})$ is $Q(f)Q(s)^{-1}$ for a roof (X', s, f), with $s\colon X' \to X$ a quasi-isomorphism. By (2), $f = gs$ in $\mathrm{K}(\mathcal{A})$ for some $g\colon X \to I$, and then $Q(f)Q(s)^{-1} = Q(g)$, so Q is surjective. The functor Q is additive by theorem 57.2.7. If $Q(h) = 0$, then proposition 57.2.12(2) gives a quasi-isomorphism $t\colon X'' \to X$ with ht null-homotopic, that is, $t^*(h) = 0$, and the injectivity of t^* gives $h = 0$ in $\mathrm{K}(\mathcal{A})$.

(3) implies (1). An acyclic X is isomorphic to 0 in $D(\mathcal{A})$ by proposition 57.2.12(1), so $\mathrm{Hom}_{D}(X, I) = 0$, and the bijection of (3) gives $\mathrm{Hom}_{\mathrm{K}}(X, I) = 0$, completing the proof.

The equivalence is [98, Tag 070I]. Condition (3) says that the morphisms into a K-injective complex are the same in $D(\mathcal{A})$ as in $\mathrm{K}(\mathcal{A})$, so they need no roofs. For a bounded-below complex of injectives, condition (3) is lemma 57.4.4(2).

Corollary 59.1.12: Bounded-Below Complexes of Injectives Are K-Injective

Let $\mathcal{A}$ be an abelian category. Every bounded-below complex of injective objects of $\mathcal{A}$ is K-injective.

***Proof*:**

For such a complex I, lemma 57.4.4(2) is condition (3) of proposition 59.1.11, as required.

So the injective resolutions of bounded-below complexes used in chapter 57, for instance the resolutions ι_B of definition 57.4.6, are K-injective resolutions. A quasi-isomorphism between bounded-below complexes of injectives is a homotopy equivalence by theorem 56.2.9, and the same holds with the bound replaced by K-injectivity.

Corollary 59.1.13: Quasi-Isomorphisms Between K-Injective Complexes

Let $\mathcal{A}$ be an abelian category.

1. A quasi-isomorphism $s\colon I \to J$ between K-injective complexes is a homotopy equivalence.
2. If $a\colon X \to I$ and $a'\colon X \to I'$ are K-injective resolutions, there is a homotopy equivalence $c\colon I \to I'$ with $ca = a'$ in $\mathrm{K}(\mathcal{A})$, and c is unique up to homotopy with this property.

***Proof*:**

1. By proposition 59.1.11(2) for I, the map $s^*\colon \mathrm{Hom}_{\mathrm{K}}(J, I) \to \mathrm{Hom}_{\mathrm{K}}(I, I)$ is bijective, so there is $t\colon J \to I$ with $ts = \mathrm{id}_I$ in $\mathrm{K}(\mathcal{A})$. Then $(st)s = s = \mathrm{id}_J s$, and $s^*\colon \mathrm{Hom}_{\mathrm{K}}(J, J) \to \mathrm{Hom}_{\mathrm{K}}(I, J)$ is injective by the same proposition for J, so $st = \mathrm{id}_J$ in $\mathrm{K}(\mathcal{A})$ and s is a homotopy equivalence.
2. By proposition 59.1.11(2) for I' and the quasi-isomorphism a, there is a unique class $c \in \mathrm{Hom}_{\mathrm{K}}(I, I')$ with $ca = a'$. Then $H^n(c)H^n(a) = H^n(a')$ with $H^n(a)$ and $H^n(a')$ isomorphisms, so c is a quasi-isomorphism and, by (1), a homotopy equivalence, as claimed.

For a bounded-below complex of injectives I, every quasi-isomorphism $s\colon X \to X'$ induces a quasi-isomorphism $s^*\colon \mathrm{Hom}^\bullet(X', I) \to \mathrm{Hom}^\bullet(X, I)$ of Hom complexes by corollary 57.4.5(1).

Corollary 59.1.14: Hom into a K-Injective Complex Preserves Quasi-Isomorphisms

Let $\mathcal{A}$ be an abelian category, $I \in \mathrm{Ch}(\mathcal{A})$ a K-injective complex and $s\colon X \to X'$ a quasi-isomorphism. Then $s^*\colon \mathrm{Hom}^\bullet(X', I) \to \mathrm{Hom}^\bullet(X, I)$ is a quasi-isomorphism.

***Proof*:**
Fix $n \in \mathbb{Z}$. By lemma 57.4.3(1) and (3), $H^n(s^*)$ is the map $\mathrm{Hom}_{\mathrm{K}}(X', I[n]) \to \mathrm{Hom}_{\mathrm{K}}(X, I[n])$, $\psi \mapsto \psi s$. The complex $I[n]$ is K-injective by lemma 59.1.9, so this map is bijective by proposition 59.1.11(2), as we sought to show.

The existence of K-injective resolutions for modules is Spaltenstein's theorem [95, Proposition 3.11], and its proof runs through the limit of a tower and its first derived functor from section 58.5. A complex X is the limit of the tower of its truncations $\tau^{\geq -n}X$ (example 59.1.16). Each truncation is bounded below and so has a bounded-below injective resolution, and the resolutions can be chosen to form a tower with split surjective transition maps. The limit of that tower is a K-injective resolution of X.

For a tower $A_\bullet$ of R-modules the map d^A of definition 58.5.2 is R-linear, so $\varprojlim A_\bullet$ and $\varprojlim{}^1 A_\bullet$ are R-modules. A homomorphism $M \to \varprojlim A_\bullet$ is the same as a family of homomorphisms $M \to A_n$ compatible with the transition maps, since $\varprojlim A_\bullet = \ker d^A$ is the module of coherent sequences.

Definition 59.1.15: Tower of Complexes and Its Limit

Let R be a ring. A *tower of complexes* of R-modules $C_\bullet = (C_n)_{n\geq 0}$ is a family of complexes C_n with chain maps $q_{n+1}\colon C_{n+1} \to C_n$. For each i the differentials $d^i\colon C_n^i \to C_n^{i+1}$ form a morphism of towers, the q_{n+1} being chain maps, so they induce $\varprojlim_n C_n^i \to \varprojlim_n C_n^{i+1}$ by definition 58.5.2, with square zero. The *limit* $\varprojlim C_\bullet$ is the resulting complex, with $(\varprojlim C_\bullet)^i = \varprojlim_n C_n^i$.

Example 59.1.16: The Tower of Truncations of a Complex

Let X be a complex of R-modules and put $X_n := \tau^{\geq -n}X$ for $n \geq 0$ (definition 56.1.12). Let $r_{n+1}\colon X_{n+1} \to X_n$ be zero in degrees below $-n$, the quotient $X^{-n} \to X^{-n}/B^{-n}$ in degree $-n$, and the identity in degrees above $-n$. It is a chain map: in degree $-n-1$ the differential of X_{n+1} lands in B^{-n}, which the quotient kills, and in degree $-n$ the induced differential of X_n composed with the quotient is d^{-n}. So $X_\bullet$ is a tower of complexes. Comparing degree by degree, the quotient maps $p_{-n}\colon X \to X_n$ satisfy $r_{n+1}p_{-n-1} = p_{-n}$, so they induce a chain map $X \to \varprojlim X_\bullet$. In degree i the maps p^i_{-n} and r^i_{n+1} are identities once $n > -i$, and a coherent sequence in a tower whose transition maps are identities from some index N on is determined by its term of index N. So $X \to \varprojlim X_\bullet$ is an isomorphism in every degree, and X is the limit of its truncations.

The projections $\varprojlim C_\bullet \to C_n$ are chain maps. For each m the groups $H^m(C_n)$ with the maps $H^m(q_{n+1})$ form a tower $H^m(C_\bullet)$.

Lemma 59.1.17: The Cohomology of a Limit of Complexes

Let R be a ring and $(C_n)_{n\geq 0}$ a tower of complexes of R-modules whose transition maps $q^i_{n+1}\colon C^i_{n+1} \to C^i_n$ are surjective for every i and n. Then for every $m \in \mathbb{Z}$ there is an exact sequence

$$0 \to \varprojlim{}^1 H^{m-1}(C_\bullet) \to H^m\big(\varprojlim C_\bullet\big) \to \varprojlim H^m(C_\bullet) \to 0$$

in which the second map is induced by the projections $\varprojlim C_\bullet \to C_n$.

***Proof*:**

Let $P := \prod_n C_n$, the product taken degreewise with the product differential, and let $\delta\colon P \to P$ be $(c_n)_n \mapsto \big(c_n - q_{n+1}(c_{n+1})\big)_n$, the map d^A of definition 58.5.2 for the tower $A_\bullet = C^i_\bullet$ in each degree i. It is a chain map, since the q_{n+1} are, and by definition $\varprojlim C_\bullet = \ker\delta$. The cokernel of δ in degree i is $\varprojlim{}^1 C^i_\bullet$, which vanishes by corollary 58.5.7. So

$$0 \to \varprojlim C_\bullet \to P \xrightarrow{\delta} P \to 0$$

is a short exact sequence of complexes, and theorem 56.1.20 gives the exact sequence

$$H^{m-1}(P) \xrightarrow{H^{m-1}(\delta)} H^{m-1}(P) \xrightarrow{\partial} H^m\big(\varprojlim C_\bullet\big) \to H^m(P) \xrightarrow{H^m(\delta)} H^m(P)$$

Products are exact in R-Mod, so $H^m(P) = \prod_n H^m(C_n)$ by lemma 56.1.11, and under this identification $H^m(\delta)$ is

$$([c_n])_n \longmapsto \big([c_n] - H^m(q_{n+1})[c_{n+1}]\big)_n$$

That is the map d^A of definition 58.5.2 for the tower $H^m(C_\bullet)$, so $\ker H^m(\delta) = \varprojlim H^m(C_\bullet)$, and likewise $\operatorname{coker} H^{m-1}(\delta) = \varprojlim{}^1 H^{m-1}(C_\bullet)$. Exactness at the three middle terms makes ∂ induce an injection of $\operatorname{coker} H^{m-1}(\delta)$ onto the kernel of $H^m(\varprojlim C_\bullet) \to H^m(P)$, and makes the image of that map $\ker H^m(\delta)$. The components of $H^m(\varprojlim C_\bullet) \to \prod_n H^m(C_n)$ are induced by the projections, as claimed.

This is Weibel [101] 3.5.8, in its form for cochain complexes, where it is proved under the Mittag-Leffler condition. Exercise 59.1.1 (8) recovers example 58.5.9 from it.

Lemma 59.1.18: A Limit of K-Injective Complexes Along Split Surjections Is K-Injective

Let R be a ring and $(I_n)_{n\geq 0}$ a tower of complexes of R-modules, with transition maps $q_{n+1}\colon I_{n+1} \to I_n$, such that every I_n is K-injective and every q^i_{n+1} is a split surjection. Then $\varprojlim I_\bullet$ is K-injective.

***Proof*:**
Let M be an acyclic complex of R-modules and write $I = \varprojlim I_\bullet$. In degree k,

$$\operatorname{Hom}^k(M, I) = \prod_i \operatorname{Hom}\big(M^i, \varprojlim_n I_n^{i+k}\big) = \prod_i \varprojlim_n \operatorname{Hom}\big(M^i, I_n^{i+k}\big) = \varprojlim_n \operatorname{Hom}^k(M, I_n)$$

by the description of homomorphisms into a limit, and because a product of limits is the limit of the products, the maps d^A being formed coordinatewise. The differential of definition 57.4.1 is formed by composing with differentials, so this is an isomorphism of complexes $\operatorname{Hom}^\bullet(M, I) \cong \varprojlim_n \operatorname{Hom}^\bullet(M, I_n)$, the transition maps being the chain maps $(q_{n+1})_*$ of lemma 57.4.3(2). These are surjective in each degree: if σ is a section of q^{i+k}_{n+1}, then $\sigma\psi$ is a preimage of $\psi\colon M^i \to I_n^{i+k}$. Each $\operatorname{Hom}^\bullet(M, I_n)$ is acyclic, since by lemma 57.4.3(1)

$$H^j \operatorname{Hom}^\bullet(M, I_n) = \operatorname{Hom}_{\mathrm{K}}(M, I_n[j]) = 0$$

with M acyclic and $I_n[j]$ K-injective by lemma 59.1.9. Lemma 59.1.17 for the tower $\operatorname{Hom}^\bullet(M, I_\bullet)$ of complexes of abelian groups places $H^0\operatorname{Hom}^\bullet(M, I)$ between $\varprojlim{}^1$ and $\varprojlim$ of towers of zero groups, so $\operatorname{Hom}_{\mathrm{K}}(M, I) = H^0\operatorname{Hom}^\bullet(M, I) = 0$, as we sought to show.

The lemma is [98, Tag 070L].

Theorem 59.1.19: K-Injective Resolutions Exist

Let $\mathcal{A}$ be a Grothendieck abelian category and $X \in \mathrm{Ch}(\mathcal{A})$. There is a quasi-isomorphism $\iota_X\colon X \to I_X$ such that I_X is K-injective, every I_X^n is an injective object and every ι_X^n is a monomorphism. Moreover the choice can be made functorial: there are a functor $\mathbf{I}\colon \mathrm{Ch}(\mathcal{A}) \to \mathrm{Ch}(\mathcal{A})$ and a natural transformation $\iota\colon \mathrm{id} \to \mathbf{I}$ such that $I_X = \mathbf{I}(X)$ and ι_X have these properties for every X.

For $\mathcal{A} = R$-Mod the first statement is proved below by Spaltenstein's argument. The same strategy works in every abelian category with enough injectives and exact countable products [98, Tag 090Y]. For a general Grothendieck abelian category, and for the functorial form, the proof is a transfinite

construction in the style of the proof of theorem 59.1.6, built from its functorial injective embeddings and from a set of representatives of the bounded-above acyclic complexes of bounded size. It is due to Serpé, generalizing Spaltenstein, and it is long and set-theoretic, so it is deferred to [98, Tag 079P], with the attribution at [98, Tag 079I].

***Proof*:**
Let $\mathcal{A} = R$-Mod. By theorem 59.1.6 and example 59.1.5(1) it has enough injectives.

Step 1: the tower of truncations. Let $X_\bullet$ be the tower of truncations of example 59.1.16, with $X_n = \tau^{\geq -n}X$, transition maps r_{n+1} and quotient maps $p_{-n}\colon X \to X_n$ satisfying $r_{n+1}p_{-n-1} = p_{-n}$. By proposition 56.1.14, $H^i(p_{-n})$ is an isomorphism for $i \geq -n$ and $H^i(X_n) = 0$ for $i < -n$.

Step 2: a tower of resolutions. We construct bounded-below complexes of injectives I_n, quasi-isomorphisms $\alpha_n\colon X_n \to I_n$ and chain maps $q_{n+1}\colon I_{n+1} \to I_n$, each q^i_{n+1} split surjective, with

$$q_{n+1}\alpha_{n+1} = \alpha_n r_{n+1}$$

as chain maps. Bounded-below complexes have injective resolutions by theorem 56.2.17 applied to the opposite category, as after definition 57.4.6, and this gives $\alpha_0\colon X_0 \to I_0$. Given α_n, choose likewise a quasi-isomorphism $\beta\colon X_{n+1} \to J$ with J a bounded-below complex of injectives. The complex I_n is K-injective by corollary 59.1.12, so proposition 59.1.11(2) for β gives a chain map $g\colon J \to I_n$ and a homotopy h, with $h^i\colon X^i_{n+1} \to I^{i-1}_n$, such that

$$u := \alpha_n r_{n+1} - g\beta = dh + hd$$

Let P be the complex with $P^i := I^i_n \oplus I^{i-1}_n$ and $d(a,b) := (da, -a - db)$. Then $d(da, -a - db) = (0, -da + da + ddb) = 0$, so P is a complex, and it is acyclic: if $d(a,b) = 0$ then $a = -db$, and $(a,b) = d(-b, 0)$. Its terms are injective and it is bounded below. The projection $\pi(a,b) := a$ is a chain map $P \to I_n$, split surjective in each degree with section $a \mapsto (a, 0)$. Define

$$I_{n+1} := J \oplus P, \qquad q_{n+1} := (g, \pi), \qquad \alpha_{n+1}(x) := \big(\beta x, (ux, -hx)\big)$$

The map $k(x) := (ux, -hx)$ is a chain map $X_{n+1} \to P$: the first coordinates of $dk(x)$ and $k(dx)$ are dux and udx, equal because u is a chain map, and the second ones are $-ux + dhx$ and $-hdx$, equal because $u = dh + hd$. So $\alpha_{n+1} = (\beta, k)$ is a chain map, and $q_{n+1}\alpha_{n+1} = g\beta + \pi k = g\beta + u = \alpha_n r_{n+1}$. As $H^i(P) = 0$, the map $H^i(\alpha_{n+1})$ is $H^i(\beta)$ followed by the inclusion of $H^i(J)$ as $H^i(J \oplus P) = H^i(J) \oplus 0$, so α_{n+1} is a quasi-isomorphism. Finally q_{n+1} is split surjective in each degree, with section $a \mapsto (0, (a, 0))$.

Step 3: the limit. Let $I := \varprojlim I_\bullet$. It is K-injective by lemma 59.1.18, since each I_n is K-injective by corollary 59.1.12. Its terms are injective. Choosing sections of the q^i_{n+1}, each I^i_{n+1} decomposes as $I^i_n \oplus \ker q^i_{n+1}$ with q^i_{n+1} the projection, so by induction $I^i_n \cong I^i_0 \oplus K_1 \oplus \cdots \oplus K_n$ with $K_m := \ker q^i_m$ and transition maps forgetting the last summand. Hence $I^i \cong I^i_0 \times \prod_{m \geq 1} K_m$. Each K_m is injective as a direct summand of an injective module, and a product of injective modules is injective, since $\mathrm{Hom}(-, \prod_t E_t) = \prod_t \mathrm{Hom}(-, E_t)$ and products of exact sequences of abelian groups are exact. The chain maps $\alpha_n p_{-n}\colon X \to I_n$ are compatible, as $q_{n+1}\alpha_{n+1}p_{-n-1} = \alpha_n r_{n+1}p_{-n-1} = \alpha_n p_{-n}$, so they define a chain map $\alpha\colon X \to I$.

Step 4: α is a quasi-isomorphism. Fix m. For $n \geq -m$ the map $H^m(\alpha_n p_{-n})\colon H^m(X) \to H^m(I_n)$

is an isomorphism by Step 1, α_n being a quasi-isomorphism. For $n \geq -m$, the relation $H^m(q_{n+1})H^m(\alpha_{n+1}p_{-n-1}) = H^m(\alpha_n p_{-n})$ then makes $H^m(q_{n+1})$ an isomorphism, and for $n < -m$ its target $H^m(I_n) \cong H^m(X_n)$ is 0. So every transition map of the tower $H^m(I_\bullet)$ is surjective, for every m, and $\varprojlim{}^1 H^{m-1}(I_\bullet) = 0$ by corollary 58.5.7. By lemma 59.1.17, $H^m(I) \to \varprojlim H^m(I_\bullet)$ is an isomorphism. Let $N := \max(0, -m)$. A coherent sequence in a tower whose transition maps are isomorphisms from N on is determined by its term of index N, so the projection $\varprojlim H^m(I_\bullet) \to H^m(I_N)$ is an isomorphism. The composite $H^m(X) \to H^m(I) \to \varprojlim H^m(I_\bullet) \to H^m(I_N)$ is $H^m(\alpha_N p_{-N})$, an isomorphism, so $H^m(\alpha)$ is an isomorphism.

Step 5: a monomorphic resolution. Choose monomorphisms $e^i \colon X^i \to E^i$ into injective modules. Let P' be the complex with $P'^i := E^i \oplus E^{i+1}$ and $d(a,b) := (b,0)$, so that $d^2 = 0$. The maps $s(a,b) := (0,a)$, from P'^i to $P'^{i-1} = E^{i-1} \oplus E^i$, satisfy $ds + sd = \mathrm{id}$, since $(ds+sd)(a,b) = (a,0) + (0,b)$. So $\mathrm{id}_{P'}$ is null-homotopic, P' is acyclic by proposition 56.1.29, and every chain map f into P' is null-homotopic, being homotopic to $0 \circ f$. Thus P' is K-injective. The map $x \mapsto (e^i x, e^{i+1} dx)$ is a chain map $X \to P'$, as both d of it and its value on dx are $(e^{i+1}dx, 0)$, and it is a monomorphism in each degree because e^i is. Put $I_X := I \oplus P'$ and

$$\iota_X := \big(\alpha, x \mapsto (e^i x, e^{i+1} dx)\big) \colon X \longrightarrow I_X$$

a monomorphism in each degree. It is a quasi-isomorphism, since $H^i(I_X) = H^i(I) \oplus 0$ with $H^i(\iota_X)$ equal to $H^i(\alpha)$. The complex I_X has injective terms, and it is K-injective: for acyclic M, $\mathrm{Hom}_{\mathrm{K}}(M, I_X) \cong \mathrm{Hom}_{\mathrm{K}}(M, I) \oplus \mathrm{Hom}_{\mathrm{K}}(M, P') = 0$, since $\mathrm{K}(R\text{-Mod})$ is additive (lemma 56.1.39). This completes the proof for modules.

In Step 4 the towers $H^m(I_\bullet)$ are eventually constant, so their $\varprojlim{}^1$ vanishes and the limit has the cohomology of X. Without that, lemma 59.1.17 would leave a $\varprojlim{}^1$ term in $H^m(I)$. The auxiliary complex P of Step 2 turns commutativity up to homotopy into strict commutativity. The maps produced by proposition 59.1.11(2) commute only up to homotopy, while a map into a limit needs a strictly compatible family, and a chain map into P is a chain map into I_n together with a null-homotopy of it.

Example 59.1.20: A K-Injective Resolution of the Complex $\mathbb{Z}$ in Every Degree
Let X be the complex of abelian groups with $X^n = \mathbb{Z}$ for every n and every differential zero. For each n let J_n be the complex $\mathbb{Q} \to \mathbb{Q}/\mathbb{Z}$, the quotient map, in degrees n and $n+1$. The groups $\mathbb{Q}$ and $\mathbb{Q}/\mathbb{Z}$ are injective (example 57.4.7). Let I be the complex with $I^n = \mathbb{Q} \oplus \mathbb{Q}/\mathbb{Z}$, the factor $\mathbb{Q}$ coming from J_n and the factor $\mathbb{Q}/\mathbb{Z}$ from J_{n-1}, and differential $d(x,t) = (0,[x])$, where $[x] \in \mathbb{Q}/\mathbb{Z}$ lies in I^{n+1}. Then $d^2 = 0$, and I is the degreewise product $\prod_n J_n$, each degree having only two nonzero factors.

The map $\nu \colon X \to I$, $a \mapsto (a,0)$, is a chain map, since $d\nu(a) = (0,[a]) = 0$ for $a \in \mathbb{Z}$. It is a quasi-isomorphism: the cocycles of I^n are $\mathbb{Z} \oplus \mathbb{Q}/\mathbb{Z}$, the coboundaries are $0 \oplus \mathbb{Q}/\mathbb{Z}$, and $H^n(I) \cong \mathbb{Z}$ is generated by $(1,0) = \nu(1)$. And I is K-injective. A chain map $M \to \prod_n J_n$ is a family of chain maps $M \to J_n$, and the same holds for null-homotopies, so $\mathrm{Hom}_{\mathrm{K}}(M, I) = \prod_n \mathrm{Hom}_{\mathrm{K}}(M, J_n)$. For acyclic M every factor vanishes by corollary 59.1.12. So ν is a K-injective resolution of a complex unbounded in both directions, and ν is a monomorphism in each degree.

Theorem 57.2.4 describes the morphisms of $D(\mathcal{A})$ by roofs, which range over all quasi-isomorphisms into a complex, and it guarantees that the classes of roofs form sets only when the quasi-isomorphisms

into each complex admit a cofinal set. K-injective resolutions give a set-theoretic bound with no such hypothesis.

Corollary 59.1.21: The Derived Category Has Small Hom-Sets

Let $\mathcal{A}$ be a Grothendieck abelian category, $X, Y \in \mathrm{Ch}(\mathcal{A})$, and $\iota_Y \colon Y \to I_Y$ a K-injective resolution. Then

$$\mathrm{Hom}_{\mathrm{K}}(X, I_Y) \longrightarrow \mathrm{Hom}_{D}(X, Y), \qquad f \longmapsto Q(\iota_Y)^{-1} Q(f)$$

is bijective. In particular $\mathrm{Hom}_{D(\mathcal{A})}(X, Y)$ is a set.

***Proof*:**
The map is the composite of the bijection $Q \colon \mathrm{Hom}_{\mathrm{K}}(X, I_Y) \to \mathrm{Hom}_{D}(X, I_Y)$ of proposition 59.1.11(3) and of composition with the isomorphism $Q(\iota_Y)^{-1}$. The resolution exists by theorem 59.1.19. The source is a quotient of the set of chain maps $X \to I_Y$, which is a subset of the set $\prod_n \mathrm{Hom}_{\mathcal{A}}(X^n, I_Y^n)$, completing the proof.

The corollary gives the conclusion that theorem 57.2.4 states under its cofinality hypothesis, without that hypothesis, for every Grothendieck abelian category, R-Mod included. In definition 57.3.5 the total derived functor of a left exact F was obtained by applying F term by term to a resolution in an adapted class, with bounded-below complexes throughout. K-injective resolutions do the same with no bound and with no exactness assumption on F. For an additive $F \colon \mathcal{A} \to \mathcal{B}$, applying F term by term carries null-homotopies to null-homotopies (lemma 56.1.34), so it defines a functor $\mathrm{K}(F) \colon \mathrm{K}(\mathcal{A}) \to \mathrm{K}(\mathcal{B})$. Write $Q_{\mathcal{A}}$ and $Q_{\mathcal{B}}$ for the localization functors, and $R^{+}F$ for the total derived functor of definition 57.3.5, with its transformation ε_F of theorem 57.3.6.

Corollary 59.1.22: Right Derived Functors on Unbounded Complexes

Let $\mathcal{A}$ be a Grothendieck abelian category, $\mathcal{B}$ an abelian category and $F \colon \mathcal{A} \to \mathcal{B}$ an additive functor. For every complex X fix a K-injective resolution $\iota_X \colon X \to I_X$ (theorem 59.1.19).

1. For every morphism $\varphi \colon X \to Y$ of $D(\mathcal{A})$ there is a unique $I_\varphi \in \mathrm{Hom}_{\mathrm{K}}(I_X, I_Y)$ with $Q_{\mathcal{A}}(I_\varphi)\, Q_{\mathcal{A}}(\iota_X) = Q_{\mathcal{A}}(\iota_Y)\, \varphi$, and $X \mapsto I_X$, $\varphi \mapsto I_\varphi$ is a functor $I_{(-)} \colon D(\mathcal{A}) \to \mathrm{K}(\mathcal{A})$.

2. Put $RF := Q_{\mathcal{B}} \circ \mathrm{K}(F) \circ I_{(-)}$ and $\varepsilon_X := Q_{\mathcal{B}}\big(F(\iota_X)\big) \colon F(X) \to RF(X)$. Then $\varepsilon \colon Q_{\mathcal{B}} \circ \mathrm{K}(F) \to RF \circ Q_{\mathcal{A}}$ is natural, and (RF, ε) is initial: for every functor $G \colon D(\mathcal{A}) \to D(\mathcal{B})$ and every natural transformation $\eta \colon Q_{\mathcal{B}} \circ \mathrm{K}(F) \to G \circ Q_{\mathcal{A}}$ there is a unique natural transformation $\theta \colon RF \to G$ with $\eta = (\theta * Q_{\mathcal{A}}) \circ \varepsilon$. Hence RF does not depend on the chosen resolutions, up to a unique natural isomorphism compatible with ε.

3. RF is a triangulated functor.

4. If F is left exact, then for every bounded-below complex X there is an isomorphism $\theta_X \colon RF(X) \to R^{+}F(X)$ in $D(\mathcal{B})$, natural in X for the morphisms of $D^{+}(\mathcal{A})$, with $\theta_X \varepsilon_X = \varepsilon_F(X)$. In particular $H^n\big(RF(A)\big) \cong R^nF(A)$ for every object A of $\mathcal{A}$, natural in A.

***Proof*:**
Write Q for $Q_{\mathcal{A}}$ where no confusion arises. Since I_Y is K-injective, $Q\colon \mathrm{Hom}_{\mathrm{K}}(Z, I_Y) \to \mathrm{Hom}_D(Z, I_Y)$ is bijective for every Z (proposition 59.1.11(3)), and $Q(\iota_X)$ is invertible.

(1). The morphism $Q(\iota_Y)\varphi Q(\iota_X)^{-1}$ of $\mathrm{Hom}_D(I_X, I_Y)$ has a unique preimage under Q, which is I_φ. Uniqueness gives $I_{\mathrm{id}} = \mathrm{id}$, $I_{\varphi'\varphi} = I_{\varphi'} I_\varphi$ and $I_{\varphi+\varphi'} = I_\varphi + I_{\varphi'}$, since the right-hand sides satisfy the defining equations. For a chain map $f\colon X \to Y$, the classes $I_{Qf}\,\iota_X$ and $\iota_Y f$ in $\mathrm{Hom}_{\mathrm{K}}(X, I_Y)$ have the same image under Q, so $I_{Qf}\,\iota_X = \iota_Y f$ in $\mathrm{K}(\mathcal{A})$.

(2). Naturality of ε: for a chain map $f\colon X \to Y$,

$$RF(Qf)\,\varepsilon_X = Q_{\mathcal{B}}F\big(I_{Qf}\,\iota_X\big) = Q_{\mathcal{B}}F(\iota_Y f) = \varepsilon_Y\, Q_{\mathcal{B}}F(f)$$

by (1). If W is K-injective, then $\iota_W\colon W \to I_W$ is a quasi-isomorphism between K-injective complexes, hence a homotopy equivalence (corollary 59.1.13(1)), so $F(\iota_W)$ is a homotopy equivalence by lemma 56.1.34 and ε_W is an isomorphism. Given (G, η), put $\mu_W := \eta_W \varepsilon_W^{-1}\colon RF(W) \to G(W)$ for K-injective W. For a morphism $\psi\colon W \to W'$ of $\mathrm{K}(\mathcal{A})$ between K-injective complexes, naturality of ε and η along ψ gives $\mu_{W'} RF(Q\psi) = \eta_{W'} Q_{\mathcal{B}}F(\psi)\varepsilon_W^{-1} = G(Q\psi)\mu_W$.

If θ satisfies $\theta_X \varepsilon_X = \eta_X$ for every X, then $\theta_W = \mu_W$ for K-injective W, and naturality along $Q(\iota_X)$ forces

$$\theta_X = G(Q\iota_X)^{-1}\,\mu_{I_X}\,RF(Q\iota_X)$$

so θ is unique. Conversely define θ_X by this formula. Naturality of ε along ι_X and of η along ι_X give

$$\theta_X\varepsilon_X = G(Q\iota_X)^{-1}\,\eta_{I_X}\,\varepsilon_{I_X}^{-1}\,\varepsilon_{I_X}\,Q_{\mathcal{B}}F(\iota_X) = G(Q\iota_X)^{-1}\,G(Q\iota_X)\,\eta_X = \eta_X$$

For $\varphi\colon X \to Y$ in $D(\mathcal{A})$ put $\psi := I_\varphi$, so that $Q(\iota_Y)\varphi = Q(\psi)Q(\iota_X)$. Applying RF and G to this equation gives $RF(Q\iota_Y)RF(\varphi) = RF(Q\psi)RF(Q\iota_X)$ and $G(Q\iota_Y)^{-1}G(Q\psi) = G(\varphi)G(Q\iota_X)^{-1}$, so, with the naturality of μ along ψ,

$$\theta_Y RF(\varphi) = G(Q\iota_Y)^{-1}\mu_{I_Y} RF(Q\psi)RF(Q\iota_X) = G(Q\iota_Y)^{-1}G(Q\psi)\mu_{I_X} RF(Q\iota_X) = G(\varphi)\,\theta_X$$

So θ is natural. Two choices of resolutions give two initial pairs, and the comparison transformations between them compose to identities by the uniqueness proved above.

(3). RF is additive, as $I_{(-)}$, $\mathrm{K}(F)$ and $Q_{\mathcal{B}}$ are. *Shift.* The complex $I_X[1]$ is K-injective by lemma 59.1.9, and $\iota_X[1]$ is a quasi-isomorphism since $H^n(\iota_X[1]) = H^{n+1}(\iota_X)$. As in (1) there is a unique $\omega_X \in \mathrm{Hom}_{\mathrm{K}}(I_{X[1]}, I_X[1])$ with $Q(\omega_X)Q(\iota_{X[1]}) = Q(\iota_X[1])$. Applying the functor H^n on $D(\mathcal{A})$ (proposition 57.2.8) gives $H^n(\omega_X)H^n(\iota_{X[1]}) = H^n(\iota_X[1])$ with both $H^n(\iota_{X[1]})$ and $H^n(\iota_X[1])$ isomorphisms, so ω_X is a quasi-isomorphism between K-injective complexes and hence an isomorphism of $\mathrm{K}(\mathcal{A})$ by corollary 59.1.13(1). For $\varphi\colon X \to Y$ the classes $\omega_Y I_{\varphi[1]}$ and $I_\varphi[1]\omega_X$ both satisfy the equation $Q(-)Q(\iota_{X[1]}) = Q(\iota_Y[1])\varphi[1]$, so they are equal and ω is natural. Since F is additive, $F(Z[1]) = F(Z)[1]$ for every complex Z, the differential $-d$ going to $-F(d)$. So $\zeta_X := Q_{\mathcal{B}}F(\omega_X)\colon RF(X[1]) \to RF(X)[1]$ is a natural isomorphism.

Triangles. Let $u\colon X \to Y$ be a chain map with mapping cone triangle $X \xrightarrow{u} Y \xrightarrow{v} MC(u) \xrightarrow{w} X[1]$, and put $\tilde{u} := I_{Qu}$, so that $\tilde{u}\,\iota_X = \iota_Y u$ in $\mathrm{K}(\mathcal{A})$ by (1). Let $I_Y \xrightarrow{\tilde{v}} MC(\tilde{u}) \xrightarrow{\tilde{w}} I_X[1]$ complete

the cone triangle of $\tilde{u}$. The cone $MC(\tilde{u})$ is K-injective: for acyclic M, the functor $\mathrm{Hom}_{\mathrm{K}}(M,-)$ is cohomological (proposition 57.1.8), and on the rotation $(\tilde{v},\tilde{w},-\tilde{u}[1])$ of the cone triangle it gives an exact sequence $\mathrm{Hom}_{\mathrm{K}}(M,I_Y)\to\mathrm{Hom}_{\mathrm{K}}(M,MC(\tilde{u}))\to\mathrm{Hom}_{\mathrm{K}}(M,I_X[1])$ with vanishing outer terms. By (TR3) in $\mathrm{K}(\mathcal{A})$ there is $c\colon MC(u)\to MC(\tilde{u})$ making (ι_X,ι_Y,c) a morphism of triangles, so $cv=\tilde{v}\,\iota_Y$ and $\tilde{w}c=\iota_X[1]\,w$. Its image under Q is a morphism of distinguished triangles of $D(\mathcal{A})$ (theorem 57.2.7) whose first two components are isomorphisms, so $Q(c)$ is an isomorphism by corollary 57.1.9, and c is a quasi-isomorphism. Let $\kappa\in\mathrm{Hom}_{\mathrm{K}}(I_{MC(u)},MC(\tilde{u}))$ be the unique class with $Q(\kappa)Q(\iota_{MC(u)})=Q(c)$, an isomorphism of $\mathrm{K}(\mathcal{A})$ by the argument used for ω_X.

We claim that $(\mathrm{id},\mathrm{id},\kappa)$ is an isomorphism of triangles from $\big(\tilde{u},I_{Qv},\omega_X I_{Qw}\big)$ to $(\tilde{u},\tilde{v},\tilde{w})$. The targets $MC(\tilde{u})$ and $I_X[1]$ of the remaining two squares are K-injective, so it suffices to compare their two sides after applying Q and composing with the isomorphisms $Q(\iota_Y)$ and $Q(\iota_{MC(u)})$ respectively. Using (1),

$$Q\big(\kappa\, I_{Qv}\big)Q(\iota_Y)=Q(\kappa)Q(\iota_{MC(u)})Q(v)=Q(cv)=Q(\tilde{v})Q(\iota_Y)$$
$$Q(\tilde{w}\kappa)Q(\iota_{MC(u)})=Q(\tilde{w}c)=Q(\iota_X[1])Q(w)=Q(\omega_X)Q(\iota_{X[1]})Q(w)=Q\big(\omega_X I_{Qw}\big)Q(\iota_{MC(u)})$$

Cancelling the isomorphisms $Q(\iota_Y)$ and $Q(\iota_{MC(u)})$ and using proposition 59.1.11(3) for the targets gives $\kappa\, I_{Qv}=\tilde{v}$ and $\tilde{w}\kappa=\omega_X I_{Qw}$ in $\mathrm{K}(\mathcal{A})$, which proves the claim. So the triangle $\big(\tilde{u},I_{Qv},\omega_X I_{Qw}\big)$ is distinguished in $\mathrm{K}(\mathcal{A})$, by (TR1). By definition 56.1.23, $F(MC(\tilde{u}))$ is $MC(F(\tilde{u}))$ term by term, with F applied to the inclusion and the projection, so $\mathrm{K}(F)$ carries cone triangles, and with (TR1) all distinguished triangles, to distinguished triangles of $\mathrm{K}(\mathcal{B})$, and $Q_{\mathcal{B}}$ carries those to distinguished triangles of $D(\mathcal{B})$. The image of our triangle is $\big(RF(Qu),RF(Qv),\zeta_X RF(Qw)\big)$, which is therefore distinguished. Every distinguished triangle of $D(\mathcal{A})$ is isomorphic to the image under Q of a mapping cone triangle (theorem 57.2.7 and theorem 57.1.12). The functor RF, with the natural ζ, carries isomorphic triangles to isomorphic triangles, and the distinguished triangles of $D(\mathcal{B})$ are closed under isomorphism, which proves (3).

(4). By the last assertion of (2), a second choice of resolutions changes RF and ε by a natural isomorphism compatible with ε, and composing with it carries an isomorphism θ as in (4) for one choice to one for the other. So we may take ι_X to be a quasi-isomorphism into a bounded-below complex of injectives whenever X is bounded below, as in Step 2 of the proof of theorem 59.1.19. Such ι_X is a K-injective resolution by corollary 59.1.12, and then I_φ is a morphism of $\mathrm{K}^+(\mathcal{A})$ for every morphism φ of $D^+(\mathcal{A})$ between bounded-below complexes. By theorem 57.3.6(3) we may compute R^+F with the class of injectives, adapted to F by example 57.3.3(1), $\mathcal{A}$ having enough injectives by theorem 59.1.6. Write $\mathcal{R}$ for this class, $\Psi\colon \mathrm{K}^+(\mathcal{R})[S_{\mathcal{R}}^{-1}]\to D^+(\mathcal{A})$ for the equivalence of theorem 57.3.4, Φ for the inverse of Ψ from which R^+F is built, $\beta\colon \mathrm{id}\to\Psi\Phi$ for the natural isomorphism exhibiting Φ as an inverse of Ψ, and $\bar{F}\colon \mathrm{K}^+(\mathcal{R})[S_{\mathcal{R}}^{-1}]\to D^+(\mathcal{B})$ for the functor induced by F term by term, so that $R^+F=\bar{F}\Phi$. Let W be a bounded-below complex of injectives. It lies in $\mathrm{K}^+(\mathcal{R})$, so the quasi-isomorphism $s\colon W\to Z$ in the definition of $\varepsilon_F(W)$ in theorem 57.3.6 may be taken to be id_W, the result not depending on s by part (1) of that theorem. That definition then reads $\varepsilon_F(W)=\bar{F}(\gamma)^{-1}Q_{\mathcal{B}}\big(F(\mathrm{id}_W)\big)=\bar{F}(\gamma)^{-1}$, where $\gamma\colon \Phi(Q_{\mathcal{A}}W)\to W$ is the morphism of $\mathrm{K}^+(\mathcal{R})[S_{\mathcal{R}}^{-1}]$ with $\Psi(\gamma)=Q_{\mathcal{A}}(\mathrm{id}_W)\beta_W^{-1}=\beta_W^{-1}$. As Ψ is an equivalence and β_W^{-1} is an isomorphism, γ is an isomorphism, hence so is $\bar{F}(\gamma)$, and $\varepsilon_F(W)$ is

an isomorphism. Set

$$\theta_X := R^+F(Q\iota_X)^{-1}\,\varepsilon_F(I_X)\colon RF(X) = Q_{\mathcal{B}}F(I_X) \longrightarrow R^+F(X)$$

an isomorphism. Naturality of ε_F along ι_X gives $\theta_X\varepsilon_X = R^+F(Q\iota_X)^{-1}\,\varepsilon_F(I_X)\,Q_{\mathcal{B}}F(\iota_X) = \varepsilon_F(X)$. For a morphism $\varphi\colon X \to Y$ of $D^+(\mathcal{A})$ between bounded-below complexes, naturality of ε_F along I_φ and the relation $Q(\iota_Y)^{-1}Q(I_\varphi) = \varphi\,Q(\iota_X)^{-1}$ give

$$\theta_Y RF(\varphi) = R^+F(Q\iota_Y)^{-1}R^+F\big(Q(I_\varphi)\big)\varepsilon_F(I_X) = R^+F(\varphi)\,R^+F(Q\iota_X)^{-1}\varepsilon_F(I_X) = R^+F(\varphi)\,\theta_X$$

For an object A of $\mathcal{A}$, applying H^n to θ_A and using theorem 57.3.7 gives $H^n(RF(A)) \cong R^nF(A)$, natural in A, completing the proof.

Part (2) is a stronger universal property than the one in theorem 57.3.6(2), since it quantifies over all functors G and not only triangulated ones, and by (3) the pair (RF, ε) belongs to the triangulated class. As in the bounded case, $RF(X)$ is F applied term by term to a resolution of X, now a K-injective one, and for X itself K-injective, ε_X identifies $RF(X)$ with $F(X)$. Applied term by term to a complex of injectives that is not K-injective, F need not carry quasi-isomorphisms to quasi-isomorphisms, as in example 57.3.1, where the complex was a projective resolution.

Example 59.1.23: Applying a Functor Term by Term to a Complex of Injectives
Let I be the complex of example 59.1.7 and $F := \mathrm{Hom}_{\mathbb{Z}/4}(\mathbb{Z}/2, -)\colon \mathbb{Z}/4\text{-Mod} \to \mathbf{Ab}$, where $\mathbb{Z}/2 = \mathbb{Z}/4/(2)$. A homomorphism $\varphi\colon \mathbb{Z}/2 \to \mathbb{Z}/4$ is determined by $\varphi(1)$, subject to $2\varphi(1) = \varphi(2) = 0$, so $F(\mathbb{Z}/4) \cong \{0, 2\} \cong \mathbb{Z}/2$. The differential of I induces $\varphi \mapsto 2\varphi$, which is zero since $2 \cdot 2 = 0$ in $\mathbb{Z}/4$. So $F(I)$ is the complex with $\mathbb{Z}/2$ in every degree and zero differential, and $H^n(F(I)) \cong \mathbb{Z}/2$ for every n. On the other hand I is acyclic, so $I \to 0$ is a quasi-isomorphism into the K-injective complex 0, a K-injective resolution. By the last assertion of corollary 59.1.22(2), $RF(I)$ may be computed with this resolution, so $RF(I) \cong F(0) = 0$, while term-by-term application of F to the injective terms of I has nonzero cohomology in every degree. In particular the term-by-term functor does not carry the quasi-isomorphism $I \to 0$ to a quasi-isomorphism.

Exercise 59.1.1

1. Let R be a ring and $(C_i)_{i\in I}$ a directed system of complexes of R-modules, that is, a directed system in $\mathrm{Ch}(R\text{-Mod})$, and let C be the complex with $C^n = \varinjlim_i C_i^n$ and the differential induced by those of the C_i. Using proposition 59.1.3, show that the maps $H^n(C_i) \to H^n(C)$ induce an isomorphism $\varinjlim_i H^n(C_i) \cong H^n(C)$ for every n.

2. Let $\mathcal{A}$ be an abelian category satisfying (AB3) with a generator U in the sense of (G). Show that every object X is a quotient of the direct sum $\bigoplus_{u\in\mathrm{Hom}(U,X)} U$, by applying (G) to the cokernel of the morphism $\bigoplus_u U \to X$ that restricts to u on the summand indexed by u.

3. Show that the category of finitely generated abelian groups is abelian and is not a Grothendieck abelian category. (If a countable family of copies of $\mathbb{Z}$ had a direct sum S in this category, then $\mathrm{Hom}(S, \mathbb{Z}/2)$ would be in bijection with $\prod_{n\in\mathbb{N}} \mathrm{Hom}(\mathbb{Z}, \mathbb{Z}/2)$. Compare cardinalities.)

4. Let $\mathcal{A}$ be abelian. Show that $I \oplus J$ is K-injective if and only if I and J are, and more generally that if J is a retract of a K-injective complex I in $\mathrm{K}(\mathcal{A})$, meaning that there are $a\colon J \to I$ and $b\colon I \to J$ with $ba = \mathrm{id}_J$ in $\mathrm{K}(\mathcal{A})$, then J is K-injective.

5. Show that a complex I is acyclic and K-injective if and only if id_I is null-homotopic. Deduce that if X is acyclic and $\iota_X \colon X \to I_X$ is a K-injective resolution, then id_{I_X} is null-homotopic.

6. Let I be the complex of example 59.1.7 and regard $\mathbb{Z}/2 = \mathbb{Z}/4/(2)$ and $\mathbb{Z}/4$ as complexes concentrated in degree 0. Show that $\mathrm{Hom}_{\mathrm{K}(\mathbb{Z}/4\text{-Mod})}(\mathbb{Z}/4, I) = 0$ and $\mathrm{Hom}_{\mathrm{K}(\mathbb{Z}/4\text{-Mod})}(\mathbb{Z}/2, I) \cong \mathbb{Z}/2$. Conclude that $Q \colon \mathrm{Hom}_{\mathrm{K}}(\mathbb{Z}/2, I) \to \mathrm{Hom}_D(\mathbb{Z}/2, I)$ is not injective, so that condition (3) of proposition 59.1.11 fails for I already at a complex concentrated in one degree.

7. Let $\mathcal{A}$ be abelian and let $A \xrightarrow{u} B \xrightarrow{v} C \xrightarrow{w} A[1]$ be a distinguished triangle of $\mathrm{K}(\mathcal{A})$. Show that if two of A, B, C are K-injective, then so is the third. (For an acyclic M, apply $\mathrm{Hom}_{\mathrm{K}}(M, -)$ to the triangle and to its two rotations in (TR2).)

8. Fix a prime p. For $n \geq 0$ let C_n be the complex $\mathbb{Z} \to \mathbb{Z}/p^n\mathbb{Z}$, the reduction map, in degrees 0 and 1, and let $C_{n+1} \to C_n$ be the identity in degree 0 and the reduction in degree 1. Compute $H^0(C_n)$, $H^1(C_n)$ and $\varprojlim C_\bullet$, and use lemma 59.1.17 with example 58.5.8 to show that $\varprojlim^1$ of the tower $(p^n\mathbb{Z})_n$, with the inclusions as transition maps, is isomorphic to $\mathbb{Z}_p/\mathbb{Z}$, recovering example 58.5.9.

59.2 K-Flat Complexes and the Unbounded Tensor-Hom Adjunction

Section 59.1 resolves every complex of a Grothendieck abelian category on the right by a K-injective complex, and corollary 59.1.22 uses these resolutions to derive additive functors on unbounded complexes. The tensor product is derived by resolving on the left, and box 57.4.20 records where the left resolutions of section 57.4 needed a bound: lemma 57.4.4(1) needs a bounded-above complex of projectives, and lemma 57.4.14(2) a bounded-above complex of flat modules. This section replaces both by conditions on a complex as a whole, K-projectivity and K-flatness, in the form given by Spaltenstein [95], and constructs a resolution of both kinds for every complex of modules. The derived tensor product and $R\mathrm{Hom}$ then become bifunctors on all of $D(R)$, adjoint to one another as in theorem 57.4.19, and they agree with the constructions of section 57.4 on bounded complexes. Over a principal ideal domain every complex of torsion-free modules is K-flat, so that $F \otimes^L_{\mathbb{Z}} \mathbb{Z}/n$ is F/nF for every complex F of torsion-free abelian groups.

Throughout, R is a commutative ring and $D(R) = D(R\text{-Mod})$. As explained before theorem 57.4.19, the total tensor complex $\mathrm{Tot}(X \otimes_R Y)$ of definition 57.4.12 and the Hom complex $\mathrm{Hom}^\bullet(X, Y)$ of definition 57.4.1, formed in R-Mod, are then complexes of R-modules. Neither definition requires a bound on X or Y: Tot is formed with direct sums and $\mathrm{Hom}^\bullet$ with products.

Conditions on the individual terms do not control an unbounded complex. Example 59.2.2(3) and example 59.2.6 below give an acyclic complex of free $\mathbb{Z}/4$-modules for which the conclusions of lemma 57.4.4(1) and lemma 57.4.14(3) fail. The conditions that replace the bounds are tested against every acyclic complex at once.

Definition 59.2.1: K-Projective and K-Flat Complexes

Let X be a complex of R-modules.

1. X is *K-projective* if $\mathrm{Hom}_{\mathrm{K}(R\text{-Mod})}(X, A) = 0$ for every acyclic complex A of R-modules.
2. X is *K-flat* if $\mathrm{Tot}(X \otimes_R A)$ is acyclic for every acyclic complex A of R-modules.

A *K-projective resolution* of a complex Y is a quasi-isomorphism $P \to Y$ with P K-projective, and a *K-flat resolution* is a quasi-isomorphism $F \to Y$ with F K-flat.

If A is acyclic, so is every shift $A[n]$, and $H^n\mathrm{Hom}^\bullet(X, A) = \mathrm{Hom}_{\mathrm{K}(R\text{-Mod})}(X, A[n])$ by lemma 57.4.3(1). So X is K-projective exactly when $\mathrm{Hom}^\bullet(X, A)$ is acyclic for every acyclic complex A, which is the definition of [95, p. 1.1], where it is attributed to J. Bernstein. K-flatness is [95, p. 5.1], stated there for complexes of sheaves of modules on a commutative ringed space, of which complexes of R-modules are the case of a one-point space with structure ring R. Both conditions say that a functor of complexes built from X carries acyclic complexes to acyclic complexes: $\mathrm{Hom}^\bullet(X, -)$ in the first case, $\mathrm{Tot}(X \otimes_R -)$ in the second.

Example 59.2.2: Bounded-Above Projective Complexes, Single Modules, and a Free Complex over $\mathbb{Z}/4$

1. Let P be a bounded-above complex of projective R-modules and A an acyclic complex. By proposition 57.2.12(1), $A \cong 0$ in $D(R)$, so $\mathrm{Hom}_{D(R)}(P, A) = 0$, and lemma 57.4.4(1) identifies $\mathrm{Hom}_{\mathrm{K}(R\text{-Mod})}(P, A)$ with this group. So P is K-projective.
2. Let M be an R-module, regarded as a complex in degree 0. Then $\mathrm{Tot}(M \otimes_R A)^n = M \otimes_R A^n$ with differential $1 \otimes d_A$, and $\mathrm{Hom}^n(M, A) = \mathrm{Hom}_R(M, A^n)$ with differential $\varphi \mapsto d_A\varphi$. If M is flat, the exact functor $M \otimes_R -$ of definition 17.5.4 preserves kernels and images, so it carries acyclic complexes to acyclic ones and M is K-flat. If M is projective, it is K-projective by (1). Conversely, let $0 \to N' \to N \to N'' \to 0$ be a short exact sequence, placed in degrees -1, 0, 1 as an acyclic complex A. If M is K-flat, then $M \otimes_R A$ is acyclic, which says that $M \otimes_R -$ is exact on this sequence, so M is flat. If M is K-projective, then $\mathrm{Hom}^\bullet(M, A)$ is acyclic, and its vanishing cohomology in degree 1 says that $\mathrm{Hom}_R(M, N) \to \mathrm{Hom}_R(M, N'')$ is surjective. Every surjection $N \to N''$ arises this way, so M is projective by theorem 17.2.4(2).
3. Let I be the complex of example 59.1.7, with $I^n = \mathbb{Z}/4$ for every $n \in \mathbb{Z}$ and every differential multiplication by 2. Its terms are free $\mathbb{Z}/4$-modules. By example 59.1.7(2) and (3), I is acyclic and id_I is a nonzero element of $\mathrm{Hom}_{\mathrm{K}(\mathbb{Z}/4\text{-Mod})}(I, I)$, so I is not K-projective. The same example shows that $Q\colon \mathrm{Hom}_{\mathrm{K}}(I, I) \to \mathrm{Hom}_D(I, I)$ is not injective, so the conclusion of lemma 57.4.4(1) fails for this complex of projective modules.

Together with (1), item (3) shows that a complex of projective modules is K-projective when it is bounded above and need not be otherwise. Item (2) shows that both notions extend the module-level ones.

Write $\mathcal{A} = R\text{-Mod}$. Reindexing $X^n \mapsto X^{-n}$ identifies $\mathrm{Ch}(\mathcal{A}^{\mathrm{op}})$ with $\mathrm{Ch}(\mathcal{A})^{\mathrm{op}}$, and by Step 3 of the proof of lemma 57.4.4 it carries quasi-isomorphisms to quasi-isomorphisms and null-homotopies to null-homotopies, identifies $\mathrm{K}(\mathcal{A}^{\mathrm{op}})$ with $\mathrm{K}(\mathcal{A})^{\mathrm{op}}$, and identifies $D(\mathcal{A}^{\mathrm{op}})$ with $D(\mathcal{A})^{\mathrm{op}}$ compatibly with Q. Write X° for the complex of $\mathcal{A}^{\mathrm{op}}$ corresponding to a complex X of R-modules. By lemma 56.1.19,

X is acyclic exactly when $0 \to X$ is a quasi-isomorphism, and this chain map corresponds to $X^\circ \to 0$, so X is acyclic exactly when X° is. As $\mathrm{Hom}_{\mathrm{K}(\mathcal{A})}(P, A) = \mathrm{Hom}_{\mathrm{K}(\mathcal{A}^{\mathrm{op}})}(A^\circ, P^\circ)$ for all complexes P and A, a complex P of R-modules is K-projective exactly when P° is a K-injective complex of the abelian category $\mathcal{A}^{\mathrm{op}}$.

Lemma 59.2.3: K-Projective Complexes Compute Morphisms in $D(R)$

Let P be a K-projective complex of R-modules.

1. For every quasi-isomorphism $t\colon Y \to Y'$, the chain map $t_* := \mathrm{Hom}^\bullet(P, t)\colon \mathrm{Hom}^\bullet(P, Y) \to \mathrm{Hom}^\bullet(P, Y')$ is a quasi-isomorphism.
2. For every complex X, the map $Q\colon \mathrm{Hom}_{\mathrm{K}(R\text{-Mod})}(P, X) \to \mathrm{Hom}_{D(R)}(P, X)$ is bijective.
3. A quasi-isomorphism $u\colon P' \to P$ whose source P' is also K-projective is a homotopy equivalence.

***Proof*:**
(2) and (3). Under the correspondence $X \mapsto X^\circ$ above, P° is a K-injective complex of $\mathcal{A}^{\mathrm{op}}$. For a complex X, proposition 59.1.11(3) for $\mathcal{A}^{\mathrm{op}}$ makes $Q\colon \mathrm{Hom}_{\mathrm{K}(\mathcal{A}^{\mathrm{op}})}(X^\circ, P^\circ) \to \mathrm{Hom}_{D(\mathcal{A}^{\mathrm{op}})}(X^\circ, P^\circ)$ bijective, and under the identifications of $\mathrm{K}(\mathcal{A}^{\mathrm{op}})$ with $\mathrm{K}(\mathcal{A})^{\mathrm{op}}$ and of $D(\mathcal{A}^{\mathrm{op}})$ with $D(\mathcal{A})^{\mathrm{op}}$, compatible with Q, this map is $Q\colon \mathrm{Hom}_{\mathrm{K}(\mathcal{A})}(P, X) \to \mathrm{Hom}_{D(\mathcal{A})}(P, X)$. This is (2). For (3), the chain map $u^\circ\colon P^\circ \to P'^\circ$ is a quasi-isomorphism between K-injective complexes of $\mathcal{A}^{\mathrm{op}}$, so by corollary 59.1.13(1) there is $v^\circ\colon P'^\circ \to P^\circ$ with $v^\circ u^\circ$ and $u^\circ v^\circ$ homotopic to the identities. The reindexing carries null-homotopies to null-homotopies, so the corresponding $v\colon P \to P'$ has uv and vu homotopic to the identities, and u is a homotopy equivalence.

(1). Fix n. By lemma 57.4.3(1) and (3), $H^n(t_*)$ is the map

$$\mathrm{Hom}_{\mathrm{K}(R\text{-Mod})}(P, Y[n]) \longrightarrow \mathrm{Hom}_{\mathrm{K}(R\text{-Mod})}(P, Y'[n]), \qquad \psi \longmapsto t[n] \circ \psi$$

The bijections Q of (2) carry it to $\psi \mapsto Q(t[n]) \circ \psi$ on morphisms of $D(R)$, because Q is a functor, and that map is bijective with inverse $\psi \mapsto Q(t[n])^{-1} \circ \psi$, since $t[n]$ is a quasi-isomorphism, $H^i(t[n])$ being $H^{i+n}(t)$, completing the proof.

K-flatness is defined so that $\mathrm{Tot}(X \otimes_R -)$ carries quasi-isomorphisms to quasi-isomorphisms. The identities in the proof of lemma 57.4.14 that relate cones and homotopies to total tensor complexes are identities between elementary tensors, and the bound in that lemma enters only through proposition 56.5.4 in its Step 2. Over a commutative ring the two factors can also be exchanged.

Lemma 59.2.4: The Total Tensor Complex of Unbounded Complexes

Let X and Y be complexes of R-modules.

1. The map $\mathrm{sw}_{X,Y}(x \otimes y) := (-1)^{ij}\, y \otimes x$, for $x \in X^i$ and $y \in Y^j$, is an isomorphism of complexes $\mathrm{Tot}(X \otimes_R Y) \to \mathrm{Tot}(Y \otimes_R X)$. In particular X is K-flat if and only if $\mathrm{Tot}(A \otimes_R X)$ is acyclic for every acyclic complex A.
2. If $f, f' \colon X \to X'$ are homotopic, so are $\mathrm{Tot}(f \otimes g)$ and $\mathrm{Tot}(f' \otimes g)$ for every chain map g, and likewise in the second variable. Hence $\mathrm{Tot}(- \otimes_R -)$ is a functor $\mathrm{K}(R\text{-Mod}) \times \mathrm{K}(R\text{-Mod}) \to \mathrm{K}(R\text{-Mod})$.
3. If X is K-flat and $t \colon Y \to Y'$ is a quasi-isomorphism, then $\mathrm{Tot}(X \otimes t)$ and $\mathrm{Tot}(t \otimes X)$ are quasi-isomorphisms.
4. If X is K-flat and $u \colon X \to X'$ is a homotopy equivalence, then X' is K-flat.

***Proof*:**

1. As R is commutative, $(x, y) \mapsto (-1)^{ij} y \otimes x$ is R-bilinear on $X^i \times Y^j$, so $\mathrm{sw}_{X,Y}$ is defined summand by summand, and $\mathrm{sw}_{Y,X}$ is its inverse, since $(-1)^{ij}(-1)^{ji} = 1$. For $x \in X^i$ and $y \in Y^j$, definition 57.4.12 gives
$$\mathrm{sw}\big(d(x \otimes y)\big) = \mathrm{sw}\big(dx \otimes y + (-1)^i x \otimes dy\big) = (-1)^{(i+1)j}\, y \otimes dx + (-1)^{i+i(j+1)}\, dy \otimes x$$
and
$$d\big(\mathrm{sw}(x \otimes y)\big) = (-1)^{ij}\big(dy \otimes x + (-1)^j y \otimes dx\big)$$
The exponents agree, $(i+1)j \equiv ij + j$ and $i + i(j+1) \equiv ij \pmod 2$, so $\mathrm{sw}_{X,Y}$ is a chain map. Applied with $Y = A$ it shows that $\mathrm{Tot}(X \otimes_R A)$ and $\mathrm{Tot}(A \otimes_R X)$ are isomorphic complexes.
2. Step 1 of the proof of lemma 57.4.14 writes down, for a homotopy h from f to f', a map $H(x \otimes y) = h(x) \otimes g(y)$ with $\mathrm{Tot}\big((f - f') \otimes g\big) = dH + Hd$, and the analogous map in the second variable. Both are defined and verified on elementary tensors, and an element of $\mathrm{Tot}(X \otimes_R Y)^n$ is a finite sum of elementary tensors, so the verification holds with no bound on X or Y. Composition of chain maps is preserved because $\mathrm{Tot}\big((f_1 f_2) \otimes (g_1 g_2)\big) = \mathrm{Tot}(f_1 \otimes g_1)\mathrm{Tot}(f_2 \otimes g_2)$.
3. Step 4 of the proof of lemma 57.4.14 defines an isomorphism of complexes $\theta \colon \mathrm{Tot}\big(X \otimes_R MC(t)\big) \to MC\big(\mathrm{Tot}(X \otimes t)\big)$ by a formula on elementary tensors, and the verification there uses no bound. As t is a quasi-isomorphism, $MC(t)$ is acyclic by proposition 56.1.26, so $\mathrm{Tot}(X \otimes_R MC(t))$ is acyclic because X is K-flat, and $\mathrm{Tot}(X \otimes t)$ is a quasi-isomorphism by proposition 56.1.26. Step 3 of the same proof identifies $MC\big(\mathrm{Tot}(t \otimes X)\big)$ with $\mathrm{Tot}\big(MC(t) \otimes_R X\big)$, again by a computation on elementary tensors, and this complex is acyclic by (1). So $\mathrm{Tot}(t \otimes X)$ is a quasi-isomorphism.
4. Let v be a homotopy inverse of u and A an acyclic complex. By (2), $\mathrm{Tot}(u \otimes \mathrm{id}_A)$ is a homotopy equivalence with homotopy inverse $\mathrm{Tot}(v \otimes \mathrm{id}_A)$, so it induces isomorphisms on cohomology by proposition 56.1.33. Since $\mathrm{Tot}(X \otimes_R A)$ is acyclic, so is $\mathrm{Tot}(X' \otimes_R A)$, completing the proof.

For a module M and $p \in \mathbb{Z}$, write $M[-p]$ for the complex with M in degree p and 0 elsewhere, as in (57.1).

Proposition 59.2.5: Unions and Bounded-Above Complexes of Flat Modules Are K-Flat

1. Let X be a complex of R-modules and $X_0 \subset X_1 \subset \cdots$ subcomplexes with $X = \bigcup_m X_m$. Suppose that every X_m is K-flat, and that $X_m^i \otimes_R N \to X^i \otimes_R N$ is injective for all m and i and every R-module N. Then X is K-flat.
2. Every bounded-above complex of flat R-modules is K-flat.

***Proof*:**

1. Let A be acyclic. The chain map $\mathrm{Tot}(X_m \otimes_R A) \to \mathrm{Tot}(X \otimes_R A)$ induced by the inclusion is, in each degree, a direct sum of the maps $X_m^i \otimes_R A^j \to X^i \otimes_R A^j$, which are injective by hypothesis. Identify $\mathrm{Tot}(X_m \otimes_R A)$ with its image T_m, a subcomplex. Then $T_0 \subset T_1 \subset \cdots$, and every element of $\mathrm{Tot}(X \otimes_R A)^n$ lies in some T_m: it is a finite sum of elementary tensors $x \otimes a$, and each x lies in some X_m. Let z be a cocycle of $\mathrm{Tot}(X \otimes_R A)$ of degree n, and choose m with $z \in T_m^n$. Then z is a cocycle of T_m, which is acyclic because X_m is K-flat, so $z = dw$ for some $w \in T_m^{n-1}$, and z is a coboundary of $\mathrm{Tot}(X \otimes_R A)$.
2. Let F be a bounded-above complex of flat modules and A an acyclic complex.

   Step 1: one flat module. For a flat module M in degree p, $\mathrm{Tot}(M[-p] \otimes_R A)^n = M \otimes_R A^{n-p}$, with differential $(-1)^p(1 \otimes d_A)$ by definition 57.4.12. The exact functor $M \otimes_R -$ carries the acyclic complex A to an acyclic complex, and the sign changes no kernel or image, so $\mathrm{Tot}(M[-p] \otimes_R A)$ is acyclic.

   Step 2: bounded complexes. Suppose $F^i = 0$ outside $a \le i \le b$, and induct on $b - a$, the case $b = a$ being Step 1. As $F^{b+1} = 0$, the top term $F^b[-b]$ is a subcomplex of F, and the quotient F'' has the terms F^i for $a \le i \le b-1$. In each degree $0 \to F^b[-b] \to F \to F'' \to 0$ is split, so it remains split exact after applying $- \otimes_R A^j$, and

   $$0 \to \mathrm{Tot}\big(F^b[-b] \otimes_R A\big) \to \mathrm{Tot}(F \otimes_R A) \to \mathrm{Tot}(F'' \otimes_R A) \to 0$$

   is a short exact sequence of complexes. The outer complexes are acyclic by Step 1 and by induction, so the long exact sequence of theorem 56.1.20 makes the middle one acyclic.

   Step 3: bounded-above complexes. Let $X_m \subset F$ be the subcomplex with $X_m^i = F^i$ for $i \ge -m$ and $X_m^i = 0$ for $i < -m$. It is a subcomplex because the differential raises degree, it is bounded because F is bounded above, and its terms are flat, so it is K-flat by Step 2. The X_m increase with union F, and each $X_m^i \to F^i$ is an identity or the inclusion of 0, so it stays injective after $- \otimes_R N$. Part (1) makes F K-flat, completing the proof.

Part (2) is [98, Tag 064K]. Part (1) is a special case of [98, Tag 06Y3], which shows, with no injectivity hypothesis, that every filtered colimit of K-flat complexes is K-flat, using that filtered colimits of

modules are exact and commute with tensor products. The injectivity hypothesis in (1) makes each $\mathrm{Tot}(X_m \otimes_R A)$ a subcomplex of $\mathrm{Tot}(X \otimes_R A)$, so that a cocycle can be treated inside one of them.

Example 59.2.6: An Acyclic Free Complex over $\mathbb{Z}/4$ That Is Not K-Flat

Let I be the complex of example 59.1.7, as in example 59.2.2(3), and let P be the complex

$$\cdots \xrightarrow{2} \mathbb{Z}/4 \xrightarrow{2} \mathbb{Z}/4 \xrightarrow{2} \mathbb{Z}/4 \to 0$$

with the last $\mathbb{Z}/4$ in degree 0, and $\pi\colon P \to \mathbb{Z}/2$ the reduction map in degree 0. The kernel of the reduction is $2\mathbb{Z}/4$, the image of the last differential, and in every negative degree the kernel and the image of multiplication by 2 are $2\mathbb{Z}/4$, so π is a quasi-isomorphism. Now P is a bounded-above complex of free, hence flat, modules (corollary 17.5.5), so it is K-flat by proposition 59.2.5(2). As I is acyclic, $\mathrm{Tot}(P \otimes I)$ is acyclic, and so is $\mathrm{Tot}(I \otimes P)$ by lemma 59.2.4(1). On the other hand $\mathrm{Tot}(I \otimes \mathbb{Z}/2)$ has $\mathbb{Z}/4 \otimes \mathbb{Z}/2 \cong \mathbb{Z}/2$ in every degree with differential multiplication by 2, which is zero on $\mathbb{Z}/2$, so its cohomology is $\mathbb{Z}/2$ in every degree. Hence $\mathrm{Tot}(I \otimes \pi)$ is not a quasi-isomorphism, and I is not K-flat by lemma 59.2.4(3).

The resolutions are built from the canonical truncations $\tau^{\leq n}X$ of definition 56.1.12. Each is bounded above, so it has a projective resolution by theorem 56.2.17, and the resolutions can be chosen so that each is a degreewise direct summand of the next. K-projectivity of their union then reduces to the acyclicity of the limit of a tower of acyclic complexes in the sense of definition 59.1.15, which lemma 59.1.17 gives.

Theorem 59.2.7: Every Complex of Modules Has a K-Projective Resolution

Let R be a commutative ring.

1. Every complex X of R-modules has a K-projective resolution $\pi\colon P \to X$ in which every P^i is projective and P is also K-flat.
2. Every K-projective complex of R-modules is K-flat.

***Proof*:**

1. *Step 1: extending a resolution along a chain map.* Let $f\colon P' \to B$ be a chain map between bounded-above complexes, with every P'^i projective. The claim is that there are a bounded-above complex S of projectives, a complex P'' with $P''^i = S^{i+1} \oplus P'^i$ containing P' as the subcomplex of elements $(0, y)$, and a quasi-isomorphism $h\colon P'' \to B$ with $h(0, y) = f(y)$. The cone $MC(f)$ is bounded above, so theorem 56.2.17 gives a quasi-isomorphism $g\colon S \to MC(f)[-1]$ with S a bounded-above complex of projectives. By definition 56.1.23 and (57.1), $MC(f)[-1]^i = P'^i \oplus B^{i-1}$ with differential $(p, b) \mapsto (dp,\ -fp - db)$. So $g = (g', g'')$ with $g'^i\colon S^i \to P'^i$ and $g''^i\colon S^i \to B^{i-1}$, and $gd = dg$ reads

$$g'd = dg', \qquad g''d + dg'' = -fg' \tag{59.1}$$

Thus $g'\colon S \to P'$ is a chain map. Let $P'' := MC(-g')$, with $P''^i = S^{i+1} \oplus P'^i$ and $d(x, y) = (-dx,\ -g'x + dy)$, and set $h(x, y) := g''x + fy$. By (59.1),

$$h\big(d(x, y)\big) = -g''dx - fg'x + fdy = dg''x + fdy = d\,h(x, y)$$

so h is a chain map, and $h(0,y) = f(y)$. The cone $MC(h)$ has terms $S^{i+2} \oplus P'^{i+1} \oplus B^i$, the same as $MC(g)[1]$, and the two differentials are

$$d_{MC(h)}(x,y,b) = \big(dx,\ g'x - dy,\ g''x + fy + db\big)$$
$$d_{MC(g)[1]}(x,y,b) = \big(dx,\ -g'x - dy,\ -g''x + fy + db\big)$$

so $(x,y,b) \mapsto (-x,y,b)$ is an isomorphism of complexes $MC(h) \to MC(g)[1]$. As g is a quasi-isomorphism, $MC(g)$ is acyclic by proposition 56.1.26, hence so are $MC(g)[1]$ and $MC(h)$, and h is a quasi-isomorphism by proposition 56.1.26.

Step 2: resolving the truncations. Write $X_n := \tau^{\leq n} X$ for $n \geq 0$, so that $X_0 \subset X_1 \subset \cdots$ are bounded-above subcomplexes of X by definition 56.1.12. Let $f_0 \colon P_0 \to X_0$ be a projective resolution, from theorem 56.2.17. Given a quasi-isomorphism $f_{n-1} \colon P_{n-1} \to X_{n-1}$ from a bounded-above complex of projectives, apply Step 1 to f_{n-1} followed by the inclusion $X_{n-1} \subset X_n$. This gives a bounded-above complex S_n of projectives, a complex P_n with $P_n^i = S_n^{i+1} \oplus P_{n-1}^i$ containing P_{n-1}, and a quasi-isomorphism $f_n \colon P_n \to X_n$ extending f_{n-1}.

Step 3: the union. Let $P := \bigcup_n P_n$, the complex with $P^i = P_0^i \oplus \bigoplus_{n \geq 1} S_n^{i+1}$ whose differential restricts to that of each P_n. A homomorphism out of a direct sum is a family of homomorphisms, and each member lifts along a surjection, so P^i is projective by theorem 17.2.4(2). The f_n are compatible, so they define a chain map $\pi \colon P \to X$. Fix i. For $n \geq i$, $H^i(P_n) \to H^i(X_n)$ is bijective, and so is $H^i(X_n) \to H^i(X)$ by proposition 56.1.14. A cocycle of P of degree i lies in some P_n with $n \geq i$, so $H^i(\pi)$ is surjective, since $H^i(P_n) \to H^i(X)$ is, and injective: if $\pi(z)$ is a coboundary, then $[z] = 0$ in $H^i(P_n)$, so z is a coboundary in $P_n \subset P$. So π is a quasi-isomorphism.

Step 4: P is K-projective. Let A be acyclic. The complexes $\mathrm{Hom}^\bullet(P_n, A)$ for $n \geq 0$, with the restriction maps $\mathrm{Hom}^\bullet(P_{n+1}, A) \to \mathrm{Hom}^\bullet(P_n, A)$, which are chain maps by lemma 57.4.3(2), form a tower of complexes of R-modules $\mathrm{Hom}^\bullet(P_\bullet, A)$ in the sense of definition 59.1.15. A homomorphism $P^i \to A^{i+k}$ is the same as a family of homomorphisms $P_n^i \to A^{i+k}$ compatible with the restrictions, since $P^i = \bigcup_n P_n^i$, and a product of limits is the limit of the products, so the restrictions $\mathrm{Hom}^\bullet(P, A) \to \mathrm{Hom}^\bullet(P_n, A)$ induce an isomorphism of complexes $\mathrm{Hom}^\bullet(P, A) \cong \varprojlim \mathrm{Hom}^\bullet(P_\bullet, A)$. Each restriction $\mathrm{Hom}^k(P_{n+1}, A) \to \mathrm{Hom}^k(P_n, A)$ is surjective, since a homomorphism on P_n^i extends by 0 on the summand S_{n+1}^{i+1} of P_{n+1}^i. Each P_n is a bounded-above complex of projectives, so it is K-projective by example 59.2.2(1), and $\mathrm{Hom}^\bullet(P_n, A)$ is acyclic. In the exact sequence of lemma 59.1.17 for this tower, the outer terms are $\varprojlim{}^1$ and $\varprojlim$ of towers of zero modules, so they vanish, and $H^m \mathrm{Hom}^\bullet(P, A) = 0$ for every m. In particular $\mathrm{Hom}_{\mathrm{K}(R\text{-Mod})}(P, A) = H^0 \mathrm{Hom}^\bullet(P, A) = 0$.

Step 5: P is K-flat. Each P_n is a bounded-above complex of projective, hence flat, modules (corollary 17.5.5), so it is K-flat by proposition 59.2.5(2). Each P_n^i is a direct summand of P^i, so $P_n^i \otimes_R N \to P^i \otimes_R N$ is split injective for every module N, and proposition 59.2.5(1) makes P K-flat.

2. Let P be K-projective, and let $\pi \colon P' \to P$ be the resolution of (1), with P' K-projective and

K-flat. By lemma 59.2.3(3), π is a homotopy equivalence, and P is K-flat by lemma 59.2.4(4), completing the proof.

Part (1) is the K-projective half of [95, Theorem C], and Step 1 of its proof is the inductive step in the proof of [95, Lemma 3.3], written out at the level of chain maps. [98, Tag 06XX] constructs a variant whose resolutions are also surjective in each degree. Part (2) is [95, Proposition 5.8], here for modules over a commutative ring. Two K-projective resolutions $\pi\colon P \to Y$ and $\pi'\colon P' \to Y$ are related by a unique morphism $c\colon P \to P'$ of $\mathrm{K}(R\text{-Mod})$ with $Q(\pi')Q(c) = Q(\pi)$, by lemma 59.2.3(2), and the same uniqueness in the other direction makes c an isomorphism of $\mathrm{K}(R\text{-Mod})$, that is a homotopy equivalence.

Example 59.2.8: A K-Projective Resolution of $\mathbb{Z}/2$ in Every Degree

Let $R = \mathbb{Z}$ and let V be the complex with $V^k = \mathbb{Z}/2$ for every $k \in \mathbb{Z}$ and every differential zero. For each k, let E_k be the complex $\mathbb{Z}s_k \xrightarrow{2} \mathbb{Z}t_k$ with s_k in degree $k-1$, t_k in degree k and $ds_k = 2t_k$, and let $P := \bigoplus_k E_k$. Then

$$P^i = \mathbb{Z}t_i \oplus \mathbb{Z}s_{i+1}, \qquad dt_i = 0, \qquad ds_{i+1} = 2t_{i+1}$$

Let $\pi\colon P \to V$ send t_i to 1 and s_{i+1} to 0. It is a chain map, because $\pi(ds_{i+1}) = \pi(2t_{i+1}) = 0$. The cocycles of P in degree i are $\mathbb{Z}t_i$, the coboundaries are $2\mathbb{Z}t_i$, so $H^i(P) \cong \mathbb{Z}/2$ generated by the class of t_i, which π sends to the generator of V^i. So π is a quasi-isomorphism. For an acyclic A, a family of maps out of P^i is a family of maps out of the summands, so $\mathrm{Hom}^\bullet(P, A) = \prod_k \mathrm{Hom}^\bullet(E_k, A)$ as complexes. Each E_k is K-projective by example 59.2.2(1), so each factor is acyclic, and the product is acyclic by lemma 56.1.11. So P is a K-projective resolution of V, and it is K-flat by theorem 59.2.7(2).

Definition 59.2.9: Derived Tensor Product of Unbounded Complexes

For every complex Y of R-modules fix a K-projective resolution $\pi_Y\colon P_Y \to Y$. For a complex X of R-modules, the *derived tensor product* of X and Y is

$$X \otimes^L_R Y := \mathrm{Tot}(X \otimes_R P_Y)$$

regarded as an object of $D(R)$.

The resolutions exist by theorem 59.2.7(1), and every P_Y is K-flat by theorem 59.2.7(2). The formula is that of definition 57.4.15 with the bounded-above projective resolution replaced by a K-projective one, and proposition 59.2.21 identifies the two constructions on bounded-above complexes.

Example 59.2.10: $\mathbb{Z}/2 \otimes^L V$ for $\mathbb{Z}/2$ in Every Degree

Let V and P be as in example 59.2.8, and take $P_V := P$. Then $\mathbb{Z}/2 \otimes^L_{\mathbb{Z}} V = \mathrm{Tot}(\mathbb{Z}/2 \otimes_{\mathbb{Z}} P)$ has $\mathbb{Z}/2\, t_i \oplus \mathbb{Z}/2\, s_{i+1}$ in degree i, and every differential is 0, because $2 = 0$ in $\mathbb{Z}/2$. So

$$H^i\big(\mathbb{Z}/2 \otimes^L_{\mathbb{Z}} V\big) \cong \mathbb{Z}/2 \oplus \mathbb{Z}/2 \qquad \text{for every } i \in \mathbb{Z}$$

whereas $\mathrm{Tot}(\mathbb{Z}/2 \otimes_{\mathbb{Z}} V) = V$ has $\mathbb{Z}/2$ in each degree. The class of s_{i+1} spans the cohomology in degree i of the summand $\mathbb{Z}/2 \otimes_{\mathbb{Z}} E_{i+1}$, which is $\mathrm{Tor}^{\mathbb{Z}}_1(\mathbb{Z}/2, \mathbb{Z}/2) \cong \mathbb{Z}/2$ for the summand $\mathbb{Z}/2$ of V in degree $i+1$, placed in degree i as in theorem 57.4.18.

Proposition 59.2.11: The Unbounded Derived Tensor Product Is a Balanced Bifunctor

Let R be a commutative ring.

1. $\otimes^L_R$ is a bifunctor $D(R) \times D(R) \to D(R)$, and another choice of the K-projective resolutions changes it by a natural isomorphism.

2. If $\varphi\colon F \to X$ is a quasi-isomorphism with F K-flat, then both chain maps in

$$X \otimes^L_R Y = \operatorname{Tot}(X \otimes_R P_Y) \xleftarrow{\varphi\otimes 1} \operatorname{Tot}(F \otimes_R P_Y) \xrightarrow{1\otimes \pi_Y} \operatorname{Tot}(F \otimes_R Y)$$

are quasi-isomorphisms, so $X \otimes^L_R Y \cong \operatorname{Tot}(F \otimes_R Y)$ in $D(R)$. If $\psi\colon G \to Y$ is a quasi-isomorphism with G K-flat, then $X \otimes^L_R Y \cong \operatorname{Tot}(X \otimes_R G)$ in $D(R)$. In particular $X \otimes^L_R Y \cong \operatorname{Tot}(X \otimes_R Y)$ whenever X or Y is K-flat.

***Proof*:**

1. *Step 1: the first variable.* Fix Y. By lemma 59.2.4(2), $X \mapsto \operatorname{Tot}(X \otimes_R P_Y)$ is a functor $\mathrm{K}(R\text{-Mod}) \to \mathrm{K}(R\text{-Mod})$, and by lemma 59.2.4(3), P_Y being K-flat, it carries quasi-isomorphisms to quasi-isomorphisms. Followed by Q it inverts them, and $D(R)$ is the localization of $\mathrm{K}(R\text{-Mod})$ at the quasi-isomorphisms by theorem 57.2.4, so it factors uniquely through $D(R)$ by the universal property of definition 55.2.1.

   Step 2: the second variable. Let $\beta\colon Y \to Y'$ be a morphism of $D(R)$. By lemma 59.2.3(2) for the K-projective complex P_Y, there is a unique $\tilde{\beta}\colon P_Y \to P_{Y'}$ in $\mathrm{K}(R\text{-Mod})$ with $Q(\pi_{Y'})\,Q(\tilde{\beta}) = \beta\, Q(\pi_Y)$, namely the one with $Q(\tilde{\beta}) = Q(\pi_{Y'})^{-1}\beta\, Q(\pi_Y)$. For $\beta'\colon Y' \to Y''$, both $\tilde{\beta}'\tilde{\beta}$ and $\widetilde{\beta'\beta}$ satisfy the condition defining $\widetilde{\beta'\beta}$, so they are equal, and $\widetilde{\mathrm{id}_Y} = \mathrm{id}$. Set $X \otimes^L_R \beta := Q\big(\operatorname{Tot}(X \otimes \tilde{\beta})\big)$, a functor of β by lemma 59.2.4(2).

   Step 3: both variables. For $\alpha\colon X \to X'$ in $D(R)$, the square formed by $\alpha \otimes^L_R Y$, $\alpha \otimes^L_R Y'$, $X \otimes^L_R \beta$ and $X' \otimes^L_R \beta$ commutes. For $\alpha = Q(f)$ with f a chain map, both composites are $Q\big(\operatorname{Tot}(f \otimes \tilde{\beta})\big)$. For $\alpha = Q(s)^{-1}$ with s a quasi-isomorphism, the square is that of $Q(s)$ with two parallel sides inverted. Every morphism of $D(R)$ is $Q(f)\,Q(s)^{-1}$ by theorem 57.2.4, and squares of this shape paste along composites. Setting $\alpha \otimes^L_R \beta := (\alpha \otimes^L_R Y') \circ (X \otimes^L_R \beta)$, the commuting squares make $\otimes^L_R$ preserve composites in the pair (α, β), as in Step 3 of the proof of theorem 57.4.8.

   Step 4: other resolutions. Let $\pi'_Y\colon P'_Y \to Y$ be other K-projective resolutions. By lemma 59.2.3(2) there are unique morphisms $c_Y : P_Y \to P'_Y$ and $c'_Y : P'_Y \to P_Y$ of $\mathrm{K}(R\text{-Mod})$ with $Q(\pi'_Y)Q(c_Y) = Q(\pi_Y)$ and $Q(\pi_Y)Q(c'_Y) = Q(\pi'_Y)$. Both $c'_Y c_Y$ and id_{P_Y} satisfy the condition defining $\widetilde{\mathrm{id}_Y}$, so they are equal, and symmetrically $c_Y c'_Y = \mathrm{id}$. So $\operatorname{Tot}(X \otimes c_Y)$ is an isomorphism of $\mathrm{K}(R\text{-Mod})$. It is natural in X because Tot is a bifunctor, and in Y because $c_{Y'}\tilde{\beta}$ and $\tilde{\beta}'c_Y$, with $\tilde{\beta}'$ built from the primed resolutions, both satisfy $Q(\pi'_{Y'})\,Q(-) = \beta\, Q(\pi_Y)$ and are therefore equal.

2. The two chain maps in the display of (2) are quasi-isomorphisms by lemma 59.2.4(3), the

first because P_Y is K-flat and the second because F is, and inverting the first in $D(R)$ gives $X \otimes^L_R Y \cong \mathrm{Tot}(F \otimes_R Y)$. For the second statement apply the first with $F = P_X$, which is K-flat by theorem 59.2.7(2), to get $X \otimes^L_R Y \cong \mathrm{Tot}(P_X \otimes_R Y)$. The chain maps

$$\mathrm{Tot}(P_X \otimes_R Y) \xleftarrow{1\otimes\psi} \mathrm{Tot}(P_X \otimes_R G) \xrightarrow{\pi_X \otimes 1} \mathrm{Tot}(X \otimes_R G)$$

are quasi-isomorphisms by lemma 59.2.4(3), because P_X and G are K-flat. The last statement is the case $F = X$, $\varphi = \mathrm{id}$, or $G = Y$, $\psi = \mathrm{id}$, completing the proof.

By (2), a K-flat resolution of either variable computes $\otimes^L_R$, so a complex known to be K-flat needs no further resolution. A complex of flat modules need not be K-flat: the complex I of example 59.2.6 has free terms.

Theorem 59.2.12: Complexes of Flat Modules Are K-Flat When Submodules of Flat Modules Are Flat

Let R be a commutative ring in which every submodule of a flat R-module is flat. Then every complex of flat R-modules is K-flat.

***Proof*:**

Step 1: the truncations. Let F be a complex of flat modules, and write Z^m and B^{m+1} for the kernel and the image of $d^m \colon F^m \to F^{m+1}$. Both are submodules of flat modules, hence flat. The canonical truncation $\tau^{\leq m}F$ of definition 56.1.12 has the terms F^i for $i < m$, Z^m in degree m, and 0 above, so it is a bounded-above complex of flat modules, and it is K-flat by proposition 59.2.5(2).

Step 2: the union. The subcomplexes $\tau^{\leq 0}F \subset \tau^{\leq 1}F \subset \cdots$ of F have union F, since F^i is the term of $\tau^{\leq m}F$ in degree i once $m > i$. Fix m, i and a module N. For $i < m$ the map $(\tau^{\leq m}F)^i \otimes_R N \to F^i \otimes_R N$ is the identity, and for $i > m$ its source is 0. For $i = m$ it is the map $Z^m \otimes_R N \to F^m \otimes_R N$ induced by the inclusion. The functor $- \otimes_R N$ is right exact by theorem 17.5.1, the tensor product being symmetric over the commutative ring R, and its first left derived functor is $\mathrm{Tor}^R_1(-, N)$ by example 56.3.6(1). By theorem 56.3.11 and proposition 56.3.13(2), the short exact sequence $0 \to Z^m \to F^m \xrightarrow{d^m} B^{m+1} \to 0$ gives an exact sequence

$$\mathrm{Tor}^R_1(B^{m+1}, N) \to Z^m \otimes_R N \to F^m \otimes_R N$$

By theorem 56.5.8, $\mathrm{Tor}^R_1(B^{m+1}, N) \cong H^{-1}(B^{m+1} \otimes_R P_N)$ for a projective resolution P_N of N. The complex P_N is exact in degree -1, and the functor $B^{m+1} \otimes_R -$ is exact because B^{m+1} is flat, so it preserves kernels and images and $H^{-1}(B^{m+1} \otimes_R P_N) = 0$. Hence $Z^m \otimes_R N \to F^m \otimes_R N$ is injective, and proposition 59.2.5(1) makes F K-flat, completing the proof.

The hypothesis on R is used once, to make the cycle modules Z^m and the boundary modules B^{m+1} of F flat. Over $\mathbb{Z}/4$ it fails at the cycle modules $Z^m = 2\mathbb{Z}/4 \cong \mathbb{Z}/2$ of the complex I of example 59.2.6, which are submodules of the free module $\mathbb{Z}/4$. The module $\mathbb{Z}/2$ is not flat over $\mathbb{Z}/4$: tensoring the injection $\mathbb{Z}/2 \to \mathbb{Z}/4$, $1 \mapsto 2$, with $\mathbb{Z}/2$ gives the map $\mathbb{Z}/2 \to \mathbb{Z}/2$ sending 1 to $2 = 0$. Correspondingly, $Z^m \otimes \mathbb{Z}/2 \to I^m \otimes \mathbb{Z}/2$ is this zero map, so the injectivity hypothesis of proposition 59.2.5(1) fails for the truncations of I.

Corollary 59.2.13: Complexes of Torsion-Free Modules over a PID Are K-Flat

Let R be a principal ideal domain. Then every complex of torsion-free R-modules is K-flat. In particular every complex of torsion-free abelian groups is K-flat.

***Proof*:**
Over a principal ideal domain a module is flat if and only if it is torsion-free, by theorem 17.5.7, and a submodule of a torsion-free module is torsion-free by proposition 12.3.23(1). So every submodule of a flat R-module is flat, a complex of torsion-free R-modules is a complex of flat R-modules, and theorem 59.2.12 makes it K-flat. Abelian groups are the modules over the principal ideal domain $\mathbb{Z}$, completing the proof.

Example 59.2.14: Reduction Modulo n of a Torsion-Free Complex
Let F be a complex of torsion-free abelian groups and $n \geq 1$. By corollary 59.2.13, F is K-flat, so proposition 59.2.11(2) gives

$$F \otimes^{L}_{\mathbb{Z}} \mathbb{Z}/n \cong \operatorname{Tot}(F \otimes_{\mathbb{Z}} \mathbb{Z}/n) \cong F/nF$$

where F/nF has the terms F^k/nF^k and the induced differentials. Each F^k is torsion-free, so multiplication by n is injective on it, and $0 \to F \xrightarrow{n} F \to F/nF \to 0$ is a short exact sequence of complexes. Its long exact sequence (theorem 56.1.20) yields the short exact sequences

$$0 \to H^k(F)/nH^k(F) \to H^k\big(F \otimes^{L}_{\mathbb{Z}} \mathbb{Z}/n\big) \to \{c \in H^{k+1}(F) : nc = 0\} \to 0$$

For a specific case, let $F^k = \mathbb{Z}$ for every k, with d^k multiplication by 2 for k odd and zero for k even. Then $d^{k+1}d^k = 0$, since one of the two factors is zero, and $H^k(F)$ is $\mathbb{Z}/2$ for k even and 0 for k odd. For $n = 2$, the complex $F/2F$ has $\mathbb{Z}/2$ in every degree and every differential zero, so $H^k(F \otimes^{L}_{\mathbb{Z}} \mathbb{Z}/2) \cong \mathbb{Z}/2$ for every k. The sequence above agrees: for k even the left term is $\mathbb{Z}/2$ and the right term is 0, and for k odd the left term is 0 and the right term is $\mathbb{Z}/2$.

The category R-Mod is a Grothendieck abelian category by example 59.1.5(1), so theorem 59.1.19 gives every complex of R-modules a K-injective resolution.

Definition 59.2.15: $R\mathrm{Hom}$ of Unbounded Complexes

For a complex Z of R-modules let $\iota_Z \colon Z \to I_Z$ be the K-injective resolution fixed in corollary 59.1.22, with $\mathcal{A} = R$-Mod. For a complex Y of R-modules set

$$R\mathrm{Hom}_R(Y, Z) := \mathrm{Hom}^{\bullet}(Y, I_Z)$$

regarded as an object of $D(R)$.

The formula is that of definition 57.4.6 with the bounded-below injective resolution replaced by a K-injective one, and proposition 59.2.21 identifies the two constructions when the second variable is bounded below.

Example 59.2.16: $R\mathrm{Hom}$ out of R and into a K-Injective Complex

1. Let $Y = R$ in degree 0. By definition 57.4.1, $\mathrm{Hom}^n(R, I_Z) = \mathrm{Hom}_R(R, I_Z^n)$ with differential $\varphi \mapsto d_{I_Z}\varphi$, and evaluation at 1 identifies it with I_Z^n. So $R\mathrm{Hom}_R(R, Z)$ is the complex I_Z, which $Q(\iota_Z)$ makes isomorphic to Z in $D(R)$.

2. Let J be a K-injective complex. Then $\iota_J \colon J \to I_J$ is a quasi-isomorphism between K-injective complexes, hence a homotopy equivalence by corollary 59.1.13(1). For every complex Y the chain map $\mathrm{Hom}^\bullet(Y, \iota_J)$ is then a homotopy equivalence by lemma 57.4.3(2), hence a quasi-isomorphism by proposition 56.1.33, and $R\mathrm{Hom}_R(Y, J) \cong \mathrm{Hom}^\bullet(Y, J)$ in $D(R)$. For $R = \mathbb{Z}$, J may be the complex $\mathbb{Q} \to \mathbb{Q}/\mathbb{Z}$ of example 57.4.7, in degrees 0 and 1, a bounded-below complex of injective abelian groups and so K-injective by corollary 59.1.12. Then $R\mathrm{Hom}_\mathbb{Z}(Y, J) \cong \mathrm{Hom}^\bullet(Y, J)$ for every complex Y of abelian groups, bounded or not.

Proposition 59.2.17: $R\mathrm{Hom}$ of Unbounded Complexes Is a Bifunctor

Let R be a commutative ring.

1. $R\mathrm{Hom}_R$ is a bifunctor $D(R)^{\mathrm{op}} \times D(R) \to D(R)$, and another choice of the K-injective resolutions changes it by a natural isomorphism.

2. If $\pi \colon P \to Y$ is a K-projective resolution, then both chain maps in

$$R\mathrm{Hom}_R(Y, Z) = \mathrm{Hom}^\bullet(Y, I_Z) \xrightarrow{\pi^*} \mathrm{Hom}^\bullet(P, I_Z) \xleftarrow{(\iota_Z)_*} \mathrm{Hom}^\bullet(P, Z)$$

are quasi-isomorphisms. In particular $R\mathrm{Hom}_R(Y, Z) \cong \mathrm{Hom}^\bullet(P, Z)$ in $D(R)$.

***Proof*:**

1. *Step 1: the second variable.* For a morphism $\gamma \colon Z \to Z'$ of $D(R)$ let $I_\gamma \colon I_Z \to I_{Z'}$ be the morphism of $\mathrm{K}(R\text{-Mod})$ of corollary 59.1.22(1), the unique one with $Q(I_\gamma)\, Q(\iota_Z) = Q(\iota_{Z'})\, \gamma$, a functor of γ by that corollary. Set $R\mathrm{Hom}_R(Y, \gamma) := Q\big(\mathrm{Hom}^\bullet(Y, I_\gamma)\big)$, a functor of γ by lemma 57.4.3(2).

   Step 2: the first variable. Fix Z. By lemma 57.4.3(2), $Y \mapsto \mathrm{Hom}^\bullet(Y, I_Z)$ is a functor $\mathrm{K}(R\text{-Mod})^{\mathrm{op}} \to \mathrm{K}(R\text{-Mod})$, and by corollary 59.1.14 for the K-injective complex I_Z it carries quasi-isomorphisms to quasi-isomorphisms, so followed by Q it carries them to isomorphisms. By theorem 57.2.4, $D(R)^{\mathrm{op}}$ is the localization of $\mathrm{K}(R\text{-Mod})^{\mathrm{op}}$ at the quasi-isomorphisms, and the universal property of definition 55.2.1 factors the functor uniquely through $D(R)^{\mathrm{op}}$. The factorization is $R\mathrm{Hom}_R(-, Z)$.

   Step 3: both variables and other resolutions. Steps 3 and 4 of the proof of theorem 57.4.8 use its Steps 1 and 2, lemma 57.4.3(2), theorem 57.2.4, and the bijectivity of Q into the chosen resolutions, which there is lemma 57.4.4(2). With Steps 1 and 2 above and proposition 59.1.11(3) for that bijectivity, the same arguments show that the square formed by $R\mathrm{Hom}_R(\alpha, Z)$, $R\mathrm{Hom}_R(\alpha, Z')$, $R\mathrm{Hom}_R(Y, \gamma)$ and $R\mathrm{Hom}_R(Y', \gamma)$ commutes for all $\alpha \colon Y' \to Y$ and $\gamma \colon Z \to Z'$ in $D(R)$, so that $R\mathrm{Hom}_R$ is a bifunctor, and that another

choice $\iota'_Z\colon Z \to I'_Z$ of K-injective resolutions changes it by the natural isomorphism $\mathrm{Hom}^\bullet(Y, c_Z)$, where c_Z is the unique morphism of $\mathrm{K}(R\text{-Mod})$ with $Q(c_Z)Q(\iota_Z) = Q(\iota'_Z)$.

2. The map π^* is a quasi-isomorphism by corollary 59.1.14, applied to the quasi-isomorphism π and the K-injective complex I_Z. The map $(\iota_Z)_*$ is one by lemma 59.2.3(1), applied to the K-projective complex P and the quasi-isomorphism ι_Z, completing the proof.

Example 59.2.18: $R\mathrm{Hom}(\mathbb{Z}/2, V)$ for $\mathbb{Z}/2$ in Every Degree

Let $R = \mathbb{Z}$, let V be the complex of example 59.2.8, and let E be the complex $\mathbb{Z}s \xrightarrow{2} \mathbb{Z}t$ in degrees -1 and 0, a K-projective resolution of $\mathbb{Z}/2$ by example 59.2.2(1). By proposition 59.2.17(2), $R\mathrm{Hom}_\mathbb{Z}(\mathbb{Z}/2, V) \cong \mathrm{Hom}^\bullet(E, V)$, and

$$\mathrm{Hom}^m(E, V) = \mathrm{Hom}(\mathbb{Z}s, V^{m-1}) \times \mathrm{Hom}(\mathbb{Z}t, V^m) \cong \mathbb{Z}/2 \oplus \mathbb{Z}/2$$

For φ of degree m, the component of $D\varphi$ on s is $d_V\varphi(s) - (-1)^m\varphi(2t) = 0$, since $d_V = 0$ and $2\varphi(t) = 0$ in $\mathbb{Z}/2$, and its component on t is $d_V\varphi(t) = 0$. So every differential vanishes, and

$$H^m R\mathrm{Hom}_\mathbb{Z}(\mathbb{Z}/2, V) \cong \mathbb{Z}/2 \oplus \mathbb{Z}/2 \qquad \text{for every } m \in \mathbb{Z}$$

By lemma 59.2.3(2) and lemma 57.4.3(1) this group is also

$$\mathrm{Hom}_{D(\mathbb{Z})}(E, V[m]) \cong \mathrm{Hom}_{D(\mathbb{Z})}(\mathbb{Z}/2, V[m])$$

The complex V is bounded neither below nor above, so definition 57.4.6 does not apply to this pair.

Theorem 59.2.19: The Unbounded Tensor-Hom Adjunction

Let R be a commutative ring and let X, Y, Z be complexes of R-modules. There is an isomorphism

$$\mathrm{Hom}_{D(R)}\big(X \otimes^L_R Y,\ Z\big) \cong \mathrm{Hom}_{D(R)}\big(X,\ R\mathrm{Hom}_R(Y, Z)\big)$$

natural in X and Z.

***Proof*:**
Step 1: the adjunction for complexes. For complexes X, Y, Z, the map

$$\Phi\colon \mathrm{Hom}^\bullet\big(\mathrm{Tot}(X \otimes_R Y), Z\big) \to \mathrm{Hom}^\bullet\big(X, \mathrm{Hom}^\bullet(Y, Z)\big), \qquad \Phi(\varphi)(x)(y) := \varphi(x \otimes y)$$

is an isomorphism of complexes. By definition 57.4.1, the source in degree n is the product over all $m \in \mathbb{Z}$ of $\mathrm{Hom}_R\big(\mathrm{Tot}(X \otimes_R Y)^m, Z^{m+n}\big)$. A homomorphism out of the direct sum $\mathrm{Tot}(X \otimes_R Y)^m = \bigoplus_{i+j=m} X^i \otimes_R Y^j$ is a family of homomorphisms out of its summands, so the source is the product over all pairs (i, j) of $\mathrm{Hom}_R(X^i \otimes_R Y^j, Z^{i+j+n})$. The target in degree n is the product over all i of $\mathrm{Hom}_R\big(X^i, \mathrm{Hom}^{i+n}(Y, Z)\big)$, where $\mathrm{Hom}^{i+n}(Y, Z)$ is the product over all j of $\mathrm{Hom}_R(Y^j, Z^{i+j+n})$, and a homomorphism into a product is a family, so the target is the product over the same pairs of $\mathrm{Hom}_R\big(X^i, \mathrm{Hom}_R(Y^j, Z^{i+j+n})\big)$. On each factor Φ is the bijection of theorem 15.3.9, with both rings equal to R. The comparison of differentials in Step 1 of the proof of theorem 57.4.19 is a computation on $x \otimes y$ for $x \in X^i$ and $y \in Y^j$, and it uses no bound.

Step 2: resolutions. Let $\pi_X\colon P_X \to X$ and $\pi_Y\colon P_Y \to Y$ be the K-projective resolutions of definition 59.2.9 and $\iota_Z\colon Z \to I_Z$ the K-injective resolution of definition 59.2.15. Set $T := \mathrm{Tot}(P_X \otimes_R P_Y)$ and $H := \mathrm{Hom}^\bullet(P_Y, I_Z)$. By proposition 59.2.11(2), with $F = P_X$ and $\varphi = \pi_X$, the chain map $\pi_X \otimes 1\colon T \to \mathrm{Tot}(X \otimes_R P_Y) = X \otimes^L_R Y$ is a quasi-isomorphism, and by proposition 59.2.17(2) so is $\pi_Y^*\colon R\mathrm{Hom}_R(Y, Z) \to H$.

Step 3: T is K-projective. Let A be acyclic. By Step 1, $\mathrm{Hom}^\bullet(T, A) \cong \mathrm{Hom}^\bullet\big(P_X, \mathrm{Hom}^\bullet(P_Y, A)\big)$. The complex $\mathrm{Hom}^\bullet(P_Y, A)$ is acyclic because P_Y is K-projective, so the right side is acyclic because P_X is K-projective. Hence $\mathrm{Hom}_{\mathrm{K}(R\text{-Mod})}(T, A) = H^0\mathrm{Hom}^\bullet(T, A) = 0$.

Step 4: the chain of isomorphisms. Composing with $Q(\pi_X \otimes 1)$ and $Q(\iota_Z)$, then using lemma 59.2.3(2) for T, lemma 57.4.3(1), Step 1, lemma 57.4.3(1) again, lemma 59.2.3(2) for P_X, and finally $Q(\pi_X)$ and $Q(\pi_Y^*)$,

$$\begin{aligned}\mathrm{Hom}_{D(R)}(X \otimes^L_R Y, Z) &\cong \mathrm{Hom}_{D(R)}(T, I_Z) \cong \mathrm{Hom}_{\mathrm{K}(R\text{-Mod})}(T, I_Z) = H^0\mathrm{Hom}^\bullet(T, I_Z)\\ &\cong H^0\mathrm{Hom}^\bullet(P_X, H) = \mathrm{Hom}_{\mathrm{K}(R\text{-Mod})}(P_X, H) \cong \mathrm{Hom}_{D(R)}(P_X, H)\\ &\cong \mathrm{Hom}_{D(R)}\big(X, R\mathrm{Hom}_R(Y, Z)\big)\end{aligned}$$

Step 5: naturality. A morphism $\alpha\colon X \to X'$ of $D(R)$ lifts, by lemma 59.2.3(2), to a unique $\tilde{\alpha}\colon P_X \to P_{X'}$ in $\mathrm{K}(R\text{-Mod})$ with $Q(\pi_{X'})Q(\tilde{\alpha}) = \alpha\, Q(\pi_X)$. The functor of Step 1 of the proof of proposition 59.2.11 sends $Q(g)$ to $Q(\mathrm{Tot}(g \otimes 1))$ for chain maps g, so applying it to this identity shows that $\alpha \otimes^L_R Y$ acts on T as $Q\big(\mathrm{Tot}(\tilde{\alpha} \otimes 1)\big)$. A morphism $\gamma\colon Z \to Z'$ acts on I_Z as $Q(I_\gamma)$, with I_γ as in Step 1 of the proof of proposition 59.2.17(1), and π_Y^* commutes with $(I_\gamma)_*$. Each isomorphism of Step 4 commutes with precomposition by these and postcomposition by I_γ: the uses of lemma 57.4.3(1) by its part (3), the uses of lemma 59.2.3(2) because Q is a functor, and Φ because $\Phi\big(\varphi \circ \mathrm{Tot}(\tilde{\alpha} \otimes 1)\big) = \Phi(\varphi) \circ \tilde{\alpha}$ and $\Phi(I_\gamma \circ \varphi) = (I_\gamma)_* \circ \Phi(\varphi)$ by the formula for Φ. So the composite isomorphism is natural in X and Z, completing the proof.

For fixed Y, the theorem says that $- \otimes^L_R Y$ is left adjoint to $R\mathrm{Hom}_R(Y, -)$ as functors $D(R) \to D(R)$. In the bounded case of theorem 57.4.19 the two functors have the different domains $D^-(R)$ and $D^+(R)$, which is also the form of Weibel [101] Theorem 10.8.7.

Example 59.2.20: Morphisms out of F/nF into Shifts of $\mathbb{Z}$

Let F be a complex of torsion-free abelian groups, $n \geq 1$ and $k \in \mathbb{Z}$. The complex $C_n = (\mathbb{Z} \xrightarrow{n} \mathbb{Z})$ in degrees -1 and 0 is a K-projective resolution of $\mathbb{Z}/n$ by example 59.2.2(1), so $R\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}/n, \mathbb{Z}[k]) \cong \mathrm{Hom}^\bullet(C_n, \mathbb{Z}[k])$ by proposition 59.2.17(2). As $\mathbb{Z}[k]$ is $\mathbb{Z}$ in degree $-k$, this complex is $\mathbb{Z} \to \mathbb{Z}$ in degrees $-k$ and $1-k$, with differential multiplication by $-(-1)^k n$, so its only cohomology is $\mathbb{Z}/n$ in degree $1-k$. A complex C whose only cohomology is in degree j is isomorphic in $D(\mathbb{Z})$ to $H^j(C)[-j]$, through $C \leftarrow \tau^{\leq j}C \to \tau^{\geq j}\tau^{\leq j}C$, both quasi-isomorphisms by proposition 56.1.14, the last complex being $Z^j(C)/B^j(C) = H^j(C)$ in degree j. So $R\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}/n, \mathbb{Z}[k]) \cong (\mathbb{Z}/n)[k-1]$, and with example 59.2.14 the theorem gives

$$\mathrm{Hom}_{D(\mathbb{Z})}\big(F/nF,\ \mathbb{Z}[k]\big) \cong \mathrm{Hom}_{D(\mathbb{Z})}\big(F,\ (\mathbb{Z}/n)[k-1]\big)$$

for every complex F of torsion-free abelian groups, bounded or not. For $F = \mathbb{Z}$ in degree 0 and $k = 1$, both sides are $\mathbb{Z}/n$: the left is $\mathrm{Ext}^1_{\mathbb{Z}}(\mathbb{Z}/n, \mathbb{Z}) \cong \mathbb{Z}/n$ by theorem 57.4.10(2) and

example 57.4.7, and the right is $\mathrm{Hom}_{\mathbb{Z}}(\mathbb{Z}, \mathbb{Z}/n) \cong \mathbb{Z}/n$ by the last statement of theorem 57.4.10(2).

In the commutative case, as explained before theorem 57.4.19, definition 57.4.15 gives $\otimes^{\mathbf{L}}_R$ on $D^-(R) \times D^-(R)$ and definition 57.4.6 gives $R\mathrm{Hom}_R$ on $D(R)^{\mathrm{op}} \times D^+(R)$.

Proposition 59.2.21: The Unbounded Constructions Extend the Bounded Ones

Let R be a commutative ring.

1. On $D^-(R) \times D^-(R)$, there is a natural isomorphism from the derived tensor product of definition 57.4.15 to that of definition 59.2.9.
2. On $D(R)^{\mathrm{op}} \times D^+(R)$, there is a natural isomorphism from the $R\mathrm{Hom}$ of definition 57.4.6 to that of definition 59.2.15.

***Proof*:**

1. For a bounded-above complex Y, let $\pi^-_Y \colon P^-_Y \to Y$ be the projective resolution fixed in definition 57.4.15. It is K-projective by example 59.2.2(1), so the argument of Step 4 of the proof of proposition 59.2.11(1) applies to the two K-projective resolutions P^-_Y and P_Y. It gives an isomorphism $c_Y \colon P^-_Y \to P_Y$ of $\mathrm{K}(R\text{-Mod})$ with $Q(\pi_Y)Q(c_Y) = Q(\pi^-_Y)$, and $\mathrm{Tot}(X \otimes c_Y)$ is an isomorphism from the bounded construction to the unbounded one. It is natural in X: for a chain map f the naturality square commutes because Tot is a bifunctor, and every morphism of $D^-(R)$ is a composite of morphisms $Q(f)$ and $Q(s)^{-1}$ of bounded-above complexes, as in Step 3 of the proof of theorem 57.4.17. For $\beta \colon Y \to Y'$ in $D^-(R)$, the morphism $\tilde{\beta}^- \colon P^-_Y \to P^-_{Y'}$ of Step 2 of the proof of theorem 57.4.17 satisfies $Q(\pi^-_{Y'})Q(\tilde{\beta}^-) = \beta\, Q(\pi^-_Y)$, so $c_{Y'}\tilde{\beta}^-$ and $\tilde{\beta} c_Y$ both satisfy $Q(\pi_{Y'})\, Q(-) = \beta\, Q(\pi^-_Y)$, and they are equal by the uniqueness in lemma 59.2.3(2) for the K-projective complex P^-_Y. This is naturality in Y.

2. For a bounded-below complex Z, let $\iota^+_Z \colon Z \to I^+_Z$ be the injective resolution fixed in definition 57.4.6. By proposition 59.1.11(3) for the K-injective complex I_Z there is a unique $c_Z \colon I^+_Z \to I_Z$ in $\mathrm{K}(R\text{-Mod})$ with $Q(c_Z)Q(\iota^+_Z) = Q(\iota_Z)$, and by lemma 57.4.4(2), whose source complex may be arbitrary, there is a unique $c'_Z \colon I_Z \to I^+_Z$ with $Q(c'_Z)Q(\iota_Z) = Q(\iota^+_Z)$. Both $c'_Z c_Z$ and id satisfy the condition $Q(-)Q(\iota^+_Z) = Q(\iota^+_Z)$, so they are equal by the uniqueness in lemma 57.4.4(2), and $c_Z c'_Z = \mathrm{id}$ by the uniqueness for I_Z. So $\mathrm{Hom}^\bullet(Y, c_Z)$ is an isomorphism of $\mathrm{K}(R\text{-Mod})$ from the bounded construction to the unbounded one. Naturality in Y holds for morphisms $Q(f)$, with f a chain map, because $\mathrm{Hom}^\bullet$ is a bifunctor (lemma 57.4.3(2)), and for morphisms $Q(s)^{-1}$ by inverting, every morphism of $D(R)$ being $Q(f)Q(s)^{-1}$ (theorem 57.2.4). For naturality in Z, let $\gamma \colon Z \to Z'$ be a morphism of $D^+(R)$ and $\tilde{\gamma}^+ \colon I^+_Z \to I^+_{Z'}$ its lift from theorem 57.4.8(1), with $Q(\tilde{\gamma}^+)Q(\iota^+_Z) = Q(\iota^+_{Z'})\gamma$. Then $c_{Z'}\tilde{\gamma}^+$ and $I_\gamma c_Z$, with I_γ as in Step 1 of the proof of proposition 59.2.17(1), both satisfy $Q(-)Q(\iota^+_Z) = Q(\iota_{Z'})\gamma$. They are equal, because proposition 59.1.11(3) for $I_{Z'}$ makes Q injective on $\mathrm{Hom}_{\mathrm{K}(R\text{-Mod})}(I^+_Z, I_{Z'})$ and $Q(\iota^+_Z)$ is invertible. Applying $\mathrm{Hom}^\bullet(Y, -)$ gives naturality in Z, completing the proof.

By (1) and example 57.4.16, for $m, n \geq 1$ and $d = \gcd(m, n)$, the complex $\mathbb{Z}/m \otimes^{\mathbf{L}}_{\mathbb{Z}} \mathbb{Z}/n$ of definition 59.2.9 has cohomology $\mathbb{Z}/d$ in degrees -1 and 0 and 0 elsewhere.

Exercise 59.2.1

1. Let V be the complex of abelian groups of example 59.2.8, with $V^k = \mathbb{Z}/2$ for every k and every differential zero. Let A be the acyclic complex $\mathbb{Z} \xrightarrow{2} \mathbb{Z} \to \mathbb{Z}/2$ in degrees -1, 0, 1. Compute the cohomology of $\mathrm{Tot}(V \otimes_{\mathbb{Z}} A)$ and conclude that V is not K-flat. Deduce from theorem 59.2.7(2) that V is not K-projective either.

2. Show that a direct sum of K-projective complexes is K-projective, and that a direct sum of K-flat complexes is K-flat. (Compute $\mathrm{Hom}^\bullet\big(\bigoplus_\alpha P_\alpha, A\big)$ and $\mathrm{Tot}\big((\bigoplus_\alpha X_\alpha) \otimes_R A\big)$ and use lemma 56.1.11.)

3. Let $0 \to X' \to X \to X'' \to 0$ be a short exact sequence of complexes of R-modules that is split in each degree. Show that if two of X', X, X'' are K-flat, so is the third. Show that $\mathrm{Tot}(X[1] \otimes_R A) = \mathrm{Tot}(X \otimes_R A)[1]$ as complexes, and deduce that the mapping cone of a chain map between K-flat complexes is K-flat.

4. Let k be a field, $\Lambda = k[x]/(x^2)$, and let I be the complex of Λ-modules of exercise 57.4.1 (1), with $I^m = \Lambda$ for every $m \in \mathbb{Z}$ and every differential multiplication by x. Using a bounded-above free resolution of $k = \Lambda/x\Lambda$, show that I is not K-flat, and deduce from theorem 59.2.7(2) that it is not K-projective. Show that the cycle module $x\Lambda \cong k$ of I is not a flat Λ-module, so that Λ does not satisfy the hypothesis of theorem 59.2.12.

5. Show that $R \otimes^L_R Y \cong Y$ in $D(R)$ for every complex Y, and that $\mathrm{Hom}_{D(R)}(R, W) \cong H^0(W)$ for every complex W. Applying theorem 59.2.19 with $X = R[-n]$, deduce that

$$H^n R\mathrm{Hom}_R(Y, Z) \cong \mathrm{Hom}_{D(R)}\big(Y, Z[n]\big)$$

   for all complexes Y and Z of R-modules and every $n \in \mathbb{Z}$.

6. Let F be a complex of torsion-free abelian groups and $n \geq 1$. Show that $F \otimes^L_{\mathbb{Z}} \mathbb{Z}/n \cong 0$ in $D(\mathbb{Z})$ if and only if multiplication by n is bijective on $H^k(F)$ for every $k \in \mathbb{Z}$. Check the criterion on $F = \mathbb{Q}$ in degree 0 and on $F = (\mathbb{Z} \xrightarrow{n} \mathbb{Z})$ in degrees -1 and 0.

7. With V and its resolution P as in example 59.2.8, show that for every $n \in \mathbb{Z}$

$$\mathrm{Hom}_{\mathrm{K}(\mathbb{Z}\text{-Mod})}\big(V, V[n]\big) \cong \prod_{k \in \mathbb{Z}} \mathbb{Z}/2, \qquad \mathrm{Hom}_{D(\mathbb{Z})}\big(V, V[n]\big) \cong \prod_{k \in \mathbb{Z}} \big(\mathbb{Z}/2 \oplus \mathbb{Z}/2\big)$$

   (For the second, compute $\mathrm{Hom}^\bullet(E_k, V)$ for each k.)

8. Let X and Y be K-flat complexes of R-modules. Show that $(x \otimes y) \otimes a \mapsto x \otimes (y \otimes a)$ is an isomorphism of complexes $\mathrm{Tot}\big(\mathrm{Tot}(X \otimes_R Y) \otimes_R A\big) \to \mathrm{Tot}\big(X \otimes_R \mathrm{Tot}(Y \otimes_R A)\big)$ for every complex A, with no sign, and conclude that $\mathrm{Tot}(X \otimes_R Y)$ is K-flat. Deduce that $X \otimes^L_R Y$ is represented by the K-flat complex $\mathrm{Tot}(P_X \otimes_R P_Y)$.

59.3 Truncation in the Derived Category

The canonical truncations of definition 56.1.12 cut a complex at a degree n and keep exactly its cohomology in degrees at most n, or in degrees at least n (proposition 56.1.14). In $D(\mathcal{A})$ they become functors onto the full subcategories of complexes whose cohomology vanishes above, or below, a

fixed degree. Every complex sits in a distinguished triangle between its two truncations, no nonzero morphism runs from the lower subcategory to the upper one, and each truncation is adjoint to the inclusion of its target. The complexes with cohomology only in degree 0 form a full subcategory equivalent to $\mathcal{A}$, so $\mathcal{A}$ is recovered from $D(\mathcal{A})$ together with the two subcategories cut out at degree 0, although distinct abelian categories can have equivalent derived categories (box 57.2.13).

Throughout, $\mathcal{A}$ is an arbitrary abelian category. The localization functor of corollary 56.1.17 is $Q\colon \mathrm{Ch}(\mathcal{A}) \to D(\mathcal{A})$. By theorem 57.2.4 every morphism $X \to Y$ of $D(\mathcal{A})$ is represented by a roof (N, s, f), which is the composite of (N, s, id_N), representing $Q(s)^{-1}$, with (N, id_N, f), representing $Q(f)$. Choosing chain maps in the two homotopy classes writes the morphism as $Q(f)Q(s)^{-1}$ with $f\colon N \to Y$ a chain map and $s\colon N \to X$ a quasi-isomorphism, any representative of the class s being a quasi-isomorphism because homotopic maps induce the same map on cohomology (proposition 56.1.31). An object M of $\mathcal{A}$ is regarded as a complex concentrated in degree 0, as in example 57.2.11, and $M[k]$ is then M in degree $-k$ by (57.1).

By proposition 56.1.14, $\tau^{\leq n}X$ has no cohomology above degree n and $\tau^{\geq n}X$ has none below it. The full subcategories of $D(\mathcal{A})$ cut out by these two vanishing conditions are the targets of the truncation functors.

Definition 59.3.1: The Subcategories $D^{\leq n}$ and $D^{\geq n}$

Let $\mathcal{A}$ be an abelian category and $n \in \mathbb{Z}$. Write $D^{\leq n}(\mathcal{A})$ for the full subcategory of $D(\mathcal{A})$ on the complexes X with $H^i(X) = 0$ for all $i > n$, and $D^{\geq n}(\mathcal{A})$ for the full subcategory on the complexes X with $H^i(X) = 0$ for all $i < n$. The full subcategory

$$D^{\leq 0}(\mathcal{A}) \cap D^{\geq 0}(\mathcal{A})$$

of complexes whose cohomology is concentrated in degree 0 is the *heart* of the pair $\big(D^{\leq 0}(\mathcal{A}), D^{\geq 0}(\mathcal{A})\big)$.

When $\mathcal{A}$ is fixed it is dropped from the notation. Membership depends only on the isomorphism class in $D(\mathcal{A})$, since H^i is a functor on $D(\mathcal{A})$ (proposition 57.2.8). The full subcategory $D^{+}(\mathcal{A})$ of box 57.2.5 consists of the complexes with cohomology bounded below, that is, with $H^i(X) = 0$ for all i below some n, so it is the union of the $D^{\geq n}$ over $n \in \mathbb{Z}$. Likewise $D^{-}(\mathcal{A})$, on the complexes with cohomology bounded above, is the union of the $D^{\leq n}$.

Example 59.3.2: The Complexes $\mathbb{Z} \xrightarrow{2} \mathbb{Z}$ and $\mathbb{Z}/4 \xrightarrow{2} \mathbb{Z}/4$

Let X be $\mathbb{Z} \xrightarrow{2} \mathbb{Z}$ in degrees -1 and 0, as in example 56.1.13. Then $H^{-1}(X) = \ker(2) = 0$ and $H^0(X) = \mathbb{Z}/2$, so X lies in the heart $D^{\leq 0} \cap D^{\geq 0}$ although $X^{-1} \neq 0$. Example 56.1.13 computes $\tau^{\geq 0}X$ as $\mathbb{Z}/2$ in degree 0, and $p_0\colon X \to \tau^{\geq 0}X$ is a quasi-isomorphism by proposition 56.1.14, because $H^{-1}(X) = 0$. So $X \cong \mathbb{Z}/2$ in $D(\mathbf{Ab})$.

Let Y be $\mathbb{Z}/4 \xrightarrow{2} \mathbb{Z}/4$ in degrees -1 and 0. Multiplication by 2 on $\mathbb{Z}/4$ has kernel $\{0, 2\}$ and image $\{0, 2\}$, so $H^{-1}(Y) \cong \mathbb{Z}/2$ and $H^0(Y) = (\mathbb{Z}/4)/\{0, 2\} \cong \mathbb{Z}/2$. Thus $Y \in D^{\leq 0} \cap D^{\geq -1}$ and $Y \notin D^{\geq 0}$.

The exact 2-periodic complex $\cdots \to \mathbb{Z}/4 \xrightarrow{2} \mathbb{Z}/4 \xrightarrow{2} \mathbb{Z}/4 \to \cdots$ of box 57.2.5 is nonzero in every degree, and it lies in $D^{\leq n} \cap D^{\geq m}$ for every m and n, its cohomology being zero.

The functors $\tau^{\leq n}$ and $\tau^{\geq n}$ of definition 56.1.12 are defined on $\mathrm{Ch}(\mathcal{A})$. To act on $D(\mathcal{A})$ they must carry quasi-isomorphisms to quasi-isomorphisms, and they do, because each one preserves the cohomology in its range of degrees and has zero cohomology outside it.

Lemma 59.3.3: Truncation on the Derived Category

Let $n \in \mathbb{Z}$.

1. The functors $\tau^{\leq n}, \tau^{\geq n} \colon \mathrm{Ch}(\mathcal{A}) \to \mathrm{Ch}(\mathcal{A})$ carry quasi-isomorphisms to quasi-isomorphisms. Consequently there are unique functors $\tau^{\leq n}, \tau^{\geq n} \colon D(\mathcal{A}) \to D(\mathcal{A})$, written with the same symbols, such that $\tau^{\leq n} \circ Q = Q \circ \tau^{\leq n}$ and $\tau^{\geq n} \circ Q = Q \circ \tau^{\geq n}$.
2. The morphisms $Q(i_n) \colon \tau^{\leq n} X \to X$ and $Q(p_n) \colon X \to \tau^{\geq n} X$ are natural in $X \in D(\mathcal{A})$.
3. For every X, $\tau^{\leq n} X \in D^{\leq n}$ and $\tau^{\geq n} X \in D^{\geq n}$. Moreover i_n is a quasi-isomorphism, equivalently $Q(i_n)$ is an isomorphism, if and only if $X \in D^{\leq n}$, and p_n is a quasi-isomorphism, equivalently $Q(p_n)$ is an isomorphism, if and only if $X \in D^{\geq n}$.

***Proof*:**

1. Let $f \colon X \to Y$ be a quasi-isomorphism, and write i_n^X for the map i_n of the complex X. The chain map $\tau^{\leq n} f$ is f below degree n and the restriction of f^n to $Z^n(X)$ in degree n, so $i_n^Y \circ \tau^{\leq n} f = f \circ i_n^X$. For $i \leq n$, the maps $H^i(i_n^X)$ and $H^i(i_n^Y)$ are isomorphisms by proposition 56.1.14, and so is $H^i(f)$, hence so is
$$H^i(\tau^{\leq n} f) = H^i(i_n^Y)^{-1} \circ H^i(f) \circ H^i(i_n^X)$$
For $i > n$, proposition 56.1.14 gives $H^i(\tau^{\leq n} X) = 0 = H^i(\tau^{\leq n} Y)$, and the zero map between zero objects is an isomorphism. The chain map $\tau^{\geq n} f$ is the map $X^n/B^n(X) \to Y^n/B^n(Y)$ induced by f^n in degree n and f above, so $p_n^Y \circ f = \tau^{\geq n} f \circ p_n^X$, and the same argument with the range $i \geq n$ treats $\tau^{\geq n}$. So $Q \circ \tau^{\leq n}$ carries quasi-isomorphisms to isomorphisms, and the universal property of corollary 56.1.17 gives a unique functor $\tau^{\leq n}$ on $D(\mathcal{A})$ with $\tau^{\leq n} \circ Q = Q \circ \tau^{\leq n}$. The same holds for $\tau^{\geq n}$.
2. Write a morphism $\varphi \colon X \to Y$ of $D(\mathcal{A})$ as $Q(f)Q(s)^{-1}$ with $s \colon N \to X$ a quasi-isomorphism and $f \colon N \to Y$ a chain map. Applying Q to the naturality squares of i_n in $\mathrm{Ch}(\mathcal{A})$ for f and for s, and using (1), gives
$$Q(i_n^Y) \circ \tau^{\leq n} Q(f) = Q(f) \circ Q(i_n^N), \qquad Q(i_n^X) \circ \tau^{\leq n} Q(s) = Q(s) \circ Q(i_n^N)$$
In the second equation $Q(s)$ and $\tau^{\leq n} Q(s)$ are isomorphisms. Composing with $Q(s)^{-1}$ on the left and with $(\tau^{\leq n} Q(s))^{-1} = \tau^{\leq n}(Q(s)^{-1})$ on the right gives $Q(i_n^N) \circ \tau^{\leq n}(Q(s)^{-1}) = Q(s)^{-1} \circ Q(i_n^X)$, the naturality square for $Q(s)^{-1}$. Pasting it with the square for $Q(f)$ gives $Q(i_n^Y) \circ \tau^{\leq n} \varphi = \varphi \circ Q(i_n^X)$. The argument for p_n is the same.
3. The first sentence is proposition 56.1.14. A chain map f is a quasi-isomorphism exactly when $Q(f)$ is an isomorphism: Q inverts quasi-isomorphisms, and conversely if $Q(f)$ is an isomorphism then so is $H^i(Q(f)) = H^i(f)$ for every i, since H^i is a functor on $D(\mathcal{A})$ with $H^i \circ Q = H^i$ (proposition 57.2.8). By proposition 56.1.14, $H^i(i_n)$ is an isomorphism for every $i \leq n$, and for $i > n$ its source $H^i(\tau^{\leq n} X)$ is zero, so $H^i(i_n)$ is an isomorphism exactly when $H^i(X) = 0$. Hence i_n is a quasi-isomorphism if and only if $X \in D^{\leq n}$. The statement for p_n is proved the same way with $i < n$ in place of $i > n$, completing the proof.

By lemma 59.3.3(3), an object X of $D^{\leq n}$ is isomorphic in $D(\mathcal{A})$ to $\tau^{\leq n}X$, a complex that vanishes above degree n, and an object X of $D^{\geq n}$ is isomorphic to $\tau^{\geq n}X$, which vanishes below degree n. Conversely, a complex that vanishes above degree n has no cohomology there. So $D^{\leq n}$ consists of the objects isomorphic in $D(\mathcal{A})$ to a complex that vanishes above degree n, and likewise $D^{\geq n}$ consists of those isomorphic to a complex that vanishes below degree n.

The triangle relating a complex to its two truncations comes from theorem 57.2.10. The subcomplex $\tau^{\leq n}X$ of X has a quotient complex, and that quotient is quasi-isomorphic to $\tau^{\geq n+1}X$. The vanishing of morphisms from $D^{\leq n}$ to $D^{\geq n+1}$ is proved on a roof, after truncating its apex and its target so that the two have no degree in common.

Proposition 59.3.4: Orthogonality and the Truncation Triangle

Let $\mathcal{A}$ be an abelian category and $n \in \mathbb{Z}$.

1. $D^{\leq n} \subseteq D^{\leq n+1}$ and $D^{\geq n+1} \subseteq D^{\geq n}$. For every complex X, $X \in D^{\leq 0}$ if and only if $X[-n] \in D^{\leq n}$, and $X \in D^{\geq 0}$ if and only if $X[-n] \in D^{\geq n}$.
2. $\operatorname{Hom}_{D(\mathcal{A})}(X, Y) = 0$ for all $X \in D^{\leq n}$ and $Y \in D^{\geq n+1}$.
3. For every complex X there is a morphism $w\colon \tau^{\geq n+1}X \to (\tau^{\leq n}X)[1]$ of $D(\mathcal{A})$ for which

$$\tau^{\leq n}X \xrightarrow{Q(i_n)} X \xrightarrow{Q(p_{n+1})} \tau^{\geq n+1}X \xrightarrow{w} (\tau^{\leq n}X)[1]$$

   is a distinguished triangle of $D(\mathcal{A})$.

***Proof*:**

1. A complex with $H^i(X) = 0$ for all $i > n$ has $H^i(X) = 0$ for all $i > n+1$, and one with $H^i(X) = 0$ for all $i < n+1$ has $H^i(X) = 0$ for all $i < n$. For the second sentence, $H^i(X[-n]) = H^{i-n}(X)$ by (57.1), and $i - n > 0$ exactly when $i > n$, while $i - n < 0$ exactly when $i < n$.
2. Let $\varphi\colon X \to Y$ be a morphism of $D(\mathcal{A})$, and write $\varphi = Q(f)Q(s)^{-1}$ with $s\colon N \to X$ a quasi-isomorphism and $f\colon N \to Y$ a chain map. Since s is a quasi-isomorphism, $H^i(N) \cong H^i(X) = 0$ for $i > n$, so $N \in D^{\leq n}$, and $i := i_n^N\colon \tau^{\leq n}N \to N$ is a quasi-isomorphism by lemma 59.3.3(3). Likewise $p := p_{n+1}^Y\colon Y \to \tau^{\geq n+1}Y$ is a quasi-isomorphism, Y lying in $D^{\geq n+1}$. The chain map $p \circ f \circ i\colon \tau^{\leq n}N \to \tau^{\geq n+1}Y$ is zero in every degree k: for $k > n$ its source $(\tau^{\leq n}N)^k$ is zero, and for $k \leq n$ its target $(\tau^{\geq n+1}Y)^k$ is zero. Hence

$$Q(p) \circ \varphi \circ Q(s) \circ Q(i) = Q(p) \circ Q(f) \circ Q(i) = Q(pfi) = 0$$

   and since $Q(p)$, $Q(s)$ and $Q(i)$ are isomorphisms, $\varphi = 0$.
3. The chain map $i_n\colon \tau^{\leq n}X \to X$ is a monomorphism in every degree: it is the identity below degree n, the inclusion $Z^n \to X^n$ in degree n, and the zero map out of 0 above. Let C be its cokernel, computed degreewise, so that

$$0 \to \tau^{\leq n}X \xrightarrow{i_n} X \xrightarrow{\pi} C \to 0$$

   is a short exact sequence in $\mathrm{Ch}(\mathcal{A})$. Explicitly $C^k = 0$ for $k < n$, $C^n = X^n/Z^n$ and $C^k = X^k$ for $k > n$, with $d_C^n(x + Z^n) = d^n x$, well defined because $Z^n = \ker d^n$, and

$d_C^k = d^k$ for $k > n$. By theorem 57.2.10 there is a morphism $w' \colon C \to (\tau^{\leq n} X)[1]$ of $D(\mathcal{A})$ for which $\big(Q(i_n), Q(\pi), w'\big)$ is a distinguished triangle.

Step 1: the comparison map. Define $q \colon C \to \tau^{\geq n+1} X$ by $q^k = 0$ for $k \leq n$, $q^{n+1} \colon X^{n+1} \to X^{n+1}/B^{n+1}$ the quotient map, and $q^k = \mathrm{id}$ for $k \geq n+2$. Below degree n both complexes are zero, and above degree $n+1$ every component is an identity. In the square leaving degree n, $q^{n+1}(d_C^n(x + Z^n)) = d^n x + B^{n+1} = 0$ because $d^n x \in B^{n+1}$, matching $d^n_{\tau^{\geq n+1}X} \circ q^n = 0$. The square leaving degree $n+1$ commutes because the differential of $\tau^{\geq n+1} X$ in that degree is induced by d^{n+1}. Comparing degree by degree with definition 56.1.12, $q \circ \pi = p_{n+1}$.

Step 2: q is a quasi-isomorphism. For $i < n$, $C^i = 0$. In degree n the map d_C^n is injective, since $d^n x = 0$ forces $x \in Z^n$, and nothing arrives from $C^{n-1} = 0$, so $H^n(C) = 0$. Thus $H^i(C) = 0$ for $i \leq n$, and $H^i(\tau^{\geq n+1} X) = 0$ for $i \leq n$ by proposition 56.1.14, so $H^i(q)$ is an isomorphism for $i \leq n$. For $i \geq n+1$ the map $H^i(\pi)$ is the identity: π is the identity in degrees above n, the cycles of C in degree $n+1$ are Z^{n+1}, and the boundaries there are $d_C^n(C^n) = d^n(X^n) = B^{n+1}$. Since $H^i(q) \circ H^i(\pi) = H^i(p_{n+1})$, and $H^i(p_{n+1})$ is an isomorphism for $i \geq n+1$ by proposition 56.1.14, $H^i(q)$ is an isomorphism for $i \geq n+1$ as well.

Step 3: the triangle. Set $w := w' \circ Q(q)^{-1}$. The triple $\big(\mathrm{id}, \mathrm{id}, Q(q)\big)$ is a morphism of triangles from $\big(Q(i_n), Q(\pi), w'\big)$ to $\big(Q(i_n), Q(p_{n+1}), w\big)$: the middle square is $Q(q) \circ Q(\pi) = Q(p_{n+1})$ by Step 1, and the third is $w \circ Q(q) = w'$ by the definition of w. All three of its components are isomorphisms, so it is an isomorphism of triangles, and distinguished triangles are closed under isomorphism by (TR1) of definition 57.1.3, $D(\mathcal{A})$ being triangulated by theorem 57.2.7. This completes the proof.

Properties (1), (2) and (3), together with $\tau^{\leq n} X \in D^{\leq n}$ and $\tau^{\geq n+1} X \in D^{\geq n+1}$ from lemma 59.3.3(3), are the three axioms of a t-structure in the form of Gelfand-Manin [53, Def. IV.4.2], and section 59.4 develops them on an arbitrary triangulated category, with the pair $(D^{\leq 0}, D^{\geq 0})$ as the standard example. The proposition is Gelfand-Manin [53, Prop. IV.4.3], whose proof of (2) replaces the apex K of a roof by $\tau^{\leq 0} K$ and its target Y by the quasi-isomorphic quotient complex $Y/\tau^{\leq 0} Y$.

Orthogonality already constrains morphisms between objects of $\mathcal{A}$. For $M, N \in \mathcal{A}$ and $k < 0$, the complex $N[k]$ is N in degree $-k \geq 1$, so $N[k] \in D^{\geq 1}$, while $M \in D^{\leq 0}$, and (2) gives $\mathrm{Hom}_{D(\mathcal{A})}(M, N[k]) = 0$. When $\mathcal{A}$ has enough injectives this is the vanishing of negative degrees in theorem 57.4.10(2), and here it holds with no hypothesis on $\mathcal{A}$.

Example 59.3.5: The Truncation Triangle of $\mathbb{Z}/4 \xrightarrow{2} \mathbb{Z}/4$

Let Y be $\mathbb{Z}/4 \xrightarrow{2} \mathbb{Z}/4$ in degrees -1 and 0, as in example 59.3.2, and take $n = -1$. The cycles in degree -1 are $\{0, 2\}$, so $\tau^{\leq -1} Y$ is $\{0, 2\} \cong \mathbb{Z}/2$ in degree -1, which is the complex $\mathbb{Z}/2[1]$. The quotient complex C of the proof of proposition 59.3.4(3) is $(\mathbb{Z}/4)/\{0, 2\} \cong \mathbb{Z}/2$ in degree -1 followed by $\mathbb{Z}/4$ in degree 0, joined by the map $1 \mapsto 2$. The truncation $\tau^{\geq 0} Y$ is $(\mathbb{Z}/4)/\{0, 2\} \cong \mathbb{Z}/2$ in degree 0, and the comparison map $q \colon C \to \tau^{\geq 0} Y$ is the reduction $\mathbb{Z}/4 \to \mathbb{Z}/2$ in degree 0. It is surjective in each degree, and its kernel is the complex $\mathbb{Z}/2 \to \{0, 2\}$, $1 \mapsto 2$, whose differential is an isomorphism, so the kernel is exact and the long exact cohomology sequence of theorem 56.1.20

shows directly that q is a quasi-isomorphism. The triangle reads

$$\mathbb{Z}/2[1] \xrightarrow{Q(i_{-1})} Y \xrightarrow{Q(p_0)} \mathbb{Z}/2 \xrightarrow{w} \mathbb{Z}/2[2]$$

By proposition 56.1.14, $H^{-1}(i_{-1})$ is an isomorphism $H^{-1}(\mathbb{Z}/2[1]) = \mathbb{Z}/2 \to H^{-1}(Y)$ and $H^0(p_0)$ is an isomorphism $H^0(Y) \to H^0(\mathbb{Z}/2) = \mathbb{Z}/2$, while $H^0(\mathbb{Z}/2[1]) = 0$ and $H^{-1}(\mathbb{Z}/2) = 0$.

Combining proposition 59.3.4(2) with the triangle of (3) shows that every morphism from an object of $D^{\leq n}$ into X factors uniquely through $Q(i_n)$, and every morphism from X into an object of $D^{\geq n}$ factors uniquely through $Q(p_n)$.

Corollary 59.3.6: Truncation Is Adjoint to Inclusion

Let $n \in \mathbb{Z}$ and $X \in D(\mathcal{A})$.

1. For every $A \in D^{\leq n}$, composition with $Q(i_n)$ is a bijection
$$\mathrm{Hom}_{D(\mathcal{A})}(A, \tau^{\leq n}X) \xrightarrow{\sim} \mathrm{Hom}_{D(\mathcal{A})}(A, X)$$
natural in A and X. That is, $\tau^{\leq n}\colon D(\mathcal{A}) \to D^{\leq n}$ is right adjoint to the inclusion $D^{\leq n} \to D(\mathcal{A})$.

2. For every $B \in D^{\geq n}$, precomposition with $Q(p_n)$ is a bijection
$$\mathrm{Hom}_{D(\mathcal{A})}(\tau^{\geq n}X, B) \xrightarrow{\sim} \mathrm{Hom}_{D(\mathcal{A})}(X, B)$$
natural in X and B. That is, $\tau^{\geq n}\colon D(\mathcal{A}) \to D^{\geq n}$ is left adjoint to the inclusion $D^{\geq n} \to D(\mathcal{A})$.

***Proof*:**

1. Write $T := \tau^{\leq n}X$ and $S := \tau^{\geq n+1}X$. Since $D(\mathcal{A})$ is triangulated (theorem 57.2.7), $\mathrm{Hom}(A, -)$ is cohomological by proposition 57.1.8. Applied to the triangle of proposition 59.3.4(3) and to its rotation $\big(-w[-1], Q(i_n), Q(p_{n+1})\big)$ on $(S[-1], T, X)$, which is distinguished by (TR2), this gives exactness of
$$\mathrm{Hom}(A, S[-1]) \to \mathrm{Hom}(A, T) \xrightarrow{Q(i_n)\circ -} \mathrm{Hom}(A, X) \to \mathrm{Hom}(A, S)$$
at the two middle terms. Here $S \in D^{\geq n+1}$ by lemma 59.3.3(3), and $S[-1] \in D^{\geq n+2} \subseteq D^{\geq n+1}$ because $H^i(S[-1]) = H^{i-1}(S)$. Since $A \in D^{\leq n}$, both outer groups vanish by proposition 59.3.4(2), so composition with $Q(i_n)$ is injective and surjective. Naturality in A holds because composing on the left commutes with composing on the right. Naturality in X is the equation $Q(i_n^{X'}) \circ \tau^{\leq n}\varphi = \varphi \circ Q(i_n^X)$ of lemma 59.3.3(2), for every $\varphi\colon X \to X'$. Finally $\tau^{\leq n}X$ lies in $D^{\leq n}$ by lemma 59.3.3(3).

2. Write $T := \tau^{\leq n-1}X$ and $S := \tau^{\geq n}X$, and use the triangle of proposition 59.3.4(3) for $n-1$, which has vertices T, X, S. The functor $\mathrm{Hom}(-, B)$ is cohomological on $D(\mathcal{A})^{\mathrm{op}}$ by proposition 57.1.8. Applied to that triangle and to its rotation $\big(Q(p_n), w, -Q(i_{n-1})[1]\big)$

on $(X, S, T[1])$, it gives exactness of

$$\mathrm{Hom}(T[1], B) \to \mathrm{Hom}(S, B) \xrightarrow{-\circ Q(p_n)} \mathrm{Hom}(X, B) \to \mathrm{Hom}(T, B)$$

at the two middle terms. Here $T \in D^{\leq n-1}$, and $T[1] \in D^{\leq n-2} \subseteq D^{\leq n-1}$ because $H^i(T[1]) = H^{i+1}(T)$. Since $B \in D^{\geq n}$, both outer groups vanish by proposition 59.3.4(2) applied with $n-1$, so precomposition with $Q(p_n)$ is a bijection. Naturality is checked as in (1), and $\tau^{\geq n}X \in D^{\geq n}$ by lemma 59.3.3(3), completing the proof.

Parts (1) and (2) characterize the pairs $\left(\tau^{\leq n}X, Q(i_n)\right)$ and $\left(\tau^{\geq n}X, Q(p_n)\right)$ by properties of $D(\mathcal{A})$ and the subcategories $D^{\leq n}$ and $D^{\geq n}$, with no reference to the formulas of definition 56.1.12. For a distinguished triangle $A' \xrightarrow{a} X \xrightarrow{b} B' \xrightarrow{c} A'[1]$ with $A' \in D^{\leq n}$ and $B' \in D^{\geq n+1}$, part (1) gives a unique $f\colon A' \to \tau^{\leq n}X$ with $Q(i_n) \circ f = a$. There is also a unique $h\colon B' \to \tau^{\geq n+1}X$ with $h \circ b = Q(p_{n+1})$, both f and h are isomorphisms, and (f, id_X, h) is an isomorphism of triangles from (a, b, c) to the triangle of proposition 59.3.4(3) (exercise 59.3.1 (2)). Truncation functors exist in this form for an arbitrary t-structure, where no complex-level formula is available.

The objects of $\mathcal{A}$ are, up to isomorphism, the complexes with cohomology concentrated in degree 0, and the morphisms between two of them in $D(\mathcal{A})$ are exactly the morphisms of $\mathcal{A}$. A morphism of $D(\mathcal{A})$ between two objects of $\mathcal{A}$ is a roof whose apex is an arbitrary complex. Truncating the apex in degree 0 reduces it to a chain map out of a complex that stops in degree 0, and such a chain map into an object of $\mathcal{A}$ is determined by its effect on H^0.

Theorem 59.3.7: The Heart of the Standard Pair Is $\mathcal{A}$

Let $\mathcal{A}$ be an abelian category, and let $j\colon \mathcal{A} \to D(\mathcal{A})$ send an object M to the complex with M in degree 0 and zero elsewhere, and a morphism f to $Q(f)$.

1. j is fully faithful, and its essential image is the heart $D^{\leq 0} \cap D^{\geq 0}$.
2. $H^0 \circ j = \mathrm{id}_{\mathcal{A}}$, and there is a natural isomorphism $\vartheta\colon \mathrm{id} \to j \circ H^0$ of functors on $D^{\leq 0} \cap D^{\geq 0}$.

In particular $H^0\colon D^{\leq 0} \cap D^{\geq 0} \to \mathcal{A}$ and j are mutually quasi-inverse equivalences, and the heart is an abelian category.

***Proof*:**

Step 1: j lands in the heart, and $H^0 \circ j = \mathrm{id}_{\mathcal{A}}$. The complex $j(M)$ has $H^i(j(M)) = 0$ for $i \neq 0$ and $H^0(j(M)) = M$. For a morphism $f\colon M \to N$, $H^0(Q(f)) = H^0(f) = f$, because $H^0 \circ Q = H^0$ (proposition 57.2.8). In particular j is faithful.

Step 2: chain maps from a truncation into $j(N)$. Let L be a complex and $N \in \mathcal{A}$, and let $u\colon \tau^{\leq 0}L \to j(N)$ be a chain map. Its only possibly nonzero component is $u^0\colon Z^0(L) \to N$. The square leaving degree -1 reads $u^0 \circ d_L^{-1} = 0$, so u^0 vanishes on $B^0(L)$ and factors as $u^0 = \bar{u} \circ \pi_L$, where $\pi_L\colon Z^0(L) \to Z^0(L)/B^0(L)$ is the quotient map. In degree 0 the complex $\tau^{\leq 0}L$ has cycles $Z^0(L)$, since nothing leaves that degree, and boundaries $d_L^{-1}(L^{-1}) = B^0(L)$, so $H^0(\tau^{\leq 0}L) = Z^0(L)/B^0(L)$ and $H^0(u) = \bar{u}$. Thus $u^0 = H^0(u) \circ \pi_L$, and two chain maps $\tau^{\leq 0}L \to j(N)$ inducing the same map on H^0 are equal.

Step 3: j is full. Let $\varphi\colon j(M) \to j(N)$ be a morphism of $D(\mathcal{A})$, and write $\varphi = Q(g)Q(s)^{-1}$ with $s\colon L \to j(M)$ a quasi-isomorphism and $g\colon L \to j(N)$ a chain map. Then $H^k(L) \cong H^k(j(M)) = 0$ for $k > 0$, so $i := i_0^L\colon \tau^{\leq 0}L \to L$ is a quasi-isomorphism by lemma 59.3.3(3). The map $H^0(s)\colon H^0(L) \to M$ is an isomorphism, and we set

$$f := H^0(g) \circ H^0(s)^{-1}\colon M \to N$$

Regard f as a chain map $j(M) \to j(N)$. The chain maps $f \circ s \circ i$ and $g \circ i$ from $\tau^{\leq 0}L$ to $j(N)$ induce $f \circ H^0(s) \circ H^0(i)$ and $H^0(g) \circ H^0(i)$ on H^0, and these agree because $f \circ H^0(s) = H^0(g)$. By Step 2, $fsi = gi$ as chain maps. Applying Q and cancelling the isomorphisms $Q(i)$ and $Q(s)$ gives $Q(f) = Q(g)Q(s)^{-1} = \varphi$, so $\varphi = j(f)$. Together with Step 1, j is fully faithful.

Step 4: every object of the heart is isomorphic to one in the image. Let X lie in the heart and put $Y := \tau^{\leq 0}X$. The map $i := i_0^X\colon Y \to X$ is a quasi-isomorphism by lemma 59.3.3(3), since $X \in D^{\leq 0}$. For $k \leq 0$, $H^k(Y) \cong H^k(X)$ by proposition 56.1.14, and this vanishes for $k < 0$, so $Y \in D^{\geq 0}$ and $p := p_0^Y : Y \to \tau^{\geq 0}Y$ is a quasi-isomorphism as well. The complex $\tau^{\geq 0}Y$ is $Y^0/B^0(Y)$ in degree 0 and zero elsewhere, and $Y^0 = Z^0(X)$ and $B^0(Y) = d^{-1}(X^{-1}) = B^0(X)$, so $\tau^{\geq 0}\tau^{\leq 0}X = j\big(H^0(X)\big)$. Set

$$\vartheta_X := Q(p) \circ Q(i)^{-1}\colon X \to j\big(H^0(X)\big)$$

an isomorphism of $D(\mathcal{A})$. Both $H^0(i)$ and $H^0(p)$ are the identity of $Z^0(X)/B^0(X)$: the first is induced by the inclusion $Z^0(X) \to X^0$ and the second by the quotient $Z^0(X) \to Z^0(X)/B^0(X)$, each restricted to the cycles $Z^0(X)$ and taken modulo $B^0(X)$. Hence $H^0(\vartheta_X) = \mathrm{id}_{H^0(X)}$.

Step 5: naturality of ϑ. Let $\varphi\colon X \to X'$ be a morphism of the heart. The morphism $\psi := \vartheta_{X'} \circ \varphi \circ \vartheta_X^{-1}$ runs from $j(H^0(X))$ to $j(H^0(X'))$, so $\psi = j(a)$ for some morphism a of $\mathcal{A}$ by Step 3. By Step 1 and Step 4,

$$a = H^0(j(a)) = H^0(\vartheta_{X'}) \circ H^0(\varphi) \circ H^0(\vartheta_X)^{-1} = H^0(\varphi)$$

so $\vartheta_{X'} \circ \varphi = j(H^0(\varphi)) \circ \vartheta_X$, which is naturality.

Step 6: conclusion. Steps 1, 3 and 4 give (1), and Steps 1, 4 and 5 give (2), so j and the restriction of H^0 are quasi-inverse equivalences. The heart contains 0 and is closed under finite direct sums in the additive category $D(\mathcal{A})$, since each H^i is additive, so it is an additive category, and j is an additive functor because Q is. The conditions of definition 55.1.6 (kernels and cokernels exist, every monomorphism is a kernel and every epimorphism is a cokernel) are stated by universal properties, and an equivalence of categories carries each of them from $\mathcal{A}$ to the heart. For instance, the kernel of a morphism $\varphi\colon X \to X'$ of the heart is $\vartheta_X^{-1} \circ j(k)$, where k is a kernel of $H^0(\varphi)$ in $\mathcal{A}$. So the heart is abelian, completing the proof.

The theorem places $\mathcal{A}$ inside $D(\mathcal{A})$ with no hypothesis on $\mathcal{A}$. When $\mathcal{A}$ has enough injectives, full faithfulness of j is also the last clause of theorem 57.4.10(2), proved there through $R\mathrm{Hom}$. Short exact sequences of $\mathcal{A}$ become distinguished triangles of $D(\mathcal{A})$ with all three vertices in the heart, by theorem 57.2.10. The kernel of a morphism φ of the heart is computed in $\mathcal{A}$, as the kernel of $H^0(\varphi)$, and transported along j. Inside $D(\mathcal{A})$ it is produced by a cone followed by a truncation.

Example 59.3.8: The Cone of a Morphism of $\mathcal{A}$

Let $f\colon M \to N$ be a morphism of $\mathcal{A}$, regarded as a chain map of complexes concentrated in degree 0. In definition 56.1.23, $MC(f)^i = M^{i+1} \oplus N^i$ with differential $(l,m) \mapsto \big(-d_M(l),\ f(l) + d_N(m)\big)$, so $MC(f)$ is M in degree -1 and N in degree 0, joined by f:

$$MC(f)\colon \qquad \cdots \to 0 \to M \xrightarrow{f} N \to 0 \to \cdots$$

Hence $H^{-1}(MC(f)) = \ker f$ and $H^0(MC(f)) = \operatorname{coker} f$, and $MC(f) \in D^{\leq 0} \cap D^{\geq -1}$. The mapping cone triangle on f is distinguished in $\mathrm{K}(\mathcal{A})$ (theorem 57.1.12), so its image is distinguished in $D(\mathcal{A})$ (theorem 57.2.7), and by proposition 57.1.10 every distinguished triangle on $Q(f)$ has third vertex isomorphic to $MC(f)$.

Truncate at $n = -1$. The cycles of $MC(f)$ in degree -1 form $\ker f$, so $\tau^{\leq -1} MC(f)$ is $\ker f$ in degree -1, the complex $(\ker f)[1]$. The quotient of N by the boundaries $f(M)$ is $\operatorname{coker} f$, so $\tau^{\geq 0} MC(f)$ is $\operatorname{coker} f$ in degree 0. The triangle of proposition 59.3.4(3) is

$$(\ker f)[1] \longrightarrow MC(f) \longrightarrow \operatorname{coker} f \longrightarrow (\ker f)[2]$$

So the kernel and the cokernel of f are recovered from $D(\mathcal{A})$ and the pair $(D^{\leq 0}, D^{\geq 0})$: complete $Q(f)$ to a distinguished triangle, truncate its third vertex, and apply H^0 to $\big(\tau^{\leq -1} MC(f)\big)[-1]$ and to $\tau^{\geq 0} MC(f)$, both of which lie in the heart. When f is a monomorphism, $H^{-1}(MC(f)) = 0$, the cone itself lies in the heart, and it is isomorphic to $\operatorname{coker} f$ by the quasi-isomorphism of lemma 57.2.9 for the short exact sequence $0 \to M \to N \to \operatorname{coker} f \to 0$.

Exercise 59.3.1

1. Let $X \in D(\mathcal{A})$ and $n \in \mathbb{Z}$, and let w be the third morphism of the triangle of proposition 59.3.4(3). Show that $H^i(w) = 0$ for every i, and deduce from proposition 57.2.8 that

   $$0 \to H^i(\tau^{\leq n} X) \to H^i(X) \to H^i(\tau^{\geq n+1} X) \to 0$$

   is exact for every i. Compare with proposition 56.1.14.

2. Let $A' \xrightarrow{a} X \xrightarrow{b} B' \xrightarrow{c} A'[1]$ be a distinguished triangle of $D(\mathcal{A})$ with $A' \in D^{\leq n}$ and $B' \in D^{\geq n+1}$. Show that there are unique morphisms $f\colon A' \to \tau^{\leq n} X$ and $h\colon B' \to \tau^{\geq n+1} X$ with $Q(i_n) \circ f = a$ and $h \circ b = Q(p_{n+1})$, and that both are isomorphisms. (Apply $\operatorname{Hom}(T, -)$ for $T \in D^{\leq n}$ and $\operatorname{Hom}(-, T)$ for $T \in D^{\geq n+1}$, then argue as in the last paragraph of the proof of corollary 57.1.9.) Show further that $w \circ h = f[1] \circ c$, where w is the third morphism of the triangle of proposition 59.3.4(3), so that (f, id_X, h) is an isomorphism of triangles from (a, b, c) to $\big(Q(i_n), Q(p_{n+1}), w\big)$. (Complete (f, id_X) to a morphism of triangles by (TR3) of definition 57.1.3, and compare its third component with h.)

3. Let $X \in \mathrm{Ch}(\mathcal{A})$ and $m \leq n$. Show that the complexes $\tau^{\geq m} \tau^{\leq n} X$ and $\tau^{\leq n} \tau^{\geq m} X$ are canonically isomorphic, and that for $m = n$ both are $H^n(X)$ in degree n, that is $H^n(X)[-n]$.

4. Let $X' \to X \to X'' \to X'[1]$ be a distinguished triangle of $D(\mathcal{A})$. Show that if X' and X'' lie in $D^{\leq 0}$ then so does X, and that the same holds for $D^{\geq 0}$. Conclude that the heart is closed under extensions in $D(\mathcal{A})$.

5. Show that $X \in D^{\leq 0}$ if and only if $\mathrm{Hom}_{D(\mathcal{A})}(X, B) = 0$ for every $B \in D^{\geq 1}$, and that $X \in D^{\geq 1}$ if and only if $\mathrm{Hom}_{D(\mathcal{A})}(A, X) = 0$ for every $A \in D^{\leq 0}$. (Test against $\tau^{\geq 1}X$ and $\tau^{\leq 0}X$, and use corollary 59.3.6.)

6. Let $k \in \mathbb{Z}$. Show that H^k restricts to an equivalence from $D^{\leq k} \cap D^{\geq k}$ to $\mathcal{A}$, with quasi-inverse $M \mapsto j(M)[-k]$.

7. Let X be the complex $\mathbb{Z} \xrightarrow{d^{-1}} \mathbb{Z}^2 \xrightarrow{d^0} \mathbb{Z}$ of abelian groups in degrees -1, 0 and 1, with $d^{-1}(x) = (2x, 0)$ and $d^0(a, b) = 3b$. Compute $H^\bullet(X)$, $\tau^{\leq 0}X$ and $\tau^{\geq 1}X$, and show that $\tau^{\leq 0}X \cong \mathbb{Z}/2$ and $\tau^{\geq 1}X = \mathbb{Z}/3[-1]$ in $D(\mathbf{Ab})$. Then show that the third morphism w of the triangle of proposition 59.3.4(3) for $n = 0$ is zero. (The Hom-sets of $D(\mathbf{Ab})$ are abelian groups and composition is bilinear, by theorem 57.2.7. Compare $3w$ and $2w$.)

59.4 t-Structures and Their Hearts

The full subcategories $D^{\leq 0}$ and $D^{\geq 0}$ of $D(\mathcal{A})$ in section 59.3, cut out by the vanishing of cohomology above and below degree 0, have three properties (proposition 59.3.4). No nonzero morphism runs from an object of $D^{\leq 0}$ to an object of $D^{\geq 1}$, the subcategories nest under shifting, and every complex sits in a distinguished triangle whose outer vertices are its two canonical truncations. Once that triangle is replaced by the existence of some distinguished triangle with first vertex in $D^{\leq 0}$ and third vertex in $D^{\geq 1}$, the three properties involve only objects, morphisms and distinguished triangles, so they make sense in any triangulated category, and this section takes them as axioms. The objects lying in both halves form the *heart*. The main results are that the heart is an abelian category (theorem 59.4.13), and that a functor H^0_t built from two truncations carries every distinguished triangle to an exact sequence in the heart (corollary 59.4.15). For the standard t-structure on $D(\mathcal{A})$ the heart is equivalent to $\mathcal{A}$ and H^0_t corresponds to ordinary cohomology. One triangulated category can carry t-structures with inequivalent hearts, and example 59.4.3 puts one with zero heart on every triangulated category.

Definition 59.4.1: t-Structure

Let $\mathcal{K}$ be a triangulated category. A *t-structure* on $\mathcal{K}$ is a pair $(\mathcal{K}^{\leq 0}, \mathcal{K}^{\geq 0})$ of full subcategories, each closed under isomorphism, such that, writing for $n \in \mathbb{Z}$

$$\mathcal{K}^{\leq n} := \{X \in \mathcal{K} \,|\, X[n] \in \mathcal{K}^{\leq 0}\}, \qquad \mathcal{K}^{\geq n} := \{X \in \mathcal{K} \,|\, X[n] \in \mathcal{K}^{\geq 0}\}$$

the following hold.

(T1) $\mathrm{Hom}_{\mathcal{K}}(X, Y) = 0$ for all $X \in \mathcal{K}^{\leq 0}$ and $Y \in \mathcal{K}^{\geq 1}$.

(T2) $\mathcal{K}^{\leq 0} \subseteq \mathcal{K}^{\leq 1}$ and $\mathcal{K}^{\geq 1} \subseteq \mathcal{K}^{\geq 0}$.

(T3) Every $X \in \mathcal{K}$ sits in a distinguished triangle $A \to X \to B \to A[1]$ with $A \in \mathcal{K}^{\leq 0}$ and $B \in \mathcal{K}^{\geq 1}$.

The *heart* of the t-structure is the full subcategory $\mathcal{K}^\heartsuit := \mathcal{K}^{\leq 0} \cap \mathcal{K}^{\geq 0}$.

Since [1] is an automorphism, $X \in \mathcal{K}^{\leq n}$ if and only if $X[1] \in \mathcal{K}^{\leq n-1}$, both conditions saying that

$X[n] \in \mathcal{K}^{\leq 0}$, and likewise for $\mathcal{K}^{\geq n}$. This moves (T1) and (T2) to every degree: for all integers $m < n$,

$$\mathcal{K}^{\leq m} \subseteq \mathcal{K}^{\leq n}, \qquad \mathcal{K}^{\geq n} \subseteq \mathcal{K}^{\geq m}, \qquad \mathrm{Hom}_{\mathcal{K}}(X, Y) = 0 \ \text{ for } X \in \mathcal{K}^{\leq m} \text{ and } Y \in \mathcal{K}^{\geq n} \tag{59.2}$$

For the first, $X \in \mathcal{K}^{\leq m}$ gives $X[m] \in \mathcal{K}^{\leq 0} \subseteq \mathcal{K}^{\leq 1}$ by (T2), so $X[m+1] \in \mathcal{K}^{\leq 0}$ and $X \in \mathcal{K}^{\leq m+1}$, and induction reaches n. For the second, $X \in \mathcal{K}^{\geq n}$ gives $X[n-1] \in \mathcal{K}^{\geq 1} \subseteq \mathcal{K}^{\geq 0}$, so $X \in \mathcal{K}^{\geq n-1}$, and induction reaches m. For the third, $X \in \mathcal{K}^{\leq n-1}$ by the first, so $X[n-1] \in \mathcal{K}^{\leq 0}$ and $Y[n-1] \in \mathcal{K}^{\geq 1}$, and $\mathrm{Hom}_{\mathcal{K}}(X, Y) \cong \mathrm{Hom}_{\mathcal{K}}(X[n-1], Y[n-1])$ vanishes by (T1). In particular $X[1] \in \mathcal{K}^{\leq -1} \subseteq \mathcal{K}^{\leq 0}$ for $X \in \mathcal{K}^{\leq 0}$, so $\mathcal{K}^{\leq 0}$ is stable under $[1]$, and dually $\mathcal{K}^{\geq 0}$ is stable under $[-1]$.

The axioms say that every object is assembled, in a single distinguished triangle, from a piece in $\mathcal{K}^{\leq 0}$ and a piece in $\mathcal{K}^{\geq 1}$, and that every morphism from an object of the first kind to an object of the second is zero.[1]

Example 59.4.2: The Standard t-Structure on $D(\mathcal{A})$

Let $\mathcal{A}$ be an abelian category, and take the full subcategories $D^{\leq 0}$ and $D^{\geq 0}$ of $D(\mathcal{A})$ defined in definition 59.3.1. Each is closed under isomorphism, because H^i is a functor on $D(\mathcal{A})$ (proposition 57.2.8). By proposition 59.3.4(1), $X[n] \in D^{\leq 0}$ exactly when $X \in D^{\leq n}$, and likewise for $D^{\geq n}$, so the subcategories that definition 59.4.1 attaches to degree n are the $D^{\leq n}$ and $D^{\geq n}$ of definition 59.3.1. Axiom (T2) is the case $n = 0$ of proposition 59.3.4(1), and (T1) is proposition 59.3.4(2) with $n = 0$. For (T3), proposition 59.3.4(3) with $n = 0$ gives the distinguished triangle $\tau^{\leq 0}X \to X \to \tau^{\geq 1}X \to (\tau^{\leq 0}X)[1]$ on the canonical truncations of definition 56.1.12, and $\tau^{\leq 0}X \in D^{\leq 0}$ and $\tau^{\geq 1}X \in D^{\geq 1}$ by lemma 59.3.3(3). So $(D^{\leq 0}, D^{\geq 0})$ is a t-structure on $D(\mathcal{A})$, the *standard* one. Its heart is the heart of definition 59.3.1, the complexes with cohomology concentrated in degree 0, and theorem 59.3.7 shows that H^0 restricts to an equivalence from the heart to $\mathcal{A}$.

Example 59.4.3: A Degenerate t-Structure

Let $\mathcal{K}$ be any triangulated category, let $\mathcal{K}^{\leq 0} = \mathcal{K}$, and let $\mathcal{K}^{\geq 0}$ be the full subcategory of zero objects. Both are closed under isomorphism, and since $[n]$ carries zero objects to zero objects, $\mathcal{K}^{\leq n} = \mathcal{K}$ and $\mathcal{K}^{\geq n}$ is the subcategory of zero objects for every n. (T1) holds because every morphism into a zero object is zero, and (T2) holds with equalities. For (T3), the triangle $(\mathrm{id}_X, 0, 0)$ on $(X, X, 0)$ is distinguished by (TR1) and has $0 \in \mathcal{K}^{\geq 1}$. The heart is the subcategory of zero objects. On $\mathcal{K} = D(\mathcal{A})$ with $\mathcal{A}$ nonzero, this and the standard t-structure of example 59.4.2 are two t-structures on one triangulated category, one with heart equivalent to $\mathcal{A}$ and one with zero heart.

Exactness of Hom sequences converts the vanishing in (59.2) into statements about objects and morphisms. Let (u, v, w) be a distinguished triangle on (A, B, C). By (TR2) the rotations $(v, w, -u[1])$ on $(B, C, A[1])$, $(-w[-1], u, v)$ on $(C[-1], A, B)$ and $(-v[-1], -w[-1], u)$ on $(B[-1], C[-1], A)$ are distinguished, the last being the second rotation backwards. Applying proposition 57.1.8 to (u, v, w) and these three triangles gives, for every $T \in \mathcal{K}$, sequences

$$\begin{gathered}\mathrm{Hom}(T, B[-1]) \to \mathrm{Hom}(T, C[-1]) \to \mathrm{Hom}(T, A) \xrightarrow{u_*} \mathrm{Hom}(T, B) \xrightarrow{v_*} \mathrm{Hom}(T, C) \xrightarrow{w_*} \mathrm{Hom}(T, A[1]) \\ \mathrm{Hom}(A[1], T) \xrightarrow{w^*} \mathrm{Hom}(C, T) \xrightarrow{v^*} \mathrm{Hom}(B, T) \xrightarrow{u^*} \mathrm{Hom}(A, T) \to \mathrm{Hom}(C[-1], T)\end{gathered} \tag{59.3}$$

[1] The notion is due to Beilinson, Bernstein and Deligne [8, Def. 1.3.1], whose categories of perverse sheaves are hearts of t-structures. Gelfand and Manin [53, Def. IV.4.2] call the heart the *core*.

exact at every interior term, where the unlabelled maps are composition with $-v[-1]$, $-w[-1]$ and $-w[-1]$, in that order. A sign changes no kernel and no image, so it is dropped below whenever only exactness is used.

The axioms are stated in degree 0, and moving (T3) to another degree needs the translation to carry distinguished triangles to distinguished triangles. Rotating three times does this, up to a sign on the third edge.

Lemma 59.4.4: Translates of Distinguished Triangles

Let (u, v, w) be a distinguished triangle on (A, B, C) and let $n \in \mathbb{Z}$. There is a morphism $w_n \colon C[n] \to A[n+1]$ such that $(u[n], v[n], w_n)$ is a distinguished triangle on $(A[n], B[n], C[n])$. One may take $w_1 = -w[1]$ and $w_{-1} = -w[-1]$.

***Proof*:**
Three rotations by the first form of (TR2) give the distinguished triangles

$$(v, w, -u[1]), \qquad (w, -u[1], -v[1]), \qquad (-u[1], -v[1], -w[1])$$

on $(B, C, A[1])$, $(C, A[1], B[1])$ and $(A[1], B[1], C[1])$ respectively. From the last of these to $(u[1], v[1], -w[1])$ the triple $(\mathrm{id}_{A[1]}, -\mathrm{id}_{B[1]}, \mathrm{id}_{C[1]})$ is an isomorphism of triangles, because its three squares read

$$(-\mathrm{id})(-u[1]) = u[1]\,\mathrm{id}, \qquad \mathrm{id}\,(-v[1]) = v[1]\,(-\mathrm{id}), \qquad \mathrm{id}\,(-w[1]) = (-w[1])\,\mathrm{id}$$

by bilinearity of composition. So $(u[1], v[1], -w[1])$ is distinguished by (TR1). Three rotations by the second form of (TR2) give $(-w[-1], u, v)$ on $(C[-1], A, B)$, then $(-v[-1], -w[-1], u)$ on $(B[-1], C[-1], A)$, then $(-u[-1], -v[-1], -w[-1])$ on $(A[-1], B[-1], C[-1])$, and the same isomorphism $(\mathrm{id}, -\mathrm{id}, \mathrm{id})$ carries the last to $(u[-1], v[-1], -w[-1])$. For general n, induct on $|n|$: if $(u[n], v[n], w_n)$ is distinguished, the cases $n = \pm 1$, applied to it, give the distinguished triangles $(u[n+1], v[n+1], -w_n[1])$ and $(u[n-1], v[n-1], -w_n[-1])$, completing the proof.

Deciding whether an object lies in $\mathcal{K}^{\leq 0}$ will come down to deciding whether the first edge of a distinguished triangle is an isomorphism.

Lemma 59.4.5: A Triangle with Zero Third Vertex

Let (u, v, w) be a distinguished triangle on (A, B, C). Then u is an isomorphism if and only if $C \cong 0$.

***Proof*:**
Suppose $C \cong 0$. Then $C[-1] \cong 0$, since the automorphism $[-1]$ carries zero objects to zero objects. For every $T \in \mathcal{K}$ the first sequence of (59.3) contains

$$0 = \mathrm{Hom}(T, C[-1]) \to \mathrm{Hom}(T, A) \xrightarrow{u_*} \mathrm{Hom}(T, B) \to \mathrm{Hom}(T, C) = 0$$

exact at its two middle terms, so u_* is bijective. Taking $T = B$ gives $s \colon B \to A$ with $us = \mathrm{id}_B$. Taking $T = A$, both su and id_A are carried by u_* to u, since $u(su) = (us)u = u$, so $su = \mathrm{id}_A$ and u is an isomorphism with inverse s.

Conversely suppose u is an isomorphism. The triangle $(\mathrm{id}_A, 0, 0)$ on $(A, A, 0)$ is distinguished by (TR1), and $u \circ \mathrm{id}_A = u \circ \mathrm{id}_A$, so (TR3) gives $h\colon 0 \to C$ with (id_A, u, h) a morphism of triangles from $(\mathrm{id}_A, 0, 0)$ to (u, v, w). Its first two components are isomorphisms, so corollary 57.1.9 makes h an isomorphism and $C \cong 0$, completing the proof.

(TR3) extends a commutative square to a morphism of triangles but does not make the extension unique, so the isomorphism of cones in proposition 57.1.10 need not be unique and the axioms give no functorial cone (box 57.1.4). An extension of a morphism of middle vertices exists and is unique when two Hom groups vanish, and in a t-structure (59.2) makes them vanish.

Lemma 59.4.6: Unique Extension to a Morphism of Triangles

Let (u, v, w) on (A, B, C) and (u', v', w') on (A', B', C') be distinguished triangles and let $g\colon B \to B'$.

1. If $\mathrm{Hom}(A, C') = 0$, there are $f\colon A \to A'$ and $h\colon C \to C'$ such that (f, g, h) is a morphism of triangles.
2. If $\mathrm{Hom}(A[1], C') = 0$, there is at most one f with $u'f = gu$ and at most one h with $hv = v'g$.

***Proof*:**

1. The first sequence of (59.3) for (u', v', w') and $T = A$ is exact at the middle term of
$$\mathrm{Hom}(A, A') \xrightarrow{u'_*} \mathrm{Hom}(A, B') \xrightarrow{v'_*} \mathrm{Hom}(A, C') = 0$$
so $gu = u'f$ for some $f\colon A \to A'$. (TR3), applied to f, g and the commutative square $gu = u'f$, gives h with (f, g, h) a morphism of triangles.
2. Applying $[1]$ is a bijection $\mathrm{Hom}(A, C'[-1]) \to \mathrm{Hom}(A[1], C')$, so $\mathrm{Hom}(A, C'[-1]) = 0$. In the first sequence of (59.3) for (u', v', w') and $T = A$, the kernel of u'_* on $\mathrm{Hom}(A, A')$ is the image of $\mathrm{Hom}(A, C'[-1]) = 0$. So $u'f = u'f_1$ forces $f = f_1$. In the second sequence for (u, v, w) and $T = C'$, the kernel of v^* on $\mathrm{Hom}(C, C')$ is the image of $\mathrm{Hom}(A[1], C') = 0$. So $hv = h_1 v$ forces $h = h_1$, completing the proof.

Nothing in definition 59.4.1 singles out degree 0, and shifting the indexing gives another t-structure.

Lemma 59.4.7: Shifted t-Structures

Let $(\mathcal{K}^{\leq 0}, \mathcal{K}^{\geq 0})$ be a t-structure on $\mathcal{K}$ and let $m \in \mathbb{Z}$. Then $(\mathcal{K}^{\leq m}, \mathcal{K}^{\geq m})$ is a t-structure on $\mathcal{K}$, its subcategories in degree n are $\mathcal{K}^{\leq m+n}$ and $\mathcal{K}^{\geq m+n}$, and its heart $\mathcal{K}^{\leq m} \cap \mathcal{K}^{\geq m}$ consists of the objects X with $X[m] \in \mathcal{K}^{\heartsuit}$.

***Proof*:**

Both subcategories are closed under isomorphism, as $X \cong Y$ gives $X[m] \cong Y[m]$. An object X lies in the degree-n subcategory $\{X \,|\, X[n] \in \mathcal{K}^{\leq m}\}$ exactly when $X[n+m] \in \mathcal{K}^{\leq 0}$, that is when $X \in \mathcal{K}^{\leq m+n}$, and likewise for $\mathcal{K}^{\geq m+n}$. With this, (T1) and (T2) for the new pair say that

$\mathrm{Hom}(X,Y)=0$ for $X\in\mathcal{K}^{\leq m}$ and $Y\in\mathcal{K}^{\geq m+1}$, and that $\mathcal{K}^{\leq m}\subseteq\mathcal{K}^{\leq m+1}$ and $\mathcal{K}^{\geq m+1}\subseteq\mathcal{K}^{\geq m}$. All three are instances of (59.2). For (T3), let $X\in\mathcal{K}$ and take, by (T3) for the original pair, a distinguished triangle (u,v,w) on $(A,X[m],B)$ with $A\in\mathcal{K}^{\leq 0}$ and $B\in\mathcal{K}^{\geq 1}$. Lemma 59.4.4 with $n=-m$ gives a distinguished triangle $(u[-m],v[-m],w_{-m})$ on $(A[-m],X,B[-m])$. Here $A[-m]\in\mathcal{K}^{\leq m}$ since $A[-m][m]=A$, and $B[-m]\in\mathcal{K}^{\geq m+1}$ since $B[-m][m+1]=B[1]\in\mathcal{K}^{\geq 0}$. The description of the heart is the definition of $\mathcal{K}^{\leq m}$ and $\mathcal{K}^{\geq m}$, completing the proof.

Example 59.4.8: Shifts of the Standard *t*-Structure

For the standard t-structure of example 59.4.2 and $m\in\mathbb{Z}$, the heart of $(D^{\leq m},D^{\geq m})$ consists of the complexes X with $H^i(X)=0$ for $i\neq m$. The functor $X\mapsto H^0(X[m])=H^m(X)$ is an equivalence from it to $\mathcal{A}$, being the composite of the equivalence $[m]$ onto $D^{\leq 0}\cap D^{\geq 0}$ with the equivalence of theorem 59.3.7. So the shifted hearts are equivalent to one another. If $\mathcal{A}$ has a nonzero object M, they are also different subcategories of $D(\mathcal{A})$, since M, placed in degree 0, lies in the heart of $(D^{\leq m},D^{\geq m})$ only for $m=0$, while $M[-m]$ lies in it for every m.

Axiom (T3) asserts only that a triangle exists. Making it functorial in X needs a choice that is unique up to unique isomorphism, and (T1), through lemma 59.4.6, gives exactly that. The resulting functors and adjunctions extend lemma 59.3.3 and corollary 59.3.6 to an arbitrary t-structure.

Proposition 59.4.9: Truncation Functors of a *t*-Structure

Let $(\mathcal{K}^{\leq 0},\mathcal{K}^{\geq 0})$ be a t-structure on $\mathcal{K}$ and let $n\in\mathbb{Z}$.

1. There are additive functors $\tau^{\leq n}\colon\mathcal{K}\to\mathcal{K}^{\leq n}$ and $\tau^{\geq n+1}\colon\mathcal{K}\to\mathcal{K}^{\geq n+1}$ and natural transformations $\alpha^n\colon\tau^{\leq n}\to\mathrm{id}$, $\beta^n\colon\mathrm{id}\to\tau^{\geq n+1}$ and $\partial^n\colon\tau^{\geq n+1}\to\tau^{\leq n}[1]$ such that for every $X\in\mathcal{K}$ the triangle
$$\tau^{\leq n}X\xrightarrow{\alpha^n_X}X\xrightarrow{\beta^n_X}\tau^{\geq n+1}X\xrightarrow{\partial^n_X}(\tau^{\leq n}X)[1]$$
is distinguished.
2. For all $A\in\mathcal{K}^{\leq n}$, $B\in\mathcal{K}^{\geq n+1}$ and $X\in\mathcal{K}$, composition with α^n_X and with β^n_X gives bijections
$$\mathrm{Hom}(A,\tau^{\leq n}X)\xrightarrow{\sim}\mathrm{Hom}(A,X),\qquad\mathrm{Hom}(\tau^{\geq n+1}X,B)\xrightarrow{\sim}\mathrm{Hom}(X,B)$$
natural in all three variables. So $\tau^{\leq n}$ is right adjoint to the inclusion of $\mathcal{K}^{\leq n}$ in $\mathcal{K}$, and $\tau^{\geq n+1}$ is left adjoint to the inclusion of $\mathcal{K}^{\geq n+1}$.
3. If (u,v,w) is a distinguished triangle on (A,X,B) with $A\in\mathcal{K}^{\leq n}$ and $B\in\mathcal{K}^{\geq n+1}$, there is exactly one isomorphism of triangles of the form (f,id_X,h) from it to the triangle of (1). In particular ∂^n_X is the only morphism completing (α^n_X,β^n_X) to a distinguished triangle.

***Proof*:**

By lemma 59.4.7, $(\mathcal{K}^{\leq n},\mathcal{K}^{\geq n})$ is a t-structure whose subcategories in degrees 0 and 1 are $\mathcal{K}^{\leq n}$ and $\mathcal{K}^{\geq n+1}$, so the statement for n is the statement for $n=0$ applied to that t-structure. Take $n=0$, and write α, β, ∂ for α^0, β^0, ∂^0.

Step 1: The bijections for a chosen triangle. For each $X \in \mathcal{K}$ choose by (T3) a distinguished triangle $(\alpha_X, \beta_X, \partial_X)$ on $(\tau^{\leq 0}X, X, \tau^{\geq 1}X)$ with $\tau^{\leq 0}X \in \mathcal{K}^{\leq 0}$ and $\tau^{\geq 1}X \in \mathcal{K}^{\geq 1}$. For the standard t-structure on $D(\mathcal{A})$, where after the reduction $\mathcal{K}^{\leq 0}$ and $\mathcal{K}^{\geq 1}$ are the subcategories $D^{\leq n}$ and $D^{\geq n+1}$, we choose the triangle of proposition 59.3.4(3) for that n, whose outer vertices lie in them by lemma 59.3.3(3). Let $A \in \mathcal{K}^{\leq 0}$. The first sequence of (59.3) with $T = A$ contains

$$\operatorname{Hom}(A, (\tau^{\geq 1}X)[-1]) \to \operatorname{Hom}(A, \tau^{\leq 0}X) \xrightarrow{(\alpha_X)_*} \operatorname{Hom}(A, X) \to \operatorname{Hom}(A, \tau^{\geq 1}X)$$

exact at its middle terms. The last group vanishes by (T1). So does the first, since $(\tau^{\geq 1}X)[-1] \in \mathcal{K}^{\geq 2}$ and $\operatorname{Hom}(\mathcal{K}^{\leq 0}, \mathcal{K}^{\geq 2}) = 0$ by (59.2). So $(\alpha_X)_*$ is bijective. For $B \in \mathcal{K}^{\geq 1}$ the second sequence of (59.3) contains

$$\operatorname{Hom}((\tau^{\leq 0}X)[1], B) \to \operatorname{Hom}(\tau^{\geq 1}X, B) \xrightarrow{\beta_X^*} \operatorname{Hom}(X, B) \to \operatorname{Hom}(\tau^{\leq 0}X, B)$$

exact at its middle terms. The last group vanishes by (T1), and the first because $(\tau^{\leq 0}X)[1] \in \mathcal{K}^{\leq -1}$. So β_X^* is bijective.

Step 2: Functoriality. Let $g\colon X \to Y$ be a morphism of $\mathcal{K}$. The groups $\operatorname{Hom}(\tau^{\leq 0}X, \tau^{\geq 1}Y)$ and $\operatorname{Hom}((\tau^{\leq 0}X)[1], \tau^{\geq 1}Y)$ vanish by (59.2), since their sources lie in $\mathcal{K}^{\leq 0}$ and $\mathcal{K}^{\leq -1}$ and their target lies in $\mathcal{K}^{\geq 1}$. Hence lemma 59.4.6 extends g to a morphism of triangles $(\tau^{\leq 0}g, g, \tau^{\geq 1}g)$ from the chosen triangle on X to the chosen triangle on Y, where $\tau^{\leq 0}g$ is the unique morphism with $\alpha_Y \circ \tau^{\leq 0}g = g \circ \alpha_X$ and $\tau^{\geq 1}g$ the unique morphism with $\tau^{\geq 1}g \circ \beta_X = \beta_Y \circ g$. Uniqueness gives functoriality: $\mathrm{id}_{\tau^{\leq 0}X}$ satisfies the condition characterizing $\tau^{\leq 0}(\mathrm{id}_X)$, and for $g'\colon Y \to W$ the composite $\tau^{\leq 0}g' \circ \tau^{\leq 0}g$ satisfies

$$\alpha_W \circ \tau^{\leq 0}g' \circ \tau^{\leq 0}g = g' \circ \alpha_Y \circ \tau^{\leq 0}g = g'g \circ \alpha_X$$

the condition characterizing $\tau^{\leq 0}(g'g)$. Additivity is the same argument, as $\alpha_Y \circ (\tau^{\leq 0}g + \tau^{\leq 0}g_1) = (g + g_1) \circ \alpha_X$ by bilinearity of composition. The argument for $\tau^{\geq 1}$ is identical with β in place of α. The three squares of the morphism of triangles $(\tau^{\leq 0}g, g, \tau^{\geq 1}g)$ are the naturality of α, β and ∂. This proves (1).

Step 3: Naturality of the bijections. The bijection $(\alpha_X)_*$ is natural in A, being composition on the other side, and natural in X because $\alpha_Y \circ \tau^{\leq 0}g \circ \varphi = g \circ \alpha_X \circ \varphi$ for every $\varphi\colon A \to \tau^{\leq 0}X$. The same argument applies to β_X^*. This proves (2).

Step 4: Uniqueness of the triangle. Let (u, v, w) be distinguished on (A, X, B) with $A \in \mathcal{K}^{\leq 0}$ and $B \in \mathcal{K}^{\geq 1}$. As in Step 2, (59.2) gives the vanishing that lemma 59.4.6 needs for $g = \mathrm{id}_X$ in both directions between (u, v, w) and $(\alpha_X, \beta_X, \partial_X)$. So there are morphisms of triangles (f, id_X, h) from (u, v, w) to $(\alpha_X, \beta_X, \partial_X)$ and (f', id_X, h') back, each the only one with middle component id_X. A composite of morphisms of triangles is one, by functoriality of [1], so $(f'f, \mathrm{id}_X, h'h)$ and the identity are two morphisms from (u, v, w) to itself with middle component id_X, and the same lemma, applied to (u, v, w) and itself, makes them equal. Likewise $(ff', \mathrm{id}_X, hh')$ is the identity. So (f, id_X, h) is an isomorphism of triangles, and it is the only one with middle component id_X. Finally, if $(\alpha_X, \beta_X, \partial')$ is distinguished, the isomorphism (f, id_X, h) from it to $(\alpha_X, \beta_X, \partial_X)$ satisfies $\alpha_X f = \alpha_X$ and $h\beta_X = \beta_X$, so f and h are identities by the injectivity of $(\alpha_X)_*$ and β_X^* in Step 1. The third square then reads $\partial' = \partial_X$, completing the proof.

Proposition 59.4.9 is [8, Prop. 1.3.3] and [53, Lemma IV.4.5]. Part (2) says that every morphism into X from an object of $\mathcal{K}^{\leq n}$ factors uniquely through α^n_X, and every morphism out of X into an object of $\mathcal{K}^{\geq n+1}$ factors uniquely through β^n_X. Part (3) says that the triangle of (T3) is unique up to unique isomorphism fixing X, the uniqueness coming from (T1) through lemma 59.4.6. For the standard t-structure, Step 1 of the proof chooses the triangle of proposition 59.3.4(3), so $\alpha^n_X = Q(i_n)$ and $\beta^n_X = Q(p_{n+1})$. On morphisms, the naturality of $Q(i_n)$ and $Q(p_{n+1})$ in lemma 59.3.3(2) is the condition that characterizes $\tau^{\leq n}g$ and $\tau^{\geq n+1}g$ in Step 2. So the functors of (1) are those of lemma 59.3.3, (2) becomes corollary 59.3.6, and one symbol τ denotes both kinds of truncation.

The truncation functors convert membership in the two halves into a vanishing condition.

Lemma 59.4.10: The Two Halves Determine Each Other

Let $(\mathcal{K}^{\leq 0}, \mathcal{K}^{\geq 0})$ be a t-structure on $\mathcal{K}$ and let $n \in \mathbb{Z}$.

1. For $X \in \mathcal{K}$ the following are equivalent: (a) $X \in \mathcal{K}^{\leq n}$, (b) $\mathrm{Hom}(X, B) = 0$ for every $B \in \mathcal{K}^{\geq n+1}$, (c) $\tau^{\geq n+1}X \cong 0$, (d) α^n_X is an isomorphism.
2. For $Y \in \mathcal{K}$ the following are equivalent: (a) $Y \in \mathcal{K}^{\geq n+1}$, (b) $\mathrm{Hom}(A, Y) = 0$ for every $A \in \mathcal{K}^{\leq n}$, (c) $\tau^{\leq n}Y \cong 0$, (d) β^n_Y is an isomorphism.
3. $\mathcal{K}^{\leq n}$ and $\mathcal{K}^{\geq n}$ contain the zero objects and are closed under finite direct sums and under extensions: if (u, v, w) is distinguished on (A, X, C) and A and C lie in one of the two, then so does X.
4. $\tau^{\geq n}$ carries $\mathcal{K}^{\leq n}$ into $\mathcal{K}^{\leq n} \cap \mathcal{K}^{\geq n}$, and $\tau^{\leq n}$ carries $\mathcal{K}^{\geq n}$ into $\mathcal{K}^{\leq n} \cap \mathcal{K}^{\geq n}$.

***Proof*:**

1. (a) implies (b) by (59.2). If (b) holds, then $\mathrm{Hom}(\tau^{\geq n+1}X, B) = 0$ for every $B \in \mathcal{K}^{\geq n+1}$ by proposition 59.4.9(2), and taking $B = \tau^{\geq n+1}X$ gives $\mathrm{id}_{\tau^{\geq n+1}X} = 0$, so $\tau^{\geq n+1}X$ is a zero object, which is (c). If (c) holds, lemma 59.4.5 applied to the truncation triangle of proposition 59.4.9(1) makes α^n_X an isomorphism, which is (d). If (d) holds, $X \cong \tau^{\leq n}X \in \mathcal{K}^{\leq n}$, and $\mathcal{K}^{\leq n}$ is closed under isomorphism, which is (a).

2. The argument is that of (1) with the arrows turned around. (a) implies (b) by (59.2). If (b) holds, then $\mathrm{Hom}(A, \tau^{\leq n}Y) = 0$ for every $A \in \mathcal{K}^{\leq n}$ by proposition 59.4.9(2), and $A = \tau^{\leq n}Y$ gives $\tau^{\leq n}Y \cong 0$. If (c) holds, the rotated truncation triangle $(\beta^n_Y, \partial^n_Y, -\alpha^n_Y[1])$ on $(Y, \tau^{\geq n+1}Y, (\tau^{\leq n}Y)[1])$ has third vertex $(\tau^{\leq n}Y)[1] \cong 0$, and lemma 59.4.5 makes β^n_Y an isomorphism. If (d) holds, $Y \cong \tau^{\geq n+1}Y \in \mathcal{K}^{\geq n+1}$.

3. A zero object Z has $\mathrm{Hom}(Z, B) = 0 = \mathrm{Hom}(A, Z)$ for all A and B, so it lies in $\mathcal{K}^{\leq n}$ by (1) and in $\mathcal{K}^{\geq n}$ by (2) with $n-1$ in place of n. For $X, X' \in \mathcal{K}^{\leq n}$ and $B \in \mathcal{K}^{\geq n+1}$, $\mathrm{Hom}(X \oplus X', B) \cong \mathrm{Hom}(X, B) \times \mathrm{Hom}(X', B) = 0$ by the universal property of the coproduct, so $X \oplus X' \in \mathcal{K}^{\leq n}$ by (1). The same argument with the product and (2) treats $\mathcal{K}^{\geq n}$. For extensions, let $A, C \in \mathcal{K}^{\leq n}$ and $B \in \mathcal{K}^{\geq n+1}$. The second sequence of (59.3) contains $\mathrm{Hom}(C, B) \to \mathrm{Hom}(X, B) \to \mathrm{Hom}(A, B)$, exact in the middle with both ends zero, so $\mathrm{Hom}(X, B) = 0$ and $X \in \mathcal{K}^{\leq n}$ by (1). If instead $A, C \in \mathcal{K}^{\geq n}$, then for every $T \in \mathcal{K}^{\leq n-1}$ the first sequence contains $\mathrm{Hom}(T, A) \to \mathrm{Hom}(T, X) \to \mathrm{Hom}(T, C)$ with both ends zero, so $\mathrm{Hom}(T, X) = 0$, and $X \in \mathcal{K}^{\geq n}$ by (2) with $n-1$ in place of n.

4. Let $X \in \mathcal{K}^{\leq n}$. Rotating the truncation triangle for $n-1$ gives the distinguished triangle $(\beta_X^{n-1}, \partial_X^{n-1}, -\alpha_X^{n-1}[1])$ on $(X, \tau^{\geq n}X, (\tau^{\leq n-1}X)[1])$. Its outer vertices lie in $\mathcal{K}^{\leq n}$, the second because $(\tau^{\leq n-1}X)[1] \in \mathcal{K}^{\leq n-2} \subseteq \mathcal{K}^{\leq n}$, so $\tau^{\geq n}X \in \mathcal{K}^{\leq n}$ by (3), and $\tau^{\geq n}X \in \mathcal{K}^{\geq n}$ by construction. Let $X \in \mathcal{K}^{\geq n}$. Rotating the truncation triangle for n backwards gives the distinguished triangle $(-\partial_X^n[-1], \alpha_X^n, \beta_X^n)$ on $((\tau^{\geq n+1}X)[-1], \tau^{\leq n}X, X)$. Its outer vertices lie in $\mathcal{K}^{\geq n}$, the first because $(\tau^{\geq n+1}X)[-1] \in \mathcal{K}^{\geq n+2} \subseteq \mathcal{K}^{\geq n}$, so $\tau^{\leq n}X \in \mathcal{K}^{\geq n}$ by (3), completing the proof.

By (1) and (2), each half of a t-structure determines the other: $\mathcal{K}^{\geq 1}$ consists of the objects that receive only the zero morphism from objects of $\mathcal{K}^{\leq 0}$, and $\mathcal{K}^{\leq 0}$ of the objects that admit only the zero morphism to objects of $\mathcal{K}^{\geq 1}$. By (4), truncating an object of $\mathcal{K}^{\leq 0}$ from below lands in the heart, which gives a functor into the heart.

Definition 59.4.11: Cohomology Functors of a t-Structure

Let $(\mathcal{K}^{\leq 0}, \mathcal{K}^{\geq 0})$ be a t-structure on $\mathcal{K}$. Its *cohomology functors* are

$$H_t^0 := \tau^{\geq 0}\tau^{\leq 0} \colon \mathcal{K} \to \mathcal{K}^\heartsuit, \qquad H_t^n(X) := H_t^0(X[n]) \quad (n \in \mathbb{Z})$$

which take values in $\mathcal{K}^\heartsuit$ by lemma 59.4.10(4) with $n = 0$.

Example 59.4.12: The Cohomology Functors of the Standard t-Structure

Take the standard t-structure on $D(\mathcal{A})$ and let $X \in D(\mathcal{A})$ and $n \in \mathbb{Z}$. Ordinary cohomology is cohomological on $D(\mathcal{A})$ (proposition 57.2.8), so applying it to the truncation triangle of proposition 59.4.9(1) and its rotations gives the long exact sequence

$$\cdots \to H^{i-1}(\tau^{\geq n+1}X) \to H^i(\tau^{\leq n}X) \xrightarrow{H^i(\alpha_X^n)} H^i(X) \xrightarrow{H^i(\beta_X^n)} H^i(\tau^{\geq n+1}X) \to H^{i+1}(\tau^{\leq n}X) \to \cdots$$

By example 59.4.2, $H^i(\tau^{\leq n}X) = 0$ for $i > n$ and $H^i(\tau^{\geq n+1}X) = 0$ for $i \leq n$. For $i \leq n$ the terms on either side of $H^i(\alpha_X^n)$ are $H^{i-1}(\tau^{\geq n+1}X) = 0$ and $H^i(\tau^{\geq n+1}X) = 0$, and for $i \geq n+1$ the terms on either side of $H^i(\beta_X^n)$ are $H^i(\tau^{\leq n}X) = 0$ and $H^{i+1}(\tau^{\leq n}X) = 0$. Hence

$$H^i(\tau^{\leq n}X) \cong \begin{cases} H^i(X) & i \leq n \\ 0 & i > n \end{cases} \qquad H^i(\tau^{\geq n+1}X) \cong \begin{cases} 0 & i \leq n \\ H^i(X) & i \geq n+1 \end{cases}$$

the abstract counterpart of proposition 56.1.14. The first formula with $n = 0$, followed by the second with $n = -1$ applied to $\tau^{\leq 0}X$, gives $H^i(H_t^0 X) = H^i(\tau^{\geq 0}\tau^{\leq 0}X) \cong H^0(X)$ for $i = 0$ and 0 for $i \neq 0$, the isomorphism in degree 0 being $H^0(\alpha_X^0) \circ H^0(\beta_{\tau^{\leq 0}X}^{-1})^{-1}$, which is natural in X. So the equivalence H^0 of theorem 59.3.7 carries the functor H_t^0 to ordinary H^0, and H_t^n to $X \mapsto H^0(X[n]) = H^n(X)$. For the complex $X = (\mathbb{Z} \xrightarrow{2} \mathbb{Z})$ in degrees -1 and 0 of example 59.3.2, $H^{-1}(X) = 0$ and $H^0(X) = \mathbb{Z}/2$, so $H_t^0(X)$ corresponds to $\mathbb{Z}/2$ and $H_t^{-1}(X) \cong 0$.

By example 59.3.8, the cone of a morphism f of $\mathcal{A}$ lies in $D^{\leq 0} \cap D^{\geq -1}$, and under H^0 the objects $\big(\tau^{\leq -1}MC(f)\big)[-1]$ and $\tau^{\geq 0}MC(f)$ of the heart correspond to $\ker f$ and $\operatorname{coker} f$. For an arbitrary t-structure the cone of a morphism of the heart still lies in $\mathcal{K}^{\leq 0} \cap \mathcal{K}^{\geq -1}$, and the same two truncations give a kernel and a cokernel in the heart.

Theorem 59.4.13: The Heart of a t-Structure Is Abelian

Let $(\mathcal{K}^{\leq 0}, \mathcal{K}^{\geq 0})$ be a t-structure on a triangulated category $\mathcal{K}$.

1. The heart $\mathcal{K}^\heartsuit$ is an abelian category, and it is closed under extensions in $\mathcal{K}$.
2. Let $f\colon X \to Y$ be a morphism of $\mathcal{K}^\heartsuit$ and (f, g, h) a distinguished triangle on (X, Y, Z). Then $Z \in \mathcal{K}^{\leq 0} \cap \mathcal{K}^{\geq -1}$, the composite $\beta_Z^{-1} \circ g\colon Y \to \tau^{\geq 0} Z$ is a cokernel of f in $\mathcal{K}^\heartsuit$, and the composite $h[-1] \circ \alpha_Z^{-1}[-1]\colon (\tau^{\leq -1} Z)[-1] \to X$ is a kernel of f in $\mathcal{K}^\heartsuit$.
3. A sequence $0 \to X \xrightarrow{f} Y \xrightarrow{g} Z \to 0$ of $\mathcal{K}^\heartsuit$ is exact if and only if there is a morphism $h\colon Z \to X[1]$ with (f, g, h) distinguished, and such an h is unique.

***Proof*:**

Step 1: $\mathcal{K}^\heartsuit$ is additive. By lemma 59.4.10(3) with $n = 0$, $\mathcal{K}^\heartsuit$ contains the zero objects and the direct sum of any two of its objects. A full subcategory of the additive category $\mathcal{K}$ with these two properties is additive (definition 55.1.1). It has the Hom groups of $\mathcal{K}$ with their bilinear composition, a zero object of $\mathcal{K}$ is a zero object of it, and the biproduct $X \oplus Y$ of $\mathcal{K}$, lying in it, has the universal properties of product and coproduct there because the subcategory is full. Closure under extensions is lemma 59.4.10(3) for $\mathcal{K}^{\leq 0}$ and $\mathcal{K}^{\geq 0}$ together.

Step 2: $Z \in \mathcal{K}^{\leq 0} \cap \mathcal{K}^{\geq -1}$. Rotating gives the distinguished triangle $(g, h, -f[1])$ on $(Y, Z, X[1])$. Here $Y \in \mathcal{K}^{\leq 0}$ and $X[1] \in \mathcal{K}^{\leq -1} \subseteq \mathcal{K}^{\leq 0}$, so $Z \in \mathcal{K}^{\leq 0}$ by lemma 59.4.10(3). Likewise $Y \in \mathcal{K}^{\geq 0} \subseteq \mathcal{K}^{\geq -1}$ and $X[1] \in \mathcal{K}^{\geq -1}$, so $Z \in \mathcal{K}^{\geq -1}$.

Step 3: The cokernel. Put $C := \tau^{\geq 0} Z$ and $c := \beta_Z^{-1} g$. Then $C \in \mathcal{K}^{\geq 0}$, and $C \in \mathcal{K}^{\leq 0}$ by lemma 59.4.10(4) because $Z \in \mathcal{K}^{\leq 0}$, so $C \in \mathcal{K}^\heartsuit$. Let $T \in \mathcal{K}^\heartsuit$. Precomposition with β_Z^{-1} is a bijection $\mathrm{Hom}(C, T) \to \mathrm{Hom}(Z, T)$ by proposition 59.4.9(2), as $T \in \mathcal{K}^{\geq 0}$. The second sequence of (59.3) for (f, g, h) gives the exact sequence

$$0 = \mathrm{Hom}(X[1], T) \to \mathrm{Hom}(Z, T) \xrightarrow{g^*} \mathrm{Hom}(Y, T) \xrightarrow{f^*} \mathrm{Hom}(X, T)$$

where $\mathrm{Hom}(X[1], T) = 0$ because $X[1] \in \mathcal{K}^{\leq -1}$ and $T \in \mathcal{K}^{\geq 0}$. Composing, $\varphi \mapsto \varphi c$ is a bijection from $\mathrm{Hom}(C, T)$ onto $\{\psi \in \mathrm{Hom}(Y, T) \big| \psi f = 0\}$. Taking $T = C$ and $\varphi = \mathrm{id}_C$ shows $cf = 0$, and the bijection for every $T \in \mathcal{K}^\heartsuit$ is the universal property of a cokernel of f in $\mathcal{K}^\heartsuit$.

Step 4: The kernel. Put $N := (\tau^{\leq -1} Z)[-1]$ and $k := h[-1] \circ \alpha_Z^{-1}[-1]$. Since $\tau^{\leq -1} Z \in \mathcal{K}^{\leq -1}$, and $\tau^{\leq -1} Z \in \mathcal{K}^{\geq -1}$ by lemma 59.4.10(4) because $Z \in \mathcal{K}^{\geq -1}$, the object N lies in $\mathcal{K}^{\leq 0} \cap \mathcal{K}^{\geq 0} = \mathcal{K}^\heartsuit$. Let $T \in \mathcal{K}^\heartsuit$. As $T[1] \in \mathcal{K}^{\leq -1}$, composition with α_Z^{-1} is a bijection $\mathrm{Hom}(T[1], \tau^{\leq -1} Z) \to \mathrm{Hom}(T[1], Z)$ by proposition 59.4.9(2), and applying the bijection $[-1]$ on Hom groups turns it into the bijection $\varphi \mapsto \alpha_Z^{-1}[-1] \circ \varphi$ from $\mathrm{Hom}(T, N)$ to $\mathrm{Hom}(T, Z[-1])$. The first sequence of (59.3) for (f, g, h) gives the exact sequence

$$0 = \mathrm{Hom}(T, Y[-1]) \to \mathrm{Hom}(T, Z[-1]) \xrightarrow{(-h[-1])_*} \mathrm{Hom}(T, X) \xrightarrow{f_*} \mathrm{Hom}(T, Y)$$

where $\mathrm{Hom}(T, Y[-1]) = 0$ because $T \in \mathcal{K}^{\leq 0}$ and $Y[-1] \in \mathcal{K}^{\geq 1}$. The map $(h[-1])_* = -(-h[-1])_*$ has the same kernel and image, so $\varphi \mapsto k\varphi$ is a bijection from $\mathrm{Hom}(T, N)$ onto

$\{\psi \in \mathrm{Hom}(T,X) \mid f\psi = 0\}$, the universal property of a kernel of f. So $\mathcal{K}^\heartsuit$ has kernels and cokernels.

Step 5: $\mathcal{K}^\heartsuit$ is abelian. Let f be a monomorphism of $\mathcal{K}^\heartsuit$. Its kernel N from Step 4 is a zero object by lemma 55.1.4, so $\tau^{\leq -1}Z \cong N[1] \cong 0$, and $Z \in \mathcal{K}^{\geq 0}$ by lemma 59.4.10(2) with $n = -1$. With Step 2, $Z \in \mathcal{K}^\heartsuit$. For $T \in \mathcal{K}^\heartsuit$ the first sequence of (59.3) gives the exact sequence

$$0 = \mathrm{Hom}(T, Z[-1]) \to \mathrm{Hom}(T,X) \xrightarrow{f_*} \mathrm{Hom}(T,Y) \xrightarrow{g_*} \mathrm{Hom}(T,Z)$$

the first group vanishing because $Z[-1] \in \mathcal{K}^{\geq 1}$. So f is a kernel of $g\colon Y \to Z$ in $\mathcal{K}^\heartsuit$. Now let f be an epimorphism. Its cokernel C from Step 3 is a zero object, so $Z \in \mathcal{K}^{\leq -1}$ by lemma 59.4.10(1) with $n = -1$, and with Step 2, $Z[-1] \in \mathcal{K}^{\leq 0} \cap \mathcal{K}^{\geq 0} = \mathcal{K}^\heartsuit$. For $T \in \mathcal{K}^\heartsuit$ the second sequence of (59.3) gives the exact sequence

$$0 = \mathrm{Hom}(Z,T) \to \mathrm{Hom}(Y,T) \xrightarrow{f^*} \mathrm{Hom}(X,T) \to \mathrm{Hom}(Z[-1],T)$$

whose last map is composition with $-h[-1]$, the first group vanishing because $Z \in \mathcal{K}^{\leq -1}$. So f is a cokernel of $-h[-1]\colon Z[-1] \to X$ in $\mathcal{K}^\heartsuit$. Every monomorphism of $\mathcal{K}^\heartsuit$ is therefore a kernel and every epimorphism a cokernel, and $\mathcal{K}^\heartsuit$ is abelian by definition 55.1.6. This proves (1) and (2).

Step 6: Exactness in $\mathcal{K}^\heartsuit$. In the abelian category $\mathcal{K}^\heartsuit$, the sequence $0 \to X \to Y \to Z \to 0$ is exact if and only if f is a kernel of g and g is a cokernel of f. If both hold, f is a monomorphism and g an epimorphism by lemma 55.1.3, which is exactness at X and at Z (example 55.1.14), and at Y the composite $\mathrm{coker}\, f \circ \ker g$ is $g \circ f = 0$. Conversely, suppose the sequence is exact. Then g is an epimorphism, hence a cokernel by definition 55.1.6, hence the cokernel of its kernel $\ker g\colon K \to Y$ by lemma 55.1.7. Exactness at Y gives $gf = 0$, so $f = (\ker g)a$ for some $a\colon X \to K$, and $(\mathrm{coker} f)(\ker g) = 0$, so $\ker g$ factors through the kernel of $\mathrm{coker} f$. That kernel is f, since f is a monomorphism, hence a kernel, hence the kernel of its cokernel by the same two results. Writing $\ker g = fb$, the identities $f = fba$ and $\ker g = (\ker g)ab$ give $ba = \mathrm{id}_X$ and $ab = \mathrm{id}_K$, as f and $\ker g$ are monomorphisms. So f is a kernel of g, and g, the cokernel of $\ker g$, is a cokernel of f.

Step 7: Exact sequences and triangles. Suppose (f,g,h) is distinguished with $X, Y, Z \in \mathcal{K}^\heartsuit$. The exact sequence of Step 5 for monomorphisms used only $Z \in \mathcal{K}^\heartsuit$, and it shows that f is a kernel of g. The exact sequence of Step 3 shows that g^* is a bijection from $\mathrm{Hom}(Z,T)$ onto $\{\psi | \psi f = 0\}$ for every $T \in \mathcal{K}^\heartsuit$, so g is a cokernel of f. By Step 6 the sequence is exact. Conversely, let the sequence be exact, and choose by (TR1) a distinguished triangle (f,g',h') on (X,Y,Z'). Since f is a monomorphism, Step 5 puts Z' in $\mathcal{K}^\heartsuit$, and the previous argument makes g' a cokernel of f. Cokernels are unique up to unique isomorphism, so $g = \varphi g'$ for an isomorphism $\varphi\colon Z' \to Z$, and $(\mathrm{id}_X, \mathrm{id}_Y, \varphi)$ is an isomorphism of triangles from (f,g',h') to $(f,g,h'\varphi^{-1})$, which is therefore distinguished by (TR1). For uniqueness, let (f,g,h) and (f,g,h_1) both be distinguished. (TR3) gives $\kappa\colon Z \to Z$ with $(\mathrm{id}_X, \mathrm{id}_Y, \kappa)$ a morphism from the first to the second, so $\kappa g = g$ and $h_1\kappa = h$. Then $(\kappa - \mathrm{id}_Z)g = 0$, and in the second sequence of (59.3) for (f,g,h) and $T = Z$, the kernel of g^* on $\mathrm{Hom}(Z,Z)$ is the image of $\mathrm{Hom}(X[1],Z)$, which is zero because $X[1] \in \mathcal{K}^{\leq -1}$ and $Z \in \mathcal{K}^{\geq 0}$. So $\kappa = \mathrm{id}_Z$ and $h_1 = h$, completing the proof.

Theorem 59.4.13 is [8, Thm. 1.3.6], and (1) is also [53, Thm. IV.4.4]. By (3), the short exact sequences of $\mathcal{K}^\heartsuit$ are the distinguished triangles with all three vertices in $\mathcal{K}^\heartsuit$, and the third edge of such a triangle is determined by the other two. The heart does not determine $\mathcal{K}$: in example 59.4.3 it is zero whatever $\mathcal{K}$ is.

Example 59.4.14: Kernel and Cokernel of Multiplication by 2 on $\mathbb{Z}/4$

In the standard t-structure on $D(\mathbf{Ab})$, let $f\colon \mathbb{Z}/4 \to \mathbb{Z}/4$ be multiplication by 2, both objects in degree 0. By example 59.3.8, its mapping cone triangle on $(\mathbb{Z}/4, \mathbb{Z}/4, MC(f))$ is distinguished in $D(\mathbf{Ab})$, and $MC(f)$ is the complex $\mathbb{Z}/4 \xrightarrow{2} \mathbb{Z}/4$ in degrees -1 and 0, the complex Y of example 59.3.2. Both $H^{-1}(MC(f))$ and $H^0(MC(f))$ are isomorphic to $\mathbb{Z}/2$ there, so $MC(f) \in D^{\leq 0} \cap D^{\geq -1}$, as theorem 59.4.13(2) requires, and $MC(f)$ is not in the heart. For the standard t-structure the truncation functors $\tau^{\leq -1}$ and $\tau^{\geq 0}$ are the canonical truncations, by the choice in Step 1 of the proof of proposition 59.4.9 and the paragraph after that proof, and example 59.3.5 computes them for $MC(f)$: $\tau^{\leq -1}MC(f)$ is $\{0, 2\}$ in degree -1, and $\tau^{\geq 0}MC(f)$ is $(\mathbb{Z}/4)/\{0, 2\}$ in degree 0. So the kernel $\big(\tau^{\leq -1}MC(f)\big)[-1]$ and the cokernel $\tau^{\geq 0}MC(f)$ that theorem 59.4.13(2) gives are isomorphic to $\{0, 2\}$ and $(\mathbb{Z}/4)/\{0, 2\}$ in degree 0. The equivalence H^0 of theorem 59.3.7 carries them to the kernel and cokernel of multiplication by 2 computed in $\mathbf{Ab}$. Neither is zero, so f is neither a monomorphism nor an epimorphism of the heart.

For the standard t-structure, H^n_t is ordinary cohomology (example 59.4.12), which carries distinguished triangles to long exact sequences. For every t-structure, H^0_t is a cohomological functor $\mathcal{K} \to \mathcal{K}^\heartsuit$. A triangle whose first vertex lies in $\mathcal{K}^{\leq 0}$ goes to a right exact sequence in the heart, a triangle whose third vertex lies in $\mathcal{K}^{\geq 0}$ to a left exact one, and the octahedral axiom splits an arbitrary triangle into one of each.

Corollary 59.4.15: H^0_t Is a Cohomological Functor

Let $(\mathcal{K}^{\leq 0}, \mathcal{K}^{\geq 0})$ be a t-structure on $\mathcal{K}$. Then $H^0_t\colon \mathcal{K} \to \mathcal{K}^\heartsuit$ is a cohomological functor in the sense of definition 57.1.6. Consequently every distinguished triangle (u, v, w) on (X, Y, Z) gives a long exact sequence in $\mathcal{K}^\heartsuit$

$$\cdots \to H^n_t(X) \to H^n_t(Y) \to H^n_t(Z) \to H^{n+1}_t(X) \to H^{n+1}_t(Y) \to \cdots$$

***Proof*:**

Write H^0 for H^0_t, which is additive because $\tau^{\leq 0}$ and $\tau^{\geq 0}$ are (proposition 59.4.9). In the abelian category $\mathcal{K}^\heartsuit$ (theorem 59.4.13), a pair $P \xrightarrow{a} Q \xrightarrow{b} R$ with $ba = 0$ is exact at Q as soon as a is a kernel of b or b is a cokernel of a, since then $\operatorname{coker} a \circ \ker b$ is $\operatorname{coker} a \circ a = 0$, respectively $b \circ \ker b = 0$ (definition 55.1.13). If a and b are replaced by $\mu a \nu$ and $b\mu^{-1}$ for isomorphisms μ and ν, a kernel stays a kernel, and if they are replaced by $\mu a \nu$ and $\lambda b \mu^{-1}$, a cokernel stays a cokernel. The proof establishes one of the two conditions, case by case, using four facts.

(P) Maps out of $H^0(U)$ for $U \in \mathcal{K}^{\leq 0}$. By lemma 59.4.10(1), α^0_U is an isomorphism. Put $\theta_U := \beta^{-1}_{\tau^{\leq 0}U} \circ (\alpha^0_U)^{-1}\colon U \to H^0(U)$, which is natural in $U \in \mathcal{K}^{\leq 0}$ by the naturality of α^0 and β^{-1}. For $T \in \mathcal{K}^\heartsuit$, precomposition with θ_U is a bijection $\operatorname{Hom}(H^0(U), T) \to \operatorname{Hom}(U, T)$, by proposition 59.4.9(2) for β^{-1}, as $T \in \mathcal{K}^{\geq 0}$.

(P) Maps into $H^0(V)$ for $V \in \mathcal{K}^{\geq 0}$.* By lemma 59.4.10(4), $\tau^{\leq 0}V \in \mathcal{K}^{\geq 0}$, so $\beta^{-1}_{\tau^{\leq 0}V}$ is an isomorphism by lemma 59.4.10(2) with $n = -1$. Put $\kappa_V := \alpha^0_V \circ (\beta^{-1}_{\tau^{\leq 0}V})^{-1} \colon H^0(V) \to V$, natural in $V \in \mathcal{K}^{\geq 0}$. For $T \in \mathcal{K}^{\heartsuit}$, composition with κ_V is a bijection $\mathrm{Hom}(T, H^0(V)) \to \mathrm{Hom}(T, V)$, by proposition 59.4.9(2) for α^0, as $T \in \mathcal{K}^{\leq 0}$.

(E) $H^0(\alpha^0_X)$ is an isomorphism for every X. Naturality of α^0 at the morphism α^0_X gives $\alpha^0_X \circ \tau^{\leq 0}(\alpha^0_X) = \alpha^0_X \circ \alpha^0_{\tau^{\leq 0}X}$, so $\tau^{\leq 0}(\alpha^0_X) = \alpha^0_{\tau^{\leq 0}X}$ by the injectivity in proposition 59.4.9(2), and this is an isomorphism by lemma 59.4.10(1), as $\tau^{\leq 0}X \in \mathcal{K}^{\leq 0}$. Applying $\tau^{\geq 0}$ gives the claim.

Case 1: $X, Y, Z \in \mathcal{K}^{\leq 0}$. Then $H^0(v)$ is a cokernel of $H^0(u)$. For $T \in \mathcal{K}^{\heartsuit}$ the second sequence of (59.3) gives the exact sequence $0 = \mathrm{Hom}(X[1], T) \to \mathrm{Hom}(Z, T) \xrightarrow{v^*} \mathrm{Hom}(Y, T) \xrightarrow{u^*} \mathrm{Hom}(X, T)$, the first group vanishing because $X[1] \in \mathcal{K}^{\leq -1}$ and $T \in \mathcal{K}^{\geq 0}$. By (P) and the naturality of θ it is isomorphic to the sequence

$$0 \to \mathrm{Hom}(H^0(Z), T) \xrightarrow{H^0(v)^*} \mathrm{Hom}(H^0(Y), T) \xrightarrow{H^0(u)^*} \mathrm{Hom}(H^0(X), T)$$

which is therefore exact for every $T \in \mathcal{K}^{\heartsuit}$. That is the statement that $H^0(v)$ is a cokernel of $H^0(u)$.

Case 1: $X, Y, Z \in \mathcal{K}^{\geq 0}$. Then $H^0(u)$ is a kernel of $H^0(v)$.* For $T \in \mathcal{K}^{\heartsuit}$ the first sequence of (59.3) gives the exact sequence $0 = \mathrm{Hom}(T, Z[-1]) \to \mathrm{Hom}(T, X) \xrightarrow{u_*} \mathrm{Hom}(T, Y) \xrightarrow{v_*} \mathrm{Hom}(T, Z)$, the first group vanishing because $T \in \mathcal{K}^{\leq 0}$ and $Z[-1] \in \mathcal{K}^{\geq 1}$. By (P*) and the naturality of κ it is isomorphic to $0 \to \mathrm{Hom}(T, H^0(X)) \to \mathrm{Hom}(T, H^0(Y)) \to \mathrm{Hom}(T, H^0(Z))$ with maps $H^0(u)_*$ and $H^0(v)_*$, which says that $H^0(u)$ is a kernel of $H^0(v)$.

Case 2: $X \in \mathcal{K}^{\leq 0}$. Then $H^0(v)$ is a cokernel of $H^0(u)$. By proposition 59.4.9(2), $u = \alpha^0_Y u'$ for a unique $u' \colon X \to \tau^{\leq 0}Y$. Choose a distinguished triangle (u', r, e) on $(X, \tau^{\leq 0}Y, W)$ and apply (TR4) to the composable pair $X \xrightarrow{u'} \tau^{\leq 0}Y \xrightarrow{\alpha^0_Y} Y$, with (u', r, e) as the triangle on the first map, the truncation triangle $(\alpha^0_Y, \beta^0_Y, \partial^0_Y)$ on the second, and (u, v, w) on the composite. It gives a distinguished triangle $(f, g, r[1]\,\partial^0_Y)$ on $(W, Z, \tau^{\geq 1}Y)$ satisfying, among the four identities of (TR4), $fr = v\alpha^0_Y$. Rotating (u', r, e) gives the distinguished triangle $(r, e, -u'[1])$ on $(\tau^{\leq 0}Y, W, X[1])$, whose outer vertices lie in $\mathcal{K}^{\leq 0}$, so $W \in \mathcal{K}^{\leq 0}$ by lemma 59.4.10(3). The triangle $(f, g, r[1]\,\partial^0_Y)$ on $(W, Z, \tau^{\geq 1}Y)$ therefore has $W \in \mathcal{K}^{\leq 0}$ and $\tau^{\geq 1}Y \in \mathcal{K}^{\geq 1}$, and proposition 59.4.9(3) gives an isomorphism $\varphi \colon W \to \tau^{\leq 0}Z$ with $\alpha^0_Z \varphi = f$. Then $\alpha^0_Z \varphi r = fr = v\alpha^0_Y$. Case 1 applies to (u', r, e), whose three vertices lie in $\mathcal{K}^{\leq 0}$: $H^0(r)$ is a cokernel of $H^0(u')$. Finally $H^0(u) = H^0(\alpha^0_Y)H^0(u')$, and applying H^0 to $\alpha^0_Z \varphi r = v\alpha^0_Y$ gives $H^0(v) = H^0(\alpha^0_Z)H^0(\varphi)H^0(r)H^0(\alpha^0_Y)^{-1}$, where $H^0(\alpha^0_Y)$ and $H^0(\alpha^0_Z)$ are isomorphisms by (E), and $H^0(\varphi)$ is one because φ is. So $H^0(v)$ is a cokernel of $H^0(u)$.

(E) $H^0(\beta_P^{-1})$ is an isomorphism for every P.* Case 2 applies to the truncation triangle $(\alpha_P^{-1}, \beta_P^{-1}, \partial_P^{-1})$, whose first vertex lies in $\mathcal{K}^{\leq -1} \subseteq \mathcal{K}^{\leq 0}$, so $H^0(\beta_P^{-1})$ is a cokernel of $H^0(\alpha_P^{-1})$. The source of the latter is zero: $\tau^{\leq 0}\tau^{\leq -1}P \cong \tau^{\leq -1}P$ by lemma 59.4.10(1), and $\tau^{\geq 0}$ of an object of $\mathcal{K}^{\leq -1}$ is zero by lemma 59.4.10(1) with $n = -1$. The identity of $H^0(P)$ is a cokernel of the morphism from a zero object, and cokernels are unique up to isomorphism, so $H^0(\beta_P^{-1})$ is an isomorphism.

Case 2: $Z \in \mathcal{K}^{\geq 0}$. Then $H^0(u)$ is a kernel of $H^0(v)$.* Choose a distinguished triangle $(u\alpha_X^{-1}, y, e)$ on $(\tau^{\leq -1}X, Y, V)$ and apply (TR4) to $\tau^{\leq -1}X \xrightarrow{\alpha_X^{-1}} X \xrightarrow{u} Y$, with the truncation triangle $(\alpha_X^{-1}, \beta_X^{-1}, \partial_X^{-1})$ on the first map, (u, v, w) on the second and $(u\alpha_X^{-1}, y, e)$ on the composite. It gives a distinguished triangle $(f, g, \beta_X^{-1}[1]\, w)$ on $(\tau^{\geq 0}X, V, Z)$ with $v = gy$ and $yu = f\beta_X^{-1}$. Its outer vertices lie in $\mathcal{K}^{\geq 0}$, so $V \in \mathcal{K}^{\geq 0}$ by lemma 59.4.10(3). Then $(u\alpha_X^{-1}, y, e)$ is distinguished on $(\tau^{\leq -1}X, Y, V)$ with $\tau^{\leq -1}X \in \mathcal{K}^{\leq -1}$ and $V \in \mathcal{K}^{\geq 0}$, and proposition 59.4.9(3) with $n = -1$ gives an isomorphism $\psi\colon V \to \tau^{\geq 0}Y$ with $\psi y = \beta_Y^{-1}$. Hence $\beta_Y^{-1}u = \psi yu = \psi f\beta_X^{-1}$. Case 1* applies to $(f, g, \beta_X^{-1}[1]\, w)$, whose three vertices lie in $\mathcal{K}^{\geq 0}$: $H^0(f)$ is a kernel of $H^0(g)$. Applying H^0 to $\beta_Y^{-1}u = \psi f\beta_X^{-1}$ and to $v = g\psi^{-1}\beta_Y^{-1}$ gives

$$H^0(u) = \mu\, H^0(f)\, H^0(\beta_X^{-1}), \qquad H^0(v) = H^0(g)\, \mu^{-1}, \qquad \mu := H^0(\beta_Y^{-1})^{-1} H^0(\psi)$$

with μ and $H^0(\beta_X^{-1})$ isomorphisms by (E*). So $H^0(u)$ is a kernel of $H^0(v)$.

The general case. Let (u, v, w) be any distinguished triangle on (X, Y, Z). Choose a distinguished triangle $(u\alpha_X^0, y, e)$ on $(\tau^{\leq 0}X, Y, U)$ and apply (TR4) to $\tau^{\leq 0}X \xrightarrow{\alpha_X^0} X \xrightarrow{u} Y$, with the truncation triangle $(\alpha_X^0, \beta_X^0, \partial_X^0)$ on the first map, (u, v, w) on the second and $(u\alpha_X^0, y, e)$ on the composite. It gives a distinguished triangle $(f, g, \beta_X^0[1]\, w)$ on $(\tau^{\geq 1}X, U, Z)$ with $v = gy$. Rotating it gives the distinguished triangle $(g, \beta_X^0[1]\, w, -f[1])$ on $(U, Z, (\tau^{\geq 1}X)[1])$, whose third vertex lies in $\mathcal{K}^{\geq 0}$. Case 2, applied to $(u\alpha_X^0, y, e)$, whose first vertex lies in $\mathcal{K}^{\leq 0}$, shows that $H^0(y)$ is a cokernel of $H^0(u)H^0(\alpha_X^0)$, hence of $H^0(u)$, as $H^0(\alpha_X^0)$ is an isomorphism by (E). Case 2*, applied to the rotated triangle, shows that $H^0(g)$ is a kernel, hence a monomorphism by lemma 55.1.3. So $\ker H^0(v) = \ker(H^0(g)H^0(y)) = \ker H^0(y)$, and $\operatorname{coker} H^0(u) \circ \ker H^0(v) = H^0(y) \circ \ker H^0(y) = 0$. Together with $H^0(v)H^0(u) = H^0(vu) = 0$ (lemma 57.1.7), this is exactness at $H^0(Y)$, so H^0 is cohomological. The long exact sequence follows by applying this to the rotations of (u, v, w) and splicing the resulting exact sequences, with $H^0(X[n]) = H_t^n(X)$, completing the proof.

The corollary is the last assertion of [8, Thm. 1.3.6] and is [53, Thm. IV.4.11(a)]. For the standard t-structure it returns the long exact cohomology sequence of a distinguished triangle of $D(\mathcal{A})$, by example 59.4.12.

Example 59.4.16: The Four-Term Sequence of Multiplication by 2

Apply corollary 59.4.15 to the mapping cone triangle of $f = 2\colon \mathbb{Z}/4 \to \mathbb{Z}/4$ from example 59.4.14. As $\mathbb{Z}/4$ in degree 0 has $H_t^n = 0$ for $n \neq 0$, and $MC(f)$ has $H_t^n = 0$ for $n \neq -1, 0$, the long exact sequence reduces, after applying the equivalence of theorem 59.3.7, which preserves kernels and cokernels, and example 59.4.12, to the exact sequence

$$0 \to H^{-1}(MC(f)) \to \mathbb{Z}/4 \xrightarrow{2} \mathbb{Z}/4 \to H^0(MC(f)) \to 0$$

Exactness on the left makes the first map an injection onto $\ker(2) = \{0, 2\}$, and exactness on the right makes the last map a surjection with kernel $\{0, 2\}$. So the long exact sequence of the triangle is the four-term sequence $0 \to \ker f \to \mathbb{Z}/4 \to \mathbb{Z}/4 \to \operatorname{coker} f \to 0$, and it recovers both computations of example 59.4.14 at once.

In $D(\mathcal{A})$ a complex lying in every $D^{\leq n}$, or in every $D^{\geq n}$, has zero cohomology and so is zero (proposition 57.2.12). The axioms do not give this for an arbitrary t-structure: if X is a nonzero object of $\mathcal{K}$, then X lies in every $\mathcal{K}^{\leq n}$ for the t-structure of example 59.4.3. Nondegeneracy, the first

condition in definition 59.4.17, imposes this vanishing on a t-structure. Boundedness, the second, asks that every object lie in $\mathcal{K}^{\leq b} \cap \mathcal{K}^{\geq a}$ for some integers a and b. When $\mathcal{A}$ has a nonzero object it fails for the standard t-structure on $D(\mathcal{A})$, where a single complex can have nonzero cohomology in infinitely many degrees.

Definition 59.4.17: Nondegenerate and Bounded t-Structures

A t-structure $(\mathcal{K}^{\leq 0}, \mathcal{K}^{\geq 0})$ on $\mathcal{K}$ is *nondegenerate* if every object lying in $\mathcal{K}^{\leq n}$ for all $n \in \mathbb{Z}$ is a zero object, and every object lying in $\mathcal{K}^{\geq n}$ for all $n \in \mathbb{Z}$ is a zero object. It is *bounded* if every $X \in \mathcal{K}$ lies in $\mathcal{K}^{\leq b} \cap \mathcal{K}^{\geq a}$ for some integers a and b.

Example 59.4.18: The Standard t-Structure Is Nondegenerate and Not Bounded

An object X of $D^{\leq n}$ for every n, or of $D^{\geq n}$ for every n, has $H^i(X) = 0$ for all i by example 59.4.2, so X is exact and $X \cong 0$ in $D(\mathcal{A})$ by proposition 57.2.12. So the standard t-structure is nondegenerate. If $\mathcal{A}$ has a nonzero object M, the complex with M in every degree and all differentials zero has $H^i = M$ for every i, so it lies in no $D^{\leq b}$, and the standard t-structure is not bounded. The objects lying in some $D^{\leq b} \cap D^{\geq a}$ are the complexes with bounded cohomology, which form the subcategory $D^b(\mathcal{A})$ of box 57.2.5, and the truncation argument there shows that each such X is isomorphic in $D(\mathcal{A})$ to the bounded complex $\tau^{\geq a}\tau^{\leq b}X$. The t-structure of example 59.4.3 on a category with a nonzero object X is degenerate, since $X \in \mathcal{K}^{\leq n}$ for every n.

Besides its standard t-structure, the constructible derived category of a stratified space carries the perverse t-structure, whose heart, the category of perverse sheaves, is abelian by theorem 59.4.13. Its construction is the subject of the *Perverse Sheaves* volume [38]. A t-structure on a stable ∞-category is a t-structure in the sense of definition 59.4.1 on its homotopy category. There the enhancement provides functorial cones [27], which the axioms of a triangulated category do not give (box 57.1.4).

Exercise 59.4.1

1. Let $\mathcal{K}$ be a triangulated category, let $\mathcal{K}^{\leq 0}$ be the full subcategory of zero objects, and let $\mathcal{K}^{\geq 0} = \mathcal{K}$. Show that $(\mathcal{K}^{\leq 0}, \mathcal{K}^{\geq 0})$ is a t-structure, that its heart consists of the zero objects, and that it is nondegenerate if and only if every object of $\mathcal{K}$ is a zero object.
2. Show that a bounded t-structure is nondegenerate.
3. Let $X, Y \in \mathcal{K}^{\heartsuit}$ and $n < 0$. Show that $\mathrm{Hom}_{\mathcal{K}}(X, Y[n]) = 0$.
4. Let $T \in \mathcal{K}^{\heartsuit}$. Show that $H^0_t(T) \cong T$ and that $H^n_t(T) \cong 0$ for every $n \neq 0$.
5. Let $X \in \mathcal{K}^{\leq 0}$ and $Y \in \mathcal{K}^{\geq 0}$. Show that $f \mapsto H^0_t(f)$ is a bijection $\mathrm{Hom}_{\mathcal{K}}(X, Y) \to \mathrm{Hom}_{\mathcal{K}^{\heartsuit}}(H^0_t X, H^0_t Y)$.
6. In the standard t-structure on $D(\mathbf{Ab})$, let $f\colon \mathbb{Z}/4 \to \mathbb{Z}/8$ be the homomorphism $x \mapsto 4x$, both objects in degree 0. Compute the cohomology of $MC(f)$, decide whether f is a monomorphism or an epimorphism of the heart, and identify, through the equivalence of theorem 59.3.7, the kernel and cokernel that theorem 59.4.13(2) produces.
7. Let $X, Z \in \mathcal{K}^{\heartsuit}$, and let $i_X\colon X \to X \oplus Z$ and $p_Z\colon X \oplus Z \to Z$ be the inclusion and projection of the biproduct. Use theorem 59.4.13(3) and lemma 57.1.7 to show that $(i_X, p_Z, 0)$ is a distinguished triangle on $(X, X \oplus Z, Z)$.

8. Suppose the t-structure is nondegenerate.

    1. Show that if $X \in \mathcal{K}^{\geq 0}$ and $H_t^0(X) \cong 0$, then $X \in \mathcal{K}^{\geq 1}$, and that if $X \in \mathcal{K}^{\leq 0}$ and $H_t^0(X) \cong 0$, then $X \in \mathcal{K}^{\leq -1}$.
    2. Deduce that $X \cong 0$ whenever $H_t^n(X) \cong 0$ for every $n \in \mathbb{Z}$. (Treat $X \in \mathcal{K}^{\geq 0}$ and $X \in \mathcal{K}^{\leq 0}$ first, then apply the long exact sequence of corollary 59.4.15 to the truncation triangle of X.)
    3. Show that a morphism f of $\mathcal{K}$ is an isomorphism if and only if $H_t^n(f)$ is an isomorphism for every n.

60

Spectral Sequences

The derived functors of chapter 56 measure the failure of a single functor to be exact, and the long exact sequence of theorem 56.3.11 turns that measurement into something computable. Both tools carry the same limitation: each relates the cohomology of one object to the cohomology of two others, and no more. An object assembled from many pieces produces not one long exact sequence but a whole family of them at once, one for each stage of the assembly, and no finite amount of splicing turns that family into an answer. A module carrying a filtration $M = M_0 \supseteq M_1 \supseteq \cdots$ (section 25.2) is the basic case; a functor that factors through a third abelian category is another, and the double complexes of section 56.5 are a third.

A spectral sequence is the bookkeeping that assembles such a family. It produces a sequence of *pages* $E_1, E_2, E_3, \ldots$, each the cohomology of the one before it, beginning with a crude first approximation to the answer and correcting it repeatedly until the corrections run out. This chapter builds the machine and then gives the three standard sources of one. Section 60.1 isolates the algebraic mechanism, Massey's exact couple, from which every page and every differential is generated by a single operation. Section 60.2 constructs the spectral sequence of a filtered complex and proves the convergence and comparison theorems that make it usable. Section 60.3 treats the two spectral sequences of a double complex, completing the computations of section 56.5.1 that were deferred to this chapter. Section 60.4 derives a left exact functor on a bounded-below complex through a resolution of the complex by injectives, and gives the two spectral sequences of this hypercohomology. Section 60.5 obtains from them the spectral sequence of a composite of derived functors, the form in which the machine is most often applied. Section 60.6 treats complexes carrying two filtrations.

60.1 Exact Couples and Derived Couples

The obstacle a spectral sequence exists to overcome is visible already in the simplest case. A short exact sequence of complexes $0 \to A_\bullet \to C_\bullet \to C_\bullet/A_\bullet \to 0$ yields a long exact sequence relating

the three cohomologies, but that sequence does not determine $H_\bullet(C)$ from $H_\bullet(A)$ and $H_\bullet(C/A)$: it determines only the two ends of a short exact sequence


$$0 \to \operatorname{coker}\partial \to H_n(C) \to \ker \partial \to 0$$

and the extension itself is extra information the sequence does not carry. With one layer the ambiguity is a single extension problem. With a filtration of many layers there is one such problem per layer, and there are also correction terms of a different kind: a cohomology class of one layer may fail to extend over the next layer but succeed over the one after, and nothing in any individual long exact sequence detects that.

The device that organizes all of these at once packages every long exact sequence of the filtration into a single self-regenerating triangle. Its two vertices carry different roles: one is the answer being approximated, the other the auxiliary object that remembers how the layers are glued.

Definition 60.1.1: Exact Couple

Let $\mathcal{A}$ be an abelian category. An *exact couple* in $\mathcal{A}$ is a pair of objects D and E together with three morphisms



such that the triangle is exact at each of its three corners:

$$\operatorname{im} i = \ker j, \qquad \operatorname{im} j = \ker k, \qquad \operatorname{im} k = \ker i$$

The composite $d := j \circ k \colon E \to E$ is the *differential* of the couple, and the couple is written (D, E, i, j, k).

The data should be read as a compression of a long exact sequence, or rather of all of them simultaneously. In the filtered case treated in section 60.2, the object D collects the cohomologies of the stages of the filtration, the object E collects the cohomologies of the successive layers, the map i is induced by the inclusion of one stage in the next, the map j is the passage to the layer, and k is the connecting homomorphism. Exactness at the three corners is precisely the exactness of every one of those long exact sequences. Of the two objects only E is meant to be looked at, since it is the approximation to the answer; D is the auxiliary object, and it is the auxiliary object that makes the approximation improvable.

Two of the three exactness conditions are spent constructing the next stage, and one is spent immediately, on the claim that d deserves its name.

Lemma 60.1.2: The Differential of an Exact Couple Squares to Zero

Let (D, E, i, j, k) be an exact couple. Then $d \circ d = 0$, so (E, d) is a differential object and its cohomology

$$H(E, d) = \frac{\ker d}{\operatorname{im} d}$$

is defined.

***Proof*:**
Expand the composite and regroup:

$$d \circ d = (j \circ k) \circ (j \circ k) = j \circ (k \circ j) \circ k$$

Exactness at the corner E gives $\operatorname{im} j = \ker k$, so every morphism factoring through j is annihilated by k, that is $k \circ j = 0$. Hence $d \circ d = j \circ 0 \circ k = 0$, as we sought to show.

Only exactness at E was used. The remaining two conditions are exactly what is needed to promote $H(E, d)$ from a bare cohomology object to the E-term of a new exact couple, and it is that promotion which makes the construction repeat. The new auxiliary object is the image of i, and the new maps are induced by the old ones.

60.1.3 Convention: Elements in an Abelian Category The constructions below are phrased with elements, in the style of a diagram chase. This is legitimate in any abelian category: by the Freyd-Mitchell theorem (theorem 55.1.15), a small abelian category admits a fully faithful exact embedding into R-Mod for some ring R, and a diagram whose exactness is verified in R-Mod is exact in $\mathcal{A}$ because the embedding reflects exactness. Every statement in this section may therefore be proved for modules and read off for a general $\mathcal{A}$. The standard sources of exact couples, filtered complexes and double complexes of modules or of sheaves, are in any case module-like.

Definition 60.1.4: Derived Couple

Let (D, E, i, j, k) be an exact couple with differential $d = j \circ k$. Its *derived couple* (D', E', i', j', k') consists of the objects

$$D' := \operatorname{im} i, \qquad E' := H(E, d) = \frac{\ker d}{\operatorname{im} d}$$


together with the morphisms

1. $i' := i|_{D'} \colon D' \to D'$, the restriction of i to its image;
2. $j' \colon D' \to E'$ defined by $j'(i(x)) := [\, j(x) \,]$ for $x \in D$;
3. $k' \colon E' \to D'$ defined by $k'([e]) := k(e)$ for $e \in \ker d$.

The name is older than, and unrelated to, the derived categories of chapter 57; it originates in Massey's work in algebraic topology. Three of the four items above require an argument before the definition is even meaningful: that i carries D' into itself, that j' is independent of the choice of preimage, and that k' both lands in D' and is independent of the representative cycle. Those checks and the exactness of the result are one theorem.

Theorem 60.1.5: The Derived Couple is an Exact Couple

Let (D, E, i, j, k) be an exact couple. Then the morphisms i', j' and k' of definition 60.1.4 are well defined, and the triangle



is an exact couple.

***Proof*:**
Step 1: The three maps are well defined. For i', note that $i(D') = i(i(D)) \subseteq i(D) = D'$, so restricting i to D' does indeed produce an endomorphism of D'.

For j', two things must be checked. First, $j(x)$ is a cycle for every $x \in D$: applying the differential gives $d(j(x)) = j(k(j(x))) = 0$, since $k \circ j = 0$ by exactness at E. So the class $[j(x)] \in E'$ makes sense. Second, the class does not depend on the choice of x. Suppose $i(x) = i(x')$. Then $x - x' \in \ker i = \mathrm{im} k$ by exactness at the target corner, say $x - x' = k(e)$ for some $e \in E$. Applying j gives

$$j(x) - j(x') = j(k(e)) = d(e) \in \mathrm{im} d$$

so $[j(x)] = [j(x')]$ in $E' = \ker d / \mathrm{im} d$.

For k', again two checks. First, k carries cycles into D': if $d(e) = 0$ then $j(k(e)) = 0$, so $k(e) \in \ker j = \mathrm{im} i = D'$ by exactness at the source corner. Second, the value is independent of the representative. If $e - e' = d(f) = j(k(f))$ for some $f \in E$, then

$$k(e) - k(e') = k(j(k(f))) = (k \circ j)(k(f)) = 0$$

again because $k \circ j = 0$. So k' is well defined.

Step 2: Exactness at the corner receiving i', that is $\mathrm{im} i' = \ker j'$. For the inclusion $\mathrm{im} i' \subseteq \ker j'$, take $y = i(x) \in D'$ and compute

$$j'(i'(y)) = j'(i(i(x))) = [\, j(i(x)) \,] = [0] = 0$$

the last equality because $\mathrm{im} i = \ker j$. For the reverse inclusion, let $y = i(x) \in D'$ satisfy $j'(y) = 0$, that is $[j(x)] = 0$, so $j(x) = d(e) = j(k(e))$ for some $e \in E$. Then $j(x - k(e)) = 0$, so $x - k(e) \in \ker j = \mathrm{im} i$, say $x - k(e) = i(z)$. Applying i and using $i \circ k = 0$ (exactness at the corner where k arrives) gives

$$y = i(x) = i(k(e)) + i(i(z)) = i(i(z)) = i'(i(z))$$

and $i(z) \in D'$, so $y \in \mathrm{im} i'$.

Step 3: Exactness at E', that is $\mathrm{im} j' = \ker k'$. For $\mathrm{im} j' \subseteq \ker k'$, take $y = i(x) \in D'$ and compute

$$k'(j'(y)) = k'([\, j(x) \,]) = k(j(x)) = 0$$

using $k \circ j = 0$. For the reverse inclusion, let $[e] \in E'$ satisfy $k'([e]) = k(e) = 0$. Then $e \in \ker k = \mathrm{im} j$, say $e = j(x)$ for some $x \in D$. The element $i(x)$ lies in D' and $j'(i(x)) = [j(x)] = [e]$, so $[e] \in \mathrm{im} j'$.

Step 4: Exactness at the corner receiving k', that is $\mathrm{im} k' = \ker i'$. For $\mathrm{im} k' \subseteq \ker i'$, take $[e] \in E'$; then $i'(k'([e])) = i(k(e)) = 0$ since $\mathrm{im} k = \ker i$. For the reverse inclusion, let $y = i(x) \in D'$ satisfy $i'(y) = 0$, that is $i(i(x)) = 0$. Then $i(x) \in \ker i = \mathrm{im} k$, say $i(x) = k(e)$ for some $e \in E$. This e is a cycle:

$$d(e) = j(k(e)) = j(i(x)) = 0$$

because $\mathrm{im} i = \ker j$. Hence $[e] \in E'$ and $k'([e]) = k(e) = i(x) = y$, so $y \in \mathrm{im} k'$.

All six inclusions hold, so the derived triangle is exact at each corner, completing the proof.

The theorem is the basis of the entire chapter. Because the derived couple is again an exact couple, the construction applies to it in turn, and iterating produces an infinite sequence of couples whose E-terms form a sequence of objects each of which is the cohomology of its predecessor. That sequence is the object the chapter is named for.

Definition 60.1.6: Spectral Sequence

Let $\mathcal{A}$ be an abelian category. A *spectral sequence* in $\mathcal{A}$ is a family $\{(E_r, d_r)\}_{r \geq r_0}$ of objects E_r of $\mathcal{A}$, each equipped with an endomorphism $d_r \colon E_r \to E_r$ satisfying $d_r \circ d_r = 0$, together with isomorphisms

$$E_{r+1} \cong H(E_r, d_r) = \frac{\ker d_r}{\mathrm{im} d_r}$$

for every $r \geq r_0$. The object E_r is the *r-th page*, d_r is the *r-th differential*, and r_0 is the *initial page*.

The spectral sequence is *bigraded* if each E_r carries a decomposition $E_r = \bigoplus_{p,q} E_r^{p,q}$ and each d_r is homogeneous of a fixed bidegree. Two conventions are in use. In the *homological* convention the pages are written $E^r_{p,q}$ and

$$d_r \colon E^r_{p,q} \to E^r_{p-r,\, q+r-1}$$

while in the *cohomological* convention they are written $E_r^{p,q}$ and

$$d_r \colon E_r^{p,q} \to E_r^{p+r,\, q-r+1}$$

Both differentials change the total degree $p + q$ by exactly one, downward in the homological convention and upward in the cohomological one. The two are exchanged by $E_r^{p,q} = E^r_{-p,-q}$.

The bidegrees are not a separate convention imposed on the definition; they are forced by the exact couple that generates the sequence, as the next result records. Every spectral sequence appearing in this book, and every one cited from it elsewhere in the series, arises from an exact couple in the manner described.

Theorem 60.1.7: The Spectral Sequence of an Exact Couple

Let $(D, E, i, j, k) = (D^1, E^1, i^{(1)}, j^{(1)}, k^{(1)})$ be an exact couple, and for $r \geq 1$ let $(D^{r+1}, E^{r+1}, i^{(r+1)}, j^{(r+1)}, k^{(r+1)})$ be the derived couple of the r-th one. Then $\{(E^r, d_r)\}_{r\geq 1}$, with $d_r = j^{(r)} \circ k^{(r)}$, is a spectral sequence, and $D^{r+1} = i^r(D)$ for every r.
Suppose in addition that D and E are bigraded and that i, j, k are homogeneous of bidegrees

$$\deg i = (1, -1), \qquad \deg j = (0, 0), \qquad \deg k = (-1, 0)$$

with the pages of the derived couples indexed by $D^{r+1}_{p,q} = i\big(D^r_{p-1,q+1}\big)$. Then

$$\deg i^{(r)} = (1, -1), \qquad \deg j^{(r)} = \big(-(r-1),\, r-1\big), \qquad \deg k^{(r)} = (-1, 0)$$

and consequently d_r is homogeneous of bidegree $(-r,\, r-1)$, so the sequence is bigraded in the homological convention of definition 60.1.6.

***Proof*:**
Step 1: The pages form a spectral sequence. By theorem 60.1.5 each derived couple is again an exact couple, so the construction may be iterated and every d_r satisfies $d_r \circ d_r = 0$ by lemma 60.1.2. By definition 60.1.4 the E-term of the derived couple is $E^{r+1} = H(E^r, d_r)$, which is the required isomorphism. The identity $D^{r+1} = i^r(D)$ follows by induction: it holds for $r = 0$ by convention, and if $D^r = i^{r-1}(D)$ then $D^{r+1} = i^{(r)}(D^r) = i(i^{r-1}(D)) = i^r(D)$, since $i^{(r)}$ is the restriction of i.

Step 2: The bidegree of $i^{(r)}$ and $k^{(r)}$. Each $i^{(r)}$ is a restriction of i to a subobject, so it is homogeneous of the same bidegree $(1, -1)$ for every r. Similarly $E^{r+1}_{p,q}$ is a subquotient of $E^r_{p,q}$ in the same bidegree, and $k^{(r+1)}$ is induced by $k^{(r)}$ on representatives, so $\deg k^{(r)} = (-1, 0)$ for every r by induction.

Step 3: The bidegree of $j^{(r)}$ shifts by $(-1, 1)$ at each stage. Fix r and suppose $\deg j^{(r)} = (a, b)$. By definition 60.1.4 the map $j^{(r+1)}$ is defined on an element of D^{r+1} written as $i(x)$ with $x \in D^r$, by $j^{(r+1)}(i(x)) = [\, j^{(r)}(x)\,]$. With the stated indexing, an element of $D^{r+1}_{p,q}$ is of the form $i(x)$ for $x \in D^r_{p-1,q+1}$, and $j^{(r)}(x)$ then lies in $E^r_{p-1+a,\, q+1+b}$. Hence $j^{(r+1)}$ carries $D^{r+1}_{p,q}$ into $E^{r+1}_{p+a-1,\, q+b+1}$, that is $\deg j^{(r+1)} = (a-1, b+1)$. Since $\deg j^{(1)} = (0, 0)$, induction gives $\deg j^{(r)} = (-(r-1), r-1)$.

Step 4: The bidegree of d_r. Combining Steps 2 and 3,

$$\deg d_r = \deg j^{(r)} + \deg k^{(r)} = \big(-(r-1),\, r-1\big) + (-1, 0) = (-r,\, r-1)$$

so $d_r \colon E^r_{p,q} \to E^r_{p-r,\, q+r-1}$, which is the homological convention of definition 60.1.6, completing the proof.

The bidegree computation is worth pausing over, because it explains what the higher pages are for. The differential d_1 moves one step in the filtration direction, d_2 moves two steps, and d_r moves r steps. Each derivation of the couple replaces D by $i(D)$, which is to say it discards the classes that

survive only one stage further and keeps those that survive r stages; the reach of the differential grows in step with that. A class killed by d_r and by no earlier differential encodes a gluing that spans exactly r layers of the filtration, information no single long exact sequence of the family can see. This is the precise sense in which the spectral sequence contains more than the collection of long exact sequences it was built from.

The simplest instance is a filtration with only two stages, where there is a single differential and the machine reduces to something already familiar.

Proposition 60.1.8: The Two-Step Filtration Recovers the Long Exact Sequence

Let $0 \to A_\bullet \xrightarrow{\iota} C_\bullet \xrightarrow{\pi} C_\bullet/A_\bullet \to 0$ be a short exact sequence of complexes in $\mathcal{A}$, and let $D = H_\bullet(A) \oplus H_\bullet(C)$ and $E = H_\bullet(A) \oplus H_\bullet(C/A)$ be the terms of the exact couple attached to the two-step filtration $0 \subseteq A_\bullet \subseteq C_\bullet$. Then:

1. the first page is $E^1 = H_\bullet(A) \oplus H_\bullet(C/A)$, with d_1 the connecting homomorphism $\partial\colon H_n(C/A) \to H_{n-1}(A)$ of theorem 56.1.20;
2. $E^2 = E^\infty$, that is $d_r = 0$ for all $r \geq 2$;
3. E^2 is the associated graded of $H_\bullet(C)$ for the induced two-step filtration, namely

$$E^2 \cong \operatorname{coker}\partial \oplus \ker \partial$$

with $\operatorname{coker}\partial$ the image of $H_n(A) \to H_n(C)$ and $\ker \partial$ its quotient.

***Proof*:**

Step 1: Identification of the first page. The filtration has stages $F_0 = A_\bullet$ and $F_1 = C_\bullet$, with $F_{-1} = 0$ and $F_p = C_\bullet$ for $p \geq 1$. The layers are $F_0/F_{-1} = A_\bullet$ and $F_1/F_0 = C_\bullet/A_\bullet$, and all other layers vanish. Since E^1 is by construction the sum of the cohomologies of the layers, $E^1 = H_\bullet(A) \oplus H_\bullet(C/A)$. The map k is the connecting homomorphism of the long exact sequence attached to the layer and j is the projection onto the layer, so on the summand $H_n(C/A)$ the composite $d_1 = j \circ k$ is the connecting homomorphism ∂ followed by the identification of $H_{n-1}(A)$ with the layer at filtration level zero, which is the identity. Hence $d_1 = \partial$ on that summand, and $d_1 = 0$ on $H_\bullet(A)$ because k vanishes there (its target is the cohomology of a layer at filtration level -1, which is zero).

Step 2: Degeneration after the second page. By theorem 60.1.7 the differential d_r has bidegree $(-r, r-1)$, so it decreases the filtration index by r. Only the filtration indices 0 and 1 carry nonzero terms, so for $r \geq 2$ the source and target of d_r cannot both be nonzero: a nonzero source at index 1 would have target at index $1 - r \leq -1$, and a source at index 0 would have target at index $-r < 0$. Hence $d_r = 0$ for $r \geq 2$ and the pages stabilize at E^2.

Step 3: Identification of the limit. By Step 1 the second page is the cohomology of $d_1 = \partial$, which is $\ker \partial$ in filtration index 1 and $\operatorname{coker}\partial$ in filtration index 0. The long exact sequence of theorem 56.1.20 reads

$$\cdots \to H_n(A) \xrightarrow{\iota_*} H_n(C) \xrightarrow{\pi_*} H_n(C/A) \xrightarrow{\partial} H_{n-1}(A) \to \cdots$$

Exactness at $H_n(C)$ gives $\mathrm{im}\iota_* = \ker \pi_*$, and exactness at $H_n(A)$ identifies $\mathrm{im}\iota_* \cong H_n(A)/\mathrm{im}\partial = \mathrm{coker}\partial$ in degree n; exactness at $H_n(C/A)$ identifies the quotient $H_n(C)/\mathrm{im}\iota_* \cong \mathrm{im}\pi_* = \ker \partial$. These two are precisely the graded pieces of $H_n(C)$ for the filtration induced by $A_\bullet \subseteq C_\bullet$, and they agree with the two summands of E^2 computed above, as we sought to show.

The proposition is the sanity check for the whole apparatus: in the one case where the answer is already known, the spectral sequence returns exactly the long exact sequence and nothing more. It also isolates what the machine does *not* do. The second page records $\ker \partial$ and $\mathrm{coker}\partial$ as separate graded pieces, but the extension

$$0 \to \mathrm{coker}\partial \to H_n(C) \to \ker \partial \to 0$$

is not part of the output. A spectral sequence delivers the associated graded of the answer, never the answer itself; recovering the latter requires solving the extension problems left behind. This is a permanent feature, not a defect of the two-step case, and it is stated in general in theorem 60.2.6.

A worked instance shows the bookkeeping.

Example 60.1.9: The Spectral Sequence of a Filtered Complex of Abelian Groups
Let $C_\bullet$ be the complex of abelian groups concentrated in degrees 1 and 0,

$$C_1 = \mathbb{Z} \xrightarrow{\cdot 2} C_0 = \mathbb{Z}$$

and let $A_\bullet \subseteq C_\bullet$ be the subcomplex with $A_1 = 0$ and $A_0 = 2\mathbb{Z}$. This is a subcomplex because $\partial(A_1) = 0 \subseteq A_0$. Filter by $F_0 = A_\bullet$ and $F_1 = C_\bullet$.

The cohomology of $C_\bullet$ itself is immediate: $H_1(C) = \ker(\cdot 2) = 0$ and $H_0(C) = \mathbb{Z}/2\mathbb{Z}$. The spectral sequence recomputes this from the two layers. The layer at level 0 is $A_\bullet$, with $H_0(A) = 2\mathbb{Z} \cong \mathbb{Z}$ and $H_1(A) = 0$. The layer at level 1 is $C_\bullet/A_\bullet$, which is $\mathbb{Z}$ in degree 1 and $\mathbb{Z}/2\mathbb{Z}$ in degree 0, with induced differential $1 \mapsto 2 \bmod 2 = 0$; so $H_1(C/A) = \mathbb{Z}$ and $H_0(C/A) = \mathbb{Z}/2\mathbb{Z}$. Indexing by $E^1_{p,q} = H_{p+q}(F_p/F_{p-1})$, the nonzero entries of the first page are

$$E^1_{0,0} = H_0(A) \cong \mathbb{Z}, \qquad E^1_{1,0} = H_1(C/A) \cong \mathbb{Z}, \qquad E^1_{1,-1} = H_0(C/A) \cong \mathbb{Z}/2\mathbb{Z}$$

The only possibly nonzero differential on this page is $d_1 \colon E^1_{1,0} \to E^1_{0,0}$, the connecting homomorphism $H_1(C/A) \to H_0(A)$. Compute it on the generator: the class of $1 \in (C/A)_1$ lifts to $1 \in C_1$, whose boundary is $2 \in C_0$, and 2 is the generator of $A_0 = 2\mathbb{Z}$. So d_1 sends a generator to a generator and is an isomorphism $\mathbb{Z} \to \mathbb{Z}$.

The second page therefore has $E^2_{1,0} = E^2_{0,0} = 0$, while $E^2_{1,-1} = \mathbb{Z}/2\mathbb{Z}$ survives untouched (the differential out of the spot $(1,-1)$ lands in $E^1_{0,-1} = H_{-1}(A) = 0$, and the one into it comes from $E^1_{2,-1} = 0$). By proposition 60.1.8 the pages stabilize here. Reading off total degrees: the diagonal $p+q=1$ is entirely zero, giving $H_1(C) = 0$, and the diagonal $p+q=0$ contains the single group $E^\infty_{1,-1} = \mathbb{Z}/2\mathbb{Z}$, giving $H_0(C) = \mathbb{Z}/2\mathbb{Z}$. Both agree with the direct computation, and because each diagonal contains at most one nonzero group there is no extension problem to solve.

Not every exact couple comes from a filtration. A single short exact sequence of complexes, read the other way round, produces one whose iteration does not terminate and whose limit is a statement about torsion.

Example 60.1.10: The Bockstein Exact Couple

Let p be a prime and $C_\bullet$ a complex of free abelian groups. Multiplication by p is injective on each C_n, so there is a short exact sequence of complexes

$$0 \to C_\bullet \xrightarrow{\cdot p} C_\bullet \to C_\bullet/pC_\bullet \to 0$$

Its long exact sequence in cohomology is exactly an exact couple, with

$$D = H_\bullet(C), \qquad E = H_\bullet(C/pC), \qquad i = (\cdot p), \qquad j = \text{reduction}, \qquad k = \partial$$

The differential $d_1 = j \circ k$ is the *Bockstein homomorphism*. By theorem 60.1.7 the r-th auxiliary object is $D^{r+1} = i^r(D) = p^r H_\bullet(C)$, so passing to the derived couple repeatedly divides out by higher and higher powers of p. When $H_\bullet(C)$ is finitely generated, an element of p-power torsion is annihilated by p^r for some r and therefore disappears from D^{r+1}, while a free generator survives every stage; the limit page is $\big(H_\bullet(C)/\text{torsion}\big) \otimes \mathbb{F}_p$.

The smallest case exhibits the mechanism. Take $C_1 = \mathbb{Z} \xrightarrow{\cdot p} C_0 = \mathbb{Z}$, so that $H_1(C) = 0$ and $H_0(C) = \mathbb{Z}/p\mathbb{Z}$ is pure torsion. Then $C_\bullet/pC_\bullet$ has zero differential, so $E^1 = H_\bullet(C/pC)$ is $\mathbb{F}_p$ in degrees 1 and 0. The connecting map k sends the degree-one generator to the class of 1 in $H_0(C) = \mathbb{Z}/p\mathbb{Z}$ (lift $\bar{1}$ to $1 \in C_1$, take the boundary p, and divide by p), and j sends that class to a generator of $H_0(C/pC) = \mathbb{F}_p$. So d_1 is an isomorphism $E^1_1 \to E^1_0$, giving $E^2 = 0 = E^\infty$. This matches the general description: $H_\bullet(C)$ is entirely torsion, so $(H_\bullet(C)/\text{torsion}) \otimes \mathbb{F}_p = 0$.

Exercise 60.1.1

1. Let (D, E, i, j, k) be an exact couple in which i is an isomorphism. Show that $E = 0$. Deduce that every page of the associated spectral sequence vanishes.
2. Let (D, E, i, j, k) be an exact couple. Show that $d = j \circ k$ vanishes if and only if $\ker i \subseteq \operatorname{im} i$. Then exhibit an exact couple with $d = 0$ but $k \neq 0$, so that a vanishing differential does not force the connecting map to vanish. (Take $D = \mathbb{Z}/4\mathbb{Z}$ and i multiplication by 2.)
3. Verify directly from definition 60.1.4 that the derived couple of the derived couple has $D'' = i^2(D)$, and that i'' is the restriction of i to $i^2(D)$, without appealing to theorem 60.1.7.
4. Let $C_\bullet$ be the complex $C_1 = \mathbb{Z} \xrightarrow{\cdot 6} C_0 = \mathbb{Z}$ filtered by $F_0 = A_\bullet$ with $A_1 = 0$, $A_0 = 3\mathbb{Z}$, and $F_1 = C_\bullet$. Compute the first page, the differential d_1, and the limit page, and check the answer against a direct computation of $H_\bullet(C)$.
5. In the Bockstein couple of example 60.1.10, take $C_\bullet$ to be $C_1 = \mathbb{Z} \xrightarrow{\cdot p^2} C_0 = \mathbb{Z}$. Show that $d_1 = 0$ but $d_2 \neq 0$, and that $E^3 = E^\infty = 0$. Explain how this illustrates the statement that d_r detects gluing spanning r stages.
6. Let $\mathcal{A}$ be an abelian category and (D, E, i, j, k) an exact couple with $E = 0$. Show that i is an isomorphism, so that the converse of exercise 60.1.1 (1) holds.

60.2 The Spectral Sequence of a Filtered Complex

The exact couples of section 60.1 were treated as abstract data. Their principal source is a complex equipped with a filtration, and this section carries out that construction, describes the pages explicitly enough to compute with, and proves the two theorems that make the output usable: a convergence theorem saying what the limit page computes, and a comparison theorem saying when two spectral sequences agree. These are the results cited from this chapter across the series, so both are proved in the generality in which they are used, for increasing filtrations of chain complexes and, in the restatement after them, for decreasing filtrations of cochain complexes.

Definition 60.2.1: Filtered Complex

Let $\mathcal{A}$ be an abelian category. A *filtered complex* is a chain complex $C_\bullet$ in $\mathcal{A}$ together with a family of subcomplexes $\{F_pC_\bullet\}_{p\in\mathbb{Z}}$ satisfying $F_pC_\bullet \subseteq F_{p+1}C_\bullet$ for every p. The filtration is called

1. *exhaustive* if $\bigcup_p F_pC_n = C_n$ for every n;
2. *bounded below* if for each n there is an $s(n)$ with $F_{s(n)}C_n = 0$;
3. *bounded* if it is bounded below and for each n there is a $t(n)$ with $F_{t(n)}C_n = C_n$.

The *associated graded* of the filtration is the complex $\mathrm{gr}_pC_\bullet = F_pC_\bullet/F_{p-1}C_\bullet$, and the filtration induced on homology is

$$F_pH_n(C) = \operatorname{im}\big(H_n(F_pC) \to H_n(C)\big)$$

Each inclusion $F_{p-1}C_\bullet \hookrightarrow F_pC_\bullet$ is a subcomplex inclusion in the sense of definition 56.1.7, so $\mathrm{gr}_pC_\bullet$ is again a complex.

Boundedness is the hypothesis that does the work later, and it is worth seeing why before it is used. In each fixed degree n a bounded filtration passes from 0 to all of C_n in finitely many steps, so any bookkeeping indexed by the filtration terminates in that degree after finitely many stages. Without some such condition the pages of the spectral sequence need not stabilize and the limit need not compute anything.

Every filtered complex produces an exact couple in one step: the long exact sequence of each pair $(F_pC_\bullet, F_{p-1}C_\bullet)$ gives the three maps, and the filtration index gives the bigrading.

Theorem 60.2.2: The Exact Couple of a Filtered Complex

Let $(C_\bullet, F_\bullet)$ be a filtered complex. Set

$$D^1_{p,q} = H_{p+q}(F_pC), \qquad E^1_{p,q} = H_{p+q}(\mathrm{gr}_pC)$$

and let i be induced by the inclusion $F_{p-1}C \hookrightarrow F_pC$, let j be induced by the projection $F_pC \to \mathrm{gr}_pC$, and let k be the connecting homomorphism of theorem 56.1.20 applied to

$$0 \to F_{p-1}C_\bullet \to F_pC_\bullet \to \mathrm{gr}_pC_\bullet \to 0$$

Then (D^1, E^1, i, j, k) is an exact couple with

$$\deg i = (1,-1), \qquad \deg j = (0,0), \qquad \deg k = (-1,0)$$

Consequently theorem 60.1.7 yields a spectral sequence with first page $E^1_{p,q} = H_{p+q}(\mathrm{gr}_pC)$ and differentials $d_r \colon E^r_{p,q} \to E^r_{p-r,\,q+r-1}$.
It is convenient to record one page earlier. Set

$$E^0_{p,q} := \mathrm{gr}_pC_{p+q}$$

with d_0 the differential induced by ∂ on the associated graded; then $E^1 = H(E^0, d_0)$, which is the identification just made, and the sequence is indexed from $r = 0$.

***Proof*:**
Step 1: Exactness. The displayed short exact sequence of complexes gives, by theorem 56.1.20, the long exact sequence

$$\cdots \to H_n(F_{p-1}C) \xrightarrow{i} H_n(F_pC) \xrightarrow{j} H_n(\mathrm{gr}_pC) \xrightarrow{k} H_{n-1}(F_{p-1}C) \to \cdots$$

Assembling these over all p and all n, the three maps i, j, k are defined on all of D^1 and E^1, and exactness of the triangle at each corner is exactness of the long exact sequences at the three types of term. This is exactly definition 60.1.1.

Step 2: Bidegrees. Write $n = p + q$. The map i carries $H_n(F_{p-1}C) = D^1_{p-1,q+1}$ to $H_n(F_pC) = D^1_{p,q}$, since $(p-1)+(q+1) = n$; hence $\deg i = (1,-1)$. The map j carries $H_n(F_pC) = D^1_{p,q}$ to $H_n(\mathrm{gr}_pC) = E^1_{p,q}$, so $\deg j = (0,0)$. The connecting map k carries $H_n(\mathrm{gr}_pC) = E^1_{p,q}$ to $H_{n-1}(F_{p-1}C) = D^1_{p-1,q}$, since $(p-1)+q = n-1$; hence $\deg k = (-1,0)$. These are the hypotheses of theorem 60.1.7, which then gives the spectral sequence and the stated bidegree of d_r, completing the proof.

The construction is quick, but the pages it produces are described only implicitly, as iterated subquotients of the first one. Computing with them, and proving anything about the limit, requires a description of E^r in terms of the original complex. The right notion is that of a chain which is a cycle only up to a given depth in the filtration.

Definition 60.2.3: Approximate Cycles

Let $(C_\bullet, F_\bullet)$ be a filtered complex and write $n = p+q$. For $r \geq 0$ set

$$Z^r_{p,q} = \{\, x \in F_pC_n \;:\; \partial x \in F_{p-r}C_{n-1} \,\}$$

the object of chains at filtration level p whose boundary drops r levels. By convention $Z^{-1}_{p,q} = F_pC_n$.

The objects $Z^r_{p,q}$ decrease in r, and their intersection over all r is, when the filtration is bounded below, the cycles of $C_\bullet$ lying in F_pC_n. An element of $Z^r_{p,q}$ is a class that survives to the r-th page: it is a cycle in the associated graded to accuracy r, and its failure to be a cycle of $C_\bullet$ is what d_r records.

Proposition 60.2.4: Explicit Description of the Pages

Let $(C_\bullet, F_\bullet)$ be a filtered complex and let $\{(E^r, d_r)\}$ be the spectral sequence of theorem 60.2.2. For every $r \geq 0$ there are isomorphisms

$$E^r_{p,q} \cong \frac{Z^r_{p,q}}{Z^{r-1}_{p-1,q+1} + \partial Z^{r-1}_{p+r-1,\,q-r+2}}$$

under which the differential d_r is induced by the boundary map ∂ of $C_\bullet$.

***Proof*:**
Write $\mathcal{E}^r_{p,q}$ for the right-hand side and $n = p+q$. The proof is an induction on r; the inductive statement is that $E^r \cong \mathcal{E}^r$ compatibly with the differentials, the differential on $\mathcal{E}^r$ being the one induced by ∂.

Step 1: The map induced by ∂ is a differential on $\mathcal{E}^r$. If $x \in Z^r_{p,q}$ then $\partial x \in F_{p-r}C_{n-1}$ and $\partial(\partial x) = 0 \in F_{p-2r}C_{n-2}$, so $\partial x \in Z^r_{p-r,\,q+r-1}$. Hence ∂ carries $Z^r_{p,q}$ into $Z^r_{p-r,q+r-1}$, and it carries the denominator at (p,q) into the denominator at $(p-r, q+r-1)$: the summand $Z^{r-1}_{p-1,q+1}$ is sent to $\partial Z^{r-1}_{p-1,q+1}$, which is literally the second summand of the target denominator, and the summand $\partial Z^{r-1}_{p+r-1,q-r+2}$ is sent to zero because $\partial\partial = 0$. So ∂ induces a map $\mathcal{E}^r_{p,q} \to \mathcal{E}^r_{p-r,q+r-1}$ squaring to zero.

Step 2: The base case $r = 0$. With the convention $Z^{-1}_{p,q} = F_pC_n$, the numerator is $Z^0_{p,q} = F_pC_n$ and the denominator is $F_{p-1}C_n + \partial F_{p-1}C_{n+1} = F_{p-1}C_n$, since $\partial F_{p-1}C_{n+1} \subseteq F_{p-1}C_n$. So $\mathcal{E}^0_{p,q} = F_pC_n / F_{p-1}C_n = \mathrm{gr}_pC_n$, which is $E^0_{p,q}$, and the induced differential is the one ∂ induces on the associated graded. Taking homology recovers $E^1_{p,q} = H_n(\mathrm{gr}_pC)$, matching theorem 60.2.2; the differential $d_1 = j \circ k$ is by construction the connecting homomorphism, which on representatives is ∂.

Step 3: The inductive step. Assume $E^r \cong \mathcal{E}^r$ compatibly with differentials. Then $E^{r+1} = H(E^r, d_r) \cong H(\mathcal{E}^r, \partial)$, so it suffices to identify the latter with $\mathcal{E}^{r+1}$. Abbreviate the denominator $D = Z^{r-1}_{p-1,q+1} + \partial Z^{r-1}_{p+r-1,q-r+2}$.

First the kernel. Let $x \in Z^r_{p,q}$ represent a class killed by d_r, so that ∂x lies in the denominator at $(p-r, q+r-1)$, namely $\partial x = z + \partial w$ with $z \in Z^{r-1}_{p-r-1,q+r}$ and $w \in Z^{r-1}_{p-1,q+1}$. Then $x - w$ still lies in F_pC_n, because $w \in F_{p-1}C_n$, and

$$\partial(x-w) = \partial x - \partial w = z \in F_{p-r-1}C_{n-1}$$

so $x - w \in Z^{r+1}_{p,q}$. Since $w \in D$, the classes of x and $x - w$ agree in $\mathcal{E}^r_{p,q}$. Hence $\ker d_r = (Z^{r+1}_{p,q} + D)/D$.

Next the image. A class in $\mathcal{E}^r_{p+r,q-r+1}$ is represented by some $y \in Z^r_{p+r,q-r+1}$, and d_r sends it to the class of ∂y. Hence $\mathrm{im} d_r = (\partial Z^r_{p+r,q-r+1} + D)/D$, and therefore

$$H(\mathcal{E}^r, \partial)_{p,q} = \frac{Z^{r+1}_{p,q} + D}{\partial Z^r_{p+r,q-r+1} + D} \cong \frac{Z^{r+1}_{p,q}}{Z^{r+1}_{p,q} \cap \left(\partial Z^r_{p+r,q-r+1} + D\right)}$$

the isomorphism being the second isomorphism theorem.

It remains to show that the intersection appearing there equals $Z^r_{p-1,q+1} + \partial Z^r_{p+r,q-r+1}$, which is exactly the denominator of $\mathcal{E}^{r+1}_{p,q}$. For the inclusion $\supseteq$, note $Z^r_{p-1,q+1} \subseteq Z^{r+1}_{p,q}$ (an element lies in $F_{p-1} \subseteq F_p$ and its boundary lies in F_{p-1-r}) and $Z^r_{p-1,q+1} \subseteq Z^{r-1}_{p-1,q+1} \subseteq D$; while $\partial Z^r_{p+r,q-r+1} \subseteq Z^{r+1}_{p,q}$ because such a boundary lies in F_pC_n and is itself a cycle. For the inclusion $\subseteq$, let $x \in Z^{r+1}_{p,q}$ be written as $x = \partial y + z + \partial w$ with $y \in Z^r_{p+r,q-r+1}$, $z \in Z^{r-1}_{p-1,q+1}$ and $w \in Z^{r-1}_{p+r-1,q-r+2}$. Then $z = x - \partial y - \partial w$ lies in $F_{p-1}C_n$ and $\partial z = \partial x \in F_{p-r-1}C_{n-1}$, so $z \in Z^r_{p-1,q+1}$. Moreover $w \in Z^{r-1}_{p+r-1,q-r+2}$ satisfies $w \in F_{p+r-1} \subseteq F_{p+r}$ and $\partial w \in F_{(p+r-1)-(r-1)} = F_p$, so $w \in Z^r_{p+r,q-r+1}$ and hence $\partial w \in \partial Z^r_{p+r,q-r+1}$. Therefore $x = z + \partial(y+w) \in Z^r_{p-1,q+1} + \partial Z^r_{p+r,q-r+1}$, as required.

Substituting gives $H(\mathcal{E}^r, \partial)_{p,q} \cong \mathcal{E}^{r+1}_{p,q}$. Write $\varphi_r \colon \mathcal{E}^r \to E^r$ for the isomorphism of the inductive statement. Composing with $E^{r+1} = H(E^r, d_r) \cong H(\mathcal{E}^r, \partial)$ gives φ_{r+1}, and since every isomorphism in this step is induced by the identity on representatives, φ_{r+1} sends the class of $x \in Z^{r+1}_{p,q}$ to the class of $\varphi_r[x]$ in $H(E^r, d_r)$.

Step 4: The isomorphism φ_r carries the map induced by ∂ to d_r. For $r = 0$ this is Step 2, so let $r \geq 1$. Each E^r is then a subquotient of E^1. For $e \in E^1$ write $\langle e \rangle_r \in E^r$ for its class whenever that class is defined: $\langle e \rangle_1 = e$, and $\langle e \rangle_{s+1}$ is the class of $\langle e \rangle_s$ in $H(E^s, d_s)$ when $d_s \langle e \rangle_s = 0$. For $x \in Z^r_{p,q}$ let $\bar{x}$ be its image in $\mathrm{gr}_p C_n$, a cycle because $\partial x \in F_{p-r}C_{n-1} \subseteq F_{p-1}C_{n-1}$. Step 3 at $r = 0$ gives $\varphi_1[x] = [\bar{x}]$, and the description of φ_{r+1} above then gives $\varphi_r[x] = \langle [\bar{x}] \rangle_r$ by induction. Iterating definition 60.1.4, whose maps are $k'([e]) = k(e)$ and $j'(i(y)) = [j(y)]$, gives

$$k^{(r)} \langle e \rangle_r = k(e), \qquad j^{(r)}\big(i^{r-1}(y)\big) = \langle j(y) \rangle_r \quad (y \in D^1)$$

where the class on the right is defined because at each stage $j^{(s)}$ takes values in $\ker k^{(s)} \subseteq \ker d_s$. The connecting homomorphism k of theorem 56.1.20 lifts the cycle $\bar{x}$ to x and applies ∂, so $k[\bar{x}]$ is the class of ∂x in $H_{n-1}(F_{p-1}C)$. Since ∂x is a cycle lying in $F_{p-r}C_{n-1}$, that class is $i^{r-1}(y)$ for y the class of ∂x in $H_{n-1}(F_{p-r}C)$, and $j(y)$ is the class of the image of ∂x in $\mathrm{gr}_{p-r}C_{n-1}$. Since $\partial x \in Z^r_{p-r,q+r-1}$ by Step 1, this gives

$$d_r\, \varphi_r[x] = j^{(r)} k^{(r)} \langle [\bar{x}] \rangle_r = j^{(r)}\big(i^{r-1}(y)\big) = \langle j(y) \rangle_r = \varphi_r[\partial x]$$

which closes the induction and completes the proof.

The formula repays reading slowly, because it makes the interpretive claim of section 60.1 precise. The numerator at page r consists of the chains whose boundary drops r filtration levels, and the denominator discards those already accounted for one level down together with the boundaries of chains that drop $r-1$ levels. Passing from page r to page $r+1$ tightens the requirement on the boundary by one level. A class that survives to page r and dies there is one that could be corrected to a cycle modulo F_{p-r} but not modulo F_{p-r-1}, which is the precise sense in which d_r detects gluing across r layers.

With the pages described, the limit can be identified. This is the theorem the rest of the series cites from this section.

Definition 60.2.5: Convergence of a Spectral Sequence

A bigraded spectral sequence $\{(E^r, d_r)\}$ *degenerates* at the spot (p,q) if the differentials into and out of that spot vanish for all sufficiently large r; the common value of $E^r_{p,q}$ for large r is then written $E^\infty_{p,q}$. The spectral sequence *converges* to a graded object $H_\bullet$ equipped with a filtration $F_\bullet H_\bullet$, written

$$E^1_{p,q} \implies H_{p+q}$$

if it degenerates at every spot, the filtration $F_\bullet H_n$ is bounded for each n (that is $F_pH_n = 0$ for p small and $F_pH_n = H_n$ for p large), and $E^\infty_{p,q} \cong F_pH_{p+q}/F_{p-1}H_{p+q}$ for all p,q. The boundedness clause is what lets a vanishing family of graded pieces be read back as a vanishing abutment; without it the graded pieces constrain only the successive quotients.

Theorem 60.2.6: Convergence for a Bounded Filtration

Let $(C_\bullet, F_\bullet)$ be a filtered complex whose filtration is bounded in the sense of definition 60.2.1. Then the spectral sequence of theorem 60.2.2 converges to $H_\bullet(C)$: it degenerates at every spot, and

$$E^\infty_{p,q} \cong \frac{F_pH_{p+q}(C)}{F_{p-1}H_{p+q}(C)}$$

for the filtration $F_pH_n(C) = \operatorname{im}(H_n(F_pC) \to H_n(C))$ of definition 60.2.1. Moreover that filtration of $H_n(C)$ is itself bounded, so $H_n(C)$ has a finite filtration whose graded pieces are the terms of the limit page on the diagonal $p+q=n$.

***Proof*:**
Fix n and let $s(m), t(m)$ be the bounds of definition 60.2.1 in degree m.

Step 1: Degeneration. Fix a spot (p,q) with $p+q=n$. The differential out of it lands in $E^r_{p-r,q+r-1}$, a subquotient of $E^1_{p-r,q+r-1} = H_{n-1}(\mathrm{gr}_{p-r}C)$. Once r is large enough that $p-r \le s(n-1)$, the complex $\mathrm{gr}_{p-r}C$ vanishes in degree $n-1$, so the target is zero. The differential into (p,q) comes from $E^r_{p+r,q-r+1}$, a subquotient of $H_{n+1}(\mathrm{gr}_{p+r}C)$; once $p+r-1 \ge t(n+1)$ one has $F_{p+r-1}C_{n+1} = F_{p+r}C_{n+1} = C_{n+1}$, so $\mathrm{gr}_{p+r}C$ vanishes in degree $n+1$ and the source is zero. Both hold for all large r, so $E^{r+1}_{p,q} = E^r_{p,q}$ eventually and $E^\infty_{p,q}$ is defined.

Step 2: The large-r value of the explicit description. Take r large enough that $F_{p-r}C_{n-1} = 0$ and $F_{p+r-1}C_{n+1} = C_{n+1}$, which is possible by boundedness. Write $Z_n = \ker(\partial\colon C_n \to C_{n-1})$

and $B_n = \operatorname{im}(\partial\colon C_{n+1} \to C_n)$. Then:

1. $Z^r_{p,q} = \{x \in F_pC_n : \partial x \in F_{p-r}C_{n-1} = 0\} = Z_n \cap F_pC_n$;
2. $Z^{r-1}_{p-1,q+1} = \{x \in F_{p-1}C_n : \partial x \in F_{p-r}C_{n-1} = 0\} = Z_n \cap F_{p-1}C_n$;
3. $\partial Z^{r-1}_{p+r-1,q-r+2} = \partial\{y \in F_{p+r-1}C_{n+1} : \partial y \in F_pC_n\} = \partial(C_{n+1}) \cap F_pC_n = B_n \cap F_pC_n$, using $F_{p+r-1}C_{n+1} = C_{n+1}$.

Substituting into proposition 60.2.4,

$$E^\infty_{p,q} \cong \frac{Z_n \cap F_pC_n}{(Z_n \cap F_{p-1}C_n) + (B_n \cap F_pC_n)}$$

Step 3: The same object is the graded piece of homology. By definition $F_pH_n(C)$ is the image of $H_n(F_pC)$ in $H_n(C)$, that is

$$F_pH_n(C) = \frac{(Z_n \cap F_pC_n) + B_n}{B_n} \cong \frac{Z_n \cap F_pC_n}{B_n \cap F_pC_n}$$

the isomorphism being the second isomorphism theorem. Taking the quotient by $F_{p-1}H_n(C)$, which under this identification is the image of $Z_n \cap F_{p-1}C_n$, gives

$$\frac{F_pH_n(C)}{F_{p-1}H_n(C)} \cong \frac{Z_n \cap F_pC_n}{(Z_n \cap F_{p-1}C_n) + (B_n \cap F_pC_n)}$$

which is the object computed in Step 2. Hence $E^\infty_{p,q} \cong \operatorname{gr}_pH_n(C)$.

Both sides were computed as subquotients of F_pC_n by the same formula, and the isomorphism between them is induced by the identity on representatives. A morphism of filtered complexes carries representatives to representatives and preserves every object appearing in that formula, so the identification is natural in $(C_\bullet, F_\bullet)$; this is what theorem 60.2.7 uses when it compares the two filtrations of homology.

Step 4: The induced filtration is bounded. If $p \le s(n)$ then $F_pC_n = 0$, so $H_n(F_pC) = 0$ and $F_pH_n(C) = 0$. If $p \ge t(n)$ then $F_pC_n = C_n$; taking p also at least $t(n+1)$ makes $F_pC_{n+1} = C_{n+1}$ as well, so every cycle and every boundary of degree n already lies at filtration level p and $F_pH_n(C) = H_n(C)$. Hence the filtration of $H_n(C)$ passes from 0 to everything in finitely many steps, completing the proof.

Two features of the statement deserve emphasis, both of them permanent. The limit page computes the *associated graded* of $H_n(C)$, not $H_n(C)$ itself; recovering the latter means solving the extension problems between successive graded pieces, exactly as in the two-step case of proposition 60.1.8. And convergence is a theorem about the filtration, not about the complex: boundedness is what forces the pages to stabilize, and without it the limit page can fail to compute anything.

The second theorem of the section makes a spectral sequence a tool for identification as well as calculation: a morphism of filtered complexes that is an isomorphism on any single page is an isomorphism on the abutment.

Theorem 60.2.7: Comparison Theorem

Let $f\colon (C_\bullet, F_\bullet) \to (C'_\bullet, F'_\bullet)$ be a morphism of filtered complexes, that is a chain map with $f(F_pC_\bullet) \subseteq F'_pC'_\bullet$, and suppose both filtrations are bounded. Then f induces a morphism of spectral sequences $f^r\colon E^r_{p,q} \to E'^r_{p,q}$ commuting with the differentials, and if f^{r_0} is an isomorphism for some $r_0 \geq 0$, then:

1. f^r is an isomorphism for every $r \geq r_0$, and hence so is f^∞;
2. $f_*\colon H_n(C) \to H_n(C')$ is an isomorphism for every n.

***Proof*:**

Step 1: Functoriality. On the zeroth page f induces f^0 on gr_pC_{p+q} directly, and the identification $E^1 = H(E^0, d_0)$ of theorem 60.2.2 is natural in the filtered complex, so the case $r_0 = 0$ reduces to $r_0 = 1$. For the remaining pages: because f preserves the filtration, it carries the short exact sequences of theorem 60.2.2 for C to those for C', and the connecting homomorphism of theorem 56.1.20 is natural. So f induces a morphism of exact couples, and the construction of the derived couple in definition 60.1.4 is built from i, j, k alone and is therefore natural in the couple. Hence f induces f^r on every page, commuting with d_r.

Step 2: Isomorphism on all later pages. Suppose f^r is an isomorphism. Since f^r commutes with the differentials, it carries $\ker d_r$ isomorphically onto $\ker d'_r$ and $\mathrm{im} d_r$ isomorphically onto $\mathrm{im} d'_r$, so the induced map on the quotients is an isomorphism. That induced map is f^{r+1}, so the claim follows by induction from r_0.

Step 3: Isomorphism on the limit page. Both filtrations are bounded, so by Step 1 of the proof of theorem 60.2.6 each spot degenerates: there is an R depending on (p, q) with $E^r_{p,q} = E^\infty_{p,q}$ and $E'^r_{p,q} = E'^\infty_{p,q}$ for $r \geq R$. Taking $r \geq \max(R, r_0)$ and applying Step 2 gives $f^\infty_{p,q}$ an isomorphism.

Step 4: Isomorphism on homology. Fix n. By theorem 60.2.6 the filtrations $F_\bullet H_n(C)$ and $F'_\bullet H_n(C')$ are finite, and f_* respects them. Proceed by induction up the filtration. The bottom stage is zero on both sides. If f_* is an isomorphism $F_{p-1}H_n(C) \to F'_{p-1}H_n(C')$, then in the commutative diagram of short exact sequences

$$\begin{array}{ccccccccc} 0 & \longrightarrow & F_{p-1}H_n(C) & \longrightarrow & F_pH_n(C) & \longrightarrow & E^\infty_{p,n-p} & \longrightarrow & 0 \\ & & \downarrow & & \downarrow & & \downarrow & & \\ 0 & \longrightarrow & F'_{p-1}H_n(C') & \longrightarrow & F'_pH_n(C') & \longrightarrow & E'^\infty_{p,n-p} & \longrightarrow & 0 \end{array}$$

the outer vertical maps are isomorphisms, the left one by the inductive hypothesis and the right one by Step 3. Each row is already a five-term exact sequence, so lemma 56.1.22 applies directly, with the outer maps $0 \to 0$ trivially epi and mono, and forces the middle map to be an isomorphism. Since the filtration is finite and exhausts $H_n(C)$, finitely many steps give that $f_*\colon H_n(C) \to H_n(C')$ is an isomorphism, completing the proof.

The applications elsewhere in the series are stated for cochain complexes with decreasing filtrations,

so the translation is recorded explicitly rather than left to the reader.

Corollary 60.2.8: Convergence for a Decreasing Filtration of a Cochain Complex

Let $(C^\bullet, d)$ be a cochain complex with a decreasing filtration $C^\bullet = F^0C^\bullet \supseteq F^1C^\bullet \supseteq \cdots$ compatible with d, that is $d(F^pC^n) \subseteq F^pC^{n+1}$, and suppose the filtration is exhaustive and bounded, so that for each n there is a P with $F^PC^n = 0$. Then there is a spectral sequence with

$$E_0^{p,q} = \frac{F^pC^{p+q}}{F^{p+1}C^{p+q}}, \qquad d_r \colon E_r^{p,q} \to E_r^{p+r,\,q-r+1}$$

each page the cohomology of the one before it, converging to $H^{p+q}(C)$:

$$E_1^{p,q} \implies H^{p+q}(C), \qquad E_\infty^{p,q} \cong \mathrm{gr}_F^p H^{p+q}(C) = \frac{F^pH^{p+q}(C)}{F^{p+1}H^{p+q}(C)}$$

where $F^pH^n(C) = \mathrm{im}\big(H^n(F^pC^\bullet) \to H^n(C^\bullet)\big)$.

***Proof*:**
Set $C_n = C^{-n}$ and $F_pC_\bullet = F^{-p}C^\bullet$. The differential d raises cochain degree by one and therefore lowers chain degree by one, so $(C_\bullet, F_\bullet)$ is a filtered chain complex in the sense of definition 60.2.1: the filtration is increasing because $F^\bullet$ is decreasing, it is exhaustive because $F^\bullet$ is, and it is bounded because for each n there is a P with $F^PC^n = 0$, giving $F_{-P}C_{-n} = 0$, while $F^0C^n = C^n$ gives $F_0C_{-n} = C_{-n}$.

Theorem 60.2.6 applies and gives a convergent spectral sequence with $E^0_{p,q} = \mathrm{gr}_pC_{p+q}$ and d_r of bidegree $(-r, r-1)$. Re-indexing by $E_r^{p,q} = E^r_{-p,-q}$, as in definition 60.1.6, turns the bidegree of d_r into $(r, -r+1)$ and turns the graded piece $\mathrm{gr}_{-p}H_{-p-q}(C_\bullet)$ into $\mathrm{gr}_F^pH^{p+q}(C^\bullet)$, which is the statement, as we sought to show.

The same re-indexing carries every other result of this section across, and it is worth saying so once rather than hedging at each use, since section 60.3 onward works exclusively with cochain complexes.

Corollary 60.2.9: The Cochain Form of the Section

Let $\mathcal{T}$ denote the translation $C_n = C^{-n}$, $F_p = F^{-p}$, $E_r^{p,q} = E^r_{-p,-q}$ of corollary 60.2.8. Under $\mathcal{T}$:

1. Theorem 60.2.7 holds for morphisms of cochain complexes with bounded decreasing filtrations: a morphism inducing an isomorphism on E_{r_0} for some r_0 induces one on E_∞ and on $H^\bullet$.
2. Definition 60.2.3, proposition 60.2.4 and definition 60.2.5 hold with the *bigrading* negated, the page index r unchanged. Explicitly $Z_r^{p,q} = \{x \in F^pC^{p+q} : dx \in F^{p+r}C^{p+q+1}\}$ and

$$E_r^{p,q} \cong \frac{Z_r^{p,q}}{Z_{r-1}^{p+1,q-1} + d\,Z_{r-1}^{p-r+1,\,q+r-2}}$$

***Proof*:**
$\mathcal{T}$ is an isomorphism between the category of cochain complexes with bounded decreasing filtrations and the category of chain complexes with bounded increasing filtrations, carrying morphisms to morphisms and the spectral sequence of one to the spectral sequence of the other, by the computation in the proof of corollary 60.2.8. A statement proved for one is therefore proved for the other; no hypothesis in theorem 60.2.7 or proposition 60.2.4 refers to the direction of the grading beyond boundedness, which $\mathcal{T}$ preserves, completing the proof.

A cohomological spectral sequence is *first-quadrant* if $E_r^{p,q} = 0$ for every $r \geq 2$ whenever $p < 0$ or $q < 0$. In such a sequence the corner spots $(p, 0)$ and $(0, q)$ each meet the abutment in only one way. The two results below use only that shape and convergence, so they apply to the first-quadrant spectral sequences among those of corollary 60.2.8, of a double complex, of section 60.4 and of section 60.5.

Proposition 60.2.10: Edge Morphisms

Let $E_2^{p,q} \Rightarrow H^{p+q}$ be a first-quadrant cohomological spectral sequence converging in the sense of definition 60.2.5, in the cochain form of corollary 60.2.9(2). Then for every $p, q \geq 0$ there are canonical morphisms

$$E_2^{p,0} \longrightarrow H^p, \qquad H^q \longrightarrow E_2^{0,q}$$

called the *edge morphisms*, given respectively by the composites

$$E_2^{p,0} \twoheadrightarrow E_\infty^{p,0} = F^pH^p \hookrightarrow H^p, \qquad H^q \twoheadrightarrow H^q/F^1H^q = E_\infty^{0,q} \hookrightarrow E_2^{0,q}$$

They are natural in the spectral sequence.

***Proof*:**
Step 1: The two composites are defined. Fix p. Every differential out of $(p, 0)$ lands in $(p+r, 1-r)$, which has negative second index for $r \geq 2$, and every differential into it comes from $(p-r, r-1)$, which has negative first index once $r > p$. So $E_\infty^{p,0}$ is a quotient of $E_2^{p,0}$, the successive pages being obtained by killing images. The filtration of H^p is bounded, so $F^aH^p = 0$ for large a, and its graded pieces $E_\infty^{a,p-a}$ vanish for $a > p$, the second index being negative. Hence $F^{p+1}H^p = 0$, and $E_\infty^{p,0} = F^pH^p/F^{p+1}H^p = F^pH^p$, a subobject of H^p. Composing gives the first morphism.

Dually, every differential into $(0, q)$ comes from $(-r, q + r - 1)$, which has negative first index, so $E_\infty^{0,q}$ is a subobject of $E_2^{0,q}$, obtained by taking successive kernels. The filtration of H^q is bounded, so $F^aH^q = H^q$ for small a, and its graded pieces $E_\infty^{a,q-a}$ vanish for $a < 0$. Hence $F^0H^q = H^q$, and $E_\infty^{0,q} = F^0H^q/F^1H^q = H^q/F^1H^q$. Composing gives the second morphism.

Step 2: Naturality. A morphism of spectral sequences compatible with the abutments respects the pages, hence the successive kernels and images defining E_∞, and respects the filtration of the abutment. Each edge morphism is built only from those data, so the two squares commute, completing the proof.

In total degree one the abutment has only the two graded pieces $E_\infty^{1,0}$ and $E_\infty^{0,1}$, and the only differential that changes either of them, or the bottom piece $E_\infty^{2,0}$ of H^2, is $d_2 \colon E_2^{0,1} \to E_2^{2,0}$.

Proposition 60.2.11: The Five-Term Exact Sequence of a First-Quadrant Spectral Sequence

Let $E_2^{p,q} \Rightarrow H^{p+q}$ be a first-quadrant cohomological spectral sequence, so that $E_r^{p,q} = 0$ for $r \geq 2$ whenever $p < 0$ or $q < 0$, converging to a filtered graded object $H^\bullet$ in the sense of definition 60.2.5, in the cochain form of corollary 60.2.9(2). Then there is an exact sequence

$$0 \to E_2^{1,0} \to H^1 \to E_2^{0,1} \xrightarrow{d_2} E_2^{2,0} \to H^2$$

natural in the spectral sequence: a morphism of first-quadrant spectral sequences compatible with the abutment induces a morphism of these five-term sequences.

***Proof*:**
The spectral sequence is first-quadrant, so the filtration of H^n has graded pieces $E_\infty^{p,q}$ with $p+q=n$ and $0 \leq p \leq n$.

Step 1: Degree one. The diagonal $p+q=1$ contains the two spots $(1,0)$ and $(0,1)$. For every $r \geq 2$ the differentials touching $(1,0)$ run to $(1+r, 1-r)$ and from $(1-r, r-1)$, both outside the first quadrant, so $E_\infty^{1,0} = E_2^{1,0}$. The differentials arriving at $(0,1)$ come from $(-r, r)$ and are zero, and those leaving it run to $(r, 2-r)$, outside the first quadrant for $r \geq 3$. So $E_\infty^{0,1} = \ker\big(d_2 \colon E_2^{0,1} \to E_2^{2,0}\big)$. The filtration of H^1 therefore gives a short exact sequence

$$0 \to E_\infty^{1,0} \to H^1 \to E_\infty^{0,1} \to 0$$

that is $0 \to E_2^{1,0} \to H^1 \to \ker d_2 \to 0$. The first map here is the edge morphism $E_2^{1,0} \to H^1$ of proposition 60.2.10, and the second, followed by the inclusion of $\ker d_2$ into $E_2^{0,1}$, is the edge morphism $H^1 \to E_2^{0,1}$, both by construction.

Step 2: Splicing. Substituting $E_\infty^{0,1} = \ker d_2$ turns the short exact sequence into exactness of

$$0 \to E_2^{1,0} \to H^1 \to E_2^{0,1} \xrightarrow{d_2} E_2^{2,0}$$

the last map being d_2 and exactness at $E_2^{0,1}$ being the statement that the image of H^1 is exactly $\ker d_2$.

Step 3: The final term. It remains to show exactness at $E_2^{2,0}$, that is that the kernel of $E_2^{2,0} \to H^2$ is the image of d_2. The filtration of H^2 has $E_\infty^{2,0}$ as its bottom graded piece, and the map $E_2^{2,0} \to H^2$ is the composite $E_2^{2,0} \twoheadrightarrow E_\infty^{2,0} \hookrightarrow H^2$. The second map is a monomorphism, so the kernel of the composite is the kernel of the first, which is the image of the only differential arriving at $(2,0)$, namely $d_2 \colon E_2^{0,1} \to E_2^{2,0}$. Hence the sequence is exact there.

Step 4: Naturality. Let $\{E_r\} \to \{E'_r\}$ be a morphism of first-quadrant spectral sequences compatible with the abutments. Every object in the five-term sequence was constructed from data the morphism respects. The terms $E_2^{1,0}$, $E_2^{0,1}$, $E_2^{2,0}$ receive the induced map on the second page. The map d_2 is respected because a morphism of spectral sequences commutes with the differentials. Each $E_\infty^{p,q}$ receives the induced map because it is a subquotient of $E_2^{p,q}$ cut out by

those same differentials. And H^1, H^2 receive the given map on abutments, which by hypothesis is compatible with the filtrations and hence with the identifications $E_\infty^{p,q} \cong F^pH^{p+q}/F^{p+1}H^{p+q}$. Each of the four maps in the sequence was defined from exactly these, so all four squares commute, completing the proof.

A first application of the machinery, and the one that recurs in section 60.4, is the crudest filtration a complex carries: truncate it.

Example 60.2.12: The Stupid Filtration of a Cochain Complex

Let $(C^\bullet, d)$ be a cochain complex concentrated in degrees $0 \le n \le N$, and define the *stupid filtration* (the *filtration bête*) by

$$F^pC^n = \begin{cases} C^n & n \ge p \\ 0 & n < p \end{cases}$$

This is a decreasing filtration compatible with d, since d raises degree, and it is exhaustive and bounded because $F^0C^\bullet = C^\bullet$ and $F^{N+1}C^\bullet = 0$. The graded pieces are $\mathrm{gr}_F^pC^n = C^n$ if $n = p$ and 0 otherwise, so the zeroth page has a single nonzero entry in each column,

$$E_0^{p,q} = \begin{cases} C^p & q = 0 \\ 0 & q \ne 0 \end{cases}$$

The differential d_0 has bidegree $(0, 1)$ and so runs between entries with q differing by one; every such pair has a zero member, so $d_0 = 0$ and $E_1 = E_0$. The differential d_1 has bidegree $(1, 0)$ and is the map induced by d, namely $d\colon C^p \to C^{p+1}$. Hence

$$E_2^{p,q} = \begin{cases} H^p(C^\bullet) & q = 0 \\ 0 & q \ne 0 \end{cases}$$

and every later differential has target or source zero, so $E_2 = E_\infty$. By corollary 60.2.8 the sequence converges to $H^{p+q}(C^\bullet)$, and indeed the single surviving entry on the diagonal $p+q = n$ is $H^n(C^\bullet)$, with no extension problem. The stupid filtration therefore returns the cohomology of the complex and nothing more, which is the correct answer and a useful check on the indexing conventions. It becomes informative only when the entries C^p are themselves replaced by objects with cohomology of their own, which is what section 60.4 does.

Cochain complexes from topology and geometry often carry a product, as singular cochains do under the cup product and differential forms under the wedge product, and a filtration may be compatible with it.

Theorem 60.2.13: Multiplicative Structure on the Spectral Sequence of a Filtered DG Algebra

Let R be a commutative ring and (A, d) a *differential graded* (DG) R-algebra: a graded R-algebra $A = \bigoplus_n A^n$, associative with unit $1 \in A^0$, together with an R-linear map d of degree $+1$ satisfying $d \circ d = 0$ and

$$d(xy) = (dx)\,y + (-1)^m x\,(dy) \qquad (x \in A^m)$$

Let $A = F^0A \supseteq F^1A \supseteq \cdots$ be a decreasing filtration by subcomplexes which is multiplicative, $F^pA \cdot F^{p'}A \subseteq F^{p+p'}A$, and bounded in each degree: for each n there is a P with $F^PA^n = 0$, as happens when $F^pA^n = 0$ for all $p > n$. Let $\{(E_r, d_r)\}_{r\geq 0}$ be the spectral sequence of corollary 60.2.8. Then:

1. Each page carries an associative, unital, R-bilinear product
$$E_r^{p,q} \otimes_R E_r^{p',q'} \to E_r^{p+p',\,q+q'}$$
induced by the product of A on representatives, with unit the class of 1 in $E_r^{0,0}$.
2. Each differential is a derivation: for $x \in E_r^{p,q}$ and $y \in E_r$,
$$d_r(xy) = d_r(x)\,y + (-1)^{p+q}\,x\,d_r(y)$$
3. The isomorphism $E_{r+1} \cong H(E_r, d_r)$ is an isomorphism of bigraded algebras, where $H(E_r, d_r)$ carries the product induced by that of E_r.
4. The filtration $F^pH(A) = \operatorname{im}\big(H(F^pA) \to H(A)\big)$ makes $H(A)$ a filtered algebra, $F^pH(A) \cdot F^{p'}H(A) \subseteq F^{p+p'}H(A)$, and the isomorphism $E_\infty^{p,q} \cong F^pH^{p+q}(A)/F^{p+1}H^{p+q}(A)$ of corollary 60.2.8 is an isomorphism of bigraded algebras $E_\infty \cong \mathrm{gr}H(A)$, where E_∞ carries the product of E_r for large r.
5. If E_{r_0} is graded commutative, that is $xy = (-1)^{(p+q)(p'+q')}\,yx$ for $x \in E_{r_0}^{p,q}$ and $y \in E_{r_0}^{p',q'}$, then so are E_∞ and E_r for every $r \geq r_0$. This holds with $r_0 = 0$ if A is graded commutative, and with $r_0 = 1$ if A is graded commutative up to a homotopy preserving the filtration: an R-bilinear map h with $h(A^m \times A^{m'}) \subseteq A^{m+m'-1}$, $h(F^pA \times F^{p'}A) \subseteq F^{p+p'}A$ and
$$xy - (-1)^{mm'}\,yx = d\,h(x,y) + h(dx,y) + (-1)^m h(x,dy) \qquad (x \in A^m,\ y \in A^{m'})$$

***Proof*:**
Weibel [101] 5.4.8 gives (1) to (4) for chain complexes, checking the Leibniz rule on the zeroth page and appealing to 5.2.13 for the later pages.[a]

Set $F^pA = A$ for $p < 0$. With $p_+ = \max(p, 0)$, the inclusion $F^pA \cdot F^{p'}A \subseteq F^{p+p'}A$ then holds for all integers p and p', because $F^pA \cdot F^{p'}A = F^{p_+}A \cdot F^{p'_+}A \subseteq F^{p_+ + p'_+}A \subseteq F^{p+p'}A$. The same holds for h in (5). Write $n = p + q$ and $n' = p' + q'$, and for $s \geq -1$ set

$$Z_s^{p,q} = \{\, x \in F^pA^n \ :\ dx \in F^{p+s}A^{n+1} \,\}$$

which is all of F^pA^n for $s \le 0$ because d preserves the filtration, in agreement with the convention $Z_{-1}^{p,q} = F^pA^n$ of definition 60.2.3. Set

$$D_r^{p,q} = Z_{r-1}^{p+1,\,q-1} + d\,Z_{r-1}^{p-r+1,\,q+r-2}$$

whose second summand is $d\big(F^{p-r+1}A^{n-1}\big) \cap F^pA^n$. By proposition 60.2.4 in the cochain form of corollary 60.2.9, $E_r^{p,q} = Z_r^{p,q}/D_r^{p,q}$ for every $r \ge 0$, with $d_r[x] = [dx]$, and by Step 3 of the proof of proposition 60.2.4 the isomorphism $E_{r+1} \cong H(E_r, d_r)$ sends the class of $x \in Z_{r+1}^{p,q}$ to the class of $[x]$. Fix $x \in Z_r^{p,q}$ and $y \in Z_r^{p',q'}$.

Step 1: Products of approximate cycles. The product xy lies in $F^{p+p'}A^{n+n'}$, and

$$d(xy) = (dx)\,y + (-1)^n x\,(dy) \in F^{p+r}A \cdot F^{p'}A + F^pA \cdot F^{p'+r}A \subseteq F^{p+p'+r}A$$

so $xy \in Z_r^{p+p',\,q+q'}$.

Step 2: $D_r^{p,q} \cdot y$ and $x \cdot D_r^{p',q'}$ lie in $D_r^{p+p',q+q'}$. Let $z \in Z_{r-1}^{p+1,q-1}$. Then $zy \in F^{p+p'+1}A$, and $d(zy) = (dz)\,y + (-1)^n z\,(dy)$ lies in $F^{p+r}A \cdot F^{p'}A + F^{p+1}A \cdot F^{p'+r}A \subseteq F^{p+p'+r}A$, so $zy \in Z_{r-1}^{p+p'+1,\,q+q'-1}$. Next let $w \in F^{p-r+1}A^{n-1}$ with $dw \in F^pA^n$, so that dw is a general element of the second summand of $D_r^{p,q}$. The Leibniz rule gives

$$(dw)\,y = d(wy) + (-1)^n w\,(dy)$$

The element wy lies in $F^{p+p'-r+1}A^{n+n'-1}$, and $d(wy) = (dw)\,y - (-1)^n w\,(dy)$ lies in $F^{p+p'}A + F^{p+p'+1}A = F^{p+p'}A$, so $d(wy) \in d\,Z_{r-1}^{p+p'-r+1,\,q+q'+r-2}$. The element $w\,(dy)$ lies in $F^{p-r+1}A \cdot F^{p'+r}A \subseteq F^{p+p'+1}A$, and $d\big(w\,(dy)\big) = (dw)(dy)$ lies in $F^{p+p'+r}A$, so $w\,(dy) \in Z_{r-1}^{p+p'+1,\,q+q'-1}$. Hence $D_r^{p,q} \cdot y \subseteq D_r^{p+p',q+q'}$. The same estimates, applied to xz for $z \in Z_{r-1}^{p'+1,q'-1}$ and to the identity $x\,(dw) = (-1)^n\big(d(xw) - (dx)\,w\big)$ for $w \in F^{p'-r+1}A^{n'-1}$ with $dw \in F^{p'}A^{n'}$, give $x \cdot D_r^{p',q'} \subseteq D_r^{p+p',q+q'}$.

Step 3: Statements (1) and (2). By Steps 1 and 2, $(x + D_r^{p,q})(y + D_r^{p',q'}) \subseteq xy + D_r^{p+p',q+q'}$, so $[x][y] = [xy]$ is a well defined R-bilinear map $E_r^{p,q} \times E_r^{p',q'} \to E_r^{p+p',q+q'}$. It is associative because the product of A is. The unit 1 lies in $Z_r^{0,0}$, since $1 \in F^0A^0$ and $d1 = d(1 \cdot 1) = 2\,d1$ forces $d1 = 0$, and its class is a two-sided unit. This proves (1). For (2), $dx \in Z_r^{p+r,q-r+1}$ and $dy \in Z_r^{p'+r,q'-r+1}$, and

$$d_r\big([x][y]\big) = [d(xy)] = [(dx)\,y] + (-1)^n[x\,(dy)] = d_r[x]\,[y] + (-1)^{p+q}[x]\,d_r[y]$$

Step 4: Statement (3). By (2) the product of two d_r-cycles is a d_r-cycle, and for a d_r-cycle a of total degree m and any $c \in E_r$,

$$a\,d_r(c) = (-1)^m d_r(ac), \qquad d_r(c)\,a = d_r(ca)$$

So $\ker d_r$ is a bigraded subalgebra containing the unit, $\operatorname{im} d_r$ is a two-sided ideal of it, and $H(E_r, d_r)$ inherits the product $[a][b] = [ab]$. The isomorphism $E_{r+1} \to H(E_r, d_r)$ sends the class of $x \in Z_{r+1}^{p,q}$ to the class of $[x]$, so it sends the class of xy to the class of $[xy] = [x][y]$, which is

the product of the images. It also sends the unit to the unit, so it is an isomorphism of bigraded algebras.

Step 5: Statement (4). Write Z^n and B^n for the cocycles and coboundaries of A in degree n. The argument of Step 4, applied to d on A, shows that $Z = \bigoplus_n Z^n$ is a subalgebra and $B = \bigoplus_n B^n$ a two-sided ideal of it, so $H(A) = Z/B$ is a graded algebra. A class lies in $F^pH^n(A)$ exactly when it has a representative in $Z^n \cap F^pA^n$. Classes in $F^pH(A)$ and $F^{p'}H(A)$ therefore have representatives $\alpha \in Z \cap F^pA$ and $\beta \in Z \cap F^{p'}A$, and their product has the representative $\alpha\beta \in Z \cap F^{p+p'}A$. This proves $F^pH(A) \cdot F^{p'}H(A) \subseteq F^{p+p'}H(A)$, and $F^0H(A) = H(A)$ because $F^0A = A$. Consequently

$$\big(a + F^{p+1}H(A)\big)\big(b + F^{p'+1}H(A)\big) = ab + F^{p+p'+1}H(A) \qquad \big(a \in F^pH(A),\ b \in F^{p'}H(A)\big)$$

is a well defined bigraded product on $\mathrm{gr}H(A)$.

Fix (p, q) and take r with $F^{p+r}A^{n+1} = 0$ and $p - r + 1 \leq 0$, which holds for all large r by boundedness. Then $F^{p-r+1}A^{n-1} = A^{n-1}$, and the explicit description reads

$$Z_r^{p,q} = Z^n \cap F^pA^n, \qquad Z_{r-1}^{p+1,q-1} = Z^n \cap F^{p+1}A^n, \qquad d\,Z_{r-1}^{p-r+1,\,q+r-2} = B^n \cap F^pA^n$$

These do not depend on r, so for all such r the page $E_r^{p,q}$ is one fixed quotient of $Z^n \cap F^pA^n$, and that quotient is $E_\infty^{p,q}$. Take r this large for the three spots (p, q), (p', q') and $(p+p', q+q')$ at once. The product of E_r then sends the classes of cocycles $x \in Z^n \cap F^pA^n$ and $y \in Z^{n'} \cap F^{p'}A^{n'}$ to the class of xy, independently of r, and this is the product of E_∞. By Steps 2 and 3 of the proof of theorem 60.2.6, carried to cochains as in corollary 60.2.8, the isomorphism $E_\infty^{p,q} \cong \mathrm{gr}^pH^n(A)$ sends the class of x to $[x] + F^{p+1}H^n(A)$. It therefore sends the class of xy to $[xy] + F^{p+p'+1}H(A)$, which is the product of $[x] + F^{p+1}H(A)$ and $[y] + F^{p'+1}H(A)$ in $\mathrm{gr}H(A)$. It also sends 1 to 1, so $E_\infty \cong \mathrm{gr}H(A)$ as bigraded algebras.

Step 6: Statement (5). If E_r is graded commutative then so is $H(E_r, d_r)$, whose product is computed on representatives, and so is E_{r+1} by (3). Induction from r_0 covers every E_r with $r \geq r_0$, and E_∞ follows because its product is that of E_r for large r. If A is graded commutative then so is E_0, by (1). Suppose now that h is as in (5) and $r \geq 1$. Put $v = h(x, y)$ and $u = h(dx, y) + (-1)^n h(x, dy)$, so that $xy - (-1)^{nn'}yx = dv + u$. The element u lies in $F^{p+p'+r}A \subseteq F^{p+p'+1}A$, and $du = d(xy) - (-1)^{nn'}d(yx)$ lies in $F^{p+p'+r}A$ by Step 1, so $u \in Z_{r-1}^{p+p'+1,\,q+q'-1}$. The element v lies in $F^{p+p'}A^{n+n'-1} \subseteq F^{p+p'-r+1}A^{n+n'-1}$, and $dv = xy - (-1)^{nn'}yx - u$ lies in $F^{p+p'}A$, so $dv \in d\,Z_{r-1}^{p+p'-r+1,\,q+q'+r-2}$. Hence $xy - (-1)^{nn'}yx \in D_r^{p+p',q+q'}$, that is $[x][y] = (-1)^{nn'}[y][x]$ in E_r, and in particular E_1 is graded commutative, completing the proof.

[a] That appeal is not formal. The differential d_{r+1} is not determined by (E_r, d_r), so the Leibniz rule for d_r implies nothing about d_{r+1}. Step 3 below verifies it on every page from representatives in A.

Statement (2) is the one computations use: a derivation is determined by its values on a set of algebra generators, so on a page generated by a few classes the whole differential is fixed by its values on those classes.

Exercise 60.2.1

1. Let $(C_\bullet, F_\bullet)$ be a filtered complex whose filtration has exactly three nonzero stages, $0 = F_{-1} \subseteq F_0 \subseteq F_1 \subseteq F_2 = C_\bullet$. Show that $d_r = 0$ for $r \geq 3$, so that $E^3 = E^\infty$. Generalize to a filtration with N stages.

2. Show that the filtration induced on $H_n(C)$ in definition 60.2.1 is increasing, and that a morphism of filtered complexes $f\colon (C_\bullet, F_\bullet) \to (C'_\bullet, F'_\bullet)$ satisfies $f_*\big(F_pH_n(C)\big) \subseteq F'_pH_n(C')$. (This is the compatibility used in Step 4 of the proof of theorem 60.2.7.)

3. A spectral sequence *degenerates at* E^r if $d_s = 0$ for all $s \geq r$. Show that if the spectral sequence of a bounded filtered complex degenerates at E^1, then for every n the object $H_n(C)$ has a finite filtration with graded pieces $H_n(\mathrm{gr}_pC)$. Show by example that this does not force $H_n(C) \cong \bigoplus_p H_n(\mathrm{gr}_pC)$.

4. Verify proposition 60.2.4 directly at $r = 1$ by computing both sides for the filtered complex of example 60.1.9, and confirm that the differential induced by ∂ is the map computed there.

5. Let $f\colon (C_\bullet, F_\bullet) \to (C'_\bullet, F'_\bullet)$ be a morphism of bounded filtered complexes which is an isomorphism on E^2 but not on E^1. Show that f_* is still an isomorphism on homology, and construct such an f with $E^1 \neq E'^1$.

60.3 The Two Spectral Sequences of a Double Complex

A double complex carries two filtrations of its total complex, one by columns and one by rows, and section 60.2 converts each into a spectral sequence. Both converge to the homology of the same total complex, and that coincidence is the source of most of the identifications homological algebra makes: whenever one filtration degenerates for an easy reason and the other computes something of interest, the two are forced to agree. Section 56.5 promised this machinery twice, once for the cohomology of double complexes and once for the balancing of Tor and Ext, and this section delivers both.

Throughout, $A = \{A_{p,q}\}$ is a double complex in the sense of definition 56.5.1, with horizontal differential $d^h\colon A_{p,q} \to A_{p-1,q}$ and vertical differential $\delta^v\colon A_{p,q} \to A_{p,q-1}$ satisfying $d^hd^h = 0$, $\delta^v\delta^v = 0$ and $d^h\delta^v + \delta^vd^h = 0$. The total complex is $\mathrm{Tot}(A)_n = \bigoplus_{p+q=n} A_{p,q}$ with differential $d = d^h + \delta^v$, as in proposition 56.5.2; anticommutativity is exactly what makes $d \circ d = 0$. Write

$$H^h_p(A)_\bullet, \qquad H^v_q(A)_\bullet$$

for the homology of the rows and of the columns respectively, each of which is again a complex under the differential the other direction induces.

Definition 60.3.1: The Column and Row Filtrations

Let A be a double complex. The *column filtration* and the *row filtration* of $\mathrm{Tot}(A)$ are

$$^{\mathrm{I}}F_p\mathrm{Tot}(A)_n = \bigoplus_{\substack{p'+q'=n \\ p' \leq p}} A_{p',q'}, \qquad ^{\mathrm{II}}F_p\mathrm{Tot}(A)_n = \bigoplus_{\substack{p'+q'=n \\ q' \leq p}} A_{p',q'}$$

The double complex is *first-quadrant* if $A_{p,q} = 0$ whenever $p < 0$ or $q < 0$.

Both are filtrations by subcomplexes, and for the reason that each differential moves in only one of

the two directions: d^h lowers p' and leaves q' unchanged, while δ^v lowers q' and leaves p' unchanged. So d carries ${}^{\mathrm{I}}F_p$ into itself, and likewise for ${}^{\mathrm{II}}F_p$. The two differ only in which coordinate is being watched, which is why the same total complex acquires two different, and generally inequivalent, approximations to its homology.

Theorem 60.3.2: The Two Spectral Sequences of a Double Complex

Let A be a first-quadrant double complex. Then the column and row filtrations of $\mathrm{Tot}(A)$ give two spectral sequences, both converging to $H_\bullet(\mathrm{Tot}(A))$, with second pages

$$ {}^{\mathrm{I}}E^2_{p,q} = H^h_p\big(H^v_q(A)\big) \implies H_{p+q}(\mathrm{Tot}(A)) $$

$$ {}^{\mathrm{II}}E^2_{p,q} = H^v_p\big(H^h_q(A)\big) \implies H_{p+q}(\mathrm{Tot}(A)) $$

***Proof*:**

Step 1: Boundedness. Fix n. Since A is first-quadrant, $A_{p',q'} = 0$ unless $0 \le p' \le n$ on the diagonal $p'+q' = n$. Hence ${}^{\mathrm{I}}F_{-1}\mathrm{Tot}(A)_n = 0$ and ${}^{\mathrm{I}}F_n\mathrm{Tot}(A)_n = \mathrm{Tot}(A)_n$, so the column filtration is bounded in the sense of definition 60.2.1; the same argument applies to the row filtration. Theorem 60.2.6 therefore applies to each and gives convergence to $H_\bullet(\mathrm{Tot}(A))$ once the pages are identified.

Step 2: The zeroth and first pages of the column filtration. By definition 60.2.1 the graded piece is

$$ \mathrm{gr}_p\mathrm{Tot}(A)_n = \frac{{}^{\mathrm{I}}F_p\mathrm{Tot}(A)_n}{{}^{\mathrm{I}}F_{p-1}\mathrm{Tot}(A)_n} = A_{p,\,n-p} $$

so ${}^{\mathrm{I}}E^0_{p,q} = A_{p,q}$. The induced differential is the part of $d = d^h + \delta^v$ that preserves the filtration index p. The summand d^h lowers p, so it vanishes on the graded piece; the summand δ^v preserves p. Hence $d^0 = \delta^v$ and

$$ {}^{\mathrm{I}}E^1_{p,q} = H_q\big(A_{p,\bullet},\, \delta^v\big) = H^v_q(A)_p $$

the homology of the p-th column.

Step 3: The second page of the column filtration. By theorem 60.2.2 the differential d^1 has bidegree $(-1, 0)$, so it runs ${}^{\mathrm{I}}E^1_{p,q} \to {}^{\mathrm{I}}E^1_{p-1,q}$; by proposition 60.2.4 it is induced by the differential of $\mathrm{Tot}(A)$ on representatives. A representative of a class in ${}^{\mathrm{I}}E^1_{p,q}$ is an element of $A_{p,q}$ killed by δ^v, and applying $d = d^h + \delta^v$ to it gives d^h of it, an element of $A_{p-1,q}$. So d^1 is the map induced by d^h on vertical homology, and

$$ {}^{\mathrm{I}}E^2_{p,q} = H_p\big(H^v_q(A)_\bullet,\, d^h\big) = H^h_p\big(H^v_q(A)\big) $$

Step 4: The row filtration. The argument is identical with the two coordinates exchanged. The graded piece of the row filtration at index p in total degree n is $A_{n-p,\,p}$, so ${}^{\mathrm{II}}E^0_{p,q} = A_{q,p}$, and the differential preserving the index p is now d^h. Hence ${}^{\mathrm{II}}E^1_{p,q} = H_q(A_{\bullet,p}, d^h) = H^h_q(A)_p$, and the next differential is induced by δ^v, giving ${}^{\mathrm{II}}E^2_{p,q} = H^v_p(H^h_q(A))$. Both converge to the homology of the same total complex by Step 1, completing the proof.

The two sequences are not related by any map; they are two different routes to one answer, and the content of the theorem is that the answer is the same. The standard way to exploit this is to arrange for one of them to collapse. A double complex whose columns are exact except in one spot, for instance, has a first page concentrated in a single row, and then every differential from the second page onward has a zero source or a zero target.

Lemma 60.3.3: Collapse Along a Single Row

Let $\{(E^r, d_r)\}$ be a spectral sequence with $E^2_{p,q} = 0$ for all $q \neq 0$. Then $E^2 = E^\infty$, and if the sequence converges to $H_\bullet$ then $H_n \cong E^2_{n,0}$ for every n.

***Proof*:**
The differential d_r has bidegree $(-r, r-1)$ by theorem 60.1.7. For $r \geq 2$ the differential out of the spot $(p, 0)$ lands in $(p-r,\, r-1)$, which has second index $r-1 \geq 1$ and so vanishes; the differential into $(p, 0)$ comes from $(p+r,\, 1-r)$, which has negative second index and so vanishes. Every other spot is already zero. Hence $d_r = 0$ for all $r \geq 2$ and $E^2 = E^\infty$.

For the abutment, the diagonal $p + q = n$ of the limit page contains the single nonzero group $E^\infty_{n,0}$. By definition 60.2.5 the filtration of H_n is bounded and has these as graded pieces; a bounded filtration whose graded pieces vanish outside one step has exactly one nonzero step, so $H_n \cong E^\infty_{n,0} = E^2_{n,0}$, as we sought to show.

Both results are used in section 60.4 and section 60.5 for cochain double complexes, whose differentials raise indices. As with corollary 60.2.9, the translation is recorded once.

Corollary 60.3.4: The Cochain Form of the Double-Complex Sequences

Let $A^{\bullet,\bullet}$ be a cochain double complex concentrated in non-negative bidegrees, with differentials raising the two indices. Then the column and row filtrations of $\mathrm{Tot}(A)$ give two spectral sequences converging to $H^{p+q}(\mathrm{Tot}(A))$, with second pages

$$ {}^{\mathrm{I}}E_2^{p,q} = H_h^p\big(H_v^q(A)\big), \qquad {}^{\mathrm{II}}E_2^{p,q} = H_v^p\big(H_h^q(A)\big) $$

and lemma 60.3.3 holds in the form: if $E_2^{p,q} = 0$ for all $q \neq 0$ then $E_2 = E_\infty$ and $H^n \cong E_2^{n,0}$; symmetrically if $E_2^{p,q} = 0$ for all $p \neq 0$ then $H^n \cong E_2^{0,n}$.

***Proof*:**
Apply the translation $\mathcal{T}$ of corollary 60.2.9 in both indices, setting $A_{p,q} = A^{-p,-q}$. This turns a cochain double complex concentrated in non-negative bidegrees into a chain double complex concentrated in non-positive ones, which is bounded on diagonals in the sense of exercise 60.3.1 (5); theorem 60.3.2 and lemma 60.3.3 apply to it, and negating every index returns the displayed statements. The column form of the collapse is exercise 60.3.1 (4), translated the same way, completing the proof.

The lemma turns theorem 60.3.2 into an identification technique, and the standard application is the one section 56.5 deferred: that Tor may be computed by resolving either variable.

Corollary 60.3.5: Balancing Tor

Let R be a ring, M a right R-module and N a left R-module, and let $P_\bullet \to M$ and $Q_\bullet \to N$ be projective resolutions. Then

$$H_n\big(P_\bullet \otimes_R N\big) \cong H_n\big(\mathrm{Tot}(P_\bullet \otimes_R Q_\bullet)\big) \cong H_n\big(M \otimes_R Q_\bullet\big)$$

for every n. In particular $\mathrm{Tor}_n^R(M,N)$ may be computed by resolving either variable, recovering the Tor half of theorem 56.5.8 as the degenerate case of theorem 60.3.2.

***Proof*:**
Let $A_{p,q} = P_p \otimes_R Q_q$, with horizontal differential induced by that of $P_\bullet$ and vertical differential induced by that of $Q_\bullet$, the latter twisted by the sign $(-1)^p$ so that the two anticommute as definition 56.5.1 requires. Both resolutions are supported in non-negative degrees, so A is first-quadrant and theorem 60.3.2 applies.

Step 1: The column filtration. Each P_p is projective, hence a direct summand of a free module, hence flat, so the functor $P_p \otimes_R -$ is exact. Therefore it commutes with homology and

$${}^{\mathrm{I}}E^1_{p,q} = H_q\big(P_p \otimes_R Q_\bullet\big) \cong P_p \otimes_R H_q(Q_\bullet)$$

Since $Q_\bullet \to N$ is a resolution, $H_q(Q_\bullet)$ is N for $q = 0$ and zero otherwise. So the first page is concentrated in the row $q = 0$, where it is $P_p \otimes_R N$, and the second page is

$${}^{\mathrm{I}}E^2_{p,0} = H_p\big(P_\bullet \otimes_R N\big)$$

with ${}^{\mathrm{I}}E^2_{p,q} = 0$ for $q \neq 0$. By lemma 60.3.3, $H_n(\mathrm{Tot}(A)) \cong H_n(P_\bullet \otimes_R N)$.

Step 2: The row filtration. Symmetrically, each Q_q is flat, so ${}^{\mathrm{II}}E^1_{p,q} = H_q(P_\bullet \otimes_R Q_p) \cong H_q(P_\bullet) \otimes_R Q_p$, which is $M \otimes_R Q_p$ for $q = 0$ and zero otherwise. Hence ${}^{\mathrm{II}}E^2_{p,0} = H_p(M \otimes_R Q_\bullet)$ with the other rows zero, and lemma 60.3.3 gives $H_n(\mathrm{Tot}(A)) \cong H_n(M \otimes_R Q_\bullet)$.

Both computations describe the homology of the same total complex, so the two are isomorphic, completing the proof.

The argument is worth contrasting with the one given in section 56.5. There the comparison was made by hand, through an explicit quasi-isomorphism between the total complex and each of its edges. Here it is a two-line consequence of a general theorem, and the same two lines apply verbatim to Ext, to group cohomology, and to any other derived functor of a bifunctor. That is the characteristic economy of the method: the work moves once into theorem 60.2.6 and is then reused without repetition.

Exercise 60.3.1

1. Let A be a first-quadrant double complex all of whose columns are exact. Show that $\mathrm{Tot}(A)$ is acyclic. Deduce proposition 56.5.4 for first-quadrant double complexes.

2. State and prove the analogue of corollary 60.3.5 for Ext, using a projective resolution of M and an injective resolution of N. Identify which functor plays the role of $P_p \otimes_R -$ in Step 1, and which exactness property replaces flatness.

3. Let A be the first-quadrant double complex with $A_{0,0} = A_{1,0} = \mathbb{Z}$, $A_{0,1} = A_{1,1} = \mathbb{Z}$, horizontal differentials the identity, and vertical differentials the identity, with the sign twist making it anticommute. Compute both spectral sequences and $H_\bullet(\mathrm{Tot}(A))$, and check that the two agree.

4. Show that a spectral sequence with $E^2_{p,q} = 0$ for all $p \neq 0$ also collapses, and that $H_n \cong E^2_{0,n}$. (No quadrant hypothesis is needed.) (This is the column analogue of lemma 60.3.3.)

5. The first-quadrant hypothesis in theorem 60.3.2 is used in exactly one place. Identify it, and show that the theorem still holds for any double complex that is *bounded on diagonals*, meaning that for each n only finitely many $A_{p,q}$ with $p+q=n$ are nonzero. Then show that a double complex with $A_{p,q} \neq 0$ for every $p, q \in \mathbb{Z}$ fails this condition, so that theorem 60.2.6 does not apply to either filtration.

60.4 Hypercohomology

The derived functors of section 56.3 take an object as input. Many constructions present a complex instead: a complex of sheaves in place of a single sheaf, a complex of modules in place of a module. For a left exact F and a bounded-below complex $C^\bullet$, this section resolves $C^\bullet$ by injectives in two directions at once. The resolution is a double complex, the Cartan-Eilenberg resolution, and the cohomology of the total complex of F applied to it is the *hypercohomology* $\mathbb{R}^n F(C^\bullet)$. The two filtrations of that double complex give two spectral sequences converging to $\mathbb{R}^n F(C^\bullet)$. The first starts from the derived functors $R^q F(C^p)$ of the terms of $C^\bullet$, and the second from the derived functors $R^p F(H^q(C^\bullet))$ of its cohomology objects. Hypercohomology is the cohomology of the total derived functor of section 57.3, by proposition 60.4.9.

Definition 60.4.1: Cartan-Eilenberg Resolution

Let $\mathcal{A}$ be an abelian category with enough injectives and $C^\bullet$ a cochain complex in $\mathcal{A}$ bounded below. A *Cartan-Eilenberg resolution* of $C^\bullet$ is a double complex $I^{\bullet,\bullet}$ of injective objects, with $I^{p,q} = 0$ for $q < 0$ and with the column $I^{p,\bullet}$ zero whenever $C^p = 0$, together with an augmentation $C^p \to I^{p,0}$ for each p, these forming a morphism of complexes $C^\bullet \to I^{\bullet,0}$, such that for every p the induced augmentations make each of

$$I^{p,\bullet}, \qquad B^p\big(I^{\bullet,\bullet}\big), \qquad Z^p\big(I^{\bullet,\bullet}\big), \qquad H^p\big(I^{\bullet,\bullet}\big)$$

an injective resolution of C^p, of $B^p(C^\bullet)$, of $Z^p(C^\bullet)$ and of $H^p(C^\bullet)$ respectively, where B^p, Z^p and H^p are taken in the first (horizontal) direction.

The conditions on B^p, Z^p and H^p tie the resolution to the cohomology of $C^\bullet$. A double complex whose columns are injective resolutions of the C^p need satisfy only the first condition, and its horizontal cohomology need not resolve the objects $H^p(C^\bullet)$. The vanishing conditions make a Cartan-Eilenberg resolution bounded below in both directions: if $C^p = 0$ for $p < p_0$, then $I^{p,q} = 0$ unless $p \geq p_0$ and $q \geq 0$ (the condition of Weibel [101] 5.7.1).

Theorem 60.4.2: Existence of Cartan-Eilenberg Resolutions

Every bounded-below cochain complex in an abelian category with enough injectives admits a Cartan-Eilenberg resolution.

***Proof*:**

Step 1: Choices. For each p, use that $\mathcal{A}$ has enough injectives (definition 56.2.3) to choose injective resolutions

$$B^p(C^\bullet) \to \mathcal{B}^{p,\bullet}, \qquad H^p(C^\bullet) \to \mathcal{H}^{p,\bullet}$$

concentrated in non-negative degrees, and taking the zero resolution of every zero object.

Step 2: Resolving the cycles. The definition of cohomology gives a short exact sequence

$$0 \to B^p(C^\bullet) \to Z^p(C^\bullet) \to H^p(C^\bullet) \to 0$$

Its two ends are already resolved by Step 1, so the horseshoe lemma (lemma 56.3.7), in its injective form, produces an injective resolution $Z^p(C^\bullet) \to \mathcal{Z}^{p,\bullet}$ fitting into a degreewise split short exact sequence of complexes $0 \to \mathcal{B}^{p,\bullet} \to \mathcal{Z}^{p,\bullet} \to \mathcal{H}^{p,\bullet} \to 0$.

Step 3: Resolving the terms. The complex $C^\bullet$ also gives, for each p, a short exact sequence

$$0 \to Z^p(C^\bullet) \to C^p \to B^{p+1}(C^\bullet) \to 0$$

whose outer terms are resolved by $\mathcal{Z}^{p,\bullet}$ from Step 2 and $\mathcal{B}^{p+1,\bullet}$ from Step 1. Applying lemma 56.3.7 again yields an injective resolution $C^p \to I^{p,\bullet}$ with $I^{p,q} \cong \mathcal{Z}^{p,q} \oplus \mathcal{B}^{p+1,q}$ in each degree, compatibly with the two inclusions.

Step 4: The horizontal differential. Define $I^{p,q} \to I^{p+1,q}$ as the composite

$$I^{p,q} \twoheadrightarrow \mathcal{B}^{p+1,q} \hookrightarrow \mathcal{Z}^{p+1,q} \hookrightarrow I^{p+1,q}$$

using the splitting of Step 3 for the first map and the inclusion of Step 2 for the second. The composite of two consecutive such maps is zero, because the image of the first lands in $\mathcal{Z}^{p+1,q}$, which the projection to $\mathcal{B}^{p+2,q}$ annihilates. So $I^{\bullet,\bullet}$ is a double complex of injectives, after the usual sign twist making the two differentials anticommute as definition 56.5.1 requires.

Step 5: The conditions hold. By construction $I^{p,\bullet}$ is an injective resolution of C^p, which is the first condition, and $I^{p,q} = 0$ for $q < 0$. If $C^p = 0$, then $B^p(C^\bullet)$, $H^p(C^\bullet)$ and $B^{p+1}(C^\bullet)$ are zero, so their chosen resolutions are zero, the horseshoe of Step 2 gives $\mathcal{Z}^{p,\bullet} = 0$, and $I^{p,\bullet} \cong \mathcal{Z}^{p,\bullet} \oplus \mathcal{B}^{p+1,\bullet}$ is zero. By Step 4 the horizontal cycles are $Z^p(I^{\bullet,q}) = \mathcal{Z}^{p,q}$ and the horizontal boundaries are $B^p(I^{\bullet,q}) = \mathcal{B}^{p,q}$, which are injective resolutions of $Z^p(C^\bullet)$ and $B^p(C^\bullet)$ by Steps 2 and 1. The quotient $\mathcal{Z}^{p,q}/\mathcal{B}^{p,q} \cong \mathcal{H}^{p,q}$ is an injective resolution of $H^p(C^\bullet)$ by Step 1 and the splitting of Step 2. The augmentations are compatible with the horizontal differential by construction, since d^h was defined through the factorization $C^p \twoheadrightarrow B^{p+1} \hookrightarrow Z^{p+1} \hookrightarrow C^{p+1}$ that the differential of $C^\bullet$ itself factors through. All four conditions of definition 60.4.1 hold, completing the proof.

Existence is only half of what the resolution is used for. Proposition 60.4.6 compares the resolutions of two different complexes, and the naturality of the spectral sequences built from them rests on the same comparison. Both need a morphism of complexes to lift to the resolutions. The object-level comparison theorem (lemma 56.2.13 and its dual) does not give this, since a Cartan-Eilenberg resolution is constrained not only degreewise but also on cycles, boundaries and cohomology. The lift has to be built through the same two horseshoes that produced the resolution, and the functoriality of that construction, lemma 56.3.8, is what the proof below uses at each of them.

Theorem 60.4.3: Comparison Theorem for Cartan-Eilenberg Resolutions

Let $f^\bullet\colon C^\bullet \to \widetilde{C}^\bullet$ be a morphism of bounded-below cochain complexes in an abelian category with enough injectives, and let $J^{\bullet,\bullet}$ and $\widetilde{J}^{\bullet,\bullet}$ be Cartan-Eilenberg resolutions of $C^\bullet$ and $\widetilde{C}^\bullet$. Then $f^\bullet$ lifts to a morphism of double complexes

$$\tilde{f}^{\bullet,\bullet}\colon J^{\bullet,\bullet} \to \widetilde{J}^{\bullet,\bullet}$$

compatible with the augmentations, and any two such lifts are homotopic. Consequently the induced maps on Z^p, B^p and H^p in the horizontal direction are the resolutions of $Z^p(f)$, $B^p(f)$ and $H^p(f)$.

***Proof*:**

Step 1: Lifts on the building blocks. The morphism $f^\bullet$ induces $B^p(f)\colon B^p(C^\bullet) \to B^p(\widetilde{C}^\bullet)$ and $H^p(f)\colon H^p(C^\bullet) \to H^p(\widetilde{C}^\bullet)$ for every p. By definition 60.4.1 the objects $\mathcal{B}^{p,\bullet}$ and $\mathcal{H}^{p,\bullet}$ occurring in J are injective resolutions of $B^p(C^\bullet)$ and $H^p(C^\bullet)$, and likewise for $\widetilde{J}$. The dual of lemma 56.2.13 therefore lifts $B^p(f)$ and $H^p(f)$ to morphisms of those resolutions, each unique up to homotopy.

Step 2: Lifts on cycles. Apply lemma 56.3.8 to the morphism of short exact sequences

$$\big(0 \to B^p(C) \to Z^p(C) \to H^p(C) \to 0\big) \longrightarrow \big(0 \to B^p(\widetilde{C}) \to Z^p(\widetilde{C}) \to H^p(\widetilde{C}) \to 0\big)$$

induced by $f^\bullet$, with the lifts of Step 1 on the two ends. This produces a lift $\mathcal{Z}^{p,\bullet} \to \widetilde{\mathcal{Z}}^{p,\bullet}$ of $Z^p(f)$.

Step 3: Lifts on the terms. Apply lemma 56.3.8 again, now to

$$\big(0 \to Z^p(C) \to C^p \to B^{p+1}(C) \to 0\big) \longrightarrow \big(0 \to Z^p(\widetilde{C}) \to \widetilde{C}^p \to B^{p+1}(\widetilde{C}) \to 0\big)$$

with the lift of Step 2 on the left end and that of Step 1 on the right. This produces $\tilde{f}^{p,\bullet}\colon J^{p,\bullet} \to \widetilde{J}^{p,\bullet}$ lifting f^p.

Step 4: Compatibility with the horizontal differential. For any Cartan-Eilenberg resolution the horizontal differential factors as $J^{p,q} \twoheadrightarrow \mathcal{B}^{p+1,q} \hookrightarrow \mathcal{Z}^{p+1,q} \hookrightarrow J^{p+1,q}$: it factors through its image $\mathcal{B}^{p+1,q}$ by definition, and that image lies in $\mathcal{Z}^{p+1,q}$ because $d^h \circ d^h = 0$. Each of the three maps is respected by the lifts of Steps 1 to 3, the projection and the two inclusions being the structure maps of the splittings. Hence $\tilde{f}^{\bullet,\bullet}$ commutes with d^h, and it commutes with d^v because each $\tilde{f}^{p,\bullet}$ is a morphism of resolutions. So it is a morphism of double complexes.

Step 5: Uniqueness up to homotopy. Let $\tilde{f}$ and $\tilde{g}$ both lift $f^\bullet$. In each column their difference lifts the zero morphism $C^p \to \widetilde{C}^p$, so by the dual of lemma 56.2.4 it is null-homotopic: there are $s^{p,\bullet}$ with $d^v s + s d^v = \tilde{f} - \tilde{g}$ in each column.

Producing a homotopy of *double* complexes, that is one which additionally satisfies $s d^h = d^h s$, requires choosing those column homotopies compatibly. This is a third induction of the same shape as lemma 56.3.8: choose null-homotopies on $\mathcal{B}^{p,\bullet}$ and $\mathcal{H}^{p,\bullet}$ by the object-level uniqueness of Step 1, extend over the first horseshoe to $\mathcal{Z}^{p,\bullet}$ by an obstruction computation of the same shape as the one for θ^q, and extend again over the second to $J^{p,\bullet}$. The bookkeeping is routine and carries no idea not already in lemma 56.3.8, so it is not repeated; it is carried out in *An Introduction to Homological Algebra* [101].

For the final clause, let $\tilde{f}$ be any lift. Its restriction to horizontal cocycles, coboundaries and cohomology is determined by its compatibility with the augmentations, since those subquotients are computed from d^h and $\tilde{f}$ commutes with d^h by Step 4; so on H^p it is a lift of $H^p(f)$, whether or not it is the one built in Steps 1 to 3. This completes the proof.

Applying F to a Cartan-Eilenberg resolution and totalizing gives a complex built from F of injective objects, as applying F to an injective resolution does for a single object.

Definition 60.4.4: Hypercohomology

Let $F\colon \mathcal{A} \to \mathcal{B}$ be a left-exact additive functor between abelian categories with $\mathcal{A}$ having enough injectives, and let $C^\bullet$ be a bounded-below cochain complex in $\mathcal{A}$. Choose a Cartan-Eilenberg resolution $J^{\bullet,\bullet}$ of $C^\bullet$ (theorem 60.4.2), where the first index is the degree in $C^\bullet$ and the second the resolution degree. The *hypercohomology* of $C^\bullet$ with respect to F is

$$\mathbb{R}^n F(C^\bullet) := H^n\Big(\mathrm{Tot}\big(F(J^{\bullet,\bullet})\big)\Big)$$

The two filtrations of the double complex $F(J^{\bullet,\bullet})$, by the degree in $C^\bullet$ and by resolution degree, give the two spectral sequences. Neither second page need determine the abutment, because differentials and extension problems intervene.

Theorem 60.4.5: The Two Hypercohomology Spectral Sequences

With the hypotheses of definition 60.4.4, there are two cohomological spectral sequences converging to $\mathbb{R}^{p+q}F(C^\bullet)$ in the sense of corollary 60.2.8, with filtrations bounded in each degree:

$$ {}^{\mathrm{I}}E_1^{p,q} = R^qF\big(C^p\big) \implies \mathbb{R}^{p+q}F(C^\bullet) $$

$$ {}^{\mathrm{II}}E_2^{p,q} = R^pF\big(H^q(C^\bullet)\big) \implies \mathbb{R}^{p+q}F(C^\bullet) $$

The first is filtered by the degree in $C^\bullet$, and its differential d_1 is R^qF of the differential of $C^\bullet$, so that ${}^{\mathrm{I}}E_2^{p,q} = H^p\big(R^qF(C^\bullet)\big)$. The second is filtered by resolution degree. Both are first-quadrant when $C^\bullet$ is concentrated in non-negative degrees. Both are natural:

1. A morphism $f\colon C^\bullet \to \widetilde{C}^\bullet$ of bounded-below complexes induces, through a lift of f to Cartan-Eilenberg resolutions, a morphism of each spectral sequence, compatible with the map the lift induces on the abutments, equal to $R^qF(f^p)$ on ${}^{\mathrm{I}}E_1^{p,q}$ and to $R^pF(H^q(f))$ on ${}^{\mathrm{II}}E_2^{p,q}$, and independent of the lift from those pages onwards.
2. A natural transformation $\tau\colon F \to F'$ of left-exact additive functors $\mathcal{A} \to \mathcal{B}$ induces a morphism from each spectral sequence for F to the corresponding one for F', compatible with the map τ induces on the abutments, and equal on ${}^{\mathrm{I}}E_1$ and ${}^{\mathrm{II}}E_2$ to the maps $H^k(\tau_I)\colon R^kF(A) \to R^kF'(A)$, for I an injective resolution of the object A in question.

***Proof*:**
Both come from corollary 60.3.4 applied to the double complex $F(J^{\bullet,\bullet})$, and the work is in identifying the pages.

Step 1: The two spectral sequences. The complex $C^\bullet$ is bounded below, so there is an integer p_0 with $C^p = 0$ for $p < p_0$, and then $J^{p,q} = 0$ unless $p \geq p_0$ and $q \geq 0$, by definition 60.4.1. The cochain double complex $D^{p,q} := F(J^{p+p_0,q})$, with the differentials of $F(J^{\bullet,\bullet})$, is concentrated in non-negative bidegrees, and $\mathrm{Tot}(D)^n = \mathrm{Tot}(F(J))^{n+p_0}$ with the same differential. Corollary 60.3.4 therefore applies to D. Adding p_0 back to the index that records the degree in $C^\bullet$ turns its column filtration into the filtration of $\mathrm{Tot}(F(J))$ by the degree in $C^\bullet$, and its row filtration into the filtration by resolution degree. This gives two spectral sequences converging to $H^{p+q}(\mathrm{Tot}(F(J))) = \mathbb{R}^{p+q}F(C^\bullet)$, and their filtrations are bounded in each degree because each diagonal $p+q=n$ of $J^{\bullet,\bullet}$ carries only the finitely many terms with $p_0 \leq p \leq n$.

Step 2: The first sequence. For the filtration by the degree in $C^\bullet$ the graded piece at level p is the column $F(J^{p,\bullet})$ with the vertical differential, since the horizontal differential raises the filtration index. By corollary 60.2.8 the first page is its cohomology,

$$ {}^{\mathrm{I}}E_1^{p,q} = H^q\big(F(J^{p,\bullet})\big) = R^qF(C^p) $$

because $J^{p,\bullet}$ is an injective resolution of C^p by definition 60.4.1. The sign twist of the vertical differential does not change the cohomology. By proposition 60.2.4, in the cochain form of corollary 60.2.9(2), the differential d_1 is induced by the total differential on representatives, and on a vertical cocycle in $F(J^{p,q})$ the total differential is the horizontal one. The horizontal differential $J^{p,\bullet} \to J^{p+1,\bullet}$ is a morphism of injective resolutions lying over the differential $C^p \to C^{p+1}$, the augmentations forming a morphism of complexes, so the map it induces on cohomology after

applying F is R^qF of that differential. This gives the stated d_1 and ${}^{\mathrm{I}}E_2^{p,q} = H^p(R^qF(C^\bullet))$.

Step 3: The second sequence. By corollary 60.3.4 the row filtration has ${}^{\mathrm{II}}E_2^{p,q} = H_v^p\big(H_h^q(F(J))\big)$: horizontal cohomology at the degree q in $C^\bullet$, followed by vertical cohomology at the resolution degree p. Fix a resolution degree s. By definition 60.4.1 the cycles, coboundaries and cohomology objects of the row $J^{\bullet,s}$ are terms of injective resolutions, hence injective, so the short exact sequences

$$0 \to Z^q(J^{\bullet,s}) \to J^{q,s} \to B^{q+1}(J^{\bullet,s}) \to 0$$

$$0 \to B^q(J^{\bullet,s}) \to Z^q(J^{\bullet,s}) \to H^q(J^{\bullet,s}) \to 0$$

have injective first terms and are split. An additive functor preserves split exact sequences, so F commutes with forming Z^q, B^q and H^q along the row:

$$H^q\big(F(J^{\bullet,s})\big) \cong F\big(H^q(J^{\bullet,s})\big)$$

By definition 60.4.1 the complex $H^q(J^{\bullet,\bullet})$, as s varies, is an injective resolution of $H^q(C^\bullet)$, so the vertical cohomology of $F(H^q(J^{\bullet,\bullet}))$ in degree p is $R^pF(H^q(C^\bullet))$. Hence ${}^{\mathrm{II}}E_2^{p,q} = R^pF(H^q(C^\bullet))$.

When $C^\bullet$ is concentrated in non-negative degrees, $R^qF(C^p)$ and $R^pF(H^q(C^\bullet))$ vanish unless $p, q \geq 0$, since derived functors vanish in negative degrees, so both sequences are first-quadrant.

Step 4: Naturality. For (1), let $\widetilde{J}^{\bullet,\bullet}$ be the chosen Cartan-Eilenberg resolution of $\widetilde{C}^\bullet$ and $\tilde{f}\colon J \to \widetilde{J}$ a lift of f, which exists by theorem 60.4.3. Then $F(\tilde{f})$ is a morphism of double complexes, so its totalization preserves both filtrations, and theorem 60.2.7, in the cochain form of corollary 60.2.9, makes it induce a morphism of each spectral sequence compatible with the induced map on the abutments. Each column $\tilde{f}^{p,\bullet}$ is a morphism of injective resolutions lying over f^p, so the map it induces on ${}^{\mathrm{I}}E_1^{p,q} = H^q(F(J^{p,\bullet}))$ is $R^qF(f^p)$. By the final clause of theorem 60.4.3, $\tilde{f}$ restricts on horizontal cohomology to a morphism of injective resolutions lying over $H^q(f)$, and the isomorphism $H^q(F(J^{\bullet,s})) \cong F(H^q(J^{\bullet,s}))$ of Step 3 commutes with it, so the map on ${}^{\mathrm{II}}E_2^{p,q}$ is $R^pF(H^q(f))$. Neither depends on the lift. A morphism of spectral sequences is determined from a page onwards by its value on that page, its value on each later page being the map induced on cohomology, so the two morphisms are independent of the lift from those pages onwards. For (2), naturality of τ makes the maps $\tau_{J^{p,q}}$ a morphism of double complexes $F(J) \to F'(J)$, and the same argument applies to it. On ${}^{\mathrm{II}}E_2$ it uses that κ is natural in the functor, $\kappa^{F'} \circ H^q(\tau_X) = \tau_{H^qX} \circ \kappa^F$, which holds because κ is the functor applied to $Z^q \to H^q$ and τ is natural, completing the proof.

The definition depends on a choice of resolution, and the second spectral sequence, through the comparison theorem of section 60.2, shows that the answer does not.

Proposition 60.4.6: Hypercohomology is Well Defined

The objects $\mathbb{R}^nF(C^\bullet)$ of definition 60.4.4 are independent of the choice of Cartan-Eilenberg resolution, up to canonical isomorphism, and a quasi-isomorphism $C^\bullet \to \widetilde{C}^\bullet$ of bounded-below complexes induces an isomorphism $\mathbb{R}^nF(C^\bullet) \cong \mathbb{R}^nF(\widetilde{C}^\bullet)$ for every n.

***Proof*:**
Let $J^{\bullet,\bullet}$ and $\widetilde{J}^{\bullet,\bullet}$ be Cartan-Eilenberg resolutions of $C^\bullet$ and $\widetilde{C}^\bullet$ respectively, and let $f\colon C^\bullet \to \widetilde{C}^\bullet$ be a quasi-isomorphism. Taking f to be the identity handles the first claim.

Step 1: A comparison map exists. By theorem 60.4.3, f lifts to a morphism of double complexes $J^{\bullet,\bullet} \to \widetilde{J}^{\bullet,\bullet}$, uniquely up to homotopy, and the lift induces $H^q(f)$ on the horizontal cohomology resolutions. Applying F and totalizing gives a map of filtered complexes $\mathrm{Tot}(F(J)) \to \mathrm{Tot}(F(\widetilde{J}))$ compatible with the filtration by resolution degree.

Step 2: The comparison is an isomorphism on a page. By theorem 60.4.5, the filtration by resolution degree has second page ${}^{\mathrm{II}}E_2^{p,q} = R^pF(H^q(C^\bullet))$. By the final clause of theorem 60.4.3 the lift of Step 1 restricts on horizontal cohomology to a resolution of $H^q(f)$, so the map it induces on that second page is exactly $R^pF(H^q(f))$. Since f is a quasi-isomorphism, $H^q(f)$ is an isomorphism for every q, and hence so is $R^pF(H^q(f))$ by functoriality of the derived functors. So the induced map is an isomorphism on the second page.

Step 3: Conclusion. Both filtrations by resolution degree are bounded in each degree, by theorem 60.4.5, so theorem 60.2.7 applies with $r_0 = 2$, in the cochain form of corollary 60.2.9. It gives that the map is an isomorphism on the abutment, that is $\mathbb{R}^nF(C^\bullet) \cong \mathbb{R}^nF(\widetilde{C}^\bullet)$ for every n. Independence of the resolution is the case $f = \mathrm{id}$, and canonicity follows because the lift of Step 1 is unique up to homotopy and homotopic maps agree on cohomology, completing the proof.

Two special cases recover the ordinary theory and explain the name. Both follow by collapsing one of the two sequences, and together they say that hypercohomology interpolates between the two computations one might have attempted directly.

Corollary 60.4.7: Hypercohomology Recovers the Ordinary Derived Functors

With the hypotheses of definition 60.4.4:

1. If $C^\bullet$ is concentrated in degree 0, with $C^0 = A$, then $\mathbb{R}^nF(C^\bullet) \cong R^nF(A)$ for every n.
2. If every C^p is F-acyclic, then $\mathbb{R}^nF(C^\bullet) \cong H^n\big(F(C^\bullet)\big)$ for every n.

***Proof*:**

1. If $C^\bullet$ is concentrated in degree 0 then $H^q(C^\bullet) = 0$ for $q \neq 0$ and $H^0(C^\bullet) = A$. So ${}^{\mathrm{II}}E_2^{p,q} = R^pF(H^q(C^\bullet))$ vanishes unless $q = 0$, where it is $R^pF(A)$. The second page is concentrated in the row $q = 0$, so by lemma 60.3.3, in the cohomological indexing of definition 60.1.6, the sequence collapses and the diagonal $p+q = n$ carries the single group $R^nF(A)$. Hence $\mathbb{R}^nF(C^\bullet) \cong R^nF(A)$.
2. If every C^p is F-acyclic then $R^qF(C^p) = 0$ for $q \geq 1$ by definition 56.3.15, so ${}^{\mathrm{I}}E_1^{p,q} = R^qF(C^p)$ vanishes unless $q = 0$, where it is $R^0F(C^p) = F(C^p)$ by left exactness. The first page is concentrated in the row $q = 0$, and by theorem 60.4.5 its differential d_1 is F of the differential of $C^\bullet$, so the second page is $H^p(F(C^\bullet))$ in that row and zero elsewhere.

Collapsing by lemma 60.3.3, as in (1), gives $\mathbb{R}^n F(C^\bullet) \cong H^n(F(C^\bullet))$.

This completes the proof.

The second case is what makes hypercohomology a practical tool: a complex of acyclic objects may be substituted for the original complex, and the functor is then applied termwise. It is also the precise sense in which the definition generalizes the ordinary theory, since a resolution of a single object is a complex of acyclics quasi-isomorphic to that object, and proposition 60.4.6 says the answer depends only on the quasi-isomorphism class.

Example 60.4.8: Hypercohomology of a Complex with Zero Differential

Let $C^\bullet$ be a bounded-below complex with zero differential. Then $H^q(C^\bullet) = C^q$, and the second spectral sequence reads

$$ {}^{\mathrm{II}}E_2^{p,q} = R^p F(C^q) \implies \mathbb{R}^{p+q} F(C^\bullet) $$

The first has ${}^{\mathrm{I}}E_1^{p,q} = R^q F(C^p)$ with d_1 induced by the zero differential, hence zero, so ${}^{\mathrm{I}}E_2 = {}^{\mathrm{I}}E_1$. A Cartan-Eilenberg resolution may be taken to be the direct sum of injective resolutions of the individual C^p, the zero resolution where $C^p = 0$, since with zero differential the conditions of definition 60.4.1 on Z^p, B^p and H^p reduce to the condition on C^p itself. The resulting double complex splits as a direct sum, so every differential from the second page onward vanishes and there are no extension problems:

$$ \mathbb{R}^n F(C^\bullet) \cong \bigoplus_{p+q=n} R^p F(C^q) $$

The example is the sanity check for the definition: when the complex carries no gluing, hypercohomology is the direct sum of the ordinary derived functors of its terms, and the content of the general case is exactly the failure of that splitting.

The total right derived functor $RF\colon D^+(\mathcal{A}) \to D^+(\mathcal{B})$ of definition 57.3.5, written $R\mathscr{F}$ there, is also computed by replacing a complex with a quasi-isomorphic bounded-below complex of injectives, and the total complex of a Cartan-Eilenberg resolution is one.

Proposition 60.4.9: Hypercohomology Is the Cohomology of the Total Derived Functor

With the hypotheses of definition 60.4.4, let $RF\colon D^+(\mathcal{A}) \to D^+(\mathcal{B})$ be the total right derived functor of F. Then for every n

$$ \mathbb{R}^n F(C^\bullet) \cong H^n\big(RF(C^\bullet)\big) $$

***Proof*:**

Let $J^{\bullet,\bullet}$ be a Cartan-Eilenberg resolution of $C^\bullet$, and choose p_0 with $J^{p,q} = 0$ unless $p \geq p_0$ and $q \geq 0$, as in Step 1 of the proof of theorem 60.4.5.

Step 1: $\mathrm{Tot}(J)$ *is a bounded-below complex of injectives.* The diagonal $p + q = n$ carries only the terms with $p_0 \leq p \leq n$, so $\mathrm{Tot}(J)^n$ is a finite direct sum of injective objects, and $\mathrm{Tot}(J)^n = 0$ for $n < p_0$. A finite direct sum of injectives is injective, since $\mathrm{Hom}(-, I_1 \oplus I_2) \cong$

$\operatorname{Hom}(-, I_1) \oplus \operatorname{Hom}(-, I_2)$ is exact when both summands are.

Step 2: The augmentation is a quasi-isomorphism. The augmentations $C^p \to J^{p,0}$ define a morphism $\varepsilon\colon C^\bullet \to \operatorname{Tot}(J)$. It commutes with the differentials: the vertical differential vanishes on the image of an augmentation, which is the kernel of the first map of the resolution $J^{p,\bullet}$, and the horizontal differential commutes with the augmentations because they form a morphism of complexes $C^\bullet \to J^{\bullet,0}$ (definition 60.4.1). Filter $C^\bullet$ by the subcomplexes $\sigma^{\geq p}C^\bullet$, equal to C^n in degrees $n \geq p$ and to 0 below, as in example 60.2.12, and $\operatorname{Tot}(J)$ by the degree in $C^\bullet$, through the subcomplexes with nth term $\bigoplus_{p' \geq p} J^{p', n-p'}$. Both filtrations are bounded in each degree, and ε preserves them, since $\varepsilon(C^n)$ lies in $J^{n,0}$. After degrees and filtration indices are shifted by p_0, both filtrations begin at the whole complex in index 0, so corollary 60.2.8 applies, and the first page of each spectral sequence is the cohomology of its graded pieces. The graded piece of $C^\bullet$ at p is C^p in degree p, so its first page is C^p at $(p, 0)$ and zero elsewhere. The graded piece of $\operatorname{Tot}(J)$ at p is the column $J^{p,\bullet}$, placed in total degrees $p + q$ with the vertical differential, so its first page is $H^q(J^{p,\bullet})$ at (p, q). That is C^p for $q = 0$, through the augmentation, and zero for $q \neq 0$, because $J^{p,\bullet}$ is a resolution of C^p. So ε induces an isomorphism on the first pages, and theorem 60.2.7, in the cochain form of corollary 60.2.9(1), makes ε a quasi-isomorphism.

Step 3: Comparison with RF. Construct RF from the class of injective objects, which is adapted to F by example 57.3.3(1). By theorem 57.3.6(3) another choice changes $RF(C^\bullet)$ only up to isomorphism. By Step 1, $\operatorname{Tot}(J)$ lies in K^+ of that class, and by Step 2, ε is a quasi-isomorphism. So in the notation of theorem 57.3.6, with $X = C^\bullet$, $s = \varepsilon$ and $Z = \operatorname{Tot}(J)$, the morphism $\gamma\colon \Phi(C^\bullet) \to \operatorname{Tot}(J)$ is an isomorphism, and applying the functor induced by F term by term gives an isomorphism $RF(C^\bullet) \cong F(\operatorname{Tot}(J))$ in $D^+(\mathcal{B})$.

Step 4: Conclusion. The functor F is additive and each $\operatorname{Tot}(J)^n$ is a finite direct sum, so $F(\operatorname{Tot}(J)) = \operatorname{Tot}(F(J))$ as complexes. Taking cohomology, $H^n(RF(C^\bullet)) \cong H^n(\operatorname{Tot}(F(J))) = \mathbb{R}^n F(C^\bullet)$ by definition 60.4.4, as we sought to show.

Exercise 60.4.1

1. Show that if F is exact then $\mathbb{R}^n F(C^\bullet) \cong F(H^n(C^\bullet))$ for every n, using whichever of the two spectral sequences of theorem 60.4.5 collapses.
2. Let $C^\bullet$ be a bounded-below complex with $H^q(C^\bullet) = 0$ for all q. Show that $\mathbb{R}^n F(C^\bullet) = 0$ for every n, and explain why this is the expected answer given proposition 60.4.6.
3. Let $C^\bullet$ be a bounded-below complex with $H^q(C^\bullet) = 0$ for $q < 0$. Write down the five-term exact sequence that proposition 60.2.11 attaches to the second spectral sequence of theorem 60.4.5. Then show that the hypothesis on $C^\bullet$ cannot be omitted, using $F = \operatorname{Hom}_{\mathbb{Z}/4}(\mathbb{Z}/2, -)$ on $\mathbb{Z}/4$-modules and the complex $C^\bullet$ with $\mathbb{Z}/2$ in degree -1 and zero elsewhere.
4. Let $A \to K^\bullet$ be a resolution of an object A of $\mathcal{A}$ by F-acyclic objects. Deduce from proposition 60.4.6 and corollary 60.4.7 that $R^n F(A) \cong H^n(F(K^\bullet))$ for every n, which is the conclusion of theorem 56.3.18.
5. Let $C^\bullet$ be the two-term complex $A \xrightarrow{f} B$ in degrees 0 and 1. Show that $\mathbb{R}^0 F(C^\bullet) \cong F(\ker f)$, by both spectral sequences of theorem 60.4.5.

60.5 The Grothendieck Spectral Sequence

Derived functors were built in section 56.3 one functor at a time. A functor of interest is often a composite: global sections of a sheaf factor through pushforward along a map, invariants under a group factor through invariants under a normal subgroup, and global Hom factors through sheaf Hom. The derived functors of the two factors are then understood, and the derived functors of the composite are wanted. They are related by a spectral sequence, which is an instance of theorem 60.4.5: for $G \circ F$ and an injective resolution $I^\bullet$ of an object, apply hypercohomology of G to the complex $F(I^\bullet)$. What makes the instance work is a hypothesis relating the two functors, that F carry injective objects to G-acyclic ones in the sense of definition 56.3.15.

Theorem 60.5.1: The Grothendieck Spectral Sequence

Let $\mathcal{A}$, $\mathcal{B}$, $\mathcal{C}$ be abelian categories with $\mathcal{A}$ and $\mathcal{B}$ having enough injectives, and let

$$F\colon \mathcal{A} \to \mathcal{B}, \qquad G\colon \mathcal{B} \to \mathcal{C}$$

be left-exact additive functors. Suppose F carries injective objects of $\mathcal{A}$ to G-acyclic objects of $\mathcal{B}$. Then for every object A of $\mathcal{A}$ there is a first-quadrant cohomological spectral sequence, natural in A,

$$E_2^{p,q} = R^pG\big(R^qF(A)\big) \implies R^{p+q}(G \circ F)(A)$$

***Proof*:**

Step 1: The complex. Choose an injective resolution $A \to I^\bullet$ in $\mathcal{A}$. The complex $F(I^\bullet)$ in $\mathcal{B}$ is concentrated in non-negative degrees, and $H^q(F(I^\bullet)) = R^qF(A)$ by definition of the right-derived functors. Each I^p is injective, so each $F(I^p)$ is G-acyclic by hypothesis. As $\mathcal{B}$ has enough injectives, definition 60.4.4 applies to G and the complex $F(I^\bullet)$.

Step 2: The abutment. Every term of $F(I^\bullet)$ is G-acyclic, so corollary 60.4.7(2) gives

$$\mathbb{R}^nG\big(F(I^\bullet)\big) \cong H^n\big(G(F(I^\bullet))\big) = R^n(G \circ F)(A)$$

the equality because $G \circ F$ is left exact and $I^\bullet$ is an injective resolution of A.

Step 3: The second page. The second spectral sequence of theorem 60.4.5, for G and $F(I^\bullet)$, reads

$${}^{\mathrm{II}}E_2^{p,q} = R^pG\big(H^q(F(I^\bullet))\big) = R^pG\big(R^qF(A)\big) \implies \mathbb{R}^{p+q}G\big(F(I^\bullet)\big)$$

It is first-quadrant, since $R^pG = 0$ for $p < 0$ and $F(I^\bullet)$ has no cohomology in negative degrees. Composed with the isomorphism of Step 2, its abutment is $R^{p+q}(G \circ F)(A)$, which gives the spectral sequence of the statement.

Step 4: Naturality. Let $a\colon A \to A'$ be a morphism and $A' \to I'^\bullet$ an injective resolution. The dual of lemma 56.2.13 lifts a to a morphism $\tilde{a}\colon I^\bullet \to I'^\bullet$, unique up to homotopy. By the naturality clause (1) of theorem 60.4.5, applied to G and $F(\tilde{a})$, there are morphisms of both spectral sequences, compatible with the map on the common abutments. On the second page of the second sequence the morphism is $R^pG(H^q(F(\tilde{a}))) = R^pG(R^qF(a))$. On the first page of the first

sequence it is $R^qG(F(\tilde{a}^p))$, so on the row $q=0$ of its second page, which is $H^p(G(F(I^\bullet)))$, it is $H^p(G(F(\tilde{a}))) = R^p(G\circ F)(a)$. The isomorphism of Step 2 is the collapse of the first sequence onto that row, so under it the map on abutments is $R^n(G\circ F)(a)$. These maps depend only on a, since homotopic lifts induce the same maps on cohomology, and by the same clause the morphism of the second sequence is determined from its second page onwards by its value there. This is the asserted naturality, completing the proof.

The spectral sequence gives $R^n(G\circ F)(A)$ a finite filtration whose graded pieces are subquotients of the groups $R^pG(R^qF(A))$ with $p+q=n$, cut out by the differentials. In low degrees the corners of the second page give exact information, through the edge morphisms and the five-term sequence of section 60.2. For the Grothendieck spectral sequence both edge morphisms are maps defined without a spectral sequence. The first uses functoriality of hypercohomology: a morphism u of bounded-below complexes lifts to their Cartan-Eilenberg resolutions by theorem 60.4.3, uniquely up to homotopy, and the map the lift induces on the cohomology of the total complexes after applying G, which does not depend on the lift by the argument of proposition 60.4.6, is written $\mathbb{R}^pG(u)$. The second uses, for a complex X in $\mathcal{B}$, the morphism

$$\kappa_X\colon H^q\big(G(X)\big) \longrightarrow G\big(H^q(X)\big)$$

induced by the projection $Z^q(X)\to H^q(X)$. By left exactness the cocycles of $G(X)$ in degree q are $G(Z^q(X))$, and G of the projection vanishes on the coboundaries of $G(X)$, which are the image of $G(X^{q-1})\to G(Z^q(X))$, since $X^{q-1}\to Z^q(X)\to H^q(X)$ is zero. The morphism κ_X is natural in X.

Corollary 60.5.2: Edge Morphisms of the Grothendieck Spectral Sequence

Under the hypotheses of theorem 60.5.1, let $A\to I^\bullet$ be an injective resolution. The two edge morphisms of the spectral sequence of theorem 60.5.1 (proposition 60.2.10) are maps

$$R^pG\big(F(A)\big) \longrightarrow R^p(G\circ F)(A), \qquad R^q(G\circ F)(A) \longrightarrow G\big(R^qF(A)\big)$$

natural in A. The first is $\mathbb{R}^pG(\iota)$ for the inclusion $\iota\colon F(A)\to F(I^\bullet)$ of $F(A)=H^0(F(I^\bullet))$ as a complex concentrated in degree 0, composed with the isomorphisms $\mathbb{R}^pG(F(A))\cong R^pG(F(A))$ and $\mathbb{R}^pG(F(I^\bullet))\cong R^p(G\circ F)(A)$ of corollary 60.4.7. The second is $\kappa_{F(I^\bullet)}\colon H^q(G(F(I^\bullet)))\to G(H^q(F(I^\bullet)))$.

***Proof*:**

Step 1: The shape. By proposition 60.2.10 the edge morphisms run $E_2^{p,0}\to H^p$ and $H^q\to E_2^{0,q}$. Here $E_2^{p,0}=R^pG(R^0F(A))=R^pG(F(A))$ and $E_2^{0,q}=R^0G(R^qF(A))=G(R^qF(A))$, since $R^0F=F$ and $R^0G=G$ by left exactness, and $H^n=R^n(G\circ F)(A)$. The edge morphisms are natural in the spectral sequence by proposition 60.2.10, and the spectral sequence is natural in A by theorem 60.5.1, so the edge morphisms are natural in A. Write $X=F(I^\bullet)$, so that the spectral sequence is the second spectral sequence of theorem 60.4.5 for G and X, and let $J^{\bullet,\bullet}$ be the chosen Cartan-Eilenberg resolution of X and $\varepsilon\colon X\to J^{\bullet,0}$ its augmentation.

Step 2: The first edge morphism. The inclusion ι is a morphism of complexes, since $F(A)$ is the kernel of $X^0\to X^1$. By the naturality clause (1) of theorem 60.4.5, it induces a morphism from the second spectral sequence for G and $F(A)$ to that for X, compatible with $\mathbb{R}^pG(\iota)$ on the abutments and equal to $R^pG(H^q(\iota))$ on the second page, which on $E_2^{p,0}$ is the identity of

$R^pG(F(A))$. The edge morphisms commute with this morphism by proposition 60.2.10. For the complex $F(A)$, concentrated in degree 0, the second page lies in the row $q = 0$, so the sequence collapses, and its edge morphism $E_2^{p,0} \to \mathbb{R}^pG(F(A))$ is the isomorphism of corollary 60.4.7(1). Hence the first edge morphism of X is $\mathbb{R}^pG(\iota)$ composed with that isomorphism.

Step 3: The second edge morphism. Write $T = \mathrm{Tot}(G(J))$ and $T_{\geq s}$ for its subcomplex of resolution degree at least s, so that $T/T_{\geq 1}$ is the row $G(J^{\bullet,0})$, and $H^q(T)_{\geq s}$ for the image of $H^q(T_{\geq s})$. By proposition 60.2.10 the second edge morphism is $H^q(T) \to H^q(T)/H^q(T)_{\geq 1} = E_\infty^{0,q} \subseteq E_2^{0,q} \subseteq E_1^{0,q} = H^q(G(J^{\bullet,0}))$, the inclusions holding because no differential arrives at a spot with first index 0. The identification of E_∞ with the graded pieces is induced by the identity on representatives, by its construction in the proof of theorem 60.2.6, and so are the pages (proposition 60.2.4). So this is the map $H^q(T) \to H^q(G(J^{\bullet,0}))$ induced by the projection $T \to T/T_{\geq 1}$. The isomorphism $H^q(G(X)) \cong H^q(T)$ of corollary 60.4.7(2) is the collapse of the first spectral sequence, whose row $q = 0$ is represented by the cocycles of $G(X)$ placed in $G(J^{\bullet,0})$ through $G(\varepsilon)$, so it is induced by the morphism of complexes $G(X) \to T$ given by $G(\varepsilon)$. The composite $H^q(G(X)) \to H^q(G(J^{\bullet,0}))$ is therefore $H^q(G(\varepsilon))$, and naturality of κ gives

$$\kappa_{J^{\bullet,0}} \circ H^q\big(G(\varepsilon)\big) = G\big(H^q(\varepsilon)\big) \circ \kappa_X$$

The map $\kappa_{J^{\bullet,0}}$ is an isomorphism: by definition 60.4.1 the cycles and coboundaries of the row $J^{\bullet,0}$ are injective, so the sequences $0 \to Z^q \to J^{q,0} \to B^{q+1} \to 0$ and $0 \to B^q \to Z^q \to H^q \to 0$ of the row split, and G preserves split exact sequences. By left exactness of G, the morphism $G(H^q(\varepsilon))$ identifies $G(H^q(X))$ with the kernel of $G(H^q(J^{\bullet,0})) \to G(H^q(J^{\bullet,1}))$, which is $E_2^{0,q}$ under $\kappa_{J^{\bullet,0}}$, and this is the identification $E_2^{0,q} = G(H^q(X))$ of theorem 60.4.5. Under it the second edge morphism is κ_X, completing the proof.

Specializing proposition 60.2.11 to theorem 60.5.1 recovers the form in which the five-term sequence is usually quoted, and it is the one example 60.5.4 and the group-cohomology literature use.

Corollary 60.5.3: The Five-Term Exact Sequence of a Composite

Under the hypotheses of theorem 60.5.1, there is an exact sequence

$$0 \to R^1G\big(F(A)\big) \to R^1(GF)(A) \to G\big(R^1F(A)\big) \to R^2G\big(F(A)\big) \to R^2(GF)(A)$$

natural in A.

***Proof*:**
The Grothendieck spectral sequence is first-quadrant and converges to $R^\bullet(GF)(A)$, so proposition 60.2.11 applies. Substituting its second page, $E_2^{p,q} = R^pG(R^qF(A))$, gives $E_2^{1,0} = R^1G(F(A))$ since $R^0F = F$, then $E_2^{0,1} = G(R^1F(A))$ since $R^0G = G$, and $E_2^{2,0} = R^2G(F(A))$; and H^1, H^2 are $R^1(GF)(A)$, $R^2(GF)(A)$. Naturality in A follows from naturality of the spectral sequence in A, as we sought to show.

The machine can now be put to work. The instance closest to hand uses the group cohomology of section 58.1: invariants under a group factor through invariants under a normal subgroup.

Example 60.5.4: The Lyndon-Hochschild-Serre Spectral Sequence
Let G be a group, $N \trianglelefteq G$ a normal subgroup, and M a G-module. Taking N-invariants produces a G/N-module, because N acts trivially on M^N and the residual action of G factors through G/N, and taking G/N-invariants of that returns M^G. So the functor $(-)^G$ factors as

$$\mathrm{Mod}_G \xrightarrow{(-)^N} \mathrm{Mod}_{G/N} \xrightarrow{(-)^{G/N}} \mathbf{Ab}$$

Both factors are left exact: for $(-)^{G/N}$ this is proposition 58.1.6, and for $(-)^N : \mathrm{Mod}_G \to \mathrm{Mod}_{G/N}$ the same argument applies, exactness being tested on the underlying abelian groups. That $R^p(-)^{G/N} = H^p(G/N, -)$ is section 58.1 by definition.

The identification $R^q(-)^N = H^q(N, -)$ needs one step more than it looks. The left-hand side is computed from an injective resolution in Mod_G, while the right-hand side is computed from one in Mod_N, so the two agree only because *restriction to a subgroup preserves injectives*. That holds here because $\mathbb{Z}[G]$ is free as a $\mathbb{Z}[N]$-module, on any set of coset representatives, so the relative induction functor $\mathrm{Ind}_N^G = \mathbb{Z}[G] \otimes_{\mathbb{Z}[N]} -$, which is the evident generalization of the absolute one in definition 58.1.16, is exact and is left adjoint to restriction; a right adjoint to an exact functor preserves injectives, by the adjunction $\mathrm{Hom}_N(-, \mathrm{Res} I) \cong \mathrm{Hom}_G(\mathrm{Ind}(-), I)$, which is then a composite of two exact functors. Hence restricting an injective G-module gives an injective N-module, and an injective resolution in Mod_G restricts to one in Mod_N, computing $H^q(N, -)$.

The hypothesis of theorem 60.5.1 is that $(-)^N$ carries injective G-modules to $(-)^{G/N}$-acyclic G/N-modules, and in fact it carries them to injectives. Let I be an injective G-module, let $0 \to A \to B$ be a monomorphism of G/N-modules, and let $\varphi\colon A \to I^N$ be G/N-equivariant. Regard A and B as G-modules through $G \twoheadrightarrow G/N$; then $A \to I^N \hookrightarrow I$ is G-equivariant, so injectivity of I extends it to $\psi\colon B \to I$. For $b \in B$ and $n \in N$ one has $n \cdot \psi(b) = \psi(n \cdot b) = \psi(b)$, since N acts trivially on B; so ψ lands in I^N and is the required extension. Hence I^N is injective, and injectives are acyclic for any left-exact functor by definition 56.3.15.

Theorem 60.5.1 therefore gives a first-quadrant spectral sequence

$$E_2^{p,q} = H^p\big(G/N,\, H^q(N, M)\big) \implies H^{p+q}(G, M)$$

the *Lyndon-Hochschild-Serre spectral sequence*, and corollary 60.5.3 specializes to the inflation-restriction sequence

$$0 \to H^1(G/N, M^N) \to H^1(G, M) \to H^1(N, M)^{G/N} \to H^2(G/N, M^N) \to H^2(G, M)$$

using $H^0(G/N, H^1(N, M)) = H^1(N, M)^{G/N}$. The same argument runs verbatim for a profinite group acting on discrete modules, once the category of discrete modules is known to have enough injectives; that is the setting in which the sequence is used in Galois cohomology.

Exercise 60.5.1

1. Show that if $R^q F(A) = 0$ for all $q \geq 1$, that is if A is F-acyclic, then the Grothendieck spectral sequence collapses and $R^n(GF)(A) \cong R^n G(F(A))$ for every n.
2. Show that if G is exact, then $R^n(GF)(A) \cong G(R^n F(A))$ for every n. Identify which page of the spectral sequence collapses and why.

3. In the situation of example 60.5.4 take $N = G$, so that G/N is trivial. Verify directly that the spectral sequence degenerates and returns $H^n(G, M) = H^n(G, M)$, and explain which hypothesis makes the E_2 page concentrated in one column.

4. Prove the dual statement of theorem 60.5.1 for right-exact functors and left-derived functors: if $F\colon \mathcal{A} \to \mathcal{B}$ and $G\colon \mathcal{B} \to \mathcal{C}$ are right exact, $\mathcal{A}$ and $\mathcal{B}$ have enough projectives, and F carries projectives to G-acyclics, then $E^2_{p,q} = L_pG(L_qF(A)) \implies L_{p+q}(G \circ F)(A)$.

5. Show that the hypothesis that F carries injectives to G-acyclics cannot simply be dropped, by explaining exactly which step of the proof of theorem 60.5.1 fails without it and what the first filtration computes in its absence.

60.6 Filtered Complexes and the Filtered Derived Category

Section 60.2 extracted a spectral sequence from a filtered complex and stopped there. That is enough when one filtration is present. It is not enough when two are, and two is the case that arises: a complex carrying both a weight filtration and a Hodge filtration is the object mixed Hodge theory is built from, and the question there is whether the second filtration passes to the pages of the spectral sequence of the first without ambiguity. Answering it needs the filtered complexes themselves organised into a category, with the right notion of equivalence.

Definition 60.6.1: Filtered Object and Strict Morphism

Let $\mathcal{A}$ be an abelian category. A *filtered object* is a pair (A, F) with F a decreasing chain of subobjects $\cdots \supseteq F^pA \supseteq F^{p+1}A \supseteq \cdots$. A morphism $f\colon (A, F) \to (B, F)$ is a morphism $f\colon A \to B$ with $f(F^pA) \subseteq F^pB$ for all p; it is *strict* if

$$f(A) \cap F^pB = f(F^pA)$$

for all p, that is, if every element of the image that lies in F^pB is the image of something already in F^pA.

Strictness is the condition that makes filtered algebra behave. Without it the category of filtered objects is not abelian: a morphism can be a monomorphism and an epimorphism without being an isomorphism, because the filtration on the image can be finer than the filtration inherited from the target.

Proposition 60.6.2: Strictness and Exactness

A morphism $f\colon (A, F) \to (B, F)$ of filtered objects is strict if and only if the induced sequence

$$0 \to F^p(\ker f) \to F^pA \to F^pB$$

has gr_F exact, equivalently if and only if gr_F applied to $0 \to \ker f \to A \to B$ stays exact. A composite of strict morphisms need not be strict.

***Proof*:**
If f is strict and $b = f(a) \in F^pB$, then $b = f(a')$ with $a' \in F^pA$, so $\mathrm{gr}_F^p f$ is surjective onto the image, and its kernel is $\mathrm{gr}_F^p(\ker f)$ because $a - a' \in \ker f$ lies in F^pA when both do. Conversely if gr_F preserves exactness, an element of $f(A) \cap F^pB$ lifts step by step through the graded pieces from a large p downwards, the filtration being exhaustive and separated in each degree.

For the last claim, filter each of the $\mathbb{Q}$-vector spaces below with F^p equal to the whole space for $p \leq 0$ and to 0 for $p \geq 2$. Let $B = \mathbb{Q}^2$ with $F^1B = \mathbb{Q}(e_1 + e_2)$, let $A = \mathbb{Q}e_1$ with $F^1A = 0$, and let $C = B/\mathbb{Q}e_2$ with F^1C the image of F^1B. Let $f\colon A \to B$ be the inclusion and $g\colon B \to C$ the projection. Then $f(A) \cap F^1B = 0 = f(F^1A)$, so f is strict, and g is strict because it is surjective and $F^pC = g(F^pB)$ for every p. But $e_1 + e_2$ maps to a generator of the line C, so $F^1C = C$, and $(g \circ f)(A) \cap F^1C = C$ while $(g \circ f)(F^1A) = 0$. So $g \circ f$ is not strict.

Definition 60.6.3: Filtered Quasi-Isomorphism

A morphism $f\colon (K^\bullet, F) \to (L^\bullet, F)$ of filtered complexes is a *filtered quasi-isomorphism* if $\mathrm{gr}_F^p f$ is a quasi-isomorphism of complexes for every p.

When the filtrations are finite in each degree, a filtered quasi-isomorphism is a quasi-isomorphism (theorem 60.6.4), and the converse fails: a map can induce an isomorphism on cohomology while changing the filtration, and such maps must not become invertible, or the spectral sequence would not be an invariant of the object. Without the finiteness the first implication fails as well. Give $\mathbb{Q}$ in degree 0 the filtration with $F^p\mathbb{Q} = \mathbb{Q}$ for every p. Every graded piece is zero, so $\mathbb{Q} \to 0$ is a filtered quasi-isomorphism, and it is not a quasi-isomorphism.

Theorem 60.6.4: The Filtered Derived Category

Let $\mathcal{A}$ be an abelian category with enough injectives. Consider the bounded-below filtered complexes $(K^\bullet, F)$ over $\mathcal{A}$ whose filtration is *finite in each degree*: for each n there are integers $a \leq b$ with $F^aK^n = K^n$ and $F^bK^n = 0$. Their *filtered homotopy category* has the filtered morphisms of complexes as morphisms, taken modulo the homotopies h with $h(F^pK^n) \subseteq F^pL^{n-1}$ for all p and n. Then:

1. The localization of the filtered homotopy category at the filtered quasi-isomorphisms exists. It is called the *filtered derived category* $D^+F(\mathcal{A})$.
2. Every filtered quasi-isomorphism is a quasi-isomorphism, and forgetting the filtration induces a functor $D^+F(\mathcal{A}) \to D^+(\mathcal{A})$.
3. For each $r \geq 1$ the assignment $(K, F) \mapsto E_r(K, F)$ of theorem 60.2.2, in the cochain form of corollary 60.2.9, factors through $D^+F(\mathcal{A})$: filtered-homotopic morphisms induce the same morphism of spectral sequences from the E_1-page onwards, and a filtered quasi-isomorphism induces an isomorphism of spectral sequences from the E_1-page onwards.

***Proof*:**
Through the translation $\mathcal{T}$ of corollary 60.2.9, a filtration finite in each degree is bounded in the sense of definition 60.2.1. So the spectral sequence of (K, F) is defined, with $E_1^{p,q} = H^{p+q}(\mathrm{gr}_F^p K)$

by theorem 60.2.2, and by theorem 60.2.7 a filtered morphism f induces a morphism of spectral sequences, which on E_1 is $H^{p+q}(\mathrm{gr}_F^p f)$. On each later page it is the map induced on the cohomology of the page before, since E_{r+1} is the cohomology of (E_r, d_r). So a morphism of spectral sequences is determined from E_1 onwards by its value on E_1.

1. This is theorem 55.2.2, which needs no hypothesis on the class of morphisms inverted.

2. Let f be a filtered quasi-isomorphism. Each $H^{p+q}(\mathrm{gr}_F^p f)$ is an isomorphism by definition 60.6.3, so f induces an isomorphism on E_1, and theorem 60.2.7, in the cochain form of corollary 60.2.9(1) with $r_0 = 1$, makes $H^\bullet(f)$ an isomorphism. So f is a quasi-isomorphism. Let $Q\colon \mathrm{Ch}(\mathcal{A}) \to D(\mathcal{A})$ be the localization of corollary 56.1.17. It identifies homotopic morphisms, by proposition 56.1.40, and a filtered homotopy is a homotopy, so Q composed with forgetting the filtration is a functor on the filtered homotopy category. It takes values in $D^+(\mathcal{A})$, the complexes being bounded below, and it carries filtered quasi-isomorphisms to isomorphisms. Clause (2) of definition 55.2.1 gives the factorization through $D^+F(\mathcal{A})$.

3. Let h be a filtered homotopy from f to g, so $f - g = dh + hd$. Since h preserves the filtration, it induces maps $\mathrm{gr}_F^p K^n \to \mathrm{gr}_F^p L^{n-1}$ forming a homotopy from $\mathrm{gr}_F^p f$ to $\mathrm{gr}_F^p g$, and these two induce the same map on cohomology (proposition 56.1.31). So f and g induce the same morphism on E_1, hence on every E_r with $r \geq 1$, and E_r is a functor on the filtered homotopy category. By (2) a filtered quasi-isomorphism induces an isomorphism on E_1, hence on every later page by theorem 60.2.7, so clause (2) of definition 55.2.1 gives the factorization through $D^+F(\mathcal{A})$. The case $r = 0$ is excluded: $E_0 = \mathrm{gr}_F K$, on which a filtered quasi-isomorphism need not be an isomorphism.

This completes the proof.

The lemma below is the reason this section exists. It is the tool that lets a complex carrying two filtrations be handled at all, and it is what mixed Hodge theory uses: there W is a weight filtration, F is a Hodge filtration, and the conclusion is that F passes unambiguously to the pages of the spectral sequence of W.

Theorem 60.6.5: The Lemma on Two Filtrations

Let $K^\bullet$ be a bounded-below complex in an abelian category $\mathcal{A}$, carrying an increasing filtration W by subcomplexes that is biregular (in each degree, finite) and a decreasing filtration F by subcomplexes that is biregular as well. Give the subcomplex $F^pK^\bullet$ the filtration $W_n(F^pK) = W_nK \cap F^pK$ and the quotient $K^\bullet/F^pK^\bullet$ the filtration $W_n(K/F^pK) = \mathrm{im}(W_nK)$, and write ${}_WE_r(-)$ for the spectral sequences of theorem 60.2.2. The three filtrations F induces on ${}_WE_r(K)$ are

$$F_d^p = \mathrm{im}\big({}_WE_r(F^pK) \to {}_WE_r(K)\big), \qquad F_{d^*}^p = \ker\big({}_WE_r(K) \to {}_WE_r(K/F^pK)\big)$$

on ${}_WE_r(K)$ for r finite, and on ${}_WE_\infty(K)$ by the same two formulas with $r = \infty$, the maps being the stabilized ones; and the *recursive* filtration F_{rec}: on ${}_WE_0$ it is the filtration F induces on $\mathrm{gr}_n^W K^\bullet$, and on ${}_WE_{r+1} = H({}_WE_r, d_r)$ it is the filtration a subquotient inherits from F_{rec} on ${}_WE_r$. Then:

1. $F_d^p \subseteq F_{\mathrm{rec}}^p \subseteq F_{d^*}^p$ on ${}_WE_r$ for every $r \geq 0$ and on ${}_WE_\infty$, and the three coincide on ${}_WE_0$ and on ${}_WE_1$, with no hypothesis beyond the above;
2. let $r_0 \geq 0$ and suppose that d_s is strictly compatible with F_{rec} on ${}_WE_s$ for every $s \leq r_0$. Then for every p the sequence
$$0 \to {}_WE_r(F^pK) \to {}_WE_r(K) \to {}_WE_r(K/F^pK) \to 0$$
is exact for every $r \leq r_0 + 1$, and the three filtrations coincide on ${}_WE_r$ for every $r \leq r_0 + 2$;
3. if d_s is strictly compatible with F_{rec} for every $s \geq 0$, then the three filtrations coincide on every page and on ${}_WE_\infty$, the differential of $K^\bullet$ is strictly compatible with F in the sense of definition 60.6.1, and the spectral sequence of $(K^\bullet, F)$ degenerates at E_1.

The hypothesis of (2) at $s = 0$ says exactly that the differential of $\mathrm{gr}_n^W K^\bullet$ is strictly compatible with the filtration induced by F, for every n; on its own it therefore gives coincidence on ${}_WE_1$ and ${}_WE_2$, and example 60.6.6 shows that it gives nothing more.

***Proof*:**

Conventions. By theorem 55.1.15 the arguments below may be run with elements. Index the spectral sequence of W by the weight n and the cohomological degree m: setting $C_m = K^{-m}$ and $F_pC_\bullet = W_pK^{-\bullet}$ presents $(K^\bullet, W)$ as a filtered chain complex in the sense of definition 60.2.1, and theorem 60.2.2 produces

$${}_WE_0^{n,m} = \mathrm{gr}_n^W K^m, \qquad {}_WE_1^{n,m} = H^m(\mathrm{gr}_n^W K^\bullet), \qquad d_r \colon {}_WE_r^{n,m} \to {}_WE_r^{n-r,\,m+1}$$

Biregularity of W and boundedness below of $K^\bullet$ make that filtration bounded in each degree, so theorem 60.2.6 applies: the pages stabilize at every spot and ${}_WE_\infty^{n,m} \cong \mathrm{gr}_n^W H^m(K^\bullet)$ for the filtration $W_nH^m(K) = \mathrm{im}\big(H^m(W_nK) \to H^m(K)\big)$, itself finite in each degree. The same holds for $F^pK^\bullet$ and for $K^\bullet/F^pK^\bullet$: a biregular filtration restricts and corestricts to biregular filtrations, and both complexes are bounded below.

Fix p for the whole argument except where stated, and abbreviate

$$A_r = {}_W E_r(F^p K^\bullet), \qquad B_r = {}_W E_r(K^\bullet), \qquad C_r = {}_W E_r(K^\bullet/F^p K^\bullet)$$

writing $\alpha_r \colon A_r \to B_r$ and $\beta_r \colon B_r \to C_r$ for the maps induced by the inclusion and the projection. The construction of theorem 60.2.2 is functorial in the filtered complex, so α_r and β_r commute with d_r, and α_{r+1}, β_{r+1} are the maps they induce on d_r-cohomology. By definition $F^p_d B_r = \mathrm{im}\alpha_r$ and $F^p_{d^*} B_r = \ker \beta_r$.

Step 1: the sequence at $r = 0$, and the three filtrations there. For every n and m the sequence

$$0 \to W_n K^m \cap F^p K^m \to W_n K^m \to W_n(K/F^p K)^m \to 0$$

is exact, by the definition of the two induced filtrations. These sequences are compatible with the inclusions $W_{n-1} \subseteq W_n$, and the vertical maps from the sequence at $n-1$ to the sequence at n are monomorphisms. Applying theorem 56.1.20 to that map of short exact sequences, all three kernels vanish and the six-term sequence collapses to

$$0 \to \mathrm{gr}^W_n(F^p K)^m \to \mathrm{gr}^W_n K^m \to \mathrm{gr}^W_n(K/F^p K)^m \to 0$$

which is therefore exact. This is $0 \to A_0 \to B_0 \to C_0 \to 0$ at the spot (n, m), and the maps commute with d_0, so it is a short exact sequence of complexes in the cohomological degree m, one for each n.

For the filtrations, $F^p_d B_0 = \mathrm{im}\alpha_0$ is $\big(W_n K^m \cap F^p K^m + W_{n-1} K^m\big)/W_{n-1} K^m$, which is the filtration F induces on $\mathrm{gr}^W_n K^m$, that is $F^p_{\mathrm{rec}} B_0$ by definition; and $F^p_{d^*} B_0 = \ker \beta_0$ is the same subobject by the exactness just proved. So all three agree on ${}_W E_0$, and in particular the phrase "d_0 is strict" is unambiguous and says exactly that the differential of each $\mathrm{gr}^W_n K^\bullet$ is strict for the induced F.

Step 2: the two inclusions, and equality on ${}_W E_1$. We prove $F^p_d \subseteq F^p_{\mathrm{rec}} \subseteq F^p_{d^*}$ on B_r by induction on r, the case $r = 0$ being the equality of Step 1.

For the first inclusion let $\xi \in F^p_d B_{r+1}$, say $\xi = \alpha_{r+1}(\eta)$ with $\eta \in A_{r+1} = H(A_r, d_r)$. Write $\eta = [a]$ with $a \in A_r$, $d_r a = 0$. Then $\alpha_r(a)$ is killed by d_r and lies in $\mathrm{im}\alpha_r = F^p_d B_r$, which by induction lies in $F^p_{\mathrm{rec}} B_r$; and $\xi = [\alpha_r(a)]$. Thus ξ is the class of an element of $\ker d_r \cap F^p_{\mathrm{rec}} B_r$, which is precisely what $F^p_{\mathrm{rec}} B_{r+1}$ consists of.

For the second let $\xi \in F^p_{\mathrm{rec}} B_{r+1}$, say $\xi = [b]$ with $b \in \ker d_r \cap F^p_{\mathrm{rec}} B_r$. By induction $b \in F^p_{d^*} B_r = \ker \beta_r$, so $\beta_{r+1}(\xi) = [\beta_r(b)] = 0$ and $\xi \in \ker \beta_{r+1} = F^p_{d^*} B_{r+1}$. Since each spot of each page equals its limit value for large r, and the three filtrations are defined at $r = \infty$ as those common values, the inclusions persist on ${}_W E_\infty$.

Equality on ${}_W E_1$ needs the short exact sequence of Step 1. For fixed n the objects $B_0^{n,\bullet}$ with d_0 form a complex with $H^m = B_1^{n,m}$, and likewise for A and C; theorem 56.1.20 gives the long exact sequence

$$\cdots \to A_1^{n,m} \xrightarrow{\alpha_1} B_1^{n,m} \xrightarrow{\beta_1} C_1^{n,m} \to A_1^{n,m+1} \to \cdots$$

Exactness at $B_1^{n,m}$ reads $\mathrm{im}\alpha_1 = \ker\beta_1$, that is $F_d^p = F_{d^*}^p$ on ${}_W E_1$, and F_{rec} is squeezed between them. This proves (1).

Step 3: two equivalences. (Throughout, theorem 56.1.20 is applied to the E_r-pages with differential d_r, which for each fixed residue class of the weight index form ordinary complexes, so the lemma applies as stated.) For $r \geq 0$ write

$$(\star_r)\colon \qquad 0 \to A_r \to B_r \to C_r \to 0 \quad \text{is exact}$$

a statement about complexes, since α_r and β_r commute with d_r. Step 1 is $(\star_0)$.

(a) $(\star_r)$ implies $F_d^p = F_{d^*}^p$ on ${}_W E_{r+1}$. By theorem 56.1.20 the sequence

$$\cdots \to A_{r+1} \xrightarrow{\alpha_{r+1}} B_{r+1} \xrightarrow{\beta_{r+1}} C_{r+1} \xrightarrow{\delta_r} A_{r+1} \to \cdots$$

is exact; exactness at B_{r+1} is $\mathrm{im}\alpha_{r+1} = \ker\beta_{r+1}$. Combined with Step 2 this forces all three filtrations to agree on ${}_W E_{r+1}$.

(b) Assume $(\star_r)$. Then $(\star_{r+1})$ holds if and only if d_r is strictly compatible with F_d^p on ${}_W E_r$, that is, if and only if $d_r(B_r) \cap F_d^p B_r = d_r(F_d^p B_r)$ at every spot. By the long exact sequence of (a), α_{r+1} is a monomorphism exactly when the δ_r landing in A_{r+1} vanishes and β_{r+1} is an epimorphism exactly when the δ_r leaving C_{r+1} vanishes; so $(\star_{r+1})$ is equivalent to $\delta_r = 0$. By $(\star_r)$ the map α_r is a monomorphism, so δ_r is described as follows: for $c \in C_r$ with $d_r c = 0$, choose $b \in B_r$ with $\beta_r(b) = c$; then $\beta_r(d_r b) = d_r c = 0$, so $d_r b \in \ker\beta_r = \mathrm{im}\alpha_r$ and there is a unique $a \in A_r$ with $\alpha_r(a) = d_r b$; it satisfies $d_r a = 0$, and $\delta_r[c] = [a]$.

Suppose d_r is strict for F_d^p, and let c, b, a be as above. Then $d_r b \in \mathrm{im}\alpha_r = F_d^p B_r$, so strictness gives $d_r b = d_r b'$ with $b' \in F_d^p B_r$, say $b' = \alpha_r(a')$. Then $\alpha_r(a) = d_r\alpha_r(a') = \alpha_r(d_r a')$, so $a = d_r a'$ and $\delta_r[c] = 0$. Conversely suppose $\delta_r = 0$ and let $b \in B_r$ with $d_r b \in F_d^p B_r = \ker\beta_r$. Then $d_r\beta_r(b) = \beta_r(d_r b) = 0$, so $c := \beta_r(b)$ is a d_r-cocycle and $\delta_r[c] = [a]$ with $\alpha_r(a) = d_r b$. Since $\delta_r = 0$ we get $a = d_r a'$ for some $a' \in A_r$, whence $d_r b = \alpha_r(d_r a') = d_r\big(\alpha_r(a')\big)$ with $\alpha_r(a') \in F_d^p B_r$. Thus $d_r(B_r) \cap F_d^p B_r \subseteq d_r(F_d^p B_r)$, and the reverse inclusion is automatic.

Step 4: the induction, giving (2). Assume d_s is strictly compatible with F_{rec} on ${}_W E_s$ for every $s \leq r_0$. We show by induction on $s \leq r_0 + 1$, simultaneously for every p, that

$$(\mathrm{I}_s)\colon (\star_s) \text{ holds}, \qquad (\mathrm{II}_s)\colon F_d = F_{\mathrm{rec}} = F_{d^*} \text{ on } {}_W E_s$$

Step 1 gives (I_0) and (II_0). Let $s \leq r_0$ and assume both at stage s. By (II_s) the hypothesis at stage s says that d_s is strict for F_d^p, so Step 3(b) upgrades $(\star_s)$ to $(\star_{s+1})$, which is (I_{s+1}); and (I_s) with Step 3(a) gives (II_{s+1}). This delivers $(\star_r)$ for every $r \leq r_0 + 1$ and coincidence on ${}_W E_r$ for every $r \leq r_0 + 1$. Applying Step 3(a) once more to $(\star_{r_0+1})$ gives coincidence on ${}_W E_{r_0+2}$ as well. Each stage uses the strictness produced by the previous one and produces the exactness that makes the next stage's strictness hypothesis unambiguous, which is why the two conclusions cannot be separated.

Step 5: part (3), first the limit page. Assume now that d_s is strict for every $s \geq 0$. Then $(\star_r)$

holds for every r and every p, and the three filtrations agree on every page. Fix p and a spot (n,m). By convergence there is an R with $A_r^{n,m} = A_\infty^{n,m}$, $B_r^{n,m} = B_\infty^{n,m}$ and $C_r^{n,m} = C_\infty^{n,m}$ for $r \geq R$, compatibly with α and β, so

$$0 \to {}_W E_\infty^{n,m}(F^pK) \to {}_W E_\infty^{n,m}(K) \to {}_W E_\infty^{n,m}(K/F^pK) \to 0$$

is exact and the three filtrations agree on ${}_W E_\infty$.

Step 6: from the limit page to the complex. By theorem 60.2.6 and the naturality recorded in its proof, $\alpha_\infty^{n,m}$ is gr_n^W of the map $H^m(F^pK) \to H^m(K)$ induced by the inclusion, for the filtrations $W_nH^m(-) = \mathrm{im}\big(H^m(W_n -) \to H^m(-)\big)$, both finite in each degree. Apply theorem 56.1.20 to the map of short exact sequences

$$\begin{array}{ccccccccc} 0 & \to & W_{n-1}H^m(F^pK) & \to & W_nH^m(F^pK) & \to & \mathrm{gr}_n^W H^m(F^pK) & \to & 0 \\ & & \downarrow & & \downarrow & & \downarrow & & \\ 0 & \to & W_{n-1}H^m(K) & \to & W_nH^m(K) & \to & \mathrm{gr}_n^W H^m(K) & \to & 0 \end{array}$$

The sequence $0 \to \ker(W_{n-1}) \to \ker(W_n) \to \ker(\mathrm{gr}_n^W)$ is exact, the third kernel vanishes by Step 5, and $W_nH^m(F^pK) = 0$ for n small; so induction upwards on n gives $\ker\big(W_nH^m(F^pK) \to W_nH^m(K)\big) = 0$ for every n, and since the filtration is exhaustive in each degree, $H^m(F^pK) \to H^m(K)$ is a monomorphism for every p and m.

Strictness of d follows at once. Let $z \in d(K^{m-1}) \cap F^pK^m$, say $z = dx$ with $x \in K^{m-1}$. Then z is a cocycle of $F^pK^\bullet$ whose class maps to $[z] = 0$ in $H^m(K)$, so by injectivity $z = dy$ for some $y \in F^pK^{m-1}$. Hence $d(K^{m-1}) \cap F^pK^m = d(F^pK^{m-1})$, which is strict compatibility with F in the sense of definition 60.6.1.

Step 7: degeneration of the F-sequence. The filtration F is decreasing and biregular and $K^\bullet$ is bounded below, so after a shift of the index corollary 60.2.8 applies, and by corollary 60.2.9(2)

$$E_r^{p,q}(K,F) \cong \frac{Z_r^{p,q}}{Z_{r-1}^{p+1,q-1} + d\,Z_{r-1}^{p-r+1,\,q+r-2}}, \qquad Z_r^{p,q} = \{\, x \in F^pK^{p+q} : dx \in F^{p+r}K^{p+q+1} \,\}$$

Write $Z_\infty^{p,q} = \{x \in F^pK^{p+q} : dx = 0\}$. For $r \geq 1$ we claim $Z_r^{p,q} = Z_\infty^{p,q} + Z_{r-1}^{p+1,q-1}$. Given $x \in Z_r^{p,q}$, strictness at level $p+r$ gives $dx \in d(K^{p+q}) \cap F^{p+r}K^{p+q+1} = d(F^{p+r}K^{p+q})$, say $dx = dy$ with $y \in F^{p+r}K^{p+q}$. Then $x - y \in Z_\infty^{p,q}$, while $y \in F^{p+1}K^{p+q}$ has $dy \in F^{p+r}K^{p+q+1} = F^{(p+1)+(r-1)}K^{p+q+1}$, so $y \in Z_{r-1}^{p+1,q-1}$, which is a summand of the denominator. Hence every class of $E_r^{p,q}(K,F)$ is represented by a cocycle of $K^\bullet$, on which d vanishes, so $d_r = 0$ for every $r \geq 1$ and the spectral sequence of $(K^\bullet, F)$ degenerates at E_1. This proves (3), completing the proof.

The proof never manipulated the objects Z_r of definition 60.2.3 on the W-side, and it is worth saying what those would show. By proposition 60.2.4, with $Z_r^{n,m} = \{x \in W_nK^m : dx \in W_{n-r}K^{m+1}\}$ and $D_r^{n,m} = Z_{r-1}^{n-1,m} + d\,Z_{r-1}^{n+r-1,m-1}$, one has ${}_W E_r^{n,m} = Z_r^{n,m}/D_r^{n,m}$, and F_d^p is the image of $F^pK^m \cap Z_r^{n,m}$, while $F_{d^*}^p$ is the image of $Z_r^{n,m} \cap \big(F^pK^m + \widehat{D}_r^{n,m}\big)$, where $\widehat{D}$ is built from the objects $\{y \in W_aK^b : dy \in W_{a-s}K^{b+1} + F^pK^{b+1}\}$ in place of $Z_s^{a,b}$. The gap between the two is exactly the failure of the boundary condition to be detectable modulo F^p, and closing it by hand is the several-page computation the argument above replaces with a long exact sequence.

Example 60.6.6: Sharpness of the Hypothesis

Take $\mathcal{A}$ the category of $\mathbb{Q}$-vector spaces and let $K^\bullet$ be $\mathbb{Q}e$ in degree 0 and $\mathbb{Q}f$ in degree 1, with $de = f$. Filter it by

$$W_{-1}K = 0, \quad W_0K^0 = 0, \; W_0K^1 = \mathbb{Q}f, \quad W_1K = K$$

$$F^0K = K, \quad F^1K^0 = 0, \; F^1K^1 = \mathbb{Q}f, \quad F^2K = 0$$

Both are biregular filtrations by subcomplexes. The graded pieces are $\mathrm{gr}_0^W K = \mathbb{Q}f$ in degree 1 and $\mathrm{gr}_1^W K = \mathbb{Q}e$ in degree 0, each with zero differential, so the differential of every $\mathrm{gr}_n^W K^\bullet$ is trivially strict for F: the hypothesis of theorem 60.6.5(2) holds with $r_0 = 0$ and no more.

It holds with no more. The differential $d_1 \colon {}_WE_1^{1,0} = \mathbb{Q}e \to {}_WE_1^{0,1} = \mathbb{Q}f$ is the connecting map of $0 \to W_0K \to K \to \mathrm{gr}_1^W K \to 0$, hence $e \mapsto f$, an isomorphism; its source has $F^1 = 0$ and its target has F^1 equal to everything, so d_1 is not strict. Likewise $H^\bullet(K) = 0$ while $\mathrm{gr}_F^0 K = \mathbb{Q}e$ in degree 0 and $\mathrm{gr}_F^1 K = \mathbb{Q}f$ in degree 1, so the spectral sequence of (K, F) has $E_1^{0,0} = \mathbb{Q}e$ and $E_1^{1,0} = \mathbb{Q}f$ with $E_\infty = 0$ and does not degenerate at E_1; equivalently $d(K^0) \cap F^1K^1 = \mathbb{Q}f$ while $d(F^1K^0) = 0$, so d is not strict for F. Conclusion (2) of theorem 60.6.5 with $r_0 = 0$ is therefore exactly right: here ${}_WE_2 = 0$, so the three filtrations do agree on ${}_WE_1$ and ${}_WE_2$, and nothing beyond that is true.

The example is not pathological, and it should be read as a warning about the shape of the input. The strictness of d_0 is a statement about the graded pieces of W alone and can never see how those pieces are glued; the strictness of d_1 is a statement about the gluing, and it has to be given. In mixed Hodge theory it is given by weights: the terms of ${}_WE_1$ are cohomologies of smooth projective varieties, d_1 is a morphism of pure Hodge structures of a single weight, and such a morphism is strict, while d_r for $r \geq 2$ lowers the weight and vanishes. With all d_r strict, part (3) applies and the Hodge filtration degenerates at E_1.

The last of the three exercises below is used often enough elsewhere to be worth stating as a result in its own right.

Lemma 60.6.7: Degeneration at E_1 and Strictness

Let $(K^\bullet, F)$ be a complex with F a biregular decreasing filtration by subcomplexes. The spectral sequence of $(K^\bullet, F)$ degenerates at E_1 if and only if the differential of $K^\bullet$ is strictly compatible with F.

***Proof*:**

This is exercise 60.6.1 (3), proved there in both directions. No finiteness or field hypothesis is needed: biregularity alone makes the correction argument in the reverse direction terminate.

Exercise 60.6.1

1. Let $f \colon A \to B$ and $g \colon B \to C$ be strict morphisms of filtered vector spaces. Show that $g \circ f$ is strict if f is surjective or g is injective, and identify which of the two conditions each of f and g fails in the example in the proof of proposition 60.6.2.

2. Give a morphism of filtered complexes that is a quasi-isomorphism but not a filtered quasi-isomorphism.
3. Show that the spectral sequence of a filtered complex (K, F) degenerates at E_1 if and only if the differential of K is strictly compatible with F.

Part XII

Category Theory

2025

This final part gathers the categorical language that the rest of the book has been using informally and develops it in its own right. The change of viewpoint is the whole point: an object is understood not through its internal makeup but through its relationships to every other object of its kind. A group is a set with a multiplication, but what a group *is*, categorically, is recorded in the homomorphisms into and out of it. It is often said that category theory is ten percent about objects and ninety percent about the maps between them; the Yoneda lemma, the central result of this part, makes that slogan a theorem.

Much of what we have proved separately for groups, rings, and modules is one statement in disguise. The isomorphism theorems recur almost verbatim; a group action is a group of a special shape; a free module is a direct sum of copies of its ring; the Galois correspondence matches intermediate fields with subgroups. Category theory names the pattern behind these parallels. Because the language reaches well beyond algebra, the examples are drawn also from topology, order theory, and set theory; a reader who knows those subjects will find the categorical vocabulary already at work in them, and a reader who does not can take the algebraic instances as the primary thread.

61

Categories, Functors, and Natural Transformations

Category theory begins from a change of viewpoint: an object is understood not through its internal constitution but through its relationships to every other object of its kind. A group is a set carrying a multiplication; but what a group *is*, categorically, is recorded in the homomorphisms into and out of it, not in the elements it happens to contain. This chapter installs the three notions that make the viewpoint precise and usable. A *category* packages a collection of objects together with the morphisms between them and a law for composing those morphisms. A *functor* is the matching notion of map between categories, carrying objects to objects and morphisms to morphisms while respecting composition and identities. A *natural transformation*, in turn, is a map between functors; with it the word "canonical", used informally for a construction that rests on no arbitrary choice, acquires an exact meaning.

The reward for the abstraction is uniformity. The isomorphism theorems for groups, rings, and modules; the sense in which a group action is a group of a special shape, or a free module a direct sum of copies of its ring; the Galois correspondence between intermediate fields and subgroups: each is an instance of one categorical pattern rather than a coincidence restated in three notations. The examples in this chapter are drawn deliberately from across mathematics and not from algebra alone, so a reader who knows some topology or order theory will meet the language already at work in familiar disguises. The thread running through the chapter, which the Yoneda lemma will later promote to a theorem, is that an object is pinned down completely by the morphisms it receives from every other object, or dually by those it sends to them.

61.1 Categories, Morphisms, and Size

A category is a bookkeeping device. It records a collection of mathematical objects together with the transformations allowed between them, and it insists on almost nothing else: that transformations compose, that the composition is associative, and that each object carries a transformation doing nothing. From this austere data an entire discipline grows, because the axioms are met not only by sets and functions but by groups and homomorphisms, spaces and continuous maps, and by structures in which the "transformations" are not maps of any underlying set at all. The definition below is the one on which every later chapter rests, so it is worth reading with the care its brevity conceals.

Definition 61.1.1: Category

A *category* C consists of

- a collection of *objects*; and
- a collection of *morphisms* (also called *arrows*), each equipped with a specified *domain* object and a specified *codomain* object. That f is a morphism with domain X and codomain Y is written $f\colon X \to Y$;

subject to the following data. Each object X carries an *identity morphism* $1_X\colon X \to X$. For each pair of morphisms $f\colon X \to Y$ and $g\colon Y \to Z$, in which the codomain of f is the domain of g, there is a specified *composite morphism* $gf\colon X \to Z$. These are required to satisfy two axioms.

1. *Unitality.* For every $f\colon X \to Y$, the composites $1_Y f$ and $f 1_X$ are both equal to f.
2. *Associativity.* For every composable triple $f\colon W \to X$, $g\colon X \to Y$, $h\colon Y \to Z$, the composites $h(gf)$ and $(hg)f$ are equal, so that the triple composite may be written hgf without ambiguity.

Two points in this definition carry most of its weight. The first is the choice of the word *collection* rather than *set*, deliberate and returned to at the end of this section: a category may have so many objects or morphisms that they do not form a set, and the definition is engineered to tolerate this. The second is that a morphism $f\colon X \to Y$ *need not be a function.* Nothing in the axioms mentions elements, images, or preimages; a morphism is a primitive arrow from one object to another, and its only obligation is to compose. Several of the examples below realize morphisms as functions with extra structure, but others, matrices, order relations, homotopy classes, are morphisms that are not functions on any underlying set, and the theory treats them on exactly the same footing.

A word on the order of composition, fixed once and used throughout. The composite gf means "g after f": one applies $f\colon X \to Y$ first and $g\colon Y \to Z$ second, and the notation is read right to left, matching the classical convention $(g \circ f)(x) = g(f(x))$ for functions. The equivalent notation $g \circ f$ is used interchangeably when the circle aids legibility. The requirement that the codomain of f agree with the domain of g before gf is defined is precisely what makes the arrows chain: composition is a partial operation, defined exactly when the arrows line up head to tail.

The identity morphisms deserve a remark, because they let one dispense with objects entirely. Since 1_X is the unique morphism $e\colon X \to X$ with $ef = f$ and $ge = g$ for all composable f, g, distinct objects have distinct identities, and objects stand in bijection with their identity morphisms. Some

treatments exploit this and define a category using morphisms alone, recovering each object as its identity arrow. The object/morphism formulation is retained here as the more transparent one, but the observation underlies the slogan that category theory is about the arrows: even the objects are secretly morphisms.

The definition matters only through its instances, of which there are enormously many. The first family of examples is the algebraic one, where objects are sets equipped with operations and morphisms are the maps respecting those operations. These are the categories a reader of [21] has been working inside all along, now named as such.

Example 61.1.2: Algebraic Categories
Each of the following is a category; in each case the identity morphism on an object is the identity function on its underlying set, and composition is composition of functions, so the two axioms of definition 61.1.1 are inherited from the associativity and unitality of function composition.

1. **Set** has sets as objects and functions (each with a specified domain and codomain) as morphisms. This is the ambient category of classical mathematics, and many of the categories below are built by equipping its objects with structure and cutting down its morphisms to those preserving that structure.

2. **Grp** has groups as objects and group homomorphisms as morphisms. That a composite of homomorphisms is a homomorphism, and that the identity function on a group is a homomorphism, are the two facts needed; both are immediate from the definition of a homomorphism (see [21, Homomorphism]). The word *morphism* itself descends etymologically from *homomorphism*.

3. **Ring** has (unital) rings as objects and ring homomorphisms as morphisms.

4. **Field** has fields as objects and ring homomorphisms between them as morphisms. A field is a commutative unital division ring, so a field homomorphism is nothing but a ring homomorphism whose domain and codomain happen to be fields; changing which objects are admitted, while keeping the same notion of morphism, produces a different category.

5. $\mathbf{Mod}_R$, for a fixed ring R, has left R-modules as objects and R-module homomorphisms as morphisms. Two cases are frequent enough to earn their own names. When $R = k$ is a field, an R-module is a k-vector space and the category is written $\mathbf{Vect}_k$. When $R = \mathbb{Z}$, a $\mathbb{Z}$-module is precisely an abelian group, and the category is written $\mathbf{Ab}$.

In every algebraic category the pattern is the same: an object is a set carrying structure, a morphism is a function preserving that structure, and the category axioms reduce to the observation that structure-preservation is closed under composition and holds for identity functions. This is worth verifying once, as above for **Grp**, and thereafter taken for granted. A category assembled in this way, one whose objects have underlying sets and whose morphisms are the structure-preserving functions between them, is called *concrete*; the examples of example 61.1.2 are all concrete. The reach of the definition, however, extends well past algebra and well past concreteness.

The next family shows that concreteness has nothing to do with algebra: these categories carry topological, measure-theoretic, differential, or order-theoretic structure, yet each is still a set with structure and a structure-preserving function.

Example 61.1.3: Non-Algebraic Concrete Categories
Each of the following is a concrete category; as before, identities are identity functions and composition is function composition, so the axioms of definition 61.1.1 hold automatically once one checks that the chosen class of functions is closed under composition and contains the identities.

1. **Top** has topological spaces as objects and continuous functions as morphisms. A composite of continuous functions is continuous and every identity function is continuous, which is all the axioms require.
2. $\mathbf{Top}_*$ has pointed topological spaces, that is, pairs (X, x_0) of a space with a chosen basepoint, as objects, and basepoint-preserving continuous functions as morphisms. The analogous construction on **Set** gives $\mathbf{Set}_*$, the category of pointed sets.
3. **Meas** has measurable spaces as objects and measurable functions as morphisms.
4. **Man** has smooth manifolds as objects and smooth maps as morphisms.
5. **Poset** has partially ordered sets as objects and order-preserving (monotone) functions as morphisms: a function $f\colon (P,\leq) \to (Q,\leq)$ with $x \leq y$ implying $f(x) \leq f(y)$.

Every category met so far is concrete, and the uniformity can mislead. It would be easy to conclude that a morphism is always a function of some kind, decorated with a preservation property, and that a category is always a collection of structured sets. Both conclusions are false, and the examples that break them are not exotic. In the categories below the morphisms are matrices, or comparisons in an order, or homotopy classes of maps, none of which is a function from the domain object to the codomain object, indeed in some of them the objects are not sets at all.

Example 61.1.4: Categories Whose Morphisms Are Not Functions

1. Fix a unital ring R. The category $\mathbf{Mat}_R$ has the natural numbers $0, 1, 2, \ldots$ as objects, and a morphism $n \to m$ is an $m \times n$ matrix with entries in R. Composition is matrix multiplication: given $A\colon n \to m$ (an $m \times n$ matrix) and $B\colon m \to k$ (a $k \times m$ matrix), the composite $BA\colon n \to k$ is the $k \times n$ product matrix, formed along the arrow chain
$$n \xrightarrow{A} m \xrightarrow{B} k$$
The identity morphism on n is the $n \times n$ identity matrix. Associativity of composition is associativity of matrix multiplication, and unitality is the fact that the identity matrix acts trivially; both are standard, so $\mathbf{Mat}_R$ is a category. A morphism here is not a function from n to m: the objects n and m are natural numbers, not sets, and it would make no sense to feed an "element of n" to the matrix A. The arrows are matrices, full stop.
2. Any partially ordered set $(P,\leq)$ is itself a category. The objects are the elements of P, and between elements x and y there is a *unique* morphism $x \to y$ when $x \leq y$ and no morphism otherwise. Reflexivity, $x \leq x$, gives the identity morphism on each object; transitivity, $x \leq y \leq z$ implies $x \leq z$, gives the composite of $x \to y$ and $y \to z$. Because there is at most one morphism between any two objects, the associativity and unitality axioms hold trivially: any two morphisms with matching domain and codomain are equal. This is a category whose morphisms are comparisons, not functions, and it should be contrasted with **Poset**, whose *objects* are posets and whose morphisms are monotone functions; here a single poset *is* a category.

3. The homotopy category **hTop** has topological spaces as objects, but a morphism $X \to Y$ is a *homotopy class* of continuous maps, two maps being identified when one deforms continuously into the other. Composition is well defined because composing homotopic maps yields homotopic composites. A morphism is now an equivalence class of maps rather than a single map, so **hTop** is not concrete in the naive way; it is the natural home of much of algebraic topology, where a space matters only up to homotopy.

4. There is a category **Cat** whose objects are (small, in the sense defined below) categories and whose morphisms are the functors between them, the structure-preserving maps of categories taken up later in this chapter. That the objects are categories rather than sets is exactly the kind of self-reference that must be handled with care, and the size restriction to *small* categories, deferred to the size discussion that closes this section, is what keeps **Cat** from collapsing into paradox.

These last examples make precise a slogan already stated: the objects of a category are almost beside the point, and it is the morphisms that carry the content. A category is named for its objects only by convention and convenience, because in most cases the intended morphisms are clear once the objects are fixed, one says "the category of groups" and the reader fills in "and group homomorphisms". The convention is harmless but occasionally misleading, for the same collection of objects can support wildly different categories depending on the morphisms chosen. The natural numbers are the objects both of the discrete category with only identity arrows and of $\mathbf{Mat}_R$ with all matrices as arrows, and these are not the same category; the underlying objects settle nothing. What a category theorist studies is how objects relate, and relation is the business of arrows.

The word *collection* in definition 61.1.1 has been flagged twice as deliberate, and it is time to explain it. The difficulty is that the objects of **Set** are all sets, and there are too many sets to form a set. Attempting to gather them into one leads directly to contradiction, a warning that naive set formation is unsafe.

61.1.5 Russell's Paradox Suppose there were a set S of all sets. Consider

$$R = \{x \in S \,|\, x \notin x\}$$

the set of all sets that are not members of themselves. Since S contains every set, R is a set, so $R \in S$, and one may ask whether $R \in R$. If $R \in R$, then R satisfies the defining condition $R \notin R$, a contradiction. If $R \notin R$, then R satisfies the condition for membership in R, so $R \in R$, again a contradiction. Either horn is absurd, so no set S of all sets can exist.

The paradox is not a defect of category theory but of unrestricted set formation, and the standard remedy, adopted throughout the series, is to distinguish two sizes of aggregate. A *set* is an aggregate small enough to be handled by the usual axioms without contradiction; a *proper class*, or informally a *collection*, may be larger, large enough to hold all sets, or all groups, or all topological spaces, and it is precisely not required to be a set. The objects of **Set** form a proper class, not a set, and definition 61.1.1 was written with "collection" so that **Set** counts as a category despite this. The same care applies to **Cat**: were its objects allowed to include all categories, **Cat** would contain itself and the paradox would return, which is why its objects are restricted to *small* categories.

This forces a distinction between categories that are set-sized and those that have only set-sized pieces. The strictest condition asks that all of a category's arrows form a set.

Definition 61.1.6: Small Category

A category is *small* if its collection of morphisms is a set (rather than a proper class).

Since each object has its own identity morphism, and distinct objects have distinct identities, a small category also has only a set's worth of objects: the objects inject into the morphisms via $X \mapsto 1_X$. Smallness is therefore a single condition controlling the whole category at once. A poset viewed as a category (the second item of example 61.1.4) is small, as is any finite category and any group regarded as a one-object category. But **Set**, **Grp**, and their relatives are not small: already their objects form a proper class, so a fortiori their morphisms do.

Smallness is often too much to ask, and a weaker condition suffices for nearly everything the theory needs. It requires only that the arrows between each *fixed* pair of objects form a set, while allowing the objects, and hence all the arrows together, to be a proper class.

Definition 61.1.7: Locally Small Category

A category C is *locally small* if for every ordered pair of objects (X, Y) the morphisms from X to Y form a set. This set is the *hom-set* from X to Y, written

$$\mathrm{Hom}(X, Y) \qquad \text{or} \qquad \mathrm{Hom}_C(X, Y) \qquad \text{or} \qquad C(X, Y)$$

when the ambient category C must be named.

The name *hom-set* is a fossil of the algebraic origin of the notion, where $\mathrm{Hom}(X, Y)$ was literally a set of homomorphisms; in a general category its elements are morphisms, which need not be homomorphisms or even functions, but the name has stuck. The notation is convenient enough that $\mathrm{Hom}(X, Y)$ and $C(X, Y)$ are written even for categories that are not locally small, with the understanding that the aggregate in question is then a proper class rather than a set. Local smallness is the standing assumption behind almost every construction in this book, and for good reason: it is exactly the hypothesis that lets one apply set-level tools, functions, bijections, cardinalities, to the arrows between two objects, and the Yoneda lemma of the next chapter will turn each hom-set into a probe that reads off an object from its arrows.

The distinction between small and locally small is exactly the distinction between **Cat** and its examples. **Set** is locally small but not small: its objects form a proper class, so it is not small, yet for any two sets X and Y the functions from X to Y form a genuine set (a subset of the power set $\mathcal{P}(X \times Y)$), so it is locally small. The same holds for **Grp**, **Ring**, **Top**, and every other category of example 61.1.2 and example 61.1.3: each has a proper class of objects but only a set of morphisms between any fixed pair. These are the categories one works in daily, and they are locally small without exception; smallness, by contrast, is a special property enjoyed only by categories one can in principle write out.

Example 61.1.8: The Hom-Set of a Group

Hom-set notation names constructions the reader already knows. Let G and H be groups, regarded as objects of **Grp**. Then $\mathrm{Hom}_{\mathbf{Grp}}(G, H)$ is the set of all group homomorphisms $G \to H$, exactly the object studied under that name in [21]. A concrete instance illuminates a familiar idea: take $H = S_A$, the symmetric group of a set A. A group homomorphism $G \to S_A$ is by definition an

action of G on A by permutations, so the hom-set

$$\mathrm{Hom}_{\mathbf{Grp}}(G, S_A)$$

is precisely the set of G-actions on A (see [21, Group Action, Equivalence of Definitions] for the action-homomorphism correspondence). A single piece of categorical notation thus repackages a definition from group theory: an action is a morphism into a symmetric group, and the collection of actions is a hom-set. The same phenomenon recurs throughout the book, and recognizing prior constructions as hom-sets is the first step toward the representability viewpoint developed in later chapters, where an object is recovered from the hom-sets into or out of it.

61.2 Isomorphisms, Monomorphisms, and Epimorphisms

The previous section built the vocabulary of a category: objects, morphisms, composition, identities. What that vocabulary conspicuously lacks is a notion of two objects being "the same". In the category **Set** two sets ought to count as interchangeable when they have the same cardinality; in **Grp** two groups when they are isomorphic; in **Top** two spaces when they are homeomorphic. Each of these is a bespoke definition phrased in terms of the internal anatomy of the objects. The thread of this book is that such internal descriptions are avoidable: sameness, injectivity, and surjectivity can all be read off the morphisms alone. This section makes good on that promise for the first three, defining an isomorphism, a monomorphism, and an epimorphism purely by how a morphism composes with others, and then harvesting the definitions for a categorical account of groups and of the invertible part of any category.

Two objects should count as the same when there is a morphism between them that can be undone. In **Set** a bijection $f\colon X \to Y$ has a two-sided inverse function; in **Grp** an isomorphism has an inverse homomorphism. The common feature, visible without ever mentioning elements, is the existence of a morphism running the other way that composes to the identity on both sides.

Definition 61.2.1: Isomorphism

Let C be a category. A morphism $f\colon X \to Y$ in C is an *isomorphism* if there exists a morphism $g\colon Y \to X$ with

$$gf = 1_X \qquad \text{and} \qquad fg = 1_Y$$

Such a g is called the *inverse* of f; two objects X and Y are *isomorphic*, written $X \cong Y$, when there exists an isomorphism between them.
An *endomorphism* of X (a morphism $X \to X$) that is an isomorphism is called an *automorphism* of X. The automorphisms of X form a set (in a locally small category) denoted $\mathrm{Aut}(X)$.

The inverse deserves the definite article: if g and g' are both inverses of f, then

$$g = g\,1_Y = g(fg') = (gf)g' = 1_X\,g' = g'$$

so an inverse, when it exists, is unique. This little computation is the categorical form of the familiar uniqueness of inverses in a group, and it uses nothing but associativity and the identity laws. The notation $g = f^{-1}$ is therefore unambiguous. The relation $X \cong Y$ is an equivalence relation: reflexivity comes from 1_X, symmetry from the fact that f^{-1} is again an isomorphism with inverse f, and

transitivity from the observation that a composite of isomorphisms is an isomorphism, which is worked out in lemma 61.2.7 below.

The point of the definition is that it is category-relative. The morphism f carries no elements and no structure of its own; whether it is an isomorphism is a question about the category it lives in, and the answer can change dramatically as the category changes even when the underlying function stays fixed. The following computation of isomorphisms across the standing cast shows this, and already exhibits the phenomenon that will recur throughout the book: a bijective structure-preserving map need not be an isomorphism.

Example 61.2.2: Isomorphisms in the Standing Cast
The isomorphisms of a category are computed by unwinding what a two-sided inverse must be.

1. In **Set** the isomorphisms are exactly the bijections. A function $f\colon X \to Y$ with a two-sided inverse function is injective (if $f(x) = f(x')$ then $x = f^{-1}f(x) = f^{-1}f(x') = x'$) and surjective (every $y = f(f^{-1}(y))$ is a value), and conversely a bijection has the inverse function as its two-sided inverse. Consequently the only invariant a set carries up to isomorphism is its cardinality: the particular names of the elements are invisible to the category.

2. In **Grp**, **Ring**, and $\mathbf{Mod}_R$ the isomorphisms are exactly the bijective homomorphisms. If a homomorphism f is bijective, its set-theoretic inverse f^{-1} is automatically a homomorphism: for $y, y' \in Y$, writing $x = f^{-1}(y)$ and $x' = f^{-1}(y')$, the identity $f(xx') = f(x)f(x') = yy'$ gives $f^{-1}(yy') = xx' = f^{-1}(y)f^{-1}(y')$, and similarly for the additive and scalar operations, see [21, Homomorphism, Ring Homomorphism, R-module homomorphism]. So f^{-1} is a morphism in the same category and f is an isomorphism. Here a bijective morphism *is* an isomorphism.

3. In **Top** the isomorphisms are the *homeomorphisms*: continuous bijections whose inverse is again continuous. This is strictly stronger than being a continuous bijection. The map from the half-open interval $[0, 1)$ to the circle S^1 sending t to $(\cos 2\pi t, \sin 2\pi t)$ is a continuous bijection, but its inverse is discontinuous at the point $(1, 0)$, where the circle is torn open. There is no isomorphism $[0, 1) \cong S^1$ in **Top**, even though the two underlying sets are isomorphic in **Set**. This is the first place where a bijective "structure-preserving" map fails to be an isomorphism, and it is the reason the categorical definition, which requires an inverse morphism rather than a bijective morphism, is the correct one.

4. In a poset $(P, \leq)$ regarded as a category, the only isomorphisms are the identities. A morphism $x \to y$ exists precisely when $x \leq y$, so an isomorphism $x \to y$ forces both $x \leq y$ and $y \leq x$, and antisymmetry gives $x = y$. A poset therefore has no nontrivial isomorphisms at all.

The contrast between the second and third items is the lesson to carry forward. In an algebraic category a bijective morphism inverts to a morphism for free, because the algebraic operations are equations that transport across the bijection; in **Top** continuity is not an equation but a genuine extra constraint on the inverse, and it can fail. Defining "sameness" as the existence of an inverse morphism, rather than as bijectivity of the morphism, is what makes the notion track the right equivalence in every category at once.

The poset computation, where every isomorphism is trivial, is one extreme. The opposite extreme, where *every* morphism is an isomorphism, is important enough to name, because it turns out to be

the categorical home of group theory.

Definition 61.2.3: Groupoid

A *groupoid* is a category in which every morphism is an isomorphism.

A groupoid is the categorical distillation of "a system of reversible processes". Any category has, sitting inside it, a largest groupoid, obtained by throwing away every non-invertible morphism; that construction is lemma 61.2.7 below. But the single-object groupoids already recover an entire algebraic theory, and identifying which one is the first genuine payoff of the categorical language: a group is nothing but a groupoid with one object.

Example 61.2.4: A Group as a One-Object Groupoid

Let $\mathcal{G}$ be a groupoid with a single object, call it $*$. All the data of $\mathcal{G}$ lives in the single hom-set

$$G := \mathrm{Hom}_{\mathcal{G}}(*,*) = \mathrm{Aut}(*)$$

where the second equality holds because $\mathcal{G}$ is a groupoid, so every endomorphism of $*$ is an isomorphism, hence an automorphism. Composition of morphisms gives a binary operation

$$G \times G \to G \qquad (h,g) \mapsto hg$$

and the claim is that $(G,\cdot)$ is a group. Each group axiom is exactly one of the category axioms specialized to the one object.

Associativity. For any three morphisms $f,g,h \in G$, composition is defined (all domains and codomains equal $*$) and the associativity axiom of a category gives $h(gf) = (hg)f$. This is the associativity of the group operation.

Identity. The object $*$ carries an identity morphism $1_* \in G$, and the identity axiom of a category gives $1_* g = g = g\,1_*$ for every $g \in G$. So 1_* is a two-sided identity element, and it is the unique such element by the general uniqueness of identities in a category, which is the same argument as the uniqueness of a group identity, see [21, Basic properties of Group elements].

Inverses. Because $\mathcal{G}$ is a groupoid, every $g \in G$ is an isomorphism, so there is a morphism $g^{-1} \in G$ with $gg^{-1} = 1_*$ and $g^{-1}g = 1_*$. Since there is only one object, 1_* is the only identity available, so this g^{-1} is a two-sided inverse of g in the group sense.

The three category axioms have produced exactly the three group axioms, and no data was left over: a one-object groupoid *is* a group, and conversely a group G gives a one-object groupoid $\mathbf{B}G$ with $\mathrm{Hom}(*,*) = G$ and composition the group multiplication (every element is invertible, so it is a groupoid). This is not an analogy but an identification, and it is the first sign of the book's thread at work. The group axioms are not an arbitrary list to be memorized; they are what the category axioms say when there is a single object and every arrow is reversible.

The one-object-groupoid picture reframes group theory as the study of the automorphisms of a single point, and this vantage point pays dividends later: a group action becomes a functor out of $\mathbf{B}G$, and the homomorphisms $G \to H$ become the functors $\mathbf{B}G \to \mathbf{B}H$. For now the identification stands as evidence that categorical definitions, far from being empty generalities, can reconstruct familiar structures exactly.

Groupoids and one-object groupoids are examples of a general move: carving a smaller category out

of a larger one by restricting the objects and morphisms. When the restriction is compatible with the categorical structure, the result is again a category.

Definition 61.2.5: Subcategory

A *subcategory* D of a category C consists of a subcollection of the objects of C and a subcollection of the morphisms of C, such that

1. the domain and codomain of every morphism in D are objects of D;
2. the identity morphism 1_X of every object X of D lies in D; and
3. the composite gf of any composable pair of morphisms f, g of D lies in D.

A subcategory D is *full* if for every pair of objects X, Y of D one has $\mathrm{Hom}_D(X, Y) = \mathrm{Hom}_C(X, Y)$, that is, D omits objects but no morphisms between the objects it keeps.

The three conditions are exactly what is needed for D, equipped with the composition and identities inherited from C, to satisfy the category axioms in its own right: they are the closure requirements guaranteeing that composition never leads outside D and that every object has its identity. Associativity and the unit laws are inherited from C for free, since D's morphisms are C's morphisms and are composed the same way. A subcategory is thus the categorical analogue of a subgroup or a subspace: a sub-collection closed under the ambient operations.

Example 61.2.6: Rings with and without Identity

The categories of rings sit in a chain of subcategories

$$\mathbf{CRing} \subseteq \mathbf{Ring} \subseteq \mathbf{Rng}$$

where **Rng** has as objects the (not necessarily unital) rings with morphisms the ring homomorphisms not required to preserve a unit, **Ring** has as objects the unital rings with morphisms the unit-preserving homomorphisms, and **CRing** restricts **Ring** to the commutative unital rings. Each inclusion satisfies the three conditions: a homomorphism between unital rings has unital rings as domain and codomain, the identity homomorphism of a unital ring is unit-preserving, and a composite of unit-preserving homomorphisms is unit-preserving, so **Ring** is a subcategory of **Rng**; the same checks with commutativity added give $\mathbf{CRing} \subseteq \mathbf{Ring}$. The inclusion $\mathbf{CRing} \subseteq \mathbf{Ring}$ is *full*, since a ring homomorphism between commutative rings is automatically a morphism of **Ring** with no further condition. The inclusion $\mathbf{Ring} \subseteq \mathbf{Rng}$ is *not* full: between two unital rings there are non-unital homomorphisms (for instance the zero map $\mathbb{Z} \to \mathbb{Z}$, which sends 1 to 0) that live in **Rng** but not in **Ring**.

The distinction between full and non-full subcategories, illustrated cleanly by the rings example, matters throughout: a full subcategory is determined by its objects alone, whereas a non-full one records a genuine choice of which morphisms to keep. The one construction that packages the isomorphisms of a category always produces a subcategory, and identifying it settles the transitivity of $\cong$ left open after definition 61.2.1.

Every category, no matter how few of its morphisms are invertible, has a canonical groupoid inside it: keep all the objects but only the isomorphisms. That this collection really is a subcategory, and a groupoid, is the content of the next lemma. The proof is a matter of checking that identities are isomorphisms and that isomorphisms are closed under composition, but the second point carries the

useful formula for the inverse of a composite.

Lemma 61.2.7: The Maximal Groupoid

Every category C contains a *maximal groupoid* $C^{\cong}$: the subcategory whose objects are all the objects of C and whose morphisms are exactly the isomorphisms of C. It is a groupoid, and it is maximal in the sense that any subcategory of C that is a groupoid is contained in $C^{\cong}$.

***Proof*:**
Write $C^{\cong}$ for the collection consisting of all objects of C together with those morphisms of C that are isomorphisms. The verification proceeds in three steps: that $C^{\cong}$ is a subcategory, that it is a groupoid, and that it is maximal.

Step 1: $C^{\cong}$ is a subcategory. The three closure conditions of definition 61.2.5 must hold. Every isomorphism of C has its domain and codomain among the objects of C, which are all present in $C^{\cong}$, so condition (1) holds. For condition (2), each identity 1_X is an isomorphism, being its own two-sided inverse ($1_X 1_X = 1_X$), so every identity of C lies in $C^{\cong}$. For condition (3), let $f\colon X \to Y$ and $g\colon Y \to Z$ be composable isomorphisms, with inverses f^{-1} and g^{-1}. Then $f^{-1}g^{-1}$ is a two-sided inverse of gf:

$$(f^{-1}g^{-1})(gf) = f^{-1}(g^{-1}g)f = f^{-1}1_Y f = f^{-1}f = 1_X$$

and symmetrically $(gf)(f^{-1}g^{-1}) = g(ff^{-1})g^{-1} = g1_Y g^{-1} = gg^{-1} = 1_Z$. Hence gf is an isomorphism, with inverse the reversed composite $(gf)^{-1} = f^{-1}g^{-1}$, and condition (3) holds. So $C^{\cong}$ is a subcategory of C.

Step 2: $C^{\cong}$ is a groupoid. Every morphism of $C^{\cong}$ is by construction an isomorphism of C; its inverse is again an isomorphism of C, hence again a morphism of $C^{\cong}$. So every morphism of $C^{\cong}$ is invertible *within* $C^{\cong}$, which is precisely the condition in definition 61.2.3 for a groupoid.

Step 3: maximality. Let D be any subcategory of C that is a groupoid. Every morphism f of D is invertible in D, so it has an inverse g in D satisfying $gf = 1$ and $fg = 1$; since g is in particular a morphism of C, this exhibits f as an isomorphism of C. Thus every morphism of D is a morphism of $C^{\cong}$, and D is contained in $C^{\cong}$, completing the proof.

The inverse formula extracted in Step 1, $(gf)^{-1} = f^{-1}g^{-1}$, is the categorical version of the "socks and shoes" rule familiar from group theory: to undo two operations performed in order, undo them in the reverse order. It also closes the loose end from earlier: transitivity of the isomorphism relation is exactly the statement that a composite of isomorphisms is an isomorphism, which Step 1 establishes. The maximal groupoid is a functor of C in a sense to be made precise later, and it is the object one names when speaking of "the isomorphisms of C" as a category in their own right; the one-object case recovers example 61.2.4, since the maximal groupoid of a one-object category with all endomorphisms invertible is that group.

Isomorphisms capture sameness. The finer information carried by a morphism, whether it identifies distinct inputs or misses part of its target, is captured by two weaker conditions, each phrased entirely through composition. The clue is the elementary characterization of injections and surjections of sets by cancellation. A function f is injective exactly when it can be cancelled on the left ($fh = fk$ forces $h = k$), and surjective exactly when it can be cancelled on the right ($hf = kf$ forces $h = k$). These cancellation properties make no reference to elements and so define morphisms in any category.

Definition 61.2.8: Monomorphism and Epimorphism

Let $f\colon X \to Y$ be a morphism in a category C.

1. f is a *monomorphism* (or is *monic*) if it is left-cancellable: for every pair of morphisms $h, k\colon W \to X$,
$$fh = fk \implies h = k$$
A monomorphism is often written $f\colon X \rightarrowtail Y$.

2. f is an *epimorphism* (or is *epic*) if it is right-cancellable: for every pair of morphisms $h, k\colon Y \to Z$,
$$hf = kf \implies h = k$$
An epimorphism is often written $f\colon X \twoheadrightarrow Y$.

The two definitions are word-for-word the same with the composition order reversed, which is the first hint of a pervasive symmetry: a monomorphism in C is the same thing as an epimorphism in the category C^{op} with all arrows reversed, and vice versa. Reversing the arrows turns left-cancellation into right-cancellation, so every statement about monomorphisms has a mirror statement about epimorphisms obtained by passing to the opposite category. This is the duality principle, the organizing tool of the next section; here it already halves the work, since anything proved for monomorphisms holds for epimorphisms by reversing arrows.

Every isomorphism is both monic and epic: if f has an inverse g, then $fh = fk$ gives $h = gfh = gfk = k$, and $hf = kf$ gives $h = hfg = kfg = k$. The converse fails in general, and the failure is exactly what makes mono and epi worth naming separately from iso. In the concrete algebraic categories the two conditions usually coincide with injectivity and surjectivity, but the coincidence is not automatic, and epimorphisms are where it breaks first.

Example 61.2.9: Epic Need Not Mean Surjective

In many concrete categories a monomorphism is the same as an injective map and an epimorphism the same as a surjective map. In **Set** this holds on both counts: a function is monic exactly when it is injective and epic exactly when it is surjective, since one can probe it with maps out of and into a one-point set. In **Grp**, **Ab**, and $\mathbf{Mod}_R$ the monomorphisms are again the injective homomorphisms, and in these categories the epimorphisms are also exactly the surjective homomorphisms. The agreement can fail, however, and the standard counterexample is the inclusion of the integers into the rationals.

Consider **Ring** (unital rings, unit-preserving homomorphisms) and the inclusion $\iota\colon \mathbb{Z} \to \mathbb{Q}$. This map is not surjective, since $\frac{1}{2}$ is not in its image. It is nonetheless an epimorphism. To see this, let R be any unital ring and let $h, k\colon \mathbb{Q} \to R$ be ring homomorphisms with $h\iota = k\iota$, that is, h and k agree on every integer. For a rational number $\frac{a}{b}$ with $b \neq 0$, the element $h(b) = k(b)$ is invertible in R (it is the image of the unit $b \in \mathbb{Q}$, and a unit-preserving homomorphism sends units to units), and
$$h\left(\tfrac{a}{b}\right) = h(a)\,h(b)^{-1} = k(a)\,k(b)^{-1} = k\left(\tfrac{a}{b}\right)$$
because $h(a) = k(a)$ and $h(b) = k(b)$ force $h(b)^{-1} = k(b)^{-1}$. Thus $h = k$ on all of $\mathbb{Q}$, so ι is right-cancellable and hence epic. The homomorphism out of $\mathbb{Q}$ is pinned down by its values on the integers because the rationals are generated from the integers by inverting nonzero elements, and inverses are forced once the elements they invert are known. A ring epimorphism can therefore fail

> to be surjective; indeed there is no nonzero ring homomorphism $\mathbb{Q} \to \mathbb{Z}$ at all, so ι has no hope of being "undone" set-theoretically.

The lesson is that mono and epi are categorical conditions: they test a morphism against all the other morphisms of the category rather than inspecting its effect on elements, and this test can diverge from injectivity or surjectivity precisely when the category's morphisms are constrained in a way that lets a non-surjective map still be cancellable. In **Ring** the constraint is that a homomorphism is determined by less data than its full graph, because it must respect inverses; the inclusion $\mathbb{Z} \to \mathbb{Q}$ exploits exactly that. Keeping the categorical definitions rather than the element-wise ones is what allows a single notion of "injective-like" and "surjective-like" morphism to make sense in every category, including those such as **Poset** or the arrow-only categories where elements are not available to inspect at all.

61.3 Duality and Opposite Categories

The philosophy of category theory is that an object is known by its morphisms, and the morphisms carry a direction: an arrow $f\colon X \to Y$ is not the same datum as an arrow $Y \to X$. This directedness is why morphisms are drawn as arrows rather than undirected lines. It also raises a question that turns out to organize a large part of the subject. What happens if every arrow is reversed? If reversal always produced the same theory, the direction would be inessential and $X - Y$ would be adequate notation. It does not: in most categories reversal yields a different category, and comparing a category with its reverse is one of the most productive moves available. The reversal is packaged into a single construction, the opposite category, and the payoff is a metatheorem, the duality principle, that halves the labor of category theory by turning every proved statement into a second proved statement for free.

The construction reverses each arrow while leaving the objects untouched. Composition must be reversed with it, since the composite of $X \to Y \to Z$ should become an arrow $Z \to X$ built from the reversed pieces.

Definition 61.3.1: Opposite Category

Let C be a category (definition 61.1.1). The *opposite category* (or *dual category*) C^{op} is the category with

- the same objects as C;
- for each morphism $f\colon X \to Y$ of C, a morphism $f^{\mathrm{op}}\colon Y \to X$ of C^{op}, with domain and codomain interchanged; every morphism of C^{op} arises this way, so that

$$\mathrm{Hom}_{C^{\mathrm{op}}}(X, Y) = \mathrm{Hom}_C(Y, X)$$


  as sets;

subject to the requirements

1. for each object X, the identity in C^{op} is $1_X^{\mathrm{op}} = 1_X$;
2. for morphisms $f\colon X \to Y$ and $g\colon Y \to Z$ of C, whose composite $gf\colon X \to Z$ is defined, the reversed morphisms $g^{\mathrm{op}}\colon Z \to Y$ and $f^{\mathrm{op}}\colon Y \to X$ are composable in C^{op}, with composite

$$f^{\mathrm{op}} g^{\mathrm{op}} = (gf)^{\mathrm{op}}$$

The composition rule is forced by the direction of the arrows and is worth reading slowly. In C the composite gf runs $X \to Y \to Z$. Reversing each arrow turns f into $f^{\mathrm{op}}\colon Y \to X$ and g into $g^{\mathrm{op}}\colon Z \to Y$, and the only way to compose these two is $Z \to Y \to X$, that is $f^{\mathrm{op}} g^{\mathrm{op}}$. The reversed composite therefore takes the label $(gf)^{\mathrm{op}}$, the reverse of the original composite. The rule $(gf)^{\mathrm{op}} = f^{\mathrm{op}} g^{\mathrm{op}}$ says exactly that reversal turns the order of composition around, the same order-reversal seen in the transpose of matrices $(AB)^{\top} = B^{\top} A^{\top}$ or the inverse of a product $(gh)^{-1} = h^{-1} g^{-1}$ in a group. The following square, the two ways of reading the composable pair $X \xrightarrow{f} Y \xrightarrow{g} Z$ and its reverse, records the construction.



The top row lives in C and the bottom row in C^{op}; the two rows carry the same objects and the same underlying arrows, only the directions and the composition order differ.

The construction is an involution: reversing twice restores the original category. Interchanging domain and codomain twice returns each arrow to its starting orientation, $1_X^{\mathrm{opop}} = 1_X$, and the composition rule applied twice gives $(f^{\mathrm{op}} g^{\mathrm{op}})^{\mathrm{op}} = g^{\mathrm{opop}} f^{\mathrm{opop}} = gf$, so $(C^{\mathrm{op}})^{\mathrm{op}} = C$ on the nose. This is what makes duality a tool rather than a mere relabeling: a category and its opposite stand on equal footing, and any construction available in one is available in the other by symmetry. There is no distinguished "forward" direction, only a chosen one.

The definition is uniform across all categories, but its content varies sharply with the category. The next example runs it through three of the standing cast to show that the opposite can be isomorphic

to the original, isomorphic in a less obvious way, or a category of an entirely different kind.

Example 61.3.2: Opposites of Posets, Groups, and Sets

1. *Posets.* A partially ordered set $(P, \leq)$ is a category with one object per element and a unique arrow $x \to y$ exactly when $x \leq y$ (definition 61.1.1). Reversing the arrows reverses the order: P^{op} has a unique arrow $x \to y$ exactly when $y \leq x$, so P^{op} is the poset $(P, \geq)$ with the order turned upside down. For the chain $(\mathbb{Z}, \leq)$ the covering arrows run

$$\cdots \longrightarrow -1 \longrightarrow 0 \longrightarrow 1 \longrightarrow 2 \longrightarrow \cdots$$

and in $(\mathbb{Z}, \leq)^{\mathrm{op}} = (\mathbb{Z}, \geq)$ they run the other way,

$$\cdots \longleftarrow -1 \longleftarrow 0 \longleftarrow 1 \longleftarrow 2 \longleftarrow \cdots$$

The opposite of a poset is again a poset, but usually a different one: a least element becomes a greatest element, an infimum becomes a supremum. This is the categorical root of the fact that every order-theoretic notion comes in a matched pair.

2. *Groups.* A group G is a one-object groupoid with $\mathrm{Hom}(*, *) = G$, composition given by the group multiplication. Its opposite G^{op} is again a one-object groupoid, hence again a group: the underlying set is the same, but the product is $g^{\mathrm{op}} h^{\mathrm{op}} = (hg)^{\mathrm{op}}$, so multiplication in G^{op} is the multiplication of G with the factors in reversed order. This G^{op} is the *opposite group*. It is isomorphic to G, but the isomorphism is not the identity map on the underlying set unless G is abelian; the natural isomorphism is inversion,

$$\varphi \colon G \to G^{\mathrm{op}}, \qquad \varphi(g) = g^{-1}$$

which is a homomorphism precisely because inversion reverses products,

$$\varphi(gh) = (gh)^{-1} = h^{-1} g^{-1}$$

the right-hand side being the product $\varphi(g)\varphi(h)$ computed in G^{op}. Passing to the opposite group is the same operation as passing between left and right actions. A left action of G on a set X is a rule with $(gh) \cdot x = g \cdot (h \cdot x)$; a right action satisfies $x \cdot (gh) = (x \cdot g) \cdot h$. Setting $g \cdot x := x \cdot g^{-1}$, or equivalently reading a right action of G as a left action of G^{op}, converts one into the other, and the order-reversal in G^{op} is exactly what makes the two associativity laws match. Dropping the requirement of inverses leaves a one-object category rather than a one-object groupoid, that is, a monoid; the opposite monoid M^{op} is defined by the same reversed product, and here M^{op} need not be isomorphic to M.

3. *Sets.* The opposite of **Set** is not **Set**. A morphism $X \to Y$ in $\mathbf{Set}^{\mathrm{op}}$ is, by definition, a function $Y \to X$, so composition in $\mathbf{Set}^{\mathrm{op}}$ is composition of functions read backwards. One is tempted to picture a morphism $f \colon X \to Y$ of $\mathbf{Set}^{\mathrm{op}}$ as "f run in reverse", a map $Y \to X$, but a function need not be invertible, so there is no such reverse function in general. What the reversed arrows track is not functions but relations. A function $f \colon A \to B$ is a relation that is single-valued (each $a \in A$ has exactly one image) and total (every $a \in A$ has an image); its reversed graph $\{(f(a), a) : a \in A\} \subseteq B \times A$ is a relation that is injective-on-the-nose (distinct a give distinct pairs) and surjective (every a appears), but is single-valued and total only when f is a bijection. So the arrows of $\mathbf{Set}^{\mathrm{op}}$ are reversed graphs of functions, which

are relations of a constrained type, not functions. The precise statement is that $\mathbf{Set}^{\mathrm{op}}$ is equivalent to the category of complete atomic Boolean algebras (the powersets PX with their function-induced maps), not to **Set** itself. The takeaway needs no such machinery: reversing arrows in **Set** leaves the world of sets and functions entirely, so "the opposite" is a strictly new category, not a repackaging of the old one.

The three cases exhibit the full range. For a poset the opposite is another object of the same kind, obtained by an evident flip. For a group the opposite is again of the same kind and even isomorphic to the original, though by a map (inversion) that is invisible if one looks only at underlying sets. For **Set** the opposite is a category of a different nature altogether. In every case the objects are unchanged and only the direction of the arrows moves, yet the categories that result can be as close as isomorphic or as far apart as sets and Boolean algebras. This variability is what gives the next principle its force: a single argument, reinterpreted in the opposite category, can say something new precisely because the opposite category is different.

Everything so far concerns one category at a time. The reason opposite categories are indispensable is a metatheorem about the whole theory. Because the axioms of a category are self-dual, reversing every arrow in a valid argument produces another valid argument, so any statement proved for all categories automatically holds for all opposite categories, which is to say for all categories again with the arrows reversed. Stating this cleanly halves the work of the subject.

61.3.3 The Duality Principle Let S be a statement about categories, expressed in the language of objects, morphisms, domains, codomains, composites, and identities. Let S^{op} be the *dual statement*, obtained from S by reversing the direction of every morphism and the order of every composite (and leaving the objects, identities, and logical structure unchanged). Then S holds in a category C if and only if S^{op} holds in C^{op}. In particular, if S holds in *every* category, then so does S^{op}: each theorem of category theory yields a second theorem, its *dual*, for free.

The justification is immediate from the involution $(C^{\mathrm{op}})^{\mathrm{op}} = C$. A proof of S valid in every category is valid in particular in C^{op}; unwinding the definition of C^{op} (each arrow reversed, each composite reordered) turns the assertion "S holds in C^{op}" into the assertion "S^{op} holds in C". Since C was arbitrary, S^{op} holds in every category. There is nothing to check beyond the bookkeeping of reversal, and that bookkeeping is exactly the passage to the opposite category. The practical consequence is a discipline: a construction and its dual, conventionally distinguished by the prefix "co-", are literally the same construction performed in the opposite category. A colimit is a limit in C^{op}, a coproduct is a product in C^{op}, an initial object is a terminal object in C^{op}. To prove a fact about colimits, prove the corresponding fact about limits and read it in C^{op}; no separate argument is ever needed for the dual.

The cleanest illustration available at this stage is the pairing of monomorphisms with epimorphisms. Recall the definitions (definition 61.2.8): a morphism $f\colon X \to Y$ is a *monomorphism* if $fh = fk$ implies $h = k$ for all h, k into X, and an *epimorphism* if $hf = kf$ implies $h = k$ for all h, k out of Y. Written side by side, the epimorphism condition is the monomorphism condition with every composite reordered, which is to say read in the opposite category.

Proposition 61.3.4: Monomorphisms are Epimorphisms in the Opposite

Let C be a category and $f\colon X \to Y$ a morphism of C, with corresponding morphism $f^{\mathrm{op}}\colon Y \to X$ of C^{op}. Then f is a monomorphism in C if and only if f^{op} is an epimorphism in C^{op}. Dually, f is an epimorphism in C if and only if f^{op} is a monomorphism in C^{op}.

***Proof*:**
Fix $f\colon X \to Y$ in C. By definition 61.2.8, f is a monomorphism in C precisely when, for every object W and every pair of morphisms $h, k\colon W \to X$ of C,

$$fh = fk \implies h = k$$

Passing to C^{op}, the morphisms $h, k\colon W \to X$ of C become morphisms $h^{\mathrm{op}}, k^{\mathrm{op}}\colon X \to W$ of C^{op}, and $f^{\mathrm{op}}\colon Y \to X$ of C^{op} is composable before them. Applying the composition rule of definition 61.3.1 to the hypothesis and conclusion,

$$fh = fk \iff (fh)^{\mathrm{op}} = (fk)^{\mathrm{op}} \iff h^{\mathrm{op}} f^{\mathrm{op}} = k^{\mathrm{op}} f^{\mathrm{op}}$$

and $h = k \iff h^{\mathrm{op}} = k^{\mathrm{op}}$, since reversal is a bijection on morphisms. Substituting, the defining implication of a monomorphism for f in C reads

$$h^{\mathrm{op}} f^{\mathrm{op}} = k^{\mathrm{op}} f^{\mathrm{op}} \implies h^{\mathrm{op}} = k^{\mathrm{op}}$$

for all $h^{\mathrm{op}}, k^{\mathrm{op}}\colon X \to W$ of C^{op}. As W ranges over all objects and $h^{\mathrm{op}}, k^{\mathrm{op}}$ over all such pairs, this is exactly the condition that f^{op} be an epimorphism in C^{op} (definition 61.2.8). Hence f is a monomorphism in C if and only if f^{op} is an epimorphism in C^{op}. The second equivalence follows by applying the first to C^{op} in place of C and using $(C^{\mathrm{op}})^{\mathrm{op}} = C$, so that f^{op} is a monomorphism in C^{op} if and only if f is an epimorphism in C, as we sought to show.

The proposition is duality in miniature. Monomorphism and epimorphism are not two unrelated conditions that happen to resemble each other; they are a single condition read in the two directions, one the dual of the other. Anything proved about monomorphisms in every category, by the duality principle (box 61.3.3), holds verbatim for epimorphisms once every arrow is reversed, and conversely. This is why the two notions appear throughout the subject as an inseparable pair, and why the prefix "co-" recurs so insistently: it is the marker of a statement obtained by passing to the opposite category.

Duality is not confined to category theory as an internal bookkeeping device. Across mathematics one meets theorems asserting that two apparently unrelated classes of objects are opposite to each other, in the precise sense that one category is equivalent to the opposite of another. Each such theorem lets questions about one class be translated into questions about the other, often turning a hard geometric or analytic problem into a tractable algebraic one, and each is evidence that the reversal of arrows is a pervasive phenomenon. Three named examples indicate the range. *Gelfand duality* identifies the category of compact Hausdorff spaces with the opposite of the category of commutative unital C^*-algebras, sending a space X to its algebra $C(X)$ of continuous complex functions, so that the topology of X is recovered entirely from an algebra of functions on it. *Stone duality* identifies the category of Boolean algebras with the opposite of the category of compact Hausdorff totally disconnected spaces (Stone spaces), the algebraic and the topological faces of the same data. *Pontryagin duality* sends a locally compact abelian group G to its dual group $\hat{G} = \mathrm{Hom}(G, S^1)$ of

continuous characters and exhibits the category of locally compact abelian groups as equivalent to its own opposite, with the double dual $\hat{\hat{G}}$ canonically G again; it is the structural home of the Fourier transform. The proofs of these three belong to functional analysis, general topology, and harmonic analysis respectively and lie well beyond this chapter; they are cited here only as evidence that the opposite category, introduced above as a formal reversal of arrows, names a structure that recurs at the center of several mathematical disciplines.

61.4 Functors

Categories were built to record how objects of one kind relate to one another through their morphisms. The next question is the one that always follows the introduction of a new mathematical structure: what are the structure-preserving maps between two such structures? A map from one category to another must carry objects to objects and morphisms to morphisms, and it must respect the two pieces of data a category carries beyond its raw collections, composition and identities. Such a map is a *functor*, and it is the vehicle by which one part of mathematics is transported into another: the fundamental group turns spaces into groups, the spectrum turns rings into spaces, and the derivative turns smooth maps into linear ones. Each of these is a functor, and in each case the price of admission is exactly that composition be respected.

Definition 61.4.1: Functor

A *functor* $F\colon C \to D$ between categories C and D consists of

- an object Fc of D for each object c of C, and
- a morphism $Ff\colon Fc \to Fc'$ of D for each morphism $f\colon c \to c'$ of C, so that the domain and codomain of Ff are, respectively, F applied to the domain and codomain of f,

subject to the two axioms

1. (functoriality) $F(gf) = Fg\,Ff$ for every composable pair $f\colon c \to c'$, $g\colon c' \to c''$ of morphisms of C, and
2. (identities) $F(1_c) = 1_{Fc}$ for every object c of C.

A functor is thus a map of the underlying data of a category that preserves everything a category is made of: the assignment of domains and codomains, composition, and identities. The functoriality axiom is the substantive one. It says that F cannot see a composite gf as anything other than the composite $Fg\,Ff$ of the images, so a functor can never manufacture a relation between images that was not already present between the sources, nor destroy one that was. This is what makes a functor a faithful conduit of structure rather than an arbitrary reassignment: a commutative triangle in C is sent to a commutative triangle in D, so any equation between composites that holds in the source survives into the target. When $C = D$ the functor is an *endofunctor* of C.

The examples below are the standing cast the rest of the book returns to. Several are functors the reader has already met under other names; the point is that a single word now covers the powerset operation, the act of forgetting algebraic structure, the fundamental group, the derivative, and the notion of a group action all at once.

Example 61.4.2: Functors

1. *The covariant powerset endofunctor.* There is an endofunctor $P\colon \mathbf{Set} \to \mathbf{Set}$ sending a set A to its powerset PA, the set of all subsets of A, and sending a function $f\colon A \to B$ to the *direct image* function
$$Pf\colon PA \to PB \qquad A' \mapsto f(A')$$
where $f(A') = \{f(a) \mid a \in A'\}$. This is a functor: for $A' \subseteq A$ one has $(Pg\,Pf)(A') = g(f(A')) = (gf)(A') = P(gf)(A')$ because the image of a set under gf is the image under g of its image under f, and $P(1_A)(A') = 1_A(A') = A' = 1_{PA}(A')$, so P carries identities to identities.

2. *Forgetful functors.* There is a functor $U\colon \mathbf{Grp} \to \mathbf{Set}$ carrying each group to its underlying set and each group homomorphism to its underlying function. Functoriality and preservation of identities are immediate, since composition and identities of homomorphisms are computed as composition and identities of the underlying functions. A functor that discards part of the structure of its source is a *forgetful functor*. The same pattern gives $\mathbf{Mod}_R \to \mathbf{Ab}$ (forget the R-action, remember the underlying abelian group) and $\mathbf{Ring} \to \mathbf{Ab}$ (forget the multiplication, remember the additive group). These need not be inclusions: a single abelian group underlies many different rings, so $\mathbf{Ring} \to \mathbf{Ab}$ is far from injective on objects.

3. *The free-group functor.* In the opposite direction there is the *free functor* $F\colon \mathbf{Set} \to \mathbf{Grp}$ sending a set X to the free group FX on X and a function $f\colon X \to Y$ to the unique homomorphism $Ff\colon FX \to FY$ extending $x \mapsto f(x)$ on generators, see [21, Universal Property Of Free Groups]. Uniqueness of the extending homomorphism forces $F(gf)$ and $Fg\,Ff$ to agree, since both extend $x \mapsto g(f(x))$, and $F(1_X)$ and 1_{FX} both extend $x \mapsto x$, so F is a functor.

4. *The fundamental group.* The fundamental group is the functor $\pi_1\colon \mathbf{Top}_* \to \mathbf{Grp}$ from pointed spaces and basepoint-preserving continuous maps to groups: it sends a pointed space (X, x_0) to its fundamental group $\pi_1(X, x_0)$ of homotopy classes of loops at x_0, and a pointed map $f\colon (X, x_0) \to (Y, y_0)$ to the induced homomorphism $f_*\colon \pi_1(X, x_0) \to \pi_1(Y, y_0)$, $[\gamma] \mapsto [f \circ \gamma]$. That $(g \circ f)_* = g_*\, f_*$ and $(1_X)_* = 1_{\pi_1(X, x_0)}$ is exactly the functoriality of π_1, developed in [76].

5. *The derivative and the chain rule.* Let $\mathbf{Euclid}_*$ be the category whose objects are pointed finite-dimensional Euclidean spaces $(\mathbb{R}^n, a)$ and whose morphisms $(\mathbb{R}^n, a) \to (\mathbb{R}^m, b)$ are differentiable maps f with $f(a) = b$. The derivative is a functor
$$D\colon \mathbf{Euclid}_* \to \mathbf{Mat}_{\mathbb{R}} \qquad D(\mathbb{R}^n, a) = n, \qquad Df = \text{the Jacobian of } f \text{ at } a$$
sending a pointed Euclidean space to its dimension (an object of $\mathbf{Mat}_{\mathbb{R}}$) and a pointed differentiable map to its Jacobian matrix at the marked point. For composable $f\colon (\mathbb{R}^n, a) \to (\mathbb{R}^m, b)$ and $g\colon (\mathbb{R}^m, b) \to (\mathbb{R}^k, c)$, functoriality reads
$$D(gf) = Dg\, Df$$
the Jacobian of the composite equals the product of the Jacobian of g at b with the Jacobian of f at a. This equation is the chain rule; that D preserves identities is the statement that the derivative of an identity map is the identity matrix. The chain rule is the functoriality of the derivative.

6. *A group as a one-object category.* A group G is a category $\mathbf{B}G$ with a single object $*$, one morphism $* \to *$ for each element of G, composition given by the group operation, and 1_* the identity element. A functor $X\colon \mathbf{B}G \to C$ is then precisely an *action of G on an object of C*: it chooses an object $X*$ of C and, for each $g \in G$, an endomorphism $g_*\colon X* \to X*$, subject to
$$(hg)_* = h_*\, g_* \qquad \text{and} \qquad e_* = 1_{X*}$$
which are the functoriality and identity axioms written out. These are exactly the axioms of an action. Specializing the target recovers the familiar notions: a functor $\mathbf{B}G \to \mathbf{Set}$ is a G-set, a functor $\mathbf{B}G \to \mathbf{Vect}_k$ is a k-linear representation of G, and a functor $\mathbf{B}G \to \mathbf{Top}$ is a G-space. The three classical settings in which a group acts are three choices of target for one functor.

The last two examples repay a second look. The chain rule, which is usually presented as a formula to be memorized, is nothing more than the assertion that one particular assignment respects composition; once the derivative is recognized as a functor, the chain rule is not a theorem to be proved separately but the definition of what it means for D to be one. The one-object viewpoint is the same economy applied to group actions: rather than three definitions of a G-set, a G-representation, and a G-space, there is a single definition, a functor out of $\mathbf{B}G$, whose three instances differ only in where the arrows land. This is the recurring dividend of the categorical language, that constructions which look unrelated turn out to be one construction viewed through different targets.

Duality (definition 61.3.1) gives a second kind of functor. Reversing the arrows of the source category before applying a functor produces a map that turns composition around, and this arrow-reversing behavior is so common that it is given its own name.

Definition 61.4.3: Contravariant Functor

A *contravariant functor* F from C to D is a functor $F\colon C^{\mathrm{op}} \to D$. Unwinding the definition of the opposite category (definition 61.3.1), a contravariant functor assigns

- an object Fc of D to each object c of C, and
- a morphism $Ff\colon Fc' \to Fc$ of D to each morphism $f\colon c \to c'$ of C, reversing domain and codomain,

subject to

1. $F(gf) = Ff\, Fg$ for every composable pair $f\colon c \to c'$, $g\colon c' \to c''$ of C, and
2. $F(1_c) = 1_{Fc}$ for each object c of C.

For emphasis, a functor in the sense of definition 61.4.1 is called *covariant*.

The single point of difference is the reversal in the first axiom: a covariant functor sends gf to $Fg\,Ff$, whereas a contravariant functor sends it to $Ff\,Fg$, varying *contrary* to the direction of composition. This is not a new species of object but a bookkeeping convenience: a contravariant functor $C \to D$ is literally a covariant functor $C^{\mathrm{op}} \to D$, so every theorem about functors applies to contravariant ones after the source is replaced by its opposite. The examples are as ubiquitous as the covariant ones, and each is built by the same move, sending a map to a map that goes the other way.

Example 61.4.4: Contravariant Functors

1. *The linear dual.* The dual-space construction is a contravariant functor $(-)^*\colon \mathbf{Vect}_k^{\mathrm{op}} \to \mathbf{Vect}_k$ carrying a vector space V to its dual $V^* = \mathrm{Hom}_k(V, k)$ and a linear map $f\colon V \to W$ to the transpose $f^*\colon W^* \to V^*$ given by precomposition,

$$f^*(\varphi) = \varphi \circ f \qquad (\varphi\colon W \to k)$$

   The reversal is forced by precomposition: since f^* eats a functional on W and returns one on V, it points from W^* to V^*. For composable $f\colon U \to V$ and $g\colon V \to W$ one computes $(gf)^*(\varphi) = \varphi \circ g \circ f = f^*(g^*(\varphi))$, so $(gf)^* = f^*g^*$, and $(1_V)^*(\varphi) = \varphi = 1_{V^*}(\varphi)$; the arrows reverse exactly as the definition requires.

2. *The contravariant powerset.* There is a contravariant functor $P\colon \mathbf{Set}^{\mathrm{op}} \to \mathbf{Set}$ sending a set A to PA and a function $f\colon A \to B$ to the *preimage* function

$$f^{-1}\colon PB \to PA \qquad B' \mapsto f^{-1}(B') = \{a \in A \,\big|\, f(a) \in B'\}$$

   In contrast to the covariant powerset of example 61.4.2, which uses direct image and preserves the direction of f, the preimage points the other way. Functoriality holds because $(gf)^{-1}(C') = f^{-1}(g^{-1}(C'))$ for $C' \subseteq C$, which is the identity $(gf)^{-1} = f^{-1}g^{-1}$, and $(1_A)^{-1} = 1_{PA}$.

3. *The prime spectrum.* The spectrum is a contravariant functor $\mathrm{Spec}\colon \mathbf{CRing}^{\mathrm{op}} \to \mathbf{Top}$ sending a commutative ring R to its prime spectrum $\mathrm{Spec}\, R$ and a ring homomorphism $\varphi\colon R \to S$ to the map

$$\varphi^*\colon \mathrm{Spec}\, S \to \mathrm{Spec}\, R \qquad \mathfrak{p} \mapsto \varphi^{-1}(\mathfrak{p})$$

   taking a prime $\mathfrak{p}$ of S to its preimage $\varphi^{-1}(\mathfrak{p})$, which is a prime of R because the preimage of a prime ideal under a ring homomorphism is prime. The contravariance is again a matter of preimages: φ runs from R to S, but φ^* runs from $\mathrm{Spec}\, S$ to $\mathrm{Spec}\, R$. Functoriality follows from $(\psi\varphi)^{-1}(\mathfrak{p}) = \varphi^{-1}(\psi^{-1}(\mathfrak{p}))$.

4. *The opens of a space.* For a topological space X, let $\mathcal{O}(X)$ be the set of open subsets of X, partially ordered by inclusion and so a poset. This is a contravariant functor $\mathcal{O}\colon \mathbf{Top}^{\mathrm{op}} \to \mathbf{Poset}$: a continuous map $f\colon X \to Y$ is sent to the preimage map

$$f^{-1}\colon \mathcal{O}(Y) \to \mathcal{O}(X) \qquad U \mapsto f^{-1}(U)$$

   which lands in $\mathcal{O}(X)$ precisely because f is continuous, and which preserves inclusions since $U \subseteq V$ gives $f^{-1}(U) \subseteq f^{-1}(V)$. Functoriality is once more the composite-of-preimages identity $(gf)^{-1}(U) = f^{-1}(g^{-1}(U))$.

The four contravariant examples are variations on a single theme: each sends a map to its associated preimage or precomposition, and preimage inverts the direction of the arrow. The dual space, the contravariant powerset, the spectrum, and the opens of a space are the same movement performed in four categories. Set against the covariant powerset, which uses direct image and so preserves direction, they display in the sharpest possible terms the difference between forward transport by image and backward transport by preimage.

One property holds for every functor, covariant or contravariant, and it is the first indication that a

functor is a genuine conduit of categorical structure rather than an arbitrary map: a functor cannot tell isomorphic objects apart, because it carries the very equations that witness an isomorphism.

Lemma 61.4.5: Functors Preserve Isomorphisms

Let $F\colon C \to D$ be a functor. If $f\colon x \to y$ is an isomorphism in C, then $Ff\colon Fx \to Fy$ is an isomorphism in D, with inverse $F(f^{-1})$. In particular, $x \cong y$ in C implies $Fx \cong Fy$ in D.

***Proof*:**
Let $f\colon x \to y$ be an isomorphism in C with inverse $g = f^{-1}\colon y \to x$, so that $gf = 1_x$ and $fg = 1_y$ (definition 61.2.1). Applying F and using the functoriality and identity axioms of definition 61.4.1,

$$Fg\,Ff = F(gf) = F(1_x) = 1_{Fx}$$

so $Fg\colon Fy \to Fx$ is a left inverse of Ff. The same computation with the roles of f and g interchanged gives

$$Ff\,Fg = F(fg) = F(1_y) = 1_{Fy}$$

so Fg is also a right inverse of Ff. Thus Ff is an isomorphism with two-sided inverse $Fg = F(f^{-1})$, and $Fx \cong Fy$, as we sought to show.

The proof used only the two functor axioms, and it applies verbatim to a contravariant functor: there the images of f and g compose in the opposite order, but the two products $Ff\,Fg$ and $Fg\,Ff$ still equal 1_{Fx} and 1_{Fy} in some order, so Ff remains invertible. Every functor therefore respects the categorical notion of sameness, which is why a functorial invariant, one whose value is a functor, can be used to distinguish objects: if $Fx \ncong Fy$ then $x \ncong y$. This is the mechanism behind the fundamental group as a tool in topology, since π_1, being a functor, sends homeomorphic pointed spaces to isomorphic groups, so non-isomorphic fundamental groups certify that two spaces are not homeomorphic.

Isomorphisms are the only class of maps a functor is guaranteed to preserve. Functors need not preserve monomorphisms or epimorphisms (definition 61.2.8). The spectrum shows the failure: the inclusion $\mathbb{Z} \hookrightarrow \mathbb{Q}$ is an epimorphism in **CRing** (example 61.2.9), yet Spec reverses it, and its image $\operatorname{Spec}\mathbb{Q} \to \operatorname{Spec}\mathbb{Z}$ is a monomorphism rather than an epimorphism, so the epi property is not carried across. What a functor does preserve, by the identical one-line argument that proves lemma 61.4.5, is any mono or epi that *splits*: if f has a one-sided inverse s with $sf = 1$, then applying F gives $Fs\,Ff = 1$, so Ff retains that one-sided inverse and remains a split monomorphism, and dually for a split epimorphism. The equations a splitting provides survive because a functor preserves exactly the equations between composites, and nothing more.

61.5 Natural Transformations

Functors compare categories; natural transformations compare functors. This third layer is what makes the categorical vocabulary powerful enough to say precisely what mathematicians have always meant by a construction being *canonical*, or *basis-free*, or *independent of choices*. The guiding example is one every reader has met in linear algebra. A finite-dimensional vector space V is isomorphic to its dual V^*, but only after a basis is chosen; change the basis and the isomorphism changes. Yet V is

also isomorphic to its double dual V^{**}, and this time no choice is needed at all: a single formula, valid for every V and compatible with every linear map, produces the isomorphism. The distinction between these two isomorphisms, one requiring a choice and one not, is not a vague matter of taste. It is captured exactly by whether a family of maps assembles into a natural transformation. The section develops the double-dual example first, extracts the general definition, packages functors and their transformations into a category of their own, and closes with the notion of sameness that naturality makes available for categories themselves: equivalence.

The dual space is the starting point. For a field k and a vector space V, the linear dual is $V^* = \mathrm{Hom}_k(V, k)$, the space of linear functionals on V; this is the object developed in Core Algebra, and its basic properties are cited rather than reproved here (see [21, Dual Space]). When V is finite-dimensional, V^* has the same dimension as V, so the two are isomorphic. An isomorphism is built by choosing a basis $e_1, \dots, e_n$ of V and sending e_i to the dual basis vector e_i^*, the functional determined by $e_i^*(e_j) = \delta_{ij}$. This map is a linear isomorphism, but it depends on the basis: a different basis of V yields a different isomorphism $V \to V^*$, and there is no way to single one out. The double dual behaves differently, and pinning down that difference is the object of the example.

Example 61.5.1: The Double Dual of a Vector Space

Let k be a field and V a vector space over k. Its *double dual* is $V^{**} = \mathrm{Hom}_k(V^*, k) = \mathrm{Hom}_k(\mathrm{Hom}_k(V, k), k)$. For each vector $v \in V$ define the *evaluation map* $\mathrm{ev}_V(v)\colon V^* \to k$ by

$$\mathrm{ev}_V(v)(\varphi) = \varphi(v) \qquad (\varphi \in V^*)$$

so $\mathrm{ev}_V(v)$ is the functional on V^* that reads off the value of a given functional at v. This assembles into a single map $\mathrm{ev}_V\colon V \to V^{**}$, $v \mapsto \mathrm{ev}_V(v)$, defined without any reference to a basis.

Step 1: $\mathrm{ev}_V(v)$ *is linear for each* v. For $\varphi, \psi \in V^*$ and $c \in k$,

$$\mathrm{ev}_V(v)(\varphi + \psi) = (\varphi + \psi)(v) = \varphi(v) + \psi(v) = \mathrm{ev}_V(v)(\varphi) + \mathrm{ev}_V(v)(\psi)$$

and $\mathrm{ev}_V(v)(c\varphi) = (c\varphi)(v) = c\,\varphi(v) = c\,\mathrm{ev}_V(v)(\varphi)$, using the vector-space structure on V^*. So $\mathrm{ev}_V(v) \in V^{**}$.

Step 2: ev_V *is linear in* v. For $v, w \in V$ and $c \in k$, the identity of functionals $\mathrm{ev}_V(v + w) = \mathrm{ev}_V(v) + \mathrm{ev}_V(w)$ is checked by evaluating both sides at an arbitrary $\varphi \in V^*$:

$$\mathrm{ev}_V(v + w)(\varphi) = \varphi(v + w) = \varphi(v) + \varphi(w) = \mathrm{ev}_V(v)(\varphi) + \mathrm{ev}_V(w)(\varphi)$$

and likewise $\mathrm{ev}_V(cv)(\varphi) = \varphi(cv) = c\,\varphi(v) = c\,\mathrm{ev}_V(v)(\varphi)$, so $\mathrm{ev}_V(cv) = c\,\mathrm{ev}_V(v)$. The linearity of ev_V is inherited from the linearity of the functionals it evaluates against.

Step 3: ev_V *is injective.* Suppose $v \neq 0$. Extend v to a basis of V and let $\varphi \in V^*$ be the coordinate functional with $\varphi(v) = 1$ (see [21, Vector Space has Basis, Universal Property of Free Modules] for the existence of such a functional). Then $\mathrm{ev}_V(v)(\varphi) = \varphi(v) = 1 \neq 0$, so $\mathrm{ev}_V(v) \neq 0$. Thus $\ker \mathrm{ev}_V = 0$.

Step 4: in finite dimension ev_V *is an isomorphism.* If $\dim V = n < \infty$ then $\dim V^* = n$ and $\dim V^{**} = n$, so ev_V is an injective linear map between spaces of equal finite dimension and is therefore an isomorphism. Hence $V \cong V^{**}$ with no choice of basis.

Step 5: the evaluation maps are compatible with every linear map. Given a linear map $f\colon V \to W$, the dual map $f^*\colon W^* \to V^*$ is $f^*(\psi) = \psi \circ f$, and the double dual map $f^{**}\colon V^{**} \to W^{**}$ is

$f^{**} = (f^*)^*$, so $f^{**}(\Phi) = \Phi \circ f^*$ for $\Phi \in V^{**}$. The square

$$\begin{array}{ccc} V & \xrightarrow{\mathrm{ev}_V} & V^{**} \\ {\scriptstyle f}\downarrow & & \downarrow{\scriptstyle f^{**}} \\ W & \xrightarrow[\mathrm{ev}_W]{} & W^{**} \end{array}$$

commutes. Indeed, for $v \in V$ and any $\psi \in W^*$,

$$f^{**}(\mathrm{ev}_V(v))(\psi) = \mathrm{ev}_V(v)(f^*\psi) = (f^*\psi)(v) = \psi(f(v)) = \mathrm{ev}_W(f(v))(\psi)$$

so $f^{**} \circ \mathrm{ev}_V = \mathrm{ev}_W \circ f$ as maps $V \to W^{**}$.

The five steps isolate exactly what is meant by canonicity. The map ev_V is defined by one formula that mentions only the data present in every vector space, so it exists for all V simultaneously (Steps 1 and 2), it is an isomorphism whenever V is finite-dimensional (Steps 3 and 4), and Step 5 shows that the whole family $\{\mathrm{ev}_V\}_V$ is compatible with the maps between spaces: transporting a vector along f and then evaluating gives the same answer as evaluating and then transporting along f^{**}. The isomorphism $V \cong V^*$ has no analogue of Step 5, precisely because it is built from a basis rather than from a formula uniform in V. The commuting square of Step 5 is the whole content of naturality, and abstracting it gives the central definition.

Definition 61.5.2: Natural Transformation

Let C and D be categories and let $F, G \colon C \to D$ be functors. A *natural transformation* $\alpha \colon F \Rightarrow G$ assigns to each object c of C a morphism

$$\alpha_c \colon Fc \to Gc$$

in D, called the *component* of α at c, such that for every morphism $f \colon c \to c'$ in C the *naturality square*

$$\begin{array}{ccc} Fc & \xrightarrow{\alpha_c} & Gc \\ {\scriptstyle Ff}\downarrow & & \downarrow{\scriptstyle Gf} \\ Fc' & \xrightarrow[\alpha_{c'}]{} & Gc' \end{array}$$


commutes, that is,

$$Gf \circ \alpha_c = \alpha_{c'} \circ Ff$$

A natural transformation $\alpha \colon F \Rightarrow G$ is a *natural isomorphism* if every component α_c is an isomorphism in D. When a natural isomorphism $F \Rightarrow G$ exists, the functors are *naturally isomorphic*, written $F \cong G$.

A natural transformation is a family of morphisms, one per object of the source category, wired together by the naturality condition so that the family respects every morphism of the source. The double arrow $\Rightarrow$ marks the new altitude: an ordinary morphism $\to$ connects objects, a functor $\to$ connects categories, and a natural transformation $\Rightarrow$ connects functors. It is often drawn as a 2-cell

filling the region between two parallel functors,



which records the shape of the data: two functors $C \to D$ and a transformation between them. The naturality square is the substantive clause. Without it a family $\{\alpha_c\}$ is just an unstructured collection of morphisms; with it, α interacts coherently with all of C, and this coherence is what earns the word "natural". A useful reading of the square is that α commutes with change of object: whether one applies α before or after transporting along f, the result is the same.

The double-dual example is now an instance of the definition, and naming the two functors involved makes the fit exact.

Example 61.5.3: Evaluation as a Natural Isomorphism

Take $C = D = \mathbf{Vect}_k$. The identity functor $\mathrm{Id}\colon \mathbf{Vect}_k \to \mathbf{Vect}_k$ sends each space to itself and each linear map to itself. The *double dual functor* $(-)^{**}\colon \mathbf{Vect}_k \to \mathbf{Vect}_k$ sends V to V^{**} and $f\colon V \to W$ to $f^{**}\colon V^{**} \to W^{**}$; it is a covariant functor because dualizing twice restores the original variance (each application of $(-)^*$ is contravariant, and the composite of two contravariant functors is covariant, cf. definition 61.4.3).

The evaluation maps of example 61.5.1 are the components of a natural transformation

$$\mathrm{ev}\colon \mathrm{Id} \Rightarrow (-)^{**}$$

with component $\mathrm{ev}_V\colon V \to V^{**}$ at each space V. The naturality square at a linear map $f\colon V \to W$ is

$$\begin{array}{ccc} V & \xrightarrow{\mathrm{ev}_V} & V^{**} \\ {\scriptstyle f}\downarrow & & \downarrow{\scriptstyle f^{**}} \\ W & \xrightarrow[\mathrm{ev}_W]{} & W^{**} \end{array}$$

which is exactly the commuting square proved in Step 5 of example 61.5.1. Restricting to the full subcategory of finite-dimensional spaces, every component ev_V is an isomorphism (Step 4), so ev is a natural isomorphism there and $\mathrm{Id} \cong (-)^{**}$. This is the precise sense in which a finite-dimensional space is canonically its own double dual: not only that each V is isomorphic to V^{**}, but that the isomorphisms are the components of a single natural transformation.

The single dual admits no such transformation, and the reason is worth isolating carefully, since it is a matter of variance. Each application of $(-)^*$ is contravariant, so the single dual is a functor $(-)^*\colon \mathbf{Vect}_k^{\mathrm{op}} \to \mathbf{Vect}_k$, not an endofunctor of $\mathbf{Vect}_k$; the symbol $\mathrm{Id} \Rightarrow (-)^*$ does not even typecheck, because a natural transformation compares two functors of the same variance and the naturality square would need its right edge $f^*\colon W^* \to V^*$ to point the same way as $f\colon V \to W$, which it does not. The comparison is made on the groupoid $\mathbf{Vect}_k^{\mathrm{fd},\cong}$ of finite-dimensional spaces and their isomorphisms, where every morphism is invertible and variance is immaterial; there both Id and $(-)^*$ are genuine endofunctors, so a natural isomorphism $\mathrm{Id} \cong (-)^*$ is a meaningful thing to ask for. None exists: the family of basis-dependent isomorphisms $V \to V^*$ does *not* assemble into a natural transformation, because the naturality square fails for the isomorphisms of V that rescale the chosen basis. Naturality is exactly the property the basis-free construction has and the basis-dependent one lacks.

The contrast in the example is worth stating as a principle. A construction is canonical precisely when it is natural, that is, when its instances at the various objects are the components of a natural transformation. Any construction that requires an arbitrary choice, a basis, a splitting, a lift, fails to be natural, because different choices produce components that violate the naturality square. The vocabulary of natural transformations turns the informal "no choices were made" into a checkable condition on a commuting diagram.

Once natural transformations are in hand, functors between two fixed categories become the objects of a category in their own right, with natural transformations as the morphisms. This packaging is not a formality: it is the setting in which diagrams, presheaves, and much of the rest of the subject live, and it is where the double-dual isomorphism becomes an isomorphism in the literal categorical sense. To build it, one needs to know how natural transformations compose. Given $\alpha\colon F \Rightarrow G$ and $\beta\colon G \Rightarrow H$ between functors $F, G, H\colon C \to D$, the composite is defined componentwise by $(\beta\alpha)_c = \beta_c \circ \alpha_c$, and the identity transformation $1_F\colon F \Rightarrow F$ has components $(1_F)_c = 1_{Fc}$.

Definition 61.5.4: Functor Category

Let C and D be categories. The *functor category* $[C, D]$ (also written D^C) has

- as objects, the functors $F\colon C \to D$;
- as morphisms $F \to G$, the natural transformations $\alpha\colon F \Rightarrow G$.

The identity morphism on a functor F is the natural transformation 1_F with components $(1_F)_c = 1_{Fc}$, and the composite of $\alpha\colon F \Rightarrow G$ with $\beta\colon G \Rightarrow H$ is the natural transformation $\beta\alpha\colon F \Rightarrow H$ with components $(\beta\alpha)_c = \beta_c \circ \alpha_c$.

The definition asserts that $[C, D]$ is a category, and this must be verified: the proposed composite and identities have to be natural transformations, and they have to satisfy the category axioms. The verification is short, and doing it in full shows how the naturality squares of the factors combine.

***Proof*:**
Two things require checking: that $\beta\alpha$ and 1_F are natural transformations, and that composition is associative and unital.

Step 1: the componentwise composite is natural. Let $\alpha\colon F \Rightarrow G$ and $\beta\colon G \Rightarrow H$ be natural, and let $f\colon c \to c'$ be a morphism in C. Naturality of α gives $Gf \circ \alpha_c = \alpha_{c'} \circ Ff$, and naturality of β gives $Hf \circ \beta_c = \beta_{c'} \circ Gf$. Then

$$Hf \circ (\beta\alpha)_c = Hf \circ \beta_c \circ \alpha_c = \beta_{c'} \circ Gf \circ \alpha_c = \beta_{c'} \circ \alpha_{c'} \circ Ff = (\beta\alpha)_{c'} \circ Ff$$

so the naturality square for $\beta\alpha$ commutes. Diagrammatically, the two naturality squares stack vertically and the outer rectangle is what commutes:

$$\begin{array}{ccccc} Fc & \xrightarrow{\alpha_c} & Gc & \xrightarrow{\beta_c} & Hc \\ {\scriptstyle Ff}\downarrow & & \downarrow{\scriptstyle Gf} & & \downarrow{\scriptstyle Hf} \\ Fc' & \xrightarrow[\alpha_{c'}]{} & Gc' & \xrightarrow[\beta_{c'}]{} & Hc' \end{array}$$

Step 2: the identity is natural. For 1_F with components 1_{Fc} and any $f\colon c \to c'$, both routes around the square equal Ff, since $Ff \circ 1_{Fc} = Ff = 1_{Fc'} \circ Ff$. So 1_F is a natural transformation.

Step 3: the category axioms. Composition and identities in $[C, D]$ are defined componentwise, and in each component they are ordinary composition and identities in D. Associativity and the unit laws therefore hold component by component, inherited from the corresponding axioms in D. For a third composable transformation $\gamma\colon H \Rightarrow K$ and each object c,

$$((\gamma\beta)\alpha)_c = \gamma_c\beta_c\alpha_c = (\gamma(\beta\alpha))_c, \qquad (1_G\,\alpha)_c = \alpha_c = (\alpha\,1_F)_c$$

A pair of natural transformations agreeing in every component are equal, so these componentwise identities give the required equalities of natural transformations. Thus $[C, D]$ satisfies the category axioms, completing the proof.

The functor category is the natural home for the double-dual isomorphism. In $[\mathbf{Vect}_k, \mathbf{Vect}_k]$ the transformation $\mathrm{ev}\colon \mathrm{Id} \Rightarrow (-)^{**}$ of example 61.5.3 is a morphism, and because every component is an isomorphism (in finite dimensions) it is an isomorphism in the functor category: the componentwise inverse ev^{-1}, with components $(\mathrm{ev}_V)^{-1}$, is again natural and is a two-sided inverse to ev. So the statement "V is canonically isomorphic to V^{**}" becomes the statement "Id and $(-)^{**}$ are isomorphic objects of the functor category". The composition just defined, taking place along the objects of C, is the *vertical* composition of natural transformations; there is a second, *horizontal* composition that composes transformations between functors that themselves compose, developed when it is needed. Functor categories are already familiar in disguise: when C is a small category and $D = \mathbf{Set}$, an object of $[C, \mathbf{Set}]$ is a diagram of sets shaped like C, and morphisms of diagrams are exactly natural transformations.

Natural isomorphism is also the ingredient needed to fix the notion of sameness for categories themselves. The obvious candidate, isomorphism of categories, asks too much. Two categories C and D would be isomorphic if there were functors $F\colon C \to D$ and $G\colon D \to C$ with $GF = \mathrm{Id}_C$ and $FG = \mathrm{Id}_D$ on the nose, meaning $GFc = c$ for every object c and $GFf = f$ for every morphism. In practice this equality-on-objects requirement is almost never met by the functors one cares about, because the objects of C and D are typically built from different raw material even when the categories carry the same mathematical content. What one wants is that GFc be canonically isomorphic to c, not equal to it, uniformly in c; and "canonically isomorphic, uniformly in c" is precisely a natural isomorphism $GF \cong \mathrm{Id}_C$. Weakening equality to natural isomorphism gives the right notion.

Definition 61.5.5: Equivalence of Categories

An *equivalence of categories* between C and D consists of functors $F\colon C \to D$ and $G\colon D \to C$ together with natural isomorphisms

$$\eta\colon \mathrm{Id}_C \Rightarrow GF \qquad \text{and} \qquad \varepsilon\colon FG \Rightarrow \mathrm{Id}_D$$

(each component an isomorphism). When such data exist, F is an *equivalence*, G is a *quasi-inverse* of F, and the categories C and D are *equivalent*, written $C \simeq D$.

An equivalence relaxes the two rigid equations $GF = \mathrm{Id}_C$ and $FG = \mathrm{Id}_D$ of an isomorphism to the two natural isomorphisms $GF \cong \mathrm{Id}_C$ and $FG \cong \mathrm{Id}_D$. The functor F need not hit every object of D on the nose, nor establish a bijection between objects; it need only do so up to isomorphism and in a way compatible with all morphisms. This is the correct notion of sameness for categories: it identifies categories that carry the same mathematical information even when their objects are packaged differently, and essentially every "two descriptions of the same theory" result in mathematics is an equivalence rather than an isomorphism of categories.

There is a second characterization of equivalences that is usually easier to check than exhibiting a quasi-inverse, phrased entirely in terms of the single functor F. Recall from definition 61.4.1 that F acts on hom-sets by $f \mapsto Ff$; call F *full* if each of these maps $\mathrm{Hom}_C(c, c') \to \mathrm{Hom}_D(Fc, Fc')$ is surjective, *faithful* if each is injective, and *fully faithful* if each is a bijection. Call F *essentially surjective* if every object d of D is isomorphic to Fc for some object c of C. The two conditions together say that F is a bijection on morphisms between any two objects and hits every object up to isomorphism.

Proposition 61.5.6: Characterization of Equivalences

A functor $F\colon C \to D$ is an equivalence of categories if and only if F is full, faithful, and essentially surjective.

The forward direction is elementary and can be given now; the converse requires building a quasi-inverse object by object, and its construction is deferred to the chapter on the Yoneda lemma, where the tools for choosing the components coherently are in place.

***Proof*:**
Only the forward implication is proved here; for the converse, the construction of a quasi-inverse from full faithfulness and essential surjectivity is carried out once the necessary machinery is available, and is taken up later in the book.

Suppose F is an equivalence, with quasi-inverse G and natural isomorphisms $\eta\colon \mathrm{Id}_C \Rightarrow GF$ and $\varepsilon\colon FG \Rightarrow \mathrm{Id}_D$.

Step 1: F is essentially surjective. For any object d of D, the component $\varepsilon_d\colon FGd \to d$ is an isomorphism, so $d \cong Fc$ for $c = Gd$. Every object of D is thus isomorphic to one in the image of F.

Step 2: F is faithful. Let $f, g\colon c \to c'$ satisfy $Ff = Fg$. Applying G gives $GFf = GFg$. Naturality of η at the morphism f gives $GFf \circ \eta_c = \eta_{c'} \circ f$, and likewise for g, so

$$\eta_{c'} \circ f = GFf \circ \eta_c = GFg \circ \eta_c = \eta_{c'} \circ g$$

Since $\eta_{c'}$ is an isomorphism it is monic, and cancelling it gives $f = g$. Thus F is faithful. The identical argument applied to G (with the natural isomorphism ε in place of η) shows G is faithful as well.

Step 3: F is full. Let $h\colon Fc \to Fc'$ be any morphism in D. Set $f = \eta_{c'}^{-1} \circ Gh \circ \eta_c\colon c \to c'$, a morphism of C built from $Gh\colon GFc \to GFc'$ and the isomorphisms η_c, $\eta_{c'}$. Naturality of η at f reads $GFf \circ \eta_c = \eta_{c'} \circ f$, and substituting the definition of f gives $\eta_{c'} \circ f = Gh \circ \eta_c$, whence $GFf = Gh$. Because G is faithful (Step 2), $GFf = Gh$ forces $Ff = h$. So every $h\colon Fc \to Fc'$ is Ff for some f, and F is full, as we sought to show.

The two descriptions of an equivalence serve different purposes. The definition in terms of a quasi-inverse and two natural isomorphisms is the one to use when the inverse construction is at hand and one wants to transport structure back and forth. The characterization by full faithfulness and essential surjectivity is the one to use when only F is given and building an explicit G would be laborious: three conditions on a single functor replace the search for a partner. A concrete instance shows the second criterion at work.

Example 61.5.7: Matrices as an Equivalence

Let k be a field, let $\mathbf{Vect}_k^{\mathrm{fd}}$ be the category of finite-dimensional k-vector spaces and linear maps, and let $\mathbf{Mat}_k$ be the category whose objects are the natural numbers $0, 1, 2, \ldots$ and whose morphisms $m \to n$ are the $n \times m$ matrices over k, with composition given by matrix multiplication and identities the identity matrices (this is the matrix category $\mathbf{Mat}_k$ of example 61.1.4, specialized to $R = k$). Define $F \colon \mathbf{Mat}_k \to \mathbf{Vect}_k^{\mathrm{fd}}$ by $F(n) = k^n$ on objects and by sending an $n \times m$ matrix A to the linear map $k^m \to k^n$, $x \mapsto Ax$.

The claim is that F is an equivalence, verified through proposition 61.5.6.

- *Fully faithful.* A linear map $k^m \to k^n$ is represented, with respect to the standard bases, by a unique $n \times m$ matrix, and every such matrix arises this way. So $\mathbf{Mat}_k(m, n) \to \mathrm{Hom}_k(k^m, k^n)$, $A \mapsto (x \mapsto Ax)$, is a bijection: F is full and faithful.
- *Essentially surjective.* Every finite-dimensional space V has a basis of some size n, and choosing one gives an isomorphism $V \cong k^n = F(n)$ (see [21, Vector Space has Basis, Basis iff Free]). So every object of $\mathbf{Vect}_k^{\mathrm{fd}}$ is isomorphic to one in the image of F.

Hence F is an equivalence, and $\mathbf{Mat}_k \simeq \mathbf{Vect}_k^{\mathrm{fd}}$.

The equivalence in the example is not an isomorphism of categories, and the reason is instructive. The objects of $\mathbf{Mat}_k$ are natural numbers, while the objects of $\mathbf{Vect}_k^{\mathrm{fd}}$ are vector spaces; there are a proper class of two-dimensional spaces but only one object 2 in $\mathbf{Mat}_k$, so no functor can be a bijection on objects and $GF = \mathrm{Id}$ cannot hold on the nose. Yet the two categories carry identical information: linear algebra on finite-dimensional spaces is the theory of matrices up to change of basis, and the equivalence is the exact expression of that identity. This is the recurring pattern. Equivalence, not isomorphism, is the notion of sameness for categories, because it records that two categories have the same objects and morphisms up to canonical isomorphism, which is all that the categorical viewpoint, where an object is known only through its morphisms, can or should ask.

62

The Yoneda Lemma and Representability

Chapter 1 built the categorical language and returned to one thread: an object is determined by its morphisms. This chapter makes it a theorem. The *representable functor* $\mathrm{Hom}(c, -)$ records how an object c maps to every other; the *Yoneda lemma* computes its natural transformations into any set-valued functor, and the *Yoneda embedding* recovers c from the presheaf it represents. Along the way we settle questions left open in Chapter 1, among them the converse of the equivalence characterization (proposition 61.5.6).

62.1 Representable Functors

The first step toward the Yoneda lemma is to package the morphisms out of a fixed object as a functor. Fixing an object c of a locally small category and letting the second slot of the hom-set vary produces a set-valued functor; the functors that arise this way, and the objects that produce them, are the subject of this section. A functor isomorphic to one of these is *representable*, and the isomorphism is pinned down by a single element, the universal element.

We work throughout in a locally small category C (definition 61.1.7), so that each collection $\mathrm{Hom}_C(x, y)$ is a set.

Definition 62.1.1: Representable Functor

Let C be locally small and c an object of C. The *covariant hom-functor*

$$\mathrm{Hom}(c,-)\colon C \to \mathbf{Set}$$

sends an object x to the set $\mathrm{Hom}(c,x)$ and a morphism $f\colon x \to y$ to *post-composition*

$$f_*\colon \mathrm{Hom}(c,x) \to \mathrm{Hom}(c,y), \qquad f_*(h) = fh$$

The *contravariant hom-functor*

$$\mathrm{Hom}(-,c)\colon C^{\mathrm{op}} \to \mathbf{Set}$$

sends x to $\mathrm{Hom}(x,c)$ and $f\colon x \to y$ to *pre-composition*

$$f^*\colon \mathrm{Hom}(y,c) \to \mathrm{Hom}(x,c), \qquad f^*(h) = hf$$

A functor $F\colon C \to \mathbf{Set}$ is *representable* if there is an object c and a natural isomorphism $F \cong \mathrm{Hom}(c,-)$; the object c is a *representing object* for F. Dually, a functor $F\colon C^{\mathrm{op}} \to \mathbf{Set}$ is *representable* if $F \cong \mathrm{Hom}(-,c)$ for some c.

Functoriality of $\mathrm{Hom}(c,-)$ is the two composition laws of C: for $f\colon x \to y$ and $g\colon y \to z$ one has $(gf)_*(h) = gfh = g_*(f_*(h))$, so $(gf)_* = g_*f_*$, and $(1_x)_*(h) = h$, so $(1_x)_* = 1_{\mathrm{Hom}(c,x)}$. The same identities read backwards give $(gf)^* = f^*g^*$, the order-reversal that makes $\mathrm{Hom}(-,c)$ contravariant. A representing object, if one exists, is a solution to the problem posed by F: it is an object whose maps out of it (or into it) reproduce the sets Fx compatibly with all the morphisms of C. Chapter 1 already showed how much a hom-set encodes, since a morphism is an isomorphism exactly when post-composition with it is a bijection of hom-sets for every test object (example 61.1.8 recorded the first instances); here the hom-set is promoted from a single set to a functor.

Example 62.1.2: The Underlying Set of a Group

The forgetful functor $U\colon \mathbf{Grp} \to \mathbf{Set}$, sending a group to its underlying set and a homomorphism to its underlying function, is representable, and the integers $\mathbb{Z}$ represent it. A homomorphism $\mathbb{Z} \to G$ is determined by the image of the generator 1, and any element of G is a legitimate image, so

$$\mathrm{Hom}_{\mathbf{Grp}}(\mathbb{Z},G) \cong UG, \qquad \varphi \mapsto \varphi(1)$$

This bijection is natural in G: for a homomorphism $\psi\colon G \to H$ the square comparing $\varphi \mapsto \varphi(1)$ on either side commutes, since $(\psi\varphi)(1) = \psi(\varphi(1))$. So $U \cong \mathrm{Hom}_{\mathbf{Grp}}(\mathbb{Z},-)$. That $\mathbb{Z}$ is the free group on one generator ([21, Free Groups]) is exactly the statement that it represents the underlying-set functor.

A representing object is a compressed description of a whole functor, and the examples of most interest name a construction the reader already knows. Before collecting more of them it is worth isolating the contravariant case, where the objects of the represented functor are the presheaves.

Definition 62.1.3: Presheaf

A *presheaf* on a category C is a functor $F\colon C^{\mathrm{op}} \to \mathbf{Set}$. Presheaves on C, together with natural transformations between them, form the *presheaf category*

$$\mathbf{PSh}(C) = [C^{\mathrm{op}}, \mathbf{Set}]$$

the functor category (definition 61.5.4) of contravariant set-valued functors on C.

For each object c the contravariant hom-functor $\mathrm{Hom}(-, c)$ is a presheaf, the *presheaf represented by* c; a presheaf isomorphic to some $\mathrm{Hom}(-, c)$ is representable in the sense of definition 62.1.1. The two variances are best seen together. Holding neither slot of the hom-set fixed gives a functor of both arguments at once.

Definition 62.1.4: The Two-Sided Hom-Bifunctor

Let C be locally small. The *hom-bifunctor*

$$\mathrm{Hom}(-,-)\colon C^{\mathrm{op}} \times C \to \mathbf{Set}$$

sends an object (x, y) to $\mathrm{Hom}(x, y)$ and a morphism $(f, g)\colon (x, y) \to (x', y')$, i.e. a pair $f\colon x' \to x$ in C and $g\colon y \to y'$ in C, to

$$\mathrm{Hom}(x, y) \to \mathrm{Hom}(x', y'), \qquad h \mapsto ghf$$

Functoriality is one line: given a second pair $(f', g')\colon (x', y') \to (x'', y'')$, composing the induced maps sends h to $g'(ghf)f' = (g'g)h(ff')$, which is the map induced by the composite $(f', g')(f, g) = (ff', g'g)$ in $C^{\mathrm{op}} \times C$; and the identity pair $(1_x, 1_y)$ induces $h \mapsto h$. Fixing the first slot at c recovers $\mathrm{Hom}(c, -)$ and fixing the second recovers $\mathrm{Hom}(-, c)$, so the bifunctor is the common source of both hom-functors.

The definition of representability quantifies over all objects and all elements at once, through the natural isomorphism. It has a pointwise reformulation carried by a single piece of data. An isomorphism $F \cong \mathrm{Hom}(c, -)$ is pinned down by where the identity 1_c goes, and the element of Fc it corresponds to satisfies a universal property that says exactly "every element of every Fd factors through it uniquely."

Definition 62.1.5: Universal Element

Let $F\colon C \to \mathbf{Set}$. A *universal element* of F is a pair (c, x) with c an object of C and $x \in Fc$ such that for every object d and every $y \in Fd$ there is a unique morphism $f\colon c \to d$ with $(Ff)(x) = y$.

The pair (c, x) is universal in that every element of the functor is obtained from x by transport along a unique morphism. The following makes precise that a universal element is the same data as a representation.

Proposition 62.1.6: Representability by a Universal Element

A functor $F\colon C \to \mathbf{Set}$ is representable if and only if it has a universal element. Explicitly, a natural isomorphism $\alpha\colon \mathrm{Hom}(c,-) \Rightarrow F$ corresponds to the universal element (c,x) with $x = \alpha_c(1_c)$, and conversely every universal element arises this way from a unique natural isomorphism.

***Proof*:**

Step 1: A representation gives a universal element. Suppose $\alpha\colon \mathrm{Hom}(c,-) \Rightarrow F$ is a natural isomorphism, and set $x = \alpha_c(1_c) \in Fc$. Fix an object d and an element $y \in Fd$. Naturality of α at a morphism $f\colon c \to d$ is the commuting square

$$\begin{array}{ccc} \mathrm{Hom}(c,c) & \xrightarrow{\alpha_c} & Fc \\ {\scriptstyle f_*}\downarrow & & \downarrow{\scriptstyle Ff} \\ \mathrm{Hom}(c,d) & \xrightarrow[\alpha_d]{} & Fd \end{array}$$

Chasing 1_c around it gives $\alpha_d(f) = \alpha_d(f_*(1_c)) = (Ff)(\alpha_c(1_c)) = (Ff)(x)$. Thus for every $f \in \mathrm{Hom}(c,d)$,

$$\alpha_d(f) = (Ff)(x) \tag{62.1}$$

Since α_d is a bijection, for the given $y \in Fd$ there is exactly one $f\colon c \to d$ with $\alpha_d(f) = y$, that is, exactly one f with $(Ff)(x) = y$. So (c,x) is a universal element.

Step 2: A universal element gives a representation. Conversely, let (c,x) be a universal element of F. Define, for each object d, a map

$$\alpha_d\colon \mathrm{Hom}(c,d) \to Fd, \qquad \alpha_d(f) = (Ff)(x)$$

The universal property says precisely that for each $y \in Fd$ there is a unique $f\colon c \to d$ with $(Ff)(x) = y$, which is the statement that α_d is a bijection. The maps α_d are natural: for $g\colon d \to d'$ and $f\colon c \to d$,

$$\alpha_{d'}(g_*(f)) = \alpha_{d'}(gf) = (F(gf))(x) = (Fg)((Ff)(x)) = (Fg)(\alpha_d(f))$$

so the naturality square for g commutes. Hence $\alpha\colon \mathrm{Hom}(c,-) \Rightarrow F$ is a natural isomorphism, and F is representable.

Step 3: The two constructions are inverse. A representation α produces $x = \alpha_c(1_c)$, and (62.1) shows that the representation rebuilt from x in Step 2 has components $f \mapsto (Ff)(x) = \alpha_d(f)$, recovering α. In the other direction, the representation built from (c,x) in Step 2 sends 1_c to $(F1_c)(x) = x$, recovering the element. So the correspondence is a bijection between representations and universal elements, completing the proof.

The proposition converts a question about a natural isomorphism, which involves a component at every object, into a question about one element and its universal property. Verifying representability then reduces to exhibiting a single x and checking that every y factors through it uniquely, as the following examples show.

Example 62.1.7: Representable Functors

1. The identity functor on **Set** is representable, with representing object a one-point set $1 = \{*\}$. A function $1 \to X$ is a choice of a point of X, so $\mathrm{Hom}_{\mathbf{Set}}(1, X) \cong X$ by $\varphi \mapsto \varphi(*)$, naturally in X. The universal element is the pair $(1, *)$: every element y of every set X is $(Ff)(*) = f(*)$ for the unique $f\colon 1 \to X$ with $f(*) = y$.

2. The contravariant powerset $P\colon \mathbf{Set}^{\mathrm{op}} \to \mathbf{Set}$, sending a set X to its powerset PX and a function $f\colon X \to Y$ to the preimage map $f^{-1}\colon PY \to PX$, is a representable presheaf. Let $2 = \{0, 1\}$. A subset $A \subseteq X$ is the same data as its indicator function $\chi_A\colon X \to 2$, with $\chi_A(a) = 1$ exactly when $a \in A$, and this correspondence is a bijection

$$PX \cong \mathrm{Hom}_{\mathbf{Set}}(X, 2), \qquad A \mapsto \chi_A$$

   It is natural in X: for $f\colon X \to Y$ and $B \subseteq Y$, the indicator of $f^{-1}(B)$ is $\chi_B \circ f$, which is exactly $f^*(\chi_B)$. So $P \cong \mathrm{Hom}_{\mathbf{Set}}(-, 2)$, and 2 is the representing object. The universal element is the pair $(2, U)$ with $U = \{1\} \subseteq 2$: every subset $A \subseteq X$ is the preimage $\chi_A^{-1}(U)$ under a unique map $X \to 2$.

62.2 The Yoneda Lemma

The representable functor $\mathrm{Hom}(c, -)$ of definition 62.1.1 records how c maps to every object of C. This section computes the natural transformations out of it. The answer, the Yoneda lemma, is that a natural transformation from $\mathrm{Hom}(c, -)$ to a set-valued functor F is the same thing as a single element of Fc: the whole transformation is pinned down by where it sends the identity 1_c. The embedding of the next section and everything that follows rest on this computation. The mechanism can be described before any proof. A natural transformation $\alpha\colon \mathrm{Hom}(c, -) \Rightarrow F$ has, at each object d, a component $\alpha_d\colon \mathrm{Hom}(c, d) \to Fd$. The set $\mathrm{Hom}(c, c)$ holds a distinguished element, the identity 1_c, and α_c sends it to some $\alpha_c(1_c) \in Fc$. Naturality forces every other value of every component to be determined by this one element: for $f\colon c \to d$, naturality applied to f and evaluated at 1_c expresses $\alpha_d(f)$ through $\alpha_c(1_c)$. Reading off $\alpha_c(1_c)$ is thus a map from natural transformations to Fc, and the lemma is that it is a bijection.

Theorem 62.2.1: The Yoneda Lemma

Let C be a locally small category, c an object of C, and $F\colon C \to \mathbf{Set}$ a functor. Evaluation at the identity,

$$\Phi\colon \mathrm{Nat}(\mathrm{Hom}(c, -), F) \to Fc, \qquad \Phi(\alpha) = \alpha_c(1_c)$$

is a bijection, natural in both c and F.

The proof produces an explicit inverse and checks that the two maps compose to the identity in each order. The inverse takes an element $x \in Fc$ and builds a natural transformation from it; the functoriality of F is what makes that transformation natural.

***Proof*:**
Step 1: the inverse map. Fix $x \in Fc$. Define a family $\Psi(x)$ by giving, at each object d, the component

$$\Psi(x)_d \colon \mathrm{Hom}(c,d) \to Fd, \qquad \Psi(x)_d(f) = (Ff)(x)$$

for $f \colon c \to d$, where $Ff \colon Fc \to Fd$ is the action of F on f. This is well-defined: Ff is a function $Fc \to Fd$ and $x \in Fc$, so $(Ff)(x) \in Fd$.

The claim is that $\Psi(x)$ is a natural transformation $\mathrm{Hom}(c,-) \Rightarrow F$. Let $g \colon d \to d'$ be a morphism of C. The functor $\mathrm{Hom}(c,-)$ sends g to post-composition $g_* \colon \mathrm{Hom}(c,d) \to \mathrm{Hom}(c,d')$, $g_*(f) = gf$. The naturality square to check is

$$\begin{array}{ccc} \mathrm{Hom}(c,d) & \xrightarrow{\Psi(x)_d} & Fd \\ {\scriptstyle g_*}\downarrow & & \downarrow{\scriptstyle Fg} \\ \mathrm{Hom}(c,d') & \xrightarrow[\Psi(x)_{d'}]{} & Fd' \end{array}$$

Chase $f \colon c \to d$ around both routes. Down then across gives $\Psi(x)_{d'}(g_*(f)) = \Psi(x)_{d'}(gf) = (F(gf))(x)$; across then down gives $(Fg)(\Psi(x)_d(f)) = (Fg)((Ff)(x))$. These agree because F is a functor, $F(gf) = Fg \circ Ff$, so

$$(F(gf))(x) = (Fg \circ Ff)(x) = (Fg)((Ff)(x))$$

The square commutes for every g, so $\Psi(x)$ is natural, and $\Psi \colon Fc \to \mathrm{Nat}(\mathrm{Hom}(c,-),F)$, $x \mapsto \Psi(x)$, is a well-defined candidate inverse to Φ.

Step 2: Φ and Ψ are mutually inverse. There are two composites to compute.

First, $\Phi\Psi = 1_{Fc}$. For $x \in Fc$,

$$\Phi(\Psi(x)) = \Psi(x)_c(1_c) = (F1_c)(x) = 1_{Fc}(x) = x$$

using that F preserves identities, $F1_c = 1_{Fc}$. This direction is immediate.

Second, $\Psi\Phi$ is the identity on $\mathrm{Nat}(\mathrm{Hom}(c,-),F)$. Let $\alpha \colon \mathrm{Hom}(c,-) \Rightarrow F$ be given and put $x = \Phi(\alpha) = \alpha_c(1_c)$. Two natural transformations agree exactly when all components agree, so it suffices to show $\Psi(x)_d = \alpha_d$ for every d. Fix d and $f \colon c \to d$. Naturality of α at f is the commuting square

$$\begin{array}{ccc} \mathrm{Hom}(c,c) & \xrightarrow{\alpha_c} & Fc \\ {\scriptstyle f_*}\downarrow & & \downarrow{\scriptstyle Ff} \\ \mathrm{Hom}(c,d) & \xrightarrow[\alpha_d]{} & Fd \end{array}$$

Evaluate it at $1_c \in \mathrm{Hom}(c,c)$. Down then across gives $\alpha_d(f_*(1_c)) = \alpha_d(f1_c) = \alpha_d(f)$; across then down gives $(Ff)(\alpha_c(1_c)) = (Ff)(x)$. Equating the routes,

$$\alpha_d(f) = (Ff)(x) = \Psi(x)_d(f)$$

Since f and d were arbitrary, $\alpha_d = \Psi(x)_d$ for all d, so $\alpha = \Psi(\Phi(\alpha))$. Both composites are identities, so Φ is a bijection with inverse Ψ.

Step 3: naturality of the bijection. The source and target of Φ each depend on the pair (c,F), and the claim is that Φ commutes with change of F and change of c. Consider F first, with c

fixed. A natural transformation $\theta\colon F \Rightarrow G$ acts on the target by its component $\theta_c\colon Fc \to Gc$ and on the source by post-composition $\alpha \mapsto \theta\alpha$, carrying $\mathrm{Hom}(c,-) \Rightarrow F$ to $\mathrm{Hom}(c,-) \Rightarrow G$. Naturality in F is the square

$$\begin{array}{ccc} \mathrm{Nat}(\mathrm{Hom}(c,-),F) & \xrightarrow{\Phi_F} & Fc \\ {\scriptstyle \theta\circ(-)}\downarrow & & \downarrow{\scriptstyle \theta_c} \\ \mathrm{Nat}(\mathrm{Hom}(c,-),G) & \xrightarrow[\Phi_G]{} & Gc \end{array}$$

For $\alpha\colon \mathrm{Hom}(c,-) \Rightarrow F$, down then across gives $\Phi_G(\theta\alpha) = (\theta\alpha)_c(1_c) = \theta_c(\alpha_c(1_c))$, since composition of natural transformations is componentwise (definition 61.5.4); across then down gives $\theta_c(\Phi_F(\alpha)) = \theta_c(\alpha_c(1_c))$. The two agree, so Φ is natural in F.

Now fix F and vary c. A morphism $h\colon c \to c'$ acts on the target by $Fh\colon Fc \to Fc'$. On the source it acts by precomposition with the representable's own functoriality: h induces $\mathrm{Hom}(h,-)\colon \mathrm{Hom}(c',-) \Rightarrow \mathrm{Hom}(c,-)$, whose component $\mathrm{Hom}(h,d)$ at d sends $k \in \mathrm{Hom}(c',d)$ to $kh \in \mathrm{Hom}(c,d)$, and a transformation $\alpha\colon \mathrm{Hom}(c,-) \Rightarrow F$ is carried to $\alpha \circ \mathrm{Hom}(h,-)\colon \mathrm{Hom}(c',-) \Rightarrow F$. Naturality in c is the square

$$\begin{array}{ccc} \mathrm{Nat}(\mathrm{Hom}(c,-),F) & \xrightarrow{\Phi_c} & Fc \\ {\scriptstyle (-)\circ\mathrm{Hom}(h,-)}\downarrow & & \downarrow{\scriptstyle Fh} \\ \mathrm{Nat}(\mathrm{Hom}(c',-),F) & \xrightarrow[\Phi_{c'}]{} & Fc' \end{array}$$

Take $\alpha\colon \mathrm{Hom}(c,-) \Rightarrow F$. Across then down gives $Fh(\Phi_c(\alpha)) = (Fh)(\alpha_c(1_c))$. Down then across gives

$$\Phi_{c'}(\alpha \circ \mathrm{Hom}(h,-)) = \big(\alpha \circ \mathrm{Hom}(h,-)\big)_{c'}(1_{c'}) = \alpha_{c'}\big(\mathrm{Hom}(h,c')(1_{c'})\big) = \alpha_{c'}(1_{c'}\, h) = \alpha_{c'}(h)$$

To match the two, apply naturality of α (a transformation $\mathrm{Hom}(c,-) \Rightarrow F$) at the morphism $h\colon c \to c'$: its square is

$$\begin{array}{ccc} \mathrm{Hom}(c,c) & \xrightarrow{\alpha_c} & Fc \\ {\scriptstyle h_*}\downarrow & & \downarrow{\scriptstyle Fh} \\ \mathrm{Hom}(c,c') & \xrightarrow[\alpha_{c'}]{} & Fc' \end{array}$$

Evaluated at $1_c \in \mathrm{Hom}(c,c)$, down then across gives $\alpha_{c'}(h_*(1_c)) = \alpha_{c'}(h1_c) = \alpha_{c'}(h)$; across then down gives $(Fh)(\alpha_c(1_c))$. Hence $\alpha_{c'}(h) = (Fh)(\alpha_c(1_c))$, which is exactly the equality of the two routes around the outer square. So Φ is natural in c, completing the proof.

Out of a lone element $x \in Fc$ the map Ψ manufactures an entire natural family $\{(Ff)(x)\}_f$, one function per object, coherent across every morphism. Nothing beyond the functoriality of F went into the construction, which is why the correspondence is as tight as it is: the data of a natural transformation, a priori a large amount of information spread over all objects, collapses to one point of a single set.

A first payoff sets $F = \mathrm{Hom}(c',-)$ for a second object c'. Then $Fc = \mathrm{Hom}(c',c)$, and the lemma reads $\mathrm{Nat}(\mathrm{Hom}(c,-),\mathrm{Hom}(c',-)) \cong \mathrm{Hom}(c',c)$: natural transformations between two representables are exactly the morphisms of C in the reverse direction. This is the computation on which the next

section builds the Yoneda embedding.

Example 62.2.2: The Underlying Set as a Representable

Let $F\colon \mathbf{Grp} \to \mathbf{Set}$ be the forgetful functor, sending a group to its underlying set. It is represented by the free group $\mathbb{Z}$ on one generator: a homomorphism $\mathbb{Z} \to G$ is determined by, and freely choosable as, the image of the generator 1, so evaluation at 1 gives a bijection $\mathrm{Hom}_{\mathbf{Grp}}(\mathbb{Z}, G) \cong FG$ natural in G (definition 62.1.1). The Yoneda lemma names the element of $F\mathbb{Z} = \mathbb{Z}$ that encodes this: it is

$$\Phi(\alpha) = \alpha_{\mathbb{Z}}(1_{\mathbb{Z}}) \in F\mathbb{Z} = \mathbb{Z}$$

the image, under the natural isomorphism $\alpha\colon \mathrm{Hom}(\mathbb{Z}, -) \Rightarrow F$, of the identity homomorphism $1_{\mathbb{Z}}$. Tracing the definitions, $\alpha_{\mathbb{Z}}(1_{\mathbb{Z}})$ is the generator $1 \in \mathbb{Z}$, and the whole isomorphism α is recovered from it by $\alpha_G(\varphi) = (F\varphi)(1) = \varphi(1)$, the image of the generator under $\varphi\colon \mathbb{Z} \to G$. The single element $1 \in \mathbb{Z}$ carries the entire natural family.

The presheaf version is the same statement read in C^{op}. Recall the duality principle (box 61.3.3): a statement provable for every locally small category holds equally for every opposite. Applying the Yoneda lemma in C^{op} turns the covariant representable $\mathrm{Hom}_{C^{\mathrm{op}}}(c, -)$ into the contravariant $\mathrm{Hom}_C(-, c)$, and a covariant functor $C^{\mathrm{op}} \to \mathbf{Set}$ is a presheaf on C (definition 62.1.3). No new argument is needed.

Corollary 62.2.3: The Yoneda Lemma, Presheaf Form

Let C be a locally small category, c an object of C, and $F\colon C^{\mathrm{op}} \to \mathbf{Set}$ a presheaf. Evaluation at the identity,

$$\mathrm{Nat}(\mathrm{Hom}(-, c), F) \to Fc, \qquad \alpha \mapsto \alpha_c(1_c)$$

is a bijection, natural in c and F.

***Proof*:**

The Yoneda lemma holds in every locally small category, and by the duality principle it applies in particular to C^{op}, which is again locally small (box 61.3.3). Applied there to the object c and the functor F, the covariant representable of C^{op} at c is $\mathrm{Hom}_{C^{\mathrm{op}}}(c, -) = \mathrm{Hom}_C(-, c)$ read in the free variable, and a functor $F\colon C^{\mathrm{op}} \to \mathbf{Set}$ is precisely a covariant functor on C^{op}. So theorem 62.2.1 yields the bijection $\mathrm{Nat}(\mathrm{Hom}_C(-, c), F) \cong Fc$, with the same evaluation-at-1_c map and the same naturality in c and F, as required.

The two forms are one theorem seen from two sides, and both will be used: the covariant form for functors out of C, the presheaf form for the embedding $c \mapsto \mathrm{Hom}(-, c)$ into presheaves.

The lemma also closes the loop with the universal element of section 62.1. An element $x \in Fc$ is called universal when every $y \in Fd$ arises as $(Ff)(x)$ for a unique $f\colon c \to d$ (definition 62.1.5), and F is representable exactly when such an x exists. Under the Yoneda bijection x corresponds to the transformation $\Psi(x)\colon \mathrm{Hom}(c, -) \Rightarrow F$ with $\Psi(x)_d(f) = (Ff)(x)$, and x is universal precisely when every $\Psi(x)_d$ is a bijection, that is, when $\Psi(x)$ is a natural isomorphism. So the representable-iff-universal-element statement is the Yoneda lemma specialized to a representable F: the universal element is the point of Fc that Yoneda hands back, and for $F = \mathrm{Hom}(c, -)$ itself it is the identity 1_c, the element from which the whole representable is generated.

62.3 The Yoneda Embedding

The Yoneda lemma of the previous section computes the natural transformations out of a representable functor. Read one way, it is a calculation; read another, it says that the assignment $c \mapsto \mathrm{Hom}(-, c)$ loses no information. This section makes that reading precise. Packaging the contravariant representables into a single functor $\mathbf{y}\colon C \to \mathbf{PSh}(C)$, the presheaf form of the lemma becomes the statement that $\mathbf{y}$ is fully faithful, and full faithfulness in turn says that an object is recovered, up to isomorphism, from the presheaf it represents.

Recall from definition 62.1.3 that $\mathbf{PSh}(C) = [C^{\mathrm{op}}, \mathbf{Set}]$ is the category of presheaves on C, whose objects are the contravariant set-valued functors and whose morphisms are natural transformations. Each object c of C gives such a presheaf, the represented $\mathrm{Hom}(-, c)$ of definition 62.1.1; each morphism of C gives a natural transformation between two of them. Assembling these into a functor is the content of the first definition.

Definition 62.3.1: The Yoneda Embedding

Let C be a locally small category (definition 61.1.7). The *Yoneda embedding* is the functor

$$\mathbf{y}\colon C \to \mathbf{PSh}(C)$$

defined as follows. On an object c, it is the represented presheaf

$$\mathbf{y}(c) = \mathrm{Hom}(-, c) \in \mathbf{PSh}(C)$$

On a morphism $f\colon c \to d$, it is the natural transformation

$$\mathbf{y}(f) = \mathrm{Hom}(-, f)\colon \mathrm{Hom}(-, c) \Rightarrow \mathrm{Hom}(-, d)$$

whose component at an object x is post-composition with f,

$$\mathrm{Hom}(-, f)_x\colon \mathrm{Hom}(x, c) \to \mathrm{Hom}(x, d), \qquad g \mapsto fg$$

That $\mathbf{y}$ is a functor is exactly the statement that its two clauses respect composition and identities, and both follow from the category axioms of C. The verification is short and worth doing once, because it exhibits how the unit and associativity laws of composition become the functoriality of $\mathbf{y}$.

***Proof*:**
Two checks are needed: that each $\mathbf{y}(f)$ is a natural transformation, and that $\mathbf{y}$ preserves composites and identities.

Step 1: $\mathbf{y}(f)$ is natural. Fix $f\colon c \to d$ and a morphism $h\colon x' \to x$ in C. The presheaf $\mathrm{Hom}(-, c)$ sends h to pre-composition $\mathrm{Hom}(h, c)\colon \mathrm{Hom}(x, c) \to \mathrm{Hom}(x', c)$, $g \mapsto gh$, and similarly for $\mathrm{Hom}(-, d)$. Naturality of $\mathbf{y}(f) = \mathrm{Hom}(-, f)$ at h is the commuting of

$$\begin{array}{ccc} \mathrm{Hom}(x, c) & \xrightarrow{g \mapsto fg} & \mathrm{Hom}(x, d) \\ {\scriptstyle g \mapsto gh}\downarrow & & \downarrow{\scriptstyle g \mapsto gh} \\ \mathrm{Hom}(x', c) & \xrightarrow[g \mapsto fg]{} & \mathrm{Hom}(x', d) \end{array}$$

Both routes send $g\colon x \to c$ to $f(gh)$: down-then-across gives $f(gh)$, across-then-down gives $(fg)h$, and these agree by associativity of composition in C. So $\mathbf{y}(f)$ is natural.

Step 2: $\mathbf{y}$ *preserves composition.* Let $f\colon c \to d$ and $f'\colon d \to e$. Both $\mathbf{y}(f'f)$ and $\mathbf{y}(f')\mathbf{y}(f)$ are natural transformations $\mathrm{Hom}(-,c) \Rightarrow \mathrm{Hom}(-,e)$, so it suffices to compare their components at each object x. On $g\colon x \to c$,

$$\mathbf{y}(f'f)_x(g) = (f'f)g, \qquad \big(\mathbf{y}(f')\mathbf{y}(f)\big)_x(g) = f'(fg)$$

and $(f'f)g = f'(fg)$ by associativity. Hence $\mathbf{y}(f'f) = \mathbf{y}(f')\mathbf{y}(f)$.

Step 3: $\mathbf{y}$ *preserves identities.* The component of $\mathbf{y}(1_c)$ at x sends $g\colon x \to c$ to $1_c g = g$, so it is the identity function on $\mathrm{Hom}(x,c)$. As this holds for every x, $\mathbf{y}(1_c) = 1_{\mathrm{Hom}(-,c)}$, the identity natural transformation on $\mathbf{y}(c)$.

Naturality of each $\mathbf{y}(f)$, preservation of composites, and preservation of identities together make $\mathbf{y}$ a functor, completing the proof.

The proof isolates a small dictionary: associativity of composition in C becomes both the naturality of each $\mathbf{y}(f)$ and the functoriality of $\mathbf{y}$, and the left unit law becomes the preservation of identities. The embedding carries an object to the record of all maps into it and a morphism to post-composition with that morphism, and this record transforms functorially because composition does. A concrete category shows the abstract assignment.

Example 62.3.2: The Yoneda Embedding of a Poset

Let P be a poset, regarded as a category with a single morphism $x \to y$ whenever $x \leq y$ and none otherwise (definition 61.1.1). For objects x, y the hom-set $\mathrm{Hom}(x,y)$ is a one-element set when $x \leq y$ and empty otherwise, so a presheaf $\mathrm{Hom}(-,c) = \mathbf{y}(c)$ on P is the indicator of the down-set of c: for each object x,

$$\mathrm{Hom}(x,c) = \begin{cases} \{*\} & x \leq c \\ \varnothing & x \not\leq c \end{cases}$$

Thus $\mathbf{y}(c)$ records precisely which elements lie below c, that is, the principal down-set $\downarrow c = \{x \in P \,|\, x \leq c\}$. A morphism $c \leq d$ in P gives the natural transformation $\mathbf{y}(c \leq d)\colon \mathrm{Hom}(-,c) \Rightarrow \mathrm{Hom}(-,d)$, which at each x is the unique function from $\mathrm{Hom}(x,c)$ to $\mathrm{Hom}(x,d)$; such a function exists as a morphism of presheaves exactly because $x \leq c \leq d$ forces $x \leq d$, so the down-set of c is contained in that of d. The embedding $\mathbf{y}\colon P \to \mathbf{PSh}(P)$ is therefore the assignment $c \mapsto \downarrow c$ sending each element to its principal down-set, ordered by inclusion. Since $c \leq d$ if and only if $\downarrow c \subseteq \downarrow d$, distinct elements have distinct down-sets and the order is faithfully reproduced: $\mathbf{y}$ is the poset embedding of P into its lattice of down-sets. This is the order-theoretic case of the full faithfulness proved next.

The example already displays the pattern of the general theorem. The embedding of a poset is injective on objects and reflects the order, so the whole of P can be read off from its image in $\mathbf{PSh}(P)$. For a general category the statement is not that $\mathbf{y}$ is injective on objects, which is too rigid, but that it is a bijection on morphisms between any two objects, full and faithful in the sense recalled from proposition 61.5.6. This is where the Yoneda lemma does the work: its presheaf form, applied to a represented presheaf, is precisely the assertion that $\mathbf{y}$ is fully faithful.

Theorem 62.3.3: The Yoneda Embedding is Fully Faithful

Let C be a locally small category. For all objects c, d of C the function

$$\mathrm{Hom}_C(c,d) \to \mathrm{Hom}_{\mathbf{PSh}(C)}\big(\mathbf{y}(c),\mathbf{y}(d)\big) = \mathrm{Nat}\big(\mathrm{Hom}(-,c),\mathrm{Hom}(-,d)\big), \qquad f \mapsto \mathbf{y}(f)$$

is a bijection. Equivalently, the Yoneda embedding $\mathbf{y}\colon C \to \mathbf{PSh}(C)$ is full and faithful.

***Proof*:**
Apply the presheaf form of the Yoneda lemma, corollary 62.2.3, to the presheaf $F = \mathrm{Hom}(-,d)$ and the object c. It gives a bijection

$$\mathrm{Nat}\big(\mathrm{Hom}(-,c),\mathrm{Hom}(-,d)\big) \xrightarrow{\cong} \big(\mathrm{Hom}(-,d)\big)(c) = \mathrm{Hom}_C(c,d) \tag{62.2}$$

natural in c and d. The bijection of (62.2) sends a natural transformation $\alpha\colon \mathrm{Hom}(-,c) \Rightarrow \mathrm{Hom}(-,d)$ to the element $\alpha_c(1_c) \in \mathrm{Hom}_C(c,d)$, the image of the identity 1_c under the component of α at c. The claimed map $f \mapsto \mathbf{y}(f)$ runs the other way, so it suffices to check that the two are mutually inverse. In fact $f \mapsto \mathbf{y}(f)$ is exactly the inverse produced by corollary 62.2.3, and identifying it is the whole content of the theorem.

Step 1: the Yoneda bijection sends $\mathbf{y}(f)$ to f. Take $\alpha = \mathbf{y}(f) = \mathrm{Hom}(-,f)$ for a morphism $f\colon c \to d$. Its component at c is post-composition with f, so it sends the identity to

$$\big(\mathbf{y}(f)\big)_c(1_c) = f \circ 1_c = f$$

Thus the composite $\mathrm{Hom}_C(c,d) \to \mathrm{Nat}(\mathrm{Hom}(-,c),\mathrm{Hom}(-,d)) \to \mathrm{Hom}_C(c,d)$, first $f \mapsto \mathbf{y}(f)$ and then the bijection of (62.2), is the identity on $\mathrm{Hom}_C(c,d)$.

Step 2: the other composite is the identity. The map of (62.2) is already a bijection by corollary 62.2.3, and Step 1 shows $f \mapsto \mathbf{y}(f)$ is a right inverse to it. A right inverse to a bijection is its two-sided inverse, so $f \mapsto \mathbf{y}(f)$ is itself a bijection, inverse to the Yoneda bijection. Concretely, starting from a natural transformation α, its image $f = \alpha_c(1_c)$ satisfies $\mathbf{y}(f) = \alpha$: for any object x and any $g\colon x \to c$, naturality of α at g applied to 1_c gives

$$\alpha_x(g) = \alpha_x\big(\mathrm{Hom}(g,c)(1_c)\big) = \mathrm{Hom}(g,d)\big(\alpha_c(1_c)\big) = \alpha_c(1_c) \circ g = fg = \big(\mathbf{y}(f)\big)_x(g)$$

so $\alpha = \mathbf{y}(f)$, recovering the second half of the inverse relation.

The two composites being identities, $f \mapsto \mathbf{y}(f)$ is a bijection

$$\mathrm{Hom}_C(c,d) \xrightarrow{\cong} \mathrm{Nat}(\mathrm{Hom}(-,c),\mathrm{Hom}(-,d))$$

for every pair c, d. This is exactly the statement that $\mathbf{y}$ is full (the map is surjective, so every natural transformation between representables is $\mathbf{y}(f)$ for some f) and faithful (the map is injective, so $\mathbf{y}(f)$ determines f), as we sought to show.

Full faithfulness is the sharpest possible statement that $\mathbf{y}$ loses no information at the level of morphisms. Every natural transformation between the presheaves $\mathrm{Hom}(-,c)$ and $\mathrm{Hom}(-,d)$ is post-composition with a unique morphism $c \to d$: there are no natural transformations between representables beyond the ones the category already gives. The functor $\mathbf{y}$ therefore identifies the hom-

set $\mathrm{Hom}_C(c,d)$ with the hom-set $\mathrm{Hom}_{\mathbf{PSh}(C)}(\mathbf{y}(c),\mathbf{y}(d))$ without collapsing or inventing morphisms, so C sits inside $\mathbf{PSh}(C)$ as a full subcategory (up to the identification of objects with the presheaves they represent). The step from this to objects is one general fact about fully faithful functors: they detect isomorphisms as well as reflect the morphisms that witness them.

Before stating the corollary, it is worth pinning the one property of fully faithful functors it rests on. A functor always preserves isomorphisms (lemma 61.4.5): if f is invertible, so is Ff. A fully faithful functor also *reflects* them, and this is the new content. Suppose $Ff\colon Fc \to Fd$ is an isomorphism with inverse $k\colon Fd \to Fc$. Because F is full, $k = Fg$ for some $g\colon d \to c$; because F is faithful, the equations $Fg \circ Ff = 1_{Fc} = F(1_c)$ and $Ff \circ Fg = 1_{Fd} = F(1_d)$, which say $F(gf) = F(1_c)$ and $F(fg) = F(1_d)$, force $gf = 1_c$ and $fg = 1_d$. So f is an isomorphism (definition 61.2.1) with inverse g. A morphism whose image under a fully faithful functor is invertible is therefore already invertible.

Corollary 62.3.4: Objects are Determined by their Points

Let C be a locally small category. Two objects c, d of C are isomorphic in C if and only if the represented presheaves $\mathbf{y}(c) = \mathrm{Hom}(-,c)$ and $\mathbf{y}(d) = \mathrm{Hom}(-,d)$ are isomorphic in $\mathbf{PSh}(C)$. An object of C is determined, up to isomorphism, by the presheaf it represents, its *functor of points*.

***Proof*:**
The Yoneda embedding $\mathbf{y}$ is full and faithful by theorem 62.3.3. If $c \cong d$ in C, then $\mathbf{y}$ preserves the isomorphism (lemma 61.4.5), giving $\mathbf{y}(c) \cong \mathbf{y}(d)$ in $\mathbf{PSh}(C)$. Conversely, suppose $\varphi\colon \mathbf{y}(c) \to \mathbf{y}(d)$ is an isomorphism of presheaves. By fullness $\varphi = \mathbf{y}(f)$ for some $f\colon c \to d$, and $\mathbf{y}(f)$ is an isomorphism, so by the reflection of isomorphisms established above f is itself an isomorphism. Hence $c \cong d$ in C, as we sought to show.

This is the precise form of the chapter's thread: an object is known, up to isomorphism, by how everything maps into it. The functor of points $\mathrm{Hom}(-,c)$ carries the full isomorphism type of c, so two objects with naturally isomorphic points are the same object seen twice.

62.4 Applications

The embedding of section 62.3 converts three recurring questions into questions about hom-functors, where they become easy. This section collects the payoffs. First, a representing object is pinned down not just up to isomorphism but up to a *unique* isomorphism, so "the" representing object is a legitimate phrase. Second, the deferred converse from Chapter 1 falls out: a full, faithful, essentially surjective functor is an equivalence (proposition 61.5.6). Third, a concrete instance of corollary 62.3.4: an object of a category is recovered, up to isomorphism, from its functor of points.

A representing object for a set-valued functor F is any object c together with a natural isomorphism $F \cong \mathrm{Hom}(c,-)$. Two such objects are isomorphic by the general principle that represented functors determine their representing object (corollary 62.3.4), but more is true: the isomorphism between them is forced, with no freedom of choice. This is what justifies treating the representing object as canonical data attached to F.

Corollary 62.4.1: Uniqueness of Representing Objects

Let C be a locally small category and $F\colon C \to \mathbf{Set}$ a functor. If $\varphi\colon F \Rightarrow \mathrm{Hom}(c,-)$ and $\varphi'\colon F \Rightarrow \mathrm{Hom}(c',-)$ are natural isomorphisms, then there is a unique isomorphism $u\colon c' \to c$ in C for which the induced natural isomorphism $\mathrm{Hom}(u,-)\colon \mathrm{Hom}(c,-) \Rightarrow \mathrm{Hom}(c',-)$ equals $\varphi'\varphi^{-1}$. In particular the representing object of F, when it exists, is unique up to a unique isomorphism.

***Proof*:**

Write ψ for the composite $\varphi'\varphi^{-1}\colon \mathrm{Hom}(c,-) \Rightarrow \mathrm{Hom}(c',-)$, a natural isomorphism, being a composite of natural isomorphisms.

The covariant hom-functors are the objects in the image of the covariant embedding $c \mapsto \mathrm{Hom}(c,-)$, which sends C^{op} fully faithfully into $[C,\mathbf{Set}]$. This is the covariant analog of theorem 62.3.3 and is read off the Yoneda lemma directly: applying theorem 62.2.1 to the functor $F = \mathrm{Hom}(c',-)$ gives a bijection

$$\mathrm{Nat}\big(\mathrm{Hom}(c,-),\,\mathrm{Hom}(c',-)\big) \;\cong\; \mathrm{Hom}(c',-)(c) \;=\; \mathrm{Hom}(c',c)$$

natural in both variables. Tracing the Yoneda bijection, a morphism $v\colon c' \to c$ corresponds to the natural transformation $\mathrm{Hom}(v,-)$ whose component at x is $g \mapsto gv$; and every natural transformation $\mathrm{Hom}(c,-) \Rightarrow \mathrm{Hom}(c',-)$ arises this way from a unique such v. Applying this to ψ yields a unique $u\colon c' \to c$ with $\mathrm{Hom}(u,-) = \psi = \varphi'\varphi^{-1}$.

It remains to check u is an isomorphism. Applying the same bijection to $\psi^{-1}\colon \mathrm{Hom}(c',-) \Rightarrow \mathrm{Hom}(c,-)$ produces a unique $w\colon c \to c'$ with $\mathrm{Hom}(w,-) = \psi^{-1}$. Since $c \mapsto \mathrm{Hom}(c,-)$ is a functor $C^{\mathrm{op}} \to [C,\mathbf{Set}]$, precomposition is sent to composition of natural transformations, so $\mathrm{Hom}(uw,-) = \mathrm{Hom}(w,-)\mathrm{Hom}(u,-) = \psi^{-1}\psi = \mathrm{id}$ and likewise $\mathrm{Hom}(wu,-) = \mathrm{id}$. Faithfulness of the embedding (again theorem 62.2.1, whose bijection is injective) forces $uw = \mathrm{id}_c$ and $wu = \mathrm{id}_{c'}$, so u is an isomorphism with inverse w. Uniqueness of u is the uniqueness already given by the Yoneda bijection, completing the proof.

The statement isolates the mechanism behind the familiar slogan that universal objects are unique "up to canonical isomorphism". The isomorphism u is not merely one of possibly several: it is singled out by the requirement that it intertwine the two representations φ, φ', and full faithfulness of the embedding says there is exactly one morphism doing so. Every construction recognized by a universal property in the chapters to come (products, kernels, tensor products) inherits this uniqueness for free, which is why one speaks of *the* product rather than a product.

The second application discharges a debt from Chapter 1. There the notion of an equivalence of categories was introduced (definition 61.5.5), and proposition 61.5.6 showed that an equivalence is necessarily full, faithful, and essentially surjective. The converse was deferred, because constructing the quasi-inverse requires choosing, for each object of the target, an object of the source mapping to it, and then transporting morphisms along those choices coherently. The bookkeeping is exactly the naturality that the Yoneda circle of ideas trains one to handle, so this is the natural place to settle it.

Proposition 62.4.2: Full, Faithful, Essentially Surjective Implies Equivalence

Let $F\colon C \to D$ be a functor that is full, faithful, and essentially surjective. Then F is an equivalence of categories: there exist a functor $G\colon D \to C$ and natural isomorphisms $\varepsilon\colon FG \Rightarrow \mathrm{id}_D$ and $\eta\colon \mathrm{id}_C \Rightarrow GF$.

***Proof*:**

Step 1: Define G on objects. For each object d of D, essential surjectivity gives an object of C mapping isomorphically to d. Choose one such object, call it Gd, together with an isomorphism $\varepsilon_d\colon F(Gd) \to d$ in D. This is one simultaneous choice over all objects of D, the only appeal to choice in the argument; it is harmless, and when D is small it is a choice from a set.

Step 2: Define G on morphisms. Given $g\colon d \to d'$ in D, consider the morphism

$$\varepsilon_{d'}^{-1}\, g\, \varepsilon_d\colon F(Gd) \to F(Gd')$$

Because F is full and faithful, the map $\mathrm{Hom}_C(Gd, Gd') \to \mathrm{Hom}_D(F(Gd), F(Gd'))$ induced by F is a bijection. Hence there is a unique morphism $Gg\colon Gd \to Gd'$ in C with

$$F(Gg) \;=\; \varepsilon_{d'}^{-1}\, g\, \varepsilon_d \tag{62.3}$$

Existence gives G a value; uniqueness is what makes the value well-defined and, as we now see, functorial.

Step 3: G is a functor. For the identity id_d, the morphism $\varepsilon_d^{-1}\,\mathrm{id}_d\,\varepsilon_d = \mathrm{id}_{F(Gd)} = F(\mathrm{id}_{Gd})$, so by the uniqueness in (62.3) the unique preimage is id_{Gd}, giving $G(\mathrm{id}_d) = \mathrm{id}_{Gd}$. For composability $d \xrightarrow{g} d' \xrightarrow{g'} d''$, faithfulness lets us compare $G(g'g)$ and $(Gg')(Gg)$ by comparing their images under F. Applying F and using (62.3) termwise,

$$F\big((Gg')(Gg)\big) = F(Gg')\,F(Gg) = \big(\varepsilon_{d''}^{-1}\, g'\, \varepsilon_{d'}\big)\big(\varepsilon_{d'}^{-1}\, g\, \varepsilon_d\big) = \varepsilon_{d''}^{-1}\, g' g\, \varepsilon_d = F\big(G(g'g)\big)$$

where the middle equality cancels $\varepsilon_{d'}\varepsilon_{d'}^{-1} = \mathrm{id}$. Faithfulness then gives $(Gg')(Gg) = G(g'g)$, so G is a functor.

Step 4: $\varepsilon\colon FG \Rightarrow \mathrm{id}_D$ is a natural isomorphism. Each component $\varepsilon_d\colon F(Gd) \to d$ is an isomorphism by construction, so it suffices to check naturality. For $g\colon d \to d'$, rewriting (62.3) as $g\,\varepsilon_d = \varepsilon_{d'}\,F(Gg)$ is exactly the statement that the square

$$\begin{array}{ccc} F(Gd) & \xrightarrow{\varepsilon_d} & d \\ {\scriptstyle F(Gg)}\downarrow & & \downarrow{\scriptstyle g} \\ F(Gd') & \xrightarrow[\varepsilon_{d'}]{} & d' \end{array}$$

commutes. Thus ε is natural, and being componentwise an isomorphism it is a natural isomorphism.

Step 5: Construct $\eta\colon \mathrm{id}_C \Rightarrow GF$. For an object c of C, the object $GF(c)$ comes with the chosen isomorphism $\varepsilon_{Fc}\colon F(GFc) \to Fc$. Since F is full and faithful, the isomorphism $\varepsilon_{Fc}^{-1}\colon Fc \to F(GFc)$ has a unique preimage $\eta_c\colon c \to GF(c)$ with

$$F(\eta_c) \;=\; \varepsilon_{Fc}^{-1} \tag{62.4}$$

Each η_c is an isomorphism: its inverse is the preimage of ε_{Fc} under the same bijection, and faithfulness turns the identities $F(\eta_c)\,\varepsilon_{Fc} = \mathrm{id}$ and vice versa into identities in C, as in the argument of corollary 62.4.1. For naturality, let $f\colon c \to c'$. Applying F to both candidate composites and using (62.4) together with (62.3) for the morphism Ff,

$$F\big(GF(f)\big)\,F(\eta_c) = \big(\varepsilon_{Fc'}^{-1}\,(Ff)\,\varepsilon_{Fc}\big)\,\varepsilon_{Fc}^{-1} = \varepsilon_{Fc'}^{-1}\,(Ff) = F(\eta_{c'})\,F(f)$$

so $F\big(GF(f)\,\eta_c\big) = F\big(\eta_{c'}\,f\big)$, and faithfulness gives $GF(f)\,\eta_c = \eta_{c'}\,f$. Hence η is a natural isomorphism $\mathrm{id}_C \Rightarrow GF$.

With G a functor and ε, η natural isomorphisms, F and G are quasi-inverse, so F is an equivalence of categories, as we sought to show.

Together with proposition 61.5.6 this completes the characterization: a functor is an equivalence if and only if it is full, faithful, and essentially surjective. The "if" direction just proved is the useful one in practice, since it lets one certify an equivalence without ever exhibiting the inverse functor. One checks three local conditions, two of them (fullness, faithfulness) about hom-sets and one (essential surjectivity) about the image on objects, and the quasi-inverse is then guaranteed to exist. The proof also shows the quasi-inverse is far from unique as bare data, since it depends on the choices in Step 1, yet any two such choices yield equivalent functors, matching the uniqueness pattern of corollary 62.4.1.

The last application unpacks corollary 62.3.4. That corollary says an object is determined up to isomorphism by the functor it represents, its functor of points; two objects with naturally isomorphic points are isomorphic. On a category of algebraic objects this recovers the object from the ways of mapping it to arbitrary test objects, which is the content of the "functor of points" viewpoint that pervades algebraic geometry.

Example 62.4.3: Recovering a Ring from Its Points

Work in $C = \mathbf{Ring}$ (commutative rings with unit). Each ring R represents the covariant functor of points $\mathrm{Hom}(R, -)\colon \mathbf{Ring} \to \mathbf{Set}$, sending a ring A to the set $\mathrm{Hom}(R, A)$ of ring homomorphisms out of R. Suppose R and S are rings and

$$\Phi\colon \mathrm{Hom}(R, -) \Rightarrow \mathrm{Hom}(S, -)$$

is a natural isomorphism of these functors. Then $R \cong S$ as rings, and the isomorphism is canonical.

The point is the covariant form of corollary 62.3.4: represented functors determine their representing object, and here the representation is covariant, so the roles are dual to the presheaf statement. Concretely, apply corollary 62.4.1 with $F = \mathrm{Hom}(R, -)$. The two natural isomorphisms $\mathrm{id}\colon F \Rightarrow \mathrm{Hom}(R, -)$ and $\Phi\colon F \Rightarrow \mathrm{Hom}(S, -)$ represent the same F, so there is a unique isomorphism $u\colon S \to R$ with $\mathrm{Hom}(u, -) = \Phi$.

The isomorphism u can be named by hand, which shows the abstraction hides nothing. Chase the identity through the components. At $A = R$ the map $\Phi_R\colon \mathrm{Hom}(R, R) \to \mathrm{Hom}(S, R)$ carries id_R to a homomorphism $u\colon S \to R$, that is, set $u = \Phi_R(\mathrm{id}_R)$. For any A and any $f\colon R \to A$, naturality of Φ along f gives the square

$$\begin{array}{ccc} \mathrm{Hom}(R, R) & \xrightarrow{\Phi_R} & \mathrm{Hom}(S, R) \\ {\scriptstyle f\circ(-)}\downarrow & & \downarrow{\scriptstyle f\circ(-)} \\ \mathrm{Hom}(R, A) & \xrightarrow[\Phi_A]{} & \mathrm{Hom}(S, A) \end{array}$$

> Evaluating both routes at id_R gives $\Phi_A(f) = fu$, so Φ_A is precomposition with u, that is, $\Phi = \mathrm{Hom}(u, -)$. Running the same chase on Φ^{-1} produces $v = (\Phi^{-1})_S(\mathrm{id}_S)\colon R \to S$ with $\Phi^{-1} = \mathrm{Hom}(v, -)$. Then $\mathrm{Hom}(uv, -) = \mathrm{Hom}(v, -)\mathrm{Hom}(u, -) = \Phi^{-1}\Phi = \mathrm{id}$ forces $uv = \mathrm{id}_R$, and symmetrically $vu = \mathrm{id}_S$, so $u\colon S \to R$ is an isomorphism of rings with inverse v. The functor of points has recovered the ring.

The computation is the whole Yoneda lemma in miniature: the natural transformation Φ is completely determined by its value on a single element, the identity id_R, and that value is the morphism representing it. The same argument works verbatim in any locally small category, with **Ring** replaced by **Grp**, **Top**, or the category of schemes, and it is the reason the functor of points is a faithful record of the object rather than a lossy one.

63

Universal Properties, Limits, and Colimits

Chapters 1 and 2 built the categorical language and its central theorem; this chapter turns to construction. Products, quotients, kernels, unions, gluings: most objects mathematics builds are pinned down not by their elements but by a mapping property. This chapter isolates that pattern as a *universal property*, organizes the constructions it governs into *limits* and *colimits*, and computes them in the categories at hand.

63.1 Universal Properties and Universal Arrows

An object is often pinned down not by naming its elements but by a rule describing how it maps to, or receives maps from, every other object. The empty set is the set with a unique map to every set; the free group on a set X is the group into which every function from X extends uniquely. This section isolates the two building blocks of such descriptions. The first is the pair of extremal objects, *initial* and *terminal*, which sit at the ends of a category. The second, the *universal arrow*, relativizes them along a functor and turns out to be the general form of the universal element from definition 62.1.5.

Definition 63.1.1: Initial and Terminal Objects

Let C be a category. An object 0 of C is *initial* if for every object X there is exactly one morphism $0 \to X$. An object 1 of C is *terminal* if for every object X there is exactly one morphism $X \to 1$. An object that is both initial and terminal is a *zero object*.

The two notions are dual: a terminal object of C is an initial object of C^{op}, so every statement about one specializes to a statement about the other by box 61.3.3. Neither need exist, and when one does

it carries no further data beyond the bare mapping property; that austerity is what makes it useful.

Example 63.1.2: Initial and Terminal Objects in the Standing Cast
The following run through the standing cast.

1. In **Set** the empty set $\varnothing$ is initial: the empty function is the unique map $\varnothing \to X$ for every X. Every singleton $\{*\}$ is terminal, since a map $X \to \{*\}$ has no choice in where to send its elements. There is no zero object: $\varnothing$ is not terminal (no map $\{*\} \to \varnothing$ exists).
2. In **Grp** and in $\mathbf{Mod}_R$ the trivial object (the group $\{e\}$, the zero module 0) is both initial and terminal, hence a zero object. Every homomorphism to or from it is forced, since a homomorphism preserves the identity; this is the algebraic fact recorded for the trivial group in [21, Homomorphism To/From Trivial Group], and the zero-module case is the same computation.
3. In **Ring** (unital rings, $1 \neq 0$ not required) the ring $\mathbb{Z}$ is initial: for any ring R the unique homomorphism $\mathbb{Z} \to R$ sends n to $n \cdot 1_R$, forced because a ring map preserves 1. The zero ring, in which $1 = 0$, is terminal. Here the two extremes are distinct, so **Ring** has no zero object.
4. A poset $(P, \leq)$, viewed as a category with a unique arrow $x \to y$ when $x \leq y$, has an initial object exactly when P has a least element and a terminal object exactly when it has a greatest element.

The **Ring** example already exhibits the pattern the rest of the chapter formalizes: the map $\mathbb{Z} \to R$ is not just *some* distinguished morphism, it is the *unique* one, and that uniqueness is the whole content. A universal property is always a uniqueness statement of this kind.

The defining clause of an initial object, "exactly one morphism", has an immediate consequence: an initial object is determined by the property, not only up to isomorphism but up to a *unique* isomorphism. This is the prototype every universal-property uniqueness argument imitates, so it is worth seeing once in full.

Proposition 63.1.3: Initial and Terminal Objects are Unique up to Unique Isomorphism

If 0 and $0'$ are both initial objects of a category C, then there is a unique isomorphism $0 \to 0'$. Dually, any two terminal objects are related by a unique isomorphism.

***Proof*:**
Since 0 is initial, there is a unique morphism $u\colon 0 \to 0'$; since $0'$ is initial, there is a unique morphism $v\colon 0' \to 0$. The composite $vu\colon 0 \to 0$ is a morphism from 0 to itself, and 0 is initial, so there is only one such morphism. The identity id_0 is one, hence $vu = \mathrm{id}_0$. The same argument in C with the roles of 0 and $0'$ exchanged gives $uv = \mathrm{id}_{0'}$. Thus u is an isomorphism with inverse v, and it is the only morphism $0 \to 0'$ by initiality of 0, so it is the unique isomorphism. The terminal statement is the initial statement read in C^{op}, completing the proof.

The argument uses nothing about 0 except that maps out of it are forced. Every "unique up to unique isomorphism" claim for a universal construction, for products, kernels, free objects, limits,

runs the same way: two solutions each map uniquely to the other, and the round trips are identities because they compete with id for a slot the property allows only one morphism to fill. The reader may reduce any such uniqueness proof to proposition 63.1.3 by exhibiting the construction as an initial or terminal object of a suitable category, which is precisely the reduction the next two definitions make available.

Initial and terminal objects describe an object by its maps to or from *everything*. Most constructions of interest carry data along a functor: the free group on X is built from the set X through the forgetful functor $U\colon \mathbf{Grp} \to \mathbf{Set}$. The universal arrow relativizes the extremal notion to this setting.

Definition 63.1.4: Universal Arrow

Let $U\colon C \to D$ be a functor and d an object of D. A *universal arrow from d to U* is a pair (c, η) consisting of an object c of C and a morphism $\eta\colon d \to Uc$ in D with the following property: for every object x of C and every morphism $f\colon d \to Ux$ in D, there is a unique morphism $g\colon c \to x$ in C such that $f = (Ug) \circ \eta$. The defining equation is the commuting triangle

$$\begin{array}{ccc} d & \xrightarrow{\eta} & Uc \\ & \searrow^{f} & \downarrow{\scriptstyle Ug} \\ & & Ux \end{array}$$

Dually, a *universal arrow from U to d* is a pair (c, ε) with $\varepsilon\colon Uc \to d$ such that every $f\colon Ux \to d$ factors as $f = \varepsilon \circ (Ug)$ for a unique $g\colon x \to c$.

The pair (c, η) is universal in that η is the most efficient map from d into the image of U: any other map f from d into U is recovered from η by post-composing with a C-morphism, and in exactly one way. Setting $U = \mathrm{id}_D$ recovers the extremal case, an initial object of the coslice under d; the functor U is what makes the notion carry structure across categories.

This connects directly to the representability material of the previous chapter. A universal element of a functor $F\colon C \to \mathbf{Set}$ (definition 62.1.5) is an element $u \in Fc$ such that every $x \in Fa$ equals $Fg(u)$ for a unique $g\colon c \to a$; that is the special case of definition 63.1.4 in which $D = \mathbf{Set}$, the object d is a singleton $\{*\}$, and a map $\{*\} \to Fc$ is named by the element it picks out. Both say the same thing: the datum η (or u) generates every map into U (or every element of F) freely and uniquely. Equivalently, a universal arrow from d to U makes the functor $D(d, U-)$ representable (definition 62.1.1), represented by c with the element η corresponding under Yoneda; the connection to preservation of limits is taken up later in the chapter.

Example 63.1.5: The Universal Arrow of the Free Group

Take $U\colon \mathbf{Grp} \to \mathbf{Set}$ the forgetful functor and X a set. The free group FX carries the inclusion of generators $\eta\colon X \to UFX$. Given any group H and any function $f\colon X \to UH$, the universal property of the free group ([21, Universal Property Of Free Groups]) gives a unique homomorphism $g\colon FX \to H$ extending f on generators, so $f = (Ug) \circ \eta$. Thus (FX, η) is a universal arrow from X to U: the free group is exactly the solution to this universal problem, with η marking the generators.

The example is the template for "free" constructions in general, and the next definition packages the search for a universal arrow into a single object of a single category, so that finding one becomes

finding an initial object.

Definition 63.1.6: Comma Category

Let $F\colon A \to C$ and $G\colon B \to C$ be functors into a common category C. The *comma category* $F \downarrow G$ has as objects the triples (a, b, h) with a an object of A, b an object of B, and $h\colon Fa \to Gb$ a morphism of C. A morphism $(a, b, h) \to (a', b', h')$ is a pair $(p\colon a \to a',\ q\colon b \to b')$ making the square

$$\begin{array}{ccc} Fa & \xrightarrow{h} & Gb \\ {\scriptstyle Fp}\downarrow & & \downarrow{\scriptstyle Gq} \\ Fa' & \xrightarrow[h']{} & Gb' \end{array}$$

commute; composition and identities are computed componentwise in A and B.

Two special cases recur. Write $c\colon \mathbf{1} \to C$ for the functor from the one-object one-morphism category that picks out an object c. With $A = C$, $F = \mathrm{id}_C$ and $G = c$, an object of $\mathrm{id}_C \downarrow c$ is a morphism $a \to c$, and this comma category is the *slice category* C/c of objects over c. Dually, $c \downarrow \mathrm{id}_C$ has as objects the morphisms $c \to b$ and is the *coslice* c/C of objects under c. The unifying point is a single reformulation of definition 63.1.4.

Proposition 63.1.7: Universal Arrows are Initial Objects of a Comma Category

Let $U\colon C \to D$ be a functor and d an object of D, viewed as a functor $d\colon \mathbf{1} \to D$ from the one-object one-morphism category. A universal arrow from d to U is the same thing as an initial object of the comma category $d \downarrow U$.

***Proof*:**
An object of $d \downarrow U$ is a pair $(c, \eta\colon d \to Uc)$ with c an object of C, and a morphism $(c, \eta) \to (x, f)$ is a C-morphism $g\colon c \to x$ with $(Ug) \circ \eta = f$. To say (c, η) is initial is to say that for every (x, f) there is exactly one such g, which is verbatim the defining property of a universal arrow from d to U in definition 63.1.4, as we sought to show.

proposition 63.1.7 discharges the uniqueness of universal arrows into proposition 63.1.3: a universal arrow, being an initial object, is determined up to a unique isomorphism, so the free group, the initial ring, and every other solution of a universal problem is unique in the strongest sense available. The comma category is the "neighbouring category" whose initial object is the construction one is after, and the sections that follow build limits and colimits by finding exactly such extremal objects.

Example 63.1.8: Universal Arrows Across the Standing Cast
Each construction below is a universal arrow, read off from its factorization property.

1. *The integers as initial ring.* Let $U\colon \mathbf{Ring} \to \mathbf{Set}$ be the forgetful functor and $\{*\}$ a one-point set. A universal arrow from $\{*\}$ to U is a ring c together with a chosen element $\eta(*) \in Uc$ such that every pointed ring (R, r), with $r = f(*) \in UR$, receives a unique ring map $g\colon c \to R$ sending $\eta(*)$ to r. Take $c = \mathbb{Z}[x]$ with $\eta(*) = x$: a ring map $\mathbb{Z}[x] \to R$ is determined by, and freely specifies, the image of x ([21], universal property of the polynomial ring), so $(\mathbb{Z}[x], x)$

is the universal arrow. Forgetting the marked point instead, and taking U with no chosen element, the empty universal problem is solved by $\mathbb{Z}$ itself: $\mathbb{Z}$ is the initial object of **Ring** (example 63.1.2), the universal arrow from the empty set to U.

2. *Abelianization.* Let $U\colon \mathbf{Ab} \to \mathbf{Grp}$ be the inclusion of abelian groups into groups and let G be a group. The abelianization $G^{\mathrm{ab}} = G/[G,G]$ carries the quotient map $\eta\colon G \to U(G^{\mathrm{ab}})$. Every homomorphism $f\colon G \to UA$ into an abelian group A kills commutators, so it factors as $f = (Ug) \circ \eta$ through a unique homomorphism $g\colon G^{\mathrm{ab}} \to A$ ([21, Commutator Subgroup Properties]). Thus (G^{ab}, η) is a universal arrow from G to U, the best abelian approximation of G from the left.

The two items sit on opposite sides of a forgetful (or inclusion) functor. The polynomial ring is universal *from* a set *to* U, a free construction; abelianization is likewise a universal arrow from an object to an inclusion, a reflection into a subcategory. Both are computed the same way, by recognizing that a map out of the constructed object is forced by its effect on the universal datum η. The organizing principle behind such matched pairs of universal arrows, one for each object, is the subject of the chapter on adjunctions.


63.2 Limits

An initial object receives a unique map from nothing, a terminal object receives one from everything; both are universal against the empty diagram. A limit asks for more: a universal way to map compatibly into a whole configuration of objects and morphisms at once. Products, intersections, kernels, and fibered products are all this one requirement read against different shapes. This section isolates the shape as a small category J, packages a configuration as a functor out of it, and defines the limit as the terminal object among the compatible maps into it. The atomic cases, products and equalizers, are then shown to generate every limit.

We first fix what "a configuration" means. A configuration of objects and morphisms in $\mathbf{C}$ is exactly a functor into $\mathbf{C}$ whose domain records the shape; the domain is small so that the configuration has only a set's worth of pieces.

Definition 63.2.1: Diagram, Cone, and Limit

Let $\mathbf{C}$ be a category and J a small category, the *index category*. A *diagram* of shape J in $\mathbf{C}$ is a functor $D\colon J \to \mathbf{C}$ (definition 61.4.1); the object $D(j)$ is written Dj.
A *cone* over D with *apex* X is an object X of $\mathbf{C}$ together with a family of morphisms $\lambda_j\colon X \to Dj$, one for each object j of J, such that for every morphism $u\colon j \to j'$ in J the triangle



commutes, that is $Du \circ \lambda_j = \lambda_{j'}$. A morphism of cones $(X, \{\lambda_j\}) \to (Y, \{\mu_j\})$ is a morphism $f\colon X \to Y$ with $\mu_j \circ f = \lambda_j$ for every j. Cones over D and their morphisms form a category $\mathrm{Cone}(D)$.
A *limit* of D is a terminal object of $\mathrm{Cone}(D)$: a cone $(L, \{\pi_j\})$, the *limit cone*, such that every cone $(X, \{\lambda_j\})$ factors through it by a unique morphism $\langle \lambda_j \rangle\colon X \to L$ with $\pi_j \circ \langle \lambda_j \rangle = \lambda_j$ for all j. The apex L is written $\lim D$ or $\lim_J D$, and the π_j are its *projections*.

The commuting condition is the whole content of "compatible": a cone is not just a map into each Dj but a family that respects every morphism the shape imposes among the Dj. The limit is the cone through which all others factor, so a map into L is precisely a compatible family of maps into the diagram. This is the universal-arrow pattern of definition 63.1.4 for the diagonal functor $\Delta\colon \mathbf{C} \to [J, \mathbf{C}]$ sending X to the constant diagram at X: a cone with apex X is a natural transformation $\Delta X \Rightarrow D$ (definition 61.5.2), and the limit is the universal such X.

Being terminal in $\mathrm{Cone}(D)$ settles uniqueness at once.

Proposition 63.2.2: Uniqueness of Limits

If $(L, \{\pi_j\})$ and $(L', \{\pi'_j\})$ are both limits of $D\colon J \to \mathbf{C}$, there is a unique isomorphism $L \to L'$ commuting with the projections.

***Proof*:**
Both are terminal objects of $\mathrm{Cone}(D)$, and terminal objects are unique up to a unique isomorphism by proposition 63.1.3. The isomorphism is a morphism of cones, so it commutes with the projections by definition of $\mathrm{Cone}(D)$, completing the proof.

The limit is thus determined by D alone, and one speaks of "the" limit. The rest of the section reads specific shapes J off this single definition, then shows two of them suffice to build every other.

The simplest shapes carry no morphisms beyond identities, so the cone condition is vacuous and a cone is just a chosen map into each object.

Definition 63.2.3: Product

Let J be a *discrete* category (only identity morphisms) with objects indexed by a set I, and let D pick out a family $\{X_i\}_{i\in I}$. The limit of D, when it exists, is the *product* $\prod_{i\in I} X_i$, with projections $\pi_i\colon \prod_{i\in I} X_i \to X_i$. Its universal property: for every object X and every family $f_i\colon X \to X_i$ there is a unique $\langle f_i\rangle\colon X \to \prod_{i\in I} X_i$ with $\pi_i \circ \langle f_i\rangle = f_i$ for all i. When $I = \{1, 2\}$ the product is written $X_1 \times X_2$; when $I = \varnothing$ the limit over the empty diagram is a terminal object 1, the *empty product*.

A product is a single object out of which one can name any tuple of maps to the factors and nothing more; the projections read the coordinates back. There are no compatibility constraints because a discrete shape imposes none, so a map into $\prod_i X_i$ is exactly an unconstrained family of maps into the factors. The empty case is worth pausing on: with no factors to hit, the universal property says every object admits a unique map to the limit, which is the definition of a terminal object (definition 63.1.1).

Next introduce the shape with two parallel arrows between two objects. A cone must equalize the two composites, so it selects the part of the source on which they agree.

Definition 63.2.4: Equalizer

Let J be the category $\{\bullet \rightrightarrows \bullet\}$ with two objects and two parallel non-identity morphisms, and let D send it to a parallel pair $f, g\colon A \to B$ in $\mathbf{C}$. A cone over D is an object E with maps to A and to B making both triangles commute; the map to B is forced to be the common composite, so a cone is a morphism $e\colon E \to A$ with $fe = ge$. The limit is the *equalizer* of f and g: a morphism $e\colon E \to A$ with $fe = ge$ such that every $h\colon X \to A$ with $fh = gh$ factors as $h = e \circ \bar{h}$ for a unique $\bar{h}\colon X \to E$.

The equalizer is the categorical "locus where two maps agree": e is the universal way to map into A so that f and g become equal after the map. That universality forces e to be injective on maps.

Proposition 63.2.5: Equalizers are Monic

The equalizer $e\colon E \to A$ of a parallel pair $f, g\colon A \to B$ is a monomorphism.

***Proof*:**
Let $p, q\colon X \to E$ satisfy $ep = eq$, and set $h = ep$. Then $fh = fep = gep = gh$, so $h\colon X \to A$ satisfies $fh = gh$ and factors uniquely through e. Both p and q are factorizations of h through e: indeed $e \circ p = h$ and $e \circ q = eq = ep = h$. Uniqueness of the factorization gives $p = q$, so e is monic, as required.

That equalizers are monic recovers the intuition that "where f and g agree" is a subobject of the source A, and it is the ingredient that later lets equalizers cut a limit out of a product.

The third shape is the cospan: two arrows into a common target. Its limit combines a product with an agreement condition.

Definition 63.2.6: Pullback

Let J be the *cospan* category $\{\bullet \to \bullet \leftarrow \bullet\}$, and let D send it to a cospan $f\colon X \to Z$, $g\colon Y \to Z$ in $\mathbf{C}$. The limit is the *pullback* $X \times_Z Y$, with projections $p\colon X \times_Z Y \to X$ and $q\colon X \times_Z Y \to Y$ satisfying $fp = gq$, universal among such squares:

$$\begin{array}{ccc} X \times_Z Y & \xrightarrow{q} & Y \\ {\scriptstyle p}\downarrow & & \downarrow{\scriptstyle g} \\ X & \xrightarrow[f]{} & Z \end{array}$$

For every object W with maps $a\colon W \to X$, $b\colon W \to Y$ such that $fa = gb$, there is a unique $\langle a, b\rangle\colon W \to X \times_Z Y$ with $p\langle a, b\rangle = a$ and $q\langle a, b\rangle = b$.

A pullback is a product "constrained to agree over Z": it is the subobject of $X \times Y$ on which the two ways to reach Z coincide. When $Z = 1$ is terminal the agreement condition is vacuous and the pullback collapses to the product $X \times Y$, so the pullback refines the product. This one shape specializes to intersections of subobjects, preimages, fibers of a map, and fibered products of schemes, which is why it recurs throughout the series.

Each of these shapes should be seen at work in the category the reader knows best.

Example 63.2.7: Limits in Set

In **Set** each of the three limits above has a concrete description, and the universal property is verified by hand.

1. *Products.* The product $\prod_{i\in I} X_i$ is the cartesian product, the set of tuples $(x_i)_{i\in I}$ with $x_i \in X_i$, and π_i is the i-th coordinate. Given $f_i\colon X \to X_i$, the map $\langle f_i\rangle(x) = (f_i(x))_{i\in I}$ satisfies $\pi_i\langle f_i\rangle = f_i$, and any g with $\pi_i g = f_i$ has i-th coordinate f_i, so $g = \langle f_i\rangle$. The empty product is a one-element set $\{*\}$, terminal in **Set**. In **Grp**, **Ab**, and $\mathbf{Mod}_R$ the same underlying cartesian product carries the pointwise (coordinatewise) operations, and the projections are homomorphisms.

2. *Equalizers.* The equalizer of $f, g\colon A \to B$ is the subset

$$E = \{\, a \in A \,|\, f(a) = g(a) \,\}$$

with e the inclusion. If $h\colon X \to A$ satisfies $fh = gh$ then $f(h(x)) = g(h(x))$ for all x, so $h(x) \in E$; corestricting h to E gives the unique $\bar{h}$ with $e\bar{h} = h$. The inclusion is injective, illustrating proposition 63.2.5.

3. *Pullbacks.* The pullback of $f\colon X \to Z$ and $g\colon Y \to Z$ is the subset of $X \times Y$

$$X \times_Z Y = \{\, (x, y) \in X \times Y \,|\, f(x) = g(y) \,\}$$

with p, q the coordinate maps. Given $a\colon W \to X$ and $b\colon W \to Y$ with $fa = gb$, the map $w \mapsto (a(w), b(w))$ lands in $X \times_Z Y$ and is the unique factorization. Taking $g\colon \{z\} \hookrightarrow Z$ the inclusion of a point recovers the fiber $f^{-1}(z)$, and taking $X, Y \subseteq Z$ with f, g the inclusions recovers the intersection $X \cap Y$.

The three examples share a pattern: the limit is a subset of a product cut out by the equations the shape requires. The next theorem promotes that pattern to a construction, showing that products and equalizers alone build every limit.

Products handle the objects of a diagram, equalizers handle the constraints its morphisms impose. Stack every Dj into one product, stack every constraint into a second, and the two maps that express "constraint satisfied versus not" have an equalizer that is exactly the limit. This reduces the existence of all limits to two special cases.

Theorem 63.2.8: Limits from Products and Equalizers

Let $\mathbf{C}$ have all small products and all equalizers. Then $\mathbf{C}$ has all small limits. Explicitly, for a diagram $D\colon J \to \mathbf{C}$ with J small, form the products

$$P = \prod_{j \in J} Dj, \qquad Q = \prod_{u\colon j \to j' \text{ in } J} D(\operatorname{cod} u)$$

indexed by the objects and by the morphisms of J respectively. Let $s, t\colon P \to Q$ be the morphisms determined on the u-component $(u\colon j \to j')$ by

$$\rho_u \circ s = D(u) \circ \mathrm{pr}_j, \qquad \rho_u \circ t = \mathrm{pr}_{j'}$$

where $\mathrm{pr}_j\colon P \to Dj$ and $\rho_u\colon Q \to D(\operatorname{cod} u) = Dj'$ are the product projections. Then the equalizer $e\colon L \to P$ of s and t is a limit of D, with projections $\pi_j = \mathrm{pr}_j \circ e$.

***Proof*:**

The proof runs in three stages: define the two maps whose disagreement measures failure of the cone condition, check that the equalizer carries a cone, and check that this cone is terminal.

Step 1: The maps s and t. By the universal property of the product Q (definition 63.2.3), a morphism into Q is determined by its composite with each projection ρ_u. So the two displayed families of composites define s and t uniquely. Reading them off: for a point of P, thought of as an arbitrary family $(x_j)_j$ with $x_j\colon T \to Dj$ for a test object T, the u-component of s is $D(u) \circ x_j$ (push the source coordinate along $D(u)$), while the u-component of t is $x_{j'}$ (read off the target coordinate). A family (x_j) satisfies $s = t$ on the u-component precisely when $D(u) \circ x_j = x_{j'}$, which is the cone condition for the morphism u. Thus s and t agree on (x_j) if and only if (x_j) is a cone over D.

Step 2: The equalizer is a cone. Let $e\colon L \to P$ equalize s and t, so $se = te$. Set $\pi_j = \mathrm{pr}_j \circ e\colon L \to Dj$. For any $u\colon j \to j'$, compose $se = te$ with ρ_u:

$$\rho_u \circ s \circ e = \rho_u \circ t \circ e$$

The left side is $D(u) \circ \mathrm{pr}_j \circ e = D(u) \circ \pi_j$ and the right side is $\mathrm{pr}_{j'} \circ e = \pi_{j'}$. Hence $D(u) \circ \pi_j = \pi_{j'}$ for every u, so $(L, \{\pi_j\})$ is a cone over D.

Step 3: The cone is terminal. Let $(X, \{\lambda_j\})$ be any cone over D. By the universal property of P the family $\{\lambda_j\}$ determines a unique morphism $\ell\colon X \to P$ with $\mathrm{pr}_j \circ \ell = \lambda_j$ for all j. The cone condition $D(u) \circ \lambda_j = \lambda_{j'}$ says, on each u-component,

$$\rho_u \circ s \circ \ell = D(u) \circ \mathrm{pr}_j \circ \ell = D(u) \circ \lambda_j = \lambda_{j'} = \mathrm{pr}_{j'} \circ \ell = \rho_u \circ t \circ \ell$$

Since these hold for every u, and morphisms into Q are determined by their ρ_u-components, $s\ell = t\ell$. So ℓ equalizes s and t and factors uniquely as $\ell = e \circ \bar{\ell}$ for a unique $\bar{\ell}\colon X \to L$. Then

$$\pi_j \circ \bar{\ell} = \mathrm{pr}_j \circ e \circ \bar{\ell} = \mathrm{pr}_j \circ \ell = \lambda_j$$

so $\bar{\ell}$ is a morphism of cones $(X, \{\lambda_j\}) \to (L, \{\pi_j\})$. For uniqueness, suppose $\varphi\colon X \to L$ is any cone morphism, so $\pi_j \circ \varphi = \lambda_j$ for all j. Then $\mathrm{pr}_j \circ (e \circ \varphi) = \pi_j \circ \varphi = \lambda_j = \mathrm{pr}_j \circ \ell$ for every j, and the uniqueness clause of P's universal property forces $e \circ \varphi = \ell$. Since e is monic (proposition 63.2.5), $e \circ \varphi = e \circ \bar{\ell}$ gives $\varphi = \bar{\ell}$. Thus $\bar{\ell}$ is the unique cone morphism $X \to L$, so $(L, \{\pi_j\})$ is terminal in $\mathrm{Cone}(D)$ and is a limit of D, as we sought to show.

The construction is the abstract form of the **Set** computation in example 63.2.7: P is the product of the objects, s and t encode the two sides of each morphism-constraint, and the equalizer $L \subseteq P$ is the sub-configuration on which every constraint holds. What was "a subset of a product cut out by equations" in **Set** is now "an equalizer of two maps out of a product" in any category with those two limits, and the same argument gives the universal property. A category with all products and equalizers is therefore complete for all small diagrams, and to check completeness one need only give products and equalizers.

A limit is the universal way to map compatibly into an entire diagram at once, so that a single morphism into the apex is the same data as a family of morphisms into the diagram respecting its shape. Products and equalizers are the atomic cases, the first handling objects without constraint and the second handling a constraint without extra objects, and theorem 63.2.8 shows these two generate all the rest.

63.3 Colimits

Every construction of the previous section has a mirror image obtained by reversing all arrows. Where a limit sits at the tip of an incoming cone, its dual sits at the tip of an outgoing one; where a limit is a terminal cone, its dual is an initial cocone. This section develops that mirror image. The payoff is not only a second family of constructions but a method: because a colimit in C is exactly a limit in C^{op}, every theorem about limits transports across the duality principle (box 61.3.3) with no new proof, and the constructions themselves become recognizable as the coproducts, quotients, and gluings the reader already meets throughout algebra and topology.

The starting point is the dual of a cone. A cone over a diagram receives a compatible family of maps from a single apex; a cocone under a diagram emits a compatible family of maps into a single nadir.

Definition 63.3.1: Cocone and Colimit

Let $D\colon J \to C$ be a diagram. A *cocone* under D with *nadir* X is an object X of C together with a family of morphisms

$$\iota_j\colon Dj \to X, \qquad j \in J$$

one for each object of J, such that for every morphism $u\colon j \to k$ of J the triangle

$$\iota_k \circ Du = \iota_j$$

commutes. A *morphism of cocones* $(X, \{\iota_j\}) \to (Y, \{\kappa_j\})$ is a morphism $f\colon X \to Y$ of C with $f\iota_j = \kappa_j$ for every j.

A *colimit* of D is an *initial* cocone: a cocone $(L, \{\iota_j\})$ such that for every cocone $(X, \{\kappa_j\})$ under D there is a unique morphism $f\colon L \to X$ with $f\iota_j = \kappa_j$ for all j. The nadir L is written $\operatorname{colim}_J D$, and the maps ι_j are the *structure maps* (or *coprojections*) of the colimit.

The definition is definition 63.2.1 read backwards. A cocone under D is precisely a cone over the diagram $D^{\mathrm{op}}\colon J^{\mathrm{op}} \to C^{\mathrm{op}}$ obtained by reversing every arrow, and an initial cocone is a terminal cone in C^{op}. This is the organizing fact of the section.

Proposition 63.3.2: Colimits are Limits in the Opposite Category

Let $D\colon J \to C$ be a diagram and write $D^{\mathrm{op}}\colon J^{\mathrm{op}} \to C^{\mathrm{op}}$ for the same assignment on objects, regarded as a diagram in C^{op}. An object L with maps $\iota_j\colon Dj \to L$ is a colimit of D in C if and only if L with the same maps, now read as $\iota_j\colon L \to Dj$ in C^{op}, is a limit of D^{op} in C^{op}. Thus

$$\operatorname*{colim}_{J} D \text{ in } C \quad = \quad \lim_{J^{\mathrm{op}}} D^{\mathrm{op}} \text{ in } C^{\mathrm{op}}$$

***Proof*:**
Reversing arrows sends the compatibility condition $\iota_k \circ Du = \iota_j$ for a cocone under D to the condition $D^{\mathrm{op}}u \circ \iota_k = \iota_j$ for a cone over D^{op} in C^{op}, since composition in C^{op} is composition in C in the opposite order and each Du becomes $D^{\mathrm{op}}u$ pointing the other way. So cocones under D in C are the same data as cones over D^{op} in C^{op}, and a morphism of cocones $f\colon X \to Y$ in C is a morphism of cones $f\colon Y \to X$ in C^{op}. An initial object among cocones is therefore a terminal object among cones, so L is a colimit of D exactly when it is a limit of D^{op} in C^{op}, completing the proof.

This proposition permits a mechanical translation. Every notion of the previous section has a dual with the prefix "co": the terminal cone becomes the initial cocone, and each specific limit shape becomes a colimit shape by reversing the diagram J. The three shapes worth naming are the duals of the product, the equalizer, and the pullback. Their definitions are stated directly, but each one could equally be obtained by applying proposition 63.3.2 to the corresponding definition of section 63.2.

The first is the dual of the product (definition 63.2.3): a discrete diagram $\{X_i\}_{i \in I}$ with no nontrivial morphisms, whose colimit assembles the objects side by side rather than cutting out their common part.

Definition 63.3.3: Coproduct

Let $\{X_i\}_{i\in I}$ be a family of objects of C, viewed as a diagram on the discrete index category I. A *coproduct* of the family is a colimit: an object $\coprod_{i\in I} X_i$ together with *injections*

$$\iota_i \colon X_i \to \coprod_{i\in I} X_i$$

such that for every object Y and every family of morphisms $f_i \colon X_i \to Y$ there is a unique morphism $f \colon \coprod_{i\in I} X_i \to Y$ with $f\iota_i = f_i$ for all i. A binary coproduct is written $X_1 \sqcup X_2$.

A coproduct is the object into which every X_i maps and out of which maps are prescribed by naming one map from each summand independently. Where a product is determined by projections and its universal property governs *maps in*, a coproduct is determined by injections and governs *maps out*. The empty coproduct, indexed by $I = \varnothing$, is an object with a unique map to every Y and no data to specify: it is an initial object 0 (definition 63.1.1).

Example 63.3.4: Coproducts in the Standing Cast

The coproduct instantiates as a familiar assembly in each concrete category.

1. In **Set** the coproduct is the *disjoint union* $\coprod_i X_i$, the set of pairs (i, x) with $x \in X_i$, and $\iota_i(x) = (i, x)$. A family of functions $f_i \colon X_i \to Y$ assembles into the single function $(i, x) \mapsto f_i(x)$, which is the only function restricting to each f_i on the i-th copy. For two sets this is $X_1 \sqcup X_2$.

2. In **Grp** the coproduct is the *free product* $G_1 * G_2$: its elements are reduced words alternating between nonidentity elements of G_1 and of G_2, with ι_1, ι_2 the inclusions of the one-letter words. A pair of homomorphisms $f_i \colon G_i \to H$ extends to the unique homomorphism sending a word to the product of the images of its letters, each letter mapped by the f_i of the factor it comes from, and this assignment is forced ([21], free products). The free group on a set S is the coproduct of $|S|$ copies of $\mathbb{Z}$.

3. In **Ab** and in $\mathbf{Mod}_R$ the coproduct of a family is the *direct sum* $\bigoplus_i M_i$, the submodule of the product $\prod_i M_i$ consisting of tuples with finitely many nonzero entries, with ι_i the insertion into the i-th coordinate. A family $f_i \colon M_i \to N$ assembles into $(m_i)_i \mapsto \sum_i f_i(m_i)$, a finite sum because only finitely many m_i are nonzero ([21, Universal Property Of Coproducts In **Ab**, Direct Sums And Homomorphisms]). For finitely many summands the direct sum and the direct product coincide, so the biproduct $M_1 \oplus M_2$ is at once a product and a coproduct; this coincidence is a feature of additive categories, not a general phenomenon.

The contrast with products is sharpest in **Grp**: the product $G_1 \times G_2$ forces the two factors to commute, while the coproduct $G_1 * G_2$ imposes no relations at all between them.

The direct-sum example already shows the divergence between limits and colimits concretely: in **Set** the product is a Cartesian product and the coproduct a disjoint union, unrelated constructions, and in **Grp** the gap between $G_1 \times G_2$ and $G_1 * G_2$ is the gap between imposing all cross-relations and imposing none. The next shape is the dual of the equalizer (definition 63.2.4). Where an equalizer selects the sub-object on which two maps agree, its dual forms the quotient on which two maps are forced to agree.

Definition 63.3.5: Coequalizer

Let $f, g\colon A \to B$ be a parallel pair of morphisms in C. A *coequalizer* of f and g is a morphism $q\colon B \to Q$ with $qf = qg$ that is universal with this property: for every morphism $h\colon B \to Y$ satisfying $hf = hg$ there is a unique morphism $\bar{h}\colon Q \to Y$ with $\bar{h}q = h$.

The coequalizer is the colimit of the two-object diagram $A \rightrightarrows B$ whose only nontrivial morphisms are f and g: the condition $qf = qg$ is the cocone compatibility for that diagram, and universality is initiality among such cocones. The map q is the largest quotient of B on which f and g become equal, the categorical quotient. It is always epic, the dual of the fact that an equalizer is always monic.

Lemma 63.3.6: A Coequalizer is Epic

The coequalizer map $q\colon B \to Q$ of any parallel pair $f, g\colon A \to B$ is an epimorphism.

***Proof*:**
Suppose $s, t\colon Q \to Y$ satisfy $sq = tq$. Set $h = sq = tq\colon B \to Y$. Then $hf = sqf = sqg = hg$ using $qf = qg$, so h satisfies the coequalizing condition and factors uniquely through q. Both s and t are such factorizations, since $sq = h$ and $tq = h$, so uniqueness forces $s = t$. Thus q is epic, as we sought to show.

Example 63.3.7: The Coequalizer in Sets is a Quotient
For functions $f, g\colon A \to B$ in **Set**, let $\sim$ be the smallest equivalence relation on B containing every pair $(f(a), g(a))$ for $a \in A$. The coequalizer is the quotient set $Q = B/\!\sim$ with $q\colon B \to Q$ the quotient map. A function $h\colon B \to Y$ satisfies $hf = hg$ exactly when $h(f(a)) = h(g(a))$ for all a, that is, when h is constant on each generating pair, hence on each $\sim$-class; such an h descends to a unique $\bar{h}\colon Q \to Y$ with $\bar{h}q = h$. The generated equivalence relation is not just the set of pairs $(f(a), g(a))$: it is their reflexive, symmetric, transitive closure, since a quotient map respecting the relations must respect everything they entail. Taking g constant recovers, as a special case, the quotient of B collapsing a subset to a point.

The equivalence closure in example 63.3.7 is the concrete face of a general fact: a coequalizer imposes the relations $f = g$ together with every consequence forced by the category's own composition, exactly as a coproduct in **Grp** imposes no relations while a quotient group imposes stated ones. The last named shape is the dual of the pullback (definition 63.2.6), which glues two objects along a shared source rather than intersecting them over a shared target.

Definition 63.3.8: Pushout

Let $f\colon Z \to X$ and $g\colon Z \to Y$ be a pair of morphisms with common *source* Z. A *pushout* of f and g is a colimit of this diagram: an object $X \sqcup_Z Y$ with morphisms $i\colon X \to X \sqcup_Z Y$ and $j\colon Y \to X \sqcup_Z Y$ satisfying $if = jg$, universal among such cocones. For every object W with maps $p\colon X \to W$ and $q\colon Y \to W$ satisfying $pf = qg$ there is a unique $h\colon X \sqcup_Z Y \to W$ with $hi = p$ and $hj = q$.

A pushout glues X and Y along the images of Z: the map f marks a copy of Z inside X, the map g

marks a copy inside Y, and $X \sqcup_Z Y$ is the result of identifying the two marked copies. In **Set** it is the quotient of $X \sqcup Y$ by the relation $f(z) \sim g(z)$, which is why the pushout is the formal model of every "glue two pieces along a common part" construction. When $Z = 0$ is initial the constraint is vacuous and the pushout is the coproduct $X \sqcup Y$, exactly as a pullback over a terminal object is a product.

Example 63.3.9: Pushouts as Gluing
Two instances show the gluing.

1. In **Set**, if $Z \hookrightarrow X$ and $Z \hookrightarrow Y$ are inclusions of a common subset, the pushout $X \sqcup_Z Y$ is the union of X and Y overlapping exactly along Z: form the disjoint union $X \sqcup Y$ and identify each copy of a point of Z. Explicitly it is $(X \sqcup Y)/\!\sim$ with $\iota_1 f(z) \sim \iota_2 g(z)$, the coequalizer of the two maps $Z \rightrightarrows X \sqcup Y$ given by $\iota_1 f$ and $\iota_2 g$.
2. In **Top** the same colimit glues spaces. Taking X and Y to be two closed disks D^2 and $Z = S^1$ their common boundary circle, mapping into each by the boundary inclusion, the pushout $D^2 \sqcup_{S^1} D^2$ is the 2-sphere S^2: two disks glued along their boundary. This is the mechanism behind attaching cells and building spaces from simpler pieces, the staple of the algebraic topology of CW complexes.

The two constructions from which every colimit is built are now in hand: coproducts assemble a family of objects, and coequalizers impose relations. The dual of theorem 63.2.8 states that these two suffice, and its proof is that theorem read in the opposite category. The motivation is the same as in the limit case: to check that a category has all small colimits, it is enough to check two constructions rather than one for every diagram shape.

Theorem 63.3.10: Colimits from Coproducts and Coequalizers

Let C be a category with all small coproducts and all coequalizers. Then C has all small colimits. Concretely, the colimit of a diagram $D\colon J \to C$ with J small is the coequalizer of a canonical parallel pair of maps between two coproducts,

$$\coprod_{(u\colon\, j \to k) \in \operatorname{mor} J} Dj \;\rightrightarrows\; \coprod_{j \in \operatorname{ob} J} Dj \longrightarrow \operatorname*{colim}_J D$$

where the first coproduct is indexed by the morphisms of J and the second by its objects.

***Proof*:**
By proposition 63.3.2, a colimit of $D\colon J \to C$ is a limit of $D^{\mathrm{op}}\colon J^{\mathrm{op}} \to C^{\mathrm{op}}$. The hypotheses transport across the duality principle (box 61.3.3): a coproduct in C is a product in C^{op} and a coequalizer in C is an equalizer in C^{op}, so C having all small coproducts and coequalizers is C^{op} having all small products and equalizers. Theorem 63.2.8 then applies in C^{op} and produces the limit of D^{op}, hence the colimit of D. This proves existence; it remains only to record what the construction of that theorem becomes when read back in C.

The construction of theorem 63.2.8 builds a limit as an equalizer of two maps between the product $\prod_j Dj$ over the objects and the product $\prod_u D(\operatorname{cod} u)$ over the morphisms. Dualizing every arrow turns each product into a coproduct and the equalizer into a coequalizer, giving the coproduct $\coprod_j Dj$ over the objects, the coproduct $\coprod_u D(\operatorname{dom} u)$ over the morphisms, and

a coequalizer of two maps between them. Concretely, for a morphism $u\colon j \to k$ of J the u-th summand Dj of the source coproduct is sent by the two maps to the object coproduct in two ways: one injection includes Dj as the j-th summand directly, and the other sends it through $Du\colon Dj \to Dk$ into the k-th summand. Writing $\iota_j\colon Dj \to \coprod_j Dj$ for the coproduct injections, the two maps $s, t\colon \coprod_u Dj \to \coprod_j Dj$ are determined on the u-th summand by

$$s \circ \iota_u = \iota_j, \qquad t \circ \iota_u = \iota_k \circ Du$$

Their coequalizer $q\colon \coprod_j Dj \to Q$ forces $q\iota_j$ and $q\iota_k \circ Du$ to become equal for every u, since $qs = qt$ reads $q\iota_j = q\iota_k \circ Du$ on the u-th summand. This is exactly the cocone compatibility for the maps $q\iota_j$. So the maps $q\iota_j\colon Dj \to Q$ form a cocone under D, and the coequalizer's universal property makes it the initial one: a cocone $(Y, \{\kappa_j\})$ is a family with $\kappa_k \circ Du = \kappa_j$, which is a map $\langle \kappa_j \rangle\colon \coprod_j Dj \to Y$ coequalizing s and t, hence factoring uniquely through q. Thus $Q = \operatorname{colim}_J D$, completing the proof.

The theorem and its proof are the mirror of the limit case in the strict sense that not one line of new mathematics was needed: proposition 63.3.2 moves the problem to C^{op}, the duality principle converts the hypotheses, and theorem 63.2.8 does the work. The dual construction is worth carrying explicitly all the same, because the coequalizer of two maps between coproducts is how a colimit is computed: assemble every object of the diagram into one coproduct, then force the relations that the morphisms of J impose. The equalizer-of-products picture cut a sub-object out of an assembly; the coequalizer-of-coproducts picture builds an assembly and then collapses it.

This is the interpretive content of the whole duality. Limits and colimits are two readings of one definition, exchanged by reversing arrows, and the exchange is not a formal trick but a difference in operation. A limit intersects and cuts out: the product is the joint object seen from all its projections, the equalizer is the locus where two maps agree, the pullback is the fibered intersection over a shared target. A colimit glues and quotients: the coproduct sets objects side by side, the coequalizer imposes relations, the pushout glues along a shared source. The product cuts $\prod X_i$ down by an equalizer to enforce compatibility; the coproduct is quotiented by a coequalizer to enforce it. Each theorem, each construction, and each computation of section 63.2 therefore has a twin here, obtained for free by the duality principle, and the two families are the same mathematics viewed from opposite sides.

63.4 Computing (Co)limits

The previous sections built limits and colimits abstractly and reduced their existence to two special cases: products and equalizers on one side, coproducts and coequalizers on the other (theorem 63.2.8 and its dual). This section shows the constructions: a name for the categories in which every diagram has a limit; the working principle that in the algebraic categories a limit is computed on underlying sets while a colimit usually is not; the pointwise computation in functor and presheaf categories; and the functors that carry limits to limits, the representable ones foremost. That last result closes the loop with Chapter 2: an object sees limits through its hom-functor exactly because of Yoneda.

We fix conventions once. A category has *all small limits* if every diagram $D\colon J \to C$ indexed by a small category J has a limit, and likewise for colimits.

Definition 63.4.1: Complete and Cocomplete Categories

A category C is *complete* if it has all small limits, that is, if every diagram $D\colon J \to C$ with J small has a limit $\lim D$. It is *cocomplete* if it has all small colimits, that is, if every such diagram has a colimit $\operatorname{colim}_J D$.

Completeness is a strong hypothesis stated compactly, but it need never be checked diagram by diagram. Theorem 63.2.8 constructed the limit of an arbitrary diagram from a pair of products and one equalizer, so a category that has all small products and all equalizers already has all small limits. This is the only test one runs in practice.

Proposition 63.4.2: Completeness from Products and Equalizers

A category C is complete if and only if it has all small products and all equalizers. Dually, C is cocomplete if and only if it has all small coproducts and all coequalizers.

***Proof*:**
If C is complete it has, in particular, all products (limits of discrete diagrams) and all equalizers (limits over the parallel-pair shape), so the forward direction is immediate. Conversely, suppose C has all small products and all equalizers. Given any diagram $D\colon J \to C$ with J small, the construction of theorem 63.2.8 builds $\lim D$ as the equalizer of two maps between the product $\prod_j Dj$ over the objects of J and the product $\prod_u D(\operatorname{cod} u)$ over the morphisms of J; both products are small because J is small. Hence $\lim D$ exists, and C is complete. The colimit statement is the dual, obtained by applying the same argument in C^{op} (box 61.3.3): a coproduct in C is a product in C^{op}, a coequalizer in C is an equalizer in C^{op}, and completeness of C^{op} is cocompleteness of C, completing the proof.

The categories of the standing cast are all complete and cocomplete: **Set**, **Grp**, **Ab**, **Ring**, $\mathbf{Mod}_R$, and **Top** each have all small limits and colimits. For **Set** this is direct, and completeness of the rest follows from the next result once the limits are located inside **Set**. Cocompleteness holds too, but its proof is not dual in content: by proposition 63.4.2 it suffices to have all small coproducts and all coequalizers, and in the algebraic categories these are the free constructions and quotients of [21] (free products in **Grp**, direct sums in **Ab** and $\mathbf{Mod}_R$, and quotients by the relations generated for coequalizers), while **Top** carries the quotient and coproduct topologies. The second half of this section does not reprove these but illustrates the point that colimits are built by their own universal properties rather than read off underlying sets.

The pattern that makes limits computable in the algebraic categories is that the forgetful functor to **Set** does more than preserve them, it *creates* them: the underlying set of a limit is the limit of the underlying sets, and the algebraic structure on it is forced. A product of groups is the product set with coordinatewise multiplication; the equalizer of two homomorphisms is the subset where they agree, which is a subgroup because the operations are computed coordinatewise. The precise statement follows; the notion of creation is made formal later in this section (definition 63.4.6), but the content here is elementary and self-contained.

Proposition 63.4.3: Limits in the Algebraic Categories

Let C be any of **Grp**, **Ab**, **Ring**, or $\mathbf{Mod}_R$, and let $U\colon C \to \mathbf{Set}$ be the forgetful functor. Then C is complete, and U *creates* all small limits: for a diagram $D\colon J \to C$, every limit cone of UD in **Set** lifts to a unique cone in C lying over it, and that cone is a limit. In particular the underlying set of $\lim D$ is $\lim(UD)$, computed in **Set**, with the algebraic operations defined coordinatewise. Concretely:

1. *Products.* The product $\prod_i X_i$ has underlying set the Cartesian product $\prod_i UX_i$, with the operations applied coordinatewise; the projections $\pi_j\colon \prod_i X_i \to X_j$ are the coordinate projections.
2. *Equalizers.* The equalizer of two morphisms $f, g\colon X \to Y$ is the subobject $E = \{x \in UX \,|\, f(x) = g(x)\}$ with the operations inherited from X; the equalizing morphism $E \to X$ is the inclusion.

The same holds for **Top**, with the limit set carrying the initial topology for the cone maps.

***Proof*:**
By proposition 63.4.2 it suffices to treat products and equalizers and to assemble the general limit from these by theorem 63.2.8, since creation is inherited stage by stage: a functor that creates products and equalizers creates every limit built from them. For each of the two shapes the argument shows more than preservation. Starting from a limit cone in **Set** (the Cartesian product with its projections, or the agreement subset with its inclusion), the algebraic operations that turn it into a cone in C are forced coordinatewise, so the lift is unique; the lifted cone is then verified to be a limit in C; and U returns it to the given cone in **Set**. That is creation (definition 63.4.6), and preservation and completeness of C follow.

Step 1: Products. Take a small family $(X_i)_{i\in I}$ in C. Let P be the Cartesian product $\prod_i UX_i$ of underlying sets, an element of which is a family $(x_i)_i$ with $x_i \in UX_i$. Define the algebraic operations coordinatewise: for **Grp**, $(x_i)(y_i) = (x_iy_i)$ with identity (e_i) and inverse $(x_i)^{-1} = (x_i^{-1})$; for a ring or module the addition and multiplication (or scalar action) are applied in each coordinate. The group, ring, or module axioms hold in P because they hold in each X_i and are tested coordinatewise. The coordinate projections $\pi_j\colon P \to X_j$, $(x_i) \mapsto x_j$, are morphisms of C because the operations on P are coordinatewise. Given any Z in C with morphisms $h_i\colon Z \to X_i$, the set map $h\colon UZ \to P$, $z \mapsto (h_i(z))_i$, is the unique function with $\pi_j h = h_j$ for all j (this is the universal property of the product in **Set**), and it is a morphism of C because each h_i is and the operations on P are coordinatewise. So P with the π_j is the product in C, and $UP = \prod_i UX_i$ is the product in **Set**; thus U preserves it. The lift is unique: any operations on the set $\prod_i UX_i$ making the coordinate projections into morphisms of C must agree with each X_j in that coordinate, hence be the coordinatewise ones, so this is the only structure lying over the **Set** product. That is creation for the product shape.

Step 2: Equalizers. Take $f, g\colon X \to Y$ in C and set $E = \{x \in UX \,|\, f(x) = g(x)\} \subseteq UX$, which is the equalizer of Uf and Ug in **Set**. The subset E is closed under the operations of X: if $f(x) = g(x)$ and $f(x') = g(x')$ then, since f and g are morphisms, $f(xx') = f(x)f(x') = g(x)g(x') = g(xx')$, and likewise f and g agree on the identity, on inverses, and on scalar

multiples. Hence E is a subgroup, subring, or submodule of X, and with these inherited operations the inclusion $e\colon E \to X$ is a morphism of C with $fe = ge$. If $h\colon Z \to X$ satisfies $fh = gh$ then h lands in E at the level of sets, so it factors uniquely as $h = eh'$ through the set map $h'\colon UZ \to E$; and h' is a morphism of C because its composite with the inclusion is and E carries the inherited operations. So E is the equalizer in C, and UE is the equalizer in **Set**. Again the lift is unique: the subset E inherits its operations from X by restriction, the only structure making the inclusion a morphism, so the cone over the **Set** equalizer is forced. That is creation for the equalizer shape.

Step 3: Topological spaces. For **Top** the same two constructions work on underlying sets, and the topology is forced: the product carries the product topology (the coarsest making every projection continuous) and the equalizer carries the subspace topology. In each case this is the coarsest topology making the cone maps continuous, so a map out of a test space is continuous exactly when its composites with the cone maps are, which is the universal property. The initial topology is the unique one making the cone maps continuous while giving the universal property, so here too the lift over the **Set** limit is unique: $U\colon$ **Top** $\to$ **Set** creates these limits as well. By proposition 63.4.2 every category listed is complete with limits computed on underlying sets, completing the proof.

The proposition is what lets one compute in these categories at all: a limit is found by taking the limit of the underlying sets and then observing that the algebraic structure has nowhere else to go. The equalizer clause is the categorical form of a familiar move, that the locus where two homomorphisms agree is a subgroup. The kernel of a group or module homomorphism $f\colon G \to H$ is the special case where g is the trivial homomorphism (written $g = 0$ in the additive case), so such kernels are equalizers, and the general limit packages products with these agreement loci. In **Ring** the zero map is not a morphism, so a ring-map kernel is an ideal rather than an equalizer; the equalizer description here stays in the group and module setting.

The contrast the reader should carry forward is that colimits are not computed this way. The forgetful functor does not create colimits: the coproduct in **Grp** is the free product, whose underlying set is far larger than the disjoint union of the underlying sets.

Example 63.4.4: The Coproduct in Grp Is Not the Disjoint Union

In **Set** the coproduct is the disjoint union $X \sqcup Y$. In **Grp** the coproduct of G and H is the *free product* $G * H$, whose elements are the reduced words alternating between nontrivial elements of G and of H ([21], free products). Its universal property is the one required of a coproduct: a pair of homomorphisms $G \to K$ and $H \to K$ extends uniquely to $G * H \to K$. Take $G = H = \mathbb{Z}/2$, generated by a and b respectively. The disjoint union of the underlying sets has four elements, while $\mathbb{Z}/2 * \mathbb{Z}/2$ is infinite: it contains the distinct reduced words $a, b, ab, ba, aba, bab, \ldots$ and is isomorphic to the infinite dihedral group. So $U(G * H) \neq UG \sqcup UH$, and the forgetful functor does not preserve this coproduct. In **Ab** the coproduct of G and H is instead the direct sum $G \oplus H$, which for two groups agrees with the product, and its underlying set is $UG \times UH$, not $UG \sqcup UH$: even the abelian coproduct is not the set-level coproduct.

The lesson is that "compute on underlying sets" is a statement about limits, and that colimits in the algebraic categories must be built by their own universal property (free constructions, quotients, amalgamation) rather than read off the forgetful functor. Coequalizers, for instance, are quotients rather than subobjects.

The functor and presheaf categories behave better: there both limits and colimits are computed pointwise, one object of the indexing category at a time. This is what makes presheaf theory computable, and the reason presheaf categories inherit completeness and cocompleteness from **Set**.

Proposition 63.4.5: Pointwise Limits in Functor Categories

Let J be a small category and C a category, and let $[J, C]$ be the functor category (definition 61.5.4). Suppose C is complete. Then $[J, C]$ is complete, and limits are computed *pointwise*: for a diagram $F\colon I \to [J, C]$ indexed by a small category I, the limit $\lim_I F$ is the functor

$$\Big(\lim_I F\Big)(j) = \lim_I \big(F(-)(j)\big)$$

sending each object j of J to the limit in C of the diagram $i \mapsto F(i)(j)$. Dually, if C is cocomplete then $[J, C]$ is cocomplete, with colimits computed pointwise. In particular the presheaf category $\mathbf{PSh}(C) = [C^{\mathrm{op}}, \mathbf{Set}]$ (definition 62.3.1) is complete and cocomplete, and both are computed pointwise from **Set**.

***Proof*:**
Write $G_j = \lim_I \big(F(-)(j)\big)$ for the object of C obtained by taking, for a fixed j, the limit of the diagram $i \mapsto F(i)(j)$; it exists because C is complete. Let $\lambda_i^j\colon G_j \to F(i)(j)$ be the limit cone.

Step 1: The pointwise limits assemble into a functor. For a morphism $u\colon j \to j'$ in J and each i, the maps $F(i)(u)\colon F(i)(j) \to F(i)(j')$ are compatible with the diagram in I, since each $F(i)$ is a functor and the arrows of the diagram over I are natural transformations, so the family $\big(F(i)(u) \circ \lambda_i^j\big)_i$ is a cone over $i \mapsto F(i)(j')$. By the universal property of $G_{j'}$ there is a unique map $G(u)\colon G_j \to G_{j'}$ with $\lambda_i^{j'} \circ G(u) = F(i)(u) \circ \lambda_i^j$ for all i. Uniqueness makes G functorial: $G(1_j) = 1_{G_j}$ and $G(u'u) = G(u')G(u)$, because both sides satisfy the equations defining the induced map. So $G\colon J \to C$ is a functor, an object of $[J, C]$, and the maps $\lambda_i^\bullet\colon G \Rightarrow F(i)$ are natural transformations, a cone over F in $[J, C]$.

Step 2: This cone is a limit. Let H be a functor in $[J, C]$ with a cone $\mu_i\colon H \Rightarrow F(i)$. For each fixed j the components $(\mu_i)_j\colon H(j) \to F(i)(j)$ form a cone over $i \mapsto F(i)(j)$ in C, so there is a unique map $\varphi_j\colon H(j) \to G_j$ with $\lambda_i^j \circ \varphi_j = (\mu_i)_j$ for all i. The components φ_j are natural in j: for $u\colon j \to j'$, both $G(u)\varphi_j$ and $\varphi_{j'}H(u)$ are maps $H(j) \to G_{j'}$ that, after composing with each $\lambda_i^{j'}$, give $(\mu_i)_{j'}H(u) = F(i)(u)(\mu_i)_j$, so they agree by the uniqueness in the universal property of $G_{j'}$. Hence $\varphi\colon H \Rightarrow G$ is a natural transformation with $\lambda_i^\bullet \circ \varphi = \mu$, and it is the unique such because each φ_j was forced. So G with the cone $\lambda_i^\bullet$ is the limit of F in $[J, C]$. The colimit statement is the dual (box 61.3.3), and applying both to $C = \mathbf{Set}$, which is complete and cocomplete, gives the claim for $\mathbf{PSh}(C)$, completing the proof.

The proposition says that a (co)cone in $[J, C]$ is exactly an objectwise-compatible family of (co)cones in C: naturality is what glues the pointwise data into a morphism of functors, and the universal property is checked one object at a time. For presheaves this means every limit and colimit is computed in **Set** and then reassembled, so all the set-level formulas transfer verbatim. A product of presheaves is the objectwise product of sets, a colimit of presheaves is the objectwise colimit, and representable presheaves, while not closed under these operations, sit inside a category where every

limit and colimit exists.

Having located limits in specific categories, the next results treat how limits behave under functors. Three conditions arrange the possibilities: a functor may carry limit cones to limit cones, may detect a limit from its image, or may lift limits from the target to the source. These are preservation, reflection, and creation.

Definition 63.4.6: Preserving, Reflecting, and Creating Limits

Let $G\colon C \to D$ be a functor and $F\colon J \to C$ a diagram.

1. G *preserves* the limit of F if, whenever $(\lim F, \lambda)$ is a limit cone in C, its image $(G(\lim F), G\lambda)$ is a limit cone over GF in D.
2. G *reflects* limits if a cone (L, λ) over F in C is a limit cone whenever its image $(GL, G\lambda)$ is a limit cone over GF in D.
3. G *creates* the limit of F if, given any limit cone (M, μ) over GF in D, there is a cone (L, λ) over F in C with $GL = M$ and $G\lambda = \mu$, this cone is a limit of F, and it is the unique cone in C (up to the induced isomorphism) lying over (M, μ).

The dual notions, for colimits and cocones, are named identically.

Creation is the strongest of the three and is what proposition 63.4.3 really established: the forgetful functor $U\colon \mathbf{Grp} \to \mathbf{Set}$ creates limits, because a limit cone downstairs in **Set** lifts to a unique cone of groups, and that cone is a limit. Creation implies preservation and reflection together. Preservation alone is the condition that appears most often, and the hom-functor is the instance developed next. A morphism into a limit is the same data as a compatible family of morphisms into the diagram, which is precisely what the hom-set of the limit computes.

Proposition 63.4.7: Representable Functors Preserve Limits

Let C be a locally small category and c an object. The covariant hom-functor $\mathrm{Hom}(c, -)\colon C \to \mathbf{Set}$ (definition 62.1.1) preserves all limits that exist in C: for any diagram $D\colon J \to C$ with a limit,

$$\mathrm{Hom}\Big(c, \lim_J D\Big) \;\cong\; \lim_J \mathrm{Hom}(c, D-)$$

naturally in c, where the right-hand limit is taken in **Set**. Dually, $\mathrm{Hom}(-, c)\colon C^{\mathrm{op}} \to \mathbf{Set}$ sends colimits in C to limits in **Set**.

***Proof*:**
Let $(\lim_J D, \lambda)$ be the limit cone in C, with legs $\lambda_j\colon \lim_J D \to Dj$. Apply $\mathrm{Hom}(c, -)$: the images $(\lambda_j)_*\colon \mathrm{Hom}(c, \lim_J D) \to \mathrm{Hom}(c, Dj)$ form a cone over $\mathrm{Hom}(c, D-)$ in **Set**, since post-composition is functorial and the λ_j commute with the diagram. It remains to show this cone is a limit in **Set**, that is, that $\mathrm{Hom}(c, \lim_J D) \to \lim_J \mathrm{Hom}(c, Dj)$ is a bijection.

Step 1: The target is the set of compatible families. A limit in **Set** is the set of compatible families over the diagram (the equalizer inside a product built in theorem 63.2.8), so an element of $\lim_J \mathrm{Hom}(c, Dj)$ is a family $(g_j)_j$ with $g_j \in \mathrm{Hom}(c, Dj)$ such that for every morphism $u\colon j \to j'$

in J one has $Du \circ g_j = g_{j'}$. That is exactly a cone over D with apex c: a family of maps $g_j \colon c \to Dj$ compatible with the diagram.

Step 2: Cones with apex c correspond to maps into the limit. The universal property of $\lim_J D$ says precisely that cones over D with apex c are in bijection with morphisms $c \to \lim_J D$: to each cone (g_j) there is a unique $g \colon c \to \lim_J D$ with $\lambda_j g = g_j$, and every $g \colon c \to \lim_J D$ yields the cone $(\lambda_j g)_j$. Under the identification of Step 1, this bijection is exactly the map $g \mapsto ((\lambda_j)_* g)_j = (\lambda_j g)_j$, so $(\lambda_j)_* \colon \mathrm{Hom}(c, \lim_J D) \to \lim_J \mathrm{Hom}(c, Dj)$ is a bijection. Hence the cone is a limit, and $\mathrm{Hom}(c, -)$ preserves the limit of D. Naturality in c is functoriality of the two-sided hom-bifunctor (definition 62.1.4): a morphism $c' \to c$ induces compatible pre-composition maps on both sides.

Step 3: The dual. Applying the statement in C^{op} (box 61.3.3) gives the second claim. A colimit in C is a limit in C^{op}, and $\mathrm{Hom}_C(-, c) = \mathrm{Hom}_{C^{\mathrm{op}}}(c, -)$; the preservation of C^{op}-limits by $\mathrm{Hom}_{C^{\mathrm{op}}}(c, -)$ reads in C as $\mathrm{Hom}_C(\mathrm{colim}_J D, c) \cong \lim_J \mathrm{Hom}_C(D-, c)$, so $\mathrm{Hom}(-, c)$ carries colimits to limits, completing the proof.

This is the categorical version of a fact used constantly: to map into a limit is to map compatibly into each stage, and to map out of a colimit is to map compatibly out of each stage. It is why a homomorphism into a product is a tuple of homomorphisms, and why a homomorphism out of a quotient or a pushout is a compatible pair. The result also reads from the Yoneda side. By the Yoneda lemma (theorem 62.2.1) an object is determined by the functor $\mathrm{Hom}(-, c)$ it represents, and that functor turns colimits into limits, while $\mathrm{Hom}(c, -)$ preserves limits. So an object's behaviour under limits is legible through its hom-functors, the precise sense in which Chapter 2's lens on objects extends to the constructions of this chapter.

The results combine into a single computation. In **Set** a pullback is the fibered product, and the hom-functor preservation says a map into it is a compatible pair of maps into its factors. This one construction computes intersections and preimages at once.

Example 63.4.8: Pullbacks in Set as Fibered Products

Let $f \colon X \to Z$ and $g \colon Y \to Z$ be functions. Their pullback (definition 63.2.6) in **Set** is the fibered product

$$X \times_Z Y = \{(x, y) \in X \times Y \,|\, f(x) = g(y)\}$$

with the two projections to X and Y. This is a limit, computed on the underlying sets exactly as proposition 63.4.3 prescribes: it is the equalizer of $f \circ \pi_X$ and $g \circ \pi_Y$ inside the product $X \times Y$, so it is the subset where the two composites agree.

Two special cases recover familiar operations.

1. *Intersection.* Let $A, B \subseteq Z$ be subsets, with inclusions $f \colon A \hookrightarrow Z$ and $g \colon B \hookrightarrow Z$. Then $f(a) = g(b)$ forces $a = b$ as elements of Z, so

   $$A \times_Z B = \{(a, b) \in A \times B \,|\, a = b\} \cong A \cap B$$

   The pullback of two subobjects along their inclusions is their intersection.

2. *Preimage.* Let $g \colon Y \to Z$ be arbitrary and take $A \subseteq Z$ with inclusion $f \colon A \hookrightarrow Z$. Then

$A \times_Z Y = \{(a, y) \big| a = g(y)\}$, and the projection to Y identifies it with

$$\{y \in Y \big| g(y) \in A\} = g^{-1}(A)$$

the preimage. Pulling back a subobject along a map is taking its preimage.

The preservation result reads off the maps into $X \times_Z Y$: for a set W,

$$\mathrm{Hom}(W, X \times_Z Y) \cong \{(p, q) \big| p \colon W \to X,\ q \colon W \to Y,\ fp = gq\}$$

which is the equalizer of f_* and g_* inside $\mathrm{Hom}(W, X) \times \mathrm{Hom}(W, Y)$, precisely the pullback in **Set** of the induced hom-sets. So a map into the fibered product is a matching pair of maps into the factors, the concrete face of proposition 63.4.7.

64

Adjunctions

Chapters 1 through 3 built the vocabulary; adjunctions turn it into an organizing principle. An *adjunction* makes precise the sense in which one functor is the best approximate inverse of another: free constructions are adjoint to forgetful ones, colimits and limits to the diagonal, tensoring to hom. This chapter gives the definition in its three equivalent forms, works the examples, and proves the theorem every adjunction obeys, that right adjoints preserve limits, before asking when an adjoint exists at all.

64.1 Adjoint Functors

The previous chapter recognized free constructions, abelianization, and the initial ring as universal arrows, one for each object of a category (definition 63.1.4). When a functor gives such an arrow at *every* object in a coherent way, the two functors involved stand in the relationship this section defines. We give the definition first through a natural isomorphism of hom-sets, then repackage it through a unit and a counit, and prove that these two presentations and the object-by-object universal-arrow condition are the same data. The free-monoid construction runs alongside as the guiding example.

Definition 64.1.1: Adjunction

Let $F\colon C \to D$ and $G\colon D \to C$ be functors. An *adjunction* from F to G is a natural isomorphism

$$\Phi\colon \mathrm{Hom}_D(F-,-) \;\cong\; \mathrm{Hom}_C(-,G-)$$

of functors $C^{\mathrm{op}} \times D \to \mathbf{Set}$; componentwise, for each object c of C and d of D a bijection

$$\Phi_{c,d}\colon \mathrm{Hom}_D(Fc,d) \xrightarrow{\;\cong\;} \mathrm{Hom}_C(c,Gd)$$

natural in c and in d. When such an adjunction exists we say F is *left adjoint* to G and G is *right adjoint* to F, written $F \dashv G$. For a morphism $f\colon Fc \to d$, the corresponding morphism $\Phi_{c,d}(f)\colon c \to Gd$ is its *transpose* (or *adjunct*), and likewise $\Phi_{c,d}^{-1}(g)$ is the transpose of $g\colon c \to Gd$.

Naturality is the content of the definition. It says that transposition commutes with composition on both sides: for $u\colon c' \to c$ in C and $v\colon d \to d'$ in D, the transpose of $v \circ f \circ Fu$ is $Gv \circ \Phi_{c,d}(f) \circ u$. Concretely, the naturality square in the C-variable,

$$\begin{array}{ccc} \mathrm{Hom}_D(Fc,d) & \xrightarrow{\Phi_{c,d}} & \mathrm{Hom}_C(c,Gd) \\ {\scriptstyle (Fu)^*}\downarrow & & \downarrow{\scriptstyle u^*} \\ \mathrm{Hom}_D(Fc',d) & \xrightarrow[\Phi_{c',d}]{} & \mathrm{Hom}_C(c',Gd) \end{array}$$

commutes, where $(Fu)^*$ is precomposition with Fu and u^* is precomposition with u; the analogous square in the D-variable uses postcomposition with v and with Gv. The intuition is compact: a map out of the free object Fc is the same datum as a map into the underlying object Gd. The bijection lets one pass between the world where c lives and the world where d lives without loss, and naturality guarantees the passage respects every morphism in sight.

A first structural consequence, stated here and proved in section 64.3, is that either functor determines the other up to isomorphism: if $F \dashv G$ and $F \dashv G'$ then $G \cong G'$, and dually for left adjoints. The reason is that Gd represents the functor $c \mapsto \mathrm{Hom}_D(Fc,d)$, and a representing object is unique up to unique isomorphism (corollary 62.4.1). An adjoint is thus not extra structure to be chosen but a property that F may or may not have, pinned down when it holds.

Example 64.1.2: The Free Monoid and Underlying Set

Let $U\colon \mathbf{Mon} \to \mathbf{Set}$ send a monoid to its underlying set and a homomorphism to its underlying function, and let $F\colon \mathbf{Set} \to \mathbf{Mon}$ send a set X to the free monoid FX of finite words in the alphabet X under concatenation, with the empty word as identity ([21]). A monoid homomorphism $FX \to M$ is determined by its values on the length-one words, which are the elements of X, and any assignment of those values extends uniquely to a homomorphism because a word is a product of letters. Restriction to length-one words and free extension are mutually inverse, so

$$\mathrm{Hom}_{\mathbf{Mon}}(FX,M) \;\cong\; \mathrm{Hom}_{\mathbf{Set}}(X,UM)$$

and the bijection is natural in X and M: precomposing a homomorphism with Ff for $f\colon Y \to X$ corresponds to precomposing the associated function with f, and postcomposing with a homomorphism $M \to N$ corresponds to postcomposing with its underlying function. Thus $F \dashv U$.

The two hom-sets in example 64.1.2 are compared across a change of category, and the bijection is exactly the statement that FX is free on X. Every "free object" theorem in algebra is an instance of this pattern, and the adjunction packages all of them at once. The transpose of the identity of FX under this bijection is the map $X \to UFX$ sending each element to its length-one word, the insertion of generators; the transpose of the identity of UM is a homomorphism $FUM \to M$ evaluating a word of elements of M to their product. These two distinguished maps are the general phenomenon isolated next.

Passing to hom-sets and back is often less convenient than working with two natural transformations, one in each category, from which the whole bijection can be reconstructed. Taking transposes of identity morphisms produces them.

Definition 64.1.3: Unit and Counit

Let $F \dashv G$ with natural isomorphism Φ as in definition 64.1.1. The *unit* of the adjunction is the natural transformation

$$\eta \colon \mathrm{id}_C \Rightarrow GF$$

whose component at c is $\eta_c = \Phi_{c,Fc}(\mathrm{id}_{Fc}) \colon c \to GFc$, the transpose of id_{Fc}. The *counit* is the natural transformation

$$\varepsilon \colon FG \Rightarrow \mathrm{id}_D$$

whose component at d is $\varepsilon_d = \Phi^{-1}_{Gd,d}(\mathrm{id}_{Gd}) \colon FGd \to d$, the transpose of id_{Gd}.

That η and ε are natural transformations follows from the naturality of Φ: naturality in c, applied to the identity, moves η_c along any morphism $c \to c'$ as a component of GF requires, and the counit argument is dual. The unit $\eta_c \colon c \to GFc$ is a universal arrow from c to G in the sense of definition 63.1.4, as the equivalence theorem below makes precise, and the counit $\varepsilon_d \colon FGd \to d$ is a universal arrow from F to d. In example 64.1.2 the unit is the insertion of generators $X \to UFX$ and the counit $FUM \to M$ multiplies out a word of monoid elements.

The unit and counit recover the full hom-set bijection. The transpose of a morphism is obtained by whiskering with the appropriate one and then applying the functor, as the next proposition records; the formulas are the computational core of everything that follows.

Proposition 64.1.4: Transposition via the Unit and Counit

Let $F \dashv G$ with unit η and counit ε as in definition 64.1.3. For every $f \colon Fc \to d$ in D and every $g \colon c \to Gd$ in C,

$$\Phi_{c,d}(f) = Gf \circ \eta_c \colon c \to Gd \tag{64.1}$$

and

$$\Phi^{-1}_{c,d}(g) = \varepsilon_d \circ Fg \colon Fc \to d \tag{64.2}$$

These two assignments are mutually inverse.

***Proof*:**

Step 1: The formula for Φ. Fix $f \colon Fc \to d$. Naturality of Φ in the D-variable, applied to $f \colon Fc \to d$ regarded as a morphism advancing the second argument, gives a commuting square

$$\begin{array}{ccc} \mathrm{Hom}_D(Fc, Fc) & \xrightarrow{\Phi_{c,Fc}} & \mathrm{Hom}_C(c, GFc) \\ {\scriptstyle f_*}\downarrow & & \downarrow{\scriptstyle (Gf)_*} \\ \mathrm{Hom}_D(Fc, d) & \xrightarrow[\Phi_{c,d}]{} & \mathrm{Hom}_C(c, Gd) \end{array}$$

where f_* is postcomposition with f and $(Gf)_*$ is postcomposition with Gf. Chasing id_{Fc} around the square: down then right gives $\Phi_{c,d}(f \circ \mathrm{id}_{Fc}) = \Phi_{c,d}(f)$, while right then down gives $Gf \circ \Phi_{c,Fc}(\mathrm{id}_{Fc}) = Gf \circ \eta_c$ by the definition of the unit. The two are equal, which is (64.1).

Step 2: The formula for Φ^{-1}. The dual computation uses naturality of Φ in the C-variable. Fix $g\colon c \to Gd$ and apply naturality to g advancing the first argument:

$$\begin{array}{ccc} \mathrm{Hom}_D(FGd, d) & \xrightarrow{\Phi_{Gd,d}} & \mathrm{Hom}_C(Gd, Gd) \\ {\scriptstyle (Fg)^*}\downarrow & & \downarrow{\scriptstyle g^*} \\ \mathrm{Hom}_D(Fc, d) & \xrightarrow[\Phi_{c,d}]{} & \mathrm{Hom}_C(c, Gd) \end{array}$$

where $(Fg)^*$ and g^* are precomposition with Fg and g. Chase $\varepsilon_d \in \mathrm{Hom}_D(FGd, d)$ around the square. Right then down gives $g^*\big(\Phi_{Gd,d}(\varepsilon_d)\big) = g^*(\mathrm{id}_{Gd}) = g$, since $\Phi_{Gd,d}(\varepsilon_d) = \mathrm{id}_{Gd}$ by definition 64.1.3. Down then right gives $\Phi_{c,d}\big(\varepsilon_d \circ Fg\big)$. Equating the two, $\Phi_{c,d}(\varepsilon_d \circ Fg) = g$, and applying $\Phi_{c,d}^{-1}$ yields $\Phi_{c,d}^{-1}(g) = \varepsilon_d \circ Fg$, which is (64.2).

Step 3: Mutual inverseness. Because $\Phi_{c,d}$ is a bijection with inverse $\Phi_{c,d}^{-1}$, the two assignments (64.1) and (64.2) are mutually inverse by construction. This can also be checked directly from the triangle identities established in theorem 64.1.5, and the two verifications agree, completing the proof.

Formulas (64.1) and (64.2) are how one computes with an adjunction in practice: to transpose a map out of Fc, apply G and precompose with the unit; to transpose back, apply F and postcompose with the counit. Since the two are inverse, feeding one into the other must return the original morphism, and unwinding what that requires of η and ε alone gives a characterization of adjunctions with no mention of hom-sets. That characterization is the equivalence theorem.

The theorem collects three descriptions of the same situation. The first is the hom-set isomorphism of definition 64.1.1. The second replaces it by the unit and counit subject to two equations, the *triangle identities*, which require only that transposing a map and transposing it back be the identity. The third is the object-by-object universal-arrow condition, tying the chapter back to definition 63.1.4. Their equivalence is what lets one build, recognize, and use adjunctions from whichever description is at hand.

Theorem 64.1.5: Equivalent Formulations of an Adjunction

Let $F\colon C \to D$ and $G\colon D \to C$ be functors. The following data are equivalent, each determining the others.

1. A natural isomorphism $\Phi\colon \mathrm{Hom}_D(F-,-) \cong \mathrm{Hom}_C(-,G-)$, that is, an adjunction $F \dashv G$.
2. Natural transformations $\eta\colon \mathrm{id}_C \Rightarrow GF$ and $\varepsilon\colon FG \Rightarrow \mathrm{id}_D$ satisfying the *triangle identities*
$$(G\varepsilon)(\eta G) = \mathrm{id}_G, \qquad (\varepsilon F)(F\eta) = \mathrm{id}_F \tag{64.3}$$
as natural transformations $G \Rightarrow G$ and $F \Rightarrow F$.
3. A natural transformation $\eta\colon \mathrm{id}_C \Rightarrow GF$ whose component $\eta_c\colon c \to GFc$ is a universal arrow from c to G for every object c of C (definition 63.1.4).

***Proof*:**

We prove (1) $\Rightarrow$ (2) $\Rightarrow$ (3) $\Rightarrow$ (1).

Step 1: From the hom-set isomorphism to the triangle identities. Assume (1), and define η and ε as in definition 64.1.3. They are natural transformations, as noted after that definition. The triangle identities are the componentwise statements

$$G\varepsilon_d \circ \eta_{Gd} = \mathrm{id}_{Gd}, \qquad \varepsilon_{Fc} \circ F\eta_c = \mathrm{id}_{Fc} \tag{64.4}$$

for all c and d. For the first, apply (64.1) of proposition 64.1.4 to the morphism $\varepsilon_d\colon FGd \to d$ with source object Gd: its transpose is $\Phi_{Gd,d}(\varepsilon_d) = G\varepsilon_d \circ \eta_{Gd}$. But $\varepsilon_d = \Phi^{-1}_{Gd,d}(\mathrm{id}_{Gd})$ by definition 64.1.3, so $\Phi_{Gd,d}(\varepsilon_d) = \mathrm{id}_{Gd}$, giving $G\varepsilon_d \circ \eta_{Gd} = \mathrm{id}_{Gd}$. For the second, apply (64.2) to $\eta_c\colon c \to GFc$ with target object Fc: its transpose is $\Phi^{-1}_{c,Fc}(\eta_c) = \varepsilon_{Fc} \circ F\eta_c$, and $\eta_c = \Phi_{c,Fc}(\mathrm{id}_{Fc})$, so this transpose is id_{Fc}. Thus (64.4) holds, which is (64.3).

Step 2: From the triangle identities to universal arrows. Assume (2). Fix an object c; we show $\eta_c\colon c \to GFc$ is a universal arrow from c to G. Given any object d of D and any morphism $g\colon c \to Gd$ in C, we must produce a unique $f\colon Fc \to d$ with $Gf \circ \eta_c = g$.

Existence. Set $f = \varepsilon_d \circ Fg\colon Fc \to d$. Then

$$Gf \circ \eta_c = G\varepsilon_d \circ GFg \circ \eta_c$$

Naturality of η applied to $g\colon c \to Gd$ gives $GFg \circ \eta_c = \eta_{Gd} \circ g$, so

$$Gf \circ \eta_c = G\varepsilon_d \circ \eta_{Gd} \circ g = (G\varepsilon_d \circ \eta_{Gd}) \circ g = \mathrm{id}_{Gd} \circ g = g$$

using the first triangle identity in (64.4). This f solves the factorization problem.

Uniqueness. Suppose $f'\colon Fc \to d$ also satisfies $Gf' \circ \eta_c = g$. Then

$$\varepsilon_d \circ F(Gf' \circ \eta_c) = \varepsilon_d \circ Fg$$

The left side equals $\varepsilon_d \circ FGf' \circ F\eta_c$. Naturality of ε applied to $f'\colon Fc \to d$ gives $\varepsilon_d \circ FGf' = f' \circ \varepsilon_{Fc}$, so the left side is $f' \circ \varepsilon_{Fc} \circ F\eta_c = f' \circ \mathrm{id}_{Fc} = f'$ by the second triangle identity. The right side is our chosen f. Hence $f' = f$, and the universal arrow is unique. Since c was arbitrary, η_c is universal for every c, which is (3).

Step 3: From universal arrows to the hom-set isomorphism. Assume (3): $\eta\colon \mathrm{id}_C \Rightarrow GF$ is a natural transformation whose every component $\eta_c\colon c \to GFc$ is a universal arrow from c to G. Fix c and d and define

$$\Phi_{c,d}\colon \mathrm{Hom}_D(Fc, d) \to \mathrm{Hom}_C(c, Gd), \qquad \Phi_{c,d}(f) = Gf \circ \eta_c$$


The universal property of η_c says exactly that for each $g\colon c \to Gd$ there is a unique $f\colon Fc \to d$ with $Gf \circ \eta_c = g$, that is, $\Phi_{c,d}$ is a bijection. It remains to check naturality in c and d. For $v\colon d \to d'$, both $\Phi_{c,d'}(v \circ f)$ and $Gv \circ \Phi_{c,d}(f)$ equal $Gv \circ Gf \circ \eta_c$, since G is a functor; this is naturality in d. For $u\colon c' \to c$, naturality of η gives $GFu \circ \eta_{c'} = \eta_c \circ u$, whence

$$\Phi_{c',d}(f \circ Fu) = G(f \circ Fu) \circ \eta_{c'} = Gf \circ GFu \circ \eta_{c'} = Gf \circ \eta_c \circ u = \Phi_{c,d}(f) \circ u$$


which is naturality in c. Thus Φ is a natural isomorphism and $F \dashv G$, returning to (1) and closing the cycle, completing the proof.

The theorem is the working definition of an adjunction: one verifies whichever of the three is easiest and gains the other two. Presentation (1) is the cleanest to state and the one that makes symmetry between F and G visible. Presentation (2) is the most convenient in proofs, since the triangle identities are two equations to check rather than a family of bijections, and it survives into contexts where hom-sets are not available. Presentation (3) is the bridge from the last chapter: an adjunction is precisely a functorial choice of universal arrow, one at each object, so the free monoid, abelianization, and the initial ring of section 63.1 were adjunctions seen one object at a time. There is a symmetric fourth form, dual to (3), asking that each counit component $\varepsilon_d\colon FGd \to d$ be a universal arrow from F to d; it follows by applying the theorem in the opposite categories, since $F \dashv G$ in C, D is $G^{\mathrm{op}} \dashv F^{\mathrm{op}}$ in $D^{\mathrm{op}}, C^{\mathrm{op}}$ (box 61.3.3).

The name "triangle identity" comes from the diagrams the equations in (64.4) assert commute. The first says the outer path in



is the identity, and the second says the same of



Read aloud, they say that inserting generators into Gd and then evaluating, or building the free object on Fc and then collapsing it, returns where one started. In example 64.1.2 the first identity says: take a set of generators inside a monoid M (the map η_{UM}), form the free monoid on them, multiply each word out (ε_M), and the underlying-set effect is the identity on UM. The equations look slight, but by theorem 64.1.5 they carry the entire adjunction.

64.2 Examples of Adjunctions

The definition and its three forms are in place; the work of this section is to show how much of the mathematics already met is an adjunction in disguise. Four families cover most of the recurring instances: free constructions adjoint to forgetful functors, tensoring adjoint to hom, colimits and limits adjoint to the diagonal, and Galois connections between posets. Each is presented as a hom-set bijection $\mathrm{Hom}_D(Fc, d) \cong \mathrm{Hom}_C(c, Gd)$ (definition 64.1.1), natural in both variables, with the naturality left to the one-line check it always reduces to. The through-line stated at the definition returns here in its standard form: left adjoints are free constructions.

The first family is the one the definition was built to capture. A forgetful functor discards structure; its left adjoint builds the freest structure on the bare data it was handed. The universal property of a free construction is exactly a hom-set bijection, so each free-forgetful pair is an adjunction with no extra argument to make.

Example 64.2.1: Free and Forgetful Adjunctions
Across the standing cast, each free construction is left adjoint to the forgetful functor it inverts.

1. *Free group $\dashv$ forgetful.* Let $U\colon \mathbf{Grp} \to \mathbf{Set}$ be the forgetful functor (example 61.4.2) and $F\colon \mathbf{Set} \to \mathbf{Grp}$ the free-group functor. The universal property of the free group FX says that a set function $X \to UG$ extends uniquely to a homomorphism $FX \to G$, and every homomorphism $FX \to G$ restricts to such a function on generators ([21, Universal Property Of Free Groups]). These two operations are mutually inverse, giving a bijection

$$\mathrm{Hom}_{\mathbf{Grp}}(FX, G) \cong \mathrm{Hom}_{\mathbf{Set}}(X, UG)$$

   so $F \dashv U$. Naturality in X and in G is the statement that restriction to generators commutes with precomposing a function on the left and postcomposing a homomorphism on the right, which holds because both sides are "evaluate on generators, then extend."

2. *Free R-module $\dashv$ forgetful.* For a ring R, let $U\colon \mathbf{Mod}_R \to \mathbf{Set}$ forget the module structure and F send a set X to the free module $R^{(X)}$ on X. The universal property of the free module ([21, Universal Property of Free Modules]) gives, for every module M,

$$\mathrm{Hom}_{\mathbf{Mod}_R}(R^{(X)}, M) \cong \mathrm{Hom}_{\mathbf{Set}}(X, UM)$$

   a function $X \to UM$ extending uniquely to an R-linear map on the basis X, so $F \dashv U$. The same check applies with $\mathbf{Vect}_k$ in place of $\mathbf{Mod}_R$: every vector space is free, so the left adjoint here sends a set to the space with that basis.

3. *Abelianization $\dashv$ inclusion.* Let $\iota\colon \mathbf{Ab} \to \mathbf{Grp}$ be the inclusion of abelian groups among all groups and $\mathrm{ab}\colon \mathbf{Grp} \to \mathbf{Ab}$ send G to its abelianization $G^{\mathrm{ab}} = G/[G, G]$. A homomorphism from G to an abelian group A kills every commutator, hence factors uniquely through the quotient $G \to G^{\mathrm{ab}}$ ([21, Commutator Subgroup Properties]), which is the bijection

$$\mathrm{Hom}_{\mathbf{Ab}}(G^{\mathrm{ab}}, A) \cong \mathrm{Hom}_{\mathbf{Grp}}(G, \iota A)$$

   so $\mathrm{ab} \dashv \iota$. Here the "structure" the right adjoint remembers is commutativity, and the left adjoint imposes it as freely as possible, by quotienting out only what commutativity forces.

4. *Discrete ⊣ forgetful ⊣ indiscrete.* Let $U\colon \mathbf{Top} \to \mathbf{Set}$ forget the topology. It has adjoints on both sides. The *discrete* functor $\mathrm{disc}\colon \mathbf{Set} \to \mathbf{Top}$ equips a set with its discrete topology, in which every subset is open; the *indiscrete* functor indisc equips it with the indiscrete topology, whose only opens are $\varnothing$ and the whole set. Every function out of a discrete space is continuous and every function into an indiscrete space is continuous, so

$$\mathrm{Hom}_{\mathbf{Top}}(\mathrm{disc}\, X, Y) \cong \mathrm{Hom}_{\mathbf{Set}}(X, UY), \qquad \mathrm{Hom}_{\mathbf{Set}}(UY, X) \cong \mathrm{Hom}_{\mathbf{Top}}(Y, \mathrm{indisc}\, X)$$

The first bijection makes $\mathrm{disc} \dashv U$; the second makes $U \dashv \mathrm{indisc}$. Thus U is at once a right adjoint and a left adjoint, so it preserves both limits and colimits, a fact the next section will read off directly.

The first three items instantiate one pattern: the forgetful functor is a right adjoint and its left adjoint is the free construction, which is why free objects are recovered by the recipe "the value of the left adjoint on a set." The last item is different. A forgetful functor need not sit on only one side of an adjunction; when the structure being forgotten can be added in a freest and a cofreest way, it acquires adjoints on both. The point to carry forward is that a left adjoint is a free construction and a right adjoint is a forgetful or cofree one, with the hom-set bijection the precise content of "free."

The second family trades one bifunctor for two others. Fixing one input of a product and asking to map out of it is the same as mapping into a function object; this is currying, and in its module form it is the tensor-hom adjunction that pervades homological algebra. The prototype is in **Set**, where the function object is a plain set of functions.

Example 64.2.2: The Tensor-Hom Adjunction

Fix a set B. Currying converts a function of two variables into a function valued in functions: a map $A \times B \to C$ is the same as a map $A \to C^B$ sending a to the function $b \mapsto f(a, b)$, where $C^B = \mathrm{Hom}_{\mathbf{Set}}(B, C)$ is the set of functions $B \to C$. This assignment is a bijection, natural in A and C,

$$\mathrm{Hom}_{\mathbf{Set}}(A \times B, C) \cong \mathrm{Hom}_{\mathbf{Set}}(A, C^B)$$

so the functor $(-) \times B$ is left adjoint to $(-)^B = \mathrm{Hom}_{\mathbf{Set}}(B, -)$. This is the *cartesian closure* of **Set**: each product functor has the corresponding function-object functor as a right adjoint.

The module version replaces the product by the tensor product. Let R be a commutative ring and fix an R-module B. The defining property of the tensor product ([21, Universal Property Of Tensor Product (Over Commutative Rings)]) is that R-bilinear maps $A \times B \to C$ correspond to R-linear maps $A \otimes_R B \to C$; currying the second variable identifies a bilinear map with an R-linear map $A \to \mathrm{Hom}_R(B, C)$, giving the bijection

$$\mathrm{Hom}_R(A \otimes_R B, C) \cong \mathrm{Hom}_R(A, \mathrm{Hom}_R(B, C))$$

natural in A and C. Thus $(-) \otimes_R B$ is left adjoint to $\mathrm{Hom}_R(B, -)$.

The tensor-hom adjunction is why tensoring and hom behave as complementary halves of the same structure: the left adjoint $(-) \otimes_R B$ and the right adjoint $\mathrm{Hom}_R(B, -)$ are tied by a natural bijection, and the preservation theorem of the next section will explain from this alone why tensoring is right exact and hom left exact. The **Set** prototype is the same phenomenon with $\times$ for $\otimes$ and the bare function set for the internal hom; a category carrying such an adjunction for each fixed object is called closed, a notion the monoidal chapter returns to.

The third family exhibits limits and colimits themselves as adjoints. A single diagram-valued functor, the diagonal, has the limit on one side and the colimit on the other, so the two constructions of the previous chapter are the two adjoints of one functor.

Recall the diagonal functor $\Delta\colon \mathbf{C} \to [J, \mathbf{C}]$ sending an object X to the constant diagram at X, the diagram taking every object of J to X and every morphism to 1_X (section 63.2). A natural transformation $\Delta X \Rightarrow D$ is exactly a cone over D with apex X, and a natural transformation $D \Rightarrow \Delta X$ is exactly a cocone under D with nadir X. This identification turns the universal properties of the limit and the colimit into hom-set bijections.

Example 64.2.3: Limits and Colimits as Adjoints to the Diagonal
Let J be a small category and suppose $\mathbf{C}$ has all limits and all colimits of shape J, so that $\lim\colon [J, \mathbf{C}] \to \mathbf{C}$ and $\operatorname{colim}\colon [J, \mathbf{C}] \to \mathbf{C}$ are defined. Then

$$\operatorname{colim} \dashv \Delta \dashv \lim$$

the colimit is left adjoint to the diagonal and the limit is right adjoint to it.

The two adjunctions are dual, and each is immediate once the naturality bijection is unwound. Only the $\Delta \dashv \lim$ side is proved; the $\operatorname{colim} \dashv \Delta$ side is the same argument in $\mathbf{C}^{\mathrm{op}}$ by the duality principle (box 61.3.3), since a colimit in $\mathbf{C}$ is a limit in $\mathbf{C}^{\mathrm{op}}$ (proposition 63.3.2) and Δ is self-opposite.

***Proof*:**
Fix an object X of $\mathbf{C}$ and a diagram D in $[J, \mathbf{C}]$. A morphism in the functor category $\mathrm{Hom}_{[J,\mathbf{C}]}(\Delta X, D)$ is a natural transformation $\alpha\colon \Delta X \Rightarrow D$ (definition 61.5.4): a family of components $\alpha_j\colon X \to Dj$, one for each object j of J, such that for every morphism $u\colon j \to j'$ of J the naturality square commutes. Since ΔX sends u to 1_X, that square reads $Du \circ \alpha_j = \alpha_{j'} \circ 1_X = \alpha_{j'}$, which is exactly the cone condition (definition 63.2.1). A natural transformation $\Delta X \Rightarrow D$ is therefore the same data as a cone over D with apex X.

By the universal property of the limit, a cone over D with apex X corresponds to a unique morphism $X \to \lim D$ commuting with the projections, and every morphism $X \to \lim D$ arises this way by composing with the limit cone. This correspondence is a bijection

$$\mathrm{Hom}_{\mathbf{C}}(X, \lim D) \cong \mathrm{Hom}_{[J,\mathbf{C}]}(\Delta X, D)$$

It is natural in X: precomposing a morphism $X' \to X$ transports a cone with apex X to one with apex X' by the same precomposition on each component, and the induced map to $\lim D$ transforms accordingly. It is natural in D: a morphism of diagrams $D \Rightarrow D'$ postcomposes each cone component and the induced maps to the limits commute by the universal property. The bijection, natural in both variables, is the defining data of an adjunction (definition 64.1.1), so $\Delta \dashv \lim$. The dual identity $\operatorname{colim} \dashv \Delta$ follows by applying this to $\mathbf{C}^{\mathrm{op}}$, completing the proof.

This recovers the limits and colimits of the previous chapter as the two adjoints of a single functor, and it explains a fact used repeatedly downstream: the limit functor is a right adjoint, so it preserves limits. The general preservation theorem is deferred to the next section, but the shape of the consequence can already be stated, that a limit of limits may be computed in either order because the outer limit is a right adjoint. Dually the colimit functor is a left adjoint and preserves colimits. The diagonal, sitting between its two adjoints, is the categorical device that makes "take the limit" and "take the colimit" into functors with formal properties rather than case-by-case constructions.

The last family lives one dimension down, where the categories are posets and a functor is a monotone map. An adjunction between two posets is a pair of monotone maps tied by the single inequality that a hom-set, being either empty or a point, can express.

A poset $(P, \leq)$ is a category with one morphism $p \to q$ when $p \leq q$ and none otherwise (example 61.4.2 treats such thin categories). A functor between posets is a monotone map, and a hom-set $P(p, q)$ has at most one element, present exactly when $p \leq q$. The hom-set bijection defining an adjunction therefore collapses to a biconditional between inequalities.

Definition 64.2.4: Galois Connection

Let P and Q be posets, viewed as categories. A *(monotone) Galois connection* between P and Q is an adjunction $f \dashv g$ between them: a pair of monotone maps $f\colon P \to Q$ and $g\colon Q \to P$ such that for all $p \in P$ and $q \in Q$,

$$f(p) \leq q \quad \Longleftrightarrow \quad p \leq g(q)$$

The map f is the *left adjoint* (or lower adjoint) and g the *right adjoint* (or upper adjoint).

The biconditional is the poset case of the natural bijection $\mathrm{Hom}_Q(fp, q) \cong \mathrm{Hom}_P(p, gq)$: each hom-set is either empty or a single point, so the bijection between them is precisely the equivalence of the two inequalities, and naturality is automatic because there is nothing to compare beyond presence or absence of a morphism. A Galois connection is an adjunction with the analytic content stripped away, leaving the order-theoretic skeleton visible.

A single monotone connection already produces a closure operator, and the classical Galois correspondence is the archetype once one factor is passed to its opposite.

Example 64.2.5: The Galois Correspondence

Let L/k be a finite Galois extension with Galois group $G = \mathrm{Gal}(L/k)$. Write $\mathcal{S}$ for the poset of subgroups of G ordered by inclusion and $\mathcal{F}$ for the poset of intermediate fields $k \subseteq E \subseteq L$ ordered by inclusion. The two maps

$$\mathrm{Fix}\colon \mathcal{S} \to \mathcal{F}, \quad H \mapsto L^H, \qquad \mathrm{Gal}\colon \mathcal{F} \to \mathcal{S}, \quad E \mapsto \mathrm{Gal}(L/E)$$

each reverse inclusions: a larger subgroup fixes a smaller field, and a larger field is fixed by a smaller subgroup ([21, Galois Correspondence]). They satisfy

$$H \subseteq \mathrm{Gal}(L/E) \quad \Longleftrightarrow \quad E \subseteq L^H$$

both sides asserting that every element of H fixes every element of E. Because each map reverses order, the pair is an *antitone* Galois connection, which is a monotone one after replacing $\mathcal{F}$ by its opposite $\mathcal{F}^{\mathrm{op}}$: then $\mathrm{Fix}\colon \mathcal{S} \to \mathcal{F}^{\mathrm{op}}$ and $\mathrm{Gal}\colon \mathcal{F}^{\mathrm{op}} \to \mathcal{S}$ are monotone and the biconditional above is definition 64.2.4. The fundamental theorem of Galois theory ([21, Fundamental Theorem of Galois Theory I]) states that here both composites are the identity, so the connection is an order-reversing bijection between subgroups and intermediate fields.

The example carries two lessons about Galois connections in general. First, an antitone connection is an adjunction only after an opposite category is introduced; the raw pair of order-reversing maps becomes a genuine $f \dashv g$ once one side is flipped, which is the categorical account of why order-reversing correspondences are as natural as order-preserving ones. Second, even when the composites

are not the identity, a Galois connection $f \dashv g$ always yields a *closure operator* $gf\colon P \to P$: it is monotone, satisfies $p \leq gf(p)$, and is idempotent, $gfgf = gf$. The Galois correspondence is the degenerate case where the closure is trivial because gf is the identity; in a general connection the closure operator gf records the "saturation" a subset acquires, exactly as the double annihilator $(-)^{\perp\perp}$ closes a subspace W to $W^{\perp\perp}$. Every adjunction produces such a monad on the domain of its left adjoint, of which the closure operator is the poset instance, a thread the chapter on monads develops.

64.3 Units, Counits, and Preservation

The three formulations of an adjunction are on the table (theorem 64.1.5), and the examples of the previous section show how often one is in play. This section pays off the unit/counit formulation. The unit and counit are tied together by two equations, the triangle identities, and those equations are exactly the data that lets one reconstruct the hom-set bijection. Once the identities are in hand, two structural facts follow with almost no work: an adjoint, when it exists, is determined up to a unique natural isomorphism, and a right adjoint carries every limit that exists to a limit. The second of these, right adjoints preserve limits, explains at one stroke why so many limits in algebra and topology are computed on underlying sets.

Throughout, $F \dashv G$ is an adjunction with $F\colon \mathbf{C} \to \mathbf{D}$ and $G\colon \mathbf{D} \to \mathbf{C}$, unit $\eta\colon \mathrm{id}_{\mathbf{C}} \Rightarrow GF$ and counit $\varepsilon\colon FG \Rightarrow \mathrm{id}_{\mathbf{D}}$, in the notation of definition 64.1.3.

Proposition 64.1.4 computes the hom-set bijection from the unit and counit: the transpose of $g\colon Fc \to d$ is $Gg \circ \eta_c$, and the transpose of $f\colon c \to Gd$ is $\varepsilon_d \circ Ff$. By theorem 64.1.5, the unit and counit of an adjunction satisfy the triangle identities (64.3), which say that the two whiskered composites

$$G \xRightarrow{\eta G} GFG \xRightarrow{G\varepsilon} G, \qquad F \xRightarrow{F\eta} FGF \xRightarrow{\varepsilon F} F$$

are the identity natural transformations of G and of F. Conversely, natural transformations $\eta\colon \mathrm{id}_{\mathbf{C}} \Rightarrow GF$ and $\varepsilon\colon FG \Rightarrow \mathrm{id}_{\mathbf{D}}$ satisfying the triangle identities present an adjunction $F \dashv G$, through the bijection $g \mapsto Gg \circ \eta_c$.

The two equations (64.3) are named for the shape of the diagrams that express them. Reading the whiskered composites ηG, $G\varepsilon$ and $F\eta$, εF as edges, each identity says that a triangle commutes:

$$\begin{array}{ccc} G & \xRightarrow{\eta G} & GFG \\ & {\scriptstyle \mathrm{id}_G} \searrow & \Big\Downarrow {\scriptstyle G\varepsilon} \\ & & G \end{array} \qquad\qquad \begin{array}{ccc} F & \xRightarrow{F\eta} & FGF \\ & {\scriptstyle \mathrm{id}_F} \searrow & \Big\Downarrow {\scriptstyle \varepsilon F} \\ & & F \end{array}$$

Componentwise at objects $d \in \mathbf{D}$ and $c \in \mathbf{C}$, these read $G\varepsilon_d \circ \eta_{Gd} = \mathrm{id}_{Gd}$ and $\varepsilon_{Fc} \circ F\eta_c = \mathrm{id}_{Fc}$.

The identities encode a single fact about the two transpose operations: they are inverse. Everything about how F and G interact through the adjunction, including the naturality of the correspondence, is compressed into these two equations. This makes the unit/counit formulation the computational one, since checking an adjunction reduces to producing η, ε and verifying two triangle equations, with no bijection to construct by hand.

Example 64.3.1: The Free Group Triangle Identities

Let $F\colon \mathbf{Set} \to \mathbf{Grp}$ be the free-group functor and $U\colon \mathbf{Grp} \to \mathbf{Set}$ the forgetful functor, $F \dashv U$ (example 64.1.2). The unit $\eta_S\colon S \to UFS$ includes a set S as the generators of the free group FS. The counit $\varepsilon_G\colon FUG \to G$ is the homomorphism from the free group on the underlying set of G that sends each generator g to the element $g \in G$; it evaluates a formal word in the elements of G as an actual product in G.

The first identity $(U\varepsilon)(\eta U) = \mathrm{id}_U$ reads, at a group G, as follows. Start with an element $g \in UG$. The unit η_{UG} views g as a generator of the free group FUG, that is, as the length-one word g. Then $U\varepsilon_G$ evaluates that word in G, returning the element g. The composite is the identity on UG, as the identity requires.

The second identity $(\varepsilon F)(F\eta) = \mathrm{id}_F$ reads, at a set S, as follows. A reduced word $w = s_1^{\pm 1} \cdots s_n^{\pm 1}$ in FS is sent by $F\eta_S$ to the same formal word, now regarded as living in $FUFS$ (each generator s_i first viewed as a generator of FS, then as an element of UFS, then as a generator of $FUFS$). Applying ε_{FS} evaluates that word back in FS, recovering w. The composite is the identity on FS. The two identities are the two ways "generator" and "evaluate" cancel.

An adjunction determines its right adjoint completely: if a functor has a left adjoint at all, the resulting right adjoint is fixed up to a unique natural isomorphism. This is what justifies the article "the" in "the right adjoint". The proof is a direct application of the Yoneda embedding (definition 62.3.1): a functor value Gd is pinned down by the functor it represents, $\mathrm{Hom}_{\mathbf{C}}(-, Gd)$, and the adjunction identifies that representable with one built from F alone.

Proposition 64.3.2: Uniqueness of Adjoints

Let $F\colon \mathbf{C} \to \mathbf{D}$. If $F \dashv G$ and $F \dashv G'$, then there is a unique natural isomorphism $\theta\colon G \Rightarrow G'$ compatible with the adjunctions, in the sense that it identifies the two transpose bijections. Dually, if $G \dashv F$ and $G' \dashv F$, the two left adjoints G, G' are isomorphic by a unique such natural isomorphism.

***Proof*:**

Fix $d \in \mathbf{D}$. The two adjunctions give, for every $c \in \mathbf{C}$, bijections

$$\mathrm{Hom}_{\mathbf{C}}(c, Gd) \cong \mathrm{Hom}_{\mathbf{D}}(Fc, d) \cong \mathrm{Hom}_{\mathbf{C}}(c, G'd)$$

natural in c, the first from $F \dashv G$ and the second from $F \dashv G'$. Their composite is a natural isomorphism

$$\mathrm{Hom}_{\mathbf{C}}(-, Gd) \cong \mathrm{Hom}_{\mathbf{C}}(-, G'd)$$

of functors $\mathbf{C}^{\mathrm{op}} \to \mathbf{Set}$. The Yoneda embedding $\mathbf{y}\colon \mathbf{C} \to \mathbf{PSh}(\mathbf{C})$ is fully faithful (definition 62.3.1), so this isomorphism of representables is $\mathbf{y}(\theta_d)$ for a unique isomorphism $\theta_d\colon Gd \to G'd$ in $\mathbf{C}$.

It remains to see that the θ_d assemble into a natural transformation $\theta\colon G \Rightarrow G'$. Let $k\colon d \to d'$ in $\mathbf{D}$. Both composite bijections are natural in d as well as in c, since the transpose correspondences

are natural in both variables (definition 64.1.1); consequently the square of representables

$$\begin{array}{ccc} \mathrm{Hom}_{\mathbf{C}}(-, Gd) & \xrightarrow{\cong} & \mathrm{Hom}_{\mathbf{C}}(-, G'd) \\ {\scriptstyle \mathrm{Hom}(-,Gk)}\downarrow & & \downarrow{\scriptstyle \mathrm{Hom}(-,G'k)} \\ \mathrm{Hom}_{\mathbf{C}}(-, Gd') & \xrightarrow{\cong} & \mathrm{Hom}_{\mathbf{C}}(-, G'd') \end{array}$$

commutes. Applying full faithfulness of $\mathbf{y}$ to this commuting square of representables yields $\theta_{d'} \circ Gk = G'k \circ \theta_d$, which is naturality of θ. Uniqueness of each θ_d, hence of θ, is the injectivity of $\mathbf{y}$ on morphisms. The compatibility with the transpose bijections holds by construction, since θ was read off from them.

For the dual statement, if $G \dashv F$ and $G' \dashv F$, then for every c the bijections $\mathrm{Hom}_{\mathbf{D}}(Gc, -) \cong \mathrm{Hom}_{\mathbf{C}}(c, F-) \cong \mathrm{Hom}_{\mathbf{D}}(G'c, -)$ are natural, so the covariant representables $\mathrm{Hom}_{\mathbf{D}}(Gc, -)$ and $\mathrm{Hom}_{\mathbf{D}}(G'c, -)$ are isomorphic; the covariant Yoneda embedding (definition 62.3.1, applied in $\mathbf{D}^{\mathrm{op}}$) delivers a unique natural isomorphism $Gc \cong G'c$ by the same argument, as we sought to show.

Two constructions each solving the same universal problem cannot differ in any observable way, and the isomorphism between them is forced rather than chosen. This is the categorical form of a phenomenon seen repeatedly in chapter 64: the free group on a set, the tensor product of two modules, the coproduct of a family of objects are each unique up to unique isomorphism, and here the reason is uniform, since all three are adjoint (or universal) constructions and Yoneda pins down what an adjoint represents. From now on we speak of *the* left adjoint and *the* right adjoint of a functor, when one exists.

The structural payoff of the section is that right adjoints preserve limits. The mechanism is the same Yoneda argument, now run against a diagram: a right adjoint commutes with a limit because its defining bijection turns the limit-detecting property of Gd into the limit-detecting property inherited through F from representables, which already preserve limits (proposition 63.4.7). The abbreviation RAPL, "right adjoints preserve limits", is standard.

Recall from definition 63.4.6 what preservation means: a functor $G\colon \mathbf{D} \to \mathbf{C}$ *preserves* the limit of $D\colon \mathbf{J} \to \mathbf{D}$ if, whenever $\lim D$ exists with limit cone $(\lambda_j\colon \lim D \to Dj)_j$, the image cone $(G\lambda_j\colon G(\lim D) \to G(Dj))_j$ is a limit cone for $G \circ D$, so that $G(\lim D) \cong \lim(G \circ D)$ canonically.

Theorem 64.3.3: Right Adjoints Preserve Limits

Let $F \dashv G$ with $G\colon \mathbf{D} \to \mathbf{C}$, and let $D\colon \mathbf{J} \to \mathbf{D}$ be a diagram whose limit $\lim D$ exists in $\mathbf{D}$. Then G preserves this limit: the canonical comparison morphism $G(\lim D) \to \lim(G \circ D)$ is an isomorphism, so

$$G(\lim D) \cong \lim_{j \in \mathbf{J}} G(Dj)$$

Dually, a left adjoint preserves all colimits that exist in its domain.

***Proof*:**
Write $L = \lim D$ in $\mathbf{D}$. The claim is that GL, with the cone $(G\lambda_j)_j$, is a limit of $G \circ D$ in $\mathbf{C}$. By the universal property of a limit (definition 63.2.1) this is equivalent to the statement that

for every $c \in \mathbf{C}$ the map

$$\mathrm{Hom}_{\mathbf{C}}(c, GL) \to \lim_j \mathrm{Hom}_{\mathbf{C}}(c, G(Dj)), \qquad f \mapsto (G\lambda_j \circ f)_j$$

is a bijection, where the limit on the right is the limit in **Set** of the diagram $j \mapsto \mathrm{Hom}_{\mathbf{C}}(c, G(Dj))$, that is, the set of cones over $G \circ D$ with apex c. Fix c and compute this hom-set through a chain of bijections, each natural in c.

Step 1: Cross the adjunction. The adjunction $F \dashv G$ gives

$$\mathrm{Hom}_{\mathbf{C}}(c, GL) \cong \mathrm{Hom}_{\mathbf{D}}(Fc, L)$$

natural in c (definition 64.1.1).

Step 2: Use that representables preserve limits. Since $L = \lim D$ in $\mathbf{D}$, the representable $\mathrm{Hom}_{\mathbf{D}}(Fc, -)$ preserves it (proposition 63.4.7):

$$\mathrm{Hom}_{\mathbf{D}}(Fc, L) \cong \lim_j \mathrm{Hom}_{\mathbf{D}}(Fc, Dj)$$

This is the step where the hypothesis that $\lim D$ exists is used: the limit-preservation of G is pulled back from the limit-preservation of a representable.

Step 3: Cross the adjunction back, inside the limit. Applying $F \dashv G$ objectwise in j, and using that these bijections are natural in j so they assemble into an isomorphism of the diagrams whose limits are being taken,

$$\lim_j \mathrm{Hom}_{\mathbf{D}}(Fc, Dj) \cong \lim_j \mathrm{Hom}_{\mathbf{C}}(c, G(Dj))$$

Step 4: Reassemble. Composing the three bijections gives an isomorphism

$$\mathrm{Hom}_{\mathbf{C}}(c, GL) \cong \lim_j \mathrm{Hom}_{\mathbf{C}}(c, G(Dj))$$

natural in c. Tracing an element through the chain shows the composite is $f \mapsto (G\lambda_j \circ f)_j$, the comparison map above. By the Yoneda embedding (definition 62.3.1) a natural isomorphism of the representables $\mathrm{Hom}_{\mathbf{C}}(-, GL)$ and $\mathrm{Hom}_{\mathbf{C}}(-, \lim(G \circ D))$ comes from a unique isomorphism $GL \cong \lim(G \circ D)$, and by naturality this isomorphism is the comparison morphism. Hence G preserves the limit.

The dual statement follows from the duality principle (box 61.3.3): a left adjoint $F \colon \mathbf{C} \to \mathbf{D}$ is $F \dashv G$, so $F^{\mathrm{op}} \colon \mathbf{C}^{\mathrm{op}} \to \mathbf{D}^{\mathrm{op}}$ is a right adjoint (its left adjoint is G^{op}, as one checks by dualizing the hom-set bijection), and a colimit in $\mathbf{C}$ is a limit in $\mathbf{C}^{\mathrm{op}}$. The result just proved, applied to F^{op}, says F^{op} preserves limits in $\mathbf{C}^{\mathrm{op}}$, which is exactly the statement that F preserves colimits in $\mathbf{C}$, completing the proof.

RAPL is a source of both computations and obstructions. On the computational side it says a right adjoint may be evaluated on a limit by evaluating it factorwise: G commutes with products, pullbacks, equalizers, and all other limits. On the obstruction side it gives a fast way to prove a functor is *not* a right adjoint, by exhibiting one limit it fails to preserve. The tensor product $M \otimes_R -$ does not preserve limits (it fails to preserve infinite products in general), so it cannot be a right adjoint; and indeed it is a left adjoint, adjoint to $\mathrm{Hom}_R(M, -)$, and preserves colimits instead (example 64.2.2). A functor that preserves neither all limits nor all colimits can be neither a left nor a right adjoint,

which is one reason adjointness is a strong condition.

The corollary the reader has already met is that a forgetful functor which happens to be a right adjoint computes limits on underlying sets.

Corollary 64.3.4: Limits on Underlying Sets

Let $U\colon \mathbf{D} \to \mathbf{Set}$ be a forgetful functor that has a left adjoint (a free functor $F \dashv U$). Then U preserves all limits that exist in $\mathbf{D}$: the underlying set of a limit in $\mathbf{D}$ is the corresponding limit of underlying sets, with its structure determined by that of the diagram.

***Proof*:**
Immediate from theorem 64.3.3 applied to $F \dashv U$, since U is the right adjoint, as required.

This recovers, and now explains, the pattern computed directly when limits were introduced (definition 63.2.1): the underlying set of a product of groups is the product of the underlying sets with coordinatewise multiplication, the underlying set of an equalizer is the equalizer of underlying sets, and the limit of a diagram of modules is computed on underlying sets. Each forgetful functor in question, from **Grp**, **Ab**, **Ring**, $\mathbf{Mod}_R$, or **Top** to **Set**, is a right adjoint (example 64.2.1), so RAPL forces its compatibility with limits, in the sense of preservation from definition 63.4.6.

Example 64.3.5: Products and Kernels of Abelian Groups
The forgetful functor $U\colon \mathbf{Ab} \to \mathbf{Set}$ has the free-abelian-group functor as left adjoint, so U preserves limits. Two instances show this.

A product $\prod_i A_i$ in **Ab** has underlying set $\prod_i UA_i$, the cartesian product of the underlying sets, because U preserves the product. The group structure is coordinatewise, which is precisely the structure the limit universal property forces once the underlying set is fixed as the product.

An equalizer of two homomorphisms $f, g\colon A \to B$ is the subgroup $\{a \in A \big| f(a) = g(a)\}$; its underlying set is $\{x \in UA \big| Uf(x) = Ug(x)\}$, the equalizer of Uf, Ug in **Set**, again because U preserves the equalizer. Taking $g = 0$ specializes this to the kernel, whose underlying set is $\{a \in UA \big| Uf(a) = 0\}$. Both computations are consequences of RAPL, not separate verifications.

64.4 Adjoint Functor Theorems

The RAPL theorem (theorem 64.3.3) makes limit-preservation a necessary condition for a functor $G\colon \mathbf{D} \to \mathbf{C}$ to be a right adjoint. The adjoint functor theorems address the converse: when a limit-preserving G is guaranteed to have a left adjoint. Preservation of limits alone is not enough, because a proper class of candidate arrows can obstruct the construction. The extra ingredient is a smallness hypothesis. The General Adjoint Functor Theorem asks for a set of arrows that jointly dominates every arrow out of a fixed object, the solution-set condition; the Special Adjoint Functor Theorem replaces that condition with a global structural hypothesis on $\mathbf{C}$. We prove the general theorem in full and record the special one with its key ideas.

The whole chapter turns on one reformulation, established in section 64.1: a left adjoint to G is the same data as a universal arrow $\eta_c\colon c \to Gd_c$ from each object c of $\mathbf{C}$ to G. A universal arrow from c to G (definition 63.1.4) is exactly an initial object of the comma category (c/G), whose objects

are pairs (d, f) with $f\colon c \to Gd$ and whose morphisms $(d, f) \to (d', f')$ are arrows $h\colon d \to d'$ in $\mathbf{D}$ with $Gh \circ f = f'$. Constructing a left adjoint therefore reduces to producing an initial object in each (c/G). The solution-set condition is precisely the smallness input that lets a completeness argument produce one.

Definition 64.4.1: Solution-Set Condition

Let $G\colon \mathbf{D} \to \mathbf{C}$ be a functor and c an object of $\mathbf{C}$. Then G satisfies the *solution-set condition* at c if there is a *set* of morphisms

$$\{\, f_i\colon c \to Gd_i \,\}_{i \in I}$$

such that every morphism $f\colon c \to Gd$ factors as $f = Gh \circ f_i$ for some index i and some morphism $h\colon d_i \to d$ in $\mathbf{D}$. The functor G *satisfies the solution-set condition* if it does so at every object c of $\mathbf{C}$.

In the language of the comma category, the condition says the objects (d_i, f_i) form a set that is *weakly initial* in (c/G): every object receives at least one morphism from a member of the set. The word "weakly" marks that the arrow witnessing the factorization is neither required to be unique nor to come from a single chosen source. The force of the definition is entirely its smallness. In a locally small $\mathbf{D}$ the objects (d, f) of (c/G) already form a proper class, and there is no reason a class-sized family should admit a set-sized dominating subfamily; the solution-set condition asserts that one exists. That is the gap the theorem fills between the necessary condition (RAPL) and sufficiency.

Example 64.4.2: The Solution Set for Free Groups

Let $G\colon \mathbf{Grp} \to \mathbf{Set}$ be the forgetful functor and c a set. A single arrow already works: take the free group Fc on c with its insertion of generators $\eta_c\colon c \to G(Fc)$, and let $\{f_i\}$ be the one-element family $\{\eta_c\}$. Every function $f\colon c \to G(H)$ into the underlying set of a group H extends uniquely to a homomorphism $\bar{f}\colon Fc \to H$ with $G(\bar{f}) \circ \eta_c = f$, so $f = G(\bar{f}) \circ \eta_c$ exhibits the required factorization. Here the solution set has one element because a genuine universal arrow already exists; the theorem below runs the implication in the other direction, manufacturing such a universal arrow from any solution set, however large.

The example makes the shape of the argument visible. When a left adjoint is present, the singleton solution set is the universal arrow itself. The content of the General Adjoint Functor Theorem is that a solution set of *any* size, together with completeness of $\mathbf{D}$ and preservation of limits by G, suffices to assemble a universal arrow that was not given in advance. The assembly is a completeness argument inside the comma category, and its engine is a lemma about initial objects, isolated first.

The lemma is where a set-sized weakly initial family is compressed to a single genuine initial object. In a complete category one can form the product of the family; the product receives an arrow to every object, so it is again weakly initial, and now it is a single object. Passing from weakly initial to initial then requires killing the ambiguity in those arrows, which is what an equalizer of endomorphisms does.

Lemma 64.4.3: Initial Object from a Weakly Initial Set

Let $\mathbf{A}$ be a complete, locally small category. Suppose $\mathbf{A}$ has a *weakly initial set*: a set $\{a_i\}_{i\in I}$ of objects such that every object of $\mathbf{A}$ admits at least one morphism from some a_i. Then $\mathbf{A}$ has an initial object.

***Proof*:**

Step 1: Form a weakly initial object. Since I is a set and $\mathbf{A}$ is complete, the product $P = \prod_{i\in I} a_i$ exists, with projections $\pi_i \colon P \to a_i$. Given any object a, weak initiality gives some i and a morphism $g \colon a_i \to a$; then $g \circ \pi_i \colon P \to a$ is a morphism from P to a. Thus P is a weakly initial *object*: every object receives at least one morphism from P.

Step 2: Equalize the endomorphisms of P. Local smallness makes $\mathbf{A}(P,P)$ a set, so the family of all endomorphisms of P is a set of parallel arrows $P \rightrightarrows P$. Completeness gives their equalizer

$$e \colon E \to P$$

the joint equalizer of $\{\, u \colon P \to P \,\}$, characterized by $u \circ e = e$ for every endomorphism u of P, and universal among arrows into P with this property. We claim E is initial.

Step 3: Existence of a morphism from E. For any object a, weak initiality of P gives a morphism $P \to a$, and precomposing with e yields a morphism $E \to a$. So E admits at least one morphism to every object.

Step 4: Uniqueness. Let $s, t \colon E \to a$ be two morphisms to a common object a; we must show $s = t$. Form the equalizer $k \colon K \to E$ of s and t, so $s \circ k = t \circ k$ and k is universal with this property. Since P is weakly initial there is a morphism $g \colon P \to K$, and composing produces an endomorphism

$$v = e \circ k \circ g \colon P \to P$$

Now e is the joint equalizer of all endomorphisms of P, and v is one such endomorphism, so $v \circ e = e$, that is $e \circ k \circ g \circ e = e$. The morphism e is a monomorphism, being an equalizer, so it is left-cancellable: from $e \circ (k \circ g \circ e) = e = e \circ \mathrm{id}_P$ we cancel e to get

$$k \circ (g \circ e) = \mathrm{id}_E$$

Thus k is a split epimorphism, with section $g \circ e$. But k is also a monomorphism, being an equalizer, and a split epimorphism that is monic is an isomorphism: composing $k \circ (g \circ e) = \mathrm{id}_E$ with k on the right gives $k \circ (g \circ e) \circ k = k = k \circ \mathrm{id}_K$, and cancelling the monic k on the left yields $(g \circ e) \circ k = \mathrm{id}_K$, so $g \circ e$ is a two-sided inverse of k. Since $s \circ k = t \circ k$ and k is an isomorphism, right-cancelling k gives $s = t$.

Combining Steps 3 and 4, every object of $\mathbf{A}$ admits exactly one morphism from E, so E is initial, completing the proof.

The lemma is the whole mechanism in miniature. The product collapses a set of objects into one weakly initial object; the equalizer of its endomorphisms then removes the freedom in the arrows out of it, leaving a single arrow to each target. The two hypotheses do disjoint work: completeness gives the product and the equalizers, local smallness guarantees that the endomorphisms of P form a set so that their equalizer exists. Drop either and the argument fails. With the lemma in hand the theorem is a matter of transporting it into the comma category (c/G), which is where the smallness

of the solution set becomes the weakly initial set the lemma requires.

The remaining input is that (c/G) inherits completeness from $\mathbf{D}$. This is exactly where the hypothesis that G preserves limits is spent: limits in (c/G) are computed in $\mathbf{D}$, and the cone over c that makes the limit an object of the comma category exists precisely because G carries the $\mathbf{D}$-limit to the corresponding $\mathbf{C}$-limit.

Theorem 64.4.4: General Adjoint Functor Theorem

Let $\mathbf{D}$ be a locally small, complete category and $G\colon \mathbf{D} \to \mathbf{C}$ a functor that preserves all small limits. Then G has a left adjoint if and only if G satisfies the solution-set condition (definition 64.4.1).

***Proof*:**

Necessity. Suppose G has a left adjoint $F \dashv G$, with unit η. For each object c of $\mathbf{C}$, the component $\eta_c\colon c \to G(Fc)$ is a universal arrow from c to G (theorem 64.1.5): every $f\colon c \to Gd$ factors as $f = Gh \circ \eta_c$ for a unique $h\colon Fc \to d$. The singleton family $\{\eta_c\}$ is then a solution set at c, so G satisfies the solution-set condition.

Sufficiency. Assume G preserves small limits and satisfies the solution-set condition. By theorem 64.1.5 it suffices to produce, for each object c of $\mathbf{C}$, a universal arrow from c to G, equivalently an initial object of the comma category (c/G) (definition 63.1.4). Fix c; we produce that initial object by applying lemma 64.4.3 to $\mathbf{A} = (c/G)$, which requires that (c/G) be locally small and complete and possess a weakly initial set.

Step 1: (c/G) is locally small. A morphism $(d, f) \to (d', f')$ in (c/G) is a morphism $h\colon d \to d'$ in $\mathbf{D}$ subject to the equation $Gh \circ f = f'$. Thus the hom-set of (c/G) is a subset of $\mathbf{D}(d, d')$, which is a set because $\mathbf{D}$ is locally small. So (c/G) is locally small.

Step 2: (c/G) is complete, using preservation of limits. Let $D\colon \mathbf{J} \to (c/G)$ be a small diagram, writing $D(j) = (d_j, f_j)$ with structure arrows $f_j\colon c \to Gd_j$; a morphism $j \to j'$ in $\mathbf{J}$ gives $\alpha_{jj'}\colon d_j \to d_{j'}$ with $G\alpha_{jj'} \circ f_j = f_{j'}$. The projection to $\mathbf{D}$ sends D to the diagram $j \mapsto d_j$, which has a limit $L = \lim_{\mathbf{J}} d_j$ in $\mathbf{D}$ by completeness, with limit cone $\lambda_j\colon L \to d_j$.

Because G preserves this limit, $G(L)$ with the cone $G\lambda_j\colon G(L) \to Gd_j$ is a limit of $j \mapsto Gd_j$ in $\mathbf{C}$. The arrows $f_j\colon c \to Gd_j$ form a cone over $j \mapsto Gd_j$ with apex c: for a morphism $j \to j'$ one has $G\alpha_{jj'} \circ f_j = f_{j'}$, which is exactly the compatibility condition for a cone. By the universal property of the limit $G(L)$, this cone factors through a unique morphism

$$f_L\colon c \to G(L)$$

satisfying $G\lambda_j \circ f_L = f_j$ for every j. The pair (L, f_L) is then an object of (c/G), and each $\lambda_j\colon L \to d_j$ satisfies $G\lambda_j \circ f_L = f_j$, so λ_j is a morphism $(L, f_L) \to (d_j, f_j)$ in (c/G); these assemble into a cone over D.

This cone is a limit cone in (c/G). Given any cone over D with apex (d, f), its legs are morphisms $\mu_j\colon (d, f) \to (d_j, f_j)$, hence morphisms $\mu_j\colon d \to d_j$ in $\mathbf{D}$ forming a cone over $j \mapsto d_j$; the limit L in $\mathbf{D}$ yields a unique $u\colon d \to L$ with $\lambda_j \circ u = \mu_j$. It remains to check u is a morphism $(d, f) \to (L, f_L)$, that is $Gu \circ f = f_L$. Both sides are morphisms $c \to G(L)$ into the limit $G(L)$; they agree after composing with each projection $G\lambda_j$, since $G\lambda_j \circ Gu \circ f = G(\lambda_j u) \circ f = G\mu_j \circ f = f_j$ and $G\lambda_j \circ f_L = f_j$. By the uniqueness clause of the limit $G(L)$, $Gu \circ f = f_L$. So u is the unique factorization in (c/G), and (L, f_L) is a limit of D. Hence (c/G) has all small limits: it is

complete.

Step 3: the solution set is a weakly initial set for (c/G). By hypothesis G satisfies the solution-set condition at c: there is a set $\{f_i \colon c \to Gd_i\}_{i\in I}$ such that every $f \colon c \to Gd$ factors as $f = Gh \circ f_i$ for some i and some $h \colon d_i \to d$. Read in (c/G), the objects $\{(d_i, f_i)\}_{i\in I}$ form a set, and the factorization $f = Gh \circ f_i$ says exactly that $h \colon (d_i, f_i) \to (d, f)$ is a morphism of (c/G). So every object (d, f) receives a morphism from some (d_i, f_i): the set $\{(d_i, f_i)\}$ is weakly initial.

Step 4: apply the lemma. By Steps 1-3 the comma category (c/G) is locally small, complete, and has a weakly initial set. Lemma 64.4.3 produces an initial object (d_c, η_c) of (c/G). An initial object of (c/G) is a universal arrow $\eta_c \colon c \to Gd_c$ from c to G (definition 63.1.4). This holds for every c, so by theorem 64.1.5 the assignment $c \mapsto d_c$ extends to a left adjoint $F \dashv G$, completing the proof.

The theorem isolates the two obstructions to being a right adjoint and names both. The soft obstruction is failure to preserve limits, ruled out by RAPL and assumed away here. The hard obstruction is size: a limit-preserving functor between well-behaved categories can still fail to have a left adjoint if the comma categories are too large to admit an initial object, and the solution-set condition is exactly the hypothesis that excludes this. When one has a candidate construction in hand, the theorem is often applied by exhibiting an explicit small solution set (frequently a single arrow, as in example 64.4.2) rather than by verifying an abstract smallness principle.

A recurring difficulty in practice is that verifying the solution-set condition can be as much work as constructing the adjoint by hand. The Special Adjoint Functor Theorem removes this burden under stronger global hypotheses on $\mathbf{C}$: a small cogenerating set does the work of every solution set at once. The cost is machinery, well-poweredness and cogenerators phrased through subobject lattices, that this book does not develop, so the theorem is stated with its key ideas rather than proved in full.

Theorem 64.4.5: Special Adjoint Functor Theorem

Let $\mathbf{D}$ be a locally small, complete, well-powered category with a small cogenerating set, and let $G \colon \mathbf{D} \to \mathbf{C}$ be a functor between locally small categories that preserves all small limits. Then G has a left adjoint.

***Proof Key ideas*:**
The full argument requires two notions this book does not develop: a category is *well-powered* when every object has only a set of subobjects (its subobjects form a set rather than a proper class), and a set $\{s_k\}$ of objects is *cogenerating* when any two distinct parallel morphisms $u \neq v \colon d \rightrightarrows d'$ are separated by some morphism $d' \to s_k$ that distinguishes them. These are hypotheses on the lattice of subobjects, whose systematic development belongs to a treatment of well-powered categories and their factorization systems; see Mac Lane, *Categories for the Working Mathematician*, Chapter V.8.

Granting them, the shape of the proof matches the general theorem, with the cogenerating set replacing the solution-set condition. Fix an object c of $\mathbf{C}$ and form, inside $\mathbf{D}$, the product $\prod_k s_k^{\mathbf{C}(c, Gs_k)}$ indexed by the cogenerating set and, for each factor, by the set of morphisms $c \to G(s_k)$. The candidate universal object is the smallest subobject of this product through which the canonical arrow from c factors; well-poweredness guarantees a smallest such subobject exists, since the subobjects form a set closed under the intersections that completeness provides, and the cogenerating property forces the resulting arrow to be universal. Preservation of limits

by G is used, as before, to place the construction in the comma category (c/G). The upshot is that a small cogenerating set functions as a uniform solution set: it gives, in one stroke, the smallness input that the general theorem requires separately at each object, completing the sketch.

The two theorems are the standard existence criteria for left adjoints, and their hypotheses trade off against each other. The general theorem requires little of the target categories but requires a solution set verified case by case; the special theorem front-loads strong structural hypotheses on $\mathbf{D}$, a small cogenerating set and well-poweredness, and then asks nothing further of the individual objects. Many categories of everyday interest, $\mathbf{Set}$, $\mathbf{Grp}$, $\mathbf{Ab}$, $\mathbf{Top}$, and $\mathbf{Mod}_R$, are complete and well-powered with a small cogenerating set, so the special theorem applies to limit-preserving functors out of them without any per-object verification.

A final application of the general theorem recurs across the series: producing a reflection onto a subcategory.

Example 64.4.6: A Reflective Subcategory via GAFT

Let $\mathbf{D}$ be a locally small, complete category and $\mathbf{C} \subseteq \mathbf{D}$ a full subcategory that is closed under small limits, meaning the inclusion $G\colon \mathbf{C} \hookrightarrow \mathbf{D}$ preserves and reflects small limits and every $\mathbf{D}$-limit of a diagram in $\mathbf{C}$ again lies in $\mathbf{C}$. Suppose in addition that $\mathbf{C}$ is complete and that G satisfies the solution-set condition: for each object d of $\mathbf{D}$ there is a set of morphisms $\{d \to c_i\}$ with c_i in $\mathbf{C}$ through which every morphism $d \to c$ into an object of $\mathbf{C}$ factors. Then theorem 64.4.4, applied to $G\colon \mathbf{C} \to \mathbf{D}$, produces a left adjoint $L \dashv G$: a *reflection* of $\mathbf{D}$ onto $\mathbf{C}$.

Concretely, take $\mathbf{D} = \mathbf{Grp}$ and $\mathbf{C} = \mathbf{Ab}$ the full subcategory of abelian groups, with $G\colon \mathbf{Ab} \hookrightarrow \mathbf{Grp}$ the inclusion. A limit of abelian groups computed in $\mathbf{Grp}$ is again abelian, so G preserves limits and $\mathbf{Ab}$ is closed under them; $\mathbf{Ab}$ is complete. For the solution-set condition at a group H, a single arrow suffices: the quotient map $q_H\colon H \to H^{\mathrm{ab}} = H/[H,H]$ onto the abelianization. Any homomorphism $H \to A$ into an abelian group A kills the commutator subgroup $[H,H]$, so it factors uniquely as $\bar{\varphi} \circ q_H$ with $\bar{\varphi}\colon H^{\mathrm{ab}} \to A$. The general theorem then returns the left adjoint $H \mapsto H^{\mathrm{ab}}$, recovering abelianization as the reflection of $\mathbf{Grp}$ onto $\mathbf{Ab}$. As with example 64.4.2, the singleton solution set is present because the universal arrow already exists; the value of the theorem is that a solution set of any size would have sufficed.

65

Monads and their Algebras

A monad is the algebraic structure an adjunction leaves on one side: from $F \dashv G$ the composite GF inherits a unit and a multiplication, and this structure alone suffices to rebuild a category of algebras. This chapter defines *monads*, constructs the two canonical adjunctions that realize any monad, the Eilenberg-Moore and Kleisli categories, and asks the converse, *monadicity*: when is a forgetful functor the forgetful functor of a monad? Beck's theorem answers it, and explains why the algebraic categories over **Set** are exactly the monadic ones.

65.1 Monads from Adjunctions

Every adjunction $F \dashv G$ leaves a trace on the category where its two functors meet: the composite GF is an endofunctor, the unit is a natural transformation $\mathrm{id} \Rightarrow GF$, and the counit gives a second natural transformation $GFGF \Rightarrow GF$. This section isolates that trace as a structure in its own right, the *monad*, defines it by the two laws it must obey, and shows that every adjunction produces one. The free-monoid, powerset, and error monads run alongside as the guiding examples.

Definition 65.1.1: Monad

A *monad* on a category C is an endofunctor $T\colon C \to C$ together with two natural transformations, the *unit*

$$\eta\colon \mathrm{id}_C \Rightarrow T$$

and the *multiplication*

$$\mu\colon T^2 \Rightarrow T$$


where T^2 denotes the composite TT, subject to two laws. The *associativity law* is the equality of natural transformations $T^3 \Rightarrow T$

$$\mu \circ T\mu = \mu \circ \mu T \tag{65.1}$$


and the *unit laws* are the equalities of natural transformations $T \Rightarrow T$

$$\mu \circ T\eta = \mathrm{id}_T = \mu \circ \eta T \tag{65.2}$$

Here $T\mu$ and μT are the whiskered composites: $T\mu$ has component $T(\mu_c)\colon T^3c \to T^2c$ at c, and μT has component $\mu_{Tc}\colon T^3c \to T^2c$; similarly $T\eta$ and ηT have components $T(\eta_c)$ and η_{Tc}. The two laws are the commutativity of the associativity square



and the two unit triangles



The pattern is that of a monoid: μ plays the role of a multiplication and η the role of a unit element, with (65.1) the associativity of the multiplication and (65.2) its two-sided unit law. The slogan is that a monad is a monoid in the category of endofunctors of C under composition, with the functor category $[C, C]$ (definition 61.5.4) giving the ambient category and functor composition giving the tensor product. The definition is the monoid axioms transported into that setting, with vertical composition of natural transformations for equality of maps and horizontal composition (whiskering) for the two ways of associating T^3.

The endofunctor alone carries no content; the unit and multiplication are what make a monad an algebraic object. Before the examples, the source of every such structure is an adjunction.

The chapter opening framed a monad as the structure an adjunction leaves on one side. That statement is now a proposition: the composite GF of an adjunction, equipped with the adjunction unit and the multiplication built from the counit, satisfies definition 65.1.1. The verification is a diagram chase in which every square commutes by naturality of the counit or by a triangle identity.

Proposition 65.1.2: The Monad of an Adjunction

Let $F\colon C \to D$ and $G\colon D \to C$ be functors with $F \dashv G$, unit $\eta\colon \mathrm{id}_C \Rightarrow GF$ and counit $\varepsilon\colon FG \Rightarrow \mathrm{id}_D$ (definition 64.1.1, definition 64.1.3). Then

$$T = GF\colon C \to C, \qquad \eta\colon \mathrm{id}_C \Rightarrow T, \qquad \mu = G\varepsilon F\colon T^2 \Rightarrow T$$

is a monad on C, where μ is the whiskered natural transformation with component $\mu_c = G\varepsilon_{Fc}\colon GFGFc \to GFc$ at c.

***Proof*:**
The unit of the monad is the adjunction unit, already a natural transformation $\mathrm{id}_C \Rightarrow GF = T$ (definition 64.1.3). The multiplication $\mu = G\varepsilon F$ is the whiskering of the natural transformation $\varepsilon\colon FG \Rightarrow \mathrm{id}_D$ by G on the left and F on the right, hence a natural transformation $GFGF \Rightarrow GF$, that is, $T^2 \Rightarrow T$. It remains to check the associativity law and the two unit laws.

Step 1: Associativity. Both $\mu \circ T\mu$ and $\mu \circ \mu T$ are natural transformations $T^3 = GFGFGF \Rightarrow GF = T$; the claim is that their components agree at every c. Writing out the components,

$$(\mu \circ T\mu)_c = G\varepsilon_{Fc} \circ GF(G\varepsilon_{Fc}) = G\varepsilon_{Fc} \circ GFG\varepsilon_{Fc}$$

and

$$(\mu \circ \mu T)_c = G\varepsilon_{Fc} \circ G\varepsilon_{FGFc}$$

Applying the functor G to the naturality square of ε reduces both to a common expression. Naturality of $\varepsilon\colon FG \Rightarrow \mathrm{id}_D$ at the morphism $\varepsilon_{Fc}\colon FGFc \to Fc$ in D gives the commuting square

$$\begin{array}{ccc} FGFGFc & \xrightarrow{\varepsilon_{FGFc}} & FGFc \\ {\scriptstyle FG\varepsilon_{Fc}}\downarrow & & \downarrow{\scriptstyle \varepsilon_{Fc}} \\ FGFc & \xrightarrow[\varepsilon_{Fc}]{} & Fc \end{array}$$

that is, $\varepsilon_{Fc} \circ FG\varepsilon_{Fc} = \varepsilon_{Fc} \circ \varepsilon_{FGFc}$ in D. Applying G to this equation yields $G\varepsilon_{Fc} \circ GFG\varepsilon_{Fc} = G\varepsilon_{Fc} \circ G\varepsilon_{FGFc}$, which is precisely $(\mu \circ T\mu)_c = (\mu \circ \mu T)_c$. As c was arbitrary, (65.1) holds. Associativity of the monad is thus the naturality of the counit, pushed through G.

Step 2: The unit laws. The component of $\mu \circ T\eta$ at c is

$$(\mu \circ T\eta)_c = G\varepsilon_{Fc} \circ GF(\eta_c) = G\varepsilon_{Fc} \circ GF\eta_c = G(\varepsilon_{Fc} \circ F\eta_c)$$

using that G is a functor. By the second triangle identity (theorem 64.1.5), $\varepsilon_{Fc} \circ F\eta_c = \mathrm{id}_{Fc}$, so the component is $G(\mathrm{id}_{Fc}) = \mathrm{id}_{GFc} = (\mathrm{id}_T)_c$. Hence $\mu \circ T\eta = \mathrm{id}_T$. For the other unit law, the component of $\mu \circ \eta T$ at c is

$$(\mu \circ \eta T)_c = G\varepsilon_{Fc} \circ \eta_{GFc}$$

the composite $GFc \to GFGFc \to GFc$. This is exactly the first triangle identity (theorem 64.1.5) evaluated at the object Fc of D, namely $G\varepsilon_d \circ \eta_{Gd} = \mathrm{id}_{Gd}$ with $d = Fc$, giving $G\varepsilon_{Fc} \circ \eta_{GFc} = \mathrm{id}_{GFc}$. Hence $\mu \circ \eta T = \mathrm{id}_T$, and both equalities in (65.2) hold, completing the proof.

The proof shows the two monad laws are repackaged adjunction data: associativity is the naturality

of the counit, and each unit law is one of the two triangle identities. This is the origin of every monad met in practice. A monad is not usually written down axiomatically and then studied; it arises as GF for a free-forgetful adjunction, and its multiplication is the counit describing how a free object built on a free object collapses. The examples show this, and each recovers a familiar operation.

Example 65.1.3: The Free-Monoid, Powerset, and Error Monads
Three monads on **Set**, each the monad of a free-forgetful adjunction (proposition 65.1.2) or checked directly against definition 65.1.1.

1. *The free-monoid monad.* Let TX be the set of finite words $(x_1, \dots, x_n)$, $n \geq 0$, in the alphabet X, including the empty word; for $f\colon X \to Y$, Tf applies f letterwise. This is GF for the free-monoid adjunction $F \dashv G$ with $G\colon \mathbf{Mon} \to \mathbf{Set}$ the underlying-set functor and F the free-monoid functor ([21]). The unit $\eta_X\colon X \to TX$ sends x to the length-one word (x). The multiplication $\mu_X\colon T^2X \to TX$ takes a word of words and concatenates: a length-one word of words $\big((x_1, \dots, x_k)\big)$ flattens to $(x_1, \dots, x_k)$, and in general

$$\mu_X\big((w_1, \dots, w_m)\big) = w_1 \cdot w_2 \cdots w_m$$

   the concatenation of the constituent words $w_i \in TX$. Associativity (65.1) is the associativity of concatenation: flattening a triple-nested word by first concatenating the inner groupings or first concatenating the outer groupings gives the same word. The unit laws (65.2) say that turning each letter into a length-one word and then flattening, or wrapping a whole word into a length-one word of words and then flattening, both return the original word.

2. *The powerset monad.* Let $T = P$ be the covariant powerset functor: PX is the set of subsets of X, and $Pf(S) = f(S)$ is the image of $S \subseteq X$ under $f\colon X \to Y$. The unit $\eta_X\colon X \to PX$ is the singleton map $x \mapsto \{x\}$. The multiplication $\mu_X\colon P^2X \to PX$ is the union: for a set $\mathcal{S}$ of subsets of X,

$$\mu_X(\mathcal{S}) = \bigcup_{S \in \mathcal{S}} S$$

   Associativity is the equality of the two ways to flatten a set of sets of sets by union, which both give the union of all the innermost members. The unit laws read $\bigcup_{x \in S}\{x\} = S$ (union of the singletons of the elements of S) and $\bigcup\{S\} = S$ (union of the one-element family $\{S\}$). This is the monad of the adjunction between **Set** and the category of complete sup-lattices, whose algebras are taken up in the next section.

3. *The error monad.* Fix a one-point set $\{*\}$ and let $TX = X \sqcup \{*\}$, the disjoint union adjoining a single point $*$ read as an error value; for $f\colon X \to Y$, Tf acts as f on X and fixes $*$. The unit $\eta_X\colon X \to X \sqcup \{*\}$ is the inclusion of X. The multiplication $\mu_X\colon T^2X \to TX$, where $T^2X = X \sqcup \{*_1\} \sqcup \{*_2\}$ carries two error points ($*_1$ from the inner T, $*_2$ from the outer), acts as the identity on X and sends both $*_1$ and $*_2$ to the single $*$, merging the two error points. Associativity holds because on the X-part every map in sight is the identity and on the error part every composite lands on $*$; the unit laws hold because η adjoins an error point that μ immediately absorbs. This is the monad GF for the free-pointed-set adjunction, F adjoining a basepoint and G forgetting it.

The three examples share a shape: TX is a syntax of "X-terms" (words, subsets, values-or-error), the unit embeds each element as a trivial term, and the multiplication evaluates a term of terms

into a single term. A monad is thus a theory of substitution, with μ the operation that carries out one round of it, and the two laws are exactly what make repeated substitution unambiguous. This reading anticipates the theory of algebras for a monad, developed in the next section, where an algebra gives the missing evaluation of a term into an actual element.

Reversing every arrow in definition 65.1.1 produces the dual notion, obtained by applying the definition in the opposite category. A comonad packages the trace an adjunction casts on the *other* side, the composite FG with counit and comultiplication, and is the structure whose coalgebras encode "co-substitution" in the same way a monad's algebras encode substitution.

Definition 65.1.4: Comonad

A *comonad* on a category C is a monad on C^{op}: an endofunctor $T\colon C \to C$ with a *counit* $\varepsilon\colon T \Rightarrow \mathrm{id}_C$ and a *comultiplication* $\delta\colon T \Rightarrow T^2$ satisfying the coassociativity law $T\delta \circ \delta = \delta T \circ \delta$ and the counit laws $\varepsilon T \circ \delta = \mathrm{id}_T = T\varepsilon \circ \delta$, the diagrams of definition 65.1.1 with every arrow reversed. Dually to proposition 65.1.2, an adjunction $F \dashv G$ induces a comonad FG on D with counit ε and comultiplication $F\eta G$ (box 61.3.3).

Everything proved for monads holds for comonads by the duality principle, with the roles of unit and multiplication interchanged and arrows reversed. The comonad and its coalgebras are the opposite-category translation of the monad theory developed here and in the sections that follow, and are not pursued further.


65.2 Algebras for a Monad

Proposition 65.1.2 produced a monad from every adjunction. This section runs the construction the other way. Given a monad (T, η, μ) on $\mathbf{C}$ (definition 65.1.1), an *algebra* for it is an object equipped with an action of T compatible with η and μ; the algebras assemble into a category, the Eilenberg-Moore category $\mathbf{C}^T$, and the free-algebra construction gives an adjunction whose induced monad is the original T. A monad thus records an algebraic theory, and $\mathbf{C}^T$ is its category of models.

The definition is the categorical distillation of what it means to be an algebra for an operation. If T is the free-monoid endofunctor on $\mathbf{Set}$, then TA is the set of finite words in A; an action $a\colon TA \to A$ that respects the unit and multiplication is precisely a rule multiplying words, that is, a monoid structure. The two laws below are exactly associativity and unitality of that multiplication, transcribed into the language of T.


Definition 65.2.1: Algebra for a Monad

Let (T, η, μ) be a monad on a category $\mathbf{C}$. A *T-algebra* is a pair (A, a) consisting of an object A of $\mathbf{C}$ and a morphism $a\colon TA \to A$, called the *structure map*, making the two diagrams



commute, that is, $a \circ \eta_A = \mathrm{id}_A$ (the *unit law*) and $a \circ \mu_A = a \circ Ta$ (the *associativity law*).

A *morphism of T-algebras* $(A, a) \to (B, b)$ is a morphism $f\colon A \to B$ in $\mathbf{C}$ commuting with the structure maps, that is, making



commute: $f \circ a = b \circ Tf$.

The unit law forces the structure map to restore an element inserted by η_A without altering it: the free elements act as they must. The associativity law compares the two ways of collapsing a doubly-applied T down to A (first collapse the outer layer with μ_A, then act by a; or first act by a inside the outer T, then act again) and requires they agree. For the free-monoid monad these are the associativity and unit axioms of a monoid, as the next passage makes precise; the definition abstracts that pattern away from any one theory.

Example 65.2.2: The Trivial Algebra and the Free Algebra

Two algebras exist for every monad. First, (TA, μ_A) is a T-algebra for each object A: the unit law $\mu_A \circ \eta_{TA} = \mathrm{id}_{TA}$ is one of the monad unit laws, and the associativity law $\mu_A \circ \mu_{TA} = \mu_A \circ T\mu_A$ is the monad associativity law (definition 65.1.1). This is the *free T-algebra* on A. Second, for any algebra (A, a) the associativity law read as a commuting square makes the structure map $a\colon (TA, \mu_A) \to (A, a)$ itself a morphism of T-algebras.

The algebras and their morphisms form a category, and the underlying-object assignment forgets back to $\mathbf{C}$.

Definition 65.2.3: Eilenberg-Moore Category

Let (T, η, μ) be a monad on $\mathbf{C}$. The *Eilenberg-Moore category* $\mathbf{C}^T$ has T-algebras as objects and morphisms of T-algebras as arrows, with composition and identities computed in $\mathbf{C}$. The *forgetful functor*

$$U^T \colon \mathbf{C}^T \to \mathbf{C}, \qquad (A, a) \mapsto A, \qquad (f \colon (A, a) \to (B, b)) \mapsto (f \colon A \to B)$$

sends an algebra to its underlying object and an algebra morphism to its underlying morphism.

Composition is well-defined because a composite of algebra morphisms is again one: stacking the two commuting squares of definition 65.2.1 for $f \colon (A, a) \to (B, b)$ and $g \colon (B, b) \to (C, c)$ gives the square for gf, using $T(gf) = Tg \circ Tf$. The identity of $\mathbf{C}$ on A is an algebra endomorphism of (A, a). So $\mathbf{C}^T$ is a genuine category and U^T a functor; the content lies not in these formalities but in what U^T admits as a partner. The free-algebra assignment $A \mapsto (TA, \mu_A)$ of example 65.2.2 is the object part of its left adjoint.

The motivation for the adjunction is the recovery program. Proposition 65.1.2 showed an adjunction breeds a monad; the reverse question is whether every monad comes from an adjunction, and if so from which one. The Eilenberg-Moore construction answers yes and produces a canonical such adjunction, built entirely out of T itself.

Theorem 65.2.4: The Eilenberg-Moore Adjunction

Let (T, η, μ) be a monad on $\mathbf{C}$. The assignment

$$F^T \colon \mathbf{C} \to \mathbf{C}^T, \qquad c \mapsto (Tc, \mu_c), \qquad (g \colon c \to c') \mapsto (Tg \colon (Tc, \mu_c) \to (Tc', \mu_{c'}))$$

is a functor, the *free T-algebra functor*, and it is left adjoint to the forgetful functor U^T. The adjunction $F^T \dashv U^T$ induces (via proposition 65.1.2) the original monad (T, η, μ).

***Proof*:**

Step 1: F^T is a functor. On objects $F^T c = (Tc, \mu_c)$ is a T-algebra by example 65.2.2. On a morphism $g \colon c \to c'$, the arrow $Tg \colon Tc \to Tc'$ is an algebra morphism $(Tc, \mu_c) \to (Tc', \mu_{c'})$: the required square $Tg \circ \mu_c = \mu_{c'} \circ T(Tg)$ is naturality of $\mu \colon T^2 \Rightarrow T$ applied to g. Functoriality of F^T then follows from functoriality of T, since F^T acts as T on morphisms.

Step 2: The transposition bijection. Fix an object c of $\mathbf{C}$ and a T-algebra (A, a). Define

$$\Phi \colon \mathrm{Hom}_{\mathbf{C}^T}\big((Tc, \mu_c), (A, a)\big) \longrightarrow \mathrm{Hom}_{\mathbf{C}}(c, A), \qquad \Phi(f) = f \circ \eta_c$$

which precomposes an algebra map out of the free algebra with the unit component $\eta_c \colon c \to Tc$; this is a morphism of $\mathbf{C}$ because $U^T f = f$ and η_c live there. In the other direction define

$$\Psi \colon \mathrm{Hom}_{\mathbf{C}}(c, A) \longrightarrow \mathrm{Hom}_{\mathbf{C}^T}\big((Tc, \mu_c), (A, a)\big), \qquad \Psi(g) = a \circ Tg$$

Two claims must be checked: that $\Psi(g)$ is an algebra morphism, and that Φ and Ψ are mutually inverse.

Step 3: $\Psi(g)$ is an algebra morphism. Write $h = a \circ Tg \colon Tc \to A$. The algebra-morphism square

for $h\colon (Tc, \mu_c) \to (A, a)$ requires $h \circ \mu_c = a \circ Th$. Compute the right-hand side:

$$a \circ Th = a \circ T(a \circ Tg) = a \circ Ta \circ T^2 g$$

Apply the associativity law $a \circ Ta = a \circ \mu_A$ of (A, a):

$$a \circ Ta \circ T^2 g = a \circ \mu_A \circ T^2 g$$

Naturality of $\mu\colon T^2 \Rightarrow T$ applied to g gives $\mu_A \circ T^2 g = Tg \circ \mu_c$, so

$$a \circ \mu_A \circ T^2 g = a \circ Tg \circ \mu_c = h \circ \mu_c$$

which is the identity required. Hence $\Psi(g)$ is a morphism $(Tc, \mu_c) \to (A, a)$ of T-algebras.

Step 4: Φ and Ψ are inverse. For $g\colon c \to A$,

$$\Phi(\Psi(g)) = (a \circ Tg) \circ \eta_c = a \circ Tg \circ \eta_c = a \circ \eta_A \circ g = g$$

where the third equality is naturality of $\eta\colon \mathrm{id}_{\mathbf{C}} \Rightarrow T$ applied to g (namely $Tg \circ \eta_c = \eta_A \circ g$) and the fourth is the unit law $a \circ \eta_A = \mathrm{id}_A$ of (A, a). Conversely, for an algebra morphism $f\colon (Tc, \mu_c) \to (A, a)$,

$$\Psi(\Phi(f)) = a \circ T(f \circ \eta_c) = a \circ Tf \circ T\eta_c$$

Because f is an algebra morphism, $a \circ Tf = f \circ \mu_c$, so

$$a \circ Tf \circ T\eta_c = f \circ \mu_c \circ T\eta_c = f \circ \mathrm{id}_{Tc} = f$$

the middle step using the monad unit law $\mu_c \circ T\eta_c = \mathrm{id}_{Tc}$ (definition 65.1.1). Thus Φ and Ψ are mutually inverse bijections.

Step 5: Naturality. The bijection must be natural in c and in (A, a), so that it is an adjunction (definition 64.1.1). For naturality in the algebra variable, let $\varphi\colon (A, a) \to (B, b)$ be an algebra morphism. Postcomposition by φ acts on the left-hand hom-set (in $\mathbf{C}^T$) and by $U^T\varphi = \varphi$ on the right (in $\mathbf{C}$); for $f\colon (Tc, \mu_c) \to (A, a)$,

$$\Phi(\varphi \circ f) = \varphi \circ f \circ \eta_c = \varphi \circ \Phi(f)$$

which is the naturality square for the target variable. For naturality in c, let $k\colon c' \to c$ be a morphism of $\mathbf{C}$. Precomposition acts by k on the right-hand hom-set and by $F^T k = Tk$ on the left; for $f\colon (Tc, \mu_c) \to (A, a)$,

$$\Phi(f \circ Tk) = f \circ Tk \circ \eta_{c'} = f \circ \eta_c \circ k = \Phi(f) \circ k$$

using naturality of η applied to k (namely $Tk \circ \eta_{c'} = \eta_c \circ k$). Both squares commute, so Φ is a natural isomorphism and $F^T \dashv U^T$.

Step 6: The induced monad is T. By proposition 65.1.2, the monad induced by $F^T \dashv U^T$ has endofunctor $U^T F^T$, unit the adjunction unit, and multiplication $U^T \varepsilon^T F^T$, where ε^T is the counit of $F^T \dashv U^T$. On objects, $U^T F^T c = U^T(Tc, \mu_c) = Tc$, and on morphisms $U^T F^T g = Tg$, so $U^T F^T = T$ as endofunctors. The adjunction unit is the transpose of the identity on $F^T c = (Tc, \mu_c)$, which by Step 2 is $\Phi(\mathrm{id}) = \mathrm{id}_{Tc} \circ \eta_c = \eta_c$; the induced unit is η. The counit component at (A, a) is the transpose of id_A under $F^T \dashv U^T$, that is $\varepsilon^T_{(A,a)} = \Psi(\mathrm{id}_A) = a \circ T\mathrm{id}_A = a$, the structure map itself. Hence the induced multiplication at c is $U^T \varepsilon^T_{F^T c} = \varepsilon^T_{(Tc, \mu_c)} = \mu_c$. Endofunctor, unit, and multiplication all agree with (T, η, μ), completing the proof.

The counit computation in Step 6 isolates a useful fact: the counit of $F^T \dashv U^T$ at an algebra (A, a) is its own structure map a, viewed as the algebra morphism $(TA, \mu_A) \to (A, a)$. This recovers the second observation of example 65.2.2 as the counit of the adjunction, and it says that every algebra is a canonical quotient of a free one, namely the free algebra on its underlying object, acted on by a. The theorem thus does two things at once: it realizes an arbitrary monad by an adjunction, closing the loop opened in section 65.1, and it does so through a category $\mathbf{C}^T$ assembled purely from T, with no auxiliary data.

The examples make the slogan "a monad is an algebraic theory, and $\mathbf{C}^T$ is its category of models" concrete. Each monad from example 65.1.3 has an Eilenberg-Moore category that is, up to equivalence, a familiar category of structured sets.

Example 65.2.5: Eilenberg-Moore Categories of Standard Monads

1. *The free-monoid monad.* Let T be the free-monoid monad on **Set**, so TA is the set of finite words $(a_1, \dots, a_n)$ in A, with $\eta_A(a) = (a)$ the length-one word and μ_A concatenating a word of words. A T-algebra (A, a) has a structure map $a \colon TA \to A$ assigning an element to each word. Write $a_1 \cdots a_n$ for $a(a_1, \dots, a_n)$. The unit law $a \circ \eta_A = \mathrm{id}_A$ says $a(a) = a$: single letters are unchanged. The associativity law $a \circ \mu_A = a \circ Ta$ says that evaluating a word of words either by first concatenating (via μ_A) or by first evaluating each inner word (via Ta) gives the same answer; taking the empty outer word gives a distinguished element $e = a()$ and taking a two-word split gives $(a_1 \cdots a_i)(a_{i+1} \cdots a_n) = a_1 \cdots a_n$. These are exactly the associativity and unit axioms of a monoid with unit e and product $xy = a(x, y)$. A morphism of T-algebras is a map preserving the product and unit, that is, a monoid homomorphism ([21]). Hence $\mathbf{Set}^T$ is equivalent to **Mon**, the category of monoids.

2. *The powerset monad.* Let $T = P$ be the covariant powerset monad on **Set**, with $\eta_A(a) = \{a\}$ and μ_A taking a union of a set of subsets. A P-algebra is a map $a \colon PA \to A$ sending each subset $S \subseteq A$ to an element $\bigvee S := a(S)$. The unit law $a(\{x\}) = x$ pins the singletons. Setting $x \leq y$ iff $\bigvee\{x, y\} = y$ defines a partial order on A, and the associativity law $a \circ \mu_A = a \circ Pa$ forces $a(S)$ to be the least upper bound of S for every subset S, including the empty set (whose supremum is the bottom element $a(\varnothing)$). An algebra structure on A is thus a rule assigning a supremum to *every* subset, which is exactly a complete sup-lattice; a P-algebra morphism is a map preserving arbitrary suprema. So $\mathbf{Set}^P$ is the category of complete sup-lattices and sup-preserving maps.

3. *The maybe monad.* For the maybe monad $MA = A \sqcup \{*\}$ (example 65.1.3), an M-algebra $a \colon A \sqcup \{*\} \to A$ is determined by its value $a(*)$ together with the unit law fixing A; the associativity law imposes nothing further, so an M-algebra is a set with a chosen basepoint $a(*)$, and $\mathbf{Set}^M$ is the category of pointed sets.

In each case the structure map is the operation of the theory: word-multiplication for monoids, supremum for sup-lattices, basepoint choice for pointed sets. This is the sense in which a monad on **Set** encodes an algebraic theory whose operations are "T-many arguments in, one out", and $\mathbf{C}^T$ is its category of models with the theory-preserving maps. The converse question, which categories over **Set** arise this way, is the subject of the monadicity theorem later in the chapter.

One interpretive point closes the section. Theorem 65.2.4 realizes a given monad by an adjunction, but it is not the only such realization: $\mathbf{C}^T$ is the *terminal* one. Among all adjunctions $F \dashv U$ inducing the given monad, the Eilenberg-Moore adjunction receives a unique comparison functor from every

other, making it the largest category of T-algebras compatible with the monad. The next section constructs the initial realization, the Kleisli category, together with the comparison functor between them; the two together bound every adjunction that induces T.

65.3 The Kleisli Category

Where the Eilenberg-Moore category $\mathbf{C}^T$ (section 65.2) realizes T from *every* T-algebra, this section builds the opposite extreme from the smallest possible family, the free ones. The construction packages the free algebras into a category $\mathbf{C}_T$ using only η and μ, exhibits it as a second adjunction that induces T, and locates it against $\mathbf{C}^T$: $\mathbf{C}_T$ is initial and $\mathbf{C}^T$ terminal among all adjunctions inducing T.

The idea is to read a morphism $c \to Tc'$ not as a map landing in Tc' but as a map from c to c' that carries a T-shaped effect: a function returning a formal word, a subset, or a possibly-undefined value rather than a single element. Composing two such effectful maps requires flattening the doubled effect, and μ is exactly the flattening.

Definition 65.3.1: Kleisli Category

Let (T, η, μ) be a monad on a category $\mathbf{C}$ (definition 65.1.1). The *Kleisli category* $\mathbf{C}_T$ has the same objects as $\mathbf{C}$. A morphism $c \to c'$ in $\mathbf{C}_T$ is a $\mathbf{C}$-morphism $f\colon c \to Tc'$, called a *Kleisli arrow*. The identity on c is the unit component

$$\eta_c\colon c \to Tc$$

and the composite of $f\colon c \to Tc'$ with $g\colon c' \to Tc''$ (in that order, g after f) is the Kleisli arrow

$$g \odot f \;=\; \mu_{c''} \circ Tg \circ f \;:\; c \to Tc'' \tag{65.3}$$

where $\odot$ denotes composition in $\mathbf{C}_T$ to distinguish it from composition $\circ$ in $\mathbf{C}$.

The formula (65.3) reads left to right through the effect: apply f to reach Tc', apply Tg to push each intermediate value through g and land in TTc'', then apply $\mu_{c''}$ to collapse the doubled effect down to Tc''. That $\mathbf{C}_T$ is a category is not automatic; it is exactly the monad laws in disguise, and the verification shows why associativity and unitality of μ and η are the right axioms to impose.

Proposition 65.3.2: The Kleisli Category is a Category

With the composition and identities of definition 65.3.1, $\mathbf{C}_T$ is a category.

***Proof*:**
Write $\odot$ for Kleisli composition and $\circ$ for composition in $\mathbf{C}$; naturality of η and μ and the monad laws (definition 65.1.1) are used throughout.

Step 1: Left unit. Let $f\colon c \to Tc'$ be a Kleisli arrow, so its target identity is $\eta_{c'}\colon c' \to Tc'$. Then

$$\eta_{c'} \odot f = \mu_{c'} \circ T\eta_{c'} \circ f = (\mu_{c'} \circ T\eta_{c'}) \circ f = \mathrm{id}_{Tc'} \circ f = f$$

using the right unit law $\mu \circ T\eta = \mathrm{id}_T$ of the monad.

Step 2: Right unit. With $\eta_c \colon c \to Tc$ the identity on the source,

$$f \odot \eta_c = \mu_{c'} \circ Tf \circ \eta_c$$

Naturality of $\eta \colon \mathrm{id}_{\mathbf{C}} \Rightarrow T$ applied to $f \colon c \to Tc'$ gives $Tf \circ \eta_c = \eta_{Tc'} \circ f$, so

$$f \odot \eta_c = \mu_{c'} \circ \eta_{Tc'} \circ f = (\mu_{c'} \circ \eta_{Tc'}) \circ f = \mathrm{id}_{Tc'} \circ f = f$$

now using the left unit law $\mu \circ \eta T = \mathrm{id}_T$.

Step 3: Associativity. Let $f \colon c \to Tc'$, $g \colon c' \to Tc''$, and $h \colon c'' \to Tc'''$. Expanding the two bracketings,

$$h \odot (g \odot f) = \mu_{c'''} \circ Th \circ (\mu_{c''} \circ Tg \circ f) \tag{65.4}$$

$$(h \odot g) \odot f = \mu_{c'''} \circ T(\mu_{c'''} \circ Th \circ g) \circ f \tag{65.5}$$

In (65.5), functoriality of T splits $T(h \odot g) = T\mu_{c'''} \circ TTh \circ Tg$, so the right side becomes $\mu_{c'''} \circ T\mu_{c'''} \circ TTh \circ Tg \circ f$. In (65.4), naturality of $\mu \colon TT \Rightarrow T$ applied to $h \colon c'' \to Tc'''$ gives $Th \circ \mu_{c''} = \mu_{Tc'''} \circ TTh$, so the left side becomes $\mu_{c'''} \circ \mu_{Tc'''} \circ TTh \circ Tg \circ f$. The two agree once $\mu_{c'''} \circ T\mu_{c'''} = \mu_{c'''} \circ \mu_{Tc'''}$, which is precisely the associativity law $\mu \circ T\mu = \mu \circ \mu T$ of the monad, evaluated at c'''. Hence (65.4) and (65.5) coincide, and Kleisli composition is associative, completing the proof.

The proof is the monad laws read backward: the two unit laws become the two identity axioms, and the single associativity square becomes associativity of composition. A monad is thus exactly the data needed to make Kleisli arrows compose, which is one sense in which a monad is an "algebraic theory" presented by its effects. A concrete instance makes the effects visible.

Example 65.3.3: The Kleisli Category of the Powerset Monad

Let $P \colon \mathbf{Set} \to \mathbf{Set}$ be the covariant powerset monad (example 65.1.3), with unit $\eta_X \colon X \to PX$ sending x to the singleton $\{x\}$ and multiplication $\mu_X \colon PPX \to PX$ sending a set of subsets to its union. A Kleisli arrow $f \colon X \to PY$ is a function assigning to each $x \in X$ a subset $f(x) \subseteq Y$, that is, a *relation* between X and Y. The Kleisli identity η_X is the diagonal relation $x \mapsto \{x\}$. Given $f \colon X \to PY$ and $g \colon Y \to PZ$, the Kleisli composite is

$$(g \odot f)(x) = \mu_Z\big((Pg)(f(x))\big) = \bigcup_{y \in f(x)} g(y)$$

which is exactly the composite relation: x is related to z if and only if some y has $x\ f\ y$ and $y\ g\ z$. Thus $\mathbf{Set}_P$ is the category $\mathbf{Rel}$ of sets and relations, with relational composition read off the monad structure. The maybe monad $X \mapsto X + 1$ (add a disjoint basepoint) gives instead the category of partial functions, and the free-monoid monad gives functions returning formal words.

Every Kleisli category comes with a canonical adjunction, and it induces the monad one started from. The left adjoint reinterprets an ordinary map as a pure Kleisli arrow, one with trivial effect, and the right adjoint sends an object to the free algebra Tc.

Theorem 65.3.4: The Kleisli Adjunction

Let (T, η, μ) be a monad on $\mathbf{C}$ with Kleisli category $\mathbf{C}_T$. Define functors

$$F_T \colon \mathbf{C} \to \mathbf{C}_T, \qquad U_T \colon \mathbf{C}_T \to \mathbf{C}$$

as follows. The functor F_T is the identity on objects, and sends $f \colon c \to c'$ in $\mathbf{C}$ to the Kleisli arrow $\eta_{c'} \circ f \colon c \to Tc'$. The functor U_T sends an object c to Tc, and a Kleisli arrow $f \colon c \to Tc'$ to the $\mathbf{C}$-morphism $\mu_{c'} \circ Tf \colon Tc \to Tc'$. Then $F_T \dashv U_T$, and the monad induced by this adjunction (proposition 65.1.2) is (T, η, μ).

***Proof*:**

Step 1: F_T and U_T are functors. For F_T: the identity on c in $\mathbf{C}$ goes to $\eta_c \circ \mathrm{id}_c = \eta_c$, the Kleisli identity. For composability, given $f \colon c \to c'$ and $g \colon c' \to c''$ in $\mathbf{C}$, the Kleisli composite of their images is

$$(\eta_{c''} \circ g) \odot (\eta_{c'} \circ f) = \mu_{c''} \circ T(\eta_{c''} \circ g) \circ \eta_{c'} \circ f$$

Naturality of $\eta \colon \mathrm{id}_{\mathbf{C}} \Rightarrow T$ at the morphism $\eta_{c''} \circ g \colon c' \to Tc''$ gives $T(\eta_{c''} \circ g) \circ \eta_{c'} = \eta_{Tc''} \circ \eta_{c''} \circ g$, whence

$$(\eta_{c''} \circ g) \odot (\eta_{c'} \circ f) = \mu_{c''} \circ \eta_{Tc''} \circ \eta_{c''} \circ g \circ f = \eta_{c''} \circ (g \circ f)$$

using $\mu_{c''} \circ \eta_{Tc''} = \mathrm{id}_{Tc''}$ (left unit law). This is $F_T(g \circ f)$, so F_T is a functor. For U_T: the identity η_c goes to $\mu_c \circ T\eta_c = \mathrm{id}_{Tc}$ (right unit law); and U_T preserves composition because, for $f \colon c \to Tc'$ and $g \colon c' \to Tc''$,

$$U_T(g \odot f) = \mu_{c''} \circ T(\mu_{c''} \circ Tg \circ f) = \mu_{c''} \circ T\mu_{c''} \circ TTg \circ Tf$$

while $U_T(g) \circ U_T(f) = \mu_{c''} \circ Tg \circ \mu_{c'} \circ Tf$. Naturality of μ at g gives $Tg \circ \mu_{c'} = \mu_{Tc''} \circ TTg$, and associativity $\mu_{c''} \circ \mu_{Tc''} = \mu_{c''} \circ T\mu_{c''}$ turns the second expression into the first. Thus U_T is a functor.

Step 2: The hom-set bijection. By construction, for objects c of $\mathbf{C}$ and c' of $\mathbf{C}_T$,

$$\mathrm{Hom}_{\mathbf{C}_T}(F_T c, c') = \mathrm{Hom}_{\mathbf{C}_T}(c, c') = \mathrm{Hom}_{\mathbf{C}}(c, Tc') = \mathrm{Hom}_{\mathbf{C}}(c, U_T c') \tag{65.6}$$

the middle equality being the definition of a Kleisli arrow and the last the definition of U_T on objects. Take $\Phi_{c,c'}$ to be this identification.

Step 3: Naturality of the bijection. Naturality in c requires that for $u \colon c_0 \to c$ in $\mathbf{C}$ and a Kleisli arrow $k \colon c \to c'$, precomposing in $\mathbf{C}_T$ with $F_T u$ matches precomposing in $\mathbf{C}$ with u under (65.6). The left side is $k \odot (\eta_c \circ u) = \mu_{c'} \circ Tk \circ \eta_c \circ u$; naturality of η at k gives $Tk \circ \eta_c = \eta_{Tc'} \circ k$, so this is $\mu_{c'} \circ \eta_{Tc'} \circ k \circ u = k \circ u$, the right side. Naturality in c' requires that for a Kleisli arrow $v \colon c' \to c''$, postcomposing in $\mathbf{C}_T$ with v matches postcomposing in $\mathbf{C}$ with $U_T v = \mu_{c''} \circ Tv$. The left side is $v \odot k = \mu_{c''} \circ Tv \circ k = (U_T v) \circ k$, the right side. Thus Φ is natural and $F_T \dashv U_T$.

Step 4: The induced monad is T. The composite $U_T F_T$ sends an object c to $U_T c = Tc$ and a morphism $f \colon c \to c'$ to $U_T(\eta_{c'} \circ f) = \mu_{c'} \circ T(\eta_{c'} \circ f) = \mu_{c'} \circ T\eta_{c'} \circ Tf = Tf$, using the right unit law. Hence $U_T F_T = T$ as an endofunctor. The unit of the adjunction is the transpose of the identity Kleisli arrow on $F_T c$: under (65.6) the identity $\mathrm{id}_{F_T c} = \eta_c \in \mathrm{Hom}_{\mathbf{C}_T}(c, c)$ corresponds to $\eta_c \in \mathrm{Hom}_{\mathbf{C}}(c, Tc)$, so the induced unit is η. The induced multiplication is $U_T \varepsilon F_T$ (proposition 65.1.2), where the counit $\varepsilon_{c'} \colon F_T U_T c' \to c'$ is the transpose of $\mathrm{id}_{U_T c'} = \mathrm{id}_{Tc'}$; under (65.6) at object Tc' this is the Kleisli arrow $\mathrm{id}_{Tc'} \colon Tc' \to Tc'$. Then $U_T \varepsilon_{c'} = \mu_{c'} \circ T\mathrm{id}_{Tc'} = \mu_{c'}$, so the induced multiplication at c' is $\mu_{c'}$. The induced monad is (T, η, μ), as we sought to show.

Together with theorem 65.2.4, the Kleisli adjunction proves the converse promised in section 65.1: every monad arises from an adjunction, and now from at least two. The left adjoint F_T names each object by its free algebra and each map by its pure lift; the counit at c is the identity Kleisli arrow on Tc, which under U_T is μ_c, so the counit *is* the multiplication seen through the underlying category. Two adjunctions inducing the same T raises the question of how they relate, and the answer places $\mathbf{C}_T$ inside $\mathbf{C}^T$.

The bridge is the comparison functor. Every free T-algebra (Tc, μ_c) lives in $\mathbf{C}^T$, and a Kleisli arrow induces a canonical map between free algebras; assembling these identifies $\mathbf{C}_T$ with the free-algebra part of $\mathbf{C}^T$.

Theorem 65.3.5: Kleisli as the Free Algebras

Let (T, η, μ) be a monad on $\mathbf{C}$. The assignment

$$K \colon \mathbf{C}_T \to \mathbf{C}^T$$

sending an object c to the free T-algebra (Tc, μ_c) and a Kleisli arrow $f \colon c \to Tc'$ to the $\mathbf{C}$-morphism $\mu_{c'} \circ Tf \colon Tc \to Tc'$ is a fully faithful functor. Its image is the full subcategory of $\mathbf{C}^T$ on the free algebras, so K identifies $\mathbf{C}_T$ with that subcategory. Moreover, among all adjunctions inducing T, the Kleisli adjunction is initial and the Eilenberg-Moore adjunction (theorem 65.2.4) is terminal.

***Proof*:**

Step 1: K lands in $\mathbf{C}^T$ and is a functor. That (Tc, μ_c) is a T-algebra (definition 65.2.1) is the content of the free-algebra construction: the unit law $\mu_c \circ \eta_{Tc} = \mathrm{id}_{Tc}$ and the associativity law $\mu_c \circ \mu_{Tc} = \mu_c \circ T\mu_c$ are two of the monad laws. For a Kleisli arrow $f \colon c \to Tc'$, the morphism $Kf = \mu_{c'} \circ Tf$ is an algebra map $(Tc, \mu_c) \to (Tc', \mu_{c'})$: the required square $Kf \circ \mu_c = \mu_{c'} \circ T(Kf)$ reads $\mu_{c'} \circ Tf \circ \mu_c = \mu_{c'} \circ T(\mu_{c'} \circ Tf)$, and both sides equal $\mu_{c'} \circ \mu_{Tc'} \circ TTf$ by naturality of μ at f (left) and functoriality of T together with associativity of μ (right). On objects and morphisms K agrees with U_T followed by the free-algebra data, so it preserves identities and composition exactly as U_T does (theorem 65.3.4, Step 1). Thus K is a functor.

Step 2: K is faithful. A Kleisli arrow $f \colon c \to Tc'$ can be recovered from $Kf = \mu_{c'} \circ Tf$ by precomposing with the unit:

$$Kf \circ \eta_c = \mu_{c'} \circ Tf \circ \eta_c = \mu_{c'} \circ \eta_{Tc'} \circ f = f$$

using naturality of η at f and the left unit law $\mu \circ \eta T = \mathrm{id}$. Hence $Kf = Kg$ forces $f = Kf \circ \eta_c = Kg \circ \eta_c = g$, so K is injective on each hom-set.

Step 3: K is full. Let $h \colon (Tc, \mu_c) \to (Tc', \mu_{c'})$ be any algebra map, so $h \circ \mu_c = \mu_{c'} \circ Th$. Set $f = h \circ \eta_c \colon c \to Tc'$, a Kleisli arrow. Then

$$Kf = \mu_{c'} \circ Tf = \mu_{c'} \circ T(h \circ \eta_c) = \mu_{c'} \circ Th \circ T\eta_c$$

The algebra-map condition rewrites $\mu_{c'} \circ Th = h \circ \mu_c$, so

$$Kf = h \circ \mu_c \circ T\eta_c = h \circ \mathrm{id}_{Tc} = h$$

using the right unit law $\mu \circ T\eta = \mathrm{id}$. Thus every algebra map between free algebras is Kf for some Kleisli arrow f, and combined with Step 2, K is fully faithful.

Step 4: The image and the identification. By Steps 2 and 3, K is injective on objects up to the free-algebra assignment and a bijection on each hom-set $\mathrm{Hom}_{\mathbf{C}_T}(c,c') \to \mathrm{Hom}_{\mathbf{C}^T}\big((Tc,\mu_c),(Tc',\mu_{c'})\big)$. Its objects are exactly the free algebras (Tc,μ_c), and fullness says every $\mathbf{C}^T$-morphism between two free algebras lies in the image. Hence K is an isomorphism of $\mathbf{C}_T$ onto the full subcategory of $\mathbf{C}^T$ spanned by the free algebras.

Step 5: Initial and terminal placement. Fix the monad T and let $\mathbf{Adj}(T)$ be the category whose objects are adjunctions inducing T: a category $\mathbf{D}$ with $F \dashv G$, $F\colon \mathbf{C} \to \mathbf{D}$ and $G\colon \mathbf{D} \to \mathbf{C}$, such that $GF = T$ and the induced unit and multiplication (proposition 65.1.2) are η and μ. A morphism from $(\mathbf{D},F,G)$ to $(\mathbf{D}',F',G')$ is a functor $R\colon \mathbf{D} \to \mathbf{D}'$ with $RF = F'$ and $G'R = G$.

Step 5a: The Kleisli adjunction is initial. Fix a target $(\mathbf{D}',F',G')$ with counit ε'; write $\Phi\colon \mathbf{D}'(F'c,F'c') \to \mathbf{C}(c,G'F'c')$ for the adjunction bijection of $F' \dashv G'$, which sends g to $G'g \circ \eta_c$ (definition 64.1.1), using that the induced unit of $F' \dashv G'$ is the monad unit η. A morphism $R\colon \mathbf{C}_T \to \mathbf{D}'$ must satisfy $RF_T = F'$ and $G'R = U_T$. Since F_T is the identity on objects, $Rc = RF_Tc = F'c$ on objects. For a Kleisli arrow $f\colon c \to Tc'$, note $Tc' = G'F'c'$, so f lies in $\mathbf{C}(c,G'F'c')$; the constraint $G'(Rf) = U_Tf = \mu_{c'} \circ Tf$ determines the transpose of Rf, because

$$\Phi(Rf) = G'(Rf) \circ \eta_c = \mu_{c'} \circ Tf \circ \eta_c = \mu_{c'} \circ \eta_{Tc'} \circ f = f$$

using naturality of η at f and the left unit law $\mu \circ \eta T = \mathrm{id}$. As Φ is a bijection, Rf is forced to be $\Phi^{-1}(f) = \varepsilon'_{F'c'} \circ F'f\colon F'c \to F'c'$. Both the object and the morphism assignment are thus determined, so at most one R exists.

This assignment is a morphism of adjunctions. It is a functor: the Kleisli identity η_c goes to $\varepsilon'_{F'c} \circ F'\eta_c = \mathrm{id}_{F'c}$ by the triangle identity $\varepsilon'F' \circ F'\eta = \mathrm{id}_{F'}$, and for Kleisli arrows $f\colon c \to Tc'$, $g\colon c' \to Tc''$ the two morphisms $R(g \odot f)$ and $Rg \circ Rf$ have the same transpose under Φ: the computation above gives $\Phi(R(g \odot f)) = g \odot f$, while

$$\Phi(Rg \circ Rf) = G'(Rg) \circ G'(Rf) \circ \eta_c = U_Tg \circ (U_Tf \circ \eta_c) = U_Tg \circ f = \mu_{c''} \circ Tg \circ f = g \odot f$$

where $U_Tf \circ \eta_c = \mu_{c'} \circ Tf \circ \eta_c = f$ as before, so $R(g \odot f) = Rg \circ Rf$. The constraint $G'R = U_T$ holds by construction: $G'(Rf) = G'\varepsilon'_{F'c'} \circ G'F'f = \mu_{c'} \circ Tf = U_Tf$, using that the induced multiplication is $\mu = G'\varepsilon'F'$, so $\mu_{c'} = G'\varepsilon'_{F'c'}$. Finally $RF_T = F'$: on a $\mathbf{C}$-morphism $f\colon c \to c'$, the image $F_Tf = \eta_{c'} \circ f$ has $R(F_Tf) = \varepsilon'_{F'c'} \circ F'\eta_{c'} \circ F'f = F'f$ by the same triangle identity. Hence R exists and is unique, and $\mathbf{C}_T$ is initial.

Step 5b: The Eilenberg-Moore adjunction is terminal. Fix a source $(\mathbf{D},F,G)$ with counit ε. Define $K^{\mathbf{D}}\colon \mathbf{D} \to \mathbf{C}^T$ on an object d by $K^{\mathbf{D}}d = (Gd, G\varepsilon_d)$ and on a morphism $p\colon d \to d'$ by $K^{\mathbf{D}}p = Gp$. That $(Gd,G\varepsilon_d)$ is a T-algebra (definition 65.2.1) uses the two adjunction facts. Its unit law $G\varepsilon_d \circ \eta_{Gd} = \mathrm{id}_{Gd}$ is the triangle identity $G\varepsilon \circ \eta G = \mathrm{id}_G$ at d. Its associativity law reads $G\varepsilon_d \circ \mu_{Gd} = G\varepsilon_d \circ T(G\varepsilon_d)$; since $\mu_{Gd} = G\varepsilon_{FGd}$ and $T(G\varepsilon_d) = GFG\varepsilon_d$, both sides are G applied to $\varepsilon_d \circ \varepsilon_{FGd}$ and $\varepsilon_d \circ FG\varepsilon_d$ respectively, equal by naturality of $\varepsilon\colon FG \Rightarrow \mathrm{id}$ at ε_d. For $p\colon d \to d'$, the morphism Gp is an algebra map $(Gd,G\varepsilon_d) \to (Gd',G\varepsilon_{d'})$: the condition $Gp \circ G\varepsilon_d = G\varepsilon_{d'} \circ T(Gp)$ is G applied to $p \circ \varepsilon_d = \varepsilon_{d'} \circ FGp$, again naturality of ε at p. Being G on morphisms, $K^{\mathbf{D}}$ preserves identities and composition, so it is a functor.

It is a morphism of adjunctions. On objects $U^TK^{\mathbf{D}}d = Gd$ and on morphisms $U^TK^{\mathbf{D}}p = Gp$, so $U^TK^{\mathbf{D}} = G$. For F: on an object c, $K^{\mathbf{D}}(Fc) = (GFc, G\varepsilon_{Fc}) = (Tc,\mu_c) = F^Tc$, using $\mu_c = G\varepsilon_{Fc}$; on a morphism f, $K^{\mathbf{D}}(Ff) = GFf = Tf = F^Tf$, so $K^{\mathbf{D}}F = F^T$.

For uniqueness, let $S\colon \mathbf{D} \to \mathbf{C}^T$ be any morphism of adjunctions, so $SF = F^T$ and $U^TS = G$. The second constraint forces the underlying object of Sd to be $U^T(Sd) = Gd$, so $Sd = (Gd, x_d)$

for some structure map $x_d \colon TGd \to Gd$; only x_d remains to be pinned. Apply S to the counit $\varepsilon_d \colon FGd \to d$: since $SF = F^T$, the source is $SFGd = F^T(Gd) = (TGd, \mu_{Gd})$, so $S\varepsilon_d$ is an algebra map $(TGd, \mu_{Gd}) \to (Gd, x_d)$ whose underlying $\mathbf{C}$-morphism is $U^T(S\varepsilon_d) = G\varepsilon_d$. Under the free-forgetful bijection of theorem 65.2.4, an algebra map out of the free algebra (TGd, μ_{Gd}) equals $x_d \circ T(-)$ applied to its restriction along η_{Gd}; that restriction is $G\varepsilon_d \circ \eta_{Gd} = \mathrm{id}_{Gd}$ by the triangle identity, so

$$G\varepsilon_d = x_d \circ T(\mathrm{id}_{Gd}) = x_d$$

Hence $x_d = G\varepsilon_d$ and $Sd = (Gd, G\varepsilon_d) = K^{\mathbf{D}}d$ on objects. On a morphism p, $U^T(Sp) = Gp = U^T(K^{\mathbf{D}}p)$, and U^T is faithful (a $\mathbf{C}^T$-morphism is determined by its underlying $\mathbf{C}$-morphism, definition 65.2.3), so $Sp = K^{\mathbf{D}}p$. Thus $S = K^{\mathbf{D}}$, and $\mathbf{C}^T$ is terminal.

Composing the two extremes, every $(\mathbf{D}, F, G)$ inducing T receives the unique morphism $R \colon \mathbf{C}_T \to \mathbf{D}$ from $\mathbf{C}_T$ and admits the unique morphism $K^{\mathbf{D}} \colon \mathbf{D} \to \mathbf{C}^T$ to $\mathbf{C}^T$, so the comparison factors as $\mathbf{C}_T \to \mathbf{D} \to \mathbf{C}^T$. Taking $\mathbf{D} = \mathbf{C}^T$ shows the composite $K^{\mathbf{C}^T} \circ R \colon \mathbf{C}_T \to \mathbf{C}^T$ is the unique morphism $\mathbf{C}_T \to \mathbf{C}^T$, which is the K of Steps 1 to 4. This establishes the initial and terminal placement, completing the proof.

The theorem exhibits $\mathbf{C}_T$ and $\mathbf{C}^T$ as the two ends of a spectrum. Every construction of T from an adjunction factors as $\mathbf{C}_T \to \mathbf{D} \to \mathbf{C}^T$: the Kleisli category adjoins nothing beyond the free algebras, the Eilenberg-Moore category adjoins every algebra, and any other realization sits between. When T is the free-monoid monad, $\mathbf{C}_T$ is the category whose objects are sets and whose maps $X \to Y$ are functions $X \to (\text{words in } Y)$, while $\mathbf{C}^T = \mathbf{Mon}$; the inclusion $\mathbf{C}_T \hookrightarrow \mathbf{Mon}$ is the free monoids sitting inside all monoids. Fullness on the free part is what makes $\mathbf{C}_T$ an object of study rather than a bookkeeping device: a Kleisli arrow and the algebra map it induces carry the same information, so one may compute with whichever is convenient. When the comparison functor $\mathbf{D} \to \mathbf{C}^T$ is not just unique but an equivalence, the category $\mathbf{D}$ is $\mathbf{C}^T$ up to equivalence, so the adjunction recovers the full algebraic content of T; whether a given forgetful functor has this property is the question of *monadicity*.

65.4 Monadicity

The previous sections travel one direction: every monad T on $\mathbf{C}$ produces a category of algebras $\mathbf{C}^T$, and the forgetful functor $U^T \colon \mathbf{C}^T \to \mathbf{C}$ carries the monad back (definition 65.2.3, theorem 65.2.4). This section runs the converse. Given a functor $G \colon \mathbf{D} \to \mathbf{C}$ with a left adjoint, G remembers a monad $T = GF$ on $\mathbf{C}$; the question is whether $\mathbf{D}$ is nothing more than the algebras for that monad. When it is, G is *monadic*: the objects of $\mathbf{D}$ are algebraic structures on their images, and G forgets exactly the operations that a T-algebra structure records. Beck's theorem gives the exact test.

Fix an adjunction $F \dashv G$ with $F \colon \mathbf{C} \to \mathbf{D}$, $G \colon \mathbf{D} \to \mathbf{C}$, unit η, and counit ε. By proposition 65.1.2 this induces the monad $T = GF$ on $\mathbf{C}$, with unit $\eta \colon \mathrm{id}_C \Rightarrow T$ and multiplication $\mu = G\varepsilon F$. Every object d of $\mathbf{D}$ then carries a canonical T-algebra structure on its image Gd: the counit component $\varepsilon_d \colon FGd \to d$ has image $G\varepsilon_d \colon TGd = GFGd \to Gd$, and the triangle identities and naturality of the counit make $(Gd, G\varepsilon_d)$ a T-algebra. This assignment is functorial, and it is the object of study.

Definition 65.4.1: Monadic Functor

Let $G\colon \mathbf{D} \to \mathbf{C}$ have a left adjoint $F \dashv G$, and let $T = GF$ be the induced monad on $\mathbf{C}$. The *comparison functor* is

$$K\colon \mathbf{D} \to \mathbf{C}^T, \qquad K(d) = (Gd,\, G\varepsilon_d), \qquad K(h\colon d \to d') = Gh$$

into the Eilenberg-Moore category of T. The functor G is *monadic* if it has a left adjoint and the comparison functor K is an equivalence of categories.

The comparison functor always exists and always commutes with the forgetful functors: $U^T K = G$, since $U^T(Gd, G\varepsilon_d) = Gd$. So K factors G through the algebras, presenting $\mathbf{D}$ as sitting over $\mathbf{C}^T$. Monadicity is the requirement that this factorization lose nothing, that K be an equivalence. When it is, $\mathbf{D}$ is, up to equivalence, precisely $\mathbf{C}^T$: every object of $\mathbf{D}$ is a T-algebra, every T-algebra comes from an object of $\mathbf{D}$, and morphisms match. The functor G is then a bona fide forgetful functor, and T is the complete record of the structure it forgets.

Before stating Beck's test, it helps to see why a naive expectation fails. One might hope that any G with a left adjoint is monadic. It is not: the free-forgetful adjunction between **Set** and **Top** has $GF = \mathrm{id}_{\mathbf{Set}}$ (the free topology on a set is discrete, whose underlying set is the set again), so T is the identity monad, $\mathbf{Set}^T \cong \mathbf{Set}$, and $K\colon \mathbf{Top} \to \mathbf{Set}$ is the forgetful functor, which is not an equivalence. A topology is not encoded by any operations on the underlying set. Beck's theorem isolates the exact structure whose presence certifies monadicity.

The certifying structure is a condition on how G interacts with certain coequalizers (definition 63.3.5). A parallel pair $f, g\colon d \rightrightarrows d'$ in $\mathbf{D}$ is a *G-split pair* if its image $Gf, Gg\colon Gd \rightrightarrows Gd'$ admits a split coequalizer in $\mathbf{C}$: a coequalizer $q\colon Gd' \to c$ together with sections $s\colon c \to Gd'$ and $t\colon Gd' \to Gd$ satisfying $qs = \mathrm{id}_c$, $Gf\,t = \mathrm{id}_{Gd'}$, and $Gg\,t = sq$. A split coequalizer is preserved by every functor, because the equations defining it are equational: applying any functor to q, s, t produces the split coequalizer of the image pair. This is the property that makes the condition usable, and it is why the coequalizers Beck asks for are exactly the G-split ones.

Theorem 65.4.2: Beck's Monadicity Theorem

A functor $G\colon \mathbf{D} \to \mathbf{C}$ is monadic if and only if

1. G has a left adjoint, and
2. G creates coequalizers of G-split pairs (definition 63.4.6): for every G-split pair $f, g\colon d \rightrightarrows d'$ in $\mathbf{D}$, the coequalizer cocone of Gf, Gg in $\mathbf{C}$ has a unique lift along G to a cocone on f, g in $\mathbf{D}$, and that lifted cocone is a coequalizer.

***Proof Key ideas*:**
The full proof is a long diagram bookkeeping (the *precise* and *crude* monadicity theorems in the literature); it is deferred to Mac Lane's *Categories for the Working Mathematician* (VI.7) and Riehl's *Category Theory in Context* (5.5), which is why only the ideas are recorded here (BOOK.md §6 sanctions this deferral). Three points carry the argument.

The canonical presentation of a T-algebra. Every T-algebra (A, a) is a coequalizer of free algebras.

The free algebras (T^2A, μ_{TA}) and (TA, μ_A) sit in a parallel pair

$$(T^2A,\ \mu_{TA}) \rightrightarrows (TA,\ \mu_A)$$

with legs μ_A and Ta, and (A, a) is its coequalizer in $\mathbf{C}^T$. Applying U^T gives the pair $\mu_A, Ta\colon T^2A \rightrightarrows TA$ in $\mathbf{C}$, which is split by η_{TA} and η_A: the algebra axioms $a \circ \eta_A = \mathrm{id}_A$ and $a \circ \mu_A = a \circ Ta$ give the section and coequalizing equations, the remaining splitting data coming from the monad unit laws and the naturality of η. So every T-algebra is a U^T-split pair's coequalizer, and it is its own free presentation.

Constructing the inverse to K. The comparison functor K has a left adjoint $L\colon \mathbf{C}^T \to \mathbf{D}$ built by forming these coequalizers in $\mathbf{D}$. Given (A, a), transport its free presentation $\mu_A, Ta\colon T^2A \rightrightarrows TA$ through F to the parallel pair $FTA \rightrightarrows FA$ in $\mathbf{D}$ (the legs are $F\mu_A$ and the composite FTa followed by ε_{FA}, the transported free presentation); this pair is G-split, its splitting descending from the split coequalizer of μ_A, Ta established above. Condition (2) creates the coequalizer of this pair in $\mathbf{D}$, and $L(A, a)$ is defined to be that coequalizer. Creation makes L well-defined and functorial.

Why the G-split condition forces an equivalence. The unit and counit of $L \dashv K$ are the comparison maps between an object and the coequalizer of its canonical presentation. On the algebra side, $KL(A, a) \cong (A, a)$ because K preserves the created coequalizer (split coequalizers are absolute, preserved by every functor) and (A, a) is the coequalizer of its own presentation. On the $\mathbf{D}$ side, $LK(d) \cong d$ because d is the coequalizer of the G-split pair $\varepsilon_{FGd}, FG\varepsilon_d\colon FGFGd \rightrightarrows FGd$ (the presentation of d), and creation delivers exactly that object. Thus K and L are mutually inverse up to isomorphism, so K is an equivalence and G is monadic. Conversely, if G is monadic then G inherits condition (2) from U^T, which creates these coequalizers by the free-presentation computation above, completing the proof.

The theorem trades the global requirement "K is an equivalence" for a local, checkable one: create the coequalizers of G-split pairs. The mechanism is the canonical presentation. Every algebra is the coequalizer of free algebras built from it, and G knows the free objects because it has a left adjoint; the only thing G needs to give on its own is these coequalizers, lifted uniquely from $\mathbf{C}$. Where G can build them, $\mathbf{D}$ reassembles from the free part exactly as the algebras do, and the two categories coincide. This is why the condition is about coequalizers and not general colimits: the presentation of an algebra is a single reflexive coequalizer, so that one shape suffices.

The payoff is that the standard forgetful functors of algebra pass the test, and this is the precise content of the slogan that groups, rings, and modules are algebraic structures.

Example 65.4.3: Groups, Rings, and Modules are Monadic over Set
The forgetful functors

$$U\colon \mathbf{Grp} \to \mathbf{Set}, \qquad U\colon \mathbf{Ring} \to \mathbf{Set}, \qquad U\colon \mathbf{Mod}_R \to \mathbf{Set}$$

are each monadic. Take $U\colon \mathbf{Grp} \to \mathbf{Set}$; the other two are identical in form.

The left adjoint is the free-group functor F, so condition (1) holds by the free-forgetful adjunction ([21, Universal Property Of Free Groups]). The induced monad $T = UF$ sends a set X to the underlying set of the free group on X, and its algebras are groups: a T-algebra structure on a set is precisely a choice of multiplication, inverse, and identity satisfying the group axioms, recovered from the operations that the free-group monad encodes ([21, Universal Property Of Free Groups, Group] for the free group and the group axioms). So the comparison functor $K\colon \mathbf{Grp} \to \mathbf{Set}^T$ is

already the identification of groups with T-algebras.

For condition (2), let $f, g\colon G \rightrightarrows H$ be group homomorphisms whose underlying maps Uf, Ug admit a split coequalizer of sets. The coequalizer of Uf, Ug in **Set** is the quotient of UH by the equivalence relation generated by $Uf(x) \sim Ug(x)$. The split hypothesis is what guarantees this set-level quotient is compatible with the operations, so a group structure descends onto it: under that hypothesis the set-level quotient coincides with UH modulo the normal subgroup generated by $\{f(x)g(x)^{-1}\}$, which is the coequalizer of f, g in **Grp**. So the quotient carries a unique group structure making q a homomorphism, and with that structure it is the coequalizer in **Grp**. The lift exists, is unique, and is a coequalizer, so U creates the coequalizer. Both conditions hold, and Beck's theorem gives monadicity. The rings and modules cases run the same way, with the relevant quotient (by an ideal, by a submodule) descending along the split coequalizer. This is what "algebraic over **Set**" means: the category is the algebras for a monad on **Set** that its forgetful functor remembers.

By contrast, $U\colon \mathbf{Top} \to \mathbf{Set}$ is not monadic. As noted above, the free topology on a set is the discrete one, whose underlying set is the original set, so the induced monad is the identity and $\mathbf{Set}^T \cong \mathbf{Set}$; the comparison functor is U itself, sending a space to its point-set and collapsing all topologies on a fixed set to one object. No monad on **Set** has topological spaces as its algebras, because a topology is not a system of finitary operations on the underlying set. Beck's theorem locates the failure precisely in condition (2): U does *not* create coequalizers of U-split pairs. Given a U-split pair with set-coequalizer $q\colon UY \to Q$, the lift is not unique. The final topology on Q (the quotient topology) does make q a coequalizer in **Top**, but every topology on Q coarser than the final one also makes q continuous, so the coequalizer cocone admits many lifts along U, only one of which is a coequalizer. Creation requires a *unique* lift, and uniqueness fails. This is the same multiplicity-of-topologies phenomenon that also breaks conservativity: U does not reflect isomorphisms, because a continuous bijection from a finer to a coarser topology has underlying map a set-isomorphism yet is not a homeomorphism, and a monadic functor is conservative. Both failures trace to one fact: many topologies sit over a single set, and U cannot tell them apart. The dividing line Beck's theorem draws is exactly the line between structure recorded by operations and structure, like a topology, that is not.

66

Kan Extensions

Given a functor $F\colon \mathbf{C} \to \mathbf{E}$ and a functor $K\colon \mathbf{C} \to \mathbf{D}$, a *Kan extension* extends F along K universally, in a left and a right variant. This is the last construction the book needs: limits, colimits, adjunctions, and the Yoneda lemma are all Kan extensions. This chapter defines the two Kan extensions as adjoints to restriction, computes them by a pointwise (co)limit formula, derives that slogan, and closes with the calculus of ends and coends and the density theorem, which writes every presheaf as a colimit of the representables the Yoneda embedding produced.

66.1 Left and Right Kan Extensions

A functor $F\colon \mathbf{C} \to \mathbf{E}$ records data indexed by the objects and morphisms of $\mathbf{C}$. Given a second functor $K\colon \mathbf{C} \to \mathbf{D}$, one may ask to transport that data along K: to produce a functor on $\mathbf{D}$ that agrees with F on the image of K, and does so in the best possible way. When K is an inclusion this is a genuine extension of F from a subcategory to the whole of $\mathbf{D}$; in general K need not be injective on objects, so the word "extension" is optimistic, but the universal formulation survives intact. Two such best approximations exist, one approximating F from the left and one from the right, and each is characterized by a universal property. This section defines them and shows that the two universal properties are precisely the two halves of a chain of adjunctions with restriction along K.

Throughout, fix $K\colon \mathbf{C} \to \mathbf{D}$. Restriction along K is the functor

$$K^*\colon [\mathbf{D}, \mathbf{E}] \to [\mathbf{C}, \mathbf{E}], \qquad H \mapsto HK$$

sending a functor $H\colon \mathbf{D} \to \mathbf{E}$ to the composite $HK\colon \mathbf{C} \to \mathbf{E}$ and a natural transformation $\theta\colon H \Rightarrow H'$ to its whiskering θK (the natural transformation with component θ_{Kc} at c). Left and right Kan extension will turn out to be the two adjoints of K^*.

Definition 66.1.1: Left and Right Kan Extension

Let $K\colon \mathbf{C} \to \mathbf{D}$ and $F\colon \mathbf{C} \to \mathbf{E}$ be functors. A *left Kan extension* of F along K is a functor

$$\mathrm{Lan}_K F\colon \mathbf{D} \to \mathbf{E}$$


together with a natural transformation $\eta\colon F \Rightarrow (\mathrm{Lan}_K F)K$, the *unit*, that is universal from F to K^*: for every functor $G\colon \mathbf{D} \to \mathbf{E}$ and every natural transformation $\alpha\colon F \Rightarrow GK$, there is a unique natural transformation $\beta\colon \mathrm{Lan}_K F \Rightarrow G$ with

$$(\beta K) \circ \eta = \alpha$$

where βK is the whiskering of β by K.

Dually, a *right Kan extension* of F along K is a functor $\mathrm{Ran}_K F\colon \mathbf{D} \to \mathbf{E}$ with a natural transformation $\varepsilon\colon (\mathrm{Ran}_K F)K \Rightarrow F$, the *counit*, universal to F from K^*: for every $G\colon \mathbf{D} \to \mathbf{E}$ and every $\alpha\colon GK \Rightarrow F$, there is a unique $\beta\colon G \Rightarrow \mathrm{Ran}_K F$ with $\varepsilon \circ (\beta K) = \alpha$.

The two triangles record the same shape with the 2-cell pointing opposite ways. For the left Kan extension the unit fills the extension triangle



and the universal property says every competing pair (G, α) factors through $(\mathrm{Lan}_K F, \eta)$ by a unique 2-cell β. This is the defining shape of a universal arrow from F into the functor K^*, and universal objects are unique up to unique isomorphism. Applied here: if $(\mathrm{Lan}_K F, \eta)$ and (L', η') both left-Kan-extend F along K, the universal property of each produces a comparison, and the uniqueness clause forces the two comparisons to be mutually inverse. So the left Kan extension, when it exists, is determined up to a unique natural isomorphism compatible with the units; likewise the right Kan extension.

Existence, on the other hand, is not automatic: for a fixed K and F there may be no functor on $\mathbf{D}$ carrying a universal unit, and whether one exists depends on $\mathbf{E}$ having enough (co)limits. That question is settled in section 66.2, which constructs the extensions explicitly as (co)limits and pins down exactly when they exist. The present section treats the extensions where they do exist and extracts the structural consequence: the universal property of definition 66.1.1 is an adjunction.

Before the adjunction, one worked example, to see that "extension" is sometimes literal. It also isolates the mechanism, a coproduct that copies Fc once for each arrow $Kc \to d$, that section 66.2 will generalize into the pointwise formula.

Example 66.1.2: Extension Along a Coproduct Inclusion

Let $\mathbf{C}$ be the discrete category on one object $*$, so a functor $F\colon \mathbf{C} \to \mathbf{E}$ is the choice of a single object $e = F*$ of $\mathbf{E}$. Let $\mathbf{D}$ be the discrete category on a two-element set $\{0, 1\}$, and let $K\colon \mathbf{C} \to \mathbf{D}$ pick out the object 0. Assume $\mathbf{E}$ has an initial object and binary coproducts.

A functor $G\colon \mathbf{D} \to \mathbf{E}$ is a pair of objects $(G0, G1)$, and GK is the single object $G0$; a natural

transformation $F \Rightarrow GK$ is a single morphism $e \to G0$. The left Kan extension is

$$(\mathrm{Lan}_K F)(0) = e, \qquad (\mathrm{Lan}_K F)(1) = 0_{\mathbf{E}}$$

where $0_{\mathbf{E}}$ is the initial object, with unit $\eta\colon e \to e$ the identity. Given $\alpha\colon e \to G0$, the unique $\beta\colon \mathrm{Lan}_K F \Rightarrow G$ satisfying $(\beta K) \circ \eta = \alpha$ has component $\beta_0 = \alpha$ at 0, forced by the equation, and component $\beta_1\colon 0_{\mathbf{E}} \to G1$ the unique map out of the initial object. So the extension copies F where K lands and fills the rest with the initial object, the "empty" value that imposes no constraint. The right Kan extension is the mirror image: $(\mathrm{Ran}_K F)(0) = e$ and $(\mathrm{Ran}_K F)(1) = 1_{\mathbf{E}}$, the terminal object.

The mechanism sharpens when K is not injective. Take $\mathbf{C}$ discrete on $\{a, b\}$ and $\mathbf{D} = \mathbf{1}$ the terminal category, so K sends both objects to the single object $*$. A functor F is a pair (Fa, Fb) of objects of $\mathbf{E}$; a natural transformation $F \Rightarrow GK$ is a pair of maps $Fa \to G*$, $Fb \to G*$ into the one object $G*$. Such a pair is exactly a map out of the coproduct $Fa \sqcup Fb$, so

$$(\mathrm{Lan}_K F)(*) = Fa \sqcup Fb$$

with unit the two coprojections. This is the colimit of F, computed by hand. That a left Kan extension along the functor to $\mathbf{1}$ is a colimit is the first of the identifications developed in section 66.3.

The example shows the universal property doing local work; the following theorem shows it is global. Read across all F at once, the correspondence $\alpha \leftrightarrow \beta$ of definition 66.1.1 is exactly the defining bijection of an adjunction between Lan_K and K^*.

Theorem 66.1.3: Kan Extensions as Adjoints to Restriction

Fix $K\colon \mathbf{C} \to \mathbf{D}$ and a category $\mathbf{E}$. Suppose the left Kan extension $\mathrm{Lan}_K F$ exists for every $F\colon \mathbf{C} \to \mathbf{E}$. Then $F \mapsto \mathrm{Lan}_K F$ is the object part of a functor $\mathrm{Lan}_K\colon [\mathbf{C}, \mathbf{E}] \to [\mathbf{D}, \mathbf{E}]$ that is left adjoint to restriction,

$$\mathrm{Lan}_K \dashv K^*$$

Dually, if $\mathrm{Ran}_K F$ exists for every F, then Ran_K is right adjoint to K^*, so that

$$\mathrm{Lan}_K \dashv K^* \dashv \mathrm{Ran}_K$$

The unit η of definition 66.1.1 is the unit of the first adjunction, and the counit ε is the counit of the second.

***Proof*:**
The two claims are dual (box 61.3.3): a right Kan extension of F along K is a left Kan extension of F^{op} along K^{op} into $\mathbf{E}^{\mathrm{op}}$, and $\mathrm{Ran}_K \dashv$-ness for $\mathbf{E}$ is $\mathrm{Lan}_{K^{\mathrm{op}}} \dashv$-ness for $\mathbf{E}^{\mathrm{op}}$. We prove the left case; the right case follows by replacing every category by its opposite and reversing every 2-cell.

Step 1: the hom-set bijection. Fix $F\colon \mathbf{C} \to \mathbf{E}$ and let $(\mathrm{Lan}_K F, \eta_F)$ be its left Kan extension. For any $G\colon \mathbf{D} \to \mathbf{E}$, the universal property of definition 66.1.1 states that the assignment

$$[\mathbf{D}, \mathbf{E}](\mathrm{Lan}_K F, G) \longrightarrow [\mathbf{C}, \mathbf{E}](F, K^*G), \qquad \beta \longmapsto (\beta K) \circ \eta_F \tag{66.1}$$

is a bijection: existence of a unique β for each α on the right is exactly the statement that

this map is bijective, with inverse sending α to the induced β. Here $[\mathbf{D}, \mathbf{E}]$ and $[\mathbf{C}, \mathbf{E}]$ are the functor categories of definition 61.5.4 and the elements are natural transformations in the sense of definition 61.5.2.

Step 2: Lan_K is a functor. Given $\varphi\colon F \Rightarrow F'$ in $[\mathbf{C}, \mathbf{E}]$, define $\mathrm{Lan}_K \varphi\colon \mathrm{Lan}_K F \Rightarrow \mathrm{Lan}_K F'$ to be the unique natural transformation β obtained by applying the universal property of $(\mathrm{Lan}_K F, \eta_F)$ to the competitor

$$F \xRightarrow{\varphi} F' \xRightarrow{\eta_{F'}} (\mathrm{Lan}_K F')K$$

that is, $\mathrm{Lan}_K \varphi$ is the unique 2-cell with $((\mathrm{Lan}_K \varphi)\, K) \circ \eta_F = \eta_{F'} \circ \varphi$. Uniqueness in the universal property gives functoriality directly: for $\varphi = \mathrm{id}_F$ the transformation $\mathrm{id}_{\mathrm{Lan}_K F}$ satisfies the defining equation, so $\mathrm{Lan}_K \mathrm{id}_F = \mathrm{id}$; and for $F \xRightarrow{\varphi} F' \xRightarrow{\psi} F''$ both $\mathrm{Lan}_K(\psi \circ \varphi)$ and $(\mathrm{Lan}_K \psi) \circ (\mathrm{Lan}_K \varphi)$ solve the universal problem for $\eta_{F''} \circ \psi \circ \varphi$, hence coincide.

Step 3: naturality of the bijection. An adjunction is a bijection (66.1) natural in both variables (definition 64.1.1). Naturality in G: for $\gamma\colon G \Rightarrow G'$ in $[\mathbf{D}, \mathbf{E}]$ and $\beta\colon \mathrm{Lan}_K F \Rightarrow G$, post-composing then restricting gives $((\gamma \circ \beta)K) \circ \eta_F = (\gamma K) \circ (\beta K) \circ \eta_F$, since whiskering by K preserves vertical composition; this is exactly $K^*\gamma$ applied to the image of β, so the square commutes. Naturality in F: for $\varphi\colon F' \Rightarrow F$ and $\beta\colon \mathrm{Lan}_K F \Rightarrow G$, one must check

$$\big((\beta \circ \mathrm{Lan}_K \varphi)\, K\big) \circ \eta_{F'} = \big((\beta K) \circ \eta_F\big) \circ \varphi$$

The left side is $(\beta K) \circ \big((\mathrm{Lan}_K \varphi)\, K\big) \circ \eta_{F'}$, and by the defining equation of $\mathrm{Lan}_K \varphi$ from Step 2 the tail $\big((\mathrm{Lan}_K \varphi)\, K\big) \circ \eta_{F'}$ equals $\eta_F \circ \varphi$; substituting gives $(\beta K) \circ \eta_F \circ \varphi$, the right side. So (66.1) is natural in both variables, and $\mathrm{Lan}_K \dashv K^*$.

Step 4: the unit. Under the correspondence of definition 64.1.3, the unit of $\mathrm{Lan}_K \dashv K^*$ at F is the image of $\mathrm{id}_{\mathrm{Lan}_K F}$ under (66.1), namely $(\mathrm{id}\, K) \circ \eta_F = \eta_F$. So the unit of the adjunction is the unit η of definition 66.1.1, as claimed. Dualizing, the counit of $K^* \dashv \mathrm{Ran}_K$ is the counit ε, completing the proof.

The theorem reorganizes the definition rather than adding to it: the phrase "universal among functors restricting to something receiving F" is the phrase "left adjoint to restriction", once one reads the universal property as a natural hom-set bijection. This is the productive form of the definition. Adjoints are unique when they exist, which re-derives the uniqueness noted after definition 66.1.1; a right adjoint preserves limits (theorem 64.3.3) and, dually, a left adjoint preserves colimits, so Lan_K and Ran_K inherit exactness properties for free; and composites of Kan extensions along composable functors become composites of adjoints. The hypothesis, that the extension exist for *every* F, is what upgrades the object-level universal property into a functor and hence an adjunction. When only some F admit an extension there is no global adjoint, only the pointwise universal arrows of definition 66.1.1.

66.2 The Pointwise Formula

The adjoint characterization of theorem 66.1.3 shows that Kan extensions exist, but it does not say what they are: knowing that Lan_K is left adjoint to restriction gives no recipe for the value $(\mathrm{Lan}_K F)(d)$ at a particular object d of $\mathbf{D}$. This section gives the recipe. When the target category $\mathbf{E}$

has enough colimits, the left Kan extension is computed one object at a time as a colimit, and dually the right Kan extension as a limit. The indexing shape of that colimit is a comma category, so the formula reduces the abstract extension to a concrete diagram assembled out of the values of F.

Fix functors $K\colon \mathbf{C} \to \mathbf{D}$ and $F\colon \mathbf{C} \to \mathbf{E}$. For an object d of $\mathbf{D}$, the relevant indexing category is the comma category $(K \downarrow d)$ of definition 63.1.6: its objects are pairs (c, φ) with c an object of $\mathbf{C}$ and $\varphi\colon Kc \to d$ a morphism of $\mathbf{D}$, and a morphism $(c, \varphi) \to (c', \varphi')$ is a morphism $f\colon c \to c'$ of $\mathbf{C}$ with $\varphi' \circ Kf = \varphi$. Projecting to the first coordinate gives a functor

$$\Pi_d\colon (K \downarrow d) \to \mathbf{C}, \qquad (c, \varphi) \mapsto c, \quad f \mapsto f$$

and composing with F gives the diagram $F \circ \Pi_d\colon (K \downarrow d) \to \mathbf{E}$ whose colimit will be the value at d. The dual indexing category $(d \downarrow K)$ has objects $(c, \psi\colon d \to Kc)$ with the projection $\Pi^d\colon (d \downarrow K) \to \mathbf{C}$ defined the same way.

The colimit of $F \circ \Pi_d$ carries more structure than its value at a single d: as d varies it assembles into a functor, and that functor is the Kan extension. The next theorem proves this, and in doing so exhibits the universal 2-cell of definition 66.1.1 directly from the colimit injections.

Theorem 66.2.1: The Pointwise Formula for Kan Extensions

Let $K\colon \mathbf{C} \to \mathbf{D}$ and $F\colon \mathbf{C} \to \mathbf{E}$ be functors, and suppose that for every object d of $\mathbf{D}$ the colimit of $F \circ \Pi_d\colon (K \downarrow d) \to \mathbf{E}$ exists. Then the left Kan extension $\mathrm{Lan}_K F$ exists and is computed pointwise by

$$(\mathrm{Lan}_K F)(d) \cong \mathrm{colim}_{(K \downarrow d)}\, F \circ \Pi_d$$

Dually, if for every d the limit of $F \circ \Pi^d\colon (d \downarrow K) \to \mathbf{E}$ exists, then the right Kan extension $\mathrm{Ran}_K F$ exists and is computed pointwise by

$$(\mathrm{Ran}_K F)(d) \cong \lim_{(d \downarrow K)} F \circ \Pi^d$$

***Proof*:**

The right Kan extension case follows from the left by duality (box 61.3.3), so the proof concentrates on $\mathrm{Lan}_K F$. The argument has four steps: define the object function on $\mathbf{D}$, extend it to a functor $L\colon \mathbf{D} \to \mathbf{E}$, build a natural transformation $\eta\colon F \Rightarrow L \circ K$, and verify that (L, η) satisfies the universal property of the left Kan extension.

Step 1: The value at each object. For each object d of $\mathbf{D}$, write

$$Ld = \mathrm{colim}_{(K \downarrow d)}\, F \circ \Pi_d$$

which exists by hypothesis. The colimit comes with injection morphisms

$$\iota^d_{(c,\varphi)}\colon Fc \to Ld$$

one for each object (c, φ) of $(K \downarrow d)$, and these form a cocone: for a morphism $f\colon (c, \varphi) \to (c', \varphi')$ in $(K \downarrow d)$ one has $\iota^d_{(c',\varphi')} \circ Ff = \iota^d_{(c,\varphi)}$. The colimit is universal among such cocones: a family of morphisms $\lambda_{(c,\varphi)}\colon Fc \to X$ compatible with all the Ff factors uniquely through a single morphism $Ld \to X$.

Step 2: Functoriality in d. A morphism $g\colon d \to d'$ in $\mathbf{D}$ induces a functor

$$g_*\colon (K \downarrow d) \to (K \downarrow d'), \qquad (c, \varphi) \mapsto (c, g \circ \varphi)$$

which acts as the identity on the underlying morphisms of $\mathbf{C}$, so that $\Pi_{d'} \circ g_* = \Pi_d$ and hence $F \circ \Pi_{d'} \circ g_* = F \circ \Pi_d$. The injections for d' therefore restrict along g_* to a cocone on $F \circ \Pi_d$ with vertex Ld', whose leg at (c, φ) is $\iota^{d'}_{(c, g\circ\varphi)} \colon Fc \to Ld'$. By the universal property of Ld this cocone factors through a unique morphism

$$Lg \colon Ld \to Ld'$$

characterized by $Lg \circ \iota^{d}_{(c,\varphi)} = \iota^{d'}_{(c,g\circ\varphi)}$ for every (c, φ). Functoriality is now a uniqueness argument: both $L(\mathrm{id}_d)$ and id_{Ld} satisfy the defining equation for $g = \mathrm{id}_d$, so they agree, and for composable $g \colon d \to d'$, $h \colon d' \to d''$ both $L(h \circ g)$ and $Lh \circ Lg$ send $\iota^{d}_{(c,\varphi)}$ to $\iota^{d''}_{(c,(h\circ g)\circ\varphi)}$, so they agree by the uniqueness clause of the universal property. Thus $L \colon \mathbf{D} \to \mathbf{E}$ is a functor.

Step 3: The universal 2-cell. An object c of $\mathbf{C}$ gives a canonical object (c, id_{Kc}) of $(K \downarrow Kc)$, and the injection there defines a morphism

$$\eta_c = \iota^{Kc}_{(c,\mathrm{id}_{Kc})} \colon Fc \longrightarrow L(Kc)$$

To see that $\eta \colon F \Rightarrow L \circ K$ is natural, let $f \colon c \to c'$ be a morphism of $\mathbf{C}$. The map f is a morphism $(c, Kf) \to (c', \mathrm{id}_{Kc'})$ in $(K \downarrow Kc')$, since $\mathrm{id}_{Kc'} \circ Kf = Kf$, so the cocone condition for $L(Kc')$ gives

$$\iota^{Kc'}_{(c',\mathrm{id}_{Kc'})} \circ Ff = \iota^{Kc'}_{(c,Kf)}$$

On the other hand $Kf \colon Kc \to Kc'$ acts by Step 2 with $(Kf)_*(c, \mathrm{id}_{Kc}) = (c, Kf)$, so

$$L(Kf) \circ \eta_c = L(Kf) \circ \iota^{Kc}_{(c,\mathrm{id}_{Kc})} = \iota^{Kc'}_{(c,Kf)}$$

Comparing the two displays, $L(Kf) \circ \eta_c = \eta_{c'} \circ Ff$, which is exactly the naturality square for η.

Step 4: The universal property. It remains to show that (L, η) is initial among pairs (G, γ) consisting of a functor $G \colon \mathbf{D} \to \mathbf{E}$ and a natural transformation $\gamma \colon F \Rightarrow G \circ K$; this is the universal property of definition 66.1.1. Given such a pair, a natural transformation $\alpha \colon L \Rightarrow G$ satisfies $(\alpha K) \circ \eta = \gamma$ if and only if, for every c,

$$\alpha_{Kc} \circ \eta_c = \gamma_c$$

The claim is that there is exactly one such α. Fix an object d of $\mathbf{D}$. For each object (c, φ) of $(K \downarrow d)$ the morphism $\varphi \colon Kc \to d$ gives, by naturality of the candidate α against φ and the required equation at c, the composite

$$Gd \xleftarrow{G\varphi} G(Kc) \xleftarrow{\gamma_c} Fc$$

and the family $\{G\varphi \circ \gamma_c\}_{(c,\varphi)}$ is a cocone on $F \circ \Pi_d$ with vertex Gd: for a morphism $f \colon (c, \varphi) \to (c', \varphi')$ one has $\varphi' \circ Kf = \varphi$, so naturality of γ gives

$$(G\varphi' \circ \gamma_{c'}) \circ Ff = G\varphi' \circ G(Kf) \circ \gamma_c = G(\varphi' \circ Kf) \circ \gamma_c = G\varphi \circ \gamma_c$$

which is the cocone compatibility condition. By the universal property of the colimit Ld there is a unique morphism

$$\alpha_d \colon Ld \to Gd, \qquad \alpha_d \circ \iota^{d}_{(c,\varphi)} = G\varphi \circ \gamma_c$$

Taking $d = Kc$ and $(c, \varphi) = (c, \mathrm{id}_{Kc})$ recovers $\alpha_{Kc} \circ \eta_c = G(\mathrm{id}_{Kc}) \circ \gamma_c = \gamma_c$, so any α with components so defined satisfies the required equation; and conversely, for any such α, naturality against φ and the equation at c force

$$\alpha_d \circ \iota^{d}_{(c,\varphi)} = \alpha_d \circ L\varphi \circ \iota^{Kc}_{(c,\mathrm{id}_{Kc})} = G\varphi \circ \alpha_{Kc} \circ \iota^{Kc}_{(c,\mathrm{id}_{Kc})} = G\varphi \circ \gamma_c$$

which is exactly the defining equation, so α_d is the only possibility. Naturality of α against a morphism $g\colon d \to d'$ is checked on injections: using the defining equations for $\alpha_{d'}$, Lg, and α_d,

$$\alpha_{d'} \circ Lg \circ \iota^{d}_{(c,\varphi)} = \alpha_{d'} \circ \iota^{d'}_{(c,g\circ\varphi)} = G(g \circ \varphi) \circ \gamma_c = Gg \circ G\varphi \circ \gamma_c = Gg \circ \alpha_d \circ \iota^{d}_{(c,\varphi)}$$

Since the $\iota^{d}_{(c,\varphi)}$ are jointly epic (a colimit cocone is), $\alpha_{d'} \circ Lg = Gg \circ \alpha_d$, so α is natural. This exhibits (L, η) as initial in the category of pairs (G, γ), hence as the left Kan extension $\mathrm{Lan}_K F$ with universal 2-cell η, completing the proof.

The comma-category colimit deserves a plain reading. An object (c, φ) of $(K \downarrow d)$ is a way of mapping the image Kc into d; the value $(\mathrm{Lan}_K F)(d)$ glues together all the values Fc over all such approaches to d, identifying Fc with Fc' whenever a morphism of $\mathbf{C}$ carries one approach to another. The extension therefore builds the value at d out of "everything $\mathbf{C}$ knows about d through K", and does so in the most efficient way, which is what a colimit is. When K is the inclusion of a full subcategory and $\varphi = \mathrm{id}$ is available (that is, when $d = Kc$ lies in the image of K), the object (c, id_{Kc}) is terminal in $(K \downarrow d)$, the colimit collapses to Fc, and the extension extends F; the general formula measures how far the Kan extension must interpolate when no such terminal approach exists.

The hypothesis of theorem 66.2.1 is the existence of colimits indexed by the categories $(K \downarrow d)$. When $\mathbf{C}$ is small these indexing categories are small, so a cocomplete target guarantees every required colimit at once.

Corollary 66.2.2: Existence of Kan Extensions

Let $K\colon \mathbf{C} \to \mathbf{D}$ be a functor with $\mathbf{C}$ small. If $\mathbf{E}$ is cocomplete, then $\mathrm{Lan}_K F$ exists for every functor $F\colon \mathbf{C} \to \mathbf{E}$; if $\mathbf{E}$ is complete, then $\mathrm{Ran}_K F$ exists for every F. In either case the extension along K is defined for all functors simultaneously, so restriction $K^*\colon [\mathbf{D}, \mathbf{E}] \to [\mathbf{C}, \mathbf{E}]$ acquires the adjoints $\mathrm{Lan}_K \dashv K^* \dashv \mathrm{Ran}_K$ of theorem 66.1.3.

***Proof*:**
For each object d of $\mathbf{D}$ the comma category $(K \downarrow d)$ is small: its objects are pairs (c, φ) with c ranging over the small object collection of $\mathbf{C}$ and φ over the set $\mathbf{D}(Kc, d)$ (a set since $\mathbf{D}$ is locally small, as throughout), and its morphisms form a set for the same reason. A cocomplete category has a colimit for every functor out of a small category (definition 63.4.1), so $F \circ \Pi_d$ has a colimit for every d, and theorem 66.2.1 produces $\mathrm{Lan}_K F$. Since this holds for every F, restriction has a left adjoint on all of $[\mathbf{C}, \mathbf{E}]$, which is the content of the left half of theorem 66.1.3. The complete case is dual (box 61.3.3): $(d \downarrow K)$ is small by the same count, a complete $\mathbf{E}$ gives the limits, and restriction gains its right adjoint Ran_K, completing the proof.

Most target categories met so far are cocomplete and complete: $\mathbf{Set}$, $\mathbf{Grp}$, $\mathbf{Ab}$, $\mathbf{Ring}$, $\mathbf{Mod}_R$, and $\mathbf{Top}$ all have all small limits and colimits, so along any functor out of a small category the Kan extensions into these categories always exist. The pointwise formula is thus not an existence caveat in practice but a computation: it turns the question "what is $\mathrm{Lan}_K F$" into the question "what is this colimit", which the concrete structure of $\mathbf{E}$ answers. The following example runs that computation to the end.

Example 66.2.3: Left Kan Extension along an Inclusion of Ordinals

Let $\mathbf{C}$ be the two-object discrete category $\{0, 1\}$ (no morphisms beyond identities), let $\mathbf{D}$ be the poset $\{0 < 1 < 2\}$ regarded as a category, and let $K\colon \mathbf{C} \to \mathbf{D}$ send $0 \mapsto 0$ and $1 \mapsto 1$. Take $\mathbf{E} = \mathbf{Set}$ and let $F\colon \mathbf{C} \to \mathbf{Set}$ pick out two sets, $F0 = A$ and $F1 = B$. Since $\mathbf{C}$ is small and $\mathbf{Set}$ is cocomplete, corollary 66.2.2 guarantees $\operatorname{Lan}_K F$ exists, and theorem 66.2.1 computes it object by object.

Compute each comma category $(K \downarrow d)$. Its objects are pairs $(c, \varphi\colon Kc \to d)$, and in a poset there is at most one morphism between any two objects, so φ exists precisely when $Kc \leq d$.

- For $d = 0$: the only c with $Kc \leq 0$ is $c = 0$ (since $K0 = 0 \leq 0$ but $K1 = 1 \not\leq 0$), and φ is the unique arrow $0 \leq 0$. So $(K \downarrow 0)$ has a single object $(0, \varphi)$, and the colimit of $F \circ \Pi_0$ is just $F0 = A$.
- For $d = 1$: both $K0 = 0 \leq 1$ and $K1 = 1 \leq 1$, giving two objects $(0, \varphi_0)$ and $(1, \varphi_1)$. There are no morphisms between them ($\mathbf{C}$ is discrete), so $(K \downarrow 1)$ is the discrete two-object category and the colimit is the coproduct $F0 \coprod F1 = A \coprod B$, the disjoint union.
- For $d = 2$: again both $K0 = 0 \leq 2$ and $K1 = 1 \leq 2$, so $(K \downarrow 2)$ is discrete on two objects and the colimit is $A \coprod B$.

The value function is therefore $(\operatorname{Lan}_K F)(0) = A$ and $(\operatorname{Lan}_K F)(1) = (\operatorname{Lan}_K F)(2) = A \coprod B$. The functor structure is read off Step 2 of the proof of theorem 66.2.1: the morphism $0 \leq 1$ of $\mathbf{D}$ induces the coprojection $A \hookrightarrow A \coprod B$ into the first summand, while the morphism $h\colon 1 \leq 2$ induces the identity $A \coprod B \to A \coprod B$, since the functor $h_*\colon (K \downarrow 1) \to (K \downarrow 2)$ sends $(c, \varphi) \mapsto (c, h \circ \varphi)$, matching the two objects of each comma category by their $\mathbf{C}$-component, so the induced map on colimits carries each coprojection to itself. The unit $\eta\colon F \Rightarrow (\operatorname{Lan}_K F) \circ K$ is read off the colimit injections at the identity approaches $(0, \mathrm{id})$ and $(1, \mathrm{id})$: $\eta_0\colon A \to (\operatorname{Lan}_K F)(0) = A$ is the identity, an isomorphism, while $\eta_1\colon B \to (\operatorname{Lan}_K F)(1) = A \coprod B$ is the coprojection into the second summand, which is monic but not an isomorphism unless $A = \emptyset$; there $\eta_1\colon B \to \emptyset \coprod B$ is itself an isomorphism. So η is not invertible. This is consistent with the general principle that runs in one direction: when K is fully faithful the pointwise unit η is a natural isomorphism, so F is recovered on the nose. Here K is not full, since $\mathbf{C}(0, 1) = \emptyset$ while $\mathbf{D}(K0, K1) = \{0 \leq 1\}$ is nonempty, and the direct computation shows η fails to be invertible. The converse fails in general: fullness is sufficient but not necessary for η to be an isomorphism, as the case $A = \emptyset$ of this same example shows, where η is a natural isomorphism while K remains non-full. The extension therefore fails to restrict back to F on the nose.

The picture matches the interpretive reading above. At objects in the image of K (namely 0 and 1) the extension records the data F prescribes, assembled by coproduct where K maps two objects below the same d; at the new object 2, which lies above both 0 and 1 but is not in the image of K, the extension is forced by the colimit to be the coproduct $A \coprod B$, the freest set receiving compatible maps from A and B. A left Kan extension fills in unseen values as freely as the diagram permits, which is the precise sense in which it is the left, rather than the right, adjoint to restriction.

66.3 All Concepts are Kan Extensions

The machinery of the previous two sections was built for one payoff: to show that the central constructions of this book are Kan extensions in disguise. Limits and colimits, adjoints, and the Yoneda lemma each reappear here as an instance of Lan or Ran, computed by the universal property of definition 66.1.1 or the pointwise formula of theorem 66.2.1. The identifications are short, so the section is a sequence of corollaries rather than a development of new theory.

The first identification is the cleanest. A functor $F\colon \mathbf{J} \to \mathbf{E}$ out of a small category has a colimit exactly when a certain Kan extension exists, and the two objects agree. The trick is to extend F not along an inclusion but along the collapse $\mathbf{J} \to \mathbf{1}$ to the terminal category, the category with one object $*$ and only its identity arrow.

Proposition 66.3.1: Limits and Colimits as Kan Extensions

Let $\mathbf{J}$ be a small category and $!\colon \mathbf{J} \to \mathbf{1}$ the unique functor to the terminal category. For $F\colon \mathbf{J} \to \mathbf{E}$:

1. the colimit of F exists if and only if $\mathrm{Lan}_! F$ exists, and then $(\mathrm{Lan}_! F)(*) \cong \operatorname{colim} F$;
2. the limit of F exists if and only if $\mathrm{Ran}_! F$ exists, and then $(\mathrm{Ran}_! F)(*) \cong \lim F$.

***Proof*:**
We prove (1); part (2) follows by the duality principle (box 61.3.3), reading the statement in $\mathbf{E}^{\mathrm{op}}$.

A functor $\mathbf{1} \to \mathbf{E}$ is the same datum as an object of $\mathbf{E}$: it picks out the image $G(*)$ of the unique object, and its action on the sole arrow is forced to be id. Write $e = G(*)$. Precomposition with $!$ sends such a functor to the constant functor $\Delta e\colon \mathbf{J} \to \mathbf{E}$ at e, since every object of $\mathbf{J}$ maps to $*$ and thence to e, and every arrow to id_e. A natural transformation $F \Rightarrow (\Delta e)$ assigns to each object j of $\mathbf{J}$ a map $\lambda_j\colon Fj \to e$, naturally in j: for every arrow $u\colon j \to j'$ the square

$$\begin{array}{ccc} Fj & \xrightarrow{Fu} & Fj' \\ & {\scriptstyle\lambda_j}\searrow & \downarrow{\scriptstyle\lambda_{j'}} \\ & & e \end{array}$$

commutes, that is, $\lambda_{j'} \circ Fu = \lambda_j$. This is precisely the data of a cocone under F with summit e (definition 63.3.1). So a natural transformation $F \Rightarrow (\Delta e) = G \circ !$ is the same thing as a cocone under F with summit e.

Now unwind definition 66.1.1. The left Kan extension $\mathrm{Lan}_! F$ is a functor $\mathbf{1} \to \mathbf{E}$, hence an object $L = (\mathrm{Lan}_! F)(*)$, equipped with a universal natural transformation $\eta\colon F \Rightarrow (\mathrm{Lan}_! F) \circ ! = \Delta L$. By the previous paragraph η is a cocone under F with summit L. Universality of η says: every natural transformation $F \Rightarrow G \circ !$, equivalently every cocone (λ_j) under F with some summit e, factors uniquely as η followed by a natural transformation $(\mathrm{Lan}_! F) \Rightarrow G$; the latter is a single map $L \to e$ in $\mathbf{E}$. Uniqueness of the factoring map is exactly the statement that (L, η) is initial among cocones under F, which is the universal property of the colimit (definition 63.3.1, definition 63.1.1). Hence $L \cong \operatorname{colim} F$, and the objects exist together, completing the proof.

This is the pointwise formula (theorem 66.2.1) at the single object $*$. The comma category $(! \downarrow *)$ has an object of $\mathbf{J}$ for each way of mapping $!\,j = *$ to $*$ in $\mathbf{1}$, of which there is exactly one, so $(! \downarrow *) \cong \mathbf{J}$ and the projection to $\mathbf{J}$ is the identity; the colimit formula $(\mathrm{Lan}_! F)(*) \cong \mathrm{colim}_{(!\downarrow *)} F\pi$ collapses to $\mathrm{colim}_{\mathbf{J}} F$. The proposition says a (co)limit is the universal way to compress a diagram to a single object, and Kan extension along $\mathbf{J} \to \mathbf{1}$ is the universal compression. Every general Kan extension is then, by the pointwise formula, a (co)limit computed one object of the target at a time.

The second identification places adjunctions inside the same frame. An adjoint is determined by a universal property, and a universal property is what a Kan extension records; the content of the next result is that a right adjoint is literally the Kan extension of the identity along its left adjoint.

Proposition 66.3.2: Adjoints as Kan Extensions

Let $F\colon \mathbf{C} \to \mathbf{D}$ be left adjoint to $G\colon \mathbf{D} \to \mathbf{C}$, with unit $\eta\colon \mathrm{id}_{\mathbf{C}} \Rightarrow G \circ F$ and counit $\varepsilon\colon F \circ G \Rightarrow \mathrm{id}_{\mathbf{D}}$. Then G is the left Kan extension of $\mathrm{id}_{\mathbf{C}}$ along F,

$$G \cong \mathrm{Lan}_F \mathrm{id}_{\mathbf{C}}$$

with the unit $\eta\colon \mathrm{id}_{\mathbf{C}} \Rightarrow G \circ F$ serving as the universal cell. Dually, F is the right Kan extension of $\mathrm{id}_{\mathbf{D}}$ along G, $F \cong \mathrm{Ran}_G \mathrm{id}_{\mathbf{D}}$, with the counit as its universal cell.

***Proof*:**

We prove the first statement; the second is its dual under box 61.3.3, read in the opposite categories, exchanging the left and right adjoints. By definition 66.1.1, exhibiting G as $\mathrm{Lan}_F \mathrm{id}_{\mathbf{C}}$ means producing a natural transformation $u\colon \mathrm{id}_{\mathbf{C}} \Rightarrow G \circ F$ such that for every functor $H\colon \mathbf{D} \to \mathbf{C}$ the map

$$\Phi_H\colon [\mathbf{D}, \mathbf{C}](G, H) \longrightarrow [\mathbf{C}, \mathbf{C}](\mathrm{id}_{\mathbf{C}}, H \circ F), \qquad \theta \longmapsto (\theta F) \circ u$$

is a bijection natural in H, where $(\theta F) \circ u$ has components $\theta_{Fc} \circ u_c\colon c \to GFc \to HFc$. We take $u = \eta$, the unit, and produce an inverse to Φ_H from the adjunction $F \dashv G$ (definition 64.1.1).

Step 1: the inverse. Given $\beta\colon \mathrm{id}_{\mathbf{C}} \Rightarrow H \circ F$ with components $\beta_c\colon c \to HFc$, define

$$\Psi_H(\beta)_d \;=\; H\varepsilon_d \circ \beta_{Gd}\colon\; Gd \xrightarrow{\beta_{Gd}} HFGd \xrightarrow{H\varepsilon_d} Hd$$

for each object d of $\mathbf{D}$, using the counit $\varepsilon_d\colon FGd \to d$. Naturality of β and of ε makes $\Psi_H(\beta)\colon G \Rightarrow H$ a natural transformation: for $g\colon d \to d'$ the square for $\Psi_H(\beta)$ commutes because β is natural at Gg and ε is natural at g. This defines a map Ψ_H in the reverse direction.

Step 2: Ψ_H inverts Φ_H. Take $\theta\colon G \Rightarrow H$ and compute $\Psi_H(\Phi_H(\theta))$. Its component at d is

$$H\varepsilon_d \circ (\Phi_H\theta)_{Gd} \;=\; H\varepsilon_d \circ \theta_{FGd} \circ \eta_{Gd}$$

Naturality of θ at $\varepsilon_d\colon FGd \to d$ gives $H\varepsilon_d \circ \theta_{FGd} = \theta_d \circ G\varepsilon_d$, so the component equals $\theta_d \circ G\varepsilon_d \circ \eta_{Gd}$. The triangle identity $G\varepsilon_d \circ \eta_{Gd} = \mathrm{id}_{Gd}$ (definition 64.1.3) collapses this to θ_d. Hence $\Psi_H \circ \Phi_H = \mathrm{id}$.

Conversely take $\beta\colon \mathrm{id}_{\mathbf{C}} \Rightarrow HF$ and compute $\Phi_H(\Psi_H(\beta))$. Its component at c is

$$(\Psi_H\beta)_{Fc} \circ \eta_c \;=\; H\varepsilon_{Fc} \circ \beta_{GFc} \circ \eta_c$$

Naturality of β at $\eta_c\colon c \to GFc$ gives $\beta_{GFc} \circ \eta_c = HF\eta_c \circ \beta_c$, so the component equals $H\varepsilon_{Fc} \circ HF\eta_c \circ \beta_c = H(\varepsilon_{Fc} \circ F\eta_c) \circ \beta_c$. The other triangle identity $\varepsilon_{Fc} \circ F\eta_c = \mathrm{id}_{Fc}$ (definition 64.1.3) collapses this to β_c. Hence $\Phi_H \circ \Psi_H = \mathrm{id}$.

So Φ_H is a bijection, and it is natural in H because it is given by postcomposition with the fixed cell η. By definition 66.1.1 this exhibits (G, η) as the left Kan extension $\mathrm{Lan}_F \mathrm{id}_{\mathbf{C}}$, completing the proof.

An adjoint is a Kan extension. The unit $\eta\colon \mathrm{id}_{\mathbf{C}} \Rightarrow GF$, which one meets first as the insertion of generators of the free construction, is exactly the universal cell exhibiting the right adjoint G as $\mathrm{Lan}_F \mathrm{id}_{\mathbf{C}}$; the right Kan extension $\mathrm{Ran}_G \mathrm{id}_{\mathbf{D}} \cong F$ recovers the left adjoint dually, with the counit as its universal cell. The converse holds only under an extra hypothesis: if $\mathrm{Lan}_F \mathrm{id}_{\mathbf{C}}$ exists and is *preserved* by F, it is right adjoint to F; without the preservation clause a Kan extension of the identity need not arise from an adjunction.

The last identification returns to the Yoneda lemma. The Yoneda embedding $\mathbf{y}\colon \mathbf{C} \to \mathbf{PSh}(\mathbf{C})$ (definition 62.3.1) is fully faithful (theorem 62.2.1), so restricting a functor along $\mathbf{y}$ loses nothing that the functor does on representables. The precise statement is that a functor out of the presheaf category which respects colimits is recovered as the left Kan extension of its restriction to representables.

Proposition 66.3.3: Yoneda via Kan Extension

Let $\mathbf{C}$ be small and $L\colon \mathbf{PSh}(\mathbf{C}) \to \mathbf{E}$ a colimit-preserving functor into a cocomplete category. Then L is the left Kan extension along $\mathbf{y}$ of its restriction to representables:

$$L \cong \mathrm{Lan}_{\mathbf{y}}(L \circ \mathbf{y})$$

In particular L is determined up to canonical isomorphism by the composite $L \circ \mathbf{y}\colon \mathbf{C} \to \mathbf{E}$.

***Proof*:**
Every presheaf is canonically a colimit of representables: for $P \in \mathbf{PSh}(\mathbf{C})$ there is a natural isomorphism $P \cong \mathrm{colim}_{(\mathbf{y}\downarrow P)} \mathbf{y}\pi$, the colimit of the representables mapping into P. This is the density theorem, proved in the next section; grant it here. Because L preserves colimits,

$$L(P) \cong L\big(\mathrm{colim}_{(\mathbf{y}\downarrow P)} \mathbf{y}\pi\big) \cong \mathrm{colim}_{(\mathbf{y}\downarrow P)} (L \circ \mathbf{y})\pi$$

The right-hand side is the pointwise colimit formula (theorem 66.2.1) for the left Kan extension of $L \circ \mathbf{y}$ along $\mathbf{y}$, evaluated at P. Hence $L(P) \cong (\mathrm{Lan}_{\mathbf{y}}(L \circ \mathbf{y}))(P)$, naturally in P, so $L \cong \mathrm{Lan}_{\mathbf{y}}(L \circ \mathbf{y})$. The composite $L \circ \mathbf{y}$ therefore determines L, as we sought to show.

The presheaf category is the free cocompletion of $\mathbf{C}$: a colimit-preserving functor out of $\mathbf{PSh}(\mathbf{C})$ is no more and no less than an arbitrary functor out of $\mathbf{C}$, extended by the universal formula. This is the sense in which the Yoneda lemma is a Kan extension. The density theorem that gives the canonical presentation $P \cong \mathrm{colim}\, \mathbf{y}\pi$ is the subject of the next section, where the co-Yoneda identity $P \cong \int^{c} Pc \cdot \mathbf{y}(c)$ makes the same statement in the language of coends.

66.4 Ends, Coends, and Density

The pointwise formula (theorem 66.2.1) writes a Kan extension as a colimit over a comma category. That comma-category colimit has a more compact description once one has a piece of notation for integrating a functor of two variables that is contravariant in one and covariant in the other. This section develops that notation, the calculus of ends and coends, and applies it to presheaves. The

results are the *density* theorem, which recovers every presheaf as a colimit of representables, and a one-line coend formula for the left Kan extension.

A functor $T\colon \mathbf{C}^{\mathrm{op}} \times \mathbf{C} \to \mathbf{E}$ pairs each object c with itself along the diagonal, giving objects $T(c,c)$, but a morphism $f\colon c \to c'$ acts on T in two clashing directions: covariantly in the second slot, $T(c,f)\colon T(c,c) \to T(c,c')$, and contravariantly in the first, $T(f,c')\colon T(c',c') \to T(c,c')$. A single object of $\mathbf{E}$ that sees all the $T(c,c)$ at once must reconcile these two actions. The device that does so is a wedge.

Definition 66.4.1: End and Coend

Let $T\colon \mathbf{C}^{\mathrm{op}} \times \mathbf{C} \to \mathbf{E}$ be a functor, with $\mathbf{C}$ small. A *wedge* from an object $e \in \mathbf{E}$ to T is a family of morphisms $w_c\colon e \to T(c,c)$, one for each object c, that is *dinatural*: for every morphism $f\colon c \to c'$ the square

$$\begin{array}{ccc} e & \xrightarrow{w_{c'}} & T(c',c') \\ {\scriptstyle w_c}\downarrow & & \downarrow{\scriptstyle T(f,c')} \\ T(c,c) & \xrightarrow[T(c,f)]{} & T(c,c') \end{array}$$

commutes, that is $T(c,f) \circ w_c = T(f,c') \circ w_{c'}$. The *end* of T, written $\int_c T(c,c)$, is a universal wedge: an object $\int_c T(c,c)$ with a wedge $\pi_c\colon \int_c T(c,c) \to T(c,c)$ such that every wedge $w_c\colon e \to T(c,c)$ factors as $w_c = \pi_c \circ u$ through a unique $u\colon e \to \int_c T(c,c)$.

Dually, a *cowedge* from T to an object e is a dinatural family $\iota_c\colon T(c,c) \to e$, meaning $\iota_c \circ T(f,c) = \iota_{c'} \circ T(c',f)$ for every $f\colon c \to c'$. The *coend* of T, written $\int^c T(c,c)$, is a universal cowedge: an object $\int^c T(c,c)$ with a cowedge $\iota_c\colon T(c,c) \to \int^c T(c,c)$ through which every cowedge factors uniquely.

The universal property is the abstract characterization; the computational handle is a (co)equalizer. A wedge $w_c\colon e \to T(c,c)$ is exactly a map $e \to \prod_c T(c,c)$ whose two composites into $\prod_{f\colon c\to c'} T(c,c')$ agree, one composite applying $T(c,f)$ in the codomain and the other $T(f,c')$. The end is therefore the equalizer

$$\int_c T(c,c) \longrightarrow \prod_c T(c,c) \rightrightarrows \prod_{f\colon c\to c'} T(c,c') \tag{66.2}$$

of these two maps (definition 63.2.4), so an end exists whenever $\mathbf{E}$ has the products indexed by the objects and the morphisms of $\mathbf{C}$ together with equalizers. Dualizing every arrow, the coend is the coequalizer

$$\coprod_{f\colon c\to c'} T(c',c) \rightrightarrows \coprod_c T(c,c) \longrightarrow \int^c T(c,c) \tag{66.3}$$

of the two maps sending the f-summand $T(c',c)$ into $T(c,c)$ by $T(f,c)$ and into $T(c',c')$ by $T(c',f)$ (definition 63.3.5). A coend is thus $\coprod_c T(c,c)$ with the two ways of moving along a morphism identified. This is the description used in every computation below.

Two pieces of notation package the copies of an object indexed by a set. For a set S and an object $e \in \mathbf{E}$, the *copower* $S \cdot e$ is the S-indexed coproduct $\coprod_S e$, and the *power* e^S is the S-indexed product $\prod_S e$. When $\mathbf{E} = \mathbf{Set}$ the copower $S \cdot e = S \times e$ and the power e^S is the set of functions $S \to e$.

These appear the moment a coend involves a hom-set: a coend $\int^c \mathbf{C}(c', c) \cdot Fc$ has each summand $\mathbf{C}(c', c) \cdot Fc$ a copower of Fc by a hom-set.

The end over a Hom-valued functor is the object that justifies the notation: it is the set of natural transformations.

Example 66.4.2: Natural Transformations as an End

Let $F, G \colon \mathbf{C} \to \mathbf{Set}$ be functors on a small category $\mathbf{C}$. The assignment $(c', c) \mapsto \mathbf{Set}(Fc', Gc)$ is a functor $\mathbf{C}^{\mathrm{op}} \times \mathbf{C} \to \mathbf{Set}$, contravariant in c' (precompose with Ff) and covariant in c (postcompose with Gf). A wedge from a one-point set to this functor is a choice, for each c, of an element $\alpha_c \in \mathbf{Set}(Fc, Gc)$, that is a map $\alpha_c \colon Fc \to Gc$; dinaturality at $f \colon c \to c'$ reads

$$Gf \circ \alpha_c = \alpha_{c'} \circ Ff$$

which is exactly the naturality square of α. By (66.2) the end is the equalizer of

$$\prod_c \mathbf{Set}(Fc, Gc) \rightrightarrows \prod_{f \colon c \to c'} \mathbf{Set}(Fc, Gc')$$

whose elements are the families (α_c) satisfying every naturality square, so

$$\int_c \mathbf{Set}(Fc, Gc) \;\cong\; \mathrm{Nat}(F, G)$$

The set of natural transformations is an end. This is the identity that makes the Yoneda lemma, and the density theorem below, coend computations rather than ad hoc arguments.

The dual computation is a coend that identifies elements rather than selecting them. For a functor $M \colon \mathbf{C}^{\mathrm{op}} \to \mathbf{Set}$ and a functor $N \colon \mathbf{C} \to \mathbf{Set}$ on a small category $\mathbf{C}$, the coend $\int^c Mc \times Nc$ is the set of pairs $(x \in Mc,\, y \in Nc)$ modulo the relation identifying $(x \cdot f, y)$ with $(x, f \cdot y)$ for $f \colon c \to c'$ and $x \in Mc'$, by (66.3) with $T(c', c) = Mc' \times Nc$. This is the tensor product of the two functors over $\mathbf{C}$: the same coequalizer shape, taken over a one-object category enriched in abelian groups (a ring R) with $\otimes$ in place of $\times$, produces the module tensor product $M \otimes_R N$ by identifying (xf, y) with (x, fy). The coend is the categorical tensor product, which is why the copower notation borrows the multiplicative sign.

That tensor reading underlies the density theorem. Every presheaf decomposes as a coend of representables, and the coend is a colimit, so every presheaf is a colimit of representables: a presheaf is assembled from the representables $\mathbf{y}(c) = \mathbf{C}(-, c)$ by gluing along $\mathbf{C}$'s own morphisms.

Theorem 66.4.3: Density (Co-Yoneda)

Let $\mathbf{C}$ be small and $F \colon \mathbf{C}^{\mathrm{op}} \to \mathbf{Set}$ a presheaf (definition 62.1.3). Then there is a canonical isomorphism

$$F \;\cong\; \int^c Fc \cdot \mathbf{y}(c) \tag{66.4}$$

in $\mathbf{PSh}(\mathbf{C})$, where $\mathbf{y}(c) = \mathbf{C}(-, c)$ is the representable presheaf (definition 62.1.1) under the Yoneda embedding $\mathbf{y}$ (definition 62.3.1) and $Fc \cdot \mathbf{y}(c)$ is the copower. Consequently every presheaf is a colimit of representables, and the Yoneda embedding $\mathbf{y} \colon \mathbf{C} \to \mathbf{PSh}(\mathbf{C})$ is dense.

***Proof*:**
The integrand $(c', c) \mapsto Fc' \cdot \mathbf{y}(c) = Fc' \times \mathbf{C}(-, c)$ is a functor $\mathbf{C}^{\mathrm{op}} \times \mathbf{C} \to \mathbf{PSh}(\mathbf{C})$, contravariant in the first slot through F and covariant in the second through $\mathbf{y}$; its coend is computed in $\mathbf{PSh}(\mathbf{C})$, where colimits are formed objectwise (definition 63.3.1). It suffices to produce, for each presheaf G, a bijection

$$\mathbf{PSh}(\mathbf{C})\Big(\int^{c} Fc \cdot \mathbf{y}(c),\, G\Big) \;\cong\; \mathbf{PSh}(\mathbf{C})(F, G)$$

natural in G: two objects of $\mathbf{PSh}(\mathbf{C})$ whose covariant hom-functors are naturally isomorphic are themselves isomorphic, this being the Yoneda lemma (theorem 62.2.1) applied in the opposite category $\mathbf{PSh}(\mathbf{C})^{\mathrm{op}}$, where the covariant hom-functors become the representables.

Step 1: Unwind the left-hand side to a wedge. By the universal property of the coend, a map $\int^c Fc \cdot \mathbf{y}(c) \to G$ is a cowedge, a dinatural family of maps $Fc \cdot \mathbf{y}(c) \to G$. A map out of a copower $Fc \cdot \mathbf{y}(c) = \coprod_{x \in Fc} \mathbf{y}(c)$ is a choice, for each $x \in Fc$, of a map $\mathbf{y}(c) \to G$ in $\mathbf{PSh}(\mathbf{C})$. Thus

$$\mathbf{PSh}(\mathbf{C})\big(Fc \cdot \mathbf{y}(c),\, G\big) \;\cong\; \prod_{x \in Fc} \mathbf{PSh}(\mathbf{C})\big(\mathbf{y}(c), G\big) \;\cong\; \mathbf{Set}\big(Fc,\; \mathbf{PSh}(\mathbf{C})(\mathbf{y}(c), G)\big)$$

Step 2: Apply Yoneda. The Yoneda lemma (theorem 62.2.1) gives a bijection $\mathbf{PSh}(\mathbf{C})(\mathbf{y}(c), G) \cong Gc$, natural in c. Substituting,

$$\mathbf{PSh}(\mathbf{C})\big(Fc \cdot \mathbf{y}(c),\, G\big) \;\cong\; \mathbf{Set}(Fc, Gc)$$

and a cowedge into G becomes a wedge from the one-point set to the functor $(c', c) \mapsto \mathbf{Set}(Fc', Gc)$, the dinaturality conditions matching under the Yoneda bijection because that bijection is natural in c.

Step 3: Recognize the end. By example 66.4.2 the wedges from a point to $(c', c) \mapsto \mathbf{Set}(Fc', Gc)$ are exactly the natural transformations $F \Rightarrow G$:

$$\int_{c} \mathbf{Set}(Fc, Gc) \;\cong\; \mathrm{Nat}(F, G) = \mathbf{PSh}(\mathbf{C})(F, G)$$

Composing the three bijections gives $\mathbf{PSh}(\mathbf{C})\big(\int^c Fc \cdot \mathbf{y}(c), G\big) \cong \mathbf{PSh}(\mathbf{C})(F, G)$, natural in G. By the Yoneda lemma applied in $\mathbf{PSh}(\mathbf{C})$, the two presheaves are isomorphic, and the isomorphism is the canonical one sending $x \in Fc$ to the pair (x, id_c) in the copower, as we sought to show.

For the final clause, the coend (66.4) is the coequalizer (66.3), hence a colimit, of a diagram of representables. So F is a colimit of representables, and since F was arbitrary the representables generate $\mathbf{PSh}(\mathbf{C})$ under colimits, which is the statement that $\mathbf{y}$ is dense, completing the proof.

The density theorem is the promised converse to the Yoneda embedding. Yoneda embeds $\mathbf{C}$ fully faithfully into $\mathbf{PSh}(\mathbf{C})$; density says the image is not lost inside a larger category but generates it, every presheaf being reachable from the representables by colimits. Together they identify $\mathbf{PSh}(\mathbf{C})$ as the *free cocompletion* of $\mathbf{C}$: freely adjoining colimits to $\mathbf{C}$ produces exactly the presheaf category, with $\mathbf{y}$ the universal inclusion. The isomorphism (66.4) shows this: a presheaf F is rebuilt from the sets Fc of its elements and the representables that receive them.

The concrete content is a formula for the elements of a presheaf and how they patch, seen most on a poset.

Example 66.4.4: Density over a Poset

Let $\mathbf{C}$ be a poset, viewed as a category with a single arrow $c \to c'$ when $c \leq c'$, and let $F\colon \mathbf{C}^{\mathrm{op}} \to \mathbf{Set}$ be a presheaf (an order-reversing assignment of sets with restriction maps $Fc' \to Fc$ for $c \leq c'$). The representable $\mathbf{y}(c) = \mathbf{C}(-, c)$ sends b to the one-point set if $b \leq c$ and to the empty set otherwise, so $\mathbf{y}(c)$ is the presheaf represented by the down-set of c. The coend (66.4) identifies, for each $x \in Fc$ and each $b \leq c$, the "germ" of x at b with the actual restriction $x|_b \in Fb$: the copower $Fc \cdot \mathbf{y}(c)$ contributes one copy of the down-set of c for every section $x \in Fc$, and the coequalizer glues the copy attached to x to the copy attached to $x|_b$ along b. The result reassembles F from its sections and their restrictions, the poset analogue of recovering a sheaf from its stalks, that is from its local data together with the compatibilities that let the pieces be glued.

The same coend calculus rewrites the pointwise formula. The colimit over the comma category $(K \downarrow d)$ in theorem 66.2.1 is a coend once the comma category is unwound, and the coend form is the one that composes with the density theorem and generalizes to the enriched setting.

Proposition 66.4.5: Coend Formula for Kan Extensions

Let $K\colon \mathbf{C} \to \mathbf{D}$ with $\mathbf{C}$ small, $F\colon \mathbf{C} \to \mathbf{E}$, and suppose the relevant (co)limits exist in $\mathbf{E}$. Then the left Kan extension is the coend

$$(\mathrm{Lan}_K F)(d) \;\cong\; \int^{c} \mathbf{D}(Kc, d) \cdot Fc \tag{66.5}$$

and the right Kan extension is the end

$$(\mathrm{Ran}_K F)(d) \;\cong\; \int_{c} Fc^{\mathbf{D}(d, Kc)} \tag{66.6}$$

where $\mathbf{D}(Kc, d) \cdot Fc$ is the copower and $Fc^{\mathbf{D}(d,Kc)}$ the power.

***Proof*:**

Fix $d \in \mathbf{D}$. By theorem 66.2.1 the value $(\mathrm{Lan}_K F)(d)$ is the colimit of the composite $(K \downarrow d) \xrightarrow{\pi} \mathbf{C} \xrightarrow{F} \mathbf{E}$, where the comma category $(K \downarrow d)$ has objects the pairs (c, g) with $g\colon Kc \to d$ and morphisms $(c, g) \to (c', g')$ the maps $h\colon c \to c'$ with $g' \circ Kh = g$. The claim is that this colimit is computed by the coequalizer (66.3) for the integrand $T(c', c) = \mathbf{D}(Kc', d) \cdot Fc$.

Step 1: Match the coproducts. The coproduct $\coprod_c T(c, c) = \coprod_c \mathbf{D}(Kc, d) \cdot Fc$ is $\coprod_c \coprod_{g\colon Kc \to d} Fc$, one copy of Fc for each pair (c, g), that is one copy of Fc for each object of $(K \downarrow d)$. This is the coproduct over the objects of $(K \downarrow d)$ of $F\pi$, the vertex coproduct in the coequalizer presentation of the colimit $\mathrm{colim}_{(K\downarrow d)} F\pi$ (definition 63.3.1).

Step 2: Match the relations. The parallel pair in (66.3) identifies, for each $h\colon c \to c'$ in $\mathbf{C}$, the summand $T(c', c) = \mathbf{D}(Kc', d) \cdot Fc$ under the two maps $T(h, c)$ and $T(c', h)$. Concretely a summand indexed by $h\colon c \to c'$ and $g'\colon Kc' \to d$ is sent, on one side, to the copy of Fc at $(c, g' \circ Kh)$ acting by the identity on Fc, and on the other to the copy of Fc' at (c', g') acting by $Fh\colon Fc \to Fc'$. This is exactly the relation imposed in the colimit of $F\pi$: a morphism

$h\colon (c, g' \circ Kh) \to (c', g')$ of $(K \downarrow d)$ identifies the image of Fc in the vertex with the image of Fc' precomposed by Fh. The two coequalizers therefore present the same quotient, giving (66.5).

Step 2 (dual): the right extension. Applying the duality principle (box 61.3.3) to the argument just given, $(\mathrm{Ran}_K F)(d)$ is the limit over $(d \downarrow K)$ of $F\pi$, presented by the equalizer (66.2) for the integrand $(c', c) \mapsto Fc^{\mathbf{D}(d, Kc')}$. The vertex product $\prod_c Fc^{\mathbf{D}(d,Kc)}$ is one copy of Fc for each map $d \to Kc$, that is one copy for each object of $(d \downarrow K)$, and the equalizer imposes the morphisms of $(d \downarrow K)$ exactly as in the left case with all arrows reversed. This gives (66.6), completing the proof.

Read against density, the coend formula (66.5) says the left Kan extension along K is what one gets by resolving F into representables and then relabeling their indices along K: the coend integrates Fc against the hom-set $\mathbf{D}(Kc, d)$, the copower weighting each Fc by the ways Kc maps to d. Taking $K = \mathbf{y}$ the Yoneda embedding and $F = \mathbf{y}$ itself, (66.5) computes $(\mathrm{Lan}_{\mathbf{y}}\, \mathbf{y})(G) \cong \int^c \mathbf{PSh}(\mathbf{C})(\mathbf{y}(c), G) \cdot \mathbf{y}(c) \cong \int^c Gc \cdot \mathbf{y}(c)$ at a presheaf G, using $\mathbf{PSh}(\mathbf{C})(\mathbf{y}(c), G) \cong Gc$; this is the density isomorphism (66.4) for G. Density is the case of the coend formula where the extension is along Yoneda. The end and coend are thus not a separate topic appended to Kan extensions but the notation in which the pointwise formula, the Yoneda lemma, and density are one computation.

67

Monoidal Categories

A *monoidal category* carries a tensor product $\otimes$, a binary operation on objects that is associative and unital up to coherent isomorphism. It is the structure behind every tensor product in mathematics, and behind a category acting on itself. This chapter defines monoidal categories and the coherence theorem that tames their associativity isomorphisms, adds the symmetry and closedness most examples carry, and identifies the monoids that live inside a monoidal category, whose instance among endofunctors is the monad of chapter 65.

67.1 Monoidal Categories and Coherence

A tensor product multiplies objects. On R-modules it is $\otimes_R$; on sets it is the cartesian product; on the endofunctors of a category it is composition. Each is associative and unital, but only up to a natural isomorphism, and those isomorphisms are themselves data that must fit together. This section isolates that data as the notion of a monoidal category, states the two axioms (pentagon and triangle) that control it, and proves the coherence theorem, which shows the axioms suffice to make every reassociation unambiguous. We write $\otimes$ for the tensor product and I for the unit object throughout.

The associativity isomorphism $(X \otimes Y) \otimes Z \cong X \otimes (Y \otimes Z)$ is called the *associator*, and the isomorphisms $I \otimes X \cong X$ and $X \otimes I \cong X$ the *left* and *right unitors*. Requiring these to be natural in their arguments is the first constraint; the pentagon and triangle axioms are the second, and they are what distinguishes a coherent choice of associativity from an arbitrary one.

Definition 67.1.1: Monoidal Category

A *monoidal category* is a category C equipped with


- a functor $\otimes\colon C \times C \to C$, the *tensor product*;
- an object I of C, the *unit object*;
- a natural isomorphism α, the *associator*, with components

$$\alpha_{X,Y,Z}\colon (X \otimes Y) \otimes Z \to X \otimes (Y \otimes Z)$$


- natural isomorphisms λ and ρ, the *left* and *right unitors*, with components

$$\lambda_X\colon I \otimes X \to X, \qquad \rho_X\colon X \otimes I \to X$$

subject to two axioms. The *pentagon axiom* requires that the diagram



commutes for all objects W, X, Y, Z, and the *triangle axiom* requires that the diagram



commutes for all objects X, Y.

The pentagon governs a fourfold tensor product. There are five ways to fully parenthesize $W \otimes X \otimes Y \otimes Z$, and the associator gives an isomorphism between adjacent parenthesizations; the pentagon says the two paths around its perimeter, from $\big((W \otimes X) \otimes Y\big) \otimes Z$ to $W \otimes \big(X \otimes (Y \otimes Z)\big)$, agree. The triangle relates the associator to the unitors, forcing the two ways of cancelling a unit factor wedged between X and Y to coincide. These two small diagrams are the entire input; the coherence theorem below shows they already force every larger diagram of associators and unitors to commute.

When the associator and unitors are not just coherent but are identity morphisms, the tensor product is strictly associative and strictly unital, and the bookkeeping vanishes.

Definition 67.1.2: Strict Monoidal Category

A monoidal category is *strict* if the associator α and the unitors λ, ρ are all identity morphisms, so that $(X \otimes Y) \otimes Z = X \otimes (Y \otimes Z)$, $I \otimes X = X$, and $X \otimes I = X$ on the nose.

In a strict monoidal category the pentagon and triangle axioms hold trivially, being equalities of identity morphisms, and one may write iterated tensor products $X_1 \otimes \cdots \otimes X_n$ without parentheses. Most monoidal categories arising from a tensor construction are not strict, since $(X \otimes Y) \otimes Z$ and $X \otimes (Y \otimes Z)$ are built by different constructions, isomorphic but not equal. The endofunctor example below is a case where strictness does hold.

The unit object is determined by the structure. It is not extra data to be pinned down by a further choice, but is fixed up to a unique compatible isomorphism, in the same way a terminal object is (definition 63.1.1).

Proposition 67.1.3: Uniqueness of the Unit Object

Let $(C, \otimes, I, \alpha, \lambda, \rho)$ be a monoidal category, and suppose I' is another object admitting isomorphisms $\lambda'_X \colon I' \otimes X \to X$ and $\rho'_X \colon X \otimes I' \to X$ natural in X and satisfying the triangle axiom with α. Then there is a unique isomorphism $u \colon I \to I'$ satisfying $u \circ \lambda_I = \lambda'_{I'} \circ (u \otimes u)$; it is the canonical comparison of the two unit structures.

The compatibility condition packages the two units into a single square: it says u intertwines the multiplication $\lambda_I \colon I \otimes I \to I$ that the unit induces on itself with the corresponding multiplication $\lambda'_{I'} \colon I' \otimes I' \to I'$ on I'. Three standard facts about the unitors drive the proof. Two are recorded once and for all in Mac Lane, *Categories for the Working Mathematician*, Chapter VII: the left and right unitors agree at the unit, $\lambda_I = \rho_I$ (and likewise $\lambda'_{I'} = \rho'_{I'}$), so the induced multiplication is unambiguous; and the two unit structures are compared by the left-unit coherence identity $\lambda'_X \circ (u \otimes \mathrm{id}_X) = \lambda_X$, a consequence of the pentagon and triangle axioms. The third is elementary: tensoring by an object whose unitors are isomorphisms is an equivalence, hence *faithful*, which lets one cancel a factor $(-) \otimes \mathrm{id}_I$ from an equation.

***Proof Key ideas*:**
Write $v = \lambda_I = \rho_I \colon I \otimes I \to I$ and $v' = \lambda'_{I'} = \rho'_{I'} \colon I' \otimes I' \to I'$ for the two induced multiplications, using $\lambda_I = \rho_I$ (and its primed analogue) cited above.

Existence. Set

$$u = \rho_{I'} \circ (\lambda'_I)^{-1} \colon I \to I' \otimes I \to I',$$

an isomorphism as a composite of isomorphisms. The compatibility square $u \circ v = v' \circ (u \otimes u)$ reduces to a single unitor identity. Indeed, write $u \otimes u = (u \otimes \mathrm{id}_{I'}) \circ (\mathrm{id}_I \otimes u)$; naturality of λ at $u \colon I \to I'$ gives $u \circ \lambda_I = \lambda_{I'} \circ (\mathrm{id}_I \otimes u)$, so $u \circ v = u \circ \lambda_I$ and $v' \circ (u \otimes u) = \lambda'_{I'} \circ (u \otimes \mathrm{id}_{I'}) \circ (\mathrm{id}_I \otimes u)$ agree if and only if, after cancelling the isomorphism $\mathrm{id}_I \otimes u$,

$$\lambda'_{I'} \circ (u \otimes \mathrm{id}_{I'}) = \lambda_{I'}$$

This is the instance at $X = I'$ of the left-unit coherence identity $\lambda'_X \circ (u \otimes \mathrm{id}_X) = \lambda_X$, which relates the two unit structures through α and holds in any monoidal category by the pentagon and triangle axioms; it is a companion to the coherence theorem (theorem 67.1.5), deferred with it to Mac Lane, Chapter VII, which is why the existence half is given in outline. Granting it, the square commutes and u is a compatible comparison.

Uniqueness. Suppose $f\colon I \to I'$ is another isomorphism with $f \circ \upsilon = \upsilon' \circ (f \otimes f)$. Both u and f are then isomorphisms $I \to I'$ of the two multiplications υ, υ', so $g = u^{-1} \circ f\colon I \to I$ is an isomorphism satisfying $g \circ \upsilon = \upsilon \circ (g \otimes g)$, an automorphism of the multiplication υ. Naturality of λ at g gives $g \circ \lambda_I = \lambda_I \circ (\mathrm{id}_I \otimes g)$, that is $g \circ \upsilon = \upsilon \circ (\mathrm{id}_I \otimes g)$; comparing with $g \circ \upsilon = \upsilon \circ (g \otimes g)$ and cancelling the isomorphism υ yields $g \otimes g = \mathrm{id}_I \otimes g$. By functoriality of $\otimes$, $g \otimes g = (g \otimes \mathrm{id}_I) \circ (\mathrm{id}_I \otimes g)$, so the equation reads $(g \otimes \mathrm{id}_I) \circ (\mathrm{id}_I \otimes g) = \mathrm{id}_I \otimes g$; precomposing with the inverse of the isomorphism $\mathrm{id}_I \otimes g$ gives $g \otimes \mathrm{id}_I = \mathrm{id}_{I \otimes I} = \mathrm{id}_I \otimes \mathrm{id}_I$, whence $g = \mathrm{id}_I$ by faithfulness of $(-) \otimes I$. Thus $f = u$, and the unit object is unique up to a unique compatible isomorphism, as we sought to show.

The proposition is the reason one speaks of *the* unit object: any two choices are canonically identified, so the ambiguity carries no content. This is the monoidal analogue of the uniqueness of a terminal object (definition 63.1.1), and it is what allows I to be treated as a fixed piece of the structure rather than a variable one.

The standing cast gives the primary examples. Each is a category already in use, now viewed as carrying a tensor product.

Example 67.1.4: Monoidal Structures on the Standing Cast
Four monoidal categories, each read against the data and axioms of definition 67.1.1.

1. *Sets under cartesian product.* The category **Set** is monoidal with $\otimes = \times$ the cartesian product (definition 63.2.3) and $I = 1$ any singleton, terminal in **Set** (definition 63.1.1). The associator $\alpha_{X,Y,Z}\colon (X \times Y) \times Z \to X \times (Y \times Z)$ sends $((x, y), z)$ to $(x, (y, z))$, and the unitors $\lambda_X\colon 1 \times X \to X$, $\rho_X\colon X \times 1 \to X$ delete the singleton coordinate. These are bijections, natural in their arguments, and the pentagon and triangle are the evident equalities of tuple regroupings. This is not strict: $(X \times Y) \times Z$ is a set of pairs whose first entry is a pair, not equal to $X \times (Y \times Z)$.

2. *Vector spaces under tensor product.* The category $\mathbf{Vect}_k$ of vector spaces over a field k is monoidal with $\otimes = \otimes_k$ the tensor product over k ([21, Tensor Product]) and $I = k$ the ground field as a one-dimensional space. The associator is the canonical isomorphism $(U \otimes V) \otimes W \to U \otimes (V \otimes W)$ sending $(u \otimes v) \otimes w$ to $u \otimes (v \otimes w)$, and the unitors $k \otimes V \to V$, $V \otimes k \to V$ send $c \otimes v$ and $v \otimes c$ to cv. The pentagon and triangle hold because both sides of each act identically on the generating simple tensors. Again not strict.

3. *Modules under tensor product.* The same construction gives a monoidal structure on $\mathbf{Mod}_R$ for a commutative ring R, with $\otimes = \otimes_R$ and $I = R$ ([21, Tensor Product]). The associator and unitors are the standard isomorphisms of module tensor products, and $\mathbf{Vect}_k$ is the special case $R = k$.

4. *Endofunctors under composition.* For any category C, the functor category $[C, C]$ (definition 61.5.4) of endofunctors is monoidal with $\otimes = \circ$ functor composition and $I = \mathrm{id}_C$ the identity functor. Composition of functors is associative on the nose, $(F \circ G) \circ H = F \circ (G \circ H)$, and the identity functor is a strict two-sided unit, $\mathrm{id}_C \circ F = F = F \circ \mathrm{id}_C$, so the associator and unitors are identity natural transformations. Thus $([C, C], \circ, \mathrm{id}_C)$ is a *strict* monoidal category (definition 67.1.2).

The endofunctor example is the one to keep in mind. It is where strictness appears without contrivance, composition being an operation that is equal, not just isomorphic, when reassociated, and it is the

setting in which the monad (T, η, μ) met earlier will reappear as a monoid object. The strictification argument in the coherence proof is modelled on exactly this category, replacing each object by its translation endofunctor. The first three examples, by contrast, are the reason coherence is needed at all: their associators and unitors are nontrivial isomorphisms, and without the pentagon and triangle there would be no guarantee that a long chain of reassociations returns an unambiguous answer.

More generally, any category with finite products is monoidal under $(\times, 1)$, with $\times$ the binary product (definition 63.2.3) and 1 a terminal object (definition 63.1.1) as unit; the first example is the case $C = \mathbf{Set}$. This is the *cartesian monoidal* structure, and it is available on **Grp**, **Top**, **Cat**, and every other member of the standing cast with finite products.

The pentagon and triangle are two small diagrams. It is not obvious that they suffice: a diagram built from a dozen associators and unitors offers many paths between its corners, and nothing so far forces those paths to agree. Mac Lane's coherence theorem is the guarantee that they do. It has two equivalent formulations, one internal (every formal diagram commutes) and one structural (every monoidal category is equivalent to a strict one), and the second is the route to proving the first.

Theorem 67.1.5: Mac Lane's Coherence Theorem

Let C be a monoidal category. Then:

1. *Coherence.* Every diagram in C whose edges are built by tensoring identities, associators $\alpha^{\pm 1}$, and unitors $\lambda^{\pm 1}$, $\rho^{\pm 1}$ commutes. Any two morphisms between the same pair of iterated tensor products built from these constituents are equal.
2. *Strictification.* There is a strict monoidal category C^{st} and a monoidal equivalence $C \simeq C^{\mathrm{st}}$.

The full proof of part (1) is a combinatorial argument about a word problem: one shows that any two formal composites of associators and unitors with the same source and target are provably equal from the pentagon and triangle, and the complete verification is long. It is given in Mac Lane, *Categories for the Working Mathematician*, Chapter VII. What follows establishes part (2) in full and shows how it yields part (1), which is the conceptual content.

***Proof Key ideas*:**
The strictification construction is given in full; the word-problem proof of part (1) from part (2) is sketched, with the complete combinatorial argument cited to Mac Lane, Chapter VII, as noted above.

Step 1: The strict category of lists. Let C^{st} be the category whose objects are finite lists $\underline{X} = (X_1, \dots, X_n)$ of objects of C (including the empty list, of length 0), and whose morphisms

$$C^{\mathrm{st}}(\underline{X}, \underline{Y}) = \mathrm{Hom}_C\big(\overline{\underline{X}}, \overline{\underline{Y}}\big)$$

are the C-morphisms between the tensorings $\overline{\underline{X}} = ((X_1 \otimes X_2) \otimes \cdots) \otimes X_n$ associated to the left in a fixed order (the empty list tensoring to I), with composition and identities taken in C. Concatenation of lists, $\underline{X} \otimes \underline{Y} = (X_1, \dots, X_n, Y_1, \dots, Y_m)$, is an associative operation on objects with strict unit the empty list, and on morphisms it is defined by transporting the tensor of the underlying C-morphisms across the associators that compare $\overline{\underline{X} \otimes \underline{Y}}$ with $\overline{\underline{X}} \otimes \overline{\underline{Y}}$; the pentagon axiom makes this transport well-defined and functorial. Thus C^{st} is a *strict* monoidal category (definition 67.1.2): concatenation is associative and unital on the nose. This is the list model of the endofunctor picture, where a length-one list (X) plays the role of the translation $X \otimes -$

and concatenation the role of composition, but built so that the bookkeeping isomorphisms live inside the definition of the tensor rather than obstructing strictness.

Step 2: L is a monoidal equivalence. Define $L\colon C \to C^{\mathrm{st}}$ on objects by $L(\underline{X}) = (X)$, the length-one list, and on morphisms by $L(f) = f$, viewing $f\colon X \to Y$ as a morphism $\overline{(X)} = X \to Y = \overline{(Y)}$ in C. Because $C^{\mathrm{st}}((X),(Y)) = \mathrm{Hom}_C(X,Y)$ by definition, L is *fully faithful* with no further argument, its action on each hom-set being the identity map of $\mathrm{Hom}_C(X,Y)$. It is essentially surjective: every list $\underline{X}$ is isomorphic in C^{st} to the length-one list $(\overline{X})$, the isomorphism being the identity of $\overline{X}$ regarded as a morphism $\underline{X} \to (\overline{X})$. A functor that is fully faithful and essentially surjective is an equivalence (proposition 61.5.6), so L is an equivalence of categories. Finally L is *strong monoidal*: the structure isomorphism $L(\underline{X}) \otimes L(\underline{Y}) = (X,Y) \to (X \otimes Y) = L(X \otimes Y)$ is the identity of $X \otimes Y$ regarded as a morphism $\overline{(X,Y)} = X \otimes Y \to X \otimes Y$, and the unit comparison $I_{C^{\mathrm{st}}} = () \to (I)$ is id_I, since both $\overline{()}$ and $\overline{(I)}$ equal I; the pentagon and triangle axioms of C are exactly the coherence identities these comparisons must satisfy. Hence L is a monoidal equivalence $C \simeq C^{\mathrm{st}}$ with strict target, proving part (2).

Step 3: Coherence from strictification. Given a formal diagram in C built from associators and unitors, apply the equivalence $L\colon C \simeq C^{\mathrm{st}}$. Since L is *strong* (not strict) monoidal, it does not send an associator to an identity; rather, the strong-monoidal coherence axioms and the strictness of the target force $L(\alpha_{X,Y,Z})$ to equal a fixed composite of the structure isomorphisms $\varphi_{A,B}\colon L(A)\otimes L(B) \cong L(A\otimes B)$ of Step 2 (each of which, in the list model, is an identity morphism of C regarded across a change of tensoring), and likewise $L(\lambda_X)$, $L(\rho_X)$ to fixed composites of the $\varphi_{A,B}$ and the unit comparison. Because concatenation in C^{st} is strictly associative and unital, these image composites depend only on the source and target parenthesizations, not on the path taken: any two formal composites of associators and unitors sharing a source and target map under L to the *same* morphism of C^{st}. As L is faithful, they are already equal in C, so the formal diagram commutes. The content that Step 3 defers is exactly the path-independence just used: that the structure isomorphisms assemble into a well-defined map depending only on the endpoints is the word-problem statement, that the free monoidal category on the objects involved has at most one morphism between any two parenthesizations. This is the combinatorial argument deferred to Mac Lane, Chapter VII; granting it, every formal diagram of associators and unitors commutes, completing the proof of part (1).

Coherence permits a controlled sloppiness. Because every formal diagram of associators and unitors commutes, one may drop parentheses from iterated tensor products and suppress the unit isomorphisms entirely, writing $X \otimes Y \otimes Z$ and $I \otimes X = X$ as though the category were strict. No ambiguity results: whichever way a suppressed reassociation is reinstated, part (1) guarantees the same morphism. In practice one works in a monoidal category as if it were strict, invoking coherence to justify the omitted brackets, and the strictification of part (2) is what makes this rigorous rather than convenient. Every monoidal category met later in this chapter is handled this way.

67.2 Braided and Symmetric Monoidal Categories

A monoidal structure (definition 67.1.1) relates $X \otimes Y$ and $Y \otimes X$ by nothing at all; in $(\mathbf{Vect}_k, \otimes, k)$ they are visibly isomorphic by the swap $x \otimes y \mapsto y \otimes x$, coherently with the tensor. This section isolates that extra datum. A *braiding* is a natural isomorphism $\beta_{X,Y}\colon X \otimes Y \to Y \otimes X$ compatible with the associator, and a braiding is *symmetric* when swapping twice returns to the start. The compatibility is governed not by one axiom but by two hexagons, one for each way of moving a factor

past a tensor product.


The compatibility a braiding must satisfy is forced by coherence. Given three objects, $X \otimes (Y \otimes Z)$ can be rewritten as $(Y \otimes Z) \otimes X$ in two ways: apply the braiding to the whole factor $Y \otimes Z$ at once, or slide X past Y and then past Z one factor at a time, reassociating as needed. A braiding is required to make these two routes agree. Each route is a hexagon of associators and braidings, and there are two of them because X may be moved to the right (past $Y \otimes Z$) or an object may be moved to the left (past $X \otimes Y$); the second hexagon is the analogue of the first for the reverse braiding.

Definition 67.2.1: Braided Monoidal Category


A *braided monoidal category* is a monoidal category $(\mathbf{C}, \otimes, I, \alpha, \lambda, \rho)$ (definition 67.1.1) equipped with a natural isomorphism

$$\beta_{X,Y} \colon X \otimes Y \to Y \otimes X$$

called the *braiding*, natural in X and Y (definition 61.5.2), such that the two hexagon diagrams commute for all objects X, Y, Z. The first hexagon



expresses the compatibility of β with α when the object X is braided past the tensor product $Y \otimes Z$. The second hexagon



expresses the same compatibility when Z is braided past $X \otimes Y$.

Naturality of β means that for morphisms $f \colon X \to X'$ and $g \colon Y \to Y'$, the square

$$\begin{array}{ccc} X \otimes Y & \xrightarrow{\beta_{X,Y}} & Y \otimes X \\ {\scriptstyle f \otimes g}\downarrow & & \downarrow{\scriptstyle g \otimes f} \\ X' \otimes Y' & \xrightarrow[\beta_{X',Y'}]{} & Y' \otimes X' \end{array}$$

commutes: braiding and then acting by $g \otimes f$ agrees with acting by $f \otimes g$ and then braiding. The two hexagons are the coherence conditions for the braiding against the associator; together with Mac

Lane's coherence theorem (theorem 67.1.5) for the underlying monoidal structure, they guarantee that every diagram built from associators, unitors, and braidings that one might expect to commute does commute, provided its two sides braid the factors into the same permutation by isotopic routes. The proviso is the point: unlike the associator and unitors, the braiding is not forced to be its own inverse, so the order in which factors are braided can matter.

In a strict monoidal category (definition 67.1.2) the associators are identities and each hexagon collapses to a triangle. The first becomes

$$\beta_{X,Y\otimes Z} = (\mathrm{id}_Y \otimes \beta_{X,Z}) \circ (\beta_{X,Y} \otimes \mathrm{id}_Z)$$

and the second becomes

$$\beta_{X\otimes Y,Z} = (\beta_{X,Z} \otimes \mathrm{id}_Y) \circ (\mathrm{id}_X \otimes \beta_{Y,Z})$$

so that a braiding past a tensor product is determined by braiding past each factor in turn. These are the relations one draws as strands crossing: $\beta_{X,Y}$ is the strand carrying X passing over the strand carrying Y, and the hexagons say that a strand passing over two others equals its passing over them one at a time.

The extra condition that makes a braiding into a symmetry is the one the swap map satisfies: undoing the crossing recovers the identity.

Definition 67.2.2: Symmetric Monoidal Category

A braided monoidal category (definition 67.2.1) is *symmetric* if its braiding satisfies

$$\beta_{Y,X} \circ \beta_{X,Y} = \mathrm{id}_{X\otimes Y}$$

for all objects X and Y. A braiding with this property is called a *symmetry*.

For a symmetry, $\beta_{Y,X} = \beta_{X,Y}^{-1}$, so the two hexagons of definition 67.2.1 become equivalent: each is obtained from the other by inverting the braidings, and symmetry identifies a braiding with its inverse. A symmetric monoidal category therefore carries a single hexagon axiom, and the strand carrying X over the strand carrying Y is indistinguishable from X under Y. The distinction between over and under crossings is what a general braiding retains and a symmetry discards.

The condition $\beta_{Y,X}\beta_{X,Y} = \mathrm{id}$ is the categorical form of a familiar identity: it says the swap is an involution. Symmetry is the monoidal counterpart of commutativity. Just as a commutative operation lets a product $a_1 a_2 \cdots a_n$ be formed without regard to the order of its factors, a symmetric braiding lets a tensor $X_1 \otimes \cdots \otimes X_n$ be reindexed by any permutation, with any two reindexings related by a canonical isomorphism independent of how the permutation is factored into transpositions. This is coherence for the symmetric group: the symmetric group S_n acts on the n-fold tensor, and the action is well-defined precisely because $\beta_{Y,X}\beta_{X,Y} = \mathrm{id}$ makes a transposition square to the identity. In a braided category that is not symmetric the braid group B_n acts in place of S_n, and B_n is infinite, so the order of braiding is remembered.

Example 67.2.3: The Standing Cast as Symmetric Monoidal Categories

The commutative examples of example 67.1.4, $(\mathbf{Vect}_k, \otimes, k)$ and $(\mathbf{Set}, \times, 1)$, each carry a symmetry; the third example there, the endofunctor category $([\mathbf{C}, \mathbf{C}], \circ, \mathrm{id})$, is deliberately excluded, since functor composition is non-commutative ($F \circ G$ is not naturally isomorphic to $G \circ F$ in general) and so admits no braiding, a point that returns when a monad is identified as a monoid object in that category. The vector-space case extends to modules over any commutative ring.

1. In $(\mathbf{Vect}_k, \otimes, k)$ the braiding is the swap

$$\beta_{V,W} : V \otimes W \to W \otimes V, \qquad v \otimes w \mapsto w \otimes v$$

extended k-bilinearly. This is a well-defined linear isomorphism because $(v, w) \mapsto w \otimes v$ is k-bilinear, and its inverse is $\beta_{W,V}$. Applying it twice returns $v \otimes w \mapsto w \otimes v \mapsto v \otimes w$, so $\beta_{W,V}\beta_{V,W} = \mathrm{id}_{V\otimes W}$ and the structure is symmetric. The hexagon axioms hold because both routes send $u \otimes v \otimes w$ (with the associators identifying the two bracketings) to the same reordered pure tensor.

2. For a commutative ring R, the category $(\mathbf{Mod}_R, \otimes_R, R)$ is symmetric with the same swap $m \otimes n \mapsto n \otimes m$. Well-definedness uses commutativity of R: for $r \in R$ the assignment must respect $rm \otimes n = m \otimes rn$, and the target $n \otimes rm = rn \otimes m$ agrees only because r is central, which it is. The tensor product itself is the tensor product of R-modules cited from [21, Tensor Product]; here it is repackaged as a symmetric monoidal structure. The case $R = k$ a field recovers the previous item.

3. In $(\mathbf{Set}, \times, 1)$ the braiding is the swap of ordered pairs

$$\beta_{A,B} : A \times B \to B \times A, \qquad (a, b) \mapsto (b, a)$$

which is its own inverse: applying it twice returns $(a, b) \mapsto (b, a) \mapsto (a, b)$, so it is a symmetry. Every category with finite products carries this symmetry on its cartesian monoidal structure $(\mathbf{C}, \times, 1)$ (the structure of definition 63.2.3): the braiding $\beta_{X,Y} : X \times Y \to Y \times X$ is the unique map whose projections to Y and X are the projections of $X \times Y$ in the other order, and its square is the identity because both maps have the same projections. A cartesian monoidal category is thus symmetric with no further choice.

Braidings that are not symmetric exist. The category of finite-dimensional representations of a quantum group $U_q(\mathfrak{g})$ carries a braiding, built from the R-matrix solving the Yang-Baxter equation, for which $\beta_{Y,X}\beta_{X,Y} \neq \mathrm{id}$: braiding past twice is a nontrivial automorphism, and the braid group B_n acts faithfully on tensor powers. This is the source of the quantum knot invariants, the Jones polynomial among them, where an over-crossing and an under-crossing of strands must be assigned different operators precisely because β and β^{-1} differ. These braided-not-symmetric categories are the natural home of that theory and are developed in the literature on quantum groups; the present book stays with the symmetric case, where the standing cast lives.

The three examples share a mechanism. In each, the braiding is a swap of coordinates, its square is the identity, and the hexagons hold because reassociating and swapping commute on pure tensors or pairs. The symmetry is not an added structure to be checked case by case so much as a reflection of the fact that the underlying product, of vector spaces, of modules, of sets, is commutative up to canonical isomorphism. Symmetric monoidal categories are the ambient setting in which the algebra of tensor products behaves like the algebra of a commutative operation.

67.3 Closed Monoidal Categories

The tensor product $\otimes$ combines two objects into one. A closed structure gives the inverse move: an object $[X, Y]$ inside the category whose maps out of any A are exactly the maps $A \otimes X \to Y$. This section makes that require precise as an adjunction (definition 64.1.1), identifies the two canonical

maps it carries, and reads off the closure of the two examples the adjunction chapter already met in another guise.

The condition to impose is that tensoring with a fixed object have a right adjoint. Naming that right adjoint $[X, -]$ turns the informal "object of maps $X \to Y$" into a functor internal to the category.

Definition 67.3.1: Closed Monoidal Category

A monoidal category $(\mathbf{C}, \otimes, I)$ (definition 67.1.1) is *closed* if for every object X the functor

$$- \otimes X \colon \mathbf{C} \to \mathbf{C}$$

has a right adjoint (definition 64.1.1), written $[X, -] \colon \mathbf{C} \to \mathbf{C}$ and called the *internal hom*. Explicitly, for each X there is a bijection

$$\mathbf{C}(A \otimes X, Y) \;\cong\; \mathbf{C}(A, [X, Y]) \tag{67.1}$$

natural in A and in Y. The object $[X, Y]$ is the *internal hom* from X to Y.

The word "closed" names the fact that the hom-set $\mathbf{C}(X, Y)$, an object of **Set** external to $\mathbf{C}$, has been promoted to an object $[X, Y]$ of $\mathbf{C}$ itself: the category is closed under forming its own hom-objects. (67.1) is the defining feature. It says a map from A into the internal hom $[X, Y]$ is the same datum as a map from $A \otimes X$ to Y, so $[X, Y]$ represents the functor $A \mapsto \mathbf{C}(A \otimes X, Y)$. The external hom is recovered by taking $A = I$: since $I \otimes X \cong X$ through the left unitor, (67.1) gives $\mathbf{C}(X, Y) \cong \mathbf{C}(I, [X, Y])$, so the ordinary maps $X \to Y$ are the "points" $I \to [X, Y]$ of the internal hom.

The definition asks $- \otimes X$ to have a right adjoint, tensoring on the right. In a symmetric monoidal category (definition 67.2.2) the braiding gives a natural isomorphism $A \otimes X \cong X \otimes A$, so a right adjoint to $- \otimes X$ is at once a right adjoint to $X \otimes -$: left and right closedness coincide, and one speaks simply of a closed symmetric monoidal category.[1]

The adjunction packaged by (67.1) carries a unit and a counit (definition 64.1.3). Named and unwound in the present notation, they are the two structural maps a closed category always provides: an evaluation and a currying map.

[1] Without symmetry the two conditions may differ, and a category can be right closed without being left closed. Every example below is symmetric, so the distinction does not arise.

Theorem 67.3.2: The Tensor-Hom Adjunction

Let $(\mathbf{C}, \otimes, I)$ be a closed monoidal category (definition 67.3.1), and fix an object X. The adjunction $- \otimes X \dashv [X, -]$ has:

1. counit the *evaluation* morphism, natural in Y,
$$\mathrm{ev}_{X,Y} \colon [X, Y] \otimes X \to Y$$
the transpose of $\mathrm{id}_{[X,Y]}$;
2. unit the *coevaluation* (or *currying*) morphism, natural in A,
$$\mathrm{coev}_{A,X} \colon A \to [X, A \otimes X]$$
the transpose of $\mathrm{id}_{A \otimes X}$.

The bijection (67.1) sends $f \colon A \otimes X \to Y$ to $[X, f] \circ \mathrm{coev}_{A,X} \colon A \to [X, Y]$, and is natural in A and in Y.

***Proof*:**
By definition 67.3.1 the functors $- \otimes X$ and $[X, -]$ are adjoint, so the general theory of section 64.1 applies with $F = - \otimes X$ and $G = [X, -]$; the content of the theorem is to name the unit and counit in this setting and confirm the transpose formula.

Step 1: The counit is evaluation. By definition 64.1.3 the counit of $- \otimes X \dashv [X, -]$ has component at Y the transpose of $\mathrm{id}_{[X,Y]}$ under the inverse of (67.1). Setting $A = [X, Y]$, that bijection reads $\mathbf{C}([X, Y] \otimes X, Y) \cong \mathbf{C}([X, Y], [X, Y])$, and the transpose of $\mathrm{id}_{[X,Y]}$ is a morphism
$$\mathrm{ev}_{X,Y} \colon [X, Y] \otimes X \to Y$$
which is the counit, hence natural in Y. It evaluates the internal hom: for $\mathbf{C} = \mathbf{Set}$ with $[X, Y] = \mathbf{Set}(X, Y)$, ev is the map $(g, x) \mapsto g(x)$.

Step 2: The unit is coevaluation. Dually, the unit has component at A the transpose of $\mathrm{id}_{A \otimes X}$ under (67.1) with $Y = A \otimes X$: the bijection $\mathbf{C}(A \otimes X, A \otimes X) \cong \mathbf{C}(A, [X, A \otimes X])$ sends $\mathrm{id}_{A \otimes X}$ to a morphism
$$\mathrm{coev}_{A,X} \colon A \to [X, A \otimes X]$$
the unit, natural in A. In $\mathbf{Set}$ it sends a to the function $x \mapsto (a, x)$, the map that curries the second coordinate.

Step 3: The transpose formula. Proposition 64.1.4 computes the transpose of a morphism through the unit and counit: for $F \dashv G$ with unit η, the transpose of $f \colon FA \to Y$ is $Gf \circ \eta_A$. With $F = - \otimes X$, $G = [X, -]$, $\eta_A = \mathrm{coev}_{A,X}$, and $Gf = [X, f]$, the transpose of $f \colon A \otimes X \to Y$ is
$$A \xrightarrow{\mathrm{coev}_{A,X}} [X, A \otimes X] \xrightarrow{[X,f]} [X, Y] \tag{67.2}$$
which is the asserted formula: curry the identity, then apply the internal hom to f.

Step 4: Naturality. Naturality of (67.1) in A and Y is naturality of the adjunction isomorphism $\Phi \colon \mathbf{C}(F-, -) \cong \mathbf{C}(-, G-)$ of definition 64.1.1, which holds by the definition of an adjunction. Concretely, for $u \colon A' \to A$ the square relating $\Phi_{A,Y}$ and $\Phi_{A',Y}$ commutes because (67.2) is built

from the natural transformation coev and the functor $[X, -]$; the Y-variable is dual, using ev. Thus the bijection is natural in both variables, completing the proof.

The evaluation and coevaluation maps are the internal forms of two operations on ordinary functions. Evaluation $[X,Y] \otimes X \to Y$ applies a map to an argument; coevaluation $A \to [X, A \otimes X]$ holds an element of A and waits for an argument in X, producing the pair. The triangle identities of theorem 64.1.5 record that currying and then evaluating returns the original map, which is the content of (67.2) run forward and back. This is the tensor-hom adjunction of example 64.2.2, now read as structure carried by a single category rather than a bijection between two external hom-sets: the module Hom-tensor identity $\mathrm{Hom}_R(A \otimes_R X, Y) \cong \mathrm{Hom}_R(A, \mathrm{Hom}_R(X,Y))$ and the currying isomorphism $\mathbf{Set}(A \times X, Y) \cong \mathbf{Set}(A, Y^X)$ are exactly (67.1) for $\mathbf{Mod}_R$ and for $\mathbf{Set}$. What the adjunction chapter presented as two adjoint functors, the closed structure presents as the category's ability to internalize its own hom.

When the monoidal structure is the cartesian one built from finite products (definition 63.2.3), closedness has a classical name and the internal hom is the exponential object.

Definition 67.3.3: Cartesian Closed Category

A category $\mathbf{C}$ with finite products is *cartesian closed* if its cartesian monoidal structure $(\mathbf{C}, \times, 1)$ is closed (definition 67.3.1): for every object X the functor $- \times X$ has a right adjoint $(-)^X \colon \mathbf{C} \to \mathbf{C}$, the *exponential*. The object $Y^X = [X,Y]$ is the *exponential object*, and the adjunction reads

$$\mathbf{C}(A \times X, Y) \;\cong\; \mathbf{C}(A, Y^X) \tag{67.3}$$

natural in A and Y.

Cartesian closedness is the special case where the tensor is the product and the unit is the terminal object 1. The bijection (67.3) is currying in its familiar form: a map of two variables $A \times X \to Y$ is the same as a map $A \to Y^X$ into the object of maps $X \to Y$. The evaluation counit $Y^X \times X \to Y$ applies a function to an argument, and taking $A = 1$ recovers the global elements of Y^X as the maps $X \to Y$, so the exponential is a genuine internal object of functions.

Example 67.3.4: Set and Vect as Closed Categories

1. **Set** *is cartesian closed.* The cartesian monoidal structure is $(\mathbf{Set}, \times, 1)$ with 1 a one-point set. For sets X and Y the exponential is the set of all functions,

$$Y^X = \mathbf{Set}(X, Y)$$

and currying is the bijection

$$\mathbf{Set}(A \times X, Y) \;\cong\; \mathbf{Set}(A, Y^X)$$

sending $f \colon A \times X \to Y$ to $a \mapsto (x \mapsto f(a,x))$. This is a bijection because a function of two arguments is determined by, and determines, its curried form; it is natural in A and Y because currying commutes with precomposition on A and postcomposition on Y. Thus $- \times X \dashv (-)^X$, and the evaluation counit $Y^X \times X \to Y$ is $(g,x) \mapsto g(x)$.

2. $\mathbf{Vect}_k$ *is closed monoidal, not cartesian.* The relevant monoidal structure on vector spaces over k is $(\mathbf{Vect}_k, \otimes_k, k)$, the tensor product with unit the ground field k, not the cartesian

product. It is closed with internal hom the space of linear maps,

$$[X, Y] = \mathrm{Hom}_k(X, Y)$$

itself a k-vector space. The bijection

$$\mathrm{Hom}_k(A \otimes_k X, Y) \;\cong\; \mathrm{Hom}_k(A, \mathrm{Hom}_k(X, Y))$$

is the tensor-hom adjunction over k (example 64.2.2): a bilinear map $A \times X \to Y$ corresponds to a linear map $A \otimes_k X \to Y$ and, curried, to a linear map $A \to \mathrm{Hom}_k(X, Y)$. The evaluation counit $\mathrm{Hom}_k(X, Y) \otimes_k X \to Y$ is $g \otimes x \mapsto g(x)$. The cartesian product $X \times Y$ (the direct sum, since finite products and coproducts coincide here) does *not* make $\mathbf{Vect}_k$ cartesian closed: the exponential would need $\mathbf{Vect}_k(A \times X, Y) \cong \mathbf{Vect}_k(A, Y^X)$, but the left side is not additive in A while the representable right side is. Since $A \times X = A \oplus X$, the left side is $\mathbf{Vect}_k(A \oplus X, Y) \cong \mathbf{Vect}_k(A, Y) \times \mathbf{Vect}_k(X, Y)$, which carries the constant summand $\mathbf{Vect}_k(X, Y)$: at $A = 0$ it returns $\mathbf{Vect}_k(X, Y)$, not a one-point set, so with $X = Y = k$ it fails to send the zero space to a terminal set. A representable functor $\mathbf{Vect}_k(-, Y^X)$ does send 0 to a point, so the two cannot be naturally isomorphic and no cartesian exponential exists. Closedness here is a feature of $\otimes_k$, not of $\times$.

The two examples separate the cartesian case from the general one. In **Set** the tensor is the product, so the internal hom is the exponential and the category is cartesian closed. In $\mathbf{Vect}_k$ the closure lives on the tensor product, and the cartesian product carries no matching exponential; the category is closed monoidal but not cartesian closed. The pattern recurs: the tensor-hom adjunction of example 64.2.2 for $\mathbf{Mod}_R$ makes each module category closed monoidal under $\otimes_R$, while a topos such as **Set** or a presheaf category is cartesian closed under $\times$.

Cartesian closed categories are the categorical semantics of the typed lambda calculus: types are objects, terms are morphisms, the product $\times$ interprets pairing, the exponential Y^X interprets the function type $X \to Y$, and the evaluation and currying maps interpret function application and lambda abstraction, with the adjunction (67.3) the statement that a function of two arguments and its curried form are interchangeable.[2]

67.4 Monoids, Comonoids, and Duality

The definition of a monoid transcribes verbatim into any monoidal category once the product is a functor $\otimes$ rather than a set-theoretic multiplication, and the reward is that the same three axioms name at once monoids, rings, algebras, and, in the endofunctor category of example 67.1.4, monads. This section makes that transcription, dualizes it to comonoids, and closes with a taste of the finiteness condition, dualizability, that lets an object have a linear dual.

Fix a monoidal category $(\mathbf{C}, \otimes, I)$ with associator α and unitors λ, ρ (definition 67.1.1). A monoid in **Set** is a set M together with a multiplication $M \times M \to M$ and a chosen unit element, which is the same as a map $1 \to M$ from the terminal set. Replacing $\times$ by $\otimes$ and the terminal set by the monoidal unit I gives the general definition.

[2]This correspondence, that cartesian closed categories model simply typed lambda calculus, is due to Lambek; a standard reference is Lambek and Scott, *Introduction to Higher Order Categorical Logic*.

Definition 67.4.1: Monoid Object

A *monoid object* in a monoidal category $(\mathbf{C}, \otimes, I)$ is an object M of $\mathbf{C}$ together with two morphisms

$$\mu \colon M \otimes M \to M \qquad \text{and} \qquad \eta \colon I \to M$$

the *multiplication* and the *unit*, such that the associativity diagram

$$\begin{array}{ccccc} (M \otimes M) \otimes M & \xrightarrow{\alpha_{M,M,M}} & M \otimes (M \otimes M) & \xrightarrow{\mathrm{id}_M \otimes \mu} & M \otimes M \\ \downarrow{\scriptstyle \mu \otimes \mathrm{id}_M} & & & & \downarrow{\scriptstyle \mu} \\ M \otimes M & & \xrightarrow[\mu]{\qquad\qquad\qquad\qquad} & & M \end{array}$$

and the two unit diagrams

$$\begin{array}{ccccc} I \otimes M & \xrightarrow{\eta \otimes \mathrm{id}_M} & M \otimes M & \xleftarrow{\mathrm{id}_M \otimes \eta} & M \otimes I \\ & {\scriptstyle \lambda_M} \searrow & \downarrow{\scriptstyle \mu} & \swarrow {\scriptstyle \rho_M} & \\ & & M & & \end{array}$$

commute.

The associativity square says the two ways of multiplying a triple $M \otimes M \otimes M$ agree once the parenthesization is corrected by the associator, and the two triangles say that inserting the unit on either side and multiplying is the same as forgetting the unit factor via λ or ρ. When $\mathbf{C}$ is strict the associator and unitors are identities and the diagrams reduce to the familiar equations $\mu(\mu \otimes \mathrm{id}) = \mu(\mathrm{id} \otimes \mu)$, $\mu(\eta \otimes \mathrm{id}) = \mathrm{id} = \mu(\mathrm{id} \otimes \eta)$; theorem 67.1.5 guarantees no generality is lost by picturing the strict case. A morphism of monoid objects $(M, \mu, \eta) \to (M', \mu', \eta')$ is a map $f \colon M \to M'$ with $f\mu = \mu'(f \otimes f)$ and $f\eta = \eta'$; monoid objects and their morphisms form a category $\mathrm{Mon}(\mathbf{C})$.

Reversing every arrow gives the dual notion. Rather than a multiplication that fuses two copies of M into one, a comonoid carries a comultiplication that splits one copy into two, and in place of a unit picking out an element it has a counit that measures an element against the ground object I.

Definition 67.4.2: Comonoid Object

A *comonoid object* in $(\mathbf{C}, \otimes, I)$ is a monoid object in the opposite monoidal category $(\mathbf{C}^{\mathrm{op}}, \otimes, I)$: an object C with a *comultiplication* $\delta\colon C \to C \otimes C$ and a *counit* $\varepsilon\colon C \to I$ making the coassociativity diagram

$$\begin{array}{ccc} C & \xrightarrow{\ \delta\ } & C \otimes C \\ {\scriptstyle\delta}\downarrow & & \downarrow{\scriptstyle \mathrm{id}_C \otimes \delta} \\ C \otimes C & \xrightarrow[\ \delta \otimes \mathrm{id}_C\ ]{} & C \otimes C \otimes C \end{array}$$

and the two counit diagrams

$$\begin{array}{ccccc} & & C & & \\ & {\scriptstyle\lambda_C^{-1}}\swarrow & \downarrow{\scriptstyle\delta} & \searrow{\scriptstyle\rho_C^{-1}} & \\ I \otimes C & \xleftarrow[\ \varepsilon \otimes \mathrm{id}_C\ ]{} & C \otimes C & \xrightarrow[\ \mathrm{id}_C \otimes \varepsilon\ ]{} & C \otimes I \end{array}$$

commute (associators suppressed in the strict picture).

By the duality principle (box 61.3.3), every statement about monoid objects has a mirror statement about comonoid objects, obtained by reversing the arrows in $\mathbf{C}$; there is nothing to prove separately. Comonoids are the less familiar of the pair only because the everyday examples, sets and modules, carry no interesting comultiplication under $\times$ or $\otimes$: the diagonal $C \to C \otimes C$ is forced. They become substantial in categories where $\otimes$ is genuinely non-cartesian, where a comonoid is the categorical form of a coalgebra, the structure dual to an algebra that organizes, for instance, the representation theory of a group through its group algebra.

The point of the definition is that a single set of axioms, read in different monoidal categories, returns structures that look unrelated on their face. The following example collects the payoff.

Example 67.4.3: Monoids, Rings, Algebras, and Monads

A monoid object is a monoid, a ring, an algebra, or a monad according to where it is read.

1. *In* $(\mathbf{Set}, \times, 1)$. A monoid object is exactly a monoid in the ordinary sense. The map $\mu\colon M \times M \to M$ is a binary operation, $\eta\colon 1 \to M$ picks out an element $e = \eta(*)$, the associativity square is $\mu(\mu(a,b),c) = \mu(a,\mu(b,c))$, and the unit triangles say $ea = a = ae$. The cartesian structure $(\mathbf{C}, \times, 1)$ of definition 63.2.3 is what makes this the definition of a monoid; the same reading in **Top** or **Grp** gives topological monoids and monoids internal to **Grp**.

2. *In* $(\mathbf{Ab}, \otimes_{\mathbb{Z}}, \mathbb{Z})$. A monoid object is exactly a ring. An abelian group R with a $\mathbb{Z}$-bilinear multiplication $\mu\colon R \otimes_{\mathbb{Z}} R \to R$ and a unit $\eta\colon \mathbb{Z} \to R$, $\eta(1) = 1_R$, is precisely a ring: bilinearity is built into the tensor product, associativity and unitality are the two diagrams. Replacing $\mathbb{Z}$ by a commutative ring k and **Ab** by $(\mathbf{Mod}_k, \otimes_k, k)$ gives a k-algebra (the multiplication and unit of k-modules cited to [21, Tensor Product, Universal Property Of Tensor Product (Over Commutative Rings)]). Thus rings and algebras are monoid objects, one monoidal category up from monoids.

3. *In* $([\mathbf{C}, \mathbf{C}], \circ, \mathrm{id})$. A monoid object in the strict monoidal category of endofunctors of $\mathbf{C}$, with $\otimes$ the composition of functors and unit object the identity functor (example 67.1.4,

> definition 61.5.4), is exactly a monad on $\mathbf{C}$. An object of $[\mathbf{C},\mathbf{C}]$ is an endofunctor T; the multiplication $\mu\colon T\circ T\to T$ and unit $\eta\colon \mathrm{id}\to T$ are natural transformations; and the associativity and unit diagrams of definition 67.4.1 are, symbol for symbol, the associativity and unit laws of a monad (T,η,μ) from definition 65.1.1. This is the identity
>
> *a monad is a monoid in the category of endofunctors*
>
> stated as the theorem it is: the two definitions are not analogous, they are the same definition read in two monoidal categories.

The third reading is the reason the notion of monoid object is worth isolating. Chapter 5 built monads by hand, checking the associativity and unit squares of natural transformations directly; definition 67.4.1 now shows those squares were never special to endofunctors. Any construction valid for monoids in an arbitrary monoidal category applies at once to monads: the category of monoid objects, the free monoid on an object, morphisms of monoids. A monad morphism, for instance, is nothing but a morphism of monoid objects in $[\mathbf{C},\mathbf{C}]$.

A monoid in $(\mathbf{Set},\times,1)$ becomes a group exactly when every element has an inverse, and the inverse is itself a morphism $i\colon G\to G$ subject to a diagram. This upgrades the monoid-object definition in a cartesian monoidal category to a group object, the notion that lets "group" be interpreted inside geometry.

Example 67.4.4: Group Objects

Let $(\mathbf{C},\times,1)$ be a category with finite products (definition 63.2.3), regarded as a cartesian monoidal category. A *group object* is a monoid object (G,μ,η) together with an *inverse* morphism $i\colon G\to G$ such that

$$\begin{array}{ccccc} G & \xrightarrow{(\mathrm{id}_G,i)} & G\times G & \xleftarrow{(i,\mathrm{id}_G)} & G \\ {\scriptstyle e}\downarrow & & \downarrow{\scriptstyle \mu} & & \downarrow{\scriptstyle e} \\ 1 & \xrightarrow[\eta]{} & G & \xleftarrow[\eta]{} & 1 \end{array}$$

commutes, where $e\colon G\to 1$ is the unique map to the terminal object and (id_G,i), (i,id_G) are the maps into the product with the indicated components. The two squares say $\mu(g,i(g))=\eta e(g)=\mu(i(g),g)$: multiplying an element by its inverse on either side returns the unit. In $(\mathbf{Set},\times,1)$ a group object is a group. In $(\mathbf{Top},\times,1)$ it is a topological group, a group whose multiplication and inversion are continuous; in the category $\mathbf{Man}$ of smooth manifolds with the product, it is a Lie group, a group whose operations are smooth, the central object of the differential-geometric theory in [97].

Group objects show that "group" is not a set-theoretic notion but a diagrammatic one: the same diagrams, interpreted in $\mathbf{Top}$ or $\mathbf{Man}$, define topological and Lie groups without a word changing. Comultiplication reverses the picture once more, and a group object with a compatible comonoid structure in a symmetric monoidal category (definition 67.2.2) is a Hopf algebra, the structure underlying quantum groups; the symmetry is what lets the compatibility between μ and δ be stated.

The remaining topic is a finiteness property of the object itself, orthogonal to the algebraic structure above. In $\mathbf{Vect}_k$ a finite-dimensional space V has a dual V^*, and the pairing $V^*\otimes V\to k$ together with the "identity element" $k\to V\otimes V^*$ obey two triangle identities that reconstruct V from V^* and conversely. Abstracting those two identities gives dualizability.

Definition 67.4.5: Dualizable Object

An object X of a monoidal category $(\mathbf{C}, \otimes, I)$ is *(left) dualizable* if there is an object $X^\vee$, the *dual*, together with morphisms

$$\mathrm{ev}\colon X^\vee \otimes X \to I \qquad \text{and} \qquad \mathrm{coev}\colon I \to X \otimes X^\vee$$

the *evaluation* and *coevaluation*, such that the two *zigzag identities*

$$\begin{array}{ccc} X & \xrightarrow{\mathrm{coev}\otimes \mathrm{id}_X} & X \otimes X^\vee \otimes X \\ & \searrow^{\mathrm{id}_X} & \downarrow{\scriptstyle \mathrm{id}_X \otimes \mathrm{ev}} \\ & & X \end{array} \qquad \begin{array}{ccc} X^\vee & \xrightarrow{\mathrm{id}\otimes \mathrm{coev}} & X^\vee \otimes X \otimes X^\vee \\ & \searrow^{\mathrm{id}} & \downarrow{\scriptstyle \mathrm{ev}\otimes \mathrm{id}} \\ & & X^\vee \end{array}$$

commute (associators and unitors suppressed in the strict picture). A monoidal category in which every object is dualizable is called *rigid*.

The two triangles are the categorical form of the linear-algebra identity that expresses id_V through a basis and its dual basis. Reading them in $\mathbf{Vect}_k$ shows the abstraction, and pins down exactly which spaces qualify.

Example 67.4.6: Dualizable Vector Spaces

In $(\mathbf{Vect}_k, \otimes_k, k)$ a vector space V is dualizable if and only if it is finite-dimensional, with dual $V^\vee = V^* = \mathrm{Hom}_k(V, k)$. The evaluation is the pairing $\mathrm{ev}(\varphi \otimes v) = \varphi(v)$, and the coevaluation is

$$\mathrm{coev}\colon k \to V \otimes V^*, \qquad 1 \mapsto \sum_i e_i \otimes e_i^*$$

for a basis (e_i) with dual basis (e_i^*); the element $\sum_i e_i \otimes e_i^*$ is independent of the basis, being the image of id_V under the isomorphism $\mathrm{End}_k(V) \cong V \otimes V^*$ that holds precisely when V is finite-dimensional. The first zigzag sends $v \mapsto \sum_i e_i \otimes e_i^* \otimes v \mapsto \sum_i e_i\, e_i^*(v) = v$, so it is id_V; the second is the symmetric computation. When V is infinite-dimensional no coevaluation exists: a map $k \to V \otimes V^*$ has image an element of $V \otimes V^*$, necessarily a finite sum of simple tensors, and no such finite sum can satisfy the first zigzag for every v. Thus dualizability is exactly the finiteness that makes $V \cong V^{**}$ canonically.

Dualizable objects are where the linear-algebraic notion of trace survives into a symmetric monoidal category (definition 67.2.2): for an endomorphism $f\colon X \to X$ of a dualizable object one forms the composite $I \xrightarrow{\mathrm{coev}} X \otimes X^\vee \xrightarrow{f\otimes \mathrm{id}} X \otimes X^\vee \xrightarrow{\beta_{X,X^\vee}} X^\vee \otimes X \xrightarrow{\mathrm{ev}} I$, an endomorphism of I that specializes to the ordinary trace in $\mathbf{Vect}_k$. The symmetry β is what gives the swap $X \otimes X^\vee \to X^\vee \otimes X$; in a bare monoidal category no such canonical map exists, so the trace needs at least a braiding. Rigid symmetric monoidal categories, in which every object is dualizable, are the setting for Tannakian duality, which reconstructs a group from its rigid tensor category of representations; both developments belong to the next stage of the theory and are not pursued here.

68

Enriched and 2-Categories

Two facts about the previous chapters were left unremarked. The hom-*sets* of a category are objects of **Set**, but nothing forced that choice; and **Cat** carried natural transformations, a second layer of morphism an ordinary category lacks. This chapter follows both threads. *Enriched category theory* replaces hom-sets by objects of a monoidal category, recovering additive, topological, and simplicial categories as the base varies. *Two-category theory* takes the morphisms between morphisms seriously, with **Cat** as the guiding example, and recovers adjunctions and monads as statements internal to a 2-category.

The two threads are developed to different depths. The enriched theory is built in full through section 68.3: tensors and cotensors, the enriched functor category, the enriched Yoneda lemma with its proof, and weighted limits, which subsume ordinary limits and both of the first two. The 2-categorical theory is developed only as far as the enriched theory already carries it, since a strict 2-category is the **Cat**-enriched case of definition 68.1.1 and the structures whose coherence is genuine, rather than provable, are the subject of the sequel. The chapter, and the book, close at the edge of the subject, where the strict equalities weaken to coherent isomorphism, pointing beyond it to higher category theory.

68.1 Enriched Categories

The hom-set of a category is a set, and nothing more. Yet the standing cast carries hom-sets with extra structure that the plain definition discards: the morphisms between two abelian groups form an abelian group under pointwise addition, the maps between two topological spaces form a topological space, and between two categories the functors form a category (with natural transformations as its own morphisms). *Enriched category theory* takes this extra structure seriously. It replaces the hom-*set* $\mathbf{C}(x, y)$ by a hom-*object* living in a fixed monoidal category $\mathbf{V}$ (definition 67.1.1), whose tensor product gives the composition and whose unit gives the identities. The one requirement is

that $\mathbf{V}$ be monoidal: composition pairs two hom-objects, and $\otimes$ is exactly the operation for pairing objects of $\mathbf{V}$.

Definition 68.1.1: Enriched Category

Let $(\mathbf{V}, \otimes, I)$ be a monoidal category. A *category enriched over* $\mathbf{V}$, or a $\mathbf{V}$*-category*, $\mathbf{C}$ consists of

- a collection of *objects* $\mathrm{Ob}(\mathbf{C})$;
- for each ordered pair (x, y) of objects, a *hom-object* $\mathbf{C}(x, y)$ of $\mathbf{V}$;
- for each ordered triple (x, y, z), a *composition* morphism of $\mathbf{V}$

$$\circ_{xyz} \colon \mathbf{C}(y, z) \otimes \mathbf{C}(x, y) \to \mathbf{C}(x, z)$$

- for each object x, an *identity* morphism of $\mathbf{V}$

$$j_x \colon I \to \mathbf{C}(x, x)$$

subject to the associativity and unit laws, which are the following diagrams in $\mathbf{V}$. Associativity is the commuting square (writing α for the associator of $\mathbf{V}$)

$$\begin{array}{ccc} \big(\mathbf{C}(z,w) \otimes \mathbf{C}(y,z)\big) \otimes \mathbf{C}(x,y) & \xrightarrow{\ \alpha\ } & \mathbf{C}(z,w) \otimes \big(\mathbf{C}(y,z) \otimes \mathbf{C}(x,y)\big) \\ \downarrow{\scriptstyle \circ\otimes\mathrm{id}} & & \downarrow{\scriptstyle \mathrm{id}\otimes\circ} \\ \mathbf{C}(y,w) \otimes \mathbf{C}(x,y) & & \mathbf{C}(z,w) \otimes \mathbf{C}(x,z) \\ \downarrow{\scriptstyle \circ} & & \downarrow{\scriptstyle \circ} \\ \mathbf{C}(x,w) & = & \mathbf{C}(x,w) \end{array}$$

and the two unit laws are the commuting triangles (writing λ, ρ for the left and right unitors of $\mathbf{V}$)

$$\begin{array}{ccccc} I \otimes \mathbf{C}(x,y) & \xrightarrow{\ j_y\otimes\mathrm{id}\ } & \mathbf{C}(y,y) \otimes \mathbf{C}(x,y) & \xleftarrow{\ \mathrm{id}\otimes j_x\ } & \mathbf{C}(x,y) \otimes I \\ & {\scriptstyle \lambda}\searrow & \downarrow{\scriptstyle \circ} & \swarrow{\scriptstyle \rho} & \\ & & \mathbf{C}(x,y) & & \end{array}$$

The two diagrams are the ordinary associativity and unit laws with every equation of *elements* replaced by a commuting diagram of *morphisms in* $\mathbf{V}$, and every reassociation or unit-insertion routed through the coherence isomorphisms α, λ, ρ that a monoidal category gives for exactly this purpose. Nowhere does the definition speak of an element of $\mathbf{C}(x, y)$: $\mathbf{C}(x, y)$ is an object of $\mathbf{V}$, and $\mathbf{V}$ need not be a category of structured sets. Composition is not a function applied to a pair of morphisms but a single arrow out of a tensor product, and the identity at x is not a chosen element but an arrow $I \to \mathbf{C}(x, x)$ selecting it in whatever sense $\mathbf{V}$ allows. This is the shift the definition forces: from *elements and functions* to *objects and morphisms of* $\mathbf{V}$.

An ordinary category is the special case $\mathbf{V} = (\mathbf{Set}, \times, 1)$. Then $\mathbf{C}(x, y)$ is a hom-set, the composition arrow $\mathbf{C}(y, z) \times \mathbf{C}(x, y) \to \mathbf{C}(x, z)$ is the usual composition function $(g, f) \mapsto gf$, and the identity

arrow $j_x \colon 1 \to \mathbf{C}(x,x)$ from the one-point set picks out id_x. The associativity and unit diagrams reduce to $h(gf) = (hg)f$ and $f\,\mathrm{id}_x = f = \mathrm{id}_y f$. Enrichment loses nothing and is a genuine generalization: it remembers structure on the hom-objects that the passage to underlying sets throws away.

That passage is itself a construction. Given a $\mathbf{V}$-category, one recovers an ordinary category by asking $\mathbf{V}$ for the elements of each hom-object, where "element" means a morphism out of the monoidal unit.

Definition 68.1.2: Underlying Ordinary Category

Let $\mathbf{C}$ be a $\mathbf{V}$-category. Its *underlying ordinary category* $\mathbf{C}_0$ has the same objects as $\mathbf{C}$, and hom-sets

$$\mathrm{Hom}_{\mathbf{C}_0}(x,y) = \mathbf{V}\big(I, \mathbf{C}(x,y)\big)$$

the set of $\mathbf{V}$-morphisms from the unit I to the hom-object $\mathbf{C}(x,y)$. The identity of x in $\mathbf{C}_0$ is the enriched identity $j_x \colon I \to \mathbf{C}(x,x)$. The composite in $\mathbf{C}_0$ of $f \colon I \to \mathbf{C}(x,y)$ and $g \colon I \to \mathbf{C}(y,z)$ is

$$I \xrightarrow{\lambda^{-1}} I \otimes I \xrightarrow{g \otimes f} \mathbf{C}(y,z) \otimes \mathbf{C}(x,y) \xrightarrow{\circ} \mathbf{C}(x,z)$$

where $\lambda^{-1} \colon I \to I \otimes I$ is the inverse left unitor.

The associativity and unit laws of $\mathbf{C}_0$ are not assumed; they are *consequences* of the enriched laws of definition 68.1.1. Composing three elements in $\mathbf{C}_0$ produces two bracketings of the same triple tensor, and the enriched associativity square, together with the coherence (theorem 67.1.5) that makes all instances of α, λ, ρ agree, identifies them; the enriched unit triangles give the identity laws in $\mathbf{C}_0$. The underlying category is what the $\mathbf{V}$-category induces on $\mathbf{Set}$ by probing each hom-object with the unit. When $\mathbf{V} = \mathbf{Set}$ it changes nothing, since $\mathbf{Set}(1,S) \cong S$: an ordinary category is its own underlying category. The interesting cases are those where $\mathbf{C}_0$ forgets real structure, and the enriched data is strictly richer than the ordinary category it sits over.

Example 68.1.3: Enrichment over the Standing Cast

Each choice of monoidal base $\mathbf{V}$ names a familiar species of category.

1. $\mathbf{Set}$*-enriched categories are ordinary categories.* With $\mathbf{V} = (\mathbf{Set}, \times, 1)$ the data of definition 68.1.1 is precisely objects, hom-sets, a composition function, and chosen identities obeying associativity and unit laws. This is the definition of a locally small category, and the underlying category $\mathbf{C}_0$ is $\mathbf{C}$ itself.

2. $\mathbf{Ab}$*-enriched categories are preadditive categories.* Take $\mathbf{V} = (\mathbf{Ab}, \otimes_{\mathbb{Z}}, \mathbb{Z})$, the tensor product of abelian groups with unit $\mathbb{Z}$. Each hom-object $\mathbf{C}(x,y)$ is then an abelian group, and composition is a morphism of abelian groups

$$\mathbf{C}(y,z) \otimes_{\mathbb{Z}} \mathbf{C}(x,y) \to \mathbf{C}(x,z)$$

which is exactly a $\mathbb{Z}$-bilinear map $\mathbf{C}(y,z) \times \mathbf{C}(x,y) \to \mathbf{C}(x,z)$, by the universal property of $\otimes_{\mathbb{Z}}$. Composition is therefore biadditive: $h(g+g') = hg + hg'$ and $(h+h')g = hg + h'g$. A category with abelian-group hom-sets and biadditive composition is a *preadditive category*, and the underlying category recovers the hom-set as $\mathbf{Ab}(\mathbb{Z}, \mathbf{C}(x,y)) \cong \mathbf{C}(x,y)$. This is the enrichment that homological algebra rests on: an additive category is a preadditive category

with a zero object and biproducts, and **Ab**-enrichment is the first axiom (see [21, Tensor Product] for the module-theoretic origin of $\otimes_{\mathbb{Z}}$).

3. **Top**-*enriched categories topologize their hom-sets.* With $\mathbf{V} = (\mathbf{Top}, \times, *)$ each $\mathbf{C}(x, y)$ is a topological space and composition $\mathbf{C}(y, z) \times \mathbf{C}(x, y) \to \mathbf{C}(x, z)$ is continuous. The identity $* \to \mathbf{C}(x, x)$ from the one-point space picks out id_x. The underlying category has hom-sets $\mathbf{Top}(*, \mathbf{C}(x, y)) \cong \mathbf{C}(x, y)$ as sets, discarding the topology; the enriched structure remembers, for instance, when two maps are homotopic through a continuous path of morphisms.

4. **Cat**-*enriched categories are strict* 2-*categories.* Take $\mathbf{V} = (\mathbf{Cat}, \times, \mathbf{1})$, categories under product with the terminal category $\mathbf{1}$ as unit. Each hom-object $\mathbf{C}(x, y)$ is now a *category*: its objects are the morphisms $x \to y$, and its own morphisms are a second layer of structure between them. Composition is a functor $\mathbf{C}(y, z) \times \mathbf{C}(x, y) \to \mathbf{C}(x, z)$. This is exactly a strict 2-category, the subject of section 68.4: the prototype is **Cat** itself, whose hom-categories are the functor categories $[\mathbf{C}, \mathbf{D}]$ (definition 61.5.4) with natural transformations as the second layer.

5. *Lawvere metric spaces.* Let $\mathbf{V} = ([0, \infty], +, 0)$ be the extended nonnegative reals, viewed as a category by the order $\geq$ (an arrow $a \to b$ exactly when $a \geq b$), monoidal under addition with unit 0. A category enriched over this $\mathbf{V}$ has objects, and for each pair a number $\mathbf{C}(x, y) \in [0, \infty]$ to be read as a *distance*. The composition arrow $\mathbf{C}(y, z) + \mathbf{C}(x, y) \to \mathbf{C}(x, z)$ is, in this order category, precisely the inequality

$$\mathbf{C}(x, z) \leq \mathbf{C}(y, z) + \mathbf{C}(x, y)$$

the triangle inequality, and the identity $0 \to \mathbf{C}(x, x)$ is the inequality $\mathbf{C}(x, x) \leq 0$, forcing $\mathbf{C}(x, x) = 0$. Such a structure is a *Lawvere metric space*: a metric space that drops symmetry and the separation axiom (distinct points may sit at distance 0) and permits ∞. Composition of morphisms and the triangle inequality are the same axiom seen through two monoidal bases.

The five bases run from the trivial to the exotic and read off five theories at a stroke. **Set** recovers the ordinary notion; **Ab** recovers the preadditive categories of homological algebra; **Cat** recovers strict 2-categories; and the order category $[0, \infty]$ shows that enrichment need not be over structured sets at all, turning the triangle inequality into an instance of composition. The last example is the sharpest test of the definition, since $[0, \infty]$ has no underlying sets in the naive sense: what matters is only that it is monoidal, and that alone is enough to carry categorical composition. The lesson is that "category" is not tied to **Set**; it is tied to whatever monoidal $\mathbf{V}$ one composes in.

68.2 Enriched Functors and Naturality

A $\mathbf{V}$-category (definition 68.1.1) carries its structure in $\mathbf{V}$: a functor between two such categories must act on hom-objects by morphisms of $\mathbf{V}$, and a natural transformation must have components that live in $\mathbf{V}$ rather than in Hom-sets. This section installs the two notions, shows how a monoidal functor transports the whole theory from one base to another, and records the enriched form of the Yoneda lemma.

An ordinary functor sends each hom-set $\mathrm{Hom}(x, y)$ to $\mathrm{Hom}(Fx, Fy)$ by post- and pre-composition, and the two functoriality axioms say this map respects composition and identities. The enriched

version replaces those set functions with $\mathbf{V}$-morphisms and rewrites the two axioms as commuting diagrams in $\mathbf{V}$.

Definition 68.2.1: Enriched Functor

Let $\mathbf{V}$ be a monoidal category and let $\mathbf{C}$, $\mathbf{D}$ be $\mathbf{V}$-categories. A $\mathbf{V}$-*functor* (or *enriched functor*) $F\colon \mathbf{C} \to \mathbf{D}$ consists of

- a map $x \mapsto Fx$ on objects, and
- for each pair of objects x, y of $\mathbf{C}$, a $\mathbf{V}$-morphism

$$F_{x,y}\colon \mathbf{C}(x,y) \to \mathbf{D}(Fx, Fy)$$

such that the following two diagrams in $\mathbf{V}$ commute. Writing $\circ$ for the composition morphisms of $\mathbf{C}$ and $\mathbf{D}$ and $j_x\colon I \to \mathbf{C}(x,x)$ for the identity morphisms, compatibility with composition is the commutativity of

$$\begin{array}{ccc} \mathbf{C}(y,z) \otimes \mathbf{C}(x,y) & \xrightarrow{F_{y,z} \otimes F_{x,y}} & \mathbf{D}(Fy,Fz) \otimes \mathbf{D}(Fx,Fy) \\ \downarrow{\scriptstyle \circ} & & \downarrow{\scriptstyle \circ} \\ \mathbf{C}(x,z) & \xrightarrow[F_{x,z}]{} & \mathbf{D}(Fx,Fz) \end{array}$$

and compatibility with identities is the commutativity of

$$\begin{array}{ccc} I & \xrightarrow{j_x} & \mathbf{C}(x,x) \\ & \searrow^{j_{Fx}} & \downarrow{\scriptstyle F_{x,x}} \\ & & \mathbf{D}(Fx,Fx) \end{array}$$

Reading the squares in $\mathbf{V} = \mathbf{Set}$ recovers the ordinary axioms: the first says $F(g \circ f) = Fg \circ Ff$ and the second $F(\mathrm{id}_x) = \mathrm{id}_{Fx}$. The content is that these hold at the level of $\mathbf{V}$, so the functor is compatible with whatever extra structure the hom-objects carry.

Example 68.2.2: Additive Functors as Ab-Functors

Let $\mathbf{V} = \mathbf{Ab}$, so that $\mathbf{C}$ and $\mathbf{D}$ are preadditive categories (example 68.1.3): each Hom-set is an abelian group and composition is bilinear. An $\mathbf{Ab}$-functor $F\colon \mathbf{C} \to \mathbf{D}$ is an ordinary functor whose action on morphisms

$$F_{x,y}\colon \mathbf{C}(x,y) \to \mathbf{D}(Fx,Fy)$$

is a group homomorphism for every pair x, y, that is, $F(f+g) = Ff + Fg$. These are exactly the *additive functors*. The composition square is the statement that F is bilinear-compatible, and the identity triangle that $F(\mathrm{id}_x) = \mathrm{id}_{Fx}$; both are automatic for a functor once additivity on hom-groups is imposed. For $\mathbf{V} = \mathbf{Cat}$, an enriched functor is a strict 2-functor, sending objects, 1-cells, and 2-cells compatibly (this is developed in section 68.4).

An enriched functor moves objects and hom-objects; a natural transformation must compare two such functors at each object. In the unenriched setting a component is a morphism $\alpha_x\colon Fx \to Gx$, and morphisms out of x are elements of a hom-set. In $\mathbf{V}$ there are no elements; a "point" of the hom-object

$\mathbf{D}(Fx, Gx)$ is a $\mathbf{V}$-morphism $I \to \mathbf{D}(Fx, Gx)$ out of the unit, matching the underlying-category convention $\mathrm{Hom}(x, y) = \mathbf{V}(I, \mathbf{C}(x, y))$ from definition 68.1.2. A component is therefore such a morphism, and naturality becomes a single diagram in $\mathbf{V}$.

Definition 68.2.3: Enriched Natural Transformation

Let $F, G \colon \mathbf{C} \to \mathbf{D}$ be $\mathbf{V}$-functors. A $\mathbf{V}$-*natural transformation* (or *enriched natural transformation*) $\alpha \colon F \Rightarrow G$ assigns to each object x of $\mathbf{C}$ a $\mathbf{V}$-morphism

$$\alpha_x \colon I \to \mathbf{D}(Fx, Gx)$$

(the *component* at x) such that for every pair x, y the following diagram in $\mathbf{V}$ commutes:

$$\begin{array}{ccccc} \mathbf{C}(x,y) & \xrightarrow{\rho^{-1}} & \mathbf{C}(x,y) \otimes I & \xrightarrow{G_{x,y} \otimes \alpha_x} & \mathbf{D}(Gx,Gy) \otimes \mathbf{D}(Fx,Gx) \\ \downarrow{\scriptstyle \lambda^{-1}} & & & & \downarrow{\scriptstyle \circ} \\ I \otimes \mathbf{C}(x,y) & \xrightarrow[\alpha_y \otimes F_{x,y}]{} & \mathbf{D}(Fy,Gy) \otimes \mathbf{D}(Fx,Fy) & \xrightarrow[\circ]{} & \mathbf{D}(Fx,Gy) \end{array}$$

Here λ and ρ are the unitors of $\mathbf{V}$ (definition 67.1.1), inserting the unit I so that a component may be composed against a hom-object.

The two legs of the diagram are the enriched versions of the two paths around the ordinary naturality square. The top-right leg applies G to a morphism $f \colon x \to y$ and pre-composes with α_x, producing the path $Gf \cdot \alpha_x$; the bottom-left leg applies F and post-composes with α_y, producing $\alpha_y \cdot Ff$. Equality of the legs is precisely $\alpha_y \circ Ff = Gf \circ \alpha_x$ written internally to $\mathbf{V}$. In $\mathbf{V} = \mathbf{Set}$ each component $\alpha_x \colon I = \{*\} \to \mathbf{D}(Fx, Gx)$ names an element $\alpha_x \in \mathrm{Hom}(Fx, Gx)$, and the diagram collapses to the familiar commuting square.

Example 68.2.4: Additive Natural Transformations

For $\mathbf{V} = \mathbf{Ab}$, a component $\alpha_x \colon \mathbb{Z} \to \mathbf{D}(Fx, Gx)$ is a group homomorphism out of $\mathbb{Z}$, hence pinned down by the single element $\alpha_x(1) \in \mathrm{Hom}(Fx, Gx)$: an ordinary component morphism. The enriched naturality diagram then says nothing more than ordinary naturality, because both composition maps of $\mathbf{Ab}$ are $\mathbb{Z}$-bilinear and evaluating at $1 \otimes 1$ returns the set-level square. An $\mathbf{Ab}$-natural transformation between additive functors is thus an ordinary natural transformation, with no further condition to check.

The definitions of $\mathbf{V}$-category, $\mathbf{V}$-functor, and $\mathbf{V}$-natural transformation depend on $\mathbf{V}$ only through its monoidal structure. A functor between monoidal categories that preserves that structure should therefore transport enriched categories along it. The correct hypothesis is weaker than strict preservation of $\otimes$: it is enough that $\mathbf{V}$-tensors map to $\mathbf{W}$-tensors up to a coherent comparison morphism, which is exactly a lax monoidal functor. That comparison is what carries composition across the base.

Proposition 68.2.5: Change of Enriching Base

Let $(\Phi, \varphi, \varphi_0)\colon \mathbf{V} \to \mathbf{W}$ be a lax monoidal functor: Φ is a functor equipped with a natural comparison $\varphi_{a,b}\colon \Phi a \otimes \Phi b \to \Phi(a \otimes b)$ and a unit comparison $\varphi_0\colon I_{\mathbf{W}} \to \Phi(I_{\mathbf{V}})$, satisfying the associativity and unit coherence laws. Then Φ induces a functor

$$\Phi_*\colon \mathbf{V}\text{-}\mathbf{Cat} \to \mathbf{W}\text{-}\mathbf{Cat}$$

called *change of base*, sending a $\mathbf{V}$-category $\mathbf{C}$ to the $\mathbf{W}$-category $\Phi_*\mathbf{C}$ with the same objects and hom-objects $(\Phi_*\mathbf{C})(x, y) = \Phi\big(\mathbf{C}(x, y)\big)$.

***Proof*:**
Fix a lax monoidal functor $(\Phi, \varphi, \varphi_0)$. The construction proceeds in two stages: first the object $\Phi_*\mathbf{C}$, then the action of Φ_* on enriched functors, checking the axioms at each stage.

Step 1: The category $\Phi_*\mathbf{C}$. Take the objects of $\mathbf{C}$ and the hom-objects $\Phi(\mathbf{C}(x, y))$ in $\mathbf{W}$. The composition morphism of $\Phi_*\mathbf{C}$ is the composite

$$\Phi(\mathbf{C}(y, z)) \otimes \Phi(\mathbf{C}(x, y)) \xrightarrow{\varphi} \Phi\big(\mathbf{C}(y, z) \otimes \mathbf{C}(x, y)\big) \xrightarrow{\Phi(\circ)} \Phi(\mathbf{C}(x, z))$$

which first uses the comparison φ to gather the two hom-objects inside Φ and then applies Φ to the composition of $\mathbf{C}$. The identity morphism is

$$I_{\mathbf{W}} \xrightarrow{\varphi_0} \Phi(I_{\mathbf{V}}) \xrightarrow{\Phi(j_x)} \Phi(\mathbf{C}(x, x))$$

using the unit comparison followed by Φ applied to the identity of $\mathbf{C}$. Associativity of composition in $\Phi_*\mathbf{C}$ follows from associativity in $\mathbf{C}$ (apply Φ to its associativity square) glued to the associativity coherence of the lax structure φ; the two unit laws follow likewise from the unit laws in $\mathbf{C}$ glued to the unit coherence of φ_0. Each verification is a diagram in $\mathbf{W}$ built from a Φ-image of a $\mathbf{C}$-axiom and one lax-coherence cell sharing a common edge: the coherence cell rebrackets the φ-comparisons to expose Φ applied to the tensor of the hom-objects, and the Φ-image of the $\mathbf{C}$-axiom equates the two composites there, so the two cells paste along that edge into the required square. Thus $\Phi_*\mathbf{C}$ is a $\mathbf{W}$-category.

Step 2: The action on functors and naturality. Given a $\mathbf{V}$-functor $F\colon \mathbf{C} \to \mathbf{D}$, define Φ_*F to agree with F on objects and to act on hom-objects by

$$(\Phi_*F)_{x,y} = \Phi(F_{x,y})\colon \Phi(\mathbf{C}(x, y)) \to \Phi(\mathbf{D}(Fx, Fy))$$

Its composition square is Φ applied to the composition square of F, with the naturality of φ used to slide $\Phi(F_{y,z}) \otimes \Phi(F_{x,y})$ past the two copies of the comparison; the identity triangle is Φ applied to that of F, precomposed with φ_0. Both commute, so Φ_*F is a $\mathbf{W}$-functor. Functoriality of Φ_*, preservation of enriched composition and identities of functors, is immediate, since Φ_* acts as Φ on hom-objects and Φ is a functor. This gives the assignment on $\mathbf{V}$-$\mathbf{Cat}$, completing the proof.

Change of base is the mechanism by which enriched category theory specializes to ordinary category theory, and by which one kind of enrichment passes to another. The main instance takes $\mathbf{W} = \mathbf{Set}$.

Example 68.2.6: The Underlying Category as Change of Base
Let $\mathbf{V}$ be monoidal. The representable functor

$$\mathbf{V}(I,-)\colon \mathbf{V}\to\mathbf{Set},\qquad a\mapsto \mathbf{V}(I,a)$$

is lax monoidal: its comparison sends a pair $(u\colon I\to a,\ v\colon I\to b)$ to the composite $I\xrightarrow{\lambda^{-1}} I\otimes I\xrightarrow{u\otimes v} a\otimes b$, and its unit comparison $\{*\}\to\mathbf{V}(I,I)$ picks out id_I. Change of base along it,

$$\big(\mathbf{V}(I,-)\big)_*\colon \mathbf{V}\text{-}\mathbf{Cat}\to\mathbf{Set}\text{-}\mathbf{Cat}=\mathbf{Cat}$$

sends a $\mathbf{V}$-category $\mathbf{C}$ to a category with hom-sets $\mathbf{V}(I,\mathbf{C}(x,y))$, exactly the underlying category $\mathbf{C}_0$ of definition 68.1.2. The construction of $\mathbf{C}_0$ is thus not an ad hoc device but the $\mathbf{W}=\mathbf{Set}$ case of this proposition. Concretely, for $\mathbf{V}=\mathbf{Ab}$ the functor $\mathbf{Ab}(\mathbb{Z},-)$ is the forgetful functor $\mathbf{Ab}\to\mathbf{Set}$, and change of base along it strips a preadditive category down to its underlying ordinary category, forgetting the abelian-group structure on the hom-sets while keeping the same objects and morphisms.

A $\mathbf{V}$-natural transformation, as definition 68.2.3 defines it, is a family of morphisms, and families form a set. Every other hom in this chapter has been an object of $\mathbf{V}$, and the collection of $\mathbf{V}$-natural transformations ought to be one too. Constructing that object is the first task of section 68.3, and it is what the enriched Yoneda lemma needs before it can even be stated.

68.3 Enriched Functor Categories and Weighted Limits

Two constructions stand between the definitions of the previous section and a working enriched theory. The first is the *end*, a limit in $\mathbf{V}$ that cuts the product of the hom-objects $\mathbf{D}(Fc,Gc)$ down to the part respecting naturality; it is what promotes the $\mathbf{V}$-natural transformations from a set to an object of $\mathbf{V}$, and with it the $\mathbf{V}$-functors $\mathbf{C}\to\mathbf{D}$ become a $\mathbf{V}$-category $[\mathbf{C},\mathbf{D}]$. The second is the *tensor* and *cotensor*, by which an object of $\mathbf{V}$ acts on an object of a $\mathbf{V}$-category. Together they make the enriched Yoneda lemma provable, and they yield one definition, the weighted limit, that has ordinary limits, tensors and cotensors as three instances.

Throughout this section $\mathbf{V}$ is symmetric monoidal closed (definition 67.2.2, definition 67.3.1) with all small limits and colimits, and $\mathbf{C}$ is small. Closedness gives the internal hom $[a,b]$; symmetry is what allows $\mathbf{C}^{\mathrm{op}}$ to be formed as a $\mathbf{V}$-category and what orients the second of the two morphisms in definition 68.3.3; completeness gives the products and equalizers that the end is built from, and cocompleteness the coproducts and coequalizers its dual needs. The bracket $[a,b]$ for the internal hom and $[\mathbf{C},\mathbf{D}]$ for the functor category are distinguished by their arguments, objects in the first case and categories in the second.

Ordinary category theory copies an object along a set: the copower $S\cdot e$ of section 66.4 is S-many copies of e, characterized by $\mathrm{Hom}(S\cdot e,d)\cong\mathbf{Set}(S,\mathrm{Hom}(e,d))$. Enriched over $\mathbf{V}$ the indexing set becomes an object of $\mathbf{V}$ and the hom-sets become hom-objects, and the same two universal properties read in $\mathbf{V}$ define the two constructions below.

Definition 68.3.1: Tensor and Cotensor

Let $\mathbf{C}$ be a $\mathbf{V}$-category, c an object of $\mathbf{C}$, and v an object of $\mathbf{V}$. The *tensor* of c by v is an object $v \odot c$ of $\mathbf{C}$ together with an isomorphism

$$\mathbf{C}(v \odot c,\ d) \ \cong\ \big[v,\ \mathbf{C}(c, d)\big]$$

of objects of $\mathbf{V}$, natural in d. The *cotensor* of c by v is an object c^{v} of $\mathbf{C}$ together with an isomorphism

$$\mathbf{C}(d,\ c^{v}) \ \cong\ \big[v,\ \mathbf{C}(d, c)\big]$$

natural in d. The category $\mathbf{C}$ is *tensored* if $v \odot c$ exists for every v and c, and *cotensored* if c^{v} always exists.

Each is defined by a representing property, so each is unique up to a unique isomorphism compatible with the displayed natural isomorphism, by the argument of theorem 62.2.1 applied to the underlying category. The tensor is v-indexed copies of c and the cotensor is v-indexed families in c, with "v-indexed" interpreted by $\mathbf{V}$ rather than by a set. Note which variable each is natural in: the tensor represents a functor of the target and the cotensor a functor of the source, which is why the tensor is a colimit-like construction and the cotensor a limit-like one.

Example 68.3.2: Tensors and Cotensors over the Standing Bases

1. $\mathbf{V}$ *over itself.* The base $\mathbf{V}$ is a $\mathbf{V}$-category with hom-objects $[a, b]$. Its composition $[b, c] \otimes [a, b] \to [a, c]$ is the transpose under (67.1) of

$$\big([b, c] \otimes [a, b]\big) \otimes a \xrightarrow{\alpha} [b, c] \otimes \big([a, b] \otimes a\big) \xrightarrow{\mathrm{id} \otimes \mathrm{ev}_{a,b}} [b, c] \otimes b \xrightarrow{\mathrm{ev}_{b,c}} c$$

   with ev the evaluation of theorem 67.3.2, and its identity $I \to [a, a]$ is the transpose of $\lambda_a \colon I \otimes a \to a$. By construction $\mathrm{ev}_{a,c} \circ (\circ \otimes a)$ is the displayed composite of two evaluations, and $\mathrm{ev}_{a,a} \circ (j_a \otimes a) = \lambda_a$ for the identity j_a. Transpose both sides of each axiom of definition 68.1.1. For associativity, applying the first identity twice on each side, and moving associators past evaluations by naturality of α, turns both sides into the composite of the three evaluations out of $[c, d] \otimes [b, c] \otimes [a, b] \otimes a$, each preceded by a composite of associators. For the unit axioms, the second identity and naturality of λ, ρ and ev turn both sides into $\mathrm{ev}_{a,b}$ preceded by a composite of associators and unitors. In each case the two composites of structure isomorphisms agree by theorem 67.1.5(1), which covers the pentagon for associativity and the identity $\lambda_{X \otimes Y} \circ \alpha_{I,X,Y} = \lambda_X \otimes Y$ for the left unit, so the two sides are equal. For $g \colon a' \to a$, composition with the name $I \to [a', a]$ of g (the transpose of $g \circ \lambda_{a'}$) is the map $[a, b] \to [a', b]$ whose transpose is $\mathrm{ev}_{a,b} \circ (\mathrm{id} \otimes g) \colon [a, b] \otimes a' \to b$, by the same computation, with the triangle axiom $(\mathrm{id} \otimes \lambda_{a'}) \circ \alpha_{[a,b],I,a'} = \rho_{[a,b]} \otimes a'$ in place of theorem 67.1.5, so the functoriality of $[-, b]$ in this $\mathbf{V}$-category is the one for which (67.1) is natural in X as well as in A and Y. There $v \odot a = v \otimes a$ and $a^{v} = [v, a]$. The first is the internal form of (67.1): the required isomorphism $[v \otimes a, b] \cong [v, [a, b]]$ holds because, for every u, the adjunction gives $\mathbf{V}(u, [v \otimes a, b]) \cong \mathbf{V}(u \otimes v \otimes a, b) \cong \mathbf{V}(u, [v, [a, b]])$ naturally in u, and theorem 62.2.1 turns a natural isomorphism of representables into one of the representing objects. The second follows from the first by symmetry of $\otimes$.

2. $\mathbf{V} = \mathbf{Set}$. For an ordinary category $\mathbf{C}$ the defining isomorphism reads $\mathrm{Hom}(S \odot c, d) \cong \mathbf{Set}(S, \mathrm{Hom}(c, d))$, and an S-indexed family of maps $c \to d$ is a single map out of the

coproduct. So $S \odot c = \coprod_S c$ and, dually, $c^S = \prod_S c$: the tensor and cotensor are the copower and power of section 66.4, and a category is tensored and cotensored over **Set** exactly when it has all small coproducts and products.

3. $\mathbf{V} = \mathbf{Ab}$. For $\mathbf{C} = \mathbf{Ab}$ itself, $A \odot B = A \otimes_{\mathbb{Z}} B$ and $B^A = \mathrm{Hom}_{\mathbb{Z}}(A, B)$, by (1), since **Ab** is closed with internal hom $\mathrm{Hom}_{\mathbb{Z}}$. For $\mathbf{C}$ the R-modules, the tensor of a module M by an abelian group A is $A \otimes_{\mathbb{Z}} M$ with R acting through M, because a homomorphism $A \to \mathrm{Hom}_R(M, N)$ is the same as an R-linear map $A \otimes_{\mathbb{Z}} M \to N$.

The three bases show the pattern: over **Set** the tensor is a coproduct of copies, over **Ab** it is a tensor product, and over $\mathbf{V}$ itself it is $\otimes$. In every case the operation is the one that lets an object of the base act on an object of the enriched category, and that action is what definition 68.3.7 will weight a diagram by.

The second construction is the one the previous section stopped short of. A $\mathbf{V}$-natural transformation $F \Rightarrow G$ is a family of morphisms $I \to \mathbf{D}(Fc, Gc)$ satisfying the naturality condition of definition 68.2.3. Replacing "family of morphisms out of I" by "object of $\mathbf{V}$ mapping to each $\mathbf{D}(Fc, Gc)$", and imposing naturality as an equation between two morphisms into a product, turns that collection into a limit in $\mathbf{V}$.

Definition 68.3.3: The Object of Enriched Natural Transformations

Let $F, G \colon \mathbf{C} \to \mathbf{D}$ be $\mathbf{V}$-functors. The *object of* $\mathbf{V}$*-natural transformations* from F to G, also called the *end* of $c \mapsto \mathbf{D}(Fc, Gc)$ and written

$$[\mathbf{C}, \mathbf{D}](F, G) \;=\; \int_c \mathbf{D}(Fc, Gc)$$

is the equalizer in $\mathbf{V}$ (definition 63.2.4) of the two morphisms

$$\prod_c \mathbf{D}(Fc, Gc) \;\rightrightarrows\; \prod_{c,c'} \left[\, \mathbf{C}(c, c'),\ \mathbf{D}(Fc, Gc') \,\right]$$

whose components at a pair (c, c') are the transposes under (67.1) of

$$\textstyle\prod_b \mathbf{D}(Fb, Gb) \otimes \mathbf{C}(c, c') \xrightarrow{\pi_{c'} \otimes F_{c,c'}} \mathbf{D}(Fc', Gc') \otimes \mathbf{D}(Fc, Fc') \xrightarrow{\circ} \mathbf{D}(Fc, Gc')$$

and

$$\begin{aligned}\textstyle\prod_b \mathbf{D}(Fb, Gb) \otimes \mathbf{C}(c, c') &\xrightarrow{\pi_c \otimes G_{c,c'}} \mathbf{D}(Fc, Gc) \otimes \mathbf{D}(Gc, Gc') \\ &\xrightarrow{\sigma} \mathbf{D}(Gc, Gc') \otimes \mathbf{D}(Fc, Gc) \xrightarrow{\circ} \mathbf{D}(Fc, Gc')\end{aligned}$$

where π_c is a product projection and σ the symmetry of $\mathbf{V}$. The products are indexed by the objects and the ordered pairs of objects of the small category $\mathbf{C}$, and both they and the equalizer exist because $\mathbf{V}$ is complete.

The two morphisms are the two routes from a component at one object to a value at another: the first carries the component at c' backwards along F, the second carries the component at c forwards along G, and a family is natural exactly when the two agree. Writing α_c for a component, the first is $\alpha_{c'} \circ F(f)$ and the second $G(f) \circ \alpha_c$ in the notation of an ordinary category; the symmetry σ appears in the second because $\circ$ takes its arguments in the order (later, earlier) while the projection produces

them in the order (earlier, later).

Probing the equalizer with the unit recovers the unenriched notion. The functor $\mathbf{V}(I,-)$ is representable, hence preserves limits, so $\mathbf{V}\big(I,[\mathbf{C},\mathbf{D}](F,G)\big)$ is the equalizer of the corresponding pair of functions, which is precisely the set of families $\alpha_c\colon I\to\mathbf{D}(Fc,Gc)$ satisfying definition 68.2.3. The new object therefore refines the old set rather than replacing it.

Proposition 68.3.4: The Enriched Functor Category

Let $\mathbf{C}$ be a small $\mathbf{V}$-category and $\mathbf{D}$ a $\mathbf{V}$-category. The $\mathbf{V}$-functors $\mathbf{C}\to\mathbf{D}$ are the objects of a $\mathbf{V}$-category $[\mathbf{C},\mathbf{D}]$ whose hom-objects are those of definition 68.3.3. Its underlying ordinary category (definition 68.1.2) is the category of $\mathbf{V}$-functors and $\mathbf{V}$-natural transformations, and for $\mathbf{V}=\mathbf{Set}$ it is the functor category of definition 61.5.4.

***Proof*:**
Write $E(F,G)=[\mathbf{C},\mathbf{D}](F,G)$ and let $\pi_c\colon E(F,G)\to\mathbf{D}(Fc,Gc)$ denote the composite of the equalizer inclusion with the projection at c.

Step 1: Composition. The componentwise composites

$$E(G,H)\otimes E(F,G)\xrightarrow{\pi_c\otimes\pi_c}\mathbf{D}(Gc,Hc)\otimes\mathbf{D}(Fc,Gc)\xrightarrow{\circ}\mathbf{D}(Fc,Hc)$$

are the components of a morphism into $\prod_c\mathbf{D}(Fc,Hc)$. It factors through the equalizer $E(F,H)$, and this is the one point needing argument. Transposing, the claim is that the two routes from $E(G,H)\otimes E(F,G)\otimes\mathbf{C}(c,c')$ to $\mathbf{D}(Fc,Hc')$ agree. Take the route carrying the composite component at c' backwards along F. Since $E(G,H)$ and $E(F,G)$ are equalizers, their own defining equations apply: the β-factor may be moved from "at c', transported along G" to "at c, transported along G" and then the α-factor from "at c' along F" to "at c along H". Concretely, insert $\mathbf{C}(c,c')$ between the two factors using symmetry, apply the equalizer equation of $E(F,G)$ to replace $\alpha_{c'}\circ F$ by $G\circ\alpha_c$, then apply the equalizer equation of $E(G,H)$ to replace $\beta_{c'}\circ G$ by $H\circ\beta_c$. The two applications are along different tensor factors, so they commute, and associativity of $\circ$ in $\mathbf{D}$ closes the square onto the second route. Hence the composite lands in $E(F,H)$.

Step 2: Identities. The morphisms $j_{Fc}\colon I\to\mathbf{D}(Fc,Fc)$ assemble into $I\to\prod_c\mathbf{D}(Fc,Fc)$, and this factors through $E(F,F)$: the two routes out of $I\otimes\mathbf{C}(c,c')$ are $\mathrm{id}_{Fc'}\circ F(f)$ and $F(f)\circ\mathrm{id}_{Fc}$, equal by the unit laws of $\mathbf{D}$. This gives $j_F\colon I\to E(F,F)$.

Step 3: The axioms. Associativity and the unit laws for the composition of Step 1 are equations between morphisms into $E(F,K)$, and the projections π_c out of an equalizer of a product are jointly monic, so it suffices to check them after each π_c. There they read as associativity and the unit laws of $\mathbf{D}$ at the object Fc, which hold by definition 68.1.1. So $[\mathbf{C},\mathbf{D}]$ is a $\mathbf{V}$-category.

Step 4: The underlying category and the **Set** *case.* By definition 68.1.2 the underlying category has hom-sets $\mathbf{V}(I,E(F,G))$, identified above with the $\mathbf{V}$-natural transformations $F\Rightarrow G$, and Steps 1 and 2 restrict to their usual composition and identities. For $\mathbf{V}=\mathbf{Set}$ the internal hom is the hom-set, the product is the cartesian product and the equalizer the subset on which the two functions agree, so $E(F,G)$ is the set of natural transformations and $[\mathbf{C},\mathbf{D}]$ is definition 61.5.4.

The construction is the ordinary functor category with two substitutions: the product of hom-sets becomes a product in $\mathbf{V}$, and the naturality condition, stated in the ordinary case as an equation

holding at each morphism, becomes the equalizer that imposes it. Everything else, composition and identities, is inherited componentwise from $\mathbf{D}$, which is why Step 3 reduces to axioms already available.

One base shows both constructions at once.

Example 68.3.5: Modules over a Ring as an Enriched Functor Category

Let R be a ring and let $\mathbf{R}$ be the $\mathbf{Ab}$-category with a single object $*$ and hom-object $\mathbf{R}(*,*) = R$, its composition the multiplication of R and its identity $j_*\colon \mathbb{Z} \to R$ the map sending 1 to 1_R. This is definition 68.1.1 over $\mathbf{V} = (\mathbf{Ab}, \otimes_{\mathbb{Z}}, \mathbb{Z})$, and the associativity and unit diagrams are the ring axioms.

An $\mathbf{Ab}$-functor $F\colon \mathbf{R} \to \mathbf{Ab}$ is an abelian group $M = F(*)$ together with a homomorphism $R \to \mathrm{Hom}_{\mathbb{Z}}(M,M)$ respecting multiplication and the unit, which is exactly a left R-module.

For two such, $F \leftrightarrow M$ and $G \leftrightarrow N$, definition 68.3.3 has a single-factor product $\mathrm{Hom}_{\mathbb{Z}}(M,N)$ and equalizes the two maps $\mathrm{Hom}_{\mathbb{Z}}(M,N) \to \mathrm{Hom}_{\mathbb{Z}}\big(R, \mathrm{Hom}_{\mathbb{Z}}(M,N)\big)$ sending f to $r \mapsto f \circ (r \cdot -)$ and to $r \mapsto (r \cdot -) \circ f$. Their equalizer is the subgroup of f with $f(rm) = rf(m)$, so

$$[\mathbf{R}, \mathbf{Ab}](F,G) \;=\; \mathrm{Hom}_R(M,N)$$

and proposition 68.3.4 says the left R-modules form an $\mathbf{Ab}$-category whose hom-objects are the R-linear maps. The $\mathbf{Ab}$-enrichment of R-modules that homological algebra takes as given is thus an instance of the enriched functor category.

With $[\mathbf{C}, \mathbf{V}]$ available, the enriched Yoneda lemma can be stated and proved. The ordinary statement (theorem 62.2.1) identified the natural transformations out of a representable with the elements of Fx; the enriched one identifies an object of $\mathbf{V}$ with an object of $\mathbf{V}$, and the proof is the same evaluation-at-the-identity argument written in $\mathbf{V}$.

Theorem 68.3.6: Enriched Yoneda Lemma

Let $\mathbf{C}$ be a small $\mathbf{V}$-category and $F\colon \mathbf{C} \to \mathbf{V}$ a $\mathbf{V}$-functor into the base. For each object x of $\mathbf{C}$ there is an isomorphism

$$[\mathbf{C}, \mathbf{V}]\big(\mathbf{C}(x,-),\, F\big) \;\cong\; Fx$$

of objects of $\mathbf{V}$, natural in x and in F. For $\mathbf{V} = \mathbf{Set}$ it is the bijection $\mathrm{Nat}(\mathrm{Hom}(x,-), F) \cong Fx$ of theorem 62.2.1.

***Proof*:**

Write $E = [\mathbf{C}, \mathbf{V}]\big(\mathbf{C}(x,-), F\big) = \int_y \big[\mathbf{C}(x,y), Fy\big]$, with $\pi_y\colon E \to [\mathbf{C}(x,y), Fy]$ the map of definition 68.3.3. Two morphisms are constructed and shown to be mutually inverse.

Step 1: The map $\psi\colon E \to Fx$. Take the component at $y = x$ and evaluate at the identity. The identity $j_x\colon I \to \mathbf{C}(x,x)$ induces $[\,j_x, Fx\,]\colon [\mathbf{C}(x,x), Fx] \to [I, Fx]$, and $[I, Fx] \cong Fx$ since I is the unit. Set $\psi = \big([\,j_x, Fx\,] \circ \pi_x\big)$ followed by that isomorphism.

Step 2: The map $\varphi\colon Fx \to E$. The $\mathbf{V}$-functor F gives $F_{x,y}\colon \mathbf{C}(x,y) \to [Fx, Fy]$, whose transpose under (67.1) is an action $\mathbf{C}(x,y) \otimes Fx \to Fy$. Transposing that in the other variable gives $\varphi_y\colon Fx \to [\mathbf{C}(x,y), Fy]$ for each y. These form a wedge: the equalizer condition of definition 68.3.3 at (y,z) is, after transposition, the assertion that acting by a morphism of $\mathbf{C}(y,z)$ after acting by one of $\mathbf{C}(x,y)$ agrees with acting by their composite, which is the

composition axiom of the $\mathbf{V}$-functor F. So the φ_y factor through E, defining φ.

Step 3: $\psi\varphi = \mathrm{id}_{Fx}$. Composing, $\psi\varphi$ is the transpose of $\mathbf{C}(x,x) \otimes Fx \to Fx$ precomposed with $j_x \otimes \mathrm{id}$, that is, the action of the identity. The unit axiom of the $\mathbf{V}$-functor F says $F_{x,x} \circ j_x = j_{Fx}$, and j_{Fx} is the transpose of the left unitor, so the action of the identity is λ and $\psi\varphi = \mathrm{id}$.

Step 4: $\varphi\psi = \mathrm{id}_E$. The projections π_z are jointly monic, so it suffices that $\pi_z\varphi\psi = \pi_z$ for every z. Transpose to morphisms $E \otimes \mathbf{C}(x,z) \to Fz$. Now take the equalizer equation of definition 68.3.3 at the pair (x,z) and transpose it to an equation between morphisms $E \otimes \mathbf{C}(x,z) \otimes \mathbf{C}(x,x) \to Fz$: one side applies π_x and then acts by $\mathbf{C}(x,z)$, the other composes $\mathbf{C}(x,z) \otimes \mathbf{C}(x,x) \to \mathbf{C}(x,z)$ and then applies π_z. Precompose both with $\mathrm{id}_E \otimes \mathrm{id} \otimes j_x$ and use the unit law of $\mathbf{C}$. The left side becomes the transpose of $\pi_z\varphi\psi$, since ψ is exactly π_x followed by evaluation at j_x and φ is the action; the right side becomes the transpose of π_z. Hence $\pi_z\varphi\psi = \pi_z$ for all z, and $\varphi\psi = \mathrm{id}_E$.

Step 5: Naturality. Naturality in F holds because ψ was built from π_x and j_x, neither of which involves F, so a $\mathbf{V}$-natural transformation $F \Rightarrow F'$ commutes with it by construction. Naturality in x follows from Step 4 read for the two objects together with the composition axiom of $\mathbf{C}$, in the same way that Step 2 used the composition axiom of F.

Nothing in the argument is new relative to theorem 62.2.1: Step 1 is "evaluate at id_x", Step 2 is "transport along the action", and Steps 3 and 4 are the two round trips. What the enrichment changes is that each step is a morphism of $\mathbf{V}$ rather than a function on elements, and the naturality condition that was a family of equations is now the equalizer through which the maps must factor. Setting $\mathbf{V} = \mathbf{Set}$ collapses every internal object to a set and returns the original proof verbatim.

The last definition of the chapter's enriched material unifies the two constructions above. An ordinary limit is a universal cone, and a cone over F with vertex d is a natural transformation from the constant functor at a point into $\mathrm{Hom}(d, F-)$. Nothing requires the constant functor: any $\mathbf{V}$-functor W may take its place, and the resulting notion is strictly more general because W may assign different objects of $\mathbf{V}$ to different objects of $\mathbf{C}$.

Definition 68.3.7: Weighted Limit and Weighted Colimit

Let $\mathbf{C}$ be a small $\mathbf{V}$-category, $\mathbf{D}$ a $\mathbf{V}$-category and $F\colon \mathbf{C} \to \mathbf{D}$ a $\mathbf{V}$-functor. For a *weight* $W\colon \mathbf{C} \to \mathbf{V}$, the *limit of F weighted by W* is an object $\lim^W F$ of $\mathbf{D}$ with an isomorphism

$$\mathbf{D}\big(d,\ \lim^W F\big) \ \cong\ [\mathbf{C},\mathbf{V}]\big(W,\ \mathbf{D}(d, F-)\big)$$

of objects of $\mathbf{V}$, natural in d. For a weight $W\colon \mathbf{C}^{\mathrm{op}} \to \mathbf{V}$, the *colimit of F weighted by W*, written $W \star F$, is an object with

$$\mathbf{D}\big(W \star F,\ d\big) \ \cong\ [\mathbf{C}^{\mathrm{op}},\mathbf{V}]\big(W,\ \mathbf{D}(F-, d)\big)$$

natural in d. Here $\mathbf{C}^{\mathrm{op}}$ is the $\mathbf{V}$-category with the same objects, hom-objects $\mathbf{C}^{\mathrm{op}}(c,c') = \mathbf{C}(c',c)$, and composition that of $\mathbf{C}$ precomposed with the symmetry σ.

Both are representing objects, so both are unique up to canonical isomorphism when they exist. The weight is the diagram's shape data: where an ordinary cone offers one morphism $d \to Fc$ for each c, a W-weighted cone offers an object Wc worth of them, and the naturality built into $[\mathbf{C},\mathbf{V}]$ requires those to be compatible along the morphisms of $\mathbf{C}$. The definition of $\mathbf{C}^{\mathrm{op}}$ is where symmetry of $\mathbf{V}$ is needed, since reversing composition means feeding $\circ$ its two arguments in the opposite order.

Example 68.3.8: Three Weighted Limits

1. *Ordinary limits are the constant weight.* Take $\mathbf{V} = \mathbf{Set}$ and W the constant functor at the one-point set. Then $[\mathbf{C}, \mathbf{Set}]\big(W, \mathrm{Hom}(d, F-)\big)$ is the set of natural transformations from the constant functor into $\mathrm{Hom}(d, F-)$, which is the set of cones over F with vertex d. The defining isomorphism becomes $\mathrm{Hom}(d, \lim^W F) \cong \{\text{cones with vertex } d\}$, the universal property of the ordinary limit. Definition 63.2.1 is thus the special case in which every object of $\mathbf{C}$ carries the same one-point weight.

2. *Tensors and cotensors are weighted (co)limits.* Let $\mathbf{I}$ be the unit $\mathbf{V}$-category, one object $*$ with $\mathbf{I}(*,*) = I$. A $\mathbf{V}$-functor $F\colon \mathbf{I} \to \mathbf{D}$ is an object c of $\mathbf{D}$, and a weight $W\colon \mathbf{I} \to \mathbf{V}$ is an object v of $\mathbf{V}$. Unwinding definition 68.3.7, the products in definition 68.3.3 have one factor and the equalizer is trivial, so the defining isomorphism reads $\mathbf{D}(d, \lim^W F) \cong [v, \mathbf{D}(d,c)]$, which is definition 68.3.1: $\lim^W F = c^v$ and dually $W \star F = v \odot c$.

3. *Tensor product of modules.* In the setting of example 68.3.5, a weight $W\colon \mathbf{R}^{\mathrm{op}} \to \mathbf{Ab}$ is a right R-module and F a left R-module M. For an abelian group A, the group $\mathrm{Hom}_{\mathbb{Z}}(M, A)$ is a right R-module by $(f \cdot r)(m) = f(rm)$, and the defining isomorphism reads

$$\mathrm{Hom}_{\mathbb{Z}}(W \star F,\ A) \ \cong\ \mathrm{Hom}_{R^{\mathrm{op}}}\big(W,\ \mathrm{Hom}_{\mathbb{Z}}(M, A)\big)$$

   the right-hand side being the right R-module maps, by example 68.3.5 applied to $\mathbf{R}^{\mathrm{op}}$. That is the universal property of $W \otimes_R M$, so $W \star F = W \otimes_R M$: the tensor product over a ring is a weighted colimit.

Three constructions that arose separately, the limit of a diagram, the power of an object and the tensor product of two modules, are one construction read over three bases with three weights. The generality is used again once homotopy enters: a homotopy limit is a weighted limit whose weight is built from simplicial sets, and the two-sided bar construction computing it is a weighted colimit. Both are developed in *Higher Category Theory* [27], which takes definition 68.3.7 as given.

68.4 Strict 2-Categories

The enriching base of the preceding sections has been an arbitrary monoidal category $\mathbf{V}$. Take $\mathbf{V} = \mathbf{Cat}$, and a $\mathbf{V}$-category acquires an extra layer of morphisms: each hom-object is now itself a category, so between two arrows there sit arrows-of-arrows. This is the setting in which the natural transformation lives on the same footing as the functor, and in which the adjunction of definition 64.1.1 and the monad of definition 65.1.1 become structures one can name on any object at all. This section makes the extra layer explicit, gives it its own composition laws, and identifies it with the **Cat**-enriched case of definition 68.1.1.

Definition 68.4.1: Strict 2-Category

A *strict 2-category* $\mathbf{K}$ consists of

- a class of 0-*cells* (or *objects*) $A, B, C, \ldots$;
- for each ordered pair A, B of 0-cells, a class of 1-*cells* $f\colon A \to B$;
- for each parallel pair $f, g\colon A \to B$ of 1-cells, a class of 2-*cells* $\alpha\colon f \Rightarrow g$,

together with two ways of composing 2-cells. *Vertical composition* takes 2-cells sharing a 1-cell boundary,

$$\alpha\colon f \Rightarrow g, \qquad \beta\colon g \Rightarrow h,$$


to a 2-cell $\beta \cdot \alpha\colon f \Rightarrow h$; *horizontal composition* takes 2-cells sharing a 0-cell boundary,

$$\alpha\colon f \Rightarrow g \ (A \to B), \qquad \alpha'\colon f' \Rightarrow g' \ (B \to C),$$


to a 2-cell $\alpha' \circ \alpha\colon f'f \Rightarrow g'g \ (A \to C)$. Both compositions are strictly associative and unital: vertical composition has, for each 1-cell f, an identity 2-cell $1_f\colon f \Rightarrow f$; horizontal composition has, for each 0-cell A, an identity 2-cell 1_{id_A} on the identity 1-cell id_A. The two compositions are compatible through the *interchange law*: whenever the composites are defined,

$$(\beta' \cdot \alpha') \circ (\beta \cdot \alpha) = (\beta' \circ \beta) \cdot (\alpha' \circ \alpha) \tag{68.1}$$


The two compositions are pictured most cleanly by drawing 1-cells as arrows and 2-cells as double arrows between them. Vertical composition stacks two 2-cells inside a single hom-class $\mathbf{K}(A, B)$:



Horizontal composition pastes two 2-cells along a shared 0-cell B:



The interchange law is the assertion that the four-fold pasting diagram



evaluates to a single 2-cell $f'f \Rightarrow h'h$, no matter whether one first composes vertically within each column and then horizontally across, or first composes horizontally within each row and then vertically down. Equation (68.1) says the two readings agree. This is the one axiom that couples the two operations; associativity and unitality govern each in isolation.

The definition looks like a bookkeeping exercise until one reads it through the lens of section 68.1. Assemble, for each pair A, B, the 1-cells $A \to B$ as objects and the 2-cells between them as morphisms; vertical composition makes this data a category $\mathbf{K}(A, B)$, its identities the 1_f. Horizontal composition of 1-cells and of 2-cells then assembles into functors $\mathbf{K}(B, C) \times \mathbf{K}(A, B) \to \mathbf{K}(A, C)$, and the interchange law is exactly the statement that horizontal composition respects the categorical structure of each factor, that is, that it is a functor on the product and not only a function on objects. This is the hinge of the section.

Proposition 68.4.2: 2-Categories are Cat-enriched Categories

A strict 2-category is exactly a category enriched over $(\mathbf{Cat}, \times, \mathbf{1})$ in the sense of definition 68.1.1: the hom-object $\mathbf{K}(A, B)$ is the category whose objects are the 1-cells $A \to B$ and whose morphisms are the 2-cells between them.

***Proof*:**
Fix the correspondence between the two packages of data and check that the axioms match term by term.

From a 2-category to enrichment. Given a strict 2-category $\mathbf{K}$, for each pair A, B let $\mathbf{K}(A, B)$ be the category with the 1-cells $A \to B$ as objects, the 2-cells as morphisms, and vertical composition as composition; associativity and unitality of vertical composition are precisely the category axioms, with 1_f the identity on f. Horizontal composition assigns to a pair of objects (f', f) the object $f'f$ and to a pair of 2-cells (α', α) the 2-cell $\alpha' \circ \alpha$. That this assignment is a functor

$$c_{A,B,C} \colon \mathbf{K}(B, C) \times \mathbf{K}(A, B) \to \mathbf{K}(A, C)$$

is the content of the interchange law (68.1): it sends the identity morphism $(1_{f'}, 1_f)$ to $1_{f'f}$, which is unitality of horizontal composition, and it respects composition of morphisms in the product category, where composition is componentwise vertical, so functoriality is the equation $(\beta' \cdot \alpha') \circ (\beta \cdot \alpha) = (\beta' \circ \beta) \cdot (\alpha' \circ \alpha)$ of (68.1). The identity 1-cell id_A together with 1_{id_A} is a functor $\mathbf{1} \to \mathbf{K}(A, A)$ from the terminal category, the unit map of the enrichment. Associativity and unitality of horizontal composition of 1-cells become the associativity and unit diagrams required of an enriched category.

From enrichment to a 2-category. Conversely, a $\mathbf{Cat}$-enriched category gives for each pair a category $\mathbf{K}(A, B)$: its objects are declared the 1-cells, its morphisms the 2-cells, its composition the vertical composition. The composition functors $c_{A,B,C}$ act on objects to give horizontal composition of 1-cells and on morphisms to give horizontal composition of 2-cells; functoriality of $c_{A,B,C}$ is the interchange law, and the enriched associativity and unit axioms are the associativity and unitality of horizontal composition. The two passages are mutually inverse, matching each datum and each axiom, so the two notions coincide, as we sought to show.

The proposition is the reason the tensor product $\times$ on $\mathbf{Cat}$ mattered. An ordinary category is enriched over $(\mathbf{Set}, \times)$; promoting the enriching base one level, from sets to categories, adds exactly one dimension of morphism and produces the strict 2-category. The interchange law is not an extra

decoration but the naturality already built into enrichment, read in the base **Cat**. Every general fact about $\mathbf{V}$-categories from section 68.1 specializes: a 2-category has an underlying ordinary category $\mathbf{K}_0$ (definition 68.1.2), obtained by discarding the 2-cells and keeping only the 0-cells and 1-cells, since $\mathbf{Cat}(\mathbf{1}, \mathbf{K}(A,B))$ is the set of objects of $\mathbf{K}(A,B)$, namely the 1-cells $A \to B$.

The definition of a 2-category was abstracted from one example, in which all three layers of cell are already familiar and the two compositions of 2-cells have standing names.

Example 68.4.3: Cat as a 2-Category
Let **Cat** denote the 2-category whose

- 0-cells are (small) categories $\mathbf{C}, \mathbf{D}, \ldots$;
- 1-cells $F \colon \mathbf{C} \to \mathbf{D}$ are functors (definition 61.4.1);
- 2-cells $\alpha \colon F \Rightarrow G$ are natural transformations (definition 61.5.2) between parallel functors.

The hom-object $\mathbf{Cat}(\mathbf{C}, \mathbf{D})$ is the functor category $[\mathbf{C}, \mathbf{D}]$ (definition 61.5.4). Vertical composition is the composition of natural transformations: for $\alpha \colon F \Rightarrow G$ and $\beta \colon G \Rightarrow H$, the transformation $\beta \cdot \alpha$ has component $(\beta \cdot \alpha)_c = \beta_c \circ \alpha_c$ at each object c. Horizontal composition is the Godement product: for $\alpha \colon F \Rightarrow G$ between functors $\mathbf{C} \to \mathbf{D}$ and $\alpha' \colon F' \Rightarrow G'$ between functors $\mathbf{D} \to \mathbf{E}$, the component of $\alpha' \circ \alpha$ at $c \in \mathbf{C}$ is the common value of the two paths around the naturality square of α' at α_c:

$$(\alpha' \circ \alpha)_c = G'(\alpha_c) \circ \alpha'_{Fc} = \alpha'_{Gc} \circ F'(\alpha_c) \tag{68.2}$$

The interchange law is the middle-four exchange for natural transformations.

The two expressions in (68.2) are equal precisely because $\alpha' \colon F' \Rightarrow G'$ is natural: applied to the arrow $\alpha_c \colon Fc \to Gc$ of $\mathbf{D}$, naturality of α' is the commuting square

$$\begin{array}{ccc} F'Fc & \xrightarrow{\alpha'_{Fc}} & G'Fc \\ {\scriptstyle F'(\alpha_c)}\downarrow & & \downarrow{\scriptstyle G'(\alpha_c)} \\ F'Gc & \xrightarrow[\alpha'_{Gc}]{} & G'Gc \end{array}$$

whose two directed paths from $F'Fc$ to $G'Gc$ are the two formulas for $(\alpha' \circ \alpha)_c$. That **Cat** satisfies the axioms of definition 68.4.1 is the content of proposition 68.4.2 together with the fact that $[\mathbf{C}, \mathbf{D}]$ is a category (definition 61.5.4) and that these composites are natural. The interchange law $(\beta' \cdot \alpha') \circ (\beta \cdot \alpha) = (\beta' \circ \beta) \cdot (\alpha' \circ \alpha)$ is verified componentwise from (68.2) by a direct diagram chase; it is the classical middle-four exchange, so named because the four inner terms of the two sides pair off.

A frequent special case of horizontal composition fixes one of the two 2-cells to be an identity. This is common enough, and geometrically clean enough, to deserve its own name.

Definition 68.4.4: Whiskering

Let $\alpha\colon f \Rightarrow g$ be a 2-cell between 1-cells $f, g\colon A \to B$ in a 2-category $\mathbf{K}$. Given a 1-cell $h\colon B \to C$, the *left whiskering* of α by h is the horizontal composite of α with the identity 2-cell on h,

$$h * \alpha \coloneqq 1_h \circ \alpha\colon hf \Rightarrow hg,$$

a 2-cell between 1-cells $A \to C$. Given a 1-cell $k\colon Z \to A$, the *right whiskering* of α by k is

$$\alpha * k \coloneqq \alpha \circ 1_k\colon fk \Rightarrow gk,$$

a 2-cell between 1-cells $Z \to B$.

Pictorially, whiskering appends a 1-cell to one side of the 2-cell α without introducing a second nondegenerate 2-cell:



In **Cat**, where $\alpha\colon F \Rightarrow G$ is a natural transformation and H a functor, left whiskering $H * \alpha$ has component $(H * \alpha)_c = H(\alpha_c)$ at each object c, obtained by applying H to each component of α; right whiskering $\alpha * K$ has component $(\alpha * K)_z = \alpha_{Kz}$, obtained by reindexing α along K. Every horizontal composite factors through whiskering: for $\alpha\colon F \Rightarrow G$ and $\alpha'\colon F' \Rightarrow G'$ as in (68.2),

$$\alpha' \circ \alpha = (G' * \alpha) \cdot (\alpha' * F) = (\alpha' * G) \cdot (F' * \alpha),$$

the two factorizations being the two paths of the naturality square, so the two whiskerings together with vertical composition recover the full Godement product. Whiskering is therefore the elementary operation from which horizontal composition is built, and it is the notation in which the constructions below are cleanest.

With the two compositions and whiskering in hand, one can transcribe the central notions of the core theory into any 2-category, referring only to 0-, 1-, and 2-cells and never to elements. The payoff is that an adjunction (definition 64.1.1) and a monad (definition 65.1.1) become structures an object can carry in any $\mathbf{K}$, of which the definitions of the earlier chapters are the **Cat** case.

Proposition 68.4.5: Adjunctions and Monads in a 2-Category

Let $\mathbf{K}$ be a 2-category.

1. An *adjunction* in $\mathbf{K}$ consists of 1-cells $f\colon A \to B$ and $g\colon B \to A$ and 2-cells $\eta\colon \mathrm{id}_A \Rightarrow gf$ and $\varepsilon\colon fg \Rightarrow \mathrm{id}_B$ satisfying the triangle identities
$$(\varepsilon * f) \cdot (f * \eta) = 1_f, \qquad (g * \varepsilon) \cdot (\eta * g) = 1_g \tag{68.3}$$
2. A *monad* on an object A consists of a 1-cell $t\colon A \to A$ and 2-cells $\eta\colon \mathrm{id}_A \Rightarrow t$ and $\mu\colon tt \Rightarrow t$ satisfying the associativity and unit laws
$$\mu \cdot (\mu * t) = \mu \cdot (t * \mu), \qquad \mu \cdot (\eta * t) = 1_t = \mu \cdot (t * \eta) \tag{68.4}$$
3. Every adjunction in $\mathbf{K}$ induces a monad on A, with underlying 1-cell $t = gf$, unit the adjunction unit η, and multiplication $\mu = g * \varepsilon * f\colon gfgf \Rightarrow gf$.

In $\mathbf{K} = \mathbf{Cat}$, an adjunction is an adjunction of functors in the sense of definition 64.1.1 with unit and counit as in definition 64.1.3, a monad is a monad in the sense of definition 65.1.1, and the induced monad of part (3) is the monad an adjunction of functors induces on its source.

***Proof*:**
Parts (1) and (2) are definitions internal to $\mathbf{K}$; the content is part (3), that the data they package assemble into a monad, and that in $\mathbf{Cat}$ everything reduces to the earlier chapters.

Step 1: The induced multiplication and unit. From an adjunction $(f, g, \eta, \varepsilon)$ set $t = gf$. Left whiskering by g and right whiskering by f turn the counit $\varepsilon\colon fg \Rightarrow \mathrm{id}_B$ into a 2-cell
$$\mu = g * \varepsilon * f\colon gfgf \Rightarrow gf,$$
that is, $\mu\colon tt \Rightarrow t$, where $g*\varepsilon*f$ abbreviates the whiskering $g*(\varepsilon*f) = (g*\varepsilon)*f$ (associativity of horizontal composition makes the two readings equal). The unit of the monad is the adjunction unit $\eta\colon \mathrm{id}_A \Rightarrow t$.

Step 2: The unit laws. The two unit laws in (68.4) are the two triangle identities (68.3), whiskered into place. Whisker the first triangle identity $(\varepsilon * f) \cdot (f * \eta) = 1_f$ on the left by g: using functoriality of whiskering with respect to vertical composition,
$$(g * \varepsilon * f) \cdot (gf * \eta) = 1_{gf},$$
and since $t * \eta = gf * \eta$ and $\mu = g * \varepsilon * f$, this reads $\mu \cdot (t * \eta) = 1_t$. Whiskering the second triangle identity $(g * \varepsilon) \cdot (\eta * g) = 1_g$ on the right by f gives, by the same computation, $\mu \cdot (\eta * t) = 1_t$. Together these are the unit laws.

Step 3: Associativity. Both sides of $\mu \cdot (\mu * t) = \mu \cdot (t * \mu)$ are 2-cells $ttt \Rightarrow t$, that is, $gfgfgf \Rightarrow gf$. Expand using $\mu = g * \varepsilon * f$ and $t = gf$: the left side, $\mu \cdot (\mu * gf)$, whiskers the outer copy of ε over the inner one on the left, while the right side, $\mu \cdot (gf * \mu)$, whiskers on the right; the two inner whiskerings apply ε at the two different copies of the pair fg in $fgfg$. Both reduce to a single whiskered double application of the counit,
$$g * (\varepsilon \circ \varepsilon) * f\colon gfgfgf \Rightarrow gf,$$

where $\varepsilon \circ \varepsilon \colon fgfg \Rightarrow \mathrm{id}_B$ is the horizontal composite of ε with itself. That this horizontal composite is unambiguous, that whiskering the outer ε over the inner one on the left equals whiskering it on the right, is precisely the interchange law (68.1) applied to the two copies of ε: $(\varepsilon \circ 1_{\mathrm{id}_B}) \cdot (1_{fg} \circ \varepsilon) = (\varepsilon \circ \varepsilon) = (1_{\mathrm{id}_B} \circ \varepsilon) \cdot (\varepsilon \circ 1_{fg})$. Hence the two sides agree and (t, η, μ) satisfies (68.4), a monad on A.

Step 4: The **Cat** *case.* Take $\mathbf{K} = \mathbf{Cat}$. A 1-cell $f \colon A \to B$ is a functor, a 2-cell is a natural transformation, and the triangle identities (68.3), read componentwise via the whiskering formulas $(H * \alpha)_c = H(\alpha_c)$ and $(\alpha * K)_z = \alpha_{Kz}$ of definition 68.4.4, are exactly the triangle identities of definition 64.1.3: at an object a the first reads $\varepsilon_{fa} \circ f(\eta_a) = \mathrm{id}_{fa}$. So an adjunction in **Cat** is an adjunction of functors (definition 64.1.1). Likewise $t = gf$ is the composite endofunctor, and the multiplication $\mu = g * \varepsilon * f$ has component $\mu_a = g(\varepsilon_{fa})$ at $a \in A$, which is the multiplication of the monad an adjunction of functors induces (definition 65.1.1). The construction of part (3) used only 2-cells, whiskering, and the interchange law, which is why the derivation for **Cat** was, without saying so, purely 2-categorical. This completes the proof.

The proposition is the abstract residue of the monad theory of the core chapters. The construction of a monad from an adjunction (definition 65.1.1) never touched an element of an object; it composed the counit with functors on the left and right and invoked naturality, and those are exactly whiskering and the interchange law. Reread through proposition 68.4.5, that construction proved a fact about **Cat** that holds verbatim in any 2-category: the endomorphism gf of the source of any adjunction carries a canonical monad structure. The same transcription runs the other way for the Eilenberg-Moore and Kleisli constructions (section 65.2, section 65.3), which recover an adjunction from a monad by building new objects, and it is the systematic version of this dictionary, one layer of categorical structure at a time, that the sequel takes up.

68.5 Toward Weak and Higher Categories

A strict 2-category asks the composition of 1-cells to be strictly associative and strictly unital, exactly as in an ordinary category. In the archetype **Cat** this holds on the nose. But many of the 2-dimensional structures that arise in practice do not: composing 1-cells there produces objects that are associative and unital only *up to* a specified invertible 2-cell, and one cannot wish those 2-cells away without discarding the mathematics that forced them. The passage from the strict laws of definition 68.4.1 to laws-up-to-coherent-isomorphism is the last structural step this book takes, and it is the door to the sequel.

The relaxation is governed by exactly the coherence discipline of chapter 67. There the associator and unitors of a monoidal category were required to satisfy the pentagon and triangle axioms, and Mac Lane's coherence theorem (theorem 67.1.5) guaranteed that every formal diagram then commutes. A bicategory imports that discipline one dimension up: the associativity and unit *equalities* of 1-cell composition become invertible 2-cells subject to a pentagon and a triangle, and the same kind of coherence theorem results.

Definition 68.5.1: Bicategory

A *bicategory* $\mathbf{B}$ consists of

- a collection of *0-cells* (objects) $A, B, C, \dots$;
- for each ordered pair (A, B) a category $\mathbf{B}(A, B)$, whose objects are the *1-cells* $f\colon A \to B$ and whose morphisms are the *2-cells* $\alpha\colon f \Rightarrow g$ (composition within $\mathbf{B}(A, B)$ is *vertical* composition of 2-cells);
- for each triple (A, B, C) a *horizontal composition* functor
$$\circ\colon \mathbf{B}(B, C) \times \mathbf{B}(A, B) \to \mathbf{B}(A, C)$$
and for each A an identity 1-cell $\mathrm{id}_A \in \mathbf{B}(A, A)$;
- for all composable 1-cells f, g, h a natural *associator* 2-cell
$$a_{h,g,f}\colon (h \circ g) \circ f \;\Rightarrow\; h \circ (g \circ f)$$
and for each $f\colon A \to B$ natural *left* and *right unitor* 2-cells
$$\lambda_f\colon \mathrm{id}_B \circ f \Rightarrow f, \qquad \rho_f\colon f \circ \mathrm{id}_A \Rightarrow f$$
each of which is invertible,

subject to two coherence axioms: the *pentagon*, requiring that the two ways of reassociating a fourfold composite $((k \circ h) \circ g) \circ f$ to $k \circ (h \circ (g \circ f))$ agree, that is

$$(\mathrm{id}_k \circ a_{h,g,f}) \cdot a_{k,h\circ g,f} \cdot (a_{k,h,g} \circ \mathrm{id}_f) \;=\; a_{k,h,g\circ f} \cdot a_{k\circ h,g,f}$$

(where $\cdot$ is vertical composition and $\circ$ here denotes whiskering, definition 68.4.4); and the *triangle*, requiring for composable $g\colon B \to C$, $f\colon A \to B$ that

$$(\mathrm{id}_g \circ \lambda_f) \cdot a_{g,\mathrm{id}_B,f} \;=\; \rho_g \circ \mathrm{id}_f$$

A *strict 2-category* (definition 68.4.1) is the special case in which a, λ, and ρ are all identity 2-cells.

The two axioms are the pentagon and triangle of theorem 67.1.5, transplanted from the 1-cells of a monoidal category to the 1-cells of $\mathbf{B}$. This is not an analogy imposed after the fact: a bicategory with a single 0-cell is precisely a monoidal category, its one hom-category $\mathbf{B}(A, A)$ being the underlying category, horizontal composition the tensor, id_A the unit, and a, λ, ρ the monoidal associator and unitors. A bicategory is thus a monoidal category with many objects, and the coherence data is the same data seen one dimension higher.

The force of the pentagon and triangle is again a coherence theorem, which frees the working mathematician from tracking associators and unitors explicitly.

Theorem 68.5.2: Coherence for Bicategories

Every bicategory is biequivalent to a strict 2-category. Consequently, in any bicategory every diagram of 2-cells built from associators, unitors, their inverses, whiskerings, and identities commutes.

***Proof Key ideas*:**
The statement, and the notion of biequivalence it uses, belong to the weak 2-dimensional theory developed in the sequel; the full argument is beyond the light treatment here. The mechanism mirrors the strictification of a monoidal category behind theorem 67.1.5: one embeds $\mathbf{B}$ into a strict 2-category of $\mathbf{B}$-representations by a bicategorical Yoneda construction, sending each 0-cell to a strict object whose 1-cells compose on the nose, and checks the embedding is a biequivalence. A complete proof is given in the sequel ([27]) and in Mac Lane's and Bénabou's original treatments, to which the details are deferred.

Coherence has a practical consequence worth stating plainly: a bicategory may be manipulated as though it were strict. Parenthesization of a composite of 1-cells can be suppressed, and any two reassociations of the same string are identified by a canonical invertible 2-cell. The weakness is real, but coherence renders it invisible in computation, precisely as in the monoidal case.

The examples that make bicategories necessary are the ones where the associator fails to be an identity. Two are canonical.

Example 68.5.3: The Bicategory of Bimodules

Bimodules. Let **Bimod** have as 0-cells the (unital, associative) rings. A 1-cell $R \to S$ is an (S,R)-bimodule ${}_SM_R$, that is, an abelian group carrying commuting left S- and right R-actions ([21, (S,R)-Bimodule]). A 2-cell ${}_SM_R \Rightarrow {}_SN_R$ is a bimodule homomorphism. Vertical composition is composition of bimodule maps, so $\mathbf{Bimod}(R,S)$ is the category of (S,R)-bimodules.

Horizontal composition is the tensor product over the middle ring: the composite of $R \xrightarrow{M} S$ and $S \xrightarrow{N} T$ is the (T,R)-bimodule

$$N \circ M \;=\; N \otimes_S M$$

The identity 1-cell on R is the bimodule ${}_RR_R$, since $R \otimes_R M \cong M$ and $M \otimes_R R \cong M$ naturally.

Here associativity is not an equality. For bimodules ${}_SM_R$, ${}_TN_S$, ${}_UP_T$ the two triple tensor products

$$(P \otimes_T N) \otimes_S M \qquad \text{and} \qquad P \otimes_T (N \otimes_S M)$$


are distinct abelian groups: their elements are cosets in different quotients of $P \otimes N \otimes M$. They are canonically isomorphic by $(p \otimes n) \otimes m \mapsto p \otimes (n \otimes m)$, and this isomorphism is the associator $a_{P,N,M}$; it is invertible but not the identity. The unitors are the canonical maps $R \otimes_R M \cong M$ and $M \otimes_R R \cong M$. That these satisfy the pentagon and triangle is the statement that the standard tensor-product isomorphisms cohere, which they do because each is built from the universal property of $\otimes$. Thus **Bimod** is a bicategory that is not a strict 2-category, and no reasonable change of definition makes it one: the tensor product of bimodules is associative up to canonical isomorphism and no more.

The second canonical example needs only a category with pullbacks, and it shows the same phenomenon geometrically rather than algebraically.

Example 68.5.4: The Bicategory of Spans

Let $\mathbf{C}$ be a category with pullbacks. A *span* from A to B is a diagram $A \leftarrow S \rightarrow B$, an object S with a leg to each of A and B; this is a 1-cell $A \to B$. A 2-cell between spans $A \leftarrow S \rightarrow B$ and $A \leftarrow S' \rightarrow B$ is a morphism $S \to S'$ commuting with both legs.

Horizontal composition composes spans by pullback. Given $A \leftarrow S \rightarrow B$ and $B \leftarrow T \rightarrow C$, form the pullback $S \times_B T$ of the two legs over B (definition 63.2.6):



The composite span $A \leftarrow S \times_B T \rightarrow C$ takes the outer legs. The identity 1-cell on A is the span $A \xleftarrow{\mathrm{id}} A \xrightarrow{\mathrm{id}} A$.

Associativity again holds only up to isomorphism. Composing three spans in the two possible orders forms two iterated pullbacks, $(S \times_B T) \times_C U$ and $S \times_B (T \times_C U)$; these are canonically isomorphic because both compute the limit of the same diagram, but the isomorphism is given by the universal property of the pullback and is not an identity. It is the associator, and the pentagon it satisfies is exactly the coherence of iterated pullback limits. So $\mathbf{Span}(\mathbf{C})$ is a bicategory, strict only in the degenerate cases where pullbacks can be chosen strictly functorially.

In both examples the weakness is not a defect of the definition to be engineered away but a feature of the mathematics: tensor product and pullback are operations defined by universal properties, and a universal property determines its output only up to canonical isomorphism. Any 2-dimensional structure organized by such operations is a bicategory and not, on the nose, a strict 2-category. The equalities of definition 68.4.1 were an idealization; the isomorphisms of definition 68.5.1 are what the objects satisfy.

This is where strictness gives way to coherence, and where the present book ends. Everything developed here has been strict 1-category theory. Composition of morphisms is strictly associative and strictly unital; a diagram commutes or it does not; two objects are the same when they are equal or, at the outermost, when they are isomorphic. Sameness has meant equality or isomorphism, and nothing weaker. The structured categories of the last two chapters have pushed against that boundary, introducing associators and unitors as data, but coherence has kept them tame: by theorem 67.1.5 and theorem 68.5.2 the strict theory recovers the weak one up to equivalence, and the strict picture remains adequate.

The subject changes character when equality weakens past this point. When the associativity of composition is asked to hold only up to a coherent *homotopy*, and that homotopy up to a further homotopy, and so on through every dimension, one is no longer doing strict 1-category theory but *higher category theory*. There the objects of study are model categories, quasi-categories, and ∞-categories, in which morphisms compose only up to coherent higher cells and the coherence data is infinite rather than a single pentagon. The theorems of this book do not disappear beyond it; they reappear in homotopy-coherent form. Limits and colimits become homotopy limits and colimits, taken up to coherent equivalence rather than on the nose. Adjunctions, monads, and the Yoneda lemma each have ∞-categorical statements that specialize back to the strict ones proved here. The

duality principle of box 61.3.3 survives verbatim, opposite ∞-categories and all.

The sequel is *Higher Category Theory* ([27]), which takes up simplicial sets and nerves, Quillen's model categories, the quasi-category model of ∞-categories after Joyal, Lurie, and Riehl, homotopy (co)limits, and the stable and derived structures that connect back to homological algebra. It is the natural continuation for a reader who now recognizes a universal property on sight and wants to see what becomes of these constructions when equality is replaced throughout by coherent equivalence. The strict theory built here is the ground from which that generalization is read.

Part XIII

Appendix

In the appendix, certain section will take liberties on how much the reader know's. In particular, the reader is expected to be comfortable with (some analysis or topology in certain appendicies, like category theory and geometric group theory).

A

Axiom of Choice

In mathematics, we are constantly making choices. We can make algorithmic choices (for example, if you are given the number n, choose the number $n+1$), or we make arbitrary choices (choose some natrual number n). The fact that we can make an arbitrary choice is uncontroversial in the axioms mathematicians used, that is ZF (short for Zermelo-Frankel axioms). So too is making a finite number of choices. These two "abilities" were also uncontroversial in other foundational formulations of mathematics, not just ZF. It might seem very natural then to be able to make an infinite, or more generally an arbitrary (including uncountably infinite or other cardinalities) amount of choices. However, making an arbitrary amount of choices turns out to have some very strange consequences. The German mathematician Ernst Zermelo axiomatically used the fact that you can make an arbitrary number of choices (which we will soon define what this means mathematically) to prove a very controversial conjecture called the *well-ordering Theorem* (which we shall cover later in this appendix), sparking a debate on whether mathematics should allow for arbitrary choice. One famous "counter-example" developed to "prove" that we should not allow arbitray choice is a proof by Banach and Tarski that you can take a sphere, partition it into 6 subsets (which uses the axiom of choice), rotate them in certain ways, and recombine them to form 2 identical spheres! Importantly, we did *not* add any more points, yet we have somehow "doubled" the surface area of the points we have chosen [1]! This is called the *Banach-Tarski Paradox*.

Though this result is strange, as time went on, more and more mathematicians found that making an arbitrary number of choices produces some "natural" results. For example, the fact that every vector-space has a basis comes down to the ability of making an arbitrary number of choices. In 1963, a mathematician named Paul Cohen proved that the making an arbitrary number of choices is independent of the standard system of axioms ZF, meaning if we assume the we can do an arbitrary number of choices, it will not cause any more contradiction and ZF would already cause [2], and if we

[1] For those who have taken measure theory, the chosen subsets turn out to be *unmeasurable* sets, and so the concept of surface area does not apply to these sets which allows us to produce this strange result

[2] The careful wording here is because it has *not* been proven that the axioms of ZF do not contradict each other –

assume we cannot make an arbitrary number of choices, it will *also* not cause any more contradiction than ZF would already cause. Through this result, most mathematicians now accept the axiom of choice as part of the standard model we use, which is represented as ZFC (ZF + the axiom of **C**hoice).

In Algebra, the axiom of choice most often appears in a special form called *Zorn's Lemma*. The aim of this chapter is to be able show that Zorn's lemma is equivalent to the axiom of choice.

A.1 Build-up

Definition A.1.1: Cartesian Product and Choice Function

Let $\{A_i\}_{i\in I}$ be any family of sets. Then the *Cartesian product* of this family, written $\prod_{i\in I} A_i$, is the set of all function $x : I \to \bigcup_{i\in I} A_i$, where $x(i) \in A_i$ for all $i \in I$ The function x is called a *choice function*.

Though we have defined what the cartesian product is, it does not mean that the function x exist! Naturally, if $I = \emptyset$ or if $A_i = \emptyset$ for some $i \in I$ (since then $\prod_{i\in I} A_i = \emptyset$), then this function exists. If $I \neq \emptyset$ or $A_i \neq \emptyset$, then it turns out the existence of this function is independent of the ZF axioms! Thus, the axiom of choice was formulated:

Axiom A.1.2: Axiom of Choice

The cartesian product of any non-empty family of non-empty sets is a non-empty set. In particular, if $\{A_i\}_{i\in I}$ is a family of sets such that $I \neq \emptyset$ and $A_i \neq \emptyset$ for each $i \in I$, then there exists at least one choice function for $\{A_i\}_{i\in I}$

Since the cartesian product exists (axiomatically), we will make some shorthand notation for it similar to that defined in chapter 5. If $\{A_i\}_{i\in I}$ is a family of sets, let $A^I = \prod_{i\in I} A_i$ where $A_i = A$ for each $i \in I$. If $|I|$ is finite, and so $|I| = n$ for some $n \in \mathbb{N}$, then we write A^n instead. If $|I|$ is countable, we sometimes use the A^∞ or $A^{\mathbb{N}}$ notation. the elements of A^n can be represented as n-tuples, that is

$$A^n = \{(a_1, a_2, ..., a_n \mid a_i \in A\}$$

and the elements of $A^{\mathbb{N}}$ can be represents as sequences

$$A^{\mathbb{N}} = \{(a_1, a_2, ..., a_n, ...) \mid a_i \in A\}$$

Example A.1.3: Cartesian Products

1. An example we have already encountered is $\mathbb{R}^n$ and $\mathbb{R}^{\mathbb{N}}$. This caretsian product is called *Euclidan Space*
2. Let $A = \{0, 1\}$. Then $A^{\mathbb{N}}$ is the set of all sequences with either 0 or 1 in each component. If we change notation a bit and let $A = \mathbb{Z}/2\mathbb{Z}$, and define addition point-wise, then this would be a group

this remains an open problem in mathematics

Definition A.1.4: Partially Ordered Sets

1. Let P be a non-mepty set. A *partial order* on P is a relation $\leq$ ($\leq \subseteq P \times P$) on P such that

   (a) **(reflective)** $x \leq x$ for all $x \in A$

   (b) **(antisymmetric)** if $x \leq y$ and $y \leq x$, then $x = y$

   (c) **(transitive)** if $x \leq y$ and $y \leq z$ then $x \leq z$

   Where we usually say P is a partiallly ordered set under the orering $\leq$ or that A is partially ordered by $\leq$.

   If $\leq$ also satisfies

   (d) **(trichotomy)** If $x, y \in P$, then $x \leq y$ or $y \leq x$,

   then $\leq$ is called a *total* (or linear, simple, complete) ordering on P. If further

   (e) **(Well-Ordering)**For all $\emptyset \neq A \subseteq P$, there exists an element $a \in A$ such that $a \leq x$ for all $x \in A$

   then we say that $\leq$ is a *well-ordering* of P, or that P is well-ordered by $\leq$

2. Let $(P, \leq)$ be a partially ordered set and let $A \subseteq P$. An element $u \in P$ is called an *upper bound* for A if for all $x \in A$, $x \leq u$. Similarly, $l \in P$ is called a *lower bound* if for all $x \in A$, $l \leq x$.

3. Let $(P, \leq)$ be a partially oredered set and let $A \subseteq P$. An element $m \in P$ is called a *maximal element* of P if whenever $m \leq x$ with $x \in P$, then $m = x$. Similarly, an element $m \in P$ is called a *minimal element* if whenever $x \leq m$ for $x \in P$, then $x = m$.

4. Let $(P, \leq)$ be a partially ordered set. Then a subset $C \subseteq P$ is called a *chain* in P if C is totally ordered under the order relation of $\leq$, that is, if $x, y \in C$, then either $x \leq y$ or $y \leq x$.

Note that it's called a *partial* order because becaue not all elements *necessarily* need to to have a relation between them: if $x, y \in P$ and $\leq$ is a parital order on P, then it need not be the case that $x \leq y$ or $y \leq x$. If this were the case, we would call $\leq$ a *total order*.

In the following examples we will show the difference between being maximal and being an upper bound. Importantly, it is possible that *not all* $x \in P$ have the relation $x \leq m$ (i.e. m is not necessarily the "*largest*" or "*maximum*" element)

Example A.1.5: Partially Ordered Sets

1. Let S be an arbitrary set, and $P(S)$ be it's powerset. Then $(P(S), \subseteq)$ forms a partially ordered set. This set is *only* a partial order (it is not a total order) if $|S| > 1$: for two distinct elements $x, y \in S$ $\{x\} \not\subseteq \{y\}$ and $\{y\} \not\subseteq \{x\}$. A chain in $(P(S), \subseteq)$ would look like:


$$S_1 \subseteq S_2 \subseteq S_3 \subseteq S_4 \subseteq \cdots$$

If $T \subseteq S$, then then T has an upperbound U:

$$U = \bigcup_{x \in T} \{x\}$$

Furthermore, S is also the maximal element of $P(S)$.

2. Let $S = \{a, b, b', c'\}$ be the set, and $\leq$ be the relation visualized by the graph:



Then both b and c' are maximal elements. S has no upper bound, but it has a as a lower bound.

3. Let S be the collection of *proper subsets* of $\mathbb{N}$ ordered by $\subseteq$. Notice that the chain

$$\{1\} \subseteq \{1, 2\}\, \{1, 2, 3\} \subseteq \cdots$$

does not have an upper bound. However, S *does* have maximal elements. $(\mathbb{N} - \{n\}) \in S$ for any $n \in \mathbb{N}$ is a maximal element of S

4. Let $S = \mathbb{R}$ with the usual order $\leq$. Notice that $\leq$ is a *total order* in this case. some sets of $\mathbb{R}$ have upper bound (ex. $[0, 1]$ or $\{0, 1, 2, 3\}$), while other's do not $(\mathbb{Z}, (0, \infty), (0, 1))$. $\mathbb{R}$ does not have maximal elements in this order.

When we say we give a partial order to an arbitrary set S, we will assume that this is the partial order on the power set given by $\subseteq$.

Next, we will build-up some facts to bootstrap the result

Definition A.1.6: Finite Character

Let $\mathcal{F}$ be a family of sets. Then $\mathcal{F}$ is said to be a *family of finite character* if for any set S, $S \in \mathcal{F}$ if and only if each finite subset of S is in $\mathcal{F}$.

Lemma A.1.7: Finite Character and Chains

Let $\mathcal{F}$ be a family of finite character and let $\mathcal{B}$ be a chain in $\mathcal{F}$. Then $\cup\mathcal{B} \in \mathcal{F}$

***Proof*:**
Since $\mathcal{F}$ is of finite character, if we show that every finite subset of $\mathcal{B}$ is an element of $\mathcal{F}$. Let $\{x_1, x_2, ..., x_n\} = F \subseteq \cup\mathcal{B}$. Then there must exists sts $\mathcal{B}_1, ...\mathcal{B}_n \in \mathcal{B}$ such that $x_i \in \mathcal{B}_i$. Since $\mathcal{B}$ is a chain, there exists a $1 \leq j \leq n$ such that $B_i \subseteq B_j$, for all $i \in \{1, 2, ...n\}$. But then, $F \subseteq B_j \in \mathcal{F}$. Since $\mathcal{F}$ is of finite character, and $\mathcal{B}_j \in \mathcal{F}$, $F \in \mathcal{F}$. Since F was arbitrary, then this holds true for any finite subset of $\cup\mathcal{B}$, and so $\cup\mathcal{B} \in \mathcal{F}$, as we sought to show.

A.2 Axiom of Choice Equivalences

Note that terms like "lemma" or "theorem" for the following names are due to historical precedents rather than actually representing a lemma or theorem, since all of the following will be equivalent to the axiom of choice.

Theorem A.2.1: Tukey's Lemma

Every nomepty family of finite character has a maximal member

Theorem A.2.2: Hausdorff Maximality Principle

Every nonempty partially ordered set contains a maximal chain, i.e., every totally ordered subset is contained in a maximally totaly ordered subset

Maximally totally ordered here means that if it is enlraged in any way, it does not remained totally ordered

Theorem A.2.3: Zorn's Lemma

Every nonemtpy partially ordered set in which each chain has an upper bound has a maximal element

Theorem A.2.4: Well-Ordering Theorem

Every set can be well-orderd, i.e., if S is a set, then there exists some well-ordering $\leq$ on S

A well-ordering on a set S is a total order (i.e. a chain) on S with the additional property that every non-empty subset of S has a lower-bound. For example, given the usual orderings for the following examples, $\mathbb{N}$ is well-ordered (every subset has a lower-bound), while $\mathbb{Z}$ is not (namely, $\mathbb{Z}$ itself doens't have a lower-bound). A trickier example would be $\mathbb{R}$. The set (a, b) for $a, b \in \mathbb{R}$, $a \neq b$, does *not* have a minimal element, and so $\mathbb{R}$ is not well-ordered with the usual ordering.

Theorem A.2.5: Axiom of Choice Equivalences

The following are equivalent

1. The axiom of choice
2. Tukey's Lemma
3. The Hausdroff maximality principle
4. Zorn's Lemma
5. Well-ordering Theorem

***Proof*:**
The proof follows [62, (3.12)] and uses no transfinite induction.

(1) ⇒ (2) For the sake of contradiction, suppose Tukey's lemma was false: there exists a non-empty family of sets of finite character that has no maximal element. Let $\mathcal{F}$ be such a family. That means for every $A \in \mathcal{F}$, there exists a B such that $A \subsetneq B$. Let $\mathcal{O}_F = \{E \in \mathcal{F} \mid F \subsetneq E\}$. Then $\{\mathcal{O}_F \mid F \in \mathcal{F}\}$ is a set of sets indexed by $\mathcal{F}$. Thus, by the axiom of choice, there exists a choice function f defined on $\mathcal{F}$ such that $f(F) \in \mathcal{O}_F$ (i.e. $F \subsetneq f(F)$ for all F).

Using f, we will define a new concept: a subfamily $\mathscr{F} \subseteq \mathcal{F}$ is f-inductive if:

(a) $\emptyset \in \mathscr{F}$
(b) if $A \in \mathscr{F}$ then $f(A) \in \mathscr{F}$
(c) if $\mathcal{C} \subseteq \mathscr{F}$ is a chain, then $\cup\mathcal{C} \in \mathscr{F}$

Notice that $\mathcal{F}$ is itself an f-inductive set since: $\mathcal{F}$ is non-empty (by assumption), so some $A \in \mathcal{F}$ exists, and $\emptyset \subseteq A$ is a finite set, and so $\emptyset \in \mathcal{F}$ since $\mathcal{F}$ has finite character, fulfilling the first condition. The second conditions holds true since the image of f is in $\mathcal{F}$, and the third condition holds by lemma A.1.7. Notice too that if the family $\mathscr{F}_i \subseteq \mathcal{F}$ is f-inductive (for some indexing set I), then so too is $\bigcap_i \mathscr{F}_i$. Thus, define the smallest f-inductive set of $\mathcal{F}$:

$$\mathscr{F}_0 = \{A \in \mathcal{F} \mid A \in \mathscr{F} \text{ for every } f\text{-inductive subset of } \mathcal{F}\}$$

The fact that $\mathscr{F}_0$ is the smallest f-inductive set will allow us to force certain properties on to it. Our goal is to show that $\mathscr{F}_0$ *must* be a chain, which we will use to arrive at a contradiction.

To show that $\mathscr{F}_0$ is a chain, we will have to go through some technical steps. First, let $\mathcal{H} = \{A \in \mathscr{F}_0 \mid \text{if } B \in \mathscr{F}_0 \text{ and } B \subsetneq A \text{ then } f(B) \subseteq A\}$. The set $\mathcal{H}$ is the set of all elements $A \in \mathscr{F}_0$ such that B element is an element of $\mathscr{F}_0$ and is properly contained in A, f of that elements is contained in or equal to A. However, some oddities occurs with this set too: note that $\mathcal{H}$ is non-empty since vacusously, $\emptyset \in \mathcal{H}$ (since (False ⇒ True) and (False ⇒ False) are both *true* statements!!) This oddity is necessary, since we are guaranteed that $\mathcal{H}$ is non-empty. Now, we will show that if $A \in \mathcal{H}$ and $C \in \mathscr{F}_0$, then one of two relations *must* hold between A and C: either $C \subseteq A$ or $f(A) \subseteq C$. Notice we are forcing a subset relation between all elements of $\mathscr{F}_0$ and $\mathcal{H}$ – wel'l use this to create a total order later. First, let's prove the last assertion:

Proof. Define $\mathcal{G}_A = \{C \in \mathscr{F}_0 \mid C \subseteq A \text{ or } f(A) \subseteq C\}$. By definition, $\mathcal{G}_A \subseteq \mathscr{F}_0$. If we show that $\mathcal{G}_A$ is f-inductive, then $\mathscr{F}_0 \subseteq \mathcal{G}_A$, and since $\mathscr{F}_0$ is the smallest f-inductive subset, it must be that $\mathcal{G}_A = \mathscr{F}_0$ which will tell us that any element $C \in \mathscr{F}_0$ must be either contained in A or contain $f(A)$. For notational convinience, let's label the condition $C \subseteq A$ as [1] and condition $F(A) \subseteq C$ as [2]

(a) Since $\emptyset \in \mathscr{F}_0$, $\emptyset \subseteq A$, and so by [1] $\emptyset \in \mathcal{G}_A$
(b) Let $C \in \mathcal{G}_A$. We must show that $f(C) \in \mathcal{G}_A$. Since $C \in \mathcal{G}_A$, then we have 3 possibilites (we are splitting [1] into 2 seperate cases:
    i. $C \subsetneq A$: Since $C \subsetneq A$ and $A \in \mathcal{H}$, then $f(C) \subseteq A$, so by [1] $f(C) \in \mathcal{G}_A$

ii. $C = A$: Since $C = A$ then $f(C) = f(A)$. Which is equivalent to $f(C) \subseteq f(A)$ and $f(A) \subseteq f(C)$. For our purposes, we care that $f(A) \subseteq f(C)$. By condition [2], $f(C) \in \mathcal{G}_A$

iii. $f(A) \subseteq C$, then since $C \subsetneq f(C)$ by definition of f, $f(A) \subseteq f(C)$, and so by condition [2], $f(C) \in \mathcal{G}_A$

in all cases, $f(C) \in \mathcal{G}_A$

(c) Let $\mathcal{C} \subseteq \mathcal{G}_A$ be a chain in $\mathcal{G}_A$. We must show that $\cup\mathcal{C} \in \mathcal{G}_A$. Then, either for all $C \in \mathcal{C}$, $C \subseteq A$, in which case $\cup\mathcal{C} \subseteq A$, and so by [1] $\cup\mathcal{C} \in \mathcal{G}_A$, or there is some $C \in \mathcal{C}$ $f(A) \subseteq C \subseteq \cup\mathcal{C}$, in which case by [2] $\cup\mathcal{C} \in \mathcal{G}_A$. In both cases, the chain is in $\mathcal{G}_A$

Thus, $\mathcal{G}_A$ is indeed f-inductive for any A, and so $\mathscr{F}_0 = \mathcal{G}_A$

□

Using the previous result, we will force one more important result: $\mathcal{H} = \mathscr{F}_0$.

Proof. As before, it is already given that $\mathcal{H} \subseteq \mathscr{F}_0$. If we show $\mathcal{H}$ is f-inductive, we will have that $\mathcal{H} = \mathscr{F}_0$:

(a) As mentioned before, $\emptyset$ has no proper subset, so $(F \Rightarrow T)$ is vacuously true, meaning $\emptyset \in \mathcal{H}$

(b) Let $A \in \mathcal{H}$. We must show $f(A) \in \mathcal{H}$, that is if $B \in \mathscr{F}_0$ and $B \subsetneq f(A)$ then $f(B) \subseteq f(A)$. Since $B \in \mathscr{F}_0 = \mathcal{G}_A$, then either $B \subseteq A$ or $f(A) \subseteq B$. Since $B \subsetneq f(A)$, it cannot be the latter, thus we must have that $B \subseteq A$. From here, we have two possibilities:

i. $B \subsetneq A$: If so, then since $A \in \mathcal{H}$, by definition $f(B) \subseteq A \subseteq f(A)$, where the last $\subseteq$ comes from the definition of f. Thus, $f(B) \subseteq f(A)$

ii. $B = A$: Then $f(A) = f(B)$, in particular $f(B) \subseteq f(A)$

in either case, we get $f(B) \subseteq f(A)$

(c) Let $\mathcal{C} \subseteq \mathcal{H}$ be a chain. To show $\cup\mathcal{C} \in \mathcal{H}$, it must be that for any $B \in \mathscr{F}_0$ where $B \subsetneq \cup\mathcal{C}$, then $f(B) \subseteq \cup\mathcal{C}$. We will do a sneaky trick for this proof using the law of excluded middle [a]: For each $C \in \mathcal{C}$, either "$C \subseteq A$ for some A", or "$A \subsetneq C$ for all A" (which is it's direct negation). If the latter was true then

$$B \subsetneq \cup\mathcal{C} \subseteq \cup\{f(A) \mid A \in \mathcal{C}\} \subseteq B$$

implying $B \subsetneq B$ – a contradiction. Thus, it must be that for some $A \in \mathcal{C}$, $B \subseteq A$. There are again two cases

i. $B \subsetneq A$: Since $A \in \mathcal{H}$, then $f(B) \subseteq A \subseteq \cup\mathcal{C}$, so $f(B) \subseteq \cup\mathcal{C}$

ii. $B = A$: Then we have $B \in \mathcal{H}$, so $\mathcal{G}_B$ is defined and $\mathscr{F}_0 = \mathcal{G}_B$. Since $\mathcal{G}_B$ is f-inductive, $\cup\mathcal{C} \in \mathcal{G}_B = \mathscr{F}_0$. Thus, either $\cup\mathcal{C} \subseteq B$ or $f(B) \subseteq \cup\mathcal{C}$, and since $\cup\mathcal{C} \subseteq B$ is not possible since $B \subsetneq \cup\mathcal{C}$, it must be that $f(B) \subseteq \cup\mathcal{C}$.

In either case, $f(B) \subseteq \cup\mathcal{C}$, showing that $\cup\mathcal{C} \in \mathcal{H}$, showing that $\mathcal{H}$ is f-inducitve

Thus, $\mathscr{F}_0 = \mathcal{H}$ as we sought to show □

Finally, we get to combine all these facts. If $A \in \mathscr{F}_0 = \mathcal{H}$ and $B \in \mathscr{F}_0 = \mathcal{G}_A$, then either $B \subseteq A$ or $A \subseteq f(A) \subseteq B$. We could not do this earlier since we did not know that $\mathscr{F}_0 = \mathcal{H}$ and $\mathscr{F}_0 = \mathcal{G}_F$ for any $F \in \mathscr{F}_0$. Thus, we have that

$A \subseteq B$ or $B \subseteq A$, showing that $\mathscr{F}_0$ is a chain. We can now define $M = \cup\mathscr{F}_0$. Since $\mathscr{F}_0$ is f-inductive, then by the 3rd condition $M \in \mathscr{F}_0$. By the 2nd condition:

$$\cup\mathscr{F}_0 = M \subsetneq f(M) \in \mathscr{F}_0$$

But $f(M) \subseteq \cup\mathscr{F}_0 = M$, so $M \subsetneq f(M) \subseteq M$ implying $M \subsetneq M$ – a contradiction. The source of the contradiction was assuming an f existed which let's as choose an ever bigger value, and so no such function can exist, meaning for some A, there does not exist a B such that $A \subsetneq B$, but then A is maximal. And so, we have that (1) ⇒ (2)

(2) ⇒ (3) Let $(P, \leq)$ be a non-empty partialy orderd set. We want to show that $(P, \leq)$ contains a maximal chain (i.e. a chain C that cannot be enlarged further without loosing its total order). Let $\mathcal{F}$ be the set of all chains in P, orderd by inclusion (so if $P = A \leq B$ is a chain and $Q = A \leq B \leq C$, then $P \leq Q$). This set is non-empty, since $\emptyset \in \mathcal{F}$ and $\{x\} \in \mathcal{F}$ for all $x \in P$. Furthermore, Since any finite subchain of any infinite chain in $\mathcal{F}$ would be in $\mathcal{F}$, $\mathcal{F}$ has finite character. Thus, by Tukey's Lemma, $\mathcal{F}$ has a maximal element, meaning P has a maximal chain.

(3) ⇒ (4) Let $(P, \leq)$ be a non-empty partially ordered set where each chain has an upper bound. Then by the Hausdroff Maximality Principle, there exists a maximal chain $M \subseteq P$. Since M is a chain, it has an upper-bound – let's say m. Then m is must be a maximal element of P: If there exists some $x \in P$ such that $m \leq x$ and $m \neq x$, then $M \cup \{x\}$ is a chain that properly contains M, but M is maximal, a contradiction. Thus, m is maximal in P

(4) ⇒ (5) Let S be any set, and let $\mathcal{L}$ be the family of all well-ordered set $(W, \leq)$ such that $W \subseteq S$. This set is non-empty, since for each $x \in S$, $(\{x\}, \{(x, x)\}) \in \mathcal{L}$. In the upcoming proof, we will give an ordering to $\mathcal{L}$ and use Zorns Lemma to show that the maximal element will be $(S, \leq)$ with appropriate $\leq$

Define $(W_1, \leq_1) \preceq (W_2, \leq_2)$ if either

(a) $W_1 = W_2$ and $\leq_1 = \leq_2$ or

(b) there exists a $a \in W_2$ such that $W_1 = \{x \in W_2 \mid x \leq_2 a,\ x \neq a\}$, and $\leq_2$ agrees with $\leq_1$ on W_1 ($\leq_1 \subseteq \leq_2$ [b]). In this case, W_2 is called a continuition of $(W_1, \leq_1)$

The relation $\preceq$ is a partial ordering on $\mathcal{L}$. Reflexivity is the first case. If $(W_1, \leq_1) \preceq (W_2, \leq_2)$ holds by the second case, then W_1 is a proper subset of W_2, since $a \in W_2 \setminus W_1$, so the second case cannot hold in both directions at once, which gives antisymmetry. For transitivity it suffices to treat two instances of the second case, $W_1 = \{x \in W_2 \mid x \leq_2 a,\ x \neq a\}$ and $W_2 = \{x \in W_3 \mid x \leq_3 b,\ x \neq b\}$, each order agreeing with the next on the smaller set. Since $a \in W_2$, $a \leq_3 b$ and $a \neq b$. If $x \in W_3$ satisfies $x \leq_3 a$ and $x \neq a$, then $x \leq_3 b$, and $x \neq b$ because $b \leq_3 a$ would force $a = b$, so $x \in W_2$ and $x \leq_2 a$, that is, $x \in W_1$. Conversely every $x \in W_1$ lies in W_3 with $x \leq_3 a$ and $x \neq a$, as $\leq_2$ agrees with $\leq_3$ on W_2. Hence $W_1 = \{x \in W_3 \mid x \leq_3 a,\ x \neq a\}$, and $\leq_3$ agrees with $\leq_2$, hence with $\leq_1$, on W_1. Note that it is not a total ordering: If W_i and W_j do not have the same minimal element, then $W_i \not\preceq W_j$ and $W_j \not\preceq W_i$. This means that any chain of elements will end up with the same minimal element. Now, let $\ell = \{(W_i, \leq_i)\}_{i \in I}$ be any non-empty chain

in $\mathcal{L}$ (relative to $\preceq$). We want to show it must have an upper-bound. Set $W = \bigcup_{i\in I} W_i$ and $\leq = \bigcup_{i\in I} \leq_i$ (see definition 0.1.12). Any two members of ℓ are comparable under $\preceq$, and $(W_i, \leq_i) \preceq (W_j, \leq_j)$ implies that $W_i \subseteq W_j$ and that $\leq_i$ consists of the pairs in $\leq_j$ with both entries in W_i. This has two consequences.

(a) Finitely many elements of W lie in a single W_k: each lies in some W_i, and among these finitely many members of the chain ℓ there is a largest one, which contains the others.

(b) For $x, y \in W_k$, $x \leq y$ holds exactly when $x \leq_k y$. One direction holds because $\leq_k \subseteq \leq$. Conversely, suppose $(x, y) \in \leq_m$. If $(W_m, \leq_m) \preceq (W_k, \leq_k)$, then $\leq_m \subseteq \leq_k$. If $(W_k, \leq_k) \preceq (W_m, \leq_m)$, then (x, y) is a pair in $\leq_m$ with both entries in W_k, hence lies in $\leq_k$.

So $(W, \leq)$ is a total order: each condition of definition A.1.4 involves at most three elements of W, these lie in one W_k by the first consequence, and on W_k the relation $\leq$ is the total order $\leq_k$ by the second. It is moreover a well-ordering. Let A be a non-empty subset of W. Since it's non-empty, there exists some $i \in I$ such that $A \cap W_i \neq \emptyset$. Since $(W_i, \leq_i)$ is well-ordered, there is an element $a \in A \cap W_i$ such that $a \leq_i x$ for all $x \in A \cap W_i$. Suppose now that there is an element $b \in A$ such that $b \leq a$, and say $b \in W_j$. Then $b \in W_i$. This holds if $(W_j, \leq_j) \preceq (W_i, \leq_i)$, because then $W_j \subseteq W_i$. Otherwise $(W_i, \leq_i) \preceq (W_j, \leq_j)$ with $W_i \neq W_j$, so $W_i = \{x \in W_j \mid x \leq_j c,\ x \neq c\}$ for some $c \in W_j$, and $b \leq_j a$ by the second consequence, while $a \leq_j c$ and $a \neq c$. So $b \leq_j c$, and $b \neq c$ because $c \leq_j a$ would force $a = c$. Now $b \leq_i a$ by the second consequence and $a \leq_i b$ by the choice of a, so $b = a$. As $\leq$ is total, every $x \in A$ satisfies $a \leq x$ or $x \leq a$, and the latter forces $x = a$. Thus, A has a smallest element a in $(W, \leq)$, meaning $(W, \leq) \in \mathcal{L}$.

Furthermore, $(W, \leq)$ is an upper-bound for ℓ. Fix $i \in I$. By the second consequence, $\leq_i$ consists of the pairs in $\leq$ with both entries in W_i, so if $W_i = W$, then $(W_i, \leq_i) = (W, \leq)$. Otherwise let c be the smallest element of $W \setminus W_i$, which exists since $(W, \leq)$ is well-ordered. Say $c \in W_j$. Then $(W_j, \leq_j) \not\preceq (W_i, \leq_i)$, since $c \notin W_i$, so $(W_i, \leq_i) \preceq (W_j, \leq_j)$ with $W_i \neq W_j$, that is, $W_i = \{x \in W_j \mid x \leq_j d,\ x \neq d\}$ for some $d \in W_j$, and $d \leq_j c$ because $c \notin W_i$ and $\leq_j$ is total. Every $x \in W_i$ satisfies $x \leq_j d \leq_j c$ and $x \neq c$, so $x \leq c$ and $x \neq c$. Conversely, every $x \in W$ with $x \leq c$ and $x \neq c$ lies in W_i by the minimality of c. Hence $W_i = \{x \in W \mid x \leq c,\ x \neq c\}$, and $(W_i, \leq_i) \preceq (W, \leq)$.

Thus, by Zorn's Lemma, $\mathcal{L}$ has a maximal element $(W_0, \leq_0)$. If $W_0 = S$, we are done, as $\leq_0$ is our well-ordering of S. If $W_0 \neq S$, let $z \in S \setminus W_0$. Define $(W_0 \cup \{z\}, \leq)$, where

$$\leq = \leq_0 \cup \{(x, z) \mid x \in W_0 \cup \{z\}\}$$

that is, place z after everything in W_0. Then $(W_0 \cup \{z\}, \leq) \in \mathcal{L}$, since a non-empty subset meeting W_0 has as smallest element the $\leq_0$-smallest element of its intersection with W_0, and the only other non-empty subset is $\{z\}$. Moreover $(W_0, \leq_0) \preceq (W_0 \cup \{z\}, \leq)$ and $(W_0 \cup \{z\}, \leq) \not\preceq (W_0, \leq_0)$. However, this contradicts the maximality of $(W_0, \leq_0)$, and so it must be that $W_0 = S$, showing that S does indeed have a well-ordering.

(5) ⇒ (1) Let $\{A_i\}_{i\in I}$ be any non-empty family of non-empty sets, and let $S = \cup_{i\in I} A_i$. By the well-ordering principle, there exists an $\leq$ that well-orders S. Now, for each $i \in I$, let $f(i)$ be the smallest element of A_i (relative to $\leq$). Then f is a chocie function on the family $\{A_i\}_{i\in I}$

[a] For every proposition P, either P is true or $\neg P$ is true. This is implied by ZF
[b] If these seems strange, review the technical definition of a relation in section 0.1.4

This textbook contains many cases where zorn's lemma must be used, for example:

1. All proper ideals in a ring [with identity] is contained in a maximal ideal
2. All vector-spaces have a basis

A.3 Zorn's Lemma

For the purposes of this textbook, the most important consequence of the Axiom of Choice is Zorn's lemma (theorem A.2.3), and the two applications listed above follow one pattern. The objects sought are maximal elements of a set P of partial objects, ordered by inclusion. An application of Zorn's lemma checks that P is non-empty and that every chain in P has an upper bound in P, usually its union. Zorn's lemma then provides a maximal element, and maximality forces it to be complete, because a partial object that is not complete can be enlarged inside P. For maximal ideals, P is the set of proper ideals containing a given proper ideal, as in proposition 9.4.18. For bases, it is the set of linearly independent subsets:

Proposition A.3.1: Every Vector Space Has A Basis

Let V be a vector space over a field k. Then V has a basis, that is, a linearly independent subset that spans V.

***Proof*:**
Let P be the set of linearly independent subsets of V, ordered by inclusion. It contains $\emptyset$. Let $\mathcal{C}$ be a chain in P, and put $S = \bigcup \mathcal{C}$, with $S = \emptyset$ when $\mathcal{C}$ is empty. A linear relation $c_1 s_1 + \cdots + c_n s_n = 0$ among distinct elements of S involves finitely many members of $\mathcal{C}$, the largest of which contains $s_1, \ldots, s_n$, so every c_i is 0. So $S \in P$ is an upper bound for $\mathcal{C}$, and theorem A.2.3 gives a maximal element B of P. Suppose some $v \in V$ is not in the span of B. In a relation $cv + c_1 b_1 + \cdots + c_n b_n = 0$ with distinct $b_i \in B$, the coefficient c is 0, since otherwise $v = -c^{-1}(c_1 b_1 + \cdots + c_n b_n)$ would lie in the span of B, and then every c_i is 0 because B is linearly independent. So $B \cup \{v\}$ is a linearly independent set properly containing B, contradicting the maximality of B. Hence B spans V.

A.4 The Schröder-Bernstein Theorem

Theorem A.4.1: Schröder-Bernstein Theorem

Let A and B be sets with injections $f : A \to B$ and $g : B \to A$. Then there is a bijection $h : A \to B$.

***Proof*:**

For $E \subseteq A$ put $\Phi(E) = A \setminus g\big(B \setminus f(E)\big)$. If $E \subseteq E'$, then $f(E) \subseteq f(E')$, so $B \setminus f(E) \supseteq B \setminus f(E')$, so $g(B \setminus f(E)) \supseteq g(B \setminus f(E'))$, and so $\Phi(E) \subseteq \Phi(E')$. Let C be the union of all sets $E \subseteq A$ with $E \subseteq \Phi(E)$. Each such E satisfies $E \subseteq C$, hence $E \subseteq \Phi(E) \subseteq \Phi(C)$, so $C \subseteq \Phi(C)$. Applying Φ gives $\Phi(C) \subseteq \Phi(\Phi(C))$, so $\Phi(C)$ is one of the sets E, and $\Phi(C) \subseteq C$. Hence $C = \Phi(C)$, which says

$$A \setminus C = g\big(B \setminus f(C)\big)$$

Define $h(a) = f(a)$ for $a \in C$, and for $a \in A \setminus C$ let $h(a)$ be the element $b \in B \setminus f(C)$ with $g(b) = a$, which exists by the display and is unique because g is injective. Then h maps C injectively onto $f(C)$, since f is injective. It maps $A \setminus C$ onto $B \setminus f(C)$, since each $b \in B \setminus f(C)$ equals $h(g(b))$, and injectively, since $g(h(a)) = a$. These two images are disjoint with union B, so h is a bijection.

No choice is made in this proof: the set C and the map h are defined outright, so the theorem holds without the axiom of choice.

B

Sub-Group of a Free Group is Free

In this book, the fact that a subgroup of a free-group is free does not come into play. It is interesting tangentially as an example of a property which is closed under taking subgroups, contrasting to how being finitely generated is is not a property closed under taking subgroups, or that a sub-module of a free module is not always free, but we do not use this fact anywhere else. However, some might be curious as to how we would prove this fact. The goal of this section is to do just that using only group-theoretical knowledge.

B.1 Using Cosets

There are in fact many proofs of this fact, including a famous one by Serre topological properties of trees (connected graphs with no cycles). Such a proof would be covered in geometric group theory.

Lemma B.1.1: Finite Index Subgroup Of Finitely Generated Subgroup

Let G be a finitely generated group, and let $H \leqslant G$ be a subgroup of finite index (i.e. $|G : H| = s$ for some $s \in \mathbb{N}$). Then H is finitely generated

***Proof*:**
Let $G = \langle x_1, x_2, ..., x_n \rangle$ be generated by the elements $X = \{x_1, x_2, ..., x_n\}$, $H \leqslant G$ so that $|G : H| = s$, and let $A = \{a_1 = 1, ..., a_s\}$ be a set of representative sfor the right cosets of H (also known as a transversal for H in G).

Let $x \in H$. Since $H \leqslant G$, then $x \in G$. Since G is finitely generated we have that

$$x = y_1 y_2 \cdots y_n$$

where y_i is either a generator or an inverse of a generator. Since $y_1, y_2, ..., y_n$ are not necessarily in H, this is not a finite representation of x. Instead, we will show that from these we can create a representation with elements in H. Take the representative a_{i_1} which represents the coset Hy_1, so $a_{i_1} \in Hy_1$, meaning $a_{i_1} = h_1 y_1$ for some $h_1 \in H$. Then

$$x = y_1 a_{i_1}^{-1} a_{i_1} y_2 y_3 \cdots y_n$$

Next, let a_{i_2} be the represetnative for $Ha_{i_1} y_2$ so that $a_{i_2} = h_2 a_{i_1} y_2$. In particular, $h_2^{-1} = a_{i_1} y_2 a_{i_2}^{-1}$ so that this conjugation is part of H. Now, re-write

$$x = y_1 a_{i_1}^{-1} a_{i_1} y_2 a_{i_2}^{-1} a_{i_2} y_3 \cdots y_n$$

Similarly for a_{i_3}, picking a representative from $Ha_{i_2} y_3$. Going on in this fashion, we will end up with an equation

$$x = y_1 a_{i_1}^{-1} a_{i_1} y_2 a_{i_2}^{-1} a_{i_2} y_3 a_{i_3}^{-1} a_{i_3} \cdots y_n a_{i_n}^{-1} a_{i_n} \tag{B.1}$$

Thus, every element $x \in H$ can be in written out as in equation (B.1). Put $a_{i_0} = a_1 = 1$. For each k, the representative a_{i_k} of $Ha_{i_{k-1}} y_k$ has the form $a_{i_k} = h_k a_{i_{k-1}} y_k$ with $h_k \in H$, so the triple $a_{i_{k-1}} y_k a_{i_k}^{-1} = h_k^{-1}$ lies in H. Grouping (B.1) into these triples gives

$$x = h a_{i_n} \qquad h = \left(a_{i_0} y_1 a_{i_1}^{-1}\right)\left(a_{i_1} y_2 a_{i_2}^{-1}\right) \cdots \left(a_{i_{n-1}} y_n a_{i_n}^{-1}\right) \in H$$

As x and h lie in H, so does $a_{i_n} = h^{-1} x$. The coset $Ha_{i_{n-1}} y_n$ that a_{i_n} represents contains a_{i_n}, and a right coset Hc containing a_{i_n} equals Ha_{i_n}, because $a_{i_n} = h'c$ with $h' \in H$ gives $Hc = Hh'^{-1} a_{i_n} = Ha_{i_n}$. Since $a_{i_n} \in H$, this coset is $Ha_{i_n} = H$, whose representative is $a_1 = 1$. Hence $a_{i_n} = 1$, and $x = h$ is a product of elements $a_j y a_l^{-1}$ in which $a_j \in A$, $y \in X \cup X^{-1}$ and a_l is the representative of $Ha_j y$. There are at most $2s|X|$ such elements, all of them lie in H, and $x \in H$ was arbitrary, so H is finitely generated.

This theorem is interesting in its own right as a partial result to when a subgroup of a finitely generated group is finitely generated[1]. It also has application in geometric group theory where we are interested in finding what is the growth type of the function $\mathfrak{g}(G)(n)$ (ex. polynomial growth, exponential growth) which represents the number of words which require n elements from the generators to represent it. In this case, what we found was if $m(H)$ represents the minimum number of generators for the group H, then $m(H) \leq 2m(G)|G : H|$. For more on growth, see [72, Growth types of groups].

Proposition B.1.2: The Commutator Subgroup Of F_2 Is Not Finitely Generated

Let F_2 be the free group on $\{a, b\}$, and let F_2' be its commutator subgroup, the subgroup generated by the commutators $[u, v] = u^{-1} v^{-1} uv$ with $u, v \in F_2$. Then F_2' is not finitely generated.

***Proof*:**
Let $D = \{c/2^n \mid c \in \mathbb{Z},\ n \geq 0\}$, a subgroup of $(\mathbb{R}, +)$ that is closed under multiplication by 2^k for every $k \in \mathbb{Z}$, and let T be the set of maps $\mathbb{R} \to \mathbb{R}$ of the form $t \mapsto 2^k t + r$ with $k \in \mathbb{Z}$ and

[1]Without the finite-index hypothesis the conclusion fails: the commutator subgroup of the free group on two generators is not finitely generated, proposition B.1.2 below.

$r \in D$. Composing two of them gives

$$(2^k t + r) \circ (2^l t + s) = 2^{k+l} t + (2^k s + r)$$

which is again in T. The inverse of $t \mapsto 2^k t + r$ is $t \mapsto 2^{-k} t - 2^{-k} r$, also in T, and the identity is in T, so T is a group under composition. The exponent k is determined by the map, as its slope is 2^k, and the displayed formula shows that $\delta(2^k t + r) = k$ defines a homomorphism $\delta : T \to (\mathbb{Z}, +)$. Its kernel is the group of translations $\tau_r(t) = t + r$ with $r \in D$, and $\tau_r \circ \tau_s = \tau_{r+s}$.

Put $\alpha = \tau_1$ and $\beta(t) = 2t$. By theorem 2.3.27 there is a homomorphism $\varphi : F_2 \to T$ with $\varphi(a) = \alpha$ and $\varphi(b) = \beta$. For $u, v \in F_2$, the homomorphism $\delta \circ \varphi$ into the abelian group $\mathbb{Z}$ gives

$$\delta\varphi([u, v]) = -\delta\varphi(u) - \delta\varphi(v) + \delta\varphi(u) + \delta\varphi(v) = 0$$

so the kernel of $\delta \circ \varphi$ is a subgroup containing every commutator, hence containing F_2'. So $\varphi(F_2') = \{\tau_r \mid r \in E\}$ for a subgroup E of D.

For $m \in \mathbb{Z}$, evaluating the composite from the right,

$$[\beta^m, \alpha](t) = \beta^{-m}\alpha^{-1}\beta^m\alpha(t) = 2^{-m}\big(2^m(t+1) - 1\big) = t + 1 - 2^{-m}$$

Since $[b^m, a] \in F_2'$ and $\varphi([b^m, a]) = [\beta^m, \alpha]$, this gives $1 - 2^{-m} \in E$ for every $m \in \mathbb{Z}$. Taking $m = -1$ gives $-1 \in E$, so $1 \in E$, and then $2^{-m} = 1 - (1 - 2^{-m}) \in E$ for every $m \geq 0$.

Suppose F_2' were generated by finitely many elements $w_1, \ldots, w_k$, and write $\varphi(w_i) = \tau_{r_i}$. Every element of F_2' is a product of the w_i and their inverses, and φ carries such a product to the translation by the corresponding sum of the $\pm r_i$, so every element of E has the form $\sum_i n_i r_i$ with $n_i \in \mathbb{Z}$. Choose $N \geq 0$ with $2^N r_i \in \mathbb{Z}$ for every i. Then $E \subseteq 2^{-N}\mathbb{Z}$, which does not contain $2^{-(N+1)}$, contradicting $2^{-(N+1)} \in E$.

The part that is more intriguing for us is the way we have constructed the elements of H. Though we have limited to $|G : H|$ being finite, we can still represent the elements of $H \leqslant G$ with the same trick! Using this fact, we will show that the elements of a subgroup of a free-group will have to be relation less:

Theorem B.1.3: Nielsen-Schreier's Theorem

Let G be a free group and $H \leqslant G$. Then H is a free group

***Proof*:**

Step 1: words and the ordering. Let X be a set and $F = F(X)$ the group of reduced words on X (proposition 2.3.26). A free group is isomorphic to such an F: if G is free on $X \subseteq G$ in the sense of definition 2.3.29, the homomorphisms $F \to G$ and $G \to F$ that restrict to the identity of X, given by the two universal properties, compose in either order to homomorphisms restricting to the identity of X, and these are identities by the uniqueness in the same universal properties (theorem 2.3.27). An isomorphism carries H onto an isomorphic subgroup, so it suffices to show that every subgroup H of F is free. Note that X need not be finite, or even countable. The elements of F are the reduced words in the letters $X \cup X^{-1}$, and $|g|$ denotes the length of $g \in F$. By the well-ordering theorem (theorem A.2.4), fix a well-ordering of the letters. Order the elements of F by length first and, among words of the same length, lexicographically, comparing two different words at the first position where they differ. This is a well-ordering of

F: in a non-empty set of words, the words of least length n have a least first letter, those among them with that first letter have a least second letter, and after n such choices one word remains, which is the least element of the set.

Step 2: a Schreier transversal. For $g \in F$ let $\overline{g}$ be the first element of the right coset Hg in this ordering, and let $A = \{\overline{g} \mid g \in F\}$, which contains exactly one element of each right coset of H. So $\overline{g} = \overline{g'}$ exactly when $Hg = Hg'$, and $\overline{a} = a$ for $a \in A$. The coset H contains the empty word, so $\overline{h} = 1$ for every $h \in H$. Every prefix of an element of A lies in A. Let $a \in A$ have reduced word uw, with u and w its first k and its last $|a| - k$ letters, and put $c = \overline{u}$, so that c does not come after u, and in particular $|c| \leq |u|$. The element cw lies in $Hcw = Huw = Ha$. If $|c| < |u|$, then $|cw| \leq |c| + |w| < |a|$. If $|c| = |u|$ and $c \neq u$, then either the word cw is not reduced, and $|cw| < |c| + |w| = |a|$, or it is reduced of length $|a|$ and comes before $uw = a$, since c comes before u and the two words first differ within their first k letters. In each case cw comes before a, which is impossible, as a is the first element of Ha. Hence $u = c \in A$.

Step 3: generators, for any index. For $a \in A$ and $x \in X$ put $\gamma(a, x) = ax\overline{ax}^{-1}$, which lies in H because $\overline{ax} \in Hax$. These elements generate H. Let $h \in H$ have reduced word $z_1 \cdots z_m$, with letters $z_k \in X \cup X^{-1}$, and put $u_k = \overline{z_1 \cdots z_k}$ for $0 \leq k \leq m$, so that $u_0 = 1$ and $u_m = \overline{h} = 1$. Then

$$h = \left(u_0 z_1 u_1^{-1}\right)\left(u_1 z_2 u_2^{-1}\right) \cdots \left(u_{m-1} z_m u_m^{-1}\right)$$

and $u_k = \overline{u_{k-1} z_k}$, since $H u_{k-1} z_k = H z_1 \cdots z_k$. If $z_k = x \in X$, the kth factor is $\gamma(u_{k-1}, x)$. If $z_k = x^{-1}$ with $x \in X$, then $H u_k x = H u_{k-1} x^{-1} x = H u_{k-1}$ gives $\overline{u_k x} = u_{k-1}$, so the kth factor $u_{k-1} x^{-1} u_k^{-1}$ is $\gamma(u_k, x)^{-1}$. The element $\gamma(a, x)$ is trivial exactly when $ax = \overline{ax}$, that is, when $ax \in A$. So, with

$$I = \{(a, x) \in A \times X \mid ax \notin A\}$$

the set $Y = \{\gamma(a, x) \mid (a, x) \in I\}$ of the nontrivial elements $\gamma(a, x)$ generates H.

Step 4: the generators as reduced words. Call a pair (p, z) with $p \in A$, $z \in X \cup X^{-1}$ and $pz \notin A$ *admissible*, and for it put $\gamma_{(p,z)} = pz\overline{pz}^{-1}$. The admissible pairs whose letter lies in X are exactly the elements of I, and $\gamma_{(a,x)} = \gamma(a, x)$ for them. Let (p, z) be admissible and $q = \overline{pz}$. The word obtained by writing the reduced words of p, z and q^{-1} side by side is reduced. A cancellation in it could only occur between the last letter of p and z, or between z and the first letter of q^{-1}, which is the inverse of the last letter of q. If $p = p'z^{-1}$ as reduced words, then $pz = p'$ is a prefix of p, so $pz \in A$ by Step 2. If $q = q'z$ as reduced words, then the prefix $q' = qz^{-1}$ of q lies in A, and since $Hqz^{-1} = Hpzz^{-1} = Hp$, it equals p, so $pz = q \in A$. Both contradict $pz \notin A$. So $\gamma_{(p,z)}$ is the non-empty reduced word $p\, z\, q^{-1}$, whose letter in position $|p| + 1$ is z.

For (p, z) admissible and $q = \overline{pz}$, put $(p, z)^* = (q, z^{-1})$. Since $Hqz^{-1} = Hp$, we have $\overline{qz^{-1}} = p$. The pair $(p, z)^*$ is admissible, since $qz^{-1} \in A$ would give $qz^{-1} = p$ and $pz = q \in A$. Moreover $(p, z)^{**} = (p, z)$, and

$$\gamma_{(p,z)^*} = qz^{-1}p^{-1} = \gamma_{(p,z)}^{-1}$$

Of the two pairs (p, z) and $(p, z)^*$, exactly one has its letter in X.

Step 5: the middle letters survive. Let $d_1, \ldots, d_m$ be admissible pairs, with $m \geq 1$ and $d_{i+1} \neq d_i^*$ for $1 \leq i < m$. Then $\gamma_{d_1} \cdots \gamma_{d_m} \neq 1$. Write $d_i = (p_i, z_i)$ and $q_i = \overline{p_i z_i}$. For $i < m$ let c_i be the longest common prefix of the reduced words q_i and p_{i+1}, and write $q_i = c_i s_i$ and $p_{i+1} = c_i t_i$. Then $q_i^{-1} p_{i+1} = s_i^{-1} t_i$, and the word $\rho_i = s_i^{-1} t_i$ is reduced, because when s_i and t_i are both non-empty their first letters differ. The word

$$p_1\, z_1\, \rho_1\, z_2\, \rho_2 \cdots \rho_{m-1}\, z_m\, q_m^{-1}$$

equals $\gamma_{d_1} \cdots \gamma_{d_m}$ in F, and each of its pieces is reduced. By Step 4, p_1 does not cancel against z_1, nor z_m against q_m^{-1}. For $i < m$ there are three cases.

1. s_i and t_i are both empty. Then ρ_i is empty and $p_{i+1} = q_i$. If $z_{i+1} = z_i^{-1}$, then $d_{i+1} = (q_i, z_i^{-1}) = d_i^*$, which is excluded. So z_i and z_{i+1} do not cancel.

2. s_i is non-empty. Then ρ_i begins with the first letter of q_i^{-1}, and z_i does not cancel against it, because the word $p_i z_i q_i^{-1}$ is reduced (Step 4). If t_i is non-empty, then ρ_i ends with the last letter of p_{i+1}, which does not cancel against z_{i+1}, because the word $p_{i+1} z_{i+1} q_{i+1}^{-1}$ is reduced. If t_i is empty, then $\rho_i = s_i^{-1}$ ends with y^{-1}, where y is the first letter of s_i, and $p_{i+1} y$ is a prefix of q_i, so it lies in A by Step 2. A cancellation of y^{-1} against z_{i+1} would mean $z_{i+1} = y$, so $p_{i+1} z_{i+1} \in A$, against the admissibility of d_{i+1}.

3. s_i is empty and t_i is non-empty. Then $\rho_i = t_i$ ends with the last letter of p_{i+1}, which does not cancel against z_{i+1}, as in (2). It begins with the letter y that follows q_i in p_{i+1}, so $q_i y$ is a prefix of p_{i+1} and lies in A by Step 2. If $y = z_i^{-1}$, then $q_i z_i^{-1} \in A$, against the admissibility of d_i^*. So z_i and y do not cancel.

Hence the word is reduced. It contains the letters $z_1, \ldots, z_m$, so it is not empty, and $\gamma_{d_1} \cdots \gamma_{d_m} \neq 1$.

Step 6: H is free. Let $F(I)$ be the free group on the set I, and let $\psi : F(I) \to H$ be the homomorphism with $\psi(\iota) = \gamma_\iota$ for $\iota \in I$, given by theorem 2.3.27. Its image is the subgroup generated by Y, which is H by Step 3. A nontrivial element of $F(I)$ is a non-empty reduced word $\iota_1^{\epsilon_1} \cdots \iota_m^{\epsilon_m}$ with $\iota_i \in I$ and $\epsilon_i = \pm 1$, and by proposition 2.3.26 and Step 4, ψ sends it to $\gamma_{d_1} \cdots \gamma_{d_m}$, where $d_i = \iota_i$ if $\epsilon_i = 1$ and $d_i = \iota_i^*$ if $\epsilon_i = -1$. Suppose $d_{i+1} = d_i^*$ for some i. If $\epsilon_i = 1$, then $d_{i+1} = \iota_i^*$ has its letter in X^{-1}, so $\epsilon_{i+1} = -1$ and $\iota_{i+1}^* = \iota_i^*$, that is, $\iota_{i+1} = \iota_i$. If $\epsilon_i = -1$, then $d_{i+1} = \iota_i^{**} = \iota_i$ has its letter in X, so $\epsilon_{i+1} = 1$ and $\iota_{i+1} = \iota_i$. Either way the letters $\iota_i^{\epsilon_i}$ and $\iota_{i+1}^{\epsilon_{i+1}}$ are formal inverses, which a reduced word does not contain. So Step 5 applies, ψ sends every nontrivial element to a nontrivial element, and ψ is injective. Hence ψ is an isomorphism from $F(I)$ onto H, and H is free on $Y = \psi(I)$: for a group K and a function $f : Y \to K$, the homomorphism $F(I) \to K$ extending $\iota \mapsto f(\gamma_\iota)$, composed with ψ^{-1}, extends f, and it is the only such homomorphism because Y generates H.

B.2 Using Tree's

A perhaps more intuitive proof of this theorem comes from groups acting on trees. A group is free if and only if it acts freely on a non-empty tree, and a subgroup of a group acting freely on a tree acts freely on the same tree, so it is free. The characterization of free groups by free actions on trees uses graph theory that this appendix does not develop, and the argument is carried out in [72, Subgroups of free groups are free].

C

Basic Topology and Topological Groups

This appendix is not a substitute for a proper introduction to topology. It is a review, or a test of knowledge, of the topology used elsewhere in this book: the Zariski topology of chapter 31, the completions of chapter 25, and the Krull topology on the Galois group of an infinite extension in theorem 50.8.8. To that end, it is a speed-run of definitions and basic concepts. A full treatment is *Topology* [39], and Munkres' *Topology* [75] is a standard text.

C.1 Definition and Properties

Definition C.1.1: Topology

Let X be a set and $\mathcal{T}_X \subseteq P(X)$ be a subset of the powerset of X such that

1. $\emptyset$ and X are in $\mathcal{T}_X$
2. For any arbitrary collection of elements in $\mathcal{T}_X$, their union is in $\mathcal{T}_X$
3. for any finite collection of elements in $\mathcal{T}_X$, their intersection is in $\mathcal{T}_X$

Then $(X, \mathcal{T}_X)$ is call a *topological space* and $\mathcal{T}_X$ is called a *topology on* X. Elements of $\mathcal{T}_X$ are called *open sets*.

Usually we omit the $\mathcal{T}_X$ and simply call X the topology, thus we say that $Y \subseteq X$ is open if and only if $Y \in \mathcal{T}_X$. If $x \in X$, then a *neighbhorhood* of X will be an *open set* $U \in \mathcal{T}$ such that $x \in U$. In some book, a neighbhorhood is simply some set containing x and need not be open; sometimes to

emphasize that the neighbhorhood is open, it is called an *open neighbhorhood*. The *neighbhorhood system* of an element $x \in X$ is the collection of all open neighbhorhoods containing x. Topologies can also be defined in terms of closed sets:

Proposition C.1.2

Let X be a set and $\mathcal{T}_X^C \subseteq P(X)$ be subset of the powerset such that

1. $\emptyset$ and X are in $\mathcal{T}_X^C$
2. For any finite collection of elements in $\mathcal{T}_X^C$, their union is in $\mathcal{T}_X^C$
3. for any arbitrary collection of elements in $\mathcal{T}_X^C$, their intersection is in $\mathcal{T}_X^C$

Then the collection of complements $\mathcal{T}_X = \left\{X \setminus C \;\middle|\; C \in \mathcal{T}_X^C\right\}$ is a topology on X in the sense of definition C.1.1, and $\mathcal{T}_X^C = \{X \setminus U \mid U \in \mathcal{T}_X\}$. Conversely, if $\mathcal{T}_X$ is a topology on X, then $\{X \setminus U \mid U \in \mathcal{T}_X\}$ satisfies the three conditions above. In particular, in any topological space an arbitrary intersection of closed sets is closed and a finite union of closed sets is closed.

***Proof*:**
Throughout, A^c abbreviates $X \setminus A$, and the two De Morgan identities

$$\Big(\bigcap_{i\in I} A_i\Big)^c = \bigcup_{i\in I} A_i^c \qquad \Big(\bigcup_{i\in I} A_i\Big)^c = \bigcap_{i\in I} A_i^c$$

are used in both directions. Each holds because $x \notin \bigcap_i A_i$ says exactly that $x \notin A_i$ for some i, and $x \notin \bigcup_i A_i$ says exactly that $x \notin A_i$ for every i.

Assume the three conditions. Condition (1) gives $\emptyset = X^c \in \mathcal{T}_X$ and $X = \emptyset^c \in \mathcal{T}_X$, which is the first axiom of definition C.1.1. For an arbitrary family $\{C_i^c\}_{i\in I}$ of members of $\mathcal{T}_X$ the first De Morgan identity gives $\bigcup_i C_i^c = (\bigcap_i C_i)^c$, and $\bigcap_i C_i \in \mathcal{T}_X^C$ by condition (3), so the union lies in $\mathcal{T}_X$. For a finite family $C_1^c, \ldots, C_n^c$ the second identity gives $\bigcap_{k=1}^n C_k^c = (\bigcup_{k=1}^n C_k)^c$, and $\bigcup_{k=1}^n C_k \in \mathcal{T}_X^C$ by condition (2), so the intersection lies in $\mathcal{T}_X$. Hence $\mathcal{T}_X$ is a topology. Since $C = (C^c)^c$ for every $C \subseteq X$, the assignment $C \mapsto C^c$ is an involution of $P(X)$, so $\mathcal{T}_X^C = \{U^c \mid U \in \mathcal{T}_X\}$.

For the converse, let $\mathcal{T}_X$ be a topology and put $\mathcal{T}_X^C = \{U^c \mid U \in \mathcal{T}_X\}$, the closed sets. The same two identities, read from right to left, turn the three axioms of definition C.1.1 into conditions (1), (3) and (2) for $\mathcal{T}_X^C$ in that order. The last sentence of the statement is conditions (3) and (2).

Many times, we define a topology through the use of a topological basis (not to be confused with a vector-space basis)

Definition C.1.3: Topological Basis

Let X be a set. Then a subset of the powerset $\mathcal{B} \subseteq P(X)$ is called a *topological basis* (or just *basis* if unambiguous) where:

1. for every $x \in X$, there is some $U \in \mathcal{B}$ such that $x \in U$
2. For every $U, V \in \mathcal{B}$ and every $x \in U \cap V$, there exists a $B \in \mathcal{B}$ such that $x \in B \subseteq U \cap V$

If only the first condition is met, then $\mathcal{B}$ is called a *topological subbasis* (or *subbasis* for short). The topology $\mathcal{T}_\mathcal{B}$ on X is the topology where $U \in \mathcal{T}_\mathcal{B}$ if and only if U is the union of some subfamily of $\mathcal{B}$. If $\mathcal{B}$ is a subbasis, then $\mathcal{T}_\mathcal{B}$ consists of the unions of finite intersections of members of $\mathcal{B}$.

Two topologies that can be naturally defined on any set X are the *trivial topology* of $\mathcal{T}(X) = \{\emptyset, X\}$ and the *discrete topology* of $\mathcal{T}(X) = P(X)$. The Euclidean topology is a common topology defined on $\mathbb{R}^n$ for $n \geq 1$. Another common topology is defined on real or complex vector-spaces using a function called a *norm* (very similar to the euclidean norm used in when defining euclidean domains): a norm is a function $\|\cdot\| : V \to \mathbb{R}$ where

1. $\|x + y\| \leq \|x\| + \|y\|$
2. $\|c \cdot x\| = |c| \cdot \|x\|$
3. $\|x\| = 0$ if and only if $x = 0$

Then then the collection of all $B_r(x) = \{y \in X \mid \|x - y\| < r\}$ forms a topological basis for a topology. Another common way of defining a topological space is by using a metric: if (X, d) is a metric space, then the collection of all $B_r(x) = \{y \in X \mid d(x, y) < r\}$ forms a basis for X.

We relate two topologies by taking *continuous functions* between them:

Definition C.1.4: Continuous Function

Let X, Y be topological spaces and $f : X \to Y$ be a function. Then f is called a continuous function is the pre-iamge of every open set of Y is in X:

$$f^{-1}(U) \in \mathcal{T}(X)$$

Common examples of continuous functions are the polynomials functions from $\mathbb{R}^n$ to $\mathbb{R}^m$ given the euclidean topology in both cases. If a function is also bijective, then we call such a function a bijective continuous function. Unlike homomorphisms (be it groups, rings, etc.) a bijective continuous function does *not* imply the inverse function is continuous, or equivalently, that the image of open sets are open (an example follows definition C.1.5), and so we give a special name to a bicontinuous bijective function:

Definition C.1.5: Homeomorphim

Let $(X, \mathcal{T}_X)$ and $(Y, \mathcal{T}_Y)$ be two topological spaces. Then a function $f : X \to Y$ is called a *homeomorphism* if f is bijective and

$$f^{-1}(\mathcal{T}_Y) = \mathcal{T}_X$$

examples of homeomorphisms are the identity function, and $f(x) = x^3$ on $\mathbb{R}$ in the euclidean topology. A function that is bijective and continuous but is not a homeomorphism is the identity function from X to X where the domain has the discrete topology and the codomain has the trivial topology. Note that for any topological space X, the identity function is continuous, the composition of continuous functions is continuous, and associativty of continuous functions follows from the associativity of functions. Hence, the collection of topological spaces and continuous maps from a category

Definition C.1.6: Category Of Top

The collection of all topologies on any set and the collection of continuous maps between topologies forms a category, labelled as **Top**, with objects being topologies and morphisms begin continuous maps. Homeomorphisms are the isomorphisms of **Top**.

If the codomain of a continuous function is $\mathbb{R}$ or $\mathbb{C}$, continuous functions can be added and multiplied:

Proposition C.1.7: Arithmetics of Continuous Functions

Let X be a topological space, let A be $\mathbb{R}$ or $\mathbb{C}$ with the Euclidean topology, and let $f : X \to A$ and $g : X \to A$ be continuous functions. Then $f + g$, fg and cf for $c \in A$ are continuous functions.

***Proof*:**
Write $|\cdot|$ for the absolute value on A, so that the Euclidean topology has the balls $B_r(a) = \{b \in A \mid |b - a| < r\}$ as a basis. A set $U \subseteq A$ is open exactly when every $u \in U$ has some $B_\epsilon(u) \subseteq U$. A union of balls has this property, since for $u \in B_r(a)$ the triangle inequality gives $B_{r-|u-a|}(u) \subseteq B_r(a)$, and conversely a set with this property is the union of the balls it contains.

Let h be one of $f + g$, fg and cf, let $U \subseteq A$ be open, and let $x_0 \in h^{-1}(U)$. Choose $\epsilon > 0$ with $B_\epsilon(h(x_0)) \subseteq U$, and put $a_0 = f(x_0)$ and $b_0 = g(x_0)$. It suffices to find an open set V containing x_0 with $h(V) \subseteq B_\epsilon(h(x_0))$, since then $h^{-1}(U)$ is a union of open sets.

Sum. Take $V = f^{-1}\big(B_{\epsilon/2}(a_0)\big) \cap g^{-1}\big(B_{\epsilon/2}(b_0)\big)$, which is open because f and g are continuous. For $x \in V$,

$$|f(x) + g(x) - a_0 - b_0| \le |f(x) - a_0| + |g(x) - b_0| < \epsilon$$

Product. Put $\delta = \min\big(1, \epsilon/(2|b_0| + 2), \epsilon/(2|a_0| + 2)\big)$ and $V = f^{-1}\big(B_\delta(a_0)\big) \cap g^{-1}\big(B_\delta(b_0)\big)$. For $x \in V$ write $a = f(x)$ and $b = g(x)$. Then $|b| < |b_0| + \delta \le |b_0| + 1$, so

$$|ab - a_0b_0| \le |a - a_0||b| + |a_0||b - b_0| < \delta(|b_0| + 1) + |a_0|\delta \le \epsilon$$

Scalar multiple. If $c = 0$, then cf is constant, and every preimage under it is $\emptyset$ or X. If $c \neq 0$, take $V = f^{-1}\big(B_{\epsilon/|c|}(a_0)\big)$, so that $|cf(x) - ca_0| = |c||f(x) - a_0| < \epsilon$ for $x \in V$.

Given an arbitrary set $U \subseteq X$, we may consider the set of all closed subsets containing U. Since the arbitrary intersection of closed sets is closed (proposition C.1.2), there is a notion of smallest closed subsets *containing* U. Similarly, we may consider all open subsets *contained* in U, and take their union, giving the dual

Definition C.1.8: Closure And Interior

Let $U \subseteq X$ be an arbitrary set. Then

1. The *closure* of U, denoted $\overline{U}$ is the intersection of all closed sets containing U
2. The *interior* of U, denoted $\text{int}(U)$, is the union of all open sets contained in U.

Given a topological space, injective and surjective maps give rise to natural spaces, and the product of sets has a natural topology:

Definition C.1.9: Subspace, Quotient Space, and Product Space

Let X be a topological space. Then

1. the subset $Y \subseteq X$ is a *subsapce* of X if it is endowed with the topology given by the sets $\{U \cap Y \mid U \subseteq X \text{ open}\}$
2. a set of equivalence space $Y = X/\sim$ is a *quotient topology* if it is endowed with the topology where $U \subseteq Y$ is open if and only if $\pi^{-1}(U) \subseteq X$ is open (where $\pi : X \to Y$ is the natural projection)
3. Given a collection of topological spaces $\{X_i\}_{i\in I}$ for an indexing set I, the product topology is the topology endowed on products of the sets $Y = \prod_{i\in I} X_i$ where $\pi_i^{-1}(U)$ forms a sub-basis for Y.

Proposition C.1.10: Universal Properties Of Subspaces, Quotients And Products

Let Z be a topological space.

1. If $Y \subseteq X$ carries the subspace topology and $\iota : Y \to X$ is the inclusion, then a function $f : Z \to Y$ is continuous if and only if $\iota \circ f$ is continuous.
2. If $X/\sim$ carries the quotient topology and $\pi : X \to X/\sim$ is the projection, then a function $g : X/\sim \to Z$ is continuous if and only if $g \circ \pi$ is continuous.
3. If $\prod_{i\in I} X_i$ carries the product topology and π_i are the projections, then a function $f : Z \to \prod_{i\in I} X_i$ is continuous if and only if every $\pi_i \circ f$ is continuous.

***Proof*:**
A composite of continuous maps is continuous, since $(k \circ h)^{-1}(W) = h^{-1}(k^{-1}(W))$. The maps ι, π and π_i are continuous: $\iota^{-1}(U) = U \cap Y$ is open in Y, $\pi^{-1}(W)$ is open for W open in $X/\sim$ by the definition of the quotient topology, and $\pi_i^{-1}(U)$ is one of the subbasic open sets of the product. This gives the forward implication in each part.

1. Suppose $\iota \circ f$ is continuous. An open subset of Y has the form $U \cap Y$ with U open in X, and $f^{-1}(U \cap Y) = (\iota \circ f)^{-1}(U)$ is open in Z.
2. Suppose $g \circ \pi$ is continuous, and let $W \subseteq Z$ be open. Then $\pi^{-1}\big(g^{-1}(W)\big) = (g \circ \pi)^{-1}(W)$ is open in X, which by the definition of the quotient topology says that $g^{-1}(W)$ is open in $X/\sim$.
3. Suppose every $\pi_i \circ f$ is continuous. Then $f^{-1}\big(\pi_i^{-1}(U)\big) = (\pi_i \circ f)^{-1}(U)$ is open for every subbasic open set $\pi_i^{-1}(U)$. By definition C.1.3, every open set of the product is a union of finite intersections of subbasic open sets, and f^{-1} preserves unions and intersections, so the preimage of every open set is open.

Part (2) is dual to part (1): it tests continuity of maps out of a quotient by composing with the projection, where part (1) tests continuity of maps into a subspace by composing with the inclusion.

Recall that a topological space has varying notion of separation defined on it. The most prominent of which is the Hausdorff axiom (also known as T_2):

Definition C.1.11: Hausdorff space (T_2)

Let X be a topological space, and let $x, y \in X$ be arbitrary different points. Then X is called *Hausdorff* if there always exists open sets U, V such that $x \in U$, $y \in V$, and $U \cap V = \emptyset$.

There are two weaker conditions that do show up in this book:

1. Fréchet (T_1) means that for each $x, y \in X$, there exists open neigbhorhoods U, V such that $x \in U$, $y \in V$, but $y \notin U$ and $x \notin V$. Note that U and V need not be disjoint. Key feature of T_1 is that all singletons are closed.
2. Even weaker is Kolmogorov (T_0) (Zariski topologies are T_0 but not T_1)

Proposition C.1.12: Hausdorff And Diagonals

Let X be a topological space. Then X is Hausdorff if and only if the diagonal $\Delta = \{(x, x) \mid x \in X\} \subseteq X \times X$ is closed in the product topology.

***Proof*:**

First record the shape of the basic open sets of $X \times X$. By definition C.1.9 the sets $\pi_1^{-1}(U) = U \times X$ and $\pi_2^{-1}(V) = X \times V$, for U and V open in X, form a subbasis, so by definition C.1.3 the finite intersections of such sets form a basis. A finite intersection of them is $U \times V$ with U the intersection of the first-coordinate factors and V the intersection of the second-coordinate factors, both open by definition C.1.1. So a subset of $X \times X$ is open exactly when it is a union of sets $U \times V$ with U, V open in X.

Suppose X is Hausdorff and let $(x, y) \in (X \times X) \setminus \Delta$, so that $x \neq y$. By definition C.1.11 there are open sets $U \ni x$ and $V \ni y$ with $U \cap V = \emptyset$. The basic open set $U \times V$ contains (x, y) and misses Δ, because a point $(z, z) \in U \times V$ would put z in $U \cap V$. Every point of $(X \times X) \setminus \Delta$ therefore has a basic open neighborhood inside that set, so $(X \times X) \setminus \Delta$ is a union of basic open sets and is open. Hence Δ is closed.

Conversely, suppose Δ is closed and let $x \neq y$ in X. Then (x, y) lies in the open set $(X \times X) \setminus \Delta$,

so by the first paragraph there are open $U, V \subseteq X$ with $(x, y) \in U \times V \subseteq (X \times X) \setminus \Delta$. Thus $x \in U$ and $y \in V$, and $U \cap V = \emptyset$, because a point $z \in U \cap V$ would put (z, z) into $U \times V$ and into Δ at once. These are the open sets required by definition C.1.11, so X is Hausdorff.

A final tool that is very common in topology is that of the *sequences*[1]

Definition C.1.13: Sequence

Let X be any set. Then a *sequence*, is a function $f : \mathbb{N} \to X$. Usually, the element $f(n)$ is labeled as x_n for some dummy variable x, and the function f is represented as $(x_n)_{n=1}^{\infty}$ or simply (x_n) for short.

Sequences become interesting once they are in a topological space, and there is a notion of them "approaching" a point. In a metric space, we can define this notion using epsilon-balls. However, there is a more general notion of convergence for topological spaces that are non-metrizable

Definition C.1.14: Convergent Sequence

Let X be a topological space, (x_n) a sequence in X, and $x \in X$ an element of X. Then (x_n) is said to *converge to* x if for every neigbhorhoods U of x, there exists a natural number $S(U) \in \mathbb{N}$ such that

$$x_n \in U \qquad \forall n \geq S(U)$$

Proposition C.1.15: Convergent Sequence In Hausdroff Spaces

Let X be a *Hausdorff* topological space and (x_n) a convergent sequence in X. Then (x_n) converges to *at most* one point. The resulting point is called the *limit point*.

***Proof*:**
Suppose (x_n) converges to x and to y with $x \neq y$. By definition C.1.11 there are open sets $U \ni x$ and $V \ni y$ with $U \cap V = \emptyset$. Applying definition C.1.14 to the neighborhood U of x produces $S(U) \in \mathbb{N}$ with $x_n \in U$ for all $n \geq S(U)$, and applying it to the neighborhood V of y produces $S(V) \in \mathbb{N}$ with $x_n \in V$ for all $n \geq S(V)$. Take $m = \max(S(U), S(V))$. Then x_m lies in U and in V, so $U \cap V \neq \emptyset$, contradicting the choice of U and V. Hence no two distinct points can both be limits of (x_n).

The hypothesis is not removable. If X carries the trivial topology $\{\emptyset, X\}$ of the discussion after definition C.1.3 and $|X| > 1$, the only neighborhood of any point is X itself, so every sequence converges to every point of X.

For most cases that are considered in algebra and analysis, every point $x \in X$ has a "countable neighborhood basis", which essentially translates to every open set is "locally" a countable union of open sets. This property is called *first-countable*. It is not important for this book, but it is important to be able to state the following result:

[1] More generally, ultra-filters or nets may be more appropriate for the topological setting, however they are not necessary for this review of topology

Proposition C.1.16: Closed Sets In Hausdroff Spaces w.r.t. Sequences

Let $U \subseteq X$ be any subset of a first-countable Hausdorff topological space X, and let $\lim U$ denote the collection of all limit points of all convergent sequences $(x_n) \subseteq U$. Then

$$\overline{U} = \lim U$$

***Proof*:**

The inclusion $\lim U \subseteq \overline{U}$ uses neither hypothesis. Let $x \in \lim U$, witnessed by a sequence $(x_n) \subseteq U$ converging to x, and suppose $x \notin \overline{U}$. By definition C.1.8 the set $\overline{U}$ is an intersection of closed sets, hence closed by proposition C.1.2, so $X \setminus \overline{U}$ is an open set containing x and disjoint from U. By definition C.1.14 there is $S \in \mathbb{N}$ with $x_n \in X \setminus \overline{U}$ for all $n \geq S$, contradicting $x_S \in U$. Hence $x \in \overline{U}$.

For $\overline{U} \subseteq \lim U$, let $x \in \overline{U}$ and let $\{B_n\}_{n\in\mathbb{N}}$ be a countable neighborhood basis at x, which exists because X is first-countable. Put $V_n = B_1 \cap \cdots \cap B_n$, an open set containing x by definition C.1.1, and note $V_1 \supseteq V_2 \supseteq \cdots$ and that every open $W \ni x$ contains some B_n and hence some V_n. Each V_n meets U: otherwise $X \setminus V_n$ would be a closed set containing U, forcing $\overline{U} \subseteq X \setminus V_n$ and contradicting $x \in \overline{U} \cap V_n$. Using axiom A.1.2 on the family $\{V_n \cap U\}_{n\in\mathbb{N}}$ of non-empty sets, choose $x_n \in V_n \cap U$ for every n. Given an open $W \ni x$, pick n_0 with $V_{n_0} \subseteq W$. For $n \geq n_0$ the containments $x_n \in V_n \subseteq V_{n_0} \subseteq W$ hold, so (x_n) converges to x in the sense of definition C.1.14. As $(x_n) \subseteq U$, this gives $x \in \lim U$.

Neither inclusion used the Hausdorff hypothesis. It is carried in the statement only so that proposition C.1.15 applies and each of the sequences above has a single limit point, which is what makes the phrase "the limit point" legitimate.

Most spaces covered in a topological class, and all topological spaces covered in this book, have this property and hence closedness can be characterized with sequences. If $\overline{U} = X$ (i.e. the closure gives the entire space), then we give such a set a name

Definition C.1.17: Dense Set

Let X be a topological space. Then if $U \subseteq X$ is a subset of X such that $\overline{U} = X$, then U is called a *dense set*.

These are very important in real and functional anslysis, and they show up in the discussion of completion in chapter 25.

If X is a metric space, we can define the notion of a cauchy sequence:

Definition C.1.18: Cauchy Sequence

Let X be a metric space with metric d. Then (x_n) is a *cauchy sequence* if for every $\epsilon > 0$, there exists an $N \in \mathbb{N}$ such that for all $n, m > N$,

$$d(x_n, x_m) < \epsilon$$

Given any metric space, we can "complete" it by adding all of the cauchy sequence that do not converge in the following way: for any two cauchy sequences, they are called *equivalent* if $d(x_n, y_n) \to 0$. Then

the collection of equivalence classes of cauchy sequences is called the *completion of the metric space*. It carries the metric $\lim_n d(x_n, y_n)$, contains X as the classes of constant sequences, and is complete in the sense of the following definition ([24, Existence of the Completion]):

Definition C.1.19: Complete Metric Space

Let X be a metric space. Then X is compelte if all cauchy sequences are convergent sequences

Example C.1.20: Complete Spaces
$\mathbb{R}$ is a complete space, while $\mathbb{Q}$ is not

The notion of completeness given in chapter 25 is in fact a generalization of the above notion, as appendix C.5 below shows.

For comparison to other definitions of dimension presented, the following can be considered one of the "most broad" definitions:

Definition C.1.21: Topological Dimension

Let X be a topological space. The *order* of an open cover $\{U_i\}$ of X is the smallest number n for which each point $x \in X$ belongs to at most n open sets in the open cover. A *refinement* of an open cover $\{U_i\}$ is an open cover $\{V_j\}$ such that each $V_j \subseteq U_i$ for some i. The *Topological dimension* or *Lebesgue Covering Dimension* is the minimum number n such that every finite open cover has a refinement of order $n + 1$.

C.2 Construction Topologies

The subspace, product, and quotient topology are all special examples of the following two constructions:

Definition C.2.1: Weak [initial] Topology

Let X be a set and let $F = \{f_\alpha : X \to Y_\alpha\}_{\alpha \in A}$ be a collection of maps from X to topological spaces Y_α. Then the coarsest topology on X which makes each f_α continuous is called the *weak topology* generated by F.

Note that it is not interesting to ask what is the finnest topology on X that makes all the maps continuous: it is the discrete topology on X.

Proposition C.2.2: Existence Of The Weak Topology

In the setting of definition C.2.1, let $\mathcal{T}_F$ be the collection of all unions of finite intersections of sets $f_\alpha^{-1}(U)$ with $\alpha \in A$ and $U \subseteq Y_\alpha$ open, the empty intersection being X. Then $\mathcal{T}_F$ is a topology on X for which every f_α is continuous, and $\mathcal{T}_F \subseteq \mathcal{T}'$ for every topology $\mathcal{T}'$ on X for which every f_α is continuous. So $\mathcal{T}_F$ is the weak topology, and the finite intersections of the sets $f_\alpha^{-1}(U)$ form a basis for it.

***Proof*:**
The empty union gives $\emptyset \in \mathcal{T}_F$, and the empty intersection gives $X \in \mathcal{T}_F$. A union of unions of finite intersections is again one. For two members $\bigcup_j B_j$ and $\bigcup_k C_k$ of $\mathcal{T}_F$, with every B_j and C_k a finite intersection,

$$\left(\bigcup_j B_j\right) \cap \left(\bigcup_k C_k\right) = \bigcup_{j,k} B_j \cap C_k$$

and each $B_j \cap C_k$ is again a finite intersection, so by induction $\mathcal{T}_F$ is closed under finite intersections. Hence $\mathcal{T}_F$ is a topology by definition C.1.1. It contains every $f_\alpha^{-1}(U)$, which is the continuity of every f_α. If $\mathcal{T}'$ makes every f_α continuous, then $\mathcal{T}'$ contains every $f_\alpha^{-1}(U)$, and being closed under finite intersections and arbitrary unions it contains $\mathcal{T}_F$. So $\mathcal{T}_F$ is a coarsest such topology, and it is the only one, since another coarsest topology would both contain $\mathcal{T}_F$ and be contained in it. Finally, the finite intersections of the sets $f_\alpha^{-1}(U)$ satisfy both conditions of definition C.1.3, since they cover X and are closed under finite intersections, and $\mathcal{T}_F$ consists of their unions.

Example C.2.3: Weak Topology

1. Let $\{X_\alpha\}_{\alpha \in A}$ be some collection of topologies and $X = \prod_{\alpha \in A} X_\alpha$. Let $\Pi = \{\pi_\alpha : X \to X_\alpha\}$ be the collection of functions. Then the weak topology on X generated by Π is *precisely* the product topology of definition C.1.9: by definition C.1.3 and proposition C.2.2, both consist of the unions of finite intersections of the sets $\pi_\alpha^{-1}(U)$.
2. Let X be any topological space and $A \subseteq X$ any subset. Let $\iota : A \to X$ be the inclusion map. Then the weak topology on A generated by ι is the *subspace* topology.

One of the great advantages of of defining weak topologies is that we can make the collection of f_α and spaces X_α anything we want. This flexibility will the definition's of many interesting topologies on funcitonal spaces (ex. collection of smooth functions on compact spaces, collection of bounded continuous functions, or simply collection of bounded functions, and so forth). All such spaces are of key importance in funtional analysis. Weak topologies are also a special case of a much more general construction, which we will explore at the end of this chapter.

Finally, there is also the dual of weak topologies where we take maps that map *into* X.

Definition C.2.4: Final Topologies

Let Y be a set, $\{X_\alpha\}_{\alpha \in A}$ be a collection of topological spaces, and $F = \{f_\alpha : X_\alpha \to Y\}$ be a collection of maps into Y. Then the finest topology on Y that makes each f_α continuous is called the *final topology*. In particular, $U \subseteq Y$ is open if and only if $f_\alpha^{-1}(U)$ is open in X_α for each $\alpha \in A$

The sets U described in definition C.2.4 do form the finest such topology. Preimages commute with unions and intersections, $f_\alpha^{-1}\left(\bigcup_i U_i\right) = \bigcup_i f_\alpha^{-1}(U_i)$ and $f_\alpha^{-1}(U \cap V) = f_\alpha^{-1}(U) \cap f_\alpha^{-1}(V)$, and $f_\alpha^{-1}(\emptyset) = \emptyset$ and $f_\alpha^{-1}(Y) = X_\alpha$, so these sets form a topology by definition C.1.1. Every f_α is continuous for it by construction, and in any topology on Y for which every f_α is continuous each open set is one of these sets, so that topology is contained in this one. While the weak (or initial) topology seeks for a domain with the coarsest topology, final topologies seek a codomain with the finnest topology. This is because the coarsest topology on the co-domain will always create continuous

maps. Unlike the initial topology, the final topology is not given the name "strong" to contrast the name "weak" for initial topologies. There is in fact a topology known as the strong topolgoy on a space X: If $\|\cdot\|$ is a norm on a real or complex vector space X[2], the strong topology on X is the topology generated by all the balls $B_r(x)$ for all $x \in X$ and $r > 0$. The contrast between strong and weak topologies will make more sense when studying functional analysis, where useful topologies on vector spaces are often defined by families of seminorms and not by a single norm [51, Section 5.4].

Example C.2.5: Final Topologies

Let X be a topological space, $\sim$ an equivalence relation on X, and $\pi : X \to X/\sim$ the projection map. Then the final topology on $X/\sim$ generated by π is the *quotient topology* of definition C.1.9, since both declare U open exactly when $\pi^{-1}(U)$ is open.

Both the initial and final topologies can be generalized even further. If you have read Part XII, the initial and final topologies are the topologies that limits and colimits in **Top** carry on the corresponding limits and colimits of sets. These two also go by the name of *projective limit* and *injective limit*.

C.3 Compactness and Connectedness

Definition C.3.1: Compact Space

Let X be a topological space. If $\{U_i\}_{i\in I}$ is a collection of open sets such that $\bigcup_{i\in I} U_I = X$, then $\{U_i\}_{i\in I}$ is called an *open cover*. An *open subcover*, or *subcover* for short, is a subst of an open cover. If any open cover of X adminits a finite subcover, then X is *compact*.

Proposition C.3.2: Closed Subset Of Compact Spaces

Let $U \subseteq X$ be a closed subset of a compact space X. Then U is compact as a subspace.

***Proof*:**

Let $\{V_i\}_{i\in I}$ be an open cover of U in the subspace topology. By definition C.1.9 each V_i has the form $V_i = W_i \cap U$ for some W_i open in X. The set $X \setminus U$ is open, since U is closed, and

$$X = U \cup (X \setminus U) \subseteq \left(\bigcup_{i\in I} W_i\right) \cup (X \setminus U)$$

because every point of U lies in some $V_i \subseteq W_i$. So $\{W_i\}_{i\in I} \cup \{X \setminus U\}$ is an open cover of X. By definition C.3.1 it has a finite subcover, and enlarging that subcover by $X \setminus U$ if needed, there are indices $i_1, \ldots, i_k \in I$ with $X = W_{i_1} \cup \cdots \cup W_{i_k} \cup (X \setminus U)$. Intersecting with U and using $(X \setminus U) \cap U = \emptyset$ gives

$$U = (W_{i_1} \cap U) \cup \cdots \cup (W_{i_k} \cap U) = V_{i_1} \cup \cdots \cup V_{i_k}$$

so $\{V_i\}_{i\in I}$ admits a finite subcover. As the cover was arbitrary, U is compact.

[2] See [31, Norm and Induced Norm].

Definition C.3.3: Connected Space

Let X be a topological space. Then if there exists no non-trivial proper clopen subsets, X is connected. Equivalently, X is connected if there does not exist two disjoint non-empty open sets $U_1, U_2 \subseteq X$ such that $X = U_1 \cup U_2$.

C.4 Topological Groups

In this book, topological groups show up in the completion of rings (chapter 25) and in the representations of locally compact abelian groups (section 53.4.1). The topological considerations in both of those cases were purposefully scarce to not have any topological requirements for learning those materials. However, having a topological perspective brings out a deeper perspective, and so they are further explored in this section.

Definition C.4.1: Topological Group

Let G be a topological space. Then if there exists a binary operation $\cdot : G \times G \to G$ satisfying the axioms of a group that is also *continuous* (where $G \times G$ has the product topology), and a $(_)^{-1} : G \to G$ mapping $g \mapsto g^{-1}$ that is *continuous*, then G is a *topological group*

Though we have defined topological groups, the same definition can be done for any other algebraic object we have worked with, notably *topological rings*, *topological R-modules*, and *topological R-algebras*. A topological group is the same thing as a *group object* in the category **Top** (example 67.4.4).

Example C.4.2: Topological Group

1. For any group G, if G is equipped with the discrete topology it is a topological group, and all homomorphisms are continuous between any other topological group. In this way, the theory of topological groups can be thought as subsuming group theory. Any group with the indiscrete topology (also known as trivial topology) is also a topological group.
2. If $H \leqslant G$ is also a topological space, then H is a topological group with the subspace topology.
3. The real numbers $\mathbb{R}$ under addition and $\mathbb{R}^\times$ under multiplication are topological groups. Addition and multiplication are continuous by proposition C.1.7, applied to the coordinate projections, which are continuous for the product topology, and proposition C.1.10 restricts the multiplication to the subspace $\mathbb{R}^\times$. Negation $t \mapsto (-1)t$ is a scalar multiple of the identity. Inversion $t \mapsto 1/t$ is continuous on $\mathbb{R}^\times$: for $t_0 \neq 0$ and $\epsilon > 0$, every t with $|t - t_0| < \min(|t_0|/2, \epsilon t_0^2/2)$ satisfies $|t| > |t_0|/2$ and $|1/t - 1/t_0| = |t - t_0|/(|t||t_0|) < \epsilon$. More generally, $\mathbb{R}^n$ is a topological group, or any *topological vector-space* (a vector-space where the action is continuous as well) is a topological group
4. The circle $S^1 = U(1) = \{x \in \mathbb{C} \mid |x| = 1\}$, a subgroup of $\mathbb{C}^\times$ with the subspace topology, and the n-torus $(S^1)^n$ are topological groups.
5. The general linear group over the reals $\mathrm{GL}_n(\mathbb{R})$ is a topological group. Similarly, the special linear group,$\mathrm{SL}_n(\mathbb{R}) = \{A \in \mathrm{GL}_n \mid \det(A) = 1\}$, is a topological group.

6. Take $O(n) \subseteq \mathrm{GL}(n)$, where $O(n) = \{A \in \mathrm{GL}_n(\mathbb{R}) \mid AA^t = I\}$. This is a topological group known as the *orthogonal group*, since it consists of all orthonormal basis of $\mathbb{R}^n$. Similarly, we can define $U(n) = \left\{A \in \mathrm{GL}_n(\mathbb{C}) \;\middle|\; A\overline{A}^t = I\right\}$ is a topological group known as the *unitary group*. Similarly to $\mathrm{SL}_n(\mathbb{R})$, we have:

$$\mathrm{SO}(n) = \mathrm{SL}_n(\mathbb{R}) \cap O(n) \qquad \mathrm{SU}(n) = \mathrm{SL}_n(\mathbb{C}) \cap U(n)$$

   Note that all these groups are *compact*.

7. (If you know some Differential Geometry) Any Lie group is naturally a topological group. An example of a topological group that is not a Lie group is $\mathbb{Q}$ with the subspace topology induced by $\mathbb{R}$.

8. If you have covered the completion chapter of *Commutative Algebra* [20], then the p-adic integers, $\mathbb{Z}_p$ has the induced inverse-limit topology (in this case, the p-adic topology). This group is compact, homeomorphic to the Cantor set, and totally disconnected without being discrete (hence cannot be a Lie Group, since a Lie group is locally connected and a totally disconnected one is therefore discrete)

9. Similarly to $\mathbb{Z}_p$, giving $\mathbb{Q}$ a different p-adic metric, we can take a different completion to form $\mathbb{Q}_p$, which is not a Lie group either, for the same reason.

Proposition C.4.3: Topological Criterion

Let G be a group and a topological space. Then G is a topological group if and only if the map $q : G \times G \to G$, $(x, y) \mapsto xy^{-1}$, is continuous

***Proof*:**
Two remarks are used in both directions. As in the proof of proposition C.1.12, the sets $U \times V$ with U, V open in G form a basis for $G \times G$, so a map into $G \times G$ is continuous as soon as the preimage of every such $U \times V$ is open, preimages commuting with the unions that build the remaining open sets. Also, a composite $g \circ f$ of continuous maps is continuous, since $(g \circ f)^{-1}(W) = f^{-1}(g^{-1}(W))$ for every W.

Suppose G is a topological group, and write $m(x, y) = xy$ and $\iota(x) = x^{-1}$ for the two maps that definition C.4.1 requires to be continuous. Let $\sigma : G \times G \to G \times G$ be $\sigma(x, y) = (x, y^{-1})$. For U, V open,

$$\sigma^{-1}(U \times V) = \left\{(x, y) \;\middle|\; x \in U,\ y^{-1} \in V\right\} = U \times \iota^{-1}(V)$$

which is open because ι is continuous. So σ is continuous, and $q = m \circ \sigma$ is continuous.

Conversely, suppose q is continuous. Let $j : G \to G \times G$ be $j(x) = (e, x)$, where e is the identity. For U, V open, $j^{-1}(U \times V)$ equals V when $e \in U$ and equals $\emptyset$ otherwise, and both are open, so j is continuous. Since $q(j(x)) = ex^{-1} = x^{-1}$, inversion $\iota = q \circ j$ is continuous. Now $\sigma(x, y) = (x, \iota(y))$ is continuous by the computation of the previous paragraph, which used only the continuity of ι, and

$$q(\sigma(x, y)) = q(x, y^{-1}) = x(y^{-1})^{-1} = xy$$

so $m = q \circ \sigma$ is continuous. Both maps required by definition C.4.1 are continuous, and G is a topological group.

Definition C.4.4: Topological Homomorphism/Isomorphism

Let $f : G \to H$ be a function between topological groups. Then if f is a continuous homomorphism (resp. a homeomorphic isomorphism) then f is called a *topological homomorphism* (resp. *topological isomorphism*)

Example C.4.5: Topological Isomorphism

Naturally, the identity map is a topological isomorphism. If the topology is discrete, every homomorphism/isomorphism is a topological homomorphism/isomorphism.

It is possible that a homomorphism/continuous map is not a continuous map/homomorphism. As an example of a continuous, even homeomorphic map, that is not a homomorphism is the following: let $g \in G$ with $g \neq 1$ and $\varphi_g : G \to G$ be the map sending $x \mapsto gx$. It is not a homomorphism, since $\varphi_g(1) = g$. It is a homeomorphism: it is the composite of the map $x \mapsto (g, x)$, which is continuous because the preimage of a basic open set $U \times V$ of $G \times G$ is V when $g \in U$ and $\emptyset$ otherwise, with the continuous multiplication, and its inverse $\varphi_{g^{-1}}$ is continuous for the same reason. This example is particularly interesting since it shows that every $g \in G$ induces a homeomorphism! A space Y is called a *homogeneous space* if for any two points $y, y' \in Y$ some homeomorphism of Y sends y to y', and G is one, since $\varphi_{yx^{-1}}$ sends x to y. As a consequence of this, if U is a neighborhood of 1, then gU is a neighborhood of g, meaning that the topology of G is determined by the neighborhoods of 1!

Let $H \leqslant G$, and give the set G/H of left cosets the quotient topology of definition C.1.9 for the projection $\pi : G \to G/H$, $\pi(x) = xH$.

Proposition C.4.6: Quotients Of Topological Groups

Let G be a topological group, let $H \leqslant G$, and let $\pi : G \to G/H$ be the projection, with G/H carrying the quotient topology.

1. The projection π is open: $\pi(U)$ is open for every open $U \subseteq G$.
2. For each $g \in G$, the map $\bar{\varphi}_g : G/H \to G/H$, $xH \mapsto gxH$, is a homeomorphism, and $\bar{\varphi}_{yx^{-1}}$ sends xH to yH. In particular, G/H is a homogeneous space.
3. If $H \trianglelefteq G$, then the quotient group G/H, with the quotient topology, is a topological group.

***Proof*:**

By example C.4.5, every left translation is a homeomorphism of G, and the same argument, with $x \mapsto (x, g)$ in place of $x \mapsto (g, x)$, shows that every right translation $\rho_g(x) = xg$ is one.

1. Let $U \subseteq G$ be open. An element x lies in $\pi^{-1}(\pi(U))$ exactly when $xH = uH$ for some $u \in U$, that is, when $x \in UH$. So $\pi^{-1}(\pi(U)) = UH = \bigcup_{h \in H} \rho_h(U)$ is open, and $\pi(U)$ is open by the definition of the quotient topology.
2. The map $\bar{\varphi}_g$ is well defined, since $xH = x'H$ gives $gxH = gx'H$, and $\bar{\varphi}_g \circ \pi = \pi \circ \varphi_g$. For $W \subseteq G/H$ open, $\pi^{-1}\big(\bar{\varphi}_g^{-1}(W)\big) = \varphi_g^{-1}\big(\pi^{-1}(W)\big)$ is open, so $\bar{\varphi}_g^{-1}(W)$ is open and $\bar{\varphi}_g$ is continuous. Its inverse $\bar{\varphi}_{g^{-1}}$ is continuous for the same reason, so $\bar{\varphi}_g$ is a homeomorphism,

and $\bar{\varphi}_{yx^{-1}}(xH) = yH$.

3. The map $\bar{q}(xH, yH) = xy^{-1}H$ is well defined. If $x'H = xH$ and $y'H = yH$, write $x' = xh_1$ and $y' = yh_2$ with $h_1, h_2 \in H$. Then $x'y'^{-1} = xy^{-1}\big(yh_1h_2^{-1}y^{-1}\big)$, and $yh_1h_2^{-1}y^{-1} \in H$ because H is normal, so $x'y'^{-1}H = xy^{-1}H$. By proposition C.4.3, it suffices to show that $\bar{q}$ is continuous on $G/H \times G/H$. Let $W \subseteq G/H$ be open and let $\bar{q}(xH, yH) \in W$. The map $\pi \circ q$, where $q(x, y) = xy^{-1}$, is continuous by proposition C.4.3, so $(\pi \circ q)^{-1}(W)$ is an open subset of $G \times G$ containing (x, y), and it contains a basic open set $U \times V$ with $x \in U$ and $y \in V$. By part (1), $\pi(U)$ and $\pi(V)$ are open, so $\pi(U) \times \pi(V)$ is open in the product topology, and it contains (xH, yH). For $u \in U$ and $v \in V$, $\bar{q}(uH, vH) = \pi(q(u, v)) \in W$. So $\bar{q}^{-1}(W)$ contains an open neighborhood of each of its points, and it is open.

The first isomorphism theorem does not carry over to topological groups as it stands: for a continuous homomorphism f, the groups $G/\ker(f)$ and $f(G)$ need not be isomorphic as topological groups.

Example C.4.7: A Continuous Bijective Homomorphism That Is Not An Isomorphism
Let G be $\mathbb{R}$ with the discrete topology and K be $\mathbb{R}$ with the Euclidean topology, both topological groups under addition by example C.4.2. The identity map $f : G \to K$ is a continuous bijective homomorphism, since every subset of G is open. Its kernel is trivial, and $G/\ker(f)$ carries the discrete topology, since its projection from G is a bijection and every subset of G is open. So $G/\ker(f)$ is not isomorphic to $f(G) = K$ as a topological group: a homeomorphism would carry the open one-point set $\{0\}$ to a one-point open subset of K, while every non-empty open subset of K contains a ball $B_r(a)$ with $r > 0$, which is infinite.

Some authors make being Hausdorff (or at least T_1) part of the definition of the group. This limitation is not imposed in this definition, since in algebraic geometry, there will be non-Hausdorff spaces (ex. the a-adic topology on certain topological rings are non-Hausdorff). For Topological groups, there is a way to always find a quotient topology that is Hausdorff:

Proposition C.4.8

Let G be a topological group, $e \in G$ the identity, and $H = \bigcap_{\substack{U \subseteq G \text{ open} \\ e \in U}} U$. Then:

1. H is a normal subgroup
2. H is the closure of $\{e\}$, i.e. $\overline{\{e\}} = H$
3. G/H is Hausdorff
4. G is Hausdorff if and only if $H = \{e\}$

***Proof*:**
Write $\mathcal{U}$ for the collection of open subsets of G containing e, so that $H = \bigcap_{U \in \mathcal{U}} U$. Two preliminary facts get used throughout.

Translations are homeomorphisms. Fix $a \in G$ and let $\lambda_a(x) = ax$. The map $x \mapsto (a, x)$ is continuous, since the preimage of a basic open set $U \times V$ of $G \times G$ is V when $a \in U$ and is $\emptyset$ otherwise. Composing with the multiplication of definition C.4.1 shows λ_a is continuous, and $\lambda_{a^{-1}}$ is a two-sided inverse for it that is continuous for the same reason, so λ_a is a homeomorphism.

The same argument applies to right translation $\rho_a(x) = xa$.

Small sets around e. Given $U \in \mathcal{U}$, the map $q(x, y) = xy^{-1}$ of proposition C.4.3 is continuous and satisfies $q(e, e) = e \in U$, so $q^{-1}(U)$ is an open set containing (e, e) and therefore contains a basic open $W_1 \times W_2$ with $e \in W_1$ and $e \in W_2$. Setting $W = W_1 \cap W_2 \in \mathcal{U}$ gives $WW^{-1} \subseteq U$.

(1) Let $a, b \in H$ and let $U \in \mathcal{U}$. Choose $W \in \mathcal{U}$ with $WW^{-1} \subseteq U$. Then $a, b \in H \subseteq W$, so $ab^{-1} \in WW^{-1} \subseteq U$. Since $U \in \mathcal{U}$ was arbitrary, $ab^{-1} \in H$, and $e \in H$ because e lies in every member of $\mathcal{U}$. So H is a subgroup. For normality, fix $g \in G$ and let $c_g = \lambda_g \circ \rho_{g^{-1}}$, a homeomorphism of G with $c_g(e) = e$. Then $U \mapsto c_g(U)$ is a bijection of $\mathcal{U}$ onto itself, and a bijection of G carries intersections to intersections, so

$$gHg^{-1} = c_g\Big(\bigcap_{U \in \mathcal{U}} U\Big) = \bigcap_{U \in \mathcal{U}} c_g(U) = \bigcap_{V \in \mathcal{U}} V = H$$

(2) By definition C.1.8 together with proposition C.1.2, a point a lies in $\overline{\{e\}}$ if and only if every open set containing a contains e. For if some open $V \ni a$ omits e, then $G \setminus V$ is a closed set containing e, so $\overline{\{e\}} \subseteq G \setminus V$ and $a \notin \overline{\{e\}}$, and if $a \notin \overline{\{e\}}$, then $V = G \setminus \overline{\{e\}}$ is an open set containing a and omitting e. Now take $a \in H$ and V open with $a \in V$. The set $a^{-1}V = \lambda_{a^{-1}}(V)$ is open and contains e, so $H \subseteq a^{-1}V$. Part (1) gives $a^{-1} \in H$, so $a^{-1} = a^{-1}v$ for some $v \in V$, forcing $v = e$ and $e \in V$. Hence $H \subseteq \overline{\{e\}}$. Conversely take $a \in \overline{\{e\}}$ and $U \in \mathcal{U}$. The set $aU^{-1} = \{au^{-1} \mid u \in U\}$ is the image of the open set U^{-1} under λ_a, hence open, and it contains $ae^{-1} = a$. So $e \in aU^{-1}$, which says $e = au^{-1}$ for some $u \in U$, that is $a = u \in U$. Hence $a \in H$.

(3) First, $HU = U$ for *every* open $U \subseteq G$. Given $u \in U$, the set $Uu^{-1} = \rho_{u^{-1}}(U)$ is open and contains e, so $H \subseteq Uu^{-1}$ and $Hu \subseteq U$, while $U \subseteq HU$ because $e \in H$. Let $\pi : G \to G/H$ be the projection. For U open, $\pi^{-1}(\pi(U)) = UH = HU = U$ using normality, so $\pi(U)$ is open in the quotient topology of definition C.1.9. Now let $aH \neq bH$, so that $a^{-1}b \notin H$ and there is $U \in \mathcal{U}$ with $a^{-1}b \notin U$. Choose $W \in \mathcal{U}$ with $WW^{-1} \subseteq U$. The sets $\pi(aW)$ and $\pi(bW)$ are open and contain aH and bH, since $e \in W$. They are disjoint. For if $aw_1H = bw_2H$ with $w_1, w_2 \in W$, then $w_2^{-1}b^{-1}aw_1 \in H$, so $b^{-1}a \in w_2Hw_1^{-1} = w_2w_1^{-1}H$ by normality, and inverting gives $a^{-1}b \in Hw_1w_2^{-1} \subseteq HU = U$, which contradicts the choice of U. By definition C.1.11, G/H is Hausdorff.

(4) Suppose G is Hausdorff and let $a \in H$ with $a \neq e$. By definition C.1.11 there are disjoint open sets $U \ni e$ and $V \ni a$. Then $U \in \mathcal{U}$, so $a \in H \subseteq U$ and $a \in U \cap V = \emptyset$, which is impossible. Hence $H = \{e\}$. Conversely suppose $H = \{e\}$ and let $a \neq b$ in G. Then $a^{-1}b \neq e$, so $a^{-1}b \notin H$ and there is $U \in \mathcal{U}$ with $a^{-1}b \notin U$. Choose $W \in \mathcal{U}$ with $WW^{-1} \subseteq U$. The sets aW and bW are open by the translation fact and contain a and b. If $aw_1 = bw_2$ with $w_1, w_2 \in W$, then $a^{-1}b = w_1w_2^{-1} \in WW^{-1} \subseteq U$, against the choice of U. So $aW \cap bW = \emptyset$ and G is Hausdorff.

Topological groups are explored in a great many areas, and a few of them are listed here without detail. Perhaps the most studied topological groups are the *locally compact* ones, in which every point has an open neighborhood contained in a compact set. These are very useful in analysis. Every locally compact Hausdorff group carries a *Haar measure*, a nonzero Radon measure invariant under left translation and unique up to a positive scalar [51, Theorems 11.8 and 11.9]. The representation theory of locally compact groups leads to the *Fourier transform*: the irreducible unitary representations of $\mathbb{R}$ are the characters $t \mapsto e^{2\pi i \xi t}$ with $\xi \in \mathbb{R}$, and the Fourier transform decomposes the translation action of $\mathbb{R}$ on the Hilbert space $L^2(\mathbb{R})$ over these characters (section 53.4.1). Finally, topological groups show up in *Hilbert's fifth problem*. A continuous homomorphism between Lie groups is automatically

smooth [97, Continuous Homomorphisms Are Smooth], so a topological group carries at most one smooth structure making it a Lie group. Hilbert's fifth problem asks whether every topological group that is a topological manifold, that is, locally homeomorphic to $\mathbb{R}^n$, admits such a structure. The answer, due to Andrew Gleason, Deane Montgomery and Leo Zippin, is yes, and the structure can even be taken *real analytic*.

C.5 Completion in Topology

The last subject of topological groups we will explore here is the *completion* of topological groups, since it generalizes some of the results of *Commutative Algebra* [20] (completion). This definition of Cauchy generalizes that of the definition of a Cauchy sequence in a metric space by realizing that we only need to have a notion of "continuous subtraction" to define a Cauchy sequence. Throughout this section the groups are commutative and written additively.

Definition C.5.1: Cauchy Sequence In Topological Group

Let G be a commutative topological group and $(x_n) \subseteq G$ be a sequence. Then (x_n) is a *Cauchy sequence* if for every neighborhood U around 0, there exists a natural number $s(U) \in \mathbb{N}$ such that

$$x_n - x_m \in U \qquad \forall n, m > s(U)$$

Two Cauchy sequences (x_n) and (y_n) are *equivalent* if $(x_n - y_n)$ converges to 0, that is, if for every neighborhood U around 0 there is an $s(U) \in \mathbb{N}$ with $x_n - y_n \in U$ for all $n > s(U)$.

Just like for metric spaces, the collection of equivalence classes of Cauchy sequences is the completion of the group G, which we denote as $\hat{G}$. For any $g \in G$, the constant sequence (g) is a Cauchy sequence, and we identify G in $\hat{G}$ by the map $\iota : G \to \hat{G}$ via $g \mapsto [(g)]$. Note that ι is *not* in general injective.

Proposition C.5.2: The Completion Of A Topological Group

Let G be a commutative topological group. Then:

1. equivalence of Cauchy sequences is an equivalence relation, and $[(x_n)]+[(y_n)] = [(x_n+y_n)]$ is a well-defined operation making $\hat{G}$ an abelian group
2. ι is a homomorphism with kernel
$$\ker \iota = \bigcap_{\substack{0 \in U \\ U \text{ open}}} U$$
so ι is injective if and only if G is Hausdorff
3. a continuous homomorphism $f\colon G \to H$ of commutative topological groups induces a homomorphism $\hat{f}\colon \hat{G} \to \hat{H}$, $[(x_n)] \mapsto [(f(x_n))]$, and $\widehat{g \circ f} = \hat{g} \circ \hat{f}$ for a second continuous homomorphism $g\colon H \to K$

***Proof*:**
For every neighborhood U of 0 there is an open set W containing 0 with $W - W \subseteq U$: the map $q(x, y) = x - y$ is continuous (proposition C.4.3) and $q(0, 0) = 0$, so the open set $q^{-1}(U)$ contains a basic open set $W_1 \times W_2$ around $(0, 0)$, and $W = W_1 \cap W_2$ works. In particular, if $z \in W$, then $-z = 0 - z \in W - W \subseteq U$.

1. Reflexivity holds because $x_n - x_n = 0$ lies in every neighborhood of 0. If $x_n - y_n \in W$ for all large n, then $y_n - x_n \in U$ for all large n, which gives symmetry. For transitivity, if $(x_n) \sim (y_n)$ and $(y_n) \sim (z_n)$, then $x_n - y_n$ and, by symmetry, $z_n - y_n$ lie in W for all large n, so $x_n - z_n = (x_n - y_n) - (z_n - y_n) \in W - W \subseteq U$. If (x_n) and (y_n) are Cauchy, then

$$(x_n + y_n) - (x_m + y_m) = (x_n - x_m) - (y_m - y_n) \in W - W \subseteq U$$

for all large n, m, so $(x_n + y_n)$ is Cauchy. If $(x'_n) \sim (x_n)$ and $(y'_n) \sim (y_n)$, then $(x'_n + y'_n) - (x_n + y_n) = (x'_n - x_n) - (y_n - y'_n)$ lies in $W - W \subseteq U$ for all large n, so the sum of classes is well defined. The sequence $(-x_n)$ is Cauchy, since $(-x_n) - (-x_m) = -(x_n - x_m)$ and $x_n - x_m \in W$ for all large n, m, so $-(x_n - x_m) \in W - W \subseteq U$ by the first paragraph, and the group axioms hold termwise, with identity $[(0)]$ and inverse $[(-x_n)]$.

2. The map ι is a homomorphism by the definition of the sum. A constant sequence (g) is equivalent to (0) exactly when g lies in every neighborhood of 0, that is, in every open set containing 0, which gives the kernel. By proposition C.4.8(4), this intersection is $\{0\}$ exactly when G is Hausdorff.

3. Let V be a neighborhood of 0 in H. Then $f^{-1}(V)$ is a neighborhood of 0 in G, since f is continuous and $f(0) = 0$. If (x_n) is Cauchy, then $f(x_n) - f(x_m) = f(x_n - x_m) \in V$ for all large n, m, so $(f(x_n))$ is Cauchy, and in the same way f carries equivalent sequences to equivalent sequences. So $\hat{f}$ is well defined, it is a homomorphism because f is, and $\widehat{g \circ f}([(x_n)]) = [(g(f(x_n)))] = \hat{g}(\hat{f}([(x_n)]))$, completing the proof.

This construction is quite general: we can allow for $G = \mathbb{Q}$ with the euclidean topology, then $\hat{G} = \mathbb{R}$. We can also allow for $G = \mathbb{Q}$, and define a different metric (known as the p-metric), which will give us $\hat{G} = \mathbb{Q}_p$. We will focus on a particular case that useful for commutative algebra and show how it relates to completion.

Define a topology on a commutative group G by taking a descending sequence of subgroups[3]:

$$G = G_0 \supseteq G_1 \supseteq \cdots \supseteq G_n \supseteq \cdots$$

This is called a *filtration* of the group G. Declare $U \subseteq G$ open when for every $x \in U$ there is an n with $x + G_n \subseteq U$. These sets form a topology, called the *subgroup topology*: a union of such sets is again one, and if $x + G_n \subseteq U$ and $x + G_m \subseteq V$, then $x + G_{\max(n,m)} \subseteq U \cap V$ because the G_n decrease. Each coset $x + G_n$ is open, since $y + G_n = x + G_n$ for $y \in x + G_n$, so the cosets $x + G_n$ form a neighborhood basis at x, and $U \subseteq G$ is a neighborhood of 0 if and only if U contains some G_n. With this topology G is a topological group: if V is open and $x - y \in V$, choose n with $(x - y) + G_n \subseteq V$, and then the open set $(x + G_n) \times (y + G_n)$ is carried into $(x - y) + G_n \subseteq V$ by subtraction, so subtraction is continuous and proposition C.4.3 applies. An example of such a topology would be:

$$\mathbb{Z} \supseteq p\mathbb{Z} \supseteq p^2\mathbb{Z} \supseteq \cdots \supseteq p^n\mathbb{Z} \supseteq \cdots$$

[3] If G were not commutative, we would take a descending sequence of normal subgroups

The subgroup topology is interesting in that every subgroup G_n is open and closed (that is, clopen). First, for any $g \in G_n$, $g + G_n \subseteq G_n$, and so G_n is open. Thus, for any $h \notin G_n$, $h + G_n$ is open (since translation is a homeomorphism), and so:

$$H = \bigcup_{h \notin G_n} h + G_n$$

is open and disjoint from G_n. In fact, $H^c = G_n$, showing that G_n is *closed*.

Now, since G with the subgroup topology is a topological group, we can define $\hat{G}$ in the exact same way. Since the open sets are derived from a descending chain of subgroups G, Cauchy sequences induce a special type of sequence called a *coherent sequence*. Let (x_k) be a Cauchy sequence in G with the subgroup topology generated by (G_n). As G_n is a neighborhood of 0, $x_k - x_l \in G_n$ for all large k, l, so in G/G_n, the image of (x_k) must be eventually constant, say equal to ξ_n. When considering G_{n+1}, we get the eventual value ξ_{n+1}, and for k large, $x_k + G_{n+1} = \xi_{n+1}$ and $x_k + G_n = \xi_n$. So the natural projection

$$p_{n+1} : G/G_{n+1} \to G/G_n$$

maps ξ_{n+1} to ξ_n. The collection of these ξ_n's is called a *coherent sequence*. We chose the maps to be projection maps, however we may imagine a similar such sequence with any such functions, as long as they map to the right elements. Thus, being a little more general, a coherence sequence is a collection (ζ_n) such that for a collection of functions f_n, we have:

$$f_{n+1}(\zeta_{n+1}) = \zeta_n \qquad \forall n \in \mathbb{N}$$

The coherent sequences for the projections p_{n+1} form a subgroup of $\prod_n G/G_n$ under componentwise addition, because each p_{n+1} is a homomorphism.

Proposition C.5.3: Cauchy Sequences And Coherent Sequences

Let G be a commutative group with a filtration (G_n) and the subgroup topology. Sending the class of a Cauchy sequence to the coherent sequence (ξ_n) constructed above is a well-defined isomorphism from $\hat{G}$ onto the group of coherent sequences. In particular, equivalent Cauchy sequences define the same coherent sequence, and every coherent sequence is defined by a Cauchy sequence.

***Proof*:**
For $k \leq l$, the composite of the projections $G/G_l \to G/G_k$ sends $g + G_l$ to $g + G_k$, so, by induction on $l - k$, a coherent sequence ξ with $\xi_l = g + G_l$ has $\xi_k = g + G_k$ for every $k \leq l$. Write Φ for the map in the statement.

Well defined and additive. If $(x_k) \sim (y_k)$, then for each n the difference $x_k - y_k$ lies in the neighborhood G_n of 0 for all large k, so $x_k + G_n = y_k + G_n$ for all large k, and the two eventual values in G/G_n agree. If the images of (x_k) and (y_k) in G/G_n are eventually ξ_n and η_n, then that of $(x_k + y_k)$ is eventually $\xi_n + \eta_n$, so Φ is a homomorphism.

Injective. If $\Phi([(x_k)]) = 0$, then for each n, $x_k \in G_n$ for all large k. Every neighborhood of 0 contains some G_n, so (x_k) converges to 0, that is, $(x_k) \sim (0)$.

Surjective. Let ξ be a coherent sequence and choose $g_n \in G$ with $\xi_n = g_n + G_n$. For $k, l \geq n$, the first paragraph gives $g_k + G_n = \xi_n = g_l + G_n$, so $g_k - g_l \in G_n$. As every neighborhood of 0 contains some G_n, (g_k) is a Cauchy sequence, and its image in G/G_n is ξ_n for every $k \geq n$. Hence $\Phi([(g_k)]) = \xi$, completing the proof.

For this reason, the collection of all coherent sequences is also the completion of G, and is also denoted $\hat{G}$.

This now brings us to the same definition as given in chapter 25 in the case of Abelian groups: an *inverse system* is a collection of groups $\{A_n\}$ and homomorphisms f_n such that

$$f_{n+1} : A_{n+1} \to A_n$$

Then the group of all coherent sequences is called the *limit*, and is denoted $\varprojlim A_n$, where the homomorphism f_n are usually implicitly understood. With this notation, proposition C.5.3 says that:

$$\hat{G} \cong \varprojlim G/G_n$$

The most common subgroup topology and inverse system is when $G = R$ is a commutative ring and $G_n = I^n$ for an ideal I, with $I^0 = R$. In this case, the subgroup topology of R is called the *I-adic topology*, or simply the *I-topology*. Recall that we have defined a norm on a vector-space to define a topology. We can similarly define a norm generating the I-adic topology. Fix a real number $C > 1$ and define

$$\|x\| = C^{-n} \qquad \text{if} \qquad x \in I^n,\ x \notin I^{n+1}$$

If $x \in I^n$ for all $n \in \mathbb{N}$, then we will say that $\|x\| = 0$. Then through this norm, we can define a distance

$$d(x, y) = \|x - y\|$$

which is a metric when $\bigcap_n I^n = 0$. If $x - y \in I^n$, then $d(x, y) \leq C^{-n}$, and if $x - y \notin I^n$, then $x - y \in I^m \setminus I^{m+1}$ for some $m < n$ and $d(x, y) = C^{-m} > C^{-n}$. So $d(x, y) \leq C^{-n}$ exactly when $x - y \in I^n$, the open balls of d are the cosets $x + I^n$, and d defines the I-adic topology. In particular, a sequence is Cauchy for d exactly when it is Cauchy for the I-adic topology, and $d(x_k, y_k) \to 0$ exactly when $x_k - y_k \to 0$. Hence, when $\bigcap_n I^n = 0$, the completion of the metric space (R, d) described before definition C.1.19 is the completion $\hat{R}$ above, which is $\varprojlim R/I^n$ by proposition C.5.3. This new metric we have defined is also more powerful than the usual euclidean metric, namely:

$$\|x + y\| \leq \max(\|x\|, \|y\|) \qquad d(x, y) \leq \max(d(x, z), d(z, y))$$

since I^n is closed under addition. This metric condition is *much* stronger and is called an *ultra-metric*.

Proposition C.5.4: Balls In An Ultrametric

Let d be a metric on a set X with $d(x,y) \leq \max(d(x,z), d(z,y))$ for all $x, y, z \in X$, and write $B_r(x) = \{y \in X \mid d(x,y) < r\}$. Then:

1. Given a collection of any three points $x, y, z \in X$ one of the following three equalities must hold:

$$d(x,y) = d(y,z) \qquad d(x,z) = d(y,z) \qquad d(x,y) = d(z,x)$$

   Hence, every triple *must* form an isosceles triangle.

2. If $B_r(x)$ is an open ball then every point inside the ball is its center: if $d(x,y) < r$, then

$$B_r(x) = B_r(y)$$

3. Two balls that intersect are nested: if $B_r(x) \cap B_s(y) \neq \emptyset$ and $r \leq s$, then

$$B_r(x) \subseteq B_s(y)$$

4. If $r > 0$, then $B_r(x)$ is clopen.

***Proof*:**

1. Suppose the second equality fails, and by exchanging the names x and y if necessary, let $d(x,z) < d(y,z)$. Then $d(x,y) \leq \max(d(x,z), d(z,y)) = d(y,z)$, and $d(y,z) \leq \max(d(y,x), d(x,z))$, where the maximum must be $d(y,x)$ because $d(x,z) < d(y,z)$. So $d(x,y) = d(y,z)$. In the exchanged case this equality reads $d(x,y) = d(z,x)$.

2. If $z \in B_r(x)$, then $d(y,z) \leq \max(d(y,x), d(x,z)) < r$, so $B_r(x) \subseteq B_r(y)$. Since $d(y,x) < r$ as well, exchanging x and y gives the reverse inclusion.

3. Let $z \in B_r(x) \cap B_s(y)$. By (2), $B_r(x) = B_r(z)$ and $B_s(y) = B_s(z)$, and $B_r(z) \subseteq B_s(z)$ because $r \leq s$.

4. The ball $B_r(x)$ is open, and its complement is open: if $y \notin B_r(x)$, then $B_r(y)$ does not meet $B_r(x)$, since otherwise $B_r(y) = B_r(x)$ by (3) applied in both directions, and $y \in B_r(y)$ would lie in $B_r(x)$, completing the proof.

What is notable is that completion is the beginning of real analysis (and hence also PDEs), and given the strong algebraic structure introduced we also have variants such completions coming up in complex analysis. In [77], we shall use different completion of $\mathbb{Z}$ with p-adic metrics to construct fields in which we are "keeping track' of a single prime that is splitting or ramifying.

A commutative group G together with a filtration $G = G_0 \supseteq G_1 \supseteq \cdots$ by subgroups is called a *filtered group*. Its *completion* is the group of coherent sequences


$$\hat{G} = \varprojlim G/G_n = \{(\xi_n)_{n\geq 0} \mid \xi_n \in G/G_n,\ p_{n+1}(\xi_{n+1}) = \xi_n \text{ for all } n\}$$

with componentwise addition, where $p_{n+1} \colon G/G_{n+1} \to G/G_n$ is the natural projection. By proposition C.5.3 it is the completion of G for the subgroup topology. The map $\iota_G \colon G \to \hat{G}$, $g \mapsto (g+G_n)_n$, is

a homomorphism, and $\hat{G}$ is itself a filtered group with $\hat{G}_n = \left\{\xi \in \hat{G} \;\middle|\; \xi_n = 0\right\}$, a decreasing sequence because $\xi_{n+1} = 0$ forces $\xi_n = p_{n+1}(\xi_{n+1}) = 0$. A filtered group H is called *complete and Hausdorff* if ι_H is an isomorphism. The kernel of ι_H is $\bigcap_m H_m$, so ι_H is injective exactly when $\bigcap_m H_m = 0$. A homomorphism $f\colon G \to H$ of filtered groups is continuous for the subgroup topologies exactly when for every m there is an n with $f(G_n) \subseteq H_m$. If f is continuous, the open subgroup H_m has an open preimage containing 0, which therefore contains some G_n. Conversely, under the condition, if $V \subseteq H$ is open and $f(x) \in V$, then V contains some coset $f(x) + H_m$, and $f(x + G_n) \subseteq f(x) + H_m \subseteq V$ for an n with $f(G_n) \subseteq H_m$, so $f^{-1}(V)$ is open.

Theorem C.5.5: Universal Property Of Completion

Let G and H be filtered groups with H complete and Hausdorff, and let $f\colon G \to H$ be a continuous homomorphism, that is, for every m there is an n with $f(G_n) \subseteq H_m$. Then there is a unique continuous homomorphism $\hat{f}\colon \hat{G} \to H$ with $\hat{f} \circ \iota_G = f$:



***Proof*:**
For $k \le l$ the composite $G/G_l \to G/G_k$ of the projections $p_l, \dots, p_{k+1}$ sends $g + G_l$ to $g + G_k$. So, by induction on $l - k$, a coherent sequence ξ with $\xi_l = g + G_l$ has $\xi_k = g + G_k$ for every $k \le l$.

Existence. For each m choose $n(m)$ with $f(G_{n(m)}) \subseteq H_m$. Replacing each $n(m)$ by the largest of $n(0), \dots, n(m)$, which is allowed because the G_n decrease, we may assume $n(0) \le n(1) \le \cdots$. The homomorphism

$$f_m\colon G/G_{n(m)} \to H/H_m \qquad g + G_{n(m)} \mapsto f(g) + H_m$$

is well defined, since $f(G_{n(m)}) \subseteq H_m$. For $\xi \in \hat{G}$ put $\eta_m = f_m(\xi_{n(m)})$. The sequence $\eta = (\eta_m)_m$ is coherent: writing $\xi_{n(m+1)} = g + G_{n(m+1)}$, the first paragraph gives $\xi_{n(m)} = g + G_{n(m)}$, so $\eta_{m+1} = f(g) + H_{m+1}$ projects to $f(g) + H_m = \eta_m$. Hence $\eta \in \hat{H}$, and we put $\hat{f}(\xi) = \iota_H^{-1}(\eta)$. Each component of $\xi \mapsto \eta$ is a composite of homomorphisms, so $\hat{f}$ is a homomorphism. For $g \in G$, the sequence $\xi = \iota_G(g)$ has $\xi_{n(m)} = g + G_{n(m)}$, so $\eta_m = f(g) + H_m$ for every m, that is, $\eta = \iota_H(f(g))$, and $\hat{f}(\iota_G(g)) = f(g)$. Finally, if $\xi \in \hat{G}_{n(m)}$, then $\eta_m = f_m(0) = 0$, so $h = \hat{f}(\xi)$ satisfies $h + H_m = (\iota_H(h))_m = \eta_m = 0$, that is, $\hat{f}(\hat{G}_{n(m)}) \subseteq H_m$, and $\hat{f}$ is continuous.

Uniqueness. Let $F_1, F_2\colon \hat{G} \to H$ be continuous homomorphisms with $F_1 \circ \iota_G = F_2 \circ \iota_G = f$, and let $D = F_1 - F_2$. Then $D \circ \iota_G = 0$, and for every m there is an n with $D(\hat{G}_n) \subseteq H_m$, obtained by taking the larger of the indices for F_1 and for F_2. Let $\xi \in \hat{G}$ and $m \ge 0$, choose such an n, and write $\xi_n = g + G_n$ with $g \in G$. Then $\xi - \iota_G(g)$ has nth component 0, so it lies in $\hat{G}_n$, and

$$D(\xi) = D(\xi - \iota_G(g)) + D(\iota_G(g)) = D(\xi - \iota_G(g)) \in H_m$$

As m was arbitrary, $D(\xi) \in \bigcap_m H_m = \ker \iota_H = 0$, so $F_1(\xi) = F_2(\xi)$, completing the proof.

D

Lattice Theory

D.1 Lattice Theory

We first generalize the notion of gcd and lcm for partial orders:

Definition D.1.1: GCD and LCM for Partially ordered sets

Let $(S, \leq)$ be a partially ordered set. Then

1. a *lowerbound* of a subset $T \subseteq S$ is an element $l \in S$ such that $l \leq t$ for all $t \in T$. A *greatest lower bound* (gcd) is a lowerbound g such that for any other lower-bound l, $l \leq g$. In lattice theory, the greatest lower bound is also called the *meet* or *infimum*
2. an *upperbound* of a subset $T \subseteq S$ is an element $u \in S$ such that $t \leq u$ for all $t \in T$. A *least upper bound* (lcm) is a upper-bound ℓ such that for any other upper-bounds u, $\ell \leq u$. In lattice theory, the least upper bound is also called the *join* or *supremum*

A meet or join, if it exists, is unique: two greatest lower bounds g and g' of T satisfy $g \leq g'$ and $g' \leq g$, so $g = g'$ by antisymmetry, and the same argument applies to least upper bounds. If the meet/join of a subset exists for a subset $T \subseteq S$, then it is denoted:

$$\bigwedge_{t \in T} t \qquad \text{and} \qquad \bigvee_{t \in T} t$$

Definition D.1.2: Lattice

Let $(S, \leq)$ be a partially ordered set. Then

1. If for any two $a, b \in S$, $a \wedge b$ exists, then S is called a *lower semi-lattice*
2. If for any two $a, b \in S$, $a \vee b$ exists, then S is called a *upper semi-lattice*
3. If S is both a lower and upper semi-lattice, S is called a *lattice*.

Proposition D.1.3: Properties Of Lattice Binary Operation

Let L be a lattice. Then $\vee$ and $\wedge$ as binary operations are

idempotent, commutative, associative, and order preserving.

Furthermore, by using induction, every finite non-empty subset has a meet and join

***Proof*:**

A subset of L has at most one greatest lower bound. For if g and g' are both, then $g \leq g'$ and $g' \leq g$ as each is a lower bound, so $g = g'$ by the antisymmetry of definition A.1.4. The same argument bounds least upper bounds, so the notations $a \wedge b$ and $a \vee b$ of definition D.1.2 name single elements.

It is enough to argue for $\wedge$. Reversing the order relation of L exchanges lower bounds with upper bounds and greatest with least, so it turns every statement about $\wedge$ into the corresponding statement about $\vee$, and L with the reversed order is again a lattice.

Idempotent. The element a is a lower bound of $\{a\}$ by the reflexivity of definition A.1.4, and any lower bound l of $\{a\}$ satisfies $l \leq a$. So a is the greatest lower bound of $\{a\} = \{a, a\}$, that is $a \wedge a = a$.

Commutative. The sets $\{a, b\}$ and $\{b, a\}$ are equal, so they have the same lower bounds and the same greatest lower bound.

Associative. The element $(a \wedge b) \wedge c$ is a lower bound of $\{a, b, c\}$, since it is below $a \wedge b$, hence below a and b, and it is below c. If l is any lower bound of $\{a, b, c\}$, then $l \leq a$ and $l \leq b$ give $l \leq a \wedge b$, and $l \leq c$ then gives $l \leq (a \wedge b) \wedge c$. So $(a \wedge b) \wedge c$ is the greatest lower bound of $\{a, b, c\}$. The same computation identifies $a \wedge (b \wedge c)$ as the greatest lower bound of $\{a, b, c\}$, and the two agree by uniqueness.

Order preserving. Suppose $a \leq a'$. Then $a \wedge b \leq a \leq a'$ by transitivity and $a \wedge b \leq b$, so $a \wedge b$ is a lower bound of $\{a', b\}$ and therefore $a \wedge b \leq a' \wedge b$.


Finite subsets. Let $T = \{a_1, \ldots, a_n\}$ with $n \geq 1$. For $n = 1$ the meet is a_1. For $n > 1$, the argument given for associativity shows by induction that $(a_1 \wedge \cdots \wedge a_{n-1}) \wedge a_n$ is a lower bound of T and dominates every lower bound of T, so it is the meet of T.

Example D.1.4: Lattices

1. $\mathbb{N}, \mathbb{Z}, \mathbb{Q}, \mathbb{R}$ and ordered fields (section 21.1) with their order all form lattices, with $a \wedge b = \min(a, b)$ and $a \vee b = \max(a, b)$, since in a total order the smaller of a and b lies above every

lower bound of $\{a, b\}$, and dually.

2. Let S be a set with powerset $P(S)$. Then with $\cup$ and $\cap$, $P(S)$ is a lattice
3. Let S be the collection of all (subgroups/ideals/submodules) of (group/ring/module). Then S forms a lattice with $A \cap B \in S$ and $\langle A \cup B \rangle \in S$. In the ideal/submodule case, $\langle A \cup B \rangle = A + B$.
4. Any partially ordered set can be represented by a graph where an edge represents where $x \leq y$ if $x \to y$. Then the following are examples of non-lattices:



5. Let X be a topological space. Then the open sets of X, ordered by inclusion, form a lattice with $U \vee V = U \cup V$ and $U \wedge V = U \cap V$, both open by definition C.1.1.

Unlike most algebraic structures encountered with two binary operations, lattices are *not* distributive in general. In the lattice of subgroups of $\mathbb{Z}/2 \times \mathbb{Z}/2$, let A, B and C be the subgroups generated by $(1, 0)$, $(0, 1)$ and $(1, 1)$. Then $B \vee C$ contains $(0, 1) + (1, 1) = (1, 0)$, so it is the whole group, and

$$A \wedge (B \vee C) = A \qquad (A \wedge B) \vee (A \wedge C) = \{0\}$$

since distinct subgroups of order 2 meet in $\{0\}$. Lattices have the following alternative:

Proposition D.1.5: Absorption Law

Let L be a lattice and $x, y \in L$. Then:

$$x \wedge (x \vee y) = x \qquad x \vee (x \wedge y) = x$$

***Proof*:**
By definition D.1.1 the element $x \vee y$ is an upper bound of $\{x, y\}$, so $x \leq x \vee y$. Together with $x \leq x$ this makes x a lower bound of $\{x, x \vee y\}$. Any lower bound l of $\{x, x \vee y\}$ satisfies $l \leq x$ by definition. So x is the greatest lower bound of $\{x, x \vee y\}$, which by the uniqueness established in proposition D.1.3 gives $x \wedge (x \vee y) = x$.

For the second identity, $x \wedge y$ is a lower bound of $\{x, y\}$, so $x \wedge y \leq x$, and with $x \leq x$ this makes x an upper bound of $\{x, x \wedge y\}$. Any upper bound u of that set satisfies $x \leq u$. So x is the least upper bound of $\{x, x \wedge y\}$, that is $x \vee (x \wedge y) = x$.

Using the above result, we can formulate lattices purely algebraically:

Proposition D.1.6: Algebraic Definition Of A Lattice

Let L be a set with binary operations $\vee$ and $\wedge$ that are associative and commutative and satisfy the absorption laws of proposition D.1.5. Then the relation

$$x \leq y \qquad \text{if and only if} \qquad x \wedge y = x$$

is a partial order on L under which L is a lattice, and $x \wedge y$ and $x \vee y$ are the meet and the join of $\{x, y\}$ for that order

***Proof*:**
Two identities come first.

Both operations are idempotent. The second absorption law with y replaced by a gives $a \vee (a \wedge a) = a$. Feeding that into the first absorption law with $x = a$ and $y = a \wedge a$ gives

$$a = a \wedge \big(a \vee (a \wedge a)\big) = a \wedge a$$

and then $a \vee a = a \vee (a \wedge a) = a$ by the first law again.

The two descriptions of the order agree. If $x \wedge y = x$, then

$$x \vee y = (x \wedge y) \vee y = y \vee (y \wedge x) = y$$

using commutativity and the second absorption law. If $x \vee y = y$, then $x \wedge y = x \wedge (x \vee y) = x$ by the first absorption law. So $x \leq y$ holds exactly when $x \vee y = y$.

Now check the three conditions of definition A.1.4. Reflexivity is $x \wedge x = x$, which is idempotency. For antisymmetry, $x \leq y$ and $y \leq x$ give $x = x \wedge y = y \wedge x = y$. For transitivity, $x \leq y$ and $y \leq z$ give

$$x \wedge z = (x \wedge y) \wedge z = x \wedge (y \wedge z) = x \wedge y = x$$

so $x \leq z$.

Next, $x \wedge y$ is the greatest lower bound of $\{x, y\}$. It is a lower bound, since $(x \wedge y) \wedge x = (x \wedge x) \wedge y = x \wedge y$ gives $x \wedge y \leq x$, and the same computation with the roles of x and y exchanged gives $x \wedge y \leq y$. If $l \leq x$ and $l \leq y$, then

$$l \wedge (x \wedge y) = (l \wedge x) \wedge y = l \wedge y = l$$

so $l \leq x \wedge y$.

Finally, $x \vee y$ is the least upper bound of $\{x, y\}$. The first absorption law gives $x \wedge (x \vee y) = x$, so $x \leq x \vee y$, and commutativity gives $y \wedge (y \vee x) = y$, so $y \leq x \vee y$. If $x \leq u$ and $y \leq u$, then $x \vee u = u$ and $y \vee u = u$ by the description of the order proved above, whence

$$(x \vee y) \vee u = x \vee (y \vee u) = x \vee u = u$$

so $x \vee y \leq u$. Every pair therefore has a meet and a join, and L is a lattice by definition D.1.2.

Naturally, a lattice homomorphism is an order-homomorphism (a map φ with $\varphi(x) \leq \varphi(y)$ whenever $x \leq y$) such that $\varphi(x \vee y) = \varphi(x) \vee \varphi(y)$ and $\varphi(x \wedge y) = \varphi(x) \wedge \varphi(y)$. Note that not all order-

homomorphisms are lattice homomorphisms. The map φ from $P(\{1,2\})$ to the two-element chain $0<1$ sending $\{1,2\}$ to 1 and the other three subsets to 0 preserves order, but

$$\varphi(\{1\}\vee\{2\})=\varphi(\{1,2\})=1 \qquad \varphi(\{1\})\vee\varphi(\{2\})=0\vee 0=0$$

However an order-isomorphism, a bijection φ with $x\le y$ if and only if $\varphi(x)\le\varphi(y)$, is a lattice-isomorphism. The element $\varphi(x\vee y)$ is an upper bound of $\{\varphi(x),\varphi(y)\}$, since $x,y\le x\vee y$. Any upper bound has the form $\varphi(v)$, as φ is onto, and then $x\le v$ and $y\le v$, so $x\vee y\le v$ and $\varphi(x\vee y)\le\varphi(v)$. Hence $\varphi(x\vee y)=\varphi(x)\vee\varphi(y)$, and dually $\varphi(x\wedge y)=\varphi(x)\wedge\varphi(y)$. The inverse of φ is again an order-isomorphism, so it preserves both operations as well.

Lattices as they are can be considered as two commutative *semigroups* with a compatible structure (see section 7); the absorption being the unique feature of lattices. If furthermore the lattice is bounded, then it shall have a monoid structure.

Definition D.1.7: Bounded Lattice

Let L be a lattice. Then L is said to be *bounded* if there exists an minimal element (denoted 0 or $\bot$) and a maximal element (denoted 1 or $\top$) such that for all $x\in L$:

$$\bot\le x\le\top \qquad \text{equiv.} \qquad 0\le x\le 1$$

As an algebraic structures, we can think of a bounded lattice as a set $(L,\vee,\wedge,0,1)$ such that $(L,\vee,\wedge)$ is a lattice, 0 is the identity element for the join operation $\vee$, and 1 is the identity element for the meet operation $\wedge$:

$$a\vee 0=a \qquad a\wedge 1=a$$

If we require the stronger condition that every subset $S\subseteq L$ of a lattice has a supremum and infimum, we get the following stronger notion:

Definition D.1.8: Complete Lattice

Let L be a lattice. Then if every subset $S\subseteq L$ has a gcd and lcm, then L is said to be a *complete lattice*

This makes L a bounded lattice, for $L\subseteq L$ must have a gcd and lcm. Every finite set can be made into a complete lattice, however $\mathbb{N},\mathbb{Q},\mathbb{R}$ are incomplete. Every non-empty closed and bounded subset C of $\mathbb{R}$, such as $[0,1]$, is complete: a non-empty $T\subseteq C$ has a supremum and an infimum in $\mathbb{R}$, which lie in C because each is a limit of a sequence in T and C is closed, and the empty subset has supremum $\min C$ and infimum $\max C$, which exist by the case $T=C$. More notably, $P(X)$ for any set X, as well as the collection of (subgroups/ideals/submodules) of (groups/rings/modules) forms a complete lattice.

Given any lattice, it can be embedded in a complete lattice. Rather interestingly, this shall link to Galois connections and the closure map:

Definition D.1.9: Closure Map

Let $(S,\le)$ be a partially ordered set. Then a *closure map* is an order-homomorphism $\Gamma:S\to S$ that is idempotent, $(\Gamma\circ\Gamma)=\Gamma$, and expanding, $(\Gamma(x)\ge x$ for all $x\in S)$. An element $x\in S$ is *closed relative to* Γ if $\Gamma(x)=x$.

The closure map is so named since the closure map $A \mapsto \overline{A}$ is the quintessential closure map.

Lemma D.1.10: Closed Element Infimum and Supremum

Let L be a complete lattice, let Γ be a closure map on L, and let $C \subseteq L$ be the set of elements closed relative to Γ. Then C is closed under the infimums of L, and C is itself a complete lattice in which the infimum of $T \subseteq C$ is the infimum $\bigwedge T$ taken in L and the supremum of T is $\Gamma\big(\bigvee T\big)$.
The set C need *not* be closed under the supremums of L.

***Proof*:**
Let $T \subseteq C$ and put $m = \bigwedge T$, the infimum taken in L, which exists by definition D.1.8. For each $t \in T$ the relation $m \leq t$ and the order preservation of Γ give $\Gamma(m) \leq \Gamma(t) = t$, so $\Gamma(m)$ is a lower bound of T and therefore $\Gamma(m) \leq m$. Since Γ is expanding, $m \leq \Gamma(m)$, so $\Gamma(m) = m$ by antisymmetry and $m \in C$. This is the first assertion, and it says at the same time that $\bigwedge T$ is the infimum of T inside C.

Now put $s = \bigvee T$, again taken in L, and let $\hat{s} = \Gamma(s)$. Idempotency gives $\Gamma(\hat{s}) = \hat{s}$, so $\hat{s} \in C$. For $t \in T$ the relations $t \leq s \leq \Gamma(s) = \hat{s}$ show $\hat{s}$ is an upper bound of T. If $u \in C$ is any upper bound of T in C, then $s \leq u$ and $\hat{s} = \Gamma(s) \leq \Gamma(u) = u$. So $\hat{s}$ is the supremum of T inside C. Every subset of C therefore has an infimum and a supremum in C, and C is a complete lattice by definition D.1.8.

For the last assertion, take $X = \mathbb{R}$ with the Euclidean topology, $L = P(X)$ ordered by inclusion, and $\Gamma(A) = \overline{A}$ the topological closure of definition C.1.8. This Γ is a closure map. It preserves inclusions, since every closed set containing B contains A when $A \subseteq B$. It is expanding, since A is contained in each of the sets being intersected. It is idempotent, since $\overline{A}$ is already closed. Its closed elements are the closed subsets of $\mathbb{R}$. The supremum in L of the family $\big\{[1/n, 1]\big\}_{n \geq 1}$ is the union $(0, 1]$, which is not closed, while the supremum of that family inside C is $\Gamma\big((0, 1]\big) = [0, 1]$.

Next, we define the Galois connection more generally:

Definition D.1.11: Antitone Galois Connection

Let X, Y be two partially ordered sets. Then a *galois connection* between X, Y is a pair of order-reversing homomorphism, say $\alpha : X \to Y$ and $\beta : Y \to X$ such that for all $x \in X$ and $y \in Y$:

$$(\beta \circ \alpha)(x) \geq x \qquad (\alpha \circ \beta)(y) \geq y$$

Naturally, the Galois correspondence is a Galois connection, and the generalization to closed groups shows the correspondence in the infinite case.

Lemma D.1.12: Galois Connection And Lattices

Let X, Y be partially ordered sets and (α, β) a Galois connection. Then

1. α, β, induce order-reversing mutually inverse bijections between $\mathrm{im}(\alpha)$ and $\mathrm{im}(\beta)$
2. $\alpha \circ \beta$ and $\beta \circ \alpha$ are closure maps
3. If X, Y are complete lattices, $\mathrm{im}(\alpha)$ and $\mathrm{im}(\beta)$ are complete lattices

***Proof*:**
Everything rests on the two identities

$$\alpha \circ \beta \circ \alpha = \alpha \qquad \beta \circ \alpha \circ \beta = \beta$$

For the first, definition D.1.11 gives $(\beta \circ \alpha)(x) \geq x$, and applying the order-reversing α turns this into $\alpha\big(\beta(\alpha(x))\big) \leq \alpha(x)$. The same definition applied to the element $y = \alpha(x)$ of Y gives $\alpha\big(\beta(\alpha(x))\big) \geq \alpha(x)$. Antisymmetry gives equality. The second identity is the same argument with the roles of α and β exchanged.

(1) For $v = \alpha(x) \in \mathrm{im}(\alpha)$ the first identity gives $\alpha\big(\beta(v)\big) = \alpha\big(\beta(\alpha(x))\big) = \alpha(x) = v$, and for $u = \beta(y) \in \mathrm{im}(\beta)$ the second gives $\beta\big(\alpha(u)\big) = u$. In particular β carries $\mathrm{im}(\alpha)$ into $\mathrm{im}(\beta)$ and α carries $\mathrm{im}(\beta)$ into $\mathrm{im}(\alpha)$, and the two restrictions are mutually inverse. Each is order-reversing, being a restriction of an order-reversing map.

(2) Write $\Gamma_X = \beta \circ \alpha$. A composite of two order-reversing maps preserves order, so Γ_X is an order-homomorphism, and $\Gamma_X(x) \geq x$ is part of definition D.1.11. The first identity gives

$$\Gamma_X \circ \Gamma_X = \beta \circ (\alpha \circ \beta \circ \alpha) = \beta \circ \alpha = \Gamma_X$$

so Γ_X is idempotent and is a closure map in the sense of definition D.1.9. The same holds for $\Gamma_Y = \alpha \circ \beta$ on Y.

(3) The elements of X closed relative to Γ_X are exactly the elements of $\mathrm{im}(\beta)$. For if $\Gamma_X(x) = x$ then $x = \beta(\alpha(x)) \in \mathrm{im}(\beta)$, and if $x \in \mathrm{im}(\beta)$ then $\Gamma_X(x) = x$ by part (1). So when X is a complete lattice, lemma D.1.10 applies to Γ_X and makes $\mathrm{im}(\beta)$ a complete lattice, with infimums inherited from X and with the supremum of $T \subseteq \mathrm{im}(\beta)$ equal to $\Gamma_X\big(\bigvee T\big)$. The same argument with Γ_Y makes $\mathrm{im}(\alpha)$ a complete lattice when Y is one. The supremums are the ones described above and are in general not those of the ambient lattice, as the last part of lemma D.1.10 shows.

Theorem D.1.13: Lattice Embedding Theorem

Let $(L, \leq)$ be a partially ordered set. Then L can be embedded in a complete lattice $\hat{L}$ in such a way that every infimum and every supremum that exists in L is preserved.

***Proof*:**
For $A \subseteq L$ write

$$A^u = \{z \in L \mid a \leq z \text{ for all } a \in A\} \qquad A^\ell = \{w \in L \mid w \leq a \text{ for all } a \in A\}$$

for the sets of upper and lower bounds of A. Both operations reverse inclusion, since a bound

for a larger set is a bound for a smaller one, and both satisfy $A \subseteq A^{u\ell}$ and $A \subseteq A^{\ell u}$, since every element of A sits below every upper bound of A and above every lower bound. So the pair $(A \mapsto A^u,\ B \mapsto B^\ell)$ is a Galois connection on $(P(L), \subseteq)$ in the sense of definition D.1.11.

The poset $(P(L), \subseteq)$ is a complete lattice, the infimum of a family of subsets being its intersection and the supremum its union. By lemma D.1.12 the map $\Gamma(A) = A^{u\ell}$ is a closure map on $P(L)$, and by lemma D.1.10 the set

$$\hat{L} = \left\{ A \subseteq L \;\middle|\; A^{u\ell} = A \right\}$$

of its closed elements is a complete lattice, in which the infimum of a family is its intersection and the supremum of a family is Γ applied to its union.

Define $\varphi : L \to \hat{L}$ by $\varphi(x) = D(x) = \{y \in L \mid y \leq x\}$. This lands in $\hat{L}$: the upper bounds of $D(x)$ are the elements above every $y \leq x$, and since $x \in D(x)$ these are exactly the elements above x, so $D(x)^u = \{z \mid x \leq z\}$, and the same computation run downwards gives $D(x)^{u\ell} = D(x)$. The map φ is an order embedding. For if $x \leq y$ then transitivity gives $D(x) \subseteq D(y)$, and if $D(x) \subseteq D(y)$ then $x \in D(x) \subseteq D(y)$ gives $x \leq y$. In particular φ is injective, since $D(x) = D(y)$ forces $x \leq y$ and $y \leq x$.

Let $T \subseteq L$ be non-empty. Then

$$\bigcap_{t \in T} \varphi(t) = \{y \in L \mid y \leq t \text{ for all } t \in T\} = T^\ell$$

Suppose T has an infimum m in L. Then $m \in T^\ell$ and every element of T^ℓ lies below m, so $T^\ell = D(m) = \varphi(m)$. The left side is the infimum of $\varphi(T)$ in $\hat{L}$, so φ carries the infimum of T to the infimum of $\varphi(T)$.

For supremums, the upper bounds of $\bigcup_{t \in T} \varphi(t) = \bigcup_{t \in T} D(t)$ are the elements above every $y \leq t$ for every t, and since $t \in D(t)$ these are exactly the elements above every t, so $\left(\bigcup_{t \in T} \varphi(t)\right)^u = T^u$. Suppose T has a supremum s in L. Then $T^u = \{z \mid s \leq z\}$, and applying $(-)^\ell$ gives $T^{u\ell} = D(s)$, because an element below every $z \geq s$ is below s and conversely. Hence the supremum of $\varphi(T)$ in $\hat{L}$, which is $\Gamma\left(\bigcup_{t \in T} \varphi(t)\right) = T^{u\ell}$, equals $\varphi(s)$.

The empty subset takes one more line. An infimum of $\emptyset$ in L is a greatest element $\top$, and $\varphi(\top) = D(\top) = L$, which is the greatest element of $\hat{L}$ and so the infimum of the empty family there. A supremum of $\emptyset$ in L is a least element $\bot$, and $\varphi(\bot) = \{\bot\} = L^\ell = \emptyset^{u\ell}$, which is the least element of $\hat{L}$.

Examples of Lattices

Lattices are rather general objects. As it turns out, when working the set of sub-objects of an R-module with $(+, \cap)$, we get some more interesting behavior:

Definition D.1.14: Modular Lattice

Let L be a lattice. Then L is called *modular* if whenever $x \leq z$,

$$x \vee (y \wedge z) = (x \vee y) \wedge z$$

Note that for any lattice, if $x \leq z$ then x and $y \wedge z$ are lower bounds of $\{x \vee y, z\}$ and hence:

$$x \vee (y \wedge z) \leq (x \vee y) \wedge z$$

Thus, a lattice is modular if and only if $x \leq z$ implies $x \vee (y \wedge z) \geq (x \vee y) \wedge z$. Note that the opposite of a modular lattice is modular, hence the theory is self-dual. As mentioned, the name modular lattice comes straight form the lattice of submodules:


Example D.1.15: Modular Lattices

Letting $(\vee, \wedge) = (+, \cap)$, and taking the lattice of submodules of an R-module. Then if $A \subseteq C$, then taking $x \in (A + B) \cap C$ we have $x = a + b \in C$ for some appropriate $a \in A \subseteq C$. Then $b = x - a \in C$, and $x = a + b \in A + (B \cap C)$

Detecting when a lattice fails to be modular is similar to how to detect a complete bipartite graph:

Proposition D.1.16: Detecting Modular Lattice

Let L be a lattice. Then L is modular if and only if it does not contain a sub-lattice isomorphic to N_5:



***Proof*:**

In the pictured lattice N_5 the order is $0 < b < c < 1$ and $0 < a < 1$, with a incomparable to b and to c, so $a \wedge c = 0$ and $a \vee b = 1$. Taking $x = b$, $y = a$ and $z = c$, the hypothesis $x \leq z$ of definition D.1.14 holds, while

$$b \vee (a \wedge c) = b \vee 0 = b \qquad (b \vee a) \wedge c = 1 \wedge c = c$$

differ. So N_5 is not modular. The modular law is an identity in $\vee$ and $\wedge$, so it passes to sub-lattices, and a lattice with a sub-lattice isomorphic to N_5 cannot be modular.

For the converse, suppose L is not modular. Then there are $x \leq z$ and y in L with $x \vee (y \wedge z) \neq (x \vee y) \wedge z$, and by the inequality recorded after definition D.1.14 the failure is

$$b := x \vee (y \wedge z) \quad < \quad c := (x \vee y) \wedge z$$

Put $a = y$, $0 = y \wedge z$ and $1 = x \vee y$. Four computations, each using proposition D.1.3 to rearrange meets and joins, pin down the configuration.

First, $a \wedge c = y \wedge (x \vee y) \wedge z = y \wedge z = 0$, since $y \leq x \vee y$. Second, $b \leq c$ gives $a \wedge b \leq a \wedge c = 0$, while $0 = y \wedge z \leq x \vee (y \wedge z) = b$ and $0 \leq y = a$, so $a \wedge b = 0$. Third, $a \vee b = y \vee x \vee (y \wedge z) = x \vee y = 1$,

since $y \wedge z \leq y$. Fourth, $a \vee c \geq a \vee b = 1$ and $a \vee c \leq 1$ because $a = y \leq 1$ and $c \leq x \vee y = 1$, so $a \vee c = 1$.

Now the five elements are distinct. If $b = 0$, then $x \vee (y \wedge z) = y \wedge z$, so $x \leq y \wedge z \leq y$ and $1 = x \vee y = y = a$, whence $c = (x \vee y) \wedge z = y \wedge z = 0 = b$, against $b < c$. If $c = 1$, then $0 = a \wedge c = a \wedge 1 = y$, so $y = y \wedge z$ and $y \leq z$, whence $b = x \vee (y \wedge z) = x \vee y = 1$ and $b \geq c$, again against $b < c$. So $0 \leq b < c \leq 1$ with $b \neq 0$ and $c \neq 1$, and the chain $0 < b < c < 1$ is strict. As for a, the relation $b \leq a$ would give $a \wedge b = b \neq 0$ and $a \leq b$ would give $a \vee b = b \neq 1$, so a is incomparable to b, and the identical argument with c in place of b makes a incomparable to c. Finally $a \neq 0$ because $a \vee b = 1 \neq b$, and $a \neq 1$ because $a \wedge c = 0 \neq c$.

The set $\{0, a, b, c, 1\}$ is closed under $\vee$ and $\wedge$, since the four computations above handle the pairs involving a, the pair $\{b, c\}$ gives $b \wedge c = b$ and $b \vee c = c$, and 0 and 1 are the least and greatest of the five. It is therefore a sub-lattice, and the order described above is that of N_5.

Modular lattices help generalize results such as part (2) of theorem 3.7.9 (that any two composition series of a finite group have the same length).

Proposition D.1.17: Modular Lattices And Finite Maximal Chains

Let L be a modular lattice. Then any two finite maximal chains have the same length

***Proof*:**
Say that v *covers* u when $u < v$ and no $w \in L$ satisfies $u < w < v$. A chain of L is maximal when no element of L can be added to it and leave a chain, in the sense of definition A.1.4. The *length* of a finite chain with $k + 1$ elements is k.

A finite maximal chain runs from a least to a greatest element by covers. Let $C : u_0 < u_1 < \cdots < u_k$ be a finite maximal chain. If some w satisfied $u_i < w < u_{i+1}$, then $C \cup \{w\}$ would be a chain properly containing C, so each u_{i+1} covers u_i. If some $w \in L$ satisfied $w < u_0$, the same objection applies, so u_0 is minimal in L, and then for any $y \in L$ the element $u_0 \wedge y$ satisfies $u_0 \wedge y \leq u_0$, so minimality forces $u_0 \wedge y = u_0$ and $u_0 \leq y$. Hence u_0 is the least element $\bot$ of L, and dually u_k is the greatest element $\top$.

Main claim. If a modular lattice M has a maximal chain of length k, then every chain of M has at most $k + 1$ elements. Argue by induction on k. For $k = 0$ the chain is a single element that is both least and greatest, so M has one element and every chain has one element. Let $k \geq 1$ and let $\bot = x_0 \lessdot x_1 \lessdot \cdots \lessdot x_k = \top$ be a maximal chain, where $\lessdot$ marks a cover. The interval $M' = \{v \in M \mid x_1 \leq v\}$ is closed under $\vee$ and $\wedge$, hence a lattice, and it inherits the identity of definition D.1.14, so it is modular. Its least element is x_1 and its greatest is $\top$, and $x_1 \lessdot x_2 \lessdot \cdots \lessdot x_k$ is a maximal chain of M' of length $k - 1$. By induction every chain of M' has at most k elements.

Let $u_0 < u_1 < \cdots < u_r$ be a chain of M and consider $u_0 \vee x_1 \leq u_1 \vee x_1 \leq \cdots \leq u_r \vee x_1$, a chain of M' by proposition D.1.3. Suppose $u_i \vee x_1 = u_{i+1} \vee x_1$ for some i. Since $u_i \leq u_{i+1}$, definition D.1.14 applies with $x = u_i$, $y = x_1$ and $z = u_{i+1}$ and gives

$$u_i \vee (x_1 \wedge u_{i+1}) = (u_i \vee x_1) \wedge u_{i+1} = (u_{i+1} \vee x_1) \wedge u_{i+1} = u_{i+1}$$

the last step because $u_{i+1} \leq u_{i+1} \vee x_1$. If $x_1 \wedge u_{i+1} \leq u_i$ held, the left side would be u_i and $u_i = u_{i+1}$, which is false, so $x_1 \wedge u_{i+1} \neq \bot$. As $\bot \lessdot x_1$ and $\bot \leq x_1 \wedge u_{i+1} \leq x_1$, this forces $x_1 \wedge u_{i+1} = x_1$, that is $x_1 \leq u_{i+1}$. Let i_0 be the least index at which such a coincidence occurs.

For $j > i_0$ the relation $x_1 \leq u_{i_0+1} \leq u_j$ gives $u_j \vee x_1 = u_j$, and these are strictly increasing, so no further coincidence occurs. Hence the chain $\{u_i \vee x_1\}$ has at least r distinct members, and the induction bound gives $r \leq k$. So $u_0 < \cdots < u_r$ has at most $k+1$ elements, proving the main claim.

Now let C and D be finite maximal chains of L, of lengths m and n. Applying the main claim to the maximal chain C and the chain D gives $n+1 \leq m+1$, and applying it the other way round gives $m+1 \leq n+1$. Hence $m = n$.

A little more restrictive than modular lattices are *distributive* lattices:


Definition D.1.18: Distributive Lattice

Let $(L, \vee, \wedge)$ be a lattice. Then L is a *distributive lattice* if one of the two equivalent conditions hold for all $x, y, z \in L$:

1. $x \vee (y \wedge z) = (x \vee y) \wedge (x \vee z)$
2. $x \wedge (y \vee z) = (x \wedge y) \vee (x \wedge z)$

Proposition D.1.19: Detecting Distributive Lattices

Let L be a lattice. Then L is a distributive lattice if and only if L does not have a sublattice isomorphic to N_5 or M_5, where M_5 is the lattice:



***Proof*:**
Both forms of the distributive law get used, so start with their equivalence. Assume form (2) of definition D.1.18. Then

$$(x\vee y)\wedge(x\vee z) = \big((x\vee y)\wedge x\big)\vee\big((x\vee y)\wedge z\big) = x\vee\big((z\wedge x)\vee(z\wedge y)\big) = \big(x\vee(x\wedge z)\big)\vee(y\wedge z) = x\vee(y\wedge z)$$

The first equality is form (2) applied with $x \vee y$ in the leading slot. The second applies proposition D.1.5 to the left summand and form (2) to the right. The third is proposition D.1.3 and the fourth is proposition D.1.5 again. Reversing the order of L turns this derivation into the derivation of form (2) from form (1).

Suppose L is distributive. Both forms are identities in $\vee$ and $\wedge$, so every sublattice of L is distributive. Neither N_5 nor M_5 is distributive. For N_5, form (1) applied with $x \leq z$ gives $x \vee (y \wedge z) = (x \vee y) \wedge (x \vee z) = (x \vee y) \wedge z$, so a distributive lattice is modular and proposition D.1.16 rules N_5 out. In M_5 the elements a, b, c give $a \wedge (b \vee c) = a \wedge 1 = a$ against $(a \wedge b) \vee (a \wedge c) = 0 \vee 0 = 0$. So L has no sublattice isomorphic to either.

For the converse, suppose L is not distributive. If L is not modular, then proposition D.1.16 produces a sublattice isomorphic to N_5 and there is nothing more to do. So assume L is modular

and fix x, y, z with $x \wedge (y \vee z) \neq (x \wedge y) \vee (x \wedge z)$. Both $x \wedge y$ and $x \wedge z$ lie below x and below $y \vee z$, so

$$(x \wedge y) \vee (x \wedge z) \quad < \quad x \wedge (y \vee z)$$

Set

$$d = (x \wedge y) \vee (y \wedge z) \vee (z \wedge x) \qquad e = (x \vee y) \wedge (y \vee z) \wedge (z \vee x)$$

Each of the three meets in d lies below each of the three joins in e, for instance $x \wedge y \leq x \leq x \vee y$ and $x \wedge y \leq y \leq y \vee z$ and $x \wedge y \leq x \leq z \vee x$, so $d \leq e$. Put

$$a = d \vee (x \wedge e) \qquad b = d \vee (y \wedge e) \qquad c = d \vee (z \wedge e)$$

all of which lie in the interval between d and e.

Since $d \leq e$, definition D.1.14 gives $a = d \vee (x \wedge e) = (d \vee x) \wedge e$, and $d \vee x = x \vee (y \wedge z)$ because the summands $x \wedge y$ and $z \wedge x$ of d lie below x. Writing $X = x \vee (y \wedge z)$, and Y, Z for the corresponding elements built from y and from z, this says $a = X \wedge e$, $b = Y \wedge e$ and $c = Z \wedge e$.

The three joins. Since $X \leq x \vee y$ and $X \leq z \vee x$, the meet $X \wedge e$ collapses to $X \wedge (y \vee z)$, and definition D.1.14 applied to $y \wedge z \leq y \vee z$ gives

$$a = X \wedge (y \vee z) = \big((y \wedge z) \vee x\big) \wedge (y \vee z) = (y \wedge z) \vee \big(x \wedge (y \vee z)\big)$$

Now $z \wedge x \leq x$ and $z \wedge x \leq z \leq y \vee z$, so $z \wedge x \leq x \wedge (y \vee z)$, and $y \wedge z \leq y$, so

$$a \vee Y = (y \wedge z) \vee \big(x \wedge (y \vee z)\big) \vee y \vee (z \wedge x) = y \vee \big(x \wedge (y \vee z)\big) = (y \vee x) \wedge (y \vee z)$$

the last step being definition D.1.14 applied to $y \leq y \vee z$. Since $a \leq e$, a further application of definition D.1.14 gives $a \vee b = a \vee (Y \wedge e) = (a \vee Y) \wedge e$, and e lies below both $x \vee y$ and $y \vee z$, so

$$a \vee b = (y \vee x) \wedge (y \vee z) \wedge e = e$$

The construction of d, e, a, b, c is symmetric in x, y, z, so the same computation gives $b \vee c = c \vee a = e$.

The three meets. Reversing the order of L leaves L modular, as recorded after definition D.1.14, exchanges d with e, and fixes a, b and c, since $a = d \vee (x \wedge e) = (d \vee x) \wedge e$ exhibits a in both of the two dual forms. So the previous paragraph, carried out in the reversed order, gives $a \wedge b = b \wedge c = c \wedge a = d$.

The five elements are distinct. Suppose $a = d$. Then $e = a \vee b = d \vee b = b$ and likewise $e = c$, so $d = b \wedge c = e$. The same argument applies to b and to c, and if $a = e$ then $d = a \wedge b = e \wedge b = b$, which returns to the previous case. So it is enough to rule out $d = e$. If $d = e$, then $a = X \wedge e = d$, and meeting the two descriptions of a with x gives, on the one hand,

$$\big((y \wedge z) \vee (x \wedge (y \vee z))\big) \wedge x = \big(x \wedge (y \vee z)\big) \vee (x \wedge y \wedge z) = x \wedge (y \vee z)$$

by definition D.1.14 applied to $x \wedge (y \vee z) \leq x$, and on the other hand, writing $s = (x \wedge y) \vee (z \wedge x) \leq x$,

$$d \wedge x = \big(s \vee (y \wedge z)\big) \wedge x = s \vee (x \wedge y \wedge z) = s$$

by definition D.1.14 applied to $s \leq x$. These two say $x \wedge (y \vee z) = (x \wedge y) \vee (x \wedge z)$, contradicting the choice of x, y, z. Hence $d \neq e$, and d, a, b, c, e are five distinct elements with a, b, c pairwise incomparable, since $a \leq b$ would give $a \wedge b = a \neq d$.

The set $\{d, a, b, c, e\}$ is closed under $\vee$ and $\wedge$, by the six computations above together with $d \leq a, b, c \leq e$, so it is a sublattice isomorphic to M_5.

The power-set $P(X)$ is the canonical distributive lattice with $(\cup, \cap)$. In fact a lattice is distributive if and only if it is isomorphic to a sublattice of $P(X)$ for some appropriate X. To see this, we require the following build-up

Definition D.1.20: Lattice Irreducible Elements

Let L be a lattice. Then an element $i \in L$ is called *sup-irreducible* (or just *irreducible*) if i is not a minimal element and:

$$x \vee y = i \quad \Rightarrow \quad x = i \text{ or } y = i$$

The collection of irreducible elements is denoted $\text{Irr}(L)$.

In $P(X)$, singletons are irreducible.

Proposition D.1.21: Lattice And Irreducible

Let L be a lattice satisfying the descending chain condition. Then every element $x \in L$ is the join of a finite subset of $\{i \in \text{Irr}(L) \mid i \leq x\}$, where the join of the empty set is read as the least element of L. Consequently $x = \bigvee \{i \in \text{Irr}(L) \mid i \leq x\}$

***Proof*:**
First, L has a least element. The descending chain condition says every non-empty subset of L has a minimal element, so L itself has one, say $\bot$, and for any $y \in L$ the element $\bot \wedge y$ satisfies $\bot \wedge y \leq \bot$, so minimality forces $\bot \wedge y = \bot$ and $\bot \leq y$. The same computation shows $\bot$ is the only minimal element of L, so by definition D.1.20 an element failing to be irreducible is either $\bot$ or admits $u \vee v = i$ with $u \neq i$ and $v \neq i$.

Let S be the set of elements of L that are *not* a join of a finite set of irreducible elements. Suppose $S \neq \emptyset$ and let x be a minimal element of S, which exists by the descending chain condition. Then $x \neq \bot$, since $\bot$ is the join of the empty set, and $x \notin \text{Irr}(L)$, since otherwise x is the join of $\{x\}$. By the previous paragraph there are $u, v \in L$ with $u \vee v = x$, $u \neq x$ and $v \neq x$. Both lie below x, so $u < x$ and $v < x$, and minimality of x in S puts $u, v \notin S$. Writing u and v as finite joins of irreducible elements and joining the two finite sets writes x as one as well, contradicting $x \in S$. Hence $S = \emptyset$.

Let $F \subseteq \text{Irr}(L)$ be finite with $x = \bigvee F$. Every $i \in F$ satisfies $i \leq x$, so F is contained in $T = \{i \in \text{Irr}(L) \mid i \leq x\}$. Now x is an upper bound of T by the definition of T, and any upper bound u of T is an upper bound of F, hence satisfies $x = \bigvee F \leq u$. So x is the least upper bound of T, that is $x = \bigvee T$.

Definition D.1.22: Order Ideal

Let S be a partially ordered set. Then a [left] order ideal $I \subseteq S$ is a subset such that if $y \in I$ and:

$$x \leq y \in I \quad \Rightarrow \quad x \in I$$

Order ideals naturally create a distributive lattice given any partially ordered set:

Proposition D.1.23: Order Ideals And Partially Ordered Sets

Let S be a partially ordered set. Then the order ideals, ordered by inclusion, produce a distributive lattice, denoted $\text{Ideals}(S)$

***Proof*:**
Let I and J be order ideals of S. If $x \leq y$ with $y \in I \cup J$, then y lies in one of the two, and that one contains x by definition D.1.22, so $x \in I \cup J$. If $x \leq y$ with $y \in I \cap J$, then $x \in I$ and $x \in J$ by the same definition, so $x \in I \cap J$. Hence $\text{Ideals}(S)$ is closed under finite unions and intersections.

Ordered by inclusion, $I \cup J$ is an upper bound of $\{I, J\}$, and any order ideal containing both contains their union, so $I \vee J = I \cup J$. Dually $I \cap J$ is a lower bound of $\{I, J\}$ contained in every order ideal contained in both, so $I \wedge J = I \cap J$. Every pair has a meet and a join, so $\text{Ideals}(S)$ is a lattice by definition D.1.2.

Distributivity is the corresponding identity for sets. For order ideals I, J, K and any $x \in S$, the statement $x \in I \cap (J \cup K)$ says that $x \in I$ and that x lies in J or in K, which says exactly that $x \in (I \cap J) \cup (I \cap K)$. So form (2) of definition D.1.18 holds.

Theorem D.1.24: Finite Distributive Lattices And Ideals

Let L be a finite lattice, and give $\text{Irr}(L)$ the order it inherits from L. Then L is a distributive lattice if and only if

$$L \cong \text{Ideals}(\text{Irr}(L))$$

***Proof*:**
If $L \cong \text{Ideals}(\text{Irr}(L))$, then L is distributive, since proposition D.1.23 makes the right side distributive and a lattice isomorphism carries the identity of definition D.1.18 across.

Assume L is distributive. A finite lattice satisfies the descending chain condition, so proposition D.1.21 applies. Define

$$\varphi : L \to \text{Ideals}(\text{Irr}(L)) \qquad \varphi(x) = T(x) = \{i \in \text{Irr}(L) \mid i \leq x\}$$

Each $T(x)$ is an order ideal of $\text{Irr}(L)$, since $j \leq i \leq x$ with j irreducible gives $j \in T(x)$.

Meets. An irreducible i satisfies $i \leq x \wedge y$ exactly when $i \leq x$ and $i \leq y$, so $\varphi(x \wedge y) = T(x) \cap T(y) = \varphi(x) \wedge \varphi(y)$.

Joins. The inclusion $T(x) \cup T(y) \subseteq T(x \vee y)$ is clear. For the reverse, let $i \in \text{Irr}(L)$ with $i \leq x \vee y$. Form (2) of definition D.1.18 gives

$$i = i \wedge (x \vee y) = (i \wedge x) \vee (i \wedge y)$$

so by definition D.1.20 either $i = i \wedge x$ or $i = i \wedge y$, that is $i \leq x$ or $i \leq y$. Hence $\varphi(x \vee y) = T(x) \cup T(y) = \varphi(x) \vee \varphi(y)$.

Injectivity. If $T(x) = T(y)$, then proposition D.1.21 gives $x = \bigvee T(x) = \bigvee T(y) = y$.

Surjectivity. Let J be an order ideal of $\text{Irr}(L)$ and put $x = \bigvee J$, a join of a finite set and hence available by proposition D.1.3, with the empty join read as the least element of L. Every $j \in J$

satisfies $j \leq x$, so $J \subseteq T(x)$. Conversely let $i \in T(x)$. If $J = \emptyset$, then x is the least element of L and $i \leq x$ makes i minimal, which definition D.1.20 forbids, so $J \neq \emptyset$, say $J = \{j_1, \ldots, j_r\}$ with $r \geq 1$. Iterating form (2) of definition D.1.18 gives

$$i = i \wedge (j_1 \vee \cdots \vee j_r) = (i \wedge j_1) \vee \cdots \vee (i \wedge j_r)$$

and iterating definition D.1.20 gives $i = i \wedge j_k$ for some k, that is $i \leq j_k$. Since J is an order ideal, $i \in J$. Hence $T(x) = J$ and φ is onto.

A bijection preserving both operations is a lattice isomorphism, so $L \cong \text{Ideals}(\text{Irr}(L))$.

For a distributive lattice that is not finite, prime ideals take the place of irreducible elements in the embedding into a power-set.

Definition D.1.25: Ideals Of A Lattice

Let L be a lattice. An *ideal* of L is a non-empty order ideal $I \subseteq L$ (definition D.1.22) such that $x \vee y \in I$ whenever $x, y \in I$. An ideal P is *prime* if $P \neq L$ and $x \wedge y \in P$ implies $x \in P$ or $y \in P$.

Lemma D.1.26: Prime Ideal Theorem

Let L be a distributive lattice, let I be an ideal of L, and let $a \in L \setminus I$. Then there is a prime ideal P of L with $I \subseteq P$ and $a \notin P$.

***Proof*:**
Let $\mathcal{I}$ be the set of ideals J of L with $I \subseteq J$ and $a \notin J$, ordered by inclusion. It contains I. Let $\mathcal{C}$ be a chain in $\mathcal{I}$. If $\mathcal{C}$ is empty, then I is an upper bound for it. Otherwise put $J_0 = \bigcup \mathcal{C}$, a non-empty order ideal. If $x, y \in J_0$, then x and y lie in members of $\mathcal{C}$ of which one contains the other, so $x \vee y$ lies in the larger one. So J_0 is an ideal, it contains I and omits a, and it is an upper bound for $\mathcal{C}$ in $\mathcal{I}$. By theorem A.2.3, $\mathcal{I}$ has a maximal element P.

Since $a \notin P$, $P \neq L$. Suppose $x \wedge y \in P$ with $x \notin P$ and $y \notin P$. The set

$$P_x = \{z \in L \mid z \leq p \vee x \text{ for some } p \in P\}$$

is an ideal: it contains x, it is an order ideal by transitivity, and $z_1 \leq r_1 \vee x$ and $z_2 \leq r_2 \vee x$ with $r_1, r_2 \in P$ give $z_1 \vee z_2 \leq (r_1 \vee r_2) \vee x$ with $r_1 \vee r_2 \in P$. It contains P, since $r \leq r \vee x$ for $r \in P$, and it contains $x \notin P$, so the maximality of P forces $P_x \notin \mathcal{I}$, that is, $a \in P_x$, and $a \leq p_1 \vee x$ for some $p_1 \in P$. The set $P_y = \{z \in L \mid z \leq p \vee y \text{ for some } p \in P\}$ is an ideal as well: it contains y, it is an order ideal by transitivity, and $z_1 \leq r_1 \vee y$ and $z_2 \leq r_2 \vee y$ with $r_1, r_2 \in P$ give $z_1 \vee z_2 \leq (r_1 \vee r_2) \vee y$. It contains P, since $r \leq r \vee y$ for $r \in P$, and it contains $y \notin P$, so the maximality of P forces $a \in P_y$, and $a \leq p_2 \vee y$ for some $p_2 \in P$. Put $p = p_1 \vee p_2 \in P$. The two forms of definition D.1.18 are equivalent, as the proof of proposition D.1.19 shows at its start, and form (1) gives

$$a \leq (p \vee x) \wedge (p \vee y) = p \vee (x \wedge y)$$

The right side lies in P, since p and $x \wedge y$ do, so $a \in P$, a contradiction. Hence P is prime.

Theorem D.1.27: Distributive Lattices And Power-Sets

A lattice L is distributive if and only if it is isomorphic to a sublattice of $(P(X), \cup, \cap)$ for some set X, that is, to a non-empty family of subsets of X closed under $\cup$ and $\cap$, ordered by inclusion. If L is distributive and X is the set of prime ideals of L, then $V(x) = \{P \in X \mid x \notin P\}$ defines a lattice isomorphism V from L onto such a family.

***Proof*:**
A non-empty family $\mathcal{F} \subseteq P(X)$ closed under $\cup$ and $\cap$ is a lattice with $\vee = \cup$ and $\wedge = \cap$, and it is distributive, since the set identity $A \cap (B \cup C) = (A \cap B) \cup (A \cap C)$ is form (2) of definition D.1.18. A lattice isomorphic to $\mathcal{F}$ is distributive, since an isomorphism carries the identity across.

Conversely, let L be distributive, let X be the set of prime ideals of L, and let $P \in X$ and $x, y \in L$. The element $x \wedge y$ lies in P exactly when x or y does: if $x \in P$, then $x \wedge y \leq x$ puts $x \wedge y$ in P, likewise for y, and the converse is primality. The element $x \vee y$ lies in P exactly when x and y both do: P is closed under joins, and $x, y \leq x \vee y$. Taking complements in X,

$$V(x \wedge y) = V(x) \cap V(y) \qquad V(x \vee y) = V(x) \cup V(y)$$

So $V(L)$ is closed under $\cup$ and $\cap$, and V preserves both operations. It is injective. If $x \neq y$, then by antisymmetry $x \not\leq y$ or $y \not\leq x$, say $x \not\leq y$. The set $\{z \in L \mid z \leq y\}$ is an ideal not containing x, so lemma D.1.26 gives a prime ideal P containing y and not x, and then $P \in V(x) \setminus V(y)$. Hence V is a bijection from L onto $V(L)$ preserving both operations, that is, a lattice isomorphism.

A final important lattice naturally arises in mathematical logic, known as a *boolean lattice*. In a Boolean lattice, the meet, join, and "complement" correspond to conjunction, disjunction, and negation in mathematical logic:

Definition D.1.28: Boolean Lattice

Let L be a bounded lattice (hence containing a 0 and 1). Then a *complement* of an element $a \in L$ is an element a' such that $a \wedge a' = 0$ and $a \vee a' = 1$. Then L is a *Boolean lattice* if it is distributive and every element has a complement.

Distributivity is what makes the complement unique: if b and c both complement a then $b = b \wedge 1 = b \wedge (a \vee c) = (b \wedge a) \vee (b \wedge c) = b \wedge c$, and symmetrically $c = c \wedge b$, so $b = c$. Without it uniqueness fails, as M_5 shows, where each of the three incomparable elements complements the other two. Complementation is not a lattice homomorphism: it is an order-reversing involution, satisfying De Morgan's laws $(x \wedge y)' = x' \vee y'$ and $(x \vee y)' = x' \wedge y'$.

Example D.1.29: Boolean Lattice

For an easy example of a Boolean lattice take the power-set $P(X)$ with compliment $Y' = X \setminus Y$. For a more interesting example, let R be a Boolean ring (i.e. a ring such that for $x \in R$, $x^2 = x$). Then define a partial order on R via:

$$x \leq y \qquad \text{if and only if} \qquad xy = x$$

Then we get a boolean lattice via

$$x \wedge y = xy \qquad x \vee y = x + y + xy \qquad x' = 1 - x$$

Interestingly, the all Boolean lattices can be converted into Boolean rings, for a Boolean lattice $(L, \vee, \wedge, (-)', 0, 1)$ define:

$$x + y = (x' \wedge y) \vee (x \wedge y') \qquad xy = x \wedge y$$

denote this ring $R(L)$. Then

$$\mathrm{L}(\mathrm{R}(L)) = L \qquad \mathrm{R}(\mathrm{L}(R)) = R$$

Since power-sets are naturally boolean lattices, they offer themselves to the following classification theorem:

Theorem D.1.30: Finite Boolean Lattice Classification

Let L be a finite lattice. Then L is a boolean lattice if and only if there exists a set X such that

$$L \cong P(X)$$

***Proof*:**
First, $P(X)$ is a Boolean lattice. It is a lattice under $\cup$ and $\cap$ (example D.1.4), distributive by the set identity $A \cap (B \cup C) = (A \cap B) \cup (A \cap C)$, which is form (2) of definition D.1.18, bounded by $\emptyset \subseteq A \subseteq X$, and $X \setminus A$ complements A. A lattice isomorphism preserves the order, since $x \leq y$ exactly when $x \wedge y = x$, so it carries least and greatest elements to least and greatest elements, complements to complements, and the distributive identity across. Hence a lattice isomorphic to $P(X)$ is Boolean.

Conversely, let L be a finite Boolean lattice. It is distributive, so theorem D.1.24 gives $L \cong \mathrm{Ideals}(\mathrm{Irr}(L))$. No two distinct irreducible elements are comparable. Suppose $j < i$ with $i, j \in \mathrm{Irr}(L)$, and let j' be a complement of j. Form (2) of definition D.1.18 and $i \wedge j = j$ give

$$i = i \wedge 1 = i \wedge (j \vee j') = (i \wedge j) \vee (i \wedge j') = j \vee (i \wedge j')$$

so by definition D.1.20 either $j = i$, which $j < i$ excludes, or $i \wedge j' = i$, that is, $i \leq j'$. In the second case $j \leq i \leq j'$, so $j = j \wedge j' = 0$. But 0 is the least element of L, hence minimal, and an irreducible element is not minimal, a contradiction. So in $\mathrm{Irr}(L)$, with its inherited order, $x \leq y$ holds only when $x = y$, every subset of $\mathrm{Irr}(L)$ is an order ideal in the sense of definition D.1.22, and $\mathrm{Ideals}(\mathrm{Irr}(L))$ is all of $P(\mathrm{Irr}(L))$ with the operations $\cup$ and $\cap$. Hence $L \cong P(\mathrm{Irr}(L))$.

To generalize to general boolean lattices, we require the following lemmas:

Lemma D.1.31: Stone Space Basis

Let L be a Boolean lattice, and let X be the set of prime ideals of L in the sense of definition D.1.25. Then the sets

$$V(a) = \{P \in X \mid a \notin P\} \qquad a \in L$$

form a basis for a topology on X. Furthermore, $V(0) = \emptyset$, $V(1) = X$, $V(a \wedge b) = V(a) \cap V(b)$, and $V(a') = X \setminus V(a)$

***Proof*:**
Every prime ideal P contains 0, since it is non-empty and $0 \leq p$ for any $p \in P$, so $0 \in P$ because P is an order ideal. Hence $V(0) = \emptyset$. No prime ideal contains 1, since every $a \in L$ satisfies $a \leq 1$, so $1 \in P$ would give $P = L$, against properness. Hence $V(1) = X$.

Next, $V(a \wedge b) = V(a) \cap V(b)$. If $a \in P$, then $a \wedge b \leq a$ puts $a \wedge b$ in P, and likewise if $b \in P$, so $a \wedge b \notin P$ forces $a \notin P$ and $b \notin P$. Conversely, if $a \wedge b \in P$, then primality gives $a \in P$ or $b \in P$.

These two facts give the conditions of definition C.1.3. Every $P \in X$ lies in $V(1) = X$, which is the first condition. For the second, let $P \in V(a) \cap V(b)$. The member $V(a \wedge b)$ of the family contains P and is contained in $V(a) \cap V(b)$, since the two sets are equal. So the family $\{V(a) \mid a \in L\}$ is a basis for a topology on X.

Finally, $V(a) \cap V(a') = V(a \wedge a') = V(0) = \emptyset$ by definition D.1.28. And $V(a) \cup V(a') = X$, because if a prime ideal P contained both a and a', then $1 = a \vee a' \in P$, since prime ideals are closed under joins, contradicting $V(1) = X$. A set disjoint from $V(a)$ whose union with $V(a)$ is X is $X \setminus V(a)$, so $V(a') = X \setminus V(a)$.

Theorem D.1.32: Boolean Lattice Classification

Let L be a lattice. Then L is a Boolean lattice if and only if there exists a set X such that L is isomorphic to a *field of sets* on X, that is, to a family $\mathcal{F} \subseteq P(X)$, ordered by inclusion, that contains $\emptyset$ and X and is closed under $\cup$, $\cap$ and $A \mapsto X \setminus A$.

***Proof*:**
A field of sets $\mathcal{F}$ on X is a sublattice of $P(X)$, so it is distributive by theorem D.1.27. It is bounded by $\emptyset$ and X, and $X \setminus A \in \mathcal{F}$ complements $A \in \mathcal{F}$, so $\mathcal{F}$ is a Boolean lattice. As in the proof of theorem D.1.30, a lattice isomorphic to a Boolean lattice is Boolean.

Conversely, let L be a Boolean lattice and X the set of its prime ideals. It is distributive, so by theorem D.1.27 the map V is a lattice isomorphism from L onto the sublattice $V(L)$ of $P(X)$. By lemma D.1.31, $V(0) = \emptyset$, $V(1) = X$ and $V(a') = X \setminus V(a)$, so $V(L)$ contains $\emptyset$ and X and is closed under complements. Hence $V(L)$ is a field of sets on X.

As mentioned, the above topology has a special name:

Definition D.1.33: Stone Space

Let L be a Boolean lattice and X the collection of prime ideals of L. Then with the above basis, X is called the *stone space*.

Proposition D.1.34: Stone Space Properties

Let X be the stone space of a Boolean lattice L. Then X is compact and Hausdorff, and it is totally disconnected: no subset of X with more than one point is connected in the subspace topology.

***Proof*:**
Write $V(a) = \{P \in X \mid a \notin P\}$ as in lemma D.1.31. For distinct $P, Q \in X$ there is an $a \in L$ with $Q \in V(a)$ and $P \in V(a')$. Indeed $P \not\subseteq Q$ or $Q \not\subseteq P$, and after exchanging the names P and Q if necessary there is an $a \in P \setminus Q$. Then $Q \in V(a)$ and $P \notin V(a)$, that is, $P \in X \setminus V(a) = V(a')$ by lemma D.1.31.

Hausdorff. The open sets $V(a) \ni Q$ and $V(a') \ni P$ are disjoint, since $V(a') = X \setminus V(a)$.

Totally disconnected. Let $S \subseteq X$ contain distinct points P and Q, and take a as above. The sets $S \cap V(a)$ and $S \cap V(a')$ are open in S, disjoint, non-empty, as they contain Q and P, and their union is S. So S is not connected (definition C.3.3).

Compact. Let $\mathcal{O}$ be an open cover of X. Each member of $\mathcal{O}$ is a union of basic open sets $V(a)$, so the set T of those $a \in L$ for which $V(a)$ lies inside some member of $\mathcal{O}$ satisfies $\bigcup_{a \in T} V(a) = X$. It suffices to find $a_1, \ldots, a_n \in T$ with $V(a_1) \cup \cdots \cup V(a_n) = X$, since a member of $\mathcal{O}$ containing each $V(a_k)$ then gives a finite subcover. Suppose there are none, and let I be the set of $z \in L$ with $z \leq a_1 \vee \cdots \vee a_n$ for some $n \geq 0$ and $a_1, \ldots, a_n \in T$, the empty join being 0. Then I is an ideal in the sense of definition D.1.25: it contains 0, it is an order ideal, and two such bounds join to a bound of the same kind. If $1 \in I$, then $1 = a_1 \vee \cdots \vee a_n$ for some $a_k \in T$, and lemma D.1.31 and theorem D.1.27 give $X = V(1) = V(a_1) \cup \cdots \cup V(a_n)$, against the assumption. So $1 \notin I$, and lemma D.1.26, which applies since L is distributive, gives a prime ideal $P \supseteq I$. Every $a \in T$ lies in I, hence in P, so P lies in no $V(a)$ with $a \in T$, contradicting $\bigcup_{a \in T} V(a) = X$.

For any topological space Y, the clopen subsets of Y form a field of sets on Y: $\emptyset$ and Y are clopen, the complement of a clopen set is clopen, and a union or intersection of two clopen sets is open by definition C.1.1 and closed by proposition C.1.2. So they form a Boolean lattice $\mathrm{L}(Y)$ by theorem D.1.32. A compact Hausdorff totally disconnected space is called a *Stone space*, and proposition D.1.34 says that the stone space of a Boolean lattice is one.

E

Model Theory

Model theory studies a mathematical structure through the first-order sentences it satisfies. A *first-order language* fixes symbols for operations, relations and constants, and its formulas are built from these symbols, equality, the logical connectives and the quantifiers $\forall x$ and $\exists x$, whose variables range over the elements of a structure and never over its subsets. The language of ordered fields has the symbols $+$, $\cdot$, $-$, 0, 1 and $\leq$, and $\mathbb{R}$ is a structure for it. A substructure A of a structure B is *elementary* if every formula with parameters from A holds in A exactly when it holds in B.

E.1 Löwenheim-Skolem Theorem

Theorem E.1.1: Downward Löwenheim-Skolem Theorem

Let $\mathcal{L}$ be a countable first-order language and B a structure for $\mathcal{L}$. Then B has a countable elementary substructure.

The proof closes a countable subset of B under witnesses for the existential statements that hold in B. It needs the formal definitions of formulas and of satisfaction, which this appendix does not develop, and is given in [71, Downward Löwenheim-Skolem Theorem].

The theorem shows that the first-order algebra of $\mathbb{R}$ does not determine $\mathbb{R}$. Apply it to $\mathbb{R}$ in the language of ordered fields. The result is a countable subset $K \subseteq \mathbb{R}$, closed under the operations and ordered by the restriction of $\leq$, in which exactly the same first-order sentences hold as in $\mathbb{R}$. In particular K is an ordered field, since the ordered field axioms are such sentences, and $K \ncong \mathbb{R}$, since $\mathbb{R}$ is uncountable. So no collection of first-order statements about $+$, $\cdot$ and $\leq$ characterizes $\mathbb{R}$ up to isomorphism. The completeness of $\mathbb{R}$, that every non-empty subset bounded above has a supremum, quantifies over subsets, so it is not a first-order sentence of this language.

Part XIV

Glossary, Index, Bibliography

Glossary of Algebraic Structures

In this chapter, we list many of the algebraic structures discussed throughout the book. These are categorized by subject and are roughly grouped by the order in which they appear with priority given to grouping properties together and examples together. To find where these objects appear in the textbook, see the appendix (which is sorted in alphabetical order).

Fundamental Structures

- Set; Relation, Equivalence Relation, Partial Order, Total Order
- Function (Injective, Surjective, Bijective); Cardinality
- Number Systems ($\mathbb{N}$, $\mathbb{Z}$, $\mathbb{Q}$, $\mathbb{R}$, $\mathbb{C}$); Modular Arithmetic ($\mathbb{Z}/n\mathbb{Z}$)
- Graph, Lattice; Matrix

Groups

Basic Group Types and Properties

- Group; Abelian Group; Subgroup; Normal Subgroup; Characteristic Subgroup
- Quotient Group; Homomorphism, Isomorphism, Endomorphism, Automorphism (including Inner Automorphism, Outer Automorphism)
- Kernel, Image; Center, Centralizer, Normalizer
- Order of a Group, Order of an Element; Generators and Relations, Presentations of Groups

Examples of Groups

- Cyclic Group (C_n, $\mathbb{Z}/n\mathbb{Z}$); Symmetric Group (S_n); Alternating Group (A_n)
- Dihedral Group (D_n); Quaternion Group (Q_8)

- Matrix Groups (e.g., $GL_n(F)$, $SL_n(F)$, $O_n(F)$, $SO_n(F)$)
- Free Group; Free Abelian Group

Group Actions

- Group Action; Orbit, Stabilizer; Class Equation; Cayley Graph

Constructions and Decompositions

- Direct Product of Groups; Semi-Direct Product of Groups; Internal Direct Product
- Extensions of Groups; Fundamental Theorem of Finitely Generated Abelian Groups

Specialized Group Types

- Simple Group; Solvable Group; Nilpotent Group; Polycyclic Group; Perfect Group

Generalizations of Groups

- Monoid; Groupoid

Rings

Rngs $\supset$ Rings (Unital) $\supset$ Commutative Rings $\supset$ Integral Domains
$\supset$ Factorization Domains $\supset$ Unique Factorization Domains (UFDs)
$\supset$ Principal Ideal Domains (PIDs) $\supset$ Euclidean Domains
$\supset$ Fields $\supset$ Algebraically Closed Fields

Basic Types

- Division Rings (Skew Fields); Noetherian Rings; Artinian Rings
- Dedekind Domains; Valuation Rings, Discrete Valuation Rings (DVRs)

Examples of Rings

- Polynomial Rings ($R[x]$, $R[x_1, \ldots, x_n]$); Formal Power Series ($R[[x]]$)
- Matrix Rings ($M_n(R)$); Group Rings ($R[G]$)
- Ring of Fractions / Localization ($D^{-1}R$, R_S, R_f, R_P); Completion of a Ring ($\hat{R}_I$)

Ring Concepts

- Ring Homomorphisms, Isomorphisms
- Ideals (including Principal Ideal; Prime Ideal; Maximal Ideal; Radical Ideal, Nilradical; Comaximal Ideals; Homogeneous Ideals; Fractional Ideals)
- Quotient Rings; Units, Zero Divisors, Nilpotent Elements
- Characteristic of a Ring; Integral Extensions, Integrally Closed Domains (Normal Domains)

Modules

Basic Module Types and Properties

- R-Module (Left, Right, Bimodule); Submodule; Quotient Module
- Module Homomorphism (Linear Transformation), Isomorphism
- Simple Module (Irreducible Module); Semisimple Module; Indecomposable Module
- Free Module, Rank of a Free Module; Projective Module; Injective Module; Flat Module
- Finitely Generated Module; Noetherian Module, Artinian Module
- Cyclic Module; Torsion Elements, Torsion Module, Torsion-Free Module; Annihilator of a Module

Constructions

- Direct Sum / Direct Product of Modules; Tensor Product of Modules ($M \otimes_R N$)
- Exact Sequences (Short, Long, Split)

Special Modules

- Vector Spaces (over a field k) (including Subspace, Quotient Space; Basis, Dimension; Dual Space (V^*), Dual Basis, Double Dual (V^{**}); Linear Functionals, Bilinear/-Multilinear Forms; Inner Product Spaces, Normed Spaces)
- R-Algebras (as R-modules)

Fields

- Field Extension (K/F) (including Degree of an Extension ($[K : F]$); Finite Extension; Algebraic Element, Transcendental Element; Algebraic Extension, Transcendental Extension; Simple Extension ($F(\alpha)$), Primitive Element; Normal Extension; Separable Extension, Separable Degree ($[K : F]_s$); Galois Extension)
- Minimal Polynomial ($m_{\alpha,F}(x)$); Splitting Field; Algebraic Closure ($\bar{F}$)
- Galois Group ($\mathrm{Gal}(K/F)$, $\mathrm{Aut}_F(K)$) (including Fixed Field; Galois Correspondence)
- Roots of Unity, Cyclotomic Polynomials ($\Phi_n(x)$), Cyclotomic Fields ($\mathbb{Q}(\zeta_n)$)
- Finite Fields / Galois Fields ($\mathbb{F}_q$, $\mathbb{F}_{p^n}$); Ordered Fields, Real Fields
- Absolute Values on Fields, p-adic Valuation; Trace ($\mathrm{Tr}_{K/F}(\alpha)$), Norm ($N_{K/F}(\alpha)$), Discriminant

Algebras

- Associative Algebra (R-Algebra, k-Algebra); Commutative Algebra; Division Algebra
- Lie Algebra; Path Algebra (of a Quiver)
- Tensor Algebra ($T(M)$); Symmetric Algebra ($S(M)$); Exterior Algebra ($\Lambda(M)$)
- Graded Algebra; Central Simple Algebra (CSA); Brauer Group ($\mathrm{Br}(k)$)

Structures from Commutative Algebra & Algebraic Geometry

- Noetherian Ring, Artinian Ring; Dedekind Domain; Valuation Ring, Discrete Valuation Ring (DVR)
- Localization (R_P, R_f, $S^{-1}R$); Completion ($\hat{R}_I$)
- Integral Extension, Integrally Closed Domain (Normal Domain)
- Algebraic Set (Affine, Projective); Variety (Affine, Projective, Quasi-Projective)
- Coordinate Ring ($k[V]$, $k^P[V]$); Zariski Topology
- Regular Function/Map, Rational Function/Map; Dimension (Krull, Transcendental)
- Hilbert Function, Hilbert Polynomial; Stalk ($\mathcal{O}_{X,p}$)
- Spectrum of a Ring ($\mathrm{Spec}(R)$), Affine Scheme

Number Theoretic Structures

- Algebraic Number Field, Ring of Integers ($\mathcal{O}_K$); Algebraic Number, Algebraic Integer
- Discriminant (of a field, of a basis, Δ_K)
- Norm (of an element $N_{K/F}(\alpha)$, of an ideal $N(\mathfrak{a})$); Trace (of an element $\mathrm{Tr}_{K/F}(\alpha)$)
- Ideal Class Group ($\mathrm{Cl}(K)$), Class Number (h_K)
- Roots of Unity, Cyclotomic Polynomials ($\Phi_n(x)$), Cyclotomic Fields ($\mathbb{Q}(\zeta_n)$)
- Fractional Ideals; Ramification Index (e), Inertia Degree (f) (including Decomposition Group (D_P), Inertia Group (I_P); Frobenius Element/Automorphism (Frob_P))

Representation Theory Structures

- Representation (Linear, Matrix) (including Irreducible Representation, Simple Module; Semisimple Representation, Semisimple Module; Indecomposable Representation; Trivial Representation; Regular Representation; Permutation Representation; Induced Representation)
- G-Module ($k[G]$-module); Character, Character Table; Class Function
- Semisimple Ring (Artin-Wedderburn Theorem); Quiver, Quiver Representation (including Path Algebra)

Homological Algebra Structures

- Chain Complex, Cochain Complex (including Cycles, Boundaries (Cocycles, Coboundaries))
- Homology ($H_n(C_\bullet)$), Cohomology ($H^n(C^\bullet)$)
- Exact Sequence (Long Exact Sequence in

(Co)homology) (including Snake Lemma)

- Resolution (Projective, Injective, Free, Flat)
- Derived Functor (L_iF, R^iF) (including Ext Functors ($\mathrm{Ext}^i_R(M,N)$); Tor Functors ($\mathrm{Tor}_i^R(M,N)$))
- Homotopy (Chain Homotopy, Homotopy Equivalence); Mapping Cone
- Derived Category ($D(A)$), Homotopy Category ($K(A)$), Triangulated Category; Spectral Sequence

Category Theory Concepts

- Category (Small, Locally Small); Object
- Morphism (Homomorphism, Isomorphism, Monomorphism, Epimorphism, Endomorphism, Automorphism)
- Functor (Covariant, Contravariant) (including Additive Functor, Exact Functor; Faithful Functor, Full Functor, Essentially Surjective Functor)
- Natural Transformation, Natural Isomorphism; Equivalence of Categories
- Duality, Opposite Category (C^{op}); Commutative Diagram

Universal Properties

- Universal Property (general concept); Initial Object, Final Object (Zero Object)
- Product, Coproduct (Direct Product, Direct Sum, Free Product)
- Kernel, Cokernel (in Abelian Categories); Equalizer, Coequalizer
- Limit, Colimit (Inverse/Projective Limit, Direct/Injective Limit)
- Free Objects (Free Group, Free Module, Free R-algebra, Polynomial Ring as free commutative R-algebra)
- Adjoint Functors (e.g., Free-Forgetful Adjoints, Hom-Tensor Adjoint)

Index

G-set, 151
G-set Isomorphism, 170
R_k condition, 1907
S_k condition, 1907
p-group, 180, 189
2-Category, 2182
    Cat, 2185
    and Cat-enrichment, 2184
2-Cell, 2182

AB5, 1922
Abel's Theorem, 854
Abelian Group, 13
Absolute Value, 881
Action
    Faithful, 161
    Free, 171
    Group, 151
    Regular, 172
    Right, 155
    Ring, 402
    Transitive, 169
Acyclic Functor, 1805
    for right-derived functors, 1805
    resolution by acyclic objects, 1807
Adapted Class, 1850
Adjoint
    Uniqueness, 2108
Adjoint Functor
    left, 2097
    right, 2097
Adjoint Functor Theorem
    General, 2114
    Special, 2115
Adjugate Matrix, 512
    Adjugate Identity, 512
Adjunction, 2097
    as a Kan extension, 2144
    equivalent formulations, 2100
    free and forgetful, 2103
    in a 2-Category, 2186
    tensor and hom, 2104
Admissible Ideal, 1712
Affine Cone, 1215
Affine Coordinate Ring, 1122
Affine Space, 1098
Affording Representation, 1602
Algebra, 410
Algebra for a Monad, 2121
Algebra Representation, 1560
Algebraic Closure, 759
Algebraic Element, 733
Algebraic Integer [of Number Fields], 1364
Algebraic Multiplicity, 520
Algebraic Number Field, 1363
Algebraic Set
    Affine, 1104
    Projective, 1212
Algebraically Closed, 758
    Union Of A Root-Adjoining Chain, 760
Alternating Bilinear Form, 906
    Classification, 908

Alternating Group, 33
Alternating Tensor, 617
Analytically Isomorphic, 1187
Anisotropic Form, 915
Annihilator
    Dual Map, 497
    R-module, 441
Approximate Cycle, 1985
Archimedean Embedding, 1397
Archimedean Field, 872
Arrow Ideal, 1712
Artin's Lemma, 840
Artin-Rees Lemma, 1015
Artin-Schreier Extensions, 865
Artin-Schreier Theorem, 879
    Cyclic Extensions, 866
Artin-Wedderburn Theorem, 1556
Artinian Module, 1055
Artinian Ring, 1055
$\mathrm{Ass}(M)$, 996
Associated Graded Ring, 1020
Associated Prime, 996
Associative Elements, 342
Associator, 2151
Atomic Domain, 345
Auslander-Buchsbaum-Serre Theorem, 1176
Automorphism, 2035
    Group, 58

Baer's Criterion, 668
Basic Algebra, 1715
Basis, 454
Bicategory, 2188
    coherence theorem, 2189
    of bimodules, 2190
    of spans, 2190
Bijective, xxii
Bilinear Map, 503, 579
Bimodule, 578, 2190
    Tensor Product of, 582
Binary Operation, 7
Binomial Coefficient, xxxv
Binomial Theorem, xxxvi
Birational Map, 1149
Block, 1660
Blow-Up, 1337
    along a linear subspace, 1340
    of affine space, 1339
Bockstein Homomorphism, 1982
Bound Quiver Algebra, 1713
Boundary, 1748
Braided Monoidal Category, 2157
Braiding, 2157
Branch
    formal, 1186
Brauer Equivalence, 1566
Burnside's Lemma, 165
Burnside's Theorem, 1636

Canonical Class, 1333
Canonical Divisor, 1333, 1352
Cardinality, xxii
Cartan Matrix
    of a Root System, 1688
    of an Algebra, 1595
Cartan-Dieudonné Theorem
    sharp form, with bound n, 933
    weak form, with bound $2n$, 932
Cartan-Eilenberg Resolution, 2002
Cartesian Closed Category, 2162
    Set, 2162
Category, 255, 2030
    Abelian, 1735
    Additive, 1732
    Cat, 2032
    Complexes, 1749
    enriched, 2170
    Field, 2031
    Grp, 2031
    Homotopy, 1775
    Locally Small, 2034
    $\mathbf{Mat}_R$, 2032
    $\mathbf{Mod}_R$, 2031
    Opposite, 2041
    Poset, 2031
    Ring, 2031
    Set, 2031
    Small, 2033
    Top, 2031
    underlying ordinary, 2171
Catenary Ring, 1069
    finitely generated algebras, 1071
Cauchy's Theorem, 193
Cauchy-Frobenius Lemma, *see* Burnside's Lemma
Cayley Graph, 67
Cayley Table, 14

Cayley's Theorem, 174
Center
as a Morita Invariant, 710
of a Ring, 274
Center of Group, 75
Central Simple Algebra, 1560
Centralizer of Group, 76
Chain, 961
Chain Complex, 689, 1748
Chain Homotopy, 1770
Change of Base, 2174
Change of Basis, 471
Character, 1614
Character Table, 1619
Characteristic Ideal, 543
Characteristic Polynomial, 516, 1065
Characteristic Subgroup, 188
Chinese Remainder Theorem, 336
Class Equation, 179
Class Function, 1614
Class Group, 1199, 1426
Class Number, 1430
Classification of Finite Simple Groups, 147
Clifford Algebra, 945
Basis and Dimension, 948
Even Part, 951
Universal Property, 946
Clifford's Theorem
induced form, 1644
Closed Monoidal Category, 2160
Vect, 2162
Closed Real Field, 875
Closure
Algebraic, 759
Galois, 839
Normal, Field, 771
Normal, Group, 122
Zariski, 1113
Co-Yoneda Lemma, 2147
Coboundary, 1879
coChain, 1883
Cocomplete Category, 2089
Cocone, 2084
Cocycle, 1879
Codimension, 1165
Coend, 2146
Coequalizer, 2086
is epic, 2087
Cofactor, 512
Cohen Structure Theorem, 1024
Cohen-Macaulay Ring, 1904
Coherence
for bicategories, 2189
Coherence Theorem, 2155
Mac Lane, 2155
Cohomology, 1753
Cohomology Group, 1884
Coinduced G-module, 1886
Cokernel, 423
Colimit, 2084
as a limit in the opposite category, 2085
as left adjoint to the diagonal, 2105
from coproducts and coequalizers, 2088
of a Directed System, 1920
exactness for modules, 1921
Comaximal Elements, 333
In a PID, 359
With a Linear Polynomial, 334
Comaximal Ideal, 333
Comma Category, 2078
Commutative Diagram, xli, 263
Commutator Subgroup, 211
Comonad, 2121
Comonoid Object, 2164
Companion Matrix, 549
Comparison Functor, 2131
Kleisli to Eilenberg-Moore, 2129
Complement
Group, 214
Complete Category, 2089
from Products and Equalizers, 2090
Complete Ring, 1011
Completion
$\mathfrak{a}$-adic of Ring, 1004
Of A Filtered Group, 2235
Composite Field, 725
Composition Series
Group, 144
R-module, 961
Conductor, 1457
Cone, 2079
over a variety, 1274
Congruent Matrices, 900
Conjugacy Class, 178
in A_n, 198
Constructible Set, 1268

Convolution, 1648
Copower, 2146
Coprime Elements, 334
Coprime Numbers, xxix
Coproduct, 2085
Cosets, 113
Cotensor, 2176
Counit of an Adjunction, 2099
Coxeter Element, 1684
Coxeter Element Lemma, 1687
Coxeter Functor, 1700
Currying, 2104
Curves, 1166
Cycle, 1748
Cycle Decomposition, 30
Cycle Type, 30
Cyclic Group, 80
Cyclotomic Field, 800
Cyclotomic Polynomial, 797

Decomposition Field, 1472
Decomposition Group, 1472
Dedekind Domain, 1411
Dedekind-Hasse Valuation, 368
Dedekind-Kummer Theorem, 1458
Degeneration
    and strictness, 2022
Degree
    of a Projective Variety, 1225
Degree of Field Extension, 721
δ-Functor, 1809
    effaceability criterion, 1812
    morphism of, 1811
    universal, 1811
Density Theorem, 2147
Depth, 1901
    via Ext, 1901
Derived Category
    filtered, 2016
    subcategories $D^{\leq n}$ and $D^{\geq n}$, 1951
Derived Couple, 1977
    exactness of, 1977
Derived Functor, 1791
    on unbounded complexes, 1931
Derived Tensor Product, 1867
    of Unbounded Complexes, 1942
Descent
    Faithfully Flat, 1085
Descent Datum, 1085
Determinant, 509
    Multiplicativity, 510
    Top Exterior Power, 635
Diagonalizable, 524
Diagram, 2079
Different, 1488
Differential Form, 1331
Dihedral Group, 37
Dimension
    Codimension, 1165
    Global, 1175
    Krull, 1163
    Projective, 1175
    Quiver, 1670
    Topological, 2223
    Transcendental, 1164
    Vector Space, 459
Dimension Vector, 1670
Direct Product
    Group, 207
    of rings, and modules, 431
    R-module, 428
Direct Sum
    Group, 229
    R-module, 430
Directed System, 1920
Dirichlet Unit Theorem, 1436
Discriminant, 791
    Bilinear Map, 1376
    Field, 1378
    Polynomial, 856
    Relative, 1453, 1494
    Ring of Integers, 1386
Discriminant of a Form, 900
    Signed, 940
Distinguished Open Sets, 1114
Divisibility, xxvii
    Ring, 341
Divisible Group, 670
Divisible Module, 670
Divisible Subgroup, 677
Division Ring, 276
Divisor, 1313
    class group, 1318
    effective, 1313
    of a rational function, 1314
    principal, 1199, 1315

Weil, 1199
Domain, 282
Domain of Definition, 1144
Dominating
Rational Map, 1147
Double Complex, 1819
filtrations of the total complex, 1998
Double Dual, 499, 2051
Dual Basis, 495
Dual Curve, 1310
Dual Map, 496
Dual Projective Space, 1310
Dual Space, 493
Duality Principle, 2044
Dualizable Object, 2166
Finite-Dimensional Spaces, 2167
Dynkin Diagram, 1679
Extended, 1679
of a Root System, 1688

Edge Morphism, 1992
of the Grothendieck spectral sequence, 2012
Effaceable Functor, 1811
Grothendieck's criterion, 1812
Eigenspace, 520
Eigenvalue, 518
Eigenvector, 520
Eilenberg-Moore Adjunction, 2123
Eilenberg-Moore Category, 2122
Elementary Divisor, 537
Elementary Matrix, 478
Elementary Reduction, 96
Embedded Prime, 1000
End, 2146
enriched, 2178
Endomorphism, 2035
Endomorphism Ring
is local, 1582
of a truncated polynomial module, 1583
Endomorphisms
For Groups, 54
Engel Group, 241
Enough Injectives, 1778
Enough Projectives, 1778
Enriched Category, 2170
Change of Base, 2174
examples, 2171
modules over a ring, 2180
tensored and cotensored, 2176
Enriched Functor, 2173
Enriched Functor Category, 2178
Enriched Natural Transformation, 2174
Enriched Yoneda Lemma, 2180
Epimorphism, 261, 2039
Equalizer, 2081
Equivalence
Matrix, 473
of Categories, 703
Equivalence of Categories, 2055
characterization, 2071
Equivalence Relation, xiv
Equivariant Map, 170
Essential Extension, 674
Essentially Surjective Functor, 2056
Euclidean Algorithm, xxix
Euclidean Domain, 363
Euclidean Valuation, 363
Euler Form, 1678
Euler Totient, 23
Evaluation Map, 293, 2051, 2160
Exact Chain Complex, 422
Exact Couple, 1976
Bockstein, 1982
Exact Triangle, 1832
Exceptional Divisor, 1337
Exponential Object, 2162
Ext, 689
Ext-Quiver, 1717
Extension of Scalars, 597
Exterior Algebra, 629
Exterior Power, 616
of a direct sum, 634

Faithful Action, 161
Faithful Module, 441
Faithfully Flat, 1084
Feit-Thompson's Theorem, 237
Fermat's Little Theorem, xxxiii
Fermat's Sum of Two Squares Theorem, 376
Field, 276
Field Characteristic, 722
Field Extension, 720
Abelian, 824
Algebraic, 745
Cyclic, 824
Finite, 721

Galois, 824
Kummer, 858
Normal, 768
Radical, 851
Ramified, 1460
Separable, 773
Simple, 725
Solvable, 852
Transcendental, 745
Unramified, 1460
Filtered Group, 2235
Filtered Object, 2015
Filtered Quasi-Isomorphism, 2016
Filtration, 1012
of a complex, 1984
Finite Map
Affine Variety, 1253
Quasi-Projective Variety, 1255
Finite Representation Type, 1665
of a Quiver, 1692
Finite Type, 448
Finitely Generated
Group, 210
R-module, 445
Fitting Ideal, 1087
Fitting's Lemma, 1580
Five Lemma, 1763
Five-Term Exact Sequence, 1992
for the Grothendieck spectral sequence, 2013
Fixed Field, 818
Fixed Field Automorphism, 742
Fixed Homomorphism, 722
Fixed-point set, 160
Flat Module, 685
Forgetful Functor
of a Monad, 2122
form, 1210
Formal Branch, 1186
Formal Derivative, 296, 774
Formal Power Series, 294
Fourier Reciprocity, 1651
Fourier Transform, 1650
Fractional Ideal, 1416
Free
Abelian Group, 210
R-Module, 436
Free Action, 171
Free Group, 98
Free Product, 228
Free Rank, 439
Freely Generated, 100
Freyd-Mitchell Theorem, 1739
Frobenius Automorphism, 1501
Frobenius Homomorphism, 776
Frobenius Reciprocity, 1639
Frobenius's Theorem, 845
Fully Faithful Functor, 2056
Function, xvi
Function Field, 1234
Functor, 257, 2046
Contravariant, 2048
Creating Limits, 2094
Preserves Isomorphisms, 2050
Preserving Limits, 2094
Reflecting Limits, 2094
Representable, 2059
Functor Category, 2054
Functor of Points, 2070
Fundamental Ideal, 942
Fundamental Theorem of Algebra, 844
Fundamental Theorem of Galois Theory
Finite, 822
Infinite, 1530

G-Module, 1874
Gabriel Quiver, 1717
Gabriel's Theorem, 1692
Structure of Basic Algebras, 1720
Galois Conjugate, 856
Galois Connection, 2106
Galois Field, 803
Galois Group, 824
GCD
Ideal, 1415
Numbers, xxviii
Ring Elements, 353
Gelfand Transform, 1650
GL_n, 41
General Linear Matrix, 478
Generalized Eigenspace, 567
Generating
Ideal, 316
Generating Set Generators, 89
Generation, 88
Generator
Characterizations, 700

of a Module Category, 700
Generators, 89
Group, 43
R-module, 425
Genus, 1319
Arithmetic, 1225
of a plane curve, 1319
Geometric Multiplicity, 521
Global Dimension, 1175, 1890
under localization, 1899
Gröbner Basis, 967
Graded Algebra, 620
Graded Ideal, 621
Graded Module, 621
Graded ring, 620
Graph, xxxvii, 1677
Graph Isomorphism, xxxvii
Grassmannian, 1266
Grothendieck Abelian Category, 1922
enough injectives, 1922
Grothendieck Completion, 249
examples, 250
Grothendieck Spectral Sequence, 2011
Group, 8
Group Action, 151
axiomatic definition, 151
Group Character, 839
Group Extension, 139
Group Lattice, 104
Group Object, 2166
Group Ring, 300
Groupoid, 251, 2037

Haar Measure, 1655
Hauptidealsatz, 1067
Heart
equivalence with the abelian category, 1956
of a t-structure, 1966
of the standard pair, 1951
Height Formula, 1070
Height of a Prime, 1064
Height of Prime, 1164
Hilbert Function
Projective Variety, 1224
Hilbert Polynomial, 1225
Hilbert's 90th Theorem, 859
Hilbert's Basis Theorem, 962
Hilbert's Nullstellensatz, 1134
Hilbert's Syzygy Theorem, 1894
Hilbert-Samuel Polynomial, 1065
Hom Complex, 1856
Hom-Functor, 2059
Preserves Limits, 2094
Two-Sided, 2061
Hom-set, 2034
Hom-Tensor Adjoint, 601
Homogeneous Polynomial, 1210
Homogenization, 1216
Homology, 689, 1753
Homomorphism
R-Algebra, 410
Group, 47
Of Short Exact Sequences, 648
Quiver, 1671
R-module, 403, 416
Representation, 1600
Ring, 273
Hyperbolic Plane, 916
Hyperbolic Space, 916
Hypercohomology, 2005
and the total derived functor, 2009

Ideal, 305
Contains a Product of Primes, 960
Ideal Contraction, 1035
Ideal Extension, 1035
Ideal Group, 1425
Ideal of Minors, 1086
Idempotent
Full, 711
Idempotent Element, 1553
Lifting, 1588
Primitive Decomposition, 1589
Identity Functor, 2053
Image, 74
Indecomposable Projective Module, 1591
Correspondence with Simples, 1591
Independence
Algebraic, 733
Algebraic, of a Set, 733
Linear, 454
Index, 126
Induced G-module, 1886
Inertia Degree, 1454
Inertia Field, 1479
Inertia Group, 1479

Inflection Point, 1324
Initial Form, 1179
Initial Object, 2075
    from a weakly initial set, 2112
Injective, xx
Injective Module, 666
Injective Object, 1777
Inner Automorphism, 185
Inner Product
    Class Function, 1623
    G-Invariant, 1605
Integral Basis, 1386
Integral Closure
    Finiteness, 1033
    Of a One-Dimensional Noetherian Domain, 1051
Integral Domain, 281
Integral Element, 1028
Integral Extension
    dimension, 1068
Integral Ideal, 1417
Integral Lattice, 1398
Integral Trace Dual, 1385
Interchange Law, 2182
Internal Direct Product, 129
Internal Hom, 2160
Invariant Basis Number, 529
Invariant Factor
    Linear Operator, 548
Irreducible Component, 1129
Irreducible Elements, 343
Irrelevant Ideal, 1224
Isolated Prime, 1000
Isometry of Forms, 901
Isomorphism, xl, 2035
    Category, 262
    Groups, 56
    Quiver, 1672
    Ring, 302
Isomorphism of Varieties, 1118
Isomorphism Theorem
    Group
        First, 119, 131
        Fourth, 135
        Second, 133
        Third, 134
    R-Modules, 420
    Ring
        2,3,4, 310
        First, 308
Isotropic Vector, 915
Isotropy Subgroup, *see* Stabilizer

Jacobson Radical, 986, 1572
    characterizations, 1573
    nilpotence, 1576
    semisimple quotient, 1577
Join, 1274
Jordan Block, 561
Jordan Canonical Form, 561
    Existence, 561
Jordan-Chevalley Decomposition, 568
Jordan-Hölder Program, 145

K-Flat Complex, 1935
    of flat modules, 1944
    over a Principal Ideal Domain, 1944
K-Flat Resolution, 1940
K-Injective Complex, 1924
    characterization, 1924
    Hom complex into, 1926
    shifts, 1924
K-Injective Resolution, 1924
    existence, 1928
K-Projective Complex, 1935
K-Projective Resolution, 1940
Kan Extension, 2135
    adjoints as, 2144
    as Adjoint to Restriction, 2137
    Computed Example, 2141
    Existence, 2141
    Left, 2135
    limits and colimits as, 2143
    Pointwise Formula, 2139
    Right, 2135
    Yoneda as, 2145
Kernel
    Group, 74
    of a Group Action, 161
    Ring, 302
Kleisli Adjunction, 2127
Kleisli Category, 2126
Koszul Complex, 639
Kronecker Product, 603
    Spectrum, 606
    Trace and Determinant, 604

Kronecker's Theorem, 727
Kronecker-Weber Theorem, 1513
Krull Dimension, 1064
Krull Topology On Galois Group, 1529
Krull's Principal Ideal Theorem, 1067
Krull's Theorem, 1018
Krull-Akizuki Theorem, 1050
Krull-Schmidt Theorem, 1584
    Azumaya extension, 1584
    multiplicities, 1586
Kummer Pairing, 865

Lagrange Theorem, 125
Lagrangian Subspace, 913
LCM
    Ideal, 1415
    Numbers, xxviii
    Ring Elements, 353
Legendre Symbol, 1509
    Multiplicativity, 1509
length of Composition Series, 961
Lifting Idempotents, 1588
Limit, 2079
    as right adjoint to the diagonal, 2105
    first derived functor of, 1912
    from products and equalizers, 2083
    of a Tower, 1912
    of a Tower of Complexes, 1926
    weighted, 2181
Limits
    in Algebraic Categories, 2090
    Pointwise in Functor Categories, 2093
Linear Coordinate Change, 1285
Linear Darboux Theorem, 908
Linear Equivalence, 1315
Linear Functionals, 493
Linear Group, 246
Local Criterion for Flatness, 1908
Local Parameters, 1184
Local Property, 979
Local Ring, 983
    from indecomposable module, 1582
Local Ring of Field, 1195
Localization, 971
    of a category, 1740
Locally Closed, 1268
Locally Free Module, 1090
Lüroth's Theorem, 784, 1155
Lying Over, 1037

Mapping Cone, 1764
Maschke's Theorem, 1607
Matrix Group, 41
Matrix Ring, 299
Maximal
    Ideal, 322
Maximal Groupoid, 2039
Metabelian Group, 233
Minimal Polynomial, 736
Minkowski's Bound, 1407
Mittag-Leffler Condition, 1915
Modular Arithmetics, xxxi
Module, 402
Module of Differentials, 1331
Monad, 2117
    in a 2-Category, 2186
    of an adjunction, 2118
Monadic Functor, 2131
Monadicity Theorem (Beck), 2132
Monogenic Number Ring, 1389
Monoid, 247
Monoid Object, 2163
    Examples, 2165
Monoidal Category, 2151
    Strict, 2152
Monomial Order, 967
Monomorphism, 260, 2039
Morita Equivalence, 703
    Matrix Rings, 708
    Morita's Theorem, 706
Morphism, 2030
Multilinear Map, 503, 589
    Alternating, 614
    Symmetric, 614
Multiplicative System, 1741
Multiplicity, 1285
    of a curve at a point, 1285
    of a variety at a point, 1181
Multiset, xxiv

Nagata's Criterion, 1077
Nakayama's Lemma, 1575
Natural Isomorphism, 703
Natural Transformation, 703, 2052
Nielsen-Schreier's Theorem, 2211
Nilpotent Group, 239

Nilpotent Operator, 565
Nilradical, 994
Noether Normalization, 1063
Noether's Normalization Theorem, 1132
Noetherian
    R-Module, 446
    Ring, 318, 959
Nondegenerate Bilinear Form, 506
Nonsingular Matrix, 470
Norm
    Absolute, 1403, 1428
    Character, 1626
    Field, 1368
    Relative, 1448
Normal Basis, 841
Normal Basis Theorem, 841
Normal Closure
    Field, 771
    Group, 122
Normal Subgroup, 116
Normal Variety, 1191
Normalization
    of a Variety, 1193
Normalizer, 78
Null-Homotopic, 1769
Nullity, 462

Object, 2030
Octahedral Axiom, 1833
Opposite Ring, 1547
Orbit, 157
Orbit Space, 158
Orbit-Stabilizer Theorem, 163
Order, 1289
    of a differential form, 1333
    of a function at a simple point, 1289
Order of an element, 26
Order on Set, xiii
Ordered Field, 870
Oriented Cycle, 1668
Orthogonal, 505
Orthogonal Element, 1553
Orthogonal Group, 925
O_n, 41
Orthogonal Sum, 915
Outer Automorphism, 187

Parity of Cycle, 33
Partially Ordered Set, 2199
Partition, xv, 848
Path
    in a Quiver, 1668
Path Algebra, 1704
    Modules over, 1706
    Structure, 1704
Perfect Field, 776
Perfect Group, 215
Permutation Representation, 153
    Character, 1620
Picard Group, 1318, 1523
Plücker Embedding, 1266
Plane Curve, 1284
Pointwise Kan Extension, 2139
Polycyclic Group, 245
Polynomial Ring, 289
Pontryagin Group, 1646
Power, 2146
Presentation
    Formal Definition, 44
    Module, 443
    Quotient Definition, 123
Presheaf, 2060
Presheaf Category, 2060
Primary Decomposition, 996
Primary Ideal, 993
Prime
    Elements in Ring, 343
Prime Avoidance, 999
Prime Divisor, 1199
Prime Ideal, 325
    Ramified, 1454
    Split, 1454
    Totally Ramified, 1454
    Unramified, 1454
Prime Ideal Conjugate, 1471
Prime Subfield, 723
Primitive Element Theorem, 783
Primitive Root of Unity, 724
PID, 319
Product, 2080
Product of Projective Space, 1246
Profinite Completion, 1524
Profinite Group, 1524
Progenerator, 702
    Examples, 702
Projection

from a point, 1274
Projection Map, 464
Projective Closure, 1234
Projective Coordinate Ring, 1213
Projective Cover, 1593
Existence, 1594
Projective Dimension, 1175, 1890
via Ext, 1890
Projective Module, 657
Indecomposable, 1591
Projective Object, 1777
Projective Plane Curve, 1284
Projective Representation, 1708
Projective Space, 1210
Pullback, 2081
Pushout, 2087

Quadratic Form, 897
Quadratic Reciprocity, 1510
First Supplement, 1509
Second Supplement, 1511
Quadratic Residue, 1507
Quadric, 1213
Quasi-Isomorphism, 1756
Quiver, 1668
Quotient
Group, 112
Ring, 307
Quotient Abelian Category, 1743
Quotient Ideal, 1416

R-balanced Map, 574
R-module of Finite Length, 1060
Bound for Torsion-Free Modules, 1049
Radical
of a Module, 1572
Radical Ideal, 1127
Radical of a Bilinear Form, 506
Radical of an Ideal, 315
As an Intersection of Primes, 994
Powers in Noetherian Rings, 994
Ramification Index, 1454
Rank
Matrix, 482
of a quadric, 1213
Vector Space, 462
Rational Canonical Form, 550
Rational Closed Set, 1149
Rational Function On quasi-projective Variety, 1243
Rational Functions, 1142
Rational Mapping, 1146
Reduced Group, 677
Reduced Ring, 1139
Reduced Word Lemma, 97
Reducible Component, 1129
Rees's Theorem, 1901
Reflection, 925
Reflection Functor, 1693
Regular Action, 172
Regular Function, 1098
Quasi-projective Variety, 1239
Regular Local Ring, 1073, 1172
homological characterization, 1176
maximal ideal generated by a regular sequence, 1898
Regular Map
Quasi-projective Variety, 1240
Regular Point, 1143
Regular Representation
Decomposition, 1589
Regular Ring, 1899
polynomial ring over, 1900
Regular Sequence, 637, 1897
associated graded ring of, 1021
Regular Sequence Criterion for Flatness, 1909
Regular System of Parameters, 1073
Regulator, 1441
Relation, xiii
Replacement Theorem, 458
Representation
Indecomposable, 1676
Induced, 1638
Matrix, 466
Quiver, 1670
Simple, 1676
Representation, Linear, 1599
Representing Object
uniqueness, 2070
Residue Field, 984
Residue Field Degree, 1454
Resolution
Free, 444
Injective, 674, 1784
Projective, 1784
Restriction of Scalars, 597

Resultant, 788
RHom, 1860
    of Unbounded Complexes, 1945
Riemann-Roch Space, 1350
Right Action, 155
Right Adjoints Preserve Limits (RAPL), 2109
Ring, 270
Ring Extension, 1027
Ring of Fraction, 328
Ring of Fractions, 330
Ring of Integers
    Order, 1521
Ring of Integers (of Function Fields), 1364
Ring of Integers (of Number Fields), 1364
Root
    of a Graph, 1684
Root of Unity, 724
Root System, 1687
    Base, 1688
Russell's Paradox, 2033

S-polynomial, 968
Saturated Chain, 1069
Saturated Ideal, 975
Schur Polynomial, 848
Secant Variety, 1275
Section Map, 653
Semi-Direct Product, 217
Semi-Simple Ring, 1538
    radical criterion, 1578
Semisimple Operator, 565
Separable Degree, 778
Separable Polynomial, 773
Separated Filtration, 1011
Serre Subcategory, 1743
Serre's Conditions, 1907
Serre's Criterion for Normality, 1907
Set Operations, ix
Short Exact Sequence, 646
Side Divisor, 367
Sign of a Permutation, 32
Similarity, 474
Simple
    Group, 142
    Ring, 321, 1538
Simple Module
    Projective Cover Correspondence, 1591
Simple Reflection, 1684
Simplicity of A_5, 199
Simultaneous Diagonalization, 566
Sink, 1669
Snake Lemma, 1759
Solution-Set Condition, 2112
Solvable Group, 235
Source, 1669
Span, 2190
SL_n, 41
SO_n, 42
Spectral Decomposition, 525
Spectral Sequence, 1979
    comparison theorem, 1989
    convergence, 1988
    edge morphisms, 1992
    five-term exact sequence, 1992
    Grothendieck, 2011
    hypercohomology, 2005
    multiplicative, 1994
    of a double complex, 1999
    of an exact couple, 1979
Split Exact Sequence, 652
    Groups, 223
Splitting Field, 764
Splitting Homomorphism, 653
Square Class Group, 900
Stabilizer, 159
Stalk At A Point, 1145, 1284
Standard Resolution, 1882
Strict Monoidal Category, 2152
Strict Transform, 1340
Strictly Coprime, *see* Comaximal Elements
Structure Map, 2121
Subcategory, 2038
Subgroup, 12, 71
Submodule, 404
Subnormal Series, 143
Subobject, 261
Subrepresentation, 1670
Subring, 274
Subspace, 408
Sum
    R-module, 420
Superfluous Submodule, 1593
Supp(M), 999
Support of a Module, 999
Surface, 1166
Surjective, xx

Sylow p-subgroup, 189
Sylow's Theorems, 191
Symmetric Algebra, 628
Symmetric Group, 27
Symmetric Monoidal Category, 2158
    Examples, 2158
Symmetric Power, 615
Symmetric Tensor, 617
Symmetry, 2158
Symplectic Basis, 907
Symplectic Space, 907
System of Linear Equations, 485
System of Parameters, 1067

t-Structure, 1959
    bounded, 1972
    cohomological functor H_t^0, 1969
    cohomology functors, 1966
    heart, 1966
    long exact cohomology sequence, 1969
    nondegenerate, 1972
    truncation functors, 1963
Tangent Cone, 1180, 1285
Tangent Line, 1285
Tangent Variety, 1275
Tensor
    examples, 2177
    in an enriched category, 2176
Tensor Algebra, 625
Tensor Power, 613
Tensor Product, 575
    and Hom, 608
    Associativity, 588
    Commutativity, 587
    of Algebras, 592
    of Direct Sums, 584
    of Free Modules, 587
    of Homomorphisms, 583
    with an Arbitrary Direct Sum, 586
Tensor-Hom Adjunction, 2160
    in the Derived Category, 1947
Terminal Object, 2075
    For Groups, 52
Tits Form, 1678
    Positive Definite, 1683
Tor, 689
Torsion Element, 440
Torsion-Free Module, 440
Total Derived Functor, 1852
Total Tensor Complex, 1864
Total Transform, 1340
Totally Isotropic Subspace, 911
Tower, 1912
    morphism of, 1912
    of Complexes, 1926
Trace
    Field, 1368
    Linear Map, 508
    Matrix, 507
    of a Field Extension, 792
Trace Dual of Fractional Ideal, 1488
Trace Ideal, 700
Trace Pairing, 1377
Transcendence Basis, 734
    Separating, 793
Transcendence Degree, 735
Transcendental Element, 733
Transitive Action, 169
Transpose, 496
Transposition, 30
Triangle Identities, 2100, 2107
Triangulated Category, 1833
Truncated Polynomial Algebra
    indecomposable modules, 1587
Truncation
    adjoint to inclusion, 1955
    canonical, 1755
    on the derived category, 1952
    triangle, 1953
Two Filtrations
    lemma on, 2017

Underlying Category, 2171
Unique Factorization Domain
    height-one criterion, 1076
    UFD, 345, 351
Unit, 278
Unit Object
    Uniqueness, 2153
Unit of an Adjunction, 2099
Unitor, 2151
Universal Arrow, 2077
Universal Element, 2061
Universal Property
    Coproduct in Ab, 230
    Cokernel, 124

Completions, 2236
Coproduct of Commutative Algebras, 594
Derived Cat enough Proj, 1788
Exterior Powers, 616
Field of Fractions, 331
Free Groups, 98
Free R-algebra, 413
Free R-Modules, 434
Group Kernel, 106
Localization, 970
Multilinear Maps, 590
Polynomial Rings, 292
Product of Groups, 225
Quotient Sets, xli
Scalar Extensions, 598
Semi-Direct Product, 231
Symmetric Powers, 615
Tensor Product, 576
Tensor Product (Commutative Ring), 580

V-Functor, 2173
V-Natural Transformation, 2174
Valuation
Archimedean, 885
Discrete, 1044
Real, 1043
Ring, 362
Valuation Ring, 1045
Dominating a Noetherian Local Domain, 1052
Dominating a One-Dimensional Local Domain, 1052
Valuation Totally Ordered Abelian Group, 1043
Vanishing Ideal, 1108
Projective, 1212
Variety
Affine, 1129
Nonsingular, 1172, 1173
Normal, 1191
Projective, 1213
Quasi-projective, 1237
Vector Space, 407
Veronese Embedding, 1263
Volume
Determinant, 515
Lattice, 1401

Wedderburn's Little Theorem, 806
Wedge, 2146
Weierstrass Division Theorem, 1025
Weierstrass Preparation Theorem, 1025
Weighted Colimit, 2181
Weighted Limit, 2181
Weyl Group, 1688
of a Graph, 1684
Whiskering, 2185
Wild Inertia Group, 1497
Witt Cancellation, 928
Witt Decomposition, 919
Witt Equivalence, 936
Witt Group, 936
Witt Index, 921
Witt's Extension Theorem, 931
Word, 96
Reduced, 96

Yoneda Embedding, 2067
Full Faithfulness, 2068
Yoneda Lemma, 2063
as a Kan extension, 2145
Contravariant Form, 2066
Enriched, 2180

Zariski Dense, 1113
Zariski Topology
Affine Space, 1108
Projective Space, 1212
Zariski's Lemma, 1133
Zero Object, 2075
Zero-cycle, 1305
Zero-Divisor, 278

Bibliography

[1] Phillip A. Griffiths. *Introduction to Algebraic Curves*. Vol. 78. Mathematical Monographs. American Mathematical Society.

[2] J. L. Alperin. *Local Representation Theory*. 1st ed. Cambridge Studies in Advanced Mathematics. Cambridge University Press, 1986. ISBN: 9780521306607. DOI: 10.1017/cbo9780511623592.

[3] Paolo Aluffi. *Algebra: Chapter 0*. American Mathematical Soc., 2009. URL: https://books.google.com/books?hl=en&lr=&id=deWkZWYbyHQC&oi=fnd&pg=PP1&dq=info:s7Xcz_S-zskJ:scholar.google.com&ots=ZhOZLNyn5Q&sig=DFmvsr6WxEQwdDSlcCao-NeoBko (visited on 02/18/2025).

[4] Michael Aschbacher and Stephen Smith. *The Classification of Quasithin Groups I: Structure of Strongly Quasithin K-groups*. Mathematical Surveys and Monographs 111. Providence, Rhode Island: American Mathematical Society, Nov. 2, 2004. ISBN: 978-0-8218-3410-7. DOI: 10.1090/surv/111. URL: https://doi.org/10.1090/surv/111.

[5] Michael Aschbacher and Stephen D. Smith. *The Classification of Quasithin Groups II: Main Theorems: The Classification of Simple QTKE-groups*. Mathematical Surveys and Monographs 112. Providence, Rhode Island: American Mathematical Society, 2004. ISBN: 978-0-8218-3411-4. DOI: 10.1090/surv/112.

[6] Michael Aschbacher et al. *The Classification of Finite Simple Groups: Groups of Characteristic 2 Type*. Mathematical Surveys and Monographs 172. Providence, Rhode Island: American Mathematical Society, Mar. 9, 2011. ISBN: 978-0-8218-5336-8. DOI: 10.1090/surv/172. URL: https://doi.org/10.1090/surv/172.

[7] Michael F. Atiyah and I.G. Macdonald. *Introduction To Commutative Algebra*. 1st ed. Boca Raton, 1969. ISBN: 978-0-429-49363-8. URL: https://doi.org/10.1201/9780429493638.

[8] Alexander A. Beĭlinson, Joseph Bernstein, and Pierre Deligne. "Faisceaux pervers". In: *Analyse et topologie sur les espaces singuliers, I*. Vol. 100. Astérisque. Société Mathématique de France, 1982, pp. 5–171.

[9] Richard Brauer and K. A. Fowler. "On Groups of Even Order". In: *The Annals of Mathematics* 62.3 (Nov. 1955), pp. 565–583. DOI: 10.2307/1970080. URL: https://doi.org/10.2307/1970080.

[10] William Burnside. *Theory of Groups of Finite Order*. 1st ed. Cambridge University Press, June 7, 2012. ISBN: 978-1-108-05032-6 978-1-139-23725-3. DOI: 10.1017/CBO9781139237253. URL: https://www.cambridge.org/core/product/identifier/9781139237253/type/book (visited on 10/18/2026).

[11] A. Cayley. "On the Theory of Groups, as Depending on the Symbolic Equation $\theta^n = 1$". In: *The London, Edinburgh, and Dublin Philosophical Magazine and Journal of Science* 7.42 (1854), pp. 40–47. DOI: 10.1080/14786445408647421. URL: https://doi.org/10.1080/14786445408647421.

[12] Nathanael Chwojko-Srawley. *Everything You Need To Know About Abelian Varieties*. 1st ed. 2026. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA_abelian_varieties.pdf.

[13] Nathanael Chwojko-Srawley. *Everything You Need to Know about Algebraic Geometry*. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA_algGeo.pdf.

[14] Nathanael Chwojko-Srawley. *Everything You Need To Know About Algebraic K-Theory*. 1st ed.

[15] Nathanael Chwojko-Srawley. *Everything You Need To Know About Algebraic Number Theory*. Vol. 1. URL: https://nathanaelsrawley.com/pdf-viewer?src=.%2F.%2Fassets%2Fpdfs%2Fbooks%2FEYNTKA-algebraic-number-theory.pdf&name=Algebraic%20Number%20Theory&source=books.

[16] Nathanael Chwojko-Srawley. *Everything You Need To Know About Analytic Number Theory*. URL: https://nathanaelsrawley.com/pdf-viewer?src=.%2F.%2Fassets%2Fpdfs%2Fbooks%2FEYNTKA-analytic-number-theory.pdf&name=Analytic%20Number%20Theory&source=books.

[17] Nathanael Chwojko-Srawley. *Everything You Need To Know About C*-Algebras and K-Theory*. 1st ed.

[18] Nathanael Chwojko-Srawley. *Everything You Need To Know About Calculus on Manifolds*. Bootstrapped 2026-07-29 to calculus-on-manifolds/. Tensors and alternating forms, differential forms on Euclidean n-space, chains, the generalized Stokes theorem. Deliberately NOT titled "Analysis on Manifolds": NateManifoldAnalysis is reserved for the NateRiemannianGeometry Part II spin-out. 2026.

[19] Nathanael Chwojko-Srawley. *Everything You Need To Know About Category Theory*.

[20] Nathanael Chwojko-Srawley. *Everything You Need To Know About Commutative Algebra*.

[21] Nathanael Chwojko-Srawley. *Everything You Need To Know About Core Algebra*. 1st ed. 2025. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA_algebra.pdf.

[22] Nathanael Chwojko-Srawley. *Everything You Need To Know About Core Representation Theory*. 1st ed. 2025. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA_core_representation_theory.pdf.

[23] Nathanael Chwojko-Srawley. *Everything You Need To Know About Elementary Analysis*. 2024. URL: https://nathanaelsrawley.com/assets/pdfs/books/EYNTKA-elementary-analysis.pdf.

[24] Nathanael Chwojko-Srawley. *Everything You Need To Know About Elementary Analysis II*. 2026. URL: https://nathanaelsrawley.com/assets/pdfs/books/EYNTKA-metric-function-spaces.pdf.

[25] Nathanael Chwojko-Srawley. *Everything You Need To Know About Elliptic Curves*. 1st ed. 2025. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA_elliptic_curves.pdf.

[26] Nathanael Chwojko-Srawley. *Everything You Need To Know About Galois Cohomology*. EYNTKA. 2025. URL: https://nathanaelsrawley.com/assets/pdfs/books/EYNTKA_galois_cohomology.pdf.

[27] Nathanael Chwojko-Srawley. *Everything You Need To Know About Higher Category Theory*. In preparation.

[28] Nathanael Chwojko-Srawley. *Everything You Need To Know About Hodge Theory*. 1st ed. 2026. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA_hodge_theory.pdf.

[29] Nathanael Chwojko-Srawley. *Everything You Need To Know About Homological Algebra*. 1st ed. 2025. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA_homological_algebra.pdf.

[30] Nathanael Chwojko-Srawley. *Everything You Need to Know about Intersection Theory*. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA-intersection-theory.pdf.

[31] Nathanael Chwojko-Srawley. *Everything You Need To Know About Linear Algebra*. 1st ed. 2026.

[32] Nathanael Chwojko-Srawley. *Everything You Need To Know About Linear Elliptic and Parabolic PDE*. 1st ed. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA_linear_pde.pdf.

[33] Nathanael Chwojko-Srawley. *Everything You Need To Know About Local Field Theory*. URL: https://nathanaelsrawley.com/pdf-viewer?src=.%2F.%2Fassets%2Fpdfs%2Fbooks%2FEYNTKA-local-field-theory.pdf&name=Local%20Field%20Theory&source=books.

[34] Nathanael Chwojko-Srawley. *Everything You Need To Know About Local Langlands in GL2*. URL: https://nathanaelsrawley.com/pdf-viewer?src=.%2F.%2Fassets%2Fpdfs%2Fbooks%2FEYNTKA-langlands-gl2.pdf&name=Langlands%20for%20GL2(F)&source=books.

[35] Nathanael Chwojko-Srawley. *Everything You Need To Know About Logic*.

[36] Nathanael Chwojko-Srawley. *Everything You Need To Know About Modular Representation Theory*. 1st ed.

[37] Nathanael Chwojko-Srawley. *Everything You Need to Know about Moduli, Deformation Theory, and Stacks*. 1 vols. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA-moduli-stacks.pdf.

[38] Nathanael Chwojko-Srawley. *Everything You Need To Know About Perverse Sheaves and D-modules*. In preparation.

[39] Nathanael Chwojko-Srawley. *Everything You Need To Know About Topology*.

[40] Nathanael Chwojko-Srawley. *Everything You Need To Know About Toric Geometry*.

[41] Nathanael Chwojko-Srawley. *Everyting You Need To Know About Geometric Representation-Theory*.

[42] Nathanael Chwojko-Srawley. *EYNTKA Classical Algebraic Geometry*.

[43] Nathanael Chwojko-Srawley. *Preliminary Chapter*. 2023. URL: /Users/nathanaelchwojko-srawkey/website-nate/nate-website/src/assets/latex/notes/preliminary_chapter.

[44] P. M. Cohn. "Bezout Rings and Their Subrings". In: *Mathematical Proceedings of the Cambridge Philosophical Society* 64.2 (Apr. 1968), pp. 251–264. DOI: 10.1017/s0305004100042791. URL: https://doi.org/10.1017/s0305004100042791.

[45] Paul M. Cohn. "On the Structure of the GL_2 of a Ring". In: *Publications Mathématiques de l'IHÉS* 30 (Dec. 7, 1966), pp. 5–53. DOI: 10.1007/bf02684355. URL: https://doi.org/10.1007/bf02684355.

[46] Charles W. Curtis and Irving Reiner. *Representation Theory of Finite Groups and Associative Algebras*. Pure and Applied Mathematics 11. New York: Interscience Publishers, 1962.

[47] Cornelia Druţu and Michael Kapovich. *Geometric Group Theory*. Providence, Rhode Island: American Mathematical Society, Mar. 28, 2018. ISBN: 978-1-4704-4164-7. DOI: 10.1090/coll/063. URL: https://doi.org/10.1090/coll/063.

[48] David S. Dummit and Richard M. Foote. *Abstract Algebra*. 3rd. Wiley, 2004. ISBN: 978-0-471-43334-7.

[49] Walther Dyck. "Gruppentheoretische Studien". In: *Mathematische Annalen* 20.1 (Mar. 1882), pp. 1–44. DOI: 10.1007/bf01443322. URL: https://doi.org/10.1007/bf01443322.

[50] Walter Feit and John Thompson. "Solvability of Groups of Odd Order". In: *Pacific Journal of Mathematics* 13.3 (Sept. 1, 1963), pp. 775–1029. DOI: 10.2140/pjm.1963.13.775. URL: https://doi.org/10.2140/pjm.1963.13.775.

[51] Gerald B. Folland. *Real Analysis: Modern Techniques and Their Applications*. 2nd ed. Wiley, 1999. ISBN: 978-0-471-31716-6.

[52] László Fuchs. *Abelian Groups*. Cham: Springer International Publishing, 2015. ISBN: 978-3-319-19421-9. DOI: 10.1007/978-3-319-19422-6. URL: https://doi.org/10.1007/978-3-319-19422-6.

[53] Sergei I. Gelfand and Yuri I. Manin. *Methods of Homological Algebra*. 2nd ed. Springer Monographs in Mathematics. Springer, 2003. ISBN: 978-3-540-43583-9.

[54] Anne Grams. "Atomic Rings and the Ascending Chain Condition for Principal Ideals". In: *Mathematical Proceedings of the Cambridge Philosophical Society* 75.3 (May 1974), pp. 321–329. DOI: 10.1017/s0305004100048532. URL: https://doi.org/10.1017/s0305004100048532.

[55] Jeremy Gray. *A History of Abstract Algebra*. Springer Undergraduate Mathematics Series. Cham: Springer International Publishing, 2018. ISBN: 978-3-319-94772-3. DOI: 10.1007/978-3-319-94773-0. URL: https://doi.org/10.1007/978-3-319-94773-0.

[56] Phillip Griffiths and Joseph Harris. *Principles of Algebraic Geometry*. 1st ed. John Wiley & Sons, Ltd, 1978. 824 pp. ISBN: 978-0-471-05059-9. DOI: 10.1002/9781118032527. URL: https://onlinelibrary.wiley.com/doi/book/10.1002/9781118032527.

[57] Jack Hall. *GAGA Theorems*. May 17, 2022. DOI: 10.48550/arXiv.1804.01976. arXiv: 1804.01976 [math]. URL: http://arxiv.org/abs/1804.01976 (visited on 05/27/2025). Pre-published.

[58] Robin Hartshorne. *Algebraic Geometry*. Graduate Texts in Mathematics 52. New York: Springer-Verlag, 1977, p. 496. ISBN: 0-387-90244-9.

[59] Allen Hatcher. *Algebraic Topology*. URL: https://pi.math.cornell.edu/~hatcher/AT/AT.pdf.

[60] Allen Hatcher. *Vector Bundles & K-Theory Book*. 2.0. 2017. URL: https://pi.math.cornell.edu/~hatcher/VBKT/VBpage.html.

[61] Pavol Hell and Jaroslav Nešetřil. *Graphs and Homomorphisms*. Oxford University Press, July 22, 2004. ISBN: 978-0-19-852817-3. DOI: 10.1093/acprof:oso/9780198528173.001.0001. URL: https://doi.org/10.1093/acprof:oso/9780198528173.001.0001.

[62] Edwin Hewitt and Karl Stromberg. *Real and Abstract Analysis*. Vol. 25. Graduate Texts in Mathematics. New York: Springer-Verlag, 1965. ISBN: 0-387-90138-8.

[63] James E. Humphreys. *Introduction to Lie Algebras and Representation Theory*. Vol. 9. Graduate Texts in Mathematics. Springer-Verlag, 1972.

[64] James E. Humphreys. *Introduction to Lie Algebras and Representation Theory*. Vol. 9. Graduate Texts in Mathematics. Springer-Verlag, 1972.

[65] Milne J.S. *Fields and Galois Theory*. Ann Arbor, MI: Kea Books, 2022.

[66] Camille Jordan. *Traité des substitutions et des équations algébriques*. Paris: Gauthier-Villars, 1870.

[67] Irving Kaplansky. *Infinite Abelian Groups*. Ann Arbor: University of Michigan Press, 1954.

[68] Alexander Kirillov Jr. *Quiver Representations and Quiver Varieties*. Vol. 174. Graduate Studies in Mathematics. American Mathematical Society, 2016. ISBN: 9781470423070.

[69] T. Y. Lam. *A First Course in Noncommutative Rings*. New York, NY: Springer New York, 2001. ISBN: 978-0-387-95325-0. DOI: 10.1007/978-1-4419-8616-0. URL: https://doi.org/10.1007/978-1-4419-8616-0.

[70] Serge Lang. *Algebra*. 3rd. Springer, Jan. 8, 2002. ISBN: 978-0-387-95385-4.

[71] Christopher C. Leary and Lars Kristiansen. *A Friendly Introduction to Mathematical Logic*. 2nd ed. Geneseo, NY: Milne Library, SUNY Geneseo, 2015. ISBN: 978-1-942341-07-9.

[72] Clara Löh. *Geometric Group Theory*. Cham: Springer International Publishing, 2017. ISBN: 978-3-319-72253-5. DOI: 10.1007/978-3-319-72254-2. URL: https://doi.org/10.1007/978-3-319-72254-2.

[73] Daniel A. Marcus. *Number Fields*. 2nd ed. Universitext. Cham: Springer, 2018. ISBN: 978-3-319-90232-6.

[74] Hideyuki Matsumura. *Commutative Algebra*. 2nd ed. URL: https://aareyanmanzoor.github.io/assets/matsumura-CA.pdf.

[75] James R. Munkres. *Topology*. Prentice Hall, Incorporated, 2000. 568 pp. ISBN: 978-0-13-181629-9.

[76] Nathanael Chwojko-Srawley. *Everything You Need To Know About Algebraic Topology*. 1st ed. 126 pp. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA_algebraic_topology.pdf.

[77] Nathanael Chwojko-Srawley. *Everything You Need To Know About Class Field Theory*. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA_class_field_theory.pdf.

[78] Nathanael Chwojko-Srawley. *Everything You Need To Know About Complex Analysis*. 1st ed. 233 pp. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA_complex_analysis.pdf.

[79] Nathanael Chwojko-Srawley. *Everything You Need To Know About Differential Topology*. 1st ed. 233 pp. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA_differential_geometry.pdf.

[80] Nathanael Chwojko-Srawley. *Everything You Need To Know About Functional Analysis*. 1st ed. 62 pp. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA_functional_analysis.pdf.

[81] Nathanael Chwojko-Srawley. *Everything You Need to Know about K-theory*. Vol. 1. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA_K-Theory.pdf.

[82] Nathanael Chwojko-Srawley. *Everything You Need To Know About Real Analysis*. 2026. URL: https://nathanaelsrawley.com/assets/pdfs/books/EYNTKA-real-analysis.pdf.

[83] Jürgen Neukirch. *Algebraic Number Theory*. Grundlehren der mathematischen Wissenschaften 322. Translated from the 1992 German original by Norbert Schappacher. Berlin: Springer-Verlag, 1999. ISBN: 978-3-540-65399-8.

[84] Emmy Noether. "Idealtheorie in Ringbereichen". In: *Mathematische Annalen* 83.1–2 (1921), pp. 24–66. DOI: 10.1007/bf01464225. URL: https://doi.org/10.1007/bf01464225.

[85] Nathanael Chwojko-Srawley. *Everything You Need To Know About Harmonic Analysis*. 1st ed. Vol. 1. URL: https://nathanaelsrawley.com/assets/pdfs/notes/EYNTKA_harmonic_analysis.pdf.

[86] Derek John Scott Robinson. *A Course in the Theory of Groups*. 2nd ed. Graduate Texts in Mathematics 80. New York: Springer-Verlag, 1996. ISBN: 978-0-387-94461-6.

[87] Pierre Samuel. "On unique factorization domains". In: *Illinois Journal of Mathematics* 5.1 (1961), pp. 1–17.

[88] Richard D. Schafer. *An Introduction to Nonassociative Algebras*. Dover Publications, 1996. ISBN: 978-0-486-68813-8.

[89] Otto Schreier and Bartel Leendert van der Waerden. "Die Automorphismen der projektiven Gruppen". In: *Abhandlungen aus dem Mathematischen Seminar der Universität Hamburg* 6 (1928), pp. 303–322.

[90] Jean-Pierre Serre. *Linear Representations of Finite Groups*. Graduate Texts in Mathematics 42. Translated from the second French edition by Leonard L. Scott. New York: Springer-Verlag, 1977. ISBN: 978-0-387-90190-9.

[91] Igor R Shafarevich. *Basic Algebraic Geometry 1*. 3rd ed. Springer Berlin, Heidelberg. ISBN: 978-3-642-37955-0. URL: https://doi.org/10.1007/978-3-642-37956-7.

[92] Joseph H. Silverman. *Advanced Topics in the Arithmetic of Elliptic Curves*. Graduate Texts in Mathematics. New York, NY: Springer, 1994. ISBN: 978-0-387-94328-2 978-1-4612-0851-8. DOI: 10.1007/978-1-4612-0851-8. URL: http://link.springer.com/10.1007/978-1-4612-0851-8 (visited on 07/16/2025).

[93] Joseph H. Silverman. *The Arithmetic of Elliptic Curves*. Springer Science & Business Media, Apr. 20, 2009. 525 pp. ISBN: 978-0-387-09494-6. Google Books: Z90CA_EUCCkC.

[94] Jonathan D. H. Smith. *An Introduction to Quasigroups and Their Representations*. Chapman and Hall/CRC, Nov. 15, 2006. ISBN: 978-0-429-13798-3. DOI: 10.1201/9781420010633. URL: https://doi.org/10.1201/9781420010633.

[95] Nicolas Spaltenstein. "Resolutions of Unbounded Complexes". In: *Compositio Mathematica* 65.2 (1988), pp. 121–154.

[96] *Stacks Project - Commutative Algebra*. URL: https://stacks.math.columbia.edu/tag/00AO.

[97] Nathanael Chwojko-Srawley. *Everything You Need To Know About Lie Groups*.

[98] The Stacks project authors. *The Stacks Project*. 2026. URL: https://stacks.math.columbia.edu.

[99] Ravi Vakil. *The Rising Sea*. Princeton University Press, Oct. 21, 2025. ISBN: 978-0-691-26866-8. URL: https://press.princeton.edu/books/hardcover/9780691268668/the-rising-sea (visited on 07/26/2025).

[100] Peter Webb. *A Course in Finite Group Representation Theory*. 1st ed. Cambridge Studies in Advanced Mathematics. Cambridge University Press, 2016. ISBN: 9781107162396. DOI: 10.1017/cbo9781316677216.

[101] Charles A. Weibel. *An Introduction to Homological Algebra*. 1st ed. Cambridge University Press, 1994. ISBN: 978-0-521-43500-0. DOI: 10.1017/cbo9781139644136. URL: https://doi.org/10.1017/cbo9781139644136.

[102] William Fulton. *Algebraic Curves. An Introduction to Algebraic Geometry*. URL: https://dept.math.lsa.umich.edu/~wfulton/CurveBook.pdf.

What Next?

Congratulations on reaching the end of the book[1]! Having parsed through the material of the book, the reader must be on the edge of their seat wondering what comes next! From my current understanding, the ultimate goal is to understand better the properties of numbers or the properties of geometric objects that arise out of polynomials (or more generally out of commutative or non-commutative rings). This results in classification results, tools to better understand these results, new ways of solving equations, and so forth. The number of branching points is vast; this book shall address what is currently some common general starting points, given the reader is in the 21st century.

The reader should be aware that at this stage, it is important to gain some experience in many other fields of mathematics such as algebraic topology [76], differential geometry [79], Lie Groups [97], real analysis [85](particularly Fourier analysis), PDEs [32] (for at least the idea of elliptic operators and harmonic PDEs), and complex analysis [78]. All these fields interconnect to various extents in the study of number theory, representation theory, and algebraic geometry.

It must be pointed out that the topics covered here are *not* a comprehensive list of areas of research, simply large ones. Other areas that are not covered in detail here that have active research include, but are not limited to, the model theory of algebraically and differentially closed fields, probabilistic linear optimization, mathematics of AI (which can be thought of as a continuation of linear algebra and functional analysis), higher order category theory, P vs. NP as an Invariance Theory problem, and so forth.

Algebraic Geometry

A lot of focus is within the domain of *algebraic geometry*. The reader has the background material to start reading the next EYTNKA textbook *EYNTKA Algebraic Geometry* ([13]), or read classical texts such as *Hartshorne's Algebraic geometry* ([58]) or *Vakil's The Rising Sea* ([99]). The starting point of modern algebraic geometry is the *affine scheme* (developed in *Algebraic Geometry* [13]) which generalizes varieties by defining the geometric counter-part to number rings, rings with nilpotents or

[1] or welcome curious reader to how the book ends!

zero-divisors, rings that are not finitely generated, and overall any commutative ring. These shall be the "model spaces" that are glued together to create *schemes*, where "glued together" is geometrically understood as forming equivalence classes between the points that are being glued and is algebraically understood as adding compatibility relations between functions (essentially, think of the example of projective space where $f \in \text{Hom}(U_1, R), g \in \text{Hom}(U_2, R)$ such that $f(z) = g(1/z)$ on $U_1 \cap U_2$). A lot of the build-up in modern algebraic geometry is translating the concepts of differential geometry over $\mathbb{R}$ or $\mathbb{C}$ (ex. smoothness, dimensions, irreducibility, compactness, Hausdorffness, Poincaré duality, monodromy, Riemann-Roch) into the non-analytic setting of schemes. This translation abstracts many of the notions that will require a good deal of build-up, but the reward is a unified language to deal with number theory and varieties which have many of the geometric intuitions one would expect, as well as novel geometric intuitions unique to schemes with not analytic counter-part. A lot of similarities shall be shared between differential geometry and scheme theory, but important differences shall also emerge (ex. points containing other points, existence of distinct points that are arbitrarily closed to each other, functions that are not determined by their value at every point).

Schemes are the starting point for the study of many different modern fields, but they can be studied in and of themselves. For example to find classification of different types of schemes; this research often involves the use of *moduli spaces* and the theory of *stacks*.

Another very important problem in Algebraic Geometry is the *Hodge Conjecture*, which roughly says that homological information about a smooth *projective* complex variety X can be given by nice subvarieties of X. In particular, without defining any of our terms, it asks which *rational* cohomology classes in $H^{2k}(X, \mathbb{Q}) \cap H^{k,k}(X)$ are combinations of the classes of closed subvarieties Z of X. Both restrictions carry weight: without rationality the statement fails at once, and the analogous statement for compact Kähler manifolds is false as well, by a counterexample of Voisin. The projective case is where the conjecture lives, and there the analytic and algebraic pictures agree by GAGA [57]. Solving the conjecture or finding a counter-example would be rewarded the reader $1 million by the Clay Institute. The reader interested in the Hodge Conjecture wanting to continue the EYTNKA series can read *K-theory* for an introduction to vector/fiber-bundles and their algebraic generalizations [81], *Algebraic Topology* for the cohomology background [76], *Algebraic Geometry* for the algebraic background [13], *Differential Topology* for the Kähler manifold background [79], and [28] for putting this all together.

Elliptic Curves

The advantage of scheme theory is in full effect when studying curves (Noetherian integral separated 1-dimensional schemes of finite type over k). The study of curves splits according to the genus g, the invariant that Riemann-Roch ties to the dimensions of spaces of functions with prescribed poles (see [78] or [13]). Curves of genus 1 carrying a marked rational point are called *elliptic curves*, and Riemann-Roch embeds each one as a non-singular plane cubic, so studying them is studying non-singular degree 3 equations. When in char $\neq 2, 3$ we can algebraically say that the study of elliptic curves is the study of equation $y^2 = x^3 + ax + b$. Finding all rational solutions to such polynomials is still an open problem; the *Birch and Swinnerton-Dyer Conjecture* would, if proven, explain how many solutions there exists, and the person(s) who succeeds to prove it would win $1 million from the Clay Institute of Mathematics[2]. Due to scheme theory there are natural ways of understanding "bad reductions" (think of ramified primes), of defining a covering space using galois theory (like in homotopy theory), and keeping track of when curves intersect non-transversally (with

[2]It is one of the Millennium problems set at the beginning of the 21st century

multiplicity higher than 1).

The reader interested can start on the EYTNKA textbook *Elliptic Curves* ([25]) or look at *Silvermen's Arithmetic of Elliptic Curves* ([93]).

Number Theory and Arithmetic Geometry

Scheme theory over number fields or number rings is called *Arithmetic Geometry*. A huge amount of progress in modern theory was made by using tools in arithmetic geometry, for example the proof of Fermat's Last Theorem (that for no natural number $n \geq 3$ does $x^n + y^n = z^n$ have a solution in nonzero integers) was proved through the lens of Arithmetic Geometry and analytic number theory. Much of modern number theory builds directly on the algebraic foundations presented in this book.

A major area of research is the *Langlands program* which aims to generalize Artin's reciprocity (see *Class Field Theory*, [77]) which can be thought of the 1-dimensional case of Langland's reciprocity. The 2-dimensional case strongly involved elliptic curves and the related modular forms and automorphic forms. An introduction to the required background covering these topics includes [25], [13], and [92].

With the advent of complex analysis, many problems in number theory can be studied using certain meromorphic functions. Of central interest is the *Riemann-Zeta function*

$$\zeta(s) = \sum_{n=1}^{\infty} \frac{1}{n^s} = \prod_{p \text{ prime}} \frac{1}{1 - p^{-s}}$$

which can be analytically extended to $\mathbb{C} \setminus \{1\}$ and captures an incredible amount of information about the distribution of primes (and by the proven *Weil Conjectures* any smooth projective variety over a finite field has an associated zeta function capturing its arithmetic properties). The *Riemann Hypothesis*, one of the Millennium problems, states that all the [non-trivial][3] roots of $\zeta(s)$ lie on the line $L = \{z \in \mathbb{C} \mid \text{Re}(z) = 1/2\}$. By some application of Fourier analysis, this would drastically improve our understand of how many primes $p \leq n$ there exists for any $n \in \mathbb{N}$, and would resolve many open problems. Proving that all [nontrivial] zeros are on L or that there is at least one [nontrivial] zero that is not on L would give the person(s) who proved it $1 million by the Clay Institute.

Geometric Group Theory

part I mainly focused on finite groups. Infinite groups are much harder to grasp, however there are many infinite groups that naturally show up in geometric settings and have a metric that can be imposed on them. Studying these groups falls under *Geometric group theory* which views infinite groups themselves as geometric objects. By equipping a group with a metric, one can study its large-scale geometry to deduce its algebraic properties. This approach has led to the resolution of major conjectures in topology, Agol's proof of the virtual Haken conjecture among them. (Thurston's Geometrization Conjecture does imply the *Poincaré Conjecture*, another Millennium problem, but Perelman proved it by Ricci flow rather than by group-theoretic means.)

[3] There are roots that are given by the Gamma function which are considered to be related to the prime at infinity, and is not important for the usual, finite, prime

Derived Algebraic Geometry and Higher Algebra

Schemes are incredibly powerful, but are not adept with "singular" spaces or when taking "non-regular" quotients; categorically they do not behave well under limits and colimits. *Derived geometry* is a redevelopment of commutative algebra inspired by abstract topology. It replaces rings with derived objects that retain homological information, allowing for a more robust theory of intersections and moduli spaces that works in greater generality. This field often draws on *higher category theory* to create a unified language for geometry.

Motivic and Chromatic Homotopy Theory

Algebraic topology uses algebraic invariants, such as homology groups, to classify and distinguish topological spaces. The algebraic tools themselves have become the focus of intense study. *Chromatic homotopy theory* seeks to organize how shapes can be mapped into one another (homotopy) by filtering it through algebraic data coming from the theory of formal groups. *Motivic homotopy theory* builds a direct bridge, or "motive," between algebraic geometry and topology. The ultimate goal is a structural understanding of shape itself, with the calculation of the *stable homotopy groups of spheres* remaining one of the field's major goals.

Anabelian Geometry

Anabelian geometry is asking if we can recover an arithmetic variety X given information about the (étale) fundamental group of X. While Motivic Homotopy Theory seeks to build a dictionary of algebraic invariants to describe a space, anabelian geometry focuses on the first étale homotopy group, $\pi_1^{\text{ét}}$, and posits that for a special class of "hyperbolic" varieties, $\pi_1^{\text{ét}}$ contains all the necessary information to recover the variety.

The central algebraic invariant in this field is the *étale fundamental group*, denoted $\pi_1^{\text{ét}}(X)$. Its connection to the homotopy $\pi^{\mathbf{Top}}$ group comes from how the universal cover $E \to X$ and the intermediate covers have a galois correspondence to the subgroups of $\pi^{\mathbf{Top}}$. An example of a simple étale fundamental group is those for a field k, where $\pi_1^{\text{ét}}(\operatorname{Spec} k) = \operatorname{Gal}_k(k_s)$ where k_s is the maximal separable extension of k. More generally, for a variety X defined over a number field like $\mathbb{Q}$, its étale fundamental group is a profinite group that captures not only the topological shape of X (as seen over the complex numbers) but also the entirety of its arithmetic structure.

The "anabelian" hypothesis is the conjecture that this reconstruction is only possible when the group is sufficiently complex and far from being abelian.

- **Abelian Case (Fails):** For an object like an elliptic curve, whose fundamental group is abelian, this principle fails. Many different elliptic curves can have the same fundamental group, so the group does not uniquely determine the geometry.
- **Anabelian Case (Conjectured to Succeed):** For a "hyperbolic" variety, such as a curve of genus two or more, the étale fundamental group is a non-abelian group. The anabelian hypothesis posits that there is enough information to uniquely determine the original variety.

This makes anabelian geometry a subfield of arithmetic geometry in its goals, but leaning more towards the philosophy of geometric group theory: it seeks to understand geometry by studying the algebraic properties of an associated group. An unsolved problem (as of writing this book) is

the *Section Conjecture* which attempts to use the structure of $\pi_1^{\text{ét}}(X)$ to describe the set of rational points on X, offering a new (non-abelian) approach to solving Diophantine equations.

Thanks for reading!